



August 31, 2021 (revised September 3, 2021)

Alexis McKinnon
Solid Waste Specialist
Kitsap County Public Works
Solid Waste Division
614 Division Street, MS-27
Port Orchard, WA 98366

**Re: Second Quarter 2021 Environmental Monitoring Report
Hansville Landfill, Kitsap County, Washington
Project No. 160423-005-05.1**

Dear Alexis:

This quarterly report summarizes the results of environmental monitoring conducted at the Hansville Landfill (Site) during the second quarter of 2021, and was prepared by Aspect Consulting, LLC (Aspect) on behalf of Kitsap County Public Works Solid Waste Division (County) and Waste Management of Washington (WMW). Ongoing environmental monitoring at the Site supports the selected remedy of natural attenuation of groundwater with enhanced monitoring and institutional controls that was established under Amended Consent Decree No. 95-2-03005-1 (August 5, 2011).

The data sets presented in this letter report were collected in accordance with the Site Cleanup Action Plan (CAP; Ecology, 2011) and the “Compliance Monitoring Plan with Sampling & Analysis Plan and Quality Assurance Plan” (SCS, 2011; herein referred as Compliance Monitoring Plan), except where otherwise noted.

Conditions monitored at the Site during the second quarter of 2021 were consistent with historical trends showing improvements in protection of human health and the environment. This report is organized consistent with quarterly reporting topics listed in the Compliance Monitoring Plan (SCS, 2011), and includes:

- Site monitoring and maintenance activities, along with a discussion of any deviations from the CAP, or required tasks not otherwise documented in project plans
- Landfill gas monitoring results and gas collection system adjustments
- Determination of groundwater flow direction and gradient, including a groundwater surface elevation contour map
- Water quality sampling results, including tabulated field data and laboratory analyses

Also included are time-series plots and projected trends in groundwater concentrations for selected analytes at selected monitoring locations. Finally, this report discusses geochemical parameters as indicators of landfill effects on groundwater and surface water.

Site Activities – Second Quarter 2021

Site activities during the reporting period included environmental monitoring of landfill gas, groundwater, and surface water. Documentation of the quarterly activities is presented the following attachments:

- Attachment A presents landfill gas monitoring data.
- Attachment B presents groundwater elevations, a groundwater contour map, and groundwater and surface water quality analytical results.
- Attachment C presents summary statistics, time-series graphs, and graphs of projected groundwater concentrations for arsenic and vinyl chloride at selected monitoring wells.
- Attachment D presents supporting field records, laboratory data reports, and chain-of-custody documentation.

A chronology of on-Site monitoring activities performed during the second quarter 2021 is provided below:

- On April 21, 2021, Aspect completed groundwater and surface water sampling in accordance with the Compliance Monitoring Plan (SCS, 2011).
- On May 20, 2021, Aspect conducted monthly performance monitoring of the blower system and condensate management system.
- On June 17, 2021, Aspect conducted landfill gas monitoring in accordance with the Compliance Monitoring Plan (SCS, 2011) and inspected the blower system for proper operation. Aspect monitored landfill gas concentrations at the blower, extraction wells, and at compliance monitoring probes. Extraction well flow rates were adjusted to ensure capture of landfill gasses, as necessary. Maintenance activities included replacement of broken flow control valves and modification of the wellhead at TD-1 to prevent condensate blockage.

Collection of landfill gas samples is ongoing, and results of the air quality analysis will be presented in a separate document at the completion of the work, anticipated for later this year.

Deviations from the Compliance Monitoring Plan

There were no deviations from the Compliance Monitoring Plan (SCS, 2011) during the second quarter 2021 environmental monitoring.

Summary of Landfill Gas Conditions

The following sections provide a discussion of landfill gas monitoring and gas extraction system performance. The layout of the landfill gas extraction system is shown on Figure A-1.

Landfill Gas Monitoring

Aspect monitored landfill gas concentrations and system vacuum at the blower on April 21, May 20, and June 17, 2021. Aspect monitored landfill gas concentrations, vacuum, and flow at the extraction wells and compliance monitoring probes on June 17, 2021.

Landfill gas concentrations were measured with a calibrated GEM-5000 multi-gas meter. Landfill gas monitoring parameters collected for the compliance monitoring event are summarized in Table A-1, and listed below:

- Landfill gas composition measurements included methane (CH₄), carbon dioxide (CO₂), oxygen (O₂), and balance gas (Balance) concentrations.
- Collection system pressure measurements included the static pressure measured before and after any valve adjustments, reported as “initial” and “adjusted,” respectively.
- Collection system flow-rate measurements were obtained at all locations via orifice plates. The differential pressure and gas temperature were measured to calculate flow. Table A-1 presents flow rates measured after valve adjustments, reported as “adjusted.”

Landfill Gas System Performance

During the compliance monitoring event on June 17, 2021, observed conditions remained within the normal range. At the blower inlet, methane and carbon dioxide concentrations were approximately 3.9 percent by volume and 10.2 percent by volume, respectively. The oxygen concentration was approximately 8.5 percent by volume. The flow rate was approximately 74 standard cubic feet per minute (scfm) with a system vacuum of 5 inches water column.

Reduced vacuum was previously observed in the southeast portion of the wellfield during previous events. To better understand the cause, the vacuum was measured at the four lateral connections. Vacuum at the north and west laterals was approximately 4-inches water column compared to approximately 0.5-inches water column at the south and east laterals. Based on those measurements, there are likely blockages in the perimeter header. The western condensate sump was observed to be full, and service was requested to remove the condensate.

On June 17, 2021, the 2,000-gallon condensate storage tank inside the flare compound contained approximately 1,150 gallons of landfill gas condensate. The condensate sump pump was tested and found to be in good working order. The condensate storage tank was installed in December 2018 and has not been emptied. Condensate collection rates have ranged between 0 and 100 gallons per month.

Based on the consistent performance of the landfill gas collection system and in consultation with the County and WMW, landfill gas wellfield monitoring and tuning is conducted on a quarterly basis, during the third month of the quarter (March, June, September, December). Wellfield optimization will continue to focus on maximizing methane and carbon dioxide collection rates. Monthly site visits include monitoring the flare inlet and condensate management system and visual inspection of the wellfield. If flare inlet readings are outside the normal range, then troubleshooting measures may include wellfield monitoring and tuning. Any damaged wellheads or wellheads with sagging flexible hose will be repaired to maintain optimal landfill gas system performance.

Explosive Gas Control

Methane was not detected in any of the compliance gas probes during the compliance monitoring event on June 17, 2021. Locations of on-property compliance probes GP-1, GP-2S, GP-2M, GP-2D, GP-3, GP-4, GP-5, and GP-6 are shown on Figure A-1, and the location of off-property

compliance probe GP-7 is shown on Figure B-1. Carbon dioxide concentrations ranged from 0.8 to 2.7 percent by volume, reflecting natural conditions.

Summary of Groundwater and Surface Water Conditions

This section addresses groundwater and surface water conditions based on the monitoring event on April 21, 2021. Samples were collected from six groundwater monitoring wells and from four surface water monitoring locations (see Figure B-1) for laboratory analysis.

Groundwater Flow

Groundwater flow conditions during the second quarter of 2021 were consistent with those observed during previous monitoring events. Groundwater surface elevations were calculated using water levels measured April 21, 2021 (see Table B-1). Groundwater elevations ranged from 238.0 feet North American Vertical Datum of 1988 (NAVD88) in MW-12I to 266.2 feet NAVD88 in the upgradient, background monitoring well MW-5. The direction of groundwater flow at the Site was generally west across the landfill then shifts southwest, consistent with historical observations. Groundwater gradients ranged from 0.005 feet over feet (feet/feet) in the upgradient areas, to 0.011 feet/feet further downgradient, with the gradient steepening near the groundwater discharge area (Figure B-1).

Groundwater and Surface Water Quality

Groundwater quality results from the second quarter of 2021 are presented in Table B-2, including field parameters, conventional parameters, dissolved metals, and volatile organic compounds. During the reporting period, dissolved arsenic concentrations in groundwater were below the Site-specific cleanup level of 0.005 milligrams per liter (mg/L) at all monitoring wells except MW-14 (0.0135 mg/L) and MW-13D (0.00521 mg/L). Dissolved manganese concentrations were below the Site-specific cleanup level of 2.24 mg/L. Vinyl chloride concentrations in groundwater were below the Site-specific groundwater cleanup level of 0.025 micrograms per liter (µg/L) at all monitoring wells except MW-6 (0.065 µg/L), MW-12I (0.073 µg/L), and MW-14 (0.040 µg/L), consistent with historical results.

Surface water quality results from the second quarter 2021 are presented in Table B-3, including field parameters, conventional parameters, dissolved metals, and volatile organic compounds. During the reporting period, dissolved arsenic concentrations in surface water were below the Site-specific cleanup level of 0.005 mg/L at all monitoring locations. Dissolved manganese concentrations in surface water were below the Site-specific cleanup level of 2.24 mg/L. Vinyl chloride concentrations in surface water were not detected at a reporting limit below the Site-specific cleanup level of 0.025 µg/L.

Time-Series Plots and Projected Trends

Groundwater sampling results since 2007 are shown on time-series plots for dissolved arsenic (Figure C-1) and vinyl chloride (Figure C-2) at all compliance monitoring locations. Figure C-1 shows that dissolved arsenic concentrations in groundwater have been less than the cleanup level of 0.005 mg/L at MW-5 (background well), MW-6, MW-7, and MW-12I. Historically, dissolved arsenic concentrations at MW-13D were below the cleanup level and have gradually increased to

exceed the cleanup level, doing so for the first time in the second quarter 2020. This increasing trend is evaluated and discussed in the following section. Dissolved arsenic concentrations at MW-14 have historically exceeded the Site-specific cleanup level and have been decreasing steadily over time.

Figure C-2 shows vinyl chloride concentrations in groundwater have been less than the cleanup level of 0.025 µg/L at MW-5 (background well), MW-7, and MW-13D. The concentrations of vinyl chloride at MW-6, MW-12I, and MW-14 have historically exceeded the Site-specific cleanup level and have been decreasing over time. Variability in rates of decreasing concentrations is attributed to inconsistent landfill gas collection system performance, which is being corrected through well head maintenance.

Figure C-3 shows time-series plots of historical and 10-year projected groundwater concentrations for MW-6 (vinyl chloride), MW-12I (vinyl chloride), MW-14 (vinyl chloride and arsenic), and MW-13D (arsenic). The projected restoration time frames for vinyl chloride concentrations range from approximately 2 to 10 years. In the event that the slowly increasing trend for dissolved arsenic at MW-13D continues, concentrations may regularly exceed the cleanup level but will remain below the Puget Sound regional background of 8 µg/L (Ecology, 2016) for more than 10 years. The projected restoration time frame for arsenic in groundwater at MW-14 is more than 10 years. Maintaining landfill gas collection performance may achieve groundwater cleanup levels within a shorter time frame than shown on Figure C-3.

Statistical Evaluation of Groundwater Trends

Statistically significant decreasing trends in dissolved arsenic and/or vinyl chloride concentrations were identified at monitoring wells MW-6, MW-12I, and MW-14. We attribute the decreasing trends to the cleanup actions at the Site, and project concentrations will continue to decrease to Site-specific cleanup levels as described above and shown on Figure C-3.

A statistically significant increasing trend in dissolved arsenic concentrations was identified at monitoring well MW-13D. Dissolved arsenic concentrations exceeded the Site-specific cleanup levels during this monitoring period but remain below the regional natural background value provided by Ecology (Ecology, 2016; Ecology, 2021) as shown on Figure C-3. The statistical trend analysis for dissolved arsenic concentrations in MW-13D was first conducted as part of the 2019 Annual Environmental Monitoring Report (Aspect, 2020) and included an evaluation of potential sources. As previously noted, based on the data available, it is likely that arsenic concentrations since 2007 reflect natural variations or off-Site influences, as opposed to effects from the Hansville Landfill Site. Dissolved arsenic concentrations in MW-13D and other locations will continue to be closely monitored and evaluated.

Table C-1 provides results of statistical analysis for arsenic and vinyl chloride for monitoring wells MW-6, MW-12I, MW-13D, and MW-14. The trends are defined as “statistically significant” because the magnitude of the Mann-Kendall Test Value (Z) was greater than the Critical Value (which is based on the number of data points and alpha). A negative Sen’s slope indicates a

decreasing trend in concentrations, while a positive Sen's slope indicates an increasing trend.¹ These statistics confirm what is visually apparent on Figure C-3 showing historical groundwater concentrations.

The statistical analysis of groundwater data was performed in accordance with the Compliance Monitoring Plan (SCS, 2011) for historical data collected since January 23, 2007. The program Sanitas WQStat (ver. 9.0.34) was used to evaluate the Mann-Kendall Test and Sen's slope. Mann-Kendall testing was performed to assess whether there were statistically significant trends in groundwater concentrations using the two-tailed test ($\alpha = 0.05$). Mann-Kendall results are reported as an approximated normal distribution Test Value "Z" (where the number of data points was greater than 40). Sen's slope analysis was performed to identify the trend direction for statistically significant trends and reflects the median of the slopes of all pairs of historical data.

Geochemical Parameters

Geochemical parameters in groundwater and surface water serve as indicators of landfill effects and can distinguish leachate impacts from gas-to-groundwater impacts. As shown in Tables B-2 and B-3, geochemical parameters collected at the Site include field parameters (dissolved oxygen, pH, Redox [reduction-oxidation potential], specific conductivity, and temperature), alkalinity/carbonate/bicarbonate, chloride, nitrate/nitrite/ammonia, sulfate, and total organic carbon.

Based on low concentrations of geochemical parameters identified as leachate indicators (such as chloride, sulfate, alkalinity, and bicarbonate) across the Site, there appears to be little if any leachate effect on groundwater and surface water quality. However, the downgradient monitoring wells show lower dissolved oxygen concentrations than the upgradient well (MW-5), which is likely caused by landfill gas coming in contact with groundwater directly beneath the landfill. Increasing the rate of landfill gas collection may prevent geochemically-mediated effects on groundwater.

¹ Sen's slope values reflect the median of the slopes of historical data pairs, and were provided in units of $\mu\text{g/L}$ per day in reports by SCS through 2016. Starting in 2017, Sen's slope values are provided in units of $\mu\text{g/L}$ per year, to support interpretation. For comparison, Table C-1 provides Sen's slope values for both units.

References

- Aspect Consulting, LLC, 2020, 2019 Annual Environmental Monitoring Report, Hansville Landfill, Kitsap County, Washington, February 28, 2020.
- SCS Engineers (SCS), 2011, Compliance Monitoring Plan with Sampling & Analysis Plan and Quality Assurance Plan – Remedial Action at the Hansville Landfill, September 15, 2011.
- Washington State Department of Ecology (Ecology), 2011, Cleanup Action Plan Hansville Landfill, Kitsap County, Washington, Ecology Facility Site Identification Number: 2605, June 2011.
- Washington State Department of Ecology (Ecology), 2016, Natural Background Groundwater Arsenic Concentrations in Washington State, Ecology Publication No. 14-09-044, March 2016.
- Washington State Department of Ecology (Ecology), 2021, Natural Background Groundwater Arsenic Concentrations in Washington State, Ecology Publication No. 14-09-044, Draft for Public Comment, July 2021.


Limitations

Work for this project was performed for Kitsap County Public Works (Client), and this letter was prepared in accordance with generally accepted professional practices for the nature and conditions of work completed in the same or similar localities, at the time the work was performed. This letter does not represent a legal opinion. No other warranty, expressed or implied, is made.

All reports prepared by Aspect Consulting for the Client apply only to the services described in the Agreement(s) with the Client. Any use or reuse by any party other than the Client is at the sole risk of that party, and without liability to Aspect Consulting. Aspect Consulting's original files/reports shall govern in the event of any dispute regarding the content of electronic documents furnished to others.

Sincerely,

Aspect consulting, LLC



9/3/2021

Peter S. Bannister, PE
Associate Engineer
pbannister@aspectconsulting.com

Meilani Lanier-Kamaha'o, LG
Project Geologist
mlkamahao@aspectconsulting.com

Attachments: A – Landfill Gas Data
 B – Water Quality Results
 C – Groundwater Statistics and Time-Series Plots
 D – Field Forms and Laboratory Reports

cc: Phil Perley, Waste Management of Washington
 Patrick Hamel, Kitsap Public Health District
 Cris Matthews, Washington State Department of Ecology
 Sam Phillips, Port Gamble S'Klallam Tribe

V:\160423 Kitsap County Hansville Landfill\Deliverables\2021 Reports\2021Q2\Q2 2021 Hansville Monitoring Report_20210903.docx

ATTACHMENT A

Landfill Gas Data

Table A-1. Landfill Gas Data, Second Quarter, 2021

Project No. 160423, Hansville Landfill, Hansville, WA

Location	Device ID	Date/Time	Methane CH4 (% by vol)	Carbon Dioxide CO2 (% by vol)	Oxygen O2 (% by vol)	Balance Bal (% by vol)	Static Pressure (inches H2O)		Gas Temperature (degrees F)		Flow Rate (SCFM)	
							Initial	Adjusted	Initial	Adjusted	Initial	Adjusted
Blower Inlet	HANSBLIN	6/17/21 11:19	3.9	10.2	8.5	77.4	-5.08	-5.08	65.2	65.2	72.6	74.5
Blower Outlet	HANSBLOT	6/17/21 11:30	3.7	9.9	8.8	77.6	N/A	N/A	N/A	N/A	N/A	N/A
Extraction Well 001	HANSR001	6/17/21 14:23	0	0.1	20.1	79.8	-0.27	-0.27	82.2	82.1	0.5	0.5
Extraction Well 002	HANSR002	6/17/21 14:18	2.6	12.6	4.5	80.3	N/A	N/A	N/A	N/A	N/A	N/A
Extraction Well 003	HANSR003	6/17/21 14:10	12.6	12.8	0	74.6	-1.15	-1.15	66	65.9	3.5	3.5
Extraction Well 004	HANSR004	6/17/21 13:20	5	17	0.1	77.9	-1.51	-1.51	74.8	74.7	2.7	2.7
Extraction Well 005	HANSR005	6/17/21 13:14	9.5	18.5	0.2	71.8	-0.92	-0.92	74.7	74.9	2.9	2.9
Extraction Well 006	HANSR006	6/17/21 13:02	2.7	15.8	2.9	78.6	-1.38	-1.38	78.4	78.4	3.4	3.4
Extraction Well 007	HANSR007	6/17/21 12:55	1	12.4	4.6	82	-0.85	-0.85	72.4	72.4	2.8	2.8
Extraction Well 008	HANSR008	6/17/21 15:01	10.9	17	0	72.1	-0.43	-0.43	75.7	75.6	0.6	0.4
Extraction Well 009	HANSR009	6/17/21 14:50	3.3	14.5	0.7	81.5	N/A	N/A	N/A	N/A	N/A	N/A
Extraction Well 010	HANSR010	6/17/21 14:44	13	11.5	1	74.5	-0.39	-0.39	99.1	99.4	0.4	0.4
Extraction Well 011	HANSR011	6/17/21 14:37	0	0.1	21	78.9	-0.32	-0.32	81.8	81.9	0.4	0.4
Extraction Well 012	HANSR012	6/17/21 12:20	0	0.1	20.2	79.7	-0.48	-0.48	71.8	72	0.1	0.1
Extraction Well 013	HANSR013	6/17/21 12:43	6.3	13.4	0.9	79.4	N/A	N/A	N/A	N/A	N/A	N/A
Trench Collector TD-1	HANSTD01	6/17/21 15:13	1.3	19.8	0.4	78.5	-0.08	-0.08	75.9	76.1	14	14.4
Trench Collector TR-1	HANSTR01	6/17/21 13:08	6.3	15.2	1.6	76.9	-0.53	-0.53	70.8	71.1	3.2	3.2
Trench Collector TR-2	HANSTR02	6/17/21 14:56	8.4	16.9	0.1	74.6	N/A	N/A	N/A	N/A	N/A	N/A
Trench Collector TR-3	HANSTR03	6/17/21 14:28	0	0.1	20.1	79.8	N/A	N/A	N/A	N/A	N/A	N/A
Trench Collector TR-4	HANSTR04	6/17/21 13:49	7.8	18.1	0	74.1	-0.53	-0.53	75.5	75.6	3.1	3.1
Trench Collector TR-5	HANSTR05	6/17/21 12:26	0	0.1	20.3	79.6	N/A	N/A	N/A	N/A	N/A	N/A
Trench Collector TR-6	HANSTR06	6/17/21 11:54	0	0.1	20.2	79.7	N/A	N/A	N/A	N/A	N/A	N/A
Trench Collector TR-7	HANSTR07	6/17/21 13:55	22.1	16.7	0.1	61.1	-0.55	-0.55	71.6	71.6	4	4
Gas Probe 1	HANSGP01	6/17/21 14:10	0	1	19.8	79.2	0	0	N/A	N/A	N/A	N/A
Gas Probe 2 Shallow	HANSGP2S	6/17/21 13:50	0	0.8	19.9	79.3	0	0	N/A	N/A	N/A	N/A
Gas Probe 2 Middle	HANSGP2M	6/17/21 13:55	0	1.1	19.3	79.6	0.01	0.01	N/A	N/A	N/A	N/A
Gas Probe 2 Deep	HANSGP2D	6/17/21 14:00	0	1.4	18	80.6	0.02	0.02	N/A	N/A	N/A	N/A
Gas Probe 3	HANSGP03	6/17/21 12:55	0	1	19.8	79.2	0.01	0.01	N/A	N/A	N/A	N/A
Gas Probe 4	HANSGP04	6/17/21 13:20	0	1.1	19.5	79.4	0.02	0.02	N/A	N/A	N/A	N/A
Gas Probe 5	HANSGP05	6/17/21 12:40	0	0.9	19.7	79.4	0	0	N/A	N/A	N/A	N/A
Gas Probe 6	HANSGP06	6/17/21 12:20	0	3	18.4	78.6	0.01	0.01	N/A	N/A	N/A	N/A
Gas Probe 7	HANSGP07	6/17/21 1:40	0	2.7	18	79.3	0	0	N/A	N/A	N/A	N/A

Notes


Flow rates measured using orifice plates (where installed).

N/A = indicates parameter not measured.

inches H2O = inches water column

degrees F = degrees Fahrenheit

(--) = indicates location was not monitored and has been decommissioned due to little to no landfill gas collection



Note:
* Sump, S-1, was disconnected from the condensate management system and decommissioned in 2019. Condensate is managed with an aboveground tank in the flare compound.

Exploration

- Gas Detection Probe
- ⌵ Gas Extraction Well (in Refuse Completion)
- ⊠ Gas Extraction Well (Native Soil Completion) *Disconnected in October, 2019*
- Trench Completion
- ⊕ Well Geologic Control
- ⊕ Condensate Sump
- ⊕ Condensate Sump* *Decommissioned in 2019*

Landfill Gas System

- LFG Pipe - 2"
- LFG Pipe - 4"
- LFG Pipe - 6"
- - - Trench
- LFG Valve
- ▭ Landfill Boundary

Landfill Gas System
2021 Second Quarter Environmental Monitoring
Report Hansville Landfill
Kitsap County, Washington



APR-2021
PROJECT NO.
160423

BY:
MLK / RAP
REVISED BY:
MLK

FIGURE NO.
A-1

ATTACHMENT B

Water Quality Results

Table B-1. Water Level Elevations

Project No. 160423, Hansville Landfill, Hansville, WA

Well	Ground Elevation (ft NAVD88)	Top of Casing Elevation (ft NAVD88)	Screen Elevation (ft NAVD88)		Depth to Water (ft)	Water Level Elevation (ft NAVD88)
			Top	Bottom		
MW-5	363.7	366.9	244	234	100.68	266.2
MW-6	332.0	332.7	260	245	74.42	258.3
MW-7	344.3	346.0	259	244	85.10	260.9
MW-12I	245.6	248.1	217	207	10.08	238.0
MW-13D	258.1	260.4	205	195	11.18	249.2
MW-14	338.6	341.1	262	247	82.36	258.7

Notes

Depths to water collected April 21, 2021.

Elevations relative to North American Vertical Datum of 1988 (NAVD88).

ft = feet

Table B-2. Groundwater Quality Results

Project No. 160423, Hansville Landfill, Hansville Washington

Location Date			MW-5 04/21/2021	MW-6 04/21/2021	MW-7 04/21/2021	MW-12I 04/21/2021	MW-13D 04/21/2021	MW-14 04/21/2021
Parameter	Units	Site Cleanup Level						
Field Parameters								
Dissolved Oxygen	mg/L		8.64	0.31	0.75	0.38	2.17	0.55
pH	pH units		7.09	7.02	6.3	7.27	7.49	7.2
Redox	mV		8.8	123.7	-0.1	79	76.1	63.9
Specific Conductivity	uS/cm		289.9	501.9	384.9	89.1	117.6	124.9
Temperature	deg C		10.4	12.6	9.4	11	12	12.3
Turbidity	NTU		0.63	1.33	1.41	0.73	0.79	0.44
Conventional								
Alkalinity	mg/L		76	140	140	69	75	91
Ammonia (as N)	mg/L		0.03 U	0.03 U	0.03 U	0.03 U	0.03 U	0.03 UJ
Bicarbonate	mg/L		76	140	140	69	75	91
Carbonate	mg/L		10 U	10 U	10 U	10 U	10 U	10 U
Chloride	mg/L		3 U	4.2	3 U	3 U	5.3	6.7
Nitrate (as N)	mg/L		2.54	1.36	0.184	0.100 U	0.100 U	0.100 U
Nitrite (as N)	mg/L		0.100 U	0.302	0.100 U	0.100 U	0.100 U	0.100 U
Orthophosphate (as P)	mg/L		0.10 U	0.10 U	0.10 U	0.10 U	0.10 U	0.10 U
Sulfate	mg/L		8.2	25	5 U	5.9	17	9.1
Total Organic Carbon	mg/L		1 U	1	1.8	2.1	1 U	2.3
Dissolved Metals								
Arsenic	mg/L	0.005	0.00182	0.00191	0.00111	0.00257	0.00521	0.0135
Manganese	mg/L	2.24	0.001 U	0.29	0.0027	0.027	0.0058	0.92
VOCs								
Vinyl Chloride	ug/L	0.025	0.02 U	0.065	0.02 U	0.073	0.02 U	0.04

Notes

Bold text = Analyte was detected

Shaded Cell = Result exceeded Site Cleanup level

U = Not detected at or above the Reporting Limit shown

UJ = Analyte not detected and the Reporting Limit is an estimate

mg/L = milligram per liter

mV = millivolts

µS/cm = microSiemens per centimeter

deg C = degrees Celcius

NTU = Nephelometric Turbidity Units

µg/L = microgram per liter

Aspect Consulting

8/31/2021

\\biserver1.aspect.local\projects\Kitsap County Solid Waste\Hansville Landfill 2016\Project 160423\Report Drafts\2021 Reports\Q2\Appendix B\2021 Q2 Summary Tables

Table B-2

Second Quarter 2021 Environmental Monitoring Report

Page 1 of 1

Table B-3. Surface Water Quality Results

Project No. 60423, Hansville Landfill, Hansville Washington

Location Date			SW-1 04/21/2021	SW-4 04/21/2021	SW-6 04/21/2021	SW-7 04/21/2021
Parameter	Units	Site Cleanup Level				
Field Parameters						
Dissolved Oxygen	mg/L		8.62	9.23	8.13	9.73
pH	pH units		7.07	7.71	7.17	7.5
Redox	mV		86.3	78.7	71.2	108.2
Specific Conductivity	uS/cm		440.1	584.6	226.2	218.9
Temperature	deg C		10.6	10.2	12.2	10.2
Turbidity	NTU		2.28	5.7	24.9	9.78
Conventional						
Alkalinity	mg/L		100	160	65	57
Ammonia (as N)	mg/L		0.03 U	0.03 U	0.03 U	0.03 U
Bicarbonate	mg/L		100	160	65	57
Carbonate	mg/L		10 U	10 U	10 U	10 U
Chloride	mg/L		10	13	3.8	3.6
Nitrate (as N)	mg/L		2.36	0.917	0.100 U	0.566
Nitrite (as N)	mg/L		0.100 U	0.100 U	0.100 U	0.100 U
Orthophosphate (as P)	mg/L		0.10 U	0.10 U	0.10 U	0.10 U
Sulfate	mg/L		18	22	6.8	7.5
Total Organic Carbon	mg/L		1.5	5.2	11	7.4
Dissolved Metals						
Arsenic	mg/L	0.005	0.00106	0.00190	0.00341	0.00151
Manganese	mg/L	2.24	0.001 U	0.042	0.053	0.0026
VOCs						
Vinyl Chloride	ug/L	0.025	0.02 U	0.02 U	0.02 U	0.02 U

Notes

Bold text = Analyte was detected

Shaded Cell = Result exceeded Site Cleanup level

U = Not detected at or above the Reporting Limit shown

mg/L = milligram per liter

mg/L = milligram per liter

mV = millivolts

uS/cm = microSiemens per centimeter

deg C = degrees Celcius

NTU = Nephelometric Turbidity Units

ug/L = microgram per liter

Aspect Consulting


8/31/2021

\\biserver1.aspect.local\projects\Kitsap County Solid Waste\Hansville Landfill 2016\Project 160423\Report Drafts\2021 Reports\Q2\Appendix B\2021 Q2 Summary Tables

Table B-3

Second Quarter 2021 Environmental Monitoring Report

Page 1 of 1



Compliance Monitoring Locations

Second Quarter 2021 Environmental Monitoring Report
Hansville Landfill
Kitsap County, Washington



JUL-2021

PROJECT NO.
160423

BY:
MLK / RAP

REVISED BY:
WEG

FIGURE NO.

B-1

Note: Vertical datum is NAVD88. Approximate area of groundwater discharge from upper aquifer delineation from Remedial Investigation Report (Parametrix, 2006).

Basemap Layer Credits || Source: Esri, Maxar, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community
Esri, HERE, Garmin, (c) OpenStreetMap contributors, and the GIS user community

GIS Path: I:\projects & Hansville\landfill_160423\Delivered\Quarterly\Report\Q2 2021 Compliance Monitoring Locations Q2 2021.mxd || Coordinate System: NAD 1983 StatePlane Washington North FIPS 4601 Feet || Date Saved: 7/27/2021 || User: bkrum || Print Date: 7/27/2021

ATTACHMENT C

Groundwater Statistics and Time-Series Plots

Table C-1. Statistical Analysis

Project 160423, Hansville Landfill, Hansville, WA

Dissolved Arsenic Statistical Results

Well	Statistical Trend ¹	Mann-Kendall Test ²				Sen's Slope	
		Test Value, Z	Critical Value	Number of data points, n	Statistical Significance	(ug/L per day)	(ug/L per year)
MW-5	-- ³	--	--	--	--	--	--
MW-6	--	--	--	--	--	--	--
MW-7	--	--	--	--	--	--	--
MW-12I	--	--	--	--	--	--	--
MW-13D	Increasing	7.5	1.96	57	Yes	5.1E-07	0.00019
MW-14	Decreasing	-7.8	-1.96	57	Yes	-3.1E-06	-0.0011

Vinyl Chloride Statistical Results

Well	Statistical Trend ¹	Mann-Kendall Test ²				Sen's Slope	
		Test Value, Z	Critical Value	Number of data points, n	Statistical Significance	(ug/L per day)	(ug/L per year)
MW-5	-- ³	--	--	--	--	--	--
MW-6	Decreasing	-7.4	-1.96	58	Yes	-6.6E-05	-0.024
MW-7	--	--	--	--	--	--	--
MW-12I	Decreasing	-7.2	-1.96	58	Yes	-8.2E-05	-0.030
MW-13D	--	--	--	--	--	--	--
MW-14	Decreasing	-8.9	-1.96	58	Yes	-9.4E-05	-0.035

Notes

1 - The Statistical Trend indicates:

"Non-significant" if the magnitude of the Test Value is less than the Critical Value,

"Increasing" if the magnitude of the Test Value is greater than the Critical Value and the Sen's Slope is positive, or

"Decreasing" if the magnitude of the Test Value is greater than the Critical Value and the Sen's Slope is negative.

2 - Mann-Kendall tests were performed with alpha = 0.05 (95% confidence level).

For N>40, Mann-Kendall uses an approximation of a normal distribution, represented by Test Value Z.

3 - "--" Indicates statistical analysis not conducted.

ug/L - micrograms per liter

4 - Data range is from 2nd quarter 2006 through 2nd quarter 2021

Aspect Consulting

8/31/2021


\\bserver1.aspect.local\projects\Kitsap County Solid Waste\Hansville Landfill 2016\Project 160423\Report Drafts\2021 Reports\Q2\App C\2021 Q2 C-1 Statistical Analysis Results

Table C-1


2021 Second Quarter Monitoring Report

1 of 1


MW-5 (Background Well)




MW-6




MW-7




MW-12I



MW-13D




MW-14




Note: Non-detected values are shown at 1/2 the reporting limit.
Results from First Quarter 2017 were rejected. See text.

Result Flags
○ Detected
□ U - Non-Detect


MW-5 (Background Well)




MW-6




MW-7




MW-12I



MW-13D



MW-14




Note: Non-detected values are shown at 1/2 the reporting limit.


Result Flags

○ Detected □ J - Estimate + U - Non-Detect


MW-6 Vinyl Chloride Trend




MW-12I Vinyl Chloride Trend




MW-14 Vinyl Chloride Trend



MW-13D Dissolved Arsenic Trend



MW-14 Dissolved Arsenic Trend



Note: Non-detected values are shown at 1/2 the reporting limit.
Attenuation curves based on exponential least squares fit to the data.

Result Flags
○ Detected □ J - Estimate + U - Non-Detect

ATTACHMENT D

Field Forms and Laboratory Reports



Page: 1 of 1

Sample Intake Depth (ft TOC):

3/4" = 0.09 Lpf 2" = 0.62 Lpf 4" = 2.46 Lpf 6" = 5.56 Lpf

Ending Total Depth (ft TOC): 10.0

Observations/Comments: DO sensor recalibrated @ 0955

Sample number MIN-14-042121

GROUNDWATER SAMPLING RECORD

WELL NUMBER: MW-14

Page: of

Project Name: Hansville Landfill

Project Number: 160423

Date: 4/21/2021

Starting Water Level (ft TOC): 82.36

Sampled by: AB

Casing Stickup (ft):

Measuring Point of Well: TDC

Total Depth (ft TOC): —

Screened Interval (ft. TOC)

Casing Diameter (inches): 7.11

Filter Pack Interval (ft. TOC)

9	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
---	---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----

Casing Volume _____ (ft Water) x _____ (Lp/v)(gpf) = _____ (L)(gal)

Casing volumes: 3/4" = 0.02 gpf 2" = 0.16 gpf 4" = 0.65 gpf 6" = 1.47 gpf

Sample Intake Depth (ft TOC): mid screen

3/4" = 0.09 Lpf 2" = 0.62 Lpf 4" = 2.46 Lpf 6" = 5.56 Lpf

PURGING MEASUREMENTS

[illegible]

Total Gallons Purged:

Total Casing Volumes Removed: _____

Ending Water Level (ft TOC): _____

Ending Total Depth (ft TOC): _____

SAMPLE INVENTORY

Time	Volume	Bottle Type	Quantity	Filtration	Preservation	Appearance		Remarks
						Color	Turbidity & Sediment	
10/5	40	VOA	3	N	HCl	Clear	I-DD	
↓ 250	500	Amber	2	N	H2SO4			
↓	500	Poly	2	N	N	↓	↓	Sub to ARI X I
↓	500	Poly	2	Y	HNO3	↓	↓	Sub to ARI x I
↓	250	Ply	1	Y	N	↓	↓	Sub to ARI
					/			

METHODS

Parameters measured with (instrument model & serial number): WLI: blue/white Turbidimeter: Yellow YSI: Red

Purging Equipment:	dedicated bladder OR persitaltic	Decon Equipment:	alconox and water
--------------------	----------------------------------	------------------	-------------------

Disposal of Discharged Water: onsite

Observations/Comments: collected duplicate MW-20DD-042121


ANALYTICAL REPORT

Eurofins TestAmerica, Denver
4955 Yarrow Street
Arvada, CO 80002
Tel: (303)736-0100

Laboratory Job ID: 280-147801-1
Client Project/Site: Hansville Landfill
Sampling Event: 2Q_3Q_4Q Sampling

For:
Aspect Consulting
350 Madison Ave N
Bainbridge Island, Washington 98110

Attn: Ms. Meilani Lanier-Kamaha'o



Authorized for release by:
5/18/2021 11:13:09 AM

Betsy Sara, Project Manager II
(303)736-0189
Betsy.Sara@Eurofinset.com

LINKS

Review your project
results through
TotalAccess

Have a Question?



Visit us at:

www.eurofinsus.com/Env

The test results in this report meet all 2003 NELAC, 2009 TNI, and 2016 TNI requirements for accredited parameters, exceptions are noted in this report. This report may not be reproduced except in full, and with written approval from the laboratory. For questions please contact the Project Manager at the e-mail address or telephone number listed on this page.

This report has been electronically signed and authorized by the signatory. Electronic signature is intended to be the legally binding equivalent of a traditionally handwritten signature.

Results relate only to the items tested and the sample(s) as received by the laboratory.

Table of Contents

Cover Page	1
Table of Contents	2
Definitions	3
Case Narrative	4
Detection Summary	6
Method Summary	8
Sample Summary	9
Client Sample Results	10
Surrogate Summary	17
QC Sample Results	18
QC Association	25
Chronicle	28
Subcontract Data	32
Chain of Custody	65
Receipt Checklists	70



Definitions/Glossary

Client: Aspect Consulting
Project/Site: Hansville Landfill

Job ID: 280-147801-1

Qualifiers

Metals

Qualifier	Qualifier Description
4	MS, MSD: The analyte present in the original sample is greater than 4 times the matrix spike concentration; therefore, control limits are not applicable.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
α	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CFU	Colony Forming Unit
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MCL	EPA recommended "Maximum Contaminant Level"
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
MPN	Most Probable Number
MQL	Method Quantitation Limit
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
NEG	Negative / Absent
POS	Positive / Present
PQL	Practical Quantitation Limit
PRES	Presumptive
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)
TNTC	Too Numerous To Count

Case Narrative

Client: Aspect Consulting
Project/Site: Hansville Landfill

Job ID: 280-147801-1

Job ID: 280-147801-1

Laboratory: Eurofins TestAmerica, Denver

Narrative

CASE NARRATIVE

Client: Aspect Consulting

Project: Hansville Landfill

Report Number: 280-147801-1

With the exceptions noted as flags or footnotes, standard analytical protocols were followed in the analysis of the samples and no problems were encountered or anomalies observed. In addition all laboratory quality control samples were within established control limits, with any exceptions noted below. Each sample was analyzed to achieve the lowest possible reporting limit within the constraints of the method. In some cases, due to interference or analytes present at high concentrations, samples were diluted. For diluted samples, the reporting limits are adjusted relative to the dilution required.

This report may include reporting limits (RLs) less than Eurofins TestAmerica's standard reporting limit. The reported sample results and associated reporting limits are being used specifically to meet the needs of this project. Note that data are not normally reported to these levels without qualification because they are inherently less reliable and potentially less defensible than required by the latest industry standards.

Sample Receiving

The samples were received on 04/23/2021; the samples arrived in good condition, properly preserved and on ice. The temperature of the cooler at receipt was 3.5 C.

Holding Times

All holding times were within established control limits.

Method Blanks

All Method Blanks were within established control limits.

Laboratory Control Samples (LCS)

All Laboratory Control Samples were within established control limits.

Matrix Spike (MS) and Matrix Spike Duplicate (MSD)

The percent recoveries and/or relative percent difference of the MS/MSD performed on a sample from another client were outside control limits for Dissolved Manganese Method 6020 because the sample concentration was greater than four times the spike amount. Because the corresponding Laboratory Control Sample and the Method Blank sample were within control limits, no corrective action was taken.

All other MS and MSD samples were within established control limits.

General Comments

The analysis for 8260C SIM was performed by Eurofins TestAmerica Buffalo.

Their address and phone number are:

Eurofins TestAmerica Buffalo
10 Hazelwood Drive, Suite 106
Amherst, NY 14228
716-691-2600

The analysis for Nitrate, Nitrite, Ortho-phos Method 300.0, and Dissolved Arsenic Method 200.8 were performed by ARI. Their address and

Case Narrative

Client: Aspect Consulting
Project/Site: Hansville Landfill

Job ID: 280-147801-1

Job ID: 280-147801-1 (Continued)

Laboratory: Eurofins TestAmerica, Denver (Continued)

phone number are:
Analytical Resources, Inc.
4611 S.134th Place
Tukwila, WA 98168-3240
206-695-6200

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

Detection Summary

Client: Aspect Consulting
Project/Site: Hansville Landfill

Job ID: 280-147801-1

Client Sample ID: MW7-042121

Lab Sample ID: 280-147801-1

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Manganese	2.7		1.0		ug/L	1		6020	Dissolved
Total Alkalinity	140		10		mg/L	1		SM 2320B	Total/NA
Bicarbonate Alkalinity	140		10		mg/L	1		SM 2320B	Total/NA
Total Organic Carbon - Average	1.8		1.0		mg/L	1		SM 5310B	Total/NA

Client Sample ID: MW5-042121

Lab Sample ID: 280-147801-2

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Sulfate	8.2		5.0		mg/L	1		300.0	Total/NA
Total Alkalinity	76		10		mg/L	1		SM 2320B	Total/NA
Bicarbonate Alkalinity	76		10		mg/L	1		SM 2320B	Total/NA

Client Sample ID: SW1-042121

Lab Sample ID: 280-147801-3

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Chloride	10		3.0		mg/L	1		300.0	Total/NA
Sulfate	18		5.0		mg/L	1		300.0	Total/NA
Total Alkalinity	100		10		mg/L	1		SM 2320B	Total/NA
Bicarbonate Alkalinity	100		10		mg/L	1		SM 2320B	Total/NA
Total Organic Carbon - Average	1.5		1.0		mg/L	1		SM 5310B	Total/NA

Client Sample ID: MW12I-042121

Lab Sample ID: 280-147801-4

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Vinyl chloride	0.073		0.020		ug/L	1		8260C SIM	Total/NA
Manganese	27		1.0		ug/L	1		6020	Dissolved
Sulfate	5.9		5.0		mg/L	1		300.0	Total/NA
Total Alkalinity	69		10		mg/L	1		SM 2320B	Total/NA
Bicarbonate Alkalinity	69		10		mg/L	1		SM 2320B	Total/NA
Total Organic Carbon - Average	2.1		1.0		mg/L	1		SM 5310B	Total/NA

Client Sample ID: SW4-042121

Lab Sample ID: 280-147801-5

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Manganese	42		1.0		ug/L	1		6020	Dissolved
Chloride	13		3.0		mg/L	1		300.0	Total/NA
Sulfate	22		5.0		mg/L	1		300.0	Total/NA
Total Alkalinity	160		10		mg/L	1		SM 2320B	Total/NA
Bicarbonate Alkalinity	160		10		mg/L	1		SM 2320B	Total/NA
Total Organic Carbon - Average	5.2		1.0		mg/L	1		SM 5310B	Total/NA

Client Sample ID: SW6-042121

Lab Sample ID: 280-147801-6

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Manganese	53		1.0		ug/L	1		6020	Dissolved
Chloride	3.8		3.0		mg/L	1		300.0	Total/NA
Sulfate	6.8		5.0		mg/L	1		300.0	Total/NA
Total Alkalinity	65		10		mg/L	1		SM 2320B	Total/NA
Bicarbonate Alkalinity	65		10		mg/L	1		SM 2320B	Total/NA
Total Organic Carbon - Average	11		1.0		mg/L	1		SM 5310B	Total/NA

This Detection Summary does not include radiochemical test results.

Eurofins TestAmerica, Denver

Detection Summary

Client: Aspect Consulting
Project/Site: Hansville Landfill

Job ID: 280-147801-1

Client Sample ID: MW13D-042121

Lab Sample ID: 280-147801-7

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Manganese	5.8		1.0		ug/L	1		6020	Dissolved
Chloride	5.3		3.0		mg/L	1		300.0	Total/NA
Sulfate	17		5.0		mg/L	1		300.0	Total/NA
Total Alkalinity	75		10		mg/L	1		SM 2320B	Total/NA
Bicarbonate Alkalinity	75		10		mg/L	1		SM 2320B	Total/NA

Client Sample ID: SW7-042121

Lab Sample ID: 280-147801-8

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Manganese	2.6		1.0		ug/L	1		6020	Dissolved
Chloride	3.6		3.0		mg/L	1		300.0	Total/NA
Sulfate	7.5		5.0		mg/L	1		300.0	Total/NA
Total Alkalinity	57		10		mg/L	1		SM 2320B	Total/NA
Bicarbonate Alkalinity	57		10		mg/L	1		SM 2320B	Total/NA
Total Organic Carbon - Average	7.4		1.0		mg/L	1		SM 5310B	Total/NA

Client Sample ID: MW6-042121

Lab Sample ID: 280-147801-9

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Vinyl chloride	0.065		0.020		ug/L	1		8260C SIM	Total/NA
Manganese	290		1.0		ug/L	1		6020	Dissolved
Chloride	4.2		3.0		mg/L	1		300.0	Total/NA
Sulfate	25		5.0		mg/L	1		300.0	Total/NA
Total Alkalinity	140		10		mg/L	1		SM 2320B	Total/NA
Bicarbonate Alkalinity	140		10		mg/L	1		SM 2320B	Total/NA
Total Organic Carbon - Average	1.0		1.0		mg/L	1		SM 5310B	Total/NA

Client Sample ID: MW14-042121

Lab Sample ID: 280-147801-10

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Vinyl chloride	0.040		0.020		ug/L	1		8260C SIM	Total/NA
Manganese	920		1.0		ug/L	1		6020	Dissolved
Chloride	6.7		3.0		mg/L	1		300.0	Total/NA
Sulfate	9.1		5.0		mg/L	1		300.0	Total/NA
Total Alkalinity	91		10		mg/L	1		SM 2320B	Total/NA
Bicarbonate Alkalinity	91		10		mg/L	1		SM 2320B	Total/NA
Total Organic Carbon - Average	2.3		1.0		mg/L	1		SM 5310B	Total/NA

Client Sample ID: MW20DD-042121

Lab Sample ID: 280-147801-11

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Vinyl chloride	0.046		0.020		ug/L	1		8260C SIM	Total/NA
Manganese	890		1.0		ug/L	1		6020	Dissolved
Chloride	6.4		3.0		mg/L	1		300.0	Total/NA
Sulfate	9.4		5.0		mg/L	1		300.0	Total/NA
Ammonia as N	0.068		0.030		mg/L	1		350.1	Total/NA
Total Alkalinity	90		10		mg/L	1		SM 2320B	Total/NA
Bicarbonate Alkalinity	90		10		mg/L	1		SM 2320B	Total/NA
Total Organic Carbon - Average	2.2		1.0		mg/L	1		SM 5310B	Total/NA

Client Sample ID: TB1

Lab Sample ID: 280-147801-12

No Detections.

This Detection Summary does not include radiochemical test results.

Eurofins TestAmerica, Denver

Method Summary

Client: Aspect Consulting
Project/Site: Hansville Landfill

Job ID: 280-147801-1

Method	Method Description	Protocol	Laboratory
8260C SIM	Volatile Organic Compounds (GC/MS)	SW846	TAL BUF
6020	Metals (ICP/MS)	SW846	TAL DEN
300.0	Anions, Ion Chromatography	MCAWW	TAL DEN
350.1	Nitrogen, Ammonia	MCAWW	TAL DEN
SM 2320B	Alkalinity	SM	TAL DEN
SM 5310B	Organic Carbon, Total (TOC)	SM	TAL DEN
Subcontract	Dissolved As (ARI) - direct sub to ARI from field	None	SC0056
Subcontract	Nitrate/Nitrite/o-phos(field filtered) (ARI) - direct sub to ARI from field	None	SC0056
3005A	Preparation, Total Recoverable or Dissolved Metals	SW846	TAL DEN
5030C	Purge and Trap	SW846	TAL BUF

Protocol References:

MCAWW = "Methods For Chemical Analysis Of Water And Wastes", EPA-600/4-79-020, March 1983 And Subsequent Revisions.

None = None

SM = "Standard Methods For The Examination Of Water And Wastewater"

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

Laboratory References:

SC0056 = Analytical Resources, Inc, 4611 South 134th Place, Suite 100, Tukwila, WA 98168, TEL (206)695-6200

TAL BUF = Eurofins TestAmerica, Buffalo, 10 Hazelwood Drive, Amherst, NY 14228-2298, TEL (716)691-2600

TAL DEN = Eurofins TestAmerica, Denver, 4955 Yarrow Street, Arvada, CO 80002, TEL (303)736-0100

Sample Summary

Client: Aspect Consulting
Project/Site: Hansville Landfill

Job ID: 280-147801-1

Lab Sample ID	Client Sample ID	Matrix	Collected	Received	Asset ID
280-147801-1	MW7-042121	Water	04/21/21 08:45	04/23/21 10:25	
280-147801-2	MW5-042121	Water	04/21/21 10:20	04/23/21 10:25	
280-147801-3	SW1-042121	Water	04/21/21 11:45	04/23/21 10:25	
280-147801-4	MW12I-042121	Water	04/21/21 12:00	04/23/21 10:25	
280-147801-5	SW4-042121	Water	04/21/21 12:30	04/23/21 10:25	
280-147801-6	SW6-042121	Water	04/21/21 13:15	04/23/21 10:25	
280-147801-7	MW13D-042121	Water	04/21/21 13:00	04/23/21 10:25	
280-147801-8	SW7-042121	Water	04/21/21 14:20	04/23/21 10:25	
280-147801-9	MW6-042121	Water	04/21/21 16:00	04/23/21 10:25	
280-147801-10	MW14-042121	Water	04/21/21 16:15	04/23/21 10:25	
280-147801-11	MW20DD-042121	Water	04/21/21 00:00	04/23/21 10:25	
280-147801-12	TB1	Water	04/21/21 08:45	04/23/21 10:25	

Client Sample Results

Client: Aspect Consulting
Project/Site: Hansville Landfill

Job ID: 280-147801-1

Method: 8260C SIM - Volatile Organic Compounds (GC/MS)

Client Sample ID: MW7-042121
Date Collected: 04/21/21 08:45
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-1
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Vinyl chloride	ND		0.020		ug/L			05/03/21 22:57	1
Surrogate	%Recovery	Qualifier	Limits				Prepared	Analyzed	Dil Fac
Dibromofluoromethane (Surr)	120		50 - 150					05/03/21 22:57	1
TBA-d9 (Surr)	97		50 - 150					05/03/21 22:57	1

Client Sample ID: MW5-042121
Date Collected: 04/21/21 10:20
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-2
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Vinyl chloride	ND		0.020		ug/L			05/03/21 23:21	1
Surrogate	%Recovery	Qualifier	Limits				Prepared	Analyzed	Dil Fac
Dibromofluoromethane (Surr)	118		50 - 150					05/03/21 23:21	1
TBA-d9 (Surr)	97		50 - 150					05/03/21 23:21	1

Client Sample ID: SW1-042121
Date Collected: 04/21/21 11:45
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-3
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Vinyl chloride	ND		0.020		ug/L			05/03/21 23:45	1
Surrogate	%Recovery	Qualifier	Limits				Prepared	Analyzed	Dil Fac
Dibromofluoromethane (Surr)	119		50 - 150					05/03/21 23:45	1
TBA-d9 (Surr)	94		50 - 150					05/03/21 23:45	1

Client Sample ID: MW121-042121
Date Collected: 04/21/21 12:00
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-4
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Vinyl chloride	0.073		0.020		ug/L			05/04/21 00:09	1
Surrogate	%Recovery	Qualifier	Limits				Prepared	Analyzed	Dil Fac
Dibromofluoromethane (Surr)	132		50 - 150					05/04/21 00:09	1
TBA-d9 (Surr)	108		50 - 150					05/04/21 00:09	1

Client Sample ID: SW4-042121
Date Collected: 04/21/21 12:30
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-5
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Vinyl chloride	ND		0.020		ug/L			05/04/21 00:33	1
Surrogate	%Recovery	Qualifier	Limits				Prepared	Analyzed	Dil Fac
Dibromofluoromethane (Surr)	121		50 - 150					05/04/21 00:33	1
TBA-d9 (Surr)	98		50 - 150					05/04/21 00:33	1

Client Sample ID: SW6-042121
Date Collected: 04/21/21 13:15
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-6
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Vinyl chloride	ND		0.020		ug/L			05/04/21 00:57	1

Eurofins TestAmerica, Denver

Client Sample Results

Client: Aspect Consulting
Project/Site: Hansville Landfill

Job ID: 280-147801-1

Method: 8260C SIM - Volatile Organic Compounds (GC/MS) (Continued)

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
Dibromofluoromethane (Surr)	119		50 - 150		05/04/21 00:57	1
TBA-d9 (Surr)	95		50 - 150		05/04/21 00:57	1

Client Sample ID: MW13D-042121
Date Collected: 04/21/21 13:00
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-7
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Vinyl chloride	ND		0.020		ug/L			05/04/21 01:21	1

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
Dibromofluoromethane (Surr)	120		50 - 150		05/04/21 01:21	1
TBA-d9 (Surr)	105		50 - 150		05/04/21 01:21	1

Client Sample ID: SW7-042121
Date Collected: 04/21/21 14:20
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-8
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Vinyl chloride	ND		0.020		ug/L			05/04/21 01:46	1

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
Dibromofluoromethane (Surr)	121		50 - 150		05/04/21 01:46	1
TBA-d9 (Surr)	99		50 - 150		05/04/21 01:46	1

Client Sample ID: MW6-042121
Date Collected: 04/21/21 16:00
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-9
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Vinyl chloride	0.065		0.020		ug/L			05/04/21 02:10	1

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
Dibromofluoromethane (Surr)	121		50 - 150		05/04/21 02:10	1
TBA-d9 (Surr)	97		50 - 150		05/04/21 02:10	1

Client Sample ID: MW14-042121
Date Collected: 04/21/21 16:15
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-10
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Vinyl chloride	0.040		0.020		ug/L			05/04/21 02:34	1

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
Dibromofluoromethane (Surr)	120		50 - 150		05/04/21 02:34	1
TBA-d9 (Surr)	96		50 - 150		05/04/21 02:34	1

Client Sample ID: MW20DD-042121
Date Collected: 04/21/21 00:00
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-11
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Vinyl chloride	0.046		0.020		ug/L			05/04/21 02:58	1

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
Dibromofluoromethane (Surr)	119		50 - 150		05/04/21 02:58	1
TBA-d9 (Surr)	96		50 - 150		05/04/21 02:58	1

Eurofins TestAmerica, Denver

Client Sample Results

Client: Aspect Consulting
Project/Site: Hansville Landfill

Job ID: 280-147801-1

Method: 8260C SIM - Volatile Organic Compounds (GC/MS)

Client Sample ID: TB1
Date Collected: 04/21/21 08:45
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-12
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Vinyl chloride	ND		0.020		ug/L			05/04/21 03:23	1
Surrogate	%Recovery	Qualifier	Limits				Prepared	Analyzed	Dil Fac
Dibromofluoromethane (Surr)	121		50 - 150					05/04/21 03:23	1
TBA-d9 (Surr)	98		50 - 150					05/04/21 03:23	1

Method: 6020 - Metals (ICP/MS) - Dissolved

Client Sample ID: MW7-042121
Date Collected: 04/21/21 08:45
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-1
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Manganese	2.7		1.0		ug/L		04/29/21 16:00	04/30/21 17:09	1

Client Sample ID: MW5-042121
Date Collected: 04/21/21 10:20
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-2
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Manganese	ND		1.0		ug/L		04/29/21 16:00	04/30/21 17:13	1

Client Sample ID: SW1-042121
Date Collected: 04/21/21 11:45
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-3
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Manganese	ND		1.0		ug/L		04/29/21 16:00	04/30/21 17:16	1

Client Sample ID: MW121-042121
Date Collected: 04/21/21 12:00
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-4
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Manganese	27		1.0		ug/L		04/29/21 16:00	04/30/21 17:20	1

Client Sample ID: SW4-042121
Date Collected: 04/21/21 12:30
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-5
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Manganese	42		1.0		ug/L		04/29/21 16:00	04/30/21 17:31	1

Client Sample ID: SW6-042121
Date Collected: 04/21/21 13:15
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-6
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Manganese	53		1.0		ug/L		04/29/21 16:00	04/30/21 17:34	1

Client Sample ID: MW13D-042121
Date Collected: 04/21/21 13:00
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-7
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Manganese	5.8		1.0		ug/L		04/29/21 16:00	04/30/21 17:38	1

Eurofins TestAmerica, Denver

Client Sample Results

Client: Aspect Consulting
Project/Site: Hansville Landfill

Job ID: 280-147801-1

Method: 6020 - Metals (ICP/MS) - Dissolved

Client Sample ID: SW7-042121
Date Collected: 04/21/21 14:20
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-8
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Manganese	2.6		1.0		ug/L		04/29/21 16:00	04/30/21 17:41	1

Client Sample ID: MW6-042121
Date Collected: 04/21/21 16:00
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-9
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Manganese	290		1.0		ug/L		04/29/21 16:00	04/30/21 17:45	1

Client Sample ID: MW14-042121
Date Collected: 04/21/21 16:15
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-10
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Manganese	920		1.0		ug/L		04/29/21 16:00	04/30/21 17:48	1

Client Sample ID: MW20DD-042121
Date Collected: 04/21/21 00:00
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-11
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Manganese	890		1.0		ug/L		04/29/21 16:00	04/30/21 17:52	1

General Chemistry

Client Sample ID: MW7-042121
Date Collected: 04/21/21 08:45
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-1
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	ND		3.0		mg/L			05/16/21 04:53	1
Sulfate	ND		5.0		mg/L			05/16/21 04:53	1
Ammonia as N	ND		0.030		mg/L			04/30/21 15:30	1
Total Alkalinity	140		10		mg/L			04/30/21 07:38	1
Bicarbonate Alkalinity	140		10		mg/L			04/30/21 07:38	1
Carbonate Alkalinity	ND		10		mg/L			04/30/21 07:38	1
Total Organic Carbon - Average	1.8		1.0		mg/L			05/07/21 01:38	1

Client Sample ID: MW5-042121
Date Collected: 04/21/21 10:20
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-2
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	ND		3.0		mg/L			05/16/21 05:07	1
Sulfate	8.2		5.0		mg/L			05/16/21 05:07	1
Ammonia as N	ND		0.030		mg/L			04/30/21 15:32	1
Total Alkalinity	76		10		mg/L			04/30/21 07:44	1
Bicarbonate Alkalinity	76		10		mg/L			04/30/21 07:44	1
Carbonate Alkalinity	ND		10		mg/L			04/30/21 07:44	1
Total Organic Carbon - Average	ND		1.0		mg/L			05/07/21 02:40	1

Client Sample ID: SW1-042121
Date Collected: 04/21/21 11:45
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-3
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	10		3.0		mg/L			05/16/21 05:21	1

Eurofins TestAmerica, Denver

Client Sample Results

Client: Aspect Consulting
Project/Site: Hansville Landfill

Job ID: 280-147801-1

General Chemistry (Continued)

Client Sample ID: SW1-042121
Date Collected: 04/21/21 11:45
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-3
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Sulfate	18		5.0		mg/L			05/16/21 05:21	1
Ammonia as N	ND		0.030		mg/L			04/30/21 15:38	1
Total Alkalinity	100		10		mg/L			05/03/21 17:56	1
Bicarbonate Alkalinity	100		10		mg/L			05/03/21 17:56	1
Carbonate Alkalinity	ND		10		mg/L			05/03/21 17:56	1
Total Organic Carbon - Average	1.5		1.0		mg/L			05/07/21 03:59	1

Client Sample ID: MW12I-042121
Date Collected: 04/21/21 12:00
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-4
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	ND		3.0		mg/L			05/16/21 05:35	1
Sulfate	5.9		5.0		mg/L			05/16/21 05:35	1
Ammonia as N	ND		0.030		mg/L			04/30/21 16:00	1
Total Alkalinity	69		10		mg/L			04/30/21 07:56	1
Bicarbonate Alkalinity	69		10		mg/L			04/30/21 07:56	1
Carbonate Alkalinity	ND		10		mg/L			04/30/21 07:56	1
Total Organic Carbon - Average	2.1		1.0		mg/L			05/07/21 04:18	1

Client Sample ID: SW4-042121
Date Collected: 04/21/21 12:30
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-5
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	13		3.0		mg/L			05/16/21 06:59	1
Sulfate	22		5.0		mg/L			05/16/21 06:59	1
Ammonia as N	ND		0.030		mg/L			04/30/21 16:02	1
Total Alkalinity	160		10		mg/L			04/30/21 08:37	1
Bicarbonate Alkalinity	160		10		mg/L			04/30/21 08:37	1
Carbonate Alkalinity	ND		10		mg/L			04/30/21 08:37	1
Total Organic Carbon - Average	5.2		1.0		mg/L			05/07/21 04:33	1

Client Sample ID: SW6-042121
Date Collected: 04/21/21 13:15
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-6
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	3.8		3.0		mg/L			05/16/21 07:13	1
Sulfate	6.8		5.0		mg/L			05/16/21 07:13	1
Ammonia as N	ND		0.030		mg/L			04/30/21 16:04	1
Total Alkalinity	65		10		mg/L			04/30/21 08:50	1
Bicarbonate Alkalinity	65		10		mg/L			04/30/21 08:50	1
Carbonate Alkalinity	ND		10		mg/L			04/30/21 08:50	1
Total Organic Carbon - Average	11		1.0		mg/L			05/07/21 04:47	1

Client Sample ID: MW13D-042121
Date Collected: 04/21/21 13:00
Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-7
Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	5.3		3.0		mg/L			05/16/21 07:27	1
Sulfate	17		5.0		mg/L			05/16/21 07:27	1
Ammonia as N	ND		0.030		mg/L			04/30/21 16:06	1

Eurofins TestAmerica, Denver

Client Sample Results

Client: Aspect Consulting
Project/Site: Hansville Landfill

Job ID: 280-147801-1

General Chemistry (Continued)

Client Sample ID: MW13D-042121

Date Collected: 04/21/21 13:00

Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-7

Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Alkalinity	75		10		mg/L			04/30/21 08:56	1
Bicarbonate Alkalinity	75		10		mg/L			04/30/21 08:56	1
Carbonate Alkalinity	ND		10		mg/L			04/30/21 08:56	1
Total Organic Carbon - Average	ND		1.0		mg/L			05/07/21 05:05	1

Client Sample ID: SW7-042121

Date Collected: 04/21/21 14:20

Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-8

Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	3.6		3.0		mg/L			05/16/21 07:41	1
Sulfate	7.5		5.0		mg/L			05/16/21 07:41	1
Ammonia as N	ND		0.030		mg/L			04/30/21 16:08	1
Total Alkalinity	57		10		mg/L			04/30/21 09:01	1
Bicarbonate Alkalinity	57		10		mg/L			04/30/21 09:01	1
Carbonate Alkalinity	ND		10		mg/L			04/30/21 09:01	1
Total Organic Carbon - Average	7.4		1.0		mg/L			05/07/21 05:20	1

Client Sample ID: MW6-042121

Date Collected: 04/21/21 16:00

Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-9

Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	4.2		3.0		mg/L			05/16/21 07:55	1
Sulfate	25		5.0		mg/L			05/16/21 07:55	1
Ammonia as N	ND		0.030		mg/L			04/30/21 16:10	1
Total Alkalinity	140		10		mg/L			04/30/21 09:07	1
Bicarbonate Alkalinity	140		10		mg/L			04/30/21 09:07	1
Carbonate Alkalinity	ND		10		mg/L			04/30/21 09:07	1
Total Organic Carbon - Average	1.0		1.0		mg/L			05/07/21 05:37	1

Client Sample ID: MW14-042121

Date Collected: 04/21/21 16:15

Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-10

Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	6.7		3.0		mg/L			05/16/21 08:09	1
Sulfate	9.1		5.0		mg/L			05/16/21 08:09	1
Ammonia as N	ND		0.030		mg/L			04/30/21 16:12	1
Total Alkalinity	91		10		mg/L			04/30/21 09:13	1
Bicarbonate Alkalinity	91		10		mg/L			04/30/21 09:13	1
Carbonate Alkalinity	ND		10		mg/L			04/30/21 09:13	1
Total Organic Carbon - Average	2.3		1.0		mg/L			05/07/21 05:54	1

Client Sample ID: MW20DD-042121

Date Collected: 04/21/21 00:00

Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-11

Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	6.4		3.0		mg/L			05/16/21 08:23	1
Sulfate	9.4		5.0		mg/L			05/16/21 08:23	1
Ammonia as N	0.068		0.030		mg/L			04/30/21 16:14	1
Total Alkalinity	90		10		mg/L			04/30/21 09:19	1
Bicarbonate Alkalinity	90		10		mg/L			04/30/21 09:19	1

Eurofins TestAmerica, Denver

Client Sample Results

Client: Aspect Consulting
Project/Site: Hansville Landfill

Job ID: 280-147801-1

General Chemistry (Continued)

Client Sample ID: MW20DD-042121

Date Collected: 04/21/21 00:00

Date Received: 04/23/21 10:25

Lab Sample ID: 280-147801-11

Matrix: Water

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Carbonate Alkalinity	ND		10		mg/L			04/30/21 09:19	1
Total Organic Carbon - Average	2.2		1.0		mg/L			05/07/21 06:10	1

Surrogate Summary

Client: Aspect Consulting
Project/Site: Hansville Landfill

Job ID: 280-147801-1

Method: 8260C SIM - Volatile Organic Compounds (GC/MS)

Matrix: Water

Prep Type: Total/NA

Percent Surrogate Recovery (Acceptance Limits)

Lab Sample ID	Client Sample ID	DBFM	TBA
		(50-150)	(50-150)
280-147801-1	MW7-042121	120	97
280-147801-2	MW5-042121	118	97
280-147801-3	SW1-042121	119	94
280-147801-4	MW12I-042121	132	108
280-147801-5	SW4-042121	121	98
280-147801-6	SW6-042121	119	95
280-147801-7	MW13D-042121	120	105
280-147801-8	SW7-042121	121	99
280-147801-9	MW6-042121	121	97
280-147801-10	MW14-042121	120	96
280-147801-11	MW20DD-042121	119	96
280-147801-12	TB1	121	98
LCS 480-579097/6	Lab Control Sample	112	87
LCSD 480-579097/7	Lab Control Sample Dup	111	92
MB 480-579097/9	Method Blank	114	100

Surrogate Legend

DBFM = Dibromofluoromethane (Surr)

TBA = TBA-d9 (Surr)

QC Sample Results

Client: Aspect Consulting
Project/Site: Hansville Landfill

Job ID: 280-147801-1

Method: 8260C SIM - Volatile Organic Compounds (GC/MS)

Lab Sample ID: MB 480-579097/9

Matrix: Water

Analysis Batch: 579097

Client Sample ID: Method Blank

Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Vinyl chloride	ND		0.020		ug/L			05/03/21 19:43	1
Surrogate	%Recovery	MB Qualifier	Limits				Prepared	Analyzed	Dil Fac
Dibromofluoromethane (Surr)	114		50 - 150					05/03/21 19:43	1
TBA-d9 (Surr)	100		50 - 150					05/03/21 19:43	1

Lab Sample ID: LCS 480-579097/6

Matrix: Water

Analysis Batch: 579097

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Vinyl chloride	0.200	0.254		ug/L		127	50 - 150
Surrogate	%Recovery	LCS Qualifier	Limits				
Dibromofluoromethane (Surr)	112		50 - 150				
TBA-d9 (Surr)	87		50 - 150				

Lab Sample ID: LCSD 480-579097/7

Matrix: Water

Analysis Batch: 579097

Client Sample ID: Lab Control Sample Dup

Prep Type: Total/NA

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Vinyl chloride	0.200	0.261		ug/L		131	50 - 150	3	20
Surrogate	%Recovery	LCSD Qualifier	Limits						
Dibromofluoromethane (Surr)	111		50 - 150						
TBA-d9 (Surr)	92		50 - 150						

Method: 6020 - Metals (ICP/MS)

Lab Sample ID: MB 280-534315/1-A

Matrix: Water

Analysis Batch: 534658

Client Sample ID: Method Blank

Prep Type: Total Recoverable

Prep Batch: 534315

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Manganese	ND		1.0		ug/L		04/29/21 16:00	04/30/21 16:20	1

Lab Sample ID: LCS 280-534315/2-A

Matrix: Water

Analysis Batch: 534658

Client Sample ID: Lab Control Sample

Prep Type: Total Recoverable

Prep Batch: 534315

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Manganese	40.0	39.3		ug/L		98	85 - 117

Eurofins TestAmerica, Denver

QC Sample Results

Client: Aspect Consulting
Project/Site: Hansville Landfill

Job ID: 280-147801-1

Method: 6020 - Metals (ICP/MS) (Continued)

Lab Sample ID: 280-147870-F-1-B MS

Matrix: Water

Analysis Batch: 534658

Client Sample ID: Matrix Spike

Prep Type: Dissolved

Prep Batch: 534315

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Manganese	940		40.0	960	4	ug/L		58	85 - 117

Lab Sample ID: 280-147870-F-1-C MSD

Matrix: Water

Analysis Batch: 534658

Client Sample ID: Matrix Spike Duplicate

Prep Type: Dissolved

Prep Batch: 534315

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	Limit
Manganese	940		40.0	976	4	ug/L		99	85 - 117	2	20

Method: 300.0 - Anions, Ion Chromatography

Lab Sample ID: MB 280-536250/6

Matrix: Water

Analysis Batch: 536250

Client Sample ID: Method Blank

Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	ND		3.0		mg/L			05/15/21 13:54	1
Sulfate	ND		5.0		mg/L			05/15/21 13:54	1

Lab Sample ID: LCS 280-536250/4

Matrix: Water

Analysis Batch: 536250

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Chloride	100	102		mg/L		102	90 - 110
Sulfate	100	108		mg/L		108	90 - 110

Lab Sample ID: LCSD 280-536250/5

Matrix: Water

Analysis Batch: 536250

Client Sample ID: Lab Control Sample Dup

Prep Type: Total/NA

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	Limit
Chloride	100	102		mg/L		102	90 - 110	0	10
Sulfate	100	108		mg/L		108	90 - 110	0	10

Lab Sample ID: MRL 280-536250/3

Matrix: Water

Analysis Batch: 536250

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Analyte	Spike Added	MRL Result	MRL Qualifier	Unit	D	%Rec	%Rec. Limits
Chloride	5.00	4.98		mg/L		100	50 - 150
Sulfate	5.00	5.19		mg/L		104	50 - 150

Lab Sample ID: 280-147801-4 MS

Matrix: Water

Analysis Batch: 536250

Client Sample ID: MW12I-042121

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Chloride	ND		50.0	58.5		mg/L		112	80 - 120
Sulfate	5.9		50.0	61.4		mg/L		111	80 - 120

Eurofins TestAmerica, Denver

QC Sample Results

Client: Aspect Consulting
Project/Site: Hansville Landfill

Job ID: 280-147801-1

Method: 300.0 - Anions, Ion Chromatography (Continued)

Lab Sample ID: 280-147801-4 MSD

Matrix: Water

Analysis Batch: 536250

Client Sample ID: MW12I-042121

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Chloride	ND		50.0	54.4		mg/L		104	80 - 120	7	20
Sulfate	5.9		50.0	57.4		mg/L		103	80 - 120	7	20

Lab Sample ID: 280-147801-11 MS

Matrix: Water

Analysis Batch: 536250

Client Sample ID: MW20DD-042121

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Chloride	6.4		50.0	60.9		mg/L		109	80 - 120		
Sulfate	9.4		50.0	63.8		mg/L		109	80 - 120		

Lab Sample ID: 280-147801-11 MSD

Matrix: Water

Analysis Batch: 536250

Client Sample ID: MW20DD-042121

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Chloride	6.4		50.0	63.2		mg/L		114	80 - 120	4	20
Sulfate	9.4		50.0	66.2		mg/L		114	80 - 120	4	20

Lab Sample ID: 280-147801-4 DU

Matrix: Water

Analysis Batch: 536250

Client Sample ID: MW12I-042121

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	DU Result	DU Qualifier	Unit	D	RPD	RPD Limit
Chloride	ND		ND		mg/L		NC	15
Sulfate	5.9		5.87		mg/L		0.2	15

Lab Sample ID: 280-147801-11 DU

Matrix: Water

Analysis Batch: 536250

Client Sample ID: MW20DD-042121

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	DU Result	DU Qualifier	Unit	D	RPD	RPD Limit
Chloride	6.4		6.41		mg/L		0.2	15
Sulfate	9.4		9.35		mg/L		0.2	15

Method: 350.1 - Nitrogen, Ammonia

Lab Sample ID: MB 280-534545/55

Matrix: Water

Analysis Batch: 534545

Client Sample ID: Method Blank

Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Ammonia as N	ND		0.030		mg/L			04/30/21 14:44	1

Lab Sample ID: MB 280-534545/91

Matrix: Water

Analysis Batch: 534545

Client Sample ID: Method Blank

Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Ammonia as N	ND		0.030		mg/L			04/30/21 15:56	1

Eurofins TestAmerica, Denver

QC Sample Results

Client: Aspect Consulting
Project/Site: Hansville Landfill

Job ID: 280-147801-1

Method: 350.1 - Nitrogen, Ammonia (Continued)

Lab Sample ID: LCS 280-534545/53

Matrix: Water

Analysis Batch: 534545

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Ammonia as N	2.50	2.45		mg/L		98	90 - 110

Lab Sample ID: LCS 280-534545/89

Matrix: Water

Analysis Batch: 534545

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Ammonia as N	2.50	2.42		mg/L		97	90 - 110

Lab Sample ID: LCSD 280-534545/54

Matrix: Water

Analysis Batch: 534545

Client Sample ID: Lab Control Sample Dup

Prep Type: Total/NA

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Ammonia as N	2.50	2.42		mg/L		97	90 - 110	1	10

Lab Sample ID: LCSD 280-534545/90

Matrix: Water

Analysis Batch: 534545

Client Sample ID: Lab Control Sample Dup

Prep Type: Total/NA

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Ammonia as N	2.50	2.39		mg/L		96	90 - 110	1	10

Lab Sample ID: 280-147801-2 MS

Matrix: Water

Analysis Batch: 534545

Client Sample ID: MW5-042121

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Ammonia as N	ND		1.00	0.968		mg/L		97	90 - 110

Lab Sample ID: 280-147801-2 MSD

Matrix: Water

Analysis Batch: 534545

Client Sample ID: MW5-042121

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Ammonia as N	ND		1.00	0.980		mg/L		98	90 - 110	1	10

Method: SM 2320B - Alkalinity

Lab Sample ID: MB 280-534505/60

Matrix: Water

Analysis Batch: 534505

Client Sample ID: Method Blank

Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Alkalinity	ND		10		mg/L			04/30/21 04:37	1
Bicarbonate Alkalinity	ND		10		mg/L			04/30/21 04:37	1
Carbonate Alkalinity	ND		10		mg/L			04/30/21 04:37	1

Eurofins TestAmerica, Denver

QC Sample Results

Client: Aspect Consulting
Project/Site: Hansville Landfill

Job ID: 280-147801-1

Method: SM 2320B - Alkalinity (Continued)

Lab Sample ID: MB 280-534505/87

Matrix: Water

Analysis Batch: 534505

Client Sample ID: Method Blank

Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Alkalinity	ND		10		mg/L			04/30/21 08:31	1
Bicarbonate Alkalinity	ND		10		mg/L			04/30/21 08:31	1
Carbonate Alkalinity	ND		10		mg/L			04/30/21 08:31	1

Lab Sample ID: LCS 280-534505/58

Matrix: Water

Analysis Batch: 534505

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Total Alkalinity	200	204		mg/L		102	89 - 109

Lab Sample ID: LCS 280-534505/85

Matrix: Water

Analysis Batch: 534505

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Total Alkalinity	200	203		mg/L		102	89 - 109

Lab Sample ID: LCSD 280-534505/59

Matrix: Water

Analysis Batch: 534505

Client Sample ID: Lab Control Sample Dup

Prep Type: Total/NA

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Total Alkalinity	200	203		mg/L		102	89 - 109	0	10

Lab Sample ID: LCSD 280-534505/86

Matrix: Water

Analysis Batch: 534505

Client Sample ID: Lab Control Sample Dup

Prep Type: Total/NA

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Total Alkalinity	200	205		mg/L		102	89 - 109	1	10

Lab Sample ID: 280-147801-5 DU

Matrix: Water

Analysis Batch: 534505

Client Sample ID: SW4-042121

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	DU Result	DU Qualifier	Unit	D	RPD	RPD Limit
Total Alkalinity	160		161		mg/L		2	10

Lab Sample ID: MB 280-534783/6

Matrix: Water

Analysis Batch: 534783

Client Sample ID: Method Blank

Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Alkalinity	ND		10		mg/L			05/03/21 15:17	1
Bicarbonate Alkalinity	ND		10		mg/L			05/03/21 15:17	1
Carbonate Alkalinity	ND		10		mg/L			05/03/21 15:17	1

Eurofins TestAmerica, Denver

QC Sample Results

Client: Aspect Consulting
Project/Site: Hansville Landfill

Job ID: 280-147801-1

Method: SM 2320B - Alkalinity (Continued)

Lab Sample ID: LCS 280-534783/4

Matrix: Water

Analysis Batch: 534783

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Total Alkalinity	200	204		mg/L		102	89 - 109

Lab Sample ID: LCSD 280-534783/5

Matrix: Water

Analysis Batch: 534783

Client Sample ID: Lab Control Sample Dup

Prep Type: Total/NA

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Total Alkalinity	200	203		mg/L		101	89 - 109	1	10

Lab Sample ID: 280-147426-F-4 DU

Matrix: Water

Analysis Batch: 534783

Client Sample ID: Duplicate

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	DU Result	DU Qualifier	Unit	D	RPD	RPD Limit
Total Alkalinity	ND		ND		mg/L		NC	10

Method: SM 5310B - Organic Carbon, Total (TOC)

Lab Sample ID: MB 280-535323/35

Matrix: Water

Analysis Batch: 535323

Client Sample ID: Method Blank

Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Organic Carbon - Average	ND		1.0		mg/L			05/07/21 02:09	1

Lab Sample ID: MB 280-535323/4

Matrix: Water

Analysis Batch: 535323

Client Sample ID: Method Blank

Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Organic Carbon - Average	ND		1.0		mg/L			05/06/21 17:45	1

Lab Sample ID: LCS 280-535323/3

Matrix: Water

Analysis Batch: 535323

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Total Organic Carbon - Average	25.0	23.8		mg/L		95	88 - 112

Lab Sample ID: LCS 280-535323/34

Matrix: Water

Analysis Batch: 535323

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Total Organic Carbon - Average	25.0	23.9		mg/L		95	88 - 112

Eurofins TestAmerica, Denver

QC Sample Results

Client: Aspect Consulting
Project/Site: Hansville Landfill

Job ID: 280-147801-1

Method: SM 5310B - Organic Carbon, Total (TOC) (Continued)

Lab Sample ID: 280-147801-2 MS

Matrix: Water

Analysis Batch: 535323

Client Sample ID: MW5-042121

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits		
Total Organic Carbon - Average	ND		25.0	24.9		mg/L		98	88 - 112		

Lab Sample ID: 280-147801-2 MSD

Matrix: Water

Analysis Batch: 535323

Client Sample ID: MW5-042121

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Total Organic Carbon - Average	ND		25.0	24.8		mg/L		97	88 - 112	0	15

QC Association Summary

Client: Aspect Consulting
Project/Site: Hansville Landfill

Job ID: 280-147801-1

GC/MS VOA

Analysis Batch: 579097

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
280-147801-1	MW7-042121	Total/NA	Water	8260C SIM	
280-147801-2	MW5-042121	Total/NA	Water	8260C SIM	
280-147801-3	SW1-042121	Total/NA	Water	8260C SIM	
280-147801-4	MW12I-042121	Total/NA	Water	8260C SIM	
280-147801-5	SW4-042121	Total/NA	Water	8260C SIM	
280-147801-6	SW6-042121	Total/NA	Water	8260C SIM	
280-147801-7	MW13D-042121	Total/NA	Water	8260C SIM	
280-147801-8	SW7-042121	Total/NA	Water	8260C SIM	
280-147801-9	MW6-042121	Total/NA	Water	8260C SIM	
280-147801-10	MW14-042121	Total/NA	Water	8260C SIM	
280-147801-11	MW20DD-042121	Total/NA	Water	8260C SIM	
280-147801-12	TB1	Total/NA	Water	8260C SIM	
MB 480-579097/9	Method Blank	Total/NA	Water	8260C SIM	
LCS 480-579097/6	Lab Control Sample	Total/NA	Water	8260C SIM	
LCSD 480-579097/7	Lab Control Sample Dup	Total/NA	Water	8260C SIM	

Metals

Prep Batch: 534315

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
280-147801-1	MW7-042121	Dissolved	Water	3005A	
280-147801-2	MW5-042121	Dissolved	Water	3005A	
280-147801-3	SW1-042121	Dissolved	Water	3005A	
280-147801-4	MW12I-042121	Dissolved	Water	3005A	
280-147801-5	SW4-042121	Dissolved	Water	3005A	
280-147801-6	SW6-042121	Dissolved	Water	3005A	
280-147801-7	MW13D-042121	Dissolved	Water	3005A	
280-147801-8	SW7-042121	Dissolved	Water	3005A	
280-147801-9	MW6-042121	Dissolved	Water	3005A	
280-147801-10	MW14-042121	Dissolved	Water	3005A	
280-147801-11	MW20DD-042121	Dissolved	Water	3005A	
MB 280-534315/1-A	Method Blank	Total Recoverable	Water	3005A	
LCS 280-534315/2-A	Lab Control Sample	Total Recoverable	Water	3005A	
280-147870-F-1-B MS	Matrix Spike	Dissolved	Water	3005A	
280-147870-F-1-C MSD	Matrix Spike Duplicate	Dissolved	Water	3005A	

Analysis Batch: 534658

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
280-147801-1	MW7-042121	Dissolved	Water	6020	534315
280-147801-2	MW5-042121	Dissolved	Water	6020	534315
280-147801-3	SW1-042121	Dissolved	Water	6020	534315
280-147801-4	MW12I-042121	Dissolved	Water	6020	534315
280-147801-5	SW4-042121	Dissolved	Water	6020	534315
280-147801-6	SW6-042121	Dissolved	Water	6020	534315
280-147801-7	MW13D-042121	Dissolved	Water	6020	534315
280-147801-8	SW7-042121	Dissolved	Water	6020	534315
280-147801-9	MW6-042121	Dissolved	Water	6020	534315
280-147801-10	MW14-042121	Dissolved	Water	6020	534315
280-147801-11	MW20DD-042121	Dissolved	Water	6020	534315
MB 280-534315/1-A	Method Blank	Total Recoverable	Water	6020	534315
LCS 280-534315/2-A	Lab Control Sample	Total Recoverable	Water	6020	534315

Eurofins TestAmerica, Denver

QC Association Summary

Client: Aspect Consulting
Project/Site: Hansville Landfill

Job ID: 280-147801-1

Metals (Continued)

Analysis Batch: 534658 (Continued)

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
280-147870-F-1-B MS	Matrix Spike	Dissolved	Water	6020	534315
280-147870-F-1-C MSD	Matrix Spike Duplicate	Dissolved	Water	6020	534315

General Chemistry

Analysis Batch: 534505

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
280-147801-1	MW7-042121	Total/NA	Water	SM 2320B	
280-147801-2	MW5-042121	Total/NA	Water	SM 2320B	
280-147801-4	MW12I-042121	Total/NA	Water	SM 2320B	
280-147801-5	SW4-042121	Total/NA	Water	SM 2320B	
280-147801-6	SW6-042121	Total/NA	Water	SM 2320B	
280-147801-7	MW13D-042121	Total/NA	Water	SM 2320B	
280-147801-8	SW7-042121	Total/NA	Water	SM 2320B	
280-147801-9	MW6-042121	Total/NA	Water	SM 2320B	
280-147801-10	MW14-042121	Total/NA	Water	SM 2320B	
280-147801-11	MW20DD-042121	Total/NA	Water	SM 2320B	
MB 280-534505/60	Method Blank	Total/NA	Water	SM 2320B	
MB 280-534505/87	Method Blank	Total/NA	Water	SM 2320B	
LCS 280-534505/58	Lab Control Sample	Total/NA	Water	SM 2320B	
LCS 280-534505/85	Lab Control Sample	Total/NA	Water	SM 2320B	
LCSD 280-534505/59	Lab Control Sample Dup	Total/NA	Water	SM 2320B	
LCSD 280-534505/86	Lab Control Sample Dup	Total/NA	Water	SM 2320B	
280-147801-5 DU	SW4-042121	Total/NA	Water	SM 2320B	

Analysis Batch: 534545

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
280-147801-1	MW7-042121	Total/NA	Water	350.1	
280-147801-2	MW5-042121	Total/NA	Water	350.1	
280-147801-3	SW1-042121	Total/NA	Water	350.1	
280-147801-4	MW12I-042121	Total/NA	Water	350.1	
280-147801-5	SW4-042121	Total/NA	Water	350.1	
280-147801-6	SW6-042121	Total/NA	Water	350.1	
280-147801-7	MW13D-042121	Total/NA	Water	350.1	
280-147801-8	SW7-042121	Total/NA	Water	350.1	
280-147801-9	MW6-042121	Total/NA	Water	350.1	
280-147801-10	MW14-042121	Total/NA	Water	350.1	
280-147801-11	MW20DD-042121	Total/NA	Water	350.1	
MB 280-534545/55	Method Blank	Total/NA	Water	350.1	
MB 280-534545/91	Method Blank	Total/NA	Water	350.1	
LCS 280-534545/53	Lab Control Sample	Total/NA	Water	350.1	
LCS 280-534545/89	Lab Control Sample	Total/NA	Water	350.1	
LCSD 280-534545/54	Lab Control Sample Dup	Total/NA	Water	350.1	
LCSD 280-534545/90	Lab Control Sample Dup	Total/NA	Water	350.1	
280-147801-2 MS	MW5-042121	Total/NA	Water	350.1	
280-147801-2 MSD	MW5-042121	Total/NA	Water	350.1	

Analysis Batch: 534783

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
280-147801-3	SW1-042121	Total/NA	Water	SM 2320B	
MB 280-534783/6	Method Blank	Total/NA	Water	SM 2320B	

Eurofins TestAmerica, Denver

QC Association Summary

Client: Aspect Consulting
Project/Site: Hansville Landfill

Job ID: 280-147801-1

General Chemistry (Continued)

Analysis Batch: 534783 (Continued)

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
LCS 280-534783/4	Lab Control Sample	Total/NA	Water	SM 2320B	
LCSD 280-534783/5	Lab Control Sample Dup	Total/NA	Water	SM 2320B	
280-147426-F-4 DU	Duplicate	Total/NA	Water	SM 2320B	

Analysis Batch: 535323

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
280-147801-1	MW7-042121	Total/NA	Water	SM 5310B	
280-147801-2	MW5-042121	Total/NA	Water	SM 5310B	
280-147801-3	SW1-042121	Total/NA	Water	SM 5310B	
280-147801-4	MW12I-042121	Total/NA	Water	SM 5310B	
280-147801-5	SW4-042121	Total/NA	Water	SM 5310B	
280-147801-6	SW6-042121	Total/NA	Water	SM 5310B	
280-147801-7	MW13D-042121	Total/NA	Water	SM 5310B	
280-147801-8	SW7-042121	Total/NA	Water	SM 5310B	
280-147801-9	MW6-042121	Total/NA	Water	SM 5310B	
280-147801-10	MW14-042121	Total/NA	Water	SM 5310B	
280-147801-11	MW20DD-042121	Total/NA	Water	SM 5310B	
MB 280-535323/35	Method Blank	Total/NA	Water	SM 5310B	
MB 280-535323/4	Method Blank	Total/NA	Water	SM 5310B	
LCS 280-535323/3	Lab Control Sample	Total/NA	Water	SM 5310B	
LCS 280-535323/34	Lab Control Sample	Total/NA	Water	SM 5310B	
280-147801-2 MS	MW5-042121	Total/NA	Water	SM 5310B	
280-147801-2 MSD	MW5-042121	Total/NA	Water	SM 5310B	

Analysis Batch: 536250

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
280-147801-1	MW7-042121	Total/NA	Water	300.0	
280-147801-2	MW5-042121	Total/NA	Water	300.0	
280-147801-3	SW1-042121	Total/NA	Water	300.0	
280-147801-4	MW12I-042121	Total/NA	Water	300.0	
280-147801-5	SW4-042121	Total/NA	Water	300.0	
280-147801-6	SW6-042121	Total/NA	Water	300.0	
280-147801-7	MW13D-042121	Total/NA	Water	300.0	
280-147801-8	SW7-042121	Total/NA	Water	300.0	
280-147801-9	MW6-042121	Total/NA	Water	300.0	
280-147801-10	MW14-042121	Total/NA	Water	300.0	
280-147801-11	MW20DD-042121	Total/NA	Water	300.0	
MB 280-536250/6	Method Blank	Total/NA	Water	300.0	
LCS 280-536250/4	Lab Control Sample	Total/NA	Water	300.0	
LCSD 280-536250/5	Lab Control Sample Dup	Total/NA	Water	300.0	
MRL 280-536250/3	Lab Control Sample	Total/NA	Water	300.0	
280-147801-4 MS	MW12I-042121	Total/NA	Water	300.0	
280-147801-4 MSD	MW12I-042121	Total/NA	Water	300.0	
280-147801-11 MS	MW20DD-042121	Total/NA	Water	300.0	
280-147801-11 MSD	MW20DD-042121	Total/NA	Water	300.0	
280-147801-4 DU	MW12I-042121	Total/NA	Water	300.0	
280-147801-11 DU	MW20DD-042121	Total/NA	Water	300.0	

Lab Chronicle

Client: Aspect Consulting
Project/Site: Hansville Landfill

Job ID: 280-147801-1

Client Sample ID: MW7-042121

Lab Sample ID: 280-147801-1

Date Collected: 04/21/21 08:45

Matrix: Water

Date Received: 04/23/21 10:25

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	8260C SIM		1	25 mL	25 mL	579097	05/03/21 22:57	CDC	TAL BUF
Dissolved	Prep	3005A			50 mL	50 mL	534315	04/29/21 16:00	EC	TAL DEN
Dissolved	Analysis	6020		1			534658	04/30/21 17:09	LMT	TAL DEN
Total/NA	Analysis	300.0		1	10 mL	10 mL	536250	05/16/21 04:53	CJ	TAL DEN
Total/NA	Analysis	350.1		1	10 mL	10 mL	534545	04/30/21 15:30	QJB	TAL DEN
Total/NA	Analysis	SM 2320B		1			534505	04/30/21 07:38	QJB	TAL DEN
Total/NA	Analysis	SM 5310B		1	20 mL	20 mL	535323	05/07/21 01:38	RAF	TAL DEN

Client Sample ID: MW5-042121

Lab Sample ID: 280-147801-2

Date Collected: 04/21/21 10:20

Matrix: Water

Date Received: 04/23/21 10:25

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	8260C SIM		1	25 mL	25 mL	579097	05/03/21 23:21	CDC	TAL BUF
Dissolved	Prep	3005A			50 mL	50 mL	534315	04/29/21 16:00	EC	TAL DEN
Dissolved	Analysis	6020		1			534658	04/30/21 17:13	LMT	TAL DEN
Total/NA	Analysis	300.0		1	10 mL	10 mL	536250	05/16/21 05:07	CJ	TAL DEN
Total/NA	Analysis	350.1		1	10 mL	10 mL	534545	04/30/21 15:32	QJB	TAL DEN
Total/NA	Analysis	SM 2320B		1			534505	04/30/21 07:44	QJB	TAL DEN
Total/NA	Analysis	SM 5310B		1	20 mL	20 mL	535323	05/07/21 02:40	RAF	TAL DEN

Client Sample ID: SW1-042121

Lab Sample ID: 280-147801-3

Date Collected: 04/21/21 11:45

Matrix: Water

Date Received: 04/23/21 10:25

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	8260C SIM		1	25 mL	25 mL	579097	05/03/21 23:45	CDC	TAL BUF
Dissolved	Prep	3005A			50 mL	50 mL	534315	04/29/21 16:00	EC	TAL DEN
Dissolved	Analysis	6020		1			534658	04/30/21 17:16	LMT	TAL DEN
Total/NA	Analysis	300.0		1	10 mL	10 mL	536250	05/16/21 05:21	CJ	TAL DEN
Total/NA	Analysis	350.1		1	10 mL	10 mL	534545	04/30/21 15:38	QJB	TAL DEN
Total/NA	Analysis	SM 2320B		1			534783	05/03/21 17:56	QJB	TAL DEN
Total/NA	Analysis	SM 5310B		1	20 mL	20 mL	535323	05/07/21 03:59	RAF	TAL DEN

Client Sample ID: MW12I-042121

Lab Sample ID: 280-147801-4

Date Collected: 04/21/21 12:00

Matrix: Water

Date Received: 04/23/21 10:25

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	8260C SIM		1	25 mL	25 mL	579097	05/04/21 00:09	CDC	TAL BUF
Dissolved	Prep	3005A			50 mL	50 mL	534315	04/29/21 16:00	EC	TAL DEN
Dissolved	Analysis	6020		1			534658	04/30/21 17:20	LMT	TAL DEN
Total/NA	Analysis	300.0		1	10 mL	10 mL	536250	05/16/21 05:35	CJ	TAL DEN

Eurofins TestAmerica, Denver

Lab Chronicle

Client: Aspect Consulting
Project/Site: Hansville Landfill

Job ID: 280-147801-1

Client Sample ID: MW12I-042121

Lab Sample ID: 280-147801-4

Date Collected: 04/21/21 12:00

Matrix: Water

Date Received: 04/23/21 10:25

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	350.1		1	10 mL	10 mL	534545	04/30/21 16:00	QJB	TAL DEN
Total/NA	Analysis	SM 2320B		1			534505	04/30/21 07:56	QJB	TAL DEN
Total/NA	Analysis	SM 5310B		1	20 mL	20 mL	535323	05/07/21 04:18	RAF	TAL DEN

Client Sample ID: SW4-042121

Lab Sample ID: 280-147801-5

Date Collected: 04/21/21 12:30

Matrix: Water

Date Received: 04/23/21 10:25

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	8260C SIM		1	25 mL	25 mL	579097	05/04/21 00:33	CDC	TAL BUF
Dissolved	Prep	3005A			50 mL	50 mL	534315	04/29/21 16:00	EC	TAL DEN
Dissolved	Analysis	6020		1			534658	04/30/21 17:31	LMT	TAL DEN
Total/NA	Analysis	300.0		1	10 mL	10 mL	536250	05/16/21 06:59	CJ	TAL DEN
Total/NA	Analysis	350.1		1	10 mL	10 mL	534545	04/30/21 16:02	QJB	TAL DEN
Total/NA	Analysis	SM 2320B		1			534505	04/30/21 08:37	QJB	TAL DEN
Total/NA	Analysis	SM 5310B		1	20 mL	20 mL	535323	05/07/21 04:33	RAF	TAL DEN

Client Sample ID: SW6-042121

Lab Sample ID: 280-147801-6

Date Collected: 04/21/21 13:15

Matrix: Water

Date Received: 04/23/21 10:25

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	8260C SIM		1	25 mL	25 mL	579097	05/04/21 00:57	CDC	TAL BUF
Dissolved	Prep	3005A			50 mL	50 mL	534315	04/29/21 16:00	EC	TAL DEN
Dissolved	Analysis	6020		1			534658	04/30/21 17:34	LMT	TAL DEN
Total/NA	Analysis	300.0		1	10 mL	10 mL	536250	05/16/21 07:13	CJ	TAL DEN
Total/NA	Analysis	350.1		1	10 mL	10 mL	534545	04/30/21 16:04	QJB	TAL DEN
Total/NA	Analysis	SM 2320B		1			534505	04/30/21 08:50	QJB	TAL DEN
Total/NA	Analysis	SM 5310B		1	20 mL	20 mL	535323	05/07/21 04:47	RAF	TAL DEN

Client Sample ID: MW13D-042121

Lab Sample ID: 280-147801-7

Date Collected: 04/21/21 13:00

Matrix: Water

Date Received: 04/23/21 10:25

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	8260C SIM		1	25 mL	25 mL	579097	05/04/21 01:21	CDC	TAL BUF
Dissolved	Prep	3005A			50 mL	50 mL	534315	04/29/21 16:00	EC	TAL DEN
Dissolved	Analysis	6020		1			534658	04/30/21 17:38	LMT	TAL DEN
Total/NA	Analysis	300.0		1	10 mL	10 mL	536250	05/16/21 07:27	CJ	TAL DEN
Total/NA	Analysis	350.1		1	10 mL	10 mL	534545	04/30/21 16:06	QJB	TAL DEN
Total/NA	Analysis	SM 2320B		1			534505	04/30/21 08:56	QJB	TAL DEN
Total/NA	Analysis	SM 5310B		1	20 mL	20 mL	535323	05/07/21 05:05	RAF	TAL DEN

Eurofins TestAmerica, Denver

Lab Chronicle

Client: Aspect Consulting
Project/Site: Hansville Landfill

Job ID: 280-147801-1

Client Sample ID: SW7-042121

Lab Sample ID: 280-147801-8

Date Collected: 04/21/21 14:20

Matrix: Water

Date Received: 04/23/21 10:25

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	8260C SIM		1	25 mL	25 mL	579097	05/04/21 01:46	CDC	TAL BUF
Dissolved	Prep	3005A			50 mL	50 mL	534315	04/29/21 16:00	EC	TAL DEN
Dissolved	Analysis	6020		1			534658	04/30/21 17:41	LMT	TAL DEN
Total/NA	Analysis	300.0		1	10 mL	10 mL	536250	05/16/21 07:41	CJ	TAL DEN
Total/NA	Analysis	350.1		1	10 mL	10 mL	534545	04/30/21 16:08	QJB	TAL DEN
Total/NA	Analysis	SM 2320B		1			534505	04/30/21 09:01	QJB	TAL DEN
Total/NA	Analysis	SM 5310B		1	20 mL	20 mL	535323	05/07/21 05:20	RAF	TAL DEN

Client Sample ID: MW6-042121

Lab Sample ID: 280-147801-9

Date Collected: 04/21/21 16:00

Matrix: Water

Date Received: 04/23/21 10:25

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	8260C SIM		1	25 mL	25 mL	579097	05/04/21 02:10	CDC	TAL BUF
Dissolved	Prep	3005A			50 mL	50 mL	534315	04/29/21 16:00	EC	TAL DEN
Dissolved	Analysis	6020		1			534658	04/30/21 17:45	LMT	TAL DEN
Total/NA	Analysis	300.0		1	10 mL	10 mL	536250	05/16/21 07:55	CJ	TAL DEN
Total/NA	Analysis	350.1		1	10 mL	10 mL	534545	04/30/21 16:10	QJB	TAL DEN
Total/NA	Analysis	SM 2320B		1			534505	04/30/21 09:07	QJB	TAL DEN
Total/NA	Analysis	SM 5310B		1	20 mL	20 mL	535323	05/07/21 05:37	RAF	TAL DEN

Client Sample ID: MW14-042121

Lab Sample ID: 280-147801-10

Date Collected: 04/21/21 16:15

Matrix: Water

Date Received: 04/23/21 10:25

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	8260C SIM		1	25 mL	25 mL	579097	05/04/21 02:34	CDC	TAL BUF
Dissolved	Prep	3005A			50 mL	50 mL	534315	04/29/21 16:00	EC	TAL DEN
Dissolved	Analysis	6020		1			534658	04/30/21 17:48	LMT	TAL DEN
Total/NA	Analysis	300.0		1	10 mL	10 mL	536250	05/16/21 08:09	CJ	TAL DEN
Total/NA	Analysis	350.1		1	10 mL	10 mL	534545	04/30/21 16:12	QJB	TAL DEN
Total/NA	Analysis	SM 2320B		1			534505	04/30/21 09:13	QJB	TAL DEN
Total/NA	Analysis	SM 5310B		1	20 mL	20 mL	535323	05/07/21 05:54	RAF	TAL DEN

Client Sample ID: MW20DD-042121

Lab Sample ID: 280-147801-11

Date Collected: 04/21/21 00:00

Matrix: Water

Date Received: 04/23/21 10:25

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	8260C SIM		1	25 mL	25 mL	579097	05/04/21 02:58	CDC	TAL BUF
Dissolved	Prep	3005A			50 mL	50 mL	534315	04/29/21 16:00	EC	TAL DEN
Dissolved	Analysis	6020		1			534658	04/30/21 17:52	LMT	TAL DEN
Total/NA	Analysis	300.0		1	10 mL	10 mL	536250	05/16/21 08:23	CJ	TAL DEN

Eurofins TestAmerica, Denver

Lab Chronicle

Client: Aspect Consulting
Project/Site: Hansville Landfill

Job ID: 280-147801-1

Client Sample ID: MW20DD-042121

Lab Sample ID: 280-147801-11

Date Collected: 04/21/21 00:00

Matrix: Water

Date Received: 04/23/21 10:25

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	350.1		1	10 mL	10 mL	534545	04/30/21 16:14	QJB	TAL DEN
Total/NA	Analysis	SM 2320B		1			534505	04/30/21 09:19	QJB	TAL DEN
Total/NA	Analysis	SM 5310B		1	20 mL	20 mL	535323	05/07/21 06:10	RAF	TAL DEN

Client Sample ID: TB1

Lab Sample ID: 280-147801-12

Date Collected: 04/21/21 08:45

Matrix: Water

Date Received: 04/23/21 10:25

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	8260C SIM		1	25 mL	25 mL	579097	05/04/21 03:23	CDC	TAL BUF

Laboratory References:

SC0056 = Analytical Resources, Inc, 4611 South 134th Place, Suite 100, Tukwila, WA 98168, TEL (206)695-6200

TAL BUF = Eurofins TestAmerica, Buffalo, 10 Hazelwood Drive, Amherst, NY 14228-2298, TEL (716)691-2600

TAL DEN = Eurofins TestAmerica, Denver, 4955 Yarrow Street, Arvada, CO 80002, TEL (303)736-0100



06 May 2021

Betsy Sara
Test America - Denver
4955 Yarrow Street
Arvada, CO 80002

RE: Hansville

Please find enclosed sample receipt documentation and analytical results for samples from the project referenced above.

Sample analyses were performed according to ARI's Quality Assurance Plan and any provided project specific Quality Assurance Plan. Each analytical section of this report has been approved and reviewed by an analytical peer, the appropriate Laboratory Supervisor or qualified substitute, and a technical reviewer.

Should you have any questions or problems, please feel free to contact us at your convenience.

Associated Work Order(s)
21D0237

Associated SDG ID(s)
N/A

I certify that this data package is in compliance with the terms and conditions of the contract, both technically and for completeness, for other than the conditions detailed in the enclose Narrative. ARI, an accredited laboratory, certifies that the report results for which ARI is accredited meets all the requirements of the accrediting body. A list of certified analyses, accreditations, and expiration dates is included in this report.

Release of the data contained in this hardcopy data package has been authorized by the Laboratory Manager or his/her designee, as verified by the following signature.

Analytical Resources, Inc.

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety.



2100237

Chain of Custody Record



Environment Testing
 TestAmerica

Client Information		Sampler: <u>Dylan Branscom / Chelsea Bush</u>		Lab PM: <u>Sara, Betsy A</u>		Carrier Tracking No(s):		COC No: <u>280-23414-6845.1</u>	
Client Contact: <u>Meilani Lanier-Kamahao</u>		Phone: <u>206-413-5408</u>		E-Mail: <u>Betsy.Sara@Eurofinset.com</u>				Page: <u>1/1</u>	
Company: <u>Aspect Consulting, LLC</u>		Address: <u>350 Madison Ave N</u>		City: <u>Bainbridge Island</u>		State, Zip: <u>WA, 98110</u>		Job #:	
Email: <u>mlkamahao@aspectconsulting.com</u>		PO #: <u></u>		Purchase Order not required		WO #: <u></u>		Analysis Requested	
Project Name: <u>Hansville Landfill</u>		Project #/skip sites/events: <u>28006013 - 2Q/3Q/4Q Sampling</u>		SSOW#: <u></u>					
Site: <u>Washington</u>									

Sample Identification	Sample Date	Sample Time	Sample Type (C=Comp, G=grab)	Matrix (W=water, S=solid, O=waste, A=air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	8260C SIM - Vinyl Chloride (TA Buffalo)	Disolved Metals	Ammonia/TOC	Alkyls/Cl/SO4	Ortho-phosphate (field filtered)- direct sub to ARI	Dissolved Arsenic - direct sub to ARI	Nitrate/Nitrite (C) - direct sub to ARI	Total Number of containers	Special Instructions/Note:
MW-7-042121	4/21/21	0845		W	X						X	X	N	X	
MW-5-042121		1020													
SW-1-042121		1145													
MW-12I-042121		1200													
SW-4-042121		1230													
SW-6-042121		1315													
MW-13D-042121		1300													
SW-7-042121		1420													
MW-6-042121		1600													
MW-14-042121		1615													
MW-20DD-042121															

Possible Hazard Identification <input type="checkbox"/> Non-Hazard <input type="checkbox"/> Flammable <input type="checkbox"/> Skin Irritant <input type="checkbox"/> Poison B <input type="checkbox"/> Unknown <input type="checkbox"/> Radiological		Sample Disposal (A fee may be assessed if samples are retained longer than 1 month) <input type="checkbox"/> Return To Client <input type="checkbox"/> Disposal By Lab <input type="checkbox"/> Archive For _____ Months	
Deliverable Requested: I, II, III, IV, Other (specify) _____		Special Instructions/QC Requirements: _____	
Empty Kit Relinquished by: _____ Date: _____		Method of Shipment: _____	
Relinquished by: _____ Date/Time: <u>4/22/21 1118</u> Company: <u>ARI</u>		Received by: _____ Date/Time: _____ Company: _____	
Relinquished by: _____ Date/Time: _____ Company: _____		Received by: _____ Date/Time: _____ Company: _____	
Relinquished by: _____ Date/Time: _____ Company: _____		Received by: _____ Date/Time: _____ Company: _____	
Custody Seals Intact: <input type="checkbox"/> Yes <input type="checkbox"/> No		Cooler Temperature(s) °C and Other Remarks: _____	



Test America - Denver
4955 Yarrow Street
Arvada CO, 80002

Project: Hansville
Project Number: [none]
Project Manager: Betsy Sara

Reported:
06-May-2021 14:53

ANALYTICAL REPORT FOR SAMPLES

Sample ID	Laboratory ID	Matrix	Date Sampled	Date Received
MW-7-042121	21D0237-01	Water	21-Apr-2021 08:45	22-Apr-2021 11:18
MW-5-042121	21D0237-02	Water	21-Apr-2021 10:20	22-Apr-2021 11:18
SW-1-042121	21D0237-03	Water	21-Apr-2021 11:45	22-Apr-2021 11:18
MW-12I-042121	21D0237-04	Water	21-Apr-2021 12:00	22-Apr-2021 11:18
SW-4-042121	21D0237-05	Water	21-Apr-2021 12:30	22-Apr-2021 11:18
SW-6-042121	21D0237-06	Water	21-Apr-2021 13:15	22-Apr-2021 11:18
MW-13D-042121	21D0237-07	Water	21-Apr-2021 13:00	22-Apr-2021 11:18
SW-7-042121	21D0237-08	Water	21-Apr-2021 14:20	22-Apr-2021 11:18
MW-6-042121	21D0237-09	Water	21-Apr-2021 16:00	22-Apr-2021 11:18
MW-14-042121	21D0237-10	Water	21-Apr-2021 16:15	22-Apr-2021 11:18
MW-20DD-042121	21D0237-11	Water	21-Apr-2021 00:00	22-Apr-2021 11:18



Test America - Denver
4955 Yarrow Street
Arvada CO, 80002

Project: Hansville
Project Number: [none]
Project Manager: Betsy Sara

Reported:
06-May-2021 14:53

Work Order Case Narrative

Client: Test America - Denver

Project: Hansville

Work Order: 21D0237

Sample receipt

Samples as listed on the preceding page were received 22-Apr-2021 11:18 under ARI work order 21D0237. For details regarding sample receipt, please refer to the Cooler Receipt Form.

Total Metals - EPA Method 200.8

The sample(s) were digested and analyzed within the recommended holding times.

Initial and continuing calibrations were within method requirements.

The method blank(s) were clean at the reporting limits.

The blank spike (BS/LCS) percent recoveries were within control limits.

Sample specific QC was performed in association with sample 21D0237-01 in batch BJD0664. The matrix spike (MS) percent recoveries and the duplicate (DUP) relative percent difference (RPD) were within advisory control limits.

Wet Chemistry

The sample(s) were prepared and analyzed within the recommended holding times.

Initial and continuing calibrations were within method requirements.

The method blank(s) were clean at the reporting limits.

The blank spike (BS/LCS) percent recoveries were within control limits.

Sample specific QC was performed in association with sample 21D0237-01 in Anions batch BJD0547. The matrix spike (MS) percent recoveries and the duplicate (DUP) relative percent difference (RPD) were within advisory control limits.



Analytical Resources, Incorporated
Analytical Chemists and Consultants

Cooler Receipt Form

ARI Client: Eurofins - Denver

Project Name: Hansville Landfill

COC No(s): _____ NA

Delivered by: Fed-Ex UPS Courier Hand Delivered Other: _____

Assigned ARI Job No: 2100237

Tracking No: _____ NA

Preliminary Examination Phase:

Were intact, properly signed and dated custody seals attached to the outside of the cooler? YES NO

Were custody papers included with the cooler? YES NO

Were custody papers properly filled out (ink, signed, etc.) YES NO

Temperature of Cooler(s) (°C) (recommended 2.0-6.0 °C for chemistry)

Time 11:18 0.1

If cooler temperature is out of compliance fill out form 00070F Temp Gun ID#: DOO 5206

Cooler Accepted by: SC Date: 4/22/21 Time: 11:18

Complete custody forms and attach all shipping documents

Log-In Phase:

Was a temperature blank included in the cooler? SC YES NO

What kind of packing material was used? ... Bubble Wrap Wet Ice Gel Packs Baggies Foam Block Paper Other: Trash Bag

Was sufficient ice used (if appropriate)? NA YES NO

How were bottles sealed in plastic bags? Individually Grouped Not

Did all bottles arrive in good condition (unbroken)? YES NO

Were all bottle labels complete and legible? YES NO

Did the number of containers listed on COC match with the number of containers received? YES NO

Did all bottle labels and tags agree with custody papers? YES NO

Were all bottles used correct for the requested analyses? YES NO

Do any of the analyses (bottles) require preservation? (attach preservation sheet, excluding VOCs) ... NA YES NO

Were all VOC vials free of air bubbles? NA YES NO

Was sufficient amount of sample sent in each bottle? YES NO

Date VOC Trip Blank was made at ARI: NA

Were the sample(s) split by ARI? NA YES Date/Time: _____ Equipment: _____ Split by: _____

Samples Logged by: SC Date: 4/22/21 Time: 11:53 Labels checked by: SC

**** Notify Project Manager of discrepancies or concerns ****

Sample ID on Bottle	Sample ID on COC	Sample ID on Bottle	Sample ID on COC

Additional Notes, Discrepancies, & Resolutions:

By: _____ Date: _____



WORK ORDER

21D0237

Client: Test America - Denver

Project Manager: Shelly Fishel

Project: Hansville

Project Number: 28006013-2Q/3Q/4Q Sampling

Preservation Confirmation

Container ID	Container Type	pH	
21D0237-01 A	Miscellaneous container, 1:1 HN03 (FF)	< 2	Pass (P)
21D0237-01 B	Miscellaneous Container		
21D0237-01 C	Miscellaneous Container (FF)		
21D0237-02 A	Miscellaneous container, 1:1 HN03 (FF)	< 2	P
21D0237-02 B	Miscellaneous Container		
21D0237-02 C	Miscellaneous Container (FF)		
21D0237-03 A	Miscellaneous container, 1:1 HN03 (FF)	< 2	P
21D0237-03 B	Miscellaneous Container		
21D0237-03 C	Miscellaneous Container (FF)		
21D0237-04 A	Miscellaneous container, 1:1 HN03 (FF)	< 2	P
21D0237-04 B	Miscellaneous Container		
21D0237-04 C	Miscellaneous Container (FF)		
21D0237-05 A	Miscellaneous container, 1:1 HN03 (FF)	< 2	P
21D0237-05 B	Miscellaneous Container		
21D0237-05 C	Miscellaneous Container (FF)		
21D0237-06 A	Miscellaneous container, 1:1 HN03 (FF)	< 2	P
21D0237-06 B	Miscellaneous Container		
21D0237-06 C	Miscellaneous Container (FF)		
21D0237-07 A	Miscellaneous container, 1:1 HN03 (FF)	< 2	P
21D0237-07 B	Miscellaneous Container		
21D0237-07 C	Miscellaneous Container (FF)		
21D0237-08 A	Miscellaneous container, 1:1 HN03 (FF)	< 2	P
21D0237-08 B	Miscellaneous Container		
21D0237-08 C	Miscellaneous Container (FF)		
21D0237-09 A	Miscellaneous container, 1:1 HN03 (FF)	< 2	P
21D0237-09 B	Miscellaneous Container		
21D0237-09 C	Miscellaneous Container (FF)		
21D0237-10 A	Miscellaneous container, 1:1 HN03 (FF)	< 2	P
21D0237-10 B	Miscellaneous Container		
21D0237-10 C	Miscellaneous Container (FF)		
21D0237-11 A	Miscellaneous container, 1:1 HN03 (FF)	< 2	P
21D0237-11 B	Miscellaneous Container		
21D0237-11 C	Miscellaneous Container (FF)		



WORK ORDER

21D0237

Client: Test America - Denver

Project Manager: Shelly Fishel

Project: Hansville

Project Number: 28006013-2Q/3Q/4Q Sampling

SC
Preservation Confirmed By

4/22/21
Date



Test America - Denver
4955 Yarrow Street
Arvada CO, 80002

Project: Hansville
Project Number: [none]
Project Manager: Betsy Sara

Reported:
06-May-2021 14:53

MW-7-042121
21D0237-01 (Water)

Metals and Metallic Compounds (dissolved)

Method: EPA 200.8 UCT-KED

Sampled: 04/21/2021 08:45

Instrument: ICPMS2 Analyst: MCB

Analyzed: 04/28/2021 19:14

Sample Preparation: Preparation Method: REN EPA 600/4-79-020 4.1.4 HNO3 matrix
Preparation Batch: BJD0664 Sample Size: 25 mL
Prepared: 04/28/2021 Final Volume: 25 mL

Extract ID: 21D0237-01 A 01

Analyte	CAS Number	Dilution	Reporting Limit	Result	Units	Notes
Arsenic, Dissolved	7440-38-2	1	0.000200	0.00111	mg/L	



Test America - Denver
4955 Yarrow Street
Arvada CO, 80002

Project: Hansville
Project Number: [none]
Project Manager: Betsy Sara

Reported:
06-May-2021 14:53

MW-7-042121
21D0237-01 (Water)

Wet Chemistry

Method: EPA 300.0

Sampled: 04/21/2021 08:45

Instrument: IC930 Analyst: WCW

Analyzed: 04/22/2021 15:24

Sample Preparation:

Preparation Method: No Prep Wet Chem

Extract ID: 21D0237-01 B

Preparation Batch: BJD0547

Sample Size: 10 mL

Prepared: 04/22/2021

Final Volume: 10 mL

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Nitrate-N	14797-55-8	1	0.100	0.100	0.184	mg/L	

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Nitrite-N	14797-65-0	1	0.100	0.100	ND	mg/L	U

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Orthophosphorus	1426-54-42	1	0.10	0.10	ND	mg-P/L	U



Test America - Denver
4955 Yarrow Street
Arvada CO, 80002

Project: Hansville
Project Number: [none]
Project Manager: Betsy Sara

Reported:
06-May-2021 14:53

MW-5-042121
21D0237-02 (Water)

Metals and Metallic Compounds (dissolved)

Method: EPA 200.8 UCT-KED

Sampled: 04/21/2021 10:20

Instrument: ICPMS2 Analyst: MCB

Analyzed: 04/28/2021 18:10

Sample Preparation: Preparation Method: REN EPA 600/4-79-020 4.1.4 HNO₃ matrix
Preparation Batch: BJD0664 Sample Size: 25 mL
Prepared: 04/28/2021 Final Volume: 25 mL

Extract ID: 21D0237-02 A 01

Analyte	CAS Number	Dilution	Reporting Limit	Result	Units	Notes
Arsenic, Dissolved	7440-38-2	1	0.000200	0.00182	mg/L	



Test America - Denver
4955 Yarrow Street
Arvada CO, 80002

Project: Hansville
Project Number: [none]
Project Manager: Betsy Sara

Reported:
06-May-2021 14:53

MW-5-042121
21D0237-02 (Water)

Wet Chemistry

Method: EPA 300.0

Sampled: 04/21/2021 10:20

Instrument: IC930 Analyst: WCW

Analyzed: 04/22/2021 16:25

Sample Preparation:

Preparation Method: No Prep Wet Chem

Extract ID: 21D0237-02 B

Preparation Batch: BJD0547

Sample Size: 10 mL

Prepared: 04/22/2021

Final Volume: 10 mL

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Nitrate-N	14797-55-8	1	0.100	0.100	2.54	mg/L	

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Nitrite-N	14797-65-0	1	0.100	0.100	ND	mg/L	U

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Orthophosphorus	1426-54-42	1	0.10	0.10	ND	mg-P/L	U



Test America - Denver
4955 Yarrow Street
Arvada CO, 80002

Project: Hansville
Project Number: [none]
Project Manager: Betsy Sara

Reported:
06-May-2021 14:53

SW-1-042121
21D0237-03 (Water)

Metals and Metallic Compounds (dissolved)

Method: EPA 200.8 UCT-KED

Sampled: 04/21/2021 11:45

Instrument: ICPMS2 Analyst: MCB

Analyzed: 04/29/2021 17:44

Sample Preparation: Preparation Method: REN EPA 600/4-79-020 4.1.4 HNO₃ matrix
Preparation Batch: BJD0664 Sample Size: 25 mL
Prepared: 04/28/2021 Final Volume: 25 mL

Extract ID: 21D0237-03 A 01

Analyte	CAS Number	Dilution	Reporting Limit	Result	Units	Notes
Arsenic, Dissolved	7440-38-2	1	0.000200	0.00106	mg/L	



Test America - Denver
4955 Yarrow Street
Arvada CO, 80002

Project: Hansville
Project Number: [none]
Project Manager: Betsy Sara

Reported:
06-May-2021 14:53

SW-1-042121
21D0237-03 (Water)

Wet Chemistry

Method: EPA 300.0

Sampled: 04/21/2021 11:45

Instrument: IC930 Analyst: WCW

Analyzed: 04/22/2021 16:45

Sample Preparation:

Preparation Method: No Prep Wet Chem

Extract ID: 21D0237-03 B

Preparation Batch: BJD0547

Sample Size: 10 mL

Prepared: 04/22/2021

Final Volume: 10 mL

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Nitrate-N	14797-55-8	1	0.100	0.100	2.36	mg/L	

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Nitrite-N	14797-65-0	1	0.100	0.100	ND	mg/L	U

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Orthophosphorus	1426-54-42	1	0.10	0.10	ND	mg-P/L	U



Test America - Denver
4955 Yarrow Street
Arvada CO, 80002

Project: Hansville
Project Number: [none]
Project Manager: Betsy Sara

Reported:
06-May-2021 14:53

MW-12I-042121
21D0237-04 (Water)

Metals and Metallic Compounds (dissolved)

Method: EPA 200.8 UCT-KED

Sampled: 04/21/2021 12:00

Instrument: ICPMS2 Analyst: MCB

Analyzed: 04/28/2021 18:18

Sample Preparation: Preparation Method: REN EPA 600/4-79-020 4.1.4 HNO3 matrix
Preparation Batch: BJD0664 Sample Size: 25 mL
Prepared: 04/28/2021 Final Volume: 25 mL

Extract ID: 21D0237-04 A 01

Analyte	CAS Number	Dilution	Reporting Limit	Result	Units	Notes
Arsenic, Dissolved	7440-38-2	1	0.000200	0.00257	mg/L	



Test America - Denver
4955 Yarrow Street
Arvada CO, 80002

Project: Hansville
Project Number: [none]
Project Manager: Betsy Sara

Reported:
06-May-2021 14:53

MW-12I-042121

21D0237-04 (Water)

Wet Chemistry

Method: EPA 300.0

Sampled: 04/21/2021 12:00

Instrument: IC930 Analyst: WCW

Analyzed: 04/22/2021 17:05

Sample Preparation:

Preparation Method: No Prep Wet Chem

Extract ID: 21D0237-04 B

Preparation Batch: BJD0547

Sample Size: 10 mL

Prepared: 04/22/2021

Final Volume: 10 mL

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Nitrate-N	14797-55-8	1	0.100	0.100	ND	mg/L	U

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Nitrite-N	14797-65-0	1	0.100	0.100	ND	mg/L	U

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Orthophosphorus	1426-54-42	1	0.10	0.10	ND	mg-P/L	U



Test America - Denver
4955 Yarrow Street
Arvada CO, 80002

Project: Hansville
Project Number: [none]
Project Manager: Betsy Sara

Reported:
06-May-2021 14:53

SW-4-042121
21D0237-05 (Water)

Metals and Metallic Compounds (dissolved)

Method: EPA 200.8 UCT-KED

Sampled: 04/21/2021 12:30

Instrument: ICPMS2 Analyst: MCB

Analyzed: 04/28/2021 18:24

Sample Preparation: Preparation Method: REN EPA 600/4-79-020 4.1.4 HNO₃ matrix
Preparation Batch: BJD0664 Sample Size: 25 mL
Prepared: 04/28/2021 Final Volume: 25 mL

Extract ID: 21D0237-05 A 01

Analyte	CAS Number	Dilution	Reporting Limit	Result	Units	Notes
Arsenic, Dissolved	7440-38-2	1	0.000200	0.00190	mg/L	



Test America - Denver
4955 Yarrow Street
Arvada CO, 80002

Project: Hansville
Project Number: [none]
Project Manager: Betsy Sara

Reported:
06-May-2021 14:53

SW-4-042121
21D0237-05 (Water)

Wet Chemistry

Method: EPA 300.0

Sampled: 04/21/2021 12:30

Instrument: IC930 Analyst: WCW

Analyzed: 04/22/2021 17:25

Sample Preparation:

Preparation Method: No Prep Wet Chem

Extract ID: 21D0237-05 B

Preparation Batch: BJD0547

Sample Size: 10 mL

Prepared: 04/22/2021

Final Volume: 10 mL

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Nitrate-N	14797-55-8	1	0.100	0.100	0.917	mg/L	

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Nitrite-N	14797-65-0	1	0.100	0.100	ND	mg/L	U

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Orthophosphorus	1426-54-42	1	0.10	0.10	ND	mg-P/L	U



Test America - Denver
4955 Yarrow Street
Arvada CO, 80002

Project: Hansville
Project Number: [none]
Project Manager: Betsy Sara

Reported:
06-May-2021 14:53

SW-6-042121
21D0237-06 (Water)

Metals and Metallic Compounds (dissolved)

Method: EPA 200.8 UCT-KED

Sampled: 04/21/2021 13:15

Instrument: ICPMS2 Analyst: MCB

Analyzed: 04/28/2021 18:28

Sample Preparation: Preparation Method: REN EPA 600/4-79-020 4.1.4 HNO₃ matrix
Preparation Batch: BJD0664 Sample Size: 25 mL
Prepared: 04/28/2021 Final Volume: 25 mL

Extract ID: 21D0237-06 A 01

Analyte	CAS Number	Dilution	Reporting Limit	Result	Units	Notes
Arsenic, Dissolved	7440-38-2	1	0.000200	0.00341	mg/L	



Test America - Denver
4955 Yarrow Street
Arvada CO, 80002

Project: Hansville
Project Number: [none]
Project Manager: Betsy Sara

Reported:
06-May-2021 14:53

SW-6-042121
21D0237-06 (Water)

Wet Chemistry

Method: EPA 300.0

Sampled: 04/21/2021 13:15

Instrument: IC930 Analyst: WCW

Analyzed: 04/22/2021 18:25

Sample Preparation:

Preparation Method: No Prep Wet Chem

Extract ID: 21D0237-06 B

Preparation Batch: BJD0547

Sample Size: 10 mL

Prepared: 04/22/2021

Final Volume: 10 mL

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Nitrate-N	14797-55-8	1	0.100	0.100	ND	mg/L	U

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Nitrite-N	14797-65-0	1	0.100	0.100	ND	mg/L	U

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Orthophosphorus	1426-54-42	1	0.10	0.10	ND	mg-P/L	U



Test America - Denver
4955 Yarrow Street
Arvada CO, 80002

Project: Hansville
Project Number: [none]
Project Manager: Betsy Sara

Reported:
06-May-2021 14:53

MW-13D-042121

21D0237-07 (Water)

Metals and Metallic Compounds (dissolved)

Method: EPA 200.8 UCT-KED

Sampled: 04/21/2021 13:00

Instrument: ICPMS2 Analyst: MCB

Analyzed: 04/28/2021 18:32

Sample Preparation: Preparation Method: REN EPA 600/4-79-020 4.1.4 HNO₃ matrix
Preparation Batch: BJD0664 Sample Size: 25 mL
Prepared: 04/28/2021 Final Volume: 25 mL

Extract ID: 21D0237-07 A 01

Analyte	CAS Number	Dilution	Reporting Limit	Result	Units	Notes
Arsenic, Dissolved	7440-38-2	1	0.000200	0.00521	mg/L	



Test America - Denver
4955 Yarrow Street
Arvada CO, 80002

Project: Hansville
Project Number: [none]
Project Manager: Betsy Sara

Reported:
06-May-2021 14:53

MW-13D-042121

21D0237-07 (Water)

Wet Chemistry

Method: EPA 300.0

Sampled: 04/21/2021 13:00

Instrument: IC930 Analyst: WCW

Analyzed: 04/22/2021 18:45

Sample Preparation:

Preparation Method: No Prep Wet Chem

Extract ID: 21D0237-07 B

Preparation Batch: BJD0547

Sample Size: 10 mL

Prepared: 04/22/2021

Final Volume: 10 mL

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Nitrate-N	14797-55-8	1	0.100	0.100	ND	mg/L	U

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Nitrite-N	14797-65-0	1	0.100	0.100	ND	mg/L	U

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Orthophosphorus	1426-54-42	1	0.10	0.10	ND	mg-P/L	U



Test America - Denver
4955 Yarrow Street
Arvada CO, 80002

Project: Hansville
Project Number: [none]
Project Manager: Betsy Sara

Reported:
06-May-2021 14:53

SW-7-042121
21D0237-08 (Water)

Metals and Metallic Compounds (dissolved)

Method: EPA 200.8 UCT-KED

Sampled: 04/21/2021 14:20

Instrument: ICPMS2 Analyst: MCB

Analyzed: 04/28/2021 18:37

Sample Preparation: Preparation Method: REN EPA 600/4-79-020 4.1.4 HNO₃ matrix
Preparation Batch: BJD0664 Sample Size: 25 mL
Prepared: 04/28/2021 Final Volume: 25 mL

Extract ID: 21D0237-08 A 01

Analyte	CAS Number	Dilution	Reporting Limit	Result	Units	Notes
Arsenic, Dissolved	7440-38-2	1	0.000200	0.00151	mg/L	



Test America - Denver
4955 Yarrow Street
Arvada CO, 80002

Project: Hansville
Project Number: [none]
Project Manager: Betsy Sara

Reported:
06-May-2021 14:53

SW-7-042121
21D0237-08 (Water)

Wet Chemistry

Method: EPA 300.0

Sampled: 04/21/2021 14:20

Instrument: IC930 Analyst: WCW

Analyzed: 04/22/2021 19:05

Sample Preparation:

Preparation Method: No Prep Wet Chem

Extract ID: 21D0237-08 B

Preparation Batch: BJD0547

Sample Size: 10 mL

Prepared: 04/22/2021

Final Volume: 10 mL

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Nitrate-N	14797-55-8	1	0.100	0.100	0.566	mg/L	

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Nitrite-N	14797-65-0	1	0.100	0.100	ND	mg/L	U

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Orthophosphorus	1426-54-42	1	0.10	0.10	ND	mg-P/L	U



Test America - Denver
4955 Yarrow Street
Arvada CO, 80002

Project: Hansville
Project Number: [none]
Project Manager: Betsy Sara

Reported:
06-May-2021 14:53

MW-6-042121
21D0237-09 (Water)

Metals and Metallic Compounds (dissolved)

Method: EPA 200.8 UCT-KED

Sampled: 04/21/2021 16:00

Instrument: ICPMS2 Analyst: MCB

Analyzed: 04/28/2021 18:41

Sample Preparation: Preparation Method: REN EPA 600/4-79-020 4.1.4 HNO₃ matrix
Preparation Batch: BJD0664 Sample Size: 25 mL
Prepared: 04/28/2021 Final Volume: 25 mL

Extract ID: 21D0237-09 A 01

Analyte	CAS Number	Dilution	Reporting Limit	Result	Units	Notes
Arsenic, Dissolved	7440-38-2	1	0.000200	0.00191	mg/L	



Test America - Denver
4955 Yarrow Street
Arvada CO, 80002

Project: Hansville
Project Number: [none]
Project Manager: Betsy Sara

Reported:
06-May-2021 14:53

MW-6-042121
21D0237-09 (Water)

Wet Chemistry

Method: EPA 300.0

Sampled: 04/21/2021 16:00

Instrument: IC930 Analyst: WCW

Analyzed: 04/22/2021 19:25

Sample Preparation:

Preparation Method: No Prep Wet Chem

Extract ID: 21D0237-09 B

Preparation Batch: BJD0547

Sample Size: 10 mL

Prepared: 04/22/2021

Final Volume: 10 mL

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Nitrate-N	14797-55-8	1	0.100	0.100	1.36	mg/L	

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Nitrite-N	14797-65-0	1	0.100	0.100	0.302	mg/L	

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Orthophosphorus	1426-54-42	1	0.10	0.10	ND	mg-P/L	U



Test America - Denver
4955 Yarrow Street
Arvada CO, 80002

Project: Hansville
Project Number: [none]
Project Manager: Betsy Sara

Reported:
06-May-2021 14:53

MW-14-042121
21D0237-10 (Water)

Metals and Metallic Compounds (dissolved)

Method: EPA 200.8 UCT-KED

Sampled: 04/21/2021 16:15

Instrument: ICPMS2 Analyst: MCB

Analyzed: 04/28/2021 18:46

Sample Preparation: Preparation Method: REN EPA 600/4-79-020 4.1.4 HNO3 matrix
Preparation Batch: BJD0664 Sample Size: 25 mL
Prepared: 04/28/2021 Final Volume: 25 mL

Extract ID: 21D0237-10 A 01

Analyte	CAS Number	Dilution	Reporting Limit	Result	Units	Notes
Arsenic, Dissolved	7440-38-2	1	0.000200	0.0135	mg/L	



Test America - Denver
4955 Yarrow Street
Arvada CO, 80002

Project: Hansville
Project Number: [none]
Project Manager: Betsy Sara

Reported:
06-May-2021 14:53

MW-14-042121
21D0237-10 (Water)

Wet Chemistry

Method: EPA 300.0

Sampled: 04/21/2021 16:15

Instrument: IC930 Analyst: WCW

Analyzed: 04/22/2021 19:45

Sample Preparation:

Preparation Method: No Prep Wet Chem

Extract ID: 21D0237-10 B

Preparation Batch: BJD0547

Sample Size: 10 mL

Prepared: 04/22/2021

Final Volume: 10 mL

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Nitrate-N	14797-55-8	1	0.100	0.100	ND	mg/L	U

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Nitrite-N	14797-65-0	1	0.100	0.100	ND	mg/L	U

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Orthophosphorus	1426-54-42	1	0.10	0.10	ND	mg-P/L	U



Test America - Denver
4955 Yarrow Street
Arvada CO, 80002

Project: Hansville
Project Number: [none]
Project Manager: Betsy Sara

Reported:
06-May-2021 14:53

MW-20DD-042121
21D0237-11 (Water)

Metals and Metallic Compounds (dissolved)

Method: EPA 200.8 UCT-KED

Sampled: 04/21/2021 00:00

Instrument: ICPMS2 Analyst: MCB

Analyzed: 04/28/2021 19:10

Sample Preparation: Preparation Method: REN EPA 600/4-79-020 4.1.4 HNO₃ matrix
Preparation Batch: BJD0664 Sample Size: 25 mL
Prepared: 04/28/2021 Final Volume: 25 mL

Extract ID: 21D0237-11 A 01

Analyte	CAS Number	Dilution	Reporting Limit	Result	Units	Notes
Arsenic, Dissolved	7440-38-2	1	0.000200	0.0132	mg/L	



Test America - Denver
4955 Yarrow Street
Arvada CO, 80002

Project: Hansville
Project Number: [none]
Project Manager: Betsy Sara

Reported:
06-May-2021 14:53

MW-20DD-042121

21D0237-11 (Water)

Wet Chemistry

Method: EPA 300.0

Sampled: 04/21/2021 00:00

Instrument: IC930 Analyst: WCW

Analyzed: 04/22/2021 20:05

Sample Preparation:

Preparation Method: No Prep Wet Chem

Extract ID: 21D0237-11 B

Preparation Batch: BJD0547

Sample Size: 10 mL

Prepared: 04/22/2021

Final Volume: 10 mL

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Nitrate-N	14797-55-8	1	0.100	0.100	ND	mg/L	U

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Nitrite-N	14797-65-0	1	0.100	0.100	ND	mg/L	U

Analyte	CAS Number	Dilution	Detection Limit	Reporting Limit	Result	Units	Notes
Orthophosphorus	1426-54-42	1	0.10	0.10	ND	mg-P/L	U



Test America - Denver
4955 Yarrow Street
Arvada CO, 80002

Project: Hansville
Project Number: [none]
Project Manager: Betsy Sara

Reported:
06-May-2021 14:53

Metals and Metallic Compounds (dissolved) - Quality Control

Batch BJD0664 - REN EPA 600/4-79-020 4.1.4 HNO3 matrix

Instrument: ICPMS2 Analyst: MCB

QC Sample/Analyte	Isotope	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Blank (BJD0664-BLK1)			Prepared: 28-Apr-2021 Analyzed: 28-Apr-2021 17:18								
Arsenic, Dissolved	75a	ND	0.000200	mg/L							U
LCS (BJD0664-BS1)			Prepared: 28-Apr-2021 Analyzed: 28-Apr-2021 17:22								
Arsenic, Dissolved	75a	0.0248	0.000200	mg/L	0.0250		99.2	80-120			
Duplicate (BJD0664-DUP1)			Source: 21D0237-01		Prepared: 28-Apr-2021 Analyzed: 28-Apr-2021 19:19						
Arsenic, Dissolved	75a	0.00116	0.000200	mg/L		0.00111			3.87	20	
Matrix Spike (BJD0664-MS1)			Source: 21D0237-01		Prepared: 28-Apr-2021 Analyzed: 28-Apr-2021 19:24						
Arsenic, Dissolved	75a	0.0259	0.000200	mg/L	0.0250	0.00111	99.3	75-125			

Recovery limits for target analytes in MS/MSD QC samples are advisory only.



Test America - Denver
4955 Yarrow Street
Arvada CO, 80002

Project: Hansville
Project Number: [none]
Project Manager: Betsy Sara

Reported:
06-May-2021 14:53

Wet Chemistry - Quality Control

Batch BJD0547 - No Prep Wet Chem

Instrument: IC930 Analyst: WCW

QC Sample/Analyte	Result	Detection Limit	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Blank (BJD0547-BLK1)						Prepared: 22-Apr-2021 Analyzed: 22-Apr-2021 14:44					
Nitrate-N	ND	0.100	0.100	mg/L							U
Nitrite-N	ND	0.100	0.100	mg/L							U
Orthophosphorus	ND	0.10	0.10	mg-P/L							U
LCS (BJD0547-BS1)						Prepared: 22-Apr-2021 Analyzed: 22-Apr-2021 15:04					
Nitrate-N	4.71	0.100	0.100	mg/L	5.00		94.2	90-110			
Nitrite-N	5.15	0.100	0.100	mg/L	5.00		103	90-110			
Orthophosphorus	4.82	0.10	0.10	mg-P/L	5.00		96.5	90-110			
Duplicate (BJD0547-DUP1)						Source: 21D0237-01 Prepared: 22-Apr-2021 Analyzed: 22-Apr-2021 15:44					
Nitrate-N	0.185	0.100	0.100	mg/L		0.184			0.54	20	
Nitrite-N	ND	0.100	0.100	mg/L		ND					U
Orthophosphorus	ND	0.10	0.10	mg-P/L		ND					U
Matrix Spike (BJD0547-MS1)						Source: 21D0237-01 Prepared: 22-Apr-2021 Analyzed: 22-Apr-2021 16:05					
Nitrate-N	2.02	0.100	0.100	mg/L	2.00	0.184	91.6	75-125			
Nitrite-N	2.01	0.100	0.100	mg/L	2.00	ND	100	75-125			
Orthophosphorus	1.67	0.10	0.10	mg-P/L	2.00	ND	83.3	75-125			

Recovery limits for target analytes in MS/MSD QC samples are advisory only.



Test America - Denver
4955 Yarrow Street
Arvada CO, 80002

Project: Hansville
Project Number: [none]
Project Manager: Betsy Sara

Reported:
06-May-2021 14:53

Certified Analyses included in this Report

Analyte	Certifications
EPA 200.8 UCT-KED in Water	
Arsenic-75a	WADOE,WA-DW,DoD-ELAP
Arsenic-75a	NELAP,WA-DW,DoD-ELAP
Arsenic-75a	NELAP,WADOE,DoD-ELAP
Arsenic-75a	NELAP,WADOE,WA-DW,DoD-ELAP
EPA 300.0 in Water	
Nitrate-N	DoD-ELAP,WADOE,NELAP
Nitrate-N	DoD-ELAP,WADOE,WA-DW,NELAP
Nitrate-N	DoD-ELAP,WADOE,WA-DW
Nitrate-N	DoD-ELAP,WA-DW,NELAP
Nitrite-N	DoD-ELAP,WADOE,WA-DW
Nitrite-N	DoD-ELAP,WA-DW,NELAP
Nitrite-N	DoD-ELAP,WADOE,NELAP
Nitrite-N	DoD-ELAP,WADOE,WA-DW,NELAP
Orthophosphorus	DoD-ELAP,WADOE,NELAP
Orthophosphorus	DoD-ELAP,WADOE,WA-DW,NELAP
Orthophosphorus	DoD-ELAP,WADOE,WA-DW
Orthophosphorus	DoD-ELAP,WA-DW,NELAP

Code	Description	Number	Expires
ADEC	Alaska Dept of Environmental Conservation	17-015	03/28/2023
DoD-ELAP	DoD-Environmental Laboratory Accreditation Program	66169	02/28/2022



Test America - Denver
4955 Yarrow Street
Arvada CO, 80002

Project: Hansville
Project Number: [none]
Project Manager: Betsy Sara

Reported:
06-May-2021 14:53

Notes and Definitions

*	Flagged value is not within established control limits.
D	The reported value is from a dilution
J	Estimated concentration value detected below the reporting limit.
U	This analyte is not detected above the reporting limit (RL) or if noted, not detected above the limit of detection (LOD).
DET	Analyte DETECTED
ND	Analyte NOT DETECTED at or above the reporting limit
NR	Not Reported
dry	Sample results reported on a dry weight basis
RPD	Relative Percent Difference
[2C]	Indicates this result was quantified on the second column on a dual column analysis.

Chain of Custody Record



Environment Testing
 TestAmerica

TA

Client Information Client Contact: <u>Dylan Branscum / Chelsea Bush</u> Phone: <u>206-413-5408</u> Company: <u>Meilani Lanier - Kamahao</u> Aspect Consulting, LLC		Lab PM: <u>Sara, Betsy A</u> E-Mail: <u>Betsy.Sara@Eurofinset.com</u>		Carrier Tracking No(s): COC No: <u>280-23414-6845.1</u> Page: <u>1/2</u> Job #:	
Address: <u>350 Madison Ave N</u> City: <u>Bainbridge Island</u> State, Zip: <u>WA, 98110</u> Phone:		Due Date Requested: TAT Requested (days): PO #: <u>Purchase Order not required</u> WO #:		Analysis Requested Field Filtered Sample (Yes or No) <input checked="" type="checkbox"/> Perform MS/MSD (Yes or No) <input checked="" type="checkbox"/> 8260C SIM - Vinyl Chloride (TA Buffalo) <input checked="" type="checkbox"/> Dissolved Metals <input checked="" type="checkbox"/> Ammonia/TOC <input checked="" type="checkbox"/> Alks/Cl/SO4 <input checked="" type="checkbox"/> Ortho-phosphate (field filtered)- direct sub to ARI <input checked="" type="checkbox"/> Dissolved Arsenic - direct sub to ARI <input checked="" type="checkbox"/> Nitrate/Nitrite (IC) - direct sub to ARI <input checked="" type="checkbox"/>	
Email: <u>mlkamahao@aspectconsulting.com</u> Project Name: <u>Hansville Landfill</u> Site: <u>Washington</u> Project # skip sites/events: <u>28006013 - 2Q/3Q/4Q Sampling</u> SSOW#:		Sample Date Sample Time Sample Type (C=Comp, G=grab) Matrix (W=water, S=solid, O=wastewater, BT=Tissue, A=Air) Preservation Code:		Preservation Codes: A - HCL B - NaOH C - Zn Acetate D - Nitric Acid E - NaHSO4 F - MeOH G - Anchor H - Ascorbic Acid I - Ice J - DI Water K - EDTA L - EDA Other:	
Sample Identification <u>MW-7-042121</u> <u>MW-5-042121</u> <u>SW-1-042121</u> <u>MW-12I-042121</u> <u>SW-4-042121</u> <u>SW-6-042121</u> <u>MW-13D-042121</u> <u>SW-7-042121</u> <u>MW-6-042121</u> <u>MW-14-042121</u> <u>MW-20DD-042121</u>		Sample Date Sample Time Sample Type (C=Comp, G=grab) Matrix (W=water, S=solid, O=wastewater, BT=Tissue, A=Air) Preservation Code:		Total Number of Containers Special Instructions/Note: Diss As, NO3, NO2, o-phos subbed direct to ARI	
Possible Hazard Identification <input type="checkbox"/> Non-Hazard <input type="checkbox"/> Flammable <input type="checkbox"/> Skin Irritant <input type="checkbox"/> Poison B <input type="checkbox"/> Unknown <input type="checkbox"/> Radiological Deliverable Requested: I, II, III, IV, Other (specify)		Sample Disposal (A fee may be assessed if samples are retained longer than 1 month) <input type="checkbox"/> Return To Client <input type="checkbox"/> Disposal By Lab <input type="checkbox"/> Archive For _____ Months		Special Instructions/OC Requirements:	
Empty Kit Relinquished by:		Date:		Method of Shipment:	
Relinquished by: <u>[Signature]</u> Relinquished by:		Date/Time: <u>4/22/21 954</u> Date/Time:		Received by: <u>Seema Chav</u> Received by:	
Relinquished by:		Date/Time:		Date/Time:	
Custody Seal No.: <u>Yes</u> <input type="checkbox"/> <u>No</u> <input type="checkbox"/>		Cooler Temperature(s) °C and Other Remarks: <u>3.10C, 1st JK#9 + 0.40</u>		Company: <u>Eurofins</u> Company:	

Chain of Custody Record

Client Information Client Contact: <u>Melani Lanier - Kamahao</u> Company: <u>Aspect Consulting, LLC</u>			Lab PM: <u>Sara, Betsy A</u> E-Mail: <u>Betsy.Sara@Eurofinset.com</u>			Carrier Tracking No(s): Page: <u>2/2</u>			GOC No: 280-23414-6845.1		
Due Date Requested: TAT Requested (days): PO #: <u>Purchase Order not required</u> WO #: <u>28006013 - 2Q/3Q/4Q Sampling</u> Project # skip sites/events SSOW#:			Sample Date Sample Time Sample Type (C=Comp, G=grab) Matrix (W=water, S=solid, O=waste/oil, BT=Tissue, AA=Air)			Field Filtered Sample (Yes or No) Perform MS/MSD (Yes or No) 8260C SIM - Vinyl Chloride (TA Buffalo) Dissolved Metals Ammonia/TOC Alks/Cl/SO4 Ortho-phosphate (field filtered)- direct sub to ARI Dissolved Arsenic - direct sub to ARI Nitrate/Nitrite (C) - direct sub to ARI			Analysis Requested		
Address: <u>3350 Madison Ave N</u> City: <u>Bainbridge Island</u> State, Zip: <u>WA, 98110</u> Phone: <u>206-413-5408</u> Email: <u>mlkamahao@aspectconsulting.com</u>			Preservation Codes: A - HCL B - NaOH C - Zn Acetate D - Nitric Acid E - NaHSO4 F - MeOH G - Amchlor H - Ascorbic Acid I - Ice J - DI Water K - EDTA L - EDA Other:			Preservation Codes: M - Hexane N - None O - AsNaO2 P - Na2O4S Q - Na2SO3 R - Na2S2SO3 S - H2SO4 T - TSP Dodecahydrate U - Acetone V - MCAA W - ph 4-5 Z - other (specify)			Special Instructions/Note:		
Sample Identification <u>Trip Blank</u>			Total Number of Containers			Diss As, NO3, NO2 o-phos subbed direct to ARI			Special Instructions/Note:		
Possible Hazard Identification <input type="checkbox"/> Non-Hazard <input type="checkbox"/> Flammable <input type="checkbox"/> Skin Irritant <input type="checkbox"/> Poison B <input type="checkbox"/> Unknown <input type="checkbox"/> Radiological			Sample Disposal (A fee may be assessed if samples are retained longer than 1 month) <input type="checkbox"/> Return To Client <input type="checkbox"/> Disposal By Lab <input type="checkbox"/> Archive For _____ Months			Special Instructions/QC Requirements:			Special Instructions/QC Requirements:		
Empty Kit Relinquished by:			Date:			Method of Shipment:			Date/Time:		
Relinquished by:			Date/Time:			Relinquished by:			Date/Time:		
Relinquished by:			Date/Time:			Relinquished by:			Date/Time:		
Relinquished by:			Date/Time:			Relinquished by:			Date/Time:		
Custody Seals Intact: <input type="checkbox"/> Yes <input type="checkbox"/> No			Custody Seal No.:			Cooler Temperature(s) °C and Other Remarks:			Cooler Temperature(s) °C and Other Remarks:		

Do Not Lift

4 E
10:30 8282
04/23

Tag



650
FZ

ment Testing
merica



ORIGIN ID: PHDA (206) 838-6587
ATTN: HANSVILLE LF DYLAN BRANSCUM
ASPECT CONSULTING, LLC
350 MADISON AVE N

SHIP DATE: 13APR21
ACTWGT: 10.00 LB MAN
CAD: 0562071/CAFE3409

BAINBRIDGE ISLAND, WA 98110
UNITED STATES US


TO

EUROFINS TESTAMERICA DENVER
4955 YARROW STREET

ARVADA CO 800024517

(303) 736-0100
REF: \$240-81060

RMA: 11111111



FedEx
Express




FedEx

TRK# 5018 6635 8282
0221

FRI - 23 APR 10:30A
PRIORITY OVERNIGHT

XH LAAA

80002
CO-US DEN



#5204558 04/22 56DJ3/F9AG/FE4A

Chain of Custody Record

Environment Testing
America

Client Information (Sub Contract Lab)		Sampler:	Lab PM:	Carrier Tracking No(s):	COC No:					
Client Contact:		Phone:	Sara, Betsy A		280-565285, 1					
Shipping/Receiving			E-Mail:	State of Origin:	Page:					
Company:			Betsy.Sara@Eurofinset.com	Washington	Page 1 of 2					
TestAmerica Laboratories, Inc.										
Address:		Due Date Requested:	Accreditations Required (See note):							
10 Hazelwood Drive,		5/6/2021	State Program - Washington							
City:	Amherst	TAT Requested (days):	Analysis Requested							
State, Zip:	NY, 14228-2298		Preservation Codes:							
Phone:	716-691-2600(Tel) 716-691-7991(Fax)	PO #:	A - HCL M - Hexane							
Email:		WO #:	B - NaOH N - None							
Project Name:	Hansville Landfill	Project #:	C - Zn Acetate O - AsNaO2							
Site:	Hansville	SSOW#:	D - Nitric Acid P - Na2O4S							
			E - NaHSO4 R - Na2SO3							
			F - MeOH G - Amchlor S - H2SO4							
			H - Ascorbic Acid T - TSP Dodecahydrate							
			I - Ice U - Acetone							
			J - DI Water V - MCAA							
			K - EDTA W - pH 4-5							
			L - EDA Z - other (specify)							
			Other:							
Sample Identification - Client ID (Lab ID)		Sample Date	Sample Time	Sample Type (C=Comp, G=grab)	Matrix (W=water, S=solid, O=wastewater, BT=Tissue, A=Air)	Field Filtered Sample (Yes or No)	Perform MS/MSD (Yes or No)	8260C, SIM/5030C (MOD) Local Method	Total Number of containers	Special Instructions/Note:
MW7-042121 (280-147801-1)	4/21/21	08:45	Pacific	Water		X	X	3		
MW5-042121 (280-147801-2)	4/21/21	10:20	Pacific	Water		X	X	3		
SW1-042121 (280-147801-3)	4/21/21	11:45	Pacific	Water		X	X	3		
MW121-042121 (280-147801-4)	4/21/21	12:00	Pacific	Water		X	X	3		
SW4-042121 (280-147801-5)	4/21/21	12:30	Pacific	Water		X	X	3		
SW6-042121 (280-147801-6)	4/21/21	13:15	Pacific	Water		X	X	3		
MW13D-042121 (280-147801-7)	4/21/21	13:00	Pacific	Water		X	X	3		
SW7-042121 (280-147801-8)	4/21/21	14:20	Pacific	Water		X	X	3		
MW6-042121 (280-147801-9)	4/21/21	16:00	Pacific	Water		X	X	3		
Note: Since laboratory accreditations are subject to change, Eurofins TestAmerica places the ownership of method, analyte & accreditation compliance upon out subcontract laboratories. This sample shipment is forwarded under chain-of-custody. If the laboratory does not currently maintain accreditation in the State of Origin listed above for analysis/tests/matrix being analyzed, the samples must be shipped back to the Eurofins TestAmerica laboratory or other instructions will be provided. Any changes to accreditation status should be brought to Eurofins TestAmerica attention immediately. If all requested accreditations are current to date, return the signed Chain of Custody attesting to said compliance to Eurofins TestAmerica.										
Possible Hazard Identification										
Unconfirmed										
Deliverable Requested: I, II, III, IV, Other (specify)		Primary Deliverable Rank: 2		Special Instructions/QC Requirements:		Return To Client <input type="checkbox"/> Disposal By Lab <input type="checkbox"/> Archive For <input type="checkbox"/> Months		Sample Disposal (A fee may be assessed if samples are retained longer than 1 month)		
Empty Kit Relinquished by:		Date:		Time:		Method of Shipment:				
Relinquished by:		Date/Time:		Company:		Received by:		Date/Time: Company:		
Relinquished by:		Date/Time:		Company:		Received by:		Date/Time: Company:		
Relinquished by:		Date/Time:		Company:		Received by:		Date/Time: Company:		
Custody Seals Intact: <input type="checkbox"/> Yes <input type="checkbox"/> No		Custody Seal No.:		Cooler Temperature(s) °C and Other Remarks:		3.6 #1 ICE				

Chain of Custody Record

[illegible]

Login Sample Receipt Checklist

Client: Aspect Consulting

Job Number: 280-147801-1

Login Number: 147801

List Source: Eurofins TestAmerica, Denver

List Number: 1

Creator: Kramer, Julieann L

Question	Answer	Comment
Radioactivity either was not measured or, if measured, is at or below background	True	
The cooler's custody seal, if present, is intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the sample IDs on the containers and the COC.	True	
Samples are received within Holding Time (Excluding tests with immediate HTs)..	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
VOA sample vials do not have headspace or bubble is <6mm (1/4") in diameter.	True	
If necessary, staff have been informed of any short hold time or quick TAT needs	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Sampling Company provided.	True	
Samples received within 48 hours of sampling.	True	
Samples requiring field filtration have been filtered in the field.	True	
Chlorine Residual checked.	N/A	

Login Sample Receipt Checklist

Client: Aspect Consulting

Job Number: 280-147801-1

Login Number: 147801

List Number: 2

Creator: Kolb, Chris M

List Source: Eurofins TestAmerica, Buffalo

List Creation: 04/30/21 12:16 PM

Question	Answer	Comment
Radioactivity either was not measured or, if measured, is at or below background	True	
The cooler's custody seal, if present, is intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	3.0 IR GUN #1 ICE
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the sample IDs on the containers and the COC.	True	
Samples are received within Holding Time (Excluding tests with immediate HTs)..	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
VOA sample vials do not have headspace or bubble is <6mm (1/4") in diameter.	True	
If necessary, staff have been informed of any short hold time or quick TAT needs	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Sampling Company provided.	True	
Samples received within 48 hours of sampling.	True	
Samples requiring field filtration have been filtered in the field.	True	
Chlorine Residual checked.	True	