

SUBMITTED TO:
Sargent Engineers, Inc.
320 Ronlee Lane NW
Olympia, WA 98502

BY:
Shannon & Wilson
400 N. 34th Street, Suite 100
Seattle, WA 98103

(206) 632-8020
www.shannonwilson.com

GEOTECHNICAL ENGINEERING AND ENVIRONMENTAL
REPORT

Cascade Mill Parkway, Phase 3

YAKIMA COUNTY, WASHINGTON

Submitted To: Sargent Engineers, Inc.
320 Ronlee Lane NW
Olympia, WA 98502
Attn: Ms. Jessica Soward, PE, SE

Subject: GEOTECHNICAL ENGINEERING AND ENVIRONMENTAL REPORT,
CASCADE MILL PARKWAY, PHASE 3, YAKIMA COUNTY, WASHINGTON

Shannon & Wilson prepared this report and participated in this project as a subconsultant to Sargent Engineers, Inc. Our scope of services was specified our proposal dated February 12, 2021, and executed via the Professional Services Agreement with Sargent Engineers, Inc., dated March 2, 2021.

We appreciate the opportunity to be of service to you on this project. If you have questions concerning this report, or we may be of further service, please contact us.

Sincerely,

SHANNON & WILSON



3/31/2023

Oliver T. Hoopes, PE
Associate

MXT:KXM:OTH:RAM/oth

CONTENTS

1 Introduction1

 1.1 General.....1

 1.2 Project Understanding and Description1

 1.3 Scope of Services3

2 Subsurface Explorations.....3

 2.1 2021 Explorations3

 2.1.1 Shannon & Wilson Borings3

 2.1.2 County Test Pits.....4

 2.1.3 WSDOT Test Pit.....5

 2.2 2017-2018 Explorations.....5

 2.3 2014 Explorations5

3 Geotechnical Laboratory Testing5

4 Environmental Laboratory Testing6

 4.1 2021 Explorations6

 4.2 2014 and 2017 Explorations7

5 Groundwater and Surface Water Measurements.....7

6 Geology and Subsurface Conditions8

 6.1 Geologic Setting.....8

 6.2 Subsurface Soil Conditions9

 6.3 Groundwater Conditions10

 6.3.1 2021 Explorations10

 6.3.2 2017-2018 Explorations11

 6.3.3 2014 Explorations11

7 Engineering Studies and Recommendations11

 7.1 Seismic Design Parameters and Hazard Evaluation.....12

 7.1.1 Ground Motions12

 7.1.2 Earthquake-Induced Geologic Hazards.....12

 7.1.2.1 Fault-Related Ground Rupture12

 7.1.2.2 Liquefaction.....13

 7.2 Yakima River Bridges13

- 7.2.1 General.....13
- 7.2.2 Subsurface Conditions.....13
- 7.2.3 Pier Scour.....14
- 7.2.4 Drilled Shaft Axial Resistance15
- 7.2.5 Lateral Resistance.....16
- 7.2.6 Lateral Earth Loads on Abutment Walls.....16
- 7.2.7 Abutment Global Stability18
- 7.3 Roadway Embankments18
 - 7.3.1 Global Stability20
 - 7.3.2 Settlement.....20
- 7.4 Stormwater Detention Pond.....21
 - 7.4.1 Subsurface Conditions and Recommendations21
 - 7.4.2 Infiltration Evaluation21
- 7.5 Sign Structure and Street Light Foundations.....22
- 7.6 Pavement Design.....23
 - 7.6.1 Traffic Load23
 - 7.6.2 Subgrade Conditions23
 - 7.6.3 Pavement Section Recommendation24
 - 7.6.4 Pavement Materials and Construction.....24
 - 7.6.5 Frost Susceptibility.....25
- 7.7 Manholes and Vaults.....25
- 7.8 Buried Utilities.....26
- 8 Construction Considerations.....26
 - 8.1 General.....26
 - 8.2 Site Preparation and Grading.....27
 - 8.3 Fill Placement and Compaction27
 - 8.4 Temporary Shoring.....28
 - 8.5 Temporary Excavations.....29
 - 8.6 Drilled Shafts30
 - 8.7 Obstructions.....30
 - 8.8 Wet Weather Considerations.....30

9 Limitations32

10 References34

Exhibits

Exhibit 1-1: Aerial Imagery Showing Recent Site Work West of I-82 (July 2021)2

Exhibit 2-1: County Wood Waste Test Pit Findings4

Exhibit 6-1: Photograph of the Bank of the Yakima River Near the Proposed YRB East
Abutment10

Exhibit 7-1: Approximate Extents of Scour Mitigation Measures15

Exhibit 7-3: Lateral Earth Pressure K Values for Surcharge Loads17

Exhibit 7-4: Factored Bearing Resistance for Proposed Wing Walls for Piers 1 and 519

Exhibit 7-5: Assumed MSW and Wood Waste Geometric Parameters for CMP Embankment
West of I-8220

Figures

Figure 1: Vicinity Map

Figure 2: Site and Exploration Plan (2 sheets)

Figure 3: Generalized Subsurface Profile A-A'

Figure 4: Generalized Subsurface Profile B-B'

Figure 5: Generalized Subsurface Profile C-C'

Figure 6: Seismic Design Response Spectra Site Class = D

Figure 7: Estimated Axial Shaft Resistance, Yakima River Bridge Pier 1, 6 Ft Diameter

Figure 8: Estimated Axial Shaft Resistance, Yakima River Bridge Pier 2, 10 Ft Diameter

Figure 9: Estimated Axial Shaft Resistance, Yakima River Bridge Pier 2, 10 Ft Diameter,
with 100 Yr Scour

Figure 10: Estimated Axial Shaft Resistance, Yakima River Bridge Pier 2, 10 Ft Diameter,
with 500 Yr Scour

Figure 11: Estimated Axial Shaft Resistance, Yakima River Bridge Pier 3, 10 Ft Diameter

Figure 12: Estimated Axial Shaft Resistance, Yakima River Bridge Pier 3, 10 Ft Diameter,
with 100 Yr Scour

Figure 13: Estimated Axial Shaft Resistance, Yakima River Bridge Pier 3, 10 Ft Diameter,
with 500 Yr Scour

Figure 14: Estimated Axial Shaft Resistance, Yakima River Bridge Pier 4, 10 Ft Diameter

Figure 15: Estimated Axial Shaft Resistance, Yakima River Bridge Pier 4, 10 Ft Diameter,
with 100 Yr Scour

Figure 16: Estimated Axial Shaft Resistance, Yakima River Bridge Pier 4, 10 Ft Diameter,
with 500 Yr Scour

- Figure 17: Estimated Axial Shaft Resistance, Yakima River Bridge Pier 5, 6 Ft Diameter
Figure 18: Yakima River Bridge LPILE Parameters for Lateral Deep Foundation Analysis
Figure 19: Recommended Surcharge Loading for Temporary and Permanent Walls
Figure 20: Loads on Buried Utilities

Appendices

- Appendix A: Subsurface Explorations
Appendix B: Geotechnical Laboratory Test Procedures and Results
Appendix C: 2014 and 2017 Subsurface Data
Appendix D: Environmental Procedures and Testing Results
Appendix E: Groundwater Observations
Appendix F: Global Stability Analyses
Important Information

ACRONYMS

AASHTO	American Association of State Highway and Transportation Officials
ADT	average daily traffic
BDM	Bridge Design Manual
bgs	below ground surface
CMP	Cascade Mill Parkway
County	Yakima County
CRBG	Columbia River Basalt Group
CSBC	crushed surfacing base course
Ecology	Washington State Department of Ecology
EFW	equivalent fluid weight
ESAL	equivalent single-axle load
EWC	East-West Corridor
FEE	functional evaluation earthquake
FS	factor of safety
g	standard acceleration of gravity
GRO	gasoline-range organics
GDM	Geotechnical Design Manual
H:V	Horizontal to Vertical
HMA	hot-mix asphalt
I-82	Interstate 82
IDW	investigation-derived waste
ksf	kips per square foot
LRFD	Load and Resistance Factor Design
mg/kg	milligrams per kilogram
mm	millimeter
MSW	municipal solid waste
MTCA	Model Toxics Control Act
pcf	pounds per cubic foot
PIT	Pilot Infiltration Test
psf	pounds per square foot
SEE	safety evaluation earthquake
SMMEW	Stormwater Management Manual for Eastern Washington
SPT	Standard Penetration Test
USBR	U.S. Bureau of Reclamation
USGS	U.S. Geological Survey
VWP	vibrating wire piezometer
WSDOT	Washington State Department of Transportation
YRB	Yakima River Bridge

1 INTRODUCTION

1.1 General

This report presents the results of our geotechnical engineering and environmental studies for Phase 3 of the Cascade Mill Parkway (CMP) Phase 3 Project (Project) in Yakima County (the County), Washington. The location of the proposed CMP roadway alignment is shown in the Vicinity Map, Figure 1.

1.2 Project Understanding and Description

The CMP Project in Yakima County includes approximately 2.1 miles of a four-lane arterial that will connect the City of Yakima with Terrace Heights, an unincorporated area of the County. The Project is designed to improve traffic flow and includes at-grade and abovegrade roads, sidewalks, a shared bicycle/pedestrian path, undercrossing bridges beneath I-82, and a bridge over the Yakima River and the Roza Canal. Other Project improvements include illumination, sewer and potable water utilities, storm drainage, levee flood protection, floodplain restoration, and wetland/stream mitigation on the Yakima River east bank. The river levee to the east and south of the Yakima River Bridge (YRB) will be removed as a part of this Project. The river levee to the east and north of the bridge will be evaluated by a separate County project.

Phase 3 of the Project includes the proposed CMP alignment from west of North 15th Street. Key proposed Phase 3 elements addressed in this report include:

- The CMP Roadway Alignment, including the roadway prism, sign and luminaire foundations, and proposed buried utilities.
- A proposed roadway embankment supporting the CMP alignment, up to about 10 feet tall, west of the I-82 embankment.
- The YRB over the Yakima River and associated approach embankments and walls.
- YRB scour protection measures.
- A stormwater infiltration and detention pond north of CMP, between Interstate-82 (I-82) and the Yakima River.

Two proposed I-82 undercrossing bridges are also associated with Phase 3 of the CMP Project because they will be designed by the Washington State Department of Transportation (WSDOT) Bridge and Structures Office. The recommendations for these bridges are presented in a separate report.

Phases 1 and 2 included the at-grade portions of the alignment east of North 15th Street in Yakima. Geotechnical recommendations for Phases 1 and 2 are presented in our Final Design Geotechnical Engineering and Environmental Report, Stages 1 and 2, East-West Corridor Project, February 14, 2020 (Shannon & Wilson, 2020).

West of the I-82 embankment, the CMP alignment crosses land that was previously used as a lumber mill and then later as a municipal solid waste (MSW) landfill. The extent of this landfill location is indicated in Figure 2 with a dashed yellow line. We understand that as part of the Bravo Company Boulevard extension project, the City of Yakima has removed the MSW and wood waste material in that area down to native sand and gravel within the CMP footprint and replaced it with compacted granular fill. Exhibit 1-1 presents a July 2021 aerial image that was taken after the City of Yakima performed this work (Google Earth, 2021).



Exhibit 1-1: Aerial Imagery Showing Recent Site Work West of I-82 (July 2021)

Based on preliminary plans, we understand that in addition to replacing the MSW and wood waste, the City of Yakima also installed a zone of low permeability material around the perimeter of the replacement zone. We understand the purpose of this relatively low permeability zone is to reduce the potential that vapor from the remaining MSW would intrude into the newly placed granular material.

1.3 Scope of Services

Our scope of services included performing subsurface explorations, field and laboratory tests, and geotechnical, hydrogeologic, and hydraulic analyses to advance the Phase 3 portion of the CMP Project to final corridor design configuration. This report updates recommendations from the following reports we performed under previous contracts:

- Draft Geotechnical Engineering and Environmental Report, East-West Corridor Project Stage 3, Yakima County, Washington (January 8, 2020)
- Draft Hydraulics Report, Yakima East-West Corridor Project, FEMA No-Rise Study, Yakima County, Washington (January 2019)

The subsurface explorations and engineering performed incorporates and builds upon those presented in previous reports.

2 SUBSURFACE EXPLORATIONS

Shannon & Wilson performed subsurface exploration programs for the CMP Project in 2014, 2017, and 2021. Approximate locations of these explorations are shown in the Site and Exploration Plan (Figure 2).

Numerous explorations by others were performed in the area west of I-82, primarily to evaluate the depth of the MSW and wood waste within the CMP Project alignment. As noted in Section 1.2, the City of Yakima removed this material within the CMP alignment and replaced it with compacted granular fill. Therefore, we have not included logs of any of these explorations west of the I-82 embankment in this report.

2.1 2021 Explorations

Subsurface explorations completed for the project in 2021 included the following three programs:

- Seven borings by Shannon & Wilson in the I-82 embankment,
- Two test pits performed by the County in the footprint of a proposed stormwater detention pond, and
- One test pit completed by WSDOT in the I-82 embankment sideslope.

2.1.1 Shannon & Wilson Borings

Shannon & Wilson performed a subsurface exploration program in 2021 that included seven borings. These borings were completed between March and April 2021. The Site and

Exploration Plan, Figure 2, shows the approximate locations of the borings. Appendix A includes the description of field methods and procedures to perform the borings and detailed logs of the borings.

Six borings were advanced for the two I-82 undercrossing bridges. Four borings were performed at the proposed abutments (B-9-21, B-10-21, B-11P-21, and B-12P-21) and two borings were performed approximately 100 feet away from the abutments to assess conditions at the tieback locations (B-13-21 and B-14-21). The borings were drilled in the interior and exterior shoulders of I-82. We advanced the abutment borings to 100 feet below ground surface (bgs) and the tieback borings to 65 feet bgs. All borings were advanced using sonic core drilling methods. The borings extended through the I-82 embankment fill and into the underlying native soil.

One subsurface boring (B-15P-21) was advanced in the existing U.S. Bureau of Reclamation (USBR) levee. The boring was advanced to 40 feet bgs using sonic core drilling methods, and a well was installed in the borehole.

In situ vibrating wire piezometers (VWPs) and dataloggers were installed in two of the abutment borings, B-11P-21 and B-12P-21, and the USBR boring, B-15P-21. We collected over 12 months of daily groundwater data from the VWPs, from April 2021 to May 2022. The dataloggers were removed from the borings in May 2022. Plots of the groundwater observations are included in Appendix E.

2.1.2 County Test Pits

In 2021, the County performed two test pits within the footprint of the proposed pond, designated North Test Hole and South Test Hole. The locations of these test pits are shown in Figure 2. Our understanding of the depth of the wood as shown in Exhibit 2-1 is based on email correspondence with the County. Shannon & Wilson was not present during the excavation of these test pits. Exhibit 2-1 presents the County's findings at these test pits.

Exhibit 2-1: County Wood Waste Test Pit Findings

Test Pit Name	Depth (feet)	Description
North Test Hole	8	Top of wood waste
	9	Bottom of wood waste / top of river alluvium
	14	Bottom of pit (also in river alluvium)
South Test Hole	1	Top of wood waste
	13	Bottom of wood waste / top of river alluvium / bottom of pit

2.1.3 WSDOT Test Pit

WSDOT performed a test pit in May 2022 to evaluate stand-up time of the I-82 embankment material. Details on the stand-up test pit and a log can be found in Appendix A. The test pit log is shown in Appendix A.

2.2 2017-2018 Explorations

Shannon & Wilson performed three boreholes and one test pit for the East-West Corridor (EWC) Project Stage 3, designated B-1-17, B-2-17, and B-3-18, and TP-P1-17 (see Figure 2). The explorations west of the Yakima River were completed between July and September 2017, and boring B-3-18, located on a gravel bar in the Yakima River, was completed in September 2018. The 2017-2018 explorations are included in the Site and Exploration Plan, Figure 2.

The borings, designated B-1-17, B-2-17, and B-3-18, were advanced using sonic core drilling techniques to depths ranging from 40 to 140 feet bgs.

The test pit, designated TP-P1-17, was excavated to design a drainage facility. The test pit was excavated to 8.5 feet bgs using a backhoe provided by the County and observed by a Shannon & Wilson representative. A Pilot Infiltration Test was performed in TP-P1-17.

Boring and test pit logs and descriptions of field methods and procedures used to perform the borings and test pits are included in Appendix C.

2.3 2014 Explorations

Shannon & Wilson completed four borings, designated EWC-B-01-14 through EWC-B-04-14, along the Stage 3 portion of the EWC alignment between June and July 2014 as a part of the 30% design study. The 2014 explorations are included in the Site and Exploration Plan, Figure 2. The borings for the 30% design were drilled using sonic core drilling techniques to an approximate depth of 100 feet bgs. Boring logs and descriptions of field methods and procedures used to perform the borings are included in Appendix C.

3 GEOTECHNICAL LABORATORY TESTING

We performed geotechnical laboratory testing on select soil samples from the explorations performed by Shannon & Wilson to evaluate index and engineering properties. This laboratory testing included visual soil classification, moisture content determinations, grain-size analysis, and Atterberg Limits. Laboratory tests were performed by Shannon & Wilson in accordance with applicable ASTM standard test procedures. Appendix B provides

descriptions of the laboratory test procedures and the laboratory test results. Results are also presented graphically in the boring logs in Appendix A.

Appendix C provides descriptions of the laboratory test procedures and the laboratory test results from 2017-2018 and 2014 explorations.

4 ENVIRONMENTAL LABORATORY TESTING

We performed environmental laboratory testing on samples retrieved from the 2014, 2017, and 2021 explorations. Environmental testing was performed by others in the area west of I-82. However, as noted in Section 1.2, the City of Yakima removed the MSW and wood waste material within the CMP Project footprint in 2021. Therefore, environmental testing results from those explorations are not included or summarized in this report.

4.1 2021 Explorations

Soil samples were collected for environmental laboratory analysis from borings B-09-21, B-10-21, B-11P-21, B-13-21, B-14-21, and B-15P-21. The laboratory analysis was completed to assist in the disposal of investigation-derived waste (IDW) generated during the investigation and to provide environmental characterization of the soils that may be encountered during construction for worker health and safety purposes. The samples were screened for the potential of contamination using a photoionization detector and visual and olfactory observations. Soil samples were collected at depths where field indication identified the potential presence of contamination. In borings where no field indication of contamination was observed, samples were collected near the groundwater-soil interface.

Analytical laboratory test results identified heavy oil-range petroleum hydrocarbons and gasoline-range organics (GRO) similar to mineral spirits present in the soil in one of the borings completed for the Project. Several metals, including arsenic, barium, chromium, lead and selenium, were detected in samples collected from each of the borings. With the exception of the GRO detected, the heavy oil-range hydrocarbons and metals, including arsenic, barium, chromium, lead and selenium, were detected below available Washington State Department of Ecology (Ecology) Model Toxics Control Act (MTCA) Method A and B criteria (Ecology, 2013).

GRO was detected at a concentration of 1,030 milligrams per kilogram (mg/kg) in the 15.5-foot sample collected from boring B-10-21. The location of this sample is depicted graphically in Generalized Subsurface Profile B-B' (Figure 4). The detected concentration exceeds the Ecology MTCA Method A soil cleanup level for unrestricted land use of

100 mg/kg. Currently, we are unsure of the source of the contamination encountered in boring B-10-21 at that depth.

Additional information is provided in Appendix D, which includes descriptions of the soil sample screening, methodology, and IDW disposal, along with analytical data results of the samples collected during the 2021 investigation. Removal, handling, and disposal recommendations for the contaminated soil are provided in Section 8.9.

4.2 2014 and 2017 Explorations

Environmental laboratory analysis was performed on soil samples collected from borings completed during previous investigations, 30% phase borings EWC-B-01-14 through EWC-B-04-14 (2014) and borings B-1-17 and B-2-17 (2017), located west of the Yakima River. The samples were collected to assist with environmental characterization of the soil that may be encountered during construction of the Project and to assist in the disposal of generated IDW. The samples were screened for the potential of contamination using a photoionization detector and visual and olfactory observations. The soil samples in the 30% borings were collected near the groundwater interface.

Laboratory test results identified gasoline-range petroleum hydrocarbons, toluene, ethylbenzene, xylenes, diesel-range-petroleum hydrocarbons, lube-oil-range petroleum hydrocarbons, arsenic, chromium, lead, and cadmium in the soil sampled along the alignment. The identified contaminants were below the Washington MTCA Method A unrestricted cleanup criteria (Ecology, 2013).

Appendix D provides descriptions of the soil sample screening, methodology, and IDW disposal, along with analytical data results.

5 GROUNDWATER AND SURFACE WATER MEASUREMENTS

We measured groundwater levels in piezometers installed in the 2021, 2017-2018, and 2014 borings. Figures E-1 through E-8 in Appendix E present plots of surface and groundwater monitoring data for the Project. The 2021, 2017-2018, and 2014 borings with VWPs and groundwater monitoring wells are as follows:

- 2021: In situ VWPs and dataloggers were installed in borings B-11P-21 and B-12P-21. A monitoring well with a VWP was installed in boring B-15P-21. Figures E-1 through E-3 present the recorded groundwater elevation versus time, and daily precipitation and relative river level between January 2021 and June 2022. Precipitation data is from a National Oceanic and Atmospheric Administration weather station near downtown

Yakima. The relative river levels represent gage heights from the Yakima River, from the U.S. Geological Survey (USGS) river gauge at Union Gap, which is approximately 6 miles downstream from the Project site.

- 2017-2018: A monitoring well was installed in B-2-17. Figure E-4 presents the groundwater elevation versus time from November 2017 through September 2018.
- 2014: Monitoring wells and VWPs were installed in EWC-B-01-14 through EWC-B-04-14. Figures E-5 through E-8 present the recorded groundwater elevation versus time, and the area precipitation between July 1, 2014, and June 16, 2015. Precipitation data is from the Yakima Air Terminal.

The boring logs in Appendix A (2021) and Appendix C (2017-2018, 2014) show the groundwater elevations measured and the corresponding dates of record.

We utilized the VWP groundwater data for the final phase of analysis and design recommendations.

6 GEOLOGY AND SUBSURFACE CONDITIONS

6.1 Geologic Setting

The Project site is located near the western margin of the Columbia Basin geologic province, a lowland occupying the southern-central portion of Washington that is characterized by expansive plateaus, incised canyons, and east-west-oriented ridges.

Bedrock within the Columbia Basin is generally composed of the Miocene Columbia River Basalt Group (CRBG) and Tertiary sedimentary rock (Lasmanis, 1991). Basalt that comprises the CRBG accumulated between about 17 and 6 million years ago. While much of the CRBG is buried by younger sedimentary rock or unconsolidated deposits, it is well exposed in many areas, including near the Project site where the basalt has been relatively uplifted and exposed in roughly east-west-oriented anticlinal folds that comprise the Yakima fold and thrust belt. Presently active deformation in the fold and thrust belt began in the Miocene (McCaffrey and others, 2016).

Cataclysmic floods periodically inundated and scoured much of the Columbia Basin during the last glacial period (Norman and others, 2004; Bjornstad, 2006). Repeated failure of the ice dams resulted in numerous massive floods that flowed across much of eastern Washington and down the Columbia River. The floods eroded channels into bedrock and removed surficial soils in some areas, while leaving extensive deposits of gravel, sand, and silt in others (Norman and others, 2004; Bjornstad, 2006).

Constrictions along the path of glacial floods resulted in the formation of temporary lakes and the accumulation of relatively fine-grained slack-water deposits in some areas (Bjornstad, 1980). The wind-deposited loess and dune deposits covering much of the western Columbia Basin were commonly derived from the reworking of these flood and slack-water deposits. Loess deposits are locally as much as 250 feet thick (Norman and others, 2004). The loess and slack-water deposits are exposed on the higher topography encompassing the east-west ridges near the Project site.

Surficial deposits of the CMP area consist of Holocene alluvium along the active Yakima River channel and Pleistocene terrace deposits at slightly higher elevations along the margins of the channel (Bentley and others, 1993; Schuster, 1994). The terrace deposits may extend to about 30 feet above the modern Yakima River floodplain.

6.2 Subsurface Soil Conditions

This section describes the geologic soil units encountered by boreholes along the CMP alignment. The geologic unit descriptions are described below and are shown in the boring logs presented in Appendices A and C. A generalized subsurface cross section along the CMP roadway alignment is presented in Figure 3, and generalized cross sections oriented approximately orthogonal to the alignment are presented in Figures 4 and 5.

The soil units encountered in the project explorations include Holocene Fill (Hf), Loess Deposits (Ql), and Alluvial Deposits (Qa). Terrace deposits from the Yakima River are undifferentiated from Qa. Descriptions of these units follow:

- Holocene Fill (Hf) – Hf generally consists of anthropogenically placed silty gravel with variable sand content and local cobbles. Where present, subsurface explorations encountered up to 50 feet of Hf with variable angularity, density, moisture, and plasticity. Hf deposits appear to be largely derived from the local native Qa deposits.
- Wood Waste and Municipal Solid Waste (MSW) West of I-82 – Within the former Cascade Mill property, MSW and wood waste were encountered in previous borings from grade to about 14 feet bgs and shown as Hf-Landfill in Figure 3.

As noted in Section 1.2, the City of Yakima removed the MSW and wood waste within the CMP Project footprint west of the I-82 embankment.

No MSW and no significant wood waste were encountered within the I-82 embankment in the 2021 explorations; however, trace amounts of wood fragments were observed in several locations.

- Wood Waste East of I-82 – Between I-82 and the Yakima River, wood waste was encountered up to about 13 feet bgs in test pits as measured by the County in 2021.

- Alluvial Deposits (Qa) – Qa generally consists of medium dense to dense, poorly sorted gravel with silt, sand, and cobbles to silty gravel with sand. The relative density interpreted from the Standard Penetration Tests (SPTs) may be overestimated due to the presence of gravel and cobbles. The subsurface explorations encountered Qa at the ground surface and underlying the Hf deposits. The Qa deposits are characterized by the presence of silty interbeds to 1 foot thick, and clay is commonly encountered in the matrix of gravel deposits. From our experience nearby, we anticipate that the matrix in the gravel and cobbles will vary widely from coarse sand to clayey, silty sand. Boulders are also likely present in the Qa material based on our observations of the surface the Yakima River channel and banks (see Exhibit 6-1).



Exhibit 6-1: Photograph of the Bank of the Yakima River Near the Proposed YRB East Abutment

6.3 Groundwater Conditions

6.3.1 2021 Explorations

Groundwater levels vary with the time of year at the site and depend on the amount of precipitation and irrigation. We recorded groundwater levels via in situ VWP's for B-11P-21, B-12P-21, and B-15P-21.

2009 and 2011 reports from SLR International Corporation described the subsurface conditions at the abandoned Cascade Mill landfill site. In the documents, SLR reports that the groundwater could fluctuate from about 8 feet bgs in the summer months to about 20 feet bgs in the winter months at the landfill site. The Yakima River strongly influences groundwater levels close to the river.

We recorded the following groundwater elevation between April 7, 2021, and May 22, 2022:

- **I-82 Roadway/Embankment:** Approximate elevation 1038 to 1043 feet

A groundwater elevation of 1043 feet was used for I-82 analyses and design recommendations. Plots of the groundwater level readings are included in Appendix E.

6.3.2 2017-2018 Explorations

We recorded groundwater levels via a well transducer in boring B-2-17. We recorded the following groundwater elevations between November 2017 and September 2018:

- **B-2-17:** Approximate elevation 1038 to 1044 feet

A plot of the observation well readings is included in Appendix E.

6.3.3 2014 Explorations

We recorded the following groundwater depths between July 17, 2014, and June 10, 2015:

- **Cascade Mill Site:** Approximately 12 to 19 feet bgs (elevation 1038 to 1045 feet)
- **Adjacent to the Yakima River:** Approximately 12 to 15 feet bgs (elevation 1041 to 1045 feet)

Plots of the groundwater level readings are included in Appendix E.

7 ENGINEERING STUDIES AND RECOMMENDATIONS

The geotechnical engineering recommendations and conclusions presented in the following sections are for the YRB and part of the CMP Phase 3 Project. We understand that the roadway alignment and bridges will be designed in accordance with the 2022 WSDOT Geotechnical Design Manual (GDM) (WSDOT, 2022b) and the American Association of State Highway and Transportation Officials (AASHTO, 2020) Load and Resistance Factor Design (LRFD) Bridge Design Specifications, 9th Edition. The recommendations and conclusions herein are based on information from field explorations, in situ testing, and laboratory testing performed for this project, and our understanding of the project.

7.1 Seismic Design Parameters and Hazard Evaluation

7.1.1 Ground Motions

We understand that the seismic design of the Project will be in accordance with the WSDOT Bridge Design Manual (BDM) (WSDOT, 2022a). The BDM specifies two design level earthquakes, the functional evaluation earthquake (FEE) and the safety evaluation earthquake (SEE). The FEE seismic design parameters are based on design ground motions with a 30% probability of exceedance in 75 years (210-year return period) and the SEE seismic design parameters are based on design ground motions with a 7% probability of exceedance in 75 years (975-year return period). We understand the proposed YRB is considered a “Normal” structure and, therefore, only the SEE is applicable for design. Seismic design parameters presented in this report are based on the SEE earthquake.

The site soil response factors are based on determination of the site class definitions as presented in the BDM. The Washington Division of Geology and Earth Resources Site Class Map of Yakima County (Palmer and others, 2004) shows that the site could be classified as Site Class C or D. Based on the description of the subsurface conditions encountered in nearby explorations and our understanding of the site geology, we recommend that the site be classified as Site Class D. We note that although the SPT blow counts in the Hf and Qa deposits are typically above 50 blows per foot, they likely are not representative of the soil relative density due to the presence of gravel, cobbles, and boulders.

The design response spectrum corresponding to the design ground motion is shown in Figure 6.

7.1.2 Earthquake-Induced Geologic Hazards

Earthquake-induced geologic hazards that may affect a given site include fault-related ground rupture, liquefaction, and liquefaction-related effects, such as loss of shear strength, bearing capacity failures, loss of lateral support, ground oscillation, and lateral spreading. An associated effect of earthquake shaking is densification of the soil and potential ground surface settlement.

7.1.2.1 Fault-Related Ground Rupture

The USGS U.S. Quaternary Fault Map does not show faults mapped within the CMP site area. The closest known faults are the east-west trending Ahtanum Ridge and Rattlesnake Hills structures, which are approximately 5½ miles south of the proposed alignment. Based on these fault locations, it is our opinion that the risk of fault-related ground rupture at the site is low.

7.1.2.2 Liquefaction

Liquefaction of loose, saturated, and cohesionless soil occurs when excess pore pressure is generated as a result of earthquake shaking. Liquefaction potential has been studied for more than 50 years, resulting in analytical methods based on laboratory and field procedures. The most widely used methods are empirical and based on correlations between SPT measurements (N-value), peak ground acceleration, and earthquake magnitude. Based on the analyses, we consider the potential for liquefaction and the associated effects (e.g., loss of shear strength, bearing capacity failures, loss of lateral support, ground oscillation, and lateral spreading) along the CMP alignment to be low.

7.2 Yakima River Bridges

7.2.1 General

Drilled shafts were selected as the preferred foundation system for the proposed YRB. The locations of these proposed bridges are shown on sheet 2 of the Site and Exploration Plan (Figure 2). The following sections provide the recommendations for scour, axial and lateral resistance of drilled shafts, lateral earth loads on abutment walls, and abutment global stability for the YRB.

We understand the structural design team have selected 6-foot-diameter drilled shafts for the abutment piers (Piers 1 and 5) and 10-foot-diameter drilled shafts for Piers 2 through 4.

7.2.2 Subsurface Conditions

Our interpretation of the subsurface conditions for the YRB is presented in sheet 2 of Profile A-A' (Figure 3). We based our interpretation on borings EWC-B-03-14, B-3-18, and EWC-B-04-14. The borings encountered native gravel with sand and cobbles and varying amounts of silt (Qa). Although these three borings did not encounter boulders, abundant cobbles and boulders are visible along the Yakima River channel bottom and banks (see Exhibit 6-1). Therefore, we anticipate the Qa geologic unit in this area likely contains scattered boulders and therefore, the Contractor should be prepared to encounter boulders in the drilled shaft excavations.

The SPT blow counts in the Qa deposit were very high. However, we consider the relative density interpreted from the SPTs to be overstated due to the presence of gravel and cobbles. Therefore, for engineering purposes we consider the Qa deposit to be medium dense to dense, rather than very dense.

7.2.3 Pier Scour

Based on the hydraulic analyses, we estimate pier scour will occur at YRB Piers 2 through 4. Detailed scour recommendation designs are presented in the Hydraulics Report for the Project (Shannon & Wilson, in press). This section summarizes the scour findings and conclusions from that report.

Pier scour occurs when waters flow into a pier and diverges both up and down, as well as around the sides of the pier. Due to the orientation of the Yakima River side channel and proposed removal of the existing levee east of Pier 5 (the east abutment), Yakima River could scour away the material around and behind the Pier 1 shafts if scour mitigation measures are not implemented there. Therefore, we recommend installing scour protection measures for the east abutment.

Design pier scour configurations for 100- and 500-year flood events are presented in sheet 2 of Profile A-A' (Figure 3).

To protect the east abutment from scour up to the 100-year flood event, we recommend installing a launchable riprap blanket around the east abutment in a "U" configuration footprint as shown in Exhibit 7-1. The proposed cross-sectional configuration of the placed and launched configurations of this blanket are shown in Profile A-A' (Figure 3). Gradation and sizing details for the riprap blanket are provided in the Hydraulics Report.

Construction of the riprap blanket will require an excavation of up to about 18 feet deep. The location of this excavation would be west of the proposed abutment but outside of the wetted perimeter of the channel. Temporary shoring may be necessary to complete this excavation. Sections 8.4 and 8.5 provided construction considerations for temporary shoring and excavation recommendations, respectively.



Exhibit 7-1: Approximate Extents of Scour Mitigation Measures

7.2.4 Drilled Shaft Axial Resistance

Drilled shaft axial resistance is a function of shaft diameter, embedment length, subsurface conditions, scour depth, and installation techniques.

Based on discussions with the design team, Piers 1 and 5 will be constructed with 6-foot-diameter drilled shafts, while Piers 2 through 4 will be constructed with 10-foot-diameter drilled shafts. Figures 7 through 17 present the results of the axial resistance analyses for service, strength, and extreme event limit states for 6- and 10-foot-diameter drilled shafts for Piers 1 through 5. The plots present nominal side and base resistance and factored total compressive resistance using the WSDOT GDM (WSDOT, 2022b) guidelines and AASHTO (2020) LRFD resistance factors. The figures show the assumed subsurface conditions based on soil conditions encountered in nearby borings.

7.2.5 Lateral Resistance

The computer program LPILE may be used to generate p-y curves (load-deflection curves) for the lateral resistance analysis of the drilled shafts and to calculate the magnitude of deflection, shear, and moment along the shaft. Figure 18 presents the recommended soil parameters for input into LPILE considering unscoured and scoured conditions.

We recommended a “Soft Clay” soil model with close to zero strength and stiffness for the scour zone for the 100-year flood scour case. Soil will not be present in this zone during the scour event, we anticipate the soil below the scour zone will not experience a significant change in overburden stress. The intent of this “zero strength” soil layer is to maintain the same overburden stresses between pre-scour and post-scour cases.

The proposed location of the YRB east abutment (Pier 5) is behind an existing levee. We assume that these levees will be properly maintained and repaired as needed following flood events. We also assume that recommended scour protection measures (as described in Section 7.2.3) will be installed at the east abutment. Under these assumptions, we do not consider the abutments susceptible to pier scour and therefore the lateral resistance analyses for the abutment shafts do not need to consider scour effects.

To account for group effects, the recommended soil parameters in Figure 18 should be adjusted using the P-multipliers summarized in Section 8.13 of the WSDOT Geotechnical Design Manual (2022b) and Sections 10.7.2.4 and 10.8.2.3 of the AASHTO LRFD (2020). These efficiency factors should be used in lateral resistance analyses of deep foundation groups.

7.2.6 Lateral Earth Loads on Abutment Walls

We understand the YRB abutments will include cast-in-place concrete stem walls above the drilled shafts and pile cap. These stem walls will retain the soil behind the abutment and these walls must be designed to resist lateral earth pressures.

Lateral earth pressures against walls are dependent upon many factors, including method of backfill placement and degree of compaction, backfill slope, surcharges, the type of backfill and/or adjacent native soil, drainage provisions, and whether or not the wall or structure can yield or deflect laterally or rotate at the top after or during placement of backfill or during and after excavation. For walls that are capable of deflecting at least 0.001 times the wall height, active lateral earth conditions govern the applied pressures. For walls or structures that are not allowed to move 0.001 times the wall height, at-rest lateral earth pressure conditions govern. Our lateral earth pressure recommendations in the form of

equivalent fluid weight (EFW) are presented in Exhibit 7-2. These recommendations assume active earth pressure conditions.

Exhibit 7-2: Recommended EFWs for Active Earth Pressure Conditions

Design Condition	EFW (pounds per cubic foot)
Static	34
Seismic	42

The recommendations for the lateral earth pressures in Exhibit 7-2 include static and seismic lateral earth pressure EFW. These should be applied as triangular pressure distributions. We note that the seismic EFW in Exhibit 7-2 includes both static and seismic components.

The seismic lateral earth pressures provided are consistent with a pseudo-static analysis using the Mononobe-Okabe equation for lateral earth pressures and include a horizontal seismic coefficient of 0.11. We used a horizontal seismic coefficient equal to one-half of the site design ground acceleration, A_s , of 0.21g (Figure 6) for the Site Class D SEE ground motion level. One-half the A_s is used because the full A_s is experienced only a few times within the record of earthquake shaking, and the actual earthquake ground motion is cyclic in nature, not static.

Lateral earth pressures due to surcharge loads should be added to the recommended lateral earth pressures, where appropriate. Recommended lateral pressures due to surcharge loads are presented in Figure 19. We recommend using the following lateral earth pressure coefficients, K values, in conjunction with Figure 19 (see Exhibit 7-3):

Exhibit 7-3: Lateral Earth Pressure K Values for Surcharge Loads

Design Condition	K Value
Static	0.26
Seismic	0.34

Unless included as a surcharge load on the wall, excavated material, fill embankments, stockpiles, and/or equipment and vehicle traffic should be placed and routed away from the top edge of the wall, no closer than a distance equal to the wall height.

The lateral earth pressure recommendations assume the walls are backfilled with properly compacted, free-draining aggregate. WSDOT Standard Specifications provide gradation criteria for wall backfill materials. The wall backfill should consist of Gravel Backfill for Walls as specified in Standard Specification Section 9-03.12(2) (WSDOT, 2021).

7.2.7 Abutment Global Stability

We performed global stability analyses for the YRB east and west abutments. The global stability analysis approach and results are presented in Appendix F. In summary, the analyses indicate that the proposed abutments will achieve an adequate factor of safety (FS) against global instability for both static and seismic cases.

As noted in Section 7.2.3, we recommend a launchable riprap blanket be constructed at the YRB east abutment to mitigate scour. For the global stability analyses, we assumed the fully launched, post-scour condition (see Profile A-A, Figure 3) to represent long-term static conditions for these analyses.

7.2.8 Wing Walls

We understand the wing wall at Piers 1 and 5 will consist of cast-in-place concrete cantilever walls and that Sargent intends to design them using WSDOT standard plans. Based on the available subsurface data at the abutments, we consider the geotechnical conditions at the proposed wing walls to meet the design assumptions for WSDOT standard plan walls.

Exhibit 7-4 presents recommended bearing resistances for various footing widths. The bearing resistance curves presented in this exhibit incorporate the following resistance factors:

- Service Limit State: 1.0
- Strength Limit State: 0.45
- Extreme Limit State: 0.9

We assumed that the bottom of the footing was at least 2 feet bgs and that the ground surface has a slope of 5 Horizontal to 1 Vertical (5H:1V) or shallower.

Our wing wall bearing resistance analyses assume the footing subgrades are prepared in accordance with Section 8.2.

We consider our global stability analyses for Piers 1 and 5 (see Section 7.2.7 and Appendix F) to apply to the wing walls. This determination is based on the following:

- The wing walls connect to the abutment walls and we consider them to have the same subsurface conditions.
- The wing walls and abutment walls will be backfilled using the same fill material and compaction methods.
- We did not include the bridge shafts in our abutment global stability analyses.
- The ground surface slope in front of the wing walls is shallower than at the abutments.




Exhibit 7-4: Factored Bearing Resistance for Proposed Wing Walls for Piers 1 and 5

7.3 Roadway Embankments

We understand the following roadway embankments are proposed for the Project that will support the CMP roadway:

- YRB approach embankments leading up to both abutments.
- An approximately 10-foot-tall fill embankment west of the I-82 embankment.

Based on preliminary plans, we understand these embankments will consist of unreinforced soil slopes constructed at 3H:1V sideslopes.

As indicated in Profile A-A' (Figure 3), MSW and wood waste were encountered near the ground surface on both sides of I-82. As noted in Section 1.2, we understand the area west of I-82 was a former City of Yakima landfill and before that the entire area west of the Yakima River in the vicinity of the EWC alignment was part of a timber mill (Cascade Mill). However, we understand that in 2021, the City of Yakima, as part of the Bravo Company Boulevard extension project, removed the MSW and wood waste west of the I-82 embankment and replaced it with compacted granular fill.

Based on our review of the preliminary plans and as-built data for the City of Yakima's MSW and wood waste removal effort and the CMP Project plans, we have assumed the geometric configuration shown in Exhibit 7-5 for the roadway embankment analyses.




Exhibit 7-5: Assumed MSW and Wood Waste Geometric Parameters for CMP Embankment West of I-82

Between the Yakima River and I-82, we estimate up to about 13 feet of wood waste are present based on the test pits performed by the County (North Test Hole and South Test Hole) and TP-P1-17. We understand that prior to the construction of the YRB approach embankment, the County intends to remove the wood waste within the CMP footprint as well as underneath the proposed stormwater detention pond north of the CMP roadway between I-82 and the Yakima River. Therefore, for the approach embankment analyses we assumed that all the wood waste will be excavated and the resulting subsurface conditions will consist of compacted granular fill underlain by native river alluvium.

7.3.1 Global Stability

We performed global stability analyses for the proposed roadway embankments. The global stability analysis approach and results are presented in Appendix F. In summary, the analyses indicate that the proposed approach embankments will achieve an adequate FS against global instability for both static and seismic cases.

7.3.2 Settlement

Based on the analyses, we anticipate settlements of the roadway embankments up to about 2 inches may occur. This estimated settlement assumes:

- The County removes all the wood waste within the CMP footprint between I-82 and the Yakima River, and
- The City of Yakima removed and replaced the MSW and wood waste west of the I-82 embankment consistent with the assumptions shown in Exhibit 7-5.

Assuming the foundation soil beneath the proposed approach embankments consists of granular material (sand and gravel), we expect this settlement to occur as the embankment

material is placed. We anticipate long-term settlements of the approach embankments will be negligible.

7.4 Stormwater Detention Pond

We understand that a proposed stormwater detention pond will be constructed as part of the Project north of the CMP roadway between I-82 and the Yakima River.

7.4.1 Subsurface Conditions and Recommendations

As noted above and described in Exhibit 2-1, wood waste is present in the area of the proposed pond. In our opinion, wood waste is not suitable for the foundation material or sidewalls of a detention pond and should be removed prior to constructing the pond.

We performed one Pilot Infiltration Test (PIT) in test pit TP-P1-17 in 2017. TP-P1-17 is located about 100 feet east of the proposed pond. The log of TP-P1-1, presented as Figure C-9 in Appendix C, shows that abundant wood debris was encountered in the upper 6 feet of this test pit with material consistent with native alluvium from 6 to 8.5 feet bgs.

In our opinion, the subsurface conditions within TP-P1-17 are similar to those that at the proposed pond area, assuming the wood waste is removed down to the native river alluvium below. We anticipate removal of wood waste will require an excavation of up to about 14 feet deep within the footprint of the pond. For pond slope stability, we recommend removing the wood waste at least 5 feet beyond the crest of the pond slopes.

Temporary excavation stability is the responsibility of the Contractor. For planning purposes, we assume that the sideslopes may need to be cut at 2H:1V or shallower. The Contractor may also elect to use temporary shoring. Sections 8.4 and 8.5 provided construction considerations for temporary shoring and excavation recommendations, respectively.

7.4.2 Infiltration Evaluation

We estimated long-term design infiltration rates for the proposed stormwater detention pond using the results of the PIT conducted in test pit TP-P1-17. This PIT was performed in a subsurface profile that included wood waste on the sidewalls and native alluvium in a portion of the sidewalls and in the bottom of the PIT excavation.

In addition to the infiltration rate estimated from the PIT, we used empirical correlations to grain-size analysis data for comparison purposes. Both PIT and grain-size analysis-based infiltration rate estimation methods result in short-term rates. We estimated the long-term design infiltration rates by applying correction factors to the short-term infiltration rates.

Appendix C describes the PIT procedure and methods for estimating the long-term design infiltration rates using the results of the PIT and grain-size distributions. The grain-size distribution curves are shown in Appendix C.

Tables C-1 and C-2 provide estimated short-term and long-term design infiltration rates. As indicated in these tables, the PIT infiltration rate results were higher compared to the empirical correlations. Based on the range of infiltration rates we obtained, we recommend using a design infiltration rate of 10 inches per hour for the proposed pond near test pit TP-P1-17. This design value assumes native alluvium material is present at the base of the pond. If new fill is placed at the bottom of the wood waste excavation within the pond footprint to raise the pond bottom grade, we assume this fill will have a similar gradation and density of the native alluvium. Although lower values were obtained based on several of the empirical grain-size distribution-based infiltration rate estimates (Table C-2) obtained from sand and gravel samples, we consider the PIT to be more representative of the likely infiltration rate behavior at TP-P1-17. Therefore, the design infiltration rate recommendation is weighted toward the PIT-based results.

The long-term design infiltration rates presented in this report meets the requirements for flow control for the Ecology Stormwater Management Manual for Eastern Washington and the Yakima County Regional Stormwater Manual. The design infiltration rates are for flow control only and assume a pretreatment system will be used to meet water quality requirements. Both the SMMEW and the Yakima County Regional Stormwater Manual require a maximum infiltration rate of 2.4 inches per hour for infiltration systems designed to meet treatment standards. The base of the proposed infiltration systems should be a minimum of 5 feet above the seasonally high groundwater level. Based on available data from piezometers installed in the EWC-B-02-14 and B-2-17 boreholes, we estimate the seasonally high groundwater level near the proposed pond to be elevation 1044 feet. See Appendix E for piezometer data.

7.5 Sign Structure and Street Light Foundations

New sign and street light structures may be installed within the CMP alignment. Based on our understanding of the locations of these structures, their foundations will be installed within either engineered YRB approach embankment fill or engineered granular fill installed within the zone where the wood waste will be removed. As such, we recommend designing sign and street light foundations for the Project using WSDOT standard foundations.

Per WSDOT GDM Section 17.2.1 (WSDOT, 2022b), WSDOT standard foundation designs for cantilever signals, strain poles, cantilever signs, sign bridges, and luminaires are based on

allowable lateral bearing pressures and soil friction angles developed from correlation. We recommend using an allowable lateral bearing pressure of 3,500 pounds per square foot (psf), and a friction angle of 36 degrees for new, engineered compacted granular borrow fill installed for this project and for the underlying native alluvial sand and gravel.

7.6 Pavement Design

We performed pavement analyses using the AASHTO (1993) method for flexible pavement design. The AASHTO method is a widely used empirical design procedure for the design of pavement structures. It considers strength of the base course materials, traffic stresses, and the strength of the pavement subgrade. We understand design life for the proposed CMP pavement is 50 years.

7.6.1 Traffic Load

Average daily traffic (ADT) counts, including heavy trucks, were provided to us in 2017 for a previous phase of the project. Based on discussions with the design team, we understand the pavement design parameters, including ADT, have not changed.

The ADT is estimated at 11,510 vehicles per day in the eastbound direction and 7,930 vehicles per day in the westbound direction. The Project design team estimated that the passenger cars and other light-duty vehicles make up 98% of the traffic loading, with the remaining 2% being made up of heavy truck traffic. We converted the traffic volumes into equivalent single-axle loads (ESALs) by using equivalent axle load factors provided in the Asphalt Institute manual (Asphalt Institute, 1991) and guidance provided in the AASHTO Design of Pavement Structures (AASHTO, 1993). The Asphalt Institute manual provides percentages of truck types that make up traffic for different function classifications of roads.

The Project design team identified the functional classification for the proposed EWC as Urban Principal. We used Table IV-1 in the Asphalt Institute manual to estimate the distribution of heavy traffic for an Urban Principal roadway. The Project design team also provided growth rates of approximately 2.6% from the design year to 2035 and 1.5% from 2035 to 2067. Based on the analysis of the existing and projected traffic conditions, we estimate that approximately 1.8 million ESALs will be subjected to the roadway over the planned 50-year design life.

7.6.2 Subgrade Conditions

We understand the proposed CMP pavement will be installed on either engineered YRB approach embankment fill, engineered granular fill installed within the zone where the

wood waste will be removed, engineered granular fill in the portion that was formerly occupied by the City landfill, or medium dense to dense, native alluvial sand and gravel.

For the pavement design analyses, we assumed embankment fill would consist of WSDOT Common Borrow as specified in Section 9-03.14(3) of the WSDOT Standard Specification (WSDOT, 2020). Placement and compaction of the embankment fill required to raise the grade is discussed in Section 8.3. In areas where the roadway will be constructed on native soils, the area underlying the proposed roadway section should be stripped to remove loose, soft, or disturbed soil, old fill, and organic materials/soils and debris. The subgrade should be graded to its design grade, smoothed, and compacted to 95% of the Modified Proctor maximum dry density (ASTM D1557) and to a dense and unyielding condition.

We recommend proof rolling the pavement subgrades prior to installing the pavement sections. Proof rolling should be observed by a geotechnical engineer and should be performed by rolling over the subgrade with a fully loaded standard dump truck. Loose or soft subgrade soil identified during proof rolling by excessive rutting or pumping should be compacted to a dense, unyielding condition or removed and replaced with at least 2 feet of compacted embankment fill as presented in Section 8.3.

We assumed an average subgrade resilient modulus of 15,000 pounds per square inch for both compacted embankment fill and compacted native granular soils. Drainage should be provided below crushed surfacing base course (CSBC) layers to mitigate saturation of the CSBC and subgrade soils.

7.6.3 Pavement Section Recommendation

The proposed pavement types include hot-mix asphalt (HMA) for the roadway and intersections. We calculated the pavement layer thicknesses using the AASHTO (1993) pavement design method. Based on the analysis results including frost susceptibility conditions described below, we recommend the flexible pavement section consist of a minimum of 6 inches of HMA underlain by 9 inches of CSBC material for a total structural pavement thickness of 15 inches.

7.6.4 Pavement Materials and Construction

The HMA, CSBC, and gravel base layers should be constructed in accordance with current WSDOT Standard Specifications for Road, Bridge, and Municipal Construction (WSDOT, 2021). HMA should conform to Section 5-04 in the WSDOT Standard Specifications. Aggregate for HMA should meet Section 9-03.8 requirements for HMA subjected to between 0.3 and 3 million ESALs.

7.6.5 Frost Susceptibility

Frost-susceptible soil is regarded as having greater than 3% finer than 0.02 millimeter (mm). Soil with a fines content not exceeding 7% passing the No. 200 sieve, based on the minus ¾-inch fraction, can normally be expected to have 3% or less finer than 0.02 mm. Based on the grain-size analyses presented in Appendices D and E, it is our opinion that the on-site soil is frost susceptible and has near-surface fines content ranging from about 2 to 60%. According to the WSDOT Everseries User's Guide (WSDOT, 2005), the frost depth in the Yakima area is about 30 inches in fine-grained soil and 55 inches in coarse-grained soil. Fine-grained soil is defined as having 50% or more passing the No. 200 sieve. The measured frost depth during the cold winters of 1949 and 1950 was about 25 to 30 inches in the Yakima area. Based on this information, we recommend assuming a frost depth of 30 inches.

Pavement can be designed for frost protection by providing a pavement section that is equal to or thicker than half of the anticipated frost depth in accordance with the WSDOT Pavement Policy (2015). The pavement section includes pavement and non-frost-susceptible granular base materials. In our opinion, the minimum recommended pavement section should provide adequate frost protection.

7.7 Manholes and Vaults

We understand that concrete manholes and vaults will be installed for belowgrade utilities along the alignment. We recommend the unyielding, precast concrete manholes and vaults be designed to resist an at-rest lateral earth pressure using an EFW applied as a triangular distribution. The recommended EFWs provided below are based on the assumption that a well-compacted Select Borrow fill will be placed around the concrete structures. Based on the groundwater observations obtained from EWC explorations, we assume that some of structures may extend below the groundwater elevation.

- EFW above groundwater – 54 pounds per cubic foot (pcf)
- EFW below groundwater – 92 pcf (includes hydrostatic pressure)

The EFW below groundwater includes hydrostatic pressure. Unbalanced lateral loads may be resisted through friction along the base of the manholes and vaults. We recommend concrete manholes and vaults be designed using a nominal coefficient of friction of 0.4 for soil against precast concrete. We recommend applying a resistance factor of 0.9 to this nominal coefficient of friction.

7.8 Buried Utilities

Figure 20 presents the geotechnical recommendations regarding loading on rigid buried pipelines caused by overburden soils (Case A and Case B) and H-20 live traffic loads (Case C). The H-20 live traffic loads shown in Case C should be added to the overburden loads for portions of the alignment within proposed or future road right-of-way to obtain the total design load for the pipeline. We recommend using steel plates to distribute temporary loads if construction traffic loads could exceed the H-20 design traffic loads, and/or where the pipeline is not designed for H-20 loading. We recommend using a backfill unit weight of 130 pcf for pipeline overburden load calculations.

We developed recommendations for modulus of soil reaction (E') values for use in the reclamation equation (Howard, 1996) for pipe design. The modulus values are based on the soil encountered in explorations, the trench backfill that we expect to be specified, and recommendations made in Howard (1996). For the buried utility pipelines along the roadway alignment, we recommend using an E' value of 1,500 kips per square foot (ksf) for the embedment material. This value assumes the pipe is embedded in Gravel Backfill for Pipe Zone Bedding as specified in the WSDOT Standard Specification, Section 9.03.12(3) (WSDOT, 2021) and that the material is compacted to at least 95% of its Modified Proctor maximum dry density (ASTM Designation D1557). For the purpose of calculating a composite E' that represents the embedment material and the trench walls, we recommend using an E' value of 1,500 ksf for the in situ gravel trench walls.

The recommended E' values are based on subsurface conditions in explorations that are several hundred feet apart. Variable subsurface conditions would likely be encountered between these explorations. The pipeline designer should consider this variability when selecting pipe type and properties.

8 CONSTRUCTION CONSIDERATIONS

8.1 General

The applicability of the design recommendations provided in this report is contingent on good construction practice. Poor construction techniques may alter conditions from those on which our recommendations are based, possibly resulting in unfavorable conditions, such as reduced foundation resistance, higher earth pressures, and increased settlement. The following sections present additional construction and material considerations for this Project.

8.2 Site Preparation and Grading

Clearing and grubbing beneath the proposed CMP alignment should be done in accordance with Section 2-01 of the WSDOT Standard Specifications (WSDOT, 2021). The alignment footprint should be cleared of trees, brush, and existing fill or debris. The area should be grubbed of stumps and large roots, and stripped of topsoil and underlying soil, which contains roots or other objectionable debris and organic matter. We recommend that organic-rich soil be removed from the site or stockpiled for reuse in landscape areas.

We assume any wood waste beneath these proposed features will be completely removed and replaced with reinforced, compacted structural fill. The areal and vertical extent of this excavation, as well as environmental considerations, are being prepared by others.

After clearing and grubbing, and prior to any fill placement, the exposed soil surface should be compacted using a heavy vibratory roller (10-ton or heavier static weight). Native subgrade soils should be proof-rolled and, if necessary, compacted to achieve at least 95% of the Modified Proctor maximum dry density (ASTM D1557). The proof-rolling operations should consist of several passes of a fully loaded dump truck to identify potential loose, soft, and/or yielding areas. Loose or soft subgrade should be compacted to a dense, unyielding condition or removed and replaced with at least 2 feet of compacted structural fill. Subgrade surfaces that will receive structural fill, levee fill, or foundations should be dense and unyielding and should be evaluated by a geotechnical engineer prior to placing the fill or constructing the foundations.

8.3 Fill Placement and Compaction

Construction of the proposed CMP Project features will require placement and compaction of:

- Roadway embankment fill,
- Utility trench backfill, and
- Retaining wall backfill.

We assumed the roadway embankment fill and utility trench backfill will be Common Borrow, as specified in Section 9-03.14(3) of the WSDOT Standard Specification (WSDOT, 2021), with the exception that the material shall not contain more than 1% organic material by dry unit weight. Based on the grain-size distributions of the on-site soil samples we tested (see Appendix C), we anticipate the on-site Qa soil along the CMP alignment will meet the requirements of Common Borrow, provided that cobbles and boulders larger than 4 inches are removed prior to or during fill placement. Numerous cobbles and boulders were encountered in the subsurface explorations. Evaluating the cost effectiveness and

schedule implications of removing oversized particles should be the Contractor's responsibility.

If fill is to be placed during periods of wet weather or under wet conditions, it should have the added requirement that the percentage of fines (materials passing the No. 200 sieve based on wet-sieving the minus 3/4-inch fraction) be limited to 5%. The fines should be nonplastic. See Section 8.8 for additional wet weather construction considerations.

For backfill of utility trenches, pipe zone bedding should extend from the trench bottom to at least 8 to 12 inches above the pipes. Pipe zone bedding should consist of select granular soil free from organic matter meeting the requirements for Gravel Backfill for Pipe Zone Bedding as specified in Standard Specification Section 9-03.12(3) (WSDOT, 2021). The pipe zone bedding below the pipe should be compacted before laying the pipe. After the pipe is installed, heavy vibratory equipment or rollers should not be allowed beside or over the pipe until at least 2 feet of material is placed above the pipe. Fill placed above the Gravel Backfill for Pipe Zone Bedding (8 to 12 inches above the pipes) to the top of the utility trench should be compacted Common Borrow backfill. As discussed above, the on-site coarse-grained (sands and gravels) soils could be used as utility trench backfill above the pipe zone bedding provided cobbles and boulders larger than 4 inches are removed.

Roadway embankment fill, retaining wall backfill, and pipe zone bedding should be placed in horizontal uniform lifts and compacted to a dense and unyielding condition to at least 95% of the Modified Proctor maximum dry density (ASTM D1557) in accordance with Standard Specification Section 2-03.3(14)C, Method C (WSDOT, 2021). Utility trench backfill may be placed and compacted in accordance with Standard Specification Section 2-03.3(14)C, Method B (WSDOT, 2021). The appropriate lift thickness and compaction methods necessary to achieve this compaction criteria should be determined by the Contractor using the Contractor's selected equipment and fill material. In situ soil density of all compacted fill materials must be verified with in situ soil density testing in accordance with WSDOT Standard Specification 2-03.3(14)D (WSDOT, 2021).

8.4 Temporary Shoring

We understand temporary shoring may be needed to facilitate buried utility installation. Temporary shoring may also be deemed necessary by the Contractor for the launchable riprap blanket installation. The design of temporary shoring is the responsibility of the Contractor as they are in control of the means and methods of construction.

Unshored and trench box-protected excavations are generally used where the groundwater is below the base of the excavation and movement of the trench walls is acceptable. Some trench wall movement is commonly acceptable when nearby structures, utilities, and other

improvements are a sufficient distance from the excavation, such that they are not impacted by the stress relief and ground movement associated with the excavation. Trench boxes are designed to provide passive protection for workers in the trench and provide poor contact with the trench sidewalls; therefore, movement of the ground adjacent to the trench is likely.

If existing utilities, or settlement-sensitive improvements are too close to the excavation, measures to protect these improvements, temporary or permanent utility relocation, and/or excavation shoring that limits ground movement would be required. We recommend assuming that utilities and other improvements above a plane that extends up and away from the bottom of the excavation at 1.5H:1V could be affected by ground movement associated with unshored or trench box-protected excavations.

8.5 Temporary Excavations

Construction slope angles required for stability and safety depend on careful evaluation of factors that include:

- Contractor means and methods,
- Amount and depth of groundwater seepage,
- Soil and materials exposed in the excavation slope,
- Depth of the excavation,
- Surcharge loads on top of the excavation,
- Geometry of the excavation, and
- Time of construction.

Because of the many factors involved, required slope values can only be estimated prior to construction. For safe working conditions and prevention of ground loss, excavation slopes should be the responsibility of the Contractor, as they will be at the jobsite full time to observe and control the work. All current and applicable safety regulations regarding excavation slopes should be followed.

For planning purposes, we recommend assuming a contractor would make temporary, unsupported, open-cut slopes in sand and gravel Qa soil no steeper than 1.5H:1V. Flatter cut slopes may be required where loose soil is encountered. The above recommendation is for temporary cut slopes in dry conditions. If wet conditions or groundwater inflow is encountered, flatter slopes may be required. Exposed cut slopes may need to be protected with a waterproof covering during periods of wet weather to reduce sloughing and erosion.

Unshored, open-trench techniques might be suitable where the excavation depth is shallow, and the trench sides can be sloped sufficiently to avoid trench side failure. Where the

excavation depth exceeds 4 feet, trench side sloping, trench boxes, a trench shoring system, or a combination of the above will be required. All traffic and/or construction equipment loads should be set back from the edge of the cut slopes a minimum of 4 feet. Excavated material, stockpiles, and equipment should not be placed closer to the edge of any excavation than the depth of the excavation, unless the excavation is shored and such materials are accounted for as a surcharge load on the shoring system.

Based on expected temporary excavation depths of up to 6 feet, anticipated subsurface conditions, and space limitations along the proposed alignment, we anticipate that trench excavations could be made using conventional excavating equipment, such as rubber-tired backhoes or tracked hydraulic excavators. If the exposed subgrade is too loose to provide a working surface or a firm foundation for utilities, the subgrade should be improved by compacting at least the upper 12 inches of loose, granular subgrade to a dense and unyielding condition.

8.6 Drilled Shafts

YRB drilled shaft foundations should be constructed in accordance with WSDOT Standard Specifications (2021), Section 6-19.

In our opinion, the Qa deposits will be prone to caving during shaft drilling. Full-depth temporary casing will likely be needed to maintain the integrity of the drill holes.

8.7 Obstructions

Based on explorations at the site and our interpretation of the local geologic deposits and field observations of the Yakima River channel and banks (see Exhibit 6-1), we expect the Contractor to encounter cobbles and boulders in shaft excavations. The cobbles and boulders may range in diameter from 3 inches to greater than 24 inches. The Contractor should be prepared to advance excavations and penetrations past such obstructions using suitable means, methods, and equipment.

8.8 Wet Weather Considerations

In the CMP area, wet weather generally begins about mid-October and continues through about May. It would be advisable to schedule earthwork during the drier weather months. However, should wet weather or wet-condition earthwork be unavoidable, the following recommendations are provided:

- The ground surface in and surrounding the construction area should be sloped to promote rapid runoff of precipitation away from the work areas and to prevent the ponding of water.

- Work areas, slopes, and stockpiles should be covered with plastic and appropriate erosion and sediment control measures applied. The use of sloping, ditching, sumps, dewatering, and other measures should be employed as necessary to permit proper completion of the work.
- Earthwork should be accomplished in small sections to minimize exposure to wet conditions. That is, each section should be small enough so that the removal of unsuitable soils and placement and compaction of clean structural fill could be accomplished on the same day.
- To mitigate soil disturbance, the size or type of construction equipment may have to be limited.
- Fill material to be placed should consist of clean, well-graded granular soils, of which not more than 5% by dry weight pass the No. 200 mesh sieve, based on the wet sieving fraction passing the ¾-inch mesh sieve. The fines should be nonplastic.
- No fill soil should be left uncompacted and exposed to moisture. A smooth-drum vibratory roller, or equivalent, should roll the surface to promote rapid runoff of the surface water.
- In-place soil or fill soil that becomes wet and unstable and/or too wet for compaction should be removed and replaced with clean, structural fill material.
- Excavation and placement of structural fill material should be observed on a full-time basis by a geotechnical engineer, experienced in wet weather/wet condition earthwork to determine that the work is being accomplished in accordance with the Project specifications and our recommendations.
- Grading and earthwork should not be performed during periods of heavy, continuous rainfall.

8.9 Removal, Handling, and Disposal of Contaminated Soil

We recommend that the Contractor remove contaminated material at boring B-10-21 for off-site disposal. Starting at 10 feet below the existing ground surface and extending to the planned depth of the excavation, the Contractor should remove a 20- by 20-foot area of soil centered in the plan view around boring B-10-21.

All contaminated material should be handled and stored in a manner that prevents the spread of contamination to adjacent soil or water.

The Contractor shall perform excavation and other tasks of this Section in compliance with applicable statutes and regulations, including the State MTCA, Chapter 70.105D RCW. We recommend that the Contractor be required to complete all soil sampling necessary to characterize material generated prior to disposal, appropriately coordinate with disposal facilities to ensure facility acceptance of characterized material prior to it leaving the project

site and comply with disposal facility permit requirements. The Contractor should allow for the Engineer to collect samples for quality assurance/quality control purposes.

If stockpiling is performed, the area used must be within the construction limits, but not in an in-service street right-of-way. The stockpiling areas should not block areas that need to be accessed during construction, such as electrical vaults and monitoring wells, or below ground sites identified for cultural resource investigation. The stockpile area should allow for ease of sampling, testing, and load out once characterization is complete.

The Contractor should divert water from contaminated and potentially hazardous stockpiled materials and cover them with a minimum of 6-mil polyethylene sheeting. The edges of the sheeting should be installed and maintained in accordance with Section 8-01.3(5). The stockpiles should be covered at all times when not being worked. The Contractor should inspect the stockpiles daily, maintain the sheeting, and replace any worn or ripped sheeting sections.

The stockpile area should be constructed to collect water from any stockpile(s), preventing it from releasing the potentially contaminated water, and should also be isolated from precipitation and stormwater run-on. Any collected stockpile water should be prevented from discharging to public sewerage without proper permitting. Stockpile water should also be prevented from discharging to waters of the State prior to treatment and sampling to confirm compliance with surface water quality standards and National Pollutant Discharge Elimination System permit requirements.

Separate stockpiles should be maintained for known hazardous or contaminated material and for suspected hazardous or contaminated material. The Contractor should transport hazardous or contaminated material and dispose of it at a permitted facility. The Contractor should provide the Engineer with a copy of the shipping manifest or bill of lading indicating the amount of material hauled to disposal and bearing the disposal site operator's confirmation for receipt of the material. Manifests should be submitted in accordance with Section 1-07.5(7).

9 LIMITATIONS

This report was prepared for the exclusive use of Sargent Engineers, Yakima County, and other members of the design team for specific application to the design of the CMP Project as it relates to the geotechnical aspects discussed in this report. Our conclusions and recommendations are intended for design of the Stage 3 of the alignment. The final version of report should be provided to a contractor for bidding and constructing the Project. The

interpretations, conclusions, and recommendations presented in this report should not be construed as a warranty of surficial or subsurface conditions.

Within the limitations of scope, schedule, and budget, the interpretations, conclusions, and recommendations presented in this report were prepared in accordance with generally accepted professional geotechnical engineering principles and practice in this area at the time this report was prepared. We make no other warranty, either express or implied.

The analyses, conclusions, and recommendations contained in this report are based on site conditions as they existed during our site visits and explorations, and further assume that the explorations are representative of the subsurface conditions throughout the CMP site, i.e., the subsurface conditions everywhere are not significantly different from those disclosed by the explorations. Our conclusions and recommendations are based on our understanding of the Project as described in this report and the site conditions as interpreted from the explorations.

If during construction, subsurface conditions different from those encountered in the explorations are observed or appear to be present, we should be advised at once so that we can review these conditions and reconsider our recommendations where necessary. If there is substantial lapse of time between submission of this report and the start of work at the site, or if conditions have changed because of natural forces or construction operations at or adjacent to the site, we recommend that this report be reviewed to determine the applicability of the conclusions and recommendations concerning the changed conditions or time lapse.

Unanticipated soil conditions are commonly encountered and cannot be fully determined by merely taking soil samples from a limited number of subsurface explorations. Such unexpected conditions frequently require that additional expenditures be made to attain a properly constructed Project. Therefore, some contingency funds are recommended to accommodate such potential extra costs.



The scope of our geotechnical services does not include evaluations regarding the presence or absence of wetlands, hazardous or toxic substances in the soil, surface water, groundwater, or air on, below, or around the site, or for the evaluation or disposal of contaminated soils or groundwater, should any be encountered.

We have prepared the document, "Important Information About Your Geotechnical/Environmental Report," to assist you and others in understanding the use and limitations of our report.

10 REFERENCES

- American Association of State Highway and Transportation Officials (AASHTO), 1993, AASHTO guide for design of pavement structures: Washington, D.C., AASHTO, 2 v.
- American Association of State Highway and Transportation Officials (AASHTO), 2020, AASHTO LRFD bridge design specifications (9th ed.): Washington, D.C., AASHTO, 2 v.
- Asphalt Institute, 1991, Thickness design: asphalt pavements for highways & streets (9th ed.): Lexington, Ky., Asphalt Institute, MS-1, 98 p.
- Bentley, R.D. and Campbell, N.P., 1983, Geologic map of the Yakima Quadrangle, Washington: Washington State Department of Natural Resources, Division of Geology and Earth Resources, Geologic Map GM-29, 1:62,500.
- Bjornstad, B.N., 1980, Sedimentology and depositional environment of the Touchet Beds, Walla Walla River Basin, Washington: Cheney, Wash., Eastern Washington University, Master's Thesis, 119 p.
- Bjornstad, B.N., 2006, On the trail of the Ice Age floods: a geological field guide to the mid-Columbia basin: Sandpoint, Idaho, Keokee Books, 307 p.
- Geo-Slope International, 2021, SIGMA/W v. 2021.4: Calgary, Alberta, Geo-Slope International.
- Google Earth, 2021, Aerial photo of I-82 and Industrial Road, Yakima, Washington: Photo dated July 4, 2021, accessed via Google Earth, September 13, 2022.
- Howard, A.K., 1996, Pipeline installation: a manual for construction of buried pipe: Lakewood, Colo., Relativity Pub.
- Lasmanis, R., 1991, The geology of Washington: Rocks & Minerals, v. 66, no. 4, p. 262-277.
- McCaffrey, Robert; King, R.W.; Wells, R.E.; and others, 2016, Contemporary deformation in the Yakima fold and thrust belt estimated with GPS: Geophysical Journal International, v. 207, no. 1, p. 1-11.
- Norman, D.K.; Busacca, A.J.; and Teissere, R.F., 2004, Geology of the Yakima valley wine country—a geologic field trip guide from Stevenson to Zillah, Washington: Olympia, Wash., Washington State Division of Geology and Earth Resources, 96th Annual Meeting of the Association of American State Geologists, Field Trip Guide 1, 13 p.

- Palmer, S.P.; Magsino, S.L.; Bilderback, E.L.; and others, 2004, Site class map of Yakima County, Washington, in Liquefaction susceptibility and site class maps of Washington State, by county: Washington State Department of Geology and Earth Resources, Open File Report 2004-20, sheet 39B, scale 1:150,000.
- Schuster, J.E., 1994, Geologic map of the east half of the Yakima 1:100,000 quadrangle, Washington: Washington State Department of Natural Resources, Division of Geology and Earth Resources, Open File Report 94-12, 19 p., 1 plate, scale 1:100,000.
- Shannon & Wilson, 2020, Final design, geotechnical engineering and environmental report, stages 1 and 2, East-West Corridor Project, Yakima County, Washington: Report prepared by Shannon & Wilson, Inc., Seattle, Wash., 21-1-22425-002, for HW Lochner, Lacey, Wash., February.
- Shannon & Wilson, in press, Hydraulics report, Cascade Mill Parkway, Phase 3, Yakima County, Washington: Report prepared by Shannon & Wilson, Inc., Seattle, Wash., 106384-003, for Sargent Engineers, Inc., Olympia, Wash.
- Washington State Department of Ecology, 2013, Model toxics control act regulation and statute: MTCA cleanup regulation, chapter 173-340 WAC; model toxics control act, chapter 70.105D RCW; uniform environmental covenants act, chapter 64.70 RCW (rev.): Olympia, Wash., Washington Dept. of Ecology, Publication no. 94.06, 324 p., available: <https://fortress.wa.gov/ecy/publications/summarypages/9406.html>.
- Washington State Department of Transportation (WSDOT), 2005, Everseries user's guide - pavement analysis computer software and case studies: Olympia, Wash., WSDOT Materials Laboratory, 112 p., available: <http://www.wsdot.wa.gov/NR/rdonlyres/0C02BB7B-C345-4958-AA08-089E5E512B96/0/EverseriesUserGuidePart1.pdf>.
- Washington State Department of Transportation (WSDOT), 2021, Standard specifications for road, bridge, and municipal construction: Olympia, Wash., WSDOT, Manual M 41-10, August, available: <https://www.wsdot.wa.gov/Publications/Manuals/M41-10.htm>.
- Washington State Department of Transportation (WSDOT), 2022a, Bridge design manual LRFD: Olympia, Wash., Manual M 23-50, June, available: <https://www.wsdot.wa.gov/Publications/Manuals/M23-50.htm>
- Washington State Department of Transportation (WSDOT), 2022b, Geotechnical design manual: Olympia, Wash., WSDOT, Manual M 46-03, 1 v., February, available: <https://www.wsdot.wa.gov/Publications/Manuals/M46-03.htm>.




SOURCE

Figure adapted from files XR-13179-182 Survey received 5-26-20, and YRB Layout to S&W_050822.dwg, received 5-9-22.



Cascade Mill Parkway Project Yakima, Washington	
VICINITY MAP	
March 2023	106384-002
SHANNON & WILSON, INC. <small>GEOTECHNICAL AND ENVIRONMENTAL CONSULTANTS</small>	FIG. 1

Filename: C:\Users\jrs\CAD Group\Dropbox\UDrive\SEA\106384\002\106384-002 Plan and Profiles.dwg Date: 03-21-2023 Login: JRS



Background image shows approx. extents of overexcavation and replacement performed by the City in 2021. All explorations shown were performed prior to overexcavation.


LEGEND

Designation and Approximate Location

B-9-21	Boring (Shannon & Wilson, 2021)	SB-13	Boring (SLR, 2009)
B-8-18	Boring (Shannon & Wilson, 2018)	North Test Hole	Test Pit (Yakima County, 2021)
B-8-17	Boring (Shannon & Wilson, 2017)	TP1-16	Test Pit (Landau, 2016)
EWC-B-02-14	Boring (Shannon & Wilson, 2015a)	TP-25	Test Pit (SLR, 2009)
TP-1-22	Test Pit (Shannon & Wilson, 2022)	GP-43	Gas Probe (Landau, 2016)
TP-P1-17	Test Pit (Shannon & Wilson, 2017)	GP-21	Gas Probe (SLR, 2009)
		MW-109	Monitoring Well (Landau, 2014)

NOTES


1. Sonic Core Borings performed by Holt Services Inc. under subcontract for Shannon & Wilson, Inc.
2. Test Pits and PITs excavated by Yakima County and observed by a Shannon & Wilson representative.
3. Horizontal Coordinate System is Washington State Plane, NAD83, South Zone, US Foot.



SOURCE

Figure adapted from files *XR-13179-182 Survey* received 5-26-20, and *YRB Layout to S&W_050822.dwg*, received 5-9-22. Aerial image from Google Earth dated 7-4-2021.

KEY PLAN



Cascade Mill Parkway Project
Yakima, Washington


SITE AND EXPLORATION PLAN

March 2023

106384-002

SHANNON & WILSON, INC.
GEOTECHNICAL AND ENVIRONMENTAL CONSULTANTS

FIG. 2
Sheet 1 of 2



LEGEND

Designation and Approximate Location

B-9-21 	Boring (Shannon & Wilson, 2021)	TP1-16 	Test Pit (Landau, 2016)
B-8-18 	Boring (Shannon & Wilson, 2018)	TP-25 	Test Pit (SLR, 2009)
B-8-17 	Boring (Shannon & Wilson, 2017)	GP-43 	Gas Probe (Landau, 2016)
EWC-B-02-14 	Boring (Shannon & Wilson, 2015a)	GP-21 	Gas Probe (SLR, 2009)
TP-P1-17 	Test Pit (Shannon & Wilson, 2017)	MW-109 	Monitoring Well (Landau, 2014)
SB-13 	Boring (SLR, 2009)		

NOTES

1. Sonic Core Borings performed by Holt Services Inc. under subcontract for Shannon & Wilson, Inc.
2. Test Pits and PITs excavated by Yakima County and observed by a Shannon & Wilson representative.
3. Horizontal Coordinate System is Washington State Plane, NAD83, South Zone, US Foot.

0 100 200

Scale in Feet

SOURCE

Figure adapted from files XR-13179-182 Survey received 5-26-20, and YRB Layout to S&W_050822.dwg, received 5-9-22. Aerial image from Google Earth dated 7-4-2021.

KEY PLAN



Cascade Mill Parkway Project
Yakima, Washington

SITE AND EXPLORATION PLAN


March 2023

106384-002





FIG. 2
Sheet 2 of 2

Filename: C:\Users\jrs\CAD Group\Dropbox\JDrive\SEA\106384\02\106384-002 Plan and Profiles.dwg Date: 03-21-2023 Login: JRS



- NOTES**
- Existing and proposed ground surfaces derived from Sargent file, *YRB Layout to S&W_072221.dwg*
 - Bridge structure and bridge ground surfaces adapted from Sargent, *YRB Layout to S&W_050822.dwg*, received 5-9-2022.
 - This subsurface cross section is generalized from materials observed in soil explorations. Variations may exist between cross section and actual conditions.
 - Some penetration resistance values and densities are artificially high due to the presence of gravel and cobbles, and do not reflect the relative density of the soil unit.

- SCOUR LEGEND**
- 1% (100-Year) AEP Scour
 - 0.2% (500-Year) AEP Scour
- BORING LEGEND**
- EWC-B-05-14 Boring Designation
 - EWC-TP-05-14 Test Pit Designation
 - (Proj. 13' N) Projected Distance



Cascade Mill Parkway Project
Yakima, Washington


GENERALIZED SUBSURFACE PROFILE A-A'

March 2023 106384-002

SHANNON & WILSON INC.
GEOTECHNICAL AND ENVIRONMENTAL CONSULTANTS



FIG. 3

Filename: C:\Users\jrs\CAD Group\Dropbox\LDriver_SEA\106384\002\106384-002 Plan and Profiles.dwg Date: 03-21-2023 Login: JRS



BORING LEGEND

- EWC-B-05-14** ← Boring Designation
- EWC-TP-05-14** ← Test Pit Designation
- (Proj. 13' N) ← Projected Distance




NOTES

1. Existing ground surface derived from LiDAR provided by the Puget Sound LiDAR Consortium.
2. This subsurface cross section is generalized from materials observed in soil explorations. Variations may exist between cross section and actual conditions.
3. Some penetration resistance values and densities are artificially high due to the presence of gravel and cobbles, and do not reflect the relative density of the soil unit.



Cascade Mill Parkway Project Yakima, Washington	
GENERALIZED SUBSURFACE PROFILE B-B'	
March 2023	106384-002
SHANNON & WILSON, INC. <small>GEOTECHNICAL AND ENVIRONMENTAL CONSULTANTS</small>	FIG. 4

Filename: C:\Users\jrs\CAD Group Dropbox\LDriver_SEA\106384\002\106384-002 Plan and Profiles.dwg Date: 03-21-2023 Login: JRS



BORING LEGEND


EWC-B-05-14 ← Boring Designation
EWC-TP-05-14 ← Test Pit Designation
 (Proj. 13' N) ← Projected Distance



NOTES

- Existing ground surface derived from LiDAR provided by the Puget Sound LiDAR Consortium.
- This subsurface cross section is generalized from materials observed in soil explorations. Variations may exist between cross section and actual conditions.
- Some penetration resistance values and densities are artificially high due to the presence of gravel and cobbles, and do not reflect the relative density of the soil unit.

Cascade Mill Parkway Project Yakima, Washington	
GENERALIZED SUBSURFACE PROFILE C-C'	
March 2023	106384-002
SHANNON & WILSON, INC. GEOTECHNICAL AND ENVIRONMENTAL CONSULTANTS	FIG. 5



Seismic Parameters

PGA = 0.14 g
 S_S = 0.31 g
 S₁ = 0.11 g
 A_s = 0.21 g
 S_{DS} = 0.48 g
 S_{D1} = 0.26 g
 F_{pga} = 1.52
 F_a = 1.55
 F_v = 2.38
 T₀ = 0.11 sec.
 T_S = 0.54 sec.

NOTES

1. We developed the design response spectrum based on guidance in WSDOT BDM (2022).
2. The safety evaluation earthquake (SEE) seismic design parameters are based on design ground motions with a 7 percent probability of exceedance in 75 years (975-year return period) for Site Class D.
3. The mapped SRA values are based on a probabilistic seismic hazard analysis performed by the USGS (Petersen and others, 2014).
4. WSDOT BDM = Washington state department of transportation bridge design manual; g = gravitational acceleration; PGA = peak ground acceleration; SRA = spectral response acceleration; USGS = U.S. Geological Survey.
5. Coordinates used for site (NAVD 88):
 Latitude = 46.6135°
 Longitude = -120.4912°

Cascade Mill Parkway Project
Yakima, Washington


**SEISMIC DESIGN RESPONSE SPECTRA
SITE CLASS = D**

March 2023

106384-002


ASSUMED SUBSURFACE PROFILE

Based on Nearby Explorations:
EWC-B-03-14



Bottom of Boring EWC-B-03-14 at Elevation ~956 ft. Boring Extrapolated to 880 ft.


SERVICE LIMIT
NOMINAL RESISTANCE (kips)



SERVICE LIMIT NOTES:

1. Recommended resistance factors per WSDOT GDM are 1.0 for both side and base resistance.
2. Per AASHTO guidelines, a detailed assessment of pile group settlement may be waived because they will be embedded in dense granular soils (AASHTO Section 10.8.2.2.4).


STRENGTH LIMIT
NOMINAL RESISTANCE (kips)



STRENGTH LIMIT NOTES:

1. Recommended compression resistance factors per WSDOT GDM are 0.55 and 0.5 for side and base resistance, respectively.
2. Shaft uplift resistance can be estimated by using the nominal side resistance shown above and a recommended resistance factor of 0.35 (per WSDOT GDM).

EXTREME EVENT LIMIT
NOMINAL RESISTANCE (kips)



EXTREME EVENT LIMIT NOTES:

1. Recommended resistance factors per WSDOT GDM for both side and base resistance are 1.0 for compression and 0.8 for uplift.

GENERAL NOTES

1. The analyses were performed based on guidelines included in the WSDOT Geotechnical Design Manual (GDM), AASHTO LRFD Bridge Design Specifications, and local experience. The analyses consider group action of closely spaced shafts (closer than 3 diameters, center to center).
2. Factored total shaft resistance shown on plots is determined by adding its nominal side and base resistances multiplied by the appropriate resistance factors as noted above.
3. Estimated shaft resistance assumes that if casing is used, it will be removed after the shaft installation. If, however, the casing is left in place, grouting should be used to fill all potential voids around the casing and the estimated resistance given above should be re-evaluated.

Cascade Mill Parkway Project
Yakima, Washington

**ESTIMATED AXIAL SHAFT RESISTANCE
YAKIMA RIVER BRIDGE PIER 1
6-FT DIAMETER**

March 2023


106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants


FIG. 7

ASSUMED SUBSURFACE PROFILE

Based on Nearby Explorations:
EWC-B-03-14, B-3-18




SERVICE LIMIT
NOMINAL RESISTANCE (kips)




- SERVICE LIMIT NOTES:**
- Recommended resistance factors per WSDOT GDM are 1.0 for both side and base resistance.
 - Per AASHTO guidelines, a detailed assessment of pile group settlement may be waived because they will be embedded in dense granular soils (AASHTO Section 10.8.2.2.4).

STRENGTH LIMIT
NOMINAL RESISTANCE (kips)



- STRENGTH LIMIT NOTES:**
- Recommended compression resistance factors per WSDOT GDM are 0.55 and 0.5 for side and base resistance, respectively.
 - Shaft uplift resistance can be estimated by using the nominal side resistance shown above and a recommended resistance factor of 0.35 (per WSDOT GDM).

EXTREME EVENT LIMIT
NOMINAL RESISTANCE (kips)



- EXTREME EVENT LIMIT NOTES:**
- Recommended resistance factors per WSDOT GDM for both side and base resistance are 1.0 for compression and 0.8 for uplift.

GENERAL NOTES

- The analyses were performed based on guidelines included in the WSDOT Geotechnical Design Manual (GDM), AASHTO LRFD Bridge Design Specifications, and local experience. The analyses consider group action of closely spaced shafts (closer than 3 diameters, center to center).
- Factored total shaft resistance shown on plots is determined by adding its nominal side and base resistances multiplied by the appropriate resistance factors as noted above.
- Estimated shaft resistance assumes that if casing is used, it will be removed after the shaft installation. If, however, the casing is left in place, grouting should be used to fill all potential voids around the casing and the estimated resistance given above should be re-evaluated.

Cascade Mill Parkway Project
Yakima, Washington

**ESTIMATED AXIAL SHAFT RESISTANCE
YAKIMA RIVER BRIDGE PIER 2
10-FT DIAMETER**

March 2023


106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants


FIG. 8

ASSUMED SUBSURFACE PROFILE

Based on Nearby Explorations:
EWC-B-03-14, B-3-18




SERVICE LIMIT
NOMINAL RESISTANCE (kips)




- SERVICE LIMIT NOTES:**
1. Recommended resistance factors per WSDOT GDM are 1.0 for both side and base resistance.
 2. Per AASHTO guidelines, a detailed assessment of pile group settlement may be waived because they will be embedded in dense granular soils (AASHTO Section 10.8.2.2.4).

STRENGTH LIMIT
NOMINAL RESISTANCE (kips)



- STRENGTH LIMIT NOTES:**
1. Recommended compression resistance factors per WSDOT GDM are 0.55 and 0.5 for side and base resistance, respectively.
 2. Shaft uplift resistance can be estimated by using the nominal side resistance shown above and a recommended resistance factor of 0.35 (per WSDOT GDM).

EXTREME EVENT LIMIT
NOMINAL RESISTANCE (kips)



- EXTREME EVENT LIMIT NOTES:**
1. Recommended resistance factors per WSDOT GDM for both side and base resistance are 1.0 for compression and 0.8 for uplift.

GENERAL NOTES

1. The analyses were performed based on guidelines included in the WSDOT Geotechnical Design Manual (GDM), AASHTO LRFD Bridge Design Specifications, and local experience. The analyses consider group action of closely spaced shafts (closer than 3 diameters, center to center).
2. Factored total shaft resistance shown on plots is determined by adding its nominal side and base resistances multiplied by the appropriate resistance factors as noted above.
3. Estimated shaft resistance assumes that if casing is used, it will be removed after the shaft installation. If, however, the casing is left in place, grouting should be used to fill all potential voids around the casing and the estimated resistance given above should be re-evaluated.

Cascade Mill Parkway Project
Yakima, Washington

**ESTIMATED AXIAL SHAFT RESISTANCE
YAKIMA RIVER BRIDGE PIER 2
10-FT DIAMETER, WITH 100-YR SCOUR**

March 2023


106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants


FIG. 9

ASSUMED SUBSURFACE PROFILE

Based on Nearby Explorations:
EWC-B-03-14, B-3-18




SERVICE LIMIT
NOMINAL RESISTANCE (kips)




- SERVICE LIMIT NOTES:**
1. Recommended resistance factors per WSDOT GDM are 1.0 for both side and base resistance.
 2. Per AASHTO guidelines, a detailed assessment of pile group settlement may be waived because they will be embedded in dense granular soils (AASHTO Section 10.8.2.2.4).

STRENGTH LIMIT
NOMINAL RESISTANCE (kips)



- STRENGTH LIMIT NOTES:**
1. Recommended compression resistance factors per WSDOT GDM are 0.55 and 0.5 for side and base resistance, respectively.
 2. Shaft uplift resistance can be estimated by using the nominal side resistance shown above and a recommended resistance factor of 0.35 (per WSDOT GDM).

EXTREME EVENT LIMIT
NOMINAL RESISTANCE (kips)



- EXTREME EVENT LIMIT NOTES:**
1. Recommended resistance factors per WSDOT GDM for both side and base resistance are 1.0 for compression and 0.8 for uplift.

GENERAL NOTES

1. The analyses were performed based on guidelines included in the WSDOT Geotechnical Design Manual (GDM), AASHTO LRFD Bridge Design Specifications, and local experience. The analyses consider group action of closely spaced shafts (closer than 3 diameters, center to center).
2. Factored total shaft resistance shown on plots is determined by adding its nominal side and base resistances multiplied by the appropriate resistance factors as noted above.
3. Estimated shaft resistance assumes that if casing is used, it will be removed after the shaft installation. If, however, the casing is left in place, grouting should be used to fill all potential voids around the casing and the estimated resistance given above should be re-evaluated.

Cascade Mill Parkway Project
Yakima, Washington

**ESTIMATED AXIAL SHAFT RESISTANCE
YAKIMA RIVER BRIDGE PIER 2
10-FT DIAMETER, WITH 500-YR SCOUR**

March 2023


106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants


FIG. 10

ASSUMED SUBSURFACE PROFILE

Based on Nearby Explorations:
B-3-18




SERVICE LIMIT
NOMINAL RESISTANCE (kips)




- SERVICE LIMIT NOTES:**
1. Recommended resistance factors per WSDOT GDM are 1.0 for both side and base resistance.
 2. Per AASHTO guidelines, a detailed assessment of pile group settlement may be waived because they will be embedded in dense granular soils (AASHTO Section 10.8.2.2.4).

STRENGTH LIMIT
NOMINAL RESISTANCE (kips)



- STRENGTH LIMIT NOTES:**
1. Recommended compression resistance factors per WSDOT GDM are 0.55 and 0.5 for side and base resistance, respectively.
 2. Shaft uplift resistance can be estimated by using the nominal side resistance shown above and a recommended resistance factor of 0.35 (per WSDOT GDM).

EXTREME EVENT LIMIT
NOMINAL RESISTANCE (kips)



- EXTREME EVENT LIMIT NOTES:**
1. Recommended resistance factors per WSDOT GDM for both side and base resistance are 1.0 for compression and 0.8 for uplift.

GENERAL NOTES

1. The analyses were performed based on guidelines included in the WSDOT Geotechnical Design Manual (GDM), AASHTO LRFD Bridge Design Specifications, and local experience. The analyses consider group action of closely spaced shafts (closer than 3 diameters, center to center).
2. Factored total shaft resistance shown on plots is determined by adding its nominal side and base resistances multiplied by the appropriate resistance factors as noted above.
3. Estimated shaft resistance assumes that if casing is used, it will be removed after the shaft installation. If, however, the casing is left in place, grouting should be used to fill all potential voids around the casing and the estimated resistance given above should be re-evaluated.

Cascade Mill Parkway Project
Yakima, Washington

**ESTIMATED AXIAL SHAFT RESISTANCE
YAKIMA RIVER BRIDGE PIER 3
10-FT DIAMETER**

March 2023


106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants


FIG. 11

ASSUMED SUBSURFACE PROFILE

Based on Nearby Explorations:
B-3-18




SERVICE LIMIT
NOMINAL RESISTANCE (kips)




- SERVICE LIMIT NOTES:**
1. Recommended resistance factors per WSDOT GDM are 1.0 for both side and base resistance.
 2. Per AASHTO guidelines, a detailed assessment of pile group settlement may be waived because they will be embedded in dense granular soils (AASHTO Section 10.8.2.2.4).

STRENGTH LIMIT
NOMINAL RESISTANCE (kips)



- STRENGTH LIMIT NOTES:**
1. Recommended compression resistance factors per WSDOT GDM are 0.55 and 0.5 for side and base resistance, respectively.
 2. Shaft uplift resistance can be estimated by using the nominal side resistance shown above and a recommended resistance factor of 0.35 (per WSDOT GDM).

EXTREME EVENT LIMIT
NOMINAL RESISTANCE (kips)



- EXTREME EVENT LIMIT NOTES:**
1. Recommended resistance factors per WSDOT GDM for both side and base resistance are 1.0 for compression and 0.8 for uplift.

GENERAL NOTES

1. The analyses were performed based on guidelines included in the WSDOT Geotechnical Design Manual (GDM), AASHTO LRFD Bridge Design Specifications, and local experience. The analyses consider group action of closely spaced shafts (closer than 3 diameters, center to center).
2. Factored total shaft resistance shown on plots is determined by adding its nominal side and base resistances multiplied by the appropriate resistance factors as noted above.
3. Estimated shaft resistance assumes that if casing is used, it will be removed after the shaft installation. If, however, the casing is left in place, grouting should be used to fill all potential voids around the casing and the estimated resistance given above should be re-evaluated.

Cascade Mill Parkway Project
Yakima, Washington

**ESTIMATED AXIAL SHAFT RESISTANCE
YAKIMA RIVER BRIDGE PIER 3
10-FT DIAMETER, WITH 100-YR SCOUR**

March 2023


106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants


FIG. 12

ASSUMED SUBSURFACE PROFILE

Based on Nearby Explorations:
B-3-18




SERVICE LIMIT
NOMINAL RESISTANCE (kips)




- SERVICE LIMIT NOTES:**
1. Recommended resistance factors per WSDOT GDM are 1.0 for both side and base resistance.
 2. Per AASHTO guidelines, a detailed assessment of pile group settlement may be waived because they will be embedded in dense granular soils (AASHTO Section 10.8.2.2.4).

STRENGTH LIMIT
NOMINAL RESISTANCE (kips)



- STRENGTH LIMIT NOTES:**
1. Recommended compression resistance factors per WSDOT GDM are 0.55 and 0.5 for side and base resistance, respectively.
 2. Shaft uplift resistance can be estimated by using the nominal side resistance shown above and a recommended resistance factor of 0.35 (per WSDOT GDM).

EXTREME EVENT LIMIT
NOMINAL RESISTANCE (kips)



- EXTREME EVENT LIMIT NOTES:**
1. Recommended resistance factors per WSDOT GDM for both side and base resistance are 1.0 for compression and 0.8 for uplift.

GENERAL NOTES

1. The analyses were performed based on guidelines included in the WSDOT Geotechnical Design Manual (GDM), AASHTO LRFD Bridge Design Specifications, and local experience. The analyses consider group action of closely spaced shafts (closer than 3 diameters, center to center).
2. Factored total shaft resistance shown on plots is determined by adding its nominal side and base resistances multiplied by the appropriate resistance factors as noted above.
3. Estimated shaft resistance assumes that if casing is used, it will be removed after the shaft installation. If, however, the casing is left in place, grouting should be used to fill all potential voids around the casing and the estimated resistance given above should be re-evaluated.

Cascade Mill Parkway Project
Yakima, Washington

**ESTIMATED AXIAL SHAFT RESISTANCE
YAKIMA RIVER BRIDGE PIER 3
10-FT DIAMETER, WITH 500-YR SCOUR**

March 2023



106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants


FIG. 13

ASSUMED SUBSURFACE PROFILE


Based on Nearby Explorations:
B-3-18, EWC-B-04-14



- SERVICE LIMIT NOTES:**
1. Recommended resistance factors per WSDOT GDM are 1.0 for both side and base resistance.
 2. Per AASHTO guidelines, a detailed assessment of pile group settlement may be waived because they will be embedded in dense granular soils (AASHTO Section 10.8.2.2.4).



- STRENGTH LIMIT NOTES:**
1. Recommended compression resistance factors per WSDOT GDM are 0.55 and 0.5 for side and base resistance, respectively.
 2. Shaft uplift resistance can be estimated by using the nominal side resistance shown above and a recommended resistance factor of 0.35 (per WSDOT GDM).



- EXTREME EVENT LIMIT NOTES:**
1. Recommended resistance factors per WSDOT GDM for both side and base resistance are 1.0 for compression and 0.8 for uplift.

GENERAL NOTES

1. The analyses were performed based on guidelines included in the WSDOT Geotechnical Design Manual (GDM), AASHTO LRFD Bridge Design Specifications, and local experience. The analyses consider group action of closely spaced shafts (closer than 3 diameters, center to center).
2. Factored total shaft resistance shown on plots is determined by adding its nominal side and base resistances multiplied by the appropriate resistance factors as noted above.
3. Estimated shaft resistance assumes that if casing is used, it will be removed after the shaft installation. If, however, the casing is left in place, grouting should be used to fill all potential voids around the casing and the estimated resistance given above should be re-evaluated.

Cascade Mill Parkway Project
Yakima, Washington

**ESTIMATED AXIAL SHAFT RESISTANCE
YAKIMA RIVER BRIDGE PIER 4
10-FT DIAMETER**

March 2023


106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants


FIG. 14

ASSUMED SUBSURFACE PROFILE

Based on Nearby Explorations:
B-3-18, EWC-B-04-14




SERVICE LIMIT
NOMINAL RESISTANCE (kips)




- SERVICE LIMIT NOTES:**
1. Recommended resistance factors per WSDOT GDM are 1.0 for both side and base resistance.
 2. Per AASHTO guidelines, a detailed assessment of pile group settlement may be waived because they will be embedded in dense granular soils (AASHTO Section 10.8.2.2.4).

STRENGTH LIMIT
NOMINAL RESISTANCE (kips)



- STRENGTH LIMIT NOTES:**
1. Recommended compression resistance factors per WSDOT GDM are 0.55 and 0.5 for side and base resistance, respectively.
 2. Shaft uplift resistance can be estimated by using the nominal side resistance shown above and a recommended resistance factor of 0.35 (per WSDOT GDM).

EXTREME EVENT LIMIT
NOMINAL RESISTANCE (kips)



- EXTREME EVENT LIMIT NOTES:**
1. Recommended resistance factors per WSDOT GDM for both side and base resistance are 1.0 for compression and 0.8 for uplift.

GENERAL NOTES

1. The analyses were performed based on guidelines included in the WSDOT Geotechnical Design Manual (GDM), AASHTO LRFD Bridge Design Specifications, and local experience. The analyses consider group action of closely spaced shafts (closer than 3 diameters, center to center).
2. Factored total shaft resistance shown on plots is determined by adding its nominal side and base resistances multiplied by the appropriate resistance factors as noted above.
3. Estimated shaft resistance assumes that if casing is used, it will be removed after the shaft installation. If, however, the casing is left in place, grouting should be used to fill all potential voids around the casing and the estimated resistance given above should be re-evaluated.

Cascade Mill Parkway Project
Yakima, Washington

**ESTIMATED AXIAL SHAFT RESISTANCE
YAKIMA RIVER BRIDGE PIER 4
10-FT DIAMETER, WITH 100-YR SCOUR**

March 2023


106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants


FIG. 15

ASSUMED SUBSURFACE PROFILE

Based on Nearby Explorations:
B-3-18, EWC-B-04-14




SERVICE LIMIT
NOMINAL RESISTANCE (kips)




- SERVICE LIMIT NOTES:**
1. Recommended resistance factors per WSDOT GDM are 1.0 for both side and base resistance.
 2. Per AASHTO guidelines, a detailed assessment of pile group settlement may be waived because they will be embedded in dense granular soils (AASHTO Section 10.8.2.2.4).

STRENGTH LIMIT
NOMINAL RESISTANCE (kips)



- STRENGTH LIMIT NOTES:**
1. Recommended compression resistance factors per WSDOT GDM are 0.55 and 0.5 for side and base resistance, respectively.
 2. Shaft uplift resistance can be estimated by using the nominal side resistance shown above and a recommended resistance factor of 0.35 (per WSDOT GDM).

EXTREME EVENT LIMIT
NOMINAL RESISTANCE (kips)



- EXTREME EVENT LIMIT NOTES:**
1. Recommended resistance factors per WSDOT GDM for both side and base resistance are 1.0 for compression and 0.8 for uplift.

GENERAL NOTES

1. The analyses were performed based on guidelines included in the WSDOT Geotechnical Design Manual (GDM), AASHTO LRFD Bridge Design Specifications, and local experience. The analyses consider group action of closely spaced shafts (closer than 3 diameters, center to center).
2. Factored total shaft resistance shown on plots is determined by adding its nominal side and base resistances multiplied by the appropriate resistance factors as noted above.
3. Estimated shaft resistance assumes that if casing is used, it will be removed after the shaft installation. If, however, the casing is left in place, grouting should be used to fill all potential voids around the casing and the estimated resistance given above should be re-evaluated.

Cascade Mill Parkway Project
Yakima, Washington

**ESTIMATED AXIAL SHAFT RESISTANCE
YAKIMA RIVER BRIDGE PIER 4
10-FT DIAMETER, WITH 500-YR SCOUR**

March 2023


106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. 16


ASSUMED SUBSURFACE PROFILE

Based on Nearby Explorations:
EWC-B-04-14



Bottom of Boring EWC-B-04-14 at Elevation ~947 ft. Boring Extrapolated to 880 ft.


SERVICE LIMIT
NOMINAL RESISTANCE (kips)



SERVICE LIMIT NOTES:

1. Recommended resistance factors per WSDOT GDM are 1.0 for both side and base resistance.
2. Per AASHTO guidelines, a detailed assessment of pile group settlement may be waived because they will be embedded in dense granular soils (AASHTO Section 10.8.2.2.4).


STRENGTH LIMIT
NOMINAL RESISTANCE (kips)



STRENGTH LIMIT NOTES:

1. Recommended compression resistance factors per WSDOT GDM are 0.55 and 0.5 for side and base resistance, respectively.
2. Shaft uplift resistance can be estimated by using the nominal side resistance shown above and a recommended resistance factor of 0.35 (per WSDOT GDM).

EXTREME EVENT LIMIT
NOMINAL RESISTANCE (kips)



EXTREME EVENT LIMIT NOTES:

1. Recommended resistance factors per WSDOT GDM for both side and base resistance are 1.0 for compression and 0.8 for uplift.

GENERAL NOTES

1. The analyses were performed based on guidelines included in the WSDOT Geotechnical Design Manual (GDM), AASHTO LRFD Bridge Design Specifications, and local experience. The analyses consider group action of closely spaced shafts (closer than 3 diameters, center to center).
2. Factored total shaft resistance shown on plots is determined by adding its nominal side and base resistances multiplied by the appropriate resistance factors as noted above.
3. Estimated shaft resistance assumes that if casing is used, it will be removed after the shaft installation. If, however, the casing is left in place, grouting should be used to fill all potential voids around the casing and the estimated resistance given above should be re-evaluated.

Cascade Mill Parkway Project
Yakima, Washington

**ESTIMATED AXIAL SHAFT RESISTANCE
YAKIMA RIVER BRIDGE PIER 5
6-FT DIAMETER**

March 2023

106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. 17

Table 18-1 - LPILE Parameters by Elevation

Soil Description	Top Elevation of Layer (See Table Below)	Effective Unit Weight (pcf)	Unscoured Conditions			Scoured Conditions					
			LPILE Model	Friction Angle, ϕ (degrees)	Initial Modulus of Subgrade Reaction, k (pci)	LPILE Model	Friction Angle, ϕ (degrees)	Initial Modulus of Subgrade Reaction, k (pci)	Undrained Cohesion, c (psf)	Strain Factor E50	Ground Slope Angle, β (deg)
Quaternary Alluvium	E	77.6	Sand (Reese)	40	95	Soft Clay (Reese)	--	--	1	1	β
Quaternary Alluvium	S	77.6	Sand (Reese)	40	95	Sand (Reese)	40	95	--	--	β


Table 18-2 - Design Elevations

Location	Elevation E (feet)	Elevation S (feet)	Note
Pier 1	See Note 2	S = E	No Scour (See Note 3)
Pier 2	1037	1005	--
Pier 3	1045	1005	--
Pier 4	1042	1005	--
Pier 5 - Riprap Option	See Note 2	S = E	See Sketch "Riprap Option"


Table 18-3 - Ground Slopes

Location	Ground Slope Angle, β (deg)
Pier 1	See Note 3
Pier 2	0
Pier 3	0
Pier 4	0
Pier 5 - Riprap Option	26.6

Piers 2, 3, and 4 Geometry Sketch




Pier 5 Geometry Sketch - Riprap Option




NOTES

1. pcf = pounds per cubic foot; pci = pounds per cubic inch; psf = pounds per square foot
2. Top of shaft elevations to be determined by structural engineer.
3. Scour is not anticipated at Pier 1 because it is located behind a levee. We assume the levee will have adequate scour protection during the design flood event. Apply soil parameters from below Elevation S (second row in Table 18-1) to all layers in LPILE model for Pier 1.

Cascade Mill Parkway Yakima, Washington	
YAKIMA RIVER BRIDGE LPILE PARAMETERS FOR LATERAL DEEP FOUNDATION ANALYSIS	
March 2023	106384-002
 SHANNON & WILSON, INC. GEOTECHNICAL AND ENVIRONMENTAL CONSULTANTS	FIG. 18


File: C:\Users\jrs\CAD Group\Dropbox\UDrive_SEA\106384\002\106384-002 Surcharge Loading.dwg Date: 09-08-2022 Author: JRS



ELEVATION VIEW


For $m \leq 0.4$: $\sigma_H = 0.28 \frac{Q_p}{H^2} \frac{n^2}{(0.16 + n^2)^3}$ (psf) (see Note 3)

For $m > 0.4$: $\sigma_H = 1.77 \frac{Q_p}{H^2} \frac{m^2 n^2}{(m^2 + n^2)^3}$ (psf)



PLAN VIEW

**A) LATERAL PRESSURE DUE TO POINT LOAD
i.e. SMALL ISOLATED FOOTING OR WHEEL LOAD**
(NAVFAC DM 7.2, 1986)




ELEVATION VIEW

For $m \leq 0.4$: $\sigma_H = 0.20 \frac{Q_l}{H} \frac{n}{(0.16 + n^2)^2}$ (psf) (see Note 3)


For $m > 0.4$: $\sigma_H = 1.28 \frac{Q_l}{H} \frac{m^2 n}{(m^2 + n^2)^2}$ (psf)

**B) LATERAL PRESSURE DUE TO LINE LOAD
i.e. NARROW CONTINUOUS FOOTING
PARALLEL TO WALL**
(NAVFAC DM 7.02, 1986)




$\sigma_H = \frac{2q}{\pi} [\delta - \sin \delta \cos (\delta + 2\alpha)]$ (psf)
in radians

C) LATERAL PRESSURE DUE TO STRIP LOAD
(AASHTO LRFD Bridge Design Specifications, 2020)




EARTH BERM



UNIFORM SURCHARGE

**D) LATERAL PRESSURE DUE TO EARTH BERM
OR UNIFORM SURCHARGE**
(derived from Poulos and Davis, *Elastic Solutions for Soil and Rock Mechanics*, 1974; and Terzaghi and Peck, *Soil Mechanics in Engineering Practice*, 1967)



E) LATERAL PRESSURE DUE TO ADJACENT FOOTING
(see Notes 5 and 6)

(derived from NAVFAC DM 7.02, 1986; and Sandhu, *Earth Pressure on Walls Due to Surcharge*, 1974)

NOTES

- Figures are not drawn to scale.
- Applicable surcharge pressures should be added to appropriate permanent wall lateral earth and water pressure.
- If point or line loads are close to the back of the wall such that $m \leq 0.4$, it may be more appropriate to model the actual load distribution (i.e., Detail E) or use more rigorous analysis methods.
- See text and lateral load diagram exhibits for recommended K values.
- The stress is estimated on the back of the wall at the center of the length, L, of loading.
- The estimated stress is based on a Poisson's ratio of 0.5.


Cascade Mill Parkway Project
Yakima, Washington

**RECOMMENDED SURCHARGE
LOADING FOR TEMPORARY AND
PERMANENT WALLS**


March 2023 106384-002

SHANNON & WILSON, INC.
GEOTECHNICAL AND ENVIRONMENTAL CONSULTANTS


FIG. 19



CASE A EMBANKMENT DEAD LOAD W ON A CONDUIT BURIED IN A SOIL EMBANKMENT



CASE B C_w FOR CONDUIT IN A TRENCH



NOTES

1. W = total dead load per unit length.
2. Embankment dead loads shown in (a) are based on soil unit weight of 100 pcf. For different soil unit weights, adjust the loads proportionately.
3. For trench backfill shown in (b): $W = C_w (\gamma)(B)^2$
 where: γ = soil unit weight.
 B = trench width at top of pipe level.

 If backfill compacted adequately, a unit weight of 125 pcf is recommended for evaluation.
4. Live loads shown in (c) include effect of impact.
5. This figure was adapted from NAVFAC DM7.

FIG. 18

Cascade Mill Parkway Project
Yakima, Washington

LOADS ON BURIED UTILITIES

March 2023

106384-002

Appendix A

Subsurface Explorations

CONTENTS

A.1 INTRODUCTION A-1

A.2 SOIL CLASSIFICATION A-1

A.3 SOIL BORINGS A-1

 A.3.1 Sonic Core Drilling Procedures A-1

 A.3.2 Split-Spoon Soil Samples A-2

 A.3.3 Sonic Core Soil Review A-2

A.4 STAND-UP TEST PIT A-3

Exploration Logs

- Figure A-1: Soil Description and Log Key (2 sheets)
- Figure A-2: Log of Boring B-9-21 (6 sheets)
- Figure A-3: Log of Boring B-10-21 (6 sheets)
- Figure A-4: Log of Boring B-11P-21 (6 sheets)
- Figure A-5: Log of Boring B-12P-21 (6 sheets)
- Figure A-6: Log of Boring B-13-21 (4 sheets)
- Figure A-7: Log of Boring B-14-21 (4 sheets)
- Figure A-8: Log of Boring B-15P-21 (3 sheets)
- Test Pit Log, TP-1-22

A.1 INTRODUCTION

The subsurface exploration program for Cascade Mill Parkway Phase 3 Project alignment consisted of drilling and sampling seven borings.

We advanced the seven borings, designated B-9-21 through B-15P-21, to depths ranging between 40 to 100 feet. We installed vibrating wire piezometers in B-11P-21, B-12P-21, and B-15P-21.

Approximate locations of the borings and tests pits were recorded in the field using a geographic information system (GIS) application accessed on a cellular phone. The locations of the explorations are shown in Figure 2. The exploration locations and elevations should be considered accurate to the degree implied by the method used.

A.2 SOIL CLASSIFICATION

A representative from Shannon & Wilson was present throughout the field explorations to observe the drilling and sampling operations; retrieve representative soil samples for subsequent laboratory testing; and to prepare descriptive field logs of the explorations. Soil sample classifications were based on ASTM Designation D2487, Standard Practice for Classification of Soils for Engineering Purposes, and ASTM Designation D2488, Standard Practice for Description and Identification of Soils (Visual-Manual Procedure). The Unified Soil Classification System, as described in Figure A-1 of this appendix, was used to classify the soil. The exploration logs in the report represent our interpretation of the contents of the field logs.

A.3 SOIL BORINGS

A.3.1 Sonic Core Drilling Procedures

Holt Services Inc. of Edgewood, Washington, drilled the soil borings under subcontract to Shannon & Wilson using a Terra Sonic 150CC track-mounted drill rig, outfitted with an automatic hammer. The sonic core drilling method uses high-frequency vibratory motion applied to the top of the drill column, along with down-pressure and rotation, to obtain nearly continuous core samples in soil and rock.

Soil samples were obtained using a 4-inch-outside-diameter (OD) core barrel. As the drill column was advanced into the ground, soil entered the core barrel. After advancing the

core barrel a distance of 5 feet (termed a core “run”), a 6-inch OD temporary casing was vibrated to the bottom of the sample interval. The drill column and core barrel were then removed from the borehole and the soil core was extracted from the core barrel into plastic bags. Soil recovered from each run was described in the field and logged by our field representative. The soil sample bags were then sealed to retain moisture and stored in core boxes for transport. After retrieval of the soil core for a specific interval, the casing was cleared of slough and the drill column and core barrel were advanced, starting at the bottom of the temporary casing.

A.3.2 Split-Spoon Soil Samples

Disturbed soil samples were obtained from the borings by a split-spoon sampler used in conjunction with a Standard Penetration Test (SPT) and the sonic core barrel. To obtain disturbed soil samples from the borings, SPTs were performed in general accordance with the ASTM Designation D1586, Standard Test Method for Standard Penetration Test and Split-Barrel Sampling of Soils. The SPTs were performed at 5-foot intervals to a depth of 40 feet, then 10-foot intervals thereafter, in between sonic core runs. The SPT consists of a 2-inch O.D., 1.375-inch-inside-diameter, split-spoon sampler driven 18 inches into the bottom of the borehole with a 140-pound hammer free falling 30 inches. The number of blows required to advance the split-spoon sampler the last 12 inches of penetration is termed the Standard Penetration Resistance (N-value). This value is an empirical parameter that provides a means of evaluating the relative density or compactness of cohesionless (granular) soils and the relative consistency (stiffness) of cohesive soils. This value is commonly used in engineering analyses to estimate soil strength and other characteristics. The terminology used to describe the relative density or consistency of the soils is presented in Figure A-1. Generally, when penetration resistances exceed 50 or more blows for 6 inches or less of penetration, the test is terminated, and the number of blows and corresponding penetration recorded. The N-values were recorded by our field representative and are plotted in the boring logs presented as Figures A-2 through A-8.

The split-spoon sampler used during the penetration test recovers a disturbed sample of the soil, which is useful for identification and classification purposes. The samples were classified and recorded in the field by our field representative. The samples were then sealed in jars to retain moisture and returned to our laboratory for testing.

A.3.3 Sonic Core Soil Review

Soil recovered from sonic core drilling was reviewed for identification and classification purposes and photographed in our warehouse. Grab samples were collected during our review and placed in labeled plastic jars and 5-gallon plastic bags, sealed, and transported to our laboratory for further analysis and testing.

A.4 STAND-UP TEST PIT

On May 22, 2022, a test pit, designated TP-1-22, was excavated in the outside shoulder of eastbound Interstate 82. The Washington State Department of Transportation advanced the test pit using a John Deere excavator mounted with a 3-foot-wide bucket. A Shannon & Wilson field representative was onsite to observe the process and log the test pit.

TP-1-22 was excavated at approximately 10 a.m. on Sunday, May 22. The test pit was 4 to 6 feet wide, by 13 feet long, by 9 to 12 feet deep. The test pit remained open for approximately 24 hours. We used a timelapse camera to observe the sidewall conditions during the 24-hour period and also made several visits to the test pit.

Upon arrival at the test pit the next morning, approximately 9 a.m. on Monday, May 23, we observed limited localized sidewall caving and minor erosion of fine sand and silt had occurred during the 24-hour period; however, the volumes were small. The test pit log for TP-1-22 shows overall beginning and ending photographs. The small volumes of erosion can be visualized by comparing the base of the excavation.

We observed that physical disturbance of the sidewalls (e.g., bumping from the excavator bucket or walking too close to the edge of the pit) caused minor sloughing due to the dry nature of the fill. This sloughing occurred immediately at the time of the disturbance.

We observed that the in-place density and compaction of the embankment material at the west, north, and south sidewalls of the test pit was relatively loose with some apparent cohesion in the upper few feet. We attribute this relatively loose layer to the test pit being located on the side slope of the embankment. In contrast, the east sidewall of the test pit, which was beneath the pavement, appeared to be more compact.

Shannon & Wilson uses a soil identification system modified from the Unified Soil Classification System (USCS). Elements of the USCS and other definitions are provided on this and the following page. Soil descriptions are based on visual-manual procedures (ASTM D2488) and laboratory testing procedures (ASTM D2487), if performed.

Structure¹

Interbedded	Alternating layers of varying material or color with layers at least 1/4-inch-thick; singular: bed.
Laminated	Alternating layers of varying material or color with layers less than 1/4-inch-thick; singular: lamination.
Fissured	Breaks along definite planes or fractures with little resistance.
Slickensided	Fracture planes appear polished or glossy; sometimes striated.
Blocky	Cohesive soil that can be broken down into small angular lumps that resist further breakdown.
Lensed	Inclusion of small pockets of different soils, such as small lenses of sand scattered through a mass of clay.
Homogeneous	Same color and appearance throughout.

Gradation

Poorly Graded	Narrow range of grain sizes present or, within the range of grain sizes present, one or more sizes are missing (Gap Graded). Meets criteria in ASTM D2487, if tested.
Well-Graded	Full range and even distribution of grain sizes present. Meets criteria in ASTM D2487, if tested.

Cementation¹

Weak	Crumbles/breaks with handling or slight finger pressure.
Moderate	Crumbles or breaks with considerable finger pressure.
Strong	Will not crumble or break with finger pressure.

Angularity and Shape¹

Angular	Sharp edges and unpolished planar surfaces.
Subangular	Similar to angular, but with rounded edges.
Subrounded	Nearly planar sides with well-rounded edges.
Rounded	Smoothly curved sides with no edges.
Flat	Width/thickness ratio > 3.
Elongated	Length/width ratio > 3.

Plasticity²

Nonplastic	Cannot roll a 1/8-in. thread at any water content.	PI < 4
Low	A thread can barely be rolled and a lump cannot be formed when drier than the plastic limit.	4 < PI < 10
Medium	A thread is easy to roll and not much time is required to reach the plastic limit. The thread cannot be rerolled after reaching the plastic limit. A lump crumbles when drier than the plastic limit.	10 < PI < 20
Hard	It takes considerable time rolling and kneading to reach the plastic limit. A thread can be rerolled several times after reaching the plastic limit. A lump can be formed without crumbling when drier than the plastic limit.	PI > 21

Standard Penetration Test (SPT)³

Hammer	140 pounds with a 30-inch free fall. Rope on 6- to 10-inch-diameter cathead 2-1/4 rope turns, > 100 rpm. If automatic hammers are used, blow counts shown on boring logs should be adjusted to account for efficiency of hammer.
Sampler	10 to 30 inches long Shoe I.D. = 1.375 inches Barrel I.D. = 1.5 inches Barrel O.D. = 2 inches
N-Value	Sum blow counts for second and third 6-inch increments. Refusal: 50 blows for 6 inches or less or 10 blows for 0 inch.

Additional Terms

Mottled	Irregular patches of different colors.
Bioturbated	Soil disturbance or mixing by plants or animals.
Diamict	Nonsorted sediment; sand and gravel in silt and/or clay matrix.
Cuttings	Material brought to surface by drilling.
Slough	Material that caved from sides of borehole.
Sheared	Disturbed texture, mix of strengths.

Moisture Content

Dry	Absence of moisture, dusty, dry to the touch.
Moist	Damp but no visible water.
Wet	Visible free water, from below water table.

Notes:

¹Reprinted, with permission, from ASTM D2488 - 09a Standard Practice for Description and Identification of Soils (Visual-Manual Procedure), copyright ASTM International, 100 Barr Harbor Drive, West Conshohocken, PA 19428. A copy of the complete standard may be obtained from ASTM International, www.astm.org.

²Adapted, with permission, from ASTM D2488 - 09a Standard Practice for Description and Identification of Soils (Visual-Manual Procedure), copyright ASTM International, 100 Barr Harbor Drive, West Conshohocken, PA 19428. A copy of the complete standard may be obtained from ASTM International, www.astm.org.

³Penetration resistances (N-values) shown on boring logs are as recorded in the field and have not been corrected for hammer efficiency, overburden, or other factors.

Unified Soil Classification System (USCS)
Modified From USACE Tech Memo 3-357, ASTM D2487, and ASTM D2488

Major Divisions	Symbol	Typical Identifications		
Coarse-Grained Soils (more than 50% retained on No. 200 sieve)	Gravels (more than 50% of coarse fraction retained on No. 4 sieve)	Gravel (less than 5% fines)	GW Well-graded Gravel; Well-graded Gravel with Sand	
		GP Poorly Graded Gravel; Poorly Graded Gravel with Sand		
	Silty or Clayey Gravel (more than 12% fines)	GM Silty Gravel; Silty Gravel with Sand		
		GC Clayey Gravel; Clayey Gravel with Sand		
	Sands (50% or more of coarse fraction passes the No. 4 sieve)	Sand (less than 5% fines)	SW Well-graded Sand; Well-graded Sand with Gravel	
			SP Poorly Graded Sand; Poorly Graded Sand with Gravel	
		Silty or Clayey Sand (more than 12% fines)	SM Silty Sand; Silty Sand with Gravel	
			SC Clayey Sand; Clayey Sand with Gravel	
	Fine-Grained Soils (50% or more passes the No. 200 sieve)	Silt and Clays (liquid limit less than 50)	Inorganic	ML Silt; Silt with Sand or Gravel; Sandy or Gravelly Silt
			CL Lean Clay; Lean Clay with Sand or Gravel; Sandy or Gravelly Lean Clay	
Organic		OL Organic Silt or Clay; Organic Silt or Clay with Sand or Gravel; Sandy or Gravelly Organic Silt or Clay		
Silt and Clays (liquid limit 50 or more)		Inorganic	MH Elastic Silt; Elastic Silt with Sand or Gravel; Sandy or Gravelly Elastic Silt	
		CH Fat Clay; Fat Clay with Sand or Gravel; Sandy or Gravelly Fat Clay		
		Organic	OH Organic Silt or Clay; Organic Silt or Clay with Sand or Gravel; Sandy or Gravelly Organic Silt or Clay	
Highly Organic Soils	Primarily organic matter, dark in color, and organic odor	PT Peat or other highly organic soils (see ASTM D4427)		

Acronyms and Abbreviations

ATD At Time of Drilling	MgO Magnesium Oxide	psi Pounds per Square Inch
Diam. Diameter	mm Millimeter	PVC Polyvinyl Chloride
Elev. Elevation	MnO Manganese Oxide	rpm Rotations per Minute
ft Feet	NA Not Applicable or Not Available	SPT Standard Penetration Test
FeO Iron Oxide	NP Nonplastic	USCS Unified Soil Classification System
gal Gallons	O.D. Outside Diameter	q _u Unconfined Compressive Strength
Horiz. Horizontal	OW Observation Well	VWP Vibrating Wire Piezometer
HSA Hollow-Stem Auger	pcf Pounds per Cubic Foot	Vert. Vertical
I.D. Inside Diameter	PID Photoionization Detector	WOH Weight of Hammer
in Inches	PMT Pressuremeter Test	WOR Weight of Rods
lbs Pounds	ppm Parts per Million	Wt Weight

Well and Backfill Symbols

	Bentonite Cement Grout
	Bentonite Grout
	Bentonite Chips
	Silica Sand
	Perforated or Screened Casing
	Surface Cement Seal
	Asphalt or Cap
	Slough
	Inclinometer or Non-perforated Casing
	Instrumentation Riser or Electrical Lead
	Vibrating Wire Piezometer with Designation

**Relative Density
Cohesionless Soils**

N, SPT, Blows/ft	Relative Density
< 4	Very loose
4 - 10	Loose
10 - 30	Medium dense
30 - 50	Dense
> 50	Very dense

**Relative Consistency
Cohesive Soils**

N, SPT, Blows/ft	Relative Consistency
< 2	Very soft
2 - 4	Soft
4 - 8	Medium stiff
8 - 15	Stiff
15 - 30	Very stiff
> 30	Hard

Percentages^{1, 2}

Trace	< 5%
Few	5 to 10%
Little	15 to 25%
Some	30 to 45%
Mostly	50 to 100%


Notes:

Dual symbols (symbols separated by a hyphen, i.e., SP-SM, Sand with Silt) are used for soils with between 5% and 12% fines or when the liquid limit and plasticity index values plot in the CL-ML area of the plasticity chart. Graphics shown on the logs for these soil types are a combination of the two graphic symbols (e.g., SP and SM).

Borderline symbols (symbols separated by a slash, i.e., CL/ML, Lean Clay to Silt; SP-SM/SM, Sand with Silt to Silty Sand) indicate that the soil properties are close to the defining boundary between two groups.

No. 4 size = 4.75 mm = 0.187 in.; No. 200 size = 0.075 mm = 0.003 in.

Total Depth: <u>100.3 ft.</u>	Northing: <u>~ 466,877 ft.</u>	Drilling Method: <u>Sonic Core</u>	Hole Diam.: <u>6 in.</u>
Top Elevation: <u>~ 1083 ft.</u>	Easting: <u>~ 1,642,549 ft.</u>	Drilling Company: <u>Holt Services</u>	Rod Diam.: <u>NWJ</u>
Vert. Datum: <u>NAVD 88</u>	Station: <u>~</u>	Drill Rig Equipment: <u>Terrasonic 150CC</u>	Hammer Type: <u>Automatic</u>
Horiz. Datum: <u>~</u>	Offset: <u>~</u>	Other Comments: <u>~</u>	



CONTINUED NEXT SHEET
LEGEND

- * Sample Not Recovered
- E Environmental Sample Obtained
- Soil Core (as in Sonic Core Borings)
- 2.0" O.D. Split Spoon Sample
- Ground Water Level ATD

- ◇ % Fines (<0.075mm)
- % Water Content
- Plastic Limit —●— Liquid Limit
- Natural Water Content

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.
4. The hole location was measured from existing site features and should be considered approximate.

Cascade Mill Parkway
Yakima, Washington


LOG OF BORING B-09-21

March 2023 106384-002

SHANNON & WILSON, INC. **FIG. A-2**
Geotechnical and Environmental Consultants Sheet 1 of 6

Log: KXM Rev: SAW Typ: LKN MASTER LOG E_106384.GPJ SHAN_WIL_GDT 6/23/22

Total Depth: 100.3 ft. Northing: ~ 466,877 ft. Drilling Method: Sonic Core Hole Diam.: 6 in.
 Top Elevation: ~ 1083 ft. Easting: ~ 1,642,549 ft. Drilling Company: Holt Services Rod Diam.: NWJ
 Vert. Datum: NAVD 88 Station: ~ Drill Rig Equipment: Terrasonic 150CC Hammer Type: Automatic
 Horiz. Datum: ~ Offset: ~ Other Comments: ~



CONTINUED NEXT SHEET
LEGEND

- * Sample Not Recovered
- E Environmental Sample Obtained
- Soil Core (as in Sonic Core Borings)
- ┌ 2.0" O.D. Split Spoon Sample
- ∇ Ground Water Level ATD

- ◇ % Fines (<0.075mm)
- % Water Content
- Plastic Limit —●— Liquid Limit
- Natural Water Content

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.
4. The hole location was measured from existing site features and should be considered approximate.

Cascade Mill Parkway
Yakima, Washington

LOG OF BORING B-09-21

March 2023
106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants
FIG. A-2
Sheet 2 of 6

Log: KXM Rev: SAW Typ: LKN MASTER LOG E_106384.GPJ SHAN_WIL_GDT_6/23/22



Total Depth: 100.3 ft. Northing: ~ 466,877 ft. Drilling Method: Sonic Core Hole Diam.: 6 in.
 Top Elevation: ~ 1083 ft. Easting: ~ 1,642,549 ft. Drilling Company: Holt Services Rod Diam.: NWJ
 Vert. Datum: NAVD 88 Station: ~ Drill Rig Equipment: Terrasonic 150CC Hammer Type: Automatic
 Horiz. Datum: _____ Offset: ~ Other Comments: _____

SOIL DESCRIPTION
 Refer to the report text for a proper understanding of the subsurface materials and drilling methods. The stratification lines represent the approximate boundaries between material types, and the transition may be gradual.


Depth, ft.
 Symbol
 PID, ppm
 Samples
 Ground Water
 Depth, ft.

PENETRATION RESISTANCE (blows/foot)
 ▲ Hammer Wt. & Drop: 140 lbs / 30 inches


- Sprouted seed at about 42 feet.
 - Dark brown organic soil, wood fragments, and slight organic odor from about 42 to 43 feet.
 - Trace wood fragments at about 45 feet.



Medium dense to dense, gray-brown to brown, *Silty Gravel with Sand and Cobbles (GM)*; moist to wet below about 50 feet; subrounded cobbles; fine to coarse, subangular to subrounded gravel; fine to coarse sand; low plasticity.
 Alluvial Deposits (Qa)
 [Environmental sample B-09-21:48 collected at 48 feet.]



Medium dense to dense, brown to orange-brown, *Poorly Graded Gravel with Silt and Sand and Cobbles (GP-GM)* to



CONTINUED NEXT SHEET
LEGEND

- * Sample Not Recovered
- E Environmental Sample Obtained
- Soil Core (as in Sonic Core Borings)
- 2.0" O.D. Split Spoon Sample
- Ground Water Level ATD

- ◇ % Fines (<0.075mm)
- % Water Content
- Plastic Limit —●— Liquid Limit
- Natural Water Content

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.
4. The hole location was measured from existing site features and should be considered approximate.

Cascade Mill Parkway
 Yakima, Washington

LOG OF BORING B-09-21

March 2023


106384-002

SHANNON & WILSON, INC.
 Geotechnical and Environmental Consultants

FIG. A-2
 Sheet 3 of 6

Log: KXM Rev: SAW Typ: LKN MASTER LOG E: 106384.GPJ SHAN WIL GDT 6/23/22

Total Depth: 100.3 ft. Northing: ~ 466,877 ft. Drilling Method: Sonic Core Hole Diam.: 6 in.
 Top Elevation: ~ 1083 ft. Easting: ~ 1,642,549 ft. Drilling Company: Holt Services Rod Diam.: NWJ
 Vert. Datum: NAVD 88 Station: ~ Drill Rig Equipment: Terrasonic 150CC Hammer Type: Automatic
 Horiz. Datum: ~ Offset: ~ Other Comments: ~



CONTINUED NEXT SHEET
LEGEND

- * Sample Not Recovered
- E Environmental Sample Obtained
- Soil Core (as in Sonic Core Borings)
- 2.0" O.D. Split Spoon Sample
- Ground Water Level ATD

- % Fines (<0.075mm)
- % Water Content
- Plastic Limit Liquid Limit
- Natural Water Content

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.
4. The hole location was measured from existing site features and should be considered approximate.

Cascade Mill Parkway
 Yakima, Washington

LOG OF BORING B-09-21

March 2023


106384-002

SHANNON & WILSON, INC.
 Geotechnical and Environmental Consultants

FIG. A-2
 Sheet 4 of 6

Log: KXM Rev: SAW Typ: LKN MASTER LOG E_106384.GPJ SHAN_WIL_GDT 6/23/22

Total Depth: 100.3 ft. Northing: ~ 466,877 ft. Drilling Method: Sonic Core Hole Diam.: 6 in.
 Top Elevation: ~ 1083 ft. Easting: ~ 1,642,549 ft. Drilling Company: Holt Services Rod Diam.: NWJ
 Vert. Datum: NAVD 88 Station: ~ Drill Rig Equipment: Terrasonic 150CC Hammer Type: Automatic
 Horiz. Datum: _____ Offset: ~ Other Comments: _____



Log: KXM Rev: SAW Typ: LKN
MASTER LOG E_106384.GPJ SHAN_WIL_GDT 6/23/22

CONTINUED NEXT SHEET
LEGEND

- * Sample Not Recovered ▽ Ground Water Level ATD
- E Environmental Sample Obtained
- Soil Core (as in Sonic Core Borings)
- ┌ 2.0" O.D. Split Spoon Sample

- ◇ % Fines (<0.075mm)
- % Water Content
- Plastic Limit —●— Liquid Limit
- Natural Water Content

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.
4. The hole location was measured from existing site features and should be considered approximate.


Cascade Mill Parkway
Yakima, Washington

LOG OF BORING B-09-21

March 2023 106384-002

SHANNON & WILSON, INC. **FIG. A-2**
 Geotechnical and Environmental Consultants Sheet 5 of 6

Total Depth: 100.3 ft. Northing: ~ 466,877 ft. Drilling Method: Sonic Core Hole Diam.: 6 in.
 Top Elevation: ~ 1083 ft. Easting: ~ 1,642,549 ft. Drilling Company: Holt Services Rod Diam.: NWJ
 Vert. Datum: NAVD 88 Station: ~ Drill Rig Equipment: Terrasonic 150CC Hammer Type: Automatic
 Horiz. Datum: _____ Offset: ~ Other Comments: _____



Log: KXM Rev: SAW Typ: LKN MASTER LOG E: 106384.GPJ SHAN WIL GDT 6/23/22

LEGEND

- * Sample Not Recovered
- E Environmental Sample Obtained
- ☐ Soil Core (as in Sonic Core Borings)
- ⊥ 2.0" O.D. Split Spoon Sample
- ∇ Ground Water Level ATD
- ◇ % Fines (<0.075mm)
- % Water Content
- Plastic Limit —●— Liquid Limit
- Natural Water Content

- NOTES**
1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
 2. Groundwater level, if indicated above, is for the date specified and may vary.
 3. USCS designation is based on visual-manual classification and selected lab testing.
 4. The hole location was measured from existing site features and should be considered approximate.


Cascade Mill Parkway
Yakima, Washington

LOG OF BORING B-09-21

March 2023 106384-002

SHANNON & WILSON, INC. **FIG. A-2**
 Geotechnical and Environmental Consultants Sheet 6 of 6

Total Depth: <u>100.3 ft.</u>	Northing: <u>~ 466,794 ft.</u>	Drilling Method: <u>Sonic Core</u>	Hole Diam.: <u>6 in.</u>
Top Elevation: <u>~ 1081 ft.</u>	Easting: <u>~ 1,642,571 ft.</u>	Drilling Company: <u>Holt Services</u>	Rod Diam.: <u>NWJ</u>
Vert. Datum: <u>NAVD 88</u>	Station: <u>~</u>	Drill Rig Equipment: <u>Terrasonic 150CC</u>	Hammer Type: <u>Automatic</u>
Horiz. Datum: <u>~</u>	Offset: <u>~</u>	Other Comments: <u>~</u>	



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- E Environmental Sample Obtained
- Soil Core (as in Sonic Core Borings)
- 2.0" O.D. Split Spoon Sample
- Ground Water Level ATD
- ◇ % Fines (<0.075mm)
- % Water Content


NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.
4. The hole location was measured from existing site features and should be considered approximate.

Cascade Mill Parkway Yakima, Washington	
LOG OF BORING B-10-21	
March 2023	106384-002
SHANNON & WILSON, INC. Geotechnical and Environmental Consultants	FIG. A-3 Sheet 1 of 6

Log: KXM Rev: SAW Typ: LKN MASTER LOG E: 106384.GPJ SHAN WIL GDT 6/23/22

Total Depth: 100.3 ft. Northing: ~ 466,794 ft. Drilling Method: Sonic Core Hole Diam.: 6 in.
 Top Elevation: ~ 1081 ft. Easting: ~ 1,642,571 ft. Drilling Company: Holt Services Rod Diam.: NWJ
 Vert. Datum: NAVD 88 Station: ~ Drill Rig Equipment: Terrasonic 150CC Hammer Type: Automatic
 Horiz. Datum: ~ Offset: ~ Other Comments: ~



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- E Environmental Sample Obtained
- ☐ Soil Core (as in Sonic Core Borings)
- ┌ 2.0" O.D. Split Spoon Sample
- ▽ Ground Water Level ATD

- ◇ % Fines (<0.075mm)
- % Water Content

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.
4. The hole location was measured from existing site features and should be considered approximate.

Cascade Mill Parkway
Yakima, Washington

LOG OF BORING B-10-21

March 2023


106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. A-3
Sheet 2 of 6

Log: KXM Rev: SAW Typ: LKN MASTER LOG E_106384.GPJ SHAN_WIL_GDT 6/23/22

Total Depth: 100.3 ft. Northing: ~ 466,794 ft. Drilling Method: Sonic Core Hole Diam.: 6 in.
 Top Elevation: ~ 1081 ft. Easting: ~ 1,642,571 ft. Drilling Company: Holt Services Rod Diam.: NWJ
 Vert. Datum: NAVD 88 Station: ~ Drill Rig Equipment: Terrasonic 150CC Hammer Type: Automatic
 Horiz. Datum: _____ Offset: ~ Other Comments: _____



CONTINUED NEXT SHEET
LEGEND

- * Sample Not Recovered
- E Environmental Sample Obtained
- Soil Core (as in Sonic Core Borings)
- 2.0" O.D. Split Spoon Sample
- Ground Water Level ATD

- % Fines (<0.075mm)
- % Water Content

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.
4. The hole location was measured from existing site features and should be considered approximate.

Cascade Mill Parkway
 Yakima, Washington

LOG OF BORING B-10-21

March 2023


106384-002

SHANNON & WILSON, INC.
 Geotechnical and Environmental Consultants

FIG. A-3
 Sheet 3 of 6

Log: KXM Rev: SAW Typ: LKN MASTER LOG E: 106384.GPJ SHAN_WIL_GDT 6/23/22

Total Depth: 100.3 ft. Northing: ~ 466,794 ft. Drilling Method: Sonic Core Hole Diam.: 6 in.
 Top Elevation: ~ 1081 ft. Easting: ~ 1,642,571 ft. Drilling Company: Holt Services Rod Diam.: NWJ
 Vert. Datum: NAVD 88 Station: ~ Drill Rig Equipment: Terrasonic 150CC Hammer Type: Automatic
 Horiz. Datum: ~ Offset: ~ Other Comments: ~



CONTINUED NEXT SHEET
LEGEND

- * Sample Not Recovered
- E Environmental Sample Obtained
- Soil Core (as in Sonic Core Borings)
- ┌ 2.0" O.D. Split Spoon Sample
- ▽ Ground Water Level ATD
- ◇ % Fines (<0.075mm)
- % Water Content

NOTES

- Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
- Groundwater level, if indicated above, is for the date specified and may vary.
- USCS designation is based on visual-manual classification and selected lab testing.
- The hole location was measured from existing site features and should be considered approximate.

Cascade Mill Parkway
 Yakima, Washington

LOG OF BORING B-10-21

March 2023


106384-002

SHANNON & WILSON, INC.
 Geotechnical and Environmental Consultants

FIG. A-3
 Sheet 4 of 6

Log: KXM Rev: SAW Typ: LKN MASTER LOG E: 106384.GPJ SHAN_WIL_GDT 6/23/22

Total Depth: 100.3 ft. Northing: ~ 466,794 ft. Drilling Method: Sonic Core Hole Diam.: 6 in.
 Top Elevation: ~ 1081 ft. Easting: ~ 1,642,571 ft. Drilling Company: Holt Services Rod Diam.: NWJ
 Vert. Datum: NAVD 88 Station: ~ Drill Rig Equipment: Terrasonic 150CC Hammer Type: Automatic
 Horiz. Datum: ~ Offset: ~ Other Comments: ~



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- E Environmental Sample Obtained
- ☐ Soil Core (as in Sonic Core Borings)
- ⊥ 2.0" O.D. Split Spoon Sample
- ▽ Ground Water Level ATD
- ◇ % Fines (<0.075mm)
- % Water Content

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.
4. The hole location was measured from existing site features and should be considered approximate.

Cascade Mill Parkway
Yakima, Washington

LOG OF BORING B-10-21

March 2023

106384-002


SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. A-3
Sheet 5 of 6


Log: KXM Rev: SAW Typ: LKN MASTER LOG E_106384.GPJ SHAN_WIL_GDT 6/23/22

Total Depth: 100.4 ft. Northing: ~ 466,801 ft. Drilling Method: Sonic Core Hole Diam.: 6 in.
 Top Elevation: ~ 1080 ft. Easting: ~ 1,642,689 ft. Drilling Company: Holt Services Rod Diam.: NWJ
 Vert. Datum: NAVD 88 Station: ~ Drill Rig Equipment: Terrasonic 150CC Hammer Type: Automatic
 Horiz. Datum: ~ Offset: ~ Other Comments: ~

SOIL DESCRIPTION
 Refer to the report text for a proper understanding of the subsurface materials and drilling methods. The stratification lines represent the approximate boundaries between material types, and the transition may be gradual.



PENETRATION RESISTANCE (blows/foot)
 ▲ Hammer Wt. & Drop: 140 lbs / 30 inches



Asphalt.
 Gray-brown, *Silty Sand with Gravel (SM)*; moist; fine sand; fine to coarse, angular to subrounded gravel; fine to coarse sand, nonplastic.
 Road Fill (Hf)
 Medium dense to dense, gray-brown, *Silty Gravel with Sand and Cobbles (GM)*; moist; subrounded cobbles; fine to coarse, angular to subrounded gravel; fine to coarse sand; nonplastic to low plasticity.
 Embankment Fill (Hf)
 - Sandy gravel layer from 8 to 10 feet.
 Medium dense to dense, brown, *Well-Graded Gravel with Silt and Sand and Cobbles (GW-GM)*; moist; subrounded cobbles; fine to coarse, angular to subrounded gravel; fine to coarse sand; nonplastic to low plasticity.
 Embankment Fill (Hf)
 Medium dense to dense, gray-brown, *Silty Gravel with Sand and Cobbles (GM)*;

CONTINUED NEXT SHEET

LEGEND

* Sample Not Recovered		Well Screen and Sand Filter		% Fines (<0.075mm)
E Environmental Sample Obtained		Bentonite-Cement Grout		% Water Content
		Bentonite Chips/Pellets		Plastic Limit
		Bentonite Grout		Liquid Limit
		Ground Water Level in VWP		Natural Water Content

- NOTES**
1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
 2. Groundwater level, if indicated above, is for the date specified and may vary.
 3. USCS designation is based on visual-manual classification and selected lab testing.
 4. The hole location was measured from existing site features and should be considered approximate.

Cascade Mill Parkway
 Yakima, Washington

LOG OF BORING B-11P-21


March 2023 106384-002

SHANNON & WILSON, INC.
 Geotechnical and Environmental Consultants

FIG. A-4
 Sheet 1 of 6

MASTER LOG E_106384.GPJ SHAN_WIL.GDT 6/23/22 Log: KXM Rev: SAW Typ: LKN

Total Depth: 100.4 ft. Northing: ~ 466,801 ft. Drilling Method: Sonic Core Hole Diam.: 6 in.
 Top Elevation: ~ 1080 ft. Easting: ~ 1,642,689 ft. Drilling Company: Holt Services Rod Diam.: NWJ
 Vert. Datum: NAVD 88 Station: ~ Drill Rig Equipment: Terrasonic 150CC Hammer Type: Automatic
 Horiz. Datum: ~ Offset: ~ Other Comments: ~



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- E Environmental Sample Obtained
- [Symbol] Soil Core (as in Sonic Core Borings)
- [Symbol] 2.0" O.D. Split Spoon Sample
- [Symbol] Well Screen and Sand Filter
- [Symbol] Bentonite-Cement Grout
- [Symbol] Bentonite Chips/Pellets
- [Symbol] Bentonite Grout
- ▼ Ground Water Level in VWP
- ◇ % Fines (<0.075mm)
- % Water Content
- Plastic Limit
- Liquid Limit
- Natural Water Content

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.
4. The hole location was measured from existing site features and should be considered approximate.

Cascade Mill Parkway
Yakima, Washington

LOG OF BORING B-11P-21


March 2023 106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. A-4
Sheet 2 of 6

Log: KXM Rev: SAW Typ: LKN MASTER LOG E_106384.GPJ SHAN_WIL.GDT 6/23/22

Total Depth: 100.4 ft. Northing: ~ 466,801 ft. Drilling Method: Sonic Core Hole Diam.: 6 in.
 Top Elevation: ~ 1080 ft. Easting: ~ 1,642,689 ft. Drilling Company: Holt Services Rod Diam.: NWJ
 Vert. Datum: NAVD 88 Station: ~ Drill Rig Equipment: Terrasonic 150CC Hammer Type: Automatic
 Horiz. Datum: ~ Offset: ~ Other Comments: ~



Log: KXM Rev: SAW Typ: LKN
MASTER LOG E_106384.GPJ SHAN WIL GDT 6/23/22

CONTINUED NEXT SHEET
LEGEND

- | | | | |
|--------------------------------------|--|-----------------------------|--|
| * Sample Not Recovered | | Well Screen and Sand Filter | |
| E Environmental Sample Obtained | | Bentonite-Cement Grout | |
| Soil Core (as in Sonic Core Borings) | | Bentonite Chips/Pellets | |
| 2.0" O.D. Split Spoon Sample | | Bentonite Grout | |
- ▼ Ground Water Level in VWP

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.
4. The hole location was measured from existing site features and should be considered approximate.


Cascade Mill Parkway
Yakima, Washington

LOG OF BORING B-11P-21

March 2023 106384-002

SHANNON & WILSON, INC. Geotechnical and Environmental Consultants	FIG. A-4 Sheet 3 of 6
---	---------------------------------

Total Depth: 100.4 ft. Northing: ~ 466,801 ft. Drilling Method: Sonic Core Hole Diam.: 6 in.
 Top Elevation: ~ 1080 ft. Easting: ~ 1,642,689 ft. Drilling Company: Holt Services Rod Diam.: NWJ
 Vert. Datum: NAVD 88 Station: ~ Drill Rig Equipment: Terrasonic 150CC Hammer Type: Automatic
 Horiz. Datum: _____ Offset: ~ Other Comments: _____



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- E Environmental Sample Obtained
- Soil Core (as in Sonic Core Borings)
- 2.0" O.D. Split Spoon Sample
- Well Screen and Sand Filter
- Bentonite-Cement Grout
- Bentonite Chips/Pellets
- Bentonite Grout
- Ground Water Level in VWP

- ◇ % Fines (<0.075mm)
- % Water Content
- Plastic Limit
- Liquid Limit
- Natural Water Content

NOTES

- Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
- Groundwater level, if indicated above, is for the date specified and may vary.
- USCS designation is based on visual-manual classification and selected lab testing.
- The hole location was measured from existing site features and should be considered approximate.

Cascade Mill Parkway
Yakima, Washington

LOG OF BORING B-11P-21

March 2023


106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. A-4
Sheet 4 of 6

Log: KXM Rev: SAW Typ: LKN MASTER LOG E: 106384.GPJ SHAN WIL GDT 6/23/22

Total Depth: 100.4 ft. Northing: ~ 466,801 ft. Drilling Method: Sonic Core Hole Diam.: 6 in.
 Top Elevation: ~ 1080 ft. Easting: ~ 1,642,689 ft. Drilling Company: Holt Services Rod Diam.: NWJ
 Vert. Datum: NAVD 88 Station: ~ Drill Rig Equipment: Terrasonic 150CC Hammer Type: Automatic
 Horiz. Datum: ~ Offset: ~ Other Comments: ~



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- E Environmental Sample Obtained
- Soil Core (as in Sonic Core Borings)
- 2.0" O.D. Split Spoon Sample
- Well Screen and Sand Filter
- Bentonite-Cement Grout
- Bentonite Chips/Pellets
- Bentonite Grout
- Ground Water Level in VWP

- % Fines (<0.075mm)
- % Water Content
- Plastic Limit
- Liquid Limit
- Natural Water Content

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.
4. The hole location was measured from existing site features and should be considered approximate.

Cascade Mill Parkway
Yakima, Washington

LOG OF BORING B-11P-21

March 2023

106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. A-4
Sheet 5 of 6

Log: KXM Rev: SAW Typ: LKN MASTER LOG E_106384.GPJ SHAN_WIL.GDT 6/23/22

Total Depth: 100.4 ft. Northing: ~ 466,801 ft. Drilling Method: Sonic Core Hole Diam.: 6 in.
 Top Elevation: ~ 1080 ft. Easting: ~ 1,642,689 ft. Drilling Company: Holt Services Rod Diam.: NWJ
 Vert. Datum: NAVD 88 Station: ~ Drill Rig Equipment: Terrasonic 150CC Hammer Type: Automatic
 Horiz. Datum: _____ Offset: ~ Other Comments: _____

SOIL DESCRIPTION <i>Refer to the report text for a proper understanding of the subsurface materials and drilling methods. The stratification lines represent the approximate boundaries between material types, and the transition may be gradual.</i>	Depth, ft.	Symbol	PID, ppm	Samples	Ground Water	Depth, ft.	PENETRATION RESISTANCE (blows/foot)			
							▲ Hammer Wt. & Drop: <u>140 lbs / 30 inches</u>			
BOTTOM OF BORING COMPLETED 3/30/2021 NOTE: Where gravels exceeding one-half the inside diameter of the split spoon sampler, cobbles, or boulders are present, the SPT blow counts are not reliable indicators of soil density or stiffness per ASTM D1586. The interpreted relative densities for layers that meet these criteria presented in this boring log are based on density of nearby soil zones encountered and interpretation of the geologic depositional environment, instead of the blow count versus relative density relationship presented in Figure A-1.	100.4		0	S-14		0	20	40	60	
									50/5"	
							105			
							110			
						115				

LEGEND

* Sample Not Recovered		Well Screen and Sand Filter		% Fines (<0.075mm)
E Environmental Sample Obtained		Bentonite-Cement Grout		% Water Content
		Bentonite Chips/Pellets	Plastic Limit	—●— Liquid Limit
		Bentonite Grout	Natural Water Content	

Ground Water Level in VWP

NOTES

- Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
- Groundwater level, if indicated above, is for the date specified and may vary.
- USCS designation is based on visual-manual classification and selected lab testing.
- The hole location was measured from existing site features and should be considered approximate.

Cascade Mill Parkway
Yakima, Washington

LOG OF BORING B-11P-21


March 2023 106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. A-4
Sheet 6 of 6

Log: KXM Rev: SAW Typ: LKN MASTER LOG E: 106384.GPJ SHAN WIL GDT 6/23/22

Total Depth: 100.25 ft. Northing: ~ 466,922 ft. Drilling Method: Sonic Core Hole Diam.: 6 in.
 Top Elevation: ~ 1083 ft. Easting: ~ 1,642,650 ft. Drilling Company: Holt Services Rod Diam.: NWJ
 Vert. Datum: NAVD 88 Station: ~ Drill Rig Equipment: Terrasonic 150CC Hammer Type: Automatic
 Horiz. Datum: ~ Offset: ~ Other Comments: ~



CONTINUED NEXT SHEET

LEGEND	
* Sample Not Recovered	Well Screen and Sand Filter
E Environmental Sample Obtained	Bentonite-Cement Grout
Soil Core (as in Sonic Core Borings)	Bentonite Chips/Pellets
2.0" O.D. Split Spoon Sample	Bentonite Grout
	Ground Water Level in VWP

- NOTES**
1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
 2. Groundwater level, if indicated above, is for the date specified and may vary.
 3. USCS designation is based on visual-manual classification and selected lab testing.
 4. The hole location was measured from existing site features and should be considered approximate.

Cascade Mill Parkway
Yakima, Washington


LOG OF BORING B-12P-21

March 2023 106384-002

SHANNON & WILSON, INC. **FIG. A-5**
 Geotechnical and Environmental Consultants Sheet 1 of 6

Log: KXM Rev: SAW Typ: LKN MASTER LOG E_106384.GPJ SHAN WIL GDT 6/23/22

Total Depth: 100.25 ft. Northing: ~ 466,922 ft. Drilling Method: Sonic Core Hole Diam.: 6 in.
 Top Elevation: ~ 1083 ft. Easting: ~ 1,642,650 ft. Drilling Company: Holt Services Rod Diam.: NWJ
 Vert. Datum: NAVD 88 Station: ~ Drill Rig Equipment: Terrasonic 150CC Hammer Type: Automatic
 Horiz. Datum: _____ Offset: ~ Other Comments: _____



CONTINUED NEXT SHEET

LEGEND

* Sample Not Recovered		Well Screen and Sand Filter	◆ % Fines (<0.075mm)
E Environmental Sample Obtained		Bentonite-Cement Grout	● % Water Content
		Bentonite Chips/Pellets	Plastic Limit —●— Liquid Limit
		Bentonite Grout	Natural Water Content

▼ Ground Water Level in VWP

- NOTES**
1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
 2. Groundwater level, if indicated above, is for the date specified and may vary.
 3. USCS designation is based on visual-manual classification and selected lab testing.
 4. The hole location was measured from existing site features and should be considered approximate.

Cascade Mill Parkway
Yakima, Washington

LOG OF BORING B-12P-21


March 2023 106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. A-5
Sheet 2 of 6

Log: KXM Rev: SAW Typ: LKN MASTER LOG E_106384.GPJ SHAN WIL GDT 6/23/22

Total Depth: 100.25 ft. Northing: ~ 466,922 ft. Drilling Method: Sonic Core Hole Diam.: 6 in.
 Top Elevation: ~ 1083 ft. Easting: ~ 1,642,650 ft. Drilling Company: Holt Services Rod Diam.: NWJ
 Vert. Datum: NAVD 88 Station: ~ Drill Rig Equipment: Terrasonic 150CC Hammer Type: Automatic
 Horiz. Datum: _____ Offset: ~ Other Comments: _____



CONTINUED NEXT SHEET

LEGEND

* Sample Not Recovered	[Symbol]	Well Screen and Sand Filter	◇ % Fines (<0.075mm)
E Environmental Sample Obtained	[Symbol]	Bentonite-Cement Grout	● % Water Content
[Symbol] Soil Core (as in Sonic Core Borings)	[Symbol]	Bentonite Chips/Pellets	Plastic Limit —●— Liquid Limit
[Symbol] 2.0" O.D. Split Spoon Sample	[Symbol]	Bentonite Grout	Natural Water Content

▼ Ground Water Level in VWP

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.
4. The hole location was measured from existing site features and should be considered approximate.

Cascade Mill Parkway
Yakima, Washington


LOG OF BORING B-12P-21

March 2023 106384-002

SHANNON & WILSON, INC. **FIG. A-5**
 Geotechnical and Environmental Consultants Sheet 3 of 6

MASTER LOG E. 106384.GPJ SHAN WIL.GDT 6/23/22 Log: KXM Rev: SAW Typ: LKN

Total Depth: 100.25 ft. Northing: ~ 466,922 ft. Drilling Method: Sonic Core Hole Diam.: 6 in.
 Top Elevation: ~ 1083 ft. Easting: ~ 1,642,650 ft. Drilling Company: Holt Services Rod Diam.: NWJ
 Vert. Datum: NAVD 88 Station: ~ Drill Rig Equipment: Terrasonic 150CC Hammer Type: Automatic
 Horiz. Datum: _____ Offset: ~ Other Comments: _____



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered [Symbol] Well Screen and Sand Filter
- E Environmental Sample Obtained [Symbol] Bentonite-Cement Grout
- [Symbol] Soil Core (as in Sonic Core Borings) [Symbol] Bentonite Chips/Pellets
- [Symbol] 2.0" O.D. Split Spoon Sample [Symbol] Bentonite Grout
- ▼ Ground Water Level in VWP

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.
4. The hole location was measured from existing site features and should be considered approximate.

Cascade Mill Parkway
Yakima, Washington

LOG OF BORING B-12P-21


March 2023 106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. A-5
Sheet 4 of 6

Log: KXM Rev: SAW Typ: LKN MASTER LOG E_106384.GPJ SHAN WIL.GDT 6/23/22

Total Depth: 100.25 ft. Northing: ~ 466,922 ft. Drilling Method: Sonic Core Hole Diam.: 6 in.
 Top Elevation: ~ 1083 ft. Easting: ~ 1,642,650 ft. Drilling Company: Holt Services Rod Diam.: NWJ
 Vert. Datum: NAVD 88 Station: ~ Drill Rig Equipment: Terrasonic 150CC Hammer Type: Automatic
 Horiz. Datum: _____ Offset: ~ Other Comments: _____



Log: KXM Rev: SAW Typ: LKN
MASTER LOG E_106384.GPJ SHAN WIL GDT 6/23/22

LEGEND

* Sample Not Recovered		Well Screen and Sand Filter		% Fines (<0.075mm)
E Environmental Sample Obtained		Bentonite-Cement Grout		% Water Content
	Soil Core (as in Sonic Core Borings)	Bentonite Chips/Pellets	Plastic Limit —●— Liquid Limit	
	2.0" O.D. Split Spoon Sample	Bentonite Grout	Natural Water Content	
		Ground Water Level in VWP		

- NOTES**
1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
 2. Groundwater level, if indicated above, is for the date specified and may vary.
 3. USCS designation is based on visual-manual classification and selected lab testing.
 4. The hole location was measured from existing site features and should be considered approximate.

Cascade Mill Parkway
Yakima, Washington


LOG OF BORING B-12P-21

March 2023 106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. A-5
Sheet 6 of 6

Total Depth: 65.3 ft. Northing: ~ 466,976 ft. Drilling Method: Sonic Core Hole Diam.: 6 in.
 Top Elevation: ~ 1084 ft. Easting: ~ 1,642,570 ft. Drilling Company: Holt Services Rod Diam.: NWJ
 Vert. Datum: NAVD 88 Station: ~ Drill Rig Equipment: Terrasonic 150CC Hammer Type: Automatic
 Horiz. Datum: ~ Offset: ~ Other Comments: ~



Log: KXM Rev: SAW Typ: LKN MASTER LOG E: 106384.GPJ SHAN WIL GDT 6/23/22

CONTINUED NEXT SHEET
LEGEND

- * Sample Not Recovered
- E Environmental Sample Obtained
- Soil Core (as in Sonic Core Borings)
- ┌ 2.0" O.D. Split Spoon Sample
- ▽ Ground Water Level ATD
- ◇ % Fines (<0.075mm)
- % Water Content

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.
4. The hole location was measured from existing site features and should be considered approximate.

Cascade Mill Parkway
Yakima, Washington



LOG OF BORING B-13-21

March 2023 106384-002

SHANNON & WILSON, INC. **FIG. A-6**
Geotechnical and Environmental Consultants Sheet 1 of 4

Total Depth: <u>65.3 ft.</u>	Northing: <u>~ 466,976 ft.</u>	Drilling Method: <u>Sonic Core</u>	Hole Diam.: <u>6 in.</u>
Top Elevation: <u>~ 1084 ft.</u>	Easting: <u>~ 1,642,570 ft.</u>	Drilling Company: <u>Holt Services</u>	Rod Diam.: <u>NWJ</u>
Vert. Datum: <u>NAVD 88</u>	Station: <u>~</u>	Drill Rig Equipment: <u>Terrasonic 150CC</u>	Hammer Type: <u>Automatic</u>
Horiz. Datum: <u>~</u>	Offset: <u>~</u>	Other Comments: <u>~</u>	

SOIL DESCRIPTION
Refer to the report text for a proper understanding of the subsurface materials and drilling methods. The stratification lines represent the approximate boundaries between material types, and the transition may be gradual.



25.5 Medium dense to dense, brown, *Poorly Graded Gravel with Silt and Sand and Cobbles (GP-GM)*; moist; subrounded cobbles; fine to coarse, subangular to subrounded gravel; fine to coarse sand; nonplastic.
Embankment Fill (Hf)

30.0 Medium dense to dense, gray-brown, *Silty Gravel with Sand and Cobbles (GM)*; moist; subrounded cobbles; fine to coarse, subrounded gravel; fine to coarse sand; low plasticity.
Embankment Fill (Hf)

35.0 Medium dense to dense, gray-brown, *Silty Gravel with Sand and Cobbles (GM) to Poorly Graded Gravel with Silt and Sand and Cobbles (GP-GM)*; moist, wet below about 50 feet; subrounded cobbles; fine to coarse, subangular to subrounded gravel; fine to coarse sand; nonplastic to low plasticity.
Embankment Fill (Hf)

CONTINUED NEXT SHEET
LEGEND

- * Sample Not Recovered
- E Environmental Sample Obtained
- Soil Core (as in Sonic Core Borings)
- 2.0" O.D. Split Spoon Sample
- Ground Water Level ATD

- ◇ % Fines (<0.075mm)
- % Water Content

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.
4. The hole location was measured from existing site features and should be considered approximate.

Cascade Mill Parkway
Yakima, Washington

LOG OF BORING B-13-21

March 2023

106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. A-6
Sheet 2 of 4

Log: KXM Rev: SAW Typ: LKN MASTER LOG E_106384.GPJ SHAN_WIL_GDT 6/23/22


Total Depth: <u>65.3 ft.</u>	Northing: <u>~ 466,976 ft.</u>	Drilling Method: <u>Sonic Core</u>	Hole Diam.: <u>6 in.</u>
Top Elevation: <u>~ 1084 ft.</u>	Easting: <u>~ 1,642,570 ft.</u>	Drilling Company: <u>Holt Services</u>	Rod Diam.: <u>NWJ</u>
Vert. Datum: <u>NAVD 88</u>	Station: <u>~</u>	Drill Rig Equipment: <u>Terrasonic 150CC</u>	Hammer Type: <u>Automatic</u>
Horiz. Datum: _____	Offset: <u>~</u>	Other Comments: _____	

SOIL DESCRIPTION
Refer to the report text for a proper understanding of the subsurface materials and drilling methods. The stratification lines represent the approximate boundaries between material types, and the transition may be gradual.


Depth, ft. Symbol PID, ppm Samples Ground Water Depth, ft. **PENETRATION RESISTANCE (blows/foot)**
▲ Hammer Wt. & Drop: 140 lbs / 30 inches

[Environmental sample B-13-21:39 collected at 39 feet.]


- Silty Sand with Gravel layer from about 40 to 42 feet.
- Slight organic odor at about 42 feet.



Medium dense to dense, gray-brown, Well-Graded Gravel with Silt and Sand and Cobbles (GW-GM) to Well-Graded Gravel with Sand and Cobbles (GW); moist, wet below about 50 feet; subrounded cobbles; fine to coarse, subangular to subrounded gravel; fine to coarse sand; nonplastic to low plasticity.
Alluvial Deposits (Qa)
[Environmental sample B-13-21:47 collected at 47 feet.]



- Orange-brown sandy gravel layer below about 59 feet.



CONTINUED NEXT SHEET

LEGEND

* Sample Not Recovered	▽ Ground Water Level ATD	◇ % Fines (<0.075mm)
E Environmental Sample Obtained		● % Water Content
□ Soil Core (as in Sonic Core Borings)		
┌ 2.0" O.D. Split Spoon Sample		

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.
4. The hole location was measured from existing site features and should be considered approximate.

Cascade Mill Parkway
Yakima, Washington


LOG OF BORING B-13-21

March 2023 106384-002

SHANNON & WILSON, INC. **FIG. A-6**
Geotechnical and Environmental Consultants Sheet 3 of 4

Log: KXM Rev: SAW Typ: LKN MASTER LOG E: 106384.GPJ SHAN WIL GDT 6/23/22

Total Depth: 65.3 ft. Northing: ~ 466,976 ft. Drilling Method: Sonic Core Hole Diam.: 6 in.
 Top Elevation: ~ 1084 ft. Easting: ~ 1,642,570 ft. Drilling Company: Holt Services Rod Diam.: NWJ
 Vert. Datum: NAVD 88 Station: ~ Drill Rig Equipment: Terrasonic 150CC Hammer Type: Automatic
 Horiz. Datum: ~ Offset: ~ Other Comments: ~



LEGEND

* Sample Not Recovered	∇ Ground Water Level ATD	◇ % Fines (<0.075mm)
E Environmental Sample Obtained		● % Water Content
▣ Soil Core (as in Sonic Core Borings)		
⊥ 2.0" O.D. Split Spoon Sample		

NOTES

- Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
- Groundwater level, if indicated above, is for the date specified and may vary.
- USCS designation is based on visual-manual classification and selected lab testing.
- The hole location was measured from existing site features and should be considered approximate.

Cascade Mill Parkway
Yakima, Washington


LOG OF BORING B-13-21

March 2023 106384-002

SHANNON & WILSON, INC. **FIG. A-6**
Geotechnical and Environmental Consultants Sheet 4 of 4

Log: KXM Rev: SAW Typ: LKN
 MASTER LOG E_106384.GPJ SHAN_WIL_GDT 6/23/22

Total Depth: 65.4 ft. Northing: ~ 466,692 ft. Drilling Method: Sonic Core Hole Diam.: 6 in.
 Top Elevation: ~ 1077 ft. Easting: ~ 1,642,660 ft. Drilling Company: Holt Services Rod Diam.: NWJ
 Vert. Datum: NAVD 88 Station: ~ Drill Rig Equipment: Terrasonic 150CC Hammer Type: Automatic
 Horiz. Datum: ~ Offset: ~ Other Comments: ~



CONTINUED NEXT SHEET
LEGEND

- * Sample Not Recovered
- E Environmental Sample Obtained
- Soil Core (as in Sonic Core Borings)
- 2.0" O.D. Split Spoon Sample
- Ground Water Level ATD
- ◇ % Fines (<0.075mm)
- % Water Content

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.
4. The hole location was measured from existing site features and should be considered approximate.

Cascade Mill Parkway
 Yakima, Washington


LOG OF BORING B-14-21

March 2023 106384-002

SHANNON & WILSON, INC. **FIG. A-7**
 Geotechnical and Environmental Consultants Sheet 1 of 4

Log: KXM Rev: SAW Typ: LKN MASTER LOG E_106384.GPJ SHAN_WIL_GDT 6/23/22

Total Depth: <u>65.4 ft.</u>	Northing: <u>~ 466,692 ft.</u>	Drilling Method: <u>Sonic Core</u>	Hole Diam.: <u>6 in.</u>
Top Elevation: <u>~ 1077 ft.</u>	Easting: <u>~ 1,642,660 ft.</u>	Drilling Company: <u>Holt Services</u>	Rod Diam.: <u>NWJ</u>
Vert. Datum: <u>NAVD 88</u>	Station: <u>~</u>	Drill Rig Equipment: <u>Terrasonic 150CC</u>	Hammer Type: <u>Automatic</u>
Horiz. Datum: <u>~</u>	Offset: <u>~</u>	Other Comments: <u>~</u>	



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- E Environmental Sample Obtained
- Soil Core (as in Sonic Core Borings)
- 2.0" O.D. Split Spoon Sample
- Ground Water Level ATD
- ◇ % Fines (<0.075mm)
- % Water Content

NOTES

- Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
- Groundwater level, if indicated above, is for the date specified and may vary.
- USCS designation is based on visual-manual classification and selected lab testing.
- The hole location was measured from existing site features and should be considered approximate.

Cascade Mill Parkway
Yakima, Washington

LOG OF BORING B-14-21

March 2023
106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants
FIG. A-7
Sheet 2 of 4

MASTER LOG E_106384.GPJ SHAN_WIL_GDT 6/23/22 Log: KXM Rev: SAW Typ: LKN

Total Depth: <u>65.4 ft.</u>	Northing: <u>~ 466,692 ft.</u>	Drilling Method: <u>Sonic Core</u>	Hole Diam.: <u>6 in.</u>
Top Elevation: <u>~ 1077 ft.</u>	Easting: <u>~ 1,642,660 ft.</u>	Drilling Company: <u>Holt Services</u>	Rod Diam.: <u>NWJ</u>
Vert. Datum: <u>NAVD 88</u>	Station: <u>~</u>	Drill Rig Equipment: <u>Terrasonic 150CC</u>	Hammer Type: <u>Automatic</u>
Horiz. Datum: <u>~</u>	Offset: <u>~</u>	Other Comments: <u>~</u>	

SOIL DESCRIPTION
Refer to the report text for a proper understanding of the subsurface materials and drilling methods. The stratification lines represent the approximate boundaries between material types, and the transition may be gradual.

Depth, ft.
Symbol
PID, ppm
Samples



Ground Water
Depth, ft.

PENETRATION RESISTANCE (blows/foot)
▲ Hammer Wt. & Drop: 140 lbs / 30 inches

and Sand and Cobbles (GW); moist; subrounded cobbles; fine to coarse, subangular to subrounded gravel; fine to coarse sand; nonplastic.
Alluvial Deposits (Qa)



Medium dense, gray-brown, Well-Graded Gravel with silt and Sand and Cobbles (GW-GM); moist; subrounded cobbles; fine to coarse, subangular to subrounded gravel; fine to coarse sand; low plasticity.
Alluvial Deposits (Qa)

Medium dense to dense, gray-brown to brown, Well-Graded Gravel with Sand and Cobbles (GW-GM); moist to wet; subrounded cobbles; fine to coarse, subangular to subrounded gravel; fine to coarse sand; nonplastic to low plasticity; few sandy zones.
Alluvial Deposits (Qa)
[Environmental sample B-14-21:48 collected at 48 feet.]



Medium dense to dense, brown to orange-brown, Clayey Gravel with Sand and Cobbles (GC); wet; subrounded cobbles; fine to coarse, subangular to subrounded gravel; fine to coarse sand; non plastic to low plasticity; few sandy zones; iron-oxide staining locally.
Alluvial Deposits (Qa)

- Orange-brown, ash or strong iron-oxide staining at about 59 feet.



CONTINUED NEXT SHEET
LEGEND

- * Sample Not Recovered
- E Environmental Sample Obtained
- Soil Core (as in Sonic Core Borings)
- 2.0" O.D. Split Spoon Sample
- Ground Water Level ATD

- ◇ % Fines (<0.075mm)
- % Water Content

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.
4. The hole location was measured from existing site features and should be considered approximate.

Cascade Mill Parkway
Yakima, Washington


LOG OF BORING B-14-21

March 2023 106384-002

SHANNON & WILSON, INC. **FIG. A-7**
Geotechnical and Environmental Consultants Sheet 3 of 4

Log: KXM Rev: SAW Typ: LKN MASTER LOG E_106384.GPJ SHAN_WIL_GDT 6/23/22

Total Depth: 65.4 ft. Northing: ~ 466,692 ft. Drilling Method: Sonic Core Hole Diam.: 6 in.
 Top Elevation: ~ 1077 ft. Easting: ~ 1,642,660 ft. Drilling Company: Holt Services Rod Diam.: NWJ
 Vert. Datum: NAVD 88 Station: ~ Drill Rig Equipment: Terrasonic 150CC Hammer Type: Automatic
 Horiz. Datum: ~ Offset: ~ Other Comments: ~



Log: KXM Rev: SAW Typ: LKN MASTER LOG E_106384.GPJ SHAN_WIL_GDT 6/23/22

LEGEND


- * Sample Not Recovered
- E Environmental Sample Obtained
- Soil Core (as in Sonic Core Borings)
- 2.0" O.D. Split Spoon Sample
- Ground Water Level ATD
- % Fines (<0.075mm)
- % Water Content

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.
4. The hole location was measured from existing site features and should be considered approximate.

Cascade Mill Parkway Yakima, Washington	
<h2 style="margin: 0;">LOG OF BORING B-14-21</h2>	
March 2023	106384-002
SHANNON & WILSON, INC. Geotechnical and Environmental Consultants	FIG. A-7 Sheet 4 of 4

Total Depth: 40.25 ft. Northing: ~ 467,307 ft. Drilling Method: Sonic Core Hole Diam.: 6 in.
 Top Elevation: ~ 1051 ft. Easting: ~ 1,643,984 ft. Drilling Company: Holt Services Rod Diam.: NWJ
 Vert. Datum: NAVD 88 Station: ~ Drill Rig Equipment: Terrasonic 150CC Hammer Type: Automatic
 Horiz. Datum: ~ Offset: ~ Other Comments: ~



Log: KXM Rev: SAW Typ: LKN MASTER LOG E_106384.GPJ SHAN_WIL_GDT_6/23/22

CONTINUED NEXT SHEET

LEGEND

* Sample Not Recovered	[Symbol]	Well Screen and Sand Filter
E Environmental Sample Obtained	[Symbol]	Bentonite-Cement Grout
[Symbol] Soil Core (as in Sonic Core Borings)	[Symbol]	Bentonite Chips/Pellets
[Symbol] 2.0" O.D. Split Spoon Sample	[Symbol]	Bentonite Grout
	▼	Ground Water Level in VWP

◇ % Fines (<0.075mm)
 ● % Water Content
 Plastic Limit —●— Liquid Limit
 Natural Water Content

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.
4. The hole location was measured from existing site features and should be considered approximate.

Cascade Mill Parkway
Yakima, Washington

LOG OF BORING B-15P-21

March 2023 106384-002

SHANNON & WILSON, INC. **FIG. A-8**
 Geotechnical and Environmental Consultants Sheet 1 of 3

Total Depth: 40.25 ft. Northing: ~ 467,307 ft. Drilling Method: Sonic Core Hole Diam.: 6 in.
 Top Elevation: ~ 1051 ft. Easting: ~ 1,643,984 ft. Drilling Company: Holt Services Rod Diam.: NWJ
 Vert. Datum: NAVD 88 Station: ~ Drill Rig Equipment: Terrasonic 150CC Hammer Type: Automatic
 Horiz. Datum: _____ Offset: ~ Other Comments: _____


SOIL DESCRIPTION
 Refer to the report text for a proper understanding of the subsurface materials and drilling methods. The stratification lines represent the approximate boundaries between material types, and the transition may be gradual.

Depth, ft. Symbol PID, ppm Samples Ground Water

PENETRATION RESISTANCE (blows/foot)
 ▲ Hammer Wt. & Drop: 140 lbs / 30 inches

20.0
 Medium dense to dense, brown, *Poorly Graded Gravel with Sand and Cobbles (GP)*; moist, wet; subrounded cobbles; fine to coarse, subangular to subrounded gravel; fine to coarse sand; nonplastic to low plasticity; zones of well-graded gravel and increased silt content; sand layer at 20 feet may be from drill action; trace organics below 20 feet.
 Alluvial Deposits (Qa)

Medium dense to dense, brown, *Well-Graded Gravel with Sand and Cobbles (GW-GM)*; wet; subrounded cobbles; fine to coarse, subrounded gravel; fine to coarse sand; low plasticity, zones of poorly graded gravel.
 Alluvial Deposits (Qa)
 [Environmental sample B-15P-21:21 collected at 21 feet.]



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- E Environmental Sample Obtained
- Soil Core (as in Sonic Core Borings)
- 2.0" O.D. Split Spoon Sample
- Well Screen and Sand Filter
- Bentonite-Cement Grout
- Bentonite Chips/Pellets
- Bentonite Grout
- Ground Water Level in VWP

- ◇ % Fines (<0.075mm)
- % Water Content
- Plastic Limit —●— Liquid Limit
- Natural Water Content

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.
4. The hole location was measured from existing site features and should be considered approximate.

Cascade Mill Parkway
 Yakima, Washington

LOG OF BORING B-15P-21

March 2023

106384-002

SHANNON & WILSON, INC.
 Geotechnical and Environmental Consultants

FIG. A-8
 Sheet 2 of 3

Log: KXM Rev: SAW Typ: LKN MASTER LOG E_106384.GPJ SHAN_WIL.GDT 6/23/22

Total Depth: 40.25 ft. Northing: ~ 467,307 ft. Drilling Method: Sonic Core Hole Diam.: 6 in.
 Top Elevation: ~ 1051 ft. Easting: ~ 1,643,984 ft. Drilling Company: Holt Services Rod Diam.: NWJ
 Vert. Datum: NAVD 88 Station: ~ Drill Rig Equipment: Terrasonic 150CC Hammer Type: Automatic
 Horiz. Datum: _____ Offset: ~ Other Comments: _____

SOIL DESCRIPTION <i>Refer to the report text for a proper understanding of the subsurface materials and drilling methods. The stratification lines represent the approximate boundaries between material types, and the transition may be gradual.</i>	Depth, ft.	Symbol	PID, ppm	Samples	Ground Water	Depth, ft.	PENETRATION RESISTANCE (blows/foot)			
							▲ Hammer Wt. & Drop: <u>140 lbs / 30 inches</u>			
BOTTOM OF BORING COMPLETED 3/22/2021 NOTE: Where gravels exceeding one-half the inside diameter of the split spoon sampler, cobbles, or boulders are present, the SPT blow counts are not reliable indicators of soil density or stiffness per ASTM D1586. The interpreted relative densities for layers that meet these criteria presented in this boring log are based on density of nearby soil zones encountered and interpretation of the geologic depositional environment, instead of the blow count versus relative density relationship presented in Figure A-1.	40.3			S8		0	20	40	60	
										50/37

Log: KXM Rev: SAW Typ: LKN MASTER LOG E: 106384.GPJ SHAN WIL GDT 6/23/22

LEGEND

* Sample Not Recovered		Well Screen and Sand Filter	◇ % Fines (<0.075mm)
E Environmental Sample Obtained		Bentonite-Cement Grout	● % Water Content
Soil Core (as in Sonic Core Borings)		Bentonite Chips/Pellets	Plastic Limit —●— Liquid Limit
2.0" O.D. Split Spoon Sample		Bentonite Grout	Natural Water Content

▼ Ground Water Level in VWP

- NOTES**
1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
 2. Groundwater level, if indicated above, is for the date specified and may vary.
 3. USCS designation is based on visual-manual classification and selected lab testing.
 4. The hole location was measured from existing site features and should be considered approximate.

Cascade Mill Parkway
Yakima, Washington

LOG OF BORING B-15P-21


March 2023 106384-002

SHANNON & WILSON, INC. **FIG. A-8**
 Geotechnical and Environmental Consultants Sheet 3 of 3

Cascade Mill Parkway
Yakima, Washington

TP-1-22

Date Completed: May 23, 2022 Northing: ~466,766 feet Maximum Depth: 12 feet Excavation Company: WSDOT
 Top Elevation: ~1080 feet Easting: ~1,642,557 feet TP Top Length: 3 feet Excavation Equipment: John Deere
 Vertical Datum: _____ Horizontal Datum: _____ TP Top Width: 13 feet



106304-002 (NEW) TEST PIT LOG - 106304 STAND UP TEST PIT.GPJ 2022 TEST PROJECT.GPJ 2022 NEW GINT LIBRARY.GLB 6/16/22

NOTES:

- Refer to KEY for explanation of symbols, codes, abbreviations, and definitions.
- Groundwater level, if indicated above, is for the date specified and may vary.
- **Excavation was performed adjacent to EB I-82 shoulder, in interstate embankment**
- Group symbol is based on visual-manual identification and selected lab testing.
- Report text contains limitations and information needed to contextually understand this log.

FINAL	
Logged by:	KXM
Review by:	OTH
Version:	1

Appendix B

Geotechnical Laboratory Test Procedures and Results

CONTENTS

B.1 INTRODUCTION B-1

B.2 VISUAL CLASSIFICATION B-1

B.3 WATER CONTENT DETERMINATION B-1

B.4 GRAIN-SIZE ANALYSES B-1

 B.4.1 Sieve Analysis B-2

 B.4.2 Combined Analysis B-2

B.5 ATTERBERG LIMITS B-2

B.6 CONSIDERATIONS B-2

Tables

- Table B-1: Summary of Laboratory Testing (5 pages)
- Laboratory Terms (2 pages)
- Sample Types

Tests

- Grain-Size Distribution Plot, Boring B-09-21
- Grain-Size Distribution Plot, Boring B-10-21
- Grain-Size Distribution Plot, Boring B-11P-21
- Grain-Size Distribution Plot, Boring B-12P-21
- Grain-Size Distribution Plot, Boring B-13-21
- Grain-Size Distribution Plot, Boring B-14-21
- Grain-Size Distribution Plot, Boring B-15P-21
- Plasticity Chart, Boring B-09-21
- Plasticity Chart, Boring B-11P-21
- Plasticity Chart, Boring B-12P-21
- Plasticity Chart, Boring B-15P-21

B.1 INTRODUCTION

We performed geotechnical laboratory testing on select soil samples retrieved from the borings completed for Cascade Mill Parkway. The laboratory testing program included tests to classify the soil and provide data for engineering studies. We performed visual classification on all retrieved samples. Our laboratory testing program included water content determinations, grain-size distribution analyses, and Atterberg limits tests.

The following sections describe the laboratory test procedures.

B.2 VISUAL CLASSIFICATION

We visually classified soil samples retrieved from the borings using a system based on ASTM D2487-11, Standard Test Method for Classification of Soil for Engineering Purposes, and ASTM D2488-09a, Standard Recommended Practice for Description of Soils (Visual-Manual Procedure). We summarize our classification system in Appendix A. We assigned a Unified Soil Classification System (USCS) group name and symbol, based on our visual classification of particles finer than 76.2 millimeters (3 inches). We revised visual classifications using results of the index tests discussed below.

B.3 WATER CONTENT DETERMINATION

We tested the water content of selected samples in accordance with ASTM D2216-10, Standard Method for Laboratory Determination of Water (Moisture) Content of Soil, Rock, and Soil-Aggregate Mixtures. Comparison of the water content of a soil with its index properties can be useful in characterizing soil unit weight, consistency, compressibility, and strength. We present water content test results in the Summary of Laboratory Testing table in this appendix and graphically on Appendix A exploration logs.

B.4 GRAIN-SIZE ANALYSES

Grain-size distribution analyses separate soil particles through mechanical or sedimentation processes. Grain-size distributions are used to classify the granular component of soils and can correlate with soil properties, including frost susceptibility, permeability, shear strength, liquefaction potential, capillary action, and sensitivity to moisture. We plot grain-size distribution analysis results in this appendix. Grain-size distribution plots provide tabular information about each specimen, including USCS group symbol and group name; water

content; constituent (i.e., cobble, gravel, sand, and fines) percentages; coefficients of uniformity and curvature, if applicable; personnel initials; ASTM standard designation; and testing remarks. Constituent percentages are presented in the Lab Summary Table in this appendix and fines contents are plotted as data points on Appendix A exploration logs.

B.4.1 Sieve Analysis

We performed mechanical sieve analyses on selected soil specimens to determine the grain-size distribution of coarse-grained soil particles, in accordance with ASTM C136/C136M 14, Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates.

B.4.2 Combined Analysis

We performed combined analyses (mechanical and sedimentation) on selected soil specimens to determine the grain-size distribution of coarse- and fine-grained soil particles, in accordance with ASTM D422-63 2007e2, Standard Test Method for Particle-Size Analysis of Soils. We assumed a specific gravity of 2.7 for hydrometer calculations, unless otherwise indicated on grain-size distribution plots.

B.5 ATTERBERG LIMITS

We performed Atterberg Limits tests on selected fine-grained samples in accordance with ASTM D4318, Standard Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils (www.astm.org). The Atterberg Limits include Liquid Limit (LL), Plastic Limit (PL), and Plasticity Index ($PI = LL - PL$). These limits can assist soil classification, indicate soil consistency (when compared to natural water content), provide correlation to soil properties, and estimate liquefaction potential. Plasticity charts provide the liquid limit, plastic limit, plasticity index, USCS group symbol, water content, and percent passing the No. 200 sieve (if a grain-size distribution analysis was performed). Soil plasticity test results are also shown graphically on the exploration logs presented in Appendix A.

B.6 CONSIDERATIONS

Drilling and sampling methodologies may affect the outcome of prescribed geotechnical laboratory tests. Refer to the field exploration discussion in this report for a discussion of these potential effects. Instances of limited recovery may have resulted in test samples not meeting specified minimum mass requirements, per ASTM standards. Test plots show which samples do not meet ASTM specified minimum mass requirements.

Table B-1: Summary of Laboratory Testing

Exploration Designation	Top Depth (feet)	Sample Number	Sample Type	SPT Blow Count (bpf)	USCS	Water Content (%)	Percent Cobbles Removed ¹ (%)	Gravel Percent (%)	Sand Percent (%)	Fines Percent (%)	Clay-size Percent (%)	Coefficient of Uniformity, C _u	Coefficient of Curvature, C _c	Liquid Limit, LL (%)	Plastic Limit, PL (%)	Soil Description
B-09-21	4	R-1	SCORE			31.3										
B-09-21	7.5	R-2	SCORE			19.9										
B-09-21	14	R-3	SCORE			2.9										
B-09-21	19	R-4	SCORE			4.5										
B-09-21	25	R-7	SCORE			0.8										
B-09-21	25	S-5	SPT	50/5"		0.8										
B-09-21	27	R-7	SCORE			3.9										
B-09-21	30	R-8	SCORE		GM	3.1	12*	44*	40*	16*						Silty Gravel with Sand and Cobbles
B-09-21	30	R-8	SPT	50/4"	GM	3.1										Silty Gravel with Sand and Cobbles
B-09-21	38	R-9	SCORE			2.7										
B-09-21	42	R-10	SCORE			12.1										
B-09-21	47	R-10	SCORE			5.1										
B-09-21	50	R-11	SCORE		GP-GM	6.1		72*	23*	5.5*		125.1	5.1			Poorly Graded Gravel with Silt and Sand
B-09-21	50	R-11	SPT	13	GP-GM	6.1										Poorly Graded Gravel with Silt and Sand
B-09-21	59	R-11	SCORE			7.2										
B-09-21	61.5	R-12	SCORE		CL	15.5								30	16	Sandy Lean Clay with Gravel
B-09-21	62.5	R-12	SCORE		GP-GM	10.3		52*	40*	7.7*		59.8	0.4			Poorly Graded Gravel with Silt and Sand
B-09-21	66	R-12	SCORE		SC	11.1								26	16	Clayey Sand with Gravel
B-09-21	74	R-13	SCORE			9.0										
B-09-21	83	R-14	SCORE			9.1										
B-09-21	92	R-15	SCORE		SC-SM	12.7								23	16	Silty, Clayey Sand with Gravel
B-09-21	92.5	R-15	SCORE		GM	7.9	15*	50*	31*	19*						Silty Gravel with Sand and Cobbles
B-10-21	3	R-1	SCORE			30.8										
B-10-21	7.5	R-2	SCORE			13.0										
B-10-21	13	R-3	SCORE			3.3										
B-10-21	17.5	R-4	SCORE		GW-GM	2.8		63*	29*	7.3*		97.1	1.7			Well-Graded Gravel with Silt and Sand
B-10-21	27	R-6	SCORE			5.1										
B-10-21	33	R-7	SCORE			5.4										
B-10-21	39	R-8	SCORE			4.1										

Exploration Designation	Top Depth (feet)	Sample Number	Sample Type	SPT Blow Count (bpf)	USCS	Water Content (%)	Percent Cobbles Removed ¹ (%)	Gravel Percent (%)	Sand Percent (%)	Fines Percent (%)	Clay-size Percent (%)	Coefficient of Uniformity, C _u	Coefficient of Curvature, C _c	Liquid Limit, LL (%)	Plastic Limit, PL (%)	Soil Description
B-10-21	45	R-9	SCORE		GW-GM	4.8	16*	59*	33*	8.4*		110.4	1.5			Well-Graded Gravel with Silt and Sand and Cobbles
B-10-21	57	R-10	SCORE			9.1										
B-10-21	62	R-11	SCORE			12.5										
B-10-21	67	R-11	SCORE			7.4										
B-10-21	72.5	R-12	SCORE		SP-SM	12.8		35*	57*	8*		8.7	0.9			Poorly Graded Sand with Silt and Gravel
B-10-21	78	R-12	SCORE			9.1										
B-10-21	80	R-13	SCORE		GM	8.6		43*	33*	24*						Silty Gravel with Sand
B-10-21	80	R-13	SPT	63/10"	GM	8.6										Silty Gravel with Sand
B-10-21	82.5	R-13	SCORE		GM	7.5		51	28	21	6					Silty Gravel with Sand
B-10-21	85	R-14	SCORE		GP-GM	8.2	6*	58*	30*	11*		709.2	7.1			Poorly Graded Gravel with Silt and Sand and Cobbles
B-10-21	92.5	R-15	SCORE		GM	10.4		57	27	16	5					Silty Gravel with Sand
B-10-21	99	R-15	SCORE			9.6										
B-11P-21	5	R-2	SCORE			2.0										
B-11P-21	5	S-1	SPT	50/4"		2.0										
B-11P-21	13	R-3	SCORE		GM	2.2	22*	43*	39*	18*						Silty Gravel with Sand and Cobbles
B-11P-21	15	R-4	SCORE			3.0										
B-11P-21	15	S-3	SPT	50/5"		3.0										
B-11P-21	20	R-5	SCORE			1.1										
B-11P-21	20	S-4	SPT	50/5"		1.1										
B-11P-21	26.5	R-6	SCORE			5.6										
B-11P-21	27.5	R-6	SCORE		GW-GM	3.8		62*	28*	9.5*		221.4	1.9			Well-Graded Gravel with Silt and Sand
B-11P-21	32	R-7	SCORE		SC-SM									21	16	Silty, Clayey Sand with Gravel
B-11P-21	36.5	R-8	SCORE		GW-GM	2.9		65*	30*	5.1*		53.9	1.4			Well-Graded Gravel with Silt and Sand
B-11P-21	40	R-9	SCORE			15.8										
B-11P-21	40	S-8	SPT	29		15.8										
B-11P-21	55	R-10	SCORE		GW-GM	6.9		60*	31*	9.3*		147.9	2.3			Well-Graded Gravel with Silt and Sand
B-11P-21	62	R-11	SCORE			12.5										
B-11P-21	71	R-12	SCORE			12.1										
B-11P-21	72.5	R-12	SCORE		GC	9.3		51*	29*	20*				27	18	Clayey Gravel with Sand
B-11P-21	80	R-13	SCORE			11.7										

Exploration Designation	Top Depth (feet)	Sample Number	Sample Type	SPT Blow Count (bpf)	USCS	Water Content (%)	Percent Cobbles Removed ¹ (%)	Gravel Percent (%)	Sand Percent (%)	Fines Percent (%)	Clay-size Percent (%)	Coefficient of Uniformity, C _u	Coefficient of Curvature, C _c	Liquid Limit, LL (%)	Plastic Limit, PL (%)	Soil Description
B-11P-21	80	S-12	SPT	50/5"		11.7										
B-11P-21	90	R-14	SCORE			12.0										
B-11P-21	90	S-13	SPT	50/5"		12.0										
B-12P-21	5	R-2	SCORE			4.7										
B-12P-21	5	S-1	SPT	50/5"		4.7										
B-12P-21	7	R-2	SCORE			3.0										
B-12P-21	10	R-4	SCORE		GP-GM	3.2		51*	39*	11*		129.6	4.3			Poorly Graded Gravel with Silt and Sand
B-12P-21	10	R-4	SPT	50/5.5"	GP-GM	3.2										Poorly Graded Gravel with Silt and Sand
B-12P-21	15	R-5	SCORE			2.5										
B-12P-21	15	S-3	SPT	50/6"		2.5										
B-12P-21	20	R-6	SCORE			4.1										
B-12P-21	20	S-4	SPT	68/11"		4.1										
B-12P-21	26	R-7	SCORE		GP-GM	2.1	8*	71*	22*	6.5*		84.4	4.3			Poorly Graded Gravel with Silt and Sand and Cobbles
B-12P-21	26	R-7	SPT	72	GP-GM	2.1										Poorly Graded Gravel with Silt and Sand and Cobbles
B-12P-21	34	R-8	SCORE			4.3										
B-12P-21	42	R-10	SCORE			7.2										
B-12P-21	50	R-11	SCORE		GP-GM	8.2	13*	55*	36*	9.3*		153.2	0.4			Poorly Graded Gravel with Silt and Sand and Cobbles
B-12P-21	50	R-11	SPT	50/6"	GP-GM	8.2										Poorly Graded Gravel with Silt and Sand and Cobbles
B-12P-21	62	R-12	SCORE		SC	9.4								24	16	Clayey Sand with Gravel
B-12P-21	67.5	R-12	SCORE		GM	7.0		55*	29*	16*						Silty Gravel with Sand
B-12P-21	77.5	R-13	SCORE			8.6										
B-12P-21	84	R-14	SCORE		CL	33.2								48	23	Lean Clay
B-12P-21	90	R-15	SCORE		GM	7.5	9*	57*	25*	18*						Silty Gravel with Sand and Cobbles
B-12P-21	90	R-15	SPT	50/5"	GM	7.5										Silty Gravel with Sand and Cobbles
B-12P-21	97	R-15	SCORE			8.6										
B-13-21	4	R-1	SCORE			5.4										
B-13-21	7	R-2	SCORE			4.5										
B-13-21	9	R-2	SCORE		GW-GM	3.4		51*	39*	9.7*		98.3	2.0			Well-Graded Gravel with Silt and Sand
B-13-21	14	R-3	SCORE			3.6										
B-13-21	20	R-5	SCORE			3.5										

Exploration Designation	Top Depth (feet)	Sample Number	Sample Type	SPT Blow Count (bpf)	USCS	Water Content (%)	Percent Cobbles Removed ¹ (%)	Gravel Percent (%)	Sand Percent (%)	Fines Percent (%)	Clay-size Percent (%)	Coefficient of Uniformity, C _u	Coefficient of Curvature, C _c	Liquid Limit, LL (%)	Plastic Limit, PL (%)	Soil Description
B-13-21	20	S-4	SPT	50/5"		3.5										
B-13-21	23	R-5	SCORE		GM	3.0		58*	30*	12*						Silty Gravel with Sand
B-13-21	28	R-6	SCORE			4.5										
B-13-21	33	R-7	SCORE			3.2										
B-13-21	39	R-8	SCORE			3.8										
B-13-21	40	R-9	SCORE		SM	5.1		22*	52*	26*						Silty Sand with Gravel
B-13-21	40	R-9	SPT	50/5"	SM	5.1										Silty Sand with Gravel
B-13-21	46	R-9	SCORE		GP-GM	3.7		75*	20*	5.1*		130.9	8.2			Poorly Graded Gravel with Silt and Sand
B-13-21	59	R-10	SCORE		GW	7.5		60*	36*	4.9*		33.3	2.4			Well-Graded Gravel with Sand
B-13-21	64	R-11	SCORE		GP-GM	9.9		62	29	9.1	3	172.8	0.8			Poorly Graded Gravel with Silt and Sand
B-14-21	5	R-2	SCORE			2.7										
B-14-21	5	S-1	SPT	65		2.7										
B-14-21	10	R-3	SCORE		GW-GM	3.0	9*	63*	29*	7.8*		96.8	2.4			Well-Graded Gravel with Silt and Sand and Cobbles
B-14-21	10	R-3	SPT	94	GW-GM	3.0										Well-Graded Gravel with Silt and Sand and Cobbles
B-14-21	15	R-4	SCORE			3.0										
B-14-21	15	S-3	SPT	50/5"		3.0										
B-14-21	20	R-5	SCORE			3.3										
B-14-21	20	S-4	SPT	77		3.3										
B-14-21	29.5	R-6	SCORE			3.8										
B-14-21	30	R-7	SCORE		GM	2.8	5*	49*	34*	18*						Silty Gravel with Sand and Cobbles
B-14-21	30	R-7	SPT	50/2"	GM	2.8										Silty Gravel with Sand and Cobbles
B-14-21	35	R-8	SCORE			4.8										
B-14-21	35	S-7	SPT	50/5"		4.8										
B-14-21	39	R-8	SCORE		GW	3.6		64*	32*	4.2*		41.9	1.7			Well-Graded Gravel with Sand
B-14-21	45	R-9	SCORE			5.6										
B-14-21	53	R-10	SCORE			11.6										
B-14-21	58	R-10	SCORE			10.5										
B-14-21	63	R-11	SCORE			10.7										
B-15P-21	0	R-1	SCORE		GP	1.9		78*	18*	4.7*		48.9	6.2			Poorly Graded Gravel with Sand
B-15P-21	5	R-2	SCORE			4.5										

Exploration Designation	Top Depth (feet)	Sample Number	Sample Type	SPT Blow Count (bpf)	USCS	Water Content (%)	Percent Cobbles Removed ¹ (%)	Gravel Percent (%)	Sand Percent (%)	Fines Percent (%)	Clay-size Percent (%)	Coefficient of Uniformity, C _u	Coefficient of Curvature, C _c	Liquid Limit, LL (%)	Plastic Limit, PL (%)	Soil Description
B-15P-21	5	S-1	SPT	26		4.5										
B-15P-21	8	R-2	SCORE		ML	14.5		0	47	53	10			26	22	Sandy Silt
B-15P-21	10	R-3	SCORE		GP-GM	3.3		53	37	10	3	211.0	0.2			Poorly Graded Gravel with Silt and Sand
B-15P-21	10	R-3	SPT	7	GP-GM	3.3										Poorly Graded Gravel with Silt and Sand
B-15P-21	15	R-4	SCORE		SM	4.2		20	56	24	7					Silty Sand with Gravel
B-15P-21	15	R-4	SPT	18	SM	4.2										Silty Sand with Gravel
B-15P-21	16	R-4	SCORE		GP-GM	4.2	15	74	20	5.4	1	97.8	5.6			Poorly Graded Gravel with Silt and Sand and Cobbles
B-15P-21	16	R-4	SPT	18	GP-GM	4.2										Poorly Graded Gravel with Silt and Sand and Cobbles
B-15P-21	17.5	R-4	SCORE		GW	5.8		71	26	3.0	1	68.1	2.6			Well-Graded Gravel with Sand
B-15P-21	21	R-5	SCORE		GW-GM	5.0		66	29	5.2	1	45.1	2.4			Well-Graded Gravel with Silt and Sand
B-15P-21	21	R-5	SPT	56	GW-GM	5.0										Well-Graded Gravel with Silt and Sand
B-15P-21	25	R-6	SCORE		GP-GM	8.8	19	47	41	12	3					Poorly Graded Gravel with Silt and Sand and Cobbles
B-15P-21	25	R-6	SPT	50/0.5"	GP-GM	8.8										Poorly Graded Gravel with Silt and Sand and Cobbles
B-15P-21	27.5	R-6	SCORE		GW-GM	8.0	7	55	34	10	3	196.4	1.7			Well-Graded Gravel with Silt and Sand and Cobbles
B-15P-21	31	R-7	SCORE			14.5										
B-15P-21	36	R-8	SCORE			13.1										

NOTES:
 * Sample specimen weight did not meet required minimum mass for the test; bpf = blows per foot; SCORE = Soil Core (as in Sonic Core Borings); SPT = 2-inch Outside Diameter Split-Spoon Sample

¹ Cobble percentages are calculated using the pre-removal, oven-dried mass of the total specimen. USCS Group Symbol, Soil Classification Group Name, Gravel Percent, Sand Percent, Fines Percent, C_u, and C_c values are calculated from particles smaller than 76.2mm (3 inches) only, per ASTM D2487.

Laboratory Terms

Abbreviations, Symbols, and Terms	Descriptions
%	percent
*	Sample specimen weight did not meet required minimum mass for the test method.
"	inch
#	Test not performed by Shannon & Wilson laboratory.
ASTM Std.	ASTM International Standard
C_c	coefficient of curvature
clay-size	Soil particles finer than 0.02 mm.
cm	centimeter
cm ²	square centimeter
coarse-grained	Soil particles coarser than 0.075 mm (cobble-, gravel-, and sand-sized particles).
cobbles	Soil particles finer than 305 mm and coarser than 76.2 mm.
C_u	coefficient of uniformity
CU	consolidated-undrained
ϵ	axial strain
fine-grained	Soil particles finer than 76.2 mm and coarser than 4.75 mm.
ft	feet
γ_m	wet unit weight
gravel	Soil particles finer than 76.2 mm and coarser than 4.75 mm.
G_s	specific gravity of soil solids
H_o	initial height
ΔH	change in height
ΔH_{load}	end of load increment deformation
in	inch
in ³	cubic inch
LL	liquid limit
min	minute
mm	millimeter
μ_m	micrometer
MC	moisture content
MPa	mega-pascal
NP	nonplastic
OC	organic content
p	total stress

Abbreviations, Symbols, and Terms	Descriptions
p'	effective stress
Pa	pascal
pcf	pounds per cubic foot
PI	Plasticity Index
PL	plastic limit
psf	pounds per square foot
psi	pounds per square inch
q	deviatoric stress
Sand	Soil particles finer than 4.75 mm and coarser than 0.075 mm.
sec	second
Silt	Soil particles finer than 0.075 mm and coarser than 0.002 mm.
t_n	time to n% primary consolidation
t_{load}	duration of load increment
tsf	short tons per square foot
USCS	Unified Soil Classification System
UU	unconsolidated-undrained
WC	water content


Sample Types

Abbreviations, Symbols, and Terms	Descriptions
2SS	2.5-inch-Outside-Diameter Split-Spoon Sample
2ST	2-inch-Outside-Diameter Thin-Walled Tube
3HSA	3-inch CME Hollow Stem Auger Sampler
3SS	3-inch-Outside-Diameter Split-Spoon Sample
4SS	4-inch-Inside-Diameter Split-Spoon Sample
6SS	6-inch-Inside-Diameter Split-Spoon Sample
CA_MC	Modified California Sampler
CA_SPT	Standard Penetration Test (SPT)
CORE	Rock Core
DM	+3.25-inch-Outside-Diameter Split-Spoon Sampler
DMR	3.25-inch Sampler with Internal Rings
GRAB	Grab Sample
GUS	3-inch-Outside-Diameter Gregory Undisturbed Sampler (GUS) Sample
OSTER	3-inch-Outside-Diameter Osterberg Sample
PITCHER	3-inch-Outside-Diameter Pitcher Sample
PMT	Pressuremeter Test (f=failed)
PO	Porter Penetration Test Sample
PT	2.5-inch-Outside-Diameter Thin-Walled Tube
ROCK	Rock Core Sample
SCORE	Soil Core (as in Sonic Core Borings)
SH1	1-inch Plastic Sheath
SH2	2-inch Plastic Sheath with Soil Recovery
SH3	2-inch Plastic Sheath with no Soil Recovery
SPT	2-inch-Outside-Diameter Split-Spoon Sample
SS	Split-Spoon
ST	3-inch-Outside-Diameter Thin-Walled Tube
STW	3-inch-Outside-Diameter Thin-Walled Tube
TEST	Sample Test Interval
TW	Thin Wall Sample
UNDIST	Undisturbed Sample
VANE	Vane Shear
WATER	Water Sample for Probe Logs
XCORE	Core Sample

Cascade Mill Parkway
Yakima, Washington

BORING B-09-21

Gravel		Sand			Fines	
Coarse	Fine	Coarse	Medium	Fine	Silt & Clay-Size	
Mesh Opening in Inches		Mesh Openings per Inch, U.S. Standard			Grain Size in Millimeters	



Sample Identification	Depth (ft)	USCS Group Symbol	USCS Group Name	Cobbles % ²	Gravel %	Sand %	Fines %	< 20µm %	< 2µm %	WC %	Tested By	Review By	ASTM Std.
● B-09-21, R-8'	30.0	GM	Silty Gravel with Sand and Cobbles	12	44	40	16			3.1	NJA	AKV	D6913
■ B-09-21, R-11'	50.0	GP-GM	Poorly Graded Gravel with Silt and Sand		72	23	5.5			6.1	NJA	AKV	D6913
▲ B-09-21, R-12'	62.5	GP-GM	Poorly Graded Gravel with Silt and Sand		52	40	7.7			10.3	NJA	AKV	D6913
◆ B-09-21, R-15'	92.5	GM	Silty Gravel with Sand and Cobbles	15	50	31	19			7.9	NJA	AKV	D6913


¹ Test specimen did not meet minimum mass recommendations.

² Cobble percentages are calculated using the pre-removal, oven-dried mass of the total specimen. USCS Group Symbol, Soil Classification Group Name, Gravel %, Sand %, Fines %, <0.02mm %, and <2µm% values are calculated from particles smaller than 76.2mm (3 inches) only, per ASTM D2487.

Cascade Mill Parkway
Yakima, Washington

BORING B-10-21

Gravel		Sand			Fines	
Coarse	Fine	Coarse	Medium	Fine	Silt	Clay-Size
Mesh Opening in Inches		Mesh Openings per Inch, U.S. Standard			Grain Size in Millimeters	



Sample Identification	Depth (ft)	USCS Group Symbol	USCS Group Name	Cobbles % ²	Gravel %	Sand %	Fines %	< 20µm %	< 2µm %	WC %	Tested By	Review By	ASTM Std.
● B-10-21, R-4 [*]	17.5	GW-GM	Well-Graded Gravel with Silt and Sand		63	29	7.3			2.8	SJD	AKV	D6913
■ B-10-21, R-9 [*]	45.0	GW-GM	Well-Graded Gravel with Silt and Sand and Cobbles	16	59	33	8.4			4.8	SJD	AKV	D6913
▲ B-10-21, R-12 [*]	72.5	SP-SM	Poorly Graded Sand with Silt and Gravel		35	57	8.0			12.8	SJD	AKV	D6913
◆ B-10-21, R-13 [*]	80.0	GM	Silty Gravel with Sand		43	33	24			8.6	SJD	AKV	D6913
○ B-10-21, R-13	82.5	GM	Silty Gravel with Sand		51	28	21	16	6	7.5	SJD	AKV	D422
□ B-10-21, R-14 [*]	85.0	GP-GM	Poorly Graded Gravel with Silt and Sand and Cobbles	6	58	30	11			8.2	SJD	AKV	D6913
△ B-10-21, R-15	92.5	GM	Silty Gravel with Sand		57	27	16	12	5	10.4	SJD	AKV	D422


^{*} Test specimen did not meet minimum mass recommendations.

² Cobble percentages are calculated using the pre-removal, oven-dried mass of the total specimen. USCS Group Symbol, Soil Classification Group Name, Gravel %, Sand %, Fines %, <0.02mm %, and <2µm% values are calculated from particles smaller than 76.2mm (3 inches) only, per ASTM D2487.

Cascade Mill Parkway
Yakima, Washington

BORING B-11P-21

Gravel		Sand			Fines	
Coarse	Fine	Coarse	Medium	Fine	Silt & Clay-Size	
Mesh Opening in Inches		Mesh Openings per Inch, U.S. Standard			Grain Size in Millimeters	




Sample Identification	Depth (ft)	USCS Group Symbol	USCS Group Name	Cobbles % ²	Gravel %	Sand %	Fines %	< 20µm %	< 2µm %	WC %	Tested By	Review By	ASTM Std.
● B-11P-21, R-3'	13.0	GM	Silty Gravel with Sand and Cobbles	22	43	39	18			2.2	NLP	AKV	D6913
■ B-11P-21, R-6'	27.5	GW-GM	Well-Graded Gravel with Silt and Sand		62	28	9.5			3.8	NLP	AKV	D6913
▲ B-11P-21, R-8'	36.5	GW-GM	Well-Graded Gravel with Silt and Sand		65	30	5.1			2.9	NLP	AKV	D6913
◆ B-11P-21, R-10'	55.0	GW-GM	Well-Graded Gravel with Silt and Sand		60	31	9.3			6.9	NLP	AKV	D6913
○ B-11P-21, R-12'	72.5	GC	Clayey Gravel with Sand		51	29	20			9.3	NLP	AKV	D6913

¹ Test specimen did not meet minimum mass recommendations.

² Cobble percentages are calculated using the pre-removal, oven-dried mass of the total specimen. USCS Group Symbol, Soil Classification Group Name, Gravel %, Sand %, Fines %, <0.02mm %, and <2µm% values are calculated from particles smaller than 76.2mm (3 inches) only, per ASTM D2487.

Cascade Mill Parkway
Yakima, Washington

BORING B-12P-21




¹ Test specimen did not meet minimum mass recommendations.

² Cobble percentages are calculated using the pre-removal, oven-dried mass of the total specimen. USCS Group Symbol, Soil Classification Group Name, Gravel %, Sand %, Fines %, <0.02mm %, and <2µm% values are calculated from particles smaller than 76.2mm (3 inches) only, per ASTM D2487.

Cascade Mill Parkway
Yakima, Washington

BORING B-13-21

Gravel		Sand			Fines	
Coarse	Fine	Coarse	Medium	Fine	Silt	Clay-Size
Mesh Opening in Inches		Mesh Openings per Inch, U.S. Standard			Grain Size in Millimeters	



Sample Identification	Depth (ft)	USCS Group Symbol	USCS Group Name	Gravel %	Sand %	Fines %	< 20µm %	< 2µm %	WC %	Tested By	Review By	ASTM Std.
● B-13-21, R-2 ¹	9.0	GW-GM	Well-Graded Gravel with Silt and Sand	51	39	9.7			3.4	SJD	AKV	D6913
■ B-13-21, R-5 ²	23.0	GM	Silty Gravel with Sand	58	30	12			3.0	SJD	AKV	D6913
▲ B-13-21, R-9 ²	40.0	SM	Silty Sand with Gravel	22	52	26			5.1	SJD	AKV	D6913
◆ B-13-21, R-9 ²	46.0	GP-GM	Poorly Graded Gravel with Silt and Sand	75	20	5.1			3.7	SJD	AKV	D6913
○ B-13-21, R-10 ²	59.0	GW	Well-Graded Gravel with Sand	60	36	4.9			7.5	SJD	AKV	D6913
□ B-13-21, R-11	64.0	GP-GM	Poorly Graded Gravel with Silt and Sand	62	29	9.1	7	3	9.9	SJD	AKV	D422


¹ Test specimen did not meet minimum mass recommendations.

² Cobble percentages are calculated using the pre-removal, oven-dried mass of the total specimen. USCS Group Symbol, Soil Classification Group Name, Gravel %, Sand %, Fines %, <0.02mm %, and <2µm% values are calculated from particles smaller than 76.2mm (3 inches) only, per ASTM D2487.

Cascade Mill Parkway
Yakima, Washington

BORING B-14-21

Gravel		Sand			Fines	
Coarse	Fine	Coarse	Medium	Fine	Silt	
Mesh Opening in Inches		Mesh Openings per Inch, U.S. Standard			Grain Size in Millimeters	
					Clay-Size	




Sample Identification	Depth (ft)	USCS Group Symbol	USCS Group Name	Cobbles % ²	Gravel %	Sand %	Fines %	< 20µm %	< 2µm %	WC %	Tested By	Review By	ASTM Std.
● B-14-21, R-3 ¹	10.0	GW-GM	Well-Graded Gravel with Silt and Sand and Cobbles	9	63	29	7.8			3.0	BXK	AKV	D6913
■ B-14-21, R-7 ¹	30.0	GM	Silty Gravel with Sand and Cobbles	5	49	34	18			2.8	BXK	AKV	D6913
▲ B-14-21, R-8 ¹	39.0	GW	Well-Graded Gravel with Sand		64	32	4.2			3.6	BXK	AKV	D6913

¹ Test specimen did not meet minimum mass recommendations.

² Cobble percentages are calculated using the pre-removal, oven-dried mass of the total specimen. USCS Group Symbol, Soil Classification Group Name, Gravel %, Sand %, Fines %, <0.02mm %, and <2µm% values are calculated from particles smaller than 76.2mm (3 inches) only, per ASTM D2487.

Cascade Mill Parkway
Yakima, Washington

BORING B-15P-21




Sample Identification	Depth (ft)	USCS Group Symbol	USCS Group Name	Cobbles % ²	Gravel %	Sand %	Fines %	< 20µm %	< 2µm %	WC %	Tested By	Review By	ASTM Std.
● B-15P-21, R-1	0.0	GP	Poorly Graded Gravel with Sand		78	18	4.7			1.9	BXK	AKV	D6913
■ B-15P-21, R-2	8.0	ML	Sandy Silt		0	47	53	24	10	14.5	SJD	AKV	D422
▲ B-15P-21, R-3	10.0	GP-GM	Poorly Graded Gravel with Silt and Sand		53	37	10	7	3	3.3	SJD	AKV	D422
◆ B-15P-21, R-4	15.0	SM	Silty Sand with Gravel		20	56	24	16	7	4.2	SJD	AKV	D422
○ B-15P-21, R-4	16.0	GP-GM	Poorly Graded Gravel with Silt and Sand and Cobbles	15	74	20	5.4	4	2	4.2	SJD	AKV	D422
□ B-15P-21, R-4	17.5	GW	Well-Graded Gravel with Sand		71	26	3.0	2	1	5.8	SJD	AKV	D422
△ B-15P-21, R-5	21.0	GW-GM	Well-Graded Gravel with Silt and Sand		66	29	5.2	4	1	5.0	SJD	AKV	D422
◇ B-15P-21, R-6	25.0	GP-GM	Poorly Graded Gravel with Silt and Sand and Cobbles	19	47	41	12	8	3	8.8	SJD	AKV	D422
▲ B-15P-21, R-6	27.5	GW-GM	Well-Graded Gravel with Silt and Sand and Cobbles	7	55	34	10	8	3	8.0	SJD	AKV	D422

¹ Test specimen did not meet minimum mass recommendations.

² Cobble percentages are calculated using the pre-removal, oven-dried mass of the total specimen. USCS Group Symbol, Soil Classification Group Name, Gravel %, Sand %, Fines %, <0.02mm %, and <2µm% values are calculated from particles smaller than 76.2mm (3 inches) only, per ASTM D2487.

Cascade Mill Parkway
Yakima, Washington


BORING B-09-21



Sample Identification	Depth (ft)	USCS Group Symbol	USCS Group Name	LL	PL	PI	WC %	Gravel %	Sand %	Fines %	< 2µm %	Tested By	Review By	ASTM Std.
● B-09-21, R-12	61.5	CL	Sandy Lean Clay with Gravel	30	16	14	15.5					DES	AKV	D4318
■ B-09-21, R-12	66.0	SC	Clayey Sand with Gravel	26	16	10	11.1					BXK	AKV	D4318
▲ B-09-21, R-15	92.0	SC-SM	Silty, Clayey Sand with Gravel	23	16	7	12.7					MXC	AKV	D4318

Cascade Mill Parkway
Yakima, Washington


BORING B-11P-21



Sample Identification	Depth (ft)	USCS Group Symbol	USCS Group Name	LL	PL	PI	WC %	Gravel %	Sand %	Fines %	< 2µm %	Tested By	Review By	ASTM Std.
● B-11P-21, R-7	32.0	SC-SM	Silty, Clayey Sand with Gravel	21	16	5						BXK	AKV	D4318
■ B-11P-21, R-12	72.5	GC	Clayey Gravel with Sand	27	18	9	9.3	51	29	20		BXK	AKV	D4318

Cascade Mill Parkway
Yakima, Washington


BORING B-12P-21



Sample Identification	Depth (ft)	USCS Group Symbol	USCS Group Name	LL	PL	PI	WC %	Gravel %	Sand %	Fines %	< 2µm %	Tested By	Review By	ASTM Std.
● B-12P-21, R-12	62.0	SC	Clayey Sand with Gravel	24	16	8	9.4					BXK	AKV	D4318
■ B-12P-21, R-14	84.0	CL	Lean Clay	48	23	25	33.2					MXC	AKV	D4318

Cascade Mill Parkway
Yakima, Washington

BORING B-15P-21



Sample Identification	Depth (ft)	USCS Group Symbol	USCS Group Name	LL	PL	PI	WC %	Gravel %	Sand %	Fines %	< 2µm %	Tested By	Review By	ASTM Std.
● B-15P-21, R-2	8.0	ML	Sandy Silt	26	22	4	14.5	0	47	53	10	BXK	AKV	D4318

Appendix C

2014 and 2017 Subsurface Data

CONTENTS

- C.1 SUBSURFACE EXPLORATIONSC-1
 - C.1.1 IntroductionC-1
 - C.1.2 Soil ClassificationC-1
 - C.1.3 Soil BoringsC-2
 - C.1.3.1 Sonic Core Drilling Procedures.....C-2
 - C.1.3.2 Split-Spoon Soil SamplesC-2
 - C.1.3.3 Sonic Core Soil ReviewC-3
 - C.1.4 Test Pit Excavation.....C-3
 - C.1.4.1 Test Pit Excavation Procedures.....C-3
 - C.1.4.2 Soil Sampling.....C-3
- C.2 GEOTECHNICAL LABORATORY TEST PROCEDURES AND RESULTSC-3
 - C.2.1 IntroductionC-3
 - C.2.2 Visual Classification.....C-4
 - C.2.3 Water Content Determination.....C-4
 - C.2.4 Grain-Size Analyses.....C-4
 - C.2.4.1 Sieve Analysis.....C-4
 - C.2.4.2 Combined AnalysisC-5
 - C.2.5 Considerations.....C-5
- C.3 PILOT INFILTRATION TEST AND PROCEDURES.....C-5
 - C.3.1 IntroductionC-5
 - C.3.2 Infiltration EvaluationC-5
 - C.3.3 Pilot Infiltration Test ProceduresC-6
 - C.3.4 Short-Term Pilot Infiltration Test Results.....C-7
 - C.3.5 Grain-Size Data Evaluation ProcedureC-7
 - C.3.6 Long-Term Design Infiltration Rate Correction Factors.....C-7
- C.4 REFERENCES.....C-8

APPENDIX C: 2014 AND 2017 SUBSURFACE DATA

Figures

Figure C-1: Soil Description and Log Key (3 sheets)

Figure C-2: Log of Boring B-1-17 (8 sheets)

Figure C-3: Log of Boring B-2-17 (3 sheets)

Figure C-4: Log of Boring B-3-18 (7 sheets)

Figure C-5: Log of Boring EWC-B-01-14 (6 sheets)

Figure C-6: Log of Boring EWC-B-02-14 (6 sheets)

Figure C-7: Log of Boring EWC-B-03-14 (6 sheets)

Figure C-8: Log of Boring EWC-B-04-14 (6 sheets)

Figure C-9: Log of Test Pit TP-P1-17

Tables

Table C-1: Summary of Pilot Infiltration Test Results

Table C-2: Summary of Grain-Size Analysis Infiltration Correlations

Tests

Grain-Size Distribution Plot, Boring B-1-17

Grain-Size Distribution Plot, Boring B-2-17

Grain-Size Distribution Plot, Boring B-3-18

Grain-Size Distribution Plot, Test Pit TP-P1-17

Grain-Size Distribution Plot, Boring EWC-B-01-14

Grain-Size Distribution Plot, Boring EWC-B-02-14

Grain-Size Distribution Plot, Boring EWC-B-03-14

Grain-Size Distribution Plot, Boring EWC-B-04-14

C.1 SUBSURFACE EXPLORATIONS

C.1.1 Introduction

The subsurface exploration program for the Stage 3 portion of the East-West Corridor (EWC) alignment consisted of drilling and sampling seven borings and excavating and collecting samples in one test pit. Four borings, designated EWC-B-01-14 through EWC-B-04-14 were completed in 2014 during the 30% design phase and the remaining explorations were completed between July and September 2017 and September 2018 (boring B-3-18).

We advanced the seven borings, designated B-1-17, B-2-17, B-3-18, and EWC-B-01-14 through EWC-B-04-14, to depths ranging between 40 to 140 feet. We installed observation wells in B-2-17 and in EWC-B-01-14 through EWC-B-04-14.

We excavated the test pit TP-P1-17 to design drainage facilities to approximately to 8.5 feet below ground surface (bgs). After completion, the test pit was backfilled with the excavation spoils and tamped with the excavator bucket at the ground surface.

Approximate locations of the borings and tests pits were recorded in the field using a hand-held Trimble global positioning system device. The locations of the explorations are shown in Figure 2, after the main text. The exploration locations and elevations should be considered accurate to the degree implied by the method used.

C.1.2 Soil Classification

A representative from Shannon & Wilson was present throughout the field explorations to observe the drilling, test pit, and sampling operations; retrieve representative soil samples for subsequent laboratory testing; and to prepare descriptive field logs of the explorations. Soil sample classifications were based on ASTM Designation D2487, Standard Practice for Classification of Soils for Engineering Purposes, and ASTM Designation D2488, Standard Practice for Description and Identification of Soils (Visual-Manual Procedure). The Unified Soil Classification System, as described in Figure A-1 of this appendix, was used to classify the soil. The exploration logs in the report represent our interpretation of the contents of the recent field logs.

C.1.3 Soil Borings

C.1.3.1 Sonic Core Drilling Procedures

Holt Services Inc. of Edgewood, Washington, drilled the soil borings under subcontract to Shannon & Wilson using a Terra Sonic track-mounted drill rig, outfitted with an automatic hammer. The sonic core drilling method uses high-frequency vibratory motion applied to the top of the drill column, along with down-pressure and rotation, to obtain nearly continuous core samples in soil and rock.

Soil samples were obtained using a 4-inch-outside-diameter (OD) core barrel. As the drill column was advanced into the ground, soil entered the core barrel. After advancing the core barrel a distance of 5 feet (termed a core “run”), a 6-inch OD temporary casing was vibrated to the bottom of the sample interval. The drill column and core barrel were then removed from the borehole and the soil core was extracted from the core barrel into plastic bags. Soil recovered from each run was described in the field and logged by our geologist. The soil sample bags were then sealed to retain moisture and stored in core boxes for transport. After retrieval of the soil core for a specific interval, the casing was cleared of slough and the drill column and core barrel were advanced, starting at the bottom of the temporary casing.

C.1.3.2 Split-Spoon Soil Samples

Disturbed soil samples were obtained from the borings by a split-spoon sampler used in conjunction with a Standard Penetration Test (SPT) and the sonic core barrel. To obtain disturbed soil samples from the borings, SPTs were performed in general accordance with the ASTM Designation D1586, Standard Test Method for Standard Penetration Test and Split-Barrel Sampling of Soils. The SPTs were generally performed at 5-foot intervals in between sonic core runs. The SPT consists of a 2-inch OD, 1.375-inch-inside-diameter, split-spoon sampler driven 18 inches into the bottom of the borehole with a 140-pound hammer free falling 30 inches. The number of blows required to advance the split-spoon sampler the last 12 inches of penetration is termed the Standard Penetration Resistance (N-value). This value is an empirical parameter that provides a means of evaluating the relative density or compactness of cohesionless (granular) soils and the relative consistency (stiffness) of cohesive soils. This value is commonly used in engineering analyses to estimate soil strength and other characteristics. The terminology used to describe the relative density or consistency of the soils is presented in Figure A-1. Generally, when penetration resistances exceed 50 or more blows for 6 inches or less of penetration, the test is terminated, and the number of blows and corresponding penetration recorded. The N-values were recorded by our field representative and are plotted in the boring logs presented as Figures C-2 through C-8.

The split-spoon sampler used during the penetration test recovers a disturbed sample of the soil, which is useful for identification and classification purposes. The samples were classified and recorded in the field by our geologist. The samples were then sealed in jars to retain moisture and returned to our laboratory for testing.

C.1.3.3 Sonic Core Soil Review

Soil recovered from sonic core drilling was reviewed for identification and classification purposes and photographed in our warehouse. Grab samples were collected during our review and placed in labeled plastic jars and 5-gallon plastic bags, sealed, and transported to our laboratory for further analysis and testing.

C.1.4 Test Pit Excavation

C.1.4.1 Test Pit Excavation Procedures

Test pit TP-P1-17 was excavated on September 27, 2017, by Yakima County Maintenance staff using a John Deere 410L rubber-tired backhoe. Test pit depth was approximately 8.5 feet bgs. Yakima County Maintenance staff backfilled the test pits with the excavation spoils in approximately the same order as it was removed from the hole. The surface of the test pit backfill was tamped with the back of the backhoe bucket for compaction.

C.1.4.2 Soil Sampling

Representative disturbed soil samples from the soil layers encountered in the test pits were collected from the backhoe bucket or spoil pile. A Shannon & Wilson representative was present throughout the test pit excavation to collect the grab samples, visually classify the soil, and prepare an exploration log for each test pit. After soil classification, the samples were sealed in jars or 5-gallon bags to retain moisture and returned to our laboratory for analyses.

The intervals where these samples were collected are shown on the test pit log presented in Figure C-9. Figure C-1 presents a soil description and symbology key for the logs.

C.2 GEOTECHNICAL LABORATORY TEST PROCEDURES AND RESULTS

C.2.1 Introduction

We performed geotechnical laboratory testing on select soil samples retrieved from the borings and test pits completed for the final design phase of this project. The laboratory testing program included tests to classify the soil and provide data for engineering studies.

We performed visual classification on all retrieved samples. Our laboratory testing program included water content determinations and grain-size distribution analyses.

The following sections describe the laboratory test procedures.

C.2.2 Visual Classification

We visually classified soil samples retrieved from the borings using a system based on ASTM D2487-11, Standard Test Method for Classification of Soil for Engineering Purposes, and ASTM D2488-09a, Standard Recommended Practice for Description of Soils (Visual-Manual Procedure). We summarize our classification system in Appendix A. We assigned a Unified Soil Classification System (USCS) group name and symbol, based on our visual classification of particles finer than 76.2 millimeters (3 inches). We revised visual classifications using results of the index tests discussed below.

C.2.3 Water Content Determination

We tested the water content of selected samples in accordance with ASTM D2216-10, Standard Method for Laboratory Determination of Water (Moisture) Content of Soil, Rock, and Soil-Aggregate Mixtures. Comparison of the water content of a soil with its index properties can be useful in characterizing soil unit weight, consistency, compressibility, and strength. We present water content test results in the Laboratory Test Summary table in this appendix, and graphically on Appendix A exploration logs.

C.2.4 Grain-Size Analyses

Grain-size distribution analyses separate soil particles through mechanical or sedimentation processes. Grain-size distributions are used to classify the granular component of soils and can correlate with soil properties, including frost susceptibility, permeability, shear strength, liquefaction potential, capillary action, and sensitivity to moisture. We plot grain-size distribution analysis results in this appendix. Grain-size distribution plots provide tabular information about each specimen, including USCS group symbol and group name; water content; constituent (i.e., cobble, gravel, sand, and fines) percentages; coefficients of uniformity and curvature, if applicable; personnel initials; ASTM standard designation; and testing remarks. Constituent percentages are presented in the Lab Summary Table in this appendix and fines contents are plotted as data points on Appendix A exploration logs.

C.2.4.1 Sieve Analysis

We performed mechanical sieve analyses on selected soil specimens to determine the grain-size distribution of coarse-grained soil particles, in accordance with ASTM C136/C136M-14, Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates.

C.2.4.2 Combined Analysis

We performed combined analyses (mechanical and sedimentation) on selected soil specimens to determine the grain-size distribution of coarse- and fine-grained soil particles, in accordance with ASTM D422-63 2007e2, Standard Test Method for Particle-Size Analysis of Soils. We assumed a specific gravity of 2.7 for hydrometer calculations, unless otherwise indicated on grain-size distribution plots.

C.2.5 Considerations

Drilling and sampling methodologies may affect the outcome of prescribed geotechnical laboratory tests. Refer to the field exploration discussion in this report for a discussion of these potential effects. Instances of limited recovery may have resulted in test samples not meeting specified minimum mass requirements, per ASTM standards. Test plots show which samples do not meet ASTM specified minimum mass requirements.

C.3 PILOT INFILTRATION TEST AND PROCEDURES

C.3.1 Introduction

Shannon & Wilson performed one Pilot Infiltration Test (PIT) within Stage 3 of the East-West Corridor Project on September 27, 2017. The approximate locations of this PIT test pit, designated TP-P1-17, is shown in Figure 2 in the main report.

C.3.2 Infiltration Evaluation

We estimated the long-term design infiltration rates for the proposed infiltration systems along the EWC alignment. The infiltration evaluation was completed according to the 2004 Washington State Department of Ecology (Ecology) Stormwater Management Manual for Eastern Washington (SMMEW) (Ecology, 2004) and the Yakima County Regional Stormwater Manual (Yakima County, 2010). The Ecology 2012 Stormwater Management Manual for Western Washington (Ecology, 2012) was used as a supplement to the SMMEW when limited information was available.

We estimated long-term design infiltration rates for Stage 3 of the EWC using the results of the PIT conducted in test pit TP-P1-17. We also used empirical correlations to grain-size analysis data for comparison purposes. Both PIT and grain-size analysis-based infiltration rate estimation methods result in short-term rates. We estimated the long-term design infiltration rates by applying correction factors to the short-term infiltration rates.

Section C.3.3 describes the PIT procedure and methods for estimating the long-term design infiltration rates using the results of the PIT and grain-size distributions. The grain-size distribution curves are shown at the end of this Appendix.

Tables C-1 and C-2 provide estimated short-term and long-term design infiltration rates. As indicated in these tables, the PIT infiltration rate results were higher compared to the empirical correlations. Based on the range of infiltration rates we obtained, we recommend using a design infiltration rate of 10 inches per hour for the Stage 3 infiltration facility near test pit TP-P1-17. Although lower values were obtained based on several of the empirical grain-size distribution-based infiltration rate estimates (Table 2), we consider the PIT to be more representative of the likely infiltration rate behavior at TP-P1-17. Therefore, our design infiltration rate recommendation is weighted toward the PIT-based results.

The long-term design infiltration rates presented in this report meet the requirements for flow control for the Ecology SMMEW and the Yakima County Regional Stormwater Manual. The design infiltration rates are for flow control only and assume a pretreatment system will be used to meet water quality requirements. Both the SMMEW and the Yakima County Regional Stormwater Manual require a maximum infiltration rate of 2.4 inches per hour for infiltration systems designed to meet treatment standards. The base of the proposed infiltration systems should be a minimum of 5 feet above the seasonally high groundwater level.

C.3.3 Pilot Infiltration Test Procedures

The PIT was performed in accordance with the Ecology 2004 SMMEW (Ecology, 2004). The procedure consisted of excavating a test pit to the proposed depth of the infiltration facility, adding water to the test pit, and measuring the drainage time of the water.

We determined the depth of the infiltration structures at each location using a grading plan provided by H.W. Lochner that described the final grade of the locations where water will be infiltrated. Based on correspondence with Lochner, we assume the maximum depth of the infiltration facility will be about 6 feet bgs. Therefore, the depth for the PIT was targeted at 8.5 feet bgs.

The Yakima County Maintenance staff used a John Deere 410L rubber-tired backhoe to excavate the test pits to the dimensions shown in Table 1 in the main report. Water was conveyed to the test pits from a 3,000-gallon water truck with a 2-inch fire hose and plastic pipe. The flow rate was regulated using a gate valve and measured using a flow meter. A measuring rod was placed in the test pit to measure the depth of the water.

The PIT included a constant rate test and a falling head test. The constant rate test was performed by filling the test pit to a constant level and taking flow rate and water level readings every 15 minutes until the flow rate and water level remained constant, or a minimum of 2 hours had passed. After the constant rate test was complete, a falling head test was performed by turning off the water and recording the rate that water in the test pit drained. Water level measurements were recorded approximately every 15 minutes during the falling head tests.

C.3.4 Short-Term Pilot Infiltration Test Results

The water level was brought up to and maintained at approximately 1 to 2 feet above the bottom of the test pit over the course of 2 hours. As shown in Table 1, the short-term falling head infiltration rate was evaluated to be about 50 inches per hour.

C.3.5 Grain-Size Data Evaluation Procedure

The SMMEW recommends using grain-size data to estimate the infiltration rate of soil; however, it provides limited information on how to estimate the infiltration rate from grain-size data. We used an analytical solution from the Ecology Stormwater Management Manual for Western Washington (SMMWW) (Ecology, 2012) to estimate the infiltration rate of soil using the grain-size data. The analytical solution used to calculate the saturated hydraulic conductivity from the grain-size data is:

$$\log_{10}(K_{\text{sat}}) = -1.57 + 1.90D_{10} + 0.015D_{60} - 0.013D_{90} - 2.08f_{\text{fines}}$$

K_{sat} = saturated hydraulic conductivity

D_{10} , D_{60} , and D_{90} = grain size in millimeters for which 10, 60, and 90% of the sample is more fine

f_{fines} = fraction of soil (by weight) that passes the number 200 sieve

C.3.6 Long-Term Design Infiltration Rate Correction Factors

The SMMEW provides limited recommendations for what correction factors to apply to short-term infiltration rates to estimate long-term design infiltration rates. We used the recommended correction factors from the SMMWW to apply to the short-term infiltration rates to obtain long-term design infiltration rates. The correction factors include:

CF_v, site variability and number of locations tested. Recommended CF_v values range from 0.33 to 0.9.

CF_t, uncertainty of test method. Recommended CF_t is 0.5 for a small-scale PIT Method and 0.4 for grain-size method.

CF_m, degree of influent control to prevent siltation and biological buildup. The CF_m value correlates to the percentage of the design infiltration rate that the pond will decrease to before maintenance occurs. For example, if an infiltration pond is cleaned after it infiltrates at 90% of the design infiltration rate, then the CF_m correction factor would be 0.9. The 2012 SMMWW does not provide a recommended range of CF_m values.

A total correction factor (CFT) is calculated by finding the product of the correction factors for site variability (CF_v), uncertainty of test method (CF_t), and influent control (CF_m). The short-term infiltration rate is multiplied by the CFT to determine the long-term design infiltration rate.

$$CF_T = CF_v \times CF_t \times CF_m$$

$$CF_T \times \text{Short Term Infiltration Rate} = \text{Long Term Design Infiltration Rate}$$

Our recommended correction factors for the infiltration evaluation are as follows:

$$CF_v = 0.7$$

CF_t = 0.5 for the PIT and 0.4 for the grain-size analysis

$$CF_m = 0.7$$

Therefore, CFT equals 0.25 for the PIT and 0.20 for the grain-size analysis. Table 1 in the main text provides the long-term design infiltration rate results of the PIT evaluation, and Table 2 in the main text provides the long-term design infiltration rate results of the grain-size analysis.

C.4 REFERENCES

Washington State Department of Ecology (Ecology), 2004, Storm drainage design guideline for site characterization, in stormwater management manual for eastern Washington: Olympia, Wash., Washington State Department of Ecology Water Quality Program, Publication No. 004-10-076, Appendix 6B.

Washington State Department of Ecology (Ecology), 2012, Hydrologic analysis and flow control design/BMPs, in stormwater management in western Washington: Olympia, Wash., Washington State Department of Ecology Water Quality Program, Publication No. 12-10-030, v. III.

Yakima County, Wash., 2010, Yakima County regional stormwater manual: Yakima Wash.,
Yakima County: Yakima, Wash., Yakima County, January, available:
<http://www.yakimacounty.us/stormwater/>.

APPENDIX C: 2014 AND 2017 SUBSURFACE DATA

Shannon & Wilson, Inc. (S&W)¹, uses a soil identification system modified from the Unified Soil Classification System (USCS). Elements of the USCS and other definitions are provided on this and the following pages. Soil descriptions are based on visual-manual procedures (ASTM D2488) and laboratory testing procedures (ASTM D2487), if performed.

S&W INORGANIC SOIL CONSTITUENT DEFINITIONS

CONSTITUENT ²	FINE-GRAINED SOILS (50% or more fines) ¹	COARSE-GRAINED SOILS (less than 50% fines) ¹
Major	Silt, Lean Clay, Elastic Silt, ³ or Fat Clay	Sand or Gravel ⁴
Modifying (Secondary) Precedes major constituent	30% or more coarse-grained: Sandy or Gravelly ⁴	More than 12% fine-grained: Silty or Clayey ³
Minor Follows major constituent	15% to 30% coarse-grained: with Sand or with Gravel ⁴ 30% or more total coarse-grained and lesser coarse-grained constituent is 15% or more: with Sand or with Gravel ⁵	5% to 12% fine-grained: with Silt or with Clay ³ 15% or more of a second coarse-grained constituent: with Sand or with Gravel ⁵

¹All percentages are by weight of total specimen passing a 3-inch sieve.
²The order of terms is: *Modifying Major with Minor*.
³Determined based on behavior.
⁴Determined based on which constituent comprises a larger percentage.
⁵Whichever is the lesser constituent.

MOISTURE CONTENT TERMS

Dry	Absence of moisture, dusty, dry to the touch
Moist	Damp but no visible water
Wet	Visible free water, from below water table

STANDARD PENETRATION TEST (SPT) SPECIFICATIONS

Hammer:	140 pounds with a 30-inch free fall. Rope on 6- to 10-inch-diam. cathead 2-1/4 rope turns, > 100 rpm
	NOTE: If automatic hammers are used, blow counts shown on boring logs should be adjusted to account for efficiency of hammer.
Sampler:	10 to 30 inches long Shoe I.D. = 1.375 inches Barrel I.D. = 1.5 inches Barrel O.D. = 2 inches
N-Value:	Sum blow counts for second and third 6-inch increments. Refusal: 50 blows for 6 inches or less; 10 blows for 0 inches.
	NOTE: Penetration resistances (N-values) shown on boring logs are as recorded in the field and have not been corrected for hammer efficiency, overburden, or other factors.

PARTICLE SIZE DEFINITIONS

DESCRIPTION	SIEVE NUMBER AND/OR APPROXIMATE SIZE
FINES	< #200 (0.075 mm = 0.003 in.)
SAND Fine Medium Coarse	#200 to #40 (0.075 to 0.4 mm; 0.003 to 0.02 in.) #40 to #10 (0.4 to 2 mm; 0.02 to 0.08 in.) #10 to #4 (2 to 4.75 mm; 0.08 to 0.187 in.)
GRAVEL Fine Coarse	#4 to 3/4 in. (4.75 to 19 mm; 0.187 to 0.75 in.) 3/4 to 3 in. (19 to 76 mm)
COBBLES	3 to 12 in. (76 to 305 mm)
BOULDERS	> 12 in. (305 mm)

RELATIVE DENSITY / CONSISTENCY

COHESIONLESS SOILS		COHESIVE SOILS	
N, SPT, BLOWS/FT.	RELATIVE DENSITY	N, SPT, BLOWS/FT.	RELATIVE CONSISTENCY
< 4	Very loose	< 2	Very soft
4 - 10	Loose	2 - 4	Soft
10 - 30	Medium dense	4 - 8	Medium stiff
30 - 50	Dense	8 - 15	Stiff
> 50	Very dense	15 - 30	Very stiff
		> 30	Hard

WELL AND BACKFILL SYMBOLS

	Bentonite Cement Grout		Surface Cement Seal
	Bentonite Grout		Asphalt or Cap
	Bentonite Chips		Slough
	Silica Sand		Inclinometer or Non-perforated Casing
	Perforated or Screened Casing		Vibrating Wire Piezometer

PERCENTAGES TERMS^{1,2}

Trace	< 5%
Few	5 to 10%
Little	15 to 25%
Some	30 to 45%
Mostly	50 to 100%

¹Gravel, sand, and fines estimated by mass. Other constituents, such as organics, cobbles, and boulders, estimated by volume.

²Reprinted, with permission, from ASTM D2488 - 09a Standard Practice for Description and Identification of Soils (Visual-Manual Procedure), copyright ASTM International, 100 Barr Harbor Drive, West Conshohocken, PA 19428. A copy of the complete standard may be obtained from ASTM International, www.astm.org.

East-West Corridor Project
 Stage 3
 Yakima, Washington

SOIL DESCRIPTION AND LOG KEY

August 2019

21-1-22425-002

SHANNON & WILSON, INC.
 Geotechnical and Environmental Consultants

FIG. C-1
 Sheet 1 of 3

UNIFIED SOIL CLASSIFICATION SYSTEM (USCS)
 (Modified From USACE Tech Memo 3-357, ASTM D2487, and ASTM D2488)

MAJOR DIVISIONS		GROUP/GRAPHIC SYMBOL	TYPICAL IDENTIFICATIONS	
COARSE-GRAINED SOILS <i>(more than 50% retained on No. 200 sieve)</i>	Gravels <i>(more than 50% of coarse fraction retained on No. 4 sieve)</i>	Gravel <i>(less than 5% fines)</i>	GW 	Well-Graded Gravel; Well-Graded Gravel with Sand
			GP 	Poorly Graded Gravel; Poorly Graded Gravel with Sand
		Silty or Clayey Gravel <i>(more than 12% fines)</i>	GM 	Silty Gravel; Silty Gravel with Sand
			GC 	Clayey Gravel; Clayey Gravel with Sand
	Sands <i>(50% or more of coarse fraction passes the No. 4 sieve)</i>	Sand <i>(less than 5% fines)</i>	SW 	Well-Graded Sand; Well-Graded Sand with Gravel
			SP 	Poorly Graded Sand; Poorly Graded Sand with Gravel
		Silty or Clayey Sand <i>(more than 12% fines)</i>	SM 	Silty Sand; Silty Sand with Gravel
			SC 	Clayey Sand; Clayey Sand with Gravel
FINE-GRAINED SOILS <i>(50% or more passes the No. 200 sieve)</i>	Silt and Clays <i>(liquid limit less than 50)</i>	Inorganic	ML 	Silt; Silt with Sand or Gravel; Sandy or Gravelly Silt
			CL 	Lean Clay; Lean Clay with Sand or Gravel; Sandy or Gravelly Lean Clay
		Organic	OL 	Organic Silt or Clay; Organic Silt or Clay with Sand or Gravel; Sandy or Gravelly Organic Silt or Clay
	Silt and Clays <i>(liquid limit 50 or more)</i>	Inorganic	MH 	Elastic Silt; Elastic Silt with Sand or Gravel; Sandy or Gravelly Elastic Silt
			CH 	Fat Clay; Fat Clay with Sand or Gravel; Sandy or Gravelly Fat Clay
		Organic	OH 	Organic Silt or Clay; Organic Silt or Clay with Sand or Gravel; Sandy or Gravelly Organic Silt or Clay
HIGHLY-ORGANIC SOILS	Primarily organic matter, dark in color, and organic odor	PT 	Peat or other highly organic soils (see ASTM D4427)	

NOTE: No. 4 size = 4.75 mm = 0.187 in.; No. 200 size = 0.075 mm = 0.003 in.

NOTES

- Dual symbols (*symbols separated by a hyphen, i.e., SP-SM, Sand with Silt*) are used for soils with between 5% and 12% fines or when the liquid limit and plasticity index values plot in the CL-ML area of the plasticity chart. Graphics shown on the logs for these soil types are a combination of the two graphic symbols (e.g., SP and SM).
- Borderline symbols (*symbols separated by a slash, i.e., CL/ML, Lean Clay to Silt; SP-SM/SM, Sand with Silt to Silty Sand*) indicate that the soil properties are close to the defining boundary between two groups.

East-West Corridor Project
 Stage 3
 Yakima, Washington

**SOIL DESCRIPTION
 AND LOG KEY**

August 2019

21-1-22425-002

SHANNON & WILSON, INC.
 Geotechnical and Environmental Consultants

FIG. C-1
 Sheet 2 of 3

GRADATION TERMS

Poorly Graded	Narrow range of grain sizes present or, within the range of grain sizes present, one or more sizes are missing (Gap Graded). Meets criteria in ASTM D2487, if tested.
Well-Graded	Full range and even distribution of grain sizes present. Meets criteria in ASTM D2487, if tested.

CEMENTATION TERMS¹

Weak	Crumbles or breaks with handling or slight finger pressure.
Moderate	Crumbles or breaks with considerable finger pressure.
Strong	Will not crumble or break with finger pressure.

PLASTICITY²

DESCRIPTION	VISUAL-MANUAL CRITERIA	APPROX. PLASTICITY INDEX RANGE
Nonplastic	A 1/8-in. thread cannot be rolled at any water content.	< 4
Low	A thread can barely be rolled and a lump cannot be formed when drier than the plastic limit.	4 to 10
Medium	A thread is easy to roll and not much time is required to reach the plastic limit. The thread cannot be rerolled after reaching the plastic limit. A lump crumbles when drier than the plastic limit.	10 to 20
High	It takes considerable time rolling and kneading to reach the plastic limit. A thread can be rerolled several times after reaching the plastic limit. A lump can be formed without crumbling when drier than the plastic limit.	> 20

ADDITIONAL TERMS

Mottled	Irregular patches of different colors.
Bioturbated	Soil disturbance or mixing by plants or animals.
Diamict	Nonsorted sediment; sand and gravel in silt and/or clay matrix.
Cuttings	Material brought to surface by drilling.
Slough	Material that caved from sides of borehole.
Sheared	Disturbed texture, mix of strengths.

PARTICLE ANGULARITY AND SHAPE TERMS¹

Angular	Sharp edges and unpolished planar surfaces.
Subangular	Similar to angular, but with rounded edges.
Subrounded	Nearly planar sides with well-rounded edges.
Rounded	Smoothly curved sides with no edges.
Flat	Width/thickness ratio > 3.
Elongated	Length/width ratio > 3.

ACRONYMS AND ABBREVIATIONS

ATD	At Time of Drilling
Diam.	Diameter
Elev.	Elevation
ft.	Feet
FeO	Iron Oxide
gal.	Gallons
Horiz.	Horizontal
HSA	Hollow Stem Auger
I.D.	Inside Diameter
in.	Inches
lbs.	Pounds
MgO	Magnesium Oxide
mm	Millimeter
MnO	Manganese Oxide
NA	Not Applicable or Not Available
NP	Nonplastic
O.D.	Outside Diameter
OW	Observation Well
pcf	Pounds per Cubic Foot
PID	Photo-Ionization Detector
PMT	Pressuremeter Test
ppm	Parts per Million
psi	Pounds per Square Inch
PVC	Polyvinyl Chloride
rpm	Rotations per Minute
SPT	Standard Penetration Test
USCS	Unified Soil Classification System
q _u	Unconfined Compressive Strength
VWP	Vibrating Wire Piezometer
Vert.	Vertical
WOH	Weight of Hammer
WOR	Weight of Rods
Wt.	Weight

STRUCTURE TERMS¹

Interbedded	Alternating layers of varying material or color with layers at least 1/4-inch thick; singular: bed.
Laminated	Alternating layers of varying material or color with layers less than 1/4-inch thick; singular: lamination.
Fissured	Breaks along definite planes or fractures with little resistance.
Slickensided	Fracture planes appear polished or glossy; sometimes striated.
Blocky	Cohesive soil that can be broken down into small angular lumps that resist further breakdown.
Lensed	Inclusion of small pockets of different soils, such as small lenses of sand scattered through a mass of clay.
Homogeneous	Same color and appearance throughout.

East-West Corridor Project
 Stage 3
 Yakima, Washington

SOIL DESCRIPTION AND LOG KEY

August 2019

21-1-22425-002


SHANNON & WILSON, INC.
 Geotechnical and Environmental Consultants

FIG. C-1
 Sheet 3 of 3

¹Reprinted, with permission, from ASTM D2488 - 09a Standard Practice for Description and Identification of Soils (Visual-Manual Procedure), copyright ASTM International, 100 Barr Harbor Drive, West Conshohocken, PA 19428. A copy of the complete standard may be obtained from ASTM International, www.astm.org.

²Adapted, with permission, from ASTM D2488 - 09a Standard Practice for Description and Identification of Soils (Visual-Manual Procedure), copyright ASTM International, 100 Barr Harbor Drive, West Conshohocken, PA 19428. A copy of the complete standard may be obtained from ASTM International, www.astm.org.

Total Depth: 140 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 8 in.
 Top Elevation: ~ 1080 ft. Easting: _____ Drilling Company: Holt Services Rod Diam.: 3-1/2"
 Vert. Datum: NAVD88 Station: _____ Drill Rig Equipment: Terrasonic 150 Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- Soil Core (as in Sonic Core Borings)
- ⊥ 2.0" O.D. Split Spoon Sample
- ▽ Ground Water Level ATD

- ◇ % Fines (<0.075mm)
- % Water Content

NOTES

- Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
- Groundwater level, if indicated above, is for the date specified and may vary.
- USCS designation is based on visual-manual classification and selected lab testing.

East-West Corridor Project
 Stage 3
 Yakima, Washington

LOG OF BORING B-1-17

August 2019


21-1-22425-002

SHANNON & WILSON, INC.
 Geotechnical and Environmental Consultants

FIG. C-2
 Sheet 1 of 8

Log: BMC Rev: EAS Typ: LKN
 MASTER LOG E 21-22425.GPJ SHAN WIL.GDT 8/16/19

Total Depth: 140 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 8 in.
 Top Elevation: ~ 1080 ft. Easting: _____ Drilling Company: Holt Services Rod Diam.: 3-1/2"
 Vert. Datum: NAVD88 Station: _____ Drill Rig Equipment: Terrasonic 150 Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- ∇ Ground Water Level ATD
- Soil Core (as in Sonic Core Borings)
- ⊥ 2.0" O.D. Split Spoon Sample

- ◇ % Fines (<0.075mm)
- % Water Content

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.

East-West Corridor Project
 Stage 3
 Yakima, Washington

LOG OF BORING B-1-17

August 2019


21-1-22425-002

SHANNON & WILSON, INC.
 Geotechnical and Environmental Consultants

FIG. C-2
 Sheet 2 of 8

Log: BMC Rev: EAS Typ: LKN MASTER LOG E 21-22425.GPJ SHAN WIL.GDT 8/16/19

Total Depth: 140 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 8 in.
 Top Elevation: ~ 1080 ft. Easting: _____ Drilling Company: Holt Services Rod Diam.: 3-1/2"
 Vert. Datum: NAVD88 Station: _____ Drill Rig Equipment: Terrasonic 150 Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



Log: BMC Rev: EAS Typ: LKN MASTER LOG E 21-22425.GPJ SHAN WIL.GDT 8/16/19

CONTINUED NEXT SHEET
LEGEND

- * Sample Not Recovered
- ☐ Soil Core (as in Sonic Core Borings)
- ⊥ 2.0" O.D. Split Spoon Sample
- ▽ Ground Water Level ATD

- ◇ % Fines (<0.075mm)
- % Water Content

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.


East-West Corridor Project
 Stage 3
 Yakima, Washington

LOG OF BORING B-1-17

August 2019 21-1-22425-002

SHANNON & WILSON, INC. Geotechnical and Environmental Consultants	FIG. C-2 Sheet 3 of 8
---	---------------------------------

Total Depth: 140 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 8 in.
 Top Elevation: ~ 1080 ft. Easting: _____ Drilling Company: Holt Services Rod Diam.: 3-1/2"
 Vert. Datum: NAVD88 Station: _____ Drill Rig Equipment: Terrasonic 150 Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- Soil Core (as in Sonic Core Borings)
- ⊥ 2.0" O.D. Split Spoon Sample
- ▽ Ground Water Level ATD
- ◇ % Fines (<0.075mm)
- % Water Content

NOTES

- Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
- Groundwater level, if indicated above, is for the date specified and may vary.
- USCS designation is based on visual-manual classification and selected lab testing.

East-West Corridor Project
 Stage 3
 Yakima, Washington

LOG OF BORING B-1-17

August 2019


21-1-22425-002

SHANNON & WILSON, INC.
 Geotechnical and Environmental Consultants

FIG. C-2
 Sheet 4 of 8

Log: BMC Rev: EAS Typ: LKN MASTER LOG E 21-22425.GPJ SHAN WIL.GDT 8/16/19

Total Depth: 140 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 8 in.
 Top Elevation: ~ 1080 ft. Easting: _____ Drilling Company: Holt Services Rod Diam.: 3-1/2"
 Vert. Datum: NAVD88 Station: _____ Drill Rig Equipment: Terrasonic 150 Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- Soil Core (as in Sonic Core Borings)
- ⊥ 2.0" O.D. Split Spoon Sample
- ▽ Ground Water Level ATD
- ◇ % Fines (<0.075mm)
- % Water Content

NOTES

- Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
- Groundwater level, if indicated above, is for the date specified and may vary.
- USCS designation is based on visual-manual classification and selected lab testing.

East-West Corridor Project
 Stage 3
 Yakima, Washington

LOG OF BORING B-1-17

August 2019


21-1-22425-002

SHANNON & WILSON, INC.
 Geotechnical and Environmental Consultants

FIG. C-2
 Sheet 5 of 8

Log: BMC Rev: EAS Typ: LKN MASTER LOG E 21-22425.GPJ SHAN WIL.GDT 8/16/19

Total Depth: 140 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 8 in.
 Top Elevation: ~ 1080 ft. Easting: _____ Drilling Company: Holt Services Rod Diam.: 3-1/2"
 Vert. Datum: NAVD88 Station: _____ Drill Rig Equipment: Terrasonic 150 Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- Soil Core (as in Sonic Core Borings)
- ⊥ 2.0" O.D. Split Spoon Sample
- ▽ Ground Water Level ATD

- ◇ % Fines (<0.075mm)
- % Water Content

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.

East-West Corridor Project
 Stage 3
 Yakima, Washington

LOG OF BORING B-1-17

August 2019


21-1-22425-002

SHANNON & WILSON, INC.
 Geotechnical and Environmental Consultants

FIG. C-2
 Sheet 6 of 8

Log: BMC Rev: EAS Typ: LKN
 MASTER LOG E 21-22425.GPJ SHAN WIL.GDT 8/16/19

Total Depth: 140 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 8 in.
 Top Elevation: ~ 1080 ft. Easting: _____ Drilling Company: Holt Services Rod Diam.: 3-1/2"
 Vert. Datum: NAVD88 Station: _____ Drill Rig Equipment: Terrasonic 150 Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- Soil Core (as in Sonic Core Borings)
- ⊥ 2.0" O.D. Split Spoon Sample
- ▽ Ground Water Level ATD

- ◇ % Fines (<0.075mm)
- % Water Content

NOTES

- Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
- Groundwater level, if indicated above, is for the date specified and may vary.
- USCS designation is based on visual-manual classification and selected lab testing.

East-West Corridor Project
 Stage 3
 Yakima, Washington

LOG OF BORING B-1-17

August 2019

21-1-22425-002

SHANNON & WILSON, INC.
 Geotechnical and Environmental Consultants

FIG. C-2
 Sheet 7 of 8

Log: BMC Rev: EAS Typ: LKN MASTER LOG E 21-22425.GPJ SHAN WIL.GDT 8/16/19

Total Depth: 140 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 8 in.
 Top Elevation: ~ 1080 ft. Easting: _____ Drilling Company: Holt Services Rod Diam.: 3-1/2"
 Vert. Datum: NAVD88 Station: _____ Drill Rig Equipment: Terrasonic 150 Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____

SOIL DESCRIPTION <i>Refer to the report text for a proper understanding of the subsurface materials and drilling methods. The stratification lines indicated below represent the approximate boundaries between material types, and the transition may be gradual.</i>	Depth, ft.	Symbol	Samples	Ground Water	Depth, ft.	PENETRATION RESISTANCE (blows/foot) ▲ Hammer Wt. & Drop: <u>140 lbs / 30 inches</u>			
						0	20	40	60
BOTTOM OF BORING COMPLETED 7/31/2017	140.0								
					142				
					144				
					146				
					148				
					150				
					152				
					154				
					156				
					158				

Log: BMC Rev: EAS Typ: LKN
MASTER LOG E 21-22425.GPJ SHAN WIL.GDT 8/16/19

LEGEND


- * Sample Not Recovered
- ☐ Soil Core (as in Sonic Core Borings)
- ┌ 2.0" O.D. Split Spoon Sample
- ∇ Ground Water Level ATD
- ◇ % Fines (<0.075mm)
- % Water Content

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.

East-West Corridor Project Stage 3 Yakima, Washington	
LOG OF BORING B-1-17	
August 2019	21-1-22425-002
SHANNON & WILSON, INC. Geotechnical and Environmental Consultants	FIG. C-2 Sheet 8 of 8

Total Depth: 40.2 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 6 in.
 Top Elevation: ~ 1055 ft. Easting: _____ Drilling Company: Holt Services Rod Diam.: 3-1/2"
 Vert. Datum: NAVD88 Station: _____ Drill Rig Equipment: Terrasonic 150 Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- Soil Core (as in Sonic Core Borings)
- 2.0" O.D. Split Spoon Sample
- Well Screen and Sand Filter
- Bentonite-Cement Grout
- Bentonite Chips/Pellets
- Bentonite Grout
- Ground Water Level in Well
- ◇ % Fines (<0.075mm)
- % Water Content

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.

East-West Corridor Project
 Stage 3
 Yakima, Washington

LOG OF BORING B-2-17

August 2019

21-1-22425-002

SHANNON & WILSON, INC.
 Geotechnical and Environmental Consultants

FIG. C-3
 Sheet 2 of 3

Log: BMC Rev: EAS Typ: LKN
 MASTER LOG E 21-22425.GPJ SHAN WIL.GDT 8/16/19

Total Depth: 40.2 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 6 in.
 Top Elevation: ~ 1055 ft. Easting: _____ Drilling Company: Holt Services Rod Diam.: 3-1/2"
 Vert. Datum: NAVD88 Station: _____ Drill Rig Equipment: Terrasonic 150 Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____

SOIL DESCRIPTION <i>Refer to the report text for a proper understanding of the subsurface materials and drilling methods. The stratification lines indicated below represent the approximate boundaries between material types, and the transition may be gradual.</i>	Depth, ft.	Symbol	Samples	Ground Water	Depth, ft.	PENETRATION RESISTANCE (blows/foot) ▲ Hammer Wt. & Drop: <u>140 lbs / 30 inches</u>				
						0	20	40	60	
BOTTOM OF BORING COMPLETED 8/3/2017	40.2	▲	8						50/27	

Log: BMC Rev: EAS Typ: LKN
MASTER LOG E 21-22425.GPJ SHAN WIL.GDT 8/16/19

LEGEND

* Sample Not Recovered		Well Screen and Sand Filter	◇ % Fines (<0.075mm)
Soil Core (as in Sonic Core Borings)		Bentonite-Cement Grout	● % Water Content
2.0" O.D. Split Spoon Sample		Bentonite Chips/Pellets	
		Bentonite Grout	
	▼	Ground Water Level in Well	

- NOTES**
1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
 2. Groundwater level, if indicated above, is for the date specified and may vary.
 3. USCS designation is based on visual-manual classification and selected lab testing.


East-West Corridor Project
Stage 3
Yakima, Washington

LOG OF BORING B-2-17

August 2019 21-1-22425-002

SHANNON & WILSON, INC. Geotechnical and Environmental Consultants	FIG. C-3 Sheet 3 of 3
---	---------------------------------

Total Depth: 125.3 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 7 in.
 Top Elevation: ~ 1045 ft. Easting: _____ Drilling Company: Holt Rod Diam.: 6-inch core
 Vert. Datum: NAVD88 Station: _____ Drill Rig Equipment: Terrasonic 150 Track Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



CONTINUED NEXT SHEET
LEGEND

- * Sample Not Recovered
- ∇ Ground Water Level ATD
- ◇ % Fines (<0.075mm)
- ⊥ 2.0" O.D. Split Spoon Sample
- % Water Content


NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.

East-West Corridor Project Stage 3 Yakima, Washington	
<h2 style="margin: 0;">LOG OF BORING B-3-18</h2>	
August 2019	21-1-22425-002
SHANNON & WILSON, INC. Geotechnical and Environmental Consultants	FIG. C-4 Sheet 1 of 7

Log: BMC Rev: BMC Typ: LKN
 MASTER LOG E 21-22425.GPJ SHAN WIL.GDT 8/16/19

Total Depth: 125.3 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 7 in.
 Top Elevation: ~ 1045 ft. Easting: _____ Drilling Company: Holt Rod Diam.: 6-inch core
 Vert. Datum: NAVD88 Station: _____ Drill Rig Equipment: Terrasonic 150 Track Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- ∇ Ground Water Level ATD
- ◇ % Fines (<0.075mm)
- ⊔ 2.0" O.D. Split Spoon Sample
- % Water Content

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.

East-West Corridor Project
Stage 3
Yakima, Washington

LOG OF BORING B-3-18

August 2019


21-1-22425-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. C-4
Sheet 2 of 7

Log: BMC Rev: BMC Typ: LKN
MASTER LOG E 21-22425.GPJ SHAN WIL.GDT 8/16/19

Total Depth: 125.3 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 7 in.
 Top Elevation: ~ 1045 ft. Easting: _____ Drilling Company: Holt Rod Diam.: 6-inch core
 Vert. Datum: NAVD88 Station: _____ Drill Rig Equipment: Terrasonic 150 Track Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- ∇ Ground Water Level ATD
- ◇ % Fines (<0.075mm)
- ⊔ 2.0" O.D. Split Spoon Sample
- % Water Content

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.

East-West Corridor Project
 Stage 3
 Yakima, Washington

LOG OF BORING B-3-18

August 2019


21-1-22425-002

SHANNON & WILSON, INC.
 Geotechnical and Environmental Consultants

FIG. C-4
 Sheet 3 of 7

Log: BMC Rev: BMC Typ: LKN
 MASTER LOG E 21-22425.GPJ SHAN WIL.GDT 8/16/19

Total Depth: 125.3 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 7 in.
 Top Elevation: ~ 1045 ft. Easting: _____ Drilling Company: Holt Rod Diam.: 6-inch core
 Vert. Datum: NAVD88 Station: _____ Drill Rig Equipment: Terrasonic 150 Track Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



CONTINUED NEXT SHEET
LEGEND

- * Sample Not Recovered
- ∇ Ground Water Level ATD
- ⊥ 2.0" O.D. Split Spoon Sample

- ◇ % Fines (<0.075mm)
- % Water Content

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.

East-West Corridor Project
 Stage 3
 Yakima, Washington

LOG OF BORING B-3-18

August 2019


21-1-22425-002

SHANNON & WILSON, INC.
 Geotechnical and Environmental Consultants

FIG. C-4
 Sheet 4 of 7

Log: BMC Rev: BMC Typ: LKN
 MASTER LOG E 21-22425.GPJ SHAN WIL.GDT 8/16/19

Total Depth: 125.3 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 7 in.
 Top Elevation: ~ 1045 ft. Easting: _____ Drilling Company: Holt Rod Diam.: 6-inch core
 Vert. Datum: NAVD88 Station: _____ Drill Rig Equipment: Terrasonic 150 Track Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- ∇ Ground Water Level ATD
- ⊥ 2.0" O.D. Split Spoon Sample

- ◇ % Fines (<0.075mm)
- % Water Content

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.

East-West Corridor Project
 Stage 3
 Yakima, Washington

LOG OF BORING B-3-18

August 2019


21-1-22425-002

SHANNON & WILSON, INC.
 Geotechnical and Environmental Consultants

FIG. C-4
 Sheet 5 of 7

Log: BMC Rev: BMC Typ: LKN
 MASTER LOG E 21-22425.GPJ SHAN WIL.GDT 8/16/19

Total Depth: 125.3 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 7 in.
 Top Elevation: ~ 1045 ft. Easting: _____ Drilling Company: Holt Rod Diam.: 6-inch core
 Vert. Datum: NAVD88 Station: _____ Drill Rig Equipment: Terrasonic 150 Track Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- ∇ Ground Water Level ATD
- ◇ % Fines (<0.075mm)
- ⊥ 2.0" O.D. Split Spoon Sample
- % Water Content

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.

East-West Corridor Project
 Stage 3
 Yakima, Washington

LOG OF BORING B-3-18

August 2019


21-1-22425-002

SHANNON & WILSON, INC.
 Geotechnical and Environmental Consultants

FIG. C-4
 Sheet 6 of 7

Log: BMC Rev: BMC Typ: LKN
 MASTER LOG E 21-22425.GPJ SHAN WIL.GDT 8/16/19

Total Depth: 125.3 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 7 in.
 Top Elevation: ~ 1045 ft. Easting: _____ Drilling Company: Holt Rod Diam.: 6-inch core
 Vert. Datum: NAVD88 Station: _____ Drill Rig Equipment: Terrasonic 150 Track Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



LEGEND

* Sample Not Recovered ▽ Ground Water Level ATD ◇ % Fines (<0.075mm)
 | 2.0" O.D. Split Spoon Sample ● % Water Content

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.

East-West Corridor Project
 Stage 3
 Yakima, Washington


LOG OF BORING B-3-18

August 2019 21-1-22425-002

SHANNON & WILSON, INC. **FIG. C-4**
 Geotechnical and Environmental Consultants Sheet 7 of 7

Log: BMC Rev: BMC Typ: LKN
 MASTER LOG E 21-22425.GPJ SHAN WIL.GDT 8/16/19

Total Depth: 100.1 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 8 in.
 Top Elevation: ~ 1057.5 ft. Easting: _____ Drilling Company: Holt Services, Inc. Rod Diam.: _____
 Vert. Datum: _____ Station: _____ Drill Rig Equipment: Terra Sonic Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- [Symbol] Soil Core (as in Sonic Core Borings)
- [Symbol] 2.0" O.D. Split Spoon Sample
- [Symbol] Well Screen and Sand Filter
- [Symbol] Bentonite-Cement Grout
- [Symbol] Bentonite Chips/Pellets
- [Symbol] Bentonite Grout
- ▽ Ground Water Level ATD
- ▽ Ground Water Level in VWP

NOTES

- Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
- Groundwater level, if indicated above, is for the date specified and may vary.
- USCS designation is based on visual-manual classification and selected lab testing.

- ◇ % Fines (<0.075mm)
- % Water Content
- Plastic Limit —●— Liquid Limit
- Natural Water Content

East-West Corridor Project
Yakima County, Washington

LOG OF BORING EWC-B-01-14

August 2015


21-1-21630-004

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. C-5
Sheet 1 of 6

Log: SAW Rev: JKP Typ: CLP
MASTER LOG E 21-21630.GPJ SHAN WIL.GDT 11/13/17

Total Depth: 100.1 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 8 in.
 Top Elevation: ~ 1057.5 ft. Easting: _____ Drilling Company: Holt Services, Inc. Rod Diam.: _____
 Vert. Datum: _____ Station: _____ Drill Rig Equipment: Terra Sonic Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- Soil Core (as in Sonic Core Borings)
- ⊥ 2.0" O.D. Split Spoon Sample
- ▨ Well Screen and Sand Filter
- ▩ Bentonite-Cement Grout
- ▧ Bentonite Chips/Pellets
- ▦ Bentonite Grout
- ∇ Ground Water Level ATD
- ▽ Ground Water Level in VWP

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.

- ◇ % Fines (<0.075mm)
- % Water Content
- Plastic Limit —●— Liquid Limit
- Natural Water Content

East-West Corridor Project
Yakima County, Washington

LOG OF BORING EWC-B-01-14

August 2015

21-1-21630-004


SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. C-5
Sheet 2 of 6

Log: SAW Rev: JKP Typ: CLP

MASTER LOG E 21-21630.GPJ SHAN WIL.GDT 11/13/17

Total Depth: 100.1 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 8 in.
 Top Elevation: ~ 1057.5 ft. Easting: _____ Drilling Company: Holt Services, Inc. Rod Diam.: _____
 Vert. Datum: _____ Station: _____ Drill Rig Equipment: Terra Sonic Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- Soil Core (as in Sonic Core Borings)
- 2.0" O.D. Split Spoon Sample
- Well Screen and Sand Filter
- Bentonite-Cement Grout
- Bentonite Chips/Pellets
- Bentonite Grout
- Ground Water Level ATD
- Ground Water Level in VWP

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.

- % Fines (<0.075mm)
- % Water Content
- Plastic Limit Liquid Limit
- Natural Water Content

East-West Corridor Project
Yakima County, Washington

LOG OF BORING EWC-B-01-14

August 2015


21-1-21630-004

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. C-5
Sheet 3 of 6

Log: SAW Rev: JKP Typ: CLP MASTER LOG E 21-21630.GPJ SHAN WIL.GDT 11/13/17

Total Depth: 100.1 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 8 in.
 Top Elevation: ~ 1057.5 ft. Easting: _____ Drilling Company: Holt Services, Inc. Rod Diam.: _____
 Vert. Datum: _____ Station: _____ Drill Rig Equipment: Terra Sonic Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- Soil Core (as in Sonic Core Borings)
- ┌ 2.0" O.D. Split Spoon Sample
- Well Screen and Sand Filter
- ▨ Bentonite-Cement Grout
- ▩ Bentonite Chips/Pellets
- ▧ Bentonite Grout
- ▽ Ground Water Level ATD
- ▽ Ground Water Level in VWP

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.

- ◇ % Fines (<0.075mm)
- % Water Content
- Plastic Limit —●— Liquid Limit
- Natural Water Content

East-West Corridor Project
Yakima County, Washington

LOG OF BORING EWC-B-01-14

August 2015


21-1-21630-004

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. C-5
Sheet 4 of 6

Log: SAW Rev: JKP Typ: CLP MASTER LOG E 21-21630.GPJ SHAN WIL.GDT 11/13/17

Total Depth: 100.1 ft Northing: _____ Drilling Method: Sonic Core Hole Diam.: 8 in.
 Top Elevation: ~ 1057.5 ft. Easting: _____ Drilling Company: Holt Services, Inc. Rod Diam.: _____
 Vert. Datum: _____ Station: _____ Drill Rig Equipment: Terra Sonic Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- Soil Core (as in Sonic Core Borings)
- 2.0" O.D. Split Spoon Sample
- Well Screen and Sand Filter
- Bentonite-Cement Grout
- Bentonite Chips/Pellets
- Bentonite Grout
- Ground Water Level ATD
- Ground Water Level in VWP

NOTES

- Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
- Groundwater level, if indicated above, is for the date specified and may vary.
- USCS designation is based on visual-manual classification and selected lab testing.

- % Fines (<0.075mm)
- % Water Content
- Plastic Limit Liquid Limit
- Natural Water Content

East-West Corridor Project
Yakima County, Washington

LOG OF BORING EWC-B-01-14

August 2015

21-1-21630-004

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. C-5
Sheet 5 of 6

Log: SAW Rev: JKP Typ: CLP MASTER LOG E 21-21630.GPJ SHAN WIL.GDT 11/13/17

Total Depth: 100.1 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 8 in.
 Top Elevation: ~ 1057.5 ft. Easting: _____ Drilling Company: Holt Services, Inc. Rod Diam.: _____
 Vert. Datum: _____ Station: _____ Drill Rig Equipment: Terra Sonic Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____

SOIL DESCRIPTION <i>Refer to the report text for a proper understanding of the subsurface materials and drilling methods. The stratification lines represent the approximate boundaries between material types, and the transition may be gradual.</i>	Depth, ft.	Symbol	PID, ppm	Samples	Ground Water	Depth, ft.	PENETRATION RESISTANCE (blows/foot)			
							▲ Hammer Wt. & Drop: <u>140 lbs / 30 inches</u>			
BOTTOM OF BORING COMPLETED 7/15/2014 Notes: a) Some blow counts are high due to the presence of gravel and cobbles, and do not reflect the relative density of the soil unit. b) Moisture content may be reduced by frictional heating generated during drilling. c) Boulders may be present in alluvium layers. d) Drilled using 4- and 6-inch diameter sonic core casings. Recovered 4-inch diameter soil core.	100.1			20		0	20	40	60	50/2
	102									
	104									
	106									
	108									
	110									
	112									
	114									
	116									
	118									

Log: SAW Rev: JKP Typ: CLP
MASTER LOG E 21-21630.GPJ SHAN WIL.GDT 11/13/17

LEGEND

* Sample Not Recovered		Well Screen and Sand Filter	◇ % Fines (<0.075mm)
Soil Core (as in Sonic Core Borings)		Bentonite-Cement Grout	● % Water Content
2.0" O.D. Split Spoon Sample		Bentonite Chips/Pellets	Plastic Limit —●— Liquid Limit
		Bentonite Grout	Natural Water Content
		Ground Water Level ATD	
		Ground Water Level in VWP	

- NOTES**
1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
 2. Groundwater level, if indicated above, is for the date specified and may vary.
 3. USCS designation is based on visual-manual classification and selected lab testing.

East-West Corridor Project
Yakima County, Washington

LOG OF BORING EWC-B-01-14

August 2015 21-1-21630-004

SHANNON & WILSON, INC. Geotechnical and Environmental Consultants	FIG. C-5 Sheet 6 of 6
---	---------------------------------



Total Depth: 101.5 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 8 in.
 Top Elevation: ~ 1052 ft. Easting: _____ Drilling Company: Holt Services, Inc. Rod Diam.: _____
 Vert. Datum: _____ Station: _____ Drill Rig Equipment: Terra Sonic Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____

SOIL DESCRIPTION
 Refer to the report text for a proper understanding of the subsurface materials and drilling methods. The stratification lines represent the approximate boundaries between material types, and the transition may be gradual.



Depth, ft. Symbol PID, ppm Samples Ground Water

PENETRATION RESISTANCE (blows/foot)
 ▲ Hammer Wt. & Drop: 140 lbs / 30 inches



Medium dense to dense, brown to dark brown, *Silty Sand with Gravel (SM)*; moist; subangular to subrounded and broken gravel; organics including wood chips and grass.
 Fill (Hf)
 - Few cobbles below 5 feet.





Medium dense to dense, gray, *Poorly Graded Gravel with Cobbles (GP)*; moist; few angular to subrounded cobbles; angular to rounded gravel; little sand; trace fines.
 Fill (Hf)





Medium dense to dense, brown, *Silty Sand with Gravel (SM)*; moist; angular to subrounded gravel; fine to medium sand; little wood debris; trace organics.
 Fill (Hf)





Medium dense to dense, brown, *Silty Gravel with Sand (GM) to Poorly Graded Gravel with Silt, Sand, and Cobbles (GP-GM)*; moist; angular to rounded gravel.
 Fill (Hf)



Medium dense, gray to gray-brown, *Silty Sand (SM)*; wet; trace fine gravel; unit fining upward.
 Alluvium (Qa)



Medium dense, gray to gray-brown, *Poorly Graded Gravel with Sand (GP)*; wet; subangular to rounded gravel; trace fines.
 Alluvium (Qa)



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- Soil Core (as in Sonic Core Borings)
- 2.0" O.D. Split Spoon Sample
- Well Screen and Sand Filter
- Bentonite-Cement Grout
- Bentonite Chips/Pellets
- Bentonite Grout
- Ground Water Level ATD
- Ground Water Level in VWP
- % Fines (<0.075mm)
- % Water Content

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.

East-West Corridor Project
 Yakima County, Washington

LOG OF BORING EWC-B-02-14

August 2015


21-1-21630-004

SHANNON & WILSON, INC.
 Geotechnical and Environmental Consultants

FIG. C-6
 Sheet 1 of 6

Log: SAW Rev: JKP Typ: CLP MASTER LOG E 21-21630.GPJ SHAN WIL.GDT 11/13/17

Total Depth: 101.5 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 8 in.
 Top Elevation: ~ 1052 ft. Easting: _____ Drilling Company: Holt Services, Inc. Rod Diam.: _____
 Vert. Datum: _____ Station: _____ Drill Rig Equipment: Terra Sonic Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- Soil Core (as in Sonic Core Borings)
- 2.0" O.D. Split Spoon Sample
- Well Screen and Sand Filter
- Bentonite-Cement Grout
- Bentonite Chips/Pellets
- Bentonite Grout
- Ground Water Level ATD
- Ground Water Level in VWP

NOTES

- Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
- Groundwater level, if indicated above, is for the date specified and may vary.
- USCS designation is based on visual-manual classification and selected lab testing.

- ◇ % Fines (<0.075mm)
- % Water Content

East-West Corridor Project
 Yakima County, Washington

LOG OF BORING EWC-B-02-14

August 2015

21-1-21630-004

SHANNON & WILSON, INC.
 Geotechnical and Environmental Consultants

FIG. C-6
 Sheet 2 of 6

MASTER LOG E 21-21630.GPJ SHAN WIL.GDT 11/13/17 Log: SAW Rev: JKP Typ: CLP

Total Depth: 101.5 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 8 in.
 Top Elevation: ~ 1052 ft. Easting: _____ Drilling Company: Holt Services, Inc. Rod Diam.: _____
 Vert. Datum: _____ Station: _____ Drill Rig Equipment: Terra Sonic Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____

SOIL DESCRIPTION
 Refer to the report text for a proper understanding of the subsurface materials and drilling methods. The stratification lines represent the approximate boundaries between material types, and the transition may be gradual.

Depth, ft. Symbol PID, ppm Samples Ground Water

PENETRATION RESISTANCE (blows/foot)
 ▲ Hammer Wt. & Drop: 140 lbs / 30 inches

cobbles; subangular to rounded gravel; low plasticity fines.
 Alluvium (Qa)
 - Light tan ash layer(?) from about 37.5 to 39 feet.
 - Light tan ash layer(?) from about 42.5 to 43.5 feet.



43.5
 44.5
 Medium dense to dense, gray-brown to brown, *Poorly Graded Sand with Silt and Gravel (SP-SM)*; wet; subrounded gravel; low plasticity fines.
 Alluvium (Qa)

47.5
 48.0
 Medium dense to dense, brown, *Poorly Graded Gravel with Silt, Sand, and Cobbles (GP-GM)*; moist; 3- to 5-inch, subrounded cobbles; subangular to subrounded gravel.
 Alluvium (Qa)

Medium dense to dense, brown, *Silty Sand (SM)*; wet; trace fine gravel; fine to medium sand.
 Alluvium (Qa)

Loose to dense, brown to gray-brown, *Silty Gravel with Sand and Cobbles (GM)*; moist; little subrounded cobbles; subrounded to rounded gravel.
 Alluvium (Qa)
 - Strong iron-oxide staining at 54.5 feet.

58.5
 Medium dense to dense, brown to gray-brown, *Poorly Graded Gravel with Silt, Sand, and Cobbles (GP-GM)*; moist to wet;



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- Soil Core (as in Sonic Core Borings)
- ⊥ 2.0" O.D. Split Spoon Sample
- Well Screen and Sand Filter
- ▨ Bentonite-Cement Grout
- ▩ Bentonite Chips/Pellets
- ▧ Bentonite Grout
- ▽ Ground Water Level ATD
- ▽ Ground Water Level in VWP

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.

East-West Corridor Project
 Yakima County, Washington

LOG OF BORING EWC-B-02-14

August 2015


21-1-21630-004

SHANNON & WILSON, INC.
 Geotechnical and Environmental Consultants

FIG. C-6
 Sheet 3 of 6

MASTER LOG E 21-21630.GPJ SHAN WIL.GDT 11/13/17 Log: SAW Rev: JKP Typ: CLP

Total Depth: 101.5 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 8 in.
 Top Elevation: ~ 1052 ft. Easting: _____ Drilling Company: Holt Services, Inc. Rod Diam.: _____
 Vert. Datum: _____ Station: _____ Drill Rig Equipment: Terra Sonic Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



Log: SAW Rev: JKP Typ: CLP

CONTINUED NEXT SHEET
LEGEND

- * Sample Not Recovered
- Soil Core (as in Sonic Core Borings)
- ⊥ 2.0" O.D. Split Spoon Sample
- Well Screen and Sand Filter
- ▨ Bentonite-Cement Grout
- ▩ Bentonite Chips/Pellets
- ▧ Bentonite Grout
- ▽ Ground Water Level ATD
- ▽ Ground Water Level in VWP
- ◇ % Fines (<0.075mm)
- % Water Content

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.

East-West Corridor Project
Yakima County, Washington

LOG OF BORING EWC-B-02-14


August 2015 21-1-21630-004

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. C-6
Sheet 4 of 6

MASTER LOG E 21-21630.GPJ SHAN WIL.GDT 11/13/17

Total Depth: 101.5 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 8 in.
 Top Elevation: ~ 1052 ft. Easting: _____ Drilling Company: Holt Services, Inc. Rod Diam.: _____
 Vert. Datum: _____ Station: _____ Drill Rig Equipment: Terra Sonic Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- Soil Core (as in Sonic Core Borings)
- ⊥ 2.0" O.D. Split Spoon Sample
- Well Screen and Sand Filter
- ▨ Bentonite-Cement Grout
- ▩ Bentonite Chips/Pellets
- ▧ Bentonite Grout
- ▽ Ground Water Level ATD
- ▽ Ground Water Level in VWP

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.

East-West Corridor Project
 Yakima County, Washington

LOG OF BORING EWC-B-02-14

August 2015


21-1-21630-004

SHANNON & WILSON, INC.
 Geotechnical and Environmental Consultants

FIG. C-6
 Sheet 5 of 6

Log: SAW Rev: JKP Typ: CLP MASTER LOG E 21-21630.GPJ SHAN WIL.GDT 11/13/17

Total Depth: 101.5 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 8 in.
 Top Elevation: ~ 1052 ft. Easting: _____ Drilling Company: Holt Services, Inc. Rod Diam.: _____
 Vert. Datum: _____ Station: _____ Drill Rig Equipment: Terra Sonic Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



LEGEND

* Sample Not Recovered		Well Screen and Sand Filter	◇ % Fines (<0.075mm)
Soil Core (as in Sonic Core Borings)		Bentonite-Cement Grout	● % Water Content
2.0" O.D. Split Spoon Sample		Bentonite Chips/Pellets	
		Bentonite Grout	
		Ground Water Level ATD	
		Ground Water Level in VWP	

- NOTES**
1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
 2. Groundwater level, if indicated above, is for the date specified and may vary.
 3. USCS designation is based on visual-manual classification and selected lab testing.

East-West Corridor Project
Yakima County, Washington


LOG OF BORING EWC-B-02-14

August 2015 21-1-21630-004

SHANNON & WILSON, INC. Geotechnical and Environmental Consultants	FIG. C-6 Sheet 6 of 6
---	---------------------------------

Log: SAW Rev: JKP Typ: CLP
MASTER LOG E 21-1-21630.GPJ SHAN WIL.GDT 11/13/17

Total Depth: 100.4 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 8 in.
 Top Elevation: ~ 1056.5 ft. Easting: _____ Drilling Company: Holt Services, Inc. Rod Diam.: _____
 Vert. Datum: _____ Station: _____ Drill Rig Equipment: Terra Sonic Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- Soil Core (as in Sonic Core Borings)
- Grab Sample
- 2.0" O.D. Split Spoon Sample
- Well Screen and Sand Filter
- Bentonite-Cement Grout
- Bentonite Chips/Pellets
- Bentonite Grout
- Ground Water Level ATD
- Ground Water Level in VWP
- % Fines (<0.075mm)
- % Water Content

NOTES

- Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
- Groundwater level, if indicated above, is for the date specified and may vary.
- USCS designation is based on visual-manual classification and selected lab testing.

East-West Corridor Project
Yakima County, Washington

LOG OF BORING EWC-B-03-14

August 2015

21-1-21630-004


SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. C-7
Sheet 2 of 6

Log: SAW Rev: JKP Typ: CLP

MASTER LOG E 21-21630.GPJ SHAN WIL.GDT 11/13/17

Total Depth: 100.4 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 8 in.
 Top Elevation: ~ 1056.5 ft. Easting: _____ Drilling Company: Holt Services, Inc. Rod Diam.: _____
 Vert. Datum: _____ Station: _____ Drill Rig Equipment: Terra Sonic Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



Log: SAW Rev: JKP Typ: CLP

CONTINUED NEXT SHEET

LEGEND

* Sample Not Recovered	Well Screen and Sand Filter	◇ % Fines (<0.075mm)
Soil Core (as in Sonic Core Borings)	Bentonite-Cement Grout	● % Water Content
Grab Sample	Bentonite Chips/Pellets	
2.0" O.D. Split Spoon Sample	Bentonite Grout	
	Ground Water Level ATD	
	Ground Water Level in VWP	

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.

East-West Corridor Project
Yakima County, Washington

LOG OF BORING EWC-B-03-14


August 2015 21-1-21630-004

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. C-7
Sheet 3 of 6

MASTER LOG E 21-21630.GPJ SHAN WIL.GDT 11/13/17

Total Depth: 100.4 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 8 in.
 Top Elevation: ~ 1056.5 ft. Easting: _____ Drilling Company: Holt Services, Inc. Rod Diam.: _____
 Vert. Datum: _____ Station: _____ Drill Rig Equipment: Terra Sonic Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



Log: SAW Rev: JKP Typ: CLP
MASTER LOG E. 21-21630.GPJ SHAN WIL.GDT 11/13/17

CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- Soil Core (as in Sonic Core Borings)
- Grab Sample
- 2.0" O.D. Split Spoon Sample
- Well Screen and Sand Filter
- Bentonite-Cement Grout
- Bentonite Chips/Pellets
- Bentonite Grout
- Ground Water Level ATD
- Ground Water Level in VWP

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.

- ◇ % Fines (<0.075mm)
- % Water Content

East-West Corridor Project
Yakima County, Washington

LOG OF BORING EWC-B-03-14


August 2015

21-1-21630-004

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. C-7
Sheet 4 of 6

Total Depth: 100.4 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 8 in.
 Top Elevation: ~ 1056.5 ft. Easting: _____ Drilling Company: Holt Services, Inc. Rod Diam.: _____
 Vert. Datum: _____ Station: _____ Drill Rig Equipment: Terra Sonic Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



CONTINUED NEXT SHEET

LEGEND

- | | | | | |
|------------------------|--|-----------------------------|--|--------------------|
| * Sample Not Recovered | | Well Screen and Sand Filter | | % Fines (<0.075mm) |
| | | Bentonite-Cement Grout | | % Water Content |
| | | Bentonite Chips/Pellets | | |
| | | Bentonite Grout | | |
| | | Ground Water Level ATD | | |
| | | Ground Water Level in VWP | | |

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.

East-West Corridor Project
Yakima County, Washington

LOG OF BORING EWC-B-03-14

August 2015

21-1-21630-004

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. C-7
Sheet 5 of 6

Total Depth: 100.4 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 8 in.
 Top Elevation: ~ 1056.5 ft. Easting: _____ Drilling Company: Holt Services, Inc. Rod Diam.: _____
 Vert. Datum: _____ Station: _____ Drill Rig Equipment: Terra Sonic Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____

SOIL DESCRIPTION <i>Refer to the report text for a proper understanding of the subsurface materials and drilling methods. The stratification lines represent the approximate boundaries between material types, and the transition may be gradual.</i>	Depth, ft.	Symbol	PID, ppm	Samples	Ground Water	Depth, ft.	PENETRATION RESISTANCE (blows/foot)			
							▲ Hammer Wt. & Drop: <u>140 lbs / 30 inches</u>			
BOTTOM OF BORING COMPLETED 6/30/2014 Notes: a) Some blow counts are high due to the presence of gravel and cobbles, and do not reflect the relative density of the soil unit. b) Moisture content may be reduced by frictional heating generated during drilling. c) Boulders may be present in alluvium layers.	100.4			20		0	20	40	60	50/5"
	102									
	104									
	106									
	108									
	110									
	112									
	114									
	116									
	118									

LEGEND

* Sample Not Recovered		Well Screen and Sand Filter	◇ % Fines (<0.075mm)
Soil Core (as in Sonic Core Borings)		Bentonite-Cement Grout	● % Water Content
Grab Sample		Bentonite Chips/Pellets	
2.0" O.D. Split Spoon Sample		Bentonite Grout	
		Ground Water Level ATD	
		Ground Water Level in VWP	

NOTES

- Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
- Groundwater level, if indicated above, is for the date specified and may vary.
- USCS designation is based on visual-manual classification and selected lab testing.

East-West Corridor Project
Yakima County, Washington


LOG OF BORING EWC-B-03-14

August 2015 21-1-21630-004

SHANNON & WILSON, INC. Geotechnical and Environmental Consultants	FIG. C-7 Sheet 6 of 6
---	---------------------------------

Log: SAW Rev: JKP Typ: CLP
MASTER LOG E 21-21630.GPJ SHAN WIL.GDT 11/13/17

Total Depth: 100.3 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 8 in.
 Top Elevation: ~ 1047 ft. Easting: _____ Drilling Company: Holt Services, Inc. Rod Diam.: _____
 Vert. Datum: _____ Station: _____ Drill Rig Equipment: Terra Sonic Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



Log: SAW Rev: JKP Typ: CLP MASTER LOG E 21-21630.GPJ SHAN WIL.GDT 11/13/17

CONTINUED NEXT SHEET
LEGEND

- * Sample Not Recovered
- Soil Core (as in Sonic Core Borings)
- ⊥ 2.0" O.D. Split Spoon Sample
- Well Screen and Sand Filter
- ▨ Bentonite-Cement Grout
- ▩ Bentonite Chips/Pellets
- ▧ Bentonite Grout
- ▽ Ground Water Level ATD
- ▽ Ground Water Level in VWP

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.

East-West Corridor Project
 Yakima County, Washington

LOG OF BORING EWC-B-04-14


August 2015

21-1-21630-004

SHANNON & WILSON, INC.
 Geotechnical and Environmental Consultants

FIG. C-8
 Sheet 2 of 6

Total Depth: 100.3 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 8 in.
 Top Elevation: ~ 1047 ft. Easting: _____ Drilling Company: Holt Services, Inc. Rod Diam.: _____
 Vert. Datum: _____ Station: _____ Drill Rig Equipment: Terra Sonic Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



CONTINUED NEXT SHEET

LEGEND

- * Sample Not Recovered
- Soil Core (as in Sonic Core Borings)
- 2.0" O.D. Split Spoon Sample
- Well Screen and Sand Filter
- Bentonite-Cement Grout
- Bentonite Chips/Pellets
- Bentonite Grout
- Ground Water Level ATD
- Ground Water Level in VWP

NOTES

1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
2. Groundwater level, if indicated above, is for the date specified and may vary.
3. USCS designation is based on visual-manual classification and selected lab testing.

- % Fines (<0.075mm)
- % Water Content

East-West Corridor Project
Yakima County, Washington

LOG OF BORING EWC-B-04-14

August 2015

21-1-21630-004

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. C-8
Sheet 3 of 6

Log: SAW Rev: JKP Typ: CLP

MASTER LOG E 21-21630.GPJ SHAN WIL.GDT 11/13/17

Total Depth: 100.3 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 8 in.
 Top Elevation: ~ 1047 ft. Easting: _____ Drilling Company: Holt Services, Inc. Rod Diam.: _____
 Vert. Datum: _____ Station: _____ Drill Rig Equipment: Terra Sonic Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____



SOIL DESCRIPTION
 Refer to the report text for a proper understanding of the subsurface materials and drilling methods. The stratification lines represent the approximate boundaries between material types, and the transition may be gradual.

Medium dense to dense, gray-brown to brown mottled with red-brown, *Clayey Gravel with Sand and Cobbles (GC)*; moist; few cobbles; angular to rounded gravel. Alluvium (Qa)

-- Strong iron-oxide staining below 66 feet.

Medium dense to dense, brown mottled with red-brown and gray, *Poorly Graded Gravel with Silt, Sand, and Cobbles (GP-GM)*; moist; few cobbles; subangular to rounded gravel; low plasticity fines; weathered cobbles and gravel. Alluvium (Qa)

-- Strong iron-oxide staining from 79 to 80 feet.



CONTINUED NEXT SHEET

- LEGEND**
- * Sample Not Recovered
 - Soil Core (as in Sonic Core Borings)
 - ⊥ 2.0" O.D. Split Spoon Sample
 - Well Screen and Sand Filter
 - ▨ Bentonite-Cement Grout
 - ▩ Bentonite Chips/Pellets
 - ▧ Bentonite Grout
 - ▽ Ground Water Level ATD
 - ▽ Ground Water Level in VWP
 - ◇ % Fines (<0.075mm)
 - % Water Content

- NOTES**
1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
 2. Groundwater level, if indicated above, is for the date specified and may vary.
 3. USCS designation is based on visual-manual classification and selected lab testing.

East-West Corridor Project
 Yakima County, Washington

LOG OF BORING EWC-B-04-14

August 2015 21-1-21630-004

SHANNON & WILSON, INC. **FIG. C-8**
 Geotechnical and Environmental Consultants Sheet 4 of 6

MASTER LOG E 21-21630.GPJ SHAN WIL.GDT 11/13/17 Log: SAW Rev: JKP Typ: CLP

Total Depth: 100.3 ft. Northing: _____ Drilling Method: Sonic Core Hole Diam.: 8 in.
 Top Elevation: ~ 1047 ft. Easting: _____ Drilling Company: Holt Services, Inc. Rod Diam.: _____
 Vert. Datum: _____ Station: _____ Drill Rig Equipment: Terra Sonic Hammer Type: Automatic
 Horiz. Datum: _____ Offset: _____ Other Comments: _____

SOIL DESCRIPTION <i>Refer to the report text for a proper understanding of the subsurface materials and drilling methods. The stratification lines represent the approximate boundaries between material types, and the transition may be gradual.</i>	Depth, ft.	Symbol	PID, ppm	Samples	Ground Water	Depth, ft.	PENETRATION RESISTANCE (blows/foot)			
							▲ Hammer Wt. & Drop: <u>140 lbs / 30 inches</u>			
BOTTOM OF BORING COMPLETED 7/9/2014 Notes: a) Some blow counts are high due to the presence of gravel and cobbles, and do not reflect the relative density of the soil unit. b) Moisture content may be reduced by frictional heating generated during drilling. c) Boulders may be present in alluvium layers.	100.3	●		20		0	20	40	60	50/4"
	102									
	104									
	106									
	108									
	110									
	112									
	114									
	116									
	118									

Log: SAW Rev: JKP Typ: CLP
MASTER LOG E 21-21630.GPJ SHAN WIL.GDT 11/13/17

LEGEND

* Sample Not Recovered		Well Screen and Sand Filter	◇ % Fines (<0.075mm)
Soil Core (as in Sonic Core Borings)		Bentonite-Cement Grout	● % Water Content
2.0" O.D. Split Spoon Sample		Bentonite Chips/Pellets	
		Bentonite Grout	
	▽	Ground Water Level ATD	
	▽	Ground Water Level in VWP	

- NOTES**
1. Refer to KEY for explanation of symbols, codes, abbreviations and definitions.
 2. Groundwater level, if indicated above, is for the date specified and may vary.
 3. USCS designation is based on visual-manual classification and selected lab testing.

East-West Corridor Project Yakima County, Washington	
LOG OF BORING EWC-B-04-14	
August 2015	21-1-21630-004
SHANNON & WILSON, INC. Geotechnical and Environmental Consultants	FIG. C-8 Sheet 6 of 6



LOG OF TEST PIT TP-P1-17

JOB NO: 21-1-22425-002 DATE: 9/27/17 LOCATION: Yakima, WA
 PROJECT: Yakima E-W Corridor

Lat/Long: 46.61396134/-120.4892509

SOIL DESCRIPTION	Ground Water	% Water Content	Samples	Depth, Ft.	Sketch of <u>South</u> Pit Side Horizontal Distance in Feet
Surface: Weeds ① Loose-medium dense, brown, Silty Gravel with Sand and Cobbles (GM); dry; SR-R Gravel and Cobbles, maximum dimension 8"; fine to coarse Sand; no fines; trace fine roots; abundant wood debris Topsoil ② Loose to medium dense, light gray-brown, Silty Gravel with Sand and Cobbles (GM); dry; SR-R Gravel and Cobbles, maximum dimension 8"; fine to coarse Sand; no fines; abundant wood debris. Fill ③ Medium dense, gray-brown, poorly-graded Sand with silt and gravel (SP-SM); moist, SR-R Gravels, maximum dimension 3"; fine to coarse Sand; no fines. Bottom at 8.5'	None Observed		S-1 S-2	0 2 4 6 8 10 12	

FIG. C-9

Table C-1: Summary of Pilot Infiltration Test Results

Project Stage	PIT ID	Test Date	Test Pit Dimensions (ft)			Average Flow Rate (gpm)	Short-Term Infiltration (in/hr)			Correction Factors			Total Correction Factors	Long-Term Design Infiltration (in/hr)
			Length	Width	Depth		Constant Head Test	Falling Head Test	Average	CF _v	CF _t	CF _m	CF _T = CF _v x CF _t x CF _m	Rate = CF _T x Ksat
Stage 3	TP-P1a-17	9/27/2017	5	7	8.5	340	53	50	51	0.7	0.5	0.7	0.25	13

NOTES:

CF_v = site variability and number of locations tested; CF_t = uncertainty of test method; CF_m = degree of influent control to prevent siltation and biological buildup; CF_T = total correction factor; ft = feet
 gpm = gallons per minute; in/hr = inches per hour; N/A = not applicable; Ksat = saturated hydraulic conductivity; PIT = pilot infiltration tests

Table C-2: Summary of Grain-Size Analysis Infiltration Correlations

Test Pit Designation and Sample	Depth of Sample (ft bgs)	D ₁₀ (mm)	D ₆₀ (mm)	D ₉₀ (mm)	ffines	(cm/sec)	(in/hr)	Correction Factors			Total Correction Factors	Long-Term Design Infiltration (in/hr)
								CF _v	CF _t	CF _m	CF _T = CF _v x CF _t x CF _m	Rate = CF _T x Ksat
TP-P1-17*	4	0.04	0.339	11.53	19.2	9.20E-03	13	0.7	0.4	0.7	0.20	2.5
TP-P1-17	8.5	0.096	0.353	0.757	6.962	2.90E-02	14	0.7	0.4	0.7	0.20	8
TP-P1-17 Average Infiltration Rate												5

NOTES:


* D10 estimated based on grain-size distribution curve.

CF_v = site variability and number of locations tested; CF_t = uncertainty of test method; CF_m = degree of influent control to prevent siltation and biological buildup; CF_T = total correction factor; cm/sec = centimeters per second; D₁₀, D₆₀, D₉₀ = grain size that corresponds to 10, 60, and 90% of the sample that is more fine; ffines = % by weight of fines (materials passing No. 200 sieve); ft bgs = feet below ground surface; in/hr = inches per hour; Ksat = saturated hydraulic conductivity; mm = millimeter

East-West Corridor Project
 Stage 3
 Yakima, Washington

BORING B-1-17

Gravel		Sand			Fines	
Coarse	Fine	Coarse	Medium	Fine	Silt	Clay-Size
Mesh Opening in Inches		Mesh Openings per Inch, U.S. Standard			Grain Size in Millimeters	



Sample Identification	Depth (ft)	USCS Group Symbol	USCS Group Name	Cobbles %	Gravel %	Sand %	Fines %	< 20µm %	< 2µm %	WC %	Tested By	Review By	ASTM Std.
● B-1-17, R-2'	8.0	GW-GM	Well-Graded Gravel with Silt and Sand		66	28	6.5			2.8	SAB		C136
■ B-1-17, R-4'	18.0	GW-GM	Well-Graded Gravel with Silt and Sand		64	29	7.4			3.8	SAB		C136
▲ B-1-17, R-6'	28.0	GW-GM	Well-Graded Gravel with Silt and Sand and Cobbles	16	55	23	6.3			2.9	SAB		C136
◆ B-1-17, R-7'	33.0	GP-GM	Poorly Graded Gravel with Silt and Sand		64	26	9.8			3.9	SAB		C136
○ B-1-17, R-12'	56.0	GM	Silty Gravel with Sand		61	28	12			8.7	SAB		C136
□ B-1-17, R-20'	98.0	GM	Silty Gravel with Sand		58	28	13			7.1	SAB		C136

¹ Test specimen did not meet minimum mass recommendations.


² Cobble percentages are calculated using the pre-removal, oven-dried mass of the total specimen. USCS Group Symbol, Soil Classification Group Name, Gravel %, Sand %, Fines %, <0.02mm %, <2µm %, Cu, and Cc values are calculated from particles smaller than 76.2mm (3 inches) only, per ASTM D2487.

21-1-22425-002 A_GSA_MAIN 21-22425.GPJ_SHAN_WIL_GDT 12/10/19

East-West Corridor Project
 Stage 3
 Yakima, Washington

BORING B-2-17

Gravel		Sand			Fines	
Coarse	Fine	Coarse	Medium	Fine	Silt & Clay-Size	
Mesh Opening in Inches		Mesh Openings per Inch, U.S. Standard			Grain Size in Millimeters	




Sample Identification	Depth (ft)	USCS Group Symbol	USCS Group Name	Gravel %	Sand %	Fines %	< 20µm %	< 2µm %	WC %	Tested By	Review By	ASTM Std.
● B-2-17, R-3 [*]	13.0	GP	Poorly Graded Gravel	83	14	2.7			1.6	SAB		C136
■ B-2-17, R-5 [*]	20.0	SW-SM	Well-Graded Sand with Silt and Gravel	19	71	9.7			12.3	SAB		C136
▲ B-2-17, R-7 [*]	30.0	GW-GM	Well-Graded Gravel with Silt and Sand	62	31	6.8			8.0	SAB		C136

^{*} Test specimen did not meet minimum mass recommendations.

21-1-22425-002 A_GSA_MAIN 21-22425.GPJ_SHAN_WIL_GDT 12/10/19

East-West Corridor Project
 Stage 3
 Yakima, Washington

BORING B-3-18
 Sheet 1 of 2



Sample Identification	Depth (ft)	USCS Group Symbol	USCS Group Name	Cobbles %	Gravel %	Sand %	Fines %	< 20µm %	< 2µm %	WC %	Tested By	Review By	ASTM Std.
● B-3-18, R-2 [*]	7.0	GP-GM	Poorly Graded Gravel with Silt and Sand and Cobbles	8	68	18	6.3			3.2	AKV	JFL	C136
■ B-3-18, R-4 [*]	17.0	GP-GM	Poorly Graded Gravel with Silt and Sand				5.3			6.1	AKV	JFL	D1140
▲ B-3-18, R-6 [*]	26.0	GP-GM	Poorly Graded Gravel with Silt and Sand				6.3			5.3	AKV	JFL	D1140
◆ B-3-18, R-8 [*]	36.0	GM	Silty Gravel with Sand		63	24	14			7.2	AKV	JFL	C136
○ B-3-18, R-10 [*]	47.5	GP-GM	Poorly Graded Gravel with Silt and Sand				9.5			5.7	AKV	JFL	D1140
□ B-3-18, R-12 [*]	56.0	GM	Silty Gravel with Sand				17			7.8	AKV	JFL	D1140
△ B-3-18, R-14 [*]	67.5	GM	Silty Gravel with Sand		56	24	20			6.6	AKV	JFL	C136
◇ B-3-18, R-16 [*]	76.0	SM	Silty Sand with Gravel				13			18.0	AKV	JFL	D1140
▲ B-3-18, R-17 [*]	82.5	GM	Silty Gravel with Sand				26			6.4	AKV	JFL	D1140
★ B-3-18, R-19 [*]	92.5	GP-GM	Poorly Graded Gravel with Silt and Sand and Cobbles	30	49	13	7.5			6.1	AKV	JFL	C136

^{*} Test specimen did not meet minimum mass recommendations.


² Cobble percentages are calculated using the pre-removal, oven-dried mass of the total specimen. USCS Group Symbol, Soil Classification Group Name, Gravel %, Sand %, Fines %, <0.02mm %, <2µm %, Cu, and Cc values are calculated from particles smaller than 76.2mm (3 inches) only, per ASTM D2487.

21-1-22425-002 A_GSA_MAIN 21-22425.GPJ_SHAN_WIL_GDT 12/10/19

East-West Corridor Project
 Stage 3
 Yakima, Washington

BORING B-3-18
 Sheet 2 of 2

Gravel		Sand			Fines	
Coarse	Fine	Coarse	Medium	Fine	Silt	
Mesh Opening in Inches		Mesh Openings per Inch, U.S. Standard			Grain Size in Millimeters	
					Clay-Size	



Sample Identification	Depth (ft)	USCS Group Symbol	USCS Group Name	Cobbles %	Gravel %	Sand %	Fines %	< 20µm %	< 2µm %	WC %	Tested By	Review By	ASTM Std.
● B-3-18, R-21 ¹	102.5	GM	Silty Gravel with Sand				14			10.2	AKV	JFL	D1140
■ B-3-18, R-22 ¹	107.5	GM	Silty Gravel with Sand				14			8.0	AKV	JFL	D1140
▲ B-3-18, R-25 ¹	122.5	GM	Silty Gravel with Sand and Cobbles	4	53	27	17			7.5	AKV	JFL	C136

¹ Test specimen did not meet minimum mass recommendations.


² Cobble percentages are calculated using the pre-removal, oven-dried mass of the total specimen. USCS Group Symbol, Soil Classification Group Name, Gravel %, Sand %, Fines %, <0.02mm %, <2µm%, Cu, and Cc values are calculated from particles smaller than 76.2mm (3 inches) only, per ASTM D2487.

21-1-22425-002 A_GSA_MAIN 21-22425.GPJ SHAN_WIL_GDT 12/10/19

East-West Corridor Project
 Stage 3
 Yakima, Washington

TEST PIT TP-P1-17


Gravel		Sand			Fines	
Coarse	Fine	Coarse	Medium	Fine	Silt & Clay-Size	
Mesh Opening in Inches		Mesh Openings per Inch, U.S. Standard			Grain Size in Millimeters	



Sample Identification	Depth (ft)	USCS Group Symbol	USCS Group Name	Gravel %	Sand %	Fines %	< 20µm %	< 2µm %	WC %	Tested By	Review By	ASTM Std.
● TP-P1-17, S-1*	4.0	SM	Silty Sand with Gravel	15	65	19			22.6	SAB		C136
■ TP-P1-17, S-2*	8.5	SP-SM	Poorly Graded Sand with Silt	6	87	7.0			9.5	SAB		C136

* Test specimen did not meet minimum mass recommendations.

SIEVE ANALYSIS		HYDROMETER ANALYSIS	
SIZE OF MESH OPENING IN INCHES	NO. OF MESH OPENINGS PER INCH, U.S. STANDARD	GRAIN SIZE IN MILLIMETERS	



COARSE	FINE	COARSE	MEDIUM	FINE	FINES: SILT OR CLAY
GRAVEL		SAND			

LEGEND

- USCS:** Unified Soil Classification System
- COBBLE %:** Percentage of cobbles in test specimen; based on pre-removal total dry mass for normalized tests
- NAT WC %:** Natural water content
- Cu:** Coefficient of uniformity
- Cc:** Coefficient of curvature
- ASTM DES:** ASTM International test standard designation

*: Sample specimen weight did not meet required minimum mass for ASTM test method.

USCS Group Symbol, Soil Classification Group Name, Gravel %, Sand %, Fines %, <0.02mm %, <2um%, Cu, and Cc values are calculated from particles smaller than 76.2mm (3 inches) only, per ASTM D2487.

BORING AND SAMPLE NO.	DEPTH (feet)	USCS GROUP SYMBOL	USCS GROUP NAME	COBBLE %	GRAVEL %	SAND %	FINES %	< 0.02mm %	< 2um %	NAT WC %	Cu	Cc	TEST BY	REVIEW BY	ASTM DES
● EWC-B-01-14, R-4*	17.0	GP	Poorly Graded Gravel with Sand		62	35	3.7			4.6	64.7	0.7	SXL	JFL	C136
■ EWC-B-01-14, R-6*	26.7	GM	Silty Gravel with Sand		51	37	12	7	2	9.3	204.4	0.3	SXL	JFL	D422
▲ EWC-B-01-14, R-8*	38.5	GM	Silty Gravel with Sand		50	32	17	9	2	8.2			SXL	JFL	D422
◆ EWC-B-01-14, R-12*	56.7	GP-GM	Poorly Graded Gravel with Silt and Sand		52	40	7.9			12.0	84.9	0.3	SXL	JFL	C136
○ EWC-B-01-14, R-18*	85.8	GM	Silty Gravel with Sand and Cobbles	19	45	31	23			7.9			SXL	JFL	C136
□ EWC-B-01-14, R-20*	95.8	GM	Silty Gravel with Sand		63	19	18			6.0			SXL	JFL	C136

East-West Corridor Project
Yakima County, Washington


**GRAIN SIZE DISTRIBUTION
BORING EWC-B-01-14**

August 2015 21-1-21630-004

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

Sheet 1 of 1

SIEVE ANALYSIS		HYDROMETER ANALYSIS	
SIZE OF MESH OPENING IN INCHES	NO. OF MESH OPENINGS PER INCH, U.S. STANDARD	GRAIN SIZE IN MILLIMETERS	



COARSE	FINE	COARSE	MEDIUM	FINE	FINES: SILT OR CLAY
GRAVEL		SAND			

- LEGEND**
- USCS:** Unified Soil Classification System
 - COBBLE %:** Percentage of cobbles in test specimen; based on pre-removal total dry mass for normalized tests
 - NAT WC %:** Natural water content
 - Cu:** Coefficient of uniformity
 - Cc:** Coefficient of curvature
 - ASTM DES:** ASTM International test standard designation

**: Sample specimen weight did not meet required minimum mass for ASTM test method.*

USCS Group Symbol, Soil Classification Group Name, Gravel %, Sand %, Fines %, <0.02mm %, <2um%, Cu, and Cc values are calculated from particles smaller than 76.2mm (3 inches) only, per ASTM D2487.

BORING AND SAMPLE NO.	DEPTH (feet)	USCS GROUP SYMBOL	USCS GROUP NAME	COBBLE %	GRAVEL %	SAND %	FINES %	< 0.02mm %	< 2um %	NAT WC %	Cu	Cc	TEST BY	REVIEW BY	ASTM DES
● EWC-B-02-14, R-2*	8.5	GP	Poorly Graded Gravel		84	12	4.6			1.0	50.1	8.7	RXG	JFL	D422
■ EWC-B-02-14, R-3*	11.8	GM	Silty Gravel with Sand		59	28	13			4.1			RXG	JFL	D422
▲ EWC-B-02-14, S-3	15.0	SM	Silty Sand		2	85	13			19.3			RXG	JFL	D422
◆ EWC-B-02-14, R-4*	17.5	GP	Poorly Graded Gravel with Sand		71	24	4.9			5.2	39.5	3.2	RXG	JFL	D422
○ EWC-B-02-14, S-4	20.0	SM	Silty Sand		0	87	13			21.1			RXG	JFL	D422
□ EWC-B-02-14, S-7	35.0	SM	Silty Sand		5	75	20			29.0			RXG	JFL	D422
△ EWC-B-02-14, R-9*	43.5	SP-SM	Poorly Graded Sand with Silt and Gravel		44	46	10	5	2	14.6	119.3	0.2	SXL	JFL	D422

East-West Corridor Project
Yakima County, Washington


**GRAIN SIZE DISTRIBUTION
BORING EWC-B-02-14**

August 2015 21-1-21630-004

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

Sheet 1 of 2

SIEVE ANALYSIS		HYDROMETER ANALYSIS	
SIZE OF MESH OPENING IN INCHES	NO. OF MESH OPENINGS PER INCH, U.S. STANDARD	GRAIN SIZE IN MILLIMETERS	



COARSE		FINE		COARSE		MEDIUM		FINE		FINES: SILT OR CLAY				
GRAVEL				SAND										

- LEGEND**
- USCS:** Unified Soil Classification System
 - COBBLE %:** Percentage of cobbles in test specimen; based on pre-removal total dry mass for normalized tests
 - NAT WC %:** Natural water content
 - Cu:** Coefficient of uniformity
 - Cc:** Coefficient of curvature
 - ASTM DES:** ASTM International test standard designation

*: Sample specimen weight did not meet required minimum mass for ASTM test method.

USCS Group Symbol, Soil Classification Group Name, Gravel %, Sand %, Fines %, <0.02mm %, <2um%, Cu, and Cc values are calculated from particles smaller than 76.2mm (3 inches) only, per ASTM D2487.

BORING AND SAMPLE NO.	DEPTH (feet)	USCS GROUP SYMBOL	USCS GROUP NAME	COBBLE %	GRAVEL %	SAND %	FINES %	< 0.02mm %	< 2um %	NAT WC %	Cu	Cc	TEST BY	REVIEW BY	ASTM DES
● EWC-B-02-14, R-12*	59.0	GP-GM	Poorly Graded Gravel with Silt and Sand		74	17	9.6	7	3	13.3	239.0	18.3	SXL	JFL	D422
■ EWC-B-02-14, R-14*	68.0	GW-GM	Well-Graded Gravel with Silt and Sand		54	37	9.1	6	1	6.9	74.8	2.9	SXL	JFL	D422
▲ EWC-B-02-14, R-16*	78.0	SM	Silty Sand with Gravel		20	40	40			9.3			RXG	JFL	D422
◆ EWC-B-02-14, R-18*	88.0	GM	Silty Gravel with Sand		68	18	14			13.2			RXG	JFL	D422

East-West Corridor Project
Yakima County, Washington


**GRAIN SIZE DISTRIBUTION
BORING EWC-B-02-14**

August 2015 21-1-21630-004

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

Sheet 2 of 2

SIEVE ANALYSIS		HYDROMETER ANALYSIS	
SIZE OF MESH OPENING IN INCHES	NO. OF MESH OPENINGS PER INCH, U.S. STANDARD	GRAIN SIZE IN MILLIMETERS	



COARSE	FINE	COARSE	MEDIUM	FINE	FINES: SILT OR CLAY	
GRAVEL		SAND				

- LEGEND**
- USCS:** Unified Soil Classification System
 - COBBLE %:** Percentage of cobbles in test specimen; based on pre-removal total dry mass for normalized tests
 - NAT WC %:** Natural water content
 - Cu:** Coefficient of uniformity
 - Cc:** Coefficient of curvature
 - ASTM DES:** ASTM International test standard designation

**: Sample specimen weight did not meet required minimum mass for ASTM test method.*

USCS Group Symbol, Soil Classification Group Name, Gravel %, Sand %, Fines %, <0.02mm %, <2um%, Cu, and Cc values are calculated from particles smaller than 76.2mm (3 inches) only, per ASTM D2487.

BORING AND SAMPLE NO.	DEPTH (feet)	USCS GROUP SYMBOL	USCS GROUP NAME	COBBLE %	GRAVEL %	SAND %	FINES %	< 0.02mm %	< 2um %	NAT WC %	Cu	Cc	TEST BY	REVIEW BY	ASTM DES
● EWC-B-03-14, R-2*	8.0	GW	Well-Graded Gravel with Sand		70	26	3.6			2.0	55.4	1.3	RXG	JFL	D422
■ EWC-B-03-14, S-3*	15.5	GP-GM	Poorly Graded Gravel with Silt and Sand		56	33	11			7.2	141.7	4.9	RXG	JFL	D422
▲ EWC-B-03-14, R-5*	22.5	GW	Well-Graded Gravel		92	6	2.5			4.7	5.1	1.9	RXG	JFL	D422
◆ EWC-B-03-14, S-6*	30.0	SP	Poorly Graded Sand		2	94	3.9			16.0	3.7	1.1	SXL	JFL	D422
○ EWC-B-03-14, R-7*	33.3	GP	Poorly Graded Gravel with Sand		73	23	4.2			6.1	27.3	4.1	RXG	JFL	D422
□ EWC-B-03-14, S-9*	46.3	GP	Poorly Graded Gravel with Sand		71	25	4.1	2	1	34.1	21.7	3.7	SXL	JFL	D422
△ EWC-B-03-14, S-11*	55.6	GW	Well-Graded Gravel with Sand		69	28	2.5			3.5	26.2	2.8	SXL	JFL	D422

East-West Corridor Project
Yakima County, Washington


**GRAIN SIZE DISTRIBUTION
BORING EWC-B-03-14**

August 2015 21-1-21630-004

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

Sheet 1 of 2

SIEVE ANALYSIS		HYDROMETER ANALYSIS	
SIZE OF MESH OPENING IN INCHES	NO. OF MESH OPENINGS PER INCH, U.S. STANDARD	GRAIN SIZE IN MILLIMETERS	



COARSE	FINE	COARSE	MEDIUM	FINE	
GRAVEL		SAND			FINES: SILT OR CLAY

LEGEND

USCS: Unified Soil Classification System

COBBLE %: Percentage of cobbles in test specimen; based on pre-removal total dry mass for normalized tests

NAT WC %: Natural water content

Cu: Coefficient of uniformity

Cc: Coefficient of curvature

ASTM DES: ASTM International test standard designation

**: Sample specimen weight did not meet required minimum mass for ASTM test method.*

USCS Group Symbol, Soil Classification Group Name, Gravel %, Sand %, Fines %, <0.02mm %, <2um%, Cu, and Cc values are calculated from particles smaller than 76.2mm (3 inches) only, per ASTM D2487.

BORING AND SAMPLE NO.	DEPTH (feet)	USCS GROUP SYMBOL	USCS GROUP NAME	COBBLE %	GRAVEL %	SAND %	FINES %	< 0.02mm %	< 2um %	NAT WC %	Cu	Cc	TEST BY	REVIEW BY	ASTM DES
● EWC-B-03-14, R-18*	85.5	GP-GM	Poorly Graded Gravel with Silt and Sand		66	23	11	7	2	7.2	235.3	15.4	SXL	JFL	D422
■ EWC-B-03-14, R-19*	94.1	GM	Silty Gravel with Sand		58	26	16			9.8			RXG	JFL	D422


East-West Corridor Project
Yakima County, Washington

**GRAIN SIZE DISTRIBUTION
BORING EWC-B-03-14**

August 2015 21-1-21630-004

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

Sheet 2 of 2



BORING AND SAMPLE NO.	DEPTH (feet)	USCS GROUP SYMBOL	USCS GROUP NAME	COBBLE %	GRAVEL %	SAND %	FINES %	< 0.02mm %	< 2um %	NAT WC %	Cu	Cc	TEST BY	REVIEW BY	ASTM DES
● EWC-B-04-14, R-1*	3.5	GW-GM	Well-Graded Gravel with Silt and Sand		61	30	8.9			1.2	169.7	1.7	AKV	JFL	D422
■ EWC-B-04-14, R-5*	22.5	GP	Poorly Graded Gravel with Sand		70	26	3.4			10.2	69.6	3.1	AKV	JFL	D422
▲ EWC-B-04-14, R-6*	28.5	GW	Well-Graded Gravel with Sand		69	28	3.3			8.9	34.0	1.3	AKV	JFL	D422
◆ EWC-B-04-14, R-8*	37.5	GW-GM	Well-Graded Gravel with Silt and Sand		59	33	7.2			11.0	57.4	1.4	RXG	JFL	D422
○ EWC-B-04-14, R-8*	38.4	GP-GM	Poorly Graded Gravel with Silt and Sand				100			11.2			AKV	JFL	D1140
□ EWC-B-04-14, R-9*	42.0	GM	Silty Gravel with Sand		53	29	18	11	4	11.0			SXL	JFL	D422
△ EWC-B-04-14, R-11*	54.5	GM	Silty Gravel with Sand		56	28	17			11.0			RXG	JFL	D422

East-West Corridor Project
Yakima County, Washington


**GRAIN SIZE DISTRIBUTION
BORING EWC-B-04-14**

August 2015 21-1-21630-004

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

Sheet 1 of 2

SIEVE ANALYSIS		HYDROMETER ANALYSIS	
SIZE OF MESH OPENING IN INCHES	NO. OF MESH OPENINGS PER INCH, U.S. STANDARD	GRAIN SIZE IN MILLIMETERS	



COARSE	FINE	COARSE	MEDIUM	FINE	FINES: SILT OR CLAY		
GRAVEL		SAND					

- LEGEND**
- USCS:** Unified Soil Classification System
 - COBBLE %:** Percentage of cobbles in test specimen; based on pre-removal total dry mass for normalized tests
 - NAT WC %:** Natural water content
 - Cu:** Coefficient of uniformity
 - Cc:** Coefficient of curvature
 - ASTM DES:** ASTM International test standard designation

**: Sample specimen weight did not meet required minimum mass for ASTM test method.*

USCS Group Symbol, Soil Classification Group Name, Gravel %, Sand %, Fines %, <0.02mm %, <2um%, Cu, and Cc values are calculated from particles smaller than 76.2mm (3 inches) only, per ASTM D2487.

BORING AND SAMPLE NO.	DEPTH (feet)	USCS GROUP SYMBOL	USCS GROUP NAME	COBBLE %	GRAVEL %	SAND %	FINES %	< 0.02mm %	< 2um %	NAT WC %	Cu	Cc	TEST BY	REVIEW BY	ASTM DES
● EWC-B-04-14, R-14*	65.5	GC	Clayey Gravel with Sand		36	34	30			11.5			RXG	JFL	D422
■ EWC-B-04-14, R-16*	78.0	GP-GM	Poorly Graded Gravel with Silt and Sand		58	33	9.0	5	1	8.9	97.6	3.3	SXL	JFL	D422
▲ EWC-B-04-14, R-19*	92.5	GP-GM	Poorly Graded Gravel with Silt and Sand		54	40	6.0			9.6	46.3	0.6	RXG	JFL	D422
◆ EWC-B-04-14, R-20*	99.0	GM	Silty Gravel with Sand		38	28	34			13.5			RXG	JFL	D422

East-West Corridor Project
Yakima County, Washington

GRAIN SIZE DISTRIBUTION
BORING EWC-B-04-14

August 2015 21-1-21630-004

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

Sheet 2 of 2

Appendix D

Environmental Procedures and Testing Results

CONTENTS

D.1 GENERAL D-1

D.2 2021 ENVIRONMENTAL TESTING D-1

 D.2.1 Soil Sampling Activities D-1

 D.2.2 Analytical Methods D-2

 D.2.3 Analytical Results D-2

 D.2.4 Investigation-Derived Waste D-3

D.3 2017 ENVIRONMENTAL TESTING D-3

 D.3.1 Soil Sampling Activities D-3

 D.3.2 Analytical Methods D-4

 D.3.3 Analytical Results D-4

 D.3.4 Investigation-Derived Waste D-5

D.4 2014 ENVIRONMENTAL TESTING D-6

 D.4.1 Soil Sampling Activities D-6

 D.4.2 Analytical Methods D-6

 D.4.3 Analytical Results D-7

 D.4.4 Investigation-Derived Waste D-7

D.5 REFERENCES D-8

Exhibits

Exhibit D-1: 2021 Fremont Analytical Reports D-2

Exhibit D-2: 2017 Fremont Analytical Report Reference Numbers D-5

Exhibit D-3: 2014 Fremont Analytical Reports D-7

Tables

- Table D-1: Summary of 2021 Analytical Testing Data
- Table D-2: Summary of 2017 Analytical Testing Data (2 pages)
- Table D-3: Summary of 2014 Analytical Testing Data (2 pages)
- Table D-4: Summary of Adjusted Toxicity Equivalence Factor Concentrations (6 pages)

Report Compilation Attachments

- 2021 Fremont Analytical Reports (127 pages)
- 2017 Fremont Analytical Reports (127 pages)
- 2014 Fremont Analytical Reports (83 pages)

D.1 GENERAL

This appendix presents the results of our environmental laboratory testing analyses for the Cascade Mill Parkway Phase 3 project. We also performed two previous sets of environmental testing: one in 2014 for the 30% design study and one in 2017 for the East-West Corridor Stage 3 design study.

D.2 2021 ENVIRONMENTAL TESTING

D.2.1 Soil Sampling Activities

Soil samples were collected from borings B-09-21, B-10-21, B-11P-21, B-13-21, B-14-21, and B-15P-21 for health and safety and waste characterization purposes.

No visual or olfactory signs of contamination were observed during drilling. Wood fragments were noted within borings B-09-21, B-10-21, and B-12-21 at depths of approximately 19, 42, and 45 feet below ground surface (bgs) in B-09-21, 10 feet bgs in B-10-21, and 36 feet bgs in B-12-21.

Soil samples were screened for the potential presence of contamination using a photoionization detector (PID) and visual and olfactory observations. PID readings ranged from 0.3 part per million (ppm) to 5.5 ppm during drilling. Elevated PID readings of 12.4 and 48 ppm were measured in boring B-09-21 and of 47 ppm measured in boring B-10-21. The elevated readings measured in both borings B-09-21 and B-10-21 may have been associated with the presence of rock dust. The dust may have impacted the PID filter and lamp bulb, which potentially could have led to erroneous readings. Field screening results are noted in the boring logs (Appendix A).

Up to two samples were collected from each boring. Samples were collected at depths where field indication potentially identified the presence of contamination. In borings where no field indication of contamination was observed, samples were collected near the groundwater interface.

Soil samples were collected using disposable sampling equipment. The samples were collected by donning a pair of disposable nitrile gloves. Each sample was collected within clean, laboratory-supplied glassware using disposable stainless-steel spoons or laboratory-provided plungers (for U.S. Environmental Protection Agency [EPA] Method 5035). The sample container labels were completed using indelible ink. The sample jars were sealed in plastic bags, and then placed into a cooler with "blue ice." Samples were transported by a

Shannon & Wilson field representative to Fremont Analytical, of Seattle, Washington, under chain-of-custody procedures.

D.2.2 Analytical Methods

Soil samples were submitted to Fremont Analytical for the following analyses:

- Gasoline-range hydrocarbons by Method Northwest Total Petroleum Hydrocarbons – Gasoline
- Diesel- and lube-oil-range hydrocarbons by Method Northwest Total Petroleum Hydrocarbons as Diesel Extended
- Benzene, toluene, ethylbenzene, and xylenes (BTEX) by EPA Method 8260C
- Resource Conservation and Recovery Act metals (arsenic, barium, cadmium, chromium, lead, mercury, selenium, and silver) by EPA Method 6020A/7471B
- Polycyclic aromatic hydrocarbons (PAHs) by EPA Method 8270DSIM
- Pentachlorophenol (Herbicide) by EPA Method 8151A

Samples were analyzed within specified holding times.

D.2.3 Analytical Results

In April 2022, ten soil samples were collected from the Stage 3 segment geotechnical to support investigation-derived waste (IDW) characterization and provide information for health and safety purposes. The analytical results of the collected samples are summarized in Table D-1. Copies of the analytical laboratory reports are included in this appendix. Dates and reference numbers for these reports are summarized in the following Exhibit D-1:

Exhibit D-1: 2021 Fremont Analytical Reports

Date	Fremont Analytical Laboratory Reference Number	Pages
4/29/2022	2104132	39 pages
4/09/2022	2104041	22 pages
4/07/2022	2103484	25 pages
4/29/2022	2104312	21 pages

No gasoline-range and diesel-range petroleum hydrocarbons were detected above laboratory reporting limits in any of the samples analyzed with the exception of the 15.5-foot sample collected in boring B-10. Gasoline range organics (GRO) with a similar pattern to mineral spirits was detected at a concentration 1,030 milligrams per kilogram (mg/kg). This detected GRO concentration exceeds the Washington State Department of Ecology (Ecology) Model Toxics Control Act (MTCA) Method A soil cleanup level for

unrestricted land use of 100 mg/kg when benzene is not present (Ecology, 2013). Heavy oil-range petroleum hydrocarbons were also detected in the same sample at a concentration of 1,120 mg/kg. The detected concentration does not exceed the MTCA Method A soil cleanup level for unrestricted land use of 2,000 mg/kg. The source of this contamination is unknown.

Several metals, including arsenic, barium, chromium, lead and selenium, were detected in each of the samples analyzed. The detected concentrations are compared to MTCA Method A cleanup levels. Where no Method A level is established, the concentrations are compared to Method B cleanup levels for direct contact. All the metals detected concentrations were below available MTCA cleanup levels. The chromium analysis does not determine if the chromium present is either trivalent or hexavalent chromium. Based on the available site history, hexavalent chromium is not considered likely. The detected concentrations are below cleanup levels for trivalent chromium.

All the detected metals concentrations, with the exception of selenium, were detected within naturally background concentrations for metals in Eastern Washington as identified in the Natural Background Soil Metals Concentrations in Washington State study prepared by Ecology in 1994 (Ecology, 1994). Detected selenium concentrations were present above the established background level of 0.78 mg/kg. It should be noted that the selenium background level established within the study was considered to be an estimate.

No PAHs, BTEX, or pentachlorophenol were detected above laboratory reporting limits within any of the samples collected and analyzed.

D.2.4 Investigation-Derived Waste

IDW generated during these field activities consisted of boring cuttings and drilling mud. IDW was placed in 55-gallon drums and temporarily stored at the Yakima County Equipment Services Yard pending laboratory analyses. Disposable sampling equipment was disposed as solid waste. The IDW was removed from the County Yard by Advanced Chemical Transport of San Jose, California, under subcontract to Shannon & Wilson, on July 13 and 26, 2021. The IDW was disposed at U.S. Ecology Landfill of Grandview, Idaho, on July 26, 2021.

D.3 2017 ENVIRONMENTAL TESTING

D.3.1 Soil Sampling Activities

Soil samples were collected from borings B-1-17 and B-2-17 for environmental characterization. No visual or olfactory signs of contamination were observed. Wood waste

was noted within boring B-2-17 from depths of approximately 1 to 10 feet below ground surface. Four samples were taken from each boring. Samples taken from boring B-1-17 were identified as ES-1 through ES-4. Samples taken from boring B-2-17 were identified as ES-5 through ES-8. From each boring, samples included a near-surface sample, a sample from above the groundwater table, a sample from the water table, and a sample from below the water table.

Soil samples were collected using disposable sampling equipment. Soil samples were collected by donning a pair of disposable nitrile gloves. Samples were collected within clean, laboratory-supplied glassware using disposable stainless-steel spoons or laboratory-provided plungers (for EPA Method 5035). The sample container labels were completed using indelible ink. The samples were sealed in plastic bags, and then placed into a cooler with "blue ice." Samples were transported by a Shannon & Wilson field representative to Fremont Analytical, of Seattle, Washington, under chain-of-custody procedures.

D.3.2 Analytical Methods

Soil samples were submitted to Fremont Analytical for the following analyses:

- Gasoline-range hydrocarbons by Method Northwest Total Petroleum Hydrocarbons – Gasoline
- Diesel- and lube-oil-range hydrocarbons by Method Northwest Total Petroleum Hydrocarbons as Diesel Extended
- Volatile organic compounds (VOCs) by EPA Method 8260C
- Resource Conservation and Recovery Act metals (arsenic, barium, cadmium, chromium, lead, mercury, selenium, and silver) and additional metals (copper, nickel, and zinc) by EPA Method 6020A/7471B
- PAHs by EPA Method 8270DSIM
- Polychlorinated biphenyls (PCBs) by EPA Method 8082
- Organochlorine pesticides by EPA Method 8081A
- Herbicides by EPA Method 8151A

Samples were analyzed within specified holding times.

D.3.3 Analytical Results

Analytical results for the Stage 3 area borings are summarized in Table D-1 and the associated analytical laboratory reports are included in this appendix. Dates and reference numbers for these reports are summarized in the following Exhibit D-2:

Exhibit D-2: 2017 Fremont Analytical Report Reference Numbers

Date	Fremont Analytical Laboratory Reference Number	Pages
8/14/2017	1707301	61 pages
8/14/2017	1708051	66 pages

Gasoline-range and diesel-range petroleum hydrocarbons were not detected above laboratory reporting limits within any of the analyzed samples. One sample (ES-6) contained petroleum hydrocarbons within the lube-oil range at a concentration of 495 mg/kg, below MTCA Method A soil cleanup level for unrestricted land use. The same sample also contained toluene, 1,2,3-trichlorobenzene, and 1,2,4-trichlorobenzene at concentrations below cleanup levels. VOCs were not detected within any of the other samples. It should be noted that sample ES-6 was taken from within the wood waste layer observed within boring B-2-17.

Several metals were detected within the samples. Concentrations were compared to MTCA Method A cleanup levels and Method B cleanup levels for direct contact. Arsenic, barium, lead, copper, nickel, and zinc were detected within all samples at concentrations below cleanup levels. Cadmium was detected within one soil sample, ES-5, at a concentration below the MTCA Method A cleanup level. Selenium was detected within all but one soil sample at concentrations below the cleanup level. Chromium was detected within all samples. Based on the known site history, hexavalent chromium is not considered likely. The detected concentrations are below cleanup levels for trivalent chromium.

With minor exceptions, all metals were detected within background concentrations for Eastern Washington. The copper, nickel, and zinc concentrations detected within sample ES-5 were above typical background concentrations, but below cleanup levels. The nickel concentration measured within sample ES-1 was also above typical background levels, but below cleanup levels. Samples ES-1 and ES-5 were both taken from near-surface depths. Selenium was detected at concentrations above the established background level of 0.78 mg/kg. It should be noted that the selenium background level established within the study was considered to be an estimate. Other sources suggest that selenium concentrations ranging between 0.01 to 2.0 mg/kg are typical of surficial soils.

PAHs, PCBs, organochlorine pesticides, and herbicides were not detected above laboratory reporting limits within any of the analyzed samples.

D.3.4 Investigation-Derived Waste

IDW generated during these field activities was removed from the site by the driller.

D.4 2014 ENVIRONMENTAL TESTING

D.4.1 Soil Sampling Activities

Soil samples were screened for the potential presence of contamination using a PID and visual and olfactory observations. PID readings were recorded at 8.7 and 13.7 ppm in the landfill material encountered in boring EWC-B-01-14. These readings are likely due to the presence of landfill debris consisting of municipal solid waste observed generally in the upper 15 feet. A slight hydrocarbon odor was also observed in the landfill material retrieved from boring EWC-B-01-14. Field screening results are noted in the boring logs (Appendix A).

Soil samples were collected from selected explorations for waste characterization purposes. In borings where no field indication of contamination was observed, samples were collected near the groundwater interface; the samples in the test pits were generally collected at the bottom of the excavation.

Soil samples were collected using disposable sampling equipment. Soil samples were collected by donning a pair of disposable nitrile gloves. At least one laboratory-supplied 8-ounce jar was filled using disposable stainless-steel spoons, and two clean, laboratory-supplied 40-millimeter vials in accordance with EPA Method 5035. The sample container labels were completed using indelible ink. The samples were sealed in plastic bags, and then placed into a cooler and maintained at 4 degrees Celsius ($^{\circ}\text{C}$) ($\pm 2^{\circ}\text{C}$) with "blue ice." Samples were transported by a Shannon & Wilson field representative to Fremont Analytical of Seattle, Washington, under chain-of-custody procedures.

D.4.2 Analytical Methods

Soil samples were submitted to Fremont Analytical for the following analyses:

- Gasoline-range hydrocarbons by Method Northwest Total Petroleum Hydrocarbons-Gasoline with benzene, toluene, ethylbenzene, and xylenes distinction
- Diesel- and lube-oil-range hydrocarbons by Method Northwest Total Petroleum Hydrocarbons as Diesel Extended with acid/silica gel cleanup
- PAHs EPA Method 8270DSIM
- MTCA metals (arsenic, cadmium, chromium, mercury, and lead) by EPA Method 6020/7471B
- Herbicides by EPA Method 8151A

Samples were analyzed within specified holding times.

D.4.3 Analytical Results

In July 2014, five soil samples were collected from the Stage 3 segment geotechnical explorations to support IDW characterization. Analytical results are summarized in Table D-2 and the analytical laboratory reports are included in this appendix. Dates and reference numbers for these reports are summarized in the following Exhibit D-3:

Exhibit D-3: 2014 Fremont Analytical Reports

Date	Fremont Analytical Laboratory Reference Number	Pages
7/10/2014	1406291	19 pages
7/11/2014	1407039	22 pages
7/21/2014	1407120	21 pages
7/25/2014	1407187	21 pages

Lube-oil-range petroleum hydrocarbons were detected in soil samples EWC-B-01-14:10.0 and EWC-B-01-14:15.0 below the cleanup criteria.

Arsenic, chromium, and lead were detected below the MTCA Method A cleanup levels in the soil samples analyzed. Cadmium was also detected below the cleanup level in samples EWC-B-01-14:10.0 and EWC-B-01-14:15.0.

Table D-3 provides a toxicity equivalence factor (TEF) analysis of the individual carcinogenic PAH (cPAH) constituents. The TEF method is used to adjust the concentrations of each cPAH such that they are relative to benzo(a)pyrene, which is the most carcinogenic of the PAHs. The individual cPAH concentrations are then added together for comparison with the MTCA cleanup level for benzo(a)pyrene. Based on the TEF analysis, sample EWC-B-01-14:15.0 has adjusted cPAH concentrations that exceed the MTCA Method A unrestricted cleanup criterion.

Herbicides were detected in soil samples analyzed with the exception of EWC-B-01-14:15.0.

D.4.4 Investigation-Derived Waste

IDW generated during these field activities consisted of boring cuttings and drilling mud. IDW was placed in 55-gallon drums and temporarily stored on site pending laboratory analyses. Disposable sampling equipment was disposed as solid waste. The IDW was removed from the site by Tri-Valley Construction, Inc. of Yakima, Washington, under subcontract to Shannon & Wilson, on January 23, 2015. The IDW was disposed at the Terrace Heights Landfill of Yakima, Washington, on January 23, 2015.

D.5 REFERENCES

- Washington State Department of Ecology (Ecology), Toxics Cleanup Program, 1994, Natural background soil metals concentrations in Washington State, Publication No. 94-115, October.
- Washington State Department of Ecology (Ecology), 2013, Model Toxics Control Act regulation and statute, Chapter 173-340 WAC: Ecology Toxics Cleanup Program, Olympia, Wash., publication no. 94-06.

Table D-1: Summary of 2021 Analytical Testing Data

Boring: Sample Identification: Sample Depth (feet below ground surface): Sample Date: Sample Delivery Group:	B-9-21		B-10-21		B-11P-21		B-12P-21		B-13-21		B-14-21	B-15P-21	MTCA Soil Cleanup Levels		Natural Background Soil Metals Concentration ²
	B-9-21/R-10@48'	B-10-21/S-3@15.5'	B-10-21/a9@48'	B-11P-21/R-10@51'	B-12P-21/R-11@50'	B-13-21/R-8@39'	B-13-21/R-9@47'	B-14-21/R-9@48'	B-15P-21/S-5@21'	MTCA Method A Unrestricted Land Use (mg/kg)	MTCA Method B (mg/kg)				
Petroleum Hydrocarbons (mg/kg)															
Gasoline	NWTPH-Gx	5.37 U	131 U, H	5.46 U	4.44 U	5.88 U	15.4 U	5.41 U	7.33 U	5.46 U	100 ³	100 ³	*		
Gasoline Range Organics ¹	NWTPH-Gx	--	1,030 DH	--	--	--	--	--	--	--	100 ³	100 ³	*		
Diesel (Fuel Oil)	NWTPH-Dx	52.0 U	52.1 U, H	53.2 U	46.8 U	47.4 U	50.2 U	51.4 U	47.4 U	52.6 U	2,000	2,000	*		
Heavy Oil	NWTPH-Dx	104 U	1,120 DH	106 U	93.6 U	94.7 U	100 U	103 U	94.9 U	105 U	2,000	2,000	*		
Volatile Organic Compounds (mg/kg)															
Benzene	SW8260D	0.0215 U	0.0263 U, H	0.0218 U	0.0178 U	0.0235 U	0.0615 U	0.0216 U	0.0293 U	0.0218 U	0.03	0.03	*		
Toluene	SW8260D	0.0699 U	0.0854 U, H	0.071 U	0.0577 U	0.0765 U	0.2 U	0.0703 U	0.0953 U	0.071 U	7	7	*		
Ethylbenzene	SW8260D	0.0269 U	0.0328 U, H	0.0273 U	0.0222 U	0.0294 U	0.0769 U	0.027 U	0.0366 U	0.0273 U	6	6	*		
m, p-Xylene	SW8260D	0.0537 U	0.0657 U, H	0.0546 U	0.0444 U	0.0588 U	0.154 U	0.0541 U	0.0733 U	0.0546 U	9	9	*		
o-Xylene	SW8260D	0.0269 U	0.0328 U, H	0.0273 U	0.0222 U	0.0294 U	0.0769 U	0.027 U	0.0366 U	0.0273 U	9	9	*		
MTCA 5 Metals (mg/kg)															
Arsenic	SW6020B	2.41 D	2.58 D	2 D	2.25 D	1.99 D	2.48 D	2.46 D	3.45 D	2.77 D	20	24	5		
Barium	SW6020B	52.7 D	70.2 D	50.5 D	68.6 D	68.1 D	64.8 D	67.2 D	63.9 D	50.5 D	*	16000	255		
Cadmium	SW6020B	0.167 U	0.168 U	0.17 U	0.173 U	0.175 U	0.17 U	0.169 U	0.168 U	0.169 U	2	80	1		
Chromium	SW6020B	15.8 D	29.7 D	14.2 D	14.7 D	17.1 D	20.6 D	16.6 D	18.8 D	15.7 D	19/2,000 ⁴	120,000	38		
Lead	SW6020B	1.97 D	3.06 D	1.96 D	2.04 D	2.15 D	4.45 D	2.49 D	5.54 D	2.15 D	250	*	11		
Mercury	SW7471	0.238 U	0.235 U	0.245 U	0.247 U	0.248 U	0.26 U	0.263 U	0.251 U	0.273 U	2	*	0.05		
Selenium	SW6020B	2.4 D	1.52 D	2.25 D	2.47 D	1.68 D	1.54 D	1.72 D	1.85 D	2.19 D	*	400	0.78		
Silver	SW6020B	0.125 U	0.126 U	0.127 U	0.13 U	0.131 U	0.127 U	0.127 U	0.126 U	0.127 U	*	400	0.61		
Polynuclear Aromatic Hydrocarbons (PAHs) (mg/kg)															
Naphthalene	SW8270SIM	0.0213 U	0.0191 U, H	0.0202 U	0.019 U	0.0219 U	0.0185 U	0.0195 U	0.0181 U	0.0206 U	5	5	*		
2-Methylnaphthalene	SW8270SIM	0.0213 U	0.0191 U, H	0.0202 U	0.019 U	0.0219 U	0.0185 U	0.0195 U	0.0181 U	0.0206 U	*	*	*		
1-Methylnaphthalene	SW8270SIM	0.0213 U	0.0191 U, H	0.0202 U	0.019 U	0.0219 U	0.0185 U	0.0195 U	0.0181 U	0.0206 U	*	*	*		
Acenaphthylene	SW8270SIM	0.0213 U	0.0191 U, H	0.0202 U	0.019 U	0.0219 U	0.0185 U	0.0195 U	0.0181 U	0.0206 U	*	*	*		
Acenaphthene	SW8270SIM	0.0213 U	0.0191 U, H	0.0202 U	0.019 U	0.0219 U	0.0185 U	0.0195 U	0.0181 U	0.0206 U	*	*	*		
Fluorene	SW8270SIM	0.0213 U	0.0191 U, H	0.0202 U	0.019 U	0.0219 U	0.0185 U	0.0195 U	0.0181 U	0.0206 U	*	*	*		
Phenanthrene	SW8270SIM	0.0426 U	0.0383 U, H	0.0404 U	0.0379 U	0.0437 U	0.0369 U	0.039 U	0.0363 U	0.0411 U	*	*	*		
Anthracene	SW8270SIM	0.0426 U	0.0383 U, H	0.0404 U	0.0379 U	0.0437 U	0.0369 U	0.039 U	0.0363 U	0.0411 U	*	*	*		
Fluoranthene	SW8270SIM	0.0426 U	0.0383 U, H	0.0404 U	0.0379 U	0.0437 U	0.0369 U	0.039 U	0.0363 U	0.0411 U	*	*	*		
Pyrene	SW8270SIM	0.0426 U	0.0383 U, H	0.0404 U	0.0379 U	0.0437 U	0.0369 U	0.039 U	0.0363 U	0.0411 U	*	*	*		
Benz[a]anthracene	SW8270SIM	0.0213 U	0.0191 U, H	0.0202 U	0.019 U	0.0219 U	0.0185 U	0.0195 U	0.0181 U	0.0206 U	*	*	*		
Chrysene	SW8270SIM	0.0426 U	0.0383 U, H	0.0404 U	0.0379 U	0.0437 U	0.0369 U	0.039 U	0.0363 U	0.0411 U	*	*	*		
Benzo(k)fluoranthene	SW8270SIM	0.0213 U	0.0191 U, H	0.0202 U	0.019 U	0.0219 U	0.0185 U	0.0195 U	0.018 U	0.0206 U	*	*	*		
Benzo(b)fluoranthene	SW8270SIM	0.0213 U	0.0191 U, H	0.0202 U	0.019 U	0.0219 U	0.0185 U	0.0195 U	0.018 U	0.0206 U	*	*	*		
Benzo(ghi)perylene	SW8270SIM	0.0213 U	0.0191 U, H	0.0202 U	0.019 U	0.0219 U	0.0185 U	0.0195 U	0.018 U	0.0206 U	*	*	*		
Benzo(a)pyrene	SW8270SIM	0.0213 U	0.0191 U, H	0.0202 U	0.019 U	0.0219 U	0.0185 U	0.0195 U	0.018 U	0.0206 U	0.1	2	*		
Indeno(1,2,3-cd)pyrene	SW8270SIM	0.0426 U	0.0383 U, H	0.0404 U	0.0379 U	0.0437 U	0.0369 U	0.039 U	0.0363 U	0.0411 U	*	*	*		
Dibenzo(a,h)anthracene	SW8270SIM	0.0426 U	0.0383 U, H	0.0404 U	0.0379 U	0.0437 U	0.0369 U	0.039 U	0.0363 U	0.0411 U	*	*	*		
TEF-adjusted cPAHs (see Table D-3)		0.025	0.02	0.023	0.022	0.0254	0.0214	0.0226	0.021	0.02	0.1	2	*		
Detected Herbicides (mg/kg)															
Pentachlorophenol	SW8151A	0.0852 U	0.076 U, H	0.0809 U	0.0759 U	0.0875 U	0.0739 U	0.078 U	0.0725 U	0.0823 U	*	*	*		

NOTES:

- 1 Unresolved gasoline range organics (C6-C12) were detected in this sample (1,030 mg/kg). The beginning pattern matches mineral spirits but the end pattern is a different product.
- 2 Natural background soil metals concentrations shown are for Yakima Basin with the exception of Barium (value from Spokane Basin), silver (statewide value), and selenium (statewide value).
- 3 Criteria for gasoline-range petroleum in soil are 100 mg/kg when benzene is not present.
- 4 Criteria for chromium are for hexavalent chromium/trivalent chromium.

* No MTCA Method A values have been established for this analyte.

bold values indicate a detection.

Criteria for gasoline-range petroleum in soil are 30 mg/kg when benzene is present and 100 mg/kg when benzene is not present.

All samples were submitted for benzene, toluene, ethylbenzene, and xylenes analysis; no analytes were detected above reporting limits.

NA = Not applicable.

Shaded values indicate a MTCA Method A exceedance.

cPAHs = carcinogenic polycyclic aromatic hydrocarbons; D= dilution was required; H = holding times for preparation or analysis exceeded; mg/kg = milligram per kilogram; MTCA = Model Toxics Control Act; NWTPH-Dx = Northwest Total Petroleum Hydrocarbons-Diesel Extended; NWTPH-Gx = Northwest Total Petroleum Hydrocarbons-Gasoline Extended;

TCLP = Toxicity Characteristic Leaching Procedure; TEF = toxicity equivalency factor; U = the analyte was not detected above the laboratory reporting limit shown

Table D-2: Summary of 2017 Analytical Testing Data

Boring:	B-1-17				B-2-17				MTCA Soil Cleanup Levels		Natural Background Soil Metals Concentration ¹	
	Sample Identification:	ES-1	ES-2	ES-3	ES-4	ES-5	ES-6	ES-7	ES-8	Method A Unrestricted Land Use		Method B Direct Contact Noncancer
Sample Depth (feet below ground surface):	0.4	41.5	43.5	53.9	0.2	8.8	15.8	21.2				
Sample Date:	07/25/17	07/26/17	07/26/17	07/27/17	08/03/17	08/03/17	08/03/17	08/03/17				
Sample Delivery Group:	1707301	1707301	1707301	1707301	1708051	1708051	1708051	1708051				
Analyte	Method											
Petroleum Hydrocarbons (mg/kg)												
Gasoline	NWTPH-Gx	NA	4.4 U	5.2 U	5.4 U	NA	25.8 U	4.5 U	4.7 U	100 ²	*	*
#2 Diesel	NWTPH-Dx	NA	18.3 U	20.2 U	18.8 U	NA	19.2 U	18.9 U	20.4 U	2,000	*	*
Lube Oil	NWTPH-Dx	NA	45.8 U	50.5 U	47.0 U	NA	495	47.3 U	51.0 U	2,000	*	*
Volatile Organic Compounds (mg/kg)³												
Toluene	SW8260C	NA	0.0175 U	0.0207 U	0.0218 U	NA	0.177	0.0181 U	0.0186 U	7	6,400	*
1,2,3-Trichlorobenzene	SW8260C	NA	0.0175 U	0.0207 U	0.0218 U	NA	0.27	0.0181 U	0.0186 U	*	*	*
1,2,4-Trichlorobenzene	SW8260C	NA	0.0218 U	0.0259 U	0.0272 U	NA	0.27	0.0226 U	0.0233 U	*	800	*
RCRA 8 Metals (mg/kg)												
Arsenic	SW6020A	3.24	2.32	1.98	1.79	4.19	2.92	2.07	2.1	20	24	5
Barium	SW6020A	71	57.5	51.9	89.9	162	72.5	54.2	63.6	*	16000	255
Cadmium	SW6020A	0.153 U	0.149 U	0.17 U	0.161 U	0.175	0.473 U	0.17 U	0.172 U	2	80	1
Chromium	SW6020A	38.1	18.1	13.2	15.7	36.7	5.51	23	23.2	19/2,000 ⁴	240/120,000	38
Lead	SW6020A	3.24	2.29	1.58	2.05	7.1	14.2	2.65	2.29	250	*	11
Mercury	SW7471B	0.208 U	0.196 U	0.208 U	0.211 U	0.251 U	0.702 U	0.253 U	0.288 U	2	*	0.05
Selenium	SW6020A	1.95	1.5	1.97	1.77	2.16	1.18 U	1.63	1.53	*	400	0.78
Silver	SW6020A	0.078 U	0.082 U	0.082 U	0.083 U	0.081 U	0.224 U	0.08 U	0.094 U	*	400	0.61
Additional Metals (mg/kg)												
Copper	SW6020A	20.1	14.2	16	16.6	48.8	12	14.7	18.7	*	3,200	26
Nickel	SW6020A	62	19.3	17.9	16.2	69.1	5.56	25	19.5	*	1,600	46
Zinc	SW6020A	69.2	40.8	40.3	45.3	82.7	56.5	43.7	42.2	*	24,000	79
Polycyclic Aromatic Hydrocarbons (PAHs) (mg/kg)												
1-Methylnaphthalene	SW8270DSIM	NA	0.0415 U	0.0396 U	0.0442 U	NA	0.1190 U	0.0371 U	0.0455 U	--	--	*
2-Methylnaphthalene	SW8270DSIM	NA	0.0415 U	0.0396 U	0.0442 U	NA	0.1190 U	0.0371 U	0.0455 U	--	--	*
Acenaphthene	SW8270DSIM	NA	0.0415 U	0.0396 U	0.0442 U	NA	0.1190 U	0.0371 U	0.0455 U	--	--	*
Acenaphthylene	SW8270DSIM	NA	0.0415 U	0.0396 U	0.0442 U	NA	0.1190 U	0.0371 U	0.0455 U	--	--	*
Anthracene	SW8270DSIM	NA	0.0415 U	0.0396 U	0.0442 U	NA	0.1190 U	0.0371 U	0.0455 U	--	--	*
Benzo(a)anthracene	SW8270DSIM	NA	0.0415 U	0.0396 U	0.0442 U	NA	0.1190 U	0.0371 U	0.0455 U	--	--	*
Benzo(a)pyrene	SW8270DSIM	NA	0.0415 U	0.0396 U	0.0442 U	NA	0.1190 U	0.0371 U	0.0455 U	--	--	*
Benzo(b)fluoranthene	SW8270DSIM	NA	0.0415 U	0.0396 U	0.0442 U	NA	0.1190 U	0.0371 U	0.0455 U	--	--	*
Benzo(ghi)perylene	SW8270DSIM	NA	0.0415 U	0.0396 U	0.0442 U	NA	0.1190 U	0.0371 U	0.0455 U	--	--	*
Benzo(k)fluoranthene	SW8270DSIM	NA	0.0415 U	0.0396 U	0.0442 U	NA	0.1190 U	0.0371 U	0.0455 U	--	--	*
Chrysene	SW8270DSIM	NA	0.0415 U	0.0396 U	0.0442 U	NA	0.1190 U	0.0371 U	0.0455 U	--	--	*
Dibenzo(a,h)anthracene	SW8270DSIM	NA	0.0415 U	0.0396 U	0.0442 U	NA	0.1190 U	0.0371 U	0.0455 U	--	--	*
Fluoranthene	SW8270DSIM	NA	0.0415 U	0.0396 U	0.0442 U	NA	0.1190 U	0.0371 U	0.0455 U	--	--	*
Fluorene	SW8270DSIM	NA	0.0415 U	0.0396 U	0.0442 U	NA	0.1190 U	0.0371 U	0.0455 U	--	--	*
Indeno(1,2,3-cd)pyrene	SW8270DSIM	NA	0.0415 U	0.0396 U	0.0442 U	NA	0.1190 U	0.0371 U	0.0455 U	--	--	*
Naphthalene	SW8270DSIM	NA	0.0415 U	0.0396 U	0.0442 U	NA	0.1190 U	0.0371 U	0.0455 U	--	--	*
Phenanthrene	SW8270DSIM	NA	0.0415 U	0.0396 U	0.0442 U	NA	0.1190 U	0.0371 U	0.0455 U	--	--	*
Pyrene	SW8270DSIM	NA	0.0415 U	0.0396 U	0.0442 U	NA	0.1190 U	0.0371 U	0.0455 U	--	--	*
Polychlorinated Biphenyls (PCBs) (mg/kg)												
PCB-aroclor 1016	SW8082	NA	0.0889 U	0.105 U	0.106 U	NA	0.295 U	0.103 U	0.118 U	--	--	*
PCB-aroclor 1221	SW8082	NA	0.0889 U	0.105 U	0.106 U	NA	0.295 U	0.103 U	0.118 U	--	--	*
PCB-aroclor 1232	SW8082	NA	0.0889 U	0.105 U	0.106 U	NA	0.295 U	0.103 U	0.118 U	--	--	*
PCB-aroclor 1242	SW8082	NA	0.0889 U	0.105 U	0.106 U	NA	0.295 U	0.103 U	0.118 U	--	--	*
PCB-aroclor 1248	SW8082	NA	0.0889 U	0.105 U	0.106 U	NA	0.295 U	0.103 U	0.118 U	--	--	*
PCB-aroclor 1254	SW8082	NA	0.0889 U	0.105 U	0.106 U	NA	0.295 U	0.103 U	0.118 U	--	--	*
PCB-aroclor 1260	SW8082	NA	0.0889 U	0.105 U	0.106 U	NA	0.295 U	0.103 U	0.118 U	--	--	*
PCB-aroclor 1262	SW8082	NA	0.0889 U	0.105 U	0.106 U	NA	0.295 U	0.103 U	0.118 U	--	--	*
PCB-aroclor 1268	SW8082	NA	0.0889 U	0.105 U	0.106 U	NA	0.295 U	0.103 U	0.118 U	--	--	*
PCB, Sum of Aroclors	SW8082	NA	0.0889 U	0.105 U	0.106 U	NA	0.295 U	0.103 U	0.118 U	--	--	*

Boring:	B-1-17				B-2-17				MTCA Soil Cleanup Levels		Natural Background Soil Metals Concentration ¹
	Sample Identification:	ES-1	ES-2	ES-3	ES-4	ES-5	ES-6	ES-7	ES-8	Method A	
Sample Depth (feet below ground surface):	0.4	41.5	43.5	53.9	0.2	8.8	15.8	21.2		Unrestricted Land Use	Direct Contact Noncancer
Sample Date:	07/25/17	07/26/17	07/26/17	07/27/17	08/03/17	08/03/17	08/03/17	08/03/17			
Sample Delivery Group:	1707301	1707301	1707301	1707301	1708051	1708051	1708051	1708051			
Analyte	Method										
Organochlorine Pesticides (mg/kg)											
4,4'-DDD	SW8081A	0.009 U	NA	NA	NA	0.011 U	NA	NA	NA	--	*
4,4'-DDE	SW8081A	0.009 U	NA	NA	NA	0.011 U	NA	NA	NA	--	*
4,4'-DDT	SW8081A	0.009 U	NA	NA	NA	0.011 U	NA	NA	NA	--	*
Aldrin	SW8081A	0.009 U	NA	NA	NA	0.011 U	NA	NA	NA	--	*
alpha-BHC	SW8081A	0.009 U	NA	NA	NA	0.011 U	NA	NA	NA	--	*
beta-BHC	SW8081A	0.009 U	NA	NA	NA	0.011 U	NA	NA	NA	--	*
cis-Chlordane	SW8081A	0.009 U	NA	NA	NA	0.011 U	NA	NA	NA	--	*
delta-BHC	SW8081A	0.009 U	NA	NA	NA	0.011 U	NA	NA	NA	--	*
Dieldrin	SW8081A	0.009 U	NA	NA	NA	0.011 U	NA	NA	NA	--	*
Endosulfan I	SW8081A	0.009 U	NA	NA	NA	0.011 U	NA	NA	NA	--	*
Endosulfan II	SW8081A	0.009 U	NA	NA	NA	0.011 U	NA	NA	NA	--	*
Endosulfan Sulfate	SW8081A	0.009 U	NA	NA	NA	0.011 U	NA	NA	NA	--	*
Endrin	SW8081A	0.009 U	NA	NA	NA	0.011 U	NA	NA	NA	--	*
Endrin Aldehyde	SW8081A	0.009 U	NA	NA	NA	0.011 U	NA	NA	NA	--	*
Endrin Ketone	SW8081A	0.009 U	NA	NA	NA	0.011 U	NA	NA	NA	--	*
gamma-Chlordane	SW8081A	0.009 U	NA	NA	NA	0.011 U	NA	NA	NA	--	*
Heptachlor	SW8081A	0.009 U	NA	NA	NA	0.011 U	NA	NA	NA	--	*
Heptachlor Epoxide	SW8081A	0.009 U	NA	NA	NA	0.011 U	NA	NA	NA	--	*
Lindane	SW8081A	0.009 U	NA	NA	NA	0.011 U	NA	NA	NA	--	*
Methoxychlor	SW8081A	0.009 U	NA	NA	NA	0.011 U	NA	NA	NA	--	*
Toxaphene	SW8081A	0.090 U	NA	NA	NA	0.106 U	NA	NA	NA	--	*
Herbicides (mg/kg)											
2,4,5-T	SW8151A	0.0485 U	NA	NA	NA	0.0516 U	NA	NA	NA	--	*
2,4-D	SW8151A	0.0291 U	NA	NA	NA	0.0309 U	NA	NA	NA	--	*
2,4-DB	SW8151A	0.0242 U	NA	NA	NA	0.0258 U	NA	NA	NA	--	*
3,5-Dichlorobenzoic Acid	SW8151A	0.0388 U	NA	NA	NA	0.0413 U	NA	NA	NA	--	*
4-Nitrophenol	SW8151A	0.0291 U	NA	NA	NA	0.0309 U	NA	NA	NA	--	*
Acifluorfen	SW8151A	0.0776 U	NA	NA	NA	0.0825 U	NA	NA	NA	--	*
Bentazon	SW8151A	0.0339 U	NA	NA	NA	0.0361 U	NA	NA	NA	--	*
Chloramben	SW8151A	0.0194 U	NA	NA	NA	0.0206 U	NA	NA	NA	--	*
Chlorthal-dimethyl	SW8151A	0.0291 U	NA	NA	NA	0.0309 U	NA	NA	NA	--	*
Dalapon	SW8151A	0.1940 U	NA	NA	NA	0.2060 U	NA	NA	NA	--	*
Dicamba	SW8151A	0.0339 U	NA	NA	NA	0.0361 U	NA	NA	NA	--	*
Dichlorprop	SW8151A	0.0242 U	NA	NA	NA	0.0258 U	NA	NA	NA	--	*
Dinoseb	SW8151A	0.0291 U	NA	NA	NA	0.0309 U	NA	NA	NA	--	*
MCPA	SW8151A	2.7200 U	NA	NA	NA	2.8900 U	NA	NA	NA	--	*
Mecoprop	SW8151A	4.2700 U	NA	NA	NA	4.5400 U	NA	NA	NA	--	*
Picloram	SW8151A	0.0485 U	NA	NA	NA	0.0516 U	NA	NA	NA	--	*
Silvex	SW8151A	0.0194 U	NA	NA	NA	0.0206 U	NA	NA	NA	--	*

NOTES:

Bold values indicate a detection.

Concentrations are in milligrams per kilogram (mg/kg)

1 Natural background soil metals concentrations shown are for Yakima Basin with the exception of Barium (value from Spokane Basin), silver (statewide value), and selenium (statewide value).

2 Criteria for gasoline-range petroleum in soil is 100 mg/kg when benzene is not present.

3 Only VOCs that were detected within one or more sample are shown in the table. All other VOCs were not detected above laboratory reporting limits.

4 Criteria for chromium are for hexavalent chromium/trivalent chromium.

* = criteria not established for this analyte

-- = not shown, no detections occurred within analytical group

mg/kg = milligram per kilogram; MTCA = Model Toxics Control Act; NA = not analyzed; MTCA = Model Toxics Control Act; NWTPH-Dx = Northwest Total Petroleum Hydrocarbons-Diesel Extended; NWTPH-Gx = Northwest Total Petroleum Hydrocarbons-Gasoline Extended; RCRA = Resource Conservation and Recovery Act;

U = the analyte was not detected above the indicated laboratory reporting limit

Table D-3: Summary of 2014 Analytical Testing Data

Boring:		EWC-B-01-14		EWC-B-02-14	EWC-B-03-14	EWC-B-04-14	MTCA Method A Unrestricted Land Use (mg/kg)	MTCA Method A Industrial Land Use (mg/kg)
Sample Identification:		EWC-B-01-14:10.0	EWC-B-01-14:15.0	EWC-B-02-14:12.25	EWC-B-03-14:12.0	EWC-B-04-14:10.0		
Analyte	Method							
Petroleum Hydrocarbons (mg/kg)								
Gasoline Range Organics	NWTPH-Gx	8.3 U	11 U	5.1 U	4.5 U	2.8 U	30/100	30/100
Diesel Range Organics	NWTPH-Dx	32 U	42 U	18 U	18 U	20 U	2,000	2,000
Lube Oil	NWTPH-Dx	147	1540	46 U	46 U	50 U	2,000	2,000
Volatile Organic Compounds (mg/kg)								
Benzene	SW8260C	0.033 U	0.042 U	0.020 U	0.018 U	0.011 U	0.03	0.03
Toluene	SW8260C	0.033 U	0.042 U	0.020 U	0.018 U	0.011 U	7	7
Ethylbenzene	SW8260C	0.050 U	0.064 U	0.030 U	0.027 U	0.017 U	6	6
m, p-Xylene	SW8260C	0.033 U	0.042 U	0.020 U	0.018 U	0.011 U		
o-Xylene	SW8260C	0.033 U	0.042 U	0.020 U	0.018 U	0.011 U	9	9
MTCA 5 Metals (mg/kg)								
Arsenic	SW6010C	2.5	6.1	2.2	2.0	2.8	20	20
Cadmium	SW6010C	0.53	0.87	0.17 U	0.16 U	0.18 U	2	2
Chromium	SW6010C	13	18	14	11	25	2,000	2,000
Lead	SW6010C	21	36	2.9	1.9	2.5	250	1,000
Mercury	SW7471B	0.41 U	0.50 U	0.29 U	0.26 U	0.29 U	2	2
Polynuclear Aromatic Hydrocarbons (PAHs) (mg/kg)								
Naphthalene	SW8270DSIM	0.083 U	0.241	0.053 U	0.049 U	0.058 U	5	5
2-Methylnaphthalene	SW8270DSIM	0.083 U	0.0997 U	0.053 U	0.049 U	0.058 U	*	*
1-Methylnaphthalene	SW8270DSIM	0.083 U	0.0997 U	0.053 U	0.049 U	0.058 U	*	*
Acenaphthylene	SW8270DSIM	0.083 U	0.0997 U	0.053 U	0.049 U	0.058 U	*	*
Acenaphthene	SW8270DSIM	0.083 U	0.126	0.053 U	0.049 U	0.058 U	*	*
Fluorene	SW8270DSIM	0.083 U	0.178	0.053 U	0.049 U	0.058 U	*	*
Phenanthrene	SW8270DSIM	0.083 U	1.07	0.053 U	0.049 U	0.058 U	*	*
Anthracene	SW8270DSIM	0.083 U	0.289	0.053 U	0.049 U	0.058 U	*	*
Fluoranthene	SW8270DSIM	0.12	1.09	0.053 U	0.049 U	0.058 U	*	*
Pyrene	SW8270DSIM	0.083 U	0.839	0.053 U	0.049 U	0.058 U	*	*
Benz[a]anthracene	SW8270DSIM	0.083 U	0.46	0.053 U	0.049 U	0.058 U	*	*
Chrysene	SW8270DSIM	0.083 U	0.25	0.053 U	0.049 U	0.058 U	*	*
Benzo(k)fluoranthene	SW8270DSIM	0.083 U	0.20	0.053 U	0.049 U	0.058 U	*	*
Benzo(b)fluoranthene	SW8270DSIM	0.083 U	0.51	0.053 U	0.049 U	0.058 U	*	*
Benzo(ghi)perylene	SW8270DSIM	0.083 U	0.25	0.053 U	0.049 U	0.058 U	*	*
Benzo(a)pyrene	SW8270DSIM	0.083 U	0.38	0.053 U	0.049 U	0.058 U	0.1	2
Indeno(1,2,3-cd)pyrene	SW8270DSIM	0.083 U	0.23	0.053 U	0.049 U	0.058 U	*	*
Dibenzo(a,h)anthracene	SW8270DSIM	0.083 U	0.13	0.053 U	0.049 U	0.058 U	*	*
Benzo(ghi)perylene	SW8270DSIM	0.083 U	0.25	0.053 U	0.049 U	0.058 U	*	*
TEF-adjusted cPAHs (see Table D-4)		0.0020 U	0.58	0.0010 U	0.0010 U	0.0012 U	0.1	2

Boring:		EWC-B-01-14		EWC-B-02-14	EWC-B-03-14	EWC-B-04-14	MTCA Method A Unrestricted Land Use (mg/kg)	MTCA Method A Industrial Land Use (mg/kg)
Sample Identification:		EWC-B-01-14:10.0	EWC-B-01-14:15.0	EWC-B-02-14:12.25	EWC-B-03-14:12.0	EWC-B-04-14:10.0		
Analyte	Method							
Detected Herbicides (ug/kg)								
Pentachlorophenol	SW8151A	0.35	0.036 U	0.043	0.051	0.15	*	*

NOTES:

* No MTCA Method A values have been established for this analyte.

Bold values indicate a detection.

Criteria for gasoline-range petroleum in soil are 30 mg/kg when benzene is present and 100 mg/kg when benzene is not present.

Shaded values indicate a MTCA Method A exceedance.

cPAHs = carcinogenic polycyclic aromatic hydrocarbons; EWC = East-West Corridor; mg/kg = milligram per kilogram; MTCA = Model Toxics Control Act; NWTPH-Dx = Northwest Total Petroleum Hydrocarbons-Diesel Extended; NWTPH-Gx = Northwest Total Petroleum Hydrocarbons-Gasoline Extended; TEF = toxicity equivalent factor; U = the analyte was not detected above the laboratory reporting limit shown; ug/kg = microgram per kilogram

Table D-4: Summary of Adjusted Toxicity Equivalence Factor Concentrations

Soil Sample	Analyte	Sample Result (mg/kg)	Method Detection Limit (mg/kg)	Toxic Equivalency Factor (TEF)	Adjusted Concentration ¹ (mg/kg)	
B-9-21/R-10@48'	Benzo(a)anthracene	ND	0.0213	0.1	0.001065	
	Chrysene	ND	0.0426	0.01	0.000213	
	Benzo(b)fluoranthene	ND	0.0213	0.1	0.001065	
	Benzo(k)fluoranthene	ND	0.0213	0.1	0.001065	
	Benzo(a)pyrene	ND	0.0213	1	0.01065	
	Indeno(1,2,3-c,d)pyrene	ND	0.0426	0.1	0.00213	
	Dibenzo(a,h)anthracene	ND	0.0426	0.4	0.0085	
	Sum²					0.025
	MTCA Method A Cleanup Level for Unrestricted Land Use					0.10
	MTCA Method A Cleanup Level for Industrial Land Use					2.0
B-10-21/S-3@15.5'	Benzo(a)anthracene	ND	0.0191	0.1	0.000955	
	Chrysene	ND	0.0383	0.01	0.0001915	
	Benzo(b)fluoranthene	ND	0.0191	0.1	0.000955	
	Benzo(k)fluoranthene	ND	0.0191	0.1	0.000955	
	Benzo(a)pyrene	ND	0.0191	1	0.00955	
	Indeno(1,2,3-c,d)pyrene	ND	0.0383	0.1	0.001915	
	Dibenzo(a,h)anthracene	ND	0.0383	0.4	0.0077	
	Sum²					0.02
	MTCA Method A Cleanup Level for Unrestricted Land Use					0.10
	MTCA Method A Cleanup Level for Industrial Land Use					2.0
B-10-21/a9@48'	Benzo(a)anthracene	ND	0.0202	0.1	0.00101	
	Chrysene	ND	0.0404	0.01	0.000202	
	Benzo(b)fluoranthene	ND	0.0202	0.1	0.00101	
	Benzo(k)fluoranthene	ND	0.0202	0.1	0.00101	
	Benzo(a)pyrene	ND	0.0202	1	0.0101	
	Indeno(1,2,3-c,d)pyrene	ND	0.0404	0.1	0.00202	
	Dibenzo(a,h)anthracene	ND	0.0404	0.4	0.00808	
	Sum²					0.023
	MTCA Method A Cleanup Level for Unrestricted Land Use					0.10
	MTCA Method A Cleanup Level for Industrial Land Use					2.0

Soil Sample	Analyte	Sample Result (mg/kg)	Method Detection Limit (mg/kg)	Toxic Equivalency	
				Factor (TEF)	Adjusted Concentration ¹ (mg/kg)
B-11P-21/R-10@51'	Benzo(a)anthracene	ND	0.0190	0.1	0.00095
	Chrysene	ND	0.0379	0.01	0.0001895
	Benzo(b)fluoranthene	ND	0.0190	0.1	0.00095
	Benzo(k)fluoranthene	ND	0.0190	0.1	0.00095
	Benzo(a)pyrene	ND	0.0190	1	0.0095
	Indeno(1,2,3-c,d)pyrene	ND	0.0379	0.1	0.001895
	Dibenzo(a,h)anthracene	ND	0.0379	0.4	0.00758
	Sum²				0.0220
	MTCA Method A Cleanup Level for Unrestricted Land Use				0.10
	MTCA Method A Cleanup Level for Industrial Land Use				2.0
B-12P-21/R-11@50'	Benzo(a)anthracene	ND	0.0219	0.1	0.001095
	Chrysene	ND	0.0437	0.01	0.0002185
	Benzo(b)fluoranthene	ND	0.0219	0.1	0.001095
	Benzo(k)fluoranthene	ND	0.0219	0.1	0.001095
	Benzo(a)pyrene	ND	0.0219	1	0.01095
	Indeno(1,2,3-c,d)pyrene	ND	0.0437	0.1	0.002185
	Dibenzo(a,h)anthracene	ND	0.0437	0.4	0.00874
	Sum²				0.0254
	MTCA Method A Cleanup Level for Unrestricted Land Use				0.10
	MTCA Method A Cleanup Level for Industrial Land Use				2.0
B-13-21/R-8@39'	Benzo(a)anthracene	ND	0.0185	0.1	0.000925
	Chrysene	ND	0.0369	0.01	0.0001845
	Benzo(b)fluoranthene	ND	0.0185	0.1	0.000925
	Benzo(k)fluoranthene	ND	0.0185	0.1	0.000925
	Benzo(a)pyrene	ND	0.0185	1	0.00925
	Indeno(1,2,3-c,d)pyrene	ND	0.0369	0.1	0.001845
	Dibenzo(a,h)anthracene	ND	0.0369	0.4	0.00738
	Sum²				0.0214
	MTCA Method A Cleanup Level for Unrestricted Land Use				0.10
	MTCA Method A Cleanup Level for Industrial Land Use				2.0

Soil Sample	Analyte	Sample Result (mg/kg)	Method Detection Limit (mg/kg)	Toxic Equivalency Factor (TEF)	Adjusted Concentration ¹ (mg/kg)	
B-13-21/R-9@47'	Benzo(a)anthracene	ND	0.0195	0.1	0.000975	
	Chrysene	ND	0.0390	0.01	0.000195	
	Benzo(b)fluoranthene	ND	0.0195	0.1	0.000975	
	Benzo(k)fluoranthene	ND	0.0195	0.1	0.000975	
	Benzo(a)pyrene	ND	0.0195	1	0.00975	
	Indeno(1,2,3-c,d)pyrene	ND	0.0390	0.1	0.00195	
	Dibenzo(a,h)anthracene	ND	0.0390	0.4	0.0078	
	Sum²					0.0226
	MTCA Method A Cleanup Level for Unrestricted Land Use					0.10
	MTCA Method A Cleanup Level for Industrial Land Use					2.0
B-14-21/R-9@48'	Benzo(a)anthracene	ND	0.0181	0.1	0.000905	
	Chrysene	ND	0.0363	0.01	0.0001815	
	Benzo(b)fluoranthene	ND	0.0181	0.1	0.000905	
	Benzo(k)fluoranthene	ND	0.0181	0.1	0.000905	
	Benzo(a)pyrene	ND	0.0181	1	0.00905	
	Indeno(1,2,3-c,d)pyrene	ND	0.0363	0.1	0.001815	
	Dibenzo(a,h)anthracene	ND	0.0363	0.4	0.00726	
	Sum²					0.0210
	MTCA Method A Cleanup Level for Unrestricted Land Use					0.10
	MTCA Method A Cleanup Level for Industrial Land Use					2.0
B-15P-21/S-5@21'	Benzo(a)anthracene	ND	0.0206	0.1	0.00103	
	Chrysene	ND	0.0411	0.01	0.0002055	
	Benzo(b)fluoranthene	ND	0.0206	0.1	0.00103	
	Benzo(k)fluoranthene	ND	0.0206	0.1	0.00103	
	Benzo(a)pyrene	ND	0.0206	1	0.0103	
	Indeno(1,2,3-c,d)pyrene	ND	0.0411	0.1	0.002055	
	Dibenzo(a,h)anthracene	ND	0.0411	0.4	0.0082	
	Sum²					0.02
	MTCA Method A Cleanup Level for Unrestricted Land Use					0.10
	MTCA Method A Cleanup Level for Industrial Land Use					2.0

Soil Sample	Analyte	Sample Result (mg/kg)	Method Detection Limit (mg/kg)	Toxic Equivalency	
				Factor (TEF)	Adjusted Concentration ¹ (mg/kg)
EWC-B-01-14:10.0	Benzo(a)anthracene	ND	0.0015	0.1	0.000075
	Chrysene	ND	0.0017	0.01	0.00000845
	Benzo(b)fluoranthene	ND	0.0019	0.1	0.0000965
	Benzo(k)fluoranthene	ND	0.0015	0.1	0.000077
	Benzo(a)pyrene	ND	0.0019	1	0.000965
	Indeno(1,2,3-c,d)pyrene	ND	0.0021	0.1	0.000106
	Dibenzo(a,h)anthracene	ND	0.0019	0.4	0.0004
	Sum²				0.002
	MTCA Method A Cleanup Level for Unrestricted Land Use				0.10
	MTCA Method A Cleanup Level for Industrial Land Use				2.0
EWC-B-01-14:15.0	Benzo(a)anthracene	0.46	0.0019	0.1	0.0462
	Chrysene	0.25	0.0020	0.01	0.00248
	Benzo(b)fluoranthene	0.51	0.0023	0.1	0.0507
	Benzo(k)fluoranthene	0.20	0.0018	0.1	0.0203
	Benzo(a)pyrene	0.38	0.0023	1	0.382
	Indeno(1,2,3-c,d)pyrene	0.23	0.0025	0.1	0.0231
	Dibenzo(a,h)anthracene	0.13	0.0022	0.4	0.0536
	Sum²				0.58
	MTCA Method A Cleanup Level for Unrestricted Land Use				0.10
	MTCA Method A Cleanup Level for Industrial Land Use				2.0
EWC-B-02-14:12.25	Benzo(a)anthracene	ND	0.0010	0.1	0.00005
	Chrysene	ND	0.0011	0.01	0.00000545
	Benzo(b)fluoranthene	ND	0.0013	0.1	0.0000625
	Benzo(k)fluoranthene	ND	0.0009	0.1	0.000045
	Benzo(a)pyrene	ND	0.0013	1	0.000625
	Indeno(1,2,3-c,d)pyrene	ND	0.0013	0.1	0.000065
	Dibenzo(a,h)anthracene	ND	0.0012	0.4	0.00024
	Sum²				0.001
	MTCA Method A Cleanup Level for Unrestricted Land Use				0.10
	MTCA Method A Cleanup Level for Industrial Land Use				2.0

Soil Sample	Analyte	Sample Result (mg/kg)	Method Detection Limit (mg/kg)	Toxic Equivalency	
				Factor (TEF)	Adjusted Concentration ¹ (mg/kg)
EWC-B-03-14:12.0	Benzo(a)anthracene	ND	0.0009	0.1	0.000045
	Chrysene	ND	0.0010	0.01	0.000005
	Benzo(b)fluoranthene	ND	0.0011	0.1	0.000055
	Benzo(k)fluoranthene	ND	0.0009	0.1	0.000045
	Benzo(a)pyrene	ND	0.0011	1	0.00055
	Indeno(1,2,3-c,d)pyrene	ND	0.0012	0.1	0.00006
	Dibenzo(a,h)anthracene	ND	0.0011	0.4	0.00022
	Sum²				0.0010
	MTCA Method A Cleanup Level for Unrestricted Land Use				0.10
	MTCA Method A Cleanup Level for Industrial Land Use				2.0
EWC-B-04-14:10.0	Benzo(a)anthracene	ND	0.0011	0.1	0.000055
	Chrysene	ND	0.0011	0.01	0.0000055
	Benzo(b)fluoranthene	ND	0.0013	0.1	0.000065
	Benzo(k)fluoranthene	ND	0.0010	0.1	0.00005
	Benzo(a)pyrene	ND	0.0013	1	0.00065
	Indeno(1,2,3-c,d)pyrene	ND	0.0014	0.1	0.00007
	Dibenzo(a,h)anthracene	ND	0.0013	0.4	0.00026
	Sum²				0.0012
	MTCA Method A Cleanup Level for Unrestricted Land Use				0.10
	MTCA Method A Cleanup Level for Industrial Land Use				2.0
EWC-TP-03-14:12	Benzo(a)anthracene	0.086	0.0500	0.1	0.0086
	Chrysene	0.082	0.0500	0.01	0.00082
	Benzo(b)fluoranthene	ND	0.0500	0.1	0.0025
	Benzo(k)fluoranthene	ND	0.0500	0.1	0.0025
	Benzo(a)pyrene	ND	0.0500	1	0.025
	Indeno(1,2,3-c,d)pyrene	ND	0.0500	0.1	0.0025
	Dibenzo(a,h)anthracene	ND	0.0500	0.4	0.0100
	Sum²				0.052
	MTCA Method A Cleanup Level for Unrestricted Land Use				0.10
	MTCA Method A Cleanup Level for Industrial Land Use				2.0

Soil Sample	Analyte	Sample Result (mg/kg)	Method Detection Limit (mg/kg)	Toxic Equivalency	
				Factor (TEF)	Adjusted Concentration ¹ (mg/kg)
EWC-TP-04-14:11	Benzo(a)anthracene	0.086	0.0100	0.1	0.0086
	Chrysene	0.070	0.0100	0.01	0.0007
	Benzo(b)fluoranthene	0.033	0.0100	0.1	0.0033
	Benzo(k)fluoranthene	0.012	0.0100	0.1	0.0012
	Benzo(a)pyrene	0.024	0.0100	1	0.024
	Indeno(1,2,3-c,d)pyrene	ND	0.0100	0.1	0.0005
	Dibenzo(a,h)anthracene	ND	0.0100	0.4	0.0020
	Sum²				0.04
	MTCA Method A Cleanup Level for Unrestricted Land Use				0.10
	MTCA Method A Cleanup Level for Industrial Land Use				2.0
EWC-TP-05-14:11.0	Benzo(a)anthracene	ND	0.0009	0.1	0.000045
	Chrysene	ND	0.0009	0.01	0.000045
	Benzo(b)fluoranthene	ND	0.0011	0.1	0.000055
	Benzo(k)fluoranthene	ND	0.0008	0.1	0.00004
	Benzo(a)pyrene	ND	0.0011	1	0.00055
	Indeno(1,2,3-c,d)pyrene	ND	0.0012	0.1	0.00006
	Dibenzo(a,h)anthracene	ND	0.0011	0.4	0.00022
	Sum²				0.0010
	MTCA Method A Cleanup Level for Unrestricted Land Use				0.10
	MTCA Method A Cleanup Level for Industrial Land Use				2.0

NOTES:

1 Calculated as the detected concentration times the TEF, or as half the method detection limit (if analyte is not detected) times the TEF.

2 Sum of the TEF for each cPAH.

Bold values indicated a detection.

Shaded values indicate an MTCA Method A exceedance.

cPAH = carcinogenic polycyclic aromatic hydrocarbon; mg/kg = milligrams per kilogram; MTCA = Washington Model Toxics Control Act; ND = not detected



3600 Fremont Ave. N.
Seattle, WA 98103
T: (206) 352-3790
F: (206) 352-7178
info@fremontanalytical.com

Shannon & Wilson

Ed Ptak
400 N. 34th Street, Suite 100
Seattle, WA 98103

RE: Yakima EWC

Lab ID: 1406291

July 10, 2014

Attention Ed Ptak:

Fremont Analytical, Inc. received 1 sample(s) on 6/27/2014 for the analyses presented in the following report.

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.
Gasoline by NWTPH-Gx
Mercury by EPA Method 7471
Pentachlorophenol by EPA 8151A
Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)
Sample Moisture (Percent Moisture)
Total Metals by EPA Method 6020
Volatile Organic Compounds by EPA Method 8260

This report consists of the following:

- Case Narrative
- Analytical Results
- Applicable Quality Control Summary Reports
- Chain of Custody

All analyses were performed consistent with the Quality Assurance program of Fremont Analytical, Inc. Please contact the laboratory if you should have any questions about the results.

Thank you for using Fremont Analytical.

Sincerely,

A handwritten signature in black ink, appearing to read "M. Dee".

Michael Dee
Sr. Chemist / Principal



Date: 07/10/2014

CLIENT: Shannon & Wilson
Project: Yakima EWC
Lab Order: 1406291

Work Order Sample Summary

Lab Sample ID	Client Sample ID	Date/Time Collected	Date/Time Received
1406291-001	EWC-B-02:12.25	06/27/2014 12:00 PM	06/27/2014 12:00 PM

Note: If no "Time Collected" is supplied, a default of 12:00AM is assigned

CLIENT: Shannon & Wilson

Project: Yakima EWC

I. SAMPLE RECEIPT:

Samples receipt information is recorded on the attached Sample Receipt Checklist.

II. GENERAL REPORTING COMMENTS:

Results are reported on a wet weight basis unless dry-weight correction is denoted in the units field on the analytical report ("mg/kg-dry" or "ug/kg-dry").

Matrix Spike (MS) and MS Duplicate (MSD) samples are tested from an analytical batch of "like" matrix to check for possible matrix effect. The MS and MSD will provide site specific matrix data only for those samples which are spiked by the laboratory. The sample chosen for spike purposes may or may not have been a sample submitted in this sample delivery group. The validity of the analytical procedures for which data is reported in this analytical report is determined by the Laboratory Control Sample (LCS) and the Method Blank (MB). The LCS and the MB are processed with the samples and the MS/MSD to ensure method criteria are achieved throughout the entire analytical process.

III. ANALYSES AND EXCEPTIONS:

Exceptions associated with this report will be footnoted in the analytical results page(s) or the quality control summary page(s) and/or noted below.



Analytical Report

WO#: 1406291

Date Reported: 7/10/2014

Client: Shannon & Wilson

Collection Date: 6/27/2014 12:00:00 PM

Project: Yakima EWC

Lab ID: 1406291-001

Matrix: Soil

Client Sample ID: EWC-B-02:12.25

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
<u>Pentachlorophenol by EPA 8151A</u>					Batch ID: 8026	Analyst: MD
Pentachlorophenol	0.0434	0.0227		mg/Kg-dry	1	7/9/2014 6:35:00 PM
Surr: 2,4-Dichlorophenylacetic acid	67.5	65-135		%REC	1	7/9/2014 6:35:00 PM
<u>Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.</u>					Batch ID: 7961	Analyst: EC
Diesel (Fuel Oil)	ND	18.4		mg/Kg-dry	1	6/29/2014 11:59:00 AM
Heavy Oil	ND	45.9		mg/Kg-dry	1	6/29/2014 11:59:00 AM
Surr: 2-Fluorobiphenyl	74.1	50-150		%REC	1	6/29/2014 11:59:00 AM
Surr: o-Terphenyl	76.3	50-150		%REC	1	6/29/2014 11:59:00 AM
<u>Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)</u>					Batch ID: 7958	Analyst: NG
Naphthalene	ND	53.3		µg/Kg-dry	1	6/29/2014 8:51:00 PM
2-Methylnaphthalene	ND	53.3		µg/Kg-dry	1	6/29/2014 8:51:00 PM
1-Methylnaphthalene	ND	53.3		µg/Kg-dry	1	6/29/2014 8:51:00 PM
Acenaphthylene	ND	53.3		µg/Kg-dry	1	6/29/2014 8:51:00 PM
Acenaphthene	ND	53.3		µg/Kg-dry	1	6/29/2014 8:51:00 PM
Fluorene	ND	53.3		µg/Kg-dry	1	6/29/2014 8:51:00 PM
Phenanthrene	ND	53.3		µg/Kg-dry	1	6/29/2014 8:51:00 PM
Anthracene	ND	53.3		µg/Kg-dry	1	6/29/2014 8:51:00 PM
Fluoranthene	ND	53.3		µg/Kg-dry	1	6/29/2014 8:51:00 PM
Pyrene	ND	53.3		µg/Kg-dry	1	6/29/2014 8:51:00 PM
Benz(a)anthracene	ND	53.3		µg/Kg-dry	1	6/29/2014 8:51:00 PM
Chrysene	ND	53.3		µg/Kg-dry	1	6/29/2014 8:51:00 PM
Benzo(b)fluoranthene	ND	53.3		µg/Kg-dry	1	6/29/2014 8:51:00 PM
Benzo(k)fluoranthene	ND	53.3		µg/Kg-dry	1	6/29/2014 8:51:00 PM
Benzo(a)pyrene	ND	53.3		µg/Kg-dry	1	6/29/2014 8:51:00 PM
Indeno(1,2,3-cd)pyrene	ND	53.3		µg/Kg-dry	1	6/29/2014 8:51:00 PM
Dibenz(a,h)anthracene	ND	53.3		µg/Kg-dry	1	6/29/2014 8:51:00 PM
Benzo(g,h,i)perylene	ND	53.3		µg/Kg-dry	1	6/29/2014 8:51:00 PM
Surr: 2-Fluorobiphenyl	90.5	42.7-132		%REC	1	6/29/2014 8:51:00 PM
Surr: Terphenyl-d14 (surr)	106	48.8-157		%REC	1	6/29/2014 8:51:00 PM

Qualifiers: B Analyte detected in the associated Method Blank
 E Value above quantitation range
 J Analyte detected below quantitation limits
 RL Reporting Limit

D Dilution was required
 H Holding times for preparation or analysis exceeded
 ND Not detected at the Reporting Limit
 S Spike recovery outside accepted recovery limits



Analytical Report

WO#: 1406291

Date Reported: 7/10/2014

Client: Shannon & Wilson

Collection Date: 6/27/2014 12:00:00 PM

Project: Yakima EWC

Lab ID: 1406291-001

Matrix: Soil

Client Sample ID: EWC-B-02:12.25

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Gasoline by NWTPH-Gx

Batch ID: R15325 Analyst: GH

Gasoline	ND	5.06		mg/Kg-dry	1	6/30/2014 8:29:00 AM
Surr: 4-Bromofluorobenzene	110	65-135		%REC	1	6/30/2014 8:29:00 AM
Surr: Toluene-d8	101	65-135		%REC	1	6/30/2014 8:29:00 AM

Volatile Organic Compounds by EPA Method 8260

Batch ID: 7957 Analyst: GH

Benzene	ND	0.0202		mg/Kg-dry	1	6/30/2014 8:29:00 AM
Toluene	ND	0.0202		mg/Kg-dry	1	6/30/2014 8:29:00 AM
Ethylbenzene	ND	0.0304		mg/Kg-dry	1	6/30/2014 8:29:00 AM
m,p-Xylene	ND	0.0202		mg/Kg-dry	1	6/30/2014 8:29:00 AM
o-Xylene	ND	0.0202		mg/Kg-dry	1	6/30/2014 8:29:00 AM
Surr: Dibromofluoromethane	99.3	63.7-129		%REC	1	6/30/2014 8:29:00 AM
Surr: Toluene-d8	95.4	61.4-128		%REC	1	6/30/2014 8:29:00 AM
Surr: 1-Bromo-4-fluorobenzene	92.5	63.1-141		%REC	1	6/30/2014 8:29:00 AM

Mercury by EPA Method 7471

Batch ID: 7963 Analyst: MW

Mercury	ND	0.285		mg/Kg-dry	1	6/30/2014 11:13:07 AM
---------	----	-------	--	-----------	---	-----------------------

Total Metals by EPA Method 6020

Batch ID: 7971 Analyst: TN

Arsenic	2.23	0.0871		mg/Kg-dry	1	6/30/2014 4:09:25 PM
Cadmium	ND	0.174		mg/Kg-dry	1	6/30/2014 4:09:25 PM
Chromium	14.4	0.0871		mg/Kg-dry	1	6/30/2014 4:09:25 PM
Lead	2.85	0.174		mg/Kg-dry	1	6/30/2014 4:09:25 PM

Sample Moisture (Percent Moisture)

Batch ID: R15161 Analyst: TK

Percent Moisture	12.4			wt%	1	6/27/2014 2:28:52 PM
------------------	------	--	--	-----	---	----------------------

Qualifiers:	B	Analyte detected in the associated Method Blank	D	Dilution was required
	E	Value above quantitation range	H	Holding times for preparation or analysis exceeded
	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits



Work Order: 1406291
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Total Metals by EPA Method 6020

Sample ID: MB-7971	SampType: MBLK	Units: mg/Kg	Prep Date: 6/30/2014	RunNo: 15335							
Client ID: MBLKS	Batch ID: 7971		Analysis Date: 6/30/2014	SeqNo: 310995							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	ND	0.100									
Cadmium	ND	0.200									
Chromium	ND	0.100									
Lead	ND	0.200									

Sample ID: LCS-7971	SampType: LCS	Units: mg/Kg	Prep Date: 6/30/2014	RunNo: 15335							
Client ID: LCSS	Batch ID: 7971		Analysis Date: 6/30/2014	SeqNo: 310996							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	114	0.100	104.0	0	109	69.5	130.8				
Cadmium	112	0.200	92.80	0	121	73.3	127.2				
Chromium	68.9	0.100	62.90	0	110	67.9	132				
Lead	359	0.200	319.0	0	113	75.9	124.1				

Sample ID: 1406291-001ADUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 6/30/2014	RunNo: 15335							
Client ID: EWC-B-02:12.25	Batch ID: 7971		Analysis Date: 6/30/2014	SeqNo: 310998							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	1.73	0.0865						2.227	25.1	30	
Cadmium	ND	0.173						0		30	
Chromium	11.2	0.0865						14.42	25.5	30	
Lead	2.62	0.173						2.851	8.59	30	

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits



Work Order: 1406291
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Total Metals by EPA Method 6020

Sample ID: 1406291-001AMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 6/30/2014	RunNo: 15335							
Client ID: EWC-B-02:12.25	Batch ID: 7971		Analysis Date: 6/30/2014	SeqNo: 311000							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	52.2	0.0871	43.56	2.227	115	75	125				
Cadmium	2.33	0.174	2.178	0.06856	104	75	125				
Chromium	66.1	0.0871	43.56	14.42	119	75	125				
Lead	27.9	0.174	21.78	2.851	115	75	125				

Sample ID: 1406291-001AMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 6/30/2014	RunNo: 15335							
Client ID: EWC-B-02:12.25	Batch ID: 7971		Analysis Date: 6/30/2014	SeqNo: 311001							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	50.6	0.0852	42.58	2.227	114	75	125	52.21	3.08	30	
Cadmium	2.37	0.170	2.129	0.06856	108	75	125	2.326	1.84	30	
Chromium	65.4	0.0852	42.58	14.42	120	75	125	66.09	0.983	30	
Lead	26.1	0.170	21.29	2.851	109	75	125	27.90	6.79	30	

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits



Work Order: 1406291
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Mercury by EPA Method 7471

Sample ID: MB-7963	SampType: MBLK	Units: mg/Kg	Prep Date: 6/27/2014	RunNo: 15316							
Client ID: MBLKS	Batch ID: 7963		Analysis Date: 6/30/2014	SeqNo: 310683							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury ND 0.250

Sample ID: LCS-7963	SampType: LCS	Units: mg/Kg	Prep Date: 6/27/2014	RunNo: 15316							
Client ID: LCSS	Batch ID: 7963		Analysis Date: 6/30/2014	SeqNo: 310684							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.578 0.250 0.5000 0 116 80 120

Sample ID: 1406267-001ADUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 6/27/2014	RunNo: 15316							
Client ID: BATCH	Batch ID: 7963		Analysis Date: 6/30/2014	SeqNo: 310686							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury ND 0.257 0 20

Sample ID: 1406267-001AMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 6/27/2014	RunNo: 15316							
Client ID: BATCH	Batch ID: 7963		Analysis Date: 6/30/2014	SeqNo: 310687							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.587 0.257 0.5142 0.02544 109 70 130

Sample ID: 1406267-001AMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 6/27/2014	RunNo: 15316							
Client ID: BATCH	Batch ID: 7963		Analysis Date: 6/30/2014	SeqNo: 310688							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.563 0.248 0.4955 0.02544 108 70 130 0.5873 4.23 20

Qualifiers: B Analyte detected in the associated Method Blank
 H Holding times for preparation or analysis exceeded
 R RPD outside accepted recovery limits
 D Dilution was required
 J Analyte detected below quantitation limits
 RL Reporting Limit
 E Value above quantitation range
 ND Not detected at the Reporting Limit
 S Spike recovery outside accepted recovery limits

Work Order: 1406291
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Sample ID: 1406256-001ADUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 6/27/2014	RunNo: 15315							
Client ID: BATCH	Batch ID: 7961		Analysis Date: 6/29/2014	SeqNo: 310640							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Diesel (Fuel Oil)	ND	20.6						0		30	
Heavy Oil	ND	51.6						0		30	
Surr: 2-Fluorobiphenyl	16.4		20.65		79.4	50	150		0		
Surr: o-Terphenyl	16.8		20.65		81.2	50	150		0		

Sample ID: LCS7961	SampType: LCS	Units: mg/Kg	Prep Date: 6/29/2014	RunNo: 15315							
Client ID: LCSS	Batch ID: 7961		Analysis Date: 6/29/2014	SeqNo: 310660							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Diesel (Fuel Oil)	451	20.0	500.0	0	90.2	65	135				
Surr: 2-Fluorobiphenyl	17.6		20.00		87.9	50	150				
Surr: o-Terphenyl	15.7		20.00		78.7	50	150				

Sample ID: MBLK7961	SampType: MBLK	Units: mg/Kg	Prep Date: 6/28/2014	RunNo: 15315							
Client ID: MBLKS	Batch ID: 7961		Analysis Date: 6/28/2014	SeqNo: 310661							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Diesel (Fuel Oil)	ND	20.0									
Heavy Oil	ND	50.0									
Surr: 2-Fluorobiphenyl	15.6		20.00		77.9	50	150				
Surr: o-Terphenyl	15.9		20.00		79.4	50	150				

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits



Date: 7/10/2014

Work Order: 1406291
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Sample ID: MB-7958	SampType: MBLK	Units: µg/Kg	Prep Date: 6/27/2014	RunNo: 15320							
Client ID: MBLKS	Batch ID: 7958		Analysis Date: 6/27/2014	SeqNo: 310748							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Naphthalene	ND	50.0									
2-Methylnaphthalene	ND	50.0									
1-Methylnaphthalene	ND	50.0									
Acenaphthylene	ND	50.0									
Acenaphthene	ND	50.0									
Fluorene	ND	50.0									
Phenanthrene	ND	50.0									
Anthracene	ND	50.0									
Fluoranthene	ND	50.0									
Pyrene	ND	50.0									
Benz(a)anthracene	ND	50.0									
Chrysene	ND	50.0									
Benzo(b)fluoranthene	ND	50.0									
Benzo(k)fluoranthene	ND	50.0									
Benzo(a)pyrene	ND	50.0									
Indeno(1,2,3-cd)pyrene	ND	50.0									
Dibenz(a,h)anthracene	ND	50.0									
Benzo(g,h,i)perylene	ND	50.0									
Surr: 2-Fluorobiphenyl	477		500.0		95.5	42.7	132				
Surr: Terphenyl-d14 (surr)	601		500.0		120	48.8	157				

Sample ID: 1406284-001ADUP	SampType: DUP	Units: µg/Kg-dry	Prep Date: 6/27/2014	RunNo: 15320							
Client ID: BATCH	Batch ID: 7958		Analysis Date: 6/27/2014	SeqNo: 310751							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Naphthalene	ND	54.9						0		30	
2-Methylnaphthalene	ND	54.9						0		30	
1-Methylnaphthalene	ND	54.9						0		30	

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits

Work Order: 1406291
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Sample ID: 1406284-001ADUP	SampType: DUP	Units: µg/Kg-dry	Prep Date: 6/27/2014	RunNo: 15320							
Client ID: BATCH	Batch ID: 7958		Analysis Date: 6/27/2014	SeqNo: 310751							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Acenaphthylene	ND	54.9						0		30	
Acenaphthene	ND	54.9						0		30	
Fluorene	ND	54.9						0		30	
Phenanthrene	ND	54.9						0		30	
Anthracene	ND	54.9						0		30	
Fluoranthene	ND	54.9						0		30	
Pyrene	ND	54.9						0		30	
Benz(a)anthracene	ND	54.9						0		30	
Chrysene	ND	54.9						0		30	
Benzo(b)fluoranthene	ND	54.9						0		30	
Benzo(k)fluoranthene	ND	54.9						0		30	
Benzo(a)pyrene	59.8	54.9						59.03	1.23	30	
Indeno(1,2,3-cd)pyrene	ND	54.9						0		30	
Dibenz(a,h)anthracene	ND	54.9						0		30	
Benzo(g,h,i)perylene	ND	54.9						0		30	
Surr: 2-Fluorobiphenyl	484		548.9		88.3	42.7	132		0		
Surr: Terphenyl-d14 (surr)	661		548.9		120	48.8	157		0		

Sample ID: 1406284-002AMS	SampType: MS	Units: µg/Kg-dry	Prep Date: 6/27/2014	RunNo: 15320							
Client ID: BATCH	Batch ID: 7958		Analysis Date: 6/27/2014	SeqNo: 310753							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	1,090	53.4	1,068	0	103	42.9	138				
2-Methylnaphthalene	1,140	53.4	1,068	0	107	42.8	151				
1-Methylnaphthalene	1,230	53.4	1,068	0	116	41.6	148				
Acenaphthylene	1,280	53.4	1,068	0	120	32.6	160				
Acenaphthene	1,170	53.4	1,068	0	110	46.3	142				
Fluorene	1,190	53.4	1,068	0	112	43.4	153				

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits



Work Order: 1406291
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Sample ID: 1406284-002AMS	SampType: MS	Units: µg/Kg-dry	Prep Date: 6/27/2014	RunNo: 15320							
Client ID: BATCH	Batch ID: 7958		Analysis Date: 6/27/2014	SeqNo: 310753							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Phenanthrene	1,270	53.4	1,068	0	118	45.5	140				
Anthracene	1,270	53.4	1,068	0	119	32.6	160				
Fluoranthene	1,400	53.4	1,068	0	131	44.6	161				
Pyrene	1,380	53.4	1,068	0	129	48.3	158				
Benz(a)anthracene	1,390	53.4	1,068	0	130	57.5	169				
Chrysene	1,260	53.4	1,068	0	118	45.2	146				
Benzo(b)fluoranthene	1,530	53.4	1,068	0	143	42.2	168				
Benzo(k)fluoranthene	1,380	53.4	1,068	0	129	48	161				
Benzo(a)pyrene	1,370	53.4	1,068	60.38	123	34.4	179				
Indeno(1,2,3-cd)pyrene	1,140	53.4	1,068	0	106	41.1	165				
Dibenz(a,h)anthracene	1,050	53.4	1,068	0	98.3	38.1	166				
Benzo(g,h,i)perylene	1,100	53.4	1,068	0	103	45.6	157				
Surr: 2-Fluorobiphenyl	496		533.8		93.0	42.7	132				
Surr: Terphenyl-d14 (surr)	641		533.8		120	48.8	157				

Sample ID: LCS-7958	SampType: LCS	Units: µg/Kg	Prep Date: 6/27/2014	RunNo: 15320							
Client ID: LCSS	Batch ID: 7958		Analysis Date: 6/27/2014	SeqNo: 310776							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Naphthalene	1,120	50.0	1,000	0	112	61.6	125				
2-Methylnaphthalene	1,170	50.0	1,000	0	117	58.2	129				
1-Methylnaphthalene	1,240	50.0	1,000	0	124	56.4	132				
Acenaphthylene	1,300	50.0	1,000	0	130	52.2	133				
Acenaphthene	1,180	50.0	1,000	0	118	54	131				
Fluorene	1,160	50.0	1,000	0	116	53.4	131				
Phenanthrene	1,200	50.0	1,000	0	120	55.6	128				
Anthracene	1,150	50.0	1,000	0	115	51	132				
Fluoranthene	1,210	50.0	1,000	0	121	48.4	134				

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits



Work Order: 1406291
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Sample ID: LCS-7958	SampType: LCS	Units: µg/Kg	Prep Date: 6/27/2014	RunNo: 15320							
Client ID: LCSS	Batch ID: 7958		Analysis Date: 6/27/2014	SeqNo: 310776							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Pyrene	1,240	50.0	1,000	0	124	48.6	135				
Benz(a)anthracene	1,150	50.0	1,000	0	115	41.9	136				
Chrysene	1,280	50.0	1,000	0	128	51.4	135				
Benzo(b)fluoranthene	1,190	50.0	1,000	0	119	39.7	137				
Benzo(k)fluoranthene	1,240	50.0	1,000	0	124	45.7	138				
Benzo(a)pyrene	1,190	50.0	1,000	0	119	45.3	135				
Indeno(1,2,3-cd)pyrene	945	50.0	1,000	0	94.5	45.4	137				
Dibenz(a,h)anthracene	901	50.0	1,000	0	90.1	45.8	134				
Benzo(g,h,i)perylene	995	50.0	1,000	0	99.5	49.3	134				
Surr: 2-Fluorobiphenyl	504		500.0		101	42.7	132				
Surr: Terphenyl-d14 (surr)	568		500.0		114	48.8	157				

Qualifiers:	B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
	R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits

Work Order: 1406291
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Pentachlorophenol by EPA 8151A

Sample ID: MB-8026	SampType: MBLK	Units: mg/Kg	Prep Date: 7/3/2014	RunNo: 15525							
Client ID: MBLKS	Batch ID: 8026		Analysis Date: 7/9/2014	SeqNo: 314233							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Pentachlorophenol	ND	0.0200									
Surr: 2,4-Dichlorophenylacetic acid	2.37		2.000		118	65	135				

Sample ID: LCS-8026	SampType: LCS	Units: mg/Kg	Prep Date: 7/3/2014	RunNo: 15525							
Client ID: LCSS	Batch ID: 8026		Analysis Date: 7/9/2014	SeqNo: 314234							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Pentachlorophenol	0.847	0.0200	1.000	0	84.7	21.4	135				
Surr: 2,4-Dichlorophenylacetic acid	1.81		2.000		90.3	65	135				

Sample ID: 1406291-001ADUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 7/3/2014	RunNo: 15525							
Client ID: EWC-B-02:12.25	Batch ID: 8026		Analysis Date: 7/9/2014	SeqNo: 314236							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Pentachlorophenol	0.0502	0.0230						0.04341	14.5	30	
Surr: 2,4-Dichlorophenylacetic acid	1.50		2.299		65.2	65	135		0		

Sample ID: 1407039-001AMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 7/3/2014	RunNo: 15525							
Client ID: BATCH	Batch ID: 8026		Analysis Date: 7/9/2014	SeqNo: 314239							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Pentachlorophenol	6.01	0.0203	5.083	0.05119	117	28.2	156				
Surr: 2,4-Dichlorophenylacetic acid	2.49		2.033		123	65	135				

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits

Work Order: 1406291
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Gasoline by NWTPH-Gx

Sample ID: LCS-R15325	SampType: LCS	Units: mg/Kg	Prep Date: 6/29/2014	RunNo: 15325							
Client ID: LCSS	Batch ID: R15325		Analysis Date: 6/29/2014	SeqNo: 310878							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	28.9	5.00	25.00	0	116	65	135				
Surr: Toluene-d8	2.50		2.500		100	65	135				
Surr: 4-Bromofluorobenzene	2.88		2.500		115	65	135				

Sample ID: MB-R15325	SampType: MBLK	Units: mg/Kg	Prep Date: 6/29/2014	RunNo: 15325							
Client ID: MBLKS	Batch ID: R15325		Analysis Date: 6/29/2014	SeqNo: 310879							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	ND	5.00									
Surr: Toluene-d8	2.50		2.500		100	65	135				
Surr: 4-Bromofluorobenzene	2.46		2.500		98.5	65	135				

Sample ID: 1406278-001BDUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 6/27/2014	RunNo: 15325							
Client ID: BATCH	Batch ID: R15325		Analysis Date: 6/30/2014	SeqNo: 310958							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	ND	5.28						0		30	
Surr: Toluene-d8	2.68		2.639		102	65	135		0		
Surr: 4-Bromofluorobenzene	2.88		2.639		109	65	135		0		

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits



Work Order: 1406291
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260

Sample ID: 1406278-001BDUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 6/27/2014	RunNo: 15324							
Client ID: BATCH	Batch ID: 7957		Analysis Date: 6/30/2014	SeqNo: 310848							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	ND	0.0211						0		30	
Toluene	ND	0.0211						0		30	
Ethylbenzene	ND	0.0317						0		30	
m,p-Xylene	ND	0.0211						0		30	
o-Xylene	ND	0.0211						0		30	
Surr: Dibromofluoromethane	2.57		2.639		97.4	63.7	129		0		
Surr: Toluene-d8	2.50		2.639		94.7	61.4	128		0		
Surr: 1-Bromo-4-fluorobenzene	2.43		2.639		92.0	63.1	141		0		

Sample ID: 1406279-001BMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 6/27/2014	RunNo: 15324							
Client ID: BATCH	Batch ID: 7957		Analysis Date: 6/30/2014	SeqNo: 310850							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	1.16	0.0223	1.115	0	104	63.5	133				
Toluene	1.10	0.0223	1.115	0	98.8	63.4	132				
Ethylbenzene	1.13	0.0334	1.115	0	102	54.5	134				
m,p-Xylene	2.30	0.0223	2.229	0	103	53.1	132				
o-Xylene	1.14	0.0223	1.115	0	103	53.3	139				
Surr: Dibromofluoromethane	2.89		2.786		104	63.7	129				
Surr: Toluene-d8	2.82		2.786		101	61.4	128				
Surr: 1-Bromo-4-fluorobenzene	2.96		2.786		106	63.1	141				

Sample ID: LCS-7957	SampType: LCS	Units: mg/Kg	Prep Date: 6/27/2014	RunNo: 15324							
Client ID: LCSS	Batch ID: 7957		Analysis Date: 6/29/2014	SeqNo: 310867							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	1.02	0.0200	1.000	0	102	74.6	124				
Toluene	0.962	0.0200	1.000	0	96.2	78.4	122				

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits



Work Order: 1406291
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260

Sample ID: LCS-7957	SampType: LCS	Units: mg/Kg				Prep Date: 6/27/2014	RunNo: 15324				
Client ID: LCSS	Batch ID: 7957					Analysis Date: 6/29/2014	SeqNo: 310867				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Ethylbenzene	0.985	0.0300	1.000	0	98.5	74	129				
m,p-Xylene	2.02	0.0200	2.000	0	101	79.8	128				
o-Xylene	0.991	0.0200	1.000	0	99.1	72.7	124				
Surr: Dibromofluoromethane	2.54		2.500		101	63.7	129				
Surr: Toluene-d8	2.49		2.500		99.7	61.4	128				
Surr: 1-Bromo-4-fluorobenzene	2.61		2.500		104	63.1	141				

Sample ID: MB-7957	SampType: MBLK	Units: mg/Kg				Prep Date: 6/27/2014	RunNo: 15324				
Client ID: MBLKS	Batch ID: 7957					Analysis Date: 6/29/2014	SeqNo: 310868				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	ND	0.0200									
Toluene	ND	0.0200									
Ethylbenzene	ND	0.0300									
m,p-Xylene	ND	0.0200									
o-Xylene	ND	0.0200									
Surr: Dibromofluoromethane	2.32		2.500		93.0	63.7	129				
Surr: Toluene-d8	2.67		2.500		107	61.4	128				
Surr: 1-Bromo-4-fluorobenzene	2.07		2.500		82.9	63.1	141				

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits



Sample Log-In Check List

Client Name: SW	Work Order Number: 1406291
Logged by: Clare Griggs	Date Received: 6/27/2014 12:00:00 PM

Chain of Custody

1. Is Chain of Custody complete? Yes No Not Present
2. How was the sample delivered? Courier

Log In

3. Coolers are present? Yes No NA
4. Shipping container/cooler in good condition? Yes No
5. Custody seals intact on shipping container/cooler? Yes No Not Required
6. Was an attempt made to cool the samples? Yes No NA
7. Were all coolers received at a temperature of >0°C to 10.0°C? Yes No NA
8. Sample(s) in proper container(s)? Yes No
9. Sufficient sample volume for indicated test(s)? Yes No
10. Are samples properly preserved? Yes No
11. Was preservative added to bottles? Yes No NA
12. Is the headspace in the VOA vials? Yes No NA
13. Did all samples containers arrive in good condition(unbroken)? Yes No
14. Does paperwork match bottle labels? Yes No
15. Are matrices correctly identified on Chain of Custody? Yes No
16. Is it clear what analyses were requested? Yes No
17. Were all holding times able to be met? Yes No

Special Handling (if applicable)

18. Was client notified of all discrepancies with this order? Yes No NA

Person Notified:	<input type="text"/>	Date:	<input type="text"/>
By Whom:	<input type="text"/>	Via:	<input type="checkbox"/> eMail <input type="checkbox"/> Phone <input type="checkbox"/> Fax <input type="checkbox"/> In Person
Regarding:	<input type="text"/>		
Client Instructions:	<input type="text"/>		

19. Additional remarks:

Item Information

Item #	Temp °C	Condition
Cooler	4.9	Good
Sample	6.0	Good



Fremont

3600 Fremont Ave. N.
Seattle, WA 98103

Tel: 206-352-3790
Fax: 206-352-7178

Date: 1/26/14

Page: 1

of 1

Laboratory Project No (Internal): 1400291

Chain of Custody Record

Client: S KANAKA & WILSON Project Name: Valina ENIC

Address: 400 N 37th St Suite 100 Location: B-02 (East side 1-82)

City, State, ZIP: Seattle, WA 98103 Tel: 206-352-8704 Collected by: SPW Stephanie Williams

Reports To (PM): Bryan R. Zwick Fax: _____ Email: SPW@SKWWilson.com Project No: SA-1-2-1400-006

* Matrix Codes: A = Air, AQ = Aquifer, S = Soil, SQ = Sediment, ST = Storm, W = Water, DW = Drinking Water, GW = Ground Water, WW = Waste Water

Sample Name	Sample Date	Sample Time	Sample Type (Matrix)	<input type="checkbox"/> VOC (EPA 8260) <input type="checkbox"/> SVOC <input type="checkbox"/> BTEX <input type="checkbox"/> Gasoline Range Organics (GX) <input type="checkbox"/> Hydrocarbon Identification (HID) <input type="checkbox"/> Diesel/heavy oil range organics (HX) <input type="checkbox"/> SEM VOC (EPA 8270) SIM <input type="checkbox"/> PAH (EPA 8270) SIM <input type="checkbox"/> PCBs (EPA 8082) <input type="checkbox"/> Metals ** (Re20/200.9) <input type="checkbox"/> Total (T) / Dissolved (D) <input type="checkbox"/> Anion (AG) *** <input type="checkbox"/> EOB (EQU) <input type="checkbox"/> PAHs (EQU)	<input type="checkbox"/> Pesticides <input type="checkbox"/> PCBs <input type="checkbox"/> Dioxins/Furans <input type="checkbox"/> PCBs (EQU)	Comments/Depth
1 SW-02-02-12.25 (802)	1/24	12:45				check with Ed. Probe for Fall list
2 SW-02-02-12.25 (40ml)	1/24	12:45				check with Ed. Probe for Fall list
3 SW-02-02-12.25 (40ml)	1/24	12:45				check with Ed. Probe for Fall list
4						
5						
6						
7						
8						
9						
10						

** Metals Analysis (Circle): MTCAS REMAINS Priority Pollutants TAL Analytical: Ag Al As B Ba Be Cd Co Cr Cu Fe Mg K Mn Mo Na Ni Pb Sb Se Sr Sn Ti U V Zn - SEE ED

*** Anions (Circle): Nitrate Nitrite Chloride Sulfate Bromide C Phosphate Fluoride Nitrate-Nitrite - SEE ED

Sample Disposal: Return to Client Disposal by Lab (A on any environmental sample site including silver-109ml) - SEE ED

Requisitioned: Stephanie Williams Date/Time: 1/26/14 9:15 Received: [Signature] Date/Time: 1/26/14 12:00

Requisitioned: [Signature] Date/Time: _____ Received: [Signature] Date/Time: _____

Printed: 1/26/14 11:51 AM



3600 Fremont Ave. N.
Seattle, WA 98103
T: (206) 352-3790
F: (206) 352-7178
info@fremontanalytical.com

Shannon & Wilson
Ed Ptak
400 N. 34th Street, Suite 100
Seattle, WA 98103

RE: Yakima EWC
Lab ID: 1407039

July 11, 2014

Attention Ed Ptak:

Fremont Analytical, Inc. received 2 sample(s) on 7/3/2014 for the analyses presented in the following report.

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.
Gasoline (NWTPH-Gx) & BTEX (EPA Method 8021B)
Mercury by EPA Method 7471
Pentachlorophenol by EPA 8151A
Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)
Sample Moisture (Percent Moisture)
Total Metals by EPA Method 6020
Volatile Organic Compounds by EPA Method 8260

This report consists of the following:

- Case Narrative
- Analytical Results
- Applicable Quality Control Summary Reports
- Chain of Custody

All analyses were performed consistent with the Quality Assurance program of Fremont Analytical, Inc. Please contact the laboratory if you should have any questions about the results.

Thank you for using Fremont Analytical.

Sincerely,

A handwritten signature in black ink, appearing to read "M. Dee".

Michael Dee
Sr. Chemist / Principal



Date: 07/11/2014

CLIENT: Shannon & Wilson
Project: Yakima EWC
Lab Order: 1407039

Work Order Sample Summary

Lab Sample ID	Client Sample ID	Date/Time Collected	Date/Time Received
1407039-001	EWC-B-03:12.0	06/26/2014 4:30 PM	07/03/2014 11:00 AM
1407039-002	EWC-B-06:24.0	07/02/2014 8:30 AM	07/03/2014 11:00 AM

Note: If no "Time Collected" is supplied, a default of 12:00AM is assigned

CLIENT: Shannon & Wilson

Project: Yakima EWC

I. SAMPLE RECEIPT:

Samples receipt information is recorded on the attached Sample Receipt Checklist.

II. GENERAL REPORTING COMMENTS:

Results are reported on a wet weight basis unless dry-weight correction is denoted in the units field on the analytical report ("mg/kg-dry" or "ug/kg-dry").

Matrix Spike (MS) and MS Duplicate (MSD) samples are tested from an analytical batch of "like" matrix to check for possible matrix effect. The MS and MSD will provide site specific matrix data only for those samples which are spiked by the laboratory. The sample chosen for spike purposes may or may not have been a sample submitted in this sample delivery group. The validity of the analytical procedures for which data is reported in this analytical report is determined by the Laboratory Control Sample (LCS) and the Method Blank (MB). The LCS and the MB are processed with the samples and the MS/MSD to ensure method criteria are achieved throughout the entire analytical process.

III. ANALYSES AND EXCEPTIONS:

Exceptions associated with this report will be footnoted in the analytical results page(s) or the quality control summary page(s) and/or noted below.



Analytical Report

WO#: 1407039

Date Reported: 7/11/2014

Client: Shannon & Wilson

Collection Date: 6/26/2014 4:30:00 PM

Project: Yakima EWC

Lab ID: 1407039-001

Matrix: Soil

Client Sample ID: EWC-B-03:12.0

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Pentachlorophenol by EPA 8151A

Batch ID: 8026

Analyst: MD

Pentachlorophenol	0.0512	0.0192		mg/Kg-dry	1	7/9/2014 7:28:00 PM
Surr: 2,4-Dichlorophenylacetic acid	96.7	65-135		%REC	1	7/9/2014 7:28:00 PM

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Batch ID: 8018

Analyst: EC

Diesel (Fuel Oil)	ND	18.2		mg/Kg-dry	1	7/5/2014 12:08:00 AM
Heavy Oil	ND	45.5		mg/Kg-dry	1	7/5/2014 12:08:00 AM
Surr: 2-Fluorobiphenyl	97.3	50-150		%REC	1	7/5/2014 12:08:00 AM
Surr: o-Terphenyl	93.9	50-150		%REC	1	7/5/2014 12:08:00 AM

Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Batch ID: 8022

Analyst: NG

Naphthalene	ND	49.0		µg/Kg-dry	1	7/3/2014 8:24:00 PM
2-Methylnaphthalene	ND	49.0		µg/Kg-dry	1	7/3/2014 8:24:00 PM
1-Methylnaphthalene	ND	49.0		µg/Kg-dry	1	7/3/2014 8:24:00 PM
Acenaphthylene	ND	49.0		µg/Kg-dry	1	7/3/2014 8:24:00 PM
Acenaphthene	ND	49.0		µg/Kg-dry	1	7/3/2014 8:24:00 PM
Fluorene	ND	49.0		µg/Kg-dry	1	7/3/2014 8:24:00 PM
Phenanthrene	ND	49.0		µg/Kg-dry	1	7/3/2014 8:24:00 PM
Anthracene	ND	49.0		µg/Kg-dry	1	7/3/2014 8:24:00 PM
Fluoranthene	ND	49.0		µg/Kg-dry	1	7/3/2014 8:24:00 PM
Pyrene	ND	49.0		µg/Kg-dry	1	7/3/2014 8:24:00 PM
Benz(a)anthracene	ND	49.0		µg/Kg-dry	1	7/3/2014 8:24:00 PM
Chrysene	ND	49.0		µg/Kg-dry	1	7/3/2014 8:24:00 PM
Benzo(b)fluoranthene	ND	49.0		µg/Kg-dry	1	7/3/2014 8:24:00 PM
Benzo(k)fluoranthene	ND	49.0		µg/Kg-dry	1	7/3/2014 8:24:00 PM
Benzo(a)pyrene	ND	49.0		µg/Kg-dry	1	7/3/2014 8:24:00 PM
Indeno(1,2,3-cd)pyrene	ND	49.0		µg/Kg-dry	1	7/3/2014 8:24:00 PM
Dibenz(a,h)anthracene	ND	49.0		µg/Kg-dry	1	7/3/2014 8:24:00 PM
Benzo(g,h,i)perylene	ND	49.0		µg/Kg-dry	1	7/3/2014 8:24:00 PM
Surr: 2-Fluorobiphenyl	112	42.7-132		%REC	1	7/3/2014 8:24:00 PM
Surr: Terphenyl-d14 (surr)	143	48.8-157		%REC	1	7/3/2014 8:24:00 PM

Qualifiers: B Analyte detected in the associated Method Blank
 E Value above quantitation range
 J Analyte detected below quantitation limits
 RL Reporting Limit

D Dilution was required
 H Holding times for preparation or analysis exceeded
 ND Not detected at the Reporting Limit
 S Spike recovery outside accepted recovery limits



Analytical Report

WO#: 1407039

Date Reported: 7/11/2014

Client: Shannon & Wilson

Collection Date: 6/26/2014 4:30:00 PM

Project: Yakima EWC

Lab ID: 1407039-001

Matrix: Soil

Client Sample ID: EWC-B-03:12.0

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Gasoline (NWTPH-Gx) & BTEX (EPA Method 8021B)

Batch ID: 8058

Analyst: BC

Gasoline	ND	4.53		mg/Kg-dry	1	7/9/2014 4:32:00 PM
Surr: 1,4-Difluorobenzene	116	65-135		%REC	1	7/9/2014 4:32:00 PM
Surr: 4-Bromofluorobenzene	115	65-135		%REC	1	7/9/2014 4:32:00 PM

Volatile Organic Compounds by EPA Method 8260

Batch ID: 8023

Analyst: GH

Benzene	ND	0.0181		mg/Kg-dry	1	7/6/2014 6:24:00 PM
Toluene	ND	0.0181		mg/Kg-dry	1	7/6/2014 6:24:00 PM
Ethylbenzene	ND	0.0272		mg/Kg-dry	1	7/6/2014 6:24:00 PM
m,p-Xylene	ND	0.0181		mg/Kg-dry	1	7/6/2014 6:24:00 PM
o-Xylene	ND	0.0181		mg/Kg-dry	1	7/6/2014 6:24:00 PM
Surr: Dibromofluoromethane	82.3	63.7-129		%REC	1	7/6/2014 6:24:00 PM
Surr: Toluene-d8	104	61.4-128		%REC	1	7/6/2014 6:24:00 PM
Surr: 1-Bromo-4-fluorobenzene	93.8	63.1-141		%REC	1	7/6/2014 6:24:00 PM

Mercury by EPA Method 7471

Batch ID: 8025

Analyst: MW

Mercury	ND	0.256		mg/Kg-dry	1	7/3/2014 3:46:10 PM
---------	----	-------	--	-----------	---	---------------------

Total Metals by EPA Method 6020

Batch ID: 8024

Analyst: TN

Arsenic	1.99	0.0819		mg/Kg-dry	1	7/3/2014 3:38:05 PM
Cadmium	ND	0.164		mg/Kg-dry	1	7/3/2014 3:38:05 PM
Chromium	11.2	0.0819		mg/Kg-dry	1	7/3/2014 3:38:05 PM
Lead	1.89	0.164		mg/Kg-dry	1	7/3/2014 3:38:05 PM

Sample Moisture (Percent Moisture)

Batch ID: R15401

Analyst: TK

Percent Moisture	6.05			wt%	1	7/3/2014 12:52:55 PM
------------------	------	--	--	-----	---	----------------------

Qualifiers: B Analyte detected in the associated Method Blank
 E Value above quantitation range
 J Analyte detected below quantitation limits
 RL Reporting Limit

D Dilution was required
 H Holding times for preparation or analysis exceeded
 ND Not detected at the Reporting Limit
 S Spike recovery outside accepted recovery limits



Analytical Report

WO#: 1407039

Date Reported: 7/11/2014

Client: Shannon & Wilson

Collection Date: 7/2/2014 8:30:00 AM

Project: Yakima EWC

Lab ID: 1407039-002

Matrix: Soil

Client Sample ID: EWC-B-06:24.0

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
<u>Pentachlorophenol by EPA 8151A</u>			Batch ID: 8026		Analyst: MD	
Pentachlorophenol	0.0227	0.0211		mg/Kg-dry	1	7/9/2014 7:54:00 PM
Surr: 2,4-Dichlorophenylacetic acid	121	65-135		%REC	1	7/9/2014 7:54:00 PM
<u>Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.</u>			Batch ID: 8018		Analyst: EC	
Diesel (Fuel Oil)	ND	21.2		mg/Kg-dry	1	7/5/2014 12:39:00 AM
Heavy Oil	ND	53.1		mg/Kg-dry	1	7/5/2014 12:39:00 AM
Surr: 2-Fluorobiphenyl	97.0	50-150		%REC	1	7/5/2014 12:39:00 AM
Surr: o-Terphenyl	93.2	50-150		%REC	1	7/5/2014 12:39:00 AM
<u>Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)</u>			Batch ID: 8022		Analyst: NG	
Naphthalene	ND	56.5		µg/Kg-dry	1	7/3/2014 8:49:00 PM
2-Methylnaphthalene	ND	56.5		µg/Kg-dry	1	7/3/2014 8:49:00 PM
1-Methylnaphthalene	ND	56.5		µg/Kg-dry	1	7/3/2014 8:49:00 PM
Acenaphthylene	ND	56.5		µg/Kg-dry	1	7/3/2014 8:49:00 PM
Acenaphthene	ND	56.5		µg/Kg-dry	1	7/3/2014 8:49:00 PM
Fluorene	ND	56.5		µg/Kg-dry	1	7/3/2014 8:49:00 PM
Phenanthrene	ND	56.5		µg/Kg-dry	1	7/3/2014 8:49:00 PM
Anthracene	ND	56.5		µg/Kg-dry	1	7/3/2014 8:49:00 PM
Fluoranthene	ND	56.5		µg/Kg-dry	1	7/3/2014 8:49:00 PM
Pyrene	ND	56.5		µg/Kg-dry	1	7/3/2014 8:49:00 PM
Benz(a)anthracene	ND	56.5		µg/Kg-dry	1	7/3/2014 8:49:00 PM
Chrysene	ND	56.5		µg/Kg-dry	1	7/3/2014 8:49:00 PM
Benzo(b)fluoranthene	ND	56.5		µg/Kg-dry	1	7/3/2014 8:49:00 PM
Benzo(k)fluoranthene	ND	56.5		µg/Kg-dry	1	7/3/2014 8:49:00 PM
Benzo(a)pyrene	ND	56.5		µg/Kg-dry	1	7/3/2014 8:49:00 PM
Indeno(1,2,3-cd)pyrene	ND	56.5		µg/Kg-dry	1	7/3/2014 8:49:00 PM
Dibenz(a,h)anthracene	ND	56.5		µg/Kg-dry	1	7/3/2014 8:49:00 PM
Benzo(g,h,i)perylene	ND	56.5		µg/Kg-dry	1	7/3/2014 8:49:00 PM
Surr: 2-Fluorobiphenyl	110	42.7-132		%REC	1	7/3/2014 8:49:00 PM
Surr: Terphenyl-d14 (surr)	146	48.8-157		%REC	1	7/3/2014 8:49:00 PM

Qualifiers:	B	Analyte detected in the associated Method Blank	D	Dilution was required
	E	Value above quantitation range	H	Holding times for preparation or analysis exceeded
	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits



Analytical Report

WO#: 1407039

Date Reported: 7/11/2014

Client: Shannon & Wilson

Collection Date: 7/2/2014 8:30:00 AM

Project: Yakima EWC

Lab ID: 1407039-002

Matrix: Soil

Client Sample ID: EWC-B-06:24.0

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Gasoline (NWTPH-Gx) & BTEX (EPA Method 8021B)

Batch ID: 8058

Analyst: BC

Gasoline	ND	5.30		mg/Kg-dry	1	7/9/2014 5:06:00 PM
Surr: 1,4-Difluorobenzene	118	65-135		%REC	1	7/9/2014 5:06:00 PM
Surr: 4-Bromofluorobenzene	117	65-135		%REC	1	7/9/2014 5:06:00 PM

Volatile Organic Compounds by EPA Method 8260

Batch ID: 8023

Analyst: GH

Benzene	ND	0.0212		mg/Kg-dry	1	7/6/2014 6:54:00 PM
Toluene	ND	0.0212		mg/Kg-dry	1	7/6/2014 6:54:00 PM
Ethylbenzene	ND	0.0318		mg/Kg-dry	1	7/6/2014 6:54:00 PM
m,p-Xylene	ND	0.0212		mg/Kg-dry	1	7/6/2014 6:54:00 PM
o-Xylene	ND	0.0212		mg/Kg-dry	1	7/6/2014 6:54:00 PM
Surr: Dibromofluoromethane	82.0	63.7-129		%REC	1	7/6/2014 6:54:00 PM
Surr: Toluene-d8	104	61.4-128		%REC	1	7/6/2014 6:54:00 PM
Surr: 1-Bromo-4-fluorobenzene	94.2	63.1-141		%REC	1	7/6/2014 6:54:00 PM

Mercury by EPA Method 7471

Batch ID: 8025

Analyst: MW

Mercury	ND	0.244		mg/Kg-dry	1	7/3/2014 3:47:47 PM
---------	----	-------	--	-----------	---	---------------------

Total Metals by EPA Method 6020

Batch ID: 8024

Analyst: TN

Arsenic	4.09	0.0884		mg/Kg-dry	1	7/3/2014 3:42:07 PM
Cadmium	ND	0.177		mg/Kg-dry	1	7/3/2014 3:42:07 PM
Chromium	27.0	0.0884		mg/Kg-dry	1	7/3/2014 3:42:07 PM
Lead	3.31	0.177		mg/Kg-dry	1	7/3/2014 3:42:07 PM

Sample Moisture (Percent Moisture)

Batch ID: R15401

Analyst: TK

Percent Moisture	13.0			wt%	1	7/3/2014 12:52:55 PM
------------------	------	--	--	-----	---	----------------------

Qualifiers: B Analyte detected in the associated Method Blank
 E Value above quantitation range
 J Analyte detected below quantitation limits
 RL Reporting Limit

D Dilution was required
 H Holding times for preparation or analysis exceeded
 ND Not detected at the Reporting Limit
 S Spike recovery outside accepted recovery limits

Work Order: 1407039
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Total Metals by EPA Method 6020

Sample ID: MB-8024	SampType: MBLK	Units: mg/Kg	Prep Date: 7/3/2014	RunNo: 15411							
Client ID: MBLKS	Batch ID: 8024		Analysis Date: 7/3/2014	SeqNo: 312321							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	ND	0.100									
Cadmium	ND	0.200									
Chromium	ND	0.100									
Lead	ND	0.200									

Sample ID: LCS-8024	SampType: LCS	Units: mg/Kg	Prep Date: 7/3/2014	RunNo: 15411							
Client ID: LCSS	Batch ID: 8024		Analysis Date: 7/3/2014	SeqNo: 312322							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	108	0.100	104.0	0	104	69.5	130.8				
Cadmium	102	0.200	92.80	0	110	73.3	127.2				
Chromium	78.9	0.100	62.90	0	125	67.9	132				
Lead	361	0.200	319.0	0	113	75.9	124.1				

Sample ID: 1407035-001ADUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 7/3/2014	RunNo: 15411							
Client ID: BATCH	Batch ID: 8024		Analysis Date: 7/3/2014	SeqNo: 312326							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	1.46	0.0834						1.372	5.97	30	
Cadmium	ND	0.167						0		30	
Chromium	20.8	0.0834						18.97	9.33	30	
Lead	1.43	0.167						1.503	4.94	30	

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits



Work Order: 1407039
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Total Metals by EPA Method 6020

Sample ID: 1407035-001AMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 7/3/2014	RunNo: 15411							
Client ID: BATCH	Batch ID: 8024		Analysis Date: 7/3/2014	SeqNo: 312328							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	43.3	0.0803	40.16	1.372	104	75	125				
Cadmium	2.38	0.161	2.008	0.05464	116	75	125				
Chromium	68.6	0.0803	40.16	18.97	124	75	125				
Lead	23.2	0.161	20.08	1.503	108	75	125				

Sample ID: 1407035-001AMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 7/3/2014	RunNo: 15411							
Client ID: BATCH	Batch ID: 8024		Analysis Date: 7/3/2014	SeqNo: 312329							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	42.4	0.0822	41.08	1.372	99.8	75	125	43.26	2.06	30	
Cadmium	2.37	0.164	2.054	0.05464	113	75	125	2.382	0.518	30	
Chromium	65.1	0.0822	41.08	18.97	112	75	125	68.65	5.26	30	
Lead	22.5	0.164	20.54	1.503	102	75	125	23.18	2.77	30	

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits



Date: 7/11/2014

Work Order: 1407039
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Mercury by EPA Method 7471

Sample ID: MB-8025	SampType: MBLK	Units: mg/Kg	Prep Date: 7/3/2014	RunNo: 15408							
Client ID: MBLKS	Batch ID: 8025	Analysis Date: 7/3/2014	SeqNo: 312274								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury ND 0.250

Sample ID: LCS-8025	SampType: LCS	Units: mg/Kg	Prep Date: 7/3/2014	RunNo: 15408							
Client ID: LCSS	Batch ID: 8025	Analysis Date: 7/3/2014	SeqNo: 312275								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.526 0.250 0.5000 0 105 80 120

Sample ID: 1407035-001ADUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 7/3/2014	RunNo: 15408							
Client ID: BATCH	Batch ID: 8025	Analysis Date: 7/3/2014	SeqNo: 312277								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury ND 0.259 0 20

Sample ID: 1407035-001AMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 7/3/2014	RunNo: 15408							
Client ID: BATCH	Batch ID: 8025	Analysis Date: 7/3/2014	SeqNo: 312278								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.495 0.232 0.4639 0.005880 106 70 130

Sample ID: 1407035-001AMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 7/3/2014	RunNo: 15408							
Client ID: BATCH	Batch ID: 8025	Analysis Date: 7/3/2014	SeqNo: 312279								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.526 0.240 0.4805 0.005880 108 70 130 0.4955 5.91 20

Qualifiers: B Analyte detected in the associated Method Blank
H Holding times for preparation or analysis exceeded
R RPD outside accepted recovery limits
D Dilution was required
J Analyte detected below quantitation limits
RL Reporting Limit
E Value above quantitation range
ND Not detected at the Reporting Limit
S Spike recovery outside accepted recovery limits

Work Order: 1407039
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Sample ID: 1407030-003ADUP	SampType: DUP	Units: mg/Kg-dry				Prep Date: 7/3/2014	RunNo: 15419				
Client ID: BATCH	Batch ID: 8018					Analysis Date: 7/4/2014	SeqNo: 312428				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	ND	19.1						0		30	
Heavy Oil	ND	47.7						0		30	
Surr: 2-Fluorobiphenyl	18.3		19.09		95.9	50	150		0		
Surr: o-Terphenyl	17.7		19.09		92.8	50	150		0		

Sample ID: 1406256-021ADUP	SampType: DUP	Units: mg/Kg-dry				Prep Date: 7/3/2014	RunNo: 15419				
Client ID: BATCH	Batch ID: 8018					Analysis Date: 7/4/2014	SeqNo: 312435				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	ND	20.1						0		30	
Heavy Oil	ND	50.3						0		30	
Surr: 2-Fluorobiphenyl	20.0		20.12		99.3	50	150		0		
Surr: o-Terphenyl	19.1		20.12		95.2	50	150		0		

Sample ID: LCS8018	SampType: LCS	Units: mg/Kg				Prep Date: 7/4/2014	RunNo: 15419				
Client ID: LCSS	Batch ID: 8018					Analysis Date: 7/4/2014	SeqNo: 312443				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	485	20.0	500.0	0	97.1	65	135				
Surr: 2-Fluorobiphenyl	21.7		20.00		108	50	150				
Surr: o-Terphenyl	18.9		20.00		94.6	50	150				

Sample ID: MBLK8018	SampType: MBLK	Units: mg/Kg				Prep Date: 7/4/2014	RunNo: 15419				
Client ID: MBLKS	Batch ID: 8018					Analysis Date: 7/4/2014	SeqNo: 312444				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	ND	20.0									

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits



Date: 7/11/2014

Work Order: 1407039
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Sample ID: MBLK8018	SampType: MBLK	Units: mg/Kg	Prep Date: 7/4/2014	RunNo: 15419							
Client ID: MBLKS	Batch ID: 8018		Analysis Date: 7/4/2014	SeqNo: 312444							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Heavy Oil	ND	50.0									
Surr: 2-Fluorobiphenyl	19.3		20.00		96.6	50	150				
Surr: o-Terphenyl	18.5		20.00		92.7	50	150				

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits

Work Order: 1407039
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Gasoline (NWTPH-Gx) & BTEX (EPA Method 8021B)

Sample ID: LCS-GX-8058	SampType: LCS	Units: mg/Kg	Prep Date: 7/9/2014	RunNo: 15502							
Client ID: LCSS	Batch ID: 8058		Analysis Date: 7/9/2014	SeqNo: 313809							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	497	5.00	500.0	0	99.4	65	135				
Surr: 1,4-Difluorobenzene	53.9		50.00		108	65	135				
Surr: 4-Bromofluorobenzene	57.0		50.00		114	65	135				

Sample ID: MB-8058	SampType: MBLK	Units: mg/Kg	Prep Date: 7/8/2014	RunNo: 15502							
Client ID: MBLKS	Batch ID: 8058		Analysis Date: 7/9/2014	SeqNo: 313810							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	ND	5.00									
Surr: 1,4-Difluorobenzene	56.8		50.00		114	65	135				
Surr: 4-Bromofluorobenzene	58.1		50.00		116	65	135				

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits

Work Order: 1407039
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Sample ID: MB-8022	SampType: MBLK	Units: µg/Kg	Prep Date: 7/3/2014	RunNo: 15435							
Client ID: MBLKS	Batch ID: 8022		Analysis Date: 7/3/2014	SeqNo: 312708							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	ND	50.0									
2-Methylnaphthalene	ND	50.0									
1-Methylnaphthalene	ND	50.0									
Acenaphthylene	ND	50.0									
Acenaphthene	ND	50.0									
Fluorene	ND	50.0									
Phenanthrene	ND	50.0									
Anthracene	ND	50.0									
Fluoranthene	ND	50.0									
Pyrene	ND	50.0									
Benz(a)anthracene	ND	50.0									
Chrysene	ND	50.0									
Benzo(b)fluoranthene	ND	50.0									
Benzo(k)fluoranthene	ND	50.0									
Benzo(a)pyrene	ND	50.0									
Indeno(1,2,3-cd)pyrene	ND	50.0									
Dibenz(a,h)anthracene	ND	50.0									
Benzo(g,h,i)perylene	ND	50.0									
Surr: 2-Fluorobiphenyl	535		500.0		107	42.7	132				
Surr: Terphenyl-d14 (surr)	716		500.0		143	48.8	157				

Sample ID: LCS-8022	SampType: LCS	Units: µg/Kg	Prep Date: 7/3/2014	RunNo: 15435							
Client ID: LCSS	Batch ID: 8022		Analysis Date: 7/3/2014	SeqNo: 312709							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	2,030	50.0	2,000	0	101	61.6	125				
2-Methylnaphthalene	1,790	50.0	2,000	0	89.7	58.2	129				
1-Methylnaphthalene	1,900	50.0	2,000	0	95.1	56.4	132				

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits

Work Order: 1407039
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Sample ID: LCS-8022	SampType: LCS	Units: µg/Kg				Prep Date: 7/3/2014	RunNo: 15435				
Client ID: LCSS	Batch ID: 8022					Analysis Date: 7/3/2014	SeqNo: 312709				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Acenaphthylene	1,870	50.0	2,000	0	93.6	52.2	133				
Acenaphthene	1,890	50.0	2,000	0	94.4	54	131				
Fluorene	1,900	50.0	2,000	0	95.1	53.4	131				
Phenanthrene	1,840	50.0	2,000	0	92.2	55.6	128				
Anthracene	1,780	50.0	2,000	0	88.8	51	132				
Fluoranthene	1,910	50.0	2,000	0	95.6	48.4	134				
Pyrene	1,860	50.0	2,000	0	93.2	48.6	135				
Benz(a)anthracene	1,960	50.0	2,000	0	98.2	41.9	136				
Chrysene	1,680	50.0	2,000	0	83.8	51.4	135				
Benzo(b)fluoranthene	1,960	50.0	2,000	0	98.1	39.7	137				
Benzo(k)fluoranthene	1,610	50.0	2,000	0	80.6	45.7	138				
Benzo(a)pyrene	1,570	50.0	2,000	0	78.5	45.3	135				
Indeno(1,2,3-cd)pyrene	1,260	50.0	2,000	0	63.1	45.4	137				
Dibenz(a,h)anthracene	1,180	50.0	2,000	0	58.9	45.8	134				
Benzo(g,h,i)perylene	1,370	50.0	2,000	0	68.7	49.3	134				
Surr: 2-Fluorobiphenyl	514		500.0		103	42.7	132				
Surr: Terphenyl-d14 (surr)	675		500.0		135	48.8	157				

Sample ID: 1407035-001ADUP	SampType: DUP	Units: µg/Kg-dry				Prep Date: 7/3/2014	RunNo: 15435				
Client ID: BATCH	Batch ID: 8022					Analysis Date: 7/3/2014	SeqNo: 312710				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	ND	51.1						0		30	
2-Methylnaphthalene	ND	51.1						0		30	
1-Methylnaphthalene	ND	51.1						0		30	
Acenaphthylene	ND	51.1						0		30	
Acenaphthene	ND	51.1						0		30	
Fluorene	ND	51.1						0		30	

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits

Work Order: 1407039
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Sample ID: 1407035-001ADUP	SampType: DUP	Units: µg/Kg-dry	Prep Date: 7/3/2014	RunNo: 15435							
Client ID: BATCH	Batch ID: 8022		Analysis Date: 7/3/2014	SeqNo: 312710							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Phenanthrene	ND	51.1						0		30	
Anthracene	ND	51.1						0		30	
Fluoranthene	ND	51.1						0		30	
Pyrene	ND	51.1						0		30	
Benz(a)anthracene	ND	51.1						0		30	
Chrysene	ND	51.1						0		30	
Benzo(b)fluoranthene	ND	51.1						0		30	
Benzo(k)fluoranthene	ND	51.1						0		30	
Benzo(a)pyrene	ND	51.1						0		30	
Indeno(1,2,3-cd)pyrene	ND	51.1						0		30	
Dibenz(a,h)anthracene	ND	51.1						0		30	
Benzo(g,h,i)perylene	ND	51.1						0		30	
Surr: 2-Fluorobiphenyl	414		511.1		81.1	42.7	132		0		
Surr: Terphenyl-d14 (surr)	534		511.1		105	48.8	157		0		

Sample ID: 1407035-002AMS	SampType: MS	Units: µg/Kg-dry	Prep Date: 7/3/2014	RunNo: 15435							
Client ID: BATCH	Batch ID: 8022		Analysis Date: 7/3/2014	SeqNo: 312787							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Naphthalene	2,080	50.9	2,037	0	102	42.9	138				
2-Methylnaphthalene	1,890	50.9	2,037	0	92.9	42.8	151				
1-Methylnaphthalene	2,030	50.9	2,037	0	99.4	41.6	148				
Acenaphthylene	1,960	50.9	2,037	0	96.3	32.6	160				
Acenaphthene	1,950	50.9	2,037	0	95.7	46.3	142				
Fluorene	1,960	50.9	2,037	0	96.3	43.4	153				
Phenanthrene	2,110	50.9	2,037	52.90	101	45.5	140				
Anthracene	2,030	50.9	2,037	7.258	99.1	32.6	160				
Fluoranthene	2,140	50.9	2,037	47.11	103	44.6	161				

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits

Work Order: 1407039
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT

Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Sample ID: 1407035-002AMS	SampType: MS	Units: µg/Kg-dry	Prep Date: 7/3/2014	RunNo: 15435							
Client ID: BATCH	Batch ID: 8022		Analysis Date: 7/3/2014	SeqNo: 312787							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Pyrene	2,100	50.9	2,037	40.76	101	48.3	158				
Benz(a)anthracene	2,090	50.9	2,037	0	103	57.5	169				
Chrysene	1,740	50.9	2,037	22.85	84.5	45.2	146				
Benzo(b)fluoranthene	2,230	50.9	2,037	0	109	42.2	168				
Benzo(k)fluoranthene	1,930	50.9	2,037	0	94.7	48	161				
Benzo(a)pyrene	1,960	50.9	2,037	46.53	94.2	34.4	179				
Indeno(1,2,3-cd)pyrene	1,800	50.9	2,037	0	88.6	41.1	165				
Dibenz(a,h)anthracene	1,820	50.9	2,037	0	89.6	38.1	166				
Benzo(g,h,i)perylene	1,980	50.9	2,037	0	97.0	45.6	157				
Surr: 2-Fluorobiphenyl	535		509.2		105	42.7	132				
Surr: Terphenyl-d14 (surr)	690		509.2		136	48.8	157				

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits

Work Order: 1407039
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Pentachlorophenol by EPA 8151A

Sample ID: MB-8026	SampType: MBLK	Units: mg/Kg	Prep Date: 7/3/2014	RunNo: 15525							
Client ID: MBLKS	Batch ID: 8026		Analysis Date: 7/9/2014	SeqNo: 314233							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Pentachlorophenol	ND	0.0200									
Surr: 2,4-Dichlorophenylacetic acid	2.37		2.000		118	65	135				

Sample ID: LCS-8026	SampType: LCS	Units: mg/Kg	Prep Date: 7/3/2014	RunNo: 15525							
Client ID: LCSS	Batch ID: 8026		Analysis Date: 7/9/2014	SeqNo: 314234							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Pentachlorophenol	0.847	0.0200	1.000	0	84.7	21.4	135				
Surr: 2,4-Dichlorophenylacetic acid	1.81		2.000		90.3	65	135				

Sample ID: 1406291-001ADUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 7/3/2014	RunNo: 15525							
Client ID: BATCH	Batch ID: 8026		Analysis Date: 7/9/2014	SeqNo: 314236							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Pentachlorophenol	0.0502	0.0230						0.04341	14.5	30	
Surr: 2,4-Dichlorophenylacetic acid	1.50		2.299		65.2	65	135		0		

Sample ID: 1407039-001AMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 7/3/2014	RunNo: 15525							
Client ID: EWC-B-03:12.0	Batch ID: 8026		Analysis Date: 7/9/2014	SeqNo: 314239							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Pentachlorophenol	6.01	0.0203	5.083	0.05119	117	28.2	156				
Surr: 2,4-Dichlorophenylacetic acid	2.49		2.033		123	65	135				

Qualifiers:
B Analyte detected in the associated Method Blank
D Dilution was required
E Value above quantitation range

H Holding times for preparation or analysis exceeded
J Analyte detected below quantitation limits
ND Not detected at the Reporting Limit

R RPD outside accepted recovery limits
RL Reporting Limit
S Spike recovery outside accepted recovery limits



Work Order: 1407039
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260

Sample ID: 1407037-001BDUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 7/3/2014	RunNo: 15418							
Client ID: BATCH	Batch ID: 8023		Analysis Date: 7/6/2014	SeqNo: 312408							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	ND	0.0199						0		30	
Toluene	ND	0.0199						0		30	
Ethylbenzene	ND	0.0299						0		30	
m,p-Xylene	ND	0.0199						0		30	
o-Xylene	ND	0.0199						0		30	
Surr: Dibromofluoromethane	2.03		2.489		81.5	63.7	129		0		
Surr: Toluene-d8	2.55		2.489		102	61.4	128		0		
Surr: 1-Bromo-4-fluorobenzene	2.33		2.489		93.7	63.1	141		0		

Sample ID: 1407037-002BMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 7/3/2014	RunNo: 15418							
Client ID: BATCH	Batch ID: 8023		Analysis Date: 7/6/2014	SeqNo: 312410							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	0.784	0.0216	1.080	0	72.6	63.5	133				
Toluene	0.985	0.0216	1.080	0	91.2	63.4	132				
Ethylbenzene	0.899	0.0324	1.080	0	83.3	54.5	134				
m,p-Xylene	1.78	0.0216	2.159	0	82.5	53.1	132				
o-Xylene	0.897	0.0216	1.080	0	83.1	53.3	139				
Surr: Dibromofluoromethane	2.32		2.699		86.0	63.7	129				
Surr: Toluene-d8	2.95		2.699		109	61.4	128				
Surr: 1-Bromo-4-fluorobenzene	2.79		2.699		103	63.1	141				

Sample ID: LCS-8023	SampType: LCS	Units: mg/Kg	Prep Date: 7/3/2014	RunNo: 15418							
Client ID: LCSS	Batch ID: 8023		Analysis Date: 7/6/2014	SeqNo: 312415							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	0.811	0.0200	1.000	0	81.1	74.6	124				
Toluene	1.04	0.0200	1.000	0	104	67.3	138				

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits

Work Order: 1407039
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260

Sample ID: LCS-8023	SampType: LCS	Units: mg/Kg	Prep Date: 7/3/2014	RunNo: 15418							
Client ID: LCSS	Batch ID: 8023		Analysis Date: 7/6/2014	SeqNo: 312415							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Ethylbenzene	0.952	0.0300	1.000	0	95.2	74	129				
m,p-Xylene	1.93	0.0200	2.000	0	96.5	79.8	128				
o-Xylene	0.955	0.0200	1.000	0	95.5	72.7	124				
Surr: Dibromofluoromethane	2.13		2.500		85.3	63.7	129				
Surr: Toluene-d8	2.75		2.500		110	61.4	128				
Surr: 1-Bromo-4-fluorobenzene	2.57		2.500		103	63.1	141				

Sample ID: MB-8023	SampType: MBLK	Units: mg/Kg	Prep Date: 7/3/2014	RunNo: 15418							
Client ID: MBLKS	Batch ID: 8023		Analysis Date: 7/6/2014	SeqNo: 312416							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	ND	0.0200									
Toluene	ND	0.0200									
Ethylbenzene	ND	0.0300									
m,p-Xylene	ND	0.0200									
o-Xylene	ND	0.0200									
Surr: Dibromofluoromethane	1.95		2.500		78.0	63.7	129				
Surr: Toluene-d8	2.57		2.500		103	61.4	128				
Surr: 1-Bromo-4-fluorobenzene	2.39		2.500		95.4	63.1	141				

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits

Client Name: **SW**
 Logged by: **Clare Griggs**

Work Order Number: **1407039**
 Date Received: **7/3/2014 11:00:00 AM**

Chain of Custody

1. Is Chain of Custody complete? Yes No Not Present
 2. How was the sample delivered? FedEx

Log In

3. Coolers are present? Yes No NA
 4. Shipping container/cooler in good condition? Yes No
 5. Custody seals intact on shipping container/cooler? Yes No Not Required
 6. Was an attempt made to cool the samples? Yes No NA
 7. Were all coolers received at a temperature of >0°C to 10.0°C? Yes No NA
 8. Sample(s) in proper container(s)? Yes No
 9. Sufficient sample volume for indicated test(s)? Yes No
 10. Are samples properly preserved? Yes No
 11. Was preservative added to bottles? Yes No NA
 12. Is the headspace in the VOA vials? Yes No NA
 13. Did all samples containers arrive in good condition(unbroken)? Yes No
 14. Does paperwork match bottle labels? Yes No
 15. Are matrices correctly identified on Chain of Custody? Yes No
 16. Is it clear what analyses were requested? Yes No
 17. Were all holding times able to be met? Yes No

Special Handling (if applicable)

18. Was client notified of all discrepancies with this order? Yes No NA

Person Notified:	<input type="text"/>	Date:	<input type="text"/>
By Whom:	<input type="text"/>	Via:	<input type="checkbox"/> eMail <input type="checkbox"/> Phone <input type="checkbox"/> Fax <input type="checkbox"/> In Person
Regarding:	<input type="text"/>		
Client Instructions:	<input type="text"/>		

19. Additional remarks:

Item Information

Item #	Temp °C	Condition
Cooler	4.2	Good
Sample	1.9	Good



Fremont Analytical

Chain of Custody Record

3600 Fremont Ave N. Seattle, WA 98103

Tel: 206-352-3790 Fax: 206-352-7178

Date: 6/26/2014

Project Name: Step 4 YKIME EUC

Location: B-54W

Collected by: SAW

Project No: 21-1-24690-006

Client: Shannon & Wilson

Address: 400 N 34th St, Suite 100

City, State, Zip: Seattle, WA 98102

Reports To (PM): Brian Reznick

Material Codes: A = Air, AQ = Aquatic, B = Bulk, O = Other, P = Product, S = Soil, SD = Sediment, SL = Solid, W = Water, DW = Drinking Water, GW = Ground Water, WFW = Waste Water

Sample Name: B-54W

Sample Date: 6/26

Sample Time: 16:30

Sample Type (Material): VOC (EPA 8260)

Sample Type (Material): OX/BTEX

Sample Type (Material): BTEX

Sample Type (Material): Gasoline Range Organics (GX)

Sample Type (Material): Hydrocarbon Identification (HCID)

Sample Type (Material): Diesel/Heavy Oil Range Organics (HCO)

Sample Type (Material): SEMI-VOC (EPA 8270)

Sample Type (Material): PAH (EPA 8270 SW)

Sample Type (Material): P/B (EPA 8082)

Sample Type (Material): Metals** (6020/200.5)

Sample Type (Material): Total (T) [Dissolved (D)

Sample Type (Material): Anions (C)***

Sample Type (Material): EDR (8011)

Sample Type (Material): Dx Pesticides/Herbicides

Sample Type (Material): Comments/Depth

Sample Name	Sample Date	Sample Time	Sample Type (Material)	VOC (EPA 8260)	OX/BTEX	BTEX	Gasoline Range Organics (GX)	Hydrocarbon Identification (HCID)	Diesel/Heavy Oil Range Organics (HCO)	SEMI-VOC (EPA 8270)	PAH (EPA 8270 SW)	P/B (EPA 8082)	Metals** (6020/200.5)	Total (T) [Dissolved (D)	Anions (C)***	EDR (8011)	Dx Pesticides/Herbicides	Comments/Depth	
1 BWC-B-03:12.0	6/26	16:30																	
2 BWC-B-03:12.0	6/26	16:30		X															
3 BWC-B-03:12.0	6/26	16:30		X															
4 BWC-B-06:24.0	7/2	8:30								X									
5 BWC-B-06:24.0	7/2	8:30								X									
6 BWC-B-06:24.0	7/2	8:30								X									
7																			
8																			
9																			
10																			

*** Anions (Circle): Nitrate Nitrite Chloride Sulfate Bromide Calcium Phosphate Fluoride Nitrate+Nitrite

Special Remarks:

Relinquish: SAW Date/Time: 7/1/2014 @ 5:55 Received: SAW Date/Time: 7/8/14 1100

Relinquish: SAW Date/Time: 7/1/2014 @ 5:55 Received: SAW Date/Time: 7/8/14 1100

TAT -> SameDay NextDay 2 Day 3 Day STD

please coordinate with the lab in advance

Distribution: White - Lab, Yellow - File, Pink - Originator

www.fremontanalytical.com



3600 Fremont Ave. N.
Seattle, WA 98103
T: (206) 352-3790
F: (206) 352-7178
info@fremontanalytical.com

Shannon & Wilson

Ed Ptak
400 N. 34th Street, Suite 100
Seattle, WA 98103

RE: Yakima EWC

Lab ID: 1407120

July 21, 2014

Attention Ed Ptak:

Fremont Analytical, Inc. received 2 sample(s) on 7/14/2014 for the analyses presented in the following report.

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.
Gasoline by NWTPH-Gx
Mercury by EPA Method 7471
Pentachlorophenol by EPA 8151A
Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)
Sample Moisture (Percent Moisture)
Total Metals by EPA Method 6020
Volatile Organic Compounds by EPA Method 8260

This report consists of the following:

- Case Narrative
- Analytical Results
- Applicable Quality Control Summary Reports
- Chain of Custody

All analyses were performed consistent with the Quality Assurance program of Fremont Analytical, Inc. Please contact the laboratory if you should have any questions about the results.

Thank you for using Fremont Analytical.

Sincerely,

A handwritten signature in black ink, appearing to read "M. Dee".

Michael Dee
Sr. Chemist / Principal



Date: 07/31/2014

CLIENT: Shannon & Wilson
Project: Yakima EWC
Lab Order: 1407120

Work Order Sample Summary

Lab Sample ID	Client Sample ID	Date/Time Collected	Date/Time Received
1407120-001	EWC-B-04:10.0	07/07/2014 4:30 PM	07/14/2014 11:18 AM
1407120-002	EWC-B-05:16.0	07/10/2014 10:50 AM	07/14/2014 11:18 AM

Note: If no "Time Collected" is supplied, a default of 12:00AM is assigned

CLIENT: Shannon & Wilson**Project:** Yakima EWC

I. SAMPLE RECEIPT:

Samples receipt information is recorded on the attached Sample Receipt Checklist.

II. GENERAL REPORTING COMMENTS:

Results are reported on a wet weight basis unless dry-weight correction is denoted in the units field on the analytical report ("mg/kg-dry" or "ug/kg-dry").

Matrix Spike (MS) and MS Duplicate (MSD) samples are tested from an analytical batch of "like" matrix to check for possible matrix effect. The MS and MSD will provide site specific matrix data only for those samples which are spiked by the laboratory. The sample chosen for spike purposes may or may not have been a sample submitted in this sample delivery group. The validity of the analytical procedures for which data is reported in this analytical report is determined by the Laboratory Control Sample (LCS) and the Method Blank (MB). The LCS and the MB are processed with the samples and the MS/MSD to ensure method criteria are achieved throughout the entire analytical process.

III. ANALYSES AND EXCEPTIONS:

Exceptions associated with this report will be footnoted in the analytical results page(s) or the quality control summary page(s) and/or noted below.



Analytical Report

WO#: 1407120

Date Reported: 7/21/2014

Client: Shannon & Wilson

Collection Date: 7/7/2014 4:30:00 PM

Project: Yakima EWC

Lab ID: 1407120-001

Matrix: Soil

Client Sample ID: EWC-B-04:10.0

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Pentachlorophenol by EPA 8151A

Batch ID: 8119

Analyst: DB

Pentachlorophenol	0.152	0.0214		mg/Kg-dry	1	7/17/2014 12:13:00 PM
Surr: 2,4-Dichlorophenylacetic acid	84.2	65-135		%REC	1	7/17/2014 12:13:00 PM

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Batch ID: 8107

Analyst: EC

Diesel (Fuel Oil)	ND	19.9		mg/Kg-dry	1	7/14/2014 6:43:00 PM
Heavy Oil	ND	49.8		mg/Kg-dry	1	7/14/2014 6:43:00 PM
Surr: 2-Fluorobiphenyl	147	50-150		%REC	1	7/14/2014 6:43:00 PM
Surr: o-Terphenyl	122	50-150		%REC	1	7/14/2014 6:43:00 PM

Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Batch ID: 8106

Analyst: NG

Naphthalene	ND	57.9		µg/Kg-dry	1	7/14/2014 10:08:00 PM
2-Methylnaphthalene	ND	57.9		µg/Kg-dry	1	7/14/2014 10:08:00 PM
1-Methylnaphthalene	ND	57.9		µg/Kg-dry	1	7/14/2014 10:08:00 PM
Acenaphthylene	ND	57.9		µg/Kg-dry	1	7/14/2014 10:08:00 PM
Acenaphthene	ND	57.9		µg/Kg-dry	1	7/14/2014 10:08:00 PM
Fluorene	ND	57.9		µg/Kg-dry	1	7/14/2014 10:08:00 PM
Phenanthrene	ND	57.9		µg/Kg-dry	1	7/14/2014 10:08:00 PM
Anthracene	ND	57.9		µg/Kg-dry	1	7/14/2014 10:08:00 PM
Fluoranthene	ND	57.9		µg/Kg-dry	1	7/14/2014 10:08:00 PM
Pyrene	ND	57.9		µg/Kg-dry	1	7/14/2014 10:08:00 PM
Benz(a)anthracene	ND	57.9		µg/Kg-dry	1	7/14/2014 10:08:00 PM
Chrysene	ND	57.9		µg/Kg-dry	1	7/14/2014 10:08:00 PM
Benzo(b)fluoranthene	ND	57.9		µg/Kg-dry	1	7/14/2014 10:08:00 PM
Benzo(k)fluoranthene	ND	57.9		µg/Kg-dry	1	7/14/2014 10:08:00 PM
Benzo(a)pyrene	ND	57.9		µg/Kg-dry	1	7/14/2014 10:08:00 PM
Indeno(1,2,3-cd)pyrene	ND	57.9		µg/Kg-dry	1	7/14/2014 10:08:00 PM
Dibenz(a,h)anthracene	ND	57.9		µg/Kg-dry	1	7/14/2014 10:08:00 PM
Benzo(g,h,i)perylene	ND	57.9		µg/Kg-dry	1	7/14/2014 10:08:00 PM
Surr: 2-Fluorobiphenyl	81.6	42.7-132		%REC	1	7/14/2014 10:08:00 PM
Surr: Terphenyl-d14 (surr)	102	48.8-157		%REC	1	7/14/2014 10:08:00 PM

Qualifiers: B Analyte detected in the associated Method Blank
 E Value above quantitation range
 J Analyte detected below quantitation limits
 RL Reporting Limit

D Dilution was required
 H Holding times for preparation or analysis exceeded
 ND Not detected at the Reporting Limit
 S Spike recovery outside accepted recovery limits



Analytical Report

WO#: 1407120

Date Reported: 7/21/2014

Client: Shannon & Wilson

Collection Date: 7/7/2014 4:30:00 PM

Project: Yakima EWC

Lab ID: 1407120-001

Matrix: Soil

Client Sample ID: EWC-B-04:10.0

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Gasoline by NWTPH-Gx

Batch ID: R15594 Analyst: BC

Gasoline	ND	2.80		mg/Kg-dry	1	7/15/2014 12:04:00 PM
Surr: 4-Bromofluorobenzene	108	65-135		%REC	1	7/15/2014 12:04:00 PM
Surr: Toluene-d8	97.4	65-135		%REC	1	7/15/2014 12:04:00 PM

Volatile Organic Compounds by EPA Method 8260

Batch ID: 8097 Analyst: BC

Benzene	ND	0.0112		mg/Kg-dry	1	7/15/2014 12:04:00 PM
Toluene	ND	0.0112		mg/Kg-dry	1	7/15/2014 12:04:00 PM
Ethylbenzene	ND	0.0168		mg/Kg-dry	1	7/15/2014 12:04:00 PM
m,p-Xylene	ND	0.0112		mg/Kg-dry	1	7/15/2014 12:04:00 PM
o-Xylene	ND	0.0112		mg/Kg-dry	1	7/15/2014 12:04:00 PM
Surr: Dibromofluoromethane	99.4	63.7-129		%REC	1	7/15/2014 12:04:00 PM
Surr: Toluene-d8	97.4	61.4-128		%REC	1	7/15/2014 12:04:00 PM
Surr: 1-Bromo-4-fluorobenzene	96.1	63.1-141		%REC	1	7/15/2014 12:04:00 PM

Mercury by EPA Method 7471

Batch ID: 8110 Analyst: MW

Mercury	ND	0.286		mg/Kg-dry	1	7/16/2014 3:24:42 PM
---------	----	-------	--	-----------	---	----------------------

Total Metals by EPA Method 6020

Batch ID: 8096 Analyst: TN

Arsenic	2.77	0.0918		mg/Kg-dry	1	7/14/2014 4:24:42 PM
Cadmium	ND	0.184		mg/Kg-dry	1	7/14/2014 4:24:42 PM
Chromium	25.3	0.0918		mg/Kg-dry	1	7/14/2014 4:24:42 PM
Lead	2.45	0.184		mg/Kg-dry	1	7/14/2014 4:24:42 PM

Sample Moisture (Percent Moisture)

Batch ID: R15551 Analyst: TK

Percent Moisture	14.3			wt%	1	7/14/2014 9:12:46 AM
------------------	------	--	--	-----	---	----------------------

Qualifiers:	B	Analyte detected in the associated Method Blank	D	Dilution was required
	E	Value above quantitation range	H	Holding times for preparation or analysis exceeded
	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits



Analytical Report

WO#: 1407120

Date Reported: 7/21/2014

Client: Shannon & Wilson

Collection Date: 7/10/2014 10:50:00 AM

Project: Yakima EWC

Lab ID: 1407120-002

Matrix: Soil

Client Sample ID: EWC-B-05:16.0

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Pentachlorophenol by EPA 8151A

Batch ID: 8119

Analyst: DB

Pentachlorophenol	0.144	0.0225		mg/Kg-dry	1	7/17/2014 1:03:00 PM
Surr: 2,4-Dichlorophenylacetic acid	76.2	65-135		%REC	1	7/17/2014 1:03:00 PM

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Batch ID: 8107

Analyst: EC

Diesel (Fuel Oil)	ND	20.1		mg/Kg-dry	1	7/14/2014 7:47:00 PM
Heavy Oil	ND	50.4		mg/Kg-dry	1	7/14/2014 7:47:00 PM
Surr: 2-Fluorobiphenyl	157	50-150	S	%REC	1	7/14/2014 7:47:00 PM
Surr: o-Terphenyl	131	50-150		%REC	1	7/14/2014 7:47:00 PM

NOTES:

S - Outlying surrogate recovery observed - High Bias. Sample was non-detect. No further action required.

Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Batch ID: 8106

Analyst: NG

Naphthalene	ND	54.7		µg/Kg-dry	1	7/14/2014 10:58:00 PM
2-Methylnaphthalene	ND	54.7		µg/Kg-dry	1	7/14/2014 10:58:00 PM
1-Methylnaphthalene	ND	54.7		µg/Kg-dry	1	7/14/2014 10:58:00 PM
Acenaphthylene	ND	54.7		µg/Kg-dry	1	7/14/2014 10:58:00 PM
Acenaphthene	ND	54.7		µg/Kg-dry	1	7/14/2014 10:58:00 PM
Fluorene	ND	54.7		µg/Kg-dry	1	7/14/2014 10:58:00 PM
Phenanthrene	ND	54.7		µg/Kg-dry	1	7/14/2014 10:58:00 PM
Anthracene	ND	54.7		µg/Kg-dry	1	7/14/2014 10:58:00 PM
Fluoranthene	ND	54.7		µg/Kg-dry	1	7/14/2014 10:58:00 PM
Pyrene	ND	54.7		µg/Kg-dry	1	7/14/2014 10:58:00 PM
Benz(a)anthracene	ND	54.7		µg/Kg-dry	1	7/14/2014 10:58:00 PM
Chrysene	ND	54.7		µg/Kg-dry	1	7/14/2014 10:58:00 PM
Benzo(b)fluoranthene	ND	54.7		µg/Kg-dry	1	7/14/2014 10:58:00 PM
Benzo(k)fluoranthene	ND	54.7		µg/Kg-dry	1	7/14/2014 10:58:00 PM
Benzo(a)pyrene	ND	54.7		µg/Kg-dry	1	7/14/2014 10:58:00 PM
Indeno(1,2,3-cd)pyrene	ND	54.7		µg/Kg-dry	1	7/14/2014 10:58:00 PM
Dibenz(a,h)anthracene	ND	54.7		µg/Kg-dry	1	7/14/2014 10:58:00 PM
Benzo(g,h,i)perylene	ND	54.7		µg/Kg-dry	1	7/14/2014 10:58:00 PM
Surr: 2-Fluorobiphenyl	77.2	42.7-132		%REC	1	7/14/2014 10:58:00 PM
Surr: Terphenyl-d14 (surr)	93.8	48.8-157		%REC	1	7/14/2014 10:58:00 PM

Qualifiers: B Analyte detected in the associated Method Blank
 E Value above quantitation range
 J Analyte detected below quantitation limits
 RL Reporting Limit

D Dilution was required
 H Holding times for preparation or analysis exceeded
 ND Not detected at the Reporting Limit
 S Spike recovery outside accepted recovery limits



Analytical Report

WO#: 1407120

Date Reported: 7/21/2014

Client: Shannon & Wilson

Collection Date: 7/10/2014 10:50:00 AM

Project: Yakima EWC

Lab ID: 1407120-002

Matrix: Soil

Client Sample ID: EWC-B-05:16.0

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Gasoline by NWTPH-Gx

Batch ID: R15594 Analyst: BC

Gasoline	ND	3.74		mg/Kg-dry	1	7/15/2014 3:03:00 PM
Surr: 4-Bromofluorobenzene	107	65-135		%REC	1	7/15/2014 3:03:00 PM
Surr: Toluene-d8	98.4	65-135		%REC	1	7/15/2014 3:03:00 PM

Volatile Organic Compounds by EPA Method 8260

Batch ID: 8097 Analyst: BC

Benzene	ND	0.0150		mg/Kg-dry	1	7/15/2014 3:03:00 PM
Toluene	ND	0.0150		mg/Kg-dry	1	7/15/2014 3:03:00 PM
Ethylbenzene	ND	0.0224		mg/Kg-dry	1	7/15/2014 3:03:00 PM
m,p-Xylene	ND	0.0150		mg/Kg-dry	1	7/15/2014 3:03:00 PM
o-Xylene	ND	0.0150		mg/Kg-dry	1	7/15/2014 3:03:00 PM
Surr: Dibromofluoromethane	97.1	63.7-129		%REC	1	7/15/2014 3:03:00 PM
Surr: Toluene-d8	97.3	61.4-128		%REC	1	7/15/2014 3:03:00 PM
Surr: 1-Bromo-4-fluorobenzene	94.9	63.1-141		%REC	1	7/15/2014 3:03:00 PM

Mercury by EPA Method 7471

Batch ID: 8110 Analyst: MW

Mercury	ND	0.282		mg/Kg-dry	1	7/16/2014 3:31:47 PM
---------	----	-------	--	-----------	---	----------------------

Total Metals by EPA Method 6020

Batch ID: 8096 Analyst: TN

Arsenic	3.52	0.0854		mg/Kg-dry	1	7/14/2014 4:28:07 PM
Cadmium	ND	0.171		mg/Kg-dry	1	7/14/2014 4:28:07 PM
Chromium	19.4	0.0854		mg/Kg-dry	1	7/14/2014 4:28:07 PM
Lead	2.13	0.171		mg/Kg-dry	1	7/14/2014 4:28:07 PM

Sample Moisture (Percent Moisture)

Batch ID: R15551 Analyst: TK

Percent Moisture	13.2			wt%	1	7/14/2014 9:12:46 AM
------------------	------	--	--	-----	---	----------------------

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required
E	Value above quantitation range	H	Holding times for preparation or analysis exceeded
J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
RL	Reporting Limit	S	Spike recovery outside accepted recovery limits

Work Order: 1407120
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Total Metals by EPA Method 6020

Sample ID: MB-8096	SampType: MBLK	Units: mg/Kg	Prep Date: 7/14/2014	RunNo: 15572							
Client ID: MBLKS	Batch ID: 8096		Analysis Date: 7/14/2014	SeqNo: 315255							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	ND	0.100									
Cadmium	ND	0.200									
Chromium	ND	0.100									
Lead	ND	0.200									

Sample ID: LCS-8096	SampType: LCS	Units: mg/Kg	Prep Date: 7/14/2014	RunNo: 15572							
Client ID: LCSS	Batch ID: 8096		Analysis Date: 7/14/2014	SeqNo: 315258							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	103	0.100	104.0	0	99.3	69.5	130.8				
Cadmium	91.9	0.200	92.80	0	99.0	73.3	127.2				
Chromium	73.0	0.100	62.90	0	116	67.9	132				
Lead	325	0.200	319.0	0	102	75.9	124.1				

Sample ID: 1407109-001ADUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 7/14/2014	RunNo: 15572							
Client ID: BATCH	Batch ID: 8096		Analysis Date: 7/14/2014	SeqNo: 315258							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	2.40	0.0817						2.928	19.8	30	
Cadmium	ND	0.163						0		30	
Chromium	25.9	0.0817						25.94	0.304	30	
Lead	5.05	0.163						6.146	19.6	30	

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits



Work Order: 1407120
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Total Metals by EPA Method 6020

Sample ID: 1407109-001AMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 7/14/2014	RunNo: 15572							
Client ID: BATCH	Batch ID: 8096	Analysis Date: 7/14/2014	SeqNo: 315263								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	42.8	0.0836	41.79	2.928	95.4	75	125				
Cadmium	2.13	0.167	2.090	0.08323	97.8	75	125				
Chromium	68.8	0.0836	41.79	25.94	103	75	125				
Lead	26.8	0.167	20.90	6.146	98.9	75	125				

Sample ID: 1407109-001AMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 7/14/2014	RunNo: 15572							
Client ID: BATCH	Batch ID: 8096	Analysis Date: 7/14/2014	SeqNo: 315263								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	43.4	0.0817	40.84	2.928	99.2	75	125	42.79	1.52	30	
Cadmium	2.15	0.163	2.042	0.08323	101	75	125	2.127	0.990	30	
Chromium	68.7	0.0817	40.84	25.94	105	75	125	68.79	0.198	30	
Lead	29.6	0.163	20.42	6.146	115	75	125	26.82	9.68	30	

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits



Work Order: 1407120
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Mercury by EPA Method 7471

Sample ID: MB-8110	SampType: MBLK	Units: mg/Kg	Prep Date: 7/16/2014	RunNo: 15616							
Client ID: MBLKS	Batch ID: 8110	Analysis Date: 7/16/2014	SeqNo: 316179								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury ND 0.250

Sample ID: LCS-8110	SampType: LCS	Units: mg/Kg	Prep Date: 7/16/2014	RunNo: 15616							
Client ID: LCSS	Batch ID: 8110	Analysis Date: 7/16/2014	SeqNo: 316180								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.586 0.250 0.5000 0 117 80 120

Sample ID: 1407120-001AMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 7/16/2014	RunNo: 15616							
Client ID: EWC-B-04:10.0	Batch ID: 8110	Analysis Date: 7/16/2014	SeqNo: 316182								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.713 0.280 0.5607 0.06998 115 70 130

Sample ID: 1407120-001AMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 7/16/2014	RunNo: 15616							
Client ID: EWC-B-04:10.0	Batch ID: 8110	Analysis Date: 7/16/2014	SeqNo: 316183								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.672 0.286 0.5717 0.06998 105 70 130 0.7132 5.90 20

Sample ID: 1407120-001ADUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 7/16/2014	RunNo: 15616							
Client ID: EWC-B-04:10.0	Batch ID: 8110	Analysis Date: 7/16/2014	SeqNo: 316184								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury ND 0.275 0 20

Qualifiers: B Analyte detected in the associated Method Blank
 D Dilution was required
 E Value above quantitation range
 H Holding times for preparation or analysis exceeded
 J Analyte detected below quantitation limits
 ND Not detected at the Reporting Limit
 R RPD outside accepted recovery limits
 RL Reporting Limit
 S Spike recovery outside accepted recovery limits

Work Order: 1407120
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Sample ID: 1407120-001ADUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 7/14/2014	RunNo: 15581							
Client ID: EWC-B-04:10.0	Batch ID: 8107		Analysis Date: 7/14/2014	SeqNo: 315457							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Diesel (Fuel Oil)	ND	22.0						0		30	
Heavy Oil	ND	55.0						0		30	
Surr: 2-Fluorobiphenyl	32.3		22.00		147	50	150		0		
Surr: o-Terphenyl	26.9		22.00		122	50	150		0		

Sample ID: LCS-8107A	SampType: LCS	Units: mg/Kg	Prep Date: 7/14/2014	RunNo: 15581							
Client ID: LCSS	Batch ID: 8107		Analysis Date: 7/14/2014	SeqNo: 315478							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Diesel (Fuel Oil)	436	20.0	500.0	0	87.2	65	135				
Surr: 2-Fluorobiphenyl	26.2		20.00		131	50	150				
Surr: o-Terphenyl	20.5		20.00		103	50	150				

Sample ID: MBLK8107	SampType: MBLK	Units: mg/Kg	Prep Date: 7/14/2014	RunNo: 15581							
Client ID: MBLKS	Batch ID: 8107		Analysis Date: 7/14/2014	SeqNo: 315720							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Diesel (Fuel Oil)	ND	20.0									
Heavy Oil	ND	50.0									
Surr: 2-Fluorobiphenyl	19.6		20.00		97.9	50	150				
Surr: o-Terphenyl	19.6		20.00		98.2	50	150				

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits

Work Order: 1407120
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT

Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Sample ID: LCS-8106	SampType: LCS	Units: µg/Kg	Prep Date: 7/14/2014	RunNo: 15582							
Client ID: LCSS	Batch ID: 8106		Analysis Date: 7/14/2014	SeqNo: 315509							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	879	50.0	1,000	0	87.9	61.6	125				
2-Methylnaphthalene	867	50.0	1,000	0	86.7	58.2	129				
1-Methylnaphthalene	841	50.0	1,000	0	84.1	56.4	132				
Acenaphthylene	853	50.0	1,000	0	85.3	52.2	133				
Acenaphthene	870	50.0	1,000	0	87.0	54	131				
Fluorene	873	50.0	1,000	0	87.3	53.4	131				
Phenanthrene	864	50.0	1,000	0	86.4	55.6	128				
Anthracene	865	50.0	1,000	0	86.5	51	132				
Fluoranthene	853	50.0	1,000	0	85.3	48.4	134				
Pyrene	839	50.0	1,000	0	83.9	48.6	135				
Benz(a)anthracene	859	50.0	1,000	0	85.9	41.9	136				
Chrysene	929	50.0	1,000	0	92.9	51.4	135				
Benzo(b)fluoranthene	894	50.0	1,000	0	89.4	39.7	137				
Benzo(k)fluoranthene	859	50.0	1,000	0	85.9	45.7	138				
Benzo(a)pyrene	902	50.0	1,000	0	90.2	45.3	135				
Indeno(1,2,3-cd)pyrene	766	50.0	1,000	0	76.6	45.4	137				
Dibenz(a,h)anthracene	710	50.0	1,000	0	71.0	45.8	134				
Benzo(g,h,i)perylene	727	50.0	1,000	0	72.7	49.3	134				
Surr: 2-Fluorobiphenyl	443		500.0		88.7	42.7	132				
Surr: Terphenyl-d14 (surr)	449		500.0		89.8	48.8	157				

Sample ID: 1407120-001ADUP	SampType: DUP	Units: µg/Kg-dry	Prep Date: 7/14/2014	RunNo: 15582							
Client ID: EWC-B-04:10.0	Batch ID: 8106		Analysis Date: 7/14/2014	SeqNo: 315511							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	ND	55.0						0		30	
2-Methylnaphthalene	ND	55.0						0		30	
1-Methylnaphthalene	ND	55.0						0		30	

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits

Work Order: 1407120
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Acenaphthylene	ND	55.0						0		30	
Acenaphthene	ND	55.0						0		30	
Fluorene	ND	55.0						0		30	
Phenanthrene	ND	55.0						0		30	
Anthracene	ND	55.0						0		30	
Fluoranthene	ND	55.0						0		30	
Pyrene	ND	55.0						0		30	
Benz(a)anthracene	ND	55.0						0		30	
Chrysene	ND	55.0						0		30	
Benzo(b)fluoranthene	ND	55.0						0		30	
Benzo(k)fluoranthene	ND	55.0						0		30	
Benzo(a)pyrene	ND	55.0						0		30	
Indeno(1,2,3-cd)pyrene	ND	55.0						0		30	
Dibenz(a,h)anthracene	ND	55.0						0		30	
Benzo(g,h,i)perylene	ND	55.0						0		30	
Surr: 2-Fluorobiphenyl	479		550.1		87.0	42.7	132		0		
Surr: Terphenyl-d14 (surr)	558		550.1		101	48.8	157		0		

Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	838	52.9	1,058	0	79.2	42.9	138				
2-Methylnaphthalene	867	52.9	1,058	0	81.9	42.8	151				
1-Methylnaphthalene	853	52.9	1,058	0	80.6	41.6	148				
Acenaphthylene	902	52.9	1,058	0	85.2	32.6	160				
Acenaphthene	898	52.9	1,058	0	84.8	46.3	142				
Fluorene	914	52.9	1,058	0	86.4	43.4	153				

Qualifiers:
B Analyte detected in the associated Method Blank
D Dilution was required
E Value above quantitation range
H Holding times for preparation or analysis exceeded
J Analyte detected below quantitation limits
ND Not detected at the Reporting Limit
R RPD outside accepted recovery limits
RL Reporting Limit
S Spike recovery outside accepted recovery limits

Work Order: 1407120
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Sample ID: 1407120-002AMS	SampType: MS	Units: µg/Kg-dry	Prep Date: 7/14/2014	RunNo: 15582							
Client ID: EWC-B-05:16.0	Batch ID: 8106		Analysis Date: 7/14/2014	SeqNo: 315513							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Phenanthrene	889	52.9	1,058	0	84.0	45.5	140				
Anthracene	899	52.9	1,058	0	85.0	32.6	160				
Fluoranthene	896	52.9	1,058	0	84.7	44.6	161				
Pyrene	868	52.9	1,058	0	82.1	48.3	158				
Benz(a)anthracene	903	52.9	1,058	0	85.4	57.5	169				
Chrysene	984	52.9	1,058	0	93.0	45.2	146				
Benzo(b)fluoranthene	962	52.9	1,058	0	90.9	42.2	168				
Benzo(k)fluoranthene	898	52.9	1,058	0	84.9	48	161				
Benzo(a)pyrene	959	52.9	1,058	0	90.6	34.4	179				
Indeno(1,2,3-cd)pyrene	837	52.9	1,058	0	79.1	41.1	165				
Dibenz(a,h)anthracene	778	52.9	1,058	0	73.5	38.1	166				
Benzo(g,h,i)perylene	788	52.9	1,058	0	74.4	45.6	157				
Surr: 2-Fluorobiphenyl	391		529.0		73.9	42.7	132				
Surr: Terphenyl-d14 (surr)	486		529.0		91.9	48.8	157				

Sample ID: MB-8106	SampType: MBLK	Units: µg/Kg	Prep Date: 7/14/2014	RunNo: 15582							
Client ID: MBLKS	Batch ID: 8106		Analysis Date: 7/14/2014	SeqNo: 315518							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Naphthalene	ND	50.0									
2-Methylnaphthalene	ND	50.0									
1-Methylnaphthalene	ND	50.0									
Acenaphthylene	ND	50.0									
Acenaphthene	ND	50.0									
Fluorene	ND	50.0									
Phenanthrene	ND	50.0									
Anthracene	ND	50.0									
Fluoranthene	ND	50.0									

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits

Work Order: 1407120
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Sample ID: MB-8106	SampType: MBLK	Units: µg/Kg	Prep Date: 7/14/2014	RunNo: 15582							
Client ID: MBLKS	Batch ID: 8106		Analysis Date: 7/14/2014	SeqNo: 315518							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Pyrene	ND	50.0									
Benz(a)anthracene	ND	50.0									
Chrysene	ND	50.0									
Benzo(b)fluoranthene	ND	50.0									
Benzo(k)fluoranthene	ND	50.0									
Benzo(a)pyrene	ND	50.0									
Indeno(1,2,3-cd)pyrene	ND	50.0									
Dibenz(a,h)anthracene	ND	50.0									
Benzo(g,h,i)perylene	ND	50.0									
Surr: 2-Fluorobiphenyl	487		500.0		97.3	42.7	132				
Surr: Terphenyl-d14 (surr)	529		500.0		106	48.8	157				

Qualifiers: B Analyte detected in the associated Method Blank H Holding times for preparation or analysis exceeded R RPD outside accepted recovery limits	D Dilution was required J Analyte detected below quantitation limits RL Reporting Limit	E Value above quantitation range ND Not detected at the Reporting Limit S Spike recovery outside accepted recovery limits
---	---	---

Work Order: 1407120
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Pentachlorophenol by EPA 8151A

Sample ID: MB-8119	SampType: MBLK	Units: mg/Kg	Prep Date: 7/15/2014	RunNo: 15646							
Client ID: MBLKS	Batch ID: 8119		Analysis Date: 7/17/2014	SeqNo: 316762							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Pentachlorophenol	ND	0.0200									
Surr: 2,4-Dichlorophenylacetic acid	2.28		5.000		45.6	65	135				S

NOTES:

S - Outlying QC recoveries were associated with this sample. All other laboratory control and field samples within range.

Sample ID: LCS-8119	SampType: LCS	Units: mg/Kg	Prep Date: 7/15/2014	RunNo: 15646							
Client ID: LCSS	Batch ID: 8119		Analysis Date: 7/17/2014	SeqNo: 316763							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Pentachlorophenol	1.23	0.0200	4.000	0	30.7	21.4	135				
Surr: 2,4-Dichlorophenylacetic acid	3.42		5.000		68.4	65	135				

Sample ID: 1407120-001ADUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 7/15/2014	RunNo: 15646							
Client ID: EWC-B-04:10.0	Batch ID: 8119		Analysis Date: 7/17/2014	SeqNo: 316765							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Pentachlorophenol	0.142	0.0216						0.1518	7.03	30	
Surr: 2,4-Dichlorophenylacetic acid	4.22		5.399		78.1	65	135		0		

Sample ID: 1407120-002AMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 7/15/2014	RunNo: 15646							
Client ID: EWC-B-05:16.0	Batch ID: 8119		Analysis Date: 7/17/2014	SeqNo: 316767							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Pentachlorophenol	4.70	0.0222	4.445	0.1443	103	28.2	156				
Surr: 2,4-Dichlorophenylacetic acid	4.69		5.556		84.5	65	135				

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits

Work Order: 1407120
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Gasoline by NWTPH-Gx

Sample ID: 1407107-001BDUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 7/11/2014	RunNo: 15594							
Client ID: BATCH	Batch ID: R15594		Analysis Date: 7/15/2014	SeqNo: 315680							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	ND	7.25						0		30	
Surr: Toluene-d8	3.57		3.626		98.4	65	135		0		
Surr: 4-Bromofluorobenzene	3.77		3.626		104	65	135		0		

Sample ID: LCS-R15594	SampType: LCS	Units: mg/Kg	Prep Date: 7/15/2014	RunNo: 15594							
Client ID: LCSS	Batch ID: R15594		Analysis Date: 7/15/2014	SeqNo: 315685							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	25.5	5.00	25.00	0	102	65	135				
Surr: Toluene-d8	2.45		2.500		97.9	65	135				
Surr: 4-Bromofluorobenzene	2.75		2.500		110	65	135				

Sample ID: MB-R15594	SampType: MBLK	Units: mg/Kg	Prep Date: 7/15/2014	RunNo: 15594							
Client ID: MBLKS	Batch ID: R15594		Analysis Date: 7/15/2014	SeqNo: 315686							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	ND	5.00									
Surr: Toluene-d8	2.48		2.500		99.1	65	135				
Surr: 4-Bromofluorobenzene	2.68		2.500		107	65	135				

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits

Work Order: 1407120
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260

Sample ID: 1407120-001BMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 7/14/2014	RunNo: 15590							
Client ID: EWC-B-04:10.0	Batch ID: 8097		Analysis Date: 7/15/2014	SeqNo: 315634							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	0.561	0.0112	0.5591	0	100	63.5	133				
Toluene	0.557	0.0112	0.5591	0	99.5	63.4	132				
Ethylbenzene	0.573	0.0168	0.5591	0	102	54.5	134				
m,p-Xylene	1.14	0.0112	1.118	0	102	53.1	132				
o-Xylene	0.554	0.0112	0.5591	0	99.1	53.3	139				
Surr: Dibromofluoromethane	1.45		1.398		104	63.7	129				
Surr: Toluene-d8	1.46		1.398		104	61.4	128				
Surr: 1-Bromo-4-fluorobenzene	1.47		1.398		105	63.1	141				

Sample ID: LCS-R15590	SampType: LCS	Units: mg/Kg	Prep Date: 7/15/2014	RunNo: 15590							
Client ID: LCSS	Batch ID: 8097		Analysis Date: 7/15/2014	SeqNo: 315638							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	1.01	0.0200	1.000	0	101	74.6	124				
Toluene	1.01	0.0200	1.000	0	101	67.3	138				
Ethylbenzene	1.01	0.0300	1.000	0	101	74	129				
m,p-Xylene	2.04	0.0200	2.000	0	102	79.8	128				
o-Xylene	0.996	0.0200	1.000	0	99.6	72.7	124				
Surr: Dibromofluoromethane	2.53		2.500		101	63.7	129				
Surr: Toluene-d8	2.55		2.500		102	61.4	128				
Surr: 1-Bromo-4-fluorobenzene	2.60		2.500		104	63.1	141				

Sample ID: MB-R15590	SampType: MBLK	Units: mg/Kg	Prep Date: 7/15/2014	RunNo: 15590							
Client ID: MBLKS	Batch ID: 8097		Analysis Date: 7/15/2014	SeqNo: 315639							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	ND	0.0200									
Toluene	ND	0.0200									

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits

Work Order: 1407120
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260

Sample ID: MB-R15590	SampType: MBLK	Units: mg/Kg	Prep Date: 7/15/2014	RunNo: 15590							
Client ID: MBLKS	Batch ID: 8097		Analysis Date: 7/15/2014	SeqNo: 315639							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Ethylbenzene	ND	0.0300									
m,p-Xylene	ND	0.0200									
o-Xylene	ND	0.0200									
Surr: Dibromofluoromethane	2.44		2.500		97.7	63.7	129				
Surr: Toluene-d8	2.44		2.500		97.6	61.4	128				
Surr: 1-Bromo-4-fluorobenzene	2.37		2.500		95.0	63.1	141				

Sample ID: 1407107-001BDUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 7/11/2014	RunNo: 15590							
Client ID: BATCH	Batch ID: 8097		Analysis Date: 7/15/2014	SeqNo: 315697							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	ND	0.0290						0		30	
Toluene	ND	0.0290						0		30	
Ethylbenzene	ND	0.0435						0		30	
m,p-Xylene	ND	0.0290						0		30	
o-Xylene	ND	0.0290						0		30	
Surr: Dibromofluoromethane	3.58		3.626		98.8	63.7	129		0		
Surr: Toluene-d8	3.52		3.626		97.0	61.4	128		0		
Surr: 1-Bromo-4-fluorobenzene	3.35		3.626		92.3	63.1	141		0		

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits



Sample Log-In Check List

Client Name: **SW**

Work Order Number: **1407120**

Logged by: **Clare Griggs**

Date Received: **7/14/2014 11:18:00 AM**

Chain of Custody

1. Is Chain of Custody complete? Yes No Not Present
2. How was the sample delivered? Client

Log In

3. Coolers are present? Yes No NA
4. Shipping container/cooler in good condition? Yes No
5. Custody seals intact on shipping container/cooler? Yes No Not Required
6. Was an attempt made to cool the samples? Yes No NA
7. Were all coolers received at a temperature of >0°C to 10.0°C? Yes No NA
8. Sample(s) in proper container(s)? Yes No
9. Sufficient sample volume for indicated test(s)? Yes No
10. Are samples properly preserved? Yes No
11. Was preservative added to bottles? Yes No NA
12. Is the headspace in the VOA vials? Yes No NA
13. Did all samples containers arrive in good condition(unbroken)? Yes No
14. Does paperwork match bottle labels? Yes No
15. Are matrices correctly identified on Chain of Custody? Yes No
16. Is it clear what analyses were requested? Yes No
17. Were all holding times able to be met? Yes No

Special Handling (if applicable)

18. Was client notified of all discrepancies with this order? Yes No NA

Person Notified:	<input type="text"/>	Date:	<input type="text"/>
By Whom:	<input type="text"/>	Via:	<input type="checkbox"/> eMail <input type="checkbox"/> Phone <input type="checkbox"/> Fax <input type="checkbox"/> In Person
Regarding:	<input type="text"/>		
Client Instructions:	<input type="text"/>		

19. Additional remarks:

Item Information

Item #	Temp °C	Condition
Cooler	5.6	Good
Sample	3.7	Good



Fremont

Chain of Custody Record

3600 Fremont Ave N.
Seattle, WA 98103

Tel: 206-352-3790
Fax: 206-352-7178

Date: 7/10/2014
Page: 1 of 1

Client: Shannon & Johnson
Address: 1800 N 24th St, Suite 100
Seattle, WA 98103

Project Name: Valensa BWC
Location: B-04 E ridge yolkemack + B-05 56th + Ford Rd
Collected by: DWS stephanie williams

City, State, Zip: Seattle, WA 98103
Tel: 206-920-4864

Reports to (PM): Brian Reznick
Email: SARC@valensa.com
Project No: 21-1-21630-006

Matrix Codes: A = Air, AD = Aqueous, B = Bulk, D = Other, P = Product, S = Soil, SD = Sediment, SL = Solid, W = Water, DW = Drinking Water, GW = Ground Water, VW = Vapour Water

Sample Name	Sample Date	Sample Time	Sample Type (Matrix)	VOC (EPA 8260)	GP/BTEX	BTEX	Gasoline Range Organics (GRO)	Hydrocarbon Identification (HID)	Dechlorinated Oil Range Organics (DORO)	SEM-VOC (EPA 8270)	PAH (EPA 8270) - SW	PCB (EPA 8082)	Metals** (5010 / 200 A)	Total (T) - Dissolved (D)	Anion (A)**	EDR (811)	Pentachloroethel	Comments/Disorb
1 B-04-10.0 (VOC)	7/7	16:30																
2 B-04-10.0 (VOC)	7/7	16:30		X														
3 B-04-10.0 (VOC)	7/2	16:30		X														
4 B-05-16.0 (SO2)	7/10	10:50											X					
5 B-05-16.0 (VOC)	7/10	10:50		X														
6 B-05-16.0 (VOC)	7/10	10:50		X														
7																		
8																		
9																		
10																		

Metals Analysis (Circle): NETALS RCP-48 Priority Problems: TAL Individual: Ag Al Ar B Ba Be Ca Cd Co Cr Cu Fe Hg K Mg Mn Mo Ni Pb Pd Sb Se Sn Ti Tl U V Zn

Sample Disposal: Return to Client Disposal by Lab (As per rule for hazardous if samples are retained after 90 days.)

Special Remarks:

Refrigerated Date/Time: 7/10/2014 @ 12:45
 Analyzed Date/Time: 7/14/14 11:00
 Released Date/Time: 7/14/14 11:15
 Released Date/Time: 7/17/14 11:08

TAT -> SameDay* NextDay* 2 Day 3 Day STD
 *Please coordinate with the lab in advance.



3600 Fremont Ave. N.
Seattle, WA 98103
T: (206) 352-3790
F: (206) 352-7178
info@fremontanalytical.com

Shannon & Wilson

Ed Ptak
400 N. 34th Street, Suite 100
Seattle, WA 98103

RE: Yakima EWC

Lab ID: 1407187

July 25, 2014

Attention Ed Ptak:

Fremont Analytical, Inc. received 2 sample(s) on 7/18/2014 for the analyses presented in the following report.

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.
Gasoline by NWTPH-Gx
Mercury by EPA Method 7471
Pentachlorophenol by EPA 8151A
Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)
Sample Moisture (Percent Moisture)
Total Metals by EPA Method 6020
Volatile Organic Compounds by EPA Method 8260

This report consists of the following:

- Case Narrative
- Analytical Results
- Applicable Quality Control Summary Reports
- Chain of Custody

All analyses were performed consistent with the Quality Assurance program of Fremont Analytical, Inc. Please contact the laboratory if you should have any questions about the results.

Thank you for using Fremont Analytical.

Sincerely,

A handwritten signature in black ink, appearing to read "M. Dee".

Michael Dee
Sr. Chemist / Principal



Date: 07/25/2014

CLIENT: Shannon & Wilson
Project: Yakima EWC
Lab Order: 1407187

Work Order Sample Summary

Lab Sample ID	Client Sample ID	Date/Time Collected	Date/Time Received
1407187-001	EWC-B-01:10.0	07/14/2014 11:50 AM	07/18/2014 12:00 AM
1407187-002	EWC-B-01:15.0	07/14/2014 12:20 PM	07/18/2014 12:00 AM

Note: If no "Time Collected" is supplied, a default of 12:00AM is assigned

CLIENT: Shannon & Wilson**Project:** Yakima EWC

I. SAMPLE RECEIPT:

Samples receipt information is recorded on the attached Sample Receipt Checklist.

II. GENERAL REPORTING COMMENTS:

Results are reported on a wet weight basis unless dry-weight correction is denoted in the units field on the analytical report ("mg/kg-dry" or "ug/kg-dry").

Matrix Spike (MS) and MS Duplicate (MSD) samples are tested from an analytical batch of "like" matrix to check for possible matrix effect. The MS and MSD will provide site specific matrix data only for those samples which are spiked by the laboratory. The sample chosen for spike purposes may or may not have been a sample submitted in this sample delivery group. The validity of the analytical procedures for which data is reported in this analytical report is determined by the Laboratory Control Sample (LCS) and the Method Blank (MB). The LCS and the MB are processed with the samples and the MS/MSD to ensure method criteria are achieved throughout the entire analytical process.

III. ANALYSES AND EXCEPTIONS:

Exceptions associated with this report will be footnoted in the analytical results page(s) or the quality control summary page(s) and/or noted below.



Analytical Report

WO#: 1407187

Date Reported: 7/25/2014

Client: Shannon & Wilson

Collection Date: 7/14/2014 11:50:00 AM

Project: Yakima EWC

Lab ID: 1407187-001

Matrix: Soil

Client Sample ID: EWC-B-01:10.0

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
<u>Pentachlorophenol by EPA 8151A</u>				Batch ID: 8186		Analyst: DB
Pentachlorophenol	0.348	0.0341		mg/Kg-dry	1	7/22/2014 6:02:00 PM
Surr: 2,4,6-Tribromophenol	119	19.7-144		%REC	1	7/22/2014 6:02:00 PM
<u>Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.</u>				Batch ID: 8169		Analyst: EC
Diesel (Fuel Oil)	ND	32.4		mg/Kg-dry	1	7/22/2014 12:32:00 AM
Heavy Oil	147	81.0		mg/Kg-dry	1	7/22/2014 12:32:00 AM
Surr: 2-Fluorobiphenyl	102	50-150		%REC	1	7/22/2014 12:32:00 AM
Surr: o-Terphenyl	98.6	50-150		%REC	1	7/22/2014 12:32:00 AM
<u>Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)</u>				Batch ID: 8165		Analyst: NG
Naphthalene	ND	82.6		µg/Kg-dry	1	7/18/2014 6:44:00 PM
2-Methylnaphthalene	ND	82.6		µg/Kg-dry	1	7/18/2014 6:44:00 PM
1-Methylnaphthalene	ND	82.6		µg/Kg-dry	1	7/18/2014 6:44:00 PM
Acenaphthylene	ND	82.6		µg/Kg-dry	1	7/18/2014 6:44:00 PM
Acenaphthene	ND	82.6		µg/Kg-dry	1	7/18/2014 6:44:00 PM
Fluorene	ND	82.6		µg/Kg-dry	1	7/18/2014 6:44:00 PM
Phenanthrene	ND	82.6		µg/Kg-dry	1	7/18/2014 6:44:00 PM
Anthracene	ND	82.6		µg/Kg-dry	1	7/18/2014 6:44:00 PM
Fluoranthene	120	82.6		µg/Kg-dry	1	7/18/2014 6:44:00 PM
Pyrene	ND	82.6		µg/Kg-dry	1	7/18/2014 6:44:00 PM
Benz(a)anthracene	ND	82.6		µg/Kg-dry	1	7/18/2014 6:44:00 PM
Chrysene	ND	82.6		µg/Kg-dry	1	7/18/2014 6:44:00 PM
Benzo(b)fluoranthene	ND	82.6		µg/Kg-dry	1	7/18/2014 6:44:00 PM
Benzo(k)fluoranthene	ND	82.6		µg/Kg-dry	1	7/18/2014 6:44:00 PM
Benzo(a)pyrene	ND	82.6		µg/Kg-dry	1	7/18/2014 6:44:00 PM
Indeno(1,2,3-cd)pyrene	ND	82.6		µg/Kg-dry	1	7/18/2014 6:44:00 PM
Dibenz(a,h)anthracene	ND	82.6		µg/Kg-dry	1	7/18/2014 6:44:00 PM
Benzo(g,h,i)perylene	ND	82.6		µg/Kg-dry	1	7/18/2014 6:44:00 PM
Surr: 2-Fluorobiphenyl	85.0	42.7-132		%REC	1	7/18/2014 6:44:00 PM
Surr: Terphenyl-d14 (surr)	95.2	48.8-157		%REC	1	7/18/2014 6:44:00 PM

Qualifiers: B Analyte detected in the associated Method Blank
 E Value above quantitation range
 J Analyte detected below quantitation limits
 RL Reporting Limit

D Dilution was required
 H Holding times for preparation or analysis exceeded
 ND Not detected at the Reporting Limit
 S Spike recovery outside accepted recovery limits



Analytical Report

WO#: 1407187

Date Reported: 7/25/2014

Client: Shannon & Wilson

Collection Date: 7/14/2014 11:50:00 AM

Project: Yakima EWC

Lab ID: 1407187-001

Matrix: Soil

Client Sample ID: EWC-B-01:10.0

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Gasoline by NWTPH-Gx

Batch ID: R15702 Analyst: BC

Gasoline	ND	8.29		mg/Kg-dry	1	7/20/2014 8:08:00 AM
Surr: 4-Bromofluorobenzene	119	65-135		%REC	1	7/20/2014 8:08:00 AM
Surr: Toluene-d8	98.9	65-135		%REC	1	7/20/2014 8:08:00 AM

Volatile Organic Compounds by EPA Method 8260

Batch ID: 8144 Analyst: BC

Benzene	ND	0.0331		mg/Kg-dry	1	7/20/2014 8:08:00 AM
Toluene	ND	0.0331		mg/Kg-dry	1	7/20/2014 8:08:00 AM
Ethylbenzene	ND	0.0497		mg/Kg-dry	1	7/20/2014 8:08:00 AM
m,p-Xylene	ND	0.0331		mg/Kg-dry	1	7/20/2014 8:08:00 AM
o-Xylene	ND	0.0331		mg/Kg-dry	1	7/20/2014 8:08:00 AM
Surr: Dibromofluoromethane	99.3	63.7-129		%REC	1	7/20/2014 8:08:00 AM
Surr: Toluene-d8	100	61.4-128		%REC	1	7/20/2014 8:08:00 AM
Surr: 1-Bromo-4-fluorobenzene	100	63.1-141		%REC	1	7/20/2014 8:08:00 AM

Mercury by EPA Method 7471

Batch ID: 8157 Analyst: MW

Mercury	ND	0.414		mg/Kg-dry	1	7/21/2014 3:28:31 PM
---------	----	-------	--	-----------	---	----------------------

Total Metals by EPA Method 6020

Batch ID: 8156 Analyst: TN

Arsenic	2.52	0.130		mg/Kg-dry	1	7/21/2014 3:15:46 PM
Cadmium	0.527	0.259		mg/Kg-dry	1	7/21/2014 3:15:46 PM
Chromium	12.5	0.130		mg/Kg-dry	1	7/21/2014 3:15:46 PM
Lead	20.6	0.259		mg/Kg-dry	1	7/21/2014 3:15:46 PM

Sample Moisture (Percent Moisture)

Batch ID: R15667 Analyst: TK

Percent Moisture	42.0			wt%	1	7/18/2014 3:50:49 PM
------------------	------	--	--	-----	---	----------------------

Qualifiers:	B	Analyte detected in the associated Method Blank	D	Dilution was required
	E	Value above quantitation range	H	Holding times for preparation or analysis exceeded
	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits



Analytical Report

WO#: 1407187

Date Reported: 7/25/2014

Client: Shannon & Wilson

Collection Date: 7/14/2014 12:20:00 PM

Project: Yakima EWC

Lab ID: 1407187-002

Matrix: Soil

Client Sample ID: EWC-B-01:15.0

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Pentachlorophenol by EPA 8151A

Batch ID: 8186

Analyst: DB

Pentachlorophenol	ND	0.0363		mg/Kg-dry	1	7/22/2014 6:52:00 PM
Surr: 2,4,6-Tribromophenol	134	19.7-144		%REC	1	7/22/2014 6:52:00 PM

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Batch ID: 8169

Analyst: EC

Diesel (Fuel Oil)	ND	42.3		mg/Kg-dry	1	7/22/2014 1:03:00 AM
Heavy Oil	1,540	106		mg/Kg-dry	1	7/22/2014 1:03:00 AM
Surr: 2-Fluorobiphenyl	99.8	50-150		%REC	1	7/22/2014 1:03:00 AM
Surr: o-Terphenyl	104	50-150		%REC	1	7/22/2014 1:03:00 AM

Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Batch ID: 8165

Analyst: NG

Naphthalene	241	99.7		µg/Kg-dry	1	7/18/2014 7:34:00 PM
2-Methylnaphthalene	ND	99.7		µg/Kg-dry	1	7/18/2014 7:34:00 PM
1-Methylnaphthalene	ND	99.7		µg/Kg-dry	1	7/18/2014 7:34:00 PM
Acenaphthylene	ND	99.7		µg/Kg-dry	1	7/18/2014 7:34:00 PM
Acenaphthene	126	99.7		µg/Kg-dry	1	7/18/2014 7:34:00 PM
Fluorene	178	99.7		µg/Kg-dry	1	7/18/2014 7:34:00 PM
Phenanthrene	1,070	99.7		µg/Kg-dry	1	7/18/2014 7:34:00 PM
Anthracene	289	99.7		µg/Kg-dry	1	7/18/2014 7:34:00 PM
Fluoranthene	1,090	99.7		µg/Kg-dry	1	7/18/2014 7:34:00 PM
Pyrene	839	99.7		µg/Kg-dry	1	7/18/2014 7:34:00 PM
Benz(a)anthracene	462	99.7		µg/Kg-dry	1	7/18/2014 7:34:00 PM
Chrysene	248	99.7		µg/Kg-dry	1	7/18/2014 7:34:00 PM
Benzo(b)fluoranthene	507	99.7		µg/Kg-dry	1	7/18/2014 7:34:00 PM
Benzo(k)fluoranthene	203	99.7		µg/Kg-dry	1	7/18/2014 7:34:00 PM
Benzo(a)pyrene	382	99.7		µg/Kg-dry	1	7/18/2014 7:34:00 PM
Indeno(1,2,3-cd)pyrene	231	99.7		µg/Kg-dry	1	7/18/2014 7:34:00 PM
Dibenz(a,h)anthracene	134	99.7		µg/Kg-dry	1	7/18/2014 7:34:00 PM
Benzo(g,h,i)perylene	247	99.7		µg/Kg-dry	1	7/18/2014 7:34:00 PM
Surr: 2-Fluorobiphenyl	44.0	42.7-132		%REC	1	7/18/2014 7:34:00 PM
Surr: Terphenyl-d14 (surr)	63.6	48.8-157		%REC	1	7/18/2014 7:34:00 PM

Qualifiers: B Analyte detected in the associated Method Blank
 E Value above quantitation range
 J Analyte detected below quantitation limits
 RL Reporting Limit

D Dilution was required
 H Holding times for preparation or analysis exceeded
 ND Not detected at the Reporting Limit
 S Spike recovery outside accepted recovery limits



Analytical Report

WO#: 1407187

Date Reported: 7/25/2014

Client: Shannon & Wilson

Collection Date: 7/14/2014 12:20:00 PM

Project: Yakima EWC

Lab ID: 1407187-002

Matrix: Soil

Client Sample ID: EWC-B-01:15.0

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Gasoline by NWTPH-Gx

Batch ID: R15702 Analyst: BC

Gasoline	ND	10.6		mg/Kg-dry	1	7/20/2014 8:38:00 AM
Surr: 4-Bromofluorobenzene	114	65-135		%REC	1	7/20/2014 8:38:00 AM
Surr: Toluene-d8	98.7	65-135		%REC	1	7/20/2014 8:38:00 AM

Volatile Organic Compounds by EPA Method 8260

Batch ID: 8144 Analyst: BC

Benzene	ND	0.0424		mg/Kg-dry	1	7/20/2014 8:38:00 AM
Toluene	ND	0.0424		mg/Kg-dry	1	7/20/2014 8:38:00 AM
Ethylbenzene	ND	0.0636		mg/Kg-dry	1	7/20/2014 8:38:00 AM
m,p-Xylene	ND	0.0424		mg/Kg-dry	1	7/20/2014 8:38:00 AM
o-Xylene	ND	0.0424		mg/Kg-dry	1	7/20/2014 8:38:00 AM
Surr: Dibromofluoromethane	98.6	63.7-129		%REC	1	7/20/2014 8:38:00 AM
Surr: Toluene-d8	99.6	61.4-128		%REC	1	7/20/2014 8:38:00 AM
Surr: 1-Bromo-4-fluorobenzene	96.2	63.1-141		%REC	1	7/20/2014 8:38:00 AM

Mercury by EPA Method 7471

Batch ID: 8157 Analyst: MW

Mercury	ND	0.502		mg/Kg-dry	1	7/21/2014 3:30:09 PM
---------	----	-------	--	-----------	---	----------------------

Total Metals by EPA Method 6020

Batch ID: 8156 Analyst: TN

Arsenic	6.08	0.165		mg/Kg-dry	1	7/21/2014 3:19:12 PM
Cadmium	0.865	0.330		mg/Kg-dry	1	7/21/2014 3:19:12 PM
Chromium	17.5	0.165		mg/Kg-dry	1	7/21/2014 3:19:12 PM
Lead	36.3	0.330		mg/Kg-dry	1	7/21/2014 3:19:12 PM

Sample Moisture (Percent Moisture)

Batch ID: R15667 Analyst: TK

Percent Moisture	53.0			wt%	1	7/18/2014 3:50:49 PM
------------------	------	--	--	-----	---	----------------------

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required
E	Value above quantitation range	H	Holding times for preparation or analysis exceeded
J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
RL	Reporting Limit	S	Spike recovery outside accepted recovery limits



Work Order: 1407187
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Total Metals by EPA Method 6020

Sample ID: MB-8156	SampType: MBLK	Units: mg/Kg	Prep Date: 7/21/2014	RunNo: 15695							
Client ID: MBLKS	Batch ID: 8156		Analysis Date: 7/21/2014	SeqNo: 317631							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	ND	0.100									
Cadmium	ND	0.200									
Chromium	ND	0.100									
Lead	ND	0.200									

Sample ID: LCS-8156	SampType: LCS	Units: mg/Kg	Prep Date: 7/21/2014	RunNo: 15695							
Client ID: LCSS	Batch ID: 8156		Analysis Date: 7/21/2014	SeqNo: 317632							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	97.0	0.100	104.0	0	93.2	69.5	130.8				
Cadmium	92.2	0.200	92.80	0	99.3	73.3	127.2				
Chromium	67.1	0.100	62.90	0	107	67.9	132				
Lead	309	0.200	319.0	0	96.8	75.9	124.1				

Sample ID: 1407175-003ADUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 7/21/2014	RunNo: 15695							
Client ID: BATCH	Batch ID: 8156		Analysis Date: 7/21/2014	SeqNo: 317634							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	2.18	0.0831						2.340	7.06	30	
Cadmium	ND	0.166						0		30	
Chromium	21.1	0.0831						20.80	1.58	30	
Lead	1.42	0.166						1.423	0.0175	30	

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits



Work Order: 1407187
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Total Metals by EPA Method 6020

Sample ID: 1407175-003AMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 7/21/2014	RunNo: 15695							
Client ID: BATCH	Batch ID: 8156		Analysis Date: 7/21/2014	SeqNo: 317638							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	46.7	0.0837	41.87	2.340	106	75	125				
Cadmium	2.21	0.167	2.094	0.03943	104	75	125				
Chromium	71.5	0.0837	41.87	20.80	121	75	125				
Lead	22.8	0.167	20.94	1.423	102	75	125				

Sample ID: 1407175-003AMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 7/21/2014	RunNo: 15695							
Client ID: BATCH	Batch ID: 8156		Analysis Date: 7/21/2014	SeqNo: 317639							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	42.7	0.0818	40.92	2.340	98.6	75	125	46.72	8.97	30	
Cadmium	1.99	0.164	2.046	0.03943	95.2	75	125	2.210	10.6	30	
Chromium	64.3	0.0818	40.92	20.80	106	75	125	71.45	10.5	30	
Lead	20.5	0.164	20.46	1.423	93.2	75	125	22.83	10.8	30	

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits



Work Order: 1407187
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Mercury by EPA Method 7471

Sample ID: MB-8157	SampType: MBLK	Units: mg/Kg	Prep Date: 7/21/2014	RunNo: 15692							
Client ID: MBLKS	Batch ID: 8157	Analysis Date: 7/21/2014	SeqNo: 317548								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury ND 0.250

Sample ID: LCS-8157	SampType: LCS	Units: mg/Kg	Prep Date: 7/21/2014	RunNo: 15692							
Client ID: LCSS	Batch ID: 8157	Analysis Date: 7/21/2014	SeqNo: 317549								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.491 0.250 0.5000 0 98.2 80 120

Sample ID: 1407184-001ADUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 7/21/2014	RunNo: 15692							
Client ID: BATCH	Batch ID: 8157	Analysis Date: 7/21/2014	SeqNo: 317551								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury ND 0.279 0 20

Sample ID: 1407184-001AMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 7/21/2014	RunNo: 15692							
Client ID: BATCH	Batch ID: 8157	Analysis Date: 7/21/2014	SeqNo: 317552								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.539 0.264 0.5281 0.03102 96.1 70 130

Sample ID: 1407184-001AMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 7/21/2014	RunNo: 15692							
Client ID: BATCH	Batch ID: 8157	Analysis Date: 7/21/2014	SeqNo: 317553								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.544 0.269 0.5379 0.03102 95.4 70 130 0.5387 1.05 20

Qualifiers: B Analyte detected in the associated Method Blank
D Dilution was required
E Value above quantitation range
H Holding times for preparation or analysis exceeded
J Analyte detected below quantitation limits
ND Not detected at the Reporting Limit
R RPD outside accepted recovery limits
RL Reporting Limit
S Spike recovery outside accepted recovery limits

Work Order: 1407187
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Sample ID: 1407199-001ADUP	SampType: DUP	Units: mg/Kg-dry				Prep Date: 7/21/2014	RunNo: 15706				
Client ID: BATCH	Batch ID: 8169					Analysis Date: 7/21/2014	SeqNo: 317859				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	ND	24.6						0		30	
Heavy Oil	ND	61.6						0		30	
Surr: 2-Fluorobiphenyl	24.1		24.64		97.6	50	150		0		
Surr: o-Terphenyl	23.1		24.64		93.5	50	150		0		

Sample ID: LCS-8169	SampType: LCS	Units: mg/Kg				Prep Date: 7/21/2014	RunNo: 15706				
Client ID: LCSS	Batch ID: 8169					Analysis Date: 7/21/2014	SeqNo: 317866				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	491	20.0	500.0	0	98.2	65	135				
Surr: 2-Fluorobiphenyl	21.9		20.00		110	50	150				
Surr: o-Terphenyl	18.8		20.00		94.2	50	150				

Sample ID: MB-8169	SampType: MBLK	Units: mg/Kg				Prep Date: 7/21/2014	RunNo: 15706				
Client ID: MBLKS	Batch ID: 8169					Analysis Date: 7/21/2014	SeqNo: 317867				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	ND	20.0									
Heavy Oil	ND	50.0									
Surr: 2-Fluorobiphenyl	20.0		20.00		100	50	150				
Surr: o-Terphenyl	19.1		20.00		95.4	50	150				

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits

Work Order: 1407187
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Sample ID: MB-8165	SampType: MBLK	Units: µg/Kg	Prep Date: 7/18/2014	RunNo: 15681							
Client ID: MBLKS	Batch ID: 8165		Analysis Date: 7/18/2014	SeqNo: 317399							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	ND	50.0									
2-Methylnaphthalene	ND	50.0									
1-Methylnaphthalene	ND	50.0									
Acenaphthylene	ND	50.0									
Acenaphthene	ND	50.0									
Fluorene	ND	50.0									
Phenanthrene	ND	50.0									
Anthracene	ND	50.0									
Fluoranthene	ND	50.0									
Pyrene	ND	50.0									
Benz(a)anthracene	ND	50.0									
Chrysene	ND	50.0									
Benzo(b)fluoranthene	ND	50.0									
Benzo(k)fluoranthene	ND	50.0									
Benzo(a)pyrene	ND	50.0									
Indeno(1,2,3-cd)pyrene	ND	50.0									
Dibenz(a,h)anthracene	ND	50.0									
Benzo(g,h,i)perylene	ND	50.0									
Surr: 2-Fluorobiphenyl	442		500.0		88.3	42.7	132				
Surr: Terphenyl-d14 (surr)	428		500.0		85.6	48.8	157				

Sample ID: LCS-8165	SampType: LCS	Units: µg/Kg	Prep Date: 7/18/2014	RunNo: 15681							
Client ID: LCSS	Batch ID: 8165		Analysis Date: 7/18/2014	SeqNo: 317400							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	861	50.0	1,000	0	86.1	61.6	125				
2-Methylnaphthalene	843	50.0	1,000	0	84.3	58.2	129				
1-Methylnaphthalene	837	50.0	1,000	0	83.7	56.4	132				

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits

Work Order: 1407187
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Sample ID: LCS-8165	SampType: LCS	Units: µg/Kg	Prep Date: 7/18/2014	RunNo: 15681							
Client ID: LCSS	Batch ID: 8165		Analysis Date: 7/18/2014	SeqNo: 317400							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Acenaphthylene	830	50.0	1,000	0	83.0	52.2	133				
Acenaphthene	903	50.0	1,000	0	90.3	54	131				
Fluorene	884	50.0	1,000	0	88.5	53.4	131				
Phenanthrene	859	50.0	1,000	0	85.9	55.6	128				
Anthracene	862	50.0	1,000	0	86.2	51	132				
Fluoranthene	864	50.0	1,000	0	86.4	48.4	134				
Pyrene	852	50.0	1,000	0	85.2	48.6	135				
Benz(a)anthracene	827	50.0	1,000	0	82.7	41.9	136				
Chrysene	951	50.0	1,000	0	95.1	51.4	135				
Benzo(b)fluoranthene	889	50.0	1,000	0	88.9	39.7	137				
Benzo(k)fluoranthene	844	50.0	1,000	0	84.4	45.7	138				
Benzo(a)pyrene	874	50.0	1,000	0	87.4	45.3	135				
Indeno(1,2,3-cd)pyrene	734	50.0	1,000	0	73.4	45.4	137				
Dibenz(a,h)anthracene	684	50.0	1,000	0	68.4	45.8	134				
Benzo(g,h,i)perylene	712	50.0	1,000	0	71.2	49.3	134				
Surr: 2-Fluorobiphenyl	421		500.0		84.1	42.7	132				
Surr: Terphenyl-d14 (surr)	416		500.0		83.1	48.8	157				

Sample ID: 1407187-001ADUP	SampType: DUP	Units: µg/Kg-dry	Prep Date: 7/18/2014	RunNo: 15681							
Client ID: EWC-B-01:10.0	Batch ID: 8165		Analysis Date: 7/18/2014	SeqNo: 317402							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	ND	82.4						0		30	
2-Methylnaphthalene	ND	82.4						0		30	
1-Methylnaphthalene	ND	82.4						0		30	
Acenaphthylene	ND	82.4						0		30	
Acenaphthene	ND	82.4						0		30	
Fluorene	ND	82.4						0		30	

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits

Work Order: 1407187
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Sample ID: 1407187-001ADUP	SampType: DUP	Units: µg/Kg-dry	Prep Date: 7/18/2014	RunNo: 15681							
Client ID: EWC-B-01:10.0	Batch ID: 8165		Analysis Date: 7/18/2014	SeqNo: 317402							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Phenanthrene	ND	82.4						0		30	
Anthracene	ND	82.4						0		30	
Fluoranthene	ND	82.4						120.2	106	30	R
Pyrene	ND	82.4						0		30	
Benz(a)anthracene	ND	82.4						0		30	
Chrysene	ND	82.4						0		30	
Benzo(b)fluoranthene	ND	82.4						0		30	
Benzo(k)fluoranthene	ND	82.4						0		30	
Benzo(a)pyrene	ND	82.4						0		30	
Indeno(1,2,3-cd)pyrene	ND	82.4						0		30	
Dibenz(a,h)anthracene	ND	82.4						0		30	
Benzo(g,h,i)perylene	ND	82.4						0		30	
Surr: 2-Fluorobiphenyl	600		824.3		72.8	42.7	132		0		
Surr: Terphenyl-d14 (surr)	807		824.3		97.9	48.8	157		0		

NOTES:

R - High RPD due to suspected sample inhomogeneity. The method is in control as indicated by the Laboratory Control Sample (LCS).

Sample ID: 1407187-002AMS	SampType: MS	Units: µg/Kg-dry	Prep Date: 7/18/2014	RunNo: 15681							
Client ID: EWC-B-01:15.0	Batch ID: 8165		Analysis Date: 7/18/2014	SeqNo: 317404							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Naphthalene	1,680	100	2,003	240.6	71.7	42.9	138				
2-Methylnaphthalene	1,520	100	2,003	92.78	71.1	42.8	151				
1-Methylnaphthalene	1,430	100	2,003	56.24	68.5	41.6	148				
Acenaphthylene	1,470	100	2,003	33.90	71.6	32.6	160				
Acenaphthene	1,650	100	2,003	126.4	76.3	46.3	142				
Fluorene	1,730	100	2,003	178.2	77.4	43.4	153				
Phenanthrene	2,310	100	2,003	1,069	62.1	45.5	140				
Anthracene	1,810	100	2,003	288.9	75.8	32.6	160				

Qualifiers:	B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
	H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
	R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits



Work Order: 1407187
 CLIENT: Shannon & Wilson
 Project: Yakima EWC

QC SUMMARY REPORT
Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Sample ID: 1407187-002AMS	SampType: MS	Units: µg/Kg-dry	Prep Date: 7/18/2014	RunNo: 15681							
Client ID: EWC-B-01:15.0	Batch ID: 8165		Analysis Date: 7/18/2014	SeqNo: 317404							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Fluoranthene	2,350	100	2,003	1,089	63.1	44.6	161				
Pyrene	2,170	100	2,003	838.6	66.6	48.3	158				
Benz(a)anthracene	1,990	100	2,003	461.7	76.1	57.5	169				
Chrysene	2,020	100	2,003	247.7	88.7	45.2	146				
Benzo(b)fluoranthene	2,120	100	2,003	506.8	80.5	42.2	168				
Benzo(k)fluoranthene	1,750	100	2,003	203.0	77.1	48	161				
Benzo(a)pyrene	2,030	100	2,003	382.1	82.2	34.4	179				
Indeno(1,2,3-cd)pyrene	1,710	100	2,003	230.7	73.7	41.1	165				
Dibenz(a,h)anthracene	1,590	100	2,003	134.2	72.5	38.1	166				
Benzo(g,h,i)perylene	1,670	100	2,003	247.1	71.3	45.6	157				
Surr: 2-Fluorobiphenyl	496		1,002		49.5	42.7	132				
Surr: Terphenyl-d14 (surr)	884		1,002		88.2	48.8	157				

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits

Work Order: 1407187
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Pentachlorophenol by EPA 8151A

Sample ID: MB-8186	SampType: MBLK	Units: mg/Kg	Prep Date: 7/22/2014	RunNo: 15797							
Client ID: MBLKS	Batch ID: 8186		Analysis Date: 7/22/2014	SeqNo: 319420							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Pentachlorophenol ND 0.0200
 Surr: 2,4,6-Tribromophenol 1.04 2.000 51.8 19.7 144

Sample ID: LCS-8186	SampType: LCS	Units: mg/Kg	Prep Date: 7/22/2014	RunNo: 15797							
Client ID: LCSS	Batch ID: 8186		Analysis Date: 7/22/2014	SeqNo: 319421							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Pentachlorophenol 1.63 0.0200 4.000 0 40.7 21.4 135
 Surr: 2,4,6-Tribromophenol 1.71 2.000 85.3 19.7 144

Sample ID: 1407187-001ADUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 7/22/2014	RunNo: 15797							
Client ID: EWC-B-01:10.0	Batch ID: 8186		Analysis Date: 7/22/2014	SeqNo: 319423							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Pentachlorophenol 0.352 0.0336 0.3485 1.04 30
 Surr: 2,4,6-Tribromophenol 4.60 3.363 137 19.7 144 0 0

Sample ID: 1407187-002AMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 7/22/2014	RunNo: 15797							
Client ID: EWC-B-01:15.0	Batch ID: 8186		Analysis Date: 7/22/2014	SeqNo: 319425							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Pentachlorophenol 9.50 0.0367 7.343 0 129 28.2 156
 Surr: 2,4,6-Tribromophenol 5.14 3.671 140 19.7 144

Qualifiers: B Analyte detected in the associated Method Blank D Dilution was required E Value above quantitation range
 H Holding times for preparation or analysis exceeded J Analyte detected below quantitation limits ND Not detected at the Reporting Limit
 R RPD outside accepted recovery limits RL Reporting Limit S Spike recovery outside accepted recovery limits

Work Order: 1407187
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Gasoline by NWTPH-Gx

Sample ID: MB-R15702	SampType: MBLK	Units: mg/Kg	Prep Date: 7/19/2014	RunNo: 15702							
Client ID: MBLKS	Batch ID: R15702		Analysis Date: 7/19/2014	SeqNo: 317786							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	ND	5.00									
Surr: Toluene-d8	2.47		2.500		98.9	65	135				
Surr: 4-Bromofluorobenzene	2.82		2.500		113	65	135				

Sample ID: 1407181-004BDUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 7/18/2014	RunNo: 15702							
Client ID: BATCH	Batch ID: R15702		Analysis Date: 7/20/2014	SeqNo: 317802							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	ND	5.69						0		30	
Surr: Toluene-d8	2.79		2.847		97.9	65	135		0		
Surr: 4-Bromofluorobenzene	3.16		2.847		111	65	135		0		

Sample ID: LCS-R15702	SampType: LCS	Units: mg/Kg	Prep Date: 7/19/2014	RunNo: 15702							
Client ID: LCSS	Batch ID: R15702		Analysis Date: 7/19/2014	SeqNo: 317807							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	27.2	5.00	25.00	0	109	65	135				
Surr: Toluene-d8	2.51		2.500		100	65	135				
Surr: 4-Bromofluorobenzene	2.91		2.500		116	65	135				

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits

Work Order: 1407187
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260

Sample ID: 1407181-004BDUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 7/18/2014	RunNo: 15693							
Client ID: BATCH	Batch ID: 8144		Analysis Date: 7/20/2014	SeqNo: 317585							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	ND	0.0228						0		30	
Toluene	ND	0.0228						0		30	
Ethylbenzene	ND	0.0342						0		30	
m,p-Xylene	ND	0.0228						0		30	
o-Xylene	ND	0.0228						0		30	
Surr: Dibromofluoromethane	2.70		2.847		94.8	63.7	129		0		
Surr: Toluene-d8	2.82		2.847		99.1	61.4	128		0		
Surr: 1-Bromo-4-fluorobenzene	2.67		2.847		93.7	63.1	141		0		

Sample ID: LCS-R15693	SampType: LCS	Units: mg/Kg	Prep Date: 7/19/2014	RunNo: 15693							
Client ID: LCSS	Batch ID: 8144		Analysis Date: 7/19/2014	SeqNo: 317591							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	0.977	0.0200	1.000	0	97.7	74.6	124				
Toluene	1.03	0.0200	1.000	0	103	67.3	138				
Ethylbenzene	0.986	0.0300	1.000	0	98.6	74	129				
m,p-Xylene	1.95	0.0200	2.000	0	97.5	79.8	128				
o-Xylene	0.962	0.0200	1.000	0	96.2	72.7	124				
Surr: Dibromofluoromethane	2.61		2.500		104	63.7	129				
Surr: Toluene-d8	2.57		2.500		103	61.4	128				
Surr: 1-Bromo-4-fluorobenzene	2.58		2.500		103	63.1	141				

Sample ID: MB-R15693	SampType: MBLK	Units: mg/Kg	Prep Date: 7/19/2014	RunNo: 15693							
Client ID: MBLKS	Batch ID: 8144		Analysis Date: 7/19/2014	SeqNo: 317592							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	ND	0.0200									
Toluene	ND	0.0200									

Qualifiers:

B	Analyte detected in the associated Method Blank	D	Dilution was required	E	Value above quantitation range
H	Holding times for preparation or analysis exceeded	J	Analyte detected below quantitation limits	ND	Not detected at the Reporting Limit
R	RPD outside accepted recovery limits	RL	Reporting Limit	S	Spike recovery outside accepted recovery limits



Work Order: 1407187
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260

Sample ID: MB-R15693	SampType: MBLK	Units: mg/Kg	Prep Date: 7/19/2014	RunNo: 15693							
Client ID: MBLKS	Batch ID: 8144		Analysis Date: 7/19/2014	SeqNo: 317592							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Ethylbenzene	ND	0.0300									
m,p-Xylene	ND	0.0200									
o-Xylene	ND	0.0200									
Surr: Dibromofluoromethane	2.47		2.500		98.7	63.7	129				
Surr: Toluene-d8	2.51		2.500		101	61.4	128				
Surr: 1-Bromo-4-fluorobenzene	2.38		2.500		95.1	63.1	141				

Qualifiers: B Analyte detected in the associated Method Blank H Holding times for preparation or analysis exceeded R RPD outside accepted recovery limits	D Dilution was required J Analyte detected below quantitation limits RL Reporting Limit	E Value above quantitation range ND Not detected at the Reporting Limit S Spike recovery outside accepted recovery limits
---	---	---

Client Name: **SW**
 Logged by: **Erica Silva**

 Work Order Number: **1407187**
 Date Received: **7/18/2014**

Chain of Custody

1. Is Chain of Custody complete? Yes No Not Present
2. How was the sample delivered? UPS

Log In

3. Coolers are present? Yes No NA
4. Shipping container/cooler in good condition? Yes No
5. Custody seals intact on shipping container/cooler? Yes No Not Required
6. Was an attempt made to cool the samples? Yes No NA
7. Were all coolers received at a temperature of >0°C to 10.0°C? Yes No NA
8. Sample(s) in proper container(s)? Yes No
9. Sufficient sample volume for indicated test(s)? Yes No
10. Are samples properly preserved? Yes No
11. Was preservative added to bottles? Yes No NA
12. Is the headspace in the VOA vials? Yes No NA
13. Did all samples containers arrive in good condition(unbroken)? Yes No
14. Does paperwork match bottle labels? Yes No
15. Are matrices correctly identified on Chain of Custody? Yes No
16. Is it clear what analyses were requested? Yes No
17. Were all holding times able to be met? Yes No

Special Handling (if applicable)

18. Was client notified of all discrepancies with this order? Yes No NA

Person Notified:	<input type="text" value="Ed Ptak"/>	Date:	<input type="text" value="7/18/2014"/>
By Whom:	<input type="text" value="Erica Silva"/>	Via:	<input checked="" type="checkbox"/> eMail <input type="checkbox"/> Phone <input type="checkbox"/> Fax <input type="checkbox"/> In Person
Regarding:	<input type="text" value="Full VOC list AND Gx/BTEX selected: clarifv"/>		
Client Instructions:	<input type="text" value="Gx/BTEX only"/>		

19. Additional remarks:

Item Information

Item #	Temp °C	Condition
Cooler	8.5	Good
Sample	9.2	Good



Fremont

Chain of Custody Record

3600 Fremont Ave N.
Seattle, WA 98103

Tel: 206-352-3790
Fax: 206-352-7178

Date: 7/16/2014

Pages: 1 of 1

1407187

Client: Stevens & Wilson
Address: 400 24th St SW #100
City, State, Zip: Seattle, WA 98102

Project Name: Victoria EWC - EWC-001, west side of 1-52
Location: SAW
Collected by: SAW

Reports To (RM): Bryan Penick

Email: 5PM@stevens-w.com Project No: 21-1-21620-006

*Matrix Codes: A = Air, AD = Aqueous, B = Bulk, O = Other, P = Product, S = Soil, SP = Sediment, SL = Solid, W = Water, DW = Drinking Water, GW = Ground Water, WW = Waste Water

Sample Name	Sample Date	Sample Time	Sample Type / Matrix	YOC (EPA 8260)	GV/TEX	ETEX	Gasoline Range Organics (GRO)	Hydrocarbon Identification (HCID)	Diesel/Heavy Oil Range Organics (DHRO)	SEM VOL (EPA 8270)	PAHs (EPA 8270-SIM)	PCBs (EPA 8092)	Metals* (6210/200.3)	Total (T) / Dissolved (D)	Anions (A)***	EDB (8013)	DX	Comments/Remarks
1 EWC-0-01-10.0	7/14	11:50		X	X													
2 EWC-0-01-15.0	7/14	12:00		X	X													
3																		
4																		
5																		
6																		
7																		
8																		
9																		
10																		

*Matrix Analysis (Circle): NTCS RCV-8 Priority Pollutants TOL Individual Ag: Al Ar B Ba Be Ca Cd Co Cr Cu Fe Hg P In I Mg Mn Ni Pb Pd Se Sr Zn Ti V U W X

**Anions (Circle): Nitrate Nitrite Chloride Sulfate Bromide Chlorophosphate Fluoride Nitrate+Merite

Sample Disturbance: Return to Client Dispose by Lab (If necessary the customer's signature has received prior to this)

Requisition: SP1000 Date/Time: 7/16/2014 09:13 Received: [Signature] Date/Time: 7/18/14 14:40

Reinforced: [Signature] Date/Time: 7/16/2014 09:13 Approved: [Signature] Date/Time: 7/18/14 14:40

Special Remarks: TA1 -> Simraday - Next Day - ED Day - 3:30 PM

*Please coordinate with the lab reference

Distribution: White - Lab, Yellow - File, Pink - Originator

www.fremontanalytical.com



3600 Fremont Ave. N.
Seattle, WA 98103
T: (206) 352-3790
F: (206) 352-7178
info@fremontanalytical.com

Shannon & Wilson

Brian Reznick
400 N. 34th Street, Suite 100
Seattle, WA 98103

RE: Yakima EWC
Work Order Number: 1707301

August 14, 2017

Attention Brian Reznick:

Fremont Analytical, Inc. received 5 sample(s) on 7/31/2017 for the analyses presented in the following report.

- Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.***
- Gasoline by NWTPH-Gx***
- Herbicides by EPA Method 8151A***
- Mercury by EPA Method 7471***
- Organochlorine Pesticides by EPA Method 8081***
- Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)***
- Polychlorinated Biphenyls (PCB) by EPA 8082***
- Sample Moisture (Percent Moisture)***
- Total Metals by EPA Method 6020***
- Volatile Organic Compounds by EPA Method 8260C***

This report consists of the following:

- Case Narrative
- Analytical Results
- Applicable Quality Control Summary Reports
- Chain of Custody

All analyses were performed consistent with the Quality Assurance program of Fremont Analytical, Inc. Please contact the laboratory if you should have any questions about the results.

Thank you for using Fremont Analytical.

Sincerely,

DoD/ELAP Certification #L17-135, ISO/IEC 17025:2005
ORELAP Certification: WA 100009-007 (NELAP Recognized)

Mike Ridgeway
Laboratory Director

*DoD/ELAP Certification #L17-135, ISO/IEC 17025:2005
ORELAP Certification: WA 100009-007 (NELAP Recognized)*



Date: 08/14/2017

CLIENT: Shannon & Wilson
Project: Yakima EWC
Work Order: 1707301

Work Order Sample Summary

Lab Sample ID	Client Sample ID	Date/Time Collected	Date/Time Received
1707301-001	ES-1	07/25/2017 9:22 AM	07/31/2017 8:39 AM
1707301-002	ES-2	07/26/2017 4:30 PM	07/31/2017 8:39 AM
1707301-003	ES-3	07/26/2017 4:40 PM	07/31/2017 8:39 AM
1707301-004	ES-4	07/27/2017 7:45 AM	07/31/2017 8:39 AM
1707301-005	Trip Blank	07/19/2017 9:20 AM	07/31/2017 8:39 AM

CLIENT: Shannon & Wilson**Project:** Yakima EWC

I. SAMPLE RECEIPT:

Samples receipt information is recorded on the attached Sample Receipt Checklist.

II. GENERAL REPORTING COMMENTS:

Results are reported on a wet weight basis unless dry-weight correction is denoted in the units field on the analytical report ("mg/kg-dry" or "ug/kg-dry").

Matrix Spike (MS) and MS Duplicate (MSD) samples are tested from an analytical batch of "like" matrix to check for possible matrix effect. The MS and MSD will provide site specific matrix data only for those samples which are spiked by the laboratory. The sample chosen for spike purposes may or may not have been a sample submitted in this sample delivery group. The validity of the analytical procedures for which data is reported in this analytical report is determined by the Laboratory Control Sample (LCS) and the Method Blank (MB). The LCS and the MB are processed with the samples and the MS/MSD to ensure method criteria are achieved throughout the entire analytical process.

III. ANALYSES AND EXCEPTIONS:

Exceptions associated with this report will be footnoted in the analytical results page(s) or the quality control summary page(s) and/or noted below.

Prep Comments for METHOD (PREP-PCB-S), SAMPLE (1707301-002A) required Acid Cleanup Procedure (Using Method No 3665A).

Prep Comments for METHOD (PREP-PCB-S), SAMPLE (1707301-003A) required Acid Cleanup Procedure (Using Method No 3665A).

Prep Comments for METHOD (PREP-PCB-S), SAMPLE (1707301-004A) required Acid Cleanup Procedure (Using Method No 3665A).

Prep Comments for METHOD (PREP-PCB-S), SAMPLE (1707301-004A) required Florisil Cleanup Procedure (Using Method No 3620C).

Prep Comments for METHOD (PREP-PCB-S), SAMPLE (1707301-003A) required Florisil Cleanup Procedure (Using Method No 3620C).

Prep Comments for METHOD (PREP-PCB-S), SAMPLE (1707301-002A) required Florisil Cleanup Procedure (Using Method No 3620C).

Qualifiers:

- * - Flagged value is not within established control limits
- B - Analyte detected in the associated Method Blank
- D - Dilution was required
- E - Value above quantitation range
- H - Holding times for preparation or analysis exceeded
- I - Analyte with an internal standard that does not meet established acceptance criteria
- J - Analyte detected below Reporting Limit
- N - Tentatively Identified Compound (TIC)
- Q - Analyte with an initial or continuing calibration that does not meet established acceptance criteria (<20%RSD, <20% Drift or minimum RRF)
- S - Spike recovery outside accepted recovery limits
- ND - Not detected at the Reporting Limit
- R - High relative percent difference observed

Acronyms:

- %Rec - Percent Recovery
- CCB - Continued Calibration Blank
- CCV - Continued Calibration Verification
- DF - Dilution Factor
- HEM - Hexane Extractable Material
- ICV - Initial Calibration Verification
- LCS/LCSD - Laboratory Control Sample / Laboratory Control Sample Duplicate
- MB or MBLANK - Method Blank
- MDL - Method Detection Limit
- MS/MSD - Matrix Spike / Matrix Spike Duplicate
- PDS - Post Digestion Spike
- Ref Val - Reference Value
- RL - Reporting Limit
- RPD - Relative Percent Difference
- SD - Serial Dilution
- SGT - Silica Gel Treatment
- SPK - Spike
- Surr - Surrogate



Client: Shannon & Wilson

Collection Date: 7/25/2017 9:22:00 AM

Project: Yakima EWC

Lab ID: 1707301-001

Matrix: Soil

Client Sample ID: ES-1

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Organochlorine Pesticides by EPA Method 8081

Batch ID: 17824

Analyst: SG

Toxaphene	ND	0.0902		mg/Kg-dry	1	8/7/2017 6:04:25 PM
Alpha BHC	ND	0.00902		mg/Kg-dry	1	8/7/2017 6:04:25 PM
Beta BHC	ND	0.00902		mg/Kg-dry	1	8/7/2017 6:04:25 PM
Gamma BHC (Lindane)	ND	0.00902		mg/Kg-dry	1	8/7/2017 6:04:25 PM
Delta BHC	ND	0.00902		mg/Kg-dry	1	8/7/2017 6:04:25 PM
Heptachlor	ND	0.00902		mg/Kg-dry	1	8/7/2017 6:04:25 PM
Aldrin	ND	0.00902		mg/Kg-dry	1	8/7/2017 6:04:25 PM
Heptachlor epoxide	ND	0.00902		mg/Kg-dry	1	8/7/2017 6:04:25 PM
gamma-Chlordane	ND	0.00902		mg/Kg-dry	1	8/7/2017 6:04:25 PM
Endosulfan I	ND	0.00902		mg/Kg-dry	1	8/7/2017 6:04:25 PM
alpha-Chlordane	ND	0.00902		mg/Kg-dry	1	8/7/2017 6:04:25 PM
Dieldrin	ND	0.00902		mg/Kg-dry	1	8/7/2017 6:04:25 PM
4,4'-DDE	ND	0.00902		mg/Kg-dry	1	8/7/2017 6:04:25 PM
Endrin	ND	0.00902		mg/Kg-dry	1	8/7/2017 6:04:25 PM
Endosulfan II	ND	0.00902		mg/Kg-dry	1	8/7/2017 6:04:25 PM
4,4'-DDD	ND	0.00902		mg/Kg-dry	1	8/7/2017 6:04:25 PM
Endrin aldehyde	ND	0.00902		mg/Kg-dry	1	8/7/2017 6:04:25 PM
Endosulfan sulfate	ND	0.00902		mg/Kg-dry	1	8/7/2017 6:04:25 PM
4,4'-DDT	ND	0.00902		mg/Kg-dry	1	8/7/2017 6:04:25 PM
Endrin ketone	ND	0.00902		mg/Kg-dry	1	8/7/2017 6:04:25 PM
Methoxychlor	ND	0.00902		mg/Kg-dry	1	8/7/2017 6:04:25 PM
Surr: Decachlorobiphenyl	97.4	17.8 - 157		%Rec	1	8/7/2017 6:04:25 PM
Surr: Tetrachloro-m-xylene	89.7	11 - 150		%Rec	1	8/7/2017 6:04:25 PM

Herbicides by EPA Method 8151A

Batch ID: 17825

Analyst: BT

Dicamba	ND	33.9		µg/Kg-dry	1	8/10/2017 1:31:30 AM
2,4-D	ND	29.1		µg/Kg-dry	1	8/10/2017 1:31:30 AM
2,4-DP	ND	24.2		µg/Kg-dry	1	8/10/2017 1:31:30 AM
2,4,5-TP (Silvex)	ND	19.4		µg/Kg-dry	1	8/10/2017 1:31:30 AM
2,4,5-T	ND	48.5		µg/Kg-dry	1	8/10/2017 1:31:30 AM
Dinoseb	ND	29.1		µg/Kg-dry	1	8/10/2017 1:31:30 AM
Dalapon	ND	194		µg/Kg-dry	1	8/10/2017 1:31:30 AM
2,4-DB	ND	24.2		µg/Kg-dry	1	8/10/2017 1:31:30 AM
MCPP	ND	4,270		µg/Kg-dry	1	8/10/2017 1:31:30 AM
MCPA	ND	2,720		µg/Kg-dry	1	8/10/2017 1:31:30 AM
Picloram	ND	48.5		µg/Kg-dry	1	8/10/2017 1:31:30 AM
Bentazon	ND	33.9		µg/Kg-dry	1	8/10/2017 1:31:30 AM
Chloramben	ND	19.4		µg/Kg-dry	1	8/10/2017 1:31:30 AM



Client: Shannon & Wilson

Collection Date: 7/25/2017 9:22:00 AM

Project: Yakima EWC

Lab ID: 1707301-001

Matrix: Soil

Client Sample ID: ES-1

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Herbicides by EPA Method 8151A

Batch ID: 17825 Analyst: BT

Acifluorfen	ND	77.6		µg/Kg-dry	1	8/10/2017 1:31:30 AM
3,5-Dichlorobenzoic acid	ND	38.8		µg/Kg-dry	1	8/10/2017 1:31:30 AM
4-Nitrophenol	ND	29.1		µg/Kg-dry	1	8/10/2017 1:31:30 AM
Dacthal (DCPA)	ND	29.1		µg/Kg-dry	1	8/10/2017 1:31:30 AM
Surr: 2,4-Dichlorophenylacetic acid	3.40	20.1 - 168	S	%Rec	1	8/10/2017 1:31:30 AM

NOTES:

S - Outlying surrogate recovery(ies) observed. A duplicate analysis was performed and recovered within range.

Mercury by EPA Method 7471

Batch ID: 17818 Analyst: WF

Mercury	ND	0.208		mg/Kg-dry	1	8/3/2017 4:03:05 PM
---------	----	-------	--	-----------	---	---------------------

Total Metals by EPA Method 6020

Batch ID: 17796 Analyst: TN

Arsenic	3.24	0.0764		mg/Kg-dry	1	8/2/2017 2:10:43 PM
Barium	71.0	0.382		mg/Kg-dry	1	8/2/2017 2:10:43 PM
Cadmium	ND	0.153		mg/Kg-dry	1	8/2/2017 2:10:43 PM
Chromium	38.1	0.0764		mg/Kg-dry	1	8/2/2017 2:10:43 PM
Copper	20.1	0.153		mg/Kg-dry	1	8/2/2017 2:10:43 PM
Lead	3.24	0.153		mg/Kg-dry	1	8/2/2017 2:10:43 PM
Nickel	62.0	0.0764		mg/Kg-dry	1	8/2/2017 2:10:43 PM
Selenium	1.95	0.382		mg/Kg-dry	1	8/2/2017 2:10:43 PM
Silver	ND	0.0775		mg/Kg-dry	1	8/3/2017 2:55:09 PM
Zinc	69.2	0.305		mg/Kg-dry	1	8/2/2017 2:10:43 PM

Sample Moisture (Percent Moisture)

Batch ID: R37765 Analyst: BB

Percent Moisture	3.72			wt%	1	8/2/2017 1:35:42 PM
------------------	------	--	--	-----	---	---------------------



Client: Shannon & Wilson

Collection Date: 7/26/2017 4:30:00 PM

Project: Yakima EWC

Lab ID: 1707301-002

Matrix: Soil

Client Sample ID: ES-2

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Polychlorinated Biphenyls (PCB) by EPA 8082

Batch ID: 17799

Analyst: SG

Aroclor 1016	ND	0.0889		mg/Kg-dry	1	8/2/2017 2:59:44 PM
Aroclor 1221	ND	0.0889		mg/Kg-dry	1	8/2/2017 2:59:44 PM
Aroclor 1232	ND	0.0889		mg/Kg-dry	1	8/2/2017 2:59:44 PM
Aroclor 1242	ND	0.0889		mg/Kg-dry	1	8/2/2017 2:59:44 PM
Aroclor 1248	ND	0.0889		mg/Kg-dry	1	8/2/2017 2:59:44 PM
Aroclor 1254	ND	0.0889		mg/Kg-dry	1	8/2/2017 2:59:44 PM
Aroclor 1260	ND	0.0889		mg/Kg-dry	1	8/2/2017 2:59:44 PM
Aroclor 1262	ND	0.0889		mg/Kg-dry	1	8/2/2017 2:59:44 PM
Aroclor 1268	ND	0.0889		mg/Kg-dry	1	8/2/2017 2:59:44 PM
Total PCBs	ND	0.0889		mg/Kg-dry	1	8/2/2017 2:59:44 PM
Surr: Decachlorobiphenyl	112	30.8 - 168		%Rec	1	8/2/2017 2:59:44 PM
Surr: Tetrachloro-m-xylene	100	30.1 - 143		%Rec	1	8/2/2017 2:59:44 PM

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Batch ID: 17798

Analyst: SB

Diesel (Fuel Oil)	ND	18.3		mg/Kg-dry	1	8/2/2017 5:25:46 PM
Heavy Oil	ND	45.8		mg/Kg-dry	1	8/2/2017 5:25:46 PM
Surr: 2-Fluorobiphenyl	83.5	50 - 150		%Rec	1	8/2/2017 5:25:46 PM
Surr: o-Terphenyl	85.9	50 - 150		%Rec	1	8/2/2017 5:25:46 PM

Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Batch ID: 17800

Analyst: BT

Naphthalene	ND	41.5		µg/Kg-dry	1	8/2/2017 7:12:26 PM
2-Methylnaphthalene	ND	41.5		µg/Kg-dry	1	8/2/2017 7:12:26 PM
1-Methylnaphthalene	ND	41.5		µg/Kg-dry	1	8/2/2017 7:12:26 PM
Acenaphthylene	ND	41.5		µg/Kg-dry	1	8/2/2017 7:12:26 PM
Acenaphthene	ND	41.5		µg/Kg-dry	1	8/2/2017 7:12:26 PM
Fluorene	ND	41.5		µg/Kg-dry	1	8/2/2017 7:12:26 PM
Phenanthrene	ND	41.5		µg/Kg-dry	1	8/2/2017 7:12:26 PM
Anthracene	ND	41.5		µg/Kg-dry	1	8/2/2017 7:12:26 PM
Fluoranthene	ND	41.5		µg/Kg-dry	1	8/2/2017 7:12:26 PM
Pyrene	ND	41.5		µg/Kg-dry	1	8/2/2017 7:12:26 PM
Benz(a)anthracene	ND	41.5		µg/Kg-dry	1	8/2/2017 7:12:26 PM
Chrysene	ND	41.5		µg/Kg-dry	1	8/2/2017 7:12:26 PM
Benzo(b)fluoranthene	ND	41.5		µg/Kg-dry	1	8/2/2017 7:12:26 PM
Benzo(j,k)fluoranthene	ND	41.5		µg/Kg-dry	1	8/2/2017 7:12:26 PM
Benzo(a)pyrene	ND	41.5		µg/Kg-dry	1	8/2/2017 7:12:26 PM
Indeno(1,2,3-cd)pyrene	ND	41.5		µg/Kg-dry	1	8/2/2017 7:12:26 PM
Dibenz(a,h)anthracene	ND	41.5		µg/Kg-dry	1	8/2/2017 7:12:26 PM



Client: Shannon & Wilson

Collection Date: 7/26/2017 4:30:00 PM

Project: Yakima EWC

Lab ID: 1707301-002

Matrix: Soil

Client Sample ID: ES-2

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Batch ID: 17800 Analyst: BT

Benzo(g,h,i)perylene	ND	41.5		µg/Kg-dry	1	8/2/2017 7:12:26 PM
Surr: 2-Fluorobiphenyl	86.0	24.5 - 139		%Rec	1	8/2/2017 7:12:26 PM
Surr: Terphenyl-d14 (surr)	113	46.2 - 179		%Rec	1	8/2/2017 7:12:26 PM

Gasoline by NWTPH-Gx

Batch ID: 17817 Analyst: MW

Gasoline	ND	4.36		mg/Kg-dry	1	8/4/2017 5:35:09 AM
Surr: Toluene-d8	105	65 - 135		%Rec	1	8/4/2017 5:35:09 AM
Surr: 4-Bromofluorobenzene	92.6	65 - 135		%Rec	1	8/4/2017 5:35:09 AM

Volatile Organic Compounds by EPA Method 8260C

Batch ID: 17817 Analyst: MW

Dichlorodifluoromethane (CFC-12)	ND	0.0175		mg/Kg-dry	1	8/4/2017 5:35:09 AM
Chloromethane	ND	0.0436		mg/Kg-dry	1	8/4/2017 5:35:09 AM
Vinyl chloride	ND	0.0218		mg/Kg-dry	1	8/4/2017 5:35:09 AM
Bromomethane	ND	0.0436		mg/Kg-dry	1	8/4/2017 5:35:09 AM
Trichlorofluoromethane (CFC-11)	ND	0.0175		mg/Kg-dry	1	8/4/2017 5:35:09 AM
Chloroethane	ND	0.0436		mg/Kg-dry	1	8/4/2017 5:35:09 AM
1,1-Dichloroethene	ND	0.0175		mg/Kg-dry	1	8/4/2017 5:35:09 AM
Methylene chloride	ND	0.0175		mg/Kg-dry	1	8/4/2017 5:35:09 AM
trans-1,2-Dichloroethene	ND	0.0175		mg/Kg-dry	1	8/4/2017 5:35:09 AM
Methyl tert-butyl ether (MTBE)	ND	0.0436		mg/Kg-dry	1	8/4/2017 5:35:09 AM
1,1-Dichloroethane	ND	0.0175		mg/Kg-dry	1	8/4/2017 5:35:09 AM
2,2-Dichloropropane	ND	0.0873	Q	mg/Kg-dry	1	8/4/2017 5:35:09 AM
cis-1,2-Dichloroethene	ND	0.0175		mg/Kg-dry	1	8/4/2017 5:35:09 AM
Chloroform	ND	0.0175		mg/Kg-dry	1	8/4/2017 5:35:09 AM
1,1,1-Trichloroethane (TCA)	ND	0.0218		mg/Kg-dry	1	8/4/2017 5:35:09 AM
1,1-Dichloropropene	ND	0.0175		mg/Kg-dry	1	8/4/2017 5:35:09 AM
Carbon tetrachloride	ND	0.0218		mg/Kg-dry	1	8/4/2017 5:35:09 AM
1,2-Dichloroethane (EDC)	ND	0.0175		mg/Kg-dry	1	8/4/2017 5:35:09 AM
Benzene	ND	0.0175		mg/Kg-dry	1	8/4/2017 5:35:09 AM
Trichloroethene (TCE)	ND	0.0175		mg/Kg-dry	1	8/4/2017 5:35:09 AM
1,2-Dichloropropane	ND	0.0175		mg/Kg-dry	1	8/4/2017 5:35:09 AM
Bromodichloromethane	ND	0.0175		mg/Kg-dry	1	8/4/2017 5:35:09 AM
Dibromomethane	ND	0.0175		mg/Kg-dry	1	8/4/2017 5:35:09 AM
cis-1,3-Dichloropropene	ND	0.0175		mg/Kg-dry	1	8/4/2017 5:35:09 AM
Toluene	ND	0.0175		mg/Kg-dry	1	8/4/2017 5:35:09 AM
trans-1,3-Dichloropropylene	ND	0.0175		mg/Kg-dry	1	8/4/2017 5:35:09 AM
1,1,2-Trichloroethane	ND	0.0175		mg/Kg-dry	1	8/4/2017 5:35:09 AM



Analytical Report

Work Order: 1707301
Date Reported: 8/14/2017

Client: Shannon & Wilson

Collection Date: 7/26/2017 4:30:00 PM

Project: Yakima EWC

Lab ID: 1707301-002

Matrix: Soil

Client Sample ID: ES-2

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Volatile Organic Compounds by EPA Method 8260C

Batch ID: 17817

Analyst: MW

1,3-Dichloropropane	ND	0.0218		mg/Kg-dry	1	8/4/2017 5:35:09 AM
Tetrachloroethene (PCE)	ND	0.0218		mg/Kg-dry	1	8/4/2017 5:35:09 AM
Dibromochloromethane	ND	0.0218		mg/Kg-dry	1	8/4/2017 5:35:09 AM
1,2-Dibromoethane (EDB)	ND	0.00436		mg/Kg-dry	1	8/4/2017 5:35:09 AM
Chlorobenzene	ND	0.0218		mg/Kg-dry	1	8/4/2017 5:35:09 AM
1,1,1,2-Tetrachloroethane	ND	0.0218		mg/Kg-dry	1	8/4/2017 5:35:09 AM
Ethylbenzene	ND	0.0218		mg/Kg-dry	1	8/4/2017 5:35:09 AM
m,p-Xylene	ND	0.0436		mg/Kg-dry	1	8/4/2017 5:35:09 AM
o-Xylene	ND	0.0218		mg/Kg-dry	1	8/4/2017 5:35:09 AM
Styrene	ND	0.0218		mg/Kg-dry	1	8/4/2017 5:35:09 AM
Isopropylbenzene	ND	0.0218		mg/Kg-dry	1	8/4/2017 5:35:09 AM
Bromoform	ND	0.0436		mg/Kg-dry	1	8/4/2017 5:35:09 AM
1,1,2,2-Tetrachloroethane	ND	0.0175		mg/Kg-dry	1	8/4/2017 5:35:09 AM
n-Propylbenzene	ND	0.0218		mg/Kg-dry	1	8/4/2017 5:35:09 AM
Bromobenzene	ND	0.0175		mg/Kg-dry	1	8/4/2017 5:35:09 AM
1,3,5-Trimethylbenzene	ND	0.0218		mg/Kg-dry	1	8/4/2017 5:35:09 AM
2-Chlorotoluene	ND	0.0218		mg/Kg-dry	1	8/4/2017 5:35:09 AM
4-Chlorotoluene	ND	0.0218		mg/Kg-dry	1	8/4/2017 5:35:09 AM
tert-Butylbenzene	ND	0.0218		mg/Kg-dry	1	8/4/2017 5:35:09 AM
1,2,3-Trichloropropane	ND	0.0218		mg/Kg-dry	1	8/4/2017 5:35:09 AM
1,2,4-Trichlorobenzene	ND	0.0218		mg/Kg-dry	1	8/4/2017 5:35:09 AM
sec-Butylbenzene	ND	0.0436		mg/Kg-dry	1	8/4/2017 5:35:09 AM
4-Isopropyltoluene	ND	0.0436		mg/Kg-dry	1	8/4/2017 5:35:09 AM
1,3-Dichlorobenzene	ND	0.0175		mg/Kg-dry	1	8/4/2017 5:35:09 AM
1,4-Dichlorobenzene	ND	0.0175		mg/Kg-dry	1	8/4/2017 5:35:09 AM
n-Butylbenzene	ND	0.0218		mg/Kg-dry	1	8/4/2017 5:35:09 AM
1,2-Dichlorobenzene	ND	0.0175		mg/Kg-dry	1	8/4/2017 5:35:09 AM
1,2-Dibromo-3-chloropropane	ND	0.436		mg/Kg-dry	1	8/4/2017 5:35:09 AM
1,2,4-Trimethylbenzene	ND	0.0175		mg/Kg-dry	1	8/4/2017 5:35:09 AM
Hexachlorobutadiene	ND	0.0436		mg/Kg-dry	1	8/4/2017 5:35:09 AM
Naphthalene	ND	0.0436		mg/Kg-dry	1	8/4/2017 5:35:09 AM
1,2,3-Trichlorobenzene	ND	0.0175		mg/Kg-dry	1	8/4/2017 5:35:09 AM
Surr: Dibromofluoromethane	88.1	56.5 - 129		%Rec	1	8/4/2017 5:35:09 AM
Surr: Toluene-d8	102	64.5 - 151		%Rec	1	8/4/2017 5:35:09 AM
Surr: 1-Bromo-4-fluorobenzene	89.3	63.1 - 141		%Rec	1	8/4/2017 5:35:09 AM

NOTES:

Q - Indicates an analyte with a continuing calibration that does not meet established acceptance criteria (<20%RSD, <20% Drift or minimum RRF).



Client: Shannon & Wilson

Collection Date: 7/26/2017 4:30:00 PM

Project: Yakima EWC

Lab ID: 1707301-002

Matrix: Soil

Client Sample ID: ES-2

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Mercury by EPA Method 7471

Batch ID: 17818 Analyst: WF

Mercury	ND	0.196		mg/Kg-dry	1	8/3/2017 4:09:35 PM
---------	----	-------	--	-----------	---	---------------------

Total Metals by EPA Method 6020

Batch ID: 17796 Analyst: TN

Arsenic	2.32	0.0747		mg/Kg-dry	1	8/2/2017 2:14:44 PM
Barium	57.5	0.374		mg/Kg-dry	1	8/2/2017 2:14:44 PM
Cadmium	ND	0.149		mg/Kg-dry	1	8/2/2017 2:14:44 PM
Chromium	18.1	0.0747		mg/Kg-dry	1	8/2/2017 2:14:44 PM
Copper	14.2	0.149		mg/Kg-dry	1	8/2/2017 2:14:44 PM
Lead	2.29	0.149		mg/Kg-dry	1	8/2/2017 2:14:44 PM
Nickel	19.3	0.0747		mg/Kg-dry	1	8/2/2017 2:14:44 PM
Selenium	1.50	0.374		mg/Kg-dry	1	8/2/2017 2:14:44 PM
Silver	ND	0.0818		mg/Kg-dry	1	8/3/2017 2:59:11 PM
Zinc	40.8	0.299		mg/Kg-dry	1	8/2/2017 2:14:44 PM

Sample Moisture (Percent Moisture)

Batch ID: R37765 Analyst: BB

Percent Moisture	3.74			wt%	1	8/2/2017 1:35:42 PM
------------------	------	--	--	-----	---	---------------------



Client: Shannon & Wilson

Collection Date: 7/26/2017 4:40:00 PM

Project: Yakima EWC

Lab ID: 1707301-003

Matrix: Soil

Client Sample ID: ES-3

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Polychlorinated Biphenyls (PCB) by EPA 8082

Batch ID: 17799

Analyst: SG

Aroclor 1016	ND	0.105		mg/Kg-dry	1	8/2/2017 3:09:50 PM
Aroclor 1221	ND	0.105		mg/Kg-dry	1	8/2/2017 3:09:50 PM
Aroclor 1232	ND	0.105		mg/Kg-dry	1	8/2/2017 3:09:50 PM
Aroclor 1242	ND	0.105		mg/Kg-dry	1	8/2/2017 3:09:50 PM
Aroclor 1248	ND	0.105		mg/Kg-dry	1	8/2/2017 3:09:50 PM
Aroclor 1254	ND	0.105		mg/Kg-dry	1	8/2/2017 3:09:50 PM
Aroclor 1260	ND	0.105		mg/Kg-dry	1	8/2/2017 3:09:50 PM
Aroclor 1262	ND	0.105		mg/Kg-dry	1	8/2/2017 3:09:50 PM
Aroclor 1268	ND	0.105		mg/Kg-dry	1	8/2/2017 3:09:50 PM
Total PCBs	ND	0.105		mg/Kg-dry	1	8/2/2017 3:09:50 PM
Surr: Decachlorobiphenyl	111	30.8 - 168		%Rec	1	8/2/2017 3:09:50 PM
Surr: Tetrachloro-m-xylene	96.7	30.1 - 143		%Rec	1	8/2/2017 3:09:50 PM

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Batch ID: 17798

Analyst: SB

Diesel (Fuel Oil)	ND	20.2		mg/Kg-dry	1	8/2/2017 5:56:43 PM
Heavy Oil	ND	50.5		mg/Kg-dry	1	8/2/2017 5:56:43 PM
Surr: 2-Fluorobiphenyl	67.5	50 - 150		%Rec	1	8/2/2017 5:56:43 PM
Surr: o-Terphenyl	70.1	50 - 150		%Rec	1	8/2/2017 5:56:43 PM

Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Batch ID: 17800

Analyst: BT

Naphthalene	ND	39.6		µg/Kg-dry	1	8/2/2017 8:49:35 PM
2-Methylnaphthalene	ND	39.6		µg/Kg-dry	1	8/2/2017 8:49:35 PM
1-Methylnaphthalene	ND	39.6		µg/Kg-dry	1	8/2/2017 8:49:35 PM
Acenaphthylene	ND	39.6		µg/Kg-dry	1	8/2/2017 8:49:35 PM
Acenaphthene	ND	39.6		µg/Kg-dry	1	8/2/2017 8:49:35 PM
Fluorene	ND	39.6		µg/Kg-dry	1	8/2/2017 8:49:35 PM
Phenanthrene	ND	39.6		µg/Kg-dry	1	8/2/2017 8:49:35 PM
Anthracene	ND	39.6		µg/Kg-dry	1	8/2/2017 8:49:35 PM
Fluoranthene	ND	39.6		µg/Kg-dry	1	8/2/2017 8:49:35 PM
Pyrene	ND	39.6		µg/Kg-dry	1	8/2/2017 8:49:35 PM
Benz(a)anthracene	ND	39.6		µg/Kg-dry	1	8/2/2017 8:49:35 PM
Chrysene	ND	39.6		µg/Kg-dry	1	8/2/2017 8:49:35 PM
Benzo(b)fluoranthene	ND	39.6		µg/Kg-dry	1	8/2/2017 8:49:35 PM
Benzo(j,k)fluoranthene	ND	39.6		µg/Kg-dry	1	8/2/2017 8:49:35 PM
Benzo(a)pyrene	ND	39.6		µg/Kg-dry	1	8/2/2017 8:49:35 PM
Indeno(1,2,3-cd)pyrene	ND	39.6		µg/Kg-dry	1	8/2/2017 8:49:35 PM
Dibenz(a,h)anthracene	ND	39.6		µg/Kg-dry	1	8/2/2017 8:49:35 PM



Client: Shannon & Wilson

Collection Date: 7/26/2017 4:40:00 PM

Project: Yakima EWC

Lab ID: 1707301-003

Matrix: Soil

Client Sample ID: ES-3

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Batch ID: 17800 Analyst: BT

Benzo(g,h,i)perylene	ND	39.6		µg/Kg-dry	1	8/2/2017 8:49:35 PM
Surr: 2-Fluorobiphenyl	63.5	24.5 - 139		%Rec	1	8/2/2017 8:49:35 PM
Surr: Terphenyl-d14 (surr)	118	46.2 - 179		%Rec	1	8/2/2017 8:49:35 PM

Gasoline by NWTPH-Gx

Batch ID: 17817 Analyst: MW

Gasoline	ND	5.18		mg/Kg-dry	1	8/4/2017 6:32:28 AM
Surr: Toluene-d8	105	65 - 135		%Rec	1	8/4/2017 6:32:28 AM
Surr: 4-Bromofluorobenzene	90.9	65 - 135		%Rec	1	8/4/2017 6:32:28 AM

Volatile Organic Compounds by EPA Method 8260C

Batch ID: 17817 Analyst: MW

Dichlorodifluoromethane (CFC-12)	ND	0.0207		mg/Kg-dry	1	8/4/2017 6:32:28 AM
Chloromethane	ND	0.0518		mg/Kg-dry	1	8/4/2017 6:32:28 AM
Vinyl chloride	ND	0.0259		mg/Kg-dry	1	8/4/2017 6:32:28 AM
Bromomethane	ND	0.0518		mg/Kg-dry	1	8/4/2017 6:32:28 AM
Trichlorofluoromethane (CFC-11)	ND	0.0207		mg/Kg-dry	1	8/4/2017 6:32:28 AM
Chloroethane	ND	0.0518		mg/Kg-dry	1	8/4/2017 6:32:28 AM
1,1-Dichloroethene	ND	0.0207		mg/Kg-dry	1	8/4/2017 6:32:28 AM
Methylene chloride	ND	0.0207		mg/Kg-dry	1	8/4/2017 6:32:28 AM
trans-1,2-Dichloroethene	ND	0.0207		mg/Kg-dry	1	8/4/2017 6:32:28 AM
Methyl tert-butyl ether (MTBE)	ND	0.0518		mg/Kg-dry	1	8/4/2017 6:32:28 AM
1,1-Dichloroethane	ND	0.0207		mg/Kg-dry	1	8/4/2017 6:32:28 AM
2,2-Dichloropropane	ND	0.104	Q	mg/Kg-dry	1	8/4/2017 6:32:28 AM
cis-1,2-Dichloroethene	ND	0.0207		mg/Kg-dry	1	8/4/2017 6:32:28 AM
Chloroform	ND	0.0207		mg/Kg-dry	1	8/4/2017 6:32:28 AM
1,1,1-Trichloroethane (TCA)	ND	0.0259		mg/Kg-dry	1	8/4/2017 6:32:28 AM
1,1-Dichloropropene	ND	0.0207		mg/Kg-dry	1	8/4/2017 6:32:28 AM
Carbon tetrachloride	ND	0.0259		mg/Kg-dry	1	8/4/2017 6:32:28 AM
1,2-Dichloroethane (EDC)	ND	0.0207		mg/Kg-dry	1	8/4/2017 6:32:28 AM
Benzene	ND	0.0207		mg/Kg-dry	1	8/4/2017 6:32:28 AM
Trichloroethene (TCE)	ND	0.0207		mg/Kg-dry	1	8/4/2017 6:32:28 AM
1,2-Dichloropropane	ND	0.0207		mg/Kg-dry	1	8/4/2017 6:32:28 AM
Bromodichloromethane	ND	0.0207		mg/Kg-dry	1	8/4/2017 6:32:28 AM
Dibromomethane	ND	0.0207		mg/Kg-dry	1	8/4/2017 6:32:28 AM
cis-1,3-Dichloropropene	ND	0.0207		mg/Kg-dry	1	8/4/2017 6:32:28 AM
Toluene	ND	0.0207		mg/Kg-dry	1	8/4/2017 6:32:28 AM
trans-1,3-Dichloropropylene	ND	0.0207		mg/Kg-dry	1	8/4/2017 6:32:28 AM
1,1,2-Trichloroethane	ND	0.0207		mg/Kg-dry	1	8/4/2017 6:32:28 AM



Client: Shannon & Wilson

Collection Date: 7/26/2017 4:40:00 PM

Project: Yakima EWC

Lab ID: 1707301-003

Matrix: Soil

Client Sample ID: ES-3

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Volatile Organic Compounds by EPA Method 8260C

Batch ID: 17817

Analyst: MW

1,3-Dichloropropane	ND	0.0259		mg/Kg-dry	1	8/4/2017 6:32:28 AM
Tetrachloroethene (PCE)	ND	0.0259		mg/Kg-dry	1	8/4/2017 6:32:28 AM
Dibromochloromethane	ND	0.0259		mg/Kg-dry	1	8/4/2017 6:32:28 AM
1,2-Dibromoethane (EDB)	ND	0.00518		mg/Kg-dry	1	8/4/2017 6:32:28 AM
Chlorobenzene	ND	0.0259		mg/Kg-dry	1	8/4/2017 6:32:28 AM
1,1,1,2-Tetrachloroethane	ND	0.0259		mg/Kg-dry	1	8/4/2017 6:32:28 AM
Ethylbenzene	ND	0.0259		mg/Kg-dry	1	8/4/2017 6:32:28 AM
m,p-Xylene	ND	0.0518		mg/Kg-dry	1	8/4/2017 6:32:28 AM
o-Xylene	ND	0.0259		mg/Kg-dry	1	8/4/2017 6:32:28 AM
Styrene	ND	0.0259		mg/Kg-dry	1	8/4/2017 6:32:28 AM
Isopropylbenzene	ND	0.0259		mg/Kg-dry	1	8/4/2017 6:32:28 AM
Bromoform	ND	0.0518		mg/Kg-dry	1	8/4/2017 6:32:28 AM
1,1,2,2-Tetrachloroethane	ND	0.0207		mg/Kg-dry	1	8/4/2017 6:32:28 AM
n-Propylbenzene	ND	0.0259		mg/Kg-dry	1	8/4/2017 6:32:28 AM
Bromobenzene	ND	0.0207		mg/Kg-dry	1	8/4/2017 6:32:28 AM
1,3,5-Trimethylbenzene	ND	0.0259		mg/Kg-dry	1	8/4/2017 6:32:28 AM
2-Chlorotoluene	ND	0.0259		mg/Kg-dry	1	8/4/2017 6:32:28 AM
4-Chlorotoluene	ND	0.0259		mg/Kg-dry	1	8/4/2017 6:32:28 AM
tert-Butylbenzene	ND	0.0259		mg/Kg-dry	1	8/4/2017 6:32:28 AM
1,2,3-Trichloropropane	ND	0.0259		mg/Kg-dry	1	8/4/2017 6:32:28 AM
1,2,4-Trichlorobenzene	ND	0.0259		mg/Kg-dry	1	8/4/2017 6:32:28 AM
sec-Butylbenzene	ND	0.0518		mg/Kg-dry	1	8/4/2017 6:32:28 AM
4-Isopropyltoluene	ND	0.0518		mg/Kg-dry	1	8/4/2017 6:32:28 AM
1,3-Dichlorobenzene	ND	0.0207		mg/Kg-dry	1	8/4/2017 6:32:28 AM
1,4-Dichlorobenzene	ND	0.0207		mg/Kg-dry	1	8/4/2017 6:32:28 AM
n-Butylbenzene	ND	0.0259		mg/Kg-dry	1	8/4/2017 6:32:28 AM
1,2-Dichlorobenzene	ND	0.0207		mg/Kg-dry	1	8/4/2017 6:32:28 AM
1,2-Dibromo-3-chloropropane	ND	0.518		mg/Kg-dry	1	8/4/2017 6:32:28 AM
1,2,4-Trimethylbenzene	ND	0.0207		mg/Kg-dry	1	8/4/2017 6:32:28 AM
Hexachlorobutadiene	ND	0.0518		mg/Kg-dry	1	8/4/2017 6:32:28 AM
Naphthalene	ND	0.0518		mg/Kg-dry	1	8/4/2017 6:32:28 AM
1,2,3-Trichlorobenzene	ND	0.0207		mg/Kg-dry	1	8/4/2017 6:32:28 AM
Surr: Dibromofluoromethane	85.3	56.5 - 129		%Rec	1	8/4/2017 6:32:28 AM
Surr: Toluene-d8	102	64.5 - 151		%Rec	1	8/4/2017 6:32:28 AM
Surr: 1-Bromo-4-fluorobenzene	87.5	63.1 - 141		%Rec	1	8/4/2017 6:32:28 AM

NOTES:

Q - Indicates an analyte with a continuing calibration that does not meet established acceptance criteria (<20%RSD, <20% Drift or minimum RRF).



Client: Shannon & Wilson

Collection Date: 7/26/2017 4:40:00 PM

Project: Yakima EWC

Lab ID: 1707301-003

Matrix: Soil

Client Sample ID: ES-3

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Mercury by EPA Method 7471

Batch ID: 17818 Analyst: WF

Mercury	ND	0.208		mg/Kg-dry	1	8/3/2017 4:11:10 PM
---------	----	-------	--	-----------	---	---------------------

Total Metals by EPA Method 6020

Batch ID: 17796 Analyst: TN

Arsenic	1.98	0.0850		mg/Kg-dry	1	8/2/2017 2:18:46 PM
Barium	51.9	0.425		mg/Kg-dry	1	8/2/2017 2:18:46 PM
Cadmium	ND	0.170		mg/Kg-dry	1	8/2/2017 2:18:46 PM
Chromium	13.2	0.0850		mg/Kg-dry	1	8/2/2017 2:18:46 PM
Copper	16.0	0.170		mg/Kg-dry	1	8/2/2017 2:18:46 PM
Lead	1.58	0.170		mg/Kg-dry	1	8/2/2017 2:18:46 PM
Nickel	17.9	0.0850		mg/Kg-dry	1	8/2/2017 2:18:46 PM
Selenium	1.97	0.425		mg/Kg-dry	1	8/2/2017 2:18:46 PM
Silver	ND	0.0818		mg/Kg-dry	1	8/3/2017 3:03:12 PM
Zinc	40.3	0.340		mg/Kg-dry	1	8/2/2017 2:18:46 PM

Sample Moisture (Percent Moisture)

Batch ID: R37765 Analyst: BB

Percent Moisture	7.40			wt%	1	8/2/2017 1:35:42 PM
------------------	------	--	--	-----	---	---------------------



Client: Shannon & Wilson

Collection Date: 7/27/2017 7:45:00 AM

Project: Yakima EWC

Lab ID: 1707301-004

Matrix: Soil

Client Sample ID: ES-4

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Polychlorinated Biphenyls (PCB) by EPA 8082

Batch ID: 17799

Analyst: SG

Aroclor 1016	ND	0.106		mg/Kg-dry	1	8/2/2017 3:19:52 PM
Aroclor 1221	ND	0.106		mg/Kg-dry	1	8/2/2017 3:19:52 PM
Aroclor 1232	ND	0.106		mg/Kg-dry	1	8/2/2017 3:19:52 PM
Aroclor 1242	ND	0.106		mg/Kg-dry	1	8/2/2017 3:19:52 PM
Aroclor 1248	ND	0.106		mg/Kg-dry	1	8/2/2017 3:19:52 PM
Aroclor 1254	ND	0.106		mg/Kg-dry	1	8/2/2017 3:19:52 PM
Aroclor 1260	ND	0.106		mg/Kg-dry	1	8/2/2017 3:19:52 PM
Aroclor 1262	ND	0.106		mg/Kg-dry	1	8/2/2017 3:19:52 PM
Aroclor 1268	ND	0.106		mg/Kg-dry	1	8/2/2017 3:19:52 PM
Total PCBs	ND	0.106		mg/Kg-dry	1	8/2/2017 3:19:52 PM
Surr: Decachlorobiphenyl	144	30.8 - 168		%Rec	1	8/2/2017 3:19:52 PM
Surr: Tetrachloro-m-xylene	113	30.1 - 143		%Rec	1	8/2/2017 3:19:52 PM

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Batch ID: 17814

Analyst: SB

Diesel (Fuel Oil)	ND	18.8		mg/Kg-dry	1	8/3/2017 10:24:43 PM
Heavy Oil	ND	47.0		mg/Kg-dry	1	8/3/2017 10:24:43 PM
Surr: 2-Fluorobiphenyl	91.4	50 - 150		%Rec	1	8/3/2017 10:24:43 PM
Surr: o-Terphenyl	98.7	50 - 150		%Rec	1	8/3/2017 10:24:43 PM

Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Batch ID: 17800

Analyst: BT

Naphthalene	ND	44.2		µg/Kg-dry	1	8/2/2017 9:13:27 PM
2-Methylnaphthalene	ND	44.2		µg/Kg-dry	1	8/2/2017 9:13:27 PM
1-Methylnaphthalene	ND	44.2		µg/Kg-dry	1	8/2/2017 9:13:27 PM
Acenaphthylene	ND	44.2		µg/Kg-dry	1	8/2/2017 9:13:27 PM
Acenaphthene	ND	44.2		µg/Kg-dry	1	8/2/2017 9:13:27 PM
Fluorene	ND	44.2		µg/Kg-dry	1	8/2/2017 9:13:27 PM
Phenanthrene	ND	44.2		µg/Kg-dry	1	8/2/2017 9:13:27 PM
Anthracene	ND	44.2		µg/Kg-dry	1	8/2/2017 9:13:27 PM
Fluoranthene	ND	44.2		µg/Kg-dry	1	8/2/2017 9:13:27 PM
Pyrene	ND	44.2		µg/Kg-dry	1	8/2/2017 9:13:27 PM
Benz(a)anthracene	ND	44.2		µg/Kg-dry	1	8/2/2017 9:13:27 PM
Chrysene	ND	44.2		µg/Kg-dry	1	8/2/2017 9:13:27 PM
Benzo(b)fluoranthene	ND	44.2		µg/Kg-dry	1	8/2/2017 9:13:27 PM
Benzo(j,k)fluoranthene	ND	44.2		µg/Kg-dry	1	8/2/2017 9:13:27 PM
Benzo(a)pyrene	ND	44.2		µg/Kg-dry	1	8/2/2017 9:13:27 PM
Indeno(1,2,3-cd)pyrene	ND	44.2		µg/Kg-dry	1	8/2/2017 9:13:27 PM
Dibenz(a,h)anthracene	ND	44.2		µg/Kg-dry	1	8/2/2017 9:13:27 PM



Client: Shannon & Wilson

Collection Date: 7/27/2017 7:45:00 AM

Project: Yakima EWC

Lab ID: 1707301-004

Matrix: Soil

Client Sample ID: ES-4

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Batch ID: 17800 Analyst: BT

Benzo(g,h,i)perylene	ND	44.2		µg/Kg-dry	1	8/2/2017 9:13:27 PM
Surr: 2-Fluorobiphenyl	43.1	24.5 - 139		%Rec	1	8/2/2017 9:13:27 PM
Surr: Terphenyl-d14 (surr)	103	46.2 - 179		%Rec	1	8/2/2017 9:13:27 PM

Gasoline by NWTPH-Gx

Batch ID: 17817 Analyst: MW

Gasoline	ND	5.44		mg/Kg-dry	1	8/4/2017 7:01:05 AM
Surr: Toluene-d8	106	65 - 135		%Rec	1	8/4/2017 7:01:05 AM
Surr: 4-Bromofluorobenzene	90.6	65 - 135		%Rec	1	8/4/2017 7:01:05 AM

Volatile Organic Compounds by EPA Method 8260C

Batch ID: 17817 Analyst: MW

Dichlorodifluoromethane (CFC-12)	ND	0.0218		mg/Kg-dry	1	8/4/2017 7:01:05 AM
Chloromethane	ND	0.0544		mg/Kg-dry	1	8/4/2017 7:01:05 AM
Vinyl chloride	ND	0.0272		mg/Kg-dry	1	8/4/2017 7:01:05 AM
Bromomethane	ND	0.0544		mg/Kg-dry	1	8/4/2017 7:01:05 AM
Trichlorofluoromethane (CFC-11)	ND	0.0218		mg/Kg-dry	1	8/4/2017 7:01:05 AM
Chloroethane	ND	0.0544		mg/Kg-dry	1	8/4/2017 7:01:05 AM
1,1-Dichloroethene	ND	0.0218		mg/Kg-dry	1	8/4/2017 7:01:05 AM
Methylene chloride	ND	0.0218		mg/Kg-dry	1	8/4/2017 7:01:05 AM
trans-1,2-Dichloroethene	ND	0.0218		mg/Kg-dry	1	8/4/2017 7:01:05 AM
Methyl tert-butyl ether (MTBE)	ND	0.0544		mg/Kg-dry	1	8/4/2017 7:01:05 AM
1,1-Dichloroethane	ND	0.0218		mg/Kg-dry	1	8/4/2017 7:01:05 AM
2,2-Dichloropropane	ND	0.109	Q	mg/Kg-dry	1	8/4/2017 7:01:05 AM
cis-1,2-Dichloroethene	ND	0.0218		mg/Kg-dry	1	8/4/2017 7:01:05 AM
Chloroform	ND	0.0218		mg/Kg-dry	1	8/4/2017 7:01:05 AM
1,1,1-Trichloroethane (TCA)	ND	0.0272		mg/Kg-dry	1	8/4/2017 7:01:05 AM
1,1-Dichloropropene	ND	0.0218		mg/Kg-dry	1	8/4/2017 7:01:05 AM
Carbon tetrachloride	ND	0.0272		mg/Kg-dry	1	8/4/2017 7:01:05 AM
1,2-Dichloroethane (EDC)	ND	0.0218		mg/Kg-dry	1	8/4/2017 7:01:05 AM
Benzene	ND	0.0218		mg/Kg-dry	1	8/4/2017 7:01:05 AM
Trichloroethene (TCE)	ND	0.0218		mg/Kg-dry	1	8/4/2017 7:01:05 AM
1,2-Dichloropropane	ND	0.0218		mg/Kg-dry	1	8/4/2017 7:01:05 AM
Bromodichloromethane	ND	0.0218		mg/Kg-dry	1	8/4/2017 7:01:05 AM
Dibromomethane	ND	0.0218		mg/Kg-dry	1	8/4/2017 7:01:05 AM
cis-1,3-Dichloropropene	ND	0.0218		mg/Kg-dry	1	8/4/2017 7:01:05 AM
Toluene	ND	0.0218		mg/Kg-dry	1	8/4/2017 7:01:05 AM
trans-1,3-Dichloropropylene	ND	0.0218		mg/Kg-dry	1	8/4/2017 7:01:05 AM
1,1,2-Trichloroethane	ND	0.0218		mg/Kg-dry	1	8/4/2017 7:01:05 AM



Analytical Report

Work Order: 1707301
Date Reported: 8/14/2017

Client: Shannon & Wilson

Collection Date: 7/27/2017 7:45:00 AM

Project: Yakima EWC

Lab ID: 1707301-004

Matrix: Soil

Client Sample ID: ES-4

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Volatile Organic Compounds by EPA Method 8260C

Batch ID: 17817

Analyst: MW

1,3-Dichloropropane	ND	0.0272		mg/Kg-dry	1	8/4/2017 7:01:05 AM
Tetrachloroethene (PCE)	ND	0.0272		mg/Kg-dry	1	8/4/2017 7:01:05 AM
Dibromochloromethane	ND	0.0272		mg/Kg-dry	1	8/4/2017 7:01:05 AM
1,2-Dibromoethane (EDB)	ND	0.00544		mg/Kg-dry	1	8/4/2017 7:01:05 AM
Chlorobenzene	ND	0.0272		mg/Kg-dry	1	8/4/2017 7:01:05 AM
1,1,1,2-Tetrachloroethane	ND	0.0272		mg/Kg-dry	1	8/4/2017 7:01:05 AM
Ethylbenzene	ND	0.0272		mg/Kg-dry	1	8/4/2017 7:01:05 AM
m,p-Xylene	ND	0.0544		mg/Kg-dry	1	8/4/2017 7:01:05 AM
o-Xylene	ND	0.0272		mg/Kg-dry	1	8/4/2017 7:01:05 AM
Styrene	ND	0.0272		mg/Kg-dry	1	8/4/2017 7:01:05 AM
Isopropylbenzene	ND	0.0272		mg/Kg-dry	1	8/4/2017 7:01:05 AM
Bromoform	ND	0.0544		mg/Kg-dry	1	8/4/2017 7:01:05 AM
1,1,2,2-Tetrachloroethane	ND	0.0218		mg/Kg-dry	1	8/4/2017 7:01:05 AM
n-Propylbenzene	ND	0.0272		mg/Kg-dry	1	8/4/2017 7:01:05 AM
Bromobenzene	ND	0.0218		mg/Kg-dry	1	8/4/2017 7:01:05 AM
1,3,5-Trimethylbenzene	ND	0.0272		mg/Kg-dry	1	8/4/2017 7:01:05 AM
2-Chlorotoluene	ND	0.0272		mg/Kg-dry	1	8/4/2017 7:01:05 AM
4-Chlorotoluene	ND	0.0272		mg/Kg-dry	1	8/4/2017 7:01:05 AM
tert-Butylbenzene	ND	0.0272		mg/Kg-dry	1	8/4/2017 7:01:05 AM
1,2,3-Trichloropropane	ND	0.0272		mg/Kg-dry	1	8/4/2017 7:01:05 AM
1,2,4-Trichlorobenzene	ND	0.0272		mg/Kg-dry	1	8/4/2017 7:01:05 AM
sec-Butylbenzene	ND	0.0544		mg/Kg-dry	1	8/4/2017 7:01:05 AM
4-Isopropyltoluene	ND	0.0544		mg/Kg-dry	1	8/4/2017 7:01:05 AM
1,3-Dichlorobenzene	ND	0.0218		mg/Kg-dry	1	8/4/2017 7:01:05 AM
1,4-Dichlorobenzene	ND	0.0218		mg/Kg-dry	1	8/4/2017 7:01:05 AM
n-Butylbenzene	ND	0.0272		mg/Kg-dry	1	8/4/2017 7:01:05 AM
1,2-Dichlorobenzene	ND	0.0218		mg/Kg-dry	1	8/4/2017 7:01:05 AM
1,2-Dibromo-3-chloropropane	ND	0.544		mg/Kg-dry	1	8/4/2017 7:01:05 AM
1,2,4-Trimethylbenzene	ND	0.0218		mg/Kg-dry	1	8/4/2017 7:01:05 AM
Hexachlorobutadiene	ND	0.0544		mg/Kg-dry	1	8/4/2017 7:01:05 AM
Naphthalene	ND	0.0544		mg/Kg-dry	1	8/4/2017 7:01:05 AM
1,2,3-Trichlorobenzene	ND	0.0218		mg/Kg-dry	1	8/4/2017 7:01:05 AM
Surr: Dibromofluoromethane	85.2	56.5 - 129		%Rec	1	8/4/2017 7:01:05 AM
Surr: Toluene-d8	102	64.5 - 151		%Rec	1	8/4/2017 7:01:05 AM
Surr: 1-Bromo-4-fluorobenzene	87.3	63.1 - 141		%Rec	1	8/4/2017 7:01:05 AM

NOTES:

Q - Indicates an analyte with a continuing calibration that does not meet established acceptance criteria (<20%RSD, <20% Drift or minimum RRF).



Client: Shannon & Wilson

Collection Date: 7/27/2017 7:45:00 AM

Project: Yakima EWC

Lab ID: 1707301-004

Matrix: Soil

Client Sample ID: ES-4

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Mercury by EPA Method 7471

Batch ID: 17818 Analyst: WF

Mercury	ND	0.211		mg/Kg-dry	1	8/3/2017 4:12:46 PM
---------	----	-------	--	-----------	---	---------------------

Total Metals by EPA Method 6020

Batch ID: 17796 Analyst: TN

Arsenic	1.79	0.0804		mg/Kg-dry	1	8/2/2017 2:22:47 PM
Barium	89.9	0.402		mg/Kg-dry	1	8/2/2017 2:22:47 PM
Cadmium	ND	0.161		mg/Kg-dry	1	8/2/2017 2:22:47 PM
Chromium	15.7	0.0804		mg/Kg-dry	1	8/2/2017 2:22:47 PM
Copper	16.6	0.161		mg/Kg-dry	1	8/2/2017 2:22:47 PM
Lead	2.05	0.161		mg/Kg-dry	1	8/2/2017 2:22:47 PM
Nickel	16.2	0.0804		mg/Kg-dry	1	8/2/2017 2:22:47 PM
Selenium	1.77	0.402		mg/Kg-dry	1	8/2/2017 2:22:47 PM
Silver	ND	0.0828		mg/Kg-dry	1	8/3/2017 3:07:13 PM
Zinc	45.3	0.322		mg/Kg-dry	1	8/2/2017 2:22:47 PM

Sample Moisture (Percent Moisture)

Batch ID: R37765 Analyst: BB

Percent Moisture	10.6			wt%	1	8/2/2017 1:35:42 PM
------------------	------	--	--	-----	---	---------------------

Work Order: 1707301
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Sample ID MB-17814	SampType: MBLK	Units: mg/Kg			Prep Date: 8/3/2017	RunNo: 37822					
Client ID: MBLKS	Batch ID: 17814				Analysis Date: 8/3/2017	SeqNo: 726906					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	ND	20.0									
Heavy Oil	ND	50.0									
Surr: 2-Fluorobiphenyl	18.1		20.00		90.3	50	150				
Surr: o-Terphenyl	19.5		20.00		97.4	50	150				

Sample ID LCS-17814	SampType: LCS	Units: mg/Kg			Prep Date: 8/3/2017	RunNo: 37822					
Client ID: LCSS	Batch ID: 17814				Analysis Date: 8/3/2017	SeqNo: 726905					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	488	20.0	500.0	0	97.5	65	135				
Surr: 2-Fluorobiphenyl	19.2		20.00		96.0	50	150				
Surr: o-Terphenyl	22.8		20.00		114	50	150				

Sample ID 1708031-022BDUP	SampType: DUP	Units: mg/Kg-dry			Prep Date: 8/3/2017	RunNo: 37822					
Client ID: BATCH	Batch ID: 17814				Analysis Date: 8/3/2017	SeqNo: 726892					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	ND	19.7						0		30	
Heavy Oil	ND	49.3						0		30	
Surr: 2-Fluorobiphenyl	19.3		19.74		97.8	50	150		0		
Surr: o-Terphenyl	21.4		19.74		108	50	150		0		

Sample ID 1708031-022BMS	SampType: MS	Units: mg/Kg-dry			Prep Date: 8/3/2017	RunNo: 37822					
Client ID: BATCH	Batch ID: 17814				Analysis Date: 8/3/2017	SeqNo: 726893					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	484	20.6	516.0	0	93.8	65	135				
Surr: 2-Fluorobiphenyl	14.7		20.64		71.4	50	150				
Surr: o-Terphenyl	17.7		20.64		85.9	50	150				

Work Order: 1707301
 CLIENT: Shannon & Wilson
 Project: Yakima EWC

QC SUMMARY REPORT
Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Sample ID	1708031-022BMS	SampType:	MS	Units:	mg/Kg-dry	Prep Date:	8/3/2017	RunNo:	37822				
Client ID:	BATCH	Batch ID:	17814			Analysis Date:	8/3/2017	SeqNo:	726893				
Analyte		Result		RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Sample ID	1708031-022BMSD	SampType:	MSD	Units:	mg/Kg-dry	Prep Date:	8/3/2017	RunNo:	37822				
Client ID:	BATCH	Batch ID:	17814			Analysis Date:	8/3/2017	SeqNo:	726894				
Analyte		Result		RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)		439		19.4	485.0	0	90.6	65	135	484.0	9.67	30	
Surr: 2-Fluorobiphenyl		18.4			19.40		94.6	50	150		0		
Surr: o-Terphenyl		21.5			19.40		111	50	150		0		

Sample ID	1708040-002ADUP	SampType:	DUP	Units:	mg/Kg-dry	Prep Date:	8/3/2017	RunNo:	37822				
Client ID:	BATCH	Batch ID:	17814			Analysis Date:	8/4/2017	SeqNo:	726902				
Analyte		Result		RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)		466		16.9						1,337	96.6	30	R
Heavy Oil		ND		42.3						0		30	
Surr: 2-Fluorobiphenyl		7.30			16.93		43.1	50	150		0		S
Surr: o-Terphenyl		11.1			16.93		65.5	50	150		0		

NOTES:

S - Outlying surrogate recovery(ies) observed. A duplicate analysis was performed and recovered within range.
 R - High RPD due to suspected sample inhomogeneity. The method is in control as indicated by the Laboratory Control Sample (LCS).

Work Order: 1707301
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Sample ID MB-17798	SampType: MBLK	Units: mg/Kg				Prep Date: 8/2/2017	RunNo: 37768				
Client ID: MBLKS	Batch ID: 17798					Analysis Date: 8/2/2017	SeqNo: 725963				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	ND	20.0									
Heavy Oil	ND	50.0									
Surr: 2-Fluorobiphenyl	15.9		20.00		79.4	50	150				
Surr: o-Terphenyl	16.4		20.00		82.2	50	150				

Sample ID LCS-17798	SampType: LCS	Units: mg/Kg				Prep Date: 8/2/2017	RunNo: 37768				
Client ID: LCSS	Batch ID: 17798					Analysis Date: 8/2/2017	SeqNo: 725958				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	523	20.0	500.0	0	105	65	135				
Surr: 2-Fluorobiphenyl	21.0		20.00		105	50	150				
Surr: o-Terphenyl	23.2		20.00		116	50	150				

Sample ID 1708015-001BDUP	SampType: DUP	Units: mg/Kg-dry				Prep Date: 8/2/2017	RunNo: 37768				
Client ID: BATCH	Batch ID: 17798					Analysis Date: 8/2/2017	SeqNo: 725959				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	ND	24.4						0		30	
Heavy Oil	ND	61.0						0		30	
Surr: 2-Fluorobiphenyl	18.9		24.39		77.7	50	150		0		
Surr: o-Terphenyl	20.1		24.39		82.6	50	150		0		

Sample ID 1708015-001BMS	SampType: MS	Units: mg/Kg-dry				Prep Date: 8/2/2017	RunNo: 37768				
Client ID: BATCH	Batch ID: 17798					Analysis Date: 8/2/2017	SeqNo: 726036				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	529	24.3	607.4	0	87.1	65	135				
Surr: 2-Fluorobiphenyl	21.9		24.30		90.1	50	150				
Surr: o-Terphenyl	24.3		24.30		100	50	150				

Work Order: 1707301
 CLIENT: Shannon & Wilson
 Project: Yakima EWC

QC SUMMARY REPORT
Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Sample ID 1708015-001BMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 8/2/2017	RunNo: 37768							
Client ID: BATCH	Batch ID: 17798	Analysis Date: 8/2/2017	SeqNo: 726036								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Sample ID 1708015-001BMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 8/2/2017	RunNo: 37768							
Client ID: BATCH	Batch ID: 17798	Analysis Date: 8/2/2017	SeqNo: 726037								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	567	23.9	596.5	0	95.1	65	135	529.1	6.92	30	
Surr: 2-Fluorobiphenyl	23.3		23.86		97.5	50	150		0		
Surr: o-Terphenyl	24.9		23.86		104	50	150		0		

Sample ID 1708009-002ADUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 8/2/2017	RunNo: 37768							
Client ID: BATCH	Batch ID: 17798	Analysis Date: 8/2/2017	SeqNo: 726304								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	ND	19.7						0		30	
Heavy Oil	ND	49.3						0		30	
Surr: 2-Fluorobiphenyl	20.3		19.73		103	50	150		0		
Surr: o-Terphenyl	20.7		19.73		105	50	150		0		

Work Order: 1707301
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Gasoline by NWTPH-Gx

Sample ID LCS-17817	SampType: LCS	Units: mg/Kg			Prep Date: 8/3/2017	RunNo: 37829					
Client ID: LCSS	Batch ID: 17817				Analysis Date: 8/3/2017	SeqNo: 727062					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	24.4	5.00	25.00	0	97.7	65	135				
Surr: Toluene-d8	1.28		1.250		102	65	135				
Surr: 4-Bromofluorobenzene	1.25		1.250		100	65	135				

Sample ID MB-17817	SampType: MBLK	Units: mg/Kg			Prep Date: 8/3/2017	RunNo: 37829					
Client ID: MBLKS	Batch ID: 17817				Analysis Date: 8/3/2017	SeqNo: 727063					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	ND	5.00									
Surr: Toluene-d8	1.33		1.250		106	65	135				
Surr: 4-Bromofluorobenzene	1.19		1.250		95.3	65	135				

Sample ID 1707301-002BDUP	SampType: DUP	Units: mg/Kg-dry			Prep Date: 8/3/2017	RunNo: 37829					
Client ID: ES-2	Batch ID: 17817				Analysis Date: 8/4/2017	SeqNo: 727053					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	ND	4.36						0		30	
Surr: Toluene-d8	1.17		1.091		107	65	135		0		
Surr: 4-Bromofluorobenzene	1.01		1.091		92.5	65	135		0		

Sample ID 1707301-004BMS	SampType: MS	Units: mg/Kg-dry			Prep Date: 8/3/2017	RunNo: 37829					
Client ID: ES-4	Batch ID: 17817				Analysis Date: 8/4/2017	SeqNo: 727056					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	28.0	5.44	27.19	0	103	65	135				
Surr: Toluene-d8	1.39		1.360		102	65	135				
Surr: 4-Bromofluorobenzene	1.39		1.360		103	65	135				

Work Order: 1707301
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Gasoline by NWTPH-Gx

Sample ID 1707301-004BMSD	SampType: MSD	Units: mg/Kg-dry		Prep Date: 8/3/2017	RunNo: 37829						
Client ID: ES-4	Batch ID: 17817			Analysis Date: 8/4/2017	SeqNo: 727057						
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Gasoline	26.0	5.44	27.19	0	95.5	65	135	27.98	7.48	30	
Surr: Toluene-d8	1.40		1.360		103	65	135		0		
Surr: 4-Bromofluorobenzene	1.37		1.360		101	65	135		0		

Work Order: 1707301
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Herbicides by EPA Method 8151A

Sample ID MB-17825	SampType: MBLK	Units: µg/Kg	Prep Date: 8/4/2017	RunNo: 37948							
Client ID: MBLKS	Batch ID: 17825		Analysis Date: 8/9/2017	SeqNo: 729321							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Dicamba	ND	35.0									
2,4-D	ND	30.0									
2,4-DP	ND	25.0									
2,4,5-TP (Silvex)	ND	20.0									
2,4,5-T	ND	50.0									
Dinoseb	ND	30.0									
Dalapon	ND	200									
2,4-DB	ND	25.0									
MCPP	ND	4,400									
MCPA	ND	2,800									
Picloram	ND	50.0									
Bentazon	ND	35.0									
Chloramben	ND	20.0									
Acifluorfen	ND	80.0									
3,5-Dichlorobenzoic acid	ND	40.0									
4-Nitrophenol	ND	30.0									
Dacthal (DCPA)	ND	30.0									
Surr: 2,4-Dichlorophenylacetic acid	716		1,000		71.6	20.1	168				

Sample ID LCS-17825	SampType: LCS	Units: µg/Kg	Prep Date: 8/4/2017	RunNo: 37948							
Client ID: LCSS	Batch ID: 17825		Analysis Date: 8/9/2017	SeqNo: 729322							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Dicamba	160	35.0	200.0	0	80.2	24.7	141				
2,4-D	179	30.0	200.0	0	89.6	22.4	130				
2,4-DP	166	25.0	200.0	0	83.2	26.4	130				
2,4,5-TP (Silvex)	180	20.0	200.0	0	90.0	21.2	138				
2,4,5-T	165	50.0	200.0	0	82.6	22.8	144				
Dinoseb	140	30.0	200.0	0	69.8	5	165				
Dalapon	930	200	1,000	0	93.0	18.4	162				



Work Order: 1707301
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Herbicides by EPA Method 8151A

Sample ID	LCS-17825	SampType:	LCS	Units:	µg/Kg	Prep Date:	8/4/2017	RunNo:	37948		
Client ID:	LCSS	Batch ID:	17825			Analysis Date:	8/9/2017	SeqNo:	729322		
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
2,4-DB	190	25.0	200.0	0	94.8	5	164				
MCPP	826	4,400	1,000	0	82.6	22.2	157				
MCPA	883	2,800	1,000	0	88.3	47.4	128				
Picloram	171	50.0	200.0	0	85.7	5	175				
Bentazon	122	35.0	200.0	0	61.0	7.59	162				
Chloramben	64.5	20.0	200.0	0	32.3	5	147				
Acifluorfen	196	80.0	200.0	0	97.9	5	163				
3,5-Dichlorobenzoic acid	160	40.0	200.0	0	79.9	18.7	139				
4-Nitrophenol	146	30.0	200.0	0	73.0	5	163				
Dacthal (DCPA)	120	30.0	200.0	0	60.2	5	164				
Surr: 2,4-Dichlorophenylacetic acid	786		1,000		78.6	20.1	168				

Sample ID	1707301-001ADUP	SampType:	DUP	Units:	µg/Kg-dry	Prep Date:	8/4/2017	RunNo:	37948		
Client ID:	ES-1	Batch ID:	17825			Analysis Date:	8/10/2017	SeqNo:	729336		
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Dicamba	ND	32.6						0		30	
2,4-D	ND	27.9						0		30	
2,4-DP	ND	23.3						0		30	
2,4,5-TP (Silvex)	ND	18.6						0		30	
2,4,5-T	ND	46.5						0		30	
Dinoseb	ND	27.9						0		30	
Dalapon	ND	186						0		30	
2,4-DB	ND	23.3						0		30	
MCPP	ND	4,090						0		30	
MCPA	ND	2,610						0		30	
Picloram	ND	46.5						0		30	
Bentazon	ND	32.6						0		30	
Chloramben	ND	18.6						0		30	
Acifluorfen	ND	74.5						0		30	

Work Order: 1707301
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Herbicides by EPA Method 8151A

Sample ID 1707301-001ADUP	SampType: DUP	Units: µg/Kg-dry	Prep Date: 8/4/2017	RunNo: 37948							
Client ID: ES-1	Batch ID: 17825		Analysis Date: 8/10/2017	SeqNo: 729336							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

3,5-Dichlorobenzoic acid	ND	37.2						0		30	
4-Nitrophenol	ND	27.9						0		30	
Dacthal (DCPA)	ND	27.9						0		30	
Surr: 2,4-Dichlorophenylacetic acid	451		930.7		48.4	20.1	168		0		

Sample ID 1707301-001AMS	SampType: MS	Units: µg/Kg-dry	Prep Date: 8/4/2017	RunNo: 37948							
Client ID: ES-1	Batch ID: 17825		Analysis Date: 8/10/2017	SeqNo: 729337							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Dicamba	154	35.7	204.3	0	75.6	31.9	118				
2,4-D	173	30.6	204.3	0	84.8	12.4	134				
2,4-DP	164	25.5	204.3	0	80.2	27.2	129				
2,4,5-TP (Silvex)	178	20.4	204.3	0	87.3	28.6	134				
2,4,5-T	153	51.1	204.3	0	74.7	13.1	147				
Dinoseb	208	30.6	204.3	0	102	10	179				
Dalapon	865	204	1,021	0	84.7	24.9	139				
2,4-DB	191	25.5	204.3	0	93.6	50.2	152				
MCPP	795	4,490	1,021	0	77.8	37.8	140				
MCPA	867	2,860	1,021	0	84.9	13.7	147				
Picloram	309	51.1	204.3	0	151	5	153				
Bentazon	153	35.7	204.3	0	75.1	15	140				
Chloramben	126	20.4	204.3	0	61.6	5	162				
Acifluorfen	251	81.7	204.3	0	123	15	140				
3,5-Dichlorobenzoic acid	157	40.9	204.3	0	77.0	10	164				
4-Nitrophenol	52.9	30.6	204.3	0	25.9	44.8	125				S
Dacthal (DCPA)	133	30.6	204.3	0	64.9	5	132				
Surr: 2,4-Dichlorophenylacetic acid	735		1,021		72.0	20.1	168				

NOTES:

S - Outlying spike recovery(ies) observed. A duplicate analysis was performed with similar results indicating a possible matrix effect.

Work Order: 1707301
 CLIENT: Shannon & Wilson
 Project: Yakima EWC

QC SUMMARY REPORT
Herbicides by EPA Method 8151A

Sample ID	1707301-001AMSD	SampType:	MSD	Units:	µg/Kg-dry	Prep Date:	8/4/2017	RunNo:	37948
Client ID:	ES-1	Batch ID:	17825	Analysis Date:	8/10/2017	SeqNo:	729338		

Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Dicamba	142	34.5	196.9	0	72.1	31.9	118	154.3	8.30	30	
2,4-D	161	29.5	196.9	0	81.6	12.4	134	173.1	7.42	30	
2,4-DP	146	24.6	196.9	0	73.9	27.2	129	163.8	11.8	30	
2,4,5-TP (Silvex)	159	19.7	196.9	0	81.0	28.6	134	178.3	11.1	30	
2,4,5-T	166	49.2	196.9	0	84.5	13.1	147	152.6	8.60	30	
Dinoseb	187	29.5	196.9	0	95.1	10	179	207.6	10.3	30	
Dalapon	875	197	984.5	0	88.9	24.9	139	864.6	1.18	30	
2,4-DB	175	24.6	196.9	0	88.9	50.2	152	191.3	8.80	30	
MCPP	789	4,330	984.5	0	80.1	37.8	140	0		30	
MCPA	867	2,760	984.5	0	88.0	13.7	147	0		30	
Picloram	270	49.2	196.9	0	137	5	153	308.9	13.5	30	
Bentazon	133	34.5	196.9	0	67.5	15	140	153.4	14.4	30	
Chloramben	81.5	19.7	196.9	0	41.4	5	162	125.8	42.7	30	R
Acifluorfen	200	78.8	196.9	0	102	15	140	251.4	22.8	30	
3,5-Dichlorobenzoic acid	146	39.4	196.9	0	74.0	10	164	157.3	7.61	30	
4-Nitrophenol	55.9	29.5	196.9	0	28.4	44.8	125	52.91	5.56	30	S
Dacthal (DCPA)	114	29.5	196.9	0	58.1	5	132	132.5	14.7	30	
Surr: 2,4-Dichlorophenylacetic acid	691		984.5		70.2	20.1	168		0		

NOTES:

S - Outlying spike recovery(ies) observed. A duplicate analysis was performed with similar results indicating a possible matrix effect.
 R - High RPD observed, spike recovery is within range.

Work Order: 1707301
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Mercury by EPA Method 7471

Sample ID MB-17818	SampType: MBLK	Units: mg/Kg			Prep Date: 8/3/2017	RunNo: 37806					
Client ID: MBLKS	Batch ID: 17818				Analysis Date: 8/3/2017	SeqNo: 726795					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury ND 0.250

Sample ID LCS-17818	SampType: LCS	Units: mg/Kg			Prep Date: 8/3/2017	RunNo: 37806					
Client ID: LCSS	Batch ID: 17818				Analysis Date: 8/3/2017	SeqNo: 726796					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.500 0.245 0.4902 0 102 80 120

Sample ID 1707301-001ADUP	SampType: DUP	Units: mg/Kg-dry			Prep Date: 8/3/2017	RunNo: 37806					
Client ID: ES-1	Batch ID: 17818				Analysis Date: 8/3/2017	SeqNo: 726798					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury ND 0.255 0 20

Sample ID 1707301-001AMS	SampType: MS	Units: mg/Kg-dry			Prep Date: 8/3/2017	RunNo: 37806					
Client ID: ES-1	Batch ID: 17818				Analysis Date: 8/3/2017	SeqNo: 726799					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.549 0.260 0.5193 0.02025 102 70 130

Sample ID 1707301-001AMSD	SampType: MSD	Units: mg/Kg-dry			Prep Date: 8/3/2017	RunNo: 37806					
Client ID: ES-1	Batch ID: 17818				Analysis Date: 8/3/2017	SeqNo: 726801					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.521 0.245 0.4899 0.02025 102 70 130 0.5494 5.26 20

Work Order: 1707301
 CLIENT: Shannon & Wilson
 Project: Yakima EWC

QC SUMMARY REPORT
Organochlorine Pesticides by EPA Method 8081

Sample ID TOX CCV A 17824	SampType: CCV	Units: mg/L	Prep Date: 8/7/2017	RunNo: 37836							
Client ID: CCV	Batch ID: 17824		Analysis Date: 8/7/2017	SeqNo: 727576							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Toxaphene	930	0.100	1,000	0	93.0	80	120				
-----------	-----	-------	-------	---	------	----	-----	--	--	--	--

Sample ID MB-17824	SampType: MBLK	Units: mg/Kg	Prep Date: 8/4/2017	RunNo: 37836							
Client ID: MBLKS	Batch ID: 17824		Analysis Date: 8/7/2017	SeqNo: 727577							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Toxaphene	ND	0.100									
Alpha BHC	ND	0.0100									
Beta BHC	ND	0.0100									
Gamma BHC (Lindane)	ND	0.0100									
Delta BHC	ND	0.0100									
Heptachlor	ND	0.0100									
Aldrin	ND	0.0100									
Heptachlor epoxide	ND	0.0100									
gamma-Chlordane	ND	0.0100									
Endosulfan I	ND	0.0100									
alpha-Chlordane	ND	0.0100									
Dieldrin	ND	0.0100									
4,4'-DDE	ND	0.0100									
Endrin	ND	0.0100									
Endosulfan II	ND	0.0100									
4,4'-DDD	ND	0.0100									
Endrin aldehyde	ND	0.0100									
Endosulfan sulfate	ND	0.0100									
4,4'-DDT	ND	0.0100									
Endrin ketone	ND	0.0100									
Methoxychlor	ND	0.0100									
Surr: Decachlorobiphenyl	0.0480		0.05000		95.9	17.8	157				
Surr: Tetrachloro-m-xylene	0.0469		0.05000		93.9	11	150				

Work Order: 1707301
 CLIENT: Shannon & Wilson
 Project: Yakima EWC

QC SUMMARY REPORT
Organochlorine Pesticides by EPA Method 8081

Sample ID	LCS-17824	SampType:	LCS	Units:	mg/Kg	Prep Date:	8/4/2017	RunNo:	37836		
Client ID:	LCSS	Batch ID:	17824	Analysis Date:	8/7/2017	SeqNo:	727578				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Alpha BHC	0.195	0.0100	0.2000	0	97.7	54.2	139				
Beta BHC	0.183	0.0100	0.2000	0	91.7	56.5	142				
Gamma BHC (Lindane)	0.195	0.0100	0.2000	0	97.5	55.5	142				
Delta BHC	0.193	0.0100	0.2000	0	96.6	47.4	157				
Heptachlor	0.209	0.0100	0.2000	0	105	50.9	153				
Aldrin	0.174	0.0100	0.2000	0	87.0	43.7	147				
Heptachlor epoxide	0.180	0.0100	0.2000	0	90.0	56.2	137				
gamma-Chlordane	0.172	0.0100	0.2000	0	86.1	58.5	136				
Endosulfan I	0.177	0.0100	0.2000	0	88.4	60	132				
alpha-Chlordane	0.173	0.0100	0.2000	0	86.6	46.1	140				
Dieldrin	0.177	0.0100	0.2000	0	88.6	61.2	133				
4,4'-DDE	0.187	0.0100	0.2000	0	93.4	55.4	142				
Endrin	0.181	0.0100	0.2000	0	90.4	56.5	143				
Endosulfan II	0.175	0.0100	0.2000	0	87.7	62	143				
4,4'-DDD	0.177	0.0100	0.2000	0	88.5	53.3	145				
Endrin aldehyde	0.168	0.0100	0.2000	0	83.8	39.5	153				
Endosulfan sulfate	0.181	0.0100	0.2000	0	90.3	53.8	148				
4,4'-DDT	0.208	0.0100	0.2000	0	104	48.2	152				
Endrin ketone	0.189	0.0100	0.2000	0	94.5	28.5	162				
Methoxychlor	0.222	0.0100	0.2000	0	111	34.6	159				
Surr: Decachlorobiphenyl	0.0516		0.05000		103	17.8	157				
Surr: Tetrachloro-m-xylene	0.0524		0.05000		105	11	150				

Sample ID	1707301-001ADUP	SampType:	DUP	Units:	mg/Kg-dry	Prep Date:	8/4/2017	RunNo:	37836		
Client ID:	ES-1	Batch ID:	17824	Analysis Date:	8/7/2017	SeqNo:	727580				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Toxaphene	ND	0.101						0		30	
Alpha BHC	ND	0.0101						0		30	
Beta BHC	ND	0.0101						0		30	

Work Order: 1707301
 CLIENT: Shannon & Wilson
 Project: Yakima EWC

QC SUMMARY REPORT
Organochlorine Pesticides by EPA Method 8081

Sample ID	1707301-001ADUP	SampType:	DUP	Units:	mg/Kg-dry	Prep Date:	8/4/2017	RunNo:	37836		
Client ID:	ES-1	Batch ID:	17824	Analysis Date:	8/7/2017	SeqNo:	727580				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Gamma BHC (Lindane)	ND	0.0101						0		30	
Delta BHC	ND	0.0101						0		30	
Heptachlor	ND	0.0101						0		30	
Aldrin	ND	0.0101						0		30	
Heptachlor epoxide	ND	0.0101						0		30	
gamma-Chlordane	ND	0.0101						0		30	
Endosulfan I	ND	0.0101						0		30	
alpha-Chlordane	ND	0.0101						0		30	
Dieldrin	ND	0.0101						0		30	
4,4'-DDE	ND	0.0101						0		30	
Endrin	ND	0.0101						0		30	
Endosulfan II	ND	0.0101						0		30	
4,4'-DDD	ND	0.0101						0		30	
Endrin aldehyde	ND	0.0101						0		30	
Endosulfan sulfate	ND	0.0101						0		30	
4,4'-DDT	ND	0.0101						0		30	
Endrin ketone	ND	0.0101						0		30	
Methoxychlor	ND	0.0101						0		30	
Surr: Decachlorobiphenyl	0.0471		0.05057		93.2	17.8	157		0		
Surr: Tetrachloro-m-xylene	0.0469		0.05057		92.8	11	150		0		

Sample ID	1707301-001AMS	SampType:	MS	Units:	mg/Kg-dry	Prep Date:	8/4/2017	RunNo:	37836		
Client ID:	ES-1	Batch ID:	17824	Analysis Date:	8/7/2017	SeqNo:	727581				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Alpha BHC	0.135	0.00929	0.1858	0	72.5	49.1	158				
Beta BHC	0.129	0.00929	0.1858	0	69.4	30.1	161				
Gamma BHC (Lindane)	0.136	0.00929	0.1858	0	73.2	40.5	158				
Delta BHC	0.136	0.00929	0.1858	0	73.0	31.5	153				
Heptachlor	0.147	0.00929	0.1858	0	79.0	37.9	156				

Work Order: 1707301
 CLIENT: Shannon & Wilson
 Project: Yakima EWC

QC SUMMARY REPORT
Organochlorine Pesticides by EPA Method 8081

Sample ID	1707301-001AMS	SampType:	MS	Units:	mg/Kg-dry	Prep Date:	8/4/2017	RunNo:	37836		
Client ID:	ES-1	Batch ID:	17824	Analysis Date:	8/7/2017	SeqNo:	727581				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Aldrin	0.121	0.00929	0.1858	0	64.9	41.9	130				
Heptachlor epoxide	0.128	0.00929	0.1858	0	68.9	41	161				
gamma-Chlordane	0.124	0.00929	0.1858	0	66.5	40.9	132				
Endosulfan I	0.126	0.00929	0.1858	0	68.0	44.7	162				
alpha-Chlordane	0.125	0.00929	0.1858	0	67.2	41.4	132				
Dieldrin	0.128	0.00929	0.1858	0	69.0	43.9	155				
4,4'-DDE	0.136	0.00929	0.1858	0	73.1	34	166				
Endrin	0.134	0.00929	0.1858	0	72.1	50.5	166				
Endosulfan II	0.134	0.00929	0.1858	0	72.3	37.9	154				
4,4'-DDD	0.135	0.00929	0.1858	0	72.4	38.9	144				
Endrin aldehyde	0.125	0.00929	0.1858	0	67.5	38.3	156				
Endosulfan sulfate	0.135	0.00929	0.1858	0	72.7	25.2	144				
4,4'-DDT	0.163	0.00929	0.1858	0	87.7	38.4	160				
Endrin ketone	0.148	0.00929	0.1858	0	79.8	40.2	119				
Methoxychlor	0.185	0.00929	0.1858	0	99.5	43.4	178				
Surr: Decachlorobiphenyl	0.0441		0.04645		94.9	17.8	157				
Surr: Tetrachloro-m-xylene	0.0372		0.04645		80.1	11	150				

Sample ID	1707301-001AMSD	SampType:	MSD	Units:	mg/Kg-dry	Prep Date:	8/4/2017	RunNo:	37836		
Client ID:	ES-1	Batch ID:	17824	Analysis Date:	8/7/2017	SeqNo:	727582				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Alpha BHC	0.140	0.00954	0.1907	0	73.3	49.1	158	0.1347	3.73	30	
Beta BHC	0.130	0.00954	0.1907	0	68.1	30.1	161	0.1289	0.700	30	
Gamma BHC (Lindane)	0.140	0.00954	0.1907	0	73.4	40.5	158	0.1360	2.85	30	
Delta BHC	0.135	0.00954	0.1907	0	70.5	31.5	153	0.1357	0.890	30	
Heptachlor	0.153	0.00954	0.1907	0	80.1	37.9	156	0.1468	3.97	30	
Aldrin	0.124	0.00954	0.1907	0	65.2	41.9	130	0.1206	3.10	30	
Heptachlor epoxide	0.130	0.00954	0.1907	0	68.3	41	161	0.1280	1.81	30	
gamma-Chlordane	0.125	0.00954	0.1907	0	65.4	40.9	132	0.1235	0.975	30	

Work Order: 1707301
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Organochlorine Pesticides by EPA Method 8081

Sample ID 1707301-001AMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 8/4/2017	RunNo: 37836
Client ID: ES-1	Batch ID: 17824		Analysis Date: 8/7/2017	SeqNo: 727582

Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Endosulfan I	0.127	0.00954	0.1907	0	66.4	44.7	162	0.1264	0.211	30	
alpha-Chlordane	0.126	0.00954	0.1907	0	66.0	41.4	132	0.1248	0.909	30	
Dieldrin	0.127	0.00954	0.1907	0	66.6	43.9	155	0.1282	0.926	30	
4,4'-DDE	0.135	0.00954	0.1907	0	70.6	34	166	0.1358	0.768	30	
Endrin	0.131	0.00954	0.1907	0	68.5	50.5	166	0.1341	2.50	30	
Endosulfan II	0.126	0.00954	0.1907	0	65.9	37.9	154	0.1344	6.61	30	
4,4'-DDD	0.128	0.00954	0.1907	0	67.2	38.9	144	0.1345	4.88	30	
Endrin aldehyde	0.109	0.00954	0.1907	0	57.1	38.3	156	0.1254	14.1	30	
Endosulfan sulfate	0.122	0.00954	0.1907	0	63.8	25.2	144	0.1351	10.5	30	
4,4'-DDT	0.154	0.00954	0.1907	0	81.0	38.4	160	0.1630	5.34	30	
Endrin ketone	0.133	0.00954	0.1907	0	69.7	40.2	119	0.1483	11.0	30	
Methoxychlor	0.168	0.00954	0.1907	0	88.0	43.4	178	0.1849	9.64	30	
Surr: Decachlorobiphenyl	0.0354		0.04769		74.3	17.8	157		0		
Surr: Tetrachloro-m-xylene	0.0372		0.04769		78.1	11	150		0		

Work Order: 1707301
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Sample ID MB-17800	SampType: MBLK	Units: µg/Kg	Prep Date: 8/2/2017	RunNo: 37792							
Client ID: MBLKS	Batch ID: 17800		Analysis Date: 8/2/2017	SeqNo: 726348							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	ND	40.0									
2-Methylnaphthalene	ND	40.0									
1-Methylnaphthalene	ND	40.0									
Acenaphthylene	ND	40.0									
Acenaphthene	ND	40.0									
Fluorene	ND	40.0									
Phenanthrene	ND	40.0									
Anthracene	ND	40.0									
Fluoranthene	ND	40.0									
Pyrene	ND	40.0									
Benz(a)anthracene	ND	40.0									
Chrysene	ND	40.0									
Benzo(b)fluoranthene	ND	40.0									
Benzo(j,k)fluoranthene	ND	40.0									
Benzo(a)pyrene	ND	40.0									
Indeno(1,2,3-cd)pyrene	ND	40.0									
Dibenz(a,h)anthracene	ND	40.0									
Benzo(g,h,i)perylene	ND	40.0									
Surr: 2-Fluorobiphenyl	494		500.0		98.7	24.5	139				
Surr: Terphenyl-d14 (surr)	666		500.0		133	46.2	179				

Sample ID LCS-17800	SampType: LCS	Units: µg/Kg	Prep Date: 8/2/2017	RunNo: 37792							
Client ID: LCSS	Batch ID: 17800		Analysis Date: 8/2/2017	SeqNo: 726349							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	599	40.0	1,000	0	59.9	46.4	125				
2-Methylnaphthalene	728	40.0	1,000	0	72.8	45.1	135				
1-Methylnaphthalene	617	40.0	1,000	0	61.7	46.2	133				
Acenaphthylene	656	40.0	1,000	0	65.6	32.8	136				
Acenaphthene	654	40.0	1,000	0	65.4	38.7	129				

Work Order: 1707301
 CLIENT: Shannon & Wilson
 Project: Yakima EWC

QC SUMMARY REPORT
Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Sample ID	LCS-17800	SampType:	LCS	Units:	µg/Kg	Prep Date:	8/2/2017	RunNo:	37792		
Client ID:	LCSS	Batch ID:	17800			Analysis Date:	8/2/2017	SeqNo:	726349		
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Fluorene	658	40.0	1,000	0	65.8	41.4	144				
Phenanthrene	621	40.0	1,000	0	62.1	43.9	133				
Anthracene	768	40.0	1,000	0	76.8	44.2	136				
Fluoranthene	689	40.0	1,000	0	68.9	45.9	137				
Pyrene	677	40.0	1,000	0	67.7	46.2	137				
Benz(a)anthracene	720	40.0	1,000	0	72.0	41.2	141				
Chrysene	667	40.0	1,000	0	66.7	46.9	138				
Benzo(b)fluoranthene	688	40.0	1,000	0	68.8	41	155				
Benzo(j,k)fluoranthene	670	40.0	1,000	0	67.0	41.8	153				
Benzo(a)pyrene	684	40.0	1,000	0	68.4	30.2	171				
Indeno(1,2,3-cd)pyrene	678	40.0	1,000	0	67.8	31.3	159				
Dibenz(a,h)anthracene	697	40.0	1,000	0	69.7	28	158				
Benzo(g,h,i)perylene	681	40.0	1,000	0	68.1	32.4	144				
Surr: 2-Fluorobiphenyl	483		500.0		96.7	24.5	139				
Surr: Terphenyl-d14 (surr)	599		500.0		120	46.2	179				

Sample ID	1707301-002ADUP	SampType:	DUP	Units:	µg/Kg-dry	Prep Date:	8/2/2017	RunNo:	37792		
Client ID:	ES-2	Batch ID:	17800			Analysis Date:	8/2/2017	SeqNo:	726353		
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	ND	39.1						0		30	
2-Methylnaphthalene	ND	39.1						0		30	
1-Methylnaphthalene	ND	39.1						0		30	
Acenaphthylene	ND	39.1						0		30	
Acenaphthene	ND	39.1						0		30	
Fluorene	ND	39.1						0		30	
Phenanthrene	ND	39.1						0		30	
Anthracene	ND	39.1						0		30	
Fluoranthene	ND	39.1						0		30	
Pyrene	ND	39.1						0		30	

Work Order: 1707301
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Sample ID	1707301-002ADUP	SampType:	DUP	Units:	µg/Kg-dry	Prep Date:	8/2/2017	RunNo:	37792		
Client ID:	ES-2	Batch ID:	17800			Analysis Date:	8/2/2017	SeqNo:	726353		
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benz(a)anthracene	ND	39.1						0		30	
Chrysene	ND	39.1						0		30	
Benzo(b)fluoranthene	ND	39.1						0		30	
Benzo(j,k)fluoranthene	ND	39.1						0		30	
Benzo(a)pyrene	ND	39.1						0		30	
Indeno(1,2,3-cd)pyrene	ND	39.1						0		30	
Dibenz(a,h)anthracene	ND	39.1						0		30	
Benzo(g,h,i)perylene	ND	39.1						0		30	
Surr: 2-Fluorobiphenyl	424		488.6		86.7	24.5	139		0		
Surr: Terphenyl-d14 (surr)	571		488.6		117	46.2	179		0		

Sample ID	1707301-002AMS	SampType:	MS	Units:	µg/Kg-dry	Prep Date:	8/2/2017	RunNo:	37792		
Client ID:	ES-2	Batch ID:	17800			Analysis Date:	8/2/2017	SeqNo:	726354		
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	558	38.4	961.0	0	58.1	42.9	138				
2-Methylnaphthalene	688	38.4	961.0	0	71.6	42.8	151				
1-Methylnaphthalene	584	38.4	961.0	0	60.8	41.6	148				
Acenaphthylene	625	38.4	961.0	0	65.0	32.6	160				
Acenaphthene	630	38.4	961.0	0	65.5	46.3	142				
Fluorene	647	38.4	961.0	0	67.3	43.4	153				
Phenanthrene	630	38.4	961.0	0	65.5	45.5	140				
Anthracene	764	38.4	961.0	0	79.5	32.6	160				
Fluoranthene	676	38.4	961.0	0	70.3	44.6	161				
Pyrene	668	38.4	961.0	0	69.5	48.3	158				
Benz(a)anthracene	706	38.4	961.0	0	73.5	34.9	139				
Chrysene	654	38.4	961.0	0	68.0	45.2	146				
Benzo(b)fluoranthene	625	38.4	961.0	0	65.0	42.2	168				
Benzo(j,k)fluoranthene	685	38.4	961.0	0	71.3	34.8	147				
Benzo(a)pyrene	650	38.4	961.0	0	67.6	34.4	179				

Work Order: 1707301
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Sample ID 1707301-002AMS	SampType: MS	Units: µg/Kg-dry				Prep Date: 8/2/2017	RunNo: 37792				
Client ID: ES-2	Batch ID: 17800					Analysis Date: 8/2/2017	SeqNo: 726354				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Indeno(1,2,3-cd)pyrene	649	38.4	961.0	0	67.6	5	113				
Dibenz(a,h)anthracene	662	38.4	961.0	0	68.9	17.3	156				
Benzo(g,h,i)perylene	652	38.4	961.0	0	67.8	24.9	119				
Surr: 2-Fluorobiphenyl	406		480.5		84.5	24.5	139				
Surr: Terphenyl-d14 (surr)	557		480.5		116	46.2	179				

Sample ID 1707301-002AMSD	SampType: MSD	Units: µg/Kg-dry				Prep Date: 8/2/2017	RunNo: 37792				
Client ID: ES-2	Batch ID: 17800					Analysis Date: 8/2/2017	SeqNo: 726355				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	623	39.4	985.6	0	63.2	42.9	138	558.0	11.0	30	
2-Methylnaphthalene	758	39.4	985.6	0	76.9	42.8	151	687.6	9.68	30	
1-Methylnaphthalene	637	39.4	985.6	0	64.6	41.6	148	583.9	8.73	30	
Acenaphthylene	679	39.4	985.6	0	68.9	32.6	160	624.9	8.27	30	
Acenaphthene	679	39.4	985.6	0	68.9	46.3	142	629.7	7.60	30	
Fluorene	705	39.4	985.6	0	71.5	43.4	153	646.5	8.61	30	
Phenanthrene	648	39.4	985.6	0	65.7	45.5	140	629.6	2.81	30	
Anthracene	792	39.4	985.6	0	80.4	32.6	160	764.0	3.65	30	
Fluoranthene	712	39.4	985.6	0	72.2	44.6	161	675.6	5.25	30	
Pyrene	692	39.4	985.6	0	70.2	48.3	158	667.6	3.53	30	
Benz(a)anthracene	751	39.4	985.6	0	76.2	34.9	139	706.4	6.14	30	
Chrysene	679	39.4	985.6	0	68.9	45.2	146	653.6	3.87	30	
Benzo(b)fluoranthene	666	39.4	985.6	0	67.6	42.2	168	624.9	6.37	30	
Benzo(j,k)fluoranthene	728	39.4	985.6	0	73.9	34.8	147	685.4	6.08	30	
Benzo(a)pyrene	697	39.4	985.6	0	70.7	34.4	179	649.5	7.08	30	
Indeno(1,2,3-cd)pyrene	685	39.4	985.6	0	69.5	5	113	649.2	5.32	30	
Dibenz(a,h)anthracene	711	39.4	985.6	0	72.1	17.3	156	661.9	7.10	30	
Benzo(g,h,i)perylene	689	39.4	985.6	0	69.9	24.9	119	651.5	5.62	30	
Surr: 2-Fluorobiphenyl	476		492.8		96.5	24.5	139		0		
Surr: Terphenyl-d14 (surr)	583		492.8		118	46.2	179		0		



Work Order: 1707301
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Sample ID	1707301-002AMSD	SampType:	MSD	Units:	µg/Kg-dry	Prep Date:	8/2/2017	RunNo:	37792		
Client ID:	ES-2	Batch ID:	17800			Analysis Date:	8/2/2017	SeqNo:	726355		
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Work Order: 1707301
 CLIENT: Shannon & Wilson
 Project: Yakima EWC

QC SUMMARY REPORT
Polychlorinated Biphenyls (PCB) by EPA 8082

Sample ID MB-17799	SampType: MBLK	Units: mg/Kg	Prep Date: 8/2/2017	RunNo: 37776							
Client ID: MBLKS	Batch ID: 17799		Analysis Date: 8/2/2017	SeqNo: 726074							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Aroclor 1016	ND	0.100									
Aroclor 1221	ND	0.100									
Aroclor 1232	ND	0.100									
Aroclor 1242	ND	0.100									
Aroclor 1248	ND	0.100									
Aroclor 1254	ND	0.100									
Aroclor 1260	ND	0.100									
Aroclor 1262	ND	0.100									
Aroclor 1268	ND	0.100									
Total PCBs	ND	0.100									
Surr: Decachlorobiphenyl	66.2		50.00		132	30.8	168				
Surr: Tetrachloro-m-xylene	60.0		50.00		120	30.1	143				

Sample ID LCS1-17799	SampType: LCS	Units: mg/Kg	Prep Date: 8/2/2017	RunNo: 37776							
Client ID: LCSS	Batch ID: 17799		Analysis Date: 8/2/2017	SeqNo: 726075							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Aroclor 1016	0.804	0.100	1.000	0	80.4	38.5	149				
Aroclor 1260	0.802	0.100	1.000	0	80.2	35.4	154				
Surr: Decachlorobiphenyl	49.4		50.00		98.8	30.8	168				
Surr: Tetrachloro-m-xylene	50.3		50.00		101	30.1	143				

Sample ID LCS2-17799	SampType: LCS	Units: mg/Kg	Prep Date: 8/2/2017	RunNo: 37776							
Client ID: LCSS	Batch ID: 17799		Analysis Date: 8/2/2017	SeqNo: 726076							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Aroclor 1254	0.898	0.100	1.000	0	89.8	32.8	151				
Surr: Decachlorobiphenyl	49.0		50.00		97.9	30.8	168				
Surr: Tetrachloro-m-xylene	50.4		50.00		101	30.1	143				

Work Order: 1707301
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Polychlorinated Biphenyls (PCB) by EPA 8082

Sample ID 1707219-010ADUP	SampType: DUP	Units: mg/Kg-dry				Prep Date: 8/2/2017	RunNo: 37776				
Client ID: BATCH	Batch ID: 17799					Analysis Date: 8/2/2017	SeqNo: 726078				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Aroclor 1016	ND	0.195						0		30	
Aroclor 1221	ND	0.195						0		30	
Aroclor 1232	ND	0.195						0		30	
Aroclor 1242	ND	0.195						0		30	
Aroclor 1248	ND	0.195						0		30	
Aroclor 1254	ND	0.195						0		30	
Aroclor 1260	ND	0.195						0		30	
Aroclor 1262	ND	0.195						0		30	
Aroclor 1268	ND	0.195						0		30	
Total PCBs	ND	0.195						0		30	
Surr: Decachlorobiphenyl	72.0		97.70		73.7	30.8	168		0		
Surr: Tetrachloro-m-xylene	70.7		97.70		72.4	30.1	143		0		

Sample ID 1707219-010AMS	SampType: MS	Units: mg/Kg-dry				Prep Date: 8/2/2017	RunNo: 37776				
Client ID: BATCH	Batch ID: 17799					Analysis Date: 8/2/2017	SeqNo: 726079				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Aroclor 1016	1.61	0.187	1.865	0	86.4	27.1	166				
Aroclor 1260	1.60	0.187	1.865	0.02832	84.1	20.6	168				
Surr: Decachlorobiphenyl	62.7		93.26		67.2	30.8	168				
Surr: Tetrachloro-m-xylene	57.9		93.26		62.1	30.1	143				

Sample ID 1707219-010AMSD	SampType: MSD	Units: mg/Kg-dry				Prep Date: 8/2/2017	RunNo: 37776				
Client ID: BATCH	Batch ID: 17799					Analysis Date: 8/2/2017	SeqNo: 726080				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Aroclor 1016	1.64	0.187	1.871	0	87.6	27.1	166	1.612	1.66	30	
Aroclor 1260	1.63	0.187	1.871	0.02832	85.7	20.6	168	1.597	2.14	30	
Surr: Decachlorobiphenyl	60.4		93.53		64.6	30.8	168		0		
Surr: Tetrachloro-m-xylene	58.5		93.53		62.5	30.1	143		0		



Work Order: 1707301
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Polychlorinated Biphenyls (PCB) by EPA 8082

Sample ID	1707219-010AMSD	SampType:	MSD	Units:	mg/Kg-dry	Prep Date:	8/2/2017	RunNo:	37776		
Client ID:	BATCH	Batch ID:	17799	Analysis Date:	8/2/2017	SeqNo:	726080				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual



Work Order: 1707301
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Sample Moisture (Percent Moisture)

Sample ID 1707220-011ADUP	SampType: DUP	Units: wt%			Prep Date: 8/2/2017	RunNo: 37765					
Client ID: BATCH	Batch ID: R37765				Analysis Date: 8/2/2017	SeqNo: 725880					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Percent Moisture	19.8	0.500						20.12	1.55	20	

Sample ID 1707310-018ADUP	SampType: DUP	Units: wt%			Prep Date: 8/2/2017	RunNo: 37765					
Client ID: BATCH	Batch ID: R37765				Analysis Date: 8/2/2017	SeqNo: 725898					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Percent Moisture	4.55	0.500						5.649	21.7	20	R

Work Order: 1707301
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Total Metals by EPA Method 6020

Sample ID MB-17812	SampType: MBLK	Units: mg/Kg	Prep Date: 8/3/2017	RunNo: 37801							
Client ID: MBLKS	Batch ID: 17812	Analysis Date: 8/3/2017	SeqNo: 726525								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Silver ND 0.0752

Sample ID LCS-17812	SampType: LCS	Units: mg/Kg	Prep Date: 8/3/2017	RunNo: 37801							
Client ID: LCSS	Batch ID: 17812	Analysis Date: 8/3/2017	SeqNo: 726526								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Silver 8.64 0.0752 9.398 0 91.9 80 120

Sample ID 1708037-002BDUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 8/3/2017	RunNo: 37801							
Client ID: BATCH	Batch ID: 17812	Analysis Date: 8/3/2017	SeqNo: 726530								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Silver ND 0.144 0 20

Sample ID 1708037-002BMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 8/3/2017	RunNo: 37801							
Client ID: BATCH	Batch ID: 17812	Analysis Date: 8/3/2017	SeqNo: 726532								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Silver 13.2 0.144 18.06 0.1420 72.6 75 125 S

NOTES:

S - Outlying spike recovery(ies) observed. A duplicate analysis was performed and recovered within range.

Sample ID 1708037-002BMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 8/3/2017	RunNo: 37801							
Client ID: BATCH	Batch ID: 17812	Analysis Date: 8/3/2017	SeqNo: 726533								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Silver 13.8 0.144 18.06 0.1420 75.6 75 125 13.25 4.01 20



Date: 8/14/2017

Work Order: 1707301
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Total Metals by EPA Method 6020

Sample ID MB-17796	SampType: MBLK	Units: mg/Kg	Prep Date: 8/2/2017	RunNo: 37771							
Client ID: MBLKS	Batch ID: 17796		Analysis Date: 8/2/2017	SeqNo: 726020							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	ND	0.0769									
Barium	ND	0.385									
Cadmium	ND	0.154									
Chromium	ND	0.0769									
Copper	ND	0.154									
Lead	ND	0.154									
Nickel	ND	0.0769									
Selenium	ND	0.385									
Zinc	ND	0.308									

Sample ID LCS-17796	SampType: LCS	Units: mg/Kg	Prep Date: 8/2/2017	RunNo: 37771							
Client ID: LCSS	Batch ID: 17796		Analysis Date: 8/2/2017	SeqNo: 726021							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	37.0	0.0725	36.23	0	102	80	120				
Barium	35.3	0.362	36.23	0	97.4	80	120				
Cadmium	1.84	0.145	1.812	0	102	80	120				
Chromium	37.7	0.0725	36.23	0	104	80	120				
Copper	37.7	0.145	36.23	0	104	80	120				
Lead	18.2	0.145	18.12	0	100	80	120				
Nickel	38.6	0.0725	36.23	0	107	80	120				
Selenium	3.52	0.362	3.623	0	97.0	80	120				
Zinc	37.0	0.290	36.23	0	102	80	120				

Sample ID 1708015-001BDUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 8/2/2017	RunNo: 37771							
Client ID: BATCH	Batch ID: 17796		Analysis Date: 8/2/2017	SeqNo: 726023							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	7.69	0.101						8.091	5.13	20	
Barium	152	0.503						166.0	8.76	20	



Date: 8/14/2017

Work Order: 1707301
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Total Metals by EPA Method 6020

Sample ID 1708015-001BDUP	SampType: DUP	Units: mg/Kg-dry				Prep Date: 8/2/2017	RunNo: 37771				
Client ID: BATCH	Batch ID: 17796					Analysis Date: 8/2/2017	SeqNo: 726023				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Cadmium	0.229	0.201						0.2297	0.132	20	
Chromium	81.8	0.101						90.69	10.3	20	
Copper	58.6	0.201						58.79	0.339	20	
Lead	15.0	0.201						12.44	18.4	20	
Nickel	92.4	0.101						98.89	6.74	20	
Selenium	1.93	0.503						2.207	13.6	20	
Zinc	107	0.403						105.2	1.66	20	

Sample ID 1708015-001BMS	SampType: MS	Units: mg/Kg-dry				Prep Date: 8/2/2017	RunNo: 37771				
Client ID: BATCH	Batch ID: 17796					Analysis Date: 8/2/2017	SeqNo: 726025				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Arsenic	55.3	0.0999	49.96	8.091	94.4	75	125				
Barium	222	0.500	49.96	166.0	113	75	125				
Cadmium	2.65	0.200	2.498	0.2297	96.9	75	125				
Chromium	144	0.0999	49.96	90.69	107	75	125				
Copper	104	0.200	49.96	58.79	91.4	75	125				
Lead	32.9	0.200	24.98	12.44	81.8	75	125				
Nickel	151	0.0999	49.96	98.89	104	75	125				
Selenium	6.64	0.500	4.996	2.207	88.7	75	125				
Zinc	156	0.400	49.96	105.2	101	75	125				

Sample ID 1708015-001BMSD	SampType: MSD	Units: mg/Kg-dry				Prep Date: 8/2/2017	RunNo: 37771				
Client ID: BATCH	Batch ID: 17796					Analysis Date: 8/2/2017	SeqNo: 726026				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Arsenic	53.6	0.0999	49.96	8.091	91.1	75	125	55.27	3.05	20	
Barium	215	0.500	49.96	166.0	97.6	75	125	222.3	3.44	20	
Cadmium	2.60	0.200	2.498	0.2297	94.8	75	125	2.650	1.98	20	
Chromium	141	0.0999	49.96	90.69	101	75	125	144.1	2.01	20	

Work Order: 1707301
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Total Metals by EPA Method 6020

Sample ID	1708015-001BMSD	SampType:	MSD	Units:	mg/Kg-dry	Prep Date:	8/2/2017	RunNo:	37771		
Client ID:	BATCH	Batch ID:	17796			Analysis Date:	8/2/2017	SeqNo:	726026		
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Copper	104	0.200	49.96	58.79	90.7	75	125	104.5	0.317	20	
Lead	31.7	0.200	24.98	12.44	77.2	75	125	32.88	3.54	20	
Nickel	143	0.0999	49.96	98.89	89.1	75	125	151.0	5.15	20	
Selenium	6.52	0.500	4.996	2.207	86.4	75	125	6.638	1.72	20	
Zinc	147	0.400	49.96	105.2	83.6	75	125	155.5	5.66	20	



Date: 8/14/2017

Work Order: 1707301
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260C

Sample ID LCS-17817	SampType: LCS	Units: mg/Kg	Prep Date: 8/3/2017	RunNo: 37828
Client ID: LCSS	Batch ID: 17817		Analysis Date: 8/3/2017	SeqNo: 727044

Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Dichlorodifluoromethane (CFC-12)	1.44	0.0200	1.000	0	144	14.3	167				
Chloromethane	1.08	0.0500	1.000	0	108	46	144				
Vinyl chloride	1.17	0.0250	1.000	0	117	43.4	151				
Bromomethane	1.25	0.0500	1.000	0	125	40.9	157				
Trichlorofluoromethane (CFC-11)	1.22	0.0200	1.000	0	122	36.9	156				
Chloroethane	1.13	0.0500	1.000	0	113	33.1	147				
1,1-Dichloroethene	1.14	0.0200	1.000	0	114	49.7	142				
Methylene chloride	1.05	0.0200	1.000	0	105	46.3	140				
trans-1,2-Dichloroethene	1.08	0.0200	1.000	0	108	68	130				
Methyl tert-butyl ether (MTBE)	0.803	0.0500	1.000	0	80.3	66.3	145				
1,1-Dichloroethane	1.05	0.0200	1.000	0	105	61.9	137				
2,2-Dichloropropane	0.805	0.100	1.000	0	80.5	35.5	186				
cis-1,2-Dichloroethene	1.06	0.0200	1.000	0	106	71.3	135				
Chloroform	1.03	0.0200	1.000	0	103	69	145				
1,1,1-Trichloroethane (TCA)	1.06	0.0250	1.000	0	106	69	132				
1,1-Dichloropropene	1.11	0.0200	1.000	0	111	72.7	131				
Carbon tetrachloride	1.10	0.0250	1.000	0	110	63.4	137				
1,2-Dichloroethane (EDC)	0.996	0.0200	1.000	0	99.6	50.9	162				
Benzene	1.06	0.0200	1.000	0	106	64.3	133				
Trichloroethene (TCE)	1.08	0.0200	1.000	0	108	65.5	137				
1,2-Dichloropropane	1.02	0.0200	1.000	0	102	63.2	142				
Bromodichloromethane	1.02	0.0200	1.000	0	102	53.4	131				
Dibromomethane	1.01	0.0200	1.000	0	101	60.1	146				
cis-1,3-Dichloropropene	0.934	0.0200	1.000	0	93.4	59.1	143				
Toluene	1.11	0.0200	1.000	0	111	67.3	138				
trans-1,3-Dichloropropylene	1.07	0.0200	1.000	0	107	49.2	149				
1,1,2-Trichloroethane	1.03	0.0200	1.000	0	103	56.9	147				
1,3-Dichloropropane	1.02	0.0250	1.000	0	102	56.1	153				
Tetrachloroethene (PCE)	1.10	0.0250	1.000	0	110	52.7	150				
Dibromochloromethane	0.958	0.0250	1.000	0	95.8	70.6	144				
1,2-Dibromoethane (EDB)	0.978	0.00500	1.000	0	97.8	50.5	154				

Work Order: 1707301
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260C

Sample ID	LCS-17817	SampType:	LCS	Units:	mg/Kg	Prep Date:	8/3/2017	RunNo:	37828		
Client ID:	LCSS	Batch ID:	17817	Analysis Date:	8/3/2017	SeqNo:	727044				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Chlorobenzene	1.07	0.0250	1.000	0	107	76.1	123				
1,1,1,2-Tetrachloroethane	1.03	0.0250	1.000	0	103	65.9	141				
Ethylbenzene	1.11	0.0250	1.000	0	111	74	129				
m,p-Xylene	2.19	0.0500	2.000	0	109	70	124				
o-Xylene	1.08	0.0250	1.000	0	108	68.1	139				
Styrene	1.07	0.0250	1.000	0	107	73.3	146				
Isopropylbenzene	1.13	0.0250	1.000	0	113	70	130				
Bromoform	0.972	0.0500	1.000	0	97.2	67	154				
1,1,2,2-Tetrachloroethane	1.01	0.0200	1.000	0	101	44.8	165				
n-Propylbenzene	1.16	0.0250	1.000	0	116	74.8	125				
Bromobenzene	1.04	0.0200	1.000	0	104	49.2	144				
1,3,5-Trimethylbenzene	1.09	0.0250	1.000	0	109	74.6	123				
2-Chlorotoluene	1.09	0.0250	1.000	0	109	76.7	129				
4-Chlorotoluene	1.08	0.0250	1.000	0	108	77.5	125				
tert-Butylbenzene	1.12	0.0250	1.000	0	112	66.2	130				
1,2,3-Trichloropropane	0.961	0.0250	1.000	0	96.1	67.9	136				
1,2,4-Trichlorobenzene	0.998	0.0250	1.000	0	99.8	62.6	143				
sec-Butylbenzene	1.15	0.0500	1.000	0	115	75.6	133				
4-Isopropyltoluene	1.07	0.0500	1.000	0	107	76.8	131				
1,3-Dichlorobenzene	1.07	0.0200	1.000	0	107	72.8	128				
1,4-Dichlorobenzene	1.06	0.0200	1.000	0	106	72.6	126				
n-Butylbenzene	1.10	0.0250	1.000	0	110	65.3	136				
1,2-Dichlorobenzene	1.06	0.0200	1.000	0	106	72.8	126				
1,2-Dibromo-3-chloropropane	0.920	0.500	1.000	0	92.0	40.2	155				
1,2,4-Trimethylbenzene	1.08	0.0200	1.000	0	108	77.5	129				
Hexachlorobutadiene	1.11	0.0500	1.000	0	111	42	151				
Naphthalene	1.02	0.0500	1.000	0	102	58.4	160				
1,2,3-Trichlorobenzene	1.02	0.0200	1.000	0	102	54.8	143				
Surr: Dibromofluoromethane	1.25		1.250		99.8	56.5	129				
Surr: Toluene-d8	1.28		1.250		103	64.5	151				
Surr: 1-Bromo-4-fluorobenzene	1.28		1.250		103	63.1	141				

Work Order: 1707301
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260C

Sample ID LCS-17817	SampType: LCS	Units: mg/Kg	Prep Date: 8/3/2017	RunNo: 37828							
Client ID: LCSS	Batch ID: 17817		Analysis Date: 8/3/2017	SeqNo: 727044							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Sample ID MB-17817	SampType: MBLK	Units: mg/Kg	Prep Date: 8/3/2017	RunNo: 37828							
Client ID: MBLKS	Batch ID: 17817		Analysis Date: 8/3/2017	SeqNo: 727045							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Dichlorodifluoromethane (CFC-12)	ND	0.0200									
Chloromethane	ND	0.0500									
Vinyl chloride	ND	0.0250									
Bromomethane	ND	0.0500									
Trichlorofluoromethane (CFC-11)	ND	0.0200									
Chloroethane	ND	0.0500									
1,1-Dichloroethene	ND	0.0200									
Methylene chloride	ND	0.0200									
trans-1,2-Dichloroethene	ND	0.0200									
Methyl tert-butyl ether (MTBE)	ND	0.0500									
1,1-Dichloroethane	ND	0.0200									
2,2-Dichloropropane	ND	0.100									Q
cis-1,2-Dichloroethene	ND	0.0200									
Chloroform	ND	0.0200									
1,1,1-Trichloroethane (TCA)	ND	0.0250									
1,1-Dichloropropene	ND	0.0200									
Carbon tetrachloride	ND	0.0250									
1,2-Dichloroethane (EDC)	ND	0.0200									
Benzene	ND	0.0200									
Trichloroethene (TCE)	ND	0.0200									
1,2-Dichloropropane	ND	0.0200									
Bromodichloromethane	ND	0.0200									
Dibromomethane	ND	0.0200									
cis-1,3-Dichloropropene	ND	0.0200									
Toluene	ND	0.0200									



Work Order: 1707301
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260C

Sample ID MB-17817	SampType: MBLK	Units: mg/Kg	Prep Date: 8/3/2017	RunNo: 37828							
Client ID: MBLKS	Batch ID: 17817		Analysis Date: 8/3/2017	SeqNo: 727045							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

trans-1,3-Dichloropropylene	ND	0.0200									
1,1,2-Trichloroethane	ND	0.0200									
1,3-Dichloropropane	ND	0.0250									
Tetrachloroethene (PCE)	ND	0.0250									
Dibromochloromethane	ND	0.0250									
1,2-Dibromoethane (EDB)	ND	0.00500									
Chlorobenzene	ND	0.0250									
1,1,1,2-Tetrachloroethane	ND	0.0250									
Ethylbenzene	ND	0.0250									
m,p-Xylene	ND	0.0500									
o-Xylene	ND	0.0250									
Styrene	ND	0.0250									
Isopropylbenzene	ND	0.0250									
Bromoform	ND	0.0500									
1,1,2,2-Tetrachloroethane	ND	0.0200									
n-Propylbenzene	ND	0.0250									
Bromobenzene	ND	0.0200									
1,3,5-Trimethylbenzene	ND	0.0250									
2-Chlorotoluene	ND	0.0250									
4-Chlorotoluene	ND	0.0250									
tert-Butylbenzene	ND	0.0250									
1,2,3-Trichloropropane	ND	0.0250									
1,2,4-Trichlorobenzene	ND	0.0250									
sec-Butylbenzene	ND	0.0500									
4-Isopropyltoluene	ND	0.0500									
1,3-Dichlorobenzene	ND	0.0200									
1,4-Dichlorobenzene	ND	0.0200									
n-Butylbenzene	ND	0.0250									
1,2-Dichlorobenzene	ND	0.0200									
1,2-Dibromo-3-chloropropane	ND	0.500									
1,2,4-Trimethylbenzene	ND	0.0200									

Work Order: 1707301
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260C

Sample ID MB-17817	SampType: MBLK	Units: mg/Kg	Prep Date: 8/3/2017	RunNo: 37828							
Client ID: MBLKS	Batch ID: 17817		Analysis Date: 8/3/2017	SeqNo: 727045							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Hexachlorobutadiene	ND	0.0500									
Naphthalene	ND	0.0500									
1,2,3-Trichlorobenzene	ND	0.0200									
Surr: Dibromofluoromethane	1.20		1.250		96.1	56.5	129				
Surr: Toluene-d8	1.27		1.250		102	64.5	151				
Surr: 1-Bromo-4-fluorobenzene	1.14		1.250		91.6	63.1	141				

Sample ID 1708016-026AMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 8/3/2017	RunNo: 37828							
Client ID: BATCH	Batch ID: 17817		Analysis Date: 8/4/2017	SeqNo: 727038							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Dichlorodifluoromethane (CFC-12)	1.96	0.0245	1.227	0	160	43.5	121				S
Chloromethane	1.49	0.0614	1.227	0	121	45	130				
Vinyl chloride	1.50	0.0307	1.227	0	122	51.2	146				
Bromomethane	0.339	0.0614	1.227	0	27.6	21.3	120				
Trichlorofluoromethane (CFC-11)	0.606	0.0245	1.227	0	49.3	35	131				
Chloroethane	0.479	0.0614	1.227	0	39.0	31.9	123				
1,1-Dichloroethene	1.38	0.0245	1.227	0	113	61.9	141				
Methylene chloride	1.36	0.0245	1.227	0	111	54.7	142				
trans-1,2-Dichloroethene	1.35	0.0245	1.227	0	110	52	136				
Methyl tert-butyl ether (MTBE)	1.09	0.0614	1.227	0	88.7	54.4	132				
1,1-Dichloroethane	1.33	0.0245	1.227	0	108	51.8	141				
2,2-Dichloropropane	0.746	0.123	1.227	0	60.8	36	123				
cis-1,2-Dichloroethene	1.33	0.0245	1.227	0	108	58.6	136				
Chloroform	1.29	0.0245	1.227	0	105	53.2	129				
1,1,1-Trichloroethane (TCA)	1.22	0.0307	1.227	0	99.6	58.3	145				
1,1-Dichloropropene	1.44	0.0245	1.227	0	118	55.1	138				
Carbon tetrachloride	1.23	0.0307	1.227	0	100	53.3	144				
1,2-Dichloroethane (EDC)	1.25	0.0245	1.227	0	102	51.3	139				
Benzene	1.38	0.0245	1.227	0	113	63.5	133				

Work Order: 1707301
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260C

Sample ID 1708016-026AMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 8/3/2017	RunNo: 37828
Client ID: BATCH	Batch ID: 17817		Analysis Date: 8/4/2017	SeqNo: 727038

Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Trichloroethene (TCE)	1.37	0.0245	1.227	0	111	68.6	132				
1,2-Dichloropropane	1.25	0.0245	1.227	0	101	59	136				
Bromodichloromethane	1.06	0.0245	1.227	0	86.2	50.7	141				
Dibromomethane	1.16	0.0245	1.227	0	94.3	50.6	137				
cis-1,3-Dichloropropene	0.950	0.0245	1.227	0	77.4	50.4	138				
Toluene	1.44	0.0245	1.227	0	117	63.4	132				
trans-1,3-Dichloropropylene	1.04	0.0245	1.227	0	84.6	44.1	147				
1,1,2-Trichloroethane	1.22	0.0245	1.227	0	99.2	51.6	137				
1,3-Dichloropropane	1.28	0.0307	1.227	0	104	53.1	134				
Tetrachloroethene (PCE)	1.58	0.0307	1.227	0.1214	119	35.6	158				
Dibromochloromethane	0.940	0.0307	1.227	0	76.6	55.3	140				
1,2-Dibromoethane (EDB)	1.16	0.00614	1.227	0	94.4	50.4	136				
Chlorobenzene	1.35	0.0307	1.227	0	110	60	133				
1,1,1,2-Tetrachloroethane	1.10	0.0307	1.227	0	89.8	53.1	142				
Ethylbenzene	1.43	0.0307	1.227	0	116	54.5	134				
m,p-Xylene	2.82	0.0614	2.455	0	115	53.1	132				
o-Xylene	1.38	0.0307	1.227	0	112	53.3	139				
Styrene	1.35	0.0307	1.227	0	110	51.1	132				
Isopropylbenzene	1.45	0.0307	1.227	0	118	58.9	138				
Bromoform	0.836	0.0614	1.227	0	68.1	57.9	130				
1,1,2,2-Tetrachloroethane	1.10	0.0245	1.227	0	89.4	51.9	131				
n-Propylbenzene	1.51	0.0307	1.227	0	123	53.6	140				
Bromobenzene	1.27	0.0245	1.227	0	104	54.2	140				
1,3,5-Trimethylbenzene	1.40	0.0307	1.227	0	114	51.8	136				
2-Chlorotoluene	1.38	0.0307	1.227	0	112	51.6	136				
4-Chlorotoluene	1.37	0.0307	1.227	0	111	50.1	139				
tert-Butylbenzene	1.43	0.0307	1.227	0	116	50.5	135				
1,2,3-Trichloropropane	1.07	0.0307	1.227	0	87.0	50.5	131				
1,2,4-Trichlorobenzene	1.27	0.0307	1.227	0	103	50.8	130				
sec-Butylbenzene	1.48	0.0614	1.227	0	121	52.6	141				
4-Isopropyltoluene	1.35	0.0614	1.227	0	110	52.9	134				

Work Order: 1707301
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260C

Sample ID 1708016-026AMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 8/3/2017	RunNo: 37828							
Client ID: BATCH	Batch ID: 17817		Analysis Date: 8/4/2017	SeqNo: 727038							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

1,3-Dichlorobenzene	1.36	0.0245	1.227	0	110	52.6	131				
1,4-Dichlorobenzene	1.35	0.0245	1.227	0	110	52.9	129				
n-Butylbenzene	1.44	0.0307	1.227	0	117	52.6	130				
1,2-Dichlorobenzene	1.30	0.0245	1.227	0	106	55.8	129				
1,2-Dibromo-3-chloropropane	0.791	0.614	1.227	0	64.4	40.5	131				
1,2,4-Trimethylbenzene	1.36	0.0245	1.227	0	111	50.6	137				
Hexachlorobutadiene	1.47	0.0614	1.227	0	120	40.6	158				
Naphthalene	1.25	0.0614	1.227	0	102	52.3	124				
1,2,3-Trichlorobenzene	1.25	0.0245	1.227	0	102	54.4	124				
Surr: Dibromofluoromethane	1.48		1.534		96.6	56.5	129				
Surr: Toluene-d8	1.59		1.534		104	64.5	151				
Surr: 1-Bromo-4-fluorobenzene	1.56		1.534		102	63.1	141				

Sample ID 1708016-026AMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 8/3/2017	RunNo: 37828							
Client ID: BATCH	Batch ID: 17817		Analysis Date: 8/4/2017	SeqNo: 727039							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Dichlorodifluoromethane (CFC-12)	1.85	0.0245	1.227	0	151	43.5	121	1.958	5.57	30	S
Chloromethane	1.54	0.0614	1.227	0	126	45	130	1.489	3.50	30	
Vinyl chloride	1.48	0.0307	1.227	0	120	51.2	146	1.497	1.23	30	
Bromomethane	0.338	0.0614	1.227	0	27.5	21.3	120	0.3385	0.136	30	
Trichlorofluoromethane (CFC-11)	0.561	0.0245	1.227	0	45.7	35	131	0.6055	7.68	30	
Chloroethane	0.449	0.0614	1.227	0	36.6	31.9	123	0.4786	6.44	30	
1,1-Dichloroethene	1.40	0.0245	1.227	0	114	61.9	141	1.381	1.02	30	
Methylene chloride	1.32	0.0245	1.227	0	108	54.7	142	1.363	2.96	30	
trans-1,2-Dichloroethene	1.33	0.0245	1.227	0	109	52	136	1.354	1.48	30	
Methyl tert-butyl ether (MTBE)	1.13	0.0614	1.227	0	92.0	54.4	132	1.088	3.67	30	
1,1-Dichloroethane	1.31	0.0245	1.227	0	107	51.8	141	1.326	1.11	30	
2,2-Dichloropropane	0.751	0.123	1.227	0	61.2	36	123	0.7462	0.672	30	
cis-1,2-Dichloroethene	1.31	0.0245	1.227	0	107	58.6	136	1.329	1.62	30	

Work Order: 1707301
 CLIENT: Shannon & Wilson
 Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260C

Sample ID 1708016-026AMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 8/3/2017	RunNo: 37828
Client ID: BATCH	Batch ID: 17817		Analysis Date: 8/4/2017	SeqNo: 727039

Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Chloroform	1.27	0.0245	1.227	0	103	53.2	129	1.290	1.60	30	
1,1,1-Trichloroethane (TCA)	1.22	0.0307	1.227	0	99.0	58.3	145	1.223	0.608	30	
1,1-Dichloropropene	1.40	0.0245	1.227	0	114	55.1	138	1.444	3.20	30	
Carbon tetrachloride	1.19	0.0307	1.227	0	96.9	53.3	144	1.231	3.50	30	
1,2-Dichloroethane (EDC)	1.23	0.0245	1.227	0	100	51.3	139	1.252	1.69	30	
Benzene	1.34	0.0245	1.227	0	109	63.5	133	1.384	2.96	30	
Trichloroethene (TCE)	1.32	0.0245	1.227	0	107	68.6	132	1.367	3.86	30	
1,2-Dichloropropane	1.23	0.0245	1.227	0	100	59	136	1.245	1.09	30	
Bromodichloromethane	1.05	0.0245	1.227	0	85.4	50.7	141	1.058	0.960	30	
Dibromomethane	1.13	0.0245	1.227	0	92.0	50.6	137	1.158	2.48	30	
cis-1,3-Dichloropropene	0.958	0.0245	1.227	0	78.0	50.4	138	0.9505	0.761	30	
Toluene	1.40	0.0245	1.227	0	114	63.4	132	1.440	3.08	30	
trans-1,3-Dichloropropylene	1.05	0.0245	1.227	0	85.8	44.1	147	1.038	1.42	30	
1,1,2-Trichloroethane	1.20	0.0245	1.227	0	97.5	51.6	137	1.218	1.69	30	
1,3-Dichloropropane	1.26	0.0307	1.227	0	103	53.1	134	1.277	1.24	30	
Tetrachloroethene (PCE)	1.52	0.0307	1.227	0.1214	114	35.6	158	1.578	3.97	30	
Dibromochloromethane	0.934	0.0307	1.227	0	76.1	55.3	140	0.9399	0.661	30	
1,2-Dibromoethane (EDB)	1.15	0.00614	1.227	0	93.8	50.4	136	1.159	0.673	30	
Chlorobenzene	1.32	0.0307	1.227	0	108	60	133	1.348	2.11	30	
1,1,1,2-Tetrachloroethane	1.09	0.0307	1.227	0	88.8	53.1	142	1.102	1.09	30	
Ethylbenzene	1.39	0.0307	1.227	0	113	54.5	134	1.429	2.57	30	
m,p-Xylene	2.73	0.0614	2.455	0	111	53.1	132	2.822	3.24	30	
o-Xylene	1.35	0.0307	1.227	0	110	53.3	139	1.378	1.76	30	
Styrene	1.33	0.0307	1.227	0	108	51.1	132	1.349	1.55	30	
Isopropylbenzene	1.41	0.0307	1.227	0	115	58.9	138	1.454	2.83	30	
Bromoform	0.829	0.0614	1.227	0	67.6	57.9	130	0.8357	0.751	30	
1,1,2,2-Tetrachloroethane	1.10	0.0245	1.227	0	89.6	51.9	131	1.097	0.256	30	
n-Propylbenzene	1.45	0.0307	1.227	0	119	53.6	140	1.508	3.61	30	
Bromobenzene	1.25	0.0245	1.227	0	102	54.2	140	1.272	2.02	30	
1,3,5-Trimethylbenzene	1.36	0.0307	1.227	0	111	51.8	136	1.400	2.75	30	
2-Chlorotoluene	1.34	0.0307	1.227	0	109	51.6	136	1.379	2.79	30	

Work Order: 1707301
 CLIENT: Shannon & Wilson
 Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260C

Sample ID	1708016-026AMSD	SampType:	MSD	Units:	mg/Kg-dry	Prep Date:	8/3/2017	RunNo:	37828		
Client ID:	BATCH	Batch ID:	17817	Analysis Date:	8/4/2017	SeqNo:	727039				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
4-Chlorotoluene	1.34	0.0307	1.227	0	109	50.1	139	1.367	2.13	30	
tert-Butylbenzene	1.39	0.0307	1.227	0	113	50.5	135	1.429	3.15	30	
1,2,3-Trichloropropane	1.05	0.0307	1.227	0	85.8	50.5	131	1.068	1.33	30	
1,2,4-Trichlorobenzene	1.31	0.0307	1.227	0	107	50.8	130	1.268	3.43	30	
sec-Butylbenzene	1.43	0.0614	1.227	0	116	52.6	141	1.483	3.83	30	
4-Isopropyltoluene	1.31	0.0614	1.227	0	106	52.9	134	1.347	3.12	30	
1,3-Dichlorobenzene	1.35	0.0245	1.227	0	110	52.6	131	1.356	0.732	30	
1,4-Dichlorobenzene	1.34	0.0245	1.227	0	109	52.9	129	1.351	1.14	30	
n-Butylbenzene	1.41	0.0307	1.227	0	115	52.6	130	1.441	1.84	30	
1,2-Dichlorobenzene	1.30	0.0245	1.227	0	106	55.8	129	1.302	0.129	30	
1,2-Dibromo-3-chloropropane	0.831	0.614	1.227	0	67.7	40.5	131	0.7908	4.92	30	
1,2,4-Trimethylbenzene	1.32	0.0245	1.227	0	107	50.6	137	1.358	3.03	30	
Hexachlorobutadiene	1.48	0.0614	1.227	0	120	40.6	158	1.474	0.228	30	
Naphthalene	1.35	0.0614	1.227	0	110	52.3	124	1.252	7.77	30	
1,2,3-Trichlorobenzene	1.29	0.0245	1.227	0	105	54.4	124	1.253	2.79	30	
Surr: Dibromofluoromethane	1.49		1.534		97.0	56.5	129		0		
Surr: Toluene-d8	1.58		1.534		103	64.5	151		0		
Surr: 1-Bromo-4-fluorobenzene	1.56		1.534		102	63.1	141		0		

Sample ID	1707301-002BDUP	SampType:	DUP	Units:	mg/Kg-dry	Prep Date:	8/3/2017	RunNo:	37828		
Client ID:	ES-2	Batch ID:	17817	Analysis Date:	8/4/2017	SeqNo:	727024				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Dichlorodifluoromethane (CFC-12)	ND	0.0175						0		30	
Chloromethane	ND	0.0436						0		30	
Vinyl chloride	ND	0.0218						0		30	
Bromomethane	ND	0.0436						0		30	
Trichlorofluoromethane (CFC-11)	ND	0.0175						0		30	
Chloroethane	ND	0.0436						0		30	
1,1-Dichloroethene	ND	0.0175						0		30	

Work Order: 1707301
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260C

Sample ID 1707301-002BDUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 8/3/2017	RunNo: 37828							
Client ID: ES-2	Batch ID: 17817		Analysis Date: 8/4/2017	SeqNo: 727024							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Methylene chloride	ND	0.0175						0		30	
trans-1,2-Dichloroethene	ND	0.0175						0		30	
Methyl tert-butyl ether (MTBE)	ND	0.0436						0		30	
1,1-Dichloroethane	ND	0.0175						0		30	
2,2-Dichloropropane	ND	0.0873						0		30	Q
cis-1,2-Dichloroethene	ND	0.0175						0		30	
Chloroform	ND	0.0175						0		30	
1,1,1-Trichloroethane (TCA)	ND	0.0218						0		30	
1,1-Dichloropropene	ND	0.0175						0		30	
Carbon tetrachloride	ND	0.0218						0		30	
1,2-Dichloroethane (EDC)	ND	0.0175						0		30	
Benzene	ND	0.0175						0		30	
Trichloroethene (TCE)	ND	0.0175						0		30	
1,2-Dichloropropane	ND	0.0175						0		30	
Bromodichloromethane	ND	0.0175						0		30	
Dibromomethane	ND	0.0175						0		30	
cis-1,3-Dichloropropene	ND	0.0175						0		30	
Toluene	ND	0.0175						0		30	
trans-1,3-Dichloropropylene	ND	0.0175						0		30	
1,1,2-Trichloroethane	ND	0.0175						0		30	
1,3-Dichloropropane	ND	0.0218						0		30	
Tetrachloroethene (PCE)	ND	0.0218						0		30	
Dibromochloromethane	ND	0.0218						0		30	
1,2-Dibromoethane (EDB)	ND	0.00436						0		30	
Chlorobenzene	ND	0.0218						0		30	
1,1,1,2-Tetrachloroethane	ND	0.0218						0		30	
Ethylbenzene	ND	0.0218						0		30	
m,p-Xylene	ND	0.0436						0		30	
o-Xylene	ND	0.0218						0		30	
Styrene	ND	0.0218						0		30	
Isopropylbenzene	ND	0.0218						0		30	

Work Order: 1707301
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260C

Sample ID 1707301-002BDUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 8/3/2017	RunNo: 37828							
Client ID: ES-2	Batch ID: 17817		Analysis Date: 8/4/2017	SeqNo: 727024							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Bromoform	ND	0.0436						0		30	
1,1,2,2-Tetrachloroethane	ND	0.0175						0		30	
n-Propylbenzene	ND	0.0218						0		30	
Bromobenzene	ND	0.0175						0		30	
1,3,5-Trimethylbenzene	ND	0.0218						0		30	
2-Chlorotoluene	ND	0.0218						0		30	
4-Chlorotoluene	ND	0.0218						0		30	
tert-Butylbenzene	ND	0.0218						0		30	
1,2,3-Trichloropropane	ND	0.0218						0		30	
1,2,4-Trichlorobenzene	ND	0.0218						0		30	
sec-Butylbenzene	ND	0.0436						0		30	
4-Isopropyltoluene	ND	0.0436						0		30	
1,3-Dichlorobenzene	ND	0.0175						0		30	
1,4-Dichlorobenzene	ND	0.0175						0		30	
n-Butylbenzene	ND	0.0218						0		30	
1,2-Dichlorobenzene	ND	0.0175						0		30	
1,2-Dibromo-3-chloropropane	ND	0.436						0		30	
1,2,4-Trimethylbenzene	ND	0.0175						0		30	
Hexachlorobutadiene	ND	0.0436						0		30	
Naphthalene	ND	0.0436						0		30	
1,2,3-Trichlorobenzene	ND	0.0175						0		30	
Surr: Dibromofluoromethane	0.952		1.091		87.3	56.5	129		0		
Surr: Toluene-d8	1.13		1.091		103	64.5	151		0		
Surr: 1-Bromo-4-fluorobenzene	0.973		1.091		89.2	63.1	141		0		

Client Name: SW	Work Order Number: 1707301
Logged by: Erica Silva	Date Received: 7/31/2017 8:39:00 AM

Chain of Custody

1. Is Chain of Custody complete? Yes No Not Present
2. How was the sample delivered? FedEx

Log In

3. Coolers are present? Yes No NA
4. Shipping container/cooler in good condition? Yes No
5. Custody Seals present on shipping container/cooler?
(Refer to comments for Custody Seals not intact) Yes No Not Required
6. Was an attempt made to cool the samples? Yes No NA

Unknown prior to receipt

7. Were all items received at a temperature of >0°C to 10.0°C* Yes No NA

Please refer to Item Information

8. Sample(s) in proper container(s)? Yes No
9. Sufficient sample volume for indicated test(s)? Yes No
10. Are samples properly preserved? Yes No
11. Was preservative added to bottles? Yes No NA
MeOH NA
12. Is there headspace in the VOA vials? Yes No NA
13. Did all samples containers arrive in good condition(unbroken)? Yes No
14. Does paperwork match bottle labels? Yes No
15. Are matrices correctly identified on Chain of Custody? Yes No
16. Is it clear what analyses were requested? Yes No
17. Were all holding times able to be met? Yes No

Special Handling (if applicable)

18. Was client notified of all discrepancies with this order? Yes No NA

Person Notified:	Ben Carlson	Date	7/31/2017
By Whom:	Erica Silva	Via:	<input checked="" type="checkbox"/> eMail <input type="checkbox"/> Phone <input type="checkbox"/> Fax <input type="checkbox"/> In Person
Regarding:	Sample dates/times, Metals select lists, Herb/Pest methods, lab extraction necessary for		
Client Instructions:	See COC for edits, lab extraction for VOCs/Gx approved		

19. Additional remarks:

Item Information

Item #	Temp °C
Cooler	21.6
Sample	22.6
Temp Blank	22.3

* Note: DoD/ELAP and TNI require items to be received at 4°C +/- 2°C



3600 Fremont Ave. N.
Seattle, WA 98103
T: (206) 352-3790
F: (206) 352-7178
info@fremontanalytical.com

Shannon & Wilson

Brian Reznick
400 N. 34th Street, Suite 100
Seattle, WA 98103

RE: Yakima EWC
Work Order Number: 1708051

August 14, 2017

Attention Brian Reznick:

Fremont Analytical, Inc. received 4 sample(s) on 8/4/2017 for the analyses presented in the following report.

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.
Gasoline by NWTPH-Gx
Herbicides by EPA Method 8151A
Mercury by EPA Method 7471
Organochlorine Pesticides by EPA Method 8081
Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)
Polychlorinated Biphenyls (PCB) by EPA 8082
Sample Moisture (Percent Moisture)
Total Metals by EPA Method 6020
Volatile Organic Compounds by EPA Method 8260C

This report consists of the following:

- Case Narrative
- Analytical Results
- Applicable Quality Control Summary Reports
- Chain of Custody

All analyses were performed consistent with the Quality Assurance program of Fremont Analytical, Inc. Please contact the laboratory if you should have any questions about the results.

Thank you for using Fremont Analytical.

Sincerely,

DoD/ELAP Certification #L17-135, ISO/IEC 17025:2005
ORELAP Certification: WA 100009-007 (NELAP Recognized)

Mike Ridgeway
Laboratory Director

*DoD/ELAP Certification #L17-135, ISO/IEC 17025:2005
ORELAP Certification: WA 100009-007 (NELAP Recognized)*



Date: 08/14/2017

CLIENT: Shannon & Wilson
Project: Yakima EWC
Work Order: 1708051

Work Order Sample Summary

Lab Sample ID	Client Sample ID	Date/Time Collected	Date/Time Received
1708051-001	ES-5	08/03/2017 3:56 AM	08/04/2017 1:15 PM
1708051-002	ES-6	08/03/2017 5:08 AM	08/04/2017 1:15 PM
1708051-003	ES-7	08/03/2017 5:25 AM	08/04/2017 1:15 PM
1708051-004	ES-8	08/03/2017 7:47 AM	08/04/2017 1:15 PM

CLIENT: Shannon & Wilson**Project:** Yakima EWC

I. SAMPLE RECEIPT:

Samples receipt information is recorded on the attached Sample Receipt Checklist.

II. GENERAL REPORTING COMMENTS:

Results are reported on a wet weight basis unless dry-weight correction is denoted in the units field on the analytical report ("mg/kg-dry" or "ug/kg-dry").

Matrix Spike (MS) and MS Duplicate (MSD) samples are tested from an analytical batch of "like" matrix to check for possible matrix effect. The MS and MSD will provide site specific matrix data only for those samples which are spiked by the laboratory. The sample chosen for spike purposes may or may not have been a sample submitted in this sample delivery group. The validity of the analytical procedures for which data is reported in this analytical report is determined by the Laboratory Control Sample (LCS) and the Method Blank (MB). The LCS and the MB are processed with the samples and the MS/MSD to ensure method criteria are achieved throughout the entire analytical process.

III. ANALYSES AND EXCEPTIONS:

Exceptions associated with this report will be footnoted in the analytical results page(s) or the quality control summary page(s) and/or noted below.

Prep Comments for METHOD (PREP-PCB-S), SAMPLE (1708051-002A) required Acid Cleanup Procedure (Using Method No 3665A).

Prep Comments for METHOD (PREP-PCB-S), SAMPLE (1708051-003A) required Acid Cleanup Procedure (Using Method No 3665A).

Prep Comments for METHOD (PREP-PCB-S), SAMPLE (1708051-004A) required Acid Cleanup Procedure (Using Method No 3665A).

Prep Comments for METHOD (PREP-PCB-S), SAMPLE (1708051-002A) required Florisil Cleanup Procedure (Using Method No 3620C).

Prep Comments for METHOD (PREP-PCB-S), SAMPLE (1708051-003A) required Florisil Cleanup Procedure (Using Method No 3620C).

Prep Comments for METHOD (PREP-PCB-S), SAMPLE (1708051-004A) required Florisil Cleanup Procedure (Using Method No 3620C).

Qualifiers:

- * - Flagged value is not within established control limits
- B - Analyte detected in the associated Method Blank
- D - Dilution was required
- E - Value above quantitation range
- H - Holding times for preparation or analysis exceeded
- I - Analyte with an internal standard that does not meet established acceptance criteria
- J - Analyte detected below Reporting Limit
- N - Tentatively Identified Compound (TIC)
- Q - Analyte with an initial or continuing calibration that does not meet established acceptance criteria (<20%RSD, <20% Drift or minimum RRF)
- S - Spike recovery outside accepted recovery limits
- ND - Not detected at the Reporting Limit
- R - High relative percent difference observed

Acronyms:

- %Rec - Percent Recovery
- CCB - Continued Calibration Blank
- CCV - Continued Calibration Verification
- DF - Dilution Factor
- HEM - Hexane Extractable Material
- ICV - Initial Calibration Verification
- LCS/LCSD - Laboratory Control Sample / Laboratory Control Sample Duplicate
- MB or MBLANK - Method Blank
- MDL - Method Detection Limit
- MS/MSD - Matrix Spike / Matrix Spike Duplicate
- PDS - Post Digestion Spike
- Ref Val - Reference Value
- RL - Reporting Limit
- RPD - Relative Percent Difference
- SD - Serial Dilution
- SGT - Silica Gel Treatment
- SPK - Spike
- Surr - Surrogate



Client: Shannon & Wilson

Collection Date: 8/3/2017 3:56:00 AM

Project: Yakima EWC

Lab ID: 1708051-001

Matrix: Soil

Client Sample ID: ES-5

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Organochlorine Pesticides by EPA Method 8081

Batch ID: 17824

Analyst: SG

Toxaphene	ND	0.106		mg/Kg-dry	1	8/7/2017 8:34:39 PM
Alpha BHC	ND	0.0106		mg/Kg-dry	1	8/7/2017 8:34:39 PM
Beta BHC	ND	0.0106		mg/Kg-dry	1	8/7/2017 8:34:39 PM
Gamma BHC (Lindane)	ND	0.0106		mg/Kg-dry	1	8/7/2017 8:34:39 PM
Delta BHC	ND	0.0106		mg/Kg-dry	1	8/7/2017 8:34:39 PM
Heptachlor	ND	0.0106		mg/Kg-dry	1	8/7/2017 8:34:39 PM
Aldrin	ND	0.0106		mg/Kg-dry	1	8/7/2017 8:34:39 PM
Heptachlor epoxide	ND	0.0106		mg/Kg-dry	1	8/7/2017 8:34:39 PM
gamma-Chlordane	ND	0.0106		mg/Kg-dry	1	8/7/2017 8:34:39 PM
Endosulfan I	ND	0.0106		mg/Kg-dry	1	8/7/2017 8:34:39 PM
alpha-Chlordane	ND	0.0106		mg/Kg-dry	1	8/7/2017 8:34:39 PM
Dieldrin	ND	0.0106		mg/Kg-dry	1	8/7/2017 8:34:39 PM
4,4'-DDE	ND	0.0106		mg/Kg-dry	1	8/7/2017 8:34:39 PM
Endrin	ND	0.0106		mg/Kg-dry	1	8/7/2017 8:34:39 PM
Endosulfan II	ND	0.0106		mg/Kg-dry	1	8/7/2017 8:34:39 PM
4,4'-DDD	ND	0.0106		mg/Kg-dry	1	8/7/2017 8:34:39 PM
Endrin aldehyde	ND	0.0106		mg/Kg-dry	1	8/7/2017 8:34:39 PM
Endosulfan sulfate	ND	0.0106		mg/Kg-dry	1	8/7/2017 8:34:39 PM
4,4'-DDT	ND	0.0106		mg/Kg-dry	1	8/7/2017 8:34:39 PM
Endrin ketone	ND	0.0106		mg/Kg-dry	1	8/7/2017 8:34:39 PM
Methoxychlor	ND	0.0106		mg/Kg-dry	1	8/7/2017 8:34:39 PM
Surr: Decachlorobiphenyl	93.8	17.8 - 157		%Rec	1	8/7/2017 8:34:39 PM
Surr: Tetrachloro-m-xylene	97.1	11 - 150		%Rec	1	8/7/2017 8:34:39 PM

Herbicides by EPA Method 8151A

Batch ID: 17825

Analyst: BT

Dicamba	ND	36.1		µg/Kg-dry	1	8/10/2017 3:58:30 AM
2,4-D	ND	30.9		µg/Kg-dry	1	8/10/2017 3:58:30 AM
2,4-DP	ND	25.8		µg/Kg-dry	1	8/10/2017 3:58:30 AM
2,4,5-TP (Silvex)	ND	20.6		µg/Kg-dry	1	8/10/2017 3:58:30 AM
2,4,5-T	ND	51.6		µg/Kg-dry	1	8/10/2017 3:58:30 AM
Dinoseb	ND	30.9		µg/Kg-dry	1	8/10/2017 3:58:30 AM
Dalapon	ND	206		µg/Kg-dry	1	8/10/2017 3:58:30 AM
2,4-DB	ND	25.8		µg/Kg-dry	1	8/10/2017 3:58:30 AM
MCPP	ND	4,540		µg/Kg-dry	1	8/10/2017 3:58:30 AM
MCPA	ND	2,890		µg/Kg-dry	1	8/10/2017 3:58:30 AM
Picloram	ND	51.6		µg/Kg-dry	1	8/10/2017 3:58:30 AM
Bentazon	ND	36.1		µg/Kg-dry	1	8/10/2017 3:58:30 AM
Chloramben	ND	20.6		µg/Kg-dry	1	8/10/2017 3:58:30 AM



Client: Shannon & Wilson

Collection Date: 8/3/2017 3:56:00 AM

Project: Yakima EWC

Lab ID: 1708051-001

Matrix: Soil

Client Sample ID: ES-5

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Herbicides by EPA Method 8151A

Batch ID: 17825 Analyst: BT

Acifluorfen	ND	82.5		µg/Kg-dry	1	8/10/2017 3:58:30 AM
3,5-Dichlorobenzoic acid	ND	41.3		µg/Kg-dry	1	8/10/2017 3:58:30 AM
4-Nitrophenol	ND	30.9		µg/Kg-dry	1	8/10/2017 3:58:30 AM
Dacthal (DCPA)	ND	30.9		µg/Kg-dry	1	8/10/2017 3:58:30 AM
Surr: 2,4-Dichlorophenylacetic acid	57.0	20.1 - 168		%Rec	1	8/10/2017 3:58:30 AM

Mercury by EPA Method 7471

Batch ID: 17871 Analyst: WF

Mercury	ND	0.251		mg/Kg-dry	1	8/10/2017 4:58:50 PM
---------	----	-------	--	-----------	---	----------------------

Total Metals by EPA Method 6020

Batch ID: 17834 Analyst: TN

Arsenic	4.19	0.0852		mg/Kg-dry	1	8/9/2017 12:44:36 PM
Barium	162	0.426		mg/Kg-dry	1	8/9/2017 12:44:36 PM
Cadmium	0.175	0.170		mg/Kg-dry	1	8/9/2017 12:44:36 PM
Chromium	36.7	0.0852		mg/Kg-dry	1	8/9/2017 12:44:36 PM
Copper	48.8	0.170		mg/Kg-dry	1	8/9/2017 12:44:36 PM
Lead	7.10	0.170		mg/Kg-dry	1	8/9/2017 12:44:36 PM
Nickel	69.1	0.0852		mg/Kg-dry	1	8/9/2017 12:44:36 PM
Selenium	2.16	0.426		mg/Kg-dry	1	8/9/2017 12:44:36 PM
Silver	ND	0.0813		mg/Kg-dry	1	8/10/2017 2:27:32 PM
Zinc	82.7	0.341		mg/Kg-dry	1	8/9/2017 12:44:36 PM

Sample Moisture (Percent Moisture)

Batch ID: R37834 Analyst: BB

Percent Moisture	6.06			wt%	1	8/7/2017 9:08:52 AM
------------------	------	--	--	-----	---	---------------------



Client: Shannon & Wilson

Collection Date: 8/3/2017 5:08:00 AM

Project: Yakima EWC

Lab ID: 1708051-002

Matrix: Soil

Client Sample ID: ES-6

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Polychlorinated Biphenyls (PCB) by EPA 8082

Batch ID: 17861 Analyst: SG

Aroclor 1016	ND	0.295		mg/Kg-dry	1	8/9/2017 5:54:14 PM
Aroclor 1221	ND	0.295		mg/Kg-dry	1	8/9/2017 5:54:14 PM
Aroclor 1232	ND	0.295		mg/Kg-dry	1	8/9/2017 5:54:14 PM
Aroclor 1242	ND	0.295		mg/Kg-dry	1	8/9/2017 5:54:14 PM
Aroclor 1248	ND	0.295		mg/Kg-dry	1	8/9/2017 5:54:14 PM
Aroclor 1254	ND	0.295		mg/Kg-dry	1	8/9/2017 5:54:14 PM
Aroclor 1260	ND	0.295		mg/Kg-dry	1	8/9/2017 5:54:14 PM
Aroclor 1262	ND	0.295		mg/Kg-dry	1	8/9/2017 5:54:14 PM
Aroclor 1268	ND	0.295		mg/Kg-dry	1	8/9/2017 5:54:14 PM
Total PCBs	ND	0.295		mg/Kg-dry	1	8/9/2017 5:54:14 PM
Surr: Decachlorobiphenyl	94.1	30.8 - 168		%Rec	1	8/9/2017 5:54:14 PM
Surr: Tetrachloro-m-xylene	67.3	30.3 - 157		%Rec	1	8/9/2017 5:54:14 PM

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Batch ID: 17826 Analyst: SB

Diesel (Fuel Oil)	ND	19.2		mg/Kg-dry	1	8/5/2017 3:35:13 AM
Heavy Oil	ND	48.1		mg/Kg-dry	1	8/5/2017 3:35:13 AM
Heavy Oil Range Organics (C24-37)	495	48.1		mg/Kg-dry	1	8/5/2017 3:35:13 AM
Surr: 2-Fluorobiphenyl	114	50 - 150		%Rec	1	8/5/2017 3:35:13 AM
Surr: o-Terphenyl	117	50 - 150		%Rec	1	8/5/2017 3:35:13 AM

NOTES:

Heavy Oil Range Organics - Indicates the presence of unresolved compounds in the Lube+ Oil ranges.

Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Batch ID: 17832 Analyst: BT

Naphthalene	ND	119		µg/Kg-dry	1	8/7/2017 3:46:33 PM
2-Methylnaphthalene	ND	119		µg/Kg-dry	1	8/7/2017 3:46:33 PM
1-Methylnaphthalene	ND	119		µg/Kg-dry	1	8/7/2017 3:46:33 PM
Acenaphthylene	ND	119		µg/Kg-dry	1	8/7/2017 3:46:33 PM
Acenaphthene	ND	119		µg/Kg-dry	1	8/7/2017 3:46:33 PM
Fluorene	ND	119		µg/Kg-dry	1	8/7/2017 3:46:33 PM
Phenanthrene	ND	119		µg/Kg-dry	1	8/7/2017 3:46:33 PM
Anthracene	ND	119		µg/Kg-dry	1	8/7/2017 3:46:33 PM
Fluoranthene	ND	119		µg/Kg-dry	1	8/7/2017 3:46:33 PM
Pyrene	ND	119		µg/Kg-dry	1	8/7/2017 3:46:33 PM
Benz(a)anthracene	ND	119		µg/Kg-dry	1	8/7/2017 3:46:33 PM
Chrysene	ND	119		µg/Kg-dry	1	8/7/2017 3:46:33 PM
Benzo(b)fluoranthene	ND	119		µg/Kg-dry	1	8/7/2017 3:46:33 PM
Benzo(j,k)fluoranthene	ND	119		µg/Kg-dry	1	8/7/2017 3:46:33 PM



Client: Shannon & Wilson

Collection Date: 8/3/2017 5:08:00 AM

Project: Yakima EWC

Lab ID: 1708051-002

Matrix: Soil

Client Sample ID: ES-6

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Batch ID: 17832 Analyst: BT

Benzo(a)pyrene	ND	119		µg/Kg-dry	1	8/7/2017 3:46:33 PM
Indeno(1,2,3-cd)pyrene	ND	119		µg/Kg-dry	1	8/7/2017 3:46:33 PM
Dibenz(a,h)anthracene	ND	119		µg/Kg-dry	1	8/7/2017 3:46:33 PM
Benzo(g,h,i)perylene	ND	119		µg/Kg-dry	1	8/7/2017 3:46:33 PM
Surr: 2-Fluorobiphenyl	80.8	24.5 - 139		%Rec	1	8/7/2017 3:46:33 PM
Surr: Terphenyl-d14 (surr)	109	46.2 - 179		%Rec	1	8/7/2017 3:46:33 PM

Gasoline by NWTPH-Gx

Batch ID: 17870 Analyst: NG

Gasoline	ND	25.8		mg/Kg-dry	1	8/10/2017 8:25:03 PM
Surr: Toluene-d8	96.5	65 - 135		%Rec	1	8/10/2017 8:25:03 PM
Surr: 4-Bromofluorobenzene	105	65 - 135		%Rec	1	8/10/2017 8:25:03 PM

Volatile Organic Compounds by EPA Method 8260C

Batch ID: 17870 Analyst: NG

Dichlorodifluoromethane (CFC-12)	ND	0.103		mg/Kg-dry	1	8/10/2017 8:25:03 PM
Chloromethane	ND	0.258		mg/Kg-dry	1	8/10/2017 8:25:03 PM
Vinyl chloride	ND	0.129		mg/Kg-dry	1	8/10/2017 8:25:03 PM
Bromomethane	ND	0.258		mg/Kg-dry	1	8/10/2017 8:25:03 PM
Trichlorofluoromethane (CFC-11)	ND	0.103		mg/Kg-dry	1	8/10/2017 8:25:03 PM
Chloroethane	ND	0.258		mg/Kg-dry	1	8/10/2017 8:25:03 PM
1,1-Dichloroethene	ND	0.103		mg/Kg-dry	1	8/10/2017 8:25:03 PM
Methylene chloride	ND	0.103		mg/Kg-dry	1	8/10/2017 8:25:03 PM
trans-1,2-Dichloroethene	ND	0.103		mg/Kg-dry	1	8/10/2017 8:25:03 PM
Methyl tert-butyl ether (MTBE)	ND	0.258		mg/Kg-dry	1	8/10/2017 8:25:03 PM
1,1-Dichloroethane	ND	0.103		mg/Kg-dry	1	8/10/2017 8:25:03 PM
2,2-Dichloropropane	ND	0.516		mg/Kg-dry	1	8/10/2017 8:25:03 PM
cis-1,2-Dichloroethene	ND	0.103		mg/Kg-dry	1	8/10/2017 8:25:03 PM
Chloroform	ND	0.103		mg/Kg-dry	1	8/10/2017 8:25:03 PM
1,1,1-Trichloroethane (TCA)	ND	0.129		mg/Kg-dry	1	8/10/2017 8:25:03 PM
1,1-Dichloropropene	ND	0.103		mg/Kg-dry	1	8/10/2017 8:25:03 PM
Carbon tetrachloride	ND	0.129		mg/Kg-dry	1	8/10/2017 8:25:03 PM
1,2-Dichloroethane (EDC)	ND	0.103		mg/Kg-dry	1	8/10/2017 8:25:03 PM
Benzene	ND	0.103		mg/Kg-dry	1	8/10/2017 8:25:03 PM
Trichloroethene (TCE)	ND	0.103		mg/Kg-dry	1	8/10/2017 8:25:03 PM
1,2-Dichloropropane	ND	0.103		mg/Kg-dry	1	8/10/2017 8:25:03 PM
Bromodichloromethane	ND	0.103		mg/Kg-dry	1	8/10/2017 8:25:03 PM
Dibromomethane	ND	0.103		mg/Kg-dry	1	8/10/2017 8:25:03 PM
cis-1,3-Dichloropropene	ND	0.103		mg/Kg-dry	1	8/10/2017 8:25:03 PM



Client: Shannon & Wilson

Collection Date: 8/3/2017 5:08:00 AM

Project: Yakima EWC

Lab ID: 1708051-002

Matrix: Soil

Client Sample ID: ES-6

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Volatile Organic Compounds by EPA Method 8260C

Batch ID: 17870

Analyst: NG

Toluene	0.177	0.103		mg/Kg-dry	1	8/10/2017 8:25:03 PM
trans-1,3-Dichloropropylene	ND	0.103		mg/Kg-dry	1	8/10/2017 8:25:03 PM
1,1,2-Trichloroethane	ND	0.103		mg/Kg-dry	1	8/10/2017 8:25:03 PM
1,3-Dichloropropane	ND	0.129		mg/Kg-dry	1	8/10/2017 8:25:03 PM
Tetrachloroethene (PCE)	ND	0.129		mg/Kg-dry	1	8/10/2017 8:25:03 PM
Dibromochloromethane	ND	0.129		mg/Kg-dry	1	8/10/2017 8:25:03 PM
1,2-Dibromoethane (EDB)	ND	0.0258		mg/Kg-dry	1	8/10/2017 8:25:03 PM
Chlorobenzene	ND	0.129		mg/Kg-dry	1	8/10/2017 8:25:03 PM
1,1,1,2-Tetrachloroethane	ND	0.129		mg/Kg-dry	1	8/10/2017 8:25:03 PM
Ethylbenzene	ND	0.129		mg/Kg-dry	1	8/10/2017 8:25:03 PM
m,p-Xylene	ND	0.258		mg/Kg-dry	1	8/10/2017 8:25:03 PM
o-Xylene	ND	0.129		mg/Kg-dry	1	8/10/2017 8:25:03 PM
Styrene	ND	0.129		mg/Kg-dry	1	8/10/2017 8:25:03 PM
Isopropylbenzene	ND	0.129		mg/Kg-dry	1	8/10/2017 8:25:03 PM
Bromoform	ND	0.258		mg/Kg-dry	1	8/10/2017 8:25:03 PM
1,1,2,2-Tetrachloroethane	ND	0.103		mg/Kg-dry	1	8/10/2017 8:25:03 PM
n-Propylbenzene	ND	0.129		mg/Kg-dry	1	8/10/2017 8:25:03 PM
Bromobenzene	ND	0.103		mg/Kg-dry	1	8/10/2017 8:25:03 PM
1,3,5-Trimethylbenzene	ND	0.129		mg/Kg-dry	1	8/10/2017 8:25:03 PM
2-Chlorotoluene	ND	0.129		mg/Kg-dry	1	8/10/2017 8:25:03 PM
4-Chlorotoluene	ND	0.129		mg/Kg-dry	1	8/10/2017 8:25:03 PM
tert-Butylbenzene	ND	0.129		mg/Kg-dry	1	8/10/2017 8:25:03 PM
1,2,3-Trichloropropane	ND	0.129		mg/Kg-dry	1	8/10/2017 8:25:03 PM
1,2,4-Trichlorobenzene	0.270	0.129		mg/Kg-dry	1	8/10/2017 8:25:03 PM
sec-Butylbenzene	ND	0.258		mg/Kg-dry	1	8/10/2017 8:25:03 PM
4-Isopropyltoluene	ND	0.258		mg/Kg-dry	1	8/10/2017 8:25:03 PM
1,3-Dichlorobenzene	ND	0.103		mg/Kg-dry	1	8/10/2017 8:25:03 PM
1,4-Dichlorobenzene	ND	0.103		mg/Kg-dry	1	8/10/2017 8:25:03 PM
n-Butylbenzene	ND	0.129		mg/Kg-dry	1	8/10/2017 8:25:03 PM
1,2-Dichlorobenzene	ND	0.103		mg/Kg-dry	1	8/10/2017 8:25:03 PM
1,2-Dibromo-3-chloropropane	ND	2.58		mg/Kg-dry	1	8/10/2017 8:25:03 PM
1,2,4-Trimethylbenzene	ND	0.103		mg/Kg-dry	1	8/10/2017 8:25:03 PM
Hexachlorobutadiene	ND	0.258		mg/Kg-dry	1	8/10/2017 8:25:03 PM
Naphthalene	ND	0.258		mg/Kg-dry	1	8/10/2017 8:25:03 PM
1,2,3-Trichlorobenzene	0.270	0.103		mg/Kg-dry	1	8/10/2017 8:25:03 PM
Surr: Dibromofluoromethane	94.7	56.5 - 129		%Rec	1	8/10/2017 8:25:03 PM
Surr: Toluene-d8	100	64.5 - 151		%Rec	1	8/10/2017 8:25:03 PM
Surr: 1-Bromo-4-fluorobenzene	106	63.1 - 141		%Rec	1	8/10/2017 8:25:03 PM



Client: Shannon & Wilson

Collection Date: 8/3/2017 5:08:00 AM

Project: Yakima EWC

Lab ID: 1708051-002

Matrix: Soil

Client Sample ID: ES-6

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Mercury by EPA Method 7471

Batch ID: 17871 Analyst: WF

Mercury	ND	0.702		mg/Kg-dry	1	8/10/2017 5:00:27 PM
---------	----	-------	--	-----------	---	----------------------

Total Metals by EPA Method 6020

Batch ID: 17834 Analyst: TN

Arsenic	2.92	0.236		mg/Kg-dry	1	8/9/2017 12:48:38 PM
Barium	72.5	1.18		mg/Kg-dry	1	8/9/2017 12:48:38 PM
Cadmium	ND	0.473		mg/Kg-dry	1	8/9/2017 12:48:38 PM
Chromium	5.51	0.236		mg/Kg-dry	1	8/9/2017 12:48:38 PM
Copper	12.0	0.473		mg/Kg-dry	1	8/9/2017 12:48:38 PM
Lead	14.2	0.473		mg/Kg-dry	1	8/9/2017 12:48:38 PM
Nickel	5.56	0.236		mg/Kg-dry	1	8/9/2017 12:48:38 PM
Selenium	ND	1.18		mg/Kg-dry	1	8/9/2017 12:48:38 PM
Silver	ND	0.224		mg/Kg-dry	1	8/10/2017 2:39:38 PM
Zinc	56.5	0.945		mg/Kg-dry	1	8/9/2017 12:48:38 PM

Sample Moisture (Percent Moisture)

Batch ID: R37834 Analyst: BB

Percent Moisture	66.4			wt%	1	8/7/2017 9:08:52 AM
------------------	------	--	--	-----	---	---------------------



Client: Shannon & Wilson

Collection Date: 8/3/2017 5:25:00 AM

Project: Yakima EWC

Lab ID: 1708051-003

Matrix: Soil

Client Sample ID: ES-7

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Polychlorinated Biphenyls (PCB) by EPA 8082

Batch ID: 17833

Analyst: SG

Aroclor 1016	ND	0.103		mg/Kg-dry	1	8/7/2017 2:10:06 PM
Aroclor 1221	ND	0.103		mg/Kg-dry	1	8/7/2017 2:10:06 PM
Aroclor 1232	ND	0.103		mg/Kg-dry	1	8/7/2017 2:10:06 PM
Aroclor 1242	ND	0.103		mg/Kg-dry	1	8/7/2017 2:10:06 PM
Aroclor 1248	ND	0.103		mg/Kg-dry	1	8/7/2017 2:10:06 PM
Aroclor 1254	ND	0.103		mg/Kg-dry	1	8/7/2017 2:10:06 PM
Aroclor 1260	ND	0.103		mg/Kg-dry	1	8/7/2017 2:10:06 PM
Aroclor 1262	ND	0.103		mg/Kg-dry	1	8/7/2017 2:10:06 PM
Aroclor 1268	ND	0.103		mg/Kg-dry	1	8/7/2017 2:10:06 PM
Total PCBs	ND	0.103		mg/Kg-dry	1	8/7/2017 2:10:06 PM
Surr: Decachlorobiphenyl	154	30.8 - 168		%Rec	1	8/7/2017 2:10:06 PM
Surr: Tetrachloro-m-xylene	130	30.3 - 157		%Rec	1	8/7/2017 2:10:06 PM

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Batch ID: 17826

Analyst: SB

Diesel (Fuel Oil)	ND	18.9		mg/Kg-dry	1	8/5/2017 4:40:29 AM
Heavy Oil	ND	47.3		mg/Kg-dry	1	8/5/2017 4:40:29 AM
Surr: 2-Fluorobiphenyl	88.2	50 - 150		%Rec	1	8/5/2017 4:40:29 AM
Surr: o-Terphenyl	93.3	50 - 150		%Rec	1	8/5/2017 4:40:29 AM

Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Batch ID: 17832

Analyst: BT

Naphthalene	ND	37.1		µg/Kg-dry	1	8/7/2017 2:13:46 PM
2-Methylnaphthalene	ND	37.1		µg/Kg-dry	1	8/7/2017 2:13:46 PM
1-Methylnaphthalene	ND	37.1		µg/Kg-dry	1	8/7/2017 2:13:46 PM
Acenaphthylene	ND	37.1		µg/Kg-dry	1	8/7/2017 2:13:46 PM
Acenaphthene	ND	37.1		µg/Kg-dry	1	8/7/2017 2:13:46 PM
Fluorene	ND	37.1		µg/Kg-dry	1	8/7/2017 2:13:46 PM
Phenanthrene	ND	37.1		µg/Kg-dry	1	8/7/2017 2:13:46 PM
Anthracene	ND	37.1		µg/Kg-dry	1	8/7/2017 2:13:46 PM
Fluoranthene	ND	37.1		µg/Kg-dry	1	8/7/2017 2:13:46 PM
Pyrene	ND	37.1		µg/Kg-dry	1	8/7/2017 2:13:46 PM
Benz(a)anthracene	ND	37.1		µg/Kg-dry	1	8/7/2017 2:13:46 PM
Chrysene	ND	37.1		µg/Kg-dry	1	8/7/2017 2:13:46 PM
Benzo(b)fluoranthene	ND	37.1		µg/Kg-dry	1	8/7/2017 2:13:46 PM
Benzo(j,k)fluoranthene	ND	37.1		µg/Kg-dry	1	8/7/2017 2:13:46 PM
Benzo(a)pyrene	ND	37.1		µg/Kg-dry	1	8/7/2017 2:13:46 PM
Indeno(1,2,3-cd)pyrene	ND	37.1		µg/Kg-dry	1	8/7/2017 2:13:46 PM
Dibenz(a,h)anthracene	ND	37.1		µg/Kg-dry	1	8/7/2017 2:13:46 PM



Client: Shannon & Wilson

Collection Date: 8/3/2017 5:25:00 AM

Project: Yakima EWC

Lab ID: 1708051-003

Matrix: Soil

Client Sample ID: ES-7

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Batch ID: 17832 Analyst: BT

Benzo(g,h,i)perylene	ND	37.1		µg/Kg-dry	1	8/7/2017 2:13:46 PM
Surr: 2-Fluorobiphenyl	80.3	24.5 - 139		%Rec	1	8/7/2017 2:13:46 PM
Surr: Terphenyl-d14 (surr)	116	46.2 - 179		%Rec	1	8/7/2017 2:13:46 PM

Gasoline by NWTPH-Gx

Batch ID: 17870 Analyst: NG

Gasoline	ND	4.51		mg/Kg-dry	1	8/10/2017 8:55:05 PM
Surr: Toluene-d8	97.1	65 - 135		%Rec	1	8/10/2017 8:55:05 PM
Surr: 4-Bromofluorobenzene	106	65 - 135		%Rec	1	8/10/2017 8:55:05 PM

Volatile Organic Compounds by EPA Method 8260C

Batch ID: 17870 Analyst: NG

Dichlorodifluoromethane (CFC-12)	ND	0.0181		mg/Kg-dry	1	8/10/2017 8:55:05 PM
Chloromethane	ND	0.0451		mg/Kg-dry	1	8/10/2017 8:55:05 PM
Vinyl chloride	ND	0.0226		mg/Kg-dry	1	8/10/2017 8:55:05 PM
Bromomethane	ND	0.0451		mg/Kg-dry	1	8/10/2017 8:55:05 PM
Trichlorofluoromethane (CFC-11)	ND	0.0181		mg/Kg-dry	1	8/10/2017 8:55:05 PM
Chloroethane	ND	0.0451		mg/Kg-dry	1	8/10/2017 8:55:05 PM
1,1-Dichloroethene	ND	0.0181		mg/Kg-dry	1	8/10/2017 8:55:05 PM
Methylene chloride	ND	0.0181		mg/Kg-dry	1	8/10/2017 8:55:05 PM
trans-1,2-Dichloroethene	ND	0.0181		mg/Kg-dry	1	8/10/2017 8:55:05 PM
Methyl tert-butyl ether (MTBE)	ND	0.0451		mg/Kg-dry	1	8/10/2017 8:55:05 PM
1,1-Dichloroethane	ND	0.0181		mg/Kg-dry	1	8/10/2017 8:55:05 PM
2,2-Dichloropropane	ND	0.0903		mg/Kg-dry	1	8/10/2017 8:55:05 PM
cis-1,2-Dichloroethene	ND	0.0181		mg/Kg-dry	1	8/10/2017 8:55:05 PM
Chloroform	ND	0.0181		mg/Kg-dry	1	8/10/2017 8:55:05 PM
1,1,1-Trichloroethane (TCA)	ND	0.0226		mg/Kg-dry	1	8/10/2017 8:55:05 PM
1,1-Dichloropropene	ND	0.0181		mg/Kg-dry	1	8/10/2017 8:55:05 PM
Carbon tetrachloride	ND	0.0226		mg/Kg-dry	1	8/10/2017 8:55:05 PM
1,2-Dichloroethane (EDC)	ND	0.0181		mg/Kg-dry	1	8/10/2017 8:55:05 PM
Benzene	ND	0.0181		mg/Kg-dry	1	8/10/2017 8:55:05 PM
Trichloroethene (TCE)	ND	0.0181		mg/Kg-dry	1	8/10/2017 8:55:05 PM
1,2-Dichloropropane	ND	0.0181		mg/Kg-dry	1	8/10/2017 8:55:05 PM
Bromodichloromethane	ND	0.0181		mg/Kg-dry	1	8/10/2017 8:55:05 PM
Dibromomethane	ND	0.0181		mg/Kg-dry	1	8/10/2017 8:55:05 PM
cis-1,3-Dichloropropene	ND	0.0181		mg/Kg-dry	1	8/10/2017 8:55:05 PM
Toluene	ND	0.0181		mg/Kg-dry	1	8/10/2017 8:55:05 PM
trans-1,3-Dichloropropylene	ND	0.0181		mg/Kg-dry	1	8/10/2017 8:55:05 PM
1,1,2-Trichloroethane	ND	0.0181		mg/Kg-dry	1	8/10/2017 8:55:05 PM



Client: Shannon & Wilson

Collection Date: 8/3/2017 5:25:00 AM

Project: Yakima EWC

Lab ID: 1708051-003

Matrix: Soil

Client Sample ID: ES-7

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Volatile Organic Compounds by EPA Method 8260C

Batch ID: 17870

Analyst: NG

1,3-Dichloropropane	ND	0.0226		mg/Kg-dry	1	8/10/2017 8:55:05 PM
Tetrachloroethene (PCE)	ND	0.0226		mg/Kg-dry	1	8/10/2017 8:55:05 PM
Dibromochloromethane	ND	0.0226		mg/Kg-dry	1	8/10/2017 8:55:05 PM
1,2-Dibromoethane (EDB)	ND	0.00451		mg/Kg-dry	1	8/10/2017 8:55:05 PM
Chlorobenzene	ND	0.0226		mg/Kg-dry	1	8/10/2017 8:55:05 PM
1,1,1,2-Tetrachloroethane	ND	0.0226		mg/Kg-dry	1	8/10/2017 8:55:05 PM
Ethylbenzene	ND	0.0226		mg/Kg-dry	1	8/10/2017 8:55:05 PM
m,p-Xylene	ND	0.0451		mg/Kg-dry	1	8/10/2017 8:55:05 PM
o-Xylene	ND	0.0226		mg/Kg-dry	1	8/10/2017 8:55:05 PM
Styrene	ND	0.0226		mg/Kg-dry	1	8/10/2017 8:55:05 PM
Isopropylbenzene	ND	0.0226		mg/Kg-dry	1	8/10/2017 8:55:05 PM
Bromoform	ND	0.0451		mg/Kg-dry	1	8/10/2017 8:55:05 PM
1,1,2,2-Tetrachloroethane	ND	0.0181		mg/Kg-dry	1	8/10/2017 8:55:05 PM
n-Propylbenzene	ND	0.0226		mg/Kg-dry	1	8/10/2017 8:55:05 PM
Bromobenzene	ND	0.0181		mg/Kg-dry	1	8/10/2017 8:55:05 PM
1,3,5-Trimethylbenzene	ND	0.0226		mg/Kg-dry	1	8/10/2017 8:55:05 PM
2-Chlorotoluene	ND	0.0226		mg/Kg-dry	1	8/10/2017 8:55:05 PM
4-Chlorotoluene	ND	0.0226		mg/Kg-dry	1	8/10/2017 8:55:05 PM
tert-Butylbenzene	ND	0.0226		mg/Kg-dry	1	8/10/2017 8:55:05 PM
1,2,3-Trichloropropane	ND	0.0226		mg/Kg-dry	1	8/10/2017 8:55:05 PM
1,2,4-Trichlorobenzene	ND	0.0226		mg/Kg-dry	1	8/10/2017 8:55:05 PM
sec-Butylbenzene	ND	0.0451		mg/Kg-dry	1	8/10/2017 8:55:05 PM
4-Isopropyltoluene	ND	0.0451		mg/Kg-dry	1	8/10/2017 8:55:05 PM
1,3-Dichlorobenzene	ND	0.0181		mg/Kg-dry	1	8/10/2017 8:55:05 PM
1,4-Dichlorobenzene	ND	0.0181		mg/Kg-dry	1	8/10/2017 8:55:05 PM
n-Butylbenzene	ND	0.0226		mg/Kg-dry	1	8/10/2017 8:55:05 PM
1,2-Dichlorobenzene	ND	0.0181		mg/Kg-dry	1	8/10/2017 8:55:05 PM
1,2-Dibromo-3-chloropropane	ND	0.451		mg/Kg-dry	1	8/10/2017 8:55:05 PM
1,2,4-Trimethylbenzene	ND	0.0181		mg/Kg-dry	1	8/10/2017 8:55:05 PM
Hexachlorobutadiene	ND	0.0451		mg/Kg-dry	1	8/10/2017 8:55:05 PM
Naphthalene	ND	0.0451		mg/Kg-dry	1	8/10/2017 8:55:05 PM
1,2,3-Trichlorobenzene	ND	0.0181		mg/Kg-dry	1	8/10/2017 8:55:05 PM
Surr: Dibromofluoromethane	94.6	56.5 - 129		%Rec	1	8/10/2017 8:55:05 PM
Surr: Toluene-d8	101	64.5 - 151		%Rec	1	8/10/2017 8:55:05 PM
Surr: 1-Bromo-4-fluorobenzene	106	63.1 - 141		%Rec	1	8/10/2017 8:55:05 PM

Mercury by EPA Method 7471

Batch ID: 17871

Analyst: WF

Mercury	ND	0.253		mg/Kg-dry	1	8/10/2017 5:02:04 PM
---------	----	-------	--	-----------	---	----------------------



Client: Shannon & Wilson

Collection Date: 8/3/2017 5:25:00 AM

Project: Yakima EWC

Lab ID: 1708051-003

Matrix: Soil

Client Sample ID: ES-7

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Total Metals by EPA Method 6020

Batch ID: 17834 Analyst: TN

Arsenic	2.07	0.0852		mg/Kg-dry	1	8/9/2017 1:00:43 PM
Barium	54.2	0.426		mg/Kg-dry	1	8/9/2017 1:00:43 PM
Cadmium	ND	0.170		mg/Kg-dry	1	8/9/2017 1:00:43 PM
Chromium	23.0	0.0852		mg/Kg-dry	1	8/9/2017 1:00:43 PM
Copper	14.7	0.170		mg/Kg-dry	1	8/9/2017 1:00:43 PM
Lead	2.65	0.170		mg/Kg-dry	1	8/9/2017 1:00:43 PM
Nickel	25.0	0.0852		mg/Kg-dry	1	8/9/2017 1:00:43 PM
Selenium	1.63	0.426		mg/Kg-dry	1	8/9/2017 1:00:43 PM
Silver	ND	0.0801		mg/Kg-dry	1	8/10/2017 2:43:39 PM
Zinc	43.7	0.341		mg/Kg-dry	1	8/9/2017 1:00:43 PM

Sample Moisture (Percent Moisture)

Batch ID: R37834 Analyst: BB

Percent Moisture	6.88			wt%	1	8/7/2017 9:08:52 AM
------------------	------	--	--	-----	---	---------------------



Client: Shannon & Wilson

Collection Date: 8/3/2017 7:47:00 AM

Project: Yakima EWC

Lab ID: 1708051-004

Matrix: Soil

Client Sample ID: ES-8

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Polychlorinated Biphenyls (PCB) by EPA 8082

Batch ID: 17833

Analyst: SG

Aroclor 1016	ND	0.118		mg/Kg-dry	1	8/7/2017 2:20:07 PM
Aroclor 1221	ND	0.118		mg/Kg-dry	1	8/7/2017 2:20:07 PM
Aroclor 1232	ND	0.118		mg/Kg-dry	1	8/7/2017 2:20:07 PM
Aroclor 1242	ND	0.118		mg/Kg-dry	1	8/7/2017 2:20:07 PM
Aroclor 1248	ND	0.118		mg/Kg-dry	1	8/7/2017 2:20:07 PM
Aroclor 1254	ND	0.118		mg/Kg-dry	1	8/7/2017 2:20:07 PM
Aroclor 1260	ND	0.118		mg/Kg-dry	1	8/7/2017 2:20:07 PM
Aroclor 1262	ND	0.118		mg/Kg-dry	1	8/7/2017 2:20:07 PM
Aroclor 1268	ND	0.118		mg/Kg-dry	1	8/7/2017 2:20:07 PM
Total PCBs	ND	0.118		mg/Kg-dry	1	8/7/2017 2:20:07 PM
Surr: Decachlorobiphenyl	125	30.8 - 168		%Rec	1	8/7/2017 2:20:07 PM
Surr: Tetrachloro-m-xylene	109	30.3 - 157		%Rec	1	8/7/2017 2:20:07 PM

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Batch ID: 17836

Analyst: SB

Diesel (Fuel Oil)	ND	20.4		mg/Kg-dry	1	8/7/2017 10:06:35 PM
Heavy Oil	ND	51.0		mg/Kg-dry	1	8/7/2017 10:06:35 PM
Surr: 2-Fluorobiphenyl	91.8	50 - 150		%Rec	1	8/7/2017 10:06:35 PM
Surr: o-Terphenyl	91.5	50 - 150		%Rec	1	8/7/2017 10:06:35 PM

Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Batch ID: 17832

Analyst: BT

Naphthalene	ND	45.5		µg/Kg-dry	1	8/7/2017 4:09:57 PM
2-Methylnaphthalene	ND	45.5		µg/Kg-dry	1	8/7/2017 4:09:57 PM
1-Methylnaphthalene	ND	45.5		µg/Kg-dry	1	8/7/2017 4:09:57 PM
Acenaphthylene	ND	45.5		µg/Kg-dry	1	8/7/2017 4:09:57 PM
Acenaphthene	ND	45.5		µg/Kg-dry	1	8/7/2017 4:09:57 PM
Fluorene	ND	45.5		µg/Kg-dry	1	8/7/2017 4:09:57 PM
Phenanthrene	ND	45.5		µg/Kg-dry	1	8/7/2017 4:09:57 PM
Anthracene	ND	45.5		µg/Kg-dry	1	8/7/2017 4:09:57 PM
Fluoranthene	ND	45.5		µg/Kg-dry	1	8/7/2017 4:09:57 PM
Pyrene	ND	45.5		µg/Kg-dry	1	8/7/2017 4:09:57 PM
Benz(a)anthracene	ND	45.5		µg/Kg-dry	1	8/7/2017 4:09:57 PM
Chrysene	ND	45.5		µg/Kg-dry	1	8/7/2017 4:09:57 PM
Benzo(b)fluoranthene	ND	45.5		µg/Kg-dry	1	8/7/2017 4:09:57 PM
Benzo(j,k)fluoranthene	ND	45.5		µg/Kg-dry	1	8/7/2017 4:09:57 PM
Benzo(a)pyrene	ND	45.5		µg/Kg-dry	1	8/7/2017 4:09:57 PM
Indeno(1,2,3-cd)pyrene	ND	45.5		µg/Kg-dry	1	8/7/2017 4:09:57 PM
Dibenz(a,h)anthracene	ND	45.5		µg/Kg-dry	1	8/7/2017 4:09:57 PM



Client: Shannon & Wilson

Collection Date: 8/3/2017 7:47:00 AM

Project: Yakima EWC

Lab ID: 1708051-004

Matrix: Soil

Client Sample ID: ES-8

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Batch ID: 17832 Analyst: BT

Benzo(g,h,i)perylene	ND	45.5		µg/Kg-dry	1	8/7/2017 4:09:57 PM
Surr: 2-Fluorobiphenyl	65.0	24.5 - 139		%Rec	1	8/7/2017 4:09:57 PM
Surr: Terphenyl-d14 (surr)	109	46.2 - 179		%Rec	1	8/7/2017 4:09:57 PM

Gasoline by NWTPH-Gx

Batch ID: 17870 Analyst: NG

Gasoline	ND	4.66		mg/Kg-dry	1	8/10/2017 9:25:02 PM
Surr: Toluene-d8	96.1	65 - 135		%Rec	1	8/10/2017 9:25:02 PM
Surr: 4-Bromofluorobenzene	104	65 - 135		%Rec	1	8/10/2017 9:25:02 PM

Volatile Organic Compounds by EPA Method 8260C

Batch ID: 17870 Analyst: NG

Dichlorodifluoromethane (CFC-12)	ND	0.0186		mg/Kg-dry	1	8/10/2017 9:25:02 PM
Chloromethane	ND	0.0466		mg/Kg-dry	1	8/10/2017 9:25:02 PM
Vinyl chloride	ND	0.0233		mg/Kg-dry	1	8/10/2017 9:25:02 PM
Bromomethane	ND	0.0466		mg/Kg-dry	1	8/10/2017 9:25:02 PM
Trichlorofluoromethane (CFC-11)	ND	0.0186		mg/Kg-dry	1	8/10/2017 9:25:02 PM
Chloroethane	ND	0.0466		mg/Kg-dry	1	8/10/2017 9:25:02 PM
1,1-Dichloroethene	ND	0.0186		mg/Kg-dry	1	8/10/2017 9:25:02 PM
Methylene chloride	ND	0.0186		mg/Kg-dry	1	8/10/2017 9:25:02 PM
trans-1,2-Dichloroethene	ND	0.0186		mg/Kg-dry	1	8/10/2017 9:25:02 PM
Methyl tert-butyl ether (MTBE)	ND	0.0466		mg/Kg-dry	1	8/10/2017 9:25:02 PM
1,1-Dichloroethane	ND	0.0186		mg/Kg-dry	1	8/10/2017 9:25:02 PM
2,2-Dichloropropane	ND	0.0931		mg/Kg-dry	1	8/10/2017 9:25:02 PM
cis-1,2-Dichloroethene	ND	0.0186		mg/Kg-dry	1	8/10/2017 9:25:02 PM
Chloroform	ND	0.0186		mg/Kg-dry	1	8/10/2017 9:25:02 PM
1,1,1-Trichloroethane (TCA)	ND	0.0233		mg/Kg-dry	1	8/10/2017 9:25:02 PM
1,1-Dichloropropene	ND	0.0186		mg/Kg-dry	1	8/10/2017 9:25:02 PM
Carbon tetrachloride	ND	0.0233		mg/Kg-dry	1	8/10/2017 9:25:02 PM
1,2-Dichloroethane (EDC)	ND	0.0186		mg/Kg-dry	1	8/10/2017 9:25:02 PM
Benzene	ND	0.0186		mg/Kg-dry	1	8/10/2017 9:25:02 PM
Trichloroethene (TCE)	ND	0.0186		mg/Kg-dry	1	8/10/2017 9:25:02 PM
1,2-Dichloropropane	ND	0.0186		mg/Kg-dry	1	8/10/2017 9:25:02 PM
Bromodichloromethane	ND	0.0186		mg/Kg-dry	1	8/10/2017 9:25:02 PM
Dibromomethane	ND	0.0186		mg/Kg-dry	1	8/10/2017 9:25:02 PM
cis-1,3-Dichloropropene	ND	0.0186		mg/Kg-dry	1	8/10/2017 9:25:02 PM
Toluene	ND	0.0186		mg/Kg-dry	1	8/10/2017 9:25:02 PM
trans-1,3-Dichloropropylene	ND	0.0186		mg/Kg-dry	1	8/10/2017 9:25:02 PM
1,1,2-Trichloroethane	ND	0.0186		mg/Kg-dry	1	8/10/2017 9:25:02 PM



Analytical Report

Work Order: 1708051
Date Reported: 8/14/2017

Client: Shannon & Wilson

Collection Date: 8/3/2017 7:47:00 AM

Project: Yakima EWC

Lab ID: 1708051-004

Matrix: Soil

Client Sample ID: ES-8

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Volatile Organic Compounds by EPA Method 8260C

Batch ID: 17870

Analyst: NG

1,3-Dichloropropane	ND	0.0233		mg/Kg-dry	1	8/10/2017 9:25:02 PM
Tetrachloroethene (PCE)	ND	0.0233		mg/Kg-dry	1	8/10/2017 9:25:02 PM
Dibromochloromethane	ND	0.0233		mg/Kg-dry	1	8/10/2017 9:25:02 PM
1,2-Dibromoethane (EDB)	ND	0.00466		mg/Kg-dry	1	8/10/2017 9:25:02 PM
Chlorobenzene	ND	0.0233		mg/Kg-dry	1	8/10/2017 9:25:02 PM
1,1,1,2-Tetrachloroethane	ND	0.0233		mg/Kg-dry	1	8/10/2017 9:25:02 PM
Ethylbenzene	ND	0.0233		mg/Kg-dry	1	8/10/2017 9:25:02 PM
m,p-Xylene	ND	0.0466		mg/Kg-dry	1	8/10/2017 9:25:02 PM
o-Xylene	ND	0.0233		mg/Kg-dry	1	8/10/2017 9:25:02 PM
Styrene	ND	0.0233		mg/Kg-dry	1	8/10/2017 9:25:02 PM
Isopropylbenzene	ND	0.0233		mg/Kg-dry	1	8/10/2017 9:25:02 PM
Bromoform	ND	0.0466		mg/Kg-dry	1	8/10/2017 9:25:02 PM
1,1,2,2-Tetrachloroethane	ND	0.0186		mg/Kg-dry	1	8/10/2017 9:25:02 PM
n-Propylbenzene	ND	0.0233		mg/Kg-dry	1	8/10/2017 9:25:02 PM
Bromobenzene	ND	0.0186		mg/Kg-dry	1	8/10/2017 9:25:02 PM
1,3,5-Trimethylbenzene	ND	0.0233		mg/Kg-dry	1	8/10/2017 9:25:02 PM
2-Chlorotoluene	ND	0.0233		mg/Kg-dry	1	8/10/2017 9:25:02 PM
4-Chlorotoluene	ND	0.0233		mg/Kg-dry	1	8/10/2017 9:25:02 PM
tert-Butylbenzene	ND	0.0233		mg/Kg-dry	1	8/10/2017 9:25:02 PM
1,2,3-Trichloropropane	ND	0.0233		mg/Kg-dry	1	8/10/2017 9:25:02 PM
1,2,4-Trichlorobenzene	ND	0.0233		mg/Kg-dry	1	8/10/2017 9:25:02 PM
sec-Butylbenzene	ND	0.0466		mg/Kg-dry	1	8/10/2017 9:25:02 PM
4-Isopropyltoluene	ND	0.0466		mg/Kg-dry	1	8/10/2017 9:25:02 PM
1,3-Dichlorobenzene	ND	0.0186		mg/Kg-dry	1	8/10/2017 9:25:02 PM
1,4-Dichlorobenzene	ND	0.0186		mg/Kg-dry	1	8/10/2017 9:25:02 PM
n-Butylbenzene	ND	0.0233		mg/Kg-dry	1	8/10/2017 9:25:02 PM
1,2-Dichlorobenzene	ND	0.0186		mg/Kg-dry	1	8/10/2017 9:25:02 PM
1,2-Dibromo-3-chloropropane	ND	0.466		mg/Kg-dry	1	8/10/2017 9:25:02 PM
1,2,4-Trimethylbenzene	ND	0.0186		mg/Kg-dry	1	8/10/2017 9:25:02 PM
Hexachlorobutadiene	ND	0.0466		mg/Kg-dry	1	8/10/2017 9:25:02 PM
Naphthalene	ND	0.0466		mg/Kg-dry	1	8/10/2017 9:25:02 PM
1,2,3-Trichlorobenzene	ND	0.0186		mg/Kg-dry	1	8/10/2017 9:25:02 PM
Surr: Dibromofluoromethane	93.3	56.5 - 129		%Rec	1	8/10/2017 9:25:02 PM
Surr: Toluene-d8	99.6	64.5 - 151		%Rec	1	8/10/2017 9:25:02 PM
Surr: 1-Bromo-4-fluorobenzene	104	63.1 - 141		%Rec	1	8/10/2017 9:25:02 PM

Mercury by EPA Method 7471

Batch ID: 17871

Analyst: WF

Mercury	ND	0.288		mg/Kg-dry	1	8/10/2017 5:03:41 PM
---------	----	-------	--	-----------	---	----------------------



Client: Shannon & Wilson

Collection Date: 8/3/2017 7:47:00 AM

Project: Yakima EWC

Lab ID: 1708051-004

Matrix: Soil

Client Sample ID: ES-8

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Total Metals by EPA Method 6020

Batch ID: 17834 Analyst: TN

Arsenic	2.10	0.0862		mg/Kg-dry	1	8/9/2017 1:04:44 PM
Barium	63.6	0.431		mg/Kg-dry	1	8/9/2017 1:04:44 PM
Cadmium	ND	0.172		mg/Kg-dry	1	8/9/2017 1:04:44 PM
Chromium	23.2	0.0862		mg/Kg-dry	1	8/9/2017 1:04:44 PM
Copper	18.7	0.172		mg/Kg-dry	1	8/9/2017 1:04:44 PM
Lead	2.29	0.172		mg/Kg-dry	1	8/9/2017 1:04:44 PM
Nickel	19.5	0.0862		mg/Kg-dry	1	8/9/2017 1:04:44 PM
Selenium	1.53	0.431		mg/Kg-dry	1	8/9/2017 1:04:44 PM
Silver	ND	0.0936		mg/Kg-dry	1	8/10/2017 2:47:40 PM
Zinc	42.2	0.345		mg/Kg-dry	1	8/9/2017 1:04:44 PM

Sample Moisture (Percent Moisture)

Batch ID: R37834 Analyst: BB

Percent Moisture	16.5			wt%	1	8/7/2017 9:08:52 AM
------------------	------	--	--	-----	---	---------------------

Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Sample ID MB-17836	SampType: MBLK	Units: mg/Kg				Prep Date: 8/7/2017	RunNo: 37852				
Client ID: MBLKS	Batch ID: 17836					Analysis Date: 8/7/2017	SeqNo: 727403				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	ND	20.0									
Heavy Oil	ND	50.0									
Surr: 2-Fluorobiphenyl	16.1		20.00		80.7	50	150				
Surr: o-Terphenyl	16.2		20.00		81.0	50	150				

Sample ID LCS-17836	SampType: LCS	Units: mg/Kg				Prep Date: 8/7/2017	RunNo: 37852				
Client ID: LCSS	Batch ID: 17836					Analysis Date: 8/7/2017	SeqNo: 727404				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	523	20.0	500.0	0	105	65	135				
Surr: 2-Fluorobiphenyl	16.9		20.00		84.4	50	150				
Surr: o-Terphenyl	18.6		20.00		92.9	50	150				

Sample ID 1708059-001ADUP	SampType: DUP	Units: mg/Kg-dry				Prep Date: 8/7/2017	RunNo: 37852				
Client ID: BATCH	Batch ID: 17836					Analysis Date: 8/7/2017	SeqNo: 727422				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	ND	21.1						0		30	
Heavy Oil	ND	52.8						0		30	
Surr: 2-Fluorobiphenyl	17.8		21.13		84.1	50	150		0		
Surr: o-Terphenyl	17.8		21.13		84.3	50	150		0		

Sample ID 1708059-001AMS	SampType: MS	Units: mg/Kg-dry				Prep Date: 8/7/2017	RunNo: 37852				
Client ID: BATCH	Batch ID: 17836					Analysis Date: 8/7/2017	SeqNo: 727423				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	541	20.3	508.3	0	106	65	135				
Surr: 2-Fluorobiphenyl	18.4		20.33		90.3	50	150				
Surr: o-Terphenyl	19.8		20.33		97.3	50	150				

Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Sample ID 1708059-001AMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 8/7/2017	RunNo: 37852							
Client ID: BATCH	Batch ID: 17836	Analysis Date: 8/7/2017	SeqNo: 727423								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Sample ID 1708059-001AMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 8/7/2017	RunNo: 37852							
Client ID: BATCH	Batch ID: 17836	Analysis Date: 8/7/2017	SeqNo: 727424								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	470	19.9	497.5	0	94.5	65	135	540.9	13.9	30	
Surr: 2-Fluorobiphenyl	16.1		19.90		80.7	50	150		0		
Surr: o-Terphenyl	17.5		19.90		88.0	50	150		0		

Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Sample ID MB-17826	SampType: MBLK	Units: mg/Kg				Prep Date: 8/4/2017	RunNo: 37842				
Client ID: MBLKS	Batch ID: 17826					Analysis Date: 8/4/2017	SeqNo: 727254				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	ND	20.0									
Heavy Oil	ND	50.0									
Surr: 2-Fluorobiphenyl	18.4		20.00		92.0	50	150				
Surr: o-Terphenyl	20.8		20.00		104	50	150				

Sample ID LCS-17826	SampType: LCS	Units: mg/Kg				Prep Date: 8/4/2017	RunNo: 37842				
Client ID: LCSS	Batch ID: 17826					Analysis Date: 8/4/2017	SeqNo: 727253				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	467	20.0	500.0	0	93.4	65	135				
Surr: 2-Fluorobiphenyl	20.3		20.00		102	50	150				
Surr: o-Terphenyl	24.1		20.00		120	50	150				

Sample ID 1708048-001ADUP	SampType: DUP	Units: mg/Kg-dry				Prep Date: 8/4/2017	RunNo: 37842				
Client ID: BATCH	Batch ID: 17826					Analysis Date: 8/4/2017	SeqNo: 727242				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	ND	24.9						0		30	
Heavy Oil	ND	62.4						0		30	
Heavy Oil Range Organics (C24-37)	68.1	62.4						71.68	5.14	30	
Surr: 2-Fluorobiphenyl	25.1		24.94		101	50	150		0		
Surr: o-Terphenyl	26.7		24.94		107	50	150		0		

NOTES:
Heavy Oil Range Organics - Indicates the presence of unresolved compounds in the Lube+ Oil ranges.

Sample ID 1708048-001AMS	SampType: MS	Units: mg/Kg-dry				Prep Date: 8/4/2017	RunNo: 37842				
Client ID: BATCH	Batch ID: 17826					Analysis Date: 8/4/2017	SeqNo: 727243				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	455	23.4	585.2	0	77.8	65	135				

Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Sample ID 1708048-001AMS	SampType: MS	Units: mg/Kg-dry		Prep Date: 8/4/2017	RunNo: 37842						
Client ID: BATCH	Batch ID: 17826			Analysis Date: 8/4/2017	SeqNo: 727243						
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Surr: 2-Fluorobiphenyl	15.4		23.41	65.8	50	150
Surr: o-Terphenyl	18.3		23.41	78.2	50	150

Sample ID 1708048-001AMSD	SampType: MSD	Units: mg/Kg-dry		Prep Date: 8/4/2017	RunNo: 37842						
Client ID: BATCH	Batch ID: 17826			Analysis Date: 8/4/2017	SeqNo: 727244						
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Diesel (Fuel Oil)	601	24.5	613.5	0	98.0	65	135	455.4	27.6	30
Surr: 2-Fluorobiphenyl	24.7		24.54		101	50	150		0	
Surr: o-Terphenyl	28.1		24.54		115	50	150		0	

Work Order: 1708051
 CLIENT: Shannon & Wilson
 Project: Yakima EWC

QC SUMMARY REPORT
Gasoline by NWTPH-Gx

Sample ID LCS-17870	SampType: LCS	Units: mg/Kg				Prep Date: 8/10/2017	RunNo: 37922				
Client ID: LCSS	Batch ID: 17870					Analysis Date: 8/10/2017	SeqNo: 728550				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	27.8	5.00	25.00	0	111	65	135				
Surr: Toluene-d8	1.30		1.250		104	65	135				
Surr: 4-Bromofluorobenzene	1.26		1.250		101	65	135				

Sample ID MB-17870	SampType: MBLK	Units: mg/Kg				Prep Date: 8/10/2017	RunNo: 37922				
Client ID: MBLKS	Batch ID: 17870					Analysis Date: 8/10/2017	SeqNo: 728551				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	ND	5.00									
Surr: Toluene-d8	1.20		1.250		96.0	65	135				
Surr: 4-Bromofluorobenzene	1.31		1.250		105	65	135				

Sample ID 1708101-002BDUP	SampType: DUP	Units: mg/Kg-dry				Prep Date: 8/10/2017	RunNo: 37922				
Client ID: BATCH	Batch ID: 17870					Analysis Date: 8/10/2017	SeqNo: 729040				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	ND	6.06						0		30	
Surr: Toluene-d8	1.46		1.516		96.6	65	135		0		
Surr: 4-Bromofluorobenzene	1.59		1.516		105	65	135		0		

Sample ID 1708101-003BMS	SampType: MS	Units: mg/Kg-dry				Prep Date: 8/10/2017	RunNo: 37922				
Client ID: BATCH	Batch ID: 17870					Analysis Date: 8/10/2017	SeqNo: 729041				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	20.8	5.56	27.81	0	74.6	65	135				
Surr: Toluene-d8	1.35		1.390		96.7	65	135				
Surr: 4-Bromofluorobenzene	1.48		1.390		107	65	135				

Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Gasoline by NWTPH-Gx

Sample ID 1708101-003BMSD	SampType: MSD	Units: mg/Kg-dry		Prep Date: 8/10/2017	RunNo: 37922						
Client ID: BATCH	Batch ID: 17870			Analysis Date: 8/10/2017	SeqNo: 729042						
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	21.9	5.56	27.81	0	78.6	65	135	20.76	5.19	30	
Surr: Toluene-d8	1.34		1.390		96.4	65	135		0		
Surr: 4-Bromofluorobenzene	1.50		1.390		108	65	135		0		

Sample ID 1708084-005BDUP	SampType: DUP	Units: mg/Kg-dry		Prep Date: 8/10/2017	RunNo: 37922						
Client ID: BATCH	Batch ID: 17870			Analysis Date: 8/10/2017	SeqNo: 729039						
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	ND	2.13						0		30	
Surr: Toluene-d8	0.527		0.5320		99.1	65	135		0		
Surr: 4-Bromofluorobenzene	0.551		0.5320		104	65	135		0		



Date: 8/14/2017

Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Herbicides by EPA Method 8151A

Sample ID MB-17825	SampType: MBLK	Units: µg/Kg	Prep Date: 8/4/2017	RunNo: 37948							
Client ID: MBLKS	Batch ID: 17825		Analysis Date: 8/9/2017	SeqNo: 729321							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Dicamba	ND	35.0									
2,4-D	ND	30.0									
2,4-DP	ND	25.0									
2,4,5-TP (Silvex)	ND	20.0									
2,4,5-T	ND	50.0									
Dinoseb	ND	30.0									
Dalapon	ND	200									
2,4-DB	ND	25.0									
MCPP	ND	4,400									
MCPA	ND	2,800									
Picloram	ND	50.0									
Bentazon	ND	35.0									
Chloramben	ND	20.0									
Acifluorfen	ND	80.0									
3,5-Dichlorobenzoic acid	ND	40.0									
4-Nitrophenol	ND	30.0									
Dacthal (DCPA)	ND	30.0									
Surr: 2,4-Dichlorophenylacetic acid	716		1,000		71.6	20.1	168				

Sample ID LCS-17825	SampType: LCS	Units: µg/Kg	Prep Date: 8/4/2017	RunNo: 37948							
Client ID: LCSS	Batch ID: 17825		Analysis Date: 8/9/2017	SeqNo: 729322							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Dicamba	160	35.0	200.0	0	80.2	24.7	141				
2,4-D	179	30.0	200.0	0	89.6	22.4	130				
2,4-DP	166	25.0	200.0	0	83.2	26.4	130				
2,4,5-TP (Silvex)	180	20.0	200.0	0	90.0	21.2	138				
2,4,5-T	165	50.0	200.0	0	82.6	22.8	144				
Dinoseb	140	30.0	200.0	0	69.8	5	165				
Dalapon	930	200	1,000	0	93.0	18.4	162				



Date: 8/14/2017

Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Herbicides by EPA Method 8151A

Sample ID	LCS-17825	SampType:	LCS	Units:	µg/Kg	Prep Date:	8/4/2017	RunNo:	37948		
Client ID:	LCSS	Batch ID:	17825	Analysis Date:	8/9/2017	SeqNo:	729322				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
2,4-DB	190	25.0	200.0	0	94.8	5	164				
MCPP	826	4,400	1,000	0	82.6	22.2	157				
MCPA	883	2,800	1,000	0	88.3	47.4	128				
Picloram	171	50.0	200.0	0	85.7	5	175				
Bentazon	122	35.0	200.0	0	61.0	7.59	162				
Chloramben	64.5	20.0	200.0	0	32.3	5	147				
Acifluorfen	196	80.0	200.0	0	97.9	5	163				
3,5-Dichlorobenzoic acid	160	40.0	200.0	0	79.9	18.7	139				
4-Nitrophenol	146	30.0	200.0	0	73.0	5	163				
Dacthal (DCPA)	120	30.0	200.0	0	60.2	5	164				
Surr: 2,4-Dichlorophenylacetic acid	786		1,000		78.6	20.1	168				

Sample ID	1707301-001ADUP	SampType:	DUP	Units:	µg/Kg-dry	Prep Date:	8/4/2017	RunNo:	37948		
Client ID:	BATCH	Batch ID:	17825	Analysis Date:	8/10/2017	SeqNo:	729336				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Dicamba	ND	32.6						0		30	
2,4-D	ND	27.9						0		30	
2,4-DP	ND	23.3						0		30	
2,4,5-TP (Silvex)	ND	18.6						0		30	
2,4,5-T	ND	46.5						0		30	
Dinoseb	ND	27.9						0		30	
Dalapon	ND	186						0		30	
2,4-DB	ND	23.3						0		30	
MCPP	ND	4,090						0		30	
MCPA	ND	2,610						0		30	
Picloram	ND	46.5						0		30	
Bentazon	ND	32.6						0		30	
Chloramben	ND	18.6						0		30	
Acifluorfen	ND	74.5						0		30	

Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Herbicides by EPA Method 8151A

Sample ID 1707301-001ADUP	SampType: DUP	Units: µg/Kg-dry	Prep Date: 8/4/2017	RunNo: 37948							
Client ID: BATCH	Batch ID: 17825		Analysis Date: 8/10/2017	SeqNo: 729336							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

3,5-Dichlorobenzoic acid	ND	37.2						0		30	
4-Nitrophenol	ND	27.9						0		30	
Dacthal (DCPA)	ND	27.9						0		30	
Surr: 2,4-Dichlorophenylacetic acid	451		930.7		48.4	20.1	168		0		

Sample ID 1707301-001AMS	SampType: MS	Units: µg/Kg-dry	Prep Date: 8/4/2017	RunNo: 37948							
Client ID: BATCH	Batch ID: 17825		Analysis Date: 8/10/2017	SeqNo: 729337							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Dicamba	154	35.7	204.3	0	75.6	31.9	118				
2,4-D	173	30.6	204.3	0	84.8	12.4	134				
2,4-DP	164	25.5	204.3	0	80.2	27.2	129				
2,4,5-TP (Silvex)	178	20.4	204.3	0	87.3	28.6	134				
2,4,5-T	153	51.1	204.3	0	74.7	13.1	147				
Dinoseb	208	30.6	204.3	0	102	10	179				
Dalapon	865	204	1,021	0	84.7	24.9	139				
2,4-DB	191	25.5	204.3	0	93.6	50.2	152				
MCPP	795	4,490	1,021	0	77.8	37.8	140				
MCPA	867	2,860	1,021	0	84.9	13.7	147				
Picloram	309	51.1	204.3	0	151	5	153				
Bentazon	153	35.7	204.3	0	75.1	15	140				
Chloramben	126	20.4	204.3	0	61.6	5	162				
Acifluorfen	251	81.7	204.3	0	123	15	140				
3,5-Dichlorobenzoic acid	157	40.9	204.3	0	77.0	10	164				
4-Nitrophenol	52.9	30.6	204.3	0	25.9	44.8	125				S
Dacthal (DCPA)	133	30.6	204.3	0	64.9	5	132				
Surr: 2,4-Dichlorophenylacetic acid	735		1,021		72.0	20.1	168				

NOTES:

S - Outlying spike recovery(ies) observed. A duplicate analysis was performed with similar results indicating a possible matrix effect.

Work Order: 1708051
 CLIENT: Shannon & Wilson
 Project: Yakima EWC

QC SUMMARY REPORT
Herbicides by EPA Method 8151A

Sample ID 1707301-001AMSD	SampType: MSD	Units: µg/Kg-dry	Prep Date: 8/4/2017	RunNo: 37948
Client ID: BATCH	Batch ID: 17825	Analysis Date: 8/10/2017	SeqNo: 729338	

Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Dicamba	142	34.5	196.9	0	72.1	31.9	118	154.3	8.30	30	
2,4-D	161	29.5	196.9	0	81.6	12.4	134	173.1	7.42	30	
2,4-DP	146	24.6	196.9	0	73.9	27.2	129	163.8	11.8	30	
2,4,5-TP (Silvex)	159	19.7	196.9	0	81.0	28.6	134	178.3	11.1	30	
2,4,5-T	166	49.2	196.9	0	84.5	13.1	147	152.6	8.60	30	
Dinoseb	187	29.5	196.9	0	95.1	10	179	207.6	10.3	30	
Dalapon	875	197	984.5	0	88.9	24.9	139	864.6	1.18	30	
2,4-DB	175	24.6	196.9	0	88.9	50.2	152	191.3	8.80	30	
MCPP	789	4,330	984.5	0	80.1	37.8	140	0		30	
MCPA	867	2,760	984.5	0	88.0	13.7	147	0		30	
Picloram	270	49.2	196.9	0	137	5	153	308.9	13.5	30	
Bentazon	133	34.5	196.9	0	67.5	15	140	153.4	14.4	30	
Chloramben	81.5	19.7	196.9	0	41.4	5	162	125.8	42.7	30	R
Acifluorfen	200	78.8	196.9	0	102	15	140	251.4	22.8	30	
3,5-Dichlorobenzoic acid	146	39.4	196.9	0	74.0	10	164	157.3	7.61	30	
4-Nitrophenol	55.9	29.5	196.9	0	28.4	44.8	125	52.91	5.56	30	S
Dacthal (DCPA)	114	29.5	196.9	0	58.1	5	132	132.5	14.7	30	
Surr: 2,4-Dichlorophenylacetic acid	691		984.5		70.2	20.1	168		0		

NOTES:

S - Outlying spike recovery(ies) observed. A duplicate analysis was performed with similar results indicating a possible matrix effect.
 R - High RPD observed, spike recovery is within range.

Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Mercury by EPA Method 7471

Sample ID MB-17871	SampType: MBLK	Units: mg/Kg			Prep Date: 8/10/2017	RunNo: 37934					
Client ID: MBLKS	Batch ID: 17871				Analysis Date: 8/10/2017	SeqNo: 728823					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury ND 0.250

Sample ID LCS-17871	SampType: LCS	Units: mg/Kg			Prep Date: 8/10/2017	RunNo: 37934					
Client ID: LCSS	Batch ID: 17871				Analysis Date: 8/10/2017	SeqNo: 728824					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.495 0.245 0.4902 0 101 80 120

Sample ID 1708101-001ADUP	SampType: DUP	Units: mg/Kg-dry			Prep Date: 8/10/2017	RunNo: 37934					
Client ID: BATCH	Batch ID: 17871				Analysis Date: 8/10/2017	SeqNo: 728826					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury ND 0.265 0 20

Sample ID 1708101-001AMS	SampType: MS	Units: mg/Kg-dry			Prep Date: 8/10/2017	RunNo: 37934					
Client ID: BATCH	Batch ID: 17871				Analysis Date: 8/10/2017	SeqNo: 728827					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.579 0.281 0.5619 0.03752 96.3 70 130

Sample ID 1708101-001AMSD	SampType: MSD	Units: mg/Kg-dry			Prep Date: 8/10/2017	RunNo: 37934					
Client ID: BATCH	Batch ID: 17871				Analysis Date: 8/10/2017	SeqNo: 728828					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.562 0.270 0.5407 0.03752 97.1 70 130 0.5788 2.88 20

Work Order: 1708051
 CLIENT: Shannon & Wilson
 Project: Yakima EWC

QC SUMMARY REPORT
Organochlorine Pesticides by EPA Method 8081

Sample ID TOX CCV A 17824	SampType: CCV	Units: mg/L	Prep Date: 8/7/2017	RunNo: 37836							
Client ID: CCV	Batch ID: 17824		Analysis Date: 8/7/2017	SeqNo: 727576							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Toxaphene	930	0.100	1,000	0	93.0	80	120				
-----------	-----	-------	-------	---	------	----	-----	--	--	--	--

Sample ID MB-17824	SampType: MBLK	Units: mg/Kg	Prep Date: 8/4/2017	RunNo: 37836							
Client ID: MBLKS	Batch ID: 17824		Analysis Date: 8/7/2017	SeqNo: 727577							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Toxaphene	ND	0.100									
Alpha BHC	ND	0.0100									
Beta BHC	ND	0.0100									
Gamma BHC (Lindane)	ND	0.0100									
Delta BHC	ND	0.0100									
Heptachlor	ND	0.0100									
Aldrin	ND	0.0100									
Heptachlor epoxide	ND	0.0100									
gamma-Chlordane	ND	0.0100									
Endosulfan I	ND	0.0100									
alpha-Chlordane	ND	0.0100									
Dieldrin	ND	0.0100									
4,4'-DDE	ND	0.0100									
Endrin	ND	0.0100									
Endosulfan II	ND	0.0100									
4,4'-DDD	ND	0.0100									
Endrin aldehyde	ND	0.0100									
Endosulfan sulfate	ND	0.0100									
4,4'-DDT	ND	0.0100									
Endrin ketone	ND	0.0100									
Methoxychlor	ND	0.0100									
Surr: Decachlorobiphenyl	0.0480		0.05000		95.9	17.8	157				
Surr: Tetrachloro-m-xylene	0.0469		0.05000		93.9	11	150				

Work Order: 1708051
 CLIENT: Shannon & Wilson
 Project: Yakima EWC

QC SUMMARY REPORT
Organochlorine Pesticides by EPA Method 8081

Sample ID	LCS-17824	SampType:	LCS	Units:	mg/Kg	Prep Date:	8/4/2017	RunNo:	37836		
Client ID:	LCSS	Batch ID:	17824	Analysis Date:	8/7/2017	SeqNo:	727578				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Alpha BHC	0.195	0.0100	0.2000	0	97.7	54.2	139				
Beta BHC	0.183	0.0100	0.2000	0	91.7	56.5	142				
Gamma BHC (Lindane)	0.195	0.0100	0.2000	0	97.5	55.5	142				
Delta BHC	0.193	0.0100	0.2000	0	96.6	47.4	157				
Heptachlor	0.209	0.0100	0.2000	0	105	50.9	153				
Aldrin	0.174	0.0100	0.2000	0	87.0	43.7	147				
Heptachlor epoxide	0.180	0.0100	0.2000	0	90.0	56.2	137				
gamma-Chlordane	0.172	0.0100	0.2000	0	86.1	58.5	136				
Endosulfan I	0.177	0.0100	0.2000	0	88.4	60	132				
alpha-Chlordane	0.173	0.0100	0.2000	0	86.6	46.1	140				
Dieldrin	0.177	0.0100	0.2000	0	88.6	61.2	133				
4,4'-DDE	0.187	0.0100	0.2000	0	93.4	55.4	142				
Endrin	0.181	0.0100	0.2000	0	90.4	56.5	143				
Endosulfan II	0.175	0.0100	0.2000	0	87.7	62	143				
4,4'-DDD	0.177	0.0100	0.2000	0	88.5	53.3	145				
Endrin aldehyde	0.168	0.0100	0.2000	0	83.8	39.5	153				
Endosulfan sulfate	0.181	0.0100	0.2000	0	90.3	53.8	148				
4,4'-DDT	0.208	0.0100	0.2000	0	104	48.2	152				
Endrin ketone	0.189	0.0100	0.2000	0	94.5	28.5	162				
Methoxychlor	0.222	0.0100	0.2000	0	111	34.6	159				
Surr: Decachlorobiphenyl	0.0516		0.05000		103	17.8	157				
Surr: Tetrachloro-m-xylene	0.0524		0.05000		105	11	150				

Sample ID	1707301-001ADUP	SampType:	DUP	Units:	mg/Kg-dry	Prep Date:	8/4/2017	RunNo:	37836		
Client ID:	BATCH	Batch ID:	17824	Analysis Date:	8/7/2017	SeqNo:	727580				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Toxaphene	ND	0.101						0		30	
Alpha BHC	ND	0.0101						0		30	
Beta BHC	ND	0.0101						0		30	

Work Order: 1708051
 CLIENT: Shannon & Wilson
 Project: Yakima EWC

QC SUMMARY REPORT
Organochlorine Pesticides by EPA Method 8081

Sample ID	1707301-001ADUP	SampType:	DUP	Units:	mg/Kg-dry	Prep Date:	8/4/2017	RunNo:	37836		
Client ID:	BATCH	Batch ID:	17824	Analysis Date:	8/7/2017	SeqNo:	727580				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Gamma BHC (Lindane)	ND	0.0101						0		30	
Delta BHC	ND	0.0101						0		30	
Heptachlor	ND	0.0101						0		30	
Aldrin	ND	0.0101						0		30	
Heptachlor epoxide	ND	0.0101						0		30	
gamma-Chlordane	ND	0.0101						0		30	
Endosulfan I	ND	0.0101						0		30	
alpha-Chlordane	ND	0.0101						0		30	
Dieldrin	ND	0.0101						0		30	
4,4'-DDE	ND	0.0101						0		30	
Endrin	ND	0.0101						0		30	
Endosulfan II	ND	0.0101						0		30	
4,4'-DDD	ND	0.0101						0		30	
Endrin aldehyde	ND	0.0101						0		30	
Endosulfan sulfate	ND	0.0101						0		30	
4,4'-DDT	ND	0.0101						0		30	
Endrin ketone	ND	0.0101						0		30	
Methoxychlor	ND	0.0101						0		30	
Surr: Decachlorobiphenyl	0.0471		0.05057		93.2	17.8	157		0		
Surr: Tetrachloro-m-xylene	0.0469		0.05057		92.8	11	150		0		

Sample ID	1707301-001AMS	SampType:	MS	Units:	mg/Kg-dry	Prep Date:	8/4/2017	RunNo:	37836		
Client ID:	BATCH	Batch ID:	17824	Analysis Date:	8/7/2017	SeqNo:	727581				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Alpha BHC	0.135	0.00929	0.1858	0	72.5	49.1	158				
Beta BHC	0.129	0.00929	0.1858	0	69.4	30.1	161				
Gamma BHC (Lindane)	0.136	0.00929	0.1858	0	73.2	40.5	158				
Delta BHC	0.136	0.00929	0.1858	0	73.0	31.5	153				
Heptachlor	0.147	0.00929	0.1858	0	79.0	37.9	156				

Work Order: 1708051
 CLIENT: Shannon & Wilson
 Project: Yakima EWC

QC SUMMARY REPORT
Organochlorine Pesticides by EPA Method 8081

Sample ID	1707301-001AMS	SampType:	MS	Units:	mg/Kg-dry	Prep Date:	8/4/2017	RunNo:	37836		
Client ID:	BATCH	Batch ID:	17824	Analysis Date:	8/7/2017	SeqNo:	727581				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Aldrin	0.121	0.00929	0.1858	0	64.9	41.9	130				
Heptachlor epoxide	0.128	0.00929	0.1858	0	68.9	41	161				
gamma-Chlordane	0.124	0.00929	0.1858	0	66.5	40.9	132				
Endosulfan I	0.126	0.00929	0.1858	0	68.0	44.7	162				
alpha-Chlordane	0.125	0.00929	0.1858	0	67.2	41.4	132				
Dieldrin	0.128	0.00929	0.1858	0	69.0	43.9	155				
4,4'-DDE	0.136	0.00929	0.1858	0	73.1	34	166				
Endrin	0.134	0.00929	0.1858	0	72.1	50.5	166				
Endosulfan II	0.134	0.00929	0.1858	0	72.3	37.9	154				
4,4'-DDD	0.135	0.00929	0.1858	0	72.4	38.9	144				
Endrin aldehyde	0.125	0.00929	0.1858	0	67.5	38.3	156				
Endosulfan sulfate	0.135	0.00929	0.1858	0	72.7	25.2	144				
4,4'-DDT	0.163	0.00929	0.1858	0	87.7	38.4	160				
Endrin ketone	0.148	0.00929	0.1858	0	79.8	40.2	119				
Methoxychlor	0.185	0.00929	0.1858	0	99.5	43.4	178				
Surr: Decachlorobiphenyl	0.0441		0.04645		94.9	17.8	157				
Surr: Tetrachloro-m-xylene	0.0372		0.04645		80.1	11	150				

Sample ID	1707301-001AMSD	SampType:	MSD	Units:	mg/Kg-dry	Prep Date:	8/4/2017	RunNo:	37836		
Client ID:	BATCH	Batch ID:	17824	Analysis Date:	8/7/2017	SeqNo:	727582				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Alpha BHC	0.140	0.00954	0.1907	0	73.3	49.1	158	0.1347	3.73	30	
Beta BHC	0.130	0.00954	0.1907	0	68.1	30.1	161	0.1289	0.700	30	
Gamma BHC (Lindane)	0.140	0.00954	0.1907	0	73.4	40.5	158	0.1360	2.85	30	
Delta BHC	0.135	0.00954	0.1907	0	70.5	31.5	153	0.1357	0.890	30	
Heptachlor	0.153	0.00954	0.1907	0	80.1	37.9	156	0.1468	3.97	30	
Aldrin	0.124	0.00954	0.1907	0	65.2	41.9	130	0.1206	3.10	30	
Heptachlor epoxide	0.130	0.00954	0.1907	0	68.3	41	161	0.1280	1.81	30	
gamma-Chlordane	0.125	0.00954	0.1907	0	65.4	40.9	132	0.1235	0.975	30	

Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Organochlorine Pesticides by EPA Method 8081

Sample ID 1707301-001AMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 8/4/2017	RunNo: 37836
Client ID: BATCH	Batch ID: 17824		Analysis Date: 8/7/2017	SeqNo: 727582

Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Endosulfan I	0.127	0.00954	0.1907	0	66.4	44.7	162	0.1264	0.211	30	
alpha-Chlordane	0.126	0.00954	0.1907	0	66.0	41.4	132	0.1248	0.909	30	
Dieldrin	0.127	0.00954	0.1907	0	66.6	43.9	155	0.1282	0.926	30	
4,4'-DDE	0.135	0.00954	0.1907	0	70.6	34	166	0.1358	0.768	30	
Endrin	0.131	0.00954	0.1907	0	68.5	50.5	166	0.1341	2.50	30	
Endosulfan II	0.126	0.00954	0.1907	0	65.9	37.9	154	0.1344	6.61	30	
4,4'-DDD	0.128	0.00954	0.1907	0	67.2	38.9	144	0.1345	4.88	30	
Endrin aldehyde	0.109	0.00954	0.1907	0	57.1	38.3	156	0.1254	14.1	30	
Endosulfan sulfate	0.122	0.00954	0.1907	0	63.8	25.2	144	0.1351	10.5	30	
4,4'-DDT	0.154	0.00954	0.1907	0	81.0	38.4	160	0.1630	5.34	30	
Endrin ketone	0.133	0.00954	0.1907	0	69.7	40.2	119	0.1483	11.0	30	
Methoxychlor	0.168	0.00954	0.1907	0	88.0	43.4	178	0.1849	9.64	30	
Surr: Decachlorobiphenyl	0.0354		0.04769		74.3	17.8	157		0		
Surr: Tetrachloro-m-xylene	0.0372		0.04769		78.1	11	150		0		

Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Sample ID MB-17832	SampType: MBLK	Units: µg/Kg	Prep Date: 8/7/2017	RunNo: 37845							
Client ID: MBLKS	Batch ID: 17832		Analysis Date: 8/7/2017	SeqNo: 727280							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	ND	40.0									
2-Methylnaphthalene	ND	40.0									
1-Methylnaphthalene	ND	40.0									
Acenaphthylene	ND	40.0									
Acenaphthene	ND	40.0									
Fluorene	ND	40.0									
Phenanthrene	ND	40.0									
Anthracene	ND	40.0									
Fluoranthene	ND	40.0									
Pyrene	ND	40.0									
Benz(a)anthracene	ND	40.0									
Chrysene	ND	40.0									
Benzo(b)fluoranthene	ND	40.0									
Benzo(j,k)fluoranthene	ND	40.0									
Benzo(a)pyrene	ND	40.0									
Indeno(1,2,3-cd)pyrene	ND	40.0									
Dibenz(a,h)anthracene	ND	40.0									
Benzo(g,h,i)perylene	ND	40.0									
Surr: 2-Fluorobiphenyl	446		500.0		89.2	24.5	139				
Surr: Terphenyl-d14 (surr)	563		500.0		113	46.2	179				

Sample ID LCS-17832	SampType: LCS	Units: µg/Kg	Prep Date: 8/7/2017	RunNo: 37845							
Client ID: LCSS	Batch ID: 17832		Analysis Date: 8/7/2017	SeqNo: 727281							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	644	40.0	1,000	0	64.4	46.4	125				
2-Methylnaphthalene	662	40.0	1,000	0	66.2	45.1	135				
1-Methylnaphthalene	654	40.0	1,000	0	65.4	46.2	133				
Acenaphthylene	682	40.0	1,000	0	68.2	32.8	136				
Acenaphthene	639	40.0	1,000	0	63.9	38.7	129				

Work Order: 1708051
 CLIENT: Shannon & Wilson
 Project: Yakima EWC

QC SUMMARY REPORT
Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Sample ID	LCS-17832	SampType:	LCS	Units:	µg/Kg	Prep Date:	8/7/2017	RunNo:	37845		
Client ID:	LCSS	Batch ID:	17832	Analysis Date:	8/7/2017	SeqNo:	727281				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Fluorene	639	40.0	1,000	0	63.9	41.4	144				
Phenanthrene	623	40.0	1,000	0	62.3	43.9	133				
Anthracene	675	40.0	1,000	0	67.5	44.2	136				
Fluoranthene	664	40.0	1,000	0	66.4	45.9	137				
Pyrene	640	40.0	1,000	0	64.0	46.2	137				
Benz(a)anthracene	640	40.0	1,000	0	64.0	41.2	141				
Chrysene	679	40.0	1,000	0	67.9	46.9	138				
Benzo(b)fluoranthene	584	40.0	1,000	0	58.4	41	155				
Benzo(j,k)fluoranthene	772	40.0	1,000	0	77.2	41.8	153				
Benzo(a)pyrene	645	40.0	1,000	0	64.5	30.2	171				
Indeno(1,2,3-cd)pyrene	622	40.0	1,000	0	62.2	31.3	159				
Dibenz(a,h)anthracene	601	40.0	1,000	0	60.1	28	158				
Benzo(g,h,i)perylene	645	40.0	1,000	0	64.5	32.4	144				
Surr: 2-Fluorobiphenyl	464		500.0		92.7	24.5	139				
Surr: Terphenyl-d14 (surr)	577		500.0		115	46.2	179				

Sample ID	1708051-003ADUP	SampType:	DUP	Units:	µg/Kg-dry	Prep Date:	8/7/2017	RunNo:	37845		
Client ID:	ES-7	Batch ID:	17832	Analysis Date:	8/7/2017	SeqNo:	727326				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	ND	38.3						0		30	
2-Methylnaphthalene	ND	38.3						0		30	
1-Methylnaphthalene	ND	38.3						0		30	
Acenaphthylene	ND	38.3						0		30	
Acenaphthene	ND	38.3						0		30	
Fluorene	ND	38.3						0		30	
Phenanthrene	ND	38.3						0		30	
Anthracene	ND	38.3						0		30	
Fluoranthene	ND	38.3						0		30	
Pyrene	ND	38.3						0		30	

Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Sample ID 1708051-003ADUP	SampType: DUP	Units: µg/Kg-dry				Prep Date: 8/7/2017	RunNo: 37845				
Client ID: ES-7	Batch ID: 17832					Analysis Date: 8/7/2017	SeqNo: 727326				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benz(a)anthracene	ND	38.3						0		30	
Chrysene	ND	38.3						0		30	
Benzo(b)fluoranthene	ND	38.3						0		30	
Benzo(j,k)fluoranthene	ND	38.3						0		30	
Benzo(a)pyrene	ND	38.3						0		30	
Indeno(1,2,3-cd)pyrene	ND	38.3						0		30	
Dibenz(a,h)anthracene	ND	38.3						0		30	
Benzo(g,h,i)perylene	ND	38.3						0		30	
Surr: 2-Fluorobiphenyl	390		478.2		81.7	24.5	139		0		
Surr: Terphenyl-d14 (surr)	529		478.2		111	46.2	179		0		

Sample ID 1708051-003AMS	SampType: MS	Units: µg/Kg-dry				Prep Date: 8/7/2017	RunNo: 37845				
Client ID: ES-7	Batch ID: 17832					Analysis Date: 8/7/2017	SeqNo: 727327				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	634	40.8	1,021	0	62.1	42.9	138				
2-Methylnaphthalene	657	40.8	1,021	0	64.4	42.8	151				
1-Methylnaphthalene	650	40.8	1,021	0	63.7	41.6	148				
Acenaphthylene	690	40.8	1,021	0	67.6	32.6	160				
Acenaphthene	624	40.8	1,021	0	61.1	46.3	142				
Fluorene	629	40.8	1,021	0	61.6	43.4	153				
Phenanthrene	604	40.8	1,021	0	59.2	45.5	140				
Anthracene	687	40.8	1,021	0	67.3	32.6	160				
Fluoranthene	684	40.8	1,021	0	67.0	44.6	161				
Pyrene	655	40.8	1,021	0	64.2	48.3	158				
Benz(a)anthracene	674	40.8	1,021	0	66.0	34.9	139				
Chrysene	646	40.8	1,021	0	63.3	45.2	146				
Benzo(b)fluoranthene	633	40.8	1,021	0	62.0	42.2	168				
Benzo(j,k)fluoranthene	767	40.8	1,021	0	75.2	34.8	147				
Benzo(a)pyrene	750	40.8	1,021	0	73.4	34.4	179				

Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Sample ID 1708051-003AMS	SampType: MS	Units: µg/Kg-dry				Prep Date: 8/7/2017	RunNo: 37845				
Client ID: ES-7	Batch ID: 17832					Analysis Date: 8/7/2017	SeqNo: 727327				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Indeno(1,2,3-cd)pyrene	671	40.8	1,021	5.758	65.1	5	113				
Dibenz(a,h)anthracene	653	40.8	1,021	5.364	63.5	17.3	156				
Benzo(g,h,i)perylene	674	40.8	1,021	3.708	65.6	24.9	119				
Surr: 2-Fluorobiphenyl	416		510.4		81.5	24.5	139				
Surr: Terphenyl-d14 (surr)	541		510.4		106	46.2	179				

Sample ID 1708051-003AMSD	SampType: MSD	Units: µg/Kg-dry				Prep Date: 8/7/2017	RunNo: 37845				
Client ID: ES-7	Batch ID: 17832					Analysis Date: 8/7/2017	SeqNo: 727328				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	693	40.9	1,022	0	67.9	42.9	138	634.1	8.95	30	
2-Methylnaphthalene	720	40.9	1,022	0	70.5	42.8	151	657.1	9.15	30	
1-Methylnaphthalene	708	40.9	1,022	0	69.3	41.6	148	649.9	8.53	30	
Acenaphthylene	755	40.9	1,022	0	73.9	32.6	160	689.9	8.99	30	
Acenaphthene	678	40.9	1,022	0	66.4	46.3	142	623.7	8.38	30	
Fluorene	688	40.9	1,022	0	67.3	43.4	153	628.8	8.92	30	
Phenanthrene	659	40.9	1,022	0	64.4	45.5	140	604.5	8.56	30	
Anthracene	740	40.9	1,022	0	72.4	32.6	160	686.7	7.45	30	
Fluoranthene	740	40.9	1,022	0	72.5	44.6	161	684.4	7.86	30	
Pyrene	710	40.9	1,022	0	69.5	48.3	158	655.4	7.95	30	
Benz(a)anthracene	731	40.9	1,022	0	71.5	34.9	139	673.6	8.17	30	
Chrysene	713	40.9	1,022	0	69.8	45.2	146	646.5	9.82	30	
Benzo(b)fluoranthene	724	40.9	1,022	0	70.8	42.2	168	633.1	13.4	30	
Benzo(j,k)fluoranthene	802	40.9	1,022	0	78.5	34.8	147	767.5	4.39	30	
Benzo(a)pyrene	816	40.9	1,022	0	79.9	34.4	179	749.6	8.51	30	
Indeno(1,2,3-cd)pyrene	728	40.9	1,022	5.758	70.7	5	113	670.6	8.17	30	
Dibenz(a,h)anthracene	717	40.9	1,022	5.364	69.6	17.3	156	653.3	9.26	30	
Benzo(g,h,i)perylene	718	40.9	1,022	3.708	69.9	24.9	119	673.7	6.31	30	
Surr: 2-Fluorobiphenyl	428		510.9		83.7	24.5	139		0		
Surr: Terphenyl-d14 (surr)	594		510.9		116	46.2	179		0		



Date: 8/14/2017

Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Sample ID	1708051-003AMSD	SampType:	MSD	Units:	µg/Kg-dry	Prep Date:	8/7/2017	RunNo:	37845		
Client ID:	ES-7	Batch ID:	17832			Analysis Date:	8/7/2017	SeqNo:	727328		
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Polychlorinated Biphenyls (PCB) by EPA 8082

Sample ID MB-17861	SampType: MBLK	Units: mg/Kg	Prep Date: 8/9/2017	RunNo: 37910							
Client ID: MBLKS	Batch ID: 17861		Analysis Date: 8/9/2017	SeqNo: 728407							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Aroclor 1016	ND	0.100									
Aroclor 1221	ND	0.100									
Aroclor 1232	ND	0.100									
Aroclor 1242	ND	0.100									
Aroclor 1248	ND	0.100									
Aroclor 1254	ND	0.100									
Aroclor 1260	ND	0.100									
Aroclor 1262	ND	0.100									
Aroclor 1268	ND	0.100									
Total PCBs	ND	0.100									
Surr: Decachlorobiphenyl	86.2		50.00		172	30.8	168				S
Surr: Tetrachloro-m-xylene	84.6		50.00		169	30.3	157				S

NOTES:

S - Outlying surrogate recovery(ies) observed (high bias). Sample is non-detect; no further action required.

Sample ID LCS1-17861	SampType: LCS	Units: mg/Kg	Prep Date: 8/9/2017	RunNo: 37910							
Client ID: LCSS	Batch ID: 17861		Analysis Date: 8/9/2017	SeqNo: 728408							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Aroclor 1016	1.43	0.100	1.000	0	143	38.5	149				
Aroclor 1260	1.45	0.100	1.000	0	145	35.4	154				
Surr: Decachlorobiphenyl	82.4		50.00		165	30.8	168				
Surr: Tetrachloro-m-xylene	82.0		50.00		164	30.3	157				S

NOTES:

S - Outlying surrogate recovery(ies) observed.

Sample ID LCS2-17861	SampType: LCS	Units: mg/Kg	Prep Date: 8/9/2017	RunNo: 37910							
Client ID: LCSS	Batch ID: 17861		Analysis Date: 8/9/2017	SeqNo: 728409							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Aroclor 1254	1.40	0.100	1.000	0	140	31.9	167				
Surr: Decachlorobiphenyl	78.4		50.00		157	30.8	168				

Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Polychlorinated Biphenyls (PCB) by EPA 8082

Sample ID	LCS2-17861	SampType:	LCS	Units:	mg/Kg	Prep Date:	8/9/2017	RunNo:	37910		
Client ID:	LCSS	Batch ID:	17861			Analysis Date:	8/9/2017	SeqNo:	728409		
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Surr: Tetrachloro-m-xylene	80.0		50.00		160	30.3	157				S
----------------------------	------	--	-------	--	-----	------	-----	--	--	--	---

NOTES:
S - Outlying surrogate recovery(ies) observed.

Sample ID	1708051-002ADUP	SampType:	DUP	Units:	mg/Kg-dry	Prep Date:	8/9/2017	RunNo:	37910		
Client ID:	ES-6	Batch ID:	17861			Analysis Date:	8/9/2017	SeqNo:	728411		
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Aroclor 1016	ND	0.289						0		30	
Aroclor 1221	ND	0.289						0		30	
Aroclor 1232	ND	0.289						0		30	
Aroclor 1242	ND	0.289						0		30	
Aroclor 1248	ND	0.289						0		30	
Aroclor 1254	ND	0.289						0		30	
Aroclor 1260	ND	0.289						0		30	
Aroclor 1262	ND	0.289						0		30	
Aroclor 1268	ND	0.289						0		30	
Total PCBs	ND	0.289						0		30	
Surr: Decachlorobiphenyl	165		144.7		114	30.8	168		0		
Surr: Tetrachloro-m-xylene	157		144.7		109	30.3	157		0		

Sample ID	1708051-002AMS	SampType:	MS	Units:	mg/Kg-dry	Prep Date:	8/9/2017	RunNo:	37910		
Client ID:	ES-6	Batch ID:	17861			Analysis Date:	8/9/2017	SeqNo:	728412		
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Aroclor 1016	3.40	0.295	2.954	0	115	27.1	166				
Aroclor 1260	3.51	0.295	2.954	0.02241	118	20.6	168				
Surr: Decachlorobiphenyl	139		147.7		94.2	30.8	168				
Surr: Tetrachloro-m-xylene	126		147.7		85.3	30.3	157				

Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Polychlorinated Biphenyls (PCB) by EPA 8082

Sample ID 1708051-002AMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 8/9/2017	RunNo: 37910							
Client ID: ES-6	Batch ID: 17861		Analysis Date: 8/9/2017	SeqNo: 728413							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Aroclor 1016	3.28	0.281	2.811	0	117	27.1	166	3.397	3.55	30	
Aroclor 1260	3.33	0.281	2.811	0.02241	118	20.6	168	3.509	5.10	30	
Surr: Decachlorobiphenyl	81.1		140.6		57.7	30.8	168		0		
Surr: Tetrachloro-m-xylene	63.9		140.6		45.5	30.3	157		0		



Date: 8/14/2017

Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Polychlorinated Biphenyls (PCB) by EPA 8082

Sample ID MB-17833	SampType: MBLK	Units: mg/Kg	Prep Date: 8/7/2017	RunNo: 37847							
Client ID: MBLKS	Batch ID: 17833		Analysis Date: 8/7/2017	SeqNo: 727313							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Aroclor 1016	ND	0.100									
Aroclor 1221	ND	0.100									
Aroclor 1232	ND	0.100									
Aroclor 1242	ND	0.100									
Aroclor 1248	ND	0.100									
Aroclor 1254	ND	0.100									
Aroclor 1260	ND	0.100									
Aroclor 1262	ND	0.100									
Aroclor 1268	ND	0.100									
Total PCBs	ND	0.100									
Surr: Decachlorobiphenyl	70.7		50.00		141	30.8	168				
Surr: Tetrachloro-m-xylene	64.7		50.00		129	30.3	157				

Sample ID LCS1-17833	SampType: LCS	Units: mg/Kg	Prep Date: 8/7/2017	RunNo: 37847							
Client ID: LCSS	Batch ID: 17833		Analysis Date: 8/7/2017	SeqNo: 727314							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Aroclor 1016	1.32	0.100	1.000	0	132	38.5	149				
Aroclor 1260	1.45	0.100	1.000	0	145	35.4	154				
Surr: Decachlorobiphenyl	87.0		50.00		174	30.8	168				S
Surr: Tetrachloro-m-xylene	77.3		50.00		155	30.3	157				

NOTES:
S - Outlying surrogate recovery(ies) observed.

Sample ID LCS2-17833	SampType: LCS	Units: mg/Kg	Prep Date: 8/7/2017	RunNo: 37847							
Client ID: LCSS	Batch ID: 17833		Analysis Date: 8/7/2017	SeqNo: 727315							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Aroclor 1254	1.57	0.100	1.000	0	157	31.9	167				
Surr: Decachlorobiphenyl	85.6		50.00		171	30.8	168				S
Surr: Tetrachloro-m-xylene	80.5		50.00		161	30.3	157				S

Work Order: 1708051
 CLIENT: Shannon & Wilson
 Project: Yakima EWC

QC SUMMARY REPORT
Polychlorinated Biphenyls (PCB) by EPA 8082

Sample ID	LCS2-17833	SampType:	LCS	Units:	mg/Kg	Prep Date:	8/7/2017	RunNo:	37847		
Client ID:	LCSS	Batch ID:	17833			Analysis Date:	8/7/2017	SeqNo:	727315		
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

NOTES:
 S - Outlying surrogate recovery(ies) observed.

Sample ID	1707254-014ADUP	SampType:	DUP	Units:	mg/Kg-dry	Prep Date:	8/7/2017	RunNo:	37847		
Client ID:	BATCH	Batch ID:	17833			Analysis Date:	8/7/2017	SeqNo:	727317		
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Aroclor 1016	ND	0.101						0		30	
Aroclor 1221	ND	0.101						0		30	
Aroclor 1232	ND	0.101						0		30	
Aroclor 1242	ND	0.101						0		30	
Aroclor 1248	ND	0.101						0		30	
Aroclor 1254	ND	0.101						0		30	
Aroclor 1260	ND	0.101						0		30	
Aroclor 1262	ND	0.101						0		30	
Aroclor 1268	ND	0.101						0		30	
Total PCBs	ND	0.101						0		30	
Surr: Decachlorobiphenyl	58.3		50.71		115	30.8	168		0		
Surr: Tetrachloro-m-xylene	62.5		50.71		123	30.3	157		0		

Sample ID	1707254-014AMS	SampType:	MS	Units:	mg/Kg-dry	Prep Date:	8/7/2017	RunNo:	37847		
Client ID:	BATCH	Batch ID:	17833			Analysis Date:	8/7/2017	SeqNo:	727318		
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Aroclor 1016	1.30	0.102	1.020	0	127	27.1	166				
Aroclor 1260	1.29	0.102	1.020	0.005811	126	20.6	168				
Surr: Decachlorobiphenyl	64.7		51.00		127	30.8	168				
Surr: Tetrachloro-m-xylene	70.9		51.00		139	30.3	157				

Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Polychlorinated Biphenyls (PCB) by EPA 8082

Sample ID 1707254-014AMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 8/7/2017	RunNo: 37847							
Client ID: BATCH	Batch ID: 17833		Analysis Date: 8/7/2017	SeqNo: 727319							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Aroclor 1016	1.44	0.107	1.067	0	135	27.1	166	1.297	10.4	30
Aroclor 1260	1.42	0.107	1.067	0.005811	132	20.6	168	1.287	9.71	30
Surr: Decachlorobiphenyl	66.8		53.33		125	30.8	168		0	
Surr: Tetrachloro-m-xylene	76.7		53.33		144	30.3	157		0	



Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Sample Moisture (Percent Moisture)

Sample ID 1708059-005ADUP	SampType: DUP	Units: wt%	Prep Date: 8/7/2017	RunNo: 37834							
Client ID: BATCH	Batch ID: R37834		Analysis Date: 8/7/2017	SeqNo: 727111							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Percent Moisture	7.39	0.500						7.194	2.65	20	

Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Total Metals by EPA Method 6020

Sample ID MB-17862	SampType: MBLK	Units: mg/Kg				Prep Date: 8/9/2017	RunNo: 37928				
Client ID: MBLKS	Batch ID: 17862					Analysis Date: 8/10/2017	SeqNo: 728681				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Silver ND 0.0794

Sample ID LCS-17862	SampType: LCS	Units: mg/Kg				Prep Date: 8/9/2017	RunNo: 37928				
Client ID: LCSS	Batch ID: 17862					Analysis Date: 8/10/2017	SeqNo: 728682				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Silver 9.74 0.0775 9.690 0 101 80 120

Sample ID 1708093-001ADUP	SampType: DUP	Units: mg/Kg-dry				Prep Date: 8/9/2017	RunNo: 37928				
Client ID: BATCH	Batch ID: 17862					Analysis Date: 8/10/2017	SeqNo: 728684				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Silver 0.204 0.0856 0.2079 1.81 20

Sample ID 1708093-001AMS	SampType: MS	Units: mg/Kg-dry				Prep Date: 8/9/2017	RunNo: 37928				
Client ID: BATCH	Batch ID: 17862					Analysis Date: 8/10/2017	SeqNo: 728686				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Silver 9.23 0.0843 10.54 0.2079 85.6 75 125

Sample ID 1708093-001AMSD	SampType: MSD	Units: mg/Kg-dry				Prep Date: 8/9/2017	RunNo: 37928				
Client ID: BATCH	Batch ID: 17862					Analysis Date: 8/10/2017	SeqNo: 728687				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Silver 10.2 0.0849 10.62 0.2079 94.5 75 125 9.226 10.4 20



Date: 8/14/2017

Work Order: 1708051
 CLIENT: Shannon & Wilson
 Project: Yakima EWC

QC SUMMARY REPORT
Total Metals by EPA Method 6020

Sample ID MB-17834	SampType: MBLK	Units: mg/Kg	Prep Date: 8/8/2017	RunNo: 37894							
Client ID: MBLKS	Batch ID: 17834		Analysis Date: 8/9/2017	SeqNo: 728012							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	ND	0.0775									
Barium	ND	0.388									
Cadmium	ND	0.155									
Chromium	ND	0.0775									
Copper	ND	0.155									
Lead	ND	0.155									
Nickel	ND	0.0775									
Selenium	ND	0.388									
Zinc	ND	0.310									

Sample ID LCS-17834	SampType: LCS	Units: mg/Kg	Prep Date: 8/8/2017	RunNo: 37894							
Client ID: LCSS	Batch ID: 17834		Analysis Date: 8/9/2017	SeqNo: 728013							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	38.2	0.0787	39.37	0	97.1	80	120				
Barium	35.9	0.394	39.37	0	91.2	80	120				
Cadmium	1.92	0.157	1.969	0	97.4	80	120				
Chromium	39.1	0.0787	39.37	0	99.3	80	120				
Copper	40.4	0.157	39.37	0	103	80	120				
Lead	20.8	0.157	19.69	0	106	80	120				
Nickel	39.9	0.0787	39.37	0	101	80	120				
Selenium	3.88	0.394	3.937	0	98.5	80	120				
Zinc	37.9	0.315	39.37	0	96.3	80	120				

Sample ID 1708069-001BDUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 8/8/2017	RunNo: 37894							
Client ID: BATCH	Batch ID: 17834		Analysis Date: 8/9/2017	SeqNo: 728015							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	4.57	0.0927						4.124	10.3	20	
Barium	88.5	0.464						91.10	2.92	20	



Date: 8/14/2017

Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Total Metals by EPA Method 6020

Sample ID 1708069-001BDUP	SampType: DUP	Units: mg/Kg-dry				Prep Date: 8/8/2017	RunNo: 37894				
Client ID: BATCH	Batch ID: 17834					Analysis Date: 8/9/2017	SeqNo: 728015				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Cadmium	ND	0.185						0		20	
Chromium	51.6	0.0927						40.11	25.2	20	R
Copper	29.2	0.185						25.83	12.2	20	
Lead	7.11	0.185						7.870	10.1	20	
Nickel	51.1	0.0927						40.10	24.1	20	R
Selenium	1.29	0.464						1.105	15.7	20	
Zinc	56.3	0.371						47.67	16.6	20	

NOTES:

R - High RPD observed. The method is in control as indicated by the LCS.

Sample ID 1708069-001BMS	SampType: MS	Units: mg/Kg-dry				Prep Date: 8/8/2017	RunNo: 37894				
Client ID: BATCH	Batch ID: 17834					Analysis Date: 8/9/2017	SeqNo: 728020				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Arsenic	52.9	0.0913	45.64	4.124	107	75	125				
Barium	135	0.456	45.64	91.10	95.9	75	125				
Cadmium	2.56	0.183	2.282	0.08180	109	75	125				
Chromium	81.3	0.0913	45.64	40.11	90.4	75	125				
Copper	76.1	0.183	45.64	25.83	110	75	125				
Lead	35.1	0.183	22.82	7.870	119	75	125				
Nickel	78.6	0.0913	45.64	40.10	84.4	75	125				
Selenium	5.75	0.456	4.564	1.105	102	75	125				
Zinc	88.2	0.365	45.64	47.67	88.8	75	125				

Sample ID 1708069-001BMSD	SampType: MSD	Units: mg/Kg-dry				Prep Date: 8/8/2017	RunNo: 37894				
Client ID: BATCH	Batch ID: 17834					Analysis Date: 8/9/2017	SeqNo: 728021				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Arsenic	51.9	0.0942	47.09	4.124	101	75	125	52.94	1.98	20	
Barium	149	0.471	47.09	91.10	124	75	125	134.9	10.1	20	
Cadmium	2.51	0.188	2.355	0.08180	103	75	125	2.565	2.33	20	

Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Total Metals by EPA Method 6020

Sample ID	1708069-001BMSD	SampType:	MSD	Units:	mg/Kg-dry	Prep Date:	8/8/2017	RunNo:	37894		
Client ID:	BATCH	Batch ID:	17834			Analysis Date:	8/9/2017	SeqNo:	728021		
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Chromium	95.6	0.0942	47.09	40.11	118	75	125	81.35	16.1	20	
Copper	74.7	0.188	47.09	25.83	104	75	125	76.13	1.86	20	
Lead	35.0	0.188	23.55	7.870	115	75	125	35.07	0.312	20	
Nickel	92.3	0.0942	47.09	40.10	111	75	125	78.64	16.0	20	
Selenium	5.85	0.471	4.709	1.105	101	75	125	5.749	1.78	20	
Zinc	98.8	0.377	47.09	47.67	109	75	125	88.18	11.3	20	



Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260C

Sample ID LCS-17870	SampType: LCS	Units: mg/Kg	Prep Date: 8/10/2017	RunNo: 37921
Client ID: LCSS	Batch ID: 17870		Analysis Date: 8/10/2017	SeqNo: 728538

Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Dichlorodifluoromethane (CFC-12)	1.39	0.0200	1.000	0	139	14.3	167				
Chloromethane	1.20	0.0500	1.000	0	120	46	144				
Vinyl chloride	1.12	0.0250	1.000	0	112	43.4	151				
Bromomethane	1.06	0.0500	1.000	0	106	40.9	157				
Trichlorofluoromethane (CFC-11)	1.06	0.0200	1.000	0	106	36.9	156				
Chloroethane	1.04	0.0500	1.000	0	104	33.1	147				
1,1-Dichloroethene	1.04	0.0200	1.000	0	104	49.7	142				
Methylene chloride	1.03	0.0200	1.000	0	103	46.3	140				
trans-1,2-Dichloroethene	1.02	0.0200	1.000	0	102	68	130				
Methyl tert-butyl ether (MTBE)	1.02	0.0500	1.000	0	102	66.3	145				
1,1-Dichloroethane	1.02	0.0200	1.000	0	102	61.9	137				
2,2-Dichloropropane	1.31	0.100	1.000	0	131	35.5	186				
cis-1,2-Dichloroethene	1.02	0.0200	1.000	0	102	71.3	135				
Chloroform	1.01	0.0200	1.000	0	101	69	145				
1,1,1-Trichloroethane (TCA)	0.982	0.0250	1.000	0	98.2	69	132				
1,1-Dichloropropene	1.04	0.0200	1.000	0	104	72.7	131				
Carbon tetrachloride	0.943	0.0250	1.000	0	94.3	63.4	137				
1,2-Dichloroethane (EDC)	1.02	0.0200	1.000	0	102	50.9	162				
Benzene	0.963	0.0200	1.000	0	96.3	64.3	133				
Trichloroethene (TCE)	0.966	0.0200	1.000	0	96.6	65.5	137				
1,2-Dichloropropane	1.03	0.0200	1.000	0	103	63.2	142				
Bromodichloromethane	0.983	0.0200	1.000	0	98.3	53.4	131				
Dibromomethane	1.01	0.0200	1.000	0	101	60.1	146				
cis-1,3-Dichloropropene	1.15	0.0200	1.000	0	115	59.1	143				
Toluene	1.03	0.0200	1.000	0	103	67.3	138				
trans-1,3-Dichloropropylene	1.14	0.0200	1.000	0	114	49.2	149				
1,1,2-Trichloroethane	1.03	0.0200	1.000	0	103	56.9	147				
1,3-Dichloropropane	1.03	0.0250	1.000	0	103	56.1	153				
Tetrachloroethene (PCE)	1.06	0.0250	1.000	0	106	52.7	150				
Dibromochloromethane	0.983	0.0250	1.000	0	98.3	70.6	144				
1,2-Dibromoethane (EDB)	1.01	0.00500	1.000	0	101	50.5	154				

Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260C

Sample ID	LCS-17870	SampType:	LCS	Units:	mg/Kg	Prep Date:	8/10/2017	RunNo:	37921		
Client ID:	LCSS	Batch ID:	17870	Analysis Date:	8/10/2017	SeqNo:	728538				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Chlorobenzene	1.02	0.0250	1.000	0	102	76.1	123				
1,1,1,2-Tetrachloroethane	0.996	0.0250	1.000	0	99.6	65.9	141				
Ethylbenzene	1.05	0.0250	1.000	0	105	74	129				
m,p-Xylene	2.12	0.0500	2.000	0	106	70	124				
o-Xylene	1.04	0.0250	1.000	0	104	68.1	139				
Styrene	1.05	0.0250	1.000	0	105	73.3	146				
Isopropylbenzene	1.05	0.0250	1.000	0	105	70	130				
Bromoform	0.970	0.0500	1.000	0	97.0	67	154				
1,1,2,2-Tetrachloroethane	1.13	0.0200	1.000	0	113	44.8	165				
n-Propylbenzene	1.08	0.0250	1.000	0	108	74.8	125				
Bromobenzene	1.03	0.0200	1.000	0	103	49.2	144				
1,3,5-Trimethylbenzene	1.06	0.0250	1.000	0	106	74.6	123				
2-Chlorotoluene	1.04	0.0250	1.000	0	104	76.7	129				
4-Chlorotoluene	1.05	0.0250	1.000	0	105	77.5	125				
tert-Butylbenzene	1.02	0.0250	1.000	0	102	66.2	130				
1,2,3-Trichloropropane	1.04	0.0250	1.000	0	104	67.9	136				
1,2,4-Trichlorobenzene	1.06	0.0250	1.000	0	106	62.6	143				
sec-Butylbenzene	1.04	0.0500	1.000	0	104	75.6	133				
4-Isopropyltoluene	1.04	0.0500	1.000	0	104	76.8	131				
1,3-Dichlorobenzene	1.04	0.0200	1.000	0	104	72.8	128				
1,4-Dichlorobenzene	1.05	0.0200	1.000	0	105	72.6	126				
n-Butylbenzene	1.14	0.0250	1.000	0	114	65.3	136				
1,2-Dichlorobenzene	1.04	0.0200	1.000	0	104	72.8	126				
1,2-Dibromo-3-chloropropane	0.999	0.500	1.000	0	99.9	40.2	155				
1,2,4-Trimethylbenzene	1.06	0.0200	1.000	0	106	77.5	129				
Hexachlorobutadiene	1.17	0.0500	1.000	0	117	42	151				
Naphthalene	1.14	0.0500	1.000	0	114	58.4	160				
1,2,3-Trichlorobenzene	1.06	0.0200	1.000	0	106	54.8	143				
Surr: Dibromofluoromethane	1.26		1.250		101	56.5	129				
Surr: Toluene-d8	1.31		1.250		104	64.5	151				
Surr: 1-Bromo-4-fluorobenzene	1.34		1.250		107	63.1	141				

Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260C

Sample ID LCS-17870	SampType: LCS	Units: mg/Kg	Prep Date: 8/10/2017	RunNo: 37921							
Client ID: LCSS	Batch ID: 17870		Analysis Date: 8/10/2017	SeqNo: 728538							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Sample ID MB-17870	SampType: MBLK	Units: mg/Kg	Prep Date: 8/10/2017	RunNo: 37921							
Client ID: MBLKS	Batch ID: 17870		Analysis Date: 8/10/2017	SeqNo: 728539							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Dichlorodifluoromethane (CFC-12)	ND	0.0200
Chloromethane	ND	0.0500
Vinyl chloride	ND	0.0250
Bromomethane	ND	0.0500
Trichlorofluoromethane (CFC-11)	ND	0.0200
Chloroethane	ND	0.0500
1,1-Dichloroethene	ND	0.0200
Methylene chloride	ND	0.0200
trans-1,2-Dichloroethene	ND	0.0200
Methyl tert-butyl ether (MTBE)	ND	0.0500
1,1-Dichloroethane	ND	0.0200
2,2-Dichloropropane	ND	0.100
cis-1,2-Dichloroethene	ND	0.0200
Chloroform	ND	0.0200
1,1,1-Trichloroethane (TCA)	ND	0.0250
1,1-Dichloropropene	ND	0.0200
Carbon tetrachloride	ND	0.0250
1,2-Dichloroethane (EDC)	ND	0.0200
Benzene	ND	0.0200
Trichloroethene (TCE)	ND	0.0200
1,2-Dichloropropane	ND	0.0200
Bromodichloromethane	ND	0.0200
Dibromomethane	ND	0.0200
cis-1,3-Dichloropropene	ND	0.0200
Toluene	ND	0.0200

Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260C

Sample ID MB-17870	SampType: MBLK	Units: mg/Kg	Prep Date: 8/10/2017	RunNo: 37921
Client ID: MBLKS	Batch ID: 17870		Analysis Date: 8/10/2017	SeqNo: 728539

Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
trans-1,3-Dichloropropylene	ND	0.0200									
1,1,2-Trichloroethane	ND	0.0200									
1,3-Dichloropropane	ND	0.0250									
Tetrachloroethene (PCE)	ND	0.0250									
Dibromochloromethane	ND	0.0250									
1,2-Dibromoethane (EDB)	ND	0.00500									
Chlorobenzene	ND	0.0250									
1,1,1,2-Tetrachloroethane	ND	0.0250									
Ethylbenzene	ND	0.0250									
m,p-Xylene	ND	0.0500									
o-Xylene	ND	0.0250									
Styrene	ND	0.0250									
Isopropylbenzene	ND	0.0250									
Bromoform	ND	0.0500									
1,1,2,2-Tetrachloroethane	ND	0.0200									
n-Propylbenzene	ND	0.0250									
Bromobenzene	ND	0.0200									
1,3,5-Trimethylbenzene	ND	0.0250									
2-Chlorotoluene	ND	0.0250									
4-Chlorotoluene	ND	0.0250									
tert-Butylbenzene	ND	0.0250									
1,2,3-Trichloropropane	ND	0.0250									
1,2,4-Trichlorobenzene	ND	0.0250									
sec-Butylbenzene	ND	0.0500									
4-Isopropyltoluene	ND	0.0500									
1,3-Dichlorobenzene	ND	0.0200									
1,4-Dichlorobenzene	ND	0.0200									
n-Butylbenzene	ND	0.0250									
1,2-Dichlorobenzene	ND	0.0200									
1,2-Dibromo-3-chloropropane	ND	0.500									
1,2,4-Trimethylbenzene	ND	0.0200									

Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260C

Sample ID MB-17870	SampType: MBLK	Units: mg/Kg	Prep Date: 8/10/2017	RunNo: 37921							
Client ID: MBLKS	Batch ID: 17870		Analysis Date: 8/10/2017	SeqNo: 728539							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Hexachlorobutadiene	ND	0.0500									
Naphthalene	ND	0.0500									
1,2,3-Trichlorobenzene	ND	0.0200									
Surr: Dibromofluoromethane	1.01		1.250		81.0	56.5	129				
Surr: Toluene-d8	1.29		1.250		103	64.5	151				
Surr: 1-Bromo-4-fluorobenzene	1.32		1.250		105	63.1	141				

Sample ID 1708101-002BDUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 8/10/2017	RunNo: 37921							
Client ID: BATCH	Batch ID: 17870		Analysis Date: 8/10/2017	SeqNo: 729055							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Dichlorodifluoromethane (CFC-12)	ND	0.0243						0		30	
Chloromethane	ND	0.0606						0		30	
Vinyl chloride	ND	0.0303						0		30	
Bromomethane	ND	0.0606						0		30	
Trichlorofluoromethane (CFC-11)	ND	0.0243						0		30	
Chloroethane	ND	0.0606						0		30	
1,1-Dichloroethene	ND	0.0243						0		30	
Methylene chloride	ND	0.0243						0		30	
trans-1,2-Dichloroethene	ND	0.0243						0		30	
Methyl tert-butyl ether (MTBE)	ND	0.0606						0		30	
1,1-Dichloroethane	ND	0.0243						0		30	
2,2-Dichloropropane	ND	0.121						0		30	
cis-1,2-Dichloroethene	ND	0.0243						0		30	
Chloroform	ND	0.0243						0		30	
1,1,1-Trichloroethane (TCA)	ND	0.0303						0		30	
1,1-Dichloropropene	ND	0.0243						0		30	
Carbon tetrachloride	ND	0.0303						0		30	
1,2-Dichloroethane (EDC)	ND	0.0243						0		30	
Benzene	ND	0.0243						0		30	



Date: 8/14/2017

Work Order: 1708051
 CLIENT: Shannon & Wilson
 Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260C

Sample ID 1708101-002BDUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 8/10/2017	RunNo: 37921							
Client ID: BATCH	Batch ID: 17870		Analysis Date: 8/10/2017	SeqNo: 729055							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Trichloroethene (TCE)	ND	0.0243						0		30	
1,2-Dichloropropane	ND	0.0243						0		30	
Bromodichloromethane	ND	0.0243						0		30	
Dibromomethane	ND	0.0243						0		30	
cis-1,3-Dichloropropene	ND	0.0243						0		30	
Toluene	0.0349	0.0243						0.03516	0.676	30	
trans-1,3-Dichloropropylene	ND	0.0243						0		30	
1,1,2-Trichloroethane	ND	0.0243						0		30	
1,3-Dichloropropane	ND	0.0303						0		30	
Tetrachloroethene (PCE)	ND	0.0303						0		30	
Dibromochloromethane	ND	0.0303						0		30	
1,2-Dibromoethane (EDB)	ND	0.0606						0		30	
Chlorobenzene	ND	0.0303						0		30	
1,1,1,2-Tetrachloroethane	ND	0.0303						0		30	
Ethylbenzene	ND	0.0303						0		30	
m,p-Xylene	ND	0.0606						0		30	
o-Xylene	ND	0.0303						0		30	
Styrene	ND	0.0303						0		30	
Isopropylbenzene	ND	0.0303						0		30	
Bromoform	ND	0.0606						0		30	
1,1,2,2-Tetrachloroethane	ND	0.0243						0		30	
n-Propylbenzene	ND	0.0303						0		30	
Bromobenzene	ND	0.0243						0		30	
1,3,5-Trimethylbenzene	ND	0.0303						0		30	
2-Chlorotoluene	ND	0.0303						0		30	
4-Chlorotoluene	ND	0.0303						0		30	
tert-Butylbenzene	ND	0.0303						0		30	
1,2,3-Trichloropropane	ND	0.0303						0		30	
1,2,4-Trichlorobenzene	ND	0.0303						0		30	
sec-Butylbenzene	ND	0.0606						0		30	
4-Isopropyltoluene	ND	0.0606						0		30	

Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260C

Sample ID 1708101-002BDUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 8/10/2017	RunNo: 37921							
Client ID: BATCH	Batch ID: 17870		Analysis Date: 8/10/2017	SeqNo: 729055							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
1,3-Dichlorobenzene	ND	0.0243						0		30	
1,4-Dichlorobenzene	ND	0.0243						0		30	
n-Butylbenzene	ND	0.0303						0		30	
1,2-Dichlorobenzene	ND	0.0243						0		30	
1,2-Dibromo-3-chloropropane	ND	0.606						0		30	
1,2,4-Trimethylbenzene	ND	0.0243						0		30	
Hexachlorobutadiene	ND	0.0606						0		30	
Naphthalene	ND	0.0606						0		30	
1,2,3-Trichlorobenzene	ND	0.0243						0		30	
Surr: Dibromofluoromethane	1.45		1.516		96.0	56.5	129		0		
Surr: Toluene-d8	1.55		1.516		102	64.5	151		0		
Surr: 1-Bromo-4-fluorobenzene	1.59		1.516		105	63.1	141		0		

Sample ID 1708101-001BMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 8/10/2017	RunNo: 37921							
Client ID: BATCH	Batch ID: 17870		Analysis Date: 8/10/2017	SeqNo: 729053							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Dichlorodifluoromethane (CFC-12)	0.843	0.0174	0.8677	0	97.2	43.5	121				
Chloromethane	0.881	0.0434	0.8677	0	102	45	130				
Vinyl chloride	0.726	0.0217	0.8677	0	83.7	51.2	146				
Bromomethane	0.973	0.0434	0.8677	0	112	21.3	120				
Trichlorofluoromethane (CFC-11)	0.646	0.0174	0.8677	0	74.4	35	131				
Chloroethane	0.625	0.0434	0.8677	0	72.0	31.9	123				
1,1-Dichloroethene	0.610	0.0174	0.8677	0	70.3	61.9	141				
Methylene chloride	0.785	0.0174	0.8677	0	90.4	54.7	142				
trans-1,2-Dichloroethene	0.772	0.0174	0.8677	0	88.9	52	136				
Methyl tert-butyl ether (MTBE)	1.09	0.0434	0.8677	0	125	54.4	132				
1,1-Dichloroethane	0.797	0.0174	0.8677	0	91.8	51.8	141				
2,2-Dichloropropane	1.67	0.0868	0.8677	0	192	36	123				S
cis-1,2-Dichloroethene	0.823	0.0174	0.8677	0	94.9	58.6	136				

Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260C

Sample ID 1708101-001BMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 8/10/2017	RunNo: 37921
Client ID: BATCH	Batch ID: 17870		Analysis Date: 8/10/2017	SeqNo: 729053

Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Chloroform	0.824	0.0174	0.8677	0	95.0	53.2	129				
1,1,1-Trichloroethane (TCA)	0.766	0.0217	0.8677	0	88.3	58.3	145				
1,1-Dichloropropene	0.776	0.0174	0.8677	0	89.4	55.1	138				
Carbon tetrachloride	0.715	0.0217	0.8677	0	82.4	53.3	144				
1,2-Dichloroethane (EDC)	0.784	0.0174	0.8677	0	90.3	51.3	139				
Benzene	0.786	0.0174	0.8677	0	90.6	63.5	133				
Trichloroethene (TCE)	0.809	0.0174	0.8677	0	93.3	68.6	132				
1,2-Dichloropropane	0.784	0.0174	0.8677	0	90.4	59	136				
Bromodichloromethane	0.772	0.0174	0.8677	0	88.9	50.7	141				
Dibromomethane	0.870	0.0174	0.8677	0	100	50.6	137				
cis-1,3-Dichloropropene	0.970	0.0174	0.8677	0	112	50.4	138				
Toluene	0.787	0.0174	0.8677	0	90.7	63.4	132				
trans-1,3-Dichloropropylene	1.03	0.0174	0.8677	0	119	44.1	147				
1,1,2-Trichloroethane	0.879	0.0174	0.8677	0	101	51.6	137				
1,3-Dichloropropane	0.930	0.0217	0.8677	0	107	53.1	134				
Tetrachloroethene (PCE)	0.767	0.0217	0.8677	0	88.4	35.6	158				
Dibromochloromethane	0.780	0.0217	0.8677	0	89.9	55.3	140				
1,2-Dibromoethane (EDB)	0.911	0.00434	0.8677	0	105	50.4	136				
Chlorobenzene	0.825	0.0217	0.8677	0	95.1	60	133				
1,1,1,2-Tetrachloroethane	0.784	0.0217	0.8677	0	90.4	53.1	142				
Ethylbenzene	0.813	0.0217	0.8677	0	93.7	54.5	134				
m,p-Xylene	1.69	0.0434	1.735	0	97.3	53.1	132				
o-Xylene	0.834	0.0217	0.8677	0	96.1	53.3	139				
Styrene	0.885	0.0217	0.8677	0	102	51.1	132				
Isopropylbenzene	0.829	0.0217	0.8677	0	95.6	58.9	138				
Bromoform	0.813	0.0434	0.8677	0	93.7	57.9	130				
1,1,2,2-Tetrachloroethane	0.915	0.0174	0.8677	0	105	51.9	131				
n-Propylbenzene	0.880	0.0217	0.8677	0	101	53.6	140				
Bromobenzene	0.880	0.0174	0.8677	0	101	54.2	140				
1,3,5-Trimethylbenzene	0.881	0.0217	0.8677	0	101	51.8	136				
2-Chlorotoluene	0.812	0.0217	0.8677	0	93.6	51.6	136				

Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260C

Sample ID 1708101-001BMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 8/10/2017	RunNo: 37921							
Client ID: BATCH	Batch ID: 17870		Analysis Date: 8/10/2017	SeqNo: 729053							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

4-Chlorotoluene	0.894	0.0217	0.8677	0	103	50.1	139				
tert-Butylbenzene	0.859	0.0217	0.8677	0	99.0	50.5	135				
1,2,3-Trichloropropane	1.08	0.0217	0.8677	0	125	50.5	131				
1,2,4-Trichlorobenzene	1.10	0.0217	0.8677	0	126	50.8	130				
sec-Butylbenzene	0.854	0.0434	0.8677	0	98.4	52.6	141				
4-Isopropyltoluene	0.918	0.0434	0.8677	0	106	52.9	134				
1,3-Dichlorobenzene	0.840	0.0174	0.8677	0	96.9	52.6	131				
1,4-Dichlorobenzene	0.851	0.0174	0.8677	0	98.1	52.9	129				
n-Butylbenzene	0.934	0.0217	0.8677	0	108	52.6	130				
1,2-Dichlorobenzene	0.869	0.0174	0.8677	0	100	55.8	129				
1,2-Dibromo-3-chloropropane	1.03	0.434	0.8677	0	118	40.5	131				
1,2,4-Trimethylbenzene	0.905	0.0174	0.8677	0	104	50.6	137				
Hexachlorobutadiene	1.01	0.0434	0.8677	0	117	40.6	158				
Naphthalene	1.32	0.0434	0.8677	0	153	52.3	124				S
1,2,3-Trichlorobenzene	1.10	0.0174	0.8677	0	126	54.4	124				S
Surr: Dibromofluoromethane	1.07		1.085		98.7	56.5	129				
Surr: Toluene-d8	1.11		1.085		102	64.5	151				
Surr: 1-Bromo-4-fluorobenzene	1.21		1.085		112	63.1	141				

Sample ID 1708101-001BMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 8/10/2017	RunNo: 37921							
Client ID: BATCH	Batch ID: 17870		Analysis Date: 8/10/2017	SeqNo: 729054							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Dichlorodifluoromethane (CFC-12)	0.780	0.0174	0.8677	0	89.9	43.5	121	0.8434	7.83	30	
Chloromethane	0.905	0.0434	0.8677	0	104	45	130	0.8812	2.63	30	
Vinyl chloride	0.706	0.0217	0.8677	0	81.3	51.2	146	0.7263	2.87	30	
Bromomethane	0.925	0.0434	0.8677	0	107	21.3	120	0.9733	5.04	30	
Trichlorofluoromethane (CFC-11)	0.628	0.0174	0.8677	0	72.4	35	131	0.6460	2.80	30	
Chloroethane	0.604	0.0434	0.8677	0	69.7	31.9	123	0.6250	3.35	30	
1,1-Dichloroethene	0.635	0.0174	0.8677	0	73.2	61.9	141	0.6097	4.02	30	

Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260C

Sample ID: 1708101-001BMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 8/10/2017	RunNo: 37921
Client ID: BATCH	Batch ID: 17870		Analysis Date: 8/10/2017	SeqNo: 729054

Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Methylene chloride	0.797	0.0174	0.8677	0	91.8	54.7	142	0.7846	1.53	30	
trans-1,2-Dichloroethene	0.789	0.0174	0.8677	0	91.0	52	136	0.7715	2.29	30	
Methyl tert-butyl ether (MTBE)	1.09	0.0434	0.8677	0	126	54.4	132	1.087	0.348	30	
1,1-Dichloroethane	0.798	0.0174	0.8677	0	92.0	51.8	141	0.7969	0.134	30	
2,2-Dichloropropane	1.62	0.0868	0.8677	0	187	36	123	1.668	2.87	30	S
cis-1,2-Dichloroethene	0.806	0.0174	0.8677	0	92.8	58.6	136	0.8231	2.14	30	
Chloroform	0.831	0.0174	0.8677	0	95.7	53.2	129	0.8239	0.827	30	
1,1,1-Trichloroethane (TCA)	0.767	0.0217	0.8677	0	88.4	58.3	145	0.7661	0.123	30	
1,1-Dichloropropene	0.763	0.0174	0.8677	0	87.9	55.1	138	0.7758	1.70	30	
Carbon tetrachloride	0.696	0.0217	0.8677	0	80.2	53.3	144	0.7152	2.68	30	
1,2-Dichloroethane (EDC)	0.790	0.0174	0.8677	0	91.1	51.3	139	0.7838	0.804	30	
Benzene	0.791	0.0174	0.8677	0	91.2	63.5	133	0.7858	0.709	30	
Trichloroethene (TCE)	0.808	0.0174	0.8677	0	93.2	68.6	132	0.8093	0.110	30	
1,2-Dichloropropane	0.795	0.0174	0.8677	0	91.7	59	136	0.7841	1.41	30	
Bromodichloromethane	0.779	0.0174	0.8677	0	89.7	50.7	141	0.7717	0.896	30	
Dibromomethane	0.889	0.0174	0.8677	0	102	50.6	137	0.8699	2.18	30	
cis-1,3-Dichloropropene	0.984	0.0174	0.8677	0	113	50.4	138	0.9700	1.39	30	
Toluene	0.790	0.0174	0.8677	0	91.0	63.4	132	0.7871	0.324	30	
trans-1,3-Dichloropropylene	1.04	0.0174	0.8677	0	120	44.1	147	1.033	1.09	30	
1,1,2-Trichloroethane	0.880	0.0174	0.8677	0	101	51.6	137	0.8786	0.210	30	
1,3-Dichloropropane	0.918	0.0217	0.8677	0	106	53.1	134	0.9302	1.32	30	
Tetrachloroethene (PCE)	0.761	0.0217	0.8677	0	87.7	35.6	158	0.7669	0.729	30	
Dibromochloromethane	0.787	0.0217	0.8677	0	90.7	55.3	140	0.7801	0.925	30	
1,2-Dibromoethane (EDB)	0.927	0.00434	0.8677	0	107	50.4	136	0.9114	1.69	30	
Chlorobenzene	0.842	0.0217	0.8677	0	97.0	60	133	0.8248	2.02	30	
1,1,1,2-Tetrachloroethane	0.799	0.0217	0.8677	0	92.1	53.1	142	0.7841	1.88	30	
Ethylbenzene	0.826	0.0217	0.8677	0	95.2	54.5	134	0.8129	1.65	30	
m,p-Xylene	1.72	0.0434	1.735	0	98.8	53.1	132	1.688	1.58	30	
o-Xylene	0.847	0.0217	0.8677	0	97.6	53.3	139	0.8342	1.51	30	
Styrene	0.897	0.0217	0.8677	0	103	51.1	132	0.8854	1.26	30	
Isopropylbenzene	0.845	0.0217	0.8677	0	97.4	58.9	138	0.8295	1.84	30	

Work Order: 1708051
 CLIENT: Shannon & Wilson
 Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260C

Sample ID 1708101-001BMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 8/10/2017	RunNo: 37921							
Client ID: BATCH	Batch ID: 17870		Analysis Date: 8/10/2017	SeqNo: 729054							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Bromoform	0.829	0.0434	0.8677	0	95.5	57.9	130	0.8132	1.90	30	
1,1,2,2-Tetrachloroethane	0.953	0.0174	0.8677	0	110	51.9	131	0.9150	4.03	30	
n-Propylbenzene	0.887	0.0217	0.8677	0	102	53.6	140	0.8797	0.819	30	
Bromobenzene	0.889	0.0174	0.8677	0	102	54.2	140	0.8799	1.07	30	
1,3,5-Trimethylbenzene	0.898	0.0217	0.8677	0	103	51.8	136	0.8806	1.95	30	
2-Chlorotoluene	0.836	0.0217	0.8677	0	96.3	51.6	136	0.8124	2.81	30	
4-Chlorotoluene	0.919	0.0217	0.8677	0	106	50.1	139	0.8938	2.74	30	
tert-Butylbenzene	0.860	0.0217	0.8677	0	99.1	50.5	135	0.8591	0.119	30	
1,2,3-Trichloropropane	1.13	0.0217	0.8677	0	130	50.5	131	1.085	4.28	30	
1,2,4-Trichlorobenzene	1.16	0.0217	0.8677	0	134	50.8	130	1.095	5.99	30	S
sec-Butylbenzene	0.859	0.0434	0.8677	0	99.0	52.6	141	0.8538	0.572	30	
4-Isopropyltoluene	0.922	0.0434	0.8677	0	106	52.9	134	0.9184	0.423	30	
1,3-Dichlorobenzene	0.878	0.0174	0.8677	0	101	52.6	131	0.8405	4.42	30	
1,4-Dichlorobenzene	0.884	0.0174	0.8677	0	102	52.9	129	0.8508	3.78	30	
n-Butylbenzene	0.963	0.0217	0.8677	0	111	52.6	130	0.9336	3.11	30	
1,2-Dichlorobenzene	0.915	0.0174	0.8677	0	105	55.8	129	0.8686	5.23	30	
1,2-Dibromo-3-chloropropane	1.09	0.434	0.8677	0	126	40.5	131	1.028	5.96	30	
1,2,4-Trimethylbenzene	0.935	0.0174	0.8677	0	108	50.6	137	0.9049	3.32	30	
Hexachlorobutadiene	1.03	0.0434	0.8677	0	119	40.6	158	1.014	1.49	30	
Naphthalene	1.44	0.0434	0.8677	0	166	52.3	124	1.324	8.34	30	S
1,2,3-Trichlorobenzene	1.16	0.0174	0.8677	0	134	54.4	124	1.095	5.99	30	S
Surr: Dibromofluoromethane	1.07		1.085		98.7	56.5	129		0		
Surr: Toluene-d8	1.10		1.085		101	64.5	151		0		
Surr: 1-Bromo-4-fluorobenzene	1.21		1.085		111	63.1	141		0		

Sample ID 1708084-005BDUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 8/10/2017	RunNo: 37921							
Client ID: BATCH	Batch ID: 17870		Analysis Date: 8/10/2017	SeqNo: 729052							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Dichlorodifluoromethane (CFC-12)	ND	0.00851						0		30	
----------------------------------	----	---------	--	--	--	--	--	---	--	----	--



Work Order: 1708051
CLIENT: Shannon & Wilson
Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260C

Sample ID 1708084-005BDUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 8/10/2017	RunNo: 37921							
Client ID: BATCH	Batch ID: 17870		Analysis Date: 8/10/2017	SeqNo: 729052							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Chloromethane	ND	0.0213						0		30	
Vinyl chloride	ND	0.0106						0		30	
Bromomethane	ND	0.0213						0		30	
Trichlorofluoromethane (CFC-11)	ND	0.00851						0		30	
Chloroethane	ND	0.0213						0		30	
1,1-Dichloroethene	ND	0.00851						0		30	
Methylene chloride	ND	0.00851						0		30	
trans-1,2-Dichloroethene	ND	0.00851						0		30	
Methyl tert-butyl ether (MTBE)	ND	0.0213						0		30	
1,1-Dichloroethane	ND	0.00851						0		30	
2,2-Dichloropropane	ND	0.0426						0		30	
cis-1,2-Dichloroethene	ND	0.00851						0		30	
Chloroform	ND	0.00851						0		30	
1,1,1-Trichloroethane (TCA)	ND	0.0106						0		30	
1,1-Dichloropropene	ND	0.00851						0		30	
Carbon tetrachloride	ND	0.0106						0		30	
1,2-Dichloroethane (EDC)	ND	0.00851						0		30	
Benzene	ND	0.00851						0		30	
Trichloroethene (TCE)	ND	0.00851						0		30	
1,2-Dichloropropane	ND	0.00851						0		30	
Bromodichloromethane	ND	0.00851						0		30	
Dibromomethane	ND	0.00851						0		30	
cis-1,3-Dichloropropene	ND	0.00851						0		30	
Toluene	ND	0.00851						0		30	
trans-1,3-Dichloropropylene	ND	0.00851						0		30	
1,1,2-Trichloroethane	ND	0.00851						0		30	
1,3-Dichloropropane	ND	0.0106						0		30	
Tetrachloroethene (PCE)	ND	0.0106						0		30	
Dibromochloromethane	ND	0.0106						0		30	
1,2-Dibromoethane (EDB)	ND	0.00213						0		30	
Chlorobenzene	ND	0.0106						0		30	

Work Order: 1708051
 CLIENT: Shannon & Wilson
 Project: Yakima EWC

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260C

Sample ID 1708084-005BDUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 8/10/2017	RunNo: 37921							
Client ID: BATCH	Batch ID: 17870		Analysis Date: 8/10/2017	SeqNo: 729052							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

1,1,1,2-Tetrachloroethane	ND	0.0106						0		30	
Ethylbenzene	ND	0.0106						0		30	
m,p-Xylene	ND	0.0213						0		30	
o-Xylene	ND	0.0106						0		30	
Styrene	ND	0.0106						0		30	
Isopropylbenzene	ND	0.0106						0		30	
Bromoform	ND	0.0213						0		30	
1,1,2,2-Tetrachloroethane	ND	0.00851						0		30	
n-Propylbenzene	ND	0.0106						0		30	
Bromobenzene	ND	0.00851						0		30	
1,3,5-Trimethylbenzene	ND	0.0106						0		30	
2-Chlorotoluene	ND	0.0106						0		30	
4-Chlorotoluene	ND	0.0106						0		30	
tert-Butylbenzene	ND	0.0106						0		30	
1,2,3-Trichloropropane	ND	0.0106						0		30	
1,2,4-Trichlorobenzene	ND	0.0106						0		30	
sec-Butylbenzene	ND	0.0213						0		30	
4-Isopropyltoluene	ND	0.0213						0		30	
1,3-Dichlorobenzene	ND	0.00851						0		30	
1,4-Dichlorobenzene	ND	0.00851						0		30	
n-Butylbenzene	ND	0.0106						0		30	
1,2-Dichlorobenzene	ND	0.00851						0		30	
1,2-Dibromo-3-chloropropane	ND	0.213						0		30	
1,2,4-Trimethylbenzene	ND	0.00851						0		30	
Hexachlorobutadiene	ND	0.0213						0		30	
Naphthalene	ND	0.0213						0		30	
1,2,3-Trichlorobenzene	ND	0.00851						0		30	
Surr: Dibromofluoromethane	0.485		0.5320		91.1	56.5	129		0		
Surr: Toluene-d8	0.516		0.5320		96.9	64.5	151		0		
Surr: 1-Bromo-4-fluorobenzene	0.552		0.5320		104	63.1	141		0		

Client Name: SW	Work Order Number: 1708051
Logged by: Clare Griggs	Date Received: 8/4/2017 1:15:00 PM

Chain of Custody

1. Is Chain of Custody complete? Yes No Not Present
2. How was the sample delivered? Client

Log In

3. Coolers are present? Yes No NA
4. Shipping container/cooler in good condition? Yes No
5. Custody Seals present on shipping container/cooler?
(Refer to comments for Custody Seals not intact) Yes No Not Required
6. Was an attempt made to cool the samples? Yes No NA
7. Were all items received at a temperature of >0°C to 10.0°C* Yes No NA
8. Sample(s) in proper container(s)? Yes No
9. Sufficient sample volume for indicated test(s)? Yes No
10. Are samples properly preserved? Yes No
11. Was preservative added to bottles? Yes No NA
12. Is there headspace in the VOA vials? Yes No NA
13. Did all samples containers arrive in good condition(unbroken)? Yes No
14. Does paperwork match bottle labels? Yes No
15. Are matrices correctly identified on Chain of Custody? Yes No
16. Is it clear what analyses were requested? Yes No
17. Were all holding times able to be met? Yes No

Special Handling (if applicable)

18. Was client notified of all discrepancies with this order? Yes No NA

Person Notified:	<input type="text"/>	Date	<input type="text"/>
By Whom:	<input type="text"/>	Via:	<input type="checkbox"/> eMail <input type="checkbox"/> Phone <input type="checkbox"/> Fax <input type="checkbox"/> In Person
Regarding:	<input type="text"/>		
Client Instructions:	<input type="text"/>		

19. Additional remarks:

Item Information

Item #	Temp °C
Cooler	8.4
Sample	3.4

* Note: DoD/ELAP and TNI require items to be received at 4°C +/- 2°C



3600 Fremont Ave. N.
Seattle, WA 98103
T: (206) 352-3790
F: (206) 352-7178
info@fremontanalytical.com

Shannon & Wilson

Dave Randall
400 N. 34th Street, Suite 100
Seattle, WA 98103

**RE: Cascade Mill Parkway
Work Order Number: 2104132**

April 29, 2021

Attention Dave Randall:

Fremont Analytical, Inc. received 4 sample(s) on 4/8/2021 for the analyses presented in the following report.

***Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.
Gasoline by NWTPH-Gx
Mercury by EPA Method 7471
Sample Moisture (Percent Moisture)
Semi-Volatile Organic Compounds by EPA 8270 (SIM)
Total Metals by EPA Method 6020B
Volatile Organic Compounds by EPA Method 8260D***

This report consists of the following:

- Case Narrative
- Analytical Results
- Applicable Quality Control Summary Reports
- Chain of Custody

All analyses were performed consistent with the Quality Assurance program of Fremont Analytical, Inc. Please contact the laboratory if you should have any questions about the results.

Thank you for using Fremont Analytical.

Sincerely,

Brianna Barnes
Project Manager

*DoD-ELAP Accreditation #79636 by PJLA, ISO/IEC 17025:2017 and QSM 5.3 for Environmental Testing
ORELAP Certification: WA 100009 (NELAP Recognized) for Environmental Testing
Washington State Department of Ecology Accredited for Environmental Testing, Lab ID C910*

Revision v1



Date: 04/29/2021

CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway
Work Order: 2104132

Work Order Sample Summary

Lab Sample ID	Client Sample ID	Date/Time Collected	Date/Time Received
2104132-001	B-10-21/S-3@15.5	04/05/2021 11:05 PM	04/08/2021 5:37 PM
2104132-002	B-10-21/A9@48	04/06/2021 10:30 PM	04/08/2021 5:37 PM
2104132-003	B-9-21/R-10@48	04/07/2021 11:05 PM	04/08/2021 5:37 PM
2104132-004	Trip Blank	03/03/2021 10:10 AM	04/08/2021 5:37 PM

Note: If no "Time Collected" is supplied, a default of 12:00AM is assigned

CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

I. SAMPLE RECEIPT:

Samples receipt information is recorded on the attached Sample Receipt Checklist.

II. GENERAL REPORTING COMMENTS:

Results are reported on a wet weight basis unless dry-weight correction is denoted in the units field on the analytical report ("mg/kg-dry" or "ug/kg-dry").

Matrix Spike (MS) and MS Duplicate (MSD) samples are tested from an analytical batch of "like" matrix to check for possible matrix effect. The MS and MSD will provide site specific matrix data only for those samples which are spiked by the laboratory. The sample chosen for spike purposes may or may not have been a sample submitted in this sample delivery group. The validity of the analytical procedures for which data is reported in this analytical report is determined by the Laboratory Control Sample (LCS) and the Method Blank (MB). The LCS and the MB are processed with the samples and the MS/MSD to ensure method criteria are achieved throughout the entire analytical process.

III. ANALYSES AND EXCEPTIONS:

Exceptions associated with this report will be footnoted in the analytical results page(s) or the quality control summary page(s) and/or noted below.

4/29/2021: Revision 1 includes additional analysis requested by client.

Qualifiers:

- * - Flagged value is not within established control limits
- B - Analyte detected in the associated Method Blank
- D - Dilution was required
- E - Value above quantitation range
- H - Holding times for preparation or analysis exceeded
- I - Analyte with an internal standard that does not meet established acceptance criteria
- J - Analyte detected below Reporting Limit
- N - Tentatively Identified Compound (TIC)
- Q - Analyte with an initial or continuing calibration that does not meet established acceptance criteria
- S - Spike recovery outside accepted recovery limits
- ND - Not detected at the Reporting Limit
- R - High relative percent difference observed

Acronyms:

- %Rec - Percent Recovery
- CCB - Continued Calibration Blank
- CCV - Continued Calibration Verification
- DF - Dilution Factor
- DUP - Sample Duplicate
- HEM - Hexane Extractable Material
- ICV - Initial Calibration Verification
- LCS/LCSD - Laboratory Control Sample / Laboratory Control Sample Duplicate
- MCL - Maximum Contaminant Level
- MB or MBLANK - Method Blank
- MDL - Method Detection Limit
- MS/MSD - Matrix Spike / Matrix Spike Duplicate
- PDS - Post Digestion Spike
- Ref Val - Reference Value
- REP - Sample Replicate
- RL - Reporting Limit
- RPD - Relative Percent Difference
- SD - Serial Dilution
- SGT - Silica Gel Treatment
- SPK - Spike
- Surr - Surrogate



Client: Shannon & Wilson

Collection Date: 4/5/2021 11:05:00 PM

Project: Cascade Mill Parkway

Lab ID: 2104132-001

Matrix: Soil

Client Sample ID: B-10-21/S-3@15.5

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Batch ID: 32091

Analyst: MM

Diesel (Fuel Oil)	ND	52.1	H	mg/Kg-dry	1	4/26/2021 5:33:39 PM
Heavy Oil	1,120	104	H	mg/Kg-dry	1	4/26/2021 5:33:39 PM
Total Petroleum Hydrocarbons	1,120	156	H	mg/Kg-dry	1	4/26/2021 5:33:39 PM
Surr: 2-Fluorobiphenyl	75.3	50 - 150	H	%Rec	1	4/26/2021 5:33:39 PM
Surr: o-Terphenyl	98.5	50 - 150	H	%Rec	1	4/26/2021 5:33:39 PM

Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Batch ID: 32072

Analyst: SB

Naphthalene	ND	19.1	H	µg/Kg-dry	1	4/26/2021 10:45:00 AM
2-Methylnaphthalene	ND	19.1	H	µg/Kg-dry	1	4/26/2021 10:45:00 AM
1-Methylnaphthalene	ND	19.1	H	µg/Kg-dry	1	4/26/2021 10:45:00 AM
Acenaphthene	ND	19.1	H	µg/Kg-dry	1	4/26/2021 10:45:00 AM
Acenaphthylene	ND	19.1	H	µg/Kg-dry	1	4/26/2021 10:45:00 AM
Fluorene	ND	19.1	H	µg/Kg-dry	1	4/26/2021 10:45:00 AM
Pentachlorophenol	ND	76.6	H	µg/Kg-dry	1	4/26/2021 10:45:00 AM
Phenanthrene	ND	38.3	H	µg/Kg-dry	1	4/26/2021 10:45:00 AM
Anthracene	ND	38.3	H	µg/Kg-dry	1	4/26/2021 10:45:00 AM
Fluoranthene	ND	38.3	H	µg/Kg-dry	1	4/26/2021 10:45:00 AM
Pyrene	ND	38.3	H	µg/Kg-dry	1	4/26/2021 10:45:00 AM
Benz(a)anthracene	ND	19.1	H	µg/Kg-dry	1	4/26/2021 10:45:00 AM
Chrysene	ND	38.3	H	µg/Kg-dry	1	4/26/2021 10:45:00 AM
Benzo(b)fluoranthene	ND	19.1	H	µg/Kg-dry	1	4/26/2021 10:45:00 AM
Benzo(k)fluoranthene	ND	19.1	H	µg/Kg-dry	1	4/26/2021 10:45:00 AM
Benzo(a)pyrene	ND	19.1	H	µg/Kg-dry	1	4/26/2021 10:45:00 AM
Indeno(1,2,3-cd)pyrene	ND	38.3	H	µg/Kg-dry	1	4/26/2021 10:45:00 AM
Dibenz(a,h)anthracene	ND	38.3	H	µg/Kg-dry	1	4/26/2021 10:45:00 AM
Benzo(g,h,i)perylene	ND	19.1	H	µg/Kg-dry	1	4/26/2021 10:45:00 AM
Surr: 2,4,6-Tribromophenol	65.5	19.4 - 153	H	%Rec	1	4/26/2021 10:45:00 AM
Surr: 2-Fluorobiphenyl	59.9	19 - 135	H	%Rec	1	4/26/2021 10:45:00 AM
Surr: Terphenyl-d14 (surr)	75.0	42.9 - 156	H	%Rec	1	4/26/2021 10:45:00 AM

Gasoline by NWTPH-Gx

Batch ID: 32073

Analyst: CR

Gasoline	ND	131	DH	mg/Kg-dry	20	4/26/2021 8:09:19 AM
Gasoline Range Organics (C6-C12)	1,030	131	DH	mg/Kg-dry	20	4/26/2021 8:09:19 AM
Surr: Toluene-d8	94.0	65 - 135	DH	%Rec	20	4/26/2021 8:09:19 AM
Surr: 4-Bromofluorobenzene	162	65 - 135	DSH	%Rec	20	4/26/2021 8:09:19 AM



Analytical Report

Work Order: 2104132
Date Reported: 4/29/2021

Client: Shannon & Wilson
Project: Cascade Mill Parkway
Lab ID: 2104132-001
Client Sample ID: B-10-21/S-3@15.5

Collection Date: 4/5/2021 11:05:00 PM
Matrix: Soil

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Gasoline by NWTPH-Gx

Batch ID: 32073 Analyst: CR

NOTES:

GRO - Indicates the presence of unresolved compounds eluting from hexane to dodecane (~C6-C12). Beginning pattern matches mineral spirits, end pattern is a different product.
S - Outlying surrogate recovery(ies) observed.

Volatile Organic Compounds by EPA Method 8260D

Batch ID: 32073 Analyst: CR

Benzene	ND	0.0263	H	mg/Kg-dry	1	4/23/2021 2:14:08 PM
Toluene	ND	0.0854	H	mg/Kg-dry	1	4/23/2021 2:14:08 PM
Ethylbenzene	ND	0.0328	H	mg/Kg-dry	1	4/23/2021 2:14:08 PM
m,p-Xylene	ND	0.0657	H	mg/Kg-dry	1	4/23/2021 2:14:08 PM
o-Xylene	ND	0.0328	H	mg/Kg-dry	1	4/23/2021 2:14:08 PM
Surr: Dibromofluoromethane	92.6	81.9 - 113	H	%Rec	1	4/23/2021 2:14:08 PM
Surr: Toluene-d8	96.7	82.7 - 115	H	%Rec	1	4/23/2021 2:14:08 PM
Surr: 1-Bromo-4-fluorobenzene	130	87.9 - 109	SH	%Rec	1	4/23/2021 2:14:08 PM

NOTES:

S - Outlying surrogate recovery(ies) observed.

Mercury by EPA Method 7471

Batch ID: 32120 Analyst: LB

Mercury	ND	0.235		mg/Kg-dry	1	4/29/2021 12:18:36 PM
---------	----	-------	--	-----------	---	-----------------------

Total Metals by EPA Method 6020B

Batch ID: 32067 Analyst: EH

Arsenic	2.58	0.101		mg/Kg-dry	1	4/26/2021 3:21:18 PM
Barium	70.2	0.505		mg/Kg-dry	1	4/26/2021 3:21:18 PM
Cadmium	ND	0.168		mg/Kg-dry	1	4/26/2021 3:21:18 PM
Chromium	29.7	0.336		mg/Kg-dry	1	4/26/2021 3:21:18 PM
Lead	3.06	0.168		mg/Kg-dry	1	4/26/2021 3:21:18 PM
Selenium	1.52	0.168		mg/Kg-dry	1	4/27/2021 6:08:48 PM
Silver	ND	0.126		mg/Kg-dry	1	4/26/2021 3:21:18 PM

Sample Moisture (Percent Moisture)

Batch ID: R66768 Analyst: mch

Percent Moisture	4.88	0.500		wt%	1	4/23/2021 1:42:51 PM
------------------	------	-------	--	-----	---	----------------------



Client: Shannon & Wilson
Project: Cascade Mill Parkway
Lab ID: 2104132-002
Client Sample ID: B-10-21/A9@48

Collection Date: 4/6/2021 10:30:00 PM
Matrix: Soil

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Batch ID: 31933 Analyst: MM

Diesel (Fuel Oil)	ND	53.2		mg/Kg-dry	1	4/12/2021 2:12:10 AM
Heavy Oil	ND	106		mg/Kg-dry	1	4/12/2021 2:12:10 AM
Total Petroleum Hydrocarbons	ND	79.8		mg/Kg-dry	1	4/12/2021 2:12:10 AM
Surr: 2-Fluorobiphenyl	85.8	50 - 150		%Rec	1	4/12/2021 2:12:10 AM
Surr: o-Terphenyl	95.0	50 - 150		%Rec	1	4/12/2021 2:12:10 AM

Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Batch ID: 31963 Analyst: SB

Naphthalene	ND	20.2		µg/Kg-dry	1	4/14/2021 9:35:30 AM
2-Methylnaphthalene	ND	20.2		µg/Kg-dry	1	4/14/2021 9:35:30 AM
1-Methylnaphthalene	ND	20.2		µg/Kg-dry	1	4/14/2021 9:35:30 AM
Acenaphthene	ND	20.2		µg/Kg-dry	1	4/14/2021 9:35:30 AM
Acenaphthylene	ND	20.2		µg/Kg-dry	1	4/14/2021 9:35:30 AM
Fluorene	ND	20.2		µg/Kg-dry	1	4/14/2021 9:35:30 AM
Pentachlorophenol	ND	80.9		µg/Kg-dry	1	4/14/2021 9:35:30 AM
Phenanthrene	ND	40.4		µg/Kg-dry	1	4/14/2021 9:35:30 AM
Anthracene	ND	40.4		µg/Kg-dry	1	4/14/2021 9:35:30 AM
Fluoranthene	ND	40.4		µg/Kg-dry	1	4/14/2021 9:35:30 AM
Pyrene	ND	40.4		µg/Kg-dry	1	4/14/2021 9:35:30 AM
Benz(a)anthracene	ND	20.2		µg/Kg-dry	1	4/14/2021 9:35:30 AM
Chrysene	ND	40.4		µg/Kg-dry	1	4/14/2021 9:35:30 AM
Benzo(b)fluoranthene	ND	20.2		µg/Kg-dry	1	4/14/2021 9:35:30 AM
Benzo(k)fluoranthene	ND	20.2		µg/Kg-dry	1	4/14/2021 9:35:30 AM
Benzo(a)pyrene	ND	20.2		µg/Kg-dry	1	4/14/2021 9:35:30 AM
Indeno(1,2,3-cd)pyrene	ND	40.4		µg/Kg-dry	1	4/14/2021 9:35:30 AM
Dibenz(a,h)anthracene	ND	40.4		µg/Kg-dry	1	4/14/2021 9:35:30 AM
Benzo(g,h,i)perylene	ND	20.2		µg/Kg-dry	1	4/14/2021 9:35:30 AM
Surr: 2,4,6-Tribromophenol	80.0	19.4 - 153		%Rec	1	4/14/2021 9:35:30 AM
Surr: 2-Fluorobiphenyl	86.8	19 - 135		%Rec	1	4/14/2021 9:35:30 AM
Surr: Terphenyl-d14 (surr)	99.8	42.9 - 156		%Rec	1	4/14/2021 9:35:30 AM

Gasoline by NWTPH-Gx

Batch ID: 31943 Analyst: KT

Gasoline	ND	5.46		mg/Kg-dry	1	4/9/2021 9:56:18 PM
Surr: Toluene-d8	94.6	65 - 135		%Rec	1	4/9/2021 9:56:18 PM
Surr: 4-Bromofluorobenzene	100	65 - 135		%Rec	1	4/9/2021 9:56:18 PM



Client: Shannon & Wilson
Project: Cascade Mill Parkway
Lab ID: 2104132-002
Client Sample ID: B-10-21/A9@48

Collection Date: 4/6/2021 10:30:00 PM

Matrix: Soil

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Volatile Organic Compounds by EPA Method 8260D

Batch ID: 31943 Analyst: KT

Benzene	ND	0.0218		mg/Kg-dry	1	4/9/2021 9:56:18 PM
Toluene	ND	0.0710		mg/Kg-dry	1	4/9/2021 9:56:18 PM
Ethylbenzene	ND	0.0273		mg/Kg-dry	1	4/9/2021 9:56:18 PM
m,p-Xylene	ND	0.0546		mg/Kg-dry	1	4/9/2021 9:56:18 PM
o-Xylene	ND	0.0273		mg/Kg-dry	1	4/9/2021 9:56:18 PM
Surr: Dibromofluoromethane	78.4	82.3 - 112	S	%Rec	1	4/9/2021 9:56:18 PM
Surr: Toluene-d8	104	90.7 - 109		%Rec	1	4/9/2021 9:56:18 PM
Surr: 1-Bromo-4-fluorobenzene	99.0	88.4 - 109		%Rec	1	4/9/2021 9:56:18 PM

NOTES:

S - Outlying surrogate recovery(ies) observed.

Mercury by EPA Method 7471

Batch ID: 31945 Analyst: LB

Mercury	ND	0.245		mg/Kg-dry	1	4/12/2021 4:28:42 PM
---------	----	-------	--	-----------	---	----------------------

Total Metals by EPA Method 6020B

Batch ID: 31944 Analyst: EH

Arsenic	2.00	0.102		mg/Kg-dry	1	4/12/2021 5:22:11 PM
Barium	50.5	0.509		mg/Kg-dry	1	4/15/2021 5:16:01 PM
Cadmium	ND	0.170		mg/Kg-dry	1	4/12/2021 5:22:11 PM
Chromium	14.2	0.340		mg/Kg-dry	1	4/12/2021 5:22:11 PM
Lead	1.96	0.170		mg/Kg-dry	1	4/12/2021 5:22:11 PM
Selenium	2.25	0.170		mg/Kg-dry	1	4/12/2021 5:22:11 PM
Silver	ND	0.127		mg/Kg-dry	1	4/12/2021 5:22:11 PM

Sample Moisture (Percent Moisture)

Batch ID: R66595 Analyst: RL

Percent Moisture	7.23	0.500		wt%	1	4/15/2021 4:59:25 PM
------------------	------	-------	--	-----	---	----------------------



Analytical Report

Work Order: 2104132
Date Reported: 4/29/2021

Client: Shannon & Wilson
Project: Cascade Mill Parkway
Lab ID: 2104132-003
Client Sample ID: B-9-21/R-10@48

Collection Date: 4/7/2021 11:05:00 PM

Matrix: Soil

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Batch ID: 31933 Analyst: MM

Diesel (Fuel Oil)	ND	52.0		mg/Kg-dry	1	4/12/2021 3:07:52 PM
Heavy Oil	ND	104		mg/Kg-dry	1	4/12/2021 3:07:52 PM
Total Petroleum Hydrocarbons	ND	78.0		mg/Kg-dry	1	4/12/2021 3:07:52 PM
Surr: 2-Fluorobiphenyl	101	50 - 150		%Rec	1	4/12/2021 3:07:52 PM
Surr: o-Terphenyl	102	50 - 150		%Rec	1	4/12/2021 3:07:52 PM

Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Batch ID: 31963 Analyst: SB

Naphthalene	ND	21.3		µg/Kg-dry	1	4/14/2021 6:12:21 PM
2-Methylnaphthalene	ND	21.3		µg/Kg-dry	1	4/14/2021 6:12:21 PM
1-Methylnaphthalene	ND	21.3		µg/Kg-dry	1	4/14/2021 6:12:21 PM
Acenaphthene	ND	21.3		µg/Kg-dry	1	4/14/2021 6:12:21 PM
Acenaphthylene	ND	21.3		µg/Kg-dry	1	4/14/2021 6:12:21 PM
Fluorene	ND	21.3		µg/Kg-dry	1	4/14/2021 6:12:21 PM
Pentachlorophenol	ND	85.2		µg/Kg-dry	1	4/14/2021 6:12:21 PM
Phenanthrene	ND	42.6		µg/Kg-dry	1	4/14/2021 6:12:21 PM
Anthracene	ND	42.6		µg/Kg-dry	1	4/14/2021 6:12:21 PM
Fluoranthene	ND	42.6		µg/Kg-dry	1	4/14/2021 6:12:21 PM
Pyrene	ND	42.6		µg/Kg-dry	1	4/14/2021 6:12:21 PM
Benz(a)anthracene	ND	21.3		µg/Kg-dry	1	4/14/2021 6:12:21 PM
Chrysene	ND	42.6		µg/Kg-dry	1	4/14/2021 6:12:21 PM
Benzo(b)fluoranthene	ND	21.3		µg/Kg-dry	1	4/14/2021 6:12:21 PM
Benzo(k)fluoranthene	ND	21.3		µg/Kg-dry	1	4/14/2021 6:12:21 PM
Benzo(a)pyrene	ND	21.3		µg/Kg-dry	1	4/14/2021 6:12:21 PM
Indeno(1,2,3-cd)pyrene	ND	42.6		µg/Kg-dry	1	4/14/2021 6:12:21 PM
Dibenz(a,h)anthracene	ND	42.6		µg/Kg-dry	1	4/14/2021 6:12:21 PM
Benzo(g,h,i)perylene	ND	21.3		µg/Kg-dry	1	4/14/2021 6:12:21 PM
Surr: 2,4,6-Tribromophenol	71.2	19.4 - 153		%Rec	1	4/14/2021 6:12:21 PM
Surr: 2-Fluorobiphenyl	84.0	19 - 135		%Rec	1	4/14/2021 6:12:21 PM
Surr: Terphenyl-d14 (surr)	94.1	42.9 - 156		%Rec	1	4/14/2021 6:12:21 PM

Gasoline by NWTPH-Gx

Batch ID: 31943 Analyst: KT

Gasoline	ND	5.37		mg/Kg-dry	1	4/9/2021 10:26:35 PM
Surr: Toluene-d8	96.2	65 - 135		%Rec	1	4/9/2021 10:26:35 PM
Surr: 4-Bromofluorobenzene	101	65 - 135		%Rec	1	4/9/2021 10:26:35 PM



Analytical Report

Work Order: 2104132
Date Reported: 4/29/2021

Client: Shannon & Wilson
Project: Cascade Mill Parkway
Lab ID: 2104132-003
Client Sample ID: B-9-21/R-10@48

Collection Date: 4/7/2021 11:05:00 PM

Matrix: Soil

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Volatile Organic Compounds by EPA Method 8260D

Batch ID: 31943 Analyst: KT

Benzene	ND	0.0215		mg/Kg-dry	1	4/9/2021 10:26:35 PM
Toluene	ND	0.0699		mg/Kg-dry	1	4/9/2021 10:26:35 PM
Ethylbenzene	ND	0.0269		mg/Kg-dry	1	4/9/2021 10:26:35 PM
m,p-Xylene	ND	0.0537		mg/Kg-dry	1	4/9/2021 10:26:35 PM
o-Xylene	ND	0.0269		mg/Kg-dry	1	4/9/2021 10:26:35 PM
Surr: Dibromofluoromethane	78.8	82.3 - 112	S	%Rec	1	4/9/2021 10:26:35 PM
Surr: Toluene-d8	106	90.7 - 109		%Rec	1	4/9/2021 10:26:35 PM
Surr: 1-Bromo-4-fluorobenzene	99.3	88.4 - 109		%Rec	1	4/9/2021 10:26:35 PM

NOTES:

S - Outlying surrogate recovery(ies) observed.

Mercury by EPA Method 7471

Batch ID: 31945 Analyst: LB

Mercury	ND	0.238		mg/Kg-dry	1	4/12/2021 4:30:19 PM
---------	----	-------	--	-----------	---	----------------------

Total Metals by EPA Method 6020B

Batch ID: 31944 Analyst: EH

Arsenic	2.41	0.100		mg/Kg-dry	1	4/12/2021 5:27:45 PM
Barium	52.7	0.501		mg/Kg-dry	1	4/15/2021 5:21:35 PM
Cadmium	ND	0.167		mg/Kg-dry	1	4/12/2021 5:27:45 PM
Chromium	15.8	0.334		mg/Kg-dry	1	4/12/2021 5:27:45 PM
Lead	1.97	0.167		mg/Kg-dry	1	4/12/2021 5:27:45 PM
Selenium	2.40	0.167		mg/Kg-dry	1	4/12/2021 5:27:45 PM
Silver	ND	0.125		mg/Kg-dry	1	4/12/2021 5:27:45 PM

Sample Moisture (Percent Moisture)

Batch ID: R66595 Analyst: RL

Percent Moisture	7.94	0.500		wt%	1	4/15/2021 4:59:25 PM
------------------	------	-------	--	-----	---	----------------------

Work Order: 2104132
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Total Metals by EPA Method 6020B

Sample ID: MB-31944	SampType: MBLK	Units: mg/Kg	Prep Date: 4/12/2021	RunNo: 66498							
Client ID: MBLKS	Batch ID: 31944		Analysis Date: 4/12/2021	SeqNo: 1338016							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Arsenic	ND	0.0968									
Barium	ND	0.484									
Cadmium	ND	0.161									
Chromium	ND	0.323									
Lead	ND	0.161									
Selenium	ND	0.161									
Silver	ND	0.121									

Sample ID: LCS-31944	SampType: LCS	Units: mg/Kg	Prep Date: 4/12/2021	RunNo: 66498							
Client ID: LCSS	Batch ID: 31944		Analysis Date: 4/12/2021	SeqNo: 1338017							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Arsenic	40.1	0.0952	39.68	0	101	80	120				
Barium	40.6	0.476	39.68	0	102	80	120				
Cadmium	2.06	0.159	1.984	0	104	80	120				
Chromium	40.5	0.317	39.68	0	102	80	120				
Lead	19.5	0.159	19.84	0	98.4	80	120				
Selenium	3.87	0.159	3.968	0	97.5	80	120				
Silver	2.10	0.119	1.984	0	106	80	120				

Sample ID: 2104143-002AMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 4/12/2021	RunNo: 66498							
Client ID: BATCH	Batch ID: 31944		Analysis Date: 4/12/2021	SeqNo: 1338020							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Arsenic	59.5	0.104	43.44	15.87	101	75	125				
Barium	208	0.521	43.44	147.7	140	75	125				S
Cadmium	2.48	0.174	2.172	0.1740	106	75	125				
Chromium	83.2	0.348	43.44	27.64	128	75	125				S
Lead	34.7	0.174	21.72	14.39	93.7	75	125				

Work Order: 2104132
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Total Metals by EPA Method 6020B

Sample ID: 2104143-002AMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 4/12/2021	RunNo: 66498							
Client ID: BATCH	Batch ID: 31944		Analysis Date: 4/12/2021	SeqNo: 1338020							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Selenium	5.68	0.174	4.344	1.245	102	75	125				
Silver	2.21	0.130	2.172	0.1049	96.9	75	125				

NOTES:
S - Outlying spike recovery(ies) observed for Ba. A duplicate analysis was performed with similar results indicating a possible matrix effect.
S - Outlying spike recovery(ies) observed for Cr and Zn. A duplicate analysis was performed and recovered within range.

Sample ID: 2104143-002AMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 4/12/2021	RunNo: 66498							
Client ID: BATCH	Batch ID: 31944		Analysis Date: 4/12/2021	SeqNo: 1338021							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	63.9	0.105	43.79	15.87	110	75	125	59.53	7.06	20	
Barium	229	0.526	43.79	147.7	187	75	125	208.4	9.61	20	ES
Cadmium	2.47	0.175	2.190	0.1740	105	75	125	2.482	0.373	20	
Chromium	79.4	0.350	43.79	27.64	118	75	125	83.22	4.67	20	
Lead	50.2	0.175	21.90	14.39	164	75	125	34.74	36.5	20	RS
Selenium	5.48	0.175	4.379	1.245	96.7	75	125	5.681	3.63	20	
Silver	2.22	0.131	2.190	0.1049	96.7	75	125	2.210	0.500	20	

NOTES:
S - Outlying spike recovery(ies) observed for Ba. A duplicate analysis was performed with similar results indicating a possible matrix effect.
S - Outlying spike recovery(ies) observed for Pb. A duplicate analysis was performed and recovered within range.
R - High RPD observed.

Sample ID: 2104143-002APDS	SampType: PDS	Units: mg/Kg-dry	Prep Date: 4/12/2021	RunNo: 66498							
Client ID: BATCH	Batch ID: 31944		Analysis Date: 4/12/2021	SeqNo: 1338024							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Barium	216	0.526	43.8	148	156	75	125				S
--------	-----	-------	------	-----	-----	----	-----	--	--	--	---

NOTES:
S - Outlying spike recovery(ies) observed.

Work Order: 2104132
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Total Metals by EPA Method 6020B

Sample ID: MB-32067	SampType: MBLK	Units: mg/Kg	Prep Date: 4/23/2021	RunNo: 66785							
Client ID: MBLKS	Batch ID: 32067		Analysis Date: 4/23/2021	SeqNo: 1344664							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Arsenic	ND	0.0960									
Barium	ND	0.480									
Cadmium	ND	0.160									
Chromium	ND	0.320									
Lead	ND	0.160									
Selenium	ND	0.160									
Silver	ND	0.120									

Sample ID: LCS-32067	SampType: LCS	Units: mg/Kg	Prep Date: 4/23/2021	RunNo: 66785							
Client ID: LCSS	Batch ID: 32067		Analysis Date: 4/23/2021	SeqNo: 1344665							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Arsenic	35.4	0.0930	38.76	0	91.3	80	120				
Barium	37.2	0.465	38.76	0	96.0	80	120				
Cadmium	1.87	0.155	1.938	0	96.5	80	120				
Chromium	37.2	0.310	38.76	0	96.1	80	120				
Lead	18.9	0.155	19.38	0	97.6	80	120				
Selenium	3.54	0.155	3.876	0	91.2	80	120				
Silver	2.10	0.116	1.938	0	108	80	120				

Sample ID: 2104274-007AMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 4/23/2021	RunNo: 66785							
Client ID: BATCH	Batch ID: 32067		Analysis Date: 4/23/2021	SeqNo: 1344668							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Arsenic	45.8	0.104	43.13	3.651	97.6	75	125				
Barium	104	0.518	43.13	58.34	106	75	125				
Cadmium	1.94	0.173	2.157	0.9874	44.1	75	125				S
Chromium	78.6	0.345	43.13	34.29	103	75	125				
Lead	22.8	0.173	21.57	2.393	94.4	75	125				

Work Order: 2104132
 CLIENT: Shannon & Wilson
 Project: Cascade Mill Parkway

QC SUMMARY REPORT
Total Metals by EPA Method 6020B

Sample ID: 2104274-007AMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 4/23/2021	RunNo: 66785							
Client ID: BATCH	Batch ID: 32067		Analysis Date: 4/23/2021	SeqNo: 1344668							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Selenium	5.07	0.173	4.313	0.8973	96.7	75	125				
Silver	1.89	0.129	2.157	0.05103	85.2	75	125				

NOTES:

S - Outlying spike recovery(ies) observed. A duplicate analysis was performed with similar results indicating a possible matrix effect.

Sample ID: 2104274-007AMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 4/23/2021	RunNo: 66785							
Client ID: BATCH	Batch ID: 32067		Analysis Date: 4/23/2021	SeqNo: 1344669							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	44.6	0.104	43.13	3.651	95.0	75	125	45.76	2.52	20	
Barium	104	0.518	43.13	58.34	106	75	125	103.9	0.0709	20	
Cadmium	1.98	0.173	2.157	0.9874	46.1	75	125	1.939	2.17	20	S
Chromium	81.2	0.345	43.13	34.29	109	75	125	78.63	3.19	20	
Lead	22.2	0.173	21.57	2.393	91.8	75	125	22.75	2.53	20	
Selenium	4.99	0.173	4.313	0.8973	95.0	75	125	5.070	1.51	20	
Silver	1.94	0.129	2.157	0.05103	87.7	75	125	1.889	2.76	20	

NOTES:

S - Outlying spike recovery(ies) observed. A duplicate analysis was performed with similar results indicating a possible matrix effect.

Sample ID: 2104274-007APDS	SampType: PDS	Units: mg/Kg-dry	Prep Date: 4/23/2021	RunNo: 66785							
Client ID: BATCH	Batch ID: 32067		Analysis Date: 4/23/2021	SeqNo: 1344670							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	45.0	0.104	43.1	3.65	95.8	75	125				
Barium	101	0.518	43.1	58.3	98.3	75	125				
Cadmium	1.88	0.173	2.16	0.987	41.6	75	125				S
Chromium	78.6	0.345	43.1	34.3	103	75	125				
Lead	21.6	0.173	21.6	2.39	89.2	75	125				
Selenium	5.01	0.173	4.31	0.897	95.4	75	125				
Silver	1.97	0.129	2.16	0.0510	88.8	75	125				

Work Order: 2104132
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Total Metals by EPA Method 6020B

Sample ID: 2104274-007APDS	SampType: PDS	Units: mg/Kg-dry	Prep Date: 4/23/2021	RunNo: 66785							
Client ID: BATCH	Batch ID: 32067		Analysis Date: 4/23/2021	SeqNo: 1344670							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

NOTES:
 S - Outlying spike recovery(ies) observed.

Work Order: 2104132
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Mercury by EPA Method 7471

Sample ID: MB-31945	SampType: MBLK	Units: mg/Kg			Prep Date: 4/12/2021	RunNo: 66489					
Client ID: MBLKS	Batch ID: 31945				Analysis Date: 4/12/2021	SeqNo: 1338591					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury ND 0.250

Sample ID: LCS-31945	SampType: LCS	Units: mg/Kg			Prep Date: 4/12/2021	RunNo: 66489					
Client ID: LCSS	Batch ID: 31945				Analysis Date: 4/12/2021	SeqNo: 1338592					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.530 0.250 0.5000 0 106 80 120

Sample ID: 2103316-022ADUP	SampType: DUP	Units: mg/Kg-dry			Prep Date: 4/12/2021	RunNo: 66489					
Client ID: BATCH	Batch ID: 31945				Analysis Date: 4/12/2021	SeqNo: 1338594					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury ND 0.257 0 20

Sample ID: 2103316-022AMS	SampType: MS	Units: mg/Kg-dry			Prep Date: 4/12/2021	RunNo: 66489					
Client ID: BATCH	Batch ID: 31945				Analysis Date: 4/12/2021	SeqNo: 1338595					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.453 0.242 0.4849 0.03031 87.1 70 130

Sample ID: 2103316-022AMSD	SampType: MSD	Units: mg/Kg-dry			Prep Date: 4/12/2021	RunNo: 66489					
Client ID: BATCH	Batch ID: 31945				Analysis Date: 4/12/2021	SeqNo: 1338596					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.534 0.234 0.4675 0.03031 108 70 130 0.4529 16.4 20

Work Order: 2104132
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Mercury by EPA Method 7471

Sample ID: MB-32120	SampType: MBLK	Units: mg/Kg			Prep Date: 4/28/2021	RunNo: 66875					
Client ID: MBLKS	Batch ID: 32120				Analysis Date: 4/29/2021	SeqNo: 1346835					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury ND 0.250

Sample ID: LCS-32120	SampType: LCS	Units: mg/Kg			Prep Date: 4/28/2021	RunNo: 66875					
Client ID: LCSS	Batch ID: 32120				Analysis Date: 4/29/2021	SeqNo: 1346836					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.492 0.250 0.5000 0 98.4 80 120

Sample ID: 2104132-001ADUP	SampType: DUP	Units: mg/Kg-dry			Prep Date: 4/28/2021	RunNo: 66875					
Client ID: B-10-21/S-3@15.5	Batch ID: 32120				Analysis Date: 4/29/2021	SeqNo: 1346838					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury ND 0.258 0 20

Sample ID: 2104132-001AMS	SampType: MS	Units: mg/Kg-dry			Prep Date: 4/28/2021	RunNo: 66875					
Client ID: B-10-21/S-3@15.5	Batch ID: 32120				Analysis Date: 4/29/2021	SeqNo: 1346839					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.391 0.253 0.5054 0 77.4 70 130

Sample ID: 2104132-001AMSD	SampType: MSD	Units: mg/Kg-dry			Prep Date: 4/28/2021	RunNo: 66875					
Client ID: B-10-21/S-3@15.5	Batch ID: 32120				Analysis Date: 4/29/2021	SeqNo: 1346840					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.433 0.248 0.4959 0 87.4 70 130 0.3912 10.2 20

Work Order: 2104132
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Sample ID: 2104083-029ADUP	SampType: DUP	Units: mg/Kg-dry			Prep Date: 4/9/2021	RunNo: 66485					
Client ID: BATCH	Batch ID: 31933				Analysis Date: 4/12/2021	SeqNo: 1337701					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	ND	104						0		30	
Heavy Oil	4,990	209						6,610	27.9	30	
Total Petroleum Hydrocarbons	5,040	157						6,655	27.6	30	
Surr: 2-Fluorobiphenyl	21.4		20.87		103	50	150		0		
Surr: o-Terphenyl	21.6		20.87		103	50	150		0		

Sample ID: MB-31933	SampType: MBLK	Units: mg/Kg			Prep Date: 4/9/2021	RunNo: 66485					
Client ID: MBLKS	Batch ID: 31933				Analysis Date: 4/12/2021	SeqNo: 1337713					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	ND	50.0									
Heavy Oil	ND	100									
Total Petroleum Hydrocarbons	ND	75.0									
Surr: 2-Fluorobiphenyl	11.0		10.00		110	50	150				
Surr: o-Terphenyl	11.7		10.00		117	50	150				

Sample ID: LCS-31933	SampType: LCS	Units: mg/Kg			Prep Date: 4/9/2021	RunNo: 66485					
Client ID: LCSS	Batch ID: 31933				Analysis Date: 4/12/2021	SeqNo: 1342812					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	570	50.0	500.0	0	114	73.7	114				
Surr: 2-Fluorobiphenyl	11.4		10.00		114	50	150				
Surr: o-Terphenyl	14.3		10.00		143	50	150				

Sample ID: 2104137-001AMS	SampType: MS	Units: mg/Kg-dry			Prep Date: 4/9/2021	RunNo: 66485					
Client ID: BATCH	Batch ID: 31933				Analysis Date: 4/12/2021	SeqNo: 1337730					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	614	50.9	509.2	0	121	61.4	129				

Work Order: 2104132
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Sample ID: 2104137-001AMS	SampType: MS	Units: mg/Kg-dry			Prep Date: 4/9/2021	RunNo: 66485					
Client ID: BATCH	Batch ID: 31933				Analysis Date: 4/12/2021	SeqNo: 1337730					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Surr: 2-Fluorobiphenyl	10.6		10.18		104	50	150				
Surr: o-Terphenyl	13.5		10.18		133	50	150				

Sample ID: 2104137-001AMSD	SampType: MSD	Units: mg/Kg-dry			Prep Date: 4/9/2021	RunNo: 66485					
Client ID: BATCH	Batch ID: 31933				Analysis Date: 4/12/2021	SeqNo: 1337731					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Diesel (Fuel Oil)	600	48.4	484.4	0	124	61.4	129	613.7	2.22	30	
Surr: 2-Fluorobiphenyl	10.1		9.688		104	50	150		0		
Surr: o-Terphenyl	12.9		9.688		133	50	150		0		

Sample ID: 2104137-002ADUP	SampType: DUP	Units: mg/Kg-dry			Prep Date: 4/9/2021	RunNo: 66485					
Client ID: BATCH	Batch ID: 31933				Analysis Date: 4/12/2021	SeqNo: 1337719					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Diesel (Fuel Oil)	ND	50.0						0		30	
Heavy Oil	ND	100						0		30	
Total Petroleum Hydrocarbons	ND	75.0						0		30	
Surr: 2-Fluorobiphenyl	10.1		10.00		101	50	150		0		
Surr: o-Terphenyl	11.0		10.00		110	50	150		0		

Sample ID: MB-32091	SampType: MBLK	Units: mg/Kg			Prep Date: 4/26/2021	RunNo: 66848					
Client ID: MBLKS	Batch ID: 32091				Analysis Date: 4/26/2021	SeqNo: 1346062					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Diesel (Fuel Oil)	ND	50.0									
Heavy Oil	ND	100									
Total Petroleum Hydrocarbons	ND	150									
Surr: 2-Fluorobiphenyl	10.0		10.00		100	50	150				

Work Order: 2104132
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Sample ID: MB-32091	SampType: MBLK	Units: mg/Kg			Prep Date: 4/26/2021	RunNo: 66848					
Client ID: MBLKS	Batch ID: 32091				Analysis Date: 4/26/2021	SeqNo: 1346062					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Surr: o-Terphenyl 10.2 10.00 102 50 150

Sample ID: LCS-32091	SampType: LCS	Units: mg/Kg			Prep Date: 4/26/2021	RunNo: 66848					
Client ID: LCSS	Batch ID: 32091				Analysis Date: 4/26/2021	SeqNo: 1346063					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Diesel (Fuel Oil) 502 50.0 500.0 0 100 73.7 114
Surr: 2-Fluorobiphenyl 9.61 10.00 96.1 50 150
Surr: o-Terphenyl 11.5 10.00 115 50 150

Sample ID: 2104292-001ADUP	SampType: DUP	Units: mg/Kg-dry			Prep Date: 4/26/2021	RunNo: 66848					
Client ID: BATCH	Batch ID: 32091				Analysis Date: 4/26/2021	SeqNo: 1346066					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Diesel (Fuel Oil) ND 96.3 0 30
Heavy Oil ND 193 0 30
Total Petroleum Hydrocarbons ND 289 0 30
Surr: 2-Fluorobiphenyl 9.63 19.26 50.0 50 150 0
Surr: o-Terphenyl 14.1 19.26 73.0 50 150 0

Sample ID: 2104303-002AMS	SampType: MS	Units: mg/Kg-dry			Prep Date: 4/26/2021	RunNo: 66848					
Client ID: BATCH	Batch ID: 32091				Analysis Date: 4/26/2021	SeqNo: 1346070					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Diesel (Fuel Oil) 540 52.5 525.4 0 103 61.4 129
Surr: 2-Fluorobiphenyl 9.89 10.51 94.1 50 150
Surr: o-Terphenyl 10.8 10.51 103 50 150

Work Order: 2104132
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Sample ID: 2104303-002AMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 4/26/2021	RunNo: 66848							
Client ID: BATCH	Batch ID: 32091		Analysis Date: 4/26/2021	SeqNo: 1346071							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	474	48.6	486.4	0	97.3	61.4	129	540.3	13.2	30	
Surr: 2-Fluorobiphenyl	8.78		9.729		90.2	50	150		0		
Surr: o-Terphenyl	9.59		9.729		98.6	50	150		0		

Work Order: 2104132
 CLIENT: Shannon & Wilson
 Project: Cascade Mill Parkway

QC SUMMARY REPORT
Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Sample ID: MB-31963	SampType: MBLK	Units: µg/Kg	Prep Date: 4/13/2021	RunNo: 66578							
Client ID: MBLKS	Batch ID: 31963		Analysis Date: 4/14/2021	SeqNo: 1340147							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Naphthalene	ND	20.0									
2-Methylnaphthalene	ND	20.0									
1-Methylnaphthalene	ND	20.0									
Acenaphthene	ND	20.0									
Acenaphthylene	ND	20.0									
Fluorene	ND	20.0									
Pentachlorophenol	ND	80.0									
Phenanthrene	ND	40.0									
Anthracene	ND	40.0									
Fluoranthene	ND	40.0									
Pyrene	ND	40.0									
Benz(a)anthracene	ND	20.0									
Chrysene	ND	40.0									
Benzo(b)fluoranthene	ND	20.0									
Benzo(k)fluoranthene	ND	20.0									
Benzo(a)pyrene	ND	20.0									
Indeno(1,2,3-cd)pyrene	ND	40.0									
Dibenz(a,h)anthracene	ND	40.0									
Benzo(g,h,i)perylene	ND	20.0									
Surr: 2,4,6-Tribromophenol	1,260		2,000		63.2	19.4	153				
Surr: 2-Fluorobiphenyl	912		1,000		91.2	19	135				
Surr: Terphenyl-d14 (surr)	1,040		1,000		104	42.9	156				

Sample ID: LCS-31963	SampType: LCS	Units: µg/Kg	Prep Date: 4/13/2021	RunNo: 66578							
Client ID: LCSS	Batch ID: 31963		Analysis Date: 4/14/2021	SeqNo: 1340148							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Naphthalene	1,680	20.0	2,000	0	83.9	62.7	127				
2-Methylnaphthalene	1,710	20.0	2,000	0	85.6	62.7	132				
1-Methylnaphthalene	1,710	20.0	2,000	0	85.7	61.4	131				

Work Order: 2104132
 CLIENT: Shannon & Wilson
 Project: Cascade Mill Parkway

QC SUMMARY REPORT
Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Sample ID: LCS-31963	SampType: LCS	Units: µg/Kg	Prep Date: 4/13/2021	RunNo: 66578							
Client ID: LCSS	Batch ID: 31963		Analysis Date: 4/14/2021	SeqNo: 1340148							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Acenaphthene	1,660	20.0	2,000	0	83.1	59.2	132				
Acenaphthylene	1,610	20.0	2,000	0	80.5	62	132				
Fluorene	1,750	20.0	2,000	0	87.5	59.1	136				
Pentachlorophenol	1,010	80.0	2,000	0	50.7	5	112				
Phenanthrene	1,790	40.0	2,000	0	89.7	54.1	139				
Anthracene	1,770	40.0	2,000	0	88.7	55.5	136				
Fluoranthene	1,790	40.0	2,000	0	89.6	52.8	149				
Pyrene	1,730	40.0	2,000	0	86.3	53.6	146				
Benz(a)anthracene	1,770	20.0	2,000	0	88.3	49.7	153				
Chrysene	1,850	40.0	2,000	0	92.3	52.6	147				
Benzo(b)fluoranthene	1,900	20.0	2,000	0	95.2	50.6	151				
Benzo(k)fluoranthene	1,780	20.0	2,000	0	89.1	47.1	155				
Benzo(a)pyrene	2,020	20.0	2,000	0	101	48.3	169				
Indeno(1,2,3-cd)pyrene	1,870	40.0	2,000	0	93.3	52.3	145				
Dibenz(a,h)anthracene	1,910	40.0	2,000	0	95.3	53	144				
Benzo(g,h,i)perylene	1,720	20.0	2,000	0	86.0	49.7	144				
Surr: 2,4,6-Tribromophenol	1,860		2,000		93.2	19.4	153				
Surr: 2-Fluorobiphenyl	898		1,000		89.8	19	135				
Surr: Terphenyl-d14 (surr)	1,010		1,000		101	42.9	156				

Sample ID: 2104132-002AMS	SampType: MS	Units: µg/Kg-dry	Prep Date: 4/13/2021	RunNo: 66578							
Client ID: B-10-21/A9@48	Batch ID: 31963		Analysis Date: 4/14/2021	SeqNo: 1340678							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Naphthalene	1,620	19.6	1,962	0	82.5	28.7	139				
2-Methylnaphthalene	1,660	19.6	1,962	0	84.8	43.5	130				
1-Methylnaphthalene	1,660	19.6	1,962	0	84.5	42.6	127				
Acenaphthene	1,590	19.6	1,962	0	81.1	45.1	123				
Acenaphthylene	1,570	19.6	1,962	0	79.9	45.3	129				
Fluorene	1,660	19.6	1,962	0	84.8	41.6	128				

Work Order: 2104132
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Sample ID: 2104132-002AMS	SampType: MS	Units: µg/Kg-dry				Prep Date: 4/13/2021	RunNo: 66578				
Client ID: B-10-21/A9@48	Batch ID: 31963					Analysis Date: 4/14/2021	SeqNo: 1340678				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Pentachlorophenol	1,460	78.5	1,962	0	74.4	5	188				
Phenanthrene	1,720	39.2	1,962	0	87.7	24.2	142				
Anthracene	1,700	39.2	1,962	0	86.6	33.1	143				
Fluoranthene	1,690	39.2	1,962	0	86.2	35.5	147				
Pyrene	1,640	39.2	1,962	0	83.4	38.3	141				
Benz(a)anthracene	1,710	19.6	1,962	0	87.1	42.5	145				
Chrysene	1,710	39.2	1,962	0	86.9	39.7	134				
Benzo(b)fluoranthene	1,830	19.6	1,962	0	93.4	29.9	152				
Benzo(k)fluoranthene	1,650	19.6	1,962	0	84.4	33.2	143.5				
Benzo(a)pyrene	1,920	19.6	1,962	0	97.8	38.2	156				
Indeno(1,2,3-cd)pyrene	1,750	39.2	1,962	0	89.1	41.4	128				
Dibenz(a,h)anthracene	1,790	39.2	1,962	0	91.5	40.4	129				
Benzo(g,h,i)perylene	1,600	19.6	1,962	0	81.7	34.2	131				
Surr: 2,4,6-Tribromophenol	1,750		1,962		89.4	19.4	153				
Surr: 2-Fluorobiphenyl	863		980.9		88.0	19	135				
Surr: Terphenyl-d14 (surr)	935		980.9		95.3	42.9	156				

Sample ID: 2104132-002AMSD	SampType: MSD	Units: µg/Kg-dry				Prep Date: 4/13/2021	RunNo: 66578				
Client ID: B-10-21/A9@48	Batch ID: 31963					Analysis Date: 4/14/2021	SeqNo: 1340679				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	1,730	20.9	2,093	0	82.4	28.7	139	1,619	6.34	30	
2-Methylnaphthalene	1,750	20.9	2,093	0	83.5	43.5	130	1,664	4.85	30	
1-Methylnaphthalene	1,750	20.9	2,093	0	83.6	42.6	127	1,657	5.42	30	
Acenaphthene	1,690	20.9	2,093	0	80.8	45.1	123	1,590	6.21	30	
Acenaphthylene	1,660	20.9	2,093	0	79.4	45.3	129	1,567	5.88	30	
Fluorene	1,760	20.9	2,093	0	84.3	41.6	128	1,664	5.83	30	
Pentachlorophenol	1,580	83.7	2,093	0	75.4	5	188	1,460	7.80	30	
Phenanthrene	1,800	41.9	2,093	0	86.1	24.2	142	1,721	4.66	30	
Anthracene	1,790	41.9	2,093	0	85.6	33.1	143	1,700	5.28	30	

Work Order: 2104132
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Sample ID: 2104132-002AMSD	SampType: MSD	Units: µg/Kg-dry	Prep Date: 4/13/2021	RunNo: 66578							
Client ID: B-10-21/A9@48	Batch ID: 31963		Analysis Date: 4/14/2021	SeqNo: 1340679							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Fluoranthene	1,790	41.9	2,093	0	85.5	35.5	147	1,690	5.69	30	
Pyrene	1,730	41.9	2,093	0	82.6	38.3	141	1,636	5.52	30	
Benz(a)anthracene	1,780	20.9	2,093	0	85.2	42.5	145	1,709	4.25	30	
Chrysene	1,810	41.9	2,093	0	86.5	39.7	134	1,705	5.94	30	
Benzo(b)fluoranthene	1,740	20.9	2,093	0	83.2	29.9	152	1,832	5.09	30	
Benzo(k)fluoranthene	1,930	20.9	2,093	0	92.2	33.2	143.5	1,655	15.4	30	
Benzo(a)pyrene	2,010	20.9	2,093	0	96.1	38.2	156	1,918	4.73	30	
Indeno(1,2,3-cd)pyrene	1,860	41.9	2,093	0	88.9	41.4	128	1,747	6.25	30	
Dibenz(a,h)anthracene	1,910	41.9	2,093	0	91.4	40.4	129	1,794	6.37	30	
Benzo(g,h,i)perylene	1,710	20.9	2,093	0	81.6	34.2	131	1,602	6.41	30	
Surr: 2,4,6-Tribromophenol	1,800		2,093		86.2	19.4	153		0		
Surr: 2-Fluorobiphenyl	913		1,047		87.2	19	135		0		
Surr: Terphenyl-d14 (surr)	995		1,047		95.1	42.9	156		0		

Sample ID: MB-32072	SampType: MBLK	Units: µg/Kg	Prep Date: 4/23/2021	RunNo: 66790							
Client ID: MBLKS	Batch ID: 32072		Analysis Date: 4/26/2021	SeqNo: 1344826							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	ND	20.0									
2-Methylnaphthalene	ND	20.0									
1-Methylnaphthalene	ND	20.0									
Acenaphthene	ND	20.0									
Acenaphthylene	ND	20.0									
Fluorene	ND	20.0									
Pentachlorophenol	ND	80.0									
Phenanthrene	ND	40.0									
Anthracene	ND	40.0									
Fluoranthene	ND	40.0									
Pyrene	ND	40.0									
Benz(a)anthracene	ND	20.0									

Work Order: 2104132
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Sample ID: MB-32072	SampType: MBLK	Units: µg/Kg		Prep Date: 4/23/2021	RunNo: 66790						
Client ID: MBLKS	Batch ID: 32072			Analysis Date: 4/26/2021	SeqNo: 1344826						
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Chrysene	ND	40.0									
Benzo(b)fluoranthene	ND	20.0									
Benzo(k)fluoranthene	ND	20.0									
Benzo(a)pyrene	ND	20.0									
Indeno(1,2,3-cd)pyrene	ND	40.0									
Dibenz(a,h)anthracene	ND	40.0									
Benzo(g,h,i)perylene	ND	20.0									
Surr: 2,4,6-Tribromophenol	794		2,000		39.7	19.4	153				
Surr: 2-Fluorobiphenyl	616		1,000		61.6	19	135				
Surr: Terphenyl-d14 (surr)	768		1,000		76.8	42.9	156				

Sample ID: LCS-32072	SampType: LCS	Units: µg/Kg		Prep Date: 4/23/2021	RunNo: 66790						
Client ID: LCSS	Batch ID: 32072			Analysis Date: 4/26/2021	SeqNo: 1344827						
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	1,500	20.0	2,000	0	75.1	62.7	127				
2-Methylnaphthalene	1,490	20.0	2,000	0	74.4	62.7	132				
1-Methylnaphthalene	1,510	20.0	2,000	0	75.6	61.4	131				
Acenaphthene	1,480	20.0	2,000	0	74.2	59.2	132				
Acenaphthylene	1,450	20.0	2,000	0	72.6	62	132				
Fluorene	1,540	20.0	2,000	0	77.1	59.1	136				
Pentachlorophenol	978	80.0	2,000	0	48.9	5	112				
Phenanthrene	1,550	40.0	2,000	0	77.6	54.1	139				
Anthracene	1,520	40.0	2,000	0	75.9	55.5	136				
Fluoranthene	1,540	40.0	2,000	0	77.2	52.8	149				
Pyrene	1,490	40.0	2,000	0	74.3	53.6	146				
Benz(a)anthracene	1,550	20.0	2,000	0	77.3	49.7	153				
Chrysene	1,550	40.0	2,000	0	77.7	52.6	147				
Benzo(b)fluoranthene	1,460	20.0	2,000	0	73.2	50.6	151				
Benzo(k)fluoranthene	1,660	20.0	2,000	0	82.9	47.1	155				

Work Order: 2104132
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Sample ID: LCS-32072	SampType: LCS	Units: µg/Kg	Prep Date: 4/23/2021	RunNo: 66790							
Client ID: LCSS	Batch ID: 32072		Analysis Date: 4/26/2021	SeqNo: 1344827							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzo(a)pyrene	1,680	20.0	2,000	0	84.2	48.3	169				
Indeno(1,2,3-cd)pyrene	1,610	40.0	2,000	0	80.6	52.3	145				
Dibenz(a,h)anthracene	1,650	40.0	2,000	0	82.4	53	144				
Benzo(g,h,i)perylene	1,510	20.0	2,000	0	75.6	49.7	144				
Surr: 2,4,6-Tribromophenol	1,500		2,000		74.8	19.4	153				
Surr: 2-Fluorobiphenyl	651		1,000		65.1	19	135				
Surr: Terphenyl-d14 (surr)	807		1,000		80.7	42.9	156				

Sample ID: 2104252-002AMS	SampType: MS	Units: µg/Kg-dry	Prep Date: 4/23/2021	RunNo: 66790							
Client ID: BATCH	Batch ID: 32072		Analysis Date: 4/26/2021	SeqNo: 1344830							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	1,390	25.0	2,496	0	55.5	28.7	139				
2-Methylnaphthalene	1,430	25.0	2,496	0	57.2	43.5	130				
1-Methylnaphthalene	1,430	25.0	2,496	0	57.3	42.6	127				
Acenaphthene	1,380	25.0	2,496	0	55.1	45.1	123				
Acenaphthylene	1,360	25.0	2,496	0	54.3	45.3	129				
Fluorene	1,450	25.0	2,496	0	57.9	41.6	128				
Pentachlorophenol	1,380	99.8	2,496	0	55.2	5	188				
Phenanthrene	1,430	49.9	2,496	0	57.5	24.2	142				
Anthracene	1,440	49.9	2,496	0	57.7	33.1	143				
Fluoranthene	1,460	49.9	2,496	0	58.5	35.5	147				
Pyrene	1,390	49.9	2,496	0	55.9	38.3	141				
Benz(a)anthracene	1,470	25.0	2,496	0	58.8	42.5	145				
Chrysene	1,430	49.9	2,496	0	57.3	39.7	134				
Benzo(b)fluoranthene	1,480	25.0	2,496	0	59.1	29.9	152				
Benzo(k)fluoranthene	1,450	25.0	2,496	0	58.2	33.2	143.5				
Benzo(a)pyrene	1,580	25.0	2,496	0	63.4	38.2	156				
Indeno(1,2,3-cd)pyrene	1,490	49.9	2,496	0	59.7	41.4	128				
Dibenz(a,h)anthracene	1,530	49.9	2,496	0	61.2	40.4	129				

Work Order: 2104132
 CLIENT: Shannon & Wilson
 Project: Cascade Mill Parkway

QC SUMMARY REPORT
Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Sample ID: 2104252-002AMS	SampType: MS	Units: µg/Kg-dry	Prep Date: 4/23/2021	RunNo: 66790							
Client ID: BATCH	Batch ID: 32072		Analysis Date: 4/26/2021	SeqNo: 1344830							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Benzo(g,h,i)perylene	1,380	25.0	2,496	0	55.1	34.2	131				
Surr: 2,4,6-Tribromophenol	1,490		2,496		59.8	19.4	153				
Surr: 2-Fluorobiphenyl	659		1,248		52.8	19	135				
Surr: Terphenyl-d14 (surr)	779		1,248		62.4	42.9	156				

Sample ID: 2104252-002AMSD	SampType: MSD	Units: µg/Kg-dry	Prep Date: 4/23/2021	RunNo: 66790							
Client ID: BATCH	Batch ID: 32072		Analysis Date: 4/26/2021	SeqNo: 1344831							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Naphthalene	1,600	24.7	2,474	0	64.6	28.7	139	1,386	14.2	30	
2-Methylnaphthalene	1,640	24.7	2,474	0	66.2	43.5	130	1,428	13.7	30	
1-Methylnaphthalene	1,640	24.7	2,474	0	66.1	42.6	127	1,430	13.4	30	
Acenaphthene	1,580	24.7	2,474	0	63.8	45.1	123	1,375	13.8	30	
Acenaphthylene	1,560	24.7	2,474	0	62.9	45.3	129	1,355	13.8	30	
Fluorene	1,650	24.7	2,474	0	66.8	41.6	128	1,446	13.3	30	
Pentachlorophenol	1,450	99.0	2,474	0	58.5	5	188	1,378	4.90	30	
Phenanthrene	1,640	49.5	2,474	0	66.5	24.2	142	1,434	13.7	30	
Anthracene	1,620	49.5	2,474	0	65.3	33.1	143	1,440	11.6	30	
Fluoranthene	1,660	49.5	2,474	0	66.9	35.5	147	1,460	12.5	30	
Pyrene	1,590	49.5	2,474	0	64.2	38.3	141	1,394	13.0	30	
Benz(a)anthracene	1,660	24.7	2,474	0	67.0	42.5	145	1,468	12.1	30	
Chrysene	1,610	49.5	2,474	0	64.9	39.7	134	1,431	11.5	30	
Benzo(b)fluoranthene	1,730	24.7	2,474	0	69.8	29.9	152	1,476	15.6	30	
Benzo(k)fluoranthene	1,550	24.7	2,474	0	62.5	33.2	143.5	1,453	6.20	30	
Benzo(a)pyrene	1,780	24.7	2,474	0	72.1	38.2	156	1,583	12.0	30	
Indeno(1,2,3-cd)pyrene	1,690	49.5	2,474	0	68.2	41.4	128	1,491	12.4	30	
Dibenz(a,h)anthracene	1,730	49.5	2,474	0	69.8	40.4	129	1,527	12.2	30	
Benzo(g,h,i)perylene	1,560	24.7	2,474	0	63.1	34.2	131	1,377	12.6	30	
Surr: 2,4,6-Tribromophenol	1,600		2,474		64.7	19.4	153		0		
Surr: 2-Fluorobiphenyl	737		1,237		59.6	19	135		0		

Work Order: 2104132
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Sample ID: 2104252-002AMSD	SampType: MSD	Units: µg/Kg-dry	Prep Date: 4/23/2021	RunNo: 66790							
Client ID: BATCH	Batch ID: 32072		Analysis Date: 4/26/2021	SeqNo: 1344831							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Surr: Terphenyl-d14 (surr)	846		1,237		68.4	42.9	156		0		

Work Order: 2104132
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Gasoline by NWTPH-Gx

Sample ID: LCS-31943	SampType: LCS	Units: mg/Kg			Prep Date: 4/9/2021	RunNo: 66481					
Client ID: LCSS	Batch ID: 31943				Analysis Date: 4/9/2021	SeqNo: 1337620					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	24.9	5.00	25.00	0	99.6	65	135				
Surr: Toluene-d8	1.17		1.250		93.6	65	135				
Surr: 4-Bromofluorobenzene	1.35		1.250		108	65	135				

Sample ID: MB-31943	SampType: MBLK	Units: mg/Kg			Prep Date: 4/9/2021	RunNo: 66481					
Client ID: MBLKS	Batch ID: 31943				Analysis Date: 4/9/2021	SeqNo: 1337621					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	ND	5.00									
Surr: Toluene-d8	1.19		1.250		95.2	65	135				
Surr: 4-Bromofluorobenzene	1.26		1.250		101	65	135				

Sample ID: 2104137-001BDUP	SampType: DUP	Units: mg/Kg-dry			Prep Date: 4/9/2021	RunNo: 66481					
Client ID: BATCH	Batch ID: 31943				Analysis Date: 4/9/2021	SeqNo: 1337617					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	ND	5.50						0		30	
Surr: Toluene-d8	1.25		1.375		90.9	65	135		0		
Surr: 4-Bromofluorobenzene	1.37		1.375		99.8	65	135		0		

Sample ID: 2104132-003BMS	SampType: MS	Units: mg/Kg-dry			Prep Date: 4/9/2021	RunNo: 66481					
Client ID: B-9-21/R-10@48	Batch ID: 31943				Analysis Date: 4/10/2021	SeqNo: 1337615					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	82.2	5.37	26.87	0	306	65	135				S
Surr: Toluene-d8	1.31		1.344		97.6	65	135				
Surr: 4-Bromofluorobenzene	1.38		1.344		103	65	135				

NOTES:

S - Outlying spike recovery observed (high bias). Samples are non-detect for this analyte; no further action required.

Work Order: 2104132
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Gasoline by NWTPH-Gx

Sample ID: LCS-32073	SampType: LCS	Units: mg/Kg			Prep Date: 4/23/2021	RunNo: 66784					
Client ID: LCSS	Batch ID: 32073				Analysis Date: 4/23/2021	SeqNo: 1344765					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	23.6	5.00	25.00	0	94.3	65	135				
Surr: Toluene-d8	1.25		1.250		100	65	135				
Surr: 4-Bromofluorobenzene	1.33		1.250		106	65	135				

Sample ID: MB-32073	SampType: MBLK	Units: mg/Kg			Prep Date: 4/23/2021	RunNo: 66784					
Client ID: MBLKS	Batch ID: 32073				Analysis Date: 4/23/2021	SeqNo: 1344764					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	ND	5.00									
Surr: Toluene-d8	1.20		1.250		96.0	65	135				
Surr: 4-Bromofluorobenzene	1.22		1.250		97.3	65	135				

Sample ID: 2104274-013BDUP	SampType: DUP	Units: mg/Kg-dry			Prep Date: 4/23/2021	RunNo: 66784					
Client ID: BATCH	Batch ID: 32073				Analysis Date: 4/23/2021	SeqNo: 1344736					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	ND	5.09						0		30	
Surr: Toluene-d8	1.22		1.273		95.7	65	135		0		
Surr: 4-Bromofluorobenzene	1.27		1.273		99.9	65	135		0		

Sample ID: 2104292-001BDUP	SampType: DUP	Units: mg/Kg-dry			Prep Date: 4/23/2021	RunNo: 66784					
Client ID: BATCH	Batch ID: 32073				Analysis Date: 4/23/2021	SeqNo: 1344742					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	ND	12.2						0		30	
Surr: Toluene-d8	2.99		3.058		97.7	65	135		0		
Surr: 4-Bromofluorobenzene	2.95		3.058		96.6	65	135		0		

Work Order: 2104132
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Gasoline by NWTPH-Gx

Sample ID: 2104274-015BMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 4/23/2021	RunNo: 66784							
Client ID: BATCH	Batch ID: 32073	Analysis Date: 4/23/2021	SeqNo: 1344738								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Gasoline	20.2	4.67	23.33	0	86.8	65	135				
Surr: Toluene-d8	1.18		1.167		101	65	135				
Surr: 4-Bromofluorobenzene	1.22		1.167		105	65	135				

Work Order: 2104132
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260D

Sample ID: LCS-31943	SampType: LCS	Units: µg/L				Prep Date: 4/9/2021	RunNo: 66479				
Client ID: LCSS	Batch ID: 31943					Analysis Date: 4/9/2021	SeqNo: 1337596				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	0.942	0.0200	1.000	0	94.2	80	120				
Toluene	0.973	0.0650	1.000	0	97.3	80	120				
Ethylbenzene	1.05	0.0250	1.000	0	105	80	120				
m,p-Xylene	2.00	0.0500	2.000	0	99.9	80	120				
o-Xylene	0.995	0.0250	1.000	0	99.5	80	120				
Surr: Dibromofluoromethane	1.02		1.250		81.5	80	120				
Surr: Toluene-d8	1.21		1.250		96.6	80	120				
Surr: 1-Bromo-4-fluorobenzene	1.26		1.250		101	80	120				

Sample ID: MB-31943	SampType: MBLK	Units: mg/Kg				Prep Date: 4/9/2021	RunNo: 66479				
Client ID: MBLKS	Batch ID: 31943					Analysis Date: 4/9/2021	SeqNo: 1337595				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	ND	0.0200									
Toluene	ND	0.0650									
Ethylbenzene	ND	0.0250									
m,p-Xylene	ND	0.0500									
o-Xylene	ND	0.0250									
Surr: Dibromofluoromethane	0.953		1.250		76.3	82.3	112				S
Surr: Toluene-d8	1.30		1.250		104	90.7	109				
Surr: 1-Bromo-4-fluorobenzene	1.25		1.250		99.7	88.4	109				

Sample ID: 2104137-001BDUP	SampType: DUP	Units: mg/Kg-dry				Prep Date: 4/9/2021	RunNo: 66479				
Client ID: BATCH	Batch ID: 31943					Analysis Date: 4/9/2021	SeqNo: 1337590				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	ND	0.0220						0		30	
Toluene	ND	0.0715						0		30	
Ethylbenzene	ND	0.0275						0		30	

Work Order: 2104132
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260D

Sample ID: 2104137-001BDUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 4/9/2021	RunNo: 66479							
Client ID: BATCH	Batch ID: 31943		Analysis Date: 4/9/2021	SeqNo: 1337590							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
m,p-Xylene	ND	0.0550						0		30	
o-Xylene	ND	0.0275						0		30	
Surr: Dibromofluoromethane	1.06		1.375		77.1	82.3	112		0		S
Surr: Toluene-d8	1.39		1.375		101	90.7	109		0		
Surr: 1-Bromo-4-fluorobenzene	1.36		1.375		98.5	88.4	109		0		
NOTES: S - Outlying surrogate recovery(ies) observed.											

Sample ID: 2104137-002BMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 4/9/2021	RunNo: 66479							
Client ID: BATCH	Batch ID: 31943		Analysis Date: 4/10/2021	SeqNo: 1337592							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	1.09	0.0249	1.247	0	87.3	76.8	129				
Toluene	1.24	0.0811	1.247	0	99.1	77.8	127				
Ethylbenzene	1.30	0.0312	1.247	0	104	78.7	130				
m,p-Xylene	2.41	0.0624	2.494	0	96.7	79.3	127				
o-Xylene	1.20	0.0312	1.247	0	96.3	80.7	124				
Surr: Dibromofluoromethane	0.644		1.559		41.3	82.3	112				S
Surr: Toluene-d8	1.59		1.559		102	90.7	109				
Surr: 1-Bromo-4-fluorobenzene	1.56		1.559		100	88.4	109				
NOTES: S - Outlying surrogate recovery(ies) observed.											

Sample ID: LCS-32073	SampType: LCS	Units: mg/Kg	Prep Date: 4/23/2021	RunNo: 66783							
Client ID: LCSS	Batch ID: 32073		Analysis Date: 4/23/2021	SeqNo: 1344702							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	0.969	0.0200	1.000	0	96.9	80	120				
Toluene	0.999	0.0650	1.000	0	99.9	80	120				
Ethylbenzene	1.00	0.0250	1.000	0	100	80	120				
m,p-Xylene	2.01	0.0500	2.000	0	100	80	120				

Work Order: 2104132
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260D

Sample ID: LCS-32073	SampType: LCS	Units: mg/Kg	Prep Date: 4/23/2021	RunNo: 66783							
Client ID: LCSS	Batch ID: 32073		Analysis Date: 4/23/2021	SeqNo: 1344702							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

o-Xylene	0.990	0.0250	1.000	0	99.0	80	120				
Surr: Dibromofluoromethane	1.20		1.250		95.7	80	120				
Surr: Toluene-d8	1.26		1.250		101	80	120				
Surr: 1-Bromo-4-fluorobenzene	1.29		1.250		103	80	120				

Sample ID: MB-32073	SampType: MBLK	Units: mg/Kg	Prep Date: 4/23/2021	RunNo: 66783							
Client ID: MBLKS	Batch ID: 32073		Analysis Date: 4/23/2021	SeqNo: 1344700							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Benzene	ND	0.0200									
Toluene	ND	0.0650									
Ethylbenzene	ND	0.0250									
m,p-Xylene	ND	0.0500									
o-Xylene	ND	0.0250									
Surr: Dibromofluoromethane	1.20		1.250		95.9	81.9	113				
Surr: Toluene-d8	1.21		1.250		96.6	82.7	115				
Surr: 1-Bromo-4-fluorobenzene	1.26		1.250		101	87.9	109				

Sample ID: 2104274-013BDUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 4/23/2021	RunNo: 66783							
Client ID: BATCH	Batch ID: 32073		Analysis Date: 4/23/2021	SeqNo: 1344676							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Benzene	ND	0.0204						0		30	
Toluene	ND	0.0662						0		30	
Ethylbenzene	ND	0.0255						0		30	
m,p-Xylene	ND	0.0509						0		30	
o-Xylene	ND	0.0255						0		30	
Surr: Dibromofluoromethane	1.24		1.273		97.4	81.9	113		0		
Surr: Toluene-d8	1.23		1.273		96.3	82.7	115		0		

Work Order: 2104132
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260D

Sample ID: 2104274-013BDUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 4/23/2021	RunNo: 66783							
Client ID: BATCH	Batch ID: 32073		Analysis Date: 4/23/2021	SeqNo: 1344676							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Surr: 1-Bromo-4-fluorobenzene	1.30		1.273		102	87.9	109		0		
-------------------------------	------	--	-------	--	-----	------	-----	--	---	--	--

Sample ID: 2104292-001BDUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 4/23/2021	RunNo: 66783							
Client ID: BATCH	Batch ID: 32073		Analysis Date: 4/23/2021	SeqNo: 1344682							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Benzene	ND	0.0489						0		30	
Toluene	ND	0.159						0		30	
Ethylbenzene	ND	0.0612						0		30	
m,p-Xylene	ND	0.122						0		30	
o-Xylene	ND	0.0612						0		30	
Surr: Dibromofluoromethane	2.97		3.058		97.3	81.9	113		0		
Surr: Toluene-d8	2.93		3.058		95.8	82.7	115		0		
Surr: 1-Bromo-4-fluorobenzene	3.06		3.058		100	87.9	109		0		

Sample ID: 2104274-015BMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 4/23/2021	RunNo: 66783							
Client ID: BATCH	Batch ID: 32073		Analysis Date: 4/23/2021	SeqNo: 1344678							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Benzene	0.922	0.0187	0.9333	0	98.8	76.8	129				
Toluene	0.956	0.0607	0.9333	0	102	77.8	127				
Ethylbenzene	0.986	0.0233	0.9333	0	106	78.7	130				
m,p-Xylene	1.99	0.0467	1.867	0	106	79.3	127				
o-Xylene	0.970	0.0233	0.9333	0	104	80.7	124				
Surr: Dibromofluoromethane	1.09		1.167		93.3	81.9	113				
Surr: Toluene-d8	1.17		1.167		100	82.7	115				
Surr: 1-Bromo-4-fluorobenzene	1.20		1.167		103	87.9	109				

Client Name: **SW**

 Work Order Number: **2104132**

 Logged by: **Gabrielle Coeulle**

 Date Received: **4/8/2021 5:37:00 PM**

Chain of Custody

1. Is Chain of Custody complete? Yes No Not Present
2. How was the sample delivered? Client

Log In

3. Coolers are present? Yes No NA
4. Shipping container/cooler in good condition? Yes No
5. Custody Seals present on shipping container/cooler?
(Refer to comments for Custody Seals not intact) Yes No Not Present
6. Was an attempt made to cool the samples? Yes No NA
7. Were all items received at a temperature of >2°C to 6°C * Yes No NA
8. Sample(s) in proper container(s)? Yes No
9. Sufficient sample volume for indicated test(s)? Yes No
10. Are samples properly preserved? Yes No
11. Was preservative added to bottles? Yes No NA
12. Is there headspace in the VOA vials? Yes No NA
13. Did all samples containers arrive in good condition(unbroken)? Yes No
14. Does paperwork match bottle labels? Yes No
15. Are matrices correctly identified on Chain of Custody? Yes No
16. Is it clear what analyses were requested? Yes No
17. Were all holding times able to be met? Yes No

Special Handling (if applicable)

18. Was client notified of all discrepancies with this order? Yes No NA

Person Notified:	<input type="text" value="David Randall"/>	Date:	<input type="text" value="4/22/2021"/>
By Whom:	<input type="text" value="Gabrielle Coeulle"/>	Via:	<input type="checkbox"/> eMail <input checked="" type="checkbox"/> Phone <input type="checkbox"/> Fax <input type="checkbox"/> In Person
Regarding:	<input type="text" value="Ok to run sample 1 out of hold for Dx, PAHs, and Gx/BTEX?"/>		
Client Instructions:	<input type="text" value="Yes."/>		

19. Additional remarks:

Item Information

Item #	Temp °C
Sample 1	3.5

* Note: DoD/ELAP and TNI require items to be received at 4°C +/- 2°C



3600 Fremont Ave N.
Seattle, WA 98103
Tel: 206-352-3790
Fax: 206-352-7178

Chain of Custody Record & Laboratory Services Agreement

Date: 4/7/21 Page: 1 of 1

Project Name: CASCADE MILL PARKWAY

Project No: 106384

Collected by: KXM

Location: YAKIMA

Report To (PM): DAVID PAQUALE


PM Email: DPA@SHANNON.COM

Laboratory Project No (Internal): 2104132

Special Remarks:

Sample Disposal: Return to client Disposal by lab (after 30 days)

Sample Name	Sample Date	Sample Time	Sample Type (Matrix)*	VOCs (EPA 8260 / 624)	GX/BTEX	BTEX	Gasoline Range Organics (GX)	Hydrocarbon Identification (HCD)	Diesel/Heavy Oil Range Organics (DH)	SVOCs (EPA 8270 / 625)	PAHs (EPA 8270 - SIM) + PCB	PCBs (EPA 8082 / 608)	Metals** (EPA 6020 / 200.8)	Total (T) / Dissolved (D)	Anions (IC)***	EDB (8011)	Comments
1 B-10-21/5-3@15.5	4/5/21	2305		X	X	X	X	X	X	X	X	X	X				Hold for analysis
2 B-10-21/AG@48	4/6/21	2230		X	X	X	X	X	X	X	X	X	X				
3 B-9-21/R-10@48	4/7/21	2305		X	X	X	X	X	X	X	X	X	X				
4																	
5																	
6																	
7																	
8																	
9																	
10																	



*Matrix: A = Air, AQ = Aqueous, B = Bulk, O = Other, P = Product, S = Soil, SD = Sediment, SL = Solid, W = Water, DW = Drinking Water, GW = Ground Water, SW = Storm Water, WW = Waste Water

**Metals (Circle): MTCA-5 (RCRA-8) Priority Pollutants TAL Individual: Ag Al As B Ba Be Ca Cd Co Cr Cu Fe Hg K Mg Mn Mo Na Ni Pb Sb Se Sr Sn Tl U V Zn

***Anions (Circle): Nitrate Nitrite Chloride Sulfate Bromide Iodide Nitrate-Nitrite Fluoride

I represent that I am authorized to enter into this Agreement with Fremont Analytical on behalf of the Client named above and that I have verified Client's agreement to each of the terms on the front and backside of this Agreement.

Relinquished	Date/Time	Received	Date/Time
<i>[Signature]</i>	4/8/21 17:20	<i>[Signature]</i>	4/8/21 7:20
<i>[Signature]</i>	4/8/21	<i>[Signature]</i>	4/18/21 @ 17:37

Turn-around Time:

- Standard
- 3 Day
- 2 Day
- Next Day
- Same Day (specify)



Shannon & Wilson

Dave Randall

400 N. 34th Street, Suite 100

Seattle, WA 98103

RE: Cascade Mill Parkway

Work Order Number: 2104041

April 09, 2021

Attention Dave Randall:

Fremont Analytical, Inc. received 2 sample(s) on 4/2/2021 for the analyses presented in the following report.

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Gasoline by NWTPH-Gx

Mercury by EPA Method 7471

Sample Moisture (Percent Moisture)

Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Total Metals by EPA Method 6020B

Volatile Organic Compounds by EPA Method 8260D

This report consists of the following:

- Case Narrative
- Analytical Results
- Applicable Quality Control Summary Reports
- Chain of Custody

All analyses were performed consistent with the Quality Assurance program of Fremont Analytical, Inc. Please contact the laboratory if you should have any questions about the results.

Thank you for using Fremont Analytical.

Sincerely,

Brianna Barnes
Project Manager

*DoD-ELAP Accreditation #79636 by PJLA, ISO/IEC 17025:2017 and QSM 5.3 for Environmental Testing
ORELAP Certification: WA 100009 (NELAP Recognized) for Environmental Testing
Washington State Department of Ecology Accredited for Environmental Testing, Lab ID C910*

Original



Date: 04/09/2021

CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway
Work Order: 2104041

Work Order Sample Summary

Lab Sample ID	Client Sample ID	Date/Time Collected	Date/Time Received
2104041-001	B-11P-21/R-10@51'	03/30/2021 1:30 AM	04/02/2021 5:31 PM
2104041-002	B-12P-21/R-11@50'	04/01/2021 1:15 AM	04/02/2021 5:31 PM

Note: If no "Time Collected" is supplied, a default of 12:00AM is assigned

CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

I. SAMPLE RECEIPT:

Samples receipt information is recorded on the attached Sample Receipt Checklist.

II. GENERAL REPORTING COMMENTS:

Results are reported on a wet weight basis unless dry-weight correction is denoted in the units field on the analytical report ("mg/kg-dry" or "ug/kg-dry").

Matrix Spike (MS) and MS Duplicate (MSD) samples are tested from an analytical batch of "like" matrix to check for possible matrix effect. The MS and MSD will provide site specific matrix data only for those samples which are spiked by the laboratory. The sample chosen for spike purposes may or may not have been a sample submitted in this sample delivery group. The validity of the analytical procedures for which data is reported in this analytical report is determined by the Laboratory Control Sample (LCS) and the Method Blank (MB). The LCS and the MB are processed with the samples and the MS/MSD to ensure method criteria are achieved throughout the entire analytical process.

III. ANALYSES AND EXCEPTIONS:

Exceptions associated with this report will be footnoted in the analytical results page(s) or the quality control summary page(s) and/or noted below.

Qualifiers:

- * - Flagged value is not within established control limits
- B - Analyte detected in the associated Method Blank
- D - Dilution was required
- E - Value above quantitation range
- H - Holding times for preparation or analysis exceeded
- I - Analyte with an internal standard that does not meet established acceptance criteria
- J - Analyte detected below Reporting Limit
- N - Tentatively Identified Compound (TIC)
- Q - Analyte with an initial or continuing calibration that does not meet established acceptance criteria
- S - Spike recovery outside accepted recovery limits
- ND - Not detected at the Reporting Limit
- R - High relative percent difference observed

Acronyms:

- %Rec - Percent Recovery
- CCB - Continued Calibration Blank
- CCV - Continued Calibration Verification
- DF - Dilution Factor
- DUP - Sample Duplicate
- HEM - Hexane Extractable Material
- ICV - Initial Calibration Verification
- LCS/LCSD - Laboratory Control Sample / Laboratory Control Sample Duplicate
- MCL - Maximum Contaminant Level
- MB or MBLANK - Method Blank
- MDL - Method Detection Limit
- MS/MSD - Matrix Spike / Matrix Spike Duplicate
- PDS - Post Digestion Spike
- Ref Val - Reference Value
- REP - Sample Replicate
- RL - Reporting Limit
- RPD - Relative Percent Difference
- SD - Serial Dilution
- SGT - Silica Gel Treatment
- SPK - Spike
- Surr - Surrogate



Analytical Report

Work Order: 2104041
Date Reported: 4/9/2021

Client: Shannon & Wilson
Project: Cascade Mill Parkway
Lab ID: 2104041-001
Client Sample ID: B-11P-21/R-10@51'

Collection Date: 3/30/2021 1:30:00 AM
Matrix: Soil

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Batch ID: 31906 Analyst: MM

Diesel (Fuel Oil)	ND	46.8		mg/Kg-dry	1	4/8/2021 9:28:22 AM
Heavy Oil	ND	93.6		mg/Kg-dry	1	4/8/2021 9:28:22 AM
Total Petroleum Hydrocarbons	ND	70.2		mg/Kg-dry	1	4/8/2021 9:28:22 AM
Surr: 2-Fluorobiphenyl	82.0	50 - 150		%Rec	1	4/8/2021 9:28:22 AM
Surr: o-Terphenyl	90.4	50 - 150		%Rec	1	4/8/2021 9:28:22 AM

Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Batch ID: 31880 Analyst: IH

Naphthalene	ND	19.0		µg/Kg-dry	1	4/6/2021 2:58:16 PM
2-Methylnaphthalene	ND	19.0		µg/Kg-dry	1	4/6/2021 2:58:16 PM
1-Methylnaphthalene	ND	19.0		µg/Kg-dry	1	4/6/2021 2:58:16 PM
Acenaphthene	ND	19.0		µg/Kg-dry	1	4/6/2021 2:58:16 PM
Acenaphthylene	ND	19.0		µg/Kg-dry	1	4/6/2021 2:58:16 PM
Fluorene	ND	19.0		µg/Kg-dry	1	4/6/2021 2:58:16 PM
Pentachlorophenol	ND	75.9		µg/Kg-dry	1	4/6/2021 2:58:16 PM
Phenanthrene	ND	37.9		µg/Kg-dry	1	4/6/2021 2:58:16 PM
Anthracene	ND	37.9		µg/Kg-dry	1	4/6/2021 2:58:16 PM
Fluoranthene	ND	37.9		µg/Kg-dry	1	4/6/2021 2:58:16 PM
Pyrene	ND	37.9		µg/Kg-dry	1	4/6/2021 2:58:16 PM
Benz(a)anthracene	ND	19.0		µg/Kg-dry	1	4/6/2021 2:58:16 PM
Chrysene	ND	37.9		µg/Kg-dry	1	4/6/2021 2:58:16 PM
Benzo(b)fluoranthene	ND	19.0		µg/Kg-dry	1	4/6/2021 2:58:16 PM
Benzo(k)fluoranthene	ND	19.0		µg/Kg-dry	1	4/6/2021 2:58:16 PM
Benzo(a)pyrene	ND	19.0		µg/Kg-dry	1	4/6/2021 2:58:16 PM
Indeno(1,2,3-cd)pyrene	ND	37.9		µg/Kg-dry	1	4/6/2021 2:58:16 PM
Dibenz(a,h)anthracene	ND	37.9		µg/Kg-dry	1	4/6/2021 2:58:16 PM
Benzo(g,h,i)perylene	ND	19.0		µg/Kg-dry	1	4/6/2021 2:58:16 PM
Surr: 2,4,6-Tribromophenol	79.6	19.4 - 153		%Rec	1	4/6/2021 2:58:16 PM
Surr: 2-Fluorobiphenyl	64.5	19 - 135		%Rec	1	4/6/2021 2:58:16 PM
Surr: Terphenyl-d14 (surr)	78.8	42.9 - 156		%Rec	1	4/6/2021 2:58:16 PM

Gasoline by NWTPH-Gx

Batch ID: 31908 Analyst: CR

Gasoline	ND	4.44		mg/Kg-dry	1	4/7/2021 10:03:10 PM
Surr: Toluene-d8	99.6	65 - 135		%Rec	1	4/7/2021 10:03:10 PM
Surr: 4-Bromofluorobenzene	99.2	65 - 135		%Rec	1	4/7/2021 10:03:10 PM



Analytical Report

Work Order: 2104041
Date Reported: 4/9/2021

Client: Shannon & Wilson
Project: Cascade Mill Parkway
Lab ID: 2104041-001
Client Sample ID: B-11P-21/R-10@51'

Collection Date: 3/30/2021 1:30:00 AM
Matrix: Soil

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Volatile Organic Compounds by EPA Method 8260D

Batch ID: 31908 Analyst: CR

Benzene	ND	0.0178		mg/Kg-dry	1	4/7/2021 10:03:10 PM
Toluene	ND	0.0577		mg/Kg-dry	1	4/7/2021 10:03:10 PM
Ethylbenzene	ND	0.0222		mg/Kg-dry	1	4/7/2021 10:03:10 PM
m,p-Xylene	ND	0.0444		mg/Kg-dry	1	4/7/2021 10:03:10 PM
o-Xylene	ND	0.0222		mg/Kg-dry	1	4/7/2021 10:03:10 PM
Surr: Dibromofluoromethane	94.4	82.3 - 112		%Rec	1	4/7/2021 10:03:10 PM
Surr: Toluene-d8	97.4	90.7 - 109		%Rec	1	4/7/2021 10:03:10 PM
Surr: 1-Bromo-4-fluorobenzene	97.9	88.4 - 109		%Rec	1	4/7/2021 10:03:10 PM

Mercury by EPA Method 7471

Batch ID: 31892 Analyst: LB

Mercury	ND	0.247		mg/Kg-dry	1	4/6/2021 3:25:22 PM
---------	----	-------	--	-----------	---	---------------------

Total Metals by EPA Method 6020B

Batch ID: 31911 Analyst: EH

Arsenic	2.25	0.104		mg/Kg-dry	1	4/9/2021 1:52:38 PM
Barium	68.6	0.519		mg/Kg-dry	1	4/9/2021 1:52:38 PM
Cadmium	ND	0.173		mg/Kg-dry	1	4/8/2021 6:24:35 PM
Chromium	14.7	0.346		mg/Kg-dry	1	4/8/2021 6:24:35 PM
Lead	2.04	0.173		mg/Kg-dry	1	4/8/2021 6:24:35 PM
Selenium	2.47	0.173		mg/Kg-dry	1	4/9/2021 1:52:38 PM
Silver	ND	0.130		mg/Kg-dry	1	4/8/2021 6:24:35 PM

Sample Moisture (Percent Moisture)

Batch ID: R66414 Analyst: OK

Percent Moisture	9.71			wt%	1	4/8/2021 10:55:13 AM
------------------	------	--	--	-----	---	----------------------



Client: Shannon & Wilson
Project: Cascade Mill Parkway
Lab ID: 2104041-002
Client Sample ID: B-12P-21/R-11 @50'

Collection Date: 4/1/2021 1:15:00 AM
Matrix: Soil

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Batch ID: 31906 Analyst: MM

Diesel (Fuel Oil)	ND	47.4		mg/Kg-dry	1	4/8/2021 9:41:12 AM
Heavy Oil	ND	94.7		mg/Kg-dry	1	4/8/2021 9:41:12 AM
Total Petroleum Hydrocarbons	ND	71.0		mg/Kg-dry	1	4/8/2021 9:41:12 AM
Surr: 2-Fluorobiphenyl	82.3	50 - 150		%Rec	1	4/8/2021 9:41:12 AM
Surr: o-Terphenyl	91.0	50 - 150		%Rec	1	4/8/2021 9:41:12 AM

Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Batch ID: 31880 Analyst: IH

Naphthalene	ND	21.9		µg/Kg-dry	1	4/6/2021 3:19:38 PM
2-Methylnaphthalene	ND	21.9		µg/Kg-dry	1	4/6/2021 3:19:38 PM
1-Methylnaphthalene	ND	21.9		µg/Kg-dry	1	4/6/2021 3:19:38 PM
Acenaphthene	ND	21.9		µg/Kg-dry	1	4/6/2021 3:19:38 PM
Acenaphthylene	ND	21.9		µg/Kg-dry	1	4/6/2021 3:19:38 PM
Fluorene	ND	21.9		µg/Kg-dry	1	4/6/2021 3:19:38 PM
Pentachlorophenol	ND	87.5		µg/Kg-dry	1	4/6/2021 3:19:38 PM
Phenanthrene	ND	43.7		µg/Kg-dry	1	4/6/2021 3:19:38 PM
Anthracene	ND	43.7		µg/Kg-dry	1	4/6/2021 3:19:38 PM
Fluoranthene	ND	43.7		µg/Kg-dry	1	4/6/2021 3:19:38 PM
Pyrene	ND	43.7		µg/Kg-dry	1	4/6/2021 3:19:38 PM
Benz(a)anthracene	ND	21.9		µg/Kg-dry	1	4/6/2021 3:19:38 PM
Chrysene	ND	43.7		µg/Kg-dry	1	4/6/2021 3:19:38 PM
Benzo(b)fluoranthene	ND	21.9		µg/Kg-dry	1	4/6/2021 3:19:38 PM
Benzo(k)fluoranthene	ND	21.9		µg/Kg-dry	1	4/6/2021 3:19:38 PM
Benzo(a)pyrene	ND	21.9		µg/Kg-dry	1	4/6/2021 3:19:38 PM
Indeno(1,2,3-cd)pyrene	ND	43.7		µg/Kg-dry	1	4/6/2021 3:19:38 PM
Dibenz(a,h)anthracene	ND	43.7		µg/Kg-dry	1	4/6/2021 3:19:38 PM
Benzo(g,h,i)perylene	ND	21.9		µg/Kg-dry	1	4/6/2021 3:19:38 PM
Surr: 2,4,6-Tribromophenol	86.5	19.4 - 153		%Rec	1	4/6/2021 3:19:38 PM
Surr: 2-Fluorobiphenyl	64.4	19 - 135		%Rec	1	4/6/2021 3:19:38 PM
Surr: Terphenyl-d14 (surr)	85.4	42.9 - 156		%Rec	1	4/6/2021 3:19:38 PM

Gasoline by NWTPH-Gx

Batch ID: 31908 Analyst: CR

Gasoline	ND	5.88		mg/Kg-dry	1	4/7/2021 10:33:33 PM
Surr: Toluene-d8	100	65 - 135		%Rec	1	4/7/2021 10:33:33 PM
Surr: 4-Bromofluorobenzene	99.0	65 - 135		%Rec	1	4/7/2021 10:33:33 PM



Analytical Report

Work Order: 2104041
Date Reported: 4/9/2021

Client: Shannon & Wilson
Project: Cascade Mill Parkway
Lab ID: 2104041-002
Client Sample ID: B-12P-21/R-11 @50'

Collection Date: 4/1/2021 1:15:00 AM
Matrix: Soil

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Volatile Organic Compounds by EPA Method 8260D

Batch ID: 31908 Analyst: CR

Benzene	ND	0.0235		mg/Kg-dry	1	4/7/2021 10:33:33 PM
Toluene	ND	0.0765		mg/Kg-dry	1	4/7/2021 10:33:33 PM
Ethylbenzene	ND	0.0294		mg/Kg-dry	1	4/7/2021 10:33:33 PM
m,p-Xylene	ND	0.0588		mg/Kg-dry	1	4/7/2021 10:33:33 PM
o-Xylene	ND	0.0294		mg/Kg-dry	1	4/7/2021 10:33:33 PM
Surr: Dibromofluoromethane	94.5	82.3 - 112		%Rec	1	4/7/2021 10:33:33 PM
Surr: Toluene-d8	98.2	90.7 - 109		%Rec	1	4/7/2021 10:33:33 PM
Surr: 1-Bromo-4-fluorobenzene	97.7	88.4 - 109		%Rec	1	4/7/2021 10:33:33 PM

Mercury by EPA Method 7471

Batch ID: 31892 Analyst: LB

Mercury	ND	0.248		mg/Kg-dry	1	4/6/2021 3:26:58 PM
---------	----	-------	--	-----------	---	---------------------

Total Metals by EPA Method 6020B

Batch ID: 31911 Analyst: EH

Arsenic	1.99	0.105		mg/Kg-dry	1	4/9/2021 1:58:12 PM
Barium	68.1	0.526		mg/Kg-dry	1	4/9/2021 1:58:12 PM
Cadmium	ND	0.175		mg/Kg-dry	1	4/8/2021 6:30:09 PM
Chromium	17.1	0.351		mg/Kg-dry	1	4/8/2021 6:30:09 PM
Lead	2.15	0.175		mg/Kg-dry	1	4/8/2021 6:30:09 PM
Selenium	1.68	0.175		mg/Kg-dry	1	4/9/2021 1:58:12 PM
Silver	ND	0.131		mg/Kg-dry	1	4/8/2021 6:30:09 PM

Sample Moisture (Percent Moisture)

Batch ID: R66414 Analyst: OK

Percent Moisture	11.6			wt%	1	4/8/2021 10:55:13 AM
------------------	------	--	--	-----	---	----------------------

Work Order: 2104041
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Total Metals by EPA Method 6020B

Sample ID: MB-31911	SampType: MBLK	Units: mg/Kg		Prep Date: 4/7/2021	RunNo: 66437						
Client ID: MBLKS	Batch ID: 31911			Analysis Date: 4/8/2021	SeqNo: 1336653						
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Arsenic	ND	0.0960									
Barium	ND	0.480									
Cadmium	ND	0.160									
Chromium	ND	0.320									
Lead	ND	0.160									
Selenium	ND	0.160									
Silver	ND	0.120									

Sample ID: LCS-31911	SampType: LCS	Units: mg/Kg		Prep Date: 4/7/2021	RunNo: 66437						
Client ID: LCSS	Batch ID: 31911			Analysis Date: 4/8/2021	SeqNo: 1336654						
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Arsenic	38.3	0.0960	40.00	0	95.8	80	120				
Barium	40.9	0.480	40.00	0	102	80	120				
Cadmium	1.93	0.160	2.000	0	96.5	80	120				
Chromium	41.6	0.320	40.00	0	104	80	120				
Lead	19.2	0.160	20.00	0	96.0	80	120				
Selenium	3.73	0.160	4.000	0	93.4	80	120				
Silver	2.03	0.120	2.000	0	102	80	120				

Sample ID: 2104091-002AMS	SampType: MS	Units: mg/Kg-dry		Prep Date: 4/7/2021	RunNo: 66437						
Client ID: BATCH	Batch ID: 31911			Analysis Date: 4/8/2021	SeqNo: 1336657						
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Arsenic	48.1	0.102	42.52	5.317	101	75	125				
Barium	117	0.510	42.52	53.67	149	75	125				S
Cadmium	2.45	0.170	2.126	0.2302	104	75	125				
Chromium	90.8	0.340	42.52	51.57	92.2	75	125				
Lead	25.1	0.170	21.26	5.121	94.0	75	125				

Work Order: 2104041
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Total Metals by EPA Method 6020B

Sample ID: 2104091-002AMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 4/7/2021	RunNo: 66437							
Client ID: BATCH	Batch ID: 31911	Analysis Date: 4/8/2021	SeqNo: 1336657								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Selenium	6.66	0.170	4.252	2.211	105	75	125				
Silver	2.03	0.128	2.126	0.09239	91.0	75	125				

NOTES:

S - Outlying spike recovery(ies) observed. A duplicate analysis was performed with similar results indicating a possible matrix effect.

Sample ID: 2104091-002AMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 4/7/2021	RunNo: 66437							
Client ID: BATCH	Batch ID: 31911	Analysis Date: 4/8/2021	SeqNo: 1336658								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	49.8	0.102	42.52	5.317	105	75	125	48.08	3.44	20	
Barium	111	0.510	42.52	53.67	136	75	125	116.9	4.90	20	S
Cadmium	2.41	0.170	2.126	0.2302	102	75	125	2.446	1.60	20	
Chromium	103	0.340	42.52	51.57	122	75	125	90.79	12.9	20	
Lead	24.9	0.170	21.26	5.121	93.2	75	125	25.10	0.632	20	
Selenium	6.34	0.170	4.252	2.211	97.0	75	125	6.658	4.98	20	
Silver	1.94	0.128	2.126	0.09239	87.0	75	125	2.026	4.20	20	

NOTES:

S - Outlying spike recovery(ies) observed for Ba. A duplicate analysis was performed with similar results indicating a possible matrix effect.

Work Order: 2104041
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Mercury by EPA Method 7471

Sample ID: MB-31892	SampType: MBLK	Units: mg/Kg	Prep Date: 4/6/2021	RunNo: 66369							
Client ID: MBLKS	Batch ID: 31892	Analysis Date: 4/6/2021	SeqNo: 1335288								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury ND 0.250

Sample ID: LCS-31892	SampType: LCS	Units: mg/Kg	Prep Date: 4/6/2021	RunNo: 66369							
Client ID: LCSS	Batch ID: 31892	Analysis Date: 4/6/2021	SeqNo: 1335289								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.529 0.250 0.5000 0 106 80 120

Sample ID: 2103402-001ADUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 4/6/2021	RunNo: 66369							
Client ID: BATCH	Batch ID: 31892	Analysis Date: 4/6/2021	SeqNo: 1335291								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury ND 0.661 0 20 Q

NOTES:

Q - Indicates an analyte with a continuing calibration that does not meet established acceptance criteria

Sample ID: 2103402-001AMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 4/6/2021	RunNo: 66369							
Client ID: BATCH	Batch ID: 31892	Analysis Date: 4/6/2021	SeqNo: 1335292								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 1.41 0.674 1.347 0.3755 76.9 70 130

Sample ID: 2103402-001AMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 4/6/2021	RunNo: 66369							
Client ID: BATCH	Batch ID: 31892	Analysis Date: 4/6/2021	SeqNo: 1335293								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 1.63 0.661 1.323 0.3755 94.8 70 130 1.412 14.3 20

Work Order: 2104041
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Sample ID: MB-31906	SampType: MBLK	Units: mg/Kg				Prep Date: 4/7/2021	RunNo: 66415				
Client ID: MBLKS	Batch ID: 31906					Analysis Date: 4/8/2021	SeqNo: 1336532				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	ND	50.0									
Heavy Oil	ND	100									
Total Petroleum Hydrocarbons	ND	75.0									
Surr: 2-Fluorobiphenyl	9.57		10.00		95.7	50	150				
Surr: o-Terphenyl	10.3		10.00		103	50	150				

Sample ID: LCS-31906	SampType: LCS	Units: mg/Kg				Prep Date: 4/7/2021	RunNo: 66415				
Client ID: LCSS	Batch ID: 31906					Analysis Date: 4/8/2021	SeqNo: 1336533				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	504	50.0	500.0	0	101	73.7	114				
Surr: 2-Fluorobiphenyl	9.11		10.00		91.1	50	150				
Surr: o-Terphenyl	10.2		10.00		102	50	150				

Sample ID: 2104041-002AMS	SampType: MS	Units: mg/Kg-dry				Prep Date: 4/7/2021	RunNo: 66415				
Client ID: B-12P-21/R-11 @50'	Batch ID: 31906					Analysis Date: 4/8/2021	SeqNo: 1336536				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	561	56.4	563.7	0	99.5	61.4	129				
Surr: 2-Fluorobiphenyl	9.48		11.27		84.1	50	150				
Surr: o-Terphenyl	10.8		11.27		96.2	50	150				

Sample ID: 2104041-002AMSD	SampType: MSD	Units: mg/Kg-dry				Prep Date: 4/7/2021	RunNo: 66415				
Client ID: B-12P-21/R-11 @50'	Batch ID: 31906					Analysis Date: 4/8/2021	SeqNo: 1336537				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	481	48.0	480.0	0	100	61.4	129	561.2	15.4	30	
Surr: 2-Fluorobiphenyl	7.63		9.600		79.5	50	150		0		
Surr: o-Terphenyl	10.0		9.600		104	50	150		0		

Work Order: 2104041
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Sample ID: 2104041-002AMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 4/7/2021	RunNo: 66415							
Client ID: B-12P-21/R-11 @50'	Batch ID: 31906	Analysis Date: 4/8/2021	SeqNo: 1336537								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Sample ID: 2104071-009ADUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 4/7/2021	RunNo: 66415							
Client ID: BATCH	Batch ID: 31906	Analysis Date: 4/8/2021	SeqNo: 1336546								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	ND	54.6						0		30	
Heavy Oil	ND	109						0		30	
Total Petroleum Hydrocarbons	ND	82.0						0		0	
Surr: 2-Fluorobiphenyl	8.84		10.93		80.9	50	150		0		
Surr: o-Terphenyl	9.85		10.93		90.1	50	150		0		

Work Order: 2104041
 CLIENT: Shannon & Wilson
 Project: Cascade Mill Parkway

QC SUMMARY REPORT
Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Sample ID: MB-31880	SampType: MBLK	Units: µg/Kg			Prep Date: 4/5/2021	RunNo: 66449					
Client ID: MBLKS	Batch ID: 31880				Analysis Date: 4/6/2021	SeqNo: 1336911					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	ND	20.0									
2-Methylnaphthalene	ND	20.0									
1-Methylnaphthalene	ND	20.0									
Acenaphthene	ND	20.0									
Acenaphthylene	ND	20.0									
Fluorene	ND	20.0									
Pentachlorophenol	ND	80.0									
Phenanthrene	ND	40.0									
Anthracene	ND	40.0									
Fluoranthene	ND	40.0									
Pyrene	ND	40.0									
Benz(a)anthracene	ND	20.0									
Chrysene	ND	40.0									
Benzo(b)fluoranthene	ND	20.0									
Benzo(k)fluoranthene	ND	20.0									
Benzo(a)pyrene	ND	20.0									
Indeno(1,2,3-cd)pyrene	ND	40.0									
Dibenz(a,h)anthracene	ND	40.0									
Benzo(g,h,i)perylene	ND	20.0									
Surr: 2,4,6-Tribromophenol	1,350		2,000		67.7	19.4	153				
Surr: 2-Fluorobiphenyl	796		1,000		79.6	19	135				
Surr: Terphenyl-d14 (surr)	947		1,000		94.7	42.9	156				

Sample ID: LCS-31880	SampType: LCS	Units: µg/Kg			Prep Date: 4/5/2021	RunNo: 66449					
Client ID: LCSS	Batch ID: 31880				Analysis Date: 4/6/2021	SeqNo: 1336912					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	1,790	20.0	2,000	0	89.5	62.7	127				
2-Methylnaphthalene	1,820	20.0	2,000	0	90.9	62.7	132				
1-Methylnaphthalene	1,840	20.0	2,000	0	91.8	61.4	131				

Work Order: 2104041
 CLIENT: Shannon & Wilson
 Project: Cascade Mill Parkway

QC SUMMARY REPORT
Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Sample ID: LCS-31880	SampType: LCS	Units: µg/Kg	Prep Date: 4/5/2021	RunNo: 66449							
Client ID: LCSS	Batch ID: 31880		Analysis Date: 4/6/2021	SeqNo: 1336912							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Acenaphthene	1,780	20.0	2,000	0	88.9	59.2	132				
Acenaphthylene	1,850	20.0	2,000	0	92.4	62	132				
Fluorene	1,880	20.0	2,000	0	94.0	59.1	136				
Pentachlorophenol	1,340	80.0	2,000	0	67.1	5	112				
Phenanthrene	1,860	40.0	2,000	0	93.0	54.1	139				
Anthracene	1,850	40.0	2,000	0	92.7	55.5	136				
Fluoranthene	1,900	40.0	2,000	0	95.2	52.8	149				
Pyrene	1,830	40.0	2,000	0	91.6	53.6	146				
Benz(a)anthracene	1,900	20.0	2,000	0	95.2	49.7	153				
Chrysene	1,810	40.0	2,000	0	90.5	52.6	147				
Benzo(b)fluoranthene	2,060	20.0	2,000	0	103	50.6	151				
Benzo(k)fluoranthene	1,860	20.0	2,000	0	92.8	47.1	155				
Benzo(a)pyrene	2,180	20.0	2,000	0	109	48.3	169				
Indeno(1,2,3-cd)pyrene	1,960	40.0	2,000	0	97.9	52.3	145				
Dibenz(a,h)anthracene	2,000	40.0	2,000	0	99.8	53	144				
Benzo(g,h,i)perylene	1,830	20.0	2,000	0	91.7	49.7	144				
Surr: 2,4,6-Tribromophenol	2,050		2,000		103	19.4	153				
Surr: 2-Fluorobiphenyl	863		1,000		86.3	19	135				
Surr: Terphenyl-d14 (surr)	961		1,000		96.1	42.9	156				

Sample ID: 2103370-004AMS	SampType: MS	Units: µg/Kg-dry	Prep Date: 4/5/2021	RunNo: 66449							
Client ID: BATCH	Batch ID: 31880		Analysis Date: 4/6/2021	SeqNo: 1336914							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Naphthalene	1,330	18.7	1,871	0	70.9	28.7	139				
2-Methylnaphthalene	1,370	18.7	1,871	0	73.1	43.5	130				
1-Methylnaphthalene	1,390	18.7	1,871	0	74.3	42.6	127				
Acenaphthene	1,340	18.7	1,871	0	71.7	45.1	123				
Acenaphthylene	1,410	18.7	1,871	0	75.3	45.3	129				
Fluorene	1,420	18.7	1,871	0	76.0	41.6	128				

Work Order: 2104041
 CLIENT: Shannon & Wilson
 Project: Cascade Mill Parkway

QC SUMMARY REPORT
Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Sample ID: 2103370-004AMS	SampType: MS	Units: µg/Kg-dry				Prep Date: 4/5/2021	RunNo: 66449				
Client ID: BATCH	Batch ID: 31880					Analysis Date: 4/6/2021	SeqNo: 1336914				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Pentachlorophenol	1,440	74.8	1,871	0	77.2	5	188				
Phenanthrene	1,420	37.4	1,871	12.51	75.2	24.2	142				
Anthracene	1,420	37.4	1,871	0	75.8	33.1	143				
Fluoranthene	1,520	37.4	1,871	33.69	79.3	35.5	147				
Pyrene	1,430	37.4	1,871	24.53	75.0	38.3	141				
Benz(a)anthracene	1,500	18.7	1,871	6.865	79.8	42.5	145				
Chrysene	1,380	37.4	1,871	18.99	72.8	39.7	134				
Benzo(b)fluoranthene	1,400	18.7	1,871	12.44	74.4	29.9	152				
Benzo(k)fluoranthene	1,600	18.7	1,871	9.164	85.1	33.2	143.5				
Benzo(a)pyrene	1,640	18.7	1,871	8.077	87.0	38.2	156				
Indeno(1,2,3-cd)pyrene	1,460	37.4	1,871	0	78.3	41.4	128				
Dibenz(a,h)anthracene	1,490	37.4	1,871	0	79.6	40.4	129				
Benzo(g,h,i)perylene	1,350	18.7	1,871	12.17	71.6	34.2	131				
Surr: 2,4,6-Tribromophenol	1,650		1,871		88.2	19.4	153				
Surr: 2-Fluorobiphenyl	687		935.4		73.4	19	135				
Surr: Terphenyl-d14 (surr)	763		935.4		81.6	42.9	156				

Sample ID: 2103370-004AMSD	SampType: MSD	Units: µg/Kg-dry				Prep Date: 4/5/2021	RunNo: 66449				
Client ID: BATCH	Batch ID: 31880					Analysis Date: 4/6/2021	SeqNo: 1336915				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	1,330	20.7	2,067	0	64.4	28.7	139	1,326	0.363	30	
2-Methylnaphthalene	1,360	20.7	2,067	0	65.9	43.5	130	1,367	0.366	30	
1-Methylnaphthalene	1,390	20.7	2,067	0	67.1	42.6	127	1,390	0.193	30	
Acenaphthene	1,350	20.7	2,067	0	65.4	45.1	123	1,341	0.804	30	
Acenaphthylene	1,400	20.7	2,067	0	67.8	45.3	129	1,409	0.560	30	
Fluorene	1,410	20.7	2,067	0	68.4	41.6	128	1,422	0.594	30	
Pentachlorophenol	1,420	82.7	2,067	0	68.7	5	188	1,444	1.70	30	
Phenanthrene	1,470	41.3	2,067	12.51	70.4	24.2	142	1,419	3.36	30	
Anthracene	1,440	41.3	2,067	0	69.8	33.1	143	1,419	1.71	30	

Work Order: 2104041
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Fluoranthene	1,510	41.3	2,067	33.69	71.6	35.5	147	1,517	0.183	30	
Pyrene	1,440	41.3	2,067	24.53	68.4	38.3	141	1,428	0.768	30	
Benz(a)anthracene	1,500	20.7	2,067	6.865	72.3	42.5	145	1,500	0.137	30	
Chrysene	1,360	41.3	2,067	18.99	64.9	39.7	134	1,380	1.41	30	
Benzo(b)fluoranthene	1,420	20.7	2,067	12.44	68.2	29.9	152	1,405	1.31	30	
Benzo(k)fluoranthene	1,570	20.7	2,067	9.164	75.5	33.2	143.5	1,601	1.97	30	
Benzo(a)pyrene	1,660	20.7	2,067	8.077	80.0	38.2	156	1,636	1.53	30	
Indeno(1,2,3-cd)pyrene	1,480	41.3	2,067	0	71.5	41.4	128	1,464	0.926	30	
Dibenz(a,h)anthracene	1,510	41.3	2,067	0	73.0	40.4	129	1,490	1.34	30	
Benzo(g,h,i)perylene	1,370	20.7	2,067	12.17	65.6	34.2	131	1,352	1.12	30	
Surr: 2,4,6-Tribromophenol	1,560		2,067		75.6	19.4	153		0		
Surr: 2-Fluorobiphenyl	636		1,034		61.5	19	135		0		
Surr: Terphenyl-d14 (surr)	712		1,034		68.9	42.9	156		0		

Work Order: 2104041
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Gasoline by NWTPH-Gx

Sample ID: LCS-31908	SampType: LCS	Units: mg/Kg			Prep Date: 4/7/2021	RunNo: 66410					
Client ID: LCSS	Batch ID: 31908				Analysis Date: 4/7/2021	SeqNo: 1336177					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	25.7	5.00	25.00	0	103	65	135				
Surr: Toluene-d8	1.23		1.250		98.6	65	135				
Surr: 4-Bromofluorobenzene	1.26		1.250		101	65	135				

Sample ID: MB-31908	SampType: MBLK	Units: mg/Kg			Prep Date: 4/7/2021	RunNo: 66410					
Client ID: MBLKS	Batch ID: 31908				Analysis Date: 4/7/2021	SeqNo: 1336178					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	ND	5.00									
Surr: Toluene-d8	1.23		1.250		98.7	65	135				
Surr: 4-Bromofluorobenzene	1.24		1.250		99.4	65	135				

Sample ID: 2104041-002BDUP	SampType: DUP	Units: mg/Kg-dry			Prep Date: 4/7/2021	RunNo: 66410					
Client ID: B-12P-21/R-11 @50'	Batch ID: 31908				Analysis Date: 4/7/2021	SeqNo: 1336167					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	ND	5.88						0		30	
Surr: Toluene-d8	1.46		1.471		99.1	65	135		0		
Surr: 4-Bromofluorobenzene	1.45		1.471		98.5	65	135		0		

Sample ID: 2104042-007BMS	SampType: MS	Units: mg/Kg-dry			Prep Date: 4/7/2021	RunNo: 66410					
Client ID: BATCH	Batch ID: 31908				Analysis Date: 4/8/2021	SeqNo: 1336172					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	24.9	4.61	23.06	0	108	65	135				
Surr: Toluene-d8	1.15		1.153		99.7	65	135				
Surr: 4-Bromofluorobenzene	1.16		1.153		100	65	135				

Work Order: 2104041
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260D

Sample ID: LCS-31908	SampType: LCS	Units: mg/Kg				Prep Date: 4/7/2021	RunNo: 66409				
Client ID: LCSS	Batch ID: 31908					Analysis Date: 4/7/2021	SeqNo: 1336312				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	0.985	0.0200	1.000	0	98.5	80	120				
Toluene	1.06	0.0650	1.000	0	106	80	120				
Ethylbenzene	1.08	0.0250	1.000	0	108	80	120				
m,p-Xylene	2.06	0.0500	2.000	0	103	80	120				
o-Xylene	1.02	0.0250	1.000	0	102	80	120				
Surr: Dibromofluoromethane	1.22		1.250		97.7	80	120				
Surr: Toluene-d8	1.28		1.250		102	80	120				
Surr: 1-Bromo-4-fluorobenzene	1.26		1.250		101	80	120				

Sample ID: MB-31908	SampType: MBLK	Units: mg/Kg				Prep Date: 4/7/2021	RunNo: 66409				
Client ID: MBLKS	Batch ID: 31908					Analysis Date: 4/7/2021	SeqNo: 1336313				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	ND	0.0200									
Toluene	ND	0.0650									
Ethylbenzene	ND	0.0250									
m,p-Xylene	ND	0.0500									
o-Xylene	ND	0.0250									
Surr: Dibromofluoromethane	1.17		1.250		93.7	82.3	112				
Surr: Toluene-d8	1.20		1.250		96.3	90.7	109				
Surr: 1-Bromo-4-fluorobenzene	1.23		1.250		98.1	88.4	109				

Sample ID: 2104041-002BDUP	SampType: DUP	Units: mg/Kg-dry				Prep Date: 4/7/2021	RunNo: 66409				
Client ID: B-12P-21/R-11 @50'	Batch ID: 31908					Analysis Date: 4/7/2021	SeqNo: 1336304				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	ND	0.0235						0		30	
Toluene	ND	0.0765						0		30	
Ethylbenzene	ND	0.0294						0		30	

Work Order: 2104041
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260D

Sample ID: 2104041-002BDUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 4/7/2021	RunNo: 66409							
Client ID: B-12P-21/R-11 @50'	Batch ID: 31908		Analysis Date: 4/7/2021	SeqNo: 1336304							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
m,p-Xylene	ND	0.0588						0		30	
o-Xylene	ND	0.0294						0		30	
Surr: Dibromofluoromethane	1.40		1.471		95.1	82.3	112		0		
Surr: Toluene-d8	1.45		1.471		98.6	90.7	109		0		
Surr: 1-Bromo-4-fluorobenzene	1.43		1.471		97.3	88.4	109		0		

Sample ID: 2104042-005BMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 4/7/2021	RunNo: 66409							
Client ID: BATCH	Batch ID: 31908		Analysis Date: 4/8/2021	SeqNo: 1336307							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	1.09	0.0214	1.068	0	102	76.8	129				
Toluene	1.09	0.0694	1.068	0	102	77.8	127				
Ethylbenzene	1.16	0.0267	1.068	0	108	78.7	130				
m,p-Xylene	2.17	0.0534	2.137	0	102	79.3	127				
o-Xylene	1.09	0.0267	1.068	0	102	80.7	124				
Surr: Dibromofluoromethane	1.34		1.335		100	82.3	112				
Surr: Toluene-d8	1.34		1.335		100	90.7	109				
Surr: 1-Bromo-4-fluorobenzene	1.35		1.335		101	88.4	109				

Client Name: **SW**

 Work Order Number: **2104041**

 Logged by: **Gabrielle Coeuille**

 Date Received: **4/2/2021 5:31:00 PM**

Chain of Custody

1. Is Chain of Custody complete? Yes No Not Present
2. How was the sample delivered? Client

Log In

3. Coolers are present? Yes No NA
4. Shipping container/cooler in good condition? Yes No
5. Custody Seals present on shipping container/cooler?
(Refer to comments for Custody Seals not intact) Yes No Not Present
6. Was an attempt made to cool the samples? Yes No NA
7. Were all items received at a temperature of >2°C to 6°C * Yes No NA
8. Sample(s) in proper container(s)? Yes No
9. Sufficient sample volume for indicated test(s)? Yes No
10. Are samples properly preserved? Yes No
11. Was preservative added to bottles? Yes No NA
12. Is there headspace in the VOA vials? Yes No NA
13. Did all samples containers arrive in good condition(unbroken)? Yes No
14. Does paperwork match bottle labels? Yes No
15. Are matrices correctly identified on Chain of Custody? Yes No
16. Is it clear what analyses were requested? Yes No
17. Were all holding times able to be met? Yes No

Special Handling (if applicable)

18. Was client notified of all discrepancies with this order? Yes No NA

Person Notified:	<input type="text"/>	Date:	<input type="text"/>
By Whom:	<input type="text"/>	Via:	<input type="checkbox"/> eMail <input type="checkbox"/> Phone <input type="checkbox"/> Fax <input type="checkbox"/> In Person
Regarding:	<input type="text"/>		
Client Instructions:	<input type="text"/>		

19. Additional remarks:

Item Information

Item #	Temp °C
Sample 1	1.1

* Note: DoD/ELAP and TNI require items to be received at 4°C +/- 2°C



Fremont
Analytical

3600 Fremont Ave N.
Seattle, WA 98103
Tel: 206-352-3790
Fax: 206-352-7118

Chain of Custody Record & Laboratory Services Agreement

Date: 4/12/21 Page: of

Project Name: Cascade Mill Parkway

Project No: 106384-002

Collected by: PKM

Location: Yakima

Report To (PM): David Randall

PM Email: dir@shawni.com

Laboratory Project No (Internal): 2104FD41

Special Remarks:

Sample Disposal: Return to client Disposal by lab (after 30 days)

Sample Name	Sample Date	Sample Time	Sample Type (Matrix)*	# of Cont.	VOCs (EPA 8260 / 624)	BTEX	Gasoline Range Organics (GX)	Hydrocarbon Identification (HCID)	Diesel/heavy Oil Range Organics (DX)	SVOCs (EPA 8270 / 625)	PAHs (EPA 8270 - SIM) + PCP	PCBs (EPA 8270 - SIM)	Metals** (EPA 8082 / 608)	Total (T) Dissolved (D)	Anions (Cl)**	EDB (801)	Comments
1 B-11P-21/R-10 @ 51'	3/30/21	01:30	SOL	3	X	X	X	X	X	X	X	X					
2 B-12P-21/R-11 @ 50'	4/1/21	01:15	SOL	3	X	X	X	X	X	X	X	X					
3																	
4																	
5																	
6																	
7																	
8																	
9																	
10																	

*Matrix: A = Air, AQ = Aqueous, B = Bulk, O = Other, P = Product, S = Soil, SD = Sediment, SL = Solid, W = Water, DW = Drinking Water, GW = Ground Water, SW = Storm Water, WW = Waste Water

**Metals (Circle): MTCA-5 (RCRA-8) Priority Pollutants TAL Individual: Ag Al As B Ba Be Ca Cd Co Cr Cu Fe Hg K Mg Mn Mo Na Ni Pb Sb Se Sr Sn Tl Ti V Zn

***Anions (Circle): Nitrate Nitrite Chloride Sulfate Bromide O-Phosphate Fluoride Nitrate-Nitrite

I represent that I am authorized to enter into this Agreement with Fremont Analytical on behalf of the Client named above; that I have verified Client's agreement to each of the terms on the front and backside of this Agreement.

Turn-around Time: Standard Next Day 3 Day Same Day 2 Day (specify)

Relinquished (Signature) *Mr. Paulard* Print Name *Mr. Paulard* Date/Time *4/12/21 10:30*

Relinquished (Signature) *Kristen McFarland* Print Name *Kristen McFarland* Date/Time *4/12/21 10:30*

Relinquished (Signature) *Mr. Paulard* Print Name *Mr. Paulard* Date/Time *4/12/2021 17:31*



Shannon & Wilson

Dave Randall
400 N. 34th Street, Suite 100
Seattle, WA 98103

**RE: Cascade Mill Parkway
Work Order Number: 2103484**

April 07, 2021

Attention Dave Randall:

Fremont Analytical, Inc. received 4 sample(s) on 3/29/2021 for the analyses presented in the following report.

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.
Gasoline by NWTPH-Gx
Mercury by EPA Method 7471
Sample Moisture (Percent Moisture)
Semi-Volatile Organic Compounds by EPA 8270 (SIM)
Total Metals by EPA Method 6020B
Volatile Organic Compounds by EPA Method 8260D

This report consists of the following:

- Case Narrative
- Analytical Results
- Applicable Quality Control Summary Reports
- Chain of Custody

All analyses were performed consistent with the Quality Assurance program of Fremont Analytical, Inc. Please contact the laboratory if you should have any questions about the results.

Thank you for using Fremont Analytical.

Sincerely,

Brianna Barnes
Project Manager

*DoD-ELAP Accreditation #79636 by PJLA, ISO/IEC 17025:2017 and QSM 5.3 for Environmental Testing
ORELAP Certification: WA 100009 (NELAP Recognized) for Environmental Testing
Washington State Department of Ecology Accredited for Environmental Testing, Lab ID C910*

Original



CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway
Work Order: 2103484

Work Order Sample Summary

Lab Sample ID	Client Sample ID	Date/Time Collected	Date/Time Received
2103484-001	B-15P-21/S-5 @ 21'	03/22/2021 4:00 PM	03/29/2021 9:06 AM
2103484-002	B-13-21/R-9 @ 47'	03/25/2021 11:55 PM	03/29/2021 9:06 AM
2103484-003	B-14-21/R-9 @ 48'	03/27/2021 12:40 AM	03/29/2021 9:06 AM
2103484-004	Trip Blank		03/29/2021 9:06 AM

Note: If no "Time Collected" is supplied, a default of 12:00AM is assigned

CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

I. SAMPLE RECEIPT:

Samples receipt information is recorded on the attached Sample Receipt Checklist.

II. GENERAL REPORTING COMMENTS:

Results are reported on a wet weight basis unless dry-weight correction is denoted in the units field on the analytical report ("mg/kg-dry" or "ug/kg-dry").

Matrix Spike (MS) and MS Duplicate (MSD) samples are tested from an analytical batch of "like" matrix to check for possible matrix effect. The MS and MSD will provide site specific matrix data only for those samples which are spiked by the laboratory. The sample chosen for spike purposes may or may not have been a sample submitted in this sample delivery group. The validity of the analytical procedures for which data is reported in this analytical report is determined by the Laboratory Control Sample (LCS) and the Method Blank (MB). The LCS and the MB are processed with the samples and the MS/MSD to ensure method criteria are achieved throughout the entire analytical process.

III. ANALYSES AND EXCEPTIONS:

Exceptions associated with this report will be footnoted in the analytical results page(s) or the quality control summary page(s) and/or noted below.

Qualifiers:

- * - Flagged value is not within established control limits
- B - Analyte detected in the associated Method Blank
- D - Dilution was required
- E - Value above quantitation range
- H - Holding times for preparation or analysis exceeded
- I - Analyte with an internal standard that does not meet established acceptance criteria
- J - Analyte detected below Reporting Limit
- N - Tentatively Identified Compound (TIC)
- Q - Analyte with an initial or continuing calibration that does not meet established acceptance criteria
- S - Spike recovery outside accepted recovery limits
- ND - Not detected at the Reporting Limit
- R - High relative percent difference observed

Acronyms:

- %Rec - Percent Recovery
- CCB - Continued Calibration Blank
- CCV - Continued Calibration Verification
- DF - Dilution Factor
- DUP - Sample Duplicate
- HEM - Hexane Extractable Material
- ICV - Initial Calibration Verification
- LCS/LCSD - Laboratory Control Sample / Laboratory Control Sample Duplicate
- MCL - Maximum Contaminant Level
- MB or MBLANK - Method Blank
- MDL - Method Detection Limit
- MS/MSD - Matrix Spike / Matrix Spike Duplicate
- PDS - Post Digestion Spike
- Ref Val - Reference Value
- REP - Sample Replicate
- RL - Reporting Limit
- RPD - Relative Percent Difference
- SD - Serial Dilution
- SGT - Silica Gel Treatment
- SPK - Spike
- Surr - Surrogate



Client: Shannon & Wilson
Project: Cascade Mill Parkway
Lab ID: 2103484-001
Client Sample ID: B-15P-21/S-5 @ 21'

Collection Date: 3/22/2021 4:00:00 PM
Matrix: Soil

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Batch ID: 31813 Analyst: MM

Diesel (Fuel Oil)	ND	52.6		mg/Kg-dry	1	3/29/2021 6:29:35 PM
Heavy Oil	ND	105		mg/Kg-dry	1	3/29/2021 6:29:35 PM
Surr: 2-Fluorobiphenyl	87.2	50 - 150		%Rec	1	3/29/2021 6:29:35 PM
Surr: o-Terphenyl	87.7	50 - 150		%Rec	1	3/29/2021 6:29:35 PM

Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Batch ID: 31842 Analyst: SB

Naphthalene	ND	20.6		µg/Kg-dry	1	3/31/2021 7:51:27 PM
2-Methylnaphthalene	ND	20.6		µg/Kg-dry	1	3/31/2021 7:51:27 PM
1-Methylnaphthalene	ND	20.6		µg/Kg-dry	1	3/31/2021 7:51:27 PM
Acenaphthene	ND	20.6		µg/Kg-dry	1	3/31/2021 7:51:27 PM
Acenaphthylene	ND	20.6		µg/Kg-dry	1	3/31/2021 7:51:27 PM
Fluorene	ND	20.6		µg/Kg-dry	1	3/31/2021 7:51:27 PM
Pentachlorophenol	ND	82.3		µg/Kg-dry	1	3/31/2021 7:51:27 PM
Phenanthrene	ND	41.1		µg/Kg-dry	1	3/31/2021 7:51:27 PM
Anthracene	ND	41.1		µg/Kg-dry	1	3/31/2021 7:51:27 PM
Fluoranthene	ND	41.1		µg/Kg-dry	1	3/31/2021 7:51:27 PM
Pyrene	ND	41.1		µg/Kg-dry	1	3/31/2021 7:51:27 PM
Benz(a)anthracene	ND	20.6		µg/Kg-dry	1	3/31/2021 7:51:27 PM
Chrysene	ND	41.1		µg/Kg-dry	1	3/31/2021 7:51:27 PM
Benzo(b)fluoranthene	ND	20.6		µg/Kg-dry	1	3/31/2021 7:51:27 PM
Benzo(k)fluoranthene	ND	20.6		µg/Kg-dry	1	3/31/2021 7:51:27 PM
Benzo(a)pyrene	ND	20.6		µg/Kg-dry	1	3/31/2021 7:51:27 PM
Indeno(1,2,3-cd)pyrene	ND	41.1		µg/Kg-dry	1	3/31/2021 7:51:27 PM
Dibenz(a,h)anthracene	ND	41.1		µg/Kg-dry	1	3/31/2021 7:51:27 PM
Benzo(g,h,i)perylene	ND	20.6		µg/Kg-dry	1	3/31/2021 7:51:27 PM
Surr: 2,4,6-Tribromophenol	80.7	19.4 - 153		%Rec	1	3/31/2021 7:51:27 PM
Surr: 2-Fluorobiphenyl	78.6	19 - 135		%Rec	1	3/31/2021 7:51:27 PM
Surr: Terphenyl-d14 (surr)	92.6	42.9 - 156		%Rec	1	3/31/2021 7:51:27 PM

Gasoline by NWTPH-Gx

Batch ID: 31836 Analyst: KT

Gasoline	ND	5.46		mg/Kg-dry	1	3/31/2021 11:20:57 AM
Surr: Toluene-d8	98.6	65 - 135		%Rec	1	3/31/2021 11:20:57 AM
Surr: 4-Bromofluorobenzene	99.4	65 - 135		%Rec	1	3/31/2021 11:20:57 AM

Volatile Organic Compounds by EPA Method 8260D

Batch ID: 31836 Analyst: KT

Benzene	ND	0.0218		mg/Kg-dry	1	3/31/2021 11:20:57 AM
---------	----	--------	--	-----------	---	-----------------------



Client: Shannon & Wilson
Project: Cascade Mill Parkway
Lab ID: 2103484-001
Client Sample ID: B-15P-21/S-5 @ 21'

Collection Date: 3/22/2021 4:00:00 PM

Matrix: Soil

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Volatile Organic Compounds by EPA Method 8260D

Batch ID: 31836 Analyst: KT

Toluene	ND	0.0710		mg/Kg-dry	1	3/31/2021 11:20:57 AM
Ethylbenzene	ND	0.0273		mg/Kg-dry	1	3/31/2021 11:20:57 AM
m,p-Xylene	ND	0.0546		mg/Kg-dry	1	3/31/2021 11:20:57 AM
o-Xylene	ND	0.0273		mg/Kg-dry	1	3/31/2021 11:20:57 AM
Surr: Dibromofluoromethane	102	82.3 - 112		%Rec	1	3/31/2021 11:20:57 AM
Surr: Toluene-d8	102	90.7 - 109		%Rec	1	3/31/2021 11:20:57 AM
Surr: 1-Bromo-4-fluorobenzene	98.0	88.4 - 109		%Rec	1	3/31/2021 11:20:57 AM

Mercury by EPA Method 7471

Batch ID: 31871 Analyst: LB

Mercury	ND	0.273		mg/Kg-dry	1	4/5/2021 2:44:37 PM
---------	----	-------	--	-----------	---	---------------------

Total Metals by EPA Method 6020B

Batch ID: 31896 Analyst: EH

Arsenic	2.77	0.101		mg/Kg-dry	1	4/7/2021 3:56:44 PM
Barium	50.5	0.507		mg/Kg-dry	1	4/7/2021 3:56:44 PM
Cadmium	ND	0.169		mg/Kg-dry	1	4/7/2021 3:56:44 PM
Chromium	15.7	0.338		mg/Kg-dry	1	4/7/2021 3:56:44 PM
Lead	2.15	0.169		mg/Kg-dry	1	4/7/2021 3:56:44 PM
Selenium	2.19	0.169		mg/Kg-dry	1	4/7/2021 3:56:44 PM
Silver	ND	0.127		mg/Kg-dry	1	4/7/2021 3:56:44 PM

Sample Moisture (Percent Moisture)

Batch ID: R66167 Analyst: CH

Percent Moisture	10.3			wt%	1	3/29/2021 2:09:28 PM
------------------	------	--	--	-----	---	----------------------



Client: Shannon & Wilson
Project: Cascade Mill Parkway
Lab ID: 2103484-002
Client Sample ID: B-13-21/R-9 @ 47'

Collection Date: 3/25/2021 11:55:00 PM

Matrix: Soil

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Batch ID: 31813 Analyst: MM

Diesel (Fuel Oil)	ND	51.4		mg/Kg-dry	1	3/30/2021 9:11:49 AM
Heavy Oil	ND	103		mg/Kg-dry	1	3/30/2021 9:11:49 AM
Surr: 2-Fluorobiphenyl	91.3	50 - 150		%Rec	1	3/30/2021 9:11:49 AM
Surr: o-Terphenyl	92.4	50 - 150		%Rec	1	3/30/2021 9:11:49 AM

Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Batch ID: 31842 Analyst: SB

Naphthalene	ND	19.5		µg/Kg-dry	1	3/31/2021 8:58:21 PM
2-Methylnaphthalene	ND	19.5		µg/Kg-dry	1	3/31/2021 8:58:21 PM
1-Methylnaphthalene	ND	19.5		µg/Kg-dry	1	3/31/2021 8:58:21 PM
Acenaphthene	ND	19.5		µg/Kg-dry	1	3/31/2021 8:58:21 PM
Acenaphthylene	ND	19.5		µg/Kg-dry	1	3/31/2021 8:58:21 PM
Fluorene	ND	19.5		µg/Kg-dry	1	3/31/2021 8:58:21 PM
Pentachlorophenol	ND	78.0		µg/Kg-dry	1	3/31/2021 8:58:21 PM
Phenanthrene	ND	39.0		µg/Kg-dry	1	3/31/2021 8:58:21 PM
Anthracene	ND	39.0		µg/Kg-dry	1	3/31/2021 8:58:21 PM
Fluoranthene	ND	39.0		µg/Kg-dry	1	3/31/2021 8:58:21 PM
Pyrene	ND	39.0		µg/Kg-dry	1	3/31/2021 8:58:21 PM
Benz(a)anthracene	ND	19.5		µg/Kg-dry	1	3/31/2021 8:58:21 PM
Chrysene	ND	39.0		µg/Kg-dry	1	3/31/2021 8:58:21 PM
Benzo(b)fluoranthene	ND	19.5		µg/Kg-dry	1	3/31/2021 8:58:21 PM
Benzo(k)fluoranthene	ND	19.5		µg/Kg-dry	1	3/31/2021 8:58:21 PM
Benzo(a)pyrene	ND	19.5		µg/Kg-dry	1	3/31/2021 8:58:21 PM
Indeno(1,2,3-cd)pyrene	ND	39.0		µg/Kg-dry	1	3/31/2021 8:58:21 PM
Dibenz(a,h)anthracene	ND	39.0		µg/Kg-dry	1	3/31/2021 8:58:21 PM
Benzo(g,h,i)perylene	ND	19.5		µg/Kg-dry	1	3/31/2021 8:58:21 PM
Surr: 2,4,6-Tribromophenol	75.9	19.4 - 153		%Rec	1	3/31/2021 8:58:21 PM
Surr: 2-Fluorobiphenyl	76.2	19 - 135		%Rec	1	3/31/2021 8:58:21 PM
Surr: Terphenyl-d14 (surr)	87.2	42.9 - 156		%Rec	1	3/31/2021 8:58:21 PM

Gasoline by NWTPH-Gx

Batch ID: 31836 Analyst: KT

Gasoline	ND	5.41		mg/Kg-dry	1	3/31/2021 12:21:45 PM
Surr: Toluene-d8	99.1	65 - 135		%Rec	1	3/31/2021 12:21:45 PM
Surr: 4-Bromofluorobenzene	99.6	65 - 135		%Rec	1	3/31/2021 12:21:45 PM

Volatile Organic Compounds by EPA Method 8260D

Batch ID: 31836 Analyst: KT

Benzene	ND	0.0216		mg/Kg-dry	1	3/31/2021 12:21:45 PM
---------	----	--------	--	-----------	---	-----------------------



Analytical Report

Work Order: 2103484
Date Reported: 4/7/2021

Client: Shannon & Wilson
Project: Cascade Mill Parkway
Lab ID: 2103484-002
Client Sample ID: B-13-21/R-9 @ 47'

Collection Date: 3/25/2021 11:55:00 PM

Matrix: Soil

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Volatile Organic Compounds by EPA Method 8260D

Batch ID: 31836 Analyst: KT

Toluene	ND	0.0703		mg/Kg-dry	1	3/31/2021 12:21:45 PM
Ethylbenzene	ND	0.0270		mg/Kg-dry	1	3/31/2021 12:21:45 PM
m,p-Xylene	ND	0.0541		mg/Kg-dry	1	3/31/2021 12:21:45 PM
o-Xylene	ND	0.0270		mg/Kg-dry	1	3/31/2021 12:21:45 PM
Surr: Dibromofluoromethane	101	82.3 - 112		%Rec	1	3/31/2021 12:21:45 PM
Surr: Toluene-d8	102	90.7 - 109		%Rec	1	3/31/2021 12:21:45 PM
Surr: 1-Bromo-4-fluorobenzene	98.1	88.4 - 109		%Rec	1	3/31/2021 12:21:45 PM

Mercury by EPA Method 7471

Batch ID: 31871 Analyst: LB

Mercury	ND	0.263		mg/Kg-dry	1	4/5/2021 2:51:06 PM
---------	----	-------	--	-----------	---	---------------------

Total Metals by EPA Method 6020B

Batch ID: 31896 Analyst: EH

Arsenic	2.46	0.102		mg/Kg-dry	1	4/7/2021 4:02:18 PM
Barium	67.2	0.508		mg/Kg-dry	1	4/7/2021 4:02:18 PM
Cadmium	ND	0.169		mg/Kg-dry	1	4/7/2021 4:02:18 PM
Chromium	16.6	0.339		mg/Kg-dry	1	4/7/2021 4:02:18 PM
Lead	2.49	0.169		mg/Kg-dry	1	4/7/2021 4:02:18 PM
Selenium	1.72	0.169		mg/Kg-dry	1	4/7/2021 4:02:18 PM
Silver	ND	0.127		mg/Kg-dry	1	4/7/2021 4:02:18 PM

Sample Moisture (Percent Moisture)

Batch ID: R66167 Analyst: CH

Percent Moisture	6.97			wt%	1	3/29/2021 2:09:28 PM
------------------	------	--	--	-----	---	----------------------



Client: Shannon & Wilson
Project: Cascade Mill Parkway
Lab ID: 2103484-003
Client Sample ID: B-14-21/R-9 @ 48'

Collection Date: 3/27/2021 12:40:00 AM

Matrix: Soil

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Batch ID: 31813 Analyst: MM

Diesel (Fuel Oil)	ND	47.4		mg/Kg-dry	1	3/30/2021 9:24:15 AM
Heavy Oil	ND	94.9		mg/Kg-dry	1	3/30/2021 9:24:15 AM
Surr: 2-Fluorobiphenyl	87.6	50 - 150		%Rec	1	3/30/2021 9:24:15 AM
Surr: o-Terphenyl	88.4	50 - 150		%Rec	1	3/30/2021 9:24:15 AM

Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Batch ID: 31842 Analyst: SB

Naphthalene	ND	18.1		µg/Kg-dry	1	3/31/2021 9:20:37 PM
2-Methylnaphthalene	ND	18.1		µg/Kg-dry	1	3/31/2021 9:20:37 PM
1-Methylnaphthalene	ND	18.1		µg/Kg-dry	1	3/31/2021 9:20:37 PM
Acenaphthene	ND	18.1		µg/Kg-dry	1	3/31/2021 9:20:37 PM
Acenaphthylene	ND	18.1		µg/Kg-dry	1	3/31/2021 9:20:37 PM
Fluorene	ND	18.1		µg/Kg-dry	1	3/31/2021 9:20:37 PM
Pentachlorophenol	ND	72.5		µg/Kg-dry	1	3/31/2021 9:20:37 PM
Phenanthrene	ND	36.3		µg/Kg-dry	1	3/31/2021 9:20:37 PM
Anthracene	ND	36.3		µg/Kg-dry	1	3/31/2021 9:20:37 PM
Fluoranthene	ND	36.3		µg/Kg-dry	1	3/31/2021 9:20:37 PM
Pyrene	ND	36.3		µg/Kg-dry	1	3/31/2021 9:20:37 PM
Benz(a)anthracene	ND	18.1		µg/Kg-dry	1	3/31/2021 9:20:37 PM
Chrysene	ND	36.3		µg/Kg-dry	1	3/31/2021 9:20:37 PM
Benzo(b)fluoranthene	ND	18.1		µg/Kg-dry	1	3/31/2021 9:20:37 PM
Benzo(k)fluoranthene	ND	18.1		µg/Kg-dry	1	3/31/2021 9:20:37 PM
Benzo(a)pyrene	ND	18.1		µg/Kg-dry	1	3/31/2021 9:20:37 PM
Indeno(1,2,3-cd)pyrene	ND	36.3		µg/Kg-dry	1	3/31/2021 9:20:37 PM
Dibenz(a,h)anthracene	ND	36.3		µg/Kg-dry	1	3/31/2021 9:20:37 PM
Benzo(g,h,i)perylene	ND	18.1		µg/Kg-dry	1	3/31/2021 9:20:37 PM
Surr: 2,4,6-Tribromophenol	72.0	19.4 - 153		%Rec	1	3/31/2021 9:20:37 PM
Surr: 2-Fluorobiphenyl	68.3	19 - 135		%Rec	1	3/31/2021 9:20:37 PM
Surr: Terphenyl-d14 (surr)	84.0	42.9 - 156		%Rec	1	3/31/2021 9:20:37 PM

Gasoline by NWTPH-Gx

Batch ID: 31836 Analyst: KT

Gasoline	ND	7.33		mg/Kg-dry	1	3/31/2021 12:52:12 PM
Surr: Toluene-d8	99.3	65 - 135		%Rec	1	3/31/2021 12:52:12 PM
Surr: 4-Bromofluorobenzene	97.3	65 - 135		%Rec	1	3/31/2021 12:52:12 PM

Volatile Organic Compounds by EPA Method 8260D

Batch ID: 31836 Analyst: KT

Benzene	ND	0.0293		mg/Kg-dry	1	3/31/2021 12:52:12 PM
---------	----	--------	--	-----------	---	-----------------------



Client: Shannon & Wilson
Project: Cascade Mill Parkway
Lab ID: 2103484-003
Client Sample ID: B-14-21/R-9 @ 48'

Collection Date: 3/27/2021 12:40:00 AM

Matrix: Soil

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Volatile Organic Compounds by EPA Method 8260D

Batch ID: 31836 Analyst: KT

Toluene	ND	0.0953		mg/Kg-dry	1	3/31/2021 12:52:12 PM
Ethylbenzene	ND	0.0366		mg/Kg-dry	1	3/31/2021 12:52:12 PM
m,p-Xylene	ND	0.0733		mg/Kg-dry	1	3/31/2021 12:52:12 PM
o-Xylene	ND	0.0366		mg/Kg-dry	1	3/31/2021 12:52:12 PM
Surr: Dibromofluoromethane	102	82.3 - 112		%Rec	1	3/31/2021 12:52:12 PM
Surr: Toluene-d8	102	90.7 - 109		%Rec	1	3/31/2021 12:52:12 PM
Surr: 1-Bromo-4-fluorobenzene	95.9	88.4 - 109		%Rec	1	3/31/2021 12:52:12 PM

Mercury by EPA Method 7471

Batch ID: 31871 Analyst: LB

Mercury	ND	0.251		mg/Kg-dry	1	4/5/2021 2:52:42 PM
---------	----	-------	--	-----------	---	---------------------

Total Metals by EPA Method 6020B

Batch ID: 31896 Analyst: EH

Arsenic	3.45	0.101		mg/Kg-dry	1	4/7/2021 3:17:35 PM
Barium	63.9	0.503		mg/Kg-dry	1	4/7/2021 3:17:35 PM
Cadmium	ND	0.168		mg/Kg-dry	1	4/7/2021 3:17:35 PM
Chromium	18.8	0.336		mg/Kg-dry	1	4/7/2021 3:17:35 PM
Lead	5.54	0.168		mg/Kg-dry	1	4/7/2021 3:17:35 PM
Selenium	1.85	0.168		mg/Kg-dry	1	4/7/2021 3:17:35 PM
Silver	ND	0.126		mg/Kg-dry	1	4/7/2021 3:17:35 PM

Sample Moisture (Percent Moisture)

Batch ID: R66167 Analyst: CH

Percent Moisture	6.13			wt%	1	3/29/2021 2:09:28 PM
------------------	------	--	--	-----	---	----------------------

Work Order: 2103484
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Total Metals by EPA Method 6020B

Sample ID: MB-31896	SampType: MBLK	Units: mg/Kg	Prep Date: 4/6/2021	RunNo: 66399							
Client ID: MBLKS	Batch ID: 31896		Analysis Date: 4/7/2021	SeqNo: 1335933							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Arsenic	ND	0.0968									
Barium	ND	0.484									
Cadmium	ND	0.161									
Chromium	ND	0.323									
Lead	ND	0.161									
Selenium	ND	0.161									
Silver	ND	0.121									

Sample ID: LCS-31896	SampType: LCS	Units: mg/Kg	Prep Date: 4/6/2021	RunNo: 66399							
Client ID: LCSS	Batch ID: 31896		Analysis Date: 4/7/2021	SeqNo: 1335935							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Arsenic	36.1	0.0938	39.06	0	92.3	80	120				
Barium	36.3	0.469	39.06	0	93.0	80	120				
Cadmium	1.87	0.156	1.953	0	95.8	80	120				
Chromium	38.4	0.312	39.06	0	98.3	80	120				
Lead	19.2	0.156	19.53	0	98.4	80	120				
Selenium	3.46	0.156	3.906	0	88.5	80	120				
Silver	1.99	0.117	1.953	0	102	80	120				

Sample ID: 2103484-003AMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 4/6/2021	RunNo: 66399							
Client ID: B-14-21/R-9 @ 48'	Batch ID: 31896		Analysis Date: 4/7/2021	SeqNo: 1335938							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Arsenic	36.5	0.101	41.94	3.189	79.4	75	125				
Barium	103	0.503	41.94	70.37	77.3	75	125				
Cadmium	1.80	0.168	2.097	0.05875	83.2	75	125				
Chromium	58.9	0.336	41.94	21.21	89.9	75	125				
Lead	20.9	0.168	20.97	5.234	74.8	75	125				S

Work Order: 2103484
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Total Metals by EPA Method 6020B

Sample ID: 2103484-003AMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 4/6/2021	RunNo: 66399							
Client ID: B-14-21/R-9 @ 48'	Batch ID: 31896		Analysis Date: 4/7/2021	SeqNo: 1335938							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Selenium	5.41	0.168	4.194	1.706	88.2	75	125				
Silver	1.74	0.126	2.097	0.07841	79.1	75	125				

NOTES:

S - Outlying spike recovery(ies) observed. A duplicate analysis was performed and recovered within range.

Sample ID: 2103484-003AMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 4/6/2021	RunNo: 66399							
Client ID: B-14-21/R-9 @ 48'	Batch ID: 31896		Analysis Date: 4/7/2021	SeqNo: 1335939							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	42.6	0.101	41.94	3.189	94.0	75	125	36.49	15.5	20	
Barium	118	0.503	41.94	70.37	113	75	125	102.8	13.4	20	
Cadmium	1.98	0.168	2.097	0.05875	91.6	75	125	1.805	9.30	20	
Chromium	58.4	0.336	41.94	21.21	88.7	75	125	58.92	0.849	20	
Lead	23.1	0.168	20.97	5.234	85.1	75	125	20.92	9.83	20	
Selenium	5.99	0.168	4.194	1.706	102	75	125	5.405	10.3	20	
Silver	1.89	0.126	2.097	0.07841	86.4	75	125	1.737	8.48	20	

Work Order: 2103484
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Mercury by EPA Method 7471

Sample ID: MB-31871	SampType: MBLK	Units: mg/Kg	Prep Date: 4/5/2021	RunNo: 66344							
Client ID: MBLKS	Batch ID: 31871		Analysis Date: 4/5/2021	SeqNo: 1334723							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury ND 0.250

Sample ID: LCS-31871	SampType: LCS	Units: mg/Kg	Prep Date: 4/5/2021	RunNo: 66344							
Client ID: LCSS	Batch ID: 31871		Analysis Date: 4/5/2021	SeqNo: 1334724							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.488 0.250 0.5000 0 97.6 80 120

Sample ID: 2103484-001ADUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 4/5/2021	RunNo: 66344							
Client ID: B-15P-21/S-5 @ 21'	Batch ID: 31871		Analysis Date: 4/5/2021	SeqNo: 1334726							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury ND 0.263 0 20

Sample ID: 2103484-001AMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 4/5/2021	RunNo: 66344							
Client ID: B-15P-21/S-5 @ 21'	Batch ID: 31871		Analysis Date: 4/5/2021	SeqNo: 1334727							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.570 0.258 0.5161 0.01486 108 70 130

Sample ID: 2103484-001AMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 4/5/2021	RunNo: 66344							
Client ID: B-15P-21/S-5 @ 21'	Batch ID: 31871		Analysis Date: 4/5/2021	SeqNo: 1334728							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.680 0.263 0.5258 0.01486 127 70 130 0.5698 17.7 20

Work Order: 2103484
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Sample ID: MB-31813	SampType: MBLK	Units: mg/Kg	Prep Date: 3/29/2021	RunNo: 66200							
Client ID: MBLKS	Batch ID: 31813		Analysis Date: 3/29/2021	SeqNo: 1332127							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Diesel (Fuel Oil)	ND	50.0									
Heavy Oil	ND	100									
Surr: 2-Fluorobiphenyl	8.86		10.00		88.6	50	150				
Surr: o-Terphenyl	8.78		10.00		87.8	50	150				

Sample ID: LCS-31813	SampType: LCS	Units: mg/Kg	Prep Date: 3/29/2021	RunNo: 66200							
Client ID: LCSS	Batch ID: 31813		Analysis Date: 3/29/2021	SeqNo: 1332128							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Diesel (Fuel Oil)	400	50.0	500.0	0	80.1	73.7	114				
Surr: 2-Fluorobiphenyl	8.36		10.00		83.6	50	150				
Surr: o-Terphenyl	9.05		10.00		90.5	50	150				

Sample ID: 2103472-001AMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 3/29/2021	RunNo: 66200							
Client ID: BATCH	Batch ID: 31813		Analysis Date: 3/29/2021	SeqNo: 1332130							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Diesel (Fuel Oil)	420	51.6	516.0	0	81.4	61.4	129				
Surr: 2-Fluorobiphenyl	8.41		10.32		81.5	50	150				
Surr: o-Terphenyl	9.18		10.32		89.0	50	150				

Sample ID: 2103472-001AMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 3/29/2021	RunNo: 66200							
Client ID: BATCH	Batch ID: 31813		Analysis Date: 3/29/2021	SeqNo: 1332131							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Diesel (Fuel Oil)	378	45.7	457.3	0	82.7	61.4	129	419.8	10.4	30	
Surr: 2-Fluorobiphenyl	7.93		9.147		86.7	50	150		0		
Surr: o-Terphenyl	9.08		9.147		99.3	50	150		0		

Work Order: 2103484
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Sample ID: MB-31842	SampType: MBLK	Units: µg/Kg	Prep Date: 3/31/2021	RunNo: 66291							
Client ID: MBLKS	Batch ID: 31842		Analysis Date: 3/31/2021	SeqNo: 1333537							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	ND	20.0									
2-Methylnaphthalene	ND	20.0									
1-Methylnaphthalene	ND	20.0									
Acenaphthene	ND	20.0									
Acenaphthylene	ND	20.0									
Fluorene	ND	20.0									
Pentachlorophenol	ND	80.0									
Phenanthrene	ND	40.0									
Anthracene	ND	40.0									
Fluoranthene	ND	40.0									
Pyrene	ND	40.0									
Benz(a)anthracene	ND	20.0									
Chrysene	ND	40.0									
Benzo(b)fluoranthene	ND	20.0									
Benzo(k)fluoranthene	ND	20.0									
Benzo(a)pyrene	ND	20.0									
Indeno(1,2,3-cd)pyrene	ND	40.0									
Dibenz(a,h)anthracene	ND	40.0									
Benzo(g,h,i)perylene	ND	20.0									
Surr: 2,4,6-Tribromophenol	1,400		2,000		70.1	19.4	153				
Surr: 2-Fluorobiphenyl	793		1,000		79.3	19	135				
Surr: Terphenyl-d14 (surr)	1,040		1,000		104	42.9	156				

Sample ID: LCS-31842	SampType: LCS	Units: µg/Kg	Prep Date: 3/31/2021	RunNo: 66291							
Client ID: LCSS	Batch ID: 31842		Analysis Date: 3/31/2021	SeqNo: 1333538							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	1,890	20.0	2,000	0	94.3	62.7	127				
2-Methylnaphthalene	1,990	20.0	2,000	0	99.4	62.7	132				
1-Methylnaphthalene	1,860	20.0	2,000	0	92.9	61.4	131				

Work Order: 2103484
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Sample ID: LCS-31842	SampType: LCS	Units: µg/Kg	Prep Date: 3/31/2021	RunNo: 66291							
Client ID: LCSS	Batch ID: 31842		Analysis Date: 3/31/2021	SeqNo: 1333538							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Acenaphthene	1,820	20.0	2,000	0	91.0	59.2	132				
Acenaphthylene	1,910	20.0	2,000	0	95.5	62	132				
Fluorene	1,840	20.0	2,000	0	92.0	59.1	136				
Pentachlorophenol	1,830	80.0	2,000	0	91.6	5	112				
Phenanthrene	1,850	40.0	2,000	0	92.3	54.1	139				
Anthracene	1,860	40.0	2,000	0	93.2	55.5	136				
Fluoranthene	1,940	40.0	2,000	0	97.2	52.8	149				
Pyrene	1,910	40.0	2,000	0	95.3	53.6	146				
Benz(a)anthracene	1,810	20.0	2,000	0	90.5	49.7	153				
Chrysene	1,930	40.0	2,000	0	96.5	52.6	147				
Benzo(b)fluoranthene	1,900	20.0	2,000	0	95.1	50.6	151				
Benzo(k)fluoranthene	1,930	20.0	2,000	0	96.7	47.1	155				
Benzo(a)pyrene	2,050	20.0	2,000	0	103	48.3	169				
Indeno(1,2,3-cd)pyrene	1,890	40.0	2,000	0	94.5	52.3	145				
Dibenz(a,h)anthracene	1,720	40.0	2,000	0	85.8	53	144				
Benzo(g,h,i)perylene	1,790	20.0	2,000	0	89.6	49.7	144				
Surr: 2,4,6-Tribromophenol	2,170		2,000		109	19.4	153				
Surr: 2-Fluorobiphenyl	995		1,000		99.5	19	135				
Surr: Terphenyl-d14 (surr)	1,050		1,000		105	42.9	156				

Sample ID: 2103484-001AMS	SampType: MS	Units: µg/Kg-dry	Prep Date: 3/31/2021	RunNo: 66291							
Client ID: B-15P-21/S-5 @ 21'	Batch ID: 31842		Analysis Date: 3/31/2021	SeqNo: 1333540							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Naphthalene	1,790	21.0	2,095	0	85.2	28.7	139				
2-Methylnaphthalene	1,890	21.0	2,095	0	90.4	43.5	130				
1-Methylnaphthalene	1,740	21.0	2,095	0	83.1	42.6	127				
Acenaphthene	1,700	21.0	2,095	0	81.2	45.1	123				
Acenaphthylene	1,800	21.0	2,095	0	85.8	45.3	129				
Fluorene	1,740	21.0	2,095	0	83.3	41.6	128				

Work Order: 2103484
 CLIENT: Shannon & Wilson
 Project: Cascade Mill Parkway

QC SUMMARY REPORT
Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Sample ID: 2103484-001AMS	SampType: MS	Units: µg/Kg-dry				Prep Date: 3/31/2021	RunNo: 66291				
Client ID: B-15P-21/S-5 @ 21'	Batch ID: 31842					Analysis Date: 3/31/2021	SeqNo: 1333540				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Pentachlorophenol	2,010	83.8	2,095	0	95.8	5	188				
Phenanthrene	1,740	41.9	2,095	0	82.8	24.2	142				
Anthracene	1,760	41.9	2,095	0	84.1	33.1	143				
Fluoranthene	1,840	41.9	2,095	0	87.6	35.5	147				
Pyrene	1,780	41.9	2,095	0	85.1	38.3	141				
Benz(a)anthracene	1,700	21.0	2,095	0	81.3	42.5	145				
Chrysene	1,820	41.9	2,095	0	86.8	39.7	134				
Benzo(b)fluoranthene	1,590	21.0	2,095	0	75.9	29.9	152				
Benzo(k)fluoranthene	1,650	21.0	2,095	0	78.8	33.2	143.5				
Benzo(a)pyrene	1,940	21.0	2,095	0	92.7	38.2	156				
Indeno(1,2,3-cd)pyrene	1,710	41.9	2,095	0	81.5	41.4	128				
Dibenz(a,h)anthracene	1,710	41.9	2,095	0	81.4	40.4	129				
Benzo(g,h,i)perylene	1,660	21.0	2,095	0	79.2	34.2	131				
Surr: 2,4,6-Tribromophenol	2,050		2,095		97.6	19.4	153				
Surr: 2-Fluorobiphenyl	929		1,048		88.6	19	135				
Surr: Terphenyl-d14 (surr)	956		1,048		91.3	42.9	156				

Sample ID: 2103484-001AMSD	SampType: MSD	Units: µg/Kg-dry				Prep Date: 3/31/2021	RunNo: 66291				
Client ID: B-15P-21/S-5 @ 21'	Batch ID: 31842					Analysis Date: 3/31/2021	SeqNo: 1333541				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	1,690	20.3	2,027	0	83.3	28.7	139	1,786	5.65	30	
2-Methylnaphthalene	1,760	20.3	2,027	0	86.8	43.5	130	1,895	7.37	30	
1-Methylnaphthalene	1,680	20.3	2,027	0	82.7	42.6	127	1,741	3.78	30	
Acenaphthene	1,610	20.3	2,027	0	79.5	45.1	123	1,702	5.48	30	
Acenaphthylene	1,690	20.3	2,027	0	83.2	45.3	129	1,797	6.34	30	
Fluorene	1,640	20.3	2,027	0	80.9	41.6	128	1,745	6.17	30	
Pentachlorophenol	1,910	81.1	2,027	0	94.2	5	188	2,008	5.01	30	
Phenanthrene	1,660	40.5	2,027	0	82.1	24.2	142	1,736	4.27	30	
Anthracene	1,680	40.5	2,027	0	82.7	33.1	143	1,763	4.97	30	

Work Order: 2103484
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Fluoranthene	1,730	40.5	2,027	0	85.5	35.5	147	1,836	5.73	30	
Pyrene	1,680	40.5	2,027	0	82.7	38.3	141	1,784	6.21	30	
Benz(a)anthracene	1,600	20.3	2,027	0	79.0	42.5	145	1,703	6.14	30	
Chrysene	1,700	40.5	2,027	0	83.6	39.7	134	1,819	7.03	30	
Benzo(b)fluoranthene	1,690	20.3	2,027	0	83.3	29.9	152	1,590	5.98	30	
Benzo(k)fluoranthene	1,720	20.3	2,027	0	84.6	33.2	143.5	1,651	3.83	30	
Benzo(a)pyrene	1,780	20.3	2,027	0	87.9	38.2	156	1,942	8.63	30	
Indeno(1,2,3-cd)pyrene	1,650	40.5	2,027	0	81.5	41.4	128	1,708	3.32	30	
Dibenz(a,h)anthracene	1,600	40.5	2,027	0	78.9	40.4	129	1,705	6.46	30	
Benzo(g,h,i)perylene	1,560	20.3	2,027	0	77.2	34.2	131	1,660	5.96	30	
Surr: 2,4,6-Tribromophenol	1,930		2,027		95.1	19.4	153		0		
Surr: 2-Fluorobiphenyl	869		1,013		85.7	19	135		0		
Surr: Terphenyl-d14 (surr)	898		1,013		88.6	42.9	156		0		

Work Order: 2103484
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Gasoline by NWTPH-Gx

Sample ID: LCS-31836	SampType: LCS	Units: mg/Kg			Prep Date: 3/31/2021	RunNo: 66269					
Client ID: LCSS	Batch ID: 31836				Analysis Date: 3/31/2021	SeqNo: 1333239					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	24.3	5.00	25.00	0	97.4	65	135				
Surr: Toluene-d8	1.23		1.250		98.1	65	135				
Surr: 4-Bromofluorobenzene	1.27		1.250		102	65	135				

Sample ID: MB-31836	SampType: MBLK	Units: mg/Kg			Prep Date: 3/31/2021	RunNo: 66269					
Client ID: MBLKS	Batch ID: 31836				Analysis Date: 3/31/2021	SeqNo: 1333240					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	ND	5.00									
Surr: Toluene-d8	1.24		1.250		99.0	65	135				
Surr: 4-Bromofluorobenzene	1.25		1.250		99.9	65	135				

Sample ID: 2103484-001BDUP	SampType: DUP	Units: mg/Kg-dry			Prep Date: 3/31/2021	RunNo: 66269					
Client ID: B-15P-21/S-5 @ 21'	Batch ID: 31836				Analysis Date: 3/31/2021	SeqNo: 1333220					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	ND	5.46						0		30	
Surr: Toluene-d8	1.35		1.365		99.1	65	135		0		
Surr: 4-Bromofluorobenzene	1.36		1.365		99.8	65	135		0		

Sample ID: 2103508-001BDUP	SampType: DUP	Units: mg/Kg-dry			Prep Date: 3/31/2021	RunNo: 66269					
Client ID: BATCH	Batch ID: 31836				Analysis Date: 3/31/2021	SeqNo: 1333224					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	ND	4.13						0		30	
Gasoline Range Organics (C6-C12)	4.59	4.13						4.448	3.24	30	
Surr: Toluene-d8	1.03		1.033		99.6	65	135		0		
Surr: 4-Bromofluorobenzene	1.02		1.033		99.0	65	135		0		

Work Order: 2103484
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Gasoline by NWTPH-Gx

Sample ID: 2103508-001BDUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 3/31/2021	RunNo: 66269							
Client ID: BATCH	Batch ID: 31836	Analysis Date: 3/31/2021	SeqNo: 1333224								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

NOTES:

GRO - Indicates the presence of unresolved compounds eluting from hexane to dodecane (~C6-C12). Pattern does not resemble a known petroleum distillate.

Sample ID: 2103508-002BMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 3/31/2021	RunNo: 66269							
Client ID: BATCH	Batch ID: 31836	Analysis Date: 3/31/2021	SeqNo: 1333226								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Gasoline	28.2	5.53	27.63	0	102	65	135				
Surr: Toluene-d8	1.36		1.382		98.7	65	135				
Surr: 4-Bromofluorobenzene	1.42		1.382		103	65	135				

Work Order: 2103484
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260D

Sample ID: LCS-31836	SampType: LCS	Units: mg/Kg	Prep Date: 3/31/2021	RunNo: 66268							
Client ID: LCSS	Batch ID: 31836		Analysis Date: 3/31/2021	SeqNo: 1333217							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	1.02	0.0200	1.000	0	102	80	120				
Toluene	1.01	0.0650	1.000	0	101	80	120				
Ethylbenzene	1.08	0.0250	1.000	0	108	80	120				
m,p-Xylene	2.08	0.0500	2.000	0	104	80	120				
o-Xylene	1.03	0.0250	1.000	0	103	80	120				
Surr: Dibromofluoromethane	1.27		1.250		102	80	120				
Surr: Toluene-d8	1.24		1.250		98.9	80	120				
Surr: 1-Bromo-4-fluorobenzene	1.28		1.250		102	80	120				

Sample ID: MB-31836	SampType: MBLK	Units: mg/Kg	Prep Date: 3/31/2021	RunNo: 66268							
Client ID: MBLKS	Batch ID: 31836		Analysis Date: 3/31/2021	SeqNo: 1333216							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	ND	0.0200									
Toluene	ND	0.0650									
Ethylbenzene	ND	0.0250									
m,p-Xylene	ND	0.0500									
o-Xylene	ND	0.0250									
Surr: Dibromofluoromethane	1.29		1.250		103	82.3	112				
Surr: Toluene-d8	1.28		1.250		102	90.7	109				
Surr: 1-Bromo-4-fluorobenzene	1.23		1.250		98.5	88.4	109				

Sample ID: 2103484-001BDUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 3/31/2021	RunNo: 66268							
Client ID: B-15P-21/S-5 @ 21'	Batch ID: 31836		Analysis Date: 3/31/2021	SeqNo: 1333196							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	ND	0.0218						0		30	
Toluene	ND	0.0710						0		30	
Ethylbenzene	ND	0.0273						0		30	

Work Order: 2103484
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260D

Sample ID: 2103484-001BDUP		SampType: DUP		Units: mg/Kg-dry		Prep Date: 3/31/2021		RunNo: 66268			
Client ID: B-15P-21/S-5 @ 21'		Batch ID: 31836				Analysis Date: 3/31/2021		SeqNo: 1333196			
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
m,p-Xylene	ND	0.0546						0		30	
o-Xylene	ND	0.0273						0		30	
Surr: Dibromofluoromethane	1.39		1.365		101	82.3	112		0		
Surr: Toluene-d8	1.39		1.365		102	90.7	109		0		
Surr: 1-Bromo-4-fluorobenzene	1.34		1.365		98.3	88.4	109		0		

Sample ID: 2103508-001BDUP		SampType: DUP		Units: mg/Kg-dry		Prep Date: 3/31/2021		RunNo: 66268			
Client ID: BATCH		Batch ID: 31836				Analysis Date: 3/31/2021		SeqNo: 1333201			
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	ND	0.0165						0		30	
Toluene	ND	0.0537						0		30	
Ethylbenzene	ND	0.0207						0		30	
m,p-Xylene	ND	0.0413						0		30	
o-Xylene	ND	0.0207						0		30	
Surr: Dibromofluoromethane	1.04		1.033		101	82.3	112		0		
Surr: Toluene-d8	1.06		1.033		102	90.7	109		0		
Surr: 1-Bromo-4-fluorobenzene	1.01		1.033		97.6	88.4	109		0		

Sample ID: 2103484-002BMS		SampType: MS		Units: mg/Kg-dry		Prep Date: 3/31/2021		RunNo: 66268			
Client ID: B-13-21/R-9 @ 47'		Batch ID: 31836				Analysis Date: 3/31/2021		SeqNo: 1333198			
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	1.16	0.0216	1.081	0	107	76.8	129				
Toluene	1.16	0.0703	1.081	0	107	77.8	127				
Ethylbenzene	1.18	0.0270	1.081	0	109	78.7	130				
m,p-Xylene	2.24	0.0541	2.163	0	104	79.3	127				
o-Xylene	1.10	0.0270	1.081	0	101	80.7	124				
Surr: Dibromofluoromethane	1.44		1.352		107	82.3	112				

Work Order: 2103484
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260D

Sample ID: 2103484-002BMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 3/31/2021	RunNo: 66268							
Client ID: B-13-21/R-9 @ 47'	Batch ID: 31836		Analysis Date: 3/31/2021	SeqNo: 1333198							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Surr: Toluene-d8	1.41		1.352		104	90.7	109				
Surr: 1-Bromo-4-fluorobenzene	1.40		1.352		104	88.4	109				

Client Name: SW	Work Order Number: 2103484
Logged by: Gabrielle Coeulle	Date Received: 3/29/2021 9:06:00 AM

Chain of Custody

1. Is Chain of Custody complete? Yes No Not Present
2. How was the sample delivered? Client

Log In

3. Coolers are present? Yes No NA
4. Shipping container/cooler in good condition? Yes No
5. Custody Seals present on shipping container/cooler?
(Refer to comments for Custody Seals not intact) Yes No Not Present
6. Was an attempt made to cool the samples? Yes No NA
7. Were all items received at a temperature of >2°C to 6°C * Yes No NA
8. Sample(s) in proper container(s)? Yes No
9. Sufficient sample volume for indicated test(s)? Yes No
10. Are samples properly preserved? Yes No
11. Was preservative added to bottles? Yes No NA
12. Is there headspace in the VOA vials? Yes No NA
13. Did all samples containers arrive in good condition(unbroken)? Yes No
14. Does paperwork match bottle labels? Yes No
15. Are matrices correctly identified on Chain of Custody? Yes No
16. Is it clear what analyses were requested? Yes No
17. Were all holding times able to be met? Yes No

Special Handling (if applicable)

18. Was client notified of all discrepancies with this order? Yes No NA

Person Notified:	<input type="text" value="Dave Randall"/>	Date:	<input type="text" value="3/29/2021"/>
By Whom:	<input type="text" value="Gabrielle Coeulle"/>	Via:	<input checked="" type="checkbox"/> eMail <input type="checkbox"/> Phone <input type="checkbox"/> Fax <input type="checkbox"/> In Person
Regarding:	<input type="text" value="Unable to test PCP by 85-40. Is 8270SIM ok?"/>		
Client Instructions:	<input type="text" value="Yes."/>		

19. Additional remarks:

Item Information

Item #	Temp °C
Sample 1	1.3

* Note: DoD/ELAP and TNI require items to be received at 4°C +/- 2°C



3600 Fremont Ave N.
Seattle, WA 98103
Tel: 206-352-3790
Fax: 206-352-7178

Chain of Custody Record & Laboratory Services Agreement

Date: 3/27/21 Page: 1 of 1
Project Name: Cascade Mill Parkway
Project No: 106384
Laboratory Project No (Internal): 2103484

Client: Shannon and Wilson

Address: 400 N 34th St, Suite 100

City, State, zip: Seattle, WA 98103

Telephone:

Location: Yakima
Report To (PM): David Randall
PM Email: djr@shannw1.com

Sample Disposal: Return to client Disposal by lab (after 30 days)

Sample Name	Sample Date	Sample Time	Sample Type (Matrix)*	# of Cont.	YOCs (EPA 8260 / 824)	BTEX	Gasoline Range Organics (GX)	Hydrocarbon Identification (HClD)	Diesel/Heavy Oil Range Organics (DH)	SVOCs (EPA 8270 / 625)	PAHs (EPA 8082 - SIM)	PCBs (EPA 8270 - SIM)	Metals** (EPA 8082 / 608)	Total (T) Dissolved (D)	Anions (IC)***	EDB (8011)	PENTRCHLOROPHENOL - C1H PCTHPPD 85-40	Comments
1. B-15P-21/S-5 @ 21'	3/22/21	16:00	SOIL	3	X	X	X	X	X	X	X	X	X	X	X	X		
2. B-13-21/R-9 @ 47'	3/15/21	23:55	SOIL	3	X	X	X	X	X	X	X	X	X	X	X	X		
3. B-14-21/R-9 @ 48'	3/27/21	00:40	SOIL	3	X	X	X	X	X	X	X	X	X	X	X	X		
4.																		
5.																		
6.																		
7.																		
8.																		
9.																		
10.																		

*Matrix: A = Air, AQ = Aqueous, B = Bulk, O = Other, P = Product, S = Soil, SD = Sediment, SL = Solid, W = Water, DW = Drinking Water, GW = Ground Water, SW = Storm Water, WW = Waste Water
 **Metals (Circle): MTCAs-5, RCMAs-8, Priority Pollutants, TAL, Individual: Ag Al As B Ba Be Ca Cd Co Cr Cu Fe Hg K Mg Mn Mo Na Ni Pb Sb Se Sr Sn Tl Ti V Zn
 ***Anions (Circle): Nitrate, Nitrite, Chloride, Sulfate, Bromide, O-Phosphate, Fluoride, Nitrate+Nitrite

I represent that I am authorized to enter into this Agreement with Fremont Analytical on behalf of the Client named above, that I have verified Client's agreement to each of the terms on the front and backside of this Agreement.

Relinquished (Signature) Kristin McFarland Print Name Kristin McFarland Date/Time 3/28/21 12:30
 Relinquished (Signature) David Randall Print Name David Randall Date/Time 3/29/21 0820
 Received (Signature) David Randall Print Name David Randall Date/Time 3/29/21 1231
 Received (Signature) Shannon Wilson Print Name Shannon Wilson Date/Time 3/25/21 0906



Shannon & Wilson

Dave Randall

400 N. 34th Street, Suite 100

Seattle, WA 98103

RE: Cascade Mill Parkway

Work Order Number: 2104312

April 29, 2021

Attention Dave Randall:

Fremont Analytical, Inc. received 1 sample(s) on 4/22/2021 for the analyses presented in the following report.

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Gasoline by NWTPH-Gx

Mercury by EPA Method 7471

Sample Moisture (Percent Moisture)

Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Total Metals by EPA Method 6020B

Volatile Organic Compounds by EPA Method 8260D

This report consists of the following:

- Case Narrative
- Analytical Results
- Applicable Quality Control Summary Reports
- Chain of Custody

All analyses were performed consistent with the Quality Assurance program of Fremont Analytical, Inc. Please contact the laboratory if you should have any questions about the results.

Thank you for using Fremont Analytical.

Sincerely,

Brianna Barnes
Project Manager

*DoD-ELAP Accreditation #79636 by PJLA, ISO/IEC 17025:2017 and QSM 5.3 for Environmental Testing
ORELAP Certification: WA 100009 (NELAP Recognized) for Environmental Testing
Washington State Department of Ecology Accredited for Environmental Testing, Lab ID C910*

Original



Date: 04/29/2021

CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway
Work Order: 2104312

Work Order Sample Summary

Lab Sample ID	Client Sample ID	Date/Time Collected	Date/Time Received
2104312-001	B-13-21/R-8@39	04/22/2021 1:31 PM	04/22/2021 3:41 PM

Note: If no "Time Collected" is supplied, a default of 12:00AM is assigned

Original

CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

I. SAMPLE RECEIPT:

Samples receipt information is recorded on the attached Sample Receipt Checklist.

II. GENERAL REPORTING COMMENTS:

Results are reported on a wet weight basis unless dry-weight correction is denoted in the units field on the analytical report ("mg/kg-dry" or "ug/kg-dry").

Matrix Spike (MS) and MS Duplicate (MSD) samples are tested from an analytical batch of "like" matrix to check for possible matrix effect. The MS and MSD will provide site specific matrix data only for those samples which are spiked by the laboratory. The sample chosen for spike purposes may or may not have been a sample submitted in this sample delivery group. The validity of the analytical procedures for which data is reported in this analytical report is determined by the Laboratory Control Sample (LCS) and the Method Blank (MB). The LCS and the MB are processed with the samples and the MS/MSD to ensure method criteria are achieved throughout the entire analytical process.

III. ANALYSES AND EXCEPTIONS:

Exceptions associated with this report will be footnoted in the analytical results page(s) or the quality control summary page(s) and/or noted below.

Qualifiers:

- * - Flagged value is not within established control limits
- B - Analyte detected in the associated Method Blank
- D - Dilution was required
- E - Value above quantitation range
- H - Holding times for preparation or analysis exceeded
- I - Analyte with an internal standard that does not meet established acceptance criteria
- J - Analyte detected below Reporting Limit
- N - Tentatively Identified Compound (TIC)
- Q - Analyte with an initial or continuing calibration that does not meet established acceptance criteria
- S - Spike recovery outside accepted recovery limits
- ND - Not detected at the Reporting Limit
- R - High relative percent difference observed

Acronyms:

- %Rec - Percent Recovery
- CCB - Continued Calibration Blank
- CCV - Continued Calibration Verification
- DF - Dilution Factor
- DUP - Sample Duplicate
- HEM - Hexane Extractable Material
- ICV - Initial Calibration Verification
- LCS/LCSD - Laboratory Control Sample / Laboratory Control Sample Duplicate
- MCL - Maximum Contaminant Level
- MB or MBLANK - Method Blank
- MDL - Method Detection Limit
- MS/MSD - Matrix Spike / Matrix Spike Duplicate
- PDS - Post Digestion Spike
- Ref Val - Reference Value
- REP - Sample Replicate
- RL - Reporting Limit
- RPD - Relative Percent Difference
- SD - Serial Dilution
- SGT - Silica Gel Treatment
- SPK - Spike
- Surr - Surrogate



Client: Shannon & Wilson
Project: Cascade Mill Parkway
Lab ID: 2104312-001
Client Sample ID: B-13-21/R-8@39

Collection Date: 4/22/2021 1:31:00 PM
Matrix: Soil

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Batch ID: 32091 Analyst: MM

Diesel (Fuel Oil)	ND	50.2		mg/Kg-dry	1	4/27/2021 10:59:21 AM
Heavy Oil	ND	100		mg/Kg-dry	1	4/27/2021 10:59:21 AM
Total Petroleum Hydrocarbons	ND	151		mg/Kg-dry	1	4/27/2021 10:59:21 AM
Surr: 2-Fluorobiphenyl	90.7	50 - 150		%Rec	1	4/27/2021 10:59:21 AM
Surr: o-Terphenyl	92.7	50 - 150		%Rec	1	4/27/2021 10:59:21 AM

Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Batch ID: 32099 Analyst: SB

Naphthalene	ND	18.5		µg/Kg-dry	1	4/27/2021 8:46:39 PM
2-Methylnaphthalene	ND	18.5		µg/Kg-dry	1	4/27/2021 8:46:39 PM
1-Methylnaphthalene	ND	18.5		µg/Kg-dry	1	4/27/2021 8:46:39 PM
Acenaphthene	ND	18.5		µg/Kg-dry	1	4/27/2021 8:46:39 PM
Acenaphthylene	ND	18.5		µg/Kg-dry	1	4/27/2021 8:46:39 PM
Fluorene	ND	18.5		µg/Kg-dry	1	4/27/2021 8:46:39 PM
Pentachlorophenol	ND	73.9		µg/Kg-dry	1	4/27/2021 8:46:39 PM
Phenanthrene	ND	36.9		µg/Kg-dry	1	4/27/2021 8:46:39 PM
Anthracene	ND	36.9		µg/Kg-dry	1	4/27/2021 8:46:39 PM
Fluoranthene	ND	36.9		µg/Kg-dry	1	4/27/2021 8:46:39 PM
Pyrene	ND	36.9		µg/Kg-dry	1	4/27/2021 8:46:39 PM
Benz(a)anthracene	ND	18.5		µg/Kg-dry	1	4/27/2021 8:46:39 PM
Chrysene	ND	36.9		µg/Kg-dry	1	4/27/2021 8:46:39 PM
Benzo(b)fluoranthene	ND	18.5		µg/Kg-dry	1	4/27/2021 8:46:39 PM
Benzo(k)fluoranthene	ND	18.5		µg/Kg-dry	1	4/27/2021 8:46:39 PM
Benzo(a)pyrene	ND	18.5		µg/Kg-dry	1	4/27/2021 8:46:39 PM
Indeno(1,2,3-cd)pyrene	ND	36.9		µg/Kg-dry	1	4/27/2021 8:46:39 PM
Dibenz(a,h)anthracene	ND	36.9		µg/Kg-dry	1	4/27/2021 8:46:39 PM
Benzo(g,h,i)perylene	ND	18.5		µg/Kg-dry	1	4/27/2021 8:46:39 PM
Surr: 2,4,6-Tribromophenol	84.6	19.4 - 153		%Rec	1	4/27/2021 8:46:39 PM
Surr: 2-Fluorobiphenyl	75.9	19 - 135		%Rec	1	4/27/2021 8:46:39 PM
Surr: Terphenyl-d14 (surr)	97.1	42.9 - 156		%Rec	1	4/27/2021 8:46:39 PM

Gasoline by NWTPH-Gx

Batch ID: 32102 Analyst: CR

Gasoline	ND	15.4		mg/Kg-dry	1	4/28/2021 4:04:06 AM
Surr: Toluene-d8	105	65 - 135		%Rec	1	4/28/2021 4:04:06 AM
Surr: 4-Bromofluorobenzene	103	65 - 135		%Rec	1	4/28/2021 4:04:06 AM



Client: Shannon & Wilson
Project: Cascade Mill Parkway
Lab ID: 2104312-001
Client Sample ID: B-13-21/R-8@39

Collection Date: 4/22/2021 1:31:00 PM

Matrix: Soil

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
----------	--------	----	------	-------	----	---------------

Volatile Organic Compounds by EPA Method 8260D

Batch ID: 32102 Analyst: CR

Benzene	ND	0.0615		mg/Kg-dry	1	4/28/2021 4:04:06 AM
Toluene	ND	0.200		mg/Kg-dry	1	4/28/2021 4:04:06 AM
Ethylbenzene	ND	0.0769		mg/Kg-dry	1	4/28/2021 4:04:06 AM
m,p-Xylene	ND	0.154		mg/Kg-dry	1	4/28/2021 4:04:06 AM
o-Xylene	ND	0.0769		mg/Kg-dry	1	4/28/2021 4:04:06 AM
Surr: Dibromofluoromethane	91.3	81.9 - 113		%Rec	1	4/28/2021 4:04:06 AM
Surr: Toluene-d8	92.0	82.7 - 115		%Rec	1	4/28/2021 4:04:06 AM
Surr: 1-Bromo-4-fluorobenzene	98.0	87.9 - 109		%Rec	1	4/28/2021 4:04:06 AM

Mercury by EPA Method 7471

Batch ID: 32120 Analyst: LB

Mercury	ND	0.260		mg/Kg-dry	1	4/29/2021 12:39:41 PM
---------	----	-------	--	-----------	---	-----------------------

Total Metals by EPA Method 6020B

Batch ID: 32085 Analyst: EH

Arsenic	2.48	0.102		mg/Kg-dry	1	4/27/2021 8:50:00 PM
Barium	64.8	0.509		mg/Kg-dry	1	4/28/2021 4:59:58 PM
Cadmium	ND	0.170		mg/Kg-dry	1	4/27/2021 8:50:00 PM
Chromium	20.6	0.339		mg/Kg-dry	1	4/27/2021 8:50:00 PM
Lead	4.45	0.170		mg/Kg-dry	1	4/27/2021 8:50:00 PM
Selenium	1.54	0.170		mg/Kg-dry	1	4/27/2021 8:50:00 PM
Silver	ND	0.127		mg/Kg-dry	1	4/27/2021 8:50:00 PM

Sample Moisture (Percent Moisture)

Batch ID: R66813 Analyst: CJ

Percent Moisture	5.67			wt%	1	4/27/2021 11:06:46 AM
------------------	------	--	--	-----	---	-----------------------

Work Order: 2104312
 CLIENT: Shannon & Wilson
 Project: Cascade Mill Parkway

QC SUMMARY REPORT
Total Metals by EPA Method 6020B

Sample ID: MB-32085	SampType: MBLK	Units: mg/Kg	Prep Date: 4/27/2021	RunNo: 66845							
Client ID: MBLKS	Batch ID: 32085		Analysis Date: 4/27/2021	SeqNo: 1345980							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Arsenic	ND	0.0952									
Barium	ND	0.476									
Cadmium	ND	0.159									
Chromium	ND	0.317									
Lead	ND	0.159									
Selenium	ND	0.159									
Silver	ND	0.119									

Sample ID: LCS-32085	SampType: LCS	Units: mg/Kg	Prep Date: 4/27/2021	RunNo: 66845							
Client ID: LCSS	Batch ID: 32085		Analysis Date: 4/27/2021	SeqNo: 1345981							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Arsenic	39.9	0.0952	39.68	0	100	80	120				
Barium	36.9	0.476	39.68	0	92.9	80	120				
Cadmium	1.85	0.159	1.984	0	93.4	80	120				
Chromium	42.5	0.317	39.68	0	107	80	120				
Lead	22.1	0.159	19.84	0	111	80	120				
Selenium	3.83	0.159	3.968	0	96.6	80	120				
Silver	2.02	0.119	1.984	0	102	80	120				

Sample ID: 2104303-003AMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 4/27/2021	RunNo: 66845							
Client ID: BATCH	Batch ID: 32085		Analysis Date: 4/27/2021	SeqNo: 1345986							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Arsenic	47.7	0.106	43.98	3.174	101	75	125				
Barium	85.8	0.528	43.98	41.67	100	75	125				
Cadmium	2.19	0.176	2.199	0.06338	96.7	75	125				
Chromium	79.7	0.352	43.98	32.86	106	75	125				
Lead	25.7	0.176	21.99	2.577	105	75	125				

Work Order: 2104312
 CLIENT: Shannon & Wilson
 Project: Cascade Mill Parkway

QC SUMMARY REPORT
Total Metals by EPA Method 6020B

Sample ID: 2104303-003AMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 4/27/2021	RunNo: 66845							
Client ID: BATCH	Batch ID: 32085	Analysis Date: 4/27/2021	SeqNo: 1345986								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Selenium	5.15	0.176	4.398	0.8593	97.7	75	125				
Silver	2.11	0.132	2.199	0.04517	93.8	75	125				

Sample ID: 2104303-003AMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 4/27/2021	RunNo: 66845							
Client ID: BATCH	Batch ID: 32085	Analysis Date: 4/27/2021	SeqNo: 1345987								
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Arsenic	45.7	0.106	43.98	3.174	96.6	75	125	47.74	4.48	20	
Barium	84.8	0.528	43.98	41.67	98.0	75	125	85.85	1.28	20	
Cadmium	2.10	0.176	2.199	0.06338	92.7	75	125	2.190	4.05	20	
Chromium	73.5	0.352	43.98	32.86	92.3	75	125	79.69	8.12	20	
Lead	24.1	0.176	21.99	2.577	97.8	75	125	25.70	6.46	20	
Selenium	4.89	0.176	4.398	0.8593	91.6	75	125	5.155	5.26	20	
Silver	2.09	0.132	2.199	0.04517	92.9	75	125	2.109	0.958	20	

Work Order: 2104312
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Mercury by EPA Method 7471

Sample ID: MB-32120	SampType: MBLK	Units: mg/Kg	Prep Date: 4/28/2021	RunNo: 66875							
Client ID: MBLKS	Batch ID: 32120		Analysis Date: 4/29/2021	SeqNo: 1346835							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury ND 0.250

Sample ID: LCS-32120	SampType: LCS	Units: mg/Kg	Prep Date: 4/28/2021	RunNo: 66875							
Client ID: LCSS	Batch ID: 32120		Analysis Date: 4/29/2021	SeqNo: 1346836							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.492 0.250 0.5000 0 98.4 80 120

Sample ID: 2104132-001ADUP	SampType: DUP	Units: mg/Kg-dry	Prep Date: 4/28/2021	RunNo: 66875							
Client ID: BATCH	Batch ID: 32120		Analysis Date: 4/29/2021	SeqNo: 1346838							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury ND 0.258 0 20

Sample ID: 2104132-001AMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 4/28/2021	RunNo: 66875							
Client ID: BATCH	Batch ID: 32120		Analysis Date: 4/29/2021	SeqNo: 1346839							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.391 0.253 0.5054 0 77.4 70 130

Sample ID: 2104132-001AMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 4/28/2021	RunNo: 66875							
Client ID: BATCH	Batch ID: 32120		Analysis Date: 4/29/2021	SeqNo: 1346840							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Mercury 0.433 0.248 0.4959 0 87.4 70 130 0.3912 10.2 20

Work Order: 2104312
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Sample ID: MB-32091	SampType: MBLK	Units: mg/Kg				Prep Date: 4/26/2021	RunNo: 66848				
Client ID: MBLKS	Batch ID: 32091					Analysis Date: 4/26/2021	SeqNo: 1346062				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	ND	50.0									
Heavy Oil	ND	100									
Total Petroleum Hydrocarbons	ND	150									
Surr: 2-Fluorobiphenyl	10.0		10.00		100	50	150				
Surr: o-Terphenyl	10.2		10.00		102	50	150				

Sample ID: LCS-32091	SampType: LCS	Units: mg/Kg				Prep Date: 4/26/2021	RunNo: 66848				
Client ID: LCSS	Batch ID: 32091					Analysis Date: 4/26/2021	SeqNo: 1346063				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	502	50.0	500.0	0	100	73.7	114				
Surr: 2-Fluorobiphenyl	9.61		10.00		96.1	50	150				
Surr: o-Terphenyl	11.5		10.00		115	50	150				

Sample ID: 2104292-001ADUP	SampType: DUP	Units: mg/Kg-dry				Prep Date: 4/26/2021	RunNo: 66848				
Client ID: BATCH	Batch ID: 32091					Analysis Date: 4/26/2021	SeqNo: 1346066				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	ND	96.3						0		30	
Heavy Oil	ND	193						0		30	
Total Petroleum Hydrocarbons	ND	289						0		30	
Surr: 2-Fluorobiphenyl	9.63		19.26		50.0	50	150		0		
Surr: o-Terphenyl	14.1		19.26		73.0	50	150		0		

Sample ID: 2104303-002AMS	SampType: MS	Units: mg/Kg-dry				Prep Date: 4/26/2021	RunNo: 66848				
Client ID: BATCH	Batch ID: 32091					Analysis Date: 4/26/2021	SeqNo: 1346070				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	540	52.5	525.4	0	103	61.4	129				

Work Order: 2104312
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Sample ID: 2104303-002AMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 4/26/2021	RunNo: 66848							
Client ID: BATCH	Batch ID: 32091		Analysis Date: 4/26/2021	SeqNo: 1346070							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Surr: 2-Fluorobiphenyl	9.89		10.51	94.1	50	150
Surr: o-Terphenyl	10.8		10.51	103	50	150

Sample ID: 2104303-002AMSD	SampType: MSD	Units: mg/Kg-dry	Prep Date: 4/26/2021	RunNo: 66848							
Client ID: BATCH	Batch ID: 32091		Analysis Date: 4/26/2021	SeqNo: 1346071							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Diesel (Fuel Oil)	474	48.6	486.4	0	97.3	61.4	129	540.3	13.2	30
Surr: 2-Fluorobiphenyl	8.78		9.729		90.2	50	150		0	
Surr: o-Terphenyl	9.59		9.729		98.6	50	150		0	

Work Order: 2104312
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Sample ID: MB-32099	SampType: MBLK	Units: µg/Kg	Prep Date: 4/27/2021	RunNo: 66850							
Client ID: MBLKS	Batch ID: 32099		Analysis Date: 4/27/2021	SeqNo: 1346170							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	ND	20.0									
2-Methylnaphthalene	ND	20.0									
1-Methylnaphthalene	ND	20.0									
Acenaphthene	ND	20.0									
Acenaphthylene	ND	20.0									
Fluorene	ND	20.0									
Pentachlorophenol	ND	80.0									
Phenanthrene	ND	40.0									
Anthracene	ND	40.0									
Fluoranthene	ND	40.0									
Pyrene	ND	40.0									
Benz(a)anthracene	ND	20.0									
Chrysene	ND	40.0									
Benzo(b)fluoranthene	ND	20.0									
Benzo(k)fluoranthene	ND	20.0									
Benzo(a)pyrene	ND	20.0									
Indeno(1,2,3-cd)pyrene	ND	40.0									
Dibenz(a,h)anthracene	ND	40.0									
Benzo(g,h,i)perylene	ND	20.0									
Surr: 2,4,6-Tribromophenol	1,220		2,000		60.8	19.4	153				
Surr: 2-Fluorobiphenyl	838		1,000		83.8	19	135				
Surr: Terphenyl-d14 (surr)	1,110		1,000		111	42.9	156				

Sample ID: LCS-32099	SampType: LCS	Units: µg/Kg	Prep Date: 4/27/2021	RunNo: 66850							
Client ID: LCSS	Batch ID: 32099		Analysis Date: 4/27/2021	SeqNo: 1346171							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	1,780	20.0	2,000	0	89.2	62.7	127				
2-Methylnaphthalene	1,770	20.0	2,000	0	88.3	62.7	132				
1-Methylnaphthalene	1,810	20.0	2,000	0	90.3	61.4	131				

Work Order: 2104312
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Sample ID: LCS-32099	SampType: LCS	Units: µg/Kg	Prep Date: 4/27/2021	RunNo: 66850							
Client ID: LCSS	Batch ID: 32099		Analysis Date: 4/27/2021	SeqNo: 1346171							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Acenaphthene	1,780	20.0	2,000	0	89.2	59.2	132				
Acenaphthylene	1,690	20.0	2,000	0	84.7	62	132				
Fluorene	1,860	20.0	2,000	0	92.8	59.1	136				
Pentachlorophenol	1,150	80.0	2,000	0	57.3	5	112				
Phenanthrene	1,950	40.0	2,000	0	97.7	54.1	139				
Anthracene	1,880	40.0	2,000	0	94.0	55.5	136				
Fluoranthene	1,920	40.0	2,000	0	96.1	52.8	149				
Pyrene	1,860	40.0	2,000	0	93.2	53.6	146				
Benz(a)anthracene	1,900	20.0	2,000	0	95.1	49.7	153				
Chrysene	1,910	40.0	2,000	0	95.3	52.6	147				
Benzo(b)fluoranthene	1,780	20.0	2,000	0	88.8	50.6	151				
Benzo(k)fluoranthene	2,040	20.0	2,000	0	102	47.1	155				
Benzo(a)pyrene	2,020	20.0	2,000	0	101	48.3	169				
Indeno(1,2,3-cd)pyrene	1,940	40.0	2,000	0	97.2	52.3	145				
Dibenz(a,h)anthracene	2,000	40.0	2,000	0	99.8	53	144				
Benzo(g,h,i)perylene	1,830	20.0	2,000	0	91.7	49.7	144				
Surr: 2,4,6-Tribromophenol	1,890		2,000		94.6	19.4	153				
Surr: 2-Fluorobiphenyl	822		1,000		82.2	19	135				
Surr: Terphenyl-d14 (surr)	1,070		1,000		107	42.9	156				

Sample ID: 2104303-001AMS	SampType: MS	Units: µg/Kg-dry	Prep Date: 4/27/2021	RunNo: 66850							
Client ID: BATCH	Batch ID: 32099		Analysis Date: 4/27/2021	SeqNo: 1346173							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Naphthalene	1,710	19.6	1,959	0	87.3	28.7	139				
2-Methylnaphthalene	1,740	19.6	1,959	0	88.7	43.5	130				
1-Methylnaphthalene	1,740	19.6	1,959	0	88.7	42.6	127				
Acenaphthene	1,710	19.6	1,959	0	87.5	45.1	123				
Acenaphthylene	1,630	19.6	1,959	0	83.1	45.3	129				
Fluorene	1,810	19.6	1,959	0	92.3	41.6	128				

Work Order: 2104312
 CLIENT: Shannon & Wilson
 Project: Cascade Mill Parkway

QC SUMMARY REPORT
Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Sample ID: 2104303-001AMS		SampType: MS		Units: µg/Kg-dry		Prep Date: 4/27/2021		RunNo: 66850			
Client ID: BATCH		Batch ID: 32099				Analysis Date: 4/27/2021		SeqNo: 1346173			
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Pentachlorophenol	1,540	78.4	1,959	0	78.7	5	188				
Phenanthrene	1,850	39.2	1,959	0	94.7	24.2	142				
Anthracene	1,820	39.2	1,959	0	92.7	33.1	143				
Fluoranthene	1,860	39.2	1,959	0	94.8	35.5	147				
Pyrene	1,800	39.2	1,959	0	91.7	38.3	141				
Benz(a)anthracene	1,880	19.6	1,959	0	95.8	42.5	145				
Chrysene	1,830	39.2	1,959	0	93.5	39.7	134				
Benzo(b)fluoranthene	1,700	19.6	1,959	0	86.9	29.9	152				
Benzo(k)fluoranthene	2,000	19.6	1,959	0	102	33.2	143.5				
Benzo(a)pyrene	2,010	19.6	1,959	0	102	38.2	156				
Indeno(1,2,3-cd)pyrene	1,850	39.2	1,959	0	94.3	41.4	128				
Dibenz(a,h)anthracene	1,890	39.2	1,959	0	96.3	40.4	129				
Benzo(g,h,i)perylene	1,720	19.6	1,959	0	87.9	34.2	131				
Surr: 2,4,6-Tribromophenol	1,810		1,959		92.3	19.4	153				
Surr: 2-Fluorobiphenyl	792		979.7		80.8	19	135				
Surr: Terphenyl-d14 (surr)	1,000		979.7		102	42.9	156				

Sample ID: 2104303-001AMSD		SampType: MSD		Units: µg/Kg-dry		Prep Date: 4/27/2021		RunNo: 66850			
Client ID: BATCH		Batch ID: 32099				Analysis Date: 4/27/2021		SeqNo: 1346174			
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	1,690	20.5	2,047	0	82.6	28.7	139	1,711	1.24	30	
2-Methylnaphthalene	1,740	20.5	2,047	0	85.2	43.5	130	1,738	0.326	30	
1-Methylnaphthalene	1,740	20.5	2,047	0	84.8	42.6	127	1,739	0.176	30	
Acenaphthene	1,750	20.5	2,047	0	85.3	45.1	123	1,714	1.88	30	
Acenaphthylene	1,640	20.5	2,047	0	80.3	45.3	129	1,629	0.897	30	
Fluorene	1,840	20.5	2,047	0	89.7	41.6	128	1,808	1.58	30	
Pentachlorophenol	1,590	81.9	2,047	0	77.8	5	188	1,542	3.14	30	
Phenanthrene	1,950	40.9	2,047	0	95.5	24.2	142	1,855	5.22	30	
Anthracene	1,870	40.9	2,047	0	91.6	33.1	143	1,816	3.18	30	

Work Order: 2104312
 CLIENT: Shannon & Wilson
 Project: Cascade Mill Parkway

QC SUMMARY REPORT
Semi-Volatile Organic Compounds by EPA 8270 (SIM)

Sample ID: 2104303-001AMSD	SampType: MSD	Units: µg/Kg-dry				Prep Date: 4/27/2021	RunNo: 66850				
Client ID: BATCH	Batch ID: 32099					Analysis Date: 4/27/2021	SeqNo: 1346174				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Fluoranthene	1,940	40.9	2,047	0	94.7	35.5	147	1,857	4.31	30	
Pyrene	1,870	40.9	2,047	0	91.4	38.3	141	1,797	3.98	30	
Benz(a)anthracene	1,940	20.5	2,047	0	94.9	42.5	145	1,877	3.49	30	
Chrysene	1,900	40.9	2,047	0	92.7	39.7	134	1,833	3.42	30	
Benzo(b)fluoranthene	2,000	20.5	2,047	0	97.9	29.9	152	1,702	16.3	30	
Benzo(k)fluoranthene	1,790	20.5	2,047	0	87.6	33.2	143.5	2,003	11.0	30	
Benzo(a)pyrene	2,080	20.5	2,047	0	102	38.2	156	2,005	3.82	30	
Indeno(1,2,3-cd)pyrene	1,920	40.9	2,047	0	94.0	41.4	128	1,847	4.09	30	
Dibenz(a,h)anthracene	1,970	40.9	2,047	0	96.0	40.4	129	1,886	4.12	30	
Benzo(g,h,i)perylene	1,790	20.5	2,047	0	87.7	34.2	131	1,723	4.08	30	
Surr: 2,4,6-Tribromophenol	1,840		2,047		89.9	19.4	153		0		
Surr: 2-Fluorobiphenyl	798		1,023		77.9	19	135		0		
Surr: Terphenyl-d14 (surr)	1,030		1,023		101	42.9	156		0		

Work Order: 2104312
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Gasoline by NWTPH-Gx

Sample ID: LCS-32102	SampType: LCS	Units: mg/Kg			Prep Date: 4/27/2021	RunNo: 66847					
Client ID: LCSS	Batch ID: 32102				Analysis Date: 4/27/2021	SeqNo: 1346096					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	29.1	5.00	25.00	0	116	65	135				
Surr: Toluene-d8	1.29		1.250		104	65	135				
Surr: 4-Bromofluorobenzene	1.26		1.250		101	65	135				

Sample ID: MB-32102	SampType: MBLK	Units: mg/Kg			Prep Date: 4/27/2021	RunNo: 66847					
Client ID: MBLKS	Batch ID: 32102				Analysis Date: 4/27/2021	SeqNo: 1346059					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	ND	5.00									
Surr: Toluene-d8	1.40		1.250		112	65	135				
Surr: 4-Bromofluorobenzene	1.28		1.250		102	65	135				

Sample ID: 2104302-001BDUP	SampType: DUP	Units: mg/Kg-dry			Prep Date: 4/27/2021	RunNo: 66847					
Client ID: BATCH	Batch ID: 32102				Analysis Date: 4/27/2021	SeqNo: 1346043					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	ND	5.27						0		30	
Surr: Toluene-d8	1.45		1.318		110	65	135		0		
Surr: 4-Bromofluorobenzene	1.34		1.318		102	65	135		0		

Sample ID: 2104303-002BDUP	SampType: DUP	Units: mg/Kg-dry			Prep Date: 4/27/2021	RunNo: 66847					
Client ID: BATCH	Batch ID: 32102				Analysis Date: 4/27/2021	SeqNo: 1346046					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual

Gasoline	ND	5.08						0		30	
Surr: Toluene-d8	1.39		1.270		110	65	135		0		
Surr: 4-Bromofluorobenzene	1.26		1.270		99.6	65	135		0		

Work Order: 2104312
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Gasoline by NWTPH-Gx

Sample ID: 2104303-003BMS	SampType: MS	Units: mg/Kg-dry		Prep Date: 4/27/2021	RunNo: 66847						
Client ID: BATCH	Batch ID: 32102			Analysis Date: 4/27/2021	SeqNo: 1346048						
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Gasoline	32.6	5.36	26.79	2.628	112	65	135				
Surr: Toluene-d8	1.49		1.339		111	65	135				
Surr: 4-Bromofluorobenzene	1.40		1.339		104	65	135				

Work Order: 2104312
 CLIENT: Shannon & Wilson
 Project: Cascade Mill Parkway

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260D

Sample ID: LCS-32102	SampType: LCS	Units: mg/Kg				Prep Date: 4/27/2021	RunNo: 66846				
Client ID: LCSS	Batch ID: 32102					Analysis Date: 4/27/2021	SeqNo: 1346038				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	0.877	0.0200	1.000	0	87.7	80	120				
Toluene	0.888	0.0650	1.000	0	88.8	80	120				
Ethylbenzene	0.971	0.0250	1.000	0	97.1	80	120				
m,p-Xylene	1.98	0.0500	2.000	0	98.8	80	120				
o-Xylene	0.995	0.0250	1.000	0	99.5	80	120				
Surr: Dibromofluoromethane	1.20		1.250		96.3	80	120				
Surr: Toluene-d8	1.17		1.250		93.4	80	120				
Surr: 1-Bromo-4-fluorobenzene	1.27		1.250		102	80	120				

Sample ID: MB-32102	SampType: MBLK	Units: mg/Kg				Prep Date: 4/27/2021	RunNo: 66846				
Client ID: MBLKS	Batch ID: 32102					Analysis Date: 4/27/2021	SeqNo: 1346033				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	ND	0.0200									
Toluene	ND	0.0650									
Ethylbenzene	ND	0.0250									
m,p-Xylene	ND	0.0500									
o-Xylene	ND	0.0250									
Surr: Dibromofluoromethane	1.12		1.250		89.8	81.9	113				
Surr: Toluene-d8	1.15		1.250		91.9	82.7	115				
Surr: 1-Bromo-4-fluorobenzene	1.21		1.250		97.0	87.9	109				

Sample ID: 2104302-001BDUP	SampType: DUP	Units: mg/Kg-dry				Prep Date: 4/27/2021	RunNo: 66846				
Client ID: BATCH	Batch ID: 32102					Analysis Date: 4/27/2021	SeqNo: 1346014				
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	ND	0.0211						0		30	
Toluene	ND	0.0685						0		30	
Ethylbenzene	ND	0.0264						0		30	

Work Order: 2104312
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260D

Sample ID: 2104302-001BDUP	SampType: DUP	Units: mg/Kg-dry			Prep Date: 4/27/2021	RunNo: 66846					
Client ID: BATCH	Batch ID: 32102				Analysis Date: 4/27/2021	SeqNo: 1346014					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
m,p-Xylene	ND	0.0527						0		30	
o-Xylene	ND	0.0264						0		30	
Surr: Dibromofluoromethane	1.17		1.318		88.9	81.9	113		0		
Surr: Toluene-d8	1.23		1.318		93.6	82.7	115		0		
Surr: 1-Bromo-4-fluorobenzene	1.26		1.318		95.8	87.9	109		0		

Sample ID: 2104303-002BDUP	SampType: DUP	Units: mg/Kg-dry			Prep Date: 4/27/2021	RunNo: 66846					
Client ID: BATCH	Batch ID: 32102				Analysis Date: 4/27/2021	SeqNo: 1346018					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	ND	0.0203						0		30	
Toluene	ND	0.0660						0		30	
Ethylbenzene	ND	0.0254						0		30	
m,p-Xylene	ND	0.0508						0		30	
o-Xylene	ND	0.0254						0		30	
Surr: Dibromofluoromethane	1.15		1.270		90.3	81.9	113		0		
Surr: Toluene-d8	1.21		1.270		95.3	82.7	115		0		
Surr: 1-Bromo-4-fluorobenzene	1.20		1.270		94.4	87.9	109		0		

Sample ID: 2104303-001BMS	SampType: MS	Units: mg/Kg-dry			Prep Date: 4/27/2021	RunNo: 66846					
Client ID: BATCH	Batch ID: 32102				Analysis Date: 4/27/2021	SeqNo: 1346016					
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	0.790	0.0162	0.8107	0	97.5	76.8	129				
Toluene	0.808	0.0527	0.8107	0	99.7	77.8	127				
Ethylbenzene	0.854	0.0203	0.8107	0	105	78.7	130				
m,p-Xylene	1.72	0.0405	1.621	0	106	79.3	127				
o-Xylene	0.864	0.0203	0.8107	0	107	80.7	124				
Surr: Dibromofluoromethane	0.986		1.013		97.3	81.9	113				

Work Order: 2104312
CLIENT: Shannon & Wilson
Project: Cascade Mill Parkway

QC SUMMARY REPORT
Volatile Organic Compounds by EPA Method 8260D

Sample ID: 2104303-001BMS	SampType: MS	Units: mg/Kg-dry	Prep Date: 4/27/2021	RunNo: 66846							
Client ID: BATCH	Batch ID: 32102		Analysis Date: 4/27/2021	SeqNo: 1346016							
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Surr: Toluene-d8	0.946		1.013		93.3	82.7	115				
Surr: 1-Bromo-4-fluorobenzene	1.07		1.013		106	87.9	109				

Client Name: **SW**

 Work Order Number: **2104312**

 Logged by: **Clare Griggs**

 Date Received: **4/22/2021 3:41:00 PM**

Chain of Custody

1. Is Chain of Custody complete? Yes No Not Present
2. How was the sample delivered? Client

Log In

3. Coolers are present? Yes No NA
4. Shipping container/cooler in good condition? Yes No
5. Custody Seals present on shipping container/cooler?
(Refer to comments for Custody Seals not intact) Yes No Not Present
6. Was an attempt made to cool the samples? Yes No NA
7. Were all items received at a temperature of >2°C to 6°C * Yes No NA
8. Sample(s) in proper container(s)? Yes No
9. Sufficient sample volume for indicated test(s)? Yes No
10. Are samples properly preserved? Yes No
11. Was preservative added to bottles? Yes No NA
12. Is there headspace in the VOA vials? Yes No NA
13. Did all samples containers arrive in good condition(unbroken)? Yes No
14. Does paperwork match bottle labels? Yes No
15. Are matrices correctly identified on Chain of Custody? Yes No
16. Is it clear what analyses were requested? Yes No
17. Were all holding times able to be met? Yes No

Special Handling (if applicable)

18. Was client notified of all discrepancies with this order? Yes No NA

Person Notified:	<input type="text"/>	Date:	<input type="text"/>
By Whom:	<input type="text"/>	Via:	<input type="checkbox"/> eMail <input type="checkbox"/> Phone <input type="checkbox"/> Fax <input type="checkbox"/> In Person
Regarding:	<input type="text"/>		
Client Instructions:	<input type="text"/>		

19. Additional remarks:

Item Information

Item #	Temp °C
Sample	5.5

* Note: DoD/ELAP and TNI require items to be received at 4°C +/- 2°C



3600 Fremont Ave N.
Seattle, WA 98103
Tel: 206-352-3790
Fax: 206-352-7178

Chain of Custody Record & Laboratory Services Agreement

Date: 4/22/21 Page: 1 of 1

Project Name: Cascade Mill Parkway

Project No: 106384

Collected by: DTR

Location: Yakima

Report To (PM): David Randall

PM Email: DTR@sitawill.com

Laboratory Project No (Internal): 2004312

Special Remarks:

Sample Disposal: Return to client Disposal by lab (after 30 days)

Client: SHANNON & WILSON
Address: 400 N. 34th ST
City, State, zip: SEATTLE, WA
Telephone: 206-695-6918

Sample Name	Sample Date	Sample Time	Sample Type (Matrix)*	# of Cont.	VOCs (EPA 8260 / 624)	BTEX	Gasoline Range Organics (GX)	Hydrocarbon Identification (HCID)	Diesel/Heavy Oil Range Organics (DX)	SVOCs (EPA 8270 / 625)	PAHs (EPA 8270 - SIM)	PCBs (EPA 808 / 608)	Metals** (EPA 6020 / 200.8)	Total (T) Dissolved (D)	Anions (CI)***	EDB (8011)	Comments
B-13-21/A-8@39	4/22/21	1331	Soil	5	X	X	X	X	X	X	X	X	X				

Matrix: A = Air, AQ = Aqueous, B = Bulk, O = Other, P = Product, S = Soil, SD = Sediment, SL = Solid, W = Water, DW = Drinking Water, GW = Ground Water, SW = Storm Water, WW = Waste Water
 **Metals (Circle): MTCA-5, RCRA-8, Priority Pollutants TAL Individual: Ag Al As B Ba Be Ca Cd Co Cr Cu Fe Hg K Mg Mn Mo Na Ni Pb Sb Se Sr Sn Tl Ti V Zn
 ***Anions (Circle): Nitrate Nitrite Chloride Sulfate Bromide O-Phosphate Fluoride Nitrate+Nitrite

I represent that I am authorized to enter into this Agreement with Fremont Analytical on behalf of the Client named above, that I have verified Client's agreement to each of the terms on the front and backside of this Agreement.

Turn-around Time:
 Standard Next Day
 3 Day Same Day
 2 Day (specify)

Relinquished (Signature) *David Randall* Print Name: David Randall Date/Time: 4/22/21 1535
 Received (Signature) *Shannon & Wilson* Print Name: Shannon & Wilson Date/Time: 4/22/21 1541

Appendix E

Groundwater Observations

CONTENTS

- Figure E-1: Groundwater Level Readings Boring B-11P-21
- Figure E-2: Groundwater Level Readings Boring B-12P-21
- Figure E-3: Groundwater Level Readings Boring B-15P-21
- Figure E-4: Observation Well B-2-17 Hydrograph
- Figure E-5: Groundwater Level Vs Precipitation Boring EWC-B-01-14
- Figure E-6: Groundwater Level Vs Precipitation Boring EWC-B-02-14
- Figure E-7: Groundwater Level Vs Precipitation Boring EWC-B-03-14
- Figure E-8: Groundwater Level Vs Precipitation Boring EWC-B-04-14





FIG. E-1

Cascade Mill Parkway Project Yakima County, Washington	
GROUNDWATER LEVEL READINGS BORING B-11P-21	
March 2023	106384-002
SHANNON & WILSON, INC. Geotechnical and Environmental Consultants	FIG. E-1

ver0.16.0-beta.2_broth

\\sea-fs-1\vol1\EF\SEA\106384_Mill_Parkway\Field_Explorations\WVP\Python_WVP_plots



Notes:


1. Groundwater data recorded hourly using a vibrating wire piezometer.
2. Daily Precipitation data from the following NOAA weather station:
Name = YAKIMA 0.9 WNW, WA US; ID = US1WAYK0024
(available: <ftp://ftp.ncdc.noaa.gov/pub/data/ghcn/daily/>)
3. Relative river levels shown represent gage heights from a USGS river gage upstream of the boring location at a different elevation. Levels shown have been shifted such that the lowest gage height aligns with the bottom of the Levee Fill layer. Relative river levels are therefore not actual elevations of the river at the boring locations. Gage height data was retrieved from the following USGS gage site:
Site Name = YAKIMA RIVER ABOVE AHTANUM CREEK AT UNION GAP, WA (No. 12500450)
(Available: <https://waterservices.usgs.gov/rest/IV-Test-Tool.html>)

FIG. E-2

Cascade Mill Parkway Project Yakima County, Washington	
GROUNDWATER LEVEL READINGS BORING B-12P-21	
March 2023	106384-002
SHANNON & WILSON, INC. Geotechnical and Environmental Consultants	FIG. E-2

ver0.16.0-beta.2_broth

\\sea-fs1\vol1\EF\SEA\106384_Mill_Parkway\Field_Explorations\WVP\Python_WVP_plots




Notes:

1. Groundwater data recorded hourly using a vibrating wire piezometer.
2. Daily Precipitation data from the following NOAA weather station:
Name = YAKIMA 0.9 WNW, WA US; ID = US1WAYK0024
(available: <ftp://ftp.ncdc.noaa.gov/pub/data/ghcn/daily/>)
3. Relative river levels shown represent gage heights from a USGS river gage upstream of the boring location at a different elevation. Levels shown have been shifted such that the lowest gage height aligns with the bottom of the Levee Fill layer. Relative river levels are therefore not actual elevations of the river at the boring locations. Gage height data was retrieved from the following USGS gage site:
Site Name = YAKIMA RIVER ABOVE AHTANUM CREEK AT UNION GAP, WA (No. 12500450)
(Available: <https://waterservices.usgs.gov/rest/IV-Test-Tool.html>)

FIG. E-3

Cascade Mill Parkway Project Yakima County, Washington	
GROUNDWATER LEVEL READINGS BORING B-15P-21	
March 2023	106384-002
SHANNON & WILSON, INC. Geotechnical and Environmental Consultants	FIG. E-3



NOTES

1. The screen in observation well B-2-17 is approximately 29.5 to 39.5 feet below ground surface (approximately elevation 1,025.5 to 1,015.5 feet (NAVD88)).
2. Grade elevation at B-2-17 is approximately 1,055 feet NAVD88.
3. Black and white reproduction of this color original may lead to incorrect interpretation.

Cascade Mill Parkway Project
Yakima County, Washington


**OBSERVATION WELL B-2-17
HYDROGRAPH**

March 2023

106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. E-4



LEGEND

- ◆ EWC-B-01-14 Vibrating Wire Piezometer 1 (84.5 feet deep)
- Daily Total Precipitation

NOTES

1. EWC-B-01-14 grade elevation is approximately 1057.5 feet.
2. Precipitation data were downloaded for the Yakima Air Terminal (24243).
3. Data logger failed sporadically starting 2/1/15.

Cascade Mill Parkway Project
Yakima County, Washington


**GROUNDWATER LEVEL VS
PRECIPITATION
BORING EWC-B-01-14**

March 2023

106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. E-5



LEGEND

- ◆ EWC-B-02-14 Vibrating Wire Piezometer 1 (30.0 feet deep)
- Daily Total Precipitation

NOTES

1. EWC-B-02-14 grade elevation is approximately 1052 feet.
2. Precipitation data were downloaded for the Yakima Air Terminal (24243).

Cascade Mill Parkway Project
Yakima County, Washington


**GROUNDWATER LEVEL VS
PRECIPITATION
BORING EWC-B-02-14**

March 2023

106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. E-6



LEGEND

- ◆ EWC-B-03-14 Vibrating Wire Piezometer 1 (53.1 feet deep)
- Daily Total Precipitation

NOTES

1. EWC-B-03-14 grade elevation is approximately 1056.5 feet.
2. Precipitation data were downloaded for the Yakima Air Terminal (24243).

Cascade Mill Parkway Project
Yakima County, Washington


**GROUNDWATER LEVEL VS
PRECIPITATION
BORING EWC-B-03-14**

March 2023

106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. E-7



LEGEND

- ◆ EWC-B-04-14 Vibrating Wire Piezometer 1 (68.1 feet deep)
- Daily Total Precipitation

NOTES

1. EWC-B-04-14 grade elevation is approximately 1047 feet.
2. Precipitation data were downloaded for the Yakima Air Terminal (24243).

Cascade Mill Parkway Project
Yakima County, Washington

**GROUNDWATER LEVEL VS
PRECIPITATION
BORING EWC-B-04-14**

March 2023

106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. E-8

Appendix F

Global Stability Analyses

CONTENTS

F.1 INTRODUCTION F-1

F.2 ANALYSIS LOCATIONS AND GEOMETRIES F-1

 F.2.1 Yakima River Bridge East Abutment and Approach Embankment F-1

 F.2.2 YRB West Abutment and Approach Embankment F-2

 F.2.3 Fill Embankment West of I-82 F-2

F.3 REQUIREMENTS F-3

F.4 METHODOLOGY F-3

 F.4.1 Limit Equilibrium Analyses F-3

 F.4.2 Soil Parameters F-4

 F.4.3 Design Loads F-5

F.5 ANALYSIS DETAILS AND RESULTS F-6

F.6 REFERENCES F-6

Exhibits

Exhibit F-1: Location of YRB East Abutment Global Stability Analyses F-1

Exhibit F-2: Location of YRB West Abutment Global Stability Analyses F-2

Exhibit F-3: Location of Fill Embankment West of I-82 Global Stability Analysis F-3

Tables

Table F-1: Materials

Figures

Figures F-1 to F-10: SLOPE/W Global Stability Analyses Results

F.1 INTRODUCTION

This appendix presents global stability modeling performed for the Cascade Mill Parkway (CMP) project in Yakima County. This appendix describes the analysis methods, soil parameters, and other assumptions made in the analyses.

F.2 ANALYSIS LOCATIONS AND GEOMETRIES

We evaluated global stability at three locations. Details for each location are provided in the following sections.

F.2.1 Yakima River Bridge East Abutment and Approach Embankment

We evaluated global stability for the longitudinal (east-west) and transverse (north-south) directions at the proposed Yakima River Bridge (YRB) east abutment. Locations of these analyses are indicated in Exhibit F-1. Figures F-1 through F-4 show our geometric assumptions for these analyses.




Exhibit F-1: Location of YRB East Abutment Global Stability Analyses

For the approach embankment analysis, we considered a skewed transverse analysis to account for the influence of river scour. Both abutment and approach embankment analyses assume post-scoured conditions for static and seismic conditions.

F.2.2 YRB West Abutment and Approach Embankment




Exhibit F-2: Location of YRB West Abutment Global Stability Analyses

We evaluated global stability for the longitudinal (east-west) and transverse (north-south) directions at the proposed YRB west abutment. Locations of these analyses are indicated in Exhibit F-2. Figures F-5 through F-8 show our geometric assumptions for these analyses.

We assume the post-scour conditions for the longitudinal west abutment analysis. We did not consider scour for the west approach embankment (transverse) analysis due to the presence of the existing levee along the west bank of the Yakima River. See main text for more details on scour.

F.2.3 Fill Embankment West of I-82

We evaluated global stability in the transverse (north-south) direction of the proposed fill embankment west of I-82. The location of this analysis is shown in Exhibit F-3. Figures F-9 and F-10 show our geometric assumptions for this analysis.

This analysis is in an area formerly used as a municipal solid waste (MSW) and wood waste storage site. We understand the City of Yakima removed the MSW and wood waste within the CMP Project footprint. Based on preliminary plans, the City of Yakima had a 50-foot temporary easement outside of the CMP right-of-way and excavated into the MSW and wood waste material at a 2 Horizontal to 1 Vertical (2H:1V) cut slope (see Figures 9 and 10). Based on the City of Yakima preliminary plans, we understand the excavations were backfilled with material consistent with Washington State Department of Transportation (WSDOT) Common Borrow.




Exhibit F-3: Location of Fill Embankment West of I-82 Global Stability Analysis

F.3 REQUIREMENTS

The slope stability factor of safety (FS) is the ratio of forces resisting sliding to forces driving sliding. If the FS is less than 1.0, then the driving forces are greater than the resisting forces, and the slope is in a state of failure. If the FS is greater than 1.0, the resisting forces are greater than the driving forces, and the slope is in a stable state.

The WSDOT Geotechnical Design Manual (GDM) (WSDOT, 2022) requires the following minimum FS values:

- 1.3 for static loading of slopes adjacent to but not directly supporting structures,
- 1.5 for static loading of slopes directly supporting structures, and
- 1.1 for seismic and post-seismic loading of slopes adjacent to or supporting structures.

F.4 METHODOLOGY

F.4.1 Limit Equilibrium Analyses

We evaluated the slope stability FS using limit equilibrium analyses. Limit equilibrium analyses treat the slide mass as a rigid body, subdivide the mass into slices, and calculate

the forces acting on each slice. We used the Morgenstern-Price limit equilibrium method (Morgenstern and Price, 1965), which:

- Includes both normal and shear interslice forces,
- Satisfies both moment and force equilibrium, and
- Allows for variable distributions of interslice forces.

We used the computer program SLOPE/W (GeoStudio International, 2021) to perform the Morgenstern-Price analyses. We used SLOPE/W to specify the potential limits of a slide mass and to calculate the FS of potential slip surfaces in the slide mass. The critical slip surface is the slip surface with the lowest FS.

For our static analyses, we included surcharge loads as specified in the American Association of State Highway and Transportation Officials (AASHTO) Load and Resistance Factor Design Bridge Design Specifications (AASHTO, 2020).

In accordance with WSDOT (2022), we analyzed seismic slope stability using a pseudo-static approach. We modeled the earthquake loading by applying a horizontal seismic coefficient, k_h , of one-half the site peak ground acceleration (PGA). The horizontal seismic coefficient is less than the PGA because:

- The PGA occurs only once during an earthquake record, while k_h is applied as a static force;
- Wave scattering effects tend to reduce the acceleration in the slide mass; and
- The slide mass is allowed to displace a small amount.

F.4.2 Soil Parameters

We selected soil parameters for the model based on laboratory and field testing performed for I-82 and other projects, our experience, and judgment.

We estimated the soil parameters by reviewing:

- The generalized subsurface profiles (see main text Figures 3 through 5) and boring logs (see Appendices A and C), and
- The results of laboratory and field testing (see Appendices B and C).

Input properties for soil layers include unit weight, cohesion, and friction angle. The soil properties are shown in Figures F-1 through F-10 and are summarized in Table F-1.

Table F-1: Materials

Material Name	Color in Figures	Unit Weight (pcf)	Effective Stress Friction Angle (degrees)	Effective Stress Cohesion Intercept (psf)	Description / Note
Concrete Abutment		150	n/a	n/a	Cast-in-place concrete for YRB abutment stem wall and cap beam – assumed impenetrable in our analyses.
Embankment Fill		125	32	0	Proposed CMP Project embankment fill.
Wall Backfill		135	38	0	Proposed CMP Project gravel backfill for retaining walls.
MSW and/or Wood Waste		50	18	0	Assumed MSW and/or wood waste material west of the I-82 embankment not removed by the City of Yakima.
City Replacement Fill		125	32	0	Assumed fill material placed by City of Yakima in 2021 to replace MSW and Wood Waste material within CMP footprint west of I-82 embankment.
Loose Silty Gravel (GM) with Wood Waste		120	24	0	Assumed material containing abundant wood waste between the I-82 embankment and the Yakima River.
County Replacement Fill		125	32	0	Assumed fill material to be placed for the CMP Project to replace wood waste material within CMP footprint between the I-82 embankment and the Yakima River.
Riprap		115	45	0	Proposed launchable riprap blanket scour protection at YRB east abutment.

MSW = municipal solid waste; n/a = not applicable; pcf = pounds per cubic foot; psf = pounds per square foot

F.4.3 Design Loads

We applied a factored traffic surcharge of 250 pounds per square foot above abutments and embankments at the CMP roadway grade.

Surcharge loads associated with the bridge superstructure or live traffic loading are not included in our analyses because these loads will be resisted by the drilled shafts.

Drilled shaft foundations are shown our global stability output figures for reference purposes only. We did not account for the lateral resistance of the shafts in our global stability analyses.

F.5 ANALYSIS DETAILS AND RESULTS

Our global stability analyses are presented as Figures F-1 through F-10. As shown in the figures, we confirmed that the geometry of the selected cross sections will meet the WSDOT GDM FS criteria for both static and seismic conditions.


F.6 REFERENCES

American Association of State Highway and Transportation Officials (AASHTO), 2020, AASHTO LRFD bridge design specifications (9th ed.): Washington, D.C., AASHTO, 2 v.

Geo-Slope International, 2021, SLOPE/W v. 2021.4: Calgary, Alberta, Geo-Slope International.

Morgenstern, N.R. and Price, V.E., 1965, The analysis of the stability of general slip surfaces: Geotechnique, v. 15. no. 1, p. 79-93.


Washington State Department of Transportation (WSDOT), 2022, Geotechnical design Manual: Olympia, Wash., WSDOT, Manual M 46-03, 1 v., February, available: <https://www.wsdot.wa.gov/Publications/Manuals/M46-03.htm>.



Color	Name	Unit Weight (pcf)	Effective Cohesion (psf)	Effective Friction Angle (°)
Grey	Concrete Abutment	150		
Yellow	Embankment Fill	125	0	32
Orange	Quaternary Alluvium	140	0	40
Dark Grey	Riprap	115	0	45
Blue	Wall Backfill	135	0	38


Cascade Mill Parkway Project Yakima County, Washington	
GLOBAL STABILITY ANALYSIS YRB EAST ABUTMENT STATIC CASE	
March 2023	106384-002
SHANNON & WILSON, INC. Geotechnical and Environmental Consultants	FIG. F-1

Directory: P:\SEA\106000s\106384 Mill Parkway\02 Geotech\GC-007_YRB Abutments Global Stability\



Color	Name	Unit Weight (pcf)	Effective Cohesion (psf)	Effective Friction Angle (°)
	Concrete Abutment	150		
	Embankment Fill	125	0	32
	Quaternary Alluvium	140	0	40
	Riprap	115	0	45
	Wall Backfill	135	0	38

Cascade Mill Parkway Project Yakima County, Washington	
GLOBAL STABILITY ANALYSIS YRB EAST ABUTMENT SEISMIC CASE	
March 2023	106384-002
SHANNON & WILSON, INC. Geotechnical and Environmental Consultants	FIG. F-2



Color	Name	Unit Weight (pcf)	Effective Cohesion (psf)	Effective Friction Angle (°)
Yellow	Embankment Fill	125	0	32
Orange	Quaternary Alluvium	140	0	40
Dark Grey	Riprap	115	0	45


Cascade Mill Parkway Project
Yakima County, Washington

GLOBAL STABILITY ANALYSIS
YRB EAST APPROACH EMBANKMENT
STATIC CASE

March 2023 106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants **FIG. F-3**

Directory: P:\SEA\106000s\106384 Mill Parkway\002 Geotech\GC-007_YRB Abutments Global Stability\



Color	Name	Unit Weight (pcf)	Effective Cohesion (psf)	Effective Friction Angle (°)
Yellow	Embankment Fill	125	0	32
Orange	Quaternary Alluvium	140	0	40
Grey	Riprap	115	0	45

Cascade Mill Parkway Project
Yakima County, Washington


GLOBAL STABILITY ANALYSIS
YRB EAST APPROACH EMBANKMENT
SEISMIC CASE

March 2023 106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. F-4


Directory: P:\SEA\106000s\106384 Mill Parkway\02 Geotech\GC-007_YRB Abutments Global Stability\



Color	Name	Unit Weight (pcf)	Effective Cohesion (psf)	Effective Friction Angle (°)
Grey	Concrete Abutment	150		
Green	County Replacement Fill	125	0	32
Yellow	Embankment Fill	125	0	32
Orange	Quaternary Alluvium	140	0	40
Blue	Wall Backfill	135	0	38

Cascade Mill Parkway Project Yakima County, Washington	
GLOBAL STABILITY ANALYSIS YRB WEST ABUTMENT STATIC CASE	
March 2023	106384-002
SHANNON & WILSON, INC. Geotechnical and Environmental Consultants	FIG. F-5

Directory: P:\SEA\106000s\106384 Mill Parkway\02 Geotech\GC-007_YRB Abutments Global Stability\



Color	Name	Unit Weight (pcf)	Effective Cohesion (psf)	Effective Friction Angle (°)
Grey	Concrete Abutment	150		
Green	County Replacement Fill	125	0	32
Yellow	Embankment Fill	125	0	32
Orange	Quaternary Alluvium	140	0	40
Blue	Wall Backfill	135	0	38


Cascade Mill Parkway Project
Yakima County, Washington

**GLOBAL STABILITY ANALYSIS
YRB WEST ABUTMENT
SEISMIC CASE**

March 2023 106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants **FIG. F-6**

Directory: P:\SEA\106000s\106384 Mill Parkway\002 Geotech\GC-007_YRB Abutments Global Stability\




Color	Name	Unit Weight (pcf)	Effective Cohesion (psf)	Effective Friction Angle (°)
Green	County Replacement Fill	125	0	32
Yellow	Embankment Fill	125	0	32
Brown	Loose GM with Wood Waste	120	0	24
Orange	Quaternary Alluvium	140	0	40

Cascade Mill Parkway Project
Yakima County, Washington

GLOBAL STABILITY ANALYSIS
YRB WEST APPROACH EMBANKMENT
STATIC CASE

March 2023 106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants **FIG. F-7**



Color	Name	Unit Weight (pcf)	Effective Cohesion (psf)	Effective Friction Angle (°)
Green	County Replacement Fill	125	0	32
Yellow	Embankment Fill	125	0	32
Brown	Loose GM with Wood Waste	120	0	24
Light Orange	Quaternary Alluvium	140	0	40


Cascade Mill Parkway Project
Yakima County, Washington

**GLOBAL STABILITY ANALYSIS
YRB WEST APPROACH EMBANKMENT
SEISMIC CASE**

March 2023 106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants

FIG. F-8




Color	Name	Unit Weight (pcf)	Effective Cohesion (psf)	Effective Friction Angle (°)
Orange	City Replacement Fill	125	0	32
Yellow	Embankment Fill	125	0	32
Purple	MSW and/or Wood Waste	50	0	18
Light Orange	Quaternary Alluvium	140	0	40

Cascade Mill Parkway Project
Yakima County, Washington

GLOBAL STABILITY ANALYSIS
FILL EMBANKMENT WEST OF I-82
STATIC CASE

March 2023 106384-002

SHANNON & WILSON, INC.
Geotechnical and Environmental Consultants **FIG. F-9**



Color	Name	Unit Weight (pcf)	Effective Cohesion (psf)	Effective Friction Angle (°)
■	City Replacement Fill	125	0	32
■	MSW and/or Wood Waste	50	0	18
■	Quaternary Alluvium	140	0	40

Cascade Mill Parkway Project Yakima County, Washington	
GLOBAL STABILITY ANALYSIS FILL EMBANKMENT WEST OF I-82 SEISMIC CASE	
March 2023	106384-002
SHANNON & WILSON, INC. Geotechnical and Environmental Consultants	FIG. F-10

Important Information

About Your Geotechnical/Environmental Report

IMPORTANT INFORMATION

CONSULTING SERVICES ARE PERFORMED FOR SPECIFIC PURPOSES AND FOR SPECIFIC CLIENTS.

Consultants prepare reports to meet the specific needs of specific individuals. A report prepared for a civil engineer may not be adequate for a construction contractor or even another civil engineer. Unless indicated otherwise, your consultant prepared your report expressly for you and expressly for the purposes you indicated. No one other than you should apply this report for its intended purpose without first conferring with the consultant. No party should apply this report for any purpose other than that originally contemplated without first conferring with the consultant.

THE CONSULTANT'S REPORT IS BASED ON PROJECT-SPECIFIC FACTORS.

A geotechnical/environmental report is based on a subsurface exploration plan designed to consider a unique set of project-specific factors. Depending on the project, these may include the general nature of the structure and property involved; its size and configuration; its historical use and practice; the location of the structure on the site and its orientation; other improvements such as access roads, parking lots, and underground utilities; and the additional risk created by scope-of-service limitations imposed by the client. To help avoid costly problems, ask the consultant to evaluate how any factors that change subsequent to the date of the report may affect the recommendations. Unless your consultant indicates otherwise, your report should not be used (1) when the nature of the proposed project is changed (for example, if an office building will be erected instead of a parking garage, or if a refrigerated warehouse will be built instead of an unrefrigerated one, or chemicals are discovered on or near the site); (2) when the size, elevation, or configuration of the proposed project is altered; (3) when the location or orientation of the proposed project is modified; (4) when there is a change of ownership; or (5) for application to an adjacent site. Consultants cannot accept responsibility for problems that may occur if they are not consulted after factors that were considered in the development of the report have changed.

SUBSURFACE CONDITIONS CAN CHANGE.

Subsurface conditions may be affected as a result of natural processes or human activity. Because a geotechnical/environmental report is based on conditions that existed at the time of subsurface exploration, construction decisions should not be based on a report whose adequacy may have been affected by time. Ask the consultant to advise if additional tests are desirable before construction starts; for example, groundwater conditions commonly vary seasonally.

Construction operations at or adjacent to the site and natural events such as floods, earthquakes, or groundwater fluctuations may also affect subsurface conditions and, thus, the continuing adequacy of a geotechnical/environmental report. The consultant should be kept apprised of any such events and should be consulted to determine if additional tests are necessary.

MOST RECOMMENDATIONS ARE PROFESSIONAL JUDGMENTS.

Site exploration and testing identifies actual surface and subsurface conditions only at those points where samples are taken. The data were extrapolated by your consultant, who then applied judgment to render an opinion about overall subsurface conditions. The actual interface between materials may be far more gradual or abrupt than your report indicates. Actual conditions in areas not sampled may differ from those predicted in your report. While nothing can be done to prevent such situations, you and your consultant can work together to help reduce their impacts. Retaining

your consultant to observe subsurface construction operations can be particularly beneficial in this respect.

A REPORT'S CONCLUSIONS ARE PRELIMINARY.

The conclusions contained in your consultant's report are preliminary, because they must be based on the assumption that conditions revealed through selective exploratory sampling are indicative of actual conditions throughout a site. Actual subsurface conditions can be discerned only during earthwork; therefore, you should retain your consultant to observe actual conditions and to provide conclusions. Only the consultant who prepared the report is fully familiar with the background information needed to determine whether or not the report's recommendations based on those conclusions are valid and whether or not the contractor is abiding by applicable recommendations. The consultant who developed your report cannot assume responsibility or liability for the adequacy of the report's recommendations if another party is retained to observe construction.

THE CONSULTANT'S REPORT IS SUBJECT TO MISINTERPRETATION.

Costly problems can occur when other design professionals develop their plans based on misinterpretation of a geotechnical/environmental report. To help avoid these problems, the consultant should be retained to work with other project design professionals to explain relevant geotechnical, geological, hydrogeological, and environmental findings, and to review the adequacy of their plans and specifications relative to these issues.

BORING LOGS AND/OR MONITORING WELL DATA SHOULD NOT BE SEPARATED FROM THE REPORT.

Final boring logs developed by the consultant are based upon interpretation of field logs (assembled by site personnel), field test results, and laboratory and/or office evaluation of field samples and data. Only final boring logs and data are customarily included in geotechnical/environmental reports. These final logs should not, under any circumstances, be redrawn for inclusion in architectural or other design drawings, because drafters may commit errors or omissions in the transfer process.

To reduce the likelihood of boring log or monitoring well misinterpretation, contractors should be given ready access to the complete geotechnical engineering/environmental report prepared or authorized for their use. If access is provided only to the report prepared for you, you should advise contractors of the report's limitations, assuming that a contractor was not one of the specific persons for whom the report was prepared, and that developing construction cost estimates was not one of the specific purposes for which it was prepared. While a contractor may gain important knowledge from a report prepared for another party, the contractor should discuss the report with your consultant and perform the additional or alternative work believed necessary to obtain the data specifically appropriate for construction cost estimating purposes. Some clients hold the mistaken impression that simply disclaiming responsibility for the accuracy of subsurface information always insulates them from attendant liability. Providing the best available information to contractors helps prevent costly construction problems and the adversarial attitudes that aggravate them to a disproportionate scale.

READ RESPONSIBILITY CLAUSES CLOSELY.

Because geotechnical/environmental engineering is based extensively on judgment and opinion, it is far less exact than other design disciplines. This situation has resulted in wholly unwarranted claims

being lodged against consultants. To help prevent this problem, consultants have developed a number of clauses for use in their contracts, reports, and other documents. These responsibility clauses are not exculpatory clauses designed to transfer the consultant's liabilities to other parties; rather, they are definitive clauses that identify where the consultant's responsibilities begin and end. Their use helps all parties involved recognize their individual responsibilities and take appropriate action. Some of these definitive clauses are likely to appear in your report, and you are encouraged to read them closely. Your consultant will be pleased to give full and frank answers to your questions.

The preceding paragraphs are based on information provided by the ASFE/Association of Engineering Firms Practicing in the Geosciences, Silver Spring, Maryland

IMPORTANT INFORMATION