APPENDIX G

SOIL, GROUNDWATER, AND SOIL VAPOR CHEMISTRY TABLES

APPENDIX G TABLES

Table G-1	On Property Soil Results for Petroleum Hydrocarbons and VOCs
Table G-2	Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
Table G-3	Off Property Soil Results for Petroleum Hydrocarbons and VOCs
Table G-4	615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
Table G-5	Petroleum Hydrocarbons and VOCs in Groundwater – 2017 and 2021
Table G-6	Petroleum Hydrocarbons and CVOCs in Shallow Zone Groundwater
Table G-7	Groundwater Petroleum Hydrocarbons and CVOCs in Intermediate A Zone Wells
Table G-8	Groundwater Petroleum Hydrocarbons and CVOCs in Intermediate B Zone Wells
Table G-9	Groundwater Petroleum Hydrocarbons and CVOCs in Deep Zone Wells
Table G-10	Summary of Reconnaissance Groundwater Analytical Data
Table G-11	Soil Vapor Analytical Results
Table G-12	Estimated Hydraulic Conductivity Based on Grain Size Analyses

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	**–**	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	**–**	**0.030**	**1.5E-07**
B-1	B-1-13	6/23/00	TR	ARI	13	27.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
B-2	B-2-6.5	6/23/00	TR	ARI	6.5	33.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B-2-11	6/23/00	TR	ARI	11	29.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B-2-16	6/23/00	TR	ARI	16	24.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
B-3	B-3-12	6/23/00	TR	ARI	12	28.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
B-5	B-5-10	6/23/00	TR	ARI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B-5-11.5	6/23/00	TR	ARI	11.5	28.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
B-6	B-6-6	6/24/00	TR	ARI	6	34.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B-6-12	6/24/00	TR	ARI	12	28.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B-6-18	6/24/00	TR	ARI	18	22.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
B-7	B-7-6	6/24/00	TR	ARI	6	34.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
B-8	B-8-4	6/24/00	TR	ARI	4	36.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B-8-8	6/24/00	TR	ARI	8	32.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
B-9	B-9-4	6/24/00	TR	ARI	4	36.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B-9-8	6/24/00	TR	ARI	8	32.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
B-10	B-10-12	6/24/00	TR	ARI	12	28.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
B-201	G-201-10	6/19/17	PES	ESC	10	29.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	G-201-30	6/19/17	PES	ESC	30	9.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	G-201-35	6/19/17	PES	ESC	35	4.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
B-202	G-202-5	6/19/17	PES	ESC	5	34.2	S	0.0404 U	–	–	–	–	–	–	–	–	–	–	–	–	–
	G-202-20	6/19/17	PES	ESC	20	19.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	G-202-50	6/19/17	PES	ESC	50	-10.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
B-203	G-203-5	6/20/17	PES	ESC	5	34.2	S	**168**	–	–	–	–	–	–	–	–	–	–	–	–	–
	G-203-25	6/20/17	PES	ESC	25	14.2	S	**0.174**	–	–	–	–	–	–	–	–	–	–	–	–	–
	G-203-40	6/20/17	PES	ESC	40	-0.8	S	0.788 U	–	–	–	–	–	–	–	–	–	–	–	–	–
	G-203-50	6/20/17	PES	ESC	50	-10.8	S	**0.216**	–	–	–	–	–	–	–	–	–	–	–	–	–
	G-203-80	6/20/17	PES	ESC	80	-40.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
B-204	G-204-20	6/20/17	PES	ESC	20	19.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	G-204-40	6/20/17	PES	ESC	40	-0.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	G-204-45	6/20/17	PES	ESC	45	-5.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
B-205	B-205-10	8/30/17	PES	ESC	10	30.3	S	**274**	–	–	–	0.0318 U	0.0345 U	0.0440 U	0.0334 U	0.0440 U	0.0240 U	0.0365 U	0.0382 U	0.0369 U	0.0894 U
	B-205-55	8/30/17	PES	ESC	55	-14.7	S	0.0396 U	–	–	–	0.000308 U	0.000334 U	0.000426 U	0.000324 U	0.000426 U	0.000232 U	0.000354 U	0.000370 U	0.000358 U	0.000866 U
	B-205-65	8/30/17	PES	ESC	65	-24.7	S	0.0359 U	–	–	–	0.000280 U	0.000303 U	0.000387 U	0.000293 U	0.000387 U	0.000211 U	0.000321 U	0.000336 U	0.000324 U	0.000785 U
	B-205-75	8/30/17	PES	ESC	75	-34.7	S	–	–	–	–	0.000283 U	0.000306 U	0.000391 U	0.000297 U	0.000391 U	0.000213 U	0.000324 U	0.000339 U	0.000328 U	0.000794 U
	B-904-50	8/30/17	PES	ESC	75 (dup)	-34.7	S	–	–	–	–	0.000283 U	0.000307 U	0.000392 U	0.000297 U	0.000392 U	0.000213 U	0.000325 U	0.000340 U	0.000328 U	0.000795 U
B-206	B-206-15	8/14/17	PES	ESC	15	24.1	S	**0.243**	–	–	–	0.00760 U	0.00823 U	0.0105 U	0.00796 U	0.0105 U	0.00573 U	0.00872 U	0.00911 U	0.00880 U	0.0213 U
	B-206-30	8/14/17	PES	ESC	30	9.1	S	**1.32**	–	–	–	0.000303 U	0.000328 U	0.000419 U	0.000318 U	0.000419 U	0.000228 U	**0.00192**	0.000364 U	0.000351 U	0.000850 U
	B-206-40	8/14/17	PES	ESC	40	-0.9	S	0.0358 U	–	–	–	0.000279 U	0.000302 U	0.000386 U	0.000293 U	0.000386 U	0.000210 U	0.000320 U	0.000335 U	0.000323 U	0.000783 U
	B-206-49	8/14/17	PES	ESC	49	-9.9	S	**4.54**	–	–	–	0.000301 U	0.000326 U	0.000416 U	0.000316 U	0.000416 U	0.000227 U	**0.00751**	0.000361 U	0.000349 U	0.000844 U
	B-206-52	8/14/17	PES	ESC	52	-12.9	S	0.0370 U	–	–	–	0.000288 U	0.000312 U	0.000399 U	0.000302 U	0.000399 U	0.000217 U	0.000331 U	0.000346 U	0.000334 U	0.000809 U
	B-206-56	8/14/17	PES	ESC	56	-16.9	S	**1.01**	–	–	–	0.000290 U	0.000314 U	0.000401 U	0.000304 U	0.000401 U	0.000219 U	**0.00103 J**	0.000348 U	0.000336 U	0.000814 U
	B-206-59	8/14/17	PES	ESC	59	-19.9	S	0.0353 U	–	–	–	0.000275 U	0.000298 U	0.000380 U	0.000288 U	0.000380 U	0.000207 U	0.000315 U	0.000330 U	0.000318 U	0.000771 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
B-206	B-206-70	8/14/17	PES	ESC	70	-30.9	S	**1.10 J**	–	–	–	0.000288 U	0.000312 U	0.000398 U	0.000302 U	0.000398 U	0.000217 U	0.000330 U	0.000345 U	0.000333 U	0.000807 U
(continued)	B-206-80	8/14/17	PES	ESC	80	-40.9	S	**0.988 J**	–	–	–	0.000288 U	0.000312 U	0.000398 U	0.000302 U	0.000398 U	0.000217 U	0.000330 U	0.000346 U	0.000334 U	0.000808 U
B-207	B-207-30	8/25/17	PES	ESC	30	8.5	S	0.0385 U	–	–	–	0.00750 U	0.00812 U	0.0104 U	0.00786 U	0.0104 U	0.00566 U	0.00861 U	0.00900 U	0.00869 U	0.0210 U
	B-207-41	8/25/17	PES	ESC	41	-2.5	S	**2.24**	–	–	–	0.000299 U	0.000324 U	0.000413 U	0.000314 U	0.000413 U	0.000225 U	**0.00404**	0.000359 U	0.000347 U	0.000839 U
	B-207-49	8/25/17	PES	ESC	49	-10.5	S	**0.727**	–	–	–	0.000294 U	0.000319 U	0.000407 U	0.000309 U	0.000407 U	0.000222 U	**0.000497 J**	0.000354 U	0.000341 U	0.000827 U
	B-207-55	8/25/17	PES	ESC	55	-16.5	S	**2.49**	–	–	–	0.000308 U	0.000334 U	0.000426 U	0.000323 U	0.000426 U	0.000232 U	**0.0148**	0.000370 U	0.000357 U	0.000865 U
	B-207-60	8/25/17	PES	ESC	60	-21.5	S	0.0361 U	–	–	–	0.000281 U	0.000304 U	0.000388 U	0.000295 U	0.000388 U	0.000212 U	0.000323 U	0.000337 U	0.000326 U	0.000789 U
	B-207-70	8/25/17	PES	ESC	70	-31.5	S	0.968 U	–	–	–	0.000301 U	0.000327 U	0.000417 U	0.000316 U	0.000417 U	0.000227 U	0.000346 U	0.000362 U	0.000349 U	0.000846 U
	B-207-80	8/25/17	PES	ESC	80	-41.5	S	**11.7**	–	–	–	0.000291 U	0.000315 U	0.000402 U	0.000305 U	0.000402 U	0.000219 U	**0.00773**	0.000349 U	0.000337 U	0.000816 U
	B-207-90	8/25/17	PES	ESC	90	-51.5	S	**0.181**	–	–	–	0.00725 U	0.00786 U	0.0100 U	0.00760 U	0.0100 U	0.00547 U	0.00833 U	0.00870 U	0.00841 U	0.0203 U
B-208	B-208-20	8/24/17	PES	ESC	20	18.8	S	–	–	–	–	0.000312 U	0.000338 U	0.000431 U	0.000327 U	0.000431 U	0.000235 U	**0.00125**	0.000375 U	0.000362 U	0.000876 U
	B-208-35	8/24/17	PES	ESC	35	3.8	S	–	–	–	–	0.000287 U	0.000311 U	0.000397 U	0.000301 U	0.000397 U	0.000217 U	**0.000656 J**	0.000345 U	0.000333 U	0.000806 U
	B-901-50	8/24/17	PES	ESC	35 (dup)	3.8	S	–	–	–	–	0.000299 U	0.000323 U	0.000413 U	0.000313 U	0.000413 U	0.000225 U	**0.000572 J**	0.000359 U	0.000346 U	0.000838 U
	B-208-50	8/24/17	PES	ESC	50	-11.2	S	–	–	–	–	0.000291 U	0.000316 U	0.000403 U	0.000306 U	0.000403 U	0.000220 U	**0.000389 J**	0.000350 U	0.000338 U	0.000818 U
	B-208-60	8/24/17	PES	ESC	60	-21.2	S	–	–	–	–	0.000294 U	0.000318 U	0.000406 U	0.000308 U	0.000406 U	0.000222 U	0.000337 U	0.000353 U	0.000341 U	0.000825 U
	B-208-70	8/24/17	PES	ESC	70	-31.2	S	–	–	–	–	0.000295 U	0.000319 U	0.000408 U	0.000309 U	0.000408 U	0.000222 U	0.000338 U	0.000354 U	0.000342 U	0.000827 U
	B-208-80	8/24/17	PES	ESC	80	-41.2	S	–	–	–	–	0.000327 U	0.000354 U	0.000452 U	0.000343 U	0.000452 U	0.000246 U	0.000375 U	0.000392 U	0.000379 U	0.000917 U
B-209	B-209-20	8/25/17	PES	ESC	20	19.0	S	–	–	–	–	0.000307 U	0.000332 U	0.000424 U	0.000322 U	0.000424 U	0.000231 U	**0.000468 J**	0.000368 U	0.000356 U	0.000861 U
	B-209-35	8/25/17	PES	ESC	35	4.0	S	–	–	–	–	0.000282 U	0.000305 U	0.000390 U	0.000296 U	0.000390 U	0.000213 U	0.000324 U	0.000339 U	0.000327 U	0.000791 U
	B-209-50	8/25/17	PES	ESC	50	-11.0	S	–	–	–	–	0.000344 U	0.000373 U	0.000476 U	0.000361 U	0.000476 U	0.000260 U	0.000395 U	0.000414 U	0.000399 U	0.000967 U
	B-209-60	8/25/17	PES	ESC	60	-21.0	S	–	–	–	–	0.000303 U	0.000328 U	0.000419 U	0.000318 U	0.000419 U	0.000228 U	0.000348 U	0.000364 U	0.000351 U	0.000851 U
	B-209-70	8/25/17	PES	ESC	70	-31.0	S	–	–	–	–	0.000281 U	0.000305 U	0.000389 U	0.000295 U	0.000389 U	0.000212 U	0.000323 U	0.000338 U	0.000326 U	0.000790 U
	B-209-75	8/25/17	PES	ESC	75	-36.0	S	–	–	–	–	0.000280 U	0.000303 U	0.000387 U	0.000294 U	0.000387 U	0.000211 U	0.000321 U	0.000336 U	0.000325 U	0.000786 U
	B-209-80	8/25/17	PES	ESC	80	-41.0	S	–	–	–	–	0.000303 U	0.000329 U	0.000419 U	0.000318 U	0.000419 U	0.000229 U	0.000348 U	0.000364 U	0.000352 U	0.000852 U
B-210	B-210-6	8/21/17	PES	ESC	6	33.4	S	–	–	–	–	0.000311 U	0.000337 U	0.000430 U	0.000327 U	0.000430 U	0.000235 U	0.000357 U	0.000374 U	0.000361 U	0.000874 U
	B-210-15	8/21/17	PES	ESC	15	24.4	S	0.919 U	–	–	–	0.00715 U	0.00775 U	0.00988 U	0.00750 U	0.00988 U	0.00540 U	0.00821 U	0.00858 U	0.00829 U	0.0200 U
	B-210-20	8/21/17	PES	ESC	20	19.4	S	0.0378 U	–	–	–	0.000294 U	0.000319 U	0.000407 U	0.000309 U	0.000407 U	0.000222 U	0.000338 U	0.000353 U	0.000341 U	0.000826 U
	B-210-35	8/21/17	PES	ESC	35	4.4	S	0.0391 U	–	–	–	0.000305 U	0.000330 U	0.000421 U	0.000320 U	0.000421 U	0.000230 U	0.000350 U	0.000366 U	0.000353 U	0.000855 U
	B-210-46	8/21/17	PES	ESC	46	-6.6	S	**0.164**	–	–	–	0.000288 U	0.000312 U	0.000398 U	0.000302 U	0.000398 U	0.000217 U	**0.000583 J**	0.000345 U	0.000333 U	0.000807 U
	B-210-60	8/22/17	PES	ESC	60	-20.6	S	0.910 U	–	–	–	0.00708 U	0.00767 U	0.00979 U	0.00743 U	0.00979 U	0.00534 U	0.00814 U	0.00850 U	0.00821 U	0.0199 U
	B-210-70	8/22/17	PES	ESC	70	-30.6	S	0.0366 U	–	–	–	0.000285 U	0.000309 U	0.000394 U	0.000299 U	0.000394 U	0.000215 U	0.000327 U	0.000342 U	0.000330 U	0.000799 U
	B-210-80	8/22/17	PES	ESC	80	-40.6	S	0.0374 U	–	–	–	0.000292 U	0.000316 U	0.000403 U	0.000306 U	0.000403 U	0.000220 U	0.000335 U	0.000350 U	0.000338 U	0.000818 U
	B-900-20	8/22/17	PES	ESC	80 (dup)	-40.6	S	–	–	–	–	0.000314 U	0.000340 U	0.000433 U	0.000329 U	0.000433 U	0.000236 U	0.000360 U	0.000376 U	0.000363 U	0.000880 U
B-211	B-211-20	8/17/17	PES	ESC	20	19.8	S	–	–	–	–	0.000295 U	0.000319 U	0.000408 U	0.000309 U	0.000408 U	0.000222 U	**0.000862 J**	0.000354 U	0.000342 U	0.000827 U
	B-211-35	8/17/17	PES	ESC	35	4.8	S	–	–	–	–	0.000297 U	0.000322 U	0.000411 U	0.000312 U	0.000411 U	0.000224 U	0.000341 U	0.000357 U	0.000344 U	0.000834 U
	B-211-50	8/17/17	PES	ESC	50	-10.3	S	–	–	–	–	0.000285 U	0.000309 U	0.000395 U	0.000300 U	0.000395 U	0.000215 U	0.000328 U	0.000343 U	0.000331 U	0.000801 U
	B-211-57	8/17/17	PES	ESC	57	-17.3	S	–	–	–	–	0.000311 U	0.000337 U	0.000430 U	0.000327 U	0.000430 U	0.000235 U	0.000357 U	0.000374 U	0.000361 U	0.000874 U
	B-211-60	8/17/17	PES	ESC	60	-20.3	S	–	–	–	–	0.000304 U	0.000330 U	0.000421 U	0.000319 U	0.000421 U	0.000229 U	**0.00566**	0.000366 U	0.000353 U	0.000854 U
	B-211-65	8/18/17	PES	ESC	65	-25.3	S	–	–	–	–	0.000298 U	0.000323 U	0.000412 U	0.000313 U	0.000412 U	0.000225 U	**0.00722**	0.000358 U	0.000345 U	0.000836 U
	B-211-70	8/18/17	PES	ESC	70	-30.3	S	–	–	–	–	0.158 U	0.171 U	0.218 U	0.165 U	0.218 U	0.119 U	0.182 U	0.189 U	0.183 U	0.443 U
	B-211-80	8/18/17	PES	ESC	80	-40.3	S	–	–	–	–	0.00715 U	0.00774 U	0.00988 U	0.00749 U	0.00988 U	0.00539 U	0.00821 U	0.00858 U	0.00828 U	0.0200 U
	B-211-90	8/18/17	PES	ESC	90	-50.3	S	–	–	–	–	0.00769 U	0.00833 U	0.0106 U	0.00807 U	0.0106 U	0.00581 U	**0.0105 J**	0.00923 U	0.00892 U	0.0216 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
B-211 (continued)	B-211-100	8/18/17	PES	ESC	100	-60.3	S	–	–	–	–	0.000306 U	0.000332 U	0.000424 U	0.000322 U	0.000424 U	0.000231 U	0.000352 U	0.000368 U	0.000355 U	0.000860 U
	B-211-110	8/18/17	PES	ESC	110	-70.3	S	–	–	–	–	0.000291 U	0.000315 U	0.000403 U	0.000305 U	0.000403 U	0.000219 U	0.000334 U	0.000350 U	0.000337 U	0.000817 U
	B-211-120	8/21/17	PES	ESC	120	-80.3	S	–	–	–	–	0.000296 U	0.000321 U	0.000409 U	0.000311 U	0.000409 U	0.000223 U	0.000340 U	0.000356 U	0.000343 U	0.000831 U
B-216	B-216-20	9/1/17	PES	ESC	20	31.9	S	–	–	–	–	0.000284 U	0.000308 U	0.000393 U	0.000298 U	0.000393 U	0.000214 U	0.000326 U	0.000341 U	0.000330 U	0.000798 U
	B-216-40	9/1/17	PES	ESC	40	11.9	S	–	–	–	–	0.000286 U	0.000310 U	0.000396 U	0.000300 U	0.000396 U	0.000216 U	0.000329 U	0.000344 U	0.000332 U	0.000804 U
	B-216-50	9/1/17	PES	ESC	50	1.9	S	–	–	–	–	0.000285 U	0.000309 U	0.000395 U	0.000299 U	0.000395 U	0.000215 U	0.000328 U	0.000343 U	0.000331 U	0.000801 U
	B-216-55	9/1/17	PES	ESC	55	-3.1	S	–	–	–	–	0.000297 U	0.000322 U	0.000411 U	0.000312 U	0.000411 U	0.000224 U	**0.000509 J**	0.000357 U	0.000345 U	0.000834 U
	B-216-65	9/1/17	PES	ESC	65	-13.1	S	–	–	–	–	0.000317 U	0.000343 U	0.000438 U	0.000333 U	0.000438 U	0.000239 U	0.000364 U	0.000381 U	0.000367 U	0.000890 U
	B-216-85	9/1/17	PES	ESC	85	-33.1	S	–	–	–	–	0.000318 U	0.000345 U	0.000440 U	0.000334 U	0.000440 U	0.000240 U	0.000365 U	0.000382 U	0.000369 U	0.000894 U
	B-216-95	9/1/17	PES	ESC	95	-43.1	S	–	–	–	–	0.000300 U	0.000325 U	0.000415 U	0.000315 U	0.000415 U	0.000226 U	0.000344 U	0.000360 U	0.000348 U	0.000842 U
B-217	B-217-15	9/5/17	PES	ESC	15	36.8	V	–	–	–	–	0.000300 U	0.000325 U	0.000414 U	0.000314 U	0.000414 U	0.000226 U	0.000344 U	0.000360 U	0.000347 U	0.000841 U
	B-217-25	9/5/17	PES	ESC	25	26.8	S	–	–	–	–	0.000293 U	0.000317 U	0.000405 U	0.000307 U	0.000405 U	0.000221 U	0.000336 U	0.000351 U	0.000339 U	0.000822 U
	B-217-35	9/5/17	PES	ESC	35	16.8	S	–	–	–	–	0.000303 U	0.000328 U	0.000419 U	0.000318 U	0.000419 U	0.000228 U	0.000348 U	0.000364 U	0.000351 U	0.000851 U
	B-217-42	9/5/17	PES	ESC	42	9.8	S	–	–	–	–	0.000302 U	0.000327 U	0.000417 U	0.000317 U	0.000417 U	0.000228 U	**0.00333**	0.000362 U	0.000350 U	0.000847 U
	B-217-55	9/5/17	PES	ESC	55	-3.2	S	–	–	–	–	0.000306 U	0.000332 U	0.000424 U	0.000322 U	0.000424 U	0.000231 U	**0.000375 J**	0.000368 U	0.000355 U	0.000860 U
	B-217-65	9/5/17	PES	ESC	65	-13.2	S	–	–	–	–	0.000304 U	0.000329 U	0.000420 U	0.000319 U	0.000420 U	0.000229 U	**0.00515**	0.000365 U	0.000352 U	0.000853 U
	B-217-75	9/5/17	PES	ESC	75	-23.2	S	–	–	–	–	0.000316 U	0.000343 U	0.000437 U	0.000332 U	0.000437 U	0.000238 U	0.000363 U	0.000380 U	0.000367 U	0.000888 U
	B-217-85	9/6/17	PES	ESC	85	-33.2	S	–	–	–	–	0.000301 U	0.000326 U	0.000416 U	0.000316 U	0.000416 U	0.000227 U	0.000345 U	0.000361 U	0.000349 U	0.000844 U
	B-217-95	9/6/17	PES	ESC	95	-43.2	S	–	–	–	–	0.000319 U	0.000346 U	0.000441 U	0.000335 U	0.000441 U	0.000241 U	0.000366 U	0.000383 U	0.000370 U	0.000896 U
	B-217-106	9/6/17	PES	ESC	106	-54.2	S	–	–	–	–	0.0324 U	0.0351 U	0.0447 U	0.0339 U	0.0447 U	0.0244 U	0.0371 U	0.0389 U	0.0375 U	0.0908 U
	B-217-115	9/6/17	PES	ESC	115	-63.2	S	–	–	–	–	0.000305 U	0.000330 U	0.000421 U	0.000320 U	0.000421 U	0.000230 U	0.000350 U	0.000366 U	0.000353 U	0.000856 U
B-218	B-218-12.5	9/19/17	PES	ESC	12.5	25.6	S	–	–	–	–	0.000301 U	0.000326 U	0.000416 U	0.000315 U	0.000416 U	0.000227 U	**0.0131**	0.000361 U	0.000348 U	0.000844 U
	B-218-19	9/19/17	PES	ESC	19	19.1	S	–	–	–	–	0.000300 U	0.000325 U	0.000414 U	0.000314 U	0.000414 U	0.000226 U	**0.000759 J**	0.000360 U	0.000347 U	0.000841 U
	B-218-25	9/19/17	PES	ESC	25	13.1	S	–	–	–	–	0.000306 U	0.000331 U	0.000423 U	0.000321 U	0.000423 U	0.000230 U	**0.000798 J**	0.000367 U	0.000354 U	0.000858 U
	B-218-40	9/19/17	PES	ESC	40	-1.9	S	–	–	–	–	0.0162 U	0.0176 U	0.0224 U	0.0170 U	0.0224 U	0.0122 U	0.0187 U	0.0195 U	0.0188 U	0.0456 U
	B-218-50	9/19/17	PES	ESC	50	-11.9	S	–	–	–	–	0.000281 U	0.000305 U	0.000389 U	0.000295 U	0.000389 U	0.000212 U	**0.00704**	0.000338 U	0.000326 U	0.000790 U
	B-913-70	9/19/17	PES	ESC	50 (dup)	-11.9	S	–	–	–	–	0.000280 U	0.000304 U	0.000388 U	0.000294 U	0.000388 U	0.000211 U	**0.00535**	0.000337 U	0.000325 U	0.000787 U
B-219	B-219-42	8/28/17	PES	ESC	42	-2.2	S	–	–	–	–	0.000288 U	0.000312 U	0.000398 U	0.000302 U	0.000398 U	0.000217 U	0.000330 U	0.000345 U	0.000333 U	0.000807 U
	B-219-50	8/28/17	PES	ESC	50	-10.2	S	–	–	–	–	0.000313 U	0.000339 U	0.000432 U	0.000328 U	0.000432 U	0.000236 U	**0.000401 J**	0.000375 U	0.000362 U	0.000878 U
	B-219-60	8/28/17	PES	ESC	60	-20.2	S	–	–	–	–	0.000284 U	0.000308 U	0.000393 U	0.000298 U	0.000393 U	0.000214 U	0.000326 U	0.000341 U	0.000329 U	0.000797 U
	B-219-70	8/28/17	PES	ESC	70	-30.2	S	–	–	–	–	0.000301 U	0.000326 U	0.000417 U	0.000316 U	0.000417 U	0.000227 U	0.000346 U	0.000362 U	0.000349 U	0.000846 U
	B-219-80	8/28/17	PES	ESC	80	-40.2	S	–	–	–	–	0.000287 U	0.00777 U	0.000396 U	0.000301 U	0.000396 U	0.000216 U	0.000329 U	0.000344 U	0.000332 U	0.000805 U
B-220	B-220-15	9/20/17	PES	ESC	15	23.9	S	–	–	–	–	0.000300 U	0.000325 U	0.000415 U	0.000315 U	0.000415 U	0.000226 U	**0.000875 J**	0.000360 U	0.000348 U	0.000843 U
	B-220-29	9/20/17	PES	ESC	29	9.9	S	–	–	–	–	0.000307 U	0.000332 U	0.000424 U	0.000322 U	0.000424 U	0.000231 U	**0.00352**	0.000368 U	0.000356 U	0.000861 U
	B-220-32	9/20/17	PES	ESC	32	6.9	S	–	–	–	–	0.000301 U	0.000326 U	0.000416 U	0.000316 U	0.000416 U	0.000227 U	**0.00451**	0.000362 U	0.000349 U	0.000845 U
	B-220-40	9/20/17	PES	ESC	40	-1.1	S	–	–	–	–	0.000293 U	0.000317 U	0.000405 U	0.000308 U	0.000405 U	0.000221 U	**0.00259**	0.000352 U	0.000340 U	0.000823 U
	B-220-50	9/20/17	PES	ESC	50	-11.1	S	–	–	–	–	0.000284 U	0.000308 U	0.000393 U	0.000298 U	0.000393 U	0.000214 U	**0.00161**	0.000341 U	0.000329 U	0.000797 U
	B-914-75	9/20/17	PES	ESC	50 (dup)	-11.1	S	–	–	–	–	0.000284 U	0.000308 U	0.000393 U	0.000298 U	0.000393 U	0.000214 U	**0.00164**	0.000341 U	0.000329 U	0.000797 U
B-221	B-221-16	9/20/17	PES	ESC	16	23.0	S	–	–	–	–	0.00773 U	0.00838 U	0.0107 U	0.00811 U	0.0107 U	0.00584 U	0.00888 U	0.00928 U	0.00896 U	0.0217 U
	B-221-22	9/20/17	PES	ESC	22	17.0	S	–	–	–	–	0.304 U	0.329 U	0.420 U	0.319 U	0.420 U	0.229 U	0.349 U	0.365 U	0.352 U	0.852 U
	B-221-33	9/20/17	PES	ESC	33	6.0	S	–	–	–	–	0.296 U	0.320 U	0.409 U	0.310 U	0.409 U	0.223 U	0.339 U	0.355 U	0.343 U	0.829 U
	B-221-37	9/20/17	PES	ESC	37	2.0	S	–	–	–	–	0.0621 U	0.0673 U	0.0858 U	0.0651 U	0.0858 U	0.0468 U	0.0713 U	0.0745 U	0.0720 U	0.174 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
B-221 (continued)	B-915-80	9/20/17	PES	ESC	37 (dup)	2.0	S	–	–	–	–	0.0303 U	0.0328 U	0.0418 U	0.0317 U	0.0418 U	0.0228 U	0.0347 U	0.0363 U	0.0351 U	0.0849 U
	B-221-45	9/20/17	PES	ESC	45	-6.0	S	–	–	–	–	2.90 U	3.14 U	4.00 U	3.04 U	4.00 U	2.18 U	3.32 U	3.48 U	3.36 U	8.13 U
	B-221-50	9/20/17	PES	ESC	50	-11.0	S	–	–	–	–	0.144 U	0.156 U	0.198 U	0.150 U	0.198 U	0.108 U	0.165 U	0.172 U	0.166 U	0.402 U
	B-221-60	9/20/17	PES	ESC	60	-21.0	S	–	–	–	–	0.146 U	0.158 U	0.201 U	0.152 U	0.201 U	0.110 U	0.168 U	0.175 U	0.169 U	0.409 U
	B-221-70	9/21/17	PES	ESC	70	-31.0	S	–	–	–	–	0.000291 U	0.000316 U	0.000403 U	0.000306 U	0.000403 U	0.000220 U	0.000334 U	0.000350 U	0.000338 U	0.000818 U
B-222	B-222-17	9/21/17	PES	ESC	17	22.2	S	–	–	–	–	0.000299 U	0.000324 U	0.000414 U	0.000314 U	0.000414 U	0.000226 U	**0.0110**	0.000359 U	0.000347 U	0.000840 U
	B-222-25	9/21/17	PES	ESC	25	14.2	S	–	–	–	–	0.000305 U	0.000331 U	0.000422 U	0.000320 U	0.000422 U	0.000230 U	**0.00119**	0.000366 U	0.000354 U	0.000856 U
	B-222-34	9/21/17	PES	ESC	34	5.2	S	–	–	–	–	0.000296 U	0.000320 U	0.000409 U	0.000310 U	0.000409 U	0.000223 U	0.000339 U	0.000355 U	0.000343 U	0.000830 U
	B-222-42	9/21/17	PES	ESC	42	-2.8	S	–	–	–	–	0.000327 U	0.000355 U	0.000453 U	0.000344 U	0.000453 U	0.000247 U	**0.00666**	0.000393 U	0.000380 U	0.000919 U
	B-222-50	9/21/17	PES	ESC	50	-10.8	S	–	–	–	–	0.0142 U	0.0153 U	0.0195 U	0.0148 U	0.0195 U	0.0107 U	0.0163 U	0.0169 U	0.0164 U	0.0397 U
	B-916-30	9/21/17	PES	ESC	50 (dup)	-10.8	S	–	–	–	–	0.000280 U	0.000303 U	0.000387 U	0.000294 U	0.000387 U	0.000211 U	**0.000787 J**	0.000336 U	0.000325 U	0.000786 U
B-223	B-223-16	9/21/17	PES	ESC	16	23.1	S	–	–	–	–	0.0624 U	0.0676 U	0.0863 U	0.0655 U	0.0863 U	0.0470 U	0.0716 U	0.0749 U	0.0723 U	0.175 U
	B-223-22	9/21/17	PES	ESC	22	17.1	S	–	–	–	–	0.0603 U	0.0653 U	0.0834 U	0.0633 U	0.0834 U	0.0455 U	0.0692 U	0.0724 U	0.0699 U	0.169 U
	B-223-30	9/21/17	PES	ESC	30	9.1	S	–	–	–	–	7.27 U	7.87 U	10.0 U	7.62 U	10.0 U	5.48 U	8.35 U	8.72 U	8.42 U	20.4 U
	B-223-39	9/21/17	PES	ESC	39	0.1	S	–	–	–	–	0.000301 U	0.000326 U	0.000416 U	0.000315 U	0.000416 U	0.000227 U	0.000345 U	0.000361 U	0.000349 U	0.000844 U
	B-223-47	9/21/17	PES	ESC	47	-7.9	S	–	–	–	–	0.000307 U	0.000332 U	0.000424 U	0.000322 U	0.000424 U	0.000231 U	0.000352 U	0.000368 U	0.000355 U	0.000860 U
	B-917-57	9/21/17	PES	ESC	47 (dup)	-7.9	S	–	–	–	–	0.000284 U	0.000307 U	0.000392 U	0.000298 U	0.000392 U	0.000214 U	0.000326 U	0.000341 U	0.000329 U	0.000796 U
B-224	B-224-6	11/27/17	PES	ESC	6	33.1	S	–	–	–	–	0.000285 U	0.000309 U	0.000395 U	0.000300 U	0.000395 U	0.000215 U	0.000328 U	0.000343 U	0.000331 U	0.000801 U
	B-224-11	11/27/17	PES	ESC	11	28.1	S	–	–	–	–	0.000704 U	0.000763 U	0.000975 U	0.000739 U	0.000975 U	0.000531 U	**0.00251 J**	0.000847 U	0.000817 U	0.00198 U
	B-224-16	11/27/17	PES	ESC	16	23.1	S	–	–	–	–	0.000319 U	0.000346 U	0.000441 U	0.000335 U	0.000441 U	0.000241 U	0.000366 U	0.000383 U	0.000370 U	0.000896 U
	B-224-21.5	11/27/17	PES	ESC	21.5	17.6	S	–	–	–	–	0.000307 U	0.000332 U	0.000424 U	0.000322 U	0.000424 U	0.000231 U	**0.000717 J**	0.000368 U	0.000355 U	0.000860 U
	B-224-26	11/27/17	PES	ESC	26	13.1	S	–	–	–	–	0.000349 U	0.000378 U	0.000482 U	0.000366 U	0.000482 U	0.000263 U	**0.00185**	0.000418 U	0.000405 U	0.000979 U
	B-224-31	11/27/17	PES	ESC	31	8.1	S	–	–	–	–	0.000309 U	0.000335 U	0.000427 U	0.000324 U	0.000427 U	0.000233 U	**0.000567 J**	0.000370 U	0.000357 U	0.000866 U
	B-224-36	11/27/17	PES	ESC	36	3.1	S	–	–	–	–	0.000293 U	0.000318 U	0.000405 U	0.000308 U	0.000405 U	0.000221 U	**0.00141**	0.000352 U	0.000340 U	0.000823 U
	B-224-60.5	11/27/17	PES	ESC	60.5	-21.4	S	–	–	–	–	0.000427 U	0.000463 U	0.000590 U	0.000448 U	0.000590 U	0.000322 U	0.000490 U	0.000513 U	0.000495 U	0.00120 U
B-225	B-225-5	11/27/17	PES	ESC	5	34.1	S	–	–	–	–	0.000286 U	0.000310 U	0.000396 U	0.000300 U	0.000396 U	0.000216 U	0.000329 U	0.000344 U	0.000332 U	0.000804 U
	B-225-11	11/27/17	PES	ESC	11	28.1	S	–	–	–	–	0.000309 U	0.000335 U	0.000427 U	0.000324 U	0.000427 U	0.000233 U	0.000354 U	0.000371 U	0.000358 U	0.000867 U
	B-225-16	11/27/17	PES	ESC	16	23.1	S	–	–	–	–	0.00776 U	0.00841 U	0.0107 U	0.00814 U	0.0107 U	0.00586 U	0.00892 U	0.00932 U	0.00900 U	0.0218 U
	B-225-21	11/27/17	PES	ESC	21	18.1	S	–	–	–	–	0.00750 U	0.00813 U	0.0104 U	0.00787 U	0.0104 U	0.00566 U	0.00862 U	0.00900 U	0.00870 U	0.0210 U
	B-225-26	11/27/17	PES	ESC	26	13.1	S	–	–	–	–	0.000310 U	0.000336 U	0.000429 U	0.000326 U	0.000429 U	0.000234 U	**0.000531 J**	0.000373 U	0.000360 U	0.000871 U
	B-225-31	11/27/17	PES	ESC	31	8.1	S	–	–	–	–	0.000302 U	0.000327 U	0.000417 U	0.000317 U	0.000417 U	0.000227 U	**0.000466 J**	0.000362 U	0.000350 U	0.000847 U
	B-225-36	11/27/17	PES	ESC	36	3.1	S	–	–	–	–	0.000325 U	0.000352 U	0.000450 U	0.000341 U	0.000450 U	0.000245 U	0.000373 U	0.000390 U	0.000377 U	0.000913 U
B-226	B-226-6	11/28/17	PES	ESC	6	33.1	S	–	–	–	–	0.000318 U	0.000344 U	0.000440 U	0.000334 U	0.000440 U	0.000240 U	0.000365 U	0.000382 U	0.000369 U	0.000892 U
	B-226-11	11/28/17	PES	ESC	11	28.1	S	–	–	–	–	0.000299 U	0.000324 U	0.000414 U	0.000314 U	0.000414 U	0.000226 U	0.000344 U	0.000360 U	0.000347 U	0.000840 U
	B-226-16	11/28/17	PES	ESC	16	23.1	S	–	–	–	–	0.00740 U	0.00802 U	0.0102 U	0.00776 U	0.0102 U	0.00559 U	0.00850 U	0.00889 U	0.00858 U	0.0208 U
	B-920-35	11/28/17	PES	ESC	16 (dup)	23.1	S	–	–	–	–	0.000292 U	0.000316 U	0.000404 U	0.000306 U	0.000404 U	0.000220 U	0.000335 U	0.000351 U	0.000339 U	0.000820 U
	B-226-21	11/28/17	PES	ESC	21	18.1	S	–	–	–	–	0.000301 U	0.000326 U	0.000416 U	0.000316 U	0.000416 U	0.000227 U	0.000345 U	0.000361 U	0.000349 U	0.000844 U
	B-226-31.5	11/28/17	PES	ESC	31.5	7.6	S	–	–	–	–	0.000281 U	0.000305 U	0.000389 U	0.000295 U	0.000389 U	0.000212 U	**0.000856 J**	0.000338 U	0.000326 U	0.000789 U
	B-226-40	11/28/17	PES	ESC	40	-0.9	S	–	–	–	–	0.000302 U	0.000327 U	0.000418 U	0.000317 U	0.000418 U	0.000228 U	**0.000559 J**	0.000363 U	0.000350 U	0.000848 U
B-227	B-227-6	11/28/17	PES	ESC	6	33.1	S	–	–	–	–	0.000301 U	0.000327 U	0.000417 U	0.000316 U	0.000417 U	0.000227 U	0.000346 U	0.000362 U	0.000349 U	0.000846 U
	B-227-11	11/28/17	PES	ESC	11	28.1	S	–	–	–	–	0.000285 U	0.000308 U	0.000393 U	0.000299 U	0.000393 U	0.000214 U	0.000327 U	0.000342 U	0.000330 U	0.000799 U
	B-227-16	11/28/17	PES	ESC	16	23.1	S	–	–	–	–	0.000303 U	0.000328 U	0.000418 U	0.000317 U	0.000418 U	0.000228 U	**0.000711 J**	0.000363 U	0.000351 U	0.000849 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
B-227 (continued)	B-227-21	11/28/17	PES	ESC	21	18.1	S	–	–	–	–	0.000306 U	0.000332 U	0.000424 U	0.000322 U	0.000424 U	0.000231 U	**0.00156**	0.000368 U	0.000355 U	0.000860 U
	B-227-26	11/28/17	PES	ESC	26	13.1	S	–	–	–	–	0.000308 U	0.000333 U	0.000425 U	0.000323 U	0.000425 U	0.000232 U	**0.000741 J**	0.000369 U	0.000356 U	0.000863 U
	B-227-31	11/28/17	PES	ESC	31	8.1	S	–	–	–	–	0.000317 U	0.000343 U	0.000438 U	0.000332 U	0.000438 U	0.000239 U	0.000363 U	0.000380 U	0.000367 U	0.000889 U
	B-227-36	11/28/17	PES	ESC	36	3.1	S	–	–	–	–	0.000303 U	0.000328 U	0.000419 U	0.000318 U	0.000419 U	0.000228 U	**0.00117**	0.000364 U	0.000351 U	0.000850 U
B-228	B-228-6	11/29/17	PES	ESC	6	33.1	S	–	–	–	–	0.000323 U	0.000350 U	0.000446 U	0.000339 U	0.000446 U	0.000243 U	0.000371 U	0.000388 U	0.000374 U	0.000906 U
	B-228-11	11/29/17	PES	ESC	11	28.1	S	–	–	–	–	0.000293 U	0.000318 U	0.000406 U	0.000308 U	0.000406 U	0.000221 U	0.000337 U	0.000352 U	0.000340 U	0.000824 U
	B-228-16	11/29/17	PES	ESC	16	23.1	S	–	–	–	–	0.000284 U	0.000308 U	0.000393 U	0.000298 U	0.000393 U	0.000214 U	**0.00143**	0.000341 U	0.000330 U	0.000798 U
	B-921-22	11/29/17	PES	ESC	16 (dup)	23.1	S	–	–	–	–	0.000303 U	0.000329 U	0.000419 U	0.000318 U	0.000419 U	0.000229 U	**0.00155**	0.000364 U	0.000352 U	0.000851 U
	B-228-21	11/29/17	PES	ESC	21	18.1	S	–	–	–	–	0.000299 U	0.000323 U	0.000413 U	0.000313 U	0.000413 U	0.000225 U	0.000343 U	0.000358 U	0.000346 U	0.000838 U
	B-228-26	11/29/17	PES	ESC	26	13.1	S	–	–	–	–	0.000284 U	0.000308 U	0.000393 U	0.000298 U	0.000393 U	0.000214 U	**0.000595 J**	0.000341 U	0.000329 U	0.000798 U
	B-228-31	11/29/17	PES	ESC	31	8.1	S	–	–	–	–	0.000293 U	0.000318 U	0.000405 U	0.000308 U	0.000405 U	0.000221 U	**0.000822 J**	0.000352 U	0.000340 U	0.000823 U
	B-228-36	11/29/17	PES	ESC	36	3.1	S	–	–	–	–	0.000298 U	0.000323 U	0.000412 U	0.000313 U	0.000412 U	0.000225 U	**0.00205**	0.000358 U	0.000346 U	0.000837 U
B-229	B-229-6	11/29/17	PES	ESC	6	33.1	S	–	–	–	–	0.000386 U	0.000419 U	0.000534 U	0.000405 U	0.000534 U	0.000291 U	0.000443 U	0.000464 U	0.000448 U	0.00108 U
	B-229-11	11/29/17	PES	ESC	11	28.1	S	–	–	–	–	0.000375 U	0.000406 U	0.000518 U	0.000393 U	0.000518 U	0.000282 U	0.000430 U	0.000450 U	0.000434 U	0.00105 U
	B-229-16	11/29/17	PES	ESC	16	23.1	S	–	–	–	–	0.000315 U	0.000341 U	0.000435 U	0.000330 U	0.000435 U	0.000237 U	0.000361 U	0.000378 U	0.000365 U	0.000883 U
	B-229-25	11/29/17	PES	ESC	25	14.1	S	–	–	–	–	0.000289 U	0.000314 U	0.000400 U	0.000304 U	0.000400 U	0.000218 U	**0.00243**	0.000348 U	0.000336 U	0.000812 U
	B-229-31	11/29/17	PES	ESC	31	8.1	S	–	–	–	–	0.000318 U	0.000345 U	0.000440 U	0.000334 U	0.000440 U	0.000240 U	**0.00294**	0.000382 U	0.000369 U	0.000894 U
	B-229-36	11/29/17	PES	ESC	36	3.1	S	–	–	–	–	0.000290 U	0.000315 U	0.000401 U	0.000305 U	0.000401 U	0.000219 U	**0.00247**	0.000349 U	0.000337 U	0.000815 U
	B-229-41	11/29/17	PES	ESC	41	-1.9	S	–	–	–	–	0.000307 U	0.000333 U	0.000425 U	0.000323 U	0.000425 U	0.000232 U	**0.00417**	0.000369 U	0.000356 U	0.000863 U
	B-229-45	11/29/17	PES	ESC	45	-5.9	S	–	–	–	–	0.000316 U	0.000342 U	0.000437 U	0.000331 U	0.000437 U	0.000238 U	**0.000619 J**	0.000379 U	0.000366 U	0.000886 U
B-230	B-230-6	11/30/17	PES	ESC	6	33.1	S	–	–	–	–	0.000278 U	0.000302 U	0.000385 U	0.000292 U	0.000385 U	0.000210 U	0.000320 U	0.000334 U	0.000323 U	0.000782 U
	B-230-11	11/30/17	PES	ESC	11	28.1	S	–	–	–	–	0.000288 U	0.000312 U	0.000399 U	0.000303 U	0.000399 U	0.000217 U	0.000331 U	0.000346 U	0.000334 U	0.000809 U
	B-230-16	11/30/17	PES	ESC	16	23.1	S	–	–	–	–	0.0735 U	0.0796 U	0.102 U	0.0770 U	0.102 U	0.0554 U	0.0844 U	0.0882 U	0.0851 U	0.206 U
	B-230-21	11/30/17	PES	ESC	21	18.1	S	–	–	–	–	0.630 U	0.683 U	0.872 U	0.661 U	0.872 U	0.475 U	0.724 U	0.757 U	0.731 U	1.77 U
	B-922-15	11/30/17	PES	ESC	21 (dup)	18.1	S	–	–	–	–	0.319 U	0.345 U	0.441 U	0.335 U	0.441 U	0.240 U	0.366 U	0.383 U	0.370 U	0.895 U
	B-230-26	11/30/17	PES	ESC	26	13.1	S	–	–	–	–	0.791 U	0.857 U	1.09 U	0.829 U	1.09 U	0.597 U	0.908 U	0.949 U	0.917 U	2.22 U
	B-230-31	11/30/17	PES	ESC	31	8.1	S	–	–	–	–	0.328 U	0.356 U	0.454 U	0.345 U	0.454 U	0.248 U	0.377 U	0.394 U	0.381 U	0.922 U
	B-230-35	11/30/17	PES	ESC	35	4.1	S	–	–	–	–	0.0477 U	0.0517 U	0.0659 U	0.0501 U	0.0659 U	0.0359 U	0.0548 U	0.0573 U	0.0553 U	0.133 U
	B-230-55	11/30/17	PES	ESC	55	-15.9	S	–	–	–	–	0.0792 U	0.0858 U	0.109 U	0.0831 U	0.109 U	0.0598 U	0.0910 U	0.0951 U	0.0918 U	0.222 U
B-231	B-231-6	11/30/17	PES	ESC	6	33.1	S	–	–	–	–	0.000326 U	0.000353 U	0.000450 U	0.000342 U	0.000450 U	0.000245 U	0.000374 U	0.000391 U	0.000377 U	0.000914 U
	B-231-11	11/30/17	PES	ESC	11	28.1	S	–	–	–	–	0.000311 U	0.000337 U	0.000430 U	0.000326 U	0.000430 U	0.000235 U	0.000357 U	0.000374 U	0.000361 U	0.000873 U
	B-231-16	11/30/17	PES	ESC	16	23.1	S	–	–	–	–	0.00739 U	0.00801 U	0.0102 U	0.00775 U	0.0102 U	0.00558 U	0.00849 U	0.00887 U	0.00857 U	0.0207 U
	B-231-21	11/30/17	PES	ESC	21	18.1	S	–	–	–	–	0.0174 U	0.0189 U	0.0241 U	0.0183 U	0.0241 U	0.0131 U	0.0201 U	0.0210 U	0.0202 U	0.0490 U
	B-231-26	11/30/17	PES	ESC	26	13.1	S	–	–	–	–	0.000307 U	0.000332 U	0.000424 U	0.000322 U	0.000424 U	0.000231 U	**0.000948 J**	0.000368 U	0.000355 U	0.000860 U
	B-231-30	11/30/17	PES	ESC	30	9.1	S	–	–	–	–	0.000298 U	0.000323 U	0.000412 U	0.000312 U	0.000412 U	0.000224 U	0.000342 U	0.000358 U	0.000345 U	0.000836 U
	B-231-36	11/30/17	PES	ESC	36	3.1	S	–	–	–	–	0.000299 U	0.000324 U	0.000414 U	0.000314 U	0.000414 U	0.000226 U	0.000344 U	0.000359 U	0.000347 U	0.000840 U
B-232	B-232-6	12/1/17	PES	ESC	6	33.1	S	–	–	–	–	0.000312 U	0.000338 U	0.000431 U	0.000327 U	0.000431 U	0.000235 U	0.000358 U	0.000374 U	0.000361 U	0.000875 U
	B-232-11	12/1/17	PES	ESC	11	28.1	S	–	–	–	–	0.000351 U	0.000381 U	0.000486 U	0.000369 U	0.000486 U	0.000265 U	0.000403 U	0.000422 U	0.000407 U	0.000986 U
	B-232-16	12/1/17	PES	ESC	16	23.1	S	–	–	–	–	0.000309 U	0.000335 U	0.000427 U	0.000324 U	0.000427 U	0.000233 U	0.000355 U	0.000371 U	0.000358 U	0.000868 U
	B-232-21	12/1/17	PES	ESC	21	18.1	S	–	–	–	–	0.000295 U	0.000320 U	0.000409 U	0.000310 U	0.000409 U	0.000223 U	**0.000638 J**	0.000355 U	0.000342 U	0.000829 U
	B-232-26	12/1/17	PES	ESC	26	13.1	S	–	–	–	–	0.00987 U	0.0107 U	0.0136 U	0.0103 U	0.0136 U	0.00744 U	0.0113 U	0.0118 U	0.0114 U	0.0276 U
	B-232-31	12/1/17	PES	ESC	31	8.1	S	–	–	–	–	0.000298 U	0.000323 U	0.000412 U	0.000313 U	0.000412 U	0.000225 U	**0.000364 J**	0.000358 U	0.000346 U	0.000837 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
B-232 (continued)	B-232-36	12/1/17	PES	ESC	36	3.1	S	–	–	–	–	0.000313 U	0.000339 U	0.000433 U	0.000328 U	0.000433 U	0.000236 U	**0.00117 J**	0.000376 U	0.000363 U	0.000878 U
B-233	B-233-6	12/1/17	PES	ESC	6	29.5	S	–	–	–	–	0.000285 U	0.000309 U	0.000394 U	0.000299 U	0.000394 U	0.000215 U	0.000327 U	0.000342 U	0.000330 U	0.000800 U
	B-233-11	12/1/17	PES	ESC	11	24.5	S	–	–	–	–	0.000737 U	0.000797 U	0.00102 U	0.000773 U	0.00102 U	0.000555 U	**0.00492**	0.000884 U	0.000853 U	0.00207 U
	B-233-16	12/1/17	PES	ESC	16	19.5	S	–	–	–	–	0.000373 U	0.000403 U	0.000515 U	0.000391 U	0.000515 U	0.000281 U	0.000428 U	0.000447 U	0.000432 U	0.00105 U
	B-233-21	12/1/17	PES	ESC	21	14.5	S	–	–	–	–	0.00753 U	0.00816 U	0.0104 U	0.00790 U	0.0104 U	0.00568 U	0.00865 U	0.00904 U	0.00873 U	0.0211 U
	B-233-26	12/1/17	PES	ESC	26	9.5	S	–	–	–	–	0.0158 U	0.0171 U	0.0218 U	0.0165 U	0.0218 U	0.0119 U	0.0182 U	0.0189 U	0.0183 U	0.0442 U
	B-233-31	12/1/17	PES	ESC	31	4.5	S	–	–	–	–	0.00821 U	0.00889 U	0.0113 U	0.00860 U	0.0113 U	0.00619 U	0.00942 U	0.00985 U	0.00951 U	0.0230 U
	B-233-36	12/1/17	PES	ESC	36	-0.5	S	–	–	–	–	0.00743 U	0.00805 U	0.0103 U	0.00779 U	0.0103 U	0.00561 U	0.00853 U	0.00891 U	0.00861 U	0.0208 U
B-234	B-234-11	12/4/17	PES	ESC	11	40.8	V	–	–	–	–	0.000307 U	0.000333 U	0.000424 U	0.000322 U	0.000424 U	0.000231 U	0.000352 U	0.000369 U	0.000356 U	0.000862 U
	B-234-30	12/4/17	PES	ESC	30	21.8	S	–	–	–	–	0.000279 U	0.000303 U	0.000386 U	0.000293 U	0.000386 U	0.000211 U	0.000321 U	0.000336 U	0.000324 U	0.000784 U
B-234A	B-234A-35	12/4/17	PES	ESC	35	16.8	S	–	–	–	–	0.000303 U	0.000328 U	0.000419 U	0.000318 U	0.000419 U	0.000228 U	0.000348 U	0.000364 U	0.000351 U	0.000850 U
	B-234A-40	12/4/17	PES	ESC	40	11.8	S	–	–	–	–	0.000284 U	0.000308 U	0.000393 U	0.000298 U	0.000393 U	0.000214 U	0.000326 U	0.000341 U	0.000329 U	0.000798 U
	B-234A-42	12/4/17	PES	ESC	42	9.8	S	–	–	–	–	0.000323 U	0.000350 U	0.000447 U	0.000339 U	0.000447 U	0.000244 U	**0.00288**	0.000388 U	0.000375 U	0.000908 U
	B-924-30	12/4/17	PES	ESC	42 (dup)	9.8	S	–	–	–	–	0.000321 U	0.000347 U	0.000443 U	0.000336 U	0.000443 U	0.000242 U	**0.00373**	0.000385 U	0.000372 U	0.000900 U
	B-234A-45	12/4/17	PES	ESC	45	6.8	S	–	–	–	–	0.000298 U	0.000322 U	0.000411 U	0.000312 U	0.000411 U	0.000224 U	**0.00126**	0.000357 U	0.000345 U	0.000835 U
B-235	B-235-15	12/5/17	PES	ESC	15	36.8	V	–	–	–	–	0.000317 U	0.000343 U	0.000438 U	0.000332 U	0.000438 U	0.000239 U	0.000363 U	0.000380 U	0.000367 U	0.000889 U
	B-235-35	12/5/17	PES	ESC	35	16.8	S	–	–	–	–	0.000292 U	0.000317 U	0.000404 U	0.000307 U	0.000404 U	0.000220 U	0.000335 U	0.000351 U	0.000339 U	0.000820 U
	B-235-40	12/5/17	PES	ESC	40	11.8	S	–	–	–	–	0.000289 U	0.000313 U	0.000400 U	0.000304 U	0.000400 U	0.000218 U	0.000332 U	0.000347 U	0.000335 U	0.000812 U
	B-235-42.5	12/5/17	PES	ESC	42.5	9.3	S	–	–	–	–	0.0577 U	0.0625 U	0.0797 U	0.0605 U	0.0797 U	0.0435 U	0.0662 U	0.0692 U	0.0668 U	0.162 U
	B-235-45	12/5/17	PES	ESC	45	6.8	S	–	–	–	–	0.000297 U	0.000322 U	0.000411 U	0.000312 U	0.000411 U	0.000224 U	**0.00276**	0.000357 U	0.000345 U	0.000834 U
B-236	B-236-20	12/5/17	PES	ESC	20	31.8	S	–	–	–	–	0.000302 U	0.000327 U	0.000417 U	0.000317 U	0.000417 U	0.000228 U	0.000346 U	0.000362 U	0.000350 U	0.000847 U
	B-236-35	12/5/17	PES	ESC	35	16.8	S	–	–	–	–	0.000478 U	0.000518 U	0.000661 U	0.000502 U	0.000661 U	0.000360 U	0.000549 U	0.000575 U	0.000555 U	0.00134 U
	B-236-40	12/5/17	PES	ESC	40	11.8	S	–	–	–	–	0.000292 U	0.000316 U	0.000404 U	0.000306 U	0.000404 U	0.000220 U	0.000335 U	0.000351 U	0.000339 U	0.000820 U
	B-236-42.5	12/5/17	PES	ESC	42.5	9.3	S	–	–	–	–	0.310 U	0.335 U	0.428 U	0.325 U	0.428 U	0.233 U	0.355 U	0.372 U	0.359 U	0.869 U
	B-236-45	12/5/17	PES	ESC	45	6.8	S	–	–	–	–	0.104 U	0.113 U	0.144 U	0.109 U	0.144 U	0.0781 U	0.120 U	0.124 U	0.121 U	0.291 U
B-237	B-237-5	12/6/17	PES	ESC	5	46.8	V	–	–	–	–	0.000307 U	0.000333 U	0.000425 U	0.000323 U	0.000425 U	0.000232 U	0.000353 U	0.000369 U	0.000356 U	0.000863 U
	B-237-35	12/6/17	PES	ESC	35	16.8	S	–	–	–	–	0.000308 U	0.000334 U	0.000426 U	0.000324 U	0.000426 U	0.000232 U	0.000354 U	0.000370 U	0.000357 U	0.000866 U
	B-237-40	12/6/17	PES	ESC	40	11.8	S	–	–	–	–	0.000284 U	0.000307 U	0.000392 U	0.000298 U	0.000392 U	0.000214 U	**0.000480 J**	0.000341 U	0.000329 U	0.000796 U
	B-237-42	12/6/17	PES	ESC	42	9.8	S	–	–	–	–	0.000312 U	0.000338 U	0.000431 U	0.000327 U	0.000431 U	0.000235 U	**0.00854**	0.000375 U	0.000362 U	0.000876 U
	B-925-41	12/6/17	PES	ESC	42 (dup)	9.8	S	–	–	–	–	0.0337 U	0.0365 U	0.0466 U	0.0354 U	0.0466 U	0.0254 U	0.0387 U	0.0405 U	0.0391 U	0.0946 U
	B-237-45	12/6/17	PES	ESC	45	6.8	S	–	–	–	–	0.000340 U	0.000368 U	0.000470 U	0.000357 U	0.000470 U	0.000256 U	**0.00246**	0.000408 U	0.000394 U	0.000954 U
B-238	B-238-6	12/6/17	PES	ESC	6	33.1	S	–	–	–	–	0.000308 U	0.000333 U	0.000426 U	0.000323 U	0.000426 U	0.000232 U	0.000353 U	0.000370 U	0.000357 U	0.000864 U
	B-238-11	12/6/17	PES	ESC	11	28.1	S	–	–	–	–	0.000307 U	0.000333 U	0.000425 U	0.000322 U	0.000425 U	0.000232 U	0.000353 U	0.000369 U	0.000356 U	0.000862 U
	B-238-16	12/6/17	PES	ESC	16	23.1	S	–	–	–	–	0.0755 U	0.0818 U	0.104 U	0.0792 U	0.104 U	0.0570 U	0.0867 U	0.0906 U	0.0875 U	0.212 U
	B-238-21	12/6/17	PES	ESC	21	18.1	S	–	–	–	–	0.295 U	0.319 U	0.407 U	0.309 U	0.407 U	0.222 U	0.338 U	0.354 U	0.341 U	0.827 U
	B-238-26	12/6/17	PES	ESC	26	13.1	S	–	–	–	–	0.000295 U	0.000320 U	0.000408 U	0.000310 U	0.000408 U	0.000223 U	**0.00340**	0.000354 U	0.000342 U	0.000829 U
	B-238-31	12/6/17	PES	ESC	31	8.1	S	–	–	–	–	0.000280 U	0.000303 U	0.000387 U	0.000294 U	0.000387 U	0.000211 U	**0.000506 J**	0.000336 U	0.000324 U	0.000786 U
	B-238-36	12/6/17	PES	ESC	36	3.1	S	–	–	–	–	0.000309 U	0.000335 U	0.000427 U	0.000324 U	0.000427 U	0.000233 U	**0.000670 J**	0.000371 U	0.000358 U	0.000868 U
B-239	B-239-5	4/3/18	PES	ESC	5	34.2	S	–	–	–	–	0.000314 U	0.000340 U	0.000434 U	0.000330 U	0.000434 U	0.000237 U	0.000360 U	0.000377 U	0.000364 U	0.000881 U
	B-239-10	4/3/18	PES	ESC	10	29.2	S	–	–	–	–	0.000311 U	0.000337 U	0.000431 U	0.000327 U	0.000431 U	0.000235 U	**0.000934 J**	0.000374 U	0.000361 U	0.000874 U
	B-239-15	4/3/18	PES	ESC	15	24.2	S	–	–	–	–	0.000301 U	0.000326 U	0.000416 U	0.000315 U	0.000416 U	0.000227 U	**0.000355 J**	0.000361 U	0.000348 U	0.000844 U
	B-239-20	4/3/18	PES	ESC	20	19.2	S	–	–	–	–	0.000298 U	0.000323 U	0.000412 U	0.000313 U	0.000412 U	0.000225 U	0.000342 U	0.000358 U	0.000345 U	0.000836 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
B-239 (continued)	B-239-25	4/3/18	PES	ESC	25	14.2	S	–	–	–	–	0.000302 U	0.000328 U	0.000418 U	0.000317 U	0.000418 U	0.000228 U	0.000347 U	0.000363 U	0.000351 U	0.000849 U
	B-239-35	4/3/18	PES	ESC	35	4.2	S	–	–	–	–	0.000286 U	0.000310 U	0.000395 U	0.000300 U	0.000395 U	0.000215 U	0.000328 U	0.000343 U	0.000331 U	0.000802 U
	B-239-40	4/3/18	PES	ESC	40	-0.8	S	–	–	–	–	0.000299 U	0.000324 U	0.000414 U	0.000314 U	0.000414 U	0.000226 U	0.000344 U	0.000360 U	0.000347 U	0.000841 U
	B-239-45	4/3/18	PES	ESC	45	-5.8	S	–	–	–	–	0.000296 U	0.000320 U	0.000409 U	0.000310 U	0.000409 U	0.000223 U	0.000339 U	0.000355 U	0.000343 U	0.000830 U
	B-239-50	4/3/18	PES	ESC	50	-10.8	S	–	–	–	–	0.000292 U	0.000316 U	0.000403 U	0.000306 U	0.000403 U	0.000220 U	0.000335 U	0.000350 U	0.000338 U	0.000818 U
	B-909-50	4/3/18	PES	ESC	50 (dup)	-10.8	S	–	–	–	–	0.000293 U	0.000318 U	0.000406 U	0.000308 U	0.000406 U	0.000221 U	0.000337 U	0.000352 U	0.000340 U	0.000823 U
	B-239-55	4/3/18	PES	ESC	55	-15.8	S	–	–	–	–	0.000300 U	0.000325 U	0.000415 U	0.000315 U	0.000415 U	0.000226 U	0.000345 U	0.000361 U	0.000348 U	0.000843 U
	B-239-60	4/3/18	PES	ESC	60	-20.8	S	–	–	–	–	0.000295 U	0.000320 U	0.000408 U	0.000310 U	0.000408 U	0.000223 U	0.000339 U	0.000355 U	0.000342 U	0.000829 U
	B-239-65	4/3/18	PES	ESC	65	-25.8	S	–	–	–	–	0.000295 U	0.000320 U	0.000408 U	0.000310 U	0.000408 U	0.000222 U	0.000339 U	0.000354 U	0.000342 U	0.000828 U
	B-239-70	4/3/18	PES	ESC	70	-30.8	S	–	–	–	–	0.000294 U	0.000319 U	0.000407 U	0.000309 U	0.000407 U	0.000222 U	0.000338 U	0.000353 U	0.000341 U	0.000825 U
	B-239-75	4/3/18	PES	ESC	75	-35.8	S	–	–	–	–	0.000304 U	0.000330 U	0.000421 U	0.000319 U	0.000421 U	0.000229 U	0.000349 U	0.000365 U	0.000353 U	0.000854 U
	B-239-80	4/3/18	PES	ESC	80	-40.8	S	–	–	–	–	0.000302 U	0.000327 U	0.000418 U	0.000317 U	0.000418 U	0.000228 U	0.000347 U	0.000363 U	0.000350 U	0.000848 U
B-240	B-240-5	4/2/18	PES	ESC	5	34.2	S	–	–	–	–	0.000291 U	0.000316 U	0.000403 U	0.000306 U	0.000403 U	0.000220 U	0.000334 U	0.000350 U	0.000338 U	0.000818 U
	B-240-10	4/2/18	PES	ESC	10	29.2	S	–	–	–	–	0.000291 U	0.000315 U	0.000402 U	0.000305 U	0.000402 U	0.000219 U	0.000334 U	0.000349 U	0.000337 U	0.000817 U
	B-240-15	4/2/18	PES	ESC	15	24.2	S	–	–	–	–	0.000303 U	0.000328 U	0.000419 U	0.000318 U	0.000419 U	0.000228 U	**0.000550 J**	0.000364 U	0.000351 U	0.000850 U
	B-240-20	4/2/18	PES	ESC	20	19.2	S	–	–	–	–	0.000307 U	0.000333 U	0.000425 U	0.000322 U	0.000425 U	0.000232 U	**0.00112 J**	0.000369 U	0.000356 U	0.000863 U
	B-240-25	4/2/18	PES	ESC	25	14.2	S	–	–	–	–	0.0147 U	0.0160 U	0.0203 U	0.0154 U	0.0203 U	0.0111 U	0.0170 U	0.0177 U	0.0171 U	0.0413 U
	B-240-30	4/2/18	PES	ESC	30	9.2	S	–	–	–	–	0.000318 U	0.000344 U	0.000440 U	0.000334 U	0.000440 U	0.000240 U	**0.000805 J**	0.000382 U	0.000369 U	0.000893 U
	B-240-35	4/2/18	PES	ESC	35	4.2	S	–	–	–	–	0.000317 U	0.000343 U	0.000438 U	0.000333 U	0.000438 U	0.000239 U	**0.000727 J**	0.000381 U	0.000367 U	0.000890 U
	B-240-42	4/2/18	PES	ESC	42	-2.8	S	–	–	–	–	0.000284 U	0.000308 U	0.000393 U	0.000298 U	0.000393 U	0.000214 U	0.000326 U	0.000341 U	0.000329 U	0.000798 U
	B-240-45	4/2/18	PES	ESC	45	-5.8	S	–	–	–	–	0.000280 U	0.000303 U	0.000387 U	0.000294 U	0.000387 U	0.000211 U	0.000321 U	0.000336 U	0.000324 U	0.000786 U
	B-240-50	4/2/18	PES	ESC	50	-10.8	S	–	–	–	–	0.000297 U	0.000322 U	0.000411 U	0.000312 U	0.000411 U	0.000224 U	0.000341 U	0.000357 U	0.000345 U	0.000834 U
	B-240-55	4/2/18	PES	ESC	55	-15.8	S	**0.376**	–	–	–	0.000306 U	0.000332 U	0.000423 U	0.000321 U	0.000423 U	0.000231 U	0.000351 U	0.000368 U	0.000355 U	0.000860 U
	B-240-60	4/2/18	PES	ESC	60	-20.8	S	**0.124**	–	–	–	0.000307 U	0.000333 U	0.000425 U	0.000322 U	0.000425 U	0.000232 U	0.000353 U	0.000369 U	0.000356 U	0.000863 U
	B-240-65	4/2/18	PES	ESC	65	-25.8	S	0.0368 U	–	–	–	0.000286 U	0.000310 U	0.000396 U	0.000300 U	0.000396 U	0.000216 U	0.000329 U	0.000344 U	0.000332 U	0.000803 U
	B-240-70	4/2/18	PES	ESC	70	-30.8	S	**0.0447 J**	–	–	–	0.000305 U	0.000331 U	0.000422 U	0.000320 U	0.000422 U	0.000230 U	0.000351 U	0.000367 U	0.000354 U	0.000857 U
	B-240-75	4/2/18	PES	ESC	75	-35.8	S	0.0372 U	–	–	–	0.000290 U	0.000314 U	0.000401 U	0.000304 U	0.000401 U	0.000219 U	0.000333 U	0.000348 U	0.000336 U	0.000814 U
	B-240-80	4/2/18	PES	ESC	80	-40.8	S	0.0386 U	–	–	–	0.000300 U	0.000325 U	0.000415 U	0.000315 U	0.000415 U	0.000226 U	0.000345 U	0.000361 U	0.000348 U	0.000843 U
B-241	B-241-5	4/4/18	PES	ESC	5	34.1	S	–	–	–	–	0.000286 U	0.000310 U	0.000396 U	0.000300 U	0.000396 U	0.000216 U	0.000329 U	0.000344 U	0.000332 U	0.000804 U
	B-241-10	4/4/18	PES	ESC	10	29.1	S	–	–	–	–	0.000299 U	0.000324 U	0.000414 U	0.000314 U	0.000414 U	0.000226 U	0.000344 U	0.000359 U	0.000347 U	0.000840 U
	B-241-15	4/4/18	PES	ESC	15	24.1	S	–	–	–	–	0.000295 U	0.000319 U	0.000407 U	0.000309 U	0.000407 U	0.000222 U	0.000338 U	0.000354 U	0.000342 U	0.000827 U
	B-241-20	4/4/18	PES	ESC	20	19.1	S	–	–	–	–	0.000321 U	0.000348 U	0.000444 U	0.000337 U	0.000444 U	0.000242 U	**0.00159**	0.000386 U	0.000372 U	0.000902 U
	B-241-25	4/4/18	PES	ESC	25	14.1	S	–	–	–	–	0.000298 U	0.000323 U	0.000413 U	0.000313 U	0.000413 U	0.000225 U	0.000342 U	0.000358 U	0.000346 U	0.000838 U
	B-241-30	4/3/18	PES	ESC	30	9.1	S	–	–	–	–	0.000296 U	0.000321 U	0.000409 U	0.000311 U	0.000409 U	0.000223 U	**0.00371**	0.000356 U	0.000343 U	0.000831 U
	B-241-35	4/3/18	PES	ESC	35	4.1	S	–	–	–	–	0.000306 U	0.000331 U	0.000423 U	0.000321 U	0.000423 U	0.000230 U	0.000351 U	0.000367 U	0.000354 U	0.000858 U
	B-241-40	4/3/18	PES	ESC	40	-0.9	S	–	–	–	–	0.000290 U	0.000314 U	0.000400 U	0.000304 U	0.000400 U	0.000218 U	0.000332 U	0.000348 U	0.000336 U	0.000813 U
	B-241-45	4/3/18	PES	ESC	45	-5.9	S	–	–	–	–	0.000291 U	0.000315 U	0.000402 U	0.000305 U	0.000402 U	0.000219 U	**0.00141**	0.000349 U	0.000337 U	0.000816 U
	B-241-50	4/4/18	PES	ESC	50	-10.9	S	–	–	–	–	0.000297 U	0.000322 U	0.000411 U	0.000312 U	0.000411 U	0.000224 U	**0.0243**	0.000357 U	0.000345 U	0.000835 U
	B-241-55	4/4/18	PES	ESC	55	-15.9	S	–	–	–	–	0.000307 U	0.000333 U	0.000425 U	0.000322 U	0.000425 U	0.000232 U	**0.0129**	0.000369 U	0.000356 U	0.000863 U
	B-241-60	4/3/18	PES	ESC	60	-20.9	S	–	–	–	–	0.000296 U	0.000320 U	0.000409 U	0.000310 U	0.000409 U	0.000223 U	0.000339 U	0.000355 U	0.000343 U	0.000830 U
	B-241-65	4/3/18	PES	ESC	65	-25.9	S	–	–	–	–	0.000312 U	0.000338 U	0.000432 U	0.000328 U	0.000432 U	0.000236 U	**0.0167**	0.000375 U	0.000362 U	0.000877 U
	B-241-70	4/3/18	PES	ESC	70	-30.9	S	–	–	–	–	0.000305 U	0.000330 U	0.000421 U	0.000320 U	0.000421 U	0.000230 U	0.000350 U	0.000366 U	0.000353 U	0.000855 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
B-241	B-241-75	4/3/18	PES	ESC	75	-35.9	S	–	–	–	–	0.000308 U	0.000333 U	0.000426 U	0.000323 U	0.000426 U	0.000232 U	**0.00240**	0.000370 U	0.000357 U	0.000864 U
(continued)	B-241-80	4/4/18	PES	ESC	80	-40.9	S	–	–	–	–	0.000303 U	0.000329 U	0.000419 U	0.000318 U	0.000419 U	0.000229 U	0.000348 U	0.000364 U	0.000352 U	0.000852 U
B-242	B-242-5	4/4/18	PES	ESC	5	33.8	S	–	–	–	–	0.000287 U	0.000310 U	0.000396 U	0.000301 U	0.000396 U	0.000216 U	0.000329 U	0.000344 U	0.000332 U	0.000804 U
	B-242-10	4/4/18	PES	ESC	10	28.8	S	–	–	–	–	0.000289 U	0.000313 U	0.000399 U	0.000303 U	0.000399 U	0.000218 U	0.000332 U	0.000347 U	0.000335 U	0.000811 U
	B-242-15	4/4/18	PES	ESC	15	23.8	S	–	–	–	–	0.000308 U	0.000333 U	0.000426 U	0.000323 U	0.000426 U	0.000232 U	0.000353 U	0.000370 U	0.000357 U	0.000864 U
	B-242-20	4/4/18	PES	ESC	20	18.8	S	–	–	–	–	0.000299 U	0.000324 U	0.000414 U	0.000314 U	0.000414 U	0.000225 U	0.000343 U	0.000359 U	0.000347 U	0.000840 U
	B-242-25	4/4/18	PES	ESC	25	13.8	S	–	–	–	–	0.0291 U	0.0315 U	0.0402 U	0.0305 U	0.0402 U	0.0219 U	0.0334 U	0.0349 U	0.0337 U	0.0817 U
	B-242-30	4/4/18	PES	ESC	30	8.8	S	–	–	–	–	0.000295 U	0.000320 U	0.000408 U	0.000310 U	0.000408 U	0.000223 U	0.000339 U	0.000355 U	0.000342 U	0.000829 U
	B-242-35	4/4/18	PES	ESC	35	3.8	S	–	–	–	–	0.000304 U	0.000329 U	0.000420 U	0.000319 U	0.000420 U	0.000229 U	0.000349 U	0.000365 U	0.000352 U	0.000853 U
	B-242-40	4/4/18	PES	ESC	40	-1.2	S	–	–	–	–	0.000289 U	0.000313 U	0.000399 U	0.000303 U	0.000399 U	0.000218 U	0.000331 U	0.000347 U	0.000335 U	0.000811 U
	B-242-45	4/4/18	PES	ESC	45	-6.2	S	–	–	–	–	0.000305 U	0.000331 U	0.000422 U	0.000320 U	0.000422 U	0.000230 U	0.000350 U	0.000367 U	0.000354 U	0.000857 U
	B-242-50	4/4/18	PES	ESC	50	-11.2	S	–	–	–	–	0.000296 U	0.000320 U	0.000409 U	0.000310 U	0.000409 U	0.000223 U	0.000339 U	0.000355 U	0.000343 U	0.000830 U
	B-910-50	4/4/18	PES	ESC	50 (dup)	-11.2	S	–	–	–	–	0.000296 U	0.000321 U	0.000409 U	0.000311 U	0.000409 U	0.000223 U	0.000340 U	0.000356 U	0.000343 U	0.000831 U
	B-242-55	4/4/18	PES	ESC	55	-16.2	S	–	–	–	–	0.000290 U	0.000314 U	0.000401 U	0.000304 U	0.000401 U	0.000219 U	0.000333 U	0.000348 U	0.000336 U	0.000814 U
	B-242-60	4/4/18	PES	ESC	60	-21.2	S	–	–	–	–	0.000291 U	0.000315 U	0.000403 U	0.000306 U	0.000403 U	0.000219 U	0.000334 U	0.000350 U	0.000337 U	0.000817 U
	B-242-65	4/4/18	PES	ESC	65	-26.2	S	–	–	–	–	0.000286 U	0.000310 U	0.000395 U	0.000300 U	0.000395 U	0.000216 U	0.000328 U	0.000343 U	0.000331 U	0.000802 U
	B-242-70	4/4/18	PES	ESC	70	-31.2	S	–	–	–	–	0.000302 U	0.000328 U	0.000418 U	0.000317 U	0.000418 U	0.000228 U	0.000347 U	0.000363 U	0.000350 U	0.000849 U
	B-242-75	4/4/18	PES	ESC	75	-36.2	S	–	–	–	–	0.000293 U	0.000317 U	0.000405 U	0.000307 U	0.000405 U	0.000221 U	0.000336 U	0.000352 U	0.000339 U	0.000822 U
	B-242-80	4/4/18	PES	ESC	80	-41.2	S	–	–	–	–	0.000306 U	0.000331 U	0.000423 U	0.000321 U	0.000423 U	0.000231 U	0.000351 U	0.000367 U	0.000355 U	0.000859 U
B-243	B-243-5	3/29/18	PES	ESC	5	34.9	S	0.0394 U	–	–	–	0.000307 U	0.000332 U	0.000424 U	0.000322 U	0.000424 U	0.000231 U	0.000352 U	0.000368 U	0.000355 U	0.000861 U
	B-243-10	3/29/18	PES	ESC	10	29.9	S	**0.619**	–	–	–	0.000300 U	0.000325 U	0.000415 U	0.000315 U	0.000415 U	0.000226 U	0.000344 U	0.000360 U	0.000348 U	0.000842 U
	B-243-15	3/29/18	PES	ESC	15	24.9	S	**1.64**	–	–	–	0.00747 U	0.00809 U	0.0103 U	0.00783 U	0.0103 U	0.00564 U	0.00858 U	0.00896 U	0.00866 U	0.0209 U
	B-243-20	3/29/18	PES	ESC	20	19.9	S	**1.11**	–	–	–	0.000304 U	0.000330 U	0.000421 U	0.000319 U	0.000421 U	0.000229 U	0.000349 U	0.000366 U	0.000353 U	0.000854 U
	B-243-25	3/29/18	PES	ESC	25	14.9	S	**0.568**	–	–	–	0.000294 U	0.000319 U	0.000407 U	0.000309 U	0.000407 U	0.000222 U	0.000338 U	0.000353 U	0.000341 U	0.000826 U
	B-243-30	3/29/18	PES	ESC	30	9.9	S	**0.586**	–	–	–	0.000287 U	0.000311 U	0.000397 U	0.000302 U	0.000397 U	0.000217 U	0.000330 U	0.000345 U	0.000333 U	0.000807 U
	B-243-35	3/29/18	PES	ESC	35	4.9	S	**0.491**	–	–	–	0.000292 U	0.000317 U	0.000404 U	0.000307 U	0.000404 U	0.000220 U	**0.000700 J**	0.000351 U	0.000339 U	0.000821 U
	B-243-42	3/29/18	PES	ESC	42	-2.1	S	**0.724**	–	–	–	0.000288 U	0.000313 U	0.000399 U	0.000303 U	0.000399 U	0.000217 U	**0.00399**	0.000346 U	0.000334 U	0.000810 U
	B-243-45	3/29/18	PES	ESC	45	-5.1	S	**0.820**	–	–	–	0.000286 U	0.000310 U	0.000395 U	0.000300 U	0.000395 U	0.000216 U	**0.00362**	0.000343 U	0.000332 U	0.000803 U
	B-243-50	3/29/18	PES	ESC	50	-10.1	S	**5.12**	–	–	–	0.000305 U	0.000330 U	0.000421 U	0.000320 U	0.000421 U	0.000230 U	**0.0354**	0.000366 U	0.000353 U	0.000856 U
	IW-908-50	3/29/18	PES	ESC	50 (dup)	-10.1	S	–	–	–	–	0.000299 U	0.000324 U	0.000413 U	0.000313 U	0.000413 U	0.000225 U	**0.0530**	0.000359 U	0.000346 U	0.000838 U
	B-243-55	3/29/18	PES	ESC	55	-15.1	S	–	–	–	–	0.000285 U	0.000309 U	0.000394 U	0.000299 U	0.000394 U	0.000215 U	**0.00916**	0.000342 U	0.000330 U	0.000800 U
	B-243-60	3/29/18	PES	ESC	60	-20.1	S	–	–	–	–	0.000302 U	0.000327 U	0.000417 U	0.000317 U	0.000417 U	0.000227 U	**0.0144**	0.000362 U	0.000350 U	0.000847 U
	B-243-65	3/29/18	PES	ESC	65	-25.1	S	–	–	–	–	0.000290 U	0.000314 U	0.000401 U	0.000304 U	0.000401 U	0.000219 U	**0.00727**	0.000348 U	0.000336 U	0.000814 U
	B-243-70	3/29/18	PES	ESC	70	-30.1	S	–	–	–	–	0.000306 U	0.000332 U	0.000423 U	0.000321 U	0.000423 U	0.000231 U	0.000351 U	0.000368 U	0.000355 U	0.000859 U
	B-243-75	3/29/18	PES	ESC	75	-35.1	S	–	–	–	–	0.000315 U	0.000341 U	0.000435 U	0.000330 U	0.000435 U	0.000237 U	0.000361 U	0.000378 U	0.000365 U	0.000883 U
	B-243-80	3/29/18	PES	ESC	80	-40.1	S	–	–	–	–	0.000321 U	0.000347 U	0.000443 U	0.000336 U	0.000443 U	0.000242 U	0.000368 U	0.000385 U	0.000372 U	0.000900 U
B-244	B-244-5	3/28/18	PES	ESC	5	33.8	S	–	–	–	–	0.000333 U	0.000361 U	0.000461 U	0.000350 U	0.000461 U	0.000251 U	0.000382 U	0.000400 U	0.000386 U	0.000935 U
	B-244-10	3/28/18	PES	ESC	10	28.8	S	–	–	–	–	0.000315 U	0.000341 U	0.000435 U	0.000330 U	0.000435 U	0.000237 U	0.000361 U	0.000378 U	0.000365 U	0.000883 U
	B-244-15	3/28/18	PES	ESC	15	23.8	S	–	–	–	–	0.000301 U	0.000326 U	0.000416 U	0.000316 U	0.000416 U	0.000227 U	0.000346 U	0.000362 U	0.000349 U	0.000845 U
	B-244-20	3/28/18	PES	ESC	20	18.8	S	–	–	–	–	0.000300 U	0.000324 U	0.000414 U	0.000314 U	0.000414 U	0.000226 U	0.000344 U	0.000360 U	0.000347 U	0.000841 U
	B-244-25	3/28/18	PES	ESC	25	13.8	S	–	–	–	–	0.000280 U	0.000303 U	0.000386 U	0.000293 U	0.000386 U	0.000211 U	0.000321 U	0.000336 U	0.000324 U	0.000785 U
	B-244-30	3/28/18	PES	ESC	30	8.8	S	–	–	–	–	0.000289 U	0.000313 U	0.000399 U	0.000303 U	0.000399 U	0.000218 U	**0.000672 J**	0.000347 U	0.000335 U	0.000810 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
B-244 (continued)	B-244-35	3/28/18	PES	ESC	35	3.8	S	–	–	–	–	0.000303 U	0.000328 U	0.000419 U	0.000318 U	0.000419 U	0.000229 U	**0.000446 J**	0.000364 U	0.000351 U	0.000851 U
	B-244-40	3/28/18	PES	ESC	40	-1.2	S	–	–	–	–	0.000291 U	0.000315 U	0.000403 U	0.000305 U	0.000403 U	0.000219 U	**0.000845 J**	0.000350 U	0.000337 U	0.000817 U
	B-244-42	3/28/18	PES	ESC	42	-3.2	S	–	–	–	–	0.00743 U	0.00804 U	0.0103 U	0.00779 U	0.0103 U	0.00560 U	0.00853 U	0.00891 U	0.00861 U	0.0208 U
	B-244-45	3/28/18	PES	ESC	45	-6.2	S	–	–	–	–	0.000297 U	0.000322 U	0.000411 U	0.000312 U	0.000411 U	0.000224 U	**0.00376 J**	0.000357 U	0.000344 U	0.000834 U
	B-244-50	3/28/18	PES	ESC	50	-11.2	S	–	–	–	–	0.000292 U	0.000316 U	0.000404 U	0.000306 U	0.000404 U	0.000220 U	**0.00268 J**	0.000351 U	0.000338 U	0.000819 U
	B-244-55	3/28/18	PES	ESC	55	-16.2	S	–	–	–	–	0.000291 U	0.000315 U	0.000402 U	0.000305 U	0.000402 U	0.000219 U	**0.00501 J**	0.000349 U	0.000337 U	0.000816 U
	B-244-60	3/28/18	PES	ESC	60	-21.2	S	–	–	–	–	0.000295 U	0.000319 U	0.000407 U	0.000309 U	0.000407 U	0.000222 U	**0.00703 J**	0.000354 U	0.000342 U	0.000827 U
	B-244-65	3/28/18	PES	ESC	65	-26.2	S	–	–	–	–	0.000299 U	0.000324 U	0.000414 U	0.000314 U	0.000414 U	0.000226 U	**0.00576 J**	0.000359 U	0.000347 U	0.000840 U
	B-244-70	3/28/18	PES	ESC	70	-31.2	S	–	–	–	–	0.000287 U	0.000310 U	0.000396 U	0.000301 U	0.000396 U	0.000216 U	**0.0119 J**	0.000344 U	0.000332 U	0.000804 U
	IW-907-70	3/28/18	PES	ESC	70 (dup)	-31.2	S	–	–	–	–	0.000287 U	0.000311 U	0.000397 U	0.000302 U	0.000397 U	0.000217 U	**0.0143**	0.000345 U	0.000333 U	0.000807 U
	B-244-75	3/28/18	PES	ESC	75	-36.2	S	–	–	–	–	0.000303 U	0.000328 U	0.000419 U	0.000318 U	0.000419 U	0.000228 U	**0.00664**	0.000364 U	0.000351 U	0.000850 U
	B-244-80	3/28/18	PES	ESC	80	-41.2	S	–	–	–	–	0.000307 U	0.000332 U	0.000424 U	0.000322 U	0.000424 U	0.000231 U	0.000352 U	0.000369 U	0.000356 U	0.000861 U
B-245	B-245-5	3/28/18	PES	ESC	5	34.9	V	–	–	–	–	0.000287 U	0.000311 U	0.000397 U	0.000301 U	0.000397 U	0.000217 U	0.000330 U	0.000345 U	0.000333 U	0.000806 U
	B-245-10	3/28/18	PES	ESC	10	29.9	S	–	–	–	–	0.000303 U	0.000328 U	0.000419 U	0.000318 U	0.000419 U	0.000228 U	0.000348 U	0.000364 U	0.000351 U	0.000850 U
	B-245-15	3/28/18	PES	ESC	15	24.9	S	–	–	–	–	0.000306 U	0.000331 U	0.000423 U	0.000321 U	0.000423 U	0.000231 U	0.000351 U	0.000367 U	0.000355 U	0.000859 U
	B-245-20	3/28/18	PES	ESC	20	19.9	S	–	–	–	–	0.000285 U	0.000309 U	0.000394 U	0.000299 U	0.000394 U	0.000215 U	0.000327 U	0.000342 U	0.000330 U	0.000800 U
	B-245-25	3/28/18	PES	ESC	25	14.9	S	–	–	–	–	0.000299 U	0.000324 U	0.000413 U	0.000313 U	0.000413 U	0.000225 U	0.000343 U	0.000359 U	0.000346 U	0.000839 U
	B-245-30	3/29/18	PES	ESC	30	9.9	S	–	–	–	–	0.000567 U	0.000615 U	0.000785 U	0.000595 U	0.000785 U	0.000427 U	**0.0259**	0.000681 U	0.000658 U	0.00160 U
	B-245-35	3/29/18	PES	ESC	35	4.9	S	–	–	–	–	0.000297 U	0.000322 U	0.000411 U	0.000312 U	0.000411 U	0.000224 U	0.000341 U	0.000357 U	0.000344 U	0.000834 U
	B-245-40	3/29/18	PES	ESC	40	-0.1	S	–	–	–	–	0.000294 U	0.000318 U	0.000406 U	0.000308 U	0.000406 U	0.000221 U	0.000337 U	0.000353 U	0.000341 U	0.000825 U
	B-245-45	3/29/18	PES	ESC	45	-5.1	S	–	–	–	–	0.000293 U	0.000318 U	0.000406 U	0.000308 U	0.000406 U	0.000221 U	0.000337 U	0.000352 U	0.000340 U	0.000824 U
	B-245-50	3/29/18	PES	ESC	50	-10.1	S	–	–	–	–	0.000299 U	0.000324 U	0.000414 U	0.000314 U	0.000414 U	0.000226 U	0.000343 U	0.000359 U	0.000347 U	0.000840 U
	B-245-55	3/29/18	PES	ESC	55	-15.1	S	–	–	–	–	0.000298 U	0.000322 U	0.000411 U	0.000312 U	0.000411 U	0.000224 U	**0.000632 J**	0.000357 U	0.000345 U	0.000835 U
	B-245-60	3/29/18	PES	ESC	60	-20.1	S	–	–	–	–	0.000283 U	0.000306 U	0.000391 U	0.000297 U	0.000391 U	0.000213 U	0.000325 U	0.000340 U	0.000328 U	0.000794 U
	B-245-65	3/29/18	PES	ESC	65	-25.1	S	–	–	–	–	0.000302 U	0.000327 U	0.000418 U	0.000317 U	0.000418 U	0.000228 U	0.000347 U	0.000363 U	0.000350 U	0.000848 U
	B-245-70	3/29/18	PES	ESC	70	-30.1	S	–	–	–	–	0.000311 U	0.000336 U	0.000429 U	0.000326 U	0.000429 U	0.000234 U	0.000356 U	0.000373 U	0.000360 U	0.000872 U
	B-245-75	3/29/18	PES	ESC	75	-35.1	S	–	–	–	–	0.000298 U	0.000322 U	0.000411 U	0.000312 U	0.000411 U	0.000224 U	0.000341 U	0.000357 U	0.000345 U	0.000835 U
	B-245-80	3/29/18	PES	ESC	80	-40.1	S	–	–	–	–	0.000306 U	0.000331 U	0.000423 U	0.000321 U	0.000423 U	0.000231 U	0.000351 U	0.000367 U	0.000355 U	0.000858 U
B-246	B-246-6	5/11/18	PES	ESC	6	33.9	S	–	–	–	–	0.000593 U	0.000326 U	0.000463 U	0.00105 U	0.000801 U	0.000682 U	0.000593 U	0.000831 U	0.000742 U	0.00605 U
	B-246-11	5/11/18	PES	ESC	11	28.9	S	–	–	–	–	0.000590 U	0.000325 U	0.000461 U	0.00104 U	0.000797 U	0.000679 U	0.000590 U	0.000827 U	0.000738 U	0.00602 U
	B-246-15	5/11/18	PES	ESC	15	24.9	S	–	–	–	–	0.000565 U	0.000311 U	0.000441 U	0.000998 U	0.000763 U	0.000650 U	0.000565 U	0.000791 U	0.000706 U	0.00576 U
	B-246-25	5/11/18	PES	ESC	25	14.9	S	–	–	–	–	0.000559 U	0.000307 U	0.000436 U	0.000987 U	0.000755 U	0.000643 U	**0.00214 J**	0.000783 U	0.000699 U	0.00570 U
	B-246-30	5/11/18	PES	ESC	30	9.9	S	–	–	–	–	0.000588 U	0.000324 U	0.000459 U	0.00104 U	0.000794 U	0.000677 U	**0.00878**	0.000824 U	0.000736 U	0.00600 U
	B-246-35	5/11/18	PES	ESC	35	4.9	S	–	–	–	–	0.000576 U	0.000317 U	0.000450 U	0.00102 U	0.000778 U	0.000663 U	0.000576 U	0.000807 U	0.000720 U	0.00588 U
	B-246-40	5/11/18	PES	ESC	40	-0.1	S	–	–	–	–	0.000566 U	0.000311 U	0.000442 U	0.00100 U	0.000764 U	0.000651 U	**0.00121 J**	0.000793 U	0.000708 U	0.00578 U
	B-246-43	5/11/18	PES	ESC	43	-3.1	S	–	–	–	–	0.000547 U	0.000301 U	0.000426 U	0.000966 U	0.000738 U	0.000629 U	**0.00192 J**	0.000765 U	0.000683 U	0.00558 U
	B-246-45	5/11/18	PES	ESC	45	-5.1	S	–	–	–	–	0.000603 U	0.000331 U	0.000471 U	0.00106 U	0.000814 U	0.000693 U	0.000603 U	0.000844 U	0.000754 U	0.00615 U
	B-246-50	5/11/18	PES	ESC	50	-10.1	S	–	–	–	–	0.000563 U	0.000309 U	0.000439 U	0.000993 U	0.000759 U	0.000647 U	0.000563 U	0.000788 U	0.000703 U	0.00574 U
	B-246-55	5/11/18	PES	ESC	55	-15.1	S	–	–	–	–	0.000573 U	0.000315 U	0.000447 U	0.00101 U	0.000773 U	0.000658 U	0.000573 U	0.000802 U	0.000716 U	0.00584 U
	B-246-60	5/11/18	PES	ESC	60	-20.1	S	–	–	–	–	0.000567 U	0.000312 U	0.000443 U	0.00100 U	0.000766 U	0.000653 U	0.000567 U	0.000794 U	0.000709 U	0.00579 U
	B-246-65	5/11/18	PES	ESC	65	-25.1	S	–	–	–	–	0.000618 U	0.000340 U	0.000482 U	0.00109 U	0.000835 U	0.000711 U	0.000618 U	0.000866 U	0.000773 U	0.00631 U
	B-246-70	5/11/18	PES	ESC	70	-30.1	S	–	–	–	–	0.000556 U	0.000306 U	0.000433 U	0.000981 U	0.000750 U	0.000639 U	**0.00147 J**	0.000778 U	0.000695 U	0.00567 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
B-246 (continued)	B-246-75	5/11/18	PES	ESC	75	-35.1	S	–	–	–	–	0.000579 U	0.000319 U	0.000452 U	0.00102 U	0.000782 U	0.000666 U	0.000579 U	0.000811 U	0.000724 U	0.00591 U
	B-246-80	5/11/18	PES	ESC	80	-40.1	S	–	–	–	–	0.000565 U	0.000311 U	0.000440 U	0.000997 U	0.000762 U	0.000649 U	0.000565 U	0.000791 U	0.000706 U	0.00576 U
	B-926-100	5/11/18	PES	ESC	45 (dup)	-5.1	S	–	–	–	–	0.000749 U	0.000412 U	0.000584 U	0.00132 U	0.00101 U	0.000861 U	0.000749 U	0.00105 U	0.000936 U	0.00764 U
B-247	B-247-5	4/20/18	PES	ESC	5	34.7	S	–	–	–	–	0.000300 U	0.000325 U	0.000414 U	0.000314 U	0.000414 U	0.000226 U	0.000344 U	0.000360 U	0.000347 U	0.000841 U
	B-247-10	4/20/18	PES	ESC	10	29.7	S	–	–	–	–	0.000304 U	0.000329 U	0.000420 U	0.000319 U	0.000420 U	0.000229 U	0.000349 U	0.000365 U	0.000352 U	0.000853 U
	B-247-15	4/20/18	PES	ESC	15	24.7	S	–	–	–	–	0.000293 U	0.000317 U	0.000405 U	0.000307 U	0.000405 U	0.000221 U	0.000336 U	0.000352 U	0.000339 U	0.000822 U
	B-247-20	4/20/18	PES	ESC	20	19.7	S	–	–	–	–	0.000295 U	0.000319 U	0.000408 U	0.000309 U	0.000408 U	0.000222 U	0.000338 U	0.000354 U	0.000342 U	0.000827 U
	B-247-25	4/20/18	PES	ESC	25	14.7	S	–	–	–	–	0.000287 U	0.000311 U	0.000397 U	0.000301 U	0.000397 U	0.000217 U	0.000330 U	0.000345 U	0.000333 U	0.000806 U
	B-247-30	4/20/18	PES	ESC	30	9.7	S	–	–	–	–	0.000291 U	0.000315 U	0.000402 U	0.000305 U	0.000402 U	0.000219 U	0.000334 U	0.000349 U	0.000337 U	0.000816 U
	B-247-35	4/20/18	PES	ESC	35	4.7	S	–	–	–	–	0.000291 U	0.000315 U	0.000402 U	0.000305 U	0.000402 U	0.000219 U	0.000334 U	0.000349 U	0.000337 U	0.000817 U
	B-247-40	4/20/18	PES	ESC	40	-0.3	S	–	–	–	–	0.000296 U	0.000321 U	0.000410 U	0.000311 U	0.000410 U	0.000223 U	0.000340 U	0.000356 U	0.000344 U	0.000832 U
	B-247-45	4/20/18	PES	ESC	45	-5.3	S	–	–	–	–	0.000285 U	0.000309 U	0.000394 U	0.000299 U	0.000394 U	0.000215 U	0.000327 U	0.000342 U	0.000331 U	0.000801 U
	B-247-50	4/20/18	PES	ESC	50	-10.3	S	–	–	–	–	0.000291 U	0.000315 U	0.000402 U	0.000305 U	0.000402 U	0.000219 U	**0.00775**	0.000349 U	0.000337 U	0.000816 U
	B-247-55	4/20/18	PES	ESC	55	-15.3	S	–	–	–	–	0.000298 U	0.000323 U	0.000412 U	0.000313 U	0.000412 U	0.000225 U	0.000342 U	0.000358 U	0.000346 U	0.000837 U
	B-247-60	4/20/18	PES	ESC	60	-20.3	S	–	–	–	–	0.000284 U	0.000308 U	0.000393 U	0.000298 U	0.000393 U	0.000214 U	**0.000535 J**	0.000342 U	0.000330 U	0.000798 U
	B-247-65	4/20/18	PES	ESC	65	-25.3	S	–	–	–	–	0.000295 U	0.000319 U	0.000407 U	0.000309 U	0.000407 U	0.000222 U	0.000338 U	0.000354 U	0.000341 U	0.000827 U
	B-247-70	4/20/18	PES	ESC	70	-30.3	S	–	–	–	–	0.000296 U	0.000320 U	0.000409 U	0.000310 U	0.000409 U	0.000223 U	0.000340 U	0.000355 U	0.000343 U	0.000830 U
	B-247-75	4/20/18	PES	ESC	75	-35.3	S	–	–	–	–	0.000302 U	0.000327 U	0.000417 U	0.000317 U	0.000417 U	0.000228 U	0.000347 U	0.000363 U	0.000350 U	0.000848 U
	B-247-80	4/20/18	PES	ESC	80	-40.3	S	–	–	–	–	0.000295 U	0.000320 U	0.000408 U	0.000310 U	0.000408 U	0.000222 U	0.000339 U	0.000354 U	0.000342 U	0.000828 U
	B-909-20	4/20/18	PES	ESC	80 (dup)	-40.3	S	–	–	–	–	0.000286 U	0.000310 U	0.000395 U	0.000300 U	0.000395 U	0.000215 U	0.000328 U	0.000343 U	0.000331 U	0.000802 U
B-248	B-248-5	4/23/18	PES	ESC	5	46.9	V	–	–	–	–	0.000301 U	0.000326 U	0.000417 U	0.000316 U	0.000417 U	0.000227 U	0.000346 U	0.000362 U	0.000349 U	0.000846 U
	B-248-10	4/23/18	PES	ESC	10	41.9	V	–	–	–	–	0.000294 U	0.000319 U	0.000407 U	0.000309 U	0.000407 U	0.000222 U	0.000338 U	0.000353 U	0.000341 U	0.000826 U
	B-248-15	4/23/18	PES	ESC	15	36.9	V	–	–	–	–	0.000550 U	0.000302 U	0.000429 U	0.000971 U	0.000742 U	0.000632 U	0.000550 U	0.000770 U	0.000687 U	0.00561 U
	B-248-20	4/23/18	PES	ESC	20	31.9	S	–	–	–	–	0.000286 U	0.000309 U	0.000395 U	0.000300 U	0.000395 U	0.000215 U	0.000328 U	0.000343 U	0.000331 U	0.000801 U
	B-248-25	4/23/18	PES	ESC	25	26.9	S	–	–	–	–	0.000587 U	0.000323 U	0.000458 U	0.00104 U	0.000792 U	0.000675 U	0.000587 U	0.000821 U	0.000733 U	0.00598 U
	B-248-30	4/23/18	PES	ESC	30	21.9	S	–	–	–	–	0.000285 U	0.000309 U	0.000395 U	0.000299 U	0.000395 U	0.000215 U	0.000328 U	0.000343 U	0.000331 U	0.000801 U
	B-248-35	4/23/18	PES	ESC	35	16.9	S	–	–	–	–	0.000542 U	0.000298 U	0.000422 U	0.000957 U	0.000731 U	0.000623 U	**0.000611 J**	0.000758 U	0.000677 U	0.00552 U
	B-248-40	4/23/18	PES	ESC	40	11.9	S	–	–	–	–	0.000557 U	0.000307 U	0.000435 U	0.000985 U	0.000753 U	0.000641 U	0.000557 U	0.000780 U	0.000697 U	0.00569 U
	B-248-45	4/23/18	PES	ESC	45	6.9	S	–	–	–	–	0.000571 U	0.000314 U	0.000445 U	0.00101 U	0.000771 U	0.000657 U	0.000571 U	0.000799 U	0.000714 U	0.00582 U
	B-248-50	4/23/18	PES	ESC	50	1.9	S	–	–	–	–	0.000547 U	0.000301 U	0.000426 U	0.000965 U	0.000738 U	0.000629 U	0.000547 U	0.000765 U	0.000683 U	0.00558 U
	B-248-55	4/23/18	PES	ESC	55	-3.2	S	–	–	–	–	0.000312 U	0.000338 U	0.000432 U	0.000328 U	0.000432 U	0.000236 U	0.000359 U	0.000375 U	0.000362 U	0.000877 U
	B-248-60	4/23/18	PES	ESC	60	-8.2	S	–	–	–	–	0.000536 U	0.000295 U	0.000418 U	0.000946 U	0.000723 U	0.000616 U	**0.0149**	0.000750 U	0.000670 U	0.00547 U
	B-248-65	4/23/18	PES	ESC	65	-13.2	S	–	–	–	–	0.000615 U	0.000338 U	0.000480 U	0.00109 U	0.000830 U	0.000707 U	0.000615 U	0.000861 U	0.000769 U	0.00627 U
	B-248-70	4/23/18	PES	ESC	70	-18.2	S	–	–	–	–	0.000575 U	0.000316 U	0.000448 U	0.00101 U	0.000776 U	0.000661 U	0.000575 U	0.000804 U	0.000718 U	0.00586 U
	B-248-75	4/23/18	PES	ESC	75	-23.2	S	–	–	–	–	0.000562 U	0.000309 U	0.000438 U	0.000992 U	0.000758 U	0.000646 U	**0.00185 J**	0.000786 U	0.000702 U	0.00573 U
	B-248-80	4/23/18	PES	ESC	80	-28.2	S	–	–	–	–	0.000317 U	0.000344 U	0.000439 U	0.000333 U	0.000439 U	0.000239 U	0.000364 U	0.000381 U	0.000368 U	0.000890 U
	B-910-20	4/23/18	PES	ESC	80 (dup)	-28.2	S	–	–	–	–	0.000326 U	0.000353 U	0.000450 U	0.000342 U	0.000450 U	0.000246 U	0.000374 U	0.000391 U	0.000378 U	0.000914 U
	B-248-85	4/23/18	PES	ESC	85	-33.2	S	–	–	–	–	0.000321 U	0.000347 U	0.000443 U	0.000336 U	0.000443 U	0.000242 U	0.000368 U	0.000385 U	0.000372 U	0.000900 U
	B-248-90	4/23/18	PES	ESC	90	-38.2	S	–	–	–	–	0.000316 U	0.000342 U	0.000437 U	0.000331 U	0.000437 U	0.000238 U	0.000362 U	0.000379 U	0.000366 U	0.000886 U
	B-248-95	4/23/18	PES	ESC	95	-43.2	S	–	–	–	–	0.000329 U	0.000357 U	0.000455 U	0.000345 U	0.000455 U	0.000248 U	0.000378 U	0.000395 U	0.000382 U	0.000924 U
	B-248-100	4/23/18	PES	ESC	100	-48.2	S	–	–	–	–	0.000320 U	0.000347 U	0.000443 U	0.000336 U	0.000443 U	0.000241 U	0.000368 U	0.000385 U	0.000371 U	0.000899 U
	B-248-105	4/23/18	PES	ESC	105	-53.2	S	–	–	–	–	0.000285 U	0.000309 U	0.000394 U	0.000299 U	0.000394 U	0.000215 U	**0.00432**	0.000343 U	0.000331 U	0.000801 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
B-248	B-248-110	4/23/18	PES	ESC	110	-58.2	S	–	–	–	–	0.000574 U	0.000316 U	0.000448 U	0.00101 U	0.000775 U	0.000660 U	**0.00357**	0.000803 U	0.000717 U	0.00585 U
(continued)	B-248-115	4/23/18	PES	ESC	115	-63.2	S	–	–	–	–	0.000309 U	0.000334 U	0.000427 U	0.000324 U	0.000427 U	0.000233 U	**0.00156**	0.000371 U	0.000358 U	0.000866 U
B-249	B-249-5	10/15/18	PES	PACE	5	34.2	S	–	–	–	–	0.000523 U	0.000287 U	0.000408 U	0.000923 U	0.000705 U	0.000601 U	0.000523 U	0.000732 U	0.000653 U	0.00533 U
	B-249-8	10/15/18	PES	PACE	8	31.2	S	–	–	–	–	0.000564 U	0.000310 U	0.000440 U	0.000996 U	0.000762 U	0.000649 U	0.000564 U	0.000790 U	0.000705 U	0.00576 U
	B-249-15	10/15/18	PES	PACE	15	24.2	S	–	–	–	–	0.000579 U	0.000318 U	0.000452 U	0.00102 U	0.000782 U	0.000666 U	0.000579 U	0.000811 U	0.000724 U	0.00591 U
	B-249-17	10/15/18	PES	PACE	17	22.2	S	–	–	–	–	0.000566 U	0.000311 U	0.000442 U	0.00100 U	0.000764 U	0.000651 U	0.000566 U	0.000793 U	0.000708 U	0.00577 U
	B-249-20	10/15/18	PES	PACE	20	19.2	S	–	–	–	–	0.000591 U	0.000325 U	0.000461 U	0.00104 U	0.000798 U	0.000679 U	0.000591 U	0.000827 U	0.000738 U	0.00603 U
B-250	B-250-2.5	10/15/18	PES	PACE	2.5	36.9	V	–	–	–	–	0.000552 U	0.000304 U	0.000431 U	0.000975 U	0.000745 U	0.000635 U	0.000552 U	0.000773 U	0.000690 U	0.00563 U
	B-250-8	10/15/18	PES	PACE	8	31.4	S	–	–	–	–	0.000557 U	0.000306 U	0.000434 U	0.000983 U	0.000752 U	0.000640 U	0.000557 U	0.000779 U	0.000696 U	0.00568 U
	B-250-10	10/15/18	PES	PACE	10	29.4	S	–	–	–	–	0.000556 U	0.000306 U	0.000434 U	0.000982 U	0.000751 U	0.000640 U	0.000556 U	0.000779 U	0.000695 U	0.00567 U
	B-250-13	10/15/18	PES	PACE	13	26.4	S	–	–	–	–	0.000562 U	0.000309 U	0.000438 U	0.000992 U	0.000758 U	0.000646 U	0.000562 U	0.000786 U	0.000702 U	0.00573 U
	B-250-20	10/15/18	PES	PACE	20	19.4	S	–	–	–	–	0.000579 U	0.000319 U	0.000452 U	0.00102 U	0.000782 U	0.000666 U	**0.00138 J**	0.000811 U	0.000724 U	0.00591 U
	B-250-24	10/15/18	PES	PACE	24	15.4	S	–	–	–	–	0.000547 U	0.000301 U	0.000427 U	0.000966 U	0.000738 U	0.000629 U	**0.00105 J**	0.000766 U	0.000684 U	0.00558 U
	B-250-30	10/16/18	PES	PACE	30	9.4	S	–	–	–	–	0.000545 U	0.000300 U	0.000425 U	0.000963 U	0.000736 U	0.000627 U	0.000545 U	0.000763 U	0.000682 U	0.00556 U
B-251	B-251-5	10/15/18	PES	PACE	5	34.3	S	–	–	–	–	0.000525 U	0.000289 U	0.000410 U	0.000928 U	0.000709 U	0.000604 U	0.000525 U	0.000735 U	0.000657 U	0.00536 U
	B-251-8	10/15/18	PES	PACE	8	31.3	S	–	–	–	–	0.000555 U	0.000305 U	0.000433 U	**0.00157 J**	0.000749 U	0.000638 U	0.000555 U	0.000776 U	0.000693 U	0.00566 U
	B-251-10	10/15/18	PES	PACE	10	29.3	S	–	–	–	–	0.000556 U	0.000306 U	0.000434 U	0.0393 U	0.000751 U	0.000640 U	0.000556 U	0.000779 U	0.000695 U	0.00567 U
	B-251-15	10/15/18	PES	PACE	15	24.3	S	–	–	–	–	0.000565 U	0.000311 U	0.000441 U	0.0399 U	0.000763 U	0.000650 U	0.000565 U	0.000791 U	0.000707 U	0.00577 U
	B-251-20	10/15/18	PES	PACE	20	19.3	S	–	–	–	–	0.000586 U	0.000322 U	0.000457 U	0.0413 U	0.000790 U	0.000673 U	0.000586 U	0.000820 U	0.000732 U	0.00597 U
	B-251-25	10/15/18	PES	PACE	25	14.3	S	–	–	–	–	0.000574 U	0.000316 U	0.000448 U	0.00101 U	0.000775 U	0.000660 U	0.000574 U	0.000804 U	0.000718 U	0.00586 U
B-252	B-252-2.5	10/15/18	PES	PACE	2.5	36.7	V	–	–	–	–	0.000522 U	0.000287 U	0.000407 U	0.000923 U	0.000705 U	0.000601 U	0.000522 U	0.000731 U	0.000653 U	0.00533 U
	B-252-8	10/15/18	PES	PACE	8	31.2	S	–	–	–	–	0.000535 U	0.000294 U	0.000417 U	0.000945 U	0.000722 U	0.000615 U	0.000535 U	0.000749 U	0.000669 U	0.00546 U
	B-252-10	10/15/18	PES	PACE	10	29.2	S	–	–	–	–	0.000554 U	0.000305 U	0.000432 U	0.000979 U	0.000748 U	0.000638 U	0.000554 U	0.000776 U	0.000693 U	0.00565 U
	B-252-15	10/15/18	PES	PACE	15	24.2	S	–	–	–	–	0.000589 U	0.000324 U	0.000460 U	0.0209 U	0.000795 U	0.000677 U	0.000589 U	0.000825 U	0.000736 U	0.00601 U
	B-252-19	10/15/18	PES	PACE	19	20.2	S	–	–	–	–	0.000603 U	0.000332 U	0.000471 U	0.0107 U	0.000815 U	0.000694 U	**0.00476**	0.000845 U	0.000754 U	0.00616 U
	B-252-25	10/15/18	PES	PACE	25	14.2	S	–	–	–	–	0.000549 U	0.000302 U	0.000428 U	0.00388 U	0.000741 U	0.000632 U	0.000549 U	0.000769 U	0.000686 U	0.00560 U
	B-252-29	10/15/18	PES	PACE	29	10.2	S	–	–	–	–	0.000572 U	0.000315 U	0.000446 U	0.00101 U	0.000772 U	0.000658 U	**0.00436**	0.000801 U	0.000715 U	0.00584 U
B-253A	B-253A-5	10/18/18	PES	PACE	5	35.6	V	–	–	–	–	0.000569 U	0.000313 U	0.000444 U	0.00101 U	0.000769 U	0.000655 U	0.000569 U	0.000797 U	0.000712 U	0.00581 U
	B-253A-8	10/18/18	PES	PACE	8	32.6	S	–	–	–	–	0.000563 U	0.000310 U	0.000439 U	0.00398 U	0.000760 U	0.000648 U	0.000563 U	0.000788 U	0.000704 U	0.00574 U
	B-253A-10	10/18/18	PES	PACE	10	30.6	S	–	–	–	–	0.000548 U	0.000301 U	0.000427 U	0.00967 U	0.000739 U	0.000630 U	0.000548 U	0.000767 U	0.000685 U	0.00559 U
	B-253A-15	10/18/18	PES	PACE	15	25.6	S	–	–	–	–	0.000561 U	0.000309 U	0.000438 U	0.0793 U	0.000758 U	0.000646 U	0.000561 U	0.000786 U	0.000702 U	0.00573 U
	B-253A-20	10/18/18	PES	PACE	20	20.6	S	–	–	–	–	0.000551 U	0.000303 U	0.000430 U	0.00389 U	0.000743 U	0.000633 U	0.000551 U	0.000771 U	0.000688 U	0.00562 U
B-254	B-254-5	10/16/18	PES	PACE	5	34.7	S	–	–	–	–	0.000599 U	0.000329 U	0.0374 U	0.00106 U	0.0647 U	0.000689 U	0.000599 U	0.000838 U	0.0599 U	0.00611 U
	B-254-10	10/16/18	PES	PACE	10	29.7	S	–	–	–	–	0.000568 U	0.000312 U	0.00354 U	0.00100 U	0.00613 U	0.000653 U	0.000568 U	0.000795 U	0.00568 U	0.00579 U
	B-254-13.5	10/16/18	PES	PACE	13.5	26.2	S	–	–	–	–	0.000586 U	0.000322 U	0.183 U	0.00104 U	0.317 U	0.000674 U	0.000586 U	0.000821 U	0.293 U	0.00598 U
	B-254-20	10/16/18	PES	PACE	20	19.7	S	–	–	–	–	0.000538 U	0.000296 U	0.0839 U	0.000950 U	0.145 U	0.000619 U	0.000538 U	0.000753 U	0.134 U	0.00549 U
	B-254-25	10/16/18	PES	PACE	25	14.7	S	–	–	–	–	0.000559 U	0.000307 U	0.174 U	0.000987 U	0.302 U	0.000642 U	0.000559 U	0.000782 U	0.279 U	0.00570 U
B-254A	B-254A-27	10/19/18	PES	PACE	27	12.7	S	–	–	–	–	0.000546 U	0.000301 U	0.000426 U	0.000965 U	0.000737 U	0.000628 U	0.000546 U	0.000764 U	0.000682 U	0.00557 U
	B-254A-30	10/19/18	PES	PACE	30	9.7	S	–	–	–	–	0.000538 U	0.000296 U	0.000420 U	0.000950 U	0.000726 U	0.000619 U	0.000538 U	0.000753 U	0.000673 U	0.00549 U
	B-254A-35	10/19/18	PES	PACE	35	4.7	S	–	–	–	–	0.000527 U	0.000290 U	0.000411 U	0.000930 U	0.000711 U	0.000606 U	0.000527 U	0.000737 U	0.000658 U	0.00537 U
B-255	B-255-3.5	10/16/18	PES	PACE	3.5	36.3	S	–	–	–	–	0.000571 U	0.000314 U	0.000445 U	0.00101 U	0.000771 U	0.000657 U	0.000571 U	0.000799 U	0.000714 U	0.00582 U
	B-255-8	10/16/18	PES	PACE	8	31.8	S	–	–	–	–	0.000579 U	0.000319 U	0.000452 U	0.00102 U	0.000782 U	0.000666 U	0.000579 U	0.000811 U	0.000724 U	0.00591 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
B-255 (continued)	B-255-15	10/16/18	PES	PACE	15	24.8	S	–	–	–	–	0.000545 U	0.000300 U	0.000425 U	0.000962 U	0.000735 U	0.000627 U	0.000545 U	0.000763 U	0.000681 U	0.00556 U
B-255A	B-255A-21	10/16/18	PES	PACE	21	18.8	S	–	–	–	–	0.000529 U	0.000291 U	0.0165 U	0.000935 U	0.0286 U	0.000609 U	**0.00498**	0.000741 U	0.0265 U	0.00540 U
B-256	B-256-2.5	10/16/18	PES	PACE	2.5	37.1	S	–	–	–	–	0.000585 U	0.000322 U	0.000456 U	0.00103 U	0.000789 U	0.000672 U	0.000585 U	0.000819 U	0.000731 U	0.00596 U
	B-256-5	10/16/18	PES	PACE	5	34.6	S	–	–	–	–	0.000552 U	0.000304 U	0.000431 U	0.000975 U	0.000746 U	0.000635 U	0.000552 U	0.000773 U	0.000690 U	0.00563 U
	B-256-10	10/16/18	PES	PACE	10	29.6	S	–	–	–	–	0.000534 U	0.000294 U	0.000417 U	0.000944 U	0.000721 U	0.000614 U	**0.00420**	0.000748 U	0.000668 U	0.00545 U
	B-256-15	10/16/18	PES	PACE	15	24.6	S	–	–	–	–	0.000553 U	0.000304 U	0.000432 U	0.000977 U	0.000747 U	0.000636 U	**0.00114 J**	0.000775 U	0.000692 U	0.00564 U
	B-256-18	10/16/18	PES	PACE	18	21.6	S	–	–	–	–	0.000553 U	0.000304 U	0.000432 U	0.000977 U	0.000747 U	0.000636 U	**0.000814 J**	0.000775 U	0.000692 U	0.00564 U
B-257	B-257-5	10/17/18	PES	PACE	5	34.4	S	–	–	–	–	0.000605 U	0.000333 U	0.000472 U	0.00107 U	0.000817 U	0.000696 U	0.000605 U	0.000848 U	0.000757 U	0.00617 U
	B-257-10	10/17/18	PES	PACE	10	29.4	S	–	–	–	–	0.000558 U	0.000307 U	0.000435 U	0.000986 U	0.000754 U	0.000642 U	0.000558 U	0.000782 U	0.000698 U	0.00569 U
	B-257-15	10/17/18	PES	PACE	15	24.4	S	–	–	–	–	0.000581 U	0.000319 U	0.000453 U	0.00103 U	0.000784 U	0.000668 U	**0.000652 J**	0.000813 U	0.000726 U	0.00592 U
	B-257-20	10/17/18	PES	PACE	20	19.4	S	–	–	–	–	0.000562 U	0.000309 U	0.00351 U	0.000992 U	0.00607 U	0.000646 U	**0.00801**	0.000787 U	0.00562 U	0.00573 U
B-258	B-258-3	10/17/18	PES	PACE	3	36.2	V	–	–	–	–	0.000548 U	0.000301 U	0.000427 U	0.000968 U	0.000740 U	0.000630 U	0.000548 U	0.000767 U	0.000685 U	0.00559 U
	B-258-8	10/17/18	PES	PACE	8	31.2	S	–	–	–	–	0.000569 U	0.000313 U	0.000444 U	0.00100 U	0.000768 U	0.000654 U	0.000569 U	0.000796 U	0.000711 U	0.00580 U
	B-258-10	10/17/18	PES	PACE	10	29.2	S	–	–	–	–	0.000598 U	0.000329 U	0.000467 U	0.00106 U	0.000808 U	0.000688 U	0.000598 U	0.000838 U	0.000748 U	0.00610 U
	B-258-15	10/17/18	PES	PACE	15	24.2	S	–	–	–	–	0.000590 U	0.000325 U	**0.000480 J**	0.00104 U	0.000797 U	0.000679 U	**0.000600 J**	0.000826 U	0.000738 U	0.00602 U
	B-258-20	10/17/18	PES	PACE	20	19.2	S	–	–	–	–	0.000558 U	0.000307 U	0.000435 U	0.000986 U	0.000753 U	0.000642 U	0.000558 U	0.000781 U	0.000698 U	0.00569 U
B-259	B-259-2.5	10/17/18	PES	PACE	2.5	36.7	V	–	–	–	–	0.000563 U	0.000310 U	0.000439 U	**0.00199 J**	0.000760 U	0.000647 U	0.000563 U	0.000788 U	0.000703 U	0.00574 U
	B-259-5	10/17/18	PES	PACE	5	34.2	S	–	–	–	–	0.000548 U	0.000301 U	0.000427 U	0.000968 U	0.000740 U	0.000630 U	0.000548 U	0.000767 U	0.000685 U	0.00559 U
	B-259-10	10/17/18	PES	PACE	10	29.2	S	–	–	–	–	**0.000757 J**	0.000315 U	0.000447 U	0.00101 U	0.000773 U	0.000659 U	**0.000899 J**	0.000802 U	0.000716 U	0.00584 U
	B-259-15	10/17/18	PES	PACE	15	24.2	S	–	–	–	–	0.000587 U	0.000323 U	0.000458 U	0.00104 U	0.000792 U	0.000675 U	**0.00509**	0.000822 U	0.000734 U	0.00599 U
	B-259-20	10/17/18	PES	PACE	20	19.2	S	–	–	–	–	0.000559 U	0.000307 U	0.000436 U	0.000987 U	0.000754 U	0.000643 U	**0.00344**	0.000782 U	0.000699 U	0.00570 U
B-260	B-260-5	10/17/18	PES	PACE	5	34.2	S	–	–	–	–	0.000554 U	0.000305 U	0.000432 U	**0.00189 J**	0.000749 U	0.000638 U	0.000554 U	0.000776 U	0.000693 U	0.00566 U
	B-260-8	10/17/18	PES	PACE	8	31.2	S	–	–	–	–	**0.000647 J**	0.000309 U	0.000438 U	0.000991 U	0.000757 U	0.000645 U	**0.000732 J**	0.000786 U	0.000701 U	0.00572 U
	B-260-10	10/17/18	PES	PACE	10	29.2	S	–	–	–	–	**0.000624 J**	0.000316 U	0.000448 U	0.00101 U	0.000775 U	0.000660 U	**0.00166 J**	0.000803 U	0.000717 U	0.00585 U
	B-260-15	10/17/18	PES	PACE	15	24.2	S	–	–	–	–	0.000581 U	0.000319 U	0.000453 U	0.00103 U	0.000784 U	0.000668 U	**0.00427**	0.000813 U	0.000726 U	0.00592 U
	B-260-20	10/17/18	PES	PACE	20	19.2	S	–	–	–	–	**0.000619 J**	0.000304 U	0.000431 U	0.000976 U	0.000746 U	0.000635 U	**0.00252 J**	0.000774 U	0.000691 U	0.00564 U
B-261	B-261-3	10/17/18	PES	PACE	3	36.9	S	–	–	–	–	0.000571 U	0.000314 U	0.000446 U	0.00101 U	0.000771 U	0.000657 U	**0.000710 J**	0.000800 U	0.000714 U	0.00583 U
	B-261-5	10/17/18	PES	PACE	5	34.9	S	–	–	–	–	**0.000576 J**	0.000311 U	**0.000889 J**	0.00100 U	0.000764 U	0.000651 U	0.000566 U	0.000793 U	0.000708 U	0.00578 U
	B-261-8	10/17/18	PES	PACE	8	31.9	S	–	–	–	–	0.000599 U	0.000330 U	0.000467 U	0.00106 U	0.000809 U	0.000689 U	0.000599 U	0.000839 U	0.000749 U	0.00611 U
	B-261-10	10/17/18	PES	PACE	10	29.9	S	–	–	–	–	0.000576 U	0.000317 U	0.000449 U	0.00102 U	0.000778 U	0.000663 U	0.000576 U	0.000807 U	0.000720 U	0.00588 U
	B-261-15	10/17/18	PES	PACE	15	24.9	S	–	–	–	–	0.000549 U	0.000302 U	0.000429 U	0.000970 U	0.000742 U	0.000632 U	0.000549 U	0.000769 U	0.000687 U	0.00560 U
	B-261-20	10/17/18	PES	PACE	20	19.9	S	–	–	–	–	0.000562 U	0.000309 U	0.000438 U	0.000992 U	0.000759 U	0.000646 U	**0.00239 J**	0.000787 U	0.000702 U	0.00573 U
B-262	B-262-5	10/17/18	PES	PACE	5	34.9	S	–	–	–	–	0.000589 U	0.000324 U	0.0368 U	0.00104 U	0.000795 U	0.000677 U	0.000589 U	0.000825 U	0.0589 U	0.00601 U
	B-262-8	10/17/18	PES	PACE	8	31.9	S	–	–	–	–	0.000550 U	0.000302 U	0.000429 U	0.000971 U	0.000742 U	0.000632 U	0.000550 U	0.000770 U	0.000687 U	0.00561 U
	B-262-10	10/17/18	PES	PACE	10	29.9	S	–	–	–	–	0.000557 U	0.000306 U	0.000434 U	0.000983 U	0.000752 U	0.000640 U	0.000557 U	0.000780 U	0.000696 U	0.00568 U
	B-262-15	10/17/18	PES	PACE	15	24.9	S	–	–	–	–	0.000549 U	0.000302 U	0.000428 U	0.000969 U	0.000741 U	0.000631 U	0.000549 U	0.000768 U	0.000686 U	0.00560 U
	B-262-20	10/17/18	PES	PACE	20	19.9	S	–	–	–	–	0.000589 U	0.000324 U	0.00459 U	0.00104 U	0.000795 U	0.000677 U	0.000589 U	0.000824 U	0.00736 U	0.00600 U
B-263	B-263-3	10/18/18	PES	PACE	3	36.8	S	–	–	–	–	0.000612 U	0.000337 U	0.000478 U	0.00108 U	0.000827 U	0.000704 U	0.000612 U	0.000857 U	0.000765 U	0.00624 U
	B-263-5	10/18/18	PES	PACE	5	34.8	S	–	–	–	–	0.000540 U	0.000297 U	0.000421 U	0.000954 U	0.000729 U	0.000621 U	0.000540 U	0.000756 U	0.000675 U	0.00551 U
	B-263-8	10/18/18	PES	PACE	8	31.8	S	–	–	–	–	0.000527 U	0.000290 U	0.000411 U	0.000931 U	0.000712 U	0.000607 U	0.000527 U	0.000738 U	0.000659 U	0.00538 U
	B-263-10	10/18/18	PES	PACE	10	29.8	S	–	–	–	–	0.000569 U	0.000313 U	0.000444 U	0.00100 U	0.000768 U	0.000654 U	0.000569 U	0.000797 U	0.000711 U	0.00580 U
	B-263-15	10/18/18	PES	PACE	15	24.8	S	–	–	–	–	0.000546 U	0.000300 U	0.000426 U	0.000964 U	0.000737 U	0.000628 U	0.000546 U	0.000764 U	0.000682 U	0.00557 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
B-263 (continued)	B-263-18	10/18/18	PES	PACE	18	21.8	S	–	–	–	–	0.000542 U	0.000298 U	0.000423 U	0.000958 U	0.000732 U	0.000624 U	0.000542 U	0.000759 U	0.000678 U	0.00553 U
B-264	B-264-3	10/18/18	PES	PACE	3	36.8	S	–	–	–	–	0.000543 U	0.000299 U	0.000424 U	0.000959 U	0.000733 U	0.000624 U	0.000543 U	0.000760 U	0.000679 U	0.00554 U
	B-264-5	10/18/18	PES	PACE	5	34.8	S	–	–	–	–	0.000579 U	0.000318 U	0.000451 U	0.00102 U	0.000781 U	0.000665 U	0.000579 U	0.000810 U	0.000723 U	0.00590 U
	B-264-8	10/18/18	PES	PACE	8	31.8	S	–	–	–	–	0.000571 U	0.000314 U	0.000446 U	0.00101 U	0.000771 U	0.000657 U	0.000571 U	0.000800 U	0.000714 U	0.00583 U
	B-264-10	10/18/18	PES	PACE	10	29.8	S	–	–	–	–	0.000551 U	0.000303 U	0.000430 U	0.000973 U	0.000744 U	0.000633 U	0.000551 U	0.000771 U	0.000689 U	0.00562 U
	B-264-15	10/18/18	PES	PACE	15	24.8	S	–	–	–	–	0.000582 U	0.000320 U	0.000454 U	0.00103 U	0.000785 U	0.000669 U	0.000582 U	0.000814 U	0.000727 U	0.00593 U
	B-264-16	10/18/18	PES	PACE	16	23.8	S	–	–	–	–	0.000561 U	0.000309 U	0.000438 U	0.000991 U	0.000758 U	0.000645 U	0.000561 U	0.000786 U	0.000702 U	0.00573 U
B-265	B-265-3	10/18/18	PES	PACE	3	36.8	S	–	–	–	–	0.000597 U	0.000328 U	0.000465 U	0.00105 U	0.000806 U	0.000686 U	0.000597 U	0.000835 U	0.000746 U	0.00609 U
	B-265-5	10/18/18	PES	PACE	5	34.8	S	–	–	–	–	0.000579 U	0.000319 U	0.000452 U	0.0102 U	0.000782 U	0.000666 U	0.000579 U	0.000811 U	0.000724 U	0.00591 U
	B-265-8	10/18/18	PES	PACE	8	31.8	S	–	–	–	–	0.000558 U	0.000307 U	0.000435 U	0.00986 U	0.000754 U	0.000642 U	0.000558 U	0.000781 U	0.000698 U	0.00569 U
	B-265-10	10/18/18	PES	PACE	10	29.8	S	–	–	–	–	0.000550 U	0.000302 U	0.000429 U	0.00776 U	0.000742 U	0.000632 U	0.000550 U	0.000770 U	0.000687 U	0.00561 U
	B-265-17.5	10/18/18	PES	PACE	18	22.3	S	–	–	–	–	0.000553 U	0.000304 U	0.000431 U	0.000977 U	0.000747 U	0.000636 U	0.000553 U	0.000774 U	0.000691 U	0.00564 U
B-266	B-266-5	10/18/18	PES	PACE	5	35.7	S	–	–	–	–	0.000609 U	0.000335 U	0.000475 U	0.00108 U	0.000823 U	0.000701 U	0.000609 U	0.000853 U	0.000762 U	0.00621 U
	B-266-8	10/18/18	PES	PACE	8	32.7	S	–	–	–	–	0.000636 U	0.000350 U	0.000496 U	0.00111 U	0.000859 U	0.000732 U	0.000636 U	0.000891 U	0.000795 U	0.00649 U
	B-266-10	10/18/18	PES	PACE	10	30.7	S	–	–	–	–	0.000805 U	0.000443 U	0.000628 U	0.00142 U	0.00109 U	0.000926 U	0.000805 U	0.00113 U	0.00101 U	0.00821 U
	B-266-15	10/18/18	PES	PACE	15	25.7	S	–	–	–	–	0.000667 U	0.000367 U	0.000520 U	0.0117 U	0.000900 U	0.000767 U	0.000667 U	0.000934 U	0.000834 U	0.00681 U
	B-266-20	10/18/18	PES	PACE	20	20.7	S	–	–	–	–	0.000557 U	0.000307 U	0.000435 U	0.0393 U	0.000752 U	0.000641 U	0.000557 U	0.000780 U	0.000697 U	0.00568 U
B-267	B-267-2.5	10/18/18	PES	PACE	2.5	37.4	S	–	–	–	–	0.000601 U	0.000331 U	0.000469 U	0.00106 U	0.000811 U	0.000691 U	0.000601 U	0.000841 U	0.000751 U	0.00613 U
	B-267-5	10/18/18	PES	PACE	5	34.9	S	–	–	–	–	0.000545 U	0.000300 U	0.000425 U	0.000963 U	0.000736 U	0.000627 U	0.000545 U	0.000764 U	0.000682 U	0.00556 U
	B-267-8	10/18/18	PES	PACE	8	31.9	S	–	–	–	–	0.000597 U	0.000328 U	0.000465 U	0.00421 U	0.000805 U	0.000686 U	0.000597 U	0.000835 U	0.000746 U	0.00608 U
	B-267-10	10/18/18	PES	PACE	10	29.9	S	–	–	–	–	0.000565 U	0.000311 U	0.000441 U	0.00399 U	0.000763 U	0.000650 U	0.000565 U	0.000791 U	0.000706 U	0.00576 U
	B-267-15	10/18/18	PES	PACE	15	24.9	S	–	–	–	–	0.0112 U	0.00615 U	0.00872 U	0.0198 U	0.0151 U	0.0129 U	0.0112 U	0.0156 U	0.0140 U	0.114 U
	B-267-20	10/18/18	PES	PACE	20	19.9	S	–	–	–	–	0.0124 U	0.00684 U	0.00969 U	0.0219 U	0.0168 U	0.0142 U	0.0124 U	0.0174 U	0.0155 U	0.127 U
CA-A10	CA-A10-21	09/04/19	PES	Fremont	21	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-A12-20	CA-A12-20-24	09/06/19	PES	Fremont	24	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
CAA-C1	CAA-C1-43	08/27/19	PES	Fremont	43	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
CAA-C2	CAA-C2-10	08/28/19	PES	Fremont	10	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-B8	CA-B8-3	09/16/19	PES	Fremont	3	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-B19	CA-B19-30	09/27/19	PES	Fremont	30	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-B10	CA-B10-17	08/30/19	PES	Fremont	17	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	CA-B10-20	08/30/19	PES	Fremont	20	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	CA-B10-21	08/30/19	PES	Fremont	21	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	CA-B10-25	08/30/19	PES	Fremont	25	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-B11	CA-B11-27	09/05/19	PES	Fremont	27	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-B18	CA-B18-20	10/26/19	PES	Fremont	20	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-B20	CA-B20-31	09/30/19	PES	Fremont	31	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B-1001-31	09/30/19	PES	Fremont	31 (dup)	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-C7	CA-C7-25	09/20/19	PES	Fremont	25	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-C8	CA-C8-35	09/03/19	PES	Fremont	35	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-C9	CA-C9-09	09/04/19	PES	Fremont	9	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-C10	CA-C10-17	09/06/19	PES	Fremont	17	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	CA-C10-26	09/06/19	PES	Fremont	26	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-C13	CA-C13-Comp	09/11/19	PES	Fremont	Comp	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-D1	CA-D1-Comp	09/11/19	PES	Fremont	Comp	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-D2	CA-D2-31	09/16/19	PES	Fremont	31	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	CA-D2-50-52	09/17/19	PES	Fremont	52	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-D3	CA-D3-40	09/23/19	PES	Fremont	40	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-D4	CA-D4-51	09/19/19	PES	Fremont	51	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	CA-D4-54	09/19/19	PES	Fremont	54	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	**–**	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	**–**	**0.030**	**1.5E-07**
CA-D5	CA-D5-14	09/03/19	PES	Fremont	14	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	CA-D5-22	09/03/19	PES	Fremont	22	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	CA-D5-26	09/03/19	PES	Fremont	26	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-D6	CA-D6-56	09/04/19	PES	Fremont	56	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	CA-D6-65	09/04/19	PES	Fremont	65	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-D7	CA-D7-15	09/05/19	PES	Fremont	15	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
DB01	DB01-10	3/18/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB01-20	3/18/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB01-30	3/18/13	SES	F&BI	30	10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB01-40	3/18/13	SES	F&BI	40	0.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
DB02	DB02-10	3/18/13	SES	F&BI	10	26.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB02-15	3/18/13	SES	F&BI	15	21.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB02-20	3/18/13	SES	F&BI	20	16.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB02-30	3/18/13	SES	F&BI	30	6.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB02-40	3/18/13	SES	F&BI	40	-4.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
DB03	DB03-05	3/27/13	SES	F&BI	5	35.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB03-20	3/27/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB03-35	3/27/13	SES	F&BI	35	5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB03-45	3/27/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB03-55	3/27/13	SES	F&BI	55	-15.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB03-60	3/27/13	SES	F&BI	60	-20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
DB04	DB04-10	3/21/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB04-20	3/21/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB04-35	3/21/13	SES	F&BI	35	5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB04-45	3/21/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB04-50	3/22/13	SES	F&BI	50	-10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB04-60	3/22/13	SES	F&BI	60	-20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
DB05	DB05-10	3/26/13	SES	F&BI	10	41.8	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB05-20	3/26/13	SES	F&BI	20	31.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB05-30	3/26/13	SES	F&BI	30	21.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB05-40	3/26/13	SES	F&BI	40	11.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB05-50	3/26/13	SES	F&BI	50	1.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB05-60	3/26/13	SES	F&BI	60	-8.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB05-70	3/26/13	SES	F&BI	70	-18.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
DB06	DB06-10	3/25/13	SES	F&BI	10	41.8	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB06-25	3/25/13	SES	F&BI	25	26.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB06-35	3/25/13	SES	F&BI	35	16.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB06-45	3/25/13	SES	F&BI	45	6.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB06-55	3/25/13	SES	F&BI	55	-3.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB06-65	3/25/13	SES	F&BI	65	-13.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB06-75	3/25/13	SES	F&BI	75	-23.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
DB07	DB07-05	3/27/13	SES	F&BI	5	35.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB07-15	3/27/13	SES	F&BI	15	25.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB07-25	3/27/13	SES	F&BI	25	15.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB07-35	3/28/13	SES	F&BI	35	5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB07-45	3/28/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB07-50	3/28/13	SES	F&BI	50	-10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB07-60	3/28/13	SES	F&BI	60	-20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB07-70	3/28/13	SES	F&BI	70	-30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
DB08	DB08-10	3/20/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB08-20	3/20/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB08-35	3/20/13	SES	F&BI	35	5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB08-45	3/20/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB08-50	3/21/13	SES	F&BI	50	-10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB08-60	3/21/13	SES	F&BI	60	-20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB08-70	3/21/13	SES	F&BI	70	-30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
DB09	DB09-10	3/19/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB09-20	3/19/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB09-30	3/19/13	SES	F&BI	30	10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB09-40	3/19/13	SES	F&BI	40	0.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB09-50	3/19/13	SES	F&BI	50	-10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB09-60	3/19/13	SES	F&BI	60	-20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB09-70	3/19/13	SES	F&BI	70	-30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
DB10	DB10-10	3/29/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB10-20	3/29/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB10-35	3/29/13	SES	F&BI	35	5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB10-45	3/29/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB10-50	4/1/13	SES	F&BI	50	-10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB10-60	4/1/13	SES	F&BI	60	-20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB10-70	4/1/13	SES	F&BI	70	-30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
DB11	DB11-15	4/2/13	SES	F&BI	15	36.8	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB11-25	4/2/13	SES	F&BI	25	26.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB11-35	4/2/13	SES	F&BI	35	16.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB11-45	4/2/13	SES	F&BI	45	6.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB11-55	4/2/13	SES	F&BI	55	-3.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
DB12	DB12-10	4/3/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB12-20	4/3/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB12-30	4/3/13	SES	F&BI	30	10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB12-40	4/3/13	SES	F&BI	40	0.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
DB13	DB13-10	4/3/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB13-20	4/3/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB13-35	4/3/13	SES	F&BI	35	5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB13-45	4/3/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	**–**	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	**–**	**0.030**	**1.5E-07**
DB14	DB14-10	4/4/13	SES	F&BI	10	31.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB14-20	4/4/13	SES	F&BI	20	21.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB14-30	4/4/13	SES	F&BI	30	11.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB14-40	4/4/13	SES	F&BI	40	1.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
G-MW1	MW 1-3-8	7/20/01	GeoEng	NCA	8	31.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW 1-8-20	7/20/01	GeoEng	NCA	20	19.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW 1-11-27.5	7/20/01	GeoEng	NCA	27.5	11.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW 1-13-32.5	7/20/01	GeoEng	NCA	32.5	6.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW 1-15-37.5	7/20/01	GeoEng	NCA	37.5	1.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
G-MW3 (G-SB4 11)	SB4-4-10	7/20/01	GeoEng	NCA	10	29.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB4-7-17.5	7/20/01	GeoEng	NCA	17.5	22.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB4-13-32.5	7/20/01	GeoEng	NCA	32.5	7.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB4-15-37.5	7/20/01	GeoEng	NCA	37.5	2.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
IW06	IW06-25	1/15/16	SES	F&BI	25	26.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-30	1/15/16	SES	F&BI	30	21.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-40	1/15/16	SES	F&BI	40	11.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-50	1/15/16	SES	F&BI	50	1.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-55	1/15/16	SES	F&BI	55	-3.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-60	1/15/16	SES	F&BI	60	-8.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-65	1/15/16	SES	F&BI	65	-13.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-70	1/15/16	SES	F&BI	70	-18.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-75	1/15/16	SES	F&BI	75	-23.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
IW-1C	IW-1C-5	3/7/18	PES	ESC	5	34.1	S	–	–	–	–	0.000293 U	0.000318 U	0.000406 U	0.000308 U	0.000406 U	0.000221 U	0.000337 U	0.000352 U	0.000340 U	0.000823 U
(-23.9 to-38.9)	IW-1C-15	3/7/18	PES	ESC	15	24.1	S	–	–	–	–	0.000310 U	0.000336 U	0.000429 U	0.000325 U	0.000429 U	0.000234 U	0.000356 U	0.000372 U	0.000359 U	0.000870 U
	IW-1C-25	3/7/18	PES	ESC	25	14.1	S	–	–	–	–	0.0627 U	0.0679 U	0.0867 U	0.0658 U	0.0867 U	0.0473 U	0.0720 U	0.0753 U	0.0727 U	0.176 U
	IW-1C-35	3/7/18	PES	ESC	35	4.1	S	–	–	–	–	0.000283 U	0.000307 U	0.000391 U	0.000297 U	0.000391 U	0.000213 U	**0.00552**	0.000340 U	0.000328 U	0.000795 U
	IW-1C-45	3/7/18	PES	ESC	45	-5.9	S	–	–	–	–	0.000296 U	0.000320 U	0.000409 U	0.000310 U	0.000409 U	0.000223 U	**0.000891 J**	0.000355 U	0.000343 U	0.000829 U
	IW-1C-55	3/7/18	PES	ESC	55	-15.9	S	–	–	–	–	0.000296 U	0.000320 U	0.000409 U	0.000310 U	0.000409 U	0.000223 U	**0.00116**	0.000355 U	0.000343 U	0.000830 U
	IW-1C-65	3/7/18	PES	ESC	65	-25.9	S	–	–	–	–	0.000303 U	0.000329 U	0.000419 U	0.000318 U	0.000419 U	0.000229 U	0.000348 U	0.000364 U	0.000352 U	0.000852 U
	IW-1C-75	3/7/18	PES	ESC	75	-35.9	S	–	–	–	–	0.000318 U	0.000344 U	0.000439 U	0.000333 U	0.000439 U	0.000239 U	0.000364 U	0.000381 U	0.000368 U	0.000891 U
IW-2C	IW-2C-5	3/7/18	PES	ESC	5	31.3	S	–	–	–	–	0.000326 U	0.000353 U	0.000451 U	0.000342 U	0.000451 U	0.000246 U	0.000374 U	0.000392 U	0.000378 U	0.000915 U
(-24.8 to-39.8)	IW-2C-15	3/7/18	PES	ESC	15	21.3	S	–	–	–	–	0.000315 U	0.000342 U	0.000436 U	0.000331 U	0.000436 U	0.000238 U	0.000362 U	0.000379 U	0.000366 U	0.000885 U
	IW-2C-25	3/7/18	PES	ESC	25	11.3	S	–	–	–	–	0.000295 U	0.000319 U	0.000408 U	0.000309 U	0.000408 U	0.000222 U	**0.000722 J**	0.000354 U	0.000342 U	0.000828 U
	IW-2C-35	3/7/18	PES	ESC	35	1.3	S	–	–	–	–	0.000333 U	0.000360 U	0.000460 U	0.000349 U	0.000460 U	0.000251 U	0.000382 U	0.000399 U	0.000385 U	0.000933 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
IW-2C (continued)	IW-2C-45	3/7/18	PES	ESC	45	-8.7	S	–	–	–	–	0.000286 U	0.000310 U	0.000396 U	0.000300 U	0.000396 U	0.000216 U	**0.00255**	0.000344 U	0.000332 U	0.000804 U
	IW-2C-55	3/7/18	PES	ESC	55	-18.7	S	–	–	–	–	0.000308 U	0.000333 U	0.000425 U	0.000323 U	0.000425 U	0.000232 U	0.000353 U	0.000369 U	0.000356 U	0.000863 U
	IW-2C-65	3/7/18	PES	ESC	65	-28.7	S	–	–	–	–	0.000289 U	0.000313 U	0.000399 U	0.000303 U	0.000399 U	0.000218 U	0.000331 U	0.000347 U	0.000335 U	0.000810 U
	IW-2C-75	3/7/18	PES	ESC	75	-38.7	S	–	–	–	–	0.000317 U	0.000344 U	0.000438 U	0.000333 U	0.000438 U	0.000239 U	0.000364 U	0.000381 U	0.000368 U	0.000890 U
IW-3C (-24.9 to-39.9)	IW-3C-5	3/9/18	PES	ESC	5	34.1	S	–	–	–	–	0.000289 U	0.000313 U	0.000399 U	0.000303 U	0.000399 U	0.000218 U	0.000331 U	0.000347 U	0.000335 U	0.000810 U
	IW-3C-15	3/9/18	PES	ESC	15	24.1	S	–	–	–	–	0.00765 U	0.00829 U	0.0106 U	0.00802 U	0.0106 U	0.00577 U	0.00878 U	0.00918 U	0.00887 U	0.0214 U
	IW-3C-25	3/9/18	PES	ESC	25	14.1	S	–	–	–	–	0.156 U	0.169 U	0.215 U	0.163 U	0.215 U	0.117 U	0.179 U	0.187 U	0.181 U	0.437 U
	IW-3C-35	3/9/18	PES	ESC	35	4.1	S	–	–	–	–	0.0587 U	0.0636 U	0.0811 U	0.0616 U	0.0811 U	0.0442 U	0.0673 U	0.0705 U	0.0680 U	0.164 U
	IW-3C-45	3/9/18	PES	ESC	45	-5.9	S	–	–	–	–	0.000304 U	0.000330 U	0.000421 U	0.000319 U	0.000421 U	0.000229 U	**0.000840 J**	0.000365 U	0.000353 U	0.000854 U
	IW-3C-55	3/9/18	PES	ESC	55	-15.9	S	–	–	–	–	0.000300 U	0.000325 U	0.000414 U	0.000314 U	0.000414 U	0.000226 U	0.000344 U	0.000360 U	0.000347 U	0.000841 U
	IW-3C-65	3/9/18	PES	ESC	65	-25.9	S	–	–	–	–	0.000301 U	0.000326 U	0.000416 U	0.000316 U	0.000416 U	0.000227 U	0.000346 U	0.000362 U	0.000349 U	0.000845 U
	IW-3C-75	3/9/18	PES	ESC	75	-35.9	S	–	–	–	–	0.000331 U	0.000358 U	0.000457 U	0.000347 U	0.000457 U	0.000249 U	0.000379 U	0.000397 U	0.000383 U	0.000928 U
	IW-3C-79	3/9/18	PES	ESC	79	-39.9	S	–	–	–	–	0.000307 U	0.000332 U	0.000424 U	0.000322 U	0.000424 U	0.000231 U	0.000352 U	0.000368 U	0.000355 U	0.000861 U
	IW-901-79	3/9/18	PES	ESC	79 (dup)	-39.9	S	–	–	–	–	0.000305 U	0.000331 U	0.000422 U	0.000320 U	0.000422 U	0.000230 U	0.000351 U	0.000367 U	0.000354 U	0.000857 U
IW-7A (5.1 to-9.9)	IW-7A-5	3/16/18	PES	ESC	5	35.1	S	**0.799**	–	–	–	0.000327 U	0.000354 U	0.000452 U	0.000343 U	0.000452 U	0.000247 U	0.000375 U	0.000393 U	0.000379 U	0.000918 U
	IW-7A-10	3/16/18	PES	ESC	10	30.1	S	**253**	–	–	–	0.000862 U	0.00112 U	0.00101 U	0.000746 U	0.000753 U	0.00105 U	0.00120 U	0.000917 U	0.00197 U	0.00339 U
	IW-7A-15	3/16/18	PES	ESC	15	25.1	S	**108**	–	–	–	0.0106 U	0.0115 U	0.0147 U	0.0111 U	0.0147 U	0.00801 U	0.0122 U	0.0127 U	0.0123 U	0.0297 U
	IW-7A-20	3/16/18	PES	ESC	20	20.1	S	**18.7**	–	–	–	0.000885 U	0.00114 U	0.00103 U	0.000765 U	0.000772 U	0.00108 U	0.00124 U	0.000941 U	0.00202 U	0.00348 U
	IW-7A-25	3/16/18	PES	ESC	25	15.1	S	**2.82**	–	–	–	0.000320 U	0.000346 U	0.000442 U	0.000336 U	0.000442 U	0.000241 U	0.000367 U	0.000384 U	0.000371 U	0.000898 U
	IW-7A-30	3/16/18	PES	ESC	30	10.1	S	**0.287**	–	–	–	0.000306 U	0.000332 U	0.000424 U	0.000321 U	0.000424 U	0.000231 U	0.000352 U	0.000368 U	0.000355 U	0.000860 U
	IW-7A-35	3/16/18	PES	ESC	35	5.1	S	**6.38**	–	–	–	0.000758 U	0.000981 U	0.000884 U	0.000656 U	0.000662 U	0.000927 U	0.00106 U	0.000806 U	0.00173 U	0.00298 U
	IW-7A-40	3/16/18	PES	ESC	40	0.1	S	**0.296**	–	–	–	0.000311 U	0.000337 U	0.000430 U	0.000326 U	0.000430 U	0.000234 U	0.000357 U	0.000373 U	0.000360 U	0.000873 U
	IW-7A-45	3/16/18	PES	ESC	45	-4.9	S	**0.282**	–	–	–	0.000309 U	0.000334 U	**0.000611 J**	0.000324 U	0.000427 U	0.000233 U	0.000354 U	0.000371 U	0.000358 U	0.000866 U
	IW-7A-50	3/16/18	PES	ESC	50	-9.9	S	**0.483**	–	–	–	0.000293 U	0.000318 U	0.000405 U	0.000308 U	0.000405 U	0.000221 U	**0.000677 J**	0.000352 U	0.000340 U	0.000823 U
IW-8B (-9.8 to-24.8)	IW-8B-5	3/19/18	PES	ESC	5	34.2	S	–	–	–	–	0.000289 U	0.000313 U	0.000400 U	0.000303 U	0.000400 U	0.000218 U	0.000332 U	0.000347 U	0.000335 U	0.000811 U
	IW-8B-10	3/19/18	PES	ESC	10	29.2	S	–	–	–	–	0.000285 U	0.000308 U	0.000393 U	0.000299 U	0.000393 U	0.000215 U	0.000327 U	0.000342 U	0.000330 U	0.000799 U
	IW-8B-15	3/19/18	PES	ESC	15	24.2	S	–	–	–	–	0.0760 U	0.0823 U	0.105 U	0.0796 U	0.105 U	0.0573 U	0.0872 U	0.0911 U	0.0880 U	0.213 U
	IW-8B-20	3/19/18	PES	ESC	20	19.2	S	–	–	–	–	0.000290 U	0.000314 U	0.000401 U	0.000304 U	0.000401 U	0.000218 U	**0.000478 J**	0.000348 U	0.000336 U	0.000813 U
	IW-8B-25	3/19/18	PES	ESC	25	14.2	S	–	–	–	–	0.000309 U	0.000335 U	0.000427 U	0.000324 U	0.000427 U	0.000233 U	**0.00248**	0.000371 U	0.000358 U	0.000867 U
	IW-8B-30	3/19/18	PES	ESC	30	9.2	S	–	–	–	–	0.000297 U	0.000321 U	0.000410 U	0.000311 U	0.000410 U	0.000224 U	**0.000605 J**	0.000356 U	0.000344 U	0.000833 U
	IW-8B-40	3/19/18	PES	ESC	40	-0.8	S	–	–	–	–	0.000294 U	0.000319 U	0.000407 U	0.000309 U	0.000407 U	0.000222 U	0.000338 U	0.000354 U	0.000341 U	0.000827 U
	IW-8B-45	3/20/18	PES	ESC	45	-5.8	S	–	–	–	–	0.000294 U	0.000319 U	0.000407 U	0.000309 U	0.000407 U	0.000222 U	0.000338 U	0.000353 U	0.000341 U	0.000826 U
	IW-8B-50	3/20/18	PES	ESC	50	-10.8	S	–	–	–	–	0.000302 U	0.000327 U	0.000417 U	0.000317 U	0.000417 U	0.000228 U	0.000347 U	0.000363 U	0.000350 U	0.000848 U
	IW-8B-55	3/20/18	PES	ESC	55	-15.8	S	–	–	–	–	0.000285 U	0.000309 U	0.000394 U	0.000299 U	0.000394 U	0.000215 U	0.000327 U	0.000342 U	0.000330 U	0.000800 U
	IW-8B-60	3/20/18	PES	ESC	60	-20.8	S	–	–	–	–	0.000302 U	0.000328 U	0.000418 U	0.000317 U	0.000418 U	0.000228 U	0.000347 U	0.000363 U	0.000350 U	0.000849 U
	IW-8B-64	3/20/18	PES	ESC	64	-24.8	S	–	–	–	–	0.000298 U	0.000322 U	0.000412 U	0.000312 U	0.000412 U	0.000224 U	0.000342 U	0.000357 U	0.000345 U	0.000835 U
IW-8C (-24.5 to-39.5)	IW-8C-5	3/14/18	PES	ESC	5	32.5	S	–	–	–	–	0.000453 U	0.000491 U	0.000627 U	0.000475 U	0.000627 U	0.000342 U	0.000520 U	0.000544 U	0.000525 U	0.00127 U
	IW-8C-10	3/14/18	PES	ESC	10	27.5	S	–	–	–	–	0.000457 U	0.000495 U	0.000631 U	0.000479 U	0.000631 U	0.000344 U	0.000524 U	0.000548 U	0.000529 U	0.00128 U
	IW-8C-15	3/14/18	PES	ESC	15	22.5	S	–	–	–	–	0.000311 U	0.000337 U	0.000430 U	0.000327 U	0.000430 U	0.000235 U	0.000357 U	0.000374 U	0.000360 U	0.000873 U
	IW-8C-20	3/14/18	PES	ESC	20	17.5	S	–	–	–	–	0.000285 U	0.000308 U	0.000394 U	0.000299 U	0.000394 U	0.000215 U	0.000327 U	0.000342 U	0.000330 U	0.000799 U
	IW-8C-25	3/14/18	PES	ESC	25	12.5	S	–	–	–	–	0.000314 U	0.000340 U	0.000435 U	0.000330 U	0.000435 U	0.000237 U	**0.00196**	0.000377 U	0.000364 U	0.000882 U
	IW-8C-30	3/14/18	PES	ESC	30	7.5	S	–	–	–	–	0.000292 U	0.000316 U	0.000404 U	0.000306 U	0.000404 U	0.000220 U	**0.00182**	0.000351 U	0.000339 U	0.000820 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
IW-8C	IW-8C-35	3/14/18	PES	ESC	35	2.5	S	–	–	–	–	0.000305 U	0.000331 U	0.000422 U	0.000320 U	0.000422 U	0.000230 U	**0.000599 J**	0.000367 U	0.000354 U	0.000857 U
(continued)	IW-8C-40	3/14/18	PES	ESC	40	-2.5	S	–	–	–	–	0.000304 U	0.000329 U	0.000420 U	0.000319 U	0.000420 U	0.000229 U	**0.00278**	0.000365 U	0.000352 U	0.000853 U
	IW-8C-45	3/14/18	PES	ESC	45	-7.5	S	–	–	–	–	0.000298 U	0.000323 U	0.000412 U	0.000312 U	0.000412 U	0.000224 U	**0.00838**	0.000358 U	0.000345 U	0.000836 U
	IW-8C-50	3/14/18	PES	ESC	50	-12.5	S	–	–	–	–	0.000310 U	0.000336 U	0.000429 U	0.000325 U	0.000429 U	0.000234 U	**0.0162**	0.000372 U	0.000360 U	0.000871 U
	IW-8C-55	3/14/18	PES	ESC	55	-17.5	S	–	–	–	–	0.000305 U	0.000330 U	0.000421 U	0.000320 U	0.000421 U	0.000230 U	**0.0141**	0.000366 U	0.000353 U	0.000855 U
	IW-8C-60	3/14/18	PES	ESC	60	-22.5	S	–	–	–	–	0.000302 U	0.000327 U	0.000417 U	0.000317 U	0.000417 U	0.000227 U	**0.00152**	0.000362 U	0.000350 U	0.000847 U
	IW-902-60	3/14/18	PES	ESC	60 (dup)	-22.5	S	–	–	–	–	0.000293 U	0.000317 U	0.000405 U	0.000307 U	0.000405 U	0.000221 U	**0.000495 J**	0.000352 U	0.000340 U	0.000822 U
	IW-8C-65	3/14/18	PES	ESC	65	-27.5	S	–	–	–	–	0.000317 U	0.000343 U	0.000438 U	0.000332 U	0.000438 U	0.000239 U	0.000363 U	0.000380 U	0.000367 U	0.000889 U
	IW-8C-70	3/14/18	PES	ESC	70	-32.5	S	–	–	–	–	0.000313 U	0.000339 U	0.000433 U	0.000329 U	0.000433 U	0.000236 U	0.000360 U	0.000376 U	0.000363 U	0.000880 U
	IW-8C-75	3/14/18	PES	ESC	75	-37.5	S	–	–	–	–	0.000296 U	0.000320 U	0.000409 U	0.000310 U	0.000409 U	0.000223 U	0.000339 U	0.000355 U	0.000343 U	0.000829 U
IW-11D	IW-11D-10	4/19/18	PES	ESC	10	28.4	S	–	–	–	–	0.000364 U	0.000395 U	0.000504 U	0.000382 U	0.000504 U	0.000275 U	0.000418 U	0.000438 U	0.000422 U	0.00102 U
(-41.8 to-56.8)	IW-11D-15	4/19/18	PES	ESC	15	23.4	S	–	–	–	–	0.000306 U	0.000331 U	0.000423 U	0.000321 U	0.000423 U	0.000231 U	0.000351 U	0.000367 U	0.000355 U	0.000859 U
	IW-11D-20	4/19/18	PES	ESC	20	18.4	S	–	–	–	–	0.000305 U	0.000331 U	0.000422 U	0.000320 U	0.000422 U	0.000230 U	0.000350 U	0.000367 U	0.000354 U	0.000857 U
	IW-11D-25	4/19/18	PES	ESC	25	13.4	S	–	–	–	–	0.000288 U	0.000313 U	0.000399 U	0.000303 U	0.000399 U	0.000217 U	0.000331 U	0.000346 U	0.000334 U	0.000810 U
	IW-11D-30	4/19/18	PES	ESC	30	8.4	S	–	–	–	–	0.000289 U	0.000313 U	0.000399 U	0.000303 U	0.000399 U	0.000218 U	0.000331 U	0.000347 U	0.000335 U	0.000810 U
	IW-11D-35	4/19/18	PES	ESC	35	3.4	S	–	–	–	–	0.000302 U	0.000328 U	0.000418 U	0.000317 U	0.000418 U	0.000228 U	**0.000721 J**	0.000363 U	0.000351 U	0.000849 U
	IW-11D-40	4/19/18	PES	ESC	40	-1.6	S	–	–	–	–	0.000292 U	0.000316 U	0.000403 U	0.000306 U	0.000403 U	0.000220 U	**0.00224**	0.000350 U	0.000338 U	0.000819 U
	IW-11D-45	4/19/18	PES	ESC	45	-6.6	S	–	–	–	–	0.00743 U	0.00805 U	0.0103 U	0.00779 U	0.0103 U	0.00561 U	0.00853 U	0.00892 U	0.00861 U	0.0208 U
	IW-11D-50	4/19/18	PES	ESC	50	-11.6	S	–	–	–	–	0.000283 U	0.000307 U	0.000392 U	0.000297 U	0.000392 U	0.000214 U	**0.00390**	0.000340 U	0.000329 U	0.000796 U
	IW-11D-55	4/19/18	PES	ESC	55	-16.6	S	–	–	–	–	0.000313 U	0.000339 U	0.000432 U	0.000328 U	0.000432 U	0.000236 U	**0.00263**	0.000376 U	0.000363 U	0.000878 U
	IW-11D-60	4/19/18	PES	ESC	60	-21.6	S	–	–	–	–	0.000290 U	0.000314 U	0.000401 U	0.000304 U	0.000401 U	0.000219 U	0.000333 U	0.000348 U	0.000336 U	0.000814 U
	IW-11D-65	4/19/18	PES	ESC	65	-26.6	S	–	–	–	–	0.000291 U	0.000315 U	0.000402 U	0.000305 U	0.000402 U	0.000219 U	0.000334 U	0.000349 U	0.000337 U	0.000816 U
	IW-11D-70	4/19/18	PES	ESC	70	-31.6	S	–	–	–	–	0.000291 U	0.000316 U	0.000403 U	0.000306 U	0.000403 U	0.000220 U	**0.00611**	0.000350 U	0.000338 U	0.000818 U
	IW-11D-75	4/19/18	PES	ESC	75	-36.6	S	–	–	–	–	0.000305 U	0.000330 U	0.000421 U	0.000320 U	0.000421 U	0.000230 U	0.000350 U	0.000366 U	0.000353 U	0.000855 U
	IW-11D-80	4/19/18	PES	ESC	80	-41.6	S	–	–	–	–	0.000297 U	0.000321 U	0.000410 U	0.000311 U	0.000410 U	0.000224 U	0.000340 U	0.000356 U	0.000344 U	0.000833 U
	IW-11D-85	4/19/18	PES	ESC	85	-46.6	S	–	–	–	–	0.000303 U	0.000329 U	0.000420 U	0.000318 U	0.000420 U	0.000229 U	0.000348 U	0.000364 U	0.000352 U	0.000852 U
	IW-11D-90	4/19/18	PES	ESC	90	-51.6	S	–	–	–	–	0.000299 U	0.000324 U	0.000414 U	0.000314 U	0.000414 U	0.000225 U	0.000343 U	0.000359 U	0.000347 U	0.000840 U
	IW-11D-95	4/19/18	PES	ESC	95	-56.6	S	–	–	–	–	0.000309 U	0.000335 U	0.000428 U	0.000325 U	0.000428 U	0.000233 U	0.000355 U	0.000371 U	0.000359 U	0.000868 U
IW-12D	IW-12D-42	9/14/18	PES	ESC	42	-3.5	S	–	–	–	–	0.000543 U	0.000298 U	0.000423 U	0.000958 U	0.000733 U	0.000624 U	**0.00651**	0.000760 U	0.0678 U	0.00554 U
(-41.4 to-56.4)	B-928-42	9/14/18	PES	ESC	42 (dup)	-3.5	S	–	–	–	–	0.000543 U	0.000299 U	0.000424 U	0.000959 U	0.000733 U	0.000625 U	**0.00321**	0.000761 U	0.0679 U	0.00554 U
	IW-12D-50	9/14/18	PES	ESC	50	-11.5	S	–	–	–	–	0.000547 U	0.000301 U	0.000427 U	0.000966 U	0.000738 U	0.000629 U	**0.0102**	0.000766 U	0.137 U	0.00558 U
	IW-12D-60	9/14/18	PES	ESC	60	-21.5	S	–	–	–	–	0.000563 U	0.000310 U	0.000439 U	0.000995 U	0.000760 U	0.000648 U	0.000563 U	0.000788 U	0.0141 U	0.00574 U
	IW-12D-85	9/17/18	PES	ESC	85	-46.5	S	–	–	–	–	0.000559 U	0.000307 U	0.000436 U	0.0198 U	0.000754 U	0.000643 U	0.000559 U	0.000782 U	0.000699 U	0.00570 U
	IW-12D-95	9/17/18	PES	ESC	95	-56.5	S	–	–	–	–	0.000601 U	0.000331 U	0.000469 U	0.00425 U	0.000812 U	0.000692 U	0.000601 U	0.000842 U	0.000752 U	0.00613 U
IW-13D	IW-13D-80	9/18/18	PES	ESC	80	-40.8	S	–	–	–	–	0.000552 U	0.000303 U	0.000430 U	0.0779 U	0.000745 U	0.000634 U	**0.0362**	0.000772 U	0.000690 U	0.00563 U
(-41.0 to-56.0)	IW-13D-85	9/18/18	PES	ESC	85	-45.8	S	–	–	–	–	0.000576 U	0.000317 U	0.000449 U	0.00102 U	0.000777 U	0.000662 U	**0.00620**	0.000806 U	0.000719 U	0.00587 U
	IW-13D-95	9/18/18	PES	ESC	95	-55.8	S	–	–	–	–	0.000602 U	0.000331 U	0.000469 U	0.00106 U	0.000812 U	0.000692 U	0.000602 U	0.000842 U	0.000752 U	0.00614 U
IW-14D	IW-14D-45	9/11/18	PES	ESC	45	-5.9	S	–	–	–	–	0.000524 U	0.000288 U	0.000409 U	0.000925 U	0.000707 U	0.000602 U	0.000524 U	0.000733 U	0.000655 U	0.00534 U
(-41.0 to-56.0)	IW-14D-55	9/11/18	PES	ESC	55	-15.9	S	–	–	–	–	0.000565 U	0.000311 U	0.000441 U	0.000998 U	0.000763 U	0.000650 U	**0.0365**	0.000791 U	0.000706 U	0.00576 U
	IW-14D-65	9/11/18	PES	ESC	65	-25.9	S	–	–	–	–	0.000561 U	0.000309 U	0.000438 U	0.000991 U	0.000758 U	0.000645 U	0.000561 U	0.000786 U	0.000701 U	0.00572 U
	IW-14D-75	9/11/18	PES	ESC	75	-35.9	S	–	–	–	–	0.000561 U	0.000309 U	0.000438 U	0.000991 U	0.000757 U	0.000645 U	0.000561 U	0.000785 U	0.000701 U	0.00572 U
	IW-14D-86	9/11/18	PES	ESC	86	-46.9	S	–	–	–	–	0.000551 U	0.000303 U	0.000430 U	0.000973 U	0.000744 U	0.000633 U	**0.00762**	0.000771 U	0.000689 U	0.00562 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
IW-14D (continued)	IW-14D-95	9/11/18	PES	ESC	95	-55.9	S	–	–	–	–	0.000566 U	0.000312 U	0.000442 U	0.00100 U	0.000765 U	0.000651 U	**0.00354**	0.000793 U	**0.00174 J**	0.00578 U
IW-15D (-41.9 to-56.9)	IW-15D-54	9/11/18	PES	ESC	54	-2.2	S	–	–	–	–	0.000535 U	0.000294 U	0.000417 U	0.000945 U	0.000722 U	0.000615 U	**0.00469**	0.000749 U	0.000669 U	0.00546 U
IW-16D (-41.5 to-56.2)	IW-16D-85	10/18/18	PES	PACE	85	-45.6	S	–	–	–	–	0.00233 U	0.00128 U	0.00182 U	0.00411 U	0.00315 U	0.00268 U	0.00233 U	0.00326 U	0.00291 U	0.0238 U
	IW-16D-90	10/18/18	PES	PACE	90	-50.6	S	–	–	–	–	0.000593 U	0.000326 U	0.000462 U	0.00105 U	0.000800 U	0.000682 U	**0.00433**	0.000830 U	0.000741 U	0.00605 U
	IW-16D-95	10/18/18	PES	PACE	95	-55.6	S	–	–	–	–	0.00242 U	0.00133 U	0.00189 U	0.00427 U	0.00327 U	0.00278 U	0.00242 U	0.00339 U	0.00303 U	0.0247 U
IW-19B (-10.6 to-25.6)	IW-19B-5	3/19/18	PES	ESC	5	32.4	S	–	–	–	–	0.000298 U	0.000323 U	0.000412 U	0.000313 U	0.000412 U	0.000225 U	0.000342 U	0.000358 U	0.000345 U	0.000837 U
	IW-19B-10	3/19/18	PES	ESC	10	27.4	S	–	–	–	–	0.000325 U	0.000352 U	0.000449 U	0.000341 U	0.000449 U	0.000245 U	0.000373 U	0.000390 U	0.000377 U	0.000912 U
	IW-19B-15	3/19/18	PES	ESC	15	22.4	S	–	–	–	–	0.000302 U	0.000328 U	0.000418 U	0.000317 U	0.000418 U	0.000228 U	0.000347 U	0.000363 U	0.000351 U	0.000849 U
	IW-19B-20	3/19/18	PES	ESC	20	17.4	S	–	–	–	–	0.000295 U	0.000319 U	0.000408 U	0.000309 U	0.000408 U	0.000222 U	0.000338 U	0.000354 U	0.000342 U	0.000827 U
	IW-19B-25	3/19/18	PES	ESC	25	12.4	S	–	–	–	–	0.000310 U	0.000336 U	0.000428 U	0.000325 U	0.000428 U	0.000234 U	0.000356 U	0.000372 U	0.000359 U	0.000870 U
	IW-19B-30	3/19/18	PES	ESC	30	7.4	S	–	–	–	–	0.000297 U	0.000321 U	0.000410 U	0.000311 U	0.000410 U	0.000224 U	0.000340 U	0.000356 U	0.000344 U	0.000832 U
	IW-19B-35	3/19/18	PES	ESC	35	2.4	S	–	–	–	–	0.000293 U	0.000317 U	0.000405 U	0.000307 U	0.000405 U	0.000221 U	0.000336 U	0.000352 U	0.000339 U	0.000822 U
	IW-19B-40	3/19/18	PES	ESC	40	-2.6	S	–	–	–	–	0.000305 U	0.000330 U	0.000421 U	0.000320 U	0.000421 U	0.000230 U	0.000350 U	0.000366 U	0.000353 U	0.000855 U
	IW-19B-45	3/19/18	PES	ESC	45	-7.6	S	–	–	–	–	0.000322 U	0.000349 U	0.000445 U	0.000338 U	0.000445 U	0.000243 U	0.000370 U	0.000387 U	0.000373 U	0.000904 U
	IW-19B-50	3/19/18	PES	ESC	50	-12.6	S	–	–	–	–	0.000337 U	0.000365 U	0.000466 U	0.000353 U	0.000466 U	0.000254 U	0.000386 U	0.000405 U	0.000391 U	0.000946 U
	IW-19B-55	3/19/18	PES	ESC	55	-17.6	S	–	–	–	–	0.000290 U	0.000315 U	0.000402 U	0.000305 U	0.000402 U	0.000219 U	**0.00451**	0.000349 U	0.000337 U	0.000815 U
	IW-19B-60	3/19/18	PES	ESC	60	-22.6	S	–	–	–	–	0.000291 U	0.000316 U	0.000403 U	0.000306 U	0.000403 U	0.000220 U	**0.0100**	0.000350 U	0.000338 U	0.000818 U
	IW-903-60	3/19/18	PES	ESC	60 (dup)	-22.6	S	–	–	–	–	0.000296 U	0.000321 U	0.000410 U	0.000311 U	0.000410 U	0.000223 U	**0.00766**	0.000356 U	0.000344 U	0.000832 U
	IW-19B-63	3/19/18	PES	ESC	63	-25.6	S	–	–	–	–	0.000296 U	0.000320 U	0.000409 U	0.000310 U	0.000409 U	0.000223 U	**0.000919 J**	0.000355 U	0.000343 U	0.000830 U
IW-21B (-10.1 to-25.1)	IW-21B-5	3/6/18	PES	ESC	5	36.9	V	–	–	–	–	0.000477 U	0.000517 U	0.000660 U	0.000501 U	0.000660 U	0.000360 U	0.000548 U	0.000573 U	0.000552 U	0.00134 U
	IW-21B-10	3/6/18	PES	ESC	10	31.9	S	–	–	–	–	0.000322 U	0.000349 U	0.000445 U	0.000338 U	0.000445 U	0.000243 U	0.000369 U	0.000386 U	0.000373 U	0.000903 U
	IW-21B-20	3/6/18	PES	ESC	20	21.9	S	–	–	–	–	0.000317 U	0.000344 U	0.000439 U	0.000333 U	0.000439 U	0.000239 U	0.000364 U	0.000381 U	0.000368 U	0.000891 U
	IW-21B-30	3/6/18	PES	ESC	30	11.9	S	–	–	–	–	0.000295 U	0.000319 U	0.000408 U	0.000309 U	0.000408 U	0.000222 U	0.000338 U	0.000354 U	0.000342 U	0.000827 U
	IW-21B-40	3/6/18	PES	ESC	40	1.9	S	–	–	–	–	0.000292 U	0.000316 U	0.000403 U	0.000306 U	0.000403 U	0.000220 U	0.000335 U	0.000350 U	0.000338 U	0.000819 U
	IW-21B-50	3/6/18	PES	ESC	50	-8.1	S	–	–	–	–	0.000286 U	0.000309 U	0.000395 U	0.000300 U	0.000395 U	0.000215 U	0.000328 U	0.000343 U	0.000331 U	0.000801 U
	IW-21B-60	3/6/18	PES	ESC	60	-18.1	S	–	–	–	–	0.00748 U	0.00810 U	0.0103 U	0.00784 U	0.0103 U	0.00564 U	0.00859 U	0.00897 U	0.00867 U	0.0210 U
	IW-21B-67	3/6/18	PES	ESC	67	-25.1	S	–	–	–	–	0.000292 U	0.000317 U	0.000404 U	0.000307 U	0.000404 U	0.000220 U	0.000336 U	0.000351 U	0.000339 U	0.000821 U
IW-22C (-25.6 to-40.6)	IW-22C-62	8/31/18	PES	ESC	62	-23.1	S	–	–	–	–	0.000577 U	0.000317 U	0.000450 U	0.00102 U	0.000779 U	0.000664 U	**0.00263 J**	0.000808 U	0.000722 U	0.00589 U
	IW-22C-78	8/31/18	PES	ESC	78	-39.1	S	–	–	–	–	0.000606 U	0.000333 U	0.000472 U	0.00107 U	0.000818 U	0.000696 U	**0.00765**	0.000848 U	0.000757 U	0.00618 U
IW-23C (-27.0 to-42.0)	IW-23C-42	9/4/18	PES	ESC	42	-3.0	S	–	–	–	–	0.000598 U	0.000329 U	0.000467 U	0.00106 U	0.323 U	0.000688 U	**0.0116**	0.000838 U	0.000748 U	0.00610 U
IW-24C (-26.1 to-41.1)	IW-24C-48	9/7/18	PES	ESC	48	-8.8	S	–	–	–	–	0.000565 U	0.000311 U	0.000441 U	0.000998 U	0.00763 U	0.000650 U	**0.0124**	0.000791 U	0.000706 U	0.00576 U
	IW-24C-55	9/7/18	PES	ESC	55	-15.8	S	–	–	–	–	0.000595 U	0.000327 U	0.000465 U	0.00105 U	0.000804 U	0.000685 U	**0.00857**	0.000834 U	0.000744 U	0.00607 U
	IW-24C-66	9/10/18	PES	ESC	66	-26.8	S	–	–	–	–	0.000618 U	0.000340 U	0.000482 U	0.00109 U	0.000835 U	0.000711 U	**0.0130**	0.000866 U	0.000773 U	0.00631 U
	IW-24C-75	9/10/18	PES	ESC	75	-35.8	S	–	–	–	–	0.000598 U	0.000329 U	0.000466 U	0.00106 U	0.000807 U	0.000687 U	**0.0198**	0.000837 U	0.000747 U	0.00610 U
	IW-24C-80	9/10/18	PES	ESC	80	-40.8	S	–	–	–	–	0.000553 U	0.000304 U	0.000431 U	0.000977 U	0.000747 U	0.000636 U	0.000553 U	0.000774 U	0.000691 U	0.00564 U
IW-27B (-8.1 to-23.1)	IW-27B-5	3/2/18	PES	ESC	5	37.0	V	–	–	–	–	0.000424 U	0.000458 U	0.000585 U	0.000443 U	0.000585 U	0.000319 U	0.000485 U	0.000507 U	0.000490 U	0.00119 U
	IW-27B-15	3/2/18	PES	ESC	15	27.0	S	–	–	–	–	0.000376 U	0.000407 U	0.000520 U	0.000394 U	0.000520 U	0.000283 U	0.000432 U	0.000451 U	0.000436 U	0.00106 U
	IW-27B-25	3/2/18	PES	ESC	25	17.0	S	–	–	–	–	0.000307 U	0.000333 U	0.000425 U	0.000322 U	0.000425 U	0.000231 U	0.000352 U	0.000369 U	0.000356 U	0.000862 U
	IW-27B-35	3/2/18	PES	ESC	35	7.0	S	–	–	–	–	0.000302 U	0.000327 U	0.000418 U	0.000317 U	0.000418 U	0.000228 U	**0.000468 J**	0.000363 U	0.000350 U	0.000848 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
IW-27C (-24.4 to-39.6)	IW-27C-45	9/10/18	PES	ESC	45	6.8	S	–	–	–	–	0.000560 U	0.000308 U	0.000437 U	0.000988 U	0.000756 U	0.000644 U	0.000560 U	0.000784 U	0.000700 U	0.00571 U
IW-28C (-26.6 to-41.7)	IW-28C-92	9/17/18	PES	ESC	92	-40.6	S	–	–	–	–	0.000544 U	0.000299 U	0.000424 U	0.00384 U	0.000734 U	0.000625 U	0.000544 U	0.000761 U	0.000679 U	0.00554 U
IW-39B (-9.8 to-24.8)	IW-39B-5	3/12/18	PES	ESC	5	35.2	V	–	–	–	–	0.000335 U	0.000363 U	0.000463 U	0.000352 U	0.000463 U	0.000253 U	0.000385 U	0.000403 U	0.000389 U	0.000941 U
	IW-39B-15	3/12/18	PES	ESC	15	25.2	S	–	–	–	–	0.000294 U	0.000319 U	0.000407 U	0.000309 U	0.000407 U	0.000222 U	0.000338 U	0.000353 U	0.000341 U	0.000826 U
	IW-39B-25	3/12/18	PES	ESC	25	15.2	S	–	–	–	–	0.000314 U	0.000340 U	0.000434 U	0.000329 U	0.000434 U	0.000237 U	**0.00122**	0.000377 U	0.000364 U	0.000881 U
	IW-39B-35	3/12/18	PES	ESC	35	5.2	S	–	–	–	–	0.000290 U	0.000314 U	0.000401 U	0.000304 U	0.000401 U	0.000219 U	0.000333 U	0.000348 U	0.000336 U	0.000814 U
	IW-39B-45	3/12/18	PES	ESC	45	-4.8	S	–	–	–	–	0.000296 U	0.000321 U	0.000409 U	0.000311 U	0.000409 U	0.000223 U	0.000340 U	0.000355 U	0.000343 U	0.000831 U
	IW-39B-55	3/12/18	PES	ESC	55	-14.8	S	–	–	–	–	0.00693 U	0.00751 U	0.00958 U	0.00727 U	0.00958 U	0.00523 U	0.00796 U	0.00832 U	0.00803 U	0.0194 U
IW-46B (-4.2 to-24.2)	IW-46B-5	3/20/18	PES	ESC	5	46.8	V	–	–	–	–	0.000297 U	0.000321 U	0.000410 U	0.000311 U	0.000410 U	0.000224 U	0.000341 U	0.000356 U	0.000344 U	0.000833 U
	IW-46B-10	3/20/18	PES	ESC	10	41.8	V	–	–	–	–	0.000290 U	0.000314 U	0.000401 U	0.000304 U	0.000401 U	0.000219 U	0.000333 U	0.000348 U	0.000336 U	0.000814 U
	IW-46B-15	3/20/18	PES	ESC	15	36.8	V	–	–	–	–	0.00730 U	0.00791 U	0.0101 U	0.00765 U	0.0101 U	0.00551 U	0.00838 U	0.00876 U	0.00846 U	0.0205 U
	IW-46B-20	3/20/18	PES	ESC	20	31.8	S	–	–	–	–	0.000295 U	0.000320 U	0.000408 U	0.000310 U	0.000408 U	0.000222 U	0.000339 U	0.000354 U	0.000342 U	0.000828 U
	IW-46B-25	3/20/18	PES	ESC	25	26.8	S	–	–	–	–	0.000292 U	0.000316 U	0.000403 U	0.000306 U	0.000403 U	0.000220 U	0.000335 U	0.000350 U	0.000338 U	0.000819 U
	IW-46B-30	3/20/18	PES	ESC	30	21.8	S	–	–	–	–	0.000295 U	0.000320 U	0.000408 U	0.000310 U	0.000408 U	0.000223 U	0.000339 U	0.000354 U	0.000342 U	0.000829 U
	IW-46B-35	3/20/18	PES	ESC	35	16.8	S	–	–	–	–	0.000319 U	0.000346 U	0.000442 U	0.000335 U	0.000442 U	0.000241 U	0.000367 U	0.000384 U	0.000370 U	0.000896 U
	IW-904-35	3/20/18	PES	ESC	35 (dup)	16.8	S	–	–	–	–	0.000338 U	0.000366 U	0.000467 U	0.000354 U	0.000467 U	0.000254 U	**0.000679 J**	0.000405 U	0.000391 U	0.000948 U
	IW-46B-40	3/20/18	PES	ESC	40	11.8	S	–	–	–	–	0.000278 U	0.000301 U	0.000384 U	0.000291 U	0.000384 U	0.000209 U	**0.000329 J**	0.000333 U	0.000322 U	0.000779 U
	IW-46B-42	3/20/18	PES	ESC	42	9.8	S	–	–	–	–	0.000317 U	0.000344 U	0.000439 U	0.000333 U	0.000439 U	0.000239 U	**0.00819**	0.000381 U	0.000368 U	0.000891 U
	IW-46B-45	3/20/18	PES	ESC	45	6.8	S	–	–	–	–	1.50 U	1.63 U	2.07 U	1.57 U	2.07 U	1.13 U	1.73 U	1.80 U	1.74 U	4.21 U
	IW-46B-50	3/20/18	PES	ESC	50	1.8	S	–	–	–	–	0.000264 U	0.000286 U	0.000365 U	0.000277 U	0.000365 U	0.000199 U	**0.00222**	0.000317 U	0.000306 U	0.000741 U
	IW-46B-55	3/20/18	PES	ESC	55	-3.2	S	–	–	–	–	0.000294 U	0.000319 U	0.000407 U	0.000309 U	0.000407 U	0.000222 U	**0.00185**	0.000353 U	0.000341 U	0.000826 U
	IW-46B-60	3/20/18	PES	ESC	60	-8.2	S	–	–	–	–	0.000298 U	0.000323 U	0.000412 U	0.000313 U	0.000412 U	0.000225 U	**0.0166**	0.000358 U	0.000346 U	0.000837 U
	IW-46B-65	3/20/18	PES	ESC	65	-13.2	S	–	–	–	–	0.000294 U	0.000318 U	0.000406 U	0.000308 U	0.000406 U	0.000221 U	**0.0131**	0.000352 U	0.000340 U	0.000824 U
	IW-46B-70	3/20/18	PES	ESC	70	-18.2	S	–	–	–	–	0.000337 U	0.000365 U	0.000466 U	0.000353 U	0.000466 U	0.000254 U	**0.0321**	0.000404 U	0.000390 U	0.000945 U
IW-47B (-5.2 to-25.2)	IW-47B-5	3/22/18	PES	ESC	5	46.8	V	–	–	–	–	0.000311 U	0.000337 U	0.000431 U	0.000327 U	0.000431 U	0.000235 U	0.000357 U	0.000374 U	0.000361 U	0.000874 U
	IW-47B-10	3/22/18	PES	ESC	10	41.8	V	–	–	–	–	0.000311 U	0.000336 U	0.000429 U	0.000326 U	0.000429 U	0.000234 U	0.000356 U	0.000373 U	0.000360 U	0.000872 U
	IW-47B-15	3/22/18	PES	ESC	15	36.8	V	–	–	–	–	0.000295 U	0.000319 U	0.000408 U	0.000309 U	0.000408 U	0.000222 U	0.000338 U	0.000354 U	0.000342 U	0.000827 U
	IW-47B-20	3/22/18	PES	ESC	20	31.8	S	–	–	–	–	0.000293 U	0.000318 U	0.000405 U	0.000308 U	0.000405 U	0.000221 U	0.000336 U	0.000352 U	0.000340 U	0.000823 U
	IW-47B-25	3/22/18	PES	ESC	25	26.8	S	–	–	–	–	0.000299 U	0.000324 U	0.000413 U	0.000313 U	0.000413 U	0.000225 U	0.000343 U	0.000359 U	0.000346 U	0.000838 U
	IW-47B-30	3/22/18	PES	ESC	30	21.8	S	–	–	–	–	0.000296 U	0.000321 U	0.000409 U	0.000311 U	0.000409 U	0.000223 U	**0.000571 J**	0.000355 U	0.000343 U	0.000831 U
	IW-47B-35	3/22/18	PES	ESC	35	16.8	S	–	–	–	–	0.000290 U	0.000315 U	0.000401 U	0.000305 U	0.000401 U	0.000219 U	0.000333 U	0.000349 U	0.000337 U	0.000815 U
	IW-47B-40	3/22/18	PES	ESC	40	11.8	S	–	–	–	–	0.000300 U	0.000325 U	0.000414 U	0.000314 U	0.000414 U	0.000226 U	0.000344 U	0.000360 U	0.000347 U	0.000841 U
	IW-47B-42	3/22/18	PES	ESC	42	9.8	S	–	–	–	–	0.000346 U	0.000375 U	0.000478 U	0.000364 U	0.000478 U	0.000261 U	0.000397 U	0.000416 U	0.000402 U	0.000972 U
	IW-47B-45	3/22/18	PES	ESC	45	6.8	S	–	–	–	–	0.000299 U	0.000323 U	0.000413 U	0.000313 U	0.000413 U	0.000225 U	**0.00297**	0.000358 U	0.000346 U	0.000838 U
	IW-47B-50	3/22/18	PES	ESC	50	1.8	S	–	–	–	–	0.000310 U	0.000336 U	0.000429 U	0.000325 U	0.000429 U	0.000234 U	**0.000366 J**	0.000372 U	0.000359 U	0.000870 U
	IW-47B-55	3/22/18	PES	ESC	55	-3.2	S	–	–	–	–	0.000285 U	0.000309 U	0.000395 U	0.000299 U	0.000395 U	0.000215 U	**0.00579**	0.000343 U	0.000331 U	0.000801 U
	IW-47B-60	3/22/18	PES	ESC	60	-8.2	S	–	–	–	–	0.000302 U	0.000327 U	0.000417 U	0.000317 U	0.000417 U	0.000228 U	**0.00230**	0.000362 U	0.000350 U	0.000847 U
	IW-47B-65	3/22/18	PES	ESC	65	-13.2	S	–	–	–	–	0.000298 U	0.000323 U	0.000412 U	0.000313 U	0.000412 U	0.000225 U	**0.000944 J**	0.000358 U	0.000345 U	0.000836 U
	IW-47B-70	3/22/18	PES	ESC	70	-18.2	S	–	–	–	–	0.000295 U	0.000319 U	0.000407 U	0.000309 U	0.000407 U	0.000222 U	**0.0164**	0.000354 U	0.000342 U	0.000827 U
	IW-47B-75	3/22/18	PES	ESC	75	-23.2	S	–	–	–	–	0.000294 U	0.000318 U	0.000406 U	0.000308 U	0.000406 U	0.000221 U	0.000337 U	0.000353 U	0.000341 U	0.000825 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
IW-48B	IW-48B-5	3/23/18	PES	ESC	5	46.7	V	–	–	–	–	0.000305 U	0.000331 U	0.000422 U	0.000320 U	0.000422 U	0.000230 U	0.000350 U	0.000366 U	0.000354 U	0.000856 U
(-9.4 to-24.4)	IW-48B-10	3/23/18	PES	ESC	10	41.7	V	–	–	–	–	0.000299 U	0.000324 U	0.000413 U	0.000314 U	0.000413 U	0.000225 U	0.000343 U	0.000359 U	0.000346 U	0.000839 U
	IW-48B-15	3/23/18	PES	ESC	15	36.7	V	–	–	–	–	0.000308 U	0.000334 U	0.000426 U	0.000323 U	0.000426 U	0.000232 U	0.000354 U	0.000370 U	0.000357 U	0.000865 U
	IW-48B-20	3/23/18	PES	ESC	20	31.7	S	–	–	–	–	0.000290 U	0.000315 U	0.000402 U	0.000305 U	0.000402 U	0.000219 U	0.000333 U	0.000349 U	0.000337 U	0.000815 U
	IW-48B-25	3/23/18	PES	ESC	25	26.7	S	–	–	–	–	0.000297 U	0.000322 U	0.000411 U	0.000312 U	0.000411 U	0.000224 U	0.000341 U	0.000357 U	0.000345 U	0.000834 U
	IW-48B-30	3/23/18	PES	ESC	30	21.7	S	–	–	–	–	0.000291 U	0.000315 U	0.000402 U	0.000305 U	0.000402 U	0.000219 U	0.000334 U	0.000349 U	0.000337 U	0.000817 U
	IW-48B-35	3/23/18	PES	ESC	35	16.7	S	–	–	–	–	0.000304 U	0.000329 U	0.000420 U	0.000319 U	0.000420 U	0.000229 U	**0.000718 J**	0.000365 U	0.000352 U	0.000853 U
	IW-48B-40	3/23/18	PES	ESC	40	11.7	S	–	–	–	–	0.000288 U	0.000312 U	0.000398 U	0.000302 U	0.000398 U	0.000217 U	**0.000350 J**	0.000346 U	0.000334 U	0.000809 U
	IW-48B-42	3/23/18	PES	ESC	42	9.7	S	–	–	–	–	0.000291 U	0.000315 U	0.000402 U	0.000305 U	0.000402 U	0.000219 U	0.000334 U	0.000349 U	0.000337 U	0.000817 U
	IW-905-42	3/23/18	PES	ESC	42 (dup)	9.7	S	–	–	–	–	0.000288 U	0.000312 U	0.000399 U	0.000303 U	0.000399 U	0.000217 U	0.000331 U	0.000346 U	0.000334 U	0.000809 U
	IW-48B-45	3/23/18	PES	ESC	45	6.7	S	–	–	–	–	0.000286 U	0.000310 U	0.000396 U	0.000301 U	0.000396 U	0.000216 U	0.000329 U	0.000344 U	0.000332 U	0.000804 U
	IW-48B-50	3/23/18	PES	ESC	50	1.7	S	–	–	–	–	0.000291 U	0.000316 U	0.000403 U	0.000306 U	0.000403 U	0.000220 U	0.000334 U	0.000350 U	0.000338 U	0.000818 U
	IW-48B-55	3/23/18	PES	ESC	55	-3.3	S	–	–	–	–	0.000286 U	0.000311 U	0.000396 U	0.000300 U	0.000396 U	0.000216 U	**0.000804 J**	0.000344 U	0.000332 U	0.000804 U
	IW-48B-60	3/23/18	PES	ESC	60	-8.3	S	–	–	–	–	0.000292 U	0.000316 U	0.000404 U	0.000306 U	0.000404 U	0.000220 U	**0.00383**	0.000351 U	0.000338 U	0.000820 U
	IW-48B-65	3/23/18	PES	ESC	65	-13.3	S	–	–	–	–	0.000312 U	0.000338 U	0.000431 U	0.000327 U	0.000431 U	0.000235 U	**0.000557 J**	0.000375 U	0.000362 U	0.000875 U
	IW-48B-70	3/23/18	PES	ESC	70	-18.3	S	–	–	–	–	0.000290 U	0.000314 U	0.000401 U	0.000305 U	0.000401 U	0.000219 U	**0.000702 J**	0.000348 U	0.000336 U	0.000815 U
	IW-48B-75	3/23/18	PES	ESC	75	-23.3	S	–	–	–	–	0.000297 U	0.000322 U	0.000410 U	0.000312 U	0.000410 U	0.000224 U	**0.0121**	0.000357 U	0.000344 U	0.000833 U
IW-50A	IW-50A-5	3/27/18	PES	ESC	5	46.9	V	–	–	–	–	0.000301 U	0.000326 U	0.000417 U	0.000316 U	0.000417 U	0.000227 U	0.000346 U	0.000362 U	0.000349 U	0.000846 U
(9.8 to-10.2)	IW-50A-10	3/27/18	PES	ESC	10	41.9	V	–	–	–	–	0.000294 U	0.000319 U	0.000407 U	0.000309 U	0.000407 U	0.000222 U	0.000338 U	0.000353 U	0.000341 U	0.000826 U
	IW-50A-15	3/27/18	PES	ESC	15	36.9	V	–	–	–	–	0.000290 U	0.000314 U	0.000401 U	0.000304 U	0.000401 U	0.000219 U	0.000333 U	0.000348 U	0.000336 U	0.000814 U
	IW-50A-20	3/27/18	PES	ESC	20	31.9	S	–	–	–	–	0.000293 U	0.000318 U	0.000406 U	0.000308 U	0.000406 U	0.000221 U	0.000337 U	0.000352 U	0.000340 U	0.000824 U
	IW-50A-25	3/27/18	PES	ESC	25	26.9	S	–	–	–	–	0.000286 U	0.000310 U	0.000395 U	0.000300 U	0.000395 U	0.000215 U	0.000328 U	0.000343 U	0.000331 U	0.000802 U
	IW-50A-30	3/27/18	PES	ESC	30	21.9	S	–	–	–	–	0.000287 U	0.000311 U	0.000396 U	0.000301 U	0.000396 U	0.000216 U	0.000329 U	0.000344 U	0.000332 U	0.000805 U
	IW-50A-35	3/27/18	PES	ESC	35	16.9	S	–	–	–	–	0.000287 U	0.000311 U	0.000397 U	0.000302 U	0.000397 U	0.000217 U	0.000330 U	0.000345 U	0.000333 U	0.000807 U
	IW-50A-40	3/27/18	PES	ESC	40	11.9	S	–	–	–	–	0.000292 U	0.000316 U	0.000403 U	0.000306 U	0.000403 U	0.000220 U	0.000335 U	0.000350 U	0.000338 U	0.000819 U
	IW-50A-42	3/27/18	PES	ESC	42	9.9	S	–	–	–	–	0.000290 U	0.000314 U	0.000401 U	0.000304 U	0.000401 U	0.000219 U	**0.000417 J**	0.000348 U	0.000336 U	0.000814 U
	IW-50A-45	3/27/18	PES	ESC	45	6.9	S	–	–	–	–	0.000292 U	0.000317 U	0.000404 U	0.000307 U	0.000404 U	0.000220 U	**0.000654 J**	0.000351 U	0.000339 U	0.000820 U
	IW-50A-50	3/27/18	PES	ESC	50	1.9	S	–	–	–	–	0.000296 U	0.000321 U	0.000410 U	0.000311 U	0.000410 U	0.000223 U	**0.000430 J**	0.000356 U	0.000343 U	0.000831 U
	IW-906-50	3/27/18	PES	ESC	50 (dup)	1.9	S	–	–	–	–	0.000298 U	0.000323 U	0.000412 U	0.000313 U	0.000412 U	0.000225 U	0.000342 U	0.000358 U	0.000345 U	0.000837 U
	IW-50A-55	3/27/18	PES	ESC	55	-3.2	S	–	–	–	–	0.000297 U	0.000322 U	0.000411 U	0.000312 U	0.000411 U	0.000224 U	0.000341 U	0.000357 U	0.000344 U	0.000834 U
	IW-50A-60	3/27/18	PES	ESC	60	-8.2	S	–	–	–	–	0.000298 U	0.000323 U	0.000412 U	0.000313 U	0.000412 U	0.000225 U	0.000342 U	0.000358 U	0.000346 U	0.000837 U
IW-51A	IW-51A-5	3/26/18	PES	ESC	5	46.9	V	–	–	–	–	0.000290 U	0.000314 U	0.000401 U	0.000305 U	0.000401 U	0.000219 U	0.000333 U	0.000349 U	0.000336 U	0.000815 U
(9.9 to-10.1)	IW-51A-10	3/26/18	PES	ESC	10	41.9	V	–	–	–	–	0.000288 U	0.000312 U	0.000398 U	0.000302 U	0.000398 U	0.000217 U	0.000330 U	0.000346 U	0.000334 U	0.000808 U
	IW-51A-15	3/26/18	PES	ESC	15	36.9	V	–	–	–	–	0.000299 U	0.000324 U	0.000414 U	0.000314 U	0.000414 U	0.000226 U	0.000344 U	0.000359 U	0.000347 U	0.000840 U
	IW-51A-20	3/26/18	PES	ESC	20	31.9	S	–	–	–	–	0.000286 U	0.000310 U	0.000395 U	0.000300 U	0.000395 U	0.000216 U	0.000328 U	0.000343 U	0.000332 U	0.000803 U
	IW-51A-25	3/26/18	PES	ESC	25	26.9	S	–	–	–	–	0.000364 U	0.000395 U	0.000503 U	0.000382 U	0.000503 U	0.000275 U	**0.000517 J**	0.000438 U	0.000423 U	0.00102 U
	IW-51A-30	3/26/18	PES	ESC	30	21.9	S	–	–	–	–	0.000284 U	0.000308 U	0.000393 U	0.000299 U	0.000393 U	0.000214 U	0.000327 U	0.000342 U	0.000330 U	0.000799 U
	IW-51A-35	3/26/18	PES	ESC	35	16.9	S	–	–	–	–	0.000287 U	0.000311 U	0.000397 U	0.000302 U	0.000397 U	0.000217 U	0.000330 U	0.000345 U	0.000333 U	0.000807 U
	IW-51A-40	3/26/18	PES	ESC	40	11.9	S	–	–	–	–	0.000288 U	0.000312 U	0.000399 U	0.000303 U	0.000399 U	0.000217 U	**0.00272**	0.000346 U	0.000334 U	0.000810 U
	IW-51A-42	3/26/18	PES	ESC	42	9.9	S	–	–	–	–	0.000294 U	0.000318 U	0.000406 U	0.000308 U	0.000406 U	0.000222 U	**0.0108**	0.000353 U	0.000341 U	0.000825 U
	IW-51A-45	3/26/18	PES	ESC	45	6.9	S	–	–	–	–	0.000294 U	0.000318 U	0.000406 U	0.000308 U	0.000406 U	0.000222 U	0.000337 U	0.000353 U	0.000341 U	0.000825 U
	IW-51A-50	3/26/18	PES	ESC	50	1.9	S	–	–	–	–	0.000302 U	0.000328 U	0.000418 U	0.000317 U	0.000418 U	0.000228 U	**0.00233**	0.000363 U	0.000351 U	0.000849 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
IW-51A	IW-51A-55	3/26/18	PES	ESC	55	-3.1	S	–	–	–	–	0.000303 U	0.000328 U	0.000418 U	0.000318 U	0.000418 U	0.000228 U	**0.000907 J**	0.000363 U	0.000351 U	0.000849 U
(continued)	IW-51A-60	3/26/18	PES	ESC	60	-8.1	S	–	–	–	–	0.000284 U	0.000308 U	0.000393 U	0.000298 U	0.000393 U	0.000214 U	0.000326 U	0.000341 U	0.000329 U	0.000797 U
	IW-51A-62	3/26/18	PES	ESC	62	-10.1	S	–	–	–	–	0.000287 U	0.000311 U	0.000397 U	0.000301 U	0.000397 U	0.000216 U	0.000330 U	0.000345 U	0.000333 U	0.000806 U
IW-53B (-11.1 to-26.1)	IW-53B-30	9/20/18	PES	ESC	30	5.3	S	–	–	–	–	0.000544 U	0.000299 U	0.000424 U	0.00961 U	0.000734 U	0.000626 U	**0.000563 J**	0.000761 U	0.000680 U	0.00555 U
IW-54A	IW-54A-8	9/12/18	PES	ESC	8	31.1	S	–	–	–	–	0.000577 U	0.000317 U	0.000450 U	0.00102 U	0.000779 U	0.000664 U	0.000577 U	0.000808 U	0.144 U	0.00589 U
(9.8 to-10.2)	IW-54A-49	9/12/18	PES	ESC	49	-9.9	S	–	–	–	–	0.000579 U	0.000319 U	0.000452 U	0.00102 U	0.000782 U	0.000666 U	0.000579 U	0.000811 U	0.000724 U	0.00591 U
IW-54B	IW-54B-8	9/5/18	PES	ESC	8	31.2	S	–	–	–	–	0.000545 U	0.000300 U	0.000425 U	0.000963 U	1.47 U	0.000627 U	0.000545 U	0.000764 U	0.000682 U	0.00556 U
(-9.5 to-24.5)	IW-54B-13	9/6/18	PES	ESC	13	26.2	S	–	–	–	–	0.000555 U	0.000305 U	0.000433 U	0.000979 U	0.00749 U	0.000638 U	0.000555 U	0.000776 U	0.000693 U	0.00566 U
	IW-54B-21	9/6/18	PES	ESC	21	18.2	S	–	–	–	–	0.000546 U	0.000300 U	0.000426 U	0.000963 U	0.0147 U	0.000627 U	**0.00669**	0.000764 U	0.000682 U	0.00556 U
	IW-54B-33	9/6/18	PES	ESC	33	6.2	S	–	–	–	–	0.000625 U	0.000344 U	0.000487 U	0.00110 U	0.000836 U	0.000720 U	**0.00379**	0.000875 U	0.000781 U	0.00638 U
IW-55B	IW-55B-39	9/13/18	PES	ESC	39	12.8	S	–	–	–	–	0.000531 U	0.000292 U	0.000414 U	0.000938 U	0.000717 U	0.000611 U	0.000531 U	0.000743 U	0.000664 U	0.00542 U
(-12.0 to-27.0)	IW-55B-43	9/13/18	PES	ESC	43	8.8	S	–	–	–	–	0.000566 U	0.000311 U	0.000441 U	0.000999 U	0.000764 U	0.000650 U	0.000566 U	0.000792 U	0.0566 U	0.00577 U
	IW-55B-61	9/13/18	PES	ESC	61	-9.2	S	–	–	–	–	0.000594 U	0.000327 U	0.000463 U	0.00105 U	0.000802 U	0.000683 U	**0.0204**	0.000832 U	0.00594 U	0.00606 U
IW-58A	IW-58A-38	10/17/18	PES	PACE	38	1.2	S	–	–	–	–	0.000547 U	0.000301 U	0.00426 U	0.000965 U	0.000738 U	0.000628 U	**0.00253 J**	0.000765 U	0.00683 U	0.00557 U
(3.9 to-11.1)	B-929-38	10/17/18	PES	PACE	38 (dup)	1.2	S	–	–	–	–	0.000563 U	0.000310 U	0.00439 U	0.000994 U	0.000760 U	0.000647 U	**0.00373**	0.000788 U	0.00704 U	0.00574 U
MW101 (B101)	B101-30	7/10/12	SES	F&BI	30	9.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(-65.5 to-75.5)	B101-34	7/10/12	SES	F&BI	34	5.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-40	7/10/12	SES	F&BI	40	-0.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-47	7/10/12	SES	F&BI	47	-7.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-48	7/10/12	SES	F&BI	48	-8.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-55	7/10/12	SES	F&BI	55	-15.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-65	7/10/12	SES	F&BI	65	-25.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-75	7/11/12	SES	F&BI	75	-35.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-81	7/11/12	SES	F&BI	81	-41.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-92	7/12/12	SES	F&BI	92	-52.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-97	7/12/12	SES	F&BI	97	-57.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-104	7/12/12	SES	F&BI	104	-64.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-114.5	7/12/12	SES	F&BI	114.5	-75.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-120	7/12/12	SES	F&BI	120	-80.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-131	7/12/12	SES	F&BI	131	-91.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-140	7/12/12	SES	F&BI	140	-100.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW130 (B130)	B130-10	3/1/16	SES	F&BI	10	29.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(-30.9 to-40.9)	B130-20	3/1/16	SES	F&BI	20	19.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B130-30	3/1/16	SES	F&BI	30	9.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B130-40	3/1/16	SES	F&BI	40	-0.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B130-45	3/2/16	SES	F&BI	45	-5.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B130-50	3/2/16	SES	F&BI	50	-10.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B130-55	3/2/16	SES	F&BI	55	-15.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B130-60	3/2/16	SES	F&BI	60	-20.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B130-65	3/2/16	SES	F&BI	65	-25.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B130-70	3/2/16	SES	F&BI	70	-30.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	**–**	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	**–**	**0.030**	**1.5E-07**
MW130 (B130)	B130-75	3/2/16	SES	F&BI	75	-35.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(continued)	B130-80	3/2/16	SES	F&BI	80	-40.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW131 (B131)	B131-10	3/1/16	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(-4.2 to-14.2)	B131-20	3/1/16	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B131-30	3/1/16	SES	F&BI	30	10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B131-40	3/1/16	SES	F&BI	40	0.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B131-45	3/2/16	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B131-55	3/2/16	SES	F&BI	55	-15.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-132	MW-132-20	8/22/17	PES	ESC	20	20.1	S	0.0378 U	–	–	–	0.000294 U	0.000319 U	0.000407 U	0.000309 U	0.000407 U	0.000222 U	0.000338 U	0.000353 U	0.000341 U	0.000826 U
(-29.9 to-39.9)	MW-132-35	8/22/17	PES	ESC	35	5.1	S	0.0379 U	–	–	–	0.000295 U	0.000320 U	0.000408 U	0.000310 U	0.000408 U	0.000223 U	0.000339 U	0.000355 U	0.000342 U	0.000829 U
	MW-132-50	8/22/17	PES	ESC	50	-9.9	S	**1.97**	–	–	–	0.000286 U	0.000309 U	0.000395 U	0.000300 U	0.000395 U	0.000215 U	**0.00220**	0.000343 U	0.000331 U	0.000802 U
	MW-132-55	8/23/17	PES	ESC	55	-14.9	S	**126**	–	–	–	0.0304 U	0.0329 U	0.0420 U	0.0319 U	0.0420 U	0.0229 U	0.0348 U	0.0365 U	0.0352 U	0.0852 U
	MW-132-60	8/23/17	PES	ESC	60	-19.9	S	**0.276**	–	–	–	0.000284 U	0.000308 U	0.000393 U	0.000298 U	0.000393 U	0.000214 U	**0.00121**	0.000341 U	0.000330 U	0.000798 U
	MW-132-70	8/23/17	PES	ESC	70	-29.9	S	1.03 U	–	–	–	0.000322 U	0.000349 U	0.000445 U	0.000338 U	0.000445 U	0.000243 U	0.000369 U	0.000386 U	0.000373 U	0.000903 U
	MW-132-83	8/23/17	PES	ESC	83	-42.9	S	0.925 U	–	–	–	0.000288 U	0.000312 U	0.000398 U	0.000302 U	0.000398 U	0.000217 U	0.000331 U	0.000346 U	0.000334 U	0.000808 U
MW-133	MW-133-20	8/15/17	PES	ESC	20	20.1	S	**0.183**	–	–	–	0.000311 U	0.000337 U	0.000430 U	0.000326 U	0.000430 U	0.000235 U	**0.000487 J**	0.000374 U	0.000361 U	0.000873 U
(-88.9 to-98.9)	MW-133-35	8/15/17	PES	ESC	35	5.1	S	0.0443 U	–	–	–	0.000345 U	0.000373 U	0.000477 U	0.000362 U	0.000477 U	0.000260 U	0.000396 U	0.000414 U	0.000400 U	0.000967 U
	MW-133-45	8/15/17	PES	ESC	45	-4.9	S	**3.59**	–	–	–	0.000287 U	0.000311 U	0.000397 U	0.000301 U	0.000397 U	0.000216 U	**0.0115**	0.000345 U	0.000333 U	0.000805 U
	MW-133-55	8/15/17	PES	ESC	55	-14.9	S	**38.9**	–	–	–	0.0646 U	0.0700 U	0.0893 U	0.0678 U	0.0893 U	0.0487 U	0.0741 U	0.0775 U	0.0749 U	0.181 U
	MW-133-58	8/15/17	PES	ESC	58	-17.9	S	**387**	–	–	–	1.56 U	1.69 U	2.15 U	1.63 U	2.15 U	1.18 U	1.80 U	1.87 U	1.81 U	4.38 U
	MW-133-65	8/15/17	PES	ESC	65	-24.9	S	**7.21**	–	–	–	0.000306 U	0.000331 U	0.000422 U	0.000321 U	0.000422 U	0.000230 U	**0.00832**	0.000367 U	0.000354 U	0.000858 U
	MW-133-75	8/15/17	PES	ESC	75	-34.9	S	0.0394 U	–	–	–	0.000307 U	0.000333 U	0.000425 U	0.000322 U	0.000425 U	0.000232 U	0.000352 U	0.000369 U	0.000356 U	0.000862 U
	MW-133-85	8/15/17	PES	ESC	85	-44.9	S	**1.28**	–	–	–	0.00774 U	0.00838 U	0.0107 U	0.00811 U	0.0107 U	0.00584 U	0.00889 U	0.00928 U	0.00897 U	0.0217 U
	MW-133-95	8/16/17	PES	ESC	95	-54.9	S	**0.0572**	–	–	–	0.000308 U	0.000333 U	0.000425 U	0.000323 U	0.000425 U	0.000232 U	0.000353 U	0.000369 U	0.000356 U	0.000863 U
	MW-133-105	8/16/17	PES	ESC	105	-64.9	S	**0.0849**	–	–	–	0.000318 U	0.000344 U	0.000439 U	0.000334 U	0.000439 U	0.000240 U	0.000365 U	0.000382 U	0.000368 U	0.000892 U
	MW-133-120	8/16/17	PES	ESC	120	-79.9	S	**0.0964**	–	–	–	0.00717 U	0.00777 U	0.00991 U	0.00752 U	0.00991 U	0.00541 U	0.00824 U	0.00861 U	0.00831 U	0.0201 U
	MW-133-130	8/16/17	PES	ESC	130	-89.9	S	**0.109**	–	–	–	0.000314 U	0.000341 U	0.000435 U	0.000330 U	0.000435 U	0.000237 U	0.000361 U	0.000378 U	0.000365 U	0.000883 U
	MW-133-135	8/16/17	PES	ESC	135	-94.9	S	**15.3**	–	–	–	0.000299 U	0.000324 U	0.000413 U	0.000314 U	0.000413 U	0.000225 U	0.000343 U	0.000359 U	0.000347 U	0.000839 U
	MW-133-141	8/16/17	PES	ESC	141	-100.9	S	0.955 U	–	–	–	0.000297 U	0.000322 U	0.000411 U	0.000312 U	0.000411 U	0.000224 U	0.000341 U	0.000357 U	0.000345 U	0.000835 U
MW-134	MW-134-20	8/29/17	PES	ESC	20	21.5	S	1.12 U	–	–	–	0.000347 U	0.000376 U	0.000480 U	0.000365 U	0.000480 U	0.000262 U	0.000399 U	0.000417 U	0.000403 U	0.000975 U
(-38.6 to-48.6)	MW-134-43	8/29/17	PES	ESC	43	-1.6	S	0.984 U	–	–	–	0.000306 U	0.00830 U	0.000424 U	0.000321 U	0.000424 U	0.000231 U	**0.00306**	0.000368 U	0.000355 U	0.000860 U
	MW-134-50	8/29/17	PES	ESC	50	-8.6	S	**1.35**	–	–	–	0.000290 U	0.0314 U	0.000401 U	0.000305 U	0.000401 U	0.000219 U	**0.00222**	0.000349 U	0.000336 U	0.000815 U
	MW-134-60	8/29/17	PES	ESC	60	-18.6	S	**0.447**	–	–	–	0.000292 U	0.00790 U	0.000403 U	0.000306 U	0.000403 U	0.000220 U	**0.00190**	0.000350 U	0.000338 U	0.000818 U
	MW-134-70	8/29/17	PES	ESC	70	-28.6	S	1.11 U	–	–	–	0.000337 U	0.000365 U	0.000466 U	0.000353 U	0.000466 U	0.000254 U	0.000387 U	0.000404 U	0.000390 U	0.000945 U
	MW-134-80	8/29/17	PES	ESC	80	-38.6	S	0.970 U	–	–	–	0.000282 U	0.000306 U	0.000390 U	0.000296 U	0.000390 U	0.000213 U	0.000324 U	0.000339 U	0.000327 U	0.000792 U
	B-903-100	8/29/17	PES	ESC	80 (dup)	-38.6	S	0.893 U	–	–	–	0.000278 U	0.000301 U	0.000385 U	0.000292 U	0.000385 U	0.000210 U	**0.000521 J**	0.000334 U	0.000322 U	0.000781 U
	MW-134-90	8/29/17	PES	ESC	90	-48.6	S	1.08 U	–	–	–	0.000335 U	0.00908 U	0.000464 U	0.000352 U	0.000464 U	0.000253 U	0.000385 U	0.000403 U	0.000389 U	0.000941 U
MW-135	MW-135-16	8/24/17	PES	ESC	14	25.1	S	**641**	–	–	–	0.0322 U	0.0349 U	0.0445 U	0.0338 U	0.0445 U	0.0243 U	**1.04**	0.0387 U	0.0373 U	0.0904 U
(-30.9 to-40.9)	MW-135-20	8/24/17	PES	ESC	20	19.1	S	**0.277**	–	–	–	0.00752 U	0.00814 U	0.0104 U	0.00788 U	0.0104 U	0.00567 U	0.00863 U	0.00902 U	0.00871 U	0.0211 U
	MW-135-30	8/24/17	PES	ESC	30	9.1	S	**10.4**	–	–	–	0.000280 U	0.000304 U	0.000388 U	0.000294 U	0.000388 U	0.000211 U	**0.00227**	0.000337 U	0.000325 U	0.000787 U
	MW-135-36	8/24/17	PES	ESC	36	3.1	S	**0.733**	–	–	–	0.000308 U	0.000334 U	0.000426 U	0.000323 U	0.000426 U	0.000232 U	**0.000661 J**	0.000370 U	0.000357 U	0.000865 U
	MW-135-40	8/24/17	PES	ESC	40	-0.9	S	**4.34**	–	–	–	0.000315 U	0.000341 U	0.000435 U	0.000330 U	0.000435 U	0.000237 U	**0.0119**	0.000378 U	0.000365 U	0.000884 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
MW-135 (continued)	MW-135-45	8/24/17	PES	ESC	45	-5.9	S	**5.09**	–	–	–	0.000313 U	0.000340 U	0.000433 U	0.000329 U	0.000433 U	0.000236 U	**0.00157**	0.000376 U	0.000363 U	0.000880 U
	MW-135-55	8/24/17	PES	ESC	55	-15.9	S	**0.157**	–	–	–	0.000287 U	0.000311 U	0.000397 U	0.000301 U	0.000397 U	0.000216 U	0.000329 U	0.000344 U	0.000332 U	0.000805 U
	MW-135-65	8/24/17	PES	ESC	65	-25.9	S	**0.161**	–	–	–	0.000313 U	0.000339 U	0.000433 U	0.000329 U	0.000433 U	0.000236 U	0.000360 U	0.000376 U	0.000363 U	0.000879 U
	MW-135-80	8/24/17	PES	ESC	80	-40.9	S	**0.138**	–	–	–	0.000295 U	0.000319 U	0.000408 U	0.000309 U	0.000408 U	0.000222 U	0.000338 U	0.000354 U	0.000342 U	0.000828 U
MW-136 (-32.7 to-42.7)	MW-136-35	8/28/17	PES	ESC	35	16.9	S	–	–	–	–	0.000278 U	0.000301 U	0.000384 U	0.000292 U	0.000384 U	0.000209 U	0.000319 U	0.000334 U	0.000322 U	0.000780 U
	B-902-15	8/28/17	PES	ESC	35 (dup)	16.9	S	–	–	–	–	0.000288 U	0.000312 U	0.000399 U	0.000303 U	0.000399 U	0.000217 U	0.000331 U	0.000346 U	0.000334 U	0.000809 U
	MW-136-44	8/28/17	PES	ESC	44	7.9	S	–	–	–	–	0.000296 U	0.000321 U	0.000410 U	0.000311 U	0.000410 U	0.000223 U	**0.000371 J**	0.000356 U	0.000343 U	0.000832 U
	MW-136-50	8/28/17	PES	ESC	50	1.9	S	–	–	–	–	0.000304 U	0.00823 U	0.000420 U	0.000319 U	0.000420 U	0.000229 U	0.000349 U	0.000365 U	0.000352 U	0.000853 U
	MW-136-65	8/28/17	PES	ESC	65	-13.1	S	–	–	–	–	0.000287 U	0.000311 U	0.000397 U	0.000301 U	0.000397 U	0.000216 U	0.000330 U	0.000345 U	0.000333 U	0.000806 U
	MW-136-75	8/28/17	PES	ESC	75	-23.1	S	–	–	–	–	0.000293 U	0.000318 U	0.000405 U	0.000308 U	0.000405 U	0.000221 U	0.000337 U	0.000352 U	0.000340 U	0.000823 U
	MW-136-85	8/28/17	PES	ESC	85	-33.1	S	–	–	–	–	0.000295 U	0.000319 U	0.000407 U	0.000309 U	0.000407 U	0.000222 U	0.000338 U	0.000354 U	0.000342 U	0.000827 U
	MW-136-95	8/28/17	PES	ESC	95	-43.1	S	–	–	–	–	0.000295 U	0.000320 U	0.000408 U	0.000310 U	0.000408 U	0.000223 U	0.000339 U	0.000355 U	0.000342 U	0.000829 U
MW-137 (-53.3 to-63.3)	MW-137-25	8/31/17	PES	ESC	25	26.7	S	0.0370 U	–	–	–	0.000288 U	0.000312 U	0.000398 U	0.000302 U	0.000398 U	0.000217 U	0.000330 U	0.000346 U	0.000334 U	0.000808 U
	MW-137-45	8/31/17	PES	ESC	45	6.7	S	0.0384 U	–	–	–	0.00747 U	0.00809 U	0.0103 U	0.00783 U	0.0103 U	0.00564 U	0.00858 U	0.00896 U	0.00866 U	0.0209 U
	MW-137-75	8/31/17	PES	ESC	75	-23.3	S	–	–	–	–	0.000290 U	0.000314 U	0.000401 U	0.000304 U	0.000401 U	0.000218 U	0.000333 U	0.000348 U	0.000336 U	0.000814 U
	MW-137-85	9/1/17	PES	ESC	85	-33.3	S	0.0406 U	–	–	–	0.000316 U	0.000343 U	0.000437 U	0.000332 U	0.000437 U	0.000238 U	0.000363 U	0.000380 U	0.000367 U	0.000888 U
	MW-137-95	9/1/17	PES	ESC	95	-43.3	S	0.0363 U	–	–	–	0.000283 U	0.000306 U	0.000391 U	0.000297 U	0.000391 U	0.000213 U	0.000324 U	0.000339 U	0.000328 U	0.000794 U
	MW-137-115	9/1/17	PES	ESC	115	-63.3	S	0.0415 U	–	–	–	0.000323 U	0.000350 U	0.000447 U	0.000339 U	0.000447 U	0.000243 U	0.000371 U	0.000388 U	0.000374 U	0.000907 U
MW-139 (-30.2 to-40.2)	MW-139-20	9/13/17	PES	ESC	20	19.8	S	–	–	–	–	0.000305 U	0.000331 U	0.000422 U	0.000320 U	0.000422 U	0.000230 U	0.000351 U	0.000367 U	0.000354 U	0.000857 U
	MW-139-31	9/13/17	PES	ESC	31	8.8	S	–	–	–	–	0.000282 U	0.000306 U	0.000391 U	0.000296 U	0.000391 U	0.000213 U	0.000324 U	0.000339 U	0.000327 U	0.000793 U
	MW-139-41	9/13/17	PES	ESC	41	-1.2	S	–	–	–	–	0.000284 U	0.000307 U	0.000392 U	0.000298 U	0.000392 U	0.000214 U	0.000325 U	0.000340 U	0.000329 U	0.000796 U
	MW-139-51	9/13/17	PES	ESC	51	-11.2	S	–	–	–	–	0.000305 U	0.000330 U	0.000421 U	0.000320 U	0.000421 U	0.000230 U	0.000350 U	0.000366 U	0.000353 U	0.000855 U
	MW-139-60	9/13/17	PES	ESC	60	-20.2	S	–	–	–	–	0.000284 U	0.000307 U	0.000392 U	0.000297 U	0.000392 U	0.000214 U	0.000325 U	0.000340 U	0.000329 U	0.000796 U
	MW-139-70	9/13/17	PES	ESC	70	-30.2	S	–	–	–	–	0.000312 U	0.000337 U	0.000431 U	0.000327 U	0.000431 U	0.000235 U	0.000358 U	0.000374 U	0.000361 U	0.000874 U
	MW-139-80	9/13/17	PES	ESC	80	-40.2	S	–	–	–	–	0.000298 U	0.000323 U	0.000412 U	0.000313 U	0.000412 U	0.000225 U	0.000342 U	0.000358 U	0.000346 U	0.000837 U
MW-141 (-55.4 to-65.4)	MW-141-15	9/18/17	PES	ESC	15	24.6	S	–	–	–	–	0.000298 U	0.000323 U	0.000412 U	0.000312 U	0.000412 U	0.000224 U	0.000342 U	0.000358 U	0.000345 U	0.000836 U
	MW-141-35	9/18/17	PES	ESC	35	4.6	S	–	–	–	–	0.000306 U	0.000332 U	0.000423 U	0.000321 U	0.000423 U	0.000231 U	0.000352 U	0.000368 U	0.000355 U	0.000860 U
	MW-141-46	9/18/17	PES	ESC	46	-6.4	S	–	–	–	–	0.000289 U	0.000313 U	0.000399 U	0.000303 U	0.000399 U	0.000218 U	0.000331 U	0.000347 U	0.000335 U	0.000810 U
	MW-141-56	9/18/17	PES	ESC	56	-16.4	S	–	–	–	–	0.000281 U	0.000304 U	0.000388 U	0.000295 U	0.000388 U	0.000212 U	0.000322 U	0.000337 U	0.000325 U	0.000788 U
	MW-141-65	9/18/17	PES	ESC	65	-25.4	S	–	–	–	–	0.000278 U	0.000301 U	0.000384 U	0.000291 U	0.000384 U	0.000209 U	0.000319 U	0.000333 U	0.000322 U	0.000779 U
	MW-141-75	9/18/17	PES	ESC	75	-35.4	S	–	–	–	–	0.000281 U	0.000305 U	0.000389 U	0.000295 U	0.000389 U	0.000212 U	0.000323 U	0.000338 U	0.000326 U	0.000790 U
	MW-141-85	9/18/17	PES	ESC	85	-45.4	S	–	–	–	–	0.000308 U	0.000334 U	0.000426 U	0.000323 U	0.000426 U	0.000232 U	0.000354 U	0.000370 U	0.000357 U	0.000865 U
	MW-141-95	9/18/17	PES	ESC	95	-55.4	S	–	–	–	–	0.000316 U	0.000343 U	0.000437 U	0.000332 U	0.000437 U	0.000238 U	0.000363 U	0.000380 U	0.000367 U	0.000888 U
	MW-141-105	9/19/17	PES	ESC	105	-65.4	S	–	–	–	–	0.000315 U	0.000341 U	0.000436 U	0.000331 U	0.000436 U	0.000238 U	0.000362 U	0.000378 U	0.000365 U	0.000885 U
MW-152 (-10.2 to-20.2)	MW-152-5	3/13/18	PES	ESC	5	34.1	S	–	–	–	–	0.000297 U	0.000322 U	0.000411 U	0.000312 U	0.000411 U	0.000224 U	0.000341 U	0.000357 U	0.000345 U	0.000835 U
	MW-152-15	3/13/18	PES	ESC	15	24.1	S	–	–	–	–	0.000292 U	0.000317 U	0.000404 U	0.000307 U	0.000404 U	0.000220 U	0.000336 U	0.000351 U	0.000339 U	0.000821 U
	MW-152-25	3/13/18	PES	ESC	25	14.1	S	–	–	–	–	0.000286 U	0.000310 U	0.000396 U	0.000300 U	0.000396 U	0.000216 U	**0.000439 J**	0.000344 U	0.000332 U	0.000804 U
	MW-152-35	3/13/18	PES	ESC	35	4.1	S	–	–	–	–	0.000290 U	0.000314 U	0.000400 U	0.000304 U	0.000400 U	0.000218 U	**0.00127**	0.000348 U	0.000336 U	0.000813 U
	MW-152-45	3/13/18	PES	ESC	45	-5.9	S	–	–	–	–	0.000298 U	0.000322 U	0.000411 U	0.000312 U	0.000411 U	0.000224 U	**0.00544**	0.000357 U	0.000345 U	0.000835 U
	MW-152-55	3/13/18	PES	ESC	55	-15.9	S	–	–	–	–	0.000299 U	0.000324 U	0.000413 U	0.000314 U	0.000413 U	0.000225 U	**0.00768**	0.000359 U	0.000347 U	0.000839 U
	MW-152-60	3/13/18	PES	ESC	60	-20.9	S	–	–	–	–	0.000286 U	0.000309 U	0.000395 U	0.000300 U	0.000395 U	0.000215 U	**0.000946 J**	0.000343 U	0.000331 U	0.000802 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
MW-162	MW-162-48	1/28/19	PES	PACE	48	-9.6	S	–	–	–	–	0.0108 U	0.00595 U	0.00844 U	0.0191 U	0.0146 U	0.0124 U	0.0108 U	0.0151 U	0.0135 U	0.110 U
(-61.6 to-71.6)	MW-162-50	1/28/19	PES	PACE	50	-11.6	S	–	–	–	–	0.000584 U	0.000321 U	0.000456 U	0.00103 U	0.000789 U	0.000672 U	**0.00746**	0.000818 U	0.000730 U	0.00596 U
	B-930-50 (dup)	1/28/19	PES	PACE	50	-11.6	S	–	–	–	–	0.000556 U	0.000306 U	0.000434 U	0.000982 U	0.000750 U	0.000639 U	**0.0332**	0.000778 U	0.000695 U	0.00567 U
	MW-162-67	1/28/19	PES	PACE	67	-28.6	S	–	–	–	–	0.000581 U	0.000319 U	0.000453 U	0.00103 U	0.000784 U	0.000668 U	**0.000967 J**	0.000813 U	0.000726 U	0.00592 U
	MW-162-70	1/28/19	PES	PACE	70	-31.6	S	–	–	–	–	0.000558 U	0.000307 U	0.000435 U	0.000986 U	0.000754 U	**0.00197 J**	**0.00885**	0.000781 U	0.000698 U	0.00569 U
	MW-162-72	1/28/19	PES	PACE	72	-33.6	S	–	–	–	–	0.000539 U	0.000297 U	0.000421 U	0.000953 U	0.000728 U	0.000620 U	**0.00311**	0.000755 U	0.000674 U	0.00550 U
	MW-162-80	1/28/19	PES	PACE	80	-41.6	S	–	–	–	–	0.000556 U	0.000306 U	0.000434 U	0.000983 U	0.000751 U	0.000640 U	**0.0199**	0.000779 U	0.000696 U	0.00568 U
	MW-162-85	1/28/19	PES	PACE	85	-46.6	S	–	–	–	–	0.000566 U	0.000311 U	0.000441 U	0.000999 U	0.000764 U	0.000651 U	0.000566 U	0.000792 U	0.000707 U	0.00577 U
	MW-162-90	1/28/19	PES	PACE	90	-51.6	S	–	–	–	–	0.000565 U	0.000311 U	0.000441 U	0.000998 U	0.000763 U	0.000650 U	0.000565 U	0.000791 U	0.000706 U	0.00576 U
	MW-162-95	1/28/19	PES	PACE	95	-56.6	S	–	–	–	–	0.000574 U	0.000316 U	0.000447 U	0.00101 U	0.000774 U	0.000660 U	0.000574 U	0.000803 U	0.000717 U	0.00585 U
	MW-162-100	1/28/19	PES	PACE	100	-61.6	S	–	–	–	–	0.000584 U	0.000321 U	0.000455 U	0.00103 U	0.000788 U	0.000671 U	0.000584 U	0.000817 U	0.000730 U	0.00595 U
	MW-162-105	1/28/19	PES	PACE	105	-66.6	S	–	–	–	–	0.000562 U	0.000309 U	0.000438 U	0.000993 U	0.000759 U	0.000646 U	0.000562 U	0.000787 U	0.000703 U	0.00573 U
	MW-162-110	1/28/19	PES	PACE	110	-71.6	S	–	–	–	–	0.000547 U	0.000301 U	0.000427 U	0.000966 U	0.000739 U	0.000629 U	0.000547 U	0.000766 U	0.000684 U	0.00558 U
MW-163	MW-163-47	1/29/19	PES	PACE	47	-7.7	S	–	–	–	–	0.000559 U	0.000308 U	0.000436 U	0.000988 U	0.000755 U	0.000643 U	**0.00751**	0.000783 U	0.000699 U	0.00570 U
(-61.0 to-71.0)	MW-163-50	1/29/19	PES	PACE	50	-10.7	S	–	–	–	–	0.000540 U	0.000297 U	0.000421 U	0.000954 U	0.000729 U	0.000621 U	**0.0283**	0.000756 U	0.000675 U	0.00551 U
	MW-163-55	1/29/19	PES	PACE	55	-15.7	S	–	–	–	–	0.000613 U	0.000337 U	0.000478 U	0.00108 U	0.000827 U	0.000705 U	**0.0286**	0.000858 U	0.000766 U	0.00625 U
	MW-163-60	1/29/19	PES	PACE	60	-20.7	S	–	–	–	–	0.000566 U	0.000311 U	0.000442 U	0.00100 U	0.000764 U	0.000651 U	**0.0226**	0.000792 U	0.000708 U	0.00577 U
	MW-163-80	1/29/19	PES	PACE	80	-40.7	S	–	–	–	–	0.000569 U	0.000313 U	0.000443 U	0.00100 U	0.000768 U	0.000654 U	**0.00410**	0.000796 U	0.000711 U	0.00580 U
	MW-163-85	1/29/19	PES	PACE	85	-45.7	S	–	–	–	–	0.000592 U	0.000325 U	0.000462 U	0.00105 U	0.000799 U	0.000681 U	0.000592 U	0.000828 U	0.000740 U	0.00604 U
	MW-163-90	1/29/19	PES	PACE	90	-50.7	S	–	–	–	–	0.000542 U	0.000298 U	0.000423 U	0.000958 U	0.000732 U	0.000624 U	**0.00490**	0.000759 U	0.000678 U	0.00553 U
	MW-163-95	1/29/19	PES	PACE	95	-55.7	S	–	–	–	–	0.000593 U	0.000326 U	0.000462 U	0.00105 U	0.000800 U	0.000682 U	**0.00898**	0.000830 U	0.000741 U	0.00605 U
	MW-163-100	1/29/19	PES	PACE	100	-60.7	S	–	–	–	–	0.000574 U	0.000316 U	0.000448 U	0.00101 U	0.000775 U	0.000660 U	0.000574 U	0.000804 U	0.000718 U	0.00586 U
	MW-163-105	1/29/19	PES	PACE	105	-65.7	S	–	–	–	–	0.000525 U	0.000289 U	0.000409 U	0.000927 U	0.000709 U	0.000604 U	0.000525 U	0.000735 U	0.000656 U	0.00535 U
	MW-163-110	1/29/19	PES	PACE	110	-70.7	S	–	–	–	–	0.000554 U	0.000305 U	0.000432 U	0.000978 U	0.000748 U	0.000637 U	0.000554 U	0.000776 U	0.000692 U	0.00565 U
MW-164	MW-164-80	1/24/19	PES	PACE	80	-40.3	S	–	–	–	–	0.000569 U	0.000313 U	0.000444 U	0.00101 U	0.000769 U	0.000655 U	0.000569 U	0.000797 U	0.000712 U	0.00581 U
(-59.9 to-69.9)	MW-164-87	1/24/19	PES	PACE	87	-47.3	S	–	–	–	–	0.000560 U	0.000308 U	0.000437 U	0.000988 U	0.000756 U	0.000644 U	0.000560 U	0.000784 U	0.000700 U	0.00571 U
	MW-164-90	1/24/19	PES	PACE	90	-50.3	S	–	–	–	–	0.000586 U	0.000322 U	0.000457 U	0.00103 U	0.000791 U	0.000673 U	0.000586 U	0.000820 U	0.000732 U	0.00597 U
	MW-164-95	1/25/19	PES	PACE	95	-55.3	S	–	–	–	–	0.000598 U	0.000329 U	0.000466 U	0.00106 U	0.000807 U	0.000688 U	0.000598 U	0.000837 U	0.000747 U	0.00610 U
	MW-164-100	1/25/19	PES	PACE	100	-60.3	S	–	–	–	–	0.000625 U	0.000344 U	0.000488 U	0.00110 U	0.000844 U	0.000719 U	0.000625 U	0.000875 U	0.000781 U	0.00638 U
	MW-164-105	1/25/19	PES	PACE	105	-65.3	S	–	–	–	–	0.000555 U	0.000305 U	0.000433 U	0.000979 U	0.000749 U	0.000638 U	0.000555 U	0.000776 U	0.000693 U	0.00566 U
	MW-164-110	1/25/19	PES	PACE	110	-70.3	S	–	–	–	–	0.000551 U	0.000303 U	0.000430 U	0.000974 U	0.000744 U	0.000634 U	0.000551 U	0.000772 U	0.000689 U	0.00562 U
	B-929-120	1/25/19	PES	PACE	110 (dup)	-70.3	S	–	–	–	–	0.000562 U	0.000309 U	0.000438 U	0.000992 U	0.000758 U	0.000646 U	0.000562 U	0.000786 U	0.000702 U	0.00573 U
MW-168 (-43.0 to -53.0)	MW-168-15	10/21/19	PES	Fremont	15	-3.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-171 (-27.6 to -37.6)	MW-171-24	09/24/19	PES	Fremont	24	-12.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-172 (-42.5 to -52.5)	MW-172-7	09/26/19	PES	Fremont	7	4.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-175	MW-175-12	10/26/19	PES	Fremont	12	-1.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(-27.8 to -37.8)	B-1002-12	10/26/19	PES	Fremont	12 (dup)	-1.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	**–**	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	**–**	**0.030**	**1.5E-07**
MW-180 (-42.7 to -52.7)	MW-180-40	09/25/19	PES	Fremont	40	-28.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW-180-24	09/25/19	PES	Fremont	24	-12.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW-180-27	09/25/19	PES	Fremont	27	-15.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-181 (1.5 to -8.5)	MW-181-14	09/27/19	PES	Fremont	14	-2.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-183 (-27.4 to -37.4)	MW-183-18	09/26/19	PES	Fremont	18	-6.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-184 (-42.5 to -52.5)	MW-184-20	09/26/19	PES	Fremont	20	-8.4	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-188 (-42.2 to -52.2)	MW-188-64	10/01/19	PES	Fremont	64	-52.4	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
P01	P01-05	2/12/14	SES	F&BI	5	35.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	P01-10	2/12/14	SES	F&BI	10	30.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
P02	P02-05	2/12/14	SES	F&BI	5	34.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	P02-07.5	2/12/14	SES	F&BI	7.5	32.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
P03	P03-05	2/12/14	SES	F&BI	5	34.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
P03	P03-07.5	2/12/14	SES	F&BI	7.5	32.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
P04	P04-05	2/12/14	SES	F&BI	7.5	32.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	P04-10	2/12/14	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
P05	P05-05	2/12/14	SES	F&BI	5	35.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	P05-07.5	2/12/14	SES	F&BI	7.5	32.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
P06	P06-07.5	2/12/14	SES	F&BI	7.5	32.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	P06-10	2/12/14	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
R-MW1	Unknown	10/22/92	Roux	Unknown	5	32.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
W-MW-03 (P-07)	SB-W-07-0135	1/26/12	WW	ARI	13.5-14	25.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-07-0275	1/26/12	WW	ARI	27.5-28	11.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-07-0335	1/26/12	WW	ARI	33.5-34	5.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-07-0430	1/26/12	WW	ARI	43-43.5	-4.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-07-0530	1/26/12	WW	ARI	53-53.5	-14.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-07-0630	1/26/12	WW	ARI	63-63.5	-24.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-07-0780	1/26/12	WW	ARI	78-78.5	-39.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
W-MW-04 (P-08)	SB-W-08-0090	1/28/12	WW	ARI	9-9.5	26.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-08-0155	1/28/12	WW	ARI	15.5-16	19.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-08-0265	1/28/12	WW	ARI	26.5-27	8.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-08-0380	1/28/12	WW	ARI	38-38.5	-3.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-08-0480	1/28/12	WW	ARI	48-48.5	-13.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-08-9480	1/28/12	WW	ARI	48-48.5 (dup)	-13.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-08-0590	1/28/12	WW	ARI	59-59.5	-24.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-08-0710	1/29/12	WW	ARI	71-71.5	-36.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-08-0760	1/29/12	WW	ARI	76-76.5	-41.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
All Data						Number of Analytes Measured		100	0	0	0	805	805	805	805	805	805	805	805	805	805
						Number of Analytes Detected		63	0	0	0	5	0	3	3	0	1	244	0	1	0
						Frequency of Detection		63.0%	–	–	–	0.6%	0.0%	0.4%	0.4%	0.0%	0.1%	30.3%	0.0%	0.1%	0.0%
						Maximum Detection		641	–	–	–	0.000757 J	–	0.000889 J	0.00199 J	–	0.00197 J	1.04	–	0.00174 J	–
						Minimum Detection		0.0353 U	–	–	–	0.000264 U	0.000286 U	0.000365 U	0.000277 U	0.000365 U	0.000199 U	0.000315 U	0.000317 U	0.000306 U	0.000741 U
						Number Of Vadose (V) Detections above SL		0	0	0	0	0	0	0	0	0	0	0	–	0	0
						Number of Saturated (S) Detections above SL		8	0	0	0	0	0	0	0	0	0	88	–	0	0
2017-2021						Number of Analytes Measured		100	0	0	0	805	805	805	805	805	805	805	805	805	805
						Number of Analytes Detected		63	0	0	0	5	0	3	3	0	1	244	0	1	0
						Frequency of Detection		63.0%	–	–	–	0.6%	0.0%	0.4%	0.4%	0.0%	0.1%	30.3%	0.0%	0.1%	0.0%
						Maximum Detection		641	–	–	–	0.000757 J	–	0.000889 J	0.00199 J	–	0.00197 J	1.04	–	0.00174 J	–
						Minimum Detection		0.0353 U	–	–	–	0.000264 U	0.000286 U	0.000365 U	0.000277 U	0.000365 U	0.000199 U	0.000315 U	0.000317 U	0.000306 U	0.000741 U
						Number Of Vadose (V) Detections above SL		0	0	0	0	0	0	0	0	0	0	0	–	0	0
						Number of Saturated (S) Detections above SL		8	0	0	0	0	0	0	0	0	0	88	–	0	0

Abbreviations:
AAL = Alden Analytical Laboratories, Inc., of Seattle, Washington
ARI = Analytical Resource, Incorporated, Seattle, Washington
B&V = Black Veatch
bgs = below ground surface
Comp = Composite Sample
dup = duplicate
EPJ = E.PJohnson Construction Inc., and Environmental
ESC = ESC Lab Services of Mt. Juliet, Tennessee
F&BI = Friedman & Bruya, Inc.
GeoEng = GeoEngineers, Inc.
HC = Hart Crowser, Inc.
NCA = North Creek Analytical, of Bothell, Washington
OnSite = OnSite Environmental Inc., of Redmond, Washington
Pace = Pace Analytical of Mt. Juliet, Tennessee (formerly ESC)
PES = PES Environmental, Inc.
Retec = Remediation Technologies, Inc.
Roux = Roux Associates
SES = SoundEarth Strategies, Inc.
TR = TR Corporation
Urban = Urban Redevelopment LLC
WW = WW Environmental LLC

Notes:
All on-Property soil was excavated during Property redevelopment above elevations 0.7 to 10.7 feet, and CVOCs in soil between elevations +10 to 55 feet was treated.
Petroleum Hydrocarbons (PHCs) analyzed by Ecology Methods NWTPH-HCID, NWTPH-Gx, or NWTPH-Dx; or EPA Method 418.1, Method 8020, or Method 8015M.
VOCs analyzed by EPA Methods 8010, 8020, 8021B, 624/8240, or 8260B/C/D.
Well screen elevations provided below Sample Location. in parentheses when appliable.
PCUL = Preliminary Cleanup Level from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021. PCULs based on the practical quantitation limits (PQLs) italicized.
Detected results shown in **bold**.
Detections above the screening level in the vadose zone are shown in **bold** and **highlighted blue**.
Detections above the screening level in the saturated zone are shown in **bold and highlighted gray.**
– = Not available or results not analyzed.
A = Result reported as total petroleum hydrocarbons.
B = Analyte detected in an associated method blank.
J = The reported concentration is an estimate based on detectable results between the method detection limit and reporting limit, laboratory QA/QC, or data validation review.
J+ = The result is an estimated quantity, but the result may be biased high.
J- = The result is an estimated quantity, but the result may be biased low.
ND = Not detected above laboratory reporting limit. Reporting limit not available.
q = Sample may contain gasoline or petroleum components. Chromatographic pattern indicates the presence of gasoline constituents.
R = The data is unusable. The sample result is rejected due to serious deficiencies in meeting QC criteria. The analyte may or may not be present in the sample
T = Analyte also detected in trip blank.
U = Not detected at a concentration exceeding laboratory reporting limit
ve = Estimated value. The reported range exceeds the calibration range of the analysis.
w = Petroleum product eluting in the C8-C9 range
x = The sample chromatographic pattern does not resemble the fuel standard used for quantitation.
z = Gasoline/petroleum detection result is likely elevated due to high detections of CVOCs.

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	**–**	**0.88**	**1.2**	**–**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	**–**	**0.058**	**0.068**	**–**
B-1	B-1-13	6/23/00	TR	ARI	13	27.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
B-2	B-2-6.5	6/23/00	TR	ARI	6.5	33.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B-2-11	6/23/00	TR	ARI	11	29.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B-2-16	6/23/00	TR	ARI	16	24.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
B-3	B-3-12	6/23/00	TR	ARI	12	28.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
B-5	B-5-10	6/23/00	TR	ARI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B-5-11.5	6/23/00	TR	ARI	11.5	28.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
B-6	B-6-6	6/24/00	TR	ARI	6	34.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B-6-12	6/24/00	TR	ARI	12	28.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B-6-18	6/24/00	TR	ARI	18	22.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
B-7	B-7-6	6/24/00	TR	ARI	6	34.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
B-8	B-8-4	6/24/00	TR	ARI	4	36.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B-8-8	6/24/00	TR	ARI	8	32.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
B-9	B-9-4	6/24/00	TR	ARI	4	36.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B-9-8	6/24/00	TR	ARI	8	32.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
B-10	B-10-12	6/24/00	TR	ARI	12	28.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
B-201	G-201-10	6/19/17	PES	ESC	10	29.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	G-201-30	6/19/17	PES	ESC	30	9.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	G-201-35	6/19/17	PES	ESC	35	4.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
B-202	G-202-5	6/19/17	PES	ESC	5	34.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	G-202-20	6/19/17	PES	ESC	20	19.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	G-202-50	6/19/17	PES	ESC	50	-10.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
B-203	G-203-5	6/20/17	PES	ESC	5	34.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	G-203-25	6/20/17	PES	ESC	25	14.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	G-203-40	6/20/17	PES	ESC	40	-0.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	G-203-50	6/20/17	PES	ESC	50	-10.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	G-203-80	6/20/17	PES	ESC	80	-40.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
B-204	G-204-20	6/20/17	PES	ESC	20	19.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	G-204-40	6/20/17	PES	ESC	40	-0.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	G-204-45	6/20/17	PES	ESC	45	-5.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
B-205	B-205-10	8/30/17	PES	ESC	10	30.3	S	**5.03**	0.0468 U	**17.0**	0.127 U	0.0414 U	0.0368 U	0.0320 U	0.0432 U	**3.37**	0.0288 U	0.0250 U	0.0273 U	0.0336 U
	B-205-55	8/30/17	PES	ESC	55	-14.7	S	0.000335 U	0.000453 U	0.00617 U	0.00123 U	0.000401 U	0.000356 U	0.000310 U	0.000418 U	0.000311 U	0.000279 U	0.000242 U	0.000264 U	0.000326 U
	B-205-65	8/30/17	PES	ESC	65	-24.7	S	0.000304 U	0.000411 U	0.000223 U	0.00111 U	0.000363 U	0.000323 U	0.000281 U	0.000379 U	0.000282 U	0.000253 U	0.000219 U	0.000239 U	0.000295 U
	B-205-75	8/30/17	PES	ESC	75	-34.7	S	0.000307 U	0.000416 U	0.000226 U	0.00112 U	0.000367 U	0.000327 U	0.000284 U	0.000383 U	0.000285 U	0.000256 U	0.000222 U	0.000242 U	0.000299 U
	B-904-50	8/30/17	PES	ESC	75 (dup)	-34.7	S	0.000308 U	0.000416 U	0.000226 U	0.00113 U	0.000368 U	0.000327 U	0.000284 U	0.000384 U	0.000285 U	0.000256 U	0.000222 U	0.000242 U	0.000299 U
B-206	B-206-15	8/14/17	PES	ESC	15	24.1	S	0.00826 U	0.0112 U	**0.0151 J**	0.0302 U	0.00987 U	0.00877 U	0.00762 U	0.0103 U	0.00765 U	0.00688 U	0.00596 U	0.00650 U	0.00803 U
	B-206-30	8/14/17	PES	ESC	30	9.1	S	0.000329 U	0.000445 U	0.000242 U	0.00120 U	0.000393 U	0.000350 U	0.000304 U	0.000411 U	0.000305 U	0.000274 U	0.000237 U	0.000259 U	0.000320 U
	B-206-40	8/14/17	PES	ESC	40	-0.9	S	0.000303 U	0.000410 U	0.000223 U	0.00111 U	0.000363 U	0.000322 U	0.000280 U	0.000378 U	0.000281 U	0.000253 U	0.000219 U	0.000239 U	0.000295 U
	B-206-49	8/14/17	PES	ESC	49	-9.9	S	0.000327 U	0.000442 U	0.000240 U	0.00120 U	0.000391 U	0.000347 U	0.000302 U	0.000408 U	0.000303 U	0.000272 U	0.000236 U	0.000257 U	0.000318 U
	B-206-52	8/14/17	PES	ESC	52	-12.9	S	0.000313 U	0.000424 U	0.000230 U	0.00115 U	0.000375 U	0.000333 U	0.000289 U	0.000391 U	0.000290 U	0.000261 U	0.000226 U	0.000247 U	0.000305 U
	B-206-56	8/14/17	PES	ESC	56	-16.9	S	0.000315 U	0.000426 U	0.000232 U	0.00115 U	0.000377 U	0.000335 U	0.000291 U	0.000393 U	0.000292 U	0.000263 U	0.000227 U	0.000248 U	0.000306 U
	B-206-59	8/14/17	PES	ESC	59	-19.9	S	0.000299 U	0.000404 U	0.000219 U	0.00109 U	0.000357 U	0.000317 U	0.000276 U	0.000372 U	0.000277 U	0.000249 U	0.000215 U	0.000235 U	0.000290 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
B-206	B-206-70	8/14/17	PES	ESC	70	-30.9	S	0.000313 U	0.000423 U	0.000230 U	0.00114 U	0.000374 U	0.000332 U	0.000289 U	0.000390 U	0.000290 U	0.000260 U	0.000226 U	0.000246 U	0.000304 U
(continued)	B-206-80	8/14/17	PES	ESC	80	-40.9	S	0.000313 U	0.000423 U	0.000230 U	0.00114 U	0.000374 U	0.000332 U	0.000289 U	0.000390 U	0.000290 U	0.000261 U	0.000226 U	0.000246 U	0.000304 U
B-207	B-207-30	8/25/17	PES	ESC	30	8.5	S	0.00816 U	0.0110 U	0.00600 U	0.0298 U	0.00975 U	0.00866 U	0.00752 U	0.0102 U	0.00756 U	0.00679 U	0.00589 U	0.00642 U	0.00793 U
	B-207-41	8/25/17	PES	ESC	41	-2.5	S	0.000325 U	0.000439 U	0.000239 U	0.00119 U	0.000388 U	0.000345 U	0.000300 U	0.000405 U	0.000301 U	0.000271 U	0.000234 U	0.000256 U	0.000316 U
	B-207-49	8/25/17	PES	ESC	49	-10.5	S	0.000320 U	0.000433 U	0.000235 U	0.00117 U	0.000383 U	0.000340 U	0.000296 U	0.000399 U	0.000297 U	0.000267 U	0.000231 U	0.000252 U	0.000311 U
	B-207-55	8/25/17	PES	ESC	55	-16.5	S	0.000335 U	0.000453 U	0.000246 U	0.00123 U	0.000400 U	0.000356 U	0.000309 U	0.000418 U	0.000311 U	0.000279 U	0.000242 U	0.000264 U	0.000326 U
	B-207-60	8/25/17	PES	ESC	60	-21.5	S	0.000305 U	0.000413 U	0.000225 U	0.00112 U	0.000365 U	0.000325 U	0.000282 U	0.000381 U	0.000283 U	0.000254 U	0.000220 U	0.000241 U	0.000297 U
	B-207-70	8/25/17	PES	ESC	70	-31.5	S	0.000328 U	0.000443 U	0.000241 U	0.00120 U	0.000392 U	0.000348 U	0.000303 U	0.000409 U	0.000304 U	0.000273 U	0.000236 U	0.000258 U	0.000319 U
	B-207-80	8/25/17	PES	ESC	80	-41.5	S	0.000316 U	0.000427 U	0.000232 U	0.00116 U	0.000378 U	0.000336 U	0.000292 U	0.000394 U	0.000293 U	0.000263 U	0.000228 U	0.000249 U	0.000307 U
	B-207-90	8/25/17	PES	ESC	90	-51.5	S	0.00789 U	0.0107 U	0.00580 U	0.0288 U	0.00943 U	0.00837 U	0.00727 U	0.00983 U	0.00731 U	0.00657 U	0.00569 U	0.00621 U	0.00767 U
B-208	B-208-20	8/24/17	PES	ESC	20	18.8	S	0.000339 U	0.000459 U	0.000249 U	0.00124 U	0.000405 U	0.000360 U	0.000313 U	0.000423 U	0.000314 U	0.000282 U	0.000245 U	0.000267 U	0.000330 U
	B-208-35	8/24/17	PES	ESC	35	3.8	S	0.000312 U	0.000422 U	0.000230 U	0.00114 U	0.000373 U	0.000332 U	0.000288 U	0.000390 U	0.000289 U	0.000260 U	0.000225 U	0.000246 U	0.000304 U
	B-901-50	8/24/17	PES	ESC	35 (dup)	3.8	S	0.000325 U	0.000439 U	0.000239 U	0.00119 U	0.000388 U	0.000345 U	0.000300 U	0.000405 U	0.000301 U	0.000270 U	0.000234 U	0.000256 U	0.000316 U
	B-208-50	8/24/17	PES	ESC	50	-11.2	S	0.000317 U	0.000428 U	0.000233 U	0.00116 U	0.000379 U	0.000337 U	0.000293 U	0.000395 U	0.000294 U	0.000264 U	0.000229 U	0.000250 U	0.000308 U
	B-208-60	8/24/17	PES	ESC	60	-21.2	S	0.000320 U	0.000432 U	0.000235 U	0.00117 U	0.000382 U	0.000340 U	0.000295 U	0.000399 U	0.000296 U	0.000266 U	0.000231 U	0.000252 U	0.000311 U
	B-208-70	8/24/17	PES	ESC	70	-31.2	S	0.000320 U	0.000433 U	0.000236 U	0.00117 U	0.000383 U	0.000341 U	0.000296 U	0.000400 U	0.000297 U	0.000267 U	0.000231 U	0.000252 U	0.000312 U
	B-208-80	8/24/17	PES	ESC	80	-41.2	S	0.000355 U	0.000480 U	0.000261 U	0.00130 U	0.000424 U	0.000377 U	0.000328 U	0.000443 U	0.000329 U	0.000296 U	0.000256 U	0.000280 U	0.000345 U
B-209	B-209-20	8/25/17	PES	ESC	20	19.0	S	0.000334 U	0.000451 U	0.000245 U	0.00122 U	0.000399 U	0.000354 U	0.000308 U	0.000416 U	0.000309 U	0.000278 U	0.000241 U	0.000263 U	0.000324 U
	B-209-35	8/25/17	PES	ESC	35	4.0	S	0.000307 U	0.000414 U	0.000225 U	0.00112 U	0.000366 U	0.000326 U	0.000283 U	0.000382 U	0.000284 U	0.000255 U	0.000221 U	0.000241 U	0.000298 U
	B-209-50	8/25/17	PES	ESC	50	-11.0	S	0.000374 U	0.000506 U	0.000275 U	0.00137 U	0.000447 U	0.000398 U	0.000346 U	0.000467 U	0.000347 U	0.000312 U	0.000270 U	0.000295 U	0.000364 U
	B-209-60	8/25/17	PES	ESC	60	-21.0	S	0.000329 U	0.000445 U	0.000242 U	0.00121 U	0.000394 U	0.000350 U	0.000304 U	0.000411 U	0.000305 U	0.000274 U	0.000238 U	0.000259 U	0.000320 U
	B-209-70	8/25/17	PES	ESC	70	-31.0	S	0.000306 U	0.000413 U	0.000225 U	0.00112 U	0.000366 U	0.000325 U	0.000282 U	0.000381 U	0.000283 U	0.000255 U	0.000221 U	0.000241 U	0.000297 U
	B-209-75	8/25/17	PES	ESC	75	-36.0	S	0.000304 U	0.000411 U	0.000224 U	0.00111 U	0.000364 U	0.000323 U	0.000281 U	0.000380 U	0.000282 U	0.000253 U	0.000220 U	0.000240 U	0.000296 U
	B-209-80	8/25/17	PES	ESC	80	-41.0	S	0.000330 U	0.000446 U	0.000243 U	0.00121 U	0.000394 U	0.000351 U	0.000305 U	0.000411 U	0.000306 U	0.000275 U	0.000238 U	0.000260 U	0.000321 U
B-210	B-210-6	8/21/17	PES	ESC	6	33.4	S	0.000338 U	0.000457 U	0.000249 U	0.00124 U	0.000404 U	0.000360 U	0.000312 U	0.000422 U	0.000314 U	0.000282 U	0.000244 U	0.000266 U	0.000329 U
	B-210-15	8/21/17	PES	ESC	15	24.4	S	0.00778 U	0.0105 U	0.00572 U	0.0284 U	0.00930 U	0.00826 U	0.00717 U	0.00970 U	0.00721 U	0.00648 U	0.00561 U	0.00612 U	0.00756 U
	B-210-20	8/21/17	PES	ESC	20	19.4	S	0.000320 U	0.000432 U	0.000235 U	0.00117 U	0.000382 U	0.000340 U	0.000295 U	0.000399 U	0.000296 U	0.000266 U	0.000231 U	0.000252 U	0.000311 U
	B-210-35	8/21/17	PES	ESC	35	4.4	S	0.000331 U	0.000448 U	0.000244 U	0.00121 U	0.000396 U	0.000352 U	0.000306 U	0.000413 U	0.000307 U	0.000276 U	0.000239 U	0.000261 U	0.000322 U
	B-210-46	8/21/17	PES	ESC	46	-6.6	S	0.000313 U	0.000423 U	0.000230 U	0.00114 U	0.000374 U	0.000332 U	0.000289 U	0.000390 U	0.000290 U	0.000260 U	0.000226 U	0.000246 U	0.000304 U
	B-210-60	8/22/17	PES	ESC	60	-20.6	S	0.00771 U	0.0104 U	0.00567 U	0.0281 U	0.00921 U	0.00818 U	0.00710 U	0.00961 U	0.00714 U	0.00642 U	0.00556 U	0.00606 U	0.00749 U
	B-210-70	8/22/17	PES	ESC	70	-30.6	S	0.000310 U	0.000419 U	0.000228 U	0.00113 U	0.000370 U	0.000329 U	0.000286 U	0.000386 U	0.000287 U	0.000258 U	0.000223 U	0.000244 U	0.000301 U
	B-210-80	8/22/17	PES	ESC	80	-40.6	S	0.000317 U	0.000429 U	0.000233 U	0.00116 U	0.000379 U	0.000337 U	0.000293 U	0.000395 U	0.000294 U	0.000264 U	0.000229 U	0.000250 U	0.000308 U
	B-900-20	8/22/17	PES	ESC	80 (dup)	-40.6	S	0.000341 U	0.000461 U	0.000251 U	0.00125 U	0.000407 U	0.000362 U	0.000315 U	0.000425 U	0.000316 U	0.000284 U	0.000246 U	0.000268 U	0.000331 U
B-211	B-211-20	8/17/17	PES	ESC	20	19.8	S	0.000320 U	0.000433 U	0.000236 U	0.00117 U	0.000383 U	0.000341 U	0.000296 U	0.000400 U	0.000297 U	0.000267 U	0.000231 U	0.000252 U	0.000312 U
	B-211-35	8/17/17	PES	ESC	35	4.8	S	0.000323 U	0.000437 U	0.000238 U	0.00118 U	0.000386 U	0.000343 U	0.000298 U	0.000403 U	0.000299 U	0.000269 U	0.000233 U	0.000254 U	0.000314 U
	B-211-50	8/17/17	PES	ESC	50	-10.3	S	0.000310 U	0.000420 U	0.000228 U	0.00114 U	0.000371 U	0.000330 U	0.000287 U	0.000387 U	0.000288 U	0.000258 U	0.000224 U	0.000244 U	0.000302 U
	B-211-57	8/17/17	PES	ESC	57	-17.3	S	0.000338 U	0.000458 U	0.000249 U	0.00124 U	0.000405 U	0.000360 U	0.000313 U	0.000422 U	0.000314 U	0.000282 U	0.000244 U	0.000267 U	0.000329 U
	B-211-60	8/17/17	PES	ESC	60	-20.3	S	0.000331 U	0.000447 U	0.000243 U	0.00121 U	0.000396 U	0.000352 U	0.000306 U	0.000413 U	0.000307 U	0.000276 U	0.000239 U	0.000261 U	0.000322 U
	B-211-65	8/18/17	PES	ESC	65	-25.3	S	0.000324 U	0.000438 U	0.000238 U	0.00119 U	0.000387 U	0.000344 U	0.000299 U	0.000404 U	0.000300 U	0.000270 U	0.000234 U	0.000255 U	0.000315 U
	B-211-70	8/18/17	PES	ESC	70	-30.3	S	0.172 U	0.232 U	0.127 U	0.628 U	0.206 U	0.182 U	0.158 U	0.214 U	0.159 U	0.144 U	0.124 U	0.135 U	0.168 U
	B-211-80	8/18/17	PES	ESC	80	-40.3	S	0.00778 U	0.0105 U	0.00572 U	0.0284 U	0.00929 U	0.00825 U	0.00717 U	0.00969 U	0.00720 U	0.00648 U	0.00561 U	0.00612 U	0.00756 U
	B-211-90	8/18/17	PES	ESC	90	-50.3	S	0.00837 U	0.0113 U	0.00615 U	0.0305 U	0.0100 U	0.00888 U	0.00772 U	0.0104 U	0.00775 U	0.00697 U	0.00604 U	0.00659 U	0.00814 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
B-211 (continued)	B-211-100	8/18/17	PES	ESC	100	-60.3	S	0.000333 U	0.000450 U	0.000245 U	0.00122 U	0.000398 U	0.000354 U	0.000308 U	0.000416 U	0.000309 U	0.000277 U	0.000240 U	0.000262 U	0.000324 U
	B-211-110	8/18/17	PES	ESC	110	-70.3	S	0.000316 U	0.000428 U	0.000233 U	0.00116 U	0.000378 U	0.000336 U	0.000292 U	0.000395 U	0.000293 U	0.000264 U	0.000228 U	0.000249 U	0.000308 U
	B-211-120	8/21/17	PES	ESC	120	-80.3	S	0.000322 U	0.000435 U	0.000237 U	0.00118 U	0.000385 U	0.000342 U	0.000297 U	0.000402 U	0.000298 U	0.000268 U	0.000232 U	0.000254 U	0.000313 U
B-216	B-216-20	9/1/17	PES	ESC	20	31.9	S	0.000309 U	0.000418 U	0.000227 U	0.00113 U	0.000369 U	0.000329 U	0.000285 U	0.000386 U	0.000287 U	0.000257 U	0.000223 U	0.000243 U	0.000301 U
	B-216-40	9/1/17	PES	ESC	40	11.9	S	0.000311 U	0.000421 U	0.000229 U	0.00114 U	0.000372 U	0.000331 U	0.000287 U	0.000388 U	0.000289 U	0.000259 U	0.000225 U	0.000245 U	0.000303 U
	B-216-50	9/1/17	PES	ESC	50	1.9	S	0.000310 U	0.000419 U	0.000228 U	0.00113 U	0.000371 U	0.000330 U	0.000286 U	0.000387 U	0.000288 U	0.000258 U	0.000224 U	0.000244 U	0.000302 U
	B-216-55	9/1/17	PES	ESC	55	-3.1	S	**0.00117**	0.000437 U	**0.00330**	0.00118 U	0.000386 U	0.000343 U	0.000298 U	0.000403 U	**0.000732 J**	0.000269 U	0.000233 U	0.000254 U	0.000314 U
	B-216-65	9/1/17	PES	ESC	65	-13.1	S	0.000345 U	0.000466 U	0.000253 U	0.00126 U	0.000412 U	0.000366 U	0.000318 U	0.000430 U	0.000319 U	0.000287 U	0.000248 U	0.000271 U	0.000335 U
	B-216-85	9/1/17	PES	ESC	85	-33.1	S	0.000346 U	0.000468 U	0.000254 U	0.00127 U	0.000414 U	0.000368 U	0.000320 U	0.000432 U	0.000321 U	0.000288 U	0.000250 U	0.000273 U	0.000336 U
	B-216-95	9/1/17	PES	ESC	95	-43.1	S	0.000326 U	0.000441 U	0.000240 U	0.00119 U	0.000390 U	0.000347 U	0.000301 U	0.000407 U	0.000302 U	0.000272 U	0.000235 U	0.000257 U	0.000317 U
B-217	B-217-15	9/5/17	PES	ESC	15	36.8	V	0.000326 U	0.000440 U	0.000239 U	0.00119 U	0.000389 U	0.000346 U	0.000301 U	0.000406 U	0.000302 U	0.000271 U	0.000235 U	0.000256 U	0.000317 U
	B-217-25	9/5/17	PES	ESC	25	26.8	S	0.000318 U	0.000430 U	0.000234 U	0.00116 U	0.000380 U	0.000338 U	0.000294 U	0.000397 U	0.000295 U	0.000265 U	0.000230 U	0.000251 U	0.000309 U
	B-217-35	9/5/17	PES	ESC	35	16.8	S	0.000329 U	0.000445 U	0.000242 U	0.00121 U	0.000394 U	0.000350 U	0.000304 U	0.000411 U	0.000305 U	0.000274 U	0.000238 U	0.000259 U	0.000320 U
	B-217-42	9/5/17	PES	ESC	42	9.8	S	**0.000383 J**	0.000444 U	**0.00113 J**	0.00120 U	0.000392 U	0.000349 U	0.000303 U	0.000409 U	**0.000471 J**	0.000273 U	0.000237 U	0.000258 U	0.000319 U
	B-217-55	9/5/17	PES	ESC	55	-3.2	S	0.000333 U	0.000450 U	0.000245 U	0.00122 U	0.000398 U	0.000354 U	0.000308 U	0.000416 U	0.000309 U	0.000277 U	0.000240 U	0.000262 U	0.000324 U
	B-217-65	9/5/17	PES	ESC	65	-13.2	S	0.000330 U	0.000447 U	0.000243 U	0.00121 U	0.000395 U	0.000351 U	0.000305 U	0.000412 U	0.000306 U	0.000275 U	0.000238 U	0.000260 U	0.000321 U
	B-217-75	9/5/17	PES	ESC	75	-23.2	S	0.000344 U	0.000465 U	0.000253 U	0.00126 U	0.000411 U	0.000365 U	0.000317 U	0.000429 U	0.000319 U	0.000286 U	0.000248 U	0.000271 U	0.000334 U
	B-217-85	9/6/17	PES	ESC	85	-33.2	S	0.000327 U	0.000442 U	0.000240 U	0.00120 U	0.000391 U	0.000347 U	0.000302 U	0.000408 U	0.000303 U	0.000272 U	0.000236 U	0.000257 U	0.000318 U
	B-217-95	9/6/17	PES	ESC	95	-43.2	S	0.000347 U	0.000469 U	0.000255 U	0.00127 U	0.000415 U	0.000369 U	0.000320 U	0.000433 U	0.000322 U	0.000289 U	0.000250 U	0.000273 U	0.000337 U
	B-217-106	9/6/17	PES	ESC	106	-54.2	S	0.0352 U	0.0476 U	0.0259 U	0.129 U	0.0420 U	0.0374 U	0.0325 U	0.0439 U	0.0326 U	0.0293 U	0.0254 U	0.0277 U	0.0342 U
	B-217-115	9/6/17	PES	ESC	115	-63.2	S	0.000331 U	0.000448 U	0.000244 U	0.00121 U	0.000396 U	0.000352 U	0.000306 U	0.000413 U	0.000307 U	0.000276 U	0.000239 U	0.000261 U	0.000322 U
B-218	B-218-12.5	9/19/17	PES	ESC	12.5	25.6	S	0.000327 U	0.000442 U	0.000240 U	0.00120 U	0.000391 U	0.000347 U	0.000302 U	0.000408 U	0.000303 U	0.000272 U	0.000236 U	0.000257 U	0.000318 U
	B-218-19	9/19/17	PES	ESC	19	19.1	S	0.000326 U	0.000440 U	0.000239 U	0.00119 U	0.000389 U	0.000346 U	0.000301 U	0.000406 U	0.000302 U	0.000271 U	0.000235 U	0.000257 U	0.000317 U
	B-218-25	9/19/17	PES	ESC	25	13.1	S	0.000332 U	0.000449 U	0.000244 U	0.00122 U	0.000397 U	0.000353 U	0.000307 U	0.000415 U	0.000308 U	0.000277 U	0.000240 U	0.000262 U	0.000323 U
	B-218-40	9/19/17	PES	ESC	40	-1.9	S	0.0177 U	0.0238 U	0.0130 U	0.0646 U	0.0211 U	0.0188 U	0.0162 U	0.0220 U	0.0164 U	0.0147 U	0.0127 U	0.0138 U	0.0171 U
	B-218-50	9/19/17	PES	ESC	50	-11.9	S	0.000306 U	0.000414 U	0.000225 U	0.00112 U	0.000366 U	0.000325 U	0.000283 U	0.000382 U	0.000284 U	0.000255 U	0.000221 U	0.000241 U	0.000297 U
	B-913-70	9/19/17	PES	ESC	50 (dup)	-11.9	S	0.000305 U	0.000412 U	0.000224 U	0.00111 U	0.000364 U	0.000324 U	0.000281 U	0.000380 U	0.000282 U	0.000254 U	0.000220 U	0.000240 U	0.000296 U
B-219	B-219-42	8/28/17	PES	ESC	42	-2.2	S	0.000313 U	0.000423 U	0.000230 U	0.00114 U	0.000374 U	0.000332 U	0.000289 U	0.000390 U	0.000290 U	0.000260 U	0.000225 U	0.000246 U	0.000304 U
	B-219-50	8/28/17	PES	ESC	50	-10.2	S	0.000340 U	0.000459 U	0.000250 U	0.00124 U	0.000406 U	0.000361 U	0.000314 U	0.000424 U	0.000315 U	0.000283 U	0.000245 U	0.000268 U	0.000330 U
	B-219-60	8/28/17	PES	ESC	60	-20.2	S	0.000309 U	0.000418 U	0.000227 U	0.00113 U	0.000369 U	0.000328 U	0.000285 U	0.000385 U	0.000286 U	0.000257 U	0.000223 U	0.000243 U	0.000300 U
	B-219-70	8/28/17	PES	ESC	70	-30.2	S	0.000328 U	0.000443 U	0.000241 U	0.00120 U	0.000391 U	0.000348 U	0.000302 U	0.000409 U	0.000304 U	0.000273 U	0.000236 U	0.000258 U	0.000318 U
	B-219-80	8/28/17	PES	ESC	80	-40.2	S	0.00780 U	0.000421 U	0.00573 U	0.00114 U	0.000373 U	0.000331 U	0.000288 U	0.000389 U	0.000289 U	0.000260 U	0.000225 U	0.000245 U	0.00758 U
B-220	B-220-15	9/20/17	PES	ESC	15	23.9	S	0.000326 U	0.000441 U	0.000240 U	0.00119 U	0.000390 U	0.000347 U	0.000301 U	0.000407 U	0.000302 U	0.000272 U	0.000235 U	0.000257 U	0.000317 U
	B-220-29	9/20/17	PES	ESC	29	9.9	S	0.000334 U	0.000451 U	**0.000401 J**	0.00122 U	0.000399 U	0.000354 U	0.000308 U	0.000416 U	0.000309 U	0.000278 U	0.000241 U	0.000263 U	0.000324 U
	B-220-32	9/20/17	PES	ESC	32	6.9	S	0.000327 U	0.000443 U	**0.000410 J**	0.00120 U	0.000391 U	0.000348 U	0.000302 U	0.000408 U	0.000303 U	0.000273 U	0.000236 U	0.000258 U	0.000318 U
	B-220-40	9/20/17	PES	ESC	40	-1.1	S	0.000319 U	0.000431 U	0.000234 U	0.00117 U	0.000381 U	0.000339 U	0.000294 U	0.000397 U	0.000295 U	0.000265 U	0.000230 U	0.000251 U	0.000310 U
	B-220-50	9/20/17	PES	ESC	50	-11.1	S	0.000309 U	0.000417 U	0.000227 U	0.00113 U	0.000369 U	0.000328 U	0.000285 U	0.000385 U	0.000286 U	0.000257 U	0.000223 U	0.000243 U	0.000300 U
	B-914-75	9/20/17	PES	ESC	50 (dup)	-11.1	S	0.000309 U	0.000417 U	0.000227 U	0.00113 U	0.000369 U	0.000328 U	0.000285 U	0.000385 U	0.000286 U	0.000257 U	0.000223 U	0.000243 U	0.000300 U
B-221	B-221-16	9/20/17	PES	ESC	16	23.0	S	0.00841 U	0.0114 U	0.00619 U	0.0307 U	0.0101 U	0.00893 U	0.00776 U	0.0105 U	0.00779 U	0.00701 U	0.00607 U	0.00662 U	0.00818 U
	B-221-22	9/20/17	PES	ESC	22	17.0	S	0.330 U	0.446 U	0.243 U	1.21 U	0.395 U	0.351 U	0.305 U	0.412 U	0.306 U	0.275 U	0.238 U	0.260 U	0.321 U
	B-221-33	9/20/17	PES	ESC	33	6.0	S	0.321 U	0.434 U	0.236 U	1.18 U	0.384 U	0.341 U	0.297 U	0.401 U	0.298 U	0.268 U	0.232 U	0.253 U	0.312 U
	B-221-37	9/20/17	PES	ESC	37	2.0	S	0.0675 U	0.0912 U	0.0496 U	0.247 U	0.0807 U	0.0717 U	0.0623 U	0.0842 U	0.0626 U	0.0562 U	0.0487 U	0.0531 U	0.0656 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
B-221 (continued)	B-915-80	9/20/17	PES	ESC	37 (dup)	2.0	S	0.0329 U	0.0445 U	0.0242 U	0.120 U	0.0393 U	0.0350 U	0.0304 U	0.0410 U	0.0305 U	0.0274 U	0.0237 U	0.0259 U	0.0320 U
	B-221-45	9/20/17	PES	ESC	45	-6.0	S	3.15 U	4.26 U	2.31 U	11.5 U	3.76 U	3.35 U	2.91 U	3.93 U	2.92 U	2.62 U	2.27 U	2.48 U	3.06 U
	B-221-50	9/20/17	PES	ESC	50	-11.0	S	0.157 U	0.211 U	0.115 U	0.571 U	0.187 U	0.165 U	0.144 U	0.195 U	0.145 U	0.131 U	0.113 U	0.123 U	0.152 U
	B-221-60	9/20/17	PES	ESC	60	-21.0	S	0.159 U	0.214 U	0.117 U	0.580 U	0.190 U	0.168 U	0.146 U	0.198 U	0.147 U	0.133 U	0.115 U	0.125 U	0.155 U
	B-221-70	9/21/17	PES	ESC	70	-31.0	S	0.000317 U	0.000428 U	0.000233 U	0.00116 U	0.000379 U	0.000337 U	0.000293 U	0.000395 U	0.000294 U	0.000264 U	0.000228 U	0.000249 U	0.000308 U
B-222	B-222-17	9/21/17	PES	ESC	17	22.2	S	0.000325 U	0.000440 U	0.000239 U	0.00119 U	0.000389 U	0.000346 U	0.000300 U	0.000406 U	0.000302 U	0.000271 U	0.000235 U	0.000256 U	0.000316 U
	B-222-25	9/21/17	PES	ESC	25	14.2	S	0.000332 U	0.000448 U	0.000244 U	0.00121 U	0.000396 U	0.000353 U	0.000306 U	0.000414 U	0.000307 U	0.000276 U	0.000239 U	0.000261 U	0.000322 U
	B-222-34	9/21/17	PES	ESC	34	5.2	S	0.000322 U	0.000435 U	0.000236 U	0.00118 U	0.000384 U	0.000342 U	0.000297 U	0.000401 U	0.000298 U	0.000268 U	0.000232 U	0.000253 U	0.000313 U
	B-222-42	9/21/17	PES	ESC	42	-2.8	S	0.000356 U	0.000481 U	0.000262 U	0.00130 U	0.000425 U	0.000378 U	0.000329 U	0.000444 U	0.000330 U	0.000296 U	0.000257 U	0.000280 U	0.000346 U
	B-222-50	9/21/17	PES	ESC	50	-10.8	S	0.0154 U	0.0208 U	0.0114 U	0.0563 U	0.0184 U	0.0163 U	0.0142 U	0.0192 U	0.0143 U	0.0129 U	0.0112 U	0.0121 U	0.0150 U
	B-916-30	9/21/17	PES	ESC	50 (dup)	-10.8	S	0.000304 U	0.000411 U	0.000224 U	0.00111 U	0.000364 U	0.000323 U	0.000281 U	0.000380 U	0.000282 U	0.000253 U	0.000220 U	0.000240 U	0.000296 U
B-223	B-223-16	9/21/17	PES	ESC	16	23.1	S	0.0678 U	0.0917 U	0.0499 U	0.248 U	0.0811 U	0.0721 U	0.0626 U	**0.203 J**	0.0629 U	0.0565 U	0.0489 U	0.0534 U	0.0659 U
	B-223-22	9/21/17	PES	ESC	22	17.1	S	0.0655 U	0.0886 U	0.0482 U	0.240 U	0.0783 U	0.0697 U	0.0605 U	0.0818 U	0.0608 U	0.0546 U	0.0473 U	0.0516 U	0.0637 U
	B-223-30	9/21/17	PES	ESC	30	9.1	S	7.90 U	10.7 U	5.81 U	28.8 U	9.45 U	8.39 U	7.29 U	9.85 U	7.32 U	6.58 U	5.70 U	6.22 U	7.68 U
	B-223-39	9/21/17	PES	ESC	39	0.1	S	0.000327 U	0.000442 U	0.0240 U	0.00120 U	0.000391 U	0.000347 U	0.000302 U	0.000408 U	0.000303 U	0.000272 U	0.000236 U	0.000257 U	0.000318 U
	B-223-47	9/21/17	PES	ESC	47	-7.9	S	0.000333 U	0.000451 U	0.000245 U	0.00122 U	0.000398 U	0.000354 U	0.000308 U	0.000416 U	0.000309 U	0.000278 U	0.000240 U	0.000262 U	0.000324 U
	B-917-57	9/21/17	PES	ESC	47 (dup)	-7.9	S	0.000308 U	0.000417 U	0.000227 U	0.00113 U	0.000369 U	0.000328 U	0.000285 U	0.000385 U	0.000286 U	0.000257 U	0.000222 U	0.000243 U	0.000300 U
B-224	B-224-6	11/27/17	PES	ESC	6	33.1	S	0.000310 U	0.000420 U	0.000228 U	0.00114 U	0.000371 U	0.000330 U	0.000287 U	0.000387 U	0.000288 U	0.000258 U	0.000224 U	0.000244 U	0.000302 U
	B-224-11	11/27/17	PES	ESC	11	28.1	S	0.000767 U	0.00104 U	0.000564 U	0.00281 U	0.000916 U	0.000815 U	0.000708 U	0.000956 U	0.000711 U	0.000638 U	0.000553 U	0.000604 U	0.000746 U
	B-224-16	11/27/17	PES	ESC	16	23.1	S	0.000347 U	0.000469 U	0.000255 U	0.00127 U	0.000415 U	0.000369 U	0.000320 U	0.000433 U	0.000322 U	0.000289 U	0.000250 U	0.000273 U	0.000337 U
	B-224-21.5	11/27/17	PES	ESC	21.5	17.6	S	0.000333 U	0.000450 U	0.000245 U	0.00122 U	0.000398 U	0.000354 U	0.000308 U	0.000416 U	0.000309 U	0.000277 U	0.000240 U	0.000262 U	0.000324 U
	B-224-26	11/27/17	PES	ESC	26	13.1	S	0.000379 U	0.000512 U	0.000278 U	0.00139 U	0.000453 U	0.000403 U	0.000350 U	0.000473 U	0.000351 U	0.000315 U	0.000274 U	0.000299 U	0.000369 U
	B-224-31	11/27/17	PES	ESC	31	8.1	S	0.000336 U	0.000454 U	0.000247 U	0.00122 U	0.000401 U	0.000356 U	0.000310 U	0.000419 U	0.000311 U	0.000279 U	0.000242 U	0.000264 U	0.000326 U
	B-224-36	11/27/17	PES	ESC	36	3.1	S	0.000319 U	0.000431 U	0.000234 U	0.00117 U	0.000381 U	0.000339 U	0.000294 U	0.000398 U	0.000295 U	0.000265 U	0.000230 U	0.000251 U	0.000310 U
	B-224-60.5	11/27/17	PES	ESC	60.5	-21.4	S	0.000464 U	0.000627 U	0.000341 U	0.00170 U	0.000555 U	0.000493 U	0.000428 U	0.000579 U	0.000431 U	0.000386 U	0.000335 U	0.000365 U	0.000451 U
B-225	B-225-5	11/27/17	PES	ESC	5	34.1	S	0.000311 U	0.000421 U	0.000229 U	0.00114 U	0.000372 U	0.000331 U	0.000287 U	0.000388 U	0.000289 U	0.000259 U	0.000225 U	0.000245 U	0.000303 U
	B-225-11	11/27/17	PES	ESC	11	28.1	S	0.000336 U	0.000454 U	0.000247 U	0.00123 U	0.000401 U	0.000357 U	0.000310 U	0.000419 U	0.000311 U	0.000280 U	0.000242 U	0.000264 U	0.000326 U
	B-225-16	11/27/17	PES	ESC	16	23.1	S	0.00845 U	0.0114 U	0.00621 U	0.0308 U	0.0101 U	0.00896 U	0.00779 U	0.0105 U	0.00782 U	0.00703 U	0.00609 U	0.00665 U	0.00821 U
	B-225-21	11/27/17	PES	ESC	21	18.1	S	0.00816 U	0.0110 U	0.00600 U	0.0298 U	0.00975 U	0.00866 U	0.00753 U	0.0102 U	0.00756 U	0.00680 U	0.00589 U	0.00642 U	0.00794 U
	B-225-26	11/27/17	PES	ESC	26	13.1	S	0.000337 U	0.000456 U	0.000248 U	0.00123 U	0.000403 U	0.000358 U	0.000311 U	0.000421 U	0.000313 U	0.000281 U	0.000243 U	0.000266 U	0.000328 U
	B-225-31	11/27/17	PES	ESC	31	8.1	S	0.000328 U	0.000443 U	0.000241 U	0.00120 U	0.000392 U	0.000349 U	0.000303 U	0.000409 U	0.000304 U	0.000273 U	0.000237 U	0.000258 U	0.000319 U
	B-225-36	11/27/17	PES	ESC	36	3.1	S	0.000353 U	0.000478 U	0.000260 U	0.00129 U	0.000422 U	0.000376 U	0.000326 U	0.000441 U	0.000328 U	0.000294 U	0.000255 U	0.000278 U	0.000344 U
B-226	B-226-6	11/28/17	PES	ESC	6	33.1	S	0.000346 U	0.000467 U	0.000254 U	0.00126 U	0.000413 U	0.000367 U	0.000319 U	0.000431 U	0.000320 U	0.000288 U	0.000249 U	0.000272 U	0.000336 U
	B-226-11	11/28/17	PES	ESC	11	28.1	S	0.000325 U	0.000440 U	**0.000268 J**	0.00119 U	0.000389 U	0.000346 U	0.000301 U	0.000406 U	0.000302 U	0.000271 U	0.000235 U	0.000256 U	0.000316 U
	B-226-16	11/28/17	PES	ESC	16	23.1	S	0.00806 U	0.0109 U	0.00592 U	0.0294 U	0.00963 U	0.00855 U	0.00743 U	0.0100 U	0.00746 U	0.00671 U	0.00581 U	0.00634 U	0.00783 U
	B-920-35	11/28/17	PES	ESC	16 (dup)	23.1	S	0.000318 U	0.000429 U	0.000233 U	0.00116 U	0.000379 U	0.000337 U	0.000293 U	0.000396 U	0.000294 U	0.000264 U	0.000229 U	0.000250 U	0.000309 U
	B-226-21	11/28/17	PES	ESC	21	18.1	S	0.000327 U	0.000442 U	0.000240 U	0.00120 U	0.000391 U	0.000347 U	0.000302 U	0.000408 U	0.000303 U	0.000272 U	0.000236 U	0.000257 U	0.000318 U
	B-226-31.5	11/28/17	PES	ESC	31.5	7.6	S	0.000306 U	0.000413 U	0.000225 U	0.00112 U	0.000365 U	0.000325 U	0.000282 U	0.000381 U	0.000283 U	0.000254 U	0.000220 U	0.000241 U	0.000297 U
	B-226-40	11/28/17	PES	ESC	40	-0.9	S	0.000329 U	0.000444 U	0.000242 U	0.00120 U	0.000393 U	0.000349 U	0.000303 U	0.000410 U	0.000305 U	0.000274 U	0.000237 U	0.000259 U	0.000319 U
B-227	B-227-6	11/28/17	PES	ESC	6	33.1	S	0.000328 U	0.000443 U	0.000241 U	0.00120 U	0.000392 U	0.000348 U	0.000303 U	0.000409 U	0.000304 U	0.000273 U	0.000236 U	0.000258 U	0.000319 U
	B-227-11	11/28/17	PES	ESC	11	28.1	S	0.000309 U	0.000418 U	0.000227 U	0.00113 U	0.000370 U	0.000329 U	0.000286 U	0.000386 U	0.000287 U	0.000258 U	0.000223 U	0.000244 U	0.000301 U
	B-227-16	11/28/17	PES	ESC	16	23.1	S	0.000329 U	0.000445 U	0.000242 U	0.00120 U	0.000393 U	0.000350 U	0.000304 U	0.000410 U	0.000305 U	0.000274 U	0.000237 U	0.000259 U	0.000320 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
B-227 (continued)	B-227-21	11/28/17	PES	ESC	21	18.1	S	0.000333 U	0.000450 U	0.000245 U	0.00122 U	0.000398 U	0.000354 U	0.000308 U	0.000416 U	0.000309 U	0.000277 U	0.000240 U	0.000262 U	0.000324 U
	B-227-26	11/28/17	PES	ESC	26	13.1	S	0.000334 U	0.000452 U	0.000246 U	0.00122 U	0.000400 U	0.000355 U	0.000309 U	0.000417 U	0.000310 U	0.000278 U	0.000241 U	0.000263 U	0.000325 U
	B-227-31	11/28/17	PES	ESC	31	8.1	S	0.000344 U	0.000465 U	0.000253 U	0.00126 U	0.000411 U	0.000366 U	0.000318 U	0.000429 U	0.000319 U	0.000287 U	0.000248 U	0.000271 U	0.000335 U
	B-227-36	11/28/17	PES	ESC	36	3.1	S	0.000329 U	0.000445 U	0.000242 U	0.00121 U	0.000394 U	0.000350 U	0.000304 U	0.000411 U	0.000305 U	0.000274 U	0.000238 U	0.000259 U	0.000320 U
B-228	B-228-6	11/29/17	PES	ESC	6	33.1	S	0.000351 U	0.000475 U	0.000258 U	0.00128 U	0.000420 U	0.000373 U	0.000324 U	0.000438 U	0.000325 U	0.000292 U	0.000253 U	0.000276 U	0.000341 U
	B-228-11	11/29/17	PES	ESC	11	28.1	S	0.000319 U	0.000431 U	0.000235 U	0.00117 U	0.000381 U	0.000339 U	0.000295 U	0.000398 U	0.000296 U	0.000266 U	0.000230 U	0.000251 U	0.000310 U
	B-228-16	11/29/17	PES	ESC	16	23.1	S	0.000309 U	0.000418 U	0.000227 U	0.00113 U	0.000369 U	0.000329 U	0.000285 U	0.000386 U	0.000287 U	0.000257 U	0.000223 U	0.000243 U	0.000301 U
	B-921-22	11/29/17	PES	ESC	16 (dup)	23.1	S	0.000330 U	0.000446 U	0.000242 U	0.00121 U	0.000394 U	0.000350 U	0.000304 U	0.000411 U	0.000306 U	0.000275 U	0.000238 U	0.000260 U	0.000320 U
	B-228-21	11/29/17	PES	ESC	21	18.1	S	0.000325 U	0.000439 U	0.000239 U	0.00119 U	0.000388 U	0.000345 U	0.000300 U	0.000405 U	0.000301 U	0.000270 U	0.000234 U	0.000256 U	0.000316 U
	B-228-26	11/29/17	PES	ESC	26	13.1	S	0.000309 U	0.000418 U	0.000227 U	0.00113 U	0.000369 U	0.000328 U	0.000285 U	0.000385 U	0.000286 U	0.000257 U	0.000223 U	0.000243 U	0.000300 U
	B-228-31	11/29/17	PES	ESC	31	8.1	S	0.000319 U	0.000431 U	0.000234 U	0.00117 U	0.000381 U	0.000339 U	0.000294 U	0.000397 U	0.000295 U	0.000265 U	0.000230 U	0.000251 U	0.000310 U
	B-228-36	11/29/17	PES	ESC	36	3.1	S	0.000324 U	0.000438 U	0.000238 U	0.00119 U	0.000387 U	0.000345 U	0.000299 U	0.000404 U	0.000300 U	0.000270 U	0.000234 U	0.000255 U	0.000315 U
B-229	B-229-6	11/29/17	PES	ESC	6	33.1	S	0.000420 U	0.000568 U	0.000309 U	0.00154 U	0.000502 U	0.000446 U	0.000388 U	0.000524 U	0.000389 U	0.000350 U	0.000303 U	0.000331 U	0.000408 U
	B-229-11	11/29/17	PES	ESC	11	28.1	S	0.000407 U	0.000551 U	0.000300 U	0.00149 U	0.000487 U	0.000433 U	0.000376 U	0.000508 U	0.000378 U	0.000339 U	0.000294 U	0.000321 U	0.000396 U
	B-229-16	11/29/17	PES	ESC	16	23.1	S	0.000342 U	0.000463 U	0.000252 U	0.00125 U	0.000409 U	0.000364 U	0.000316 U	0.000427 U	0.000317 U	0.000285 U	0.000247 U	0.000269 U	0.000333 U
	B-229-25	11/29/17	PES	ESC	25	14.1	S	0.000315 U	0.000425 U	0.000231 U	0.00115 U	0.000376 U	0.000334 U	0.000291 U	0.000393 U	0.000292 U	0.000262 U	0.000227 U	0.000248 U	0.000306 U
	B-229-31	11/29/17	PES	ESC	31	8.1	S	0.000346 U	0.000468 U	0.000254 U	0.00127 U	0.000414 U	0.000368 U	0.000320 U	0.000432 U	0.000321 U	0.000288 U	0.000250 U	0.000273 U	0.000336 U
	B-229-36	11/29/17	PES	ESC	36	3.1	S	0.000316 U	0.000427 U	**0.000385 J**	0.00115 U	0.000377 U	0.000335 U	0.000291 U	0.000394 U	0.000293 U	0.000263 U	0.000228 U	0.000249 U	0.000307 U
	B-229-41	11/29/17	PES	ESC	41	-1.9	S	0.000334 U	0.000452 U	**0.00110 J**	0.00122 U	0.000399 U	0.000355 U	0.000309 U	0.000417 U	**0.000425 J**	0.000278 U	0.000241 U	0.000263 U	0.000325 U
	B-229-45	11/29/17	PES	ESC	45	-5.9	S	0.000343 U	0.000464 U	**0.000622 J**	0.00126 U	0.000410 U	0.000365 U	0.000317 U	0.000428 U	0.000318 U	0.000286 U	0.000248 U	0.000270 U	0.000334 U
B-230	B-230-6	11/30/17	PES	ESC	6	33.1	S	0.000303 U	0.000409 U	0.000223 U	0.00111 U	0.000362 U	0.000322 U	0.000280 U	0.000378 U	0.000281 U	0.000252 U	0.000218 U	0.000238 U	0.000294 U
	B-230-11	11/30/17	PES	ESC	11	28.1	S	0.000313 U	0.000424 U	0.000230 U	0.00115 U	0.000375 U	0.000333 U	0.000289 U	0.000391 U	0.000291 U	0.000261 U	0.000226 U	0.000247 U	0.000305 U
	B-230-16	11/30/17	PES	ESC	16	23.1	S	0.0799 U	0.108 U	**0.0621 J**	0.292 U	0.0955 U	0.0848 U	0.0737 U	0.0996 U	0.0740 U	0.0666 U	0.0577 U	0.0629 U	0.0777 U
	B-230-21	11/30/17	PES	ESC	21	18.1	S	0.685 U	0.926 U	0.504 U	2.51 U	0.819 U	0.728 U	0.633 U	0.855 U	0.635 U	0.571 U	0.494 U	0.540 U	0.666 U
	B-922-15	11/30/17	PES	ESC	21 (dup)	18.1	S	0.347 U	0.469 U	0.255 U	1.27 U	0.414 U	0.368 U	0.320 U	0.432 U	0.321 U	0.289 U	0.250 U	0.273 U	0.337 U
	B-230-26	11/30/17	PES	ESC	26	13.1	S	0.860 U	1.16 U	0.633 U	3.14 U	1.03 U	0.913 U	0.793 U	1.07 U	0.797 U	0.717 U	0.621 U	0.677 U	0.836 U
	B-230-31	11/30/17	PES	ESC	31	8.1	S	0.357 U	0.483 U	0.262 U	1.31 U	0.427 U	0.379 U	0.330 U	0.445 U	0.331 U	0.297 U	0.257 U	0.281 U	0.347 U
	B-230-35	11/30/17	PES	ESC	35	4.1	S	0.0518 U	0.0701 U	**0.0580 J**	0.190 U	0.0620 U	0.0551 U	0.0478 U	0.0647 U	0.0481 U	0.0432 U	0.0374 U	0.0409 U	0.0504 U
	B-230-55	11/30/17	PES	ESC	55	-15.9	S	0.0862 U	0.116 U	0.0634 U	0.314 U	0.103 U	0.0915 U	0.0795 U	0.107 U	0.0798 U	0.0718 U	0.0622 U	0.0678 U	0.0838 U
B-231	B-231-6	11/30/17	PES	ESC	6	33.1	S	0.000354 U	0.000479 U	0.000260 U	0.00130 U	0.000423 U	0.000376 U	0.000327 U	0.000442 U	0.000328 U	0.000295 U	0.000255 U	0.000279 U	0.000344 U
	B-231-11	11/30/17	PES	ESC	11	28.1	S	0.000338 U	0.000457 U	0.000249 U	0.00124 U	0.000404 U	0.000359 U	0.000312 U	0.000422 U	0.000314 U	0.000282 U	0.000244 U	0.000266 U	0.000329 U
	B-231-16	11/30/17	PES	ESC	16	23.1	S	0.00804 U	0.0109 U	0.00592 U	0.0294 U	0.00961 U	0.00854 U	0.00742 U	0.0100 U	0.00745 U	0.00670 U	0.00580 U	0.00633 U	0.00782 U
	B-231-21	11/30/17	PES	ESC	21	18.1	S	0.0190 U	0.0256 U	0.0139 U	0.0694 U	0.0227 U	0.0202 U	0.0175 U	0.0237 U	0.0176 U	0.0158 U	0.0137 U	0.0150 U	0.0184 U
	B-231-26	11/30/17	PES	ESC	26	13.1	S	0.000333 U	0.000451 U	0.000245 U	0.00122 U	0.000398 U	0.000354 U	0.000308 U	0.000416 U	0.000309 U	0.000278 U	0.000240 U	0.000262 U	0.000324 U
	B-231-30	11/30/17	PES	ESC	30	9.1	S	0.000324 U	0.000438 U	0.000238 U	0.00118 U	0.000387 U	0.000344 U	0.000299 U	0.000404 U	0.000300 U	0.000270 U	0.000233 U	0.000255 U	0.000315 U
	B-231-36	11/30/17	PES	ESC	36	3.1	S	0.000325 U	0.000440 U	0.000239 U	0.00119 U	0.000389 U	0.000346 U	0.000301 U	0.000406 U	0.000302 U	0.000271 U	0.000235 U	0.000256 U	0.000316 U
B-232	B-232-6	12/1/17	PES	ESC	6	33.1	S	**0.000734 J**	0.000458 U	**0.000571 J**	0.00124 U	0.000405 U	0.000360 U	0.000313 U	0.000423 U	0.000314 U	0.000282 U	0.000244 U	0.000267 U	0.000329 U
	B-232-11	12/1/17	PES	ESC	11	28.1	S	0.000382 U	0.000516 U	**0.000384 J**	0.00140 U	0.000456 U	0.000406 U	0.000353 U	0.000476 U	0.000354 U	0.000318 U	0.000275 U	0.000301 U	0.000371 U
	B-232-16	12/1/17	PES	ESC	16	23.1	S	0.000336 U	0.000454 U	0.000247 U	0.00123 U	0.000402 U	0.000357 U	0.000310 U	0.000419 U	0.000311 U	0.000280 U	0.000242 U	0.000265 U	0.000327 U
	B-232-21	12/1/17	PES	ESC	21	18.1	S	0.000321 U	0.000434 U	0.000236 U	0.00118 U	0.000384 U	0.000341 U	0.000297 U	0.000401 U	0.000298 U	0.000267 U	0.000232 U	0.000253 U	0.000312 U
	B-232-26	12/1/17	PES	ESC	26	13.1	S	0.0107 U	0.0145 U	0.00789 U	0.0393 U	0.0128 U	0.0114 U	0.00990 U	0.0134 U	0.00994 U	0.00893 U	0.00773 U	0.00844 U	0.0104 U
	B-232-31	12/1/17	PES	ESC	31	8.1	S	0.000324 U	0.000438 U	0.000238 U	0.00119 U	0.000387 U	0.000344 U	0.000299 U	0.000404 U	0.000300 U	0.000270 U	0.000234 U	0.000255 U	0.000315 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
B-232 (continued)	B-232-36	12/1/17	PES	ESC	36	3.1	S	0.000340 U	0.000460 U	0.000250 U	0.00124 U	0.000407 U	0.000362 U	0.000314 U	0.000424 U	0.000315 U	0.000283 U	0.000245 U	0.000268 U	0.000331 U
B-233	B-233-6	12/1/17	PES	ESC	6	29.5	S	0.000310 U	0.000419 U	0.000228 U	0.00113 U	0.000370 U	0.000329 U	0.000286 U	0.000386 U	0.000287 U	0.000258 U	0.000223 U	0.000244 U	0.000301 U
	B-233-11	12/1/17	PES	ESC	11	24.5	S	0.000801 U	0.00108 U	0.000589 U	0.00293 U	0.000957 U	0.000851 U	0.000739 U	0.000998 U	0.000742 U	0.000667 U	0.000577 U	0.000631 U	0.000778 U
	B-233-16	12/1/17	PES	ESC	16	19.5	S	0.000405 U	0.000548 U	0.000298 U	0.00148 U	0.000484 U	0.000431 U	0.000374 U	0.000505 U	0.000376 U	0.000337 U	0.000292 U	0.000319 U	0.000393 U
	B-233-21	12/1/17	PES	ESC	21	14.5	S	0.00819 U	0.0111 U	0.00602 U	0.0299 U	0.00979 U	0.00869 U	0.00755 U	0.0102 U	0.00759 U	0.00682 U	0.00591 U	0.00645 U	0.00796 U
	B-233-26	12/1/17	PES	ESC	26	9.5	S	0.0172 U	0.0232 U	0.0127 U	0.0628 U	0.0206 U	0.0182 U	0.0158 U	0.0214 U	0.0159 U	0.0143 U	0.0124 U	0.0135 U	0.0167 U
	B-233-31	12/1/17	PES	ESC	31	4.5	S	0.00893 U	0.0121 U	0.00657 U	0.0326 U	0.0107 U	0.00947 U	0.00823 U	0.0111 U	0.00827 U	0.00744 U	0.00644 U	0.00703 U	0.00868 U
	B-233-36	12/1/17	PES	ESC	36	-0.5	S	0.00808 U	0.0109 U	0.00594 U	0.0295 U	0.00966 U	0.00858 U	0.00745 U	0.0101 U	0.00749 U	0.00673 U	0.00583 U	0.00636 U	0.00786 U
B-234	B-234-11	12/4/17	PES	ESC	11	40.8	V	0.000334 U	0.000451 U	0.000245 U	0.00122 U	0.000399 U	0.000355 U	0.000308 U	0.000416 U	0.000309 U	0.000278 U	0.000241 U	0.000263 U	0.000324 U
	B-234-30	12/4/17	PES	ESC	30	21.8	S	0.000304 U	0.000411 U	0.000223 U	0.00111 U	0.000363 U	0.000323 U	0.000280 U	0.000379 U	0.000282 U	0.000253 U	0.000219 U	0.000239 U	0.000295 U
B-234A	B-234A-35	12/4/17	PES	ESC	35	16.8	S	0.000329 U	0.000445 U	0.000242 U	0.00120 U	0.000393 U	0.000350 U	0.000304 U	0.000411 U	0.000305 U	0.000274 U	0.000237 U	0.000259 U	0.000320 U
	B-234A-40	12/4/17	PES	ESC	40	11.8	S	0.000309 U	0.000418 U	0.000227 U	0.00113 U	0.000369 U	0.000328 U	0.000285 U	0.000385 U	0.000286 U	0.000257 U	0.000223 U	0.000243 U	0.000300 U
	B-234A-42	12/4/17	PES	ESC	42	9.8	S	0.000352 U	0.000475 U	0.000259 U	0.00129 U	0.000420 U	0.000374 U	0.000325 U	0.000439 U	0.000326 U	0.000293 U	0.000254 U	0.000277 U	0.000342 U
	B-924-30	12/4/17	PES	ESC	42 (dup)	9.8	S	0.000349 U	0.000471 U	0.000256 U	0.00128 U	0.000417 U	0.000370 U	0.000322 U	0.000435 U	0.000323 U	0.000290 U	0.000251 U	0.000274 U	0.000339 U
	B-234A-45	12/4/17	PES	ESC	45	6.8	S	0.000323 U	0.000437 U	0.000238 U	0.00118 U	0.000387 U	0.000344 U	0.000299 U	0.000403 U	0.000300 U	0.000269 U	0.000233 U	0.000255 U	0.000314 U
B-235	B-235-15	12/5/17	PES	ESC	15	36.8	V	0.000345 U	0.000466 U	0.000253 U	0.00126 U	0.000411 U	0.000366 U	0.000318 U	0.000430 U	0.000319 U	0.000287 U	0.000249 U	0.000271 U	0.000335 U
	B-235-35	12/5/17	PES	ESC	35	16.8	S	0.000318 U	0.000430 U	0.000234 U	0.00116 U	0.000380 U	0.000338 U	0.000293 U	0.000396 U	0.000294 U	0.000265 U	0.000229 U	0.000250 U	0.000309 U
	B-235-40	12/5/17	PES	ESC	40	11.8	S	0.000315 U	0.000425 U	0.000231 U	0.00115 U	0.000376 U	0.000334 U	0.000290 U	0.000392 U	0.000292 U	0.000262 U	0.000227 U	0.000248 U	0.000306 U
	B-235-42.5	12/5/17	PES	ESC	42.5	9.3	S	0.0627 U	0.0847 U	0.0461 U	0.229 U	0.0749 U	0.0666 U	0.0579 U	0.0782 U	0.0581 U	0.0522 U	0.0452 U	0.0494 U	0.0609 U
	B-235-45	12/5/17	PES	ESC	45	6.8	S	0.000323 U	0.000437 U	**0.000312 J**	0.00118 U	0.000386 U	0.000343 U	0.000298 U	0.000403 U	0.000300 U	0.000269 U	0.000233 U	0.000255 U	0.000314 U
B-236	B-236-20	12/5/17	PES	ESC	20	31.8	S	0.000328 U	0.000444 U	0.000241 U	0.00120 U	0.000392 U	0.000349 U	0.000303 U	0.000409 U	0.000304 U	0.000273 U	0.000237 U	0.000258 U	0.000319 U
	B-236-35	12/5/17	PES	ESC	35	16.8	S	0.000520 U	0.000702 U	0.000382 U	0.00190 U	0.000621 U	0.000552 U	0.000480 U	0.000649 U	0.000482 U	0.000433 U	0.000375 U	0.000409 U	0.000506 U
	B-236-40	12/5/17	PES	ESC	40	11.8	S	0.000318 U	0.000429 U	0.000233 U	0.00116 U	0.000380 U	0.000337 U	0.000293 U	0.000396 U	0.000294 U	0.000264 U	0.000229 U	0.000250 U	0.000309 U
	B-236-42.5	12/5/17	PES	ESC	42.5	9.3	S	**0.728 J**	0.455 U	**2.33**	1.23 U	0.402 U	0.358 U	0.311 U	0.420 U	**0.745 J**	0.280 U	0.243 U	0.265 U	0.327 U
	B-236-45	12/5/17	PES	ESC	45	6.8	S	0.113 U	0.153 U	0.0829 U	0.413 U	0.135 U	0.120 U	0.104 U	0.141 U	0.104 U	0.0938 U	0.0813 U	0.0887 U	0.110 U
B-237	B-237-5	12/6/17	PES	ESC	5	46.8	V	0.000334 U	0.000452 U	0.000246 U	0.00122 U	0.000400 U	0.000355 U	0.000309 U	0.000417 U	0.000310 U	0.000278 U	0.000241 U	0.000263 U	0.000325 U
	B-237-35	12/6/17	PES	ESC	35	16.8	S	0.000335 U	0.000453 U	0.000246 U	0.00123 U	0.000401 U	0.000356 U	0.000310 U	0.000418 U	0.000311 U	0.000279 U	0.000242 U	0.000264 U	0.000326 U
	B-237-40	12/6/17	PES	ESC	40	11.8	S	0.000308 U	0.000417 U	0.000227 U	0.00113 U	0.000369 U	0.000328 U	0.000285 U	0.000385 U	0.000286 U	0.000257 U	0.000222 U	0.000243 U	0.000300 U
	B-237-42	12/6/17	PES	ESC	42	9.8	S	0.000339 U	0.000459 U	**0.000557 J**	0.00124 U	0.000405 U	0.000360 U	0.000313 U	0.000423 U	0.000314 U	0.000282 U	0.000245 U	0.000267 U	0.000330 U
	B-925-41	12/6/17	PES	ESC	42 (dup)	9.8	S	0.0366 U	0.0495 U	0.0269 U	0.134 U	0.0438 U	0.0389 U	0.0338 U	0.0457 U	0.0340 U	0.0305 U	0.0264 U	0.0289 U	0.0356 U
	B-237-45	12/6/17	PES	ESC	45	6.8	S	0.000369 U	0.000499 U	0.000272 U	0.00135 U	0.000442 U	0.000393 U	0.000341 U	0.000461 U	0.000342 U	0.000308 U	0.000266 U	0.000291 U	0.000359 U
B-238	B-238-6	12/6/17	PES	ESC	6	33.1	S	0.000335 U	0.000452 U	0.000246 U	0.00122 U	0.000400 U	0.000356 U	0.000309 U	0.000417 U	0.000310 U	0.000279 U	0.000241 U	0.000263 U	0.000325 U
	B-238-11	12/6/17	PES	ESC	11	28.1	S	**0.000402 J**	0.000451 U	**0.00114 J**	0.00122 U	0.000399 U	0.000355 U	0.000308 U	0.000417 U	**0.000551 J**	0.000278 U	0.000241 U	0.000263 U	0.000325 U
	B-238-16	12/6/17	PES	ESC	16	23.1	S	0.0821 U	0.111 U	0.0604 U	0.300 U	0.0982 U	0.0872 U	0.0757 U	0.102 U	0.0761 U	0.0684 U	0.0593 U	0.0646 U	0.0799 U
	B-238-21	12/6/17	PES	ESC	21	18.1	S	0.320 U	0.433 U	0.235 U	1.17 U	0.383 U	0.340 U	0.296 U	0.399 U	0.297 U	0.267 U	0.231 U	0.252 U	0.311 U
	B-238-26	12/6/17	PES	ESC	26	13.1	S	0.000321 U	0.000434 U	0.000236 U	0.00117 U	0.000384 U	0.000341 U	0.000296 U	0.000400 U	0.000297 U	0.000267 U	0.000231 U	0.000253 U	0.000312 U
	B-238-31	12/6/17	PES	ESC	31	8.1	S	0.000304 U	0.000411 U	0.000224 U	0.00111 U	0.000364 U	0.000323 U	0.000281 U	0.000380 U	0.000282 U	0.000253 U	0.000219 U	0.000240 U	0.000296 U
	B-238-36	12/6/17	PES	ESC	36	3.1	S	0.000336 U	0.000454 U	0.000247 U	0.00123 U	0.000402 U	0.000357 U	0.000310 U	0.000419 U	0.000312 U	0.000280 U	0.000242 U	0.000265 U	0.000327 U
B-239	B-239-5	4/3/18	PES	ESC	5	34.2	S	0.000341 U	0.000462 U	0.000251 U	0.00125 U	0.000408 U	0.000363 U	0.000315 U	0.000426 U	0.000316 U	0.000284 U	0.000246 U	0.000269 U	0.000332 U
	B-239-10	4/3/18	PES	ESC	10	29.2	S	0.000339 U	0.000458 U	0.000249 U	0.00124 U	0.000405 U	0.000360 U	0.000313 U	0.000422 U	0.000314 U	0.000282 U	0.000244 U	0.000267 U	0.000329 U
	B-239-15	4/3/18	PES	ESC	15	24.2	S	0.000327 U	0.000442 U	0.000240 U	0.00120 U	0.000391 U	0.000347 U	0.000302 U	0.000408 U	0.000303 U	0.000272 U	0.000236 U	0.000257 U	0.000318 U
	B-239-20	4/3/18	PES	ESC	20	19.2	S	0.000324 U	0.000438 U	0.000238 U	0.00118 U	0.000387 U	0.000344 U	0.000299 U	0.000404 U	0.000300 U	0.000270 U	0.000234 U	0.000255 U	0.000315 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
B-239 (continued)	B-239-25	4/3/18	PES	ESC	25	14.2	S	0.000329 U	0.000444 U	0.000242 U	0.00120 U	0.000393 U	0.000349 U	0.000304 U	0.000410 U	0.000305 U	0.000274 U	0.000237 U	0.000259 U	0.000320 U
	B-239-35	4/3/18	PES	ESC	35	4.2	S	0.000311 U	0.000420 U	0.000228 U	0.00114 U	0.000371 U	0.000330 U	0.000287 U	0.000388 U	0.000288 U	0.000259 U	0.000224 U	0.000245 U	0.000302 U
	B-239-40	4/3/18	PES	ESC	40	-0.8	S	0.000326 U	0.000440 U	0.000239 U	0.00119 U	0.000389 U	0.000346 U	0.000301 U	0.000406 U	0.000302 U	0.000271 U	0.000235 U	0.000256 U	0.000317 U
	B-239-45	4/3/18	PES	ESC	45	-5.8	S	0.000321 U	0.000435 U	0.000236 U	0.00118 U	0.000384 U	0.000342 U	0.000297 U	0.000401 U	0.000298 U	0.000268 U	0.000232 U	0.000253 U	0.000313 U
	B-239-50	4/3/18	PES	ESC	50	-10.8	S	0.000317 U	0.000428 U	0.000233 U	0.00116 U	0.000379 U	0.000337 U	0.000293 U	0.000395 U	0.000294 U	0.000264 U	0.000229 U	0.000250 U	0.000308 U
	B-909-50	4/3/18	PES	ESC	50 (dup)	-10.8	S	0.000319 U	0.000431 U	0.000234 U	0.00117 U	0.000381 U	0.000339 U	0.000294 U	0.000398 U	0.000296 U	0.000266 U	0.000230 U	0.000251 U	0.000310 U
	B-239-55	4/3/18	PES	ESC	55	-15.8	S	0.000327 U	0.000441 U	0.000240 U	0.00119 U	0.000390 U	0.000347 U	0.000302 U	0.000407 U	0.000303 U	0.000272 U	0.000236 U	0.000257 U	0.000317 U
	B-239-60	4/3/18	PES	ESC	60	-20.8	S	0.000321 U	0.000434 U	0.000236 U	0.00117 U	0.000384 U	0.000341 U	0.000296 U	0.000400 U	0.000297 U	0.000267 U	0.000231 U	0.000253 U	0.000312 U
	B-239-65	4/3/18	PES	ESC	65	-25.8	S	0.000321 U	0.000434 U	0.000236 U	0.00117 U	0.000383 U	0.000341 U	0.000296 U	0.000400 U	0.000297 U	0.000267 U	0.000231 U	0.000253 U	0.000312 U
	B-239-70	4/3/18	PES	ESC	70	-30.8	S	0.000320 U	0.000432 U	0.000235 U	0.00117 U	0.000382 U	0.000340 U	0.000295 U	0.000399 U	0.000296 U	0.000266 U	0.000231 U	0.000252 U	0.000311 U
	B-239-75	4/3/18	PES	ESC	75	-35.8	S	0.000331 U	0.000447 U	0.000243 U	0.00121 U	0.000395 U	0.000352 U	0.000305 U	0.000413 U	0.000307 U	0.000275 U	0.000239 U	0.000260 U	0.000322 U
	B-239-80	4/3/18	PES	ESC	80	-40.8	S	0.000328 U	0.000444 U	0.000241 U	0.00120 U	0.000393 U	0.000349 U	0.000303 U	0.000410 U	0.000304 U	0.000274 U	0.000237 U	0.000259 U	0.000319 U
B-240	B-240-5	4/2/18	PES	ESC	5	34.2	S	0.000317 U	0.000428 U	0.000233 U	0.00116 U	0.000378 U	0.000337 U	0.000292 U	0.000395 U	0.000294 U	0.000264 U	0.000228 U	0.000249 U	0.000308 U
	B-240-10	4/2/18	PES	ESC	10	29.2	S	0.000316 U	0.000428 U	0.000233 U	0.00116 U	0.000378 U	0.000336 U	0.000292 U	0.000395 U	0.000293 U	0.000263 U	0.000228 U	0.000249 U	0.000308 U
	B-240-15	4/2/18	PES	ESC	15	24.2	S	0.000329 U	0.000445 U	**0.000382 J**	0.00120 U	0.000394 U	0.000350 U	0.000304 U	0.000411 U	0.000305 U	0.000274 U	0.000238 U	0.000259 U	0.000320 U
	B-240-20	4/2/18	PES	ESC	20	19.2	S	0.000334 U	0.000452 U	0.000246 U	0.00122 U	0.000399 U	0.000355 U	0.000308 U	0.000417 U	0.000310 U	0.000278 U	0.000241 U	0.000263 U	0.000325 U
	B-240-25	4/2/18	PES	ESC	25	14.2	S	0.0161 U	0.0217 U	0.0118 U	0.0586 U	0.0192 U	0.0170 U	0.0147 U	0.0200 U	0.0149 U	0.0134 U	0.0116 U	0.0126 U	0.0156 U
	B-240-30	4/2/18	PES	ESC	30	9.2	S	0.000346 U	0.000467 U	0.000254 U	0.00126 U	0.000413 U	0.000367 U	0.000319 U	0.000431 U	0.000320 U	0.000288 U	0.000249 U	0.000272 U	0.000336 U
	B-240-35	4/2/18	PES	ESC	35	4.2	S	0.000345 U	0.000466 U	0.000253 U	0.00126 U	0.000412 U	0.000366 U	0.000318 U	0.000430 U	0.000319 U	0.000287 U	0.000249 U	0.000271 U	0.000335 U
	B-240-42	4/2/18	PES	ESC	42	-2.8	S	0.000309 U	0.000418 U	0.000227 U	0.00113 U	0.000369 U	0.000328 U	0.000285 U	0.000385 U	0.000286 U	0.000257 U	0.000223 U	0.000243 U	0.000300 U
	B-240-45	4/2/18	PES	ESC	45	-5.8	S	0.000304 U	0.000411 U	0.000224 U	0.00111 U	0.000364 U	0.000323 U	0.000281 U	0.000380 U	0.000282 U	0.000253 U	0.000219 U	0.000240 U	0.000296 U
	B-240-50	4/2/18	PES	ESC	50	-10.8	S	0.000323 U	0.000437 U	0.000238 U	0.00118 U	0.000386 U	0.000343 U	0.000298 U	0.000403 U	0.000300 U	0.000269 U	0.000233 U	0.000255 U	0.000314 U
	B-240-55	4/2/18	PES	ESC	55	-15.8	S	0.000333 U	0.000450 U	0.000245 U	0.00122 U	0.000398 U	0.000354 U	0.000307 U	0.000415 U	0.000309 U	0.000277 U	0.000240 U	0.000262 U	0.000324 U
	B-240-60	4/2/18	PES	ESC	60	-20.8	S	0.000334 U	0.000452 U	0.000246 U	0.00122 U	0.000399 U	0.000355 U	0.000309 U	0.000417 U	0.000310 U	0.000278 U	0.000241 U	0.000263 U	0.000325 U
	B-240-65	4/2/18	PES	ESC	65	-25.8	S	0.000311 U	0.000421 U	0.000229 U	0.00114 U	0.000372 U	0.000331 U	0.000287 U	0.000388 U	0.000288 U	0.000259 U	0.000224 U	0.000245 U	0.000303 U
	B-240-70	4/2/18	PES	ESC	70	-30.8	S	0.000332 U	0.000449 U	0.000244 U	0.00121 U	0.000397 U	0.000353 U	0.000307 U	0.000414 U	0.000308 U	0.000277 U	0.000239 U	0.000261 U	0.000323 U
	B-240-75	4/2/18	PES	ESC	75	-35.8	S	0.000315 U	0.000426 U	0.000232 U	0.00115 U	0.000377 U	0.000335 U	0.000291 U	0.000393 U	0.000292 U	0.000262 U	0.000227 U	0.000248 U	0.000306 U
	B-240-80	4/2/18	PES	ESC	80	-40.8	S	0.000326 U	0.000441 U	0.000240 U	0.00119 U	0.000390 U	0.000347 U	0.000301 U	0.000407 U	0.000303 U	0.000272 U	0.000235 U	0.000257 U	0.000317 U
B-241	B-241-5	4/4/18	PES	ESC	5	34.1	S	**0.0961**	0.000421 U	**3.64**	0.00114 U	0.000372 U	0.000331 U	0.000287 U	0.000388 U	**0.119**	0.000259 U	0.000225 U	0.000245 U	0.000303 U
	B-241-10	4/4/18	PES	ESC	10	29.1	S	**0.000540 J**	0.000440 U	0.000239 U	0.00119 U	0.000389 U	0.000346 U	0.000300 U	0.000406 U	**0.000440 J**	0.000271 U	0.000235 U	0.000256 U	0.000316 U
	B-241-15	4/4/18	PES	ESC	15	24.1	S	0.000320 U	0.000433 U	0.000236 U	0.00117 U	0.000383 U	0.000340 U	0.000296 U	0.000400 U	0.000297 U	0.000267 U	0.000231 U	0.000252 U	0.000311 U
	B-241-20	4/4/18	PES	ESC	20	19.1	S	0.000349 U	0.000472 U	0.000257 U	0.00128 U	0.000417 U	0.000371 U	0.000323 U	0.000436 U	0.000324 U	0.000291 U	0.000252 U	0.000275 U	0.000340 U
	B-241-25	4/4/18	PES	ESC	25	14.1	S	0.000324 U	0.000439 U	**0.000427**	0.00119 U	0.000388 U	0.000345 U	0.000300 U	0.000405 U	0.000301 U	0.000270 U	0.000234 U	0.000255 U	0.000315 U
	B-241-30	4/3/18	PES	ESC	30	9.1	S	0.000322 U	0.000435 U	0.000237 U	0.00118 U	0.000385 U	0.000342 U	0.000297 U	0.000402 U	0.000298 U	0.000268 U	0.000232 U	0.000253 U	0.000313 U
	B-241-35	4/3/18	PES	ESC	35	4.1	S	0.000332 U	0.000449 U	0.000244 U	0.00122 U	0.000397 U	0.000353 U	0.000307 U	0.000414 U	0.000308 U	0.000277 U	0.000240 U	0.000262 U	0.000323 U
	B-241-40	4/3/18	PES	ESC	40	-0.9	S	0.000315 U	0.000426 U	0.000232 U	0.00115 U	0.000376 U	0.000335 U	0.000291 U	0.000393 U	0.000292 U	0.000262 U	0.000227 U	0.000248 U	0.000306 U
	B-241-45	4/3/18	PES	ESC	45	-5.9	S	0.000316 U	0.000427 U	0.000232 U	0.00116 U	0.000378 U	0.000336 U	0.000292 U	0.000394 U	0.000293 U	0.000263 U	0.000228 U	0.000249 U	0.000307 U
	B-241-50	4/4/18	PES	ESC	50	-10.9	S	0.000323 U	0.000437 U	**0.000499**	0.00118 U	0.000387 U	0.000344 U	0.000299 U	0.000403 U	0.000300 U	0.000269 U	0.000233 U	0.000255 U	0.000314 U
	B-241-55	4/4/18	PES	ESC	55	-15.9	S	0.000334 U	0.000452 U	0.000246 U	0.00122 U	0.000399 U	0.000355 U	0.000309 U	0.000417 U	0.000310 U	0.000278 U	0.000241 U	0.000263 U	0.000325 U
	B-241-60	4/3/18	PES	ESC	60	-20.9	S	0.000321 U	0.000434 U	0.000236 U	0.00118 U	0.000384 U	0.000341 U	0.000297 U	0.000401 U	0.000298 U	0.000268 U	0.000232 U	0.000253 U	0.000312 U
	B-241-65	4/3/18	PES	ESC	65	-25.9	S	0.000340 U	0.000459 U	0.000250 U	0.00124 U	0.000406 U	0.000361 U	0.000314 U	0.000424 U	0.000315 U	0.000283 U	0.000245 U	0.000267 U	0.000330 U
	B-241-70	4/3/18	PES	ESC	70	-30.9	S	0.000331 U	0.000448 U	0.000244 U	0.00121 U	0.000396 U	0.000352 U	0.000306 U	0.000413 U	0.000307 U	0.000276 U	0.000239 U	0.000261 U	0.000322 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
B-241	B-241-75	4/3/18	PES	ESC	75	-35.9	S	0.000335 U	0.000452 U	0.000246 U	0.00122 U	0.000400 U	0.000356 U	0.000309 U	0.000417 U	0.000310 U	0.000279 U	0.000241 U	0.000264 U	0.000325 U
(continued)	B-241-80	4/4/18	PES	ESC	80	-40.9	S	0.000330 U	0.000446 U	0.000242 U	0.00121 U	0.000394 U	0.000350 U	0.000305 U	0.000411 U	0.000306 U	0.000275 U	0.000238 U	0.000260 U	0.000321 U
B-242	B-242-5	4/4/18	PES	ESC	5	33.8	S	0.000311 U	0.000421 U	0.000229 U	0.00114 U	0.000372 U	0.000331 U	0.000288 U	0.000389 U	0.000289 U	0.000259 U	0.000225 U	0.000245 U	0.000303 U
	B-242-10	4/4/18	PES	ESC	10	28.8	S	0.000314 U	0.000425 U	0.000231 U	0.00115 U	0.000375 U	0.000334 U	0.000290 U	0.000392 U	0.000291 U	0.000262 U	0.000227 U	0.000247 U	0.000305 U
	B-242-15	4/4/18	PES	ESC	15	23.8	S	0.000335 U	0.000452 U	**0.000264 J**	0.00122 U	0.000400 U	0.000356 U	0.000309 U	0.000417 U	0.000310 U	0.000279 U	0.000241 U	0.000264 U	0.000325 U
	B-242-20	4/4/18	PES	ESC	20	18.8	S	0.000325 U	0.000440 U	0.000239 U	0.00119 U	0.000389 U	0.000346 U	0.000300 U	0.000406 U	0.000301 U	0.000271 U	0.000235 U	0.000256 U	0.000316 U
	B-242-25	4/4/18	PES	ESC	25	13.8	S	0.0316 U	0.0428 U	0.0233 U	0.116 U	0.0378 U	0.0336 U	0.0292 U	0.0395 U	0.0293 U	0.0263 U	0.0228 U	0.0249 U	0.0308 U
	B-242-30	4/4/18	PES	ESC	30	8.8	S	0.000321 U	0.000434 U	0.000236 U	0.00117 U	0.000384 U	0.000341 U	0.000296 U	0.000400 U	0.000298 U	0.000267 U	0.000232 U	0.000253 U	0.000312 U
	B-242-35	4/4/18	PES	ESC	35	3.8	S	0.000330 U	0.000447 U	0.000243 U	0.00121 U	0.000395 U	0.000351 U	0.000305 U	0.000412 U	0.000306 U	0.000275 U	0.000238 U	0.000260 U	0.000321 U
	B-242-40	4/4/18	PES	ESC	40	-1.2	S	0.000314 U	0.000424 U	0.000231 U	0.00115 U	0.000375 U	0.000334 U	0.000290 U	0.000392 U	0.000291 U	0.000261 U	0.000226 U	0.000247 U	0.000305 U
	B-242-45	4/4/18	PES	ESC	45	-6.2	S	0.000332 U	0.000449 U	0.000244 U	0.00121 U	0.000397 U	0.000353 U	0.000306 U	0.000414 U	0.000308 U	0.000276 U	0.000239 U	0.000261 U	0.000323 U
	B-242-50	4/4/18	PES	ESC	50	-11.2	S	0.000321 U	0.000435 U	0.000236 U	0.00118 U	0.000384 U	0.000342 U	0.000297 U	0.000401 U	0.000298 U	0.000268 U	0.000232 U	0.000253 U	0.000312 U
	B-910-50	4/4/18	PES	ESC	50 (dup)	-11.2	S	0.000322 U	0.000435 U	0.000237 U	0.00118 U	0.000385 U	0.000342 U	0.000297 U	0.000402 U	0.000298 U	0.000268 U	0.000232 U	0.000254 U	0.000313 U
	B-242-55	4/4/18	PES	ESC	55	-16.2	S	0.000315 U	0.000426 U	0.000232 U	0.00115 U	0.000377 U	0.000335 U	0.000291 U	0.000393 U	0.000292 U	0.000263 U	0.000227 U	0.000248 U	0.000306 U
	B-242-60	4/4/18	PES	ESC	60	-21.2	S	0.000317 U	0.000428 U	0.000233 U	0.00116 U	0.000378 U	0.000336 U	0.000292 U	0.000395 U	0.000293 U	0.000264 U	0.000228 U	0.000249 U	0.000308 U
	B-242-65	4/4/18	PES	ESC	65	-26.2	S	0.000311 U	0.000420 U	0.000228 U	0.00114 U	0.000371 U	0.000330 U	0.000287 U	0.000388 U	0.000288 U	0.000259 U	0.000224 U	0.000245 U	0.000302 U
	B-242-70	4/4/18	PES	ESC	70	-31.2	S	0.000329 U	0.000444 U	0.000242 U	0.00120 U	0.000393 U	0.000349 U	0.000304 U	0.000410 U	0.000305 U	0.000274 U	0.000237 U	0.000259 U	0.000320 U
	B-242-75	4/4/18	PES	ESC	75	-36.2	S	0.000318 U	0.000430 U	0.000234 U	0.00116 U	0.000380 U	0.000338 U	0.000294 U	0.000397 U	0.000295 U	0.000265 U	0.000230 U	0.000251 U	0.000309 U
	B-242-80	4/4/18	PES	ESC	80	-41.2	S	0.000333 U	0.000450 U	0.000244 U	0.00122 U	0.000397 U	0.000353 U	0.000307 U	0.000415 U	0.000308 U	0.000277 U	0.000240 U	0.000262 U	0.000323 U
B-243	B-243-5	3/29/18	PES	ESC	5	34.9	S	0.000333 U	0.000451 U	0.000245 U	0.00122 U	0.000398 U	0.000354 U	0.000308 U	0.000416 U	0.000309 U	0.000278 U	0.000240 U	0.000262 U	0.000324 U
	B-243-10	3/29/18	PES	ESC	10	29.9	S	0.000326 U	0.000441 U	**0.00226**	0.00119 U	0.000390 U	0.000346 U	0.000301 U	0.000407 U	**0.00110 J**	0.000271 U	0.000235 U	0.000257 U	0.000317 U
	B-243-15	3/29/18	PES	ESC	15	24.9	S	0.00812 U	0.0110 U	0.00597 U	0.0296 U	0.00971 U	0.00862 U	0.00749 U	0.0101 U	0.00752 U	0.00677 U	0.00586 U	0.00639 U	0.00790 U
	B-243-20	3/29/18	PES	ESC	20	19.9	S	0.000331 U	0.000447 U	0.000243 U	0.00121 U	0.000396 U	0.000352 U	0.000306 U	0.000413 U	0.000307 U	0.000276 U	0.000239 U	0.000261 U	0.000322 U
	B-243-25	3/29/18	PES	ESC	25	14.9	S	0.000320 U	0.000432 U	0.000235 U	0.00117 U	0.000382 U	0.000340 U	0.000295 U	0.000399 U	0.000296 U	0.000266 U	0.000231 U	0.000252 U	0.000311 U
	B-243-30	3/29/18	PES	ESC	30	9.9	S	0.000313 U	0.000423 U	0.000230 U	0.00114 U	0.000374 U	0.000332 U	0.000289 U	0.000390 U	0.000290 U	0.000260 U	0.000225 U	0.000246 U	0.000304 U
	B-243-35	3/29/18	PES	ESC	35	4.9	S	0.000318 U	0.000430 U	0.000234 U	0.00116 U	0.000380 U	0.000338 U	0.000294 U	0.000397 U	0.000295 U	0.000265 U	0.000229 U	0.000250 U	0.000309 U
	B-243-42	3/29/18	PES	ESC	42	-2.1	S	0.000314 U	0.000424 U	0.000231 U	0.00115 U	0.000375 U	0.000333 U	0.000290 U	0.000391 U	0.000291 U	0.000261 U	0.000226 U	0.000247 U	0.000305 U
	B-243-45	3/29/18	PES	ESC	45	-5.1	S	0.000311 U	0.000420 U	0.000229 U	0.00114 U	0.000372 U	0.000330 U	0.000287 U	0.000388 U	0.000288 U	0.000259 U	0.000224 U	0.000245 U	0.000302 U
	B-243-50	3/29/18	PES	ESC	50	-10.1	S	0.000331 U	0.000448 U	0.000244 U	0.00121 U	0.000396 U	0.000352 U	0.000306 U	0.000413 U	0.000307 U	0.000276 U	0.000239 U	0.000261 U	0.000322 U
	IW-908-50	3/29/18	PES	ESC	50 (dup)	-10.1	S	0.000325 U	0.000439 U	0.000239 U	0.00119 U	0.000388 U	0.000345 U	0.000300 U	0.000405 U	0.000301 U	0.000270 U	0.000234 U	0.000256 U	0.000316 U
	B-243-55	3/29/18	PES	ESC	55	-15.1	S	0.000310 U	0.000419 U	0.000228 U	0.00113 U	0.000370 U	0.000329 U	0.000286 U	0.000387 U	0.000287 U	0.000258 U	0.000223 U	0.000244 U	0.000301 U
	B-243-60	3/29/18	PES	ESC	60	-20.1	S	0.000328 U	0.000443 U	0.000241 U	0.00120 U	0.000392 U	0.000349 U	0.000303 U	0.000409 U	0.000304 U	0.000273 U	0.000237 U	0.000258 U	0.000319 U
	B-243-65	3/29/18	PES	ESC	65	-25.1	S	0.000315 U	0.000426 U	0.000232 U	0.00115 U	0.000377 U	0.000335 U	0.000291 U	0.000393 U	0.000292 U	0.000262 U	0.000227 U	0.000248 U	0.000306 U
	B-243-70	3/29/18	PES	ESC	70	-30.1	S	0.000333 U	0.000450 U	0.000245 U	0.00122 U	0.000398 U	0.000354 U	0.000307 U	0.000415 U	0.000308 U	0.000277 U	0.000240 U	0.000262 U	0.000323 U
	B-243-75	3/29/18	PES	ESC	75	-35.1	S	0.000342 U	0.000462 U	0.000251 U	0.00125 U	0.000409 U	0.000363 U	0.000316 U	0.000427 U	0.000317 U	0.000285 U	0.000247 U	0.000269 U	0.000332 U
	B-243-80	3/29/18	PES	ESC	80	-40.1	S	0.000349 U	0.000471 U	0.000256 U	0.00128 U	0.000417 U	0.000370 U	0.000322 U	0.000435 U	0.000323 U	0.000290 U	0.000251 U	0.000275 U	0.000339 U
B-244	B-244-5	3/28/18	PES	ESC	5	33.8	S	0.000362 U	0.000490 U	**0.000583 J**	0.00133 U	0.000433 U	0.000385 U	0.000334 U	0.000452 U	0.000336 U	0.000302 U	0.000261 U	0.000285 U	0.000352 U
	B-244-10	3/28/18	PES	ESC	10	28.8	S	0.000342 U	0.000462 U	0.000251 U	0.00125 U	0.000409 U	0.000363 U	0.000316 U	0.000427 U	0.000317 U	0.000285 U	0.000247 U	0.000269 U	0.000332 U
	B-244-15	3/28/18	PES	ESC	15	23.8	S	0.000327 U	0.000443 U	0.000241 U	0.00120 U	0.000391 U	0.000348 U	0.000302 U	0.000408 U	0.000303 U	0.000273 U	0.000236 U	0.000258 U	0.000318 U
	B-244-20	3/28/18	PES	ESC	20	18.8	S	0.000326 U	0.000440 U	0.000239 U	0.00119 U	0.000389 U	0.000346 U	0.000301 U	0.000406 U	0.000302 U	0.000271 U	0.000235 U	0.000256 U	0.000317 U
	B-244-25	3/28/18	PES	ESC	25	13.8	S	0.000304 U	0.000411 U	0.000223 U	0.00111 U	0.000363 U	0.000323 U	0.000281 U	0.000379 U	0.000282 U	0.000253 U	0.000219 U	0.000239 U	0.000295 U
	B-244-30	3/28/18	PES	ESC	30	8.8	S	0.000314 U	0.000424 U	0.000231 U	0.00115 U	0.000375 U	0.000333 U	0.000290 U	0.000391 U	0.000291 U	0.000261 U	0.000226 U	0.000247 U	0.000305 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
B-244 (continued)	B-244-35	3/28/18	PES	ESC	35	3.8	S	0.000330 U	0.000446 U	0.000242 U	0.00121 U	0.000394 U	0.000350 U	0.000304 U	0.000411 U	0.000306 U	0.000275 U	0.000238 U	0.000260 U	0.000320 U
	B-244-40	3/28/18	PES	ESC	40	-1.2	S	0.000317 U	0.000428 U	0.000233 U	0.00116 U	0.000378 U	0.000336 U	0.000292 U	0.000395 U	0.000293 U	0.000264 U	0.000228 U	0.000249 U	0.000308 U
	B-244-42	3/28/18	PES	ESC	42	-3.2	S	0.00808 U	0.0109 U	0.00594 U	0.0295 U	0.00965 U	0.00857 U	0.00745 U	0.0101 U	0.00748 U	0.00673 U	0.00583 U	0.00636 U	0.00785 U
	B-244-45	3/28/18	PES	ESC	45	-6.2	S	0.000323 U	0.000437 U	0.000237 U	0.00118 U	0.000386 U	0.000343 U	0.000298 U	0.000403 U	0.000299 U	0.000269 U	0.000233 U	0.000254 U	0.000314 U
	B-244-50	3/28/18	PES	ESC	50	-11.2	S	0.000317 U	0.000429 U	0.000233 U	0.00116 U	0.000379 U	0.000337 U	0.000293 U	0.000396 U	0.000294 U	0.000264 U	0.000229 U	0.000250 U	0.000309 U
	B-244-55	3/28/18	PES	ESC	55	-16.2	S	0.000316 U	0.000427 U	0.000232 U	0.00116 U	0.000378 U	0.000336 U	0.000292 U	0.000394 U	0.000293 U	0.000263 U	0.000228 U	0.000249 U	0.000307 U
	B-244-60	3/28/18	PES	ESC	60	-21.2	S	0.000320 U	0.000433 U	0.000236 U	0.00117 U	0.000383 U	0.000340 U	0.000296 U	0.000400 U	0.000297 U	0.000267 U	0.000231 U	0.000252 U	0.000311 U
	B-244-65	3/28/18	PES	ESC	65	-26.2	S	0.000325 U	0.000440 U	0.000239 U	0.00119 U	0.000389 U	0.000346 U	0.000300 U	0.000406 U	0.000302 U	0.000271 U	0.000235 U	0.000256 U	0.000316 U
	B-244-70	3/28/18	PES	ESC	70	-31.2	S	0.000312 U	0.000421 U	0.000229 U	0.00114 U	0.000372 U	0.000331 U	0.000288 U	0.000389 U	0.000289 U	0.000259 U	0.000225 U	0.000245 U	0.000303 U
	IW-907-70	3/28/18	PES	ESC	70 (dup)	-31.2	S	0.000312 U	0.000422 U	0.000230 U	0.00114 U	0.000373 U	0.000332 U	0.000288 U	0.000390 U	0.000290 U	0.000260 U	0.000225 U	0.000246 U	0.000304 U
	B-244-75	3/28/18	PES	ESC	75	-36.2	S	0.000329 U	0.000445 U	0.000242 U	0.00120 U	0.000393 U	0.000350 U	0.000304 U	0.000411 U	0.000305 U	0.000274 U	0.000237 U	0.000259 U	0.000320 U
	B-244-80	3/28/18	PES	ESC	80	-41.2	S	0.000334 U	0.000451 U	0.000245 U	0.00122 U	0.000399 U	0.000355 U	0.000308 U	0.000416 U	0.000309 U	0.000278 U	0.000241 U	0.000263 U	0.000324 U
B-245	B-245-5	3/28/18	PES	ESC	5	34.9	V	0.000312 U	0.000422 U	0.000230 U	0.00114 U	0.000373 U	0.000332 U	0.000288 U	0.000390 U	0.000289 U	0.000260 U	0.000225 U	0.000246 U	0.000304 U
	B-245-10	3/28/18	PES	ESC	10	29.9	S	0.000329 U	0.000445 U	0.000242 U	0.00120 U	0.000393 U	0.000350 U	0.000304 U	0.000411 U	0.000305 U	0.000274 U	0.000237 U	0.000259 U	0.000320 U
	B-245-15	3/28/18	PES	ESC	15	24.9	S	0.000333 U	0.000450 U	0.000245 U	0.00122 U	0.000397 U	0.000353 U	0.000307 U	0.000415 U	0.000308 U	0.000277 U	0.000240 U	0.000262 U	0.000323 U
	B-245-20	3/28/18	PES	ESC	20	19.9	S	0.000310 U	0.000419 U	0.000228 U	0.00113 U	0.000370 U	0.000329 U	0.000286 U	0.000387 U	0.000287 U	0.000258 U	0.000224 U	0.000244 U	0.000301 U
	B-245-25	3/28/18	PES	ESC	25	14.9	S	0.000325 U	0.000439 U	0.000239 U	0.00119 U	0.000388 U	0.000345 U	0.000300 U	0.000405 U	0.000301 U	0.000270 U	0.000234 U	0.000256 U	0.000316 U
	B-245-30	3/29/18	PES	ESC	30	9.9	S	0.000617 U	0.000834 U	0.000454 U	0.00226 U	0.000738 U	0.000656 U	0.000570 U	0.000770 U	0.000572 U	0.000513 U	0.000445 U	0.000486 U	0.000599 U
	B-245-35	3/29/18	PES	ESC	35	4.9	S	0.000323 U	0.000437 U	0.000237 U	0.00118 U	0.000386 U	0.000343 U	0.000298 U	0.000403 U	0.000299 U	0.000269 U	0.000233 U	0.000254 U	0.000314 U
	B-245-40	3/29/18	PES	ESC	40	-0.1	S	0.000319 U	0.000432 U	0.000235 U	0.00117 U	0.000382 U	0.000339 U	0.000295 U	0.000398 U	0.000296 U	0.000266 U	0.000230 U	0.000252 U	0.000311 U
	B-245-45	3/29/18	PES	ESC	45	-5.1	S	0.000319 U	0.000431 U	0.000235 U	0.00117 U	0.000381 U	0.000339 U	0.000295 U	0.000398 U	0.000296 U	0.000266 U	0.000230 U	0.000251 U	0.000310 U
	B-245-50	3/29/18	PES	ESC	50	-10.1	S	0.000325 U	0.000440 U	0.000239 U	0.00119 U	0.000389 U	0.000346 U	0.000300 U	0.000406 U	0.000301 U	0.000271 U	0.000235 U	0.000256 U	0.000316 U
	B-245-55	3/29/18	PES	ESC	55	-15.1	S	0.000323 U	0.000437 U	0.000238 U	0.00118 U	0.000387 U	0.000344 U	0.000299 U	0.000403 U	0.000300 U	0.000269 U	0.000233 U	0.000255 U	0.000314 U
	B-245-60	3/29/18	PES	ESC	60	-20.1	S	0.000307 U	0.000416 U	0.000226 U	0.00112 U	0.000367 U	0.000327 U	0.000284 U	0.000383 U	0.000285 U	0.000256 U	0.000222 U	0.000242 U	0.000299 U
	B-245-65	3/29/18	PES	ESC	65	-25.1	S	0.000328 U	0.000444 U	0.000241 U	0.00120 U	0.000392 U	0.000349 U	0.000303 U	0.000410 U	0.000304 U	0.000273 U	0.000237 U	0.000259 U	0.000319 U
	B-245-70	3/29/18	PES	ESC	70	-30.1	S	0.000338 U	0.000456 U	0.000248 U	0.00124 U	0.000403 U	0.000359 U	0.000312 U	0.000421 U	0.000313 U	0.000281 U	0.000244 U	0.000266 U	0.000328 U
	B-245-75	3/29/18	PES	ESC	75	-35.1	S	0.000323 U	0.000437 U	0.000238 U	0.00118 U	0.000387 U	0.000344 U	0.000299 U	0.000403 U	0.000300 U	0.000269 U	0.000233 U	0.000255 U	0.000314 U
	B-245-80	3/29/18	PES	ESC	80	-40.1	S	0.000333 U	0.000450 U	0.000244 U	0.00122 U	0.000397 U	0.000353 U	0.000307 U	0.000415 U	0.000308 U	0.000277 U	0.000240 U	0.000262 U	0.000323 U
B-246	B-246-6	5/11/18	PES	ESC	6	33.9	S	0.00136 U	0.00572 U	0.00138 U	0.00605 U	0.000623 U	0.00172 U	0.000564 U	0.00151 U	0.00128 U	0.00202 U	0.00208 U	0.00234 U	0.000941 U
	B-246-11	5/11/18	PES	ESC	11	28.9	S	0.00136 U	0.00569 U	0.00137 U	0.00602 U	0.000620 U	0.00171 U	0.000561 U	0.00150 U	0.00128 U	0.00201 U	0.00207 U	0.00233 U	0.000936 U
	B-246-15	5/11/18	PES	ESC	15	24.9	S	0.00130 U	0.00545 U	0.00131 U	0.00576 U	0.000593 U	0.00164 U	0.000537 U	0.00144 U	0.00122 U	0.00192 U	0.00198 U	0.00223 U	0.000896 U
	B-246-25	5/11/18	PES	ESC	25	14.9	S	0.00129 U	0.00539 U	0.00130 U	0.00570 U	0.000587 U	0.00162 U	0.000531 U	0.00142 U	0.00121 U	0.00190 U	0.00196 U	0.00220 U	0.000887 U
	B-246-30	5/11/18	PES	ESC	30	9.9	S	0.00135 U	0.00567 U	0.00137 U	0.00600 U	0.000618 U	0.00171 U	0.000559 U	0.00149 U	0.00127 U	0.00200 U	0.00206 U	0.00232 U	0.000933 U
	B-246-35	5/11/18	PES	ESC	35	4.9	S	0.00133 U	0.00556 U	0.00134 U	0.00588 U	0.000605 U	0.00167 U	0.000548 U	0.00146 U	0.00125 U	0.00196 U	0.00202 U	0.00227 U	0.000914 U
	B-246-40	5/11/18	PES	ESC	40	-0.1	S	0.00130 U	0.00546 U	0.00131 U	0.00578 U	0.000595 U	0.00164 U	0.000538 U	0.00144 U	0.00122 U	0.00193 U	0.00198 U	0.00223 U	0.000898 U
	B-246-43	5/11/18	PES	ESC	43	-3.1	S	0.00126 U	0.00527 U	0.00127 U	0.00558 U	0.000574 U	0.00159 U	0.000519 U	0.00139 U	0.00118 U	0.00186 U	0.00191 U	0.00215 U	0.000867 U
	B-246-45	5/11/18	PES	ESC	45	-5.1	S	0.00138 U	0.00581 U	0.00139 U	0.00615 U	0.000633 U	0.00174 U	0.000573 U	0.00153 U	0.00130 U	0.00205 U	0.00211 U	0.00238 U	0.000957 U
	B-246-50	5/11/18	PES	ESC	50	-10.1	S	0.00129 U	0.00542 U	0.00131 U	0.00574 U	0.000591 U	0.00163 U	0.000534 U	0.00143 U	0.00122 U	0.00191 U	0.00197 U	0.00222 U	0.000892 U
	B-246-55	5/11/18	PES	ESC	55	-15.1	S	0.00132 U	0.00552 U	0.00133 U	0.00584 U	0.000601 U	0.00166 U	0.000544 U	0.00145 U	0.00124 U	0.00195 U	0.00200 U	0.00226 U	0.000908 U
	B-246-60	5/11/18	PES	ESC	60	-20.1	S	0.00131 U	0.00547 U	0.00132 U	0.00579 U	0.000596 U	0.00165 U	0.000539 U	0.00144 U	0.00123 U	0.00193 U	0.00199 U	0.00224 U	0.000900 U
	B-246-65	5/11/18	PES	ESC	65	-25.1	S	0.00142 U	0.00596 U	0.00143 U	0.00631 U	0.000649 U	0.00179 U	0.000588 U	0.00157 U	0.00134 U	0.00210 U	0.00216 U	0.00244 U	0.000981 U
	B-246-70	5/11/18	PES	ESC	70	-30.1	S	0.00128 U	0.00536 U	0.00129 U	0.00567 U	0.000584 U	0.00161 U	0.000528 U	0.00141 U	0.00120 U	0.00189 U	0.00195 U	0.00219 U	0.000881 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
B-246 (continued)	B-246-75	5/11/18	PES	ESC	75	-35.1	S	0.00133 U	0.00558 U	0.00134 U	0.00591 U	0.000608 U	0.00168 U	0.000550 U	0.00147 U	0.00125 U	0.00197 U	0.00203 U	0.00228 U	0.000919 U
	B-246-80	5/11/18	PES	ESC	80	-40.1	S	0.00130 U	0.00544 U	0.00131 U	0.00576 U	0.000593 U	0.00164 U	0.000536 U	0.00143 U	0.00122 U	0.00192 U	0.00198 U	0.00223 U	0.000896 U
	B-926-100	5/11/18	PES	ESC	45 (dup)	-5.1	S	0.00173 U	0.00721 U	0.00174 U	0.00764 U	0.000786 U	0.00218 U	0.000712 U	0.00190 U	0.00162 U	0.00255 U	0.00262 U	0.00295 U	0.00119 U
B-247	B-247-5	4/20/18	PES	ESC	5	34.7	S	0.000326 U	0.000440 U	0.000240 U	0.00119 U	0.000389 U	0.000346 U	0.000301 U	0.000406 U	0.000302 U	0.000271 U	0.000235 U	0.000257 U	0.000317 U
	B-247-10	4/20/18	PES	ESC	10	29.7	S	0.000330 U	0.000447 U	0.000243 U	0.00121 U	0.000395 U	0.000351 U	0.000305 U	0.000412 U	0.000306 U	0.000275 U	0.000238 U	0.000260 U	0.000321 U
	B-247-15	4/20/18	PES	ESC	15	24.7	S	0.000318 U	0.000430 U	0.000234 U	0.00116 U	0.000380 U	0.000338 U	0.000294 U	0.000397 U	0.000295 U	0.000265 U	0.000230 U	0.000251 U	0.000309 U
	B-247-20	4/20/18	PES	ESC	20	19.7	S	0.000320 U	0.000433 U	0.000236 U	0.00117 U	0.000383 U	0.000341 U	0.000296 U	0.000400 U	0.000297 U	0.000267 U	0.000231 U	0.000252 U	0.000312 U
	B-247-25	4/20/18	PES	ESC	25	14.7	S	0.000312 U	0.000422 U	0.000230 U	0.00114 U	0.000373 U	0.000332 U	0.000288 U	0.000390 U	0.000289 U	0.000260 U	0.000225 U	0.000246 U	0.000304 U
	B-247-30	4/20/18	PES	ESC	30	9.7	S	0.000316 U	0.000427 U	0.000232 U	0.00116 U	0.000378 U	0.000336 U	0.000292 U	0.000394 U	0.000293 U	0.000263 U	0.000228 U	0.000249 U	0.000307 U
	B-247-35	4/20/18	PES	ESC	35	4.7	S	0.000316 U	0.000428 U	0.000233 U	0.00116 U	0.000378 U	0.000336 U	0.000292 U	0.000395 U	0.000293 U	0.000263 U	0.000228 U	0.000249 U	0.000307 U
	B-247-40	4/20/18	PES	ESC	40	-0.3	S	0.000322 U	0.000436 U	0.000237 U	0.00118 U	0.000385 U	0.000342 U	0.000298 U	0.000402 U	0.000299 U	0.000268 U	0.000232 U	0.000254 U	0.000313 U
	B-247-45	4/20/18	PES	ESC	45	-5.3	S	0.000310 U	0.000419 U	0.000228 U	0.00113 U	0.000371 U	0.000330 U	0.000286 U	0.000387 U	0.000287 U	0.000258 U	0.000224 U	0.000244 U	0.000301 U
	B-247-50	4/20/18	PES	ESC	50	-10.3	S	0.000316 U	0.000427 U	0.000232 U	0.00116 U	0.000378 U	0.000336 U	0.000292 U	0.000394 U	0.000293 U	0.000263 U	0.000228 U	0.000249 U	0.000307 U
	B-247-55	4/20/18	PES	ESC	55	-15.3	S	0.000324 U	0.000438 U	0.000238 U	0.00119 U	0.000387 U	0.000345 U	0.000299 U	0.000404 U	0.000300 U	0.000270 U	0.000234 U	0.000255 U	0.000315 U
	B-247-60	4/20/18	PES	ESC	60	-20.3	S	0.000309 U	0.000418 U	0.000227 U	0.00113 U	0.000370 U	0.000329 U	0.000285 U	0.000386 U	0.000287 U	0.000257 U	0.000223 U	0.000243 U	0.000301 U
	B-247-65	4/20/18	PES	ESC	65	-25.3	S	0.000320 U	0.000433 U	0.000235 U	0.00117 U	0.000383 U	0.000340 U	0.000296 U	0.000399 U	0.000297 U	0.000267 U	0.000231 U	0.000252 U	0.000311 U
	B-247-70	4/20/18	PES	ESC	70	-30.3	S	0.000322 U	0.000435 U	0.000236 U	0.00118 U	0.000384 U	0.000342 U	0.000297 U	0.000401 U	0.000298 U	0.000268 U	0.000232 U	0.000253 U	0.000313 U
	B-247-75	4/20/18	PES	ESC	75	-35.3	S	0.000328 U	0.000444 U	0.000241 U	0.00120 U	0.000392 U	0.000349 U	0.000303 U	0.000409 U	0.000304 U	0.000273 U	0.000237 U	0.000258 U	0.000319 U
	B-247-80	4/20/18	PES	ESC	80	-40.3	S	0.000321 U	0.000434 U	0.000236 U	0.00117 U	0.000383 U	0.000341 U	0.000296 U	0.000400 U	0.000297 U	0.000267 U	0.000231 U	0.000253 U	0.000312 U
	B-909-20	4/20/18	PES	ESC	80 (dup)	-40.3	S	0.000311 U	0.000420 U	0.000228 U	0.00114 U	0.000371 U	0.000330 U	0.000287 U	0.000388 U	0.000288 U	0.000259 U	0.000224 U	0.000245 U	0.000302 U
B-248	B-248-5	4/23/18	PES	ESC	5	46.9	V	0.000328 U	0.000443 U	0.000241 U	0.00120 U	0.000392 U	0.000348 U	0.000302 U	0.000409 U	0.000304 U	0.000273 U	0.000236 U	0.000258 U	0.000318 U
	B-248-10	4/23/18	PES	ESC	10	41.9	V	0.000320 U	0.000433 U	0.000235 U	0.00117 U	0.000382 U	0.000340 U	0.000295 U	0.000399 U	0.000297 U	0.000266 U	0.000231 U	0.000252 U	0.000311 U
	B-248-15	4/23/18	PES	ESC	15	36.9	V	0.00126 U	0.00530 U	0.00128 U	0.00561 U	0.000577 U	0.00159 U	0.000522 U	0.00140 U	0.00119 U	0.00187 U	0.00192 U	0.00217 U	0.000872 U
	B-248-20	4/23/18	PES	ESC	20	31.9	S	0.000310 U	0.000420 U	0.000228 U	0.00114 U	0.000371 U	0.000330 U	0.000287 U	0.000387 U	0.000288 U	0.000258 U	0.000224 U	0.000244 U	0.000302 U
	B-248-25	4/23/18	PES	ESC	25	26.9	S	0.00135 U	0.00566 U	0.00136 U	0.00598 U	0.000616 U	0.00170 U	0.000557 U	0.00149 U	0.00127 U	0.00199 U	0.00205 U	0.00231 U	0.000930 U
	B-248-30	4/23/18	PES	ESC	30	21.9	S	0.000310 U	0.000419 U	0.000228 U	0.00114 U	0.000371 U	0.000330 U	0.000287 U	0.000387 U	0.000288 U	0.000258 U	0.000224 U	0.000244 U	0.000302 U
	B-248-35	4/23/18	PES	ESC	35	16.9	S	0.00125 U	0.00522 U	0.00126 U	0.00552 U	0.000569 U	0.00157 U	0.000515 U	0.00138 U	0.00117 U	0.00184 U	0.00190 U	0.00213 U	0.000859 U
	B-248-40	4/23/18	PES	ESC	40	11.9	S	0.00128 U	0.00537 U	0.00129 U	0.00569 U	0.000585 U	0.00162 U	0.000530 U	0.00142 U	0.00120 U	0.00190 U	0.00195 U	0.00220 U	0.000884 U
	B-248-45	4/23/18	PES	ESC	45	6.9	S	0.00131 U	0.00550 U	0.00132 U	0.00582 U	0.000600 U	0.00166 U	0.000542 U	0.00145 U	0.00123 U	0.00194 U	0.00200 U	0.00225 U	0.000906 U
	B-248-50	4/23/18	PES	ESC	50	1.9	S	0.00126 U	0.00527 U	0.00127 U	0.00558 U	0.000574 U	0.00159 U	0.000519 U	0.00139 U	0.00118 U	0.00186 U	0.00191 U	0.00215 U	0.000867 U
	B-248-55	4/23/18	PES	ESC	55	-3.2	S	0.000340 U	0.000459 U	0.000250 U	0.00124 U	0.000406 U	0.000361 U	0.000314 U	0.000424 U	0.000315 U	0.000283 U	0.000245 U	0.000267 U	0.000330 U
	B-248-60	4/23/18	PES	ESC	60	-8.2	S	0.00123 U	0.00517 U	0.00124 U	0.00547 U	0.000563 U	0.00155 U	0.000509 U	0.00136 U	0.00116 U	0.00182 U	0.00188 U	0.00211 U	0.000850 U
	B-248-65	4/23/18	PES	ESC	65	-13.2	S	0.00141 U	0.00593 U	0.00143 U	0.00627 U	0.000646 U	0.00178 U	0.000584 U	0.00156 U	0.00133 U	0.00209 U	0.00215 U	0.00242 U	0.000975 U
	B-248-70	4/23/18	PES	ESC	70	-18.2	S	0.00132 U	0.00554 U	0.00133 U	0.00586 U	0.000603 U	0.00167 U	0.000546 U	0.00146 U	0.00124 U	0.00195 U	0.00201 U	0.00226 U	0.000911 U
	B-248-75	4/23/18	PES	ESC	75	-23.2	S	0.00129 U	0.00541 U	0.00130 U	0.00573 U	0.000590 U	0.00163 U	0.000534 U	0.00143 U	0.00121 U	0.00191 U	0.00197 U	0.00221 U	0.000891 U
	B-248-80	4/23/18	PES	ESC	80	-28.2	S	0.000345 U	0.000466 U	0.000254 U	0.00126 U	0.000412 U	0.000366 U	0.000318 U	0.000430 U	0.000320 U	0.000287 U	0.000249 U	0.000272 U	0.000335 U
	B-910-20	4/23/18	PES	ESC	80 (dup)	-28.2	S	0.000354 U	0.000479 U	0.000260 U	0.00130 U	0.000423 U	0.000376 U	0.000327 U	0.000442 U	0.000328 U	0.000295 U	0.000255 U	0.000279 U	0.000344 U
	B-248-85	4/23/18	PES	ESC	85	-33.2	S	0.000348 U	0.000471 U	0.000256 U	0.00127 U	0.000416 U	0.000370 U	0.000322 U	0.000435 U	0.000323 U	0.000290 U	0.000251 U	0.000274 U	0.000339 U
	B-248-90	4/23/18	PES	ESC	90	-38.2	S	0.000343 U	0.000464 U	0.000252 U	0.00126 U	0.000410 U	0.000365 U	0.000317 U	0.000428 U	0.000318 U	0.000286 U	0.000248 U	0.000270 U	0.000334 U
	B-248-95	4/23/18	PES	ESC	95	-43.2	S	0.000358 U	0.000484 U	0.000263 U	0.00131 U	0.000428 U	0.000380 U	0.000330 U	0.000446 U	0.000332 U	0.000298 U	0.000258 U	0.000282 U	0.000348 U
	B-248-100	4/23/18	PES	ESC	100	-48.2	S	0.000348 U	0.000471 U	0.000256 U	0.00127 U	0.000416 U	0.000370 U	0.000321 U	0.000434 U	0.000323 U	0.000290 U	0.000251 U	0.000274 U	0.000338 U
	B-248-105	4/23/18	PES	ESC	105	-53.2	S	0.000310 U	0.000419 U	0.000228 U	0.00113 U	0.000371 U	0.000330 U	0.000286 U	0.000387 U	0.000287 U	0.000258 U	0.000224 U	0.000244 U	0.000301 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
B-248	B-248-110	4/23/18	PES	ESC	110	-58.2	S	0.00132 U	0.00553 U	0.00133 U	0.00585 U	0.000602 U	0.00166 U	0.000545 U	0.00146 U	0.00124 U	0.00195 U	0.00201 U	0.00226 U	0.000910 U
(continued)	B-248-115	4/23/18	PES	ESC	115	-63.2	S	0.000336 U	0.000454 U	0.000247 U	0.00123 U	0.000401 U	0.000357 U	0.000310 U	0.000419 U	0.000311 U	0.000279 U	0.000242 U	0.000264 U	0.000326 U
B-249	B-249-5	10/15/18	PES	PACE	5	34.2	S	0.00120 U	0.00504 U	0.00121 U	0.00533 U	0.000549 U	0.00152 U	0.000496 U	0.00133 U	0.00113 U	0.00178 U	0.00183 U	0.00206 U	0.000829 U
	B-249-8	10/15/18	PES	PACE	8	31.2	S	0.00130 U	0.00544 U	0.00131 U	0.00576 U	0.000592 U	0.00164 U	0.000536 U	0.00143 U	0.00122 U	0.00192 U	0.00197 U	0.00222 U	0.000895 U
	B-249-15	10/15/18	PES	PACE	15	24.2	S	**0.0203**	0.00558 U	**0.0425 J**	0.00591 U	0.000608 U	0.00168 U	0.000550 U	0.00147 U	**0.0118**	0.00197 U	0.00203 U	0.00228 U	0.000918 U
	B-249-17	10/15/18	PES	PACE	17	22.2	S	0.00130 U	0.00546 U	0.00131 U	0.00577 U	0.000594 U	0.00164 U	0.000538 U	0.00144 U	0.00122 U	0.00192 U	0.00198 U	0.00223 U	0.000898 U
	B-249-20	10/15/18	PES	PACE	20	19.2	S	0.00136 U	0.00569 U	0.00137 U	0.00603 U	0.000620 U	0.00171 U	0.000561 U	0.00150 U	0.00128 U	0.00201 U	0.00207 U	0.00233 U	0.000937 U
B-250	B-250-2.5	10/15/18	PES	PACE	2.5	36.9	V	0.00127 U	0.00532 U	0.00128 U	0.00563 U	0.000580 U	0.00160 U	0.000524 U	0.00140 U	0.00119 U	0.00188 U	0.00193 U	0.00218 U	0.000876 U
	B-250-8	10/15/18	PES	PACE	8	31.4	S	0.00128 U	0.00537 U	0.00129 U	0.00568 U	0.000585 U	0.00161 U	0.000529 U	0.00141 U	0.00120 U	0.00189 U	0.00195 U	0.00219 U	0.000883 U
	B-250-10	10/15/18	PES	PACE	10	29.4	S	0.00128 U	0.00536 U	0.00129 U	0.00567 U	0.000584 U	0.00161 U	0.000528 U	0.00141 U	0.00120 U	0.00189 U	0.00195 U	0.00219 U	0.000882 U
	B-250-13	10/15/18	PES	PACE	13	26.4	S	0.00129 U	0.00541 U	0.00130 U	0.00573 U	0.000590 U	0.00163 U	0.000534 U	0.00143 U	0.00121 U	0.00191 U	0.00197 U	0.00221 U	0.000891 U
	B-250-20	10/15/18	PES	PACE	20	19.4	S	0.00133 U	0.00558 U	0.00134 U	0.00591 U	0.000608 U	0.00168 U	0.000550 U	0.00147 U	0.00125 U	0.00197 U	0.00203 U	0.00228 U	0.000919 U
	B-250-24	10/15/18	PES	PACE	24	15.4	S	0.00126 U	0.00527 U	**0.00130 J**	0.00558 U	0.000574 U	0.00159 U	0.000520 U	0.00139 U	0.00118 U	0.00186 U	0.00191 U	0.00215 U	0.000867 U
	B-250-30	10/16/18	PES	PACE	30	9.4	S	0.00125 U	0.00526 U	**0.00182 J**	0.00556 U	0.000573 U	0.00158 U	0.000518 U	0.00138 U	0.00118 U	0.00185 U	0.00191 U	0.00215 U	0.000865 U
B-251	B-251-5	10/15/18	PES	PACE	5	34.3	S	0.00121 U	0.00506 U	0.00122 U	0.00536 U	0.000552 U	0.00152 U	0.000499 U	0.00133 U	0.00113 U	0.00179 U	0.00184 U	0.00207 U	0.000833 U
	B-251-8	10/15/18	PES	PACE	8	31.3	S	0.00128 U	0.00535 U	0.00129 U	0.00566 U	0.000582 U	0.00161 U	0.000527 U	0.00141 U	0.00120 U	0.00189 U	0.00194 U	0.00219 U	0.000880 U
	B-251-10	10/15/18	PES	PACE	10	29.3	S	0.00128 U	0.00536 U	0.00129 U	0.00567 U	0.000584 U	0.00161 U	0.000528 U	0.0565 U	0.00120 U	0.00189 U	0.00195 U	0.00219 U	0.000882 U
	B-251-15	10/15/18	PES	PACE	15	24.3	S	0.00130 U	0.00545 U	0.00131 U	0.00577 U	0.000594 U	0.00164 U	0.000537 U	0.0574 U	0.00122 U	0.00192 U	0.00198 U	0.00223 U	0.000897 U
	B-251-20	10/15/18	PES	PACE	20	19.3	S	0.00135 U	0.00564 U	0.00136 U	0.00597 U	0.000615 U	0.00170 U	0.000556 U	0.0595 U	0.00126 U	0.00199 U	0.00205 U	0.00231 U	0.000929 U
	B-251-25	10/15/18	PES	PACE	25	14.3	S	0.00132 U	0.00554 U	0.00133 U	0.00586 U	0.000603 U	0.00167 U	0.000546 U	0.00146 U	0.00124 U	0.00195 U	0.00201 U	0.00226 U	0.000911 U
B-252	B-252-2.5	10/15/18	PES	PACE	2.5	36.7	V	0.00120 U	0.00504 U	0.00121 U	0.00533 U	0.000549 U	0.00151 U	0.000496 U	0.00133 U	0.00113 U	0.00178 U	0.00183 U	0.00206 U	0.000829 U
	B-252-8	10/15/18	PES	PACE	8	31.2	S	0.00123 U	0.00516 U	0.00124 U	0.00546 U	0.000562 U	0.00155 U	0.000508 U	0.00136 U	0.00116 U	0.00182 U	0.00187 U	0.00211 U	0.000848 U
	B-252-10	10/15/18	PES	PACE	10	29.2	S	0.00128 U	0.00534 U	0.00129 U	0.00565 U	0.000582 U	0.00161 U	0.000527 U	0.00141 U	0.00120 U	0.00188 U	0.00194 U	0.00218 U	0.000879 U
	B-252-15	10/15/18	PES	PACE	15	24.2	S	0.00135 U	0.00568 U	0.00137 U	0.00601 U	0.000619 U	0.00171 U	0.000560 U	0.0299 U	0.00127 U	0.00200 U	0.00206 U	0.00232 U	0.000934 U
	B-252-19	10/15/18	PES	PACE	19	20.2	S	0.00139 U	0.00582 U	0.00140 U	0.00616 U	0.000634 U	0.00175 U	0.000573 U	0.0153 U	0.00130 U	0.00205 U	0.00211 U	0.00238 U	0.000957 U
	B-252-25	10/15/18	PES	PACE	25	14.2	S	0.00126 U	0.00529 U	0.00127 U	0.00560 U	0.000577 U	0.00159 U	0.000522 U	0.00558 U	0.00119 U	0.00187 U	0.00192 U	0.00216 U	0.000871 U
	B-252-29	10/15/18	PES	PACE	29	10.2	S	0.00132 U	0.00552 U	0.00133 U	0.00584 U	0.000601 U	0.00166 U	0.000544 U	0.00145 U	0.00124 U	0.00195 U	0.00200 U	0.00225 U	0.000907 U
B-253A	B-253A-5	10/18/18	PES	PACE	5	35.6	V	0.00131 U	0.00549 U	0.00132 U	0.00581 U	0.000598 U	0.00165 U	0.000541 U	0.00145 U	0.00123 U	0.00194 U	0.00199 U	0.00224 U	0.000903 U
	B-253A-8	10/18/18	PES	PACE	8	32.6	S	0.00130 U	0.00543 U	0.00131 U	0.00574 U	0.000591 U	0.00163 U	0.000535 U	0.00572 U	0.00122 U	0.00191 U	0.00197 U	0.00222 U	0.000893 U
	B-253A-10	10/18/18	PES	PACE	10	30.6	S	0.00126 U	0.00528 U	0.00127 U	0.00559 U	0.000575 U	0.00159 U	0.000520 U	0.0139 U	0.00118 U	0.00186 U	0.00192 U	0.00216 U	0.000869 U
	B-253A-15	10/18/18	PES	PACE	15	25.6	S	0.00129 U	0.00541 U	**0.00139 J**	0.00573 U	0.000590 U	0.00163 U	0.000533 U	0.00143 U	0.00121 U	0.00191 U	0.00197 U	0.00221 U	0.000890 U
	B-253A-20	10/18/18	PES	PACE	20	20.6	S	0.00127 U	0.00531 U	0.00128 U	0.00562 U	0.000578 U	0.00160 U	0.000523 U	0.00560 U	0.00119 U	0.00187 U	0.00193 U	0.00217 U	0.000873 U
B-254	B-254-5	10/16/18	PES	PACE	5	34.7	S	0.00138 U	0.00577 U	0.00139 U	0.00611 U	0.000629 U	0.00174 U	0.000569 U	0.00152 U	0.00129 U	0.00204 U	0.00210 U	0.00236 U	0.000950 U
	B-254-10	10/16/18	PES	PACE	10	29.7	S	0.00131 U	0.00547 U	0.00132 U	0.00579 U	0.000596 U	0.00165 U	0.000539 U	0.00144 U	0.00123 U	0.00193 U	0.00199 U	0.00224 U	0.000900 U
	B-254-13.5	10/16/18	PES	PACE	13.5	26.2	S	**0.00223 J**	0.00565 U	**0.00657**	0.00598 U	0.000616 U	0.00170 U	0.000557 U	0.00149 U	**0.00219 J**	0.00199 U	0.00205 U	0.00231 U	0.000930 U
	B-254-20	10/16/18	PES	PACE	20	19.7	S	**0.00134 J**	0.00519 U	**0.00341 J**	0.00549 U	0.000565 U	0.00156 U	0.000511 U	0.00137 U	**0.00120 J**	0.00183 U	0.00188 U	0.00212 U	0.000853 U
	B-254-25	10/16/18	PES	PACE	25	14.7	S	**0.00170 J**	0.00539 U	**0.00517 J**	0.00570 U	0.000587 U	0.00162 U	0.000531 U	0.00142 U	**0.00138 J**	0.00190 U	0.00196 U	0.00220 U	0.000886 U
B-254A	B-254A-27	10/19/18	PES	PACE	27	12.7	S	0.00125 U	0.00527 U	**0.00139 J**	0.00557 U	0.000573 U	0.00158 U	0.000519 U	0.00138 U	0.00118 U	0.00186 U	0.00191 U	0.00215 U	0.000866 U
	B-254A-30	10/19/18	PES	PACE	30	9.7	S	0.00124 U	0.00519 U	**0.00210 J**	0.00549 U	0.000565 U	0.00156 U	0.000511 U	0.00137 U	0.00116 U	0.00183 U	0.00188 U	0.00212 U	0.000853 U
	B-254A-35	10/19/18	PES	PACE	35	4.7	S	**0.00126 J**	0.00508 U	**0.00195 J**	0.00537 U	0.000553 U	0.00153 U	0.000500 U	0.00134 U	0.00114 U	0.00179 U	0.00184 U	0.00208 U	0.000835 U
B-255	B-255-3.5	10/16/18	PES	PACE	3.5	36.3	S	0.00131 U	0.00550 U	0.00132 U	0.00582 U	0.000600 U	0.00166 U	0.000542 U	0.00145 U	0.00123 U	0.00194 U	0.00200 U	0.00225 U	0.000906 U
	B-255-8	10/16/18	PES	PACE	8	31.8	S	0.00133 U	0.00558 U	0.00134 U	0.00591 U	0.000608 U	0.00168 U	0.000550 U	0.00147 U	0.00125 U	0.00197 U	0.00203 U	0.00228 U	0.000919 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
B-255 (continued)	B-255-15	10/16/18	PES	PACE	15	24.8	S	0.00125 U	0.00525 U	0.00126 U	0.00556 U	0.000572 U	0.00158 U	0.000518 U	0.00138 U	0.00118 U	0.00185 U	0.00191 U	0.00215 U	0.000864 U
B-255A	B-255A-21	10/16/18	PES	PACE	21	18.8	S	**0.00196 J**	0.00510 U	**0.00387 J**	0.00540 U	0.000556 U	0.00153 U	0.000503 U	0.00134 U	**0.00130 J**	0.00180 U	0.00185 U	0.00209 U	0.000839 U
B-256	B-256-2.5	10/16/18	PES	PACE	2.5	37.1	S	0.00134 U	0.00564 U	0.00136 U	0.00596 U	0.000614 U	0.00170 U	0.000555 U	0.00149 U	0.00126 U	0.00199 U	0.00205 U	0.00230 U	0.000927 U
	B-256-5	10/16/18	PES	PACE	5	34.6	S	0.00127 U	0.00532 U	0.00128 U	0.00563 U	0.000580 U	0.00160 U	0.000525 U	0.00140 U	0.00119 U	0.00188 U	0.00193 U	0.00218 U	0.000876 U
	B-256-10	10/16/18	PES	PACE	10	29.6	S	0.00123 U	0.00515 U	0.00124 U	0.00545 U	0.000561 U	0.00155 U	0.000508 U	0.00136 U	0.00115 U	0.00182 U	0.00187 U	0.00211 U	0.000847 U
	B-256-15	10/16/18	PES	PACE	15	24.6	S	0.00127 U	0.00533 U	0.00128 U	0.00564 U	0.000581 U	0.00160 U	0.000526 U	0.00141 U	0.00120 U	0.00188 U	0.00194 U	0.00218 U	0.000878 U
	B-256-18	10/16/18	PES	PACE	18	21.6	S	0.00127 U	0.00533 U	0.00128 U	0.00564 U	0.000581 U	0.00160 U	0.000526 U	0.00141 U	0.00120 U	0.00188 U	0.00194 U	0.00218 U	0.000877 U
B-257	B-257-5	10/17/18	PES	PACE	5	34.4	S	0.00139 U	0.00584 U	0.00140 U	0.00617 U	0.000636 U	0.00176 U	0.000575 U	0.00154 U	0.00131 U	0.00206 U	0.00212 U	0.00239 U	0.000960 U
	B-257-10	10/17/18	PES	PACE	10	29.4	S	0.00128 U	0.00538 U	0.00130 U	0.00569 U	0.000586 U	0.00162 U	0.000530 U	0.00142 U	0.00121 U	0.00190 U	0.00195 U	0.00220 U	0.000885 U
	B-257-15	10/17/18	PES	PACE	15	24.4	S	0.00134 U	0.00560 U	0.00135 U	0.00592 U	0.000610 U	0.00168 U	0.000552 U	0.00148 U	0.00125 U	0.00197 U	0.00203 U	0.00229 U	0.000921 U
	B-257-20	10/17/18	PES	PACE	20	19.4	S	0.00129 U	0.00542 U	0.00130 U	0.00573 U	0.000590 U	0.00163 U	0.000534 U	0.00143 U	0.00121 U	0.00191 U	0.00197 U	0.00221 U	0.000891 U
B-258	B-258-3	10/17/18	PES	PACE	3	36.2	V	0.00126 U	0.00528 U	0.00127 U	0.00559 U	0.000575 U	0.00159 U	0.000520 U	0.00139 U	0.00118 U	0.00186 U	0.00192 U	0.00216 U	0.000869 U
	B-258-8	10/17/18	PES	PACE	8	31.2	S	0.00131 U	0.00548 U	0.00132 U	0.00580 U	0.000597 U	0.00165 U	0.000540 U	0.00144 U	0.00123 U	0.00193 U	0.00199 U	0.00224 U	0.000902 U
	B-258-10	10/17/18	PES	PACE	10	29.2	S	0.00138 U	0.00577 U	0.00139 U	0.00610 U	0.000628 U	0.00174 U	0.000568 U	0.00152 U	0.00129 U	0.00203 U	0.00209 U	0.00236 U	0.000949 U
	B-258-15	10/17/18	PES	PACE	15	24.2	S	**0.00234 J**	0.114 U	0.00137 U	0.00602 U	0.000620 U	0.00171 U	0.000561 U	0.00150 U	**0.00148 J**	0.00201 U	0.00207 U	0.00232 U	**0.000945 J**
	B-258-20	10/17/18	PES	PACE	20	19.2	S	0.00128 U	0.00538 U	0.00129 U	0.00569 U	0.000586 U	0.00162 U	0.000530 U	0.00142 U	0.00121 U	0.00190 U	0.00195 U	0.00220 U	0.000885 U
B-259	B-259-2.5	10/17/18	PES	PACE	2.5	36.7	V	0.00129 U	0.00542 U	0.00131 U	0.00574 U	0.000591 U	0.00163 U	0.000535 U	0.00143 U	0.00122 U	0.00191 U	0.00197 U	0.00222 U	0.000893 U
	B-259-5	10/17/18	PES	PACE	5	34.2	S	0.00126 U	0.00528 U	0.00127 U	0.00559 U	0.000575 U	0.00159 U	0.000521 U	0.00139 U	0.00118 U	0.00186 U	0.00192 U	0.00216 U	0.000869 U
	B-259-10	10/17/18	PES	PACE	10	29.2	S	0.00132 U	0.00552 U	0.00133 U	0.00584 U	0.000602 U	0.00166 U	0.000544 U	0.00146 U	0.00124 U	0.00195 U	0.00201 U	0.00226 U	0.000909 U
	B-259-15	10/17/18	PES	PACE	15	24.2	S	0.00135 U	0.00566 U	0.00136 U	0.00599 U	0.000616 U	0.00170 U	0.000558 U	0.00149 U	0.00127 U	0.00200 U	0.00205 U	0.00231 U	0.000931 U
	B-259-20	10/17/18	PES	PACE	20	19.2	S	0.00129 U	0.00539 U	0.00130 U	0.00570 U	0.000587 U	0.00162 U	0.000531 U	0.00142 U	0.00121 U	0.00190 U	0.00196 U	0.00220 U	0.000886 U
B-260	B-260-5	10/17/18	PES	PACE	5	34.2	S	0.00128 U	0.00535 U	0.00129 U	0.00566 U	0.000582 U	0.00161 U	0.000527 U	0.00141 U	0.00120 U	0.00189 U	0.00194 U	0.00218 U	0.000879 U
	B-260-8	10/17/18	PES	PACE	8	31.2	S	0.00129 U	0.00541 U	**0.00132 J**	0.00572 U	0.000589 U	0.00163 U	0.000533 U	0.00143 U	0.00121 U	0.00191 U	0.00196 U	0.00221 U	0.000890 U
	B-260-10	10/17/18	PES	PACE	10	29.2	S	0.00132 U	0.00553 U	0.00133 U	0.00585 U	0.000602 U	0.00166 U	0.000545 U	0.00146 U	0.00124 U	0.00195 U	0.00201 U	0.00226 U	0.000910 U
	B-260-15	10/17/18	PES	PACE	15	24.2	S	0.00134 U	0.0560 U	0.00135 U	0.00592 U	0.000610 U	0.00168 U	0.000552 U	0.00147 U	0.00125 U	0.00197 U	0.00203 U	0.00229 U	0.000921 U
	B-260-20	10/17/18	PES	PACE	20	19.2	S	0.00127 U	0.0533 U	0.00128 U	0.00564 U	0.000580 U	0.00160 U	0.000525 U	0.00140 U	0.00119 U	0.00188 U	0.00193 U	0.00218 U	0.000876 U
B-261	B-261-3	10/17/18	PES	PACE	3	36.9	S	0.00131 U	0.00551 U	0.00133 U	0.00583 U	0.000600 U	0.00166 U	0.000543 U	0.00145 U	0.00123 U	0.00194 U	0.00200 U	0.00225 U	0.000906 U
	B-261-5	10/17/18	PES	PACE	5	34.9	S	0.00130 U	0.437 U	0.00131 U	0.00578 U	0.000594 U	0.00164 U	0.000538 U	0.00144 U	0.00122 U	0.00193 U	0.00198 U	0.00223 U	0.000898 U
	B-261-8	10/17/18	PES	PACE	8	31.9	S	0.00138 U	0.0578 U	0.00139 U	0.00611 U	0.000629 U	0.00174 U	0.000569 U	0.00152 U	0.00129 U	0.00204 U	0.00210 U	0.00236 U	0.000950 U
	B-261-10	10/17/18	PES	PACE	10	29.9	S	0.00133 U	0.222 U	0.00134 U	0.00588 U	0.000605 U	0.00167 U	0.000547 U	0.00146 U	0.00124 U	0.00196 U	0.00202 U	0.00227 U	0.000914 U
	B-261-15	10/17/18	PES	PACE	15	24.9	S	0.00126 U	0.106 U	**0.00228 J**	0.00560 U	0.000577 U	0.00159 U	0.000522 U	0.00140 U	0.00119 U	0.00187 U	0.00192 U	0.00216 U	0.000871 U
	B-261-20	10/17/18	PES	PACE	20	19.9	S	**0.00393 J**	1.08 U	**0.0136**	0.00573 U	0.000590 U	0.00163 U	0.000534 U	0.00143 U	**0.00399 J**	0.00191 U	0.00197 U	0.00221 U	0.000891 U
B-262	B-262-5	10/17/18	PES	PACE	5	34.9	S	0.00135 U	0.00568 U	**0.00354 J**	0.00601 U	0.000618 U	0.00171 U	0.000560 U	0.00150 U	0.00127 U	0.00200 U	0.00206 U	0.00232 U	0.000934 U
	B-262-8	10/17/18	PES	PACE	8	31.9	S	0.00126 U	0.00530 U	0.00128 U	0.00561 U	0.000577 U	0.00159 U	0.000522 U	0.00140 U	0.00119 U	0.00187 U	0.00192 U	0.00217 U	0.000872 U
	B-262-10	10/17/18	PES	PACE	10	29.9	S	0.00128 U	0.00537 U	0.00129 U	0.00568 U	0.000585 U	0.00161 U	0.000529 U	0.00141 U	0.00120 U	0.00189 U	0.00195 U	0.00219 U	0.000883 U
	B-262-15	10/17/18	PES	PACE	15	24.9	S	0.00126 U	0.00529 U	0.00127 U	0.00560 U	0.000576 U	0.00159 U	0.000521 U	0.00139 U	0.00119 U	0.00187 U	0.00192 U	0.00216 U	0.000870 U
	B-262-20	10/17/18	PES	PACE	20	19.9	S	0.00135 U	0.00567 U	0.00137 U	0.00600 U	0.000618 U	0.00171 U	0.000559 U	0.00150 U	0.00127 U	0.00200 U	0.00206 U	0.00232 U	0.000934 U
B-263	B-263-3	10/18/18	PES	PACE	3	36.8	S	0.00141 U	0.00590 U	0.00142 U	0.00624 U	0.000643 U	0.00178 U	0.000582 U	0.00156 U	0.00132 U	0.00208 U	0.00214 U	0.00241 U	0.000971 U
	B-263-5	10/18/18	PES	PACE	5	34.8	S	0.00124 U	0.00521 U	0.00125 U	0.00551 U	0.000567 U	0.00157 U	0.000513 U	0.00137 U	0.00117 U	0.00184 U	0.00189 U	0.00213 U	0.000857 U
	B-263-8	10/18/18	PES	PACE	8	31.8	S	0.00121 U	0.00508 U	0.00122 U	0.00538 U	0.000554 U	0.00153 U	0.000501 U	0.00134 U	0.00114 U	0.00179 U	0.00185 U	0.00208 U	0.000836 U
	B-263-10	10/18/18	PES	PACE	10	29.8	S	0.00131 U	0.00549 U	0.00132 U	0.00580 U	0.000597 U	0.00165 U	0.000541 U	0.00145 U	0.00123 U	0.00193 U	0.00199 U	0.00224 U	0.000902 U
	B-263-15	10/18/18	PES	PACE	15	24.8	S	0.00126 U	0.00526 U	0.00127 U	0.00557 U	0.000573 U	0.00158 U	0.000519 U	0.00139 U	0.00118 U	0.00186 U	0.00191 U	0.00215 U	0.000866 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
B-263 (continued)	B-263-18	10/18/18	PES	PACE	18	21.8	S	0.00125 U	0.00523 U	0.00126 U	0.00553 U	0.000570 U	0.00157 U	0.000515 U	0.00138 U	0.00117 U	0.00184 U	0.00190 U	0.00214 U	0.000860 U
B-264	B-264-3	10/18/18	PES	PACE	3	36.8	S	0.00125 U	0.00523 U	0.00126 U	0.00554 U	0.000570 U	0.00157 U	0.000516 U	0.00138 U	0.00117 U	0.00185 U	0.00190 U	0.00214 U	0.000861 U
	B-264-5	10/18/18	PES	PACE	5	34.8	S	0.00133 U	0.00558 U	0.00134 U	0.00590 U	0.000608 U	0.00168 U	0.000550 U	0.00147 U	0.00125 U	0.00197 U	0.00203 U	0.00228 U	0.000918 U
	B-264-8	10/18/18	PES	PACE	8	31.8	S	0.00131 U	0.00551 U	0.00133 U	0.00583 U	0.000600 U	0.00166 U	0.000543 U	0.00145 U	0.00123 U	0.00194 U	0.00200 U	0.00225 U	0.000906 U
	B-264-10	10/18/18	PES	PACE	10	29.8	S	0.00127 U	0.00531 U	0.00128 U	0.00562 U	0.000578 U	0.00160 U	0.000523 U	0.00140 U	0.00119 U	0.00187 U	0.00193 U	0.00217 U	0.000874 U
	B-264-15	10/18/18	PES	PACE	15	24.8	S	0.00134 U	0.00561 U	0.00135 U	0.00593 U	0.000611 U	0.00169 U	0.000553 U	0.00148 U	0.00126 U	0.00198 U	0.00204 U	0.00229 U	0.000923 U
	B-264-16	10/18/18	PES	PACE	16	23.8	S	0.00129 U	0.00541 U	0.00130 U	0.00573 U	0.000589 U	0.00163 U	0.000533 U	0.00143 U	0.00121 U	0.00191 U	0.00196 U	0.00221 U	0.000890 U
B-265	B-265-3	10/18/18	PES	PACE	3	36.8	S	0.00137 U	0.00575 U	0.00138 U	0.00609 U	0.000627 U	0.00173 U	0.000567 U	0.00152 U	0.00129 U	0.00203 U	0.00209 U	0.00235 U	0.000946 U
	B-265-5	10/18/18	PES	PACE	5	34.8	S	0.00133 U	0.00559 U	0.00134 U	0.00591 U	0.000608 U	0.00168 U	0.000550 U	0.0147 U	0.00125 U	0.00197 U	0.00203 U	0.00228 U	0.000919 U
	B-265-8	10/18/18	PES	PACE	8	31.8	S	0.00128 U	0.00538 U	0.00129 U	0.00569 U	0.000586 U	0.00162 U	0.000530 U	0.0142 U	0.00121 U	0.00190 U	0.00195 U	0.00220 U	0.000885 U
	B-265-10	10/18/18	PES	PACE	10	29.8	S	0.00126 U	0.00530 U	0.00128 U	0.00561 U	0.000577 U	0.00159 U	0.000522 U	0.0112 U	0.00119 U	0.00187 U	0.00192 U	0.00217 U	0.000872 U
	B-265-17.5	10/18/18	PES	PACE	18	22.3	S	0.00127 U	0.00533 U	0.00128 U	0.00564 U	0.000581 U	0.00160 U	0.000526 U	0.00141 U	0.00119 U	0.00188 U	0.00194 U	0.00218 U	0.000877 U
B-266	B-266-5	10/18/18	PES	PACE	5	35.7	S	0.00140 U	0.00587 U	0.00141 U	0.00621 U	0.000640 U	0.00177 U	0.000579 U	0.00155 U	0.00132 U	0.00207 U	0.00213 U	0.00240 U	0.000966 U
	B-266-8	10/18/18	PES	PACE	8	32.7	S	0.00146 U	0.00613 U	0.00148 U	0.00649 U	0.000667 U	0.00185 U	0.000605 U	0.00160 U	0.00137 U	0.00216 U	0.00223 U	0.00251 U	0.00101 U
	B-266-10	10/18/18	PES	PACE	10	30.7	S	0.00185 U	0.00776 U	0.00187 U	0.00821 U	0.000845 U	0.00233 U	0.000765 U	0.00204 U	0.00173 U	0.00274 U	0.00282 U	0.00317 U	0.00128 U
	B-266-15	10/18/18	PES	PACE	15	25.7	S	0.00153 U	0.00643 U	0.00154 U	0.00681 U	0.000700 U	0.00193 U	0.000634 U	0.0169 U	0.00144 U	0.00227 U	0.00233 U	0.00262 U	0.00106 U
	B-266-20	10/18/18	PES	PACE	20	20.7	S	0.00128 U	0.00537 U	0.00129 U	0.00568 U	0.000585 U	0.00162 U	0.000529 U	0.0566 U	0.00120 U	0.00189 U	0.00195 U	0.00220 U	0.000884 U
B-267	B-267-2.5	10/18/18	PES	PACE	2.5	37.4	S	0.00138 U	0.00579 U	0.00139 U	0.00613 U	0.000631 U	0.00174 U	0.000571 U	0.00153 U	0.00130 U	0.00204 U	0.00210 U	0.00237 U	0.000953 U
	B-267-5	10/18/18	PES	PACE	5	34.9	S	0.00125 U	0.00526 U	0.00127 U	0.00556 U	0.000573 U	0.00158 U	0.000518 U	0.00139 U	0.00118 U	0.00185 U	0.00191 U	0.00215 U	0.000865 U
	B-267-8	10/18/18	PES	PACE	8	31.9	S	0.00137 U	0.00575 U	0.00138 U	0.00608 U	0.000626 U	0.00173 U	0.000567 U	0.00606 U	0.00129 U	0.00203 U	0.00209 U	0.00235 U	0.000946 U
	B-267-10	10/18/18	PES	PACE	10	29.9	S	0.00130 U	0.00545 U	0.00131 U	0.00576 U	0.000593 U	0.00164 U	0.000537 U	0.00574 U	0.00122 U	0.00192 U	0.00198 U	0.00223 U	0.000896 U
	B-267-15	10/18/18	PES	PACE	15	24.9	S	0.0257 U	0.108 U	0.0259 U	0.114 U	0.0117 U	0.0324 U	0.0106 U	0.0284 U	0.0241 U	0.0380 U	0.0391 U	0.0440 U	0.0178 U
	B-267-20	10/18/18	PES	PACE	20	19.9	S	0.0286 U	0.120 U	0.0288 U	0.127 U	0.0130 U	0.0360 U	0.0119 U	0.0316 U	0.0268 U	0.0423 U	0.0435 U	0.0489 U	0.0197 U
CA-A10	CA-A10-21	09/04/19	PES	Fremont	21	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-A12-20	CA-A12-20-24	09/06/19	PES	Fremont	24	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CAA-C1	CAA-C1-43	08/27/19	PES	Fremont	43	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CAA-C2	CAA-C2-10	08/28/19	PES	Fremont	10	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-B8	CA-B8-3	09/16/19	PES	Fremont	3	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-B19	CA-B19-30	09/27/19	PES	Fremont	30	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-B10	CA-B10-17	08/30/19	PES	Fremont	17	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	CA-B10-20	08/30/19	PES	Fremont	20	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	CA-B10-21	08/30/19	PES	Fremont	21	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	CA-B10-25	08/30/19	PES	Fremont	25	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-B11	CA-B11-27	09/05/19	PES	Fremont	27	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-B18	CA-B18-20	10/26/19	PES	Fremont	20	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-B20	CA-B20-31	09/30/19	PES	Fremont	31	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B-1001-31	09/30/19	PES	Fremont	31 (dup)	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-C7	CA-C7-25	09/20/19	PES	Fremont	25	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-C8	CA-C8-35	09/03/19	PES	Fremont	35	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-C9	CA-C9-09	09/04/19	PES	Fremont	9	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-C10	CA-C10-17	09/06/19	PES	Fremont	17	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	CA-C10-26	09/06/19	PES	Fremont	26	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-C13	CA-C13-Comp	09/11/19	PES	Fremont	Comp	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-D1	CA-D1-Comp	09/11/19	PES	Fremont	Comp	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-D2	CA-D2-31	09/16/19	PES	Fremont	31	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	CA-D2-50-52	09/17/19	PES	Fremont	52	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-D3	CA-D3-40	09/23/19	PES	Fremont	40	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-D4	CA-D4-51	09/19/19	PES	Fremont	51	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	CA-D4-54	09/19/19	PES	Fremont	54	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	**–**	**0.88**	**1.2**	**–**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	**–**	**0.058**	**0.068**	**–**
CA-D5	CA-D5-14	09/03/19	PES	Fremont	14	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	CA-D5-22	09/03/19	PES	Fremont	22	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	CA-D5-26	09/03/19	PES	Fremont	26	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-D6	CA-D6-56	09/04/19	PES	Fremont	56	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	CA-D6-65	09/04/19	PES	Fremont	65	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-D7	CA-D7-15	09/05/19	PES	Fremont	15	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
DB01	DB01-10	3/18/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB01-20	3/18/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB01-30	3/18/13	SES	F&BI	30	10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB01-40	3/18/13	SES	F&BI	40	0.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
DB02	DB02-10	3/18/13	SES	F&BI	10	26.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB02-15	3/18/13	SES	F&BI	15	21.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB02-20	3/18/13	SES	F&BI	20	16.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB02-30	3/18/13	SES	F&BI	30	6.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB02-40	3/18/13	SES	F&BI	40	-4.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
DB03	DB03-05	3/27/13	SES	F&BI	5	35.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB03-20	3/27/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB03-35	3/27/13	SES	F&BI	35	5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB03-45	3/27/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB03-55	3/27/13	SES	F&BI	55	-15.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB03-60	3/27/13	SES	F&BI	60	-20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
DB04	DB04-10	3/21/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB04-20	3/21/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB04-35	3/21/13	SES	F&BI	35	5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB04-45	3/21/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB04-50	3/22/13	SES	F&BI	50	-10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB04-60	3/22/13	SES	F&BI	60	-20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
DB05	DB05-10	3/26/13	SES	F&BI	10	41.8	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB05-20	3/26/13	SES	F&BI	20	31.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB05-30	3/26/13	SES	F&BI	30	21.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB05-40	3/26/13	SES	F&BI	40	11.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB05-50	3/26/13	SES	F&BI	50	1.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB05-60	3/26/13	SES	F&BI	60	-8.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB05-70	3/26/13	SES	F&BI	70	-18.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
DB06	DB06-10	3/25/13	SES	F&BI	10	41.8	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB06-25	3/25/13	SES	F&BI	25	26.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB06-35	3/25/13	SES	F&BI	35	16.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB06-45	3/25/13	SES	F&BI	45	6.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB06-55	3/25/13	SES	F&BI	55	-3.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB06-65	3/25/13	SES	F&BI	65	-13.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB06-75	3/25/13	SES	F&BI	75	-23.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	**–**	**0.88**	**1.2**	**–**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	**–**	**0.058**	**0.068**	**–**
DB07	DB07-05	3/27/13	SES	F&BI	5	35.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB07-15	3/27/13	SES	F&BI	15	25.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB07-25	3/27/13	SES	F&BI	25	15.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB07-35	3/28/13	SES	F&BI	35	5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB07-45	3/28/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB07-50	3/28/13	SES	F&BI	50	-10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB07-60	3/28/13	SES	F&BI	60	-20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB07-70	3/28/13	SES	F&BI	70	-30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
DB08	DB08-10	3/20/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB08-20	3/20/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB08-35	3/20/13	SES	F&BI	35	5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB08-45	3/20/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB08-50	3/21/13	SES	F&BI	50	-10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB08-60	3/21/13	SES	F&BI	60	-20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB08-70	3/21/13	SES	F&BI	70	-30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
DB09	DB09-10	3/19/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB09-20	3/19/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB09-30	3/19/13	SES	F&BI	30	10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB09-40	3/19/13	SES	F&BI	40	0.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB09-50	3/19/13	SES	F&BI	50	-10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB09-60	3/19/13	SES	F&BI	60	-20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB09-70	3/19/13	SES	F&BI	70	-30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
DB10	DB10-10	3/29/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB10-20	3/29/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB10-35	3/29/13	SES	F&BI	35	5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB10-45	3/29/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB10-50	4/1/13	SES	F&BI	50	-10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB10-60	4/1/13	SES	F&BI	60	-20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB10-70	4/1/13	SES	F&BI	70	-30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
DB11	DB11-15	4/2/13	SES	F&BI	15	36.8	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB11-25	4/2/13	SES	F&BI	25	26.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB11-35	4/2/13	SES	F&BI	35	16.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB11-45	4/2/13	SES	F&BI	45	6.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB11-55	4/2/13	SES	F&BI	55	-3.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
DB12	DB12-10	4/3/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB12-20	4/3/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB12-30	4/3/13	SES	F&BI	30	10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB12-40	4/3/13	SES	F&BI	40	0.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
DB13	DB13-10	4/3/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB13-20	4/3/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB13-35	4/3/13	SES	F&BI	35	5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB13-45	4/3/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	**–**	**0.88**	**1.2**	**–**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	**–**	**0.058**	**0.068**	**–**
DB14	DB14-10	4/4/13	SES	F&BI	10	31.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB14-20	4/4/13	SES	F&BI	20	21.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB14-30	4/4/13	SES	F&BI	30	11.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB14-40	4/4/13	SES	F&BI	40	1.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
G-MW1	MW 1-3-8	7/20/01	GeoEng	NCA	8	31.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW 1-8-20	7/20/01	GeoEng	NCA	20	19.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW 1-11-27.5	7/20/01	GeoEng	NCA	27.5	11.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW 1-13-32.5	7/20/01	GeoEng	NCA	32.5	6.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW 1-15-37.5	7/20/01	GeoEng	NCA	37.5	1.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
G-MW3 (G-SB4 11)	SB4-4-10	7/20/01	GeoEng	NCA	10	29.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB4-7-17.5	7/20/01	GeoEng	NCA	17.5	22.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB4-13-32.5	7/20/01	GeoEng	NCA	32.5	7.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB4-15-37.5	7/20/01	GeoEng	NCA	37.5	2.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
IW06	IW06-25	1/15/16	SES	F&BI	25	26.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-30	1/15/16	SES	F&BI	30	21.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-40	1/15/16	SES	F&BI	40	11.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-50	1/15/16	SES	F&BI	50	1.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-55	1/15/16	SES	F&BI	55	-3.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-60	1/15/16	SES	F&BI	60	-8.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-65	1/15/16	SES	F&BI	65	-13.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-70	1/15/16	SES	F&BI	70	-18.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-75	1/15/16	SES	F&BI	75	-23.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
IW-1C	IW-1C-5	3/7/18	PES	ESC	5	34.1	S	**0.000791 J**	0.000431 U	**0.00161**	0.00117 U	0.000381 U	0.000339 U	0.000294 U	0.000398 U	**0.000513 J**	0.000266 U	0.000230 U	0.000251 U	0.000310 U
(-23.9 to-38.9)	IW-1C-15	3/7/18	PES	ESC	15	24.1	S	0.000337 U	0.000456 U	0.000248 U	0.00123 U	0.000403 U	0.000358 U	0.000311 U	0.000420 U	0.000312 U	0.000281 U	0.000243 U	0.000265 U	0.000328 U
	IW-1C-25	3/7/18	PES	ESC	25	14.1	S	0.0682 U	0.0922 U	0.0501 U	0.249 U	0.0815 U	0.0724 U	0.0629 U	0.0850 U	0.0632 U	0.0568 U	0.0492 U	0.0537 U	0.0663 U
	IW-1C-35	3/7/18	PES	ESC	35	4.1	S	0.000308 U	0.000416 U	0.000226 U	0.00113 U	0.000368 U	0.000327 U	0.000284 U	0.000384 U	0.000285 U	0.000256 U	0.000222 U	0.000242 U	0.000299 U
	IW-1C-45	3/7/18	PES	ESC	45	-5.9	S	0.000321 U	0.000434 U	0.000236 U	0.00118 U	0.000384 U	0.000341 U	0.000297 U	0.000401 U	0.000298 U	0.000268 U	0.000232 U	0.000253 U	0.000312 U
	IW-1C-55	3/7/18	PES	ESC	55	-15.9	S	0.000321 U	0.000435 U	0.000236 U	0.00118 U	0.000384 U	0.000342 U	0.000297 U	0.000401 U	0.000298 U	0.000268 U	0.000232 U	0.000253 U	0.000312 U
	IW-1C-65	3/7/18	PES	ESC	65	-25.9	S	0.000330 U	0.000446 U	0.000242 U	0.00121 U	0.000394 U	0.000351 U	0.000305 U	0.000411 U	0.000306 U	0.000275 U	0.000238 U	0.000260 U	0.000321 U
	IW-1C-75	3/7/18	PES	ESC	75	-35.9	S	0.000345 U	0.000467 U	0.000254 U	0.00126 U	0.000413 U	0.000367 U	0.000319 U	0.000431 U	0.000320 U	0.000287 U	0.000249 U	0.000272 U	0.000336 U
IW-2C	IW-2C-5	3/7/18	PES	ESC	5	31.3	S	0.000354 U	0.000479 U	0.000261 U	0.00130 U	0.000424 U	0.000377 U	0.000327 U	0.000442 U	0.000329 U	0.000295 U	0.000256 U	0.000279 U	0.000345 U
(-24.8 to-39.8)	IW-2C-15	3/7/18	PES	ESC	15	21.3	S	0.000343 U	0.000464 U	0.000252 U	0.00125 U	0.000410 U	0.000364 U	0.000317 U	0.000428 U	0.000318 U	0.000286 U	0.000247 U	0.000270 U	0.000333 U
	IW-2C-25	3/7/18	PES	ESC	25	11.3	S	0.000321 U	0.000433 U	0.000236 U	0.00117 U	0.000383 U	0.000341 U	0.000296 U	0.000400 U	0.000297 U	0.000267 U	0.000231 U	0.000252 U	0.000312 U
	IW-2C-35	3/7/18	PES	ESC	35	1.3	S	0.000362 U	0.000489 U	0.000266 U	0.00132 U	0.000432 U	0.000384 U	0.000334 U	0.000451 U	0.000335 U	0.000301 U	0.000261 U	0.000285 U	0.000351 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
IW-2C (continued)	IW-2C-45	3/7/18	PES	ESC	45	-8.7	S	0.000311 U	0.000421 U	0.000229 U	0.00114 U	0.000372 U	0.000331 U	0.000287 U	0.000388 U	0.000288 U	0.000259 U	0.000224 U	0.000245 U	0.000303 U
	IW-2C-55	3/7/18	PES	ESC	55	-18.7	S	0.000334 U	0.000452 U	0.000246 U	0.00122 U	0.000400 U	0.000355 U	0.000309 U	0.000417 U	0.000310 U	0.000278 U	0.000241 U	0.000263 U	0.000325 U
	IW-2C-65	3/7/18	PES	ESC	65	-28.7	S	0.000314 U	0.000424 U	0.000231 U	0.00115 U	0.000375 U	0.000334 U	0.000290 U	0.000392 U	0.000291 U	0.000261 U	0.000226 U	0.000247 U	0.000305 U
	IW-2C-75	3/7/18	PES	ESC	75	-38.7	S	0.000345 U	0.000466 U	0.000253 U	0.00126 U	0.000412 U	0.000366 U	0.000318 U	0.000430 U	0.000319 U	0.000287 U	0.000249 U	0.000271 U	0.000335 U
IW-3C (-24.9 to-39.9)	IW-3C-5	3/9/18	PES	ESC	5	34.1	S	0.000314 U	0.000424 U	0.000231 U	0.00115 U	0.000375 U	0.000334 U	0.000290 U	0.000391 U	0.000291 U	0.000261 U	0.000226 U	0.000247 U	0.000305 U
	IW-3C-15	3/9/18	PES	ESC	15	24.1	S	0.00832 U	0.0112 U	0.00612 U	0.0304 U	0.00994 U	0.00883 U	0.00767 U	0.0104 U	0.00771 U	0.00693 U	0.00600 U	0.00655 U	0.00809 U
	IW-3C-25	3/9/18	PES	ESC	25	14.1	S	0.170 U	0.229 U	0.125 U	0.620 U	0.203 U	0.179 U	0.156 U	0.211 U	0.157 U	0.142 U	0.123 U	0.133 U	0.165 U
	IW-3C-35	3/9/18	PES	ESC	35	4.1	S	0.0638 U	0.0862 U	0.0469 U	0.233 U	0.0762 U	0.0678 U	0.0589 U	0.0796 U	0.0591 U	0.0531 U	0.0460 U	0.0502 U	0.0620 U
	IW-3C-45	3/9/18	PES	ESC	45	-5.9	S	0.000331 U	0.000447 U	0.000243 U	0.00121 U	0.000395 U	0.000352 U	0.000305 U	0.000413 U	0.000307 U	0.000275 U	0.000239 U	0.000260 U	0.000322 U
	IW-3C-55	3/9/18	PES	ESC	55	-15.9	S	0.000326 U	0.000440 U	0.000239 U	0.00119 U	0.000389 U	0.000346 U	0.000301 U	0.000406 U	0.000302 U	0.000271 U	0.000235 U	0.000256 U	0.000317 U
	IW-3C-65	3/9/18	PES	ESC	65	-25.9	S	0.000327 U	0.000443 U	0.000241 U	0.00120 U	0.000391 U	0.000348 U	0.000302 U	0.000408 U	0.000303 U	0.000273 U	0.000236 U	0.000258 U	0.000318 U
	IW-3C-75	3/9/18	PES	ESC	75	-35.9	S	0.000359 U	0.000486 U	0.000264 U	0.00131 U	0.000429 U	0.000382 U	0.000332 U	0.000448 U	0.000333 U	0.000299 U	0.000259 U	0.000283 U	0.000349 U
	IW-3C-79	3/9/18	PES	ESC	79	-39.9	S	0.000333 U	0.000451 U	0.000245 U	0.00122 U	0.000398 U	0.000354 U	0.000308 U	0.000416 U	0.000309 U	0.000278 U	0.000240 U	0.000263 U	0.000324 U
	IW-901-79	3/9/18	PES	ESC	79 (dup)	-39.9	S	0.000332 U	0.000449 U	0.000244 U	0.00121 U	0.000397 U	0.000353 U	0.000307 U	0.000414 U	0.000308 U	0.000276 U	0.000239 U	0.000261 U	0.000323 U
IW-7A (5.1 to-9.9)	IW-7A-5	3/16/18	PES	ESC	5	35.1	S	**0.00130**	0.000481 U	**0.00298**	0.00130 U	0.000425 U	0.000378 U	0.000328 U	0.000444 U	**0.000627 J**	0.000296 U	0.000257 U	0.000280 U	0.000346 U
	IW-7A-10	3/16/18	PES	ESC	10	30.1	S	**0.0262**	0.00257 U	**0.0498**	0.00328 U	0.00130 U	0.00160 U	0.000958 U	0.00175 U	**0.00664**	0.00183 U	0.000705 U	0.00178 U	0.000769 U
	IW-7A-15	3/16/18	PES	ESC	15	25.1	S	**0.102**	0.0156 U	**0.184**	0.0421 U	0.0138 U	0.0122 U	0.0106 U	0.0144 U	**0.0306 J**	0.00961 U	0.00833 U	0.00908 U	0.0112 U
	IW-7A-20	3/16/18	PES	ESC	20	20.1	S	**0.00672**	0.00264 U	**0.00804**	0.00337 U	0.00134 U	0.00164 U	0.000983 U	0.00180 U	**0.00328 J**	0.00188 U	0.000723 U	0.00183 U	0.000789 U
	IW-7A-25	3/16/18	PES	ESC	25	15.1	S	0.000348 U	0.000470 U	0.000256 U	0.00127 U	0.000415 U	0.000369 U	0.000321 U	0.000434 U	0.000322 U	0.000289 U	0.000251 U	0.000274 U	0.000338 U
	IW-7A-30	3/16/18	PES	ESC	30	10.1	S	0.000333 U	0.000450 U	0.000245 U	0.00122 U	0.000398 U	0.000354 U	0.000308 U	0.000415 U	0.000309 U	0.000277 U	0.000240 U	0.000262 U	0.000324 U
	IW-7A-35	3/16/18	PES	ESC	35	5.1	S	**0.00333**	0.00226 U	**0.00333**	0.00289 U	0.00115 U	0.00141 U	0.000842 U	0.00154 U	0.00197 U	0.00161 U	0.000620 U	0.00156 U	0.000676 U
	IW-7A-40	3/16/18	PES	ESC	40	0.1	S	0.000338 U	0.000457 U	0.000248 U	0.00124 U	0.000404 U	0.000359 U	0.000312 U	0.000422 U	0.000313 U	0.000281 U	0.000244 U	0.000266 U	0.000329 U
	IW-7A-45	3/16/18	PES	ESC	45	-4.9	S	0.000335 U	0.000454 U	0.000247 U	0.00123 U	0.000401 U	0.000356 U	0.000310 U	0.000418 U	0.000311 U	0.000279 U	0.000242 U	0.000264 U	0.000326 U
	IW-7A-50	3/16/18	PES	ESC	50	-9.9	S	0.000319 U	0.000431 U	0.000234 U	0.00117 U	0.000381 U	0.000339 U	0.000294 U	0.000398 U	0.000295 U	0.000265 U	0.000230 U	0.000251 U	0.000310 U
IW-8B (-9.8 to-24.8)	IW-8B-5	3/19/18	PES	ESC	5	34.2	S	0.000314 U	0.000425 U	0.000231 U	0.00115 U	0.000375 U	0.000334 U	0.000290 U	0.000392 U	0.000291 U	0.000262 U	0.000227 U	0.000247 U	0.000305 U
	IW-8B-10	3/19/18	PES	ESC	10	29.2	S	0.000309 U	0.000418 U	0.000227 U	0.00113 U	0.000370 U	0.000329 U	0.000286 U	0.000386 U	0.000287 U	0.000258 U	0.000223 U	0.000244 U	0.000301 U
	IW-8B-15	3/19/18	PES	ESC	15	24.2	S	0.0826 U	0.112 U	0.0608 U	0.302 U	0.0987 U	0.0877 U	0.0762 U	0.103 U	0.0765 U	0.0688 U	0.0596 U	0.0650 U	0.0803 U
	IW-8B-20	3/19/18	PES	ESC	20	19.2	S	0.000315 U	0.000426 U	0.000232 U	0.00115 U	0.000376 U	0.000335 U	0.000291 U	0.000393 U	0.000292 U	0.000262 U	0.000227 U	0.000248 U	0.000306 U
	IW-8B-25	3/19/18	PES	ESC	25	14.2	S	0.000336 U	0.000454 U	0.000247 U	0.00123 U	0.000401 U	0.000357 U	0.000310 U	0.000419 U	0.000311 U	0.000280 U	0.000242 U	0.000264 U	0.000327 U
	IW-8B-30	3/19/18	PES	ESC	30	9.2	S	0.000323 U	0.000436 U	0.000237 U	0.00118 U	0.000385 U	0.000343 U	0.000298 U	0.000402 U	0.000299 U	0.000269 U	0.000233 U	0.000254 U	0.000314 U
	IW-8B-40	3/19/18	PES	ESC	40	-0.8	S	0.000320 U	0.000433 U	0.000235 U	0.00117 U	0.000383 U	0.000340 U	0.000296 U	0.000399 U	0.000297 U	0.000267 U	0.000231 U	0.000252 U	0.000311 U
	IW-8B-45	3/20/18	PES	ESC	45	-5.8	S	0.000320 U	0.000432 U	0.000235 U	0.00117 U	0.000382 U	0.000340 U	0.000295 U	0.000399 U	0.000296 U	0.000266 U	0.000231 U	0.000252 U	0.000311 U
	IW-8B-50	3/20/18	PES	ESC	50	-10.8	S	0.000328 U	0.000444 U	0.000241 U	0.00120 U	0.000392 U	0.000349 U	0.000303 U	0.000409 U	0.000304 U	0.000273 U	0.000237 U	0.000259 U	0.000319 U
	IW-8B-55	3/20/18	PES	ESC	55	-15.8	S	0.000310 U	0.000419 U	0.000228 U	0.00113 U	0.000370 U	0.000329 U	0.000286 U	0.000386 U	0.000287 U	0.000258 U	0.000223 U	0.000244 U	0.000301 U
	IW-8B-60	3/20/18	PES	ESC	60	-20.8	S	0.000329 U	0.000444 U	0.000242 U	0.00120 U	0.000393 U	0.000349 U	0.000303 U	0.000410 U	0.000305 U	0.000274 U	0.000237 U	0.000259 U	0.000320 U
	IW-8B-64	3/20/18	PES	ESC	64	-24.8	S	0.000324 U	0.000437 U	0.000238 U	0.00118 U	0.000387 U	0.000344 U	0.000299 U	0.000404 U	0.000300 U	0.000269 U	0.000233 U	0.000255 U	0.000315 U
IW-8C (-24.5 to-39.5)	IW-8C-5	3/14/18	PES	ESC	5	32.5	S	0.000493 U	0.000666 U	**0.000378 J**	0.00180 U	0.000588 U	0.000523 U	0.000455 U	0.000615 U	0.000456 U	0.000410 U	0.000356 U	0.000388 U	0.000479 U
	IW-8C-10	3/14/18	PES	ESC	10	27.5	S	**0.000825 J**	0.000671 U	**0.000832 J**	0.00182 U	0.000593 U	0.000528 U	0.000458 U	0.000619 U	0.000460 U	0.000413 U	0.000358 U	0.000391 U	0.000483 U
	IW-8C-15	3/14/18	PES	ESC	15	22.5	S	0.000338 U	0.000457 U	0.000249 U	0.00123 U	0.000405 U	0.000359 U	0.000312 U	0.000421 U	0.000314 U	0.000281 U	0.000243 U	0.000267 U	0.000329 U
	IW-8C-20	3/14/18	PES	ESC	20	17.5	S	0.000310 U	0.000418 U	0.000228 U	0.00113 U	0.000370 U	0.000329 U	0.000286 U	0.000386 U	0.000287 U	0.000258 U	0.000223 U	0.000244 U	0.000301 U
	IW-8C-25	3/14/18	PES	ESC	25	12.5	S	0.000342 U	0.000462 U	0.000251 U	0.00125 U	0.000408 U	0.000363 U	0.000315 U	0.000426 U	0.000317 U	0.000285 U	0.000246 U	0.000269 U	0.000332 U
	IW-8C-30	3/14/18	PES	ESC	30	7.5	S	0.000318 U	0.000429 U	0.000233 U	0.00116 U	0.000379 U	0.000337 U	0.000293 U	0.000396 U	0.000294 U	0.000264 U	0.000229 U	0.000250 U	0.000309 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
IW-8C (continued)	IW-8C-35	3/14/18	PES	ESC	35	2.5	S	0.000332 U	0.000449 U	0.000244 U	0.00121 U	0.000397 U	0.000353 U	0.000307 U	0.000414 U	0.000308 U	0.000276 U	0.000239 U	0.000261 U	0.000323 U
	IW-8C-40	3/14/18	PES	ESC	40	-2.5	S	0.000330 U	0.000447 U	0.000243 U	0.00121 U	0.000395 U	0.000351 U	0.000305 U	0.000412 U	0.000306 U	0.000275 U	0.000238 U	0.000260 U	0.000321 U
	IW-8C-45	3/14/18	PES	ESC	45	-7.5	S	0.000324 U	0.000438 U	0.000238 U	0.00118 U	0.000387 U	0.000344 U	0.000299 U	0.000404 U	0.000300 U	0.000270 U	0.000233 U	0.000255 U	0.000315 U
	IW-8C-50	3/14/18	PES	ESC	50	-12.5	S	**0.00274**	0.000456 U	**0.00692**	0.00123 U	0.000403 U	0.000358 U	0.000311 U	0.000421 U	**0.00233**	0.000281 U	0.000243 U	0.000266 U	0.000328 U
	IW-8C-55	3/14/18	PES	ESC	55	-17.5	S	**0.00115 J**	0.000448 U	**0.00270**	0.00121 U	0.000396 U	0.000352 U	0.000306 U	0.000413 U	**0.00105 J**	0.000276 U	0.000239 U	0.000261 U	0.000322 U
	IW-8C-60	3/14/18	PES	ESC	60	-22.5	S	0.000328 U	0.000443 U	**0.000420 J**	0.00120 U	0.000392 U	0.000348 U	0.000303 U	0.000409 U	0.000304 U	0.000273 U	0.000237 U	0.000258 U	0.000319 U
	IW-902-60	3/14/18	PES	ESC	60 (dup)	-22.5	S	0.000318 U	0.000431 U	0.000234 U	0.00117 U	0.000381 U	0.000338 U	0.000294 U	0.000397 U	0.000295 U	0.000265 U	0.000230 U	0.000251 U	0.000310 U
	IW-8C-65	3/14/18	PES	ESC	65	-27.5	S	0.000344 U	0.000465 U	0.000253 U	0.00126 U	0.000411 U	0.000366 U	0.000318 U	0.000429 U	0.000319 U	0.000287 U	0.000248 U	0.000271 U	0.000335 U
	IW-8C-70	3/14/18	PES	ESC	70	-32.5	S	0.000341 U	0.000461 U	0.000250 U	0.00125 U	0.000407 U	0.000362 U	0.000315 U	0.000425 U	0.000316 U	0.000284 U	0.000246 U	0.000268 U	0.000331 U
	IW-8C-75	3/14/18	PES	ESC	75	-37.5	S	0.000321 U	0.000434 U	0.000236 U	0.00118 U	0.000384 U	0.000341 U	0.000297 U	0.000401 U	0.000298 U	0.000268 U	0.000232 U	0.000253 U	0.000312 U
IW-11D (-41.8 to-56.8)	IW-11D-10	4/19/18	PES	ESC	10	28.4	S	0.000396 U	0.000536 U	0.000291 U	0.00145 U	0.000474 U	0.000421 U	0.000366 U	0.000494 U	0.000367 U	0.000330 U	0.000286 U	0.000312 U	0.000385 U
	IW-11D-15	4/19/18	PES	ESC	15	23.4	S	0.000333 U	0.000450 U	0.000245 U	0.00122 U	0.000398 U	0.000354 U	0.000307 U	0.000415 U	0.000308 U	0.000277 U	0.000240 U	0.000262 U	0.000323 U
	IW-11D-20	4/19/18	PES	ESC	20	18.4	S	0.000332 U	0.000449 U	0.000244 U	0.00121 U	0.000397 U	0.000353 U	0.000307 U	0.000414 U	0.000308 U	0.000276 U	0.000239 U	0.000261 U	0.000323 U
	IW-11D-25	4/19/18	PES	ESC	25	13.4	S	0.000314 U	0.000424 U	0.000231 U	0.00115 U	0.000375 U	0.000333 U	0.000290 U	0.000391 U	0.000291 U	0.000261 U	0.000226 U	0.000247 U	0.000305 U
	IW-11D-30	4/19/18	PES	ESC	30	8.4	S	0.000314 U	0.000424 U	0.000231 U	0.00115 U	0.000375 U	0.000334 U	0.000290 U	0.000392 U	0.000291 U	0.000261 U	0.000226 U	0.000247 U	0.000305 U
	IW-11D-35	4/19/18	PES	ESC	35	3.4	S	0.000329 U	0.000444 U	0.000242 U	0.00120 U	0.000393 U	0.000349 U	0.000304 U	0.000410 U	0.000305 U	0.000274 U	0.000237 U	0.000259 U	0.000320 U
	IW-11D-40	4/19/18	PES	ESC	40	-1.6	S	0.000317 U	0.000429 U	0.000233 U	0.00116 U	0.000379 U	0.000337 U	0.000293 U	0.000396 U	0.000294 U	0.000264 U	0.000229 U	0.000250 U	0.000308 U
	IW-11D-45	4/19/18	PES	ESC	45	-6.6	S	0.00808 U	0.0109 U	0.00594 U	0.0295 U	0.00966 U	0.00858 U	0.00745 U	0.0101 U	0.00749 U	0.00673 U	0.00583 U	0.00636 U	0.00786 U
	IW-11D-50	4/19/18	PES	ESC	50	-11.6	S	0.000308 U	0.000417 U	0.000227 U	0.00113 U	0.000368 U	0.000327 U	0.000285 U	0.000384 U	0.000286 U	0.000257 U	0.000222 U	0.000243 U	0.000300 U
	IW-11D-55	4/19/18	PES	ESC	55	-16.6	S	0.000340 U	0.000460 U	0.000250 U	0.00124 U	0.000406 U	0.000361 U	0.000314 U	0.000424 U	0.000315 U	0.000283 U	0.000245 U	0.000268 U	0.000331 U
	IW-11D-60	4/19/18	PES	ESC	60	-21.6	S	0.000315 U	0.000426 U	0.000232 U	0.00115 U	0.000377 U	0.000335 U	0.000291 U	0.000393 U	0.000292 U	0.000263 U	0.000227 U	0.000248 U	0.000306 U
	IW-11D-65	4/19/18	PES	ESC	65	-26.6	S	0.000316 U	0.000427 U	0.000232 U	0.00116 U	0.000378 U	0.000336 U	0.000292 U	0.000394 U	0.000293 U	0.000263 U	0.000228 U	0.000249 U	0.000307 U
	IW-11D-70	4/19/18	PES	ESC	70	-31.6	S	0.000317 U	0.000428 U	0.000233 U	0.00116 U	0.000379 U	0.000337 U	0.000292 U	0.000395 U	0.000294 U	0.000264 U	0.000228 U	0.000249 U	0.000308 U
	IW-11D-75	4/19/18	PES	ESC	75	-36.6	S	0.000331 U	0.000448 U	0.000244 U	0.00121 U	0.000396 U	0.000352 U	0.000306 U	0.000413 U	0.000307 U	0.000276 U	0.000239 U	0.000261 U	0.000322 U
	IW-11D-80	4/19/18	PES	ESC	80	-41.6	S	0.000322 U	0.000436 U	0.000237 U	0.00118 U	0.000385 U	0.000343 U	0.000298 U	0.000402 U	0.000299 U	0.000269 U	0.000233 U	0.000254 U	0.000313 U
	IW-11D-85	4/19/18	PES	ESC	85	-46.6	S	0.000330 U	0.000446 U	0.000243 U	0.00121 U	0.000394 U	0.000351 U	0.000305 U	0.000412 U	0.000306 U	0.000275 U	0.000238 U	0.000260 U	0.000321 U
	IW-11D-90	4/19/18	PES	ESC	90	-51.6	S	0.000325 U	0.000440 U	0.000239 U	0.00119 U	0.000389 U	0.000346 U	0.000300 U	0.000406 U	0.000301 U	0.000271 U	0.000235 U	0.000256 U	0.000316 U
	IW-11D-95	4/19/18	PES	ESC	95	-56.6	S	0.000336 U	0.000455 U	0.000247 U	0.00123 U	0.000402 U	0.000357 U	0.000311 U	0.000419 U	0.000312 U	0.000280 U	0.000243 U	0.000265 U	0.000327 U
IW-12D (-41.4 to-56.4)	IW-12D-42	9/14/18	PES	ESC	42	-3.5	S	**0.00197 J**	0.00523 U	**0.00460 J**	0.00554 U	0.000570 U	0.00157 U	0.000516 U	0.138 U	**0.00184 J**	0.00185 U	0.00190 U	0.00214 U	0.000861 U
	B-928-42	9/14/18	PES	ESC	42 (dup)	-3.5	S	**0.00215 J**	0.00524 U	**0.00425 J**	0.00554 U	0.000570 U	0.00158 U	0.000516 U	0.138 U	0.00117 U	0.00185 U	0.00190 U	0.00214 U	0.000862 U
	IW-12D-50	9/14/18	PES	ESC	50	-11.5	S	**0.00233 J**	0.00527 U	**0.00512 J**	0.00558 U	0.000574 U	0.00159 U	0.000519 U	0.278 U	**0.00197 J**	0.00186 U	0.00191 U	0.00215 U	0.000867 U
	IW-12D-60	9/14/18	PES	ESC	60	-21.5	S	0.00130 U	0.00543 U	0.00131 U	0.00574 U	0.000591 U	0.00163 U	0.000535 U	0.0286 U	0.00122 U	0.00191 U	0.00197 U	0.00222 U	0.000893 U
	IW-12D-85	9/17/18	PES	ESC	85	-46.5	S	0.00129 U	0.00539 U	**0.00173 J**	0.00570 U	0.000587 U	0.00162 U	0.000531 U	0.0284 U	0.00121 U	0.00190 U	0.00196 U	0.00220 U	0.000886 U
	IW-12D-95	9/17/18	PES	ESC	95	-56.5	S	0.00138 U	0.00580 U	0.00140 U	0.00613 U	0.000631 U	0.00174 U	0.000571 U	0.00611 U	0.00130 U	0.00204 U	0.00210 U	0.00237 U	0.000954 U
IW-13D (-41.0 to-56.0)	IW-13D-80	9/18/18	PES	ESC	80	-40.8	S	**0.00129 J**	0.00532 U	**0.00240 J**	0.00563 U	0.000579 U	0.00160 U	0.000524 U	0.113 U	0.00119 U	0.00188 U	0.00193 U	0.00217 U	0.000875 U
	IW-13D-85	9/18/18	PES	ESC	85	-45.8	S	0.00132 U	0.00555 U	0.00134 U	0.00587 U	0.000604 U	0.00167 U	0.000547 U	0.00146 U	0.00124 U	0.00196 U	0.00201 U	0.00227 U	0.000913 U
	IW-13D-95	9/18/18	PES	ESC	95	-55.8	S	0.00138 U	0.00580 U	0.00140 U	0.00614 U	0.000632 U	0.00175 U	0.000572 U	0.00153 U	0.00130 U	0.00205 U	0.00211 U	0.00237 U	0.000954 U
IW-14D (-41.0 to-56.0)	IW-14D-45	9/11/18	PES	ESC	45	-5.9	S	0.00120 U	0.00505 U	0.00122 U	0.00534 U	0.000550 U	0.00152 U	0.000498 U	0.00266 U	0.00113 U	0.00178 U	0.00183 U	0.00206 U	**0.000981 J**
	IW-14D-55	9/11/18	PES	ESC	55	-15.9	S	**0.00267 J**	0.00545 U	**0.00887**	0.00576 U	0.000593 U	0.00164 U	0.000537 U	0.0574 U	**0.00398 J**	0.00192 U	0.00198 U	0.00223 U	0.000896 U
	IW-14D-65	9/11/18	PES	ESC	65	-25.9	S	0.00129 U	0.00541 U	0.00130 U	0.00572 U	0.000589 U	0.00163 U	0.000533 U	0.00143 U	0.00121 U	0.00191 U	0.00196 U	0.00221 U	0.000890 U
	IW-14D-75	9/11/18	PES	ESC	75	-35.9	S	0.00129 U	0.00541 U	0.00130 U	0.00572 U	0.000589 U	0.00163 U	0.000533 U	0.00142 U	0.00121 U	0.00191 U	0.00196 U	0.00221 U	**0.00171 J**
	IW-14D-86	9/11/18	PES	ESC	86	-46.9	S	0.00127 U	0.00531 U	0.00128 U	0.00562 U	0.000578 U	0.00160 U	0.000523 U	0.00140 U	0.00119 U	0.00187 U	0.00193 U	0.00217 U	0.000874 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
IW-14D (continued)	IW-14D-95	9/11/18	PES	ESC	95	-55.9	S	0.00130 U	0.00546 U	**0.00133 J**	0.00578 U	0.000595 U	0.00164 U	0.000538 U	0.0116 U	**0.00133 J**	0.00193 U	0.00198 U	0.00223 U	**0.00316 J**
IW-15D (-41.9 to-56.9)	IW-15D-54	9/11/18	PES	ESC	54	-2.2	S	0.00123 U	0.00516 U	**0.00271 J**	0.00546 U	0.000562 U	0.00155 U	0.000508 U	0.00544 U	**0.00118 J**	0.00182 U	0.00187 U	0.00211 U	0.000849 U
IW-16D (-41.5 to-56.2)	IW-16D-85	10/18/18	PES	PACE	85	-45.6	S	0.00536 U	0.0225 U	0.00541 U	0.0238 U	0.00245 U	0.00676 U	0.00221 U	0.00592 U	0.00503 U	0.00792 U	0.00816 U	0.00918 U	0.00369 U
	IW-16D-90	10/18/18	PES	PACE	90	-50.6	S	0.00136 U	0.00571 U	0.00138 U	0.00605 U	0.000622 U	0.00172 U	0.000563 U	0.00151 U	0.00128 U	0.00202 U	0.00207 U	0.00234 U	0.000940 U
	IW-16D-95	10/18/18	PES	PACE	95	-55.6	S	0.00557 U	0.0234 U	0.00562 U	0.0247 U	0.00254 U	0.00702 U	0.00230 U	0.00615 U	0.00523 U	0.00823 U	0.00848 U	0.00954 U	0.00384 U
IW-19B (-10.6 to-25.6)	IW-19B-5	3/19/18	PES	ESC	5	32.4	S	0.000324 U	0.000438 U	0.000238 U	0.00118 U	0.000387 U	0.000344 U	0.000299 U	0.000405 U	0.000300 U	0.000270 U	0.000234 U	0.000255 U	0.000315 U
	IW-19B-10	3/19/18	PES	ESC	10	27.4	S	0.000353 U	0.000477 U	0.000260 U	0.00129 U	0.000422 U	0.000375 U	0.000326 U	0.000441 U	0.000327 U	0.000294 U	0.000255 U	0.000278 U	0.000343 U
	IW-19B-15	3/19/18	PES	ESC	15	22.4	S	0.000329 U	0.000445 U	0.000242 U	0.00120 U	0.000393 U	0.000349 U	0.000304 U	0.000410 U	0.000305 U	0.000274 U	0.000237 U	0.000259 U	0.000320 U
	IW-19B-20	3/19/18	PES	ESC	20	17.4	S	0.000320 U	0.000433 U	0.000236 U	0.00117 U	0.000383 U	0.000341 U	0.000296 U	0.000400 U	0.000297 U	0.000267 U	0.000231 U	0.000252 U	0.000312 U
	IW-19B-25	3/19/18	PES	ESC	25	12.4	S	0.000337 U	0.000455 U	0.000248 U	0.00123 U	0.000403 U	0.000358 U	0.000311 U	0.000420 U	0.000312 U	0.000281 U	0.000243 U	0.000265 U	0.000327 U
	IW-19B-30	3/19/18	PES	ESC	30	7.4	S	0.000322 U	0.000436 U	0.000237 U	0.00118 U	0.000385 U	0.000343 U	0.000298 U	0.000402 U	0.000299 U	0.000268 U	0.000232 U	0.000254 U	0.000313 U
	IW-19B-35	3/19/18	PES	ESC	35	2.4	S	0.000318 U	0.000430 U	0.000234 U	0.00116 U	0.000380 U	0.000338 U	0.000294 U	0.000397 U	0.000295 U	0.000265 U	0.000230 U	0.000251 U	0.000309 U
	IW-19B-40	3/19/18	PES	ESC	40	-2.6	S	0.000331 U	0.000448 U	0.000244 U	0.00121 U	0.000396 U	0.000352 U	0.000306 U	0.000413 U	0.000307 U	0.000276 U	0.000239 U	0.000261 U	0.000322 U
	IW-19B-45	3/19/18	PES	ESC	45	-7.6	S	0.000350 U	0.000474 U	0.000258 U	0.00128 U	0.000419 U	0.000372 U	0.000323 U	0.000437 U	0.000325 U	0.000292 U	0.000253 U	0.000276 U	0.000340 U
	IW-19B-50	3/19/18	PES	ESC	50	-12.6	S	0.000366 U	0.000495 U	0.000269 U	0.00134 U	0.000438 U	0.000390 U	0.000338 U	0.000457 U	0.000340 U	0.000305 U	0.000264 U	0.000288 U	0.000356 U
	IW-19B-55	3/19/18	PES	ESC	55	-17.6	S	0.000316 U	0.000427 U	0.000232 U	0.00116 U	0.000377 U	0.000336 U	0.000292 U	0.000394 U	0.000293 U	0.000263 U	0.000228 U	0.000249 U	0.000307 U
	IW-19B-60	3/19/18	PES	ESC	60	-22.6	S	0.000317 U	0.000428 U	0.000233 U	0.00116 U	0.000378 U	0.000337 U	0.000292 U	0.000395 U	0.000293 U	0.000264 U	0.000228 U	0.000249 U	0.000308 U
	IW-903-60	3/19/18	PES	ESC	60 (dup)	-22.6	S	0.000322 U	0.000436 U	0.000237 U	0.00118 U	0.000385 U	0.000342 U	0.000298 U	0.000402 U	0.000299 U	0.000268 U	0.000232 U	0.000254 U	0.000313 U
	IW-19B-63	3/19/18	PES	ESC	63	-25.6	S	0.000321 U	0.000434 U	0.000236 U	0.00118 U	0.000384 U	0.000341 U	0.000297 U	0.000401 U	0.000298 U	0.000268 U	0.000232 U	0.000253 U	0.000312 U
IW-21B (-10.1 to-25.1)	IW-21B-5	3/6/18	PES	ESC	5	36.9	V	0.000519 U	0.000701 U	0.000382 U	0.00190 U	0.000620 U	0.000551 U	0.000479 U	0.000646 U	0.000480 U	0.000432 U	0.000375 U	0.000408 U	0.000504 U
	IW-21B-10	3/6/18	PES	ESC	10	31.9	S	0.000350 U	0.000473 U	0.000257 U	0.00128 U	0.000418 U	0.000372 U	0.000323 U	0.000436 U	0.000324 U	0.000291 U	0.000252 U	0.000276 U	0.000340 U
	IW-21B-20	3/6/18	PES	ESC	20	21.9	S	0.000345 U	0.000467 U	0.000254 U	0.00126 U	0.000412 U	0.000367 U	0.000319 U	0.000430 U	0.000320 U	0.000287 U	0.000249 U	0.000272 U	0.000335 U
	IW-21B-30	3/6/18	PES	ESC	30	11.9	S	0.000320 U	0.000433 U	0.000236 U	0.00117 U	0.000383 U	0.000341 U	0.000296 U	0.000400 U	0.000297 U	0.000267 U	0.000231 U	0.000252 U	0.000312 U
	IW-21B-40	3/6/18	PES	ESC	40	1.9	S	0.000317 U	0.000429 U	0.000233 U	0.00116 U	0.000379 U	0.000337 U	0.000293 U	0.000396 U	0.000294 U	0.000264 U	0.000229 U	0.000250 U	0.000308 U
	IW-21B-50	3/6/18	PES	ESC	50	-8.1	S	0.000310 U	0.000420 U	0.000228 U	0.00114 U	0.000371 U	0.000330 U	0.000287 U	0.000387 U	0.000288 U	0.000258 U	0.000224 U	0.000244 U	0.000302 U
	IW-21B-60	3/6/18	PES	ESC	60	-18.1	S	0.00814 U	0.0110 U	0.00598 U	0.0297 U	0.00972 U	0.00863 U	0.00750 U	0.0101 U	0.00754 U	0.00678 U	0.00587 U	0.00640 U	0.00791 U
	IW-21B-67	3/6/18	PES	ESC	67	-25.1	S	0.000318 U	0.000430 U	0.000234 U	0.00116 U	0.000380 U	0.000338 U	0.000294 U	0.000397 U	0.000295 U	0.000265 U	0.000229 U	0.000250 U	0.000309 U
IW-22C (-25.6 to-40.6)	IW-22C-62	8/31/18	PES	ESC	62	-23.1	S	**0.00278 J**	0.00557 U	**0.0107**	0.00589 U	0.000606 U	0.00167 U	0.000548 U	0.0581 U	**0.00366 J**	0.00196 U	0.00202 U	0.00228 U	0.000915 U
	IW-22C-78	8/31/18	PES	ESC	78	-39.1	S	0.00139 U	0.00584 U	**0.00241 J**	0.00618 U	0.000636 U	0.00176 U	0.000575 U	0.0615 U	0.00131 U	0.00206 U	0.00212 U	0.00239 U	0.000961 U
IW-23C (-27.0 to-42.0)	IW-23C-42	9/4/18	PES	ESC	42	-3.0	S	**0.0380**	0.00577 U	**0.0811**	0.00610 U	0.000628 U	0.00174 U	0.000569 U	0.608 U	**0.0240**	0.00203 U	0.00209 U	0.00236 U	0.000949 U
IW-24C (-26.1 to-41.1)	IW-24C-48	9/7/18	PES	ESC	48	-8.8	S	0.00130 U	0.00545 U	**0.00191 J**	0.00576 U	0.000593 U	0.00164 U	0.000537 U	0.0144 U	0.00122 U	0.00192 U	0.00198 U	0.00223 U	0.000896 U
	IW-24C-55	9/7/18	PES	ESC	55	-15.8	S	**0.00905**	0.00574 U	**0.0250**	0.00607 U	0.000625 U	0.00173 U	0.000566 U	0.00151 U	**0.00869**	0.00203 U	0.00208 U	0.00235 U	0.000945 U
	IW-24C-66	9/10/18	PES	ESC	66	-26.8	S	**0.0149**	0.00596 U	**0.0427**	0.00631 U	0.000649 U	0.00179 U	0.000587 U	0.00157 U	**0.0148**	0.00210 U	0.00216 U	0.00244 U	0.000981 U
	IW-24C-75	9/10/18	PES	ESC	75	-35.8	S	**0.0159**	0.00576 U	**0.0481**	0.00610 U	0.000628 U	0.00174 U	0.000568 U	0.00152 U	**0.0170**	0.00204 U	0.00209 U	0.00236 U	0.000947 U
	IW-24C-80	9/10/18	PES	ESC	80	-40.8	S	0.00127 U	0.00533 U	**0.00194 J**	0.00564 U	0.000581 U	0.00160 U	0.000525 U	0.0281 U	0.00119 U	0.00188 U	0.00194 U	0.00218 U	**0.00144 J**
IW-27B (-8.1 to-23.1)	IW-27B-5	3/2/18	PES	ESC	5	37.0	V	0.000460 U	0.000621 U	0.000339 U	0.00169 U	0.000549 U	0.000489 U	0.000425 U	0.000574 U	0.000426 U	0.000383 U	0.000332 U	0.000362 U	0.000447 U
	IW-27B-15	3/2/18	PES	ESC	15	27.0	S	0.000409 U	0.000553 U	**0.000398 J**	0.00150 U	0.000488 U	0.000434 U	0.000377 U	0.000510 U	0.000379 U	0.000340 U	0.000295 U	0.000322 U	0.000397 U
	IW-27B-25	3/2/18	PES	ESC	25	17.0	S	0.000334 U	0.000451 U	0.000245 U	0.00122 U	0.000399 U	0.000355 U	0.000308 U	0.000416 U	0.000309 U	0.000278 U	0.000241 U	0.000263 U	0.000324 U
	IW-27B-35	3/2/18	PES	ESC	35	7.0	S	0.000328 U	0.000444 U	0.000241 U	0.00120 U	0.000393 U	0.000349 U	0.000303 U	0.000410 U	0.000304 U	0.000274 U	0.000237 U	0.000259 U	0.000319 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
IW-27C (-24.4 to-39.6)	IW-27C-45	9/10/18	PES	ESC	45	6.8	S	0.00129 U	0.00540 U	**0.00436 J**	0.00571 U	0.000588 U	0.00162 U	0.000532 U	0.0284 U	**0.00144 J**	0.00190 U	0.00196 U	0.00221 U	0.000888 U
IW-28C (-26.6 to-41.7)	IW-28C-92	9/17/18	PES	ESC	92	-40.6	S	0.00125 U	0.00524 U	0.00126 U	0.00554 U	0.000571 U	0.00158 U	0.000516 U	0.00552 U	0.00117 U	0.00185 U	0.00190 U	0.00214 U	0.000862 U
IW-39B (-9.8 to-24.8)	IW-39B-5	3/12/18	PES	ESC	5	35.2	V	0.000364 U	0.000493 U	0.000268 U	0.00133 U	0.000436 U	0.000387 U	0.000336 U	0.000455 U	0.000338 U	0.000303 U	0.000263 U	0.000287 U	0.000354 U
	IW-39B-15	3/12/18	PES	ESC	15	25.2	S	0.000320 U	0.000432 U	0.000235 U	0.00117 U	0.000382 U	0.000340 U	0.000295 U	0.000399 U	0.000296 U	0.000266 U	0.000231 U	0.000252 U	0.000311 U
	IW-39B-25	3/12/18	PES	ESC	25	15.2	S	0.000341 U	0.000461 U	0.000251 U	0.00125 U	0.000408 U	0.000363 U	0.000315 U	0.000426 U	0.000316 U	0.000284 U	0.000246 U	0.000269 U	0.000332 U
	IW-39B-35	3/12/18	PES	ESC	35	5.2	S	0.000315 U	0.000426 U	0.000232 U	0.00115 U	0.000377 U	0.000335 U	0.000291 U	0.000393 U	0.000292 U	0.000262 U	0.000227 U	0.000248 U	0.000306 U
	IW-39B-45	3/12/18	PES	ESC	45	-4.8	S	0.000322 U	0.000435 U	0.000237 U	0.00118 U	0.000385 U	0.000342 U	0.000297 U	0.000401 U	0.000298 U	0.000268 U	0.000232 U	0.000253 U	0.000313 U
	IW-39B-55	3/12/18	PES	ESC	55	-14.8	S	0.00754 U	0.0102 U	0.00554 U	0.0275 U	0.00901 U	0.00800 U	0.00695 U	0.00940 U	0.00698 U	0.00628 U	0.00544 U	0.00593 U	0.00733 U
IW-46B (-4.2 to-24.2)	IW-46B-5	3/20/18	PES	ESC	5	46.8	V	0.000323 U	0.000436 U	0.000237 U	0.00118 U	0.000386 U	0.000343 U	0.000298 U	0.000402 U	0.000299 U	0.000269 U	0.000233 U	0.000254 U	0.000314 U
	IW-46B-10	3/20/18	PES	ESC	10	41.8	V	0.000315 U	0.000426 U	0.000232 U	0.00115 U	0.000377 U	0.000335 U	0.000291 U	0.000393 U	0.000292 U	0.000263 U	0.000227 U	0.000248 U	0.000307 U
	IW-46B-15	3/20/18	PES	ESC	15	36.8	V	0.00794 U	0.0107 U	0.00584 U	0.0290 U	0.00949 U	0.00843 U	0.00732 U	0.00990 U	0.00736 U	0.00661 U	0.00573 U	0.00625 U	0.00772 U
	IW-46B-20	3/20/18	PES	ESC	20	31.8	S	0.000321 U	0.000434 U	0.000236 U	0.00117 U	0.000383 U	0.000341 U	0.000296 U	0.000400 U	0.000297 U	0.000267 U	0.000231 U	0.000253 U	0.000312 U
	IW-46B-25	3/20/18	PES	ESC	25	26.8	S	0.000317 U	0.000429 U	0.000233 U	0.00116 U	0.000379 U	0.000337 U	0.000293 U	0.000396 U	0.000294 U	0.000264 U	0.000229 U	0.000250 U	0.000308 U
	IW-46B-30	3/20/18	PES	ESC	30	21.8	S	0.000321 U	0.000434 U	0.000236 U	0.00117 U	0.000384 U	0.000341 U	0.000296 U	0.000400 U	0.000297 U	0.000267 U	0.000231 U	0.000253 U	0.000312 U
	IW-46B-35	3/20/18	PES	ESC	35	16.8	S	0.000347 U	0.000469 U	0.000255 U	0.00127 U	0.000415 U	0.000369 U	0.000321 U	0.000433 U	0.000322 U	0.000289 U	0.000250 U	0.000273 U	0.000338 U
	IW-904-35	3/20/18	PES	ESC	35 (dup)	16.8	S	0.000367 U	0.000496 U	0.000270 U	0.00134 U	0.000439 U	0.000390 U	0.000339 U	0.000458 U	0.000340 U	0.000306 U	0.000265 U	0.000289 U	0.000357 U
	IW-46B-40	3/20/18	PES	ESC	40	11.8	S	0.000302 U	0.000408 U	0.000222 U	0.00110 U	0.000361 U	0.000321 U	0.000279 U	0.000376 U	0.000280 U	0.000251 U	0.000218 U	0.000238 U	0.000293 U
	IW-46B-42	3/20/18	PES	ESC	42	9.8	S	**0.000541 J**	0.000467 U	**0.00136**	0.00126 U	0.000412 U	0.000367 U	0.000319 U	0.000430 U	**0.000545 J**	0.000287 U	0.000249 U	0.000272 U	0.000335 U
	IW-46B-45	3/20/18	PES	ESC	45	6.8	S	1.64 U	2.21 U	1.21 U	5.97 U	1.96 U	1.73 U	1.50 U	2.04 U	1.51 U	1.37 U	1.18 U	1.29 U	1.59 U
	IW-46B-50	3/20/18	PES	ESC	50	1.8	S	0.000287 U	0.000388 U	0.000211 U	0.00105 U	0.000343 U	0.000305 U	0.000265 U	0.000358 U	0.000266 U	0.000239 U	0.000207 U	0.000226 U	0.000279 U
	IW-46B-55	3/20/18	PES	ESC	55	-3.2	S	0.000320 U	0.000433 U	**0.000290 J**	0.00117 U	0.000382 U	0.000340 U	0.000296 U	0.000399 U	0.000297 U	0.000267 U	0.000231 U	0.000252 U	0.000311 U
	IW-46B-60	3/20/18	PES	ESC	60	-8.2	S	0.000324 U	0.000438 U	0.000238 U	0.00119 U	0.000387 U	0.000345 U	0.000299 U	0.000404 U	0.000300 U	0.000270 U	0.000234 U	0.000255 U	0.000315 U
	IW-46B-65	3/20/18	PES	ESC	65	-13.2	S	0.000319 U	0.000431 U	0.000235 U	0.00117 U	0.000381 U	0.000339 U	0.000295 U	0.000398 U	0.000296 U	0.000266 U	0.000230 U	0.000251 U	0.000310 U
	IW-46B-70	3/20/18	PES	ESC	70	-18.2	S	0.000366 U	0.000495 U	0.000269 U	0.00134 U	0.000438 U	0.000389 U	0.000338 U	0.000457 U	0.000339 U	0.000305 U	0.000264 U	0.000288 U	0.000356 U
IW-47B (-5.2 to-25.2)	IW-47B-5	3/22/18	PES	ESC	5	46.8	V	0.000339 U	0.000458 U	0.000249 U	0.00124 U	0.000405 U	0.000360 U	0.000313 U	0.000422 U	0.000314 U	0.000282 U	0.000244 U	0.000267 U	0.000329 U
	IW-47B-10	3/22/18	PES	ESC	10	41.8	V	0.000338 U	0.000456 U	0.000248 U	0.00124 U	0.000403 U	0.000359 U	0.000312 U	0.000421 U	0.000313 U	0.000281 U	0.000244 U	0.000266 U	0.000328 U
	IW-47B-15	3/22/18	PES	ESC	15	36.8	V	0.000320 U	0.000433 U	0.000236 U	0.00117 U	0.000383 U	0.000341 U	0.000296 U	0.000400 U	0.000297 U	0.000267 U	0.000231 U	0.000252 U	0.000312 U
	IW-47B-20	3/22/18	PES	ESC	20	31.8	S	0.000319 U	0.000431 U	0.000234 U	0.00117 U	0.000381 U	0.000339 U	0.000294 U	0.000398 U	0.000295 U	0.000265 U	0.000230 U	0.000251 U	0.000310 U
	IW-47B-25	3/22/18	PES	ESC	25	26.8	S	0.000325 U	0.000439 U	0.000239 U	0.00119 U	0.000388 U	0.000345 U	0.000300 U	0.000405 U	0.000301 U	0.000270 U	0.000234 U	0.000256 U	0.000316 U
	IW-47B-30	3/22/18	PES	ESC	30	21.8	S	0.000322 U	0.000435 U	0.000237 U	0.00118 U	0.000385 U	0.000342 U	0.000297 U	0.000401 U	0.000298 U	0.000268 U	0.000232 U	0.000253 U	0.000313 U
	IW-47B-35	3/22/18	PES	ESC	35	16.8	S	0.000316 U	0.000427 U	0.000232 U	0.00115 U	0.000377 U	0.000335 U	0.000291 U	0.000394 U	0.000293 U	0.000263 U	0.000228 U	0.000249 U	0.000307 U
	IW-47B-40	3/22/18	PES	ESC	40	11.8	S	0.000326 U	0.000440 U	0.000240 U	0.00119 U	0.000389 U	0.000346 U	0.000301 U	0.000406 U	0.000302 U	0.000271 U	0.000235 U	0.000257 U	0.000317 U
	IW-47B-42	3/22/18	PES	ESC	42	9.8	S	0.000376 U	0.000509 U	0.000276 U	0.00138 U	0.000451 U	0.000401 U	0.000347 U	0.000469 U	0.000348 U	0.000314 U	0.000272 U	0.000296 U	0.000366 U
	IW-47B-45	3/22/18	PES	ESC	45	6.8	S	0.000325 U	0.000439 U	0.000239 U	0.00119 U	0.000388 U	0.000345 U	0.000300 U	0.000405 U	0.000301 U	0.000270 U	0.000234 U	0.000256 U	0.000315 U
	IW-47B-50	3/22/18	PES	ESC	50	1.8	S	0.000337 U	0.000456 U	0.000248 U	0.00123 U	0.000403 U	0.000358 U	0.000311 U	0.000421 U	0.000312 U	0.000281 U	0.000243 U	0.000265 U	0.000328 U
	IW-47B-55	3/22/18	PES	ESC	55	-3.2	S	0.000310 U	0.000419 U	0.000228 U	0.00113 U	0.000371 U	0.000330 U	0.000286 U	0.000387 U	0.000288 U	0.000258 U	0.000224 U	0.000244 U	0.000302 U
	IW-47B-60	3/22/18	PES	ESC	60	-8.2	S	0.000328 U	0.000444 U	0.000241 U	0.00120 U	0.000392 U	0.000349 U	0.000303 U	0.000409 U	0.000304 U	0.000273 U	0.000237 U	0.000258 U	0.000319 U
	IW-47B-65	3/22/18	PES	ESC	65	-13.2	S	0.000324 U	0.000438 U	0.000238 U	0.00119 U	0.000387 U	0.000344 U	0.000299 U	0.000404 U	0.000300 U	0.000270 U	0.000234 U	0.000255 U	0.000315 U
	IW-47B-70	3/22/18	PES	ESC	70	-18.2	S	0.000320 U	0.000433 U	0.000236 U	0.00117 U	0.000383 U	0.000340 U	0.000296 U	0.000400 U	0.000297 U	0.000267 U	0.000231 U	0.000252 U	0.000311 U
	IW-47B-75	3/22/18	PES	ESC	75	-23.2	S	0.000319 U	0.000432 U	0.000235 U	0.00117 U	0.000382 U	0.000339 U	0.000295 U	0.000398 U	0.000296 U	0.000266 U	0.000230 U	0.000252 U	0.000310 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
IW-48B	IW-48B-5	3/23/18	PES	ESC	5	46.7	V	0.000332 U	0.000448 U	0.000244 U	0.00121 U	0.000396 U	0.000352 U	0.000306 U	0.000414 U	0.000307 U	0.000276 U	0.000239 U	0.000261 U	0.000322 U
(-9.4 to-24.4)	IW-48B-10	3/23/18	PES	ESC	10	41.7	V	0.000325 U	0.000439 U	0.000239 U	0.00119 U	0.000388 U	0.000345 U	0.000300 U	0.000405 U	0.000301 U	0.000271 U	0.000234 U	0.000256 U	0.000316 U
	IW-48B-15	3/23/18	PES	ESC	15	36.7	V	0.000335 U	0.000453 U	0.000246 U	0.00123 U	0.000400 U	0.000356 U	0.000309 U	0.000418 U	0.000311 U	0.000279 U	0.000242 U	0.000264 U	0.000326 U
	IW-48B-20	3/23/18	PES	ESC	20	31.7	S	0.000316 U	0.000427 U	0.000232 U	0.00116 U	0.000377 U	0.000336 U	0.000292 U	0.000394 U	0.000293 U	0.000263 U	0.000228 U	0.000249 U	0.000307 U
	IW-48B-25	3/23/18	PES	ESC	25	26.7	S	0.000323 U	0.000437 U	0.000238 U	0.00118 U	0.000386 U	0.000343 U	0.000298 U	0.000403 U	0.000300 U	0.000269 U	0.000233 U	0.000254 U	0.000314 U
	IW-48B-30	3/23/18	PES	ESC	30	21.7	S	0.000316 U	0.000428 U	0.000233 U	0.00116 U	0.000378 U	0.000336 U	0.000292 U	0.000395 U	0.000293 U	0.000263 U	0.000228 U	0.000249 U	0.000308 U
	IW-48B-35	3/23/18	PES	ESC	35	16.7	S	0.000330 U	0.000446 U	0.000243 U	0.00121 U	0.000395 U	0.000351 U	0.000305 U	0.000412 U	0.000306 U	0.000275 U	0.000238 U	0.000260 U	0.000321 U
	IW-48B-40	3/23/18	PES	ESC	40	11.7	S	0.000313 U	0.000423 U	0.000230 U	0.00115 U	0.000374 U	0.000333 U	0.000289 U	0.000391 U	0.000290 U	0.000261 U	0.000226 U	0.000247 U	0.000305 U
	IW-48B-42	3/23/18	PES	ESC	42	9.7	S	0.000316 U	0.000428 U	0.000233 U	0.00116 U	0.000378 U	0.000336 U	0.000292 U	0.000395 U	0.000293 U	0.000263 U	0.000228 U	0.000249 U	0.000307 U
	IW-905-42	3/23/18	PES	ESC	42 (dup)	9.7	S	0.000314 U	0.000424 U	0.000231 U	0.00115 U	0.000375 U	0.000333 U	0.000289 U	0.000391 U	0.000291 U	0.000261 U	0.000226 U	0.000247 U	0.000305 U
	IW-48B-45	3/23/18	PES	ESC	45	6.7	S	0.000311 U	0.000421 U	0.000229 U	0.00114 U	0.000372 U	0.000331 U	0.000288 U	0.000388 U	0.000289 U	0.000259 U	0.000225 U	0.000245 U	0.000303 U
	IW-48B-50	3/23/18	PES	ESC	50	1.7	S	0.000317 U	0.000428 U	0.000233 U	0.00116 U	0.000379 U	0.000337 U	0.000292 U	0.000395 U	0.000294 U	0.000264 U	0.000228 U	0.000249 U	0.000308 U
	IW-48B-55	3/23/18	PES	ESC	55	-3.3	S	0.000312 U	0.000421 U	0.000229 U	0.00114 U	0.000372 U	0.000331 U	0.000287 U	0.000388 U	0.000288 U	0.000260 U	0.000224 U	0.000245 U	0.000302 U
	IW-48B-60	3/23/18	PES	ESC	60	-8.3	S	0.000317 U	0.000429 U	**0.000248 J**	0.00116 U	0.000379 U	0.000337 U	0.000293 U	0.000396 U	0.000294 U	0.000264 U	0.000229 U	0.000250 U	0.000309 U
	IW-48B-65	3/23/18	PES	ESC	65	-13.3	S	0.000339 U	0.000458 U	0.000249 U	0.00124 U	0.000405 U	0.000360 U	0.000313 U	0.000423 U	0.000314 U	0.000282 U	0.000245 U	0.000267 U	0.000330 U
	IW-48B-70	3/23/18	PES	ESC	70	-18.3	S	0.000315 U	0.000427 U	0.000232 U	0.00115 U	0.000377 U	0.000335 U	0.000291 U	0.000394 U	0.000292 U	0.000263 U	0.000228 U	0.000248 U	0.000307 U
	IW-48B-75	3/23/18	PES	ESC	75	-23.3	S	0.000323 U	0.000436 U	0.000237 U	0.00118 U	0.000386 U	0.000343 U	0.000298 U	0.000403 U	0.000299 U	0.000269 U	0.000233 U	0.000254 U	0.000314 U
IW-50A	IW-50A-5	3/27/18	PES	ESC	5	46.9	V	0.000328 U	0.000443 U	0.000241 U	0.00120 U	0.000392 U	0.000348 U	0.000302 U	0.000409 U	0.000304 U	0.000273 U	0.000236 U	0.000258 U	0.000318 U
(9.8 to-10.2)	IW-50A-10	3/27/18	PES	ESC	10	41.9	V	0.000320 U	0.000432 U	0.000235 U	0.00117 U	0.000382 U	0.000340 U	0.000295 U	0.000399 U	0.000296 U	0.000266 U	0.000231 U	0.000252 U	0.000311 U
	IW-50A-15	3/27/18	PES	ESC	15	36.9	V	0.000315 U	0.000426 U	0.000232 U	0.00115 U	0.000377 U	0.000335 U	0.000291 U	0.000393 U	0.000292 U	0.000263 U	0.000227 U	0.000248 U	0.000306 U
	IW-50A-20	3/27/18	PES	ESC	20	31.9	S	0.000319 U	0.000431 U	0.000235 U	0.00117 U	0.000381 U	0.000339 U	0.000295 U	0.000398 U	0.000296 U	0.000266 U	0.000230 U	0.000251 U	0.000310 U
	IW-50A-25	3/27/18	PES	ESC	25	26.9	S	0.000311 U	0.000420 U	0.000228 U	0.00114 U	0.000371 U	0.000330 U	0.000287 U	0.000387 U	0.000288 U	0.000259 U	0.000224 U	0.000245 U	0.000302 U
	IW-50A-30	3/27/18	PES	ESC	30	21.9	S	0.000312 U	0.000421 U	0.000229 U	0.00114 U	0.000373 U	0.000331 U	0.000288 U	0.000389 U	0.000289 U	0.000260 U	0.000225 U	0.000245 U	0.000303 U
	IW-50A-35	3/27/18	PES	ESC	35	16.9	S	0.000313 U	0.000422 U	0.000230 U	0.00114 U	0.000373 U	0.000332 U	0.000289 U	0.000390 U	0.000290 U	0.000260 U	0.000225 U	0.000246 U	0.000304 U
	IW-50A-40	3/27/18	PES	ESC	40	11.9	S	0.000317 U	0.000429 U	0.000233 U	0.00116 U	0.000379 U	0.000337 U	0.000293 U	0.000396 U	0.000294 U	0.000264 U	0.000229 U	0.000250 U	0.000308 U
	IW-50A-42	3/27/18	PES	ESC	42	9.9	S	0.000315 U	0.000426 U	0.000232 U	0.00115 U	0.000377 U	0.000335 U	0.000291 U	0.000393 U	0.000292 U	0.000263 U	0.000227 U	0.000248 U	0.000306 U
	IW-50A-45	3/27/18	PES	ESC	45	6.9	S	0.000318 U	0.000430 U	0.000234 U	0.00116 U	0.000380 U	0.000338 U	0.000293 U	0.000396 U	0.000295 U	0.000265 U	0.000229 U	0.000250 U	0.000309 U
	IW-50A-50	3/27/18	PES	ESC	50	1.9	S	0.000322 U	0.000435 U	0.000237 U	0.00118 U	0.000385 U	0.000342 U	0.000297 U	0.000402 U	0.000298 U	0.000268 U	0.000232 U	0.000254 U	0.000313 U
	IW-906-50	3/27/18	PES	ESC	50 (dup)	1.9	S	0.000324 U	0.000438 U	0.000238 U	0.00119 U	0.000387 U	0.000344 U	0.000299 U	0.000404 U	0.000300 U	0.000270 U	0.000234 U	0.000255 U	0.000315 U
	IW-50A-55	3/27/18	PES	ESC	55	-3.2	S	0.000323 U	0.000437 U	0.000237 U	0.00118 U	0.000386 U	0.000343 U	0.000298 U	0.000403 U	0.000299 U	0.000269 U	0.000233 U	0.000254 U	0.000314 U
	IW-50A-60	3/27/18	PES	ESC	60	-8.2	S	0.000324 U	0.000438 U	0.000238 U	0.00119 U	0.000387 U	0.000344 U	0.000299 U	0.000404 U	0.000300 U	0.000270 U	0.000234 U	0.000255 U	0.000315 U
IW-51A	IW-51A-5	3/26/18	PES	ESC	5	46.9	V	0.000316 U	0.000427 U	0.000232 U	0.00115 U	0.000377 U	0.000335 U	0.000291 U	0.000394 U	0.000292 U	0.000263 U	0.000228 U	0.000249 U	0.000307 U
(9.9 to-10.1)	IW-51A-10	3/26/18	PES	ESC	10	41.9	V	0.000313 U	0.000423 U	0.000230 U	0.00115 U	0.000374 U	0.000333 U	0.000289 U	0.000390 U	0.000290 U	0.000261 U	0.000226 U	0.000246 U	0.000304 U
	IW-51A-15	3/26/18	PES	ESC	15	36.9	V	0.000325 U	0.000440 U	0.000239 U	0.00119 U	0.000389 U	0.000346 U	0.000301 U	0.000406 U	0.000302 U	0.000271 U	0.000235 U	0.000256 U	0.000316 U
	IW-51A-20	3/26/18	PES	ESC	20	31.9	S	0.000311 U	0.000420 U	0.000229 U	0.00114 U	0.000372 U	0.000330 U	0.000287 U	0.000388 U	0.000288 U	0.000259 U	0.000224 U	0.000245 U	0.000302 U
	IW-51A-25	3/26/18	PES	ESC	25	26.9	S	0.000396 U	0.000536 U	0.000291 U	0.00144 U	0.000473 U	0.000420 U	0.000365 U	0.000494 U	0.000367 U	0.000330 U	0.000286 U	0.000312 U	0.000385 U
	IW-51A-30	3/26/18	PES	ESC	30	21.9	S	0.000309 U	0.000418 U	0.000227 U	0.00113 U	0.000370 U	0.000329 U	0.000286 U	0.000386 U	0.000287 U	0.000258 U	0.000223 U	0.000244 U	0.000301 U
	IW-51A-35	3/26/18	PES	ESC	35	16.9	S	0.000313 U	0.000423 U	0.000230 U	0.00114 U	0.000374 U	0.000332 U	0.000289 U	0.000390 U	0.000290 U	0.000260 U	0.000225 U	0.000246 U	0.000304 U
	IW-51A-40	3/26/18	PES	ESC	40	11.9	S	0.000314 U	0.000424 U	0.000231 U	0.00115 U	0.000375 U	0.000333 U	0.000290 U	0.000391 U	0.000291 U	0.000261 U	0.000226 U	0.000247 U	0.000305 U
	IW-51A-42	3/26/18	PES	ESC	42	9.9	S	0.000319 U	0.000432 U	0.000235 U	0.00117 U	0.000382 U	0.000340 U	0.000295 U	0.000399 U	0.000296 U	0.000266 U	0.000230 U	0.000252 U	0.000311 U
	IW-51A-45	3/26/18	PES	ESC	45	6.9	S	0.000320 U	0.000432 U	0.000235 U	0.00117 U	0.000382 U	0.000340 U	0.000295 U	0.000399 U	0.000296 U	0.000266 U	0.000231 U	0.000252 U	0.000311 U
	IW-51A-50	3/26/18	PES	ESC	50	1.9	S	0.000329 U	0.000444 U	0.000242 U	0.00120 U	0.000393 U	0.000349 U	0.000304 U	0.000410 U	0.000305 U	0.000274 U	0.000237 U	0.000259 U	0.000320 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
IW-51A (continued)	IW-51A-55	3/26/18	PES	ESC	55	-3.1	S	0.000329 U	0.000445 U	0.000242 U	0.00120 U	0.000393 U	0.000350 U	0.000304 U	0.000410 U	0.000305 U	0.000274 U	0.000237 U	0.000259 U	0.000320 U
	IW-51A-60	3/26/18	PES	ESC	60	-8.1	S	0.000309 U	0.000417 U	0.000227 U	0.00113 U	0.000369 U	0.000328 U	0.000285 U	0.000385 U	0.000286 U	0.000257 U	0.000223 U	0.000243 U	0.000300 U
	IW-51A-62	3/26/18	PES	ESC	62	-10.1	S	0.000312 U	0.000422 U	0.000229 U	0.00114 U	0.000373 U	0.000332 U	0.000288 U	0.000389 U	0.000289 U	0.000260 U	0.000225 U	0.000246 U	0.000303 U
IW-53B (-11.1 to-26.1)	IW-53B-30	9/20/18	PES	ESC	30	5.3	S	0.00125 U	0.00524 U	0.00126 U	0.00555 U	0.000571 U	0.00158 U	0.000517 U	0.0138 U	0.00117 U	0.00185 U	0.00190 U	0.00214 U	0.000863 U
IW-54A (9.8 to-10.2)	IW-54A-8	9/12/18	PES	ESC	8	31.1	S	0.00133 U	0.00556 U	**0.00204 J**	0.00589 U	0.000606 U	0.00167 U	0.000548 U	0.293 U	0.00125 U	0.00196 U	0.00202 U	0.00227 U	0.000915 U
	IW-54A-49	9/12/18	PES	ESC	49	-9.9	S	0.00133 U	0.00558 U	**0.00160 J**	0.00591 U	0.000608 U	0.00168 U	0.000550 U	0.00147 U	0.00125 U	0.00197 U	0.00203 U	0.00228 U	0.000918 U
IW-54B (-9.5 to-24.5)	IW-54B-8	9/5/18	PES	ESC	8	31.2	S	0.00125 U	0.00526 U	**0.00891**	0.00556 U	0.000573 U	0.00158 U	0.000518 U	2.77 U	**0.00290 J**	0.00185 U	0.00191 U	0.00215 U	0.000865 U
	IW-54B-13	9/6/18	PES	ESC	13	26.2	S	0.00128 U	0.00535 U	0.00129 U	0.00566 U	0.000582 U	0.00161 U	0.000527 U	0.0141 U	0.00120 U	0.00189 U	0.00194 U	0.00219 U	0.000880 U
	IW-54B-21	9/6/18	PES	ESC	21	18.2	S	0.00125 U	0.00526 U	**0.00251 J**	0.00556 U	0.000573 U	0.00158 U	0.000518 U	**1.13**	0.00118 U	0.00185 U	0.00191 U	0.00215 U	0.000865 U
	IW-54B-33	9/6/18	PES	ESC	33	6.2	S	0.00144 U	0.00603 U	0.00145 U	0.00638 U	0.000656 U	0.00182 U	0.000595 U	0.00157 U	0.00134 U	0.00212 U	0.00219 U	0.00247 U	0.000991 U
IW-55B (-12.0 to-27.0)	IW-55B-39	9/13/18	PES	ESC	39	12.8	S	0.00122 U	0.00512 U	0.00123 U	0.00542 U	0.000557 U	0.00154 U	0.000504 U	0.00135 U	0.00115 U	0.00181 U	0.00186 U	0.00209 U	0.000842 U
	IW-55B-43	9/13/18	PES	ESC	43	8.8	S	**0.00306 J**	0.00545 U	**0.00711**	0.00577 U	0.000594 U	0.00164 U	0.000537 U	0.115 U	**0.00241 J**	0.00192 U	0.00198 U	0.00223 U	0.000897 U
	IW-55B-61	9/13/18	PES	ESC	61	-9.2	S	**0.00145 J**	0.00573 U	**0.00156 J**	0.00606 U	0.000624 U	0.00172 U	0.000564 U	0.0121 U	0.00128 U	0.00202 U	0.00208 U	0.00234 U	0.000942 U
IW-58A (3.9 to-11.1)	IW-58A-38	10/17/18	PES	PACE	38	1.2	S	0.00126 U	0.00527 U	0.00127 U	0.00557 U	0.000574 U	0.00158 U	0.000519 U	0.00139 U	0.00118 U	0.00186 U	0.00191 U	0.00215 U	0.000867 U
	B-929-38	10/17/18	PES	PACE	38 (dup)	1.2	S	0.00129 U	0.00543 U	**0.00149 J**	0.00574 U	0.000591 U	0.00163 U	0.000535 U	0.00143 U	0.00122 U	0.00191 U	0.00197 U	0.00222 U	0.000893 U
MW101 (B101) (-65.5 to-75.5)	B101-30	7/10/12	SES	F&BI	30	9.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-34	7/10/12	SES	F&BI	34	5.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-40	7/10/12	SES	F&BI	40	-0.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-47	7/10/12	SES	F&BI	47	-7.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-48	7/10/12	SES	F&BI	48	-8.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-55	7/10/12	SES	F&BI	55	-15.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-65	7/10/12	SES	F&BI	65	-25.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-75	7/11/12	SES	F&BI	75	-35.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-81	7/11/12	SES	F&BI	81	-41.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-92	7/12/12	SES	F&BI	92	-52.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-97	7/12/12	SES	F&BI	97	-57.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-104	7/12/12	SES	F&BI	104	-64.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-114.5	7/12/12	SES	F&BI	114.5	-75.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-120	7/12/12	SES	F&BI	120	-80.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-131	7/12/12	SES	F&BI	131	-91.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-140	7/12/12	SES	F&BI	140	-100.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW130 (B130) (-30.9 to-40.9)	B130-10	3/1/16	SES	F&BI	10	29.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B130-20	3/1/16	SES	F&BI	20	19.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B130-30	3/1/16	SES	F&BI	30	9.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B130-40	3/1/16	SES	F&BI	40	-0.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B130-45	3/2/16	SES	F&BI	45	-5.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B130-50	3/2/16	SES	F&BI	50	-10.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B130-55	3/2/16	SES	F&BI	55	-15.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B130-60	3/2/16	SES	F&BI	60	-20.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B130-65	3/2/16	SES	F&BI	65	-25.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B130-70	3/2/16	SES	F&BI	70	-30.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	**–**	**0.88**	**1.2**	**–**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	**–**	**0.058**	**0.068**	**–**
MW130 (B130)	B130-75	3/2/16	SES	F&BI	75	-35.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
(continued)	B130-80	3/2/16	SES	F&BI	80	-40.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW131 (B131)	B131-10	3/1/16	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
(-4.2 to-14.2)	B131-20	3/1/16	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B131-30	3/1/16	SES	F&BI	30	10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B131-40	3/1/16	SES	F&BI	40	0.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B131-45	3/2/16	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B131-55	3/2/16	SES	F&BI	55	-15.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-132	MW-132-20	8/22/17	PES	ESC	20	20.1	S	0.000320 U	0.000433 U	0.000235 U	0.00117 U	0.000382 U	0.000340 U	0.000295 U	0.000399 U	0.000297 U	0.000266 U	0.000231 U	0.000252 U	0.000311 U
(-29.9 to-39.9)	MW-132-35	8/22/17	PES	ESC	35	5.1	S	0.000321 U	0.000434 U	0.000236 U	0.00117 U	0.000384 U	0.000341 U	0.000297 U	0.000401 U	0.000298 U	0.000267 U	0.000232 U	0.000253 U	0.000312 U
	MW-132-50	8/22/17	PES	ESC	50	-9.9	S	0.000310 U	0.000420 U	0.000228 U	0.00114 U	0.000371 U	0.000330 U	0.000287 U	0.000387 U	0.000288 U	0.000259 U	0.000224 U	0.000244 U	0.000302 U
	MW-132-55	8/23/17	PES	ESC	55	-14.9	S	**0.0533 J**	0.0446 U	**0.212**	0.121 U	0.0394 U	0.0351 U	0.0305 U	0.0412 U	**0.0664 J**	0.0275 U	0.0238 U	0.0260 U	0.0321 U
	MW-132-60	8/23/17	PES	ESC	60	-19.9	S	0.000309 U	0.000418 U	0.000227 U	0.00113 U	0.000369 U	0.000328 U	0.000285 U	0.000386 U	0.000286 U	0.000257 U	0.000223 U	0.000243 U	0.000300 U
	MW-132-70	8/23/17	PES	ESC	70	-29.9	S	0.000350 U	0.000473 U	0.000257 U	0.00128 U	0.000418 U	0.000372 U	0.000323 U	0.000436 U	0.000324 U	0.000291 U	0.000252 U	0.000276 U	0.000340 U
	MW-132-83	8/23/17	PES	ESC	83	-42.9	S	0.000313 U	0.000423 U	0.000230 U	0.00115 U	0.000374 U	0.000333 U	0.000289 U	0.000391 U	0.000290 U	0.000261 U	0.000226 U	0.000247 U	0.000304 U
MW-133	MW-133-20	8/15/17	PES	ESC	20	20.1	S	0.000338 U	0.000457 U	0.000249 U	0.00124 U	0.000404 U	0.000359 U	0.000312 U	0.000422 U	0.000313 U	0.000282 U	0.000244 U	0.000266 U	0.000329 U
(-88.9 to-98.9)	MW-133-35	8/15/17	PES	ESC	35	5.1	S	0.000375 U	0.000507 U	0.000275 U	0.00137 U	0.000448 U	0.000398 U	0.000346 U	0.000467 U	0.000347 U	0.000312 U	0.000270 U	0.000295 U	0.000364 U
	MW-133-45	8/15/17	PES	ESC	45	-4.9	S	0.000312 U	0.000422 U	0.000229 U	0.00114 U	0.000373 U	0.000331 U	0.000288 U	0.000389 U	0.000289 U	0.000260 U	0.000225 U	0.000246 U	0.000303 U
	MW-133-55	8/15/17	PES	ESC	55	-14.9	S	0.0702 U	0.0949 U	0.0516 U	0.257 U	0.0839 U	0.0746 U	0.0648 U	0.0876 U	0.0651 U	0.0585 U	0.0506 U	0.0553 U	0.0683 U
	MW-133-58	8/15/17	PES	ESC	58	-17.9	S	1.70 U	2.29 U	1.25 U	6.21 U	2.03 U	1.80 U	1.56 U	2.12 U	1.57 U	1.42 U	1.23 U	1.34 U	1.66 U
	MW-133-65	8/15/17	PES	ESC	65	-24.9	S	0.000332 U	0.000449 U	0.000244 U	0.00122 U	0.000397 U	0.000353 U	0.000307 U	0.000414 U	0.000308 U	0.000277 U	0.000240 U	0.000262 U	0.000323 U
	MW-133-75	8/15/17	PES	ESC	75	-34.9	S	0.000334 U	0.000451 U	0.000245 U	0.00122 U	0.000399 U	0.000355 U	0.000308 U	0.000416 U	0.000309 U	0.000278 U	0.000241 U	0.000263 U	0.000325 U
	MW-133-85	8/15/17	PES	ESC	85	-44.9	S	0.00842 U	0.0114 U	0.00619 U	0.0307 U	0.0101 U	0.00893 U	0.00776 U	0.0105 U	0.00780 U	0.00701 U	0.00607 U	0.00662 U	0.00818 U
	MW-133-95	8/16/17	PES	ESC	95	-54.9	S	0.000334 U	0.000452 U	0.000246 U	0.00122 U	0.000400 U	0.000355 U	0.000309 U	0.000417 U	0.000310 U	0.000278 U	0.000241 U	0.000263 U	0.000325 U
	MW-133-105	8/16/17	PES	ESC	105	-64.9	S	0.000346 U	0.000467 U	0.000254 U	0.00126 U	0.000413 U	0.000367 U	0.000319 U	0.000431 U	0.000320 U	0.000288 U	0.000249 U	0.000272 U	0.000336 U
	MW-133-120	8/16/17	PES	ESC	120	-79.9	S	0.00780 U	0.0105 U	0.00574 U	0.0285 U	0.00933 U	0.00828 U	0.00719 U	0.00973 U	0.00723 U	0.00650 U	0.00563 U	0.00614 U	0.00759 U
	MW-133-130	8/16/17	PES	ESC	130	-89.9	S	0.000342 U	0.000462 U	0.000251 U	0.00125 U	0.000409 U	0.000363 U	0.000316 U	0.000426 U	0.000317 U	0.000285 U	0.000247 U	0.000269 U	0.000332 U
	MW-133-135	8/16/17	PES	ESC	135	-94.9	S	0.000325 U	0.000440 U	**0.000845 J**	0.00119 U	0.000389 U	0.000346 U	0.000300 U	0.000406 U	0.000301 U	0.000271 U	0.000234 U	0.000256 U	0.000316 U
	MW-133-141	8/16/17	PES	ESC	141	-100.9	S	0.000323 U	0.000437 U	0.000238 U	0.00118 U	0.000386 U	0.000343 U	0.000298 U	0.000403 U	0.000300 U	0.000269 U	0.000233 U	0.000255 U	0.000314 U
MW-134	MW-134-20	8/29/17	PES	ESC	20	21.5	S	0.000378 U	0.000511 U	0.000278 U	0.00138 U	0.000451 U	0.000401 U	0.000349 U	0.000471 U	0.000350 U	0.000315 U	0.000272 U	0.000297 U	0.000367 U
(-38.6 to-48.6)	MW-134-43	8/29/17	PES	ESC	43	-1.6	S	0.00833 U	0.000450 U	0.00613 U	0.00122 U	0.000398 U	0.000354 U	0.000307 U	0.000415 U	0.000309 U	0.000277 U	0.000240 U	0.000262 U	0.00810 U
	MW-134-50	8/29/17	PES	ESC	50	-8.6	S	0.0316 U	0.000427 U	**0.0675 J**	0.00115 U	0.000377 U	0.000335 U	0.000291 U	0.000394 U	0.000292 U	0.000263 U	0.000228 U	0.000248 U	0.0307 U
	MW-134-60	8/29/17	PES	ESC	60	-18.6	S	0.00793 U	0.000428 U	0.00583 U	0.00116 U	0.000379 U	0.000337 U	0.000293 U	0.000395 U	0.000294 U	0.000264 U	0.000229 U	0.000250 U	0.00771 U
	MW-134-70	8/29/17	PES	ESC	70	-28.6	S	0.000366 U	0.000495 U	0.000269 U	0.00134 U	0.000438 U	0.000389 U	0.000338 U	0.000457 U	0.000339 U	0.000305 U	0.000264 U	0.000288 U	0.000356 U
	MW-134-80	8/29/17	PES	ESC	80	-38.6	S	0.000307 U	0.000415 U	0.000226 U	0.00112 U	0.000367 U	0.000326 U	0.000283 U	0.000383 U	0.000284 U	0.000256 U	0.000221 U	0.000242 U	0.000298 U
	B-903-100	8/29/17	PES	ESC	80 (dup)	-38.6	S	0.000302 U	0.000409 U	0.000222 U	0.00111 U	0.000361 U	0.000321 U	0.000279 U	0.000377 U	0.000280 U	0.000252 U	0.000218 U	0.000238 U	0.000294 U
	MW-134-90	8/29/17	PES	ESC	90	-48.6	S	0.00912 U	0.000493 U	0.00671 U	0.00133 U	0.000436 U	0.000387 U	0.000337 U	0.000455 U	0.000338 U	0.000304 U	0.000263 U	0.000287 U	0.00886 U
MW-135	MW-135-16	8/24/17	PES	ESC	14	25.1	S	**0.257**	0.0473 U	**0.483**	0.128 U	0.0418 U	0.0372 U	0.0323 U	0.0437 U	**0.159**	0.0292 U	0.0253 U	0.0276 U	0.0340 U
(-30.9 to-40.9)	MW-135-20	8/24/17	PES	ESC	20	19.1	S	0.00818 U	0.0110 U	0.00601 U	0.0298 U	0.00977 U	0.00868 U	0.00754 U	0.0102 U	0.00757 U	0.00681 U	0.00590 U	0.00644 U	0.00795 U
	MW-135-30	8/24/17	PES	ESC	30	9.1	S	**0.00146**	0.000412 U	**0.00350**	0.00112 U	0.000364 U	0.000324 U	0.000281 U	0.000380 U	**0.00114**	0.000254 U	0.000220 U	0.000240 U	0.000296 U
	MW-135-36	8/24/17	PES	ESC	36	3.1	S	0.000335 U	0.000453 U	**0.000439 J**	0.00123 U	0.000400 U	0.000356 U	0.000309 U	0.000418 U	0.000311 U	0.000279 U	0.000242 U	0.000264 U	0.000326 U
	MW-135-40	8/24/17	PES	ESC	40	-0.9	S	0.000342 U	0.000463 U	**0.000329 J**	0.00125 U	0.000409 U	0.000364 U	0.000316 U	0.000427 U	0.000317 U	0.000285 U	0.000247 U	0.000270 U	0.000333 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
MW-135 (continued)	MW-135-45	8/24/17	PES	ESC	45	-5.9	S	0.000341 U	0.000461 U	**0.000717 J**	0.00125 U	0.000407 U	0.000362 U	0.000315 U	0.000425 U	0.000316 U	0.000284 U	0.000246 U	0.000268 U	0.000331 U
	MW-135-55	8/24/17	PES	ESC	55	-15.9	S	0.000312 U	0.000421 U	0.000229 U	0.00114 U	0.000373 U	0.000331 U	0.000288 U	0.000389 U	0.000289 U	0.000260 U	0.000225 U	0.000246 U	0.000303 U
	MW-135-65	8/24/17	PES	ESC	65	-25.9	S	0.000341 U	0.000460 U	0.000250 U	0.00125 U	0.000407 U	0.000362 U	0.000314 U	0.000425 U	0.000316 U	0.000284 U	0.000246 U	0.000268 U	0.000331 U
	MW-135-80	8/24/17	PES	ESC	80	-40.9	S	0.000321 U	0.000433 U	0.000236 U	0.00117 U	0.000383 U	0.000341 U	0.000296 U	0.000400 U	0.000297 U	0.000267 U	0.000231 U	0.000252 U	0.000312 U
MW-136 (-32.7 to-42.7)	MW-136-35	8/28/17	PES	ESC	35	16.9	S	0.000302 U	0.000408 U	0.000222 U	0.00111 U	0.000361 U	0.000321 U	0.000279 U	0.000377 U	0.000280 U	0.000252 U	0.000218 U	0.000238 U	0.000294 U
	B-902-15	8/28/17	PES	ESC	35 (dup)	16.9	S	0.000313 U	0.000424 U	0.000230 U	0.00115 U	0.000375 U	0.000333 U	0.000289 U	0.000391 U	0.000291 U	0.000261 U	0.000226 U	0.000247 U	0.000305 U
	MW-136-44	8/28/17	PES	ESC	44	7.9	S	0.000322 U	0.000435 U	0.000237 U	0.00118 U	0.000385 U	0.000342 U	0.000297 U	0.000402 U	0.000299 U	0.000268 U	0.000232 U	0.000254 U	0.000313 U
	MW-136-50	8/28/17	PES	ESC	50	1.9	S	0.00826 U	0.000446 U	0.00608 U	0.00121 U	0.000395 U	0.000351 U	0.000305 U	0.000412 U	0.000306 U	0.000275 U	0.000238 U	0.000260 U	0.00803 U
	MW-136-65	8/28/17	PES	ESC	65	-13.1	S	0.000312 U	0.000422 U	0.000229 U	0.00114 U	0.000373 U	0.000332 U	0.000288 U	0.000389 U	0.000289 U	0.000260 U	0.000225 U	0.000246 U	0.000303 U
	MW-136-75	8/28/17	PES	ESC	75	-23.1	S	0.000319 U	0.000431 U	0.000234 U	0.00117 U	0.000381 U	0.000339 U	0.000294 U	0.000398 U	0.000296 U	0.000266 U	0.000230 U	0.000251 U	0.000310 U
	MW-136-85	8/28/17	PES	ESC	85	-33.1	S	0.000320 U	0.000433 U	0.000236 U	0.00117 U	0.000383 U	0.000340 U	0.000296 U	0.000400 U	0.000297 U	0.000267 U	0.000231 U	0.000252 U	0.000311 U
	MW-136-95	8/28/17	PES	ESC	95	-43.1	S	0.000321 U	0.000434 U	0.000236 U	0.00117 U	0.000384 U	0.000341 U	0.000297 U	0.000401 U	0.000298 U	0.000267 U	0.000232 U	0.000253 U	0.000312 U
MW-137 (-53.3 to-63.3)	MW-137-25	8/31/17	PES	ESC	25	26.7	S	0.000313 U	0.000423 U	0.000230 U	0.00115 U	0.000374 U	0.000333 U	0.000289 U	0.000390 U	0.000290 U	0.000261 U	0.000226 U	0.000246 U	0.000304 U
	MW-137-45	8/31/17	PES	ESC	45	6.7	S	0.00813 U	0.0110 U	0.00597 U	0.0296 U	0.00971 U	0.00862 U	0.00749 U	0.0101 U	0.00753 U	0.00677 U	0.00586 U	0.00639 U	0.00790 U
	MW-137-75	8/31/17	PES	ESC	75	-23.3	S	0.000315 U	0.000426 U	0.000232 U	0.00115 U	0.000377 U	0.000335 U	0.000291 U	0.000393 U	0.000292 U	0.000262 U	0.000227 U	0.000248 U	0.000306 U
	MW-137-85	9/1/17	PES	ESC	85	-33.3	S	0.000344 U	0.000465 U	0.000253 U	0.00126 U	0.000411 U	0.000366 U	0.000318 U	0.000429 U	0.000319 U	0.000286 U	0.000248 U	0.000271 U	0.000334 U
	MW-137-95	9/1/17	PES	ESC	95	-43.3	S	0.000307 U	0.000416 U	0.000226 U	0.00112 U	0.000367 U	0.000327 U	0.000284 U	0.000383 U	0.000285 U	0.000256 U	0.000222 U	0.000242 U	0.000299 U
	MW-137-115	9/1/17	PES	ESC	115	-63.3	S	0.000351 U	0.000475 U	0.000258 U	0.00128 U	0.000420 U	0.000373 U	0.000324 U	0.000438 U	0.000325 U	0.000292 U	0.000253 U	0.000276 U	0.000341 U
MW-139 (-30.2 to-40.2)	MW-139-20	9/13/17	PES	ESC	20	19.8	S	0.000332 U	0.000449 U	0.000244 U	0.00121 U	0.000397 U	0.000353 U	0.000307 U	0.000414 U	0.000308 U	0.000276 U	0.000239 U	0.000261 U	0.000323 U
	MW-139-31	9/13/17	PES	ESC	31	8.8	S	0.000307 U	0.000415 U	0.000226 U	0.00112 U	0.000367 U	0.000326 U	0.000284 U	0.000383 U	0.000285 U	0.000256 U	0.000221 U	0.000242 U	0.000298 U
	MW-139-41	9/13/17	PES	ESC	41	-1.2	S	0.000308 U	0.000417 U	0.000227 U	0.00113 U	0.000368 U	0.000328 U	0.000285 U	0.000385 U	0.000286 U	0.000257 U	0.000222 U	0.000243 U	0.000300 U
	MW-139-51	9/13/17	PES	ESC	51	-11.2	S	0.000331 U	0.000448 U	0.000243 U	0.00121 U	0.000396 U	0.000352 U	0.000306 U	0.000413 U	0.000307 U	0.000276 U	0.000239 U	0.000261 U	0.000322 U
	MW-139-60	9/13/17	PES	ESC	60	-20.2	S	0.000308 U	0.000417 U	0.000227 U	0.00113 U	0.000368 U	0.000328 U	0.000285 U	0.000384 U	0.000286 U	0.000257 U	0.000222 U	0.000243 U	0.000300 U
	MW-139-70	9/13/17	PES	ESC	70	-30.2	S	0.000339 U	0.000458 U	0.000249 U	0.00124 U	0.000405 U	0.000360 U	0.000313 U	0.000422 U	0.000314 U	0.000282 U	0.000244 U	0.000267 U	0.000329 U
	MW-139-80	9/13/17	PES	ESC	80	-40.2	S	0.000324 U	0.000438 U	0.000238 U	0.00119 U	0.000388 U	0.000345 U	0.000299 U	0.000405 U	0.000301 U	0.000270 U	0.000234 U	0.000255 U	0.000315 U
MW-141 (-55.4 to-65.4)	MW-141-15	9/18/17	PES	ESC	15	24.6	S	0.000324 U	0.000438 U	0.000238 U	0.00118 U	0.000387 U	0.000344 U	0.000299 U	0.000404 U	0.000300 U	0.000270 U	0.000234 U	0.000255 U	0.000315 U
	MW-141-35	9/18/17	PES	ESC	35	4.6	S	0.000333 U	0.000450 U	0.000245 U	0.00122 U	0.000398 U	0.000354 U	0.000307 U	0.000415 U	0.000309 U	0.000277 U	0.000240 U	0.000262 U	0.000324 U
	MW-141-46	9/18/17	PES	ESC	46	-6.4	S	0.000314 U	0.000424 U	0.000231 U	0.00115 U	0.000375 U	0.000333 U	0.000290 U	0.000391 U	0.000291 U	0.000261 U	0.000226 U	0.000247 U	0.000305 U
	MW-141-56	9/18/17	PES	ESC	56	-16.4	S	0.000305 U	0.000413 U	0.000224 U	0.00112 U	0.000365 U	0.000324 U	0.000282 U	0.000381 U	0.000283 U	0.000254 U	0.000220 U	0.000240 U	0.000297 U
	MW-141-65	9/18/17	PES	ESC	65	-25.4	S	0.000302 U	0.000408 U	0.000222 U	0.00110 U	0.000361 U	0.000321 U	0.000279 U	0.000377 U	0.000280 U	0.000251 U	0.000218 U	0.000238 U	0.000293 U
	MW-141-75	9/18/17	PES	ESC	75	-35.4	S	0.000306 U	0.000414 U	0.000225 U	0.00112 U	0.000366 U	0.000325 U	0.000282 U	0.000382 U	0.000284 U	0.000255 U	0.000221 U	0.000241 U	0.000297 U
	MW-141-85	9/18/17	PES	ESC	85	-45.4	S	0.000335 U	0.000453 U	0.000246 U	0.00123 U	0.000401 U	0.000356 U	0.000309 U	0.000418 U	0.000311 U	0.000279 U	0.000242 U	0.000264 U	0.000326 U
	MW-141-95	9/18/17	PES	ESC	95	-55.4	S	0.000344 U	0.000465 U	0.000253 U	0.00126 U	0.000411 U	0.000365 U	0.000317 U	0.000429 U	0.000319 U	0.000286 U	0.000248 U	0.000271 U	0.000334 U
	MW-141-105	9/19/17	PES	ESC	105	-65.4	S	0.000343 U	0.000463 U	0.000252 U	0.00125 U	0.000409 U	0.000364 U	0.000316 U	0.000427 U	0.000318 U	0.000285 U	0.000247 U	0.000270 U	0.000333 U
MW-152 (-10.2 to-20.2)	MW-152-5	3/13/18	PES	ESC	5	34.1	S	**0.000532 J**	0.000437 U	**0.000877 J**	0.00118 U	0.000386 U	0.000344 U	0.000299 U	0.000403 U	0.000300 U	0.000269 U	0.000233 U	0.000255 U	0.000314 U
	MW-152-15	3/13/18	PES	ESC	15	24.1	S	0.000318 U	0.000430 U	0.000234 U	0.00116 U	0.000380 U	0.000338 U	0.000293 U	0.000396 U	0.000295 U	0.000265 U	0.000229 U	0.000250 U	0.000309 U
	MW-152-25	3/13/18	PES	ESC	25	14.1	S	0.000311 U	0.000421 U	0.000229 U	0.00114 U	0.000372 U	0.000331 U	0.000287 U	0.000388 U	0.000289 U	0.000259 U	0.000225 U	0.000245 U	0.000303 U
	MW-152-35	3/13/18	PES	ESC	35	4.1	S	0.000315 U	0.000426 U	0.000231 U	0.00115 U	0.000376 U	0.000334 U	0.000291 U	0.000393 U	0.000292 U	0.000262 U	0.000227 U	0.000248 U	0.000306 U
	MW-152-45	3/13/18	PES	ESC	45	-5.9	S	**0.00185**	0.000437 U	**0.00577**	0.00118 U	0.000387 U	0.000344 U	0.000299 U	0.000404 U	**0.00190**	0.000269 U	0.000233 U	0.000255 U	0.000315 U
	MW-152-55	3/13/18	PES	ESC	55	-15.9	S	0.000325 U	0.000439 U	**0.000440 J**	0.00119 U	0.000389 U	0.000345 U	0.000300 U	0.000406 U	0.000301 U	0.000271 U	0.000234 U	0.000256 U	0.000316 U
	MW-152-60	3/13/18	PES	ESC	60	-20.9	S	0.000310 U	0.000420 U	0.000228 U	0.00114 U	0.000371 U	0.000330 U	0.000287 U	0.000387 U	0.000288 U	0.000259 U	0.000224 U	0.000244 U	0.000302 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
MW-162 (-61.6 to-71.6)	MW-162-48	1/28/19	PES	PACE	48	-9.6	S	0.0249 U	0.104 U	0.0251 U	0.110 U	0.0114 U	0.0314 U	0.0103 U	0.0275 U	0.0234 U	0.0368 U	0.0379 U	0.0426 U	0.0172 U
	MW-162-50	1/28/19	PES	PACE	50	-11.6	S	0.00134 U	0.00563 U	0.00136 U	0.00596 U	0.000613 U	0.00169 U	0.000555 U	0.0297 U	0.00126 U	0.00199 U	0.00204 U	0.00230 U	0.000926 U
	B-930-50 (dup)	1/28/19	PES	PACE	50	-11.6	S	**0.00136 J**	0.00536 U	**0.00147 J**	0.00567 U	0.000584 U	0.00161 U	0.000528 U	0.0565 U	0.00120 U	0.00189 U	0.00195 U	0.00219 U	0.000882 U
	MW-162-67	1/28/19	PES	PACE	67	-28.6	S	0.00134 U	0.00560 U	**0.00251 J**	0.00592 U	0.000610 U	0.00168 U	0.000552 U	0.0295 U	0.00125 U	0.00197 U	0.00203 U	0.00229 U	0.000921 U
	MW-162-70	1/28/19	PES	PACE	70	-31.6	S	**0.00273 J**	0.00538 U	**0.00452 J**	0.00569 U	0.000586 U	0.00162 U	0.000530 U	0.0567 U	**0.00177 J**	0.00190 U	0.00195 U	0.00220 U	0.000885 U
	MW-162-72	1/28/19	PES	PACE	72	-33.6	S	0.00124 U	0.00520 U	0.00125 U	0.00550 U	0.000566 U	0.00156 U	0.000512 U	0.0548 U	0.00117 U	0.00183 U	0.00189 U	0.00213 U	0.000856 U
	MW-162-80	1/28/19	PES	PACE	80	-41.6	S	0.00128 U	0.00536 U	0.00129 U	0.00568 U	0.000584 U	0.00161 U	0.000529 U	0.00141 U	0.00120 U	0.00189 U	0.00195 U	0.00219 U	0.000883 U
	MW-162-85	1/28/19	PES	PACE	85	-46.6	S	0.00130 U	0.00546 U	0.00131 U	0.00577 U	0.000594 U	0.00164 U	0.000538 U	0.00144 U	0.00122 U	0.00192 U	0.00198 U	0.00223 U	0.000898 U
	MW-162-90	1/28/19	PES	PACE	90	-51.6	S	0.00130 U	0.00545 U	0.00131 U	0.00576 U	0.000593 U	0.00164 U	0.000537 U	0.00144 U	0.00122 U	0.00192 U	0.00198 U	0.00223 U	0.000896 U
	MW-162-95	1/28/19	PES	PACE	95	-56.6	S	0.00132 U	0.00553 U	0.00133 U	0.00585 U	0.000602 U	0.00166 U	0.000545 U	0.00146 U	0.00124 U	0.00195 U	0.00201 U	0.00226 U	0.000910 U
	MW-162-100	1/28/19	PES	PACE	100	-61.6	S	0.00134 U	0.00563 U	0.00135 U	0.00595 U	0.000613 U	0.00169 U	0.000555 U	0.00148 U	0.00126 U	0.00198 U	0.00204 U	0.00230 U	0.000926 U
	MW-162-105	1/28/19	PES	PACE	105	-66.6	S	0.00129 U	0.00542 U	0.00130 U	0.00573 U	0.000590 U	0.00163 U	0.000534 U	0.00143 U	0.00121 U	0.00191 U	0.00197 U	0.00221 U	0.000891 U
	MW-162-110	1/28/19	PES	PACE	110	-71.6	S	0.00126 U	0.00528 U	0.00127 U	0.00558 U	0.000575 U	0.00159 U	0.000520 U	0.00139 U	0.00118 U	0.00186 U	0.00192 U	0.00216 U	0.000868 U
MW-163 (-61.0 to-71.0)	MW-163-47	1/29/19	PES	PACE	47	-7.7	S	**0.00144 J**	0.00539 U	**0.00329 J**	0.00570 U	0.000587 U	0.00162 U	0.000531 U	0.0284 U	**0.00143 J**	0.00190 U	0.00196 U	0.00220 U	0.000887 U
	MW-163-50	1/29/19	PES	PACE	50	-10.7	S	**0.00125 J**	0.00521 U	**0.00129 J**	0.00551 U	0.000567 U	0.00157 U	0.000513 U	0.0274 U	0.00117 U	0.00184 U	0.00189 U	0.00213 U	0.000857 U
	MW-163-55	1/29/19	PES	PACE	55	-15.7	S	0.00141 U	0.00591 U	0.00142 U	0.00625 U	0.000643 U	0.00177 U	0.000582 U	0.0311 U	0.00132 U	0.00208 U	0.00214 U	0.00242 U	0.000972 U
	MW-163-60	1/29/19	PES	PACE	60	-20.7	S	**0.00146 J**	0.00546 U	**0.00318 J**	0.00577 U	0.000594 U	0.00164 U	0.000538 U	0.0288 U	**0.00147 J**	0.00192 U	0.00198 U	0.00223 U	0.000898 U
	MW-163-80	1/29/19	PES	PACE	80	-40.7	S	0.00131 U	0.00548 U	0.00132 U	0.00580 U	0.000597 U	0.00165 U	0.000540 U	0.00144 U	0.00123 U	0.00193 U	0.00199 U	0.00224 U	0.000902 U
	MW-163-85	1/29/19	PES	PACE	85	-45.7	S	0.00136 U	0.00570 U	0.00137 U	0.00604 U	0.000621 U	0.00172 U	0.000562 U	0.00150 U	0.00128 U	0.00201 U	0.00207 U	0.00233 U	0.000939 U
	MW-163-90	1/29/19	PES	PACE	90	-50.7	S	0.00125 U	0.00523 U	0.00126 U	0.00553 U	0.000569 U	0.00157 U	0.000515 U	0.00138 U	0.00117 U	0.00184 U	0.00190 U	0.00214 U	0.000860 U
	MW-163-95	1/29/19	PES	PACE	95	-55.7	S	0.00136 U	0.00571 U	0.00138 U	0.00605 U	0.000622 U	0.00172 U	0.000563 U	0.00151 U	0.00128 U	0.00202 U	0.00207 U	0.00234 U	0.000940 U
	MW-163-100	1/29/19	PES	PACE	100	-60.7	S	0.00132 U	0.00554 U	0.00133 U	0.00586 U	0.000603 U	0.00167 U	0.000546 U	0.00146 U	0.00124 U	0.00195 U	0.00201 U	0.00226 U	0.000911 U
	MW-163-105	1/29/19	PES	PACE	105	-65.7	S	0.00121 U	0.00506 U	0.00122 U	0.00535 U	0.000551 U	0.00152 U	0.000499 U	0.00133 U	0.00113 U	0.00178 U	0.00184 U	0.00207 U	0.000833 U
	MW-163-110	1/29/19	PES	PACE	110	-70.7	S	0.00127 U	0.00534 U	0.00129 U	0.00565 U	0.000582 U	0.00161 U	0.000526 U	0.00141 U	0.00120 U	0.00188 U	0.00194 U	0.00218 U	0.000879 U
MW-164 (-59.9 to-69.9)	MW-164-80	1/24/19	PES	PACE	80	-40.3	S	0.00131 U	0.00549 U	0.00132 U	0.00581 U	0.000598 U	0.00165 U	0.000541 U	0.00145 U	0.00123 U	0.00194 U	0.00199 U	0.00224 U	0.000903 U
	MW-164-87	1/24/19	PES	PACE	87	-47.3	S	0.00129 U	0.00540 U	0.00130 U	0.00571 U	0.000588 U	0.00162 U	0.000532 U	0.00142 U	0.00121 U	0.00190 U	0.00196 U	0.00221 U	0.000888 U
	MW-164-90	1/24/19	PES	PACE	90	-50.3	S	0.00135 U	0.00565 U	0.00136 U	0.00597 U	0.000615 U	0.00170 U	0.000556 U	0.00149 U	0.00126 U	0.00199 U	0.00205 U	0.00231 U	0.000929 U
	MW-164-95	1/25/19	PES	PACE	95	-55.3	S	0.00138 U	0.00576 U	0.00139 U	0.00610 U	0.000628 U	0.00173 U	0.000568 U	0.00152 U	0.00129 U	0.00203 U	0.00209 U	0.00236 U	0.000948 U
	MW-164-100	1/25/19	PES	PACE	100	-60.3	S	0.00144 U	0.00603 U	0.00145 U	0.00638 U	0.000656 U	0.00181 U	0.000594 U	0.00159 U	0.00135 U	0.00213 U	0.00219 U	0.00246 U	0.000991 U
	MW-164-105	1/25/19	PES	PACE	105	-65.3	S	0.00128 U	0.00535 U	0.00129 U	0.00566 U	0.000582 U	0.00161 U	0.000527 U	0.00141 U	0.00120 U	0.00189 U	0.00194 U	0.00218 U	0.000879 U
	MW-164-110	1/25/19	PES	PACE	110	-70.3	S	0.00127 U	0.00532 U	0.00128 U	0.00562 U	0.000579 U	0.00160 U	0.000524 U	0.00140 U	0.00119 U	0.00187 U	0.00193 U	0.00217 U	0.000875 U
	B-929-120	1/25/19	PES	PACE	110 (dup)	-70.3	S	0.00129 U	0.00542 U	0.00130 U	0.00573 U	0.000590 U	0.00163 U	0.000534 U	0.00143 U	0.00121 U	0.00191 U	0.00197 U	0.00221 U	0.000891 U
MW-168 (-43.0 to -53.0)	MW-168-15	10/21/19	PES	Fremont	15	-3.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-171 (-27.6 to -37.6)	MW-171-24	09/24/19	PES	Fremont	24	-12.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-172 (-42.5 to -52.5)	MW-172-7	09/26/19	PES	Fremont	7	4.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-175 (-27.8 to -37.8)	MW-175-12	10/26/19	PES	Fremont	12	-1.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B-1002-12	10/26/19	PES	Fremont	12 (dup)	-1.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	**–**	**0.88**	**1.2**	**–**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	**–**	**0.058**	**0.068**	**–**
MW-180 (-42.7 to -52.7)	MW-180-40	09/25/19	PES	Fremont	40	-28.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW-180-24	09/25/19	PES	Fremont	24	-12.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW-180-27	09/25/19	PES	Fremont	27	-15.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-181 (1.5 to -8.5)	MW-181-14	09/27/19	PES	Fremont	14	-2.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-183 (-27.4 to -37.4)	MW-183-18	09/26/19	PES	Fremont	18	-6.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-184 (-42.5 to -52.5)	MW-184-20	09/26/19	PES	Fremont	20	-8.4	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-188 (-42.2 to -52.2)	MW-188-64	10/01/19	PES	Fremont	64	-52.4	S	–	–	–	–	–	–	–	–	–	–	–	–	–
P01	P01-05	2/12/14	SES	F&BI	5	35.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	P01-10	2/12/14	SES	F&BI	10	30.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
P02	P02-05	2/12/14	SES	F&BI	5	34.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	P02-07.5	2/12/14	SES	F&BI	7.5	32.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
P03	P03-05	2/12/14	SES	F&BI	5	34.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
P03	P03-07.5	2/12/14	SES	F&BI	7.5	32.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
P04	P04-05	2/12/14	SES	F&BI	7.5	32.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	P04-10	2/12/14	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
P05	P05-05	2/12/14	SES	F&BI	5	35.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	P05-07.5	2/12/14	SES	F&BI	7.5	32.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
P06	P06-07.5	2/12/14	SES	F&BI	7.5	32.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	P06-10	2/12/14	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
R-MW1	Unknown	10/22/92	Roux	Unknown	5	32.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
W-MW-03 (P-07)	SB-W-07-0135	1/26/12	WW	ARI	13.5-14	25.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-07-0275	1/26/12	WW	ARI	27.5-28	11.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-07-0335	1/26/12	WW	ARI	33.5-34	5.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-07-0430	1/26/12	WW	ARI	43-43.5	-4.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-07-0530	1/26/12	WW	ARI	53-53.5	-14.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-07-0630	1/26/12	WW	ARI	63-63.5	-24.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-07-0780	1/26/12	WW	ARI	78-78.5	-39.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	**–**	**0.88**	**1.2**	**–**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	**–**	**0.058**	**0.068**	**–**
W-MW-04 (P-08)	SB-W-08-0090	1/28/12	WW	ARI	9-9.5	26.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-08-0155	1/28/12	WW	ARI	15.5-16	19.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-08-0265	1/28/12	WW	ARI	26.5-27	8.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-08-0380	1/28/12	WW	ARI	38-38.5	-3.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-08-0480	1/28/12	WW	ARI	48-48.5	-13.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-08-9480	1/28/12	WW	ARI	48-48.5 (dup)	-13.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-08-0590	1/28/12	WW	ARI	59-59.5	-24.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-08-0710	1/29/12	WW	ARI	71-71.5	-36.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-08-0760	1/29/12	WW	ARI	76-76.5	-41.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
All Data							Number of Analytes Measured	805	805	805	805	805	805	805	805	805	805	805	805	805
							Number of Analytes Detected	47	0	94	0	0	0	0	2	44	0	0	0	5
							Frequency of Detection	5.8%	0.0%	11.7%	0.0%	0.0%	0.0%	0.0%	0.2%	5.5%	0.0%	0.0%	0.0%	0.6%
							Maximum Detection	5.03	–	17	–	–	–	–	1.13	3.37	–	–	–	0.00316 J
							Minimum Detection	0.000287 U	0.000388 U	0.000211 U	0.00105 U	0.000343 U	0.000305 U	0.000265 U	0.000358 U	0.000266 U	0.000239 U	0.000207 U	0.000226 U	0.000279 U
							Number Of Vadose (V) Detections above SL	0	0	0	0	0	0	0	0	0	–	0	0	–
							Number of Saturated (S) Detections above SL	5	0	7	0	0	0	0	2	4	–	0	0	–
2017-2021							Number of Analytes Measured	805	805	805	805	805	805	805	805	805	805	805	805	805
							Number of Analytes Detected	47	0	94	0	0	0	0	2	44	0	0	0	5
							Frequency of Detection	5.8%	0.0%	11.7%	0.0%	0.0%	0.0%	0.0%	0.2%	5.5%	0.0%	0.0%	0.0%	0.6%
							Maximum Detection	5.03	–	17	–	–	–	–	1.13	3.37	–	–	–	0.00316 J
							Minimum Detection	0.000287 U	0.000388 U	0.000211 U	0.00105 U	0.000343 U	0.000305 U	0.000265 U	0.000358 U	0.000266 U	0.000239 U	0.000207 U	0.000226 U	0.000279 U
							Number Of Vadose (V) Detections above SL	0	0	0	0	0	0	0	0	0	–	0	0	–
							Number of Saturated (S) Detections above SL	5	0	7	0	0	0	0	2	4	–	0	0	–

Abbreviations:
AAL = Alden Analytical Laboratories, Inc., of Seattle, Washington
ARI = Analytical Resource, Incorporated, Seattle, Washington
B&V = Black Veatch
bgs = below ground surface
Comp = Composite Sample
dup = duplicate
EPJ = E.PJohnson Construction Inc., and Environmental
ESC = ESC Lab Services of Mt. Juliet, Tennessee
F&BI = Friedman & Bruya, Inc.
GeoEng = GeoEngineers, Inc.
HC = Hart Crowser, Inc.
NCA = North Creek Analytical, of Bothell, Washington
OnSite = OnSite Environmental Inc., of Redmond, Washington
Pace = Pace Analytical of Mt. Juliet, Tennessee (formerly ESC)
PES = PES Environmental, Inc.
Retec = Remediation Technologies, Inc.
Roux = Roux Associates
SES = SoundEarth Strategies, Inc.
TR = TR Corporation
Urban = Urban Redevelopment LLC
WW = WW Environmental LLC

Notes:
All on-Property soil was excavated during Property redevelopment above elevations 0.7 to 10.7 feet, and CVOCs in soil between elevations +10 to 55 feet was treated.
Petroleum Hydrocarbons (PHCs) analyzed by Ecology Methods NWTPH-HCID, NWTPH-Gx, or NWTPH-Dx; or EPA Method 418.1, Method 8020, or Method 8015M.
VOCs analyzed by EPA Methods 8010, 8020, 8021B, 624/8240, or 8260B/C/D.
Well screen elevations provided below Sample Location. in parentheses when appliable.
PCUL = Preliminary Cleanup Level from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021. PCULs based on the practical quantitation limits (PQLs) italicized.
Detected results shown in **bold**.
Detections above the screening level in the vadose zone are shown in **bold and highlighted blue.**
Detections above the screening level in the saturated zone are shown in **bold** and **highlighted gray.**
– = Not available or results not analyzed.
A = Result reported as total petroleum hydrocarbons.
B = Analyte detected in an associated method blank.
J = The reported concentration is an estimate based on detectable results between the method detection limit and reporting limit, laboratory QA/QC, or data validation review.
J+ = The result is an estimated quantity, but the result may be biased high.
J- = The result is an estimated quantity, but the result may be biased low.
ND = Not detected above laboratory reporting limit. Reporting limit not available.
q = Sample may contain gasoline or petroleum components. Chromatographic pattern indicates the presence of gasoline constituents.
R = The data is unusable. The sample result is rejected due to serious deficiencies in meeting QC criteria. The analyte may or may not be present in the sample
T = Analyte also detected in trip blank.
U = Not detected at a concentration exceeding laboratory reporting limit
ve = Estimated value. The reported range exceeds the calibration range of the analysis.
w = Petroleum product eluting in the C8-C9 range
x = The sample chromatographic pattern does not resemble the fuel standard used for quantitation.
z = Gasoline/petroleum detection result is likely elevated due to high detections of CVOCs.

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	**–**	**–**	**29**	**0.030**	**0.027**	**0.56**	**–**	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	**–**	**–**	**2.1**	**0.030**	**0.002**	**0.033**	**–**	**0.023**	**0.0033**	**0.27**
B-1	B-1-13	6/23/00	TR	ARI	13	27.0	S	–	–	–	–	–	–	–	0.0012 U	–	–	–	–	–
B-2	B-2-6.5	6/23/00	TR	ARI	6.5	33.5	S	–	–	–	–	–	–	–	0.0011 U	–	–	–	–	–
	B-2-11	6/23/00	TR	ARI	11	29.0	S	–	–	–	–	–	–	–	0.0012 U	–	–	–	–	–
	B-2-16	6/23/00	TR	ARI	16	24.0	S	–	–	–	–	–	–	–	0.0011 U	–	–	–	–	–
B-3	B-3-12	6/23/00	TR	ARI	12	28.0	S	–	–	–	–	–	–	–	0.0013 U	–	–	–	–	–
B-5	B-5-10	6/23/00	TR	ARI	10	30.0	S	–	–	–	–	–	–	–	0.0011 U	–	–	–	–	–
	B-5-11.5	6/23/00	TR	ARI	11.5	28.5	S	–	–	–	–	–	–	–	0.0012 U	–	–	–	–	–
B-6	B-6-6	6/24/00	TR	ARI	6	34.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B-6-12	6/24/00	TR	ARI	12	28.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B-6-18	6/24/00	TR	ARI	18	22.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
B-7	B-7-6	6/24/00	TR	ARI	6	34.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
B-8	B-8-4	6/24/00	TR	ARI	4	36.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B-8-8	6/24/00	TR	ARI	8	32.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
B-9	B-9-4	6/24/00	TR	ARI	4	36.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B-9-8	6/24/00	TR	ARI	8	32.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
B-10	B-10-12	6/24/00	TR	ARI	12	28.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
B-201	G-201-10	6/19/17	PES	ESC	10	29.8	S	–	–	–	–	–	–	–	0.00120 U	–	–	–	–	–
	G-201-30	6/19/17	PES	ESC	30	9.8	S	–	–	–	–	–	–	–	0.00113 U	–	–	–	–	–
	G-201-35	6/19/17	PES	ESC	35	4.8	S	–	–	–	–	–	–	–	0.00116 U	–	–	–	–	–
B-202	G-202-5	6/19/17	PES	ESC	5	34.2	S	–	–	–	–	–	–	–	0.00119 U	–	–	–	–	–
	G-202-20	6/19/17	PES	ESC	20	19.2	S	–	–	–	–	–	–	–	0.00119 U	–	–	–	–	–
	G-202-50	6/19/17	PES	ESC	50	-10.8	S	–	–	–	–	–	–	–	0.00132 U	–	–	–	–	–
B-203	G-203-5	6/20/17	PES	ESC	5	34.2	S	–	–	–	–	–	–	–	**0.0358**	–	–	–	–	–
	G-203-25	6/20/17	PES	ESC	25	14.2	S	–	–	–	–	–	–	–	0.00117 U	–	–	–	–	–
	G-203-40	6/20/17	PES	ESC	40	-0.8	S	–	–	–	–	–	–	–	**0.00561**	–	–	–	–	–
	G-203-50	6/20/17	PES	ESC	50	-10.8	S	–	–	–	–	–	–	–	0.00112 U	–	–	–	–	–
	G-203-80	6/20/17	PES	ESC	80	-40.8	S	–	–	–	–	–	–	–	0.00110 U	–	–	–	–	–
B-204	G-204-20	6/20/17	PES	ESC	20	19.8	S	–	–	–	–	–	–	–	0.00116 U	–	–	–	–	–
	G-204-40	6/20/17	PES	ESC	40	-0.2	S	–	–	–	–	–	–	–	0.00113 U	–	–	–	–	–
	G-204-45	6/20/17	PES	ESC	45	-5.2	S	–	–	–	–	–	–	–	0.00121 U	–	–	–	–	–
B-205	B-205-10	8/30/17	PES	ESC	10	30.3	S	0.564 U	0.0363 U	0.165 U	0.0289 U	**0.255**	1.21 U	0.216 U	**0.304**	0.0343 U	0.0470 U	0.0511 U	0.162 U	0.0267 U
	B-205-55	8/30/17	PES	ESC	55	-14.7	S	0.00547 U	0.000352 U	0.00160 U	0.000280 U	0.000238 U	0.0117 U	0.00209 U	0.000315 U	0.000332 U	0.000456 U	0.000495 U	0.00157 U	**0.00157**
	B-205-65	8/30/17	PES	ESC	65	-24.7	S	0.00496 U	0.000319 U	0.00145 U	0.000254 U	0.000216 U	0.0106 U	0.00190 U	0.000286 U	0.000301 U	0.000413 U	0.000449 U	0.00142 U	**0.00148**
	B-205-75	8/30/17	PES	ESC	75	-34.7	S	0.00501 U	0.000322 U	0.00147 U	0.000257 U	0.000218 U	0.0107 U	0.00192 U	0.000289 U	0.000304 U	0.000418 U	0.000454 U	0.00144 U	**0.00121**
	B-904-50	8/30/17	PES	ESC	75 (dup)	-34.7	S	0.00502 U	0.000323 U	0.00147 U	0.000257 U	0.000219 U	0.0107 U	0.00192 U	0.000290 U	0.000305 U	0.000418 U	0.000455 U	0.00144 U	**0.000877 J**
B-206	B-206-15	8/14/17	PES	ESC	15	24.1	S	0.135 U	0.00865 U	0.0394 U	0.00690 U	0.00587 U	0.288 U	0.0516 U	0.00777 U	0.00817 U	0.0112 U	0.0122 U	0.0386 U	0.00635 U
	B-206-30	8/14/17	PES	ESC	30	9.1	S	0.00537 U	0.000345 U	0.00157 U	0.000275 U	0.000234 U	**0.0177 J**	0.00205 U	0.000310 U	0.000326 U	0.000447 U	0.000486 U	0.00154 U	**0.00174**
	B-206-40	8/14/17	PES	ESC	40	-0.9	S	0.00495 U	0.000318 U	0.00145 U	0.000254 U	0.000216 U	**0.0191 J**	0.00189 U	0.000285 U	0.000300 U	0.000412 U	0.000448 U	0.00142 U	**0.00114**
	B-206-49	8/14/17	PES	ESC	49	-9.9	S	0.00533 U	0.000343 U	0.00156 U	0.000273 U	0.000232 U	0.0114 U	0.00204 U	0.000308 U	0.000324 U	0.000444 U	0.000483 U	0.00153 U	**0.00390**
	B-206-52	8/14/17	PES	ESC	52	-12.9	S	0.00511 U	0.000329 U	0.00150 U	0.000262 U	0.000223 U	0.0109 U	0.00195 U	0.000295 U	0.000310 U	0.000426 U	0.000463 U	0.00146 U	**0.000706 J**
	B-206-56	8/14/17	PES	ESC	56	-16.9	S	0.00514 U	0.000331 U	0.00150 U	0.000264 U	0.000224 U	0.0110 U	0.00197 U	0.000297 U	0.000312 U	0.000428 U	0.000466 U	0.00147 U	**0.00187**
	B-206-59	8/14/17	PES	ESC	59	-19.9	S	0.00487 U	0.000313 U	0.00143 U	0.000250 U	0.000212 U	0.0104 U	0.00186 U	0.000281 U	0.000295 U	0.000406 U	0.000441 U	0.00139 U	**0.000485 J**

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
B-206	B-206-70	8/14/17	PES	ESC	70	-30.9	S	0.00510 U	0.000328 U	0.00149 U	0.000261 U	0.000222 U	0.0109 U	0.00195 U	0.000294 U	0.000309 U	0.000425 U	0.000462 U	0.00146 U	**0.000401 J**
(continued)	B-206-80	8/14/17	PES	ESC	80	-40.9	S	0.00510 U	0.000328 U	0.00149 U	0.000262 U	0.000222 U	0.0109 U	0.00195 U	0.000294 U	0.000310 U	0.000425 U	0.000462 U	0.00146 U	**0.000339 J**
B-207	B-207-30	8/25/17	PES	ESC	30	8.5	S	0.133 U	0.00854 U	0.0389 U	0.00682 U	0.00579 U	0.284 U	0.0509 U	0.00767 U	0.00807 U	0.0111 U	0.0120 U	0.0381 U	0.00627 U
	B-207-41	8/25/17	PES	ESC	41	-2.5	S	0.00530 U	0.000341 U	0.00155 U	0.000272 U	0.000231 U	0.0113 U	0.00203 U	0.000306 U	0.000322 U	0.000442 U	0.000480 U	0.00152 U	**0.000483 J**
	B-207-49	8/25/17	PES	ESC	49	-10.5	S	0.00522 U	0.000336 U	0.00153 U	0.000268 U	0.000228 U	**0.0169 J**	0.00200 U	**0.000397 J**	0.000317 U	0.000435 U	0.000473 U	0.00149 U	**0.00478**
	B-207-55	8/25/17	PES	ESC	55	-16.5	S	0.00546 U	0.000351 U	0.00160 U	0.000280 U	0.000238 U	0.765 U	0.00209 U	0.000315 U	0.000332 U	0.000455 U	0.000495 U	0.00156 U	**0.000689 J**
	B-207-60	8/25/17	PES	ESC	60	-21.5	S	0.00498 U	0.000320 U	0.00146 U	0.000255 U	0.000217 U	0.266 U	0.00191 U	0.000287 U	0.000302 U	0.000415 U	0.000451 U	0.00143 U	**0.00159**
	B-207-70	8/25/17	PES	ESC	70	-31.5	S	0.00534 U	0.000344 U	0.00156 U	0.000274 U	0.000233 U	0.285 U	0.00204 U	0.000308 U	0.000324 U	0.000445 U	0.000484 U	0.00153 U	**0.000471 J**
	B-207-80	8/25/17	PES	ESC	80	-41.5	S	0.00516 U	0.000332 U	0.00151 U	0.000264 U	0.000225 U	1.10 U	0.00197 U	0.000297 U	0.000313 U	0.000430 U	0.000467 U	0.00148 U	**0.00102 J**
	B-207-90	8/25/17	PES	ESC	90	-51.5	S	0.129 U	0.00826 U	0.0376 U	0.00659 U	0.00560 U	0.275 U	0.0492 U	0.00742 U	0.00780 U	0.0107 U	0.0116 U	0.0368 U	0.00606 U
B-208	B-208-20	8/24/17	PES	ESC	20	18.8	S	0.00553 U	0.000356 U	0.00162 U	0.000284 U	0.000241 U	0.0118 U	0.00212 U	0.000319 U	0.000336 U	0.000461 U	0.000501 U	0.00158 U	0.000261 U
	B-208-35	8/24/17	PES	ESC	35	3.8	S	0.00509 U	0.000328 U	0.00149 U	0.000261 U	0.000222 U	**0.0123 J**	0.00195 U	0.000294 U	0.000309 U	0.000424 U	0.000461 U	0.00146 U	**0.00136**
	B-901-50	8/24/17	PES	ESC	35 (dup)	3.8	S	0.00529 U	0.000340 U	0.00155 U	0.000271 U	0.000231 U	**0.0135 J**	0.00202 U	0.000305 U	0.000321 U	0.000441 U	0.000480 U	0.00152 U	**0.000864 J**
	B-208-50	8/24/17	PES	ESC	50	-11.2	S	0.00517 U	0.000332 U	0.00151 U	0.000265 U	0.000225 U	0.0110 U	0.00198 U	0.000298 U	0.000314 U	0.000431 U	0.000468 U	0.00148 U	**0.000930 J**
	B-208-60	8/24/17	PES	ESC	60	-21.2	S	0.00521 U	0.000335 U	0.00153 U	0.000267 U	0.000227 U	**0.0227 J**	0.00199 U	**0.000440 J**	0.000316 U	0.000434 U	0.000472 U	0.00149 U	**0.00232**
	B-208-70	8/24/17	PES	ESC	70	-31.2	S	0.00523 U	0.000336 U	0.00153 U	0.000268 U	0.000228 U	**0.0144 J**	0.00200 U	0.000302 U	0.000317 U	0.000436 U	0.000473 U	0.00150 U	**0.00232**
	B-208-80	8/24/17	PES	ESC	80	-41.2	S	0.00579 U	0.000372 U	0.00169 U	0.000297 U	0.000252 U	0.0124 U	0.00221 U	0.000334 U	0.000351 U	0.000482 U	0.000525 U	0.00166 U	**0.000305 J**
B-209	B-209-20	8/25/17	PES	ESC	20	19.0	S	0.00544 U	0.000350 U	0.00159 U	0.000279 U	0.000237 U	0.0116 U	0.00208 U	0.000314 U	0.000330 U	0.000453 U	0.000493 U	0.00156 U	0.000257 U
	B-209-35	8/25/17	PES	ESC	35	4.0	S	0.00500 U	0.000321 U	0.00146 U	0.000256 U	0.000218 U	**0.0123 J**	0.00191 U	0.000288 U	0.000303 U	0.000417 U	0.000453 U	0.00143 U	**0.00190**
	B-209-50	8/25/17	PES	ESC	50	-11.0	S	0.00611 U	0.000393 U	0.00179 U	0.000313 U	0.000266 U	0.0130 U	0.00234 U	0.000352 U	0.000371 U	0.000509 U	0.000553 U	0.00175 U	**0.000410 J**
	B-209-60	8/25/17	PES	ESC	60	-21.0	S	0.00537 U	0.000346 U	0.00157 U	0.000275 U	0.000234 U	0.0115 U	0.00205 U	0.000310 U	0.000326 U	0.000448 U	0.000487 U	0.00154 U	**0.00176**
	B-209-70	8/25/17	PES	ESC	70	-31.0	S	0.00499 U	0.000321 U	0.00146 U	0.000256 U	0.000217 U	0.0107 U	0.00191 U	0.000288 U	0.000303 U	0.000416 U	0.000452 U	0.00143 U	**0.00130**
	B-209-75	8/25/17	PES	ESC	75	-36.0	S	0.00496 U	0.000319 U	0.00145 U	0.000255 U	0.000216 U	**0.0115 J**	0.00190 U	0.000286 U	0.000301 U	0.000414 U	0.000450 U	0.00142 U	**0.000870 J**
	B-209-80	8/25/17	PES	ESC	80	-41.0	S	0.00538 U	0.000346 U	0.00157 U	0.000276 U	0.000234 U	0.0115 U	0.00206 U	0.000310 U	0.000326 U	0.000448 U	0.000487 U	0.00154 U	**0.000499 J**
B-210	B-210-6	8/21/17	PES	ESC	6	33.4	S	0.00552 U	0.000355 U	0.00162 U	0.000283 U	0.000241 U	**0.0351 J**	0.00211 U	0.000318 U	0.000335 U	0.000460 U	0.000500 U	0.00158 U	**0.000327 J**
	B-210-15	8/21/17	PES	ESC	15	24.4	S	0.127 U	0.00815 U	0.0371 U	0.00650 U	0.00553 U	0.271 U	0.0485 U	0.00731 U	0.00769 U	0.0106 U	0.0115 U	0.0363 U	0.00598 U
	B-210-20	8/21/17	PES	ESC	20	19.4	S	0.00521 U	0.000335 U	0.00153 U	0.000267 U	0.000227 U	0.0111 U	0.00199 U	0.000301 U	0.000316 U	0.000434 U	0.000472 U	0.00149 U	0.000246 U
	B-210-35	8/21/17	PES	ESC	35	4.4	S	0.00540 U	0.000347 U	0.00158 U	0.000277 U	0.000235 U	0.0115 U	0.00207 U	0.000312 U	0.000328 U	0.000450 U	0.000489 U	0.00155 U	**0.000783 J**
	B-210-46	8/21/17	PES	ESC	46	-6.6	S	0.00510 U	0.000328 U	0.00149 U	0.000261 U	0.000222 U	0.0109 U	0.00195 U	0.000294 U	0.000309 U	0.000425 U	0.000462 U	0.00146 U	**0.000271 J**
	B-210-60	8/22/17	PES	ESC	60	-20.6	S	0.126 U	0.00807 U	0.0367 U	0.00644 U	0.00547 U	0.268 U	0.0481 U	0.00724 U	0.00762 U	0.0105 U	0.0114 U	0.0360 U	0.00592 U
	B-210-70	8/22/17	PES	ESC	70	-30.6	S	0.00505 U	0.000325 U	0.00148 U	0.000259 U	0.000220 U	0.0108 U	0.00193 U	0.000291 U	0.000306 U	0.000421 U	0.000457 U	0.00145 U	**0.000803 J**
	B-210-80	8/22/17	PES	ESC	80	-40.6	S	0.00517 U	0.000332 U	0.00151 U	0.000265 U	0.000225 U	0.0110 U	0.00198 U	0.000298 U	0.000314 U	0.000431 U	0.000468 U	0.00148 U	0.000244 U
	B-900-20	8/22/17	PES	ESC	80 (dup)	-40.6	S	0.00556 U	0.000357 U	0.00163 U	0.000285 U	0.000242 U	0.0119 U	0.00213 U	0.000321 U	0.000337 U	0.000463 U	0.000504 U	0.00159 U	0.000262 U
B-211	B-211-20	8/17/17	PES	ESC	20	19.8	S	0.00523 U	0.000336 U	0.00153 U	0.000268 U	0.000228 U	0.0112 U	0.00200 U	0.000301 U	0.000317 U	0.000435 U	0.000473 U	0.00150 U	0.000247 U
	B-211-35	8/17/17	PES	ESC	35	4.8	S	0.00527 U	0.000339 U	0.00154 U	0.000270 U	0.000230 U	0.0113 U	0.00201 U	0.000304 U	0.000320 U	0.000439 U	0.000477 U	0.00151 U	**0.000481 J**
	B-211-50	8/17/17	PES	ESC	50	-10.3	S	0.00506 U	0.000325 U	0.00148 U	0.000259 U	0.000221 U	**0.0114 J**	0.00194 U	0.000292 U	0.000307 U	0.000422 U	0.000458 U	0.00145 U	**0.000898 J**
	B-211-57	8/17/17	PES	ESC	57	-17.3	S	0.00552 U	0.000355 U	0.00162 U	0.000283 U	0.000241 U	0.0118 U	0.00211 U	0.000318 U	0.000335 U	0.000460 U	0.000500 U	0.00158 U	**0.00150**
	B-211-60	8/17/17	PES	ESC	60	-20.3	S	0.00540 U	0.000347 U	0.00158 U	0.000277 U	0.000235 U	0.0115 U	0.00206 U	0.000311 U	0.000327 U	0.000450 U	0.000489 U	0.00155 U	**0.00223**
	B-211-65	8/18/17	PES	ESC	65	-25.3	S	0.00528 U	0.000340 U	0.00155 U	0.000271 U	0.000230 U	0.0113 U	0.00202 U	0.000305 U	0.000321 U	0.000440 U	0.000479 U	0.00151 U	**0.00239**
	B-211-70	8/18/17	PES	ESC	70	-30.3	S	2.80 U	0.180 U	0.820 U	0.144 U	0.122 U	5.98 U	1.07 U	0.162 U	0.170 U	0.233 U	0.254 U	0.802 U	0.132 U
	B-211-80	8/18/17	PES	ESC	80	-40.3	S	0.127 U	0.00814 U	0.0370 U	0.00650 U	0.00552 U	0.271 U	0.0485 U	0.00731 U	0.00769 U	0.0106 U	0.0115 U	0.0363 U	0.00598 U
	B-211-90	8/18/17	PES	ESC	90	-50.3	S	0.136 U	0.00877 U	0.0399 U	0.00699 U	0.00594 U	0.291 U	0.0522 U	0.00787 U	0.00828 U	0.0114 U	0.0124 U	0.0391 U	0.00643 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
B-211 (continued)	B-211-100	8/18/17	PES	ESC	100	-60.3	S	0.00543 U	0.000349 U	0.00159 U	0.000279 U	0.000237 U	0.0116 U	0.00208 U	0.000313 U	0.000330 U	0.000453 U	0.000492 U	0.00156 U	0.000257 U
	B-211-110	8/18/17	PES	ESC	110	-70.3	S	0.00516 U	0.000332 U	0.00151 U	0.000265 U	0.000225 U	0.0110 U	0.00197 U	0.000298 U	0.000313 U	0.000430 U	0.000468 U	0.00148 U	0.000244 U
	B-211-120	8/21/17	PES	ESC	120	-80.3	S	0.00525 U	0.000338 U	0.00154 U	0.000269 U	0.000229 U	0.0112 U	0.00201 U	0.000303 U	0.000319 U	0.000438 U	0.000476 U	0.00150 U	0.000248 U
B-216	B-216-20	9/1/17	PES	ESC	20	31.9	S	0.00504 U	0.000324 U	0.00148 U	0.000259 U	0.000220 U	0.0108 U	0.00193 U	0.000291 U	0.000306 U	0.000420 U	0.000457 U	0.00144 U	**0.000700 J**
	B-216-40	9/1/17	PES	ESC	40	11.9	S	**0.00569 J**	0.000327 U	0.00149 U	0.000260 U	0.000221 U	**0.0269 J**	0.00194 U	0.000293 U	0.000308 U	0.000423 U	0.000460 U	0.00145 U	**0.000272 J**
	B-216-50	9/1/17	PES	ESC	50	1.9	S	0.00506 U	0.000325 U	0.00148 U	0.000259 U	0.000221 U	0.0108 U	0.00193 U	0.000292 U	0.000307 U	0.000422 U	0.000458 U	0.00145 U	**0.000310 J**
	B-216-55	9/1/17	PES	ESC	55	-3.1	S	**0.0293**	0.000339 U	**0.00727 J**	0.000270 U	0.000230 U	**0.0386 J**	0.00202 U	0.0221	0.000320 U	0.000439 U	0.000477 U	0.00151 U	**0.00288**
	B-216-65	9/1/17	PES	ESC	65	-13.1	S	0.00562 U	0.000361 U	0.00164 U	0.000288 U	0.000245 U	**0.0145 J**	0.00215 U	0.000324 U	0.000341 U	0.000468 U	0.000509 U	0.00161 U	**0.000664 J**
	B-216-85	9/1/17	PES	ESC	85	-33.1	S	**0.0107 J**	0.000363 U	0.00165 U	0.000289 U	0.000246 U	**0.0220 J**	0.00216 U	**0.000541 J**	0.000343 U	0.000470 U	0.000511 U	0.00162 U	**0.00382**
	B-216-95	9/1/17	PES	ESC	95	-43.1	S	0.00532 U	0.000342 U	0.00156 U	0.000273 U	0.000232 U	0.0114 U	0.00203 U	0.000307 U	0.000323 U	0.000443 U	0.000482 U	0.00152 U	0.000251 U
B-217	B-217-15	9/5/17	PES	ESC	15	36.8	V	0.00531 U	0.000342 U	0.00155 U	0.000272 U	0.000232 U	0.0113 U	0.00203 U	0.000306 U	0.000322 U	0.000443 U	0.000481 U	0.00152 U	**0.000952 J**
	B-217-25	9/5/17	PES	ESC	25	26.8	S	0.00519 U	0.000334 U	0.00152 U	0.000266 U	0.000226 U	0.0111 U	0.00198 U	0.000299 U	0.000315 U	0.000432 U	0.000470 U	0.00149 U	0.000245 U
	B-217-35	9/5/17	PES	ESC	35	16.8	S	0.00537 U	0.000345 U	0.00157 U	0.000275 U	0.000234 U	0.0115 U	0.00205 U	0.000310 U	0.000326 U	0.000448 U	0.000487 U	0.00154 U	0.000254 U
	B-217-42	9/5/17	PES	ESC	42	9.8	S	0.00535 U	0.000344 U	0.00157 U	0.000274 U	0.000233 U	0.0114 U	0.00205 U	0.000309 U	0.000325 U	0.000446 U	0.000485 U	0.00153 U	**0.00112 J**
	B-217-55	9/5/17	PES	ESC	55	-3.2	S	**0.0155**	0.000349 U	0.00159 U	0.000279 U	0.000237 U	**0.0228 J**	0.00208 U	0.000313 U	0.000330 U	0.000453 U	0.000492 U	0.00156 U	**0.000321 J**
	B-217-65	9/5/17	PES	ESC	65	-13.2	S	0.00539 U	0.000347 U	0.00158 U	0.000276 U	0.000235 U	0.0115 U	0.00206 U	0.000311 U	0.000327 U	0.000449 U	0.000488 U	0.00154 U	**0.00111 J**
	B-217-75	9/5/17	PES	ESC	75	-23.2	S	0.00561 U	0.000361 U	0.00164 U	0.000287 U	0.000244 U	0.0120 U	0.00214 U	0.000323 U	0.000340 U	0.000467 U	0.000508 U	0.00161 U	**0.000452 J**
	B-217-85	9/6/17	PES	ESC	85	-33.2	S	0.00533 U	0.000343 U	0.00156 U	0.000273 U	0.000232 U	0.0114 U	0.00204 U	0.000308 U	0.000324 U	0.000444 U	0.000483 U	0.00153 U	**0.000537 J**
	B-217-95	9/6/17	PES	ESC	95	-43.2	S	0.00566 U	0.000364 U	0.00166 U	0.000290 U	0.000247 U	0.0121 U	0.00216 U	0.000326 U	0.000343 U	0.000471 U	0.000512 U	0.00162 U	0.000267 U
	B-217-106	9/6/17	PES	ESC	106	-54.2	S	0.574 U	0.0369 U	0.168 U	0.0294 U	0.0250 U	1.23 U	0.219 U	0.0331 U	0.0348 U	0.0478 U	0.0520 U	0.164 U	0.0271 U
	B-217-115	9/6/17	PES	ESC	115	-63.2	S	0.00540 U	0.000348 U	0.00158 U	0.000277 U	0.000236 U	0.0115 U	0.00207 U	0.000312 U	0.000328 U	0.000450 U	0.000490 U	0.00155 U	0.000255 U
B-218	B-218-12.5	9/19/17	PES	ESC	12.5	25.6	S	0.00533 U	0.000343 U	0.00156 U	0.000273 U	0.000232 U	0.0114 U	0.00204 U	0.000307 U	0.000323 U	0.000444 U	0.000483 U	0.00153 U	0.000252 U
	B-218-19	9/19/17	PES	ESC	19	19.1	S	0.00531 U	0.000342 U	0.00155 U	0.000272 U	0.000232 U	0.0114 U	0.00203 U	0.000306 U	0.000322 U	0.000443 U	0.000481 U	0.00152 U	0.000251 U
	B-218-25	9/19/17	PES	ESC	25	13.1	S	0.00542 U	0.000349 U	0.00159 U	0.000278 U	0.000236 U	0.0116 U	0.00207 U	0.000313 U	0.000329 U	0.000452 U	0.000491 U	0.00155 U	0.000256 U
	B-218-40	9/19/17	PES	ESC	40	-1.9	S	0.288 U	0.0184 U	0.0842 U	0.0147 U	0.0125 U	0.615 U	0.110 U	0.0166 U	0.0175 U	0.0239 U	0.0260 U	0.0823 U	0.0136 U
	B-218-50	9/19/17	PES	ESC	50	-11.9	S	0.00499 U	0.000321 U	0.00146 U	0.000256 U	0.000218 U	**0.0173 J**	0.00191 U	0.000288 U	0.000303 U	0.000416 U	0.000452 U	0.00143 U	**0.00186 J**
	B-913-70	9/19/17	PES	ESC	50 (dup)	-11.9	S	0.00497 U	0.000320 U	0.00145 U	0.000255 U	0.000217 U	0.0106 U	0.00190 U	0.000287 U	0.000302 U	0.000414 U	0.000450 U	0.00142 U	**0.00221 J**
B-219	B-219-42	8/28/17	PES	ESC	42	-2.2	S	**0.0125**	0.000328 U	0.00149 U	0.000261 U	0.000222 U	**0.0356 J**	0.00195 U	0.000294 U	0.000309 U	0.000425 U	0.000462 U	0.00146 U	**0.000984 J**
	B-219-50	8/28/17	PES	ESC	50	-10.2	S	**0.169**	0.000356 U	**0.00471 J**	0.000284 U	0.000242 U	**0.134 J**	0.00212 U	0.000320 U	0.000336 U	0.000462 U	0.000502 U	0.00159 U	**0.00184 J**
	B-219-60	8/28/17	PES	ESC	60	-20.2	S	0.00504 U	0.000324 U	0.00147 U	0.000258 U	0.000220 U	**0.0146 J**	0.00193 U	0.000291 U	0.000306 U	0.000420 U	0.000456 U	0.00144 U	**0.000573 J**
	B-219-70	8/28/17	PES	ESC	70	-30.2	S	**0.0183**	0.000343 U	0.00156 U	0.000274 U	0.000233 U	**0.0237 J**	0.00204 U	0.000308 U	0.000324 U	0.000445 U	0.000484 U	0.00153 U	**0.00345 J**
	B-219-80	8/28/17	PES	ESC	80	-40.2	S	0.00508 U	0.000327 U	0.00149 U	0.000261 U	0.000222 U	0.0109 U	0.00194 U	0.000293 U	0.000308 U	0.000424 U	0.000461 U	0.00146 U	**0.000358 J**
B-220	B-220-15	9/20/17	PES	ESC	15	23.9	S	0.00532 U	0.000342 U	0.00156 U	0.000273 U	0.000232 U	0.0114 U	0.00204 U	0.000307 U	0.000323 U	0.000443 U	0.000482 U	0.00152 U	0.000251 U
	B-220-29	9/20/17	PES	ESC	29	9.9	S	**0.00592 J**	0.000350 U	0.00159 U	0.000279 U	0.000237 U	**0.0387 J**	0.00208 U	0.000314 U	0.000330 U	0.000453 U	0.000493 U	0.00156 U	**0.000360 J**
	B-220-32	9/20/17	PES	ESC	32	6.9	S	0.00534 U	0.000343 U	0.00156 U	0.000274 U	0.000233 U	0.0114 U	0.00204 U	0.000308 U	0.000324 U	0.000445 U	0.000484 U	0.00153 U	0.000252 U
	B-220-40	9/20/17	PES	ESC	40	-1.1	S	0.00520 U	0.000334 U	0.00152 U	0.000266 U	0.000226 U	0.0111 U	0.00199 U	0.000300 U	0.000315 U	0.000433 U	0.000471 U	0.00149 U	**0.00104 J**
	B-220-50	9/20/17	PES	ESC	50	-11.1	S	0.00503 U	0.000324 U	0.00147 U	0.000258 U	0.000219 U	**0.0133 J**	0.00193 U	0.000290 U	0.000305 U	0.000419 U	0.000456 U	0.00144 U	**0.00188 J**
	B-914-75	9/20/17	PES	ESC	50 (dup)	-11.1	S	0.00503 U	0.000324 U	0.00147 U	0.000258 U	0.000219 U	**0.0204 J**	0.00193 U	0.000290 U	0.000305 U	0.000419 U	0.000456 U	0.00144 U	**0.00177 J**
B-221	B-221-16	9/20/17	PES	ESC	16	23.0	S	0.137 U	0.00881 U	0.0401 U	0.00703 U	0.00598 U	0.293 U	0.0525 U	0.00791 U	0.00832 U	0.0114 U	0.0124 U	0.0393 U	0.00647 U
	B-221-22	9/20/17	PES	ESC	22	17.0	S	5.38 U	0.346 U	1.58 U	0.276 U	0.235 U	11.5 U	2.06 U	0.311 U	0.327 U	0.449 U	0.488 U	1.54 U	0.254 U
	B-221-33	9/20/17	PES	ESC	33	6.0	S	5.24 U	0.337 U	1.53 U	0.269 U	0.228 U	11.2 U	2.00 U	0.302 U	0.318 U	0.437 U	0.475 U	1.50 U	0.247 U
	B-221-37	9/20/17	PES	ESC	37	2.0	S	1.10 U	0.0708 U	0.322 U	0.0564 U	0.0480 U	2.35 U	0.421 U	0.0635 U	0.0668 U	0.0917 U	0.0997 U	0.315 U	0.0520 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
B-221 (continued)	B-915-80	9/20/17	PES	ESC	37 (dup)	2.0	S	0.536 U	0.0345 U	0.157 U	0.0275 U	0.0234 U	1.15 U	0.205 U	0.0309 U	0.0325 U	0.0447 U	0.0486 U	0.154 U	0.0253 U
	B-221-45	9/20/17	PES	ESC	45	-6.0	S	51.3 U	3.30 U	15.0 U	2.63 U	2.24 U	110 U	19.6 U	2.96 U	3.11 U	4.28 U	4.65 U	14.7 U	2.42 U
	B-221-50	9/20/17	PES	ESC	50	-11.0	S	2.54 U	0.163 U	0.745 U	0.131 U	0.111 U	5.44 U	0.973 U	0.147 U	0.154 U	0.212 U	0.231 U	0.729 U	0.120 U
	B-221-60	9/20/17	PES	ESC	60	-21.0	S	2.59 U	0.166 U	0.757 U	0.133 U	0.113 U	5.53 U	0.989 U	0.149 U	0.157 U	0.215 U	0.234 U	0.740 U	0.122 U
	B-221-70	9/21/17	PES	ESC	70	-31.0	S	0.00517 U	0.000332 U	0.00151 U	0.000265 U	0.000225 U	0.0110 U	0.00198 U	0.000298 U	0.000313 U	0.000431 U	0.000468 U	0.00148 U	**0.000317 J**
B-222	B-222-17	9/21/17	PES	ESC	17	22.2	S	0.00531 U	0.000341 U	0.00155 U	0.000272 U	0.000231 U	0.0113 U	0.00203 U	0.000306 U	0.000322 U	0.000442 U	0.000481 U	0.00152 U	**0.000299 J**
	B-222-25	9/21/17	PES	ESC	25	14.2	S	0.00541 U	0.000348 U	0.00158 U	0.000277 U	0.000236 U	0.0116 U	0.00207 U	0.000312 U	0.000328 U	0.000451 U	0.000490 U	0.00155 U	0.000255 U
	B-222-34	9/21/17	PES	ESC	34	5.2	S	**0.00629 J**	0.000337 U	0.00153 U	0.000269 U	0.000229 U	0.0112 U	0.00201 U	0.000303 U	0.000318 U	0.000437 U	0.000475 U	0.00150 U	0.000248 U
	B-222-42	9/21/17	PES	ESC	42	-2.8	S	0.00580 U	0.000373 U	0.00170 U	0.000298 U	0.000253 U	0.0124 U	0.00222 U	**0.000387 J**	0.000352 U	0.000484 U	0.000526 U	0.00166 U	**0.00400**
	B-222-50	9/21/17	PES	ESC	50	-10.8	S	0.251 U	0.0161 U	0.0735 U	0.0129 U	0.0109 U	0.536 U	0.0960 U	0.0145 U	0.0152 U	0.0209 U	0.0227 U	0.0719 U	0.0118 U
	B-916-30	9/21/17	PES	ESC	50 (dup)	-10.8	S	0.00496 U	0.000319 U	0.00145 U	0.000255 U	0.000216 U	0.0106 U	0.00190 U	0.000286 U	0.000301 U	0.000414 U	0.000450 U	0.00142 U	**0.00171**
B-223	B-223-16	9/21/17	PES	ESC	16	23.1	S	1.11 U	0.0711 U	0.324 U	0.0567 U	0.0482 U	2.36 U	0.423 U	0.0638 U	0.0671 U	0.0922 U	0.100 U	0.317 U	0.0522 U
	B-223-22	9/21/17	PES	ESC	22	17.1	S	1.07 U	0.0687 U	0.313 U	0.0548 U	0.0466 U	2.28 U	0.409 U	0.0617 U	0.0649 U	0.0891 U	0.0968 U	0.306 U	0.0505 U
	B-223-30	9/21/17	PES	ESC	30	9.1	S	129 U	8.28 U	37.7 U	6.61 U	5.61 U	275 U	49.3 U	7.43 U	7.82 U	10.7 U	11.7 U	36.9 U	6.08 U
	B-223-39	9/21/17	PES	ESC	39	0.1	S	0.00533 U	0.000343 U	0.00156 U	0.000273 U	0.000232 U	0.0114 U	0.00204 U	0.000308 U	0.000323 U	0.000444 U	0.000483 U	0.00153 U	0.000252 U
	B-223-47	9/21/17	PES	ESC	47	-7.9	S	0.00543 U	0.000349 U	0.00159 U	0.000279 U	0.000237 U	**0.0138 J**	0.00208 U	0.000314 U	0.000330 U	0.000453 U	0.000492 U	0.00156 U	**0.00113 J**
	B-917-57	9/21/17	PES	ESC	47 (dup)	-7.9	S	0.00503 U	0.000323 U	0.00147 U	0.000258 U	0.000219 U	0.0107 U	0.00192 U	0.000290 U	0.000305 U	0.000419 U	0.000456 U	0.00144 U	**0.00100 J**
B-224	B-224-6	11/27/17	PES	ESC	6	33.1	S	0.00506 U	0.000326 U	0.00148 U	0.000260 U	0.000221 U	**0.0135 J**	0.00194 U	0.000292 U	0.000307 U	0.000422 U	0.000459 U	0.00145 U	0.000239 U
	B-224-11	11/27/17	PES	ESC	11	28.1	S	0.0125 U	0.000805 U	0.00366 U	0.000642 U	**0.00418**	**0.0995 J**	0.00479 U	0.000722 U	0.000758 U	0.00104 U	0.00113 U	0.00357 U	**0.0240**
	B-224-16	11/27/17	PES	ESC	16	23.1	S	0.00566 U	0.000364 U	0.00166 U	0.000290 U	0.000247 U	0.0121 U	0.00216 U	0.000326 U	0.000343 U	0.000472 U	0.000513 U	0.00162 U	0.000267 U
	B-224-21.5	11/27/17	PES	ESC	21.5	17.6	S	0.00543 U	0.000349 U	0.00159 U	0.000279 U	0.000237 U	0.0116 U	0.00208 U	0.000313 U	0.000330 U	0.000453 U	0.000492 U	0.00156 U	0.000257 U
	B-224-26	11/27/17	PES	ESC	26	13.1	S	0.00619 U	0.000398 U	0.00181 U	0.000318 U	0.000269 U	0.0132 U	0.00236 U	0.000357 U	0.000376 U	0.000516 U	0.000560 U	0.00177 U	0.000292 U
	B-224-31	11/27/17	PES	ESC	31	8.1	S	0.00547 U	0.000352 U	0.00160 U	0.000280 U	0.000238 U	0.0117 U	0.00209 U	0.000316 U	0.000332 U	0.000456 U	0.000496 U	0.00157 U	0.000259 U
	B-224-36	11/27/17	PES	ESC	36	3.1	S	0.00520 U	0.000334 U	0.00152 U	0.000267 U	0.000227 U	0.0111 U	0.00199 U	0.000300 U	0.000315 U	0.000433 U	0.000471 U	0.00149 U	0.000245 U
	B-224-60.5	11/27/17	PES	ESC	60.5	-21.4	S	0.00756 U	0.000486 U	0.00221 U	0.000389 U	0.000330 U	0.0162 U	0.00290 U	0.000436 U	0.000460 U	0.000631 U	0.000685 U	0.00216 U	**0.000609 J**
B-225	B-225-5	11/27/17	PES	ESC	5	34.1	S	0.00508 U	0.000326 U	0.00149 U	0.000260 U	0.000221 U	0.0108 U	0.00194 U	0.000293 U	0.000308 U	0.000423 U	0.000460 U	0.00145 U	0.000240 U
	B-225-11	11/27/17	PES	ESC	11	28.1	S	0.00547 U	0.000352 U	0.00160 U	0.000281 U	0.000239 U	0.0117 U	0.00209 U	0.000316 U	0.000332 U	0.000456 U	0.000496 U	0.00157 U	0.000259 U
	B-225-16	11/27/17	PES	ESC	16	23.1	S	0.138 U	0.00885 U	0.0402 U	0.00706 U	0.00600 U	0.294 U	0.0527 U	0.00794 U	0.00835 U	0.0115 U	0.0125 U	0.0394 U	0.00649 U
	B-225-21	11/27/17	PES	ESC	21	18.1	S	0.133 U	0.00855 U	0.0389 U	0.00682 U	0.00580 U	0.284 U	0.0509 U	0.00767 U	0.00807 U	0.0111 U	0.0121 U	0.0381 U	0.00628 U
	B-225-26	11/27/17	PES	ESC	26	13.1	S	0.00550 U	0.000354 U	0.00161 U	0.000282 U	0.000240 U	0.0118 U	0.00210 U	0.000317 U	0.000334 U	0.000458 U	0.000498 U	0.00157 U	0.000260 U
	B-225-31	11/27/17	PES	ESC	31	8.1	S	0.00535 U	0.000344 U	0.00157 U	0.000274 U	0.000233 U	0.0114 U	0.00205 U	0.000309 U	0.000325 U	0.000446 U	0.000485 U	0.00153 U	0.000253 U
	B-225-36	11/27/17	PES	ESC	36	3.1	S	0.00576 U	0.000371 U	0.00169 U	0.000296 U	0.000251 U	0.0123 U	0.00220 U	0.000333 U	0.000350 U	0.000480 U	0.000522 U	0.00165 U	0.000272 U
B-226	B-226-6	11/28/17	PES	ESC	6	33.1	S	0.00564 U	0.000363 U	0.00165 U	0.000289 U	0.000246 U	0.0120 U	0.00216 U	0.000325 U	0.000342 U	0.000470 U	0.000511 U	0.00161 U	0.000266 U
	B-226-11	11/28/17	PES	ESC	11	28.1	S	0.00531 U	0.000341 U	0.00155 U	0.000272 U	**0.00241**	**0.0132 J**	0.00203 U	0.000306 U	0.000322 U	0.000442 U	0.000481 U	0.00152 U	**0.00146**
	B-226-16	11/28/17	PES	ESC	16	23.1	S	0.131 U	0.00844 U	0.0384 U	0.00673 U	0.00572 U	0.280 U	0.0503 U	0.00757 U	0.00797 U	0.0109 U	0.0119 U	0.0376 U	0.00619 U
	B-920-35	11/28/17	PES	ESC	16 (dup)	23.1	S	0.00518 U	0.000333 U	0.00152 U	0.000266 U	0.000226 U	0.0111 U	0.00198 U	0.000299 U	0.000314 U	0.000431 U	0.000469 U	0.00148 U	**0.000710 J**
	B-226-21	11/28/17	PES	ESC	21	18.1	S	0.00533 U	0.000343 U	0.00156 U	0.000273 U	0.000232 U	0.0114 U	0.00204 U	0.000308 U	0.000323 U	0.000444 U	0.000483 U	0.00153 U	0.000252 U
	B-226-31.5	11/28/17	PES	ESC	31.5	7.6	S	0.00498 U	0.000320 U	0.00146 U	0.000256 U	0.000217 U	0.0106 U	0.00191 U	0.000287 U	0.000302 U	0.000415 U	0.000451 U	0.00143 U	**0.000372 J**
	B-226-40	11/28/17	PES	ESC	40	-0.9	S	0.00536 U	0.000345 U	0.00157 U	0.000275 U	0.000234 U	0.0114 U	0.00205 U	0.000309 U	0.000325 U	0.000446 U	0.000485 U	0.00153 U	**0.000491 J**
B-227	B-227-6	11/28/17	PES	ESC	6	33.1	S	0.00534 U	0.000344 U	0.00156 U	0.000274 U	0.000233 U	0.0114 U	0.00204 U	0.000308 U	0.000324 U	0.000445 U	0.000484 U	0.00153 U	0.000252 U
	B-227-11	11/28/17	PES	ESC	11	28.1	S	0.00504 U	0.000324 U	0.00148 U	0.000259 U	0.000220 U	0.0108 U	0.00193 U	0.000291 U	0.000306 U	0.000420 U	0.000457 U	0.00144 U	**0.000628 J**
	B-227-16	11/28/17	PES	ESC	16	23.1	S	0.00536 U	0.000345 U	0.00157 U	0.000275 U	0.000234 U	0.0115 U	0.00205 U	0.000309 U	0.000325 U	0.000447 U	0.000486 U	0.00154 U	0.000253 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
B-227 (continued)	B-227-21	11/28/17	PES	ESC	21	18.1	S	0.00543 U	0.000349 U	0.00159 U	0.000279 U	0.000237 U	0.0116 U	0.00208 U	0.000313 U	0.000330 U	0.000453 U	0.000492 U	0.00156 U	0.000257 U
	B-227-26	11/28/17	PES	ESC	26	13.1	S	0.00545 U	0.000351 U	0.00160 U	0.000280 U	0.000238 U	0.0116 U	0.00209 U	0.000315 U	0.000331 U	0.000454 U	0.000494 U	0.00156 U	0.000257 U
	B-227-31	11/28/17	PES	ESC	31	8.1	S	0.00561 U	0.000361 U	0.00164 U	0.000288 U	0.000245 U	0.0120 U	0.00215 U	0.000324 U	0.000341 U	0.000468 U	0.000509 U	0.00161 U	0.000265 U
	B-227-36	11/28/17	PES	ESC	36	3.1	S	0.00537 U	0.000345 U	0.00157 U	0.000275 U	0.000234 U	0.0115 U	0.00205 U	0.000310 U	0.000326 U	0.000448 U	0.000487 U	0.00154 U	0.000254 U
B-228	B-228-6	11/29/17	PES	ESC	6	33.1	S	0.00572 U	0.000368 U	0.00168 U	0.000294 U	0.000250 U	0.0122 U	0.00219 U	0.000330 U	0.000347 U	0.000477 U	0.000519 U	0.00164 U	0.000270 U
	B-228-11	11/29/17	PES	ESC	11	28.1	S	0.00520 U	0.000335 U	0.00152 U	0.000267 U	0.000227 U	0.0111 U	0.00199 U	0.000300 U	0.000316 U	0.000433 U	0.000471 U	0.00149 U	0.000246 U
	B-228-16	11/29/17	PES	ESC	16	23.1	S	0.00504 U	0.000324 U	0.00148 U	0.000259 U	0.000220 U	0.0108 U	0.00193 U	0.000291 U	0.000306 U	0.000420 U	0.000457 U	0.00144 U	0.000238 U
	B-921-22	11/29/17	PES	ESC	16 (dup)	23.1	S	0.00538 U	0.000346 U	0.00157 U	0.000276 U	0.000234 U	0.0115 U	0.00206 U	0.000310 U	0.000326 U	0.000448 U	0.000487 U	0.00154 U	0.000254 U
	B-228-21	11/29/17	PES	ESC	21	18.1	S	0.00529 U	0.000340 U	0.00155 U	0.000271 U	0.000231 U	0.0113 U	0.00202 U	0.000305 U	0.000321 U	0.000441 U	0.000479 U	0.00152 U	0.000250 U
	B-228-26	11/29/17	PES	ESC	26	13.1	S	0.00504 U	0.000324 U	0.00147 U	0.000258 U	0.000220 U	0.0108 U	0.00193 U	0.000291 U	0.000306 U	0.000420 U	0.000456 U	0.00144 U	0.000238 U
	B-228-31	11/29/17	PES	ESC	31	8.1	S	0.00520 U	0.000334 U	0.00152 U	0.000266 U	0.000227 U	0.0111 U	0.00199 U	0.000300 U	0.000315 U	0.000433 U	0.000471 U	0.00149 U	0.000245 U
	B-228-36	11/29/17	PES	ESC	36	3.1	S	0.00529 U	0.000340 U	0.00155 U	0.000271 U	0.000230 U	0.0113 U	0.00202 U	0.000305 U	0.000321 U	0.000441 U	0.000479 U	0.00151 U	0.000250 U
B-229	B-229-6	11/29/17	PES	ESC	6	33.1	S	0.00685 U	0.000440 U	0.00200 U	0.000351 U	0.000299 U	0.0146 U	0.00262 U	0.000395 U	0.000416 U	0.000571 U	0.000620 U	0.00196 U	0.000323 U
	B-229-11	11/29/17	PES	ESC	11	28.1	S	0.00664 U	0.000427 U	0.00194 U	0.000341 U	0.000290 U	0.0142 U	0.00254 U	0.000383 U	0.000403 U	0.000554 U	0.000602 U	0.00190 U	**0.00210**
	B-229-16	11/29/17	PES	ESC	16	23.1	S	0.00558 U	0.000359 U	0.00163 U	0.000286 U	0.000243 U	0.0119 U	0.00213 U	**0.000388 J**	0.000339 U	0.000465 U	0.000505 U	0.00160 U	**0.000547 J**
	B-229-25	11/29/17	PES	ESC	25	14.1	S	0.00513 U	0.000330 U	0.00150 U	0.000263 U	0.000224 U	0.0110 U	0.00196 U	0.000296 U	0.000311 U	0.000428 U	0.000465 U	0.00147 U	0.000242 U
	B-229-31	11/29/17	PES	ESC	31	8.1	S	0.00564 U	0.000363 U	0.00165 U	0.000289 U	0.000246 U	0.0121 U	0.00216 U	0.000326 U	0.000343 U	0.000470 U	0.000511 U	0.00162 U	0.000267 U
	B-229-36	11/29/17	PES	ESC	36	3.1	S	0.00515 U	0.000331 U	0.00151 U	0.000264 U	0.000224 U	0.0110 U	0.00197 U	0.000297 U	0.000312 U	0.000429 U	0.000466 U	0.00147 U	0.000243 U
	B-229-41	11/29/17	PES	ESC	41	-1.9	S	0.00545 U	0.000350 U	0.00160 U	0.000279 U	0.000238 U	0.0116 U	0.00208 U	0.000314 U	0.000331 U	0.000454 U	0.000494 U	0.00156 U	0.000257 U
	B-229-45	11/29/17	PES	ESC	45	-5.9	S	0.00560 U	0.000360 U	0.00164 U	0.000287 U	0.000244 U	0.0120 U	0.00214 U	0.000323 U	0.000340 U	0.000466 U	0.000507 U	0.00160 U	**0.000547 J**
B-230	B-230-6	11/30/17	PES	ESC	6	33.1	S	0.00494 U	0.000318 U	0.00145 U	0.000253 U	0.000215 U	0.0105 U	0.00189 U	0.000285 U	0.000300 U	0.000411 U	0.000447 U	0.00141 U	0.000233 U
	B-230-11	11/30/17	PES	ESC	11	28.1	S	**0.00714 J**	0.000329 U	0.00150 U	0.000262 U	0.000223 U	**0.0239 J**	0.00196 U	**0.000348 J**	0.000310 U	0.000426 U	0.000463 U	0.00146 U	0.000241 U
	B-230-16	11/30/17	PES	ESC	16	23.1	S	1.30 U	0.0837 U	0.381 U	0.0668 U	0.0568 U	2.78 U	0.499 U	0.0751 U	0.0790 U	0.109 U	0.118 U	0.373 U	0.0614 U
	B-230-21	11/30/17	PES	ESC	21	18.1	S	11.2 U	0.719 U	3.27 U	0.573 U	0.487 U	23.9 U	4.27 U	0.645 U	0.678 U	0.931 U	1.01 U	3.20 U	0.528 U
	B-922-15	11/30/17	PES	ESC	21 (dup)	18.1	S	5.65 U	0.363 U	1.65 U	0.290 U	0.246 U	12.1 U	2.16 U	0.326 U	0.343 U	0.471 U	0.512 U	1.62 U	0.267 U
	B-230-26	11/30/17	PES	ESC	26	13.1	S	14.0 U	0.901 U	4.10 U	0.719 U	0.611 U	30.0 U	5.37 U	0.809 U	0.851 U	1.17 U	1.27 U	4.01 U	0.662 U
	B-230-31	11/30/17	PES	ESC	31	8.1	S	5.82 U	0.374 U	1.70 U	0.299 U	0.254 U	12.4 U	2.23 U	0.336 U	0.353 U	0.485 U	0.527 U	1.67 U	0.275 U
	B-230-35	11/30/17	PES	ESC	35	4.1	S	0.845 U	0.0543 U	0.248 U	0.0433 U	0.0368 U	1.81 U	0.324 U	0.0488 U	0.0512 U	0.0705 U	0.0766 U	0.242 U	0.0399 U
	B-230-55	11/30/17	PES	ESC	55	-15.9	S	1.40 U	0.0903 U	0.410 U	0.0720 U	0.0612 U	3.00 U	0.538 U	0.0810 U	0.0852 U	0.117 U	0.127 U	0.402 U	0.0663 U
B-231	B-231-6	11/30/17	PES	ESC	6	33.1	S	0.00577 U	0.000371 U	0.00169 U	0.000296 U	0.000252 U	0.0123 U	0.00221 U	0.000333 U	0.000350 U	0.000481 U	0.000523 U	0.00165 U	0.000273 U
	B-231-11	11/30/17	PES	ESC	11	28.1	S	0.00552 U	0.000355 U	0.00161 U	0.000283 U	0.000240 U	0.0118 U	0.00211 U	0.000318 U	0.000335 U	0.000460 U	0.000500 U	0.00158 U	0.000260 U
	B-231-16	11/30/17	PES	ESC	16	23.1	S	0.131 U	0.00843 U	0.0383 U	0.00672 U	0.00571 U	0.280 U	0.0502 U	0.00756 U	0.00796 U	0.0109 U	0.0119 U	0.0375 U	0.00618 U
	B-231-21	11/30/17	PES	ESC	21	18.1	S	0.310 U	0.0200 U	0.0906 U	0.0159 U	0.0135 U	0.661 U	0.118 U	0.0179 U	0.0188 U	0.0258 U	0.0281 U	0.0886 U	0.0146 U
	B-231-26	11/30/17	PES	ESC	26	13.1	S	**0.00630 J**	0.000350 U	0.00159 U	0.000279 U	0.000237 U	0.0116 U	0.00208 U	0.000314 U	0.000330 U	0.000453 U	0.000492 U	0.00156 U	**0.000687 J**
	B-231-30	11/30/17	PES	ESC	30	9.1	S	0.00528 U	0.000340 U	0.00155 U	0.000271 U	0.000230 U	0.0113 U	0.00202 U	0.000305 U	0.000320 U	0.000440 U	0.000478 U	0.00151 U	0.000249 U
	B-231-36	11/30/17	PES	ESC	36	3.1	S	**0.00640 J**	0.000341 U	0.00155 U	0.000272 U	0.000231 U	0.0113 U	0.00203 U	0.000306 U	0.000322 U	0.000442 U	0.000481 U	0.00152 U	**0.000409 J**
B-232	B-232-6	12/1/17	PES	ESC	6	33.1	S	**0.00951 J**	0.000355 U	0.00162 U	0.000283 U	**0.00115 J**	**0.0263 J**	0.00211 U	**0.000380 J**	0.000335 U	0.000460 U	0.000501 U	0.00158 U	**0.00105 J**
	B-232-11	12/1/17	PES	ESC	11	28.1	S	0.00623 U	0.000400 U	0.00182 U	0.000319 U	**0.000373 J**	**0.0206 J**	0.00238 U	**0.000630 J+**	0.000378 U	0.000519 U	0.000564 U	0.00178 U	**0.00310**
	B-232-16	12/1/17	PES	ESC	16	23.1	S	0.00548 U	0.000352 U	0.00160 U	0.000281 U	0.000239 U	0.0117 U	0.00210 U	0.000316 U	0.000333 U	0.000457 U	0.000496 U	0.00157 U	0.000259 U
	B-232-21	12/1/17	PES	ESC	21	18.1	S	0.00524 U	0.000337 U	0.00153 U	0.000269 U	0.000228 U	0.0112 U	0.00200 U	0.000302 U	0.000318 U	0.000436 U	0.000475 U	0.00150 U	0.000247 U
	B-232-26	12/1/17	PES	ESC	26	13.1	S	0.174 U	0.0112 U	0.0512 U	0.00897 U	0.00763 U	0.374 U	0.0669 U	0.0101 U	0.0106 U	0.0146 U	0.0159 U	0.0501 U	0.00826 U
	B-232-31	12/1/17	PES	ESC	31	8.1	S	0.00528 U	0.000340 U	0.00155 U	0.000271 U	0.000230 U	0.0113 U	0.00202 U	0.000305 U	0.000321 U	0.000440 U	0.000479 U	0.00151 U	0.000250 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
B-232 (continued)	B-232-36	12/1/17	PES	ESC	36	3.1	S	0.00555 U	0.000357 U	0.00162 U	0.000284 U	0.000242 U	0.0119 U	0.00212 U	0.000320 U	0.000337 U	0.000462 U	0.000503 U	0.00159 U	0.000262 U
B-233	B-233-6	12/1/17	PES	ESC	6	29.5	S	0.00505 U	0.000325 U	0.00148 U	0.000259 U	0.000220 U	0.0108 U	0.00193 U	0.000291 U	0.000306 U	0.000421 U	0.000458 U	0.00145 U	0.000238 U
	B-233-11	12/1/17	PES	ESC	11	24.5	S	0.0130 U	0.000839 U	0.00383 U	0.000669 U	**0.00104 J**	**0.104 J**	0.00499 U	**0.00167 J+**	0.000792 U	0.00109 U	0.00118 U	0.00374 U	**0.0211**
	B-233-16	12/1/17	PES	ESC	16	19.5	S	0.00660 U	0.000425 U	0.00194 U	0.000338 U	0.000288 U	0.0141 U	0.00252 U	**0.000420 J**	0.000401 U	0.000550 U	0.000598 U	0.00189 U	0.000312 U
	B-233-21	12/1/17	PES	ESC	21	14.5	S	0.133 U	0.00858 U	0.0390 U	0.00685 U	0.00582 U	0.285 U	0.0511 U	**0.00770**	0.00810 U	0.0111 U	0.0121 U	0.0382 U	0.00630 U
	B-233-26	12/1/17	PES	ESC	26	9.5	S	0.280 U	0.0179 U	0.0819 U	0.0143 U	0.0122 U	0.598 U	0.107 U	0.0161 U	0.0170 U	0.0233 U	0.0253 U	0.0801 U	0.0131 U
	B-233-31	12/1/17	PES	ESC	31	4.5	S	0.145 U	0.00935 U	0.0425 U	0.00746 U	0.00634 U	0.311 U	0.0557 U	0.00839 U	0.00883 U	0.0121 U	0.0132 U	0.0417 U	0.00686 U
	B-233-36	12/1/17	PES	ESC	36	-0.5	S	0.132 U	0.00846 U	0.0385 U	0.00675 U	0.00574 U	0.281 U	0.0504 U	0.00760 U	0.00799 U	0.0110 U	0.0119 U	0.0377 U	0.00621 U
B-234	B-234-11	12/4/17	PES	ESC	11	40.8	V	0.00544 U	0.000350 U	0.00159 U	0.000279 U	0.000237 U	0.0116 U	0.00208 U	0.000314 U	0.000330 U	0.000453 U	0.000493 U	0.00156 U	0.000257 U
	B-234-30	12/4/17	PES	ESC	30	21.8	S	0.00495 U	0.000319 U	0.00145 U	0.000254 U	0.000216 U	0.0106 U	0.00189 U	0.000286 U	0.000301 U	0.000413 U	0.000449 U	0.00142 U	0.000234 U
B-234A	B-234A-35	12/4/17	PES	ESC	35	16.8	S	0.00537 U	0.000345 U	0.00157 U	0.000275 U	0.000234 U	0.0115 U	0.00205 U	0.000310 U	0.000326 U	0.000447 U	0.000486 U	0.00154 U	0.000254 U
	B-234A-40	12/4/17	PES	ESC	40	11.8	S	0.00504 U	0.000324 U	0.00147 U	0.000258 U	0.000220 U	0.0108 U	0.00193 U	0.000291 U	0.000306 U	0.000420 U	0.000456 U	0.00144 U	0.000238 U
	B-234A-42	12/4/17	PES	ESC	42	9.8	S	0.00573 U	0.000369 U	0.00168 U	0.000294 U	0.000250 U	0.0123 U	0.00219 U	0.000331 U	0.000348 U	0.000478 U	0.000519 U	0.00164 U	0.000271 U
	B-924-30	12/4/17	PES	ESC	42 (dup)	9.8	S	0.00568 U	0.000366 U	0.00166 U	0.000292 U	0.000248 U	0.0121 U	0.00217 U	0.000328 U	0.000345 U	0.000474 U	0.000515 U	0.00163 U	0.000268 U
	B-234A-45	12/4/17	PES	ESC	45	6.8	S	**0.00676 J**	0.000339 U	0.00154 U	0.000270 U	0.000230 U	**0.0150 J**	0.00202 U	0.000304 U	0.000320 U	0.000440 U	0.000478 U	0.00151 U	**0.000271 J**
B-235	B-235-15	12/5/17	PES	ESC	15	36.8	V	0.00561 U	0.000361 U	0.00164 U	0.000288 U	0.000245 U	0.0120 U	0.00215 U	0.000325 U	0.000341 U	0.000468 U	0.000509 U	0.00161 U	0.000266 U
	B-235-35	12/5/17	PES	ESC	35	16.8	S	0.00518 U	0.000333 U	0.00152 U	0.000266 U	0.000226 U	0.0111 U	0.00198 U	0.000299 U	0.000314 U	0.000432 U	0.000469 U	0.00148 U	0.000245 U
	B-235-40	12/5/17	PES	ESC	40	11.8	S	0.00513 U	0.000330 U	0.00150 U	0.000263 U	0.000224 U	0.0110 U	0.00196 U	**0.000326 J**	0.000311 U	0.000427 U	0.000465 U	0.00147 U	**0.000472 J**
	B-235-42.5	12/5/17	PES	ESC	42.5	9.3	S	1.02 U	0.0657 U	0.299 U	0.0524 U	0.0446 U	2.18 U	0.391 U	0.0590 U	0.0620 U	0.0852 U	0.0926 U	0.293 U	0.0483 U
	B-235-45	12/5/17	PES	ESC	45	6.8	S	0.00527 U	0.000339 U	0.00154 U	0.000270 U	0.000230 U	0.0113 U	0.00202 U	0.000304 U	0.000320 U	0.000439 U	0.000477 U	0.00151 U	**0.000767 J**
B-236	B-236-20	12/5/17	PES	ESC	20	31.8	S	0.00535 U	0.000344 U	0.00157 U	0.000274 U	0.000233 U	0.0114 U	0.00205 U	0.000309 U	0.000325 U	0.000446 U	0.000485 U	0.00153 U	0.000253 U
	B-236-35	12/5/17	PES	ESC	35	16.8	S	0.00848 U	0.000546 U	0.00248 U	0.000435 U	0.000369 U	0.0181 U	0.00325 U	0.000489 U	0.000515 U	0.000707 U	0.000768 U	0.00242 U	0.000400 U
	B-236-40	12/5/17	PES	ESC	40	11.8	S	0.00518 U	0.000333 U	0.00152 U	0.000266 U	0.000226 U	0.0111 U	0.00198 U	0.000299 U	0.000314 U	0.000432 U	0.000469 U	0.00148 U	**0.000767 J**
	B-236-42.5	12/5/17	PES	ESC	42.5	9.3	S	5.49 U	0.353 U	1.61 U	0.281 U	0.239 U	11.7 U	2.10 U	0.317 U	0.333 U	0.457 U	0.497 U	1.57 U	0.259 U
	B-236-45	12/5/17	PES	ESC	45	6.8	S	1.84 U	0.118 U	0.538 U	0.0943 U	0.0801 U	3.93 U	0.703 U	0.106 U	0.112 U	0.153 U	0.166 U	0.527 U	0.0868 U
B-237	B-237-5	12/6/17	PES	ESC	5	46.8	V	0.00545 U	0.000351 U	0.00160 U	0.000280 U	0.000238 U	**0.0197 J**	0.00208 U	0.000314 U	0.000331 U	0.000454 U	0.000494 U	0.00156 U	0.000257 U
	B-237-35	12/6/17	PES	ESC	35	16.8	S	0.00547 U	0.000352 U	0.00160 U	0.000280 U	0.000238 U	0.0117 U	0.00209 U	0.000315 U	0.000332 U	0.000456 U	0.000495 U	0.00157 U	0.000258 U
	B-237-40	12/6/17	PES	ESC	40	11.8	S	0.00503 U	0.000323 U	0.00147 U	0.000258 U	0.000219 U	0.0107 U	0.00192 U	0.000290 U	0.000305 U	0.000419 U	0.000456 U	0.00144 U	0.000237 U
	B-237-42	12/6/17	PES	ESC	42	9.8	S	0.00553 U	0.000356 U	0.00162 U	0.000284 U	0.000241 U	0.0118 U	0.00212 U	0.000319 U	0.000336 U	0.000461 U	0.000501 U	0.00158 U	**0.000656 J**
	B-925-41	12/6/17	PES	ESC	42 (dup)	9.8	S	0.598 U	0.0384 U	0.175 U	0.0306 U	0.0260 U	1.28 U	0.229 U	0.0345 U	0.0363 U	0.0498 U	0.0541 U	0.171 U	0.0282 U
	B-237-45	12/6/17	PES	ESC	45	6.8	S	**0.0167**	0.000387 U	0.00176 U	0.000309 U	0.000263 U	**0.0264 J**	0.00230 U	0.000348 U	0.000366 U	0.000502 U	0.000546 U	0.00172 U	**0.00125 J**
B-238	B-238-6	12/6/17	PES	ESC	6	33.1	S	0.00546 U	0.000351 U	**0.00182 J**	0.000280 U	0.000238 U	0.0117 U	0.00209 U	0.000315 U	0.000331 U	0.000455 U	0.000494 U	0.00156 U	0.000258 U
	B-238-11	12/6/17	PES	ESC	11	28.1	S	**0.0228**	0.000350 U	**0.0164**	0.000279 U	**0.000241 J**	**0.0287 J**	0.00208 U	**0.000929 J+**	0.000330 U	0.000454 U	0.000493 U	0.00156 U	**0.00139**
	B-238-16	12/6/17	PES	ESC	16	23.1	S	1.34 U	0.0860 U	0.391 U	0.0686 U	0.0584 U	2.86 U	0.513 U	0.0772 U	0.0812 U	0.112 U	0.121 U	0.383 U	0.0632 U
	B-238-21	12/6/17	PES	ESC	21	18.1	S	5.22 U	0.336 U	1.53 U	0.268 U	0.228 U	11.2 U	2.00 U	0.301 U	0.317 U	0.435 U	0.473 U	1.50 U	0.247 U
	B-238-26	12/6/17	PES	ESC	26	13.1	S	0.00523 U	0.000337 U	0.00153 U	0.000268 U	0.000228 U	0.0112 U	0.00200 U	0.000302 U	0.000318 U	0.000436 U	0.000474 U	0.00150 U	0.000247 U
	B-238-31	12/6/17	PES	ESC	31	8.1	S	0.00496 U	0.000319 U	0.00145 U	0.000254 U	0.000216 U	0.0106 U	0.00190 U	0.000286 U	0.000301 U	0.000413 U	0.000449 U	0.00142 U	0.000234 U
	B-238-36	12/6/17	PES	ESC	36	3.1	S	0.00548 U	0.000353 U	0.00160 U	0.000281 U	0.000239 U	0.0117 U	0.00210 U	0.000316 U	0.000333 U	0.000457 U	0.000497 U	0.00157 U	**0.000486 J**
B-239	B-239-5	4/3/18	PES	ESC	5	34.2	S	0.00557 U	0.000358 U	0.00163 U	0.000286 U	0.000243 U	0.0119 U	0.00213 U	0.000321 U	0.000338 U	0.000464 U	0.000504 U	0.00159 U	0.000263 U
	B-239-10	4/3/18	PES	ESC	10	29.2	S	0.00552 U	0.000355 U	0.00162 U	0.000283 U	0.000241 U	0.0118 U	0.00211 U	0.000319 U	0.000335 U	0.000460 U	0.000500 U	0.00158 U	**0.000271 J**
	B-239-15	4/3/18	PES	ESC	15	24.2	S	0.00533 U	0.000343 U	0.00156 U	0.000273 U	0.000232 U	**0.0122 J**	0.00204 U	0.000307 U	0.000323 U	0.000444 U	0.000483 U	0.00153 U	**0.000467 J**
	B-239-20	4/3/18	PES	ESC	20	19.2	S	0.00528 U	0.000340 U	0.00155 U	0.000271 U	0.000230 U	0.0113 U	0.00202 U	0.000305 U	0.000320 U	0.000440 U	0.000478 U	0.00151 U	0.000249 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
B-239 (continued)	B-239-25	4/3/18	PES	ESC	25	14.2	S	0.00536 U	0.000345 U	0.00157 U	0.000275 U	0.000234 U	0.0115 U	0.00205 U	0.000309 U	0.000325 U	0.000447 U	0.000486 U	0.00153 U	0.000253 U
	B-239-35	4/3/18	PES	ESC	35	4.2	S	0.00507 U	0.000326 U	0.00148 U	0.000260 U	0.000221 U	0.0108 U	0.00194 U	0.000292 U	0.000307 U	0.000422 U	0.000459 U	0.00145 U	**0.000540 J**
	B-239-40	4/3/18	PES	ESC	40	-0.8	S	0.00531 U	0.000341 U	0.00155 U	0.000272 U	0.000231 U	0.0113 U	0.00203 U	0.000306 U	0.000322 U	0.000442 U	0.000481 U	0.00152 U	**0.000553 J**
	B-239-45	4/3/18	PES	ESC	45	-5.8	S	0.00524 U	0.000337 U	0.00153 U	0.000269 U	0.000229 U	**0.0156 J**	0.00201 U	0.000302 U	0.000318 U	0.000437 U	0.000475 U	0.00150 U	0.000248 U
	B-239-50	4/3/18	PES	ESC	50	-10.8	S	0.00517 U	0.000332 U	0.00151 U	0.000265 U	0.000225 U	0.0110 U	0.00198 U	0.000298 U	0.000314 U	0.000431 U	0.000468 U	0.00148 U	0.000244 U
	B-909-50	4/3/18	PES	ESC	50 (dup)	-10.8	S	0.00520 U	0.000334 U	0.00152 U	0.000267 U	0.000227 U	0.0111 U	0.00199 U	0.000300 U	0.000316 U	0.000433 U	0.000471 U	0.00149 U	0.000246 U
	B-239-55	4/3/18	PES	ESC	55	-15.8	S	0.00533 U	0.000342 U	0.00156 U	0.000273 U	0.000232 U	0.0114 U	0.00204 U	0.000307 U	0.000323 U	0.000444 U	0.000482 U	0.00152 U	0.000251 U
	B-239-60	4/3/18	PES	ESC	60	-20.8	S	0.00523 U	0.000337 U	0.00153 U	0.000268 U	0.000228 U	0.0112 U	0.00200 U	0.000302 U	0.000318 U	0.000436 U	0.000474 U	0.00150 U	0.000247 U
	B-239-65	4/3/18	PES	ESC	65	-25.8	S	0.00523 U	0.000336 U	0.00153 U	0.000268 U	0.000228 U	0.0112 U	0.00200 U	0.000302 U	0.000317 U	0.000436 U	0.000474 U	0.00150 U	0.000247 U
	B-239-70	4/3/18	PES	ESC	70	-30.8	S	0.00521 U	0.000335 U	0.00153 U	0.000267 U	0.000227 U	**0.0124 J**	0.00199 U	0.000301 U	0.000316 U	0.000434 U	0.000472 U	0.00149 U	**0.000311 J**
	B-239-75	4/3/18	PES	ESC	75	-35.8	S	0.00539 U	0.000347 U	0.00158 U	0.000277 U	0.000235 U	0.0115 U	0.00206 U	0.000311 U	0.000327 U	0.000450 U	0.000489 U	0.00154 U	0.000255 U
	B-239-80	4/3/18	PES	ESC	80	-40.8	S	0.00536 U	0.000345 U	0.00157 U	0.000275 U	0.000233 U	0.0114 U	0.00205 U	0.000309 U	0.000325 U	0.000446 U	0.000485 U	0.00153 U	0.000253 U
B-240	B-240-5	4/2/18	PES	ESC	5	34.2	S	0.00516 U	0.000332 U	0.00151 U	0.000265 U	0.000225 U	0.0110 U	0.00198 U	0.000298 U	0.000313 U	0.000430 U	0.000468 U	0.00148 U	**0.000247 J**
	B-240-10	4/2/18	PES	ESC	10	29.2	S	0.00516 U	0.000332 U	0.00151 U	0.000265 U	0.000225 U	0.0110 U	0.00197 U	**0.000325 J**	0.000313 U	0.000430 U	0.000467 U	0.00148 U	**0.000576 J**
	B-240-15	4/2/18	PES	ESC	15	24.2	S	0.00537 U	0.000345 U	0.00157 U	0.000275 U	0.000234 U	0.0115 U	0.00205 U	0.000310 U	0.000326 U	0.000447 U	0.000486 U	0.00154 U	0.000254 U
	B-240-20	4/2/18	PES	ESC	20	19.2	S	0.00545 U	0.000350 U	0.00159 U	0.000279 U	0.000237 U	0.0116 U	0.00208 U	0.000314 U	0.000331 U	0.000454 U	0.000494 U	0.00156 U	0.000257 U
	B-240-25	4/2/18	PES	ESC	25	14.2	S	0.261 U	0.0168 U	0.0765 U	0.0134 U	0.0114 U	0.559 U	0.100 U	0.0151 U	0.0159 U	0.0218 U	0.0237 U	0.0748 U	0.0123 U
	B-240-30	4/2/18	PES	ESC	30	9.2	S	0.00564 U	0.000363 U	0.00165 U	0.000289 U	0.000246 U	0.0120 U	0.00216 U	0.000325 U	0.000342 U	0.000470 U	0.000511 U	0.00161 U	0.000266 U
	B-240-35	4/2/18	PES	ESC	35	4.2	S	0.00562 U	0.000361 U	0.00165 U	0.000288 U	0.000245 U	0.0120 U	0.00215 U	0.000324 U	0.000341 U	0.000468 U	0.000509 U	0.00161 U	0.000265 U
	B-240-42	4/2/18	PES	ESC	42	-2.8	S	0.00504 U	0.000324 U	0.00147 U	0.000258 U	0.000220 U	0.0108 U	0.00193 U	0.000291 U	0.000306 U	0.000420 U	0.000456 U	0.00144 U	0.000238 U
	B-240-45	4/2/18	PES	ESC	45	-5.8	S	0.00496 U	0.000319 U	0.00145 U	0.000254 U	0.000216 U	0.0106 U	0.00190 U	0.000286 U	0.000301 U	0.000414 U	0.000450 U	0.00142 U	0.000234 U
	B-240-50	4/2/18	PES	ESC	50	-10.8	S	0.00527 U	0.000339 U	0.00154 U	0.000270 U	0.000230 U	0.0113 U	0.00202 U	0.000304 U	0.000320 U	0.000439 U	0.000477 U	0.00151 U	0.000249 U
	B-240-55	4/2/18	PES	ESC	55	-15.8	S	0.00543 U	0.000349 U	0.00159 U	0.000278 U	0.000237 U	0.0116 U	0.00208 U	0.000313 U	0.000329 U	0.000452 U	0.000492 U	0.00155 U	0.000256 U
	B-240-60	4/2/18	PES	ESC	60	-20.8	S	0.00545 U	0.000350 U	0.00159 U	0.000279 U	0.000237 U	0.0116 U	0.00208 U	0.000314 U	0.000331 U	0.000454 U	0.000494 U	0.00156 U	**0.000291 J**
	B-240-65	4/2/18	PES	ESC	65	-25.8	S	0.00507 U	0.000326 U	0.00149 U	0.000260 U	0.000221 U	0.0108 U	0.00194 U	0.000293 U	0.000308 U	0.000423 U	0.000460 U	0.00145 U	0.000240 U
	B-240-70	4/2/18	PES	ESC	70	-30.8	S	0.00541 U	0.000348 U	0.00158 U	0.000278 U	0.000236 U	0.0116 U	0.00207 U	0.000312 U	0.000329 U	0.000451 U	0.000491 U	0.00155 U	0.000256 U
	B-240-75	4/2/18	PES	ESC	75	-35.8	S	0.00514 U	0.000331 U	0.00150 U	0.000264 U	0.000224 U	0.0110 U	0.00197 U	0.000297 U	0.000312 U	0.000428 U	0.000466 U	0.00147 U	0.000243 U
	B-240-80	4/2/18	PES	ESC	80	-40.8	S	0.00532 U	0.000342 U	0.00156 U	0.000273 U	0.000232 U	0.0114 U	0.00204 U	0.000307 U	0.000323 U	0.000444 U	0.000482 U	0.00152 U	0.000251 U
B-241	B-241-5	4/4/18	PES	ESC	5	34.1	S	0.00508 U	0.000326 U	0.00149 U	0.000260 U	**0.00284**	0.0108 U	0.00194 U	**0.00118**	0.000308 U	0.000423 U	0.000460 U	0.00145 U	**0.00263**
	B-241-10	4/4/18	PES	ESC	10	29.1	S	0.00531 U	0.000341 U	0.00155 U	0.000272 U	0.000231 U	0.0113 U	0.00203 U	0.000306 U	0.000322 U	0.000442 U	0.000481 U	0.00152 U	0.000251 U
	B-241-15	4/4/18	PES	ESC	15	24.1	S	0.00522 U	0.000336 U	0.00153 U	0.000268 U	0.000228 U	0.0112 U	0.00200 U	0.000301 U	0.000317 U	0.000435 U	0.000473 U	0.00150 U	0.000247 U
	B-241-20	4/4/18	PES	ESC	20	19.1	S	0.00570 U	0.000366 U	0.00167 U	0.000292 U	0.000248 U	0.0122 U	0.00218 U	0.000329 U	0.000346 U	0.000475 U	0.000516 U	0.00163 U	0.000269 U
	B-241-25	4/4/18	PES	ESC	25	14.1	S	**0.0137**	0.000340 U	0.00155 U	0.000271 U	0.000231 U	**0.0254 J**	0.00202 U	0.000305 U	0.000321 U	0.000441 U	0.000479 U	0.00151 U	**0.000732 J**
	B-241-30	4/3/18	PES	ESC	30	9.1	S	0.00525 U	0.000338 U	0.00154 U	0.000269 U	0.000229 U	0.0112 U	0.00201 U	0.000303 U	0.000319 U	0.000437 U	0.000476 U	0.00150 U	0.000248 U
	B-241-35	4/3/18	PES	ESC	35	4.1	S	**0.00637 J**	0.000348 U	0.00159 U	0.000278 U	0.000236 U	**0.0143 J**	0.00207 U	0.000313 U	0.000329 U	0.000451 U	0.000491 U	0.00155 U	**0.000607 J**
	B-241-40	4/3/18	PES	ESC	40	-0.9	S	0.00514 U	0.000330 U	0.00150 U	0.000263 U	0.000224 U	0.0110 U	0.00196 U	0.000296 U	0.000312 U	0.000428 U	0.000465 U	0.00147 U	**0.000248 J**
	B-241-45	4/3/18	PES	ESC	45	-5.9	S	0.00515 U	0.000331 U	0.00151 U	0.000264 U	0.000225 U	0.0110 U	0.00197 U	**0.000370 J+**	0.000313 U	0.000429 U	0.000467 U	0.00148 U	**0.00101 J**
	B-241-50	4/4/18	PES	ESC	50	-10.9	S	0.00527 U	0.000339 U	0.00154 U	0.000270 U	0.000230 U	0.0113 U	0.00202 U	0.000304 U	0.000320 U	0.000439 U	0.000478 U	0.00151 U	**0.00197**
	B-241-55	4/4/18	PES	ESC	55	-15.9	S	0.00545 U	0.000350 U	0.00160 U	0.000279 U	0.000238 U	0.0116 U	0.00208 U	0.000314 U	0.000331 U	0.000454 U	0.000494 U	0.00156 U	**0.000986 J**
	B-241-60	4/3/18	PES	ESC	60	-20.9	S	0.00524 U	0.000337 U	0.00153 U	0.000269 U	0.000228 U	0.0112 U	0.00200 U	0.000302 U	0.000318 U	0.000437 U	0.000475 U	0.00150 U	0.000247 U
	B-241-65	4/3/18	PES	ESC	65	-25.9	S	0.00554 U	0.000356 U	0.00162 U	0.000284 U	0.000241 U	0.0118 U	0.00212 U	**0.000470 J**	0.000336 U	0.000462 U	0.000502 U	0.00159 U	**0.000849 J**
	B-241-70	4/3/18	PES	ESC	70	-30.9	S	0.00540 U	0.000347 U	0.00158 U	0.000277 U	0.000235 U	0.0115 U	0.00207 U	0.000312 U	0.000328 U	0.000450 U	0.000489 U	0.00155 U	0.000255 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
B-241	B-241-75	4/3/18	PES	ESC	75	-35.9	S	0.00546 U	0.000351 U	0.00160 U	0.000280 U	0.000238 U	0.0117 U	0.00209 U	0.000315 U	0.000331 U	0.000455 U	0.000494 U	0.00156 U	**0.000320 J**
(continued)	B-241-80	4/4/18	PES	ESC	80	-40.9	S	0.00538 U	0.000346 U	0.00157 U	0.000276 U	0.000234 U	0.0115 U	0.00206 U	0.000310 U	0.000326 U	0.000448 U	0.000487 U	0.00154 U	0.000254 U
B-242	B-242-5	4/4/18	PES	ESC	5	33.8	S	0.00508 U	0.000327 U	0.00149 U	0.000260 U	0.000221 U	0.0109 U	0.00194 U	0.000293 U	0.000308 U	0.000423 U	0.000460 U	0.00145 U	**0.000251 J**
	B-242-10	4/4/18	PES	ESC	10	28.8	S	0.00512 U	0.000329 U	0.00150 U	0.000263 U	0.000223 U	0.0109 U	0.00196 U	0.000296 U	0.000311 U	0.000427 U	0.000464 U	0.00147 U	0.000242 U
	B-242-15	4/4/18	PES	ESC	15	23.8	S	0.00546 U	0.000351 U	0.00160 U	0.000280 U	0.000238 U	0.0117 U	0.00209 U	0.000315 U	0.000331 U	0.000455 U	0.000494 U	0.00156 U	0.000258 U
	B-242-20	4/4/18	PES	ESC	20	18.8	S	0.00530 U	0.000341 U	0.00155 U	0.000272 U	0.000231 U	0.0113 U	0.00203 U	0.000306 U	0.000322 U	0.000442 U	0.000480 U	0.00152 U	0.000250 U
	B-242-25	4/4/18	PES	ESC	25	13.8	S	0.516 U	0.0332 U	0.151 U	0.0265 U	0.0225 U	1.10 U	0.197 U	0.0298 U	0.0313 U	0.0430 U	0.0467 U	0.148 U	0.0244 U
	B-242-30	4/4/18	PES	ESC	30	8.8	S	0.00523 U	0.000337 U	0.00153 U	0.000268 U	0.000228 U	**0.0148 J**	0.00200 U	0.000302 U	0.000318 U	0.000436 U	0.000474 U	0.00150 U	0.000247 U
	B-242-35	4/4/18	PES	ESC	35	3.8	S	**0.0301 J**	0.000347 U	0.00158 U	0.000276 U	0.000235 U	**0.118**	0.00206 U	0.000311 U	0.000327 U	0.000449 U	0.000488 U	0.00154 U	**0.000364 J**
	B-242-40	4/4/18	PES	ESC	40	-1.2	S	**0.00927 J**	0.000329 U	0.00150 U	0.000263 U	0.000223 U	**0.0493 J**	0.00196 U	0.000295 U	0.000311 U	0.000427 U	0.000464 U	0.00147 U	**0.000693 J**
	B-242-45	4/4/18	PES	ESC	45	-6.2	S	0.00541 U	0.000348 U	0.00158 U	0.000278 U	0.000236 U	0.0116 U	0.00207 U	0.000312 U	0.000328 U	0.000451 U	0.000490 U	0.00155 U	0.000256 U
	B-242-50	4/4/18	PES	ESC	50	-11.2	S	0.00524 U	0.000337 U	0.00153 U	0.000269 U	0.000228 U	**0.0119 J**	0.00200 U	0.000302 U	0.000318 U	0.000437 U	0.000475 U	0.00150 U	0.000247 U
	B-910-50	4/4/18	PES	ESC	50 (dup)	-11.2	S	0.00525 U	0.000338 U	0.00154 U	0.000269 U	0.000229 U	**0.0113 J**	0.00201 U	0.000303 U	0.000319 U	0.000438 U	0.000476 U	0.00150 U	**0.000815 J**
	B-242-55	4/4/18	PES	ESC	55	-16.2	S	0.00514 U	0.000331 U	0.00150 U	0.000264 U	0.000224 U	0.0110 U	0.00197 U	0.000297 U	0.000312 U	0.000428 U	0.000466 U	0.00147 U	0.000243 U
	B-242-60	4/4/18	PES	ESC	60	-21.2	S	0.00516 U	0.000332 U	0.00151 U	0.000265 U	0.000225 U	0.0110 U	0.00197 U	0.000298 U	0.000313 U	0.000430 U	0.000468 U	0.00148 U	**0.000248 J**
	B-242-65	4/4/18	PES	ESC	65	-26.2	S	0.00507 U	0.000326 U	0.00148 U	0.000260 U	0.000221 U	0.0108 U	0.00194 U	0.000292 U	0.000308 U	0.000422 U	0.000459 U	0.00145 U	**0.000320 J**
	B-242-70	4/4/18	PES	ESC	70	-31.2	S	0.00536 U	0.000345 U	0.00157 U	0.000275 U	0.000234 U	0.0115 U	0.00205 U	0.000309 U	0.000325 U	0.000447 U	0.000486 U	0.00153 U	0.000253 U
	B-242-75	4/4/18	PES	ESC	75	-36.2	S	0.00519 U	0.000334 U	0.00152 U	0.000266 U	0.000226 U	0.0111 U	0.00199 U	0.000300 U	0.000315 U	0.000433 U	0.000470 U	0.00149 U	**0.00136**
	B-242-80	4/4/18	PES	ESC	80	-41.2	S	0.00542 U	0.000349 U	0.00159 U	0.000278 U	0.000236 U	0.0116 U	0.00207 U	0.000313 U	0.000329 U	0.000452 U	0.000491 U	0.00155 U	0.000256 U
B-243	B-243-5	3/29/18	PES	ESC	5	34.9	S	0.00544 U	0.000350 U	0.00159 U	0.000279 U	0.000237 U	0.0116 U	0.00208 U	0.000314 U	0.000330 U	0.000453 U	0.000492 U	0.00156 U	0.000257 U
	B-243-10	3/29/18	PES	ESC	10	29.9	S	0.00532 U	0.000342 U	0.00156 U	0.000273 U	**0.000749 J**	0.0114 U	0.00203 U	0.000307 U	0.000323 U	0.000443 U	0.000482 U	0.00152 U	0.000251 U
	B-243-15	3/29/18	PES	ESC	15	24.9	S	0.132 U	0.00851 U	0.0387 U	0.00679 U	0.00577 U	0.283 U	0.0507 U	0.00764 U	0.00803 U	0.0110 U	0.0120 U	0.0379 U	0.00625 U
	B-243-20	3/29/18	PES	ESC	20	19.9	S	0.00540 U	0.000347 U	0.00158 U	0.000277 U	0.000235 U	0.0115 U	0.00206 U	0.000311 U	0.000327 U	0.000450 U	0.000489 U	0.00155 U	0.000255 U
	B-243-25	3/29/18	PES	ESC	25	14.9	S	0.00522 U	0.000335 U	0.00153 U	0.000267 U	0.000227 U	0.0111 U	0.00199 U	0.000301 U	0.000316 U	0.000435 U	0.000472 U	0.00149 U	0.000246 U
	B-243-30	3/29/18	PES	ESC	30	9.9	S	0.00510 U	0.000328 U	0.00149 U	0.000261 U	0.000222 U	0.0109 U	0.00195 U	0.000294 U	0.000309 U	0.000425 U	0.000462 U	0.00146 U	0.000241 U
	B-243-35	3/29/18	PES	ESC	35	4.9	S	0.00518 U	0.000333 U	0.00152 U	0.000266 U	0.000226 U	0.0111 U	0.00198 U	0.000299 U	0.000315 U	0.000432 U	0.000470 U	0.00148 U	**0.00114**
	B-243-42	3/29/18	PES	ESC	42	-2.1	S	0.00511 U	0.000329 U	0.00150 U	0.000262 U	0.000223 U	0.0109 U	0.00196 U	0.000295 U	0.000310 U	0.000426 U	0.000463 U	0.00146 U	**0.00163**
	B-243-45	3/29/18	PES	ESC	45	-5.1	S	0.00507 U	0.000326 U	0.00148 U	0.000260 U	0.000221 U	0.0108 U	0.00194 U	0.000293 U	0.000308 U	0.000423 U	0.000459 U	0.00145 U	**0.00150**
	B-243-50	3/29/18	PES	ESC	50	-10.1	S	0.00540 U	0.000348 U	0.00158 U	0.000277 U	0.000236 U	0.0115 U	0.00207 U	0.000312 U	0.000328 U	0.000450 U	0.000490 U	0.00155 U	**0.00489**
	IW-908-50	3/29/18	PES	ESC	50 (dup)	-10.1	S	0.00529 U	0.000340 U	0.00155 U	0.000271 U	0.000231 U	0.0113 U	0.00202 U	0.000305 U	0.000321 U	0.000441 U	0.000480 U	0.00152 U	**0.00351 J**
	B-243-55	3/29/18	PES	ESC	55	-15.1	S	0.00505 U	0.000325 U	0.00148 U	0.000259 U	0.000220 U	0.0108 U	0.00193 U	0.000292 U	0.000307 U	0.000421 U	0.000458 U	0.00145 U	**0.00187**
	B-243-60	3/29/18	PES	ESC	60	-20.1	S	0.00535 U	0.000344 U	0.00157 U	0.000274 U	0.000233 U	0.0114 U	0.00205 U	0.000309 U	0.000325 U	0.000446 U	0.000485 U	0.00153 U	**0.00152**
	B-243-65	3/29/18	PES	ESC	65	-25.1	S	0.00514 U	0.000331 U	0.00150 U	0.000264 U	0.000224 U	0.0110 U	0.00197 U	0.000297 U	0.000312 U	0.000428 U	0.000466 U	0.00147 U	**0.000841 J**
	B-243-70	3/29/18	PES	ESC	70	-30.1	S	0.00543 U	0.000349 U	0.00159 U	0.000278 U	0.000237 U	0.0116 U	0.00208 U	0.000313 U	0.000329 U	0.000452 U	0.000492 U	0.00155 U	**0.000289 J**
	B-243-75	3/29/18	PES	ESC	75	-35.1	S	0.00558 U	0.000359 U	0.00163 U	0.000286 U	0.000243 U	0.0119 U	0.00213 U	0.000322 U	0.000338 U	0.000465 U	0.000505 U	0.00160 U	0.000263 U
	B-243-80	3/29/18	PES	ESC	80	-40.1	S	0.00568 U	0.000366 U	0.00166 U	0.000292 U	0.000248 U	0.0121 U	0.00217 U	0.000328 U	0.000345 U	0.000474 U	0.000515 U	0.00163 U	**0.000471 J**
B-244	B-244-5	3/28/18	PES	ESC	5	33.8	S	**0.0320 J**	0.000380 U	**0.0102 J**	0.000303 U	0.000257 U	**0.125 J**	0.00226 U	**0.00411**	0.000358 U	0.000492 U	0.000535 U	0.00169 U	**0.00929 J**
	B-244-10	3/28/18	PES	ESC	10	28.8	S	**0.00628 J**	0.000359 U	0.00163 U	0.000286 U	0.000243 U	**0.0308 J**	0.00213 U	**0.000911 J**	0.000338 U	0.000465 U	0.000505 U	0.00160 U	**0.00132 J**
	B-244-15	3/28/18	PES	ESC	15	23.8	S	0.00534 U	0.000343 U	0.00156 U	0.000274 U	0.000233 U	**0.0138 J**	0.00204 U	0.000308 U	0.000324 U	0.000445 U	0.000484 U	0.00153 U	**0.00161 J**
	B-244-20	3/28/18	PES	ESC	20	18.8	S	0.00531 U	0.000342 U	0.00155 U	0.000272 U	0.000231 U	**0.0126 J**	0.00203 U	0.000306 U	0.000322 U	0.000442 U	0.000481 U	0.00152 U	**0.000710 J**
	B-244-25	3/28/18	PES	ESC	25	13.8	S	0.00495 U	0.000319 U	0.00145 U	0.000254 U	0.000216 U	**0.0107 J**	0.00190 U	0.000286 U	0.000301 U	0.000413 U	0.000449 U	0.00142 U	0.000234 U
	B-244-30	3/28/18	PES	ESC	30	8.8	S	0.00512 U	0.000329 U	0.00150 U	0.000262 U	0.000223 U	**0.0133 J**	0.00196 U	0.000295 U	0.000311 U	0.000426 U	0.000464 U	0.00147 U	**0.000655 J**

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
B-244 (continued)	B-244-35	3/28/18	PES	ESC	35	3.8	S	0.00538 U	0.000346 U	0.00157 U	0.000276 U	0.000234 U	**0.0135 J**	0.00206 U	0.000310 U	0.000326 U	0.000448 U	0.000487 U	0.00154 U	**0.00116 J**
	B-244-40	3/28/18	PES	ESC	40	-1.2	S	0.00516 U	0.000332 U	0.00151 U	0.000265 U	0.000225 U	0.0110 U	0.00197 U	0.000298 U	0.000313 U	0.000430 U	0.000468 U	0.00148 U	**0.000822 J**
	B-244-42	3/28/18	PES	ESC	42	-3.2	S	0.132 U	0.00846 U	0.0385 U	0.00675 U	0.00574 U	0.281 U	0.0504 U	0.00759 U	0.00799 U	0.0110 U	0.0119 U	0.0377 U	0.00621 U
	B-244-45	3/28/18	PES	ESC	45	-6.2	S	**0.00730 J**	0.000339 U	0.00154 U	0.000270 U	0.000230 U	**0.0273 J**	0.00201 U	0.000304 U	0.000320 U	0.000439 U	0.000477 U	0.00151 U	**0.00162 J**
	B-244-50	3/28/18	PES	ESC	50	-11.2	S	0.00518 U	0.000333 U	0.00152 U	0.000265 U	0.000226 U	**0.0285 J**	0.00198 U	0.000299 U	0.000314 U	0.000431 U	0.000469 U	0.00148 U	**0.00124 J**
	B-244-55	3/28/18	PES	ESC	55	-16.2	S	0.00515 U	0.000331 U	0.00151 U	0.000264 U	0.000225 U	**0.0177 J**	0.00197 U	0.000297 U	0.000313 U	0.000429 U	0.000467 U	0.00148 U	**0.00270 J**
	B-244-60	3/28/18	PES	ESC	60	-21.2	S	0.00522 U	0.000336 U	0.00153 U	0.000268 U	0.000228 U	**0.0411 J**	0.00200 U	0.000301 U	0.000317 U	0.000435 U	0.000473 U	0.00150 U	**0.00140 J**
	B-244-65	3/28/18	PES	ESC	65	-26.2	S	**0.00655 J**	0.000341 U	0.00155 U	0.000272 U	0.000231 U	**0.0220 J**	0.00203 U	**0.00184**	0.000322 U	0.000442 U	0.000481 U	0.00152 U	**0.00144 J**
	B-244-70	3/28/18	PES	ESC	70	-31.2	S	0.00508 U	0.000327 U	0.00149 U	0.000261 U	0.000221 U	**0.0157 J**	0.00194 U	0.000293 U	0.000308 U	0.000423 U	0.000460 U	0.00145 U	**0.00118 J**
	IW-907-70	3/28/18	PES	ESC	70 (dup)	-31.2	S	0.00509 U	0.000328 U	0.00149 U	0.000261 U	0.000222 U	**0.0151 J**	0.00195 U	0.000294 U	0.000309 U	0.000425 U	0.000462 U	0.00146 U	**0.000931 J**
	B-244-75	3/28/18	PES	ESC	75	-36.2	S	0.00537 U	0.000345 U	0.00157 U	0.000275 U	0.000234 U	**0.0128 J**	0.00205 U	0.000310 U	0.000326 U	0.000447 U	0.000486 U	0.00154 U	**0.000969 J**
	B-244-80	3/28/18	PES	ESC	80	-41.2	S	0.00544 U	0.000350 U	0.00159 U	0.000279 U	0.000237 U	0.0116 U	0.00208 U	0.000314 U	0.000330 U	0.000453 U	0.000493 U	0.00156 U	0.000257 U
B-245	B-245-5	3/28/18	PES	ESC	5	34.9	V	0.00509 U	0.000328 U	0.00149 U	0.000261 U	0.000222 U	**0.0278 J**	0.00195 U	0.000294 U	0.000309 U	0.000424 U	0.000461 U	0.00146 U	0.000240 U
	B-245-10	3/28/18	PES	ESC	10	29.9	S	0.00537 U	0.000345 U	0.00157 U	0.000275 U	0.000234 U	0.0115 U	0.00205 U	0.000310 U	0.000326 U	0.000447 U	0.000486 U	0.00154 U	0.000254 U
	B-245-15	3/28/18	PES	ESC	15	24.9	S	0.00542 U	0.000349 U	0.00159 U	0.000278 U	0.000236 U	**0.0121 J**	0.00207 U	0.000313 U	0.000329 U	0.000452 U	0.000491 U	0.00155 U	0.000256 U
	B-245-20	3/28/18	PES	ESC	20	19.9	S	0.00505 U	0.000325 U	0.00148 U	0.000259 U	0.000220 U	0.0108 U	0.00193 U	0.000292 U	0.000307 U	0.000421 U	0.000458 U	0.00145 U	0.000239 U
	B-245-25	3/28/18	PES	ESC	25	14.9	S	0.00530 U	0.000341 U	0.00155 U	0.000272 U	0.000231 U	**0.0121 J**	0.00203 U	0.000306 U	0.000321 U	0.000441 U	0.000480 U	0.00152 U	0.000250 U
	B-245-30	3/29/18	PES	ESC	30	9.9	S	0.0101 U	0.000647 U	0.00294 U	0.000516 U	0.000438 U	**0.0659 J**	0.00384 U	0.000580 U	0.000610 U	0.000838 U	0.000912 U	0.00289 U	**0.00248**
	B-245-35	3/29/18	PES	ESC	35	4.9	S	0.00527 U	0.000339 U	0.00154 U	0.000270 U	0.000230 U	0.0113 U	0.00201 U	**0.000419 J**	0.000320 U	0.000439 U	0.000477 U	0.00151 U	**0.000730 J**
	B-245-40	3/29/18	PES	ESC	40	-0.1	S	**0.0178**	0.000335 U	0.00152 U	0.000267 U	0.000227 U	**0.0537 J**	0.00199 U	0.000301 U	0.000316 U	0.000434 U	0.000472 U	0.00149 U	**0.000820 J**
	B-245-45	3/29/18	PES	ESC	45	-5.1	S	**0.0126**	0.000335 U	0.00152 U	0.000267 U	0.000227 U	**0.0272 J**	0.00199 U	0.000300 U	0.000316 U	0.000434 U	0.000471 U	0.00149 U	**0.000447 J**
	B-245-50	3/29/18	PES	ESC	50	-10.1	S	0.00530 U	0.000341 U	0.00155 U	0.000272 U	0.000231 U	**0.0191 J**	0.00203 U	0.000306 U	0.000322 U	0.000442 U	0.000481 U	0.00152 U	**0.000449 J**
	B-245-55	3/29/18	PES	ESC	55	-15.1	S	0.00527 U	0.000339 U	0.00154 U	0.000270 U	0.000230 U	**0.0133 J**	0.00202 U	0.000304 U	0.000320 U	0.000440 U	0.000478 U	0.00151 U	0.000249 U
	B-245-60	3/29/18	PES	ESC	60	-20.1	S	**0.00503 J**	0.000322 U	0.00147 U	0.000257 U	0.000219 U	**0.0212 J**	0.00192 U	**0.000503 J**	0.000304 U	0.000418 U	0.000454 U	0.00144 U	**0.000626 J**
	B-245-65	3/29/18	PES	ESC	65	-25.1	S	**0.00572 J**	0.000344 U	0.00157 U	0.000275 U	0.000233 U	**0.0207 J**	0.00205 U	0.000309 U	0.000325 U	0.000446 U	0.000485 U	0.00153 U	**0.000633 J**
	B-245-70	3/29/18	PES	ESC	70	-30.1	S	0.00551 U	0.000354 U	0.00161 U	0.000282 U	0.000240 U	0.0118 U	0.00211 U	0.000318 U	0.000334 U	0.000459 U	0.000499 U	0.00158 U	0.000260 U
	B-245-75	3/29/18	PES	ESC	75	-35.1	S	0.00527 U	0.000339 U	0.00154 U	0.000270 U	0.000230 U	0.0113 U	0.00202 U	0.000304 U	0.000320 U	0.000440 U	0.000478 U	0.00151 U	**0.000440 J**
	B-245-80	3/29/18	PES	ESC	80	-40.1	S	0.00542 U	0.000349 U	0.00159 U	0.000278 U	0.000236 U	0.0116 U	0.00207 U	0.000313 U	0.000329 U	0.000452 U	0.000491 U	0.00155 U	0.000256 U
B-246	B-246-6	5/11/18	PES	ESC	6	33.9	S	0.0148 U	0.00109 U	0.0119 U	0.00134 U	0.00277 U	0.0163 U	0.00226 U	0.000475 U	0.00125 U	0.00134 U	0.00710 U	0.00439 U	0.00482 U
	B-246-11	5/11/18	PES	ESC	11	28.9	S	0.0148 U	0.00109 U	0.0118 U	0.00133 U	0.00275 U	0.0162 U	0.00224 U	0.000472 U	0.00124 U	0.00133 U	0.00706 U	0.00437 U	0.00479 U
	B-246-15	5/11/18	PES	ESC	15	24.9	S	0.0141 U	0.00104 U	0.0113 U	0.00128 U	0.00263 U	0.0155 U	0.00215 U	**0.000583 J**	0.00119 U	0.00128 U	0.00676 U	0.00418 U	0.00459 U
	B-246-25	5/11/18	PES	ESC	25	14.9	S	0.0140 U	0.00103 U	0.0112 U	0.00126 U	0.00261 U	0.0153 U	0.00212 U	0.000447 U	0.00117 U	0.00126 U	0.00669 U	0.00414 U	0.00454 U
	B-246-30	5/11/18	PES	ESC	30	9.9	S	0.0147 U	0.00108 U	0.0118 U	0.00133 U	0.00274 U	0.0161 U	0.00224 U	0.000471 U	0.00124 U	0.00133 U	0.00704 U	0.00435 U	0.00478 U
	B-246-35	5/11/18	PES	ESC	35	4.9	S	0.0144 U	0.00106 U	0.0115 U	0.00130 U	0.00269 U	0.0158 U	0.00219 U	0.000461 U	0.00121 U	0.00130 U	0.00689 U	0.00427 U	0.00468 U
	B-246-40	5/11/18	PES	ESC	40	-0.1	S	0.0142 U	0.00104 U	0.0113 U	0.00128 U	0.00264 U	0.0155 U	0.00215 U	0.000453 U	0.00119 U	0.00128 U	0.00677 U	0.00419 U	0.00460 U
	B-246-43	5/11/18	PES	ESC	43	-3.1	S	0.0137 U	0.00101 U	0.0109 U	0.00124 U	0.00255 U	0.0150 U	0.00208 U	0.000437 U	0.00115 U	0.00124 U	0.00654 U	0.00405 U	0.00444 U
	B-246-45	5/11/18	PES	ESC	45	-5.1	S	0.0151 U	0.00111 U	0.0121 U	0.00136 U	0.00281 U	**0.0277 J**	0.00229 U	0.000482 U	0.00126 U	0.00136 U	0.00721 U	0.00446 U	0.00489 U
	B-246-50	5/11/18	PES	ESC	50	-10.1	S	0.0141 U	0.00104 U	0.0113 U	0.00127 U	0.00262 U	0.0154 U	0.00214 U	0.000450 U	0.00118 U	0.00127 U	0.00673 U	0.00416 U	0.00457 U
	B-246-55	5/11/18	PES	ESC	55	-15.1	S	0.0143 U	0.00105 U	0.0115 U	0.00129 U	0.00267 U	0.0157 U	0.00218 U	0.000458 U	0.00120 U	0.00129 U	0.00685 U	0.00424 U	0.00465 U
	B-246-60	5/11/18	PES	ESC	60	-20.1	S	0.0142 U	0.00104 U	0.0113 U	0.00128 U	0.00264 U	0.0155 U	0.00216 U	0.000454 U	0.00119 U	0.00128 U	0.00679 U	0.00420 U	0.00461 U
	B-246-65	5/11/18	PES	ESC	65	-25.1	S	0.0155 U	0.00114 U	0.0124 U	0.00140 U	0.00288 U	0.0169 U	0.00235 U	0.000495 U	0.00130 U	0.00140 U	0.00740 U	0.00458 U	0.00502 U
	B-246-70	5/11/18	PES	ESC	70	-30.1	S	0.0139 U	0.00102 U	0.0111 U	0.00126 U	0.00259 U	**0.0166 J**	0.00211 U	0.000445 UJ	0.00117 U	0.00126 U	0.00665 U	0.00411 U	0.00451 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
B-246 (continued)	B-246-75	5/11/18	PES	ESC	75	-35.1	S	0.0145 U	0.00107 U	0.0116 U	0.00131 U	0.00270 U	**0.0178 J**	0.00220 U	0.000463 U	0.00122 U	0.00131 U	0.00693 U	0.00429 U	0.00470 U
	B-246-80	5/11/18	PES	ESC	80	-40.1	S	0.0141 U	0.00104 U	0.0113 U	0.00128 U	0.00263 U	0.0155 U	0.00215 U	0.000452 U	0.00119 U	0.00128 U	0.00675 U	0.00418 U	0.00459 U
	B-926-100	5/11/18	PES	ESC	45 (dup)	-5.1	S	0.0187 U	0.00138 U	0.0150 U	0.00169 U	0.00349 U	0.0205 U	0.00284 U	**0.000776 J**	0.00157 U	0.00169 U	0.00895 U	0.00554 U	0.00608 U
B-247	B-247-5	4/20/18	PES	ESC	5	34.7	S	0.00531 U	0.000342 U	0.00156 U	0.000272 U	0.000232 U	**0.0126 J**	0.00203 U	0.000306 U	0.000322 U	0.000443 U	0.000481 U	0.00152 U	**0.000866 J**
	B-247-10	4/20/18	PES	ESC	10	29.7	S	0.00539 U	0.000347 U	0.00158 U	0.000276 U	0.000235 U	0.0115 U	0.00206 U	0.000311 U	0.000327 U	0.000449 U	0.000488 U	0.00154 U	0.000254 U
	B-247-15	4/20/18	PES	ESC	15	24.7	S	0.00519 U	0.000334 U	0.00152 U	0.000266 U	0.000226 U	0.0111 U	0.00199 U	0.000299 U	0.000315 U	0.000433 U	0.000470 U	0.00149 U	0.000245 U
	B-247-20	4/20/18	PES	ESC	20	19.7	S	**0.0115**	0.000336 U	0.00153 U	0.000268 U	0.000228 U	**0.0471 J**	0.00200 U	0.000301 U	0.000317 U	0.000435 U	0.000473 U	0.00150 U	**0.00126**
	B-247-25	4/20/18	PES	ESC	25	14.7	S	0.00509 U	0.000328 U	0.00149 U	0.000261 U	0.000222 U	0.0109 U	0.00195 U	0.000294 U	0.000309 U	0.000424 U	0.000461 U	0.00146 U	**0.000530 J**
	B-247-30	4/20/18	PES	ESC	30	9.7	S	0.00516 U	0.000332 U	0.00151 U	0.000264 U	0.000225 U	0.0110 U	0.00197 U	0.000297 U	0.000313 U	0.000430 U	0.000467 U	0.00148 U	**0.000405 J**
	B-247-35	4/20/18	PES	ESC	35	4.7	S	0.00516 U	0.000332 U	0.00151 U	0.000265 U	0.000225 U	0.0110 U	0.00197 U	0.000298 U	0.000313 U	0.000430 U	0.000467 U	0.00148 U	**0.000526 J**
	B-247-40	4/20/18	PES	ESC	40	-0.3	S	0.00525 U	0.000338 U	0.00154 U	0.000269 U	0.000229 U	**0.0152 J**	0.00201 U	0.000303 U	0.000319 U	0.000438 U	0.000476 U	0.00150 U	**0.000876 J**
	B-247-45	4/20/18	PES	ESC	45	-5.3	S	0.00506 U	0.000325 U	**0.00220 J**	0.000259 U	0.000220 U	**0.0251 J**	0.00193 U	0.000292 U	0.000307 U	0.000421 U	0.000458 U	0.00145 U	**0.00219**
	B-247-50	4/20/18	PES	ESC	50	-10.3	S	0.00515 U	0.000331 U	0.00151 U	0.000264 U	0.000225 U	0.0110 U	0.00197 U	0.000297 U	0.000313 U	0.000429 U	0.000467 U	0.00148 U	**0.000811 J**
	B-247-55	4/20/18	PES	ESC	55	-15.3	S	0.00529 U	0.000340 U	0.00155 U	0.000271 U	0.000230 U	0.0113 U	0.00202 U	0.000305 U	0.000321 U	0.000441 U	0.000479 U	0.00151 U	**0.000350 J**
	B-247-60	4/20/18	PES	ESC	60	-20.3	S	0.00504 U	0.000324 U	0.00148 U	0.000259 U	0.000220 U	0.0108 U	0.00193 U	0.000291 U	0.000306 U	0.000420 U	0.000457 U	0.00144 U	**0.000401 J**
	B-247-65	4/20/18	PES	ESC	65	-25.3	S	0.00522 U	0.000336 U	0.00153 U	0.000268 U	0.000228 U	0.0112 U	0.00200 U	**0.000434 J**	0.000317 U	0.000435 U	0.000473 U	0.00149 U	**0.000337 J**
	B-247-70	4/20/18	PES	ESC	70	-30.3	S	0.00524 U	0.000337 U	0.00154 U	0.000269 U	0.000229 U	0.0112 U	0.00201 U	0.000303 U	0.000318 U	0.000437 U	0.000475 U	0.00150 U	**0.000273 J**
	B-247-75	4/20/18	PES	ESC	75	-35.3	S	0.00535 U	0.000344 U	0.00157 U	0.000275 U	0.000233 U	0.0114 U	0.00205 U	0.000309 U	0.000325 U	0.000446 U	0.000485 U	0.00153 U	**0.000285 J**
	B-247-80	4/20/18	PES	ESC	80	-40.3	S	0.00523 U	0.000336 U	0.00153 U	0.000268 U	0.000228 U	0.0112 U	0.00200 U	0.000302 U	0.000317 U	0.000436 U	0.000474 U	0.00150 U	**0.000400 J**
	B-909-20	4/20/18	PES	ESC	80 (dup)	-40.3	S	0.00507 U	0.000326 U	0.00148 U	0.000260 U	0.000221 U	0.0108 U	0.00194 U	0.000292 U	0.000307 U	0.000422 U	0.000459 U	0.00145 U	**0.000540 J**
B-248	B-248-5	4/23/18	PES	ESC	5	46.9	V	0.00534 U	0.000344 U	0.00156 U	0.000274 U	0.000233 U	**0.0226 J**	0.00204 U	0.000308 U	0.000324 U	0.000445 U	0.000484 U	0.00153 U	0.000252 U
	B-248-10	4/23/18	PES	ESC	10	41.9	V	0.00522 U	0.000336 U	0.00153 U	0.000268 U	0.000227 U	0.0112 U	0.00200 U	0.000301 U	0.000317 U	0.000435 U	0.000473 U	0.00149 U	0.000246 U
	B-248-15	4/23/18	PES	ESC	15	36.9	V	0.0137 U	0.00101 U	0.0110 U	0.00124 U	0.00256 U	0.0151 U	0.00209 U	0.000440 U	0.00115 U	0.00124 U	0.00658 U	0.00407 U	0.00447 U
	B-248-20	4/23/18	PES	ESC	20	31.9	S	0.00506 U	0.000326 U	0.00148 U	0.000260 U	0.000221 U	0.0108 U	0.00194 U	0.000292 U	0.000307 U	0.000422 U	0.000459 U	0.00145 U	**0.000274 J**
	B-248-25	4/23/18	PES	ESC	25	26.9	S	0.0147 U	0.00108 U	0.0117 U	0.00133 U	0.00273 U	0.0161 U	0.00223 U	0.000469 U	0.00123 U	0.00133 U	0.00702 U	0.00434 U	0.00476 U
	B-248-30	4/23/18	PES	ESC	30	21.9	S	0.00506 U	0.000325 U	0.00148 U	0.000259 U	0.000221 U	0.0108 U	0.00194 U	0.000292 U	0.000307 U	0.000422 U	0.000458 U	0.00145 U	0.000239 U
	B-248-35	4/23/18	PES	ESC	35	16.9	S	0.0135 U	0.000997 U	0.0108 U	0.00122 U	0.00252 U	0.0148 U	0.00206 U	**0.000442 J**	0.00114 U	0.00122 U	0.00648 U	0.00401 U	0.00440 U
	B-248-40	4/23/18	PES	ESC	40	11.9	S	0.0139 U	0.00103 U	0.0111 U	0.00126 U	0.00260 U	0.0153 U	0.00212 U	**0.000463 J**	0.00117 U	0.00126 U	0.00667 U	0.00413 U	0.00453 U
	B-248-45	4/23/18	PES	ESC	45	6.9	S	**0.0279 J**	0.00105 U	0.0114 U	0.00129 U	0.00266 U	0.0156 U	0.00217 U	**0.000865 J**	0.00120 U	0.00129 U	0.00683 U	0.00423 U	0.00464 U
	B-248-50	4/23/18	PES	ESC	50	1.9	S	0.0137 U	0.00101 U	**0.0928**	0.00124 U	0.00255 U	**11.3 J**	0.00208 U	**0.000945 J-**	0.00115 U	0.00124 U	0.00654 U	0.00405 U	0.00444 U
	B-248-55	4/23/18	PES	ESC	55	-3.2	S	**0.0534**	0.000356 U	0.00162 U	0.000284 U	0.000241 U	**0.251**	0.00212 U	0.000320 U	0.000336 U	0.000462 U	0.000502 U	0.00159 U	**0.000573 J**
	B-248-60	4/23/18	PES	ESC	60	-8.2	S	0.0134 U	0.000986 U	0.0107 U	0.00121 U	0.00250 U	0.147 U	0.00204 U	**0.000549 J**	0.00113 U	0.00121 U	0.00641 U	0.00397 U	0.00435 U
	B-248-65	4/23/18	PES	ESC	65	-13.2	S	0.0154 U	0.00113 U	0.0123 U	0.00139 U	0.00287 U	0.0169 U	0.00234 U	0.000492 U	0.00129 U	0.00139 U	0.00736 U	0.00455 U	0.00499 U
	B-248-70	4/23/18	PES	ESC	70	-18.2	S	0.0144 U	0.00106 U	0.0115 U	0.00130 U	0.00268 U	0.0157 U	0.00218 U	0.000460 U	0.00121 U	0.00130 U	0.00687 U	0.00425 U	0.00467 U
	B-248-75	4/23/18	PES	ESC	75	-23.2	S	0.0140 U	0.00103 U	0.0112 U	0.00127 U	0.00262 U	0.0154 U	0.00213 U	0.000449 UJ	0.00118 U	0.00127 U	0.00672 U	0.00416 U	0.00456 U
	B-248-80	4/23/18	PES	ESC	80	-28.2	S	0.00562 U	0.000362 U	0.00165 U	0.000288 U	0.000245 U	**0.0184 J**	0.00215 U	0.000324 U	0.000341 U	0.000469 U	0.000509 U	0.00161 U	**0.000528 J**
	B-910-20	4/23/18	PES	ESC	80 (dup)	-28.2	S	0.00578 U	0.000371 U	0.00169 U	0.000296 U	0.000252 U	**0.0125 J**	0.00221 U	0.000333 U	0.000350 U	0.000481 U	0.000523 U	0.00165 U	0.000273 U
	B-248-85	4/23/18	PES	ESC	85	-33.2	S	0.00568 U	0.000365 U	0.00166 U	0.000291 U	0.000248 U	0.0121 U	0.00217 U	0.000328 U	0.000345 U	0.000474 U	0.000515 U	0.00163 U	**0.000577 J**
	B-248-90	4/23/18	PES	ESC	90	-38.2	S	0.00560 U	0.000360 U	0.00164 U	0.000287 U	0.000244 U	0.0120 U	0.00214 U	0.000323 U	0.000340 U	0.000466 U	0.000507 U	0.00160 U	**0.000323 J**
	B-248-95	4/23/18	PES	ESC	95	-43.2	S	0.00583 U	0.000375 U	0.00171 U	0.000299 U	0.000254 U	**0.0253 J**	0.00223 U	0.000337 U	0.000354 U	0.000486 U	0.000529 U	0.00167 U	0.000276 U
	B-248-100	4/23/18	PES	ESC	100	-48.2	S	0.00568 U	0.000365 U	0.00166 U	0.000291 U	0.000247 U	0.0121 U	0.00217 U	0.000328 U	0.000345 U	0.000473 U	0.000514 U	0.00163 U	**0.000422 J**
	B-248-105	4/23/18	PES	ESC	105	-53.2	S	0.00506 U	0.000325 U	0.00148 U	0.000259 U	0.000220 U	**0.0188 J**	0.00193 U	0.000292 U	0.000307 U	0.000421 U	0.000458 U	0.00145 U	0.000239 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
B-248	B-248-110	4/23/18	PES	ESC	110	-58.2	S	0.0143 U	0.00106 U	0.0115 U	0.00130 U	0.00267 U	0.0157 U	0.00218 U	0.000459 U	0.00120 U	0.00130 U	0.00686 U	0.00425 U	0.00466 U
(continued)	B-248-115	4/23/18	PES	ESC	115	-63.2	S	0.00547 U	0.000352 U	0.00160 U	0.000281 U	0.000239 U	**0.0124 J**	0.00209 U	0.000316 U	0.000332 U	0.000456 U	0.000496 U	0.00157 U	0.000258 U
B-249	B-249-5	10/15/18	PES	PACE	5	34.2	S	0.0131 U	0.000961 U	0.0105 U	0.00118 U	0.00243 U	0.0143 U	0.00199 U	0.000418 U	0.00110 U	0.00118 U	0.00625 U	0.00387 U	0.00424 U
	B-249-8	10/15/18	PES	PACE	8	31.2	S	0.0141 U	0.00104 U	0.0113 U	0.00128 U	0.00263 U	0.0155 U	0.00214 U	0.000451 U	0.00118 U	0.00128 U	0.00675 U	0.00418 U	0.00458 U
	B-249-15	10/15/18	PES	PACE	15	24.2	S	0.0145 U	0.00107 U	0.0116 U	0.00131 U	0.00270 U	0.127 U	0.00220 U	0.000463 U	0.00122 U	0.00131 U	0.00693 U	0.00429 U	0.00470 U
	B-249-17	10/15/18	PES	PACE	17	22.2	S	0.0142 U	0.00104 U	0.0113 U	0.00128 U	0.00264 U	0.621 U	0.00215 U	0.000453 U	0.00119 U	0.00128 U	0.00677 U	0.00419 U	0.00460 U
	B-249-20	10/15/18	PES	PACE	20	19.2	S	0.0148 U	0.00109 U	0.0118 U	0.00134 U	0.00275 U	11.3 U	0.00224 U	0.000473 U	0.00124 U	0.00134 U	0.00707 U	0.00437 U	0.00480 U
B-250	B-250-2.5	10/15/18	PES	PACE	2.5	36.9	V	0.0138 U	0.00102 U	0.0110 U	0.00125 U	0.00257 U	0.0151 U	0.00210 U	0.000442 U	0.00116 U	0.00125 U	0.00660 U	0.00409 U	0.00448 U
	B-250-8	10/15/18	PES	PACE	8	31.4	S	0.0139 U	0.00102 U	0.0111 U	0.00126 U	0.00259 U	0.122 U	0.00212 U	0.000445 U	0.00117 U	0.00126 U	0.00666 U	0.00412 U	0.00452 U
	B-250-10	10/15/18	PES	PACE	10	29.4	S	0.0139 U	0.00102 U	0.0111 U	0.00126 U	0.00259 U	1.22 U	0.00211 U	0.000445 U	0.00117 U	0.00126 U	0.00665 U	0.00412 U	0.00452 U
	B-250-13	10/15/18	PES	PACE	13	26.4	S	0.0140 U	0.00103 U	0.0112 U	0.00127 U	0.00262 U	1.24 U	0.00213 U	0.000449 U	0.00118 U	0.00127 U	0.00672 U	0.00416 U	0.00456 U
	B-250-20	10/15/18	PES	PACE	20	19.4	S	0.0145 U	0.00107 U	0.0116 U	0.00131 U	0.00270 U	0.635 U	0.00220 U	0.000463 U	0.00122 U	0.00131 U	0.00693 U	0.00429 U	0.00470 U
	B-250-24	10/15/18	PES	PACE	24	15.4	S	0.0137 U	0.00101 U	0.0109 U	0.00124 U	0.00255 U	10.0 U	0.00208 U	0.000438 U	0.00115 U	0.00124 U	0.00654 U	0.00405 U	0.00444 U
	B-250-30	10/16/18	PES	PACE	30	9.4	S	**0.0327**	0.00100 U	0.0109 U	0.00123 U	0.00254 U	0.0149 U	0.00207 U	0.000436 U	0.00115 U	0.00123 U	0.00652 U	0.00403 U	0.00443 U
B-251	B-251-5	10/15/18	PES	PACE	5	34.3	S	0.0131 U	0.000967 U	0.0105 U	0.00119 U	0.00245 U	0.0144 U	0.00200 U	0.000420 U	0.00110 U	0.00119 U	0.00628 U	0.00389 U	0.00427 U
	B-251-8	10/15/18	PES	PACE	8	31.3	S	**0.0603 J**	0.00102 U	0.0111 U	0.00125 U	0.00258 U	0.0152 U	0.00211 U	0.000444 U	0.00116 U	0.00125 U	0.00663 U	0.00410 U	0.00450 U
	B-251-10	10/15/18	PES	PACE	10	29.3	S	0.556 U	0.00102 U	0.0111 U	0.00126 U	0.00259 U	0.0152 U	0.00211 U	0.000445 U	0.00117 U	0.00126 U	0.00665 U	0.00412 U	0.00452 U
	B-251-15	10/15/18	PES	PACE	15	24.3	S	0.565 U	0.00104 U	0.0113 U	0.00128 U	0.00263 U	0.0155 U	0.00215 U	0.000452 U	0.00119 U	0.00128 U	0.00676 U	0.00418 U	0.00459 U
	B-251-20	10/15/18	PES	PACE	20	19.3	S	0.586 U	0.00108 U	0.0117 U	0.00132 U	0.00273 U	**0.0178 J**	0.00222 U	0.000468 U	0.00123 U	0.00132 U	0.00700 U	0.00433 U	0.00475 U
	B-251-25	10/15/18	PES	PACE	25	14.3	S	0.0144 U	0.00106 U	0.0115 U	0.00130 U	0.00268 U	13.1 U	0.00218 U	0.000459 U	0.00121 U	0.00130 U	0.00687 U	0.00425 U	0.00466 U
B-252	B-252-2.5	10/15/18	PES	PACE	2.5	36.7	V	**0.0516 J**	0.000961 U	0.0104 U	0.00118 U	0.00243 U	0.0143 U	0.00199 U	0.000418 U	0.00110 U	0.00118 U	0.00625 U	0.00387 U	0.00424 U
	B-252-8	10/15/18	PES	PACE	8	31.2	S	**0.0507 J**	0.000984 U	0.0107 U	0.00121 U	0.00249 U	0.0147 U	0.00203 U	0.000428 U	0.00112 U	0.00121 U	0.00640 U	0.00396 U	0.00434 U
	B-252-10	10/15/18	PES	PACE	10	29.2	S	**0.0333 J**	0.00102 U	0.0111 U	0.00125 U	0.00258 U	0.0152 U	0.00211 U	0.000443 U	0.00116 U	0.00125 U	0.00663 U	0.00410 U	0.00450 U
	B-252-15	10/15/18	PES	PACE	15	24.2	S	0.295 U	0.00108 U	0.0118 U	0.00133 U	0.00275 U	0.0161 U	0.00224 U	0.000471 U	0.00124 U	0.00133 U	0.00705 U	0.00436 U	0.00478 U
	B-252-19	10/15/18	PES	PACE	19	20.2	S	0.151 U	0.00111 U	0.0121 U	0.00136 U	0.00281 U	0.0165 U	0.00229 U	0.000483 U	0.00127 U	0.00136 U	0.00722 U	0.00447 U	0.00490 U
	B-252-25	10/15/18	PES	PACE	25	14.2	S	0.0549 U	0.00101 U	0.0110 U	0.00124 U	0.00256 U	0.0150 U	0.00209 U	0.000439 U	0.00115 U	0.00124 U	0.00657 U	0.00406 U	0.00446 U
	B-252-29	10/15/18	PES	PACE	29	10.2	S	0.0143 U	0.00105 U	0.0114 U	0.00129 U	0.00267 U	2.75 U	0.00217 U	0.000458 U	0.00120 U	0.00129 U	0.00684 U	0.00423 U	0.00465 U
B-253A	B-253A-5	10/18/18	PES	PACE	5	35.6	V	**0.0408**	0.00105 U	0.0114 U	0.00129 U	0.00265 U	0.0156 U	0.00216 U	0.000456 U	0.00120 U	0.00129 U	0.00681 U	0.00421 U	0.00462 U
	B-253A-8	10/18/18	PES	PACE	8	32.6	S	0.0563 U	0.00104 U	0.0113 U	0.00127 U	0.00262 U	0.0617 U	0.00214 U	0.000451 U	0.00118 U	0.00127 U	0.00673 U	0.00417 U	0.00457 U
	B-253A-10	10/18/18	PES	PACE	10	30.6	S	0.137 U	0.00101 U	0.0110 U	0.00124 U	0.00255 U	0.150 U	0.00208 U	0.000438 U	0.00115 U	0.00124 U	0.00655 U	0.00405 U	0.00445 U
	B-253A-15	10/18/18	PES	PACE	15	25.6	S	1.12 U	0.00103 U	0.0112 U	0.00127 U	0.00262 U	1.24 U	0.00213 U	0.000449 U	0.00118 U	0.00127 U	0.00671 U	0.00415 U	0.00456 U
	B-253A-20	10/18/18	PES	PACE	20	20.6	S	0.0551 U	0.00101 U	0.0110 U	0.00124 U	0.00257 U	0.0604 U	0.00209 U	0.000441 U	0.00116 U	0.00124 U	0.00659 U	0.00408 U	0.00447 U
B-254	B-254-5	10/16/18	PES	PACE	5	34.7	S	**0.0513**	0.00110 U	0.0120 U	0.00135 U	0.00279 U	1.32 U	0.00228 U	0.000479 U	0.00126 U	0.00135 U	0.00716 U	0.00443 U	0.00486 U
	B-254-10	10/16/18	PES	PACE	10	29.7	S	**0.0249**	0.00104 U	0.0114 U	0.00128 U	0.00265 U	0.125 U	0.00216 U	0.000454 U	0.00119 U	0.00128 U	0.00679 U	0.00420 U	0.00461 U
	B-254-13.5	10/16/18	PES	PACE	13.5	26.2	S	**0.0321**	0.00108 U	0.0117 U	0.00133 U	0.00273 U	6.43 U	0.00223 U	0.000469 U	0.00123 U	0.00133 U	0.00701 U	0.00434 U	0.00476 U
	B-254-20	10/16/18	PES	PACE	20	19.7	S	**0.0314**	0.000990 U	0.0108 U	0.00122 U	0.00251 U	2.95 U	0.00204 U	0.000430 U	0.00113 U	0.00122 U	0.00643 U	0.00398 U	0.00437 U
	B-254-25	10/16/18	PES	PACE	25	14.7	S	**0.0313**	0.00103 U	0.0112 U	0.00126 U	0.00260 U	6.12 U	0.00212 U	0.000447 U	0.00117 U	0.00126 U	0.00668 U	0.00413 U	0.00454 U
B-254A	B-254A-27	10/19/18	PES	PACE	27	12.7	S	**0.0430 J**	0.00100 U	0.0109 U	0.00123 U	0.00254 U	0.0149 U	0.00208 U	0.000437 U	0.00115 U	0.00123 U	0.00653 U	0.00404 U	**0.00592 J**
	B-254A-30	10/19/18	PES	PACE	30	9.7	S	0.0135 U	0.000990 U	0.0108 U	0.00122 U	0.00251 U	0.147 U	0.00204 U	0.000430 U	0.00113 U	0.00122 U	0.00644 U	0.00398 U	**0.00619 J**
	B-254A-35	10/19/18	PES	PACE	35	4.7	S	**0.0250**	0.000969 U	0.0105 U	0.00119 U	0.00245 U	0.0144 U	0.00200 U	0.000421 UJ	0.00111 U	0.00119 U	0.00630 U	0.00390 U	0.00428 U
B-255	B-255-3.5	10/16/18	PES	PACE	3.5	36.3	S	**0.0274**	0.00105 U	0.0114 U	0.00129 U	0.00266 U	0.0156 U	0.00217 U	0.000457 U	0.00120 U	0.00129 U	0.00683 U	0.00423 U	0.00464 U
	B-255-8	10/16/18	PES	PACE	8	31.8	S	**0.0328**	0.00107 U	0.0116 U	0.00131 U	0.00270 U	0.0159 U	0.00220 U	0.000463 U	0.00122 U	0.00131 U	0.00693 U	0.00429 U	0.00470 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
B-255 (continued)	B-255-15	10/16/18	PES	PACE	15	24.8	S	**0.0295**	0.00100 U	0.0109 U	0.00123 U	0.00254 U	0.0149 U	0.00207 U	0.000436 U	0.00114 U	0.00123 U	0.00652 U	0.00403 U	0.00442 U
B-255A	B-255A-21	10/16/18	PES	PACE	21	18.8	S	**0.0330**	0.000974 U	0.0106 U	0.00120 U	0.00247 U	0.580 U	0.00201 U	0.000423 U	0.00111 U	0.00120 U	0.00633 U	0.00392 U	0.00430 U
B-256	B-256-2.5	10/16/18	PES	PACE	2.5	37.1	S	**0.0576**	0.00108 U	0.0117 U	0.00132 U	0.00272 U	0.0160 U	0.00222 U	0.000468 U	0.00123 U	0.00132 U	0.00699 U	0.00433 U	0.00475 U
	B-256-5	10/16/18	PES	PACE	5	34.6	S	**0.0448**	0.00102 U	0.0110 U	0.00125 U	0.00257 U	0.0151 U	0.00210 U	0.000442 U	0.00116 U	0.00125 U	0.00661 U	0.00409 U	0.00449 U
	B-256-10	10/16/18	PES	PACE	10	29.6	S	**0.0312**	0.000983 U	0.0107 U	0.00121 U	0.00249 U	0.0146 U	0.00203 U	0.000427 U	0.00112 U	0.00121 U	0.00639 U	0.00395 U	0.00434 U
	B-256-15	10/16/18	PES	PACE	15	24.6	S	**0.0292**	0.00102 U	0.0111 U	0.00125 U	0.00258 U	0.0152 U	0.00210 U	0.000443 U	0.00116 U	0.00125 U	0.00662 U	0.00409 U	0.00449 U
	B-256-18	10/16/18	PES	PACE	18	21.6	S	0.0138 U	0.00102 U	0.0111 U	0.00125 U	0.00258 U	0.0152 U	0.00210 U	0.000443 U	0.00116 U	0.00125 U	0.00662 U	0.00409 U	0.00449 U
B-257	B-257-5	10/17/18	PES	PACE	5	34.4	S	**0.0553**	0.00111 U	0.0121 U	0.00137 U	0.00282 U	0.0166 U	0.00230 U	0.000484 U	0.00127 U	0.00137 U	0.00724 U	0.00448 U	0.00492 U
	B-257-10	10/17/18	PES	PACE	10	29.4	S	**0.0232**	0.00103 U	0.0112 U	0.00126 U	0.00260 U	0.0153 U	0.00212 U	0.000447 U	0.00117 U	0.00126 U	0.00668 U	0.00413 U	0.00453 U
	B-257-15	10/17/18	PES	PACE	15	24.4	S	**0.0225**	0.00107 U	0.0116 U	0.00131 U	0.00271 U	0.0159 U	0.00221 U	0.000465 U	0.00122 U	0.00131 U	0.00695 U	0.00430 U	0.00472 U
	B-257-20	10/17/18	PES	PACE	20	19.4	S	**0.0273**	0.00103 U	0.0112 U	0.00127 U	0.00262 U	0.124 U	0.00214 U	0.000450 U	0.00118 U	0.00127 U	0.00672 U	0.00416 U	0.00456 U
B-258	B-258-3	10/17/18	PES	PACE	3	36.2	V	**0.0293**	0.00101 U	0.0110 U	0.00124 U	0.00255 U	0.0150 U	0.00208 U	0.000438 U	0.00115 U	0.00124 U	0.00655 U	0.00405 U	0.00445 U
	B-258-8	10/17/18	PES	PACE	8	31.2	S	**0.0301**	0.00105 U	0.0114 U	0.00129 U	0.00265 U	0.0156 U	0.00216 U	0.000455 U	0.00119 U	0.00129 U	0.00680 U	0.00421 U	0.00462 U
	B-258-10	10/17/18	PES	PACE	10	29.2	S	**0.0268 J**	0.00110 U	0.0120 U	0.00135 U	0.00279 U	0.0164 U	0.00227 U	0.000479 U	0.00126 U	0.00135 U	0.00716 U	0.00443 U	0.00486 U
	B-258-15	10/17/18	PES	PACE	15	24.2	S	**0.0343**	0.00109 U	0.0118 U	0.00133 U	0.00275 U	0.0162 U	0.00224 U	0.00944 U	0.00124 U	0.00133 U	0.00706 U	0.00437 U	0.00479 U
	B-258-20	10/17/18	PES	PACE	20	19.2	S	**0.0211 J**	0.00103 U	0.0112 U	0.00126 U	0.00260 U	0.0153 U	0.00212 U	0.000446 U	0.00117 U	0.00126 U	0.00667 U	0.00413 U	0.00453 U
B-259	B-259-2.5	10/17/18	PES	PACE	2.5	36.7	V	**0.0274 J**	0.00104 U	0.0113 U	0.00127 U	0.00262 U	0.0154 U	0.00214 U	0.000450 U	0.00118 U	0.00127 U	0.00673 U	0.00416 U	0.00457 U
	B-259-5	10/17/18	PES	PACE	5	34.2	S	**0.0348**	0.00101 U	0.0110 U	0.00124 U	0.00255 U	0.0150 U	0.00208 U	0.000438 U	0.00115 U	0.00124 U	0.00655 U	0.00405 U	0.00445 U
	B-259-10	10/17/18	PES	PACE	10	29.2	S	**0.0255 J**	0.00105 U	0.0115 U	0.00129 U	0.00267 U	0.0157 U	0.00218 U	0.000458 U	0.00120 U	0.00129 U	0.00685 U	0.00424 U	0.00465 U
	B-259-15	10/17/18	PES	PACE	15	24.2	S	**0.0272 J**	0.00108 U	0.0117 U	0.00133 U	0.00274 U	0.0161 U	0.00223 U	0.000470 U	0.00123 U	0.00133 U	0.00702 U	0.00434 U	0.00477 U
	B-259-20	10/17/18	PES	PACE	20	19.2	S	**0.0198 J**	0.00103 U	0.0112 U	0.00126 U	0.00260 U	0.0153 U	0.00212 U	0.000447 U	0.00117 U	0.00126 U	0.00668 U	0.00414 U	0.00454 U
B-260	B-260-5	10/17/18	PES	PACE	5	34.2	S	**0.0209 J**	0.00102 U	0.0111 U	0.00125 U	0.00258 U	0.0152 U	0.00211 U	0.000444 U	0.00116 U	0.00125 U	0.00663 U	0.00410 U	0.00450 U
	B-260-8	10/17/18	PES	PACE	8	31.2	S	**0.0348**	0.00103 U	0.0112 U	0.00127 U	0.00261 U	0.0154 U	0.00213 U	0.000449 UJ	0.00118 U	0.00127 U	0.00671 U	0.00415 U	0.00456 U
	B-260-10	10/17/18	PES	PACE	10	29.2	S	**0.0241 J**	0.00106 U	0.0115 U	0.00130 U	0.00267 U	0.0157 U	0.00218 U	0.000459 U	0.00120 U	0.00130 U	0.00686 U	0.00425 U	0.00466 U
	B-260-15	10/17/18	PES	PACE	15	24.2	S	**0.0288 J**	0.00107 U	0.0116 U	0.00131 U	0.00271 U	0.0159 U	0.00221 U	0.00465 U	0.00122 U	0.00131 U	0.00694 U	0.00430 U	0.00471 U
	B-260-20	10/17/18	PES	PACE	20	19.2	S	**0.0234 J**	0.00102 U	0.0111 U	0.00125 U	0.00258 U	0.0151 U	0.00210 U	0.00442 U	0.00116 U	0.00125 U	0.00661 U	0.00409 U	0.00449 U
B-261	B-261-3	10/17/18	PES	PACE	3	36.9	S	**0.0385**	0.00105 U	0.0114 U	0.00129 U	0.00266 U	0.0157 U	0.00217 U	0.000457 U	0.00120 U	0.00129 U	0.00683 U	0.00423 U	0.00464 U
	B-261-5	10/17/18	PES	PACE	5	34.9	S	**0.0396**	0.00104 U	0.0113 U	0.00128 U	0.00264 U	0.0155 U	0.00215 U	0.0362 U	0.00119 U	0.00128 U	0.00677 U	0.00419 U	0.00460 U
	B-261-8	10/17/18	PES	PACE	8	31.9	S	**0.0558**	0.00110 U	0.0120 U	0.00135 U	0.00279 U	0.0164 U	0.00228 U	0.00479 U	0.00126 U	0.00135 U	0.00717 U	0.00443 U	0.00487 U
	B-261-10	10/17/18	PES	PACE	10	29.9	S	**0.0333**	0.00106 U	0.0115 U	0.00130 U	0.00268 U	0.0158 U	0.00219 U	0.0184 U	0.00121 U	0.00130 U	0.00689 U	0.00426 U	0.00468 U
	B-261-15	10/17/18	PES	PACE	15	24.9	S	**0.0179 J**	0.00101 U	0.0110 U	0.00124 U	0.00256 U	0.0151 U	0.00209 U	0.00879 U	0.00115 U	0.00124 U	0.00657 U	0.00407 U	0.00446 U
	B-261-20	10/17/18	PES	PACE	20	19.9	S	**0.0256 J**	0.00103 U	0.0112 U	0.00127 U	**0.00394 J**	0.0154 U	0.00214 U	0.0899 U	0.00118 U	0.00127 U	0.00672 U	0.00416 U	0.00456 U
B-262	B-262-5	10/17/18	PES	PACE	5	34.9	S	**0.0207 J**	0.00108 U	0.0118 U	0.00133 U	0.00274 U	1.30 U	0.00224 U	0.000471 U	0.00124 U	0.00133 U	0.00704 U	0.00436 U	0.00478 U
	B-262-8	10/17/18	PES	PACE	8	31.9	S	0.0137 U	0.00101 U	0.0110 U	0.00124 U	0.00256 U	**0.0214 J**	0.00209 U	0.000440 U	0.00115 U	0.00124 U	0.00658 U	0.00407 U	0.00447 U
	B-262-10	10/17/18	PES	PACE	10	29.9	S	**0.0232 J**	0.00102 U	0.0111 U	0.00126 U	0.00259 U	0.0153 U	0.00212 U	0.000445 U	0.00117 U	0.00126 U	0.00666 U	0.00412 U	0.00452 U
	B-262-15	10/17/18	PES	PACE	15	24.9	S	**0.0236 J**	0.00101 U	0.0110 U	0.00124 U	0.00256 U	0.0150 U	0.00209 U	0.000439 U	0.00115 U	0.00124 U	0.00656 U	0.00406 U	0.00446 U
	B-262-20	10/17/18	PES	PACE	20	19.9	S	0.0147 U	0.00108 U	0.0118 U	0.00133 U	0.00274 U	0.161 U	0.00224 U	0.000471 U	0.00124 U	0.00133 U	0.00704 U	0.00436 U	0.00478 U
B-263	B-263-3	10/18/18	PES	PACE	3	36.8	S	**0.0386**	0.00113 U	0.0122 U	0.00138 U	0.00285 U	0.0168 U	0.00233 U	0.000490 U	0.00129 U	0.00138 U	0.00732 U	0.00453 U	0.00497 U
	B-263-5	10/18/18	PES	PACE	5	34.8	S	**0.0253 J**	0.000994 U	0.0108 U	0.00122 U	0.00252 U	0.0148 U	0.00205 U	0.000432 U	0.00113 U	0.00122 U	0.00646 U	0.00400 U	0.00439 U
	B-263-8	10/18/18	PES	PACE	8	31.8	S	**0.0258 J**	0.000970 U	0.0105 U	0.00119 U	0.00246 U	0.0145 U	0.00200 U	0.000422 U	0.00111 U	0.00119 U	0.00631 U	0.00390 U	0.00428 U
	B-263-10	10/18/18	PES	PACE	10	29.8	S	**0.0289**	0.00105 U	0.0114 U	0.00129 U	0.00265 U	0.0156 U	0.00216 U	0.000455 U	0.00119 U	0.00129 U	0.00681 U	0.00421 U	0.00462 U
	B-263-15	10/18/18	PES	PACE	15	24.8	S	**0.0228 J**	0.00100 U	0.0109 U	0.00123 U	0.00254 U	0.0150 U	0.00207 U	0.000437 U	0.00115 U	0.00123 U	0.00653 U	0.00404 U	**0.00546 J**

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
B-263 (continued)	B-263-18	10/18/18	PES	PACE	18	21.8	S	**0.0287**	0.000998 U	0.0108 U	0.00123 U	0.00253 U	0.0149 U	0.00206 U	0.000434 U	0.00114 U	0.00123 U	0.00649 U	0.00401 U	0.00440 U
B-264	B-264-3	10/18/18	PES	PACE	3	36.8	S	0.0136 U	0.000999 U	0.0109 U	0.00123 U	0.00253 U	0.0149 U	0.00206 U	0.000434 U	0.00114 U	0.00123 U	0.00649 U	0.00402 U	0.00441 U
	B-264-5	10/18/18	PES	PACE	5	34.8	S	**0.0277 J**	0.00106 U	0.0116 U	0.00131 U	0.00270 U	0.0159 U	0.00220 U	0.000463 U	0.00122 U	0.00131 U	0.00692 U	0.00428 U	0.00470 U
	B-264-8	10/18/18	PES	PACE	8	31.8	S	0.0143 U	0.00105 U	0.0114 U	0.00129 U	0.00266 U	0.0157 U	0.00217 U	0.000457 U	0.00120 U	0.00129 U	0.00683 U	0.00423 U	0.00464 U
	B-264-10	10/18/18	PES	PACE	10	29.8	S	**0.0274 J**	0.00101 U	0.0110 U	0.00124 U	0.00257 U	0.0151 U	0.00209 U	0.000441 U	0.00116 U	0.00124 U	0.00659 U	0.00408 U	0.00447 U
	B-264-15	10/18/18	PES	PACE	15	24.8	S	**0.0402**	0.00107 U	0.0116 U	0.00131 U	0.00271 U	0.0159 U	0.00221 U	0.000465 U	0.00122 U	0.00131 U	0.00696 U	0.00430 U	0.00472 U
	B-264-16	10/18/18	PES	PACE	16	23.8	S	**0.0297**	0.00103 U	0.0112 U	0.00127 U	0.00262 U	0.0154 U	0.00213 U	**0.00115**	0.00118 U	0.00127 U	0.00671 U	0.00415 U	0.00456 U
B-265	B-265-3	10/18/18	PES	PACE	3	36.8	S	**0.0676**	0.00110 U	0.0119 U	0.00135 U	0.00278 U	0.0163 U	0.00227 U	0.000477 U	0.00125 U	0.00135 U	0.00714 U	0.00442 U	0.00485 U
	B-265-5	10/18/18	PES	PACE	5	34.8	S	0.145 U	0.00107 U	0.0116 U	0.00131 U	0.00270 U	0.159 U	0.00220 U	0.000464 U	0.00122 U	0.00131 U	0.00693 U	0.00429 U	0.00470 U
	B-265-8	10/18/18	PES	PACE	8	31.8	S	0.140 U	0.00103 U	0.0112 U	0.00126 U	0.00260 U	0.153 U	0.00212 U	0.000447 U	0.00117 U	0.00126 U	0.00668 U	0.00413 U	0.00453 U
	B-265-10	10/18/18	PES	PACE	10	29.8	S	0.110 U	0.00101 U	0.0110 U	0.00124 U	0.00256 U	0.121 U	0.00209 U	0.000440 U	0.00115 U	0.00124 U	0.00657 U	0.00407 U	0.00446 U
	B-265-17.5	10/18/18	PES	PACE	18	22.3	S	0.0138 U	0.00102 U	0.0111 U	0.00125 U	0.00258 U	0.0152 U	0.00210 U	0.000443 U	0.00116 U	0.00125 U	0.00662 U	0.00409 U	0.00449 U
B-266	B-266-5	10/18/18	PES	PACE	5	35.7	S	0.0152 U	0.00112 U	0.0122 U	0.00138 U	0.00284 U	**0.0288 J**	0.00232 U	0.000487 U	0.00128 U	0.00138 U	0.00729 U	0.00451 U	0.00495 U
	B-266-8	10/18/18	PES	PACE	8	32.7	S	0.0157 U	0.00117 U	0.0127 U	0.00144 U	0.00296 U	0.0173 U	0.00241 U	0.000509 U	0.00133 U	0.00144 U	0.00761 U	0.00471 U	0.00516 U
	B-266-10	10/18/18	PES	PACE	10	30.7	S	0.0201 U	0.00148 U	0.0161 U	0.00181 U	0.00374 U	0.0220 U	0.00306 U	0.000644 U	0.00169 U	0.00181 U	0.00962 U	0.00596 U	0.00653 U
	B-266-15	10/18/18	PES	PACE	15	25.7	S	0.167 U	0.00123 U	0.0133 U	0.00151 U	0.00310 U	0.183 U	0.00253 U	0.000534 U	0.00140 U	0.00151 U	0.00798 U	0.00493 U	0.00542 U
	B-266-20	10/18/18	PES	PACE	20	20.7	S	0.557 U	0.00103 U	0.0111 U	0.00126 U	0.00260 U	0.611 U	0.00212 U	0.000446 U	0.00117 U	0.00126 U	0.00667 U	0.00412 U	0.00453 U
B-267	B-267-2.5	10/18/18	PES	PACE	2.5	37.4	S	0.0150 U	0.00111 U	0.0120 U	0.00136 U	0.00280 U	0.0165 U	0.00228 U	0.000481 U	0.00126 U	0.00136 U	0.00719 U	0.00445 U	0.00488 U
	B-267-5	10/18/18	PES	PACE	5	34.9	S	0.0136 U	0.00100 U	0.0109 U	0.00123 U	0.00254 U	0.0149 U	0.00207 U	0.000436 U	0.00115 U	0.00123 U	0.00652 U	0.00404 U	0.00443 U
	B-267-8	10/18/18	PES	PACE	8	31.9	S	0.0597 U	0.00110 U	0.0119 U	0.00135 U	0.00278 U	0.0654 U	0.00227 U	0.000477 U	0.00125 U	0.00135 U	0.00713 U	0.00441 U	0.00484 U
	B-267-10	10/18/18	PES	PACE	10	29.9	S	0.0565 U	0.00104 U	0.0113 U	0.00128 U	0.00263 U	0.0619 U	0.00215 U	0.000452 U	0.00119 U	0.00128 U	0.00676 U	0.00418 U	0.00459 U
	B-267-15	10/18/18	PES	PACE	15	24.9	S	0.279 U	0.0206 U	0.224 U	0.0253 U	0.0521 U	0.306 U	0.0425 U	0.00894 U	0.0235 U	0.0253 U	0.134 U	0.0827 U	0.0908 U
	B-267-20	10/18/18	PES	PACE	20	19.9	S	0.310 U	0.0228 U	0.248 U	0.0280 U	0.0579 U	0.341 U	0.0472 U	0.00994 U	0.0261 U	0.0280 U	0.148 U	0.0920 U	0.101 U
CA-A10	CA-A10-21	09/04/19	PES	Fremont	21	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-A12-20	CA-A12-20-24	09/06/19	PES	Fremont	24	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CAA-C1	CAA-C1-43	08/27/19	PES	Fremont	43	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CAA-C2	CAA-C2-10	08/28/19	PES	Fremont	10	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-B8	CA-B8-3	09/16/19	PES	Fremont	3	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-B19	CA-B19-30	09/27/19	PES	Fremont	30	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-B10	CA-B10-17	08/30/19	PES	Fremont	17	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	CA-B10-20	08/30/19	PES	Fremont	20	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	CA-B10-21	08/30/19	PES	Fremont	21	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	CA-B10-25	08/30/19	PES	Fremont	25	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-B11	CA-B11-27	09/05/19	PES	Fremont	27	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-B18	CA-B18-20	10/26/19	PES	Fremont	20	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-B20	CA-B20-31	09/30/19	PES	Fremont	31	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B-1001-31	09/30/19	PES	Fremont	31 (dup)	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-C7	CA-C7-25	09/20/19	PES	Fremont	25	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-C8	CA-C8-35	09/03/19	PES	Fremont	35	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-C9	CA-C9-09	09/04/19	PES	Fremont	9	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-C10	CA-C10-17	09/06/19	PES	Fremont	17	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	CA-C10-26	09/06/19	PES	Fremont	26	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-C13	CA-C13-Comp	09/11/19	PES	Fremont	Comp	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-D1	CA-D1-Comp	09/11/19	PES	Fremont	Comp	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-D2	CA-D2-31	09/16/19	PES	Fremont	31	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	CA-D2-50-52	09/17/19	PES	Fremont	52	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-D3	CA-D3-40	09/23/19	PES	Fremont	40	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-D4	CA-D4-51	09/19/19	PES	Fremont	51	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	CA-D4-54	09/19/19	PES	Fremont	54	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	**–**	**–**	**29**	**0.030**	**0.027**	**0.56**	**–**	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	**–**	**–**	**2.1**	**0.030**	**0.002**	**0.033**	**–**	**0.023**	**0.0033**	**0.27**
CA-D5	CA-D5-14	09/03/19	PES	Fremont	14	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	CA-D5-22	09/03/19	PES	Fremont	22	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	CA-D5-26	09/03/19	PES	Fremont	26	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-D6	CA-D6-56	09/04/19	PES	Fremont	56	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	CA-D6-65	09/04/19	PES	Fremont	65	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CA-D7	CA-D7-15	09/05/19	PES	Fremont	15	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
DB01	DB01-10	3/18/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB01-20	3/18/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB01-30	3/18/13	SES	F&BI	30	10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB01-40	3/18/13	SES	F&BI	40	0.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
DB02	DB02-10	3/18/13	SES	F&BI	10	26.0	S	–	–	–	–	–	–	–	0.020 U	–	–	–	–	–
	DB02-15	3/18/13	SES	F&BI	15	21.0	S	–	–	–	–	–	–	–	0.020 U	–	–	–	–	–
	DB02-20	3/18/13	SES	F&BI	20	16.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB02-30	3/18/13	SES	F&BI	30	6.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB02-40	3/18/13	SES	F&BI	40	-4.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
DB03	DB03-05	3/27/13	SES	F&BI	5	35.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB03-20	3/27/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB03-35	3/27/13	SES	F&BI	35	5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB03-45	3/27/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB03-55	3/27/13	SES	F&BI	55	-15.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB03-60	3/27/13	SES	F&BI	60	-20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
DB04	DB04-10	3/21/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB04-20	3/21/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB04-35	3/21/13	SES	F&BI	35	5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB04-45	3/21/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB04-50	3/22/13	SES	F&BI	50	-10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB04-60	3/22/13	SES	F&BI	60	-20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
DB05	DB05-10	3/26/13	SES	F&BI	10	41.8	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB05-20	3/26/13	SES	F&BI	20	31.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB05-30	3/26/13	SES	F&BI	30	21.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB05-40	3/26/13	SES	F&BI	40	11.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB05-50	3/26/13	SES	F&BI	50	1.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB05-60	3/26/13	SES	F&BI	60	-8.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB05-70	3/26/13	SES	F&BI	70	-18.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
DB06	DB06-10	3/25/13	SES	F&BI	10	41.8	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB06-25	3/25/13	SES	F&BI	25	26.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB06-35	3/25/13	SES	F&BI	35	16.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB06-45	3/25/13	SES	F&BI	45	6.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB06-55	3/25/13	SES	F&BI	55	-3.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB06-65	3/25/13	SES	F&BI	65	-13.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB06-75	3/25/13	SES	F&BI	75	-23.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	**–**	**–**	**29**	**0.030**	**0.027**	**0.56**	**–**	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	**–**	**–**	**2.1**	**0.030**	**0.002**	**0.033**	**–**	**0.023**	**0.0033**	**0.27**
DB07	DB07-05	3/27/13	SES	F&BI	5	35.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB07-15	3/27/13	SES	F&BI	15	25.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB07-25	3/27/13	SES	F&BI	25	15.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB07-35	3/28/13	SES	F&BI	35	5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB07-45	3/28/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB07-50	3/28/13	SES	F&BI	50	-10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB07-60	3/28/13	SES	F&BI	60	-20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB07-70	3/28/13	SES	F&BI	70	-30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
DB08	DB08-10	3/20/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB08-20	3/20/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB08-35	3/20/13	SES	F&BI	35	5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB08-45	3/20/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB08-50	3/21/13	SES	F&BI	50	-10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB08-60	3/21/13	SES	F&BI	60	-20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB08-70	3/21/13	SES	F&BI	70	-30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
DB09	DB09-10	3/19/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB09-20	3/19/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB09-30	3/19/13	SES	F&BI	30	10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB09-40	3/19/13	SES	F&BI	40	0.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB09-50	3/19/13	SES	F&BI	50	-10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB09-60	3/19/13	SES	F&BI	60	-20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB09-70	3/19/13	SES	F&BI	70	-30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
DB10	DB10-10	3/29/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB10-20	3/29/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB10-35	3/29/13	SES	F&BI	35	5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB10-45	3/29/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB10-50	4/1/13	SES	F&BI	50	-10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB10-60	4/1/13	SES	F&BI	60	-20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB10-70	4/1/13	SES	F&BI	70	-30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
DB11	DB11-15	4/2/13	SES	F&BI	15	36.8	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB11-25	4/2/13	SES	F&BI	25	26.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB11-35	4/2/13	SES	F&BI	35	16.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB11-45	4/2/13	SES	F&BI	45	6.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB11-55	4/2/13	SES	F&BI	55	-3.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
DB12	DB12-10	4/3/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB12-20	4/3/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB12-30	4/3/13	SES	F&BI	30	10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB12-40	4/3/13	SES	F&BI	40	0.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
DB13	DB13-10	4/3/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB13-20	4/3/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB13-35	4/3/13	SES	F&BI	35	5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB13-45	4/3/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
DB14	DB14-10	4/4/13	SES	F&BI	10	31.5	S	–	–	–	–	–	–	–	**0.059**	–	–	–	–	–
	DB14-20	4/4/13	SES	F&BI	20	21.5	S	–	–	–	–	–	–	–	0.020 U	–	–	–	–	–
	DB14-30	4/4/13	SES	F&BI	30	11.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	DB14-40	4/4/13	SES	F&BI	40	1.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
G-MW1	MW 1-3-8	7/20/01	GeoEng	NCA	8	31.0	S	–	–	–	–	–	–	–	0.019 U	–	–	–	–	–
	MW 1-8-20	7/20/01	GeoEng	NCA	20	19.0	S	–	–	–	–	–	–	–	0.019 U	–	–	–	–	–
	MW 1-11-27.5	7/20/01	GeoEng	NCA	27.5	11.5	S	–	–	–	–	–	–	–	0.019 U	–	–	–	–	–
	MW 1-13-32.5	7/20/01	GeoEng	NCA	32.5	6.5	S	–	–	–	–	–	–	–	0.038 U	–	–	–	–	–
	MW 1-15-37.5	7/20/01	GeoEng	NCA	37.5	1.5	S	–	–	–	–	–	–	–	0.019 U	–	–	–	–	–
G-MW3 (G-SB4 11)	SB4-4-10	7/20/01	GeoEng	NCA	10	29.6	S	–	–	–	–	–	–	–	0.019 U	–	–	–	–	–
	SB4-7-17.5	7/20/01	GeoEng	NCA	17.5	22.1	S	–	–	–	–	–	–	–	0.019 U	–	–	–	–	–
	SB4-13-32.5	7/20/01	GeoEng	NCA	32.5	7.1	S	–	–	–	–	–	–	–	0.019 U	–	–	–	–	–
	SB4-15-37.5	7/20/01	GeoEng	NCA	37.5	2.1	S	–	–	–	–	–	–	–	0.019 U	–	–	–	–	–
IW06	IW06-25	1/15/16	SES	F&BI	25	26.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-30	1/15/16	SES	F&BI	30	21.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-40	1/15/16	SES	F&BI	40	11.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-50	1/15/16	SES	F&BI	50	1.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-55	1/15/16	SES	F&BI	55	-3.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-60	1/15/16	SES	F&BI	60	-8.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-65	1/15/16	SES	F&BI	65	-13.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-70	1/15/16	SES	F&BI	70	-18.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-75	1/15/16	SES	F&BI	75	-23.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
IW-1C	IW-1C-5	3/7/18	PES	ESC	5	34.1	S	0.00520 U	0.000334 U	0.00152 U	0.000267 U	0.000227 U	0.0111 U	0.00199 U	0.000300 U	0.000316 U	0.000433 U	0.000471 U	0.00149 U	**0.000570 J**
(-23.9 to-38.9)	IW-1C-15	3/7/18	PES	ESC	15	24.1	S	0.00550 U	0.000353 U	0.00161 U	0.000282 U	0.000240 U	0.0117 U	0.00210 U	0.000317 U	0.000334 U	0.000458 U	0.000498 U	0.00157 U	0.000260 U
	IW-1C-25	3/7/18	PES	ESC	25	14.1	S	1.11 U	0.0715 U	0.325 U	0.0570 U	0.0485 U	2.38 U	0.425 U	0.0641 U	0.0675 U	0.0926 U	0.101 U	0.318 U	0.0525 U
	IW-1C-35	3/7/18	PES	ESC	35	4.1	S	0.00502 U	0.000323 U	0.00147 U	0.000257 U	0.000219 U	0.0107 U	0.00192 U	0.000290 U	0.000305 U	0.000418 U	0.000455 U	0.00144 U	0.000237 U
	IW-1C-45	3/7/18	PES	ESC	45	-5.9	S	0.00524 U	0.000337 U	0.00153 U	0.000269 U	0.000228 U	0.0112 U	0.00200 U	0.000302 U	0.000318 U	0.000437 U	0.000475 U	0.00150 U	**0.00124**
	IW-1C-55	3/7/18	PES	ESC	55	-15.9	S	0.00524 U	0.000337 U	0.00153 U	0.000269 U	0.000228 U	0.0112 U	0.00200 U	0.000302 U	0.000318 U	0.000437 U	0.000475 U	0.00150 U	**0.000567 J**
	IW-1C-65	3/7/18	PES	ESC	65	-25.9	S	0.00538 U	0.000346 U	0.00157 U	0.000276 U	0.000234 U	0.0115 U	0.00206 U	0.000310 U	0.000326 U	0.000448 U	0.000487 U	0.00154 U	0.000254 U
	IW-1C-75	3/7/18	PES	ESC	75	-35.9	S	0.00563 U	0.000362 U	0.00165 U	0.000289 U	0.000245 U	0.0120 U	0.00215 U	0.000325 U	0.000342 U	0.000469 U	0.000510 U	0.00161 U	**0.000969 J**
IW-2C	IW-2C-5	3/7/18	PES	ESC	5	31.3	S	0.00578 U	0.000372 U	0.00169 U	0.000296 U	0.000252 U	**0.0154 J**	0.00221 U	**0.000546 J**	0.000351 U	0.000482 U	0.000524 U	0.00166 U	**0.00254**
(-24.8 to-39.8)	IW-2C-15	3/7/18	PES	ESC	15	21.3	S	0.00559 U	0.000360 U	0.00164 U	0.000287 U	0.000244 U	0.0119 U	0.00214 U	0.000323 U	0.000339 U	0.000466 U	0.000507 U	0.00160 U	**0.00121**
	IW-2C-25	3/7/18	PES	ESC	25	11.3	S	0.00523 U	0.000336 U	0.00153 U	0.000268 U	0.000228 U	0.0112 U	0.00200 U	0.000302 U	0.000317 U	0.000436 U	0.000474 U	0.00150 U	0.000247 U
	IW-2C-35	3/7/18	PES	ESC	35	1.3	S	0.00590 U	0.000379 U	0.00173 U	0.000302 U	0.000257 U	0.0126 U	0.00225 U	0.000340 U	0.000358 U	0.000491 U	0.000534 U	0.00169 U	**0.000409 J**

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
IW-2C (continued)	IW-2C-45	3/7/18	PES	ESC	45	-8.7	S	0.00508 U	0.000326 U	0.00149 U	0.000260 U	0.000221 U	0.0108 U	0.00194 U	0.000293 U	0.000308 U	0.000423 U	0.000460 U	0.00145 U	**0.000649 J**
	IW-2C-55	3/7/18	PES	ESC	55	-18.7	S	0.00545 U	0.000351 U	0.00160 U	0.000280 U	0.000238 U	0.0116 U	0.00208 U	0.000314 U	0.000331 U	0.000454 U	0.000494 U	0.00156 U	**0.000584 J**
	IW-2C-65	3/7/18	PES	ESC	65	-28.7	S	0.00512 U	0.000329 U	0.00150 U	0.000262 U	0.000223 U	0.0109 U	0.00196 U	**0.000814 J**	0.000311 U	0.000427 U	0.000464 U	0.00147 U	**0.000627 J**
	IW-2C-75	3/7/18	PES	ESC	75	-38.7	S	0.00562 U	0.000362 U	0.00165 U	0.000288 U	0.000245 U	0.0120 U	0.00215 U	0.000324 U	0.000341 U	0.000468 U	0.000509 U	0.00161 U	**0.000537 J**
IW-3C (-24.9 to-39.9)	IW-3C-5	3/9/18	PES	ESC	5	34.1	S	0.00512 U	0.000329 U	0.00150 U	0.000262 U	0.000223 U	0.0109 U	0.00196 U	0.000295 U	0.000311 U	0.000426 U	0.000464 U	0.00147 U	0.000242 U
	IW-3C-15	3/9/18	PES	ESC	15	24.1	S	0.136 U	0.00872 U	0.0396 U	0.00695 U	0.00591 U	0.290 U	0.0519 U	0.00782 U	0.00823 U	0.0113 U	0.0123 U	0.0388 U	0.00640 U
	IW-3C-25	3/9/18	PES	ESC	25	14.1	S	2.76 U	0.177 U	0.809 U	0.142 U	0.120 U	5.90 U	1.06 U	0.159 U	0.168 U	0.230 U	0.250 U	0.791 U	0.130 U
	IW-3C-35	3/9/18	PES	ESC	35	4.1	S	1.04 U	0.0669 U	0.305 U	0.0533 U	0.0453 U	2.22 U	0.398 U	0.0600 U	0.0631 U	0.0867 U	0.0942 U	0.298 U	0.0491 U
	IW-3C-45	3/9/18	PES	ESC	45	-5.9	S	0.00539 U	0.000347 U	0.00158 U	0.000277 U	0.000235 U	0.0115 U	0.00206 U	0.000311 U	0.000327 U	0.000450 U	0.000489 U	0.00154 U	**0.000411 J**
	IW-3C-55	3/9/18	PES	ESC	55	-15.9	S	0.00531 U	0.000342 U	0.00155 U	0.000272 U	0.000231 U	0.0113 U	0.00203 U	0.000306 U	0.000322 U	0.000443 U	0.000481 U	0.00152 U	0.000251 U
	IW-3C-65	3/9/18	PES	ESC	65	-25.9	S	0.00534 U	0.000343 U	0.00156 U	0.000274 U	0.000233 U	0.0114 U	0.00204 U	0.000308 U	0.000324 U	0.000445 U	0.000484 U	0.00153 U	**0.000260 J**
	IW-3C-75	3/9/18	PES	ESC	75	-35.9	S	0.00586 U	0.000377 U	0.00172 U	0.000300 U	0.000255 U	0.0125 U	0.00224 U	0.000338 U	0.000356 U	0.000488 U	0.000531 U	0.00168 U	**0.000306 J**
	IW-3C-79	3/9/18	PES	ESC	79	-39.9	S	0.00544 U	0.000350 U	0.00159 U	0.000279 U	0.000237 U	0.0116 U	0.00208 U	0.000314 U	0.000330 U	0.000453 U	0.000493 U	0.00156 U	0.000257 U
	IW-901-79	3/9/18	PES	ESC	79 (dup)	-39.9	S	0.00541 U	0.000348 U	0.00158 U	0.000278 U	0.000236 U	0.0116 U	0.00207 U	0.000312 U	0.000329 U	0.000451 U	0.000490 U	0.00155 U	0.000256 U
IW-7A (5.1 to-9.9)	IW-7A-5	3/16/18	PES	ESC	5	35.1	S	0.00580 U	0.000373 U	0.00170 U	0.000297 U	0.000253 U	0.0124 U	0.00222 U	**0.0122**	0.000352 U	0.000483 U	0.000525 U	0.00166 U	0.000274 U
	IW-7A-10	3/16/18	PES	ESC	10	30.1	S	0.0171 U	0.00128 U	**0.0743**	0.00155 U	**0.0140**	**0.148 J**	0.0102 U	**0.0433**	0.00123 U	0.000978 U	0.000835 U	0.00520 U	0.00114 U
	IW-7A-15	3/16/18	PES	ESC	15	25.1	S	0.188 U	0.0121 U	0.0550 U	0.00964 U	**0.165**	0.402 U	0.0720 U	**0.279**	0.0114 U	0.0157 U	0.0170 U	0.0539 U	**0.0183 J**
	IW-7A-20	3/16/18	PES	ESC	20	20.1	S	0.0176 U	0.00131 U	**0.00477 J**	0.00159 U	**0.0356**	**0.0629 J**	0.0104 U	**0.00723**	0.00126 U	0.00100 U	0.000857 U	0.00534 U	**0.00459**
	IW-7A-25	3/16/18	PES	ESC	25	15.1	S	0.00567 U	0.000365 U	0.00166 U	0.000291 U	0.000247 U	**0.0230 J**	0.00217 U	**0.00189**	0.000344 U	0.000472 U	0.000514 U	0.00162 U	**0.000638 J**
	IW-7A-30	3/16/18	PES	ESC	30	10.1	S	0.00543 U	0.000349 U	0.00159 U	0.000279 U	**0.000507 J**	0.0116 U	0.00208 U	**0.00201**	0.000330 U	0.000453 U	0.000492 U	0.00156 U	**0.00597 J**
	IW-7A-35	3/16/18	PES	ESC	35	5.1	S	0.0150 U	0.00113 U	0.00343 U	0.00136 U	**0.0109**	**0.0497 J**	0.00893 U	**0.00282 J**	0.00108 U	0.000860 U	0.000734 U	0.00457 U	**0.00139 J**
	IW-7A-40	3/16/18	PES	ESC	40	0.1	S	0.00551 U	0.000354 U	0.00161 U	0.000283 U	0.000240 U	0.0118 U	0.00211 U	0.000318 U	0.000334 U	0.000459 U	0.000499 U	0.00158 U	**0.000376 J**
	IW-7A-45	3/16/18	PES	ESC	45	-4.9	S	0.00547 U	0.000352 U	0.00160 U	0.000281 U	0.000238 U	0.0117 U	0.00209 U	**0.000600 J**	0.000332 U	0.000456 U	0.000496 U	0.00157 U	**0.000628 J**
	IW-7A-50	3/16/18	PES	ESC	50	-9.9	S	0.00520 U	0.000334 U	0.00152 U	0.000267 U	0.000227 U	**0.0327 J**	0.00199 U	0.000300 U	0.000315 U	0.000433 U	0.000471 U	0.00149 U	0.000245 U
IW-8B (-9.8 to-24.8)	IW-8B-5	3/19/18	PES	ESC	5	34.2	S	0.00512 U	0.000329 U	0.00150 U	0.000263 U	0.000223 U	**0.0204 J**	0.00196 U	0.000296 U	0.000311 U	0.000427 U	0.000464 U	0.00147 U	**0.00132**
	IW-8B-10	3/19/18	PES	ESC	10	29.2	S	0.00504 U	0.000324 U	0.00148 U	0.000259 U	0.000220 U	0.0108 U	0.00193 U	0.000291 U	0.000306 U	0.000420 U	0.000457 U	0.00144 U	0.000238 U
	IW-8B-15	3/19/18	PES	ESC	15	24.2	S	1.35 U	0.0865 U	0.394 U	0.0691 U	0.0587 U	2.88 U	0.516 U	0.0777 U	0.0817 U	0.112 U	0.122 U	0.386 U	0.0635 U
	IW-8B-20	3/19/18	PES	ESC	20	19.2	S	0.00514 U	0.000330 U	0.00150 U	0.000263 U	0.000224 U	0.0110 U	0.00196 U	0.000296 U	0.000312 U	0.000428 U	0.000465 U	0.00147 U	**0.00201**
	IW-8B-25	3/19/18	PES	ESC	25	14.2	S	0.00548 U	0.000352 U	0.00160 U	0.000281 U	0.000239 U	0.0117 U	0.00209 U	0.000316 U	0.000332 U	0.000456 U	0.000496 U	0.00157 U	0.000259 U
	IW-8B-30	3/19/18	PES	ESC	30	9.2	S	0.00526 U	0.000338 U	0.00154 U	0.000270 U	0.000229 U	0.0112 U	0.00201 U	0.000303 U	0.000319 U	0.000438 U	0.000476 U	0.00151 U	**0.000321**
	IW-8B-40	3/19/18	PES	ESC	40	-0.8	S	0.00522 U	0.000336 U	0.00153 U	0.000268 U	0.000228 U	0.0112 U	0.00200 U	0.000301 U	0.000317 U	0.000435 U	0.000473 U	0.00149 U	**0.000576**
	IW-8B-45	3/20/18	PES	ESC	45	-5.8	S	0.00522 U	0.000335 U	0.00153 U	0.000267 U	0.000227 U	0.0111 U	0.00200 U	0.000301 U	0.000317 U	0.000435 U	0.000473 U	0.00149 U	**0.000507**
	IW-8B-50	3/20/18	PES	ESC	50	-10.8	S	0.00535 U	0.000344 U	0.00157 U	0.000275 U	0.000233 U	0.0114 U	0.00205 U	0.000309 U	0.000325 U	0.000446 U	0.000485 U	0.00153 U	**0.000626**
	IW-8B-55	3/20/18	PES	ESC	55	-15.8	S	0.00505 U	0.000325 U	0.00148 U	0.000259 U	0.000220 U	0.0108 U	0.00193 U	0.000291 U	0.000306 U	0.000421 U	0.000457 U	0.00145 U	**0.000479**
	IW-8B-60	3/20/18	PES	ESC	60	-20.8	S	0.00536 U	0.000345 U	0.00157 U	0.000275 U	0.000234 U	0.0115 U	0.00205 U	0.000309 U	0.000325 U	0.000447 U	0.000486 U	0.00153 U	**0.000293**
	IW-8B-64	3/20/18	PES	ESC	64	-24.8	S	0.00528 U	0.000339 U	0.00154 U	0.000271 U	0.000230 U	0.0113 U	0.00202 U	0.000304 U	0.000320 U	0.000440 U	0.000478 U	0.00151 U	**0.000584**
IW-8C (-24.5 to-39.5)	IW-8C-5	3/14/18	PES	ESC	5	32.5	S	**0.0102 J**	0.000517 U	0.00235 U	0.000412 U	0.000350 U	**0.0315 J**	0.00307 U	**0.00198 J+**	0.000488 U	0.000669 U	0.000728 U	0.00231 U	**0.00251**
	IW-8C-10	3/14/18	PES	ESC	10	27.5	S	**0.0197 J**	0.000521 U	0.00237 U	0.000415 U	**0.00176**	**0.0564 J**	0.00310 U	**0.00277**	0.000491 U	0.000675 U	0.000733 U	0.00232 U	**0.00288**
	IW-8C-15	3/14/18	PES	ESC	15	22.5	S	0.00551 U	0.000355 U	0.00161 U	0.000282 U	0.000240 U	0.0118 U	0.00211 U	0.000318 U	0.000335 U	0.000459 U	0.000499 U	0.00158 U	0.000260 U
	IW-8C-20	3/14/18	PES	ESC	20	17.5	S	0.00505 U	0.000325 U	0.00148 U	0.000259 U	0.000220 U	0.0108 U	0.00193 U	0.000291 U	0.000306 U	0.000421 U	0.000457 U	0.00145 U	0.000238 U
	IW-8C-25	3/14/18	PES	ESC	25	12.5	S	0.00557 U	0.000358 U	0.00163 U	0.000286 U	0.000243 U	0.0119 U	0.00213 U	0.000321 U	0.000338 U	0.000464 U	0.000505 U	0.00160 U	0.000263 U
	IW-8C-30	3/14/18	PES	ESC	30	7.5	S	0.00518 U	0.000333 U	0.00152 U	0.000266 U	0.000226 U	0.0111 U	0.00198 U	0.000299 U	0.000314 U	0.000431 U	0.000469 U	0.00148 U	**0.000657 J**

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
IW-8C (continued)	IW-8C-35	3/14/18	PES	ESC	35	2.5	S	0.00541 U	0.000348 U	0.00158 U	0.000278 U	0.000236 U	0.0116 U	0.00207 U	0.000312 U	0.000329 U	0.000451 U	0.000490 U	0.00155 U	**0.000847 J**
	IW-8C-40	3/14/18	PES	ESC	40	-2.5	S	0.00539 U	0.000347 U	0.00158 U	0.000276 U	0.000235 U	0.0115 U	0.00206 U	0.000311 U	0.000327 U	0.000449 U	0.000488 U	0.00154 U	**0.00126**
	IW-8C-45	3/14/18	PES	ESC	45	-7.5	S	0.00528 U	0.000340 U	0.00155 U	0.000271 U	0.000230 U	0.0113 U	0.00202 U	**0.000346 J**	0.000320 U	0.000440 U	0.000478 U	0.00151 U	**0.00111 J**
	IW-8C-50	3/14/18	PES	ESC	50	-12.5	S	0.00550 U	0.000354 U	0.00161 U	0.000282 U	**0.000731 J**	0.0117 U	0.00210 U	0.000317 U	0.000334 U	0.000458 U	0.000498 U	0.00157 U	**0.00193**
	IW-8C-55	3/14/18	PES	ESC	55	-17.5	S	0.00540 U	0.000347 U	0.00158 U	0.000277 U	**0.000277 J**	0.0115 U	0.00207 U	0.000312 U	0.000328 U	0.000450 U	0.000489 U	0.00155 U	**0.00180**
	IW-8C-60	3/14/18	PES	ESC	60	-22.5	S	0.00535 U	0.000344 U	0.00157 U	0.000274 U	0.000233 U	0.0114 U	0.00205 U	0.000309 U	0.000325 U	0.000446 U	0.000484 U	0.00153 U	**0.00102 J**
	IW-902-60	3/14/18	PES	ESC	60 (dup)	-22.5	S	0.00519 U	0.000334 U	0.00152 U	0.000266 U	0.000226 U	0.0111 U	0.00199 U	0.000300 U	0.000315 U	0.000433 U	0.000471 U	0.00149 U	**0.000336 J**
	IW-8C-65	3/14/18	PES	ESC	65	-27.5	S	0.00561 U	0.000361 U	0.00164 U	0.000288 U	0.000245 U	0.0120 U	0.00215 U	0.000324 U	0.000341 U	0.000468 U	0.000509 U	0.00161 U	0.000265 U
	IW-8C-70	3/14/18	PES	ESC	70	-32.5	S	0.00556 U	0.000357 U	0.00163 U	0.000285 U	0.000242 U	0.0119 U	0.00212 U	0.000320 U	0.000337 U	0.000463 U	0.000503 U	0.00159 U	0.000262 U
	IW-8C-75	3/14/18	PES	ESC	75	-37.5	S	0.00524 U	0.000337 U	0.00153 U	0.000269 U	0.000228 U	0.0112 U	0.00200 U	0.000302 U	0.000318 U	0.000437 U	0.000475 U	0.00150 U	0.000247 U
IW-11D (-41.8 to-56.8)	IW-11D-10	4/19/18	PES	ESC	10	28.4	S	**0.0120 J**	0.000416 U	0.00189 U	0.000331 U	0.000282 U	**0.0415 J**	0.00247 U	**0.00456**	0.000392 U	0.000538 U	0.000585 U	0.00185 U	**0.00291**
	IW-11D-15	4/19/18	PES	ESC	15	23.4	S	0.00542 U	0.000349 U	0.00159 U	0.000278 U	0.000236 U	0.0116 U	0.00207 U	0.000313 U	0.000329 U	0.000452 U	0.000491 U	0.00155 U	**0.000575 J**
	IW-11D-20	4/19/18	PES	ESC	20	18.4	S	0.00541 U	0.000348 U	0.00158 U	0.000278 U	0.000236 U	0.0116 U	0.00207 U	0.000312 U	0.000328 U	0.000451 U	0.000490 U	0.00155 U	0.000256 U
	IW-11D-25	4/19/18	PES	ESC	25	13.4	S	0.00511 U	0.000329 U	0.00150 U	0.000262 U	0.000223 U	0.0109 U	0.00196 U	0.000295 U	0.000310 U	0.000426 U	0.000463 U	0.00146 U	**0.000439 J**
	IW-11D-30	4/19/18	PES	ESC	30	8.4	S	0.00512 U	0.000329 U	0.00150 U	0.000262 U	0.000223 U	0.0109 U	0.00196 U	0.000295 U	0.000311 U	0.000427 U	0.000464 U	0.00147 U	**0.00161**
	IW-11D-35	4/19/18	PES	ESC	35	3.4	S	0.00536 U	0.000345 U	0.00157 U	0.000275 U	0.000234 U	0.0115 U	0.00205 U	0.000309 U	0.000325 U	0.000447 U	0.000486 U	0.00154 U	**0.000708 J**
	IW-11D-40	4/19/18	PES	ESC	40	-1.6	S	0.00517 U	0.000333 U	0.00151 U	0.000265 U	0.000225 U	0.0111 U	0.00198 U	0.000298 U	0.000314 U	0.000431 U	0.000469 U	0.00148 U	**0.000757 J**
	IW-11D-45	4/19/18	PES	ESC	45	-6.6	S	0.132 U	0.00847 U	0.0385 U	0.00675 U	0.00574 U	0.281 U	0.0504 U	0.00760 U	0.00799 U	0.0110 U	0.0119 U	0.0377 U	0.00621 U
	IW-11D-50	4/19/18	PES	ESC	50	-11.6	S	0.00503 U	0.000323 U	0.00147 U	0.000258 U	0.000219 U	**0.0112 J**	0.00192 U	0.000290 U	0.000305 U	0.000419 U	0.000455 U	0.00144 U	**0.000463 J**
	IW-11D-55	4/19/18	PES	ESC	55	-16.6	S	0.00555 U	0.000357 U	0.00162 U	0.000284 U	0.000242 U	0.0118 U	0.00212 U	0.000320 U	0.000336 U	0.000462 U	0.000502 U	0.00159 U	**0.000440 J**
	IW-11D-60	4/19/18	PES	ESC	60	-21.6	S	0.00514 U	0.000331 U	0.00150 U	0.000264 U	0.000224 U	0.0110 U	0.00197 U	0.000297 U	0.000312 U	0.000428 U	0.000466 U	0.00147 U	0.000243 U
	IW-11D-65	4/19/18	PES	ESC	65	-26.6	S	0.00516 U	0.000332 U	0.00151 U	0.000264 U	0.000225 U	0.0110 U	0.00197 U	0.000297 U	0.000313 U	0.000430 U	0.000467 U	0.00148 U	**0.000279 J**
	IW-11D-70	4/19/18	PES	ESC	70	-31.6	S	0.00516 U	0.000332 U	0.00151 U	0.000265 U	0.000225 U	0.0110 U	0.00198 U	0.000298 U	0.000313 U	0.000430 U	0.000468 U	0.00148 U	**0.000445 J**
	IW-11D-75	4/19/18	PES	ESC	75	-36.6	S	0.00540 U	0.000347 U	0.00158 U	0.000277 U	0.000235 U	0.0115 U	0.00207 U	0.000312 U	0.000328 U	0.000450 U	0.000489 U	0.00155 U	**0.000545 J**
	IW-11D-80	4/19/18	PES	ESC	80	-41.6	S	0.00526 U	0.000338 U	0.00154 U	0.000270 U	0.000229 U	0.0112 U	0.00201 U	0.000303 U	0.000319 U	0.000438 U	0.000476 U	0.00151 U	0.000248 U
	IW-11D-85	4/19/18	PES	ESC	85	-46.6	S	0.00538 U	0.000346 U	0.00157 U	0.000276 U	0.000235 U	0.0115 U	0.00206 U	0.000310 U	0.000326 U	0.000448 U	0.000487 U	0.00154 U	0.000254 U
	IW-11D-90	4/19/18	PES	ESC	90	-51.6	S	0.00530 U	0.000341 U	0.00155 U	0.000272 U	0.000231 U	0.0113 U	0.00203 U	0.000306 U	0.000322 U	0.000442 U	0.000480 U	0.00152 U	0.000250 U
	IW-11D-95	4/19/18	PES	ESC	95	-56.6	S	0.00548 U	0.000353 U	0.00161 U	0.000281 U	0.000239 U	0.0117 U	0.00210 U	0.000316 U	0.000333 U	0.000457 U	0.000497 U	0.00157 U	0.000259 U
IW-12D (-41.4 to-56.4)	IW-12D-42	9/14/18	PES	ESC	42	-3.5	S	0.0136 U	0.000999 U	0.0109 U	0.00123 U	0.00253 U	1.49 U	0.00206 U	0.000434 U	0.00114 U	0.00123 U	0.00649 U	0.00402 U	0.00441 U
	B-928-42	9/14/18	PES	ESC	42 (dup)	-3.5	S	0.0136 U	0.00100 U	0.0109 U	0.00123 U	0.00253 U	1.49 U	0.00206 U	0.000435 U	0.00114 U	0.00123 U	0.00650 U	0.00402 U	0.00441 U
	IW-12D-50	9/14/18	PES	ESC	50	-11.5	S	0.0137 U	0.00101 U	0.0109 U	0.00124 U	0.00255 U	3.00 U	0.00208 U	0.000437 U	0.00115 U	0.00124 U	0.00654 U	0.00405 U	0.00444 U
	IW-12D-60	9/14/18	PES	ESC	60	-21.5	S	0.0141 U	0.00104 U	0.0113 U	0.00127 U	0.00262 U	0.309 U	0.00214 U	0.000451 U	0.00118 U	0.00127 U	0.00674 U	0.00417 U	0.00457 U
	IW-12D-85	9/17/18	PES	ESC	85	-46.5	S	0.279 U	0.00103 U	0.0112 U	0.00126 U	0.00260 U	0.306 U	0.00212 U	**0.000458 J**	0.00117 U	0.00126 U	0.00668 U	0.00414 U	0.00454 U
	IW-12D-95	9/17/18	PES	ESC	95	-56.5	S	0.0601 U	0.00111 U	0.0120 U	0.00136 U	0.00280 U	0.0659 U	0.00229 U	0.000481 U	0.00126 U	0.00136 U	0.00719 U	0.00445 U	0.00488 U
IW-13D (-41.0 to-56.0)	IW-13D-80	9/18/18	PES	ESC	80	-40.8	S	1.10 U	0.00102 U	0.0110 U	0.00125 U	0.00257 U	1.21 U	0.00210 U	0.000441 U	0.00116 U	0.00125 U	0.00660 U	0.00408 U	0.00448 U
	IW-13D-85	9/18/18	PES	ESC	85	-45.8	S	**0.0211 J**	0.00106 U	0.0115 U	0.00130 U	0.00268 U	0.0158 U	0.00219 U	0.000460 U	0.00121 U	0.00130 U	0.00688 U	0.00426 U	0.00467 U
	IW-13D-95	9/18/18	PES	ESC	95	-55.8	S	**0.0213 J**	0.00111 U	0.0120 U	0.00136 U	0.00280 U	0.0165 U	0.00229 U	0.000481 U	0.00126 U	0.00136 U	0.00720 U	0.00445 U	0.00489 U
IW-14D (-41.0 to-56.0)	IW-14D-45	9/11/18	PES	ESC	45	-5.9	S	0.0262 U	0.000964 U	0.0105 U	0.00118 U	0.00244 U	0.0144 U	0.00199 U	0.000419 U	0.00110 U	0.00118 U	0.00627 U	0.00388 U	0.00425 U
	IW-14D-55	9/11/18	PES	ESC	55	-15.9	S	0.565 U	0.00104 U	0.0113 U	0.00128 U	0.00263 U	0.0155 U	0.00215 U	0.000452 U	0.00119 U	0.00128 U	0.00676 U	0.00418 U	0.00459 U
	IW-14D-65	9/11/18	PES	ESC	65	-25.9	S	0.0140 U	0.00103 U	0.0112 U	0.00127 U	0.00262 U	0.0154 U	0.00213 U	0.000449 U	0.00118 U	0.00127 U	0.00671 U	0.00415 U	0.00456 U
	IW-14D-75	9/11/18	PES	ESC	75	-35.9	S	0.0140 U	0.00103 U	0.0112 U	0.00127 U	0.00261 U	**0.0671**	0.00213 U	**0.000525 J**	0.00118 U	0.00127 U	0.00671 U	0.00415 U	0.00455 U
	IW-14D-86	9/11/18	PES	ESC	86	-46.9	S	0.0138 U	0.00101 U	0.0110 U	0.00124 U	0.00257 U	0.0151 U	0.00209 U	**0.000604 J**	0.00116 U	0.00124 U	0.00659 U	0.00408 U	0.00447 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
IW-14D (continued)	IW-14D-95	9/11/18	PES	ESC	95	-55.9	S	0.113 U	0.00104 U	0.0113 U	0.00128 U	0.00264 U	0.0155 U	0.00215 U	**0.000701 J**	0.00119 U	0.00128 U	0.00677 U	0.00419 U	0.00460 U
IW-15D (-41.9 to-56.9)	IW-15D-54	9/11/18	PES	ESC	54	-2.2	S	0.0535 U	0.000984 U	0.0107 U	0.00121 U	0.00249 U	**0.0590**	0.00203 U	**0.000455 J**	0.00112 U	0.00121 U	0.00640 U	0.00396 U	0.00434 U
IW-16D (-41.5 to-56.2)	IW-16D-85	10/18/18	PES	PACE	85	-45.6	S	0.0583 U	0.00429 U	0.0466 U	0.00527 U	0.0109 U	0.0639 U	0.00886 U	**0.00321 J**	0.00489 U	0.00527 U	0.0278 U	0.0172 U	0.0189 U
	IW-16D-90	10/18/18	PES	PACE	90	-50.6	S	0.0148 U	0.00109 U	0.0119 U	0.00134 U	0.00276 U	0.0162 U	0.00225 U	0.000474 U	0.00124 U	0.00134 U	0.00709 U	0.00439 U	0.00481 U
	IW-16D-95	10/18/18	PES	PACE	95	-55.6	S	0.0605 U	0.00446 U	0.0484 U	0.00547 U	0.0113 U	0.0663 U	0.00920 U	0.00194 U	0.00509 U	0.00547 U	0.0289 U	0.0179 U	0.0196 U
IW-19B (-10.6 to-25.6)	IW-19B-5	3/19/18	PES	ESC	5	32.4	S	0.00528 U	0.000340 U	0.00155 U	0.000271 U	0.000230 U	**0.0388 J**	0.00202 U	**0.000797 J**	0.000321 U	0.000440 U	0.000479 U	0.00152 U	**0.00144**
	IW-19B-10	3/19/18	PES	ESC	10	27.4	S	**0.0220**	0.000370 U	0.00169 U	0.000295 U	0.000251 U	**0.115**	0.00220 U	**0.000465 J**	0.000349 U	0.000480 U	0.000522 U	0.00165 U	**0.00196**
	IW-19B-15	3/19/18	PES	ESC	15	22.4	S	0.00536 U	0.000345 U	0.00157 U	0.000275 U	0.000234 U	**0.0119 J**	0.00205 U	0.000309 U	0.000325 U	0.000447 U	0.000486 U	0.00154 U	**0.00135 J**
	IW-19B-20	3/19/18	PES	ESC	20	17.4	S	0.00523 U	0.000336 U	0.00153 U	0.000268 U	0.000228 U	**0.0126 J**	0.00200 U	0.000302 U	0.000317 U	0.000436 U	0.000473 U	0.00150 U	**0.00254**
	IW-19B-25	3/19/18	PES	ESC	25	12.4	S	0.00549 U	0.000353 U	0.00161 U	0.000282 U	0.000239 U	**0.0157 J**	0.00210 U	0.000317 U	0.000333 U	0.000458 U	0.000498 U	0.00157 U	**0.00388**
	IW-19B-30	3/19/18	PES	ESC	30	7.4	S	0.00526 U	0.000338 U	0.00154 U	0.000270 U	0.000229 U	**0.0139 J**	0.00201 U	0.000303 U	0.000319 U	0.000438 U	0.000476 U	0.00150 U	**0.000756 J**
	IW-19B-35	3/19/18	PES	ESC	35	2.4	S	0.00519 U	0.000334 U	0.00152 U	0.000266 U	0.000226 U	**0.0145 J**	0.00199 U	0.000299 U	0.000315 U	0.000433 U	0.000470 U	0.00149 U	**0.00330**
	IW-19B-40	3/19/18	PES	ESC	40	-2.6	S	**0.00772 J**	0.000347 U	0.00158 U	0.000277 U	0.000235 U	**0.0380 J**	0.00207 U	0.000312 U	0.000328 U	0.000450 U	0.000489 U	0.00155 U	**0.00114 J**
	IW-19B-45	3/19/18	PES	ESC	45	-7.6	S	0.00571 U	0.000367 U	0.00167 U	0.000293 U	0.000249 U	**0.0212 J**	0.00218 U	0.000330 U	0.000347 U	0.000476 U	0.000517 U	0.00164 U	**0.00105 J**
	IW-19B-50	3/19/18	PES	ESC	50	-12.6	S	0.00597 U	0.000384 U	0.00174 U	0.000307 U	0.000260 U	0.0128 U	0.00228 U	0.000344 U	0.000362 U	0.000498 U	0.000541 U	0.00171 U	**0.00307**
	IW-19B-55	3/19/18	PES	ESC	55	-17.6	S	0.00515 U	0.000331 U	0.00151 U	0.000264 U	0.000224 U	0.0110 U	0.00197 U	0.000297 U	0.000312 U	0.000429 U	0.000467 U	0.00147 U	**0.00291**
	IW-19B-60	3/19/18	PES	ESC	60	-22.6	S	0.00516 U	0.000332 U	0.00151 U	0.000265 U	0.000225 U	0.0110 U	0.00197 U	0.000298 U	0.000313 U	0.000430 U	0.000468 U	0.00148 U	**0.00446**
	IW-903-60	3/19/18	PES	ESC	60 (dup)	-22.6	S	0.00525 U	0.000338 U	0.00154 U	0.000269 U	0.000229 U	**0.0137 J**	0.00201 U	0.000303 U	0.000319 U	0.000438 U	0.000476 U	0.00150 U	**0.00319**
	IW-19B-63	3/19/18	PES	ESC	63	-25.6	S	0.00524 U	0.000337 U	0.00153 U	0.000269 U	0.000228 U	0.0112 U	0.00200 U	0.000302 U	0.000318 U	0.000437 U	0.000475 U	0.00150 U	**0.000488 J**
IW-21B (-10.1 to-25.1)	IW-21B-5	3/6/18	PES	ESC	5	36.9	V	0.00846 U	0.000544 U	0.00247 U	0.000433 U	0.000369 U	0.0181 U	0.00323 U	0.000488 U	0.000513 U	0.000705 U	0.000767 U	0.00242 U	0.000400 U
	IW-21B-10	3/6/18	PES	ESC	10	31.9	S	0.00571 U	0.000367 U	0.00167 U	0.000293 U	0.000249 U	**0.0147 J**	0.00218 U	0.000329 U	0.000346 U	0.000475 U	0.000517 U	0.00163 U	0.000269 U
	IW-21B-20	3/6/18	PES	ESC	20	21.9	S	0.00563 U	0.000362 U	0.00165 U	0.000289 U	**0.000744 J**	**0.0123 J**	0.00215 U	**0.000864 J**	0.000341 U	0.000469 U	0.000510 U	0.00161 U	**0.00209**
	IW-21B-30	3/6/18	PES	ESC	30	11.9	S	0.00523 U	0.000336 U	0.00153 U	0.000268 U	0.000228 U	0.0112 U	0.00200 U	0.000301 U	0.000317 U	0.000435 U	0.000473 U	0.00150 U	**0.000830 J**
	IW-21B-40	3/6/18	PES	ESC	40	1.9	S	0.00517 U	0.000333 U	0.00151 U	0.000265 U	0.000225 U	0.0111 U	0.00198 U	0.000298 U	0.000314 U	0.000431 U	0.000469 U	0.00148 U	**0.000861 J**
	IW-21B-50	3/6/18	PES	ESC	50	-8.1	S	0.00506 U	0.000326 U	0.00148 U	0.000260 U	0.000221 U	0.0108 U	0.00194 U	0.000292 U	0.000307 U	0.000422 U	0.000459 U	0.00145 U	**0.000274 J**
	IW-21B-60	3/6/18	PES	ESC	60	-18.1	S	0.133 U	0.00852 U	0.0388 U	0.00680 U	0.00578 U	0.283 U	0.0508 U	0.00765 U	0.00805 U	0.0110 U	0.0120 U	0.0380 U	0.00625 U
	IW-21B-67	3/6/18	PES	ESC	67	-25.1	S	0.00518 U	0.000333 U	0.00152 U	0.000266 U	0.000226 U	0.0111 U	0.00198 U	0.000299 U	0.000315 U	0.000432 U	0.000470 U	0.00148 U	**0.000377 J**
IW-22C (-25.6 to-40.6)	IW-22C-62	8/31/18	PES	ESC	62	-23.1	S	**0.0342**	0.00106 U	0.0115 U	**0.00193 J**	0.00269 U	**0.0193 J**	0.00219 U	0.000462 U	0.00121 U	0.00131 U	0.00691 U	0.00427 U	0.00468 U
	IW-22C-78	8/31/18	PES	ESC	78	-39.1	S	**0.0382**	0.00111 U	0.0121 U	0.00137 U	0.00282 U	0.0166 U	0.00230 U	0.000484 U	0.00127 U	0.00137 U	0.00724 U	0.00448 U	**0.00695 J**
IW-23C (-27.0 to-42.0)	IW-23C-42	9/4/18	PES	ESC	42	-3.0	S	0.0150 U	0.00110 U	0.0120 U	0.00135 U	**0.00450 J**	**0.0193 J**	0.00227 U	0.000479 U	0.00126 U	0.00135 U	0.00716 U	0.00443 U	0.00486 U
IW-24C (-26.1 to-41.1)	IW-24C-48	9/7/18	PES	ESC	48	-8.8	S	0.0141 U	0.00104 U	0.0113 U	0.00128 U	0.00263 U	0.0155 U	0.00215 U	**0.000635 J**	0.00119 U	0.00128 U	0.00676 U	0.00418 U	0.00459 U
	IW-24C-55	9/7/18	PES	ESC	55	-15.8	S	**0.0508**	0.00110 U	0.0119 U	0.00135 U	**0.00285 J**	0.0163 U	0.00227 U	**0.000769 J**	0.00125 U	0.00135 U	0.00712 U	0.441 U	**0.00537**
	IW-24C-66	9/10/18	PES	ESC	66	-26.8	S	0.0155 U	0.00114 U	0.0124 U	0.00140 U	**0.00325 J**	0.0169 U	0.00235 U	0.000495 U	0.00130 U	0.00140 U	0.00740 U	1.83 U	0.00502 U
	IW-24C-75	9/10/18	PES	ESC	75	-35.8	S	0.0149 U	0.00110 U	0.0120 U	0.00135 U	0.00279 U	0.0164 U	0.00227 U	0.000478 U	0.00125 U	0.00135 U	0.00715 U	1.77 U	0.00485 U
	IW-24C-80	9/10/18	PES	ESC	80	-40.8	S	0.277 U	0.00102 U	0.0111 U	0.00125 U	0.00258 U	0.0152 U	0.00210 U	0.000442 U	0.00116 U	0.00125 U	0.00661 U	0.00409 U	0.00449 U
IW-27B (-8.1 to-23.1)	IW-27B-5	3/2/18	PES	ESC	5	37.0	V	0.00750 U	0.000482 U	0.00220 U	0.000385 U	0.000327 U	0.0160 U	0.00287 U	0.000432 U	0.000456 U	0.000624 U	0.000680 U	0.00215 U	0.000354 U
	IW-27B-15	3/2/18	PES	ESC	15	27.0	S	**0.0258**	0.000429 U	0.00195 U	0.000342 U	**0.00167**	**0.0649 J**	0.00255 U	**0.00393**	0.000404 U	0.000555 U	0.000604 U	0.00191 U	**0.00228**
	IW-27B-25	3/2/18	PES	ESC	25	17.0	S	0.00544 U	0.000350 U	0.00159 U	0.000279 U	0.000237 U	0.0116 U	0.00208 U	0.000314 U	0.000330 U	0.000454 U	0.000493 U	0.00156 U	0.000257 U
	IW-27B-35	3/2/18	PES	ESC	35	7.0	S	0.00536 U	0.000344 U	0.00157 U	0.000275 U	0.000233 U	0.0114 U	0.00205 U	0.000309 U	0.000325 U	0.000446 U	0.000485 U	0.00153 U	**0.00139**

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
IW-27C (-24.4 to-39.6)	IW-27C-45	9/10/18	PES	ESC	45	6.8	S	0.280 U	0.00103 U	0.0112 U	0.00126 U	0.00261 U	0.0153 U	0.00213 U	0.000448 U	0.00118 U	0.00126 U	0.00669 U	0.00414 U	0.00454 U
IW-28C (-26.6 to-41.7)	IW-28C-92	9/17/18	PES	ESC	92	-40.6	S	0.0544 U	0.00100 U	0.0109 U	0.00123 U	0.00253 U	0.0596 U	0.00207 U	0.000435 U	0.00114 U	0.00123 U	0.00650 U	0.00402 U	0.00441 U
IW-39B (-9.8 to-24.8)	IW-39B-5	3/12/18	PES	ESC	5	35.2	V	0.00594 U	0.000382 U	0.00174 U	0.000305 U	0.000259 U	**0.0189 J**	0.00227 U	0.000343 U	0.000361 U	0.000495 U	0.000538 U	0.00170 U	**0.00335**
	IW-39B-15	3/12/18	PES	ESC	15	25.2	S	0.00522 U	0.000335 U	0.00153 U	0.000267 U	0.000227 U	0.0111 U	0.00199 U	0.000301 U	0.000316 U	0.000435 U	0.000473 U	0.00149 U	0.000246 U
	IW-39B-25	3/12/18	PES	ESC	25	15.2	S	0.00556 U	0.000358 U	0.00163 U	0.000285 U	0.000243 U	0.0119 U	0.00213 U	0.000321 U	0.000338 U	0.000464 U	0.000504 U	0.00159 U	**0.000306 J**
	IW-39B-35	3/12/18	PES	ESC	35	5.2	S	0.00514 U	0.000331 U	0.00150 U	0.000264 U	0.000224 U	0.0110 U	0.00197 U	0.000296 U	0.000312 U	0.000428 U	0.000466 U	0.00147 U	**0.000442 J**
	IW-39B-45	3/12/18	PES	ESC	45	-4.8	S	0.00525 U	0.000338 U	0.00154 U	0.000269 U	0.000229 U	0.0112 U	0.00201 U	0.000303 U	0.000318 U	0.000437 U	0.000475 U	0.00150 U	**0.000442 J**
	IW-39B-55	3/12/18	PES	ESC	55	-14.8	S	0.123 U	0.00790 U	0.0359 U	0.00630 U	0.00536 U	0.263 U	0.0470 U	0.00709 U	0.00746 U	0.0102 U	0.0111 U	0.0352 U	0.00580 U
IW-46B (-4.2 to-24.2)	IW-46B-5	3/20/18	PES	ESC	5	46.8	V	0.00526 U	0.000338 U	0.00154 U	0.000270 U	0.000229 U	**0.0389 J**	0.00201 U	0.000303 UJ	0.000319 U	0.000438 U	0.000477 U	0.00151 U	**0.000328 J**
	IW-46B-10	3/20/18	PES	ESC	10	41.8	V	**0.00532 J**	0.000331 U	0.00151 U	0.000264 U	0.000224 U	**0.0688**	0.00197 U	**0.000327 J**	0.000312 U	0.000429 U	0.000466 U	0.00147 U	**0.00104 J**
	IW-46B-15	3/20/18	PES	ESC	15	36.8	V	0.129 U	0.00832 U	0.0378 U	0.00664 U	0.00564 U	0.277 U	0.0496 U	0.00747 UJ	0.00785 U	0.0108 U	0.0117 U	0.0371 U	0.00611 U
	IW-46B-20	3/20/18	PES	ESC	20	31.8	S	0.00523 U	0.000337 U	0.00153 U	0.000268 U	0.000228 U	0.0112 U	0.00200 U	0.000302 UJ	0.000318 U	0.000436 U	0.000474 U	0.00150 U	0.000247 U
	IW-46B-25	3/20/18	PES	ESC	25	26.8	S	0.00517 U	0.000333 U	0.00151 U	0.000265 U	0.000225 U	**0.0116 J**	0.00198 U	0.000298 UJ	0.000314 U	0.000431 U	0.000469 U	0.00148 U	**0.00128**
	IW-46B-30	3/20/18	PES	ESC	30	21.8	S	0.00523 U	0.000337 U	0.00153 U	0.000268 U	0.000228 U	**0.0144 J**	0.00200 U	0.000302 UJ	0.000318 U	0.000436 U	0.000474 U	0.00150 U	**0.000553 J**
	IW-46B-35	3/20/18	PES	ESC	35	16.8	S	0.00566 U	0.000364 U	0.00166 U	0.000290 U	0.000247 U	**0.0147 J**	0.00217 U	0.000327 UJ	0.000344 U	0.000472 U	0.000513 U	0.00162 U	**0.000363 J**
	IW-904-35	3/20/18	PES	ESC	35 (dup)	16.8	S	0.00599 U	0.000385 U	0.00175 U	0.000307 U	0.000261 U	**0.0178 J**	0.00229 U	0.000345 UJ	0.000363 U	0.000499 U	0.000542 U	0.00171 U	**0.000623 J**
	IW-46B-40	3/20/18	PES	ESC	40	11.8	S	0.00492 U	0.000316 U	0.00144 U	0.000252 U	0.000214 U	0.0105 U	0.00188 U	0.000284 UJ	0.000299 U	0.000410 U	0.000446 U	0.00141 U	**0.000999 J**
	IW-46B-42	3/20/18	PES	ESC	42	9.8	S	0.00563 U	0.000362 U	0.00165 U	0.000289 U	0.000245 U	**0.0256 J**	0.00215 U	**0.000384 J**	0.000341 U	0.000469 U	0.000510 U	0.00161 U	**0.00580**
	IW-46B-45	3/20/18	PES	ESC	45	6.8	S	26.6 U	1.71 U	7.79 U	1.37 U	1.16 U	56.9 U	10.2 U	1.54 UJ	1.62 U	2.22 U	2.41 U	7.62 U	1.25 U
	IW-46B-50	3/20/18	PES	ESC	50	1.8	S	0.00468 U	0.000301 U	0.00137 U	0.000240 U	0.000204 U	**0.0203 J**	0.00179 U	**0.000504 J**	0.000284 U	0.000390 U	0.000424 U	0.00134 U	**0.00218**
	IW-46B-55	3/20/18	PES	ESC	55	-3.2	S	0.00522 U	0.000336 U	0.00153 U	0.000268 U	0.000227 U	**0.0159 J**	0.00200 U	**0.000305 J**	0.000317 U	0.000435 U	0.000473 U	0.00149 U	**0.00266**
	IW-46B-60	3/20/18	PES	ESC	60	-8.2	S	0.00529 U	0.000340 U	0.00155 U	0.000271 U	0.000230 U	**0.0123 J**	0.00202 U	0.000305 UJ	0.000321 U	0.000441 U	0.000479 U	0.00151 U	**0.00171**
	IW-46B-65	3/20/18	PES	ESC	65	-13.2	S	0.00520 U	0.000335 U	0.00152 U	0.000267 U	0.000227 U	**0.0191 J**	0.00199 U	0.000300 UJ	0.000316 U	0.000434 U	0.000471 U	0.00149 U	**0.00125**
	IW-46B-70	3/20/18	PES	ESC	70	-18.2	S	0.00597 U	0.000384 U	0.00175 U	0.000306 U	0.000260 U	**0.0257 J**	0.00228 U	0.000344 UJ	0.000362 U	0.000497 U	0.000541 U	0.00171 U	**0.00187**
IW-47B (-5.2 to-25.2)	IW-47B-5	3/22/18	PES	ESC	5	46.8	V	0.00552 U	0.000355 U	0.00162 U	0.000283 U	0.000241 U	**0.0309 J**	0.00211 U	**0.000323 J**	0.000335 U	0.000460 U	0.000500 U	0.00158 U	**0.000553 J**
	IW-47B-10	3/22/18	PES	ESC	10	41.8	V	0.00551 U	0.000354 U	0.00161 U	0.000282 U	0.000240 U	0.0118 U	0.00211 U	0.000318 UJ	0.000334 U	0.000459 U	0.000499 U	0.00158 U	0.000260 U
	IW-47B-15	3/22/18	PES	ESC	15	36.8	V	0.00523 U	0.000336 U	0.00153 U	0.000268 U	0.000228 U	0.0112 U	0.00200 U	0.000301 UJ	0.000317 U	0.000435 U	0.000473 U	0.00150 U	0.000247 U
	IW-47B-20	3/22/18	PES	ESC	20	31.8	S	0.00520 U	0.000334 U	0.00152 U	0.000267 U	0.000227 U	0.0111 U	0.00199 U	0.000300 UJ	0.000315 U	0.000433 U	0.000471 U	0.00149 U	**0.000425 J**
	IW-47B-25	3/22/18	PES	ESC	25	26.8	S	0.00530 U	0.000341 U	0.00155 U	0.000272 U	0.000231 U	0.0113 U	0.00203 U	0.000305 UJ	0.000321 U	0.000441 U	0.000480 U	0.00152 U	0.000250 U
	IW-47B-30	3/22/18	PES	ESC	30	21.8	S	**0.0126**	0.000337 U	0.00154 U	0.000269 U	0.000229 U	**0.0166 J**	0.00201 U	0.000303 UJ	0.000318 U	0.000437 U	0.000475 U	0.00150 U	**0.000846 J**
	IW-47B-35	3/22/18	PES	ESC	35	16.8	S	0.00515 U	0.000331 U	0.00151 U	0.000264 U	0.000224 U	**0.0184 J**	0.00197 U	0.000297 UJ	0.000312 U	0.000429 U	0.000466 U	0.00147 U	**0.00108 J**
	IW-47B-40	3/22/18	PES	ESC	40	11.8	S	**0.00909 J**	0.000342 U	0.00156 U	0.000272 U	0.000232 U	**0.0221 J**	0.00203 U	0.000306 UJ	0.000322 U	0.000443 U	0.000481 U	0.00152 U	**0.00131**
	IW-47B-42	3/22/18	PES	ESC	42	9.8	S	0.00614 U	0.000395 U	0.00180 U	0.000315 U	0.000267 U	**0.0138 J**	0.00235 U	0.000354 UJ	0.000373 U	0.000512 U	0.000556 U	0.00175 U	**0.00132**
	IW-47B-45	3/22/18	PES	ESC	45	6.8	S	**0.00673 J**	0.000340 U	0.00155 U	0.000271 U	0.000231 U	**0.0361 J**	0.00202 U	0.000305 UJ	0.000321 U	0.000441 U	0.000479 U	0.00152 U	**0.00209**
	IW-47B-50	3/22/18	PES	ESC	50	1.8	S	0.00550 U	0.000354 U	0.00161 U	0.000282 U	0.000240 U	**0.0297 J**	0.00210 U	0.000317 UJ	0.000334 U	0.000458 U	0.000498 U	0.00157 U	**0.00182**
	IW-47B-55	3/22/18	PES	ESC	55	-3.2	S	0.00506 U	0.000325 U	0.00148 U	0.000259 U	0.000221 U	0.0108 U	0.00193 U	0.000292 UJ	0.000307 U	0.000422 U	0.000458 U	0.00145 U	**0.00303**
	IW-47B-60	3/22/18	PES	ESC	60	-8.2	S	0.00535 U	0.000344 U	0.00157 U	0.000274 U	0.000233 U	**0.0335 J**	0.00205 U	0.000309 UJ	0.000325 U	0.000446 U	0.000485 U	0.00153 U	**0.00132**
	IW-47B-65	3/22/18	PES	ESC	65	-13.2	S	0.00528 U	0.000340 U	0.00155 U	0.000271 U	0.000230 U	**0.0282 J**	0.00202 U	0.000305 UJ	0.000321 U	0.000440 U	0.000479 U	0.00151 U	**0.00188**
	IW-47B-70	3/22/18	PES	ESC	70	-18.2	S	0.00522 U	0.000336 U	0.00153 U	0.000268 U	0.000228 U	**0.0175 J**	0.00200 U	0.000301 UJ	0.000317 U	0.000435 U	0.000473 U	0.00150 U	**0.00163**
	IW-47B-75	3/22/18	PES	ESC	75	-23.2	S	0.00521 U	0.000335 U	0.00152 U	0.000267 U	0.000227 U	0.0111 U	0.00199 U	0.000300 UJ	0.000316 U	0.000434 U	0.000472 U	0.00149 U	**0.000338 J**

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
IW-48B	IW-48B-5	3/23/18	PES	ESC	5	46.7	V	0.00541 U	0.000348 U	0.00158 U	0.000277 U	0.000236 U	0.0116 U	0.00207 U	0.000312 U	0.000328 U	0.000451 U	0.000490 U	0.00155 U	0.000255 U
(-9.4 to-24.4)	IW-48B-10	3/23/18	PES	ESC	10	41.7	V	0.00530 U	0.000341 U	0.00155 U	0.000272 U	0.000231 U	0.0113 U	0.00203 U	0.000306 U	0.000322 U	0.000442 U	0.000480 U	0.00152 U	0.000250 U
	IW-48B-15	3/23/18	PES	ESC	15	36.7	V	0.00546 U	0.000351 U	0.00160 U	0.000280 U	0.000238 U	**0.0247 J**	0.00209 U	**0.00101 J**	0.000332 U	0.000455 U	0.000495 U	0.00156 U	**0.000467 J**
	IW-48B-20	3/23/18	PES	ESC	20	31.7	S	0.00515 U	0.000331 U	0.00151 U	0.000264 U	0.000224 U	0.0110 U	0.00197 U	0.000297 U	0.000312 U	0.000429 U	0.000467 U	0.00147 U	0.000243 U
	IW-48B-25	3/23/18	PES	ESC	25	26.7	S	0.00527 U	0.000339 U	0.00154 U	0.000270 U	0.000230 U	0.0113 U	0.00202 U	0.000304 U	0.000320 U	0.000439 U	0.000477 U	0.00151 U	**0.000616 J**
	IW-48B-30	3/23/18	PES	ESC	30	21.7	S	0.00516 U	0.000332 U	0.00151 U	0.000265 U	0.000225 U	0.0110 U	0.00197 U	0.000298 U	0.000313 U	0.000430 U	0.000467 U	0.00148 U	**0.000291 J**
	IW-48B-35	3/23/18	PES	ESC	35	16.7	S	0.00538 U	0.000346 U	0.00158 U	0.000276 U	0.000235 U	0.0115 U	0.00206 U	0.000311 U	0.000327 U	0.000449 U	0.000488 U	0.00154 U	**0.00108 J**
	IW-48B-40	3/23/18	PES	ESC	40	11.7	S	0.00511 U	0.000329 U	0.00150 U	0.000262 U	0.000223 U	0.0109 U	0.00195 U	0.000295 U	0.000310 U	0.000426 U	0.000463 U	0.00146 U	**0.00119**
	IW-48B-42	3/23/18	PES	ESC	42	9.7	S	0.00516 U	0.000332 U	0.00151 U	0.000265 U	0.000225 U	0.0110 U	0.00197 U	0.000298 U	0.000313 U	0.000430 U	0.000467 U	0.00148 U	**0.00100 J**
	IW-905-42	3/23/18	PES	ESC	42 (dup)	9.7	S	0.00511 U	0.000329 U	0.00150 U	0.000262 U	0.000223 U	0.0109 U	0.00196 U	0.000295 U	0.000310 U	0.000426 U	0.000463 U	0.00146 U	**0.00138**
	IW-48B-45	3/23/18	PES	ESC	45	6.7	S	**0.0121**	0.000327 U	0.00149 U	0.000260 U	0.000221 U	**0.0201 J**	0.00194 U	0.000293 U	0.000308 U	0.000423 U	0.000460 U	0.00145 U	**0.000835 J**
	IW-48B-50	3/23/18	PES	ESC	50	1.7	S	**0.0134**	0.000332 U	0.00151 U	0.000265 U	0.000225 U	**0.0194 J**	0.00198 U	0.000298 U	0.000313 U	0.000430 U	0.000468 U	0.00148 U	**0.00124**
	IW-48B-55	3/23/18	PES	ESC	55	-3.3	S	0.00507 U	0.000327 U	0.00149 U	0.000261 U	0.000221 U	0.0108 U	0.00194 U	0.000293 U	0.000308 U	0.000423 U	0.000460 U	0.00146 U	**0.00213**
	IW-48B-60	3/23/18	PES	ESC	60	-8.3	S	0.00518 U	0.000333 U	0.00152 U	0.000265 U	0.000226 U	0.0111 U	0.00198 U	0.000299 U	0.000314 U	0.000431 U	0.000469 U	0.00148 U	**0.00234**
	IW-48B-65	3/23/18	PES	ESC	65	-13.3	S	0.00553 U	0.000356 U	0.00162 U	0.000284 U	0.000241 U	**0.0214 J**	0.00211 U	0.000319 U	0.000336 U	0.000461 U	0.000501 U	0.00158 U	**0.000739 J**
	IW-48B-70	3/23/18	PES	ESC	70	-18.3	S	0.00514 U	0.000331 U	0.00151 U	0.000264 U	0.000224 U	0.0110 U	0.00197 U	0.000297 U	0.000312 U	0.000429 U	0.000466 U	0.00147 U	**0.000383 J**
	IW-48B-75	3/23/18	PES	ESC	75	-23.3	S	0.00526 U	0.000339 U	0.00154 U	0.000270 U	0.000229 U	0.0112 U	0.00201 U	0.000304 U	0.000319 U	0.000439 U	0.000477 U	0.00151 U	**0.00256**
IW-50A	IW-50A-5	3/27/18	PES	ESC	5	46.9	V	0.00534 U	0.000344 U	0.00156 U	0.000274 U	0.000233 U	**0.0493 J**	0.00204 U	**0.000343 J**	0.000324 U	0.000445 U	0.000484 U	0.00153 U	**0.000543 J**
(9.8 to-10.2)	IW-50A-10	3/27/18	PES	ESC	10	41.9	V	**0.0791**	0.000335 U	0.00153 U	0.000267 U	0.000227 U	**0.504**	0.00200 U	0.000301 U	0.000317 U	0.000435 U	0.000473 U	0.00149 U	0.000246 U
	IW-50A-15	3/27/18	PES	ESC	15	36.9	V	**0.225**	0.000331 U	0.00150 U	0.000264 U	0.000224 U	**0.667 J**	0.00197 U	0.000297 U	0.000312 U	0.000428 U	0.000466 U	0.00147 U	**0.000287 J**
	IW-50A-20	3/27/18	PES	ESC	20	31.9	S	**0.0116**	0.000335 U	0.00152 U	0.000267 U	0.000227 U	**0.0419 J**	0.00199 U	0.000300 U	0.000316 U	0.000433 U	0.000471 U	0.00149 U	0.000246 U
	IW-50A-25	3/27/18	PES	ESC	25	26.9	S	**0.00600 J**	0.000326 U	0.00148 U	0.000260 U	0.000221 U	0.0108 U	0.00194 U	0.000292 U	0.000307 U	0.000422 U	0.000459 U	0.00145 U	0.000239 U
	IW-50A-30	3/27/18	PES	ESC	30	21.9	S	**0.153**	0.000327 U	0.00149 U	0.000261 U	0.000222 U	**0.0706**	0.00194 U	0.000293 U	0.000308 U	0.000424 U	0.000460 U	0.00146 U	**0.000545 J**
	IW-50A-35	3/27/18	PES	ESC	35	16.9	S	**0.0561**	0.000328 U	0.00149 U	0.000261 U	0.000222 U	**0.0368 J**	0.00195 U	0.000294 U	0.000309 U	0.000425 U	0.000462 U	0.00146 U	**0.000801 J**
	IW-50A-40	3/27/18	PES	ESC	40	11.9	S	**0.0513**	0.000333 U	0.00151 U	0.000265 U	0.000225 U	**0.0380 J**	0.00198 U	0.000298 U	0.000314 U	0.000431 U	0.000468 U	0.00148 U	**0.000945 J**
	IW-50A-42	3/27/18	PES	ESC	42	9.9	S	**0.0253**	0.000331 U	0.00150 U	0.000264 U	0.000224 U	**0.0140 J**	0.00197 U	0.000297 U	0.000312 U	0.000428 U	0.000466 U	0.00147 U	**0.000639 J**
	IW-50A-45	3/27/18	PES	ESC	45	6.9	S	**0.0783**	0.000333 U	0.00152 U	0.000266 U	0.000226 U	**0.0558**	0.00198 U	0.000299 U	0.000314 U	0.000432 U	0.000469 U	0.00148 U	**0.00176**
	IW-50A-50	3/27/18	PES	ESC	50	1.9	S	**0.0460**	0.000338 U	0.00154 U	0.000269 U	0.000229 U	**0.0337 J**	0.00201 U	0.000303 U	0.000319 U	0.000438 U	0.000476 U	0.00150 U	**0.00122**
	IW-906-50	3/27/18	PES	ESC	50 (dup)	1.9	S	**0.0184 J**	0.000340 U	0.00155 U	0.000271 U	0.000230 U	**0.0120 J**	0.00202 U	0.000305 U	0.000321 U	0.000440 U	0.000479 U	0.00151 U	**0.000751 J**
	IW-50A-55	3/27/18	PES	ESC	55	-3.2	S	**0.0116**	0.000339 U	0.00154 U	0.000270 U	0.000230 U	**0.0191 J**	0.00201 U	0.000304 U	0.000320 U	0.000439 U	0.000477 U	0.00151 U	**0.000464 J**
	IW-50A-60	3/27/18	PES	ESC	60	-8.2	S	0.00529 U	0.000340 U	0.00155 U	0.000271 U	0.000230 U	0.0113 U	0.00202 U	0.000305 U	0.000321 U	0.000440 U	0.000479 U	0.00151 U	**0.000379 J**
IW-51A	IW-51A-5	3/26/18	PES	ESC	5	46.9	V	0.00515 U	0.000331 U	0.00151 U	0.000264 U	0.000224 U	0.0110 U	0.00197 U	0.000297 U	0.000312 U	0.000429 U	0.000466 U	0.00147 U	**0.000561 J**
(9.9 to-10.1)	IW-51A-10	3/26/18	PES	ESC	10	41.9	V	0.00510 U	0.000328 U	0.00149 U	0.000262 U	0.000222 U	0.0109 U	0.00195 U	0.000294 U	0.000310 U	0.000425 U	0.000462 U	0.00146 U	0.000241 U
	IW-51A-15	3/26/18	PES	ESC	15	36.9	V	**0.0807 J**	0.000341 U	0.00155 U	0.000272 U	0.000231 U	**0.186 J**	0.00203 U	0.000306 U	0.000322 U	0.000442 U	0.000481 U	0.00152 U	**0.00136**
	IW-51A-20	3/26/18	PES	ESC	20	31.9	S	**0.0108 J**	0.000326 U	0.00148 U	0.000260 U	0.000221 U	**0.0156 J**	0.00194 U	0.000293 U	0.000308 U	0.000423 U	0.000459 U	0.00145 U	**0.000312 J**
	IW-51A-25	3/26/18	PES	ESC	25	26.9	S	0.00646 U	0.000415 U	0.00189 U	0.000331 U	0.000281 U	0.0138 U	0.00247 U	0.000373 U	0.000392 U	0.000538 U	0.000585 U	0.00185 U	0.000305 U
	IW-51A-30	3/26/18	PES	ESC	30	21.9	S	0.00504 U	0.000324 U	0.00148 U	0.000259 U	0.000220 U	0.0108 U	0.00193 U	0.000291 U	0.000306 U	0.000420 U	0.000457 U	0.00144 U	0.000238 U
	IW-51A-35	3/26/18	PES	ESC	35	16.9	S	0.00510 U	0.000328 U	0.00149 U	0.000261 U	0.000222 U	0.0109 U	0.00195 U	0.000294 U	0.000309 U	0.000425 U	0.000462 U	0.00146 U	**0.000309 J**
	IW-51A-40	3/26/18	PES	ESC	40	11.9	S	0.00511 U	0.000329 U	0.00150 U	0.000262 U	0.000223 U	0.0109 U	0.00196 U	0.000295 U	0.000310 U	0.000426 U	0.000463 U	0.00146 U	**0.000784 J**
	IW-51A-42	3/26/18	PES	ESC	42	9.9	S	**0.0232 J**	0.000335 U	0.00153 U	0.000267 U	0.000227 U	0.0111 U	0.00199 U	0.000301 U	0.000316 U	0.000434 U	0.000472 U	0.00149 U	**0.00131**
	IW-51A-45	3/26/18	PES	ESC	45	6.9	S	0.00521 U	0.000335 U	0.00153 U	0.000267 U	0.000227 U	0.0111 U	0.00199 U	0.000301 U	0.000316 U	0.000434 U	0.000472 U	0.00149 U	**0.000486 J**
	IW-51A-50	3/26/18	PES	ESC	50	1.9	S	**0.0540**	0.000345 U	0.00157 U	0.000275 U	0.000234 U	**0.0181 J**	0.00205 U	**0.000378 J**	0.000325 U	0.000447 U	0.000486 U	0.00154 U	**0.000907 J**

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
IW-51A (continued)	IW-51A-55	3/26/18	PES	ESC	55	-3.1	S	**0.0160**	0.000345 U	0.00157 U	0.000275 U	0.000234 U	**0.0198 J**	0.00205 U	0.000310 U	0.000326 U	0.000447 U	0.000486 U	0.00154 U	**0.000492 J**
	IW-51A-60	3/26/18	PES	ESC	60	-8.1	S	0.00503 U	0.000324 U	0.00147 U	0.000258 U	0.000219 U	0.0108 U	0.00193 U	0.000290 U	0.000305 U	0.000420 U	0.000456 U	0.00144 U	**0.000255 J**
	IW-51A-62	3/26/18	PES	ESC	62	-10.1	S	0.00509 U	0.000327 U	0.00149 U	0.000261 U	0.000222 U	0.0109 U	0.00195 U	0.000294 U	0.000309 U	0.000424 U	0.000461 U	0.00146 U	**0.000264 J**
IW-53B (-11.1 to-26.1)	IW-53B-30	9/20/18	PES	ESC	30	5.3	S	0.136 U	0.00100 U	0.0109 U	0.00123 U	0.00253 U	0.149 U	0.00207 U	**0.000505 J**	0.00114 U	0.00123 U	0.00651 U	0.00402 U	0.00442 U
IW-54A (9.8 to-10.2)	IW-54A-8	9/12/18	PES	ESC	8	31.1	S	**0.0472**	0.00106 U	0.0115 U	0.00130 U	0.00269 U	3.16 U	0.00219 U	0.000462 U	0.00121 U	0.00130 U	0.00690 U	0.00427 U	0.00469 U
	IW-54A-49	9/12/18	PES	ESC	49	-9.9	S	0.0145 U	0.00107 U	0.0116 U	0.00131 U	0.00270 U	0.0159 U	0.00220 U	0.000463 U	0.00122 U	0.00131 U	0.00693 U	0.00429 U	0.00470 U
IW-54B (-9.5 to-24.5)	IW-54B-8	9/5/18	PES	ESC	8	31.2	S	**0.0224 J**	0.00100 U	0.0109 U	0.00123 U	0.00254 U	0.0149 U	0.00207 U	0.000436 U	0.00115 U	0.00123 U	0.00652 U	0.00404 U	0.00443 U
	IW-54B-13	9/6/18	PES	ESC	13	26.2	S	0.0139 U	0.00102 U	0.0111 U	0.00125 U	0.00258 U	**0.0186 J**	0.00211 U	0.000444 U	0.00116 U	0.00125 U	0.00663 U	0.00410 U	0.00450 U
	IW-54B-21	9/6/18	PES	ESC	21	18.2	S	**0.0152 J**	0.00100 U	0.0109 U	0.00123 U	0.00254 U	0.0149 U	0.00207 U	0.000436 U	0.00115 U	0.00123 U	0.00652 U	0.00404 U	0.00443 U
	IW-54B-33	9/6/18	PES	ESC	33	6.2	S	**0.0350**	0.00115 U	0.0125 U	0.00142 U	0.00291 U	0.0171 U	0.00237 U	**0.000702 J**	0.00131 U	0.00142 U	0.00748 U	0.00462 U	0.00507 U
IW-55B (-12.0 to-27.0)	IW-55B-39	9/13/18	PES	ESC	39	12.8	S	0.0133 U	0.000977 U	0.0106 U	0.00120 U	0.00247 U	**0.0413**	0.00202 U	0.000425 U	0.00111 U	0.00120 U	0.00635 U	0.00393 U	0.00431 U
	IW-55B-43	9/13/18	PES	ESC	43	8.8	S	**0.0163 J**	0.00104 U	0.0113 U	0.00128 U	0.00264 U	1.24 U	0.00215 U	0.000452 U	0.00119 U	0.00128 U	0.00676 U	0.00419 U	0.00459 U
	IW-55B-61	9/13/18	PES	ESC	61	-9.2	S	**0.0167 J**	0.00109 U	0.0119 U	0.00134 U	0.00277 U	**0.152 J**	0.00226 U	0.000475 U	0.00125 U	0.00134 U	0.00710 U	0.00440 U	**0.00631 J**
IW-58A (3.9 to-11.1)	IW-58A-38	10/17/18	PES	PACE	38	1.2	S	**0.0413**	0.00101 U	0.0109 U	0.00124 U	0.00255 U	0.150 U	0.00208 U	0.000437 U	0.00115 U	0.00124 U	0.00654 U	0.00404 U	0.00444 U
	B-929-38	10/17/18	PES	PACE	38 (dup)	1.2	S	**0.0306**	0.00104 U	0.0113 U	0.00127 U	0.00262 U	0.154 U	0.00214 U	0.000450 U	0.00118 U	0.00127 U	0.00673 U	0.00417 U	0.00457 U
MW101 (B101) (-65.5 to-75.5)	B101-30	7/10/12	SES	F&BI	30	9.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-34	7/10/12	SES	F&BI	34	5.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-40	7/10/12	SES	F&BI	40	-0.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-47	7/10/12	SES	F&BI	47	-7.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-48	7/10/12	SES	F&BI	48	-8.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-55	7/10/12	SES	F&BI	55	-15.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-65	7/10/12	SES	F&BI	65	-25.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-75	7/11/12	SES	F&BI	75	-35.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-81	7/11/12	SES	F&BI	81	-41.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-92	7/12/12	SES	F&BI	92	-52.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-97	7/12/12	SES	F&BI	97	-57.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-104	7/12/12	SES	F&BI	104	-64.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-114.5	7/12/12	SES	F&BI	114.5	-75.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-120	7/12/12	SES	F&BI	120	-80.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-131	7/12/12	SES	F&BI	131	-91.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-140	7/12/12	SES	F&BI	140	-100.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW130 (B130) (-30.9 to-40.9)	B130-10	3/1/16	SES	F&BI	10	29.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B130-20	3/1/16	SES	F&BI	20	19.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B130-30	3/1/16	SES	F&BI	30	9.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B130-40	3/1/16	SES	F&BI	40	-0.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B130-45	3/2/16	SES	F&BI	45	-5.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B130-50	3/2/16	SES	F&BI	50	-10.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B130-55	3/2/16	SES	F&BI	55	-15.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B130-60	3/2/16	SES	F&BI	60	-20.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B130-65	3/2/16	SES	F&BI	65	-25.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B130-70	3/2/16	SES	F&BI	70	-30.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
MW130 (B130)	B130-75	3/2/16	SES	F&BI	75	-35.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
(continued)	B130-80	3/2/16	SES	F&BI	80	-40.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW131 (B131)	B131-10	3/1/16	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
(-4.2 to-14.2)	B131-20	3/1/16	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B131-30	3/1/16	SES	F&BI	30	10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B131-40	3/1/16	SES	F&BI	40	0.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B131-45	3/2/16	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B131-55	3/2/16	SES	F&BI	55	-15.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-132	MW-132-20	8/22/17	PES	ESC	20	20.1	S	0.00522 U	0.000336 U	0.00153 U	0.000268 U	0.000227 U	0.0112 U	0.00200 U	0.000301 U	0.000317 U	0.000435 U	0.000473 U	0.00149 U	0.000246 U
(-29.9 to-39.9)	MW-132-35	8/22/17	PES	ESC	35	5.1	S	0.00524 U	0.000337 U	0.00153 U	0.000269 U	0.000228 U	0.0112 U	0.00200 U	0.000302 U	0.000318 U	0.000436 U	0.000474 U	0.00150 U	**0.00118 J**
	MW-132-50	8/22/17	PES	ESC	50	-9.9	S	0.00506 U	0.000326 U	0.00148 U	0.000260 U	0.000221 U	**0.0231 J**	0.00194 U	0.000292 U	0.000307 U	0.000422 U	0.000459 U	0.00145 U	**0.00341 J**
	MW-132-55	8/23/17	PES	ESC	55	-14.9	S	0.538 U	0.0346 U	0.158 U	0.0276 U	0.0235 U	1.15 U	0.206 U	0.0310 U	0.0327 U	0.0448 U	0.0488 U	0.154 U	0.0254 U
	MW-132-60	8/23/17	PES	ESC	60	-19.9	S	0.00504 U	0.000324 U	0.00148 U	0.000258 U	0.000220 U	**0.0149 J**	0.00193 U	0.000291 U	0.000306 U	0.000420 U	0.000457 U	0.00144 U	**0.00175 J**
	MW-132-70	8/23/17	PES	ESC	70	-29.9	S	0.00571 U	0.000367 U	0.00167 U	0.000293 U	0.000249 U	**0.0182 J**	0.00218 U	0.000329 U	0.000346 U	0.000475 U	0.000517 U	0.00163 U	**0.000464 J**
	MW-132-83	8/23/17	PES	ESC	83	-42.9	S	0.00510 U	0.000328 U	0.00149 U	0.000262 U	0.000223 U	**0.0262 J**	0.00195 U	**0.000302 J**	0.000310 U	0.000425 U	0.000463 U	0.00146 U	**0.00271**
MW-133	MW-133-20	8/15/17	PES	ESC	20	20.1	S	0.00552 U	0.000355 U	0.00161 U	0.000283 U	0.000240 U	**0.0279 J**	0.00211 U	**0.000422 J**	0.000335 U	0.000460 U	0.000500 U	0.00158 U	**0.00252**
(-88.9 to-98.9)	MW-133-35	8/15/17	PES	ESC	35	5.1	S	**0.0258**	0.000393 U	0.00179 U	0.000313 U	0.000266 U	**0.169**	0.00234 U	0.000353 U	0.000371 U	0.000509 U	0.000554 U	0.00175 U	**0.000593 J**
	MW-133-45	8/15/17	PES	ESC	45	-4.9	S	0.00509 U	0.000327 U	0.00149 U	0.000261 U	0.000222 U	**0.0142 J**	0.00195 U	0.000293 U	0.000309 U	0.000424 U	0.000461 U	0.00146 U	**0.00239**
	MW-133-55	8/15/17	PES	ESC	55	-14.9	S	1.14 U	0.0736 U	0.335 U	0.0587 U	**0.0804 J**	2.45 U	0.438 U	0.0661 U	0.0695 U	0.0954 U	0.104 U	0.328 U	0.0541 U
	MW-133-58	8/15/17	PES	ESC	58	-17.9	S	27.7 U	1.77 U	8.10 U	1.42 U	1.21 U	59.1 U	10.6 U	1.60 U	1.68 U	2.31 U	2.51 U	7.92 U	1.30 U
	MW-133-65	8/15/17	PES	ESC	65	-24.9	S	0.00542 U	0.000348 U	0.00159 U	0.000278 U	0.000236 U	**0.0188 J**	0.00207 U	0.000313 U	0.000329 U	0.000451 U	0.000491 U	0.00155 U	**0.00554**
	MW-133-75	8/15/17	PES	ESC	75	-34.9	S	0.00544 U	0.000350 U	0.00159 U	0.000279 U	0.000237 U	0.0116 U	0.00208 U	0.000314 U	0.000330 U	0.000454 U	0.000493 U	0.00156 U	**0.000728 J**
	MW-133-85	8/15/17	PES	ESC	85	-44.9	S	0.137 U	0.00882 U	0.0401 U	0.00703 U	0.00598 U	0.293 U	0.0525 U	0.00791 U	0.00832 U	0.0114 U	0.0124 U	0.0393 U	0.00647 U
	MW-133-95	8/16/17	PES	ESC	95	-54.9	S	0.00545 U	0.000351 U	0.00160 U	0.000280 U	0.000238 U	0.0116 U	0.00209 U	0.000315 U	0.000331 U	0.000454 U	0.000494 U	0.00156 U	0.000257 U
	MW-133-105	8/16/17	PES	ESC	105	-64.9	S	0.00563 U	0.000362 U	0.00165 U	0.000289 U	0.000246 U	0.0120 U	0.00216 U	0.000325 U	0.000342 U	0.000470 U	0.000511 U	0.00161 U	0.000266 U
	MW-133-120	8/16/17	PES	ESC	120	-79.9	S	0.127 U	0.00817 U	0.0372 U	0.00652 U	0.00554 U	0.272 U	0.0487 U	0.00734 U	0.00772 U	0.0106 U	0.0115 U	0.0364 U	0.00600 U
	MW-133-130	8/16/17	PES	ESC	130	-89.9	S	0.00558 U	0.000359 U	0.00163 U	0.000286 U	0.000243 U	0.0119 U	0.00213 U	0.000322 U	0.000338 U	0.000465 U	0.000505 U	0.00160 U	0.000263 U
	MW-133-135	8/16/17	PES	ESC	135	-94.9	S	**0.0156**	0.000341 U	0.00155 U	0.000272 U	0.000231 U	**0.0172 J**	0.00203 U	**0.00369**	0.000322 U	0.000442 U	0.000480 U	0.00152 U	0.000250 U
	MW-133-141	8/16/17	PES	ESC	141	-100.9	S	0.00527 U	0.000339 U	0.00154 U	0.000270 U	0.000230 U	0.0113 U	0.00202 U	**0.000766 J**	0.000320 U	0.000439 U	0.000478 U	0.00151 U	**0.00232**
MW-134	MW-134-20	8/29/17	PES	ESC	20	21.5	S	0.00616 U	0.000396 U	0.00180 U	0.000316 U	0.000268 U	**0.0219 J**	0.00236 U	0.00197 U	0.000374 U	0.000513 U	0.000558 U	0.00176 U	**0.000769 J**
(-38.6 to-48.6)	MW-134-43	8/29/17	PES	ESC	43	-1.6	S	0.00543 U	0.000349 U	0.00159 U	0.000278 U	0.000237 U	0.0116 U	0.00208 U	0.000313 U	0.000330 U	0.000453 U	0.000492 U	0.00155 U	**0.00115 J**
	MW-134-50	8/29/17	PES	ESC	50	-8.6	S	0.00515 U	0.000331 U	0.00151 U	0.000264 U	0.000224 U	0.0110 U	0.00197 U	0.000297 U	0.000312 U	0.000429 U	0.000466 U	0.00147 U	**0.000786 J**
	MW-134-60	8/29/17	PES	ESC	60	-18.6	S	0.00517 U	0.000332 U	0.00151 U	0.000265 U	0.000225 U	**0.0221 J**	0.00198 U	0.000298 U	0.000314 U	0.000431 U	0.000468 U	0.00148 U	**0.00223**
	MW-134-70	8/29/17	PES	ESC	70	-28.6	S	0.00597 U	0.000384 U	0.00175 U	0.000306 U	0.000260 U	0.0128 U	0.00228 U	0.000344 U	0.000362 U	0.000497 U	0.000541 U	0.00171 U	**0.00153**
	MW-134-80	8/29/17	PES	ESC	80	-38.6	S	0.00501 U	0.000322 U	0.00147 U	0.000257 U	0.000218 U	0.0107 U	0.00191 U	0.000289 U	0.000304 U	0.000417 U	0.000453 U	0.00143 U	**0.000414 J**
	B-903-100	8/29/17	PES	ESC	80 (dup)	-38.6	S	0.00493 U	0.000317 U	0.00144 U	0.000253 U	0.000215 U	0.0105 U	0.00189 U	0.000284 U	0.000299 U	0.000411 U	0.000447 U	0.00141 U	**0.000563 J**
	MW-134-90	8/29/17	PES	ESC	90	-48.6	S	0.00594 U	0.000382 U	0.00174 U	0.000305 U	0.000259 U	0.0127 U	0.00227 U	0.000343 U	0.000361 U	0.000495 U	0.000538 U	0.00170 U	**0.000666 J**
MW-135	MW-135-16	8/24/17	PES	ESC	14	25.1	S	0.571 U	0.0367 U	0.167 U	0.0293 U	**0.681**	1.22 U	0.218 U	0.0329 U	0.0346 U	0.0476 U	0.0517 U	0.163 U	0.0270 U
(-30.9 to-40.9)	MW-135-20	8/24/17	PES	ESC	20	19.1	S	0.133 U	0.00857 U	0.0390 U	0.00683 U	0.00581 U	0.285 U	0.0510 U	0.00769 U	0.00809 U	0.0111 U	0.0121 U	0.0382 U	0.00629 U
	MW-135-30	8/24/17	PES	ESC	30	9.1	S	0.00497 U	0.000320 U	0.00146 U	0.000255 U	**0.00354**	**0.0148 J**	0.00190 U	0.000287 U	0.000302 U	0.000414 U	0.000450 U	0.00142 U	**0.00300**
	MW-135-36	8/24/17	PES	ESC	36	3.1	S	0.00546 U	0.000351 U	0.00160 U	0.000280 U	0.000238 U	0.0117 U	0.00209 U	0.000315 U	0.000332 U	0.000455 U	0.000495 U	0.00156 U	0.000258 U
	MW-135-40	8/24/17	PES	ESC	40	-0.9	S	0.00558 U	0.000359 U	0.00163 U	0.000286 U	0.000243 U	0.0119 U	0.00213 U	0.000322 U	0.000339 U	0.000465 U	0.000506 U	0.00160 U	0.000264 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
MW-135 (continued)	MW-135-45	8/24/17	PES	ESC	45	-5.9	S	0.00556 U	0.000357 U	0.00163 U	0.000285 U	0.000242 U	0.0119 U	0.00213 U	0.000321 U	0.000337 U	0.000463 U	0.000503 U	0.00159 U	**0.00207**
	MW-135-55	8/24/17	PES	ESC	55	-15.9	S	0.00508 U	0.000327 U	0.00149 U	0.000261 U	0.000222 U	**0.0148 J**	0.00194 U	0.000293 U	0.000309 U	0.000424 U	0.000461 U	0.00146 U	**0.00114**
	MW-135-65	8/24/17	PES	ESC	65	-25.9	S	0.00555 U	0.000357 U	0.00163 U	0.000285 U	0.000242 U	0.0119 U	0.00212 U	0.000320 U	0.000337 U	0.000463 U	0.000503 U	0.00159 U	**0.00101 J**
	MW-135-80	8/24/17	PES	ESC	80	-40.9	S	0.00523 U	0.000336 U	0.00153 U	0.000268 U	0.000228 U	**0.0167 J**	0.00200 U	0.000302 U	0.000317 U	0.000436 U	0.000474 U	0.00150 U	**0.000867 J**
MW-136 (-32.7 to-42.7)	MW-136-35	8/28/17	PES	ESC	35	16.9	S	0.00493 U	0.000317 U	0.00144 U	0.000253 U	0.000215 U	**0.0121 J**	0.00188 U	0.000284 U	0.000299 U	0.000410 U	0.000446 U	0.00141 U	**0.00210 J**
	B-902-15	8/28/17	PES	ESC	35 (dup)	16.9	S	0.00511 U	0.000329 U	0.00150 U	0.000262 U	0.000223 U	0.0109 U	0.00196 U	0.000295 U	0.000310 U	0.000426 U	0.000463 U	0.00146 U	**0.00126 J**
	MW-136-44	8/28/17	PES	ESC	44	7.9	S	**0.0640**	0.000338 U	0.00154 U	0.000269 U	0.000229 U	**0.0239 J**	0.00201 U	0.000303 U	0.000319 U	0.000438 U	0.000476 U	0.00150 U	**0.00112 J**
	MW-136-50	8/28/17	PES	ESC	50	1.9	S	**0.0103 J**	0.000346 U	0.00158 U	0.000276 U	0.000235 U	**0.0403 J**	0.00206 U	0.000311 U	0.000327 U	0.000449 U	0.000488 U	0.00154 U	**0.00138**
	MW-136-65	8/28/17	PES	ESC	65	-13.1	S	0.00509 U	0.000327 U	0.00149 U	0.000261 U	0.000222 U	**0.0178 J**	0.00195 U	**0.000838 J**	0.000309 U	0.000424 U	0.000461 U	0.00146 U	**0.00256**
	MW-136-75	8/28/17	PES	ESC	75	-23.1	S	0.00520 U	0.000334 U	0.00152 U	0.000267 U	0.000227 U	0.0111 U	0.00199 U	0.000300 U	0.000315 U	0.000433 U	0.000471 U	0.00149 U	**0.000260 J**
	MW-136-85	8/28/17	PES	ESC	85	-33.1	S	0.00522 U	0.000336 U	0.00153 U	0.000268 U	0.000228 U	0.0112 U	0.00200 U	0.000301 U	0.000317 U	0.000435 U	0.000473 U	0.00150 U	**0.000451 J**
	MW-136-95	8/28/17	PES	ESC	95	-43.1	S	0.00524 U	0.000337 U	0.00153 U	0.000269 U	0.000228 U	0.0112 U	0.00200 U	0.000302 U	0.000318 U	0.000436 U	0.000474 U	0.00150 U	0.000247 U
MW-137 (-53.3 to-63.3)	MW-137-25	8/31/17	PES	ESC	25	26.7	S	0.00510 U	0.000328 U	0.00149 U	0.000262 U	0.000223 U	0.0109 U	0.00195 U	0.000294 U	0.000310 U	0.000425 U	0.000462 U	0.00146 U	0.000241 U
	MW-137-45	8/31/17	PES	ESC	45	6.7	S	0.132 U	0.00851 U	0.0387 U	0.00679 U	0.00577 U	0.283 U	0.0507 U	0.00764 U	0.00803 U	0.0110 U	0.0120 U	0.0379 U	0.00625 U
	MW-137-75	8/31/17	PES	ESC	75	-23.3	S	0.00514 U	0.000330 U	0.00150 U	0.000264 U	0.000224 U	**0.0138 J**	0.00197 U	**0.000533 J**	0.000312 U	0.000428 U	0.000466 U	0.00147 U	**0.000859 J**
	MW-137-85	9/1/17	PES	ESC	85	-33.3	S	0.00561 U	0.000361 U	0.00164 U	0.000288 U	0.000244 U	0.0120 U	0.00215 U	0.000324 U	0.000340 U	0.000467 U	0.000508 U	0.00161 U	**0.00141**
	MW-137-95	9/1/17	PES	ESC	95	-43.3	S	0.00501 U	0.000322 U	0.00147 U	0.000257 U	0.000218 U	0.0107 U	0.00192 U	0.000289 U	0.000304 U	0.000418 U	0.000454 U	0.00143 U	**0.000537 J**
	MW-137-115	9/1/17	PES	ESC	115	-63.3	S	0.00573 U	0.000368 U	0.00168 U	0.000294 U	0.000250 U	0.0122 U	0.00219 U	0.000330 U	0.000347 U	0.000477 U	0.000519 U	0.00164 U	0.000270 U
MW-139 (-30.2 to-40.2)	MW-139-20	9/13/17	PES	ESC	20	19.8	S	0.00541 U	0.000348 U	0.00158 U	0.000278 U	0.000236 U	0.0116 U	0.00207 U	0.000312 U	0.000329 U	0.000451 U	0.000490 U	0.00155 U	**0.000485 J**
	MW-139-31	9/13/17	PES	ESC	31	8.8	S	0.00501 U	0.000322 U	0.00147 U	0.000257 U	0.000218 U	0.0107 U	0.00192 U	0.000289 U	0.000304 U	0.000417 U	0.000454 U	0.00143 U	**0.000694 J**
	MW-139-41	9/13/17	PES	ESC	41	-1.2	S	0.00503 U	0.000323 U	0.00147 U	0.000258 U	0.000219 U	**0.0153 J**	0.00192 U	0.000290 U	0.000305 U	0.000419 U	0.000455 U	0.00144 U	**0.00149**
	MW-139-51	9/13/17	PES	ESC	51	-11.2	S	0.00540 U	0.000347 U	0.00158 U	0.000277 U	0.000235 U	**0.0147 J**	0.00207 U	0.000312 U	0.000328 U	0.000450 U	0.000489 U	0.00155 U	**0.000918 J**
	MW-139-60	9/13/17	PES	ESC	60	-20.2	S	0.00503 U	0.000323 U	0.00147 U	0.000258 U	0.000219 U	0.0107 U	0.00192 U	0.000290 U	0.000305 U	0.000419 U	0.000455 U	0.00144 U	**0.000528 J**
	MW-139-70	9/13/17	PES	ESC	70	-30.2	S	0.00552 U	0.000355 U	0.00162 U	0.000283 U	0.000241 U	**0.0118 J**	0.00211 U	0.000319 U	0.000335 U	0.000460 U	0.000500 U	0.00158 U	**0.000621 J**
	MW-139-80	9/13/17	PES	ESC	80	-40.2	S	0.00529 U	0.000340 U	0.00155 U	0.000271 U	0.000231 U	0.0113 U	0.00202 U	0.000305 U	0.000321 U	0.000441 U	0.000479 U	0.00151 U	**0.000551 J**
MW-141 (-55.4 to-65.4)	MW-141-15	9/18/17	PES	ESC	15	24.6	S	**0.179 J**	0.000340 U	0.00155 U	0.000271 U	0.000230 U	**0.382 J**	0.00202 U	0.000305 U	0.000320 U	0.000440 U	0.000478 U	0.00151 U	0.000249 U
	MW-141-35	9/18/17	PES	ESC	35	4.6	S	0.00543 U	0.000349 U	0.00159 U	0.000278 U	0.000237 U	0.0116 U	0.00208 U	0.000313 U	0.000330 U	0.000452 U	0.000492 U	0.00155 U	**0.000351 J**
	MW-141-46	9/18/17	PES	ESC	46	-6.4	S	0.00512 U	0.000329 U	0.00150 U	0.000262 U	0.000223 U	**0.0198 J**	0.00196 U	0.000295 U	0.000311 U	0.000426 U	0.000464 U	0.00147 U	**0.00126**
	MW-141-56	9/18/17	PES	ESC	56	-16.4	S	0.00498 U	0.000320 U	0.00146 U	0.000255 U	0.000217 U	0.0106 U	0.00190 U	0.000287 U	0.000302 U	0.000415 U	0.000451 U	0.00143 U	**0.000836 J**
	MW-141-65	9/18/17	PES	ESC	65	-25.4	S	0.00492 U	0.000317 U	0.00144 U	0.000252 U	0.000215 U	**0.0110 J**	0.00188 U	0.000284 U	0.000299 U	0.000410 U	0.000446 U	0.00141 U	**0.000894 J**
	MW-141-75	9/18/17	PES	ESC	75	-35.4	S	0.00499 U	0.000321 U	0.00146 U	0.000256 U	0.000217 U	**0.0160 J**	0.00191 U	**0.000480 J**	0.000303 U	0.000416 U	0.000452 U	0.00143 U	**0.00357**
	MW-141-85	9/18/17	PES	ESC	85	-45.4	S	0.00547 U	0.000352 U	0.00160 U	0.000280 U	0.000238 U	0.0117 U	0.00209 U	0.000315 U	0.000332 U	0.000455 U	0.000495 U	0.00156 U	**0.000448 J**
	MW-141-95	9/18/17	PES	ESC	95	-55.4	S	0.00561 U	0.000361 U	0.00164 U	0.000287 U	0.000244 U	0.0120 U	0.00214 U	0.000323 U	0.000340 U	0.000467 U	0.000508 U	0.00161 U	0.000265 U
	MW-141-105	9/19/17	PES	ESC	105	-65.4	S	0.00559 U	0.000359 U	0.00164 U	0.000287 U	0.000244 U	0.0119 U	0.00214 U	0.000322 U	0.000339 U	0.000466 U	0.000506 U	0.00160 U	0.000264 U
MW-152 (-10.2 to-20.2)	MW-152-5	3/13/18	PES	ESC	5	34.1	S	0.00527 U	0.000339 U	0.00154 U	0.000270 U	0.000230 U	0.0113 U	0.00202 U	0.000304 U	0.000320 U	0.000439 U	0.000478 U	0.00151 U	**0.000505 J**
	MW-152-15	3/13/18	PES	ESC	15	24.1	S	0.00518 U	0.000333 U	0.00152 U	0.000266 U	0.000226 U	0.0111 U	0.00198 U	0.000299 U	0.000315 U	0.000432 U	0.000470 U	0.00148 U	**0.000864 J**
	MW-152-25	3/13/18	PES	ESC	25	14.1	S	0.00508 U	0.000327 U	0.00149 U	0.000260 U	0.000221 U	0.0108 U	0.00194 U	0.000293 U	0.000308 U	0.000423 U	0.000460 U	0.00145 U	**0.000702 J**
	MW-152-35	3/13/18	PES	ESC	35	4.1	S	0.00513 U	0.000330 U	0.00150 U	0.000263 U	0.000224 U	**0.0112 J**	0.00196 U	0.000296 U	0.000311 U	0.000428 U	0.000465 U	0.00147 U	**0.00130**
	MW-152-45	3/13/18	PES	ESC	45	-5.9	S	0.00528 U	0.000339 U	0.00154 U	0.000271 U	**0.000446 J**	0.0113 U	0.00202 U	0.000304 U	0.000320 U	0.000440 U	0.000478 U	0.00151 U	**0.00108 J**
	MW-152-55	3/13/18	PES	ESC	55	-15.9	S	0.00530 U	0.000341 U	0.00155 U	0.000272 U	0.000231 U	0.0113 U	0.00203 U	0.000306 U	0.000322 U	0.000442 U	0.000480 U	0.00152 U	**0.00132**
	MW-152-60	3/13/18	PES	ESC	60	-20.9	S	0.00506 U	0.000326 U	0.00148 U	0.000260 U	0.000221 U	0.0108 U	0.00194 U	0.000292 U	0.000307 U	0.000422 U	0.000459 U	0.00145 U	**0.000566 J**

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
MW-162	MW-162-48	1/28/19	PES	PACE	48	-9.6	S	0.270 U	0.0199 U	0.216 U	0.0245 U	0.0504 U	0.296 U	0.0411 U	0.00865 U	0.0227 U	0.0245 U	0.130 U	0.0801 U	0.0878 U
(-61.6 to-71.6)	MW-162-50	1/28/19	PES	PACE	50	-11.6	S	0.292 U	0.00107 U	0.0117 U	0.00132 U	0.00272 U	0.320 U	0.00222 U	0.000467 U	0.00123 U	0.00132 U	0.00699 U	0.00432 U	0.00474 U
	B-930-50 (dup)	1/28/19	PES	PACE	50	-11.6	S	0.556 U	0.00102 U	0.0111 U	0.00126 U	0.00259 U	0.609 U	0.00211 U	**0.000494 J**	0.00117 U	0.00126 U	0.00665 U	0.00411 U	0.00451 U
	MW-162-67	1/28/19	PES	PACE	67	-28.6	S	0.290 U	0.00107 U	0.0116 U	0.00131 U	0.00271 U	**0.736**	0.00211 U	0.000465 U	0.00122 U	0.00131 U	0.00695 U	0.00430 U	0.00472 U
	MW-162-70	1/28/19	PES	PACE	70	-31.6	S	0.558 U	0.00103 U	0.0112 U	0.00126 U	0.00260 U	**1.72**	0.00212 U	**0.000937 J**	0.00117 U	0.00126 U	0.00668 U	0.00413 U	0.00453 U
	MW-162-72	1/28/19	PES	PACE	72	-33.6	S	0.539 U	0.000993 U	0.0108 U	0.00122 U	0.00251 U	**1.75**	0.00205 U	0.000432 U	0.00113 U	0.00122 U	0.00645 U	0.00399 U	0.00438 U
	MW-162-80	1/28/19	PES	PACE	80	-41.6	S	**0.0241 J**	0.00102 U	0.0111 U	0.00126 U	0.00259 U	**0.0329 J**	0.00211 U	**0.000450 J**	0.00117 U	0.00126 U	0.00666 U	0.00412 U	0.00452 U
	MW-162-85	1/28/19	PES	PACE	85	-46.6	S	**0.0192 J**	0.00104 U	0.0113 U	0.00128 U	0.00264 U	**0.0240 J**	0.00215 U	**0.000535 J**	0.00119 U	0.00128 U	0.00677 U	0.00419 U	0.00460 U
	MW-162-90	1/28/19	PES	PACE	90	-51.6	S	0.0141 U	0.00104 U	0.0113 U	0.00128 U	0.00263 U	**0.0277 J**	0.00215 U	0.000452 U	0.00119 U	0.00128 U	0.00676 U	0.00418 U	0.00459 U
	MW-162-95	1/28/19	PES	PACE	95	-56.6	S	0.0143 U	0.00106 U	0.0115 U	0.00130 U	0.00267 U	**0.0236 J**	0.00218 U	0.000459 U	0.00120 U	0.00130 U	0.00686 U	0.00425 U	0.00466 U
	MW-162-100	1/28/19	PES	PACE	100	-61.6	S	**0.0200 J**	0.00107 U	0.0117 U	0.00132 U	0.00272 U	**0.0227 J**	0.00222 U	0.000467 U	0.00123 U	0.00132 U	0.00698 U	0.00432 U	0.00474 U
	MW-162-105	1/28/19	PES	PACE	105	-66.6	S	**0.0251 J**	0.00103 U	0.0112 U	0.00127 U	0.00262 U	**0.0259 J**	0.00214 U	0.000450 U	0.00118 U	0.00127 U	0.00672 U	0.00416 U	0.00456 U
	MW-162-110	1/28/19	PES	PACE	110	-71.6	S	**0.0213 J**	0.00101 U	0.0109 U	0.00124 U	0.00255 U	**0.0196**	0.00208 U	0.000438 U	0.00115 U	0.00124 U	0.00655 U	0.00405 U	0.00444 U
MW-163	MW-163-47	1/29/19	PES	PACE	47	-7.7	S	0.280 U	0.00103 U	0.0112 U	0.00126 U	0.00261 U	**1.30**	0.00212 U	**0.000517 J**	0.00117 U	0.00126 U	0.00669 U	0.00414 U	0.00454 U
(-61.0 to-71.0)	MW-163-50	1/29/19	PES	PACE	50	-10.7	S	0.270 U	0.000994 U	0.0108 U	0.00122 U	0.00252 U	**0.797**	0.00205 U	**0.000594 J**	0.00113 U	0.00122 U	0.00646 U	0.00400 U	0.00439 U
	MW-163-55	1/29/19	PES	PACE	55	-15.7	S	0.306 U	0.00113 U	0.0123 U	0.00138 U	0.00286 U	**1.36**	0.00233 U	**0.000680 J**	0.00129 U	0.00138 U	0.00733 U	0.00453 U	0.00498 U
	MW-163-60	1/29/19	PES	PACE	60	-20.7	S	0.283 U	0.00104 U	0.0113 U	0.00128 U	0.00264 U	**0.658 J**	0.00215 U	0.000453 U	0.00119 U	0.00128 U	0.00677 U	0.00419 U	0.00460 U
	MW-163-80	1/29/19	PES	PACE	80	-40.7	S	**0.0218 J**	0.00105 U	0.0114 U	0.00128 U	0.00265 U	**0.0178 J**	0.00216 U	0.000455 U	0.00119 U	0.00128 U	0.00680 U	0.00421 U	0.00462 U
	MW-163-85	1/29/19	PES	PACE	85	-45.7	S	**0.0227 J**	0.00109 U	0.0118 U	0.00134 U	0.00276 U	**0.0289 J**	0.00225 U	0.000473 U	0.00124 U	0.00134 U	0.00708 U	0.00438 U	0.00481 U
	MW-163-90	1/29/19	PES	PACE	90	-50.7	S	**0.0197 J**	0.000998 U	0.0108 U	0.00123 U	0.00253 U	**0.0249**	0.00206 U	0.000434 U	0.00114 U	0.00123 U	0.00648 U	0.00401 U	0.00440 U
	MW-163-95	1/29/19	PES	PACE	95	-55.7	S	**0.0289 J**	0.00109 U	0.0119 U	0.00134 U	0.00276 U	0.0378 U	0.00225 U	**0.000633 J**	0.00124 U	0.00134 U	0.00709 U	0.00439 U	0.00481 U
	MW-163-100	1/29/19	PES	PACE	100	-60.7	S	**0.0199 J**	0.00106 U	0.0115 U	0.00130 U	0.00268 U	**0.0157 J**	0.00218 U	**0.000590 J**	0.00121 U	0.00130 U	0.00687 U	0.00425 U	0.00466 U
	MW-163-105	1/29/19	PES	PACE	105	-65.7	S	**0.0183 J**	0.000966 U	0.0105 U	0.00119 U	0.00245 U	**0.0157**	0.00199 U	0.000420 U	0.00110 U	0.00119 U	0.00628 U	0.00388 U	0.00426 U
	MW-163-110	1/29/19	PES	PACE	110	-70.7	S	**0.0220 J**	0.00102 U	0.0111 U	0.00125 U	0.00258 U	**0.0280**	0.00211 U	**0.000587 J**	0.00116 U	0.00125 U	0.00663 U	0.00410 U	0.00450 U
MW-164	MW-164-80	1/24/19	PES	PACE	80	-40.3	S	0.0142 U	0.00105 U	0.0114 U	0.00129 U	0.00265 U	**0.0247**	0.00216 U	0.000455 U	0.00120 U	0.00129 U	0.00681 U	0.00421 U	0.00462 U
(-59.9 to-69.9)	MW-164-87	1/24/19	PES	PACE	87	-47.3	S	**0.0327**	0.00103 U	0.0112 U	0.00126 U	0.00261 U	**0.0393**	0.00213 U	0.000448 U	0.00118 U	0.00126 U	0.00669 U	0.00414 U	0.00454 U
	MW-164-90	1/24/19	PES	PACE	90	-50.3	S	**0.0262 J**	0.00108 U	0.0117 U	0.00132 U	0.00273 U	**0.0281**	0.00223 U	0.000468 U	0.00123 U	0.00132 U	0.00700 U	0.00433 U	0.00476 U
	MW-164-95	1/25/19	PES	PACE	95	-55.3	S	**0.0435**	0.00110 U	0.0120 U	0.00135 U	0.00279 U	**0.0365**	0.00227 U	0.000478 U	0.00126 U	0.00135 U	0.00715 U	0.00442 U	0.00486 U
	MW-164-100	1/25/19	PES	PACE	100	-60.3	S	**0.0446**	0.00115 U	0.0125 U	0.00141 U	0.00291 U	**0.0332**	0.00238 U	0.000500 U	0.00131 U	0.00141 U	0.00748 U	0.00463 U	0.00508 U
	MW-164-105	1/25/19	PES	PACE	105	-65.3	S	**0.0328**	0.00102 U	0.0111 U	0.00125 U	0.00258 U	**0.0311**	0.00211 U	0.000444 U	0.00116 U	0.00125 U	0.00663 U	0.00410 U	0.00450 U
	MW-164-110	1/25/19	PES	PACE	110	-70.3	S	**0.0322**	0.00101 U	0.0110 U	0.00125 U	0.00257 U	**0.0374**	0.00210 U	0.000441 U	0.00116 U	0.00125 U	0.00659 U	0.00408 U	0.00448 U
	B-929-120	1/25/19	PES	PACE	110 (dup)	-70.3	S	**0.0290**	0.00103 U	0.0112 U	0.00127 U	0.00262 U	**0.0417**	0.00213 U	0.000449 U	0.00118 U	0.00127 U	0.00672 U	0.00416 U	0.00456 U
MW-168 (-43.0 to -53.0)	MW-168-15	10/21/19	PES	Fremont	15	-3.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-171 (-27.6 to -37.6)	MW-171-24	09/24/19	PES	Fremont	24	-12.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-172 (-42.5 to -52.5)	MW-172-7	09/26/19	PES	Fremont	7	4.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-175	MW-175-12	10/26/19	PES	Fremont	12	-1.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
(-27.8 to -37.8)	B-1002-12	10/26/19	PES	Fremont	12 (dup)	-1.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	**–**	**–**	**29**	**0.030**	**0.027**	**0.56**	**–**	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	**–**	**–**	**2.1**	**0.030**	**0.002**	**0.033**	**–**	**0.023**	**0.0033**	**0.27**
MW-180 (-42.7 to -52.7)	MW-180-40	09/25/19	PES	Fremont	40	-28.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW-180-24	09/25/19	PES	Fremont	24	-12.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW-180-27	09/25/19	PES	Fremont	27	-15.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-181 (1.5 to -8.5)	MW-181-14	09/27/19	PES	Fremont	14	-2.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-183 (-27.4 to -37.4)	MW-183-18	09/26/19	PES	Fremont	18	-6.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-184 (-42.5 to -52.5)	MW-184-20	09/26/19	PES	Fremont	20	-8.4	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-188 (-42.2 to -52.2)	MW-188-64	10/01/19	PES	Fremont	64	-52.4	S	–	–	–	–	–	–	–	–	–	–	–	–	–
P01	P01-05	2/12/14	SES	F&BI	5	35.5	S	–	–	–	–	–	–	–	0.020 U	–	–	–	–	–
	P01-10	2/12/14	SES	F&BI	10	30.5	S	–	–	–	–	–	–	–	0.020 U	–	–	–	–	–
P02	P02-05	2/12/14	SES	F&BI	5	34.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	P02-07.5	2/12/14	SES	F&BI	7.5	32.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
P03	P03-05	2/12/14	SES	F&BI	5	34.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
P03	P03-07.5	2/12/14	SES	F&BI	7.5	32.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
P04	P04-05	2/12/14	SES	F&BI	7.5	32.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	P04-10	2/12/14	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
P05	P05-05	2/12/14	SES	F&BI	5	35.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	P05-07.5	2/12/14	SES	F&BI	7.5	32.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
P06	P06-07.5	2/12/14	SES	F&BI	7.5	32.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	P06-10	2/12/14	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
R-MW1	Unknown	10/22/92	Roux	Unknown	5	32.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
W-MW-03 (P-07)	SB-W-07-0135	1/26/12	WW	ARI	13.5-14	25.2	S	–	–	–	–	–	–	–	**0.0007 J**	–	–	–	–	–
	SB-W-07-0275	1/26/12	WW	ARI	27.5-28	11.2	S	–	–	–	–	–	–	–	**0.0005 J**	–	–	–	–	–
	SB-W-07-0335	1/26/12	WW	ARI	33.5-34	5.2	S	–	–	–	–	–	–	–	0.0008 U	–	–	–	–	–
	SB-W-07-0430	1/26/12	WW	ARI	43-43.5	-4.3	S	–	–	–	–	–	–	–	0.0008 U	–	–	–	–	–
	SB-W-07-0530	1/26/12	WW	ARI	53-53.5	-14.3	S	–	–	–	–	–	–	–	0.0008 U	–	–	–	–	–
	SB-W-07-0630	1/26/12	WW	ARI	63-63.5	-24.3	S	–	–	–	–	–	–	–	0.0010 U	–	–	–	–	–
	SB-W-07-0780	1/26/12	WW	ARI	78-78.5	-39.3	S	–	–	–	–	–	–	–	0.0008 U	–	–	–	–	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
W-MW-04 (P-08)	SB-W-08-0090	1/28/12	WW	ARI	9-9.5	26.0	S	–	–	–	–	–	–	–	0.27 U	–	–	–	–	–
	SB-W-08-0155	1/28/12	WW	ARI	15.5-16	19.5	S	–	–	–	–	–	–	–	0.0009 U	–	–	–	–	–
	SB-W-08-0265	1/28/12	WW	ARI	26.5-27	8.5	S	–	–	–	–	–	–	–	0.0009 U	–	–	–	–	–
	SB-W-08-0380	1/28/12	WW	ARI	38-38.5	-3.0	S	–	–	–	–	–	–	–	0.0008 U	–	–	–	–	–
	SB-W-08-0480	1/28/12	WW	ARI	48-48.5	-13.0	S	–	–	–	–	–	–	–	**0.0005 J**	–	–	–	–	–
	SB-W-08-9480	1/28/12	WW	ARI	48-48.5 (dup)	-13.0	S	–	–	–	–	–	–	–	**0.0004 J**	–	–	–	–	–
	SB-W-08-0590	1/28/12	WW	ARI	59-59.5	-24.0	S	–	–	–	–	–	–	–	0.13 U	–	–	–	–	–
	SB-W-08-0710	1/29/12	WW	ARI	71-71.5	-36.0	S	–	–	–	–	–	–	–	0.20 U	–	–	–	–	–
	SB-W-08-0760	1/29/12	WW	ARI	76-76.5	-41.0	S	–	–	–	–	–	–	–	0.0009 U	–	–	–	–	–
All Data							Number of Analytes Measured	805	805	805	805	805	805	805	856	805	805	805	805	805
							Number of Analytes Detected	154	0	9	1	27	209	0	91	0	0	0	0	349
							Frequency of Detection	19.1%	0.0%	1.1%	0.1%	3.4%	26.0%	0.0%	10.6%	0.0%	0.0%	0.0%	0.0%	43.4%
							Maximum Detection	0.225	–	0.0928	0.00193 J	0.681	11.3 J	–	0.304	–	–	–	–	0.024
							Minimum Detection	0.00468 U	0.000301 U	0.00137 U	0.00024 U	0.000204 U	0.0104 U	0.00179 U	0.000281 U	0.000284 U	0.00039 U	0.000424 U	0.00134 U	0.000233 U
							Number Of Vadose (V) Detections above SL	0	0	0	–	–	0	0	0	0	–	0	0	0
							Number of Saturated (S) Detections above SL	0	0	3	–	–	1	0	18	0	–	0	0	0
2017-2021							Number of Analytes Measured	805	805	805	805	805	805	805	819	805	805	805	805	805
							Number of Analytes Detected	154	0	9	1	27	209	0	87	0	0	0	0	349
							Frequency of Detection	19.1%	0.0%	1.1%	0.1%	3.4%	26.0%	0.0%	10.6%	0.0%	0.0%	0.0%	0.0%	43.4%
							Maximum Detection	0.225	–	0.0928	0.00193 J	0.681	11.3 J	–	0.304	–	–	–	–	0.024
							Minimum Detection	0.00468 U	0.000301 U	0.00137 U	0.00024 U	0.000204 U	0.0104 U	0.00179 U	0.000281 U	0.000284 U	0.00039 U	0.000424 U	0.00134 U	0.000233 U
							Number Of Vadose (V) Detections above SL	0	0	0	–	–	0	0	0	0	–	0	0	0
							Number of Saturated (S) Detections above SL	0	0	3	–	–	1	0	17	0	–	0	0	0

Abbreviations:
AAL = Alden Analytical Laboratories, Inc., of Seattle, Washington
ARI = Analytical Resource, Incorporated, Seattle, Washington
B&V = Black Veatch
bgs = below ground surface
Comp = Composite Sample
dup = duplicate
EPJ = E.PJohnson Construction Inc., and Environmental
ESC = ESC Lab Services of Mt. Juliet, Tennessee
F&BI = Friedman & Bruya, Inc.
GeoEng = GeoEngineers, Inc.
HC = Hart Crowser, Inc.
NCA = North Creek Analytical, of Bothell, Washington
OnSite = OnSite Environmental Inc., of Redmond, Washington
Pace = Pace Analytical of Mt. Juliet, Tennessee (formerly ESC)
PES = PES Environmental, Inc.
Retec = Remediation Technologies, Inc.
Roux = Roux Associates
SES = SoundEarth Strategies, Inc.
TR = TR Corporation
Urban = Urban Redevelopment LLC
WW = WW Environmental LLC

Notes:
All on-Property soil was excavated during Property redevelopment above elevations 0.7 to 10.7 feet, and CVOCs in soil between elevations +10 to 55 feet was treated.
Petroleum Hydrocarbons (PHCs) analyzed by Ecology Methods NWTPH-HCID, NWTPH-Gx, or NWTPH-Dx; or EPA Method 418.1, Method 8020, or Method 8015M.
VOCs analyzed by EPA Methods 8010, 8020, 8021B, 624/8240, or 8260B/C/D.
Well screen elevations provided below Sample Location. in parentheses when appliable.
PCUL = Preliminary Cleanup Level from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021. PCULs based on the practical quantitation limits (PQLs) italicized.
Detected results shown in **bold**.
Detections above the screening level in the vadose zone are shown in **bold and highlighted blue**.
Detections above the screening level in the saturated zone are shown in **bold and highlighted gray.**
– = Not available or results not analyzed.
A = Result reported as total petroleum hydrocarbons.
B = Analyte detected in an associated method blank.
J = The reported concentration is an estimate based on detectable results between the method detection limit and reporting limit, laboratory QA/QC, or data validation review.
J+ = The result is an estimated quantity, but the result may be biased high.
J- = The result is an estimated quantity, but the result may be biased low.
ND = Not detected above laboratory reporting limit. Reporting limit not available.
q = Sample may contain gasoline or petroleum components. Chromatographic pattern indicates the presence of gasoline constituents.
R = The data is unusable. The sample result is rejected due to serious deficiencies in meeting QC criteria. The analyte may or may not be present in the sample
T = Analyte also detected in trip blank.
U = Not detected at a concentration exceeding laboratory reporting limit
ve = Estimated value. The reported range exceeds the calibration range of the analysis.
w = Petroleum product eluting in the C8-C9 range
x = The sample chromatographic pattern does not resemble the fuel standard used for quantitation.
z = Gasoline/petroleum detection result is likely elevated due to high detections of CVOCs.

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	**–**	**0.074**	**–**	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	**–**	**0.007**	**–**	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
B-1	B-1-13	6/23/00	TR	ARI	13	27.0	S	–	–	–	–	–	–	**0.0021**	–	–	–	–	0.0012 U
B-2	B-2-6.5	6/23/00	TR	ARI	6.5	33.5	S	–	–	–	–	–	–	**0.011**	–	–	–	–	0.0011 U
	B-2-11	6/23/00	TR	ARI	11	29.0	S	–	–	–	–	–	–	**0.64**	–	–	–	–	0.0012 U
	B-2-16	6/23/00	TR	ARI	16	24.0	S	–	–	–	–	–	–	**0.0075**	–	–	–	–	0.0011 U
B-3	B-3-12	6/23/00	TR	ARI	12	28.0	S	–	–	–	–	–	–	**0.0016**	–	–	–	–	0.0013 U
B-5	B-5-10	6/23/00	TR	ARI	10	30.0	S	–	–	–	–	–	–	**0.0021**	–	–	–	–	0.0011 U
	B-5-11.5	6/23/00	TR	ARI	11.5	28.5	S	–	–	–	–	–	–	**0.013**	–	–	–	–	0.0012 U
B-6	B-6-6	6/24/00	TR	ARI	6	34.0	S	–	–	–	–	–	–	**0.0021**	–	–	–	–	–
	B-6-12	6/24/00	TR	ARI	12	28.0	S	–	–	–	–	–	–	**0.0047**	–	–	–	–	–
	B-6-18	6/24/00	TR	ARI	18	22.0	S	–	–	–	–	–	–	**0.0031**	–	–	–	–	–
B-7	B-7-6	6/24/00	TR	ARI	6	34.0	S	–	–	–	–	–	–	**0.0052**	–	–	–	–	–
B-8	B-8-4	6/24/00	TR	ARI	4	36.0	S	–	–	–	–	–	–	**0.0019**	–	–	–	–	–
	B-8-8	6/24/00	TR	ARI	8	32.0	S	–	–	–	–	–	–	**0.021**	–	–	–	–	–
B-9	B-9-4	6/24/00	TR	ARI	4	36.0	S	–	–	–	–	–	–	1.6 U	–	–	–	–	–
	B-9-8	6/24/00	TR	ARI	8	32.0	S	–	–	–	–	–	–	**0.21**	–	–	–	–	–
B-10	B-10-12	6/24/00	TR	ARI	12	28.0	S	–	–	–	–	–	–	**0.0061**	–	–	–	–	–
B-201	G-201-10	6/19/17	PES	ESC	10	29.8	S	–	–	–	–	–	–	**0.00298**	–	–	–	–	0.00120 U
	G-201-30	6/19/17	PES	ESC	30	9.8	S	–	–	–	–	–	–	**0.0784**	–	–	–	–	0.00113 U
	G-201-35	6/19/17	PES	ESC	35	4.8	S	–	–	–	–	–	–	**0.0149**	–	–	–	–	0.00116 U
B-202	G-202-5	6/19/17	PES	ESC	5	34.2	S	–	–	–	–	–	–	0.00119 U	–	–	–	–	0.00119 U
	G-202-20	6/19/17	PES	ESC	20	19.2	S	–	–	–	–	–	–	0.00119 U	–	–	–	–	0.00119 U
	G-202-50	6/19/17	PES	ESC	50	-10.8	S	–	–	–	–	–	–	0.00132 U	–	–	–	–	0.00132 U
B-203	G-203-5	6/20/17	PES	ESC	5	34.2	S	–	–	–	–	–	–	0.00115 U	–	–	–	–	**0.0745**
	G-203-25	6/20/17	PES	ESC	25	14.2	S	–	–	–	–	–	–	0.00117 U	–	–	–	–	0.00117 U
	G-203-40	6/20/17	PES	ESC	40	-0.8	S	–	–	–	–	–	–	**0.168**	–	–	–	–	**0.00299**
	G-203-50	6/20/17	PES	ESC	50	-10.8	S	–	–	–	–	–	–	**0.136**	–	–	–	–	0.00112 U
	G-203-80	6/20/17	PES	ESC	80	-40.8	S	–	–	–	–	–	–	0.00110 U	–	–	–	–	0.00110 U
B-204	G-204-20	6/20/17	PES	ESC	20	19.8	S	–	–	–	–	–	–	0.00116 U	–	–	–	–	0.00116 U
	G-204-40	6/20/17	PES	ESC	40	-0.2	S	–	–	–	–	–	–	**2.60**	–	–	–	–	0.00113 U
	G-204-45	6/20/17	PES	ESC	45	-5.2	S	–	–	–	–	–	–	**16.7**	–	–	–	–	0.00121 U
B-205	B-205-10	8/30/17	PES	ESC	10	30.3	S	0.0396 U	0.0256 U	0.0450 U	0.114 U	0.0276 U	0.0452 U	0.0283 U	0.0316 U	0.0461 U	0.0306 U	0.0860 U	**4.74**
	B-205-55	8/30/17	PES	ESC	55	-14.7	S	0.000383 U	0.000248 U	0.000436 U	0.00111 U	0.000268 U	0.000438 U	**0.0155**	0.000306 U	0.000446 U	0.000297 U	0.000833 U	0.000347 U
	B-205-65	8/30/17	PES	ESC	65	-24.7	S	0.000347 U	0.000224 U	0.000395 U	0.00100 U	0.000242 U	0.000397 U	**0.00390**	0.000277 U	0.000405 U	0.000269 U	0.000755 U	0.000314 U
	B-205-75	8/30/17	PES	ESC	75	-34.7	S	0.000351 U	0.000227 U	0.000399 U	0.00101 U	0.000245 U	0.000402 U	**0.000585 J**	0.000281 U	0.000409 U	0.000272 U	0.000764 U	0.000318 U
	B-904-50	8/30/17	PES	ESC	75 (dup)	-34.7	S	0.000352 U	0.000227 U	0.000400 U	0.00101 U	0.000246 U	0.000402 U	**0.00170**	0.000281 U	0.000410 U	0.000272 U	0.000765 U	0.000319 U
B-206	B-206-15	8/14/17	PES	ESC	15	24.1	S	0.00944 U	0.00610 U	0.0107 U	0.0272 U	0.00658 U	0.0108 U	**0.306**	0.00754 U	0.0110 U	0.00731 U	0.0205 U	0.00854 U
	B-206-30	8/14/17	PES	ESC	30	9.1	S	0.000376 U	0.000243 U	0.000428 U	0.00109 U	0.000263 U	0.000430 U	**12.6**	0.000301 U	0.000438 U	0.000291 U	0.000818 U	0.000341 U
	B-206-40	8/14/17	PES	ESC	40	-0.9	S	0.000347 U	0.000224 U	0.000394 U	0.00100 U	0.000242 U	0.000396 U	**0.00879 J**	0.000277 U	0.000404 U	0.000268 U	0.000754 U	0.000314 U
	B-206-49	8/14/17	PES	ESC	49	-9.9	S	0.000374 U	0.000242 U	0.000425 U	0.00108 U	0.000261 U	0.000427 U	**6.41**	0.000298 U	0.000435 U	0.000289 U	0.000812 U	0.000338 U
	B-206-52	8/14/17	PES	ESC	52	-12.9	S	0.000358 U	0.000231 U	0.000407 U	0.00103 U	0.000250 U	0.000409 U	0.00642 U	0.000286 U	0.000417 U	0.000277 U	0.000779 U	0.000324 U
	B-206-56	8/14/17	PES	ESC	56	-16.9	S	0.000360 U	0.000233 U	0.000410 U	0.00104 U	0.000252 U	0.000412 U	**0.140**	0.000288 U	0.000420 U	0.000279 U	0.000783 U	0.000326 U
	B-206-59	8/14/17	PES	ESC	59	-19.9	S	0.000341 U	0.000221 U	0.000388 U	0.000984 U	0.000238 U	0.000390 U	**0.00686**	0.000273 U	0.000397 U	0.000264 U	0.000742 U	0.000309 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
B-206	B-206-70	8/14/17	PES	ESC	70	-30.9	S	0.000357 U	0.000231 U	0.000406 U	0.00103 U	0.000249 U	0.000409 U	**0.00201**	0.000285 U	0.000416 U	0.000277 U	0.000777 U	0.000324 U
(continued)	B-206-80	8/14/17	PES	ESC	80	-40.9	S	0.000358 U	0.000231 U	0.000407 U	0.00103 U	0.000250 U	0.000409 U	**0.000647 J**	0.000286 U	0.000416 U	0.000277 U	0.000777 U	0.000324 U
B-207	B-207-30	8/25/17	PES	ESC	30	8.5	S	0.00932 U	0.00602 U	0.0106 U	0.0268 U	0.00650 U	0.0107 U	**0.0557**	0.00744 U	0.0109 U	0.00722 U	0.0202 U	0.00843 U
	B-207-41	8/25/17	PES	ESC	41	-2.5	S	0.000371 U	0.000240 U	0.000422 U	0.00107 U	0.000259 U	0.000425 U	**6.93**	0.000297 U	0.000433 U	0.000288 U	0.000807 U	0.000336 U
	B-207-49	8/25/17	PES	ESC	49	-10.5	S	0.000366 U	0.000236 U	0.000416 U	0.00106 U	0.000255 U	0.000418 U	**2.47**	0.000292 U	0.000426 U	0.000283 U	0.000795 U	0.000331 U
	B-207-55	8/25/17	PES	ESC	55	-16.5	S	0.000383 U	0.000248 U	0.000436 U	0.00110 U	0.000267 U	0.000438 U	**0.581**	0.000306 U	0.000446 U	0.000297 U	0.000832 U	0.000347 U
	B-207-60	8/25/17	PES	ESC	60	-21.5	S	0.000349 U	0.000226 U	0.000397 U	0.00101 U	0.000244 U	0.000399 U	0.00626 U	0.000279 U	0.000407 U	0.000270 U	0.000759 U	0.000316 U
	B-207-70	8/25/17	PES	ESC	70	-31.5	S	0.000375 U	0.000242 U	0.000426 U	0.00108 U	0.000262 U	0.000428 U	0.00671 U	0.000299 U	0.000436 U	0.000290 U	0.000814 U	0.000339 U
	B-207-80	8/25/17	PES	ESC	80	-41.5	S	0.000361 U	0.000234 U	0.000411 U	0.00104 U	0.000252 U	0.000413 U	**0.990**	0.000289 U	0.000421 U	0.000280 U	0.000785 U	0.000327 U
	B-207-90	8/25/17	PES	ESC	90	-51.5	S	0.00901 U	0.00582 U	0.0102 U	0.0259 U	0.00628 U	0.0103 U	**0.311**	0.00720 U	0.0105 U	0.00698 U	0.0196 U	0.00815 U
B-208	B-208-20	8/24/17	PES	ESC	20	18.8	S	0.000388 U	0.000251 U	0.000441 U	0.00112 U	0.000271 U	0.000443 U	**0.0257**	0.000310 U	0.000451 U	0.000300 U	0.000843 U	0.000351 U
	B-208-35	8/24/17	PES	ESC	35	3.8	S	0.000357 U	0.000231 U	0.000406 U	0.00103 U	0.000249 U	0.000408 U	**0.160**	0.000285 U	0.000416 U	0.000276 U	0.000776 U	0.000323 U
	B-901-50	8/24/17	PES	ESC	35 (dup)	3.8	S	0.000371 U	0.000240 U	0.000422 U	0.00107 U	0.000259 U	0.000424 U	**0.152**	0.000296 U	0.000432 U	0.000287 U	0.000806 U	0.000336 U
	B-208-50	8/24/17	PES	ESC	50	-11.2	S	0.000362 U	0.000234 U	0.000412 U	0.00104 U	0.000253 U	0.000414 U	**0.0739**	0.000289 U	0.000422 U	0.000280 U	0.000787 U	0.000328 U
	B-208-60	8/24/17	PES	ESC	60	-21.2	S	0.000365 U	0.000236 U	0.000415 U	0.00105 U	0.000255 U	0.000418 U	**0.000685 J**	0.000292 U	0.000425 U	0.000283 U	0.000794 U	0.000331 U
	B-208-70	8/24/17	PES	ESC	70	-31.2	S	0.000366 U	0.000237 U	0.000417 U	0.00106 U	0.000256 U	0.000419 U	**0.000316 J**	0.000293 U	0.000427 U	0.000284 U	0.000796 U	0.000332 U
	B-208-80	8/24/17	PES	ESC	80	-41.2	S	0.000406 U	0.000262 U	0.000461 U	0.00117 U	0.000283 U	0.000464 U	0.000291 U	0.000324 U	0.000473 U	0.000314 U	0.000882 U	0.000367 U
B-209	B-209-20	8/25/17	PES	ESC	20	19.0	S	0.000381 U	0.000246 U	0.000433 U	0.00110 U	0.000266 U	0.000436 U	**0.0174**	0.000304 U	0.000444 U	0.000295 U	0.000829 U	0.000345 U
	B-209-35	8/25/17	PES	ESC	35	4.0	S	0.000350 U	0.000226 U	0.000398 U	0.00101 U	0.000245 U	0.000401 U	**0.0508**	0.000280 U	0.000408 U	0.000271 U	0.000762 U	0.000317 U
	B-209-50	8/25/17	PES	ESC	50	-11.0	S	0.000428 U	0.000277 U	0.000487 U	0.00123 U	0.000299 U	0.000489 U	0.000307 U	0.000342 U	0.000498 U	0.000331 U	0.000930 U	0.000387 U
	B-209-60	8/25/17	PES	ESC	60	-21.0	S	0.000376 U	0.000243 U	0.000428 U	0.00109 U	0.000263 U	0.000430 U	0.000270 U	0.000301 U	0.000438 U	0.000292 U	0.000818 U	0.000341 U
	B-209-70	8/25/17	PES	ESC	70	-31.0	S	0.000350 U	0.000226 U	0.000397 U	0.00101 U	0.000244 U	0.000400 U	0.000323 U	0.000279 U	0.000407 U	0.000271 U	0.000760 U	0.000316 U
	B-209-75	8/25/17	PES	ESC	75	-36.0	S	0.000348 U	0.000225 U	0.000396 U	0.00100 U	0.000243 U	0.000398 U	0.000249 U	0.000278 U	0.000405 U	0.000269 U	0.000756 U	0.000315 U
	B-209-80	8/25/17	PES	ESC	80	-41.0	S	0.000377 U	0.000244 U	0.000429 U	0.00109 U	0.000263 U	0.000431 U	**0.00106 J**	0.000301 U	0.000439 U	0.000292 U	0.000819 U	0.000341 U
B-210	B-210-6	8/21/17	PES	ESC	6	33.4	S	0.000387 U	0.000250 U	0.000440 U	0.00112 U	0.000270 U	0.000442 U	**0.000287 J**	0.000309 U	0.000450 U	0.000299 U	0.000841 U	0.000350 U
	B-210-15	8/21/17	PES	ESC	15	24.4	S	0.00889 U	0.00574 U	0.0101 U	0.0256 U	0.00620 U	0.0102 U	0.00637 U	0.00710 U	0.0103 U	0.00688 U	0.0193 U	0.00804 U
	B-210-20	8/21/17	PES	ESC	20	19.4	S	0.000365 U	0.000236 U	0.000416 U	0.00105 U	0.000255 U	0.000418 U	**0.00185**	0.000292 U	0.000426 U	0.000283 U	0.000794 U	0.000331 U
	B-210-35	8/21/17	PES	ESC	35	4.4	S	0.000379 U	0.000245 U	0.000430 U	0.00109 U	0.000264 U	0.000433 U	**0.00950**	0.000302 U	0.000441 U	0.000293 U	0.000823 U	0.000343 U
	B-210-46	8/21/17	PES	ESC	46	-6.6	S	0.000357 U	0.000231 U	0.000406 U	0.00103 U	0.000250 U	0.000409 U	**3.27**	0.000285 U	0.000416 U	0.000277 U	0.000777 U	0.000324 U
	B-210-60	8/22/17	PES	ESC	60	-20.6	S	0.00880 U	0.00569 U	0.0100 U	0.0253 U	0.00614 U	0.0101 U	0.00631 U	0.00703 U	0.0102 U	0.00682 U	0.0191 U	0.00796 U
	B-210-70	8/22/17	PES	ESC	70	-30.6	S	0.000354 U	0.000229 U	0.000402 U	0.00102 U	0.000247 U	0.000405 U	**0.0115**	0.000283 U	0.000412 U	0.000274 U	0.000769 U	0.000320 U
	B-210-80	8/22/17	PES	ESC	80	-40.6	S	0.000362 U	0.000234 U	0.000412 U	0.00104 U	0.000253 U	0.000414 U	**0.000500 J**	0.000289 U	0.000422 U	0.000281 U	0.000787 U	0.000328 U
	B-900-20	8/22/17	PES	ESC	80 (dup)	-40.6	S	0.000390 U	0.000252 U	0.000443 U	0.00112 U	0.000272 U	0.000445 U	**0.000837 J**	0.000311 U	0.000454 U	0.000302 U	0.000847 U	0.000353 U
B-211	B-211-20	8/17/17	PES	ESC	20	19.8	S	0.000366 U	0.000237 U	0.000416 U	0.00106 U	0.000256 U	0.000419 U	**0.0282**	0.000293 U	0.000427 U	0.000284 U	0.000796 U	0.000332 U
	B-211-35	8/17/17	PES	ESC	35	4.8	S	0.000369 U	0.000239 U	0.000420 U	0.00106 U	0.000258 U	0.000422 U	**0.00104 J**	0.000295 U	0.000430 U	0.000286 U	0.000803 U	0.000334 U
	B-211-50	8/17/17	PES	ESC	50	-10.3	S	0.000355 U	0.000229 U	0.000403 U	0.00102 U	0.000248 U	0.000405 U	**0.0189**	0.000283 U	0.000413 U	0.000275 U	0.000771 U	0.000321 U
	B-211-57	8/17/17	PES	ESC	57	-17.3	S	0.000387 U	0.000250 U	0.000440 U	0.00112 U	0.000270 U	0.000442 U	**0.0830**	0.000309 U	0.000451 U	0.000300 U	0.000841 U	0.000350 U
	B-211-60	8/17/17	PES	ESC	60	-20.3	S	0.000378 U	0.000244 U	0.000430 U	0.00109 U	0.000264 U	0.000432 U	**4.99**	0.000302 U	0.000440 U	0.000293 U	0.000822 U	0.000342 U
	B-211-65	8/18/17	PES	ESC	65	-25.3	S	0.000370 U	0.000239 U	0.000421 U	0.00107 U	0.000258 U	0.000423 U	**5.58**	0.000296 U	0.000431 U	0.000287 U	0.000805 U	0.000335 U
	B-211-70	8/18/17	PES	ESC	70	-30.3	S	0.196 U	0.127 U	0.223 U	0.566 U	0.136 U	0.225 U	**3.96**	0.157 U	0.229 U	0.152 U	0.426 U	0.177 U
	B-211-80	8/18/17	PES	ESC	80	-40.3	S	0.00888 U	0.00574 U	0.0101 U	0.0256 U	0.00619 U	0.0102 U	**0.172**	0.00709 U	0.0103 U	0.00688 U	0.0193 U	0.00804 U
	B-211-90	8/18/17	PES	ESC	90	-50.3	S	0.00956 U	0.00618 U	0.0109 U	0.0275 U	0.00667 U	0.0109 U	**0.0362**	0.00764 U	0.0111 U	0.00740 U	0.0207 U	0.00865 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
B-211 (continued)	B-211-100	8/18/17	PES	ESC	100	-60.3	S	0.000381 U	0.000246 U	0.000433 U	0.00110 U	0.000266 U	0.000435 U	0.000273 U	0.000304 U	0.000443 U	0.000295 U	0.000828 U	0.000345 U
	B-211-110	8/18/17	PES	ESC	110	-70.3	S	0.000362 U	0.000234 U	0.000411 U	0.00104 U	0.000253 U	0.000414 U	0.000259 U	0.000289 U	0.000421 U	0.000280 U	0.000786 U	0.000328 U
	B-211-120	8/21/17	PES	ESC	120	-80.3	S	0.000368 U	0.000238 U	0.000418 U	0.00106 U	0.000257 U	0.000421 U	0.000264 U	0.000294 U	0.000429 U	0.000285 U	0.000800 U	0.000333 U
B-216	B-216-20	9/1/17	PES	ESC	20	31.9	S	0.000353 U	0.000228 U	0.000402 U	0.00102 U	0.000247 U	0.000404 U	0.000253 U	0.000282 U	0.000411 U	0.000274 U	0.000768 U	0.000320 U
	B-216-40	9/1/17	PES	ESC	40	11.9	S	0.000356 U	0.000230 U	0.000405 U	0.00103 U	0.000248 U	0.000407 U	0.000255 U	0.000284 U	0.000414 U	0.000276 U	0.000773 U	0.000322 U
	B-216-50	9/1/17	PES	ESC	50	1.9	S	0.000355 U	0.000229 U	0.000403 U	0.00102 U	0.000248 U	0.000405 U	0.000254 U	0.000283 U	0.000413 U	0.000275 U	0.000771 U	0.000321 U
	B-216-55	9/1/17	PES	ESC	55	-3.1	S	0.000369 U	0.000239 U	0.000420 U	0.00107 U	0.000258 U	0.000422 U	**0.182**	0.000295 U	0.000430 U	0.000286 U	0.000803 U	**0.00876**
	B-216-65	9/1/17	PES	ESC	65	-13.1	S	0.000394 U	0.000254 U	0.000448 U	0.00114 U	0.000275 U	0.000450 U	0.000282 U	0.000315 U	0.000459 U	0.000305 U	0.000856 U	0.000357 U
	B-216-85	9/1/17	PES	ESC	85	-33.1	S	0.000396 U	0.000256 U	0.000450 U	0.00114 U	0.000276 U	0.000452 U	**0.000289 J**	0.000316 U	0.000461 U	0.000306 U	0.000860 U	0.000358 U
	B-216-95	9/1/17	PES	ESC	95	-43.1	S	0.000373 U	0.000241 U	0.000424 U	0.00107 U	0.000260 U	0.000426 U	0.000267 U	0.000298 U	0.000434 U	0.000289 U	0.000810 U	0.000337 U
B-217	B-217-15	9/5/17	PES	ESC	15	36.8	V	0.000372 U	0.000241 U	0.000423 U	0.00107 U	0.000260 U	0.000426 U	0.000267 U	0.000297 U	0.000434 U	0.000288 U	0.000809 U	0.000337 U
	B-217-25	9/5/17	PES	ESC	25	26.8	S	0.000364 U	0.000235 U	0.000414 U	0.00105 U	0.000254 U	0.000416 U	**0.00105 J**	0.000290 U	0.000424 U	0.000282 U	0.000791 U	0.000329 U
	B-217-35	9/5/17	PES	ESC	35	16.8	S	0.000376 U	0.000243 U	0.000428 U	0.00109 U	0.000263 U	0.000430 U	0.000270 U	0.000301 U	0.000438 U	0.000292 U	0.000818 U	0.000341 U
	B-217-42	9/5/17	PES	ESC	42	9.8	S	0.000375 U	0.000242 U	0.000427 U	0.00108 U	0.000262 U	0.000429 U	**5.73**	0.000300 U	0.000437 U	0.000290 U	0.000815 U	0.000340 U
	B-217-55	9/5/17	PES	ESC	55	-3.2	S	0.000381 U	0.000246 U	0.000433 U	0.00110 U	0.000266 U	0.000435 U	**0.0787**	0.000304 U	0.000443 U	0.000295 U	0.000828 U	0.000345 U
	B-217-65	9/5/17	PES	ESC	65	-13.2	S	0.000378 U	0.000244 U	0.000430 U	0.00109 U	0.000264 U	0.000432 U	**3.14**	0.000302 U	0.000440 U	0.000292 U	0.000821 U	0.000342 U
	B-217-75	9/5/17	PES	ESC	75	-23.2	S	0.000393 U	0.000254 U	0.000447 U	0.00113 U	0.000274 U	0.000449 U	0.000281 U	0.000314 U	0.000458 U	0.000304 U	0.000854 U	0.000356 U
	B-217-85	9/6/17	PES	ESC	85	-33.2	S	0.000374 U	0.000242 U	0.000425 U	0.00108 U	0.000261 U	0.000427 U	0.000268 U	0.000298 U	0.000435 U	0.000289 U	0.000812 U	0.000338 U
	B-217-95	9/6/17	PES	ESC	95	-43.2	S	0.000396 U	0.000256 U	0.000451 U	0.00114 U	0.000277 U	0.000453 U	0.000284 U	0.000317 U	0.000462 U	0.000307 U	0.000862 U	0.000359 U
	B-217-106	9/6/17	PES	ESC	106	-54.2	S	0.0402 U	0.0260 U	0.0457 U	0.116 U	0.0281 U	0.0460 U	0.0288 U	0.0321 U	0.0468 U	0.0311 U	0.0874 U	0.0364 U
	B-217-115	9/6/17	PES	ESC	115	-63.2	S	0.000379 U	0.000245 U	0.000431 U	0.00109 U	0.000264 U	0.000433 U	0.000271 U	0.000303 U	0.000441 U	0.000293 U	0.000823 U	0.000343 U
B-218	B-218-12.5	9/19/17	PES	ESC	12.5	25.6	S	0.000373 U	0.000241 U	0.000425 U	0.00108 U	0.000261 U	0.000427 U	**2.16**	0.000298 U	0.000435 U	0.000289 U	0.000812 U	0.000338 U
	B-218-19	9/19/17	PES	ESC	19	19.1	S	0.000372 U	0.000241 U	0.000423 U	**0.00550 J**	0.000260 U	0.000426 U	**0.123**	0.000297 U	0.000434 U	0.000288 U	0.000809 U	0.000337 U
	B-218-25	9/19/17	PES	ESC	25	13.1	S	0.000380 U	0.000245 U	0.000432 U	**0.00115 J**	0.000265 U	0.000434 U	**0.0781**	0.000303 U	0.000442 U	0.000294 U	0.000826 U	0.000344 U
	B-218-40	9/19/17	PES	ESC	40	-1.9	S	0.0202 U	0.0131 U	0.0229 U	0.0582 U	0.0141 U	0.0231 U	**5.25**	0.0161 U	0.0235 U	0.0156 U	0.0438 U	0.0182 U
	B-218-50	9/19/17	PES	ESC	50	-11.9	S	0.000350 U	0.000226 U	0.000398 U	0.00101 U	0.000244 U	0.000400 U	**3.19 J**	0.000279 U	0.000407 U	0.000271 U	0.000760 U	0.000317 U
	B-913-70	9/19/17	PES	ESC	50 (dup)	-11.9	S	0.000348 U	0.000225 U	0.000396 U	0.00100 U	0.000243 U	0.000398 U	**5.52 J**	0.000278 U	0.000406 U	0.000270 U	0.000757 U	0.000315 U
B-219	B-219-42	8/28/17	PES	ESC	42	-2.2	S	0.000357 U	0.000231 U	0.000406 U	0.00103 U	0.000249 U	0.000408 U	**0.0179**	0.000285 U	0.000416 U	0.000277 U	0.000777 U	0.000323 U
	B-219-50	8/28/17	PES	ESC	50	-10.2	S	0.000388 U	0.000251 U	0.000442 U	0.00112 U	0.000271 U	0.000444 U	**0.139**	0.000310 U	0.000452 U	0.000301 U	0.000844 U	0.000352 U
	B-219-60	8/28/17	PES	ESC	60	-20.2	S	0.000353 U	0.000228 U	0.000401 U	0.00102 U	0.000246 U	0.000404 U	**0.00202**	0.000282 U	0.000411 U	0.000273 U	0.000767 U	0.000320 U
	B-219-70	8/28/17	PES	ESC	70	-30.2	S	0.000374 U	0.000242 U	0.000426 U	0.00108 U	0.000261 U	0.000428 U	**0.00307**	0.000299 U	0.000436 U	0.000290 U	0.000814 U	0.000339 U
	B-219-80	8/28/17	PES	ESC	80	-40.2	S	0.00891 U	0.000230 U	0.000405 U	0.00103 U	0.000249 U	0.0102 U	0.00639 U	0.000285 U	0.000415 U	0.000276 U	0.000774 U	0.000323 U
B-220	B-220-15	9/20/17	PES	ESC	15	23.9	S	0.000373 U	0.000241 U	0.000424 U	0.00108 U	0.000260 U	0.000426 U	**0.576**	0.000298 U	0.000434 U	0.000289 U	0.000811 U	0.000338 U
	B-220-29	9/20/17	PES	ESC	29	9.9	S	0.000381 U	0.000246 U	0.000434 U	0.00110 U	**0.000671 J**	0.000436 U	**2.13**	0.000305 U	0.000444 U	0.000295 U	0.000829 U	0.000345 U
	B-220-32	9/20/17	PES	ESC	32	6.9	S	0.000374 U	0.000242 U	0.000426 U	**0.00202 J**	0.000261 U	0.000428 U	**1.55**	0.000299 U	0.000436 U	0.000290 U	0.000813 U	0.000339 U
	B-220-40	9/20/17	PES	ESC	40	-1.1	S	0.000364 U	0.000235 U	0.000414 U	0.00105 U	0.000254 U	0.000416 U	**2.73**	0.000291 U	0.000424 U	0.000282 U	0.000792 U	0.000330 U
	B-220-50	9/20/17	PES	ESC	50	-11.1	S	0.000353 U	0.000228 U	0.000401 U	0.00102 U	0.000246 U	0.000403 U	**0.0766**	0.000282 U	0.000411 U	0.000273 U	0.000767 U	0.000319 U
	B-914-75	9/20/17	PES	ESC	50 (dup)	-11.1	S	0.000353 U	0.000228 U	0.000401 U	0.00102 U	0.000246 U	0.000403 U	**0.0913**	0.000282 U	0.000411 U	0.000273 U	0.000767 U	0.000319 U
B-221	B-221-16	9/20/17	PES	ESC	16	23.0	S	0.00961 U	0.00621 U	0.0109 U	0.0277 U	0.00670 U	0.0110 U	**1.37**	0.00768 U	0.0112 U	0.00744 U	0.0209 U	0.00869 U
	B-221-22	9/20/17	PES	ESC	22	17.0	S	0.377 U	0.244 U	0.429 U	1.09 U	0.263 U	0.431 U	**2.56**	0.301 U	0.439 U	0.292 U	0.820 U	0.342 U
	B-221-33	9/20/17	PES	ESC	33	6.0	S	0.367 U	0.237 U	0.418 U	1.06 U	0.256 U	0.420 U	**1.93**	0.293 U	0.428 U	0.284 U	0.798 U	0.332 U
	B-221-37	9/20/17	PES	ESC	37	2.0	S	0.0771 U	0.0499 U	0.0877 U	0.222 U	0.0539 U	0.0882 U	**0.438**	0.0616 U	0.0898 U	0.0597 U	0.168 U	0.0698 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
B-221 (continued)	B-915-80	9/20/17	PES	ESC	37 (dup)	2.0	S	0.0376 U	0.0243 U	0.0428 U	0.108 U	0.0262 U	0.0430 U	**0.342**	0.0300 U	0.0438 U	0.0291 U	0.0817 U	0.0340 U
	B-221-45	9/20/17	PES	ESC	45	-6.0	S	3.60 U	2.33 U	4.09 U	10.4 U	2.51 U	4.11 U	2.58 U	2.87 U	4.19 U	2.79 U	7.82 U	3.26 U
	B-221-50	9/20/17	PES	ESC	50	-11.0	S	0.178 U	0.115 U	0.202 U	0.514 U	0.124 U	0.204 U	**0.561**	0.142 U	0.208 U	0.138 U	0.387 U	0.161 U
	B-221-60	9/20/17	PES	ESC	60	-21.0	S	0.181 U	0.117 U	0.206 U	0.523 U	0.126 U	0.208 U	**1.41**	0.145 U	0.211 U	0.140 U	0.393 U	0.164 U
	B-221-70	9/21/17	PES	ESC	70	-31.0	S	0.000362 U	0.000234 U	0.000412 U	0.00104 U	0.000253 U	0.000414 U	**0.00582**	0.000289 U	0.000422 U	0.000280 U	0.000787 U	0.000328 U
B-222	B-222-17	9/21/17	PES	ESC	17	22.2	S	0.000372 U	0.000240 U	0.000423 U	0.00107 U	0.000260 U	0.000425 U	0.000266 U	0.000297 U	0.000433 U	0.000288 U	0.000808 U	0.000337 U
	B-222-25	9/21/17	PES	ESC	25	14.2	S	0.000379 U	0.000245 U	0.000431 U	0.00109 U	0.000265 U	0.000433 U	**0.109**	0.000303 U	0.000442 U	0.000294 U	0.000824 U	0.000343 U
	B-222-34	9/21/17	PES	ESC	34	5.2	S	0.000368 U	0.000238 U	0.000418 U	**0.00230 J**	0.000257 U	0.000420 U	**0.0255**	0.000294 U	0.000428 U	0.000285 U	0.000799 U	0.000333 U
	B-222-42	9/21/17	PES	ESC	42	-2.8	S	0.000407 U	0.000263 U	0.000463 U	0.00117 U	0.000284 U	0.000465 U	**7.34**	0.000325 U	0.000474 U	0.000315 U	0.000884 U	0.000368 U
	B-222-50	9/21/17	PES	ESC	50	-10.8	S	0.0176 U	0.0114 U	0.0199 U	0.0507 U	0.0122 U	0.0202 U	**0.498 J**	0.0140 U	0.0205 U	0.0136 U	0.0382 U	0.0159 U
	B-916-30	9/21/17	PES	ESC	50 (dup)	-10.8	S	0.000348 U	0.000225 U	0.000396 U	0.00100 U	0.000243 U	0.000398 U	**0.160 J**	0.000278 U	0.000405 U	0.000269 U	0.000756 U	0.000315 U
B-223	B-223-16	9/21/17	PES	ESC	16	23.1	S	0.0775 U	0.0501 U	0.0881 U	0.223 U	0.0541 U	0.0886 U	**1.71**	0.0619 U	0.0903 U	0.0600 U	0.169 U	0.0702 U
	B-223-22	9/21/17	PES	ESC	22	17.1	S	0.0749 U	0.0484 U	0.0852 U	0.216 U	0.0523 U	0.0856 U	**0.713**	0.0598 U	0.0872 U	0.0580 U	0.163 U	0.0678 U
	B-223-30	9/21/17	PES	ESC	30	9.1	S	9.03 U	5.84 U	10.3 U	26.0 U	6.30 U	10.3 U	6.47 U	7.21 U	10.5 U	6.99 U	19.6 U	8.17 U
	B-223-39	9/21/17	PES	ESC	39	0.1	S	0.000374 U	0.000241 U	0.000425 U	**0.00151 J**	0.000261 U	0.000427 U	**0.0914**	0.000298 U	0.000435 U	0.000289 U	0.000812 U	0.000338 U
	B-223-47	9/21/17	PES	ESC	47	-7.9	S	0.000381 U	0.000246 U	0.000433 U	0.00110 U	0.000266 U	0.000435 U	**0.00208**	0.000304 U	0.000444 U	0.000295 U	0.000828 U	0.000345 U
	B-917-57	9/21/17	PES	ESC	47 (dup)	-7.9	S	0.000353 U	0.000228 U	0.000401 U	0.00102 U	0.000246 U	0.000403 U	**0.000728 J**	0.000282 U	0.000411 U	0.000273 U	0.000766 U	0.000319 U
B-224	B-224-6	11/27/17	PES	ESC	6	33.1	S	0.000355 U	0.000229 U	0.000403 U	0.00102 U	0.000248 U	0.000406 U	**0.000624 J**	0.000283 U	0.000413 U	0.000275 U	0.000771 U	0.000321 U
	B-224-11	11/27/17	PES	ESC	11	28.1	S	0.000876 U	0.000566 U	0.000996 U	0.00253 U	0.000612 U	0.00100 U	**0.148**	0.000699 U	0.00102 U	0.000678 U	0.00191 U	0.000793 U
	B-224-16	11/27/17	PES	ESC	16	23.1	S	0.000397 U	0.000256 U	0.000451 U	0.00114 U	0.000277 U	0.000453 U	**0.0279**	0.000317 U	0.000462 U	0.000307 U	0.000862 U	0.000359 U
	B-224-21.5	11/27/17	PES	ESC	21.5	17.6	S	0.000381 U	0.000246 U	0.000433 U	0.00110 U	0.000266 U	0.000435 U	**0.117**	0.000304 U	0.000444 U	0.000295 U	0.000828 U	0.000345 U
	B-224-26	11/27/17	PES	ESC	26	13.1	S	0.000433 U	0.000280 U	0.000493 U	0.00125 U	**0.000313 J**	0.000496 U	**0.289**	0.000347 U	0.000504 U	0.000336 U	0.000942 U	0.000392 U
	B-224-31	11/27/17	PES	ESC	31	8.1	S	0.000383 U	0.000248 U	0.000436 U	0.00110 U	0.000267 U	0.000438 U	**0.207**	0.000306 U	0.000446 U	0.000297 U	0.000834 U	0.000348 U
	B-224-36	11/27/17	PES	ESC	36	3.1	S	0.000364 U	0.000235 U	0.000414 U	**0.00108 J**	0.000254 U	0.000416 U	**0.326**	0.000291 U	0.000424 U	0.000282 U	0.000792 U	0.000330 U
	B-224-60.5	11/27/17	PES	ESC	60.5	-21.4	S	0.000531 U	0.000343 U	0.000603 U	0.00152 U	0.000370 U	0.000606 U	**0.0323**	0.000424 U	0.000618 U	0.000411 U	0.00115 U	0.000481 U
B-225	B-225-5	11/27/17	PES	ESC	5	34.1	S	0.000356 U	0.000230 U	0.000405 U	0.00103 U	0.000248 U	0.000407 U	**0.00217**	0.000284 U	0.000414 U	0.000276 U	0.000773 U	0.000322 U
	B-225-11	11/27/17	PES	ESC	11	28.1	S	0.000384 U	0.000248 U	0.000436 U	0.00111 U	0.000268 U	0.000439 U	**0.0222**	0.000306 U	0.000447 U	0.000297 U	0.000834 U	0.000347 U
	B-225-16	11/27/17	PES	ESC	16	23.1	S	0.00965 U	0.00623 U	0.0110 U	0.0278 U	0.00673 U	0.0110 U	**1.62**	0.00771 U	0.0112 U	0.00747 U	0.0209 U	0.00873 U
	B-225-21	11/27/17	PES	ESC	21	18.1	S	0.00932 U	0.00603 U	0.0106 U	0.0268 U	0.00650 U	0.0107 U	**0.0455**	0.00745 U	0.0109 U	0.00722 U	0.0202 U	0.00844 U
	B-225-26	11/27/17	PES	ESC	26	13.1	S	0.000386 U	0.000249 U	0.000438 U	0.00111 U	0.000269 U	0.000441 U	**0.0710**	0.000308 U	0.000449 U	0.000299 U	0.000838 U	0.000349 U
	B-225-31	11/27/17	PES	ESC	31	8.1	S	0.000375 U	0.000242 U	0.000426 U	0.00108 U	0.000262 U	0.000429 U	**0.164**	0.000299 U	0.000437 U	0.000290 U	0.000815 U	0.000339 U
	B-225-36	11/27/17	PES	ESC	36	3.1	S	0.000404 U	0.000261 U	0.000459 U	0.00117 U	0.000282 U	0.000462 U	**0.0115**	0.000323 U	0.000470 U	0.000313 U	0.000878 U	0.000366 U
B-226	B-226-6	11/28/17	PES	ESC	6	33.1	S	0.000395 U	0.000255 U	0.000449 U	0.00114 U	0.000276 U	0.000452 U	**0.00317**	0.000316 U	0.000460 U	0.000306 U	0.000859 U	0.000358 U
	B-226-11	11/28/17	PES	ESC	11	28.1	S	0.000372 U	0.000240 U	0.000423 U	0.00107 U	0.000260 U	0.000425 U	**0.00338**	0.000297 U	0.000433 U	0.000288 U	0.000809 U	0.000337 U
	B-226-16	11/28/17	PES	ESC	16	23.1	S	0.00920 U	0.00595 U	0.0105 U	0.0265 U	0.00642 U	0.0105 U	**1.84 J**	0.00735 U	0.0107 U	0.00712 U	0.0200 U	0.00832 U
	B-920-35	11/28/17	PES	ESC	16 (dup)	23.1	S	0.000363 U	0.000235 U	0.000413 U	0.00105 U	0.000253 U	0.000415 U	**0.0714 J**	0.000290 U	0.000423 U	0.000281 U	0.000789 U	0.000329 U
	B-226-21	11/28/17	PES	ESC	21	18.1	S	0.000374 U	0.000241 U	0.000425 U	0.00108 U	0.000261 U	0.000427 U	**0.00832**	0.000298 U	0.000435 U	0.000289 U	0.000812 U	0.000338 U
	B-226-31.5	11/28/17	PES	ESC	31.5	7.6	S	0.000349 U	0.000226 U	0.000397 U	0.00101 U	0.000244 U	0.000399 U	**0.135**	0.000279 U	0.000407 U	0.000270 U	0.000759 U	0.000316 U
	B-226-40	11/28/17	PES	ESC	40	-0.9	S	0.000375 U	0.000243 U	0.000427 U	**0.00130 J**	**0.00127 J**	0.000429 U	**0.112**	0.000300 U	0.000437 U	0.000291 U	0.000816 U	0.000340 U
B-227	B-227-6	11/28/17	PES	ESC	6	33.1	S	0.000374 U	0.000242 U	0.000426 U	0.00108 U	0.000261 U	0.000428 U	**0.000455 J**	0.000299 U	0.000436 U	0.000290 U	0.000814 U	0.000339 U
	B-227-11	11/28/17	PES	ESC	11	28.1	S	0.000354 U	0.000228 U	0.000402 U	0.00102 U	0.000247 U	0.000404 U	**0.0438**	0.000282 U	0.000412 U	0.000274 U	0.000768 U	0.000320 U
	B-227-16	11/28/17	PES	ESC	16	23.1	S	0.000376 U	0.000243 U	0.000427 U	0.00108 U	0.000262 U	0.000430 U	**0.429**	0.000300 U	0.000438 U	0.000291 U	0.000817 U	0.000340 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
B-227 (continued)	B-227-21	11/28/17	PES	ESC	21	18.1	S	0.000381 U	0.000246 U	0.000433 U	0.00110 U	**0.000652 J**	0.000435 U	**0.393**	0.000304 U	0.000443 U	0.000295 U	0.000828 U	0.000345 U
	B-227-26	11/28/17	PES	ESC	26	13.1	S	0.000382 U	0.000247 U	0.000435 U	0.00110 U	**0.000388 J**	0.000437 U	**0.351**	0.000305 U	0.000445 U	0.000296 U	0.000831 U	0.000346 U
	B-227-31	11/28/17	PES	ESC	31	8.1	S	0.000393 U	0.000254 U	0.000447 U	0.00113 U	0.000275 U	0.000450 U	**0.0636**	0.000314 U	0.000458 U	0.000305 U	0.000855 U	**0.000356**
	B-227-36	11/28/17	PES	ESC	36	3.1	S	0.000376 U	0.000243 U	0.000428 U	**0.00119 J**	0.000263 U	0.000430 U	**0.382**	0.000301 U	0.000438 U	0.000292 U	0.000818 U	**0.000341**
B-228	B-228-6	11/29/17	PES	ESC	6	33.1	S	0.000401 U	0.000259 U	0.000456 U	0.00116 U	0.000280 U	0.000459 U	**0.00505**	0.000320 U	0.000467 U	0.000311 U	0.000872 U	0.000363 U
	B-228-11	11/29/17	PES	ESC	11	28.1	S	0.000365 U	0.000236 U	0.000415 U	0.00105 U	0.000255 U	0.000417 U	**0.000669 J**	0.000291 U	0.000425 U	0.000282 U	0.000793 U	0.000330 U
	B-228-16	11/29/17	PES	ESC	16	23.1	S	0.000353 U	0.000228 U	0.000402 U	0.00102 U	**0.000638 J**	0.000404 U	**0.811 J**	0.000282 U	0.000411 U	0.000274 U	0.000768 U	0.000320 U
	B-921-22	11/29/17	PES	ESC	16 (dup)	23.1	S	0.000377 U	0.000244 U	0.000428 U	0.00109 U	**0.000686 J**	0.000431 U	**0.474 J**	0.000301 U	0.000439 U	0.000292 U	0.000819 U	0.000341 U
	B-228-21	11/29/17	PES	ESC	21	18.1	S	0.000371 U	0.000240 U	0.000422 U	0.00107 U	0.000259 U	0.000424 U	**0.0290**	0.000296 U	0.000432 U	0.000287 U	0.000806 U	0.000336 U
	B-228-26	11/29/17	PES	ESC	26	13.1	S	0.000353 U	0.000228 U	0.000401 U	**0.00187 J**	0.000246 U	0.000404 U	**0.112**	0.000282 U	0.000411 U	0.000273 U	0.000767 U	0.000320 U
	B-228-31	11/29/17	PES	ESC	31	8.1	S	0.000364 U	0.000235 U	0.000414 U	0.00105 U	0.000254 U	0.000416 U	**0.121**	0.000291 U	0.000424 U	0.000282 U	0.000792 U	0.000330 U
	B-228-36	11/29/17	PES	ESC	36	3.1	S	0.000371 U	0.000239 U	0.000421 U	0.00107 U	0.000259 U	0.000424 U	**0.0648**	0.000296 U	0.000432 U	0.000287 U	0.000805 U	0.000336 U
B-229	B-229-6	11/29/17	PES	ESC	6	33.1	S	0.000480 U	0.000310 U	0.000546 U	0.00138 U	**0.00195 J**	0.000549 U	**0.0257**	0.000383 U	0.000559 U	0.000372 U	0.00104 U	0.000435 U
	B-229-11	11/29/17	PES	ESC	11	28.1	S	0.000466 U	0.000301 U	0.000529 U	0.00134 U	0.000325 U	0.000532 U	**0.118**	0.000372 U	0.000542 U	0.000361 U	0.00101 U	0.000422 U
	B-229-16	11/29/17	PES	ESC	16	23.1	S	0.000391 U	0.000253 U	0.000445 U	0.00113 U	**0.000291 J**	0.000447 U	**0.0188**	0.000312 U	0.000455 U	0.000303 U	0.000850 U	0.000354 U
	B-229-25	11/29/17	PES	ESC	25	14.1	S	0.000360 U	0.000232 U	0.000409 U	**0.00195 J**	0.000251 U	0.000411 U	**0.865**	0.000287 U	0.000419 U	0.000278 U	0.000782 U	0.000326 U
	B-229-31	11/29/17	PES	ESC	31	8.1	S	0.000396 U	0.000256 U	0.000450 U	0.00114 U	0.000276 U	0.000452 U	**2.35**	0.000316 U	0.000461 U	0.000306 U	0.000860 U	0.000358 U
	B-229-36	11/29/17	PES	ESC	36	3.1	S	0.000361 U	0.000233 U	0.000410 U	**0.00204 J**	0.000252 U	0.000412 U	**1.02**	0.000288 U	0.000420 U	0.000279 U	0.000784 U	0.000327 U
	B-229-41	11/29/17	PES	ESC	41	-1.9	S	0.000382 U	0.000247 U	0.000434 U	**0.00197 J**	0.000267 U	0.000437 U	**0.403 J**	0.000305 U	0.000445 U	0.000296 U	0.000830 U	0.000346 U
	B-229-45	11/29/17	PES	ESC	45	-5.9	S	0.000392 U	0.000254 U	0.000446 U	0.00113 U	0.000274 U	0.000449 U	**0.105 J+**	0.000313 U	0.000457 U	0.000304 U	0.000853 U	0.000355 U
B-230	B-230-6	11/30/17	PES	ESC	6	33.1	S	0.000346 U	0.000224 U	0.000393 U	0.000998 U	0.000242 U	0.000396 U	**0.00376**	0.000276 U	0.000403 U	0.000268 U	0.000752 U	0.000313 U
	B-230-11	11/30/17	PES	ESC	11	28.1	S	0.000358 U	0.000232 U	0.000407 U	0.00103 U	0.000250 U	0.000410 U	**0.00634**	0.000286 U	0.000417 U	0.000277 U	0.000779 U	0.000324 U
	B-230-16	11/30/17	PES	ESC	16	23.1	S	0.0913 U	0.0590 U	0.104 U	0.263 U	0.0637 U	0.104 U	**10.4**	0.0729 U	0.106 U	0.0707 U	0.198 U	0.0826 U
	B-230-21	11/30/17	PES	ESC	21	18.1	S	0.783 U	0.506 U	0.891 U	2.26 U	0.547 U	0.895 U	**2.71 J**	0.626 U	0.912 U	0.607 U	1.71 U	0.709 U
	B-922-15	11/30/17	PES	ESC	21 (dup)	18.1	S	0.396 U	0.256 U	0.450 U	1.14 U	0.277 U	0.453 U	**0.884 J**	0.316 U	0.461 U	0.307 U	0.861 U	0.359 U
	B-230-26	11/30/17	PES	ESC	26	13.1	S	0.983 U	0.635 U	1.12 U	2.83 U	0.685 U	1.12 U	0.705 U	0.785 U	1.14 U	0.761 U	2.13 U	0.889 U
	B-230-31	11/30/17	PES	ESC	31	8.1	S	0.408 U	0.264 U	0.464 U	1.18 U	0.285 U	0.466 U	**1.82**	0.326 U	0.475 U	0.316 U	0.887 U	0.369 U
	B-230-35	11/30/17	PES	ESC	35	4.1	S	0.0593 U	0.0383 U	0.0674 U	0.171 U	0.0413 U	0.0678 U	**0.470**	0.0473 U	0.0690 U	0.0459 U	0.129 U	0.0536 U
	B-230-55	11/30/17	PES	ESC	55	-15.9	S	0.0984 U	0.0636 U	0.112 U	0.283 U	0.0687 U	0.113 U	**1.97**	0.0786 U	0.115 U	0.0762 U	0.214 U	0.0891 U
B-231	B-231-6	11/30/17	PES	ESC	6	33.1	S	0.000405 U	0.000261 U	0.000460 U	0.00117 U	0.000282 U	0.000463 U	**0.00617**	0.000323 U	0.000471 U	0.000313 U	0.000879 U	0.000366 U
	B-231-11	11/30/17	PES	ESC	11	28.1	S	0.000387 U	0.000250 U	0.000440 U	0.00111 U	0.000270 U	0.000442 U	**0.000868 J**	0.000309 U	0.000450 U	0.000299 U	0.000840 U	0.000350 U
	B-231-16	11/30/17	PES	ESC	16	23.1	S	0.00919 U	0.00594 U	0.0104 U	0.0264 U	0.00641 U	0.0105 U	**2.18**	0.00734 U	0.0107 U	0.00711 U	0.0199 U	0.00831 U
	B-231-21	11/30/17	PES	ESC	21	18.1	S	0.0217 U	0.0140 U	0.0247 U	0.0625 U	0.0151 U	0.0248 U	**0.911**	0.0173 U	0.0253 U	0.0168 U	0.0471 U	0.0196 U
	B-231-26	11/30/17	PES	ESC	26	13.1	S	0.000381 U	0.000246 U	0.000433 U	**0.00193 J**	0.000266 U	0.000435 U	**0.122**	0.000304 U	0.000444 U	0.000295 U	0.000828 U	0.000345 U
	B-231-30	11/30/17	PES	ESC	30	9.1	S	0.000370 U	0.000239 U	0.000421 U	0.00107 U	0.000258 U	0.000423 U	**0.00245**	0.000296 U	0.000431 U	0.000287 U	0.000804 U	0.000335 U
	B-231-36	11/30/17	PES	ESC	36	3.1	S	0.000372 U	0.000240 U	0.000423 U	0.00107 U	0.000260 U	0.000425 U	**0.0441**	0.000297 U	0.000433 U	0.000288 U	0.000809 U	0.000337 U
B-232	B-232-6	12/1/17	PES	ESC	6	33.1	S	0.000387 U	0.000250 U	0.000440 U	0.00112 U	0.000270 U	0.000443 U	**0.00586**	0.000309 U	0.000451 U	0.000300 U	0.000842 U	0.000351 U
	B-232-11	12/1/17	PES	ESC	11	28.1	S	0.000436 U	0.000282 U	0.000496 U	0.00126 U	0.000305 U	0.000499 U	**0.00464 J+**	0.000349 U	0.000508 U	0.000338 U	0.000949 U	0.000395 U
	B-232-16	12/1/17	PES	ESC	16	23.1	S	0.000384 U	0.000248 U	0.000437 U	0.00111 U	0.000268 U	0.000439 U	**0.0101**	0.000307 U	0.000447 U	0.000297 U	0.000835 U	0.000348 U
	B-232-21	12/1/17	PES	ESC	21	18.1	S	0.000367 U	0.000237 U	0.000417 U	0.00106 U	0.000256 U	0.000420 U	**0.147**	0.000293 U	0.000428 U	0.000284 U	0.000798 U	0.000332 U
	B-232-26	12/1/17	PES	ESC	26	13.1	S	0.0122 U	0.00792 U	0.0139 U	0.0353 U	0.00855 U	0.0140 U	**0.474**	0.00979 U	0.0142 U	0.00949 U	0.0266 U	0.0111 U
	B-232-31	12/1/17	PES	ESC	31	8.1	S	0.000370 U	0.000239 U	0.000421 U	0.00107 U	0.000259 U	0.000423 U	**0.0874**	0.000296 U	0.000431 U	0.000287 U	0.000805 U	0.000335 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
B-232 (continued)	B-232-36	12/1/17	PES	ESC	36	3.1	S	0.000389 U	0.000251 U	0.000442 U	0.00112 U	0.000271 U	0.000445 U	**0.110**	0.000311 U	0.000453 U	0.000301 U	0.000845 U	0.000352 U
B-233	B-233-6	12/1/17	PES	ESC	6	29.5	S	0.000354 U	0.000229 U	0.000403 U	0.00102 U	0.000247 U	0.000405 U	**0.00266**	0.000283 U	0.000412 U	0.000274 U	0.000769 U	0.000320 U
	B-233-11	12/1/17	PES	ESC	11	24.5	S	0.000915 U	0.000591 U	0.00104 U	0.00264 U	0.000638 U	0.00105 U	**0.0321 J+**	0.000731 U	0.00107 U	0.000709 U	0.00198 U	0.000828 U
	B-233-16	12/1/17	PES	ESC	16	19.5	S	0.000463 U	0.000299 U	0.000526 U	0.00134 U	0.000323 U	0.000529 U	**0.0101**	0.000370 U	0.000539 U	0.000359 U	0.00101 U	0.000419 U
	B-233-21	12/1/17	PES	ESC	21	14.5	S	0.00936 U	0.00605 U	0.0106 U	0.0269 U	0.00653 U	0.0107 U	**0.645**	0.00747 U	0.0109 U	0.00724 U	0.0203 U	0.00847 U
	B-233-26	12/1/17	PES	ESC	26	9.5	S	0.0196 U	0.0127 U	0.0222 U	0.0565 U	0.0136 U	0.0225 U	**2.40**	0.0157 U	0.0228 U	0.0152 U	0.0426 U	0.0177 U
	B-233-31	12/1/17	PES	ESC	31	4.5	S	0.0102 U	0.00659 U	0.0116 U	0.0293 U	0.00711 U	0.0117 U	**1.65**	0.00814 U	0.0119 U	0.00790 U	0.0221 U	0.00923 U
	B-233-36	12/1/17	PES	ESC	36	-0.5	S	0.00923 U	0.00597 U	0.0105 U	0.0266 U	0.00644 U	0.0106 U	**0.969**	0.00737 U	0.0107 U	0.00715 U	0.0200 U	0.00835 U
B-234	B-234-11	12/4/17	PES	ESC	11	40.8	V	0.000381 U	0.000246 U	0.000434 U	0.00110 U	0.000266 U	0.000436 U	0.000273 U	0.000305 U	0.000444 U	0.000295 U	0.000829 U	0.000345 U
	B-234-30	12/4/17	PES	ESC	30	21.8	S	0.000347 U	0.000224 U	0.000395 U	0.00100 U	0.000242 U	0.000397 U	0.000249 U	0.000277 U	0.000404 U	0.000269 U	0.000755 U	0.000314 U
B-234A	B-234A-35	12/4/17	PES	ESC	35	16.8	S	0.000376 U	0.000243 U	0.000428 U	0.00109 U	0.000263 U	0.000430 U	0.000270 U	0.000301 U	0.000438 U	0.000291 U	0.000818 U	0.000341 U
	B-234A-40	12/4/17	PES	ESC	40	11.8	S	0.000353 U	0.000228 U	0.000401 U	0.00102 U	0.000246 U	0.000404 U	0.000253 U	0.000282 U	0.000411 U	0.000273 U	0.000767 U	0.000320 U
	B-234A-42	12/4/17	PES	ESC	42	9.8	S	0.000402 U	0.000260 U	0.000457 U	0.00116 U	0.000281 U	0.000459 U	**3.65 J**	0.000321 U	0.000468 U	0.000311 U	0.000874 U	0.000364 U
	B-924-30	12/4/17	PES	ESC	42 (dup)	9.8	S	0.000398 U	0.000257 U	0.000453 U	0.00115 U	0.000278 U	0.000455 U	**2.54 J**	0.000318 U	0.000464 U	0.000309 U	0.000866 U	0.000361 U
	B-234A-45	12/4/17	PES	ESC	45	6.8	S	0.000370 U	0.000239 U	0.000420 U	0.00107 U	0.000258 U	0.000423 U	**1.99**	0.000295 U	0.000430 U	0.000286 U	0.000804 U	0.000335 U
B-235	B-235-15	12/5/17	PES	ESC	15	36.8	V	0.000393 U	0.000255 U	0.000448 U	0.00113 U	0.000275 U	0.000450 U	0.000261 U	0.000315 U	0.000458 U	0.000305 U	0.000856 U	0.000357 U
	B-235-35	12/5/17	PES	ESC	35	16.8	S	0.000363 U	0.000235 U	0.000413 U	0.00105 U	0.000254 U	0.000415 U	**0.000746 J**	0.000290 U	0.000423 U	0.000281 U	0.000789 U	0.000329 U
	B-235-40	12/5/17	PES	ESC	40	11.8	S	0.000360 U	0.000232 U	0.000409 U	0.00104 U	0.000251 U	0.000411 U	**0.00618**	0.000287 U	0.000419 U	0.000278 U	0.000782 U	0.000326 U
	B-235-42.5	12/5/17	PES	ESC	42.5	9.3	S	0.0716 U	0.0463 U	0.0815 U	0.206 U	0.0500 U	0.0819 U	**2.07**	0.0572 U	0.0834 U	0.0555 U	0.156 U	0.0649 U
	B-235-45	12/5/17	PES	ESC	45	6.8	S	0.000369 U	0.000239 U	0.000420 U	0.00107 U	0.000258 U	0.000422 U	**0.479**	0.000295 U	0.000430 U	0.000286 U	0.000803 U	0.000334 U
B-236	B-236-20	12/5/17	PES	ESC	20	31.8	S	0.000375 U	0.000242 U	0.000426 U	0.00108 U	0.000262 U	0.000429 U	**0.00139**	0.000300 U	0.000437 U	0.000290 U	0.000815 U	0.000340 U
	B-236-35	12/5/17	PES	ESC	35	16.8	S	0.000595 U	0.000385 U	0.000676 U	0.00171 U	0.000415 U	0.000679 U	0.000261 U	0.000475 U	0.000692 U	0.000460 U	0.00129 U	0.000538 U
	B-236-40	12/5/17	PES	ESC	40	11.8	S	0.000363 U	0.000235 U	0.000413 U	0.00105 U	0.000253 U	0.000415 U	**0.00621**	0.000290 U	0.000423 U	0.000281 U	0.000789 U	0.000329 U
	B-236-42.5	12/5/17	PES	ESC	42.5	9.3	S	0.385 U	0.249 U	0.437 U	1.11 U	0.269 U	0.440 U	**2.87**	0.307 U	0.448 U	0.298 U	0.836 U	0.348 U
	B-236-45	12/5/17	PES	ESC	45	6.8	S	0.128 U	0.0833 U	0.146 U	0.372 U	0.0900 U	0.147 U	**0.969**	0.103 U	0.150 U	0.0998 U	0.280 U	0.116 U
B-237	B-237-5	12/6/17	PES	ESC	5	46.8	V	0.000382 U	0.000247 U	0.000434 U	0.00110 U	0.000267 U	0.000437 U	0.000274 U	0.000305 U	0.000445 U	0.000296 U	0.000830 U	0.000346 U
	B-237-35	12/6/17	PES	ESC	35	16.8	S	0.000383 U	0.000248 U	0.000436 U	0.00110 U	0.000267 U	0.000438 U	0.000274 U	0.000306 U	0.000446 U	0.000297 U	0.000833 U	0.000347 U
	B-237-40	12/6/17	PES	ESC	40	11.8	S	0.000352 U	0.000228 U	0.000401 U	0.00102 U	0.000246 U	0.000403 U	**1.34**	0.000282 U	0.000410 U	0.000273 U	0.000766 U	0.000319 U
	B-237-42	12/6/17	PES	ESC	42	9.8	S	0.000388 U	0.000251 U	0.000441 U	0.00112 U	0.000271 U	0.000443 U	**1.84 J**	0.000310 U	0.000451 U	0.000300 U	0.000843 U	0.000351 U
	B-925-41	12/6/17	PES	ESC	42 (dup)	9.8	S	0.0419 U	0.0271 U	0.0476 U	0.121 U	0.0292 U	0.0479 U	**4.51 J**	0.0335 U	0.0488 U	0.0324 U	0.0910 U	0.0379 U
	B-237-45	12/6/17	PES	ESC	45	6.8	S	0.000422 U	0.000273 U	0.000480 U	0.00122 U	0.000295 U	0.000483 U	**2.83**	0.000337 U	0.000492 U	0.000327 U	0.000918 U	0.000382 U
B-238	B-238-6	12/6/17	PES	ESC	6	33.1	S	0.000382 U	0.000247 U	0.000435 U	0.00110 U	0.000267 U	0.000437 U	**0.0118**	0.000305 U	0.000445 U	0.000296 U	0.000831 U	0.000346 U
	B-238-11	12/6/17	PES	ESC	11	28.1	S	0.000382 U	0.000247 U	0.000434 U	**0.00205 J**	0.000266 U	0.000436 U	**0.0767 J+**	0.000305 U	0.000444 U	0.000296 U	0.000830 U	0.000346 U
	B-238-16	12/6/17	PES	ESC	16	23.1	S	0.0938 U	0.0606 U	0.107 U	0.270 U	0.0654 U	0.107 U	**0.191 J**	0.0749 U	0.109 U	0.0727 U	0.204 U	0.0849 U
	B-238-21	12/6/17	PES	ESC	21	18.1	S	0.366 U	0.237 U	0.416 U	1.06 U	0.256 U	0.418 U	0.262 U	0.292 U	0.426 U	0.283 U	0.796 U	0.331 U
	B-238-26	12/6/17	PES	ESC	26	13.1	S	0.000367 U	0.000237 U	0.000417 U	**0.00393 J**	0.000256 U	0.000419 U	**0.375**	0.000293 U	0.000427 U	0.000284 U	0.000797 U	0.000332 U
	B-238-31	12/6/17	PES	ESC	31	8.1	S	0.000348 U	0.000225 U	0.000395 U	0.00100 U	0.000243 U	0.000398 U	**0.0572**	0.000278 U	0.000405 U	0.000269 U	0.000756 U	0.000315 U
	B-238-36	12/6/17	PES	ESC	36	3.1	S	0.000384 U	0.000248 U	0.000437 U	0.00111 U	0.000268 U	0.000439 U	**0.0928**	0.000307 U	0.000447 U	0.000297 U	0.000835 U	0.000348 U
B-239	B-239-5	4/3/18	PES	ESC	5	34.2	S	0.000390 U	0.000252 U	0.000444 U	0.00113 U	0.000272 U	0.000446 U	**0.0107**	0.000312 U	0.000454 U	0.000302 U	0.000848 U	0.000353 U
	B-239-10	4/3/18	PES	ESC	10	29.2	S	0.000387 U	0.000250 U	0.000440 U	0.00112 U	0.000270 U	0.000442 U	**0.0366**	0.000309 U	0.000451 U	0.000300 U	0.000841 U	0.000350 U
	B-239-15	4/3/18	PES	ESC	15	24.2	S	0.000373 U	0.000241 U	0.000425 U	0.00108 U	0.000261 U	0.000427 U	**0.0187**	0.000298 U	0.000435 U	0.000289 U	0.000812 U	0.000338 U
	B-239-20	4/3/18	PES	ESC	20	19.2	S	0.000370 U	0.000239 U	0.000421 U	0.00107 U	0.000258 U	0.000423 U	**0.000649 J**	0.000296 U	0.000431 U	0.000287 U	0.000805 U	0.000335 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
B-239 (continued)	B-239-25	4/3/18	PES	ESC	25	14.2	S	0.000376 U	0.000243 U	0.000427 U	0.00108 U	0.000262 U	0.000430 U	**0.000411 J**	0.000300 U	0.000438 U	0.000291 U	0.000817 U	0.000340 U
	B-239-35	4/3/18	PES	ESC	35	4.2	S	0.000355 U	0.000229 U	0.000404 U	0.00102 U	**0.000249 J**	0.000406 U	**0.00395**	0.000284 U	0.000414 U	0.000275 U	0.000772 U	0.000322 U
	B-239-40	4/3/18	PES	ESC	40	-0.8	S	0.000372 U	0.000241 U	0.000423 U	0.00107 U	**0.000349 J**	0.000425 U	**0.00454**	0.000297 U	0.000433 U	0.000288 U	0.000809 U	0.000337 U
	B-239-45	4/3/18	PES	ESC	45	-5.8	S	0.000367 U	0.000237 U	0.000418 U	0.00106 U	0.000257 U	0.000420 U	**0.000317 J**	0.000293 U	0.000428 U	0.000285 U	0.000799 U	0.000333 U
	B-239-50	4/3/18	PES	ESC	50	-10.8	S	0.000362 U	0.000234 U	0.000412 U	0.00104 U	0.000253 U	0.000414 U	**0.000272 J**	0.000289 U	0.000422 U	0.000281 U	0.000787 U	0.000328 U
	B-909-50	4/3/18	PES	ESC	50 (dup)	-10.8	S	0.000364 U	0.000236 U	0.000414 U	0.00105 U	0.000254 U	0.000417 U	0.000261 U	0.000291 U	0.000424 U	0.000282 U	0.000792 U	0.000330 U
	B-239-55	4/3/18	PES	ESC	55	-15.8	S	0.000373 U	0.000241 U	0.000424 U	0.00108 U	0.000261 U	0.000427 U	0.000267 U	0.000298 U	0.000435 U	0.000289 U	0.000811 U	0.000338 U
	B-239-60	4/3/18	PES	ESC	60	-20.8	S	0.000367 U	0.000237 U	0.000417 U	0.00106 U	0.000256 U	0.000419 U	0.000263 U	0.000293 U	0.000427 U	0.000284 U	0.000797 U	0.000332 U
	B-239-65	4/3/18	PES	ESC	65	-25.8	S	0.000367 U	0.000237 U	0.000417 U	0.00106 U	0.000256 U	0.000419 U	0.000263 U	0.000293 U	0.000427 U	0.000284 U	0.000797 U	0.000332 U
	B-239-70	4/3/18	PES	ESC	70	-30.8	S	0.000365 U	0.000236 U	0.000415 U	0.00105 U	0.000255 U	0.000418 U	0.000262 U	0.000292 U	0.000426 U	0.000283 U	0.000794 U	0.000331 U
	B-239-75	4/3/18	PES	ESC	75	-35.8	S	0.000378 U	0.000244 U	0.000430 U	0.00109 U	0.000264 U	0.000432 U	0.000271 U	0.000302 U	0.000440 U	0.000293 U	0.000822 U	0.000342 U
	B-239-80	4/3/18	PES	ESC	80	-40.8	S	0.000375 U	0.000243 U	0.000427 U	0.00108 U	0.000262 U	0.000429 U	0.000269 U	0.000300 U	0.000437 U	0.000291 U	0.000816 U	0.000340 U
B-240	B-240-5	4/2/18	PES	ESC	5	34.2	S	0.000362 U	0.000234 U	0.000412 U	0.00104 U	0.000253 U	0.000414 U	**0.00274**	0.000289 U	0.000422 U	0.000280 U	0.000787 U	0.000328 U
	B-240-10	4/2/18	PES	ESC	10	29.2	S	0.000362 U	0.000234 U	0.000411 U	0.00104 U	0.000252 U	0.000413 U	**0.0929**	0.000289 U	0.000421 U	0.000280 U	0.000786 U	0.000327 U
	B-240-15	4/2/18	PES	ESC	15	24.2	S	0.000376 U	0.000243 U	0.000428 U	0.00109 U	0.000263 U	0.000430 U	**0.0785**	0.000301 U	0.000438 U	0.000291 U	0.000818 U	0.000341 U
	B-240-20	4/2/18	PES	ESC	20	19.2	S	0.000382 U	0.000247 U	0.000434 U	0.00110 U	0.000267 U	0.000437 U	**0.142**	0.000305 U	0.000445 U	0.000296 U	0.000830 U	0.000346 U
	B-240-25	4/2/18	PES	ESC	25	14.2	S	0.0183 U	0.0118 U	0.0208 U	0.0528 U	0.0127 U	0.0210 U	**0.356**	0.0146 U	0.0213 U	0.0142 U	0.0398 U	0.0165 U
	B-240-30	4/2/18	PES	ESC	30	9.2	S	0.000395 U	0.000255 U	0.000449 U	0.00114 U	0.000276 U	0.000452 U	**0.578**	0.000316 U	0.000460 U	0.000306 U	0.000859 U	0.000358 U
	B-240-35	4/2/18	PES	ESC	35	4.2	S	0.000394 U	0.000255 U	0.000448 U	0.00114 U	0.000275 U	0.000450 U	**0.461**	0.000315 U	0.000459 U	0.000305 U	0.000856 U	0.000357 U
	B-240-42	4/2/18	PES	ESC	42	-2.8	S	0.000353 U	0.000228 U	0.000402 U	0.00102 U	0.000247 U	0.000404 U	**0.00863 J**	0.000282 U	0.000411 U	0.000273 U	0.000768 U	0.000320 U
	B-240-45	4/2/18	PES	ESC	45	-5.8	S	0.000348 U	0.000225 U	0.000396 U	0.00100 U	0.000243 U	0.000398 U	**0.000371 J**	0.000278 U	0.000405 U	0.000269 U	0.000756 U	0.000315 U
	B-240-50	4/2/18	PES	ESC	50	-10.8	S	0.000369 U	0.000239 U	0.000420 U	0.00107 U	0.000258 U	0.000422 U	0.000265 U	0.000295 U	0.000430 U	0.000286 U	0.000803 U	0.000334 U
	B-240-55	4/2/18	PES	ESC	55	-15.8	S	0.000381 U	0.000246 U	0.000433 U	0.00110 U	0.000266 U	0.000435 U	**0.00231**	0.000304 U	0.000443 U	0.000295 U	0.000827 U	0.000345 U
	B-240-60	4/2/18	PES	ESC	60	-20.8	S	0.000382 U	0.000247 U	0.000434 U	0.00110 U	0.000267 U	0.000437 U	**0.0157**	0.000305 U	0.000445 U	0.000296 U	0.000830 U	0.000346 U
	B-240-65	4/2/18	PES	ESC	65	-25.8	S	0.000356 U	0.000230 U	0.000404 U	0.00103 U	0.000248 U	0.000407 U	**0.00152**	0.000284 U	0.000414 U	0.000275 U	0.000773 U	0.000322 U
	B-240-70	4/2/18	PES	ESC	70	-30.8	S	0.000379 U	0.000245 U	0.000432 U	0.00109 U	0.000265 U	0.000434 U	**0.0138**	0.000303 U	0.000442 U	0.000294 U	0.000825 U	0.000344 U
	B-240-75	4/2/18	PES	ESC	75	-35.8	S	0.000360 U	0.000233 U	0.000410 U	0.00104 U	0.000251 U	0.000412 U	**0.00612**	0.000288 U	0.000420 U	0.000279 U	0.000783 U	0.000326 U
	B-240-80	4/2/18	PES	ESC	80	-40.8	S	0.000373 U	0.000241 U	0.000424 U	0.00108 U	0.000260 U	0.000427 U	**0.000662 J**	0.000298 U	0.000435 U	0.000289 U	0.000811 U	0.000338 U
B-241	B-241-5	4/4/18	PES	ESC	5	34.1	S	0.000356 U	0.000230 U	0.000405 U	0.00103 U	0.000248 U	0.000407 U	**0.00554**	0.000284 U	0.000414 U	0.000275 U	0.000773 U	**0.210**
	B-241-10	4/4/18	PES	ESC	10	29.1	S	0.000372 U	0.000240 U	0.000423 U	0.00107 U	0.000260 U	0.000425 U	**0.0503**	0.000297 U	0.000433 U	0.000288 U	0.000808 U	**0.000337 J**
	B-241-15	4/4/18	PES	ESC	15	24.1	S	0.000366 U	0.000237 U	0.000416 U	**0.00120 J**	0.000256 U	0.000419 U	**0.000701 J**	0.000292 U	0.000426 U	0.000284 U	0.000796 U	0.000332 U
	B-241-20	4/4/18	PES	ESC	20	19.1	S	0.000399 U	0.000258 U	0.000454 U	**0.00488 J**	0.000279 U	0.000456 U	**0.172**	0.000319 U	0.000465 U	0.000309 U	0.000868 U	0.000361 U
	B-241-25	4/4/18	PES	ESC	25	14.1	S	0.000371 U	0.000240 U	0.000422 U	0.00107 U	0.000259 U	**0.000674 J**	**0.0177**	0.000296 U	0.000432 U	0.000287 U	0.000806 U	0.000336 U
	B-241-30	4/3/18	PES	ESC	30	9.1	S	0.000368 U	0.000238 U	0.000418 U	**0.0124**	0.000257 U	0.000421 U	**0.469**	0.000294 U	0.000428 U	0.000285 U	0.000800 U	0.000333 U
	B-241-35	4/3/18	PES	ESC	35	4.1	S	0.000380 U	0.000245 U	0.000432 U	0.00110 U	0.000265 U	0.000434 U	**0.00791**	0.000303 U	0.000442 U	0.000294 U	0.000825 U	0.000344 U
	B-241-40	4/3/18	PES	ESC	40	-0.9	S	0.000360 U	0.000233 U	0.000409 U	0.00104 U	0.000251 U	**0.000804 J**	**0.0154**	0.000287 U	0.000419 U	0.000279 U	0.000782 U	0.000326 U
	B-241-45	4/3/18	PES	ESC	45	-5.9	S	0.000361 U	0.000233 U	0.000411 U	0.00104 U	0.000252 U	**0.00406**	**1.37**	0.000288 U	0.000421 U	0.000280 U	0.000785 U	0.000327 U
	B-241-50	4/4/18	PES	ESC	50	-10.9	S	0.000370 U	0.000239 U	0.000420 U	0.00107 U	0.000258 U	0.000423 U	**7.44**	0.000295 U	0.000430 U	0.000286 U	0.000803 U	0.000335 U
	B-241-55	4/4/18	PES	ESC	55	-15.9	S	0.000382 U	0.000247 U	0.000434 U	0.00110 U	0.000267 U	0.000437 U	**2.01**	0.000305 U	0.000445 U	0.000296 U	0.000830 U	0.000346 U
	B-241-60	4/3/18	PES	ESC	60	-20.9	S	0.000367 U	0.000237 U	0.000418 U	0.00106 U	0.000256 U	0.000420 U	**0.00708**	0.000293 U	0.000428 U	0.000284 U	0.000798 U	0.000333 U
	B-241-65	4/3/18	PES	ESC	65	-25.9	S	0.000388 U	0.000251 U	0.000441 U	0.00112 U	0.000271 U	0.000444 U	**0.0585**	0.000310 U	0.000452 U	0.000301 U	0.000844 U	0.000352 U
	B-241-70	4/3/18	PES	ESC	70	-30.9	S	0.000379 U	0.000245 U	0.000431 U	0.00109 U	0.000264 U	**0.000544 J**	**0.0186**	0.000302 U	0.000441 U	0.000293 U	0.000823 U	0.000343 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
B-241	B-241-75	4/3/18	PES	ESC	75	-35.9	S	0.000382 U	0.000247 U	0.000435 U	0.00110 U	0.000267 U	**0.000514 J**	**0.358**	0.000306 U	0.000445 U	0.000296 U	0.000831 U	0.000346 U
(continued)	B-241-80	4/4/18	PES	ESC	80	-40.9	S	0.000377 U	0.000244 U	0.000429 U	0.00109 U	0.000263 U	0.000431 U	**0.0508**	0.000301 U	0.000439 U	0.000292 U	0.000819 U	0.000341 U
B-242	B-242-5	4/4/18	PES	ESC	5	33.8	S	0.000356 U	0.000230 U	0.000405 U	0.00103 U	0.000249 U	0.000407 U	**0.00494**	0.000284 U	0.000415 U	0.000276 U	0.000774 U	0.000322 U
	B-242-10	4/4/18	PES	ESC	10	28.8	S	0.000359 U	0.000232 U	0.000408 U	0.00104 U	0.000251 U	0.000410 U	**0.00156**	0.000287 U	0.000418 U	0.000278 U	0.000780 U	0.000325 U
	B-242-15	4/4/18	PES	ESC	15	23.8	S	0.000382 U	0.000247 U	0.000435 U	0.00110 U	0.000267 U	0.000437 U	**0.00483**	0.000306 U	0.000445 U	0.000296 U	0.000831 U	0.000346 U
	B-242-20	4/4/18	PES	ESC	20	18.8	S	0.000372 U	0.000240 U	0.000423 U	0.00107 U	0.000259 U	0.000425 U	**0.00878**	0.000297 U	0.000433 U	0.000288 U	0.000808 U	0.000336 U
	B-242-25	4/4/18	PES	ESC	25	13.8	S	0.0362 U	0.0234 U	0.0411 U	0.104 U	0.0252 U	0.0413 U	0.0259 U	0.0289 U	0.0421 U	0.0280 U	0.0786 U	0.0327 U
	B-242-30	4/4/18	PES	ESC	30	8.8	S	0.000367 U	0.000237 U	0.000417 U	0.00106 U	0.000256 U	0.000419 U	**0.00101 J**	0.000293 U	0.000427 U	0.000284 U	0.000798 U	0.000332 U
	B-242-35	4/4/18	PES	ESC	35	3.8	S	0.000378 U	0.000244 U	0.000430 U	0.00109 U	0.000264 U	0.000432 U	**0.000439 J**	0.000302 U	0.000440 U	0.000292 U	0.000821 U	0.000342 U
	B-242-40	4/4/18	PES	ESC	40	-1.2	S	0.000359 U	0.000232 U	0.000408 U	0.00103 U	0.000251 U	0.000410 U	**0.00272**	0.000287 U	0.000418 U	0.000278 U	0.000780 U	0.000325 U
	B-242-45	4/4/18	PES	ESC	45	-6.2	S	0.000379 U	0.000245 U	0.000431 U	0.00109 U	0.000265 U	0.000434 U	0.000272 U	0.000303 U	0.000442 U	0.000294 U	0.000825 U	0.000344 U
	B-242-50	4/4/18	PES	ESC	50	-11.2	S	0.000367 U	0.000237 U	0.000418 U	0.00106 U	0.000256 U	0.000420 U	0.000263 U	0.000293 U	0.000428 U	0.000284 U	0.000798 U	0.000333 U
	B-910-50	4/4/18	PES	ESC	50 (dup)	-11.2	S	0.000368 U	0.000238 U	0.000418 U	0.00106 U	0.000257 U	0.000421 U	0.000264 U	0.000294 U	0.000429 U	0.000285 U	0.000800 U	0.000333 U
	B-242-55	4/4/18	PES	ESC	55	-16.2	S	0.000360 U	0.000233 U	0.000410 U	0.00104 U	0.000252 U	0.000412 U	0.000258 U	0.000288 U	0.000420 U	0.000279 U	0.000783 U	0.000326 U
	B-242-60	4/4/18	PES	ESC	60	-21.2	S	0.000362 U	0.000234 U	0.000411 U	0.00104 U	0.000253 U	0.000414 U	0.000259 U	0.000289 U	0.000421 U	0.000280 U	0.000786 U	0.000328 U
	B-242-65	4/4/18	PES	ESC	65	-26.2	S	0.000355 U	0.000230 U	0.000404 U	0.00102 U	0.000248 U	0.000406 U	0.000254 U	0.000284 U	0.000414 U	0.000275 U	0.000772 U	0.000322 U
	B-242-70	4/4/18	PES	ESC	70	-31.2	S	0.000376 U	0.000243 U	0.000427 U	0.00108 U	0.000262 U	0.000430 U	0.000269 U	0.000300 U	0.000438 U	0.000291 U	0.000817 U	0.000340 U
	B-242-75	4/4/18	PES	ESC	75	-36.2	S	0.000364 U	0.000235 U	0.000414 U	0.00105 U	0.000254 U	**0.00349**	**0.00118 J+**	0.000291 U	0.000424 U	0.000282 U	0.000791 U	0.000329 U
	B-242-80	4/4/18	PES	ESC	80	-41.2	S	0.000380 U	0.000246 U	0.000432 U	0.00110 U	0.000265 U	0.000434 U	0.000272 U	0.000304 U	0.000443 U	0.000294 U	0.000826 U	0.000344 U
B-243	B-243-5	3/29/18	PES	ESC	5	34.9	S	0.000381 U	0.000246 U	0.000433 U	0.00110 U	0.000266 U	0.000436 U	0.000273 U	0.000304 U	0.000444 U	0.000295 U	0.000828 U	0.000345 U
	B-243-10	3/29/18	PES	ESC	10	29.9	S	0.000373 U	0.000241 U	0.000424 U	0.00107 U	0.000260 U	0.000426 U	**0.000267 J**	0.000298 U	0.000434 U	0.000289 U	0.000810 U	0.000337 U
	B-243-15	3/29/18	PES	ESC	15	24.9	S	0.00928 U	0.00600 U	0.0105 U	0.0267 U	0.00647 U	0.0106 U	0.00665 U	0.00741 U	0.0108 U	0.00719 U	0.0201 U	0.00840 U
	B-243-20	3/29/18	PES	ESC	20	19.9	S	0.000378 U	0.000244 U	0.000430 U	0.00109 U	0.000264 U	0.000432 U	0.000271 U	0.000302 U	0.000440 U	0.000293 U	0.000822 U	0.000342 U
	B-243-25	3/29/18	PES	ESC	25	14.9	S	0.000366 U	0.000236 U	0.000416 U	0.00105 U	0.000255 U	0.000418 U	0.000262 U	0.000292 U	0.000426 U	0.000283 U	0.000795 U	0.000331 U
	B-243-30	3/29/18	PES	ESC	30	9.9	S	0.000357 U	0.000231 U	0.000406 U	0.00103 U	0.000249 U	0.000408 U	0.000256 U	0.000285 U	0.000416 U	0.000277 U	0.000776 U	0.000323 U
	B-243-35	3/29/18	PES	ESC	35	4.9	S	0.000363 U	0.000235 U	0.000413 U	0.00105 U	**0.000274 J**	0.000415 U	**0.0121**	0.000290 U	0.000423 U	0.000281 U	0.000790 U	0.000329 U
	B-243-42	3/29/18	PES	ESC	42	-2.1	S	0.000358 U	0.000232 U	0.000408 U	0.00103 U	0.000250 U	0.000410 U	**1.40**	0.000286 U	0.000417 U	0.000278 U	0.000779 U	0.000325 U
	B-243-45	3/29/18	PES	ESC	45	-5.1	S	0.000355 U	0.000230 U	0.000404 U	0.00102 U	0.000248 U	0.000406 U	**0.569**	0.000284 U	0.000414 U	0.000275 U	0.000772 U	0.000322 U
	B-243-50	3/29/18	PES	ESC	50	-10.1	S	0.000379 U	0.000245 U	0.000431 U	0.00109 U	0.000264 U	0.000433 U	**16.0**	0.000303 U	0.000441 U	0.000293 U	0.000823 U	0.000343 U
	IW-908-50	3/29/18	PES	ESC	50 (dup)	-10.1	S	0.000371 U	0.000240 U	0.000422 U	0.00107 U	0.000259 U	0.000424 U	**15.9**	0.000296 U	0.000432 U	0.000287 U	0.000807 U	0.000336 U
	B-243-55	3/29/18	PES	ESC	55	-15.1	S	0.000354 U	0.000229 U	0.000403 U	0.00102 U	0.000247 U	0.000405 U	**2.33**	0.000283 U	0.000412 U	0.000274 U	0.000770 U	0.000321 U
	B-243-60	3/29/18	PES	ESC	60	-20.1	S	0.000375 U	0.000242 U	0.000426 U	0.00108 U	0.000262 U	0.000429 U	**6.30**	0.000299 U	0.000437 U	0.000290 U	0.000815 U	0.000339 U
	B-243-65	3/29/18	PES	ESC	65	-25.1	S	0.000360 U	0.000233 U	0.000410 U	0.00104 U	0.000251 U	0.000412 U	**0.530**	0.000288 U	0.000420 U	0.000279 U	0.000783 U	0.000326 U
	B-243-70	3/29/18	PES	ESC	70	-30.1	S	0.000380 U	0.000246 U	0.000432 U	0.00110 U	0.000266 U	0.000435 U	0.000882 U	0.000304 U	0.000443 U	0.000294 U	0.000827 U	0.000344 U
	B-243-75	3/29/18	PES	ESC	75	-35.1	S	0.000391 U	0.000253 U	0.000444 U	0.00113 U	0.000273 U	0.000447 U	**0.00440**	0.000312 U	0.000455 U	0.000303 U	0.000849 U	0.000354 U
	B-243-80	3/29/18	PES	ESC	80	-40.1	S	0.000398 U	0.000258 U	0.000453 U	0.00115 U	0.000278 U	0.000455 U	**0.00775**	0.000318 U	0.000464 U	0.000309 U	0.000866 U	0.000361 U
B-244	B-244-5	3/28/18	PES	ESC	5	33.8	S	0.000414 U	0.000268 U	0.000471 U	0.00119 U	0.000289 U	0.000473 U	**0.00740**	0.000331 U	0.000482 U	0.000321 U	0.000900 U	0.000375 U
	B-244-10	3/28/18	PES	ESC	10	28.8	S	0.000391 U	0.000253 U	0.000444 U	0.00113 U	0.000273 U	0.000447 U	**0.00128**	0.000312 U	0.000455 U	0.000303 U	0.000850 U	0.000354 U
	B-244-15	3/28/18	PES	ESC	15	23.8	S	0.000374 U	0.000242 U	0.000426 U	0.00108 U	0.000261 U	0.000428 U	**0.000833 J**	0.000299 U	0.000436 U	0.000290 U	0.000814 U	0.000339 U
	B-244-20	3/28/18	PES	ESC	20	18.8	S	0.000372 U	0.000241 U	0.000423 U	0.00107 U	0.000260 U	0.000425 U	**0.00537**	0.000297 U	0.000433 U	0.000288 U	0.000809 U	0.000337 U
	B-244-25	3/28/18	PES	ESC	25	13.8	S	0.000347 U	0.000224 U	0.000395 U	0.00100 U	0.000242 U	0.000397 U	**0.00556**	0.000277 U	0.000404 U	0.000269 U	0.000755 U	0.000314 U
	B-244-30	3/28/18	PES	ESC	30	8.8	S	0.000359 U	0.000232 U	0.000408 U	0.00103 U	0.000250 U	0.000410 U	**0.0243**	0.000286 U	0.000418 U	0.000278 U	0.000780 U	0.000325 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
B-244 (continued)	B-244-35	3/28/18	PES	ESC	35	3.8	S	0.000377 U	0.000243 U	0.000428 U	0.00109 U	0.000263 U	0.000431 U	**0.0522**	0.000301 U	0.000439 U	0.000292 U	0.000819 U	0.000341 U
	B-244-40	3/28/18	PES	ESC	40	-1.2	S	0.000362 U	0.000234 U	0.000411 U	0.00104 U	0.000253 U	0.000414 U	**2.00**	0.000289 U	0.000421 U	0.000280 U	0.000786 U	0.000328 U
	B-244-42	3/28/18	PES	ESC	42	-3.2	S	0.00923 U	0.00596 U	0.0105 U	0.0266 U	0.00644 U	0.0106 U	**0.886**	0.00737 U	0.0107 U	0.00714 U	0.0200 U	0.00835 U
	B-244-45	3/28/18	PES	ESC	45	-6.2	S	0.000369 U	0.000239 U	0.000420 U	0.00106 U	0.000258 U	**0.00475 J**	**5.01**	0.000295 U	0.000430 U	0.000286 U	0.000802 U	0.000334 U
	B-244-50	3/28/18	PES	ESC	50	-11.2	S	0.000363 U	0.000234 U	0.000413 U	0.00105 U	0.000253 U	**0.000967 J**	**4.57**	0.000290 U	0.000422 U	0.000281 U	0.000789 U	0.000328 U
	B-244-55	3/28/18	PES	ESC	55	-16.2	S	0.000361 U	0.000233 U	0.000411 U	0.00104 U	0.000252 U	0.000413 U	**6.54**	0.000288 U	0.000421 U	0.000280 U	0.000785 U	0.000327 U
	B-244-60	3/28/18	PES	ESC	60	-21.2	S	0.000366 U	0.000237 U	0.000416 U	0.00106 U	0.000256 U	0.000419 U	**4.83**	0.000292 U	0.000426 U	0.000284 U	0.000796 U	0.000332 U
	B-244-65	3/28/18	PES	ESC	65	-26.2	S	0.000372 U	0.000240 U	0.000423 U	0.00107 U	0.000260 U	0.000425 U	**0.918**	0.000297 U	0.000433 U	0.000288 U	0.000808 U	0.000337 U
	B-244-70	3/28/18	PES	ESC	70	-31.2	S	0.000356 U	0.000230 U	0.000405 U	0.00103 U	0.000249 U	0.000407 U	**6.08**	0.000284 U	0.000415 U	0.000276 U	0.000774 U	0.000322 U
	IW-907-70	3/28/18	PES	ESC	70 (dup)	-31.2	S	0.000357 U	0.000231 U	0.000406 U	0.00103 U	0.000249 U	0.000408 U	**6.39**	0.000285 U	0.000416 U	0.000277 U	0.000776 U	0.000323 U
	B-244-75	3/28/18	PES	ESC	75	-36.2	S	0.000376 U	0.000243 U	0.000428 U	0.00108 U	0.000263 U	0.000430 U	**5.77**	0.000300 U	0.000438 U	0.000291 U	0.000818 U	0.000341 U
	B-244-80	3/28/18	PES	ESC	80	-41.2	S	0.000381 U	0.000246 U	0.000434 U	0.00110 U	0.000266 U	0.000436 U	**0.0188**	0.000305 U	0.000444 U	0.000295 U	0.000829 U	0.000345 U
B-245	B-245-5	3/28/18	PES	ESC	5	34.9	V	0.000357 U	0.000231 U	0.000406 U	0.00103 U	0.000249 U	0.000408 U	**0.000490 J**	0.000285 U	0.000416 U	0.000276 U	0.000776 U	0.000323 U
	B-245-10	3/28/18	PES	ESC	10	29.9	S	0.000376 U	0.000243 U	0.000428 U	0.00109 U	0.000263 U	0.000430 U	**0.00132**	0.000301 U	0.000438 U	0.000291 U	0.000818 U	0.000341 U
	B-245-15	3/28/18	PES	ESC	15	24.9	S	0.000380 U	0.000246 U	0.000432 U	0.00110 U	0.000265 U	0.000435 U	**0.00502**	0.000304 U	0.000443 U	0.000294 U	0.000826 U	0.000344 U
	B-245-20	3/28/18	PES	ESC	20	19.9	S	0.000354 U	0.000229 U	0.000403 U	0.00102 U	0.000247 U	0.000405 U	**0.00265**	0.000283 U	0.000413 U	0.000274 U	0.000770 U	0.000321 U
	B-245-25	3/28/18	PES	ESC	25	14.9	S	0.000371 U	0.000240 U	0.000422 U	0.00107 U	0.000259 U	0.000424 U	**0.00148**	0.000296 U	0.000432 U	0.000287 U	0.000807 U	0.000336 U
	B-245-30	3/29/18	PES	ESC	30	9.9	S	0.000705 U	0.000456 U	0.000802 U	0.00204 U	0.000493 U	0.000806 U	**4.73**	0.000563 U	0.000821 U	0.000547 U	0.00153 U	0.000638 U
	B-245-35	3/29/18	PES	ESC	35	4.9	S	0.000369 U	0.000239 U	0.000420 U	0.00106 U	0.000258 U	0.000422 U	**0.0564**	0.000295 U	0.000430 U	0.000286 U	0.000802 U	0.000334 U
	B-245-40	3/29/18	PES	ESC	40	-0.1	S	0.000365 U	0.000236 U	0.000415 U	0.00105 U	0.000255 U	0.000417 U	**0.107**	0.000292 U	0.000425 U	0.000283 U	0.000794 U	0.000331 U
	B-245-45	3/29/18	PES	ESC	45	-5.1	S	0.000365 U	0.000236 U	0.000415 U	0.00105 U	0.000255 U	0.000417 U	**0.00725**	0.000291 U	0.000425 U	0.000282 U	0.000793 U	0.000330 U
	B-245-50	3/29/18	PES	ESC	50	-10.1	S	0.000372 U	0.000240 U	0.000423 U	0.00107 U	0.000260 U	0.000425 U	**0.0159**	0.000297 U	0.000433 U	0.000288 U	0.000808 U	0.000337 U
	B-245-55	3/29/18	PES	ESC	55	-15.1	S	0.000370 U	0.000239 U	0.000420 U	0.00107 U	0.000258 U	0.000423 U	**0.0583**	0.000295 U	0.000431 U	0.000286 U	0.000804 U	0.000335 U
	B-245-60	3/29/18	PES	ESC	60	-20.1	S	0.000351 U	0.000227 U	0.000400 U	0.00101 U	0.000245 U	0.000402 U	**0.0180**	0.000281 U	0.000409 U	0.000272 U	0.000764 U	0.000318 U
	B-245-65	3/29/18	PES	ESC	65	-25.1	S	0.000375 U	0.000243 U	0.000427 U	0.00108 U	0.000262 U	0.000429 U	**0.0101**	0.000300 U	0.000437 U	0.000291 U	0.000816 U	0.000340 U
	B-245-70	3/29/18	PES	ESC	70	-30.1	S	0.000386 U	0.000249 U	0.000439 U	0.00111 U	0.000269 U	0.000441 U	**0.000656 J**	0.000308 U	0.000449 U	0.000299 U	0.000839 U	0.000349 U
	B-245-75	3/29/18	PES	ESC	75	-35.1	S	0.000370 U	0.000239 U	0.000420 U	0.00107 U	0.000258 U	0.000423 U	**0.000841 J**	0.000295 U	0.000431 U	0.000286 U	0.000804 U	0.000335 U
	B-245-80	3/29/18	PES	ESC	80	-40.1	S	0.000380 U	0.000246 U	0.000432 U	0.00110 U	0.000265 U	0.000434 U	**0.000946 J**	0.000304 U	0.000443 U	0.000294 U	0.000826 U	0.000344 U
B-246	B-246-6	5/11/18	PES	ESC	6	33.9	S	0.00128 U	0.000680 U	0.000534 U	0.00128 U	0.000493 U	0.00165 U	**0.00324**	0.000805 U	0.00119 U	0.000935 U	0.000971 U	0.000629 U
	B-246-11	5/11/18	PES	ESC	11	28.9	S	0.00128 U	0.000677 U	0.000531 U	0.00128 U	0.000490 U	0.00164 U	**0.00531**	0.000801 U	0.00118 U	0.000931 U	0.000966 U	0.000626 U
	B-246-15	5/11/18	PES	ESC	15	24.9	S	0.00122 U	0.000648 U	0.000509 U	0.00122 U	0.000469 U	0.00157 U	**0.0196**	0.000766 U	0.00113 U	0.000890 U	0.000924 U	0.000599 U
	B-246-25	5/11/18	PES	ESC	25	14.9	S	0.00121 U	0.000641 U	0.000503 U	0.00121 U	0.000464 U	0.00155 U	**0.157**	0.000758 U	0.00112 U	0.000881 U	0.000915 U	0.000593 U
	B-246-30	5/11/18	PES	ESC	30	9.9	S	0.00127 U	0.000674 U	0.000530 U	0.00127 U	0.000488 U	0.00164 U	**3.36**	0.000798 U	0.00118 U	0.000927 U	0.000963 U	0.000624 U
	B-246-35	5/11/18	PES	ESC	35	4.9	S	0.00125 U	0.000661 U	0.000519 U	0.00125 U	0.000478 U	0.00160 U	**0.00505**	0.000782 U	0.00115 U	0.000908 U	0.000943 U	0.000611 U
	B-246-40	5/11/18	PES	ESC	40	-0.1	S	0.00122 U	0.000649 U	0.000510 U	0.00122 U	0.000470 U	0.00157 U	**0.255**	0.000768 U	0.00113 U	0.000892 U	0.000926 U	0.000600 U
	B-246-43	5/11/18	PES	ESC	43	-3.1	S	0.00118 U	0.000627 U	0.000492 U	0.00118 U	0.000454 U	0.00152 U	**0.330**	0.000741 U	0.00109 U	0.000862 U	0.000895 U	0.000580 U
	B-246-45	5/11/18	PES	ESC	45	-5.1	S	0.00130 U	0.000691 U	0.000543 U	0.00130 U	0.000500 U	0.00167 U	**0.00410**	0.000817 U	0.00121 U	0.000951 U	0.000986 U	0.000639 U
	B-246-50	5/11/18	PES	ESC	50	-10.1	S	0.00122 U	0.000645 U	0.000506 U	0.00122 U	0.000467 U	0.00156 U	**0.00150 J**	0.000763 U	0.00113 U	0.000887 U	0.000920 U	0.000596 U
	B-246-55	5/11/18	PES	ESC	55	-15.1	S	0.00124 U	0.000656 U	0.000515 U	0.00124 U	0.000475 U	0.00159 U	**0.00111 J**	0.000776 U	0.00115 U	0.000902 U	0.000937 U	0.000607 U
	B-246-60	5/11/18	PES	ESC	60	-20.1	S	0.00123 U	0.000650 U	0.000511 U	0.00123 U	0.000471 U	0.00158 U	**0.00153 J**	0.000769 U	0.00113 U	0.000894 U	0.000928 U	0.000601 U
	B-246-65	5/11/18	PES	ESC	65	-25.1	S	0.00134 U	0.000709 U	0.000557 U	0.00134 U	0.000513 U	0.00172 U	**0.0338**	0.000839 U	0.00124 U	0.000975 U	0.00101 U	0.000656 U
	B-246-70	5/11/18	PES	ESC	70	-30.1	S	0.00120 U	0.000637 U	0.000500 U	0.00120 U	0.000461 U	0.00154 U	**0.232 J**	0.000754 U	0.00111 U	0.000876 U	0.000909 U	0.000589 UJ

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
B-246 (continued)	B-246-75	5/11/18	PES	ESC	75	-35.1	S	0.00125 U	0.000664 U	0.000521 U	0.00125 U	0.000481 U	0.00161 U	0.000799 U	0.000786 U	0.00116 U	0.000913 U	0.000948 U	0.000614 U
	B-246-80	5/11/18	PES	ESC	80	-40.1	S	0.00122 U	0.000647 U	0.000508 U	0.00122 U	0.000469 U	0.00157 U	0.000779 U	0.000766 U	0.00113 U	0.000890 U	0.000924 U	0.000599 U
	B-926-100	5/11/18	PES	ESC	45 (dup)	-5.1	S	0.00162 U	0.000858 U	0.000673 U	0.00162 U	0.000621 U	0.00208 U	**0.0150 J**	0.00102 U	0.00150 U	0.00118 U	0.00122 U	0.000793 UJ
B-247	B-247-5	4/20/18	PES	ESC	5	34.7	S	0.000372 U	0.000241 U	0.000423 U	0.00107 U	0.000260 U	0.000426 U	**0.0478**	0.000297 U	0.000434 U	0.000288 U	0.000809 U	0.000337 U
	B-247-10	4/20/18	PES	ESC	10	29.7	S	0.000378 U	0.000244 U	0.000429 U	0.00109 U	0.000264 U	0.000432 U	**0.00459**	0.000302 U	0.000440 U	0.000292 U	0.000821 U	0.000342 U
	B-247-15	4/20/18	PES	ESC	15	24.7	S	0.000364 U	0.000235 U	0.000414 U	0.00105 U	0.000254 U	0.000416 U	**0.00577**	0.000291 U	0.000424 U	0.000282 U	0.000791 U	0.000329 U
	B-247-20	4/20/18	PES	ESC	20	19.7	S	0.000366 U	0.000237 U	0.000417 U	0.00106 U	0.000256 U	0.000419 U	**0.00682**	0.000293 U	0.000427 U	0.000284 U	0.000796 U	0.000332 U
	B-247-25	4/20/18	PES	ESC	25	14.7	S	0.000357 U	0.000231 U	0.000406 U	0.00103 U	0.000249 U	0.000408 U	**0.000271 J**	0.000285 U	0.000416 U	0.000276 U	0.000776 U	0.000323 U
	B-247-30	4/20/18	PES	ESC	30	9.7	S	0.000361 U	0.000234 U	0.000411 U	0.00104 U	0.000252 U	0.000413 U	**0.000409 J**	0.000289 U	0.000421 U	0.000280 U	0.000785 U	0.000327 U
	B-247-35	4/20/18	PES	ESC	35	4.7	S	0.000361 U	0.000234 U	0.000411 U	0.00104 U	0.000252 U	0.000413 U	**0.000430 J**	0.000289 U	0.000421 U	0.000280 U	0.000786 U	0.000327 U
	B-247-40	4/20/18	PES	ESC	40	-0.3	S	0.000368 U	0.000238 U	0.000419 U	0.00106 U	0.000257 U	**0.00157 J**	**0.00144**	0.000294 U	0.000429 U	0.000285 U	0.000801 U	0.000333 U
	B-247-45	4/20/18	PES	ESC	45	-5.3	S	0.000354 U	0.000229 U	0.000403 U	0.00102 U	0.000247 U	**0.00160 J**	**0.00979**	0.000283 U	0.000413 U	0.000274 U	0.000770 U	0.000321 U
	B-247-50	4/20/18	PES	ESC	50	-10.3	S	0.000361 U	0.000233 U	0.000411 U	0.00104 U	0.000252 U	0.000413 U	**4.71**	0.000288 U	0.000421 U	0.000280 U	0.000785 U	0.000327 U
	B-247-55	4/20/18	PES	ESC	55	-15.3	S	0.000371 U	0.000239 U	0.000421 U	0.00107 U	0.000259 U	0.000424 U	**0.0125**	0.000296 U	0.000432 U	0.000287 U	0.000805 U	0.000335 U
	B-247-60	4/20/18	PES	ESC	60	-20.3	S	0.000353 U	0.000228 U	0.000402 U	0.00102 U	0.000247 U	0.000404 U	**0.0754**	0.000282 U	0.000412 U	0.000274 U	0.000768 U	0.000320 U
	B-247-65	4/20/18	PES	ESC	65	-25.3	S	0.000366 U	0.000237 U	0.000416 U	0.00106 U	0.000255 U	0.000418 U	**0.00500**	0.000292 U	0.000426 U	0.000283 U	0.000795 U	0.000331 U
	B-247-70	4/20/18	PES	ESC	70	-30.3	S	0.000368 U	0.000238 U	0.000418 U	0.00106 U	0.000257 U	0.000420 U	**0.000306 J**	0.000294 U	0.000428 U	0.000285 U	0.000799 U	0.000333 U
	B-247-75	4/20/18	PES	ESC	75	-35.3	S	0.000375 U	0.000242 U	0.000427 U	0.00108 U	0.000262 U	0.000429 U	**0.00237**	0.000300 U	0.000437 U	0.000291 U	0.000816 U	0.000340 U
	B-247-80	4/20/18	PES	ESC	80	-40.3	S	0.000367 U	0.000237 U	0.000417 U	0.00106 U	0.000256 U	**0.000478 J**	**0.00249**	0.000293 U	0.000427 U	0.000284 U	0.000797 U	0.000332 U
	B-909-20	4/20/18	PES	ESC	80 (dup)	-40.3	S	0.000355 U	0.000229 U	0.000404 U	0.00102 U	0.000248 U	**0.00105 J**	**0.00164**	0.000284 U	0.000413 U	0.000275 U	0.000772 U	0.000321 U
B-248	B-248-5	4/23/18	PES	ESC	5	46.9	V	0.000374 U	0.000242 U	0.000426 U	0.00108 U	0.000261 U	0.000428 U	0.000268 U	0.000299 U	0.000436 U	0.000290 U	0.000814 U	0.000339 U
	B-248-10	4/23/18	PES	ESC	10	41.9	V	0.000366 U	0.000236 U	0.000416 U	0.00105 U	0.000255 U	0.000418 U	0.000511 U	0.000292 U	0.000426 U	0.000283 U	0.000795 U	0.000331 U
	B-248-15	4/23/18	PES	ESC	15	36.9	V	0.00119 U	0.000630 U	0.000495 U	0.00119 U	0.000456 U	0.00153 U	0.00113 U	0.000746 U	0.00110 U	0.000867 U	0.000900 U	0.000583 U
	B-248-20	4/23/18	PES	ESC	20	31.9	S	0.000355 U	0.000229 U	0.000403 U	0.00102 U	0.000248 U	0.000406 U	**0.00426 J+**	0.000283 U	0.000413 U	0.000275 U	0.000771 U	0.000321 U
	B-248-25	4/23/18	PES	ESC	25	26.9	S	0.00127 U	0.000672 U	0.000528 U	0.00127 U	0.000487 U	0.00163 U	**0.0426 J+**	0.000795 U	0.00117 U	0.000925 U	0.000960 U	0.000622 U
	B-248-30	4/23/18	PES	ESC	30	21.9	S	0.000355 U	0.000229 U	0.000403 U	0.00102 U	0.000248 U	0.000405 U	**0.00122**	0.000283 U	0.000413 U	0.000275 U	0.000771 U	0.000321 U
	B-248-35	4/23/18	PES	ESC	35	16.9	S	0.00117 U	0.000621 U	0.000487 U	0.00117 U	0.000450 U	0.00151 U	**0.142 J+**	0.000734 U	0.00108 U	0.000854 U	0.000886 U	0.000574 U
	B-248-40	4/23/18	PES	ESC	40	11.9	S	0.00120 U	0.000639 U	0.000502 U	0.00120 U	0.000463 U	0.00155 U	**0.0429 J+**	0.000756 U	0.00111 U	0.000879 U	0.000912 U	0.000591 U
	B-248-45	4/23/18	PES	ESC	45	6.9	S	0.00123 U	0.000654 U	0.000514 U	0.00123 U	0.000474 U	0.00159 U	**0.00492 J+**	0.000774 U	0.00114 U	0.000900 U	0.000934 U	0.000605 U
	B-248-50	4/23/18	PES	ESC	50	1.9	S	0.00118 U	0.000626 U	0.000492 U	0.00118 U	0.000454 U	0.00152 U	**0.00350 J+**	0.000741 U	0.00109 U	0.000862 U	0.000894 U	0.000579 UJ
	B-248-55	4/23/18	PES	ESC	55	-3.2	S	0.000388 U	0.000251 U	0.000441 U	0.00112 U	0.000271 U	0.000444 U	0.000278 U	0.000310 U	0.000452 U	0.000301 U	0.000844 U	0.000352 U
	B-248-60	4/23/18	PES	ESC	60	-8.2	S	0.00116 U	0.000614 U	0.000482 U	0.00116 U	0.000445 U	0.00149 U	**0.553 J+**	0.000727 U	0.00107 U	0.000845 U	0.000877 U	0.000568 U
	B-248-65	4/23/18	PES	ESC	65	-13.2	S	0.00133 U	0.000705 U	0.000554 U	0.00133 U	0.000510 U	0.00171 U	**0.0215 J+**	0.000834 U	0.00123 U	0.000969 U	0.00101 U	0.000652 U
	B-248-70	4/23/18	PES	ESC	70	-18.2	S	0.00124 U	0.000658 U	0.000517 U	0.00124 U	0.000477 U	0.00160 U	**0.00436 J+**	0.000779 U	0.00115 U	0.000906 U	0.000940 U	0.000609 U
	B-248-75	4/23/18	PES	ESC	75	-23.2	S	0.00121 U	0.000644 U	0.000505 U	0.00121 U	0.000466 U	0.00156 U	**0.136 J+**	0.000762 U	0.00112 U	0.000885 U	0.000919 U	0.00595 UJ
	B-248-80	4/23/18	PES	ESC	80	-28.2	S	0.000394 U	0.000255 U	0.000448 U	0.00114 U	0.000275 U	0.000451 U	**0.00448**	0.000315 U	0.000459 U	0.000305 U	0.000857 U	0.000357 U
	B-910-20	4/23/18	PES	ESC	80 (dup)	-28.2	S	0.000405 U	0.000262 U	0.000460 U	0.00117 U	0.000283 U	0.000463 U	0.000290 U	0.000323 U	0.000471 U	0.000313 U	0.000880 U	0.000367 U
	B-248-85	4/23/18	PES	ESC	85	-33.2	S	0.000398 U	0.000257 U	0.000453 U	0.00115 U	0.000278 U	0.000455 U	**0.00261**	0.000318 U	0.000464 U	0.000308 U	0.000866 U	0.000361 U
	B-248-90	4/23/18	PES	ESC	90	-38.2	S	0.000392 U	0.000254 U	0.000446 U	0.00113 U	0.000274 U	0.000449 U	**0.000415 J**	0.000313 U	0.000457 U	0.000304 U	0.000853 U	0.000355 U
	B-248-95	4/23/18	PES	ESC	95	-43.2	S	0.000409 U	0.000264 U	0.000465 U	0.00118 U	0.000286 U	0.000468 U	0.000293 U	0.000327 U	0.000476 U	0.000317 U	0.000889 U	0.000370 U
	B-248-100	4/23/18	PES	ESC	100	-48.2	S	0.000398 U	0.000257 U	0.000452 U	0.00115 U	0.000278 U	0.000455 U	**0.00541**	0.000318 U	0.000463 U	0.000308 U	0.000865 U	0.000360 U
	B-248-105	4/23/18	PES	ESC	105	-53.2	S	0.000354 U	0.000229 U	0.000403 U	0.00102 U	0.000247 U	0.000405 U	**0.00880**	0.000283 U	0.000413 U	0.000274 U	0.000770 U	0.000321 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
B-248	B-248-110	4/23/18	PES	ESC	110	-58.2	S	0.00124 U	0.000658 U	0.000516 U	0.00124 U	0.000476 U	0.00160 U	**0.00624 J+**	0.000778 U	0.00115 U	0.000904 U	0.000939 U	0.000608 U
(continued)	B-248-115	4/23/18	PES	ESC	115	-63.2	S	0.000383 U	0.000248 U	0.000436 U	0.00111 U	0.000268 U	0.000438 U	**0.00480**	0.000306 U	0.000447 U	0.000297 U	0.000834 U	0.000347 U
B-249	B-249-5	10/15/18	PES	PACE	5	34.2	S	0.00113 U	0.000599 U	0.000470 U	0.00113 U	**0.000568 J**	0.00145 U	**0.0102**	0.000709 U	0.00105 U	0.000823 U	0.000855 U	0.000554 U
	B-249-8	10/15/18	PES	PACE	8	31.2	S	0.00122 U	0.000647 U	0.000508 U	0.00122 U	**0.000675 J**	0.00157 U	**0.0287**	0.000765 U	0.00113 U	0.000889 U	0.000923 U	0.000598 U
	B-249-15	10/15/18	PES	PACE	15	24.2	S	0.00125 U	0.000664 U	0.000521 U	0.00125 U	**0.000777 J**	0.00161 U	**0.0692**	0.000785 U	0.00116 U	0.000913 U	0.000947 U	**0.00143 J**
	B-249-17	10/15/18	PES	PACE	17	22.2	S	0.00122 U	0.000649 U	0.000510 U	0.00122 U	**0.000636 J**	0.00157 U	**0.0459**	0.000768 U	0.00113 U	0.000892 U	0.000926 U	0.000600 U
	B-249-20	10/15/18	PES	PACE	20	19.2	S	0.00128 U	0.000677 U	0.000532 U	0.00128 U	0.000490 U	0.00164 U	**0.558**	0.000801 U	0.00118 U	0.000931 U	0.000966 U	0.000626 U
B-250	B-250-2.5	10/15/18	PES	PACE	2.5	36.9	V	0.00119 U	0.000633 U	0.000497 U	0.00119 U	**0.000710 J**	0.00153 U	0.00164 **J**	0.000749 U	0.00110 U	0.000870 U	0.000903 U	0.000585 U
	B-250-8	10/15/18	PES	PACE	8	31.4	S	0.00120 U	0.000638 U	0.000501 U	0.00120 U	0.000462 U	0.00155 U	0.00387	0.000755 U	0.00111 U	0.000877 U	0.000911 U	0.000590 U
	B-250-10	10/15/18	PES	PACE	10	29.4	S	0.00120 U	0.000637 U	0.000501 U	0.00120 U	**0.000645 J**	0.00155 U	**0.123**	0.000754 U	0.00111 U	0.000877 U	0.000910 U	0.000590 U
	B-250-13	10/15/18	PES	PACE	13	26.4	S	0.00121 U	0.000644 U	0.000505 U	0.00121 U	**0.000708 J**	0.00156 U	**0.288**	0.000762 U	0.00112 U	0.000885 U	0.000919 U	0.000595 U
	B-250-20	10/15/18	PES	PACE	20	19.4	S	0.00125 U	0.000664 U	0.000521 U	0.00125 U	**0.000752 J**	0.00161 U	**0.833**	0.000785 U	0.00116 U	0.000913 U	0.000947 U	0.000614 U
	B-250-24	10/15/18	PES	PACE	24	15.4	S	0.00118 U	0.000627 U	0.000492 U	0.00118 U	**0.000592**	0.00152 U	**0.614**	0.000742 U	0.00109 U	0.000862 U	0.000895 U	0.000580 U
	B-250-30	10/16/18	PES	PACE	30	9.4	S	0.00118 U	0.000625 U	0.000491 U	0.00118 U	0.000453 U	0.00152 U	**0.533**	0.000739 U	0.00109 U	0.000859 U	0.000892 U	**0.000590 J**
B-251	B-251-5	10/15/18	PES	PACE	5	34.3	S	0.00113 U	0.000602 U	0.000473 U	0.00113 U	**0.000670 J**	0.00146 U	**0.0153**	0.000712 U	0.00105 U	0.000828 U	0.000859 U	0.000557 U
	B-251-8	10/15/18	PES	PACE	8	31.3	S	0.00120 U	0.000636 U	0.000499 U	0.00120 U	**0.000707**	0.00154 U	**0.0879**	0.000752 U	0.00111 U	0.000874 U	0.000907 U	0.000588 U
	B-251-10	10/15/18	PES	PACE	10	29.3	S	0.00120 U	0.000637 U	0.000501 U	0.00120 U	**0.000940**	0.00155 U	**0.0191**	0.000754 U	0.00111 U	0.000877 U	0.000910 U	0.000590 U
	B-251-15	10/15/18	PES	PACE	15	24.3	S	0.00122 U	0.000648 U	0.000509 U	0.00122 U	**0.000654**	0.00157 U	**0.0366**	0.000767 U	0.00113 U	0.000891 U	0.000925 U	0.000599 U
	B-251-20	10/15/18	PES	PACE	20	19.3	S	0.00126 U	0.000671 U	0.000527 U	0.00126 U	**0.000952**	0.00163 U	**0.0474**	0.000794 U	0.00117 U	0.000923 U	0.000958 U	0.000621 U
	B-251-25	10/15/18	PES	PACE	25	14.3	S	0.00124 U	0.000658 U	0.000517 U	0.00124 U	**0.000767**	0.00160 U	**0.191**	0.000779 U	0.00115 U	0.000905 U	0.000940 U	0.000609 U
B-252	B-252-2.5	10/15/18	PES	PACE	2.5	36.7	V	0.00113 U	0.000599 U	0.000470 U	0.00113 U	**0.000887**	0.00145 U	**0.0146**	0.000708 U	0.00104 U	0.000823 U	0.000855 U	0.000554 U
	B-252-8	10/15/18	PES	PACE	8	31.2	S	0.00116 U	0.000613 U	0.000481 U	0.00116 U	0.000444 U	0.00149 U	**0.0312**	0.000725 U	0.00107 U	0.000843 U	0.000875 U	0.000567 U
	B-252-10	10/15/18	PES	PACE	10	29.2	S	0.00120 U	0.000635 U	0.000499 U	0.00120 U	**0.000808**	0.00154 U	**0.0600**	0.000752 U	0.00111 U	0.000874 U	0.000907 U	0.000588 U
	B-252-15	10/15/18	PES	PACE	15	24.2	S	0.00127 U	0.000675 U	0.000530 U	0.00127 U	**0.00130**	0.00164 U	**0.340**	0.000799 U	0.00118 U	0.000928 U	0.000964 U	0.000624 U
	B-252-19	10/15/18	PES	PACE	19	20.2	S	0.00130 U	0.000692 U	0.000543 U	0.00130 U	0.000501 U	0.00168 U	**1.36**	0.000818 U	0.00121 U	0.000951 U	0.000987 U	0.000640 U
	B-252-25	10/15/18	PES	PACE	25	14.2	S	0.00119 U	0.000629 U	0.000494 U	0.00119 U	0.000456 U	0.00153 U	**0.207**	0.000745 U	0.00110 U	0.000866 U	0.000898 U	0.000582 U
	B-252-29	10/15/18	PES	PACE	29	10.2	S	0.00124 U	0.000656 U	0.000515 U	0.00124 U	0.000475 U	0.00159 U	**0.484**	0.000776 U	0.00114 U	0.000902 U	0.000936 U	0.000606 U
B-253A	B-253A-5	10/18/18	PES	PACE	5	35.6	V	0.00123 U	0.000653 U	0.000512 U	0.00123 U	**0.00179**	0.00158 U	**0.0322**	0.000772 U	0.00114 U	0.000897 U	0.000932 U	0.000604 U
	B-253A-8	10/18/18	PES	PACE	8	32.6	S	0.00122 U	0.000645 U	0.000507 U	0.00122 U	**0.00162**	0.00157 U	**0.00584**	0.000764 U	0.00113 U	0.000887 U	0.000921 U	0.000597 U
	B-253A-10	10/18/18	PES	PACE	10	30.6	S	0.00118 U	0.000628 U	0.000493 U	0.00118 U	**0.00127**	0.00152 U	**0.00458**	0.000743 U	0.00110 U	0.000863 U	0.000896 U	0.000581 U
	B-253A-15	10/18/18	PES	PACE	15	25.6	S	0.00121 U	0.000643 U	0.000505 U	0.00121 U	**0.00111**	0.00156 U	**0.00229 J**	0.000761 U	0.00112 U	0.0707 U	0.000919 U	0.000595 U
	B-253A-20	10/18/18	PES	PACE	20	20.6	S	0.00119 U	0.000631 U	0.000496 U	0.00119 U	**0.00118**	0.00153 U	0.000760 U	0.000747 U	0.00110 U	0.000868 U	0.000901 U	0.000584 U
B-254	B-254-5	10/16/18	PES	PACE	5	34.7	S	0.00129 U	0.000686 U	0.000539 U	0.00129 U	0.000497 U	0.00166 U	**0.0425**	0.000812 U	0.00120 U	0.000944 U	0.0783 U	0.000635 UJ
	B-254-10	10/16/18	PES	PACE	10	29.7	S	0.00123 U	0.000651 U	0.000511 U	0.00123 U	0.000471 U	0.00158 U	**0.0251**	0.000770 U	0.00114 U	0.000895 U	0.00743 U	0.000602 UJ
	B-254-13.5	10/16/18	PES	PACE	13.5	26.2	S	0.00127 U	0.000672 U	0.000528 U	0.00127 U	0.000487 U	0.00163 U	**0.366**	0.000795 U	0.00117 U	0.000924 U	0.383 U	0.000622 UJ
	B-254-20	10/16/18	PES	PACE	20	19.7	S	0.00116 U	0.000616 U	0.000484 U	0.00116 U	0.000447 U	0.00150 U	**0.182**	0.000729 U	0.00108 U	0.000848 U	0.176 U	0.000570 UJ
	B-254-25	10/16/18	PES	PACE	25	14.7	S	0.00121 U	0.000640 U	0.000503 U	0.00121 U	0.000464 U	0.00155 U	**1.20**	0.000757 U	0.00112 U	0.000880 U	0.365 U	**0.000655 J**
B-254A	B-254A-27	10/19/18	PES	PACE	27	12.7	S	0.00118 U	0.000626 U	0.000491 U	0.00118 U	0.000453 U	0.00151 U	**0.165**	0.000741 U	0.00109 U	0.000861 U	0.000893 U	0.000578 U
	B-254A-30	10/19/18	PES	PACE	30	9.7	S	0.00116 U	0.000617 U	0.000484 U	0.00116 U	0.000447 U	0.00150 U	**0.0964**	0.000730 U	0.00108 U	0.000848 U	0.000880 U	0.000570 U
	B-254A-35	10/19/18	PES	PACE	35	4.7	S	0.00114 U	0.000604 U	0.000474 U	0.00114 U	**0.000575 J**	0.00146 U	**0.143 J**	0.000714 U	0.00105 U	0.000830 U	0.000862 U	0.000558 UJ
B-255	B-255-3.5	10/16/18	PES	PACE	3.5	36.3	S	0.00123 U	0.000654 U	0.000514 U	0.00123 U	0.000474 U	0.00159 U	**0.0101**	0.000774 U	0.00114 U	0.000900 U	0.000934 U	0.000605 UJ
	B-255-8	10/16/18	PES	PACE	8	31.8	S	0.00125 U	0.000664 U	0.000521 U	0.00125 U	0.000481 U	0.00161 U	**0.0118**	0.000786 U	0.00116 U	0.000913 U	0.000948 U	0.000614 UJ

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
B-255 (continued)	B-255-15	10/16/18	PES	PACE	15	24.8	S	0.00118 U	0.000624 U	0.000490 U	0.00118 U	0.000452 U	0.00151 U	**0.0294**	0.000739 U	0.00109 U	0.000859 U	0.000891 U	0.000577 UJ
B-255A	B-255A-21	10/16/18	PES	PACE	21	18.8	S	0.00114 U	0.000607 U	0.000476 U	0.00114 U	0.000439 U	0.00147 U	**2.74**	0.000718 U	0.00106 U	0.000834 U	0.0346 U	**0.000720 J**
B-256	B-256-2.5	10/16/18	PES	PACE	2.5	37.1	S	0.00126 U	0.000670 U	0.000526 U	0.00126 U	0.000485 U	0.00163 U	**0.0273**	0.000793 U	0.00117 U	0.000921 U	0.000957 U	0.000620 UJ
	B-256-5	10/16/18	PES	PACE	5	34.6	S	0.00119 U	0.000633 U	0.000497 U	0.00119 U	0.000458 U	0.00154 U	**0.0190**	0.000749 U	0.00110 U	0.000871 U	0.000904 U	0.000585 UJ
	B-256-10	10/16/18	PES	PACE	10	29.6	S	0.00115 U	0.000612 U	0.000481 U	0.00115 U	0.000443 U	0.00149 U	**0.548**	0.000724 U	0.00107 U	0.000842 U	0.000874 U	0.000566 UJ
	B-256-15	10/16/18	PES	PACE	15	24.6	S	0.00120 U	0.000634 U	0.000498 U	0.00120 U	0.000459 U	0.00154 U	**0.768**	0.000750 U	0.00111 U	0.000872 U	0.000905 U	0.000587 UJ
	B-256-18	10/16/18	PES	PACE	18	21.6	S	0.00120 U	0.000634 U	0.000498 U	0.00120 U	0.000459 U	0.00154 U	**0.143**	0.000750 U	0.00111 U	0.000872 U	0.000905 U	0.000586 UJ
B-257	B-257-5	10/17/18	PES	PACE	5	34.4	S	0.00131 U	0.000694 U	0.000545 U	0.00131 U	0.000502 U	0.00168 U	**0.0699**	0.000821 U	0.00121 U	0.000954 U	0.000990 U	0.000642 UJ
	B-257-10	10/17/18	PES	PACE	10	29.4	S	0.00121 U	0.000640 U	0.000502 U	0.00121 U	0.000463 U	0.00155 U	**0.481**	0.000757 U	0.00112 U	0.000880 U	0.000913 U	0.000592 UJ
	B-257-15	10/17/18	PES	PACE	15	24.4	S	0.00125 U	0.000666 U	0.000523 U	0.00125 U	0.000482 U	0.00161 U	**0.364**	0.000788 U	0.00116 U	0.000915 U	0.000950 U	0.000616 UJ
	B-257-20	10/17/18	PES	PACE	20	19.4	S	0.00121 U	0.000644 U	0.000506 U	0.00121 U	0.000466 U	0.00156 U	**1.67**	0.000762 U	0.00112 U	0.000886 U	0.00735 U	0.000596 UJ
B-258	B-258-3	10/17/18	PES	PACE	3	36.2	V	0.00118 U	0.000628 U	0.000493 U	0.00118 U	**0.00130 J**	0.00152 U	**0.0116**	0.000743 U	0.00110 U	0.000863 U	0.000896 U	0.000581 UJ
	B-258-8	10/17/18	PES	PACE	8	31.2	S	0.00123 U	0.000652 U	0.000512 U	0.00123 U	**0.00166**	0.00158 U	**0.00236 J**	0.000771 U	0.00114 U	0.000896 U	0.000930 U	0.000603 U
	B-258-10	10/17/18	PES	PACE	10	29.2	S	0.00129 U	0.000686 U	0.000538 U	0.00129 U	**0.00168**	0.00166 U	**0.00481**	0.000811 U	0.00120 U	0.000943 U	0.000979 U	0.000634 U
	B-258-15	10/17/18	PES	PACE	15	24.2	S	0.00127 U	0.000676 U	0.000531 U	0.00127 U	**0.00158**	0.00164 U	**0.0119**	0.000800 U	0.00118 U	0.000930 U	0.000965 U	0.000625 U
	B-258-20	10/17/18	PES	PACE	20	19.2	S	0.00121 U	0.000640 U	0.000502 U	0.00121 U	**0.00141**	0.00155 U	**0.0135**	0.000757 U	0.00112 U	0.000879 U	0.000913 U	0.000592 U
B-259	B-259-2.5	10/17/18	PES	PACE	2.5	36.7	V	0.00122 U	0.000645 U	0.000506 U	0.00122 U	**0.00211**	0.00156 U	**0.00815**	0.000763 U	0.00113 U	0.000887 U	0.000921 U	0.000597 U
	B-259-5	10/17/18	PES	PACE	5	34.2	S	0.00118 U	0.000628 U	0.000493 U	0.00118 U	**0.00140**	0.00152 U	**0.0696**	0.000743 U	0.00110 U	0.000864 U	0.000896 U	0.000581 U
	B-259-10	10/17/18	PES	PACE	10	29.2	S	0.00124 U	0.000657 U	0.000516 U	0.00124 U	**0.00244**	0.00159 U	**0.105**	0.000777 U	0.00115 U	0.000903 U	0.000937 U	0.000607 U
	B-259-15	10/17/18	PES	PACE	15	24.2	S	0.00127 U	0.000673 U	0.000528 U	0.00127 U	**0.00189**	0.00163 U	**0.715**	0.000796 U	0.00117 U	0.000925 U	0.000960 U	0.000622 U
	B-259-20	10/17/18	PES	PACE	20	19.2	S	0.00121 U	0.000640 U	0.000503 U	0.00121 U	**0.00179**	0.00155 U	**0.718**	0.000758 U	0.00112 U	0.000881 U	0.000914 U	0.000592 U
B-260	B-260-5	10/17/18	PES	PACE	5	34.2	S	0.00120 U	0.000635 U	0.000499 U	0.00120 U	**0.00189**	0.00154 U	**0.0185**	0.000752 U	0.00111 U	0.000874 U	0.000907 U	0.000588 U
	B-260-8	10/17/18	PES	PACE	8	31.2	S	0.00121 U	0.000643 U	0.000505 U	0.00121 U	**0.00206**	0.00156 U	**0.142**	0.000761 U	0.00112 U	0.000884 U	0.000918 U	0.000595 U
	B-260-10	10/17/18	PES	PACE	10	29.2	S	0.00124 U	0.000658 U	0.000516 U	0.00124 U	**0.00159**	0.00160 U	**0.568**	0.000778 U	0.00115 U	0.000904 U	0.000939 U	0.000608 U
	B-260-15	10/17/18	PES	PACE	15	24.2	S	0.00125 U	0.000665 U	0.000523 U	0.00125 U	**0.00183**	0.00161 U	**0.414**	**0.000791 J**	0.00116 U	0.000915 U	0.000950 U	0.000615 U
	B-260-20	10/17/18	PES	PACE	20	19.2	S	0.00119 U	0.000633 U	0.000497 U	0.00119 U	**0.00166**	0.00154 U	**0.588**	0.000749 U	0.00111 U	0.000871 U	0.000904 U	0.000586 U
B-261	B-261-3	10/17/18	PES	PACE	3	36.9	S	0.00123 U	0.000655 U	0.000514 U	0.00123 U	**0.00165**	0.00159 U	**0.00244 J**	0.000775 U	0.00114 U	0.000900 U	0.000935 U	0.000606 U
	B-261-5	10/17/18	PES	PACE	5	34.9	S	0.00122 U	0.000649 U	0.000510 U	0.00122 U	**0.00170**	0.00157 U	**0.00255 J**	0.000768 U	0.00113 U	0.000892 U	0.000926 U	0.000600 U
	B-261-8	10/17/18	PES	PACE	8	31.9	S	0.00129 U	0.000687 U	0.000539 U	0.00129 U	**0.00196**	0.00167 U	**0.00234 J**	0.000812 U	0.00120 U	0.000944 U	0.000980 U	0.000635 U
	B-261-10	10/17/18	PES	PACE	10	29.9	S	0.00124 U	0.000660 U	**0.000554 J**	0.00124 U	**0.00198**	0.00160 U	**0.00359**	0.000781 U	0.00115 U	0.000908 U	0.000943 U	0.000611 U
	B-261-15	10/17/18	PES	PACE	15	24.9	S	0.00119 U	0.000630 U	0.000494 U	0.00119 U	**0.00171**	0.00153 U	**0.00353**	0.000745 U	0.00110 U	0.000866 U	0.000899 U	0.000582 U
	B-261-20	10/17/18	PES	PACE	20	19.9	S	0.00121 U	0.000644 U	**0.000852 J**	0.00121 U	**0.00214**	0.00156 U	**0.105**	0.000762 U	0.00112 U	0.000886 U	0.000919 U	**0.000806 J**
B-262	B-262-5	10/17/18	PES	PACE	5	34.9	S	0.00127 U	0.000675 U	0.000530 U	0.00127 U	**0.00115**	0.00164 U	0.0650 U	0.000799 U	0.00118 U	0.000928 U	0.0770 U	**0.00214 J**
	B-262-8	10/17/18	PES	PACE	8	31.9	S	0.00119 U	0.000630 U	0.000495 U	0.00119 U	0.000456 U	0.00153 U	**0.00981**	0.000746 U	0.00110 U	0.000867 U	0.000900 U	0.000583 U
	B-262-10	10/17/18	PES	PACE	10	29.9	S	0.00120 U	0.000638 U	0.000501 U	0.00120 U	**0.00103**	0.00155 U	**0.00190 J**	0.000755 U	0.00111 U	0.000878 U	0.000911 U	0.000590 U
	B-262-15	10/17/18	PES	PACE	15	24.9	S	0.00119 U	0.000629 U	0.000494 U	0.00119 U	0.000455 U	0.00153 U	**0.00332**	0.000744 U	0.00110 U	0.000865 U	0.000898 U	0.000582 U
	B-262-20	10/17/18	PES	PACE	20	19.9	S	0.00127 U	0.000675 U	0.000530 U	0.00127 U	**0.00116**	0.00164 U	**0.0429**	0.000798 U	0.00118 U	0.000928 U	0.00963 U	0.000624 U
B-263	B-263-3	10/18/18	PES	PACE	3	36.8	S	0.00132 U	0.000702 U	0.000551 U	0.00132 U	**0.00110**	0.00170 U	**0.00113 J**	0.000830 U	0.00122 U	0.000965 U	0.00100 U	0.000649 U
	B-263-5	10/18/18	PES	PACE	5	34.8	S	0.00117 U	0.000619 U	0.000486 U	0.00117 U	0.000448 U	0.00150 U	**0.0164**	0.000733 U	0.00108 U	0.000852 U	0.000884 U	0.000573 U
	B-263-8	10/18/18	PES	PACE	8	31.8	S	0.00114 U	0.000604 U	0.000475 U	0.00114 U	**0.00135**	0.00147 U	**0.0277**	0.000715 U	0.00105 U	0.000831 U	0.000863 U	0.000559 U
	B-263-10	10/18/18	PES	PACE	10	29.8	S	0.00123 U	0.000652 U	0.000512 U	0.00123 U	0.000472 U	0.00158 U	0.000785 U	0.000772 U	0.00114 U	0.000897 U	0.000931 U	0.000603 U
	B-263-15	10/18/18	PES	PACE	15	24.8	S	0.00118 U	0.000625 U	0.000491 U	0.00118 U	0.000453 U	0.00152 U	**0.0170**	0.000740 U	0.00109 U	0.000860 U	0.000893 U	0.000579 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
B-263 (continued)	B-263-18	10/18/18	PES	PACE	18	21.8	S	0.00117 U	0.000622 U	0.000488 U	0.00117 U	0.000450 U	0.00151 U	**0.0894**	0.000736 U	0.00108 U	0.000855 U	0.000887 U	0.000575 U
B-264	B-264-3	10/18/18	PES	PACE	3	36.8	S	0.00117 U	0.000622 U	0.000489 U	0.00117 U	0.000451 U	0.00151 U	0.000749 U	0.000736 U	0.00109 U	0.000856 U	0.000888 U	0.000576 U
	B-264-5	10/18/18	PES	PACE	5	34.8	S	0.00125 U	0.000663 U	0.000521 U	0.00125 U	0.000480 U	0.00161 U	0.000799 U	0.000785 U	0.00116 U	0.000912 U	0.000947 U	0.000613 U
	B-264-8	10/18/18	PES	PACE	8	31.8	S	0.00123 U	0.000655 U	0.000514 U	0.00123 U	**0.00122**	0.00159 U	0.000789 U	0.000775 U	0.00114 U	0.000901 U	0.000935 U	0.000606 U
	B-264-10	10/18/18	PES	PACE	10	29.8	S	0.00119 U	0.000631 U	0.000496 U	0.00119 U	0.000457 U	0.00153 U	0.000760 U	0.000747 U	0.00110 U	0.000868 U	0.000901 U	0.000584 U
	B-264-15	10/18/18	PES	PACE	15	24.8	S	0.00126 U	0.000667 U	0.000524 U	0.00126 U	**0.00152**	0.00162 U	**0.000940 J**	0.000789 U	0.00116 U	0.000917 U	0.000952 U	0.000617 U
	B-264-16	10/18/18	PES	PACE	16	23.8	S	0.00121 U	0.000643 U	0.000505 U	0.00121 U	**0.00127**	0.00156 U	**0.00250 J**	0.000761 U	0.00112 U	0.000885 U	0.000918 U	0.000595 U
B-265	B-265-3	10/18/18	PES	PACE	3	36.8	S	0.00129 U	0.000684 U	0.000537 U	0.00129 U	**0.00162**	0.00166 U	**0.00118 J**	0.000809 U	0.00119 U	0.000940 U	0.000976 U	0.000632 U
	B-265-5	10/18/18	PES	PACE	5	34.8	S	0.00125 U	0.000664 U	0.000521 U	0.00125 U	**0.00111**	0.00161 U	**0.00391**	0.000786 U	0.00116 U	0.000913 U	0.000948 U	0.000614 U
	B-265-8	10/18/18	PES	PACE	8	31.8	S	0.00121 U	0.000640 U	0.000502 U	0.00121 U	**0.00104**	0.00155 U	**0.00354**	0.000757 U	0.00112 U	0.000880 U	0.000913 U	0.000592 U
	B-265-10	10/18/18	PES	PACE	10	29.8	S	0.00119 U	0.000630 U	0.000495 U	0.00119 U	**0.00127**	0.00153 U	**0.00135 J**	0.000745 U	0.00110 U	0.000866 U	0.000899 U	0.000583 U
	B-265-17.5	10/18/18	PES	PACE	18	22.3	S	0.00119 U	0.000634 U	0.000498 U	0.00119 U	**0.000779**	0.00154 U	0.000763 U	0.000750 U	0.00111 U	0.000872 U	0.000905 U	0.000586 U
B-266	B-266-5	10/18/18	PES	PACE	5	35.7	S	0.00132 U	0.000698 U	0.000548 U	0.00132 U	**0.00119**	0.00169 U	**0.00515**	0.000826 U	0.00122 U	0.000960 U	0.000997 U	0.000646 U
	B-266-8	10/18/18	PES	PACE	8	32.7	S	0.00137 U	0.000729 U	0.000573 U	0.00137 U	**0.00156**	0.00176 U	**0.00854**	0.000863 U	0.00127 U	0.00100 U	0.00104 U	0.000675 U
	B-266-10	10/18/18	PES	PACE	10	30.7	S	0.00173 U	0.000922 U	0.000724 U	0.00173 U	**0.00180**	0.00224 U	**0.00620**	0.00109 U	0.00161 U	0.00127 U	0.00131 U	0.000853 U
	B-266-15	10/18/18	PES	PACE	15	25.7	S	0.00144 U	0.000765 U	0.000600 U	0.00144 U	**0.00182**	0.00185 U	0.000920 U	0.000904 U	0.00133 U	0.00105 U	0.00109 U	0.000707 U
	B-266-20	10/18/18	PES	PACE	20	20.7	S	0.00120 U	0.000639 U	0.000502 U	0.00120 U	**0.00109**	0.00155 U	**0.0195**	0.000756 U	0.00111 U	0.000878 U	0.000912 U	0.000591 U
B-267	B-267-2.5	10/18/18	PES	PACE	2.5	37.4	S	0.00130 U	0.000689 U	0.000541 U	0.00130 U	**0.00132**	0.00167 U	0.000829 U	0.000815 U	0.00120 U	0.000947 U	0.000983 U	0.000637 U
	B-267-5	10/18/18	PES	PACE	5	34.9	S	0.00118 U	0.000625 U	0.000491 U	0.00118 U	**0.00101**	0.00152 U	0.000753 U	0.000740 U	0.00109 U	0.000859 U	0.000892 U	0.000578 U
	B-267-8	10/18/18	PES	PACE	8	31.9	S	0.00129 U	0.000684 U	0.000537 U	0.00129 U	**0.00112**	0.00166 U	0.000823 U	0.000809 U	0.00119 U	0.000940 U	0.000976 U	0.000632 U
	B-267-10	10/18/18	PES	PACE	10	29.9	S	0.00122 U	0.000648 U	0.000509 U	0.00122 U	**0.00153**	0.00157 U	0.000780 U	0.000766 U	0.00113 U	0.000891 U	0.000925 U	0.000599 U
	B-267-15	10/18/18	PES	PACE	15	24.9	S	0.0241 U	0.0129 U	0.0101 U	0.0241 U	0.00928 U	0.0311 U	0.0154 U	0.0152 U	0.0224 U	0.0177 U	0.0183 U	0.0118 U
	B-267-20	10/18/18	PES	PACE	20	19.9	S	0.0268 U	0.0142 U	0.0112 U	0.0268 U	0.0103 U	0.0345 U	0.0171 U	0.0169 U	0.0248 U	0.0196 U	0.0203 U	0.0132 U
CA-A10	CA-A10-21	09/04/19	PES	Fremont	21	–	S	–	–	–	–	–	–	**0.427**	–	–	–	–	–
CA-A12-20	CA-A12-20-24	09/06/19	PES	Fremont	24	–	S	–	–	–	–	–	–	**2.41**	–	–	–	–	–
CAA-C1	CAA-C1-43	08/27/19	PES	Fremont	43	–	S	–	–	–	–	–	–	0.209 U	–	–	–	–	–
CAA-C2	CAA-C2-10	08/28/19	PES	Fremont	10	–	S	–	–	–	–	–	–	0.222 U	–	–	–	–	–
CA-B8	CA-B8-3	09/16/19	PES	Fremont	3	–	S	–	–	–	–	–	–	0.232 U	–	–	–	–	–
CA-B19	CA-B19-30	09/27/19	PES	Fremont	30	–	S	–	–	–	–	–	–		–	–	–	–	–
CA-B10	CA-B10-17	08/30/19	PES	Fremont	17	–	S	–	–	–	–	–	–	0.191 U	–	–	–	–	–
	CA-B10-20	08/30/19	PES	Fremont	20	–	S	–	–	–	–	–	–	**3.26**	–	–	–	–	–
	CA-B10-21	08/30/19	PES	Fremont	21	–	S	–	–	–	–	–	–	**0.168 J**	–	–	–	–	–
	CA-B10-25	08/30/19	PES	Fremont	25	–	S	–	–	–	–	–	–	0.176 U	–	–	–	–	–
CA-B11	CA-B11-27	09/05/19	PES	Fremont	27	–	S	–	–	–	–	–	–	**0.270**	–	–	–	–	–
CA-B18	CA-B18-20	10/26/19	PES	Fremont	20	–	S	–	–	–	–	–	–	**2.41**	–	–	–	–	–
CA-B20	CA-B20-31	09/30/19	PES	Fremont	31	–	S	–	–	–	–	–	–	0.186 U	–	–	–	–	–
	B-1001-31	09/30/19	PES	Fremont	31 (dup)	–	S	–	–	–	–	–	–	0.203 U	–	–	–	–	–
CA-C7	CA-C7-25	09/20/19	PES	Fremont	25	–	S	–	–	–	–	–	–	0.198 U	–	–	–	–	–
CA-C8	CA-C8-35	09/03/19	PES	Fremont	35	–	S	–	–	–	–	–	–	0.167 U	–	–	–	–	–
CA-C9	CA-C9-09	09/04/19	PES	Fremont	9	–	S	–	–	–	–	–	–	0.177 U	–	–	–	–	–
CA-C10	CA-C10-17	09/06/19	PES	Fremont	17	–	S	–	–	–	–	–	–	**2.86**	–	–	–	–	–
	CA-C10-26	09/06/19	PES	Fremont	26	–	S	–	–	–	–	–	–	0.233 U	–	–	–	–	–
CA-C13	CA-C13-Comp	09/11/19	PES	Fremont	Comp	–	S	–	–	–	–	–	–	0.232 U	–	–	–	–	–
CA-D1	CA-D1-Comp	09/11/19	PES	Fremont	Comp	–	S	–	–	–	–	–	–	0.208 U	–	–	–	–	–
CA-D2	CA-D2-31	09/16/19	PES	Fremont	31	–	S	–	–	–	–	–	–	0.202 U	–	–	–	–	–
	CA-D2-50-52	09/17/19	PES	Fremont	52	–	S	–	–	–	–	–	–	0.224 U	–	–	–	–	–
CA-D3	CA-D3-40	09/23/19	PES	Fremont	40	–	S	–	–	–	–	–	–	**0.240**	–	–	–	–	–
CA-D4	CA-D4-51	09/19/19	PES	Fremont	51	–	S	–	–	–	–	–	–	0.251 U	–	–	–	–	–
	CA-D4-54	09/19/19	PES	Fremont	54	–	S	–	–	–	–	–	–	**0.121 J**	–	–	–	–	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	**–**	**0.074**	**–**	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	**–**	**0.007**	**–**	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
CA-D5	CA-D5-14	09/03/19	PES	Fremont	14	–	S	–	–	–	–	–	–	0.177 U	–	–	–	–	–
	CA-D5-22	09/03/19	PES	Fremont	22	–	S	–	–	–	–	–	–	**1.49**	–	–	–	–	–
	CA-D5-26	09/03/19	PES	Fremont	26	–	S	–	–	–	–	–	–	**0.646**	–	–	–	–	–
CA-D6	CA-D6-56	09/04/19	PES	Fremont	56	–	S	–	–	–	–	–	–	**0.173 J**	–	–	–	–	–
	CA-D6-65	09/04/19	PES	Fremont	65	–	S	–	–	–	–	–	–	**1.32**	–	–	–	–	–
CA-D7	CA-D7-15	09/05/19	PES	Fremont	15	–	S	–	–	–	–	–	–	**0.744**	–	–	–	–	–
DB01	DB01-10	3/18/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB01-20	3/18/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB01-30	3/18/13	SES	F&BI	30	10.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB01-40	3/18/13	SES	F&BI	40	0.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
DB02	DB02-10	3/18/13	SES	F&BI	10	26.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	0.020 U
	DB02-15	3/18/13	SES	F&BI	15	21.0	S	–	–	–	–	–	–	–	–	–	–	–	0.020 U
	DB02-20	3/18/13	SES	F&BI	20	16.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB02-30	3/18/13	SES	F&BI	30	6.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB02-40	3/18/13	SES	F&BI	40	-4.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
DB03	DB03-05	3/27/13	SES	F&BI	5	35.0	S	–	–	–	–	–	–	0.10 U	–	–	–	–	–
	DB03-20	3/27/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB03-35	3/27/13	SES	F&BI	35	5.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB03-45	3/27/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB03-55	3/27/13	SES	F&BI	55	-15.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB03-60	3/27/13	SES	F&BI	60	-20.0	S	–	–	–	–	–	–	**0.15**	–	–	–	–	–
DB04	DB04-10	3/21/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB04-20	3/21/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB04-35	3/21/13	SES	F&BI	35	5.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB04-45	3/21/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB04-50	3/22/13	SES	F&BI	50	-10.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB04-60	3/22/13	SES	F&BI	60	-20.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
DB05	DB05-10	3/26/13	SES	F&BI	10	41.8	V	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB05-20	3/26/13	SES	F&BI	20	31.8	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB05-30	3/26/13	SES	F&BI	30	21.8	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB05-40	3/26/13	SES	F&BI	40	11.8	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB05-50	3/26/13	SES	F&BI	50	1.8	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB05-60	3/26/13	SES	F&BI	60	-8.2	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB05-70	3/26/13	SES	F&BI	70	-18.2	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
DB06	DB06-10	3/25/13	SES	F&BI	10	41.8	V	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB06-25	3/25/13	SES	F&BI	25	26.8	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB06-35	3/25/13	SES	F&BI	35	16.8	S	–	–	–	–	–	–	**0.096**	–	–	–	–	–
	DB06-45	3/25/13	SES	F&BI	45	6.8	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB06-55	3/25/13	SES	F&BI	55	-3.2	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB06-65	3/25/13	SES	F&BI	65	-13.2	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB06-75	3/25/13	SES	F&BI	75	-23.2	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
DB07	DB07-05	3/27/13	SES	F&BI	5	35.0	S	–	–	–	–	–	–	**0.076**	–	–	–	–	–
	DB07-15	3/27/13	SES	F&BI	15	25.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB07-25	3/27/13	SES	F&BI	25	15.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB07-35	3/28/13	SES	F&BI	35	5.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB07-45	3/28/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB07-50	3/28/13	SES	F&BI	50	-10.0	S	–	–	–	–	–	–	**0.16**	–	–	–	–	–
	DB07-60	3/28/13	SES	F&BI	60	-20.0	S	–	–	–	–	–	–	**0.53**	–	–	–	–	–
	DB07-70	3/28/13	SES	F&BI	70	-30.0	S	–	–	–	–	–	–	**0.41**	–	–	–	–	–
DB08	DB08-10	3/20/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB08-20	3/20/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	**0.097**	–	–	–	–	–
	DB08-35	3/20/13	SES	F&BI	35	5.0	S	–	–	–	–	–	–	**0.94**	–	–	–	–	–
	DB08-45	3/20/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB08-50	3/21/13	SES	F&BI	50	-10.0	S	–	–	–	–	–	–	**0.070**	–	–	–	–	–
	DB08-60	3/21/13	SES	F&BI	60	-20.0	S	–	–	–	–	–	–	**0.080**	–	–	–	–	–
	DB08-70	3/21/13	SES	F&BI	70	-30.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
DB09	DB09-10	3/19/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB09-20	3/19/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB09-30	3/19/13	SES	F&BI	30	10.0	S	–	–	–	–	–	–	**0.25**	–	–	–	–	–
	DB09-40	3/19/13	SES	F&BI	40	0.0	S	–	–	–	–	–	–	**0.18**	–	–	–	–	–
	DB09-50	3/19/13	SES	F&BI	50	-10.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB09-60	3/19/13	SES	F&BI	60	-20.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB09-70	3/19/13	SES	F&BI	70	-30.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
DB10	DB10-10	3/29/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB10-20	3/29/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB10-35	3/29/13	SES	F&BI	35	5.0	S	–	–	–	–	–	–	0.50 U	–	–	–	–	–
	DB10-45	3/29/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	0.50 U	–	–	–	–	–
	DB10-50	4/1/13	SES	F&BI	50	-10.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB10-60	4/1/13	SES	F&BI	60	-20.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB10-70	4/1/13	SES	F&BI	70	-30.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
DB11	DB11-15	4/2/13	SES	F&BI	15	36.8	V	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB11-25	4/2/13	SES	F&BI	25	26.8	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB11-35	4/2/13	SES	F&BI	35	16.8	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB11-45	4/2/13	SES	F&BI	45	6.8	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB11-55	4/2/13	SES	F&BI	55	-3.2	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
DB12	DB12-10	4/3/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB12-20	4/3/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	**1.6**	–	–	–	–	–
	DB12-30	4/3/13	SES	F&BI	30	10.0	S	–	–	–	–	–	–	**0.052**	–	–	–	–	–
	DB12-40	4/3/13	SES	F&BI	40	0.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
DB13	DB13-10	4/3/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB13-20	4/3/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	DB13-35	4/3/13	SES	F&BI	35	5.0	S	–	–	–	–	–	–	**0.063**	–	–	–	–	–
	DB13-45	4/3/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	**–**	**0.074**	**–**	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	**–**	**0.007**	**–**	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
DB14	DB14-10	4/4/13	SES	F&BI	10	31.5	S	–	–	–	–	–	–	0.050 U	–	–	–	–	**1.2**
	DB14-20	4/4/13	SES	F&BI	20	21.5	S	–	–	–	–	–	–	0.050 U	–	–	–	–	**0.29**
	DB14-30	4/4/13	SES	F&BI	30	11.5	S	–	–	–	–	–	–	0.050 U	–	–	–	–	**–**
	DB14-40	4/4/13	SES	F&BI	40	1.5	S	–	–	–	–	–	–	**0.077**	–	–	–	–	**–**
G-MW1	MW 1-3-8	7/20/01	GeoEng	NCA	8	31.0	S	–	–	–	–	–	–	0.026 U	–	–	–	–	0.019 U
	MW 1-8-20	7/20/01	GeoEng	NCA	20	19.0	S	–	–	–	–	–	–	0.026 U	–	–	–	–	0.019 U
	MW 1-11-27.5	7/20/01	GeoEng	NCA	27.5	11.5	S	–	–	–	–	–	–	0.026 U	–	–	–	–	0.019 U
	MW 1-13-32.5	7/20/01	GeoEng	NCA	32.5	6.5	S	–	–	–	–	–	–	0.052 U	–	–	–	–	0.038 U
	MW 1-15-37.5	7/20/01	GeoEng	NCA	37.5	1.5	S	–	–	–	–	–	–	0.026 U	–	–	–	–	0.019 U
G-MW3 (G-SB4 11)	SB4-4-10	7/20/01	GeoEng	NCA	10	29.6	S	–	–	–	–	–	–	0.026 U	–	–	–	–	0.019 U
	SB4-7-17.5	7/20/01	GeoEng	NCA	17.5	22.1	S	–	–	–	–	–	–	0.026 U	–	–	–	–	0.019 U
	SB4-13-32.5	7/20/01	GeoEng	NCA	32.5	7.1	S	–	–	–	–	–	–	0.026 U	–	–	–	–	0.019 U
	SB4-15-37.5	7/20/01	GeoEng	NCA	37.5	2.1	S	–	–	–	–	–	–	0.026 U	–	–	–	–	0.019 U
IW06	IW06-25	1/15/16	SES	F&BI	25	26.8	S	–	–	–	–	–	–	0.005 U	–	–	–	–	**–**
	IW06-30	1/15/16	SES	F&BI	30	21.8	S	–	–	–	–	–	–	0.005 U	–	–	–	–	**–**
	IW06-40	1/15/16	SES	F&BI	40	11.8	S	–	–	–	–	–	–	0.005 U	–	–	–	–	**–**
	IW06-50	1/15/16	SES	F&BI	50	1.8	S	–	–	–	–	–	–	0.005 U	–	–	–	–	**–**
	IW06-55	1/15/16	SES	F&BI	55	-3.2	S	–	–	–	–	–	–	0.005 U	–	–	–	–	**–**
	IW06-60	1/15/16	SES	F&BI	60	-8.2	S	–	–	–	–	–	–	**0.0061**	–	–	–	–	**–**
	IW06-65	1/15/16	SES	F&BI	65	-13.2	S	–	–	–	–	–	–	0.005 U	–	–	–	–	**–**
	IW06-70	1/15/16	SES	F&BI	70	-18.2	S	–	–	–	–	–	–	0.005 U	–	–	–	–	**–**
	IW06-75	1/15/16	SES	F&BI	75	-23.2	S	–	–	–	–	–	–	0.005 UJ	–	–	–	–	**–**
IW-1C (-23.9 to-38.9)	IW-1C-5	3/7/18	PES	ESC	5	34.1	S	0.000364 U	0.000236 U	0.000414 U	0.00105 U	0.000254 U	0.000417 U	**0.00291**	0.000291 U	0.000424 U	0.000282 U	0.000792 U	0.000330 U
	IW-1C-15	3/7/18	PES	ESC	15	24.1	S	0.000385 U	0.000249 U	0.000438 U	0.00111 U	0.000269 U	0.000440 U	**0.00154**	0.000308 U	0.000449 U	0.000298 U	0.000837 U	0.000349 U
	IW-1C-25	3/7/18	PES	ESC	25	14.1	S	0.0779 U	0.0504 U	0.0886 U	0.224 U	0.0544 U	0.0891 U	**0.769**	0.0622 U	0.0907 U	0.0603 U	0.170 U	0.0705 U
	IW-1C-35	3/7/18	PES	ESC	35	4.1	S	0.000352 U	0.000227 U	0.000400 U	**0.00270 J**	0.000246 U	0.000402 U	**0.404**	0.000281 U	0.000410 U	0.000272 U	0.000765 U	0.000319 U
	IW-1C-45	3/7/18	PES	ESC	45	-5.9	S	0.000367 U	0.000237 U	0.000418 U	0.00106 U	**0.000576 J**	0.000420 U	**0.153**	0.000293 U	0.000428 U	0.000284 U	0.000798 U	0.000332 U
	IW-1C-55	3/7/18	PES	ESC	55	-15.9	S	0.000367 U	0.000237 U	0.000418 U	0.00106 U	0.000256 U	0.000420 U	**0.324**	0.000293 U	0.000428 U	0.000284 U	0.000798 U	0.000333 U
	IW-1C-65	3/7/18	PES	ESC	65	-25.9	S	0.000377 U	0.000244 U	0.000429 U	0.00109 U	0.000263 U	0.000431 U	**0.000953 J**	0.000301 U	0.000439 U	0.000292 U	0.000819 U	0.000341 U
	IW-1C-75	3/7/18	PES	ESC	75	-35.9	S	0.000395 U	0.000255 U	0.000449 U	0.00114 U	**0.00114 J**	0.000451 U	**0.00329**	0.000315 U	0.000459 U	0.000306 U	0.000858 U	0.000357 U
IW-2C (-24.8 to-39.8)	IW-2C-5	3/7/18	PES	ESC	5	31.3	S	0.000405 U	0.000262 U	0.000461 U	0.00117 U	0.000283 U	0.000463 U	**0.00860**	0.000324 U	0.000472 U	0.000314 U	0.000881 U	0.000367 U
	IW-2C-15	3/7/18	PES	ESC	15	21.3	S	0.000392 U	0.000253 U	0.000446 U	0.00113 U	0.000274 U	0.000448 U	**0.000795 J**	0.000313 U	0.000456 U	0.000303 U	0.000852 U	0.000355 U
	IW-2C-25	3/7/18	PES	ESC	25	11.3	S	0.000366 U	0.000237 U	0.000417 U	0.00106 U	0.000256 U	0.000419 U	**0.304**	0.000293 U	0.000427 U	0.000284 U	0.000796 U	0.000332 U
	IW-2C-35	3/7/18	PES	ESC	35	1.3	S	0.000413 U	0.000267 U	0.000470 U	0.00119 U	0.000288 U	0.000472 U	**0.0708**	0.000330 U	0.000481 U	0.000320 U	0.000898 U	0.000374 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
IW-2C (continued)	IW-2C-45	3/7/18	PES	ESC	45	-8.7	S	0.000356 U	0.000230 U	0.000405 U	0.00103 U	0.000248 U	0.000407 U	**1.02**	0.000284 U	0.000414 U	0.000275 U	0.000773 U	0.000322 U
	IW-2C-55	3/7/18	PES	ESC	55	-18.7	S	0.000382 U	0.000247 U	0.000434 U	0.00110 U	0.000267 U	0.000437 U	**0.0123**	0.000305 U	0.000445 U	0.000296 U	0.000830 U	0.000346 U
	IW-2C-65	3/7/18	PES	ESC	65	-28.7	S	0.000359 U	0.000232 U	0.000408 U	0.00103 U	0.000250 U	0.000410 U	**0.00376**	0.000287 U	0.000418 U	0.000278 U	0.000780 U	0.000325 U
	IW-2C-75	3/7/18	PES	ESC	75	-38.7	S	0.000394 U	0.000255 U	0.000448 U	0.00114 U	0.000275 U	0.000450 U	0.000282 U	0.000315 U	0.000459 U	0.000305 U	0.000856 U	0.000357 U
IW-3C (-24.9 to-39.9)	IW-3C-5	3/9/18	PES	ESC	5	34.1	S	0.000359 U	0.000232 U	0.000408 U	0.00103 U	0.000250 U	0.000410 U	**0.000620 J**	0.000286 U	0.000418 U	0.000278 U	0.000780 U	0.000325 U
	IW-3C-15	3/9/18	PES	ESC	15	24.1	S	0.00950 U	0.00614 U	0.0108 U	0.0274 U	0.00663 U	0.0109 U	**0.422**	0.00759 U	0.0111 U	0.00736 U	0.0206 U	0.00860 U
	IW-3C-25	3/9/18	PES	ESC	25	14.1	S	0.194 U	0.125 U	0.220 U	0.558 U	0.135 U	0.222 U	**0.968**	0.155 U	0.225 U	0.150 U	0.420 U	0.175 U
	IW-3C-35	3/9/18	PES	ESC	35	4.1	S	0.0729 U	0.0471 U	0.0829 U	0.210 U	0.0509 U	0.0833 U	**0.918**	0.0582 U	0.0849 U	0.0565 U	0.159 U	0.0660 U
	IW-3C-45	3/9/18	PES	ESC	45	-5.9	S	0.000378 U	0.000244 U	0.000430 U	**0.00212 J**	0.000264 U	0.000432 U	**0.199**	0.000302 U	0.000440 U	0.000293 U	0.000822 U	0.000342 U
	IW-3C-55	3/9/18	PES	ESC	55	-15.9	S	0.000372 U	0.000241 U	0.000423 U	0.00107 U	0.000260 U	0.000426 U	**0.0107**	0.000297 U	0.000433 U	0.000288 U	0.000809 U	0.000337 U
	IW-3C-65	3/9/18	PES	ESC	65	-25.9	S	0.000374 U	0.000242 U	0.000426 U	0.00108 U	0.000261 U	0.000428 U	**0.141**	0.000299 U	0.000436 U	0.000290 U	0.000813 U	0.000339 U
	IW-3C-75	3/9/18	PES	ESC	75	-35.9	S	0.000411 U	0.000265 U	0.000467 U	0.00118 U	0.000287 U	0.000470 U	**0.131**	0.000328 U	0.000478 U	0.000318 U	0.000893 U	0.000372 U
	IW-3C-79	3/9/18	PES	ESC	79	-39.9	S	0.000381 U	0.000246 U	0.000433 U	0.00110 U	0.000266 U	0.000436 U	**0.00195**	0.000304 U	0.000444 U	0.000295 U	0.000828 U	0.000345 U
	IW-901-79	3/9/18	PES	ESC	79 (dup)	-39.9	S	0.000379 U	0.000245 U	0.000431 U	0.00109 U	0.000265 U	0.000434 U	0.000272 U	0.000303 U	0.000442 U	0.000294 U	0.000825 U	0.000344 U
IW-7A (5.1 to-9.9)	IW-7A-5	3/16/18	PES	ESC	5	35.1	S	0.000406 U	0.000263 U	0.000462 U	0.00117 U	0.000284 U	0.000465 U	**0.00829**	0.000325 U	0.000473 U	0.000315 U	0.000884 U	**0.00221**
	IW-7A-10	3/16/18	PES	ESC	10	30.1	S	0.000801 U	0.00119 U	0.000983 U	0.00643 U	0.00238 U	0.00307 U	**0.00509**	0.00123 U	0.00137 U	0.000879 U	0.00200 U	**0.0304**
	IW-7A-15	3/16/18	PES	ESC	15	25.1	S	0.0132 U	0.00852 U	0.0150 U	0.0379 U	0.00919 U	0.0151 U	**0.0163 J**	0.0105 U	0.0154 U	0.0102 U	0.0286 U	**0.232**
	IW-7A-20	3/16/18	PES	ESC	20	20.1	S	0.000822 U	0.00122 U	0.00101 U	0.00660 U	0.00244 U	0.00315 U	**0.00155 J**	0.00127 U	0.00140 U	0.000902 U	0.00205 U	**0.00585**
	IW-7A-25	3/16/18	PES	ESC	25	15.1	S	0.000397 U	0.000257 U	0.000452 U	0.00115 U	0.000277 U	0.000454 U	**0.000857 J**	0.000317 U	0.000463 U	0.000308 U	0.000864 U	0.000360 U
	IW-7A-30	3/16/18	PES	ESC	30	10.1	S	0.000381 U	0.000246 U	0.000433 U	0.00110 U	0.000266 U	0.000435 U	**0.00175**	0.000304 U	0.000443 U	0.000295 U	0.000827 U	**0.000369 J**
	IW-7A-35	3/16/18	PES	ESC	35	5.1	S	0.000704 U	0.00105 U	0.000864 U	0.00566 U	0.00209 U	0.00270 U	**0.00193 J**	0.00109 U	0.00120 U	0.000773 U	0.00176 U	**0.00222 J**
	IW-7A-40	3/16/18	PES	ESC	40	0.1	S	0.000386 U	0.000250 U	0.000439 U	0.00111 U	0.000270 U	0.000442 U	**0.000564 J**	0.000308 U	0.000450 U	0.000299 U	0.000840 U	0.000350 U
	IW-7A-45	3/16/18	PES	ESC	45	-4.9	S	0.000383 U	0.000248 U	0.000436 U	0.00111 U	0.000268 U	0.000438 U	**0.000444 J**	0.000306 U	0.000446 U	0.000297 U	0.000833 U	0.000347 U
	IW-7A-50	3/16/18	PES	ESC	50	-9.9	S	0.000364 U	0.000235 U	0.000414 U	0.00105 U	0.000254 U	0.000417 U	**0.117**	0.000291 U	0.000424 U	0.000282 U	0.000792 U	0.000330 U
IW-8B (-9.8 to-24.8)	IW-8B-5	3/19/18	PES	ESC	5	34.2	S	0.000359 U	0.000232 U	0.000408 U	0.00104 U	0.000251 U	0.000410 U	**0.00224**	0.000287 U	0.000418 U	0.000278 U	0.000780 U	0.000325 U
	IW-8B-10	3/19/18	PES	ESC	10	29.2	S	0.000354 U	0.000229 U	0.000402 U	0.00102 U	0.000247 U	0.000404 U	**0.00634**	0.000282 U	0.000412 U	0.000274 U	0.000769 U	0.000320 U
	IW-8B-15	3/19/18	PES	ESC	15	24.2	S	0.0944 U	0.0610 U	0.107 U	0.272 U	0.0658 U	0.108 U	0.198 U	0.0754 U	0.110 U	0.0731 U	0.205 U	0.0854 U
	IW-8B-20	3/19/18	PES	ESC	20	19.2	S	0.000360 U	0.000233 U	0.000409 U	0.00104 U	**0.000493 J**	0.000412 U	**0.117**	0.000288 U	0.000419 U	0.000279 U	0.000782 U	0.000326 U
	IW-8B-25	3/19/18	PES	ESC	25	14.2	S	0.000384 U	0.000248 U	0.000437 U	**0.00257 J**	0.000268 U	0.000439 U	**0.319**	0.000307 U	0.000447 U	0.000297 U	0.000834 U	0.000348 U
	IW-8B-30	3/19/18	PES	ESC	30	9.2	S	0.000369 U	0.000238 U	0.000419 U	0.00106 U	0.000257 U	0.000421 U	**0.107**	0.000294 U	0.000429 U	0.000285 U	0.000801 U	0.000334 U
	IW-8B-40	3/19/18	PES	ESC	40	-0.8	S	0.000366 U	0.000236 U	0.000416 U	0.00106 U	0.000255 U	**0.00114 J**	**0.00401**	0.000292 U	0.000426 U	0.000283 U	0.000795 U	0.000331 U
	IW-8B-45	3/20/18	PES	ESC	45	-5.8	S	0.000366 U	0.000236 U	0.000416 U	0.00105 U	0.000255 U	**0.00149 J**	**0.00866**	0.000292 U	0.000426 U	0.000283 U	0.000795 U	0.000331 U
	IW-8B-50	3/20/18	PES	ESC	50	-10.8	S	0.000375 U	0.000242 U	0.000427 U	0.00108 U	0.000262 U	0.000429 U	**0.00364**	0.000300 U	0.000437 U	0.000291 U	0.000816 U	0.000340 U
	IW-8B-55	3/20/18	PES	ESC	55	-15.8	S	0.000354 U	0.000229 U	0.000402 U	0.00102 U	0.000247 U	**0.00123 J**	**0.00183**	0.000283 U	0.000412 U	0.000274 U	0.000769 U	0.000320 U
	IW-8B-60	3/20/18	PES	ESC	60	-20.8	S	0.000376 U	0.000243 U	0.000427 U	0.00108 U	0.000262 U	0.000429 U	**0.00148**	0.000300 U	0.000437 U	0.000291 U	0.000817 U	0.000340 U
	IW-8B-64	3/20/18	PES	ESC	64	-24.8	S	0.000370 U	0.000239 U	0.000421 U	0.00107 U	0.000258 U	0.000423 U	0.00102 U	0.000295 U	0.000431 U	0.000286 U	0.000804 U	0.000335 U
IW-8C (-24.5 to-39.5)	IW-8C-5	3/14/18	PES	ESC	5	32.5	S	0.000563 U	0.000364 U	0.000641 U	0.00162 U	**0.00117 J**	0.000644 U	**0.0338 J+**	0.000450 U	0.000655 U	0.000436 U	0.00122 U	0.000510 U
	IW-8C-10	3/14/18	PES	ESC	10	27.5	S	0.000567 U	0.000367 U	0.000645 U	0.00164 U	0.000396 U	0.000649 U	**0.0112**	0.000453 U	0.000661 U	0.000439 U	0.00123 U	0.000514 U
	IW-8C-15	3/14/18	PES	ESC	15	22.5	S	0.000387 U	0.000250 U	0.000439 U	0.00111 U	0.000270 U	0.000442 U	**0.000359 J**	0.000309 U	0.000450 U	0.000299 U	0.000840 U	0.000350 U
	IW-8C-20	3/14/18	PES	ESC	20	17.5	S	0.000354 U	0.000229 U	0.000402 U	0.00102 U	0.000247 U	0.000404 U	**0.0108**	0.000283 U	0.000412 U	0.000274 U	0.000769 U	0.000320 U
	IW-8C-25	3/14/18	PES	ESC	25	12.5	S	0.000390 U	0.000252 U	0.000444 U	**0.00124 J**	0.000273 U	0.000446 U	**0.946**	0.000312 U	0.000455 U	0.000302 U	0.000849 U	0.000354 U
	IW-8C-30	3/14/18	PES	ESC	30	7.5	S	0.000363 U	0.000235 U	0.000413 U	0.00105 U	0.000253 U	0.000415 U	**0.143**	0.000290 U	0.000423 U	0.000281 U	0.000789 U	0.000329 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
IW-8C (continued)	IW-8C-35	3/14/18	PES	ESC	35	2.5	S	0.000379 U	0.000245 U	0.000431 U	0.00109 U	0.000265 U	0.000434 U	**0.162**	0.000303 U	0.000442 U	0.000294 U	0.000825 U	0.000344 U
	IW-8C-40	3/14/18	PES	ESC	40	-2.5	S	0.000378 U	0.000244 U	0.000430 U	0.00109 U	0.000264 U	0.000432 U	**1.54**	0.000302 U	0.000440 U	0.000292 U	0.000821 U	0.000342 U
	IW-8C-45	3/14/18	PES	ESC	45	-7.5	S	0.000370 U	0.000239 U	0.000421 U	0.00107 U	0.000258 U	0.000423 U	**0.200**	0.000296 U	0.000431 U	0.000287 U	0.000804 U	0.000335 U
	IW-8C-50	3/14/18	PES	ESC	50	-12.5	S	0.000385 U	0.000249 U	0.000438 U	0.00111 U	**0.000324 J**	0.000441 U	**3.68**	0.000308 U	0.000449 U	0.000298 U	0.000838 U	**0.00441 J+**
	IW-8C-55	3/14/18	PES	ESC	55	-17.5	S	0.000378 U	0.000245 U	0.000430 U	0.00109 U	**0.000398 J**	0.000433 U	**2.31**	0.000302 U	0.000441 U	0.000293 U	0.000823 U	**0.000604 J+**
	IW-8C-60	3/14/18	PES	ESC	60	-22.5	S	0.000375 U	0.000242 U	0.000426 U	0.00108 U	0.000262 U	0.000428 U	**0.464**	0.000299 U	0.000436 U	0.000290 U	0.000815 U	0.000339 U
	IW-902-60	3/14/18	PES	ESC	60 (dup)	-22.5	S	0.000364 U	0.000235 U	0.000414 U	0.00105 U	0.000254 U	**0.00634**	**0.108**	0.000291 U	0.000424 U	0.000282 U	0.000791 U	0.000330 U
	IW-8C-65	3/14/18	PES	ESC	65	-27.5	S	0.000393 U	0.000254 U	0.000447 U	0.00113 U	0.000275 U	0.000450 U	**0.00158**	0.000314 U	0.000458 U	0.000305 U	0.000855 U	0.000356 U
	IW-8C-70	3/14/18	PES	ESC	70	-32.5	S	0.000389 U	0.000252 U	0.000443 U	0.00112 U	0.000272 U	0.000445 U	**0.0327**	0.000311 U	0.000453 U	0.000302 U	0.000846 U	0.000353 U
	IW-8C-75	3/14/18	PES	ESC	75	-37.5	S	0.000367 U	0.000237 U	0.000418 U	0.00106 U	0.000256 U	0.000420 U	**0.00864**	0.000293 U	0.000428 U	0.000284 U	0.000798 U	0.000332 U
IW-11D (-41.8 to-56.8)	IW-11D-10	4/19/18	PES	ESC	10	28.4	S	0.000453 U	0.000293 U	0.000515 U	0.00131 U	0.000316 U	0.000518 U	**0.000329 J**	0.000362 U	0.000527 U	0.000351 U	0.000984 U	**0.000463 J**
	IW-11D-15	4/19/18	PES	ESC	15	23.4	S	0.000380 U	0.000246 U	0.000432 U	0.00110 U	0.000265 U	0.000435 U	0.000272 U	0.000304 U	0.000443 U	0.000294 U	0.000826 U	0.000344 U
	IW-11D-20	4/19/18	PES	ESC	20	18.4	S	0.000379 U	0.000245 U	0.000431 U	0.00109 U	0.000265 U	0.000434 U	0.000272 U	0.000303 U	0.000442 U	0.000294 U	0.000825 U	0.000344 U
	IW-11D-25	4/19/18	PES	ESC	25	13.4	S	0.000358 U	0.000232 U	0.000408 U	0.00103 U	0.000250 U	0.000410 U	**0.0174**	0.000286 U	0.000417 U	0.000278 U	0.000779 U	0.000325 U
	IW-11D-30	4/19/18	PES	ESC	30	8.4	S	0.000359 U	0.000232 U	0.000408 U	0.00103 U	0.000250 U	0.000410 U	**0.00931**	0.000287 U	0.000418 U	0.000278 U	0.000780 U	0.000325 U
	IW-11D-35	4/19/18	PES	ESC	35	3.4	S	0.000376 U	0.000243 U	0.000427 U	0.00108 U	0.000262 U	0.000430 U	**0.101**	0.000300 U	0.000438 U	0.000291 U	0.000817 U	0.000340 U
	IW-11D-40	4/19/18	PES	ESC	40	-1.6	S	0.000362 U	0.000234 U	0.000412 U	0.00105 U	0.000253 U	0.000414 U	**1.25**	0.000290 U	0.000422 U	0.000281 U	0.000788 U	0.000328 U
	IW-11D-45	4/19/18	PES	ESC	45	-6.6	S	0.00923 U	0.00597 U	0.0105 U	0.0266 U	0.00644 U	0.0106 U	**0.426**	0.00737 U	0.0108 U	0.00715 U	0.0200 U	0.00835 U
	IW-11D-50	4/19/18	PES	ESC	50	-11.6	S	0.000352 U	0.000228 U	0.000401 U	0.00102 U	0.000246 U	0.000403 U	**0.693**	0.000281 U	0.000410 U	0.000273 U	0.000766 U	0.000319 U
	IW-11D-55	4/19/18	PES	ESC	55	-16.6	S	0.000389 U	0.000251 U	0.000442 U	0.00112 U	0.000271 U	0.000444 U	**2.04**	0.000310 U	0.000453 U	0.000301 U	0.000845 U	0.000352 U
	IW-11D-60	4/19/18	PES	ESC	60	-21.6	S	0.000360 U	0.000233 U	0.000410 U	0.00104 U	0.000252 U	0.000412 U	**0.00916**	0.000288 U	0.000420 U	0.000279 U	0.000783 U	0.000326 U
	IW-11D-65	4/19/18	PES	ESC	65	-26.6	S	0.000361 U	0.000234 U	0.000411 U	0.00104 U	0.000252 U	0.000413 U	**0.00280**	0.000289 U	0.000421 U	0.000280 U	0.000785 U	0.000327 U
	IW-11D-70	4/19/18	PES	ESC	70	-31.6	S	0.000362 U	0.000234 U	0.000412 U	0.00104 U	0.000253 U	0.000414 U	**2.07**	0.000289 U	0.000422 U	0.000280 U	0.000787 U	0.000328 U
	IW-11D-75	4/19/18	PES	ESC	75	-36.6	S	0.000379 U	0.000245 U	0.000431 U	0.00109 U	0.000264 U	0.000433 U	**0.106**	0.000302 U	0.000441 U	0.000293 U	0.000823 U	0.000343 U
	IW-11D-80	4/19/18	PES	ESC	80	-41.6	S	0.000369 U	0.000238 U	0.000419 U	0.00106 U	0.000257 U	0.000421 U	**0.00473**	0.000294 U	0.000429 U	0.000285 U	0.000801 U	0.000334 U
	IW-11D-85	4/19/18	PES	ESC	85	-46.6	S	0.000377 U	0.000244 U	0.000429 U	0.00109 U	0.000263 U	0.000431 U	**0.000785 J**	0.000301 U	0.000439 U	0.000292 U	0.000820 U	0.000341 U
	IW-11D-90	4/19/18	PES	ESC	90	-51.6	S	0.000372 U	0.000240 U	0.000423 U	0.00107 U	0.000259 U	0.000425 U	**0.00227**	0.000297 U	0.000433 U	0.000288 U	0.000808 U	0.000336 U
	IW-11D-95	4/19/18	PES	ESC	95	-56.6	S	0.000384 U	0.000248 U	0.000437 U	0.00111 U	0.000268 U	0.000439 U	0.000275 U	0.000307 U	0.000448 U	0.000298 U	0.000835 U	0.000348 U
IW-12D (-41.4 to-56.4)	IW-12D-42	9/14/18	PES	ESC	42	-3.5	S	0.00117 U	0.000622 U	0.000488 U	0.117 U	0.000450 U	0.00151 U	**2.16**	0.000736 U	0.00109 U	0.000855 U	0.000888 U	0.000575 U
	B-928-42	9/14/18	PES	ESC	42 (dup)	-3.5	S	0.00117 U	0.000623 U	0.000489 U	0.117 U	0.000451 U	0.00151 U	**1.88**	0.000737 U	0.00109 U	0.000856 U	0.000889 U	0.000576 U
	IW-12D-50	9/14/18	PES	ESC	50	-11.5	S	0.00118 U	0.000627 U	0.000492 U	0.236 U	0.000454 U	0.00152 U	**1.04**	0.000741 U	0.00109 U	0.000862 U	0.000895 U	0.000580 U
	IW-12D-60	9/14/18	PES	ESC	60	-21.5	S	0.00122 U	0.000645 U	0.000507 U	0.0243 U	0.000467 U	0.00157 U	**0.566**	0.000764 U	0.00113 U	0.000888 U	0.000921 U	0.000597 U
	IW-12D-85	9/17/18	PES	ESC	85	-46.5	S	0.00121 U	0.000640 U	0.000503 U	0.00121 U	0.000464 U	0.00155 U	**0.0596**	0.000758 U	0.00112 U	0.000881 U	0.000914 U	0.000592 U
	IW-12D-95	9/17/18	PES	ESC	95	-56.5	S	0.00130 U	0.000689 U	0.000541 U	0.00130 U	0.000499 U	0.00167 U	**0.00818**	0.000815 U	0.00120 U	0.000948 U	0.000984 U	0.00637 U
IW-13D (-41.0 to-56.0)	IW-13D-80	9/18/18	PES	ESC	80	-40.8	S	0.00119 U	0.000632 U	0.000496 U	0.00119 U	0.000458 U	0.00153 U	**0.157**	0.000748 U	0.00110 U	0.000869 U	0.000903 U	**0.000719**
	IW-13D-85	9/18/18	PES	ESC	85	-45.8	S	0.00124 U	0.000660 U	0.000518 U	0.00124 U	0.000478 U	0.00160 U	**0.0220**	0.000780 U	0.00115 U	0.000907 U	0.000942 U	0.000610 U
	IW-13D-95	9/18/18	PES	ESC	95	-55.8	S	0.00130 U	0.000690 U	0.000542 U	0.00130 U	0.000499 U	0.00167 U	**0.00113**	0.000816 U	0.00120 U	0.000948 U	0.000984 U	0.000638 U
IW-14D (-41.0 to-56.0)	IW-14D-45	9/11/18	PES	ESC	45	-5.9	S	0.00113 U	0.000600 U	0.000471 U	**0.0188**	0.000435 U	0.00146 U	**0.224**	0.000710 U	0.00105 U	0.000826 U	0.000857 U	0.000555 U
	IW-14D-55	9/11/18	PES	ESC	55	-15.9	S	0.00122 U	0.000647 U	0.000508 U	**0.0149**	0.000469 U	0.00157 U	**3.90**	0.000766 U	0.00113 U	0.000890 U	0.000924 U	**0.000834 J**
	IW-14D-65	9/11/18	PES	ESC	65	-25.9	S	0.00121 U	0.000643 U	0.000505 U	0.00121 U	0.000466 U	0.00156 U	**0.244**	0.000761 U	0.00112 U	0.000884 U	0.000918 U	0.000595 U
	IW-14D-75	9/11/18	PES	ESC	75	-35.9	S	0.00121 U	0.000643 U	0.000505 U	**0.0282**	0.000466 U	0.00156 U	**0.00943**	0.000761 U	0.00112 U	0.000884 U	0.000918 U	0.000595 U
	IW-14D-86	9/11/18	PES	ESC	86	-46.9	S	0.00119 U	0.000631 U	0.000496 U	0.00119 U	0.000457 U	0.00153 U	**0.0189**	0.000747 U	0.00110 U	0.000868 U	0.000901 U	0.000584 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
IW-14D (continued)	IW-14D-95	9/11/18	PES	ESC	95	-55.9	S	0.00122 U	0.000649 U	0.000510 U	**0.0244**	0.000470 U	0.00157 U	**0.0212**	0.000768 U	0.00113 U	0.000893 U	0.000927 U	**0.000606 J**
IW-15D (-41.9 to-56.9)	IW-15D-54	9/11/18	PES	ESC	54	-2.2	S	0.00116 U	0.000613 U	0.000482 U	**0.0265**	0.000444 U	0.00149 U	**0.242**	0.000725 U	0.00107 U	0.000843 U	0.000875 U	**0.000628 J**
IW-16D (-41.5 to-56.2)	IW-16D-85	10/18/18	PES	PACE	85	-45.6	S	0.00503 U	0.00267 U	0.00210 U	0.00503 U	**0.00193 J**	0.00648 U	**0.336**	0.00316 U	0.00466 U	0.00367 U	0.00381 U	**0.00256 J**
	IW-16D-90	10/18/18	PES	PACE	90	-50.6	S	0.00128 U	0.000679 U	0.000534 U	0.00128 U	0.000492 U	0.00165 U	**0.0191**	0.000804 U	0.00119 U	0.000934 U	0.000970 U	0.000628 U
	IW-16D-95	10/18/18	PES	PACE	95	-55.6	S	0.00523 U	0.00277 U	0.00218 U	0.00523 U	0.00201 U	0.00673 U	**0.0238**	0.00328 U	0.00484 U	0.00381 U	0.00396 U	0.00257 U
IW-19B (-10.6 to-25.6)	IW-19B-5	3/19/18	PES	ESC	5	32.4	S	0.000370 U	0.000240 U	0.000421 U	0.00107 U	0.000258 U	0.000424 U	0.000961 U	0.000296 U	0.000431 U	0.000287 U	0.000805 U	0.000336 U
	IW-19B-10	3/19/18	PES	ESC	10	27.4	S	0.000404 U	0.000261 U	0.000459 U	0.00116 U	0.000282 U	0.000461 U	0.000718 U	0.000322 U	0.000470 U	0.000313 U	0.000877 U	0.000365 U
	IW-19B-15	3/19/18	PES	ESC	15	22.4	S	0.000376 U	0.000243 U	0.000427 U	0.00108 U	0.000262 U	0.000430 U	0.000383 U	0.000300 U	0.000438 U	0.000291 U	0.000817 U	0.000340 U
	IW-19B-20	3/19/18	PES	ESC	20	17.4	S	0.000366 U	0.000237 U	0.000417 U	0.00106 U	0.000256 U	0.000419 U	0.000349 U	0.000293 U	0.000427 U	0.000284 U	0.000796 U	0.000332 U
	IW-19B-25	3/19/18	PES	ESC	25	12.4	S	0.000385 U	0.000249 U	0.000438 U	0.00111 U	**0.00122 J**	0.000440 U	0.000621 U	0.000308 U	0.000448 U	0.000298 U	0.000837 U	0.000349 U
	IW-19B-30	3/19/18	PES	ESC	30	7.4	S	0.000368 U	0.000238 U	0.000419 U	0.00106 U	0.000257 U	0.000421 U	0.000600 U	0.000294 U	0.000429 U	0.000285 U	0.000801 U	0.000334 U
	IW-19B-35	3/19/18	PES	ESC	35	2.4	S	0.000364 U	0.000235 U	0.000414 U	0.00105 U	**0.000438 J**	0.000416 U	0.000786 U	0.000291 U	0.000424 U	0.000282 U	0.000791 U	0.000329 U
	IW-19B-40	3/19/18	PES	ESC	40	-2.6	S	0.000379 U	0.000245 U	0.000431 U	0.00109 U	0.000264 U	0.000433 U	**0.0140**	0.000302 U	0.000441 U	0.000293 U	0.000823 U	0.000343 U
	IW-19B-45	3/19/18	PES	ESC	45	-7.6	S	0.000400 U	0.000259 U	0.000455 U	0.00115 U	0.000279 U	0.000458 U	0.00112 U	0.000320 U	0.000466 U	0.000310 U	0.000870 U	0.000362 U
	IW-19B-50	3/19/18	PES	ESC	50	-12.6	S	0.000418 U	0.000270 U	0.000476 U	0.00121 U	0.000292 U	**0.0575**	**0.0683**	0.000334 U	0.000488 U	0.000324 U	0.000909 U	0.000379 U
	IW-19B-55	3/19/18	PES	ESC	55	-17.6	S	0.000361 U	0.000233 U	0.000410 U	0.00104 U	0.000252 U	0.000413 U	**1.93**	0.000288 U	0.000420 U	0.000279 U	0.000785 U	0.000327 U
	IW-19B-60	3/19/18	PES	ESC	60	-22.6	S	0.000362 U	0.000234 U	0.000412 U	0.00104 U	0.000253 U	0.000414 U	**3.16**	0.000289 U	0.000421 U	0.000280 U	0.000787 U	0.000328 U
	IW-903-60	3/19/18	PES	ESC	60 (dup)	-22.6	S	0.000368 U	0.000238 U	0.000419 U	0.00106 U	0.000257 U	0.000421 U	**3.68**	0.000294 U	0.000429 U	0.000285 U	0.000800 U	0.000333 U
	IW-19B-63	3/19/18	PES	ESC	63	-25.6	S	0.000367 U	0.000237 U	0.000418 U	0.00106 U	0.000256 U	0.000420 U	**0.0326**	0.000293 U	0.000428 U	0.000284 U	0.000798 U	0.000333 U
IW-21B (-10.1 to-25.1)	IW-21B-5	3/6/18	PES	ESC	5	36.9	V	0.000592 U	0.000383 U	0.000674 U	0.00170 U	0.000414 U	0.000677 U	**0.00711**	0.000473 U	0.000690 U	0.000458 U	0.00129 U	0.000536 U
	IW-21B-10	3/6/18	PES	ESC	10	31.9	S	0.000400 U	0.000258 U	0.000455 U	0.00115 U	0.000279 U	0.000457 U	**0.00482**	0.000319 U	0.000466 U	0.000310 U	0.000869 U	0.000362 U
	IW-21B-20	3/6/18	PES	ESC	20	21.9	S	0.000394 U	0.000255 U	0.000448 U	0.00114 U	0.000275 U	0.000451 U	0.000283 U	0.000315 U	0.000459 U	0.000305 U	0.000857 U	0.000357 U
	IW-21B-30	3/6/18	PES	ESC	30	11.9	S	0.000366 U	0.000237 U	0.000416 U	0.00106 U	0.000256 U	0.000419 U	**0.000406 J**	0.000293 U	0.000427 U	0.000284 U	0.000796 U	0.000332 U
	IW-21B-40	3/6/18	PES	ESC	40	1.9	S	0.000363 U	0.000234 U	0.000412 U	0.00105 U	0.000253 U	0.000415 U	**0.0424**	0.000290 U	0.000422 U	0.000281 U	0.000788 U	0.000328 U
	IW-21B-50	3/6/18	PES	ESC	50	-8.1	S	0.000355 U	0.000229 U	0.000403 U	0.00102 U	0.000248 U	0.000406 U	**0.0340**	0.000283 U	0.000413 U	0.000275 U	0.000771 U	0.000321 U
	IW-21B-60	3/6/18	PES	ESC	60	-18.1	S	0.00929 U	0.00601 U	0.0106 U	0.0267 U	0.00648 U	0.0106 U	**3.82**	0.00742 U	0.0108 U	0.00720 U	0.0202 U	0.00841 U
	IW-21B-67	3/6/18	PES	ESC	67	-25.1	S	0.000363 U	0.000235 U	0.000413 U	0.00105 U	0.000254 U	0.000415 U	**0.0353 J**	0.000290 U	0.000423 U	0.000281 U	0.000790 U	0.000329 U
IW-22C (-25.6 to-40.6)	IW-22C-62	8/31/18	PES	ESC	62	-23.1	S	0.00125 U	0.000661 U	0.000520 U	0.00125 U	0.000479 U	0.00161 U	**0.305**	0.000782 U	0.00115 U	0.000910 U	0.000944 U	**0.00123 J**
	IW-22C-78	8/31/18	PES	ESC	78	-39.1	S	0.00131 U	0.000694 U	0.000545 U	0.00131 U	0.000503 U	0.00168 U	**0.975**	0.000821 U	0.00121 U	0.000954 U	0.000991 U	0.000642 U
IW-23C (-27.0 to-42.0)	IW-23C-42	9/4/18	PES	ESC	42	-3.0	S	0.00129 U	0.000686 U	0.000539 U	0.00129 U	0.000497 U	0.00166 U	**8.86**	0.000812 U	0.00120 U	0.000943 U	0.000979 U	**0.00266 J**
IW-24C (-26.1 to-41.1)	IW-24C-48	9/7/18	PES	ESC	48	-8.8	S	0.00122 U	0.000648 U	0.000509 U	0.00122 U	0.000469 U	0.00157 U	**3.74**	0.000766 U	0.00113 U	0.000891 U	0.000925 U	**0.000599**
	IW-24C-55	9/7/18	PES	ESC	55	-15.8	S	0.00128 U	0.000682 U	0.000536 U	0.00128 U	0.000495 U	0.00165 U	**0.980**	0.000807 U	0.00119 U	0.0939 U	0.000974 U	**0.00186 J**
	IW-24C-66	9/10/18	PES	ESC	66	-26.8	S	0.00134 U	0.000709 U	0.000557 U	0.00134 U	0.000513 U	0.00172 U	**2.18**	0.000839 U	0.00124 U	0.390 U	0.00101 U	0.262 U
	IW-24C-75	9/10/18	PES	ESC	75	-35.8	S	0.00129 U	0.000685 U	0.000538 U	0.00129 U	0.000496 U	0.00166 U	**2.62**	0.000810 U	0.00120 U	0.376 U	0.000977 U	0.253 U
	IW-24C-80	9/10/18	PES	ESC	80	-40.8	S	0.00119 U	0.000634 U	**0.000680 J**	0.00119 U	0.000459 U	0.00154 U	**0.699**	0.000750 U	0.00111 U	0.000872 U	0.000905 U	0.000586 U
IW-27B (-8.1 to-23.1)	IW-27B-5	3/2/18	PES	ESC	5	37.0	V	0.000525 U	0.000340 U	0.000598 U	0.00152 U	0.000366 U	0.000600 U	**0.0106**	0.000419 U	0.000612 U	0.000407 U	0.00114 U	0.000476 U
	IW-27B-15	3/2/18	PES	ESC	15	27.0	S	0.000467 U	0.000302 U	0.000531 U	0.00135 U	0.000326 U	0.000534 U	**0.00218**	0.000373 U	0.000544 U	0.000362 U	0.00102 U	0.000423 U
	IW-27B-25	3/2/18	PES	ESC	25	17.0	S	0.000381 U	0.000247 U	0.000434 U	0.00110 U	0.000266 U	0.000436 U	0.000273 U	0.000305 U	0.000444 U	0.000295 U	0.000829 U	0.000345 U
	IW-27B-35	3/2/18	PES	ESC	35	7.0	S	0.000375 U	0.000243 U	0.000427 U	0.00108 U	0.000262 U	0.000429 U	**0.108**	0.000300 U	0.000437 U	0.000291 U	0.000816 U	0.000340 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
IW-27C (-24.4 to-39.6)	IW-27C-45	9/10/18	PES	ESC	45	6.8	S	0.00121 U	0.000641 U	0.000504 U	0.00121 U	0.000465 U	0.00156 U	**0.282**	0.000759 U	0.00112 U	0.000882 U	0.000916 U	0.000593 U
IW-28C (-26.6 to-41.7)	IW-28C-92	9/17/18	PES	ESC	92	-40.6	S	0.00117 U	0.000623 U	0.000489 U	0.00117 U	0.000451 U	0.00151 U	**0.0103**	0.000737 U	0.00109 U	0.000857 U	0.000889 U	0.000576 U
IW-39B (-9.8 to-24.8)	IW-39B-5	3/12/18	PES	ESC	5	35.2	V	0.000416 U	0.000269 U	0.000474 U	0.00120 U	0.000291 U	0.000476 U	**0.0227**	0.000333 U	0.000485 U	0.000323 U	0.000905 U	0.000377 U
	IW-39B-15	3/12/18	PES	ESC	15	25.2	S	0.000366 U	0.000236 U	0.000416 U	0.00105 U	0.000255 U	0.000418 U	**0.00624**	0.000292 U	0.000426 U	0.000283 U	0.000795 U	0.000331 U
	IW-39B-25	3/12/18	PES	ESC	25	15.2	S	0.000390 U	0.000252 U	0.000443 U	0.00112 U	0.000272 U	0.000446 U	**0.0239**	0.000311 U	0.000454 U	0.000302 U	0.000848 U	0.000353 U
	IW-39B-35	3/12/18	PES	ESC	35	5.2	S	0.000360 U	0.000233 U	0.000410 U	0.00104 U	0.000251 U	0.000412 U	**0.0135**	0.000288 U	0.000419 U	0.000279 U	0.000783 U	0.000326 U
	IW-39B-45	3/12/18	PES	ESC	45	-4.8	S	0.000368 U	0.000238 U	0.000418 U	0.00106 U	0.000257 U	0.000420 U	**0.0185**	0.000294 U	0.000428 U	0.000285 U	0.000799 U	0.000333 U
	IW-39B-55	3/12/18	PES	ESC	55	-14.8	S	0.00861 U	0.00557 U	0.00979 U	0.0248 U	0.00601 U	0.00985 U	**1.57**	0.00688 U	0.0100 U	0.00667 U	0.0187 U	0.00779 U
IW-46B (-4.2 to-24.2)	IW-46B-5	3/20/18	PES	ESC	5	46.8	V	0.000369 U	0.000238 U	0.000419 U	0.00106 U	0.000257 U	0.000422 U	**0.000434 J**	0.000295 U	0.000429 U	0.000286 U	0.000801 U	0.000334 UJ
	IW-46B-10	3/20/18	PES	ESC	10	41.8	V	0.000360 U	0.000233 U	0.000410 U	0.00104 U	0.000252 U	0.000412 U	**0.000349 J**	0.000288 U	0.000420 U	0.000279 U	0.000783 U	0.000326 UJ
	IW-46B-15	3/20/18	PES	ESC	15	36.8	V	0.00907 U	0.00586 U	0.0103 U	0.0261 U	0.00633 U	0.0104 U	0.00650 UJ	0.00725 U	0.0106 U	0.00702 U	0.0197 U	0.00821 UJ
	IW-46B-20	3/20/18	PES	ESC	20	31.8	S	0.000367 U	0.000237 U	0.000417 U	0.00106 U	0.000256 U	0.000419 U	**0.000960 J**	0.000293 U	0.000427 U	0.000284 U	0.000797 U	0.000332 UJ
	IW-46B-25	3/20/18	PES	ESC	25	26.8	S	0.000363 U	0.000234 U	0.000412 U	0.00105 U	0.000253 U	0.000414 U	**0.00239 J**	0.000290 U	0.000422 U	0.000281 U	0.000788 U	0.000328 UJ
	IW-46B-30	3/20/18	PES	ESC	30	21.8	S	0.000367 U	0.000237 U	0.000417 U	0.00106 U	0.000256 U	0.000419 U	**0.00513 J**	0.000293 U	0.000427 U	0.000284 U	0.000797 U	0.000332 UJ
	IW-46B-35	3/20/18	PES	ESC	35	16.8	S	0.000397 U	0.000256 U	0.000451 U	0.00114 U	0.000277 U	0.000454 U	**0.000737 J**	0.000317 U	0.000462 U	0.000307 U	0.000863 U	0.000359 UJ
	IW-904-35	3/20/18	PES	ESC	35 (dup)	16.8	S	0.000419 U	0.000271 U	0.000477 U	0.00121 U	0.000293 U	0.000480 U	**0.00147 J**	0.000335 U	0.000489 U	0.000325 U	0.000912 U	0.000380 UJ
	IW-46B-40	3/20/18	PES	ESC	40	11.8	S	0.000345 U	0.000223 U	0.000392 U	0.000994 U	0.000241 U	0.000394 U	**0.00149 J**	0.000275 U	0.000402 U	0.000267 U	0.000749 U	0.000312 UJ
	IW-46B-42	3/20/18	PES	ESC	42	9.8	S	0.000394 U	0.000255 U	0.000449 U	0.00114 U	**0.000660 J**	0.000451 U	**4.91 J**	0.000315 U	0.000459 U	0.000305 U	0.000857 U	0.000357 UJ
	IW-46B-45	3/20/18	PES	ESC	45	6.8	S	1.87 U	1.21 U	2.12 U	5.38 U	1.30 U	2.14 U	**2.47 J**	1.49 U	2.17 U	1.44 U	4.05 U	1.68 UJ
	IW-46B-50	3/20/18	PES	ESC	50	1.8	S	0.000328 U	0.000212 U	0.000373 U	0.000946 U	0.000229 U	0.000375 U	**2.05 J**	0.000262 U	0.000382 U	0.000254 U	0.000713 U	0.000297 UJ
	IW-46B-55	3/20/18	PES	ESC	55	-3.2	S	0.000366 U	0.000236 U	0.000416 U	0.00105 U	0.000255 U	0.000418 U	**1.06 J**	0.000292 U	0.000426 U	0.000283 U	0.000795 U	0.000331 UJ
	IW-46B-60	3/20/18	PES	ESC	60	-8.2	S	0.000371 U	0.000239 U	0.000421 U	0.00107 U	0.000259 U	0.000424 U	**4.95 J**	0.000296 U	0.000432 U	0.000287 U	0.000805 U	0.000335 UJ
	IW-46B-65	3/20/18	PES	ESC	65	-13.2	S	0.000365 U	0.000236 U	0.000415 U	0.00105 U	0.000255 U	0.000417 U	**4.82 J**	0.000291 U	0.000425 U	0.000282 U	0.000793 U	0.000330 UJ
	IW-46B-70	3/20/18	PES	ESC	70	-18.2	S	0.000418 U	0.000270 U	0.000476 U	0.00121 U	0.000292 U	0.000478 U	**4.07 J**	0.000334 U	0.000487 U	0.000324 U	0.000909 U	0.000379 UJ
IW-47B (-5.2 to-25.2)	IW-47B-5	3/22/18	PES	ESC	5	46.8	V	0.000387 U	0.000250 U	0.000440 U	0.00112 U	0.000270 U	0.000442 U	**0.000394 J**	0.000309 U	0.000451 U	0.000300 U	0.000841 U	0.000350 UJ
	IW-47B-10	3/22/18	PES	ESC	10	41.8	V	0.000386 U	0.000249 U	0.000439 U	0.00111 U	0.000269 U	0.000441 U	**0.000623 J**	0.000308 U	0.000449 U	0.000299 U	0.000839 U	0.000349 UJ
	IW-47B-15	3/22/18	PES	ESC	15	36.8	V	0.000366 U	0.000237 U	0.000416 U	0.00106 U	0.000256 U	0.000419 U	**0.0413 J**	0.000293 U	0.000427 U	0.000284 U	0.000796 U	0.000332 UJ
	IW-47B-20	3/22/18	PES	ESC	20	31.8	S	0.000364 U	0.000235 U	0.000414 U	0.00105 U	0.000254 U	0.000416 U	**0.00146 J**	0.000291 U	0.000424 U	0.000282 U	0.000792 U	0.000330 UJ
	IW-47B-25	3/22/18	PES	ESC	25	26.8	S	0.000371 U	0.000240 U	0.000422 U	0.00107 U	0.000259 U	0.000424 U	**0.00859 J**	0.000296 U	0.000432 U	0.000287 U	0.000807 U	0.000336 UJ
	IW-47B-30	3/22/18	PES	ESC	30	21.8	S	0.000368 U	0.000238 U	0.000418 U	0.00106 U	0.000257 U	0.000420 U	**0.146 J**	0.000294 U	0.000428 U	0.000285 U	0.000799 U	0.000333 UJ
	IW-47B-35	3/22/18	PES	ESC	35	16.8	S	0.000361 U	0.000233 U	0.000410 U	0.00104 U	0.000252 U	0.000412 U	**0.00566 J**	0.000288 U	0.000420 U	0.000279 U	0.000784 U	0.000327 UJ
	IW-47B-40	3/22/18	PES	ESC	40	11.8	S	0.000372 U	0.000241 U	0.000423 U	0.00107 U	0.000260 U	0.000426 U	**0.0378 J**	0.000297 U	0.000434 U	0.000288 U	0.000809 U	0.000337 UJ
	IW-47B-42	3/22/18	PES	ESC	42	9.8	S	0.000431 U	0.000279 U	0.000489 U	0.00124 U	0.000301 U	0.000492 U	**0.0477 J**	0.000344 U	0.000502 U	0.000333 U	0.000936 U	0.000390 UJ
	IW-47B-45	3/22/18	PES	ESC	45	6.8	S	0.000371 U	0.000240 U	0.000422 U	0.00107 U	0.000259 U	0.000424 U	**1.42 J**	0.000296 U	0.000432 U	0.000287 U	0.000806 U	0.000336 UJ
	IW-47B-50	3/22/18	PES	ESC	50	1.8	S	0.000385 U	0.000249 U	0.000438 U	0.00111 U	0.000269 U	0.000440 U	**0.0368 J**	0.000308 U	0.000449 U	0.000298 U	0.000837 U	0.000349 UJ
	IW-47B-55	3/22/18	PES	ESC	55	-3.2	S	0.000355 U	0.000229 U	0.000403 U	0.00102 U	0.000248 U	0.000405 U	**3.47 J**	0.000283 U	0.000413 U	0.000275 U	0.000771 U	0.000321 UJ
	IW-47B-60	3/22/18	PES	ESC	60	-8.2	S	0.000375 U	0.000242 U	0.000426 U	0.00108 U	0.000262 U	0.000429 U	**0.348 J**	0.000300 U	0.000437 U	0.000290 U	0.000815 U	0.000340 UJ
	IW-47B-65	3/22/18	PES	ESC	65	-13.2	S	0.000370 U	0.000239 U	0.000421 U	0.00107 U	0.000259 U	0.000423 U	**0.119 J**	0.000296 U	0.000431 U	0.000287 U	0.000805 U	0.000335 UJ
	IW-47B-70	3/22/18	PES	ESC	70	-18.2	S	0.000366 U	0.000237 U	0.000416 U	0.00106 U	0.000256 U	0.000419 U	**2.21 J**	0.000292 U	0.000426 U	0.000284 U	0.000796 U	0.000332 UJ
	IW-47B-75	3/22/18	PES	ESC	75	-23.2	S	0.000365 U	0.000236 U	0.000415 U	0.00105 U	0.000255 U	0.000417 U	**0.00197 J**	0.000292 U	0.000425 U	0.000283 U	0.000793 U	0.000331 UJ

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
IW-48B	IW-48B-5	3/23/18	PES	ESC	5	46.7	V	0.000379 U	0.000245 U	0.000431 U	0.00109 U	0.000265 U	0.000433 U	0.000272 U	0.000303 U	0.000441 U	0.000294 U	0.000824 U	0.000343 U
(-9.4 to-24.4)	IW-48B-10	3/23/18	PES	ESC	10	41.7	V	0.000371 U	0.000240 U	0.000422 U	0.00107 U	0.000259 U	0.000425 U	**0.00100 J**	0.000297 U	0.000432 U	0.000288 U	0.000807 U	0.000336 U
	IW-48B-15	3/23/18	PES	ESC	15	36.7	V	0.000383 U	0.000248 U	0.000435 U	0.00110 U	0.000267 U	0.000438 U	**0.000585 J**	0.000306 U	0.000446 U	0.000297 U	0.000832 U	0.000347 U
	IW-48B-20	3/23/18	PES	ESC	20	31.7	S	0.000361 U	0.000233 U	0.000410 U	0.00104 U	0.000252 U	0.000413 U	**0.00149**	0.000288 U	0.000420 U	0.000279 U	0.000785 U	0.000327 U
	IW-48B-25	3/23/18	PES	ESC	25	26.7	S	0.000369 U	0.000239 U	0.000420 U	0.00107 U	0.000258 U	0.000422 U	**0.00777**	0.000295 U	0.000430 U	0.000286 U	0.000803 U	0.000334 U
	IW-48B-30	3/23/18	PES	ESC	30	21.7	S	0.000362 U	0.000234 U	0.000411 U	0.00104 U	0.000252 U	0.000413 U	**0.00569**	0.000289 U	0.000421 U	0.000280 U	0.000786 U	0.000327 U
	IW-48B-35	3/23/18	PES	ESC	35	16.7	S	0.000377 U	0.000244 U	0.000429 U	0.00109 U	0.000263 U	0.000431 U	**0.0901**	0.000301 U	0.000440 U	0.000292 U	0.000820 U	0.000342 U
	IW-48B-40	3/23/18	PES	ESC	40	11.7	S	0.000358 U	0.000231 U	0.000407 U	0.00103 U	0.000250 U	0.000409 U	**0.000350 J**	0.000286 U	0.000417 U	0.000277 U	0.000778 U	0.000324 U
	IW-48B-42	3/23/18	PES	ESC	42	9.7	S	0.000361 U	0.000234 U	0.000411 U	0.00104 U	0.000252 U	0.000413 U	**0.0110**	0.000289 U	0.000421 U	0.000280 U	0.000786 U	0.000327 U
	IW-905-42	3/23/18	PES	ESC	42 (dup)	9.7	S	0.000358 U	0.000232 U	0.000407 U	0.00103 U	0.000250 U	0.000410 U	**0.00820**	0.000286 U	0.000417 U	0.000277 U	0.000779 U	0.000324 U
	IW-48B-45	3/23/18	PES	ESC	45	6.7	S	0.000356 U	0.000230 U	0.000405 U	0.00103 U	0.000248 U	0.000407 U	**0.00156**	0.000284 U	0.000414 U	0.000276 U	0.000774 U	0.000322 U
	IW-48B-50	3/23/18	PES	ESC	50	1.7	S	0.000362 U	0.000234 U	0.000412 U	0.00104 U	0.000253 U	0.000414 U	**0.00420**	0.000289 U	0.000422 U	0.000280 U	0.000787 U	0.000328 U
	IW-48B-55	3/23/18	PES	ESC	55	-3.3	S	0.000355 U	0.000230 U	0.000404 U	0.00103 U	0.000249 U	0.000406 U	**0.148**	0.000284 U	0.000415 U	0.000275 U	0.000773 U	0.000322 U
	IW-48B-60	3/23/18	PES	ESC	60	-8.3	S	0.000363 U	0.000235 U	0.000413 U	0.00105 U	0.000253 U	0.000415 U	**3.47**	0.000290 U	0.000423 U	0.000281 U	0.000789 U	0.000329 U
	IW-48B-65	3/23/18	PES	ESC	65	-13.3	S	0.000388 U	0.000250 U	0.000441 U	0.00112 U	0.000271 U	0.000443 U	**0.121**	0.000310 U	0.000451 U	0.000300 U	0.000842 U	0.000351 U
	IW-48B-70	3/23/18	PES	ESC	70	-18.3	S	0.000361 U	0.000233 U	0.000410 U	0.00104 U	0.000252 U	0.000412 U	**0.00825**	0.000288 U	0.000420 U	0.000279 U	0.000784 U	0.000326 U
	IW-48B-75	3/23/18	PES	ESC	75	-23.3	S	0.000369 U	0.000238 U	0.000419 U	0.00106 U	0.000258 U	0.000422 U	**0.0303**	0.000295 U	0.000430 U	0.000286 U	0.000802 U	0.000334 U
IW-50A	IW-50A-5	3/27/18	PES	ESC	5	46.9	V	0.000374 U	0.000242 U	0.000426 U	0.00108 U	0.000261 U	0.000428 U	0.000268 U	0.000299 U	0.000436 U	0.000290 U	0.000814 U	0.000339 U
(9.8 to-10.2)	IW-50A-10	3/27/18	PES	ESC	10	41.9	V	0.000366 U	0.000236 U	0.000416 U	0.00105 U	0.000255 U	0.000418 U	**0.00210**	0.000292 U	0.000426 U	0.000283 U	0.000795 U	0.000331 U
	IW-50A-15	3/27/18	PES	ESC	15	36.9	V	0.000360 U	0.000233 U	0.000410 U	0.00104 U	0.000252 U	0.000412 U	**0.00185**	0.000288 U	0.000420 U	0.000279 U	0.000783 U	0.000326 U
	IW-50A-20	3/27/18	PES	ESC	20	31.9	S	0.000365 U	0.000236 U	0.000415 U	0.00105 U	0.000255 U	0.000417 U	**0.0300**	0.000291 U	0.000425 U	0.000282 U	0.000792 U	0.000330 U
	IW-50A-25	3/27/18	PES	ESC	25	26.9	S	0.000355 U	0.000229 U	0.000404 U	0.00102 U	0.000248 U	0.000406 U	**0.0836**	0.000284 U	0.000413 U	0.000275 U	0.000772 U	0.000321 U
	IW-50A-30	3/27/18	PES	ESC	30	21.9	S	0.000356 U	0.000230 U	0.000405 U	0.00103 U	0.000249 U	0.000407 U	**0.0103**	0.000285 U	0.000415 U	0.000276 U	0.000774 U	0.000323 U
	IW-50A-35	3/27/18	PES	ESC	35	16.9	S	0.000357 U	0.000231 U	0.000406 U	0.00103 U	0.000249 U	0.000408 U	**0.0158**	0.000285 U	0.000416 U	0.000277 U	0.000776 U	0.000323 U
	IW-50A-40	3/27/18	PES	ESC	40	11.9	S	0.000362 U	0.000234 U	0.000412 U	0.00105 U	0.000253 U	0.000414 U	**0.0273**	0.000289 U	0.000422 U	0.000281 U	0.000788 U	0.000328 U
	IW-50A-42	3/27/18	PES	ESC	42	9.9	S	0.000360 U	0.000233 U	0.000410 U	0.00104 U	0.000252 U	0.000412 U	**0.0970**	0.000288 U	0.000420 U	0.000279 U	0.000783 U	0.000326 U
	IW-50A-45	3/27/18	PES	ESC	45	6.9	S	0.000363 U	0.000235 U	0.000413 U	0.00105 U	0.000254 U	0.000415 U	**0.350**	0.000290 U	0.000423 U	0.000281 U	0.000789 U	0.000329 U
	IW-50A-50	3/27/18	PES	ESC	50	1.9	S	0.000368 U	0.000238 U	0.000418 U	0.00106 U	0.000257 U	0.000421 U	**0.621 J**	0.000294 U	0.000429 U	0.000285 U	0.000800 U	0.000333 U
	IW-906-50	3/27/18	PES	ESC	50 (dup)	1.9	S	0.000370 U	0.000239 U	0.000421 U	0.00107 U	0.000259 U	0.000423 U	**0.121 J**	0.000296 U	0.000431 U	0.000287 U	0.000805 U	0.000335 U
	IW-50A-55	3/27/18	PES	ESC	55	-3.2	S	0.000369 U	0.000239 U	0.000420 U	0.00106 U	0.000258 U	0.000422 U	**0.0706**	0.000295 U	0.000430 U	0.000286 U	0.000802 U	0.000334 U
	IW-50A-60	3/27/18	PES	ESC	60	-8.2	S	0.000370 U	0.000239 U	0.000421 U	0.00107 U	0.000259 U	0.000424 U	**0.00646**	0.000296 U	0.000431 U	0.000287 U	0.000805 U	0.000335 U
IW-51A	IW-51A-5	3/26/18	PES	ESC	5	46.9	V	0.000361 U	0.000233 U	0.000410 U	0.00104 U	0.000252 U	0.000412 U	**0.000359 J**	0.000288 U	0.000420 U	0.000279 U	0.000784 U	0.000327 U
(9.9 to-10.1)	IW-51A-10	3/26/18	PES	ESC	10	41.9	V	0.000358 U	0.000231 U	0.000407 U	0.00103 U	0.000250 U	0.000409 U	0.000256 U	0.000286 U	0.000417 U	0.000277 U	0.000778 U	0.000324 U
	IW-51A-15	3/26/18	PES	ESC	15	36.9	V	0.000372 U	0.000240 U	0.000423 U	0.00107 U	0.000260 U	0.000425 U	**0.000778 J**	0.000297 U	0.000433 U	0.000288 U	0.000809 U	0.000337 U
	IW-51A-20	3/26/18	PES	ESC	20	31.9	S	0.000355 U	0.000230 U	0.000404 U	0.00102 U	0.000248 U	0.000406 U	**0.000759 J**	0.000284 U	0.000414 U	0.000275 U	0.000772 U	0.000322 U
	IW-51A-25	3/26/18	PES	ESC	25	26.9	S	0.000453 U	0.000292 U	0.000514 U	0.00130 U	0.000316 U	0.000517 U	**0.0670**	0.000361 U	0.000527 U	0.000350 U	0.000984 U	0.000410 U
	IW-51A-30	3/26/18	PES	ESC	30	21.9	S	0.000353 U	0.000228 U	0.000402 U	0.00102 U	0.000247 U	0.000404 U	**0.00590**	0.000282 U	0.000412 U	0.000274 U	0.000768 U	0.000320 U
	IW-51A-35	3/26/18	PES	ESC	35	16.9	S	0.000357 U	0.000231 U	0.000406 U	0.00103 U	0.000249 U	0.000408 U	**0.00305**	0.000285 U	0.000416 U	0.000277 U	0.000776 U	0.000323 U
	IW-51A-40	3/26/18	PES	ESC	40	11.9	S	0.000358 U	0.000232 U	0.000407 U	0.00103 U	0.000250 U	0.000410 U	**2.17**	0.000286 U	0.000417 U	0.000277 U	0.000779 U	0.000324 U
	IW-51A-42	3/26/18	PES	ESC	42	9.9	S	0.000365 U	0.000236 U	0.000415 U	0.00105 U	0.000255 U	0.000417 U	**2.37**	0.000292 U	0.000425 U	0.000283 U	0.000794 U	0.000331 U
	IW-51A-45	3/26/18	PES	ESC	45	6.9	S	0.000365 U	0.000236 U	0.000415 U	0.00105 U	0.000255 U	0.000418 U	**0.0456**	0.000292 U	0.000425 U	0.000283 U	0.000794 U	0.000331 U
	IW-51A-50	3/26/18	PES	ESC	50	1.9	S	0.000376 U	0.000243 U	0.000427 U	0.00108 U	0.000262 U	0.000430 U	**2.06**	0.000300 U	0.000438 U	0.000291 U	0.000817 U	0.000340 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
IW-51A (continued)	IW-51A-55	3/26/18	PES	ESC	55	-3.1	S	0.000376 U	0.000243 U	0.000428 U	0.00108 U	0.000263 U	0.000430 U	**0.729**	0.000300 U	0.000438 U	0.000291 U	0.000817 U	0.000340 U
	IW-51A-60	3/26/18	PES	ESC	60	-8.1	S	0.000353 U	0.000228 U	0.000401 U	0.00102 U	0.000246 U	0.000403 U	**0.00129**	0.000282 U	0.000411 U	0.000273 U	0.000767 U	0.000319 U
	IW-51A-62	3/26/18	PES	ESC	62	-10.1	S	0.000357 U	0.000231 U	0.000406 U	0.00103 U	0.000249 U	0.000408 U	**0.00180**	0.000285 U	0.000415 U	0.000276 U	0.000776 U	0.000323 U
IW-53B (-11.1 to-26.1)	IW-53B-30	9/20/18	PES	ESC	30	5.3	S	0.00117 U	0.000623 U	0.000490 U	0.00117 U	0.000451 U	0.00151 U	**0.171**	0.000738 U	0.00109 U	0.000857 U	0.000890 U	**0.000610**
IW-54A (9.8 to-10.2)	IW-54A-8	9/12/18	PES	ESC	8	31.1	S	0.00125 U	0.000661 U	0.000519 U	0.249 U	0.000479 U	0.00160 U	**0.00700**	0.000783 U	0.00115 U	0.000910 U	0.000944 U	0.000612 U
	IW-54A-49	9/12/18	PES	ESC	49	-9.9	S	0.00125 U	0.000664 U	0.000521 U	0.00125 U	0.000481 U	0.00161 U	0.000799 U	0.000785 U	0.00116 U	0.000913 U	0.000947 U	0.000614 U
IW-54B (-9.5 to-24.5)	IW-54B-8	9/5/18	PES	ESC	8	31.2	S	0.00118 U	0.000625 U	0.000491 U	0.00118 U	0.000453 U	0.00152 U	1.51 U	0.000740 U	0.00109 U	0.000860 U	0.000892 U	**0.00226 J**
	IW-54B-13	9/6/18	PES	ESC	13	26.2	S	0.00120 U	0.000636 U	0.000499 U	0.00120 U	0.000460 U	0.00154 U	**0.0349**	0.000752 U	0.00111 U	0.000874 U	0.000907 U	0.000588 U
	IW-54B-21	9/6/18	PES	ESC	21	18.2	S	0.00118 U	0.000625 U	0.000491 U	0.00118 U	0.000453 U	0.00152 U	**1.90**	0.000740 U	0.00109 U	0.000860 U	0.000893 U	0.000578 U
	IW-54B-33	9/6/18	PES	ESC	33	6.2	S	0.00134 U	0.000716 U	0.000563 U	0.00134 U	0.000519 U	0.00173 U	**1.02**	0.000848 U	0.00125 U	0.000985 U	0.00102 U	0.000663 U
IW-55B (-12.0 to-27.0)	IW-55B-39	9/13/18	PES	ESC	39	12.8	S	0.00115 U	0.000608 U	0.000478 U	0.00115 U	0.000441 U	0.00148 U	**0.0320**	0.000720 U	0.00106 U	0.000837 U	0.000869 U	0.000563 U
	IW-55B-43	9/13/18	PES	ESC	43	8.8	S	0.00122 U	0.000648 U	0.000509 U	0.0977 U	0.000469 U	0.00157 U	**1.06**	0.000767 U	0.00113 U	0.000891 U	0.000925 U	0.000600 U
	IW-55B-61	9/13/18	PES	ESC	61	-9.2	S	0.00128 U	0.000681 U	0.000535 U	0.0103 U	0.000493 U	0.00165 U	**3.42**	0.000805 U	0.00119 U	0.000936 U	0.000972 U	**0.000966 J**
IW-58A (3.9 to-11.1)	IW-58A-38	10/17/18	PES	PACE	38	1.2	S	0.00118 U	0.000626 U	0.000492 U	0.00118 U	0.000454 U	0.00152 U	**1.48**	0.000741 U	0.00109 U	0.000861 U	0.00894 U	0.000579 U
	B-929-38	10/17/18	PES	PACE	38 (dup)	1.2	S	0.00122 U	0.000645 U	0.000507 U	0.00122 U	0.000467 U	0.00156 U	**1.77**	0.000763 U	0.00113 U	0.000887 U	0.00921 U	0.000597 U
MW101 (B101) (-65.5 to-75.5)	B101-30	7/10/12	SES	F&BI	30	9.5	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	B101-34	7/10/12	SES	F&BI	34	5.5	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	B101-40	7/10/12	SES	F&BI	40	-0.5	S	–	–	–	–	–	–	**0.064**	–	–	–	–	–
	B101-47	7/10/12	SES	F&BI	47	-7.5	S	–	–	–	–	–	–	**0.12**	–	–	–	–	–
	B101-48	7/10/12	SES	F&BI	48	-8.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B101-55	7/10/12	SES	F&BI	55	-15.5	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	B101-65	7/10/12	SES	F&BI	65	-25.5	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	B101-75	7/11/12	SES	F&BI	75	-35.5	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	B101-81	7/11/12	SES	F&BI	81	-41.5	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	B101-92	7/12/12	SES	F&BI	92	-52.5	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	B101-97	7/12/12	SES	F&BI	97	-57.5	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	B101-104	7/12/12	SES	F&BI	104	-64.5	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	B101-114.5	7/12/12	SES	F&BI	114.5	-75.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	B101-120	7/12/12	SES	F&BI	120	-80.5	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	B101-131	7/12/12	SES	F&BI	131	-91.5	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	B101-140	7/12/12	SES	F&BI	140	-100.5	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
MW130 (B130) (-30.9 to-40.9)	B130-10	3/1/16	SES	F&BI	10	29.5	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	B130-20	3/1/16	SES	F&BI	20	19.5	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	B130-30	3/1/16	SES	F&BI	30	9.5	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	B130-40	3/1/16	SES	F&BI	40	-0.5	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	B130-45	3/2/16	SES	F&BI	45	-5.5	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	B130-50	3/2/16	SES	F&BI	50	-10.5	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	B130-55	3/2/16	SES	F&BI	55	-15.5	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	B130-60	3/2/16	SES	F&BI	60	-20.5	S	–	–	–	–	–	–	**1.2**	–	–	–	–	–
	B130-65	3/2/16	SES	F&BI	65	-25.5	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	B130-70	3/2/16	SES	F&BI	70	-30.5	S	–	–	–	–	–	–	**0.073**	–	–	–	–	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	**–**	**0.074**	**–**	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	**–**	**0.007**	**–**	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
MW130 (B130)	B130-75	3/2/16	SES	F&BI	75	-35.5	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
(continued)	B130-80	3/2/16	SES	F&BI	80	-40.5	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
MW131 (B131)	B131-10	3/1/16	SES	F&BI	10	30.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
(-4.2 to-14.2)	B131-20	3/1/16	SES	F&BI	20	20.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	B131-30	3/1/16	SES	F&BI	30	10.0	S	–	–	–	–	–	–	**3.2**	–	–	–	–	–
	B131-40	3/1/16	SES	F&BI	40	0.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	B131-45	3/2/16	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	**0.069**	–	–	–	–	–
	B131-55	3/2/16	SES	F&BI	55	-15.0	S	–	–	–	–	–	–	**0.55**	–	–	–	–	–
MW-132	MW-132-20	8/22/17	PES	ESC	20	20.1	S	0.000366 U	0.000236 U	0.000416 U	0.00105 U	0.000255 U	0.000418 U	**0.0108**	0.000292 U	0.000426 U	0.000283 U	0.000795 U	0.000331 U
(-29.9 to-39.9)	MW-132-35	8/22/17	PES	ESC	35	5.1	S	0.000367 U	0.000237 U	0.000417 U	0.00106 U	0.000256 U	0.000420 U	**0.00506**	0.000293 U	0.000427 U	0.000284 U	0.000798 U	0.000332 U
	MW-132-50	8/22/17	PES	ESC	50	-9.9	S	0.000355 U	0.000229 U	0.000404 U	0.00102 U	0.000248 U	0.000406 U	**4.62**	0.000283 U	0.000413 U	0.000275 U	0.000771 U	0.000321 U
	MW-132-55	8/23/17	PES	ESC	55	-14.9	S	0.0377 U	0.0244 U	0.0429 U	0.109 U	0.0263 U	0.0431 U	**2.22**	0.0301 U	0.0439 U	0.0292 U	0.0820 U	0.0342 U
	MW-132-60	8/23/17	PES	ESC	60	-19.9	S	0.000353 U	0.000228 U	0.000402 U	0.00102 U	0.000247 U	0.000404 U	**0.0871**	0.000282 U	0.000411 U	0.000274 U	0.000768 U	0.000320 U
	MW-132-70	8/23/17	PES	ESC	70	-29.9	S	0.000400 U	0.000258 U	0.000455 U	0.00115 U	0.000279 U	0.000457 U	**0.000586 J**	0.000319 U	0.000466 U	0.000310 U	0.000869 U	0.000362 U
	MW-132-83	8/23/17	PES	ESC	83	-42.9	S	0.000358 U	0.000231 U	0.000407 U	0.00103 U	0.000250 U	0.000409 U	**0.000283 J**	0.000286 U	0.000417 U	0.000277 U	0.000778 U	0.000324 U
MW-133	MW-133-20	8/15/17	PES	ESC	20	20.1	S	0.000387 U	0.000250 U	0.000440 U	0.00111 U	0.000270 U	0.000442 U	**0.159**	0.000309 U	0.000450 U	0.000299 U	0.000840 U	0.000350 U
(-88.9 to-98.9)	MW-133-35	8/15/17	PES	ESC	35	5.1	S	0.000428 U	0.000277 U	0.000487 U	0.00124 U	0.000299 U	0.000490 U	**0.000361 J**	0.000342 U	0.000499 U	0.000332 U	0.000931 U	0.000388 U
	MW-133-45	8/15/17	PES	ESC	45	-4.9	S	0.000356 U	0.000230 U	0.000405 U	0.00103 U	0.000249 U	0.000408 U	**13.0**	0.000285 U	0.000415 U	0.000276 U	0.000775 U	0.000323 U
	MW-133-55	8/15/17	PES	ESC	55	-14.9	S	0.0802 U	0.0519 U	0.0912 U	0.231 U	0.0560 U	0.0917 U	**4.09**	0.0641 U	0.0935 U	0.0621 U	0.175 U	0.0727 U
	MW-133-58	8/15/17	PES	ESC	58	-17.9	S	1.94 U	1.25 U	2.20 U	5.59 U	1.35 U	2.22 U	1.40 U	1.55 U	2.26 U	1.50 U	4.21 U	1.75 U
	MW-133-65	8/15/17	PES	ESC	65	-24.9	S	0.000380 U	0.000245 U	0.000432 U	0.00109 U	0.000265 U	0.000434 U	**1.41**	0.000303 U	0.000442 U	0.000294 U	0.000825 U	0.000344 U
	MW-133-75	8/15/17	PES	ESC	75	-34.9	S	0.000382 U	0.000247 U	0.000434 U	0.00110 U	0.000266 U	0.000436 U	**0.00191**	0.000305 U	0.000444 U	0.000295 U	0.000829 U	0.000346 U
	MW-133-85	8/15/17	PES	ESC	85	-44.9	S	0.00961 U	0.00621 U	0.0109 U	0.0277 U	0.00671 U	0.0110 U	**0.0717**	0.00768 U	0.0112 U	0.00744 U	0.0209 U	0.00870 U
	MW-133-95	8/16/17	PES	ESC	95	-54.9	S	0.000382 U	0.000247 U	0.000435 U	0.00110 U	0.000267 U	0.000437 U	0.000274 U	0.000305 U	0.000445 U	0.000296 U	0.000831 U	0.000346 U
	MW-133-105	8/16/17	PES	ESC	105	-64.9	S	0.000395 U	0.000255 U	0.000449 U	0.00114 U	0.000276 U	0.000452 U	0.000283 U	0.000315 U	0.000460 U	0.000306 U	0.000858 U	0.000358 U
	MW-133-120	8/16/17	PES	ESC	120	-79.9	S	0.00891 U	0.00576 U	0.0101 U	0.0256 U	0.00622 U	0.0102 U	0.00639 U	0.00712 U	0.0104 U	0.00690 U	0.0193 U	0.00806 U
	MW-133-130	8/16/17	PES	ESC	130	-89.9	S	0.000391 U	0.000253 U	0.000444 U	0.00113 U	0.000273 U	0.000447 U	**0.000888 J**	0.000312 U	0.000455 U	0.000303 U	0.000849 U	0.000354 U
	MW-133-135	8/16/17	PES	ESC	135	-94.9	S	0.000372 U	0.000240 U	0.000423 U	0.00107 U	0.000259 U	0.000425 U	**0.000836 J**	0.000297 U	0.000433 U	0.000288 U	0.000808 U	**0.00179**
	MW-133-141	8/16/17	PES	ESC	141	-100.9	S	0.000369 U	0.000239 U	0.000420 U	0.00107 U	0.000258 U	0.000422 U	0.000265 U	0.000295 U	0.000430 U	0.000286 U	0.000803 U	0.000334 U
MW-134	MW-134-20	8/29/17	PES	ESC	20	21.5	S	0.000432 U	0.000279 U	0.000491 U	0.00124 U	0.000301 U	0.000494 U	0.000309 U	0.000345 U	0.000503 U	0.000334 U	0.000938 U	0.000391 U
(-38.6 to-48.6)	MW-134-43	8/29/17	PES	ESC	43	-1.6	S	0.00951 U	0.000246 U	0.000433 U	**0.00137 J**	0.000266 U	0.0109 U	**2.58**	0.000304 U	0.000443 U	0.000295 U	0.000827 U	0.000345 U
	MW-134-50	8/29/17	PES	ESC	50	-8.6	S	0.0361 U	0.000233 U	0.000410 U	0.00104 U	0.000252 U	0.0412 U	**0.740**	0.000288 U	0.000420 U	0.000279 U	0.000784 U	0.000327 U
	MW-134-60	8/29/17	PES	ESC	60	-18.6	S	0.00906 U	0.000234 U	0.000412 U	0.00104 U	0.000253 U	0.0104 U	**4.46**	0.000289 U	0.000422 U	0.000280 U	0.000787 U	0.000328 U
	MW-134-70	8/29/17	PES	ESC	70	-28.6	S	0.000418 U	0.000270 U	0.000476 U	0.00121 U	0.000292 U	**0.00219 J**	**0.0468**	0.000334 U	0.000487 U	0.000324 U	0.000910 U	0.000379 U
	MW-134-80	8/29/17	PES	ESC	80	-38.6	S	0.000351 U	0.000227 U	0.000399 U	0.00101 U	0.000245 U	**0.00164 J**	**0.0119 J**	0.000280 U	0.000409 U	0.000272 U	0.000763 U	0.000318 U
	B-903-100	8/29/17	PES	ESC	80 (dup)	-38.6	S	0.000346 U	0.000223 U	0.000393 U	0.000997 U	0.000241 U	**0.00171 J**	**0.0725 J**	0.000276 U	0.000402 U	0.000268 U	0.000751 U	0.000313 U
	MW-134-90	8/29/17	PES	ESC	90	-48.6	S	0.0104 U	0.000269 U	0.000474 U	0.00120 U	0.000291 U	0.0119 U	0.00747 U	0.000333 U	0.000485 U	0.000323 U	0.000905 U	0.000377 U
MW-135	MW-135-16	8/24/17	PES	ESC	14	25.1	S	0.0400 U	0.0259 U	0.0455 U	0.115 U	0.0279 U	0.0457 U	**329**	0.0320 U	0.0466 U	0.0310 U	0.0870 U	**0.0750 J**
(-30.9 to-40.9)	MW-135-20	8/24/17	PES	ESC	20	19.1	S	0.00934 U	0.00604 U	0.0106 U	0.0269 U	0.00651 U	0.0107 U	**0.408**	0.00746 U	0.0109 U	0.00723 U	0.0203 U	0.00845 U
	MW-135-30	8/24/17	PES	ESC	30	9.1	S	0.000348 U	0.000225 U	0.000396 U	0.00100 U	0.000243 U	0.000398 U	**1.98**	0.000278 U	0.000406 U	0.000270 U	0.000757 U	0.000315 U
	MW-135-36	8/24/17	PES	ESC	36	3.1	S	0.000383 U	0.000248 U	0.000435 U	0.00110 U	0.000267 U	0.000438 U	**0.154**	0.000306 U	0.000446 U	0.000297 U	0.000832 U	0.000347 U
	MW-135-40	8/24/17	PES	ESC	40	-0.9	S	0.000391 U	0.000253 U	0.000445 U	0.00113 U	0.000273 U	0.000447 U	**12.8**	0.000312 U	0.000456 U	0.000303 U	0.000850 U	0.000354 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
MW-135 (continued)	MW-135-45	8/24/17	PES	ESC	45	-5.9	S	0.000389 U	0.000252 U	0.000443 U	0.00112 U	0.000272 U	0.000445 U	**5.35**	0.000311 U	0.000454 U	0.000302 U	0.000847 U	0.000353 U
	MW-135-55	8/24/17	PES	ESC	55	-15.9	S	0.000356 U	0.000230 U	0.000405 U	0.00103 U	0.000249 U	0.000407 U	**0.0594**	0.000285 U	0.000415 U	0.000276 U	0.000775 U	0.000323 U
	MW-135-65	8/24/17	PES	ESC	65	-25.9	S	0.000389 U	0.000252 U	0.000443 U	0.00112 U	0.000272 U	0.000445 U	**0.0170**	0.000311 U	0.000453 U	0.000301 U	0.000846 U	0.000352 U
	MW-135-80	8/24/17	PES	ESC	80	-40.9	S	0.000366 U	0.000237 U	0.000417 U	0.00106 U	0.000256 U	0.000419 U	**0.00115**	0.000293 U	0.000427 U	0.000284 U	0.000796 U	0.000332 U
MW-136 (-32.7 to-42.7)	MW-136-35	8/28/17	PES	ESC	35	16.9	S	0.000345 U	0.000223 U	0.000393 U	0.000996 U	0.000241 U	0.000395 U	**0.0117**	0.000276 U	0.000402 U	0.000267 U	0.000750 U	0.000313 U
	B-902-15	8/28/17	PES	ESC	35 (dup)	16.9	S	0.000358 U	0.000232 U	0.000407 U	0.00103 U	0.000250 U	0.000410 U	**0.0141**	0.000286 U	0.000417 U	0.000277 U	0.000779 U	0.000324 U
	MW-136-44	8/28/17	PES	ESC	44	7.9	S	0.000368 U	0.000238 U	0.000419 U	0.00106 U	0.000257 U	0.000421 U	**0.0174**	0.000294 U	0.000429 U	0.000285 U	0.000800 U	0.000333 U
	MW-136-50	8/28/17	PES	ESC	50	1.9	S	0.00944 U	0.000244 U	0.000429 U	0.00109 U	0.000264 U	0.0108 U	0.00677 U	0.000301 U	0.000440 U	0.000292 U	0.000820 U	0.000342 U
	MW-136-65	8/28/17	PES	ESC	65	-13.1	S	0.000357 U	0.000231 U	0.000406 U	0.00103 U	0.000249 U	0.000408 U	0.000256 U	0.000285 U	0.000415 U	0.000276 U	0.000775 U	0.000323 U
	MW-136-75	8/28/17	PES	ESC	75	-23.1	S	0.000364 U	0.000236 U	0.000414 U	0.00105 U	0.000254 U	0.000417 U	0.000261 U	0.000291 U	0.000424 U	0.000282 U	0.000792 U	0.000330 U
	MW-136-85	8/28/17	PES	ESC	85	-33.1	S	0.000366 U	0.000237 U	0.000416 U	0.00106 U	0.000256 U	0.000419 U	0.000262 U	0.000292 U	0.000426 U	0.000284 U	0.000796 U	0.000332 U
	MW-136-95	8/28/17	PES	ESC	95	-43.1	S	0.000367 U	0.000237 U	0.000417 U	0.00106 U	0.000256 U	0.000420 U	0.000263 U	0.000293 U	0.000427 U	0.000284 U	0.000798 U	0.000332 U
MW-137 (-53.3 to-63.3)	MW-137-25	8/31/17	PES	ESC	25	26.7	S	0.000358 U	0.000231 U	0.000407 U	0.00103 U	0.000250 U	0.000409 U	**0.000783 J**	0.000286 U	0.000417 U	0.000277 U	0.000778 U	0.000324 U
	MW-137-45	8/31/17	PES	ESC	45	6.7	S	0.00928 U	0.00600 U	0.0105 U	0.0267 U	0.00647 U	0.0106 U	**0.00753 J**	0.00741 U	0.0108 U	0.00719 U	0.0201 U	0.00840 U
	MW-137-75	8/31/17	PES	ESC	75	-23.3	S	0.000360 U	0.000233 U	0.000410 U	0.00104 U	0.000251 U	0.000412 U	0.000258 U	0.000288 U	0.000419 U	0.000279 U	0.000783 U	0.000326 U
	MW-137-85	9/1/17	PES	ESC	85	-33.3	S	0.000393 U	0.000254 U	0.000447 U	0.00113 U	0.000274 U	0.000449 U	0.000282 U	0.000314 U	0.000458 U	0.000304 U	0.000855 U	0.000356 U
	MW-137-95	9/1/17	PES	ESC	95	-43.3	S	0.000351 U	0.000227 U	0.000399 U	0.00101 U	0.000245 U	0.000402 U	0.000252 U	0.000281 U	0.000409 U	0.000272 U	0.000764 U	0.000318 U
	MW-137-115	9/1/17	PES	ESC	115	-63.3	S	0.000401 U	0.000259 U	0.000456 U	0.00116 U	0.000280 U	0.000459 U	0.000287 U	0.000321 U	0.000467 U	0.000311 U	0.000872 U	0.000363 U
MW-139 (-30.2 to-40.2)	MW-139-20	9/13/17	PES	ESC	20	19.8	S	0.000379 U	0.000245 U	0.000431 U	0.00109 U	0.000265 U	0.000434 U	**0.000500 J**	0.000303 U	0.000442 U	0.000294 U	0.000825 U	0.000344 U
	MW-139-31	9/13/17	PES	ESC	31	8.8	S	0.000351 U	0.000227 U	0.000399 U	0.00101 U	0.000245 U	0.000401 U	**0.00814**	0.000280 U	0.000409 U	0.000272 U	0.000763 U	0.000318 U
	MW-139-41	9/13/17	PES	ESC	41	-1.2	S	0.000352 U	0.000228 U	0.000401 U	0.00102 U	0.000246 U	0.000403 U	**0.0982**	0.000281 U	0.000410 U	0.000273 U	0.000766 U	0.000319 U
	MW-139-51	9/13/17	PES	ESC	51	-11.2	S	0.000378 U	0.000245 U	0.000430 U	0.00109 U	0.000264 U	0.000433 U	**0.000763 J**	0.000302 U	0.000441 U	0.000293 U	0.000823 U	0.000343 U
	MW-139-60	9/13/17	PES	ESC	60	-20.2	S	0.000352 U	0.000228 U	0.000401 U	0.00102 U	0.000246 U	0.000403 U	0.000252 U	0.000281 U	0.000410 U	0.000273 U	0.000766 U	0.000319 U
	MW-139-70	9/13/17	PES	ESC	70	-30.2	S	0.000387 U	0.000250 U	0.000440 U	0.00112 U	0.000270 U	0.000442 U	0.000277 U	0.000309 U	0.000451 U	0.000300 U	0.000841 U	0.000350 U
	MW-139-80	9/13/17	PES	ESC	80	-40.2	S	0.000371 U	0.000240 U	0.000421 U	0.00107 U	0.000259 U	0.000424 U	0.000266 U	0.000296 U	0.000432 U	0.000287 U	0.000806 U	0.000336 U
MW-141 (-55.4 to-65.4)	MW-141-15	9/18/17	PES	ESC	15	24.6	S	0.000370 U	0.000239 U	0.000421 U	0.00107 U	0.000258 U	0.000423 U	**0.00128**	0.000296 U	0.000431 U	0.000287 U	0.000804 U	0.000335 U
	MW-141-35	9/18/17	PES	ESC	35	4.6	S	0.000381 U	0.000246 U	0.000433 U	0.00110 U	0.000266 U	0.000435 U	**0.000473 J**	0.000304 U	0.000443 U	0.000295 U	0.000827 U	0.000345 U
	MW-141-46	9/18/17	PES	ESC	46	-6.4	S	0.000359 U	0.000232 U	0.000408 U	0.00103 U	0.000250 U	0.000410 U	**0.00329**	0.000286 U	0.000418 U	0.000278 U	0.000780 U	0.000325 U
	MW-141-56	9/18/17	PES	ESC	56	-16.4	S	0.000349 U	0.000226 U	0.000397 U	0.00101 U	0.000244 U	0.000399 U	**0.000474 J**	0.000279 U	0.000406 U	0.000270 U	0.000758 U	0.000316 U
	MW-141-65	9/18/17	PES	ESC	65	-25.4	S	0.000345 U	0.000223 U	0.000392 U	0.000995 U	0.000241 U	0.000394 U	0.000247 U	0.000276 U	0.000402 U	0.000267 U	0.000750 U	0.000312 U
	MW-141-75	9/18/17	PES	ESC	75	-35.4	S	0.000350 U	0.000226 U	0.000398 U	0.00101 U	0.000244 U	0.000400 U	0.000251 U	0.000279 U	0.000407 U	0.000271 U	0.000760 U	0.000317 U
	MW-141-85	9/18/17	PES	ESC	85	-45.4	S	0.000383 U	0.000248 U	0.000436 U	0.00110 U	0.000267 U	0.000438 U	0.000274 U	0.000306 U	0.000446 U	0.000297 U	0.000833 U	0.000347 U
	MW-141-95	9/18/17	PES	ESC	95	-55.4	S	0.000393 U	0.000254 U	0.000447 U	0.00113 U	0.000274 U	0.000449 U	0.000281 U	0.000314 U	0.000458 U	0.000304 U	0.000854 U	0.000356 U
	MW-141-105	9/19/17	PES	ESC	105	-65.4	S	0.000392 U	0.000253 U	0.000445 U	0.00113 U	0.000273 U	0.000448 U	0.000281 U	0.000313 U	0.000456 U	0.000303 U	0.000851 U	0.000355 U
MW-152 (-10.2 to-20.2)	MW-152-5	3/13/18	PES	ESC	5	34.1	S	0.000370 U	0.000239 U	0.000420 U	0.00107 U	0.000258 U	0.000423 U	0.000265 U	0.000295 U	0.000430 U	0.000286 U	0.000803 U	0.000335 U
	MW-152-15	3/13/18	PES	ESC	15	24.1	S	0.000363 U	0.000235 U	0.000413 U	0.00105 U	0.000254 U	0.000415 U	**0.00864**	0.000290 U	0.000423 U	0.000281 U	0.000790 U	0.000329 U
	MW-152-25	3/13/18	PES	ESC	25	14.1	S	0.000356 U	0.000230 U	0.000405 U	0.00103 U	0.000248 U	0.000407 U	**1.11**	0.000284 U	0.000414 U	0.000276 U	0.000773 U	0.000322 U
	MW-152-35	3/13/18	PES	ESC	35	4.1	S	0.000360 U	0.000232 U	0.000409 U	0.00104 U	0.000251 U	0.000411 U	**0.776**	0.000287 U	0.000419 U	0.000279 U	0.000782 U	0.000326 U
	MW-152-45	3/13/18	PES	ESC	45	-5.9	S	0.000370 U	0.000239 U	0.000420 U	0.00107 U	0.000258 U	0.000423 U	**7.54**	0.000295 U	0.000431 U	0.000286 U	0.000804 U	0.000335 U
	MW-152-55	3/13/18	PES	ESC	55	-15.9	S	0.000372 U	0.000240 U	0.000422 U	0.00107 U	0.000259 U	0.000425 U	**4.37**	0.000297 U	0.000433 U	0.000288 U	0.000808 U	0.000336 U
	MW-152-60	3/13/18	PES	ESC	60	-20.9	S	0.000355 U	0.000229 U	0.000404 U	0.00102 U	0.000248 U	0.000406 U	**0.167**	0.000283 U	0.000413 U	0.000275 U	0.000771 U	0.000321 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
MW-162 (-61.6 to-71.6)	MW-162-48	1/28/19	PES	PACE	48	-9.6	S	0.0234 U	0.0124 U	0.00974 U	0.0234 U	0.00898 U	0.0301 U	**1.57**	0.0147 U	0.0216 U	0.0171 U	0.0177 U	0.0115 U
	MW-162-50	1/28/19	PES	PACE	50	-11.6	S	0.00126 U	0.000669 U	0.000526 U	0.00126 U	0.000485 U	0.00162 U	**0.766**	0.000792 U	0.00117 U	0.000921 U	0.000956 U	0.000619 U
	B-930-50 (dup)	1/28/19	PES	PACE	50	-11.6	S	0.00120 U	0.000637 U	0.000500 U	0.00120 U	0.000461 U	0.00155 U	**7.57**	0.000754 U	0.00111 U	0.000876 U	0.000909 U	0.000589 U
	MW-162-67	1/28/19	PES	PACE	67	-28.6	S	0.00125 U	0.000666 U	0.000523 U	0.00125 U	0.000482 U	0.00161 U	**0.253**	0.000787 U	0.00116 U	0.000915 U	0.000950 U	0.000616 U
	MW-162-70	1/28/19	PES	PACE	70	-31.6	S	0.00121 U	0.000640 U	0.000502 U	0.00121 U	0.000463 U	0.00155 U	**1.44**	0.000757 U	0.00112 U	0.000880 U	0.000913 U	**0.000641 J**
	MW-162-72	1/28/19	PES	PACE	72	-33.6	S	0.00117 U	0.000618 U	0.000486 U	0.00117 U	0.000448 U	0.00150 U	**0.358**	0.000732 U	0.00108 U	0.000850 U	0.000883 U	0.000572 U
	MW-162-80	1/28/19	PES	PACE	80	-41.6	S	0.00120 U	0.000638 U	0.000501 U	0.00120 U	0.000462 U	0.00155 U	**2.23**	0.000755 U	0.00111 U	0.000877 U	0.000910 U	0.000590 U
	MW-162-85	1/28/19	PES	PACE	85	-46.6	S	0.00122 U	0.000649 U	0.000509 U	0.00122 U	0.000470 U	0.00157 U	**0.0203**	0.000767 U	0.00113 U	0.000892 U	0.000926 U	0.000600 U
	MW-162-90	1/28/19	PES	PACE	90	-51.6	S	0.00122 U	0.000648 U	0.000509 U	0.00122 U	0.000469 U	0.00157 U	**0.0193**	0.000766 U	0.00113 U	0.000891 U	0.000924 U	0.000599 U
	MW-162-95	1/28/19	PES	PACE	95	-56.6	S	0.00124 U	0.000657 U	0.000516 U	0.00124 U	0.000476 U	0.00159 U	**0.0178**	0.000778 U	0.00115 U	0.000904 U	0.000939 U	0.000608 U
	MW-162-100	1/28/19	PES	PACE	100	-61.6	S	0.00126 U	0.000669 U	0.000525 U	0.00126 U	0.000485 U	0.00162 U	**0.00108 J**	0.000792 U	0.00117 U	0.000920 U	0.000955 U	0.000619 U
	MW-162-105	1/28/19	PES	PACE	105	-66.6	S	0.00121 U	0.000644 U	0.000506 U	0.00121 U	0.000466 U	0.00156 U	**0.00206 J**	0.000762 U	0.00112 U	0.000886 U	0.000920 U	0.000596 U
	MW-162-110	1/28/19	PES	PACE	110	-71.6	S	0.00118 U	0.000627 U	0.000493 U	0.00118 U	0.000454 U	0.00152 U	0.000755 U	0.000742 U	0.00109 U	0.000862 U	0.000895 U	0.000580 U
MW-163 (-61.0 to-71.0)	MW-163-47	1/29/19	PES	PACE	47	-7.7	S	0.00121 U	0.000641 U	0.000503 U	0.00121 U	0.000464 U	0.00155 U	**5.83 J**	0.000758 U	0.00112 U	0.000881 U	0.000915 U	0.000593 U
	MW-163-50	1/29/19	PES	PACE	50	-10.7	S	0.00117 U	0.000619 U	0.000486 U	0.00117 U	0.000448 U	0.00150 U	**16.6 J**	0.000732 U	0.00108 U	0.000851 U	0.000884 U	0.000573 U
	MW-163-55	1/29/19	PES	PACE	55	-15.7	S	0.00132 U	0.000703 U	0.000552 U	0.00132 U	0.000509 U	0.00171 U	**6.47 J**	0.000831 U	0.00123 U	0.000965 U	0.00100 U	0.000650 U
	MW-163-60	1/29/19	PES	PACE	60	-20.7	S	0.00122 U	0.000649 U	0.000509 U	0.00122 U	0.000470 U	0.00157 U	**4.64 J**	0.000768 U	0.00113 U	0.000892 U	0.000926 U	0.000600 U
	MW-163-80	1/29/19	PES	PACE	80	-40.7	S	0.00123 U	0.000652 U	0.000512 U	0.00123 U	0.000472 U	0.00158 U	**0.0732**	0.000771 U	0.00114 U	0.000896 U	0.000930 U	0.000603 U
	MW-163-85	1/29/19	PES	PACE	85	-45.7	S	0.00128 U	0.000678 U	0.000533 U	0.00128 U	0.000491 U	0.00165 U	**0.000916 J**	0.000802 U	0.00118 U	0.000933 U	0.000968 U	0.000627 U
	MW-163-90	1/29/19	PES	PACE	90	-50.7	S	0.00117 U	0.000621 U	0.000488 U	0.00117 U	0.000450 U	0.00151 U	**0.136**	0.000735 U	0.00108 U	0.000855 U	0.000887 U	0.000575 U
	MW-163-95	1/29/19	PES	PACE	95	-55.7	S	0.00128 U	0.000679 U	0.000533 U	0.00128 U	0.000492 U	0.00165 U	**0.0255**	0.000804 U	0.00119 U	0.000934 U	0.000970 U	0.000628 U
	MW-163-100	1/29/19	PES	PACE	100	-60.7	S	0.00124 U	0.000658 U	0.000517 U	0.00124 U	0.000477 U	0.00160 U	**0.00269 J**	0.000779 U	0.00115 U	0.000905 U	0.000939 U	0.000609 U
	MW-163-105	1/29/19	PES	PACE	105	-65.7	S	0.00113 U	0.000602 U	0.000472 U	0.00113 U	0.000436 U	0.00146 U	**0.0249**	0.000712 U	0.00105 U	0.000827 U	0.000859 U	0.000556 U
	MW-163-110	1/29/19	PES	PACE	110	-70.7	S	0.00120 U	0.000635 U	0.000499 U	0.00120 U	0.000460 U	0.00154 U	**0.00194 J**	0.000751 U	0.00111 U	0.000873 U	0.000906 U	0.000587 U
MW-164 (-59.9 to-69.9)	MW-164-80	1/24/19	PES	PACE	80	-40.3	S	0.00123 U	0.000652 U	0.000512 U	0.00123 U	**0.00161 J**	0.00158 U	**0.0194**	0.000772 U	0.00114 U	0.000897 U	0.000931 U	0.000603 U
	MW-164-87	1/24/19	PES	PACE	87	-47.3	S	0.00121 U	0.000641 U	0.000504 U	0.00121 U	**0.00159 J**	0.00156 U	**0.00519**	0.000759 U	0.00112 U	0.000882 U	0.000916 U	0.000593 U
	MW-164-90	1/24/19	PES	PACE	90	-50.3	S	0.00126 U	0.000671 U	0.000527 U	0.00126 U	**0.00225 J**	0.00163 U	**0.0870**	0.000794 U	0.00117 U	0.000923 U	0.000958 U	0.000621 U
	MW-164-95	1/25/19	PES	PACE	95	-55.3	S	0.00129 U	0.000685 U	0.000538 U	0.00129 U	**0.00196 J**	0.00166 U	**0.474**	0.000811 U	0.00120 U	0.000942 U	0.000978 U	0.000634 U
	MW-164-100	1/25/19	PES	PACE	100	-60.3	S	0.00135 U	0.000716 U	0.000563 U	0.00135 U	**0.00197 J**	0.00174 U	**0.00428**	0.000848 U	0.00125 U	0.000985 U	0.00102 U	0.000663 U
	MW-164-105	1/25/19	PES	PACE	105	-65.3	S	0.00120 U	0.000635 U	0.000499 U	0.00120 U	0.000460 U	0.00154 U	**0.00442**	0.000752 U	0.00111 U	0.000874 U	0.000907 U	0.000588 U
	MW-164-110	1/25/19	PES	PACE	110	-70.3	S	0.00119 U	0.000632 U	0.000496 U	0.00119 U	0.000458 U	0.00153 U	0.000761 U	0.000748 U	0.00110 U	0.000869 U	0.000902 U	0.000584 U
	B-929-120	1/25/19	PES	PACE	110 (dup)	-70.3	S	0.00121 U	0.000644 U	0.000506 U	0.00121 U	0.000466 U	0.00156 U	**0.00519**	0.000762 U	0.00112 U	0.000885 U	0.000919 U	0.000595 U
MW-168 (-43.0 to -53.0)	MW-168-15	10/21/19	PES	Fremont	15	-3.8	S	–	–	–	–	–	–	**5.98**	–	–	–	–	–
MW-171 (-27.6 to -37.6)	MW-171-24	09/24/19	PES	Fremont	24	-12.8	S	–	–	–	–	–	–	0.160 U	–	–	–	–	–
MW-172 (-42.5 to -52.5)	MW-172-7	09/26/19	PES	Fremont	7	4.2	S	–	–	–	–	–	–	0.188 U	–	–	–	–	–
MW-175 (-27.8 to -37.8)	MW-175-12	10/26/19	PES	Fremont	12	-1.3	S	–	–	–	–	–	–	0.190 U	–	–	–	–	–
	B-1002-12	10/26/19	PES	Fremont	12 (dup)	-1.3	S	–	–	–	–	–	–	**0.0791 J**	–	–	–	–	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	**–**	**0.074**	**–**	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	**–**	**0.007**	**–**	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
MW-180 (-42.7 to -52.7)	MW-180-40	09/25/19	PES	Fremont	40	-28.2	S	–	–	–	–	–	–	**0.851**	–	–	–	–	–
	MW-180-24	09/25/19	PES	Fremont	24	-12.2	S	–	–	–	–	–	–	**30.5**	–	–	–	–	–
	MW-180-27	09/25/19	PES	Fremont	27	-15.2	S	–	–	–	–	–	–	**0.107**	–	–	–	–	–
MW-181 (1.5 to -8.5)	MW-181-14	09/27/19	PES	Fremont	14	-2.5	S	–	–	–	–	–	–	0.216 U	–	–	–	–	–
MW-183 (-27.4 to -37.4)	MW-183-18	09/26/19	PES	Fremont	18	-6.5	S	–	–	–	–	–	–	**6.92**	–	–	–	–	–
MW-184 (-42.5 to -52.5)	MW-184-20	09/26/19	PES	Fremont	20	-8.4	S	–	–	–	–	–	–	**1.32**	–	–	–	–	–
MW-188 (-42.2 to -52.2)	MW-188-64	10/01/19	PES	Fremont	64	-52.4	S	–	–	–	–	–	–	0.200 U	–	–	–	–	–
P01	P01-05	2/12/14	SES	F&BI	5	35.5	S	–	–	–	–	–	–	–	–	–	–	–	0.020 U
	P01-10	2/12/14	SES	F&BI	10	30.5	S	–	–	–	–	–	–	–	–	–	–	–	0.020 U
P02	P02-05	2/12/14	SES	F&BI	5	34.5	S	–	–	–	–	–	–	0.050 U	–	–	–	–	**–**
	P02-07.5	2/12/14	SES	F&BI	7.5	32.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	**–**
P03	P03-05	2/12/14	SES	F&BI	5	34.5	S	–	–	–	–	–	–	0.050 U	–	–	–	–	**–**
P03	P03-07.5	2/12/14	SES	F&BI	7.5	32.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	**–**
P04	P04-05	2/12/14	SES	F&BI	7.5	32.5	S	–	–	–	–	–	–	0.050 U	–	–	–	–	**–**
	P04-10	2/12/14	SES	F&BI	10	30.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	**–**
P05	P05-05	2/12/14	SES	F&BI	5	35.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	**–**
	P05-07.5	2/12/14	SES	F&BI	7.5	32.5	S	–	–	–	–	–	–	0.050 U	–	–	–	–	**–**
P06	P06-07.5	2/12/14	SES	F&BI	7.5	32.5	S	–	–	–	–	–	–	0.050 U	–	–	–	–	**–**
	P06-10	2/12/14	SES	F&BI	10	30.0	S	–	–	–	–	–	–	0.050 U	–	–	–	–	**–**
R-MW1	Unknown	10/22/92	Roux	Unknown	5	32.8	S	–	–	–	–	–	–	**–**	–	–	–	–	**–**
W-MW-03 (P-07)	SB-W-07-0135	1/26/12	WW	ARI	13.5-14	25.2	S	–	–	–	–	–	–	**0.0008 J**	–	–	–	–	0.0009 U
	SB-W-07-0275	1/26/12	WW	ARI	27.5-28	11.2	S	–	–	–	–	–	–	**0.083**	–	–	–	–	0.0009 U
	SB-W-07-0335	1/26/12	WW	ARI	33.5-34	5.2	S	–	–	–	–	–	–	**0.011**	–	–	–	–	0.0008 U
	SB-W-07-0430	1/26/12	WW	ARI	43-43.5	-4.3	S	–	–	–	–	–	–	**0.091**	–	–	–	–	0.0008 U
	SB-W-07-0530	1/26/12	WW	ARI	53-53.5	-14.3	S	–	–	–	–	–	–	**0.63**	–	–	–	–	0.0008 U
	SB-W-07-0630	1/26/12	WW	ARI	63-63.5	-24.3	S	–	–	–	–	–	–	0.0010 U	–	–	–	–	0.0010 U
	SB-W-07-0780	1/26/12	WW	ARI	78-78.5	-39.3	S	–	–	–	–	–	–	0.0008 U	–	–	–	–	0.0008 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
W-MW-04 (P-08)	SB-W-08-0090	1/28/12	WW	ARI	9-9.5	26.0	S	–	–	–	–	–	–	**7.3**	–	–	–	–	0.27 U
	SB-W-08-0155	1/28/12	WW	ARI	15.5-16	19.5	S	–	–	–	–	–	–	**0.12**	–	–	–	–	0.0009 U
	SB-W-08-0265	1/28/12	WW	ARI	26.5-27	8.5	S	–	–	–	–	–	–	**0.0043**	–	–	–	–	0.0009 U
	SB-W-08-0380	1/28/12	WW	ARI	38-38.5	-3.0	S	–	–	–	–	–	–	**0.0012**	–	–	–	–	0.0008 U
	SB-W-08-0480	1/28/12	WW	ARI	48-48.5	-13.0	S	–	–	–	–	–	–	**0.0009 J**	–	–	–	–	0.0009 U
	SB-W-08-9480	1/28/12	WW	ARI	48-48.5 (dup)	-13.0	S	–	–	–	–	–	–	**0.0005 J**	–	–	–	–	0.0009 U
	SB-W-08-0590	1/28/12	WW	ARI	59-59.5	-24.0	S	–	–	–	–	–	–	0.13 U	–	–	–	–	0.13 U
	SB-W-08-0710	1/29/12	WW	ARI	71-71.5	-36.0	S	–	–	–	–	–	–	0.20 U	–	–	–	–	0.20 U
	SB-W-08-0760	1/29/12	WW	ARI	76-76.5	-41.0	S	–	–	–	–	–	–	0.0009 U	–	–	–	–	0.0009 U
All Data							Number of Analytes Measured	805	805	805	805	805	805	1,033	805	805	805	805	856
							Number of Analytes Detected	0	0	3	28	93	17	750	1	0	0	0	40
							Frequency of Detection	0.0%	0.0%	0.4%	3.5%	11.6%	2.1%	72.6%	0.1%	0.0%	0.0%	0.0%	4.7%
							Maximum Detection	–	–	0.000852 J	0.0282	0.00244	0.0575	329	0.000791 J	–	–	–	4.74
							Minimum Detection	0.000328 U	0.000212 U	0.000373 U	0.000946 U	0.000229 U	0.000375 U	0.000247 U	0.000262 U	0.000382 U	0.000254 U	0.000713 U	0.000297 UJ
							Number Of Vadose (V) Detections above SL	0	0	0	–	0	–	0	0	0	0	0	0
							Number of Saturated (S) Detections above SL	0	0	0	–	0	–	544	1	0	0	0	2
2017-2021							Number of Analytes Measured	805	805	805	805	805	805	861	805	805	805	805	819
							Number of Analytes Detected	0	0	3	28	93	17	701	1	0	0	0	38
							Frequency of Detection	0.0%	0.0%	0.4%	3.5%	11.6%	2.1%	81.4%	0.1%	0.0%	0.0%	0.0%	4.6%
							Maximum Detection	–	–	0.000852 J	0.0282	0.00244	0.0575	329	0.000791 J	–	–	–	4.74
							Minimum Detection	0.000328 U	0.000212 U	0.000373 U	0.000946 U	0.000229 U	0.000375 U	0.000247 U	0.000262 U	0.000382 U	0.000254 U	0.000713 U	0.000297 UJ
							Number Of Vadose (V) Detections above SL	0	0	0	–	0	–	0	0	0	0	0	0
							Number of Saturated (S) Detections above SL	0	0	0	–	0	–	506	1	0	0	0	1

Abbreviations:
AAL = Alden Analytical Laboratories, Inc., of Seattle, Washington
ARI = Analytical Resource, Incorporated, Seattle, Washington
B&V = Black Veatch
bgs = below ground surface
Comp = Composite Sample
dup = duplicate
EPJ = E.PJohnson Construction Inc., and Environmental
ESC = ESC Lab Services of Mt. Juliet, Tennessee
F&BI = Friedman & Bruya, Inc.
GeoEng = GeoEngineers, Inc.
HC = Hart Crowser, Inc.
NCA = North Creek Analytical, of Bothell, Washington
OnSite = OnSite Environmental Inc., of Redmond, Washington
Pace = Pace Analytical of Mt. Juliet, Tennessee (formerly ESC)
PES = PES Environmental, Inc.
Retec = Remediation Technologies, Inc.
Roux = Roux Associates
SES = SoundEarth Strategies, Inc.
TR = TR Corporation
Urban = Urban Redevelopment LLC
WW = WW Environmental LLC

Notes:
All on-Property soil was excavated during Property redevelopment above elevations 0.7 to 10.7 feet, and CVOCs in soil between elevations +10 to 55 feet was treated.
Petroleum Hydrocarbons (PHCs) analyzed by Ecology Methods NWTPH-HCID, NWTPH-Gx, or NWTPH-Dx; or EPA Method 418.1, Method 8020, or Method 8015M.
VOCs analyzed by EPA Methods 8010, 8020, 8021B, 624/8240, or 8260B/C/D.
Well screen elevations provided below Sample Location. in parentheses when appliable.
PCUL = Preliminary Cleanup Level from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021. PCULs based on the practical quantitation limits (PQLs) italicized.
Detected results shown in **bold**.
Detections above the screening level in the vadose zone are shown in **bold** and **highlighted blue**
Detections above the screening level in the saturated zone are shown in **bold** and **highlighted gray.**
– = Not available or results not analyzed.
A = Result reported as total petroleum hydrocarbons.
B = Analyte detected in an associated method blank.
J = The reported concentration is an estimate based on detectable results between the method detection limit and reporting limit, laboratory QA/QC, or data validation review.
J+ = The result is an estimated quantity, but the result may be biased high.
J- = The result is an estimated quantity, but the result may be biased low.
ND = Not detected above laboratory reporting limit. Reporting limit not available.
q = Sample may contain gasoline or petroleum components. Chromatographic pattern indicates the presence of gasoline constituents.
R = The data is unusable. The sample result is rejected due to serious deficiencies in meeting QC criteria. The analyte may or may not be present in the sample
T = Analyte also detected in trip blank.
U = Not detected at a concentration exceeding laboratory reporting limit
ve = Estimated value. The reported range exceeds the calibration range of the analysis.
w = Petroleum product eluting in the C8-C9 range
x = The sample chromatographic pattern does not resemble the fuel standard used for quantitation.
z = Gasoline/petroleum detection result is likely elevated due to high detections of CVOCs.

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
B-1	B-1-13	6/23/00	TR	ARI	13	27.0	S	–	–	–	–	–	–	–	–	–	–	–	–
B-2	B-2-6.5	6/23/00	TR	ARI	6.5	33.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B-2-11	6/23/00	TR	ARI	11	29.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B-2-16	6/23/00	TR	ARI	16	24.0	S	–	–	–	–	–	–	–	–	–	–	–	–
B-3	B-3-12	6/23/00	TR	ARI	12	28.0	S	–	–	–	–	–	–	–	–	–	–	–	–
B-5	B-5-10	6/23/00	TR	ARI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B-5-11.5	6/23/00	TR	ARI	11.5	28.5	S	–	–	–	–	–	–	–	–	–	–	–	–
B-6	B-6-6	6/24/00	TR	ARI	6	34.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B-6-12	6/24/00	TR	ARI	12	28.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B-6-18	6/24/00	TR	ARI	18	22.0	S	–	–	–	–	–	–	–	–	–	–	–	–
B-7	B-7-6	6/24/00	TR	ARI	6	34.0	S	–	–	–	–	–	–	–	–	–	–	–	–
B-8	B-8-4	6/24/00	TR	ARI	4	36.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B-8-8	6/24/00	TR	ARI	8	32.0	S	–	–	–	–	–	–	–	–	–	–	–	–
B-9	B-9-4	6/24/00	TR	ARI	4	36.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B-9-8	6/24/00	TR	ARI	8	32.0	S	–	–	–	–	–	–	–	–	–	–	–	–
B-10	B-10-12	6/24/00	TR	ARI	12	28.0	S	–	–	–	–	–	–	–	–	–	–	–	–
B-201	G-201-10	6/19/17	PES	ESC	10	29.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	G-201-30	6/19/17	PES	ESC	30	9.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	G-201-35	6/19/17	PES	ESC	35	4.8	S	–	–	–	–	–	–	–	–	–	–	–	–
B-202	G-202-5	6/19/17	PES	ESC	5	34.2	S	–	–	–	–	–	–	–	–	–	–	–	–
	G-202-20	6/19/17	PES	ESC	20	19.2	S	–	–	–	–	–	–	–	–	–	–	–	–
	G-202-50	6/19/17	PES	ESC	50	-10.8	S	–	–	–	–	–	–	–	–	–	–	–	–
B-203	G-203-5	6/20/17	PES	ESC	5	34.2	S	–	–	–	–	–	–	–	–	–	–	–	–
	G-203-25	6/20/17	PES	ESC	25	14.2	S	–	–	–	–	–	–	–	–	–	–	–	–
	G-203-40	6/20/17	PES	ESC	40	-0.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	G-203-50	6/20/17	PES	ESC	50	-10.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	G-203-80	6/20/17	PES	ESC	80	-40.8	S	–	–	–	–	–	–	–	–	–	–	–	–
B-204	G-204-20	6/20/17	PES	ESC	20	19.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	G-204-40	6/20/17	PES	ESC	40	-0.2	S	–	–	–	–	–	–	–	–	–	–	–	–
	G-204-45	6/20/17	PES	ESC	45	-5.2	S	–	–	–	–	–	–	–	–	–	–	–	–
B-205	B-205-10	8/30/17	PES	ESC	10	30.3	S	0.0412 U	0.0350 U	0.305 U	0.0299 U	**0.851**	0.227 U	0.0256 U	0.121 U	**5.21**	**0.973**	**2.84**	**0.642**
	B-205-55	8/30/17	PES	ESC	55	-14.7	S	0.000400 U	**0.00466 J**	0.00296 U	0.000290 U	0.000284 U	0.00220 U	0.000248 U	0.00117 U	0.00117 U	0.000301 U	0.000241 U	0.000235 U
	B-205-65	8/30/17	PES	ESC	65	-24.7	S	0.000362 U	**0.00583 J**	0.00268 U	0.000263 U	0.000257 U	0.00199 U	0.000224 U	0.00106 U	0.00106 U	0.000273 U	0.000218 U	0.000213 U
	B-205-75	8/30/17	PES	ESC	75	-34.7	S	0.000366 U	**0.00452 J**	0.00271 U	0.000266 U	0.000260 U	0.00201 U	0.000227 U	0.00107 U	0.00107 U	0.000276 U	0.000221 U	0.000215 U
	B-904-50	8/30/17	PES	ESC	75 (dup)	-34.7	S	0.000367 U	**0.00551 J**	0.00271 U	0.000266 U	0.000261 U	0.00202 U	0.000227 U	0.00107 U	0.00107 U	0.000277 U	0.000221 U	0.000216 U
B-206	B-206-15	8/14/17	PES	ESC	15	24.1	S	0.00984 U	**0.0395 J**	0.0727 U	0.00714 U	0.00700 U	0.0541 U	**0.145**	0.0288 U	0.0288 U	0.00742 U	0.00593 U	0.00578 U
	B-206-30	8/14/17	PES	ESC	30	9.1	S	0.000392 U	0.000333 U	0.00290 U	0.000284 U	0.000279 U	0.00216 U	0.000243 U	0.00115 U	**0.0340**	0.000296 U	0.000236 U	0.000231 U
	B-206-40	8/14/17	PES	ESC	40	-0.9	S	0.000362 U	**0.00151 J**	0.00267 U	0.000262 U	0.000257 U	0.00199 U	0.000224 U	0.00106 U	**0.00114 J**	0.000273 U	0.000218 U	0.000212 U
	B-206-49	8/14/17	PES	ESC	49	-9.9	S	0.000390 U	**0.00815 J**	0.00288 U	0.000283 U	0.000277 U	0.00214 U	0.000242 U	0.00114 U	0.00114 U	0.000294 U	0.000235 U	0.000229 U
	B-206-52	8/14/17	PES	ESC	52	-12.9	S	0.000373 U	0.000317 U	0.00276 U	0.000271 U	0.000265 U	0.00205 U	0.000231 U	0.00109 U	0.00109 U	0.000282 U	0.000225 U	0.000219 U
	B-206-56	8/14/17	PES	ESC	56	-16.9	S	0.000376 U	0.000319 U	0.00278 U	0.000272 U	0.000267 U	0.00207 U	0.000233 U	0.00110 U	0.00110 U	0.000283 U	0.000226 U	0.000221 U
	B-206-59	8/14/17	PES	ESC	59	-19.9	S	0.000356 U	0.000302 U	0.00263 U	0.000258 U	0.000253 U	0.00196 U	0.000221 U	0.00104 U	0.00104 U	0.000268 U	0.000214 U	0.000209 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
B-206	B-206-70	8/14/17	PES	ESC	70	-30.9	S	0.000373 U	**0.000515 J**	0.00276 U	0.000270 U	0.000265 U	0.00205 U	0.000231 U	0.00109 U	0.00109 U	0.000281 U	0.000224 U	0.000219 U
(continued)	B-206-80	8/14/17	PES	ESC	80	-40.9	S	0.000373 U	**0.000634 J**	0.00276 U	0.000270 U	0.000265 U	0.00205 U	0.000231 U	0.00109 U	0.00109 U	0.000281 U	0.000225 U	0.000219 U
B-207	B-207-30	8/25/17	PES	ESC	30	8.5	S	0.00971 U	0.00824 U	0.0718 U	0.00704 U	0.00691 U	0.0534 U	0.00602 U	0.0284 U	0.0284 U	0.00733 U	0.00585 U	0.00570 U
	B-207-41	8/25/17	PES	ESC	41	-2.5	S	0.0194 U	0.000328 U	0.00287 U	0.000281 U	0.000275 U	0.00213 U	0.000240 U	0.00113 U	0.00113 U	0.000292 U	0.000233 U	0.000228 U
	B-207-49	8/25/17	PES	ESC	49	-10.5	S	0.00954 U	**0.0285**	0.00282 U	0.000277 U	0.000271 U	0.00210 U	0.000236 U	0.00112 U	0.00112 U	0.000288 U	0.000230 U	0.000224 U
	B-207-55	8/25/17	PES	ESC	55	-16.5	S	0.000399 U	**0.000445 J**	0.00295 U	0.000290 U	0.000284 U	0.00220 U	0.000248 U	0.00117 U	0.00117 U	0.000301 U	0.000241 U	0.000235 U
	B-207-60	8/25/17	PES	ESC	60	-21.5	S	0.000364 U	0.000309 U	0.00269 U	0.000264 U	0.000259 U	0.00200 U	0.000226 U	0.00106 U	0.00106 U	0.000275 U	0.000219 U	0.000214 U
	B-207-70	8/25/17	PES	ESC	70	-31.5	S	0.000391 U	0.000331 U	0.00289 U	0.000283 U	0.000278 U	0.00215 U	0.000242 U	0.00114 U	0.00114 U	0.000295 U	0.000235 U	0.000230 U
	B-207-80	8/25/17	PES	ESC	80	-41.5	S	0.000377 U	**0.000787 J**	0.00279 U	0.000273 U	0.000268 U	0.00207 U	0.000234 U	0.00110 U	0.00110 U	0.000284 U	0.000227 U	0.000221 U
	B-207-90	8/25/17	PES	ESC	90	-51.5	S	0.00939 U	0.00797 U	0.0694 U	0.00681 U	0.00668 U	0.0516 U	0.00582 U	0.0275 U	0.0275 U	0.00709 U	0.00566 U	0.00552 U
B-208	B-208-20	8/24/17	PES	ESC	20	18.8	S	0.000404 U	0.000343 U	0.00299 U	0.000293 U	0.000287 U	0.00222 U	0.000251 U	0.00118 U	0.00118 U	0.000305 U	0.000243 U	0.000238 U
	B-208-35	8/24/17	PES	ESC	35	3.8	S	0.000372 U	**0.000803 J**	0.00275 U	0.000270 U	0.000264 U	0.00205 U	0.000231 U	0.00109 U	0.00109 U	0.000281 U	0.000224 U	0.000219 U
	B-901-50	8/24/17	PES	ESC	35 (dup)	3.8	S	0.000387 U	**0.000628 J**	0.00286 U	0.000280 U	0.000275 U	0.00213 U	0.000240 U	0.00113 U	0.00113 U	0.000292 U	0.000233 U	0.000227 U
	B-208-50	8/24/17	PES	ESC	50	-11.2	S	0.000378 U	0.000320 U	0.00279 U	0.000274 U	0.000268 U	0.00208 U	0.000234 U	0.00110 U	0.00110 U	0.000285 U	0.000227 U	0.000222 U
	B-208-60	8/24/17	PES	ESC	60	-21.2	S	0.000381 U	**0.0298**	0.00282 U	0.000276 U	0.000271 U	0.00209 U	0.000236 U	0.00111 U	0.00111 U	0.000287 U	0.000229 U	0.000224 U
	B-208-70	8/24/17	PES	ESC	70	-31.2	S	0.000382 U	0.000324 U	0.00283 U	0.000277 U	0.000271 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000288 U	0.000230 U	0.000224 U
	B-208-80	8/24/17	PES	ESC	80	-41.2	S	0.000423 U	0.000359 U	0.00313 U	0.000307 U	0.000301 U	0.00233 U	0.000262 U	0.00124 U	0.00124 U	0.000319 U	0.000255 U	0.000249 U
B-209	B-209-20	8/25/17	PES	ESC	20	19.0	S	0.000397 U	**0.000396 J**	0.00294 U	0.000288 U	0.000282 U	0.00218 U	0.000246 U	0.00116 U	0.00116 U	0.000300 U	0.000239 U	0.000234 U
	B-209-35	8/25/17	PES	ESC	35	4.0	S	0.000365 U	**0.00231 J**	0.00270 U	0.000265 U	0.000260 U	0.00201 U	0.000226 U	0.00107 U	0.00107 U	0.000276 U	0.000220 U	0.000215 U
	B-209-50	8/25/17	PES	ESC	50	-11.0	S	0.000446 U	**0.00124 J**	0.00330 U	0.000324 U	0.000317 U	0.00245 U	0.000277 U	0.00130 U	0.00130 U	0.000337 U	0.000269 U	0.000262 U
	B-209-60	8/25/17	PES	ESC	60	-21.0	S	0.000393 U	0.000333 U	0.00290 U	0.000285 U	0.000279 U	0.00216 U	0.000243 U	0.00115 U	0.00115 U	0.000296 U	0.000236 U	0.000231 U
	B-209-70	8/25/17	PES	ESC	70	-31.0	S	0.000470 U	**0.00194 J**	0.00270 U	0.000264 U	0.000259 U	0.00200 U	0.000226 U	0.00107 U	0.00107 U	0.000275 U	0.000220 U	0.000214 U
	B-209-75	8/25/17	PES	ESC	75	-36.0	S	0.000363 U	0.000308 U	0.00268 U	0.000263 U	0.000258 U	0.00199 U	0.000225 U	0.00106 U	0.00106 U	0.000274 U	0.000218 U	0.000213 U
	B-209-80	8/25/17	PES	ESC	80	-41.0	S	0.000393 U	**0.000674 J**	0.00291 U	0.000285 U	0.000279 U	0.00216 U	0.000244 U	0.00115 U	0.00115 U	0.000297 U	0.000237 U	0.000231 U
B-210	B-210-6	8/21/17	PES	ESC	6	33.4	S	0.000403 U	0.000342 U	0.00298 U	0.000292 U	0.000286 U	0.00222 U	0.000250 U	0.00118 U	0.00118 U	0.000304 U	0.000243 U	0.000237 U
	B-210-15	8/21/17	PES	ESC	15	24.4	S	0.00927 U	0.00786 U	0.0685 U	0.00672 U	0.00659 U	0.0509 U	**0.0523**	0.0271 U	0.0271 U	0.00699 U	0.00558 U	0.00544 U
	B-210-20	8/21/17	PES	ESC	20	19.4	S	0.000381 U	0.000323 U	0.00282 U	0.000276 U	0.000271 U	0.00209 U	0.000236 U	0.00111 U	0.00111 U	0.000287 U	0.000229 U	0.000224 U
	B-210-35	8/21/17	PES	ESC	35	4.4	S	0.000395 U	0.000335 U	0.00292 U	0.000286 U	0.000280 U	0.00217 U	0.000245 U	0.00115 U	0.00115 U	0.000298 U	0.000238 U	0.000232 U
	B-210-46	8/21/17	PES	ESC	46	-6.6	S	0.000373 U	**0.000325 J**	0.00276 U	0.000270 U	0.000265 U	0.00205 U	0.000231 U	0.00109 U	0.00109 U	0.000281 U	0.000224 U	0.000219 U
	B-210-60	8/22/17	PES	ESC	60	-20.6	S	0.00918 U	0.00778 U	0.0678 U	0.00665 U	0.00653 U	0.0504 U	**0.0446**	0.0268 U	0.0268 U	0.00692 U	0.00553 U	0.00539 U
	B-210-70	8/22/17	PES	ESC	70	-30.6	S	0.000369 U	**0.00741 J**	0.00273 U	0.000268 U	0.000262 U	0.00203 U	0.000229 U	0.00108 U	0.00108 U	0.000278 U	0.000222 U	0.000217 U
	B-210-80	8/22/17	PES	ESC	80	-40.6	S	0.000378 U	0.000320 U	0.00279 U	0.000274 U	0.000268 U	0.00208 U	0.000234 U	0.00110 U	0.00110 U	0.000285 U	0.000228 U	0.000222 U
	B-900-20	8/22/17	PES	ESC	80 (dup)	-40.6	S	0.000406 U	0.000344 U	0.00300 U	0.000295 U	0.000289 U	0.00223 U	0.000252 U	0.00119 U	0.00119 U	0.000306 U	0.000245 U	0.000239 U
B-211	B-211-20	8/17/17	PES	ESC	20	19.8	S	0.000382 U	0.000324 U	0.00282 U	0.000277 U	0.000271 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000288 U	0.000230 U	0.000224 U
	B-211-35	8/17/17	PES	ESC	35	4.8	S	0.000385 U	**0.000482 J**	0.00285 U	0.000279 U	0.000274 U	0.00212 U	0.000239 U	0.00113 U	0.00113 U	0.000290 U	0.000232 U	0.000226 U
	B-211-50	8/17/17	PES	ESC	50	-10.3	S	0.000370 U	0.000314 U	0.00274 U	0.000268 U	0.000263 U	0.00203 U	0.000229 U	0.00108 U	0.00108 U	0.000279 U	0.000223 U	0.000217 U
	B-211-57	8/17/17	PES	ESC	57	-17.3	S	0.000403 U	**0.00389 J**	0.00298 U	0.000292 U	0.000287 U	0.00222 U	0.000250 U	0.00118 U	0.00118 U	0.000304 U	0.000243 U	0.000237 U
	B-211-60	8/17/17	PES	ESC	60	-20.3	S	0.000394 U	0.000334 U	0.00292 U	0.000286 U	0.000280 U	0.00217 U	0.000244 U	0.00115 U	0.00115 U	0.000298 U	0.000238 U	0.000232 U
	B-211-65	8/18/17	PES	ESC	65	-25.3	S	0.000386 U	0.000327 U	0.00286 U	0.000280 U	0.000274 U	0.00212 U	0.000239 U	0.00113 U	0.00113 U	0.000291 U	0.000233 U	0.000227 U
	B-211-70	8/18/17	PES	ESC	70	-30.3	S	0.205 U	0.174 U	1.51 U	0.148 U	0.146 U	1.13 U	**0.202 J**	0.598 U	0.598 U	0.154 U	0.123 U	0.120 U
	B-211-80	8/18/17	PES	ESC	80	-40.3	S	0.00926 U	0.00785 U	0.0684 U	0.00671 U	0.00658 U	0.0509 U	**0.0548**	0.0271 U	0.0271 U	0.00698 U	0.00558 U	0.00544 U
	B-211-90	8/18/17	PES	ESC	90	-50.3	S	0.00997 U	0.00845 U	0.0737 U	0.00723 U	0.00709 U	0.0548 U	**0.0570**	0.0291 U	0.0291 U	0.00752 U	0.00600 U	0.00585 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	–	–	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	–	–	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
B-211 (continued)	B-211-100	8/18/17	PES	ESC	100	-60.3	S	0.000397 U	0.000337 U	0.00294 U	0.000288 U	0.000282 U	0.00218 U	0.000246 U	0.00116 U	0.00116 U	0.000299 U	0.000239 U	0.000233 U
	B-211-110	8/18/17	PES	ESC	110	-70.3	S	0.000377 U	0.000320 U	0.00279 U	0.000273 U	0.000268 U	0.00207 U	0.000234 U	0.00110 U	0.00110 U	0.000285 U	0.000227 U	0.000222 U
	B-211-120	8/21/17	PES	ESC	120	-80.3	S	0.000384 U	0.000325 U	0.00284 U	0.000278 U	0.000273 U	0.00211 U	0.000238 U	0.00112 U	0.00112 U	0.000289 U	0.000231 U	0.000226 U
B-216	B-216-20	9/1/17	PES	ESC	20	31.9	S	0.000368 U	**0.000460 J**	0.00273 U	0.000267 U	0.000262 U	0.00202 U	0.000228 U	0.00108 U	0.00108 U	0.000278 U	0.000222 U	0.000216 U
	B-216-40	9/1/17	PES	ESC	40	11.9	S	0.000371 U	**0.000659 J**	0.00274 U	0.000269 U	0.000264 U	0.00204 U	0.000230 U	0.00108 U	0.00108 U	0.000280 U	0.000223 U	0.000218 U
	B-216-50	9/1/17	PES	ESC	50	1.9	S	0.000370 U	**0.000708 J**	0.00273 U	0.000268 U	0.000263 U	0.00203 U	0.000229 U	0.00108 U	0.00108 U	0.000279 U	0.000223 U	0.000217 U
	B-216-55	9/1/17	PES	ESC	55	-3.1	S	0.000385 U	**0.0368**	0.00285 U	0.000279 U	**0.000650 J**	0.00212 U	0.000239 U	0.00113 U	**0.00226 J**	**0.00318**	**0.00407**	**0.000274 J**
	B-216-65	9/1/17	PES	ESC	65	-13.1	S	0.000411 U	**0.00129 J**	0.00304 U	0.000298 U	0.000292 U	0.00226 U	0.000254 U	0.00120 U	0.00120 U	0.000310 U	0.000247 U	0.000241 U
	B-216-85	9/1/17	PES	ESC	85	-33.1	S	0.000412 U	**0.00652 J**	0.00305 U	0.000299 U	0.000293 U	0.00227 U	0.000256 U	0.00121 U	0.00121 U	0.000311 U	0.000248 U	0.000242 U
	B-216-95	9/1/17	PES	ESC	95	-43.1	S	0.000389 U	**0.00113 J**	0.00287 U	0.000282 U	0.000276 U	0.00214 U	0.000241 U	0.00114 U	0.00114 U	0.000293 U	0.000234 U	0.000228 U
B-217	B-217-15	9/5/17	PES	ESC	15	36.8	V	0.000388 U	**0.000359 J**	0.00287 U	0.000281 U	0.000276 U	0.00213 U	0.000241 U	0.00113 U	0.00113 U	0.000293 U	0.000234 U	0.000228 U
	B-217-25	9/5/17	PES	ESC	25	26.8	S	0.000379 U	0.000322 U	0.00281 U	0.000275 U	0.000269 U	0.00208 U	0.000235 U	0.00111 U	0.00111 U	0.000286 U	0.000228 U	0.000223 U
	B-217-35	9/5/17	PES	ESC	35	16.8	S	0.000393 U	**0.000409 J**	0.00290 U	0.000285 U	0.000279 U	0.00216 U	0.000243 U	0.00115 U	0.00115 U	0.000296 U	0.000236 U	0.000231 U
	B-217-42	9/5/17	PES	ESC	42	9.8	S	0.000391 U	**0.00116 J**	0.00289 U	0.000284 U	0.000278 U	0.00215 U	0.000242 U	0.00114 U	0.00114 U	0.000295 U	0.000236 U	0.000230 U
	B-217-55	9/5/17	PES	ESC	55	-3.2	S	0.000397 U	0.000337 U	0.00294 U	0.000288 U	0.000282 U	0.00218 U	0.000246 U	0.00116 U	0.00116 U	0.000300 U	0.000239 U	0.000233 U
	B-217-65	9/5/17	PES	ESC	65	-13.2	S	0.000394 U	0.000334 U	0.00291 U	0.000286 U	0.000280 U	0.00216 U	0.000244 U	0.00115 U	0.00115 U	0.000297 U	0.000237 U	0.000231 U
	B-217-75	9/5/17	PES	ESC	75	-23.2	S	0.000410 U	0.000347 U	0.00303 U	0.000297 U	0.000291 U	0.00225 U	0.000254 U	0.00120 U	0.00120 U	0.000309 U	0.000247 U	0.000241 U
	B-217-85	9/6/17	PES	ESC	85	-33.2	S	0.000390 U	0.000330 U	0.00288 U	0.000283 U	0.000277 U	0.00214 U	0.000242 U	0.00114 U	0.00114 U	0.000294 U	0.000235 U	0.000229 U
	B-217-95	9/6/17	PES	ESC	95	-43.2	S	0.000413 U	0.000351 U	0.00306 U	0.000300 U	0.000294 U	0.00227 U	0.000256 U	0.00121 U	0.00121 U	0.000312 U	0.000249 U	0.000243 U
	B-217-106	9/6/17	PES	ESC	106	-54.2	S	0.0419 U	0.0355 U	0.310 U	0.0304 U	0.0298 U	0.230 U	0.0260 U	0.123 U	0.123 U	0.0316 U	0.0252 U	0.0246 U
	B-217-115	9/6/17	PES	ESC	115	-63.2	S	0.000395 U	0.000335 U	0.00292 U	0.000286 U	0.000281 U	0.00217 U	0.000245 U	0.00115 U	0.00115 U	0.000298 U	0.000238 U	0.000232 U
B-218	B-218-12.5	9/19/17	PES	ESC	12.5	25.6	S	0.000389 U	0.000330 U	0.00288 U	0.000282 U	0.000277 U	0.00214 U	0.000241 U	0.00114 U	0.00114 U	0.000294 U	0.000235 U	0.000229 U
	B-218-19	9/19/17	PES	ESC	19	19.1	S	0.000388 U	0.000329 U	0.00287 U	0.000281 U	0.000276 U	0.00213 U	0.000241 U	0.00114 U	0.00114 U	0.000293 U	0.000234 U	0.000228 U
	B-218-25	9/19/17	PES	ESC	25	13.1	S	0.000396 U	0.000336 U	0.00293 U	0.000287 U	0.000281 U	0.00218 U	0.000245 U	0.00116 U	0.00116 U	0.000299 U	0.000239 U	0.000233 U
	B-218-40	9/19/17	PES	ESC	40	-1.9	S	0.0211 U	0.0178 U	0.156 U	0.0153 U	0.0149 U	0.115 U	0.0131 U	0.0615 U	0.0615 U	0.0158 U	0.0126 U	0.0123 U
	B-218-50	9/19/17	PES	ESC	50	-11.9	S	0.000365 U	0.000309 U	0.00270 U	0.000264 U	0.000259 U	0.00200 U	0.000226 U	0.00107 U	0.00107 U	0.000275 U	0.000220 U	0.000214 U
	B-913-70	9/19/17	PES	ESC	50 (dup)	-11.9	S	0.000363 U	0.000308 U	0.00269 U	0.000263 U	0.000258 U	0.00200 U	0.000225 U	0.00106 U	0.00106 U	0.000274 U	0.000219 U	0.000213 U
B-219	B-219-42	8/28/17	PES	ESC	42	-2.2	S	0.000372 U	**0.00264 J**	0.00276 U	0.000270 U	0.000265 U	0.00205 U	0.000231 U	0.00109 U	0.00109 U	0.000281 U	0.000224 U	0.000219 U
	B-219-50	8/28/17	PES	ESC	50	-10.2	S	0.000405 U	0.000343 U	0.00300 U	0.000294 U	0.000288 U	0.00223 U	0.000251 U	0.00118 U	0.00118 U	0.000306 U	0.000244 U	0.000238 U
	B-219-60	8/28/17	PES	ESC	60	-20.2	S	0.000368 U	**0.00248 J**	0.00272 U	0.000267 U	0.000262 U	0.00202 U	0.000228 U	0.00108 U	0.00108 U	0.000278 U	0.000222 U	0.000216 U
	B-219-70	8/28/17	PES	ESC	70	-30.2	S	0.000390 U	**0.00634 J**	0.00289 U	0.000283 U	0.000277 U	0.00215 U	0.000242 U	0.00114 U	0.00114 U	0.000294 U	0.000235 U	0.000229 U
	B-219-80	8/28/17	PES	ESC	80	-40.2	S	0.000371 U	**0.00111 J**	0.00275 U	0.00673 U	0.000264 U	0.00204 U	0.000230 U	0.00109 U	0.00109 U	0.000280 U	0.000224 U	0.000218 U
B-220	B-220-15	9/20/17	PES	ESC	15	23.9	S	0.000389 U	0.000330 U	0.00288 U	0.000282 U	0.000276 U	0.00214 U	0.000241 U	0.00114 U	0.00114 U	0.000293 U	0.000234 U	0.000229 U
	B-220-29	9/20/17	PES	ESC	29	9.9	S	0.000397 U	0.000337 U	0.00294 U	0.000288 U	0.000282 U	0.00219 U	0.000246 U	0.00116 U	0.00116 U	0.000300 U	0.000239 U	0.000234 U
	B-220-32	9/20/17	PES	ESC	32	6.9	S	0.000390 U	0.000331 U	0.00289 U	0.000283 U	0.000277 U	0.00214 U	0.000242 U	0.00114 U	0.00114 U	0.000294 U	0.000235 U	0.000229 U
	B-220-40	9/20/17	PES	ESC	40	-1.1	S	0.000380 U	0.000322 U	0.00281 U	0.000275 U	0.000270 U	0.00209 U	0.000235 U	0.00111 U	0.00111 U	0.000286 U	0.000229 U	0.000223 U
	B-220-50	9/20/17	PES	ESC	50	-11.1	S	0.000368 U	**0.00215 J**	0.00272 U	0.000267 U	0.000261 U	0.00202 U	0.000228 U	0.00108 U	0.00108 U	0.000277 U	0.000222 U	0.000216 U
	B-914-75	9/20/17	PES	ESC	50 (dup)	-11.1	S	0.000368 U	**0.00212 J**	0.00272 U	0.000267 U	0.000261 U	0.00202 U	0.000228 U	0.00108 U	0.00108 U	0.000277 U	0.000222 U	0.000216 U
B-221	B-221-16	9/20/17	PES	ESC	16	23.0	S	0.0100 U	0.00850 U	0.0741 U	0.00727 U	0.00712 U	0.0551 U	0.00621 U	0.0293 U	0.0293 U	0.00756 U	0.00603 U	0.00588 U
	B-221-22	9/20/17	PES	ESC	22	17.0	S	0.393 U	0.334 U	2.91 U	0.285 U	0.280 U	2.16 U	0.244 U	1.15 U	1.15 U	0.297 U	0.237 U	0.231 U
	B-221-33	9/20/17	PES	ESC	33	6.0	S	0.383 U	0.325 U	2.83 U	0.278 U	0.272 U	2.10 U	0.237 U	1.12 U	1.12 U	0.289 U	0.231 U	0.225 U
	B-221-37	9/20/17	PES	ESC	37	2.0	S	0.0804 U	0.0682 U	0.595 U	0.0583 U	0.0571 U	0.442 U	0.0499 U	0.235 U	0.235 U	0.0607 U	0.0484 U	0.0473 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	–	–	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	–	–	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
B-221 (continued)	B-915-80	9/20/17	PES	ESC	37 (dup)	2.0	S	0.0392 U	0.0332 U	0.290 U	0.0284 U	0.0279 U	0.215 U	0.0243 U	0.115 U	0.115 U	0.0296 U	0.0236 U	0.0230 U
	B-221-45	9/20/17	PES	ESC	45	-6.0	S	3.75 U	3.18 U	27.7 U	2.72 U	2.67 U	20.6 U	2.33 U	11.0 U	11.0 U	2.83 U	2.26 U	2.20 U
	B-221-50	9/20/17	PES	ESC	50	-11.0	S	0.186 U	0.158 U	1.37 U	0.135 U	0.133 U	1.02 U	0.115 U	0.544 U	0.544 U	0.140 U	0.112 U	0.109 U
	B-221-60	9/20/17	PES	ESC	60	-21.0	S	0.189 U	0.160 U	1.39 U	0.137 U	0.135 U	1.04 U	0.117 U	0.553 U	0.553 U	0.143 U	0.114 U	0.111 U
	B-221-70	9/21/17	PES	ESC	70	-31.0	S	0.000378 U	0.000320 U	0.00279 U	0.000274 U	0.000268 U	0.00208 U	0.000234 U	0.00110 U	0.00110 U	0.000285 U	0.000227 U	0.000222 U
B-222	B-222-17	9/21/17	PES	ESC	17	22.2	S	0.000388 U	0.000329 U	0.00287 U	0.000281 U	0.000276 U	0.00213 U	0.000240 U	0.00113 U	0.00113 U	0.000293 U	0.000234 U	0.000228 U
	B-222-25	9/21/17	PES	ESC	25	14.2	S	0.000395 U	0.000335 U	0.00292 U	0.000287 U	0.000281 U	0.00217 U	0.000245 U	0.00116 U	0.00116 U	0.000298 U	0.000238 U	0.000232 U
	B-222-34	9/21/17	PES	ESC	34	5.2	S	0.000383 U	0.000325 U	0.00283 U	0.000278 U	0.000272 U	0.00211 U	0.000238 U	0.00112 U	0.00112 U	0.000289 U	0.000231 U	0.000225 U
	B-222-42	9/21/17	PES	ESC	42	-2.8	S	0.000424 U	**0.00395 J**	0.00314 U	0.000308 U	0.000301 U	0.00233 U	0.000263 U	0.00124 U	0.00124 U	0.000320 U	0.000255 U	0.000249 U
	B-222-50	9/21/17	PES	ESC	50	-10.8	S	0.0183 U	0.0156 U	0.135 U	0.0133 U	0.0131 U	0.101 U	0.0114 U	0.0536 U	0.0536 U	0.0138 U	0.0110 U	0.0107 U
	B-916-30	9/21/17	PES	ESC	50 (dup)	-10.8	S	0.000363 U	**0.000393 J**	0.00268 U	0.000263 U	0.000258 U	0.00199 U	0.000225 U	0.00106 U	0.00106 U	0.000274 U	0.000218 U	0.000213 U
B-223	B-223-16	9/21/17	PES	ESC	16	23.1	S	0.0808 U	0.0685 U	0.598 U	0.0586 U	0.0574 U	0.444 U	0.0501 U	0.236 U	0.236 U	0.0610 U	0.0487 U	0.0475 U
	B-223-22	9/21/17	PES	ESC	22	17.1	S	0.0781 U	0.0662 U	0.578 U	0.0566 U	0.0555 U	0.429 U	0.0484 U	0.228 U	0.228 U	0.0589 U	0.0470 U	0.0459 U
	B-223-30	9/21/17	PES	ESC	30	9.1	S	9.41 U	7.98 U	69.6 U	6.83 U	6.69 U	51.7 U	5.84 U	27.5 U	27.5 U	7.10 U	5.67 U	5.53 U
	B-223-39	9/21/17	PES	ESC	39	0.1	S	0.000390 U	0.000330 U	0.00288 U	0.000282 U	0.000277 U	0.00214 U	0.000241 U	0.00114 U	0.00114 U	0.000294 U	0.000235 U	0.000229 U
	B-223-47	9/21/17	PES	ESC	47	-7.9	S	0.000397 U	0.000337 U	0.00294 U	0.000288 U	0.000282 U	0.00218 U	0.000246 U	0.00116 U	0.00116 U	0.000300 U	0.000239 U	0.000233 U
	B-917-57	9/21/17	PES	ESC	47 (dup)	-7.9	S	0.000368 U	0.000312 U	0.00272 U	0.000267 U	0.000261 U	0.00202 U	0.000228 U	0.00107 U	0.00107 U	0.000277 U	0.000221 U	0.000216 U
B-224	B-224-6	11/27/17	PES	ESC	6	33.1	S	0.000370 U	**0.00142 J**	0.00274 U	0.000268 U	0.000263 U	0.00203 U	0.000229 U	0.00108 U	0.00108 U	0.000279 U	0.000223 U	0.000217 U
	B-224-11	11/27/17	PES	ESC	11	28.1	S	0.000914 U	**0.0140 J**	0.00677 U	0.000663 U	0.000649 U	0.00503 U	0.000566 U	0.00267 U	0.00267 U	0.000689 U	0.000550 U	0.000538 U
	B-224-16	11/27/17	PES	ESC	16	23.1	S	0.000414 U	0.000351 U	0.00306 U	0.000300 U	0.000294 U	0.00227 U	0.000256 U	0.00121 U	0.00121 U	0.000312 U	0.000249 U	0.000243 U
	B-224-21.5	11/27/17	PES	ESC	21.5	17.6	S	0.000397 U	0.000337 U	0.00294 U	0.000288 U	0.000282 U	0.00218 U	0.000246 U	0.00116 U	0.00116 U	0.000300 U	0.000239 U	0.000233 U
	B-224-26	11/27/17	PES	ESC	26	13.1	S	0.000452 U	0.000384 U	0.00334 U	0.000328 U	0.000321 U	0.00248 U	0.000280 U	0.00132 U	0.00132 U	0.000341 U	0.000272 U	0.000265 U
	B-224-31	11/27/17	PES	ESC	31	8.1	S	0.000399 U	**0.000354 J**	0.00296 U	0.000290 U	0.000284 U	0.00220 U	0.000248 U	0.00117 U	0.00117 U	0.000302 U	0.000240 U	0.000235 U
	B-224-36	11/27/17	PES	ESC	36	3.1	S	0.000380 U	**0.000529 J**	0.00281 U	0.000275 U	0.000270 U	0.00209 U	0.000235 U	0.00111 U	0.00111 U	0.000286 U	0.000229 U	0.000223 U
	B-224-60.5	11/27/17	PES	ESC	60.5	-21.4	S	0.000553 U	0.000469 U	0.00410 U	0.000401 U	0.000393 U	0.00304 U	0.000343 U	0.00162 U	0.00162 U	0.000418 U	0.000333 U	0.000325 U
B-225	B-225-5	11/27/17	PES	ESC	5	34.1	S	0.000371 U	0.000315 U	0.00274 U	0.000269 U	0.000264 U	0.00204 U	0.000230 U	0.00108 U	0.00108 U	0.000280 U	0.000223 U	0.000218 U
	B-225-11	11/27/17	PES	ESC	11	28.1	S	0.000400 U	0.000339 U	0.00296 U	0.000290 U	0.000284 U	0.00220 U	0.000248 U	0.00117 U	0.00117 U	0.000302 U	0.000241 U	0.000235 U
	B-225-16	11/27/17	PES	ESC	16	23.1	S	0.0101 U	0.00853 U	0.0743 U	0.00729 U	0.00715 U	0.0553 U	0.00623 U	0.0294 U	0.0294 U	0.00759 U	0.00606 U	0.00591 U
	B-225-21	11/27/17	PES	ESC	21	18.1	S	0.00972 U	0.00824 U	0.0718 U	0.00705 U	0.00691 U	0.0534 U	0.00603 U	0.0284 U	0.0284 U	0.00733 U	0.00585 U	0.00571 U
	B-225-26	11/27/17	PES	ESC	26	13.1	S	0.000402 U	**0.000676 J**	0.00297 U	0.000291 U	0.000286 U	0.00221 U	0.000249 U	0.00118 U	0.00118 U	0.000303 U	0.000242 U	0.000236 U
	B-225-31	11/27/17	PES	ESC	31	8.1	S	0.000391 U	**0.000570 J**	0.00289 U	0.000283 U	0.000278 U	0.00215 U	0.000242 U	0.00114 U	0.00114 U	0.000295 U	0.000235 U	0.000230 U
	B-225-36	11/27/17	PES	ESC	36	3.1	S	0.000421 U	0.000357 U	0.00312 U	0.000305 U	0.000299 U	0.00232 U	0.000261 U	0.00123 U	0.00123 U	0.000318 U	0.000254 U	0.000248 U
B-226	B-226-6	11/28/17	PES	ESC	6	33.1	S	0.000412 U	0.000349 U	0.00305 U	0.000299 U	0.000293 U	0.00226 U	0.000255 U	0.00120 U	0.00120 U	0.000311 U	0.000248 U	0.000242 U
	B-226-11	11/28/17	PES	ESC	11	28.1	S	0.000388 U	0.000329 U	0.00287 U	0.000281 U	0.000276 U	0.00213 U	0.000240 U	0.00113 U	0.00113 U	0.000293 U	0.000234 U	0.000228 U
	B-226-16	11/28/17	PES	ESC	16	23.1	S	0.00959 U	0.00813 U	0.0709 U	0.00696 U	0.00682 U	0.0527 U	0.00595 U	0.0280 U	0.0280 U	0.00724 U	0.00578 U	0.00563 U
	B-920-35	11/28/17	PES	ESC	16 (dup)	23.1	S	0.000378 U	0.000321 U	0.00280 U	0.000274 U	0.000269 U	0.00208 U	0.000235 U	0.00111 U	0.00111 U	0.000285 U	0.000228 U	0.000222 U
	B-226-21	11/28/17	PES	ESC	21	18.1	S	0.000390 U	0.000330 U	0.00288 U	0.000282 U	0.000277 U	0.00214 U	0.000241 U	0.00114 U	0.00114 U	0.000294 U	0.000235 U	0.000229 U
	B-226-31.5	11/28/17	PES	ESC	31.5	7.6	S	0.000364 U	**0.00216 J**	0.00269 U	0.000264 U	0.000259 U	0.00200 U	0.000226 U	0.00106 U	0.00106 U	0.000275 U	0.000219 U	0.000214 U
	B-226-40	11/28/17	PES	ESC	40	-0.9	S	0.000392 U	**0.0159**	0.00290 U	0.000284 U	0.000278 U	0.00215 U	0.000243 U	0.00114 U	0.00114 U	0.000295 U	0.000236 U	0.000230 U
B-227	B-227-6	11/28/17	PES	ESC	6	33.1	S	0.000390 U	0.000331 U	0.00289 U	0.000283 U	0.000277 U	0.00215 U	0.000242 U	0.00114 U	0.00114 U	0.000295 U	0.000235 U	0.000229 U
	B-227-11	11/28/17	PES	ESC	11	28.1	S	0.000369 U	0.000313 U	0.00273 U	0.000267 U	0.000262 U	0.00203 U	0.000228 U	0.00108 U	0.00108 U	0.000278 U	0.000222 U	0.000217 U
	B-227-16	11/28/17	PES	ESC	16	23.1	S	0.000392 U	0.000332 U	0.00290 U	0.000284 U	0.000278 U	0.00215 U	0.000243 U	0.00115 U	0.00115 U	0.000296 U	0.000236 U	0.000230 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
B-227 (continued)	B-227-21	11/28/17	PES	ESC	21	18.1	S	0.000397 U	0.000337 U	0.00294 U	0.000288 U	0.000282 U	0.00218 U	0.000246 U	0.00116 U	0.00116 U	0.000299 U	0.000239 U	0.000233 U
	B-227-26	11/28/17	PES	ESC	26	13.1	S	0.000398 U	0.000338 U	0.00295 U	0.000289 U	0.000283 U	0.00219 U	0.000247 U	0.00116 U	0.00116 U	0.000301 U	0.000240 U	0.000234 U
	B-227-31	11/28/17	PES	ESC	31	8.1	S	0.000410 U	0.000348 U	0.00304 U	0.000298 U	0.000292 U	0.00226 U	0.000254 U	0.00120 U	0.00120 U	0.000310 U	0.000247 U	0.000241 U
	B-227-36	11/28/17	PES	ESC	36	3.1	S	0.000393 U	0.000333 U	0.00290 U	0.000285 U	0.000279 U	0.00216 U	0.000243 U	0.00115 U	0.00115 U	0.000296 U	0.000236 U	0.000231 U
B-228	B-228-6	11/29/17	PES	ESC	6	33.1	S	0.000418 U	0.000355 U	0.00309 U	0.000303 U	0.000297 U	0.00230 U	0.000259 U	0.00122 U	0.00122 U	0.000316 U	0.000252 U	0.000246 U
	B-228-11	11/29/17	PES	ESC	11	28.1	S	0.000380 U	0.000322 U	0.00281 U	0.000276 U	0.000270 U	0.00209 U	0.000236 U	0.00111 U	0.00111 U	0.000287 U	0.000229 U	0.000223 U
	B-228-16	11/29/17	PES	ESC	16	23.1	S	0.000368 U	0.000312 U	0.00273 U	0.000267 U	0.000262 U	0.00203 U	0.000228 U	0.00108 U	0.00108 U	0.000278 U	0.000222 U	0.000217 U
	B-921-22	11/29/17	PES	ESC	16 (dup)	23.1	S	0.000393 U	0.000333 U	0.00291 U	0.000285 U	0.000279 U	0.00216 U	0.000244 U	0.00115 U	0.00115 U	0.000296 U	0.000237 U	0.000231 U
	B-228-21	11/29/17	PES	ESC	21	18.1	S	0.000387 U	0.000328 U	0.00286 U	0.000280 U	0.000275 U	0.00213 U	0.000240 U	0.00113 U	0.00113 U	0.000292 U	0.000233 U	0.000227 U
	B-228-26	11/29/17	PES	ESC	26	13.1	S	0.000368 U	0.000312 U	0.00272 U	0.000267 U	0.000262 U	0.00202 U	0.000228 U	0.00108 U	0.00108 U	0.000278 U	0.000222 U	0.000216 U
	B-228-31	11/29/17	PES	ESC	31	8.1	S	0.000380 U	0.000322 U	0.00281 U	0.000275 U	0.000270 U	0.00209 U	0.000235 U	0.00111 U	0.00111 U	0.000286 U	0.000229 U	0.000223 U
	B-228-36	11/29/17	PES	ESC	36	3.1	S	0.000386 U	0.000328 U	0.00286 U	0.000280 U	0.000275 U	0.00212 U	0.000239 U	0.00113 U	0.00113 U	0.000291 U	0.000233 U	0.000227 U
B-229	B-229-6	11/29/17	PES	ESC	6	33.1	S	0.000500 U	0.000424 U	0.00370 U	0.000363 U	0.000356 U	0.00275 U	0.000310 U	0.00146 U	0.00146 U	0.000378 U	0.000301 U	0.000294 U
	B-229-11	11/29/17	PES	ESC	11	28.1	S	0.000485 U	0.000412 U	0.00359 U	0.000352 U	0.000345 U	0.00267 U	0.000301 U	0.00142 U	0.00142 U	0.000366 U	0.000292 U	0.000285 U
	B-229-16	11/29/17	PES	ESC	16	23.1	S	0.000408 U	0.000346 U	0.00302 U	0.000296 U	0.000290 U	0.00224 U	0.000253 U	0.00119 U	0.00119 U	0.000308 U	0.000246 U	0.000240 U
	B-229-25	11/29/17	PES	ESC	25	14.1	S	0.000375 U	0.000318 U	0.00277 U	0.000272 U	0.000266 U	0.00206 U	0.000232 U	0.00110 U	0.00110 U	0.000283 U	0.000226 U	0.000220 U
	B-229-31	11/29/17	PES	ESC	31	8.1	S	0.000412 U	0.000350 U	0.00305 U	0.000299 U	0.000293 U	0.00227 U	0.000256 U	0.00121 U	0.00121 U	0.000311 U	0.000248 U	0.000242 U
	B-229-36	11/29/17	PES	ESC	36	3.1	S	0.000376 U	**0.00192 J**	0.00278 U	0.000273 U	0.000267 U	0.00207 U	0.000233 U	0.00110 U	0.00110 U	0.000284 U	0.000227 U	0.000221 U
	B-229-41	11/29/17	PES	ESC	41	-1.9	S	0.000398 U	0.000338 U	0.00295 U	0.000289 U	0.000283 U	0.00219 U	0.000247 U	0.00116 U	0.00116 U	0.000300 U	**0.000280 J**	0.000234 U
	B-229-45	11/29/17	PES	ESC	45	-5.9	S	0.000409 U	**0.000389 J**	0.00303 U	0.000297 U	0.000291 U	0.00225 U	0.000254 U	0.00120 U	0.00120 U	0.000309 U	0.000246 U	0.000240 U
B-230	B-230-6	11/30/17	PES	ESC	6	33.1	S	0.000361 U	0.000306 U	0.00267 U	0.000262 U	0.000256 U	0.00198 U	0.000224 U	0.00105 U	0.00105 U	0.000272 U	0.000217 U	0.000212 U
	B-230-11	11/30/17	PES	ESC	11	28.1	S	0.000374 U	0.000317 U	0.00276 U	0.000271 U	0.000265 U	0.00205 U	0.000232 U	0.00109 U	0.00109 U	0.000282 U	0.000225 U	0.000220 U
	B-230-16	11/30/17	PES	ESC	16	23.1	S	0.0952 U	0.0807 U	0.703 U	0.0690 U	0.0677 U	0.523 U	0.0590 U	0.278 U	0.278 U	0.0718 U	0.0573 U	0.0559 U
	B-230-21	11/30/17	PES	ESC	21	18.1	S	0.817 U	0.692 U	6.04 U	0.592 U	0.580 U	4.49 U	0.506 U	2.39 U	2.39 U	0.616 U	0.492 U	0.480 U
	B-922-15	11/30/17	PES	ESC	21 (dup)	18.1	S	0.413 U	0.350 U	3.06 U	0.299 U	0.293 U	2.27 U	0.256 U	1.21 U	1.21 U	0.312 U	0.249 U	0.243 U
	B-230-26	11/30/17	PES	ESC	26	13.1	S	1.02 U	0.869 U	7.57 U	0.743 U	0.729 U	5.63 U	0.635 U	3.00 U	3.00 U	0.773 U	0.617 U	0.602 U
	B-230-31	11/30/17	PES	ESC	31	8.1	S	0.425 U	0.361 U	3.15 U	0.308 U	0.302 U	2.34 U	0.264 U	1.24 U	1.24 U	0.321 U	0.256 U	0.250 U
	B-230-35	11/30/17	PES	ESC	35	4.1	S	0.0618 U	0.0524 U	0.457 U	0.0447 U	0.0439 U	0.340 U	0.0383 U	0.181 U	0.181 U	0.0466 U	0.0372 U	0.0364 U
	B-230-55	11/30/17	PES	ESC	55	-15.9	S	0.103 U	0.0870 U	0.759 U	0.0744 U	0.0730 U	0.564 U	0.0636 U	0.300 U	0.300 U	0.0774 U	0.0618 U	0.0603 U
B-231	B-231-6	11/30/17	PES	ESC	6	33.1	S	0.000422 U	0.000358 U	0.00312 U	0.000306 U	0.000300 U	0.00232 U	0.000261 U	0.00123 U	0.00123 U	0.000318 U	0.000254 U	0.000248 U
	B-231-11	11/30/17	PES	ESC	11	28.1	S	0.000403 U	0.000342 U	0.00298 U	0.000292 U	0.000286 U	0.00222 U	0.000250 U	0.00118 U	0.00118 U	0.000304 U	0.000243 U	0.000237 U
	B-231-16	11/30/17	PES	ESC	16	23.1	S	0.00958 U	0.00812 U	0.0708 U	0.00695 U	0.00681 U	0.0527 U	0.00594 U	0.0280 U	0.0280 U	0.00723 U	0.00577 U	0.00562 U
	B-231-21	11/30/17	PES	ESC	21	18.1	S	0.0226 U	**0.0214 J**	0.167 U	0.0164 U	0.0160 U	0.124 U	0.0140 U	0.0661 U	0.0661 U	0.0171 U	0.0136 U	0.0132 U
	B-231-26	11/30/17	PES	ESC	26	13.1	S	0.000397 U	**0.00165 J**	0.00294 U	0.000288 U	0.000282 U	0.00218 U	0.000246 U	0.00116 U	0.00116 U	0.000300 U	0.000239 U	0.000233 U
	B-231-30	11/30/17	PES	ESC	30	9.1	S	0.000386 U	0.000327 U	0.00285 U	0.000280 U	0.000274 U	0.00212 U	0.000239 U	0.00113 U	0.00113 U	0.000291 U	0.000232 U	0.000227 U
	B-231-36	11/30/17	PES	ESC	36	3.1	S	0.000388 U	0.000329 U	0.00287 U	0.000281 U	0.000276 U	0.00213 U	0.000240 U	0.00113 U	0.00113 U	0.000293 U	0.000234 U	0.000228 U
B-232	B-232-6	12/1/17	PES	ESC	6	33.1	S	0.000404 U	**0.000870 J**	0.00299 U	0.000293 U	0.000287 U	0.00222 U	0.000250 U	0.00118 U	0.00118 U	0.000305 U	0.000243 U	0.000237 U
	B-232-11	12/1/17	PES	ESC	11	28.1	S	0.000455 U	0.000386 U	0.00337 U	0.000330 U	0.000323 U	0.00250 U	0.000282 U	0.00133 U	0.00133 U	0.000343 U	0.000274 U	0.000267 U
	B-232-16	12/1/17	PES	ESC	16	23.1	S	0.000400 U	0.000340 U	0.00296 U	0.000290 U	0.000285 U	0.00220 U	0.000248 U	0.00117 U	0.00117 U	0.000302 U	0.000241 U	0.000235 U
	B-232-21	12/1/17	PES	ESC	21	18.1	S	0.000383 U	0.000325 U	0.00283 U	0.000278 U	0.000272 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000289 U	0.000231 U	0.000225 U
	B-232-26	12/1/17	PES	ESC	26	13.1	S	0.0128 U	0.0108 U	0.0945 U	0.00926 U	0.00907 U	0.0702 U	0.00792 U	0.0374 U	0.0374 U	0.00964 U	0.00770 U	0.00751 U
	B-232-31	12/1/17	PES	ESC	31	8.1	S	0.000386 U	0.000327 U	0.00286 U	0.000280 U	0.000274 U	0.00212 U	0.000239 U	0.00113 U	0.00113 U	0.000291 U	0.000233 U	0.000227 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
B-232 (continued)	B-232-36	12/1/17	PES	ESC	36	3.1	S	0.000405 U	0.000344 U	0.00300 U	0.000294 U	0.000288 U	0.00223 U	0.000251 U	0.00119 U	0.00119 U	0.000306 U	0.000244 U	0.000238 U
B-233	B-233-6	12/1/17	PES	ESC	6	29.5	S	0.000369 U	0.000313 U	0.00273 U	0.000268 U	0.000262 U	0.00203 U	0.000229 U	0.00108 U	0.00108 U	0.000278 U	0.000222 U	0.000217 U
	B-233-11	12/1/17	PES	ESC	11	24.5	S	0.000954 U	0.000809 U	0.00706 U	0.000692 U	0.000678 U	0.00525 U	0.000591 U	0.00279 U	0.00279 U	0.000719 U	0.000574 U	0.000560 U
	B-233-16	12/1/17	PES	ESC	16	19.5	S	0.000483 U	0.000409 U	0.00356 U	0.000350 U	0.000343 U	0.00265 U	0.000299 U	0.00141 U	0.00141 U	0.000364 U	0.000291 U	0.000283 U
	B-233-21	12/1/17	PES	ESC	21	14.5	S	0.00975 U	0.00827 U	0.0721 U	0.00707 U	0.00694 U	0.0536 U	0.00605 U	0.0285 U	0.0285 U	0.00736 U	0.00588 U	0.00573 U
	B-233-26	12/1/17	PES	ESC	26	9.5	S	0.0204 U	0.0173 U	0.151 U	0.0148 U	0.0146 U	0.112 U	0.0127 U	0.0598 U	0.0598 U	0.0154 U	0.0123 U	0.0120 U
	B-233-31	12/1/17	PES	ESC	31	4.5	S	0.0106 U	0.00901 U	0.0786 U	0.00771 U	0.00756 U	0.0584 U	0.00659 U	0.0311 U	0.0311 U	0.00802 U	0.00640 U	0.00624 U
	B-233-36	12/1/17	PES	ESC	36	-0.5	S	0.00962 U	0.00816 U	0.0711 U	0.00698 U	0.00684 U	0.0529 U	0.00597 U	0.0281 U	0.0281 U	0.00726 U	0.00580 U	0.00565 U
B-234	B-234-11	12/4/17	PES	ESC	11	40.8	V	0.000398 U	0.000337 U	0.00294 U	0.000288 U	0.000283 U	0.00219 U	0.000246 U	0.00116 U	0.00116 U	0.000300 U	0.000240 U	0.000234 U
	B-234-30	12/4/17	PES	ESC	30	21.8	S	0.000362 U	0.000307 U	0.00268 U	0.000263 U	0.000257 U	0.00199 U	0.000224 U	0.00106 U	0.00106 U	0.000273 U	0.000218 U	0.000213 U
B-234A	B-234A-35	12/4/17	PES	ESC	35	16.8	S	0.000392 U	0.000333 U	0.00290 U	0.000284 U	0.000279 U	0.00216 U	0.000243 U	0.00115 U	0.00115 U	0.000296 U	0.000236 U	0.000231 U
	B-234A-40	12/4/17	PES	ESC	40	11.8	S	0.000368 U	0.000312 U	0.00272 U	0.000267 U	0.000262 U	0.00202 U	0.000228 U	0.00108 U	0.00108 U	0.000278 U	0.000222 U	0.000216 U
	B-234A-42	12/4/17	PES	ESC	42	9.8	S	0.000419 U	0.000355 U	0.00310 U	0.000304 U	0.000298 U	0.00230 U	0.000260 U	0.00123 U	0.00123 U	0.000316 U	0.000252 U	0.000246 U
	B-924-30	12/4/17	PES	ESC	42 (dup)	9.8	S	0.000415 U	0.000352 U	0.00307 U	0.000301 U	0.000295 U	0.00228 U	0.000257 U	0.00121 U	0.00121 U	0.000313 U	0.000250 U	0.000244 U
	B-234A-45	12/4/17	PES	ESC	45	6.8	S	0.000385 U	**0.00818 J**	0.00285 U	0.000279 U	0.000274 U	0.00212 U	0.000239 U	0.00113 U	0.00113 U	0.000291 U	0.000232 U	0.000227 U
B-235	B-235-15	12/5/17	PES	ESC	15	36.8	V	0.000410 U	0.000348 U	0.00303 U	0.000298 U	0.000291 U	0.00226 U	0.000255 U	0.00120 U	0.00120 U	0.000310 U	0.000247 U	0.000241 U
	B-235-35	12/5/17	PES	ESC	35	16.8	S	0.000379 U	0.000321 U	0.00280 U	0.000275 U	0.000269 U	0.00208 U	0.000235 U	0.00111 U	0.00111 U	0.000286 U	0.000228 U	0.000223 U
	B-235-40	12/5/17	PES	ESC	40	11.8	S	0.000375 U	**0.000757 J**	0.00277 U	0.000272 U	0.000266 U	0.00206 U	0.000232 U	0.00110 U	0.00110 U	0.000283 U	0.000226 U	0.000220 U
	B-235-42.5	12/5/17	PES	ESC	42.5	9.3	S	0.0747 U	0.0633 U	0.553 U	0.0542 U	0.0531 U	0.411 U	0.0463 U	0.218 U	0.218 U	0.0563 U	0.0450 U	0.0439 U
	B-235-45	12/5/17	PES	ESC	45	6.8	S	0.000385 U	**0.000505 J**	0.00285 U	0.000279 U	0.000274 U	0.00212 U	0.000239 U	0.00113 U	0.00113 U	0.000291 U	0.000232 U	0.000226 U
B-236	B-236-20	12/5/17	PES	ESC	20	31.8	S	0.000391 U	0.000332 U	0.00289 U	0.000284 U	0.000278 U	0.00215 U	0.000242 U	0.00114 U	0.00114 U	0.000295 U	0.000236 U	0.000230 U
	B-236-35	12/5/17	PES	ESC	35	16.8	S	0.000619 U	0.000526 U	0.00458 U	0.000449 U	0.000440 U	0.00340 U	0.000385 U	0.00181 U	0.00181 U	0.000467 U	0.000373 U	0.000365 U
	B-236-40	12/5/17	PES	ESC	40	11.8	S	0.000378 U	**0.000486 J**	0.00280 U	0.000274 U	0.000269 U	0.00208 U	0.000235 U	0.00111 U	0.00111 U	0.000285 U	0.000228 U	0.000222 U
	B-236-42.5	12/5/17	PES	ESC	42.5	9.3	S	0.401 U	0.340 U	2.97 U	0.291 U	0.285 U	2.20 U	0.249 U	1.17 U	1.17 U	0.303 U	**0.355 J**	0.236 U
	B-236-45	12/5/17	PES	ESC	45	6.8	S	0.134 U	0.114 U	0.994 U	0.0974 U	0.0955 U	0.738 U	0.0833 U	0.393 U	0.393 U	0.101 U	0.0809 U	0.0790 U
B-237	B-237-5	12/6/17	PES	ESC	5	46.8	V	0.000398 U	0.000338 U	0.00295 U	0.000289 U	0.000283 U	0.00219 U	0.000247 U	0.00116 U	0.00116 U	0.000301 U	0.000240 U	0.000234 U
	B-237-35	12/6/17	PES	ESC	35	16.8	S	0.000399 U	0.000339 U	0.00296 U	0.000290 U	0.000284 U	0.00220 U	0.000248 U	0.00117 U	0.00117 U	0.000301 U	0.000241 U	0.000235 U
	B-237-40	12/6/17	PES	ESC	40	11.8	S	0.000367 U	0.000312 U	0.00272 U	0.000266 U	0.000261 U	0.00202 U	0.000228 U	0.00107 U	0.00107 U	0.000277 U	0.000221 U	0.000216 U
	B-237-42	12/6/17	PES	ESC	42	9.8	S	0.000404 U	0.000343 U	0.00299 U	0.000293 U	0.000287 U	0.00222 U	0.000251 U	0.00118 U	0.00118 U	0.000305 U	0.000243 U	0.000238 U
	B-925-41	12/6/17	PES	ESC	42 (dup)	9.8	S	0.0437 U	0.0370 U	0.323 U	0.0317 U	0.0310 U	0.240 U	0.0271 U	0.128 U	0.128 U	0.0329 U	0.0263 U	0.0257 U
	B-237-45	12/6/17	PES	ESC	45	6.8	S	0.000440 U	**0.00162 J**	0.00326 U	0.000319 U	0.000313 U	0.00242 U	0.000273 U	0.00129 U	0.00129 U	0.000332 U	0.000265 U	0.000259 U
B-238	B-238-6	12/6/17	PES	ESC	6	33.1	S	0.000399 U	**0.000697 J**	0.00295 U	0.000289 U	0.000283 U	0.00219 U	0.000247 U	0.00117 U	0.00117 U	0.000301 U	0.000240 U	0.000234 U
	B-238-11	12/6/17	PES	ESC	11	28.1	S	0.000398 U	**0.00731 J**	0.00294 U	0.000289 U	0.000283 U	0.00219 U	0.000247 U	0.00116 U	0.00116 U	0.000300 U	**0.000502 J**	0.000234 U
	B-238-16	12/6/17	PES	ESC	16	23.1	S	0.0978 U	0.0829 U	0.723 U	0.0709 U	0.0696 U	0.538 U	0.0606 U	0.286 U	0.286 U	0.0738 U	0.0589 U	0.0574 U
	B-238-21	12/6/17	PES	ESC	21	18.1	S	0.382 U	0.324 U	2.82 U	0.277 U	0.271 U	2.10 U	0.237 U	1.12 U	1.12 U	0.288 U	0.230 U	0.224 U
	B-238-26	12/6/17	PES	ESC	26	13.1	S	0.000382 U	0.000324 U	0.00283 U	0.000277 U	0.000272 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000288 U	0.000230 U	0.000225 U
	B-238-31	12/6/17	PES	ESC	31	8.1	S	0.000363 U	0.000307 U	0.00268 U	0.000263 U	0.000258 U	0.00199 U	0.000225 U	0.00106 U	0.00106 U	0.000274 U	0.000218 U	0.000213 U
	B-238-36	12/6/17	PES	ESC	36	3.1	S	0.000401 U	0.000340 U	0.00296 U	0.000290 U	0.000285 U	0.00220 U	0.000248 U	0.00117 U	0.00117 U	0.000302 U	0.000241 U	0.000235 U
B-239	B-239-5	4/3/18	PES	ESC	5	34.2	S	0.000407 U	0.000345 U	0.00301 U	0.000295 U	0.000289 U	0.00224 U	0.000252 U	0.00119 U	0.00119 U	0.000307 U	0.000245 U	0.000239 U
	B-239-10	4/3/18	PES	ESC	10	29.2	S	0.000404 U	0.000342 U	0.00298 U	0.000293 U	0.000287 U	0.00222 U	0.000250 U	0.00118 U	0.00118 U	0.000304 U	0.000243 U	0.000237 U
	B-239-15	4/3/18	PES	ESC	15	24.2	S	0.000389 U	0.000330 U	0.00288 U	0.000282 U	0.000277 U	0.00214 U	0.000241 U	0.00114 U	0.00114 U	0.000294 U	0.000235 U	0.000229 U
	B-239-20	4/3/18	PES	ESC	20	19.2	S	0.000386 U	0.000327 U	0.00286 U	0.000280 U	0.000274 U	0.00212 U	0.000239 U	0.00113 U	0.00113 U	0.000291 U	0.000232 U	0.000227 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
B-239 (continued)	B-239-25	4/3/18	PES	ESC	25	14.2	S	0.000392 U	0.000332 U	0.00290 U	0.000284 U	0.000278 U	0.00215 U	0.000243 U	0.00115 U	0.00115 U	0.000296 U	0.000236 U	0.000230 U
	B-239-35	4/3/18	PES	ESC	35	4.2	S	0.000370 U	0.000314 U	0.00274 U	0.000268 U	0.000263 U	0.00204 U	0.000229 U	0.00108 U	0.00108 U	0.000279 U	0.000223 U	0.000218 U
	B-239-40	4/3/18	PES	ESC	40	-0.8	S	0.000388 U	0.000329 U	0.00287 U	0.000281 U	0.000276 U	0.00213 U	0.000241 U	0.00113 U	0.00113 U	0.000293 U	0.000234 U	0.000228 U
	B-239-45	4/3/18	PES	ESC	45	-5.8	S	0.000383 U	**0.000524 J**	0.00283 U	0.000278 U	0.000272 U	0.00211 U	0.000237 U	0.00112 U	0.00112 U	0.000289 U	0.000231 U	0.000225 U
	B-239-50	4/3/18	PES	ESC	50	-10.8	S	0.000378 U	0.000320 U	0.00279 U	0.000274 U	0.000268 U	0.00208 U	0.000234 U	0.00110 U	0.00110 U	0.000285 U	0.000228 U	0.000222 U
	B-909-50	4/3/18	PES	ESC	50 (dup)	-10.8	S	0.000380 U	**0.000391 J**	0.00281 U	0.000276 U	0.000270 U	0.00209 U	0.000236 U	0.00111 U	0.00111 U	0.000287 U	0.000229 U	0.000223 U
	B-239-55	4/3/18	PES	ESC	55	-15.8	S	0.000389 U	0.000330 U	0.00288 U	0.000282 U	0.000276 U	0.00214 U	0.000241 U	0.00114 U	0.00114 U	0.000294 U	0.000234 U	0.000229 U
	B-239-60	4/3/18	PES	ESC	60	-20.8	S	0.000382 U	**0.000378 J**	0.00283 U	0.000277 U	0.000272 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000289 U	0.000230 U	0.000225 U
	B-239-65	4/3/18	PES	ESC	65	-25.8	S	0.000382 U	0.000324 U	0.00283 U	0.000277 U	0.000272 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000288 U	0.000230 U	0.000225 U
	B-239-70	4/3/18	PES	ESC	70	-30.8	S	0.000381 U	0.000323 U	0.00282 U	0.000276 U	0.000271 U	0.00209 U	0.000236 U	0.00111 U	0.00111 U	0.000287 U	0.000229 U	0.000224 U
	B-239-75	4/3/18	PES	ESC	75	-35.8	S	0.000394 U	0.000334 U	0.00292 U	0.000286 U	0.000280 U	0.00217 U	0.000244 U	0.00115 U	0.00115 U	0.000297 U	0.000237 U	0.000232 U
	B-239-80	4/3/18	PES	ESC	80	-40.8	S	0.000391 U	0.000332 U	0.00290 U	0.000284 U	0.000278 U	0.00215 U	0.000243 U	0.00114 U	0.00114 U	0.000295 U	0.000236 U	0.000230 U
B-240	B-240-5	4/2/18	PES	ESC	5	34.2	S	0.000377 U	0.000320 U	0.00279 U	0.000274 U	0.000268 U	0.00207 U	0.000234 U	0.00110 U	0.00110 U	0.000285 U	0.000227 U	0.000222 U
	B-240-10	4/2/18	PES	ESC	10	29.2	S	0.000377 U	0.000320 U	0.00279 U	0.000273 U	0.000268 U	0.00207 U	0.000234 U	0.00110 U	0.00110 U	0.000284 U	0.000227 U	0.000222 U
	B-240-15	4/2/18	PES	ESC	15	24.2	S	0.000392 U	0.000333 U	0.00290 U	0.000285 U	0.000279 U	0.00216 U	0.000243 U	0.00115 U	0.00115 U	0.000296 U	0.000236 U	0.000231 U
	B-240-20	4/2/18	PES	ESC	20	19.2	S	0.000398 U	0.000338 U	0.00295 U	0.000289 U	0.000283 U	0.00219 U	0.000247 U	0.00116 U	0.00116 U	0.000300 U	0.000240 U	0.000234 U
	B-240-25	4/2/18	PES	ESC	25	14.2	S	0.0191 U	0.0162 U	0.141 U	0.0139 U	0.0136 U	0.105 U	0.0118 U	0.0559 U	0.0559 U	0.0144 U	0.0115 U	0.0112 U
	B-240-30	4/2/18	PES	ESC	30	9.2	S	0.000412 U	0.000349 U	0.00305 U	0.000299 U	0.000293 U	0.00226 U	0.000255 U	0.00120 U	0.00120 U	0.000311 U	0.000248 U	0.000242 U
	B-240-35	4/2/18	PES	ESC	35	4.2	S	0.000411 U	**0.00211 J**	0.00304 U	0.000298 U	0.000292 U	0.00226 U	0.000255 U	0.00120 U	0.00120 U	0.000310 U	0.000247 U	0.000241 U
	B-240-42	4/2/18	PES	ESC	42	-2.8	S	0.000368 U	0.000312 U	0.00272 U	0.000267 U	0.000262 U	0.00202 U	0.000228 U	0.00108 U	0.00108 U	0.000278 U	0.000222 U	0.000216 U
	B-240-45	4/2/18	PES	ESC	45	-5.8	S	0.000363 U	0.000308 U	0.00268 U	0.000263 U	0.000258 U	0.00199 U	0.000225 U	0.00106 U	0.00106 U	0.000274 U	0.000218 U	0.000213 U
	B-240-50	4/2/18	PES	ESC	50	-10.8	S	0.000385 U	0.000327 U	0.00285 U	0.000279 U	0.000274 U	0.00212 U	0.000239 U	0.00113 U	0.00113 U	0.000291 U	0.000232 U	0.000226 U
	B-240-55	4/2/18	PES	ESC	55	-15.8	S	0.000397 U	**0.000692 J**	0.00293 U	0.000288 U	0.000282 U	0.00218 U	0.000246 U	0.00116 U	0.00116 U	0.000299 U	0.000239 U	0.000233 U
	B-240-60	4/2/18	PES	ESC	60	-20.8	S	0.000398 U	**0.00116 J**	0.00295 U	0.000289 U	0.000283 U	0.00219 U	0.000247 U	0.00116 U	0.00116 U	0.000300 U	0.000240 U	0.000234 U
	B-240-65	4/2/18	PES	ESC	65	-25.8	S	0.000371 U	0.000314 U	0.00274 U	0.000269 U	0.000263 U	0.00204 U	0.000230 U	0.00108 U	0.00108 U	0.000280 U	0.000223 U	0.000218 U
	B-240-70	4/2/18	PES	ESC	70	-30.8	S	0.000396 U	**0.000860 J**	0.00293 U	0.000287 U	0.000281 U	0.00217 U	0.000245 U	0.00116 U	0.00116 U	0.000298 U	0.000238 U	0.000233 U
	B-240-75	4/2/18	PES	ESC	75	-35.8	S	0.000376 U	0.000318 U	0.00278 U	0.000272 U	0.000267 U	0.00206 U	0.000233 U	0.00110 U	0.00110 U	0.000283 U	0.000226 U	0.000221 U
	B-240-80	4/2/18	PES	ESC	80	-40.8	S	0.000389 U	0.000330 U	0.00288 U	0.000282 U	0.000276 U	0.00214 U	0.000241 U	0.00114 U	0.00114 U	0.000293 U	0.000234 U	0.000229 U
B-241	B-241-5	4/4/18	PES	ESC	5	34.1	S	0.000371 U	**0.0739**	0.00274 U	0.000269 U	**0.0169**	0.00204 U	0.000230 U	0.00108 U	**0.0651**	**0.0102**	**0.0615**	**0.00470**
	B-241-10	4/4/18	PES	ESC	10	29.1	S	0.000388 U	**0.000331 J**	0.00287 U	0.000281 U	0.000276 U	0.00213 U	0.000240 U	0.00113 U	**0.00187 J**	0.000293 U	0.000234 U	0.000228 U
	B-241-15	4/4/18	PES	ESC	15	24.1	S	0.000382 U	0.000324 U	0.00282 U	0.000277 U	0.000271 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000288 U	0.000230 U	0.000224 U
	B-241-20	4/4/18	PES	ESC	20	19.1	S	0.000416 U	0.000353 U	0.00308 U	0.000302 U	0.000296 U	0.00229 U	0.000258 U	0.00122 U	0.00122 U	0.000314 U	0.000251 U	0.000245 U
	B-241-25	4/4/18	PES	ESC	25	14.1	S	0.000387 U	0.000328 U	0.00286 U	0.000280 U	0.000275 U	0.00212 U	0.000240 U	0.00113 U	0.00113 U	0.000292 U	0.000233 U	0.000227 U
	B-241-30	4/3/18	PES	ESC	30	9.1	S	0.000384 U	0.000325 U	0.00284 U	0.000278 U	0.000273 U	0.00211 U	0.000238 U	0.00112 U	0.00112 U	0.000289 U	0.000231 U	0.000225 U
	B-241-35	4/3/18	PES	ESC	35	4.1	S	0.000396 U	0.000336 U	0.00293 U	0.000287 U	0.000281 U	0.00218 U	0.000245 U	0.00116 U	0.00116 U	0.000299 U	0.000238 U	0.000233 U
	B-241-40	4/3/18	PES	ESC	40	-0.9	S	0.000375 U	0.000318 U	0.00278 U	0.000272 U	0.000267 U	0.00206 U	0.000233 U	0.00110 U	0.00110 U	0.000283 U	0.000226 U	0.000221 U
	B-241-45	4/3/18	PES	ESC	45	-5.9	S	0.000377 U	0.000319 U	0.00279 U	0.000273 U	0.000268 U	0.00207 U	0.000233 U	0.00110 U	0.00110 U	0.000284 U	0.000227 U	0.000221 U
	B-241-50	4/4/18	PES	ESC	50	-10.9	S	0.000385 U	**0.000927 J**	0.00285 U	0.000279 U	0.000274 U	0.00212 U	0.000239 U	0.00113 U	0.00113 U	0.000291 U	0.000232 U	0.000227 U
	B-241-55	4/4/18	PES	ESC	55	-15.9	S	0.000398 U	0.000338 U	0.00295 U	0.000289 U	0.000283 U	0.00219 U	0.000247 U	0.00116 U	0.00116 U	0.000300 U	0.000240 U	0.000234 U
	B-241-60	4/3/18	PES	ESC	60	-20.9	S	0.000383 U	0.000325 U	0.00283 U	0.000278 U	0.000272 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000289 U	0.000231 U	0.000225 U
	B-241-65	4/3/18	PES	ESC	65	-25.9	S	0.000405 U	**0.000482 J**	0.00299 U	0.000294 U	0.000288 U	0.00223 U	0.000251 U	0.00118 U	0.00118 U	0.000305 U	0.000244 U	0.000238 U
	B-241-70	4/3/18	PES	ESC	70	-30.9	S	0.000395 U	0.000335 U	0.00292 U	0.000286 U	0.000281 U	0.00217 U	0.000245 U	0.00115 U	0.00115 U	0.000298 U	0.000238 U	0.000232 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
B-241	B-241-75	4/3/18	PES	ESC	75	-35.9	S	0.000399 U	0.000338 U	0.00295 U	0.000289 U	0.000283 U	0.00219 U	0.000247 U	0.00117 U	0.00117 U	0.000301 U	0.000240 U	0.000234 U
(continued)	B-241-80	4/4/18	PES	ESC	80	-40.9	S	0.000393 U	0.000333 U	0.00291 U	0.000285 U	0.000279 U	0.00216 U	0.000244 U	0.00115 U	0.00115 U	0.000296 U	0.000237 U	0.000231 U
B-242	B-242-5	4/4/18	PES	ESC	5	33.8	S	0.000371 U	0.000315 U	0.00275 U	0.000269 U	0.000264 U	0.00204 U	0.000230 U	0.00109 U	0.00109 U	0.000280 U	0.000224 U	0.000218 U
	B-242-10	4/4/18	PES	ESC	10	28.8	S	0.000374 U	0.000317 U	0.00277 U	0.000271 U	0.000266 U	0.00206 U	0.000232 U	0.00109 U	0.00109 U	0.000282 U	0.000225 U	0.000220 U
	B-242-15	4/4/18	PES	ESC	15	23.8	S	0.000399 U	0.000338 U	0.00295 U	0.000289 U	0.000283 U	0.00219 U	0.000247 U	0.00117 U	0.00117 U	0.000301 U	0.000240 U	0.000234 U
	B-242-20	4/4/18	PES	ESC	20	18.8	S	0.000387 U	0.000329 U	0.00287 U	0.000281 U	0.000275 U	0.00213 U	0.000240 U	0.00113 U	0.00113 U	0.000292 U	0.000233 U	0.000228 U
	B-242-25	4/4/18	PES	ESC	25	13.8	S	0.0377 U	0.0320 U	0.279 U	0.0273 U	0.0268 U	0.207 U	0.0234 U	0.110 U	0.110 U	0.0284 U	0.0227 U	0.0222 U
	B-242-30	4/4/18	PES	ESC	30	8.8	S	0.000383 U	0.000324 U	0.00283 U	0.000277 U	0.000272 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000289 U	0.000230 U	0.000225 U
	B-242-35	4/4/18	PES	ESC	35	3.8	S	0.000394 U	0.000334 U	0.00291 U	0.000286 U	0.000280 U	0.00216 U	0.000244 U	0.00115 U	0.00115 U	0.000297 U	0.000237 U	0.000231 U
	B-242-40	4/4/18	PES	ESC	40	-1.2	S	0.000374 U	0.000317 U	0.00277 U	0.000271 U	0.000266 U	0.00206 U	0.000232 U	0.00109 U	0.00109 U	0.000282 U	0.000225 U	0.000220 U
	B-242-45	4/4/18	PES	ESC	45	-6.2	S	0.000396 U	0.000335 U	0.00293 U	0.000287 U	0.000281 U	0.00217 U	0.000245 U	0.00116 U	0.00116 U	0.000298 U	0.000238 U	0.000232 U
	B-242-50	4/4/18	PES	ESC	50	-11.2	S	0.000383 U	0.000325 U	0.00283 U	0.000278 U	0.000272 U	0.00211 U	0.000237 U	0.00112 U	0.00112 U	0.000289 U	0.000231 U	0.000225 U
	B-910-50	4/4/18	PES	ESC	50 (dup)	-11.2	S	0.000384 U	0.000325 U	0.00284 U	0.000278 U	0.000273 U	0.00211 U	0.000238 U	0.00112 U	0.00112 U	0.000289 U	0.000231 U	0.000226 U
	B-242-55	4/4/18	PES	ESC	55	-16.2	S	0.000376 U	0.000319 U	0.00278 U	0.000272 U	0.000267 U	0.00206 U	0.000233 U	0.00110 U	0.00110 U	0.000283 U	0.000226 U	0.000221 U
	B-242-60	4/4/18	PES	ESC	60	-21.2	S	0.000377 U	0.000320 U	0.00279 U	0.000274 U	0.000268 U	0.00207 U	0.000234 U	0.00110 U	0.00110 U	0.000285 U	0.000227 U	0.000222 U
	B-242-65	4/4/18	PES	ESC	65	-26.2	S	0.000370 U	0.000314 U	0.00274 U	0.000269 U	0.000263 U	0.00204 U	0.000230 U	0.00108 U	0.00108 U	0.000279 U	0.000223 U	0.000218 U
	B-242-70	4/4/18	PES	ESC	70	-31.2	S	0.000392 U	0.000332 U	0.00290 U	0.000284 U	0.000278 U	0.00215 U	0.000243 U	0.00115 U	0.00115 U	0.000296 U	0.000236 U	0.000230 U
	B-242-75	4/4/18	PES	ESC	75	-36.2	S	0.000379 U	0.000322 U	0.00281 U	0.000275 U	0.000270 U	0.00209 U	0.000235 U	0.00111 U	0.00111 U	0.000286 U	0.000229 U	0.000223 U
	B-242-80	4/4/18	PES	ESC	80	-41.2	S	0.000396 U	0.000336 U	0.00293 U	0.000287 U	0.000282 U	0.00218 U	0.000246 U	0.00116 U	0.00116 U	0.000299 U	0.000239 U	0.000233 U
B-243	B-243-5	3/29/18	PES	ESC	5	34.9	S	0.000397 U	0.000337 U	0.00294 U	0.000288 U	0.000282 U	0.00218 U	0.000246 U	0.00116 U	0.00116 U	0.000300 U	0.000239 U	0.000233 U
	B-243-10	3/29/18	PES	ESC	10	29.9	S	0.000388 U	**0.000483 J**	0.00287 U	0.000282 U	0.000276 U	0.00214 U	0.000241 U	0.00114 U	0.00114 U	**0.00143**	0.000234 U	**0.000993 J**
	B-243-15	3/29/18	PES	ESC	15	24.9	S	0.00967 U	0.00820 U	0.0715 U	0.00702 U	0.00688 U	0.0532 U	0.00600 U	0.0283 U	0.0283 U	0.00730 U	0.00583 U	0.00568 U
	B-243-20	3/29/18	PES	ESC	20	19.9	S	0.000394 U	0.000334 U	0.00292 U	0.000286 U	0.000280 U	0.00217 U	0.000244 U	0.00115 U	0.00115 U	0.000298 U	0.000238 U	0.000232 U
	B-243-25	3/29/18	PES	ESC	25	14.9	S	0.000381 U	**0.0248 J**	0.00282 U	0.000276 U	0.000271 U	0.00210 U	0.000236 U	0.00111 U	0.00111 U	0.000288 U	0.000230 U	0.000224 U
	B-243-30	3/29/18	PES	ESC	30	9.9	S	0.000372 U	0.000316 U	0.00276 U	0.000270 U	0.000265 U	0.00205 U	0.000231 U	0.00109 U	0.00109 U	0.000281 U	0.000224 U	0.000219 U
	B-243-35	3/29/18	PES	ESC	35	4.9	S	0.000379 U	0.000321 U	0.00280 U	0.000275 U	0.000269 U	0.00208 U	0.000235 U	0.00111 U	0.00111 U	0.000286 U	0.000228 U	0.000223 U
	B-243-42	3/29/18	PES	ESC	42	-2.1	S	0.000374 U	0.000317 U	0.00276 U	0.000271 U	0.000266 U	0.00205 U	0.000232 U	0.00109 U	0.00109 U	0.000282 U	0.000225 U	0.000220 U
	B-243-45	3/29/18	PES	ESC	45	-5.1	S	0.000371 U	**0.000612 J**	0.00274 U	0.000269 U	0.000263 U	0.00204 U	0.000230 U	0.00108 U	0.00108 U	0.000280 U	0.000223 U	0.000218 U
	B-243-50	3/29/18	PES	ESC	50	-10.1	S	0.000395 U	0.000335 U	0.00292 U	0.000286 U	0.000281 U	0.00217 U	0.000245 U	0.00115 U	0.00115 U	0.000298 U	0.000238 U	0.000232 U
	IW-908-50	3/29/18	PES	ESC	50 (dup)	-10.1	S	0.000387 U	**0.000343 J**	0.00286 U	0.000281 U	0.000275 U	0.00213 U	0.000240 U	0.00113 U	0.00113 U	0.000292 U	0.000233 U	0.000227 U
	B-243-55	3/29/18	PES	ESC	55	-15.1	S	0.000369 U	0.000313 U	0.00273 U	0.000268 U	0.000262 U	0.00203 U	0.000229 U	0.00108 U	0.00108 U	0.000279 U	0.000222 U	0.000217 U
	B-243-60	3/29/18	PES	ESC	60	-20.1	S	0.000391 U	**0.000353 J**	0.00289 U	0.000283 U	0.000278 U	0.00215 U	0.000242 U	0.00114 U	0.00114 U	0.000295 U	0.000235 U	0.000230 U
	B-243-65	3/29/18	PES	ESC	65	-25.1	S	0.000376 U	**0.000804 J**	0.00278 U	0.000272 U	0.000267 U	0.00206 U	0.000233 U	0.00110 U	0.00110 U	0.000283 U	0.000226 U	0.000221 U
	B-243-70	3/29/18	PES	ESC	70	-30.1	S	0.000397 U	0.000336 U	0.00293 U	0.000288 U	0.000282 U	0.00218 U	0.000246 U	0.00116 U	0.00116 U	0.000299 U	0.000239 U	0.000233 U
	B-243-75	3/29/18	PES	ESC	75	-35.1	S	0.000407 U	0.000346 U	0.00301 U	0.000295 U	0.000290 U	0.00224 U	0.000253 U	0.00119 U	0.00119 U	0.000307 U	0.000245 U	0.000239 U
	B-243-80	3/29/18	PES	ESC	80	-40.1	S	0.000415 U	0.000352 U	0.00307 U	0.000301 U	0.000295 U	0.00228 U	0.000258 U	0.00121 U	0.00121 U	0.000313 U	0.000250 U	0.000244 U
B-244	B-244-5	3/28/18	PES	ESC	5	33.8	S	0.000432 U	0.000366 U	0.00319 U	0.000313 U	0.000307 U	**0.00267 J**	0.000268 U	0.00126 U	0.00126 U	0.000326 U	0.000260 U	0.000254 U
	B-244-10	3/28/18	PES	ESC	10	28.8	S	0.000407 U	0.000346 U	0.00301 U	0.000295 U	0.000290 U	0.00224 U	0.000253 U	0.00119 U	0.00119 U	0.000307 U	0.000245 U	0.000239 U
	B-244-15	3/28/18	PES	ESC	15	23.8	S	0.000390 U	0.000331 U	0.00289 U	0.000283 U	0.000277 U	0.00215 U	0.000242 U	0.00114 U	0.00114 U	0.000294 U	0.000235 U	0.000229 U
	B-244-20	3/28/18	PES	ESC	20	18.8	S	0.000388 U	0.000329 U	0.00287 U	0.000281 U	0.000276 U	0.00213 U	0.000241 U	0.00113 U	0.00113 U	0.000293 U	0.000234 U	0.000228 U
	B-244-25	3/28/18	PES	ESC	25	13.8	S	0.000362 U	0.000307 U	0.00268 U	0.000263 U	0.000257 U	0.00199 U	0.000224 U	0.00106 U	0.00106 U	0.000273 U	0.000218 U	0.000213 U
	B-244-30	3/28/18	PES	ESC	30	8.8	S	0.000374 U	0.000317 U	0.00277 U	0.000271 U	0.000266 U	0.00206 U	0.000232 U	0.00109 U	0.00109 U	0.000282 U	0.000225 U	0.000220 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	–	–	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	–	–	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
B-244 (continued)	B-244-35	3/28/18	PES	ESC	35	3.8	S	0.000393 U	0.000333 U	0.00291 U	0.000285 U	0.000279 U	0.00216 U	0.000243 U	0.00115 U	0.00115 U	0.000296 U	0.000237 U	0.000231 U
	B-244-40	3/28/18	PES	ESC	40	-1.2	S	0.000377 U	0.000320 U	0.00279 U	0.000274 U	0.000268 U	0.00207 U	0.000234 U	0.00110 U	0.00110 U	0.000285 U	0.000227 U	0.000222 U
	B-244-42	3/28/18	PES	ESC	42	-3.2	S	0.00962 U	0.00816 U	0.0711 U	0.00698 U	0.00684 U	0.0529 U	0.00596 U	0.0281 U	0.0281 U	0.00726 U	0.00579 U	0.00565 U
	B-244-45	3/28/18	PES	ESC	45	-6.2	S	0.000385 U	0.000326 U	0.00285 U	0.000279 U	0.000273 U	0.00212 U	0.000239 U	0.00113 U	0.00113 U	0.000290 U	0.000232 U	0.000226 U
	B-244-50	3/28/18	PES	ESC	50	-11.2	S	0.000378 U	0.000321 U	0.00280 U	0.000274 U	0.000269 U	0.00208 U	0.000234 U	0.00111 U	0.00111 U	0.000285 U	0.000228 U	0.000222 U
	B-244-55	3/28/18	PES	ESC	55	-16.2	S	0.000377 U	0.000319 U	0.00279 U	0.000273 U	0.000268 U	0.00207 U	0.000233 U	0.00110 U	0.00110 U	0.000284 U	0.000227 U	0.000221 U
	B-244-60	3/28/18	PES	ESC	60	-21.2	S	0.000382 U	0.000324 U	0.00282 U	0.000277 U	0.000271 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000288 U	0.000230 U	0.000224 U
	B-244-65	3/28/18	PES	ESC	65	-26.2	S	0.000388 U	0.000329 U	0.00287 U	0.000281 U	0.000275 U	0.00213 U	0.000240 U	0.00113 U	0.00113 U	0.000293 U	0.000234 U	0.000228 U
	B-244-70	3/28/18	PES	ESC	70	-31.2	S	0.000371 U	0.000315 U	0.00275 U	0.000269 U	0.000264 U	0.00204 U	0.000230 U	0.00109 U	0.00109 U	0.000280 U	0.000224 U	0.000218 U
	IW-907-70	3/28/18	PES	ESC	70 (dup)	-31.2	S	0.000372 U	**0.00100**	0.00275 U	0.000270 U	0.000265 U	0.00205 U	0.000231 U	0.00109 U	0.00109 U	0.000281 U	0.000224 U	0.000219 U
	B-244-75	3/28/18	PES	ESC	75	-36.2	S	0.000392 U	**0.000507**	0.00290 U	0.000284 U	0.000279 U	0.00216 U	0.000243 U	0.00115 U	0.00115 U	0.000296 U	0.000236 U	0.000231 U
	B-244-80	3/28/18	PES	ESC	80	-41.2	S	0.000398 U	**0.000649**	0.00294 U	0.000288 U	0.000282 U	0.00219 U	0.000246 U	0.00116 U	0.00116 U	0.000300 U	0.000239 U	0.000234 U
B-245	B-245-5	3/28/18	PES	ESC	5	34.9	V	0.000372 U	**0.000383**	0.00275 U	0.000270 U	0.000264 U	0.00205 U	0.000231 U	0.00109 U	0.00109 U	0.000281 U	0.000224 U	0.000219 U
	B-245-10	3/28/18	PES	ESC	10	29.9	S	0.000392 U	0.000333 U	0.00290 U	0.000285 U	0.000279 U	0.00216 U	0.000243 U	0.00115 U	0.00115 U	0.000296 U	0.000236 U	0.000231 U
	B-245-15	3/28/18	PES	ESC	15	24.9	S	0.000396 U	0.000336 U	0.00293 U	0.000287 U	0.000282 U	0.00218 U	0.000246 U	0.00116 U	0.00116 U	0.000299 U	0.000239 U	0.000233 U
	B-245-20	3/28/18	PES	ESC	20	19.9	S	0.000369 U	**0.000509**	0.00273 U	0.000268 U	0.000262 U	0.00203 U	0.000229 U	0.00108 U	0.00108 U	0.000279 U	0.000222 U	0.000217 U
	B-245-25	3/28/18	PES	ESC	25	14.9	S	0.000387 U	**0.000403**	0.00286 U	0.000281 U	0.000275 U	0.00213 U	0.000240 U	0.00113 U	0.00113 U	0.000292 U	0.000233 U	0.000227 U
	B-245-30	3/29/18	PES	ESC	30	9.9	S	0.000735 U	**0.00113**	0.00544 U	0.000533 U	0.000523 U	0.00404 U	0.000456 U	0.00215 U	0.00215 U	0.000555 U	0.000443 U	0.000433 U
	B-245-35	3/29/18	PES	ESC	35	4.9	S	0.000385 U	0.000326 U	0.00285 U	0.000279 U	0.000273 U	0.00212 U	0.000239 U	0.00113 U	0.00113 U	0.000290 U	0.000232 U	0.000226 U
	B-245-40	3/29/18	PES	ESC	40	-0.1	S	0.000381 U	0.000323 U	0.00282 U	0.000276 U	0.000270 U	0.00209 U	0.000236 U	0.00111 U	0.00111 U	0.000287 U	0.000229 U	0.000224 U
	B-245-45	3/29/18	PES	ESC	45	-5.1	S	0.000380 U	0.000322 U	0.00281 U	0.000276 U	0.000270 U	0.00209 U	0.000236 U	0.00111 U	0.00111 U	0.000287 U	0.000229 U	0.000223 U
	B-245-50	3/29/18	PES	ESC	50	-10.1	S	0.000388 U	0.000329 U	0.00287 U	0.000281 U	0.000275 U	0.00213 U	0.000240 U	0.00113 U	0.00113 U	0.000292 U	0.000233 U	0.000228 U
	B-245-55	3/29/18	PES	ESC	55	-15.1	S	0.000385 U	0.000327 U	0.00285 U	0.000279 U	0.000274 U	0.00212 U	0.000239 U	0.00113 U	0.00113 U	0.000291 U	0.000232 U	0.000227 U
	B-245-60	3/29/18	PES	ESC	60	-20.1	S	0.000366 U	0.000311 U	0.00271 U	0.000266 U	0.000260 U	0.00201 U	0.000227 U	0.00107 U	0.00107 U	0.000276 U	0.000221 U	0.000215 U
	B-245-65	3/29/18	PES	ESC	65	-25.1	S	0.000391 U	0.000332 U	0.00289 U	0.000284 U	0.000278 U	0.00215 U	0.000243 U	0.00114 U	0.00114 U	0.000295 U	0.000236 U	0.000230 U
	B-245-70	3/29/18	PES	ESC	70	-30.1	S	0.000402 U	0.000341 U	0.00298 U	0.000292 U	0.000286 U	0.00221 U	0.000249 U	0.00118 U	0.00118 U	0.000303 U	0.000242 U	0.000236 U
	B-245-75	3/29/18	PES	ESC	75	-35.1	S	0.000385 U	0.000327 U	0.00285 U	0.000280 U	0.000274 U	0.00212 U	0.000239 U	0.00113 U	0.00113 U	0.000291 U	0.000232 U	0.000227 U
	B-245-80	3/29/18	PES	ESC	80	-40.1	S	0.000396 U	**0.000873 J**	0.00293 U	0.000287 U	0.000282 U	0.00218 U	0.000246 U	0.00116 U	0.00116 U	0.000299 U	0.000239 U	0.000233 U
B-246	B-246-6	5/11/18	PES	ESC	6	33.9	S	0.0151 U	0.00126 U	0.00718 U	0.000415 U	0.00102 U	0.0119 U	**0.000453 J**	0.00788 U	0.00370 U	0.00456 U	0.00140 U	0.00300 U
	B-246-11	5/11/18	PES	ESC	11	28.9	S	0.0150 U	0.00125 U	0.00714 U	0.000413 U	0.00102 U	0.0118 U	**0.000484 J**	0.00784 U	0.00368 U	0.00453 U	0.00139 U	0.00299 U
	B-246-15	5/11/18	PES	ESC	15	24.9	S	0.0144 U	**0.00367 J**	0.00684 U	0.000396 U	0.000975 U	0.0113 U	**0.000419 J**	0.00750 U	0.00353 U	0.00434 U	0.00133 U	0.00286 U
	B-246-25	5/11/18	PES	ESC	25	14.9	S	0.0142 U	**0.00160 J**	0.00676 U	0.000391 U	0.000965 U	0.0112 U	**0.000422 J**	0.00742 U	0.00349 U	0.00429 U	0.00132 U	0.00283 U
	B-246-30	5/11/18	PES	ESC	30	9.9	S	0.0149 U	**0.00348 J**	0.00712 U	0.000412 U	0.00102 U	0.0118 U	**0.000538 J**	0.00781 U	0.00367 U	0.00452 U	0.00139 U	0.00298 U
	B-246-35	5/11/18	PES	ESC	35	4.9	S	0.0146 U	0.00122 U	0.00697 U	0.000403 U	0.000995 U	0.0115 U	0.000340 U	0.00765 U	0.00360 U	0.00443 U	0.00136 U	0.00292 U
	B-246-40	5/11/18	PES	ESC	40	-0.1	S	0.0144 U	**0.00171 J**	0.00685 U	0.000396 U	0.000977 U	0.0113 U	**0.000376 J**	0.00752 U	0.00353 U	0.00435 U	0.00134 U	0.00287 U
	B-246-43	5/11/18	PES	ESC	43	-3.1	S	0.0139 U	**0.00209 J**	0.00662 U	0.000383 U	0.000944 U	0.0109 U	**0.000437 J**	0.00726 U	0.00341 U	0.00420 U	0.00129 U	0.00277 U
	B-246-45	5/11/18	PES	ESC	45	-5.1	S	0.0153 U	**0.00858 J**	0.00729 U	0.000422 U	0.00104 U	0.0121 U	0.000356 U	0.00801 U	0.00376 U	0.00464 U	0.00143 U	0.00304 U
	B-246-50	5/11/18	PES	ESC	50	-10.1	S	0.0143 U	**0.00197 J**	0.00681 U	0.000394 U	0.000971 U	0.0113 U	0.000332 U	0.00747 U	0.00351 U	0.00432 U	0.00133 U	0.00285 U
	B-246-55	5/11/18	PES	ESC	55	-15.1	S	0.0145 U	**0.00229 J**	0.00693 U	0.000401 U	0.000988 U	0.0115 U	0.000338 U	0.00760 U	0.00357 U	0.00440 U	0.00135 U	0.00290 U
	B-246-60	5/11/18	PES	ESC	60	-20.1	S	0.0144 U	**0.00222 J**	0.00687 U	0.000397 U	0.000979 U	0.0113 U	**0.000377 J**	0.00754 U	0.00354 U	0.00436 U	0.00134 U	0.00287 U
	B-246-65	5/11/18	PES	ESC	65	-25.1	S	0.0157 U	**0.00253 J**	0.00748 U	0.000433 U	0.00107 U	0.0124 U	0.000365 U	0.00821 U	0.00386 U	0.00475 U	0.00146 U	0.00313 U
	B-246-70	5/11/18	PES	ESC	70	-30.1	S	0.0141 U	**0.00291 J**	0.00672 U	0.000389 U	0.000959 U	0.0111 U	**0.000596 J**	0.00738 U	0.00347 U	0.00427 U	0.00131 U	0.00281 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	–	–	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	–	–	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
B-246 (continued)	B-246-75	5/11/18	PES	ESC	75	-35.1	S	0.0147 U	**0.00301 J**	0.00701 U	0.000406 U	0.00100 U	0.0116 U	**0.000689 J**	0.00769 U	0.00361 U	0.00445 U	0.00137 U	0.00293 U
	B-246-80	5/11/18	PES	ESC	80	-40.1	S	0.0143 U	0.00120 U	0.00683 U	0.000395 U	0.000975 U	0.0113 U	**0.000343 J**	0.00750 U	0.00352 U	0.00434 U	0.00133 U	0.00286 U
	B-926-100	5/11/18	PES	ESC	45 (dup)	-5.1	S	0.0190 U	**0.00536 J**	0.00906 U	0.000525 U	0.00129 U	0.0150 U	**0.000771 J**	0.00995 U	0.00467 U	0.00575 U	0.00177 U	0.00379 U
B-247	B-247-5	4/20/18	PES	ESC	5	34.7	S	0.000388 U	0.000329 U	0.00287 U	0.000282 U	0.000276 U	0.00213 U	0.000241 U	0.00114 U	0.00114 U	0.000293 U	0.000234 U	0.000228 U
	B-247-10	4/20/18	PES	ESC	10	29.7	S	0.000394 U	0.000334 U	0.00291 U	0.000286 U	0.000280 U	0.00216 U	0.000244 U	0.00115 U	0.00115 U	0.000297 U	0.000237 U	0.000231 U
	B-247-15	4/20/18	PES	ESC	15	24.7	S	0.000379 U	**0.00147 J**	0.00281 U	0.000275 U	0.000270 U	0.00209 U	0.000235 U	0.00111 U	0.00111 U	0.000286 U	0.000228 U	0.000223 U
	B-247-20	4/20/18	PES	ESC	20	19.7	S	0.000382 U	0.000324 U	0.00283 U	0.000277 U	0.000271 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000288 U	0.000230 U	0.000224 U
	B-247-25	4/20/18	PES	ESC	25	14.7	S	0.000372 U	**0.000377 J**	0.00275 U	0.000270 U	0.000264 U	0.00205 U	0.000231 U	0.00109 U	0.00109 U	0.000281 U	0.000224 U	0.000219 U
	B-247-30	4/20/18	PES	ESC	30	9.7	S	0.000377 U	0.000319 U	0.00279 U	0.000273 U	0.000268 U	0.00207 U	0.000234 U	0.00110 U	0.00110 U	0.000284 U	0.000227 U	0.000221 U
	B-247-35	4/20/18	PES	ESC	35	4.7	S	0.000377 U	0.000320 U	0.00279 U	0.000273 U	0.000268 U	0.00207 U	0.000234 U	0.00110 U	0.00110 U	0.000284 U	0.000227 U	0.000222 U
	B-247-40	4/20/18	PES	ESC	40	-0.3	S	0.000384 U	**0.00225 J**	0.00284 U	0.000278 U	0.000273 U	0.00211 U	0.000238 U	0.00112 U	0.00112 U	0.000290 U	0.000231 U	0.000226 U
	B-247-45	4/20/18	PES	ESC	45	-5.3	S	0.000370 U	**0.00272 J**	0.00273 U	0.000268 U	0.000263 U	0.00203 U	0.000229 U	0.00108 U	0.00108 U	0.000279 U	0.000223 U	0.000217 U
	B-247-50	4/20/18	PES	ESC	50	-10.3	S	0.000377 U	0.000319 U	0.00279 U	0.000273 U	0.000268 U	0.00207 U	0.000233 U	0.00110 U	0.00110 U	0.000284 U	0.000227 U	0.000221 U
	B-247-55	4/20/18	PES	ESC	55	-15.3	S	0.000386 U	**0.000393 J**	0.00286 U	0.000280 U	0.000274 U	0.00212 U	0.000239 U	0.00113 U	0.00113 U	0.000291 U	0.000233 U	0.000227 U
	B-247-60	4/20/18	PES	ESC	60	-20.3	S	0.000368 U	0.000312 U	0.00273 U	0.000267 U	0.000262 U	0.00203 U	0.000228 U	0.00108 U	0.00108 U	0.000278 U	0.000222 U	0.000217 U
	B-247-65	4/20/18	PES	ESC	65	-25.3	S	0.000382 U	**0.000492 J**	0.00282 U	0.000277 U	0.000271 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000288 U	0.000230 U	0.000224 U
	B-247-70	4/20/18	PES	ESC	70	-30.3	S	0.000383 U	0.000325 U	0.00284 U	0.000278 U	0.000272 U	0.00211 U	0.000238 U	0.00112 U	0.00112 U	0.000289 U	0.000231 U	0.000225 U
	B-247-75	4/20/18	PES	ESC	75	-35.3	S	0.000391 U	0.000332 U	0.00289 U	0.000284 U	0.000278 U	0.00215 U	0.000242 U	0.00114 U	0.00114 U	0.000295 U	0.000236 U	0.000230 U
	B-247-80	4/20/18	PES	ESC	80	-40.3	S	0.000382 U	**0.000943 J**	0.00283 U	0.000277 U	0.000272 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000288 U	0.000230 U	0.000225 U
	B-909-20	4/20/18	PES	ESC	80 (dup)	-40.3	S	0.000370 U	**0.00202 J**	0.00274 U	0.000268 U	0.000263 U	0.00204 U	0.000229 U	0.00108 U	0.00108 U	0.000279 U	0.000223 U	0.000218 U
B-248	B-248-5	4/23/18	PES	ESC	5	46.9	V	0.000390 U	**0.000354 J**	0.00289 U	0.000283 U	0.000277 U	0.00215 U	0.000242 U	0.00114 U	0.00114 U	0.000294 U	0.000235 U	0.000229 U
	B-248-10	4/23/18	PES	ESC	10	41.9	V	0.000381 U	0.000323 U	0.00282 U	0.000277 U	0.000271 U	0.00210 U	0.000236 U	0.00112 U	0.00112 U	0.000288 U	0.000230 U	0.000224 U
	B-248-15	4/23/18	PES	ESC	15	36.9	V	0.0140 U	0.00117 U	0.00665 U	0.000385 U	0.000949 U	0.0110 U	0.000324 U	0.00730 U	0.00343 U	0.00422 U	0.00130 U	0.00278 U
	B-248-20	4/23/18	PES	ESC	20	31.9	S	0.000370 U	**0.00132 J**	0.00274 U	0.000268 U	0.000263 U	0.00203 U	0.000229 U	0.00108 U	0.00108 U	0.000279 U	0.000223 U	0.000217 U
	B-248-25	4/23/18	PES	ESC	25	26.9	S	0.0149 U	0.00124 U	0.00710 U	0.000411 U	0.00101 U	0.0117 U	0.000346 U	0.00779 U	0.00366 U	0.00451 U	0.00138 U	0.00297 U
	B-248-30	4/23/18	PES	ESC	30	21.9	S	0.000370 U	0.000314 U	0.00274 U	0.000268 U	0.000263 U	0.00203 U	0.000229 U	0.00108 U	0.00108 U	0.000279 U	0.000223 U	0.000217 U
	B-248-35	4/23/18	PES	ESC	35	16.9	S	0.0138 U	**0.00135 J**	0.00655 U	0.000379 U	0.000935 U	0.0108 U	**0.000698 J**	0.00719 U	0.00338 U	0.00416 U	0.00128 U	0.00274 U
	B-248-40	4/23/18	PES	ESC	40	11.9	S	0.0142 U	0.00118 U	0.00675 U	0.000390 U	0.000962 U	0.0111 U	0.000329 U	0.00740 U	0.00348 U	0.00428 U	0.00132 U	0.00282 U
	B-248-45	4/23/18	PES	ESC	45	6.9	S	0.0145 U	0.00121 U	0.00691 U	0.000400 U	0.000986 U	0.0114 U	0.000337 U	0.00758 U	0.00356 U	0.00439 U	0.00135 U	0.00289 U
	B-248-50	4/23/18	PES	ESC	50	1.9	S	0.0139 U	**0.00407 J**	0.00661 U	0.000383 U	0.000944 U	0.0109 U	0.000323 U	0.00726 U	0.00341 U	0.00420 U	0.00129 U	0.00277 U
	B-248-55	4/23/18	PES	ESC	55	-3.2	S	0.000405 U	0.000343 U	0.00299 U	0.000294 U	0.000288 U	0.00223 U	0.000251 U	0.00118 U	0.00118 U	0.000305 U	0.000244 U	0.000238 U
	B-248-60	4/23/18	PES	ESC	60	-8.2	S	0.0136 U	0.00114 U	0.00648 U	0.000375 U	0.000925 U	0.0107 U	**0.000403 J**	0.00712 U	0.00334 U	0.00412 U	0.00126 U	0.00271 U
	B-248-65	4/23/18	PES	ESC	65	-13.2	S	0.0156 U	0.00130 U	0.00744 U	0.000431 U	0.00106 U	0.0123 U	0.000363 U	0.00817 U	0.00384 U	0.00472 U	0.00145 U	0.00311 U
	B-248-70	4/23/18	PES	ESC	70	-18.2	S	0.0146 U	0.00122 U	0.00695 U	0.000402 U	0.000992 U	0.0115 U	0.000339 U	0.00763 U	0.00359 U	0.00441 U	0.00136 U	0.00291 U
	B-248-75	4/23/18	PES	ESC	75	-23.2	S	0.0143 U	0.00119 U	0.00680 U	0.000393 U	0.000969 U	0.0112 U	0.000331 U	0.00746 U	0.00350 U	0.00431 U	0.00133 U	0.00284 U
	B-248-80	4/23/18	PES	ESC	80	-28.2	S	0.000411 U	0.000348 U	0.00304 U	0.000298 U	0.000292 U	0.00226 U	0.000255 U	0.00120 U	0.00120 U	0.000310 U	0.000248 U	0.000242 U
	B-910-20	4/23/18	PES	ESC	80 (dup)	-28.2	S	0.000422 U	0.000358 U	0.00312 U	0.000306 U	0.000300 U	0.00232 U	0.000262 U	0.00123 U	0.00123 U	0.000318 U	0.000254 U	0.000248 U
	B-248-85	4/23/18	PES	ESC	85	-33.2	S	0.000415 U	**0.00365 J**	0.00307 U	0.000301 U	0.000295 U	0.00228 U	0.000257 U	0.00121 U	0.00121 U	0.000313 U	0.000250 U	0.000244 U
	B-248-90	4/23/18	PES	ESC	90	-38.2	S	0.000409 U	0.000347 U	0.00303 U	0.000297 U	0.000291 U	0.00225 U	0.000254 U	0.00120 U	0.00120 U	0.000309 U	0.000246 U	0.000240 U
	B-248-95	4/23/18	PES	ESC	95	-43.2	S	0.000426 U	0.000362 U	0.00315 U	0.000309 U	0.000303 U	0.00234 U	0.000264 U	0.00125 U	0.00125 U	0.000322 U	0.000257 U	0.000251 U
	B-248-100	4/23/18	PES	ESC	100	-48.2	S	0.000415 U	**0.00263 J**	0.00307 U	0.000301 U	0.000295 U	0.00228 U	0.000257 U	0.00121 U	0.00121 U	0.000313 U	0.000250 U	0.000244 U
	B-248-105	4/23/18	PES	ESC	105	-53.2	S	0.000370 U	**0.000399 J**	0.00273 U	0.000268 U	0.000263 U	0.00203 U	0.000229 U	0.00108 U	0.00108 U	0.000279 U	0.000223 U	0.000217 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
B-248	B-248-110	4/23/18	PES	ESC	110	-58.2	S	0.0146 U	0.00122 U	0.00694 U	0.000402 U	0.000990 U	0.0115 U	0.000339 U	0.00762 U	0.00358 U	0.00441 U	0.00135 U	0.00290 U
(continued)	B-248-115	4/23/18	PES	ESC	115	-63.2	S	0.000400 U	0.000339 U	0.00296 U	0.000290 U	0.000284 U	0.00220 U	0.000248 U	0.00117 U	0.00117 U	0.000302 U	0.000241 U	0.000235 U
B-249	B-249-5	10/15/18	PES	PACE	5	34.2	S	0.0133 U	**0.00139 J**	0.00632 U	0.000366 U	0.000902 U	0.0105 U	0.000308 U	0.00694 U	0.00326 U	0.00401 U	0.00123 U	0.00264 U
	B-249-8	10/15/18	PES	PACE	8	31.2	S	0.0143 U	0.00120 U	0.00683 U	0.000395 U	0.000974 U	0.0113 U	0.000333 U	0.00749 U	0.00352 U	0.00433 U	0.00133 U	0.00285 U
	B-249-15	10/15/18	PES	PACE	15	24.2	S	0.0147 U	**0.00123 J**	0.00701 U	0.000405 U	0.000999 U	0.0116 U	0.000342 U	0.00769 U	**0.191**	**0.0247**	**0.00402 J**	0.00293 U
	B-249-17	10/15/18	PES	PACE	17	22.2	S	0.0144 U	0.00120 U	0.00685 U	0.000396 U	0.000977 U	0.0113 U	0.000334 U	0.00752 U	0.00353 U	0.00435 U	0.00134 U	0.00286 U
	B-249-20	10/15/18	PES	PACE	20	19.2	S	0.0150 U	0.00125 U	0.00715 U	0.000414 U	0.00102 U	0.0118 U	0.000349 U	0.00785 U	0.00369 U	0.00454 U	0.00139 U	0.00299 U
B-250	B-250-2.5	10/15/18	PES	PACE	2.5	36.9	V	0.0140 U	**0.00136 J**	0.00668 U	0.000386 U	0.000953 U	0.0110 U	0.000326 U	0.00733 U	0.00345 U	0.00424 U	0.00130 U	0.00279 U
	B-250-8	10/15/18	PES	PACE	8	31.4	S	0.0141 U	0.00118 U	0.00674 U	0.000390 U	0.000961 U	0.0111 U	0.000328 U	0.00739 U	0.00347 U	0.00428 U	0.00131 U	0.00282 U
	B-250-10	10/15/18	PES	PACE	10	29.4	S	0.0141 U	**0.00119 J**	0.00673 U	0.000389 U	0.000960 U	0.0111 U	0.000328 U	0.00739 U	0.00347 U	0.00427 U	0.00131 U	0.00281 U
	B-250-13	10/15/18	PES	PACE	13	26.4	S	0.0143 U	0.00119 U	0.00680 U	0.000393 U	0.000969 U	0.0112 U	0.000331 U	0.00746 U	0.00350 U	0.00431 U	0.00133 U	0.00284 U
	B-250-20	10/15/18	PES	PACE	20	19.4	S	0.0147 U	**0.00134 J**	0.00701 U	0.000405 U	0.00100 U	0.0116 U	0.000342 U	0.00769 U	0.00361 U	0.00445 U	0.00137 U	0.00293 U
	B-250-24	10/15/18	PES	PACE	24	15.4	S	0.0139 U	0.00116 U	0.00662 U	0.000383 U	0.000944 U	0.0109 U	0.000323 U	0.00726 U	0.00341 U	0.00420 U	0.00129 U	0.00277 U
	B-250-30	10/16/18	PES	PACE	30	9.4	S	0.0138 U	**0.00621 J**	0.00660 U	0.000382 U	0.000941 U	0.0109 U	0.000322 U	0.00724 U	0.00340 U	0.00419 U	0.00129 U	0.00276 U
B-251	B-251-5	10/15/18	PES	PACE	5	34.3	S	0.0133 U	0.00111 U	0.00636 U	0.000368 U	0.000907 U	0.0105 U	0.000310 U	0.00698 U	0.00328 U	0.00403 U	0.00124 U	0.00266 U
	B-251-8	10/15/18	PES	PACE	8	31.3	S	0.0141 U	0.00118 U	0.00671 U	0.000388 U	0.000957 U	0.0111 U	0.000327 U	0.00737 U	0.00346 U	0.00426 U	0.00131 U	0.00281 U
	B-251-10	10/15/18	PES	PACE	10	29.3	S	0.0141 U	0.00118 U	0.00673 U	0.000389 U	0.000960 U	0.0111 U	0.000328 U	0.00739 U	0.00347 U	0.00427 U	0.00131 U	0.00281 U
	B-251-15	10/15/18	PES	PACE	15	24.3	S	0.0144 U	0.00120 U	0.00684 U	0.000396 U	0.000976 U	0.0113 U	0.000334 U	0.00751 U	0.00353 U	0.00434 U	0.00133 U	0.00286 U
	B-251-20	10/15/18	PES	PACE	20	19.3	S	0.0149 U	0.00124 U	0.00708 U	0.000410 U	0.00101 U	0.0117 U	0.000345 U	0.00778 U	0.00365 U	0.00450 U	0.00138 U	0.00296 U
	B-251-25	10/15/18	PES	PACE	25	14.3	S	0.0146 U	**0.00180 J**	0.00695 U	0.000402 U	0.000991 U	0.0115 U	0.000339 U	0.00763 U	0.00358 U	0.00441 U	0.00136 U	0.00291 U
B-252	B-252-2.5	10/15/18	PES	PACE	2.5	36.7	V	0.0133 U	**0.00228 J**	0.00632 U	0.000366 U	0.000902 U	0.0104 U	0.000308 U	**0.00853**	0.00326 U	0.00401 U	0.00123 U	0.00264 U
	B-252-8	10/15/18	PES	PACE	8	31.2	S	0.0136 U	0.00113 U	0.00647 U	0.000374 U	0.000923 U	0.0107 U	0.000316 U	0.00710 U	0.00334 U	0.00411 U	0.00126 U	0.00271 U
	B-252-10	10/15/18	PES	PACE	10	29.2	S	0.0141 U	**0.00177 J**	0.00671 U	0.000388 U	0.000957 U	0.0111 U	0.000327 U	0.00736 U	0.00346 U	0.00426 U	0.00131 U	0.00281 U
	B-252-15	10/15/18	PES	PACE	15	24.2	S	0.0150 U	0.00125 U	0.00713 U	0.000412 U	0.00102 U	0.0118 U	0.000348 U	0.00782 U	0.00368 U	0.00452 U	0.00139 U	0.00298 U
	B-252-19	10/15/18	PES	PACE	19	20.2	S	0.0153 U	0.00128 U	0.00730 U	0.000422 U	0.00104 U	0.0121 U	0.000356 U	0.00801 U	0.00377 U	0.00463 U	0.00142 U	0.00305 U
	B-252-25	10/15/18	PES	PACE	25	14.2	S	0.0139 U	0.00116 U	0.00665 U	0.000384 U	0.000948 U	0.0110 U	0.000324 U	0.00729 U	0.00343 U	0.00422 U	0.00130 U	0.00278 U
	B-252-29	10/15/18	PES	PACE	29	10.2	S	0.0145 U	0.00121 U	0.00692 U	0.000400 U	0.000988 U	0.0114 U	0.000338 U	0.00760 U	0.00357 U	0.00439 U	0.00135 U	0.00290 U
B-253A	B-253A-5	10/18/18	PES	PACE	5	35.6	V	0.0145 U	0.00121 U	0.00689 U	0.000399 U	0.000983 U	0.0114 U	0.000336 U	0.00756 U	0.00355 U	0.00437 U	0.00134 U	0.00288 U
	B-253A-8	10/18/18	PES	PACE	8	32.6	S	0.0143 U	0.00478 U	0.00681 U	0.000394 U	0.000972 U	0.0113 U	0.000332 U	0.00748 U	0.00351 U	0.00432 U	0.00133 U	0.00285 U
	B-253A-10	10/18/18	PES	PACE	10	30.6	S	0.0139 U	0.0116 U	0.00663 U	0.000383 U	0.000945 U	0.0110 U	0.000323 U	0.00727 U	0.00342 U	0.00421 U	0.00129 U	0.00277 U
	B-253A-15	10/18/18	PES	PACE	15	25.6	S	0.0143 U	0.0952 U	0.00679 U	0.000393 U	0.000969 U	0.0112 U	0.000331 U	0.00746 U	0.00350 U	0.00431 U	0.00132 U	0.00284 U
	B-253A-20	10/18/18	PES	PACE	20	20.6	S	0.0140 U	0.00467 U	0.00666 U	0.000386 U	0.000951 U	0.0110 U	0.000325 U	0.00731 U	0.00344 U	0.00423 U	0.00130 U	0.00279 U
B-254	B-254-5	10/16/18	PES	PACE	5	34.7	S	0.0152 U	0.00127 U	0.00724 U	0.000419 U	0.00103 U	0.0120 U	0.000353 U	0.00795 U	0.00374 U	0.00460 U	0.00141 U	0.00303 U
	B-254-10	10/16/18	PES	PACE	10	29.7	S	0.0144 U	0.00120 U	0.00687 U	0.000397 U	0.000980 U	0.0114 U	0.000335 U	0.00754 U	0.00354 U	0.00436 U	0.00134 U	0.00287 U
	B-254-13.5	10/16/18	PES	PACE	13.5	26.2	S	0.0149 U	**0.00289 J**	0.00709 U	0.000410 U	0.00101 U	0.0117 U	0.000346 U	0.00779 U	0.00366 U	0.00450 U	0.00138 U	0.00297 U
	B-254-20	10/16/18	PES	PACE	20	19.7	S	0.0137 U	**0.00515 J**	0.00651 U	0.000377 U	0.000929 U	0.0108 U	0.000317 U	0.00714 U	0.00336 U	0.00413 U	0.00127 U	0.00272 U
	B-254-25	10/16/18	PES	PACE	25	14.7	S	0.0142 U	**0.00486 J**	0.00676 U	0.000391 U	0.000964 U	0.0112 U	0.000330 U	0.00742 U	0.00349 U	0.00429 U	0.00132 U	0.00283 U
B-254A	B-254A-27	10/19/18	PES	PACE	27	12.7	S	0.0138 U	0.00116 U	0.00661 U	0.000383 U	0.000943 U	0.0109 U	0.000322 U	0.00726 U	0.00341 U	0.00420 U	0.00129 U	0.00277 U
	B-254A-30	10/19/18	PES	PACE	30	9.7	S	0.0137 U	**0.00540**	0.00651 U	0.000377 U	0.000929 U	0.0108 U	0.000317 U	0.00715 U	0.00336 U	0.00413 U	0.00127 U	0.00272 U
	B-254A-35	10/19/18	PES	PACE	35	4.7	S	0.0134 U	0.00112 U	0.00637 U	0.000369 U	0.000909 U	0.0105 U	0.000311 U	0.00699 U	0.00329 U	0.00405 U	0.00124 U	0.00267 U
B-255	B-255-3.5	10/16/18	PES	PACE	3.5	36.3	S	0.0145 U	**0.00578 J**	0.00691 U	0.000400 U	0.000986 U	0.0114 U	0.000337 U	0.00758 U	0.00356 U	0.00439 U	0.00135 U	0.00289 U
	B-255-8	10/16/18	PES	PACE	8	31.8	S	0.0147 U	**0.00565 J**	0.00701 U	0.000406 U	0.00100 U	0.0116 U	0.000342 U	0.00769 U	0.00362 U	0.00445 U	0.00137 U	0.00293 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
B-255 (continued)	B-255-15	10/16/18	PES	PACE	15	24.8	S	0.0138 U	**0.00689 J**	0.00659 U	0.000381 U	0.000940 U	0.0109 U	0.000321 U	0.00723 U	0.00340 U	0.00418 U	0.00129 U	0.00276 U
B-255A	B-255A-21	10/16/18	PES	PACE	21	18.8	S	0.0134 U	**0.00438 J**	0.00640 U	0.000370 U	0.000914 U	0.0106 U	0.000312 U	0.00703 U	0.00330 U	0.00406 U	0.00125 U	0.00268 U
B-256	B-256-2.5	10/16/18	PES	PACE	2.5	37.1	S	0.0149 U	0.00124 U	0.00707 U	0.000409 U	0.00101 U	0.0117 U	0.000345 U	0.00776 U	0.00365 U	0.00449 U	0.00138 U	0.00296 U
	B-256-5	10/16/18	PES	PACE	5	34.6	S	0.0140 U	**0.00347 J**	0.00668 U	0.000387 U	0.000953 U	0.0110 U	0.000326 U	0.00734 U	0.00345 U	0.00424 U	0.00130 U	0.00279 U
	B-256-10	10/16/18	PES	PACE	10	29.6	S	0.0136 U	**0.00527 J**	0.00646 U	0.000374 U	0.000922 U	0.0107 U	0.000315 U	0.00710 U	0.00333 U	0.00410 U	0.00126 U	0.00270 U
	B-256-15	10/16/18	PES	PACE	15	24.6	S	0.0141 U	**0.00313 J**	0.00670 U	0.000387 U	0.000955 U	0.0111 U	0.000326 U	0.00735 U	0.00345 U	0.00425 U	0.00131 U	0.00280 U
	B-256-18	10/16/18	PES	PACE	18	21.6	S	0.0141 U	**0.00386 J**	0.00669 U	0.000387 U	0.000955 U	0.0111 U	0.000326 U	0.00735 U	0.00345 U	0.00425 U	0.00131 U	0.00280 U
B-257	B-257-5	10/17/18	PES	PACE	5	34.4	S	0.0154 U	**0.00420 J**	0.00732 U	0.000424 U	0.00104 U	0.0121 U	0.000357 U	0.00804 U	0.00378 U	0.00465 U	0.00143 U	0.00306 U
	B-257-10	10/17/18	PES	PACE	10	29.4	S	0.0142 U	**0.00506 J**	0.00676 U	0.000391 U	0.000964 U	0.0112 U	0.000329 U	0.00741 U	0.00348 U	0.00429 U	0.00132 U	0.00283 U
	B-257-15	10/17/18	PES	PACE	15	24.4	S	0.0148 U	**0.00558 J**	0.00703 U	0.000407 U	0.00100 U	0.0116 U	0.000343 U	0.00771 U	0.00362 U	0.00446 U	0.00137 U	0.00294 U
	B-257-20	10/17/18	PES	PACE	20	19.4	S	0.0143 U	**0.00569 J**	0.00680 U	0.000393 U	0.000970 U	0.0112 U	0.000332 U	0.00746 U	0.00351 U	0.00432 U	0.00133 U	0.00284 U
B-258	B-258-3	10/17/18	PES	PACE	3	36.2	V	0.0139 U	**0.00671 J**	0.00663 U	0.000384 U	0.000946 U	0.0110 U	0.000323 U	0.00728 U	0.00342 U	0.00421 U	0.00129 U	0.00277 U
	B-258-8	10/17/18	PES	PACE	8	31.2	S	0.0144 U	0.00121 U	0.00688 U	0.000398 U	0.000981 U	0.0114 U	0.000335 U	0.00755 U	0.00355 U	0.00437 U	0.00134 U	0.00288 U
	B-258-10	10/17/18	PES	PACE	10	29.2	S	0.0152 U	0.00127 U	0.00724 U	0.000419 U	0.00103 U	0.0120 U	0.000353 U	0.00795 U	0.00373 U	0.00460 U	0.00141 U	0.00303 U
	B-258-15	10/17/18	PES	PACE	15	24.2	S	0.0150 U	0.00125 U	0.00714 U	0.00826 U	0.00102 U	0.0118 U	0.00696 U	0.00784 U	0.00368 U	0.00453 U	0.00139 U	0.00299 U
	B-258-20	10/17/18	PES	PACE	20	19.2	S	0.0142 U	0.00118 U	0.00675 U	0.000391 U	0.000963 U	0.0112 U	0.000329 U	0.00741 U	0.00348 U	0.00429 U	0.00132 U	0.00282 U
B-259	B-259-2.5	10/17/18	PES	PACE	2.5	36.7	V	0.0143 U	**0.00602**	0.00681 U	0.000394 U	0.000971 U	0.0113 U	0.000332 U	0.00747 U	0.00351 U	0.00432 U	0.00133 U	0.00285 U
	B-259-5	10/17/18	PES	PACE	5	34.2	S	0.0139 U	0.00116 U	0.00663 U	0.000384 U	0.000946 U	0.0110 U	0.000323 U	0.00728 U	0.00342 U	0.00421 U	0.00129 U	0.00277 U
	B-259-10	10/17/18	PES	PACE	10	29.2	S	0.0146 U	0.00121 U	0.00693 U	0.000401 U	0.000989 U	0.0115 U	0.000338 U	0.00761 U	0.00358 U	0.00440 U	0.00135 U	0.00290 U
	B-259-15	10/17/18	PES	PACE	15	24.2	S	0.0149 U	0.00124 U	0.00710 U	0.000411 U	0.00101 U	0.0117 U	0.000346 U	0.00780 U	0.00366 U	0.00451 U	0.00139 U	0.00297 U
	B-259-20	10/17/18	PES	PACE	20	19.2	S	0.0142 U	0.00118 U	0.00676 U	0.000391 U	0.000965 U	0.0112 U	0.000330 U	0.00742 U	0.00349 U	0.00429 U	0.00132 U	0.00283 U
B-260	B-260-5	10/17/18	PES	PACE	5	34.2	S	0.0141 U	0.00118 U	0.00671 U	0.000388 U	0.000957 U	0.0111 U	0.000327 U	0.00736 U	0.00346 U	0.00426 U	0.00131 U	0.00281 U
	B-260-8	10/17/18	PES	PACE	8	31.2	S	0.0143 U	0.00119 U	0.00679 U	0.000393 U	0.000968 U	0.0112 U	0.000331 U	0.00745 U	0.00350 U	0.00431 U	0.00132 U	0.00284 U
	B-260-10	10/17/18	PES	PACE	10	29.2	S	0.0146 U	0.00122 U	0.00694 U	0.000402 U	0.000990 U	0.0115 U	0.000339 U	0.00762 U	0.00358 U	0.00441 U	0.00135 U	0.00290 U
	B-260-15	10/17/18	PES	PACE	15	24.2	S	0.0147 U	**0.00587**	0.00703 U	0.00406 U	0.00100 U	0.0116 U	0.00343 U	0.00771 U	0.00362 U	0.00446 U	0.00137 U	0.00294 U
	B-260-20	10/17/18	PES	PACE	20	19.2	S	0.0140 U	0.00117 U	0.00669 U	0.00387 U	0.000954 U	0.0111 U	0.00326 U	0.00734 U	0.00345 U	0.00424 U	0.00130 U	0.00280 U
B-261	B-261-3	10/17/18	PES	PACE	3	36.9	S	0.0145 U	**0.00385 J**	0.00691 U	0.000400 U	0.000986 U	0.0114 U	0.000337 U	0.00759 U	0.00357 U	0.00439 U	0.00135 U	0.00289 U
	B-261-5	10/17/18	PES	PACE	5	34.9	S	0.0144 U	0.00120 U	0.00685 U	0.0317 U	0.000977 U	0.0113 U	0.0267 U	0.00752 U	0.00353 U	0.00435 U	0.00134 U	0.00286 U
	B-261-8	10/17/18	PES	PACE	8	31.9	S	0.0152 U	0.00127 U	0.00725 U	0.00419 U	0.00103 U	0.0120 U	0.00354 U	0.00796 U	0.00374 U	0.00460 U	0.00141 U	0.00303 U
	B-261-10	10/17/18	PES	PACE	10	29.9	S	0.0146 U	0.00122 U	0.00697 U	0.0161 U	0.000994 U	0.0115 U	0.0136 U	0.00765 U	0.00359 U	0.00442 U	0.00136 U	0.00292 U
	B-261-15	10/17/18	PES	PACE	15	24.9	S	0.0140 U	0.00116 U	0.00665 U	0.00769 U	0.000948 U	0.0110 U	0.00648 U	0.00730 U	0.00343 U	0.00422 U	0.00130 U	0.00278 U
	B-261-20	10/17/18	PES	PACE	20	19.9	S	0.0143 U	0.00119 U	0.00680 U	0.0787 U	0.000970 U	0.0112 U	0.0663 U	0.00746 U	0.00351 U	0.00432 U	**0.00321 J**	0.00284 U
B-262	B-262-5	10/17/18	PES	PACE	5	34.9	S	0.0150 U	0.00125 U	0.00713 U	0.000412 U	0.00102 U	0.0118 U	0.000348 U	0.00782 U	**0.00764 J**	0.00452 U	0.00139 U	0.00298 U
	B-262-8	10/17/18	PES	PACE	8	31.9	S	0.0140 U	0.00117 U	0.00665 U	0.000385 U	0.000949 U	0.0110 U	0.000324 U	0.00730 U	0.00343 U	0.00422 U	0.00130 U	0.00278 U
	B-262-10	10/17/18	PES	PACE	10	29.9	S	0.0141 U	0.00118 U	0.00674 U	0.000390 U	0.000961 U	0.0111 U	0.000329 U	0.00739 U	0.00347 U	0.00428 U	0.00131 U	0.00282 U
	B-262-15	10/17/18	PES	PACE	15	24.9	S	0.0139 U	0.00116 U	0.00664 U	0.000384 U	0.000947 U	0.0110 U	0.000324 U	0.00729 U	0.00342 U	0.00421 U	0.00130 U	0.00278 U
	B-262-20	10/17/18	PES	PACE	20	19.9	S	0.0150 U	0.00125 U	0.00712 U	0.000412 U	0.00102 U	0.0118 U	0.000347 U	0.00782 U	0.00367 U	0.00452 U	0.00139 U	0.00298 U
B-263	B-263-3	10/18/18	PES	PACE	3	36.8	S	0.0156 U	0.00130 U	0.00741 U	0.000429 U	0.00106 U	0.0122 U	0.000361 U	0.00813 U	0.00382 U	0.00470 U	0.00144 U	0.00310 U
	B-263-5	10/18/18	PES	PACE	5	34.8	S	0.0137 U	0.00115 U	0.00654 U	0.000378 U	0.000933 U	0.0108 U	0.000319 U	0.00718 U	0.00337 U	0.00415 U	0.00128 U	0.00273 U
	B-263-8	10/18/18	PES	PACE	8	31.8	S	0.0134 U	0.00112 U	0.00638 U	0.000369 U	0.000910 U	0.0105 U	0.000311 U	0.00700 U	0.00329 U	0.00405 U	0.00124 U	0.00267 U
	B-263-10	10/18/18	PES	PACE	10	29.8	S	0.0145 U	0.00121 U	0.00689 U	0.000398 U	0.000982 U	0.0114 U	0.000336 U	0.00756 U	0.00355 U	0.00437 U	0.00134 U	0.00288 U
	B-263-15	10/18/18	PES	PACE	15	24.8	S	0.0139 U	0.00116 U	0.00660 U	0.000382 U	0.000942 U	0.0109 U	0.000322 U	0.00725 U	0.00341 U	0.00419 U	0.00129 U	0.00276 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
B-263 (continued)	B-263-18	10/18/18	PES	PACE	18	21.8	S	0.0138 U	0.00115 U	0.00656 U	0.000380 U	0.000936 U	0.0108 U	0.000320 U	0.00720 U	0.00338 U	0.00417 U	0.00128 U	0.00274 U
B-264	B-264-3	10/18/18	PES	PACE	3	36.8	S	0.0138 U	0.00115 U	0.00657 U	0.000380 U	0.000937 U	0.0109 U	0.000320 U	0.00721 U	0.00339 U	0.00417 U	0.00128 U	0.00275 U
	B-264-5	10/18/18	PES	PACE	5	34.8	S	0.0147 U	0.00123 U	0.00700 U	0.000405 U	0.000999 U	0.0116 U	0.000341 U	0.00768 U	0.00361 U	0.00444 U	0.00137 U	0.00293 U
	B-264-8	10/18/18	PES	PACE	8	31.8	S	0.0145 U	0.00121 U	0.00691 U	0.000400 U	0.000986 U	0.0114 U	0.000337 U	0.00759 U	0.00357 U	0.00439 U	0.00135 U	0.00289 U
	B-264-10	10/18/18	PES	PACE	10	29.8	S	0.0140 U	0.00117 U	0.00667 U	0.000386 U	0.000951 U	0.0110 U	0.000325 U	0.00732 U	0.00344 U	0.00423 U	0.00130 U	0.00279 U
	B-264-15	10/18/18	PES	PACE	15	24.8	S	0.0148 U	0.00123 U	0.00704 U	0.000407 U	0.00100 U	0.0116 U	0.000343 U	0.00773 U	0.00363 U	0.00447 U	0.00137 U	0.00294 U
	B-264-16	10/18/18	PES	PACE	16	23.8	S	0.0143 U	0.00119 U	0.00679 U	0.000393 U	0.000969 U	0.0112 U	0.000331 U	0.00745 U	0.00350 U	0.00431 U	0.00132 U	0.00284 U
B-265	B-265-3	10/18/18	PES	PACE	3	36.8	S	0.0152 U	0.00126 U	0.00722 U	0.000418 U	0.00103 U	0.0119 U	0.000352 U	0.00792 U	0.00372 U	0.00458 U	0.00141 U	0.00302 U
	B-265-5	10/18/18	PES	PACE	5	34.8	S	0.0147 U	0.0123 U	0.00701 U	0.000406 U	0.00100 U	0.0116 U	0.000342 U	0.00769 U	0.00362 U	0.00445 U	0.00137 U	0.00293 U
	B-265-8	10/18/18	PES	PACE	8	31.8	S	0.0142 U	0.0118 U	0.00675 U	0.000391 U	0.000963 U	0.0112 U	0.000329 U	0.00741 U	0.00348 U	0.00429 U	0.00132 U	0.00282 U
	B-265-10	10/18/18	PES	PACE	10	29.8	S	0.0140 U	0.00932 U	0.00665 U	0.000385 U	0.000949 U	0.0110 U	0.000324 U	0.00730 U	0.00343 U	0.00422 U	0.00130 U	0.00278 U
	B-265-17.5	10/18/18	PES	PACE	18	22.3	S	0.0141 U	0.00117 U	0.00669 U	0.000387 U	0.000955 U	0.0111 U	0.000326 U	0.00735 U	0.00345 U	0.00425 U	0.00131 U	0.00280 U
B-266	B-266-5	10/18/18	PES	PACE	5	35.7	S	0.0155 U	**0.00663**	0.00737 U	0.000426 U	0.00105 U	0.0122 U	0.000359 U	0.00809 U	0.00380 U	0.00468 U	0.00144 U	0.00308 U
	B-266-8	10/18/18	PES	PACE	8	32.7	S	0.0162 U	0.00133 U	0.00769 U	0.000445 U	0.00110 U	0.0127 U	0.000376 U	0.00845 U	0.00397 U	0.00489 U	0.00150 U	0.00322 U
	B-266-10	10/18/18	PES	PACE	10	30.7	S	0.0204 U	0.00170 U	0.00974 U	0.000564 U	0.00139 U	0.0161 U	0.000475 U	0.0107 U	0.00502 U	0.00617 U	0.00189 U	0.00407 U
	B-266-15	10/18/18	PES	PACE	15	25.7	S	0.0169 U	0.0141 U	0.00807 U	0.000467 U	0.00115 U	0.0133 U	0.000393 U	0.00885 U	0.00416 U	0.00512 U	0.00158 U	0.00337 U
	B-266-20	10/18/18	PES	PACE	20	20.7	S	0.0142 U	0.0473 U	0.00674 U	0.000390 U	0.000962 U	0.0111 U	0.000329 U	0.00740 U	0.00348 U	0.00428 U	0.00132 U	0.00282 U
B-267	B-267-2.5	10/18/18	PES	PACE	2.5	37.4	S	0.0153 U	0.00127 U	0.00727 U	0.000421 U	0.00104 U	0.0120 U	0.000355 U	0.00798 U	0.00375 U	0.00462 U	0.00142 U	0.00304 U
	B-267-5	10/18/18	PES	PACE	5	34.9	S	0.0139 U	0.00116 U	0.00660 U	0.000382 U	0.000941 U	0.0109 U	0.000322 U	0.00724 U	0.00340 U	0.00419 U	0.00129 U	0.00276 U
	B-267-8	10/18/18	PES	PACE	8	31.9	S	0.0152 U	0.00506 U	0.00722 U	0.000418 U	0.00103 U	0.0119 U	0.000352 U	0.00792 U	0.00372 U	0.00458 U	0.00141 U	0.00302 U
	B-267-10	10/18/18	PES	PACE	10	29.9	S	0.0144 U	0.00479 U	0.00684 U	0.000396 U	0.000975 U	0.0113 U	0.000333 U	0.00750 U	0.00353 U	0.00434 U	0.00133 U	0.00286 U
	B-267-15	10/18/18	PES	PACE	15	24.9	S	0.284 U	0.0237 U	0.135 U	0.00782 U	0.0193 U	0.224 U	0.00659 U	0.149 U	0.0697 U	0.0858 U	0.0264 U	0.0566 U
	B-267-20	10/18/18	PES	PACE	20	19.9	S	0.316 U	0.0263 U	0.150 U	0.00870 U	0.0214 U	0.248 U	0.00733 U	0.165 U	0.0775 U	0.0954 U	0.0293 U	0.0629 U
CA-A10	CA-A10-21	09/04/19	PES	Fremont	21	–	S	–	–	–	–	–	–	–	–	–	–	–	–
CA-A12-20	CA-A12-20-24	09/06/19	PES	Fremont	24	–	S	–	–	–	–	–	–	–	–	–	–	–	–
CAA-C1	CAA-C1-43	08/27/19	PES	Fremont	43	–	S	–	–	–	–	–	–	–	–	–	–	–	–
CAA-C2	CAA-C2-10	08/28/19	PES	Fremont	10	–	S	–	–	–	–	–	–	–	–	–	–	–	–
CA-B8	CA-B8-3	09/16/19	PES	Fremont	3	–	S	–	–	–	–	–	–	–	–	–	–	–	–
CA-B19	CA-B19-30	09/27/19	PES	Fremont	30	–	S	–	–	–	–	–	–	–	–	–	–	–	–
CA-B10	CA-B10-17	08/30/19	PES	Fremont	17	–	S	–	–	–	–	–	–	–	–	–	–	–	–
	CA-B10-20	08/30/19	PES	Fremont	20	–	S	–	–	–	–	–	–	–	–	–	–	–	–
	CA-B10-21	08/30/19	PES	Fremont	21	–	S	–	–	–	–	–	–	–	–	–	–	–	–
	CA-B10-25	08/30/19	PES	Fremont	25	–	S	–	–	–	–	–	–	–	–	–	–	–	–
CA-B11	CA-B11-27	09/05/19	PES	Fremont	27	–	S	–	–	–	–	–	–	–	–	–	–	–	–
CA-B18	CA-B18-20	10/26/19	PES	Fremont	20	–	S	–	–	–	–	–	–	–	–	–	–	–	–
CA-B20	CA-B20-31	09/30/19	PES	Fremont	31	–	S	–	–	–	–	–	–	–	–	–	–	–	–
	B-1001-31	09/30/19	PES	Fremont	31 (dup)	–	S	–	–	–	–	–	–	–	–	–	–	–	–
CA-C7	CA-C7-25	09/20/19	PES	Fremont	25	–	S	–	–	–	–	–	–	–	–	–	–	–	–
CA-C8	CA-C8-35	09/03/19	PES	Fremont	35	–	S	–	–	–	–	–	–	–	–	–	–	–	–
CA-C9	CA-C9-09	09/04/19	PES	Fremont	9	–	S	–	–	–	–	–	–	–	–	–	–	–	–
CA-C10	CA-C10-17	09/06/19	PES	Fremont	17	–	S	–	–	–	–	–	–	–	–	–	–	–	–
	CA-C10-26	09/06/19	PES	Fremont	26	–	S	–	–	–	–	–	–	–	–	–	–	–	–
CA-C13	CA-C13-Comp	09/11/19	PES	Fremont	Comp	–	S	–	–	–	–	–	–	–	–	–	–	–	–
CA-D1	CA-D1-Comp	09/11/19	PES	Fremont	Comp	–	S	–	–	–	–	–	–	–	–	–	–	–	–
CA-D2	CA-D2-31	09/16/19	PES	Fremont	31	–	S	–	–	–	–	–	–	–	–	–	–	–	–
	CA-D2-50-52	09/17/19	PES	Fremont	52	–	S	–	–	–	–	–	–	–	–	–	–	–	–
CA-D3	CA-D3-40	09/23/19	PES	Fremont	40	–	S	–	–	–	–	–	–	–	–	–	–	–	–
CA-D4	CA-D4-51	09/19/19	PES	Fremont	51	–	S	–	–	–	–	–	–	–	–	–	–	–	–
	CA-D4-54	09/19/19	PES	Fremont	54	–	S	–	–	–	–	–	–	–	–	–	–	–	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
CA-D5	CA-D5-14	09/03/19	PES	Fremont	14	–	S	–	–	–	–	–	–	–	–	–	–	–	–
	CA-D5-22	09/03/19	PES	Fremont	22	–	S	–	–	–	–	–	–	–	–	–	–	–	–
	CA-D5-26	09/03/19	PES	Fremont	26	–	S	–	–	–	–	–	–	–	–	–	–	–	–
CA-D6	CA-D6-56	09/04/19	PES	Fremont	56	–	S	–	–	–	–	–	–	–	–	–	–	–	–
	CA-D6-65	09/04/19	PES	Fremont	65	–	S	–	–	–	–	–	–	–	–	–	–	–	–
CA-D7	CA-D7-15	09/05/19	PES	Fremont	15	–	S	–	–	–	–	–	–	–	–	–	–	–	–
DB01	DB01-10	3/18/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB01-20	3/18/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB01-30	3/18/13	SES	F&BI	30	10.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB01-40	3/18/13	SES	F&BI	40	0.0	S	–	–	–	–	–	–	–	–	–	–	–	–
DB02	DB02-10	3/18/13	SES	F&BI	10	26.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB02-15	3/18/13	SES	F&BI	15	21.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB02-20	3/18/13	SES	F&BI	20	16.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB02-30	3/18/13	SES	F&BI	30	6.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB02-40	3/18/13	SES	F&BI	40	-4.0	S	–	–	–	–	–	–	–	–	–	–	–	–
DB03	DB03-05	3/27/13	SES	F&BI	5	35.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB03-20	3/27/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB03-35	3/27/13	SES	F&BI	35	5.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB03-45	3/27/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB03-55	3/27/13	SES	F&BI	55	-15.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB03-60	3/27/13	SES	F&BI	60	-20.0	S	–	–	–	–	–	–	–	–	–	–	–	–
DB04	DB04-10	3/21/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB04-20	3/21/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB04-35	3/21/13	SES	F&BI	35	5.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB04-45	3/21/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB04-50	3/22/13	SES	F&BI	50	-10.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB04-60	3/22/13	SES	F&BI	60	-20.0	S	–	–	–	–	–	–	–	–	–	–	–	–
DB05	DB05-10	3/26/13	SES	F&BI	10	41.8	V	–	–	–	–	–	–	–	–	–	–	–	–
	DB05-20	3/26/13	SES	F&BI	20	31.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB05-30	3/26/13	SES	F&BI	30	21.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB05-40	3/26/13	SES	F&BI	40	11.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB05-50	3/26/13	SES	F&BI	50	1.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB05-60	3/26/13	SES	F&BI	60	-8.2	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB05-70	3/26/13	SES	F&BI	70	-18.2	S	–	–	–	–	–	–	–	–	–	–	–	–
DB06	DB06-10	3/25/13	SES	F&BI	10	41.8	V	–	–	–	–	–	–	–	–	–	–	–	–
	DB06-25	3/25/13	SES	F&BI	25	26.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB06-35	3/25/13	SES	F&BI	35	16.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB06-45	3/25/13	SES	F&BI	45	6.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB06-55	3/25/13	SES	F&BI	55	-3.2	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB06-65	3/25/13	SES	F&BI	65	-13.2	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB06-75	3/25/13	SES	F&BI	75	-23.2	S	–	–	–	–	–	–	–	–	–	–	–	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
DB07	DB07-05	3/27/13	SES	F&BI	5	35.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB07-15	3/27/13	SES	F&BI	15	25.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB07-25	3/27/13	SES	F&BI	25	15.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB07-35	3/28/13	SES	F&BI	35	5.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB07-45	3/28/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB07-50	3/28/13	SES	F&BI	50	-10.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB07-60	3/28/13	SES	F&BI	60	-20.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB07-70	3/28/13	SES	F&BI	70	-30.0	S	–	–	–	–	–	–	–	–	–	–	–	–
DB08	DB08-10	3/20/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB08-20	3/20/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB08-35	3/20/13	SES	F&BI	35	5.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB08-45	3/20/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB08-50	3/21/13	SES	F&BI	50	-10.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB08-60	3/21/13	SES	F&BI	60	-20.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB08-70	3/21/13	SES	F&BI	70	-30.0	S	–	–	–	–	–	–	–	–	–	–	–	–
DB09	DB09-10	3/19/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB09-20	3/19/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB09-30	3/19/13	SES	F&BI	30	10.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB09-40	3/19/13	SES	F&BI	40	0.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB09-50	3/19/13	SES	F&BI	50	-10.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB09-60	3/19/13	SES	F&BI	60	-20.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB09-70	3/19/13	SES	F&BI	70	-30.0	S	–	–	–	–	–	–	–	–	–	–	–	–
DB10	DB10-10	3/29/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB10-20	3/29/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB10-35	3/29/13	SES	F&BI	35	5.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB10-45	3/29/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB10-50	4/1/13	SES	F&BI	50	-10.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB10-60	4/1/13	SES	F&BI	60	-20.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB10-70	4/1/13	SES	F&BI	70	-30.0	S	–	–	–	–	–	–	–	–	–	–	–	–
DB11	DB11-15	4/2/13	SES	F&BI	15	36.8	V	–	–	–	–	–	–	–	–	–	–	–	–
	DB11-25	4/2/13	SES	F&BI	25	26.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB11-35	4/2/13	SES	F&BI	35	16.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB11-45	4/2/13	SES	F&BI	45	6.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB11-55	4/2/13	SES	F&BI	55	-3.2	S	–	–	–	–	–	–	–	–	–	–	–	–
DB12	DB12-10	4/3/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB12-20	4/3/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB12-30	4/3/13	SES	F&BI	30	10.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB12-40	4/3/13	SES	F&BI	40	0.0	S	–	–	–	–	–	–	–	–	–	–	–	–
DB13	DB13-10	4/3/13	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB13-20	4/3/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB13-35	4/3/13	SES	F&BI	35	5.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB13-45	4/3/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
DB14	DB14-10	4/4/13	SES	F&BI	10	31.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB14-20	4/4/13	SES	F&BI	20	21.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB14-30	4/4/13	SES	F&BI	30	11.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	DB14-40	4/4/13	SES	F&BI	40	1.5	S	–	–	–	–	–	–	–	–	–	–	–	–
G-MW1	MW 1-3-8	7/20/01	GeoEng	NCA	8	31.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	MW 1-8-20	7/20/01	GeoEng	NCA	20	19.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	MW 1-11-27.5	7/20/01	GeoEng	NCA	27.5	11.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	MW 1-13-32.5	7/20/01	GeoEng	NCA	32.5	6.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	MW 1-15-37.5	7/20/01	GeoEng	NCA	37.5	1.5	S	–	–	–	–	–	–	–	–	–	–	–	–
G-MW3 (G-SB4 11)	SB4-4-10	7/20/01	GeoEng	NCA	10	29.6	S	–	–	–	–	–	–	–	–	–	–	–	–
	SB4-7-17.5	7/20/01	GeoEng	NCA	17.5	22.1	S	–	–	–	–	–	–	–	–	–	–	–	–
	SB4-13-32.5	7/20/01	GeoEng	NCA	32.5	7.1	S	–	–	–	–	–	–	–	–	–	–	–	–
	SB4-15-37.5	7/20/01	GeoEng	NCA	37.5	2.1	S	–	–	–	–	–	–	–	–	–	–	–	–
IW06	IW06-25	1/15/16	SES	F&BI	25	26.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-30	1/15/16	SES	F&BI	30	21.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-40	1/15/16	SES	F&BI	40	11.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-50	1/15/16	SES	F&BI	50	1.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-55	1/15/16	SES	F&BI	55	-3.2	S	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-60	1/15/16	SES	F&BI	60	-8.2	S	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-65	1/15/16	SES	F&BI	65	-13.2	S	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-70	1/15/16	SES	F&BI	70	-18.2	S	–	–	–	–	–	–	–	–	–	–	–	–
	IW06-75	1/15/16	SES	F&BI	75	-23.2	S	–	–	–	–	–	–	–	–	–	–	–	–
IW-1C	IW-1C-5	3/7/18	PES	ESC	5	34.1	S	0.000380 U	0.000322 U	0.00281 U	0.000276 U	0.000270 U	0.00209 U	0.000236 U	0.00111 U	0.00111 U	0.000287 U	0.000229 U	0.000223 U
(-23.9 to-38.9)	IW-1C-15	3/7/18	PES	ESC	15	24.1	S	0.000402 U	**0.000851 J**	0.00297 U	0.000291 U	0.000285 U	0.00221 U	0.000249 U	0.00117 U	0.00117 U	0.000303 U	0.000242 U	0.000236 U
	IW-1C-25	3/7/18	PES	ESC	25	14.1	S	0.0812 U	0.0689 U	0.601 U	0.0589 U	0.0577 U	0.447 U	**0.554 J**	0.238 U	0.238 U	0.0613 U	0.0489 U	0.0477 U
	IW-1C-35	3/7/18	PES	ESC	35	4.1	S	0.000367 U	0.000311 U	0.00271 U	0.000266 U	0.000261 U	0.00202 U	0.000227 U	0.00107 U	0.00107 U	0.000277 U	0.000221 U	0.000216 U
	IW-1C-45	3/7/18	PES	ESC	45	-5.9	S	0.000383 U	**0.00151 J**	0.00283 U	0.000278 U	0.000272 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000289 U	0.000231 U	0.000225 U
	IW-1C-55	3/7/18	PES	ESC	55	-15.9	S	0.000383 U	0.000325 U	0.00283 U	0.000278 U	0.000272 U	0.00211 U	0.000237 U	0.00112 U	0.00112 U	0.000289 U	0.000231 U	0.000225 U
	IW-1C-65	3/7/18	PES	ESC	65	-25.9	S	0.000393 U	0.000333 U	0.00291 U	0.000285 U	0.000279 U	0.00216 U	0.000244 U	0.00115 U	0.00115 U	0.000296 U	0.000237 U	0.000231 U
	IW-1C-75	3/7/18	PES	ESC	75	-35.9	S	0.000411 U	0.000349 U	0.00304 U	0.000298 U	0.000292 U	0.00226 U	0.000255 U	0.00120 U	0.00120 U	0.000310 U	0.000248 U	0.000242 U
IW-2C	IW-2C-5	3/7/18	PES	ESC	5	31.3	S	0.000422 U	**0.00173 J**	0.00312 U	0.000306 U	0.000300 U	0.00232 U	0.000262 U	0.00124 U	0.00124 U	0.000319 U	0.000254 U	0.000248 U
(-24.8 to-39.8)	IW-2C-15	3/7/18	PES	ESC	15	21.3	S	0.000409 U	**0.000408 J**	0.00302 U	0.000296 U	0.000290 U	0.00225 U	0.000253 U	0.00119 U	0.00119 U	0.000308 U	0.000246 U	0.000240 U
	IW-2C-25	3/7/18	PES	ESC	25	11.3	S	0.000382 U	0.000324 U	0.00283 U	0.000277 U	0.000271 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000288 U	0.000230 U	0.000225 U
	IW-2C-35	3/7/18	PES	ESC	35	1.3	S	0.000431 U	**0.000769 J**	0.00319 U	0.000312 U	0.000306 U	0.00237 U	0.000267 U	0.00126 U	0.00126 U	0.000325 U	0.000259 U	0.000253 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	–	–	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	–	–	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
IW-2C	IW-2C-45	3/7/18	PES	ESC	45	-8.7	S	0.000371 U	**0.000782 J**	0.00274 U	0.000269 U	0.000264 U	0.00204 U	0.000230 U	0.00108 U	0.00108 U	0.000280 U	0.000223 U	0.000218 U
(continued)	IW-2C-55	3/7/18	PES	ESC	55	-18.7	S	0.000398 U	**0.00569 J**	0.00295 U	0.000289 U	0.000283 U	0.00219 U	0.000247 U	0.00116 U	0.00116 U	0.000301 U	0.000240 U	0.000234 U
	IW-2C-65	3/7/18	PES	ESC	65	-28.7	S	0.000374 U	0.000317 U	0.00277 U	0.000271 U	0.000266 U	0.00206 U	0.000232 U	0.00109 U	0.00109 U	0.000282 U	0.000225 U	0.000220 U
	IW-2C-75	3/7/18	PES	ESC	75	-38.7	S	0.000411 U	0.000348 U	0.00304 U	0.000298 U	0.000292 U	0.00226 U	0.000255 U	0.00120 U	0.00120 U	0.000310 U	0.000247 U	0.000241 U
IW-3C	IW-3C-5	3/9/18	PES	ESC	5	34.1	S	0.000374 U	0.000317 U	0.00277 U	0.000271 U	0.000266 U	0.00206 U	0.000232 U	0.00109 U	0.00109 U	0.000282 U	0.000225 U	0.000220 U
(-24.9 to-39.9)	IW-3C-15	3/9/18	PES	ESC	15	24.1	S	0.00991 U	0.00840 U	0.0732 U	0.00719 U	0.00705 U	0.0545 U	**0.0700 J**	0.0290 U	0.0290 U	0.00748 U	0.00597 U	0.00582 U
	IW-3C-25	3/9/18	PES	ESC	25	14.1	S	0.202 U	0.171 U	1.49 U	0.146 U	0.144 U	1.11 U	**0.325 J**	0.590 U	0.590 U	0.152 U	0.122 U	0.118 U
	IW-3C-35	3/9/18	PES	ESC	35	4.1	S	0.0760 U	0.0645 U	0.562 U	0.0551 U	0.0540 U	0.418 U	**0.432 J**	0.222 U	0.222 U	0.0573 U	0.0458 U	0.0447 U
	IW-3C-45	3/9/18	PES	ESC	45	-5.9	S	0.000394 U	0.000334 U	0.00292 U	0.000286 U	0.000280 U	0.00217 U	0.000244 U	0.00115 U	0.00115 U	0.000297 U	0.000237 U	0.000232 U
	IW-3C-55	3/9/18	PES	ESC	55	-15.9	S	0.000388 U	0.000329 U	0.00287 U	0.000281 U	0.000276 U	0.00213 U	0.000241 U	0.00113 U	0.00113 U	0.000293 U	0.000234 U	0.000228 U
	IW-3C-65	3/9/18	PES	ESC	65	-25.9	S	0.000390 U	0.000331 U	0.00289 U	0.000283 U	0.000277 U	0.00214 U	0.000242 U	0.00114 U	0.00114 U	0.000294 U	0.000235 U	0.000229 U
	IW-3C-75	3/9/18	PES	ESC	75	-35.9	S	0.000428 U	0.000363 U	0.00317 U	0.000311 U	0.000304 U	0.00235 U	0.000265 U	0.00125 U	0.00125 U	0.000323 U	0.000258 U	0.000252 U
	IW-3C-79	3/9/18	PES	ESC	79	-39.9	S	0.000397 U	0.000337 U	0.00294 U	0.000288 U	0.000282 U	0.00218 U	0.000246 U	0.00116 U	0.00116 U	0.000300 U	0.000239 U	0.000233 U
	IW-901-79	3/9/18	PES	ESC	79 (dup)	-39.9	S	0.000396 U	0.000335 U	0.00293 U	0.000287 U	0.000281 U	0.00217 U	0.000245 U	0.00116 U	0.00116 U	0.000298 U	0.000238 U	0.000233 U
IW-7A	IW-7A-5	3/16/18	PES	ESC	5	35.1	S	0.000424 U	**0.00194 J**	0.00314 U	0.000307 U	0.000301 U	0.00233 U	0.000263 U	0.00124 U	0.00124 U	0.000320 U	**0.000313 J**	0.000249 U
(5.1 to-9.9)	IW-7A-10	3/16/18	PES	ESC	10	30.1	S	0.00424 U	**0.00508 J**	0.00267 U	0.000814 U	**0.0505**	0.0106 U	0.00133 U	0.00427 U	0.00972 U	**0.279**	**0.131**	**0.170**
	IW-7A-15	3/16/18	PES	ESC	15	25.1	S	0.0137 U	**0.0716 J**	0.102 U	0.00997 U	**0.108**	0.0756 U	0.00852 U	0.0402 U	**0.375**	**0.373**	**0.499**	**0.182**
	IW-7A-20	3/16/18	PES	ESC	20	20.1	S	0.00435 U	0.00181 U	0.00274 U	0.000836 U	**0.00455**	0.0109 U	0.00137 U	0.00438 U	0.00997 U	**0.0127**	**0.0112**	**0.00877**
	IW-7A-25	3/16/18	PES	ESC	25	15.1	S	0.000414 U	**0.000647 J**	0.00306 U	0.000300 U	0.000294 U	0.00228 U	0.000257 U	0.00121 U	0.00121 U	0.000313 U	0.000250 U	0.000243 U
	IW-7A-30	3/16/18	PES	ESC	30	10.1	S	0.000397 U	**0.000969 J**	0.00294 U	0.000288 U	**0.000332 J**	0.00218 U	0.000246 U	0.00116 U	0.00116 U	0.000299 U	**0.000493 J**	**0.000333 J**
	IW-7A-35	3/16/18	PES	ESC	35	5.1	S	0.00373 U	0.00155 U	0.00235 U	0.000716 U	**0.00128 J**	0.00933 U	0.00117 U	0.00375 U	0.00854 U	**0.00331**	**0.00389**	**0.00190 J**
	IW-7A-40	3/16/18	PES	ESC	40	0.1	S	0.000403 U	0.000341 U	0.00298 U	0.000292 U	0.000286 U	0.00221 U	0.000250 U	0.00118 U	0.00118 U	0.000304 U	0.000243 U	0.000237 U
	IW-7A-45	3/16/18	PES	ESC	45	-4.9	S	0.000400 U	0.000339 U	0.00296 U	0.000290 U	0.000284 U	0.00220 U	0.000248 U	0.00117 U	0.00117 U	0.000302 U	0.000241 U	0.000235 U
	IW-7A-50	3/16/18	PES	ESC	50	-9.9	S	0.000380 U	0.000322 U	0.00281 U	0.000275 U	0.000270 U	0.00209 U	0.000235 U	0.00111 U	0.00111 U	0.000287 U	0.000229 U	0.000223 U
IW-8B	IW-8B-5	3/19/18	PES	ESC	5	34.2	S	0.000374 U	0.000317 U	0.00277 U	0.000271 U	0.000266 U	0.00206 U	0.000232 U	0.00109 U	0.00109 U	0.000282 U	0.000225 U	0.000220 U
(-9.8 to-24.8)	IW-8B-10	3/19/18	PES	ESC	10	29.2	S	0.000369 U	0.000313 U	0.00273 U	0.000267 U	0.000262 U	0.00203 U	0.000229 U	0.00108 U	0.00108 U	0.000278 U	0.000222 U	0.000217 U
	IW-8B-15	3/19/18	PES	ESC	15	24.2	S	0.0984 U	0.0834 U	0.727 U	0.0714 U	0.0700 U	0.541 U	0.0610 U	0.288 U	0.288 U	0.0742 U	0.0593 U	0.0578 U
	IW-8B-20	3/19/18	PES	ESC	20	19.2	S	0.000375 U	0.000318 U	0.00278 U	0.000272 U	0.000267 U	0.00206 U	0.000233 U	0.00110 U	0.00110 U	0.000283 U	0.000226 U	0.000221 U
	IW-8B-25	3/19/18	PES	ESC	25	14.2	S	0.000400 U	0.000339 U	0.00296 U	0.000290 U	0.000284 U	0.00220 U	0.000248 U	0.00117 U	0.00117 U	0.000302 U	0.000241 U	0.000235 U
	IW-8B-30	3/19/18	PES	ESC	30	9.2	S	0.000384 U	**0.000939 J**	0.00284 U	0.000279 U	0.000273 U	0.00211 U	0.000238 U	0.00112 U	0.00112 U	0.000290 U	0.000232 U	0.000226 U
	IW-8B-40	3/19/18	PES	ESC	40	-0.8	S	0.000381 U	0.000323 U	0.00282 U	0.000277 U	0.000271 U	0.00210 U	0.000236 U	0.00112 U	0.00112 U	0.000288 U	0.000230 U	0.000224 U
	IW-8B-45	3/20/18	PES	ESC	45	-5.8	S	0.000381 U	**0.00357 J**	0.00282 U	0.000276 U	0.000271 U	0.00210 U	0.000236 U	0.00111 U	0.00111 U	0.000288 U	0.000230 U	0.000224 U
	IW-8B-50	3/20/18	PES	ESC	50	-10.8	S	0.000391 U	0.000332 U	0.00289 U	0.000284 U	0.000278 U	0.00215 U	0.000242 U	0.00114 U	0.00114 U	0.000295 U	0.000236 U	0.000230 U
	IW-8B-55	3/20/18	PES	ESC	55	-15.8	S	0.000369 U	**0.00287 J**	0.00273 U	0.000268 U	0.000262 U	0.00203 U	0.000229 U	0.00108 U	0.00108 U	0.000278 U	0.000222 U	0.000217 U
	IW-8B-60	3/20/18	PES	ESC	60	-20.8	S	0.000392 U	0.000332 U	0.00290 U	0.000284 U	0.000278 U	0.00215 U	0.000243 U	0.00115 U	0.00115 U	0.000295 U	0.000236 U	0.000230 U
	IW-8B-64	3/20/18	PES	ESC	64	-24.8	S	0.000386 U	0.000327 U	0.00285 U	0.000280 U	0.000274 U	0.00212 U	0.000239 U	0.00113 U	0.00113 U	0.000291 U	0.000232 U	0.000227 U
IW-8C	IW-8C-5	3/14/18	PES	ESC	5	32.5	S	0.000587 U	**0.00167 J**	0.00434 U	0.000426 U	0.000417 U	0.00323 U	0.000364 U	0.00172 U	**0.00335 J**	0.000444 U	0.000353 U	0.000345 U
(-24.5 to-39.5)	IW-8C-10	3/14/18	PES	ESC	10	27.5	S	0.000592 U	**0.00234 J**	0.00438 U	0.000429 U	0.000420 U	0.00325 U	0.000367 U	0.00173 U	0.00173 U	0.000446 U	0.000356 U	0.000348 U
	IW-8C-15	3/14/18	PES	ESC	15	22.5	S	0.000402 U	0.000341 U	0.00298 U	0.000292 U	0.000287 U	0.00221 U	0.000250 U	0.00118 U	0.00118 U	0.000304 U	0.000242 U	0.000237 U
	IW-8C-20	3/14/18	PES	ESC	20	17.5	S	0.000369 U	0.000313 U	0.00273 U	0.000267 U	0.000262 U	0.00203 U	0.000229 U	0.00108 U	0.00108 U	0.000278 U	0.000222 U	0.000217 U
	IW-8C-25	3/14/18	PES	ESC	25	12.5	S	0.000407 U	0.000345 U	0.00301 U	0.000295 U	0.000289 U	0.00224 U	0.000252 U	0.00119 U	0.00119 U	0.000307 U	0.000245 U	0.000239 U
	IW-8C-30	3/14/18	PES	ESC	30	7.5	S	0.000378 U	0.000321 U	0.00280 U	0.000274 U	0.000269 U	0.00208 U	0.000235 U	0.00111 U	0.00111 U	0.000285 U	0.000228 U	0.000222 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
IW-8C	IW-8C-35	3/14/18	PES	ESC	35	2.5	S	0.000396 U	**0.000832 J**	0.00293 U	0.000287 U	0.000281 U	0.00217 U	0.000245 U	0.00116 U	0.00116 U	0.000298 U	0.000238 U	0.000233 U
(continued)	IW-8C-40	3/14/18	PES	ESC	40	-2.5	S	0.000394 U	0.000334 U	0.00291 U	0.000286 U	0.000280 U	0.00216 U	0.000244 U	0.00115 U	0.00115 U	0.000297 U	0.000237 U	0.000231 U
	IW-8C-45	3/14/18	PES	ESC	45	-7.5	S	0.000386 U	**0.000525 J**	0.00285 U	0.000280 U	0.000274 U	0.00212 U	0.000239 U	0.00113 U	0.00113 U	0.000291 U	0.000232 U	0.000227 U
	IW-8C-50	3/14/18	PES	ESC	50	-12.5	S	0.000402 U	0.000341 U	0.00297 U	0.000291 U	0.000286 U	0.00221 U	0.000249 U	0.00117 U	**0.00128 J**	**0.000473 J**	**0.00101 J**	**0.000431 J**
	IW-8C-55	3/14/18	PES	ESC	55	-17.5	S	0.000395 U	0.000335 U	0.00292 U	0.000286 U	0.000280 U	0.00217 U	0.000245 U	0.00115 U	0.00115 U	0.000298 U	**0.000529 J**	0.000232 U
	IW-8C-60	3/14/18	PES	ESC	60	-22.5	S	0.000391 U	0.000331 U	0.00289 U	0.000283 U	0.000278 U	0.00215 U	0.000242 U	0.00114 U	0.00114 U	0.000295 U	0.000235 U	0.000230 U
	IW-902-60	3/14/18	PES	ESC	60 (dup)	-22.5	S	0.000380 U	0.000322 U	0.00281 U	0.000275 U	0.000270 U	0.00209 U	0.000235 U	0.00111 U	0.00111 U	0.000286 U	0.000229 U	0.000223 U
	IW-8C-65	3/14/18	PES	ESC	65	-27.5	S	0.000410 U	0.000348 U	0.00303 U	0.000297 U	0.000291 U	0.00225 U	0.000254 U	0.00120 U	0.00120 U	0.000309 U	0.000247 U	0.000241 U
	IW-8C-70	3/14/18	PES	ESC	70	-32.5	S	0.000406 U	0.000344 U	0.00300 U	0.000294 U	0.000288 U	0.00223 U	0.000252 U	0.00119 U	0.00119 U	0.000306 U	0.000245 U	0.000239 U
	IW-8C-75	3/14/18	PES	ESC	75	-37.5	S	0.000383 U	0.000325 U	0.00283 U	0.000278 U	0.000272 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000289 U	0.000231 U	0.000225 U
IW-11D	IW-11D-10	4/19/18	PES	ESC	10	28.4	S	0.000472 U	**0.000557 J**	0.00349 U	0.000342 U	0.000335 U	0.00260 U	0.000293 U	0.00138 U	0.00138 U	0.000356 U	0.000284 U	0.000277 U
(-41.8 to-56.8)	IW-11D-15	4/19/18	PES	ESC	15	23.4	S	0.000396 U	0.000336 U	0.00293 U	0.000287 U	0.000282 U	0.00218 U	0.000246 U	0.00116 U	0.00116 U	0.000299 U	0.000239 U	0.000233 U
	IW-11D-20	4/19/18	PES	ESC	20	18.4	S	0.000396 U	0.000335 U	0.00293 U	0.000287 U	0.000281 U	0.00217 U	0.000245 U	0.00116 U	0.00116 U	0.000298 U	0.000238 U	0.000232 U
	IW-11D-25	4/19/18	PES	ESC	25	13.4	S	0.000374 U	0.000317 U	0.00276 U	0.000271 U	0.000266 U	0.00205 U	0.000232 U	0.00109 U	0.00109 U	0.000282 U	0.000225 U	0.000220 U
	IW-11D-30	4/19/18	PES	ESC	30	8.4	S	0.000374 U	**0.00282 J**	0.00277 U	0.000271 U	0.000266 U	0.00206 U	0.000232 U	0.00109 U	0.00109 U	0.000282 U	0.000225 U	0.000220 U
	IW-11D-35	4/19/18	PES	ESC	35	3.4	S	0.000392 U	0.000332 U	0.00290 U	0.000284 U	0.000278 U	0.00215 U	0.000243 U	0.00115 U	0.00115 U	0.000296 U	0.000236 U	0.000230 U
	IW-11D-40	4/19/18	PES	ESC	40	-1.6	S	0.000378 U	0.000320 U	0.00280 U	0.000274 U	0.000269 U	0.00208 U	0.000234 U	0.00111 U	0.00111 U	0.000285 U	0.000228 U	0.000222 U
	IW-11D-45	4/19/18	PES	ESC	45	-6.6	S	0.00962 U	0.00816 U	0.0711 U	0.00698 U	0.00684 U	0.0529 U	0.00597 U	0.0281 U	0.0281 U	0.00726 U	0.00580 U	0.00565 U
	IW-11D-50	4/19/18	PES	ESC	50	-11.6	S	0.000367 U	**0.00121 J**	0.00272 U	0.000266 U	0.000261 U	0.00202 U	0.000228 U	0.00107 U	0.00107 U	0.000277 U	0.000221 U	0.000216 U
	IW-11D-55	4/19/18	PES	ESC	55	-16.6	S	0.000405 U	**0.000569 J**	0.00300 U	0.000294 U	0.000288 U	0.00223 U	0.000251 U	0.00118 U	0.00118 U	0.000306 U	0.000244 U	0.000238 U
	IW-11D-60	4/19/18	PES	ESC	60	-21.6	S	0.000376 U	**0.000700 J**	0.00278 U	0.000272 U	0.000267 U	0.00206 U	0.000233 U	0.00110 U	0.00110 U	0.000283 U	0.000226 U	0.000221 U
	IW-11D-65	4/19/18	PES	ESC	65	-26.6	S	0.000377 U	0.000319 U	0.00279 U	0.000273 U	0.000268 U	0.00207 U	0.000234 U	0.00110 U	0.00110 U	0.000284 U	0.000227 U	0.000221 U
	IW-11D-70	4/19/18	PES	ESC	70	-31.6	S	0.000377 U	0.000320 U	0.00279 U	0.000274 U	0.000268 U	0.00207 U	0.000234 U	0.00110 U	0.00110 U	0.000285 U	0.000227 U	0.000222 U
	IW-11D-75	4/19/18	PES	ESC	75	-36.6	S	0.000395 U	**0.000422 J**	0.00292 U	0.000286 U	0.000281 U	0.00217 U	0.000245 U	0.00115 U	0.00115 U	0.000298 U	0.000238 U	0.000232 U
	IW-11D-80	4/19/18	PES	ESC	80	-41.6	S	0.000384 U	0.000326 U	0.00284 U	0.000279 U	0.000273 U	0.00211 U	0.000238 U	0.00112 U	0.00112 U	0.000290 U	0.000231 U	0.000226 U
	IW-11D-85	4/19/18	PES	ESC	85	-46.6	S	0.000393 U	0.000333 U	0.00291 U	0.000285 U	0.000279 U	0.00216 U	0.000244 U	0.00115 U	0.00115 U	0.000297 U	0.000237 U	0.000231 U
	IW-11D-90	4/19/18	PES	ESC	90	-51.6	S	0.000387 U	0.000329 U	0.00287 U	0.000281 U	0.000275 U	0.00213 U	0.000240 U	0.00113 U	0.00113 U	0.000292 U	0.000233 U	0.000228 U
	IW-11D-95	4/19/18	PES	ESC	95	-56.6	S	0.000401 U	0.000340 U	0.00296 U	0.000291 U	0.000285 U	0.00220 U	0.000248 U	0.00117 U	0.00117 U	0.000302 U	0.000241 U	0.000236 U
IW-12D	IW-12D-42	9/14/18	PES	ESC	42	-3.5	S	0.0138 U	0.00115 U	0.00657 U	0.000380 U	0.000937 U	0.0109 U	0.000320 U	0.00721 U	0.00339 U	0.00417 U	0.00128 U	0.00275 U
(-41.4 to-56.4)	B-928-42	9/14/18	PES	ESC	42 (dup)	-3.5	S	0.0138 U	0.00115 U	0.00657 U	0.000380 U	0.000938 U	0.0109 U	0.000320 U	0.00721 U	0.00339 U	0.00417 U	0.00128 U	0.00275 U
	IW-12D-50	9/14/18	PES	ESC	50	-11.5	S	0.0139 U	0.00116 U	0.00662 U	0.000383 U	0.000944 U	0.0109 U	0.000323 U	**0.00902 J**	0.00341 U	0.00420 U	0.00129 U	0.00277 U
	IW-12D-60	9/14/18	PES	ESC	60	-21.5	S	0.0143 U	0.00119 U	0.00681 U	0.000394 U	0.000972 U	0.0113 U	0.000332 U	**0.0109 J**	0.00351 U	0.00433 U	0.00133 U	0.00285 U
	IW-12D-85	9/17/18	PES	ESC	85	-46.5	S	0.284 U	0.00118 U	0.00676 U	0.000391 U	0.000965 U	0.0112 U	0.000330 U	0.00742 U	0.00349 U	0.00429 U	0.00132 U	0.00283 U
	IW-12D-95	9/17/18	PES	ESC	95	-56.5	S	0.0611 U	**0.00282 J**	0.00728 U	0.000421 U	0.00104 U	0.0120 U	0.000355 U	0.00799 U	0.00375 U	0.00462 U	0.00142 U	0.00304 U
IW-13D	IW-13D-80	9/18/18	PES	ESC	80	-40.8	S	1.13 U	**0.00405 J**	0.00668 U	0.000386 U	0.000952 U	0.0110 U	0.000325 U	0.00733 U	0.00344 U	0.00424 U	0.00130 U	0.00279 U
(-41.0 to-56.0)	IW-13D-85	9/18/18	PES	ESC	85	-45.8	S	0.0146 U	0.00122 U	0.00696 U	0.000403 U	0.000993 U	0.0115 U	0.000340 U	0.00764 U	0.00359 U	0.00442 U	0.00136 U	0.00291 U
	IW-13D-95	9/18/18	PES	ESC	95	-55.8	S	0.0153 U	0.00128 U	0.00728 U	0.000421 U	0.00104 U	0.0120 U	0.000355 U	0.00799 U	0.00376 U	0.00462 U	0.00142 U	0.00304 U
IW-14D	IW-14D-45	9/11/18	PES	ESC	45	-5.9	S	0.0133 U	**0.00489 J**	0.00634 U	0.000367 U	0.000904 U	0.0105 U	0.000309 U	**0.0112**	0.00327 U	0.00402 U	0.00124 U	0.00265 U
(-41.0 to-56.0)	IW-14D-55	9/11/18	PES	ESC	55	-15.9	S	0.0143 U	0.0479 U	0.00684 U	0.000395 U	0.000975 U	0.0113 U	0.000333 U	0.00750 U	0.00353 U	0.00434 U	**0.00287 J**	0.00286 U
	IW-14D-65	9/11/18	PES	ESC	65	-25.9	S	0.0143 U	**0.00251 J**	0.00679 U	0.000393 U	0.000969 U	0.0112 U	0.000331 U	**0.0102**	0.00350 U	0.00431 U	0.00132 U	0.00284 U
	IW-14D-75	9/11/18	PES	ESC	75	-35.9	S	0.0142 U	**0.00162 J**	0.00679 U	0.000393 U	0.000968 U	0.0112 U	**0.000562 J**	**0.00858**	0.00350 U	0.00431 U	0.00132 U	0.00284 U
	IW-14D-86	9/11/18	PES	ESC	86	-46.9	S	0.0140 U	**0.00146 J**	0.00666 U	0.000386 U	0.000951 U	0.0110 U	0.000325 U	0.00731 U	0.00344 U	0.00423 U	0.00130 U	0.00279 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	–	–	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	–	–	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
IW-14D (continued)	IW-14D-95	9/11/18	PES	ESC	95	-55.9	S	0.0144 U	0.00961 U	0.00685 U	0.000396 U	0.000978 U	0.0113 U	**0.00135**	**0.00858**	0.00353 U	0.00435 U	0.00134 U	0.00287 U
IW-15D (-41.9 to-56.9)	IW-15D-54	9/11/18	PES	ESC	54	-2.2	S	0.0136 U	0.00454 U	0.00647 U	0.000375 U	0.000923 U	0.0107 U	**0.00144**	**0.00833**	0.00334 U	0.00411 U	0.00126 U	0.00271 U
IW-16D (-41.5 to-56.2)	IW-16D-85	10/18/18	PES	PACE	85	-45.6	S	0.0592 U	0.00494 U	0.0282 U	0.00163 U	0.00402 U	0.0466 U	0.00137 U	0.0310 U	0.0146 U	0.0179 U	0.00550 U	0.0118 U
	IW-16D-90	10/18/18	PES	PACE	90	-50.6	S	0.0151 U	0.00126 U	0.00717 U	0.000415 U	0.00102 U	0.0119 U	0.000350 U	0.00787 U	0.00370 U	0.00455 U	0.00140 U	0.00300 U
	IW-16D-95	10/18/18	PES	PACE	95	-55.6	S	0.0615 U	0.00513 U	0.0293 U	0.00170 U	0.00418 U	0.0484 U	0.00143 U	0.0322 U	0.0151 U	0.0186 U	0.00571 U	0.0122 U
IW-19B (-10.6 to-25.6)	IW-19B-5	3/19/18	PES	ESC	5	32.4	S	0.000386 U	0.000327 U	0.00286 U	0.000280 U	0.000274 U	0.00212 U	0.000240 U	0.00113 U	0.00113 U	0.000292 U	0.000232 U	0.000227 U
	IW-19B-10	3/19/18	PES	ESC	10	27.4	S	0.000421 U	0.000357 U	0.00311 U	0.000305 U	0.000299 U	0.00231 U	0.000261 U	0.00123 U	0.00123 U	0.000317 U	0.000253 U	0.000247 U
	IW-19B-15	3/19/18	PES	ESC	15	22.4	S	0.000392 U	0.000332 U	0.00290 U	0.000284 U	0.000278 U	0.00215 U	0.000243 U	0.00115 U	0.00115 U	0.000296 U	0.000236 U	0.000230 U
	IW-19B-20	3/19/18	PES	ESC	20	17.4	S	0.000382 U	0.000324 U	0.00283 U	0.000277 U	0.000271 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000288 U	0.000230 U	0.000224 U
	IW-19B-25	3/19/18	PES	ESC	25	12.4	S	0.000401 U	0.000340 U	0.00297 U	0.000291 U	0.000285 U	0.00221 U	0.000249 U	0.00117 U	0.00117 U	0.000303 U	0.000242 U	0.000236 U
	IW-19B-30	3/19/18	PES	ESC	30	7.4	S	0.000384 U	**0.000793 J**	0.00284 U	0.000279 U	0.000273 U	0.00211 U	0.000238 U	0.00112 U	0.00112 U	0.000290 U	0.000231 U	0.000226 U
	IW-19B-35	3/19/18	PES	ESC	35	2.4	S	0.000379 U	**0.00200 J**	0.00281 U	0.000275 U	0.000270 U	0.00209 U	0.000235 U	0.00111 U	0.00111 U	0.000286 U	0.000228 U	0.000223 U
	IW-19B-40	3/19/18	PES	ESC	40	-2.6	S	0.000395 U	0.000335 U	0.00292 U	0.000286 U	0.000280 U	0.00217 U	0.000245 U	0.00115 U	0.00115 U	0.000298 U	0.000238 U	0.000232 U
	IW-19B-45	3/19/18	PES	ESC	45	-7.6	S	0.000417 U	0.000354 U	0.00309 U	0.000303 U	0.000297 U	0.00229 U	0.000259 U	0.00122 U	0.00122 U	0.000315 U	0.000251 U	0.000245 U
	IW-19B-50	3/19/18	PES	ESC	50	-12.6	S	0.000436 U	**0.110**	0.00322 U	0.000317 U	0.000310 U	0.00239 U	0.000270 U	0.00128 U	0.00128 U	0.000329 U	0.000263 U	0.000256 U
	IW-19B-55	3/19/18	PES	ESC	55	-17.6	S	0.000376 U	**0.000325 J**	0.00278 U	0.000273 U	0.000267 U	0.00207 U	0.000233 U	0.00110 U	0.00110 U	0.000284 U	0.000227 U	0.000221 U
	IW-19B-60	3/19/18	PES	ESC	60	-22.6	S	0.000377 U	0.000320 U	0.00279 U	0.000274 U	0.000268 U	0.00207 U	0.000234 U	0.00110 U	0.00110 U	0.000285 U	0.000227 U	0.000222 U
	IW-903-60	3/19/18	PES	ESC	60 (dup)	-22.6	S	0.000384 U	0.000326 U	0.00284 U	0.000278 U	0.000273 U	0.00211 U	0.000238 U	0.00112 U	0.00112 U	0.000290 U	0.000231 U	0.000226 U
	IW-19B-63	3/19/18	PES	ESC	63	-25.6	S	0.000383 U	0.000325 U	0.00283 U	0.000278 U	0.000272 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000289 U	0.000231 U	0.000225 U
IW-21B (-10.1 to-25.1)	IW-21B-5	3/6/18	PES	ESC	5	36.9	V	0.000618 U	0.000524 U	0.00457 U	0.000448 U	0.000439 U	0.00339 U	0.000383 U	0.00181 U	0.00181 U	0.000466 U	0.000372 U	0.000363 U
	IW-21B-10	3/6/18	PES	ESC	10	31.9	S	0.000417 U	**0.00163 J**	0.00308 U	0.000302 U	0.000296 U	0.00229 U	0.000258 U	0.00122 U	0.00122 U	0.000315 U	0.000251 U	0.000245 U
	IW-21B-20	3/6/18	PES	ESC	20	21.9	S	0.000411 U	0.000349 U	0.00304 U	0.000298 U	0.000292 U	0.00226 U	0.000255 U	0.00120 U	0.00120 U	0.000310 U	0.000248 U	0.000242 U
	IW-21B-30	3/6/18	PES	ESC	30	11.9	S	0.000382 U	0.000324 U	0.00283 U	0.000277 U	0.000271 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000288 U	0.000230 U	0.000224 U
	IW-21B-40	3/6/18	PES	ESC	40	1.9	S	0.000378 U	0.000321 U	0.00280 U	0.000274 U	0.000269 U	0.00208 U	0.000234 U	0.00111 U	0.00111 U	0.000285 U	0.000228 U	0.000222 U
	IW-21B-50	3/6/18	PES	ESC	50	-8.1	S	0.000370 U	0.000314 U	0.00274 U	0.000268 U	0.000263 U	0.00203 U	0.000229 U	0.00108 U	0.00108 U	0.000279 U	0.000223 U	0.000217 U
	IW-21B-60	3/6/18	PES	ESC	60	-18.1	S	0.00969 U	0.00822 U	0.0716 U	0.00703 U	0.00689 U	0.0533 U	0.00601 U	0.0283 U	0.0283 U	0.00731 U	0.00584 U	0.00569 U
	IW-21B-67	3/6/18	PES	ESC	67	-25.1	S	0.000379 U	0.000321 U	0.00280 U	0.000275 U	0.000269 U	0.00208 U	0.000235 U	0.00111 U	0.00111 U	0.000286 U	0.000228 U	0.000223 U
IW-22C (-25.6 to-40.6)	IW-22C-62	8/31/18	PES	ESC	62	-23.1	S	0.0147 U	0.00122 U	0.00698 U	0.000404 U	0.000996 U	0.0115 U	0.000341 U	0.00766 U	0.00360 U	0.00443 U	**0.00179 J**	0.00292 U
	IW-22C-78	8/31/18	PES	ESC	78	-39.1	S	0.0154 U	0.00128 U	0.00733 U	0.000424 U	0.00105 U	0.0121 U	0.000357 U	0.00804 U	0.00378 U	0.00465 U	0.00143 U	0.00306 U
IW-23C (-27.0 to-42.0)	IW-23C-42	9/4/18	PES	ESC	42	-3.0	S	0.0152 U	0.00127 U	0.00724 U	0.000419 U	**0.00186 J**	0.0120 U	0.000353 U	0.00795 U	**0.0229**	**0.00802 J**	**0.00809**	**0.00399 J**
IW-24C (-26.1 to-41.1)	IW-24C-48	9/7/18	PES	ESC	48	-8.8	S	0.0144 U	0.00120 U	0.00684 U	0.000396 U	0.000975 U	0.0113 U	0.000333 U	0.00751 U	0.00353 U	0.00434 U	0.00133 U	0.00286 U
	IW-24C-55	9/7/18	PES	ESC	55	-15.8	S	0.0151 U	0.00126 U	0.720 U	0.000417 U	**0.00133 J**	0.0119 U	0.000352 U	0.00790 U	**0.00586 J**	**0.00478 J**	**0.00290 J**	0.00301 U
	IW-24C-66	9/10/18	PES	ESC	66	-26.8	S	0.0157 U	**0.00438 J**	0.00748 U	0.000433 U	**0.00161 J**	0.0124 U	0.000365 U	**0.00907**	**0.00746 J**	**0.00916 J**	**0.00663**	**0.00315 J**
	IW-24C-75	9/10/18	PES	ESC	75	-35.8	S	0.0152 U	0.00126 U	0.00723 U	0.000418 U	**0.00149 J**	0.0120 U	0.000353 U	**0.0112**	**0.00881 J**	**0.00998 J**	**0.00761**	**0.00336 J**
	IW-24C-80	9/10/18	PES	ESC	80	-40.8	S	0.0140 U	0.0234 U	0.00669 U	0.000387 U	0.000955 U	0.0111 U	0.000326 U	0.00734 U	0.00345 U	0.00425 U	0.00131 U	0.00280 U
IW-27B (-8.1 to-23.1)	IW-27B-5	3/2/18	PES	ESC	5	37.0	V	0.000548 U	**0.00103 J**	0.00405 U	0.000397 U	0.000389 U	0.00301 U	0.000340 U	0.00160 U	0.00160 U	0.000414 U	0.000330 U	0.000322 U
	IW-27B-15	3/2/18	PES	ESC	15	27.0	S	0.000487 U	**0.00233 J**	0.00360 U	0.000353 U	0.000346 U	0.00268 U	0.000302 U	0.00142 U	0.00142 U	0.000367 U	0.000293 U	0.000286 U
	IW-27B-25	3/2/18	PES	ESC	25	17.0	S	0.000398 U	0.000337 U	0.00294 U	0.000288 U	0.000283 U	0.00219 U	0.000247 U	0.00116 U	0.00116 U	0.000300 U	0.000240 U	0.000234 U
	IW-27B-35	3/2/18	PES	ESC	35	7.0	S	0.000391 U	0.000332 U	0.00290 U	0.000284 U	0.000278 U	0.00215 U	0.000243 U	0.00114 U	0.00114 U	0.000295 U	0.000236 U	0.000230 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	–	–	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	–	–	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
IW-27C (-24.4 to-39.6)	IW-27C-45	9/10/18	PES	ESC	45	6.8	S	0.0142 U	0.0237 U	0.00677 U	0.000392 U	0.000966 U	0.0112 U	0.000330 U	0.00743 U	0.00349 U	0.00430 U	0.00132 U	0.00283 U
IW-28C (-26.6 to-41.7)	IW-28C-92	9/17/18	PES	ESC	92	-40.6	S	0.0552 U	**0.00228 J**	0.00658 U	0.000380 U	0.000938 U	0.0109 U	0.000321 U	0.00722 U	0.00339 U	0.00417 U	0.00128 U	0.00275 U
IW-39B (-9.8 to-24.8)	IW-39B-5	3/12/18	PES	ESC	5	35.2	V	0.000434 U	0.000368 U	0.00321 U	0.000315 U	0.000309 U	0.00239 U	0.000269 U	0.00127 U	0.00127 U	0.000328 U	0.000262 U	0.000255 U
	IW-39B-15	3/12/18	PES	ESC	15	25.2	S	0.000381 U	0.000323 U	0.00282 U	0.000276 U	0.000271 U	0.00210 U	0.000236 U	0.00111 U	0.00111 U	0.000288 U	0.000230 U	0.000224 U
	IW-39B-25	3/12/18	PES	ESC	25	15.2	S	0.000407 U	0.000345 U	0.00301 U	0.000295 U	0.000289 U	0.00223 U	0.000252 U	0.00119 U	0.00119 U	0.000307 U	0.000245 U	0.000239 U
	IW-39B-35	3/12/18	PES	ESC	35	5.2	S	0.000376 U	0.000318 U	0.00278 U	0.000272 U	0.000267 U	0.00206 U	0.000233 U	0.00110 U	0.00110 U	0.000283 U	0.000226 U	0.000221 U
	IW-39B-45	3/12/18	PES	ESC	45	-4.8	S	0.000383 U	0.000325 U	0.00284 U	0.000278 U	0.000272 U	0.00211 U	0.000238 U	0.00112 U	0.00112 U	0.000289 U	0.000231 U	0.000225 U
	IW-39B-55	3/12/18	PES	ESC	55	-14.8	S	0.00898 U	0.00761 U	0.0664 U	0.00651 U	0.00638 U	0.0494 U	0.00557 U	0.0263 U	0.0263 U	0.00677 U	0.00541 U	0.00527 U
IW-46B (-4.2 to-24.2)	IW-46B-5	3/20/18	PES	ESC	5	46.8	V	0.000384 U	0.000326 U	0.00284 U	0.000279 U	0.000273 U	0.00211 U	0.000238 U	0.00112 U	0.00112 U	0.000290 U	0.000232 U	0.000226 U
	IW-46B-10	3/20/18	PES	ESC	10	41.8	V	0.000376 U	0.000319 U	0.00278 U	0.000273 U	0.000267 U	0.00207 U	0.000233 U	0.00110 U	0.00110 U	0.000284 U	0.000226 U	0.000221 U
	IW-46B-15	3/20/18	PES	ESC	15	36.8	V	0.00946 U	0.00802 U	0.0699 U	0.00686 U	0.00673 U	0.0520 U	0.00586 U	0.0277 U	0.0277 U	0.00713 U	0.00570 U	0.00555 U
	IW-46B-20	3/20/18	PES	ESC	20	31.8	S	0.000382 U	0.000324 U	0.00283 U	0.000277 U	0.000272 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000288 U	0.000230 U	0.000225 U
	IW-46B-25	3/20/18	PES	ESC	25	26.8	S	0.000378 U	0.000321 U	0.00280 U	0.000274 U	0.000269 U	0.00208 U	0.000234 U	0.00111 U	0.00111 U	0.000285 U	0.000228 U	0.000222 U
	IW-46B-30	3/20/18	PES	ESC	30	21.8	S	0.000382 U	0.000324 U	0.00283 U	0.000277 U	0.000272 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000289 U	0.000230 U	0.000225 U
	IW-46B-35	3/20/18	PES	ESC	35	16.8	S	0.000414 U	0.000351 U	0.00306 U	0.000300 U	0.000294 U	0.00227 U	0.000256 U	0.00121 U	0.00121 U	0.000312 U	0.000249 U	0.000243 U
	IW-904-35	3/20/18	PES	ESC	35 (dup)	16.8	S	0.000437 U	0.000371 U	0.00324 U	0.000317 U	0.000311 U	0.00240 U	0.000271 U	0.00128 U	0.00128 U	0.000330 U	0.000263 U	0.000257 U
	IW-46B-40	3/20/18	PES	ESC	40	11.8	S	0.000359 U	**0.000618 J**	0.00266 U	0.000261 U	0.000255 U	0.00198 U	0.000223 U	0.00105 U	0.00105 U	0.000271 U	0.000217 U	0.000211 U
	IW-46B-42	3/20/18	PES	ESC	42	9.8	S	0.000411 U	**0.00177 J**	0.00304 U	0.000298 U	0.000292 U	0.00226 U	0.000255 U	0.00120 U	0.00120 U	0.000310 U	0.000248 U	0.000242 U
	IW-46B-45	3/20/18	PES	ESC	45	6.8	S	1.95 U	1.65 U	14.3 U	1.41 U	1.39 U	10.7 U	1.21 U	5.69 U	5.69 U	1.47 U	1.17 U	1.14 U
	IW-46B-50	3/20/18	PES	ESC	50	1.8	S	0.000342 U	0.000290 U	0.00253 U	0.000248 U	0.000243 U	0.00188 U	0.000212 U	0.00100 U	0.00100 U	0.000258 U	0.000206 U	0.000201 U
	IW-46B-55	3/20/18	PES	ESC	55	-3.2	S	0.000381 U	0.000323 U	0.00282 U	0.000277 U	0.000271 U	0.00210 U	0.000236 U	0.00112 U	0.00112 U	0.000288 U	0.000230 U	0.000224 U
	IW-46B-60	3/20/18	PES	ESC	60	-8.2	S	0.000386 U	0.000328 U	0.00286 U	0.000280 U	0.000274 U	0.00212 U	0.000239 U	0.00113 U	0.00113 U	0.000291 U	0.000233 U	0.000227 U
	IW-46B-65	3/20/18	PES	ESC	65	-13.2	S	0.000380 U	0.000322 U	0.00281 U	0.000276 U	0.000270 U	0.00209 U	0.000236 U	0.00111 U	0.00111 U	0.000287 U	0.000229 U	0.000223 U
	IW-46B-70	3/20/18	PES	ESC	70	-18.2	S	0.000436 U	0.000370 U	0.00323 U	0.000316 U	0.000310 U	0.00240 U	0.000270 U	0.00128 U	0.00128 U	0.000329 U	0.000263 U	0.000256 U
IW-47B (-5.2 to-25.2)	IW-47B-5	3/22/18	PES	ESC	5	46.8	V	0.000403 U	0.000342 U	0.00298 U	0.000293 U	0.000287 U	0.00222 U	0.000250 U	0.00118 U	0.00118 U	0.000304 U	0.000243 U	0.000237 U
	IW-47B-10	3/22/18	PES	ESC	10	41.8	V	0.000402 U	0.000341 U	0.00298 U	0.000292 U	0.000286 U	0.00221 U	0.000249 U	0.00118 U	0.00118 U	0.000303 U	0.000242 U	0.000236 U
	IW-47B-15	3/22/18	PES	ESC	15	36.8	V	0.000382 U	0.000324 U	0.00282 U	0.000277 U	0.000271 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000288 U	0.000230 U	0.000224 U
	IW-47B-20	3/22/18	PES	ESC	20	31.8	S	0.000380 U	0.000322 U	0.00281 U	0.000275 U	0.000270 U	0.00209 U	0.000235 U	0.00111 U	0.00111 U	0.000286 U	0.000229 U	0.000223 U
	IW-47B-25	3/22/18	PES	ESC	25	26.8	S	0.000387 U	0.000328 U	0.00286 U	0.000281 U	0.000275 U	0.00213 U	0.000240 U	0.00113 U	0.00113 U	0.000292 U	0.000233 U	0.000227 U
	IW-47B-30	3/22/18	PES	ESC	30	21.8	S	0.000383 U	0.000325 U	0.00284 U	0.000278 U	0.000272 U	0.00211 U	0.000238 U	0.00112 U	0.00112 U	0.000289 U	0.000231 U	0.000225 U
	IW-47B-35	3/22/18	PES	ESC	35	16.8	S	0.000376 U	0.000319 U	0.00278 U	0.000273 U	0.000267 U	0.00207 U	0.000233 U	0.00110 U	0.00110 U	0.000284 U	0.000227 U	0.000221 U
	IW-47B-40	3/22/18	PES	ESC	40	11.8	S	0.000388 U	**0.00235 J**	0.00287 U	0.000282 U	0.000276 U	0.00213 U	0.000241 U	0.00114 U	0.00114 U	0.000293 U	0.000234 U	0.000228 U
	IW-47B-42	3/22/18	PES	ESC	42	9.8	S	0.000448 U	**0.000702 J**	0.00332 U	0.000325 U	0.000318 U	0.00246 U	0.000279 U	0.00131 U	0.00131 U	0.000339 U	0.000271 U	0.000264 U
	IW-47B-45	3/22/18	PES	ESC	45	6.8	S	0.000387 U	0.000328 U	0.00286 U	0.000280 U	0.000275 U	0.00213 U	0.000240 U	0.00113 U	0.00113 U	0.000292 U	0.000233 U	0.000227 U
	IW-47B-50	3/22/18	PES	ESC	50	1.8	S	0.000402 U	0.000341 U	0.00297 U	0.000291 U	0.000285 U	0.00221 U	0.000249 U	0.00117 U	0.00117 U	0.000303 U	0.000242 U	0.000236 U
	IW-47B-55	3/22/18	PES	ESC	55	-3.2	S	0.000370 U	0.000313 U	0.00273 U	0.000268 U	0.000263 U	0.00203 U	0.000229 U	0.00108 U	0.00108 U	0.000279 U	0.000223 U	0.000217 U
	IW-47B-60	3/22/18	PES	ESC	60	-8.2	S	0.000391 U	0.000332 U	0.00289 U	0.000278 U	0.000278 U	0.00215 U	0.000242 U	0.00114 U	0.00114 U	0.000295 U	0.000236 U	0.000230 U
	IW-47B-65	3/22/18	PES	ESC	65	-13.2	S	0.000386 U	0.000327 U	0.00286 U	0.000280 U	0.000274 U	0.00212 U	0.000239 U	0.00113 U	0.00113 U	0.000291 U	0.000233 U	0.000227 U
	IW-47B-70	3/22/18	PES	ESC	70	-18.2	S	0.000382 U	0.000324 U	0.00282 U	0.000277 U	0.000271 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000288 U	0.000230 U	0.000224 U
	IW-47B-75	3/22/18	PES	ESC	75	-23.2	S	0.000381 U	0.000323 U	0.00282 U	0.000276 U	0.000270 U	0.00209 U	0.000236 U	0.00111 U	0.00111 U	0.000287 U	0.000229 U	0.000224 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
IW-48B	IW-48B-5	3/23/18	PES	ESC	5	46.7	V	0.000395 U	0.000335 U	0.00292 U	0.000287 U	0.000281 U	0.00217 U	0.000245 U	0.00116 U	0.00116 U	0.000298 U	0.000238 U	0.000232 U
(-9.4 to-24.4)	IW-48B-10	3/23/18	PES	ESC	10	41.7	V	0.000387 U	0.000328 U	0.00286 U	0.000281 U	0.000275 U	0.00213 U	0.000240 U	0.00113 U	0.00113 U	0.000292 U	0.000233 U	0.000228 U
	IW-48B-15	3/23/18	PES	ESC	15	36.7	V	0.000399 U	**0.00319 J**	0.00295 U	0.000290 U	0.000284 U	0.00220 U	0.000248 U	0.00117 U	0.00117 U	0.000301 U	0.000241 U	0.000235 U
	IW-48B-20	3/23/18	PES	ESC	20	31.7	S	0.000376 U	0.000319 U	0.00278 U	0.000273 U	0.000267 U	0.00207 U	0.000233 U	0.00110 U	0.00110 U	0.000284 U	0.000227 U	0.000221 U
	IW-48B-25	3/23/18	PES	ESC	25	26.7	S	0.000385 U	0.000327 U	0.00285 U	0.000279 U	0.000274 U	0.00212 U	0.000239 U	0.00113 U	0.00113 U	0.000290 U	0.000232 U	0.000226 U
	IW-48B-30	3/23/18	PES	ESC	30	21.7	S	0.000377 U	0.000320 U	0.00279 U	0.000273 U	0.000268 U	0.00207 U	0.000234 U	0.00110 U	0.00110 U	0.000284 U	0.000227 U	0.000222 U
	IW-48B-35	3/23/18	PES	ESC	35	16.7	S	0.000393 U	0.000334 U	0.00291 U	0.000285 U	0.000280 U	0.00216 U	0.000244 U	0.00115 U	0.00115 U	0.000297 U	0.000237 U	0.000231 U
	IW-48B-40	3/23/18	PES	ESC	40	11.7	S	0.000373 U	**0.00104 J**	0.00276 U	0.000271 U	0.000265 U	0.00205 U	0.000231 U	0.00109 U	0.00109 U	0.000282 U	0.000225 U	0.000219 U
	IW-48B-42	3/23/18	PES	ESC	42	9.7	S	0.000377 U	0.000320 U	0.00279 U	0.000273 U	0.000268 U	0.00207 U	0.000234 U	0.00110 U	0.00110 U	0.000284 U	0.000227 U	0.000222 U
	IW-905-42	3/23/18	PES	ESC	42 (dup)	9.7	S	0.000374 U	0.000317 U	0.00276 U	0.000271 U	0.000265 U	0.00205 U	0.000232 U	0.00109 U	0.00109 U	0.000282 U	0.000225 U	0.000220 U
	IW-48B-45	3/23/18	PES	ESC	45	6.7	S	0.000371 U	0.000315 U	0.00274 U	0.000269 U	0.000264 U	0.00204 U	0.000230 U	0.00108 U	0.00108 U	0.000280 U	0.000224 U	0.000218 U
	IW-48B-50	3/23/18	PES	ESC	50	1.7	S	0.000377 U	0.000320 U	0.00279 U	0.000274 U	0.000268 U	0.00208 U	0.000234 U	0.00110 U	0.00110 U	0.000285 U	0.000227 U	0.000222 U
	IW-48B-55	3/23/18	PES	ESC	55	-3.3	S	0.000371 U	0.000315 U	0.00274 U	0.000269 U	0.000264 U	0.00204 U	0.000230 U	0.00108 U	0.00108 U	0.000280 U	0.000223 U	0.000218 U
	IW-48B-60	3/23/18	PES	ESC	60	-8.3	S	0.000378 U	0.000321 U	0.00280 U	0.000274 U	0.000269 U	0.00208 U	0.000235 U	0.00111 U	0.00111 U	0.000285 U	0.000228 U	0.000222 U
	IW-48B-65	3/23/18	PES	ESC	65	-13.3	S	0.000404 U	**0.00151 J**	0.00299 U	0.000293 U	0.000287 U	0.00222 U	0.000250 U	0.00118 U	0.00118 U	0.000305 U	0.000243 U	0.000237 U
	IW-48B-70	3/23/18	PES	ESC	70	-18.3	S	0.000376 U	0.000319 U	0.00278 U	0.000273 U	0.000267 U	0.00207 U	0.000233 U	0.00110 U	0.00110 U	0.000284 U	0.000226 U	0.000221 U
	IW-48B-75	3/23/18	PES	ESC	75	-23.3	S	0.000385 U	**0.000476 J**	0.00285 U	0.000279 U	0.000273 U	0.00211 U	0.000238 U	0.00112 U	0.00112 U	0.000290 U	0.000232 U	0.000226 U
IW-50A	IW-50A-5	3/27/18	PES	ESC	5	46.9	V	0.000390 U	**0.00123 J**	0.00289 U	0.000283 U	0.000277 U	**0.00621 J**	0.000242 U	0.00114 U	0.00114 U	0.000294 U	0.000235 U	0.000229 U
(9.8 to-10.2)	IW-50A-10	3/27/18	PES	ESC	10	41.9	V	0.000381 U	0.000323 U	0.00282 U	0.000276 U	0.000271 U	0.00210 U	0.000236 U	0.00111 U	0.00111 U	0.000288 U	0.000230 U	0.000224 U
	IW-50A-15	3/27/18	PES	ESC	15	36.9	V	0.000376 U	0.000319 U	0.00278 U	0.000272 U	0.000267 U	0.00207 U	0.000233 U	0.00110 U	0.00110 U	0.000283 U	0.000226 U	0.000221 U
	IW-50A-20	3/27/18	PES	ESC	20	31.9	S	0.000380 U	0.000322 U	0.00281 U	0.000276 U	0.000270 U	0.00209 U	0.000236 U	0.00111 U	0.00111 U	0.000287 U	0.000229 U	0.000223 U
	IW-50A-25	3/27/18	PES	ESC	25	26.9	S	0.000370 U	0.000314 U	0.00274 U	0.000268 U	0.000263 U	0.00203 U	0.000229 U	0.00108 U	0.00108 U	0.000279 U	0.000223 U	0.000218 U
	IW-50A-30	3/27/18	PES	ESC	30	21.9	S	0.000371 U	0.000315 U	0.00275 U	0.000269 U	0.000264 U	0.00204 U	0.000230 U	0.00109 U	0.00109 U	0.000280 U	0.000224 U	0.000218 U
	IW-50A-35	3/27/18	PES	ESC	35	16.9	S	0.000372 U	**0.00423 J**	0.00275 U	0.000270 U	0.000265 U	0.00205 U	0.000231 U	0.00109 U	0.00109 U	0.000281 U	0.000224 U	0.000219 U
	IW-50A-40	3/27/18	PES	ESC	40	11.9	S	0.000378 U	0.000320 U	0.00280 U	0.000274 U	0.000268 U	0.00208 U	0.000234 U	0.00110 U	0.00110 U	0.000285 U	0.000228 U	0.000222 U
	IW-50A-42	3/27/18	PES	ESC	42	9.9	S	0.000376 U	0.000319 U	0.00278 U	0.000272 U	0.000267 U	0.00207 U	0.000233 U	0.00110 U	0.00110 U	0.000283 U	0.000226 U	0.000221 U
	IW-50A-45	3/27/18	PES	ESC	45	6.9	S	0.000379 U	0.000321 U	0.00280 U	0.000275 U	0.000269 U	0.00208 U	0.000235 U	0.00111 U	0.00111 U	0.000286 U	0.000228 U	0.000223 U
	IW-50A-50	3/27/18	PES	ESC	50	1.9	S	0.000384 U	0.000325 U	0.00284 U	0.000278 U	0.000273 U	0.00211 U	0.000238 U	0.00112 U	0.00112 U	0.000289 U	0.000231 U	0.000226 U
	IW-906-50	3/27/18	PES	ESC	50 (dup)	1.9	S	0.000386 U	0.000327 U	0.00286 U	0.000280 U	0.000274 U	0.00212 U	0.000239 U	0.00113 U	0.00113 U	0.000291 U	0.000233 U	0.000227 U
	IW-50A-55	3/27/18	PES	ESC	55	-3.2	S	0.000385 U	0.000326 U	0.00285 U	0.000279 U	0.000273 U	0.00212 U	0.000239 U	0.00113 U	0.00113 U	0.000290 U	0.000232 U	0.000226 U
	IW-50A-60	3/27/18	PES	ESC	60	-8.2	S	0.000386 U	0.000328 U	0.00286 U	0.000280 U	0.000274 U	0.00212 U	0.000239 U	0.00113 U	0.00113 U	0.000291 U	0.000233 U	0.000227 U
IW-51A	IW-51A-5	3/26/18	PES	ESC	5	46.9	V	0.000376 U	0.000319 U	0.00278 U	0.000273 U	0.000267 U	0.00207 U	0.000233 U	0.00110 U	0.00110 U	0.000284 U	0.000227 U	0.000221 U
(9.9 to-10.1)	IW-51A-10	3/26/18	PES	ESC	10	41.9	V	0.000373 U	0.000316 U	0.00276 U	0.000270 U	0.000265 U	0.00205 U	0.000231 U	0.00109 U	0.00109 U	0.000281 U	0.000225 U	0.000219 U
	IW-51A-15	3/26/18	PES	ESC	15	36.9	V	0.000388 U	0.000329 U	0.00287 U	0.000281 U	0.000276 U	0.00213 U	0.000240 U	0.00113 U	0.00113 U	0.000293 U	0.000234 U	0.000228 U
	IW-51A-20	3/26/18	PES	ESC	20	31.9	S	0.000371 U	0.000314 U	0.00274 U	0.000269 U	0.000263 U	0.00204 U	0.000230 U	0.00108 U	0.00108 U	0.000280 U	0.000223 U	0.000218 U
	IW-51A-25	3/26/18	PES	ESC	25	26.9	S	0.000472 U	0.000400 U	0.00349 U	0.000342 U	0.000335 U	0.00260 U	0.000292 U	0.00138 U	0.00138 U	0.000356 U	0.000285 U	0.000277 U
	IW-51A-30	3/26/18	PES	ESC	30	21.9	S	0.000369 U	0.000313 U	0.00273 U	0.000267 U	0.000262 U	0.00203 U	0.000228 U	0.00108 U	0.00108 U	0.000278 U	0.000222 U	0.000217 U
	IW-51A-35	3/26/18	PES	ESC	35	16.9	S	0.000372 U	0.000316 U	0.00276 U	0.000270 U	0.000265 U	0.00205 U	0.000231 U	0.00109 U	0.00109 U	0.000281 U	0.000224 U	0.000219 U
	IW-51A-40	3/26/18	PES	ESC	40	11.9	S	0.000374 U	0.000317 U	0.00276 U	0.000271 U	0.000265 U	0.00205 U	0.000232 U	0.00109 U	0.00109 U	0.000282 U	0.000225 U	0.000220 U
	IW-51A-42	3/26/18	PES	ESC	42	9.9	S	0.000381 U	0.000323 U	0.00282 U	0.000276 U	0.000270 U	0.00209 U	0.000236 U	0.00111 U	0.00111 U	0.000287 U	0.000229 U	0.000224 U
	IW-51A-45	3/26/18	PES	ESC	45	6.9	S	0.000381 U	0.000323 U	0.00282 U	0.000276 U	0.000271 U	0.00209 U	0.000236 U	0.00111 U	0.00111 U	0.000287 U	0.000229 U	0.000224 U
	IW-51A-50	3/26/18	PES	ESC	50	1.9	S	0.000392 U	0.000332 U	0.00290 U	0.000284 U	0.000278 U	0.00215 U	0.000243 U	0.00115 U	0.00115 U	0.000296 U	0.000236 U	0.000230 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
IW-51A (continued)	IW-51A-55	3/26/18	PES	ESC	55	-3.1	S	0.000392 U	0.000332 U	0.00290 U	0.000284 U	0.000279 U	0.00216 U	0.000243 U	0.00115 U	0.00115 U	0.000296 U	0.000236 U	0.000230 U
	IW-51A-60	3/26/18	PES	ESC	60	-8.1	S	0.000368 U	0.000312 U	0.00272 U	0.000267 U	0.000261 U	0.00202 U	0.000228 U	0.00108 U	0.00108 U	0.000278 U	0.000222 U	0.000216 U
	IW-51A-62	3/26/18	PES	ESC	62	-10.1	S	0.000372 U	0.000315 U	0.00275 U	0.000270 U	0.000264 U	0.00204 U	0.000231 U	0.00109 U	0.00109 U	0.000281 U	0.000224 U	0.000219 U
IW-53B (-11.1 to-26.1)	IW-53B-30	9/20/18	PES	ESC	30	5.3	S	0.138 U	**0.00339 J**	0.00658 U	0.000381 U	0.000939 U	0.0109 U	0.000321 U	0.00722 U	0.00339 U	0.00418 U	0.00128 U	0.00275 U
IW-54A (9.8 to-10.2)	IW-54A-8	9/12/18	PES	ESC	8	31.1	S	0.0147 U	0.00122 U	0.00698 U	0.000404 U	0.000996 U	0.0115 U	0.000340 U	0.00766 U	0.00360 U	0.00443 U	0.00136 U	0.00292 U
	IW-54A-49	9/12/18	PES	ESC	49	-9.9	S	0.0147 U	0.00123 U	0.00701 U	0.000405 U	0.00100 U	0.0116 U	0.000342 U	**0.00867 J**	0.00361 U	0.00445 U	0.00137 U	0.00293 U
IW-54B (-9.5 to-24.5)	IW-54B-8	9/5/18	PES	ESC	8	31.2	S	0.0139 U	0.00116 U	0.00660 U	0.000382 U	**0.000956 J**	0.0109 U	0.000322 U	0.00724 U	0.00340 U	0.00419 U	**0.00358 J**	0.00276 U
	IW-54B-13	9/6/18	PES	ESC	13	26.2	S	0.0141 U	0.00118 U	0.00671 U	0.000388 U	0.000957 U	0.0111 U	0.000327 U	0.00737 U	0.00346 U	0.00426 U	0.00131 U	0.00281 U
	IW-54B-21	9/6/18	PES	ESC	21	18.2	S	0.0139 U	0.00116 U	0.00660 U	0.000382 U	0.000942 U	0.0109 U	0.000322 U	0.00724 U	0.00340 U	0.00419 U	0.00129 U	0.00276 U
	IW-54B-33	9/6/18	PES	ESC	33	6.2	S	0.0159 U	0.00132 U	0.00756 U	0.000438 U	0.00108 U	0.0125 U	0.000369 U	0.00830 U	0.00390 U	0.00480 U	0.00147 U	0.00316 U
IW-55B (-12.0 to-27.0)	IW-55B-39	9/13/18	PES	ESC	39	12.8	S	0.0135 U	0.00113 U	0.00642 U	0.000372 U	0.000916 U	0.0106 U	0.000313 U	**0.00906 J**	0.00331 U	0.00408 U	0.00125 U	0.00269 U
	IW-55B-43	9/13/18	PES	ESC	43	8.8	S	0.0144 U	0.00120 U	0.00684 U	0.000396 U	0.000976 U	0.0113 U	0.000334 U	0.00751 U	0.00353 U	0.00434 U	0.00133 U	0.00286 U
	IW-55B-61	9/13/18	PES	ESC	61	-9.2	S	0.0151 U	0.00126 U	0.00719 U	0.000416 U	0.00103 U	0.0119 U	0.000350 U	0.00789 U	0.00371 U	0.00456 U	0.00140 U	0.00301 U
IW-58A (3.9 to-11.1)	IW-58A-38	10/17/18	PES	PACE	38	1.2	S	0.0139 U	0.00116 U	0.00661 U	0.000383 U	0.000943 U	0.0109 U	0.000322 U	0.00726 U	0.00341 U	0.00420 U	0.00129 U	0.00277 U
	B-929-38	10/17/18	PES	PACE	38 (dup)	1.2	S	0.0143 U	0.00119 U	0.00681 U	0.000394 U	0.000972 U	0.0113 U	0.000332 U	0.00748 U	0.00351 U	0.00432 U	0.00133 U	0.00285 U
MW101 (B101) (-65.5 to-75.5)	B101-30	7/10/12	SES	F&BI	30	9.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B101-34	7/10/12	SES	F&BI	34	5.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B101-40	7/10/12	SES	F&BI	40	-0.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B101-47	7/10/12	SES	F&BI	47	-7.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B101-48	7/10/12	SES	F&BI	48	-8.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B101-55	7/10/12	SES	F&BI	55	-15.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B101-65	7/10/12	SES	F&BI	65	-25.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B101-75	7/11/12	SES	F&BI	75	-35.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B101-81	7/11/12	SES	F&BI	81	-41.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B101-92	7/12/12	SES	F&BI	92	-52.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B101-97	7/12/12	SES	F&BI	97	-57.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B101-104	7/12/12	SES	F&BI	104	-64.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B101-114.5	7/12/12	SES	F&BI	114.5	-75.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B101-120	7/12/12	SES	F&BI	120	-80.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B101-131	7/12/12	SES	F&BI	131	-91.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B101-140	7/12/12	SES	F&BI	140	-100.5	S	–	–	–	–	–	–	–	–	–	–	–	–
MW130 (B130) (-30.9 to-40.9)	B130-10	3/1/16	SES	F&BI	10	29.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B130-20	3/1/16	SES	F&BI	20	19.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B130-30	3/1/16	SES	F&BI	30	9.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B130-40	3/1/16	SES	F&BI	40	-0.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B130-45	3/2/16	SES	F&BI	45	-5.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B130-50	3/2/16	SES	F&BI	50	-10.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B130-55	3/2/16	SES	F&BI	55	-15.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B130-60	3/2/16	SES	F&BI	60	-20.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B130-65	3/2/16	SES	F&BI	65	-25.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B130-70	3/2/16	SES	F&BI	70	-30.5	S	–	–	–	–	–	–	–	–	–	–	–	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
MW130 (B130)	B130-75	3/2/16	SES	F&BI	75	-35.5	S	–	–	–	–	–	–	–	–	–	–	–	–
(continued)	B130-80	3/2/16	SES	F&BI	80	-40.5	S	–	–	–	–	–	–	–	–	–	–	–	–
MW131 (B131)	B131-10	3/1/16	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–
(-4.2 to-14.2)	B131-20	3/1/16	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B131-30	3/1/16	SES	F&BI	30	10.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B131-40	3/1/16	SES	F&BI	40	0.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B131-45	3/2/16	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B131-55	3/2/16	SES	F&BI	55	-15.0	S	–	–	–	–	–	–	–	–	–	–	–	–
MW-132	MW-132-20	8/22/17	PES	ESC	20	20.1	S	0.000381 U	0.000323 U	0.00282 U	0.000277 U	0.000271 U	0.00210 U	0.000236 U	0.00112 U	0.00112 U	0.000288 U	0.000230 U	0.000224 U
(-29.9 to-39.9)	MW-132-35	8/22/17	PES	ESC	35	5.1	S	0.000383 U	0.000324 U	0.00283 U	0.000277 U	0.000272 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000289 U	0.000230 U	0.000225 U
	MW-132-50	8/22/17	PES	ESC	50	-9.9	S	0.000370 U	**0.00271 J**	0.00274 U	0.000268 U	0.000263 U	0.00203 U	0.000229 U	0.00108 U	0.00108 U	0.000279 U	0.000223 U	0.000217 U
	MW-132-55	8/23/17	PES	ESC	55	-14.9	S	0.0393 U	0.0333 U	0.291 U	0.0285 U	0.0279 U	0.216 U	**0.159**	0.115 U	0.115 U	0.0297 U	**0.0501 J**	0.0231 U
	MW-132-60	8/23/17	PES	ESC	60	-19.9	S	0.000368 U	**0.000678 J**	0.00272 U	0.000267 U	0.000262 U	0.00202 U	0.000228 U	0.00108 U	0.00108 U	0.000278 U	0.000222 U	0.000216 U
	MW-132-70	8/23/17	PES	ESC	70	-29.9	S	0.000417 U	**0.000499 J**	0.00308 U	0.000302 U	0.000296 U	0.00229 U	0.000258 U	0.00122 U	0.00122 U	0.000315 U	0.000251 U	0.000245 U
	MW-132-83	8/23/17	PES	ESC	83	-42.9	S	0.000373 U	0.000316 U	0.00276 U	0.000271 U	0.000265 U	0.00205 U	0.000231 U	0.00109 U	0.00109 U	0.000281 U	0.000225 U	0.000219 U
MW-133	MW-133-20	8/15/17	PES	ESC	20	20.1	S	0.000403 U	**0.00531 J**	0.00298 U	0.000292 U	0.000286 U	0.00222 U	0.000250 U	0.00118 U	0.00118 U	0.000304 U	0.000243 U	0.000237 U
(-88.9 to-98.9)	MW-133-35	8/15/17	PES	ESC	35	5.1	S	0.000447 U	0.000379 U	0.00330 U	0.000324 U	0.000317 U	0.00245 U	0.000277 U	0.00131 U	0.00131 U	0.000337 U	0.000269 U	0.000262 U
	MW-133-45	8/15/17	PES	ESC	45	-4.9	S	0.000372 U	**0.000378 J**	0.00275 U	0.000270 U	0.000264 U	0.00204 U	0.000230 U	0.00109 U	0.00109 U	0.000280 U	0.000224 U	0.000218 U
	MW-133-55	8/15/17	PES	ESC	55	-14.9	S	0.0837 U	0.0709 U	0.619 U	0.0607 U	0.0594 U	0.460 U	**0.0801 J**	0.245 U	0.245 U	0.0631 U	0.0504 U	0.0492 U
	MW-133-58	8/15/17	PES	ESC	58	-17.9	S	2.02 U	1.71 U	14.9 U	1.47 U	1.44 U	11.1 U	1.25 U	5.91 U	5.91 U	1.53 U	1.22 U	1.18 U
	MW-133-65	8/15/17	PES	ESC	65	-24.9	S	0.000396 U	**0.000897 J**	0.00293 U	0.000287 U	0.000281 U	0.00218 U	0.000245 U	0.00116 U	0.00116 U	0.000299 U	0.000238 U	0.000233 U
	MW-133-75	8/15/17	PES	ESC	75	-34.9	S	0.000398 U	0.000337 U	0.00294 U	0.000289 U	0.000283 U	0.00219 U	0.000247 U	0.00116 U	0.00116 U	0.000300 U	0.000240 U	0.000234 U
	MW-133-85	8/15/17	PES	ESC	85	-44.9	S	0.0100 U	0.00850 U	0.0741 U	0.00727 U	0.00713 U	0.0551 U	**0.0772**	0.0293 U	0.0293 U	0.00756 U	0.00604 U	0.00588 U
	MW-133-95	8/16/17	PES	ESC	95	-54.9	S	0.000398 U	0.000338 U	0.00295 U	0.000289 U	0.000283 U	0.00219 U	0.000247 U	0.00116 U	0.00116 U	0.000301 U	0.000240 U	0.000234 U
	MW-133-105	8/16/17	PES	ESC	105	-64.9	S	0.000412 U	0.000349 U	0.00305 U	0.000299 U	0.000293 U	0.00226 U	0.000255 U	0.00120 U	0.00120 U	0.000311 U	0.000248 U	0.000242 U
	MW-133-120	8/16/17	PES	ESC	120	-79.9	S	0.00929 U	0.00788 U	0.0687 U	0.00674 U	0.00661 U	0.0511 U	**0.0760**	0.0272 U	0.0272 U	0.00701 U	0.00560 U	0.00546 U
	MW-133-130	8/16/17	PES	ESC	130	-89.9	S	0.000407 U	**0.00262 J**	0.00301 U	0.000295 U	0.000289 U	0.00224 U	0.000253 U	0.00119 U	0.00119 U	0.000307 U	0.000245 U	0.000239 U
	MW-133-135	8/16/17	PES	ESC	135	-94.9	S	0.000387 U	**0.100**	0.00287 U	0.000281 U	0.000275 U	0.00213 U	0.000240 U	0.00113 U	0.00113 U	**0.000535 J**	**0.000915 J**	0.000228 U
	MW-133-141	8/16/17	PES	ESC	141	-100.9	S	0.000385 U	**0.0113**	0.00285 U	0.000279 U	0.000274 U	0.00212 U	0.000239 U	0.00113 U	0.00113 U	0.000291 U	0.000232 U	0.000226 U
MW-134	MW-134-20	8/29/17	PES	ESC	20	21.5	S	0.000450 U	0.000382 U	0.00333 U	0.000326 U	0.000320 U	0.00247 U	0.000279 U	0.00132 U	0.00132 U	0.000340 U	0.000271 U	0.000265 U
(-38.6 to-48.6)	MW-134-43	8/29/17	PES	ESC	43	-1.6	S	0.000397 U	**0.000648 J**	0.00294 U	0.00719 U	0.000282 U	0.00218 U	0.000246 U	0.00116 U	0.00116 U	0.000299 U	0.000239 U	0.000233 U
	MW-134-50	8/29/17	PES	ESC	50	-8.6	S	0.000376 U	0.000319 U	0.00278 U	0.0273 U	0.000267 U	0.00207 U	0.000233 U	0.00110 U	0.00110 U	0.000284 U	0.000226 U	0.000221 U
	MW-134-60	8/29/17	PES	ESC	60	-18.6	S	0.000378 U	**0.00136 J**	0.00279 U	0.00685 U	0.000268 U	0.00208 U	0.000234 U	0.00110 U	0.00110 U	0.000285 U	0.000227 U	0.000222 U
	MW-134-70	8/29/17	PES	ESC	70	-28.6	S	0.000436 U	**0.00178 J**	0.00323 U	0.000316 U	0.000310 U	0.00240 U	0.000270 U	0.00128 U	0.00128 U	0.000329 U	0.000263 U	0.000256 U
	MW-134-80	8/29/17	PES	ESC	80	-38.6	S	0.000366 U	**0.00184 J**	0.00271 U	0.000265 U	0.000260 U	0.00201 U	0.000227 U	0.00107 U	0.00107 U	0.000276 U	0.000220 U	0.000215 U
	B-903-100	8/29/17	PES	ESC	80 (dup)	-38.6	S	0.000360 U	**0.00103 J**	0.00267 U	0.000261 U	0.000256 U	0.00198 U	0.000223 U	0.00105 U	0.00105 U	0.000272 U	0.000217 U	0.000212 U
	MW-134-90	8/29/17	PES	ESC	90	-48.6	S	0.000434 U	**0.00494 J**	0.00321 U	0.00787 U	0.000309 U	0.00239 U	0.000269 U	0.00127 U	0.00127 U	0.000328 U	0.000262 U	0.000255 U
MW-135	MW-135-16	8/24/17	PES	ESC	14	25.1	S	0.0417 U	0.0354 U	0.309 U	0.0303 U	**0.0628 J**	0.229 U	0.0259 U	0.122 U	**0.543 J**	**0.339**	**0.170**	**0.167**
(-30.9 to-40.9)	MW-135-20	8/24/17	PES	ESC	20	19.1	S	0.00974 U	0.00826 U	0.0720 U	0.00706 U	0.00692 U	0.0535 U	0.00604 U	0.0285 U	0.0285 U	0.00735 U	0.00587 U	0.00572 U
	MW-135-30	8/24/17	PES	ESC	30	9.1	S	0.000363 U	0.000308 U	0.00269 U	0.000263 U	**0.000278 J**	0.00200 U	0.000225 U	0.00106 U	**0.00253 J**	**0.000805 J**	**0.000769 J**	**0.000496 J**
	MW-135-36	8/24/17	PES	ESC	36	3.1	S	0.000399 U	0.000339 U	0.00295 U	0.000290 U	0.000284 U	0.00219 U	0.000248 U	0.00117 U	0.00117 U	0.000301 U	0.000241 U	0.000235 U
	MW-135-40	8/24/17	PES	ESC	40	-0.9	S	0.000408 U	0.000346 U	0.00302 U	0.000296 U	0.000290 U	0.00224 U	0.000253 U	0.00119 U	0.00119 U	0.000308 U	0.000246 U	0.000240 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
MW-135 (continued)	MW-135-45	8/24/17	PES	ESC	45	-5.9	S	0.000406 U	0.000344 U	0.00300 U	0.000294 U	0.000289 U	0.00223 U	0.000252 U	0.00119 U	0.00119 U	0.000306 U	0.000245 U	0.000239 U
	MW-135-55	8/24/17	PES	ESC	55	-15.9	S	0.000372 U	**0.00123 J**	0.00275 U	0.000269 U	0.000264 U	0.00204 U	0.000230 U	0.00109 U	0.00109 U	0.000280 U	0.000224 U	0.000218 U
	MW-135-65	8/24/17	PES	ESC	65	-25.9	S	0.000406 U	0.000344 U	0.00300 U	0.000294 U	0.000288 U	0.00223 U	0.000252 U	0.00119 U	0.00119 U	0.000306 U	0.000244 U	0.000239 U
	MW-135-80	8/24/17	PES	ESC	80	-40.9	S	0.00955 U	0.000324 U	0.00283 U	0.000277 U	0.000271 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000288 U	0.000230 U	0.000224 U
MW-136 (-32.7 to-42.7)	MW-136-35	8/28/17	PES	ESC	35	16.9	S	0.000360 U	**0.00176 J**	0.00266 U	0.000261 U	0.000256 U	0.00198 U	0.000223 U	0.00105 U	0.00105 U	0.000272 U	0.000217 U	0.000212 U
	B-902-15	8/28/17	PES	ESC	35 (dup)	16.9	S	0.000374 U	**0.000689 J**	0.00276 U	0.000271 U	0.000265 U	0.00205 U	0.000232 U	0.00109 U	0.00109 U	0.000282 U	0.000225 U	0.000220 U
	MW-136-44	8/28/17	PES	ESC	44	7.9	S	0.000384 U	**0.000656 J**	0.00284 U	0.000278 U	0.000273 U	0.00211 U	0.000238 U	0.00112 U	0.00112 U	0.000290 U	0.000231 U	0.000226 U
	MW-136-50	8/28/17	PES	ESC	50	1.9	S	0.000394 U	**0.000453 J**	0.00291 U	0.00713 U	0.000280 U	0.00216 U	0.000244 U	0.00115 U	0.00115 U	0.000297 U	0.000237 U	0.000231 U
	MW-136-65	8/28/17	PES	ESC	65	-13.1	S	0.000372 U	**0.00387 J**	0.00275 U	0.000270 U	0.000264 U	0.00204 U	0.000231 U	0.00109 U	0.00109 U	0.000281 U	0.000224 U	0.000219 U
	MW-136-75	8/28/17	PES	ESC	75	-23.1	S	0.000380 U	0.000322 U	0.00281 U	0.000276 U	0.000270 U	0.00209 U	0.000236 U	0.00111 U	0.00111 U	0.000287 U	0.000229 U	0.000223 U
	MW-136-85	8/28/17	PES	ESC	85	-33.1	S	0.000382 U	0.000324 U	0.00282 U	0.000277 U	0.000271 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000288 U	0.000230 U	0.000224 U
	MW-136-95	8/28/17	PES	ESC	95	-43.1	S	0.000383 U	0.000325 U	0.00283 U	0.000278 U	0.000272 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000289 U	0.000231 U	0.000225 U
MW-137 (-53.3 to-63.3)	MW-137-25	8/31/17	PES	ESC	25	26.7	S	0.000373 U	**0.00162 J**	0.00276 U	0.000270 U	0.000265 U	0.00205 U	0.000231 U	0.00109 U	0.00109 U	0.000281 U	0.000225 U	0.000219 U
	MW-137-45	8/31/17	PES	ESC	45	6.7	S	0.00968 U	**0.0117 J**	0.0715 U	0.00702 U	0.00688 U	0.0532 U	0.00600 U	0.0283 U	0.0283 U	0.00730 U	0.00583 U	0.00568 U
	MW-137-75	8/31/17	PES	ESC	75	-23.3	S	0.000375 U	0.000318 U	0.00278 U	0.000272 U	0.000267 U	0.00206 U	0.000233 U	0.00110 U	0.00110 U	0.000283 U	0.000226 U	0.000221 U
	MW-137-85	9/1/17	PES	ESC	85	-33.3	S	0.000410 U	**0.00261 J**	0.00303 U	0.000297 U	0.000291 U	0.00225 U	0.000254 U	0.00120 U	0.00120 U	0.000309 U	0.000247 U	0.000241 U
	MW-137-95	9/1/17	PES	ESC	95	-43.3	S	0.000366 U	**0.00340 J**	0.00271 U	0.000266 U	0.000260 U	0.00201 U	0.000227 U	0.00107 U	0.00107 U	0.000276 U	0.000221 U	0.000215 U
	MW-137-115	9/1/17	PES	ESC	115	-63.3	S	0.000418 U	0.000355 U	0.00310 U	0.000303 U	0.000297 U	0.00230 U	0.000259 U	0.00122 U	0.00122 U	0.000316 U	0.000252 U	0.000246 U
MW-139 (-30.2 to-40.2)	MW-139-20	9/13/17	PES	ESC	20	19.8	S	0.000396 U	0.000335 U	0.00293 U	0.000287 U	0.000281 U	0.00217 U	0.000245 U	0.00116 U	0.00116 U	0.000298 U	0.000238 U	0.000233 U
	MW-139-31	9/13/17	PES	ESC	31	8.8	S	0.000366 U	0.000310 U	0.00271 U	0.000265 U	0.000260 U	0.00201 U	0.000227 U	0.00107 U	0.00107 U	0.000276 U	0.000220 U	0.000215 U
	MW-139-41	9/13/17	PES	ESC	41	-1.2	S	0.000367 U	**0.00158 J**	0.00272 U	0.000266 U	0.000261 U	0.00202 U	0.000228 U	0.00107 U	0.00107 U	0.000277 U	0.000221 U	0.000216 U
	MW-139-51	9/13/17	PES	ESC	51	-11.2	S	0.000395 U	**0.000675 J**	0.00292 U	0.000286 U	0.000280 U	0.00217 U	0.000245 U	0.00115 U	0.00115 U	0.000298 U	0.000238 U	0.000232 U
	MW-139-60	9/13/17	PES	ESC	60	-20.2	S	0.000367 U	0.000311 U	0.00272 U	0.000266 U	0.000261 U	0.00202 U	0.000228 U	0.00107 U	0.00107 U	0.000277 U	0.000221 U	0.000216 U
	MW-139-70	9/13/17	PES	ESC	70	-30.2	S	0.000404 U	0.000342 U	0.00299 U	0.000293 U	0.000287 U	0.00222 U	0.000250 U	0.00118 U	0.00118 U	0.000304 U	0.000243 U	0.000237 U
	MW-139-80	9/13/17	PES	ESC	80	-40.2	S	0.000386 U	0.000328 U	0.00286 U	0.000280 U	0.000275 U	0.00212 U	0.000240 U	0.00113 U	0.00113 U	0.000292 U	0.000233 U	0.000227 U
MW-141 (-55.4 to-65.4)	MW-141-15	9/18/17	PES	ESC	15	24.6	S	0.000386 U	0.000327 U	0.00285 U	0.000280 U	0.000274 U	0.00212 U	0.000239 U	0.00113 U	0.00113 U	0.000291 U	0.000232 U	0.000227 U
	MW-141-35	9/18/17	PES	ESC	35	4.6	S	0.000397 U	**0.000542 J**	0.00294 U	0.000288 U	0.000282 U	0.00218 U	0.000246 U	0.00116 U	0.00116 U	0.000299 U	0.000239 U	0.000233 U
	MW-141-46	9/18/17	PES	ESC	46	-6.4	S	0.000374 U	**0.00427 J**	0.00277 U	0.000271 U	0.000266 U	0.00206 U	0.000232 U	0.00109 U	0.00109 U	0.000282 U	0.000225 U	0.000220 U
	MW-141-56	9/18/17	PES	ESC	56	-16.4	S	0.000364 U	**0.00226 J**	0.00269 U	0.000264 U	0.000258 U	0.00200 U	0.000226 U	0.00106 U	0.00106 U	0.000274 U	0.000219 U	0.000214 U
	MW-141-65	9/18/17	PES	ESC	65	-25.4	S	0.000360 U	**0.00497 J**	0.00266 U	0.000261 U	0.000256 U	0.00198 U	0.000223 U	0.00105 U	0.00105 U	0.000271 U	0.000217 U	0.000211 U
	MW-141-75	9/18/17	PES	ESC	75	-35.4	S	0.000365 U	**0.00845 J**	0.00270 U	0.000264 U	0.000259 U	0.00200 U	0.000226 U	0.00107 U	0.00107 U	0.000275 U	0.000220 U	0.000214 U
	MW-141-85	9/18/17	PES	ESC	85	-45.4	S	0.000399 U	**0.000898 J**	0.00295 U	0.000290 U	0.000284 U	0.00220 U	0.000248 U	0.00117 U	0.00117 U	0.000301 U	0.000241 U	0.000235 U
	MW-141-95	9/18/17	PES	ESC	95	-55.4	S	0.000410 U	0.000347 U	0.00303 U	0.000297 U	0.000291 U	0.00225 U	0.000254 U	0.00120 U	0.00120 U	0.000309 U	0.000247 U	0.000241 U
	MW-141-105	9/19/17	PES	ESC	105	-65.4	S	0.000408 U	0.000346 U	0.00302 U	0.000296 U	0.000290 U	0.00224 U	0.000253 U	0.00119 U	0.00119 U	0.000308 U	0.000246 U	0.000240 U
MW-152 (-10.2 to-20.2)	MW-152-5	3/13/18	PES	ESC	5	34.1	S	0.000385 U	0.000327 U	0.00285 U	0.000279 U	0.000274 U	0.00212 U	0.000239 U	0.00113 U	0.00113 U	0.000291 U	0.000232 U	0.000226 U
	MW-152-15	3/13/18	PES	ESC	15	24.1	S	0.000379 U	0.000321 U	0.00280 U	0.000275 U	0.000269 U	0.00208 U	0.000235 U	0.00111 U	0.00111 U	0.000286 U	0.000228 U	0.000223 U
	MW-152-25	3/13/18	PES	ESC	25	14.1	S	0.000371 U	0.000315 U	0.00274 U	0.000269 U	0.000264 U	0.00204 U	0.000230 U	0.00108 U	0.00108 U	0.000280 U	0.000223 U	0.000218 U
	MW-152-35	3/13/18	PES	ESC	35	4.1	S	0.000375 U	0.000318 U	0.00277 U	0.000272 U	0.000266 U	0.00206 U	0.000232 U	0.00110 U	0.00110 U	0.000283 U	0.000226 U	0.000220 U
	MW-152-45	3/13/18	PES	ESC	45	-5.9	S	0.000386 U	**0.000925 J**	0.00285 U	0.000280 U	0.000274 U	0.00212 U	0.000239 U	0.00113 U	0.00113 U	**0.000435 J**	**0.000851 J**	**0.000397 J**
	MW-152-55	3/13/18	PES	ESC	55	-15.9	S	0.000387 U	0.000328 U	0.00287 U	0.000281 U	0.000275 U	0.00213 U	0.000240 U	0.00113 U	0.00113 U	0.000292 U	0.000233 U	0.000228 U
	MW-152-60	3/13/18	PES	ESC	60	-20.9	S	0.000370 U	**0.0102 J**	0.00274 U	0.000268 U	0.000263 U	0.00203 U	0.000229 U	0.00108 U	0.00108 U	0.000279 U	0.000223 U	0.000217 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
MW-162	MW-162-48	1/28/19	PES	PACE	48	-9.6	S	0.275 U	0.0229 U	0.131 U	0.00757 U	0.0187 U	0.216 U	0.00638 U	0.144 U	0.0675 U	0.0831 U	0.0255 U	0.0547 U
(-61.6 to-71.6)	MW-162-50	1/28/19	PES	PACE	50	-11.6	S	0.0148 U	0.00124 U	0.00707 U	0.000409 U	0.00101 U	0.0117 U	0.000345 U	0.00776 U	0.00364 U	0.00449 U	0.00138 U	0.00296 U
	B-930-50 (dup)	1/28/19	PES	PACE	50	-11.6	S	0.0141 U	0.00118 U	0.00673 U	0.000389 U	0.000959 U	0.0111 U	0.000328 U	0.00738 U	0.00347 U	0.00427 U	0.00131 U	0.00281 U
	MW-162-67	1/28/19	PES	PACE	67	-28.6	S	0.0148 U	0.00123 U	0.00703 U	0.000407 U	0.00100 U	0.0116 U	0.000343 U	0.00771 U	0.00362 U	0.00446 U	0.00137 U	0.00294 U
	MW-162-70	1/28/19	PES	PACE	70	-31.6	S	0.0142 U	0.00118 U	0.00675 U	0.000391 U	0.000963 U	0.0112 U	0.000329 U	0.00741 U	0.00348 U	0.00429 U	0.00132 U	0.00282 U
	MW-162-72	1/28/19	PES	PACE	72	-33.6	S	0.0137 U	0.00114 U	0.00653 U	0.000378 U	0.000931 U	0.0108 U	0.000318 U	0.00716 U	0.00337 U	0.00414 U	0.00127 U	0.00273 U
	MW-162-80	1/28/19	PES	PACE	80	-41.6	S	0.0141 U	0.00118 U	0.00673 U	0.000390 U	0.000960 U	0.0111 U	0.000328 U	0.00739 U	0.00347 U	0.00427 U	0.00131 U	0.00282 U
	MW-162-85	1/28/19	PES	PACE	85	-46.6	S	0.0144 U	0.00120 U	0.00685 U	0.000396 U	0.000977 U	0.0113 U	0.000334 U	0.00752 U	0.00353 U	0.00435 U	0.00134 U	0.00286 U
	MW-162-90	1/28/19	PES	PACE	90	-51.6	S	0.0144 U	0.00120 U	0.00684 U	0.000396 U	0.000975 U	0.0113 U	0.000333 U	0.00750 U	0.00353 U	0.00434 U	0.00133 U	0.00286 U
	MW-162-95	1/28/19	PES	PACE	95	-56.6	S	0.0146 U	0.00122 U	0.00694 U	0.000402 U	0.000990 U	0.0115 U	0.000338 U	**0.00870 J**	0.00358 U	0.00441 U	0.00135 U	0.00290 U
	MW-162-100	1/28/19	PES	PACE	100	-61.6	S	0.0148 U	0.00124 U	0.00706 U	0.000409 U	0.00101 U	0.0117 U	0.000344 U	0.00775 U	0.00364 U	0.00448 U	0.00138 U	0.00295 U
	MW-162-105	1/28/19	PES	PACE	105	-66.6	S	0.0143 U	0.00119 U	0.00680 U	0.000393 U	0.000970 U	0.0112 U	0.000332 U	0.00746 U	0.00351 U	0.00432 U	0.00133 U	0.00284 U
	MW-162-110	1/28/19	PES	PACE	110	-71.6	S	0.0139 U	0.00116 U	0.00662 U	0.000383 U	0.000945 U	0.0109 U	0.000323 U	0.00727 U	0.00341 U	0.00420 U	0.00129 U	0.00277 U
MW-163	MW-163-47	1/29/19	PES	PACE	47	-7.7	S	0.0142 U	0.00119 U	0.00677 U	0.000391 U	0.000965 U	0.0112 U	0.000330 U	0.00743 U	0.00349 U	0.00429 U	0.00132 U	0.00283 U
(-61.0 to-71.0)	MW-163-50	1/29/19	PES	PACE	50	-10.7	S	0.0137 U	0.00115 U	0.00654 U	0.000378 U	0.000932 U	0.0108 U	0.000319 U	0.00717 U	0.00337 U	0.00415 U	0.00127 U	0.00273 U
	MW-163-55	1/29/19	PES	PACE	55	-15.7	S	0.0155 U	0.00130 U	0.00742 U	0.000429 U	0.00106 U	0.0123 U	0.000361 U	0.00814 U	0.00382 U	0.00471 U	0.00144 U	0.00310 U
	MW-163-60	1/29/19	PES	PACE	60	-20.7	S	0.0144 U	0.00120 U	0.00685 U	0.000396 U	0.000977 U	0.0113 U	0.000334 U	0.00752 U	0.00353 U	0.00435 U	0.00134 U	0.00286 U
	MW-163-80	1/29/19	PES	PACE	80	-40.7	S	0.0144 U	0.00121 U	0.00688 U	0.000398 U	0.000981 U	0.0114 U	0.000335 U	0.00755 U	0.00355 U	0.00437 U	0.00134 U	0.00288 U
	MW-163-85	1/29/19	PES	PACE	85	-45.7	S	0.0150 U	0.00125 U	0.00716 U	0.000414 U	0.00102 U	0.0118 U	0.000349 U	0.00786 U	0.00369 U	0.00454 U	0.00140 U	0.00299 U
	MW-163-90	1/29/19	PES	PACE	90	-50.7	S	0.0138 U	0.00115 U	0.00656 U	0.000380 U	0.000936 U	0.0108 U	0.000320 U	0.00720 U	0.00338 U	0.00416 U	0.00128 U	0.00274 U
	MW-163-95	1/29/19	PES	PACE	95	-55.7	S	0.0151 U	0.00126 U	0.00717 U	0.000415 U	0.00102 U	0.0119 U	0.000350 U	0.00787 U	0.00370 U	0.00455 U	0.00140 U	0.00300 U
	MW-163-100	1/29/19	PES	PACE	100	-60.7	S	0.0146 U	0.00122 U	0.00695 U	0.000402 U	0.000991 U	0.0115 U	0.000339 U	0.00763 U	0.00358 U	0.00441 U	0.00136 U	0.00291 U
	MW-163-105	1/29/19	PES	PACE	105	-65.7	S	0.0133 U	0.00111 U	0.00635 U	0.000367 U	0.000906 U	0.0105 U	0.000310 U	0.00697 U	0.00328 U	0.00403 U	0.00124 U	0.00266 U
	MW-163-110	1/29/19	PES	PACE	110	-70.7	S	0.0141 U	0.00117 U	0.00670 U	0.000388 U	0.000956 U	0.0111 U	0.000327 U	0.00736 U	0.00346 U	0.00425 U	0.00131 U	0.00280 U
MW-164	MW-164-80	1/24/19	PES	PACE	80	-40.3	S	0.0145 U	0.00121 U	0.00689 U	0.000399 U	0.000983 U	0.0114 U	0.000336 U	0.00756 U	0.00355 U	0.00437 U	0.00134 U	0.00288 U
(-59.9 to-69.9)	MW-164-87	1/24/19	PES	PACE	87	-47.3	S	0.0142 U	0.00119 U	0.00677 U	0.000392 U	0.000966 U	0.0112 U	0.000330 U	0.00743 U	0.00349 U	0.00430 U	0.00132 U	0.00283 U
	MW-164-90	1/24/19	PES	PACE	90	-50.3	S	0.0149 U	0.00124 U	0.00709 U	0.000410 U	0.00101 U	0.0117 U	0.000346 U	0.00778 U	0.00365 U	0.00450 U	0.00138 U	0.00296 U
	MW-164-95	1/25/19	PES	PACE	95	-55.3	S	0.0152 U	0.00127 U	0.00723 U	0.000419 U	0.00103 U	0.0120 U	0.000353 U	0.00794 U	0.00373 U	0.00459 U	0.00141 U	0.00303 U
	MW-164-100	1/25/19	PES	PACE	100	-60.3	S	0.0159 U	0.00133 U	0.00756 U	0.000438 U	0.00108 U	0.0125 U	0.000369 U	0.00830 U	0.00390 U	0.00480 U	0.00148 U	0.00316 U
	MW-164-105	1/25/19	PES	PACE	105	-65.3	S	0.0141 U	0.00118 U	0.00671 U	0.000388 U	0.000957 U	0.0111 U	0.000327 U	0.00736 U	0.00346 U	0.00426 U	0.00131 U	0.00281 U
	MW-164-110	1/25/19	PES	PACE	110	-70.3	S	0.0140 U	0.00117 U	0.00667 U	0.000386 U	0.000952 U	0.0110 U	0.000325 U	0.00732 U	0.00344 U	0.00423 U	0.00130 U	0.00279 U
	B-929-120	1/25/19	PES	PACE	110 (dup)	-70.3	S	0.0143 U	0.00119 U	0.00680 U	0.000393 U	0.000970 U	0.0112 U	0.000331 U	0.00746 U	0.00351 U	0.00431 U	0.00133 U	0.00284 U
MW-168	MW-168-15	10/21/19	PES	Fremont	15	-3.8	S	–	–	–	–	–	–	–	–	–	–	–	–
(-43.0 to -53.0)																			
MW-171	MW-171-24	09/24/19	PES	Fremont	24	-12.8	S	–	–	–	–	–	–	–	–	–	–	–	–
(-27.6 to -37.6)																			
MW-172	MW-172-7	09/26/19	PES	Fremont	7	4.2	S	–	–	–	–	–	–	–	–	–	–	–	–
(-42.5 to -52.5)																			
MW-175	MW-175-12	10/26/19	PES	Fremont	12	-1.3	S	–	–	–	–	–	–	–	–	–	–	–	–
(-27.8 to -37.8)	B-1002-12	10/26/19	PES	Fremont	12 (dup)	-1.3	S	–	–	–	–	–	–	–	–	–	–	–	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
MW-180	MW-180-40	09/25/19	PES	Fremont	40	-28.2	S	–	–	–	–	–	–	–	–	–	–	–	–
(-42.7 to -52.7)	MW-180-24	09/25/19	PES	Fremont	24	-12.2	S	–	–	–	–	–	–	–	–	–	–	–	–
	MW-180-27	09/25/19	PES	Fremont	27	-15.2	S	–	–	–	–	–	–	–	–	–	–	–	–
MW-181 (1.5 to -8.5)	MW-181-14	09/27/19	PES	Fremont	14	-2.5	S	–	–	–	–	–	–	–	–	–	–	–	–
MW-183 (-27.4 to -37.4)	MW-183-18	09/26/19	PES	Fremont	18	-6.5	S	–	–	–	–	–	–	–	–	–	–	–	–
MW-184 (-42.5 to -52.5)	MW-184-20	09/26/19	PES	Fremont	20	-8.4	S	–	–	–	–	–	–	–	–	–	–	–	–
MW-188 (-42.2 to -52.2)	MW-188-64	10/01/19	PES	Fremont	64	-52.4	S	–	–	–	–	–	–	–	–	–	–	–	–
P01	P01-05	2/12/14	SES	F&BI	5	35.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	P01-10	2/12/14	SES	F&BI	10	30.5	S	–	–	–	–	–	–	–	–	–	–	–	–
P02	P02-05	2/12/14	SES	F&BI	5	34.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	P02-07.5	2/12/14	SES	F&BI	7.5	32.0	S	–	–	–	–	–	–	–	–	–	–	–	–
P03	P03-05	2/12/14	SES	F&BI	5	34.5	S	–	–	–	–	–	–	–	–	–	–	–	–
P03	P03-07.5	2/12/14	SES	F&BI	7.5	32.0	S	–	–	–	–	–	–	–	–	–	–	–	–
P04	P04-05	2/12/14	SES	F&BI	7.5	32.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	P04-10	2/12/14	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–
P05	P05-05	2/12/14	SES	F&BI	5	35.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	P05-07.5	2/12/14	SES	F&BI	7.5	32.5	S	–	–	–	–	–	–	–	–	–	–	–	–
P06	P06-07.5	2/12/14	SES	F&BI	7.5	32.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	P06-10	2/12/14	SES	F&BI	10	30.0	S	–	–	–	–	–	–	–	–	–	–	–	–
R-MW1	Unknown	10/22/92	Roux	Unknown	5	32.8	S	–	–	–	–	–	–	–	–	–	–	–	–
W-MW-03	SB-W-07-0135	1/26/12	WW	ARI	13.5-14	25.2	S	–	–	–	–	–	–	–	–	–	–	–	–
(P-07)	SB-W-07-0275	1/26/12	WW	ARI	27.5-28	11.2	S	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-07-0335	1/26/12	WW	ARI	33.5-34	5.2	S	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-07-0430	1/26/12	WW	ARI	43-43.5	-4.3	S	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-07-0530	1/26/12	WW	ARI	53-53.5	-14.3	S	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-07-0630	1/26/12	WW	ARI	63-63.5	-24.3	S	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-07-0780	1/26/12	WW	ARI	78-78.5	-39.3	S	–	–	–	–	–	–	–	–	–	–	–	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
W-MW-04 (P-08)	SB-W-08-0090	1/28/12	WW	ARI	9-9.5	26.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-08-0155	1/28/12	WW	ARI	15.5-16	19.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-08-0265	1/28/12	WW	ARI	26.5-27	8.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-08-0380	1/28/12	WW	ARI	38-38.5	-3.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-08-0480	1/28/12	WW	ARI	48-48.5	-13.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-08-9480	1/28/12	WW	ARI	48-48.5 (dup)	-13.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-08-0590	1/28/12	WW	ARI	59-59.5	-24.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-08-0710	1/29/12	WW	ARI	71-71.5	-36.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-08-0760	1/29/12	WW	ARI	76-76.5	-41.0	S	–	–	–	–	–	–	–	–	–	–	–	–
All Data							Number of Analytes Measured	805	805	805	805	805	805	805	805	805	805	805	805
							Number of Analytes Detected	0	220	0	0	15	2	30	13	17	18	28	16
							Frequency of Detection	0.0%	27.3%	0.0%	0.0%	1.9%	0.2%	3.7%	1.6%	2.1%	2.2%	3.5%	2.0%
							Maximum Detection	–	0.11	–	–	0.851	0.00621 J	0.554 J	0.0112	5.21	0.973	2.84	0.642
							Minimum Detection	0.000342 U	0.00029 U	0.00235 U	0.000248 U	0.000243 U	0.00188 U	0.000212 U	0.001 U	0.001 U	0.000258 U	0.000206 U	0.000201 U
							Number Of Vadose (V) Detections above SL	0	0	–	–	0	0	0	0	0	0	0	0
							Number of Saturated (S) Detections above SL	0	0	–	–	1	0	14	0	3	1	1	0
2017-2021							Number of Analytes Measured	805	805	805	805	805	805	805	805	805	805	805	805
							Number of Analytes Detected	0	220	0	0	15	2	30	13	17	18	28	16
							Frequency of Detection	0.0%	27.3%	0.0%	0.0%	1.9%	0.2%	3.7%	1.6%	2.1%	2.2%	3.5%	2.0%
							Maximum Detection	–	0.11	–	–	0.851	0.00621 J	0.554 J	0.0112	5.21	0.973	2.84	0.642
							Minimum Detection	0.000342 U	0.00029 U	0.00235 U	0.000248 U	0.000243 U	0.00188 U	0.000212 U	0.001 U	0.001 U	0.000258 U	0.000206 U	0.000201 U
							Number Of Vadose (V) Detections above SL	0	0	–	–	0	0	0	0	0	0	0	0
							Number of Saturated (S) Detections above SL	0	0	–	–	1	0	14	0	3	1	1	0

Abbreviations:
AAL = Alden Analytical Laboratories, Inc., of Seattle, Washington
ARI = Analytical Resource, Incorporated, Seattle, Washington
B&V = Black Veatch
bgs = below ground surface
Comp = Composite Sample
dup = duplicate
EPJ = E.PJohnson Construction Inc., and Environmental
ESC = ESC Lab Services of Mt. Juliet, Tennessee
F&BI = Friedman & Bruya, Inc.
GeoEng = GeoEngineers, Inc.
HC = Hart Crowser, Inc.
NCA = North Creek Analytical, of Bothell, Washington
OnSite = OnSite Environmental Inc., of Redmond, Washington
Pace = Pace Analytical of Mt. Juliet, Tennessee (formerly ESC)
PES = PES Environmental, Inc.
Retec = Remediation Technologies, Inc.
Roux = Roux Associates
SES = SoundEarth Strategies, Inc.
TR = TR Corporation
Urban = Urban Redevelopment LLC
WW = WW Environmental LLC

Notes:
All on-Property soil was excavated during Property redevelopment above elevations 0.7 to 10.7 feet, and CVOCs in soil between elevations +10 to 55 feet was treated.
Petroleum Hydrocarbons (PHCs) analyzed by Ecology Methods NWTPH-HCID, NWTPH-Gx, or NWTPH-Dx; or EPA Method 418.1, Method 8020, or Method 8015M.
VOCs analyzed by EPA Methods 8010, 8020, 8021B, 624/8240, or 8260B/C/D.
Well screen elevations provided below Sample Location. in parentheses when appliable.
PCUL = Preliminary Cleanup Level from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021. PCULs based on the practical quantitation limits (PQLs) italicized.
Detected results shown in **bold**.
Detections above the screening level in the vadose zone are shown in **bold and highlighted blue**.
Detections above the screening level in the saturated zone are shown in **bold and highlighted gray.**
– = Not available or results not analyzed.
A = Result reported as total petroleum hydrocarbons.
B = Analyte detected in an associated method blank.
J = The reported concentration is an estimate based on detectable results between the method detection limit and reporting limit, laboratory QA/QC, or data validation review.
J+ = The result is an estimated quantity, but the result may be biased high.
J- = The result is an estimated quantity, but the result may be biased low.
ND = Not detected above laboratory reporting limit. Reporting limit not available.
q = Sample may contain gasoline or petroleum components. Chromatographic pattern indicates the presence of gasoline constituents.
R = The data is unusable. The sample result is rejected due to serious deficiencies in meeting QC criteria. The analyte may or may not be present in the sample
T = Analyte also detected in trip blank.
U = Not detected at a concentration exceeding laboratory reporting limit
ve = Estimated value. The reported range exceeds the calibration range of the analysis.
w = Petroleum product eluting in the C8-C9 range
x = The sample chromatographic pattern does not resemble the fuel standard used for quantitation.
z = Gasoline/petroleum detection result is likely elevated due to high detections of CVOCs.

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene ((tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
B-1	B-1-13	6/23/00	TR	ARI	13	27.0	S	–	–	0.0012 U	0.0012 U	0.0012 U	–	–	0.0012 U	–	–	0.0012 U	0.0024 U
B-2	B-2-6.5	6/23/00	TR	ARI	6.5	33.5	S	–	–	**0.017**	0.0011 U	0.0011 U	–	–	**0.0020**	–	–	0.0011 U	0.0022 U
	B-2-11	6/23/00	TR	ARI	11	29.0	S	–	–	**0.92**	0.0012 U	**0.0037**	–	–	**0.085**	–	–	0.0012 U	0.0024 U
	B-2-16	6/23/00	TR	ARI	16	24.0	S	–	–	**0.049**	0.0011 U	0.0011 U	–	–	**0.0011**	–	–	0.0011 U	0.0022 U
B-3	B-3-12	6/23/00	TR	ARI	12	28.0	S	–	–	0.0013 U	0.0013 U	0.0013 U	–	–	0.0013 U	–	–	0.0013 U	0.0026 U
B-5	B-5-10	6/23/00	TR	ARI	10	30.0	S	–	–	**0.0051**	0.0011 U	0.0011 U	–	–	0.0011 U	–	–	0.0011 U	0.0022 U
	B-5-11.5	6/23/00	TR	ARI	11.5	28.5	S	–	–	**0.12**	0.0012 U	0.0012 U	–	–	**0.0088**	–	–	0.0012 U	0.0024 U
B-6	B-6-6	6/24/00	TR	ARI	6	34.0	S	–	–	**0.0085**	–	0.0012 U	–	–	**0.0014**	–	–	0.0012 U	–
	B-6-12	6/24/00	TR	ARI	12	28.0	S	–	–	**0.0067**	–	0.0012 U	–	–	**0.0026**	–	–	0.0012 U	–
	B-6-18	6/24/00	TR	ARI	18	22.0	S	–	–	**2.3**	–	0.0013 U	–	–	**0.0078**	–	–	0.0013 U	–
B-7	B-7-6	6/24/00	TR	ARI	6	34.0	S	–	–	**0.031**	–	0.0012 U	–	–	**0.0029**	–	–	0.0012 U	–
B-8	B-8-4	6/24/00	TR	ARI	4	36.0	S	–	–	**0.092**	–	0.0011 U	–	–	**0.0006**	–	–	0.0011 U	–
	B-8-8	6/24/00	TR	ARI	8	32.0	S	–	–	**1.4**	–	0.0011 U	–	–	**0.017**	–	–	0.0011 U	–
B-9	B-9-4	6/24/00	TR	ARI	4	36.0	S	–	–	**170**	–	1.6 U	–	–	1.6 U	–	–	1.6 U	–
	B-9-8	6/24/00	TR	ARI	8	32.0	S	–	–	**4.8**	–	**0.0022**	–	–	**0.13**	–	–	0.0012 U	–
B-10	B-10-12	6/24/00	TR	ARI	12	28.0	S	–	–	**0.017**	–	0.0011 U	–	–	**0.0014**	–	–	0.0011 U	–
B-201	G-201-10	6/19/17	PES	ESC	10	29.8	S	–	–	**0.0679**	0.00601 U	0.00120 U	–	–	**0.00638**	–	–	0.00120 U	0.00361 U
	G-201-30	6/19/17	PES	ESC	30	9.8	S	–	–	**0.00264**	0.00567 U	**0.00761**	–	–	0.00113 U	–	–	0.00113 U	0.00340 U
	G-201-35	6/19/17	PES	ESC	35	4.8	S	–	–	**0.00471**	0.00580 U	**0.00200**	–	–	**0.00134**	–	–	0.00116 U	0.00348 U
B-202	G-202-5	6/19/17	PES	ESC	5	34.2	S	–	–	**0.108**	0.00595 U	0.00119 U	–	–	**0.00580**	–	–	0.00119 U	0.00357 U
	G-202-20	6/19/17	PES	ESC	20	19.2	S	–	–	**0.0632**	0.00594 U	0.00119 U	–	–	**0.00503**	–	–	0.00119 U	0.00356 U
	G-202-50	6/19/17	PES	ESC	50	-10.8	S	–	–	**0.00163**	0.00662 U	0.00132 U	–	–	0.00132 U	–	–	0.00132 U	0.00397 U
B-203	G-203-5	6/20/17	PES	ESC	5	34.2	S	–	–	0.00115 U	**0.0272**	0.00115 U	–	–	0.00115 U	–	–	0.00115 U	**0.0494**
	G-203-25	6/20/17	PES	ESC	25	14.2	S	–	–	**0.00241**	0.00586 U	0.00117 U	–	–	0.00117 U	–	–	0.00117 U	0.00351 U
	G-203-40	6/20/17	PES	ESC	40	-0.8	S	–	–	**0.910**	0.00561 U	**0.00197**	–	–	**0.0674**	–	–	**0.0438**	**0.00719**
	G-203-50	6/20/17	PES	ESC	50	-10.8	S	–	–	**0.903**	0.00560 U	0.00112 U	–	–	**0.0481**	–	–	**0.00337**	0.00336 U
	G-203-80	6/20/17	PES	ESC	80	-40.8	S	–	–	0.00110 U	0.00548 U	0.00110 U	–	–	0.00110 U	–	–	0.00110 U	0.00329 U
B-204	G-204-20	6/20/17	PES	ESC	20	19.8	S	–	–	0.00116 U	0.00579 U	0.00116 U	–	–	0.00116 U	–	–	0.00116 U	0.00347 U
	G-204-40	6/20/17	PES	ESC	40	-0.2	S	–	–	**0.0318**	0.00563 U	**0.00485**	–	–	**0.00545**	–	–	**0.981**	0.00338 U
	G-204-45	6/20/17	PES	ESC	45	-5.2	S	–	–	**0.0315**	0.00606 U	**0.00714**	–	–	**0.0101**	–	–	**2.94**	0.00364 U
B-205	B-205-10	8/30/17	PES	ESC	10	30.3	S	0.0282 U	0.0248 U	0.0333 U	**0.372 J**	0.0318 U	0.0322 U	0.0938 U	0.0336 U	0.0461 U	0.288 U	0.0351 U	**6.02**
	B-205-55	8/30/17	PES	ESC	55	-14.7	S	0.000273 U	0.000241 U	**0.0625**	0.000507 U	0.000308 U	0.000312 U	0.000909 U	**0.00923**	0.000446 U	0.00279 U	**0.00562**	0.000815 U
	B-205-65	8/30/17	PES	ESC	65	-24.7	S	0.000248 U	0.000218 U	**0.0296**	0.000460 U	0.000280 U	0.000283 U	0.000824 U	**0.00582**	0.000405 U	0.00253 U	**0.000378 J**	0.000739 U
	B-205-75	8/30/17	PES	ESC	75	-34.7	S	0.000251 U	0.000221 U	**0.00308 J**	0.000465 U	0.000283 U	0.000286 U	0.000833 U	**0.000399 J**	0.000409 U	0.00256 U	0.000312 U	0.000748 U
	B-904-50	8/30/17	PES	ESC	75 (dup)	-34.7	S	0.000251 U	0.000221 U	**0.00954 J**	0.000466 U	0.000283 U	0.000286 U	0.000835 U	**0.00234**	0.000410 U	0.00256 U	0.000312 U	0.000749 U
B-206	B-206-15	8/14/17	PES	ESC	15	24.1	S	0.00673 U	0.00593 U	**0.0715**	0.0124 U	**0.00825 J**	0.00769 U	0.0223 U	**0.00831 J**	0.0110 U	0.0688 U	0.00838 U	0.0200 U
	B-206-30	8/14/17	PES	ESC	30	9.1	S	0.000268 U	0.000236 U	**0.0522**	0.000498 U	**0.00230**	0.000306 U	0.000892 U	**0.0289**	0.000438 U	0.00274 U	**0.124**	0.000801 U
	B-206-40	8/14/17	PES	ESC	40	-0.9	S	0.000247 U	0.000218 U	**0.000306 J**	0.000459 U	0.000279 U	0.000282 U	0.000822 U	0.000295 U	0.000404 U	0.00253 U	0.000308 U	0.000738 U
	B-206-49	8/14/17	PES	ESC	49	-9.9	S	0.000267 U	0.000235 U	**17.2**	0.000494 U	**0.0132**	0.000304 U	0.000886 U	**2.28**	0.000435 U	0.00272 U	**0.154**	0.000795 U
	B-206-52	8/14/17	PES	ESC	52	-12.9	S	0.000256 U	0.000225 U	**0.0483**	0.000474 U	0.000288 U	0.000292 U	0.000849 U	**0.00790 J**	0.000417 U	0.00261 U	**0.000383 J**	0.000762 U
	B-206-56	8/14/17	PES	ESC	56	-16.9	S	0.000257 U	0.000226 U	**9.95 J**	0.000477 U	0.000290 U	0.000293 U	0.000855 U	**2.16**	0.000420 U	0.00263 U	**0.000558 J**	0.000767 U
	B-206-59	8/14/17	PES	ESC	59	-19.9	S	0.000243 U	0.000214 U	**0.00866 J**	0.000451 U	0.000275 U	0.000278 U	0.000809 U	**0.00248**	0.000397 U	0.00249 U	**0.000368 J**	0.000726 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
B-206	B-206-70	8/14/17	PES	ESC	70	-30.9	S	0.000255 U	0.000224 U	0.000301 UJ	0.000473 U	0.000288 U	0.000291 U	0.000848 U	0.000304 U	0.000416 U	0.00260 U	0.000317 U	0.000760 U
(continued)	B-206-80	8/14/17	PES	ESC	80	-40.9	S	0.000255 U	0.000225 U	**0.00283 J**	0.000473 U	0.000288 U	0.000291 U	0.000848 U	0.000304 U	0.000416 U	0.00261 U	**0.000386 J**	0.000761 U
B-207	B-207-30	8/25/17	PES	ESC	30	8.5	S	0.00665 U	0.00585 U	**0.109**	0.0123 U	0.00750 U	0.00759 U	0.0220 U	**0.0373**	0.0109 U	0.0679 U	0.00827 U	0.0198 U
	B-207-41	8/25/17	PES	ESC	41	-2.5	S	0.000265 U	0.000233 U	**0.00152**	0.000491 U	**0.0224**	0.000302 U	0.000881 U	0.000316 U	0.000433 U	0.00271 U	**0.428**	0.000790 U
	B-207-49	8/25/17	PES	ESC	49	-10.5	S	0.000261 U	0.000230 U	**0.0325**	0.000484 U	**0.00359**	0.000298 U	0.000868 U	**0.00590**	0.000426 U	0.00267 U	**0.0261**	0.000779 U
	B-207-55	8/25/17	PES	ESC	55	-16.5	S	0.000273 U	0.000241 U	**0.0859**	0.000507 U	**0.0212**	0.000312 U	0.000908 U	**0.871**	0.000446 U	0.00279 U	**0.00887**	0.000815 U
	B-207-60	8/25/17	PES	ESC	60	-21.5	S	0.000249 U	0.000219 U	0.000294 U	0.000462 U	0.000281 U	0.000284 U	0.000828 U	0.00743 U	0.000407 U	0.00254 U	0.000310 U	0.000743 U
	B-207-70	8/25/17	PES	ESC	70	-31.5	S	0.000267 U	0.000235 U	0.000315 U	0.000496 U	0.000301 U	0.000305 U	0.000888 U	0.00797 U	0.000436 U	0.00273 U	0.000332 U	0.000797 U
	B-207-80	8/25/17	PES	ESC	80	-41.5	S	0.000258 U	0.000227 U	**173**	**0.000550 J**	**0.000601 J**	0.000294 U	0.000857 U	**1.23**	0.000421 U	0.00263 U	**0.00558**	0.000769 U
	B-207-90	8/25/17	PES	ESC	90	-51.5	S	0.00643 U	0.00566 U	**5.42**	0.0119 U	0.00725 U	0.00734 U	0.0213 U	**0.462**	0.0105 U	0.0657 U	0.00800 U	0.0191 U
B-208	B-208-20	8/24/17	PES	ESC	20	18.8	S	0.000277 U	0.000243 U	0.00816 U	0.000513 U	**0.000708 J**	0.000316 U	0.000920 U	**0.000689 J**	0.000451 U	0.00282 U	**0.00270**	0.000825 U
	B-208-35	8/24/17	PES	ESC	35	3.8	S	0.000255 U	0.000224 U	**0.0109 J**	0.000472 U	**0.00656**	0.000291 U	0.000847 U	**0.00162**	0.000416 U	0.00260 U	**0.00719**	0.000760 U
	B-901-50	8/24/17	PES	ESC	35 (dup)	3.8	S	0.000265 U	0.000233 U	**0.407 J**	0.000491 U	**0.00577**	0.000302 U	0.000880 U	**0.00118**	0.000432 U	0.00270 U	**0.00719**	0.000789 U
	B-208-50	8/24/17	PES	ESC	50	-11.2	S	0.000258 U	0.000227 U	**0.00150**	0.000479 U	**0.00455**	0.000295 U	0.000859 U	0.000308 U	0.000422 U	0.00264 U	0.000321 U	0.000771 U
	B-208-60	8/24/17	PES	ESC	60	-21.2	S	0.000261 U	0.000229 U	0.000307 U	0.000483 U	0.000294 U	0.000297 U	0.000866 U	0.000311 U	0.000425 U	0.00266 U	0.000324 U	0.000777 U
	B-208-70	8/24/17	PES	ESC	70	-31.2	S	0.000261 U	0.000230 U	0.000308 U	0.000485 U	0.000295 U	0.000298 U	0.000869 U	0.000312 U	0.000427 U	0.00267 U	0.000325 U	0.000779 U
	B-208-80	8/24/17	PES	ESC	80	-41.2	S	0.000289 U	0.000255 U	0.000341 U	0.000537 U	0.000327 U	0.000330 U	0.000962 U	0.000345 U	0.000473 U	0.00296 U	0.000360 U	0.000864 U
B-209	B-209-20	8/25/17	PES	ESC	20	19.0	S	0.000272 U	0.000239 U	**0.000424 J**	0.000504 U	**0.000402 J**	0.000310 U	0.000904 U	**0.000587 J**	0.000444 U	0.00278 U	**0.00168**	0.000811 U
	B-209-35	8/25/17	PES	ESC	35	4.0	S	0.000250 U	0.000220 U	**0.00682**	0.000464 U	**0.000840 J**	0.000285 U	0.000831 U	**0.00119**	0.000408 U	0.00255 U	**0.00915**	0.000746 U
	B-209-50	8/25/17	PES	ESC	50	-11.0	S	0.000305 U	0.000269 U	0.000360 U	0.000566 U	0.000344 U	0.000348 U	0.00102 U	0.000364 U	0.000498 U	0.00312 U	0.000380 U	0.000911 U
	B-209-60	8/25/17	PES	ESC	60	-21.0	S	0.000269 U	0.000236 U	0.000317 U	0.000498 U	0.000303 U	0.000306 U	0.000893 U	0.000320 U	0.000438 U	0.00274 U	0.000334 U	0.000801 U
	B-209-70	8/25/17	PES	ESC	70	-31.0	S	0.000249 U	0.000220 U	**0.000322 J**	0.000462 U	0.000281 U	0.000285 U	0.000829 U	0.000297 U	0.000407 U	0.00255 U	0.000310 U	0.000744 U
	B-209-75	8/25/17	PES	ESC	75	-36.0	S	0.000248 U	0.000218 U	0.000293 U	0.000460 U	0.000280 U	0.000283 U	0.000825 U	0.000296 U	0.000405 U	0.00253 U	0.000309 U	0.000740 U
	B-209-80	8/25/17	PES	ESC	80	-41.0	S	0.000269 U	0.000237 U	0.000317 U	0.000499 U	0.000303 U	0.000307 U	0.000894 U	0.000321 U	0.000439 U	0.00275 U	0.000334 U	0.000802 U
B-210	B-210-6	8/21/17	PES	ESC	6	33.4	S	0.000276 U	0.000243 U	**0.0313**	0.000512 U	0.000311 U	0.000315 U	0.000917 U	**0.00234**	0.000450 U	0.00282 U	0.000343 U	0.000823 U
	B-210-15	8/21/17	PES	ESC	15	24.4	S	0.00634 U	0.00558 U	**0.0730**	0.0117 U	0.00715 U	0.00724 U	0.0210 U	**0.0647**	0.0103 U	0.0648 U	0.00789 U	0.0189 U
	B-210-20	8/21/17	PES	ESC	20	19.4	S	0.000261 U	0.000229 U	0.000307 U	0.000484 U	0.000294 U	0.000297 U	0.000867 U	0.000311 U	0.000426 U	0.00266 U	**0.000499 J**	0.000778 U
	B-210-35	8/21/17	PES	ESC	35	4.4	S	0.000270 U	0.000238 U	**0.00789**	0.000501 U	0.000305 U	0.000308 U	0.000898 U	**0.00300**	0.000441 U	0.00276 U	0.000336 U	0.000806 U
	B-210-46	8/21/17	PES	ESC	46	-6.6	S	0.000255 U	0.000224 U	**0.000912 J**	0.000473 U	**0.00790**	0.000291 U	0.000848 U	**0.000376 J**	0.000416 U	0.00260 U	**0.00182 J**	0.000760 U
	B-210-60	8/22/17	PES	ESC	60	-20.6	S	0.00628 U	0.00553 U	0.00741 U	0.0116 U	0.00708 U	0.00717 U	0.0208 U	0.00749 U	0.0102 U	0.0642 U	0.00781 U	0.0187 U
	B-210-70	8/22/17	PES	ESC	70	-30.6	S	0.000252 U	0.000222 U	0.000298 U	0.000468 U	0.000285 U	0.000288 U	0.000839 U	0.000301 U	0.000412 U	0.00258 U	0.000314 U	0.000753 U
	B-210-80	8/22/17	PES	ESC	80	-40.6	S	0.000258 U	0.000228 U	0.000305 U	0.000479 U	0.000292 U	0.000295 U	0.000859 U	0.000308 U	0.000422 U	0.00264 U	**0.000485 J**	0.000771 U
	B-900-20	8/22/17	PES	ESC	80 (dup)	-40.6	S	0.000278 U	0.000245 U	0.000328 U	0.000515 U	0.000314 U	0.000317 U	0.000924 U	0.000331 U	0.000454 U	0.00284 U	0.000346 U	0.000829 U
B-211	B-211-20	8/17/17	PES	ESC	20	19.8	S	0.000261 U	0.000230 U	**0.0153**	0.000485 U	**0.00109 J**	0.000298 U	0.000869 U	**0.0202**	0.000427 U	0.00267 U	**0.000723 J**	0.000779 U
	B-211-35	8/17/17	PES	ESC	35	4.8	S	0.000263 U	0.000232 U	**0.000805 J**	0.000489 U	0.000297 U	0.000301 U	0.000876 U	0.000314 U	0.000430 U	0.00269 U	**0.000539 J**	0.000786 U
	B-211-50	8/17/17	PES	ESC	50	-10.3	S	0.000253 U	0.000223 U	**0.0235**	0.000469 U	**0.000512 J**	0.000289 U	0.000841 U	0.000302 U	0.000413 U	0.00258 U	**0.00127**	0.000755 U
	B-211-57	8/17/17	PES	ESC	57	-17.3	S	0.000276 U	0.000243 U	**0.0294 J**	0.000512 U	**0.00171**	0.000315 U	0.000918 U	**0.00212**	0.000451 U	0.00282 U	**0.00600**	0.000823 U
	B-211-60	8/17/17	PES	ESC	60	-20.3	S	0.000270 U	0.000238 U	**0.162**	0.000500 U	**0.0599**	0.000308 U	0.000897 U	**0.000907 J**	0.000440 U	0.00276 U	**1.15**	0.000805 U
	B-211-65	8/18/17	PES	ESC	65	-25.3	S	0.000264 U	0.000233 U	**7.42**	**0.00201 J**	**0.0110**	0.000301 U	0.000878 U	**1.15**	0.000431 U	0.00270 U	**0.0421**	0.000788 U
	B-211-70	8/18/17	PES	ESC	70	-30.3	S	0.140 U	0.123 U	**46.1**	0.260 U	0.158 U	0.160 U	0.466 U	**2.88**	0.229 U	1.44 U	0.175 U	0.418 U
	B-211-80	8/18/17	PES	ESC	80	-40.3	S	0.00634 U	0.00558 U	**9.34**	0.0117 U	0.00715 U	0.00723 U	0.0210 U	**0.495**	0.0103 U	0.0648 U	0.00788 U	0.0188 U
	B-211-90	8/18/17	PES	ESC	90	-50.3	S	0.00682 U	0.00600 U	**2.66**	0.0126 U	**0.0159 J**	0.00779 U	0.0226 U	**1.00**	0.0111 U	0.0697 U	0.00849 U	0.0203 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
B-211 (continued)	B-211-100	8/18/17	PES	ESC	100	-60.3	S	0.000272 U	0.000239 U	0.000320 U	0.000504 U	0.000306 U	0.000310 U	0.000903 U	0.000324 U	0.000443 U	0.00277 U	0.000388 U	0.000810 U
	B-211-110	8/18/17	PES	ESC	110	-70.3	S	0.000258 U	0.000227 U	**0.00132**	0.000479 U	0.000291 U	0.000294 U	0.000858 U	**0.000436 J**	0.000421 U	0.00264 U	0.000321 U	0.000770 U
	B-211-120	8/21/17	PES	ESC	120	-80.3	S	0.000263 U	0.000231 U	**0.000628 J**	0.000487 U	0.000296 U	0.000300 U	0.000873 U	**0.000423 J**	0.000429 U	0.00268 U	0.000326 U	0.000783 U
B-216	B-216-20	9/1/17	PES	ESC	20	31.9	S	0.000252 U	0.000222 U	**0.00134**	0.000467 U	0.000284 U	0.000288 U	0.000838 U	0.000301 U	0.000411 U	0.00257 U	0.000313 U	0.000752 U
	B-216-40	9/1/17	PES	ESC	40	11.9	S	0.000254 U	0.000223 U	0.000299 U	0.000471 U	0.000286 U	0.000290 U	0.000844 U	0.000303 U	0.000414 U	0.00259 U	0.000316 U	0.000757 U
	B-216-50	9/1/17	PES	ESC	50	1.9	S	0.000253 U	0.000223 U	0.000298 U	0.000469 U	0.000285 U	0.000289 U	0.000841 U	0.000302 U	0.000413 U	0.00258 U	0.000315 U	0.000754 U
	B-216-55	9/1/17	PES	ESC	55	-3.1	S	**0.000676 J**	0.000232 U	**0.0139**	**0.0228**	**0.00356**	0.000301 U	0.000876 U	**0.00182**	0.000430 U	0.00269 U	**0.00113**	**0.0189**
	B-216-65	9/1/17	PES	ESC	65	-13.1	S	0.000281 U	0.000247 U	0.000331 U	0.000521 U	0.000317 U	0.000321 U	0.000934 U	0.000335 U	0.000459 U	0.00287 U	0.000349 U	0.000838 U
	B-216-85	9/1/17	PES	ESC	85	-33.1	S	0.000282 U	0.000248 U	0.000333 U	**0.000655 J**	0.000318 U	0.000322 U	0.000938 U	0.000336 U	0.000461 U	0.00288 U	0.000351 U	0.000842 U
	B-216-95	9/1/17	PES	ESC	95	-43.1	S	0.000266 U	0.000234 U	0.000314 U	0.000493 U	0.000300 U	0.000303 U	0.000884 U	0.000317 U	0.000434 U	0.00272 U	0.000331 U	0.000793 U
B-217	B-217-15	9/5/17	PES	ESC	15	36.8	V	0.000266 U	0.000234 U	**0.0221**	0.000493 U	0.000300 U	0.000303 U	0.000883 U	0.000317 U	0.000434 U	0.00271 U	0.000330 U	0.000792 U
	B-217-25	9/5/17	PES	ESC	25	26.8	S	0.000259 U	0.000228 U	**0.0432**	0.000481 U	0.000293 U	0.000296 U	0.000863 U	**0.00122**	0.000424 U	0.00265 U	0.000323 U	0.000774 U
	B-217-35	9/5/17	PES	ESC	35	16.8	S	0.000269 U	0.000236 U	0.000317 U	0.000498 U	0.000303 U	0.000306 U	0.000893 U	0.000320 U	0.000438 U	0.00274 U	0.000334 U	0.000801 U
	B-217-42	9/5/17	PES	ESC	42	9.8	S	0.000268 U	0.000236 U	**152**	**0.000702 J**	**0.00334**	0.000305 U	0.000890 U	**0.150**	0.000437 U	0.00273 U	**0.464 J**	0.000798 U
	B-217-55	9/5/17	PES	ESC	55	-3.2	S	0.000272 U	0.000239 U	0.000320 U	0.000504 U	0.000306 U	0.000310 U	0.000903 U	0.000324 U	0.000443 U	0.00277 U	**0.00462**	0.000810 U
	B-217-65	9/5/17	PES	ESC	65	-13.2	S	0.000269 U	0.000237 U	**0.0255**	0.000500 U	**0.000366 J**	0.000307 U	0.000896 U	**0.00178**	0.000440 U	0.00275 U	**0.00259**	0.000804 U
	B-217-75	9/5/17	PES	ESC	75	-23.2	S	0.000280 U	0.000247 U	0.000331 U	0.000520 U	0.000316 U	0.000320 U	0.000932 U	0.000334 U	0.000458 U	0.00286 U	0.000349 U	0.000836 U
	B-217-85	9/6/17	PES	ESC	85	-33.2	S	0.000267 U	0.000235 U	0.000314 U	0.000494 U	0.000301 U	0.000304 U	0.000886 U	0.000318 U	0.000435 U	0.00272 U	0.000332 U	0.000795 U
	B-217-95	9/6/17	PES	ESC	95	-43.2	S	0.000283 U	0.000249 U	**0.00111 J**	0.000525 U	0.000319 U	0.000323 U	0.000940 U	0.000337 U	0.000462 U	0.00289 U	0.000352 U	0.000844 U
	B-217-106	9/6/17	PES	ESC	106	-54.2	S	0.0287 U	0.0252 U	**5.18**	0.0532 U	0.0324 U	0.0327 U	0.0954 U	**0.704**	0.0468 U	0.293 U	0.0357 U	0.0855 U
	B-217-115	9/6/17	PES	ESC	115	-63.2	S	0.000270 U	0.000238 U	0.000319 U	0.000501 U	0.000305 U	0.000308 U	0.000898 U	0.000322 U	0.000441 U	0.00276 U	0.000336 U	0.000806 U
B-218	B-218-12.5	9/19/17	PES	ESC	12.5	25.6	S	0.000266 U	0.000235 U	**0.0438**	0.000494 U	**0.0171**	0.000304 U	0.000886 U	**0.775**	0.000435 U	0.00272 U	**0.0281**	0.000795 U
	B-218-19	9/19/17	PES	ESC	19	19.1	S	0.000266 U	0.000234 U	**0.000476 J**	0.000493 U	**0.00346**	0.000303 U	0.000883 U	**0.00946 J**	0.000434 U	0.00271 U	**0.0286**	0.000792 U
	B-218-25	9/19/17	PES	ESC	25	13.1	S	0.000271 U	0.000239 U	**0.0104**	0.000503 U	**0.00124**	0.000309 U	0.000901 U	**0.0144**	0.000442 U	0.00277 U	**0.0449**	0.000808 U
	B-218-40	9/19/17	PES	ESC	40	-1.9	S	0.0144 U	0.0126 U	**0.421**	0.0267 U	**0.0724**	0.0165 U	0.0479 U	**0.255**	0.0235 U	0.147 U	**0.271**	0.0429 U
	B-218-50	9/19/17	PES	ESC	50	-11.9	S	0.000250 U	0.000220 U	**2.01 J**	0.000463 U	**0.0173**	0.000285 U	0.000830 U	**0.953 J**	0.000407 U	0.00255 U	**0.0144 J**	0.000744 U
	B-913-70	9/19/17	PES	ESC	50 (dup)	-11.9	S	0.000248 U	0.000219 U	**0.537 J**	0.000461 U	**0.0127**	0.000283 U	0.000826 U	**0.180 J**	0.000406 U	0.00254 U	**0.00427 J**	0.000741 U
B-219	B-219-42	8/28/17	PES	ESC	42	-2.2	S	0.000255 U	0.000224 U	**0.000857 J**	0.000473 U	0.000288 U	0.000291 U	0.000847 U	**0.000504 J**	0.000416 U	0.00260 U	**0.00214**	0.000760 U
	B-219-50	8/28/17	PES	ESC	50	-10.2	S	0.000277 U	0.000244 U	**0.0534 J**	0.000514 U	**0.00107 J**	0.000316 U	0.000921 U	**0.00555**	0.000452 U	0.00283 U	**0.156**	0.000827 U
	B-219-60	8/28/17	PES	ESC	60	-20.2	S	0.000252 U	0.000222 U	**0.000478 J**	0.000467 U	0.000284 U	0.000287 U	0.000837 U	0.000300 U	0.000411 U	0.00257 U	**0.00161**	0.000751 U
	B-219-70	8/28/17	PES	ESC	70	-30.2	S	0.000267 U	0.000235 U	**0.00134 J**	0.000495 U	0.000301 U	0.000305 U	0.000888 U	0.000318 U	0.000436 U	0.00273 U	**0.000670 J**	0.000797 U
	B-219-80	8/28/17	PES	ESC	80	-40.2	S	0.000254 U	0.000224 U	0.000300 U	0.000471 U	0.00717 U	0.000290 U	0.000845 U	0.000303 U	0.000415 U	0.00260 U	0.000316 U	0.000758 U
B-220	B-220-15	9/20/17	PES	ESC	15	23.9	S	0.000266 U	0.000234 U	**0.0351**	**0.000493**	**0.00163**	0.000304 U	0.000885 U	**0.0526**	0.000434 U	0.00272 U	**0.0771**	0.000794 U
	B-220-29	9/20/17	PES	ESC	29	9.9	S	0.000272 U	0.000239 U	**14.0**	**0.000672 J+**	**0.00550 J+**	0.000310 U	0.000904 U	**1.74**	0.000444 U	0.00278 U	**0.0490 J+**	0.000811 U
	B-220-32	9/20/17	PES	ESC	32	6.9	S	0.000267 U	0.000235 U	**6.52**	0.000495 U	**0.00784**	0.000305 U	0.000888 U	**0.692 J**	0.000436 U	0.00273 U	**0.143**	0.000796 U
	B-220-40	9/20/17	PES	ESC	40	-1.1	S	0.000260 U	0.000229 U	**38.9**	0.000482 U	**0.00562**	0.000296 U	0.000864 U	**5.82**	0.000424 U	0.00265 U	**0.132**	0.000775 U
	B-220-50	9/20/17	PES	ESC	50	-11.1	S	0.000252 U	0.000222 U	**18.5**	0.000467 U	**0.000658 J**	0.000287 U	0.000837 U	**2.03**	0.000411 U	0.00257 U	**0.00191**	0.000751 U
	B-914-75	9/20/17	PES	ESC	50 (dup)	-11.1	S	0.000252 U	0.000222 U	**15.5**	0.000467 U	**0.000689 J**	0.000287 U	0.000837 U	**1.25**	0.000411 U	0.00257 U	**0.00210**	0.000751 U
B-221	B-221-16	9/20/17	PES	ESC	16	23.0	S	0.00686 U	0.00603 U	**0.539**	0.0127 U	0.00773 U	0.00783 U	0.0227 U	**0.250**	0.0112 U	0.0701 U	0.0805 U	0.0204 U
	B-221-22	9/20/17	PES	ESC	22	17.0	S	0.269 U	0.237 U	**25.8**	0.499 U	0.304 U	0.307 U	0.895 U	**0.984 J**	0.439 U	2.75 U	0.335 U	0.803 U
	B-221-33	9/20/17	PES	ESC	33	6.0	S	0.262 U	0.231 U	**21.8**	0.486 U	0.296 U	0.299 U	0.871 U	**0.835 J**	0.428 U	2.68 U	0.326 U	0.781 U
	B-221-37	9/20/17	PES	ESC	37	2.0	S	0.0550 U	0.0484 U	**9.02**	0.102 U	0.0621 U	0.0628 U	0.183 U	**0.447**	0.0898 U	0.562 U	0.0684 U	0.165 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
B-221 (continued)	B-915-80	9/20/17	PES	ESC	37 (dup)	2.0	S	0.0268 U	0.0236 U	**7.54**	0.0497 U	0.0303 U	0.0306 U	0.0892 U	**0.400**	0.0438 U	0.274 U	0.0334 U	0.0800 U
	B-221-45	9/20/17	PES	ESC	45	-6.0	S	2.57 U	2.26 U	**8.270**	4.76 U	2.90 U	2.93 U	8.53 U	**4.43 J**	4.19 U	26.2 U	3.19 U	7.66 U
	B-221-50	9/20/17	PES	ESC	50	-11.0	S	0.127 U	0.112 U	**30.4**	0.236 U	0.144 U	0.146 U	0.423 U	**0.618**	0.208 U	1.31 U	0.159 U	0.380 U
	B-221-60	9/20/17	PES	ESC	60	-21.0	S	0.129 U	0.114 U	**14.5**	0.240 U	0.146 U	0.148 U	0.430 U	**0.865**	0.211 U	1.33 U	0.161 U	0.386 U
	B-221-70	9/21/17	PES	ESC	70	-31.0	S	0.000258 U	0.000227 U	**0.0853 J**	0.000479 U	0.000291 U	0.000295 U	0.000859 U	**0.00152**	0.000422 U	0.00264 U	**0.00153**	0.000770 U
B-222	B-222-17	9/21/17	PES	ESC	17	22.2	S	0.000265 U	0.000234 U	**1.01**	0.000492 U	**0.00481**	0.000303 U	0.000882 U	**0.815**	0.000433 U	0.00271 U	**0.00907**	0.000791 U
	B-222-25	9/21/17	PES	ESC	25	14.2	S	0.000270 U	0.000238 U	**0.714**	0.000502 U	**0.00171**	0.000309 U	0.000899 U	**0.130**	0.000442 U	0.00276 U	**0.0116**	0.000807 U
	B-222-34	9/21/17	PES	ESC	34	5.2	S	0.000262 U	0.000231 U	0.0190 UJ	0.000486 U	**0.000980 J**	0.000299 U	0.000872 U	**0.00506**	0.000428 U	0.00268 U	**0.0120**	0.000782 U
	B-222-42	9/21/17	PES	ESC	42	-2.8	S	0.000290 U	0.000255 U	**0.0557 J**	0.000538 U	**0.0431**	0.000331 U	0.000965 U	**0.00699**	0.000474 U	0.00296 U	**0.127**	0.000866 U
	B-222-50	9/21/17	PES	ESC	50	-10.8	S	0.0125 U	0.0110 U	**4.09**	0.0233 U	0.0142 U	0.0144 U	0.0417 U	**1.40 J**	0.0205 U	0.129 U	0.0157 U	0.0374 U
	B-916-30	9/21/17	PES	ESC	50 (dup)	-10.8	S	0.000248 U	0.000218 U	**4.34**	**0.000460**	**0.00183**	0.000283 U	0.000825 U	**0.172 J**	0.000405 U	0.00253 U	0.000309 U	0.000740 U
B-223	B-223-16	9/21/17	PES	ESC	16	23.1	S	0.0553 U	0.0487 U	**27.0**	0.103 U	0.0624 U	0.0631 U	0.184 U	**1.08**	0.0903 U	0.565 U	0.0688 U	0.165 U
	B-223-22	9/21/17	PES	ESC	22	17.1	S	0.0534 U	0.0470 U	**38.0**	0.0991 U	0.0603 U	0.0610 U	0.178 U	**0.453**	0.0872 U	0.546 U	0.0665 U	0.160 U
	B-223-30	9/21/17	PES	ESC	30	9.1	S	6.44 U	5.67 U	**5,560**	11.9 U	7.27 U	7.35 U	21.4 U	7.68 U	10.5 U	65.8 U	8.01 U	19.2 U
	B-223-39	9/21/17	PES	ESC	39	0.1	S	0.000267 U	0.000235 U	**4.68**	0.000494 U	**0.000883 J**	0.000304 U	0.000886 U	**0.0228**	0.000435 U	0.00272 U	**0.00775**	0.000795 U
	B-223-47	9/21/17	PES	ESC	47	-7.9	S	0.000272 U	0.000239 U	**2.17 J**	0.000504 U	0.000307 U	0.000310 U	0.000903 U	**0.00106 J**	0.000444 U	0.00278 U	0.000338 U	0.000810 U
	B-917-57	9/21/17	PES	ESC	47 (dup)	-7.9	S	0.000251 U	0.000221 U	**1.13 J**	0.000466 U	0.000284 U	0.000287 U	0.000836 U	**0.000520 J**	0.000411 U	0.00257 U	0.000313 U	0.000750 U
B-224	B-224-6	11/27/17	PES	ESC	6	33.1	S	0.000253 U	0.000223 U	**0.0208**	0.000469 U	0.000285 U	0.000289 U	0.000841 U	**0.00205**	0.000413 U	0.00258 U	0.000315 U	0.000755 U
	B-224-11	11/27/17	PES	ESC	11	28.1	S	0.000625 U	0.000550 U	**0.151**	**0.00174 J**	**0.0136**	0.000713 U	0.00208 U	**0.0404**	0.00102 U	0.00638 U	**0.0577**	0.00186 U
	B-224-16	11/27/17	PES	ESC	16	23.1	S	0.000283 U	0.000249 U	**0.0101**	0.000525 U	**0.000403 J**	0.000323 U	0.000941 U	**0.00374**	0.000462 U	0.00289 U	**0.0195**	0.000844 U
	B-224-21.5	11/27/17	PES	ESC	21.5	17.6	S	0.000272 U	0.000239 U	**2.71**	0.000504 U	**0.00140**	0.000310 U	0.000903 U	**0.0906**	0.000444 U	0.00277 U	**0.00460**	0.000810 U
	B-224-26	11/27/17	PES	ESC	26	13.1	S	0.000309 U	0.000272 U	**3.07**	0.000574 U	**0.00329**	0.000352 U	0.00103 U	**0.234**	0.000504 U	0.00315 U	**0.0154**	0.000923 U
	B-224-31	11/27/17	PES	ESC	31	8.1	S	0.000274 U	0.000240 U	**4.71**	0.000508 U	**0.00128**	0.000312 U	0.000909 U	**0.137**	0.000446 U	0.00279 U	**0.00773**	0.000816 U
	B-224-36	11/27/17	PES	ESC	36	3.1	S	0.000260 U	0.000229 U	**6.55**	0.000482 U	**0.00289**	0.000296 U	0.000864 U	**0.269**	0.000424 U	0.00265 U	**0.0255**	0.000775 U
	B-224-60.5	11/27/17	PES	ESC	60.5	-21.4	S	0.000378 U	0.000333 U	**0.151**	0.000702 U	0.000427 U	0.000432 U	0.00126 U	**0.00944**	0.000618 U	0.00386 U	**0.0103**	0.00113 U
B-225	B-225-5	11/27/17	PES	ESC	5	34.1	S	0.000254 U	0.000223 U	**0.0223**	0.000471 U	0.000286 U	0.000290 U	0.000844 U	**0.00239**	0.000414 U	0.00259 U	0.000316 U	0.000757 U
	B-225-11	11/27/17	PES	ESC	11	28.1	S	0.000274 U	0.000241 U	**0.0124**	0.000508 U	0.000309 U	0.000312 U	0.000910 U	**0.00394**	0.000447 U	0.00280 U	**0.000480 J**	0.000816 U
	B-225-16	11/27/17	PES	ESC	16	23.1	S	0.00688 U	0.00606 U	**4.26**	0.0127 U	0.00776 U	0.00786 U	0.0228 U	**0.353**	0.0112 U	0.0703 U	**0.0460**	0.0205 U
	B-225-21	11/27/17	PES	ESC	21	18.1	S	0.00665 U	0.00585 U	**1.11**	0.0123 U	0.00750 U	0.00759 U	0.0221 U	**0.0428**	0.0109 U	0.0680 U	0.00828 U	0.0198 U
	B-225-26	11/27/17	PES	ESC	26	13.1	S	0.000275 U	0.000242 U	**1.13**	0.000510 U	**0.000763 J**	0.000314 U	0.000914 U	**0.0370**	0.000449 U	0.00281 U	**0.00619**	0.000820 U
	B-225-31	11/27/17	PES	ESC	31	8.1	S	0.000267 U	0.000235 U	**1.09**	0.000496 U	**0.000751 J**	0.000305 U	0.000889 U	**0.0372**	0.000437 U	0.00273 U	**0.00550**	0.000798 U
	B-225-36	11/27/17	PES	ESC	36	3.1	S	0.000288 U	0.000254 U	**0.158**	0.000535 U	0.000325 U	0.000329 U	0.000958 U	**0.00696**	0.000470 U	0.00294 U	**0.000538 J**	0.000860 U
B-226	B-226-6	11/28/17	PES	ESC	6	33.1	S	0.000282 U	0.000248 U	**0.0227**	0.000523 U	0.000318 U	0.000322 U	0.000937 U	**0.00209**	0.000460 U	0.00288 U	0.000350 U	0.000841 U
	B-226-11	11/28/17	PES	ESC	11	28.1	S	0.000265 U	0.000234 U	**0.00869**	**0.000730 J**	0.000299 U	0.000303 U	0.000882 U	**0.00190**	0.000433 U	0.00271 U	**0.000805 J**	0.000792 U
	B-226-16	11/28/17	PES	ESC	16	23.1	S	0.00656 U	0.00578 U	**21.7 J**	0.0121 U	**0.0147 J**	0.00749 U	0.0218 U	**0.917 J**	0.0107 U	0.0671 U	**0.0557 J**	0.0195 U
	B-920-35	11/28/17	PES	ESC	16 (dup)	23.1	S	0.000259 U	0.000228 U	**10.6 J**	0.000480 U	**0.000613 J**	0.000295 U	0.000861 U	**0.0316 J**	0.000423 U	0.00264 U	**0.00141 J**	0.000772 U
	B-226-21	11/28/17	PES	ESC	21	18.1	S	0.000267 U	0.000235 U	**3.07**	0.000494 U	0.000301 U	0.000304 U	0.000886 U	**0.00779**	0.000435 U	0.00272 U	**0.000390 J**	0.000795 U
	B-226-31.5	11/28/17	PES	ESC	31.5	7.6	S	0.000249 U	0.000219 U	**4.80**	0.000462 U	**0.00128**	0.000284 U	0.000828 U	**0.0755**	0.000407 U	0.00254 U	**0.0102**	0.000743 U
	B-226-40	11/28/17	PES	ESC	40	-0.9	S	0.000268 U	0.000236 U	**1.75**	0.000497 U	**0.000939 J**	0.000306 U	0.000891 U	**0.0401**	0.000437 U	0.00274 U	**0.0188**	0.000799 U
B-227	B-227-6	11/28/17	PES	ESC	6	33.1	S	0.000267 U	0.000235 U	**0.0154**	0.000496 U	0.000301 U	0.000305 U	0.000888 U	**0.000798 J**	0.000436 U	0.00273 U	0.000332 U	0.000797 U
	B-227-11	11/28/17	PES	ESC	11	28.1	S	0.000252 U	0.000222 U	**0.141**	0.000468 U	**0.00143**	0.000288 U	0.000839 U	**0.0406**	0.000412 U	0.00258 U	0.000314 U	0.000752 U
	B-227-16	11/28/17	PES	ESC	16	23.1	S	0.000268 U	0.000236 U	**2.47**	0.000497 U	**0.00203**	0.000306 U	0.000892 U	**0.0804**	0.000438 U	0.00274 U	**0.00781**	0.000800 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
B-227 (continued)	B-227-21	11/28/17	PES	ESC	21	18.1	S	0.000272 U	0.000239 U	**7.18**	0.000504 U	**0.00290**	0.000310 U	0.000903 U	**0.311**	0.000443 U	0.00277 U	**0.0186**	0.000810 U
	B-227-26	11/28/17	PES	ESC	26	13.1	S	0.000273 U	0.000240 U	**7.86**	0.000506 U	**0.00186**	0.000311 U	0.000906 U	**0.124**	0.000445 U	0.00278 U	**0.00735**	0.000813 U
	B-227-31	11/28/17	PES	ESC	31	8.1	S	0.000281 U	0.000247 U	**8.38**	0.000521 U	**0.000628 J**	0.000320 U	0.000933 U	**0.0396**	0.000458 U	0.00287 U	**0.00446**	0.000837 U
	B-227-36	11/28/17	PES	ESC	36	3.1	S	0.000269 U	0.000236 U	**1.75**	0.000498 U	**0.00193**	0.000306 U	0.000893 U	**0.138**	0.000438 U	0.00274 U	**0.00169**	0.000801 U
B-228	B-228-6	11/29/17	PES	ESC	6	33.1	S	0.000286 U	0.000252 U	**0.0291**	0.000531 U	0.000323 U	0.000327 U	0.000952 U	**0.00216**	0.000467 U	0.000292 U	0.000356 U	0.000854 U
	B-228-11	11/29/17	PES	ESC	11	28.1	S	0.000260 U	0.000229 U	**0.00300**	0.000482 U	0.000293 U	0.000297 U	0.000865 U	**0.000709 J**	0.000425 U	0.00266 U	0.000323 U	0.000776 U
	B-228-16	11/29/17	PES	ESC	16	23.1	S	0.000252 U	0.000222 U	**203 J**	**0.000556 J**	**0.00385**	0.000288 U	0.000838 U	**0.680 J**	0.000411 U	0.00257 U	**0.00764**	0.000752 U
	B-921-22	11/29/17	PES	ESC	16 (dup)	23.1	S	0.000269 U	0.000237 U	**18.2 J**	**0.000672 J**	**0.00415**	0.000307 U	0.000894 U	**0.378 J**	0.000439 U	0.00275 U	**0.00840**	0.000802 U
	B-228-21	11/29/17	PES	ESC	21	18.1	S	0.000265 U	0.000233 U	**14.0**	0.000491 U	**0.000496 J**	0.000302 U	0.000880 U	**0.0594**	0.000432 U	0.00270 U	**0.000858 J**	0.000789 U
	B-228-26	11/29/17	PES	ESC	26	13.1	S	0.000252 U	0.000222 U	**10.2**	0.000467 U	**0.000777 J**	0.000287 U	0.000837 U	**0.0775**	0.000411 U	0.00257 U	**0.0127**	0.000751 U
	B-228-31	11/29/17	PES	ESC	31	8.1	S	0.000260 U	0.000229 U	**1.60**	0.000482 U	**0.000614 J**	0.000296 U	0.000864 U	**0.0786**	0.000424 U	0.00265 U	**0.0103**	0.000775 U
	B-228-36	11/29/17	PES	ESC	36	3.1	S	0.000264 U	0.000233 U	**0.101**	0.000490 U	**0.000603 J**	0.000302 U	0.000879 U	**0.0486**	0.000432 U	0.00270 U	**0.0217**	0.000789 U
B-229	B-229-6	11/29/17	PES	ESC	6	33.1	S	0.000342 U	0.000301 U	**0.769**	0.000635 U	0.000386 U	0.000391 U	0.00114 U	**0.0382**	0.000559 U	0.00350 U	0.000426 U	0.00102 U
	B-229-11	11/29/17	PES	ESC	11	28.1	S	0.000332 U	0.000292 U	**0.0366**	**0.00219 J**	**0.00148**	0.000379 U	0.00110 U	**0.00585**	0.000542 U	0.00339 U	**0.0272**	0.000991 U
	B-229-16	11/29/17	PES	ESC	16	23.1	S	0.000279 U	0.000246 U	**0.101**	0.000517 U	**0.000828 J**	0.000318 U	0.000927 U	**0.0138**	0.000455 U	0.00285 U	**0.00481**	0.000832 U
	B-229-25	11/29/17	PES	ESC	25	14.1	S	0.000257 U	0.000226 U	**2.50**	0.000476 U	**0.00195**	0.000293 U	0.000853 U	**0.510**	0.000419 U	0.00262 U	**0.0418**	0.000765 U
	B-229-31	11/29/17	PES	ESC	31	8.1	S	0.000282 U	0.000248 U	**4.99**	0.000523 U	**0.00384**	0.000322 U	0.000938 U	**1.53**	0.000461 U	0.00288 U	**0.105**	0.000842 U
	B-229-36	11/29/17	PES	ESC	36	3.1	S	0.000257 U	0.000227 U	**9.25**	0.000477 U	**0.00217**	0.000294 U	0.000856 U	**0.898**	0.000420 U	0.00263 U	**0.0609**	0.000768 U
	B-229-41	11/29/17	PES	ESC	41	-1.9	S	0.000272 U	0.000240 U	**64.0**	0.000505 U	**0.00377**	0.000311 U	0.000906 U	**0.384 J**	0.000445 U	0.00278 U	**0.126**	0.000813 U
	B-229-45	11/29/17	PES	ESC	45	-5.9	S	0.000280 U	0.000246 U	**158 J+**	0.000519 U	**0.000316 J+**	0.000319 U	0.000931 U	**0.0946 J+**	0.000457 U	0.00286 U	**0.00430 J+**	0.000835 U
B-230	B-230-6	11/30/17	PES	ESC	6	33.1	S	0.000247 U	0.000217 U	**0.0333**	0.000458 U	0.000278 U	0.000282 U	0.000821 U	**0.00215**	0.000403 U	0.00252 U	0.000307 U	0.000736 U
	B-230-11	11/30/17	PES	ESC	11	28.1	S	0.000256 U	0.000225 U	**0.00442**	0.000474 U	0.000288 U	0.000292 U	0.000850 U	**0.000709 J**	0.000417 U	0.00261 U	**0.00225**	0.000762 U
	B-230-16	11/30/17	PES	ESC	16	23.1	S	0.0651 U	0.0573 U	**1,100**	0.120 U	0.0735 U	0.0744 U	0.216 U	**9.17**	0.106 U	0.666 U	0.0810 U	0.194 U
	B-230-21	11/30/17	PES	ESC	21	18.1	S	0.559 U	0.492 U	**2,820 J**	1.04 U	0.630 U	0.638 U	1.86 U	**4.43 J**	0.912 U	5.71 U	0.695 U	1.67 U
	B-922-15	11/30/17	PES	ESC	21 (dup)	18.1	S	0.283 U	0.249 U	**165 J**	0.524 U	0.319 U	0.322 U	0.940 U	**0.505 J**	0.461 U	2.89 U	0.351 U	0.843 U
	B-230-26	11/30/17	PES	ESC	26	13.1	S	0.701 U	0.617 U	**607**	1.29 U	0.791 U	0.801 U	2.32 U	0.836 U	1.14 U	7.17 U	0.872 U	2.09 U
	B-230-31	11/30/17	PES	ESC	31	8.1	S	0.291 U	0.256 U	**105**	0.540 U	0.328 U	0.332 U	0.968 U	**0.603 J**	0.475 U	2.97 U	0.362 U	0.868 U
	B-230-35	11/30/17	PES	ESC	35	4.1	S	0.0423 U	0.0372 U	**25.4**	0.0784 U	0.0477 U	0.0482 U	0.141 U	**0.211**	0.0690 U	0.432 U	0.0525 U	**0.174 J**
	B-230-55	11/30/17	PES	ESC	55	-15.9	S	0.0702 U	0.0618 U	**42.3**	0.130 U	0.0792 U	0.0802 U	0.233 U	**5.09**	0.115 U	0.718 U	0.0874 U	0.209 U
B-231	B-231-6	11/30/17	PES	ESC	6	33.1	S	0.000289 U	0.000254 U	**0.0109**	0.000535 U	0.000326 U	0.000329 U	0.000960 U	**0.00146**	0.000471 U	0.00295 U	0.000359 U	0.000861 U
	B-231-11	11/30/17	PES	ESC	11	28.1	S	0.000276 U	0.000243 U	**0.0347**	0.000512 U	0.000311 U	0.000315 U	0.000917 U	**0.000346 J**	0.000450 U	0.00282 U	0.000343 U	0.000823 U
	B-231-16	11/30/17	PES	ESC	16	23.1	S	0.00655 U	0.00577 U	**0.438**	0.0121 U	0.00739 U	0.00748 U	0.0217 U	**0.118**	0.0107 U	0.0670 U	**0.0114 J**	0.0195 U
	B-231-21	11/30/17	PES	ESC	21	18.1	S	0.0154 U	0.0136 U	**0.728**	0.0287 U	0.0174 U	0.0176 U	0.0514 U	**0.180**	0.0253 U	0.158 U	**0.0458 J**	0.0462 U
	B-231-26	11/30/17	PES	ESC	26	13.1	S	0.000272 U	0.000239 U	**0.119**	0.000504 U	**0.000898 J**	0.000310 U	0.000903 U	**0.0177**	0.000444 U	0.00278 U	**0.00996**	0.000811 U
	B-231-30	11/30/17	PES	ESC	30	9.1	S	0.000264 U	0.000232 U	**0.0182**	0.000490 U	0.000298 U	0.000301 U	0.000878 U	**0.00140**	0.000431 U	0.00270 U	**0.00142**	0.000787 U
	B-231-36	11/30/17	PES	ESC	36	3.1	S	0.000265 U	0.000234 U	**0.0521**	0.000492 U	**0.000664 J**	0.000303 U	0.000882 U	**0.00158**	0.000433 U	0.00271 U	**0.118**	0.000792 U
B-232	B-232-6	12/1/17	PES	ESC	6	33.1	S	0.000276 U	0.000243 U	**0.00936**	**0.00268 J**	**0.000488 J**	0.000315 U	0.000919 U	**0.00224**	0.000451 U	0.00282 U	**0.00163**	**0.000825 J**
	B-232-11	12/1/17	PES	ESC	11	28.1	S	0.000311 U	0.000274 U	**0.00590 J+**	**0.000806 J+**	0.000351 U	0.000355 U	0.00104 U	**0.00169 J+**	0.000508 U	0.00318 U	**0.00346 J+**	0.000929 U
	B-232-16	12/1/17	PES	ESC	16	23.1	S	0.000274 U	0.000241 U	0.000676 U	0.000508 U	0.000309 U	0.000313 U	0.000911 U	0.000327 U	0.000447 U	0.00280 U	**0.00442**	0.000817 U
	B-232-21	12/1/17	PES	ESC	21	18.1	S	0.000262 U	0.000231 U	**0.0190**	0.000486 U	**0.00106 J**	0.000299 U	0.000871 U	**0.0216**	0.000428 U	0.00267 U	**0.00682**	0.000781 U
	B-232-26	12/1/17	PES	ESC	26	13.1	S	0.00874 U	0.00770 U	**11.1**	0.0162 U	0.00987 U	0.00997 U	0.0291 U	**0.763**	0.0142 U	0.0893 U	0.0109 U	0.0261 U
	B-232-31	12/1/17	PES	ESC	31	8.1	S	0.000264 U	0.000233 U	**4.27**	0.000490 U	**0.000524 J**	0.000301 U	0.000878 U	**0.0964**	0.000431 U	0.00270 U	**0.0110**	0.000788 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
B-232 (continued)	B-232-36	12/1/17	PES	ESC	36	3.1	S	0.000277 U	0.000244 U	**1.88**	0.000514 U	**0.000631 J**	0.000316 U	0.000922 U	**0.0913**	0.000453 U	0.00283 U	**0.0123**	0.000827 U
B-233	B-233-6	12/1/17	PES	ESC	6	29.5	S	0.000253 U	0.000222 U	**0.0192**	0.000468 U	0.000285 U	0.000288 U	0.000840 U	**0.00321**	0.000412 U	0.00258 U	0.000314 U	0.000753 U
	B-233-11	12/1/17	PES	ESC	11	24.5	S	0.000652 U	0.000574 U	**0.172 J+**	**0.00349 J+**	0.000737 U	0.000745 U	0.00217 U	**0.0579 J+**	0.00107 U	0.00667 U	**0.00824 J+**	0.00194 U
	B-233-16	12/1/17	PES	ESC	16	19.5	S	0.000330 U	0.000291 U	**0.0231**	0.000612 U	0.000373 U	0.000377 U	0.00110 U	**0.00524**	0.000539 U	0.00337 U	**0.00358**	0.000985 U
	B-233-21	12/1/17	PES	ESC	21	14.5	S	0.00667 U	0.00588 U	**8.23**	0.0123 U	**0.00859 J**	0.00762 U	0.0221 U	**0.434**	0.0109 U	0.0682 U	**0.0584**	0.0199 U
	B-233-26	12/1/17	PES	ESC	26	9.5	S	0.0140 U	0.0123 U	**9.90**	0.0259 U	0.0158 U	0.0160 U	0.0465 U	**2.55**	0.0228 U	0.143 U	**0.0261 J**	0.0417 U
	B-233-31	12/1/17	PES	ESC	31	4.5	S	0.00727 U	0.00640 U	**17.3**	0.0134 U	0.00821 U	0.00831 U	0.0241 U	**1.99**	0.0119 U	0.0744 U	**0.0519**	0.0216 U
	B-233-36	12/1/17	PES	ESC	36	-0.5	S	0.00658 U	0.00580 U	**6.26**	0.0122 U	0.00743 U	0.00752 U	0.0218 U	**0.474**	0.0107 U	0.0673 U	**0.0404**	0.0196 U
B-234	B-234-11	12/4/17	PES	ESC	11	40.8	V	0.000272 U	0.000240 U	**0.00155**	0.000505 U	0.000307 U	0.000310 U	0.000905 U	0.000324 U	0.000444 U	0.00278 U	0.000338 U	0.000812 U
	B-234-30	12/4/17	PES	ESC	30	21.8	S	0.000248 U	0.000218 U	0.000292 U	0.000459 U	0.000279 U	0.000283 U	0.000824 U	0.000295 U	0.000404 U	0.00253 U	0.000308 U	0.000739 U
B-234A	B-234A-35	12/4/17	PES	ESC	35	16.8	S	0.000268 U	0.000236 U	**0.000320 J**	0.000498 U	0.000303 U	0.000306 U	0.000892 U	0.000320 U	0.000438 U	0.00274 U	0.000334 U	0.000801 U
	B-234A-40	12/4/17	PES	ESC	40	11.8	S	0.000252 U	0.000222 U	**0.000501 J**	0.000467 U	0.000284 U	0.000287 U	0.000837 U	0.000300 U	0.000411 U	0.00257 U	0.000313 U	0.000751 U
	B-234A-42	12/4/17	PES	ESC	42	9.8	S	0.000287 U	0.000252 U	**0.0146**	0.000532 U	**0.00104 J**	0.000327 U	0.000953 U	**0.00180**	0.000468 U	0.00293 U	**0.343 J**	0.000855 U
	B-924-30	12/4/17	PES	ESC	42 (dup)	9.8	S	0.000284 U	0.000250 U	**0.0113**	0.000527 U	**0.00119 J**	0.000324 U	0.000945 U	**0.00161**	0.000464 U	0.00290 U	**0.167 J**	0.000848 U
	B-234A-45	12/4/17	PES	ESC	45	6.8	S	0.000264 U	0.000232 U	**0.0533**	0.000489 U	**0.000552 J**	0.000301 U	0.000877 U	**0.00364**	0.000430 U	0.00269 U	**0.106**	0.000787 U
B-235	B-235-15	12/5/17	PES	ESC	15	36.8	V	0.000281 U	0.000247 U	**0.0393**	0.000521 U	0.000317 U	0.000320 U	0.000934 U	**0.000776 J**	0.000458 U	0.00287 U	0.000349 U	0.000838 U
	B-235-35	12/5/17	PES	ESC	35	16.8	S	0.000259 U	0.000228 U	**0.0424**	0.000480 U	0.000292 U	0.000296 U	0.000861 U	**0.00527**	0.000423 U	0.00265 U	0.000322 U	0.000773 U
	B-235-40	12/5/17	PES	ESC	40	11.8	S	0.000256 U	0.000226 U	**2.24**	0.000476 U	0.000289 U	0.000293 U	0.000853 U	**0.0233**	0.000419 U	0.00262 U	0.000319 U	0.000765 U
	B-235-42.5	12/5/17	PES	ESC	42.5	9.3	S	0.0511 U	0.0450 U	**18.9**	0.0948 U	0.0577 U	0.0583 U	0.170 U	**1.06**	0.0834 U	0.522 U	**0.0877 J**	0.153 U
	B-235-45	12/5/17	PES	ESC	45	6.8	S	0.000264 U	0.000232 U	**20.7**	**0.000506 J**	**0.000963 J**	0.000301 U	0.000876 U	**1.09**	0.000430 U	0.00269 U	**0.0885**	0.000786 U
B-236	B-236-20	12/5/17	PES	ESC	20	31.8	S	0.000268 U	0.000236 U	**0.0460**	0.000496 U	0.000302 U	0.000305 U	0.000889 U	**0.00164**	0.000437 U	0.00273 U	0.000333 U	0.000798 U
	B-236-35	12/5/17	PES	ESC	35	16.8	S	0.000423 U	0.000373 U	**0.00968**	0.000786 U	0.000478 U	0.000484 U	0.00141 U	0.000310 U	0.000692 U	0.00433 U	0.000527 U	0.00127 U
	B-236-40	12/5/17	PES	ESC	40	11.8	S	0.000259 U	0.000228 U	**0.0440**	0.000480 U	0.000292 U	0.000295 U	0.000861 U	**0.000826 J**	0.000423 U	0.00264 U	**0.00373**	0.000772 U
	B-236-42.5	12/5/17	PES	ESC	42.5	9.3	S	0.274 U	0.242 U	**16.400**	0.509 U	0.310 U	0.313 U	0.912 U	**72.5**	0.448 U	2.80 U	**0.407 J**	0.819 U
	B-236-45	12/5/17	PES	ESC	45	6.8	S	0.0920 U	0.0809 U	**31.0**	0.170 U	0.104 U	0.105 U	0.305 U	**0.335 J**	0.150 U	0.938 U	0.114 U	0.274 U
B-237	B-237-5	12/6/17	PES	ESC	5	46.8	V	0.000273 U	0.000240 U	**0.00814**	0.000505 U	0.000307 U	0.000311 U	0.000906 U	0.000325 U	0.000445 U	0.00278 U	0.000339 U	0.000813 U
	B-237-35	12/6/17	PES	ESC	35	16.8	S	0.000273 U	0.000241 U	**0.000770 J**	0.000507 U	0.000308 U	0.000312 U	0.000909 U	0.000326 U	0.000446 U	0.00279 U	0.000340 U	0.000815 U
	B-237-40	12/6/17	PES	ESC	40	11.8	S	0.000251 U	0.000221 U	**2.57**	0.000466 U	0.000284 U	0.000287 U	0.000836 U	**0.0163**	0.000410 U	0.00257 U	0.000313 U	0.000750 U
	B-237-42	12/6/17	PES	ESC	42	9.8	S	0.000277 U	0.000243 U	**24.1 J**	**0.000539 J**	**0.00338 J**	0.000316 U	0.000919 U	**0.746 J**	0.000451 U	0.00282 U	**0.290 J**	0.000825 U
	B-925-41	12/6/17	PES	ESC	42 (dup)	9.8	S	0.0299 U	0.0263 U	**53.0 J**	0.0554 U	0.0337 U	0.0341 U	0.0993 U	**1.86 J**	0.0488 U	0.305 U	**0.110 J**	0.0891 U
	B-237-45	12/6/17	PES	ESC	45	6.8	S	0.000301 U	0.000265 U	**10.9**	0.000559 U	**0.000848 J**	0.000344 U	0.00100 U	**0.0457**	0.000492 U	0.00308 U	**0.131**	0.000899 U
B-238	B-238-6	12/6/17	PES	ESC	6	33.1	S	0.000273 U	0.000240 U	**0.0262**	0.000506 U	0.000308 U	0.000311 U	0.000907 U	**0.00294**	0.000445 U	0.00279 U	0.000339 U	0.000814 U
	B-238-11	12/6/17	PES	ESC	11	28.1	S	0.000272 U	0.000240 U	**22.7**	**0.00774 J+**	**0.000705 J+**	0.000311 U	0.000905 U	**0.0724 J+**	0.000444 U	0.00278 U	**0.00193**	0.000812 U
	B-238-16	12/6/17	PES	ESC	16	23.1	S	0.0669 U	0.0589 U	**28.6**	0.124 U	0.0755 U	0.0764 U	0.222 U	**0.262 J**	0.109 U	0.684 U	0.0833 U	0.199 U
	B-238-21	12/6/17	PES	ESC	21	18.1	S	0.261 U	0.230 U	**156**	0.484 U	0.295 U	0.298 U	0.868 U	0.311 U	0.426 U	2.67 U	0.325 U	0.779 U
	B-238-26	12/6/17	PES	ESC	26	13.1	S	0.000262 U	0.000230 U	**3.04**	0.000485 U	**0.00236**	0.000299 U	0.000870 U	**0.303**	0.000427 U	0.00267 U	**0.0375**	0.000781 U
	B-238-31	12/6/17	PES	ESC	31	8.1	S	0.000248 U	0.000218 U	**1.02**	0.000460 U	**0.000537 J**	0.000283 U	0.000825 U	**0.0375**	0.000405 U	0.00253 U	**0.0210**	0.000740 U
	B-238-36	12/6/17	PES	ESC	36	3.1	S	0.000274 U	0.000241 U	**4.04**	0.000508 U	**0.000500 J**	0.000313 U	0.000911 U	**0.0399**	0.000447 U	0.00280 U	**0.0328**	0.000817 U
B-239	B-239-5	4/3/18	PES	ESC	5	34.2	S	0.000278 U	0.000245 U	**0.0292**	0.000516 U	0.000314 U	0.000318 U	0.000926 U	**0.00590**	0.000454 U	0.00284 U	0.000346 U	0.000830 U
	B-239-10	4/3/18	PES	ESC	10	29.2	S	0.000276 U	0.000243 U	**0.509**	0.000512 U	**0.000619 J**	0.000315 U	0.000918 U	**0.104**	0.000451 U	0.00282 U	**0.0159**	0.000824 U
	B-239-15	4/3/18	PES	ESC	15	24.2	S	0.000266 U	0.000235 U	**0.133**	0.000494 U	0.000301 U	0.000304 U	0.000886 U	**0.0428**	0.000435 U	0.00272 U	**0.00479**	0.000795 U
	B-239-20	4/3/18	PES	ESC	20	19.2	S	0.000264 U	0.000232 U	**0.00688**	0.000490 U	0.000298 U	0.000301 U	0.000878 U	**0.000781 J**	0.000431 U	0.00270 U	0.000328 U	0.000788 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
B-239 (continued)	B-239-25	4/3/18	PES	ESC	25	14.2	S	0.000268 U	0.000236 U	**0.00259**	0.000497 U	0.000302 U	0.000306 U	0.000891 U	**0.000327 J**	0.000438 U	0.00274 U	0.000333 U	0.000800 U
	B-239-35	4/3/18	PES	ESC	35	4.2	S	0.000253 U	0.000223 U	**0.0330**	0.000470 U	0.000286 U	0.000289 U	0.000842 U	**0.00550**	0.000414 U	0.00259 U	**0.000632 J**	0.000756 U
	B-239-40	4/3/18	PES	ESC	40	-0.8	S	0.000265 U	0.000234 U	**0.0414**	0.000492 U	0.000299 U	0.000303 U	0.000883 U	**0.00626**	0.000433 U	0.00271 U	**0.000769 J**	0.000792 U
	B-239-45	4/3/18	PES	ESC	45	-5.8	S	0.000262 U	0.000231 U	**0.000534 J**	0.000486 U	0.000296 U	0.000299 U	0.000871 U	0.000313 U	0.000428 U	0.00268 U	**0.000390 J**	0.000782 U
	B-239-50	4/3/18	PES	ESC	50	-10.8	S	0.000258 U	0.000228 U	**0.000777 J**	0.000479 U	0.000292 U	0.000295 U	0.000859 U	0.000308 U	0.000422 U	0.00264 U	0.000321 U	0.000771 U
	B-909-50	4/3/18	PES	ESC	50 (dup)	-10.8	S	0.000260 U	0.000229 U	**0.000448 J**	0.000482 U	0.000293 U	0.000297 U	0.000865 U	0.000310 U	0.000424 U	0.00266 U	0.000323 U	0.000776 U
	B-239-55	4/3/18	PES	ESC	55	-15.8	S	0.000266 U	0.000234 U	0.000314 U	0.000494 U	0.000300 U	0.000304 U	0.000885 U	0.000317 U	0.000435 U	0.00272 U	0.000331 U	0.000794 U
	B-239-60	4/3/18	PES	ESC	60	-20.8	S	0.000262 U	0.000230 U	0.000309 U	0.000485 U	0.000295 U	0.000299 U	0.000870 U	0.000312 U	0.000427 U	0.00267 U	0.000325 U	0.000781 U
	B-239-65	4/3/18	PES	ESC	65	-25.8	S	0.000262 U	0.000230 U	0.000308 U	0.000485 U	0.000295 U	0.000298 U	0.000870 U	0.000312 U	0.000427 U	0.00267 U	0.000325 U	0.000780 U
	B-239-70	4/3/18	PES	ESC	70	-30.8	S	0.000261 U	0.000229 U	**0.000926 J**	0.000483 U	0.000294 U	0.000297 U	0.000867 U	0.000311 U	0.000426 U	0.00266 U	0.000324 U	0.000778 U
	B-239-75	4/3/18	PES	ESC	75	-35.8	S	0.000270 U	0.000237 U	0.000318 U	0.000500 U	0.000304 U	0.000308 U	0.000897 U	0.000322 U	0.000440 U	0.00275 U	0.000335 U	0.000805 U
	B-239-80	4/3/18	PES	ESC	80	-40.8	S	0.000268 U	0.000236 U	0.000316 U	0.000497 U	0.000302 U	0.000306 U	0.000890 U	0.000319 U	0.000437 U	0.00274 U	0.000333 U	0.000799 U
B-240	B-240-5	4/2/18	PES	ESC	5	34.2	S	0.000258 U	0.000227 U	**0.0231**	0.000479 U	0.000291 U	0.000295 U	0.000859 U	0.000308 U	0.000422 U	0.00264 U	0.000321 U	0.000770
	B-240-10	4/2/18	PES	ESC	10	29.2	S	0.000258 U	0.000227 U	**1.25**	0.000478 U	**0.000635 J**	0.000294 U	0.000858 U	**0.0141**	0.000421 U	0.00263 U	**0.0427**	0.000770 U
	B-240-15	4/2/18	PES	ESC	15	24.2	S	0.000268 U	0.000236 U	**53.7**	0.000498 U	**0.000802 J**	0.000306 U	0.000893 U	**0.118**	0.000438 U	0.00274 U	**0.00418**	0.000801 U
	B-240-20	4/2/18	PES	ESC	20	19.2	S	0.000272 U	0.000240 U	**6.75**	0.000505 U	**0.000619 J**	0.000311 U	0.000906 U	**0.0715 J**	0.000445 U	0.00278 U	**0.0268**	0.000813 U
	B-240-25	4/2/18	PES	ESC	25	14.2	S	0.0131 U	0.0115 U	**5.18**	0.0242 U	0.0147 U	0.0150 U	0.0435 U	**0.214**	0.0213 U	0.134 U	**0.0421 J**	0.0390 U
	B-240-30	4/2/18	PES	ESC	30	9.2	S	0.000282 U	0.000248 U	**5.51**	0.000523 U	**0.00143**	0.000322 U	0.000937 U	**0.352**	0.000460 U	0.00288 U	**0.0480**	0.000841 U
	B-240-35	4/2/18	PES	ESC	35	4.2	S	0.000281 U	0.000247 U	**5.53**	0.000521 U	**0.00131**	0.000321 U	0.000934 U	**0.290**	0.000459 U	0.00287 U	**0.0447**	0.000838 U
	B-240-42	4/2/18	PES	ESC	42	-2.8	S	0.000252 U	0.000222 U	**0.204**	0.000467 U	0.000284 U	0.000287 U	0.000838 U	0.00751 UJ	0.000411 U	0.00257 U	**0.00225**	0.000751 U
	B-240-45	4/2/18	PES	ESC	45	-5.8	S	0.000248 U	0.000218 U	**0.00137**	0.000460 U	0.000280 U	0.000283 U	0.000825 U	0.000296 U	0.000405 U	0.00253 U	0.000309 U	0.000740 U
	B-240-50	4/2/18	PES	ESC	50	-10.8	S	0.000264 U	0.000232 U	0.000311 U	0.000489 U	0.000297 U	0.000301 U	0.000876 U	0.000314 U	0.000430 U	0.00269 U	0.000328 U	0.000786 U
	B-240-55	4/2/18	PES	ESC	55	-15.8	S	0.000271 U	0.000239 U	**0.0161**	0.000503 U	0.000306 U	0.000310 U	0.000903 U	**0.000513 J**	0.000443 U	0.00277 U	**0.000654 J**	0.000810 U
	B-240-60	4/2/18	PES	ESC	60	-20.8	S	0.000272 U	0.000240 U	**0.0323**	0.000505 U	0.000307 U	0.000311 U	0.000906 U	**0.00223**	0.000445 U	0.00278 U	**0.00133**	0.000813 U
	B-240-65	4/2/18	PES	ESC	65	-25.8	S	0.000254 U	0.000223 U	**0.0171**	0.000471 U	0.000286 U	0.000289 U	0.000844 U	**0.000760 J**	0.000414 U	0.00259 U	**0.000410 J**	0.000757 U
	B-240-70	4/2/18	PES	ESC	70	-30.8	S	0.000271 U	0.000238 U	**0.0621**	0.000502 U	0.000305 U	0.000309 U	0.000900 U	**0.00454**	0.000442 U	0.00277 U	**0.00117**	0.000808 U
	B-240-75	4/2/18	PES	ESC	75	-35.8	S	0.000257 U	0.000226 U	**0.00162**	0.000477 U	0.000290 U	0.000293 U	0.000854 U	**0.000773 J**	0.000420 U	0.00262 U	0.000320 U	0.000767 U
	B-240-80	4/2/18	PES	ESC	80	-40.8	S	0.000266 U	0.000234 U	**0.000376 J**	0.000494 U	0.000300 U	0.000304 U	0.000885 U	0.000317 U	0.000435 U	0.00272 U	0.000331 U	0.000794 U
B-241	B-241-5	4/4/18	PES	ESC	5	34.1	S	0.000254 U	0.000223 U	**0.0428**	**0.0139**	0.000286 U	0.000290 U	0.000844 U	**0.00500**	0.000414 U	0.00259 U	0.000316 U	**4.11**
	B-241-10	4/4/18	PES	ESC	10	29.1	S	0.000265 U	0.000234 U	**0.00116**	0.000492 U	**0.000357 J**	0.000303 U	0.000882 U	**0.000459 J**	0.000433 U	0.00271 U	**0.00320**	0.000791 U
	B-241-15	4/4/18	PES	ESC	15	24.1	S	0.000261 U	0.000230 U	**0.00106 J**	0.000484 U	0.000295 U	0.000298 U	0.000868 U	**0.000424 J**	0.000426 U	0.00267 U	**0.00335**	0.000779 U
	B-241-20	4/4/18	PES	ESC	20	19.1	S	0.000285 U	0.000251 U	**0.0273**	0.000528 U	**0.00274**	0.000325 U	0.000947 U	**0.0525**	0.000465 U	0.00291 U	**0.0648**	0.000849 U
	B-241-25	4/4/18	PES	ESC	25	14.1	S	0.000264 U	0.000233 U	**0.0148**	0.000491 U	0.000298 U	0.000302 U	0.000879 U	**0.00615**	0.000432 U	0.00270 U	**0.00779**	0.000789 U
	B-241-30	4/3/18	PES	ESC	30	9.1	S	0.000262 U	0.000231 U	**0.0422**	0.000487 U	**0.00315**	0.000299 U	0.000873 U	**0.0721**	0.000428 U	0.00268 U	**0.107**	0.000783 U
	B-241-35	4/3/18	PES	ESC	35	4.1	S	0.000271 U	0.000238 U	**0.00290 J+**	0.000502 U	**0.00103 J+**	0.000309 U	0.000901 U	**0.000891 J+**	0.000442 U	0.00277 U	**0.0114**	0.000808 U
	B-241-40	4/3/18	PES	ESC	40	-0.9	S	0.000257 U	0.000226 U	**0.00525**	0.000476 U	0.000290 U	0.000293 U	0.000854 U	**0.00280**	0.000419 U	0.00262 U	**0.00660**	0.000766 U
	B-241-45	4/3/18	PES	ESC	45	-5.9	S	0.000258 U	0.000227 U	**0.0263 J+**	0.000478 U	**0.0398**	0.000294 U	0.000856 U	**0.00580 J+**	0.000421 U	0.00263 U	**1.14**	0.000768 U
	B-241-50	4/4/18	PES	ESC	50	-10.9	S	0.000264 U	0.000232 U	**28.3**	0.000489 U	**0.0330**	0.000301 U	0.000877 U	**4.69**	0.000430 U	0.00269 U	**0.488**	0.000787 U
	B-241-55	4/4/18	PES	ESC	55	-15.9	S	0.000272 U	0.000240 U	**7.75**	0.000505 U	**0.00119**	0.000311 U	0.000906 U	**2.11**	0.000445 U	0.00278 U	**0.0575**	0.000813 U
	B-241-60	4/3/18	PES	ESC	60	-20.9	S	0.000262 U	0.000231 U	**0.0191**	0.000486 U	0.000296 U	0.000299 U	0.000871 U	**0.00284**	0.000428 U	0.00268 U	**0.00382**	0.000782 U
	B-241-65	4/3/18	PES	ESC	65	-25.9	S	0.000277 U	0.000244 U	**17.2**	**0.000883 J**	**0.000642 J**	0.000316 U	0.000921 U	**0.699**	0.000452 U	0.00283 U	**0.0156**	0.000826 U
	B-241-70	4/3/18	PES	ESC	70	-30.9	S	0.000270 U	0.000238 U	**0.0301**	0.000501 U	0.000305 U	0.000308 U	0.000898 U	**0.00161**	0.000441 U	0.00276 U	**0.00422**	0.000806 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
B-241	B-241-75	4/3/18	PES	ESC	75	-35.9	S	0.000273 U	0.000240 U	**0.147 J+**	0.000506 U	**0.000813 J+**	0.000311 U	0.000907 U	**0.0513 J+**	0.000445 U	0.00279 U	**0.0301 J+**	0.000814 U
(continued)	B-241-80	4/4/18	PES	ESC	80	-40.9	S	0.000269 U	0.000237 U	**0.0295**	0.000499 U	0.000303 U	0.000307 U	0.000894 U	**0.00759**	0.000439 U	0.00275 U	**0.00387**	0.000802 U
B-242	B-242-5	4/4/18	PES	ESC	5	33.8	S	0.000254 U	0.000224 U	**0.0116**	0.000471 U	0.000287 U	0.000290 U	0.000844 U	**0.00647**	0.000415 U	0.00259 U	0.000316 U	0.000758 U
	B-242-10	4/4/18	PES	ESC	10	28.8	S	0.000256 U	0.000225 U	**0.0783**	0.000475 U	0.000289 U	0.000292 U	0.000852 U	**0.00835**	0.000418 U	0.00262 U	0.000319 U	0.000764 U
	B-242-15	4/4/18	PES	ESC	15	23.8	S	0.000273 U	0.000240 U	**1.97**	0.000506 U	0.000308 U	0.000311 U	0.000907 U	**0.0304**	0.000445 U	0.00279 U	0.000339 U	0.000814 U
	B-242-20	4/4/18	PES	ESC	20	18.8	S	0.000265 U	0.000233 U	**6.61**	0.000492 U	0.000299 U	0.000303 U	0.000881 U	**0.0335**	0.000433 U	0.00271 U	0.000330 U	0.000791 U
	B-242-25	4/4/18	PES	ESC	25	13.8	S	0.0258 U	0.0227 U	**2.05**	0.0478 U	0.0291 U	0.0294 U	0.0858 U	0.0308 U	0.0421 U	0.263 U	0.0321 U	0.0769 U
	B-242-30	4/4/18	PES	ESC	30	8.8	S	0.000262 U	0.000230 U	**0.205**	0.000485 U	0.000295 U	0.000299 U	0.000870 U	**0.000348 J**	0.000427 U	0.00267 U	**0.00828**	0.000781 U
	B-242-35	4/4/18	PES	ESC	35	3.8	S	0.000269 U	0.000237 U	**0.00754**	0.000500 U	0.000304 U	0.000307 U	0.000896 U	0.000321 U	0.000440 U	0.00275 U	0.000335 U	0.000804 U
	B-242-40	4/4/18	PES	ESC	40	-1.2	S	0.000256 U	0.000225 U	**0.0298**	0.000475 U	0.000289 U	0.000292 U	0.000851 U	**0.00181**	0.000418 U	0.00261 U	**0.000782 J**	0.000764 U
	B-242-45	4/4/18	PES	ESC	45	-6.2	S	0.000271 U	0.000238 U	**0.00909**	0.000502 U	0.000305 U	0.000309 U	0.000900 U	0.000323 U	0.000442 U	0.00276 U	0.000337 U	0.000807 U
	B-242-50	4/4/18	PES	ESC	50	-11.2	S	0.000262 U	0.000231 U	**0.0273**	0.000486 U	0.000296 U	0.000299 U	0.000871 U	0.000312 U	0.000428 U	0.00268 U	0.000326 U	0.000782 U
	B-910-50	4/4/18	PES	ESC	50 (dup)	-11.2	S	0.000263 U	0.000231 U	**0.0276**	0.000487 U	0.000296 U	0.000300 U	0.000873 U	0.000313 U	0.000429 U	0.00268 U	0.000326 U	0.000783 U
	B-242-55	4/4/18	PES	ESC	55	-16.2	S	0.000257 U	0.000226 U	**0.0300**	0.000477 U	0.000290 U	0.000293 U	0.000855 U	0.000306 U	0.000420 U	0.00263 U	0.000320 U	0.000767 U
	B-242-60	4/4/18	PES	ESC	60	-21.2	S	0.000258 U	0.000227 U	**0.0303**	0.000479 U	0.000291 U	0.000294 U	0.000858 U	0.000308 U	0.000421 U	0.00264 U	0.000321 U	0.000770 U
	B-242-65	4/4/18	PES	ESC	65	-26.2	S	0.000253 U	0.000223 U	**0.00172**	0.000470 U	0.000286 U	0.000289 U	0.000843 U	0.000302 U	0.000414 U	0.00259 U	0.000315 U	0.000756 U
	B-242-70	4/4/18	PES	ESC	70	-31.2	S	0.000268 U	0.000236 U	0.000316 U	0.000497 U	0.000302 U	0.000306 U	0.000891 U	0.000320 U	0.000438 U	0.00274 U	0.000333 U	0.000799 U
	B-242-75	4/4/18	PES	ESC	75	-36.2	S	0.000260 U	0.000229 U	**0.0478 J+**	0.000481 U	0.000293 U	0.000296 U	0.000863 U	**0.000770 J+**	0.000424 U	0.00265 U	0.000323 U	0.000774 U
	B-242-80	4/4/18	PES	ESC	80	-41.2	S	0.000271 U	0.000239 U	**0.00122**	0.000503 U	0.000306 U	0.000309 U	0.000901 U	0.000323 U	0.000443 U	0.00277 U	0.000337 U	0.000809 U
B-243	B-243-5	3/29/18	PES	ESC	5	34.9	S	0.000272 U	0.000239 U	**0.0560**	0.000504 U	0.000307 U	0.000310 U	0.000904 U	0.000324 U	0.000444 U	0.00278 U	0.000338 U	0.000811 U
	B-243-10	3/29/18	PES	ESC	10	29.9	S	0.000266 U	**0.000445 J**	**6.96**	0.000493 U	0.000300 U	0.000303 U	0.000884 U	**0.00115**	0.000434 U	0.00271 U	0.000331 U	0.000793 U
	B-243-15	3/29/18	PES	ESC	15	24.9	S	0.00662 U	0.00583 U	**0.888**	0.0122 U	0.00747 U	0.00756 U	0.0220 U	0.00790 U	0.0108 U	0.0677 U	0.00824 U	0.0197 U
	B-243-20	3/29/18	PES	ESC	20	19.9	S	0.000270 U	0.000238 U	**25.3**	0.000500 U	0.000304 U	0.000308 U	0.000897 U	**0.0563 J+**	0.000440 U	0.00276 U	0.000336 U	0.000805 U
	B-243-25	3/29/18	PES	ESC	25	14.9	S	0.000261 U	0.000230 U	**6.66**	0.000484 U	0.000294 U	0.000298 U	0.000867 U	**0.0547**	0.000426 U	0.00266 U	0.000324 U	0.000778 U
	B-243-30	3/29/18	PES	ESC	30	9.9	S	0.000255 U	0.000224 U	**6.12**	0.000473 U	0.000287 U	0.000291 U	0.000847 U	**0.0763**	0.000416 U	0.00260 U	0.000317 U	0.000760 U
	B-243-35	3/29/18	PES	ESC	35	4.9	S	0.000259 U	0.000228 U	**11.0**	0.000481 U	0.000292 U	0.000296 U	0.000862 U	**0.0967**	0.000423 U	0.00265 U	0.000322 U	0.000773 U
	B-243-42	3/29/18	PES	ESC	42	-2.1	S	0.000256 U	0.000225 U	**9.04**	0.000474 U	**0.000783 J**	0.000292 U	0.000850 U	**0.834**	0.000417 U	0.00261 U	**0.0160**	0.000763 U
	B-243-45	3/29/18	PES	ESC	45	-5.1	S	0.000254 U	0.000223 U	**12.2**	0.000470 U	**0.000462 J**	0.000289 U	0.000843 U	**1.87**	0.000414 U	0.00259 U	**0.00310**	0.000756 U
	B-243-50	3/29/18	PES	ESC	50	-10.1	S	0.000270 U	0.000238 U	**29.0 J**	0.000501 U	**0.00868**	0.000308 U	0.000898 U	**7.72**	0.000441 U	0.00276 U	**0.292**	0.000806 U
	IW-908-50	3/29/18	PES	ESC	50 (dup)	-10.1	S	0.000265 U	0.000233 U	**41.0 J**	**0.000500 J**	**0.0113**	0.000302 U	0.000880 U	**6.18**	0.000432 U	0.00270 U	**0.404 J**	0.000790 U
	B-243-55	3/29/18	PES	ESC	55	-15.1	S	0.000253 U	0.000222 U	**14.4**	0.000469 U	**0.00776**	0.000288 U	0.000840 U	**0.0810**	0.000412 U	0.00258 U	**0.307 J**	0.000754 U
	B-243-60	3/29/18	PES	ESC	60	-20.1	S	0.000267 U	0.000235 U	**10.3**	0.000496 U	**0.00479**	0.000305 U	0.000889 U	**2.34**	0.000437 U	0.00273 U	**0.181 J**	0.000798 U
	B-243-65	3/29/18	PES	ESC	65	-25.1	S	0.000257 U	0.000226 U	**1.49**	0.000477 U	**0.000888 J**	0.000293 U	0.000854 U	**0.205**	0.000420 U	0.00262 U	0.0607 UJ	0.000767 U
	B-243-70	3/29/18	PES	ESC	70	-30.1	S	0.000271 U	0.000239 U	**0.00378**	0.000503 U	0.000306 U	0.000310 U	0.000902 U	0.000323 U	0.000443 U	0.00277 U	**0.00207**	0.000809 U
	B-243-75	3/29/18	PES	ESC	75	-35.1	S	0.000279 U	0.000245 U	**0.0290**	0.000517 U	0.000315 U	0.000318 U	0.000927 U	**0.00173**	0.000455 U	0.00285 U	0.000347 U	0.000832 U
	B-243-80	3/29/18	PES	ESC	80	-40.1	S	0.000284 U	0.000250 U	**0.0300**	0.000527 U	0.000321 U	0.000324 U	0.000945 U	**0.00253**	0.000464 U	0.00290 U	**0.000385 J**	0.000848 U
B-244	B-244-5	3/28/18	PES	ESC	5	33.8	S	0.000295 U	0.000260 U	**0.0205**	**0.00127 J**	0.000333 U	0.000337 U	0.000982 U	**0.00511**	0.000482 U	0.00302 U	**0.00137**	**0.00133 J**
	B-244-10	3/28/18	PES	ESC	10	28.8	S	0.000279 U	0.000245 U	**0.00727**	**0.000594 J**	0.000315 U	0.000318 U	0.000927 U	**0.000767 J**	0.000455 U	0.00285 U	**0.000526 J**	0.000832 U
	B-244-15	3/28/18	PES	ESC	15	23.8	S	0.000267 U	0.000235 U	**0.00254**	0.000495 U	0.000301 U	0.000305 U	0.000888 U	**0.000615 J**	0.000436 U	0.00273 U	**0.00102 J**	0.000796 U
	B-244-20	3/28/18	PES	ESC	20	18.8	S	0.000265 U	0.000234 U	**0.000760 J**	0.000492 U	**0.000309 J**	0.000303 U	0.000883 U	**0.00185**	0.000433 U	0.00271 U	**0.000575 J**	0.000792 U
	B-244-25	3/28/18	PES	ESC	25	13.8	S	0.000248 U	0.000218 U	0.000292 U	0.000459 U	0.000280 U	0.000283 U	0.000824 U	**0.000296 J**	0.000404 U	0.00253 U	**0.00150**	0.000739 U
	B-244-30	3/28/18	PES	ESC	30	8.8	S	0.000256 U	0.000225 U	**0.00210**	0.000475 U	**0.00106 J**	0.000292 U	0.000851 U	0.000305 U	0.000418 U	0.00261 U	**0.00144**	0.000763 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
B-244 (continued)	B-244-35	3/28/18	PES	ESC	35	3.8	S	0.000269 U	0.000237 U	**0.0158**	0.000498 U	**0.00211**	0.000307 U	0.000894 U	**0.00357**	0.000439 U	0.00275 U	**0.00668**	0.000802 U
	B-244-40	3/28/18	PES	ESC	40	-1.2	S	0.000258 U	0.000227 U	**0.00131**	0.000479 U	**0.0665**	0.000294 U	0.000858 U	**0.000382 J**	0.000421 U	0.00264 U	**1.35**	0.000770 U
	B-244-42	3/28/18	PES	ESC	42	-3.2	S	0.00658 U	0.00579 U	**0.237**	0.0122 U	**0.0882 J**	0.00752 U	0.0218 U	**0.0208 J**	0.0107 U	0.0673 U	**0.256**	0.0196 U
	B-244-45	3/28/18	PES	ESC	45	-6.2	S	0.000263 U	0.000232 U	**0.0323**	0.000488 U	**0.0619**	0.000301 U	0.000876 U	**0.0212**	0.000430 U	0.00269 U	**0.858**	0.000786 U
	B-244-50	3/28/18	PES	ESC	50	-11.2	S	0.000259 U	0.000228 U	**0.0352**	0.000480 U	**0.0339**	0.000295 U	0.000860 U	**0.0107**	0.000422 U	0.00264 U	**0.0824**	0.000772 U
	B-244-55	3/28/18	PES	ESC	55	-16.2	S	0.000258 U	0.000227 U	**0.0635**	0.000478 U	**0.0502**	0.000294 U	0.000857 U	**0.0408**	0.000421 U	0.00263 U	**0.0120**	0.000769 U
	B-244-60	3/28/18	PES	ESC	60	-21.2	S	0.000261 U	0.000230 U	**5.05**	0.000485 U	**0.0297**	0.000298 U	0.000869 U	**0.127**	0.000426 U	0.00267 U	**0.0104**	0.000779 U
	B-244-65	3/28/18	PES	ESC	65	-26.2	S	0.000265 U	0.000234 U	**0.504**	**0.000670 J**	**0.0169**	0.000303 U	0.000882 U	**0.0970**	0.000433 U	0.00271 U	**0.0244**	0.000791 U
	B-244-70	3/28/18	PES	ESC	70	-31.2	S	0.000254 U	0.000224 U	**0.0620 J**	0.000471 U	**0.0240**	0.000290 U	0.000845 U	**0.0320 J**	0.000415 U	0.00259 U	**0.00878 J**	0.000758 U
	IW-907-70	3/28/18	PES	ESC	70 (dup)	-31.2	S	0.000255 U	0.000224 U	**0.0176 J**	0.000472 U	**0.0209**	0.000291 U	0.000847 U	**0.00987 J**	0.000416 U	0.00260 U	**0.0139 J**	0.000760 U
	B-244-75	3/28/18	PES	ESC	75	-36.2	S	0.000268 U	0.000236 U	**0.00375**	0.000498 U	**0.00337**	0.000306 U	0.000892 U	**0.00183**	0.000438 U	0.00274 U	**0.0252**	0.000801 U
	B-244-80	3/28/18	PES	ESC	80	-41.2	S	0.000272 U	0.000239 U	**0.00219**	0.000505 U	**0.000314 J**	0.000310 U	0.000904 U	**0.000678 J**	0.000444 U	0.00278 U	**0.00399**	0.000811 U
B-245	B-245-5	3/28/18	PES	ESC	5	34.9	V	0.000255 U	0.000224 U	**0.00371**	0.000472 U	0.000287 U	0.000291 U	0.000847 U	0.000304 U	0.000416 U	0.00260 U	**0.00142**	0.000760 U
	B-245-10	3/28/18	PES	ESC	10	29.9	S	0.000268 U	0.000236 U	**0.00419**	0.000498 U	0.000303 U	0.000306 U	0.000893 U	0.000320 U	0.000438 U	0.00274 U	0.000334 U	0.000801 U
	B-245-15	3/28/18	PES	ESC	15	24.9	S	0.000271 U	0.000239 U	**0.0317**	0.000503 U	0.000306 U	0.000309 U	0.000902 U	**0.00188**	0.000443 U	0.00277 U	**0.000458 J**	0.000809 U
	B-245-20	3/28/18	PES	ESC	20	19.9	S	0.000253 U	0.000222 U	**0.00746**	0.000469 U	0.000285 U	0.000288 U	0.000840 U	**0.000868 J**	0.000413 U	0.00258 U	**0.000458 J**	0.000754 U
	B-245-25	3/28/18	PES	ESC	25	14.9	S	0.000265 U	0.000233 U	**0.00364**	0.000491 U	0.000299 U	0.000302 U	0.000880 U	**0.000464 J**	0.000432 U	0.00270 U	**0.000466 J**	0.000790 U
	B-245-30	3/29/18	PES	ESC	30	9.9	S	0.000504 U	0.000443 U	**0.0737**	0.000934 U	**0.00437**	0.000574 U	0.00166 U	**0.145**	0.000821 U	0.00513 U	**0.224 J**	**0.00150**
	B-245-35	3/29/18	PES	ESC	35	4.9	S	0.000263 U	0.000232 U	**0.00623**	0.000488 U	0.000297 U	0.000300 U	0.000875 U	**0.00152**	0.000430 U	0.00269 U	**0.0194**	0.000785 U
	B-245-40	3/29/18	PES	ESC	40	-0.1	S	0.000260 U	0.000229 U	**0.0149**	0.000483 U	0.000294 U	0.000297 U	0.000866 U	**0.00287**	0.000425 U	0.00266 U	**0.0204**	0.000777 U
	B-245-45	3/29/18	PES	ESC	45	-5.1	S	0.000260 U	0.000229 U	**0.00112**	0.000482 U	0.000293 U	0.000297 U	0.000865 U	**0.000720 J**	0.000425 U	0.00266 U	**0.00491**	0.000776 U
	B-245-50	3/29/18	PES	ESC	50	-10.1	S	0.000265 U	0.000233 U	**0.00546**	0.000492 U	0.000299 U	0.000303 U	0.000882 U	**0.00370**	0.000433 U	0.00271 U	**0.0398**	0.000791 U
	B-245-55	3/29/18	PES	ESC	55	-15.1	S	0.000264 U	0.000232 U	**0.00226**	0.000489 U	0.000298 U	0.000301 U	0.000877 U	**0.00313**	0.000431 U	0.00269 U	**0.00776**	0.000787 U
	B-245-60	3/29/18	PES	ESC	60	-20.1	S	0.000251 U	0.000221 U	**0.00176**	0.000465 U	0.000283 U	0.000286 U	0.000833 U	**0.00181**	0.000409 U	0.00256 U	**0.00999**	0.000748 U
	B-245-65	3/29/18	PES	ESC	65	-25.1	S	0.000268 U	0.000236 U	**0.000656 J**	0.000497 U	0.000302 U	0.000305 U	0.000890 U	**0.000449 J**	0.000437 U	0.00273 U	**0.00929**	0.000799 U
	B-245-70	3/29/18	PES	ESC	70	-30.1	S	0.000275 U	0.000242 U	0.000325 U	0.000325 U	0.000311 U	0.000314 U	0.000915 U	0.000328 U	0.000449 U	0.00281 U	**0.00151**	0.000821 U
	B-245-75	3/29/18	PES	ESC	75	-35.1	S	0.000264 U	0.000232 U	0.000311 U	0.000489 U	0.000298 U	0.000301 U	0.000877 U	0.000314 U	0.000431 U	0.00269 U	**0.000623 J**	0.000787 U
	B-245-80	3/29/18	PES	ESC	80	-40.1	S	0.000271 U	0.000239 U	0.000320 U	0.000503 U	0.000306 U	0.000309 U	0.000901 U	0.000323 U	0.000443 U	0.00277 U	**0.000863 J**	0.000809 U
B-246	B-246-6	5/11/18	PES	ESC	6	33.9	S	0.00324 U	0.00184 U	**0.00396**	0.00148 U	0.00170 U	0.00182 U	0.00166 U	**0.00192**	0.000593 U	0.00418 U	0.000811 U	0.00567 U
	B-246-11	5/11/18	PES	ESC	11	28.9	S	0.00322 U	0.00183 U	**0.0271**	0.00148 U	0.00169 U	0.00181 U	0.00165 U	**0.00638**	0.000590 U	0.00416 U	0.000807 U	0.00564 U
	B-246-15	5/11/18	PES	ESC	15	24.9	S	0.00309 U	0.00175 U	**0.0616**	**0.00318 J**	0.00162 U	0.00173 U	0.00158 U	**0.0132**	0.000565 U	0.00398 U	0.000772 U	0.00540 U
	B-246-25	5/11/18	PES	ESC	25	14.9	S	0.00305 U	0.00173 U	**12.7**	0.00214 UJ	**0.00745**	0.00171 U	0.00157 U	**0.448**	0.000559 U	0.00394 U	0.000764 U	0.00534 U
	B-246-30	5/11/18	PES	ESC	30	9.9	S	0.00321 U	0.00182 U	**6.98**	**0.00172 J**	**0.00860**	0.00180 U	0.00165 U	**0.162**	0.000588 U	0.00414 U	**0.0308**	0.00563 U
	B-246-35	5/11/18	PES	ESC	35	4.9	S	0.00315 U	0.00179 U	**0.00548**	0.00144 U	0.00165 U	0.00176 U	0.00161 U	0.000461 U	0.000576 U	0.00406 U	0.000787 U	0.00551 U
	B-246-40	5/11/18	PES	ESC	40	-0.1	S	0.00309 U	0.00176 U	**4.07**	0.00142 U	0.00162 U	0.00173 U	0.00159 U	**0.280**	0.000566 U	0.00399 U	**0.00735**	0.00541 U
	B-246-43	5/11/18	PES	ESC	43	-3.1	S	0.00299 U	0.00169 U	**0.00312**	**0.00143 J**	0.00156 U	0.00167 U	0.00153 U	**0.00780**	0.000547 U	0.00385 U	**0.00339**	0.00523 U
	B-246-45	5/11/18	PES	ESC	45	-5.1	S	0.00329 U	0.00187 U	0.000836 U	**0.00477 J**	0.00172 U	0.00185 U	0.00169 U	**0.000999 J**	0.000603 U	0.00424 U	0.000823 U	0.00576 U
	B-246-50	5/11/18	PES	ESC	50	-10.1	S	0.00307 U	0.00174 U	**0.00576**	**0.00215 J**	0.00161 U	0.00172 U	0.00158 U	**0.000767 J**	0.000563 U	0.00396 U	0.000768 U	0.00538 U
	B-246-55	5/11/18	PES	ESC	55	-15.1	S	0.00313 U	0.00177 U	**0.00372**	**0.00446 J**	0.00164 U	0.00175 U	0.00160 U	**0.000650 J**	0.000573 U	0.00403 U	0.000782 U	0.00547 U
	B-246-60	5/11/18	PES	ESC	60	-20.1	S	0.00310 U	0.00176 U	**0.00493**	**0.00208 J**	0.00162 U	0.00174 U	0.00159 U	**0.000723 J**	0.000567 U	0.00399 U	0.000775 U	0.00542 U
	B-246-65	5/11/18	PES	ESC	65	-25.1	S	0.00338 U	0.00192 U	**0.00178 J**	**0.00178 J**	0.00177 U	0.00189 U	0.00173 U	0.000495 U	0.000618 U	0.00435 U	**0.0154**	0.00591 U
	B-246-70	5/11/18	PES	ESC	70	-30.1	S	0.00303 U	0.00172 U	**0.223 J**	**0.00520 J**	0.00159 UJ	0.00170 U	0.00156 U	**0.239 J**	0.000556 U	0.00391 U	**0.00822 J**	0.00531 UJ

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
B-246 (continued)	B-246-75	5/11/18	PES	ESC	75	-35.1	S	0.00316 U	0.00180 U	**0.00130 J**	**0.00494 J**	0.00166 U	0.00177 U	0.00162 U	0.000463 U	0.000579 U	0.00408 U	0.000791 U	0.00554 U
	B-246-80	5/11/18	PES	ESC	80	-40.1	S	0.00308 U	0.00175 U	0.000791 U	0.00141 U	0.00162 U	0.00173 U	0.00158 U	0.000452 U	0.000565 U	0.00398 U	0.000771 U	0.00540 U
	B-926-100	5/11/18	PES	ESC	45 (dup)	-5.1	S	0.00409 U	0.00232 U	**0.0144 J**	**0.00231 J**	0.00214 UJ	0.00230 U	0.00210 U	**0.00359 J**	0.000749 U	0.00527 U	0.00102 UJ	0.00716 UJ
B-247	B-247-5	4/20/18	PES	ESC	5	34.7	S	0.000266 U	0.000234 U	**0.0594**	0.000493 U	**0.000491 J**	0.000303 U	0.000883 U	**0.00692**	0.000434 U	0.00271 U	**0.00114**	0.000792 U
	B-247-10	4/20/18	PES	ESC	10	29.7	S	0.000269 U	0.000237 U	**0.00586**	0.000500 U	0.000304 U	0.000307 U	0.000896 U	**0.00175**	0.000440 U	0.00275 U	**0.00173**	0.000804 U
	B-247-15	4/20/18	PES	ESC	15	24.7	S	0.000260 U	0.000228 U	**0.00415**	0.000481 U	0.000293 U	0.000296 U	0.000863 U	**0.00482**	0.000424 U	0.00265 U	**0.00221**	0.000774 U
	B-247-20	4/20/18	PES	ESC	20	19.7	S	0.000261 U	0.000230 U	**0.00432**	0.000485 U	0.000295 U	0.000298 U	0.000869 U	**0.000887 J**	0.000427 U	0.00267 U	**0.00718**	0.000779 U
	B-247-25	4/20/18	PES	ESC	25	14.7	S	0.000255 U	0.000224 U	**0.00244**	0.000472 U	0.000287 U	0.000291 U	0.000847 U	**0.000327 J**	0.000416 U	0.00260 U	**0.000411 J**	0.000759 U
	B-247-30	4/20/18	PES	ESC	30	9.7	S	0.000258 U	0.000227 U	**0.000984 J**	0.000478 U	0.000291 U	0.000294 U	0.000857 U	0.000307 U	0.000421 U	0.00263 U	**0.000651 J**	0.000769 U
	B-247-35	4/20/18	PES	ESC	35	4.7	S	0.000258 U	0.000227 U	**0.00128**	0.000478 U	**0.000452 J**	0.000294 U	0.000857 U	0.000307 U	0.000421 U	0.00263 U	0.000321 U	0.000769 U
	B-247-40	4/20/18	PES	ESC	40	-0.3	S	0.000263 U	0.000231 U	**0.00427**	0.000487 U	**0.000386 J**	0.000300 U	0.000874 U	**0.00104 J**	0.000429 U	0.00268 U	**0.000395 J**	0.000784 U
	B-247-45	4/20/18	PES	ESC	45	-5.3	S	0.000253 U	0.000223 U	**0.00230**	0.000469 U	**0.000306 J**	0.000288 U	0.000841 U	**0.000708 J**	0.000413 U	0.00258 U	**0.00279**	0.000754 U
	B-247-50	4/20/18	PES	ESC	50	-10.3	S	0.000258 U	0.000227 U	0.000304 U	0.000478 U	**0.0711**	0.000294 U	0.000857 U	0.000307 U	0.000421 U	0.00263 U	**0.779**	0.000768 U
	B-247-55	4/20/18	PES	ESC	55	-15.3	S	0.000264 U	0.000233 U	0.000312 U	0.000490 U	**0.000318 J**	0.000302 U	0.000879 U	0.000315 U	0.000432 U	0.00270 U	**0.0367**	0.000788 U
	B-247-60	4/20/18	PES	ESC	60	-20.3	S	0.000252 U	0.000222 U	0.000297 U	0.000468 U	**0.000984 J**	0.000288 U	0.000838 U	0.000301 U	0.000412 U	0.00257 U	**0.0672**	0.000752 U
	B-247-65	4/20/18	PES	ESC	65	-25.3	S	0.000261 U	0.000230 U	**0.00103 J**	0.000484 U	0.000295 U	0.000298 U	0.000868 U	0.000311 U	0.000426 U	0.00267 U	0.000779 U	0.000779 U
	B-247-70	4/20/18	PES	ESC	70	-30.3	S	0.000262 U	0.000231 U	0.000309 U	0.000486 U	0.000296 U	0.000299 U	0.000872 U	0.000313 U	0.000428 U	0.00268 U	0.000326 U	0.000782 U
	B-247-75	4/20/18	PES	ESC	75	-35.3	S	0.000268 U	0.000236 U	0.000316 U	0.000496 U	0.000302 U	0.000305 U	0.000890 U	0.000319 U	0.000437 U	0.00273 U	**0.0123**	0.000798 U
	B-247-80	4/20/18	PES	ESC	80	-40.3	S	0.000262 U	0.000230 U	0.000309 U	0.000485 U	0.000295 U	0.000298 U	0.000870 U	0.000312 U	0.000427 U	0.00267 U	**0.00344**	0.000780 U
	B-909-20	4/20/18	PES	ESC	80 (dup)	-40.3	S	0.000253 U	0.000223 U	0.000299 U	0.000470 U	0.000286 U	0.000289 U	0.000842 U	0.000302 U	0.000413 U	0.00259 U	**0.00310**	0.000756 U
B-248	B-248-5	4/23/18	PES	ESC	5	46.9	V	0.000267 U	0.000235 U	**0.00318**	0.000495 U	0.000301 U	0.000305 U	0.000888 U	0.000318 UJ	0.000436 U	0.00273 U	0.000332 U	0.000797 U
	B-248-10	4/23/18	PES	ESC	10	41.9	V	0.000261 U	0.000230 U	**0.0178**	0.000484 U	0.000294 U	0.000298 U	0.000868 U	**0.00126 J**	0.000426 U	0.00266 U	0.000324 U	0.000778 UJ
	B-248-15	4/23/18	PES	ESC	15	36.9	V	0.00300 U	0.00170 U	**0.118**	0.00137 U	0.00157 U	0.00168 U	0.00154 U	**0.00378**	0.000550 U	0.00387 U	0.000751 U	0.00526 U
	B-248-20	4/23/18	PES	ESC	20	31.9	S	0.000253 U	0.000223 U	**0.0238**	0.00469 U	0.000286 U	0.000289 U	0.000841 U	**0.00233 J**	0.000413 U	0.00258 U	0.000315 U	0.000755 UJ
	B-248-25	4/23/18	PES	ESC	25	26.9	S	0.00320 U	0.00182 U	**0.621**	0.00147 U	0.00168 U	0.00180 U	0.00164 U	**0.0667**	0.000587 U	0.00413 U	0.000801 U	0.00561 U
	B-248-30	4/23/18	PES	ESC	30	21.9	S	0.000253 U	0.000223 U	**0.00255 J**	0.000469 U	0.000285 U	0.000289 U	0.000841 U	**0.00297 J**	0.000413 U	0.00258 U	0.000315 U	0.000755 UJ
	B-248-35	4/23/18	PES	ESC	35	16.9	S	0.00296 U	0.00168 U	**0.122**	**0.00178 J**	0.00155 U	0.00166 U	0.00152 U	**0.0456**	0.000542 U	0.00381 U	0.000740 U	0.00518 U
	B-248-40	4/23/18	PES	ESC	40	11.9	S	0.00304 U	0.00173 U	**0.200**	0.00139 U	0.00159 U	0.00171 U	0.00156 U	**0.0599**	0.000557 U	0.00392 U	**0.00574**	0.00533 U
	B-248-45	4/23/18	PES	ESC	45	6.9	S	0.00312 U	0.00177 U	**0.0248**	**0.00143 J**	0.00163 U	0.00175 U	0.00160 U	**0.00566**	0.000571 U	0.00402 U	0.000780 U	0.00546 U
	B-248-50	4/23/18	PES	ESC	50	1.9	S	0.00298 U	0.00169 U	**0.0109 J-**	**0.00163 J-**	0.00156 UJ	0.00167 U	0.00153 U	**0.00177 J-**	0.000547 U	0.00385 U	0.00167 U	0.00523 UJ
	B-248-55	4/23/18	PES	ESC	55	-3.2	S	0.000277 U	0.000244 U	0.000327 U	0.000514 U	0.000312 U	0.000316 U	0.000921 U	0.000330 UJ	0.000452 U	0.00283 U	0.000344 U	0.000826 UJ
	B-248-60	4/23/18	PES	ESC	60	-8.2	S	0.00293 U	0.00166 U	**0.167**	0.00134 U	**0.0144**	0.00164 U	0.00150 U	**0.0244**	0.000536 U	0.00377 U	**0.0121**	0.00512 U
	B-248-65	4/23/18	PES	ESC	65	-13.2	S	0.00336 U	0.00191 U	0.000861 U	0.00154 U	0.00176 U	0.00188 U	0.00172 U	0.000492 U	0.000615 U	0.00433 U	**0.00629**	0.00588 U
	B-248-70	4/23/18	PES	ESC	70	-18.2	S	0.00314 U	0.00178 U	0.000804 U	0.00144 U	0.00164 U	0.00176 U	0.00161 U	0.000460 U	0.000575 U	0.00404 U	**0.00315**	0.00549 U
	B-248-75	4/23/18	PES	ESC	75	-23.2	S	0.00307 U	0.00174 U	0.000786 UJ	0.00140 UJ	0.00161 UJ	0.00172 U	0.00157 U	0.000449 UJ	0.000562 U	0.00395 U	**0.0124 J-**	0.00537 UJ
	B-248-80	4/23/18	PES	ESC	80	-28.2	S	0.000281 U	0.000248 U	0.000332 UJ	0.000521 U	0.000317 U	0.000321 U	0.000935 U	**0.000439 J**	0.000459 U	0.00287 U	**0.00140**	0.000839 UJ
	B-910-20	4/23/18	PES	ESC	80 (dup)	-28.2	S	0.000289 U	0.000254 U	0.000341 U	0.000536 U	0.000326 U	0.000330 U	0.000960 U	0.000344 UJ	0.000471 U	0.00295 U	**0.000581 J**	0.000861 UJ
	B-248-85	4/23/18	PES	ESC	85	-33.2	S	0.000284 U	0.000250 U	0.000335 U	0.000527 U	0.000321 U	0.000324 U	0.000945 U	0.000339 UJ	0.000464 U	0.00290 U	**0.000378 J**	0.000848 UJ
	B-248-90	4/23/18	PES	ESC	90	-38.2	S	0.000280 U	0.000246 U	0.000330 U	0.000519 U	0.000316 U	0.000319 U	0.000931 U	0.000334 UJ	0.000457 U	0.00286 U	0.000348 U	0.000835 UJ
	B-248-95	4/23/18	PES	ESC	95	-43.2	S	0.000292 U	0.000257 U	0.000344 U	0.000541 U	0.000329 U	0.000333 U	0.000970 U	0.000348 UJ	0.000476 U	0.00298 U	0.000363 U	0.000870 UJ
	B-248-100	4/23/18	PES	ESC	100	-48.2	S	0.000284 U	0.000250 U	0.000335 U	0.000526 U	0.000320 U	0.000324 U	0.000944 U	0.000338 UJ	0.000463 U	0.00290 U	**0.000881 J**	0.000847 UJ
	B-248-105	4/23/18	PES	ESC	105	-53.2	S	0.000253 U	0.000223 U	**0.0102**	0.000469 U	**0.00141**	0.000289 U	0.000841 U	**0.0562 J**	0.000413 U	0.00258 U	0.000314 U	0.000754 UJ

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene ((tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
B-248	B-248-110	4/23/18	PES	ESC	110	-58.2	S	0.00313 U	0.00178 U	0.00185 U	0.00143 U	**0.00379 J**	0.00176 U	0.00161 U	0.0113 U	0.000574 U	0.00404 U	0.000784 U	0.00549 U
(continued)	B-248-115	4/23/18	PES	ESC	115	-63.2	S	0.000274 U	0.000241 U	0.00125 UJ	0.000507 U	0.000309 U	0.000312 U	0.000910 U	**0.00615 J**	0.000447 U	0.00279 U	**0.000418 J**	0.000816 UJ
B-249	B-249-5	10/15/18	PES	PACE	5	34.2	S	0.00285 U	0.00162 U	**0.122 J**	0.00131 U	0.00149 U	0.00160 U	0.00146 U	**0.0109**	0.000523 U	0.00368 U	0.000714 U	0.00500 U
	B-249-8	10/15/18	PES	PACE	8	31.2	S	0.00308 U	0.00175 U	**0.949 J**	0.00141 U	0.00161 U	0.00173 U	0.00158 U	**0.0828**	0.000564 U	0.00397 U	0.000771 U	0.00539 U
	B-249-15	10/15/18	PES	PACE	15	24.2	S	0.00316 U	0.00180 U	**1.97 J**	**0.00236 J**	0.00166 U	0.00177 U	0.00162 U	**0.214**	0.000579 U	0.00408 U	0.000791 U	**0.00973**
	B-249-17	10/15/18	PES	PACE	17	22.2	S	0.00309 U	0.00176 U	**8.35 J**	0.00142 U	0.00162 U	0.00173 U	0.00159 U	**0.150**	0.000566 U	0.00399 U	0.000773 U	0.00541 U
	B-249-20	10/15/18	PES	PACE	20	19.2	S	0.00323 U	0.00183 U	**10.3**	0.00148 U	**0.00420 J**	0.00181 U	0.00165 U	**0.661**	0.000591 U	0.00416 U	0.000807 U	0.00565 U
B-250	B-250-2.5	10/15/18	PES	PACE	2.5	36.9	V	0.00301 U	0.00171 U	**0.701 J**	0.00138 U	0.00158 U	0.00169 U	0.00155 U	**0.00576**	0.000552 U	0.00389 U	0.000754 U	0.00528 U
	B-250-8	10/15/18	PES	PACE	8	31.4	S	0.00304 U	0.00173 U	**1.81 J**	0.00139 U	0.00159 U	0.00170 U	0.00156 U	**0.0269**	0.000557 U	0.00392 U	0.000760 U	0.00532 U
	B-250-10	10/15/18	PES	PACE	10	29.4	S	0.00304 U	0.00172 U	**21.7 J**	0.00139 U	0.00166 **J**	0.00170 U	0.00156 U	**0.0762**	0.000556 U	0.00392 U	0.000760 U	0.00532 U
	B-250-13	10/15/18	PES	PACE	13	26.4	S	0.00307 U	0.00174 U	**18.2 J**	0.00140 U	0.00285 **J**	0.00172 U	0.00157 U	**0.553**	0.000562 U	0.00395 U	0.000767 U	0.00537 U
	B-250-20	10/15/18	PES	PACE	20	19.4	S	0.00316 U	0.00180 U	**8.68 J**	0.00145 U	0.00435 **J**	0.00177 U	0.00162 U	**0.528**	0.000579 U	0.00408 U	**0.00304**	0.00554 U
	B-250-24	10/15/18	PES	PACE	24	15.4	S	0.00299 U	0.00170 U	**7.69**	0.00137 U	0.00344 **J**	0.00167 U	0.00153 U	**0.407**	0.000547 U	0.00385 U	**0.00318**	0.00523 U
	B-250-30	10/16/18	PES	PACE	30	9.4	S	0.00298 U	0.00169 U	**0.288**	**0.00259 J**	**0.0138**	0.00167 U	0.00153 U	**0.0519**	0.000545 U	0.00384 U	**0.358**	0.00521 U
B-251	B-251-5	10/15/18	PES	PACE	5	34.3	S	0.00287 U	0.00163 U	**0.0286**	0.00131 U	0.00150 U	0.00161 U	0.00147 U	**0.146**	0.000525 U	0.00370 U	0.000718 R	0.00502 U
	B-251-8	10/15/18	PES	PACE	8	31.3	S	0.00303 U	0.00172 U	**0.230**	0.00139 U	0.00159 U	0.00170 U	0.00155 U	**0.135**	0.000555 U	0.00390 U	0.000758 U	0.00530 U
	B-251-10	10/15/18	PES	PACE	10	29.3	S	0.00304 U	0.00172 U	**10.3**	0.00139 U	0.00159 U	0.00170 U	0.00156 U	**0.0501**	0.000556 U	0.00392 U	0.000760 U	0.00532 U
	B-251-15	10/15/18	PES	PACE	15	24.3	S	0.00309 U	0.00175 U	**12.0**	0.00141 U	0.00162 U	0.00173 U	0.00158 U	**0.102**	0.000565 U	0.00398 U	0.000772 U	0.00540 U
	B-251-20	10/15/18	PES	PACE	20	19.3	S	0.00320 U	0.00182 U	**6.66**	0.00146 U	0.00167 U	0.00179 U	0.00164 U	**0.154**	0.000586 U	0.00412 U	0.000800 U	0.00560 U
	B-251-25	10/15/18	PES	PACE	25	14.3	S	0.00314 U	0.00178 U	**6.09**	0.00144 U	0.00164 U	0.00176 U	0.00161 U	**0.512**	0.000574 U	0.00404 U	0.000785 U	0.00549 U
B-252	B-252-2.5	10/15/18	PES	PACE	2.5	36.7	V	0.00285 U	0.00162 U	**0.306**	0.00131 U	0.00149 U	0.00160 U	0.00146 U	**0.0201**	0.000522 U	0.00368 U	0.000714 U	0.00499 U
	B-252-8	10/15/18	PES	PACE	8	31.2	S	0.00292 U	0.00166 U	**0.0783**	0.00134 U	0.00153 U	0.00164 U	0.00150 U	**0.0156**	0.000535 U	0.00377 U	0.000731 U	0.00511 U
	B-252-10	10/15/18	PES	PACE	10	29.2	S	0.00303 U	0.00172 U	**0.356**	0.00139 U	0.00159 U	0.00170 U	0.00155 U	**0.0503**	0.000554 U	0.00390 U	0.000757 U	0.00530 U
	B-252-15	10/15/18	PES	PACE	15	24.2	S	0.00322 U	0.00183 U	**3.43**	0.00147 U	0.00168 U	0.00180 U	0.00165 U	**0.682**	0.000589 U	0.00415 U	0.000805 U	0.00563 U
	B-252-19	10/15/18	PES	PACE	19	20.2	S	0.00330 U	0.00187 U	**2.88**	0.00151 U	0.00231 **J**	0.00185 U	0.00169 U	–	0.000603 U	0.00425 U	**0.138 J**	0.00577 U
	B-252-25	10/15/18	PES	PACE	25	14.2	S	0.00300 U	0.00170 U	**1.35**	0.00137 U	0.00157 U	0.00168 U	0.00154 U	**0.266**	0.000549 U	0.00387 U	**0.00602**	0.00525 U
	B-252-29	10/15/18	PES	PACE	29	10.2	S	0.00312 U	0.00177 U	**1.99**	0.00143 U	0.00656	0.00175 U	0.00160 U	**0.483**	0.000572 U	0.00403 U	**0.00634**	0.00547 U
B-253A	B-253A-5	10/18/18	PES	PACE	5	35.6	V	0.00311 U	0.00177 U	**0.0116 J**	**0.00195 J**	0.00163 U	0.00174 U	0.00159 U	**0.0285**	0.000569 U	0.00401 U	0.000778 U	0.00544 U
	B-253A-8	10/18/18	PES	PACE	8	32.6	S	0.00307 U	0.00175 U	**0.917 J**	**0.00193 J**	0.00161 U	0.00172 U	0.00158 U	**0.00621**	0.000563 U	0.00396 U	0.000769 U	0.00538 U
	B-253A-10	10/18/18	PES	PACE	10	30.6	S	0.00299 U	0.00170 U	**2.29 J**	0.00137 U	0.00157 U	0.00168 U	0.00153 U	**0.00740**	0.000548 U	0.00386 U	0.000748 U	0.00524 U
	B-253A-15	10/18/18	PES	PACE	15	25.6	S	0.00307 U	0.00174 U	**15.7 J**	**0.00193 J**	0.00161 U	0.00172 U	0.00157 U	**0.0186 J**	0.000561 U	0.00395 U	0.000767 U	0.00537 U
	B-253A-20	10/18/18	PES	PACE	20	20.6	S	0.00301 U	0.00171 U	**0.868 J**	0.00138 U	0.00158 U	0.00169 U	0.00154 U	**0.00529**	0.000551 U	0.00388 U	0.000752 U	0.00526 U
B-254	B-254-5	10/16/18	PES	PACE	5	34.7	S	0.00327 U	0.00186 U	**9.35**	0.00150 U	0.00171 U	0.00183 U	0.00168 U	**0.0662**	0.000599 U	0.00422 U	0.0654 U	0.00572 U
	B-254-10	10/16/18	PES	PACE	10	29.7	S	0.00310 U	0.00176 U	**3.09**	0.00142 U	0.00162 U	0.00174 U	0.00159 U	**0.0173**	0.000568 U	0.00400 U	**0.0111 J**	0.00543 U
	B-254-13.5	10/16/18	PES	PACE	13.5	26.2	S	0.00320 U	0.00182 U	**42.2**	**0.00152 J**	**0.00740**	0.00179 U	0.00164 U	**0.353**	0.000586 U	0.00413 U	0.320 U	0.00561 U
	B-254-20	10/16/18	PES	PACE	20	19.7	S	0.00294 U	0.00167 U	**28.0**	0.00134 U	**0.00222 J**	0.00165 U	0.00151 U	**0.228**	0.000538 U	0.00379 U	0.147 U	0.00514 U
	B-254-25	10/16/18	PES	PACE	25	14.7	S	0.00305 U	0.00173 U	**46.7**	**0.00321 J**	**0.00449 J**	0.00171 U	0.00156 U	**0.681**	0.000559 U	0.00393 U	0.305 U	0.00534 U
B-254A	B-254A-27	10/19/18	PES	PACE	27	12.7	S	0.00298 U	0.00169 U	**0.0954**	**0.00161 J**	0.00156 U	0.00167 U	0.00152 U	**0.0118**	0.000546 U	0.00385 U	**0.0508**	0.00522 U
	B-254A-30	10/19/18	PES	PACE	30	9.7	S	0.00294 U	0.00167 U	**6.24**	**0.00166 J**	0.00154 U	0.00165 U	0.00151 U	**0.143**	0.000538 U	0.00379 U	0.000735 U	0.00514 U
	B-254A-35	10/19/18	PES	PACE	35	4.7	S	0.00288 U	0.00163 U	**0.0584 J**	0.00132 UJ	0.00151 UJ	0.00161 U	0.00147 U	**0.000679 J**	0.000527 U	0.00371 U	**0.0326 J**	0.00504 UJ
B-255	B-255-3.5	10/16/18	PES	PACE	3.5	36.3	S	0.00312 U	0.00177 U	**0.0927**	0.00143 U	0.00163 U	0.00175 U	0.00160 U	**0.00586**	0.000571 U	0.00402 U	0.000780 U	0.00546 U
	B-255-8	10/16/18	PES	PACE	8	31.8	S	0.00316 U	0.00180 U	**0.0420**	0.00145 U	0.00166 U	0.00177 U	0.00162 U	**0.0342**	0.000579 U	0.00408 U	0.000791 U	0.00554 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
B-255 (continued)	B-255-15	10/16/18	PES	PACE	15	24.8	S	0.00297 U	0.00169 U	**1.23**	0.00136 U	0.00156 U	0.00167 U	0.00153 U	**0.0362**	0.000545 U	0.00384 U	**0.00247 J**	0.00521 U
B-255A	B-255A-21	10/16/18	PES	PACE	21	18.8	S	0.00289 U	0.00164 U	**18.9**	0.00132 U	**0.00577**	0.00162 U	0.00148 U	**3.11**	0.000529 U	0.00373 U	**0.0532 J**	0.00506 U
B-256	B-256-2.5	10/16/18	PES	PACE	2.5	37.1	S	0.00319 U	0.00181 U	**0.0550**	0.00146 U	0.00167 U	0.00179 U	0.00164 U	**0.0532**	0.000585 U	0.00412 U	**0.0123**	0.00559 U
	B-256-5	10/16/18	PES	PACE	5	34.6	S	0.00302 U	0.00171 U	**0.0193**	0.00138 U	0.00158 U	0.00169 U	0.00155 U	**0.0162 J**	0.000552 U	0.00389 U	**0.0155**	0.00528 U
	B-256-10	10/16/18	PES	PACE	10	29.6	S	0.00292 U	0.00166 U	**0.589**	0.00134 U	**0.00197 J**	0.00163 U	0.00150 U	**0.182**	0.000534 U	0.00376 U	**0.0359**	0.00511 U
	B-256-15	10/16/18	PES	PACE	15	24.6	S	0.00302 U	0.00172 U	**0.324**	0.00138 U	**0.00510 J**	0.00169 U	0.00155 U	**0.0863**	0.000553 U	0.00390 U	**0.0715**	0.00529 U
	B-256-18	10/16/18	PES	PACE	18	21.6	S	0.00302 U	0.00172 U	**0.207**	0.00138 U	0.00158 U	0.00169 U	0.00155 U	**0.0126**	0.000553 U	0.00390 U	**0.0170**	0.00529 U
B-257	B-257-5	10/17/18	PES	PACE	5	34.4	S	0.00331 U	0.00188 U	**0.0333**	0.00151 U	0.00173 U	0.00185 U	0.00170 U	**0.0356**	0.000605 U	0.00426 U	**0.00478**	0.00579 U
	B-257-10	10/17/18	PES	PACE	10	29.4	S	0.00305 U	0.00173 U	**1.75**	0.00140 U	**0.00474 J**	0.00171 U	0.00156 U	**0.183**	0.000558 U	0.00393 U	**0.0252**	0.00534 U
	B-257-15	10/17/18	PES	PACE	15	24.4	S	0.00317 U	0.00180 U	**1.26**	0.00145 U	**0.00411 J**	0.00178 U	0.00163 U	**0.134**	0.000581 U	0.00409 U	0.000793 U	0.00555 U
	B-257-20	10/17/18	PES	PACE	20	19.4	S	0.00307 U	0.00174 U	**2.06**	0.00140 U	**0.00652**	0.00172 U	0.00157 U	**0.455**	0.000562 U	0.00396 U	**0.226**	0.00537 U
B-258	B-258-3	10/17/18	PES	PACE	3	36.2	V	0.00299 U	0.00170 U	**0.0198**	0.00137 U	0.00157 U	0.00168 U	0.00153 U	**0.00793**	0.000548 U	0.00386 U	0.000748 U	0.00524 U
	B-258-8	10/17/18	PES	PACE	8	31.2	S	0.00310 U	0.00176 U	**0.0619**	0.00142 U	0.00163 U	0.00174 U	0.00159 U	**0.00635**	0.000569 U	0.00400 U	0.000777 U	0.00544 U
	B-258-10	10/17/18	PES	PACE	10	29.2	S	0.00327 U	0.00185 U	**0.538**	0.00150 U	0.00171 U	0.00183 U	0.00168 U	**0.0149**	0.000598 U	0.00421 U	0.000817 U	0.00572 U
	B-258-15	10/17/18	PES	PACE	15	24.2	S	0.00322 U	0.00183 U	**16.2**	0.00148 U	0.00169 U	0.00181 U	0.00165 U	**0.0763**	0.000590 U	0.00415 U	0.000806 U	0.00564 U
	B-258-20	10/17/18	PES	PACE	20	19.2	S	0.00305 U	0.00173 U	**3.71**	0.00140 U	0.00160 U	0.00171 U	0.00156 U	**0.0117**	0.000558 U	0.00393 U	0.000762 U	0.00533 U
B-259	B-259-2.5	10/17/18	PES	PACE	2.5	36.7	V	0.00307 U	0.00174 U	**0.0784**	**0.00189 J**	0.00161 U	0.00172 U	0.00158 U	**0.00504**	0.000563 U	0.00396 U	0.000769 U	0.00538 U
	B-259-5	10/17/18	PES	PACE	5	34.2	S	0.00299 U	0.00170 U	**0.00933**	0.00137 U	0.00157 U	0.00168 U	0.00153 U	**0.00910**	0.000548 U	0.00386 U	**0.00121 J**	0.00524 U
	B-259-10	10/17/18	PES	PACE	10	29.2	S	0.00313 U	0.00178 U	**0.00535**	**0.00224 J**	0.00164 U	0.00175 U	0.00160 U	**0.00372**	0.000573 U	0.00403 U	**0.00257 J**	0.00548 U
	B-259-15	10/17/18	PES	PACE	15	24.2	S	0.00321 U	0.00182 U	**0.0251**	**0.00152 J**	**0.00395 J**	0.00180 U	0.00164 U	**0.0103**	0.000587 U	0.00413 U	**0.166**	0.00561 U
	B-259-20	10/17/18	PES	PACE	20	19.2	S	0.00305 U	0.00173 U	**0.697**	0.00140 U	0.00160 U	0.00171 U	0.00156 U	**0.253**	0.000559 U	0.00393 U	**0.0191**	0.00534 U
B-260	B-260-5	10/17/18	PES	PACE	5	34.2	S	0.00303 U	0.00172 U	**0.0785**	0.00139 U	0.00159 U	0.00170 U	0.00155 U	**0.00667**	0.000554 U	0.00390 U	0.000757 U	0.00530 U
	B-260-8	10/17/18	PES	PACE	8	31.2	S	0.00306 U	0.00174 U	**0.0294 J+**	**0.00153 J**	**0.00182 J**	0.00172 U	0.00157 U	**0.00771 J**	0.000561 U	0.00395 U	**0.00269 J**	0.00536 U
	B-260-10	10/17/18	PES	PACE	10	29.2	S	0.00313 U	0.00178 U	**0.0106**	0.00143 U	**0.00241 J**	0.00176 U	0.00161 U	**0.00211**	0.000574 U	0.00404 U	**0.0103**	0.00549 U
	B-260-15	10/17/18	PES	PACE	15	24.2	S	0.00317 U	0.00180 U	**9.92**	**0.00165 J**	**0.00349 J**	0.00178 U	0.00163 U	**1.98**	0.000581 U	0.00409 U	**0.0101**	0.00555 U
	B-260-20	10/17/18	PES	PACE	20	19.2	S	0.00302 U	0.00171 U	**8.23**	0.00138 U	0.00158 U	0.00169 U	0.00155 U	**1.38**	0.000553 U	0.00389 U	**0.00167 J**	0.00528 U
B-261	B-261-3	10/17/18	PES	PACE	3	36.9	S	0.00312 U	0.00177 U	**0.0198**	0.00143 U	0.00163 U	0.00175 U	0.00160 U	**0.000584 J**	0.000571 U	0.00402 U	0.000780 U	0.00546 U
	B-261-5	10/17/18	PES	PACE	5	34.9	S	0.00309 U	0.00176 U	**25.2 J+**	**0.00151 J**	0.00162 U	0.00173 U	0.00159 U	0.0362 U	0.000566 U	0.00399 U	0.000773 U	0.00541 U
	B-261-8	10/17/18	PES	PACE	8	31.9	S	0.00327 U	0.00186 U	**7.13**	**0.00162 J**	0.00171 U	0.00183 U	0.00168 U	0.00479 U	0.000599 U	0.00422 U	0.000818 U	0.00573 U
	B-261-10	10/17/18	PES	PACE	10	29.9	S	0.00315 U	0.00179 U	**25.3 J+**	0.00144 U	0.00165 U	0.00176 U	0.00161 U	0.0184 U	0.000576 U	0.00406 U	0.000787 U	0.00551 U
	B-261-15	10/17/18	PES	PACE	15	24.9	S	0.00300 U	0.00170 U	**13.1**	0.00137 U	0.00157 U	0.00168 U	0.00154 U	**0.0284**	0.000549 U	0.00387 U	0.000750 U	0.00525 U
	B-261-20	10/17/18	PES	PACE	20	19.9	S	0.00307 U	0.00174 U	**112 J+**	**0.00203 J**	**0.00200 J**	0.00172 U	0.00157 U	**0.908**	0.000562 U	0.00396 U	0.000768 U	0.00537 U
B-262	B-262-5	10/17/18	PES	PACE	5	34.9	S	0.00322 U	0.00183 U	**14.4 J**	**0.00858**	0.00168 U	0.00180 U	0.00165 U	**0.0142**	0.000589 U	0.00415 U	0.000805 U	**0.00775**
	B-262-8	10/17/18	PES	PACE	8	31.9	S	0.00300 U	0.00170 U	**0.612**	0.00137 U	0.00157 U	0.00168 U	0.00154 U	**0.00725**	0.000550 U	0.00387 U	0.000751 U	0.00526 U
	B-262-10	10/17/18	PES	PACE	10	29.9	S	0.00304 U	0.00173 U	**0.495**	0.00139 U	0.00159 U	0.00170 U	0.00156 U	**0.00390**	0.000557 U	0.00392 U	0.000761 U	0.00532 U
	B-262-15	10/17/18	PES	PACE	15	24.9	S	0.00300 U	0.00170 U	**1.81**	0.00137 U	0.00157 U	0.00168 U	0.00154 U	**0.0301**	0.000549 U	0.00386 U	0.000750 U	0.00525 U
	B-262-20	10/17/18	PES	PACE	20	19.9	S	0.00321 U	0.00182 U	**2.05 J**	0.00147 U	0.00168 U	0.00180 U	0.00165 U	**0.0634**	0.000589 U	0.00414 U	0.000804 U	0.00563 U
B-263	B-263-3	10/18/18	PES	PACE	3	36.8	S	0.00334 U	0.00190 U	**0.0143**	0.00153 U	0.00175 U	0.00187 U	0.00171 U	**0.000626 J**	0.000612 U	0.00431 U	0.000836 U	0.00585 U
	B-263-5	10/18/18	PES	PACE	5	34.8	S	0.00295 U	0.00167 U	**0.0302**	0.00135 U	0.00155 U	0.00165 U	0.00151 U	**0.00438**	0.000540 U	0.00380 U	0.000738 U	0.00517 U
	B-263-8	10/18/18	PES	PACE	8	31.8	S	0.00288 U	0.00163 U	**0.0301**	0.00132 U	0.00151 U	0.00161 U	0.00148 U	**0.00471**	0.000527 U	0.00371 U	0.000720 U	0.00504 U
	B-263-10	10/18/18	PES	PACE	10	29.8	S	0.00311 U	0.00176 U	**0.0321**	0.00142 U	0.00163 U	0.00174 U	0.00159 U	**0.00106 J**	0.000569 U	0.00401 U	0.000777 U	0.00544 U
	B-263-15	10/18/18	PES	PACE	15	24.8	S	0.00298 U	0.00169 U	**0.0558**	0.00136 U	0.00156 U	0.00167 U	0.00153 U	**0.00523**	0.000546 U	0.00384 U	0.000746 U	0.00522 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
B-263 (continued)	B-263-18	10/18/18	PES	PACE	18	21.8	S	0.00296 U	0.00168 U	**0.416**	0.00136 U	0.00155 U	0.00166 U	0.00152 U	**0.0154**	0.000542 U	0.00382 U	**0.00733**	0.00519 U
B-264	B-264-3	10/18/18	PES	PACE	3	36.8	S	0.00296 U	0.00168 U	**0.200**	0.00136 U	0.00155 U	0.00166 U	0.00152 U	**0.00630**	0.000543 U	0.00382 U	0.000742 U	0.00519 U
	B-264-5	10/18/18	PES	PACE	5	34.8	S	0.00316 U	0.00179 U	**0.0960**	0.00145 U	0.00165 U	0.00177 U	0.00162 U	**0.00185**	0.000579 U	0.00407 U	0.000790 U	0.00553 U
	B-264-8	10/18/18	PES	PACE	8	31.8	S	0.00312 U	0.00177 U	**0.415**	0.00143 U	0.00163 U	0.00175 U	0.00160 U	**0.00376**	0.000571 U	0.00402 U	0.000781 U	0.00546 U
	B-264-10	10/18/18	PES	PACE	10	29.8	S	0.00301 U	0.00171 U	**1.29**	0.00138 U	0.00158 U	0.00169 U	0.00154 U	**0.00533**	0.000551 U	0.00388 U	0.000752 U	0.00527 U
	B-264-15	10/18/18	PES	PACE	15	24.8	S	0.00318 U	0.00180 U	**0.663**	0.00145 U	0.00166 U	0.00178 U	0.00163 U	**0.00852**	0.000582 U	0.00410 U	**0.00303**	0.00556 U
	B-264-16	10/18/18	PES	PACE	16	23.8	S	0.00306 U	0.00174 U	**0.199**	**0.00291 J**	0.00161 U	0.00172 U	0.00157 U	**0.00250**	0.000561 U	0.00395 U	0.000767 U	0.00537 U
B-265	B-265-3	10/18/18	PES	PACE	3	36.8	S	0.00326 U	0.00185 U	**0.154**	**0.00150 J**	0.00171 U	0.00183 U	0.00167 U	**0.00198**	0.000597 U	0.00420 U	0.000815 U	0.00570 U
	B-265-5	10/18/18	PES	PACE	5	34.8	S	0.00316 U	0.00180 U	1.57 UJ	0.00145 U	0.00166 U	0.00177 U	0.00162 U	**0.00413**	0.000579 U	0.00408 U	0.000791 U	0.00554 U
	B-265-8	10/18/18	PES	PACE	8	31.8	S	0.00305 U	0.00173 U	**2.37 J**	0.00140 U	0.00160 U	0.00171 U	0.00156 U	**0.00473**	0.000558 U	0.00393 U	0.000762 U	0.00534 U
	B-265-10	10/18/18	PES	PACE	10	29.8	S	0.00300 U	0.00170 U	**1.15 J**	0.00137 U	0.00157 U	0.00168 U	0.00154 U	**0.00325**	0.000550 U	0.00387 U	0.000751 U	0.00526 U
	B-265-17.5	10/18/18	PES	PACE	18	22.3	S	0.00302 U	0.00171 U	**0.0155 J**	0.00138 U	0.00158 U	0.00169 U	0.00155 U	0.000443 U	0.000553 U	0.00389 U	0.000756 U	0.00529 U
B-266	B-266-5	10/18/18	PES	PACE	5	35.7	S	0.00333 U	0.00189 U	**0.0153 J**	**0.00546 J**	0.00174 U	0.00186 U	0.00171 U	**0.00639**	0.000609 U	0.00429 U	0.000832 U	0.00582 U
	B-266-8	10/18/18	PES	PACE	8	32.7	S	0.00347 U	0.00197 U	**0.00703 J**	**0.00302 J**	0.00182 U	0.00194 U	0.00178 U	**0.00919**	0.000636 U	0.00448 U	0.000869 U	0.00609 U
	B-266-10	10/18/18	PES	PACE	10	30.7	S	0.00439 U	0.00249 U	**0.00843 J**	0.00201 U	0.00231 U	0.00247 U	0.00225 U	**0.00315**	0.000805 U	0.00566 U	0.00110 U	0.00769 U
	B-266-15	10/18/18	PES	PACE	15	25.7	S	0.00365 U	0.00207 U	**1.79 J**	**0.00296 J**	0.00191 U	0.00204 U	0.00186 U	**0.00212**	0.000667 U	0.00469 U	0.000911 U	0.00637 U
	B-266-20	10/18/18	PES	PACE	20	20.7	S	0.00304 U	0.00173 U	**5.70 J**	**0.00330 J**	0.00159 U	0.00171 U	0.00156 U	**0.111**	0.000557 U	0.00392 U	0.000761 U	0.00533 U
B-267	B-267-2.5	10/18/18	PES	PACE	2.5	37.4	S	0.00328 U	0.00186 U	**0.00171 J**	0.00150 U	0.00172 U	0.00184 U	0.00168 U	0.000481 U	0.000601 U	0.00423 U	0.000821 U	0.00574 U
	B-267-5	10/18/18	PES	PACE	5	34.9	S	0.00298 U	0.00169 U	**0.138**	**0.00570**	0.00156 U	0.00167 U	0.00153 U	**0.000945 J**	0.000545 U	0.00384 U	0.000745 U	0.00521 U
	B-267-8	10/18/18	PES	PACE	8	31.9	S	0.00326 U	0.00185 U	**0.604 J**	0.00149 U	0.00171 U	0.00183 U	0.00167 U	**0.00123**	0.000597 U	0.00420 U	0.000815 U	0.00570 U
	B-267-10	10/18/18	PES	PACE	10	29.9	S	0.00309 U	0.00175 U	**0.517 J**	**0.00188 J**	0.00162 U	0.00173 U	0.00158 U	**0.00270**	0.000565 U	0.00398 U	0.000772 U	0.00540 U
	B-267-15	10/18/18	PES	PACE	15	24.9	S	0.0610 U	0.0347 U	**7.72**	0.0279 U	0.0320 U	0.0342 U	0.0313 U	**0.0853**	0.0112 U	0.0787 U	0.0153 U	0.107 U
	B-267-20	10/18/18	PES	PACE	20	19.9	S	0.0678 U	0.0385 U	**8.01**	0.0310 U	0.0356 U	0.0381 U	0.0348 U	**0.102**	0.0124 U	0.0874 U	0.0170 U	0.119 U
CA-A10	CA-A10-21	09/04/19	PES	Fremont	21	–	S	–	–	**4.68**	–	–	–	–	**0.427**	–	–	0.239 U	–
CA-A12-20	CA-A12-20-24	09/06/19	PES	Fremont	24	–	S	–	–	**35.0**	–	–	–	–	**2.41**	–	–	0.224 U	–
CAA-C1	CAA-C1-43	08/27/19	PES	Fremont	43	–	S	–	–	0.261 U	–	–	–	–	0.209 U	–	–	0.261 U	–
CAA-C2	CAA-C2-10	08/28/19	PES	Fremont	10	–	S	–	–	0.278 U	–	–	–	–	0.222 U	–	–	0.278 U	–
CA-B8	CA-B8-3	09/16/19	PES	Fremont	3	–	S	–	–	**2.98**	–	–	–	–	0.232 U	–	–	0.290 U	–
CA-B19	CA-B19-30	09/27/19	PES	Fremont	30	–	S	–	–		–	–	–	–		–	–		–
CA-B10	CA-B10-17	08/30/19	PES	Fremont	17	–	S	–	–	**1.31**	–	–	–	–	0.191 U	–	–	0.239 U	–
	CA-B10-20	08/30/19	PES	Fremont	20	–	S	–	–	**1,220**	–	–	–	–	**3.26**	–	–	**0.292**	–
	CA-B10-21	08/30/19	PES	Fremont	21	–	S	–	–	**13.7**	–	–	–	–	**0.168 J**	–	–	0.280 U	–
	CA-B10-25	08/30/19	PES	Fremont	25	–	S	–	–	**4.07**	–	–	–	–	0.176 U	–	–	0.221 U	–
CA-B11	CA-B11-27	09/05/19	PES	Fremont	27	–	S	–	–	**191**	–	–	–	–	**0.270**	–	–	0.225 U	–
CA-B18	CA-B18-20	10/26/19	PES	Fremont	20	–	S	–	–	**0.0961 J**	–	–	–	–	0.168 U	–	–	0.210 U	–
CA-B20	CA-B20-31	09/30/19	PES	Fremont	31	–	S	–	–	**0.141 J**	–	–	–	–	0.186 U	–	–	0.232 U	–
	B-1001-31	09/30/19	PES	Fremont	31 (dup)	–	S	–	–	**0.125 J**	–	–	–	–	0.203 U	–	–	0.254 U	–
CA-C7	CA-C7-25	09/20/19	PES	Fremont	25	–	S	–	–	**0.167 J**	–	–	–	–	0.198 U	–	–	**0.172 J**	–
CA-C8	CA-C8-35	09/03/19	PES	Fremont	35	–	S	–	–	0.209 U	–	–	–	–	0.167 U	–	–	0.209 U	–
CA-C9	CA-C9-09	09/04/19	PES	Fremont	9	–	S	–	–	**15.0**	–	–	–	–	0.177 U	–	–	0.221 U	–
CA-C10	CA-C10-17	09/06/19	PES	Fremont	17	–	S	–	–	**713**	–	–	–	–	**2.86**	–	–	0.255 U	–
	CA-C10-26	09/06/19	PES	Fremont	26	–	S	–	–	**0.249 J**	–	–	–	–	0.233 U	–	–	0.291 U	–
CA-C13	CA-C13-Comp	09/11/19	PES	Fremont	Comp	–	S	–	–	0.290 U	–	–	–	–	0.232 U	–	–	0.290 U	–
CA-D1	CA-D1-Comp	09/11/19	PES	Fremont	Comp	–	S	–	–	0.260 U	–	–	–	–	0.208 U	–	–	0.260 U	–
CA-D2	CA-D2-31	09/16/19	PES	Fremont	31	–	S	–	–	**26.0**	–	–	–	–	0.202 U	–	–	0.253 U	–
	CA-D2-50-52	09/17/19	PES	Fremont	52	–	S	–	–	**0.158 J**	–	–	–	–	0.224 U	–	–	0.280 U	–
CA-D3	CA-D3-40	09/23/19	PES	Fremont	40	–	S	–	–	**4.58**	–	–	–	–	**0.240**	–	–	**0.472**	–
CA-D4	CA-D4-51	09/19/19	PES	Fremont	51	–	S	–	–	**1.14**	–	–	–	–	0.251 U	–	–	0.314 U	–
	CA-D4-54	09/19/19	PES	Fremont	54	–	S	–	–	**1.84**	–	–	–	–	**0.121 J**	–	–	0.282 U	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	**–**	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	**–**	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
CA-D5	CA-D5-14	09/03/19	PES	Fremont	14	–	S	–	–	**9.08**	–	–	–	–	0.177 U	–	–	0.221 U	–
	CA-D5-22	09/03/19	PES	Fremont	22	–	S	–	–	**904**	–	–	–	–	**1.49**	–	–	0.229 U	–
	CA-D5-26	09/03/19	PES	Fremont	26	–	S	–	–	**9.24**	–	–	–	–	**0.646**	–	–	0.226 U	–
CA-D6	CA-D6-56	09/04/19	PES	Fremont	56	–	S	–	–	**22.3**	–	–	–	–	**0.173 J**	–	–	0.303 U	–
	CA-D6-65	09/04/19	PES	Fremont	65	–	S	–	–	**13.2**	–	–	–	–	**1.32**	–	–	0.312 U	–
CA-D7	CA-D7-15	09/05/19	PES	Fremont	15	–	S	–	–	**64.1**	–	–	–	–	**0.744**	–	–	0.202 U	–
DB01	DB01-10	3/18/13	SES	F&BI	10	30.0	S	–	–	**0.042**	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
	DB01-20	3/18/13	SES	F&BI	20	20.0	S	–	–	0.025 U	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
	DB01-30	3/18/13	SES	F&BI	30	10.0	S	–	–	0.025 U	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
	DB01-40	3/18/13	SES	F&BI	40	0.0	S	–	–	0.025 U	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
DB02	DB02-10	3/18/13	SES	F&BI	10	26.0	S	–	–	0.025 U	0.020 U	0.050 U	–	–	0.030 U	–	–	0.050 U	0.060 U
	DB02-15	3/18/13	SES	F&BI	15	21.0	S	–	–	**–**	0.020 U	**–**	–	–	**–**	–	–	**–**	0.060 U
	DB02-20	3/18/13	SES	F&BI	20	16.0	S	–	–	**0.22**	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
	DB02-30	3/18/13	SES	F&BI	30	6.0	S	–	–	**0.058**	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
	DB02-40	3/18/13	SES	F&BI	40	-4.0	S	–	–	**2.0**	**–**	0.050 U	–	–	**0.060**	–	–	0.050 U	**–**
DB03	DB03-05	3/27/13	SES	F&BI	5	35.0	S	–	–	**0.061**	**–**	0.10 U	–	–	0.060 U	–	–	0.10 U	**–**
	DB03-20	3/27/13	SES	F&BI	20	20.0	S	–	–	0.025 U	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
	DB03-35	3/27/13	SES	F&BI	35	5.0	S	–	–	0.025 U	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
	DB03-45	3/27/13	SES	F&BI	45	-5.0	S	–	–	**2.7**	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
	DB03-55	3/27/13	SES	F&BI	55	-15.0	S	–	–	**3.6**	**–**	0.050 U	–	–	**0.11**	–	–	0.050 U	**–**
	DB03-60	3/27/13	SES	F&BI	60	-20.0	S	–	–	**3.4**	**–**	0.050 U	–	–	**0.23**	–	–	0.050 U	**–**
DB04	DB04-10	3/21/13	SES	F&BI	10	30.0	S	–	–	**0.17**	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
	DB04-20	3/21/13	SES	F&BI	20	20.0	S	–	–	**4.5**	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
	DB04-35	3/21/13	SES	F&BI	35	5.0	S	–	–	**8.0**	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
	DB04-45	3/21/13	SES	F&BI	45	-5.0	S	–	–	**0.28**	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
	DB04-50	3/22/13	SES	F&BI	50	-10.0	S	–	–	0.025 U	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
	DB04-60	3/22/13	SES	F&BI	60	-20.0	S	–	–	0.025 U	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
DB05	DB05-10	3/26/13	SES	F&BI	10	41.8	V	–	–	0.025 U	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
	DB05-20	3/26/13	SES	F&BI	20	31.8	S	–	–	0.025 U	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
	DB05-30	3/26/13	SES	F&BI	30	21.8	S	–	–	**3.2**	**–**	0.050 U	–	–	**0.040**	–	–	0.050 U	**–**
	DB05-40	3/26/13	SES	F&BI	40	11.8	S	–	–	**14**	**–**	0.050 U	–	–	**0.085**	–	–	0.050 U	**–**
	DB05-50	3/26/13	SES	F&BI	50	1.8	S	–	–	0.025 U	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
	DB05-60	3/26/13	SES	F&BI	60	-8.2	S	–	–	**0.34**	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
	DB05-70	3/26/13	SES	F&BI	70	-18.2	S	–	–	**0.033**	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
DB06	DB06-10	3/25/13	SES	F&BI	10	41.8	V	–	–	0.025 U	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
	DB06-25	3/25/13	SES	F&BI	25	26.8	S	–	–	**0.98**	**–**	0.050 U	–	–	**0.033**	–	–	0.050 U	**–**
	DB06-35	3/25/13	SES	F&BI	35	16.8	S	–	–	**30**	**–**	0.050 U	–	–	**0.26**	–	–	0.050 U	**–**
	DB06-45	3/25/13	SES	F&BI	45	6.8	S	–	–	**1.3**	**–**	0.050 U	–	–	**0.036**	–	–	0.050 U	**–**
	DB06-55	3/25/13	SES	F&BI	55	-3.2	S	–	–	**0.027**	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
	DB06-65	3/25/13	SES	F&BI	65	-13.2	S	–	–	**0.029**	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
	DB06-75	3/25/13	SES	F&BI	75	-23.2	S	–	–	0.025 U	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
DB07	DB07-05	3/27/13	SES	F&BI	5	35.0	S	–	–	**2.7**	–	0.050 U	–	–	**0.084**	–	–	0.050 U	–
	DB07-15	3/27/13	SES	F&BI	15	25.0	S	–	–	**7.1**	–	0.050 U	–	–	0.030 U	–	–	0.050 U	–
	DB07-25	3/27/13	SES	F&BI	25	15.0	S	–	–	**9.8**	–	0.050 U	–	–	**0.067**	–	–	0.050 U	–
	DB07-35	3/28/13	SES	F&BI	35	5.0	S	–	–	**16**	–	0.050 U	–	–	**0.088**	–	–	0.050 U	–
	DB07-45	3/28/13	SES	F&BI	45	-5.0	S	–	–	**13**	–	0.050 U	–	–	**0.72**	–	–	0.050 U	–
	DB07-50	3/28/13	SES	F&BI	50	-10.0	S	–	–	**7.3**	–	0.050 U	–	–	**0.19**	–	–	0.050 U	–
	DB07-60	3/28/13	SES	F&BI	60	-20.0	S	–	–	**1.5**	–	0.050 U	–	–	**0.92**	–	–	0.050 U	–
	DB07-70	3/28/13	SES	F&BI	70	-30.0	S	–	–	**5.0**	–	0.050 U	–	–	**0.96**	–	–	0.050 U	–
DB08	DB08-10	3/20/13	SES	F&BI	10	30.0	S	–	–	**0.048**	–	0.050 U	–	–	0.030 U	–	–	0.050 U	–
	DB08-20	3/20/13	SES	F&BI	20	20.0	S	–	–	**4.0**	–	0.050 U	–	–	**0.19**	–	–	0.050 U	–
	DB08-35	3/20/13	SES	F&BI	35	5.0	S	–	–	**4.5**	–	0.050 U	–	–	**0.21**	–	–	0.050 U	–
	DB08-45	3/20/13	SES	F&BI	45	-5.0	S	–	–	**0.056**	–	0.050 U	–	–	0.030 U	–	–	0.050 U	–
	DB08-50	3/21/13	SES	F&BI	50	-10.0	S	–	–	**4.2**	–	0.050 U	–	–	**0.25**	–	–	0.050 U	–
	DB08-60	3/21/13	SES	F&BI	60	-20.0	S	–	–	**0.51**	–	0.050 U	–	–	**0.20**	–	–	0.050 U	–
	DB08-70	3/21/13	SES	F&BI	70	-30.0	S	–	–	**0.41**	–	0.050 U	–	–	**0.040**	–	–	0.050 U	–
DB09	DB09-10	3/19/13	SES	F&BI	10	30.0	S	–	–	**0.027**	–	0.050 U	–	–	0.030 U	–	–	0.050 U	–
	DB09-20	3/19/13	SES	F&BI	20	20.0	S	–	–	**0.15**	–	0.050 U	–	–	0.030 U	–	–	0.050 U	–
	DB09-30	3/19/13	SES	F&BI	30	10.0	S	–	–	**6.1**	–	0.050 U	–	–	**0.22**	–	–	0.050 U	–
	DB09-40	3/19/13	SES	F&BI	40	0.0	S	–	–	**1.3**	–	0.050 U	–	–	**0.28**	–	–	0.050 U	–
	DB09-50	3/19/13	SES	F&BI	50	-10.0	S	–	–	**0.14**	–	0.050 U	–	–	0.030 U	–	–	0.050 U	–
	DB09-60	3/19/13	SES	F&BI	60	-20.0	S	–	–	**0.031**	–	0.050 U	–	–	0.030 U	–	–	0.050 U	–
	DB09-70	3/19/13	SES	F&BI	70	-30.0	S	–	–	**0.025** U	–	0.050 U	–	–	0.030 U	–	–	0.050 U	–
DB10	DB10-10	3/29/13	SES	F&BI	10	30.0	S	–	–	**0.34**	–	0.050 U	–	–	0.030 U	–	–	0.050 U	–
	DB10-20	3/29/13	SES	F&BI	20	20.0	S	–	–	**23**	–	0.050 U	–	–	**0.11**	–	–	0.050 U	–
	DB10-35	3/29/13	SES	F&BI	35	5.0	S	–	–	**35**	–	0.50 U	–	–	**0.40**	–	–	0.50 U	–
	DB10-45	3/29/13	SES	F&BI	45	-5.0	S	–	–	**57**	–	0.50 U	–	–	0.30 U	–	–	0.50 U	–
	DB10-50	4/1/13	SES	F&BI	50	-10.0	S	–	–	**52**	–	0.050 U	–	–	**0.26**	–	–	0.050 U	–
	DB10-60	4/1/13	SES	F&BI	60	-20.0	S	–	–	**2.0**	–	0.050 U	–	–	0.030 U	–	–	0.050 U	–
	DB10-70	4/1/13	SES	F&BI	70	-30.0	S	–	–	**1.8**	–	0.050 U	–	–	**0.035**	–	–	0.050 U	–
DB11	DB11-15	4/2/13	SES	F&BI	15	36.8	V	–	–	0.025 U	–	0.050 U	–	–	0.030 U	–	–	0.050 U	–
	DB11-25	4/2/13	SES	F&BI	25	26.8	S	–	–	**0.028**	–	0.050 U	–	–	0.030 U	–	–	0.050 U	–
	DB11-35	4/2/13	SES	F&BI	35	16.8	S	–	–	0.025 U	–	0.050 U	–	–	0.030 U	–	–	0.050 U	–
	DB11-45	4/2/13	SES	F&BI	45	6.8	S	–	–	**15**	–	0.050 U	–	–	**0.12**	–	–	0.050 U	–
	DB11-55	4/2/13	SES	F&BI	55	-3.2	S	–	–	**0.16**	–	0.050 U	–	–	0.030 U	–	–	0.050 U	–
DB12	DB12-10	4/3/13	SES	F&BI	10	30.0	S	–	–	**0.068**	–	0.050 U	–	–	0.030 U	–	–	0.050 U	–
	DB12-20	4/3/13	SES	F&BI	20	20.0	S	–	–	**18**	–	0.050 U	–	–	**0.56**	–	–	0.050 U	–
	DB12-30	4/3/13	SES	F&BI	30	10.0	S	–	–	**6.7**	–	0.050 U	–	–	**0.032**	–	–	0.050 U	–
	DB12-40	4/3/13	SES	F&BI	40	0.0	S	–	–	**11**	–	0.050 U	–	–	**0.060**	–	–	0.050 U	–
DB13	DB13-10	4/3/13	SES	F&BI	10	30.0	S	–	–	**0.12**	–	0.050 U	–	–	0.030 U	–	–	0.050 U	–
	DB13-20	4/3/13	SES	F&BI	20	20.0	S	–	–	**0.78**	–	0.050 U	–	–	0.030 U	–	–	0.050 U	–
	DB13-35	4/3/13	SES	F&BI	35	5.0	S	–	–	**2.7**	–	0.050 U	–	–	**0.24**	–	–	0.050 U	–
	DB13-45	4/3/13	SES	F&BI	45	-5.0	S	–	–	**0.066**	–	0.050 U	–	–	0.030 U	–	–	0.050 U	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
DB14	DB14-10	4/4/13	SES	F&BI	10	31.5	S	–	–	0.025 U	**0.41**	0.050 U	–	–	0.030 U	–	–	0.050 U	**3.6**
	DB14-20	4/4/13	SES	F&BI	20	21.5	S	–	–	0.025 U	**0.078**	0.050 U	–	–	0.030 U	–	–	0.050 U	**1.0**
	DB14-30	4/4/13	SES	F&BI	30	11.5	S	–	–	0.025 U	–	0.050 U	–	–	0.030 U	–	–	0.050 U	–
	DB14-40	4/4/13	SES	F&BI	40	1.5	S	–	–	**0.050**	–	0.050 U	–	–	0.030 U	–	–	0.050 U	–
G-MW1	MW 1-3-8	7/20/01	GeoEng	NCA	8	31.0	S	–	–	**20**	0.018 U	0.013 U	–	–	0.023 U	–	–	0.013 U	0.054 U
	MW 1-8-20	7/20/01	GeoEng	NCA	20	19.0	S	–	–	**237**	0.018 U	0.013 U	–	–	**0.062**	–	–	0.013 U	0.054 U
	MW 1-11-27.5	7/20/01	GeoEng	NCA	27.5	11.5	S	–	–	**16**	0.018 U	0.013 U	–	–	**0.071 J**	–	–	0.013 U	0.054 U
	MW 1-13-32.5	7/20/01	GeoEng	NCA	32.5	6.5	S	–	–	**33**	0.036 U	0.026 U	–	–	**0.39**	–	–	0.026 U	0.11 U
	MW 1-15-37.5	7/20/01	GeoEng	NCA	37.5	1.5	S	–	–	**0.68**	0.018 U	0.013 U	–	–	0.023 U	–	–	0.013 U	0.054 U
G-MW3 (G-SB4 11)	SB4-4-10	7/20/01	GeoEng	NCA	10	29.6	S	–	–	**0.53**	0.018 U	0.013 U	–	–	0.023 U	–	–	0.013 U	0.054 U
	SB4-7-17.5	7/20/01	GeoEng	NCA	17.5	22.1	S	–	–	**13**	0.018 U	0.013 U	–	–	0.023 U	–	–	0.013 U	0.054 U
	SB4-13-32.5	7/20/01	GeoEng	NCA	32.5	7.1	S	–	–	**5.7**	0.018 U	0.013 U	–	–	**0.18**	–	–	0.013 U	0.054 U
	SB4-15-37.5	7/20/01	GeoEng	NCA	37.5	2.1	S	–	–	**0.58**	0.018 U	0.013 U	–	–	0.023 U	–	–	0.013 U	0.054 U
IW06	IW06-25	1/15/16	SES	F&BI	25	26.8	S	–	–	**0.49 ve**	–	0.005 U	–	–	**0.010**	–	–	0.005 U	–
	IW06-30	1/15/16	SES	F&BI	30	21.8	S	–	–	**0.19**	–	0.005 U	–	–	**0.0080**	–	–	0.005 U	–
	IW06-40	1/15/16	SES	F&BI	40	11.8	S	–	–	0.005 U	–	0.005 U	–	–	0.003 U	–	–	0.005 U	–
	IW06-50	1/15/16	SES	F&BI	50	1.8	S	–	–	**0.071**	–	0.005 U	–	–	0.003 U	–	–	0.005 U	–
	IW06-55	1/15/16	SES	F&BI	55	-3.2	S	–	–	**0.018**	–	0.005 U	–	–	0.003 U	–	–	0.005 U	–
	IW06-60	1/15/16	SES	F&BI	60	-8.2	S	–	–	0.005 U	–	0.005 U	–	–	0.003 U	–	–	0.005 U	–
	IW06-65	1/15/16	SES	F&BI	65	-13.2	S	–	–	**0.017**	–	0.005 U	–	–	0.003 U	–	–	0.005 U	–
	IW06-70	1/15/16	SES	F&BI	70	-18.2	S	–	–	0.005 UJ	–	0.005 U	–	–	0.003 U	–	–	0.005 U	–
	IW06-75	1/15/16	SES	F&BI	75	-23.2	S	–	–	**0.019 J**	–	0.005 UJ	–	–	0.003 UJ	–	–	0.005 UJ	–
IW-1C (-23.9 to-38.9)	IW-1C-5	3/7/18	PES	ESC	5	34.1	S	0.000260 U	0.000229 U	**0.0399**	0.000482 U	0.000293 U	0.000297 U	0.000864 U	**0.00620**	0.000424 U	0.00266 U	0.000323 U	0.000775 U
	IW-1C-15	3/7/18	PES	ESC	15	24.1	S	0.000275 U	0.000242 U	**0.00145**	0.000510 U	0.000310 U	0.000314 U	0.000914 U	**0.000516 J**	0.000449 U	0.00281 U	**0.000790 J**	0.000820 U
	IW-1C-25	3/7/18	PES	ESC	25	14.1	S	0.0556 U	0.0489 U	**11.1**	0.103 U	0.0627 U	0.0634 U	0.185 U	**0.845**	0.0907 U	0.568 U	0.0691 U	0.166 U
	IW-1C-35	3/7/18	PES	ESC	35	4.1	S	0.000251 U	0.000221 U	**2.66**	0.000465 U	**0.00339**	0.000286 U	0.000834 U	**0.286**	0.000410 U	0.00256 U	**0.0511**	0.000749 U
	IW-1C-45	3/7/18	PES	ESC	45	-5.9	S	0.000262 U	0.000231 U	**3.09**	**0.000626 J**	**0.00107 J**	0.000299 U	0.000871 U	**0.0782**	0.000428 U	0.00268 U	**0.0238**	0.000781 U
	IW-1C-55	3/7/18	PES	ESC	55	-15.9	S	0.000262 U	0.000231 U	**1.30**	0.000486 U	**0.000342 J**	0.000299 U	0.000871 U	**0.00519**	0.000428 U	0.00268 U	**0.176**	0.000782 U
	IW-1C-65	3/7/18	PES	ESC	65	-25.9	S	0.000269 U	0.000237 U	**0.00241**	0.000499 U	0.000303 U	0.000307 U	0.000894 U	**0.00116**	0.000439 U	0.00275 U	0.000334 U	0.000802 U
	IW-1C-75	3/7/18	PES	ESC	75	-35.9	S	0.000281 U	0.000248 U	**0.00735**	**0.000696 J**	0.000318 U	0.000321 U	0.000936 U	**0.00116 J**	0.000459 U	0.00287 U	**0.00172**	0.000840 U
IW-2C (-24.8 to-39.8)	IW-2C-5	3/7/18	PES	ESC	5	31.3	S	0.000289 U	0.000254 U	**0.000478 J**	0.000536 U	**0.000363 J**	0.000330 U	0.000961 U	**0.000790 J**	0.000472 U	0.00295 U	**0.000593 J**	0.000862 U
	IW-2C-15	3/7/18	PES	ESC	15	21.3	S	0.000280 U	0.000246 U	0.000330 U	0.000519 U	0.000315 U	0.000319 U	0.000930 U	0.000333 U	0.000456 U	0.00286 U	**0.00186**	0.000834 U
	IW-2C-25	3/7/18	PES	ESC	25	11.3	S	0.000261 U	0.000230 U	**6.20**	0.000485 U	**0.00130**	0.000298 U	0.000869 U	**0.388**	0.000427 U	0.00267 U	**0.00850**	0.000780 U
	IW-2C-35	3/7/18	PES	ESC	35	1.3	S	0.000295 U	0.000259 U	**0.947**	0.000547 U	**0.000522 J**	0.000336 U	0.000980 U	**0.0403**	0.000481 U	0.00301 U	**0.00140**	0.000879 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
IW-2C (continued)	IW-2C-45	3/7/18	PES	ESC	45	-8.7	S	0.000254 U	0.000223 U	**8.84**	0.000471 U	**0.00232**	0.000290 U	0.000844 U	**0.611**	0.000414 U	0.00259 U	**0.0551**	0.000757 U
	IW-2C-55	3/7/18	PES	ESC	55	-18.7	S	0.000273 U	0.000240 U	**0.0381**	0.000506 U	0.000308 U	0.000311 U	0.000906 U	**0.00499**	0.000445 U	0.00278 U	**0.00598**	0.000813 U
	IW-2C-65	3/7/18	PES	ESC	65	-28.7	S	0.000256 U	0.000225 U	**0.00836**	**0.000725 J**	0.000289 U	0.000292 U	0.000851 U	**0.000755 J**	0.000418 U	0.00261 U	**0.00496**	0.000763 U
	IW-2C-75	3/7/18	PES	ESC	75	-38.7	S	0.000281 U	0.000247 U	0.000331 U	0.000521 U	0.000317 U	0.000321 U	0.000934 U	0.000335 U	0.000459 U	0.00287 U	0.000350 U	0.000838 U
IW-3C (-24.9 to-39.9)	IW-3C-5	3/9/18	PES	ESC	5	34.1	S	0.000256 U	0.000225 U	**0.0323**	0.000475 U	0.000289 U	0.000292 U	0.000851 U	**0.00162**	0.000418 U	0.00261 U	0.000318 U	0.000763 U
	IW-3C-15	3/9/18	PES	ESC	15	24.1	S	0.00678 U	0.00597 U	**1.36**	0.0125 U	0.00765 U	0.00774 U	0.0225 U	**0.0812**	0.0111 U	0.0693 U	**0.00964 J**	0.0202 U
	IW-3C-25	3/9/18	PES	ESC	25	14.1	S	0.138 U	0.122 U	**19.0**	0.256 U	0.156 U	0.158 U	0.459 U	**0.774**	0.225 U	1.42 U	0.172 U	0.412 U
	IW-3C-35	3/9/18	PES	ESC	35	4.1	S	0.0520 U	0.0458 U	**9.68**	0.0965 U	0.0587 U	0.0593 U	0.173 U	**0.456**	0.0849 U	0.531 U	**0.0932 J**	0.156 U
	IW-3C-45	3/9/18	PES	ESC	45	-5.9	S	0.000270 U	0.000237 U	**1.85**	0.000500 U	0.00138 U	0.000308 U	0.000897 U	**0.0926**	0.000440 U	0.00275 U	**0.0251**	0.000805 U
	IW-3C-55	3/9/18	PES	ESC	55	-15.9	S	0.000266 U	0.000234 U	**0.0387**	0.000492 U	0.000300 U	0.000303 U	0.000883 U	**0.00215**	0.000433 U	0.00271 U	**0.00140**	0.000792 U
	IW-3C-65	3/9/18	PES	ESC	65	-25.9	S	0.000267 U	0.000235 U	**0.0830**	0.000495 U	0.000301 U	0.000305 U	0.000888 U	**0.0128**	0.000436 U	0.00273 U	**0.00726**	0.000796 U
	IW-3C-75	3/9/18	PES	ESC	75	-35.9	S	0.000293 U	0.000258 U	**0.0413**	0.000543 U	0.000331 U	0.000334 U	0.000974 U	**0.00631**	0.000478 U	0.00299 U	**0.00484**	0.000874 U
	IW-3C-79	3/9/18	PES	ESC	79	-39.9	S	0.000272 U	0.000239 U	**0.00138**	0.000504 U	0.000307 U	0.000310 U	0.000904 U	0.000324 U	0.000444 U	0.00278 U	0.000338 U	0.000811 U
	IW-901-79	3/9/18	PES	ESC	79 (dup)	-39.9	S	0.000271 U	0.000238 U	0.000319 U	0.000502 U	0.000305 U	0.000309 U	0.000900 U	0.000323 U	0.000442 U	0.00276 U	0.000337 U	0.000807 U
IW-7A (5.1 to-9.9)	IW-7A-5	3/16/18	PES	ESC	5	35.1	S	0.000290 U	0.000255 U	**0.00171**	**0.00706**	0.000327 U	0.000331 U	0.000964 U	**0.000944 J**	0.000473 U	0.00296 U	**0.000638 J**	**0.00827**
	IW-7A-10	3/16/18	PES	ESC	10	30.1	S	0.00161 U	**0.00417**	0.00163 U	**0.0179**	0.00246 U	0.00109 U	**0.254**	0.00145 U	0.00246 U	0.00367 U	0.00134 U	**0.0686**
	IW-7A-15	3/16/18	PES	ESC	15	25.1	S	0.00940 U	0.00828 U	**0.0250 J**	**0.135 J**	0.0106 U	0.0107 U	0.0312 U	0.0112 U	0.0154 U	0.0961 U	0.0117 U	**0.389**
	IW-7A-20	3/16/18	PES	ESC	20	20.1	S	0.00166 U	0.00152 U	0.00167 U	**0.0250**	0.00253 U	0.00112 U	**0.00815 J**	0.00149 U	0.00253 U	0.00376 U	0.00137 U	**0.0170**
	IW-7A-25	3/16/18	PES	ESC	25	15.1	S	0.000283 U	0.000250 U	0.000334 U	0.000526 U	0.000320 U	0.000323 U	0.000942 U	0.000338 U	0.000463 U	0.00289 U	0.000352 U	0.000845 U
	IW-7A-30	3/16/18	PES	ESC	30	10.1	S	0.000272 U	0.000239 U	**0.00109 J**	**0.000845 J**	0.000306 U	0.000310 U	0.000903 U	**0.000495 J**	0.000443 U	0.00277 U	**0.000829 J**	0.000810 U
	IW-7A-35	3/16/18	PES	ESC	35	5.1	S	0.00142 U	0.00130 U	**0.00201 J**	**0.00752**	0.00217 U	0.000960 U	**0.00247 J**	0.00128 U	0.00217 U	0.00322 U	0.00118 U	0.00575 U
	IW-7A-40	3/16/18	PES	ESC	40	0.1	S	0.000276 U	0.000243 U	**0.00118**	0.000511 U	0.000311 U	0.000314 U	0.000916 U	**0.000393 J**	0.000450 U	0.00281 U	0.000343 U	0.000822 U
	IW-7A-45	3/16/18	PES	ESC	45	-4.9	S	0.000274 U	0.000241 U	**0.000910 J**	0.000507 U	0.000309 U	0.000312 U	0.000909 U	0.000326 U	0.000446 U	0.00279 U	0.000340 U	0.000816 U
	IW-7A-50	3/16/18	PES	ESC	50	-9.9	S	0.000260 U	0.000229 U	**0.0179**	0.000482 U	**0.000372 J**	0.000297 U	0.000864 U	**0.00761**	0.000424 U	0.00265 U	**0.00223**	0.000775 U
IW-8B (-9.8 to-24.8)	IW-8B-5	3/19/18	PES	ESC	5	34.2	S	0.000256 U	0.000225 U	**0.0342**	0.000475 U	0.000289 U	0.000292 U	0.000852 U	**0.00314**	0.000418 U	0.00262 U	0.000319 U	0.000764 U
	IW-8B-10	3/19/18	PES	ESC	10	29.2	S	0.000252 U	0.000222 U	**0.0432**	0.000468 U	0.000285 U	0.000288 U	0.000839 U	**0.00481**	0.000412 U	0.00258 U	0.000314 U	0.000752 U
	IW-8B-15	3/19/18	PES	ESC	15	24.2	S	0.0673 U	0.0593 U	**29.6**	0.124 U	**0.0760**	0.0769 U	0.223 U	**0.243 J**	0.110 U	0.688 U	0.0838 U	0.200 U
	IW-8B-20	3/19/18	PES	ESC	20	19.2	S	0.000257 U	0.000226 U	**23.9**	0.000790 U	**0.00141**	0.000293 U	0.000854 U	**0.105**	0.000419 U	0.00262 U	**0.00354**	0.000766 U
	IW-8B-25	3/19/18	PES	ESC	25	14.2	S	0.000274 U	0.000241 U	**4.80**	0.000508 U	**0.00107 J**	0.000312 U	0.000910 U	**0.109**	0.000447 U	0.00280 U	**0.0350**	0.000817 U
	IW-8B-30	3/19/18	PES	ESC	30	9.2	S	0.000263 U	0.000232 U	**2.56**	0.000488 U	**0.000461 J**	0.000300 U	0.000874 U	**0.0560**	0.000429 U	0.00269 U	**0.0153**	0.000784 U
	IW-8B-40	3/19/18	PES	ESC	40	-0.8	S	0.000261 U	0.000230 U	**0.0249**	0.000484 U	0.000294 U	0.000298 U	0.000868 U	**0.00131**	0.000426 U	0.00267 U	**0.00106 J**	0.000779 U
	IW-8B-45	3/20/18	PES	ESC	45	-5.8	S	0.000261 U	0.000230 U	**0.0424**	0.000484 U	0.000294 U	0.000298 U	0.000867 U	**0.00265**	0.000426 U	0.00266 U	**0.00141**	0.000778 U
	IW-8B-50	3/20/18	PES	ESC	50	-10.8	S	0.000268 U	0.000236 U	**0.0164**	0.000496 U	0.000302 U	0.000305 U	0.000890 U	**0.000972 J**	0.000437 U	0.00273 U	**0.000608 J**	0.000798 U
	IW-8B-55	3/20/18	PES	ESC	55	-15.8	S	0.000252 U	0.000222 U	**0.00501**	0.000468 U	0.000285 U	0.000288 U	0.000839 U	**0.000352 J**	0.000412 U	0.00258 U	**0.000393 J**	0.000753 U
	IW-8B-60	3/20/18	PES	ESC	60	-20.8	S	0.000268 U	0.000236 U	**0.00710**	0.000497 U	0.000302 U	0.000306 U	0.000891 U	**0.000382 J**	0.000437 U	0.00274 U	0.000333 U	0.000799 U
	IW-8B-64	3/20/18	PES	ESC	64	-24.8	S	0.000264 U	0.000232 U	**0.00679**	0.000489 U	0.000298 U	0.000301 U	0.000877 U	**0.000406 J**	0.000431 U	0.00269 U	0.000328 U	0.000787 U
IW-8C (-24.5 to-39.5)	IW-8C-5	3/14/18	PES	ESC	5	32.5	S	0.000402 U	0.000353 U	**5.81**	0.000746 U	**0.000693 J+**	0.000458 U	0.00134 U	**0.129 J+**	0.000655 U	0.00410 U	**0.00182 J+**	0.00120 U
	IW-8C-10	3/14/18	PES	ESC	10	27.5	S	0.000405 U	0.000356 U	**0.0394**	**0.00153 J**	**0.00192**	0.000462 U	0.00135 U	**0.00705**	0.000661 U	0.00413 U	**0.00710**	**0.00122 J**
	IW-8C-15	3/14/18	PES	ESC	15	22.5	S	0.000276 U	0.000242 U	**0.000583 J**	0.000511 U	0.000311 U	0.000315 U	0.000917 U	0.000329 U	0.000450 U	0.00281 U	0.000342 U	0.000823 U
	IW-8C-20	3/14/18	PES	ESC	20	17.5	S	0.000252 U	0.000222 U	**0.00474**	0.000468 U	0.000285 U	0.000288 U	0.000839 U	**0.000938 J**	0.000412 U	0.00258 U	**0.00100 J**	0.000753 U
	IW-8C-25	3/14/18	PES	ESC	25	12.5	S	0.000279 U	0.000245 U	**5.39**	0.000517 U	**0.00231**	0.000318 U	0.000926 U	**0.768**	0.000455 U	0.00285 U	**0.0426**	0.000831 U
	IW-8C-30	3/14/18	PES	ESC	30	7.5	S	0.000259 U	0.000228 U	**0.798**	0.000480 U	**0.00177**	0.000295 U	0.000861 U	**0.0947**	0.000423 U	0.00264 U	**0.0814**	0.000772 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
IW-8C (continued)	IW-8C-35	3/14/18	PES	ESC	35	2.5	S	0.000271 U	0.000238 U	**0.833**	0.000502 U	**0.000842 J**	0.000309 U	0.000900 U	**0.0474**	0.000442 U	0.00276 U	**0.0230**	0.000807 U
	IW-8C-40	3/14/18	PES	ESC	40	-2.5	S	0.000269 U	0.000237 U	**40.7**	0.000500 U	**0.00250**	0.000307 U	0.000896 U	**3.56**	0.000440 U	0.00275 U	**0.0684**	0.000804 U
	IW-8C-45	3/14/18	PES	ESC	45	-7.5	S	0.000264 U	0.000232 U	**1.05**	**0.000557 J**	**0.00889**	0.000301 U	0.000878 U	**0.327**	0.000431 U	0.00270 U	**0.164 J**	0.000787 U
	IW-8C-50	3/14/18	PES	ESC	50	-12.5	S	0.000275 U	0.000242 U	**105**	**0.0210 J+**	**0.0135 J+**	0.000314 U	0.000914 U	**3.06**	0.000449 U	0.00281 U	**0.101 J+**	**0.0244**
	IW-8C-55	3/14/18	PES	ESC	55	-17.5	S	0.000270 U	0.000238 U	**11.9**	**0.00402 J+**	**0.00620 J+**	0.000308 U	0.000898 U	**0.340 J**	0.000441 U	0.00276 U	**0.0531 J+**	**0.00330 J+**
	IW-8C-60	3/14/18	PES	ESC	60	-22.5	S	0.000267 U	0.000235 U	**10.8**	**0.000637 J**	**0.00132**	0.000305 U	0.000889 U	**0.275**	0.000436 U	0.00273 U	**0.0104**	0.000798 U
	IW-902-60	3/14/18	PES	ESC	60 (dup)	-22.5	S	0.000260 U	0.000229 U	**0.955**	0.000482 U	**0.000329 J**	0.000296 U	0.000863 U	**0.0566**	0.000424 U	0.00265 U	**0.00405**	0.000775 U
	IW-8C-65	3/14/18	PES	ESC	65	-27.5	S	0.000281 U	0.000247 U	**0.0191**	0.000521 U	0.000317 U	0.000320 U	0.000933 U	**0.000468 J**	0.000458 U	0.00287 U	**0.000360 J**	0.000837 U
	IW-8C-70	3/14/18	PES	ESC	70	-32.5	S	0.000278 U	0.000245 U	**1.96**	0.000515 U	0.000313 U	0.000317 U	0.000924 U	**0.0138**	0.000453 U	0.00284 U	**0.00139**	0.000829 U
	IW-8C-75	3/14/18	PES	ESC	75	-37.5	S	0.000262 U	0.000231 U	**0.0850**	0.000486 U	0.000296 U	0.000299 U	0.000871 U	**0.00383**	0.000428 U	0.00268 U	**0.000586 J**	0.000781 U
IW-11D (-41.8 to-56.8)	IW-11D-10	4/19/18	PES	ESC	10	28.4	S	0.000323 U	0.000284 U	**0.00183**	**0.00223 J**	0.000364 U	0.000369 U	0.00107 U	0.000385 U	0.000527 U	0.00330 U	0.000402 U	0.000964 U
	IW-11D-15	4/19/18	PES	ESC	15	23.4	S	0.000271 U	0.000239 U	0.000320 U	0.000503 U	0.000306 U	0.000309 U	0.000902 U	0.000323 U	0.000443 U	0.00277 U	0.000337 U	0.000809 U
	IW-11D-20	4/19/18	PES	ESC	20	18.4	S	0.000271 U	0.000238 U	0.000319 U	0.000502 U	0.000305 U	0.000309 U	0.000900 U	0.000323 U	0.000442 U	0.00276 U	0.000337 U	0.000807 U
	IW-11D-25	4/19/18	PES	ESC	25	13.4	S	0.000256 U	0.000225 U	**0.00342**	0.000474 U	0.000288 U	0.000292 U	0.000850 U	**0.00368**	0.000417 U	0.00261 U	**0.00161**	0.000763 U
	IW-11D-30	4/19/18	PES	ESC	30	8.4	S	0.000256 U	0.000225 U	**0.0362**	0.000475 U	0.000289 U	0.000292 U	0.000851 U	**0.00990**	0.000418 U	0.00261 U	**0.00215**	0.000763 U
	IW-11D-35	4/19/18	PES	ESC	35	3.4	S	0.000268 U	0.000236 U	**0.0167**	0.000497 U	**0.00208**	0.000306 U	0.000891 U	**0.0176**	0.000438 U	0.00274 U	**0.0389**	0.000800 U
	IW-11D-40	4/19/18	PES	ESC	40	-1.6	S	0.000259 U	0.000228 U	**0.00301**	0.000480 U	**0.00785**	0.000295 U	0.000860 U	**0.00143**	0.000422 U	0.00264 U	**0.113**	0.000771 U
	IW-11D-45	4/19/18	PES	ESC	45	-6.6	S	0.00659 U	0.00580 U	**0.227**	0.0122 U	**0.0576**	0.00752 U	0.0218 U	**0.144**	0.0108 U	0.0673 U	**0.506**	0.0196 U
	IW-11D-50	4/19/18	PES	ESC	50	-11.6	S	0.000251 U	0.000221 U	**0.115**	0.000466 U	**0.00602**	0.000287 U	0.000835 U	**0.387**	0.000410 U	0.00257 U	**0.0505**	0.000749 U
	IW-11D-55	4/19/18	PES	ESC	55	-16.6	S	0.000277 U	0.000244 U	**0.0281**	0.000514 U	**0.00127**	0.000316 U	0.000922 U	**0.0427**	0.000453 U	0.00283 U	**0.0113**	0.000827 U
	IW-11D-60	4/19/18	PES	ESC	60	-21.6	S	0.000257 U	0.000226 U	**0.00270**	0.000477 U	0.000290 U	0.000293 U	0.000855 U	**0.00337**	0.000420 U	0.00263 U	**0.000843 J**	0.000767 U
	IW-11D-65	4/19/18	PES	ESC	65	-26.6	S	0.000258 U	0.000227 U	**0.000793 J**	0.000478 U	0.000291 U	0.000294 U	0.000857 U	**0.000816 J**	0.000421 U	0.00263 U	0.000321 U	0.000769 U
	IW-11D-70	4/19/18	PES	ESC	70	-31.6	S	0.000258 U	0.000227 U	**2.23**	0.000479 U	**0.00132**	0.000295 U	0.000859 U	**1.80**	0.000422 U	0.00264 U	**0.00344**	0.000770 U
	IW-11D-75	4/19/18	PES	ESC	75	-36.6	S	0.000270 U	0.000238 U	**0.0140**	0.000501 U	**0.000725 J**	0.000308 U	0.000898 U	**0.0277**	0.000441 U	0.00276 U	**0.00270**	0.000806 U
	IW-11D-80	4/19/18	PES	ESC	80	-41.6	S	0.000263 U	0.000231 U	**0.000610 J**	0.000488 U	0.000297 U	0.000300 U	0.000874 U	**0.00104 J**	0.000429 U	0.00269 U	0.000327 U	0.000784 U
	IW-11D-85	4/19/18	PES	ESC	85	-46.6	S	0.000269 U	0.000237 U	0.000317 U	0.000499 U	0.000303 U	0.000307 U	0.000894 U	**0.000401 J**	0.000439 U	0.00275 U	0.000335 U	0.000802 U
	IW-11D-90	4/19/18	PES	ESC	90	-51.6	S	0.000265 U	0.000233 U	**0.00552**	0.000492 U	0.000299 U	0.000303 U	0.000881 U	**0.00374**	0.000433 U	0.00271 U	**0.00127**	0.000791 U
	IW-11D-95	4/19/18	PES	ESC	95	-56.6	S	0.000274 U	0.000241 U	0.000323 U	0.000509 U	0.000309 U	0.000313 U	0.000912 U	0.000327 U	0.000448 U	0.00280 U	0.000341 U	0.000818 U
IW-12D (-41.4 to-56.4)	IW-12D-42	9/14/18	PES	ESC	42	-3.5	S	0.00296 U	0.00168 U	**55.8**	**0.00188 J**	0.00155 U	0.00166 U	0.00152 U	**0.491**	0.000543 U	0.00382 U	**0.132**	0.00519 U
	B-928-42	9/14/18	PES	ESC	42 (dup)	-3.5	S	0.00297 U	0.00168 U	**50.8**	**0.00326 J**	0.00155 U	0.00166 U	0.00152 U	**0.401**	0.000543 U	0.00382 U	**0.105**	0.00519 U
	IW-12D-50	9/14/18	PES	ESC	50	-11.5	S	0.00299 U	0.00170 U	**54.4**	**0.00427 J**	**0.0126**	0.00167 U	0.00153 U	**1.51**	0.000547 U	0.00385 U	**0.0585**	0.00523 U
	IW-12D-60	9/14/18	PES	ESC	60	-21.5	S	0.00307 U	0.00175 U	**9.63**	**0.00436 J**	0.00161 U	0.00172 U	0.00158 U	**0.347**	0.000563 U	0.00396 U	**0.0123**	0.00538 U
	IW-12D-85	9/17/18	PES	ESC	85	-46.5	S	0.00305 U	0.00173 U	**8.01**	**0.00194 J**	0.00160 U	0.00171 U	0.00156 U	**0.0451**	0.000559 U	0.00393 U	0.000763 U	0.00534 U
	IW-12D-95	9/17/18	PES	ESC	95	-56.5	S	0.00328 U	0.00186 U	**0.942**	0.00150 U	0.00172 U	0.00184 U	0.00168 U	**0.00512**	0.000601 U	0.00423 U	**0.00139**	0.00575 U
IW-13D (-41.0 to-56.0)	IW-13D-80	9/18/18	PES	ESC	80	-40.8	S	0.00301 U	0.00171 U	**31.4**	**0.00447**	**0.00404**	0.00169 U	0.00154 U	**1.21**	0.000552 U	0.00388 U	**0.0191**	**0.00585**
	IW-13D-85	9/18/18	PES	ESC	85	-45.8	S	0.00314 U	0.00178 U	**0.205**	**0.00178**	**0.00499**	0.00176 U	0.00161 U	**0.202**	0.000576 U	0.00405 U	0.000786 U	0.00550 U
	IW-13D-95	9/18/18	PES	ESC	95	-55.8	S	0.00329 U	0.00187 U	**0.00194**	**0.00171**	0.00172 U	0.00184 U	0.00168 U	**0.00168**	0.000602 U	0.00424 U	0.000822 U	0.00575 U
IW-14D (-41.0 to-56.0)	IW-14D-45	9/11/18	PES	ESC	45	-5.9	S	0.00572 U	0.00162 U	**0.712**	0.00131 U	**0.00591 J**	0.00160 U	0.00147 U	**0.0173**	0.000524 U	0.00369 U	**0.0146**	0.00501 U
	IW-14D-55	9/11/18	PES	ESC	55	-15.9	S	0.123 U	0.00175 U	**56.7**	**0.00389 J**	0.0111 UJ	0.00173 U	0.00158 U	**4.36**	0.000565 U	0.00398 U	**0.0180**	0.00540 U
	IW-14D-65	9/11/18	PES	ESC	65	-25.9	S	0.00306 U	0.00174 U	**1.60**	**0.00166 J**	**0.00171 J**	0.00172 U	0.00157 U	**0.100**	0.000561 U	0.00395 U	0.000767 U	0.00536 U
	IW-14D-75	9/11/18	PES	ESC	75	-35.9	S	0.00306 U	0.00174 U	**0.0728**	**0.00304 J**	0.00160 UJ	**0.00600 J**	0.00157 U	**0.00797**	0.000561 U	0.00395 U	0.000766 U	0.00536 U
	IW-14D-86	9/11/18	PES	ESC	86	-46.9	S	0.00301 U	0.00171 U	**2.31**	**0.00291 J**	**0.00742 J**	**0.00731 J**	0.00154 U	**0.502**	0.000551 U	0.00388 U	0.000752 U	0.00527 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
IW-14D (continued)	IW-14D-95	9/11/18	PES	ESC	95	-55.9	S	0.0247 U	0.00176 U	**5.03**	**0.00318 J**	**0.00528 J**	0.00173 U	0.00159 U	**0.616**	0.000566 U	0.00399 U	0.000774 U	0.00541 U
IW-15D (-41.9 to-56.9)	IW-15D-54	9/11/18	PES	ESC	54	-2.2	S	0.0117 U	0.00166 U	**2.32**	**0.00333 J**	0.00153 U	0.00164 U	0.00150 U	**0.282**	0.000535 U	0.00377 U	**0.00390**	0.00511 U
IW-16D (-41.5 to-56.2)	IW-16D-85	10/18/18	PES	PACE	85	-45.6	S	0.0127 U	0.00722 U	**1.35**	**0.00897 J**	0.00666 U	0.00713 U	0.00653 U	**0.336**	0.00233 U	0.0164 U	0.00318 U	0.0223 U
	IW-16D-90	10/18/18	PES	PACE	90	-50.6	S	0.00324 U	0.00184 U	**0.0916**	0.00148 U	0.00170 U	0.00181 U	0.00166 U	**0.140**	0.000593 U	0.00417 U	0.000810 U	0.00567 U
	IW-16D-95	10/18/18	PES	PACE	95	-55.6	S	0.0132 U	0.00751 U	**1.47**	0.00605 U	0.00693 U	0.00741 U	0.00678 U	**0.564**	0.00242 U	0.0171 U	0.00331 U	0.0231 U
IW-19B (-10.6 to-25.6)	IW-19B-5	3/19/18	PES	ESC	5	32.4	S	0.000265 U	0.000232 U	**0.00478**	0.000491 U	0.000298 U	0.000301 U	0.000879 U	**0.000961 J**	0.000431 U	0.00270 U	0.000328 U	0.000789 U
	IW-19B-10	3/19/18	PES	ESC	10	27.4	S	0.000288 U	0.000253 U	0.000340 U	0.000980 U	0.000325 U	0.000329 U	0.000957 U	0.000343 U	0.000470 U	0.00294 U	0.000358 U	0.000859 U
	IW-19B-15	3/19/18	PES	ESC	15	22.4	S	0.000268 U	0.000236 U	**0.00104 J**	0.000497 U	0.000302 U	0.000306 U	0.000891 U	0.000320 U	0.000438 U	0.00274 U	0.000333 U	0.000800 U
	IW-19B-20	3/19/18	PES	ESC	20	17.4	S	0.000261 U	0.000230 U	**0.000942 J**	0.000485 U	0.000295 U	0.000298 U	0.000869 U	0.000312 U	0.000427 U	0.00267 U	0.000325 U	0.000779 U
	IW-19B-25	3/19/18	PES	ESC	25	12.4	S	0.000275 U	0.000242 U	**0.00166**	0.000509 U	0.000310 U	0.000313 U	0.000913 U	**0.000434 J**	0.000448 U	0.00281 U	0.000342 U	0.000819 U
	IW-19B-30	3/19/18	PES	ESC	30	7.4	S	0.000263 U	0.000231 U	0.000310 U	0.000487 U	0.000297 U	0.000300 U	0.000874 U	0.000313 U	0.000429 U	0.00268 U	0.000327 U	0.000784 U
	IW-19B-35	3/19/18	PES	ESC	35	2.4	S	0.000260 U	0.000228 U	**0.00134**	0.000481 U	0.000293 U	0.000296 U	0.000863 U	**0.000436 J**	0.000424 U	0.00265 U	0.000323 U	0.000774 U
	IW-19B-40	3/19/18	PES	ESC	40	-2.6	S	0.000270 U	0.000238 U	0.000319 U	0.000501 U	0.000305 U	0.000308 U	0.000898 U	0.000322 U	0.000441 U	0.00276 U	**0.00417**	0.000806 U
	IW-19B-45	3/19/18	PES	ESC	45	-7.6	S	0.000286 U	0.000251 U	0.000337 U	0.000530 U	0.000322 U	0.000326 U	0.000949 U	**0.000472 J**	0.000466 U	0.00292 U	**0.000514 J**	0.000852 U
	IW-19B-50	3/19/18	PES	ESC	50	-12.6	S	0.000299 U	0.000263 U	**0.00660**	0.000646 U	**0.00178**	0.000341 U	0.000992 U	**0.0168**	0.000488 U	0.00305 U	**0.0457**	0.000891 U
	IW-19B-55	3/19/18	PES	ESC	55	-17.6	S	0.000257 U	0.000227 U	**10.3**	0.000478 U	**0.0123**	0.000294 U	0.000856 U	**3.01**	0.000420 U	0.00263 U	**0.109**	0.000768 U
	IW-19B-60	3/19/18	PES	ESC	60	-22.6	S	0.000258 U	0.000227 U	**14.5 J**	0.000479 U	**0.0185**	0.000295 U	0.000858 U	**3.70**	0.000421 U	0.00264 U	**0.268**	0.000770 U
	IW-903-60	3/19/18	PES	ESC	60 (dup)	-22.6	S	0.000263 U	0.000231 U	**20.3 J**	0.000487 U	**0.0182**	0.000300 U	0.000873 U	**4.58**	0.000429 U	0.00268 U	**0.280**	0.000784 U
	IW-19B-63	3/19/18	PES	ESC	63	-25.6	S	0.000262 U	0.000231 U	**0.0326**	0.000486 U	0.000296	0.000299 U	0.000871 U	**0.0180**	0.000428 U	0.00268 U	**0.0108**	0.000781 U
IW-21B (-10.1 to-25.1)	IW-21B-5	3/6/18	PES	ESC	5	36.9	V	0.000423 U	0.000372 U	**0.0140**	0.000784 U	0.000477 U	0.000482 U	0.00141 U	**0.00659**	0.000690 U	0.00432 U	0.000526 U	0.00126 U
	IW-21B-10	3/6/18	PES	ESC	10	31.9	S	0.000285 U	0.000251 U	**0.0130**	0.000529 U	0.000322 U	0.000325 U	0.000948 U	**0.00524**	0.000466 U	0.00291 U	0.000355 U	0.000851 U
	IW-21B-20	3/6/18	PES	ESC	20	21.9	S	0.000281 U	0.000248 U	**0.000338 J**	**0.00128 J**	0.000317 U	0.000321 U	0.000935 U	0.000335 U	0.000459 U	0.00287 U	0.000350 U	0.000839 U
	IW-21B-30	3/6/18	PES	ESC	30	11.9	S	0.000261 U	0.000230 U	0.000308 U	0.000485 U	0.000295 U	0.000298 U	0.000869 U	0.000312 U	0.000427 U	0.00267 U	0.000325 U	0.000779 U
	IW-21B-40	3/6/18	PES	ESC	40	1.9	S	0.000259 U	0.000228 U	**0.00709**	0.000480 U	**0.00134**	0.000295 U	0.000860 U	**0.00187**	0.000422 U	0.00264 U	**0.0212**	0.000772 U
	IW-21B-50	3/6/18	PES	ESC	50	-8.1	S	0.000253 U	0.000223 U	**0.00382**	0.000469 U	**0.000587 J**	0.000289 U	0.000841 U	**0.00783**	0.000413 U	0.00258 U	**0.0338**	0.000755 U
	IW-21B-60	3/6/18	PES	ESC	60	-18.1	S	0.00663 U	0.00584 U	**10.5**	0.0122 U	**0.0341**	0.00757 U	0.0220 U	**3.82**	0.0108 U	0.0678 U	**0.0525**	0.0197 U
	IW-21B-67	3/6/18	PES	ESC	67	-25.1	S	0.000259 U	0.000228 U	**0.00196**	0.000481 U	**0.000295 J**	0.000296 U	0.000862 U	**0.00311**	0.000423 U	0.00265 U	**0.00878**	0.000773 U
IW-22C (-25.6 to-40.6)	IW-22C-62	8/31/18	PES	ESC	62	-23.1	S	0.00315 U	0.00179 U	**14.5**	**0.00954**	0.00165 U	0.00177 U	0.00162 U	**0.708**	0.000577 U	0.00407 U	0.000789 U	0.219 U
	IW-22C-78	8/31/18	PES	ESC	78	-39.1	S	0.00331 U	0.00188 U	**16.6**	**0.00182 J**	0.00173 U	0.00185 U	0.00170 U	**0.915**	0.000606 U	0.00426 U	**0.00698**	0.231 U
IW-23C (-27.0 to-42.0)	IW-23C-42	9/4/18	PES	ESC	42	-3.0	S	0.00327 U	**0.00248 J**	**308**	**0.00716**	**0.0116 J**	0.00183 U	0.00168 U	**0.929**	0.000598 U	0.00421 U	**0.532**	2.29 U
IW-24C (-26.1 to-41.1)	IW-24C-48	9/7/18	PES	ESC	48	-8.8	S	0.00309 U	0.00175 U	**0.313**	**0.00380 J**	**0.0101 J**	0.00173 U	0.00158 U	**0.0257**	0.000565 U	0.00398 U	**0.176 J-**	0.0540 U
	IW-24C-55	9/7/18	PES	ESC	55	-15.8	S	0.00325 U	**0.00213 J**	**140**	**0.00382 J**	**0.0424**	0.00182 U	0.00167 U	**0.882**	0.000595 U	0.00419 U	0.000813 U	**0.00785**
	IW-24C-66	9/10/18	PES	ESC	66	-26.8	S	0.00338 U	0.00192 U	**210**	0.618 U	**0.0248**	0.00189 U	0.00173 U	**1.54**	0.000618 U	0.00435 U	0.000845 U	**0.0121**
	IW-24C-75	9/10/18	PES	ESC	75	-35.8	S	0.00326 U	0.00185 U	**309**	0.598 U	**0.0228**	0.00183 U	0.00167 U	**2.12**	0.000598 U	0.00421 U	0.000817 U	**0.0127**
	IW-24C-80	9/10/18	PES	ESC	80	-40.8	S	0.0604 U	0.00171 U	**12.3**	**0.00148 J**	**0.00418 J**	0.00169 U	0.00155 U	**0.128**	0.000553 U	0.00389 U	**0.0312**	0.00529 U
IW-27B (-8.1 to-23.1)	IW-27B-5	3/2/18	PES	ESC	5	37.0	V	0.000375 U	0.000330 U	**0.0678**	0.000695 U	0.000424 U	0.000428 U	0.00125 U	**0.0248**	0.000612 U	0.00383 U	0.000467 U	0.00112 U
	IW-27B-15	3/2/18	PES	ESC	15	27.0	S	0.000333 U	0.000293 U	**0.0178**	**0.00124 J**	0.000376 U	0.000380 U	0.00111 U	**0.00435**	0.000544 U	0.00340 U	**0.000493 J**	0.000994 U
	IW-27B-25	3/2/18	PES	ESC	25	17.0	S	0.000272 U	0.000240 U	0.000321 U	0.000505 U	0.000307 U	0.000311 U	0.000905 U	0.000324 U	0.000444 U	0.00278 U	0.000338 U	0.000812 U
	IW-27B-35	3/2/18	PES	ESC	35	7.0	S	0.000268 U	0.000236 U	**0.00114 J**	0.000497 U	**0.120**	0.000306 U	0.000890 U	**0.000325 J**	0.000437 U	0.00274 U	**0.0195**	0.000799 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
IW-27C (-24.4 to-39.6)	IW-27C-45	9/10/18	PES	ESC	45	6.8	S	0.0611 U	0.00173 U	**18.6**	**0.00223 J**	**0.00239 J**	0.00171 U	0.00157 U	**0.178**	0.000560 U	0.00394 U	**0.0297**	0.00535 U
IW-28C (-26.6 to-41.7)	IW-28C-92	9/17/18	PES	ESC	92	-40.6	S	0.00297 U	0.00168 U	**0.983**	**0.00168**	0.00155 U	0.00166 U	0.00152 U	**0.00290**	0.000544 U	0.00383 U	0.000742 U	0.00520 U
IW-39B (-9.8 to-24.8)	IW-39B-5	3/12/18	PES	ESC	5	35.2	V	0.000297 U	0.000262 U	**0.0961**	0.000551 U	**0.000423 J**	0.000339 U	0.000988 U	**0.00856**	0.000485 U	0.00303 U	0.000370 U	0.000886 U
	IW-39B-15	3/12/18	PES	ESC	15	25.2	S	0.000261 U	0.000230 U	0.000308 U	0.000484 U	0.000294 U	0.000298 U	0.000867 U	0.000311 U	0.000426 U	0.00266 U	0.000324 U	0.000778 U
	IW-39B-25	3/12/18	PES	ESC	25	15.2	S	0.000278 U	0.000245 U	**0.0371**	0.000516 U	**0.000814 J**	0.000317 U	0.000925 U	**0.00557**	0.000454 U	0.00284 U	**0.000945 J**	0.000830 U
	IW-39B-35	3/12/18	PES	ESC	35	5.2	S	0.000257 U	0.000226 U	**0.00404**	0.000477 U	**0.000397 J**	0.000293 U	0.000854 U	**0.00185**	0.000419 U	0.00262 U	**0.00311**	0.000766 U
	IW-39B-45	3/12/18	PES	ESC	45	-4.8	S	0.000262 U	0.000231 U	**0.00336**	0.000487 U	0.000296 U	0.000299 U	0.000872 U	**0.00126**	0.000428 U	0.00268 U	**0.00592**	0.000783 U
	IW-39B-55	3/12/18	PES	ESC	55	-14.8	S	0.00614 U	0.00541 U	**0.0868**	0.0113 U	**0.0809**	0.00701 U	0.0204 U	**0.0219 J**	0.0100 U	0.0628 U	**0.0245 J**	0.0183 U
IW-46B (-4.2 to-24.2)	IW-46B-5	3/20/18	PES	ESC	5	46.8	V	0.000263 U	0.000232 U	**0.00450 J**	0.000488 UJ	0.000297 UJ	0.000300 U	0.000875 U	0.000314 UJ	0.000429 U	0.00269 U	0.000327 UJ	0.000785 UJ
	IW-46B-10	3/20/18	PES	ESC	10	41.8	V	0.000257 U	0.000226 U	**0.0223 J**	0.000477 UJ	0.000290 UJ	0.000293 U	0.000855 U	0.000307 UJ	0.000420 U	0.00263 U	0.000320 UJ	0.000767 UJ
	IW-46B-15	3/20/18	PES	ESC	15	36.8	V	0.00647 U	0.00570 U	**0.386 J**	0.0119 UJ	0.00730 UJ	0.00739 U	0.0215 U	**0.0108 J**	0.0106 U	0.0661 U	0.00805 UJ	0.0192 UJ
	IW-46B-20	3/20/18	PES	ESC	20	31.8	S	0.000262 U	0.000230 U	**0.0626 J**	0.000485 UJ	0.000295 UJ	0.000299 U	0.000870 U	**0.00127 J**	0.000427 U	0.00267 U	0.000325 UJ	0.000780 UJ
	IW-46B-25	3/20/18	PES	ESC	25	26.8	S	0.000259 U	0.000228 U	**20.1 J**	0.000480 UJ	0.000292 UJ	0.000295 U	0.000860 U	**0.0476 J**	0.000422 U	0.00264 U	**0.000784 J**	0.000772 UJ
	IW-46B-30	3/20/18	PES	ESC	30	21.8	S	0.000262 U	0.000230 U	**5.63 J**	0.000485 UJ	0.000295 UJ	0.000299 U	0.000870 U	**0.0134 J**	0.000427 U	0.00267 U	0.000325 UJ	0.000781 UJ
	IW-46B-35	3/20/18	PES	ESC	35	16.8	S	0.000283 U	0.000249 U	**0.00462 J**	0.000525 UJ	0.000319 UJ	0.000323 U	0.000941 U	0.000338 UJ	0.000462 U	0.00289 U	**0.000712 J**	0.000844 UJ
	IW-904-35	3/20/18	PES	ESC	35 (dup)	16.8	S	0.000299 U	0.000263 U	**0.0143 J**	0.000555 UJ	0.000338 UJ	0.000341 U	0.000995 U	**0.00219 J**	0.000489 U	0.00306 U	**0.000756 J**	0.000893 UJ
	IW-46B-40	3/20/18	PES	ESC	40	11.8	S	0.000246 U	0.000217 U	**2.36 J**	0.000456 UJ	0.000278 UJ	0.000281 U	0.000818 U	**0.0147 J**	0.000402 U	0.00251 U	0.000306 UJ	0.000734 UJ
	IW-46B-42	3/20/18	PES	ESC	42	9.8	S	0.000281 U	0.000248 U	**145 J**	**0.00189 J**	**0.00269 J**	0.000321 U	0.000935 U	**1.31 J**	0.000459 U	0.00287 U	**0.356 J**	**0.00187 J**
	IW-46B-45	3/20/18	PES	ESC	45	6.8	S	1.33 U	1.17 U	**261 J**	2.47 UJ	1.50 UJ	1.52 U	4.43 U	**1.59 J**	2.17 U	13.7 U	1.66 UJ	3.97 UJ
	IW-46B-50	3/20/18	PES	ESC	50	1.8	S	0.000234 U	0.000206 U	**2.31 J**	**0.000577 J**	**0.00309 J**	0.000267 U	0.000778 U	**0.0168 J**	0.000382 U	0.00239 U	**1.65 J**	0.000698 UJ
	IW-46B-55	3/20/18	PES	ESC	55	-3.2	S	0.000261 U	0.000230 U	**14.3 J**	0.000484 UJ	**0.000783 J**	0.000298 U	0.000868 U	**0.0266 J**	0.000426 U	0.00267 U	**0.0923 J**	0.000778 UJ
	IW-46B-60	3/20/18	PES	ESC	60	-8.2	S	0.000264 U	0.000233 U	**8.71 J**	0.000490 UJ	**0.00223 J**	0.000302 U	0.000879 U	**0.0393 J**	0.000432 U	0.00270 U	**0.908 J**	0.000788 UJ
	IW-46B-65	3/20/18	PES	ESC	65	-13.2	S	0.000260 U	0.000229 U	**1.78 J**	0.000483 UJ	**0.000435 J**	0.000297 U	0.000865 U	**0.00183 J**	0.000425 U	0.00266 U	**0.0639 J**	0.000776 UJ
	IW-46B-70	3/20/18	PES	ESC	70	-18.2	S	0.000298 U	0.000263 U	**2.79 J**	0.000554 UJ	**0.00185 J**	0.000341 U	0.000992 U	**0.0366 J**	0.000487 U	0.00305 U	**0.0252 J**	0.000890 UJ
IW-47B (-5.2 to-25.2)	IW-47B-5	3/22/18	PES	ESC	5	46.8	V	0.000276 U	0.000243 U	**0.0518**	0.000512 UJ	0.000311 UJ	0.000315 U	0.000918 U	**0.00121 J**	0.000451 U	0.00282 U	0.000343 UJ	0.000823 UJ
	IW-47B-10	3/22/18	PES	ESC	10	41.8	V	0.000275 U	0.000242 U	**0.0214 J**	0.000511 UJ	0.000311 UJ	0.000314 U	0.000915 U	**0.000935 J**	0.000449 U	0.00281 U	0.000342 UJ	0.000821 UJ
	IW-47B-15	3/22/18	PES	ESC	15	36.8	V	0.000261 U	0.000230 U	**0.00348 J**	0.000485 UJ	0.000295 UJ	0.000298 U	0.000869 U	0.000312 UJ	0.000427 U	0.00267 U	0.000325 UJ	0.000779 UJ
	IW-47B-20	3/22/18	PES	ESC	20	31.8	S	0.000260 U	0.000229 U	**0.0344 J**	0.000482 UJ	0.000293 UJ	0.000296 U	0.000864 U	**0.00453 J**	0.000424 U	0.00265 U	0.000323 UJ	0.000775 UJ
	IW-47B-25	3/22/18	PES	ESC	25	26.8	S	0.000265 U	0.000233 U	**0.0435 J**	0.000491 UJ	0.000299 UJ	0.000302 U	0.000880 U	**0.00663 J**	0.000432 U	0.00270 U	0.000329 UJ	0.000790 UJ
	IW-47B-30	3/22/18	PES	ESC	30	21.8	S	0.000262 U	0.000231 U	**0.00334 J**	0.000487 UJ	**0.000962 J**	0.000299 U	0.000872 U	**0.00136 J**	0.000428 U	0.00268 U	0.000326 UJ	0.000783 UJ
	IW-47B-35	3/22/18	PES	ESC	35	16.8	S	0.000257 U	0.000227 U	**0.00552 J**	0.000477 UJ	0.000290 UJ	0.000294 U	0.000856 U	**0.00173 J**	0.000420 U	0.00263 U	0.000320 UJ	0.000768 UJ
	IW-47B-40	3/22/18	PES	ESC	40	11.8	S	0.000266 U	0.000234 U	**0.0155 J**	0.000493 UJ	0.000300 UJ	0.000303 U	0.000883 U	**0.00284 J**	0.000434 U	0.00271 U	**0.00246 J**	0.000792 UJ
	IW-47B-42	3/22/18	PES	ESC	42	9.8	S	0.000307 U	0.000271 U	**0.196 J**	**0.000822 J**	0.000346 UJ	0.000351 U	0.00102 U	**0.0157 J**	0.000502 U	0.00314 U	**0.00137 J**	0.000916 UJ
	IW-47B-45	3/22/18	PES	ESC	45	6.8	S	0.000265 U	0.000233 U	**0.0192 J**	0.000491 UJ	**0.000473 J**	0.000302 U	0.000880 U	**0.00253 J**	0.000432 U	0.00270 U	**0.00224 J**	0.000789 UJ
	IW-47B-50	3/22/18	PES	ESC	50	1.8	S	0.000275 U	0.000242 U	**0.0102 J**	0.000510 UJ	**0.00397 J**	0.000314 U	0.000914 U	**0.00206 J**	0.000449 U	0.00281 U	**0.00131 J**	0.000820 UJ
	IW-47B-55	3/22/18	PES	ESC	55	-3.2	S	0.000253 U	0.000223 U	**0.0158 J**	0.000469 UJ	**0.00213 J**	0.000289 U	0.000841 U	**0.00209 J**	0.000413 U	0.00258 U	**0.105 J**	0.000754 UJ
	IW-47B-60	3/22/18	PES	ESC	60	-8.2	S	0.000268 U	0.000236 U	**0.0204 J**	0.000496 UJ	**0.000867 J**	0.000305 U	0.000890 U	**0.00194 J**	0.000437 U	0.00273 U	**0.0200 J**	0.000798 UJ
	IW-47B-65	3/22/18	PES	ESC	65	-13.2	S	0.000264 U	0.000233 U	**0.0244 J**	0.000490 UJ	**0.000369 J**	0.000301 U	0.000878 U	**0.00115 J**	0.000431 U	0.00270 U	**0.00491 J**	0.000788 UJ
	IW-47B-70	3/22/18	PES	ESC	70	-18.2	S	0.000261 U	0.000230 U	**0.0312 J**	0.000485 UJ	**0.00244 J**	0.000298 U	0.000869 U	**0.00264 J**	0.000426 U	0.00267 U	**0.0168 J**	0.000779 UJ
	IW-47B-75	3/22/18	PES	ESC	75	-23.2	S	0.000260 U	0.000229 U	**0.000331 J**	0.000483 UJ	0.000294 UJ	0.000297 U	0.000866 U	0.000310 UJ	0.000425 U	0.00266 U	0.000324 UJ	0.000777 UJ

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
IW-48B (-9.4 to-24.4)	IW-48B-5	3/23/18	PES	ESC	5	46.7	V	0.000270 U	0.000238 U	**0.0108**	0.000502 U	0.000305 U	0.000309 U	0.000899 U	0.000322 U	0.000441 U	0.00276 U	0.000336 U	0.000807 U
	IW-48B-10	3/23/18	PES	ESC	10	41.7	V	0.000265 U	0.000233 U	**0.00589**	0.000491 U	0.000299 U	0.000302 U	0.000881 U	0.000316 U	0.000432 U	0.00271 U	0.000329 U	0.000790 U
	IW-48B-15	3/23/18	PES	ESC	15	36.7	V	0.000273 U	0.000241 U	**0.0117**	0.000507 U	0.000308 U	0.000312 U	0.000908 U	0.000326 U	0.000446 U	0.00279 U	0.000340 U	0.000815 U
	IW-48B-20	3/23/18	PES	ESC	20	31.7	S	0.000257 U	0.000227 U	**0.0775**	0.000478 U	0.000290 U	0.000294 U	0.000856 U	**0.00543**	0.000420 U	0.00263 U	0.000320 U	0.000768 U
	IW-48B-25	3/23/18	PES	ESC	25	26.7	S	0.000263 U	0.000232 U	**0.924**	0.000489 U	0.000297 U	0.000301 U	0.000876 U	**0.0104**	0.000430 U	0.00269 U	0.000328 U	0.000786 U
	IW-48B-30	3/23/18	PES	ESC	30	21.7	S	0.000258 U	0.000227 U	0.127 UJ	0.000478 U	0.000291 U	0.000294 U	0.000858 U	**0.00751**	0.000421 U	0.00263 U	0.000321 U	0.000769 U
	IW-48B-35	3/23/18	PES	ESC	35	16.7	S	0.000269 U	0.000237 U	0.00825 UJ	0.000499 U	**0.000991 J**	0.000307 U	0.000895 U	**0.00215**	0.000440 U	0.00275 U	0.000335 U	0.000803 U
	IW-48B-40	3/23/18	PES	ESC	40	11.7	S	0.000255 U	0.000225 U	**0.0129 J**	0.000474 U	**0.00178**	0.000291 U	0.000849 U	**0.00267**	0.000417 U	0.00261 U	0.000318 U	0.000762 U
	IW-48B-42	3/23/18	PES	ESC	42	9.7	S	0.000258 U	0.000227 U	0.00329 UJ	0.000478 U	0.000291 U	0.000294 U	0.000857 U	**0.00150**	0.000421 U	0.00263 U	0.000321 U	0.000769 U
	IW-905-42	3/23/18	PES	ESC	42 (dup)	9.7	S	0.000256 U	0.000225 U	**0.00302**	0.000474 U	0.000288 U	0.000292 U	0.000850 U	**0.00122**	0.000417 U	0.00261 U	0.000318 U	0.000763 U
	IW-48B-45	3/23/18	PES	ESC	45	6.7	S	0.000254 U	0.000224 U	**0.000668 J**	0.000471 U	0.000286 U	0.000290 U	0.000844 U	0.000303 U	0.000414 U	0.00259 U	0.000316 U	0.000757 U
	IW-48B-50	3/23/18	PES	ESC	50	1.7	S	0.000258 U	0.000227 U	**0.00167 J**	0.000479 U	**0.00118**	0.000295 U	0.000859 U	**0.00101 J**	0.000422 U	0.00264 U	0.000321 U	0.000770 U
	IW-48B-55	3/23/18	PES	ESC	55	-3.3	S	0.000254 U	0.000223 U	**0.0683 J**	0.000471 U	**0.0204**	0.000289 U	0.000845 U	**0.0476**	0.000415 U	0.00260 U	**0.000480 J**	0.000757 U
	IW-48B-60	3/23/18	PES	ESC	60	-8.3	S	0.000259 U	0.000228 U	**8.37**	0.000480 U	**0.0176 J**	0.000295 U	0.000861 U	**0.191 J**	0.000423 U	0.00264 U	**0.00534**	0.000772 U
	IW-48B-65	3/23/18	PES	ESC	65	-13.3	S	0.000276 U	0.000243 U	**0.154**	0.000513 U	**0.00172**	0.000315 U	0.000919 U	**0.00448**	0.000451 U	0.00282 U	**0.00410**	0.000825 U
	IW-48B-70	3/23/18	PES	ESC	70	-18.3	S	0.000257 U	0.000226 U	**0.0158**	0.000477 U	0.000290 U	0.000294 U	0.000855 U	**0.000853 J**	0.000420 U	0.00263 U	**0.00248**	0.000767 U
	IW-48B-75	3/23/18	PES	ESC	75	-23.3	S	0.000263 U	0.000232 U	**24.4**	0.000488 U	**0.000968 J**	0.000300 U	0.000875 U	**0.932**	0.000430 U	0.00269 U	**0.00760**	0.000785 U
IW-50A (9.8 to-10.2)	IW-50A-5	3/27/18	PES	ESC	5	46.9	V	0.000267 U	0.000235 U	**0.0105**	0.000495 U	0.000301 U	0.000305 U	0.000888 U	0.000318 U	0.000436 U	0.00273 U	0.000332 U	0.000797 U
	IW-50A-10	3/27/18	PES	ESC	10	41.9	V	0.000261 U	0.000230 U	**0.00526**	0.000484 U	0.000294 U	0.000298 U	0.000867 U	**0.00365**	0.000426 U	0.00266 U	0.000324 U	0.000778 U
	IW-50A-15	3/27/18	PES	ESC	15	36.9	V	0.000257 U	0.000226 U	**0.00323**	0.000477 U	0.000290 U	0.000293 U	0.000855 U	**0.00225**	0.000420 U	0.00263 U	0.000320 U	0.000767 U
	IW-50A-20	3/27/18	PES	ESC	20	31.9	S	0.000260 U	0.000229 U	**0.00173**	0.000482 U	0.000293 U	0.000297 U	0.000865 U	0.000310 U	0.000425 U	0.00266 U	0.000323 U	0.000776 U
	IW-50A-25	3/27/18	PES	ESC	25	26.9	S	0.000253 U	0.000223 U	**0.0149**	0.000470 U	**0.000640 J**	0.000289 U	0.000842 U	**0.00376**	0.000413 U	0.00259 U	0.000315 U	0.000755 U
	IW-50A-30	3/27/18	PES	ESC	30	21.9	S	0.000254 U	0.000224 U	**0.00643**	0.000471 U	0.000287 U	0.000290 U	0.000845 U	**0.00146**	0.000415 U	0.00260 U	0.000316 U	0.000758 U
	IW-50A-35	3/27/18	PES	ESC	35	16.9	S	0.000255 U	0.000224 U	**0.00599**	0.000473 U	0.000287 U	0.000291 U	0.000847 U	**0.00158**	0.000416 U	0.00260 U	0.000317 U	0.000760 U
	IW-50A-40	3/27/18	PES	ESC	40	11.9	S	0.000259 U	0.000228 U	**0.00647**	0.000480 U	0.000292 U	0.000295 U	0.000860 U	**0.00188**	0.000422 U	0.00264 U	0.000322 U	0.000771 U
	IW-50A-42	3/27/18	PES	ESC	42	9.9	S	0.000257 U	0.000226 U	**0.0263**	0.000477 U	0.000290 U	0.000293 U	0.000855 U	**0.00273**	0.000420 U	0.00263 U	**0.00893**	0.000767 U
	IW-50A-45	3/27/18	PES	ESC	45	6.9	S	0.000259 U	0.000228 U	**2.10**	0.000481 U	0.000292 U	0.000296 U	0.000861 U	**0.0367**	0.000423 U	0.00265 U	**0.00501**	0.000773 U
	IW-50A-50	3/27/18	PES	ESC	50	1.9	S	0.000263 U	0.000231 U	**2.67 J**	0.000487 U	0.000296 U	0.000300 U	0.000873 U	**0.0210 J**	0.000429 U	0.00268 U	**0.0112**	0.000783 U
	IW-906-50	3/27/18	PES	ESC	50 (dup)	1.9	S	0.000264 U	0.000233 U	**0.0849 J**	0.000490 U	0.000298 U	0.000301 U	0.000878 U	**0.00989 J**	0.000431 U	0.00270 U	**0.0119**	0.000788 U
	IW-50A-55	3/27/18	PES	ESC	55	-3.2	S	0.000263 U	0.000232 U	**0.0127**	0.000488 U	0.000297 U	0.000300 U	0.000876 U	**0.00151**	0.000430 U	0.00269 U	**0.00993**	0.000786 U
	IW-50A-60	3/27/18	PES	ESC	60	-8.2	S	0.000264 U	0.000233 U	**0.00210**	0.000490 U	0.000298 U	0.000302 U	0.000879 U	0.000315 U	0.000431 U	0.00270 U	**0.00363**	0.000788 U
IW-51A (9.9 to-10.1)	IW-51A-5	3/26/18	PES	ESC	5	46.9	V	0.000257 U	0.000227 U	**0.00410**	0.000477 U	0.000290 U	0.000294 U	0.000856 U	0.000307 U	0.000420 U	0.00263 U	0.000320 U	0.000768 U
	IW-51A-10	3/26/18	PES	ESC	10	41.9	V	0.000255 U	0.000225 U	**0.00112**	0.000473 U	0.000288 U	0.000291 U	0.000848 U	0.000304 U	0.000417 U	0.00261 U	0.000317 U	0.000761 U
	IW-51A-15	3/26/18	PES	ESC	15	36.9	V	0.000265 U	0.000234 U	**0.00450**	0.000492 U	0.000299 U	0.000303 U	0.000882 U	0.000316 U	0.000433 U	0.00271 U	0.000330 U	0.000792 U
	IW-51A-20	3/26/18	PES	ESC	20	31.9	S	0.000254 U	0.000223 U	**0.00211**	0.000470 U	0.000286 U	0.000289 U	0.000843 U	0.000302 U	0.000414 U	0.00259 U	0.000315 U	0.000756 U
	IW-51A-25	3/26/18	PES	ESC	25	26.9	S	0.000323 U	0.000285 U	**5.20**	0.000599 U	**0.000506 J**	0.000369 U	0.00107 U	**0.0410**	0.000527 U	0.00330 U	0.000401 U	0.000963 U
	IW-51A-30	3/26/18	PES	ESC	30	21.9	S	0.000252 U	0.000222 U	**3.14**	0.000468 U	0.000284 U	0.000288 U	0.000838 U	**0.0147**	0.000412 U	0.00258 U	0.000314 U	0.000752 U
	IW-51A-35	3/26/18	PES	ESC	35	16.9	S	0.000255 U	0.000224 U	**0.00981**	0.000473 U	0.000287 U	0.000291 U	0.000847 U	0.000304 U	0.000416 U	0.00260 U	**0.000805 J**	0.000760 U
	IW-51A-40	3/26/18	PES	ESC	40	11.9	S	0.000256 U	0.000225 U	**0.101**	0.000474 U	**0.000872 J**	0.000292 U	0.000850 U	**0.00781**	0.000417 U	0.00261 U	**0.0155**	0.000763 U
	IW-51A-42	3/26/18	PES	ESC	42	9.9	S	0.000260 U	0.000229 U	**2.97**	0.000483 U	**0.00244**	0.000297 U	0.000866 U	**0.0397**	0.000425 U	0.00266 U	**0.0869 J**	0.000777 U
	IW-51A-45	3/26/18	PES	ESC	45	6.9	S	0.000261 U	0.000229 U	**0.125**	0.000483 U	0.000294 U	0.000297 U	0.000866 U	0.000311 U	0.000425 U	0.00266 U	**0.0448**	0.000777 U
	IW-51A-50	3/26/18	PES	ESC	50	1.9	S	0.000268 U	0.000236 U	**1.36**	0.000497 U	**0.000572 J**	0.000306 U	0.000891 U	**0.0165**	0.000438 U	0.00274 U	**0.00557**	0.000800 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
IW-51A (continued)	IW-51A-55	3/26/18	PES	ESC	55	-3.1	S	0.000268 U	0.000236 U	**0.103**	0.000498 U	0.000303 U	0.000306 U	0.000892 U	**0.00933**	0.000438 U	0.00274 U	**0.00612**	0.000800 U
	IW-51A-60	3/26/18	PES	ESC	60	-8.1	S	0.000252 U	0.000222 U	**0.000796 J**	0.000467 U	0.000284 U	0.000287 U	0.000837 U	0.000300 U	0.000411 U	0.00257 U	**0.000706 J**	0.000751 U
	IW-51A-62	3/26/18	PES	ESC	62	-10.1	S	0.000255 U	0.000224 U	**0.000824 J**	0.000472 U	0.000287 U	0.000290 U	0.000846 U	0.000303 U	0.000415 U	0.00260 U	**0.00354**	0.000759 U
IW-53B (-11.1 to-26.1)	IW-53B-30	9/20/18	PES	ESC	30	5.3	S	0.00297 U	0.00169 U	**1.74**	**0.00303 J**	**0.00381**	0.00166 U	0.00152 U	**0.152**	0.000544 U	0.00383 U	**0.00790**	0.00520 U
IW-54A (9.8 to-10.2)	IW-54A-8	9/12/18	PES	ESC	8	31.1	S	0.00315 U	0.00179 U	**48.1**	**0.00424 J**	0.00165 U	0.00177 U	0.00162 U	**0.0503**	0.000577 U	0.00406 U	0.000778 U	0.00552 U
	IW-54A-49	9/12/18	PES	ESC	49	-9.9	S	0.00316 U	0.00180 U	**0.0827**	**0.00537 J**	0.00166 U	0.00177 U	0.00162 U	0.000463 U	0.000579 U	0.00408 U	0.000791 U	0.00554 U
IW-54B (-9.5 to-24.5)	IW-54B-8	9/5/18	PES	ESC	8	31.2	S	0.00298 U	0.00169 U	**937**	**0.00476 J**	0.00156 UJ	0.00167 U	0.00153 U	**0.922 J**	0.000545 U	0.00384 U	**0.00293**	10.4 U
	IW-54B-13	9/6/18	PES	ESC	13	26.2	S	0.00303 U	0.00172 U	**2.21**	0.00139 U	0.00159 UJ	0.00170 U	0.00155 U	**0.0456**	0.000555 U	0.00390 U	0.000758 U	0.0530 U
	IW-54B-21	9/6/18	PES	ESC	21	18.2	S	0.00298 U	0.00169 U	**11.0**	**0.00277 J**	**0.00612 J**	0.00167 U	0.00153 U	**4.48**	0.000546 U	0.00384 U	0.000745 U	0.104 U
	IW-54B-33	9/6/18	PES	ESC	33	6.2	S	0.00341 U	0.00193 U	**0.0689**	**0.00246 J**	0.00179 UJ	0.00191 U	0.00175 U	**0.0349**	0.000625 U	0.00440 U	**0.0927**	0.00592 U
IW-55B (-12.0 to-27.0)	IW-55B-39	9/13/18	PES	ESC	39	12.8	S	0.00290 U	0.00165 U	**1.13**	**0.00173 J**	0.00152 U	0.00162 U	0.00149 U	**0.0340**	0.000531 U	0.00374 U	0.000725 U	0.00508 U
	IW-55B-43	9/13/18	PES	ESC	43	8.8	S	0.00309 U	0.00175 U	**47.1**	0.00141 U	0.00162 U	0.00173 U	0.00158 U	**1.04**	0.000566 U	0.00398 U	**0.0522**	0.00541 U
	IW-55B-61	9/13/18	PES	ESC	61	-9.2	S	0.00324 U	0.00184 U	**0.343**	**0.00745**	**0.0213**	0.00182 U	0.00166 U	**0.0155**	0.000594 U	0.00418 U	**0.341**	0.00568 U
IW-58A (3.9 to-11.1)	IW-58A-38	10/17/18	PES	PACE	38	1.2	S	0.00298 U	0.00169 U	**2.67 J**	**0.00206 J**	**0.0323**	0.00167 U	0.00153 U	**0.279**	0.000547 U	0.00385 U	**0.0128**	0.00522 U
	B-929-38	10/17/18	PES	PACE	38 (dup)	1.2	S	0.00307 U	0.00175 U	**2.31 J**	**0.00250 J**	**0.0456**	0.00172 U	0.00158 U	**0.201**	0.000563 U	0.00396 U	**0.0167**	0.00538 U
MW101 (B101) (-65.5 to-75.5)	B101-30	7/10/12	SES	F&BI	30	9.5	S	–	–	**24**	–	0.050 U	–	–	**0.12**	–	–	0.050 U	–
	B101-34	7/10/12	SES	F&BI	34	5.5	S	–	–	**8.4**	–	0.050 U	–	–	**0.033**	–	–	0.050 U	–
	B101-40	7/10/12	SES	F&BI	40	-0.5	S	–	–	**20**	–	0.050 U	–	–	**0.28**	–	–	0.050 U	–
	B101-47	7/10/12	SES	F&BI	47	-7.5	S	–	–	**7.2**	–	0.050 U	–	–	**0.20**	–	–	0.050 U	–
	B101-48	7/10/12	SES	F&BI	48	-8.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B101-55	7/10/12	SES	F&BI	55	-15.5	S	–	–	**4.2**	–	0.050 U	–	–	**0.084**	–	–	0.050 U	–
	B101-65	7/10/12	SES	F&BI	65	-25.5	S	–	–	0.025 U	–	0.050 U	–	–	0.030 U	–	–	0.050 U	–
	B101-75	7/11/12	SES	F&BI	75	-35.5	S	–	–	0.025 U	–	0.050 U	–	–	0.030 U	–	–	0.050 U	–
	B101-81	7/11/12	SES	F&BI	81	-41.5	S	–	–	**0.31**	–	0.050 U	–	–	0.030 U	–	–	0.050 U	–
	B101-92	7/12/12	SES	F&BI	92	-52.5	S	–	–	0.025 U	–	0.050 U	–	–	0.030 U	–	–	0.050 U	–
	B101-97	7/12/12	SES	F&BI	97	-57.5	S	–	–	0.025 U	–	0.050 U	–	–	0.030 U	–	–	0.050 U	–
	B101-104	7/12/12	SES	F&BI	104	-64.5	S	–	–	0.025 U	–	0.050 U	–	–	0.030 U	–	–	0.050 U	–
	B101-114.5	7/12/12	SES	F&BI	114.5	-75.0	S	–	–	0.025 U	–	0.050 U	–	–	0.030 U	–	–	0.050 U	–
	B101-120	7/12/12	SES	F&BI	120	-80.5	S	–	–	0.025 U	–	0.050 U	–	–	0.030 U	–	–	0.050 U	–
	B101-131	7/12/12	SES	F&BI	131	-91.5	S	–	–	0.025 U	–	0.050 U	–	–	0.030 U	–	–	0.050 U	–
	B101-140	7/12/12	SES	F&BI	140	-100.5	S	–	–	0.025 U	–	0.050 U	–	–	0.030 U	–	–	0.050 U	–
MW130 (B130) (-30.9 to-40.9)	B130-10	3/1/16	SES	F&BI	10	29.5	S	–	–	**0.17**	–	0.050 U	–	–	**0.040**	–	–	0.050 U	–
	B130-20	3/1/16	SES	F&BI	20	19.5	S	–	–	**0.82**	–	0.050 U	–	–	**0.054**	–	–	0.050 U	–
	B130-30	3/1/16	SES	F&BI	30	9.5	S	–	–	0.025 U	–	0.050 U	–	–	0.020 U	–	–	0.050 U	–
	B130-40	3/1/16	SES	F&BI	40	-0.5	S	–	–	**0.032**	–	0.050 U	–	–	0.020 U	–	–	0.050 U	–
	B130-45	3/2/16	SES	F&BI	45	-5.5	S	–	–	0.025 U	–	0.050 U	–	–	0.020 U	–	–	0.050 U	–
	B130-50	3/2/16	SES	F&BI	50	-10.5	S	–	–	0.025 U	–	0.050 U	–	–	0.020 U	–	–	0.050 U	–
	B130-55	3/2/16	SES	F&BI	55	-15.5	S	–	–	0.025 U	–	0.050 U	–	–	0.020 U	–	–	0.050 U	–
	B130-60	3/2/16	SES	F&BI	60	-20.5	S	–	–	**0.086**	–	0.050 U	–	–	0.020 U	–	–	0.050 U	–
	B130-65	3/2/16	SES	F&BI	65	-25.5	S	–	–	**1.9**	–	0.050 U	–	–	**0.079**	–	–	0.050 U	–
	B130-70	3/2/16	SES	F&BI	70	-30.5	S	–	–	**37 ve**	–	0.050 U	–	–	**0.44**	–	–	0.050 U	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
MW130 (B130)	B130-75	3/2/16	SES	F&BI	75	-35.5	S	–	–	**2.9**	–	0.050 U	–	–	**0.058**	–	–	0.050 U	–
(continued)	B130-80	3/2/16	SES	F&BI	80	-40.5	S	–	–	**0.59**	–	0.050 U	–	–	0.020 U	–	–	0.050 U	–
MW131 (B131)	B131-10	3/1/16	SES	F&BI	10	30.0	S	–	–	0.025 U	–	0.050 U	–	–	0.020 U	–	–	0.050 U	–
(-4.2 to-14.2)	B131-20	3/1/16	SES	F&BI	20	20.0	S	–	–	0.025 U	–	0.050 U	–	–	0.020 U	–	–	0.050 U	–
	B131-30	3/1/16	SES	F&BI	30	10.0	S	–	–	**0.097**	–	**0.064**	–	–	**2.4**	–	–	0.050 U	–
	B131-40	3/1/16	SES	F&BI	40	0.0	S	–	–	0.025 U	–	0.050 U	–	–	0.020 U	–	–	0.050 U	–
	B131-45	3/2/16	SES	F&BI	45	-5.0	S	–	–	**0.21**	–	0.050 U	–	–	**0.036**	–	–	0.050 U	–
	B131-55	3/2/16	SES	F&BI	55	-15.0	S	–	–	**0.44**	–	0.050 U	–	–	**0.60**	–	–	0.050 U	–
MW-132	MW-132-20	8/22/17	PES	ESC	20	20.1	S	0.000261 U	0.000230 U	**0.000312 J**	0.000484 U	**0.000443 J**	0.000298 U	0.000868 U	**0.000380 J**	0.000426 U	0.00266 U	**0.00217**	0.000778 U
(-29.9 to-39.9)	MW-132-35	8/22/17	PES	ESC	35	5.1	S	0.000262 U	0.000230 U	**0.00166**	0.000486 U	0.000295 U	0.000299 U	0.000871 U	0.000312 U	0.000427 U	0.00267 U	0.00377 UJ	0.000781 U
	MW-132-50	8/22/17	PES	ESC	50	-9.9	S	0.000253 U	0.000223 U	**0.109**	0.000470 U	**0.0405**	0.000289 U	0.000842 U	**0.153**	0.000413 U	0.00259 U	**0.00219**	0.000755 U
	MW-132-55	8/23/17	PES	ESC	55	-14.9	S	0.0269 U	0.0237 U	**385**	0.0499 U	**0.0725 J**	0.0307 U	0.0895 U	**9.63**	0.0439 U	0.275 U	0.0335 U	0.0803 U
	MW-132-60	8/23/17	PES	ESC	60	-19.9	S	0.000252 U	0.000222 U	**3.92**	0.000467 U	**0.000785 J**	0.000288 U	0.000838 U	**4.60**	0.000411 U	0.00257 U	**0.000808 J**	0.000752 U
	MW-132-70	8/23/17	PES	ESC	70	-29.9	S	0.000285 U	0.000251 U	**0.00905 J**	0.000529 U	0.000322 U	0.000325 U	0.000948 U	0.00851 U	0.000466 U	0.00291 U	0.000355 U	0.000851 U
	MW-132-83	8/23/17	PES	ESC	83	-42.9	S	0.000255 U	0.000225 U	0.00753 U	0.000473 U	0.000288 U	0.000291 U	0.000849 U	0.000304 U	0.000417 U	0.00261 U	0.000317 U	0.000761 U
MW-133	MW-133-20	8/15/17	PES	ESC	20	20.1	S	0.000276 U	0.000243 U	**3.62**	0.000511 U	**0.000591 J**	0.000315 U	0.000917 U	**0.0688**	0.000450 U	0.00282 U	**0.000389 J**	0.000823 U
(-88.9 to-98.9)	MW-133-35	8/15/17	PES	ESC	35	5.1	S	0.000306 U	0.000269 U	0.00901 U	0.000567 U	0.000345 U	0.000349 U	0.00102 U	**0.000594 J**	0.000499 U	0.00312 U	0.000380 U	0.000911 U
	MW-133-45	8/15/17	PES	ESC	45	-4.9	S	0.000254 U	0.000224 U	**5.17**	0.000472 U	**0.00508**	0.000290 U	0.000846 U	**0.0309**	0.000415 U	0.00260 U	**0.323**	0.000759 U
	MW-133-55	8/15/17	PES	ESC	55	-14.9	S	0.0572 U	0.0504 U	**114**	0.106 U	0.0646 U	0.0653 U	0.191 U	**0.988**	0.0935 U	0.585 U	0.0712 U	0.171 U
	MW-133-58	8/15/17	PES	ESC	58	-17.9	S	1.38 U	1.22 U	**691**	2.57 U	1.56 U	1.58 U	4.60 U	1.66 U	2.26 U	14.2 U	1.73 U	4.13 U
	MW-133-65	8/15/17	PES	ESC	65	-24.9	S	0.000271 U	0.000238 U	**36.0**	0.000502 U	**0.00123**	0.000309 U	0.000901 U	**2.96**	0.000442 U	0.00277 U	**0.00631**	0.000808 U
	MW-133-75	8/15/17	PES	ESC	75	-34.9	S	0.000272 U	0.000240 U	**0.0468 J**	0.000505 U	0.000307 U	0.000311 U	0.000905 U	**0.000647 J**	0.000444 U	0.00278 U	0.000339 U	0.000812 U
	MW-133-85	8/15/17	PES	ESC	85	-44.9	S	0.00686 U	0.00604 U	**2.28**	**0.580**	0.00774 U	0.00783 U	0.0227 U	**0.146**	0.0112 U	0.0701 U	0.00853 U	0.0204 U
	MW-133-95	8/16/17	PES	ESC	95	-54.9	S	0.000273 U	0.000240 U	**0.00127**	0.000506 U	0.000308 U	0.000311 U	0.000906 U	0.000325 U	0.000445 U	0.00278 U	0.000339 U	0.000813 U
	MW-133-105	8/16/17	PES	ESC	105	-64.9	S	0.000282 U	0.000248 U	**0.000345 J**	0.000523 U	0.000318 U	0.000321 U	0.000937 U	0.000336 U	0.000460 U	0.00288 U	0.000350 U	0.000840 U
	MW-133-120	8/16/17	PES	ESC	120	-79.9	S	0.00636 U	0.00560 U	0.00750 U	0.0117 U	0.00717 U	0.00726 U	0.0211 U	0.00759 U	0.0104 U	0.0650 U	0.00791 U	0.0189 U
	MW-133-130	8/16/17	PES	ESC	130	-89.9	S	0.000279 U	0.000245 U	**0.0119**	0.000517 U	0.000314 U	0.000318 U	0.000927 U	**0.00354**	0.000455 U	0.00285 U	0.000347 U	0.000832 U
	MW-133-135	8/16/17	PES	ESC	135	-94.9	S	**0.000429 J**	0.000233 U	**0.0107**	**0.0119**	0.000299 U	0.000302 U	0.000881 U	**0.000965 J**	0.000433 U	0.00271 U	0.000330 U	**0.00392**
	MW-133-141	8/16/17	PES	ESC	141	-100.9	S	0.000264 U	0.000232 U	0.000311 U	0.000489 U	0.000297 U	0.000301 U	0.000876 U	0.000314 U	0.000430 U	0.00269 U	0.000328 U	0.000786 U
MW-134	MW-134-20	8/29/17	PES	ESC	20	21.5	S	0.000308 U	0.000271 U	0.000363 U	0.000571 U	0.000347 U	0.000351 U	0.00102 U	0.000367 U	0.000503 U	0.00315 U	0.000383 U	0.000919 U
(-38.6 to-48.6)	MW-134-43	8/29/17	PES	ESC	43	-1.6	S	0.000272 U	0.000239 U	**0.00863**	0.000504 U	**0.0111 J**	0.000310 U	0.000903 U	**0.0551**	0.000443 U	0.00277 U	**0.217**	0.000810 U
	MW-134-50	8/29/17	PES	ESC	50	-8.6	S	0.000257 U	0.000226 U	**17.9**	0.000477 U	0.0290 U	0.000294 U	0.000855 U	**2.34**	0.000420 U	0.00263 U	**0.0196**	0.000767 U
	MW-134-60	8/29/17	PES	ESC	60	-18.6	S	0.000258 U	0.000227 U	**0.0770**	0.000479 U	0.00729 U	0.000295 U	0.000859 U	**0.00544**	0.000422 U	0.00264 U	**0.0118**	0.000771 U
	MW-134-70	8/29/17	PES	ESC	70	-28.6	S	0.000298 U	0.000263 U	**0.0742**	0.000554 U	0.000337 U	0.000341 U	0.000992 U	**0.0111**	0.000487 U	0.00305 U	**0.0426**	0.000890 U
	MW-134-80	8/29/17	PES	ESC	80	-38.6	S	0.000250 U	0.000220 U	**0.0105 J**	0.000464 U	0.000282 U	0.000286 U	0.000832 U	**0.00316 J**	0.000409 U	0.00256 U	**0.00656 J**	0.000746 U
	B-903-100	8/29/17	PES	ESC	80 (dup)	-38.6	S	0.000247 U	0.000217 U	**0.0407 J**	0.000457 U	0.000278 U	0.000281 U	0.000820 U	**0.0132 J**	0.000402 U	0.00252 U	**0.0143 J**	0.000735 U
	MW-134-90	8/29/17	PES	ESC	90	-48.6	S	0.000297 U	0.000262 U	**0.000676 J**	0.000551 U	0.00838 U	0.000339 U	0.000988 U	0.000354 U	0.000485 U	0.00304 U	0.000370 U	0.000886 U
MW-135	MW-135-16	8/24/17	PES	ESC	14	25.1	S	0.0285 U	**0.0271 J**	**933**	**0.166 J**	**0.700**	0.0326 U	0.0949 U	**113**	0.0466 U	0.292 U	**17.0**	**0.331 J**
(-30.9 to-40.9)	MW-135-20	8/24/17	PES	ESC	20	19.1	S	0.00666 U	0.00587 U	**1.73**	0.0123 U	0.00752 U	0.00761 U	0.0221 U	**0.461**	0.0109 U	0.0681 U	**0.0241 J**	0.0198 U
	MW-135-30	8/24/17	PES	ESC	30	9.1	S	0.000249 U	**0.000237 J**	**109**	**0.00159 J**	**0.00363**	0.000284 U	0.000826 U	**2.90**	0.000406 U	0.00254 U	**0.0430**	**0.00135 J**
	MW-135-36	8/24/17	PES	ESC	36	3.1	S	0.000273 U	0.000241 U	**20.1**	0.000507 U	**0.000907 J**	0.000312 U	0.000908 U	**0.0571**	0.000446 U	0.00279 U	**0.00962**	0.000815 U
	MW-135-40	8/24/17	PES	ESC	40	-0.9	S	0.000279 U	0.000246 U	**10.6**	0.000518 U	**0.00769**	0.000318 U	0.000928 U	**2.71**	0.000456 U	0.00285 U	**0.405**	0.000832 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
MW-135 (continued)	MW-135-45	8/24/17	PES	ESC	45	-5.9	S	0.000278 U	0.000245 U	**69.7**	0.000515 U	**0.00859**	0.000317 U	0.000924 U	**3.10**	0.000454 U	0.00284 U	**0.00963**	0.000829 U
	MW-135-55	8/24/17	PES	ESC	55	-15.9	S	0.000254 U	0.000224 U	**8.68**	0.000471 U	0.000287 U	0.000290 U	0.000845 U	**0.0673**	0.000415 U	0.00260 U	**0.00105 J**	0.000758 U
	MW-135-65	8/24/17	PES	ESC	65	-25.9	S	0.000278 U	0.000244 U	**0.190**	0.000515 U	0.000313 U	0.000317 U	0.000923 U	**0.00881**	0.000453 U	0.00284 U	0.000345 U	0.000828 U
	MW-135-80	8/24/17	PES	ESC	80	-40.9	S	0.000261 U	0.000230 U	**0.0106**	0.000485 U	0.000295 U	0.000298 U	0.000869 U	**0.000372 J**	0.000427 U	0.00267 U	0.000325 U	0.000780 U
MW-136 (-32.7 to-42.7)	MW-136-35	8/28/17	PES	ESC	35	16.9	S	0.000246 U	0.000217 U	**0.00777**	0.000457 U	0.000278 U	0.000281 U	0.000819 U	**0.000437 J**	0.000402 U	0.00252 U	0.000306 U	0.000735 U
	B-902-15	8/28/17	PES	ESC	35 (dup)	16.9	S	0.000256 U	0.000225 U	**0.00621**	0.000474 U	0.000288 U	0.000292 U	0.000850 U	**0.000324 J**	0.000417 U	0.00261 U	0.000318 U	0.000762 U
	MW-136-44	8/28/17	PES	ESC	44	7.9	S	0.000263 U	0.000231 U	0.0853 UJ	0.000487 U	0.000296 U	0.000300 U	0.000873 U	**0.00255**	0.000429 U	0.00268 U	0.000327 U	0.000783 U
	MW-136-50	8/28/17	PES	ESC	50	1.9	S	0.000269 U	0.000237 U	0.000318 U	0.000499 U	0.00759 U	0.000307 U	0.000895 U	0.000321 U	0.000440 U	0.00275 U	0.000335 U	0.000803 U
	MW-136-65	8/28/17	PES	ESC	65	-13.1	S	0.000254 U	0.000224 U	0.000300 U	0.000472 U	0.000287 U	0.000290 U	0.000846 U	0.000303 U	0.000415 U	0.00260 U	0.000316 U	0.000759 U
	MW-136-75	8/28/17	PES	ESC	75	-23.1	S	0.000260 U	0.000229 U	0.000307 U	0.000482 U	0.000293 U	0.000297 U	0.000864 U	0.000310 U	0.000424 U	0.00266 U	0.000323 U	0.000775 U
	MW-136-85	8/28/17	PES	ESC	85	-33.1	S	0.000261 U	0.000230 U	0.000308 U	0.000485 U	0.000295 U	0.000298 U	0.000869 U	0.000311 U	0.000426 U	0.00267 U	0.000325 U	0.000779 U
	MW-136-95	8/28/17	PES	ESC	95	-43.1	S	0.000262 U	0.000231 U	0.000309 U	0.000486 U	0.000295 U	0.000299 U	0.000871 U	0.000312 U	0.000427 U	0.00267 U	0.000326 U	0.000781 U
MW-137 (-53.3 to-63.3)	MW-137-25	8/31/17	PES	ESC	25	26.7	S	0.000255 U	0.000225 U	**0.00174**	0.000473 U	0.000288 U	0.000291 U	0.000849 U	**0.00245**	0.000417 U	0.00261 U	0.000317 U	0.000761 U
	MW-137-45	8/31/17	PES	ESC	45	6.7	S	0.00662 U	0.00583 U	0.00781 U	0.0122 U	0.00747 U	0.00756 U	0.0220 U	0.00790 U	0.0108 U	0.0677 U	0.00824 U	0.0197 U
	MW-137-75	8/31/17	PES	ESC	75	-23.3	S	0.000257 U	0.000226 U	0.000303 U	0.000477 U	0.000290 U	0.000293 U	0.000854 U	0.000306 U	0.000419 U	0.00262 U	0.000319 U	0.000766 U
	MW-137-85	9/1/17	PES	ESC	85	-33.3	S	0.000280 U	0.000247 U	0.000331 U	0.000520 U	0.000316 U	0.000320 U	0.000932 U	0.000334 U	0.000458 U	0.00286 U	0.000349 U	0.000837 U
	MW-137-95	9/1/17	PES	ESC	95	-43.3	S	0.000251 U	0.000221 U	0.000296 U	0.000465 U	0.000283 U	0.000286 U	0.000833 U	0.000299 U	0.000409 U	0.00256 U	0.000312 U	0.000747 U
	MW-137-115	9/1/17	PES	ESC	115	-63.3	S	0.000286 U	0.000252 U	0.000338 U	0.000531 U	0.000323 U	0.000327 U	0.000952 U	0.000341 U	0.000467 U	0.00292 U	0.000356 U	0.000854 U
MW-139 (-30.2 to-40.2)	MW-139-20	9/13/17	PES	ESC	20	19.8	S	0.000271 U	0.000238 U	**0.0138 J**	0.000502 U	0.000305 U	0.000309 U	0.0276 U	0.000323 U	0.000442 U	0.00276 U	**0.00397**	0.000807 U
	MW-139-31	9/13/17	PES	ESC	31	8.8	S	0.000250 U	0.000220 U	**0.00308**	0.000464 U	0.000282 U	0.000286 U	0.000832 U	**0.000467 J**	0.000409 U	0.00256 U	**0.00139**	0.000747 U
	MW-139-41	9/13/17	PES	ESC	41	-1.2	S	0.000251 U	0.000221 U	**0.0126**	0.000466 U	**0.000407 J**	0.000287 U	0.000836 U	**0.00100 J**	0.000410 U	0.00257 U	**0.00209**	0.000750 U
	MW-139-51	9/13/17	PES	ESC	51	-11.2	S	0.000270 U	0.000238 U	**0.000397 J**	0.000501 U	0.000305 U	0.000308 U	0.000898 U	0.000322 U	0.000441 U	0.00276 U	0.000336 U	0.000805 U
	MW-139-60	9/13/17	PES	ESC	60	-20.2	S	0.000251 U	0.000221 U	0.000296 U	0.000466 U	0.000284 U	0.000287 U	0.000836 U	0.000300 U	0.000410 U	0.00257 U	0.000313 U	0.000750 U
	MW-139-70	9/13/17	PES	ESC	70	-30.2	S	0.000276 U	0.000243 U	0.000326 U	0.000512 U	0.000312 U	0.000315 U	0.000918 U	0.000329 U	0.000451 U	0.00282 U	0.000343 U	0.000824 U
	MW-139-80	9/13/17	PES	ESC	80	-40.2	S	0.000264 U	0.000233 U	0.000780 U	0.000490 U	0.000298 U	0.000302 U	0.0219 U	0.000315 U	0.000432 U	0.00270 U	0.000329 U	0.000789 U
MW-141 (-55.4 to-65.4)	MW-141-15	9/18/17	PES	ESC	15	24.6	S	0.000264 U	0.000232 U	0.000311 U	0.000490 U	0.000298 U	0.000301 U	0.000878 U	0.000315 U	0.000431 U	0.00270 U	**0.000388 J**	0.000787 U
	MW-141-35	9/18/17	PES	ESC	35	4.6	S	0.000271 U	0.000239 U	0.000320 U	0.000504 U	0.000306 U	0.000310 U	0.000903 U	0.000324 U	0.000443 U	0.00277 U	0.000338 U	0.000810 U
	MW-141-46	9/18/17	PES	ESC	46	-6.4	S	0.000256 U	0.000225 U	**0.000357 J**	0.000475 U	0.000289 U	0.000292 U	0.000851 U	**0.000424 J**	0.000418 U	0.00261 U	**0.00194**	0.000763 U
	MW-141-56	9/18/17	PES	ESC	56	-16.4	S	0.000249 U	0.000219 U	0.000294 U	0.000462 U	0.000281 U	0.000284 U	0.000828 U	0.000297 U	0.000406 U	0.00254 U	0.000310 U	0.000742 U
	MW-141-65	9/18/17	PES	ESC	65	-25.4	S	0.000246 U	0.000217 U	0.000290 U	0.000457 U	0.000278 U	0.000281 U	0.000818 U	0.000293 U	0.000402 U	0.00251 U	0.000306 U	0.000734 U
	MW-141-75	9/18/17	PES	ESC	75	-35.4	S	0.000249 U	0.000220 U	0.000294 U	0.000463 U	0.000281 U	0.000285 U	0.000829 U	0.000297 U	0.000407 U	0.00255 U	0.000310 U	0.000744 U
	MW-141-85	9/18/17	PES	ESC	85	-45.4	S	0.000273 U	0.000241 U	0.000322 U	0.000507 U	0.000308 U	0.000312 U	0.000909 U	0.000326 U	0.000446 U	0.00279 U	0.000340 U	0.000815 U
	MW-141-95	9/18/17	PES	ESC	95	-55.4	S	0.000280 U	0.000247 U	0.000331 U	0.000520 U	0.000316 U	0.000320 U	0.000932 U	0.000334 U	0.000458 U	0.00286 U	0.000349 U	0.000836 U
	MW-141-105	9/19/17	PES	ESC	105	-65.4	S	0.000279 U	0.000246 U	0.000330 U	0.000518 U	0.000315 U	0.000319 U	0.000929 U	0.000333 U	0.000456 U	0.00285 U	0.000347 U	0.000833 U
MW-152 (-10.2 to-20.2)	MW-152-5	3/13/18	PES	ESC	5	34.1	S	0.000264 U	0.000232 U	**0.116**	**0.000678 J**	0.000297 U	0.000301 U	0.000877 U	**0.000861 J**	0.000430 U	0.00269 U	0.000328 U	**0.00131 J**
	MW-152-15	3/13/18	PES	ESC	15	24.1	S	0.000259 U	0.000228 U	**6.12**	0.000481 U	0.000292 U	0.000296 U	0.000862 U	**0.101**	0.000423 U	0.00265 U	0.000322 U	0.000773 U
	MW-152-25	3/13/18	PES	ESC	25	14.1	S	0.000254 U	0.000223 U	**0.276**	0.000471 U	**0.00188**	0.000290 U	0.000844 U	**0.00768**	0.000414 U	0.00259 U	**0.00488**	0.000757 U
	MW-152-35	3/13/18	PES	ESC	35	4.1	S	0.000257 U	0.000226 U	**1.23**	0.000476 U	**0.00168**	0.000293 U	0.000853 U	**0.0203**	0.000419 U	0.00262 U	**0.0282**	0.000765 U
	MW-152-45	3/13/18	PES	ESC	45	-5.9	S	0.000264 U	**0.000252 J**	**122**	**0.000853 J**	**0.00382**	0.000301 U	0.000877 U	**0.532 J**	0.000431 U	0.00269 U	**1.06**	**0.00173 J**
	MW-152-55	3/13/18	PES	ESC	55	-15.9	S	0.000265 U	0.000233 U	**57.4**	**0.000571 J**	**0.0117**	0.000302 U	0.000881 U	**0.0545**	0.000433 U	0.00271 U	**0.0949**	0.000791 U
	MW-152-60	3/13/18	PES	ESC	60	-20.9	S	0.000253 U	0.000223 U	**3.92**	0.000470 U	**0.000850 J**	0.000289 U	0.000842 U	**0.00733**	0.000413 U	0.00259 U	**0.0100**	0.000755 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
MW-162 (-61.6 to-71.6)	MW-162-48	1/28/19	PES	PACE	48	-9.6	S	0.0591 U	0.0335 U	**34.1**	0.0270 U	0.0309 U	0.0331 U	0.0303 U	**4.66**	0.0108 U	0.0762 U	0.0148 U	0.103 U
	MW-162-50	1/28/19	PES	PACE	50	-11.6	S	0.00319 U	0.00181 U	**5.26 J**	0.00146 U	**0.00213 J**	0.00179 U	0.00164 U	**1.11**	0.000584 U	0.00411 U	**0.00368**	0.00558 U
	B-930-50 (dup)	1/28/19	PES	PACE	50	-11.6	S	0.00304 U	0.00172 U	**13.7**	**0.00462 J**	**0.0107**	0.00170 U	0.00156 U	**5.91**	0.000556 U	0.00391 U	**0.0124**	0.00531 U
	MW-162-67	1/28/19	PES	PACE	67	-28.6	S	0.00317 U	0.00180 U	**9.41**	0.00145 U	0.00166 U	0.00178 U	0.00163 U	**0.900**	0.000581 U	0.00409 U	0.000793 U	0.00555 U
	MW-162-70	1/28/19	PES	PACE	70	-31.6	S	0.00305 U	0.00173 U	**21.7 J**	**0.00278 J**	**0.00593**	0.00171 U	0.00156 U	**1.67**	0.000558 U	0.00393 U	**0.0156**	0.00534 U
	MW-162-72	1/28/19	PES	PACE	72	-33.6	S	0.00295 U	0.00167 U	**11.6 J**	0.00135 U	0.00154 U	0.00165 U	0.00151 U	**0.613**	0.000539 U	0.00380 U	**0.00126 J**	0.00516 U
	MW-162-80	1/28/19	PES	PACE	80	-41.6	S	0.00304 U	0.00173 U	**0.150**	0.00139 U	**0.00256 J**	0.00170 U	0.00156 U	**0.0699**	0.000556 U	0.00392 U	**0.00787**	0.00532 U
	MW-162-85	1/28/19	PES	PACE	85	-46.6	S	0.00309 U	0.00175 U	**0.00281 J**	**0.00163 J**	0.00162 U	0.00173 U	0.00158 U	**0.00139**	0.000566 U	0.00398 U	0.000773 U	0.00541 U
	MW-162-90	1/28/19	PES	PACE	90	-51.6	S	0.00309 U	0.00175 U	**0.000964 J**	0.00141 U	0.00162 U	0.00173 U	0.00158 U	**0.00615**	0.000565 U	0.00398 U	0.000772 U	0.00540 U
	MW-162-95	1/28/19	PES	PACE	95	-56.6	S	0.00313 U	0.00178 U	**0.276 J**	0.00143 U	0.00164 U	0.00176 U	0.00161 U	**0.0152**	0.000574 U	0.00404 U	0.000784 U	0.00548 U
	MW-162-100	1/28/19	PES	PACE	100	-61.6	S	0.00319 U	0.00181 U	**0.00679 J**	0.00146 U	0.00167 U	0.00179 U	0.00163 U	0.000467 U	0.000584 U	0.00411 U	0.000797 U	0.00558 U
	MW-162-105	1/28/19	PES	PACE	105	-66.6	S	0.00307 U	0.00174 U	**0.0269 J**	0.00141 U	0.00161 U	0.00172 U	0.00157 U	**0.00349**	0.000562 U	0.00396 U	0.000768 U	0.00537 U
	MW-162-110	1/28/19	PES	PACE	110	-71.6	S	0.00299 U	0.00170 U	**0.00190 J**	0.00137 U	0.00157 U	0.00167 U	0.00153 U	0.000438 U	0.000547 U	0.00385 U	0.000748 U	0.00523 U
MW-163 (-61.0 to-71.0)	MW-163-47	1/29/19	PES	PACE	47	-7.7	S	0.00305 U	0.00173 U	**7.09 J**	**0.00160 J**	**0.0358**	0.00171 U	0.00157 U	**0.745**	0.000559 U	0.00394 U	**0.0322**	0.00535 U
	MW-163-50	1/29/19	PES	PACE	50	-10.7	S	0.00295 U	0.00167 U	**2.61 J**	**0.00254 J**	**0.132**	0.00165 U	0.00151 U	**0.128**	0.000540 U	0.00380 U	**0.189**	0.00516 U
	MW-163-55	1/29/19	PES	PACE	55	-15.7	S	0.00335 U	0.00190 U	**1.66 J**	**0.00286 J**	**0.0326**	0.00187 U	0.00172 U	**2.32**	0.000613 U	0.00431 U	**0.00971**	0.00585 U
	MW-163-60	1/29/19	PES	PACE	60	-20.7	S	0.00309 U	0.00175 U	**6.69 J**	**0.00189 J**	**0.0192**	0.00173 U	0.00158 U	**3.59 J**	0.000566 U	0.00398 U	**0.00599**	0.00541 U
	MW-163-80	1/29/19	PES	PACE	80	-40.7	S	0.00310 U	0.00176 U	**0.0191**	0.00142 U	**0.00306 J**	0.00174 U	0.00159 U	**0.0388**	0.000569 U	0.00400 U	0.000777 U	0.00544 U
	MW-163-85	1/29/19	PES	PACE	85	-45.7	S	0.00323 U	0.00183 U	**0.00202 J**	0.00148 U	0.00169 U	0.00181 U	0.00166 U	0.000473 U	0.000592 U	0.00417 U	0.000808 U	0.00566 U
	MW-163-90	1/29/19	PES	PACE	90	-50.7	S	0.00296 U	0.00168 U	**0.0806 J**	0.00136 U	**0.00614**	0.00166 U	0.00152 U	**0.0834**	0.000542 U	0.00382 U	0.000741 U	0.00518 U
	MW-163-95	1/29/19	PES	PACE	95	-55.7	S	0.00324 U	0.00184 U	**2.05**	**0.00264 J**	**0.00458 J**	0.00181 U	0.00166 U	**0.346**	0.000593 U	0.00417 U	0.000810 U	0.00567 U
	MW-163-100	1/29/19	PES	PACE	100	-60.7	S	0.00314 U	0.00178 U	**0.0109**	0.00144 U	0.00164 U	0.00176 U	0.00161 U	**0.00246**	0.000574 U	0.00404 U	0.000784 U	0.00549 U
	MW-163-105	1/29/19	PES	PACE	105	-65.7	S	0.00287 U	0.00163 U	**0.00124 J**	0.00131 U	0.00150 U	0.00161 U	0.00147 U	**0.00256**	0.000525 U	0.00370 U	0.000717 U	0.00502 U
	MW-163-110	1/29/19	PES	PACE	110	-70.7	S	0.00302 U	0.00172 U	**0.00134 J**	0.00138 U	0.00158 U	0.00170 U	0.00155 U	**0.000687 J**	0.000554 U	0.00390 U	0.000757 U	0.00530 U
MW-164 (-59.9 to-69.9)	MW-164-80	1/24/19	PES	PACE	80	-40.3	S	0.00311 U	0.00176 U	**0.00236 J**	0.00142 U	0.00163 U	0.00174 U	0.00159 U	0.000455 U	0.000569 U	0.00401 U	**0.0313**	0.00544 U
	MW-164-87	1/24/19	PES	PACE	87	-47.3	S	0.00306 U	0.00174 U	**0.00102 J**	0.00140 U	0.00160 U	0.00171 U	0.00157 U	0.000448 U	0.000560 U	0.00394 U	**0.0349**	0.00535 U
	MW-164-90	1/24/19	PES	PACE	90	-50.3	S	0.00320 U	0.00182 U	**0.428**	0.00146 U	**0.00250 J**	0.00179 U	0.00164 U	**0.0599**	0.000586 U	0.00412 U	**0.0101**	0.00560 U
	MW-164-95	1/25/19	PES	PACE	95	-55.3	S	0.00326 U	0.00185 U	**0.788**	0.00149 U	**0.00379 J**	0.00183 U	0.00167 U	**0.172**	0.000598 U	0.00421 U	**0.00420**	0.00572 U
	MW-164-100	1/25/19	PES	PACE	100	-60.3	S	0.00341 U	0.00194 U	**0.00777**	0.00156 U	0.00179 U	0.00191 U	0.00175 U	**0.0124**	0.000625 U	0.00440 U	**0.00145 J**	0.00598 U
	MW-164-105	1/25/19	PES	PACE	105	-65.3	S	0.00303 U	0.00172 U	**0.00369**	**0.00150 J**	0.00159 U	0.00170 U	0.00155 U	0.000444 U	0.000555 U	0.00390 U	**0.00428**	0.00530 U
	MW-164-110	1/25/19	PES	PACE	110	-70.3	S	0.00301 U	0.00171 U	0.000772 U	0.00138 U	0.00158 U	0.00169 U	0.00154 U	0.000441 U	0.000551 U	0.00388 U	0.000753 U	0.00527 U
	B-929-120	1/25/19	PES	PACE	110 (dup)	-70.3	S	0.00307 U	0.00174 U	**0.00468**	**0.00186 J**	0.00161 U	0.00172 U	0.00157 U	0.000449 U	0.000562 U	0.00395 U	**0.00368**	0.00537 U
MW-168 (-43.0 to -53.0)	MW-168-15	10/21/19	PES	Fremont	15	-3.8	S	–	–	**2.78**	–	–	–	–	**3.42**	–	–	0.247 U	–
MW-171 (-27.6 to -37.6)	MW-171-24	09/24/19	PES	Fremont	24	-12.8	S	–	–	0.199 U	–	–	–	–	0.160 U	–	–	0.199 U	–
MW-172 (-42.5 to -52.5)	MW-172-7	09/26/19	PES	Fremont	7	4.2	S	–	–	0.235 U	–	–	–	–	0.188 U	–	–	0.235 U	–
MW-175 (-27.8 to -37.8)	MW-175-12	10/26/19	PES	Fremont	12	-1.3	S	–	–	0.237 U	–	–	–	–	0.190 U	–	–	0.237 U	–
	B-1002-12	10/26/19	PES	Fremont	12 (dup)	-1.3	S	–	–	0.233 U	–	–	–	–	0.187 U	–	–	0.233 U	–

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	**–**	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	**–**	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
MW-180 (-42.7 to -52.7)	MW-180-40	09/25/19	PES	Fremont	40	-28.2	S	–	–	**0.204**	–	–	–	–	0.0997 U	–	–	0.125 U	–
	MW-180-24	09/25/19	PES	Fremont	24	-12.2	S	–	–	**8.960**	–	–	–	–	**28.7**	–	–	**0.515**	–
	MW-180-27	09/25/19	PES	Fremont	27	-15.2	S	–	–	**12.8**	–	–	–	–	0.0984 U	–	–	0.123 U	–
MW-181 (1.5 to -8.5)	MW-181-14	09/27/19	PES	Fremont	14	-2.5	S	–	–	0.270 U	–	–	–	–	0.216 U	–	–	0.270 U	–
MW-183 (-27.4 to -37.4)	MW-183-18	09/26/19	PES	Fremont	18	-6.5	S	–	–	0.250 U	–	–	–	–	0.200 U	–	–	0.250 U	–
MW-184 (-42.5 to -52.5)	MW-184-20	09/26/19	PES	Fremont	20	-8.4	S	–	–	0.273 U	–	–	–	–	0.218 U	–	–	0.273 U	–
MW-188 (-42.2 to -52.2)	MW-188-64	10/01/19	PES	Fremont	64	-52.4	S	–	–	0.251 U	–	–	–	–	0.200 U	–	–	0.251 U	–
P01	P01-05	2/12/14	SES	F&BI	5	35.5	S	–	–	–	0.020 U	–	–	–	–	–	–	–	0.060 U
	P01-10	2/12/14	SES	F&BI	10	30.5	S	–	–	–	0.020 U	–	–	–	–	–	–	–	0.060 U
P02	P02-05	2/12/14	SES	F&BI	5	34.5	S	–	–	**0.16**	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
	P02-07.5	2/12/14	SES	F&BI	7.5	32.0	S	–	–	**1.2**	**–**	0.050 U	–	–	**0.072**	–	–	0.050 U	**–**
P03	P03-05	2/12/14	SES	F&BI	5	34.5	S	–	–	**0.36**	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
P03	P03-07.5	2/12/14	SES	F&BI	7.5	32.0	S	–	–	**0.061**	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
P04	P04-05	2/12/14	SES	F&BI	7.5	32.5	S	–	–	**0.55**	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
	P04-10	2/12/14	SES	F&BI	10	30.0	S	–	–	0.025 U	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
P05	P05-05	2/12/14	SES	F&BI	5	35.0	S	–	–	**0.049**	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
	P05-07.5	2/12/14	SES	F&BI	7.5	32.5	S	–	–	**0.031**	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
P06	P06-07.5	2/12/14	SES	F&BI	7.5	32.5	S	–	–	**0.31**	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
	P06-10	2/12/14	SES	F&BI	10	30.0	S	–	–	**0.083**	**–**	0.050 U	–	–	0.030 U	–	–	0.050 U	**–**
R-MW1	Unknown	10/22/92	Roux	Unknown	5	32.8	S	–	–	**5.8**	**–**	0.005 U	–	–	**0.35**	–	–	0.010 U	**–**
W-MW-03 (P-07)	SB-W-07-0135	1/26/12	WW	ARI	13.5-14	25.2	S	–	–	**0.0038**	**0.0024**	0.0009 U	–	–	**0.0005 J**	–	–	0.0009 U	**0.0008 J**
	SB-W-07-0275	1/26/12	WW	ARI	27.5-28	11.2	S	–	–	**0.12**	**0.0013**	**0.0013**	–	–	**0.0053**	–	–	0.0009 U	0.0018 U
	SB-W-07-0335	1/26/12	WW	ARI	33.5-34	5.2	S	–	–	**18 B**	**0.0012**	0.0008 U	–	–	**0.050**	–	–	0.0008 U	**0.0004 J**
	SB-W-07-0430	1/26/12	WW	ARI	43-43.5	-4.3	S	–	–	**46 B**	**0.0009**	**0.0009**	–	–	**0.70**	–	–	0.0008 U	0.0016 U
	SB-W-07-0530	1/26/12	WW	ARI	53-53.5	-14.3	S	–	–	**18 B**	**0.0012**	**0.0009**	–	–	**1.1**	–	–	0.0008 U	0.0016 U
	SB-W-07-0630	1/26/12	WW	ARI	63-63.5	-24.3	S	–	–	**0.0012 B**	**0.0007 J**	0.0010 U	–	–	0.0010 U	–	–	0.0010 U	0.0020 U
	SB-W-07-0780	1/26/12	WW	ARI	78-78.5	-39.3	S	–	–	**0.0023 B**	**0.0004 J**	0.0008 U	–	–	0.0008 U	–	–	0.0008 U	0.0016 U

Table G-1

On Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
W-MW-04 (P-08)	SB-W-08-0090	1/28/12	WW	ARI	9-9.5	26.0	S	–	–	**9.5 T**	0.27 U	**0.22 J**	–	–	**2.3**	–	–	**0.71**	0.54 U
	SB-W-08-0155	1/28/12	WW	ARI	15.5-16	19.5	S	–	–	**0.38 T**	**0.0006 J**	**0.0039**	–	–	**0.11**	–	–	**0.12**	0.0018 U
	SB-W-08-0265	1/28/12	WW	ARI	26.5-27	8.5	S	–	–	**0.37 T**	**0.0006 J**	0.0009 U	–	–	**0.0052**	–	–	0.0009 U	0.0019 U
	SB-W-08-0380	1/28/12	WW	ARI	38-38.5	-3.0	S	–	–	**0.48 T**	0.0008 U	0.0008 U	–	–	**0.0019**	–	–	0.0008 U	0.0016 U
	SB-W-08-0480	1/28/12	WW	ARI	48-48.5	-13.0	S	–	–	**0.025 T**	**0.0013**	0.0009 U	–	–	**0.0007 J**	–	–	0.0009 U	0.0018 U
	SB-W-08-9480	1/28/12	WW	ARI	48-48.5 (dup)	-13.0	S	–	–	**0.016 T**	**0.0008 J**	0.0009 U	–	–	0.0009 U	–	–	0.0009 U	0.0018 U
	SB-W-08-0590	1/28/12	WW	ARI	59-59.5	-24.0	S	–	–	**10 T**	0.13 U	0.13 U	–	–	**0.081 J**	–	–	0.13 U	0.26 U
	SB-W-08-0710	1/29/12	WW	ARI	71-71.5	-36.0	S	–	–	**9.4 T**	0.20 U	0.20 U	–	–	**0.33**	–	–	0.20 U	0.40 U
	SB-W-08-0760	1/29/12	WW	ARI	76-76.5	-41.0	S	–	–	**0.017 T**	**0.0009**	0.0009 U	–	–	0.0009 U	–	–	0.0009 U	0.0018 U
All Data							Number of Analytes Measured	805	805	1,034	856	992	805	805	1,033	805	805	1,034	856
							Number of Analytes Detected	2	7	869	143	282	2	3	711	0	0	418	33
							Frequency of Detection	0.2%	0.9%	84.0%	16.7%	28.4%	0.2%	0.4%	68.8%	0.0%	0.0%	40.4%	3.9%
							Maximum Detection	0.000676 J	0.0271 J	16400	0.58	0.7	0.00731 J	0.254	113	–	–	17	6.02
							Minimum Detection	0.000234 U	0.000206 U	0.00029 U	0.000325 U	0.000275 U	0.000267 U	0.000778 U	0.000293 U	0.000382 U	0.00239 U	0.000306 UJ	0.0004 J
							Number Of Vadose (V) Detections above SL	0	0	8	0	0	0	–	1	0	0	0	0
							Number of Saturated (S) Detections above SL	0	0	710	3	26	2	–	557	0	0	273	4
2017-2021							Number of Analytes Measured	805	805	861	819	819	805	805	860	805	805	861	819
							Number of Analytes Detected	2	7	737	130	274	2	3	635	0	0	416	29
							Frequency of Detection	0.2%	0.9%	85.6%	15.9%	33.5%	0.2%	0.4%	73.8%	0.0%	0.0%	48.3%	3.5%
							Maximum Detection	0.000676 J	0.0271 J	16400	0.58	0.7	0.00731 J	0.254	113	–	–	17	6.02
							Minimum Detection	0.000234 U	0.000206 U	0.00029 U	0.000325 U	0.000275 U	0.000267 U	0.000778 U	0.000293 U	0.000382 U	0.00239 U	0.000306 UJ	0.000698 UJ
							Number Of Vadose (V) Detections above SL	0	0	8	0	0	0	–	1	0	0	0	0
							Number of Saturated (S) Detections above SL	0	0	581	2	24	2	–	488	0	0	271	2

Abbreviations:
AAL = Alden Analytical Laboratories, Inc., of Seattle, Washington
ARI = Analytical Resource, Incorporated, Seattle, Washington
B&V = Black Veatch
bgs = below ground surface
Comp = Composite Sample
dup = duplicate
EPJ = E.PJohnson Construction Inc., and Environmental
ESC = ESC Lab Services of Mt. Juliet, Tennessee
F&BI = Friedman & Bruya, Inc.
GeoEng = GeoEngineers, Inc.
HC = Hart Crowser, Inc.
NCA = North Creek Analytical, of Bothell, Washington
OnSite = OnSite Environmental Inc., of Redmond, Washington
Pace = Pace Analytical of Mt. Juliet, Tennessee (formerly ESC)
PES = PES Environmental, Inc.
Retec = Remediation Technologies, Inc.
Roux = Roux Associates
SES = SoundEarth Strategies, Inc.
TR = TR Corporation
Urban = Urban Redevelopment LLC
WW = WW Environmental LLC

Notes:
All on-Property soil was excavated during Property redevelopment above elevations 0.7 to 10.7 feet, and CVOCs in soil between elevations +10 to 55 feet was treated.
Petroleum Hydrocarbons (PHCs) analyzed by Ecology Methods NWTPH-HCID, NWTPH-Gx, or NWTPH-Dx; or EPA Method 418.1, Method 8020, or Method 8015M.
VOCs analyzed by EPA Methods 8010, 8020, 8021B, 624/8240, or 8260B/C/D.
Well screen elevations provided below Sample Location. in parentheses when appliable.
PCUL = Preliminary Cleanup Level from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021. PCULs based on the practical quantitation limits (PQLs) italicized.
Detected results shown in **bold**.
Detections above the screening level in the vadose zone are shown in **bold and highlighted blue.**
Detections above the screening level in the saturated zone are shown in **bold and highlighted gray.**
– = Not available or results not analyzed.
A = Result reported as total petroleum hydrocarbons.
B = Analyte detected in an associated method blank.
J = The reported concentration is an estimate based on detectable results between the method detection limit and reporting limit, laboratory QA/QC, or data validation review.
J+ = The result is an estimated quantity, but the result may be biased high.
J- = The result is an estimated quantity, but the result may be biased low.
ND = Not detected above laboratory reporting limit. Reporting limit not available.
q = Sample may contain gasoline or petroleum components. Chromatographic pattern indicates the presence of gasoline constituents.
R = The data is unusable. The sample result is rejected due to serious deficiencies in meeting QC criteria. The analyte may or may not be present in the sample
T = Analyte also detected in trip blank.
U = Not detected at a concentration exceeding laboratory reporting limit
ve = Estimated value. The reported range exceeds the calibration range of the analysis.
w = Petroleum product eluting in the C8-C9 range
x = The sample chromatographic pattern does not resemble the fuel standard used for quantitation.
z = Gasoline/petroleum detection result is likely elevated due to high detections of CVOCs.

Table G-2

Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	**–**	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	**–**	**0.030**	**1.5E-07**
PRB-A3/PRB-C3	A3C3-3	01/16/19	PES	Pace	3	39.7	V	0.904 U	–	–	–	0.000533 U	0.000293 U	0.000416 U	0.000942 U	0.000720 U	0.000613 U	0.000533 U	0.000746 U	0.000666 U	0.00544 U
	A3C3-6	01/16/19	PES	Pace	6	36.7	V	0.973 U	–	–	–	0.000574 U	0.000315 U	0.000447 U	0.00101 U	0.000774 U	0.000660 U	0.000574 U	0.000803 U	0.000717 U	0.00585 U
	A3C3-8	01/16/19	PES	Pace	8	34.7	V	**12.9**	–	–	–	0.00100 U	0.000550 U	0.000780 U	0.00176 U	0.00135 U	0.00115 U	0.00100 U	0.00140 U	0.00125 U	0.0102 U
	A3C3-10	02/13/19	PES	Pace	10	32.7	S	**3.52**	–	–	–	0.000679 U	0.000373 U	0.000530 U	0.00120 U	0.000917 U	0.000781 U	0.000679 U	0.000951 U	0.000849 U	0.00693 U
	A3C3-15	02/13/19	PES	Pace	15	27.7	S	**4.42**	–	–	–	0.000578 U	0.000318 U	0.000451 U	0.00102 U	0.000780 U	0.000665 U	0.000578 U	0.000809 U	0.000722 U	0.00589 U
	A3C3-20	02/13/19	PES	Pace	20	22.7	S	**1.38 J**	–	–	–	0.000572 U	0.000315 U	0.000446 U	0.00101 U	0.000772 U	0.000658 U	0.000572 U	0.000801 U	0.000715 U	0.00584 U
	A3C3-25	02/13/19	PES	Pace	25	17.7	S	1.01 U	–	–	–	0.000596 U	0.000328 U	0.000465 U	0.00105 U	0.000805 U	0.000686 U	0.000596 U	0.000835 U	0.000746 U	0.00608 U
	A3C3-32	02/13/19	PES	Pace	32	10.7	S	**1.37 J**	–	–	–	0.000576 U	0.000317 U	0.000449 U	0.00102 U	0.000778 U	0.000663 U	0.000576 U	0.000807 U	0.000720 U	0.00588 U
	A3C3-35	02/13/19	PES	Pace	35	7.7	S	**1.21 J**	–	–	–	0.000565 U	0.000311 U	0.000441 U	0.000998 U	0.000763 U	0.000650 U	0.000565 U	0.000791 U	0.000706 U	0.00576 U
	A3C3-40	02/13/19	PES	Pace	40	2.7	S	**2.31 J**	–	–	–	0.000615 U	0.000338 U	0.000480 U	0.00109 U	0.000831 U	0.000708 U	0.000615 U	0.000861 U	0.000769 U	0.00628 U
	A3C3-45	02/13/19	PES	Pace	45	-2.3	S	**1.27 J**	–	–	–	0.000567 U	0.000312 U	0.000443 U	0.00100 U	0.000766 U	0.000653 U	0.000567 U	0.000794 U	0.000709 U	0.00579 U
	A3C3-50	02/13/19	PES	Pace	50	-7.3	S	**1.40 J**	–	–	–	0.000590 U	0.000324 U	0.000460 U	0.00104 U	0.000796 U	0.000678 U	0.000590 U	0.000826 U	0.000737 U	0.00602 U
PRB-A9/PRB-C9	A9C9-3	01/21/19	PES	Pace	3	40.1	V	–	–	–	–	0.000844 U	0.000464 U	0.000658 U	0.00148 U	0.00114 U	0.000971 U	0.000844 U	0.00118 U	0.00105 U	0.00861 U
	A9C9-6	01/21/19	PES	Pace	6	37.1	V	–	–	–	–	0.000613 U	0.000337 U	0.000478 U	0.00108 U	0.000827 U	0.000704 U	0.000613 U	0.000858 U	0.000766 U	0.00625 U
	A9C9-10	01/21/19	PES	Pace	10	33.1	S	–	–	–	–	0.000578 U	0.000318 U	0.000451 U	0.00102 U	0.000780 U	0.000664 U	0.000578 U	0.000809 U	0.000722 U	0.00589 U
	A9C9-15	02/07/19	PES	Pace	15	28.1	S	–	–	–	–	0.000583 U	0.000321 U	0.000455 U	0.00103 U	0.000788 U	0.000671 U	0.000583 U	0.000817 U	0.000729 U	0.00595 U
	A9C9-20	02/07/19	PES	Pace	20	23.1	S	–	–	–	–	0.000575 U	0.000316 U	0.000448 U	0.00101 U	0.000776 U	0.000661 U	0.000575 U	0.000805 U	0.000718 U	0.00586 U
	A9C9-25	02/07/19	PES	Pace	25	18.1	S	–	–	–	–	0.000538 U	0.000296 U	0.000420 U	0.000950 U	0.000726 U	0.000619 U	0.000538 U	0.000753 U	0.000673 U	0.00549 U
	A9C9-32	02/07/19	PES	Pace	32	11.1	S	–	–	–	–	0.000534 U	0.000294 U	0.000417 U	0.000943 U	0.000721 U	0.000614 U	**0.00349**	0.000748 U	0.000668 U	0.00545 U
	A9C9-35	02/07/19	PES	Pace	35	8.1	S	–	–	–	–	0.000529 U	0.000291 U	0.000413 U	0.000934 U	0.000714 U	0.000609 U	0.000529 U	0.000741 U	0.000661 U	0.00540 U
	A9C9-40	02/07/19	PES	Pace	40	3.1	S	–	–	–	–	0.000536 U	0.000295 U	0.000418 U	0.000947 U	0.000724 U	0.000617 U	**0.00636**	0.000751 U	0.000670 U	0.00547 U
	A9C9-45	02/07/19	PES	Pace	45	-1.9	S	–	–	–	–	0.000523 U	0.000288 U	0.000408 U	0.000924 U	0.000706 U	0.000602 U	0.000523 U	0.000732 U	0.000654 U	0.00534 U
	A9C9-50	02/07/19	PES	Pace	50	-6.9	S	–	–	–	–	0.000538 U	0.000296 U	0.000419 U	0.000949 U	0.000726 U	0.000618 U	0.000538 U	0.000753 U	0.000672 U	0.00548 U
	B-931-50	02/07/19	PES	Pace	50 (dup)	-6.9	S	–	–	–	–	0.000538 U	0.000296 U	0.000420 U	0.000950 U	0.000727 U	0.000619 U	0.000538 U	0.000753 U	0.000673 U	0.00549 U
PRB-B1/PRB-D1	B1D1-11	01/17/19	PES	Pace	11	30.8	S	**2.42 J**	–	–	–	0.000584 U	0.000321 U	0.000456 U	0.00103 U	0.000789 U	0.000672 U	0.000584 U	0.000818 U	0.000730 U	0.00596 U
	B1D1-15	01/17/19	PES	Pace	15	26.8	S	**1.67 J**	–	–	–	0.000764 U	0.000420 U	0.000596 U	0.00135 U	0.00103 U	0.000879 U	0.000764 U	0.00107 U	0.000955 U	0.00780 U
	B1D1-20	01/17/19	PES	Pace	20	21.8	S	**1.67 J**	–	–	–	0.000614 U	0.000338 U	0.000479 U	0.00108 U	0.000829 U	0.000706 U	0.000614 U	0.000859 U	0.000767 U	0.00626 U
	B1D1-25	01/17/19	PES	Pace	25	16.8	S	**1.89 J**	–	–	–	0.000695 U	0.000382 U	0.000542 U	0.00123 U	0.000939 U	0.000800 U	0.000695 U	0.000974 U	0.000869 U	0.00709 U
	B1D1-31	01/17/19	PES	Pace	31	10.8	S	**1.07 J**	–	–	–	0.000544 U	0.000299 U	0.000424 U	0.000961 U	0.000735 U	0.000626 U	0.000544 U	0.000762 U	0.000680 U	0.00555 U
	B1D1-35	01/17/19	PES	Pace	35	6.8	S	**1.05 J**	–	–	–	0.000612 U	0.000337 U	0.000478 U	0.00108 U	0.000827 U	0.000704 U	0.000612 U	0.000857 U	0.000766 U	0.00625 U
	B1D1-40	01/17/19	PES	Pace	40	1.8	S	**0.969 J**	–	–	–	0.000559 U	0.000307 U	0.000436 U	0.000987 U	0.000755 U	0.000643 U	0.000559 U	0.000783 U	0.000699 U	0.00570 U
	B1D1-45	01/17/19	PES	Pace	45	-3.3	S	**1.18 J**	–	–	–	0.000572 U	0.000315 U	0.000446 U	0.00101 U	0.000773 U	0.000658 U	0.000572 U	0.000801 U	0.000715 U	0.00584 U
	B1D1-50	01/17/19	PES	Pace	50	-8.3	S	**1.69 J**	–	–	–	0.000578 U	0.000318 U	0.000450 U	0.00102 U	0.000780 U	0.000664 U	0.000578 U	0.000809 U	0.000722 U	0.00589 U
PRB-B2/PRB-D2	B2D2-3	01/16/19	PES	Pace	3	38.8	V	0.924 U	–	–	–	0.000545 U	0.000300 U	0.000425 U	0.000963 U	0.000736 U	0.000627 U	0.000545 U	0.000763 U	0.000681 U	0.00556 U
	B2D2-6	01/16/19	PES	Pace	6	35.8	V	**4.28**	–	–	–	0.000696 U	0.000383 U	0.000543 U	0.00123 U	0.000940 U	0.000801 U	0.000696 U	0.000975 U	0.000870 U	0.00710 U
	B2D2-10	01/21/19	PES	Pace	10	31.8	S	**24.9**	–	–	–	0.00109 U	0.000601 U	0.000845 U	0.00193 U	0.00148 U	0.00126 U	0.00108 U	0.00153 U	0.00137 U	0.0111 U

Table G-2

Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	**–**	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	**–**	**0.030**	**1.5E-07**
PRB-B4/PRB-D4	B4D4-3	01/17/19	PES	Pace	3	39.7	V	–	–	–	–	0.000566 U	0.000311 U	0.000441 U	0.000999 U	0.000764 U	0.000651 U	0.000566 U	0.000792 U	0.000707 U	0.00577 U
	B4D4-6	01/17/19	PES	Pace	6	36.7	V	–	–	–	–	0.000787 U	0.000432 U	0.000607 U	0.00139 U	0.00106 U	0.000904 U	0.000779 U	0.00110 U	0.000973 U	0.00803 U
	B4D4-10	01/17/19	PES	Pace	10	32.7	S	–	–	–	–	0.000635 U	0.000349 U	0.000495 U	0.00112 U	0.000857 U	0.000730 U	0.000635 U	0.000889 U	0.000794 U	0.00648 U
PRB-B5/PRB-D5	B5D5-10	02/14/19	PES	Pace	10	32.9	S	–	–	–	–	0.000586 U	0.000322 U	0.000457 U	–	0.000791 U	0.000674 U	0.000586 U	0.000820 U	0.000732 U	0.00598 U
	B5D5-15	02/14/19	PES	Pace	15	27.9	S	–	–	–	–	0.000582 U	0.000320 U	0.000454 U	–	0.000786 U	0.000669 U	0.000582 U	0.000815 U	0.000728 U	0.00594 U
	B5D5-20	02/14/19	PES	Pace	20	22.9	S	–	–	–	–	0.000584 U	0.000321 U	0.000456 U	0.00103 U	0.000788 U	0.000672 U	0.000584 U	0.000818 U	0.000730 U	0.00596 U
	B5D5-25	02/14/19	PES	Pace	25	17.9	S	–	–	–	–	0.000589 U	0.000324 U	0.000460 U	0.00104 U	0.000795 U	0.000677 U	0.000589 U	0.000825 U	0.000736 U	0.00601 U
	B5D5-32	02/14/19	PES	Pace	32	10.9	S	–	–	–	–	0.000568 U	0.000312 U	0.000443 U	0.00100 U	0.000767 U	0.000653 U	0.000568 U	0.000795 U	0.000710 U	0.00579 U
	B5D5-35	02/14/19	PES	Pace	35	7.9	S	–	–	–	–	0.000551 U	0.000303 U	0.000430 U	0.000973 U	0.000744 U	0.000633 U	**0.00395**	0.000771 U	0.000689 U	0.00562 U
	B5D5-40	02/14/19	PES	Pace	40	2.9	S	–	–	–	–	0.000551 U	0.000303 U	0.000430 U	0.000974 U	0.000744 U	0.000634 U	**0.00336**	0.000772 U	0.000689 U	0.00562 U
	B5D5-45	02/14/19	PES	Pace	45	-2.1	S	–	–	–	–	0.000538 U	0.000296 U	0.000419 U	0.000950 U	0.000726 U	0.000618 U	0.000538 U	0.000753 U	0.000672 U	0.00548 U
	B5D5-50	02/14/19	PES	Pace	50	-7.1	S	–	–	–	–	0.000521 U	0.000287 U	0.000407 U	0.000921 U	0.000704 U	0.000599 U	0.000521 U	0.000730 U	0.000652 U	0.00532 U
	B-932-50	02/14/19	PES	Pace	50 (dup)	-7.1	S	–	–	–	–	0.000531 U	0.000292 U	0.000414 U	0.000937 U	0.000716 U	0.000610 U	0.000531 U	0.000743 U	0.000663 U	0.00541 U
PRB-B6/PRB-D6	B6D6-17	02/20/19	PES	Pace	17	25.9	S	–	–	–	–	0.000575 U	0.000316 U	0.000448 U	0.00102 U	0.000776 U	0.000661 U	0.000575 U	0.000805 U	0.000719 U	0.00586 U
	B6D6-20	02/20/19	PES	Pace	20	22.9	S	–	–	–	–	0.000581 U	0.000319 U	0.000453 U	0.00103 U	0.000784 U	0.000668 U	0.000581 U	0.000813 U	0.000726 U	0.00592 U
	B6D6-25	02/20/19	PES	Pace	25	17.9	S	–	–	–	–	0.000595 U	0.000327 U	0.000464 U	0.00105 U	0.000803 U	0.000684 U	0.000595 U	0.000833 U	0.000744 U	0.00607 U
	B6D6-32	02/20/19	PES	Pace	32	10.9	S	–	–	–	–	0.000602 U	0.000331 U	0.000470 U	0.00106 U	0.000813 U	0.000693 U	**0.00190 J**	0.000843 U	0.000753 U	0.00614 U
	B6D6-35	02/20/19	PES	Pace	35	7.9	S	–	–	–	–	0.000543 U	0.000299 U	0.000423 U	0.000959 U	0.000733 U	0.000624 U	**0.00535**	0.000760 U	0.000678 U	0.00554 U
	B6D6-40	02/20/19	PES	Pace	40	2.9	S	–	–	–	–	0.000590 U	0.000325 U	0.000461 U	0.00104 U	0.000797 U	0.000679 U	0.000590 U	0.000827 U	0.000738 U	0.00602 U
	B6D6-45	02/20/19	PES	Pace	45	-2.1	S	–	–	–	–	0.00110 U	0.000607 U	0.000861 U	0.00195 U	0.00149 U	0.00127 U	**0.00763**	0.00155 U	0.00138 U	0.0113 U
	B6D6-50	02/20/19	PES	Pace	50	-7.1	S	–	–	–	–	0.000535 U	0.000294 U	0.000418 U	0.000945 U	0.000723 U	0.000616 U	0.000535 U	0.000749 U	0.000669 U	0.00546 U
	B-933-50	02/20/19	PES	Pace	50 (dup)	-7.1	S	–	–	–	–	0.000550 U	0.000303 U	0.000429 U	0.000971 U	0.000743 U	0.000633 U	**0.00191 J**	0.000770 U	0.000688 U	0.00561 U
PRB-B10/PRB-D10	B10D10-15	02/21/19	PES	Pace	15	30.1	S	–	–	–	–	0.000630 U	0.000347 U	0.000492 U	0.00111 U	0.000851 U	0.000725 U	0.000630 U	0.000883 U	0.000788 U	0.00643 U
	B10D10-20	02/21/19	PES	Pace	20	25.1	S	–	–	–	–	0.000604 U	0.000332 U	0.000471 U	0.00107 U	0.000815 U	0.000694 U	0.000604 U	0.000845 U	0.000755 U	0.00616 U
	B10D10-25	02/21/19	PES	Pace	25	20.1	S	–	–	–	–	0.000565 U	0.000311 U	0.000441 U	0.000998 U	0.000763 U	0.000650 U	**0.00219 J**	0.000791 U	0.000706 U	0.00576 U
	B10D10-30	02/21/19	PES	Pace	30	15.1	S	–	–	–	–	0.000561 U	0.000309 U	0.000438 U	0.000991 U	0.000758 U	0.000646 U	**0.00332**	0.000786 U	0.000702 U	0.00573 U
	B10D10-35	02/21/19	PES	Pace	35	10.1	S	–	–	–	–	0.000549 U	0.000302 U	0.000428 U	0.000969 U	0.000741 U	0.000631 U	**0.00269 J**	0.000768 U	0.000686 U	0.00560 U
	B10D10-40	02/21/19	PES	Pace	40	5.1	S	–	–	–	–	0.000571 U	0.000314 U	0.000445 U	0.00101 U	0.000771 U	0.000657 U	**0.00222 J**	0.000799 U	0.000714 U	0.00582 U
	B10D10-45	02/21/19	PES	Pace	45	0.1	S	–	–	–	–	0.00876 U	0.00482 U	0.00683 U	0.0155 U	0.0118 U	0.0101 U	0.00876 U	0.0122 U	0.0109 U	0.0893 U
	B10D10-50	02/21/19	PES	Pace	50	-4.9	S	–	–	–	–	0.000554 U	0.000305 U	0.000432 U	0.000978 U	0.000748 U	0.000637 U	**0.00206 J**	0.000775 U	0.000692 U	0.00565 U

Table G-2

Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	**–**	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	**–**	**0.030**	**1.5E-07**
PRB-B11/PRB-D11	B11D11-10	01/15/19	PES	Pace	10	35.1	V	–	–	–	–	0.000674 U	0.000370 U	0.000520 U	0.00119 U	0.000910 U	0.000775 U	0.000668 U	0.000944 U	0.000843 U	0.00688 U
	B11D11-15	01/15/19	PES	Pace	15	30.1	S	–	–	–	–	0.000544 U	0.000299 U	0.000425 U	0.000961 U	0.000735 U	0.000626 U	0.000544 U	0.000762 U	0.000680 U	0.00555 U
	B11D11-20	01/15/19	PES	Pace	20	25.1	S	–	–	–	–	0.000574 U	0.000316 U	0.000448 U	0.00101 U	0.000775 U	0.000660 U	0.000574 U	0.000804 U	0.000718 U	0.00586 U
	B11D11-27	01/15/19	PES	Pace	27	18.1	S	–	–	–	–	0.000549 U	0.000302 U	0.000428 U	0.000969 U	0.000741 U	0.000631 U	0.000549 U	0.000768 U	0.000686 U	0.00560 U
	B11D11-30	01/15/19	PES	Pace	30	15.1	S	–	–	–	–	0.000519 U	0.000286 U	0.000405 U	0.000917 U	0.000701 U	0.000597 U	0.000519 U	0.000727 U	0.000649 U	0.00529 U
	B11D11-35	01/15/19	PES	Pace	35	10.1	S	–	–	–	–	0.000559 U	0.000308 U	0.000436 U	0.000988 U	0.000755 U	0.000643 U	**0.00171 J**	0.000783 U	0.000699 U	0.00570 U
	B11D11-40	01/15/19	PES	Pace	40	5.1	S	–	–	–	–	0.000546 U	0.000300 U	0.000426 U	0.000964 U	0.000737 U	0.000628 U	0.000546 U	0.000764 U	0.000682 U	0.00557 U
	B11D11-46	01/15/19	PES	Pace	46	-0.9	S	–	–	–	–	0.000564 U	0.000310 U	0.000440 U	0.000995 U	0.000761 U	0.000648 U	0.000564 U	0.000789 U	0.000704 U	0.00575 U
	B-928-46	01/15/19	PES	Pace	46 (dup)	-0.9	S	–	–	–	–	0.000562 U	0.000309 U	0.000439 U	0.000993 U	0.000759 U	0.000647 U	0.000562 U	0.000787 U	0.000703 U	0.00574 U
	B11D11-50	01/15/19	PES	Pace	50	-4.9	S	–	–	–	–	0.000667 U	0.000367 U	0.000520 U	0.00118 U	0.000900 U	0.000767 U	0.000667 U	0.000933 U	0.000833 U	0.00680 U
PRB-B13/PRB-D13	B13D13-10	03/21/19	PES	Pace	10	37.5	V	–	–	–	–	0.000570 U	0.000314 U	0.000445 U	0.00101 U	0.000770 U	0.000656 U	0.000570 U	0.000798 U	0.000713 U	0.00582 U
	B13D13-20	03/21/19	PES	Pace	20	27.5	S	–	–	–	–	0.000592 U	0.000326 U	0.000462 U	0.00105 U	0.000800 U	0.000681 U	0.000592 U	0.000829 U	0.000740 U	0.00604 U
	B13D13-30	03/21/19	PES	Pace	30	17.5	S	–	–	–	–	0.000574 U	0.000316 U	0.000448 U	0.00101 U	0.000775 U	0.000661 U	0.000574 U	0.000804 U	0.000718 U	0.00586 U
	B13D13-40	03/21/19	PES	Pace	40	7.5	S	–	–	–	–	0.000534 U	0.000293 U	0.000416 U	0.000942 U	0.000720 U	0.000614 U	0.000534 U	0.000747 U	0.000667 U	0.00544 U
	B13D13-50	03/21/19	PES	Pace	50	-2.5	S	–	–	–	–	0.000549 U	0.000302 U	0.000428 U	0.000970 U	0.000741 U	0.000632 U	0.000549 U	0.000769 U	0.000687 U	0.00560 U
PRB-B16/PRB-D16	B16D16-15	03/13/19	PES	Pace	15	34.5	S	–	–	–	–	0.00235 U	0.00129 U	0.00183 U	0.00415 U	0.00317 U	0.00270 U	0.00235 U	0.00329 U	0.00294 U	0.0240 U
	B16D16-20	03/13/19	PES	Pace	20	29.5	S	–	–	–	–	0.000547 U	0.000301 U	0.000427 U	0.000966 U	0.000738 U	0.000629 U	0.000547 U	0.000766 U	0.000684 U	0.00558 U
	B16D16-25	03/13/19	PES	Pace	25	24.5	S	–	–	–	–	0.000536 U	0.000295 U	0.000418 U	0.000946 U	0.000723 U	0.000616 U	0.000536 U	0.000750 U	0.000669 U	0.00546 U
	B16D16-30	03/13/19	PES	Pace	30	19.5	S	–	–	–	–	0.000550 U	0.000302 U	0.000429 U	0.000970 U	0.000742 U	0.000632 U	0.000550 U	0.000769 U	0.000687 U	0.00560 U
	B16D16-35	03/13/19	PES	Pace	35	14.5	S	–	–	–	–	0.000550 U	0.000302 U	0.000429 U	0.000971 U	0.000742 U	0.000632 U	**0.00288**	0.000770 U	0.000687 U	0.00561 U
	B16D16-40	03/13/19	PES	Pace	40	9.5	S	–	–	–	–	0.000583 U	0.000321 U	0.000455 U	0.00103 U	0.000787 U	0.000670 U	**0.00492**	0.000816 U	0.000729 U	0.00595 U
	B16D16-45	03/13/19	PES	Pace	45	4.5	S	–	–	–	–	0.000534 U	0.000294 U	0.000417 U	0.000944 U	0.000721 U	0.000615 U	**0.00152 J**	0.000748 U	0.000668 U	0.00545 U
	B16D16-50	03/13/19	PES	Pace	50	-0.5	S	–	–	–	–	0.000544 U	0.000299 U	0.000424 U	0.000961 U	0.000734 U	0.000626 U	**0.000721 J**	0.000762 U	0.000680 U	0.00555 U
	B16D16-55	03/13/19	PES	Pace	55	-5.5	S	–	–	–	–	0.00246 U	0.00135 U	0.00191 U	0.00433 U	0.00331 U	0.00282 U	0.00246 U	0.00344 U	0.00307 U	0.0251 U
	B16D16-60	03/13/19	PES	Pace	60	-10.5	S	–	–	–	–	0.000532 U	0.000293 U	0.000415 U	0.000940 U	0.000718 U	0.000612 U	0.000532 U	0.000745 U	0.000665 U	0.00543 U
	B16D16-65	03/13/19	PES	Pace	65	-15.5	S	–	–	–	–	0.000547 U	0.000301 U	0.000427 U	0.000966 U	0.000739 U	0.000629 U	0.000547 U	0.000766 U	0.000684 U	0.00558 U
	B16D16-70	03/13/19	PES	Pace	70	-20.5	S	–	–	–	–	0.000560 U	0.000308 U	0.000437 U	0.000990 U	0.000757 U	0.000645 U	0.000560 U	0.000785 U	0.000701 U	0.00572 U
	B16D16-75	03/13/19	PES	Pace	75	-25.5	S	–	–	–	–	0.000549 U	0.000302 U	0.000428 U	0.000969 U	0.000741 U	0.000631 U	0.000549 U	0.000769 U	0.000686 U	0.00560 U
	B16D16-80	03/13/19	PES	Pace	80	-30.5	S	–	–	–	–	0.000558 U	0.000307 U	0.000435 U	0.000985 U	0.000753 U	0.000642 U	0.000558 U	0.000781 U	0.000697 U	0.00569 U
	B16D16-85	03/13/19	PES	Pace	85	-35.5	S	–	–	–	–	0.000555 U	0.000305 U	0.000433 U	0.000979 U	0.000749 U	0.000638 U	0.000555 U	0.000776 U	0.000693 U	0.00566 U
	B16D16-90	03/13/19	PES	Pace	90	-40.5	S	–	–	–	–	0.000565 U	0.000311 U	0.000440 U	0.000997 U	0.000762 U	0.000649 U	0.000565 U	0.000791 U	0.000706 U	0.00576 U
	B16D16-95	03/13/19	PES	Pace	95	-45.5	S	–	–	–	–	0.000582 U	0.000320 U	0.000454 U	0.00103 U	0.000786 U	0.000670 U	0.000582 U	0.000815 U	0.000728 U	0.00594 U
	B16D16-100	03/13/19	PES	Pace	100	-50.5	S	–	–	–	–	0.000579 U	0.000319 U	0.000452 U	0.00102 U	0.000782 U	0.000666 U	0.000579 U	0.000811 U	0.000724 U	0.00591 U
	B16D16-105	03/13/19	PES	Pace	105	-55.5	S	–	–	–	–	0.000570 U	0.000313 U	0.000445 U	0.00101 U	0.000769 U	0.000655 U	0.000570 U	0.000798 U	0.000712 U	0.00581 U
	B-934-105	03/13/19	PES	Pace	105 (dup)	-55.5	S	–	–	–	–	0.000571 U	0.000314 U	0.000445 U	0.00101 U	0.000770 U	0.000656 U	0.000571 U	0.000799 U	0.000713 U	0.00582 U

Table G-2

Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	**–**	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	**–**	**0.030**	**1.5E-07**
PRB-B18/PRB-D18	B18D18-10	03/22/19	PES	Pace	10	41.0	V	–	–	–	–	0.000583 U	0.000321 U	0.000455 U	0.00103 U	0.000788 U	0.000671 U	0.000583 U	0.000817 U	0.000729 U	0.00595 U
	B18D18-20	03/22/19	PES	Pace	20	31.0	S	–	–	–	–	0.000556 U	0.000306 U	0.000434 U	0.000982 U	0.000751 U	0.000639 U	0.000556 U	0.000778 U	0.000695 U	0.00567 U
	B18D18-30	03/22/19	PES	Pace	30	21.0	S	–	–	–	–	0.000551 U	0.000303 U	0.000429 U	0.000972 U	0.000743 U	0.000633 U	0.000551 U	0.000771 U	0.000688 U	0.00562 U
	B18D18-40	03/22/19	PES	Pace	40	11.0	S	–	–	–	–	0.000552 U	0.000303 U	0.000430 U	0.000974 U	0.000745 U	0.000634 U	0.000552 U	0.000772 U	0.000690 U	0.00563 U
	B18D18-50	03/22/19	PES	Pace	50	1.0	S	–	–	–	–	0.000542 U	0.000298 U	0.000423 U	0.000957 U	0.000732 U	0.000623 U	0.000542 U	0.000759 U	0.000677 U	0.00553 U
PRB-B19/PRB-D19	B19D19-10	03/18/19	PES	Pace	10	42.5	V	–	–	–	–	0.000551 U	0.000303 U	0.000430 U	0.000973 U	0.000744 U	0.000634 U	0.000551 U	0.000772 U	0.000689 U	0.00562 U
	B19D19-15	03/18/19	PES	Pace	15	37.5	V	–	–	–	–	0.000617 U	0.000340 U	0.000481 U	0.00109 U	0.000833 U	0.000710 U	0.000617 U	0.000864 U	0.000770 U	0.00630 U
	B19D19-20	03/18/19	PES	Pace	20	32.5	S	–	–	–	–	0.000584 U	0.000321 U	0.000455 U	0.00103 U	0.000788 U	0.000671 U	0.000584 U	0.000817 U	0.000730 U	0.00595 U
	B19D19-25	03/18/19	PES	Pace	25	27.5	S	–	–	–	–	0.000620 U	0.000341 U	0.000483 U	0.00110 U	0.000837 U	0.000713 U	0.000620 U	0.000868 U	0.000775 U	0.00632 U
	B19D19-30	03/18/19	PES	Pace	30	22.5	S	–	–	–	–	0.000575 U	0.000316 U	0.000448 U	0.00101 U	0.000776 U	0.000661 U	0.000575 U	0.000805 U	0.000718 U	0.00586 U
	B19D19-35	03/18/19	PES	Pace	35	17.5	S	–	–	–	–	0.000567 U	0.000312 U	0.000442 U	0.00100 U	0.000765 U	0.000652 U	0.000567 U	0.000794 U	0.000709 U	0.00578 U
	B19D19-40	03/18/19	PES	Pace	40	12.5	S	–	–	–	–	0.000582 U	0.000320 U	0.000454 U	0.00103 U	0.000786 U	0.000670 U	0.000582 U	0.000815 U	0.000728 U	0.00594 U
	B19D19-45	03/18/19	PES	Pace	45	7.5	S	–	–	–	–	0.000579 U	0.000319 U	0.000452 U	0.00102 U	0.000782 U	0.000666 U	0.000579 U	0.000811 U	0.000724 U	0.00590 U
	B19D19-50	03/18/19	PES	Pace	50	2.5	S	–	–	–	–	0.000573 U	0.000315 U	0.000447 U	0.00101 U	0.000774 U	0.000659 U	0.000573 U	0.000803 U	0.000717 U	0.00585 U
	B19D19-55	03/18/19	PES	Pace	55	-2.5	S	–	–	–	–	0.000576 U	0.000317 U	0.000449 U	0.00102 U	0.000778 U	0.000663 U	0.000576 U	0.000807 U	0.000720 U	0.00588 U
	B19D19-60	03/18/19	PES	Pace	60	-7.5	S	–	–	–	–	0.000560 U	0.000308 U	0.000437 U	0.000989 U	0.000756 U	0.000644 U	0.000560 U	0.000784 U	0.000700 U	0.00571 U
	B19D19-65	03/18/19	PES	Pace	65	-12.5	S	–	–	–	–	0.000634 U	0.000349 U	0.000495 U	0.00112 U	0.000856 U	0.000729 U	0.000634 U	0.000888 U	0.000793 U	0.00648 U
	B19D19-70	03/18/19	PES	Pace	70	-17.5	S	–	–	–	–	0.000610 U	0.000336 U	0.000476 U	0.00108 U	0.000824 U	0.000702 U	0.000610 U	0.000854 U	0.000763 U	0.00622 U
	B19D19-75	03/18/19	PES	Pace	75	-22.5	S	–	–	–	–	0.000594 U	0.000327 U	0.000464 U	0.00105 U	0.000803 U	0.000684 U	0.000594 U	0.000832 U	0.000743 U	0.00606 U
	B19D19-80	03/18/19	PES	Pace	80	-27.5	S	–	–	–	–	0.000566 U	0.000311 U	0.000442 U	0.00100 U	0.000765 U	0.000651 U	0.000566 U	0.000793 U	0.000708 U	0.00578 U
	B19D19-85	03/18/19	PES	Pace	85	-32.5	S	–	–	–	–	0.000607 U	0.000334 U	0.000474 U	0.00107 U	0.000820 U	0.000698 U	0.000607 U	0.000850 U	0.000759 U	0.00619 U
	B19D19-90	03/18/19	PES	Pace	90	-37.5	S	–	–	–	–	0.000630 U	0.000346 U	0.000491 U	0.00111 U	0.000850 U	0.000724 U	0.000630 U	0.000881 U	0.000787 U	0.00642 U
	B19D19-95	03/18/19	PES	Pace	95	-42.5	S	–	–	–	–	0.000599 U	0.000330 U	0.000468 U	0.00106 U	0.000809 U	0.000689 U	0.000599 U	0.000839 U	0.000749 U	0.00611 U
	B19D19-100	03/18/19	PES	Pace	100	-47.5	S	–	–	–	–	0.000609 U	0.000335 U	0.000475 U	0.00108 U	0.000822 U	0.000700 U	0.000609 U	0.000852 U	0.000761 U	0.00621 U
	B19D19-105	03/18/19	PES	Pace	105	-52.5	S	–	–	–	–	0.000558 U	0.000307 U	0.000435 U	0.000985 U	0.000753 U	0.000641 U	0.000558 U	0.000781 U	0.000697 U	0.00569 U
	B19D19-110	03/18/19	PES	Pace	110	-57.5	S	–	–	–	–	0.000630 U	0.000346 U	0.000491 U	0.00111 U	0.000850 U	0.000724 U	0.000630 U	0.000881 U	0.000787 U	0.00642 U
	B-935-40	03/18/19	PES	Pace	110 (dup)	-57.5	S	–	–	–	–	0.000671 U	0.000369 U	0.000523 U	0.00118 U	0.000906 U	0.000772 U	0.000671 U	0.000939 U	0.000838 U	0.00685 U

Table G-2

Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	**–**	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	**–**	**0.030**	**1.5E-07**
PRB-B21/PRB-D21	B21D21-10	03/25/19	PES	Pace	10	44.0	V	–	–	–	–	0.000573 U	0.000316 U	0.000447 U	0.00101 U	0.000774 U	0.000660 U	0.000573 U	0.000803 U	0.000716 U	0.00585 U
	B21D21-20	03/25/19	PES	Pace	20	34.0	S	–	–	–	–	0.000592 U	0.000325 U	0.000461 U	0.00105 U	0.000799 U	0.000680 U	0.000592 U	0.000828 U	0.000739 U	0.00604 U
	B21D21-30	03/25/19	PES	Pace	30	24.0	S	–	–	–	–	0.000539 U	0.000296 U	0.000420 U	0.000952 U	0.000728 U	0.000620 U	0.000539 U	0.000755 U	0.000674 U	0.00550 U
	B21D21-40	03/25/19	PES	Pace	40	14.0	S	–	–	–	–	0.000554 U	0.000305 U	0.000432 U	0.000978 U	0.000748 U	0.000637 U	0.000554 U	0.000776 U	0.000693 U	0.00565 U
	B21D21-50	03/25/19	PES	Pace	50	4.0	S	–	–	–	–	0.000566 U	0.000311 U	0.000442 U	0.00100 U	0.000765 U	0.000651 U	0.000566 U	0.000793 U	0.000708 U	0.00578 U
	B21D21-60	03/26/19	PES	Pace	60	-6.0	S	–	–	–	–	0.000546 U	0.000300 U	0.000426 U	0.000964 U	0.000737 U	0.000628 U	0.000546 U	0.000764 U	0.000682 U	0.00557 U
	B-936-60	03/26/19	PES	Pace	60 (dup)	-6.0	S	–	–	–	–	0.000547 U	0.000301 U	0.000427 U	0.000967 U	0.000739 U	0.000629 U	0.000547 U	0.000766 U	0.000684 U	0.00558 U
All Data							Number of Analytes Measured	24	0	0	0	128	128	128	126	128	128	128	128	128	128
							Number of Analytes Detected	20	0	0	0	0	0	0	0	0	0	17	0	0	0
							Frequency of Detection	83.3%	–	–	–	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	13.3%	0.0%	0.0%	0.0%
							Maximum Detection	24.9	–	–	–	–	–	–	–	–	–	0.00763	–	–	–
							Minimum Detection	0.904 U	–	–	–	0.000519 U	0.000286 U	0.000405 U	0.000917 U	0.000701 U	0.000597 U	0.000519 U	0.000727 U	0.000649 U	0.00529 U
							Number Of Vadose (V) Detections above SL	0	0	0	0	0	0	0	0	0	0	0	–	0	0
							Number of Saturated (S) Detections above SL	0	0	0	0	0	0	0	0	0	0	4	–	0	0
2017-2021							Number of Analytes Measured	24	0	0	0	128	128	128	126	128	128	128	128	128	128
							Number of Analytes Detected	20	0	0	0	0	0	0	0	0	0	17	0	0	0
							Frequency of Detection	83.3%	–	–	–	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	13.3%	0.0%	0.0%	0.0%
							Maximum Detection	24.9	–	–	–	–	–	–	–	–	–	0.00763	–	–	–
							Minimum Detection	0.904 U	–	–	–	0.000519 U	0.000286 U	0.000405 U	0.000917 U	0.000701 U	0.000597 U	0.000519 U	0.000727 U	0.000649 U	0.00529 U
							Number Of Vadose (V) Detections above SL	0	0	0	0	0	0	0	0	0	0	0	–	0	0
							Number of Saturated (S) Detections above SL	0	0	0	0	0	0	0	0	0	0	4	–	0	0

Notes and Abbreviations:
Soil between elevations +10 to 55 feet was treated.
Petroleum Hydrocarbons (PHCs) analyzed by Ecology Method NWTPH-Gx.
VOCs analyzed by EPA Method 8260C or D.
PCUL = Preliminary Cleanup Level from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021. PCULs based on the practical quantitation limits (PQLs) italicized.
Detected results shown in **bold**.
Detections above the screening level in the vadose zone are shown in **bold** and **highlighted blue**.
Detections above the screening level in the saturated zone are shown in **bold** and **highlighted gray.**
– = Not available or results not analyzed.
J = The reported concentration is an estimate based on detectable results between the method detection limit and reporting limit, laboratory QA/QC, or data validation review.
J+ = The result is an estimated quantity, but the result may be biased high.
J- = The result is an estimated quantity, but the result may be biased low.
U = Not detected at a concentration exceeding laboratory reporting limit
z = Gasoline/petroleum detection result is likely elevated due to high detections of CVOCs.
bgs = below ground surface
dup = duplicate
Pace = Pace Analytical of Mt. Juliet, Tennessee (formerly ESC)
PES = PES Environmental, Inc.

Table G-2

Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
PRB-A3/PRB-C3	A3C3-3	01/16/19	PES	Pace	3	39.7	V	0.00123 U	0.00514 U	0.00124 U	0.00544 U	0.000560 U	0.00155 U	0.000507 U	0.00135 U	0.00115 U	0.00181 U	0.00187 U	0.00210 U	0.000846 U
	A3C3-6	01/16/19	PES	Pace	6	36.7	V	**0.00263 J**	0.00553 U	**0.00472 J**	0.00585 U	0.000602 U	0.00166 U	0.000545 U	0.00146 U	**0.00135 J**	0.00195 U	0.00201 U	0.00226 U	0.000910 U
	A3C3-8	01/16/19	PES	Pace	8	34.7	V	**0.00354 J**	0.00964 U	**0.00457 J**	0.0102 U	0.00105 U	0.00290 U	0.000950 U	0.00254 U	0.00216 U	0.00340 U	0.00350 U	0.00394 U	0.00159 U
	A3C3-10	02/13/19	PES	Pace	10	32.7	S	**0.00375 J**	0.00655 U	**0.00265 J**	0.00693 U	0.000713 U	0.00197 U	0.000645 U	0.00172 U	0.00147 U	0.00231 U	0.00238 U	0.00268 U	0.00108 U
	A3C3-15	02/13/19	PES	Pace	15	27.7	S	**0.00772**	0.00557 U	**0.00773**	0.00589 U	0.000607 U	0.00168 U	0.000549 U	0.00147 U	**0.00234 J**	0.00196 U	0.00202 U	0.00228 U	0.000917 U
	A3C3-20	02/13/19	PES	Pace	20	22.7	S	0.00132 U	0.00551 U	0.00133 U	0.00584 U	0.000601 U	0.00166 U	0.000543 U	0.00145 U	0.00124 U	0.00195 U	0.00200 U	0.00225 U	0.000907 U
	A3C3-25	02/13/19	PES	Pace	25	17.7	S	0.00137 U	0.00575 U	0.00138 U	0.00608 U	0.000626 U	0.00173 U	0.000567 U	0.00152 U	0.00129 U	0.00203 U	0.00209 U	0.00235 U	0.000946 U
	A3C3-32	02/13/19	PES	Pace	32	10.7	S	0.00133 U	0.00555 U	0.00134 U	0.00588 U	0.000605 U	0.00167 U	0.000547 U	0.00146 U	0.00124 U	0.00196 U	0.00202 U	0.00227 U	0.000914 U
	A3C3-35	02/13/19	PES	Pace	35	7.7	S	0.00130 U	0.00545 U	0.00131 U	0.00576 U	0.000593 U	0.00164 U	0.000537 U	0.00143 U	0.00122 U	0.00192 U	0.00198 U	0.00223 U	0.000896 U
	A3C3-40	02/13/19	PES	Pace	40	2.7	S	0.00142 U	0.00593 U	0.00143 U	0.00628 U	0.000646 U	0.00178 U	0.000585 U	0.00156 U	0.00133 U	0.00209 U	0.00215 U	0.00242 U	0.000976 U
	A3C3-45	02/13/19	PES	Pace	45	-2.3	S	0.00131 U	0.00547 U	0.00132 U	0.00579 U	0.000596 U	0.00165 U	0.000539 U	0.00144 U	0.00123 U	0.00193 U	0.00199 U	0.00224 U	0.000900 U
	A3C3-50	02/13/19	PES	Pace	50	-7.3	S	0.00136 U	0.00569 U	0.00137 U	0.00602 U	0.000619 U	0.00171 U	0.000560 U	0.00150 U	0.00127 U	0.00201 U	0.00206 U	0.00232 U	0.000936 U
PRB-A9/PRB-C9	A9C9-3	01/21/19	PES	Pace	3	40.1	V	0.00194 U	0.00813 U	0.00195 U	0.00861 U	0.000886 U	0.00244 U	0.000802 U	0.00214 U	0.00182 U	0.00287 U	0.00295 U	0.00332 U	0.00134 U
	A9C9-6	01/21/19	PES	Pace	6	37.1	V	**0.00365 J**	0.00590 U	**0.00729**	0.00625 U	0.000643 U	0.00178 U	0.000582 U	0.00156 U	**0.00205 J**	0.00208 U	0.00214 U	0.00241 U	0.000971 U
	A9C9-10	01/21/19	PES	Pace	10	33.1	S	0.00133 U	0.00557 U	**0.00174 J**	0.00589 U	0.000607 U	0.00168 U	0.000549 U	0.00147 U	0.00125 U	0.00196 U	0.00202 U	0.00228 U	0.000916 U
	A9C9-15	02/07/19	PES	Pace	15	28.1	S	0.00134 U	0.00562 U	0.00135 U	0.00595 U	0.000613 U	0.00169 U	0.000554 U	0.00148 U	0.00126 U	0.00198 U	0.00204 U	0.00230 U	0.000925 U
	A9C9-20	02/07/19	PES	Pace	20	23.1	S	0.00132 U	0.00554 U	0.00133 U	0.00586 U	0.000603 U	0.00167 U	0.000546 U	0.00146 U	0.00124 U	0.00195 U	0.00201 U	0.00226 U	0.000911 U
	A9C9-25	02/07/19	PES	Pace	25	18.1	S	0.00124 U	0.00519 U	0.00125 U	0.00549 U	0.000565 U	0.00156 U	0.000511 U	0.00137 U	0.00116 U	0.00183 U	0.00188 U	0.00212 U	0.000853 U
	A9C9-32	02/07/19	PES	Pace	32	11.1	S	0.00123 U	0.00515 U	0.00124 U	0.00545 U	0.000561 U	0.00155 U	**0.00771 J**	0.0136 U	0.00115 U	0.00182 U	0.00187 U	0.00210 U	0.000847 U
	A9C9-35	02/07/19	PES	Pace	35	8.1	S	0.00122 U	0.00510 U	0.00123 U	0.00540 U	0.000556 U	0.00153 U	0.000503 U	0.00134 U	0.00114 U	0.00180 U	0.00185 U	0.00208 U	0.000839 U
	A9C9-40	02/07/19	PES	Pace	40	3.1	S	0.00123 U	0.00517 U	0.00124 U	0.00547 U	0.000563 U	0.00156 U	0.000510 U	0.00136 U	0.00116 U	0.00182 U	0.00188 U	0.00211 U	0.000851 U
	A9C9-45	02/07/19	PES	Pace	45	-1.9	S	0.00120 U	0.00504 U	0.00121 U	0.00534 U	0.000549 U	0.00152 U	0.000497 U	0.00133 U	0.00113 U	0.00178 U	0.00183 U	0.00206 U	0.000830 U
	A9C9-50	02/07/19	PES	Pace	50	-6.9	S	0.00124 U	0.00518 U	0.00125 U	0.00548 U	0.000564 U	0.00156 U	0.000511 U	0.00137 U	0.00116 U	0.00183 U	0.00188 U	0.00212 U	0.000853 U
	B-931-50	02/07/19	PES	Pace	50 (dup)	-6.9	S	0.00124 U	0.00519 U	0.00125 U	0.00549 U	0.000565 U	0.00156 U	0.000511 U	0.00137 U	0.00116 U	0.00183 U	0.00188 U	0.00212 U	0.000854 U
PRB-B1/PRB-D1	B1D1-11	01/17/19	PES	Pace	11	30.8	S	0.00134 U	0.00563 U	**0.00188 J**	0.00596 U	0.000613 U	0.00169 U	0.000555 U	0.00148 U	0.00126 U	0.00199 U	0.00204 U	0.00230 U	0.000927 U
	B1D1-15	01/17/19	PES	Pace	15	26.8	S	0.00176 U	0.00737 U	0.00177 U	0.00780 U	0.000803 U	0.00222 U	0.000726 U	0.00194 U	0.00165 U	0.00260 U	0.00268 U	0.00301 U	0.00121 U
	B1D1-20	01/17/19	PES	Pace	20	21.8	S	0.00141 U	0.00592 U	0.00142 U	0.00626 U	0.000644 U	0.00178 U	0.000583 U	0.00156 U	0.00133 U	0.00209 U	0.00215 U	0.00242 U	0.000973 U
	B1D1-25	01/17/19	PES	Pace	25	16.8	S	0.00160 U	0.00670 U	0.00161 U	0.00709 U	0.000730 U	0.00202 U	0.000661 U	0.00177 U	0.00150 U	0.00236 U	0.00243 U	0.00274 U	0.00110 U
	B1D1-31	01/17/19	PES	Pace	31	10.8	S	0.00125 U	0.00525 U	0.00126 U	0.00555 U	0.000571 U	0.00158 U	0.000517 U	0.00138 U	0.00118 U	0.00185 U	0.00190 U	0.00214 U	0.000863 U
	B1D1-35	01/17/19	PES	Pace	35	6.8	S	0.00141 U	0.00590 U	0.00142 U	0.00625 U	0.000643 U	0.00178 U	0.000582 U	0.00156 U	0.00132 U	0.00208 U	0.00214 U	0.00241 U	0.000971 U
	B1D1-40	01/17/19	PES	Pace	40	1.8	S	0.00129 U	0.00539 U	0.00130 U	0.00570 U	0.000587 U	0.00162 U	0.000531 U	0.00142 U	0.00121 U	0.00190 U	0.00196 U	0.00220 U	0.000886 U
	B1D1-45	01/17/19	PES	Pace	45	-3.3	S	0.00132 U	0.00552 U	0.00133 U	0.00584 U	0.000601 U	0.00166 U	0.000544 U	0.00145 U	0.00124 U	0.00195 U	0.00200 U	0.00225 U	0.000908 U
	B1D1-50	01/17/19	PES	Pace	50	-8.3	S	0.00133 U	0.00557 U	0.00134 U	0.00589 U	0.000606 U	0.00167 U	0.000549 U	0.00147 U	0.00125 U	0.00196 U	0.00202 U	0.00228 U	0.000916 U
PRB-B2/PRB-D2	B2D2-3	01/16/19	PES	Pace	3	38.8	V	0.00125 U	0.00525 U	0.00126 U	0.00556 U	0.000572 U	0.00158 U	0.000518 U	0.00138 U	0.00118 U	0.00185 U	0.00191 U	0.00215 U	0.000864 U
	B2D2-6	01/16/19	PES	Pace	6	35.8	V	**0.00283 J**	0.00671 U	**0.00413 J**	0.00710 U	0.000731 U	0.00202 U	0.000662 U	0.00177 U	**0.00618 J**	0.00237 U	0.00244 U	0.00274 U	0.00110 U
	B2D2-10	01/21/19	PES	Pace	10	31.8	S	**0.0116 J**	0.0105 U	**0.0155**	0.0111 U	0.00115 U	0.00316 U	0.00104 U	0.00277 U	**0.00992 J**	0.00371 U	0.00382 U	0.00430 U	0.00173 U

Table G-2

Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
PRB-B4/PRB-D4	B4D4-3	01/17/19	PES	Pace	3	39.7	V	0.00130 U	0.00545 U	0.00131 U	0.00577 U	0.000594 U	0.00164 U	0.000537 U	0.00144 U	0.00122 U	0.00192 U	0.00198 U	0.00223 U	0.000897 U
	B4D4-6	01/17/19	PES	Pace	6	36.7	V	**0.00254 J**	0.00759 U	**0.00312 J**	0.00796 U	0.000826 U	0.00228 U	0.000747 U	0.00200 U	0.00171 U	0.00268 U	0.00275 U	0.00310 U	0.00125 U
	B4D4-10	01/17/19	PES	Pace	10	32.7	S	**0.00277 J**	0.00612 U	**0.00409 J**	0.00648 U	0.000667 U	0.00184 U	0.000603 U	0.00161 U	**0.00183 J**	0.00216 U	0.00222 U	0.00250 U	0.00101 U
PRB-B5/PRB-D5	B5D5-10	02/14/19	PES	Pace	10	32.9	S	**0.00141 J**	0.00565 U	**0.00148 J**	0.00598 U	0.000615 U	0.00170 U	0.000557 U	0.00149 U	–	–	0.00205 U	0.00231 U	0.000929 U
	B5D5-15	02/14/19	PES	Pace	15	27.9	S	–	0.00561 U	–	0.00594 U	0.000611 U	–	0.000553 U	–	–	0.00198 U	–	0.00229 U	0.000923 U
	B5D5-20	02/14/19	PES	Pace	20	22.9	S	0.00134 U	0.00563 U	0.00135 U	0.00596 U	0.000613 U	0.00169 U	0.000555 U	0.00148 U	0.00126 U	0.00199 U	0.00204 U	0.00230 U	0.000926 U
	B5D5-25	02/14/19	PES	Pace	25	17.9	S	0.00135 U	0.00568 U	0.00137 U	0.00601 U	0.000619 U	0.00171 U	0.000560 U	0.00150 U	0.00127 U	0.00200 U	0.00206 U	0.00232 U	0.000934 U
	B5D5-32	02/14/19	PES	Pace	32	10.9	S	0.00131 U	0.00548 U	0.00132 U	0.00579 U	0.000596 U	0.00165 U	0.000540 U	0.00144 U	0.00123 U	0.00193 U	0.00199 U	0.00224 U	0.000901 U
	B5D5-35	02/14/19	PES	Pace	35	7.9	S	0.00127 U	0.00531 U	0.00128 U	0.00562 U	0.000578 U	0.00160 U	0.000523 U	0.00140 U	0.00119 U	0.00187 U	0.00193 U	0.00217 U	0.000874 U
	B5D5-40	02/14/19	PES	Pace	40	2.9	S	0.00127 U	0.00532 U	0.00128 U	0.00562 U	0.000579 U	0.00160 U	0.000524 U	0.00140 U	0.00119 U	0.00187 U	0.00193 U	0.00217 U	0.000875 U
	B5D5-45	02/14/19	PES	Pace	45	-2.1	S	0.00124 U	0.00518 U	0.00125 U	0.00548 U	0.000565 U	0.00156 U	0.000511 U	0.00137 U	0.00116 U	0.00183 U	0.00188 U	0.00212 U	0.000853 U
	B5D5-50	02/14/19	PES	Pace	50	-7.1	S	0.00120 U	0.00502 U	**0.00146 J**	0.00532 U	0.000547 U	0.00151 U	0.000495 U	0.00132 U	0.00113 U	0.00177 U	0.00182 U	0.00205 U	0.000827 U
	B-932-50	02/14/19	PES	Pace	50 (dup)	-7.1	S	**0.00136 J**	0.00511 U	**0.00175 J**	0.00541 U	0.000557 U	0.00154 U	0.000504 U	0.00135 U	0.00115 U	0.00180 U	0.00186 U	0.00209 U	0.000841 U
PRB-B6/PRB-D6	B6D6-17	02/20/19	PES	Pace	17	25.9	S	0.00132 U	0.00554 U	0.00133 U	0.00586 U	0.000604 U	0.00167 U	0.000546 U	0.00146 U	0.00124 U	0.00195 U	0.00201 U	0.00226 U	0.000912 U
	B6D6-20	02/20/19	PES	Pace	20	22.9	S	0.00134 U	0.00560 U	0.00135 U	0.00592 U	0.000610 U	0.00168 U	0.000552 U	0.00147 U	0.00125 U	0.00197 U	0.00203 U	0.00229 U	0.000921 U
	B6D6-25	02/20/19	PES	Pace	25	17.9	S	0.00137 U	0.00574 U	0.00138 U	0.00607 U	0.000625 U	0.00173 U	0.000565 U	0.00151 U	0.00129 U	0.00202 U	0.00208 U	0.00234 U	0.000944 U
	B6D6-32	02/20/19	PES	Pace	32	10.9	S	0.00139 U	0.00581 U	0.00140 U	0.00614 U	0.000632 U	0.00175 U	0.000572 U	0.00153 U	0.00130 U	0.00205 U	0.00211 U	0.00237 U	0.000955 U
	B6D6-35	02/20/19	PES	Pace	35	7.9	S	0.00125 U	0.00523 U	0.00126 U	0.00554 U	0.000570 U	0.00157 U	0.00413 U	0.00138 U	0.00117 U	0.00185 U	0.00190 U	0.00214 U	0.000861 U
	B6D6-40	02/20/19	PES	Pace	40	2.9	S	0.00136 U	0.00569 U	0.00137 U	0.00602 U	0.000620 U	0.00171 U	0.000561 U	0.00150 U	0.00128 U	0.00201 U	0.00207 U	0.00233 U	0.000936 U
	B6D6-45	02/20/19	PES	Pace	45	-2.1	S	0.00254 U	0.0106 U	0.00256 U	0.0113 U	0.00116 U	0.00320 U	0.00105 U	0.00281 U	0.00239 U	0.00376 U	0.00387 U	0.00435 U	0.00176 U
	B6D6-50	02/20/19	PES	Pace	50	-7.1	S	0.00123 U	0.00516 U	0.00124 U	0.00546 U	0.000562 U	0.00155 U	0.000509 U	0.00136 U	0.00116 U	0.00182 U	0.00187 U	0.00211 U	0.000849 U
	B-933-50	02/20/19	PES	Pace	50 (dup)	-7.1	S	0.00127 U	0.00530 U	0.00128 U	0.00561 U	0.000578 U	0.00160 U	0.000523 U	0.00140 U	0.00119 U	0.00187 U	0.00193 U	0.00217 U	0.000872 U
PRB-B10/PRB-D10	B10D10-15	02/21/19	PES	Pace	15	30.1	S	**0.00390 J**	0.00608 U	**0.00447 J**	0.00643 U	0.000662 U	0.00183 U	0.000599 U	0.00160 U	**0.00201 J**	0.00214 U	0.00221 U	0.00248 U	0.00100 U
	B10D10-20	02/21/19	PES	Pace	20	25.1	S	0.00139 U	0.00582 U	0.00140 U	0.00616 U	0.000634 U	0.00175 U	0.000574 U	0.00153 U	0.00130 U	0.00205 U	0.00211 U	0.00238 U	0.000958 U
	B10D10-25	02/21/19	PES	Pace	25	20.1	S	0.00130 U	0.00545 U	0.00131 U	0.00576 U	0.000593 U	0.00164 U	0.00537 U	0.00144 U	0.00122 U	0.00192 U	0.00198 U	0.00223 U	0.000896 U
	B10D10-30	02/21/19	PES	Pace	30	15.1	S	0.00129 U	0.00541 U	0.00130 U	0.00573 U	0.000590 U	0.00163 U	0.0107 U	0.00143 U	0.00121 U	0.00191 U	0.00197 U	0.00221 U	0.000890 U
	B10D10-35	02/21/19	PES	Pace	35	10.1	S	0.00126 U	0.00529 U	0.00127 U	0.00560 U	0.000576 U	0.00159 U	0.000521 U	0.00139 U	0.00119 U	0.00187 U	0.00192 U	0.00216 U	0.000871 U
	B10D10-40	02/21/19	PES	Pace	40	5.1	S	0.00131 U	0.00550 U	0.00132 U	0.00582 U	0.000600 U	0.00166 U	0.000542 U	0.00145 U	0.00123 U	0.00194 U	0.00200 U	0.00225 U	0.000906 U
	B10D10-45	02/21/19	PES	Pace	45	0.1	S	0.0201 U	0.0844 U	0.0203 U	0.0893 U	0.00919 U	0.0254 U	0.00514 U	0.0223 U	0.0189 U	0.0297 U	0.0307 U	0.0345 U	0.0138 U
	B10D10-50	02/21/19	PES	Pace	50	-4.9	S	0.00127 U	0.00534 U	0.00128 U	0.00565 U	0.000581 U	0.00161 U	0.000526 U	0.00141 U	0.00120 U	0.00188 U	0.00194 U	0.00218 U	0.000878 U

Table G-2

Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
PRB-B11/PRB-D11	B11D11-10	01/15/19	PES	Pace	10	35.1	V	0.00154 U	0.00650 U	0.00156 U	0.00688 U	0.000708 U	0.00195 U	0.000640 U	0.00171 U	0.00146 U	0.00229 U	0.00236 U	0.00266 U	0.00107 U
	B11D11-15	01/15/19	PES	Pace	15	30.1	S	0.00125 U	0.00525 U	0.00126 U	0.00555 U	0.000572 U	0.00158 U	0.000517 U	0.00138 U	0.00118 U	0.00185 U	0.00191 U	0.00214 U	0.000863 U
	B11D11-20	01/15/19	PES	Pace	20	25.1	S	0.00132 U	0.00553 U	0.00133 U	0.00586 U	0.000603 U	0.00166 U	0.000545 U	0.00146 U	0.00124 U	0.00195 U	0.00201 U	0.00226 U	0.000910 U
	B11D11-27	01/15/19	PES	Pace	27	18.1	S	0.00126 U	0.00529 U	0.00127 U	0.00560 U	0.000576 U	0.00159 U	0.000521 U	0.00139 U	0.00118 U	0.00187 U	0.00192 U	0.00216 U	0.000870 U
	B11D11-30	01/15/19	PES	Pace	30	15.1	S	0.00119 U	0.00500 U	**0.00144 J**	0.00529 U	0.000545 U	0.00151 U	0.000493 U	0.00132 U	0.00112 U	0.00176 U	0.00182 U	0.00205 U	0.000823 U
	B11D11-35	01/15/19	PES	Pace	35	10.1	S	0.00129 U	0.00539 U	**0.00131 J**	0.00570 U	0.000587 U	0.00162 U	0.000531 U	0.00142 U	0.00121 U	0.00190 U	0.00196 U	0.00220 U	0.000887 U
	B11D11-40	01/15/19	PES	Pace	40	5.1	S	0.00126 U	0.00526 U	0.00127 U	0.00557 U	0.000573 U	0.00158 U	0.000518 U	0.00139 U	0.00118 U	0.00186 U	0.00191 U	0.00215 U	0.000866 U
	B11D11-46	01/15/19	PES	Pace	46	-0.9	S	0.00130 U	0.00543 U	0.00131 U	0.00575 U	0.000592 U	0.00163 U	0.000535 U	0.00143 U	0.00122 U	0.00192 U	0.00197 U	0.00222 U	0.000894 U
	B-928-46	01/15/19	PES	Pace	46 (dup)	-0.9	S	0.00129 U	0.00542 U	0.00130 U	0.00574 U	0.000591 U	0.00163 U	0.000534 U	0.00143 U	0.00121 U	0.00191 U	0.00197 U	0.00222 U	0.000892 U
	B11D11-50	01/15/19	PES	Pace	50	-4.9	S	0.00153 U	0.00643 U	**0.00192 J**	0.00680 U	0.000699 U	0.00193 U	0.000634 U	0.00169 U	0.00144 U	0.00226 U	0.00234 U	0.00262 U	0.00106 U
PRB-B13/PRB-D13	B13D13-10	03/21/19	PES	Pace	10	37.5	V	0.00131 U	0.00550 U	0.00132 U	0.00582 U	0.000599 U	0.00165 U	0.000542 U	0.00145 U	0.00123 U	0.00194 U	0.00200 U	0.00225 U	0.000904 U
	B13D13-20	03/21/19	PES	Pace	20	27.5	S	0.00136 U	0.00571 U	0.00137 U	0.00604 U	0.000622 U	0.00172 U	0.000563 U	0.00150 U	0.00128 U	0.00201 U	0.00207 U	0.00233 U	0.000939 U
	B13D13-30	03/21/19	PES	Pace	30	17.5	S	0.00132 U	0.00554 U	0.00133 U	0.00586 U	0.000603 U	0.00167 U	0.000546 U	0.00146 U	0.00124 U	0.00195 U	0.00201 U	0.00226 U	0.000911 U
	B13D13-40	03/21/19	PES	Pace	40	7.5	S	0.00123 U	0.00514 U	0.00124 U	0.00544 U	0.000560 U	0.00155 U	0.000507 U	0.00136 U	0.00115 U	0.00181 U	0.00187 U	0.00210 U	0.000846 U
	B13D13-50	03/21/19	PES	Pace	50	-2.5	S	0.00126 U	0.00529 U	0.00127 U	0.00560 U	0.000577 U	0.00159 U	0.000522 U	0.00140 U	0.00119 U	0.00187 U	0.00192 U	0.00216 U	0.000871 U
PRB-B16/PRB-D16	B16D16-15	03/13/19	PES	Pace	15	34.5	S	0.00540 U	0.0227 U	**0.00636 J**	0.0240 U	0.00247 U	0.00681 U	0.00223 U	0.00597 U	0.00507 U	0.00798 U	0.00822 U	0.00925 U	0.00372 U
	B16D16-20	03/13/19	PES	Pace	20	29.5	S	0.00126 U	0.00527 U	0.00127 U	0.00558 U	0.000574 U	0.00159 U	0.000520 U	0.00139 U	0.00118 U	0.00186 U	0.00191 U	0.00215 U	0.000867 U
	B16D16-25	03/13/19	PES	Pace	25	24.5	S	0.00123 U	0.00516 U	**0.00142 J**	0.00546 U	0.000562 U	0.00155 U	0.000509 U	0.00136 U	0.00116 U	0.00182 U	0.00187 U	0.00211 U	0.000849 U
	B16D16-30	03/13/19	PES	Pace	30	19.5	S	0.00126 U	0.00530 U	0.00127 U	0.00560 U	0.000577 U	0.00159 U	0.000522 U	0.00140 U	0.00119 U	0.00187 U	0.00192 U	0.00217 U	0.000872 U
	B16D16-35	03/13/19	PES	Pace	35	14.5	S	0.00126 U	0.00530 U	0.00128 U	0.00561 U	0.000577 U	0.00159 U	0.000522 U	0.00140 U	0.00119 U	0.00187 U	0.00192 U	0.00217 U	0.000872 U
	B16D16-40	03/13/19	PES	Pace	40	9.5	S	0.00134 U	0.00562 U	0.00135 U	0.00595 U	0.000612 U	0.00169 U	0.000554 U	0.00148 U	0.00126 U	0.00198 U	0.00204 U	0.00230 U	0.000924 U
	B16D16-45	03/13/19	PES	Pace	45	4.5	S	0.00123 U	0.00515 U	0.00124 U	0.00545 U	0.000561 U	0.00155 U	0.000508 U	0.00136 U	0.00115 U	0.00182 U	0.00187 U	0.00211 U	0.000848 U
	B16D16-50	03/13/19	PES	Pace	50	-0.5	S	0.00125 U	0.00524 U	**0.00242 J**	0.00555 U	0.000571 U	0.00158 U	0.000517 U	0.00138 U	0.00118 U	0.00185 U	0.00190 U	0.00214 U	0.000863 U
	B16D16-55	03/13/19	PES	Pace	55	-5.5	S	0.00565 U	0.0237 U	0.00570 U	0.0251 U	0.00258 U	0.00712 U	0.00233 U	0.00623 U	0.00531 U	0.00835 U	0.00859 U	0.00967 U	0.00390 U
	B16D16-60	03/13/19	PES	Pace	60	-10.5	S	0.00122 U	0.00513 U	**0.00136 J**	0.00543 U	0.000559 U	0.00154 U	0.000505 U	0.00135 U	0.00115 U	0.00181 U	0.00186 U	0.00210 U	0.000844 U
	B16D16-65	03/13/19	PES	Pace	65	-15.5	S	0.00126 U	0.00527 U	0.00127 U	0.00558 U	0.000574 U	0.00159 U	0.000520 U	0.00139 U	0.00118 U	0.00186 U	0.00191 U	0.00216 U	0.000868 U
	B16D16-70	03/13/19	PES	Pace	70	-20.5	S	0.00129 U	0.00540 U	**0.00140 J**	0.00572 U	0.000589 U	0.00163 U	0.000532 U	0.00142 U	0.00121 U	0.00191 U	0.00196 U	0.00221 U	0.000889 U
	B16D16-75	03/13/19	PES	Pace	75	-25.5	S	0.00126 U	0.00529 U	0.00127 U	0.00560 U	0.000576 U	0.00159 U	0.000521 U	0.00139 U	0.00119 U	0.00187 U	0.00192 U	0.00216 U	0.000871 U
	B16D16-80	03/13/19	PES	Pace	80	-30.5	S	0.00128 U	0.00538 U	0.00129 U	0.00569 U	0.000586 U	0.00162 U	0.000530 U	0.00142 U	0.00120 U	0.00190 U	0.00195 U	0.00220 U	0.000885 U
	B16D16-85	03/13/19	PES	Pace	85	-35.5	S	0.00128 U	0.00535 U	0.00129 U	0.00566 U	0.000582 U	0.00161 U	0.000527 U	0.00141 U	0.00120 U	0.00189 U	0.00194 U	0.00219 U	0.000880 U
	B16D16-90	03/13/19	PES	Pace	90	-40.5	S	0.00130 U	0.00544 U	0.00131 U	0.00576 U	0.000593 U	0.00164 U	0.000536 U	0.00143 U	0.00122 U	0.00192 U	0.00198 U	0.00223 U	0.000896 U
	B16D16-95	03/13/19	PES	Pace	95	-45.5	S	0.00134 U	0.00561 U	0.00135 U	0.00594 U	0.000611 U	0.00169 U	0.000553 U	0.00148 U	0.00126 U	0.00198 U	0.00204 U	0.00229 U	0.000923 U
	B16D16-100	03/13/19	PES	Pace	100	-50.5	S	0.00133 U	0.00558 U	0.00134 U	0.00591 U	0.000608 U	0.00168 U	0.000550 U	0.00147 U	0.00125 U	0.00197 U	0.00203 U	0.00228 U	0.000919 U
	B16D16-105	03/13/19	PES	Pace	105	-55.5	S	0.00131 U	0.00549 U	0.00132 U	0.00581 U	0.000598 U	0.00165 U	0.000541 U	0.00145 U	0.00123 U	0.00194 U	0.00199 U	0.00225 U	0.000904 U
	B-934-105	03/13/19	PES	Pace	105 (dup)	-55.5	S	0.00131 U	0.00550 U	0.00132 U	0.00582 U	0.000599 U	0.00165 U	0.000542 U	0.00145 U	0.00123 U	0.00194 U	0.00200 U	0.00225 U	0.000905 U

Table G-2

Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
PRB-B18/PRB-D18	B18D18-10	03/22/19	PES	Pace	10	41.0	V	0.00134 U	0.00562 U	0.00135 U	0.00595 U	0.000613 U	0.00169 U	0.000554 U	0.00148 U	0.00126 U	0.00198 U	0.00204 U	0.00230 U	0.000925 U
	B18D18-20	03/22/19	PES	Pace	20	31.0	S	0.00128 U	0.00536 U	0.00129 U	0.00567 U	0.000584 U	0.00161 U	0.000528 U	0.00141 U	0.00120 U	0.00189 U	0.00195 U	0.00219 U	0.000882 U
	B18D18-30	03/22/19	PES	Pace	30	21.0	S	0.00127 U	0.00531 U	0.00128 U	0.00562 U	0.000578 U	0.00160 U	0.000523 U	0.00140 U	0.00119 U	0.00187 U	0.00193 U	0.00217 U	0.000873 U
	B18D18-40	03/22/19	PES	Pace	40	11.0	S	0.00127 U	0.00532 U	0.00128 U	0.00563 U	0.000579 U	0.00160 U	0.000524 U	0.00140 U	0.00119 U	0.00188 U	0.00193 U	0.00217 U	0.000875 U
	B18D18-50	03/22/19	PES	Pace	50	1.0	S	0.00125 U	0.00522 U	0.00126 U	0.00553 U	0.000569 U	0.00157 U	0.000515 U	0.00138 U	0.00117 U	0.00184 U	0.00190 U	0.00214 U	0.000859 U
PRB-B19/PRB-D19	B19D19-10	03/18/19	PES	Pace	10	42.5	V	0.00127 U	0.00531 U	0.00128 U	0.00562 U	0.000579 U	0.00160 U	0.000524 U	0.00140 U	0.00119 U	0.00187 U	0.00193 U	0.00217 U	0.000874 U
	B19D19-15	03/18/19	PES	Pace	15	37.5	V	0.00142 U	0.00595 U	0.00143 U	0.00630 U	0.000647 U	0.00179 U	0.000587 U	0.00157 U	0.00133 U	0.00209 U	0.00216 U	0.00243 U	0.000978 U
	B19D19-20	03/18/19	PES	Pace	20	32.5	S	0.00134 U	0.00563 U	0.00135 U	0.00595 U	0.000613 U	0.00169 U	0.000554 U	0.00148 U	0.00126 U	0.00198 U	0.00204 U	0.00230 U	0.000926 U
	B19D19-25	03/18/19	PES	Pace	25	27.5	S	0.00142 U	0.00597 U	0.00143 U	0.00632 U	0.000651 U	0.00180 U	0.000589 U	0.00157 U	0.00134 U	0.00211 U	0.00217 U	0.00244 U	0.000983 U
	B19D19-30	03/18/19	PES	Pace	30	22.5	S	0.00132 U	0.00554 U	0.00133 U	0.00586 U	0.000603 U	0.00167 U	0.000546 U	0.00146 U	0.00124 U	0.00195 U	0.00201 U	0.00226 U	0.000911 U
	B19D19-35	03/18/19	PES	Pace	35	17.5	S	0.00130 U	0.00547 U	0.00132 U	0.00578 U	0.000595 U	0.00164 U	0.000539 U	0.00144 U	0.00122 U	0.00193 U	0.00198 U	0.00223 U	0.000899 U
	B19D19-40	03/18/19	PES	Pace	40	12.5	S	0.00134 U	0.00561 U	0.00135 U	0.00594 U	0.000612 U	0.00169 U	0.000553 U	0.00148 U	0.00126 U	0.00198 U	0.00204 U	0.00229 U	0.000924 U
	B19D19-45	03/18/19	PES	Pace	45	7.5	S	0.00134 U	0.00558 U	0.00135 U	0.00590 U	0.000608 U	0.00168 U	0.000550 U	0.00147 U	0.00125 U	0.00197 U	0.00203 U	0.00228 U	0.000919 U
	B19D19-50	03/18/19	PES	Pace	50	2.5	S	0.00132 U	0.00553 U	0.00133 U	0.00585 U	0.000602 U	0.00166 U	0.000545 U	0.00146 U	0.00124 U	0.00195 U	0.00201 U	0.00226 U	0.000909 U
	B19D19-55	03/18/19	PES	Pace	55	-2.5	S	0.00133 U	0.00555 U	0.00134 U	0.00588 U	0.000605 U	0.00167 U	0.000547 U	0.00146 U	0.00124 U	0.00196 U	0.00202 U	0.00227 U	0.000914 U
	B19D19-60	03/18/19	PES	Pace	60	-7.5	S	0.00129 U	0.00540 U	0.00130 U	0.00571 U	0.000588 U	0.00162 U	0.000532 U	0.00142 U	0.00121 U	0.00190 U	0.00196 U	0.00221 U	0.000888 U
	B19D19-65	03/18/19	PES	Pace	65	-12.5	S	0.00146 U	0.00612 U	0.00147 U	0.00648 U	0.000666 U	0.00184 U	0.000602 U	0.00161 U	0.00138 U	0.00216 U	0.00222 U	0.00250 U	0.00101 U
	B19D19-70	03/18/19	PES	Pace	70	-17.5	S	0.00140 U	0.00588 U	**0.00197 J**	0.00622 U	0.000641 U	0.00177 U	0.000580 U	0.00155 U	0.00132 U	0.00207 U	0.00214 U	0.00240 U	0.000968 U
	B19D19-75	03/18/19	PES	Pace	75	-22.5	S	0.00136 U	0.00573 U	0.00138 U	0.00606 U	0.000624 U	0.00172 U	0.000565 U	0.00151 U	0.00128 U	0.00202 U	0.00208 U	0.00234 U	0.000943 U
	B19D19-80	03/18/19	PES	Pace	80	-27.5	S	0.00130 U	0.00546 U	**0.00140 J**	0.00578 U	0.000595 U	0.00164 U	0.000538 U	0.00144 U	0.00122 U	0.00193 U	0.00198 U	0.00223 U	0.000898 U
	B19D19-85	03/18/19	PES	Pace	85	-32.5	S	0.00140 U	0.00585 U	0.00141 U	0.00619 U	0.000638 U	0.00176 U	0.000577 U	0.00154 U	0.00131 U	0.00206 U	0.00213 U	0.00239 U	0.000963 U
	B19D19-90	03/18/19	PES	Pace	90	-37.5	S	0.00145 U	0.00607 U	0.00146 U	0.00642 U	0.000661 U	0.00182 U	0.000598 U	0.00160 U	0.00136 U	0.00214 U	0.00220 U	0.00248 U	0.000998 U
	B19D19-95	03/18/19	PES	Pace	95	-42.5	S	0.00138 U	0.00578 U	0.00139 U	0.00611 U	0.000629 U	0.00174 U	0.000569 U	0.00152 U	0.00129 U	0.00204 U	0.00210 U	0.00236 U	0.000951 U
	B19D19-100	03/18/19	PES	Pace	100	-47.5	S	0.00140 U	0.00587 U	0.00141 U	0.00621 U	0.000639 U	0.00176 U	0.000579 U	0.00154 U	0.00131 U	0.00207 U	0.00213 U	0.00240 U	0.000966 U
	B19D19-105	03/18/19	PES	Pace	105	-52.5	S	0.00128 U	0.00538 U	0.00129 U	0.00569 U	0.000586 U	0.00162 U	0.000530 U	0.00142 U	0.00120 U	0.00190 U	0.00195 U	0.00220 U	0.000885 U
	B19D19-110	03/18/19	PES	Pace	110	-57.5	S	0.00145 U	0.00607 U	0.00146 U	0.00642 U	0.000661 U	0.00183 U	0.000598 U	0.00160 U	0.00136 U	0.00214 U	0.00220 U	0.00248 U	0.000998 U
	B-935-40	03/18/19	PES	Pace	110 (dup)	-57.5	S	0.00154 U	0.00646 U	0.00155 U	0.00685 U	0.000704 U	0.00195 U	0.000638 U	0.00170 U	0.00145 U	0.00228 U	0.00235 U	0.00265 U	0.00106 U

Table G-2

Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
PRB-B21/PRB-D21	B21D21-10	03/25/19	PES	Pace	10	44.0	V	0.00132 U	0.00553 U	0.00133 U	0.00585 U	0.000601 U	0.00167 U	0.000545 U	0.00146 U	0.00123 U	0.00195 U	0.00201 U	0.00226 U	0.000909 U
	B21D21-20	03/25/19	PES	Pace	20	34.0	S	0.00136 U	0.00570 U	0.00137 U	0.00604 U	0.000621 U	0.00172 U	0.000562 U	0.00150 U	0.00128 U	0.00202 U	0.00207 U	0.00233 U	0.000938 U
	B21D21-30	03/25/19	PES	Pace	30	24.0	S	0.00124 U	0.00520 U	0.00125 U	0.00550 U	0.000566 U	0.00156 U	0.000512 U	0.00137 U	0.00116 U	0.00183 U	0.00189 U	0.00212 U	0.000855 U
	B21D21-40	03/25/19	PES	Pace	40	14.0	S	0.00127 U	0.00534 U	0.00129 U	0.00565 U	0.000582 U	0.00161 U	0.000526 U	0.00141 U	0.00120 U	0.00188 U	0.00194 U	0.00218 U	0.000879 U
	B21D21-50	03/25/19	PES	Pace	50	4.0	S	0.00130 U	0.00546 U	0.00131 U	0.00578 U	0.000595 U	0.00164 U	0.000538 U	0.00144 U	0.00122 U	0.00193 U	0.00198 U	0.00223 U	0.000898 U
	B21D21-60	03/26/19	PES	Pace	60	-6.0	S	0.00126 U	0.00526 U	0.00127 U	0.00557 U	0.000573 U	0.00158 U	0.000518 U	0.00139 U	0.00118 U	0.00186 U	0.00191 U	0.00215 U	0.000865 U
	B-936-60	03/26/19	PES	Pace	60 (dup)	-6.0	S	0.00126 U	0.00528 U	**0.00146 J**	0.00558 U	0.000575 U	0.00159 U	0.000520 U	0.00139 U	0.00118 U	0.00186 U	0.00192 U	0.00216 U	0.000868 U
All Data	Number of Analytes Measured							127	128	127	128	128	127	128	127	126	127	127	128	128
	Number of Analytes Detected							11	0	24	0	0	0	1	0	7	0	0	0	0
	Frequency of Detection							8.7%	0.0%	18.9%	0.0%	0.0%	0.0%	0.8%	0.0%	5.6%	0.0%	0.0%	0.0%	0.0%
	Maximum Detection							0.0116 J	–	0.0155	–	–	–	0.00771 J	–	0.00992 J	–	–	–	–
	Minimum Detection							0.00119 U	0.005 U	0.00121 U	0.00529 U	0.000545 U	0.00151 U	0.000493 U	0.00132 U	0.00112 U	0.00176 U	0.00182 U	0.00205 U	0.000823 U
	Number Of Vadose (V) Detections above SL							0	0	0	0	0	0	0	0	0	–	0	0	–
	Number of Saturated (S) Detections above SL							0	0	0	0	0	0	1	0	0	–	0	0	–
2017-2021	Number of Analytes Measured							127	128	127	128	128	127	128	127	126	127	127	128	128
	Number of Analytes Detected							11	0	24	0	0	0	1	0	7	0	0	0	0
	Frequency of Detection							8.7%	0.0%	18.9%	0.0%	0.0%	0.0%	0.8%	0.0%	5.6%	0.0%	0.0%	0.0%	0.0%
	Maximum Detection							0.0116 J	–	0.0155	–	–	–	0.00771 J	–	0.00992 J	–	–	–	–
	Minimum Detection							0.00119 U	0.005 U	0.00121 U	0.00529 U	0.000545 U	0.00151 U	0.000493 U	0.00132 U	0.00112 U	0.00176 U	0.00182 U	0.00205 U	0.000823 U
	Number Of Vadose (V) Detections above SL							0	0	0	0	0	0	0	0	0	–	0	0	–
	Number of Saturated (S) Detections above SL							0	0	0	0	0	0	1	0	0	–	0	0	–

Notes and Abbreviations:
Soil between elevations +10 to 55 feet was treated.
Petroleum Hydrocarbons (PHCs) analyzed by Ecology Method NWTPH-Gx.
VOCs analyzed by EPA Method 8260C or D.
PCUL = Preliminary Cleanup Level from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021. PCULs based on the practical quantitation limits (PQLs) italicized. Detected results shown in bold.
Detections above the screening level in the vadose zone are shown in **bold and highlighted blue**.
Detections above the screening level in the saturated zone are shown in **bold and highlighted gray.**
– = Not available or results not analyzed.
J = The reported concentration is an estimate based on detectable results between the method detection limit and reporting limit, laboratory QA/QC, or data validation review.
J+ = The result is an estimated quantity, but the result may be biased high.
J- = The result is an estimated quantity, but the result may be biased low.
U = Not detected at a concentration exceeding laboratory reporting limit
z = Gasoline/petroleum detection result is likely elevated due to high detections of CVOCs.
bgs = below ground surface
dup = duplicate
Pace = Pace Analytical of Mt. Juliet, Tennessee (formerly ESC)
PES = PES Environmental, Inc.

Table G-2

Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	**–**	**–**	**29**	**0.030**	**0.027**	**0.56**	**–**	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	**–**	**–**	**2.1**	**0.030**	**0.002**	**0.033**	**–**	**0.023**	**0.0033**	**0.27**
PRB-A3/PRB-C3	A3C3-3	01/16/19	PES	Pace	3	39.7	V	**0.0194 J**	0.000981 U	0.0107 U	0.00121 U	0.00248 U	0.0146 U	0.00203 U	0.000427 U	0.00112 U	0.00121 U	0.00638 U	0.00395 U	0.00433 U
	A3C3-6	01/16/19	PES	Pace	6	36.7	V	0.0143 U	0.00106 U	0.0115 U	0.00130 U	0.00267 U	0.0157 U	0.00218 U	0.000459 U	0.00120 U	0.00130 U	0.00686 U	0.00424 U	0.00466 U
	A3C3-8	01/16/19	PES	Pace	8	34.7	V	0.0251 U	0.00184 U	0.0200 U	0.00227 U	**0.0289**	0.0274 U	0.00380 U	**0.00540**	0.00210 U	0.00227 U	0.0120 U	0.00741 U	0.00813 U
	A3C3-10	02/13/19	PES	Pace	10	32.7	S	0.0170 U	0.00125 U	0.0136 U	0.00153 U	**0.00474 J**	**0.0708**	0.00258 U	**0.00236**	0.00143 U	0.00153 U	0.00812 U	0.00503 U	**0.00895 J**
	A3C3-15	02/13/19	PES	Pace	15	27.7	S	0.0144 U	0.00106 U	0.0116 U	0.00131 U	**0.00775**	**0.0273 J**	0.00220 U	**0.00298**	0.00121 U	0.00131 U	0.00691 U	0.00428 U	**0.00665 J**
	A3C3-20	02/13/19	PES	Pace	20	22.7	S	**0.0310**	0.00105 U	0.0114 U	0.00129 U	0.00267 U	0.0157 U	0.00217 U	**0.000913 J**	0.00120 U	0.00129 U	0.00684 U	0.00423 U	0.00465 U
	A3C3-25	02/13/19	PES	Pace	25	17.7	S	0.0149 U	0.00110 U	0.0119 U	0.00135 U	0.00278 U	0.0163 U	0.00227 U	**0.000638 J**	0.00125 U	0.00135 U	0.00713 U	0.00441 U	0.00484 U
	A3C3-32	02/13/19	PES	Pace	32	10.7	S	0.0144 U	0.00106 U	0.0115 U	0.00130 U	0.00268 U	0.0158 U	0.00219 U	**0.000776 J**	0.00121 U	0.00130 U	0.00689 U	0.00426 U	0.00468 U
	A3C3-35	02/13/19	PES	Pace	35	7.7	S	**0.0205 J**	0.00104 U	0.0113 U	0.00128 U	0.00263 U	0.0155 U	0.00215 U	**0.000572 J**	0.00119 U	0.00128 U	0.00676 U	0.00418 U	0.00459 U
	A3C3-40	02/13/19	PES	Pace	40	2.7	S	**0.0288 J**	0.00113 U	0.0123 U	0.00139 U	0.00287 U	0.0169 U	0.00234 U	**0.000654 J**	0.00129 U	0.00139 U	0.00736 U	0.00455 U	0.00500 U
	A3C3-45	02/13/19	PES	Pace	45	-2.3	S	0.0142 U	0.00104 U	0.0113 U	0.00128 U	0.00264 U	0.0155 U	0.00216 U	**0.00108 J**	0.00119 U	0.00128 U	0.00679 U	0.00420 U	0.00461 U
	A3C3-50	02/13/19	PES	Pace	50	-7.3	S	**0.0194 J**	0.00109 U	0.0118 U	0.00133 U	0.00275 U	0.0162 U	0.00224 U	**0.000509 J**	0.00124 U	0.00133 U	0.00706 U	0.00437 U	0.00479 U
PRB-A9/PRB-C9	A9C9-3	01/21/19	PES	Pace	3	40.1	V	**0.0467**	0.00156 U	0.0169 U	0.00191 U	**0.00489 J**	**0.0265 J**	0.00320 U	**0.141**	0.00178 U	0.00191 U	0.0101 U	0.00624 U	0.00685 U
	A9C9-6	01/21/19	PES	Pace	6	37.1	V	**0.0452**	0.00113 U	0.0123 U	0.00138 U	**0.00779**	**0.0248 J**	0.00233 U	**0.0153**	0.00129 U	0.00138 U	0.00733 U	0.00453 U	0.00497 U
	A9C9-10	01/21/19	PES	Pace	10	33.1	S	**0.0305**	0.00106 U	0.0116 U	0.00131 U	0.00269 U	**0.0336**	0.00220 U	**0.0228**	0.00121 U	0.00131 U	0.00691 U	0.00428 U	0.00469 U
	A9C9-15	02/07/19	PES	Pace	15	28.1	S	**0.0149 J**	0.00107 U	0.0117 U	0.00132 U	0.00272 U	**0.0696**	0.00222 U	**0.00166**	0.00123 U	0.00132 U	0.00698 U	0.00432 U	0.00474 U
	A9C9-20	02/07/19	PES	Pace	20	23.1	S	0.0144 U	0.00106 U	0.0115 U	0.00130 U	0.00268 U	0.0157 U	0.00218 U	**0.000462 J**	0.00121 U	0.00130 U	0.00687 U	0.00425 U	0.00467 U
	A9C9-25	02/07/19	PES	Pace	25	18.1	S	**0.0207 J**	0.000990 U	0.0108 U	0.00122 U	0.00251 U	0.0147 U	0.00204 U	0.000430 U	0.00113 U	0.00122 U	0.00644 U	0.00398 U	0.00437 U
	A9C9-32	02/07/19	PES	Pace	32	11.1	S	**0.0169 J**	0.000983 U	0.0107 U	0.00121 U	0.00249 U	0.146 U	0.00203 U	**0.000558 J**	0.00112 U	0.00121 U	0.00639 U	0.00395 U	0.00434 U
	A9C9-35	02/07/19	PES	Pace	35	8.1	S	0.0132 U	0.000974 U	0.0106 U	0.00120 U	0.00247 U	0.0145 U	0.00201 U	0.000423 U	0.00111 U	0.00120 U	0.00633 U	0.00392 U	0.00430 U
	A9C9-40	02/07/19	PES	Pace	40	3.1	S	**0.0209 J**	0.000987 U	0.0107 U	0.00121 U	0.00250 U	0.0147 U	0.00204 U	**0.000825 J**	0.00113 U	0.00121 U	0.00641 U	0.00397 U	0.00436 U
	A9C9-45	02/07/19	PES	Pace	45	-1.9	S	**0.0182 J**	0.000963 U	0.0105 U	0.00118 U	0.00244 U	0.0143 U	0.00199 U	**0.000500 J**	0.00110 U	0.00118 U	0.00626 U	0.00387 U	**0.00996 J**
	A9C9-50	02/07/19	PES	Pace	50	-6.9	S	**0.0166 J**	0.000989 U	0.0108 U	0.00121 U	0.00250 U	**0.0170 J**	0.00204 U	**0.000690 J**	0.00113 U	0.00121 U	0.00643 U	0.00398 U	0.00436 U
	B-931-50	02/07/19	PES	Pace	50 (dup)	-6.9	S	**0.0156 J**	0.000990 U	0.0108 U	0.00122 U	0.00251 U	0.0147 U	0.00204 U	**0.000725 J**	0.00113 U	0.00122 U	0.00644 U	0.00398 U	0.00437 U
PRB-B1/PRB-D1	B1D1-11	01/17/19	PES	Pace	11	30.8	S	0.0146 U	0.00107 U	0.0117 U	0.00132 U	**0.0141**	0.0160 U	0.00222 U	**0.00250**	0.00123 U	0.00132 U	0.00699 U	0.00432 U	0.00474 U
	B1D1-15	01/17/19	PES	Pace	15	26.8	S	0.0191 U	0.00141 U	0.0153 U	0.00173 U	0.00356 U	0.0209 U	0.00290 U	0.000611 U	0.00161 U	0.00173 U	0.00914 U	0.00566 U	0.00621 U
	B1D1-20	01/17/19	PES	Pace	20	21.8	S	0.0153 U	0.00113 U	0.0123 U	0.00139 U	0.00286 U	0.0168 U	0.00233 U	0.000491 U	0.00129 U	0.00139 U	0.00734 U	0.00454 U	0.00498 U
	B1D1-25	01/17/19	PES	Pace	25	16.8	S	0.0174 U	0.00128 U	0.0139 U	0.00157 U	0.00324 U	0.0191 U	0.00264 U	**0.000625 J**	0.00146 U	0.00157 U	0.00832 U	0.00515 U	0.00565 U
	B1D1-31	01/17/19	PES	Pace	31	10.8	S	0.0136 U	0.00100 U	0.0109 U	0.00123 U	0.00254 U	0.0149 U	0.00207 U	0.000435 U	0.00114 U	0.00123 U	0.00651 U	0.00403 U	0.00442 U
	B1D1-35	01/17/19	PES	Pace	35	6.8	S	0.0153 U	0.00113 U	0.0122 U	0.00138 U	0.00285 U	0.0168 U	0.00233 U	0.000490 U	0.00129 U	0.00138 U	0.00732 U	0.00453 U	0.00497 U
	B1D1-40	01/17/19	PES	Pace	40	1.8	S	0.0140 U	0.00103 U	0.0112 U	0.00126 U	0.00260 U	0.0153 U	0.00212 U	0.000447 U	0.00117 U	0.00126 U	0.00668 U	0.00414 U	0.00454 U
	B1D1-45	01/17/19	PES	Pace	45	-3.3	S	0.0143 U	0.00105 U	0.0114 U	0.00129 U	0.00267 U	0.0157 U	0.00217 U	0.000458 U	0.00120 U	0.00129 U	0.00684 U	0.00423 U	0.00465 U
	B1D1-50	01/17/19	PES	Pace	50	-8.3	S	0.0144 U	0.00106 U	0.0116 U	0.00131 U	0.00269 U	0.0158 U	0.00219 U	0.000462 U	0.00121 U	0.00131 U	0.00691 U	0.00427 U	0.00469 U
PRB-B2/PRB-D2	B2D2-3	01/16/19	PES	Pace	3	38.8	V	**0.0206 J**	0.00100 U	0.0109 U	0.00123 U	0.00254 U	0.0149 U	0.00207 U	0.000436 U	0.00114 U	0.00123 U	0.00652 U	0.00403 U	0.00443 U
	B2D2-6	01/16/19	PES	Pace	6	35.8	V	0.0174 U	0.00128 U	0.0139 U	0.00157 U	**0.0695**	0.0191 U	0.00265 U	**0.0111**	0.00146 U	0.00157 U	0.00833 U	0.00515 U	0.00565 U
	B2D2-10	01/21/19	PES	Pace	10	31.8	S	**0.213**	0.00200 U	0.0219 U	0.00246 U	**0.118**	**0.168**	0.00415 U	**0.274**	0.00230 U	0.00246 U	0.0131 U	0.00808 U	**0.0228 J**

Table G-2

Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
PRB-B4/PRB-D4	B4D4-3	01/17/19	PES	Pace	3	39.7	V	**0.0388**	0.00104 U	0.0113 U	0.00128 U	0.00264 U	0.0155 U	0.00215 U	0.000453 U	0.00119 U	0.00128 U	0.00677 U	0.00419 U	0.00459 U
	B4D4-6	01/17/19	PES	Pace	6	36.7	V	**0.0763**	0.00145 U	0.0157 U	0.00178 U	**0.0100**	0.0215 U	0.00299 U	**0.00961**	0.00165 U	0.00178 U	0.00941 U	0.00582 U	0.00638 U
	B4D4-10	01/17/19	PES	Pace	10	32.7	S	**0.0545**	0.00117 U	0.0127 U	0.00144 U	**0.00814**	0.0174 U	0.00241 U	**0.00245 J-**	0.00133 U	0.00144 U	0.00759 U	0.00470 U	**0.00913 J**
PRB-B5/PRB-D5	B5D5-10	02/14/19	PES	Pace	10	32.9	S	–	–	–	–	0.00273 U	–	0.00223 U	**0.00147**	–	–	0.00701 U	0.00434 U	0.00476 U
	B5D5-15	02/14/19	PES	Pace	15	27.9	S	–	–	0.0116 U	–	0.00271 U	0.0160 U	0.00221 U	0.000466 U	0.00122 U	–	0.00696 U	0.00431 U	0.00473 U
	B5D5-20	02/14/19	PES	Pace	20	22.9	S	0.0146 U	0.00107 U	0.0117 U	0.00132 U	0.00272 U	**0.0162 J**	0.00222 U	0.000467 U	0.00123 U	0.00132 U	0.00698 U	0.00432 U	0.00474 U
	B5D5-25	02/14/19	PES	Pace	25	17.9	S	**0.0222 J**	0.00108 U	0.0118 U	0.00133 U	0.00275 U	0.0161 U	0.00224 U	0.000471 U	0.00124 U	0.00133 U	0.00705 U	0.00436 U	0.00478 U
	B5D5-32	02/14/19	PES	Pace	32	10.9	S	**0.0316**	0.00105 U	0.0114 U	0.00128 U	0.00265 U	0.0156 U	0.00216 U	**0.000600 J**	0.00119 U	0.00128 U	0.00679 U	0.00420 U	0.00461 U
	B5D5-35	02/14/19	PES	Pace	35	7.9	S	–	0.00101 U	0.0110 U	0.00124 U	–	0.0151 U	0.00209 U	**0.000735 J**	0.00116 U	0.00124 U	0.00659 U	0.00408 U	0.00447 U
	B5D5-40	02/14/19	PES	Pace	40	2.9	S	0.0138 U	0.00101 U	0.0110 U	0.00125 U	0.00257 U	0.0151 U	0.00210 U	**0.000878 J**	0.00116 U	0.00125 U	0.00660 U	0.00408 U	0.00448 U
	B5D5-45	02/14/19	PES	Pace	45	-2.1	S	0.0134 U	0.000989 U	0.0108 U	0.00122 U	0.00251 U	0.0589 U	0.00204 U	**0.000824 J**	0.00113 U	0.00122 U	0.00643 U	0.00398 U	0.00437 U
	B5D5-50	02/14/19	PES	Pace	50	-7.1	S	0.0130 U	0.000959 U	0.0104 U	0.00118 U	0.00243 U	0.0143 U	0.00198 U	**0.000797 J**	0.00109 U	0.00118 U	0.00623 U	0.00386 U	0.00423 U
	B-932-50	02/14/19	PES	Pace	50 (dup)	-7.1	S	**0.0438**	0.000976 U	0.0106 U	0.00120 U	0.00247 U	**0.0155 J**	0.00202 U	**0.000746 J**	0.00111 U	0.00120 U	0.00635 U	0.00393 U	0.00431 U
PRB-B6/PRB-D6	B6D6-17	02/20/19	PES	Pace	17	25.9	S	0.0144 U	0.00106 U	0.0115 U	0.00130 U	0.00268 U	0.0157 U	0.00218 U	0.000460 U	0.00121 U	0.00130 U	0.00687 U	0.00425 U	0.00467 U
	B6D6-20	02/20/19	PES	Pace	20	22.9	S	0.0145 U	0.00107 U	0.0116 U	0.00131 U	0.00271 U	0.0159 U	0.00221 U	0.000465 U	0.00122 U	0.00131 U	0.00694 U	0.00430 U	0.00471 U
	B6D6-25	02/20/19	PES	Pace	25	17.9	S	0.0149 U	0.00109 U	0.0119 U	0.00134 U	0.00277 U	0.0163 U	0.00226 U	0.000476 U	0.00125 U	0.00134 U	0.00712 U	0.00440 U	0.00483 U
	B6D6-32	02/20/19	PES	Pace	32	10.9	S	0.0151 U	0.00111 U	0.0120 U	0.00136 U	0.00281 U	0.0165 U	0.00229 U	0.000482 U	0.00126 U	0.00136 U	0.00720 U	0.00446 U	0.00489 U
	B6D6-35	02/20/19	PES	Pace	35	7.9	S	0.0136 U	0.000999 U	0.0109 U	0.00123 U	0.00253 U	0.0149 U	0.00206 U	**0.000453 J**	0.00114 U	0.00123 U	0.0519 U	0.00402 U	0.00441 U
	B6D6-40	02/20/19	PES	Pace	40	2.9	S	0.0148 U	0.00109 U	0.0118 U	0.00133 U	0.00275 U	0.0162 U	0.00224 U	**0.000692 J**	0.00124 U	0.00133 U	0.00706 U	0.00437 U	0.00479 U
	B6D6-45	02/20/19	PES	Pace	45	-2.1	S	0.0276 U	0.00203 U	0.0221 U	0.00250 U	0.00515 U	0.0303 U	0.00420 U	0.000884 U	0.00232 U	0.00250 U	0.0133 U	0.00817 U	0.00897 U
	B6D6-50	02/20/19	PES	Pace	50	-7.1	S	0.0134 U	0.000985 U	0.0107 U	0.00121 U	0.00249 U	0.0147 U	0.00203 U	0.000428 U	0.00112 U	0.00121 U	0.00640 U	0.00396 U	0.00435 U
	B-933-50	02/20/19	PES	Pace	50 (dup)	-7.1	S	0.0138 U	0.00101 U	0.0110 U	0.00124 U	0.00256 U	0.0151 U	0.00209 U	0.000440 U	0.00116 U	0.00124 U	0.00658 U	0.00407 U	0.00447 U
PRB-B10/PRB-D10	B10D10-15	02/21/19	PES	Pace	15	30.1	S	0.0158 U	0.00116 U	0.0126 U	0.00142 U	**0.00695**	0.0173 U	0.00240 U	**0.00843**	0.00132 U	0.00142 U	0.00754 U	0.00466 U	0.00512 U
	B10D10-20	02/21/19	PES	Pace	20	25.1	S	0.0151 U	0.00111 U	0.0121 U	0.00136 U	0.00281 U	0.0165 U	0.00229 U	0.000483 U	0.00127 U	0.00136 U	0.00722 U	0.00447 U	0.00490 U
	B10D10-25	02/21/19	PES	Pace	25	20.1	S	0.0141 U	0.00104 U	0.0113 U	0.00128 U	0.00263 U	0.0155 U	0.00215 U	0.000452 U	0.00119 U	0.00128 U	0.0676 U	0.00418 U	0.00459 U
	B10D10-30	02/21/19	PES	Pace	30	15.1	S	0.0140 U	0.00103 U	0.0112 U	0.00127 U	0.00262 U	0.0154 U	0.00213 U	0.000449 U	0.00118 U	0.00127 U	0.135 U	0.00415 U	0.00456 U
	B10D10-35	02/21/19	PES	Pace	35	10.1	S	0.0137 U	0.00101 U	0.0110 U	0.00124 U	0.00256 U	0.0150 U	0.00209 U	0.000439 U	0.00115 U	0.00124 U	0.00656 U	0.00406 U	0.00446 U
	B10D10-40	02/21/19	PES	Pace	40	5.1	S	0.0143 U	0.00105 U	0.0114 U	0.00129 U	0.00266 U	0.0156 U	0.00217 U	0.000457 U	0.00120 U	0.00129 U	0.00683 U	0.00423 U	0.00464 U
	B10D10-45	02/21/19	PES	Pace	45	0.1	S	0.218 U	0.0161 U	0.175 U	0.0198 U	0.0408 U	0.240 U	0.0333 U	0.00701 U	0.0184 U	0.0198 U	0.0647 U	0.0648 U	0.0711 U
	B10D10-50	02/21/19	PES	Pace	50	-4.9	S	0.0138 U	0.00102 U	0.0111 U	0.00125 U	0.00258 U	0.0152 U	0.00210 U	0.000443 U	0.00116 U	0.00125 U	0.00662 U	0.00410 U	0.00450 U

Table G-2

Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)		2-Chlorotoluene		2-Hexanone		4-Chlorotoluene		4-Isopropyltoluene (p-Isopropyltoluene)		Acetone		Acrylonitrile		Benzene		Bromobenzene		Bromochloromethane		Bromoform		Bromomethane		Carbon Disulfide	
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**		**1.9**		**0.17**		–		–		**29**		**0.030**		**0.027**		**0.56**		–		**0.36**		**0.05**		**5**	
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**		**0.11**		**0.012**		–		–		**2.1**		**0.030**		**0.002**		**0.033**		–		**0.023**		**0.0033**		**0.27**	
PRB-B11/PRB-D11	B11D11-10	01/15/19	PES	Pace	10	35.1	V	**0.0481**		0.00124	U	0.0135	U	0.00152	U	0.00314	U	**0.0961**		0.00256	U	0.000539	U	0.00141	U	0.00152	U	0.00806	U	0.00499	U	0.00547	U
	B11D11-15	01/15/19	PES	Pace	15	30.1	S	0.0136	U	0.00100	U	0.0109	U	0.00123	U	0.00254	U	**0.0185**	**J**	0.00207	U	0.000436	U	0.00114	U	0.00123	U	0.00651	U	0.00403	U	0.00442	U
	B11D11-20	01/15/19	PES	Pace	20	25.1	S	0.0144	U	0.00106	U	0.0115	U	0.00130	U	0.00268	U	0.0157	U	0.00218	U	0.000459	U	0.00121	U	0.00130	U	0.00687	U	0.00425	U	0.00466	U
	B11D11-27	01/15/19	PES	Pace	27	18.1	S	0.0137	U	0.00101	U	0.0110	U	0.00124	U	0.00256	U	0.0150	U	0.00208	U	0.000439	U	0.00115	U	0.00124	U	0.00656	U	0.00406	U	0.00445	U
	B11D11-30	01/15/19	PES	Pace	30	15.1	S	0.0130	U	0.000955	U	0.0104	U	0.00117	U	0.00242	U	**0.0167**	**J**	0.00197	U	0.000415	U	0.00109	U	0.00117	U	0.00621	U	0.00384	U	0.00422	U
	B11D11-35	01/15/19	PES	Pace	35	10.1	S	0.0140	U	0.00103	U	0.0112	U	0.00126	U	0.00261	U	**0.0347**		0.00213	U	**0.000469**	**J**	0.00117	U	0.00126	U	0.00669	U	0.00414	U	0.00454	U
	B11D11-40	01/15/19	PES	Pace	40	5.1	S	0.0136	U	0.00100	U	0.0109	U	0.00123	U	0.00254	U	**0.0204**	**J**	0.00207	U	0.000437	U	0.00115	U	0.00123	U	0.00653	U	0.00404	U	0.00443	U
	B11D11-46	01/15/19	PES	Pace	46	-0.9	S	0.0141	U	0.00104	U	0.0113	U	0.00127	U	0.00263	U	**0.0274**	**J**	0.00214	U	0.000451	U	0.00118	U	0.00127	U	0.00674	U	0.00417	U	0.00458	U
	B-928-46	01/15/19	PES	Pace	46 (dup)	-0.9	S	0.0141	U	0.00103	U	0.0112	U	0.00127	U	0.00262	U	**0.0274**	**J**	0.00214	U	0.000450	U	0.00118	U	0.00127	U	0.00673	U	0.00416	U	0.00457	U
	B11D11-50	01/15/19	PES	Pace	50	-4.9	S	0.0166	U	0.00122	U	0.0133	U	0.00151	U	0.00310	U	**0.0426**		0.00254	U	0.000533	U	0.00140	U	0.00151	U	0.00798	U	0.00493	U	0.00541	U
PRB-B13/PRB-D13	B13D13-10	03/21/19	PES	Pace	10	37.5	V	0.0143	U	0.00105	U	0.0114	U	0.00129	U	0.00266	U	0.0156	U	0.00217	U	0.000456	U	0.00120	U	0.00129	U	0.00682	U	0.00422	U	0.00463	U
	B13D13-20	03/21/19	PES	Pace	20	27.5	S	0.0148	U	0.00109	U	0.0118	U	0.00134	U	0.00276	U	0.0162	U	0.00225	U	0.000474	U	0.00124	U	0.00134	U	0.00708	U	0.00438	U	0.00481	U
	B13D13-30	03/21/19	PES	Pace	30	17.5	S	0.0144	U	0.00106	U	0.0115	U	0.00130	U	0.00268	U	0.0157	U	0.00218	U	0.000460	U	0.00121	U	0.00130	U	0.00687	U	0.00425	U	0.00466	U
	B13D13-40	03/21/19	PES	Pace	40	7.5	S	0.0133	U	0.000982	U	0.0107	U	0.00121	U	0.00249	U	**0.0274**		0.00203	U	0.000427	U	0.00112	U	0.00121	U	0.00638	U	0.00395	U	0.00433	U
	B13D13-50	03/21/19	PES	Pace	50	-2.5	S	0.0137	U	0.00101	U	0.0110	U	0.00124	U	0.00256	U	0.0150	U	0.00209	U	0.000439	UJ	0.00115	U	0.00124	U	0.00657	U	0.00406	U	0.00446	U
PRB-B16/PRB-D16	B16D16-15	03/13/19	PES	Pace	15	34.5	S	0.0587	U	0.00432	U	0.0470	U	0.00531	U	0.0109	U	**0.0908**	**J**	0.00892	U	0.00188	U	0.00493	U	0.00531	U	0.0281	U	0.0174	U	0.0190	U
	B16D16-20	03/13/19	PES	Pace	20	29.5	S	0.0137	U	0.00101	U	0.0109	U	0.00124	U	0.00255	U	0.0150	U	0.00208	U	0.000438	U	0.00115	U	0.00124	U	0.00654	U	0.00405	U	0.00444	U
	B16D16-25	03/13/19	PES	Pace	25	24.5	S	**0.0265**	**J**	0.000985	U	0.0107	U	0.00121	U	0.00250	U	**0.0183**	**J**	0.00203	U	0.000428	U	0.00112	U	0.00121	U	0.00640	U	0.00396	U	0.00435	U
	B16D16-30	03/13/19	PES	Pace	30	19.5	S	**0.0402**		0.00101	U	0.0110	U	0.00124	U	0.00256	U	**0.0196**	**J**	0.00209	U	0.000440	U	0.00115	U	0.00124	U	0.00657	U	0.00407	U	0.00446	U
	B16D16-35	03/13/19	PES	Pace	35	14.5	S	0.0137	U	0.00101	U	0.0110	U	0.00124	U	0.00256	U	0.0151	U	0.00209	U	**0.000599**	**J**	0.00115	U	0.00124	U	0.00657	U	0.00407	U	0.00446	U
	B16D16-40	03/13/19	PES	Pace	40	9.5	S	0.0146	U	0.00107	U	0.0117	U	0.00132	U	0.00272	U	**0.0278**	**J**	0.00221	U	0.000466	U	0.00122	U	0.00132	U	0.00697	U	0.00431	U	**0.00566**	**J**
	B16D16-45	03/13/19	PES	Pace	45	4.5	S	**0.0157**	**J**	0.000983	U	0.0107	U	0.00121	U	0.00249	U	**0.0226**	**J**	0.00203	U	0.000428	U	0.00112	U	0.00121	U	0.00639	U	0.00395	U	0.00434	U
	B16D16-50	03/13/19	PES	Pace	50	-0.5	S	**0.0680**		0.00100	U	0.0109	U	0.00123	U	0.00254	U	**0.0334**		0.00207	U	**0.000448**	**J**	0.00114	U	0.00123	U	0.00651	U	0.00403	U	0.00442	U
	B16D16-55	03/13/19	PES	Pace	55	-5.5	S	0.0614	U	0.00452	U	0.0491	U	0.00555	U	0.0114	U	**0.110**	**J**	0.00933	U	0.00196	U	0.00516	U	0.00555	U	0.0294	U	0.0181	U	0.0200	U
	B16D16-60	03/13/19	PES	Pace	60	-10.5	S	0.0133	U	0.000979	U	0.0106	U	0.00120	U	0.00248	U	**0.0192**	**J**	0.00202	U	0.000426	U	0.00112	U	0.00120	U	0.00636	U	0.00394	U	**0.00501**	**J**
	B16D16-65	03/13/19	PES	Pace	65	-15.5	S	**0.0226**	**J**	0.00101	U	0.0109	U	0.00124	U	0.00255	U	**0.0160**	**J**	0.00208	U	0.000438	U	0.00115	U	0.00124	U	0.00654	U	0.00405	U	0.00444	U
	B16D16-70	03/13/19	PES	Pace	70	-20.5	S	**0.0212**	**J**	0.00103	U	0.0112	U	0.00127	U	0.00261	U	**0.0287**		0.00213	U	**0.000766**	**J**	0.00118	U	0.00127	U	0.00670	U	0.00415	U	0.00455	U
	B16D16-75	03/13/19	PES	Pace	75	-25.5	S	**0.0215**	**J**	0.00101	U	0.0110	U	0.00124	U	0.00256	U	**0.0346**		0.00209	U	**0.000674**	**J**	0.00115	U	0.00124	U	0.00657	U	0.00406	U	0.00446	U
	B16D16-80	03/13/19	PES	Pace	80	-30.5	S	**0.0147**	**J**	0.00103	U	0.0112	U	0.00126	U	0.00260	U	0.0153	U	0.00212	U	0.000446	U	0.00117	U	0.00126	U	0.00667	U	0.00413	U	0.00453	U
	B16D16-85	03/13/19	PES	Pace	85	-35.5	S	**0.0236**	**J**	0.00102	U	0.0111	U	0.00125	U	0.00258	U	**0.0289**		0.00211	U	**0.000468**	**J**	0.00116	U	0.00125	U	0.00663	U	0.00410	U	0.00450	U
	B16D16-90	03/13/19	PES	Pace	90	-40.5	S	**0.0165**	**J**	0.00104	U	0.0113	U	0.00128	U	0.00263	U	0.0155	U	0.00215	U	0.000452	U	0.00119	U	0.00128	U	0.00675	U	0.00418	U	0.00459	U
	B16D16-95	03/13/19	PES	Pace	95	-45.5	S	**0.0171**	**J**	0.00107	U	0.0116	U	0.00132	U	0.00271	U	0.0160	U	0.00221	U	0.000466	U	0.00122	U	0.00132	U	0.00696	U	0.00431	U	0.00473	U
	B16D16-100	03/13/19	PES	Pace	100	-50.5	S	0.0145	U	0.00107	U	0.0116	U	0.00131	U	0.00270	U	**0.0216**	**J**	0.00220	U	0.000463	U	0.00122	U	0.00131	U	0.00693	U	0.00429	U	0.00470	U
	B16D16-105	03/13/19	PES	Pace	105	-55.5	S	0.0142	U	0.00105	U	0.0114	U	0.00129	U	0.00266	U	**0.0242**	**J**	0.00217	U	0.000456	U	0.00120	U	0.00129	U	0.00682	U	0.00422	U	0.00463	U
	B-934-105	03/13/19	PES	Pace	105 (dup)	-55.5	S	0.0143	U	0.00105	U	0.0114	U	0.00129	U	0.00266	U	**0.0624**		0.00217	U	0.000456	U	0.00120	U	0.00129	U	0.00682	U	0.00422	U	0.00463	U

Table G-2

Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
PRB-B18/PRB-D18	B18D18-10	03/22/19	PES	Pace	10	41.0	V	0.0146 U	0.00107 U	0.0117 U	0.00132 U	0.00272 U	0.0160 U	0.00222 U	0.000467 U	0.00123 U	0.00132 U	0.00698 U	0.00432 U	0.00474 U
	B18D18-20	03/22/19	PES	Pace	20	31.0	S	**0.116**	0.00102 U	0.0111 U	0.00126 U	0.00259 U	0.0152 U	0.00211 U	**0.000467 J**	0.00117 U	0.00126 U	0.00665 U	0.00411 U	0.00451 U
	B18D18-30	03/22/19	PES	Pace	30	21.0	S	0.0138 U	0.00101 U	0.0110 U	0.00124 U	0.00257 U	**0.0492**	0.00209 U	**0.000548 J**	0.00116 U	0.00124 U	0.00659 U	0.00407 U	0.00447 U
	B18D18-40	03/22/19	PES	Pace	40	11.0	S	0.0138 U	0.00102 U	0.0110 U	0.00125 U	0.00257 U	**0.0166 J**	0.00210 U	0.000441 U	0.00116 U	0.00125 U	0.00660 U	0.00408 U	0.00448 U
	B18D18-50	03/22/19	PES	Pace	50	1.0	S	0.0135 U	0.000997 U	0.0108 U	0.00122 U	0.00253 U	0.0148 U	0.00206 U	0.000434 U	0.00114 U	0.00122 U	0.00648 U	0.00401 U	0.00440 U
PRB-B19/PRB-D19	B19D19-10	03/18/19	PES	Pace	10	42.5	V	0.0138 U	0.00101 U	0.0110 U	0.00125 U	0.00257 U	0.0151 U	0.00209 U	0.000441 U	0.00116 U	0.00125 U	0.00659 U	0.00408 U	0.00447 U
	B19D19-15	03/18/19	PES	Pace	15	37.5	V	0.0154 U	0.00113 U	0.0123 U	0.00140 U	0.00287 U	0.0169 U	0.00234 U	0.000493 U	0.00129 U	0.00140 U	0.00738 U	0.00456 U	0.00500 U
	B19D19-20	03/18/19	PES	Pace	20	32.5	S	0.0146 U	0.00107 U	0.0117 U	0.00132 U	0.00272 U	0.0160 U	0.00222 U	0.000467 U	0.00123 U	0.00132 U	0.00698 U	0.00432 U	0.00474 U
	B19D19-25	03/18/19	PES	Pace	25	27.5	S	0.0155 U	0.00114 U	0.0124 U	0.00140 U	0.00289 U	0.0170 U	0.00235 U	0.000496 U	0.00130 U	0.00140 U	0.00741 U	0.00459 U	**0.00667 J**
	B19D19-30	03/18/19	PES	Pace	30	22.5	S	0.0144 U	0.00106 U	0.0115 U	0.00130 U	0.00268 U	0.0157 U	0.00218 U	0.000460 U	0.00121 U	0.00130 U	0.00687 U	0.00425 U	0.00467 U
	B19D19-35	03/18/19	PES	Pace	35	17.5	S	0.0142 U	0.00104 U	0.0113 U	0.00128 U	0.00264 U	0.0155 U	0.00215 U	0.000454 U	0.00119 U	0.00128 U	0.00678 U	0.00420 U	0.00460 U
	B19D19-40	03/18/19	PES	Pace	40	12.5	S	0.0146 U	0.00107 U	0.0116 U	0.00132 U	0.00271 U	0.0160 U	0.00221 U	0.000466 U	0.00122 U	0.00132 U	0.00697 U	0.00431 U	0.00473 U
	B19D19-45	03/18/19	PES	Pace	45	7.5	S	0.0145 U	0.00107 U	0.0116 U	0.00131 U	0.00270 U	0.311 U	0.00221 U	0.000463 U	0.00121 U	0.00131 U	0.00693 U	0.00429 U	0.00470 U
	B19D19-50	03/18/19	PES	Pace	50	2.5	S	0.0143 U	0.00105 U	0.0115 U	0.00130 U	0.00267 U	0.0157 U	0.00218 U	**0.000779 J**	0.00120 U	0.00130 U	0.00686 U	0.00424 U	0.00466 U
	B19D19-55	03/18/19	PES	Pace	55	-2.5	S	0.0144 U	0.00106 U	0.0115 U	0.00130 U	0.00268 U	0.0158 U	0.00219 U	**0.000769 J**	0.00121 U	0.00130 U	0.00689 U	0.00426 U	0.00468 U
	B19D19-60	03/18/19	PES	Pace	60	-7.5	S	**0.0166 J**	0.00103 U	0.0112 U	0.00127 U	0.00261 U	0.0153 U	0.00213 U	0.000448 U	0.00118 U	0.00127 U	0.00670 U	0.00415 U	**0.00535 J**
	B19D19-65	03/18/19	PES	Pace	65	-12.5	S	0.0159 U	0.00117 U	0.0127 U	0.00143 U	0.00295 U	**0.0196 J**	0.00241 U	0.000508 U	0.00133 U	0.00143 U	0.00759 U	0.00470 U	0.00515 U
	B19D19-70	03/18/19	PES	Pace	70	-17.5	S	0.0153 U	0.00112 U	0.0122 U	0.00138 U	0.00284 U	0.0167 U	0.00232 U	0.000488 U	0.00128 U	0.00138 U	0.00730 U	0.00452 U	0.00496 U
	B19D19-75	03/18/19	PES	Pace	75	-22.5	S	0.0148 U	0.00109 U	0.0119 U	0.00134 U	0.00277 U	0.0162 U	0.00226 U	0.000475 U	0.00125 U	0.00134 U	0.00711 U	0.00440 U	0.00482 U
	B19D19-80	03/18/19	PES	Pace	80	-27.5	S	0.0142 U	0.00104 U	0.0113 U	0.00128 U	0.00264 U	0.0155 U	0.00215 U	0.000453 U	0.00119 U	0.00128 U	0.00677 U	0.00419 U	0.00460 U
	B19D19-85	03/18/19	PES	Pace	85	-32.5	S	0.0152 U	0.00112 U	0.0121 U	0.00137 U	0.00283 U	**0.0167 J**	0.00231 U	0.000486 U	0.00128 U	0.00137 U	0.00726 U	0.00449 U	0.00493 U
	B19D19-90	03/18/19	PES	Pace	90	-37.5	S	0.0158 U	0.00116 U	0.0126 U	0.00142 U	0.00293 U	**0.0242 J**	0.00239 U	0.000504 U	0.00132 U	0.00142 U	0.00753 U	0.00466 U	0.00511 U
	B19D19-95	03/18/19	PES	Pace	95	-42.5	S	0.0150 U	0.00110 U	0.0120 U	0.00135 U	0.00279 U	0.0164 U	0.00228 U	0.000479 U	0.00126 U	0.00135 U	0.00717 U	0.00444 U	0.00487 U
	B19D19-100	03/18/19	PES	Pace	100	-47.5	S	0.0152 U	0.00112 U	0.0122 U	0.00137 U	0.00283 U	**0.0227 J**	0.00231 U	0.000487 U	0.00128 U	0.00137 U	0.00728 U	0.00451 U	0.00494 U
	B19D19-105	03/18/19	PES	Pace	105	-52.5	S	0.0139 U	0.00103 U	0.0112 U	0.00126 U	0.00260 U	**0.0164 J**	0.00212 U	0.000446 U	0.00117 U	0.00126 U	0.00667 U	0.00413 U	0.00453 U
	B19D19-110	03/18/19	PES	Pace	110	-57.5	S	0.0157 U	0.00116 U	0.0126 U	0.00142 U	0.00293 U	**0.0247 J**	0.00239 U	0.000504 U	0.00132 U	0.00142 U	0.00753 U	0.00466 U	0.00511 U
	B-935-40	03/18/19	PES	Pace	110 (dup)	-57.5	S	0.0167 U	0.00123 U	0.0134 U	0.00151 U	0.00313 U	0.0183 U	0.00255 U	0.000537 U	0.00140 U	0.00151 U	0.00803 U	0.00496 U	0.00544 U

Table G-2

Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
PRB-B21/PRB-D21	B21D21-10	03/25/19	PES	Pace	10	44.0	V	0.0143 U	0.00105 U	0.0115 U	0.00130 U	0.00267 U	0.0157 U	0.00217 U	0.000459 U	0.00120 U	0.00130 U	0.00686 U	0.00424 U	0.00465 U
	B21D21-20	03/25/19	PES	Pace	20	34.0	S	0.0148 U	0.00109 U	0.0118 U	0.00134 U	0.00276 U	0.0162 U	0.00225 U	0.000473 U	0.00124 U	0.00134 U	0.00708 U	0.00438 U	0.00480 U
	B21D21-30	03/25/19	PES	Pace	30	24.0	S	0.0135 U	0.000992 U	0.0108 U	0.00122 U	0.00251 U	**0.0261 J**	0.00205 U	0.000431 U	0.00113 U	0.00122 U	0.00645 U	0.00399 U	**0.0141**
	B21D21-40	03/25/19	PES	Pace	40	14.0	S	0.0139 U	0.00102 U	0.0111 U	0.00125 U	0.00258 U	**0.0227 J**	0.00211 U	0.000443 U	0.00116 U	0.00125 U	0.00663 U	0.00410 U	0.00450 U
	B21D21-50	03/25/19	PES	Pace	50	4.0	S	**0.0353**	0.00104 U	0.0113 U	0.00128 U	0.00264 U	**0.0361**	0.00215 U	0.000453 U	0.00119 U	0.00128 U	0.00677 U	0.00419 U	0.00460 U
	B21D21-60	03/26/19	PES	Pace	60	-6.0	S	**0.0427**	0.00100 U	0.0109 U	0.00123 U	0.00254 U	**0.0321**	0.00207 U	0.000437 U	0.00115 U	0.00123 U	0.00653 U	0.00404 U	0.00443 U
	B-936-60	03/26/19	PES	Pace	60 (dup)	-6.0	S	**0.0321**	0.00101 U	0.0109 U	0.00124 U	0.00255 U	–	0.00208 U	0.000438 U	0.00115 U	0.00124 U	0.00655 U	0.00405 U	0.00444 U
All Data							Number of Analytes Measured	125	126	127	126	127	127	128	128	127	126	128	128	128
							Number of Analytes Detected	37	0	0	0	11	43	0	44	0	0	0	0	10
							Frequency of Detection	29.6%	0.0%	0.0%	0.0%	8.7%	33.9%	0.0%	34.4%	0.0%	0.0%	0.0%	0.0%	7.8%
							Maximum Detection	0.213	–	–	–	0.118	0.168	–	0.274	–	–	–	–	0.0228 J
							Minimum Detection	0.013 U	0.000955 U	0.0104 U	0.00117 U	0.00242 U	0.0143 U	0.00197 U	0.000415 U	0.00109 U	0.00117 U	0.00621 U	0.00384 U	0.00422 U
							Number Of Vadose (V) Detections above SL	0	0	0	–	–	0	0	1	0	–	0	0	0
							Number of Saturated (S) Detections above SL	0	0	0	–	–	0	0	7	0	–	0	0	0
2017-2021							Number of Analytes Measured	125	126	127	126	127	127	128	128	127	126	128	128	128
							Number of Analytes Detected	37	0	0	0	11	43	0	44	0	0	0	0	10
							Frequency of Detection	29.6%	0.0%	0.0%	0.0%	8.7%	33.9%	0.0%	34.4%	0.0%	0.0%	0.0%	0.0%	7.8%
							Maximum Detection	0.213	–	–	–	0.118	0.168	–	0.274	–	–	–	–	0.0228 J
							Minimum Detection	0.013 U	0.000955 U	0.0104 U	0.00117 U	0.00242 U	0.0143 U	0.00197 U	0.000415 U	0.00109 U	0.00117 U	0.00621 U	0.00384 U	0.00422 U
							Number Of Vadose (V) Detections above SL	0	0	0	–	–	0	0	1	0	–	0	0	0
							Number of Saturated (S) Detections above SL	0	0	0	–	–	0	0	7	0	–	0	0	0

Notes and Abbreviations:
Soil between elevations +10 to 55 feet was treated.
Petroleum Hydrocarbons (PHCs) analyzed by Ecology Method NWTPH-Gx.
VOCs analyzed by EPA Method 8260C or D.
PCUL = Preliminary Cleanup Level from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021. PCULs based on the practical quantitation limits (PQLs) italicized. Detected results shown in bold.
Detections above the screening level in the vadose zone are shown in **bold and highlighted blue.**
Detections above the screening level in the saturated zone are shown in **bold and highlighted gray.**
– = Not available or results not analyzed.
J = The reported concentration is an estimate based on detectable results between the method detection limit and reporting limit, laboratory QA/QC, or data validation review.
J+ = The result is an estimated quantity, but the result may be biased high.
J- = The result is an estimated quantity, but the result may be biased low.
U = Not detected at a concentration exceeding laboratory reporting limit
z = Gasoline/petroleum detection result is likely elevated due to high detections of CVOCs.
bgs = below ground surface
dup = duplicate
Pace = Pace Analytical of Mt. Juliet, Tennessee (formerly ESC)
PES = PES Environmental, Inc.

Table G-2

Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
PRB-A3/PRB-C3	A3C3-3	01/16/19	PES	Pace	3	39.7	V	0.00115 U	0.000611 U	0.000480 U	0.00115 U	0.000443 U	0.00148 U	0.000736 U	0.000723 U	0.00107 U	0.000840 U	0.000872 U	0.000565 U
	A3C3-6	01/16/19	PES	Pace	6	36.7	V	0.00124 U	0.000657 U	0.000516 U	0.00124 U	0.000476 U	0.00159 U	**0.00343**	0.000778 U	0.00115 U	0.000904 U	0.000938 U	**0.00140 J**
	A3C3-8	01/16/19	PES	Pace	8	34.7	V	0.00216 U	0.00115 U	0.000901 U	0.00216 U	0.000830 U	0.00277 U	**0.00948**	0.00136 U	0.00200 U	0.00158 U	0.00164 U	**0.00311 J**
	A3C3-10	02/13/19	PES	Pace	10	32.7	S	0.00147 U	0.000778 U	0.000611 U	0.00147 U	0.000564 U	0.00189 U	**0.00175 J**	0.000921 U	0.00136 U	0.00107 U	0.00111 U	**0.00132 J**
	A3C3-15	02/13/19	PES	Pace	15	27.7	S	0.00125 U	0.000662 U	0.000520 U	0.00125 U	0.000480 U	0.00161 U	0.000798 U	0.000784 U	0.00116 U	0.000911 U	0.000945 U	**0.00379**
	A3C3-20	02/13/19	PES	Pace	20	22.7	S	0.00124 U	0.000656 U	0.000515 U	0.00124 U	0.000475 U	0.00159 U	0.000789 U	0.000776 U	0.00114 U	0.000902 U	0.000936 U	0.000606 U
	A3C3-25	02/13/19	PES	Pace	25	17.7	S	0.00129 U	0.000684 U	0.000537 U	0.00129 U	0.000495 U	0.00166 U	**0.00390**	0.000809 U	0.00119 U	0.000940 U	0.000976 U	0.000632 U
	A3C3-32	02/13/19	PES	Pace	32	10.7	S	0.00124 U	0.000660 U	0.000518 U	0.00124 U	0.000478 U	0.00160 U	**0.119**	0.000781 U	0.00115 U	0.000908 U	0.000942 U	0.000611 U
	A3C3-35	02/13/19	PES	Pace	35	7.7	S	0.00122 U	0.000647 U	0.000508 U	0.00122 U	0.000469 U	0.00157 U	**0.0369**	0.000766 U	0.00113 U	0.000890 U	0.000924 U	0.000599 U
	A3C3-40	02/13/19	PES	Pace	40	2.7	S	0.00133 U	0.000705 U	0.000554 U	0.00133 U	0.000511 U	0.00171 U	**0.471**	0.000834 U	0.00123 U	0.000970 U	0.00101 U	0.000652 U
	A3C3-45	02/13/19	PES	Pace	45	-2.3	S	0.00123 U	0.000650 U	0.000511 U	0.00123 U	0.000471 U	0.00158 U	**0.121**	0.000769 U	0.00113 U	0.000894 U	0.000928 U	0.000602 U
	A3C3-50	02/13/19	PES	Pace	50	-7.3	S	0.00127 U	0.000676 U	0.000531 U	0.00127 U	0.000490 U	0.00164 U	**0.108**	0.000800 U	0.00118 U	0.000930 U	0.000965 U	0.000625 U
PRB-A9/PRB-C9	A9C9-3	01/21/19	PES	Pace	3	40.1	V	0.00182 U	0.000968 U	0.000760 U	0.00182 U	0.000700 U	0.00234 U	0.00116 U	0.00114 U	0.00169 U	0.00133 U	0.00138 U	**0.00160 J**
	A9C9-6	01/21/19	PES	Pace	6	37.1	V	0.00132 U	0.000702 U	0.000551 U	0.00132 U	0.000508 U	0.00170 U	0.000845 U	0.000831 U	0.00123 U	0.000965 U	0.00100 U	**0.00295 J**
	A9C9-10	01/21/19	PES	Pace	10	33.1	S	0.00125 U	0.000662 U	0.000520 U	0.00125 U	**0.000510 J**	0.00161 U	**0.00338**	0.000784 U	0.00116 U	0.000911 U	0.000945 U	**0.000632 J**
	A9C9-15	02/07/19	PES	Pace	15	28.1	S	0.00126 U	0.000669 U	0.000525 U	0.00126 U	0.000484 U	0.00162 U	**0.0243**	0.000791 U	0.00117 U	0.000920 U	0.000955 U	0.000618 U
	A9C9-20	02/07/19	PES	Pace	20	23.1	S	0.00124 U	0.000659 U	0.000517 U	0.00124 U	0.000477 U	0.00160 U	**0.00665**	0.000779 U	0.00115 U	0.000906 U	0.000940 U	0.000609 U
	A9C9-25	02/07/19	PES	Pace	25	18.1	S	0.00116 U	0.000617 U	0.000484 U	0.00116 U	0.000447 U	0.00150 U	**0.00881**	0.000730 U	0.00108 U	0.000848 U	0.000880 U	0.000570 U
	A9C9-32	02/07/19	PES	Pace	32	11.1	S	0.00115 U	0.000612 U	0.000481 U	0.00115 U	0.000443 U	0.00148 U	**1.04**	0.000724 U	0.00107 U	0.000842 U	0.000874 U	0.000566 U
	A9C9-35	02/07/19	PES	Pace	35	8.1	S	0.00114 U	0.000606 U	0.000476 U	0.00114 U	0.000439 U	0.00147 U	**0.167**	0.000718 U	0.00106 U	0.000834 U	0.000866 U	0.000561 U
	A9C9-40	02/07/19	PES	Pace	40	3.1	S	0.00116 U	0.000615 U	0.000483 U	0.00116 U	0.000445 U	0.00149 U	**1.74**	0.000727 U	0.00107 U	0.000845 U	0.000877 U	0.000569 U
	A9C9-45	02/07/19	PES	Pace	45	-1.9	S	0.00113 U	0.000600 U	0.000471 U	0.00113 U	0.000434 U	0.00145 U	**0.0596**	0.000709 U	0.00105 U	0.000825 U	0.000856 U	0.000555 U
	A9C9-50	02/07/19	PES	Pace	50	-6.9	S	0.00116 U	0.000616 U	0.000484 U	0.00116 U	0.000446 U	0.00149 U	**0.0743**	0.000729 U	0.00108 U	0.000847 U	0.000879 U	0.000570 U
	B-931-50	02/07/19	PES	Pace	50 (dup)	-6.9	S	0.00116 U	0.000617 U	0.000484 U	0.00116 U	0.000447 U	0.00150 U	**0.0869**	0.000730 U	0.00108 U	0.000848 U	0.000880 U	0.000570 U
PRB-B1/PRB-D1	B1D1-11	01/17/19	PES	Pace	11	30.8	S	0.00126 U	0.000669 U	0.000526 U	0.00126 U	0.000485 U	0.00162 U	0.000806 U	0.000792 U	0.00117 U	0.000921 U	0.000956 U	**0.00129 J**
	B1D1-15	01/17/19	PES	Pace	15	26.8	S	0.00165 U	0.000876 U	0.000688 U	0.00165 U	0.000634 U	0.00212 U	0.00105 U	0.00104 U	0.00153 U	0.00120 U	0.00125 U	0.000810 U
	B1D1-20	01/17/19	PES	Pace	20	21.8	S	0.00133 U	0.000703 U	0.000552 U	0.00133 U	0.000509 U	0.00171 U	**0.0236**	0.000832 U	0.00123 U	0.000967 U	0.00100 U	0.000651 U
	B1D1-25	01/17/19	PES	Pace	25	16.8	S	0.00150 U	0.000797 U	0.000626 U	0.00150 U	0.000577 U	0.00193 U	**0.148**	0.000943 U	0.00139 U	0.00110 U	0.00114 U	0.000737 U
	B1D1-31	01/17/19	PES	Pace	31	10.8	S	0.00118 U	0.000624 U	0.000490 U	0.00118 U	0.000452 U	0.00151 U	**0.0147**	0.000738 U	0.00109 U	0.000858 U	0.000890 U	0.000577 U
	B1D1-35	01/17/19	PES	Pace	35	6.8	S	0.00132 U	0.000702 U	0.000551 U	0.00132 U	0.000508 U	0.00170 U	**0.0194**	0.000830 U	0.00122 U	0.000965 U	0.00100 U	0.000649 U
	B1D1-40	01/17/19	PES	Pace	40	1.8	S	0.00121 U	0.000641 U	0.000503 U	0.00121 U	0.000464 U	0.00155 U	**0.0157**	0.000758 U	0.00112 U	0.000881 U	0.000914 U	0.000592 U
	B1D1-45	01/17/19	PES	Pace	45	-3.3	S	0.00124 U	0.000656 U	0.000515 U	0.00124 U	0.000475 U	0.00159 U	**0.0852**	0.000776 U	0.00114 U	0.000902 U	0.000936 U	0.000607 U
	B1D1-50	01/17/19	PES	Pace	50	-8.3	S	0.00125 U	0.000662 U	0.000520 U	0.00125 U	0.000479 U	0.00161 U	**0.199**	0.000783 U	0.00116 U	0.000910 U	0.000945 U	0.000612 U
PRB-B2/PRB-D2	B2D2-3	01/16/19	PES	Pace	3	38.8	V	0.00118 U	0.000625 U	0.000491 U	0.00118 U	0.000452 U	0.00152 U	0.000752 U	0.000739 U	0.00109 U	0.000859 U	0.000892 U	0.000578 U
	B2D2-6	01/16/19	PES	Pace	6	35.8	V	0.00150 U	0.000798 U	0.000627 U	0.00150 U	0.000578 U	0.00194 U	0.000961 U	0.000944 U	0.00139 U	0.00110 U	0.00114 U	**0.00256 J**
	B2D2-10	01/21/19	PES	Pace	10	31.8	S	0.00235 U	0.00125 U	0.000985 U	0.00235 U	0.000907 U	0.00303 U	**0.864**	0.00148 U	0.00219 U	0.00172 U	0.00177 U	**0.0240**

Table G-2

Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
PRB-B4/PRB-D4	B4D4-3	01/17/19	PES	Pace	3	39.7	V	0.00122 U	0.000648 U	0.000509 U	0.00122 U	0.000470 U	0.00157 U	0.000781 U	0.000767 U	0.00113 U	0.000891 U	0.000925 U	0.000600 U
	B4D4-6	01/17/19	PES	Pace	6	36.7	V	0.00171 U	0.000901 U	0.000709 U	0.00171 U	0.000653 U	0.00219 U	**0.00697**	0.00107 U	0.00157 U	0.00124 U	0.00127 U	**0.00168 J**
	B4D4-10	01/17/19	PES	Pace	10	32.7	S	0.00137 U	0.000728 U	0.000571 U	0.00137 U	0.000527 U	0.00177 U	**0.0467 J-**	0.000861 U	0.00127 U	0.00100 U	0.00104 U	**0.00140 J-**
PRB-B5/PRB-D5	B5D5-10	02/14/19	PES	Pace	10	32.9	S	–	0.000671 U	0.000527 U	–	0.000486 U	0.00163 U	**0.0484**	0.000794 U	–	0.000923 U	0.000958 U	0.000621 U
	B5D5-15	02/14/19	PES	Pace	15	27.9	S	–	0.000667 U	0.000524 U	–	0.000483 U	–	**0.0104**	0.000789 U	0.00116 U	0.000917 U	0.000952 U	0.000617 U
	B5D5-20	02/14/19	PES	Pace	20	22.9	S	0.00126 U	0.000669 U	0.000526 U	0.00126 U	0.000485 U	0.00162 U	**0.0277**	0.000792 U	0.00117 U	0.000920 U	0.000955 U	0.000619 U
	B5D5-25	02/14/19	PES	Pace	25	17.9	S	0.00127 U	0.000675 U	0.000530 U	0.00127 U	0.000489 U	0.00164 U	**0.156**	0.000799 U	0.00118 U	0.000928 U	0.000964 U	0.000624 U
	B5D5-32	02/14/19	PES	Pace	32	10.9	S	0.00123 U	0.000651 U	0.000511 U	0.00123 U	0.000471 U	0.00158 U	**0.257**	0.000770 U	0.00114 U	0.000895 U	0.000929 U	0.000602 U
	B5D5-35	02/14/19	PES	Pace	35	7.9	S	0.00119 U	0.000631 U	–	–	0.000457 U	–	**0.924**	0.000747 U	–	0.000868 U	0.000901 U	0.000584 U
	B5D5-40	02/14/19	PES	Pace	40	2.9	S	0.00119 U	0.000632 U	0.000496 U	0.00119 U	0.000458 U	0.00153 U	**1.80**	0.000748 U	0.00110 U	0.000869 U	0.000902 U	0.000585 U
	B5D5-45	02/14/19	PES	Pace	45	-2.1	S	0.00116 U	0.000616 U	0.000484 U	0.00116 U	0.000446 U	0.00149 U	**0.712**	0.000729 U	0.00108 U	0.000847 U	0.000880 U	0.000570 U
	B5D5-50	02/14/19	PES	Pace	50	-7.1	S	0.00113 U	0.000597 U	0.000469 U	0.00113 U	0.000433 U	0.00145 U	**0.0246**	0.000707 U	0.00104 U	0.000821 U	0.000853 U	0.000553 U
	B-932-50	02/14/19	PES	Pace	50 (dup)	-7.1	S	0.00115 U	0.000608 U	0.000477 U	0.00115 U	0.000440 U	0.00147 U	**0.0260**	0.000719 U	0.00106 U	0.000836 U	0.000868 U	**0.000651 J**
PRB-B6/PRB-D6	B6D6-17	02/20/19	PES	Pace	17	25.9	S	0.00124 U	0.000659 U	0.000517 U	0.00124 U	0.000477 U	0.00160 U	**0.00388**	0.000779 U	0.00115 U	0.000906 U	0.000940 U	0.000609 U
	B6D6-20	02/20/19	PES	Pace	20	22.9	S	0.00125 U	0.000665 U	0.000523 U	0.00125 U	0.000482 U	0.00161 U	**0.0233**	0.000787 U	0.00116 U	0.000915 U	0.000950 U	0.000615 U
	B6D6-25	02/20/19	PES	Pace	25	17.9	S	0.00129 U	0.000682 U	0.000536 U	0.00129 U	0.000494 U	0.00165 U	**0.0372**	0.000807 U	0.00119 U	0.000938 U	0.000974 U	0.000631 U
	B6D6-32	02/20/19	PES	Pace	32	10.9	S	0.00130 U	0.000690 U	0.000542 U	0.00130 U	0.000500 U	0.00167 U	**0.402**	0.000817 U	0.00120 U	0.000949 U	0.000985 U	0.000638 U
	B6D6-35	02/20/19	PES	Pace	35	7.9	S	0.00117 U	0.000622 U	0.000489 U	0.00117 U	0.000451 U	0.00151 U	**0.420**	0.000736 U	0.00109 U	0.000855 U	0.000888 U	0.000575 U
	B6D6-40	02/20/19	PES	Pace	40	2.9	S	0.00128 U	0.000677 U	0.000531 U	0.00128 U	0.000490 U	0.00164 U	**0.0713**	0.000801 U	0.00118 U	0.000931 U	0.000966 U	0.000626 U
	B6D6-45	02/20/19	PES	Pace	45	-2.1	S	0.00239 U	0.00127 U	0.000994 U	0.00239 U	0.000917 U	0.00307 U	**1.82**	0.00150 U	0.00221 U	0.00175 U	0.00181 U	0.00117 U
	B6D6-50	02/20/19	PES	Pace	50	-7.1	S	0.00116 U	0.000613 U	0.000482 U	0.00116 U	0.000444 U	0.00149 U	**0.00754**	0.000726 U	0.00107 U	0.000844 U	0.000876 U	0.000567 U
	B-933-50	02/20/19	PES	Pace	50 (dup)	-7.1	S	0.00119 U	0.000630 U	0.000495 U	0.00119 U	0.000457 U	0.00153 U	**0.552**	0.000746 U	0.00110 U	0.000867 U	0.000900 U	0.000583 U
PRB-B10/PRB-D10	B10D10-15	02/21/19	PES	Pace	15	30.1	S	0.00136 U	0.000722 U	0.000567 U	0.00136 U	0.000523 U	0.00175 U	**0.00105 J**	0.000855 U	0.00126 U	0.000994 U	0.00103 U	**0.00170 J**
	B10D10-20	02/21/19	PES	Pace	20	25.1	S	0.00130 U	0.000692 U	0.000544 U	0.00130 U	0.000501 U	0.00168 U	**0.339**	0.000819 U	0.00121 U	0.000952 U	0.000988 U	0.000640 U
	B10D10-25	02/21/19	PES	Pace	25	20.1	S	0.00122 U	0.000647 U	0.000509 U	0.00122 U	0.000469 U	0.00157 U	**0.196**	0.000766 U	0.00113 U	0.000890 U	0.000924 U	0.000599 U
	B10D10-30	02/21/19	PES	Pace	30	15.1	S	0.00121 U	0.000643 U	0.000505 U	0.00121 U	0.000466 U	0.00156 U	**0.409**	0.000761 U	0.00112 U	0.000885 U	0.000919 U	0.000595 U
	B10D10-35	02/21/19	PES	Pace	35	10.1	S	0.00119 U	0.000629 U	0.000494 U	0.00119 U	0.000456 U	0.00153 U	**0.995**	0.000744 U	0.00110 U	0.000865 U	0.000898 U	0.000582 U
	B10D10-40	02/21/19	PES	Pace	40	5.1	S	0.00123 U	0.000654 U	0.000514 U	0.00123 U	0.000474 U	0.00159 U	**0.694**	0.000774 U	0.00114 U	0.000900 U	0.000934 U	0.000605 U
	B10D10-45	02/21/19	PES	Pace	45	0.1	S	0.0189 U	0.0100 U	0.00788 U	0.0189 U	0.00727 U	0.0243 U	**0.209**	0.0119 U	0.0175 U	0.0138 U	0.0143 U	0.00929 U
	B10D10-50	02/21/19	PES	Pace	50	-4.9	S	0.00120 U	0.000635 U	0.000498 U	0.00120 U	0.000460 U	0.00154 U	**0.564**	0.000751 U	0.00111 U	0.000873 U	0.000906 U	0.000587 U

Table G-2

Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
PRB-B11/PRB-D11	B11D11-10	01/15/19	PES	Pace	10	35.1	V	0.00146 U	0.000772 U	0.000607 U	0.00146 U	0.000559 U	0.00188 U	0.000921 U	0.000913 U	0.00135 U	0.00106 U	0.00109 U	**0.000783 J**
	B11D11-15	01/15/19	PES	Pace	15	30.1	S	0.00118 U	0.000624 U	0.000490 U	0.00118 U	0.000452 U	0.00151 U	**0.00436**	0.000738 U	0.00109 U	0.000858 U	0.000891 U	0.000577 U
	B11D11-20	01/15/19	PES	Pace	20	25.1	S	0.00124 U	0.000658 U	0.000517 U	0.00124 U	0.000476 U	0.00160 U	**0.0158**	0.000778 U	0.00115 U	0.000905 U	0.000939 U	0.000608 U
	B11D11-27	01/15/19	PES	Pace	27	18.1	S	0.00118 U	0.000629 U	0.000494 U	0.00118 U	0.000455 U	0.00152 U	**0.0292**	0.000744 U	0.00110 U	0.000865 U	0.000897 U	0.000581 U
	B11D11-30	01/15/19	PES	Pace	30	15.1	S	0.00112 U	0.000595 U	0.000467 U	0.00112 U	**0.000542 J**	0.00144 U	**0.0698**	0.000704 U	0.00104 U	0.000818 U	0.000849 U	0.000550 U
	B11D11-35	01/15/19	PES	Pace	35	10.1	S	0.00121 U	0.000641 U	0.000503 U	0.00121 U	**0.000511 J**	0.00155 U	**0.574**	0.000758 U	0.00112 U	0.000881 U	0.000915 U	0.000593 U
	B11D11-40	01/15/19	PES	Pace	40	5.1	S	0.00118 U	0.000625 U	0.000491 U	0.00118 U	**0.000549 J**	0.00152 U	**0.275**	0.000740 U	0.00109 U	0.000860 U	0.000893 U	0.000578 U
	B11D11-46	01/15/19	PES	Pace	46	-0.9	S	0.00122 U	0.000646 U	0.000507 U	0.00122 U	**0.000559 J**	0.00157 U	**0.105**	0.000764 U	0.00113 U	0.000888 U	0.000922 U	0.000597 U
	B-928-46	01/15/19	PES	Pace	46 (dup)	-0.9	S	0.00121 U	0.000645 U	0.000506 U	0.00121 U	**0.000594 J**	0.00156 U	**0.130**	0.000763 U	0.00112 U	0.000886 U	0.000920 U	0.000596 U
	B11D11-50	01/15/19	PES	Pace	50	-4.9	S	0.00144 U	0.000764 U	0.000600 U	0.00144 U	**0.000766 J**	0.00186 U	**0.0512**	0.000904 U	0.00133 U	0.00105 U	0.00109 U	0.000707 U
PRB-B13/PRB-D13	B13D13-10	03/21/19	PES	Pace	10	37.5	V	0.00123 U	0.000653 U	0.000513 U	0.00123 U	0.000473 U	0.00159 U	0.000787 U	0.000773 U	0.00114 U	0.000899 U	0.000933 U	0.000604 U
	B13D13-20	03/21/19	PES	Pace	20	27.5	S	0.00128 U	0.000679 U	0.000533 U	0.00128 U	0.000492 U	0.00165 U	0.000817 U	0.000803 U	0.00118 U	0.000933 U	0.000969 U	0.000628 U
	B13D13-30	03/21/19	PES	Pace	30	17.5	S	0.00124 U	0.000658 U	0.000517 U	0.00124 U	0.000477 U	0.00160 U	**0.0169**	0.000779 U	0.00115 U	0.000905 U	0.000940 U	0.000609 U
	B13D13-40	03/21/19	PES	Pace	40	7.5	S	0.00115 U	0.000611 U	0.000480 U	0.00115 U	0.000443 U	0.00148 U	**0.00174 J**	0.000723 U	0.00107 U	0.000841 U	0.000873 U	0.000566 U
	B13D13-50	03/21/19	PES	Pace	50	-2.5	S	0.00119 U	0.000629 U	0.000494 U	0.00119 U	0.000456 U	0.00153 U	0.000758 U	0.000745 U	0.00110 U	0.000866 U	0.000899 U	0.000582 U
PRB-B16/PRB-D16	B16D16-15	03/13/19	PES	Pace	15	34.5	S	0.00507 U	0.00269 U	0.00211 U	0.00507 U	0.00195 U	0.00653 U	0.00324 U	0.00318 U	0.00470 U	0.00370 U	0.00384 U	0.00249 U
	B16D16-20	03/13/19	PES	Pace	20	29.5	S	0.00118 U	0.000627 U	0.000492 U	0.00118 U	0.000454 U	0.00152 U	0.000755 U	0.000742 U	0.00109 U	0.000862 U	0.000895 U	0.000580 U
	B16D16-25	03/13/19	PES	Pace	25	24.5	S	0.00116 U	0.000614 U	0.000482 U	0.00116 U	0.000444 U	0.00149 U	**0.00264 J**	0.000726 U	0.00107 U	0.000844 U	0.000876 U	**0.000665 J**
	B16D16-30	03/13/19	PES	Pace	30	19.5	S	0.00119 U	0.000630 U	0.000495 U	0.00119 U	0.000456 U	0.00153 U	**0.00446**	0.000745 U	0.00110 U	0.000866 U	0.000899 U	0.000582 U
	B16D16-35	03/13/19	PES	Pace	35	14.5	S	0.00119 U	0.000630 U	0.000495 U	0.00119 U	0.000456 U	0.00153 U	**0.713**	0.000745 U	0.00110 U	0.000866 U	0.000899 U	0.000583 U
	B16D16-40	03/13/19	PES	Pace	40	9.5	S	0.00126 U	0.000668 U	0.000525 U	0.00126 U	0.000484 U	0.00162 U	**2.31**	0.000790 U	0.00117 U	0.000919 U	0.000954 U	0.000618 U
	B16D16-45	03/13/19	PES	Pace	45	4.5	S	0.00115 U	0.000612 U	0.000481 U	0.00115 U	0.000444 U	0.00149 U	**0.665**	0.000725 U	0.00107 U	0.000842 U	0.000874 U	0.000567 U
	B16D16-50	03/13/19	PES	Pace	50	-0.5	S	0.00118 U	0.000623 U	0.000490 U	0.00118 U	0.000452 U	0.00151 U	**1.23**	0.000738 U	0.00109 U	0.000857 U	0.000890 U	**0.00109 J**
	B16D16-55	03/13/19	PES	Pace	55	-5.5	S	0.00531 U	0.00282 U	0.00221 U	0.00531 U	0.00204 U	0.00682 U	0.00338 U	0.00333 U	0.00491 U	0.00386 U	0.00401 U	0.00260 U
	B16D16-60	03/13/19	PES	Pace	60	-10.5	S	0.00115 U	0.000610 U	0.000479 U	0.00115 U	0.000442 U	0.00148 U	**0.000940 J**	0.000721 U	0.00106 U	0.000839 U	0.000870 U	0.000564 U
	B16D16-65	03/13/19	PES	Pace	65	-15.5	S	0.00118 U	0.000627 U	0.000492 U	0.00118 U	0.000454 U	0.00152 U	0.000755 U	0.000742 U	0.00109 U	0.000862 U	0.000895 U	0.000580 U
	B16D16-70	03/13/19	PES	Pace	70	-20.5	S	0.00121 U	0.000642 U	0.000504 U	0.00121 U	0.000465 U	0.00156 U	0.000773 U	0.000760 U	0.00112 U	0.000883 U	0.000917 U	0.000594 U
	B16D16-75	03/13/19	PES	Pace	75	-25.5	S	0.00119 U	0.000629 U	0.000494 U	0.00119 U	0.000456 U	0.00153 U	0.000758 U	0.000744 U	0.00110 U	0.000865 U	0.000898 U	0.000582 U
	B16D16-80	03/13/19	PES	Pace	80	-30.5	S	0.00120 U	0.000639 U	0.000502 U	0.00120 U	0.000463 U	0.00155 U	0.000770 U	0.000756 U	0.00112 U	0.000879 U	0.000913 U	0.000591 U
	B16D16-85	03/13/19	PES	Pace	85	-35.5	S	0.00120 U	0.000636 U	0.000499 U	0.00120 U	**0.000618 J**	0.00154 U	0.000765 U	0.000752 U	0.00111 U	0.000874 U	0.000907 U	0.000588 U
	B16D16-90	03/13/19	PES	Pace	90	-40.5	S	0.00122 U	0.000647 U	0.000508 U	0.00122 U	0.000469 U	0.00157 U	0.000779 U	0.000766 U	0.00113 U	0.000890 U	0.000924 U	0.000599 U
	B16D16-95	03/13/19	PES	Pace	95	-45.5	S	0.00126 U	0.000667 U	0.000524 U	0.00126 U	0.000483 U	0.00162 U	0.000804 U	0.000790 U	0.00116 U	0.000918 U	0.000953 U	0.000617 U
	B16D16-100	03/13/19	PES	Pace	100	-50.5	S	0.00125 U	0.000664 U	0.000521 U	0.00125 U	0.000481 U	0.00161 U	0.000799 U	0.000786 U	0.00116 U	0.000913 U	0.000948 U	0.000614 U
	B16D16-105	03/13/19	PES	Pace	105	-55.5	S	0.00123 U	0.000653 U	0.000513 U	0.00123 U	0.000473 U	0.00158 U	0.000787 U	0.000773 U	0.00114 U	0.000898 U	0.000932 U	0.000604 U
	B-934-105	03/13/19	PES	Pace	105 (dup)	-55.5	S	0.00123 U	0.000654 U	0.000514 U	0.00123 U	0.000474 U	0.00159 U	0.000787 U	0.000774 U	0.00114 U	0.000899 U	0.000933 U	0.000605 U

Table G-2

Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
PRB-B18/PRB-D18	B18D18-10	03/22/19	PES	Pace	10	41.0	V	0.00126 U	0.000669 U	0.000525 U	0.00126 U	0.000484 U	0.00162 U	0.000805 U	0.000791 U	0.00117 U	0.000919 U	0.000954 U	0.000618 U
	B18D18-20	03/22/19	PES	Pace	20	31.0	S	0.00120 U	0.000637 U	0.000500 U	0.00120 U	0.000461 U	0.00155 U	**0.0319**	0.000754 U	0.00111 U	0.000876 U	0.000910 U	0.000589 U
	B18D18-30	03/22/19	PES	Pace	30	21.0	S	0.00119 U	0.000631 U	0.000496 U	0.00119 U	0.000457 U	0.00153 U	**0.712**	0.000747 U	0.00110 U	0.000868 U	0.000901 U	0.000584 U
	B18D18-40	03/22/19	PES	Pace	40	11.0	S	0.00119 U	0.000632 U	0.000497 U	0.00119 U	0.000458 U	0.00153 U	**0.0174**	0.000748 U	0.00110 U	0.000869 U	0.000903 U	0.000585 U
	B18D18-50	03/22/19	PES	Pace	50	1.0	S	0.00117 U	0.000621 U	0.000488 U	0.00117 U	0.000450 U	0.00151 U	**0.0255**	0.000735 U	0.00108 U	0.000854 U	0.000887 U	0.000574 U
PRB-B19/PRB-D19	B19D19-10	03/18/19	PES	Pace	10	42.5	V	0.00119 U	0.000632 U	0.000496 U	0.00119 U	0.000457 U	0.00153 U	0.000760 U	0.000747 U	0.00110 U	0.000869 U	0.000902 U	0.000584 U
	B19D19-15	03/18/19	PES	Pace	15	37.5	V	0.00133 U	0.000706 U	0.000555 U	0.00133 U	0.000512 U	0.00171 U	**0.0310 J**	0.000837 U	0.00123 U	0.000972 U	0.00101 U	0.000654 U
	B19D19-20	03/18/19	PES	Pace	20	32.5	S	0.00126 U	0.000669 U	0.000525 U	0.00126 U	0.000484 U	0.00162 U	**0.00927 J**	0.000791 U	0.00117 U	0.000920 U	0.000955 U	0.000619 U
	B19D19-25	03/18/19	PES	Pace	25	27.5	S	0.00134 U	0.000711 U	0.000558 U	0.00134 U	0.000514 U	0.00172 U	**0.0500 J**	0.000840 U	0.00124 U	0.000977 U	0.00101 U	0.000657 U
	B19D19-30	03/18/19	PES	Pace	30	22.5	S	0.00124 U	0.000659 U	0.000517 U	0.00124 U	0.000477 U	0.00160 U	**0.0551 J**	0.000779 U	0.00115 U	0.000906 U	0.000940 U	0.000609 U
	B19D19-35	03/18/19	PES	Pace	35	17.5	S	0.00122 U	0.000650 U	0.000510 U	0.00122 U	0.000471 U	0.00158 U	**0.324 J**	0.000769 U	0.00113 U	0.000893 U	0.000927 U	0.000601 U
	B19D19-40	03/18/19	PES	Pace	40	12.5	S	0.00126 U	0.000667 U	0.000524 U	0.00126 U	0.000483 U	0.00162 U	**0.0658 J**	0.000790 U	0.00116 U	0.000918 U	0.000953 U	**0.000808 J**
	B19D19-45	03/18/19	PES	Pace	45	7.5	S	0.00125 U	0.000664 U	0.000521 U	0.00125 U	0.000481 U	0.00160 U	**0.126 J**	0.000785 U	0.00116 U	0.000913 U	0.000948 U	0.000614 U
	B19D19-50	03/18/19	PES	Pace	50	2.5	S	0.00124 U	0.000657 U	0.000516 U	0.00124 U	0.000476 U	0.00159 U	0.000791 U	0.000777 U	0.00115 U	0.000904 U	0.000938 U	0.000608 U
	B19D19-55	03/18/19	PES	Pace	55	-2.5	S	0.00124 U	0.000660 U	0.000519 U	0.00124 U	0.000478 U	0.00160 U	0.000795 U	0.000781 U	0.00115 U	0.000908 U	0.000943 U	0.000611 UJ
	B19D19-60	03/18/19	PES	Pace	60	-7.5	S	0.00121 U	0.000642 U	0.000504 U	0.00121 U	0.000465 U	0.00156 U	0.000773 U	0.000760 U	0.00112 U	0.000883 U	0.000916 U	**0.000613 J**
	B19D19-65	03/18/19	PES	Pace	65	-12.5	S	0.00138 U	0.000727 U	0.000572 U	0.00138 U	0.000527 U	0.00177 U	0.000875 U	0.000860 U	0.00127 U	0.00100 U	0.00104 U	0.000672 UJ
	B19D19-70	03/18/19	PES	Pace	70	-17.5	S	0.00132 U	0.000699 U	0.000549 U	0.00132 U	0.000507 U	0.00170 U	0.000842 U	0.000828 U	0.00122 U	0.000962 U	0.000998 U	0.000647 U
	B19D19-75	03/18/19	PES	Pace	75	-22.5	S	0.00128 U	0.000681 U	0.000534 U	0.00128 U	0.000493 U	0.00165 U	0.000820 U	0.000806 U	0.00119 U	0.000937 U	0.000972 U	0.000630 U
	B19D19-80	03/18/19	PES	Pace	80	-27.5	S	0.00122 U	0.000649 U	0.000510 U	0.00122 U	0.000470 U	0.00157 U	0.000782 U	0.000768 U	0.00113 U	0.000893 U	0.000926 U	0.000600 U
	B19D19-85	03/18/19	PES	Pace	85	-32.5	S	0.00131 U	0.000696 U	0.000546 U	0.00131 U	0.000504 U	0.00169 U	0.000838 U	0.000823 U	0.00121 U	0.000957 U	0.000993 U	0.000644 U
	B19D19-90	03/18/19	PES	Pace	90	-37.5	S	0.00136 U	0.000721 U	0.000567 U	0.00136 U	0.000522 U	0.00175 U	0.000868 U	0.000853 U	0.00126 U	0.000992 U	0.00103 U	0.000667 U
	B19D19-95	03/18/19	PES	Pace	95	-42.5	S	0.00129 U	0.000687 U	0.000539 U	0.00129 U	0.000497 U	0.00167 U	0.000827 U	0.000813 U	0.00120 U	0.000945 U	0.000981 U	0.000635 U
	B19D19-100	03/18/19	PES	Pace	100	-47.5	S	0.00131 U	0.000698 U	0.000547 U	0.00131 U	0.000505 U	0.00169 U	0.000840 U	0.000826 U	0.00122 U	0.000960 U	0.000996 U	0.000645 U
	B19D19-105	03/18/19	PES	Pace	105	-52.5	S	0.00120 U	0.000639 U	0.000502 U	0.00120 U	0.000463 U	0.00155 U	0.000770 U	0.000756 U	0.00112 U	0.000879 U	0.000912 U	0.000591 U
	B19D19-110	03/18/19	PES	Pace	110	-57.5	S	0.00136 U	0.000721 U	0.000567 U	0.00136 U	0.000522 U	0.00175 U	0.000869 U	0.000854 U	0.00126 U	0.000992 U	0.00103 U	0.000667 U
	B-935-40	03/18/19	PES	Pace	110 (dup)	-57.5	S	0.00145 U	0.000768 U	0.000603 U	0.00145 U	0.000556 U	0.00187 U	0.000926 UJ	0.000910 U	0.00134 U	0.00106 U	0.00110 U	0.000712 U

Table G-2

Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
PRB-B21/PRB-D21	B21D21-10	03/25/19	PES	Pace	10	44.0	V	0.00123 U	0.000657 U	0.000516 U	0.00123 U	0.000476 U	0.00159 U	0.000791 U	0.000778 U	0.00115 U	0.000903 U	0.000938 U	0.000608 U
	B21D21-20	03/25/19	PES	Pace	20	34.0	S	0.00128 U	0.000678 U	0.000532 U	0.00128 U	0.000491 U	0.00164 U	0.000816 U	0.000802 U	0.00118 U	0.000932 U	0.000967 U	0.000627 U
	B21D21-30	03/25/19	PES	Pace	30	24.0	S	0.00116 U	0.000618 U	0.000485 U	0.00116 U	0.000447 U	0.00150 U	**0.0215**	0.000731 U	0.00108 U	0.000850 U	0.000882 U	0.000571 U
	B21D21-40	03/25/19	PES	Pace	40	14.0	S	0.00120 U	0.000635 U	0.000499 U	0.00120 U	0.000460 U	0.00154 U	0.000765 U	0.000751 U	0.00111 U	0.000873 U	0.000906 U	0.000587 U
	B21D21-50	03/25/19	PES	Pace	50	4.0	S	0.00122 U	0.000649 U	0.000510 U	0.00122 U	0.000470 U	0.00157 U	**0.307**	0.000768 U	0.00113 U	0.000893 U	0.000927 U	0.000600 U
	B21D21-60	03/26/19	PES	Pace	60	-6.0	S	0.00118 U	0.000625 U	0.000491 U	0.00118 U	0.000453 U	0.00152 U	**0.0961 J**	0.000740 U	0.00109 U	0.000860 U	0.000893 U	0.000578 U
	B-936-60	03/26/19	PES	Pace	60 (dup)	-6.0	S	0.00118 U	0.000627 U	0.000493 U	0.00118 U	0.000454 U	0.00152 U	**0.180 J**	0.000742 U	0.00109 U	0.000863 U	0.000895 U	0.000580 U
All Data	Number of Analytes Measured							126	128	127	125	128	126	128	128	126	128	128	128
	Number of Analytes Detected							0	0	0	0	7	0	84	0	0	0	0	18
	Frequency of Detection							0.0%	0.0%	0.0%	0.0%	5.5%	0.0%	65.6%	0.0%	0.0%	0.0%	0.0%	14.1%
	Maximum Detection							–	–	–	–	0.000766 J	–	2.31	–	–	–	–	0.024
	Minimum Detection							0.00112 U	0.000595 U	0.000467 U	0.00112 U	0.000433 U	0.00144 U	0.000736 U	0.000704 U	0.00104 U	0.000818 U	0.000849 U	0.00055 U
	Number Of Vadose (V) Detections above SL							0	0	0	–	0	–	0	0	0	0	0	0
	Number of Saturated (S) Detections above SL							0	0	0	–	0	–	70	0	0	0	0	0
2017-2021	Number of Analytes Measured							126	128	127	125	128	126	128	128	126	128	128	128
	Number of Analytes Detected							0	0	0	0	7	0	84	0	0	0	0	18
	Frequency of Detection							0.0%	0.0%	0.0%	0.0%	5.5%	0.0%	65.6%	0.0%	0.0%	0.0%	0.0%	14.1%
	Maximum Detection							–	–	–	–	0.000766 J	–	2.31	–	–	–	–	0.024
	Minimum Detection							0.00112 U	0.000595 U	0.000467 U	0.00112 U	0.000433 U	0.00144 U	0.000736 U	0.000704 U	0.00104 U	0.000818 U	0.000849 U	0.00055 U
	Number Of Vadose (V) Detections above SL							0	0	0	–	0	–	0	0	0	0	0	0
	Number of Saturated (S) Detections above SL							0	0	0	–	0	–	70	0	0	0	0	0

Notes and Abbreviations:
Soil between elevations +10 to 55 feet was treated.
Petroleum Hydrocarbons (PHCs) analyzed by Ecology Method NWTPH-Gx.
VOCs analyzed by EPA Method 8260C or D.
PCUL = Preliminary Cleanup Level from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021. PCULs based on the practical quantitation limits (PQLs) italicized. Detected results shown in bold.
Detections above the screening level in the vadose zone are shown in **bold and highlighted blue**.
Detections above the screening level in the saturated zone are shown in **bold and highlighted gray.**
– = Not available or results not analyzed.
J = The reported concentration is an estimate based on detectable results between the method detection limit and reporting limit, laboratory QA/QC, or data validation review.
J+ = The result is an estimated quantity, but the result may be biased high.
J- = The result is an estimated quantity, but the result may be biased low.
U = Not detected at a concentration exceeding laboratory reporting limit
z = Gasoline/petroleum detection result is likely elevated due to high detections of CVOCs.
bgs = below ground surface
dup = duplicate
Pace = Pace Analytical of Mt. Juliet, Tennessee (formerly ESC)
PES = PES Environmental, Inc.

Table G-2

Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	–	–	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	–	–	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
PRB-A3/PRB-C3	A3C3-3	01/16/19	PES	Pace	3	39.7	V	0.0135 U	**0.00684**	0.00645 U	0.000373 U	0.000920 U	0.0107 U	0.000315 U	0.00708 U	0.00333 U	0.00409 U	0.00126 U	0.00270 U
	A3C3-6	01/16/19	PES	Pace	6	36.7	V	0.0146 U	**0.116**	0.00694 U	0.000401 U	0.000990 U	0.0115 U	0.000338 U	0.00762 U	0.00358 U	0.00441 U	0.00135 U	0.00290 U
	A3C3-8	01/16/19	PES	Pace	8	34.7	V	0.0254 U	**0.269**	0.0121 U	0.000700 U	0.00173 U	0.0200 U	0.000591 U	0.0133 U	0.00624 U	0.00769 U	0.00236 U	0.00506 U
	A3C3-10	02/13/19	PES	Pace	10	32.7	S	0.0172 U	**0.0604**	0.00822 U	0.000475 U	0.00117 U	0.0136 U	0.000401 U	0.00902 U	**0.00766 J**	0.00522 U	0.00160 U	0.00344 U
	A3C3-15	02/13/19	PES	Pace	15	27.7	S	0.0147 U	**0.0771**	0.00699 U	0.000405 U	**0.00145 J**	0.0116 U	0.000341 U	0.00767 U	**0.0108 J**	0.00444 U	0.00136 U	0.00292 U
	A3C3-20	02/13/19	PES	Pace	20	22.7	S	0.0145 U	0.00121 U	0.00692 U	0.000400 U	0.000987 U	0.0114 U	0.000338 U	0.00760 U	0.00357 U	0.00439 U	0.00135 U	0.00289 U
	A3C3-25	02/13/19	PES	Pace	25	17.7	S	0.0152 U	0.00126 U	0.00722 U	0.000418 U	0.00103 U	0.0119 U	0.000352 U	0.00792 U	0.00372 U	0.00458 U	0.00141 U	0.00302 U
	A3C3-32	02/13/19	PES	Pace	32	10.7	S	0.0146 U	0.00122 U	0.00697 U	0.000403 U	0.000994 U	0.0115 U	0.000340 U	0.00765 U	0.00359 U	0.00442 U	0.00136 U	0.00292 U
	A3C3-35	02/13/19	PES	Pace	35	7.7	S	0.0143 U	0.00120 U	0.00684 U	0.000395 U	0.000975 U	0.0113 U	0.000333 U	0.00750 U	0.00352 U	0.00434 U	0.00133 U	0.00286 U
	A3C3-40	02/13/19	PES	Pace	40	2.7	S	0.0156 U	0.00130 U	0.00745 U	0.000431 U	0.00106 U	0.0123 U	0.000363 U	0.00817 U	0.00384 U	0.00473 U	0.00145 U	0.00311 U
	A3C3-45	02/13/19	PES	Pace	45	-2.3	S	0.0144 U	0.00120 U	0.00687 U	0.000397 U	0.000979 U	0.0113 U	0.000335 U	0.00754 U	0.00354 U	0.00436 U	0.00134 U	0.00287 U
	A3C3-50	02/13/19	PES	Pace	50	-7.3	S	0.0150 U	0.00125 U	0.00714 U	0.000413 U	0.00102 U	0.0118 U	0.000348 U	0.00783 U	0.00368 U	0.00453 U	0.00139 U	0.00298 U
PRB-A9/PRB-C9	A9C9-3	01/21/19	PES	Pace	3	40.1	V	0.0214 U	**0.0699**	0.0102 U	0.000591 U	0.00146 U	0.0169 U	0.000498 U	0.0112 U	0.00527 U	0.00648 U	0.00199 U	0.00426 U
	A9C9-6	01/21/19	PES	Pace	6	37.1	V	0.0156 U	**0.00687**	0.00741 U	0.000429 U	0.00106 U	0.0123 U	0.000361 U	0.00813 U	0.00382 U	0.00470 U	0.00145 U	0.00310 U
	A9C9-10	01/21/19	PES	Pace	10	33.1	S	0.0147 U	**0.00318 J**	0.00699 U	0.000404 U	0.000997 U	0.0116 U	0.000341 U	0.00767 U	0.00361 U	0.00444 U	0.00136 U	0.00292 U
	A9C9-15	02/07/19	PES	Pace	15	28.1	S	0.0148 U	0.00124 U	0.00706 U	0.000408 U	0.00101 U	0.0117 U	0.000344 U	0.00775 U	0.00364 U	0.00448 U	0.00138 U	0.00295 U
	A9C9-20	02/07/19	PES	Pace	20	23.1	S	0.0146 U	**0.00374 J**	0.00695 U	0.000402 U	0.000992 U	0.0115 U	0.000339 U	0.00763 U	0.00359 U	0.00441 U	0.00136 U	0.00291 U
	A9C9-25	02/07/19	PES	Pace	25	18.1	S	0.0137 U	0.00114 U	0.00651 U	0.000377 U	0.000929 U	0.0108 U	0.000317 U	0.00715 U	0.00336 U	0.00413 U	0.00127 U	0.00272 U
	A9C9-32	02/07/19	PES	Pace	32	11.1	S	0.0136 U	**0.00516 J**	0.00646 U	0.000374 U	0.000922 U	0.0107 U	0.000315 U	0.00709 U	0.00333 U	0.00410 U	0.00126 U	0.00270 U
	A9C9-35	02/07/19	PES	Pace	35	8.1	S	0.0134 U	**0.00317 J**	0.00640 U	0.000370 U	0.000913 U	0.0106 U	0.000312 U	0.00703 U	0.00330 U	0.00406 U	0.00125 U	0.00268 U
	A9C9-40	02/07/19	PES	Pace	40	3.1	S	0.0136 U	0.00114 U	0.00649 U	0.000375 U	0.000926 U	0.0107 U	0.000316 U	0.00712 U	0.00335 U	0.00412 U	0.00127 U	0.00271 U
	A9C9-45	02/07/19	PES	Pace	45	-1.9	S	0.0133 U	0.00111 U	0.00633 U	0.000366 U	0.000903 U	0.0105 U	**0.000435 J**	0.00695 U	0.00326 U	0.00402 U	0.00123 U	0.00265 U
	A9C9-50	02/07/19	PES	Pace	50	-6.9	S	0.0137 U	0.00114 U	0.00650 U	0.000376 U	0.000928 U	0.0108 U	**0.000357 J**	0.00714 U	0.00335 U	0.00413 U	0.00127 U	0.00272 U
	B-931-50	02/07/19	PES	Pace	50 (dup)	-6.9	S	0.0137 U	**0.00505 J**	0.00651 U	0.000377 U	0.000929 U	0.0108 U	0.000318 U	0.00715 U	0.00336 U	0.00413 U	0.00127 U	0.00272 U
PRB-B1/PRB-D1	B1D1-11	01/17/19	PES	Pace	11	30.8	S	0.0148 U	**0.0136**	0.00707 U	0.000409 U	0.00101 U	0.0117 U	0.000345 U	0.00776 U	0.00365 U	0.00449 U	**0.00188 J**	0.00296 U
	B1D1-15	01/17/19	PES	Pace	15	26.8	S	0.0194 U	**0.00264 J**	0.00925 U	0.000535 U	0.00132 U	0.0153 U	0.000451 U	0.0102 U	0.00477 U	0.00587 U	0.00180 U	0.00387 U
	B1D1-20	01/17/19	PES	Pace	20	21.8	S	0.0156 U	**0.00443 J**	0.00743 U	0.000430 U	0.00106 U	0.0123 U	0.000362 U	**0.0104 J**	0.00383 U	0.00471 U	0.00145 U	0.00311 U
	B1D1-25	01/17/19	PES	Pace	25	16.8	S	0.0177 U	**0.00361 J**	0.00841 U	0.000487 U	0.00120 U	0.0139 U	0.000410 U	0.00923 U	0.00434 U	0.00534 U	0.00164 U	0.00352 U
	B1D1-31	01/17/19	PES	Pace	31	10.8	S	0.0138 U	0.00115 U	0.00658 U	0.000381 U	0.000939 U	0.0109 U	0.000321 U	0.00723 U	0.00340 U	0.00418 U	0.00128 U	0.00275 U
	B1D1-35	01/17/19	PES	Pace	35	6.8	S	0.0156 U	**0.00186 J**	0.00741 U	0.000429 U	0.00106 U	0.0122 U	0.000361 U	0.00813 U	0.00382 U	0.00470 U	0.00145 U	0.00310 U
	B1D1-40	01/17/19	PES	Pace	40	1.8	S	0.0142 U	**0.00244 J**	0.00676 U	0.000391 U	0.000965 U	0.0112 U	0.000330 U	0.00742 U	0.00349 U	0.00429 U	0.00132 U	0.00283 U
	B1D1-45	01/17/19	PES	Pace	45	-3.3	S	0.0145 U	0.00121 U	0.00692 U	0.000401 U	0.000988 U	0.0114 U	0.000338 U	0.00760 U	0.00357 U	0.00439 U	0.00135 U	0.00290 U
	B1D1-50	01/17/19	PES	Pace	50	-8.3	S	0.0147 U	**0.00283 J**	0.00699 U	0.000404 U	0.000997 U	0.0116 U	0.000341 U	0.00767 U	0.00360 U	0.00444 U	0.00136 U	0.00292 U
PRB-B2/PRB-D2	B2D2-3	01/16/19	PES	Pace	3	38.8	V	0.0138 U	**0.00778**	0.00660 U	0.000382 U	0.000941 U	0.0109 U	0.000322 U	0.00724 U	0.00340 U	0.00419 U	0.00129 U	0.00276 U
	B2D2-6	01/16/19	PES	Pace	6	35.8	V	0.0177 U	**0.0982**	0.00843 U	0.000487 U	**0.00398**	0.0139 U	0.000411 U	0.00925 U	0.00435 U	0.00535 U	0.00164 U	0.00352 U
	B2D2-10	01/21/19	PES	Pace	10	31.8	S	0.0277 U	**1.22**	0.0132 U	0.000759 U	**0.00922**	0.0219 U	0.000645 U	0.0145 U	0.00681 U	0.00839 U	**0.00827 J**	0.00553 U

Table G-2

Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	–	–	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	–	–	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
PRB-B4/PRB-D4	B4D4-3	01/17/19	PES	Pace	3	39.7	V	0.0144 U	**0.00346 J**	0.00684 U	0.000396 U	0.000976 U	0.0113 U	0.000334 U	0.00751 U	0.00353 U	0.00434 U	0.00133 U	0.00286 U
	B4D4-6	01/17/19	PES	Pace	6	36.7	V	0.0200 U	**0.205**	0.00951 U	0.000546 U	0.00136 U	0.0157 U	0.000465 U	0.0104 U	0.00487 U	0.00604 U	0.00185 U	0.00399 U
	B4D4-10	01/17/19	PES	Pace	10	32.7	S	0.0161 U	**0.122**	0.00768 U	0.000444 U	**0.00117 J**	0.0127 U	0.000375 U	0.00843 U	**0.00918 J**	0.00488 U	0.00150 U	0.00321 U
PRB-B5/PRB-D5	B5D5-10	02/14/19	PES	Pace	10	32.9	S	0.0149 U	**0.0115**	0.00709 U	0.000410 U	–	–	0.000346 U	0.00778 U	0.00366 U	0.00450 U	–	–
	B5D5-15	02/14/19	PES	Pace	15	27.9	S	–	0.00123 U	0.00704 U	0.000407 U	0.00100 U	0.0116 U	0.000343 U	0.00773 U	0.00363 U	0.00447 U	0.00137 U	0.00295 U
	B5D5-20	02/14/19	PES	Pace	20	22.9	S	0.0148 U	0.00124 U	0.00707 U	0.000409 U	0.00101 U	0.0117 U	0.000345 U	0.00776 U	0.00364 U	0.00449 U	0.00138 U	0.00296 U
	B5D5-25	02/14/19	PES	Pace	25	17.9	S	0.0150 U	0.00125 U	0.00713 U	0.000412 U	0.00102 U	0.0118 U	0.000348 U	0.00782 U	0.00368 U	0.00452 U	0.00139 U	0.00298 U
	B5D5-32	02/14/19	PES	Pace	32	10.9	S	0.0144 U	0.00120 U	0.00687 U	0.000398 U	0.000980 U	0.0114 U	0.000335 U	0.00754 U	0.00354 U	0.00436 U	0.00134 U	0.00287 U
	B5D5-35	02/14/19	PES	Pace	35	7.9	S	–	–	0.00666 U	–	0.000951 U	–	–	0.00731 U	–	0.00423 U	–	–
	B5D5-40	02/14/19	PES	Pace	40	2.9	S	0.0140 U	0.00117 U	0.00667 U	0.000386 U	0.000952 U	0.0110 U	0.000325 U	0.00732 U	0.00344 U	0.00423 U	0.00130 U	0.00279 U
	B5D5-45	02/14/19	PES	Pace	45	-2.1	S	0.0137 U	0.00114 U	0.00651 U	0.000376 U	0.000928 U	0.0108 U	0.000317 U	0.00714 U	0.00336 U	0.00413 U	0.00127 U	0.00272 U
	B5D5-50	02/14/19	PES	Pace	50	-7.1	S	0.0132 U	0.00111 U	0.00631 U	0.000365 U	0.000900 U	0.0104 U	0.000308 U	0.00692 U	0.00325 U	0.00400 U	0.00123 U	0.00264 U
	B-932-50	02/14/19	PES	Pace	50 (dup)	-7.1	S	0.0135 U	0.00112 U	0.00642 U	0.000371 U	0.000916 U	0.0106 U	0.000313 U	0.00705 U	0.00331 U	0.00407 U	0.00125 U	0.00268 U
PRB-B6/PRB-D6	B6D6-17	02/20/19	PES	Pace	17	25.9	S	0.0146 U	**0.00214 J**	0.00696 U	0.000402 U	0.000992 U	0.0115 U	0.000339 U	0.00763 U	0.00359 U	0.00441 U	0.00136 U	0.00291 U
	B6D6-20	02/20/19	PES	Pace	20	22.9	S	0.0147 U	0.00123 U	0.00703 U	0.000406 U	0.00100 U	0.0116 U	0.000343 U	0.00771 U	0.00362 U	0.00446 U	0.00137 U	0.00294 U
	B6D6-25	02/20/19	PES	Pace	25	17.9	S	0.0151 U	0.00126 U	0.00720 U	0.000417 U	0.00103 U	0.0119 U	0.000351 U	0.00790 U	0.00371 U	0.00457 U	0.00140 U	0.00301 U
	B6D6-32	02/20/19	PES	Pace	32	10.9	S	0.0153 U	**0.00133 J**	0.00729 U	0.000422 U	0.00104 U	0.0120 U	0.000355 U	0.00800 U	0.00376 U	0.00463 U	0.00142 U	0.00305 U
	B6D6-35	02/20/19	PES	Pace	35	7.9	S	0.0138 U	**0.00276 J**	0.00657 U	0.000380 U	0.000937 U	0.0109 U	0.000320 U	0.00721 U	0.00339 U	0.00417 U	0.00128 U	0.00275 U
	B6D6-40	02/20/19	PES	Pace	40	2.9	S	0.0150 U	**0.00213 J**	0.00714 U	0.000413 U	0.00102 U	0.0118 U	0.000348 U	0.00784 U	0.00368 U	0.00453 U	0.00139 U	0.00299 U
	B6D6-45	02/20/19	PES	Pace	45	-2.1	S	0.0281 U	**0.00347 J**	0.0134 U	0.000773 U	0.00191 U	0.0221 U	0.000652 U	0.0147 U	0.00689 U	0.00848 U	0.00261 U	0.00559 U
	B6D6-50	02/20/19	PES	Pace	50	-7.1	S	0.0136 U	**0.00281 J**	0.00648 U	0.000375 U	0.000924 U	0.0107 U	0.000316 U	0.00711 U	0.00334 U	0.00411 U	0.00126 U	0.00271 U
	B-933-50	02/20/19	PES	Pace	50 (dup)	-7.1	S	0.0140 U	**0.00182 J**	0.00666 U	0.000385 U	0.000949 U	0.0110 U	0.000325 U	0.00730 U	0.00343 U	0.00422 U	0.00130 U	0.00278 U
PRB-B10/PRB-D10	B10D10-15	02/21/19	PES	Pace	15	30.1	S	0.0160 U	**0.00404 J**	0.00763 U	0.000441 U	0.00109 U	0.0126 U	0.000372 U	0.00837 U	**0.0173**	0.00484 U	0.00149 U	0.00319 U
	B10D10-20	02/21/19	PES	Pace	20	25.1	S	0.0153 U	**0.00135 J**	0.00731 U	0.000423 U	0.00104 U	0.0121 U	0.000356 U	0.00802 U	0.00377 U	0.00464 U	0.00143 U	0.00306 U
	B10D10-25	02/21/19	PES	Pace	25	20.1	S	0.0144 U	0.00120 U	0.00684 U	0.000396 U	0.000975 U	0.0113 U	0.000333 U	0.00750 U	0.00353 U	0.00434 U	0.00133 U	0.00286 U
	B10D10-30	02/21/19	PES	Pace	30	15.1	S	0.0143 U	**0.00164 J**	0.00679 U	0.000393 U	0.000969 U	0.0112 U	0.000331 U	0.00746 U	0.00350 U	0.00431 U	0.00132 U	0.00284 U
	B10D10-35	02/21/19	PES	Pace	35	10.1	S	0.0139 U	0.00116 U	0.00664 U	0.000384 U	0.000947 U	0.0110 U	0.000324 U	0.00729 U	0.00343 U	0.00422 U	0.00130 U	0.00278 U
	B10D10-40	02/21/19	PES	Pace	40	5.1	S	0.0145 U	**0.00199 J**	0.00691 U	0.000400 U	0.000986 U	0.0114 U	0.000337 U	0.00758 U	0.00356 U	0.00439 U	0.00135 U	0.00289 U
	B10D10-45	02/21/19	PES	Pace	45	0.1	S	0.223 U	0.0186 U	0.106 U	0.00613 U	0.0151 U	0.175 U	0.00517 U	0.117 U	0.0546 U	0.0673 U	0.0207 U	0.0443 U
	B10D10-50	02/21/19	PES	Pace	50	-4.9	S	0.0141 U	**0.00142 J**	0.00670 U	0.000388 U	0.000956 U	0.0111 U	0.000327 U	0.00735 U	0.00346 U	0.00425 U	0.00131 U	0.00280 U

Table G-2

Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	–	–	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	–	–	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
PRB-B11/PRB-D11	B11D11-10	01/15/19	PES	Pace	10	35.1	V	0.0171 U	0.00142 U	0.00815 U	0.000467 U	**0.00195 J**	0.0135 U	0.000398 U	0.00894 U	0.00421 U	0.00518 U	0.00159 U	0.00341 U
	B11D11-15	01/15/19	PES	Pace	15	30.1	S	0.0138 U	**0.00130 J**	0.00659 U	0.000381 U	0.000940 U	0.0109 U	0.000321 U	0.00723 U	0.00340 U	0.00418 U	0.00128 U	0.00275 U
	B11D11-20	01/15/19	PES	Pace	20	25.1	S	0.0146 U	0.00122 U	0.00695 U	0.000402 U	0.000991 U	0.0115 U	0.000339 U	0.00762 U	0.00358 U	0.00441 U	0.00135 U	0.00290 U
	B11D11-27	01/15/19	PES	Pace	27	18.1	S	0.0139 U	**0.00343 J**	0.00664 U	0.000384 U	0.000947 U	0.0110 U	0.000324 U	0.00728 U	0.00342 U	0.00421 U	0.00129 U	0.00278 U
	B11D11-30	01/15/19	PES	Pace	30	15.1	S	0.0132 U	**0.00158 J**	0.00628 U	0.000363 U	0.000896 U	0.0104 U	0.000306 U	0.00689 U	0.00324 U	0.00399 U	0.00123 U	0.00263 U
	B11D11-35	01/15/19	PES	Pace	35	10.1	S	0.0142 U	**0.00199 J**	0.00677 U	0.000391 U	0.000965 U	0.0112 U	0.000330 U	0.00743 U	0.00349 U	0.00430 U	0.00132 U	0.00283 U
	B11D11-40	01/15/19	PES	Pace	40	5.1	S	0.0139 U	**0.00137 J**	0.00660 U	0.000382 U	0.000942 U	0.0109 U	0.000322 U	0.00725 U	0.00341 U	0.00419 U	0.00129 U	0.00276 U
	B11D11-46	01/15/19	PES	Pace	46	-0.9	S	0.0143 U	**0.00158 J**	0.00682 U	0.000394 U	0.000973 U	0.0113 U	0.000332 U	0.00748 U	0.00352 U	0.00433 U	0.00133 U	0.00285 U
	B-928-46	01/15/19	PES	Pace	46 (dup)	-0.9	S	0.0143 U	**0.00200 J**	0.00681 U	0.000394 U	0.000971 U	0.0112 U	0.000332 U	0.00747 U	0.00351 U	0.00432 U	0.00133 U	0.00285 U
	B11D11-50	01/15/19	PES	Pace	50	-4.9	S	0.0169 U	**0.00495 J**	0.00806 U	0.000467 U	0.00115 U	0.0133 U	0.000393 U	0.00885 U	0.00416 U	0.00511 U	0.00157 U	0.00338 U
PRB-B13/PRB-D13	B13D13-10	03/21/19	PES	Pace	10	37.5	V	0.0145 U	0.00121 U	0.00690 U	0.000399 U	0.000984 U	0.0114 U	0.000336 U	0.00757 U	0.00356 U	0.00438 U	0.00135 U	0.00289 U
	B13D13-20	03/21/19	PES	Pace	20	27.5	S	0.0150 U	0.00126 U	0.00717 U	0.000415 U	0.00102 U	0.0118 U	0.000349 U	0.00787 U	0.00370 U	0.00455 U	0.00140 U	0.00300 U
	B13D13-30	03/21/19	PES	Pace	30	17.5	S	0.0146 U	0.00122 U	0.00695 U	0.000402 U	0.000991 U	0.0115 U	0.000339 U	0.00763 U	0.00358 U	0.00441 U	0.00136 U	0.00291 U
	B13D13-40	03/21/19	PES	Pace	40	7.5	S	0.0136 U	0.00113 U	0.00646 U	0.000373 U	0.000921 U	0.0107 U	0.000315 U	0.00708 U	0.00333 U	0.00410 U	0.00126 U	0.00270 U
	B13D13-50	03/21/19	PES	Pace	50	-2.5	S	0.0140 U	0.00116 U	0.00665 U	0.000384 U	0.000948 U	0.0110 U	0.000324 U	0.00729 U	0.00343 U	0.00422 U	0.00130 U	0.00278 U
PRB-B16/PRB-D16	B16D16-15	03/13/19	PES	Pace	15	34.5	S	0.0597 U	0.00498 U	0.0284 U	0.00164 U	0.00405 U	0.0470 U	0.00139 U	0.0312 U	0.0147 U	0.0181 U	0.00554 U	0.0119 U
	B16D16-20	03/13/19	PES	Pace	20	29.5	S	0.0139 U	0.00116 U	0.00662 U	0.000383 U	0.000944 U	0.0109 U	0.000323 U	0.00726 U	0.00341 U	0.00420 U	0.00129 U	0.00277 U
	B16D16-25	03/13/19	PES	Pace	25	24.5	S	0.0136 U	0.00114 U	0.00648 U	0.000375 U	0.000924 U	0.0107 U	0.000316 U	0.00711 U	0.00334 U	0.00411 U	0.00126 U	0.00271 U
	B16D16-30	03/13/19	PES	Pace	30	19.5	S	0.0140 U	0.00116 U	0.00665 U	0.000385 U	0.000948 U	0.0110 U	0.000324 U	0.00730 U	0.00343 U	0.00422 U	0.00130 U	0.00278 U
	B16D16-35	03/13/19	PES	Pace	35	14.5	S	0.0140 U	0.00117 U	0.00665 U	0.000385 U	0.000949 U	0.0110 U	0.000324 U	0.00730 U	0.00343 U	0.00422 U	0.00130 U	0.00278 U
	B16D16-40	03/13/19	PES	Pace	40	9.5	S	0.0148 U	0.00124 U	0.00705 U	0.000408 U	0.00101 U	0.0117 U	0.000344 U	0.00774 U	0.00364 U	0.00448 U	0.00138 U	0.00295 U
	B16D16-45	03/13/19	PES	Pace	45	4.5	S	0.0136 U	0.00113 U	0.00647 U	0.000374 U	0.000922 U	0.0107 U	0.000315 U	0.00710 U	0.00333 U	0.00410 U	0.00126 U	0.00270 U
	B16D16-50	03/13/19	PES	Pace	50	-0.5	S	0.0138 U	0.00115 U	0.00658 U	0.000381 U	0.000939 U	0.0109 U	0.000321 U	0.00722 U	0.00339 U	0.00418 U	0.00128 U	0.00275 U
	B16D16-55	03/13/19	PES	Pace	55	-5.5	S	0.0623 U	0.00521 U	0.0297 U	0.00172 U	0.00424 U	0.0491 U	0.00145 U	0.0326 U	0.0154 U	0.0189 U	0.00580 U	0.0124 U
	B16D16-60	03/13/19	PES	Pace	60	-10.5	S	0.0135 U	0.00113 U	0.00644 U	0.000372 U	0.000918 U	0.0106 U	0.000314 U	0.00707 U	0.00332 U	0.00409 U	0.00126 U	0.00269 U
	B16D16-65	03/13/19	PES	Pace	65	-15.5	S	0.0139 U	0.00116 U	0.00662 U	0.000383 U	0.000944 U	0.0109 U	0.000323 U	0.00727 U	0.00341 U	0.00420 U	0.00129 U	0.00277 U
	B16D16-70	03/13/19	PES	Pace	70	-20.5	S	0.0142 U	0.00119 U	0.00678 U	0.000392 U	0.000967 U	0.0112 U	0.000331 U	0.00744 U	0.00350 U	0.00430 U	0.00132 U	0.00284 U
	B16D16-75	03/13/19	PES	Pace	75	-25.5	S	0.0139 U	0.00116 U	0.00664 U	0.000384 U	0.000947 U	0.0110 U	0.000324 U	0.00729 U	0.00343 U	0.00422 U	0.00130 U	0.00278 U
	B16D16-80	03/13/19	PES	Pace	80	-30.5	S	0.0142 U	0.00118 U	0.00675 U	0.000390 U	0.000963 U	0.0112 U	0.000329 U	0.00741 U	0.00348 U	0.00428 U	0.00132 U	0.00282 U
	B16D16-85	03/13/19	PES	Pace	85	-35.5	S	0.0141 U	0.00118 U	0.00671 U	0.000388 U	0.000957 U	0.0111 U	0.000327 U	0.00737 U	0.00346 U	0.00426 U	0.00131 U	0.00281 U
	B16D16-90	03/13/19	PES	Pace	90	-40.5	S	0.0143 U	0.00120 U	0.00683 U	0.000395 U	0.000975 U	0.0113 U	0.000333 U	0.00750 U	0.00352 U	0.00434 U	0.00133 U	0.00286 U
	B16D16-95	03/13/19	PES	Pace	95	-45.5	S	0.0148 U	0.00123 U	0.00705 U	0.000408 U	0.00100 U	0.0116 U	0.000344 U	0.00773 U	0.00363 U	0.00447 U	0.00137 U	0.00295 U
	B16D16-100	03/13/19	PES	Pace	100	-50.5	S	0.0147 U	0.00123 U	0.00701 U	0.000406 U	0.00100 U	0.0116 U	0.000342 U	0.00769 U	0.00362 U	0.00445 U	0.00137 U	0.00293 U
	B16D16-105	03/13/19	PES	Pace	105	-55.5	S	0.0145 U	0.00121 U	0.00690 U	0.000399 U	0.000984 U	0.0114 U	0.000336 U	0.00757 U	0.00356 U	0.00438 U	0.00135 U	0.00288 U
	B-934-105	03/13/19	PES	Pace	105 (dup)	-55.5	S	0.0145 U	0.00121 U	0.00690 U	0.000399 U	0.000985 U	0.0114 U	0.000337 U	0.00758 U	0.00356 U	0.00438 U	0.00135 U	0.00289 U

Table G-2

Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	–	–	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	–	–	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
PRB-B18/PRB-D18	B18D18-10	03/22/19	PES	Pace	10	41.0	V	0.0148 U	**0.00737**	0.00706 U	0.000408 U	0.00101 U	0.0117 U	0.000344 U	0.00775 U	0.00364 U	0.00448 U	0.00138 U	0.00295 U
	B18D18-20	03/22/19	PES	Pace	20	31.0	S	0.0141 U	**0.00647**	0.00673 U	0.000389 U	0.000960 U	0.0111 U	0.000328 U	0.00738 U	0.00347 U	0.00427 U	0.00131 U	0.00281 U
	B18D18-30	03/22/19	PES	Pace	30	21.0	S	0.0140 U	**0.0142**	0.00666 U	0.000385 U	0.000950 U	0.0110 U	0.000325 U	0.00731 U	0.00344 U	0.00423 U	0.00130 U	0.00279 U
	B18D18-40	03/22/19	PES	Pace	40	11.0	S	0.0140 U	**0.00226 J**	0.00668 U	0.000386 U	0.000952 U	0.0110 U	0.000325 U	0.00733 U	0.00344 U	0.00424 U	0.00130 U	0.00279 U
	B18D18-50	03/22/19	PES	Pace	50	1.0	S	0.0138 U	**0.00357 J**	0.00656 U	0.000379 U	0.000935 U	0.0108 U	0.000320 U	0.00720 U	0.00338 U	0.00416 U	0.00128 U	0.00274 U
PRB-B19/PRB-D19	B19D19-10	03/18/19	PES	Pace	10	42.5	V	0.0140 U	0.00117 U	0.00667 U	0.000386 U	0.000951 U	0.0110 U	0.000325 U	0.00732 U	0.00344 U	0.00423 U	0.00130 U	0.00279 U
	B19D19-15	03/18/19	PES	Pace	15	37.5	V	0.0157 U	0.00130 U	0.00746 U	0.000432 U	0.00106 U	0.0123 U	0.000364 U	0.00819 U	0.00385 U	0.00474 U	0.00145 U	0.00312 U
	B19D19-20	03/18/19	PES	Pace	20	32.5	S	0.0148 U	0.00124 U	0.00706 U	0.000409 U	0.00101 U	0.0117 U	0.000344 U	0.00775 U	0.00364 U	0.00448 U	0.00138 U	0.00295 U
	B19D19-25	03/18/19	PES	Pace	25	27.5	S	0.0157 U	**0.0102**	0.00750 U	0.000434 U	0.00107 U	0.0124 U	0.000366 U	0.00823 U	0.00387 U	0.00476 U	0.00146 U	0.00313 U
	B19D19-30	03/18/19	PES	Pace	30	22.5	S	0.0146 U	**0.0109**	0.00695 U	0.000402 U	0.000992 U	0.0115 U	0.000339 U	0.00763 U	0.00359 U	0.00441 U	0.00136 U	0.00291 U
	B19D19-35	03/18/19	PES	Pace	35	17.5	S	0.0144 U	0.00120 U	0.00686 U	0.000397 U	0.000978 U	0.0113 U	0.000334 U	0.00753 U	0.00354 U	0.00435 U	0.00134 U	0.00287 U
	B19D19-40	03/18/19	PES	Pace	40	12.5	S	0.0148 U	**0.0110**	0.00705 U	0.000408 U	0.00101 U	0.0116 U	0.000344 U	0.00773 U	0.00363 U	0.00447 U	0.00137 U	0.00295 U
	B19D19-45	03/18/19	PES	Pace	45	7.5	S	0.0147 U	0.00123 U	0.00701 U	0.000405 U	0.00100 U	0.0116 U	0.000342 U	0.00769 U	0.00361 U	0.00444 U	0.00137 U	0.00293 U
	B19D19-50	03/18/19	PES	Pace	50	2.5	S	0.0146 U	**0.0138**	0.00694 U	0.000401 U	0.000990 U	0.0115 U	0.000338 U	0.00761 U	0.00358 U	0.00440 U	0.00135 U	0.00290 U
	B19D19-55	03/18/19	PES	Pace	55	-2.5	S	0.0146 U	**0.00653**	0.00697 U	0.000403 U	0.000994 U	0.0115 U	0.000340 U	0.00765 U	0.00360 U	0.00442 U	0.00136 U	0.00292 U
	B19D19-60	03/18/19	PES	Pace	60	-7.5	S	0.0142 U	0.00119 U	0.00678 U	0.000392 U	0.000967 U	0.0112 U	0.000331 U	0.00744 U	0.00350 U	0.00430 U	0.00132 U	0.00283 U
	B19D19-65	03/18/19	PES	Pace	65	-12.5	S	0.0161 U	0.00134 U	0.00767 U	0.000444 U	0.00109 U	0.0127 U	0.000375 U	0.00842 U	0.00396 U	0.00487 U	0.00149 U	0.00321 U
	B19D19-70	03/18/19	PES	Pace	70	-17.5	S	0.0155 U	0.00129 U	0.00738 U	0.000427 U	**0.00188 J**	0.0122 U	0.000360 U	0.00810 U	**0.0177**	0.00469 U	**0.00769**	0.00309 U
	B19D19-75	03/18/19	PES	Pace	75	-22.5	S	0.0151 U	0.00126 U	0.00719 U	0.000417 U	0.00103 U	0.0119 U	0.000351 U	0.00790 U	**0.00535 J**	0.00457 U	**0.00256 J**	0.00301 U
	B19D19-80	03/18/19	PES	Pace	80	-27.5	S	0.0144 U	0.00120 U	0.00685 U	0.000396 U	0.000977 U	0.0113 U	0.000334 U	0.00752 U	0.00353 U	0.00435 U	0.00134 U	0.00287 U
	B19D19-85	03/18/19	PES	Pace	85	-32.5	S	0.0154 U	0.00129 U	0.00735 U	0.000425 U	0.00105 U	0.0121 U	0.000358 U	0.00806 U	0.00379 U	0.00466 U	0.00143 U	0.00307 U
	B19D19-90	03/18/19	PES	Pace	90	-37.5	S	0.0160 U	**0.0160**	0.00761 U	0.000440 U	0.00109 U	0.0126 U	0.000372 U	0.00835 U	0.00393 U	0.00484 U	0.00148 U	0.00319 U
	B19D19-95	03/18/19	PES	Pace	95	-42.5	S	0.0152 U	0.00127 U	0.00725 U	0.000420 U	0.00103 U	0.0120 U	0.000354 U	0.00796 U	0.00374 U	0.00460 U	0.00141 U	0.00303 U
	B19D19-100	03/18/19	PES	Pace	100	-47.5	S	0.0154 U	0.00129 U	0.00737 U	0.000427 U	0.00105 U	0.0122 U	0.000359 U	0.00809 U	0.00380 U	0.00468 U	0.00143 U	0.00309 U
	B19D19-105	03/18/19	PES	Pace	105	-52.5	S	0.0142 U	0.00118 U	0.00675 U	0.000390 U	0.000963 U	0.0112 U	0.000329 U	0.00741 U	0.00348 U	0.00428 U	0.00132 U	0.00282 U
	B19D19-110	03/18/19	PES	Pace	110	-57.5	S	0.0160 U	0.00133 U	0.00762 U	0.000441 U	0.00109 U	0.0126 U	0.000371 U	0.00836 U	**0.00418 J**	0.00483 U	0.00149 U	0.00319 U
	B-935-40	03/18/19	PES	Pace	110 (dup)	-57.5	S	0.0170 U	0.00143 U	0.00811 U	0.000470 U	0.00116 U	0.0134 U	0.000396 U	0.00891 U	0.00419 U	0.00515 U	0.00159 U	0.00340 U

Table G-2

Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	–	–	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	–	–	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
PRB-B21/PRB-D21	B21D21-10	03/25/19	PES	Pace	10	44.0	V	0.0146 U	**0.00150 J**	0.00693 U	0.000401 U	0.000990 U	0.0115 U	0.000339 U	**0.0117 J**	0.00358 U	0.00440 U	0.00135 U	0.00290 U
	B21D21-20	03/25/19	PES	Pace	20	34.0	S	0.0150 U	**0.00134 J**	0.00715 U	0.000414 U	0.00102 U	0.0118 U	0.000349 U	**0.00925 J**	0.00369 U	0.00455 U	0.00139 U	0.00299 U
	B21D21-30	03/25/19	PES	Pace	30	24.0	S	0.0137 U	**0.00496 J**	0.00652 U	0.000377 U	0.000930 U	0.0108 U	0.000318 U	**0.00824 J**	0.00336 U	0.00414 U	0.00127 U	0.00273 U
	B21D21-40	03/25/19	PES	Pace	40	14.0	S	0.0141 U	**0.00370 J**	0.00670 U	0.000388 U	0.000956 U	0.0111 U	0.000327 U	**0.00949 J**	0.00346 U	0.00426 U	0.00131 U	0.00280 U
	B21D21-50	03/25/19	PES	Pace	50	4.0	S	0.0144 U	0.00120 U	0.00685 U	0.000396 U	0.000978 U	0.0113 U	0.000334 U	**0.0106 J**	0.00353 U	0.00435 U	0.00134 U	0.00287 U
	B21D21-60	03/26/19	PES	Pace	60	-6.0	S	0.0139 U	**0.00221 J**	0.00660 U	0.000382 U	0.000942 U	0.0109 U	0.000322 U	**0.00899 J**	0.00341 U	0.00419 U	0.00129 U	0.00276 U
	B-936-60	03/26/19	PES	Pace	60 (dup)	-6.0	S	0.0139 U	**0.00317 J**	0.00662 U	0.000383 U	0.000945 U	0.0109 U	0.000323 U	**0.0112 J**	0.00342 U	0.00420 U	0.00129 U	0.00277 U
All Data	Number of Analytes Measured							126	127	128	127	127	126	127	128	127	128	126	126
	Number of Analytes Detected							0	59	0	0	6	0	2	7	7	0	4	0
	Frequency of Detection							0.0%	46.5%	0.0%	0.0%	4.7%	0.0%	1.6%	5.5%	5.5%	0.0%	3.2%	0.0%
	Maximum Detection							–	1.22	–	–	0.00922	–	0.000435 J	0.0117 J	0.0177	–	0.00827 J	–
	Minimum Detection							0.0132 U	0.00111 U	0.00628 U	0.000363 U	0.000896 U	0.0104 U	0.000306 U	0.00689 U	0.00324 U	0.00399 U	0.00123 U	0.00263 U
	Number Of Vadose (V) Detections above SL							0	0	–	–	0	0	0	0	0	0	0	0
	Number of Saturated (S) Detections above SL							0	0	–	–	0	0	0	0	0	0	0	0
2017-2021	Number of Analytes Measured							126	127	128	127	127	126	127	128	127	128	126	126
	Number of Analytes Detected							0	59	0	0	6	0	2	7	7	0	4	0
	Frequency of Detection							0.0%	46.5%	0.0%	0.0%	4.7%	0.0%	1.6%	5.5%	5.5%	0.0%	3.2%	0.0%
	Maximum Detection							–	1.22	–	–	0.00922	–	0.000435 J	0.0117 J	0.0177	–	0.00827 J	–
	Minimum Detection							0.0132 U	0.00111 U	0.00628 U	0.000363 U	0.000896 U	0.0104 U	0.000306 U	0.00689 U	0.00324 U	0.00399 U	0.00123 U	0.00263 U
	Number Of Vadose (V) Detections above SL							0	0	–	–	0	0	0	0	0	0	0	0
	Number of Saturated (S) Detections above SL							0	0	–	–	0	0	0	0	0	0	0	0

Notes and Abbreviations:
Soil between elevations +10 to 55 feet was treated.
Petroleum Hydrocarbons (PHCs) analyzed by Ecology Method NWTPH-Gx.
VOCs analyzed by EPA Method 8260C or D.
PCUL = Preliminary Cleanup Level from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021. PCULs based on the practical quantitation limits (PQLs) italicized. Detected results shown in bold.
Detections above the screening level in the vadose zone are shown in **bold and highlighted blue**.
Detections above the screening level in the saturated zone are shown in **bold and highlighted gray.**
– = Not available or results not analyzed.
J = The reported concentration is an estimate based on detectable results between the method detection limit and reporting limit, laboratory QA/QC, or data validation review.
J+ = The result is an estimated quantity, but the result may be biased high.
J- = The result is an estimated quantity, but the result may be biased low.
U = Not detected at a concentration exceeding laboratory reporting limit
z = Gasoline/petroleum detection result is likely elevated due to high detections of CVOCs.
bgs = below ground surface
dup = duplicate
Pace = Pace Analytical of Mt. Juliet, Tennessee (formerly ESC)
PES = PES Environmental, Inc.

Table G-2

Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
PRB-A3/PRB-C3	A3C3-3	01/16/19	PES	Pace	3	39.7	V	0.00291 U	0.00165 U	**0.00790**	**0.00283 J**	0.00152 U	0.00163 U	0.00149 U	**0.000766 J**	0.000533 U	0.00375 U	0.000728 U	0.00510 U
	A3C3-6	01/16/19	PES	Pace	6	36.7	V	0.00313 U	0.00178 U	**0.160**	**0.00350 J**	0.00164 U	0.00176 U	0.00161 U	**0.0214**	0.000574 U	0.00404 U	0.000783 U	0.00548 U
	A3C3-8	01/16/19	PES	Pace	8	34.7	V	0.00547 U	0.00310 U	**0.149**	**0.0380**	0.00287 U	0.00306 U	0.00280 U	**0.0396**	0.00100 U	0.00704 U	0.00137 U	**0.0142**
	A3C3-10	02/13/19	PES	Pace	10	32.7	S	0.00371 U	0.00211 U	**0.00298 J**	**0.00626 J**	0.00194 U	0.00208 U	0.00190 U	0.000543 U	0.000679 U	0.00478 U	0.000928 U	**0.00652 J**
	A3C3-15	02/13/19	PES	Pace	15	27.7	S	0.00316 U	0.00179 U	**0.00281 J**	**0.0167**	0.00165 U	0.00177 U	0.00162 U	0.000462 U	0.000578 U	0.00407 U	0.000789 U	**0.0136**
	A3C3-20	02/13/19	PES	Pace	20	22.7	S	0.00312 U	0.00177 U	0.000801 U	0.00143 U	0.00164 U	0.00175 U	0.00160 U	0.000458 U	0.000572 U	0.00403 U	0.000781 U	0.00547 U
	A3C3-25	02/13/19	PES	Pace	25	17.7	S	0.00326 U	0.00185 U	0.000835 U	0.00149 U	0.00171 U	0.00183 U	0.00167 U	0.000477 U	0.000596 U	0.00420 U	0.000815 U	0.00570 U
	A3C3-32	02/13/19	PES	Pace	32	10.7	S	0.00315 U	0.00179 U	0.000807 U	0.00144 U	**0.00169 J**	0.00176 U	0.00161 U	0.000461 U	0.000576 U	0.00406 U	**0.00675**	0.00551 U
	A3C3-35	02/13/19	PES	Pace	35	7.7	S	0.00308 U	0.00175 U	**0.00198 J**	**0.00158 J**	0.00162 U	0.00173 U	0.00158 U	0.000452 U	0.000565 U	0.00398 U	0.000772 U	0.00540 U
	A3C3-40	02/13/19	PES	Pace	40	2.7	S	0.00336 U	0.00191 U	**0.265**	**0.00156 J**	**0.00227 J**	0.00188 U	0.00172 U	**0.0163**	0.000615 U	0.00433 U	0.000841 U	0.00588 U
	A3C3-45	02/13/19	PES	Pace	45	-2.3	S	0.00310 U	0.00176 U	0.000794 U	**0.00196 J**	**0.00300 J**	0.00174 U	0.00159 U	0.000454 U	0.000567 U	0.00400 U	0.000775 U	0.00543 U
	A3C3-50	02/13/19	PES	Pace	50	-7.3	S	0.00322 U	0.00183 U	**0.0279**	**0.00167 J**	**0.00198 J**	0.00181 U	0.00165 U	**0.00163**	0.000590 U	0.00415 U	**0.0203**	0.00564 U
PRB-A9/PRB-C9	A9C9-3	01/21/19	PES	Pace	3	40.1	V	0.00461 U	0.00262 U	**0.109**	**0.0115**	0.00242 U	0.00258 U	0.00236 U	0.000675 U	0.000844 U	0.00594 U	0.00115 U	0.00806 U
	A9C9-6	01/21/19	PES	Pace	6	37.1	V	0.00334 U	0.00190 U	**0.00257 J**	**0.00773**	0.00175 U	0.00187 U	0.00172 U	0.000490 U	0.000613 U	0.00431 U	0.000837 U	**0.0170**
	A9C9-10	01/21/19	PES	Pace	10	33.1	S	0.00315 U	0.00179 U	**0.00251 J**	**0.00384 J**	0.00165 U	0.00177 U	0.00162 U	0.000462 U	0.000578 U	0.00407 U	**0.00102 J**	0.00552 U
	A9C9-15	02/07/19	PES	Pace	15	28.1	S	0.00319 U	0.00181 U	**0.0477**	0.00146 U	0.00167 U	0.00179 U	0.00163 U	**0.0296**	0.000583 U	0.00411 U	0.000797 U	0.00558 U
	A9C9-20	02/07/19	PES	Pace	20	23.1	S	0.00314 U	0.00178 U	**0.0190**	0.00144 U	0.00164 U	0.00176 U	0.00161 U	**0.00885**	0.000575 U	0.00405 U	0.000785 U	0.00549 U
	A9C9-25	02/07/19	PES	Pace	25	18.1	S	0.00294 U	0.00167 U	**0.0381**	0.00135 U	0.00154 U	0.00165 U	0.00151 U	**0.00731**	0.000538 U	0.00379 U	**0.00576**	0.00514 U
	A9C9-32	02/07/19	PES	Pace	32	11.1	S	0.00292 U	0.00166 U	**4.44**	**0.00160 J**	**0.00738**	0.00163 U	0.00150 U	**1.32**	0.000534 U	0.00376 U	**0.0872**	0.00511 U
	A9C9-35	02/07/19	PES	Pace	35	8.1	S	0.00289 U	0.00164 U	**0.187**	0.00132 U	**0.00170 J**	0.00162 U	0.00148 U	**0.248**	0.000529 U	0.00373 U	**0.00747**	0.00506 U
	A9C9-40	02/07/19	PES	Pace	40	3.1	S	0.00293 U	0.00166 U	**0.0243**	**0.00217 J**	**0.00383 J**	0.00164 U	0.00150 U	**0.153**	0.000536 U	0.00378 U	**0.0754**	0.00513 U
	A9C9-45	02/07/19	PES	Pace	45	-1.9	S	0.00286 U	0.00162 U	**0.00154 J**	**0.00140 J**	0.00150 U	0.00160 U	0.00146 U	**0.00275**	0.000523 U	0.00368 U	**0.0123**	0.00500 U
	A9C9-50	02/07/19	PES	Pace	50	-6.9	S	0.00293 U	0.00167 U	**0.415**	**0.00174 J**	**0.00183 J**	0.00164 U	0.00151 U	**0.0656**	0.000538 U	0.00378 U	**0.0124**	0.00514 U
	B-931-50	02/07/19	PES	Pace	50 (dup)	-6.9	S	0.00294 U	0.00167 U	**0.387**	**0.00181 J**	**0.00208 J**	0.00165 U	0.00151 U	**0.0732**	0.000538 U	0.00379 U	**0.0181**	0.00514 U
PRB-B1/PRB-D1	B1D1-11	01/17/19	PES	Pace	11	30.8	S	0.00319 U	0.00181 U	**0.00192 J**	**0.00261 J**	0.00167 U	0.00179 U	0.00164 U	0.000467 U	0.000584 U	0.00411 U	0.000798 U	0.00558 U
	B1D1-15	01/17/19	PES	Pace	15	26.8	S	0.00417 U	0.00237 U	0.00107 U	0.00191 U	0.00219 U	0.00234 U	0.00214 U	0.000611 U	0.000764 U	0.00538 U	0.00104 U	0.00731 U
	B1D1-20	01/17/19	PES	Pace	20	21.8	S	0.00335 U	0.00190 U	**0.00173 J**	0.00153 U	0.00176 U	0.00188 U	0.00172 U	0.000491 U	0.000614 U	0.00432 U	0.000838 U	0.00587 U
	B1D1-25	01/17/19	PES	Pace	25	16.8	S	0.00380 U	0.00216 U	**0.00783**	0.00174 U	**0.00304 J**	0.00213 U	0.00195 U	**0.0922**	0.000695 U	0.00490 U	**0.0596**	0.00665 U
	B1D1-31	01/17/19	PES	Pace	31	10.8	S	0.00297 U	0.00169 U	**0.0185**	0.00136 U	0.00156 U	0.00166 U	0.00152 U	**0.0176**	0.000544 U	0.00383 U	**0.00468**	0.00520 U
	B1D1-35	01/17/19	PES	Pace	35	6.8	S	0.00334 U	0.00190 U	**0.0505**	0.00153 U	0.00175 U	0.00187 U	0.00171 U	**0.0219**	0.000612 U	0.00431 U	0.000837 U	0.00585 U
	B1D1-40	01/17/19	PES	Pace	40	1.8	S	0.00305 U	0.00173 U	**0.123**	0.00140 U	0.00160 U	0.00171 U	0.00157 U	**0.0284**	0.000559 U	0.00393 U	0.000764 U	0.00534 U
	B1D1-45	01/17/19	PES	Pace	45	-3.3	S	0.00312 U	0.00177 U	**0.478**	0.00143 U	0.00164 U	0.00175 U	0.00160 U	**0.139**	0.000572 U	0.00403 U	**0.000989 J**	0.00547 U
	B1D1-50	01/17/19	PES	Pace	50	-8.3	S	0.00315 U	0.00179 U	**1.71**	0.00144 U	**0.00268 J**	0.00177 U	0.00162 U	**0.274**	0.000578 U	0.00407 U	**0.00154 J**	0.00552 U
PRB-B2/PRB-D2	B2D2-3	01/16/19	PES	Pace	3	38.8	V	0.00298 U	0.00169 U	**0.0133**	**0.00144 J**	0.00156 U	0.00167 U	0.00153 U	0.000436 U	0.000545 U	0.00384 U	0.000745 U	0.00521 U
	B2D2-6	01/16/19	PES	Pace	6	35.8	V	0.00380 U	0.00216 U	**0.180**	**0.00424 J**	0.00199 U	0.00213 U	0.00195 U	0.000557 U	0.000696 U	0.00490 U	0.000951 U	**0.0127**
	B2D2-10	01/21/19	PES	Pace	10	31.8	S	0.00597 U	0.00338 U	**0.00154 J**	**0.118**	**0.0366**	0.00334 U	0.00303 U	**0.00166 J**	0.00109 U	0.00770 U	**0.141**	**0.0516**

Table G-2

Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
PRB-B4/PRB-D4	B4D4-3	01/17/19	PES	Pace	3	39.7	V	0.00309 U	0.00175 U	0.000792 U	0.00141 U	0.00162 U	0.00173 U	0.00158 U	0.000453 U	0.000566 U	0.00398 U	0.000773 U	0.00541 U
	B4D4-6	01/17/19	PES	Pace	6	36.7	V	0.00429 U	0.00244 U	**0.0605**	**0.00647 J**	0.00225 U	0.00241 U	0.00218 U	**0.00337**	0.000787 U	0.00554 U	**0.00371 J**	**0.00818 J**
	B4D4-10	01/17/19	PES	Pace	10	32.7	S	0.00347 U	0.00197 U	**0.00665 J-**	**0.00632 J-**	**0.00429 J-**	0.00194 U	0.00178 U	**0.00675 J-**	0.000635 U	0.00447 U	**0.0160 J-**	**0.00611 J-**
PRB-B5/PRB-D5	B5D5-10	02/14/19	PES	Pace	10	32.9	S	0.00320 U	0.00182 U	**0.140**	**0.00260 J**	**0.00325 J**	–	–	**0.00203**	0.000586 U	0.00412 U	0.000800 U	0.00560 U
	B5D5-15	02/14/19	PES	Pace	15	27.9	S	0.00318 U	0.00180 U	**0.00298**	0.00146 U	0.00166 U	0.00178 U	0.00163 U	0.000466 U	0.000582 U	0.00410 U	0.000795 U	0.00557 U
	B5D5-20	02/14/19	PES	Pace	20	22.9	S	0.00319 U	0.00181 U	**0.00166 J**	0.00146 U	0.00167 U	0.00179 U	0.00164 U	0.000467 U	0.000584 U	0.00411 U	0.000798 U	0.00558 U
	B5D5-25	02/14/19	PES	Pace	25	17.9	S	0.00322 U	0.00183 U	**0.0608**	0.00147 U	**0.00294 J**	0.00180 U	0.00165 U	**0.00455**	0.000589 U	0.00415 U	**0.00858**	0.00563 U
	B5D5-32	02/14/19	PES	Pace	32	10.9	S	0.00310 U	0.00176 U	**0.0382**	0.00142 U	**0.00280 J**	0.00174 U	0.00159 U	**0.00548**	0.000568 U	0.00400 U	**0.0169**	0.00543 U
	B5D5-35	02/14/19	PES	Pace	35	7.9	S	–	–	**0.200**	**0.00155 J**	**0.0482**	–	–	**0.000844 J**	–	–	**0.136**	0.00527 U
	B5D5-40	02/14/19	PES	Pace	40	2.9	S	0.00301 U	0.00171 U	**0.483**	**0.00144 J**	**0.0103**	0.00169 U	0.00154 U	**0.00165**	0.000551 U	0.00388 U	**0.219**	0.00527 U
	B5D5-45	02/14/19	PES	Pace	45	-2.1	S	0.00294 U	0.00167 U	**3.45**	**0.00148 J**	**0.00663**	0.00165 U	0.00151 U	**0.310**	0.000538 U	0.00379 U	**0.0802**	0.00514 U
	B5D5-50	02/14/19	PES	Pace	50	-7.1	S	0.00285 U	0.00162 U	**0.0112**	**0.00233 J**	0.00149 U	0.00160 U	0.00146 U	**0.00173**	0.000521 U	0.00367 U	**0.0158**	0.00498 U
	B-932-50	02/14/19	PES	Pace	50 (dup)	-7.1	S	0.00290 U	0.00164 U	**0.0148**	**0.00200 J**	0.00152 U	0.00162 U	0.00149 U	**0.00198**	0.000531 U	0.00373 U	**0.0223**	**0.00595 J**
PRB-B6/PRB-D6	B6D6-17	02/20/19	PES	Pace	17	25.9	S	0.00314 U	0.00178 U	**0.00641**	**0.00146 J**	0.00164 U	0.00176 U	0.00161 U	**0.00629**	0.000575 U	0.00405 U	0.000785 U	0.00550 U
	B6D6-20	02/20/19	PES	Pace	20	22.9	S	0.00317 U	0.00180 U	**0.00154 J**	**0.00201 J**	0.00166 U	0.00178 U	0.00163 U	**0.00333**	0.000581 U	0.00409 U	0.000793 U	0.00555 U
	B6D6-25	02/20/19	PES	Pace	25	17.9	S	0.00325 U	0.00184 U	**0.00806**	0.00149 U	0.00170 U	0.00182 U	0.00167 U	**0.00229**	0.000595 U	0.00419 U	0.000813 U	0.00569 U
	B6D6-32	02/20/19	PES	Pace	32	10.9	S	0.00329 U	0.00187 U	**0.441**	0.00151 U	**0.00889**	0.00184 U	0.00169 U	**0.147**	0.000602 U	0.00424 U	0.000823 U	0.00576 U
	B6D6-35	02/20/19	PES	Pace	35	7.9	S	0.00296 U	0.00168 U	**0.575**	**0.00140 J**	**0.0293**	0.00166 U	0.00152 U	**0.577**	0.000543 U	0.00382 U	0.000741 U	0.00519 U
	B6D6-40	02/20/19	PES	Pace	40	2.9	S	0.00322 U	0.00183 U	**0.00500**	**0.00187 J**	**0.00213 J**	0.00181 U	0.00165 U	**0.0210**	0.000590 U	0.00416 U	0.000807 U	0.00564 U
	B6D6-45	02/20/19	PES	Pace	45	-2.1	S	0.00603 U	0.00342 U	**0.193**	**0.00282 J**	**0.00347 J**	0.00338 U	0.00309 U	**0.316**	0.00110 U	0.00778 U	**0.00759**	0.0106 U
	B6D6-50	02/20/19	PES	Pace	50	-7.1	S	0.00292 U	0.00166 U	**0.00513**	**0.00156 J**	0.00153 U	0.00164 U	0.00150 U	**0.00153**	0.000535 U	0.00377 U	0.000731 U	0.00512 U
	B-933-50	02/20/19	PES	Pace	50 (dup)	-7.1	S	0.00300 U	0.00171 U	**0.285**	**0.00216 J**	**0.00224 J**	0.00168 U	0.00154 U	**0.264**	0.000550 U	0.00387 U	0.000751 U	0.00526 U
PRB-B10/PRB-D10	B10D10-15	02/21/19	PES	Pace	15	30.1	S	0.00344 U	0.00195 U	**0.0321**	**0.00787**	0.00180 U	0.00193 U	0.00177 U	0.000504 U	0.000630 U	0.00444 U	0.000861 U	**0.00656 J**
	B10D10-20	02/21/19	PES	Pace	20	25.1	S	0.00330 U	0.00187 U	**0.00726**	0.00151 U	**0.00334 J**	0.00185 U	0.00169 U	**0.00164**	0.000604 U	0.00425 U	0.000825 U	0.00577 U
	B10D10-25	02/21/19	PES	Pace	25	20.1	S	0.00308 U	0.00175 U	**1.89**	**0.00185 J**	**0.00652**	0.00173 U	0.00158 U	**0.419**	0.000565 U	0.00398 U	0.000772 U	0.00540 U
	B10D10-30	02/21/19	PES	Pace	30	15.1	S	0.00307 U	0.00174 U	**1.03**	0.00140 U	**0.00837**	0.00172 U	0.00157 U	**0.603**	0.000561 U	0.00395 U	0.000767 U	0.00537 U
	B10D10-35	02/21/19	PES	Pace	35	10.1	S	0.00300 U	0.00170 U	**0.0809**	**0.00154 J**	**0.00238 J**	0.00168 U	0.00154 U	**0.418**	0.000549 U	0.00386 U	0.000750 U	0.00525 U
	B10D10-40	02/21/19	PES	Pace	40	5.1	S	0.00312 U	0.00177 U	**0.0210**	**0.00166 J**	0.00163 U	0.00175 U	0.00160 U	**0.0552**	0.000571 U	0.00402 U	0.000780 U	0.00546 U
	B10D10-45	02/21/19	PES	Pace	45	0.1	S	0.0478 U	0.0271 U	0.00757 U	0.0218 U	0.0251 U	0.0268 U	0.0245 U	**0.0182**	0.00876 U	0.0616 U	0.0120 U	0.0837 U
	B10D10-50	02/21/19	PES	Pace	50	-4.9	S	0.00302 U	0.00172 U	**0.251**	**0.00146 J**	**0.00208 J**	0.00169 U	0.00155 U	**0.247**	0.000554 U	0.00390 U	0.000756 U	0.00529 U

Table G-2

Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
PRB-B11/PRB-D11	B11D11-10	01/15/19	PES	Pace	10	35.1	V	0.00368 U	0.00209 U	0.000944 U	**0.0101**	0.00193 U	0.00207 U	0.00186 U	0.000539 U	0.000674 U	0.00475 U	0.000921 U	0.00644 U
	B11D11-15	01/15/19	PES	Pace	15	30.1	S	0.00297 U	0.00169 U	**0.00295**	0.00136 U	0.00156 U	0.00167 U	0.00152 U	**0.00351**	0.000544 U	0.00383 U	0.000744 UJ	0.00520 U
	B11D11-20	01/15/19	PES	Pace	20	25.1	S	0.00313 U	0.00178 U	**0.0526**	0.00144 U	0.00164 U	0.00176 U	0.00161 U	**0.0138**	0.000574 U	0.00404 U	0.000784 UJ	0.00549 U
	B11D11-27	01/15/19	PES	Pace	27	18.1	S	0.00300 U	0.00170 U	**1.77**	0.00137 U	0.00157 U	0.00168 U	0.00154 U	**0.0723**	0.000549 U	0.00386 U	0.000749 U	0.00524 U
	B11D11-30	01/15/19	PES	Pace	30	15.1	S	0.00283 U	0.00161 U	**4.42**	0.00130 U	**0.00410 J**	0.00159 U	0.00145 U	**0.226**	0.000519 U	0.00365 U	0.000709 UJ	0.00496 U
	B11D11-35	01/15/19	PES	Pace	35	10.1	S	0.00305 U	0.00173 U	**2.60**	**0.00160 J**	**0.00269 J**	0.00171 U	0.00157 U	**0.441**	0.000559 U	0.00394 U	0.000764 UJ	0.00535 U
	B11D11-40	01/15/19	PES	Pace	40	5.1	S	0.00298 U	0.00169 U	**0.0198**	0.00136 U	0.00156 U	0.00167 U	0.00153 U	**0.0156**	0.000546 U	0.00384 U	0.000745 UJ	0.00522 U
	B11D11-46	01/15/19	PES	Pace	46	-0.9	S	0.00308 U	0.00175 U	**1.13**	0.00141 U	**0.00185 J**	0.00172 U	0.00158 U	**0.273**	0.000564 U	0.00397 U	0.000770 UJ	0.00539 U
	B-928-46	01/15/19	PES	Pace	46 (dup)	-0.9	S	0.00307 U	0.00174 U	**1.43**	0.00141 U	**0.00216 J**	0.00172 U	0.00157 U	**0.332**	0.000562 U	0.00396 U	0.000768 UJ	0.00538 U
	B11D11-50	01/15/19	PES	Pace	50	-4.9	S	0.00364 U	0.00207 U	**0.0119**	**0.00238 J**	0.00190 U	0.00204 U	0.00187 U	**0.00177**	0.000667 U	0.00469 U	0.000910 UJ	0.00637 U
PRB-B13/PRB-D13	B13D13-10	03/21/19	PES	Pace	10	37.5	V	0.00311 U	0.00177 U	**0.000798** U	0.00143 U	0.00163 U	0.00174 U	0.00160 U	0.000456 U	0.000570 U	0.00401 U	0.000779 U	0.00545 U
	B13D13-20	03/21/19	PES	Pace	20	27.5	S	0.00323 U	0.00184 U	**0.000829** U	0.00148 U	0.00169 U	0.00181 U	0.00166 U	0.000474 U	0.000592 U	0.00417 U	0.000809 U	0.00566 U
	B13D13-30	03/21/19	PES	Pace	30	17.5	S	0.00314 U	0.00178 U	**0.0498**	0.00144 U	0.00164 U	0.00176 U	0.00161 U	**0.0117**	0.000574 U	0.00404 U	0.000785 U	0.00549 U
	B13D13-40	03/21/19	PES	Pace	40	7.5	S	0.00291 U	0.00165 U	**0.00300**	0.00133 U	0.00153 U	0.00163 U	0.00149 U	**0.000505 J**	0.000534 U	0.00376 U	0.000729 U	0.00510 U
	B13D13-50	03/21/19	PES	Pace	50	-2.5	S	0.00300 U	0.00170 U	**0.00784**	0.00137 UJ	0.00157 U	0.00168 U	0.00154 U	0.00166 UJ	0.000549 U	0.00387 U	0.000750 UJ	0.00525 UJ
PRB-B16/PRB-D16	B16D16-15	03/13/19	PES	Pace	15	34.5	S	0.0128 U	0.00728 U	0.00329 U	0.00587 U	0.00672 U	0.00719 U	0.00658 U	0.00188 U	0.00235 U	0.0166 U	0.00321 U	0.0224 U
	B16D16-20	03/13/19	PES	Pace	20	29.5	S	0.00299 U	0.00170 U	**0.0142**	0.00137 U	0.00156 U	0.00167 U	0.00153 U	**0.000603 J**	0.000547 U	0.00385 U	0.000747 U	0.00523 U
	B16D16-25	03/13/19	PES	Pace	25	24.5	S	0.00292 U	0.00166 U	**0.0242**	0.00134 U	0.00153 U	0.00164 U	0.00150 U	**0.00173**	0.000536 U	0.00377 U	0.000732 U	0.00512 U
	B16D16-30	03/13/19	PES	Pace	30	19.5	S	0.00300 U	0.00170 U	**0.0590**	0.00137 U	0.00157 U	0.00168 U	0.00154 U	**0.00431**	0.000550 U	0.00387 U	0.000751 U	0.00525 U
	B16D16-35	03/13/19	PES	Pace	35	14.5	S	0.00300 U	0.00170 U	**0.00319**	0.00137 U	0.00157 U	0.00168 U	0.00154 U	**0.0279**	0.000550 U	0.00387 U	**0.00599**	0.00526 U
	B16D16-40	03/13/19	PES	Pace	40	9.5	S	0.00318 U	0.00181 U	**0.321**	0.00146 U	**0.00788**	0.00178 U	0.00163 U	**0.0276**	0.000583 U	0.00410 U	**0.789**	0.00557 U
	B16D16-45	03/13/19	PES	Pace	45	4.5	S	0.00292 U	0.00166 U	**0.598**	0.00134 U	0.00153 U	0.00164 U	0.00150 U	**0.165**	0.000534 U	0.00376 U	**0.0503**	0.00511 U
	B16D16-50	03/13/19	PES	Pace	50	-0.5	S	0.00297 U	0.00169 U	**0.884**	**0.00247 J**	0.00156 U	0.00166 U	0.00152 U	**0.0610**	0.000544 U	0.00383 U	**0.0421**	0.00520 U
	B16D16-55	03/13/19	PES	Pace	55	-5.5	S	0.0135 U	0.00761 U	**0.00483 J**	0.00614 U	0.00702 U	0.00752 U	0.00688 U	0.00196 U	0.00246 U	0.0173 U	0.00335 U	0.0235 U
	B16D16-60	03/13/19	PES	Pace	60	-10.5	S	0.00290 U	0.00165 U	**0.00112 J**	**0.00152 J**	0.00152 U	0.00163 U	0.00149 U	0.000426 U	0.000532 U	0.00375 U	0.000727 U	0.00509 U
	B16D16-65	03/13/19	PES	Pace	65	-15.5	S	0.00299 U	0.00170 U	0.000766 U	0.00137 U	0.00156 U	0.00167 U	0.00153 U	0.000438 U	0.000547 U	0.00385 U	0.000747 U	0.00523 U
	B16D16-70	03/13/19	PES	Pace	70	-20.5	S	0.00306 U	0.00174 U	0.000785 U	**0.00207 J**	0.00160 U	0.00172 U	0.00157 U	0.000448 U	0.000560 U	0.00395 U	0.000766 U	0.00536 U
	B16D16-75	03/13/19	PES	Pace	75	-25.5	S	0.00300 U	0.00170 U	0.000769 U	**0.00359 J**	0.00157 U	0.00168 U	0.00154 U	0.000439 U	0.000549 U	0.00386 U	0.000750 U	0.00525 U
	B16D16-80	03/13/19	PES	Pace	80	-30.5	S	0.00305 U	0.00173 U	0.000781 U	0.00139 U	0.00160 U	0.00171 U	0.00156 U	0.000446 U	0.000558 U	0.00393 U	0.000762 U	0.00533 U
	B16D16-85	03/13/19	PES	Pace	85	-35.5	S	0.00303 U	0.00172 U	0.000776 U	0.00139 U	0.00159 U	0.00170 U	0.00155 U	0.000444 U	0.000555 U	0.00390 U	0.000758 U	0.00530 U
	B16D16-90	03/13/19	PES	Pace	90	-40.5	S	0.00308 U	0.00175 U	0.000791 U	0.00141 U	0.00162 U	0.00173 U	0.00158 U	0.000452 U	0.000565 U	0.00398 U	0.000771 U	0.00540 U
	B16D16-95	03/13/19	PES	Pace	95	-45.5	S	0.00318 U	0.00180 U	0.000815 U	0.00146 U	0.00167 U	0.00178 U	0.00163 U	0.000466 U	0.000582 U	0.00410 U	0.000795 U	0.00557 U
	B16D16-100	03/13/19	PES	Pace	100	-50.5	S	0.00316 U	0.00180 U	0.000811 U	0.00145 U	0.00166 U	0.00177 U	0.00162 U	0.000463 U	0.000579 U	0.00408 U	0.000791 U	0.00554 U
	B16D16-105	03/13/19	PES	Pace	105	-55.5	S	0.00311 U	0.00177 U	0.000798 U	0.00142 U	0.00163 U	0.00174 U	0.00160 U	0.000456 U	0.000570 U	0.00401 U	0.000779 U	0.00545 U
	B-934-105	03/13/19	PES	Pace	105 (dup)	-55.5	S	0.00312 U	0.00177 U	0.000799 U	0.00143 U	0.00163 U	0.00175 U	0.00160 U	0.000456 U	0.000571 U	0.00402 U	0.000779 U	0.00545 U

Table G-2

Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
PRB-B18/PRB-D18	B18D18-10	03/22/19	PES	Pace	10	41.0	V	0.00319 U	0.00181 U	**0.00519**	0.00146 U	0.00167 U	0.00179 U	0.00163 U	0.000467 UJ	0.000583 U	0.00411 U	0.000797 U	0.00558 U
	B18D18-20	03/22/19	PES	Pace	20	31.0	S	0.00304 U	0.00172 U	**0.00911**	0.00139 U	0.00159 U	0.00170 U	0.00156 U	0.000445 UJ	0.000556 U	0.00391 U	0.000760 U	0.00532 U
	B18D18-30	03/22/19	PES	Pace	30	21.0	S	0.00301 U	0.00171 U	**0.253**	**0.00233 J**	**0.00168 J**	0.00168 U	0.00154 U	**0.00663 J**	0.000551 U	0.00388 U	0.000752 U	0.00526 U
	B18D18-40	03/22/19	PES	Pace	40	11.0	S	0.00301 U	0.00171 U	**0.0237**	0.00138 U	0.00158 U	0.00169 U	0.00154 U	**0.00331 J**	0.000552 U	0.00388 U	0.000754 U	0.00527 U
	B18D18-50	03/22/19	PES	Pace	50	1.0	S	0.00296 U	0.00168 U	**0.00688**	0.00135 U	0.00155 U	0.00166 U	0.00152 U	**0.00244 J**	0.000542 U	0.00382 U	0.000740 U	0.00518 U
PRB-B19/PRB-D19	B19D19-10	03/18/19	PES	Pace	10	42.5	V	0.00301 U	0.00171 U	0.000772 U	**0.00149 J**	0.00158 U	0.00169 U	0.00154 U	0.000441 U	0.000551 U	0.00388 U	0.000753 U	0.00527 U
	B19D19-15	03/18/19	PES	Pace	15	37.5	V	0.00336 U	0.00191 U	**0.0182**	0.00154 U	0.00177 U	0.00189 U	0.00172 U	0.000493 U	0.000617 U	0.00434 U	0.000843 U	0.00590 U
	B19D19-20	03/18/19	PES	Pace	20	32.5	S	0.00319 U	0.00181 U	**0.0251**	**0.00152 J**	0.00167 U	0.00179 U	0.00163 U	**0.000616 J**	0.000584 U	0.00411 U	0.000797 U	0.00558 U
	B19D19-25	03/18/19	PES	Pace	25	27.5	S	0.00339 U	0.00192 U	**2.38**	**0.00184 J**	0.00177 U	0.00189 U	0.00173 U	**0.221**	0.000620 U	0.00436 U	0.000847 U	0.00592 U
	B19D19-30	03/18/19	PES	Pace	30	22.5	S	0.00314 U	0.00178 U	**0.604**	**0.00171 J**	0.00164 U	0.00176 U	0.00161 U	**0.0272**	0.000575 U	0.00405 U	0.000785 U	0.00549 U
	B19D19-35	03/18/19	PES	Pace	35	17.5	S	0.00310 U	0.00176 U	**0.189**	0.00142 U	0.00162 U	0.00173 U	0.00159 U	**0.0189**	0.000567 U	0.00399 U	**0.0176**	0.00542 U
	B19D19-40	03/18/19	PES	Pace	40	12.5	S	0.00318 U	0.00181 U	**0.212 J**	**0.00188 J**	0.00167 U	0.00178 U	0.00163 U	**0.00993 J**	0.000582 U	0.00410 U	0.000796 U	0.00557 U
	B19D19-45	03/18/19	PES	Pace	45	7.5	S	0.00316 U	0.00179 U	**7.74**	0.00145 U	0.00166 U	0.00177 U	0.00163 U	**0.222**	0.000579 U	0.00408 U	0.000791 U	0.00554 U
	B19D19-50	03/18/19	PES	Pace	50	2.5	S	0.00313 U	0.00178 U	**0.00329**	**0.00247 J**	0.00164 U	0.00175 U	0.00161 U	0.000459 U	0.000573 U	0.00404 U	0.000783 U	0.00548 U
	B19D19-55	03/18/19	PES	Pace	55	-2.5	S	0.00315 U	0.00179 U	0.000807 U	**0.00173 J**	0.00165 U	0.00176 U	0.00161 U	0.000461 U	0.000576 U	0.00406 U	0.000787 U	0.00551 UJ
	B19D19-60	03/18/19	PES	Pace	60	-7.5	S	0.00306 U	0.00174 U	0.000784 U	**0.00253 J**	0.00160 U	0.00171 U	0.00157 U	0.000448 U	0.000560 U	0.00394 U	0.000765 U	0.00536 U
	B19D19-65	03/18/19	PES	Pace	65	-12.5	S	0.00346 U	0.00197 U	0.000888 U	**0.00244 J**	0.00181 U	0.00194 U	0.00178 U	0.000508 U	0.000634 U	0.00447 U	0.000867 U	0.00606 U
	B19D19-70	03/18/19	PES	Pace	70	-17.5	S	0.00333 U	0.00189 U	**0.00179 J**	**0.00181 J**	0.00175 U	0.00187 U	0.00171 U	0.000488 U	0.000610 U	0.00430 U	0.000834 U	0.00583 U
	B19D19-75	03/18/19	PES	Pace	75	-22.5	S	0.00325 U	0.00184 U	0.000832 U	0.00148 U	0.00169 U	0.00181 U	0.00166 U	0.000475 U	0.000594 U	0.00419 U	0.000812 U	0.00568 U
	B19D19-80	03/18/19	PES	Pace	80	-27.5	S	0.00309 U	0.00176 U	0.000793 U	0.00142 U	0.00162 U	0.00173 U	0.00159 U	0.000453 U	0.000566 U	0.00399 U	0.000774 U	0.00541 U
	B19D19-85	03/18/19	PES	Pace	85	-32.5	S	0.00332 U	0.00188 U	0.000850 U	0.00152 U	0.00174 U	0.00186 U	0.00170 U	0.000486 U	0.000607 U	0.00427 U	0.000829 U	0.00580 U
	B19D19-90	03/18/19	PES	Pace	90	-37.5	S	0.00344 U	0.00195 U	0.000881 U	**0.00213 J**	0.00180 U	0.00193 U	0.00177 U	0.000504 U	0.000630 U	0.00444 U	0.000860 U	0.00601 U
	B19D19-95	03/18/19	PES	Pace	95	-42.5	S	0.00327 U	0.00186 U	0.000839 U	0.00150 U	0.00171 U	0.00183 U	0.00168 U	0.000479 U	0.000599 U	0.00422 U	0.000819 U	0.00573 U
	B19D19-100	03/18/19	PES	Pace	100	-47.5	S	0.00333 U	0.00188 U	0.000852 U	**0.00159 J**	0.00174 U	0.00186 U	0.00170 U	0.000487 U	0.000609 U	0.00429 U	0.000832 U	0.00582 U
	B19D19-105	03/18/19	PES	Pace	105	-52.5	S	0.00305 U	0.00173 U	0.000781 U	0.00139 U	0.00160 U	0.00171 U	0.00156 U	0.000446 U	0.000558 U	0.00393 U	0.000762 U	0.00533 U
	B19D19-110	03/18/19	PES	Pace	110	-57.5	S	0.00344 U	0.00195 U	0.000881 U	0.00157 U	0.00180 U	0.00193 U	0.00176 U	0.000504 U	0.000630 U	0.00443 U	0.000860 U	0.00602 U
	B-935-40	03/18/19	PES	Pace	110 (dup)	-57.5	S	0.00367 U	0.00208 U	0.000939 UJ	0.00167 U	0.00192 U	0.00206 U	0.00188 U	0.000537 UJ	0.000671 U	0.00473 U	0.000916 U	0.00641 U

Table G-2

Perimeter Injection Well Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
PRB-B21/PRB-D21	B21D21-10	03/25/19	PES	Pace	10	44.0	V	0.00313 U	0.00177 U	**0.000803** U	0.00143 U	0.00164 U	0.00175 U	0.00160 U	0.000459 U	0.000573 U	0.00403 U	0.000783 U	0.00548 U
	B21D21-20	03/25/19	PES	Pace	20	34.0	S	0.00323 U	0.00183 U	**0.000828** U	0.00148 U	0.00169 U	0.00181 U	0.00165 U	0.000473 U	0.000592 U	0.00416 U	0.000808 U	0.00565 U
	B21D21-30	03/25/19	PES	Pace	30	24.0	S	0.00294 U	0.00167 U	**2.06**	0.00135 U	0.00154 U	0.00165 U	0.00151 U	**0.0810**	0.000539 U	0.00379 U	0.000736 U	0.00515 U
	B21D21-40	03/25/19	PES	Pace	40	14.0	S	0.00303 U	0.00172 U	**0.00395**	0.00139 U	0.00158 U	0.00170 U	0.00155 U	0.000443 U	0.000554 U	0.00390 U	0.000757 U	0.00530 U
	B21D21-50	03/25/19	PES	Pace	50	4.0	S	0.00309 U	0.00176 U	**0.600**	**0.00229 J**	0.00162 U	0.00173 U	0.00159 U	**0.00903**	0.000566 U	0.00399 U	**0.0933**	0.00541 U
	B21D21-60	03/26/19	PES	Pace	60	-6.0	S	0.00298 U	0.00169 U	**0.00192 J**	0.00136 U	0.00156 U	0.00167 U	0.00153 U	0.000437 U	0.000546 U	0.00384 U	**0.0162 J**	0.00522 U
	B-936-60	03/26/19	PES	Pace	60 (dup)	-6.0	S	0.00299 U	0.00170 U	0.000766 U	**0.00180 J**	0.00157 U	0.00167 U	0.00153 U	0.000438 U	0.000547 U	0.00385 U	**0.0601 J**	0.00523 U
All Data	Number of Analytes Measured							127	127	128	128	128	126	126	128	127	127	128	128
	Number of Analytes Detected							0	0	94	59	32	0	0	72	0	0	30	9
	Frequency of Detection							0.0%	0.0%	73.4%	46.1%	25.0%	0.0%	0.0%	56.3%	0.0%	0.0%	23.4%	7.0%
	Maximum Detection							–	–	7.74	0.118	0.0482	–	–	1.32	–	–	0.789	0.0516
	Minimum Detection							0.00283 U	0.00161 U	0.000766 U	0.0013 U	0.00149 U	0.00159 U	0.00145 U	0.000426 U	0.000519 U	0.00365 U	0.000709 UJ	0.00496 U
	Number Of Vadose (V) Detections above SL							0	0	5	0	0	0	–	1	0	0	0	0
	Number of Saturated (S) Detections above SL							0	0	64	0	2	0	–	56	0	0	26	0
2017-2021	Number of Analytes Measured							127	127	128	128	128	126	126	128	127	127	128	128
	Number of Analytes Detected							0	0	94	59	32	0	0	72	0	0	30	9
	Frequency of Detection							0.0%	0.0%	73.4%	46.1%	25.0%	0.0%	0.0%	56.3%	0.0%	0.0%	23.4%	7.0%
	Maximum Detection							–	–	7.74	0.118	0.0482	–	–	1.32	–	–	0.789	0.0516
	Minimum Detection							0.00283 U	0.00161 U	0.000766 U	0.0013 U	0.00149 U	0.00159 U	0.00145 U	0.000426 U	0.000519 U	0.00365 U	0.000709 UJ	0.00496 U
	Number Of Vadose (V) Detections above SL							0	0	5	0	0	0	–	1	0	0	0	0
	Number of Saturated (S) Detections above SL							0	0	64	0	2	0	–	56	0	0	26	0

Notes and Abbreviations:

Soil between elevations +10 to 55 feet was treated.

Petroleum Hydrocarbons (PHCs) analyzed by Ecology Method NWTPH-Gx.

VOCs analyzed by EPA Method 8260C or D.

PCUL = Preliminary Cleanup Level from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021. PCULs based on the practical quantitation limits (PQLs) italicized. Detected results shown in bold.

Detections above the screening level in the vadose zone are shown in **bold and highlighted blue**.

Detections above the screening level in the saturated zone are shown in **bold and highlighted gray.**

– = Not available or results not analyzed.

J = The reported concentration is an estimate based on detectable results between the method detection limit and reporting limit, laboratory QA/QC, or data validation review.

J+ = The result is an estimated quantity, but the result may be biased high.

J- = The result is an estimated quantity, but the result may be biased low.

U = Not detected at a concentration exceeding laboratory reporting limit

z = Gasoline/petroleum detection result is likely elevated due to high detections of CVOCs.

bgs = below ground surface

dup = duplicate

Pace = Pace Analytical of Mt. Juliet, Tennessee (formerly ESC)

PES = PES Environmental, Inc.

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	**–**	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	**–**	**0.030**	**1.5E-07**
B-1A	B-1/S-2	12/01/89	HC	ARI	10.5	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
B-2A	B-2/S-1	12/01/89	HC	ARI	10	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
B-212	B-212-15	09/08/17	PES	ESC	15	42.6	V	0.977 U	–	–	–	0.000304 U	0.000329 U	0.000420 U	0.000319 U	0.000420 U	0.000229 U	0.000349 U	0.000365 U	0.000352 U	0.000853 U
	B-212-21	09/08/17	PES	ESC	21	36.6	S	**63.0**	–	–	–	0.000274 U	0.000297 U	0.000379 U	0.000288 U	0.000379 U	0.000207 U	0.000315 U	0.000329 U	0.000318 U	0.000770 U
	B-212-35	09/08/17	PES	ESC	35	22.6	S	**1.98**	–	–	–	0.000288 U	0.000312 U	0.000398 U	0.000302 U	0.000398 U	0.000217 U	0.000330 U	0.000346 U	0.000334 U	0.000808 U
	B-212-45	09/08/17	PES	ESC	45	12.6	S	**2.81**	–	–	–	0.000276 U	0.000299 U	0.000382 U	0.000290 U	0.000382 U	0.000208 U	0.000317 U	0.000332 U	0.000320 U	0.000775 U
	B-907-25	09/08/17	PES	ESC	45 (dup)	12.6	S	**1.16**	–	–	–	0.00789 U	0.00855 U	0.0109 U	0.00827 U	0.0109 U	0.00595 U	0.00906 U	0.00947 U	0.00914 U	0.0221 U
	B-212-55	09/08/17	PES	ESC	55	2.6	S	–	–	–	–	0.000298 U	0.000323 U	0.000412 U	0.000313 U	0.000412 U	0.000225 U	0.000342 U	0.000358 U	0.000345 U	0.000836 U
	B-212-65	09/08/17	PES	ESC	65	-7.4	S	**1.29**	–	–	–	0.000306 U	0.000332 U	0.000424 U	0.000322 U	0.000424 U	0.000231 U	0.000352 U	0.000368 U	0.000355 U	0.000860 U
	B-212-75	09/08/17	PES	ESC	75	-17.4	S	1.05 U	–	–	–	0.000307 U	0.000333 U	0.000424 U	0.000322 U	0.000424 U	0.000231 U	0.000352 U	0.000369 U	0.000356 U	0.000862 U
	B-212-85	09/11/17	PES	ESC	85	-27.4	S	0.0385 U	–	–	–	0.000300 U	0.000325 U	0.000414 U	0.000314 U	0.000414 U	0.000226 U	0.000344 U	0.000360 U	0.000347 U	0.000841 U
	B-212-95	09/11/17	PES	ESC	95	-37.4	S	0.0422 U	–	–	–	0.000345 U	0.000374 U	0.000477 U	0.000362 U	0.000477 U	0.000260 U	0.000396 U	0.000415 U	0.000400 U	0.000969 U
	B-212-100	09/11/17	PES	ESC	100	-42.4	S	0.0409 U	–	–	–	0.000319 U	0.000345 U	0.000440 U	0.000334 U	0.000440 U	0.000240 U	0.000366 U	0.000383 U	0.000369 U	0.000894 U
B-213	B-213-15	09/05/17	PES	ESC	15	42.4	V	–	–	–	–	0.000306 U	0.000331 U	0.000423 U	0.000321 U	0.000423 U	0.000231 U	0.000351 U	0.000367 U	0.000355 U	0.000859 U
	B-213-21.5	09/05/17	PES	ESC	22	35.9	S	–	–	–	–	0.000275 U	0.000298 U	0.000380 U	0.000289 U	0.000380 U	0.000207 U	0.000316 U	0.000330 U	0.000319 U	0.000772 U
	B-213-35	09/05/17	PES	ESC	35	22.4	S	–	–	–	–	0.000286 U	0.000310 U	0.000395 U	0.000300 U	0.000395 U	0.000215 U	0.000328 U	0.000343 U	0.000331 U	0.000802 U
	B-213-45	09/05/17	PES	ESC	45	12.4	S	–	–	–	–	0.000293 U	0.000317 U	0.000405 U	0.000307 U	0.000405 U	0.000221 U	0.000336 U	0.000351 U	0.000339 U	0.000821 U
	B-213-55	09/05/17	PES	ESC	55	2.4	S	–	–	–	–	0.000287 U	0.000311 U	0.000397 U	0.000302 U	0.000397 U	0.000217 U	0.000330 U	0.000345 U	0.000333 U	0.000807 U
	B-213-65	09/05/17	PES	ESC	65	-7.6	S	–	–	–	–	0.000290 U	0.000315 U	0.000402 U	0.000305 U	0.000402 U	0.000219 U	0.000333 U	0.000349 U	0.000337 U	0.000815 U
	B-213-75	09/05/17	PES	ESC	75	-17.6	S	–	–	–	–	0.000289 U	0.000313 U	0.000399 U	0.000303 U	0.000399 U	0.000217 U	0.000331 U	0.000346 U	0.000334 U	0.000810 U
	B-213-85	09/05/17	PES	ESC	85	-27.6	S	–	–	–	–	0.000322 U	0.000349 U	0.000445 U	0.000338 U	0.000445 U	0.000243 U	0.000369 U	0.000386 U	0.000373 U	0.000903 U
	B-213-95	09/06/17	PES	ESC	95	-37.6	S	–	–	–	–	0.000326 U	0.000353 U	0.000451 U	0.000342 U	0.000451 U	0.000246 U	0.000374 U	0.000392 U	0.000378 U	0.000915 U
	B-213-105	09/06/17	PES	ESC	105	-47.6	S	–	–	–	–	0.000303 U	0.000329 U	0.000419 U	0.000318 U	0.000419 U	0.000229 U	0.000348 U	0.000364 U	0.000352 U	0.000851 U
	B-906-110	09/06/17	PES	ESC	105 (dup)	-47.6	S	–	–	–	–	0.000303 U	0.000328 U	0.000419 U	0.000318 U	0.000419 U	0.000228 U	0.000348 U	0.000364 U	0.000351 U	0.000851 U
	B-213-115	09/06/17	PES	ESC	115	-57.6	S	–	–	–	–	0.000324 U	0.000351 U	0.000448 U	0.000340 U	0.000448 U	0.000244 U	0.000372 U	0.000389 U	0.000375 U	0.000909 U
	B-213-125	09/06/17	PES	ESC	125	-67.6	S	–	–	–	–	0.000391 U	0.000423 U	0.000540 U	0.000410 U	0.000540 U	0.000295 U	0.000448 U	0.000469 U	0.000453 U	0.00110 U
B-214	B-214-15	09/07/17	PES	ESC	15	42.4	V	–	–	–	–	0.000283 U	0.000307 U	0.000391 U	0.000297 U	0.000391 U	0.000213 U	0.000325 U	0.000340 U	0.000328 U	0.000795 U
	B-214-25	09/07/17	PES	ESC	25	32.4	S	–	–	–	–	0.000279 U	0.000302 U	0.000386 U	0.000293 U	0.000386 U	0.000210 U	0.000320 U	0.000335 U	0.000323 U	0.000783 U
	B-214-35	09/07/17	PES	ESC	35	22.4	S	–	–	–	–	0.000287 U	0.000311 U	0.000396 U	0.000301 U	0.000396 U	0.000216 U	0.000329 U	0.000344 U	0.000332 U	0.000805 U
	B-214-45	09/07/17	PES	ESC	45	12.4	S	–	–	–	–	0.000281 U	0.000304 U	0.000388 U	0.000295 U	0.000388 U	0.000212 U	0.000322 U	0.000337 U	0.000326 U	0.000789 U
	B-214-55	09/07/17	PES	ESC	55	2.4	S	–	–	–	–	0.000293 U	0.000318 U	0.000405 U	0.000308 U	0.000405 U	0.000221 U	0.000336 U	0.000352 U	0.000340 U	0.000823 U
	B-214-65	09/07/17	PES	ESC	65	-7.6	S	–	–	–	–	0.000340 U	0.000368 U	0.000470 U	0.000356 U	0.000470 U	0.000256 U	0.000390 U	0.000408 U	0.000394 U	0.000954 U
	B-214-75	09/07/17	PES	ESC	75	-17.6	S	–	–	–	–	0.000293 U	0.000318 U	0.000405 U	0.000308 U	0.000405 U	0.000221 U	0.000337 U	0.000352 U	0.000340 U	0.000823 U
	B-214-85	09/07/17	PES	ESC	85	-27.6	S	–	–	–	–	0.000317 U	0.000344 U	0.000439 U	0.000333 U	0.000439 U	0.000239 U	0.000364 U	0.000381 U	0.000368 U	0.000891 U
	B-908-100	09/07/17	PES	ESC	85 (dup)	-27.6	S	–	–	–	–	0.000295 U	0.000320 U	0.000408 U	0.000310 U	0.000408 U	0.000222 U	0.000339 U	0.000354 U	0.000342 U	0.000828 U
	B-214-95	09/07/17	PES	ESC	95	-37.6	S	–	–	–	–	0.000290 U	0.000314 U	0.000401 U	0.000304 U	0.000401 U	0.000218 U	0.000333 U	0.000348 U	0.000336 U	0.000813 U
	B-214-105	09/07/17	PES	ESC	105	-47.6	S	–	–	–	–	0.000334 U	0.000362 U	0.000462 U	0.000351 U	0.000462 U	0.000252 U	0.000383 U	0.000401 U	0.000387 U	0.000938 U
	B-214-115	09/11/17	PES	ESC	115	-57.6	S	–	–	–	–	0.000322 U	0.000349 U	0.000445 U	0.000338 U	0.000445 U	0.000243 U	0.000370 U	0.000387 U	0.000373 U	0.000904 U
	B-214-120	09/11/17	PES	ESC	120	-62.6	S	–	–	–	–	0.000312 U	0.000338 U	0.000431 U	0.000327 U	0.000431 U	0.000235 U	0.000358 U	0.000374 U	0.000361 U	0.000875 U
B-215	B-215-15	09/12/17	PES	ESC	15	39.0	V	–	–	–	–	0.000286 U	0.000310 U	0.000396 U	0.000300 U	0.000396 U	0.000216 U	0.000329 U	0.000344 U	0.000332 U	0.000804 U
	B-215-25	09/12/17	PES	ESC	25	29.0	S	–	–	–	–	0.000283 U	0.000306 U	0.000391 U	0.000296 U	0.000391 U	0.000213 U	0.000324 U	0.000339 U	0.000327 U	0.000793 U
	B-215-35	09/12/17	PES	ESC	35	19.0	S	–	–	–	–	0.000311 U	0.000337 U	0.000430 U	0.000327 U	0.000430 U	0.000235 U	0.000357 U	0.000374 U	0.000361 U	0.000874 U
	B-215-45	09/12/17	PES	ESC	45	9.0	S	–	–	–	–	0.000281 U	0.000304 U	0.000388 U	0.000295 U	0.000388 U	0.000212 U	0.000322 U	0.000337 U	0.000326 U	0.000788 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
B-215 (continued)	B-215-55	09/12/17	PES	ESC	55	-1.1	S	–	–	–	–	0.000292 U	0.000317 U	0.000404 U	0.000307 U	0.000404 U	0.000220 U	0.000336 U	0.000351 U	0.000339 U	0.000821 U
	B-215-65	09/12/17	PES	ESC	65	-11.1	S	–	–	–	–	0.00755 U	0.00818 U	0.0104 U	0.00791 U	0.0104 U	0.00570 U	**0.0242 J**	0.00906 U	0.00875 U	0.0212 U
	B-215-75	09/12/17	PES	ESC	75	-21.1	S	–	–	–	–	0.000291 U	0.000315 U	0.000403 U	0.000305 U	0.000403 U	0.000219 U	0.000334 U	0.000350 U	0.000337 U	0.000817 U
	B-215-85	09/13/17	PES	ESC	85	-31.1	S	–	–	–	–	0.000318 U	0.000345 U	0.000440 U	0.000334 U	0.000440 U	0.000240 U	0.000365 U	0.000382 U	0.000369 U	0.000893 U
	B-909-115	09/13/17	PES	ESC	85 (dup)	-31.1	S	–	–	–	–	0.000296 U	0.000320 U	0.000409 U	0.000310 U	0.000409 U	0.000223 U	0.000340 U	0.000355 U	0.000343 U	0.000830 U
	B-215-95	09/13/17	PES	ESC	95	-41.1	S	–	–	–	–	0.000316 U	0.000342 U	0.000437 U	0.000332 U	0.000437 U	0.000238 U	0.000363 U	0.000379 U	0.000366 U	0.000887 U
B-268	B-268-1	03/17/20	PES	PACE	1	–	V	1.05 U	–	–	–	0.000620 U	0.000341 U	0.000484 U	0.00110 U	0.000837 U	0.000713 U	0.000620 U	0.000868 U	0.000775 U	0.00633 U
B-269	B-269-1.5	03/17/20	PES	PACE	1.5	–	V	0.926 U	–	–	–	0.000546 U	0.000300 U	0.000426 U	0.000964 U	0.000737 U	0.000628 U	0.000546 U	0.000764 U	0.000683 U	0.00557 U
B-270	B-270-2	03/17/20	PES	PACE	2	–	V	**82.5**	**114**	4.03 U	**114**	0.000605 U	0.000333 U	0.000472 U	0.00107 U	0.000816 U	0.000695 U	0.000605 U	0.000847 U	0.000756 U	0.00617 U
B-271	B-271-1	03/17/20	PES	PACE	1	–	V	0.910 U	–	–	–	0.000537 U	0.000295 U	0.000419 U	0.000948 U	0.000725 U	0.000617 U	0.000537 U	0.000752 U	0.000671 U	0.00548 U
B-272	B-272-1	03/17/20	PES	PACE	1	–	V	1.00 U	–	–	–	0.000590 U	0.000324 U	0.000460 U	0.00104 U	0.000796 U	0.000678 U	0.000590 U	0.000825 U	0.000737 U	0.00601 U
	B-272-6	03/17/20	PES	PACE	6	–	V	1.05 U	–	–	–	0.000619 U	0.000340 U	0.000483 U	0.00109 U	0.000835 U	0.000712 U	0.000619 U	0.000866 U	0.000773 U	0.00631 U
B-273	B-273-1	03/17/20	PES	PACE	1	–	V	0.952 U	–	–	–	0.000561 U	0.000309 U	0.000438 U	0.000991 U	0.000758 U	0.000645 U	0.000561 U	0.000786 U	0.000701 U	0.00572 U
	B-273-3	03/17/20	PES	PACE	3	–	V	0.937 U	–	–	–	0.000553 U	0.000304 U	0.000431 U	0.000976 U	0.000746 U	0.000636 U	0.000553 U	0.000774 U	0.000691 U	0.00564 U
	B-273-6	03/17/20	PES	PACE	6	–	V	**10.7**	–	–	–	0.00111 U	0.000609 U	0.000864 U	0.00196 U	0.00150 U	0.00127 U	0.00111 U	0.00155 U	0.00139 U	0.0113 U
B-274	B-274-1	03/17/20	PES	PACE	1	–	V	0.954 U	–	–	–	0.000562 U	0.000309 U	0.000439 U	0.000993 U	0.000759 U	0.000647 U	0.000562 U	0.000787 U	0.000703 U	0.00574 U
	B-274-3	03/17/20	PES	PACE	3	–	V	0.918 U	–	–	–	0.000541 U	0.000298 U	0.000422 U	0.000956 U	0.000731 U	0.000623 U	0.000541 U	0.000758 U	0.000677 U	0.00552 U
	B-274-6	03/17/20	PES	PACE	6	–	V	**10.7**	–	–	–	0.000889 U	0.000490 U	0.000694 U	0.00158 U	0.00120 U	0.00102 U	0.000889 U	0.00124 U	0.00111 U	0.00906 U
B-275	B-275-1	03/17/20	PES	PACE	1	–	V	0.995 U	–	–	–	0.000587 U	0.000323 U	0.000458 U	0.00104 U	0.000792 U	0.000675 U	0.000587 U	0.000822 U	0.000734 U	0.00599 U
	B-275-6	03/17/20	PES	PACE	6	–	V	1.33 U	–	–	–	0.000926 U	0.000509 U	0.000723 U	0.00163 U	0.00125 U	0.00106 U	0.000926 U	0.00130 U	0.00116 U	0.00945 U
	B-275-9	03/17/20	PES	PACE	9	–	S	1.30 U	–	–	–	0.000769 U	0.000423 U	0.000600 U	0.00136 U	0.00104 U	0.000885 U	0.000769 U	0.00108 U	0.000962 U	0.00785 U
	B-275-10	03/17/20	PES	PACE	10	–	S	0.932 U	–	–	–	0.000550 U	0.000302 U	0.000429 U	0.000971 U	0.000742 U	0.000632 U	0.000550 U	0.000770 U	0.000687 U	0.00561 U
B-276	B-276-1	03/17/20	PES	PACE	1	–	V	1.03 U	–	–	–	0.000922 U	0.000507 U	0.000720 U	0.00163 U	0.00125 U	0.00106 U	0.000922 U	0.00129 U	0.00115 U	0.00941 U
	B-276-7	03/17/20	PES	PACE	7	–	V	0.938 U	–	–	–	0.000553 U	0.000304 U	0.000431 U	0.000977 U	0.000747 U	0.000636 U	0.000553 U	0.000774 U	0.000691 U	0.00564 U
	B-970-6	03/17/20	PES	PACE	7 (dup)	–	V	0.938 U	–	–	–	0.000553 U	0.000304 U	0.000432 U	0.000977 U	0.000747 U	0.000636 U	0.000553 U	0.000775 U	0.000692 UJ	0.00564 U
	B-276-11	03/17/20	PES	PACE	11	–	S	0.991 U	–	–	–	0.000584 U	0.000321 U	0.000456 U	0.00103 U	0.000788 U	0.000672 U	0.000584 U	0.000818 U	0.000730 UJ	0.00596 U
B-277	B-277-1	03/18/20	PES	PACE	1	–	V	1.07 U	–	–	–	0.000630 U	0.000347 U	0.000492 U	0.00111 U	0.000851 U	0.000725 U	0.000630 U	0.000882 U	0.000788 U	0.00643 U
	B-277-3	03/18/20	PES	PACE	3	–	V	0.932 U	–	–	–	0.000549 U	0.000302 U	0.000429 U	0.000970 U	0.000742 U	0.000632 U	0.000549 U	0.000769 U	0.000687 U	0.00560 U
	B-277-5	03/18/20	PES	PACE	5	–	V	1.40 U	–	–	–	0.000826 U	0.000454 U	0.000644 U	0.00146 U	0.00111 U	0.000950 U	0.000826 U	0.00116 U	0.00103 U	0.00842 U
	B-277-9.5	03/18/20	PES	PACE	9.5	–	V	**1.72 J**	–	–	–	0.00119 U	0.000654 U	0.000927 U	0.00209 U	0.00160 U	0.00137 U	0.00119 U	0.00166 U	0.00149 U	0.0121 U
	B-277-11	03/18/20	PES	PACE	11	–	S	**1.13 J**	–	–	–	0.000540 U	0.000297 U	0.000421 U	0.000953 U	0.000728 U	0.000620 U	0.000540 U	0.000755 U	0.000674 U	0.00550 U
B-278	B-278-3	03/18/20	PES	PACE	3	–	V	0.946 U	–	–	–	0.000558 U	0.000307 U	0.000435 U	0.000986 U	0.000753 U	0.000642 U	0.000558 U	0.000781 U	0.000698 U	0.00569 U
	B-278-6	03/18/20	PES	PACE	6	–	V	0.940 U	–	–	–	0.000554 U	0.000305 U	0.000432 U	0.000979 U	0.000749 U	0.000638 U	0.000554 U	0.000776 U	0.000693 U	0.00566 U
B-279	B-279-3	03/18/20	PES	PACE	3	–	V	0.962 U	–	–	–	0.000567 U	0.000312 U	0.000442 U	0.00100 U	0.000766 U	0.000652 U	0.000567 U	0.000794 U	0.000709 U	0.00578 U
	B-279-5	03/18/20	PES	PACE	5	–	V	0.948 U	–	–	–	0.000559 U	0.000308 U	0.000436 U	0.000987 U	0.000755 U	0.000643 U	0.000559 U	0.000783 U	0.000699 U	0.00570 U
	B-279-10	03/18/20	PES	PACE	10	–	V	0.921 U	–	–	–	0.000543 U	0.000299 U	0.000424 U	0.000959 U	0.000733 U	0.000625 U	0.000543 U	0.000761 U	0.000679 U	0.00554 U
B-280	B-280-4.5	03/18/20	PES	PACE	4.5	–	V	0.878 U	–	–	–	0.000518 U	0.000285 U	0.000404 U	0.000915 U	0.000699 U	0.000596 U	0.000518 U	0.000725 U	0.000647 U	0.00528 U
	B-280-6	03/18/20	PES	PACE	6	–	V	0.923 U	–	–	–	0.000544 U	0.000299 U	0.000424 U	0.000961 U	0.000734 U	0.000626 U	0.000544 U	0.000762 U	0.000680 U	0.00555 U
B-281	B-281-2	03/18/20	PES	PACE	2	–	V	0.887 U	–	–	–	0.000523 U	0.000287 U	0.000408 U	0.000923 U	0.000706 U	0.000601 U	0.000523 U	0.000732 U	0.000653 U	0.00533 U
	B-281-5	03/18/20	PES	PACE	5	–	V	0.961 U	–	–	–	0.000567 U	0.000312 U	0.000442 U	0.00100 U	0.000765 U	0.000652 U	0.000567 U	0.000793 U	0.000708 U	0.00578 U
B-282	B-282-2	03/18/20	PES	PACE	2	–	V	0.967 U	–	–	–	0.000570 U	0.000314 U	0.000445 U	0.00101 U	0.000770 U	0.000656 U	0.000570 U	0.000798 U	0.000713 U	0.00581 U
	B-282-4	03/18/20	PES	PACE	4	–	V	0.937 U	–	–	–	0.000552 U	0.000304 U	0.000431 U	0.000975 U	0.000746 U	0.000635 U	0.000552 U	0.000773 U	0.000690 U	0.00563 U
	B-971-5	03/18/20	PES	PACE	4 (dup)	–	V	0.903 U	–	–	–	0.000532 U	0.000293 U	0.000415 U	0.000940 U	0.000718 U	0.000612 U	0.000532 U	0.000745 U	0.000665 U	0.00543 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	**–**	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	**–**	**0.030**	**1.5E-07**
B-283	B-283-0.5	08/19/20	PES	PACE	0.5	–	V	–	–	–	–	0.00114 UJ	0.00111 U	0.000836 U	0.000718 U	0.000907 U	0.000590 U	0.000729 U	0.000973 U	0.00882 UJ	0.00195 U
B-284	B-284-1	08/19/20	PES	PACE	1	–	V	–	–	–	–	0.00114 UJ	0.00111 U	0.000834 U	0.000716 U	0.000905 U	0.000589 U	0.000727 U	0.000971 U	0.00880 UJ	0.00194 U
B-285	B-285-1	08/19/20	PES	PACE	1	–	V	–	–	–	–	0.00124 UJ	0.00121 U	0.000908 U	0.000779 U	0.000985 U	0.000641 U	0.000791 U	0.00106 U	0.00958 UJ	0.00212 U
B-286	B-286-0.5	08/19/20	PES	PACE	0.5	–	V	–	–	–	–	0.00253 UJ	0.00245 U	0.00185 U	0.00159 U	0.00200 U	0.00131 U	0.00162 U	0.00215 U	0.0195 UJ	0.00431 U
B-287	B-287-1	08/19/20	PES	PACE	1	–	V	–	–	–	–	0.00247 UJ	0.00240 U	0.00181 U	0.00155 U	0.00196 U	0.00128 U	0.00157 U	0.00210 U	0.0191 UJ	0.00420 U
B-288	B-288-1	08/19/20	PES	PACE	1	–	V	–	–	–	–	0.00505 UJ	0.00490 U	0.00369 U	0.00317 U	0.00401 U	0.00261 U	0.00322 U	0.00430 U	0.0390 UJ	0.00861 U
B-289	B-289-0.5	08/19/20	PES	PACE	0.5	–	V	–	–	–	–	0.00412 UJ	0.00403 U	0.00303 U	0.00261 U	0.00329 U	0.00214 U	0.00264 U	0.00353 U	0.0320 UJ	0.00707 U
B-290	B-290-1	08/20/20	PES	PACE	1	–	V	–	–	–	–	0.00150 UJ	0.00145 U	0.00110 U	0.000942 U	0.00119 U	0.000774 U	0.000956 U	0.00127 U	0.0116 UJ	0.00255 U
B-291	B-291-1	08/20/20	PES	PACE	1	–	V	–	–	–	–	0.00129 UJ	0.00126 U	0.000942 U	0.000809 U	0.00102 U	0.000666 U	0.000821 U	0.00110 U	0.00994 UJ	0.00219 U
B-292	B-292-3	08/22/20	PES	PACE	3	–	V	–	–	–	–	0.00119 U	0.00116 U	0.000875 U	0.000751 U	0.000949 U	0.000618 U	0.000763 U	0.00102 U	0.00922 UJ	0.00204 U
	B-292-6	08/22/20	PES	PACE	6	–	V	–	–	–	–	0.00123 U	0.00120 U	0.000904 U	0.000776 U	0.000980 U	0.000638 U	0.000788 U	0.00105 U	0.00953 UJ	0.00211 U
	B-292-9	08/22/20	PES	PACE	9	–	V	–	–	–	–	0.00112 U	0.00109 U	0.000821 U	0.000706 U	0.000891 U	0.000580 U	0.000716 U	0.000956 U	0.00866 UJ	0.00191 U
	B-292-12	08/22/20	PES	PACE	12	–	V	–	–	–	–	0.00124 U	0.00121 U	0.000912 U	0.000784 U	0.000990 U	0.000645 U	0.000795 U	0.00106 U	0.00962 UJ	0.00213 U
B-293	B-293-1	08/26/20	PES	PACE	1	–	V	–	–	–	–	0.00105 U	0.00102 UJ	0.000770 U	0.000662 U	0.000836 U	0.000544 UJ	0.000672 UJ	0.000897 U	0.00813 UJ	0.00180 U
B-294	B-294-1	08/26/20	PES	PACE	1	–	V	–	–	–	–	0.00133 U	0.00130 UJ	0.000976 U	0.000838 U	0.00106 U	0.000689 UJ	0.000851 UJ	0.00114 U	0.0103 UJ	0.00227 U
	B-294-2	08/26/20	PES	PACE	2	–	V	–	–	–	–	0.00275 U	0.00268 UJ	0.00203 U	0.00173 U	0.00218 U	0.00143 UJ	0.00176 UJ	0.00234 U	0.0213 UJ	0.00470 U
	B-294-6	08/26/20	PES	PACE	6	–	V	–	–	–	–	0.00271 U	0.00263 UJ	0.00198 U	0.00170 U	0.00215 U	0.00140 UJ	0.00173 UJ	0.00232 U	0.0209 UJ	0.00463 U
	B-294-10	08/26/20	PES	PACE	10	–	S	–	–	–	–	0.00128 U	0.00124 UJ	0.000935 U	0.000803 U	0.00101 U	0.000661 UJ	0.000816 UJ	0.00109 U	0.00987 UJ	0.00218 U
B-295	B-295-1	08/26/20	PES	PACE	1	–	V	–	–	–	–	0.00114 U	0.00111 UJ	0.000837 U	0.000719 U	0.000908 U	0.000591 UJ	0.000729 UJ	0.000974 U	0.00882 UJ	0.00195 U
	B-295-3	08/26/20	PES	PACE	3	–	V	–	–	–	–	0.00169 U	0.00165 UJ	0.00124 U	0.00107 U	0.00135 U	0.000876 UJ	0.00108 UJ	0.00144 U	0.0131 UJ	0.00289 U
	B-295-7	08/26/20	PES	PACE	7	–	V	–	–	–	–	0.00142 U	0.00138 UJ	0.00104 U	0.000895 U	0.00113 U	0.000736 UJ	0.000908 UJ	0.00121 U	0.0110 UJ	0.00243 U
	B-295-10	08/26/20	PES	PACE	10	–	S	–	–	–	–	0.00133 U	0.00130 UJ	0.000977 U	0.000839 U	0.00106 U	0.000690 UJ	0.000852 UJ	0.00114 U	0.0103 UJ	0.00228 U
B-296	B-296-1	08/26/20	PES	PACE	1	–	V	–	–	–	–	0.00108 U	0.00105 UJ	0.000790 U	0.000678 U	0.000857 U	0.000558 UJ	0.000688 UJ	0.000919 U	0.00833 UJ	0.00184 U
B-297	B-297-1	08/26/20	PES	PACE	1	–	V	–	–	–	–	0.00117 U	0.00114 UJ	0.000856 U	0.000735 U	0.000929 U	0.000605 UJ	0.000747 UJ	0.000997 U	0.00903 UJ	0.00200 U
	B-297-3	08/26/20	PES	PACE	3	–	V	–	–	–	–	0.00109 U	0.00106 UJ	0.000798 U	0.000686 U	0.000866 U	0.000564 UJ	0.000696 UJ	0.000929 U	0.00842 UJ	0.00186 U
	B-500-1	08/26/20	PES	PACE	3 (dup)	–	V	–	–	–	–	0.00111 UJ	0.00108 U	0.000814 U	0.000700 U	0.000884 U	0.000575 U	0.000710 U	0.000948 U	0.00859 UJ	0.00190 U
	B-297-5	08/26/20	PES	PACE	5	–	V	–	–	–	–	0.00108 UJ	0.00105 U	0.000794 U	0.000682 U	0.000862 U	0.000561 U	0.000692 U	0.000924 U	0.00838 UJ	0.00185 U
B-298	B-298-5	08/26/20	PES	PACE	5	–	V	–	–	–	–	0.00100 UJ	0.000974 U	0.000733 U	0.000630 U	0.000796 U	0.000518 U	0.000639 U	0.000854 U	0.00773 UJ	0.00171 U
	B-298-6	08/26/20	PES	PACE	6	–	V	–	–	–	–	0.00120 UJ	0.00117 U	0.000882 U	0.000757 U	0.000957 U	0.000623 U	0.000769 U	0.00103 U	0.00930 UJ	0.00205 U
B-299	B-299-2	02/01/21	PES	PACE	2	–	V	1.12 U	–	–	–	0.00125 U	0.00122 U	0.000917 UJ	0.000788 U	0.000995 U	0.000648 U	0.000800 U	0.00107 U	0.00968 U	0.00214 UJ
	B-299-5.5	02/01/21	PES	PACE	5.5	–	V	1.01 U	–	–	–	0.00113 U	0.00110 U	0.000828 UJ	0.000712 U	0.000899 U	0.000585 U	0.000722 U	0.000964 U	0.00874 U	0.00193 UJ
	B-1003-10	02/01/21	PES	PACE	5.5 (dup)	–	V	1.05 U	–	–	–	0.00118 U	0.00114 U	0.000861 UJ	0.000740 U	0.000935 U	0.000609 U	0.000751 U	0.00100 U	0.00909 U	0.00201 UJ
B-300	B-300-2.5	02/01/21	PES	PACE	2.5	–	V	1.12 U	–	–	–	0.00125 U	0.00122 U	0.000919 UJ	0.000789 U	0.000996 U	0.000649 U	0.000801 U	0.00107 U	0.00969 U	0.00214 UJ
	B-300-5.5	02/01/21	PES	PACE	5.5	–	V	1.09 U	–	–	–	0.00122 U	0.00119 U	0.000896 UJ	0.000770 U	0.000972 U	0.000633 U	0.000782 U	0.00104 U	0.00945 U	0.00209 UJ
B-301	B-301-2	02/01/21	PES	PACE	2	–	V	1.09 U	–	–	–	0.00122 U	0.00118 U	0.000891 UJ	0.000766 U	0.000967 U	0.000630 U	0.000777 U	0.00104 U	0.00940 U	0.00208 UJ
	B-301-5	02/01/21	PES	PACE	5	–	V	1.15 U	–	–	–	0.00128 U	0.00125 U	0.000939 UJ	0.000807 U	0.00102 U	0.000664 U	0.000819 U	0.00109 U	0.00991 U	0.00219 UJ
B-302	B-302-2	02/01/21	PES	PACE	2	–	V	1.06 U	–	–	–	0.00119 U	0.00116 U	0.000870 UJ	0.000747 U	0.000944 U	0.000615 U	0.000758 U	0.00101 U	0.00917 U	0.00203 UJ
	B-302-4	02/01/21	PES	PACE	4	–	V	1.21 U	–	–	–	0.00135 U	0.00132 U	0.000992 UJ	0.000852 U	0.00108 U	0.000701 U	0.000865 U	0.00115 U	0.0105 U	0.00231 UJ
BB-5	S-6	03/09/97	B&V	Unknown	15-17	34.0	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	S-10	03/09/97	B&V	Unknown	25-27	24.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
BB-7	S-4	04/06/97	B&V	Unknown	10-12	17.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	**–**	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	**–**	**0.030**	**1.5E-07**
BB-8 (13.6 to 3.6)	S-8	06/06/97	B&V	Unknown	20-22	23.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
BB-10	S-6	08/29/97	B&V	Unknown	15-17	42.0	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
BB-12	S-3	03/18/98	B&V	Unknown	15-16.5	18.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	S-14	03/18/98	B&V	Unknown	45-46.5	-11.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
BB-13	S-10	03/19/98	B&V	Unknown	25-27.5	1.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	S-16	03/19/98	B&V	Unknown	40-41.5	-13.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
BB-14	S-2	03/03/98	B&V	Unknown	5-6.5	21.3	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	S-5	03/03/98	B&V	Unknown	12.5-14	14.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	S-9	03/03/98	B&V	Unknown	22.5-24	4.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	S-12	03/03/98	B&V	Unknown	30-31.5	-4.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
CHB-07	CHB-07-12.5-13.5	04/14/05	CH2M	ARI	12.5-13.5	16.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	CHB-07-5.0-7.0	04/14/08	CH2M	ARI	5-7	23.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
CHB-08	CHB-08-15.0-16.0	04/15/08	CH2M	ARI	15-16	14.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
CHB-09	CHB-09-20.0-21.5	04/16/08	CH2M	ARI	20-21.5	15.4	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	CHB-09-25.0-26.5	04/16/08	CH2M	ARI	25-26.5	10.4	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
GEI-MW-1 (-9.7 to -29.7)	MW-1-1-2.5	08/22/14	GEI	Fremont	1	29.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
GEI-MW-2 (4.0 to -6.0)	MW-2-2-5.0	08/23/14	GEI	Fremont	5	26.6	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW-2-4-10.0	08/23/14	GEI	Fremont	10	21.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW-2-8-20.0	08/23/14	GEI	Fremont	20	11.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
GEI-MW-3 (-18.7 to -28.7)	MW-3-4-10.0	08/23/14	GEI	Fremont	10	20.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW-3-10-50.0	08/23/14	GEI	Fremont	50	-19.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
GEI-4	GEI-4-2-5.0	08/23/14	GEI	Fremont	5	26.0	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	GEI-4-5-12.5	08/23/14	GEI	Fremont	12.5	18.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-1 (SCLB-3)	RS3-2.5	03/15/93	EPJ	OnSite	2.5	37.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS3-7.5	03/15/93	EPJ	OnSite	7.5	32.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS3-17.5	03/15/93	EPJ	OnSite	17.5	22.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS3-22.5/RS3-27.5 (Comp)	03/15/93	EPJ	OnSite	22.5-27.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS3-32.5	03/15/93	EPJ	OnSite	32.5	7.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS3-37.5	03/15/93	EPJ	OnSite	37.5	2.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-2 (SCLB-4)	RS4-2.5	03/15/93	EPJ	OnSite	2.5	37.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS4-7.5	03/15/93	EPJ	OnSite	7.5	32.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS4-12.5/RS4-17.5	03/15/93	EPJ	OnSite	12.5-17.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS4-22.5/RS4-27.5 (Comp)	03/15/93	EPJ	OnSite	22.5-27.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS4-37.5	03/15/93	EPJ	OnSite	37.5	2.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-3 (SCLB-5)	RS5-2.5/RS5-7.5 (Comp)	03/16/93	EPJ	OnSite	2.5-7.5	–	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS5-12.5/RS5-17.5 (Comp)	03/16/93	EPJ	OnSite	12.5-17.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS5-17.5	03/16/93	EPJ	OnSite	17.5	21.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS5-22.5	03/16/93	EPJ	OnSite	22.5	16.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS5-32.5	03/16/93	EPJ	OnSite	32.5	6.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS5-37.5	03/16/93	EPJ	OnSite	37.5	1.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	**–**	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	**–**	**0.030**	**1.5E-07**
MW-4 (SCLB-6)	RS6-2.5	03/17/93	EPJ	OnSite	2.5	37.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS6-7.5	03/17/93	EPJ	OnSite	7.5	32.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS6-12.5	03/17/93	EPJ	OnSite	12.5	27.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS6-17.5/RS6-22.5 (Comp)	03/17/93	EPJ	OnSite	17.5-22.5	–	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS6-27.5	03/17/93	EPJ	OnSite	27.5	12.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-5 (SCLB-7)	RS7-2.5	03/17/93	EPJ	OnSite	2.5	37.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS7-7.5	03/17/93	EPJ	OnSite	7.5	32.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS7-12.5	03/17/93	EPJ	OnSite	12.5	27.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS7-17.5	03/17/93	EPJ	OnSite	17.5	22.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS7-22.5	03/17/93	EPJ	OnSite	22.5	17.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-6	MW6-25	10/11/93	Retec	ARI	25	13.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-7	MW7-16.5	10/11/93	Retec	ARI	16.5	18.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW7-18.5	10/11/93	Retec	ARI	18.5	16.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-8 (28.7 to 14.2)	MW8-20	10/18/93	Retec	AAL	20	13.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-9 (33.7 to 18.7)	MW9-17.5	10/18/93	Retec	AAL	17.5	23.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-10	MW10-17.5	10/19/93	Retec	AAL	17.5	20.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW102 (B102) (-65.8 to -75.8)	B102-20	07/17/12	SES	F&BI	20	29.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-30	07/17/12	SES	F&BI	30	19.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-38	07/17/12	SES	F&BI	38	11.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-40	07/17/12	SES	F&BI	40	9.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-49	07/17/12	SES	F&BI	49	0.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-60	07/17/12	SES	F&BI	60	-10.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-70	07/18/12	SES	F&BI	70	-20.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-80	07/19/12	SES	F&BI	80	-30.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-90	07/19/12	SES	F&BI	90	-40.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-100	07/20/12	SES	F&BI	100	-50.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-110	07/20/12	SES	F&BI	110	-60.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-120	07/23/12	SES	F&BI	120	-70.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW103 (B103) (-67.6 to -77.6)	B103-10	07/25/12	SES	F&BI	10	25.9	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-18	07/25/12	SES	F&BI	18	17.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-30	07/25/12	SES	F&BI	30	5.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-40	07/25/12	SES	F&BI	40	-4.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-45	07/25/12	SES	F&BI	45	-9.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-55	07/25/12	SES	F&BI	55	-19.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-62.5	07/26/12	SES	F&BI	62.5	-26.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-75	07/26/12	SES	F&BI	75	-39.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-83	07/26/12	SES	F&BI	83	-47.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-95	07/26/12	SES	F&BI	95	-59.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-105	07/27/12	SES	F&BI	105	-69.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-113	07/27/12	SES	F&BI	113	-77.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	**–**	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	**–**	**0.030**	**1.5E-07**
MW104 (B104)	B104-10	07/30/12	SES	F&BI	10	32.7	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(-76.3 to -86.3)	B104-20	07/30/12	SES	F&BI	20	22.7	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-30	07/30/12	SES	F&BI	30	12.7	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-35	07/30/12	SES	F&BI	35	7.7	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-50	07/30/12	SES	F&BI	50	-7.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-60	07/31/12	SES	F&BI	60	-17.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-69	07/31/12	SES	F&BI	69	-26.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-80	07/31/12	SES	F&BI	80	-37.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-90	08/01/12	SES	F&BI	90	-47.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-100	08/01/12	SES	F&BI	100	-57.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-110	08/01/12	SES	F&BI	110	-67.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-120	08/01/12	SES	F&BI	120	-77.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-130	08/01/12	SES	F&BI	130	-87.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW105 (B105)	B105-10	08/06/12	SES	F&BI	10	34.2	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(-85.8 to -95.8)	B105-20	08/06/12	SES	F&BI	20	24.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-30	08/06/12	SES	F&BI	30	14.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-40	08/08/12	SES	F&BI	40	4.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-50	08/08/12	SES	F&BI	50	-5.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-60	08/09/12	SES	F&BI	60	-15.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-70	08/09/12	SES	F&BI	70	-25.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-80	08/09/12	SES	F&BI	80	-35.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-90	08/10/12	SES	F&BI	90	-45.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-100	08/10/12	SES	F&BI	100	-55.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-110	08/10/12	SES	F&BI	110	-65.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-120	08/10/12	SES	F&BI	120	-75.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-130	08/10/12	SES	F&BI	130	-85.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-138	08/10/12	SES	F&BI	138	-93.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW106 (B106)	B106-10	08/14/12	SES	F&BI	10	42.0	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(-78.0 to -88.0)	B106-20	08/14/12	SES	F&BI	20	32.0	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-30	08/14/12	SES	F&BI	30	22.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-40	08/14/12	SES	F&BI	40	12.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-50	08/14/12	SES	F&BI	50	2.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-60	08/14/12	SES	F&BI	60	-8.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-70	08/15/12	SES	F&BI	70	-18.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-80	08/15/12	SES	F&BI	80	-28.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-90	08/15/12	SES	F&BI	90	-38.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-100	08/15/12	SES	F&BI	100	-48.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-110	08/15/12	SES	F&BI	110	-58.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-120	08/15/12	SES	F&BI	120	-68.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-130	08/15/12	SES	F&BI	130	-78.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-140	08/15/12	SES	F&BI	140	-88.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	**–**	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	**–**	**0.030**	**1.5E-07**
MW107 (B107)	B107-05	03/12/12	SES	F&BI	5	38.8	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(8.8 to -1.2)	B107-15	03/12/12	SES	F&BI	15	28.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B107-25	03/12/12	SES	F&BI	25	18.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B107-35	03/12/12	SES	F&BI	35	8.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B107-45	03/12/12	SES	F&BI	45	-1.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW108 (B108)	B108-15	12/14/12	SES	F&BI	15	17.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(-7.2 to -17.2)	B108-25	12/14/12	SES	F&BI	25	7.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B108-35	12/14/12	SES	F&BI	35	-2.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B108-45	12/14/12	SES	F&BI	45	-12.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B108-50	12/14/12	SES	F&BI	50	-17.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW109 (B109)	B109-05	04/12/12	SES	F&BI	5	30.0	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(0.0 to -10.0)	B109-15	04/12/12	SES	F&BI	15	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B109-25	04/12/12	SES	F&BI	25	10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B109-35	04/12/12	SES	F&BI	35	0.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B109-45	04/12/12	SES	F&BI	45	-10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW110 (B110)	B110-15	04/12/12	SES	F&BI	15	24.7	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(4.7 to -5.3)	B110-25	04/12/12	SES	F&BI	25	14.7	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B110-35	04/12/12	SES	F&BI	35	4.7	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B110-45	04/12/12	SES	F&BI	45	-5.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW111 (B111)	B111-10	05/12/12	SES	F&BI	10	26.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(-33.5 to -43.5)	B111-20	05/12/12	SES	F&BI	20	16.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B111-30	05/12/12	SES	F&BI	30	6.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B111-38	05/12/12	SES	F&BI	38	-1.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B111-50	05/12/12	SES	F&BI	50	-13.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B111-60	06/12/12	SES	F&BI	60	-23.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B111-70	06/12/12	SES	F&BI	70	-33.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B111-80	06/12/12	SES	F&BI	80	-43.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW112 (B112)	B112-10	11/12/12	SES	F&BI	10	47.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(-17.5 to -27.5)	B112-20	11/12/12	SES	F&BI	20	37.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B112-30	11/12/12	SES	F&BI	30	27.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B112-40	11/12/12	SES	F&BI	40	17.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B112-50	11/12/12	SES	F&BI	50	7.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B112-60	11/12/12	SES	F&BI	60	-2.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B112-75	11/12/12	SES	F&BI	75	-17.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B112-85	12/12/12	SES	F&BI	85	-27.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW113 (B113)	B113-10	12/18/12	SES	F&BI	10	22.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(-37.1 to -47.1)	B113-20	12/18/12	SES	F&BI	20	12.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B113-30	12/18/12	SES	F&BI	30	2.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B113-40	12/18/12	SES	F&BI	40	-7.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B113-50	12/18/12	SES	F&BI	50	-17.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW114 (B114)	B114-15	10/12/12	SES	F&BI	15	30.8	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(10.8 to 0.8)	B114-25	10/12/12	SES	F&BI	25	20.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B114-35	10/12/12	SES	F&BI	35	10.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	**–**	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	**–**	**0.030**	**1.5E-07**
MW114 (B114)	B114-40	10/12/12	SES	F&BI	40	5.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(continued)	B114-45	10/12/12	SES	F&BI	45	0.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW115 (B115)	B115-10	12/13/12	SES	F&BI	10	24.1	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(-0.9 to -10.9)	B115-15	12/13/12	SES	F&BI	15	19.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B115-25	12/13/12	SES	F&BI	25	9.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B115-35	12/13/12	SES	F&BI	35	-0.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B115-45	12/13/12	SES	F&BI	45	-10.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW116 (B116)	B116-15	07/12/12	SES	F&BI	15	16.4	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(-3.6 to -13.6)	B116-25	07/12/12	SES	F&BI	25	6.4	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B116-35	07/12/12	SES	F&BI	35	-3.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B116-45	07/12/12	SES	F&BI	45	-13.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW117 (B117)	B117-10	02/04/13	SES	F&BI	10	46.9	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(16.9 to 1.9)	B117-20	02/04/13	SES	F&BI	20	36.9	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B117-30	02/04/13	SES	F&BI	30	26.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B117-40	02/04/13	SES	F&BI	40	16.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B117-50	02/04/13	SES	F&BI	50	6.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW118 (B118)	B118-10	03/21/13	SES	F&BI	10	42.9	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(12.9 to 2.9)	B118-20	03/21/13	SES	F&BI	20	32.9	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B118-30	03/21/13	SES	F&BI	30	22.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B118-40	03/21/13	SES	F&BI	40	12.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B118-50	03/21/13	SES	F&BI	50	2.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW119 (B119)	B119-10	03/21/13	SES	F&BI	10	27.4	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(2.4 to -7.7)	B119-20	03/21/13	SES	F&BI	20	17.4	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B119-30	03/21/13	SES	F&BI	30	7.4	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B119-40	03/21/13	SES	F&BI	40	-2.7	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW120 (B120)	B120-20	12/16/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(0 to -10)	B120-30	12/16/13	SES	F&BI	30	10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B120-45	12/16/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW121 (B121)	B121-15	12/16/13	SES	F&BI	15	26.7	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(26.7 to 16.7)	B121-25	12/16/13	SES	F&BI	25	16.7	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW122 (B122)	B122-15	12/17/13	SES	F&BI	15	15.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(-75 to -89)	B122-25	12/17/13	SES	F&BI	25	5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B122-40	12/17/13	SES	F&BI	40	-10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B122-45	12/17/13	SES	F&BI	45	-15.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B122-50	12/17/13	SES	F&BI	50	-20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B122-60	12/17/13	SES	F&BI	60	-30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B122-70	12/17/13	SES	F&BI	70	-40.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B122-80	12/17/13	SES	F&BI	80	-50.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B122-100	12/17/13	SES	F&BI	100	-70.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW123 (B123)	B123-20	12/18/13	SES	F&BI	20	7.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(-42.5 to -52.5)																					

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	**–**	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	**–**	**0.030**	**1.5E-07**
MW124 (B124)	B124-10	12/19/13	SES	F&BI	10	46.2	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(-53.8 to -63.8)	B124-20	12/19/13	SES	F&BI	20	36.2	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B124-30	12/19/13	SES	F&BI	30	26.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B124-40	12/19/13	SES	F&BI	40	16.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B124-50	12/19/13	SES	F&BI	50	6.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B124-60	12/19/13	SES	F&BI	60	-3.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B124-70	12/19/13	SES	F&BI	70	-13.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B124-80	12/19/13	SES	F&BI	80	-23.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B124-90	12/19/13	SES	F&BI	90	-33.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B124-100	12/19/13	SES	F&BI	100	-43.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B124-110	12/19/13	SES	F&BI	110	-53.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B124-120	12/19/13	SES	F&BI	120	-63.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW125 (B125)	B125-15	12/20/13	SES	F&BI	15	28.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(28.6 to 13.6)	B125-20	12/20/13	SES	F&BI	20	23.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B125-25	12/20/13	SES	F&BI	25	18.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B125-30	12/20/13	SES	F&BI	30	13.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW126 (B126)	B126-20	12/30/13	SES	F&BI	20	10.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(-54.1 to -64.1)	B126-35	12/30/13	SES	F&BI	35	-4.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B126-45	12/30/13	SES	F&BI	45	-14.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B126-55	12/30/13	SES	F&BI	55	-24.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B126-60	12/31/13	SES	F&BI	60	-29.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B126-65	01/01/14	SES	F&BI	65	-34.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B126-75	01/02/14	SES	F&BI	75	-44.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B126-80	01/03/14	SES	F&BI	80	-49.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B126-85	01/04/14	SES	F&BI	85	-54.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B126-95	01/05/14	SES	F&BI	95	-64.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW127 (B127)	B127-15	12/31/13	SES	F&BI	15	24.0	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(-1.0 to -11.0)	B127-25	12/31/13	SES	F&BI	25	14.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B127-40	12/31/13	SES	F&BI	40	-1.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B127-45	12/31/13	SES	F&BI	45	-6.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B127-50	12/31/13	SES	F&BI	50	-11.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW128 (B128)	B128-25	01/09/14	SES	F&BI	25	2.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(-30.8 to -40.8)	B128-45	01/09/14	SES	F&BI	45	-17.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B128-65	01/09/14	SES	F&BI	65	-37.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-138	MW-138-15	09/12/17	PES	ESC	15	42.5	V	–	–	–	–	0.000314 U	0.000340 U	0.000434 U	0.000329 U	0.000434 U	0.000237 U	0.000360 U	0.000377 U	0.000364 U	0.000881 U
(-47.5 to -57.5)	MW-138-25	09/12/17	PES	ESC	25	32.5	S	–	–	–	–	0.000304 U	0.000329 U	0.000420 U	0.000319 U	0.000420 U	0.000229 U	0.000349 U	0.000365 U	0.000352 U	0.000853 U
	MW-138-35	09/12/17	PES	ESC	35	22.5	S	–	–	–	–	0.000282 U	0.000306 U	0.000390 U	0.000296 U	0.000390 U	0.000213 U	0.000324 U	0.000339 U	0.000327 U	0.000792 U
	MW-138-45	09/12/17	PES	ESC	45	12.5	S	–	–	–	–	0.000279 U	0.000302 U	0.000386 U	0.000293 U	0.000386 U	0.000210 U	0.000320 U	0.000335 U	0.000323 U	0.000783 U
	MW-138-56	09/12/17	PES	ESC	56	1.5	S	–	–	–	–	0.000297 U	0.000322 U	0.000411 U	0.000312 U	0.000411 U	0.000224 U	0.000341 U	0.000357 U	0.000344 U	0.000833 U
	MW-138-65	09/13/17	PES	ESC	65	-7.5	S	–	–	–	–	0.000286 U	0.000309 U	0.000395 U	0.000300 U	0.000395 U	0.000215 U	0.000328 U	0.000343 U	0.000331 U	0.000801 U
	B-910-90	09/13/17	PES	ESC	65 (dup)	-7.5	S	–	–	–	–	0.000306 U	0.000331 U	0.000423 U	0.000321 U	0.000423 U	0.000231 U	0.000351 U	0.000367 U	0.000355 U	0.000859 U
	MW-138-75	09/13/17	PES	ESC	75	-17.5	S	–	–	–	–	0.000291 U	0.000315 U	0.000402 U	0.000305 U	0.000402 U	0.000219 U	0.000334 U	0.000349 U	0.000337 U	0.000816 U
	MW-138-85	09/13/17	PES	ESC	85	-27.5	S	–	–	–	–	0.000317 U	0.000344 U	0.000439 U	0.000333 U	0.000439 U	0.000239 U	0.000364 U	0.000381 U	0.000368 U	0.000891 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
MW-138 (continued)	MW-138-95	09/13/17	PES	ESC	95	-37.5	S	–	–	–	–	0.000288 U	0.000312 U	0.000398 U	0.000302 U	0.000398 U	0.000217 U	0.000331 U	0.000346 U	0.000334 U	0.000808 U
	MW-138-105	09/13/17	PES	ESC	105	-47.5	S	–	–	–	–	0.000328 U	0.000356 U	0.000454 U	0.000345 U	0.000454 U	0.000248 U	0.000377 U	0.000394 U	0.000381 U	0.000922 U
	MW-138-115	09/14/17	PES	ESC	115	-57.5	S	–	–	–	–	0.000306 U	0.000331 U	0.000423 U	0.000321 U	0.000423 U	0.000231 U	0.000351 U	0.000367 U	0.000354 U	0.000858 U
MW-140 (-78.9 to -88.9)	MW-140-15	08/30/17	PES	ESC	15	35.6	V	–	–	–	–	0.000301 U	0.000326 U	0.000416 U	0.000316 U	0.000416 U	0.000227 U	0.000346 U	0.000361 U	0.000349 U	0.000845 U
	MW-140-25	08/30/17	PES	ESC	25	25.6	S	–	–	–	–	0.000286 U	0.000310 U	0.000396 U	0.000300 U	0.000396 U	0.000216 U	0.000329 U	0.000344 U	0.000332 U	0.000804 U
	MW-140-35	08/30/17	PES	ESC	35	15.6	S	–	–	–	–	0.00769 U	0.00833 U	0.0106 U	0.00806 U	0.0106 U	0.00580 U	0.00883 U	0.00923 U	0.00891 U	0.0216 U
	MW-140-45	08/30/17	PES	ESC	45	5.6	S	–	–	–	–	0.000282 U	0.000305 U	0.000390 U	0.000296 U	0.000390 U	0.000212 U	**0.000324 J**	0.000338 U	0.000327 U	0.000791 U
	MW-140-55	08/30/17	PES	ESC	55	-4.4	S	–	–	–	–	0.000290 U	0.000314 U	0.000401 U	0.000304 U	0.000401 U	0.000218 U	**0.000499 J**	0.000348 U	0.000336 U	0.000813 U
	MW-140-65	08/30/17	PES	ESC	65	-14.4	S	–	–	–	–	0.000283 U	0.000306 U	0.000391 U	0.000297 U	0.000391 U	0.000213 U	0.000324 U	0.000339 U	0.000328 U	0.000793 U
	MW-140-75	08/30/17	PES	ESC	75	-24.4	S	–	–	–	–	0.00712 U	0.00771 U	0.00984 U	0.00746 U	0.00984 U	0.00537 U	0.00817 U	0.00854 U	0.00825 U	0.0200 U
	MW-140-90	08/30/17	PES	ESC	90	-39.4	S	–	–	–	–	0.000311 U	0.000336 U	0.000429 U	0.000326 U	0.000429 U	0.000234 U	0.000356 U	0.000373 U	0.000360 U	0.000872 U
	MW-140-110	08/31/17	PES	ESC	110	-59.4	S	–	–	–	–	0.000306 U	0.000331 U	0.000423 U	0.000321 U	0.000423 U	0.000230 U	0.000351 U	0.000367 U	0.000354 U	0.000858 U
	MW-140-130	08/31/17	PES	ESC	130	-79.4	S	–	–	–	–	0.000298 U	0.000323 U	0.000413 U	0.000313 U	0.000413 U	0.000225 U	0.000343 U	0.000358 U	0.000346 U	0.000838 U
	MW-140-140	08/31/17	PES	ESC	140	-89.4	S	–	–	–	–	0.00745 U	0.00808 U	0.0103 U	0.00782 U	0.0103 U	0.00562 U	0.00856 U	0.00894 U	0.00864 U	0.0209 U
MW-142 (2.4 to -7.6)	MW-142-5	04/12/18	PES	ESC	5	37.1	V	–	–	–	–	0.000318 U	0.000344 U	0.000439 U	0.000333 U	0.000439 U	0.000239 U	0.000365 U	0.000381 U	0.000368 U	0.000892 U
MW-143 (-27.7 to -37.7)	MW-143-10	04/11/18	PES	ESC	10	32.0	V	–	–	–	–	0.000366 U	**0.000715 J**	0.000506 U	0.000384 U	0.000506 U	**0.000609 J**	0.000420 U	0.000439 U	0.000424 U	0.00103 U
	MW-143-20	04/11/18	PES	ESC	20	22.0	S	–	–	–	–	0.000307 U	0.000332 U	0.000424 U	0.000322 U	0.000424 U	0.000231 U	0.000352 U	0.000368 U	0.000355 U	0.000861 U
	MW-143-30	04/11/18	PES	ESC	30	12.0	S	–	–	–	–	0.000301 U	0.000326 U	0.000416 U	0.000315 U	0.000416 U	0.000227 U	0.000345 U	0.000361 U	0.000348 U	0.000844 U
	MW-143-40	04/11/18	PES	ESC	40	2.0	S	–	–	–	–	0.000315 U	0.000341 U	0.000435 U	0.000330 U	0.000435 U	0.000237 U	0.000361 U	0.000378 U	0.000365 U	0.000884 U
	MW-143-50	04/11/18	PES	ESC	50	-8.0	S	–	–	–	–	0.000302 U	0.000328 U	0.000418 U	0.000317 U	0.000418 U	0.000228 U	**0.000867 J**	0.000363 U	0.000350 U	0.000849 U
	MW-143-60	04/11/18	PES	ESC	60	-18.0	S	–	–	–	–	0.000293 U	0.000318 U	0.000406 U	0.000308 U	0.000406 U	0.000221 U	0.000337 U	0.000352 U	0.000340 U	0.000824 U
	MW-143-70	04/11/18	PES	ESC	70	-28.0	S	–	–	–	–	0.000290 U	0.000315 U	0.000402 U	0.000305 U	0.000402 U	0.000219 U	0.000333 U	0.000349 U	0.000337 U	0.000815 U
	MW-143-80	04/11/18	PES	ESC	80	-38.0	S	–	–	–	–	0.000300 U	0.000325 U	0.000415 U	0.000315 U	0.000415 U	0.000226 U	0.000344 U	0.000360 U	0.000348 U	0.000842 U
	MW-902-20	04/11/18	PES	ESC	80 (dup)	-38.0	S	–	–	–	–	0.000295 U	0.000320 U	0.000408 U	0.000310 U	0.000408 U	0.000223 U	0.000339 U	0.000355 U	0.000342 U	0.000829 U
MW-145 (-26.1 to -36.1)	MW-145-10	04/17/18	PES	ESC	10	33.5	V	–	–	–	–	0.000332 U	0.000359 U	0.000459 U	0.000348 U	0.000459 U	0.000250 U	0.000381 U	0.000398 U	0.000384 U	0.000931 U
	MW-145-20	04/17/18	PES	ESC	20	23.5	S	–	–	–	–	0.000308 U	0.000334 U	0.000426 U	0.000323 U	0.000426 U	0.000232 U	0.000354 U	0.000370 U	0.000357 U	0.000865 U
	MW-145-30	04/17/18	PES	ESC	30	13.5	S	–	–	–	–	0.000313 U	0.000339 U	0.000433 U	0.000328 U	0.000433 U	0.000236 U	**0.00118 J**	0.000376 U	0.000363 U	0.000879 U
	MW-145-40	04/17/18	PES	ESC	40	3.5	S	–	–	–	–	0.000294 U	0.000319 U	0.000407 U	0.000309 U	0.000407 U	0.000222 U	0.000338 U	0.000353 U	0.000341 U	0.000826 U
	MW-145-50	04/17/18	PES	ESC	50	-6.5	S	–	–	–	–	0.000289 U	0.000313 U	0.000400 U	0.000304 U	0.000400 U	0.000218 U	0.000332 U	0.000347 U	0.000335 U	0.000812 U
	MW-145-60	04/17/18	PES	ESC	60	-16.5	S	–	–	–	–	0.000291 U	0.000315 U	0.000402 U	0.000305 U	0.000402 U	0.000219 U	0.000334 U	0.000349 U	0.000337 U	0.000817 U
	MW-145-70	04/17/18	PES	ESC	70	-26.5	S	–	–	–	–	0.000320 U	0.000347 U	0.000443 U	0.000336 U	0.000443 U	0.000241 U	0.000368 U	0.000385 U	0.000371 U	0.000899 U
	MW-145-80	04/17/18	PES	ESC	80	-36.5	S	–	–	–	–	0.000303 U	0.000328 U	0.000419 U	0.000318 U	0.000419 U	0.000229 U	0.000348 U	0.000364 U	0.000351 U	0.000851 U
	MW-903-40	04/17/18	PES	ESC	80 (dup)	-36.5	S	–	–	–	–	0.000296 U	0.000321 U	0.000409 U	0.000311 U	0.000409 U	0.000223 U	0.000340 U	0.000356 U	0.000343 U	0.000831 U
MW-147 (-17.6 to -27.6)	MW-147-10	04/02/18	PES	ESC	10	41.9	V	–	–	–	–	0.000287 U	0.000311 U	0.000396 U	0.000301 U	0.000396 U	0.000216 U	0.000329 U	0.000344 U	0.000332 U	0.000805 U
	MW-147-20	04/02/18	PES	ESC	20	31.9	S	–	–	–	–	0.000285 U	0.000309 U	0.000394 U	0.000299 U	0.000394 U	0.000215 U	0.000327 U	0.000343 U	0.000331 U	0.000801 U
	MW-147-30	04/02/18	PES	ESC	30	21.9	S	–	–	–	–	0.000295 U	0.000319 U	0.000408 U	0.000309 U	0.000408 U	0.000222 U	0.000338 U	0.000354 U	0.000342 U	0.000827 U
	MW-147-40	04/02/18	PES	ESC	40	11.9	S	–	–	–	–	0.000291 U	0.000316 U	0.000403 U	0.000306 U	0.000403 U	0.000220 U	0.000334 U	0.000350 U	0.000338 U	0.000818 U
	MW-147-50	04/02/18	PES	ESC	50	1.9	S	–	–	–	–	0.000292 U	0.000317 U	0.000404 U	0.000307 U	0.000404 U	0.000220 U	0.000336 U	0.000351 U	0.000339 U	0.000821 U
	MW-147-60	04/02/18	PES	ESC	60	-8.2	S	–	–	–	–	0.000284 U	0.000308 U	0.000392 U	0.000298 U	0.000392 U	0.000214 U	0.000326 U	0.000341 U	0.000329 U	0.000797 U
	MW-901-10	04/02/18	PES	ESC	60 (dup)	-8.2	S	–	–	–	–	0.000284 U	0.000308 U	0.000393 U	0.000298 U	0.000393 U	0.000214 U	0.000326 U	0.000341 U	0.000330 U	0.000798 U
	MW-147-70	04/02/18	PES	ESC	70	-18.2	S	–	–	–	–	0.000295 U	0.000320 U	0.000408 U	0.000310 U	0.000408 U	0.000223 U	0.000339 U	0.000355 U	0.000342 U	0.000829 U
	MW-147-80	04/02/18	PES	ESC	80	-28.2	S	–	–	–	–	0.000305 U	0.000331 U	0.000422 U	0.000321 U	0.000422 U	0.000230 U	0.000351 U	0.000367 U	0.000354 U	0.000857 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
MW-148	MW-148-11	04/09/18	PES	ESC	11	32.9	V	–	–	–	–	0.000305 U	0.000330 U	0.000421 U	0.000320 U	0.000421 U	0.000230 U	0.000350 U	0.000366 U	0.000353 U	0.000855 U
(-25.7 to -35.7)	MW-148-20	04/09/18	PES	ESC	20	23.9	S	–	–	–	–	0.000286 U	0.000310 U	0.000396 U	0.000300 U	0.000396 U	0.000216 U	0.000329 U	0.000344 U	0.000332 U	0.000804 U
	MW-148-30	04/09/18	PES	ESC	30	13.9	S	–	–	–	–	0.000296 U	0.000321 U	0.000410 U	0.000311 U	0.000410 U	0.000223 U	0.000340 U	0.000356 U	0.000344 U	0.000832 U
	MW-148-40	04/09/18	PES	ESC	40	3.9	S	–	–	–	–	0.000287 U	0.000311 U	0.000397 U	0.000301 U	0.000397 U	0.000216 U	0.000329 U	0.000344 U	0.000332 U	0.000805 U
	MW-148-50	04/09/18	PES	ESC	50	-6.1	S	–	–	–	–	0.000291 U	0.000315 U	0.000403 U	0.000306 U	0.000403 U	0.000219 U	0.000334 U	0.000350 U	0.000338 U	0.000817 U
	MW-148-60	04/09/18	PES	ESC	60	-16.1	S	–	–	–	–	0.000333 U	0.000361 U	0.000461 U	0.000350 U	0.000461 U	0.000251 U	0.000382 U	0.000400 U	0.000386 U	0.000935 U
	MW-148-70	04/09/18	PES	ESC	70	-26.1	S	–	–	–	–	0.000333 U	0.000360 U	0.000460 U	0.000349 U	0.000460 U	0.000251 U	0.000382 U	0.000399 U	0.000386 U	0.000934 U
	MW-148-80	04/09/18	PES	ESC	80	-36.1	S	–	–	–	–	0.000310 U	0.000336 U	0.000429 U	0.000326 U	0.000429 U	0.000234 U	0.000356 U	0.000373 U	0.000360 U	0.000871 U
MW-153	MW-153-10	03/27/18	PES	ESC	10	44.4	V	–	–	–	–	0.000299 U	0.000324 U	0.000414 U	0.000314 U	0.000414 U	0.000226 U	0.000344 U	0.000359 U	0.000347 U	0.000840 U
(-65.3 to -75.3)	MW-153-20	03/27/18	PES	ESC	20	34.4	V	–	–	–	–	0.000289 U	0.000313 U	0.000399 U	0.000303 U	0.000399 U	0.000218 U	0.000332 U	0.000347 U	0.000335 U	0.000811 U
	MW-153-30	03/27/18	PES	ESC	30	24.4	S	–	–	–	–	0.000283 U	0.000307 U	0.000392 U	0.000297 U	0.000392 U	0.000213 U	0.000325 U	0.000340 U	0.000328 U	0.000795 U
	MW-153-40	03/27/18	PES	ESC	40	14.4	S	–	–	–	–	0.000299 U	0.000324 U	0.000414 U	0.000314 U	0.000414 U	0.000225 U	0.000343 U	0.000359 U	0.000347 U	0.000839 U
	MW-153-50	03/27/18	PES	ESC	50	4.4	S	–	–	–	–	0.000293 U	0.000317 U	0.000405 U	0.000307 U	0.000405 U	0.000221 U	0.000336 U	0.000352 U	0.000339 U	0.000822 U
	MW-153-61	03/27/18	PES	ESC	61	-6.7	S	–	–	–	–	0.000300 U	0.000325 U	0.000415 U	0.000315 U	0.000415 U	0.000226 U	0.000344 U	0.000360 U	0.000348 U	0.000842 U
	MW-153-70	03/27/18	PES	ESC	70	-15.7	S	–	–	–	–	0.000294 U	0.000318 U	0.000406 U	0.000308 U	0.000406 U	0.000222 U	0.000337 U	0.000353 U	0.000341 U	0.000825 U
	MW-153-80	03/28/18	PES	ESC	80	-25.7	S	–	–	–	–	0.000291 U	0.000316 U	0.000403 U	0.000306 U	0.000403 U	0.000220 U	0.000334 U	0.000350 U	0.000338 U	0.000818 U
	MW-153-90	03/28/18	PES	ESC	90	-35.7	S	–	–	–	–	0.000318 U	0.000344 U	0.000440 U	0.000334 U	0.000440 U	0.000240 U	0.000365 U	0.000382 U	0.000369 U	0.000892 U
	MW-153-110	03/28/18	PES	ESC	110	-55.7	S	–	–	–	–	0.000311 U	0.000337 U	0.000430 U	0.000326 U	0.000430 U	0.000234 U	0.000357 U	0.000373 U	0.000360 U	0.000872 U
	MW-153-130	03/29/18	PES	ESC	130	-75.7	S	–	–	–	–	0.000303 U	0.000329 U	0.000419 U	0.000318 U	0.000419 U	0.000229 U	0.000348 U	0.000364 U	0.000352 U	0.000851 U
MW-158	MW-158-20	04/05/18	PES	ESC	20	21.1	S	0.0384 U	–	–	–	0.000299 U	0.000324 U	0.000413 U	0.000314 U	0.000413 U	0.000225 U	0.000343 U	0.000359 U	0.000347 U	0.000839 U
	MW-158-30	04/05/18	PES	ESC	30	11.1	S	**1.50**	–	–	–	0.0311 U	0.0337 U	0.0431 U	0.0327 U	0.0431 U	0.0235 U	0.0357 U	0.0374 U	0.0361 U	0.0874 U
MW-158A	MW-158A-40	04/05/18	PES	ESC	40	1.1	S	**0.839**	–	–	–	0.000325 U	0.000353 U	0.000450 U	0.000341 U	0.000450 U	0.000245 U	**0.000568 J**	0.000391 U	0.000377 U	0.000913 U
(-47.2 to -58.5)	MW-158A-50	04/05/18	PES	ESC	50	-8.9	S	**0.194**	–	–	–	0.000305 U	0.000331 U	0.000422 U	0.000320 U	0.000422 U	0.000230 U	**0.000421 J**	0.000367 U	0.000354 U	0.000857 U
	MW-158A-60	04/05/18	PES	ESC	60	-18.9	S	**0.319**	–	–	–	0.000304 U	0.000329 U	0.000420 U	0.000319 U	0.000420 U	0.000229 U	**0.000756 J**	0.000365 U	0.000352 U	0.000853 U
	MW-158A-70	04/05/18	PES	ESC	70	-28.9	S	**0.129**	–	–	–	0.000296 U	0.000321 U	0.000410 U	0.000311 U	0.000410 U	0.000223 U	**0.000692 J**	0.000356 U	0.000343 U	0.000831 U
	MW-158A-80	04/06/18	PES	ESC	80	-38.9	S	0.0376 U	–	–	–	0.000293 U	0.000317 U	0.000405 U	0.000307 U	0.000405 U	0.000221 U	0.000336 U	0.000352 U	0.000339 U	0.000822 U
	MW-158A-90	04/06/18	PES	ESC	90	-48.9	S	0.0389 U	–	–	–	0.000303 U	0.000328 U	0.000419 U	0.000318 U	0.000419 U	0.000228 U	0.000348 U	0.000364 U	0.000351 U	0.000850 U
	MW-158A-100	04/06/18	PES	ESC	100	-58.9	S	0.0398 U	–	–	–	0.000310 U	0.000336 U	0.000429 U	0.000325 U	0.000429 U	0.000234 U	0.000356 U	0.000372 U	0.000360 U	0.000871 U
MW-159	MW-159-20	04/16/18	PES	ESC	20	22.8	S	–	–	–	–	0.000319 U	0.000346 U	0.000441 U	0.000335 U	0.000441 U	0.000241 U	0.000366 U	0.000383 U	0.000370 U	0.000896 U
(22.9 to 12.9)	MW-159-30	04/16/18	PES	ESC	30	12.8	S	–	–	–	–	0.000322 U	0.000349 U	0.000445 U	0.000338 U	0.000445 U	0.000243 U	**0.000425 J**	0.000386 U	0.000373 U	0.000903 U
MW-160	MW-160-11	05/08/18	PES	ESC	11	31.5	S	–	–	–	–	0.000812 U	0.000446 U	0.000634 U	0.00143 U	0.00110 U	0.000933 U	0.000812 U	0.00114 U	**0.00136 J**	0.00827 U
(-76.5 to -86.5)	MW-160-21	05/08/18	PES	ESC	21	21.5	S	–	–	–	–	0.000586 U	0.000322 U	0.000457 U	0.00104 U	0.000791 U	0.000674 U	0.000586 U	0.000821 U	0.000733 U	0.00598 U
	MW-160-31	05/08/18	PES	ESC	31	11.5	S	–	–	–	–	0.000606 U	0.000334 U	0.000473 U	0.00107 U	0.000819 U	0.000697 U	0.000606 U	0.000849 U	0.000758 U	0.00619 U
	MW-160-40	05/08/18	PES	ESC	40	2.5	S	–	–	–	–	0.000568 U	0.000312 U	0.000443 U	0.00100 U	0.000766 U	0.000653 U	0.000568 U	0.000795 U	0.000710 U	0.00579 U
	MW-160-50	05/08/18	PES	ESC	50	-7.5	S	–	–	–	–	0.000571 U	0.000314 U	0.000446 U	0.00101 U	0.000771 U	0.000657 U	0.000571 U	0.000800 U	0.000714 U	0.00583 U
	MW-160-55	05/08/18	PES	ESC	55	-12.5	S	–	–	–	–	0.000593 U	0.000326 U	0.000463 U	0.00105 U	0.000801 U	0.000682 U	**0.00477**	0.000830 U	0.000741 U	0.00605 U
	MW-160-60	05/08/18	PES	ESC	60	-17.5	S	–	–	–	–	0.000545 U	0.000300 U	0.000425 U	0.000962 U	0.000735 U	0.000626 U	**0.00255 J**	0.000763 U	0.000681 U	0.00556 U
	MW-160-70	05/08/18	PES	ESC	70	-27.5	S	–	–	–	–	0.000584 U	0.000321 U	0.000456 U	0.00103 U	0.000789 U	0.000672 U	0.000584 U	0.000818 U	0.000730 U	0.00596 U
	MW-160-90	05/08/18	PES	ESC	90	-47.5	S	–	–	–	–	0.000588 U	0.000324 U	0.000459 U	0.00104 U	0.000794 U	0.000677 U	0.000588 U	0.000824 U	0.000736 U	0.00600 U
	MW-160-100	05/08/18	PES	ESC	100	-57.5	S	–	–	–	–	0.000601 U	0.000331 U	0.000469 U	0.00106 U	0.000812 U	0.000692 U	0.000601 U	0.000842 U	0.000752 U	0.00614 U
	MW-160-110	05/08/18	PES	ESC	110	-67.5	S	–	–	–	–	0.000567 U	0.000312 U	0.000442 U	0.00100 U	0.000765 U	0.000652 U	0.000567 U	0.000794 U	0.000709 U	0.00578 U
	MW-160-125	05/10/18	PES	ESC	125	-82.5	S	–	–	–	–	0.000572 U	0.000315 U	0.000447 U	0.00101 U	0.000773 U	0.000658 U	0.000572 U	0.000801 U	0.000716 U	0.00584 U
	MW-160-127.5	05/10/18	PES	ESC	128	-85.0	S	–	–	–	–	0.000577 U	0.000318 U	0.000450 U	0.00102 U	0.000779 U	0.000664 U	0.000577 U	0.000808 U	0.000722 U	0.00589 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
MW-161	MW-161-11	05/14/18	PES	ESC	11	32.8	S	–	–	–	–	0.000615 U	0.000338 U	0.000480 U	0.00109 U	0.000830 U	0.000707 U	0.000615 U	0.000861 U	0.000768 U	0.00627 U
(-78.9 to -88.9)	MW-161-21	05/14/18	PES	ESC	21	22.8	S	–	–	–	–	0.000520 U	0.000286 U	0.000405 U	0.000918 U	0.000702 U	0.000598 U	0.000520 U	0.000728 U	0.000650 U	0.00530 U
	MW-161-31	05/14/18	PES	ESC	31	12.8	S	–	–	–	–	0.000572 U	0.000315 U	0.000446 U	0.00101 U	0.000773 U	0.000658 U	0.000572 U	0.000801 U	0.000715 U	0.00584 U
	MW-161-40	05/14/18	PES	ESC	40	3.8	S	–	–	–	–	0.000552 U	0.000304 U	0.000430 U	0.000975 U	0.000745 U	0.000635 U	0.000552 U	0.000773 U	0.000690 U	0.00563 U
	MW-161-50	05/14/18	PES	ESC	50	-6.2	S	–	–	–	–	0.000558 U	0.000307 U	0.000435 U	0.000985 U	0.000753 U	0.000642 U	0.000558 U	0.000781 U	0.000697 U	0.00569 U
	MW-161-60	05/14/18	PES	ESC	60	-16.2	S	–	–	–	–	0.000571 U	0.000314 U	0.000445 U	0.00101 U	0.000771 U	0.000657 U	0.000571 U	0.000800 U	0.000714 U	0.00583 U
	MW-161-70	05/14/18	PES	ESC	70	-26.2	S	–	–	–	–	0.000558 U	0.000307 U	0.000436 U	0.000986 U	0.000754 U	0.000642 U	0.000558 U	0.000782 U	0.000698 U	0.00570 U
	MW-161-80	05/14/18	PES	ESC	80	-36.2	S	–	–	–	–	0.000616 U	0.000339 U	0.000481 U	0.00109 U	0.000832 U	0.000709 U	0.000616 U	0.000863 U	0.000770 U	0.00629 U
	MW-161-90	05/14/18	PES	ESC	90	-46.2	S	–	–	–	–	0.000569 U	0.000313 U	0.000444 U	0.00100 U	0.000768 U	0.000654 U	0.000569 U	0.000797 U	0.000711 U	0.00580 U
	B-927-30	05/14/18	PES	ESC	90 (dup)	-46.2	S	–	–	–	–	0.000621 U	0.000341 U	0.000484 U	0.00110 U	0.000838 U	0.000714 U	0.000621 U	0.000869 U	0.000776 U	0.00633 U
	MW-161-100	05/14/18	PES	ESC	100	-56.2	S	–	–	–	–	0.000582 U	0.000320 U	0.000454 U	0.00103 U	0.000786 U	0.000670 U	0.000582 U	0.000815 U	0.000728 U	0.00594 U
	MW-161-110	05/14/18	PES	ESC	110	-66.2	S	–	–	–	–	0.000610 U	0.000335 U	0.000476 U	0.00108 U	0.000823 U	0.000701 U	0.000610 U	0.000854 U	0.000762 U	0.00622 U
	MW-161-120	05/14/18	PES	ESC	120	-76.2	S	–	–	–	–	0.000610 U	0.000336 U	0.000476 U	0.00108 U	0.000824 U	0.000702 U	0.000610 U	0.000854 U	0.000763 U	0.00622 U
	MW-161-130	05/14/18	PES	ESC	130	-86.2	S	–	–	–	–	0.000550 U	0.000302 U	0.000429 U	0.000971 U	0.000742 U	0.000632 U	0.000550 U	0.000770 U	0.000687 U	0.00561 U
	MW-161-140	05/15/18	PES	ESC	140	-96.2	S	–	–	–	–	0.000613 U	0.000337 U	0.000478 U	0.00108 U	0.000827 U	0.000705 U	0.000613 U	0.000858 U	0.000766 U	0.00625 U
MW-190	MW-190-5	09/19/19	PES	PACE	5	43.7	V	**1.03 J**	–	–	–	0.000577 U	0.000317 U	0.000450 U	0.00102 U	0.000779 U	0.000663 U	0.000577 U	0.000807 U	0.000721 U	0.00588 U
(-30.2 to -40.2)	MW-190-10	09/19/19	PES	PACE	10	38.7	V	**3.07 J**	–	–	–	0.00103 U	0.000569 U	0.000806 U	0.00183 U	0.00140 U	0.00119 U	0.00103 U	0.00145 U	0.00129 U	0.0105 U
	MW-190-15	09/19/19	PES	PACE	15	33.7	S	1.12 U	–	–	–	0.000662 U	0.000364 U	0.000516 U	0.00117 U	0.000894 U	0.000761 U	0.000662 U	0.000927 U	0.000827 U	0.00675 U
	MW-190-20	09/19/19	PES	PACE	20	28.7	S	1.06 U	–	–	–	0.000622 U	0.000342 U	0.000485 U	0.00110 U	0.000840 U	0.000716 U	0.000622 U	0.000871 U	0.000778 U	0.00635 U
	MW-190-25	09/19/19	PES	PACE	25	23.7	S	0.995 U	–	–	–	0.000587 U	0.000323 U	0.000458 U	0.00104 U	0.000792 U	0.000675 U	0.000587 U	0.000822 U	0.000734 U	0.00599 U
	MW-190-30	09/19/19	PES	PACE	30	18.7	S	**1.12 J**	–	–	–	0.000524 U	0.000288 U	0.000409 U	0.000925 U	0.000707 U	0.000602 U	0.000524 U	0.000733 U	0.000655 U	0.00534 U
	MW-190-35	09/19/19	PES	PACE	35	13.7	S	**1.17 J**	–	–	–	0.000531 U	0.000292 U	0.000414 U	0.000938 U	0.000717 U	0.000611 U	0.000531 U	0.000744 U	0.000664 U	0.00542 U
	MW-190-40	09/19/19	PES	PACE	40	8.7	S	0.952 U	–	–	–	0.000561 U	0.000309 U	0.000438 U	0.000991 U	0.000758 U	0.000645 U	0.000561 U	0.000786 U	0.000702 U	0.00572 U
	MW-190-45	09/19/19	PES	PACE	45	3.7	S	0.970 U	–	–	–	0.000572 U	0.000314 U	0.000446 U	0.00101 U	0.000772 U	0.000657 U	0.000572 U	0.000800 U	0.000715 U	0.00583 U
	MW-190-50	09/19/19	PES	PACE	50	-1.4	S	**1.79 J**	–	–	–	0.000524 U	0.000288 U	0.000409 U	0.000925 U	0.000707 U	0.000602 U	0.000524 U	0.000733 U	0.000655 U	0.00534 U
	MW-190-55	09/19/19	PES	PACE	55	-6.4	S	**1.44 J**	–	–	–	0.000542 U	0.000298 U	0.000423 U	0.000958 U	0.000732 U	0.000624 U	0.000542 U	0.000759 U	0.000678 U	0.00553 U
	MW-190-60	09/19/19	PES	PACE	60	-11.4	S	**1.39 J**	–	–	–	0.000545 U	0.000300 U	0.000425 U	0.000962 U	0.000736 U	0.000627 U	0.000545 U	0.000763 U	0.000681 U	0.00556 U
	MW-2008-60	09/19/19	PES	PACE	60 (dup)	-11.4	S	**1.18 J**	–	–	–	0.000540 U	0.000297 U	0.000422 U	0.000954 U	0.000730 U	0.000622 U	0.000540 U	0.000757 U	0.000676 U	0.00551 U
	MW-190-65	09/19/19	PES	PACE	65	-16.4	S	**1.65 J**	–	–	–	0.000552 U	0.000304 U	0.000431 U	0.000975 U	0.000745 U	0.000635 U	0.000552 U	0.000773 U	0.000690 U	0.00563 U
	MW-190-70	09/19/19	PES	PACE	70	-21.4	S	**0.943 J**	–	–	–	0.000554 U	0.000305 U	0.000432 U	0.000978 U	0.000748 U	0.000637 U	0.000554 U	0.000775 U	0.000692 U	0.00565 U
	MW-190-75	09/19/19	PES	PACE	75	-26.4	S	0.927 U	–	–	–	0.000547 U	0.000301 U	0.000426 U	0.000965 U	0.000738 U	0.000629 U	0.000547 U	0.000765 U	0.000683 U	0.00558 U
	MW-190-80	09/19/19	PES	PACE	80	-31.4	S	**1.49 J**	–	–	–	0.000546 U	0.000300 U	0.000426 U	0.000964 U	0.000737 U	0.000628 U	0.000546 U	0.000764 U	0.000682 U	0.00557 U
	MW-190-85	09/19/19	PES	PACE	85	-36.4	S	**1.23 J**	–	–	–	0.000575 U	0.000316 U	0.000448 U	0.00102 U	0.000776 U	0.000661 U	0.000575 U	0.000805 U	0.000719 U	0.00586 U
	MW-190-87	09/19/19	PES	PACE	87	-38.4	S	**1.02 J**	–	–	–	0.000598 U	0.000329 U	0.000466 U	0.00106 U	0.000807 U	0.000687 U	0.000598 U	0.000837 U	0.000747 U	0.00609 U
MW-301	MW-301-6	09/20/19	PES	PACE	6	47.8	V	–	–	–	–	0.000586 U	0.000322 U	0.000457 U	0.00103 U	0.000791 U	0.000674 U	0.000586 U	0.000820 U	0.000732 U	0.00598 U
(35.6 to 25.6)	MW-301-10	09/20/19	PES	PACE	10	43.8	V	–	–	–	–	0.000550 U	0.000302 U	0.000429 U	0.000971 U	0.000742 U	0.000632 U	0.000550 U	0.000770 U	0.000687 U	0.00561 U
	MW-301-15	09/20/19	PES	PACE	15	38.8	V	–	–	–	–	0.000568 U	0.000312 U	0.000443 U	0.00100 U	0.000766 U	0.000653 U	0.000568 U	0.000795 U	0.000710 U	0.00579 U
	MW-301-20	09/20/19	PES	PACE	20	33.8	S	–	–	–	–	0.00169 U	0.000929 U	0.00132 U	0.00298 U	0.00228 U	0.00194 U	0.00169 U	0.00236 U	0.00211 U	0.0172 U
	MW-301-25	09/20/19	PES	PACE	25	28.8	S	–	–	–	–	0.000568 U	0.000313 U	0.000443 U	0.00100 U	0.000767 U	0.000654 U	0.000568 U	0.000796 U	0.000710 U	0.00580 U
	MW-301-30	09/20/19	PES	PACE	30	23.8	S	–	–	–	–	0.000619 U	0.000340 U	0.000483 U	0.00109 U	0.000835 U	0.000711 U	0.000619 U	0.000866 U	0.000774 U	0.00631 U
MW-302	MW-302-5	10/01/19	PES	PACE	5	52.3	V	–	–	–	–	0.000585 U	0.000322 U	0.000457 U	0.00103 U	0.000790 U	0.000673 U	0.000585 U	0.000820 U	0.000732 U	0.00597 U
(3.0 to -7.0)	MW-302-10	10/01/19	PES	PACE	10	47.3	V	–	–	–	–	0.000622 U	0.000342 U	0.000485 U	0.00110 U	0.000840 U	0.000715 U	0.000622 U	0.000871 U	0.000778 U	0.00635 U
	MW-302-15	10/01/19	PES	PACE	15	42.3	V	–	–	–	–	0.000682 U	0.000375 U	0.000531 U	0.00120 U	0.000921 U	0.000784 U	0.000682 U	0.000955 U	0.000852 U	0.00696 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
MW-302 (continued)	MW-302-20	10/01/19	PES	PACE	20	37.3	S	–	–	–	–	0.000597 U	0.000328 U	0.000465 U	0.00105 U	0.000806 U	0.000686 U	0.000597 U	0.000835 U	0.000746 U	0.00609 U
	MW-302-25	10/01/19	PES	PACE	25	32.3	S	–	–	–	–	0.000560 U	0.000308 U	0.000437 U	0.000990 U	0.000756 U	0.000644 U	0.000560 U	0.000784 U	0.000700 U	0.00572 U
	MW-302-30	10/01/19	PES	PACE	30	27.3	S	–	–	–	–	0.000547 U	0.000301 U	0.000427 U	0.000966 U	0.000738 U	0.000629 U	0.000547 U	0.000766 U	0.000684 U	0.00558 U
	MW-302-35	10/01/19	PES	PACE	35	22.3	S	–	–	–	–	0.000537 U	0.000296 U	0.000419 U	0.000949 U	0.000725 U	0.000618 U	0.000537 U	0.000752 U	0.000672 U	0.00548 U
	MW-302-40	10/01/19	PES	PACE	40	17.3	S	–	–	–	–	0.000532 U	0.000293 U	0.000415 U	0.000939 U	0.000718 U	0.000612 U	0.000532 U	0.000745 U	0.000665 U	0.00542 U
	MW-302-45	10/01/19	PES	PACE	45	12.3	S	–	–	–	–	0.000596 U	0.000328 U	0.000465 U	0.00105 U	0.000804 U	0.000685 U	0.000596 U	0.000834 U	0.000745 U	0.00608 U
	MW-302-50	10/01/19	PES	PACE	50	7.3	S	–	–	–	–	0.000597 U	0.000328 U	0.000466 U	0.00105 U	0.000806 U	0.000687 U	0.000597 U	0.000836 U	0.000746 U	0.00609 U
	MW-302-55	10/01/19	PES	PACE	55	2.3	S	–	–	–	–	0.000568 U	0.000312 U	0.000443 U	0.00100 U	0.000767 U	0.000653 U	0.000568 U	0.000795 U	0.000710 U	0.00580 U
	MW-302-60	10/01/19	PES	PACE	60	-2.7	S	–	–	–	–	0.000711 U	0.000391 U	0.000554 U	0.00126 U	0.000959 U	0.000817 U	0.000711 U	0.000995 U	0.000888 U	0.00725 U
	MW-302-65	10/01/19	PES	PACE	65	-7.7	S	–	–	–	–	0.000586 U	0.000322 U	0.000457 U	0.00103 U	0.000791 U	0.000673 U	0.000586 U	0.000820 U	0.000732 U	0.00597 U
	MW-2014-65	10/01/19	PES	PACE	65 (dup)	-7.7	S	–	–	–	–	0.000606 U	0.000333 U	0.000473 U	0.00107 U	0.000818 U	0.000697 U	0.000606 U	0.000849 U	0.000758 U	0.00618 U
MW-304 (-47.6 to -57.6)	MW-304-5	10/01/19	PES	PACE	5	52.6	V	–	–	–	–	0.000563 U	0.000310 U	0.000439 U	0.000995 U	0.000760 U	0.000648 U	0.000563 U	0.000788 U	**0.00121 J**	0.00574 U
	MW-304-10	10/01/19	PES	PACE	10	47.6	V	–	–	–	–	0.000570 U	0.000313 U	0.000444 U	0.00101 U	0.000769 U	0.000655 U	0.000570 U	0.000798 U	0.000712 U	0.00581 U
	MW-304-15	10/01/19	PES	PACE	15	42.6	V	–	–	–	–	0.000595 U	0.000327 U	0.000464 U	0.00105 U	0.000803 U	0.000684 U	0.000595 U	0.000832 U	0.000743 U	0.00606 U
	MW-304-20	10/01/19	PES	PACE	20	37.6	S	–	–	–	–	0.000589 U	0.000324 U	0.000459 U	0.00104 U	0.000795 U	0.000677 U	0.000589 U	0.000824 U	0.000736 U	0.00601 U
	MW-304-25	10/01/19	PES	PACE	25	32.6	S	–	–	–	–	0.000547 U	0.000301 U	0.000427 U	0.000966 U	0.000738 U	0.000629 U	0.000547 U	0.000766 U	0.000684 U	0.00558 U
	MW-304-30	10/01/19	PES	PACE	30	27.6	S	–	–	–	–	0.000588 U	0.000323 U	0.000459 U	0.00104 U	0.000794 U	0.000676 U	0.000588 U	0.000823 U	0.000735 U	0.00600 U
	MW-304-40	10/01/19	PES	PACE	40	17.6	S	–	–	–	–	0.000543 U	0.000298 U	0.000423 U	0.000958 U	0.000732 U	0.000624 U	0.000543 U	0.000760 U	0.000678 U	0.00553 U
	MW-304-45	10/01/19	PES	PACE	45	12.6	S	–	–	–	–	0.000508 U	0.000279 U	0.000396 U	0.000897 U	0.000686 U	0.000584 U	0.000508 U	0.000711 U	0.000635 U	0.00518 U
	MW-304-50	10/01/19	PES	PACE	50	7.6	S	–	–	–	–	0.000538 U	0.000296 U	0.000420 U	0.000951 U	0.000727 U	0.000619 U	0.000538 U	0.000754 U	0.000673 U	0.00549 U
	MW-304-55	10/01/19	PES	PACE	55	2.6	S	–	–	–	–	0.000504 U	0.000277 U	0.000393 U	0.000890 U	0.000680 U	0.000580 U	0.000504 U	0.000706 U	0.000630 U	0.00514 U
	MW-304-60	10/01/19	PES	PACE	60	-2.4	S	–	–	–	–	0.000527 U	0.000290 U	0.000411 U	0.000931 U	0.000712 U	0.000606 U	0.000527 U	0.000738 U	0.000659 U	0.00538 U
	MW-304-65	10/01/19	PES	PACE	65	-7.4	S	–	–	–	–	0.000579 U	0.000318 U	0.000452 U	0.00102 U	0.000782 U	0.000666 U	0.000579 U	0.000811 U	0.000724 U	0.00591 U
	MW-304-70	10/01/19	PES	PACE	70	-12.4	S	–	–	–	–	0.000607 U	0.000334 U	0.000474 U	0.00107 U	0.000820 U	0.000699 U	0.000607 U	0.000850 U	0.000759 U	0.00620 U
	MW-304-75	10/01/19	PES	PACE	75	-17.4	S	–	–	–	–	0.000572 U	0.000315 U	0.000447 U	0.00101 U	0.000773 U	0.000658 U	0.000572 U	0.000801 U	0.000716 U	0.00584 U
	MW-304-80	10/01/19	PES	PACE	80	-22.4	S	–	–	–	–	0.000547 U	0.000301 U	0.000427 U	0.000966 U	0.000739 U	0.000629 U	0.000547 U	0.000766 U	0.000684 U	0.00558 U
	MW-304-85	10/01/19	PES	PACE	85	-27.4	S	–	–	–	–	0.000548 U	0.000301 U	0.000427 U	0.000967 U	0.000739 U	0.000630 U	0.000548 U	0.000767 U	0.000685 U	0.00559 U
	MW-304-90	10/01/19	PES	PACE	90	-32.4	S	–	–	–	–	0.000599 U	0.000330 U	0.000468 U	0.00106 U	0.000809 U	0.000689 U	0.000599 U	0.000839 U	0.000749 U	0.00611 U
	MW-304-95	10/01/19	PES	PACE	95	-37.4	S	–	–	–	–	0.000592 U	0.000326 U	0.000462 U	0.00105 U	0.000800 U	0.000681 U	0.000592 U	0.000829 U	0.000741 U	0.00604 U
	MW-2009-95	10/01/19	PES	PACE	95 (dup)	-37.4	S	–	–	–	–	0.000601 U	0.000330 U	0.000469 U	0.00106 U	0.000811 U	0.000691 U	0.000601 U	0.000841 U	0.000751 U	0.00613 U
	MW-304-100	10/02/19	PES	PACE	100	-42.4	S	–	–	–	–	0.000589 U	0.000324 U	0.000460 U	0.00104 U	0.000796 U	0.000678 U	0.000589 U	0.000825 U	0.000737 U	0.00601 U
	MW-304-105	10/02/19	PES	PACE	105	-47.4	S	–	–	–	–	0.000585 U	0.000322 U	0.000456 U	0.00103 U	0.000790 U	0.000673 U	0.000585 U	0.000819 U	0.000731 U	0.00597 U
	MW-304-110	10/02/19	PES	PACE	110	-52.4	S	–	–	–	–	0.000632 U	0.000348 U	0.000493 U	0.00112 U	0.000853 U	0.000727 U	0.000632 U	0.000885 U	0.000790 U	0.00645 U
	MW-304-115	10/02/19	PES	PACE	115	-57.4	S	–	–	–	–	0.000583 U	0.000320 U	0.000454 U	0.00103 U	0.000786 U	0.000670 U	0.000583 U	0.000816 U	0.000728 U	0.00594 U
MW-307 (-12.4 to -22.4)	MW-307-6	10/03/19	PES	PACE	6	54.5	V	–	–	–	–	0.000559 U	0.000307 U	0.000436 U	0.000987 U	0.000755 U	0.000643 U	0.000559 U	0.000783 U	0.000699 U	0.00570 U
	MW-307-10	10/03/19	PES	PACE	10	50.5	V	–	–	–	–	0.000576 U	0.000317 U	0.000449 U	0.00102 U	0.000778 U	0.000661 U	0.000576 U	0.000806 U	0.000720 U	0.00588 U
	MW-307-15	10/03/19	PES	PACE	15	45.5	V	–	–	–	–	0.000539 U	0.000296 U	0.000420 U	0.000951 U	0.000727 U	0.000620 U	0.000539 U	0.000754 U	0.000673 U	0.00549 U
	MW-307-20	10/03/19	PES	PACE	20	40.5	V	–	–	–	–	0.000535 U	0.000294 U	0.000417 U	0.000944 U	0.000722 U	0.000615 U	0.000535 U	0.000749 U	0.000668 U	0.00545 U
	MW-307-25	10/03/19	PES	PACE	25	35.5	S	–	–	–	–	0.000549 U	0.000302 U	0.000428 U	0.000969 U	0.000740 U	0.000631 U	0.000549 U	0.000768 U	0.000686 U	0.00559 U
	MW-307-30	10/03/19	PES	PACE	30	30.5	S	–	–	–	–	0.000737 U	0.000406 U	0.000575 U	0.00130 U	0.000995 U	0.000848 U	0.000737 U	0.00103 U	0.000921 U	0.00751 U
	MW-307-35	10/03/19	PES	PACE	35	25.5	S	–	–	–	–	0.000535 U	0.000294 U	0.000417 U	0.000945 U	0.000722 U	0.000615 U	0.000535 U	0.000749 U	0.000669 U	0.00546 U
	MW-307-40	10/03/19	PES	PACE	40	20.5	S	–	–	–	–	0.000571 U	0.000314 U	0.000445 U	0.00101 U	0.000771 U	0.000657 U	0.000571 U	0.000799 U	0.000714 U	0.00582 U
	MW-307-45	10/03/19	PES	PACE	45	15.5	S	–	–	–	–	0.000551 U	0.000303 U	0.000430 U	0.000974 U	0.000744 U	0.000634 U	0.000551 U	0.000772 U	0.000689 U	0.00563 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
MW-307 (continued)	MW-307-50	10/03/19	PES	PACE	50	10.5	S	–	–	–	–	0.000556 U	0.000306 U	0.000434 U	0.000982 U	0.000751 U	0.000639 U	0.000556 U	0.000778 U	0.000695 U	0.00567 U
	MW-307-55	10/03/19	PES	PACE	55	5.5	S	–	–	–	–	0.000543 U	0.000299 U	0.000423 U	0.000959 U	0.000733 U	0.000624 U	0.000543 U	0.000760 U	0.000679 U	0.00554 U
	MW-307-60	10/03/19	PES	PACE	60	0.5	S	–	–	–	–	0.000565 U	0.000311 U	0.000440 U	0.000997 U	0.000762 U	0.000649 U	0.000565 U	0.000790 U	0.000706 U	0.00576 U
	MW-307-65	10/03/19	PES	PACE	65	-4.5	S	–	–	–	–	0.00115 U	0.000634 U	0.000898 U	0.00203 U	0.00155 U	0.00132 U	0.00115 U	0.00161 U	0.00144 U	0.0117 U
	MW-307-70	10/03/19	PES	PACE	70	-9.5	S	–	–	–	–	0.00573 U	0.00315 U	0.00447 U	0.0101 U	0.00773 U	0.00659 U	0.00573 U	0.00802 U	0.00716 U	0.0584 U
	MW-307-75	10/03/19	PES	PACE	75	-14.5	S	–	–	–	–	0.000551 U	0.000303 U	0.000430 U	0.000974 U	0.000744 U	0.000634 U	0.000551 U	0.000772 U	0.000689 U	0.00562 U
	MW-307-80	10/03/19	PES	PACE	80	-19.5	S	–	–	–	–	0.000584 U	0.000321 U	0.000456 U	0.00103 U	0.000788 U	0.000672 U	0.000584 U	0.000818 U	0.000731 U	0.00596 U
	MW-307-85	10/03/19	PES	PACE	85	-24.5	S	–	–	–	–	0.000573 U	0.000315 U	0.000447 U	0.00101 U	0.000773 U	0.000659 U	0.000573 U	0.000802 U	0.000716 U	0.00584 U
	MW-2016-85	10/03/19	PES	PACE	85 (dup)	-24.5	S	–	–	–	–	0.000540 U	0.000297 U	0.000421 U	0.000954 U	0.000729 U	0.000621 U	0.000540 U	0.000756 U	0.000675 U	0.00551 U
MW-309 (-32.0 to -42.0)	MW-309-5	09/19/19	PES	PACE	5	25.4	V	–	–	–	–	0.000597 U	0.000328 U	0.000465 U	0.00105 U	0.000805 U	0.000686 U	0.000597 U	0.000835 U	0.000746 U	0.00609 U
	MW-309-10	09/19/19	PES	PACE	10	20.4	S	**389**	**99.0**	**162**	**261**	0.0315 U	0.0173 U	0.0245 U	0.0555 U	0.0425 U	0.0362 U	0.0315 U	0.0440 U	0.0393 U	0.321 U
	MW-309-13.5	09/19/19	PES	PACE	13.5	16.9	S	**15.6**	**5.04**	4.07 U	**5.04**	0.000611 U	0.000336 U	0.000476 U	0.00108 U	0.000824 U	0.000702 U	0.000611 U	0.000855 U	0.000763 U	0.00623 U
	MW-309-15	09/19/19	PES	PACE	15	15.4	S	**29.9**	**2.34**	**4.21 J**	**6.55 J**	0.00471 U	0.00259 U	0.00367 U	0.00831 U	0.00636 U	0.00542 U	0.00471 U	0.00659 U	0.00589 U	0.0480 U
	MW-309-20	09/19/19	PES	PACE	20	10.4	S	–	–	–	–	0.000588 U	0.000324 U	0.000459 U	0.00104 U	0.000794 U	0.000677 U	0.000588 U	0.000824 U	0.000735 U	0.00600 U
	MW-309-25	09/19/19	PES	PACE	25	5.4	S	–	–	–	–	0.000591 U	0.000325 U	0.000461 U	0.00104 U	0.000797 U	0.000679 U	0.000591 U	0.000827 U	0.000738 U	0.00603 U
	MW-309-30	09/19/19	PES	PACE	30	0.4	S	–	–	–	–	0.000597 U	0.000328 U	0.000466 U	0.00105 U	0.000806 U	0.000687 U	0.000597 U	0.000836 U	0.000746 U	0.00609 U
	MW-309-35	09/19/19	PES	PACE	35	-4.6	S	–	–	–	–	0.000606 U	0.000333 U	0.000473 U	0.00107 U	0.000818 U	0.000697 U	0.000606 U	0.000849 U	0.000758 U	0.00618 U
	MW-309-40	09/19/19	PES	PACE	40	-9.6	S	–	–	–	–	0.000606 U	0.000333 U	0.000473 U	0.00107 U	0.000818 U	0.000697 U	0.000606 U	0.000849 U	0.000758 U	0.00618 U
	MW-309-45	09/19/19	PES	PACE	45	-14.6	S	–	–	–	–	0.000631 U	0.000347 U	0.000492 U	0.00111 U	0.000851 U	0.000725 U	0.000631 U	0.000883 U	0.000788 U	0.00643 U
	MW-309-50	09/19/19	PES	PACE	50	-19.6	S	–	–	–	–	0.000596 U	0.000328 U	0.000465 U	0.00105 U	0.000804 U	0.000685 U	0.000596 U	0.000834 U	0.000745 U	0.00608 U
	MW-309-55	09/19/19	PES	PACE	55	-24.6	S	–	–	–	–	0.000555 U	0.000305 U	0.000433 U	0.000980 U	0.000749 U	0.000638 U	0.000555 U	0.000777 U	0.000694 U	0.00566 U
	MW-309-60	09/19/19	PES	PACE	60	-29.6	S	–	–	–	–	0.000559 U	0.000307 U	0.000436 U	0.000986 U	0.000754 U	0.000642 U	0.000559 U	0.000782 U	0.000698 U	0.00569 U
	MW-309-65	09/19/19	PES	PACE	65	-34.6	S	–	–	–	–	0.000562 U	0.000309 U	0.000438 U	0.000992 U	0.000758 U	0.000646 U	0.000562 U	0.000786 U	0.000702 U	0.00573 U
	MW-309-70	09/19/19	PES	PACE	70	-39.6	S	–	–	–	–	0.000569 U	0.000313 U	0.000443 U	0.00100 U	0.000768 U	0.000654 U	0.000569 U	0.000796 U	0.000711 U	0.00580 U
	MW-309-75	09/19/19	PES	PACE	75	-44.6	S	–	–	–	–	0.000540 U	0.000297 U	0.000422 U	0.000954 U	0.000730 U	0.000621 U	0.000540 U	0.000757 U	0.000676 U	0.00551 U
MW-311 (-29.0 to -39.0)	MW-311-5	09/18/19	PES	PACE	5	28.1	V	–	–	–	–	0.000599 U	0.000329 U	0.000467 UJ	0.00106 U	0.000808 U	0.000688 U	0.000599 U	0.000838 U	0.000748 U	0.00610 U
	MW-311-10	09/18/19	PES	PACE	10	23.1	S	–	–	–	–	0.000576 U	0.000317 U	0.000449 UJ	0.00102 U	0.000777 U	0.000662 U	0.000576 U	0.000806 U	0.000719 U	0.00587 U
	MW-311-15	09/18/19	PES	PACE	15	18.1	S	–	–	–	–	0.00134 U	0.000738 U	0.00105 UJ	0.00237 U	0.00181 U	0.00154 U	0.00134 U	0.00188 U	0.00168 U	0.0137 U
	MW-311-20	09/18/19	PES	PACE	20	13.1	S	–	–	–	–	0.00140 U	0.000769 U	0.00109 UJ	0.00247 U	0.00189 U	0.00160 U	0.00140 U	0.00196 U	0.00175 U	0.0143 U
	MW-311-25	09/18/19	PES	PACE	25	8.1	S	–	–	–	–	0.00248 U	0.00137 U	0.00194 UJ	0.00438 U	0.00335 U	0.00286 U	0.00248 U	0.00348 U	0.00310 U	0.0253 U
	MW-311-30	09/18/19	PES	PACE	30	3.1	S	–	–	–	–	0.00132 U	0.000722 U	0.00102 UJ	0.00231 U	0.00177 U	0.00150 U	0.00132 U	0.00184 U	0.00164 U	0.0134 U
	MW-311-35	09/18/19	PES	PACE	35	-1.9	S	–	–	–	–	0.00117 U	0.000642 U	0.000910 UJ	0.00206 U	0.00157 U	0.00134 U	0.00117 U	0.00163 U	0.00146 U	0.0119 U
	MW-311-40	09/18/19	PES	PACE	40	-6.9	S	–	–	–	–	0.000586 U	0.000322 U	0.000457 UJ	0.00103 U	0.000791 U	0.000674 U	0.000586 U	0.000820 U	0.000732 U	0.00598 U
	MW-311-45	09/18/19	PES	PACE	45	-11.9	S	–	–	–	–	0.000628 U	0.000345 U	0.000490 UJ	0.00111 U	0.000847 U	0.000722 U	**0.000838 J**	0.000879 U	0.000784 U	0.00640 U
	MW-311-50	09/18/19	PES	PACE	50	-16.9	S	–	–	–	–	0.000584 U	0.000321 U	0.000455 UJ	0.00103 U	0.000788 U	0.000671 U	**0.000999 J**	0.000817 U	0.000730 U	0.00595 U
	MW-311-55	09/18/19	PES	PACE	55	-21.9	S	–	–	–	–	0.000553 U	0.000304 U	0.000431 UJ	0.000976 U	0.000746 U	0.000636 U	**0.00508**	0.000774 U	0.000691 U	0.00564 U
	MW-311-60	09/18/19	PES	PACE	60	-26.9	S	–	–	–	–	0.00110 U	0.000603 U	0.000855 UJ	0.00194 U	0.00148 U	0.00126 U	0.00110 U	0.00153 U	0.00137 U	0.0112 U
	MW-311-65	09/18/19	PES	PACE	65	-31.9	S	–	–	–	–	0.000530 U	0.000291 U	0.000413 UJ	0.000936 U	0.000715 U	0.000609 U	0.000530 U	0.000742 U	0.000662 U	0.00541 U
	MW-2005-65	09/18/19	PES	PACE	65 (dup)	-31.9	S	–	–	–	–	0.000549 U	0.000302 U	0.000428 U	0.000969 U	0.000740 U	0.000631 U	0.000549 U	0.000768 U	0.000686 U	0.00559 U
	MW-311-70	09/18/19	PES	PACE	70	-36.9	S	–	–	–	–	0.000551 U	0.000303 U	0.000430 U	0.000973 U	0.000744 U	0.000634 U	0.000551 U	0.000771 U	0.000689 U	0.00562 U
	MW-2007-70	09/18/19	PES	PACE	70 (dup)	-38.3	S	–	–	–	–	0.00107 U	0.000586 U	0.000831 U	0.00189 U	0.00144 U	0.00123 U	0.00107 U	0.00149 U	0.00133 U	0.0109 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
MW-312	MW-312-6	09/16/19	PES	PACE	6	29.6	V	–	–	–	–	0.000608 U	0.000335 U	0.000474 UJ	0.00107 U	0.000821 U	0.000700 U	0.000608 U	0.000852 U	0.000760 U	0.00620 U
(19.9 to9.9)	MW-312-10	09/16/19	PES	PACE	10	25.6	V	–	–	–	–	0.00101 U	0.000559 U	0.000792 UJ	0.00180 U	0.00137 U	0.00117 U	0.00101 U	0.00142 U	0.00127 U	0.0103 U
	MW-312-15	09/16/19	PES	PACE	15	20.6	S	–	–	–	–	0.000691 U	0.000380 U	0.000540 UJ	0.00122 U	0.000933 U	0.000795 U	0.000691 U	0.000968 U	0.000864 U	0.00705 U
	MW-312-20	09/16/19	PES	PACE	20	15.6	S	–	–	–	–	0.000541 U	0.000298 U	0.000422 UJ	0.000955 U	0.000730 U	0.000622 U	0.000541 U	0.000757 U	0.000676 U	0.00552 U
	MW-2004-20	09/16/19	PES	PACE	20	15.6	S	–	–	–	–	0.000577 U	0.000318 U	0.000450 UJ	0.00102 U	0.000779 U	0.000664 U	0.000577 U	0.000808 U	0.000722 U	0.00589 U
	MW-312-25	09/16/19	PES	PACE	25	10.6	S	–	–	–	–	0.000559 U	0.000308 U	0.000436 UJ	0.000988 U	0.000755 U	0.000643 U	0.000559 U	0.000783 U	0.000699 U	0.00570 U
MW-314	MW-314-6	09/13/19	PES	PACE	6	33.8	V	–	–	–	–	0.000568 U	0.000312 U	0.000443 U	0.00100 U	0.000767 U	0.000653 U	0.000568 U	0.000795 U	0.000710 U	0.00579 U
(-28.0 to -38.0)	MW-314-10	09/13/19	PES	PACE	10	29.8	V	–	–	–	–	0.000574 U	0.000316 U	0.000447 U	0.00101 U	0.000775 U	0.000660 U	0.000574 U	0.000803 U	0.000717 U	0.00586 U
	MW-314-15	09/13/19	PES	PACE	15	24.8	V	–	–	–	–	0.000563 U	0.000309 U	0.000439 U	0.000993 U	0.000759 U	0.000647 U	0.000563 U	0.000788 U	0.000703 U	0.00574 U
	MW-314-20	09/13/19	PES	PACE	20	19.8	S	–	–	–	–	0.000574 U	0.000316 U	0.000448 U	0.00101 U	0.000775 U	0.000660 U	0.000574 U	0.000803 U	0.000717 U	0.00585 U
	MW-314-25	09/13/19	PES	PACE	25	14.8	S	–	–	–	–	0.000635 U	0.000349 U	0.000495 U	0.00112 U	0.000857 U	0.000730 U	0.000635 U	0.000889 U	0.000794 U	0.00648 U
	MW-2002-25	09/13/19	PES	PACE	25	14.8	S	–	–	–	–	0.000631 U	0.000347 U	0.000492 UJ	0.00111 U	0.000852 U	0.000726 U	0.000631 U	0.000884 U	0.000789 U	0.00644 U
	MW-314-30	09/13/19	PES	PACE	30	9.8	S	–	–	–	–	0.000622 U	0.000342 U	0.000485 U	0.00110 U	0.000840 U	0.000715 U	0.000622 U	0.000871 U	0.000778 U	0.00634 U
	MW-314-35	09/13/19	PES	PACE	35	4.8	S	–	–	–	–	0.000536 U	0.000295 U	0.000418 U	0.000947 U	0.000724 U	0.000617 U	0.000536 U	0.000751 U	0.000670 U	0.00547 U
	MW-314-40	09/13/19	PES	PACE	40	-0.2	S	–	–	–	–	0.000557 U	0.000307 U	0.000435 U	0.000985 U	0.000753 U	0.000641 U	**0.00566**	0.000780 U	0.000697 U	0.00569 U
	MW-314-45	09/13/19	PES	PACE	45	-5.2	S	–	–	–	–	0.000553 U	0.000304 U	0.000432 U	0.000977 U	0.000747 U	0.000636 U	0.000553 U	0.000775 U	0.000692 U	0.00564 U
	MW-314-50	09/13/19	PES	PACE	50	-10.2	S	–	–	–	–	0.000557 U	0.000306 U	0.000434 U	0.000983 U	0.000751 U	0.000640 U	0.000557 U	0.000779 U	0.000696 U	0.00568 U
	MW-314-55	09/13/19	PES	PACE	55	-15.2	S	–	–	–	–	0.000604 U	0.000332 U	0.000471 U	0.00107 U	0.000815 U	0.000694 U	0.000604 U	0.000845 U	0.000755 U	0.00616 U
	MW-314-60	09/13/19	PES	PACE	60	-20.2	S	–	–	–	–	0.000553 U	0.000304 U	0.000431 U	0.000977 U	0.000747 U	0.000636 U	0.000553 U	0.000774 U	0.000691 U	0.00564 U
	MW-314-65	09/13/19	PES	PACE	65	-25.2	S	–	–	–	–	0.000568 U	0.000312 U	0.000443 UJ	0.00100 U	0.000766 U	0.000653 U	0.000568 U	0.000795 U	0.000710 U	0.00579 U
	MW-314-70	09/13/19	PES	PACE	70	-30.2	S	–	–	–	–	0.00607 U	0.00334 U	0.00473 UJ	0.0107 U	0.00820 U	0.00699 U	0.00607 U	0.00851 U	0.00759 U	0.0620 U
	MW-314-75	09/13/19	PES	PACE	75	-35.2	S	–	–	–	–	0.00114 U	0.000628 U	0.000890 UJ	0.00202 U	0.00154 U	0.00131 U	0.00114 U	0.00160 U	0.00143 U	0.0116 U
	MW-314-80	09/13/19	PES	PACE	80	-40.2	S	–	–	–	–	0.000747 U	0.000411 U	0.000583 UJ	0.00132 U	0.00101 U	0.000859 U	0.000747 U	0.00105 U	0.000933 U	0.00761 U
MW-316	MW-316-5	09/09/19	PES	PACE	5	44.8	V	–	–	–	–	0.000541 U	0.000298 U	0.000422 U	0.000956 U	0.000731 U	0.000622 U	0.000541 U	0.000758 U	0.000677 U	0.00552 U
(-10.0 to -20.0)	MW-316-10	09/09/19	PES	PACE	10	39.8	V	–	–	–	–	0.000566 U	0.000311 U	0.000441 U	0.000999 U	0.000764 U	0.000650 U	0.000566 U	0.000792 U	0.000707 U	0.00577 U
	MW-316-15	09/09/19	PES	PACE	15	34.8	V	–	–	–	–	0.000562 U	0.000309 U	0.000439 U	0.000993 U	0.000759 U	0.000647 U	0.000562 U	0.000787 U	0.000703 U	0.00573 U
	MW-316-20	09/09/19	PES	PACE	20	29.8	V	–	–	–	–	0.000539 U	0.000297 U	0.000421 U	0.000953 U	0.000728 U	0.000620 U	0.000539 U	0.000755 U	0.000674 U	0.00550 U
	MW-316-25	09/09/19	PES	PACE	25	24.8	S	–	–	–	–	0.000567 U	0.000312 U	0.000442 U	0.00100 U	0.000766 U	**0.00317**	**0.000568 J**	0.000794 U	0.000709 U	0.00579 U
	MW-316-30	09/09/19	PES	PACE	30	19.8	S	–	–	–	–	0.000555 U	0.000305 U	0.000433 U	0.000980 U	0.000749 U	0.000638 U	0.000555 U	0.000777 U	0.000693 U	0.00566 U
	MW-316-35	09/09/19	PES	PACE	35	14.8	S	–	–	–	–	0.000564 U	0.000310 U	0.000440 U	0.000997 U	0.000762 U	0.000649 U	0.000564 U	0.000790 U	0.000706 U	0.00576 U
	MW-316-40	09/09/19	PES	PACE	40	9.8	S	–	–	–	–	0.000569 U	0.000313 U	0.000444 U	0.00100 U	0.000768 U	0.000654 U	0.000569 U	0.000797 U	0.000711 U	0.00580 U
	MW-316-45	09/09/19	PES	PACE	45	4.8	S	–	–	–	–	0.000556 U	0.000306 U	0.000434 U	0.000982 U	0.000751 U	0.000639 U	0.000556 U	0.000778 U	0.000695 U	0.00567 U
	MW-316-50	09/09/19	PES	PACE	50	-0.2	S	–	–	–	–	0.000598 U	0.000329 U	0.000467 U	0.00106 U	0.000808 U	0.000688 U	0.000598 U	0.000838 U	0.000748 U	0.00610 U
	MW-316-55	09/09/19	PES	PACE	55	-5.2	S	–	–	–	–	0.000566 U	0.000311 U	0.000442 U	0.00100 U	0.000764 U	0.000651 U	0.000566 U	0.000793 U	0.000708 U	0.00578 U
	MW-316-60	09/09/19	PES	PACE	60	-10.2	S	–	–	–	–	0.000562 U	0.000309 U	0.000438 U	0.000993 U	0.000759 U	0.000646 U	0.000562 U	0.000787 U	0.000703 U	0.00573 U
	MW-316-65	09/10/19	PES	PACE	65	-15.2	S	–	–	–	–	0.000748 U	0.000412 U	0.000584 U	0.00132 U	0.00101 U	0.000861 U	0.000748 U	0.00105 U	0.000935 U	0.00763 U
	MW-2001-65	09/10/19	PES	PACE	65	-15.2	S	–	–	–	–	0.000592 U	0.000326 U	0.000462 U	0.00105 U	0.000799 U	0.000681 U	0.000592 U	0.000829 U	0.000740 U	0.00604 U
	MW-316-70	09/10/19	PES	PACE	70	-20.2	S	–	–	–	–	0.000566 U	0.000311 U	0.000441 U	0.000999 U	0.000764 U	0.000651 U	0.000566 U	0.000792 U	0.000707 U	0.00577 U
MW-319	MW-319-6	09/18/19	PES	PACE	6	25.7	V	–	–	–	–	0.000580 U	0.000319 U	0.000452 U	0.00102 U	0.000783 U	0.000667 U	0.000580 U	0.000812 U	0.000725 U	0.00592 U
(-42.8 to -52.8)	MW-319-10	09/18/19	PES	PACE	10	21.7	S	–	–	–	–	0.000576 U	0.000317 U	0.000450 U	0.00102 U	0.000778 U	0.000663 U	0.000576 U	0.000807 U	0.000721 U	0.00588 U
	MW-319-15	09/18/19	PES	PACE	15	16.7	S	–	–	–	–	0.000573 U	0.000315 U	0.000447 U	0.00101 U	0.000773 U	0.000659 U	0.000573 U	0.000802 U	0.000716 U	0.00584 U
	MW-319-20	09/18/19	PES	PACE	20	11.7	S	–	–	–	–	0.000619 U	0.000341 U	0.000483 U	0.00109 U	0.000836 U	0.000712 U	0.000619 U	0.000867 U	0.000774 U	0.00632 U
	MW-319-30	09/18/19	PES	PACE	30	1.7	S	–	–	–	–	0.000571 U	0.000314 U	0.000446 U	0.00101 U	0.000771 U	0.000657 U	0.000571 U	0.000800 U	0.000714 U	0.00583 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
MW-319	MW-319-35	09/18/19	PES	PACE	35	-3.3	S	–	–	–	–	0.000631 U	0.000347 U	0.000492 U	0.00111 U	0.000851 U	0.000725 U	0.000631 U	0.000883 U	0.000788 U	0.00643 U
(continued)	MW-319-40	09/18/19	PES	PACE	40	-8.3	S	–	–	–	–	0.000590 U	0.000325 U	0.000460 U	0.00104 U	0.000797 U	0.000679 U	0.000590 U	0.000826 U	0.000738 U	0.00602 U
	MW-319-45	09/18/19	PES	PACE	45	-13.3	S	–	–	–	–	0.000594 U	0.000327 U	0.000463 U	0.00105 U	0.000802 U	0.000683 U	0.000594 U	0.000831 U	0.000742 U	0.00606 U
	MW-319-50	09/18/19	PES	PACE	50	-18.3	S	–	–	–	–	0.000611 U	0.000336 U	0.000476 U	0.00108 U	0.000824 U	0.000702 U	0.000611 U	0.000855 U	0.000763 U	0.00623 U
	MW-319-55	09/18/19	PES	PACE	55	-23.3	S	–	–	–	–	0.000631 U	0.000347 U	0.000493 U	0.00112 U	0.000852 U	0.000726 U	0.000631 U	0.000884 U	0.000789 U	0.00644 U
	MW-319-60	09/18/19	PES	PACE	60	-28.3	S	–	–	–	–	0.000594 U	0.000327 U	0.000463 U	0.00105 U	0.000802 U	0.000683 U	0.000594 U	0.000831 U	0.000742 U	0.00606 U
	MW-319-65	09/18/19	PES	PACE	65	-33.3	S	–	–	–	–	0.000637 U	0.000351 U	0.000497 U	0.00113 U	0.000860 U	0.000733 U	0.000637 U	0.000892 U	0.000797 U	0.00650 U
	MW-319-70	09/18/19	PES	PACE	70	-38.3	S	–	–	–	–	0.000609 U	0.000335 U	0.000475 U	0.00108 U	0.000823 U	0.000701 U	0.000609 U	0.000853 U	0.000762 U	0.00621 U
	MW-2006-70	09/18/19	PES	PACE	70 (dup)	-36.9	S	–	–	–	–	0.000627 U	0.000345 U	0.000489 UJ	0.00111 U	0.000846 U	0.000721 U	0.000627 U	0.000877 U	0.000783 U	0.00639 U
	MW-319-75	09/18/19	PES	PACE	75	-43.3	S	–	–	–	–	0.000554 U	0.000305 U	0.000432 U	0.000978 U	0.000748 U	**0.00211 J**	**0.00162 J**	0.000775 U	0.000692 U	0.00565 U
	MW-319-80	09/18/19	PES	PACE	80	-48.3	S	–	–	–	–	0.000608 U	0.000334 U	0.000474 UJ	0.00107 U	0.000820 U	0.000699 U	0.000608 U	0.000851 U	0.000760 U	0.00620 U
	MW-319-85	09/18/19	PES	PACE	85	-53.3	S	–	–	–	–	0.000601 U	0.000331 U	0.000469 UJ	0.00106 U	0.000812 U	0.000692 U	0.000601 U	0.000842 U	0.000752 U	0.00614 U
MW-320	MW-320-19	09/29/19	PES	PACE	19	15.1	S	**707**	–	–	–	0.0112 U	0.00614 U	0.00871 U	0.0198 U	0.0151 U	0.0128 U	0.0112 U	0.0156 U	0.0140 U	0.114 U
(18.6 to 8.6)	MW-320-27	09/29/19	PES	PACE	27	7.1	S	0.982 U	–	–	–	0.000579 U	0.000318 U	0.000452 U	0.00102 U	0.000782 U	0.000666 U	0.000579 U	0.000811 U	0.000724 U	0.00591 U
MW-323	MW-323-10	09/28/19	PES	PACE	10	24.7	V	–	–	–	–	0.00122 U	**0.00172 J**	0.000951 U	0.00216 U	0.00165 U	0.00140 U	0.00122 U	0.00171 U	0.00152 U	0.0124 U
(-65.4 to -75.4)	MW-2012-10	09/28/19	PES	PACE	10 (dup)	24.7	V	–	–	–	–	0.000625 U	0.000344 U	0.000487 U	0.00110 U	0.000844 U	0.000719 U	0.000625 U	0.000875 U	0.000782 U	0.00637 U
	MW-323-15	09/28/19	PES	PACE	15	19.7	S	–	–	–	–	0.00115 U	0.000630 U	0.000895 U	0.00202 U	0.00155 U	0.00131 U	0.00115 U	0.00161 U	0.00144 U	0.0117 U
	MW-323-20	09/28/19	PES	PACE	20	14.7	S	–	–	–	–	0.000565 U	0.000311 U	0.000440 U	0.000997 U	0.000762 U	0.000649 U	0.000565 U	0.000790 U	0.000706 U	0.00576 U
	MW-323-25	09/28/19	PES	PACE	25	9.7	S	–	–	–	–	0.000570 U	0.000314 U	0.000445 U	0.00101 U	0.000770 U	0.000656 U	0.000570 U	0.000798 U	0.000713 U	0.00582 U
	MW-323-30	09/28/19	PES	PACE	30	4.7	S	–	–	–	–	0.00106 U	0.000584 U	0.000828 U	0.00188 U	0.00143 U	0.00122 U	0.00106 U	0.00149 U	0.00133 U	0.0108 U
	MW-323-35	09/28/19	PES	PACE	35	-0.4	S	–	–	–	–	0.000643 U	0.000353 U	0.000501 U	0.00113 U	0.000868 U	0.000739 U	0.000643 U	0.000900 U	0.000803 U	0.00655 U
	MW-323-40	09/28/19	PES	PACE	40	-5.4	S	–	–	–	–	0.000642 U	0.000353 U	0.000501 U	0.00113 U	0.000867 U	0.000738 U	0.000642 U	0.000899 U	0.000803 U	0.00655 U
	MW-323-45	09/28/19	PES	PACE	45	-10.4	S	–	–	–	–	0.000640 U	0.000352 U	0.000499 U	0.00113 U	0.000864 U	0.000736 U	0.000640 U	0.000896 U	0.000800 U	0.00652 U
	MW-323-50	09/28/19	PES	PACE	50	-15.4	S	–	–	–	–	0.000575 U	0.000317 U	0.000449 U	0.00102 U	0.000777 U	0.000662 U	0.000575 U	0.000806 U	0.000719 U	0.00587 U
	MW-323-55	09/28/19	PES	PACE	55	-20.4	S	–	–	–	–	0.000583 U	0.000320 U	0.000454 U	0.00103 U	0.000787 U	0.000670 U	**0.000733 J**	0.000816 U	0.000728 U	0.00594 U
	MW-323-60	09/28/19	PES	PACE	60	-25.4	S	–	–	–	–	0.000641 U	0.000353 U	0.000500 U	0.00113 U	0.000866 U	0.000737 U	**0.00201 J**	0.000897 U	0.000801 U	0.00654 U
	MW-2010-60	09/28/19	PES	PACE	60 (dup)	-25.4	S	–	–	–	–	0.000610 U	0.000335 U	0.000475 U	0.00108 U	0.000823 U	0.000701 U	0.000610 U	0.000853 U	0.000762 U	0.00622 U
	MW-323-65	09/28/19	PES	PACE	65	-30.4	S	–	–	–	–	0.000601 U	0.000330 U	0.000469 U	0.00106 U	0.000811 U	0.000691 U	0.000601 U	0.000841 U	0.000751 U	0.00613 U
	MW-323-70	09/28/19	PES	PACE	70	-35.4	S	–	–	–	–	0.0841 U	0.0462 U	0.0656 U	0.149 U	0.114 U	0.0967 U	0.0841 U	0.118 U	0.105 U	0.858 U
	MW-323-75	09/28/19	PES	PACE	75	-40.4	S	–	–	–	–	0.000588 U	0.000323 U	0.000458 U	0.00104 U	0.000793 U	0.000676 U	0.000588 U	0.000823 U	0.000734 U	0.00599 U
	MW-323-80	09/28/19	PES	PACE	80	-45.4	S	–	–	–	–	0.000565 U	0.000311 U	0.000441 U	0.000998 U	0.000763 U	0.000650 U	0.000565 U	0.000791 U	0.000706 U	0.00576 U
	MW-323-85	09/28/19	PES	PACE	85	-50.4	S	–	–	–	–	0.000599 U	0.000329 U	0.000467 U	0.00106 U	0.000808 U	0.000689 U	0.000599 U	0.000838 U	0.000748 U	0.00611 U
	MW-323-91	09/28/19	PES	PACE	91	-56.4	S	–	–	–	–	0.00142 U	0.000779 U	0.00111 U	0.00250 U	0.00192 U	0.00162 U	0.00142 U	0.00198 U	0.00177 U	0.0144 U
	MW-323-95	09/28/19	PES	PACE	95	-60.4	S	–	–	–	–	0.000599 U	0.000330 U	0.000468 U	0.00106 U	0.000809 U	0.000689 U	0.000599 U	0.000839 U	0.000749 U	0.00611 U
	MW-323-99	09/28/19	PES	PACE	99	-64.4	S	–	–	–	–	0.000578 U	0.000318 U	0.000451 U	0.00102 U	0.000780 U	0.000665 U	0.000578 U	0.000809 U	0.000723 U	0.00590 U
	MW-323-105	09/28/19	PES	PACE	105	-70.4	S	–	–	–	–	0.000590 U	0.000325 U	0.000461 U	0.00104 U	0.000797 U	0.000679 U	0.000590 U	0.000827 U	0.000738 U	0.00602 U
	MW-323-110	09/28/19	PES	PACE	110	-75.4	S	–	–	–	–	0.00123 U	0.000674 U	0.000955 U	0.00217 U	0.00166 U	0.00141 U	0.00123 U	0.00171 U	0.00153 U	0.0125 U
MW-324	MW-324-6	09/12/19	PES	PACE	6	28.3	V	–	–	–	–	0.000562 U	0.000309 U	0.000439 U	0.000993 U	0.000759 U	0.000647 U	0.000562 U	0.000787 U	0.000703 U	0.00574 U
(-32.1 to -42.1)	MW-324-10	09/12/19	PES	PACE	10	24.3	V	–	–	–	–	0.000579 U	0.000318 U	0.000452 U	0.00102 U	0.000782 U	0.000666 U	0.000579 U	0.000811 U	0.000724 U	0.00591 U
	MW-324-15	09/12/19	PES	PACE	15	19.3	S	–	–	–	–	0.000546 U	0.000300 U	0.000426 U	0.000964 U	0.000737 U	0.000628 U	0.000546 U	0.000764 U	0.000683 U	0.00557 U
	MW-324-20	09/12/19	PES	PACE	20	14.3	S	–	–	–	–	0.000583 U	0.000321 U	0.000455 U	0.00103 U	0.000788 U	0.000671 U	0.000583 U	0.000817 U	0.000729 U	0.00595 U
	MW-324-25	09/12/19	PES	PACE	25	9.3	S	–	–	–	–	0.000590 U	0.000325 U	0.000460 U	0.00104 U	0.000797 U	0.000679 U	0.000590 U	0.000826 U	0.000738 U	0.00602 U
	MW-324-30	09/12/19	PES	PACE	30	4.3	S	–	–	–	–	0.000615 U	0.000337 U	0.000480 U	0.00109 U	0.000829 U	0.000706 U	0.000615 U	0.000860 U	0.000769 U	0.00627 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
MW-324 (continued)	MW-324-35	09/12/19	PES	PACE	35	-0.7	S	–	–	–	–	0.000597 U	0.000328 U	0.000466 U	0.00105 U	0.000806 U	0.000686 U	0.000597 U	0.000836 U	0.000746 U	0.00609 U
	MW-324-40	09/12/19	PES	PACE	40	-5.7	S	–	–	–	–	0.000604 U	0.000332 U	0.000471 U	0.00107 U	0.000816 U	0.000695 U	0.000604 U	0.000846 U	0.000755 U	0.00616 U
	MW-324-45	09/12/19	PES	PACE	45	-10.7	S	–	–	–	–	0.000629 U	0.000346 U	0.000491 U	0.00111 U	0.000850 U	0.000724 U	0.000629 U	0.000881 U	0.000787 U	0.00642 U
	MW-324-50	09/12/19	PES	PACE	50	-15.7	S	–	–	–	–	0.000500 U	0.000275 U	0.000390 U	0.000883 U	0.000675 U	0.000575 U	0.000500 U	0.000700 U	0.000625 U	0.00510 U
	MW-324-55	09/12/19	PES	PACE	55	-20.7	S	–	–	–	–	0.000567 U	0.000312 U	0.000442 U	0.00100 U	0.000765 U	0.000652 U	0.000567 U	0.000793 U	0.000708 U	0.00578 U
	MW-324-60	09/12/19	PES	PACE	60	-25.7	S	–	–	–	–	0.000567 U	0.000312 U	0.000442 U	0.00100 U	0.000765 U	0.000652 U	0.000567 U	0.000793 U	0.000708 U	0.00578 U
	MW-324-65	09/12/19	PES	PACE	65	-30.7	S	–	–	–	–	0.000588 U	0.000324 U	0.000459 U	0.00104 U	0.000794 U	0.000677 U	**0.00307**	0.000823 U	0.000735 U	0.00600 U
	MW-324-70	09/12/19	PES	PACE	70	-35.7	S	–	–	–	–	0.000620 U	0.000342 U	0.000483 U	0.00110 U	0.000838 U	0.000714 U	**0.00188 J**	0.000868 U	0.000775 U	0.00633 U
	MW-324-75	09/12/19	PES	PACE	75	-40.7	S	–	–	–	–	0.000627 U	0.000345 U	0.000489 U	0.00111 U	0.000847 U	0.000721 U	**0.00111 J**	0.000878 U	0.000784 U	0.00640 U
	MW-324-80	09/12/19	PES	PACE	80	-45.7	S	–	–	–	–	0.000626 U	0.000344 U	0.000488 U	0.00111 U	0.000845 U	0.000720 U	**0.00232 J**	0.000876 U	0.000782 U	0.00638 U
MW-326 (-48.7 to -58.7)	MW-326-5	09/09/19	PES	PACE	5	36.3	V	–	–	–	–	0.000551 U	0.000303 U	0.000430 U	0.000973 U	0.000744 U	0.000634 U	0.000551 U	0.000771 U	0.000689 U	0.00562 U
	MW-326-10	09/09/19	PES	PACE	10	31.3	V	–	–	–	–	0.000665 U	0.000365 U	0.000519 U	0.00117 U	0.000898 U	0.000765 U	0.000665 U	0.000932 U	0.000832 U	0.00679 U
	MW-326-15	09/09/19	PES	PACE	15	26.3	V	–	–	–	–	0.000585 U	0.000322 U	0.000456 U	0.00103 U	0.000789 U	0.000672 U	0.000585 U	0.000819 U	0.000731 U	0.00596 U
	MW-326-20	09/09/19	PES	PACE	20	21.3	S	–	–	–	–	0.000585 U	0.000322 U	0.000457 U	0.00103 U	0.000790 U	0.000673 U	0.000585 U	0.000819 U	0.000732 U	0.00597 U
	MW-326-25	09/09/19	PES	PACE	25	16.3	S	–	–	–	–	0.000620 U	0.000341 U	0.000484 U	0.00110 U	0.000838 U	0.000714 U	0.000620 U	0.000869 U	0.000776 U	0.00633 U
	MW-326-30	09/09/19	PES	PACE	30	11.3	S	–	–	–	–	0.00203 U	0.00111 U	0.00158 U	0.00357 U	0.00273 U	0.00233 U	0.00203 U	0.00283 U	0.00253 U	0.0206 U
	MW-326-35	09/09/19	PES	PACE	35	6.3	S	–	–	–	–	0.000618 U	0.000340 U	0.000482 U	0.00109 U	0.000835 U	0.000711 U	0.000618 U	0.000866 U	0.000773 U	0.00631 U
	MW-326-40	09/09/19	PES	PACE	40	1.3	S	–	–	–	–	0.000596 U	0.000328 U	0.000465 U	0.00105 U	0.000805 U	0.000686 U	0.000596 U	0.000835 U	0.000745 U	0.00608 U
	MW-326-45	09/09/19	PES	PACE	45	-3.7	S	–	–	–	–	0.000602 U	0.000331 U	0.000470 U	0.00106 U	0.000813 U	0.000693 U	0.000602 U	0.000843 U	0.000753 U	0.00614 U
	MW-326-50	09/09/19	PES	PACE	50	-8.7	S	–	–	–	–	0.000572 U	0.000314 U	0.000446 U	0.00101 U	0.000772 U	0.000657 U	0.000572 U	0.000800 U	0.000715 U	0.00583 U
	MW-326-55	09/09/19	PES	PACE	55	-13.7	S	–	–	–	–	0.000608 U	0.000335 U	0.000474 U	0.00107 U	0.000821 U	0.000699 U	0.000608 U	0.000852 U	0.000760 U	0.00620 U
	MW-326-60	09/09/19	PES	PACE	60	-18.7	S	–	–	–	–	0.000543 U	0.000299 U	0.000424 U	0.000960 U	0.000734 U	0.000625 U	0.000543 U	0.000761 U	0.000679 U	0.00554 U
	MW-326-65	09/09/19	PES	PACE	65	-23.7	S	–	–	–	–	0.000580 U	0.000319 U	0.000452 UJ	0.00102 U	0.000782 U	0.000667 U	0.000580 U	0.000811 U	0.000724 U	0.00591 U
	MW-326-70	09/09/19	PES	PACE	70	-28.7	S	–	–	–	–	0.000609 U	0.000335 U	0.000475 UJ	0.00108 U	0.000822 U	0.000701 U	0.000609 U	0.000853 U	0.000762 U	0.00621 U
	MW-326-75	09/09/19	PES	PACE	75	-33.7	S	–	–	–	–	0.000606 U	0.000333 U	0.000473 UJ	0.00107 U	0.000818 U	0.000697 U	0.000606 U	0.000849 U	0.000758 U	0.00618 U
	MW-326-80	09/09/19	PES	PACE	80	-38.7	S	–	–	–	–	0.000594 U	0.000327 U	0.000464 UJ	0.00105 U	0.000802 U	0.000683 U	0.000594 U	0.000832 U	0.000743 U	0.00606 U
	MW-326-85	09/10/19	PES	PACE	85	-43.7	S	–	–	–	–	0.000584 U	0.000321 U	0.000456 UJ	0.00103 U	0.000789 U	0.000672 U	0.000584 U	0.000818 U	0.000730 U	0.00596 U
	MW-326-90	09/10/19	PES	PACE	90	-48.7	S	–	–	–	–	0.000589 U	0.000324 U	0.000459 UJ	0.00104 U	0.000795 U	0.000677 U	0.000589 U	0.000824 U	0.000736 U	0.00601 U
	MW-326-95	09/10/19	PES	PACE	95	-53.7	S	–	–	–	–	0.000562 U	0.000309 U	0.000438 UJ	0.000992 U	0.000758 U	0.000646 U	0.000562 U	0.000786 U	0.000702 U	0.00573 U
	MW-200I-95	09/10/19	PES	PACE	95 (dup)	-53.7	S	–	–	–	–	0.000570 U	0.000314 U	0.000445 U	0.00101 U	0.000770 U	0.000656 U	0.000570 U	0.000798 U	0.000713 U	0.00582 U
	MW-326-100	09/10/19	PES	PACE	100	-58.7	S	–	–	–	–	0.000604 U	0.000332 U	0.000471 UJ	0.00107 U	0.000816 U	0.000695 U	0.000604 U	0.000846 U	0.000755 U	0.00616 U
MW-328 (-36.1 to -46.1)	MW-328-5	09/16/19	PES	PACE	5	23.4	V	–	–	–	–	0.000594 U	0.000327 U	0.000464 UJ	0.00105 U	0.000802 U	0.000684 U	0.000594 U	0.000832 U	0.000743 U	0.00606 U
	MW-328-10	09/16/19	PES	PACE	10	18.4	S	–	–	–	–	0.000687 U	0.000378 U	0.000536 UJ	0.00121 U	0.000928 U	0.000790 U	0.000687 U	0.000962 U	0.000859 U	0.00701 U
	MW-328-15	09/16/19	PES	PACE	15	13.4	S	–	–	–	–	0.000614 U	0.000338 U	0.000479 UJ	0.00108 U	0.000829 U	0.000706 U	0.000614 U	0.000859 U	0.000767 U	0.00626 U
	MW-328-20	09/16/19	PES	PACE	20	8.4	S	–	–	–	–	0.000597 U	0.000328 U	0.000466 UJ	0.00105 U	0.000806 U	0.000687 U	0.000597 U	0.000836 U	0.000746 U	0.00609 U
	MW-328-30	09/16/19	PES	PACE	30	-1.6	S	–	–	–	–	0.0118 U	0.00648 U	0.00919 UJ	0.0209 U	0.0159 U	0.0135 U	0.0118 U	0.0165 U	0.0148 U	0.120 U
	MW-328-35	09/16/19	PES	PACE	35	-6.6	S	–	–	–	–	0.000643 U	0.000354 U	0.000501 UJ	0.00113 U	0.000868 U	0.000740 U	0.000643 U	0.000900 U	0.000803 U	0.00656 U
	MW-328-40	09/16/19	PES	PACE	40	-11.6	S	–	–	–	–	0.00146 U	0.000801 U	0.00114 UJ	0.00257 U	0.00197 U	0.00167 U	0.00146 U	0.00204 U	0.00182 U	0.0148 U
	MW-328-45	09/16/19	PES	PACE	45	-16.6	S	–	–	–	–	0.000617 U	0.000339 U	0.000481 UJ	0.00109 U	0.000832 U	0.000709 U	0.000617 U	0.000863 U	0.000771 U	0.00629 U
	MW-328-50	09/16/19	PES	PACE	50	-21.6	S	–	–	–	–	0.0183 U	0.0101 U	0.0144 UJ	0.0324 U	0.0247 U	0.0211 U	0.0183 U	0.0257 U	0.0230 U	0.187 U
	MW-328-55	09/16/19	PES	PACE	55	-26.6	S	–	–	–	–	0.000595 U	0.000327 U	0.000464 UJ	0.00105 U	0.000803 U	0.000684 U	0.000595 U	0.000833 U	0.000744 U	0.00607 U
	MW-328-60	09/16/19	PES	PACE	60	-31.6	S	–	–	–	–	0.000601 U	0.000331 U	0.000469 UJ	0.00106 U	0.000812 U	0.000691 U	0.000601 U	0.000842 U	0.000752 U	0.00613 U
	MW-328-65	09/16/19	PES	PACE	65	-36.6	S	–	–	–	–	0.000583 U	0.000321 U	0.000455 UJ	0.00103 U	0.000787 U	0.000670 U	0.000583 U	0.000816 U	0.000729 U	0.00595 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
MW-328 (continued)	MW-328-70	09/16/19	PES	PACE	70	-41.6	S	–	–	–	–	0.000602 U	0.000331 U	0.000470 UJ	0.00106 U	0.000813 U	0.000692 U	0.000602 U	0.000843 U	0.000753 U	0.00614 U
	MW-328-75	09/16/19	PES	PACE	75	-46.6	S	–	–	–	–	0.000583 U	0.000321 U	0.000455 UJ	0.00103 U	0.000787 U	0.000671 U	0.000583 U	0.000816 U	0.000729 U	0.00595 U
	MW-328-80	09/16/19	PES	PACE	80	-51.6	S	–	–	–	–	0.000660 U	0.000363 U	0.000515 UJ	0.00116 U	0.000890 U	0.000759 U	0.000660 U	0.000923 U	0.000825 U	0.00673 U
MW-329 (-69.0 to -79.0)	MW-329-5	09/12/19	PES	PACE	5	24.3	V	–	–	–	–	0.000534 U	0.000294 U	0.000417 U	0.000944 U	0.000721 U	0.000615 U	0.000534 U	0.000748 U	0.000668 U	0.00545 U
	MW-329-10	09/12/19	PES	PACE	10	19.3	S	–	–	–	–	0.000526 U	0.000289 U	0.000410 U	0.000929 U	0.000710 U	0.000605 U	0.000526 U	0.000736 U	0.000657 U	0.00536 U
	MW-329-15	09/12/19	PES	PACE	15	14.3	S	–	–	–	–	0.000549 U	0.000302 U	0.000428 U	0.000969 U	0.000741 U	0.000631 U	0.000549 U	0.000769 U	0.000686 U	0.00560 U
	MW-329-20	09/12/19	PES	PACE	20	9.3	S	–	–	–	–	0.000691 U	0.000380 U	**0.000783 J**	0.00122 U	0.000933 U	0.000795 U	0.000691 U	0.000968 U	0.000864 U	0.00705 U
	MW-329-25	09/12/19	PES	PACE	25	4.3	S	–	–	–	–	0.000717 U	0.000394 U	0.000559 U	0.00127 U	0.000967 U	0.000824 U	0.000717 U	0.00100 U	0.000896 U	0.00731 U
	MW-329-30	09/12/19	PES	PACE	30	-0.7	S	–	–	–	–	0.000618 U	0.000340 U	0.000482 U	0.00109 U	0.000834 U	0.000710 U	0.000618 U	0.000865 U	0.000772 U	0.00630 U
	MW-329-35	09/12/19	PES	PACE	35	-5.7	S	–	–	–	–	0.000613 U	0.000337 U	0.000478 U	0.00108 U	0.000827 U	0.000705 U	0.000613 U	0.000858 U	0.000766 U	0.00625 U
	MW-329-40	09/12/19	PES	PACE	40	-10.7	S	–	–	–	–	0.000616 U	0.000339 U	0.000481 U	0.00109 U	0.000832 U	0.000709 U	0.000616 U	0.000863 U	0.000770 U	0.00629 U
	MW-329-45	09/12/19	PES	PACE	45	-15.7	S	–	–	–	–	0.000596 U	0.000328 U	0.000465 U	0.00105 U	0.000805 U	0.000686 U	0.000596 U	0.000835 U	0.000745 U	0.00608 U
	MW-329-50	09/12/19	PES	PACE	50	-20.7	S	–	–	–	–	0.000616 U	0.000339 U	0.000481 U	0.00109 U	0.000832 U	0.000709 U	0.000616 U	0.000863 U	0.000770 U	0.00629 U
	MW-2003-50	09/12/19	PES	PACE	50 (dup)	-20.7	S	–	–	–	–	0.000546 U	0.000300 U	0.000426 U	0.000965 U	0.000737 U	0.000628 U	0.000546 U	0.000765 U	0.000683 U	0.00557 U
	MW-329-55	09/12/19	PES	PACE	55	-25.7	S	–	–	–	–	0.000577 U	0.000317 U	0.000450 U	0.00102 U	0.000779 U	0.000664 U	0.000577 U	0.000808 U	0.000721 U	0.00589 U
	MW-329-60	09/12/19	PES	PACE	60	-30.7	S	–	–	–	–	0.000585 U	0.000322 U	0.000456 U	0.00103 U	0.000790 U	0.000673 U	0.000585 U	0.000819 U	0.000731 U	0.00597 U
	MW-329-65	09/12/19	PES	PACE	65	-35.7	S	–	–	–	–	0.000584 U	0.000321 U	0.000456 U	0.00103 U	0.000789 U	0.000672 U	0.000584 U	0.000818 U	0.000730 U	0.00596 U
	MW-329-70	09/12/19	PES	PACE	70	-40.7	S	–	–	–	–	0.000583 U	0.000320 U	0.000455 U	0.00103 U	0.000787 U	0.000670 U	0.000583 U	0.000816 U	0.000728 U	0.00594 U
	MW-329-75	09/12/19	PES	PACE	75	-45.7	S	–	–	–	–	0.000573 U	0.000315 U	0.000447 U	0.00101 U	0.000773 U	0.000659 U	0.000573 U	0.000802 U	0.000716 U	0.00584 U
	MW-329-80	09/12/19	PES	PACE	80	-50.7	S	–	–	–	–	0.000607 U	0.000334 U	0.000474 UJ	0.00107 U	0.000820 U	0.000698 U	0.000607 U	0.000850 U	0.000759 U	0.00620 U
	MW-329-85	09/12/19	PES	PACE	85	-55.7	S	–	–	–	–	0.000585 U	0.000322 U	0.000456 U	0.00103 U	0.000789 U	0.000672 U	0.000585 U	0.000818 U	0.000731 U	0.00596 U
	MW-329-90	09/12/19	PES	PACE	90	-60.7	S	–	–	–	–	0.000588 U	0.000323 U	0.000459 U	0.00104 U	0.000794 U	0.000676 U	0.000588 U	0.000823 U	0.000735 U	0.00600 U
	MW-329-95	09/12/19	PES	PACE	95	-65.7	S	–	–	–	–	0.000594 U	0.000327 U	0.000463 U	0.00105 U	0.000801 U	0.000683 U	0.000594 U	0.000831 U	0.000742 U	0.00606 U
	MW-329-100	09/12/19	PES	PACE	100	-70.7	S	–	–	–	–	0.000595 U	0.000327 U	0.000464 U	0.00105 U	0.000804 U	0.000685 U	0.000595 U	0.000833 U	0.000744 U	0.00607 U
	MW-329-105	09/12/19	PES	PACE	105	-75.7	S	–	–	–	–	0.000550 U	0.000303 U	0.000429 U	0.000972 U	0.000743 U	0.000633 U	0.000550 U	0.000771 U	0.000688 U	0.00561 U
	MW-329-110	09/12/19	PES	PACE	110	-80.7	S	–	–	–	–	0.000546 U	0.000300 U	0.000426 U	0.000965 U	0.000737 U	0.000628 U	0.000546 U	0.000765 U	0.000683 U	0.00557 U
MW-330	MW-330-6	04/20/20	PES	PACE	6	46.0	V	–	–	–	–	0.00108 U	0.00105 U	0.000789 U	0.000678 U	0.000856 U	0.000558 U	0.000688 U	0.000919 U	0.00833 UJ	0.00184 U
	MW-330-10	04/20/20	PES	PACE	10	42.0	V	–	–	–	–	0.00105 U	0.00102 U	0.000767 U	0.000659 U	0.000832 U	0.000542 U	0.000669 U	0.000893 U	0.00809 UJ	0.00179 U
	MW-330-11.5	04/20/20	PES	PACE	11.5	40.5	V	–	–	–	–	0.00111 U	0.00108 U	0.000810 U	0.000696 U	0.000879 U	0.000572 U	0.000707 U	0.000943 U	0.00855 UJ	0.00189 U
	MW-330-16	04/20/20	PES	PACE	16	36.0	V	–	–	–	–	0.00108 U	0.00105 U	0.000790 U	0.000678 U	0.000857 U	0.000558 U	0.000688 U	0.000919 U	0.00833 UJ	0.00184 U
	MW-330-21.5	04/20/20	PES	PACE	21.5	30.5	S	–	–	–	–	0.00101 U	0.000983 U	0.000740 U	0.000636 U	0.000803 U	0.000523 U	0.000645 U	0.000861 U	0.00780 UJ	0.00172 U
	MW-330-27	04/20/20	PES	PACE	27	25.0	S	–	–	–	–	0.00102 U	0.000992 U	0.000747 U	0.000642 U	0.000811 U	0.000528 U	0.000652 U	0.000870 U	0.00788 UJ	0.00174 U
	MW-330-32	04/20/20	PES	PACE	32	20.0	S	–	–	–	–	0.00102 U	0.000994 U	0.000749 U	0.000643 U	0.000812 U	0.000529 U	0.000653 U	0.000871 U	0.00790 UJ	0.00174 U
	MW-330-38	04/20/20	PES	PACE	38	14.0	S	–	–	–	–	0.00102 U	0.000993 U	0.000748 U	0.000642 U	0.000811 U	0.000528 U	0.000652 U	0.000870 U	0.00789 UJ	0.00174 U
	MW-330-42	04/20/20	PES	PACE	42	10.0	S	–	–	–	–	0.000993 U	0.000966 U	0.000728 U	0.000625 U	0.000789 U	0.000514 U	0.000634 U	0.000847 U	0.00767 UJ	0.00170 U
	MW-330-47	04/20/20	PES	PACE	47	5.0	S	–	–	–	–	0.00107 U	0.00104 U	0.000787 U	0.000676 U	0.000854 U	0.000556 U	0.000686 U	0.000916 U	0.00830 UJ	0.00183 U
	MW-330-52	04/20/20	PES	PACE	52	0.0	S	–	–	–	–	0.00104 U	0.00101 U	0.000763 U	0.000655 U	0.000828 U	0.000539 U	0.000665 U	0.000888 U	0.00805 UJ	0.00178 U
	MW-330-58	04/20/20	PES	PACE	58	-6.0	S	–	–	–	–	0.00103 U	0.00100 U	0.000756 U	0.000650 U	0.000820 U	0.000534 U	0.000659 U	0.000880 U	0.00798 UJ	0.00176 U
	MW-330-62	04/20/20	PES	PACE	62	-10.0	S	–	–	–	–	0.00104 U	0.00101 U	0.000763 U	0.000656 U	0.000828 U	0.000539 U	0.000666 U	0.000889 U	0.00805 UJ	0.00178 U
MW-331	MW-331-7	04/17/20	PES	PACE	7	24.2	V	**49.7**	–	–	–	0.00146 U	0.00143 U	0.00107 U	0.000922 U	0.00116 U	0.000758 U	0.000936 U	0.00125 U	0.0113 U	0.00250 U
	MW-331-11	04/17/20	PES	PACE	11	20.2	S	**717**	–	–	–	0.00849 U	0.00827 U	0.00623 U	0.00535 U	0.00675 U	0.00440 U	0.00543 U	0.00725 U	0.0656 U	0.0146 U
	MW-331-16	04/17/20	PES	PACE	16	15.2	S	**7.34**	–	–	–	0.00112 U	0.00109 U	0.000820 U	0.000705 U	0.000890 U	0.000580 U	0.000715 U	0.000955 U	0.00865 U	0.00191 U
	MW-331-20	04/17/20	PES	PACE	20	11.2	S	**2.81 J**	–	–	–	0.00110 U	0.00107 U	0.000803 U	0.000690 U	0.000871 U	0.000567 U	0.000700 U	0.000935 U	0.00847 U	0.00187 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
MW-331 (continued)	MW-331-29.5	04/17/20	PES	PACE	29.5	1.7	S	**1.85 J**	–	–	–	0.00110 U	0.00107 U	0.000805 U	0.000692 U	0.000874 U	0.000569 U	0.000702 U	0.000938 U	0.00850 UJ	0.00188 U
	MW-331-35	04/17/20	PES	PACE	35	-3.8	S	–	–	–	–	0.00112 U	0.00109 U	0.000821 U	0.000705 U	0.000890 U	0.000580 U	0.000716 U	0.000955 U	0.00866 UJ	0.00191 U
	MW-2018-35	04/17/20	PES	PACE	35 (dup)	-3.8	S	–	–	–	–	0.00114 U	0.00111 U	0.000835 U	0.000717 U	0.000906 U	0.000590 U	0.000728 U	0.000972 U	0.00881 U	0.00195 U
	MW-331-40	04/17/20	PES	PACE	40	-8.8	S	–	–	–	–	0.00114 U	0.00111 U	0.000839 U	0.000720 U	0.000910 U	0.000592 U	0.000731 U	0.000976 U	0.00884 U	0.00195 U
	MW-331-45	04/17/20	PES	PACE	45	-13.8	S	–	–	–	–	0.00114 U	0.00111 U	0.000836 U	0.000718 U	0.000907 U	0.000590 U	0.000729 U	0.000973 U	0.00881 U	0.00195 U
MW-332	MW-332-7	04/17/20	PES	PACE	7	29.3	V	–	–	–	–	0.00106 U	0.00104 U	0.000779 U	0.000669 U	0.000846 U	0.000551 U	0.000680 U	0.000907 U	0.00822 U	0.00182 U
	MW-332-11	04/17/20	PES	PACE	11	25.3	V	–	–	–	–	0.00112 U	0.00109 U	0.000819 U	0.000703 U	0.000888 U	0.000578 U	0.000714 U	0.000953 U	0.00863 U	0.00191 U
	MW-332-16	04/17/20	PES	PACE	16	20.3	S	–	–	–	–	0.00109 U	0.00106 U	0.000802 U	0.000689 U	0.000870 U	0.000566 U	0.000699 U	0.000933 U	0.00846 U	0.00187 U
	MW-332-20	04/17/20	PES	PACE	20	16.3	S	–	–	–	–	0.00111 U	0.00108 U	0.000814 U	0.000700 U	0.000884 U	0.000575 U	0.000710 U	0.000948 U	0.00859 U	0.00190 U
	MW-332-25	04/17/20	PES	PACE	25	11.3	S	–	–	–	–	0.00115 U	0.00112 U	0.000843 U	0.000724 U	0.000915 U	0.000596 U	0.000735 U	0.000982 U	0.00889 U	0.00197 U
	MW-332-30	04/17/20	PES	PACE	30	6.3	S	–	–	–	–	0.00118 U	0.00114 U	0.000861 U	0.000740 U	0.000935 U	0.000609 U	0.000751 U	0.00100 U	0.00909 U	0.00201 U
MW-334	MW-334-6	04/16/20	PES	PACE	6	25.4	V	–	–	–	–	0.00115 U	0.00112 U	0.000844 U	0.000725 U	0.000916 U	0.000596 U	0.000736 U	0.000983 U	0.00890 U	0.00197 U
	MW-334-10	04/16/20	PES	PACE	10	21.4	V	**8.53**	–	–	–	0.00115 U	0.00112 U	0.000845 U	0.000726 U	0.000917 U	0.000597 U	0.000737 U	0.000984 U	0.00891 U	0.00197 U
	MW-334-13	04/16/20	PES	PACE	13	18.4	S	**644**	–	–	–	0.00853 U	0.00831 U	0.00626 U	0.00538 U	0.00679 U	0.00442 U	0.00546 U	0.00728 U	0.0660 U	0.0146 U
	MW-334-17	04/16/20	PES	PACE	17	14.4	S	**16.5**	–	–	–	0.000980 U	0.000954 U	0.000718 U	0.000617 U	0.000779 U	0.000507 U	0.000626 U	0.000836 U	0.00757 U	0.00167 U
	MW-334-23	04/16/20	PES	PACE	23	8.4	S	**3.93**	–	–	–	0.00113 U	0.00110 U	0.000827 U	0.000711 U	0.000897 U	0.000584 U	0.000721 U	0.000963 U	0.00872 U	0.00193 U
	MW-334-28	04/16/20	PES	PACE	28	3.4	S	–	–	–	–	0.00112 U	0.00109 U	0.000819 U	0.000703 U	0.000888 U	0.000578 U	0.000714 U	0.000953 U	0.00863 U	0.00191 U
	MW-334-35	04/16/20	PES	PACE	35	-3.6	S	–	–	–	–	0.00120 U	0.00117 U	0.000878 U	0.000755 U	0.000953 U	0.000621 U	0.000766 U	0.00102 U	0.00926 U	0.00205 U
	MW-334-40	04/16/20	PES	PACE	40	-8.6	S	–	–	–	–	0.00122 U	0.00119 U	0.000898 U	0.000771 U	0.000974 U	0.000634 U	0.000783 U	0.00104 U	0.00947 U	0.00209 U
	MW-334-45.5	04/16/20	PES	PACE	45.5	-14.1	S	–	–	–	–	0.00115 U	0.00112 U	0.000845 U	0.000726 U	0.000917 U	0.000597 U	0.000737 U	0.000984 U	0.00892 U	0.00197 U
	MW-334-50	04/16/20	PES	PACE	50	-18.6	S	–	–	–	–	0.00105 U	0.00102 U	0.000769 U	0.000661 U	0.000834 U	0.000543 U	0.000671 U	0.000895 U	0.00811 U	0.00179 U
	MW-334-54.5	04/16/20	PES	PACE	54.5	-23.1	S	–	–	–	–	0.00117 U	0.00114 U	0.000860 U	0.000739 U	0.000933 U	0.000608 U	0.000750 U	0.00100 U	0.00907 U	0.00200 U
	MW-334-60	04/16/20	PES	PACE	60	-28.6	S	–	–	–	–	0.00108 U	0.00105 U	0.000791 U	0.000680 U	0.000859 U	0.000559 U	0.000690 U	0.000921 U	0.00835 U	0.00184 U
	MW-334-63	04/16/20	PES	PACE	63	-31.6	S	–	–	–	–	0.00113 U	0.00110 U	0.000831 U	0.000714 U	0.000902 U	0.000587 U	0.000725 U	0.000968 U	0.00877 U	0.00194 U
MW-336	MW-336-7	04/22/20	PES	PACE	7	26.7	V	–	–	–	–	0.00106 U	0.00103 U	0.000775 U	0.000666 U	0.000841 U	0.000548 U	0.000676 U	0.000903 U	0.00818 UJ	0.00181 U
	MW-336-11.5	04/22/20	PES	PACE	11.5	22.2	V	–	–	–	–	0.00113 U	0.00110 U	0.000828 U	0.000711 U	0.000898 U	0.000585 U	0.000722 U	0.000963 U	0.00873 UJ	0.00193 U
	MW-2019-11.5	04/22/20	PES	PACE	11.5 (dup)	22.2	V	–	–	–	–	0.00116 U	0.00113 U	**0.000946 J**	0.000728 U	0.000919 U	0.000599 U	0.000739 U	0.000987 U	0.00894 U	0.00198 U
	MW-336-14.5	04/22/20	PES	PACE	14.5	19.2	V	–	–	–	–	0.00122 U	0.00118 U	0.000891 U	0.000765 U	0.000966 U	0.000629 U	0.000777 U	0.00104 U	0.00940 UJ	0.00208 U
	MW-336-20	04/22/20	PES	PACE	20	13.7	S	–	–	–	–	0.00116 U	0.00113 U	0.000851 U	0.000731 U	0.000923 U	0.000601 U	0.000742 U	0.000991 U	0.00898 UJ	0.00198 U
	MW-336-25	04/22/20	PES	PACE	25	8.7	S	–	–	–	–	0.00156 U	0.00152 U	0.00114 U	0.000983 U	0.00124 U	0.000808 U	0.000997 U	0.00133 U	0.0121 UJ	0.00267 U
	MW-336-30	04/22/20	PES	PACE	30	3.7	S	–	–	–	–	0.00144 U	0.00141 U	0.00106 U	0.000909 U	0.00115 U	0.000748 U	0.000923 U	0.00123 U	0.0112 UJ	0.00247 U
	MW-336-35	04/22/20	PES	PACE	35	-1.3	S	–	–	–	–	0.00116 U	0.00113 U	0.000853 U	0.000733 U	0.000925 U	0.000602 U	0.000744 U	0.000993 U	0.00899 UJ	0.00199 U
	MW-336-40	04/22/20	PES	PACE	40	-6.3	S	–	–	–	–	0.00114 U	0.00111 U	0.000838 U	0.000720 U	0.000909 U	0.000592 U	0.000731 U	0.000975 U	0.00884 U	0.00195 U
	MW-336-45	04/22/20	PES	PACE	45	-11.3	S	–	–	–	–	0.00126 U	0.00123 U	0.000923 U	0.000793 U	0.00100 U	0.000652 U	0.000805 U	0.00107 U	0.00973 U	0.00215 U
	MW-336-51	04/22/20	PES	PACE	51	-17.3	S	–	–	–	–	0.00109 U	0.00106 U	0.000800 U	0.000687 U	0.000868 U	0.000565 U	0.000698 U	0.000931 U	0.00844 U	0.00187 U
	MW-336-55	04/22/20	PES	PACE	55	-21.3	S	–	–	–	–	0.00108 U	0.00105 U	0.000794 U	0.000682 U	0.000861 U	0.000561 U	0.000692 U	0.000924 U	0.00837 U	0.00185 U
	MW-336-60	04/22/20	PES	PACE	60	-26.3	S	–	–	–	–	0.00111 U	0.00108 U	0.000816 U	0.000701 U	0.000885 U	0.000576 U	0.000711 U	0.000949 U	0.00860 U	0.00190 U
	MW-336-65	04/22/20	PES	PACE	65	-31.3	S	–	–	–	–	0.00111 U	0.00108 U	0.000811 U	0.000696 U	0.000880 U	0.000573 U	0.000707 U	0.000944 U	0.00855 U	0.00189 U
	MW-336-69	04/22/20	PES	PACE	69	-35.3	S	–	–	–	–	0.00118 U	0.00115 U	0.000864 U	0.000742 U	0.000937 U	0.000610 U	0.000753 U	0.00101 U	0.00911 U	0.00201 U
	MW-336-74.5	04/22/20	PES	PACE	74.5	-40.8	S	–	–	–	–	0.00110 U	0.00107 U	0.000809 U	0.000695 U	0.000878 U	0.000572 U	0.000705 U	0.000942 U	0.00853 U	0.00189 U
	MW-336-79	04/22/20	PES	PACE	79	-45.3	S	–	–	–	–	0.00114 U	0.00111 U	0.000834 U	0.000716 U	0.000905 U	0.000589 U	0.000727 U	0.000971 U	0.00879 U	0.00194 U
	MW-336-85	04/22/20	PES	PACE	85	-51.3	S	–	–	–	–	0.00114 U	0.00111 U	0.000835 U	0.000717 U	0.000906 U	0.000590 U	0.000728 U	0.000972 U	0.00881 U	0.00195 U
	MW-2021-85	05/04/20	PES	PACE	85 (dup)	-51.3	S	–	–	–	–	0.00109 U	0.00106 U	0.000800 U	0.000687 U	0.000868 U	0.000565 U	0.000698 U	0.000931 U	0.00844 U	0.00187 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
MW-336 (continued)	MW-336-90	04/22/20	PES	PACE	90	-56.3	S	–	–	–	–	0.00114 U	0.00111 U	0.000838 U	0.000720 U	0.000909 U	0.000592 U	0.000731 U	0.000975 U	0.00884 U	0.00195 U
	MW-336-95	04/22/20	PES	PACE	95	-61.3	S	–	–	–	–	0.00114 U	0.00111 U	0.000835 U	0.000717 U	0.000906 U	0.000590 U	0.000728 U	0.000972 U	0.00881 U	0.00195 U
	MW-2020-95	04/22/20	PES	PACE	95 (dup)	-61.3	S	–	–	–	–	0.00113 U	0.00110 U	0.000828 U	0.000711 U	0.000898 U	0.000585 U	0.000722 U	0.000963 U	0.00873 U	0.00193 U
MW-338	MW-338-10	05/01/20	PES	PACE	10	17.8	S	–	–	–	–	0.00115 U	0.00112 U	0.000843 U	0.000724 U	0.000914 U	0.000595 U	0.000735 U	0.000981 U	0.00889 U	0.00196 U
	MW-338-15	05/01/20	PES	PACE	15	12.8	S	–	–	–	–	0.00125 U	0.00122 U	0.000919 U	0.000789 U	0.000997 U	0.000649 U	0.000801 U	0.00107 U	0.00969 U	0.00214 U
	MW-338-20	05/01/20	PES	PACE	20	7.8	S	–	–	–	–	0.00110 U	0.00107 U	0.000806 U	0.000692 U	0.000874 U	0.000569 U	0.000702 U	0.000938 U	0.00850 U	0.00188 U
	MW-338-23	05/01/20	PES	PACE	23	4.8	S	–	–	–	–	0.00120 U	0.00117 U	0.000883 U	0.000759 U	0.000958 U	0.000624 U	0.000770 U	0.00103 U	0.00931 U	0.00206 U
	MW-338-28	05/01/20	PES	PACE	28	-0.2	S	–	–	–	–	0.00119 U	0.00116 U	0.000874 U	0.000751 U	0.000948 U	0.000617 U	0.000762 U	0.00102 U	0.00922 U	0.00204 U
	MW-338-34	05/01/20	PES	PACE	34	-6.2	S	–	–	–	–	0.00106 U	0.00103 U	0.000777 U	0.000667 U	0.000843 U	0.000549 U	0.000677 U	0.000904 U	0.00819 U	0.00181 U
	MW-338-39	05/01/20	PES	PACE	39	-11.2	S	–	–	–	–	0.00115 U	0.00112 U	0.000842 U	0.000723 U	0.000913 U	0.000595 U	0.000734 U	0.000980 U	0.00888 U	0.00196 U
	MW-338-41	05/01/20	PES	PACE	41	-13.2	S	–	–	–	–	0.00117 U	0.00114 U	0.000857 U	0.000736 U	0.000930 U	0.000605 U	0.000747 U	0.000997 U	0.00904 U	0.00200 U
	MW-338-45	05/01/20	PES	PACE	45	-17.2	S	–	–	–	–	0.00116 U	0.00113 U	0.000848 U	0.000729 U	0.000920 U	0.000599 U	0.000740 U	0.000988 U	0.00895 U	0.00198 U
	MW-338-51	05/01/20	PES	PACE	51	-23.2	S	–	–	–	–	0.00117 U	0.00114 U	0.000861 U	0.000740 U	0.000934 U	0.000609 U	0.000751 U	0.00100 U	0.00908 U	0.00201 U
	MW-338-55	05/01/20	PES	PACE	55	-27.2	S	–	–	–	–	0.00109 U	0.00106 U	0.000798 U	0.000685 U	0.000866 U	0.000564 U	0.000696 U	0.000929 U	0.00841 U	0.00186 U
MW-341	MW-341-85	05/04/20	PES	PACE	85	-56.6	S	–	–	–	–	0.00108 U	0.00105 U	0.000790 U	0.000678 U	0.000857 U	0.000558 U	0.000688 U	0.000919 U	0.00833 U	0.00184 U
	MW-341-90	05/04/20	PES	PACE	90	-61.6	S	–	–	–	–	0.00107 U	0.00104 U	0.000782 U	0.000672 U	0.000848 U	0.000552 U	0.000682 U	0.000910 U	0.00825 U	0.00182 U
	MW-341-95	05/04/20	PES	PACE	95	-66.6	S	–	–	–	–	0.00110 U	0.00108 U	0.000810 U	0.000696 U	0.000879 U	0.000572 U	0.000706 U	0.000943 U	0.00854 U	0.00189 U
	MW-341-99	05/04/20	PES	PACE	99	-70.6	S	–	–	–	–	0.00111 U	0.00108 U	0.000815 U	0.000700 U	0.000884 U	0.000576 U	0.000710 U	0.000948 U	0.00859 U	0.00190 U
	MW-341-104	05/04/20	PES	PACE	104	-75.6	S	–	–	–	–	0.00113 U	0.00110 U	0.000829 U	0.000712 U	0.000899 U	0.000586 U	0.000723 U	0.000965 U	0.00874 U	0.00193 U
MW-343	MW-343-5	04/13/20	PES	PACE	5	22.6	V	–	–	–	–	0.00107 U	0.00104 U	0.000785 U	0.000674 U	0.000852 U	0.000555 U	0.000685 U	0.000914 U	0.00828 U	0.00183 U
	MW-343-10	04/13/20	PES	PACE	10	17.6	S	–	–	–	–	0.00112 U	0.00109 U	0.000823 U	0.000707 U	0.000893 U	0.000581 U	0.000717 U	0.000958 U	0.00868 U	0.00192 U
	MW-343-12.5	04/13/20	PES	PACE	12.5	15.1	S	–	–	–	–	0.00116 U	0.00113 U	0.000853 U	0.000732 U	0.000925 U	0.000602 U	0.000744 U	0.000993 U	0.00899 U	0.00199 U
	MW-343-17	04/13/20	PES	PACE	17	10.6	S	–	–	–	–	0.00109 U	0.00106 U	0.000800 U	0.000687 U	0.000867 U	0.000565 U	0.000697 U	0.000931 U	0.00843 U	0.00186 U
	MW-343-24	04/13/20	PES	PACE	24	3.6	S	–	–	–	–	0.00109 U	0.00106 U	0.000801 U	0.000688 U	0.000869 U	0.000566 U	0.000699 U	0.000933 U	0.00845 U	0.00187 U
	MW-343-28.5	04/13/20	PES	PACE	28.5	-0.9	S	–	–	–	–	0.00117 U	0.00114 U	0.000860 U	0.000739 U	0.000933 U	0.000607 U	0.000750 U	0.00100 U	0.00907 U	0.00200 U
	MW-343-35	04/13/20	PES	PACE	35	-7.4	S	–	–	–	–	0.00119 U	0.00115 U	0.000870 U	0.000747 U	0.000943 U	0.000614 U	0.000758 U	0.00101 U	0.00917 U	0.00203 U
	MW-343-38	04/13/20	PES	PACE	38	-10.4	S	–	–	–	–	0.00111 U	0.00108 U	0.000813 U	0.000698 U	0.000882 U	0.000574 U	0.000709 U	0.000946 U	0.00857 U	0.00190 U
	MW-343-44	04/13/20	PES	PACE	44	-16.4	S	–	–	–	–	0.00104 U	0.00102 U	0.000766 U	0.000658 U	0.000831 U	0.000541 U	0.000668 U	0.000892 U	0.00808 U	0.00179 U
	MW-343-47	04/13/20	PES	PACE	47	-19.4	S	–	–	–	–	0.00118 U	0.00115 U	0.000865 U	0.000743 U	0.000939 U	0.000611 U	0.000754 U	0.00101 U	0.00912 U	0.00202 U
	MW-343-51	04/13/20	PES	PACE	51	-23.4	S	–	–	–	–	0.00105 U	0.00103 U	0.000773 U	0.000664 U	0.000839 U	0.000546 U	0.000674 U	0.000900 U	0.00816 U	0.00180 U
	MW-343-55	04/13/20	PES	PACE	55	-27.4	S	–	–	–	–	0.00108 U	0.00105 U	0.000790 U	0.000679 U	0.000857 U	0.000558 U	0.000689 U	0.000920 U	0.00834 U	0.00184 U
	MW-343-62	04/13/20	PES	PACE	62	-34.4	S	–	–	–	–	0.00110 U	0.00107 U	0.000804 U	0.000691 U	0.000873 U	0.000568 U	0.000701 U	0.000936 U	0.00848 U	0.00187 U
	MW-343-68	04/13/20	PES	PACE	68	-40.4	S	–	–	–	–	0.00108 U	0.00105 U	0.000792 U	0.000681 U	0.000860 U	0.000560 U	0.000691 U	0.000922 U	0.00836 U	0.00185 U
	MW-343-73	04/13/20	PES	PACE	73	-45.4	S	–	–	–	–	0.00109 U	0.00106 U	0.000801 U	0.000688 U	0.000869 U	0.000566 U	0.000698 U	0.000932 U	0.00844 U	0.00187 U
	MW-343-79	04/13/20	PES	PACE	79	-51.4	S	–	–	–	–	0.00103 U	0.00100 U	0.000753 U	0.000647 U	0.000817 U	0.000532 U	0.000656 U	0.000876 U	0.00794 U	0.00175 U
	MW-343-82	04/13/20	PES	PACE	82	-54.4	S	–	–	–	–	0.00103 U	0.00100 U	0.000755 U	0.000648 U	0.000819 U	0.000533 U	0.000658 U	0.000878 U	0.00796 U	0.00176 U
	MW-343-86	04/13/20	PES	PACE	86	-58.4	S	–	–	–	–	0.00100 U	0.000978 U	0.000736 U	0.000632 U	0.000799 U	0.000520 U	0.000642 U	0.000857 U	0.00776 U	0.00172 U
	MW-343-93	04/13/20	PES	PACE	93	-65.4	S	–	–	–	–	0.00106 U	0.00103 U	0.000778 U	0.000669 U	0.000845 U	0.000550 U	0.000679 U	0.000906 U	0.00821 U	0.00181 U
	MW-343-99	04/13/20	PES	PACE	99	-71.4	S	–	–	–	–	0.00102 U	0.000991 U	0.000746 U	0.000641 U	0.000809 U	0.000527 U	0.000651 U	0.000868 U	0.00787 U	0.00174 U
	MW-343-102	04/14/20	PES	PACE	102	-74.4	S	–	–	–	–	0.00105 U	0.00102 U	0.000767 U	0.000659 U	0.000832 U	0.000542 U	0.000669 U	0.000892 U	0.00809 UJ	0.00179 U
	MW-2017-102	04/14/20	PES	PACE	102 (dup)	-74.4	S	–	–	–	–	0.00104 U	0.00101 U	0.000759 U	0.000652 U	0.000823 U	0.000536 U	0.000662 U	0.000883 U	0.00800 UJ	0.00177 U
	MW-343-106	04/14/20	PES	PACE	106	-78.4	S	–	–	–	–	0.00102 U	0.000990 U	0.000745 U	0.000640 U	0.000808 U	0.000526 U	0.000650 U	0.000867 U	0.00786 UJ	0.00174 U
	MW-343-108	04/14/20	PES	PACE	108	-80.4	S	–	–	–	–	0.00105 U	0.00102 U	0.000770 U	0.000662 U	0.000836 U	0.000544 U	0.000672 U	0.000897 U	0.00813 UJ	0.00180 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	**–**	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	**–**	**0.030**	**1.5E-07**
PH22	PH22	04/17/18	PES	Fremont	0-3	–	V	–	–	–	–	0.0304 UJ	0.0304 U	0.0243 U	0.0243 UJ	–	0.0243 U	0.0243 U	0.0243 U	0.0243 U	0.0304 U
PH34	PH34	04/17/18	PES	Fremont	1.5-6.5	–	V	–	–	–	–	0.0240 UJ	0.0240 U	0.0192 U	0.0192 UJ	–	0.0192 U	0.0192 U	0.0192 U	0.0192 U	0.0240 U
PH38	PH38	04/17/18	PES	Fremont	1.5-4	–	V	–	–	–	–	0.0292 UJ	0.0292 U	0.0233 U	0.0233 UJ	–	0.0233 U	0.0233 U	0.0233 U	0.0233 U	0.0292 U
PH52	PH52	04/17/18	PES	Fremont	1-5	–	V	–	–	–	–	0.0282 UJ	0.0282 U	0.0226 U	0.0226 UJ	–	0.0226 U	0.0226 U	0.0226 U	0.0226 U	0.0282 U
PW-1	Composite	01/01/98	B&V	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
PW-4	Composite	05/13/98	B&V	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
R-MW4	Unknown	10/22/92	Roux	Unknown	5	35.9	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	Unknown	10/22/92	Roux	Unknown	15	25.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	Unknown	10/22/92	Roux	Unknown	30	10.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
R-MW6	Unknown	10/27/92	Roux	Unknown	6	39.3	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(33.3 to 23.3)	Unknown	10/27/92	Roux	Unknown	11	34.3	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	Unknown	10/27/92	Roux	Unknown	16	29.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
RB1	RB1-17.5	10/18/93	Retec	AAL	17.5	18.4	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
RB2	RB2-12.5	10/18/93	Retec	AAL	12.5	23.6	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RB2-17.5	10/18/93	Retec	AAL	17.5	18.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
RB3	RB3-17.5	10/18/93	Retec	AAL	17.5	20.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
SCL-B100	B-100, S1	06/10/02	Urban	F&BI	5-6.5	–	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B-100, S2	06/10/02	Urban	F&BI	10-11.5	–	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
SCL-B101	B-101- S1&2	06/17/02	Urban	F&BI	0-6	–	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-S3	06/17/02	Urban	F&BI	8	–	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
SCL-B102	B102-S1	06/17/02	Urban	F&BI	0-3	–	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-S2	06/17/02	Urban	F&BI	4	–	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
SCL-MW101	MW101-S3	06/14/02	Urban	F&BI	16	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(25.0 to 15.0)																					
SCL-MW102	MW-102, S1	06/10/02	Urban	F&BI	5-6.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW-102, S2	06/10/02	Urban	F&BI	5-6.5, 10-11.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
SCL-MW103	MW103-S1&S2	06/14/02	Urban	F&BI	5-6.5, 10-11.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
SCL-MW105	MW-105, S2	06/10/02	Urban	F&BI	10-11.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(10.8 to 0.8)	MW-105, S4	06/10/02	Urban	F&BI	20-21.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
SCLB-1	RS1-2.5/RS-1 7.5 (Comp)	03/12/93	EPJ	OnSite	2.5-7.5	–	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS1-12.5/RS1-17.5 (Comp)	03/12/93	EPJ	OnSite	12.5-17.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS-1 17.5	03/12/93	EPJ	OnSite	17.5	21.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS1-22.5/RS-27.5 (Comp)	03/12/93	EPJ	OnSite	22.5-27.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS1-32.5	03/12/93	EPJ	OnSite	32.5	6.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS1-37.5	03/12/93	EPJ	OnSite	37.5	1.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
SCLB-2	RS2-2.5/RS-2 7.5 (Comp)	03/12/93	EPJ	OnSite	2.5-7.5	–	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS2-12.5/RS2-17.5 (Comp)	03/12/93	EPJ	OnSite	12.5-17.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS2-17.5	03/12/93	EPJ	OnSite	17.5	21.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS2-22.5/RS2-27.5 (Comp)	03/12/93	EPJ	OnSite	22.5-27.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS2-32.5	03/12/93	EPJ	OnSite	32.5	6.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS2-37.5	03/12/93	EPJ	OnSite	37.5	1.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	**–**	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	**–**	**0.030**	**1.5E-07**
SSD-MW-1	MW-1 S-2	05/24/89	HC	Unknown	5-6.5	34.0	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW-1 S-6	05/24/89	HC	Unknown	15-16.5	24.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
SSD-MW-2	MW-2 S-3	05/24/89	HC	Unknown	7.5-9	31.0	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW-2 S-6	05/24/89	HC	Unknown	15-16.5	31.0	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
SSD-MW-3	MW-3 S-2	05/24/89	HC	Unknown	5-6.5	34.0	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW-3 S-5	05/24/89	HC	Unknown	12.5-14	34.0	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
SSD-MW-4	MW-4 S-6	05/25/89	HC	Unknown	14.5-16	36.8	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW-4 S-9	05/25/89	HC	Unknown	22-23	29.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
SV-04	SV-04-6	06/29/20	PES	PACE	6	–	V	–	–	–	–	0.00123 U	0.00120 U	0.000901 U	0.000774 U	0.000977 U	0.000636 U	0.000785 U	0.00105 U	0.00950 U	0.00210 U
SV-05	SV-05-10	06/29/20	PES	PACE	10	–	V	–	–	–	–	0.00131 U	0.00128 U	0.000962 U	0.000827 U	0.00104 U	0.000680 U	0.000839 U	0.00112 U	0.0101 UJ	0.00224 U
SV-06	SV-06-6	06/29/20	PES	PACE	6	–	V	–	–	–	–	0.00121 U	0.00118 U	0.000887 U	0.000762 U	0.000962 U	0.000626 U	0.000773 U	0.00103 U	0.00935 UJ	0.00207 U
SV-07	SV-07-15	06/29/20	PES	PACE	15	–	V	–	–	–	–	0.00104 U	0.00101 U	0.000762 U	0.000654 U	0.000826 U	0.000538 U	0.000664 U	0.000887 U	0.00803 UJ	0.00178 U
SV-08	SV-08-6	06/30/20	PES	PACE	6	–	V	–	–	–	–	0.00132 U	0.00128 U	0.000966 U	0.000830 U	0.00105 U	0.000683 U	0.000843 U	0.00112 U	0.0102 UJ	0.00225 U
	SV-08-7.5	06/30/20	PES	PACE	7.5	–	V	–	–	–	–	0.00134 U	0.00131 U	0.000985 U	0.000846 U	0.00107 U	0.000696 U	0.000859 U	0.00115 U	0.0104 U	0.00230 U
SV-09	SV-09-5.5	07/01/20	PES	PACE	5.5	–	V	–	–	–	–	0.00125 U	0.00122 U	0.000920 U	0.000790 U	0.000998 U	0.000650 U	0.000802 U	0.00107 U	0.00970 U	0.00214 U
SV-10	SV-10-5.5	06/30/20	PES	PACE	5.5	–	V	–	–	–	–	0.00125 U	0.00122 U	0.000916 U	0.000787 U	0.000994 U	0.000647 U	0.000799 U	0.00107 U	0.00966 U	0.00214 U
SV-11	SV-11-10	06/30/20	PES	PACE	10	–	V	–	–	–	–	0.00127 U	0.00123 U	0.000929 U	0.000798 U	0.00101 U	0.000656 U	0.000810 U	0.00108 U	0.00980 U	0.00217 U
SV-12	SV-12-5.5	07/01/20	PES	PACE	5.5	–	V	–	–	–	–	0.00104 U	0.00101 U	0.000760 U	0.000653 U	0.000824 U	0.000537 U	0.000663 U	0.000884 U	0.00801 U	0.00177 U
SV-13	SV-13-10.5	07/01/20	PES	PACE	10.5	–	V	–	–	–	–	0.00122 U	0.00118 U	0.000891 U	0.000766 U	0.000967 U	0.000630 U	0.000777 U	0.00104 U	0.00940 U	0.00208 U
SV-14	SV-14-5.5	07/01/20	PES	PACE	5.5	–	V	–	–	–	–	0.00127 U	0.00123 U	0.000929 U	0.000798 U	0.00101 U	0.000656 U	0.000810 U	0.00108 U	0.00980 U	0.00217 U
SV-15	SV-15-13	07/01/20	PES	PACE	13	–	V	–	–	–	–	0.00123 U	0.00120 U	0.000902 U	0.000775 U	0.000979 U	0.000637 U	0.000786 U	0.00105 U	0.00951 U	0.00210 U
SV-16	SV-16-5	07/02/20	PES	PACE	5	–	V	–	–	–	–	0.00251 U	0.00244 U	0.00184 U	0.00159 U	0.00200 U	0.00130 U	0.00161 U	0.00215 U	0.0195 UJ	0.00431 U
	SV-100-5	07/02/20	PES	PACE	5 (dup)	–	V	–	–	–	–	0.00224 U	0.00219 U	0.00165 U	0.00142 U	0.00179 U	0.00117 U	0.00144 U	0.00192 U	0.0174 UJ	0.00385 U
SV-17	SV-17-4.5	07/02/20	PES	PACE	4.5	–	V	–	–	–	–	0.00186 U	0.00182 U	0.00137 U	0.00117 U	0.00148 U	0.000966 U	0.00119 U	0.00159 U	0.0144 U	0.00319 U
SV-18	SV-18-5.5	07/02/20	PES	PACE	5.5	–	V	–	–	–	–	0.00102 U	0.000995 U	0.000749 U	0.000643 U	0.000813 U	0.000529 U	0.000653 U	0.000872 U	0.00790 U	0.00175 U
SV-19	SV-19-5	07/09/20	PES	PACE	5	–	V	–	–	–	–	0.00102 U	0.000994 U	0.000748 U	0.000643 U	0.000812 U	0.000529 U	0.000653 U	0.000871 U	0.00789 U	0.00174 U
SV-20	SV-20-9	07/09/20	PES	PACE	9	–	V	–	–	–	–	0.00134 U	0.00131 U	0.000984 U	0.000845 U	0.00107 U	0.000695 U	0.000858 U	0.00115 U	0.0104 U	0.00229 U
SV-21	SV-21-6	07/09/20	PES	PACE	6	–	V	–	–	–	–	0.00104 U	0.00101 U	0.000762 U	0.000654 U	0.000826 U	0.000538 U	0.000664 U	0.000887 U	0.00803 U	0.00178 U
SV-22	SV-22-8.5	07/09/20	PES	PACE	8.5	–	V	–	–	–	–	0.00193 U	0.00188 U	0.00142 U	0.00122 U	0.00154 U	0.00100 U	0.00124 U	0.00165 U	0.0150 U	0.00331 U
SV-23	SV-23-4.5	07/09/20	PES	PACE	4.5	–	V	–	–	–	–	0.00143 U	0.00140 U	0.00105 U	0.000903 U	0.00114 U	0.000742 U	0.000916 U	0.00122 U	0.0111 U	0.00245 U
SV-24	SV-24-8	07/09/20	PES	PACE	8	–	V	–	–	–	–	0.00103 U	0.00100 U	0.000754 U	0.000648 U	0.000819 U	0.000533 U	0.000658 U	0.000878 U	0.00796 U	0.00176 U
SV-25	SV-25-4	07/10/20	PES	PACE	4	–	V	–	–	–	–	0.00125 U	0.00122 U	0.000915 U	0.000786 U	0.000993 U	0.000647 U	0.000798 U	0.00107 U	0.00965 U	0.00213 U
SV-26	SV-26-12	07/10/20	PES	PACE	12	–	V	–	–	–	–	0.00139 U	0.00135 U	0.00102 U	0.000874 U	0.00110 U	0.000719 U	0.000887 U	0.00118 U	0.0107 U	0.00237 U
SV-27	SV-27-5.5	07/10/20	PES	PACE	5.5	–	V	–	–	–	–	0.00124 U	0.00121 U	0.000912 U	0.000783 U	0.000989 U	0.000644 U	0.000795 U	0.00106 U	0.00962 U	0.00213 U
	SV-27-13.5	07/10/20	PES	PACE	13.5	–	V	–	–	–	–	0.00125 U	0.00121 U	0.000913 U	0.000784 U	0.000991 U	0.000645 U	0.000796 U	0.00106 U	0.00963 U	0.00213 U
TB-12	16	08/01/97	B&V	Unknown	62-63	-24.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
TB-18	S-2	03/17/98	B&V	Unknown	5-6.5	38.3	V	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	S-8	03/17/98	B&V	Unknown	20-21.5	23.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	S-21	03/17/98	B&V	Unknown	57.5-59	1.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
T1	T1-2.5-071718	07/17/18	PES	Fremont	2.5	–	V	5.31 U	19.6 U	49.0 U	49.0 U	0.0265 U	0.0265 U	0.0212 U	0.0212 U	–	0.0212 U	0.0212 U	0.0212 U	0.0212 U	0.0265 U
T-2	T-2-071618	07/16/18	PES	Fremont	2	–	V	2.87 U	24.1 U	60.2 U	60.2 U	0.0143 U	0.0143 U	0.0115 U	0.0115 U	–	0.0115 U	0.0115 U	0.0115 U	0.0115 U	0.0143 U
T-2B	T-2B-071618	07/16/18	PES	Fremont	2	–	V	5.93 U	**360**	**1,500**	**1,860**	0.0297 U	0.0297 U	0.0237 U	0.0237 U	–	0.0237 U	0.0237 U	0.0237 U	0.0237 U	0.0297 U
T2	T2-6-071718	07/17/18	PES	Fremont	6	–	V	6.14 U	**906**	56.0 U	**906**	0.0307 U	0.0307 U	0.0245 U	0.0245 U	–	0.0245 U	0.0245 U	0.0245 U	0.0245 U	0.0307 U
T3	T3-3-071718	07/17/18	PES	Fremont	3	–	V	5.73 U	19.8 U	49.5 U	49.5 U	0.0287 U	0.0287 U	0.0229 U	0.0229 U	–	0.0229 U	0.0229 U	0.0229 U	0.0229 U	0.0287 U
T4	T4-6-071718	07/17/18	PES	Fremont	6	–	V	5.16 U	21.0 U	52.4 U	52.4 U	0.0258 U	0.0258 U	0.0206 U	0.0206 U	–	0.0206 U	0.0206 U	0.0206 U	0.0206 U	0.0258 U
T-5	T-5-071618	07/16/18	PES	Fremont	5	–	V	5.09 U	19.6 U	49.0 U	49.0 U	0.0255 U	0.0255 U	0.0204 U	0.0204 U	–	0.0204 U	0.0204 U	0.0204 U	0.0204 U	0.0255 U
T6	T6-4-071818	07/18/18	PES	Fremont	4	–	V	4.74 U	21.2 U	53.0 U	53.0 U	0.0237 U	0.0237 U	0.0189 U	0.0189 U	–	0.0189 U	0.0189 U	0.0189 U	0.0189 U	0.0237 U
T7	T7-7-071818	07/18/18	PES	Fremont	7	–	V	6.84 U	25.1 U	62.8 U	62.8 U	0.0342 U	0.0342 U	0.0274 U	0.0274 U	–	0.0274 U	0.0274 U	0.0274 U	0.0274 U	0.0342 U
T8	T8-3-072018	07/20/18	PES	Fremont	3	–	V	5.36 U	18.6 U	**51.0**	**51.0**	0.0268 U	0.0268 U	0.0214 U	0.0214 U	–	0.0214 U	0.0214 U	0.0214 U	0.0214 U	0.0268 U
T8	T8-6-072018	07/20/18	PES	Fremont	6	–	V	7.71 U	24.8 U	**774**	**774**	0.0377 U	0.0377 U	0.0301 U	0.0301 U	–	0.0301 U	0.0301 U	0.0301 U	0.0301 U	0.0377 U
T9	T9-3-072018	07/20/18	PES	Fremont	3	–	V	**8.79**	23.5 U	58.8 U	58.8 U	0.0437 U	0.0437 U	0.0350 U	0.0350 U	–	0.0350 U	0.0350 U	0.0350 U	0.0350 U	0.0437 U
T9	T9-3.5-072018	07/20/18	PES	Fremont	3.5	–	V	5.83 U	19.0 U	**270**	**270**	0.0291 U	0.0291 U	0.0233 U	0.0233 U	–	0.0233 U	0.0233 U	0.0233 U	0.0233 U	0.0291 U
T9	T9-6-072018	07/20/18	PES	Fremont	6	–	V	6.05 U	20.5 U	51.2 U	51.2 U	0.0303 U	0.0303 U	0.0242 U	0.0242 U	–	0.0242 U	0.0242 U	0.0242 U	0.0242 U	0.0303 U
T10	T10-3-072018	07/20/18	PES	Fremont	3	–	V	10.3 U	23.2 U	**256**	**256**	0.0513 U	0.0513 U	0.0411 U	0.0411 U	–	0.0411 U	0.0411 U	0.0411 U	0.0411 U	0.0513 U
T10	T10-6-072018	07/20/18	PES	Fremont	6	–	V	5.56 U	19.6 U	48.9 U	48.9 U	0.0278 U	0.0278 U	0.0222 U	0.0222 U	–	0.0222 U	0.0222 U	0.0222 U	0.0222 U	0.0278 U
T11	T11-3.5-073118	07/31/18	PES	Fremont	3.5	–	V	7.16 U	46.8 U	–	–	0.0358 U	0.0358 U	0.0286 U	0.0286 U	–	0.0286 U	0.0286 U	0.0286 U	0.0286 U	0.0358 U
T12	T12-3-091818	09/18/18	PES	Fremont	3	–	V	6.14 U	24.6 U	61.4 U	61.4 U	0.0307 U	0.0307 U	0.0245 U	0.0245 U	–	0.0245 U	0.0245 U	0.0245 U	0.0245 U	0.0307 U
T12	T12-7-091818	09/18/18	PES	Fremont	7	–	V	6.07 U	21.1 U	52.7 U	52.7 U	0.0303 U	0.0303 U	0.0243 U	0.0243 U	–	0.0243 U	0.0243 U	0.0243 U	0.0243 U	0.0303 U
T12	T12-7.5-073118	07/31/18	PES	Fremont	7.5	–	V	5.19 U	53.2 U	–	–	0.0259 U	0.0259 U	0.0207 U	0.0207 U	–	0.0207 U	0.0207 U	0.0207 U	0.0207 U	0.0259 U
T13	T13-3.5-091818	09/18/18	PES	Fremont	3.5	–	V	5.67 U	20.1 U	50.2 U	50.2 U	0.0283 U	0.0283 U	0.0227 U	0.0227 U	–	0.0227 U	0.0227 U	0.0227 U	0.0227 U	0.0283 U
T13	T13-6.5-091818	09/18/18	PES	Fremont	6.5	–	V	5.00 U	20.7 U	51.6 U	51.6 U	0.0250 U	0.0250 U	0.0200 U	0.0200 U	–	0.0200 U	0.0200 U	0.0200 U	0.0200 U	0.0250 U
T14	T14-3.5-091818	09/18/18	PES	Fremont	3.5	–	V	5.99 U	21.1 U	52.6 U	52.6 U	0.0300 U	0.0300 U	0.0240 U	0.0240 U	–	0.0240 U	0.0240 U	0.0240 U	0.0240 U	0.0300 U
T14	T14-7-091818	09/18/18	PES	Fremont	7	–	V	6.35 U	19.6 U	48.9 U	48.9 U	0.0318 U	0.0318 U	0.0254 U	0.0254 U	–	0.0254 U	0.0254 U	0.0254 U	0.0254 U	0.0318 U
TP-15	TP-15-3-092818	09/28/18	PES	Fremont	3	–	V	6.09 U	21.8 U	54.6 U	54.6 U	0.0304 U	0.0304 U	0.0244 U	0.0244 U	–	0.0244 U	0.0244 U	0.0244 U	0.0244 U	0.0304 U
TP-15	TP-15-6.5-092818	09/28/18	PES	Fremont	6.5	–	V	6.25 U	21.7 U	**73.2**	**73.2**	0.0313 U	0.0313 U	0.0250 U	0.0250 U	–	0.0250 U	0.0250 U	0.0250 U	0.0250 U	0.0313 U
TP-16	TP-16-3-092818	09/28/18	PES	Fremont	3	–	V	8.52 U	23.9 U	**170**	**170**	0.0426 U	0.0426 U	0.0341 U	0.0341 U	–	0.0341 U	0.0341 U	0.0341 U	0.0341 U	0.0426 U
TP-16	TP-16-6-092818	09/28/18	PES	Fremont	6	–	V	8.92 U	22.6 U	**114**	**114**	0.0446 U	0.0446 U	0.0357 U	0.0357 U	–	0.0357 U	0.0357 U	0.0357 U	0.0357 U	0.0446 U
TP-16	TP-16-9-092818	09/28/18	PES	Fremont	9	–	V	5.25 U	22.2 U	55.6 U	55.6 U	0.0263 U	0.0263 U	0.0210 U	0.0210 U	–	0.0210 U	0.0210 U	0.0210 U	0.0210 U	0.0263 U
TP-SD-01	TP-SD-01-2	06/03/19	PES	Fremont	2	–	V	4.29 U	19.2 U	47.9 U	47.9 U	0.0214 U	0.0214 U	0.0172 U	0.0172 U	–	0.0172 U	0.0172 U	0.0172 U	0.0172 U	0.0214 U
TP-SD-01	TP-SD-01-5	06/03/19	PES	Fremont	5	–	V	5.34 U	22.7 U	**59.0**	**59.0**	0.0267 U	0.0267 U	0.0213 U	0.0213 U	–	0.0213 U	0.0213 U	0.0213 U	0.0213 U	0.0267 U
TP-SD-04	TP-SD-04-2	06/03/19	PES	Fremont	2	–	V	5.04 U	21.1 U	52.6 U	52.6 U	0.0252 U	0.0252 U	0.0202 U	0.0202 U	–	0.0202 U	0.0202 U	0.0202 U	0.0202 U	0.0252 U
TP-SD-04	TP-SD-04-5	06/03/19	PES	Fremont	5	–	V	5.44 U	23.7 U	59.1 U	59.1 U	0.0272 U	0.0272 U	0.0218 U	0.0218 U	–	0.0218 U	0.0218 U	0.0218 U	0.0218 U	0.0272 U
TP-SD-05	TP-SD-05-2	06/03/19	PES	Fremont	2	–	V	5.17 U	22.0 U	55.1 U	55.1 U	0.0258 U	0.0258 U	0.0207 U	0.0207 U	–	0.0207 U	0.0207 U	0.0207 U	0.0207 U	0.0258 U
TP-SD-05	TP-SD-05-5	06/03/19	PES	Fremont	5	–	V	5.85 U	23.3 U	58.3 U	58.3 U	0.0292 U	0.0292 U	0.0234 U	0.0234 U	–	0.0234 U	0.0234 U	0.0234 U	0.0234 U	0.0292 U
TP-SD-06	TP-SD-06-2	06/03/19	PES	Fremont	2	–	V	6.88 U	18.8 U	47.0 U	47.0 U	0.0344 U	0.0344 U	0.0275 U	0.0275 U	–	0.0275 U	0.0275 U	0.0275 U	0.0275 U	0.0344 U
TP-SD-06	TP-SD-06-5	06/03/19	PES	Fremont	5	–	V	5.44 U	21.6 U	54.0 U	54.0 U	0.0272 U	0.0272 U	0.0218 U	0.0218 U	–	0.0218 U	0.0218 U	0.0218 U	0.0218 U	0.0272 U
TP-SD-07	TP-SD-07-2	06/03/19	PES	Fremont	2	–	V	4.35 U	20.8 U	52.0 U	52.0 U	0.0217 U	0.0217 U	0.0174 U	0.0174 U	–	0.0174 U	0.0174 U	0.0174 U	0.0174 U	0.0217 U
TP-SD-07	B-942-2	06/03/19	PES	Fremont	2 (dup)	–	V	4.66 U	19.8 U	49.5 U	49.5 U	0.0233 U	0.0233 U	0.0186 U	0.0186 U	–	0.0186 U	0.0186 U	0.0186 U	0.0186 U	0.0233 U
TP-SD-07	TP-SD-07-5	06/03/19	PES	Fremont	5	–	V	4.24 U	21.4 U	53.5 U	53.5 U	0.0212 U	0.0212 U	0.0169 U	0.0169 U	–	0.0169 U	0.0169 U	0.0169 U	0.0169 U	0.0212 U
TP-SD-08	TP-SD-08-2	06/03/19	PES	Fremont	2	–	V	4.83 U	21.2 U	52.9 U	52.9 U	0.0242 U	0.0242 U	0.0193 U	0.0193 U	–	0.0193 U	0.0193 U	0.0193 U	0.0193 U	0.0242 U
TP-SD-08	TP-SD-08-5	06/03/19	PES	Fremont	5	–	V	4.15 U	19.6 U	48.9 U	48.9 U	0.0207 U	0.0207 U	0.0166 U	0.0166 U	–	0.0166 U	0.0166 U	0.0166 U	0.0166 U	0.0207 U
TP-SD-08	TP-SD-08-8	06/03/19	PES	Fremont	8	–	S	4.98 U	21.6 U	54.1 U	54.1 U	0.0249 U	0.0249 U	0.0199 U	0.0199 U	–	0.0199 U	0.0199 U	0.0199 U	0.0199 U	0.0249 U
W-MW-01 (P-03)	SB-W-03-0160	01/27/12	WW	ARI	16-16.5	28.4	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(-25.1 to -35.1)	SB-W-03-0225	01/27/12	WW	ARI	22.5-23	21.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-03-0315	01/27/12	WW	ARI	31.5-32	12.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-03-0450	01/27/12	WW	ARI	45-45.5	-0.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-03-0550	01/27/12	WW	ARI	55.5-56	-11.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	**–**	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	**–**	**0.030**	**1.5E-07**
W-MW-01 (P-03)	SB-W-03-0645	01/27/12	WW	ARI	64.5-65	-20.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(continued)	SB-W-03-0730	01/27/12	WW	ARI	73-73.5	-28.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
W-MW-02 (P-06)	SB-W-06-0900	01/29/12	WW	ARI	9-9.5	34.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(-26.5 to -36.5)	SB-W-06-0185	01/29/12	WW	ARI	18.5-19	24.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-06-0305	01/30/12	WW	ARI	30.5-31	12.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-06-0380	01/30/12	WW	ARI	38-38.5	5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-06-0405	01/30/12	WW	ARI	40.5-41	2.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-06-0485	01/30/12	WW	ARI	48.5-49	-5.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-06-9485	01/30/12	WW	ARI	48.5-49 (dup)	-5.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-06-0590	01/30/12	WW	ARI	59-59.5	-16.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-06-0715	01/30/12	WW	ARI	71.5-72	-28.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-06-0790	01/31/12	WW	ARI	79-79.5	-36.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–	–
All Data						Number of Analytes Measured		135	46	44	44	644	644	644	644	598	644	644	644	644	644
						Number of Analytes Detected		40	6	11	14	0	2	1	0	0	3	24	0	2	0
						Frequency of Detection		29.6%	13.0%	25.0%	31.8%	0.0%	0.3%	0.2%	0.0%	0.0%	0.5%	3.7%	0.0%	0.3%	0.0%
						Maximum Detection		717	906	1500	1860	–	0.00172 J	0.000946 J	–	–	0.00317	0.0242 J	–	0.00136 J	–
						Minimum Detection		0.0376 U	2.34	4.03 U	5.04	0.000274 U	0.000275 U	0.000379 U	0.000288 U	0.000379 U	0.000207 U	0.000315 U	0.000329 U	0.000318 U	0.00077 U
						Number Of Vadose (V) Detections above SL		2	0	0	0	0	0	0	0	0	0	0	–	0	0
						Number of Saturated (S) Detections above SL		5	0	0	0	0	0	0	0	0	0	4	–	0	0
2017-2021						Number of Analytes Measured		135	46	44	44	644	644	644	644	598	644	644	644	644	644
						Number of Analytes Detected		40	6	11	14	0	2	1	0	0	3	24	0	2	0
						Frequency of Detection		29.6%	13.0%	25.0%	31.8%	0.0%	0.3%	0.2%	0.0%	0.0%	0.5%	3.7%	0.0%	0.3%	0.0%
						Maximum Detection		717	906	1500	1860	–	0.00172 J	0.000946 J	–	–	0.00317	0.0242 J	–	0.00136 J	–
						Minimum Detection		0.0376 U	2.34	4.03 U	5.04	0.000274 U	0.000275 U	0.000379 U	0.000288 U	0.000379 U	0.000207 U	0.000315 U	0.000329 U	0.000318 U	0.00077 U
						Number Of Vadose (V) Detections above SL		2	0	0	0	0	0	0	0	0	0	0	–	0	0
						Number of Saturated (S) Detections above SL		5	0	0	0	0	0	0	0	0	0	4	–	0	0

Abbreviations:
AAL = Alden Analytical Laboratories, Inc., of Seattle, Washington
ARI = Analytical Resource, Incorporated, Seattle, Washington
B&V = Black Veatch
bgs = below ground surface
Comp = Composite Sample
dup = duplicate
EPJ = E.PJohnson Construction Inc., and Environmental
ESC = ESC Lab Services of Mt. Juliet, Tennessee
F&BI = Friedman & Bruya, Inc.
HC = Hart Crowser, Inc.
OnSite = OnSite Environmental Inc., of Redmond, Washington
Pace = Pace Analytical of Mt. Juliet, Tennessee (formerly ESC)
PES = PES Environmental, Inc.
Retec = Remediation Technologies, Inc.
Roux = Roux Associates
Urban = Urban Redevelopment LLC
WW = WW Environmental LLC

Notes:
Petroleum Hydrocarbons (PHCs) analyzed by Ecology Methods NWTPH-HCID, NWTPH-Gx, or NWTPH-Dx; or EPA Method 418.1, Method 8020, or Method 8015M.
VOCs analyzed by EPA Methods 8010, 8020, 8021B, 624/8240, or 8260B/C/D.
Well screen elevations provided below Sample Location. in parentheses when appliable.
PCUL = Preliminary Cleanup Level from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021. PCULs based on the practical quantitation limits (PQLs) italicized.
Detected results shown in **bold**.
Detections above the screening level in the vadose zone are shown in **bold and highlighted blue**.
Detections above the screening level in the saturated zone are shown in **bold and highlighted gray.**
– = Not available or results not analyzed.
B = Analyte detected in an associated method blank.
J = The reported concentration is an estimate based on detectable results between the method detection limit and reporting limit, laboratory QA/QC, or data validation review.
J+ = The result is an estimated quantity, but the result may be biased high.
J- = The result is an estimated quantity, but the result may be biased low.
ND = Not detected above laboratory reporting limit. Reporting limit not available.
R = The data is unusable. The sample result is rejected due to serious deficiencies in meeting QC criteria. The analyte may or may not be present in the sample
T = Analyte also detected in trip blank.
U = Not detected at a concentration exceeding laboratory reporting limit
ve = Estimated value. The reported range exceeds the calibration range of the analysis.
z = Gasoline/petroleum detection result is likely elevated due to high detections of CVOCs.

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	**–**	**0.88**	**1.2**	**–**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	**–**	**0.058**	**0.068**	**–**
B-1A	B-1/S-2	12/01/89	HC	ARI	10.5	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
B-2A	B-2/S-1	12/01/89	HC	ARI	10	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
B-212	B-212-15	09/08/17	PES	ESC	15	42.6	V	0.000331 U	0.000447 U	0.000243 U	0.00121 U	0.000395 U	0.000351 U	0.000305 U	0.000412 U	0.000306 U	0.000275 U	0.000238 U	0.000260 U	0.000321 U
	B-212-21	09/08/17	PES	ESC	21	36.6	S	**0.0237 J**	0.000403 U	**0.0435**	0.00109 U	0.000356 U	0.000317 U	0.000275 U	0.000372 U	**0.00931**	0.000248 U	0.000215 U	0.000235 U	0.000290 U
	B-212-35	09/08/17	PES	ESC	35	22.6	S	0.000313 U	0.000423 U	0.000230 U	0.00115 U	0.000374 U	0.000333 U	0.000289 U	0.000390 U	0.000290 U	0.000261 U	0.000226 U	0.000246 U	0.000304 U
	B-212-45	09/08/17	PES	ESC	45	12.6	S	0.000300 U	0.000406 U	0.000221 U	0.00110 U	0.000359 U	0.000319 U	0.000277 U	0.000375 U	0.000278 U	0.000250 U	0.000217 U	0.000236 U	0.000292 U
	B-907-25	09/08/17	PES	ESC	45 (dup)	12.6	S	0.00858 U	0.0116 U	0.00631 U	0.0313 U	0.0103 U	0.00911 U	0.00791 U	0.0107 U	0.00795 U	0.00715 U	0.00619 U	0.00675 U	0.00834 U
	B-212-55	09/08/17	PES	ESC	55	2.6	S	0.000324 U	0.000438 U	0.000238 U	0.00118 U	0.000387 U	0.000344 U	0.000299 U	0.000404 U	0.000300 U	0.000270 U	0.000234 U	0.000255 U	0.000315 U
	B-212-65	09/08/17	PES	ESC	65	-7.4	S	0.000333 U	0.000450 U	0.000245 U	0.00122 U	0.000398 U	0.000354 U	0.000308 U	0.000416 U	0.000309 U	0.000277 U	0.000240 U	0.000262 U	0.000324 U
	B-212-75	09/08/17	PES	ESC	75	-17.4	S	0.000334 U	0.000451 U	0.000245 U	0.00122 U	0.000399 U	0.000355 U	0.000308 U	0.000416 U	0.000309 U	0.000278 U	0.000241 U	0.000263 U	0.000324 U
	B-212-85	09/11/17	PES	ESC	85	-27.4	S	0.000326 U	0.000440 U	0.000239 U	0.00119 U	0.000389 U	0.000346 U	0.000301 U	0.000406 U	0.000302 U	0.000271 U	0.000235 U	0.000256 U	0.000317 U
	B-212-95	09/11/17	PES	ESC	95	-37.4	S	0.000375 U	0.000507 U	0.000276 U	0.00137 U	0.000448 U	0.000399 U	0.000346 U	0.000468 U	0.000347 U	0.000313 U	0.000270 U	0.000295 U	0.000365 U
	B-212-100	09/11/17	PES	ESC	100	-42.4	S	0.000346 U	0.000468 U	0.000255 U	0.00127 U	0.000414 U	0.000368 U	0.000320 U	0.000432 U	0.000321 U	0.000288 U	0.000250 U	0.000273 U	0.000337 U
B-213	B-213-15	09/05/17	PES	ESC	15	42.4	V	0.000333 U	0.000450 U	**0.000365 J**	0.00122 U	0.000397 U	0.000353 U	0.000307 U	0.000415 U	0.000308 U	0.000277 U	0.000240 U	0.000262 U	0.000323 U
	B-213-21.5	09/05/17	PES	ESC	22	35.9	S	**0.0392**	0.000404 U	**0.0661**	0.00109 U	0.000357 U	0.000318 U	0.000276 U	0.000373 U	**0.0155**	0.000249 U	0.000216 U	0.000236 U	0.000291 U
	B-213-35	09/05/17	PES	ESC	35	22.4	S	0.000311 U	0.000420 U	0.000228 U	0.00114 U	0.000371 U	0.000330 U	0.000287 U	0.000388 U	0.000288 U	0.000259 U	0.000224 U	0.000245 U	0.000302 U
	B-213-45	09/05/17	PES	ESC	45	12.4	S	0.000318 U	0.000430 U	0.000234 U	0.00116 U	0.000380 U	0.000338 U	0.000294 U	0.000397 U	0.000295 U	0.000265 U	0.000229 U	0.000251 U	0.000309 U
	B-213-55	09/05/17	PES	ESC	55	2.4	S	0.000312 U	0.000422 U	0.000230 U	0.00114 U	0.000373 U	0.000332 U	0.000288 U	0.000390 U	0.000290 U	0.000260 U	0.000225 U	0.000246 U	0.000304 U
	B-213-65	09/05/17	PES	ESC	65	-7.6	S	0.000316 U	0.000427 U	0.000232 U	0.00116 U	0.000377 U	0.000336 U	0.000292 U	0.000394 U	0.000293 U	0.000263 U	0.000228 U	0.000249 U	0.000307 U
	B-213-75	09/05/17	PES	ESC	75	-17.6	S	0.000314 U	0.000424 U	0.000231 U	0.00115 U	0.000375 U	0.000333 U	0.000290 U	0.000391 U	0.000291 U	0.000261 U	0.000226 U	0.000247 U	0.000305 U
	B-213-85	09/05/17	PES	ESC	85	-27.6	S	0.000350 U	0.000473 U	0.000257 U	0.00128 U	0.000418 U	0.000372 U	0.000323 U	0.000436 U	0.000324 U	0.000291 U	0.000252 U	0.000276 U	0.000340 U
	B-213-95	09/06/17	PES	ESC	95	-37.6	S	0.000355 U	0.000479 U	0.000261 U	0.00130 U	0.000424 U	0.000377 U	0.000327 U	0.000442 U	0.000329 U	0.000295 U	0.000256 U	0.000279 U	0.000345 U
	B-213-105	09/06/17	PES	ESC	105	-47.6	S	0.000330 U	0.000446 U	0.000242 U	0.00121 U	0.000394 U	0.000350 U	0.000304 U	0.000411 U	0.000306 U	0.000275 U	0.000238 U	0.000260 U	0.000321 U
	B-906-110	09/06/17	PES	ESC	105 (dup)	-47.6	S	0.000330 U	0.000445 U	0.000242 U	0.00121 U	0.000394 U	0.000350 U	0.000304 U	0.000411 U	0.000305 U	0.000274 U	0.000238 U	0.000259 U	0.000320 U
	B-213-115	09/06/17	PES	ESC	115	-57.6	S	0.000352 U	0.000476 U	0.000259 U	0.00129 U	0.000421 U	0.000374 U	0.000325 U	0.000439 U	0.000326 U	0.000293 U	0.000254 U	0.000277 U	0.000342 U
	B-213-125	09/06/17	PES	ESC	125	-67.6	S	0.000425 U	0.000575 U	0.000312 U	0.00156 U	0.000507 U	0.000452 U	0.000392 U	0.000530 U	0.000394 U	0.000354 U	0.000307 U	0.000334 U	0.000413 U
B-214	B-214-15	09/07/17	PES	ESC	15	42.4	V	0.000308 U	0.000416 U	0.000226 U	0.00113 U	0.000368 U	0.000327 U	0.000284 U	0.000384 U	0.000285 U	0.000256 U	0.000222 U	0.000242 U	0.000299 U
	B-214-25	09/07/17	PES	ESC	25	32.4	S	0.000303 U	0.000410 U	0.000223 U	0.00111 U	0.000363 U	0.000322 U	0.000280 U	0.000378 U	0.000281 U	0.000253 U	0.000219 U	0.000239 U	0.000295 U
	B-214-35	09/07/17	PES	ESC	35	22.4	S	0.000312 U	0.000421 U	0.000229 U	0.00114 U	0.000372 U	0.000331 U	0.000288 U	0.000389 U	0.000289 U	0.000260 U	0.000225 U	0.000245 U	0.000303 U
	B-214-45	09/07/17	PES	ESC	45	12.4	S	0.000305 U	0.000413 U	0.000225 U	0.00112 U	0.000365 U	0.000325 U	0.000282 U	0.000381 U	0.000283 U	0.000254 U	0.000220 U	0.000241 U	0.000297 U
	B-214-55	09/07/17	PES	ESC	55	2.4	S	0.000319 U	0.000431 U	0.000234 U	0.00117 U	0.000381 U	0.000339 U	0.000294 U	0.000398 U	0.000295 U	0.000265 U	0.000230 U	0.000251 U	0.000310 U
	B-214-65	09/07/17	PES	ESC	65	-7.6	S	0.000369 U	0.000499 U	0.000272 U	0.00135 U	0.000441 U	0.000393 U	0.000341 U	0.000461 U	0.000342 U	0.000308 U	0.000266 U	0.000291 U	0.000359 U
	B-214-75	09/07/17	PES	ESC	75	-17.6	S	0.000319 U	0.000431 U	0.000234 U	0.00117 U	0.000381 U	0.000339 U	0.000294 U	0.000398 U	0.000296 U	0.000266 U	0.000230 U	0.000251 U	0.000310 U
	B-214-85	09/07/17	PES	ESC	85	-27.6	S	0.000345 U	0.000466 U	0.000254 U	0.00126 U	0.000412 U	0.000367 U	0.000319 U	0.000430 U	0.000320 U	0.000287 U	0.000249 U	0.000272 U	0.000335 U
	B-908-100	09/07/17	PES	ESC	85 (dup)	-27.6	S	0.000321 U	0.000434 U	0.000236 U	0.00117 U	0.000383 U	0.000341 U	0.000296 U	0.000400 U	0.000297 U	0.000267 U	0.000231 U	0.000253 U	0.000312 U
	B-214-95	09/07/17	PES	ESC	95	-37.6	S	0.000315 U	0.000426 U	0.000232 U	0.00115 U	0.000377 U	0.000335 U	0.000291 U	0.000393 U	0.000292 U	0.000262 U	0.000227 U	0.000248 U	0.000306 U
	B-214-105	09/07/17	PES	ESC	105	-47.6	S	0.000363 U	0.000491 U	0.000267 U	0.00133 U	0.000434 U	0.000386 U	0.000335 U	0.000453 U	0.000337 U	0.000302 U	0.000262 U	0.000286 U	0.000353 U
	B-214-115	09/11/17	PES	ESC	115	-57.6	S	0.000350 U	0.000473 U	0.000257 U	0.00128 U	0.000418 U	0.000372 U	0.000323 U	0.000437 U	0.000324 U	0.000292 U	0.000252 U	0.000276 U	0.000340 U
	B-214-120	09/11/17	PES	ESC	120	-62.6	S	0.000339 U	0.000458 U	0.000249 U	0.00124 U	0.000405 U	0.000360 U	0.000313 U	0.000423 U	0.000314 U	0.000282 U	0.000244 U	0.000267 U	0.000329 U
B-215	B-215-15	09/12/17	PES	ESC	15	39.0	V	0.000311 U	0.000421 U	0.000229 U	0.00114 U	0.000372 U	0.000331 U	0.000287 U	0.000388 U	0.000288 U	0.000259 U	0.000224 U	0.000245 U	0.000303 U
	B-215-25	09/12/17	PES	ESC	25	29.0	S	0.000307 U	0.000415 U	0.000226 U	0.00112 U	0.000367 U	0.000326 U	0.000284 U	0.000383 U	0.000285 U	0.000256 U	0.000222 U	0.000242 U	0.000299 U
	B-215-35	09/12/17	PES	ESC	35	19.0	S	0.000338 U	0.000457 U	0.000249 U	0.00124 U	0.000404 U	0.000360 U	0.000312 U	0.000422 U	0.000314 U	0.000282 U	0.000244 U	0.000266 U	0.000329 U
	B-215-45	09/12/17	PES	ESC	45	9.0	S	0.000305 U	0.000413 U	0.000225 U	0.00112 U	0.000365 U	0.000325 U	0.000282 U	0.000381 U	0.000283 U	0.000254 U	0.000220 U	0.000240 U	0.000297 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
B-215 (continued)	B-215-55	09/12/17	PES	ESC	55	-1.1	S	0.000318 U	0.000430 U	0.000234 U	0.00116 U	0.000380 U	0.000338 U	0.000293 U	0.000396 U	0.000295 U	0.000265 U	0.000229 U	0.000250 U	0.000309 U
	B-215-65	09/12/17	PES	ESC	65	-11.1	S	0.00821 U	0.0111 U	0.00604 U	0.0300 U	0.00981 U	0.00872 U	0.00757 U	0.0102 U	0.00761 U	0.00684 U	0.00592 U	0.00646 U	0.00798 U
	B-215-75	09/12/17	PES	ESC	75	-21.1	S	0.000316 U	0.000428 U	0.000233 U	0.00116 U	0.000378 U	0.000336 U	0.000292 U	0.000395 U	0.000293 U	0.000264 U	0.000228 U	0.000249 U	0.000308 U
	B-215-85	09/13/17	PES	ESC	85	-31.1	S	0.000346 U	0.000468 U	0.000254 U	0.00127 U	0.000413 U	0.000368 U	0.000319 U	0.000432 U	0.000321 U	0.000288 U	0.000250 U	0.000272 U	0.000336 U
	B-909-115	09/13/17	PES	ESC	85 (dup)	-31.1	S	0.000322 U	0.000435 U	0.000236 U	0.00118 U	0.000384 U	0.000342 U	0.000297 U	0.000401 U	0.000298 U	0.000268 U	0.000232 U	0.000253 U	0.000313 U
	B-215-95	09/13/17	PES	ESC	95	-41.1	S	0.000344 U	0.000464 U	0.000253 U	0.00126 U	0.000411 U	0.000365 U	0.000317 U	0.000428 U	0.000318 U	0.000286 U	0.000248 U	0.000271 U	0.000334 U
B-268	B-268-1	03/17/20	PES	PACE	1	–	V	0.00143 U	0.00598 U	0.00144 U	0.00633 U	0.000651 U	0.00180 U	0.000589 U	0.00158 U	0.00134 U	0.00211 U	0.00217 U	0.00244 U	0.000984 U
B-269	B-269-1.5	03/17/20	PES	PACE	1.5	–	V	**0.0140**	0.00526 U	**0.0187**	0.00557 U	0.000573 U	0.00158 U	0.000519 U	0.00139 U	**0.00742**	0.00186 U	0.00191 U	0.00215 U	0.000866 U
B-270	B-270-2	03/17/20	PES	PACE	2	–	V	**0.166**	0.00583 U	**0.0133**	0.00617 U	0.000635 U	0.00175 U	0.000575 U	0.00154 U	**0.0947**	0.00206 U	0.00212 U	0.00238 U	0.000959 U
B-271	B-271-1	03/17/20	PES	PACE	1	–	V	**0.00126 J**	0.00518 U	0.00125 U	0.00548 U	0.000564 U	0.00156 U	0.000510 U	0.00136 U	0.00116 U	0.00183 U	0.00188 U	0.00212 U	0.000851 U
B-272	B-272-1	03/17/20	PES	PACE	1	–	V	**0.00395 J**	0.00568 U	**0.00304 J**	0.00601 U	0.000619 U	0.00171 U	0.000560 U	0.00150 U	**0.00162 J**	0.00200 U	0.00206 U	0.00232 U	0.000935 U
	B-272-6	03/17/20	PES	PACE	6	–	V	0.00142 U	0.00596 U	0.00144 U	0.00631 U	0.000650 U	0.00179 U	0.000588 U	0.00157 U	0.00134 U	0.00210 U	0.00217 U	0.00244 U	0.000981 U
B-273	B-273-1	03/17/20	PES	PACE	1	–	V	**0.00258 J**	0.00541 U	**0.00259 J**	0.00572 U	0.000589 U	0.00163 U	0.000533 U	0.00143 U	**0.00128 J**	0.00191 U	0.00196 U	0.00221 U	0.000890 U
	B-273-3	03/17/20	PES	PACE	3	–	V	**0.00197 J**	0.00533 U	**0.00181 J**	0.00564 U	0.000580 U	0.00160 U	0.000525 U	0.00140 U	0.00119 U	0.00188 U	0.00193 U	0.00218 U	0.000876 U
	B-273-6	03/17/20	PES	PACE	6	–	V	**0.00433 J**	0.0107 U	**0.00572 J**	0.0113 U	0.00116 U	0.00321 U	0.00105 U	0.00282 U	**0.00321 J**	0.00377 U	0.00388 U	0.00437 U	0.00176 U
B-274	B-274-1	03/17/20	PES	PACE	1	–	V	**0.00623**	0.00542 U	**0.00720**	0.00574 U	0.000590 U	0.00163 U	0.000534 U	0.00143 U	**0.00260 J**	0.00191 U	0.00197 U	0.00222 U	0.000892 U
	B-274-3	03/17/20	PES	PACE	3	–	V	**0.00206 J**	0.00522 U	**0.00184 J**	0.00552 U	0.000568 U	0.00157 U	0.000514 U	0.00138 U	**0.00130 J**	0.00184 U	0.00189 U	0.00213 U	0.000859 U
	B-274-6	03/17/20	PES	PACE	6	–	V	**0.00608 J**	0.00856 U	**0.00667 J**	0.00906 U	0.000934 U	0.00257 U	0.000845 U	0.00226 U	**0.00298 J**	0.00303 U	0.00312 U	0.00351 U	0.00141 U
B-275	B-275-1	03/17/20	PES	PACE	1	–	V	**0.00143 J**	0.00566 U	0.00136 U	0.00599 U	0.000616 U	0.00170 U	0.000558 U	0.00149 U	0.00127 U	0.00200 U	0.00205 U	0.00231 U	0.000931 U
	B-275-6	03/17/20	PES	PACE	6	–	V	**0.0491**	0.00893 U	**0.0601**	0.00945 U	0.000972 U	0.00269 U	0.000879 U	0.00234 U	**0.0219**	0.00315 U	0.00324 U	0.00365 U	0.00147 U
	B-275-9	03/17/20	PES	PACE	9	–	S	**0.00306 J**	0.00742 U	**0.00182 J**	0.00785 U	0.000808 U	0.00223 U	0.000731 U	0.00195 U	0.00166 U	0.00262 U	0.00269 U	0.00303 U	0.00122 U
	B-275-10	03/17/20	PES	PACE	10	–	S	0.00126 U	0.00530 U	0.00128 U	0.00561 U	0.000577 U	0.00159 U	0.000522 U	0.00140 U	0.00119 U	0.00187 U	0.00192 U	0.00217 U	0.000872 U
B-276	B-276-1	03/17/20	PES	PACE	1	–	V	0.00212 U	0.00890 U	0.00214 U	0.00941 U	0.000969 U	0.00267 U	0.000876 U	0.00234 U	0.00199 U	0.00313 U	0.00323 U	0.00363 U	0.00147 U
	B-276-7	03/17/20	PES	PACE	7	–	V	0.00127 U	0.00533 U	0.00128 U	0.00564 U	0.000581 U	0.00160 U	0.000525 U	0.00140 U	0.00119 U	0.00188 U	0.00194 U	0.00218 U	0.000877 U
	B-970-6	03/17/20	PES	PACE	7 (dup)	–	V	0.00127 U	0.00533 UJ	0.00128 U	0.00564 U	0.000581 U	0.00160 U	0.000526 U	0.00141 U	0.00120 U	0.00188 U	0.00194 U	0.00218 U	0.000878 U
	B-276-11	03/17/20	PES	PACE	11	–	S	0.00134 U	0.00563 UJ	0.00135 U	0.00596 U	0.000613 U	0.00169 U	0.000555 U	0.00148 U	0.00126 U	0.00199 U	0.00204 U	0.00230 U	0.000926 U
B-277	B-277-1	03/18/20	PES	PACE	1	–	V	0.00145 U	0.00608 U	0.00146 U	0.00643 U	0.000662 U	0.00183 U	0.000599 U	0.00160 U	0.00136 U	0.00214 U	0.00221 U	0.00248 U	0.00100 U
	B-277-3	03/18/20	PES	PACE	3	–	V	0.00126 U	0.00530 U	0.00127 U	0.00560 U	0.000577 U	0.00159 U	0.000522 U	0.00140 U	0.00119 U	0.00187 U	0.00192 U	0.00216 U	0.000871 U
	B-277-5	03/18/20	PES	PACE	5	–	V	0.00190 U	0.00796 U	0.00192 U	0.00842 U	0.000867 U	0.00239 U	0.000784 U	0.00210 U	0.00178 U	0.00281 U	0.00289 U	0.00325 U	0.00131 U
	B-277-9.5	03/18/20	PES	PACE	9.5	–	V	**0.00874 J**	0.0114 U	**0.00790 J**	0.0121 U	0.00125 U	0.00345 U	0.00113 U	0.00301 U	**0.00291 J**	0.00403 U	0.00417 U	0.00469 U	0.00189 U
	B-277-11	03/18/20	PES	PACE	11	–	S	0.00124 U	0.00520 U	0.00125 U	0.00550 U	0.000567 U	0.00156 U	0.000513 U	0.00137 U	0.00117 U	0.00183 U	0.00189 U	0.00213 U	0.000856 U
B-278	B-278-3	03/18/20	PES	PACE	3	–	V	0.00128 U	0.00538 U	0.00129 U	0.00569 U	0.000586 U	0.00162 U	0.000530 U	0.00142 U	0.00121 U	0.00190 U	0.00195 U	0.00220 U	0.000885 U
	B-278-6	03/18/20	PES	PACE	6	–	V	0.00128 U	0.00534 U	0.00129 U	0.00566 U	0.000582 U	0.00161 U	0.000527 U	0.00141 U	0.00120 U	0.00189 U	0.00194 U	0.00218 U	0.000879 U
B-279	B-279-3	03/18/20	PES	PACE	3	–	V	0.00130 U	0.00547 U	0.00132 U	0.00578 U	0.000595 U	0.00164 U	0.000539 U	0.00144 U	0.00122 U	0.00193 U	0.00198 U	0.00223 U	0.000899 U
	B-279-5	03/18/20	PES	PACE	5	–	V	0.00129 U	0.00539 U	0.00130 U	0.00570 U	0.000587 U	0.00162 U	0.000531 U	0.00142 U	0.00121 U	0.00190 U	0.00196 U	0.00220 U	0.000887 U
	B-279-10	03/18/20	PES	PACE	10	–	V	0.00125 U	0.00524 U	0.00126 U	0.00554 U	0.000570 U	0.00158 U	0.000516 U	0.00138 U	0.00117 U	0.00185 U	0.00190 U	0.00214 U	0.000862 U
B-280	B-280-4.5	03/18/20	PES	PACE	4.5	–	V	0.00119 U	0.00499 U	0.00120 U	0.00528 U	0.000544 U	0.00150 U	0.000492 U	0.00132 U	0.00112 U	0.00176 U	0.00181 U	0.00204 U	0.000821 U
	B-280-6	03/18/20	PES	PACE	6	–	V	0.00125 U	0.00524 U	0.00126 U	0.00555 U	0.000571 U	0.00158 U	0.000517 U	0.00138 U	0.00118 U	0.00185 U	0.00190 U	0.00214 U	0.000863 U
B-281	B-281-2	03/18/20	PES	PACE	2	–	V	**0.00170 J**	0.00504 U	0.00121 U	0.00533 U	0.000549 U	0.00152 U	0.000497 U	0.00133 U	0.00113 U	0.00178 U	0.00183 U	0.00206 U	0.000829 U
	B-281-5	03/18/20	PES	PACE	5	–	V	0.00130 U	0.00546 U	0.00131 U	0.00578 U	0.000595 U	0.00164 U	0.000538 U	0.00144 U	0.00122 U	0.00193 U	0.00198 U	0.00223 U	0.000899 U
B-282	B-282-2	03/18/20	PES	PACE	2	–	V	0.00131 U	0.00550 U	0.00132 U	0.00581 U	0.000599 U	0.00165 U	0.000542 U	0.00145 U	0.00123 U	0.00194 U	0.00200 U	0.00225 U	0.000904 U
	B-282-4	03/18/20	PES	PACE	4	–	V	0.00127 U	0.00532 U	0.00128 U	0.00563 U	0.000580 U	0.00160 U	0.000525 U	0.00140 U	0.00119 U	0.00188 U	0.00193 U	0.00218 U	0.000876 U
	B-971-5	03/18/20	PES	PACE	4 (dup)	–	V	0.00122 U	0.00513 U	0.00123 U	0.00543 U	0.000559 U	0.00154 U	0.000506 U	0.00135 U	0.00115 U	0.00181 U	0.00186 U	0.00210 U	0.000844 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
B-283	B-283-0.5	08/19/20	PES	PACE	0.5	–	V	**0.00597 J**	0.00529 UJ	**0.00257 J**	0.00469 U	0.000779 U	0.000511 U	0.000781 U	0.00171 U	**0.00317 J**	0.000722 U	0.000603 U	0.000842 U	0.00166 U
B-284	B-284-1	08/19/20	PES	PACE	1	–	V	**0.00296 J**	0.00528 UJ	**0.00630**	0.00468 U	0.000778 U	0.000510 U	0.000779 U	0.00170 U	0.00240 U	0.000720 U	0.000601 U	0.000840 U	0.00166 U
B-285	B-285-1	08/19/20	PES	PACE	1	–	V	**0.00444 J**	0.00574 UJ	**0.00434 J**	0.00510 U	0.000846 U	0.000555 U	0.000847 U	0.00186 U	0.00261 U	0.000784 U	0.000654 U	0.000914 U	0.00180 U
B-286	B-286-0.5	08/19/20	PES	PACE	0.5	–	V	**0.00472 J**	0.0117 UJ	**0.0118 J**	0.0104 U	0.00172 U	0.00113 U	0.00172 U	0.00378 U	0.00532 U	0.00160 U	0.00133 U	0.00187 U	0.00367 U
B-287	B-287-1	08/19/20	PES	PACE	1	–	V	0.00411 U	0.0114 UJ	0.00411 U	0.0101 U	0.00168 U	0.00110 U	0.00169 U	0.00368 U	0.00520 U	0.00156 U	0.00130 U	0.00182 U	0.00359 U
B-288	B-288-1	08/19/20	PES	PACE	1	–	V	**0.0206 J**	0.0233 UJ	**0.0616**	0.0207 U	0.00344 U	0.00226 U	0.00344 U	0.00753 U	**0.0194 J**	0.00318 U	0.00266 U	0.00371 U	0.00731 U
B-289	B-289-0.5	08/19/20	PES	PACE	0.5	–	V	**0.0175 J**	0.0192 UJ	**0.0198 J**	0.0170 U	0.00283 U	0.00185 U	0.00283 U	0.00618 U	0.00873 U	0.00262 U	0.00219 U	0.00305 U	0.00602 U
B-290	B-290-1	08/20/20	PES	PACE	1	–	V	**0.00591 J**	0.00695 UJ	**0.0108**	0.00615 U	0.00102 U	0.000671 U	0.00102 U	0.00224 U	**0.00367 J**	0.000947 U	0.000790 U	0.00110 U	0.00218 U
B-291	B-291-1	08/20/20	PES	PACE	1	–	V	**0.00299 J**	0.00596 UJ	**0.00441 J**	0.00529 U	0.000878 U	0.000576 U	0.000879 U	0.00193 U	0.00271 U	0.000813 U	0.000679 U	0.000949 U	0.00187 U
B-292	B-292-3	08/22/20	PES	PACE	3	–	V	0.00199 U	0.00554 UJ	0.00199 U	0.00491 U	0.000815 U	0.000535 U	0.000817 U	0.00179 U	0.00252 U	0.000755 U	0.000630 U	0.000881 U	0.00174 U
	B-292-6	08/22/20	PES	PACE	6	–	V	0.00205 U	0.00572 UJ	0.00205 U	0.00507 U	0.000842 U	0.000553 U	0.000844 U	0.00185 U	0.00260 U	0.000780 U	0.000651 U	0.000910 U	0.00179 U
	B-292-9	08/22/20	PES	PACE	9	–	V	0.00187 U	0.00520 UJ	0.00187 U	0.00461 U	0.000766 U	0.000502 U	0.000767 U	0.00168 U	0.00236 U	0.000709 U	0.000592 U	0.000827 U	0.00163 U
	B-292-12	08/22/20	PES	PACE	12	–	V	0.00207 U	0.00578 UJ	0.00207 U	0.00512 U	0.000851 U	0.000558 U	0.000852 U	0.00186 U	0.00263 U	0.000788 U	0.000658 U	0.000919 U	0.00181 U
B-293	B-293-1	08/26/20	PES	PACE	1	–	V	0.00175 U	0.00488 U	0.00175 UJ	0.00432 U	0.000718 U	0.000471 U	0.000719 U	0.00157 U	0.00222 UJ	0.000665 U	0.000555 U	0.000776 U	0.00153 U
B-294	B-294-1	08/26/20	PES	PACE	1	–	V	**0.0107**	0.00618 U	**0.0136**	0.00547 U	0.000910 U	0.000597 U	0.000911 U	0.00199 U	**0.00538 J**	0.000842 U	0.000703 U	0.000983 U	0.00194 U
	B-294-2	08/26/20	PES	PACE	2	–	V	**0.0592**	0.0128 U	**0.0590**	0.0113 U	0.00188 U	0.00123 U	0.00188 U	0.00412 U	0.0278	0.00174 U	0.00146 U	0.00203 U	0.00402 U
	B-294-6	08/26/20	PES	PACE	6	–	V	0.00451 U	0.0126 U	**0.00463 J**	0.0111 U	0.00185 U	0.00121 U	0.00185 U	0.00405 U	0.00571 UJ	0.00171 U	0.00143 U	0.00200 U	0.00393 U
	B-294-10	08/26/20	PES	PACE	10	–	S	0.00213 U	0.00592 U	0.00213 UJ	0.00525 U	0.000872 U	0.000572 U	0.000873 U	0.00191 U	0.00269 UJ	0.000808 U	0.000674 U	0.000942 U	0.00186 U
B-295	B-295-1	08/26/20	PES	PACE	1	–	V	0.00190 U	0.00530 U	0.00190 UJ	0.00469 U	0.000780 U	0.000512 U	0.000781 U	0.00171 U	0.00241 UJ	0.000722 U	0.000603 U	0.000843 U	0.00166 U
	B-295-3	08/26/20	PES	PACE	3	–	V	0.00282 U	0.00785 U	0.00282 UJ	0.00696 U	0.00116 U	0.000758 U	0.00116 U	0.00253 U	0.00357 UJ	0.00107 U	0.000894 U	0.00125 U	0.00246 U
	B-295-7	08/26/20	PES	PACE	7	–	V	0.00237 U	0.00659 U	**0.00348 J**	0.00584 U	0.000971 U	0.000637 U	0.000972 U	0.00213 U	0.00300 UJ	0.000899 U	0.000751 U	0.00105 U	0.00207 U
	B-295-10	08/26/20	PES	PACE	10	–	S	0.00222 U	0.00618 U	0.00222 UJ	0.00548 U	0.000911 U	0.000597 U	0.000912 U	0.00200 U	0.00281 UJ	0.000843 U	0.000704 U	0.000984 U	0.00194 U
B-296	B-296-1	08/26/20	PES	PACE	1	–	V	**0.00245 J**	0.00500 U	**0.00306 J**	0.00443 U	0.000736 U	0.000483 U	0.000737 U	0.00161 U	0.00227 UJ	0.000682 U	0.000569 U	0.000795 U	0.00157 U
B-297	B-297-1	08/26/20	PES	PACE	1	–	V	0.00195 U	0.00542 U	0.00195 UJ	0.00480 U	0.000798 U	0.000524 U	0.000800 U	0.00175 U	0.00246 UJ	0.000739 U	0.000617 U	0.000862 U	0.00170 U
	B-297-3	08/26/20	PES	PACE	3	–	V	0.00181 U	0.00505 U	0.00181 UJ	0.00448 U	0.000744 U	0.000488 U	0.000746 U	0.00163 U	0.00230 UJ	0.000689 U	0.000576 U	0.000804 U	0.00159 U
	B-500-1	08/26/20	PES	PACE	3 (dup)	–	V	0.00185 U	0.00516 UJ	0.00185 U	0.00457 U	0.000759 U	0.000498 U	0.000761 U	0.00166 U	0.00234 U	0.000703 U	0.000587 U	0.000820 U	0.00162 U
	B-297-5	08/26/20	PES	PACE	5	–	V	0.00181 U	0.00503 UJ	0.00181 U	0.00446 U	0.000740 U	0.000486 U	0.000742 U	0.00162 U	0.00229 U	0.000686 U	0.000573 U	0.000800 U	0.00158 U
B-298	B-298-5	08/26/20	PES	PACE	5	–	V	0.00167 U	0.00464 UJ	0.00167 U	0.00412 U	0.000683 U	0.000448 U	0.000684 U	0.00149 U	0.00211 U	0.000633 U	0.000529 U	0.000739 U	0.00145 U
	B-298-6	08/26/20	PES	PACE	6	–	V	**0.00280 J**	0.00558 UJ	**0.00835**	0.00495 U	0.000823 U	0.000540 U	0.000824 U	0.00181 U	**0.00254 J**	0.000761 U	0.000636 U	0.000888 U	0.00175 U
B-299	B-299-2	02/01/21	PES	PACE	2	–	V	0.00209 U	0.00581 U	0.00209 U	0.00515 UJ	0.000855 U	0.000561 U	0.000857 U	0.00187 U	0.00264 U	0.000792 U	0.000661 U	0.000924 U	0.00182 U
	B-299-5.5	02/01/21	PES	PACE	5.5	–	V	0.00188 U	0.00524 U	0.00188 U	0.00465 UJ	0.000772 U	0.000507 U	0.000774 U	0.00169 U	0.00238 U	0.000715 U	0.000597 U	0.000834 U	0.00164 U
	B-1003-10	02/01/21	PES	PACE	5.5 (dup)	–	V	0.00196 U	0.00545 U	0.00196 U	0.00483 UJ	0.000803 U	0.000527 U	0.000804 U	0.00176 U	0.00248 U	0.000744 U	0.000621 U	0.000868 U	0.00171 U
B-300	B-300-2.5	02/01/21	PES	PACE	2.5	–	V	0.00209 U	0.00582 U	**0.00225 J**	0.00515 UJ	0.000856 U	0.000562 U	0.000858 U	0.00188 U	0.00264 U	0.000793 U	0.000662 U	0.000925 U	0.00182 U
	B-300-5.5	02/01/21	PES	PACE	5.5	–	V	0.00204 U	0.00567 U	0.00204 U	0.00503 UJ	0.000836 U	0.000548 U	0.000837 U	0.00183 U	0.00258 U	0.000774 U	0.000646 U	0.000903 U	0.00178 U
B-301	B-301-2	02/01/21	PES	PACE	2	–	V	0.00203 U	0.00564 U	0.00203 U	0.00500 UJ	0.000831 U	0.000545 U	0.000832 U	0.00182 U	0.00257 U	0.000770 U	0.000643 U	0.000898 U	0.00177 U
	B-301-5	02/01/21	PES	PACE	5	–	V	0.00214 U	0.00595 U	0.00214 U	0.00527 UJ	0.000876 U	0.000574 U	0.000877 U	0.00192 U	0.00270 U	0.000811 U	0.000677 U	0.000946 U	0.00187 U
B-302	B-302-2	02/01/21	PES	PACE	2	–	V	0.00198 U	0.00551 U	0.00198 U	0.00488 UJ	0.000811 U	0.000532 U	0.000812 U	0.00178 U	0.00250 U	0.000751 U	0.000627 U	0.000876 U	0.00173 U
	B-302-4	02/01/21	PES	PACE	4	–	V	0.00225 U	0.00628 U	0.00225 U	0.00556 UJ	0.000925 U	0.000606 U	0.000926 U	0.00203 U	0.00285 U	0.000856 U	0.000715 U	0.000999 U	0.00197 U
BB-5	S-6	03/09/97	B&V	Unknown	15-17	34.0	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	S-10	03/09/97	B&V	Unknown	25-27	24.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
BB-7	S-4	04/06/97	B&V	Unknown	10-12	17.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	**–**	**0.88**	**1.2**	**–**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	**–**	**0.058**	**0.068**	**–**
BB-8 (13.6 to 3.6)	S-8	06/06/97	B&V	Unknown	20-22	23.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–
BB-10	S-6	08/29/97	B&V	Unknown	15-17	42.0	V	–	–	–	–	–	–	–	–	–	–	–	–	–
BB-12	S-3	03/18/98	B&V	Unknown	15-16.5	18.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	S-14	03/18/98	B&V	Unknown	45-46.5	-11.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
BB-13	S-10	03/19/98	B&V	Unknown	25-27.5	1.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	S-16	03/19/98	B&V	Unknown	40-41.5	-13.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
BB-14	S-2	03/03/98	B&V	Unknown	5-6.5	21.3	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	S-5	03/03/98	B&V	Unknown	12.5-14	14.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	S-9	03/03/98	B&V	Unknown	22.5-24	4.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	S-12	03/03/98	B&V	Unknown	30-31.5	-4.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CHB-07	CHB-07-12.5-13.5	04/14/05	CH2M	ARI	12.5-13.5	16.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	CHB-07-5.0-7.0	04/14/08	CH2M	ARI	5-7	23.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CHB-08	CHB-08-15.0-16.0	04/15/08	CH2M	ARI	15-16	14.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CHB-09	CHB-09-20.0-21.5	04/16/08	CH2M	ARI	20-21.5	15.4	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	CHB-09-25.0-26.5	04/16/08	CH2M	ARI	25-26.5	10.4	S	–	–	–	–	–	–	–	–	–	–	–	–	–
GEI-MW-1 (-9.7 to -29.7)	MW-1-1-2.5	08/22/14	GEI	Fremont	1	29.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–
GEI-MW-2 (4.0 to -6.0)	MW-2-2-5.0	08/23/14	GEI	Fremont	5	26.6	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW-2-4-10.0	08/23/14	GEI	Fremont	10	21.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW-2-8-20.0	08/23/14	GEI	Fremont	20	11.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–
GEI-MW-3 (-18.7 to -28.7)	MW-3-4-10.0	08/23/14	GEI	Fremont	10	20.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW-3-10-50.0	08/23/14	GEI	Fremont	50	-19.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
GEI-4	GEI-4-2-5.0	08/23/14	GEI	Fremont	5	26.0	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	GEI-4-5-12.5	08/23/14	GEI	Fremont	12.5	18.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-1 (SCLB-3)	RS3-2.5	03/15/93	EPJ	OnSite	2.5	37.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS3-7.5	03/15/93	EPJ	OnSite	7.5	32.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS3-17.5	03/15/93	EPJ	OnSite	17.5	22.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS3-22.5/RS3-27.5 (Comp)	03/15/93	EPJ	OnSite	22.5-27.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS3-32.5	03/15/93	EPJ	OnSite	32.5	7.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS3-37.5	03/15/93	EPJ	OnSite	37.5	2.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-2 (SCLB-4)	RS4-2.5	03/15/93	EPJ	OnSite	2.5	37.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS4-7.5	03/15/93	EPJ	OnSite	7.5	32.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS4-12.5/RS4-17.5	03/15/93	EPJ	OnSite	12.5-17.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS4-22.5/RS4-27.5 (Comp)	03/15/93	EPJ	OnSite	22.5-27.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS4-37.5	03/15/93	EPJ	OnSite	37.5	2.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-3 (SCLB-5)	RS5-2.5/RS5-7.5 (Comp)	03/16/93	EPJ	OnSite	2.5-7.5	–	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS5-12.5/RS5-17.5 (Comp)	03/16/93	EPJ	OnSite	12.5-17.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS5-17.5	03/16/93	EPJ	OnSite	17.5	21.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS5-22.5	03/16/93	EPJ	OnSite	22.5	16.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS5-32.5	03/16/93	EPJ	OnSite	32.5	6.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS5-37.5	03/16/93	EPJ	OnSite	37.5	1.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	**–**	**0.88**	**1.2**	**–**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	**–**	**0.058**	**0.068**	**–**
MW-4 (SCLB-6)	RS6-2.5	03/17/93	EPJ	OnSite	2.5	37.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS6-7.5	03/17/93	EPJ	OnSite	7.5	32.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS6-12.5	03/17/93	EPJ	OnSite	12.5	27.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS6-17.5/RS6-22.5 (Comp)	03/17/93	EPJ	OnSite	17.5-22.5	–	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS6-27.5	03/17/93	EPJ	OnSite	27.5	12.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-5 (SCLB-7)	RS7-2.5	03/17/93	EPJ	OnSite	2.5	37.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS7-7.5	03/17/93	EPJ	OnSite	7.5	32.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS7-12.5	03/17/93	EPJ	OnSite	12.5	27.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS7-17.5	03/17/93	EPJ	OnSite	17.5	22.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS7-22.5	03/17/93	EPJ	OnSite	22.5	17.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-6	MW6-25	10/11/93	Retec	ARI	25	13.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-7	MW7-16.5	10/11/93	Retec	ARI	16.5	18.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW7-18.5	10/11/93	Retec	ARI	18.5	16.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-8 (28.7 to 14.2)	MW8-20	10/18/93	Retec	AAL	20	13.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-9 (33.7 to 18.7)	MW9-17.5	10/18/93	Retec	AAL	17.5	23.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-10	MW10-17.5	10/19/93	Retec	AAL	17.5	20.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW102 (B102) (-65.8 to -75.8)	B102-20	07/17/12	SES	F&BI	20	29.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-30	07/17/12	SES	F&BI	30	19.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-38	07/17/12	SES	F&BI	38	11.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-40	07/17/12	SES	F&BI	40	9.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-49	07/17/12	SES	F&BI	49	0.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-60	07/17/12	SES	F&BI	60	-10.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-70	07/18/12	SES	F&BI	70	-20.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-80	07/19/12	SES	F&BI	80	-30.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-90	07/19/12	SES	F&BI	90	-40.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-100	07/20/12	SES	F&BI	100	-50.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-110	07/20/12	SES	F&BI	110	-60.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-120	07/23/12	SES	F&BI	120	-70.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW103 (B103) (-67.6 to -77.6)	B103-10	07/25/12	SES	F&BI	10	25.9	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-18	07/25/12	SES	F&BI	18	17.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-30	07/25/12	SES	F&BI	30	5.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-40	07/25/12	SES	F&BI	40	-4.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-45	07/25/12	SES	F&BI	45	-9.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-55	07/25/12	SES	F&BI	55	-19.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-62.5	07/26/12	SES	F&BI	62.5	-26.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-75	07/26/12	SES	F&BI	75	-39.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-83	07/26/12	SES	F&BI	83	-47.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-95	07/26/12	SES	F&BI	95	-59.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-105	07/27/12	SES	F&BI	105	-69.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-113	07/27/12	SES	F&BI	113	-77.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	**–**	**0.88**	**1.2**	**–**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	**–**	**0.058**	**0.068**	**–**
MW104 (B104)	B104-10	07/30/12	SES	F&BI	10	32.7	S	–	–	–	–	–	–	–	–	–	–	–	–	–
(-76.3 to -86.3)	B104-20	07/30/12	SES	F&BI	20	22.7	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-30	07/30/12	SES	F&BI	30	12.7	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-35	07/30/12	SES	F&BI	35	7.7	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-50	07/30/12	SES	F&BI	50	-7.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-60	07/31/12	SES	F&BI	60	-17.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-69	07/31/12	SES	F&BI	69	-26.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-80	07/31/12	SES	F&BI	80	-37.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-90	08/01/12	SES	F&BI	90	-47.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-100	08/01/12	SES	F&BI	100	-57.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-110	08/01/12	SES	F&BI	110	-67.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-120	08/01/12	SES	F&BI	120	-77.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-130	08/01/12	SES	F&BI	130	-87.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW105 (B105)	B105-10	08/06/12	SES	F&BI	10	34.2	V	–	–	–	–	–	–	–	–	–	–	–	–	–
(-85.8 to -95.8)	B105-20	08/06/12	SES	F&BI	20	24.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-30	08/06/12	SES	F&BI	30	14.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-40	08/08/12	SES	F&BI	40	4.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-50	08/08/12	SES	F&BI	50	-5.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-60	08/09/12	SES	F&BI	60	-15.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-70	08/09/12	SES	F&BI	70	-25.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-80	08/09/12	SES	F&BI	80	-35.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-90	08/10/12	SES	F&BI	90	-45.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-100	08/10/12	SES	F&BI	100	-55.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-110	08/10/12	SES	F&BI	110	-65.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-120	08/10/12	SES	F&BI	120	-75.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-130	08/10/12	SES	F&BI	130	-85.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-138	08/10/12	SES	F&BI	138	-93.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW106 (B106)	B106-10	08/14/12	SES	F&BI	10	42.0	V	–	–	–	–	–	–	–	–	–	–	–	–	–
(-78.0 to -88.0)	B106-20	08/14/12	SES	F&BI	20	32.0	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-30	08/14/12	SES	F&BI	30	22.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-40	08/14/12	SES	F&BI	40	12.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-50	08/14/12	SES	F&BI	50	2.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-60	08/14/12	SES	F&BI	60	-8.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-70	08/15/12	SES	F&BI	70	-18.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-80	08/15/12	SES	F&BI	80	-28.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-90	08/15/12	SES	F&BI	90	-38.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-100	08/15/12	SES	F&BI	100	-48.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-110	08/15/12	SES	F&BI	110	-58.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-120	08/15/12	SES	F&BI	120	-68.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-130	08/15/12	SES	F&BI	130	-78.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-140	08/15/12	SES	F&BI	140	-88.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	**–**	**0.88**	**1.2**	**–**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	**–**	**0.058**	**0.068**	**–**
MW107 (B107) (8.8 to -1.2)	B107-05	03/12/12	SES	F&BI	5	38.8	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	B107-15	03/12/12	SES	F&BI	15	28.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B107-25	03/12/12	SES	F&BI	25	18.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B107-35	03/12/12	SES	F&BI	35	8.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B107-45	03/12/12	SES	F&BI	45	-1.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW108 (B108) (-7.2 to -17.2)	B108-15	12/14/12	SES	F&BI	15	17.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B108-25	12/14/12	SES	F&BI	25	7.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B108-35	12/14/12	SES	F&BI	35	-2.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B108-45	12/14/12	SES	F&BI	45	-12.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B108-50	12/14/12	SES	F&BI	50	-17.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW109 (B109) (0.0 to -10.0)	B109-05	04/12/12	SES	F&BI	5	30.0	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	B109-15	04/12/12	SES	F&BI	15	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B109-25	04/12/12	SES	F&BI	25	10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B109-35	04/12/12	SES	F&BI	35	0.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B109-45	04/12/12	SES	F&BI	45	-10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW110 (B110) (4.7 to -5.3)	B110-15	04/12/12	SES	F&BI	15	24.7	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	B110-25	04/12/12	SES	F&BI	25	14.7	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B110-35	04/12/12	SES	F&BI	35	4.7	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B110-45	04/12/12	SES	F&BI	45	-5.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW111 (B111) (-33.5 to -43.5)	B111-10	05/12/12	SES	F&BI	10	26.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	B111-20	05/12/12	SES	F&BI	20	16.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B111-30	05/12/12	SES	F&BI	30	6.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B111-38	05/12/12	SES	F&BI	38	-1.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B111-50	05/12/12	SES	F&BI	50	-13.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B111-60	06/12/12	SES	F&BI	60	-23.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B111-70	06/12/12	SES	F&BI	70	-33.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B111-80	06/12/12	SES	F&BI	80	-43.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW112 (B112) (-17.5 to -27.5)	B112-10	11/12/12	SES	F&BI	10	47.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	B112-20	11/12/12	SES	F&BI	20	37.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B112-30	11/12/12	SES	F&BI	30	27.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B112-40	11/12/12	SES	F&BI	40	17.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B112-50	11/12/12	SES	F&BI	50	7.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B112-60	11/12/12	SES	F&BI	60	-2.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B112-75	11/12/12	SES	F&BI	75	-17.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B112-85	12/12/12	SES	F&BI	85	-27.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW113 (B113) (-37.1 to -47.1)	B113-10	12/18/12	SES	F&BI	10	22.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B113-20	12/18/12	SES	F&BI	20	12.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B113-30	12/18/12	SES	F&BI	30	2.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B113-40	12/18/12	SES	F&BI	40	-7.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B113-50	12/18/12	SES	F&BI	50	-17.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW114 (B114) (10.8 to 0.8)	B114-15	10/12/12	SES	F&BI	15	30.8	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	B114-25	10/12/12	SES	F&BI	25	20.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B114-35	10/12/12	SES	F&BI	35	10.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	**–**	**0.88**	**1.2**	**–**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	**–**	**0.058**	**0.068**	**–**
MW114 (B114)	B114-40	10/12/12	SES	F&BI	40	5.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
(continued)	B114-45	10/12/12	SES	F&BI	45	0.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW115 (B115)	B115-10	12/13/12	SES	F&BI	10	24.1	V	–	–	–	–	–	–	–	–	–	–	–	–	–
(-0.9 to -10.9)	B115-15	12/13/12	SES	F&BI	15	19.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B115-25	12/13/12	SES	F&BI	25	9.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B115-35	12/13/12	SES	F&BI	35	-0.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B115-45	12/13/12	SES	F&BI	45	-10.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW116 (B116)	B116-15	07/12/12	SES	F&BI	15	16.4	S	–	–	–	–	–	–	–	–	–	–	–	–	–
(-3.6 to -13.6)	B116-25	07/12/12	SES	F&BI	25	6.4	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B116-35	07/12/12	SES	F&BI	35	-3.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B116-45	07/12/12	SES	F&BI	45	-13.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW117 (B117)	B117-10	02/04/13	SES	F&BI	10	46.9	V	–	–	–	–	–	–	–	–	–	–	–	–	–
(16.9 to 1.9)	B117-20	02/04/13	SES	F&BI	20	36.9	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	B117-30	02/04/13	SES	F&BI	30	26.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B117-40	02/04/13	SES	F&BI	40	16.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B117-50	02/04/13	SES	F&BI	50	6.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW118 (B118)	B118-10	03/21/13	SES	F&BI	10	42.9	V	–	–	–	–	–	–	–	–	–	–	–	–	–
(12.9 to 2.9)	B118-20	03/21/13	SES	F&BI	20	32.9	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	B118-30	03/21/13	SES	F&BI	30	22.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B118-40	03/21/13	SES	F&BI	40	12.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B118-50	03/21/13	SES	F&BI	50	2.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW119 (B119)	B119-10	03/21/13	SES	F&BI	10	27.4	V	–	–	–	–	–	–	–	–	–	–	–	–	–
(2.4 to -7.7)	B119-20	03/21/13	SES	F&BI	20	17.4	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B119-30	03/21/13	SES	F&BI	30	7.4	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B119-40	03/21/13	SES	F&BI	40	-2.7	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW120 (B120)	B120-20	12/16/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
(0 to -10)	B120-30	12/16/13	SES	F&BI	30	10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B120-45	12/16/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW121 (B121)	B121-15	12/16/13	SES	F&BI	15	26.7	S	–	–	–	–	–	–	–	–	–	–	–	–	–
(26.7 to 16.7)	B121-25	12/16/13	SES	F&BI	25	16.7	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW122 (B122)	B122-15	12/17/13	SES	F&BI	15	15.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
(-75 to -89)	B122-25	12/17/13	SES	F&BI	25	5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B122-40	12/17/13	SES	F&BI	40	-10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B122-45	12/17/13	SES	F&BI	45	-15.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B122-50	12/17/13	SES	F&BI	50	-20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B122-60	12/17/13	SES	F&BI	60	-30.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B122-70	12/17/13	SES	F&BI	70	-40.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B122-80	12/17/13	SES	F&BI	80	-50.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B122-100	12/17/13	SES	F&BI	100	-70.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW123 (B123)	B123-20	12/18/13	SES	F&BI	20	7.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
(-42.5 to -52.5)																				

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	**–**	**0.88**	**1.2**	**–**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	**–**	**0.058**	**0.068**	**–**
MW124 (B124)	B124-10	12/19/13	SES	F&BI	10	46.2	V	–	–	–	–	–	–	–	–	–	–	–	–	–
(-53.8 to -63.8)	B124-20	12/19/13	SES	F&BI	20	36.2	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	B124-30	12/19/13	SES	F&BI	30	26.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B124-40	12/19/13	SES	F&BI	40	16.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B124-50	12/19/13	SES	F&BI	50	6.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B124-60	12/19/13	SES	F&BI	60	-3.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B124-70	12/19/13	SES	F&BI	70	-13.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B124-80	12/19/13	SES	F&BI	80	-23.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B124-90	12/19/13	SES	F&BI	90	-33.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B124-100	12/19/13	SES	F&BI	100	-43.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B124-110	12/19/13	SES	F&BI	110	-53.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B124-120	12/19/13	SES	F&BI	120	-63.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW125 (B125)	B125-15	12/20/13	SES	F&BI	15	28.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–
(28.6 to 13.6)	B125-20	12/20/13	SES	F&BI	20	23.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B125-25	12/20/13	SES	F&BI	25	18.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B125-30	12/20/13	SES	F&BI	30	13.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW126 (B126)	B126-20	12/30/13	SES	F&BI	20	10.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
(-54.1 to -64.1)	B126-35	12/30/13	SES	F&BI	35	-4.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B126-45	12/30/13	SES	F&BI	45	-14.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B126-55	12/30/13	SES	F&BI	55	-24.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B126-60	12/31/13	SES	F&BI	60	-29.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B126-65	01/01/14	SES	F&BI	65	-34.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B126-75	01/02/14	SES	F&BI	75	-44.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B126-80	01/03/14	SES	F&BI	80	-49.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B126-85	01/04/14	SES	F&BI	85	-54.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B126-95	01/05/14	SES	F&BI	95	-64.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW127 (B127)	B127-15	12/31/13	SES	F&BI	15	24.0	V	–	–	–	–	–	–	–	–	–	–	–	–	–
(-1.0 to -11.0)	B127-25	12/31/13	SES	F&BI	25	14.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B127-40	12/31/13	SES	F&BI	40	-1.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B127-45	12/31/13	SES	F&BI	45	-6.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B127-50	12/31/13	SES	F&BI	50	-11.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW128 (B128)	B128-25	01/09/14	SES	F&BI	25	2.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
(-30.8 to -40.8)	B128-45	01/09/14	SES	F&BI	45	-17.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B128-65	01/09/14	SES	F&BI	65	-37.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-138	MW-138-15	09/12/17	PES	ESC	15	42.5	V	0.000341 U	0.000461 U	0.000251 U	0.00125 U	0.000408 U	0.000363 U	0.000315 U	0.000426 U	0.000316 U	0.000284 U	0.000246 U	0.000269 U	0.000332 U
(-47.5 to -57.5)	MW-138-25	09/12/17	PES	ESC	25	32.5	S	0.000330 U	0.000447 U	0.000243 U	0.00121 U	0.000395 U	0.000351 U	0.000305 U	0.000412 U	0.000306 U	0.000275 U	0.000238 U	0.000260 U	0.000321 U
	MW-138-35	09/12/17	PES	ESC	35	22.5	S	0.000307 U	0.000415 U	0.000225 U	0.00112 U	0.000366 U	0.000326 U	0.000283 U	0.000383 U	0.000284 U	0.000255 U	0.000221 U	0.000241 U	0.000298 U
	MW-138-45	09/12/17	PES	ESC	45	12.5	S	0.000303 U	0.000410 U	0.000223 U	0.00111 U	0.000363 U	0.000322 U	0.000280 U	0.000378 U	0.000281 U	0.000253 U	0.000219 U	0.000239 U	0.000295 U
	MW-138-56	09/12/17	PES	ESC	56	1.5	S	0.000323 U	0.000436 U	0.000237 U	0.00118 U	0.000386 U	0.000343 U	0.000298 U	0.000403 U	0.000299 U	0.000269 U	0.000233 U	0.000254 U	0.000314 U
	MW-138-65	09/13/17	PES	ESC	65	-7.5	S	0.000310 U	0.000420 U	0.000228 U	0.00114 U	0.000371 U	0.000330 U	0.000287 U	0.000387 U	0.000288 U	0.000258 U	0.000224 U	0.000244 U	0.000302 U
	B-910-90	09/13/17	PES	ESC	65 (dup)	-7.5	S	0.000333 U	0.000450 U	0.000244 U	0.00122 U	0.000397 U	0.000353 U	0.000307 U	0.000415 U	0.000308 U	0.000277 U	0.000240 U	0.000262 U	0.000323 U
	MW-138-75	09/13/17	PES	ESC	75	-17.5	S	0.000316 U	0.000427 U	0.000232 U	0.00116 U	0.000378 U	0.000336 U	0.000292 U	0.000394 U	0.000293 U	0.000263 U	0.000228 U	0.000249 U	0.000307 U
	MW-138-85	09/13/17	PES	ESC	85	-27.5	S	0.000345 U	0.000466 U	0.000254 U	0.00126 U	0.000412 U	0.000367 U	0.000319 U	0.000430 U	0.000320 U	0.000287 U	0.000249 U	0.000272 U	0.000335 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
MW-138 (continued)	MW-138-95	09/13/17	PES	ESC	95	-37.5	S	0.000313 U	0.000423 U	0.000230 U	0.00115 U	0.000374 U	0.000333 U	0.000289 U	0.000390 U	0.000290 U	0.000261 U	0.000226 U	0.000247 U	0.000304 U
	MW-138-105	09/13/17	PES	ESC	105	-47.5	S	0.000357 U	0.000483 U	0.000262 U	0.00131 U	0.000427 U	0.000379 U	0.000330 U	0.000445 U	0.000331 U	0.000297 U	0.000257 U	0.000281 U	0.000347 U
	MW-138-115	09/14/17	PES	ESC	115	-57.5	S	0.000332 U	0.000449 U	0.000244 U	0.00122 U	0.000397 U	0.000353 U	0.000307 U	0.000415 U	0.000308 U	0.000277 U	0.000240 U	0.000262 U	0.000323 U
MW-140 (-78.9 to -88.9)	MW-140-15	08/30/17	PES	ESC	15	35.6	V	0.000327 U	0.000442 U	0.000241 U	0.00120 U	0.000391 U	0.000348 U	0.000302 U	0.000408 U	0.000303 U	0.000273 U	0.000236 U	0.000258 U	0.000318 U
	MW-140-25	08/30/17	PES	ESC	25	25.6	S	0.000311 U	0.000421 U	0.000229 U	0.00114 U	0.000372 U	0.000331 U	0.000287 U	0.000388 U	0.000288 U	0.000259 U	0.000224 U	0.000245 U	0.000303 U
	MW-140-35	08/30/17	PES	ESC	35	15.6	S	0.00837 U	0.0113 U	0.00615 U	0.0305 U	0.0100 U	0.00888 U	0.00771 U	0.0104 U	0.00775 U	0.00697 U	0.00604 U	0.00658 U	0.00813 U
	MW-140-45	08/30/17	PES	ESC	45	5.6	S	0.000306 U	0.000414 U	0.000225 U	0.00112 U	0.000366 U	0.000325 U	0.000283 U	0.000382 U	0.000284 U	0.000255 U	0.000221 U	0.000241 U	0.000298 U
	MW-140-55	08/30/17	PES	ESC	55	-4.4	S	0.000315 U	0.000426 U	0.000232 U	0.00115 U	0.000376 U	0.000335 U	0.000291 U	0.000393 U	0.000292 U	0.000262 U	0.000227 U	0.000248 U	0.000306 U
	MW-140-65	08/30/17	PES	ESC	65	-14.4	S	0.000307 U	0.000415 U	0.000226 U	0.00112 U	0.000367 U	0.000327 U	0.000284 U	0.000383 U	0.000285 U	0.000256 U	0.000222 U	0.000242 U	0.000299 U
	MW-140-75	08/30/17	PES	ESC	75	-24.4	S	0.00774 U	0.0105 U	0.00569 U	0.0283 U	0.00925 U	0.00822 U	0.00714 U	0.00965 U	0.00717 U	0.00645 U	0.00559 U	0.00609 U	0.00753 U
	MW-140-90	08/30/17	PES	ESC	90	-39.4	S	0.000338 U	0.000456 U	0.000248 U	0.00124 U	0.000403 U	0.000359 U	0.000312 U	0.000421 U	0.000313 U	0.000281 U	0.000244 U	0.000266 U	0.000328 U
	MW-140-110	08/31/17	PES	ESC	110	-59.4	S	0.000332 U	0.000449 U	0.000244 U	0.00122 U	0.000397 U	0.000353 U	0.000307 U	0.000415 U	0.000308 U	0.000277 U	0.000240 U	0.000262 U	0.000323 U
	MW-140-130	08/31/17	PES	ESC	130	-79.4	S	0.000324 U	0.000439 U	0.000239 U	0.00119 U	0.000388 U	0.000345 U	0.000300 U	0.000405 U	0.000301 U	0.000270 U	0.000234 U	0.000256 U	0.000315 U
	MW-140-140	08/31/17	PES	ESC	140	-89.4	S	0.00811 U	0.0110 U	0.00596 U	0.0296 U	0.00969 U	0.00861 U	0.00748 U	0.0101 U	0.00751 U	0.00675 U	0.00585 U	0.00638 U	0.00788 U
MW-142 (2.4 to -7.6)	MW-142-5	04/12/18	PES	ESC	5	37.1	V	0.000345 U	0.000467 U	0.000254 U	0.00126 U	0.000413 U	0.000367 U	0.000319 U	0.000431 U	0.000320 U	0.000288 U	0.000249 U	0.000272 U	0.000336 U
MW-143 (-27.7 to -37.7)	MW-143-10	04/11/18	PES	ESC	10	32.0	V	0.000398 U	0.000538 U	0.000292 U	0.00146 U	0.000475 U	0.000423 U	0.000367 U	0.000496 U	0.000369 U	0.000331 U	0.000287 U	0.000313 U	0.000387 U
	MW-143-20	04/11/18	PES	ESC	20	22.0	S	0.000333 U	0.000451 U	0.000245 U	0.00122 U	0.000398 U	0.000354 U	0.000308 U	0.000416 U	0.000309 U	0.000278 U	0.000240 U	0.000263 U	0.000324 U
	MW-143-30	04/11/18	PES	ESC	30	12.0	S	0.000327 U	0.000442 U	0.000240 U	0.00120 U	0.000391 U	0.000347 U	0.000302 U	0.000408 U	0.000303 U	0.000272 U	0.000236 U	0.000257 U	0.000318 U
	MW-143-40	04/11/18	PES	ESC	40	2.0	S	0.000342 U	0.000463 U	0.000252 U	0.00125 U	0.000409 U	0.000364 U	0.000316 U	0.000427 U	0.000317 U	0.000285 U	0.000247 U	0.000270 U	0.000333 U
	MW-143-50	04/11/18	PES	ESC	50	-8.0	S	0.000329 U	0.000444 U	0.000242 U	0.00120 U	0.000393 U	0.000349 U	0.000304 U	0.000410 U	0.000305 U	0.000274 U	0.000237 U	0.000259 U	0.000320 U
	MW-143-60	04/11/18	PES	ESC	60	-18.0	S	0.000319 U	0.000431 U	0.000235 U	0.00117 U	0.000381 U	0.000339 U	0.000295 U	0.000398 U	0.000296 U	0.000266 U	0.000230 U	0.000251 U	0.000310 U
	MW-143-70	04/11/18	PES	ESC	70	-28.0	S	0.000316 U	0.000427 U	0.000232 U	0.00116 U	0.000377 U	0.000336 U	0.000292 U	0.000394 U	0.000293 U	0.000263 U	0.000228 U	0.000249 U	0.000307 U
	MW-143-80	04/11/18	PES	ESC	80	-38.0	S	0.000326 U	0.000441 U	0.000240 U	0.00119 U	0.000390 U	0.000347 U	0.000301 U	0.000407 U	0.000302 U	0.000272 U	0.000235 U	0.000257 U	0.000317 U
	MW-902-20	04/11/18	PES	ESC	80 (dup)	-38.0	S	0.000321 U	0.000434 U	0.000236 U	0.00117 U	0.000384 U	0.000341 U	0.000297 U	0.000401 U	0.000298 U	0.000267 U	0.000232 U	0.000253 U	0.000312 U
MW-145 (-26.1 to -36.1)	MW-145-10	04/17/18	PES	ESC	10	33.5	V	0.000361 U	0.000487 U	0.000265 U	0.00132 U	0.000431 U	0.000383 U	0.000333 U	0.000450 U	0.000334 U	0.000300 U	0.000260 U	0.000284 U	0.000351 U
	MW-145-20	04/17/18	PES	ESC	20	23.5	S	0.000335 U	0.000453 U	0.000246 U	0.00123 U	0.000400 U	0.000356 U	0.000309 U	0.000418 U	0.000311 U	0.000279 U	0.000242 U	0.000264 U	0.000326 U
	MW-145-30	04/17/18	PES	ESC	30	13.5	S	0.000340 U	0.000460 U	0.000250 U	0.00125 U	0.000407 U	0.000362 U	0.000314 U	0.000425 U	0.000315 U	0.000283 U	0.000245 U	0.000268 U	0.000331 U
	MW-145-40	04/17/18	PES	ESC	40	3.5	S	0.000320 U	0.000432 U	0.000235 U	0.00117 U	0.000382 U	0.000340 U	0.000295 U	0.000399 U	0.000296 U	0.000266 U	0.000231 U	0.000252 U	0.000311 U
	MW-145-50	04/17/18	PES	ESC	50	-6.5	S	0.000314 U	0.000425 U	0.000231 U	0.00115 U	0.000376 U	0.000334 U	0.000290 U	0.000392 U	0.000291 U	0.000262 U	0.000227 U	0.000248 U	0.000306 U
	MW-145-60	04/17/18	PES	ESC	60	-16.5	S	0.000316 U	0.000428 U	0.000233 U	0.00116 U	0.000378 U	0.000336 U	0.000292 U	0.000395 U	0.000293 U	0.000263 U	0.000228 U	0.000249 U	0.000308 U
	MW-145-70	04/17/18	PES	ESC	70	-26.5	S	0.000348 U	0.000471 U	0.000256 U	0.00127 U	0.000416 U	0.000370 U	0.000321 U	0.000434 U	0.000323 U	0.000290 U	0.000251 U	0.000274 U	0.000338 U
	MW-145-80	04/17/18	PES	ESC	80	-36.5	S	0.000330 U	0.000446 U	0.000242 U	0.00121 U	0.000394 U	0.000350 U	0.000304 U	0.000411 U	0.000306 U	0.000274 U	0.000238 U	0.000260 U	0.000320 U
	MW-903-40	04/17/18	PES	ESC	80 (dup)	-36.5	S	0.000322 U	0.000435 U	0.000237 U	0.00118 U	0.000385 U	0.000342 U	0.000297 U	0.000402 U	0.000298 U	0.000268 U	0.000232 U	0.000253 U	0.000313 U
MW-147 (-17.6 to -27.6)	MW-147-10	04/02/18	PES	ESC	10	41.9	V	0.000312 U	0.000421 U	0.000229 U	0.00114 U	0.000372 U	0.000331 U	0.000288 U	0.000389 U	0.000289 U	0.000260 U	0.000225 U	0.000245 U	0.000303 U
	MW-147-20	04/02/18	PES	ESC	20	31.9	S	0.000310 U	0.000419 U	0.000228 U	0.00113 U	0.000371 U	0.000330 U	0.000286 U	0.000387 U	0.000287 U	0.000258 U	0.000224 U	0.000244 U	0.000302 U
	MW-147-30	04/02/18	PES	ESC	30	21.9	S	0.000320 U	0.000433 U	0.000236 U	0.00117 U	0.000383 U	0.000341 U	0.000296 U	0.000400 U	0.000297 U	0.000267 U	0.000231 U	0.000252 U	0.000312 U
	MW-147-40	04/02/18	PES	ESC	40	11.9	S	0.000317 U	0.000428 U	0.000233 U	0.00116 U	0.000378 U	0.000337 U	0.000292 U	0.000395 U	0.000293 U	0.000264 U	0.000228 U	0.000249 U	0.000308 U
	MW-147-50	04/02/18	PES	ESC	50	1.9	S	0.000318 U	0.000430 U	0.000234 U	0.00116 U	0.000380 U	0.000338 U	0.000294 U	0.000397 U	0.000295 U	0.000265 U	0.000229 U	0.000250 U	0.000309 U
	MW-147-60	04/02/18	PES	ESC	60	-8.2	S	0.000309 U	0.000417 U	0.000227 U	0.00113 U	0.000369 U	0.000328 U	0.000285 U	0.000385 U	0.000286 U	0.000257 U	0.000223 U	0.000243 U	0.000300 U
	MW-901-10	04/02/18	PES	ESC	60 (dup)	-8.2	S	0.000309 U	0.000418 U	0.000227 U	0.00113 U	0.000369 U	0.000328 U	0.000285 U	0.000386 U	0.000286 U	0.000257 U	0.000223 U	0.000243 U	0.000300 U
	MW-147-70	04/02/18	PES	ESC	70	-18.2	S	0.000321 U	0.000434 U	0.000236 U	0.00118 U	0.000384 U	0.000341 U	0.000297 U	0.000401 U	0.000298 U	0.000267 U	0.000232 U	0.000253 U	0.000312 U
	MW-147-80	04/02/18	PES	ESC	80	-28.2	S	0.000332 U	0.000449 U	0.000244 U	0.00121 U	0.000397 U	0.000353 U	0.000307 U	0.000414 U	0.000308 U	0.000277 U	0.000240 U	0.000262 U	0.000323 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
MW-148	MW-148-11	04/09/18	PES	ESC	11	32.9	V	0.000331 U	0.000448 U	0.000243 U	0.00121 U	0.000396 U	0.000352 U	0.000306 U	0.000413 U	0.000307 U	0.000276 U	0.000239 U	0.000261 U	0.000322 U
(-25.7 to -35.7)	MW-148-20	04/09/18	PES	ESC	20	23.9	S	0.000311 U	0.000421 U	0.000229 U	0.00114 U	0.000372 U	0.000331 U	0.000287 U	0.000388 U	0.000289 U	0.000259 U	0.000225 U	0.000245 U	0.000303 U
	MW-148-30	04/09/18	PES	ESC	30	13.9	S	0.000322 U	0.000436 U	0.000237 U	0.00118 U	0.000385 U	0.000342 U	0.000298 U	0.000402 U	0.000299 U	0.000268 U	0.000232 U	0.000254 U	0.000313 U
	MW-148-40	04/09/18	PES	ESC	40	3.9	S	0.000312 U	0.000421 U	0.000229 U	0.00114 U	0.000373 U	0.000331 U	0.000288 U	0.000389 U	0.000289 U	0.000260 U	0.000225 U	0.000246 U	0.000303 U
	MW-148-50	04/09/18	PES	ESC	50	-6.1	S	0.000317 U	0.000428 U	0.000233 U	0.00116 U	0.000378 U	0.000336 U	0.000292 U	0.000395 U	0.000293 U	0.000264 U	0.000228 U	0.000249 U	0.000308 U
	MW-148-60	04/09/18	PES	ESC	60	-16.1	S	0.000362 U	0.000490 U	0.000266 U	0.00132 U	0.000433 U	0.000385 U	0.000334 U	0.000452 U	0.000336 U	0.000302 U	0.000261 U	0.000285 U	0.000352 U
	MW-148-70	04/09/18	PES	ESC	70	-26.1	S	0.000362 U	0.000489 U	0.000266 U	0.00132 U	0.000432 U	0.000384 U	0.000334 U	0.000451 U	0.000335 U	0.000301 U	0.000261 U	0.000285 U	0.000352 U
	MW-148-80	04/09/18	PES	ESC	80	-36.1	S	0.000337 U	0.000456 U	0.000248 U	0.00123 U	0.000403 U	0.000358 U	0.000311 U	0.000421 U	0.000313 U	0.000281 U	0.000243 U	0.000266 U	0.000328 U
MW-153	MW-153-10	03/27/18	PES	ESC	10	44.4	V	0.000325 U	0.000440 U	0.000239 U	0.00119 U	0.000389 U	0.000346 U	0.000301 U	0.000406 U	0.000302 U	0.000271 U	0.000235 U	0.000256 U	0.000316 U
(-65.3 to -75.3)	MW-153-20	03/27/18	PES	ESC	20	34.4	V	0.000314 U	0.000425 U	0.000231 U	0.00115 U	0.000375 U	0.000334 U	0.000290 U	0.000392 U	0.000291 U	0.000262 U	0.000227 U	0.000247 U	0.000305 U
	MW-153-30	03/27/18	PES	ESC	30	24.4	S	0.000308 U	0.000416 U	0.000226 U	0.00113 U	0.000368 U	0.000327 U	0.000284 U	0.000384 U	0.000285 U	0.000256 U	0.000222 U	0.000242 U	0.000299 U
	MW-153-40	03/27/18	PES	ESC	40	14.4	S	0.000325 U	0.000440 U	0.000239 U	0.00119 U	0.000389 U	0.000346 U	0.000300 U	0.000406 U	0.000301 U	0.000271 U	0.000235 U	0.000256 U	0.000316 U
	MW-153-50	03/27/18	PES	ESC	50	4.4	S	0.000318 U	0.000430 U	0.000234 U	0.00116 U	0.000380 U	0.000338 U	0.000294 U	0.000397 U	0.000295 U	0.000265 U	0.000230 U	0.000251 U	0.000309 U
	MW-153-61	03/27/18	PES	ESC	61	-6.7	S	0.000326 U	0.000441 U	0.000240 U	0.00119 U	0.000390 U	0.000347 U	0.000301 U	0.000407 U	0.000302 U	0.000272 U	0.000235 U	0.000257 U	0.000317 U
	MW-153-70	03/27/18	PES	ESC	70	-15.7	S	0.000320 U	0.000432 U	0.000235 U	0.00117 U	0.000382 U	0.000340 U	0.000295 U	0.000399 U	0.000296 U	0.000266 U	0.000230 U	0.000252 U	0.000311 U
	MW-153-80	03/28/18	PES	ESC	80	-25.7	S	0.000317 U	0.000428 U	0.000233 U	0.00116 U	0.000378 U	0.000337 U	0.000292 U	0.000395 U	0.000293 U	0.000264 U	0.000228 U	0.000249 U	0.000308 U
	MW-153-90	03/28/18	PES	ESC	90	-35.7	S	0.000346 U	0.000467 U	0.000254 U	0.00126 U	0.000413 U	0.000367 U	0.000319 U	0.000431 U	0.000320 U	0.000288 U	0.000249 U	0.000272 U	0.000336 U
	MW-153-110	03/28/18	PES	ESC	110	-55.7	S	0.000338 U	0.000457 U	0.000248 U	0.00124 U	0.000404 U	0.000359 U	0.000312 U	0.000421 U	0.000313 U	0.000281 U	0.000244 U	0.000266 U	0.000328 U
	MW-153-130	03/29/18	PES	ESC	130	-75.7	S	0.000330 U	0.000446 U	0.000242 U	0.00121 U	0.000394 U	0.000350 U	0.000304 U	0.000411 U	0.000306 U	0.000275 U	0.000238 U	0.000260 U	0.000321 U
MW-158	MW-158-20	04/05/18	PES	ESC	20	21.1	S	0.000325 U	0.000439 U	0.000239 U	0.00119 U	0.000389 U	0.000345 U	0.000300 U	0.000406 U	0.000301 U	0.000271 U	0.000234 U	0.000256 U	0.000316 U
	MW-158-30	04/05/18	PES	ESC	30	11.1	S	0.0339 U	0.0458 U	**0.0317 J**	0.124 U	0.0405 U	0.0360 U	0.0313 U	0.0422 U	0.0314 U	0.0282 U	0.0244 U	0.0267 U	0.0329 U
MW-158A	MW-158A-40	04/05/18	PES	ESC	40	1.1	S	0.000354 U	0.000478 U	0.000260 U	0.00129 U	0.000423 U	0.000376 U	0.000327 U	0.000441 U	0.000328 U	0.000295 U	0.000255 U	0.000279 U	0.000344 U
(-47.2 to -58.5)	MW-158A-50	04/05/18	PES	ESC	50	-8.9	S	0.000332 U	0.000449 U	0.000244 U	0.00121 U	0.000397 U	0.000353 U	0.000306 U	0.000414 U	0.000308 U	0.000276 U	0.000239 U	0.000261 U	0.000323 U
	MW-158A-60	04/05/18	PES	ESC	60	-18.9	S	0.000330 U	0.000447 U	0.000243 U	0.00121 U	0.000395 U	0.000351 U	0.000305 U	0.000412 U	0.000306 U	0.000275 U	0.000238 U	0.000260 U	0.000321 U
	MW-158A-70	04/05/18	PES	ESC	70	-28.9	S	0.000322 U	0.000435 U	0.000237 U	0.00118 U	0.000385 U	0.000342 U	0.000297 U	0.000402 U	0.000298 U	0.000268 U	0.000232 U	0.000254 U	0.000313 U
	MW-158A-80	04/06/18	PES	ESC	80	-38.9	S	0.000318 U	0.000430 U	0.000234 U	0.00116 U	0.000380 U	0.000338 U	0.000294 U	0.000397 U	0.000295 U	0.000265 U	0.000230 U	0.000251 U	0.000309 U
	MW-158A-90	04/06/18	PES	ESC	90	-48.9	S	0.000329 U	0.000445 U	0.000242 U	0.00120 U	0.000394 U	0.000350 U	0.000304 U	0.000411 U	0.000305 U	0.000274 U	0.000237 U	0.000259 U	0.000320 U
	MW-158A-100	04/06/18	PES	ESC	100	-58.9	S	0.000337 U	0.000456 U	0.000248 U	0.00123 U	0.000403 U	0.000358 U	0.000311 U	0.000421 U	0.000313 U	0.000281 U	0.000243 U	0.000266 U	0.000328 U
MW-159	MW-159-20	04/16/18	PES	ESC	20	22.8	S	0.000347 U	0.000469 U	0.000255 U	0.00127 U	0.000415 U	0.000369 U	0.000320 U	0.000433 U	0.000322 U	0.000289 U	0.000250 U	0.000273 U	0.000337 U
(22.9 to 12.9)	MW-159-30	04/16/18	PES	ESC	30	12.8	S	0.000350 U	0.000473 U	0.000257 U	0.00128 U	0.000418 U	0.000372 U	0.000323 U	0.000436 U	0.000324 U	0.000291 U	0.000252 U	0.000275 U	0.000340 U
MW-160	MW-160-11	05/08/18	PES	ESC	11	31.5	S	0.00187 U	0.00783 U	0.00188 U	0.00827 U	0.000852 U	0.00236 U	0.000771 U	0.00206 U	0.00175 U	0.00276 U	0.00284 U	0.00319 U	0.00129 U
(-76.5 to -86.5)	MW-160-21	05/08/18	PES	ESC	21	21.5	S	0.00135 U	0.00565 U	0.00136 U	0.00598 U	0.000615 U	0.00170 U	0.000557 U	0.00149 U	0.00127 U	0.00199 U	0.00205 U	0.00231 U	0.000930 U
	MW-160-31	05/08/18	PES	ESC	31	11.5	S	0.00139 U	0.00585 U	0.00141 U	0.00619 U	0.000637 U	0.00176 U	0.000576 U	0.00154 U	0.00131 U	0.00206 U	0.00212 U	0.00239 U	0.000962 U
	MW-160-40	05/08/18	PES	ESC	40	2.5	S	0.00131 U	0.00547 U	0.00132 U	0.00579 U	0.000596 U	0.00165 U	0.000539 U	0.00144 U	0.00123 U	0.00193 U	0.00199 U	0.00224 U	0.000900 U
	MW-160-50	05/08/18	PES	ESC	50	-7.5	S	0.00131 U	0.00551 U	0.00133 U	0.00583 U	0.000600 U	0.00166 U	0.000543 U	0.00145 U	0.00123 U	0.00194 U	0.00200 U	0.00225 U	0.000906 U
	MW-160-55	05/08/18	PES	ESC	55	-12.5	S	0.00136 U	0.00572 U	0.00138 U	0.00605 U	0.000623 U	0.00172 U	0.000563 U	0.00151 U	0.00128 U	0.00202 U	0.00208 U	0.00234 U	0.000941 U
	MW-160-60	05/08/18	PES	ESC	60	-17.5	S	0.00125 U	0.00525 U	**0.00138 J**	0.00556 U	0.000572 U	0.00158 U	0.000518 U	0.00138 U	0.00118 U	0.00185 U	0.00191 U	0.00215 U	0.000864 U
	MW-160-70	05/08/18	PES	ESC	70	-27.5	S	0.00134 U	0.00563 U	0.00136 U	0.00596 U	0.000613 U	0.00169 U	0.000555 U	0.00148 U	0.00126 U	0.00199 U	0.00204 U	0.00230 U	0.000926 U
	MW-160-90	05/08/18	PES	ESC	90	-47.5	S	0.00135 U	0.00567 U	0.00137 U	0.00600 U	0.000618 U	0.00171 U	0.000559 U	0.00149 U	0.00127 U	0.00200 U	0.00206 U	0.00232 U	0.000933 U
	MW-160-100	05/08/18	PES	ESC	100	-57.5	S	0.00138 U	0.00580 U	0.00140 U	0.00614 U	0.000632 U	0.00174 U	0.000571 U	0.00153 U	0.00130 U	0.00205 U	0.00211 U	0.00237 U	0.000954 U
	MW-160-110	05/08/18	PES	ESC	110	-67.5	S	0.00130 U	0.00547 U	0.00132 U	0.00578 U	0.000595 U	0.00164 U	0.000539 U	0.00144 U	0.00122 U	0.00193 U	0.00198 U	0.00223 U	0.000899 U
	MW-160-125	05/10/18	PES	ESC	125	-82.5	S	0.00132 U	0.00552 U	0.00133 U	0.00584 U	0.000601 U	0.00166 U	0.000544 U	0.00145 U	0.00124 U	0.00195 U	0.00200 U	0.00226 U	0.000908 U
	MW-160-127.5	05/10/18	PES	ESC	128	-85.0	S	0.00133 U	0.00557 U	0.00134 U	0.00589 U	0.000606 U	0.00167 U	0.000549 U	0.00147 U	0.00125 U	0.00196 U	0.00202 U	0.00227 U	0.000916 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
MW-161	MW-161-11	05/14/18	PES	ESC	11	32.8	S	0.00141 U	0.00593 U	0.00143 U	0.00627 U	0.000645 U	0.00178 U	0.000584 U	0.00156 U	0.00133 U	0.00209 U	0.00215 U	0.00242 U	0.000975 U
(-78.9 to -88.9)	MW-161-21	05/14/18	PES	ESC	21	22.8	S	0.00120 U	0.00501 U	0.00121 U	0.00530 U	0.000546 U	0.00151 U	0.000494 U	0.00132 U	0.00112 U	0.00177 U	0.00182 U	0.00205 U	0.000824 U
	MW-161-31	05/14/18	PES	ESC	31	12.8	S	0.00132 U	0.00552 U	0.00133 U	0.00584 U	0.000601 U	0.00166 U	0.000544 U	0.00145 U	0.00124 U	0.00195 U	0.00200 U	0.00226 U	0.000908 U
	MW-161-40	05/14/18	PES	ESC	40	3.8	S	0.00127 U	0.00532 U	0.00128 U	0.00563 U	0.000579 U	0.00160 U	0.000524 U	0.00140 U	0.00119 U	0.00188 U	0.00193 U	0.00217 U	0.000875 U
	MW-161-50	05/14/18	PES	ESC	50	-6.2	S	0.00128 U	0.00538 U	0.00129 U	0.00569 U	0.000586 U	0.00162 U	0.000530 U	0.00142 U	0.00121 U	0.00190 U	0.00195 U	0.00220 U	0.000885 U
	MW-161-60	05/14/18	PES	ESC	60	-16.2	S	0.00131 U	0.00551 U	0.00132 U	0.00583 U	0.000600 U	0.00166 U	0.000543 U	0.00145 U	0.00123 U	0.00194 U	0.00200 U	0.00225 U	0.000906 U
	MW-161-70	05/14/18	PES	ESC	70	-26.2	S	0.00128 U	0.00538 U	0.00130 U	0.00570 U	0.000586 U	0.00162 U	0.000531 U	0.00142 U	0.00121 U	0.00190 U	0.00195 U	0.00220 U	0.000886 U
	MW-161-80	05/14/18	PES	ESC	80	-36.2	S	0.00142 U	0.00594 U	0.00143 U	0.00629 U	0.000647 U	0.00179 U	0.000585 U	0.00157 U	0.00133 U	0.00210 U	0.00216 U	0.00243 U	0.000977 U
	MW-161-90	05/14/18	PES	ESC	90	-46.2	S	0.00131 U	0.00549 U	0.00132 U	0.00580 U	0.000597 U	0.00165 U	0.000541 U	0.00145 U	0.00123 U	0.00193 U	0.00199 U	0.00224 U	0.000902 U
	B-927-30	05/14/18	PES	ESC	90 (dup)	-46.2	S	0.00143 U	0.00599 U	0.00144 U	0.00633 U	0.000652 U	0.00180 U	0.000590 U	0.00158 U	0.00134 U	0.00211 U	0.00217 U	0.00245 U	0.000985 U
	MW-161-100	05/14/18	PES	ESC	100	-56.2	S	0.00134 U	0.00561 U	0.00135 U	0.00594 U	0.000611 U	0.00169 U	0.000553 U	0.00148 U	0.00126 U	0.00198 U	0.00204 U	0.00229 U	0.000923 U
	MW-161-110	05/14/18	PES	ESC	110	-66.2	S	0.00140 U	0.00588 U	0.00142 U	0.00622 U	0.000640 U	0.00177 U	0.000579 U	0.00155 U	0.00132 U	0.00207 U	0.00213 U	0.00240 U	0.000967 U
	MW-161-120	05/14/18	PES	ESC	120	-76.2	S	0.00140 U	0.00588 U	0.00142 U	0.00622 U	0.000641 U	0.00177 U	0.000580 U	0.00155 U	0.00132 U	0.00207 U	0.00214 U	0.00240 U	0.000968 U
	MW-161-130	05/14/18	PES	ESC	130	-86.2	S	0.00126 U	0.00530 U	0.00128 U	0.00561 U	0.000577 U	0.00159 U	0.000522 U	0.00140 U	0.00119 U	0.00187 U	0.00192 U	0.00217 U	0.000872 U
	MW-161-140	05/15/18	PES	ESC	140	-96.2	S	0.00141 U	0.00591 U	0.00142 U	0.00625 U	0.000644 U	0.00178 U	0.000582 U	0.00156 U	0.00132 U	0.00208 U	0.00215 U	0.00241 U	0.000972 U
MW-190	MW-190-5	09/19/19	PES	PACE	5	43.7	V	**0.00141 J**	0.00556 U	**0.00259 J**	0.00588 U	0.000606 U	0.00167 U	0.000548 U	0.00146 U	0.00125 U	0.00196 U	0.00202 U	0.00227 U	0.000915 U
(-30.2 to -40.2)	MW-190-10	09/19/19	PES	PACE	10	38.7	V	**0.00715 J**	0.00997 U	**0.0112**	0.0105 U	0.00108 U	0.00299 U	0.000983 U	0.00262 U	**0.00380 J**	0.00352 U	0.00363 U	0.00407 U	0.00164 U
	MW-190-15	09/19/19	PES	PACE	15	33.7	S	0.00152 U	0.00638 U	0.00154 U	0.00675 U	0.000695 U	0.00192 U	0.000629 U	0.00168 U	0.00143 U	0.00225 U	0.00232 U	0.00261 U	0.00105 U
	MW-190-20	09/19/19	PES	PACE	20	28.7	S	0.00143 U	0.00600 U	**0.00153 J**	0.00635 U	0.000653 U	0.00180 U	0.000591 U	0.00158 U	0.00134 U	0.00212 U	0.00218 U	0.00245 U	0.000987 U
	MW-190-25	09/19/19	PES	PACE	25	23.7	S	0.00135 U	0.00566 U	0.00136 U	0.00599 U	0.000616 U	0.00170 U	0.000558 U	0.00149 U	0.00127 U	0.00200 U	0.00205 U	0.00231 U	0.000931 U
	MW-190-30	09/19/19	PES	PACE	30	18.7	S	0.00120 U	0.00505 U	0.00122 U	0.00534 U	0.000550 U	0.00152 U	0.000498 U	0.00133 U	0.00113 U	0.00178 U	0.00183 U	0.00206 U	0.000831 U
	MW-190-35	09/19/19	PES	PACE	35	13.7	S	0.00122 U	0.00512 U	0.00123 U	0.00542 U	0.000558 U	0.00154 U	0.000505 U	0.00135 U	0.00115 U	0.00181 U	0.00186 U	0.00209 U	0.000842 U
	MW-190-40	09/19/19	PES	PACE	40	8.7	S	0.00129 U	0.00541 U	0.00130 U	0.00572 U	0.000589 U	0.00163 U	0.000533 U	0.00143 U	0.00121 U	0.00191 U	0.00196 U	0.00221 U	0.000890 U
	MW-190-45	09/19/19	PES	PACE	45	3.7	S	0.00131 U	0.00551 U	0.00133 U	0.00583 U	0.000600 U	0.00166 U	0.000543 U	0.00145 U	0.00123 U	0.00194 U	0.00200 U	0.00225 U	0.000907 U
	MW-190-50	09/19/19	PES	PACE	50	-1.4	S	0.00120 U	0.00505 U	0.00122 U	0.00534 U	0.000550 U	0.00152 U	0.000498 U	0.00133 U	0.00113 U	0.00178 U	0.00183 U	0.00206 U	0.000831 U
	MW-190-55	09/19/19	PES	PACE	55	-6.4	S	0.00125 U	0.00523 U	0.00126 U	0.00553 U	0.000569 U	0.00157 U	0.000515 U	0.00138 U	0.00117 U	0.00184 U	0.00190 U	0.00214 U	0.000860 U
	MW-190-60	09/19/19	PES	PACE	60	-11.4	S	0.00125 U	0.00525 U	0.00126 U	0.00556 U	0.000572 U	0.00158 U	0.000518 U	0.00138 U	0.00118 U	0.00185 U	0.00191 U	0.00215 U	0.000864 U
	MW-2008-60	09/19/19	PES	PACE	60 (dup)	-11.4	S	0.00124 U	0.00521 U	0.00125 U	0.00551 U	0.000567 U	0.00157 U	0.000513 U	0.00137 U	0.00117 U	0.00184 U	0.00189 U	0.00213 U	0.000857 U
	MW-190-65	09/19/19	PES	PACE	65	-16.4	S	0.00127 U	0.00532 U	**0.00140 J**	0.00563 U	0.000580 U	0.00160 U	0.000525 U	0.00140 U	0.00119 U	0.00188 U	0.00193 U	0.00218 U	0.000876 U
	MW-190-70	09/19/19	PES	PACE	70	-21.4	S	0.00127 U	0.00534 U	0.00128 U	0.00565 U	0.000582 U	0.00161 U	0.000526 U	0.00141 U	0.00120 U	0.00188 U	0.00194 U	0.00218 U	0.000878 U
	MW-190-75	09/19/19	PES	PACE	75	-26.4	S	0.00126 U	0.00527 U	0.00127 U	0.00558 U	0.000574 U	0.00159 U	0.000519 U	0.00139 U	0.00118 U	0.00186 U	0.00191 U	0.00215 U	0.000867 U
	MW-190-80	09/19/19	PES	PACE	80	-31.4	S	0.00126 U	0.00526 U	0.00127 U	0.00557 U	0.000573 U	0.00158 U	0.000519 U	0.00139 U	0.00118 U	0.00186 U	0.00191 U	0.00215 U	0.000866 U
	MW-190-85	09/19/19	PES	PACE	85	-36.4	S	0.00132 U	0.00554 U	0.00133 U	0.00586 U	0.000604 U	0.00167 U	0.000546 U	0.00146 U	0.00124 U	0.00195 U	0.00201 U	0.00226 U	0.000912 U
	MW-190-87	09/19/19	PES	PACE	87	-38.4	S	0.00137 U	0.00576 U	0.00139 U	0.00609 U	0.000627 U	0.00173 U	0.000568 U	0.00152 U	0.00129 U	0.00203 U	0.00209 U	0.00235 U	0.000948 U
MW-301	MW-301-6	09/20/19	PES	PACE	6	47.8	V	0.00135 U	0.00565 U	**0.00137 J**	0.00598 U	0.000615 U	0.00170 U	0.000557 U	0.00149 U	0.00127 U	0.00199 U	0.00205 U	0.00231 U	0.000929 U
(35.6 to 25.6)	MW-301-10	09/20/19	PES	PACE	10	43.8	V	0.00126 U	0.00530 U	0.00128 U	0.00561 U	0.000577 U	0.00159 U	0.000522 U	0.00140 U	0.00119 U	0.00187 U	0.00192 U	0.00217 U	0.000872 U
	MW-301-15	09/20/19	PES	PACE	15	38.8	V	0.00131 U	0.00547 U	0.00132 U	0.00579 U	0.000596 U	0.00165 U	0.000539 U	0.00144 U	0.00123 U	0.00193 U	0.00199 U	0.00224 U	0.000900 U
	MW-301-20	09/20/19	PES	PACE	20	33.8	S	0.00388 U	0.0163 U	0.00392 U	0.0172 U	0.00177 U	0.00490 U	0.00161 U	0.00429 U	0.00364 U	0.00574 U	0.00592 U	0.00666 U	0.00268 U
	MW-301-25	09/20/19	PES	PACE	25	28.8	S	0.00131 U	0.00548 U	0.00132 U	0.00580 U	0.000597 U	0.00165 U	0.000540 U	0.00144 U	0.00123 U	0.00193 U	0.00199 U	0.00224 U	0.000901 U
	MW-301-30	09/20/19	PES	PACE	30	23.8	S	0.00142 U	0.00597 U	0.00144 U	0.00631 U	0.000650 U	0.00179 U	0.000588 U	0.00157 U	0.00133 U	0.00210 U	0.00216 U	0.00243 U	0.000982 U
MW-302	MW-302-5	10/01/19	PES	PACE	5	52.3	V	**0.00296 J**	0.00564 U	**0.00427 J**	0.00597 U	0.000615 U	0.00170 U	0.000556 U	0.00149 U	0.00126 U	0.00199 U	0.00205 U	0.00231 U	0.000929 U
(3.0 to -7.0)	MW-302-10	10/01/19	PES	PACE	10	47.3	V	0.00143 U	0.00600 U	0.00144 U	0.00635 U	0.000653 U	0.00180 U	0.000591 U	0.00158 U	0.00134 U	0.00212 U	0.00218 U	0.00245 U	0.000987 U
	MW-302-15	10/01/19	PES	PACE	15	42.3	V	0.00156 U	0.00657 U	0.00159 U	0.00696 U	0.000716 U	0.00198 U	0.000648 U	0.00173 U	0.00147 U	0.00232 U	0.00239 U	0.00269 U	0.00108 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
MW-302 (continued)	MW-302-20	10/01/19	PES	PACE	20	37.3	S	0.00137 U	0.00575 U	0.00138 U	0.00609 U	0.000627 U	0.00173 U	0.000567 U	0.00152 U	0.00129 U	0.00203 U	0.00209 U	0.00235 U	0.000946 U
	MW-302-25	10/01/19	PES	PACE	25	32.3	S	0.00129 U	0.00540 U	0.00130 U	0.00572 U	0.000588 U	0.00163 U	0.000532 U	0.00142 U	0.00121 U	0.00191 U	0.00196 U	0.00221 U	0.000889 U
	MW-302-30	10/01/19	PES	PACE	30	27.3	S	0.00126 U	0.00527 U	0.00127 U	0.00558 U	0.000574 U	0.00159 U	0.000520 U	0.00139 U	0.00118 U	0.00186 U	0.00191 U	0.00215 U	0.000867 U
	MW-302-35	10/01/19	PES	PACE	35	22.3	S	0.00124 U	0.00518 U	0.00125 U	0.00548 U	0.000564 U	0.00156 U	0.000511 U	0.00136 U	0.00116 U	0.00183 U	0.00188 U	0.00212 U	0.000852 U
	MW-302-40	10/01/19	PES	PACE	40	17.3	S	0.00122 U	0.00513 U	0.00123 U	0.00542 U	0.000558 U	0.00154 U	0.000505 U	0.00135 U	0.00115 U	0.00181 U	0.00186 U	0.00210 U	0.000844 U
	MW-302-45	10/01/19	PES	PACE	45	12.3	S	0.00137 U	0.00574 U	0.00138 U	0.00608 U	0.000626 U	0.00173 U	0.000566 U	0.00151 U	0.00129 U	0.00203 U	0.00209 U	0.00235 U	0.000945 U
	MW-302-50	10/01/19	PES	PACE	50	7.3	S	0.00137 U	0.00576 U	0.00139 U	0.00609 U	0.000627 U	0.00173 U	0.000567 U	0.00152 U	0.00129 U	0.00203 U	0.00209 U	0.00235 U	0.000947 U
	MW-302-55	10/01/19	PES	PACE	55	2.3	S	0.00131 U	0.00548 U	0.00132 U	0.00580 U	0.000597 U	0.00165 U	0.000540 U	0.00144 U	0.00123 U	0.00193 U	0.00199 U	0.00224 U	0.000901 U
	MW-302-60	10/01/19	PES	PACE	60	-2.7	S	0.00163 U	0.00685 U	**0.00188 J**	0.00725 U	0.000746 U	0.00206 U	0.000675 U	0.00180 U	**0.00156 J**	0.00242 U	0.00249 U	0.00280 U	0.00113 U
	MW-302-65	10/01/19	PES	PACE	65	-7.7	S	0.00135 U	0.00564 U	0.00136 U	0.00597 U	0.000615 U	0.00170 U	0.000556 U	0.00149 U	0.00126 U	0.00199 U	0.00205 U	0.00231 U	0.000929 U
	MW-2014-65	10/01/19	PES	PACE	65 (dup)	-7.7	S	0.00139 U	0.00584 UJ	0.00141 U	0.00618 U	0.000636 U	0.00176 U	0.000576 U	0.00154 U	0.00131 U	0.00206 U	0.00212 U	0.00239 U	0.000961 U
MW-304 (-47.6 to -57.6)	MW-304-5	10/01/19	PES	PACE	5	52.6	V	0.00130 U	**0.0199**	0.00131 U	0.00574 U	0.000591 U	0.00163 U	0.000535 U	0.00143 U	0.00122 U	0.00191 U	0.00197 U	0.00222 U	0.000893 U
	MW-304-10	10/01/19	PES	PACE	10	47.6	V	0.00131 U	0.00549 U	0.00132 U	0.00581 U	0.000598 U	0.00165 U	0.000541 U	0.00145 U	0.00123 U	0.00194 U	0.00199 U	0.00224 U	0.000904 U
	MW-304-15	10/01/19	PES	PACE	15	42.6	V	0.00137 U	0.00573 U	0.00138 U	0.00606 U	0.000624 U	0.00172 U	0.000565 U	0.00151 U	0.00128 U	0.00202 U	0.00208 U	0.00234 U	0.000943 U
	MW-304-20	10/01/19	PES	PACE	20	37.6	S	0.00135 U	0.00568 U	0.00137 U	0.00601 U	0.000618 U	0.00171 U	0.000559 U	0.00150 U	0.00127 U	0.00200 U	0.00206 U	0.00232 U	0.000934 U
	MW-304-25	10/01/19	PES	PACE	25	32.6	S	0.00126 U	0.00527 U	0.00127 U	0.00558 U	0.000574 U	0.00159 U	0.000520 U	0.00139 U	0.00118 U	0.00186 U	0.00191 U	0.00215 U	0.000867 U
	MW-304-30	10/01/19	PES	PACE	30	27.6	S	0.00135 U	0.00567 U	0.00136 U	0.00600 U	0.000618 U	0.00171 U	0.000559 U	0.00149 U	0.00127 U	0.00200 U	0.00206 U	0.00232 U	0.000933 U
	MW-304-40	10/01/19	PES	PACE	40	17.6	S	0.00125 U	0.00523 U	0.00126 U	0.00553 U	0.000570 U	0.00157 U	0.000515 U	0.00138 U	0.00117 U	0.00184 U	0.00190 U	0.00214 U	0.000861 U
	MW-304-45	10/01/19	PES	PACE	45	12.6	S	0.00117 U	0.00490 U	0.00118 U	0.00518 U	0.000533 U	0.00147 U	0.000483 U	0.00129 U	0.00110 U	0.00173 U	0.00178 U	0.00200 U	0.000806 U
	MW-304-50	10/01/19	PES	PACE	50	7.6	S	0.00124 U	0.00519 U	0.00125 U	0.00549 U	0.000565 U	0.00156 U	0.000511 U	0.00137 U	0.00116 U	0.00183 U	0.00188 U	0.00212 U	0.000854 U
	MW-304-55	10/01/19	PES	PACE	55	2.6	S	0.00116 U	0.00486 U	0.00117 U	0.00514 U	0.000529 U	0.00146 U	0.000479 U	0.00128 U	0.00109 U	0.00171 U	0.00176 U	0.00199 U	0.000799 U
	MW-304-60	10/01/19	PES	PACE	60	-2.4	S	0.00121 U	0.00508 U	0.00122 U	0.00538 U	0.000554 U	0.00153 U	0.000501 U	0.00134 U	0.00114 U	0.00179 U	0.00185 U	0.00208 U	0.000836 U
	MW-304-65	10/01/19	PES	PACE	65	-7.4	S	0.00133 U	0.00558 U	0.00134 U	0.00591 U	0.000608 U	0.00168 U	0.000550 U	0.00147 U	0.00125 U	0.00197 U	0.00203 U	0.00228 U	0.000918 U
	MW-304-70	10/01/19	PES	PACE	70	-12.4	S	0.00140 U	0.00586 U	0.00141 U	0.00620 U	0.000638 U	0.00176 U	0.000577 U	0.00154 U	0.00131 U	0.00207 U	0.00213 U	0.00239 U	0.000963 U
	MW-304-75	10/01/19	PES	PACE	75	-17.4	S	0.00132 U	0.00552 U	0.00133 U	0.00584 U	0.000601 U	0.00166 U	0.000544 U	0.00145 U	0.00124 U	0.00195 U	0.00200 U	0.00226 U	0.000908 U
	MW-304-80	10/01/19	PES	PACE	80	-22.4	S	0.00126 U	0.00528 U	0.00127 U	0.00558 U	0.000575 U	0.00159 U	0.000520 U	0.00139 U	0.00118 U	0.00186 U	0.00192 U	0.00216 U	0.000868 U
	MW-304-85	10/01/19	PES	PACE	85	-27.4	S	0.00126 U	0.00528 U	0.00127 U	0.00559 U	0.000575 U	0.00159 U	0.000520 U	0.00139 U	0.00118 U	0.00186 U	0.00192 U	0.00216 U	0.000869 U
	MW-304-90	10/01/19	PES	PACE	90	-32.4	S	0.00138 U	0.00578 U	0.00139 U	0.00611 U	0.000629 U	0.00174 U	0.000570 U	0.00152 U	0.00129 U	0.00204 U	0.00210 U	0.00236 U	0.000951 U
	MW-304-95	10/01/19	PES	PACE	95	-37.4	S	0.00136 U	0.00571 U	0.00137 U	0.00604 U	0.000622 U	0.00172 U	0.000563 U	0.00150 U	0.00128 U	0.00201 U	0.00207 U	0.00233 U	0.000940 U
	MW-2009-95	10/01/19	PES	PACE	95 (dup)	-37.4	S	0.00138 U	0.00579 U	0.00139 U	0.00613 U	0.000631 U	0.00174 U	0.000571 U	0.00153 U	0.00130 U	0.00204 U	0.00210 U	0.00237 U	0.000953 U
	MW-304-100	10/02/19	PES	PACE	100	-42.4	S	0.00136 U	0.00568 U	0.00137 U	0.00601 U	0.000619 U	0.00171 U	0.000560 U	0.00150 U	0.00127 U	0.00200 U	0.00206 U	0.00232 U	0.000935 U
	MW-304-105	10/02/19	PES	PACE	105	-47.4	S	0.00135 U	0.00564 U	0.00136 U	0.00597 U	0.000614 U	0.00170 U	0.000556 U	0.00149 U	0.00126 U	0.00199 U	0.00205 U	0.00231 U	0.000928 U
	MW-304-110	10/02/19	PES	PACE	110	-52.4	S	0.00145 U	0.00609 U	0.00147 U	0.00645 U	0.000664 U	0.00183 U	0.000601 U	0.00161 U	0.00137 U	0.00215 U	0.00221 U	0.00249 U	0.00100 UJ
	MW-304-115	10/02/19	PES	PACE	115	-57.4	S	0.00134 U	0.00562 U	0.00135 U	0.00594 U	0.000612 U	0.00169 U	0.000553 U	0.00148 U	0.00126 U	0.00198 U	0.00204 U	0.00230 U	0.000924 U
MW-307 (-12.4 to -22.4)	MW-307-6	10/03/19	PES	PACE	6	54.5	V	0.00129 U	0.00539 U	0.00130 U	0.00570 U	0.000587 U	0.00162 U	0.000531 U	0.00142 U	0.00121 U	0.00190 U	0.00196 U	0.00220 U	0.000887 U
	MW-307-10	10/03/19	PES	PACE	10	50.5	V	0.00132 U	0.00555 U	0.00134 U	0.00588 U	0.000604 U	0.00167 U	0.000547 U	0.00147 U	0.00124 U	0.00195 U	0.00202 U	0.00227 U	0.000913 U
	MW-307-15	10/03/19	PES	PACE	15	45.5	V	0.00124 U	0.00519 U	0.00125 U	0.00549 U	0.000566 U	0.00156 U	0.000512 U	0.00137 U	0.00116 U	0.00183 U	0.00189 U	0.00212 U	0.000854 U
	MW-307-20	10/03/19	PES	PACE	20	40.5	V	0.00123 U	0.00515 U	0.00124 U	0.00545 U	0.000561 U	0.00155 U	0.000508 U	0.00136 U	0.00115 U	0.00182 U	0.00187 U	0.00211 U	0.000848 U
	MW-307-25	10/03/19	PES	PACE	25	35.5	S	0.00126 U	0.00529 U	0.00127 U	0.00559 U	0.000576 U	0.00159 U	0.000521 U	0.00139 U	0.00118 U	0.00186 U	0.00192 U	0.00216 U	0.000870 U
	MW-307-30	10/03/19	PES	PACE	30	30.5	S	0.00170 U	0.00710 U	0.00171 U	0.00751 U	0.000773 U	0.00214 U	0.000700 U	0.00187 U	0.00160 U	0.00250 U	0.00258 U	0.00290 U	0.00116 U
	MW-307-35	10/03/19	PES	PACE	35	25.5	S	0.00123 U	0.00516 U	0.00124 U	0.00546 U	0.000562 U	0.00155 U	0.000508 U	0.00136 U	0.00116 U	0.00182 U	0.00187 U	0.00211 U	0.000849 U
	MW-307-40	10/03/19	PES	PACE	40	20.5	S	0.00131 U	0.00550 U	0.00132 U	0.00582 U	0.000599 U	0.00166 U	0.000542 U	0.00145 U	0.00123 U	0.00194 U	0.00200 U	0.00225 U	0.000905 U
	MW-307-45	10/03/19	PES	PACE	45	15.5	S	0.00127 U	0.00532 U	0.00128 U	0.00563 U	0.000579 U	0.00160 U	0.000524 U	0.00140 U	0.00119 U	0.00188 U	0.00193 U	0.00217 U	0.000875 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
MW-307 (continued)	MW-307-50	10/03/19	PES	PACE	50	10.5	S	0.00128 U	0.00536 U	0.00129 U	0.00567 U	0.000584 U	0.00161 U	0.000528 U	0.00141 U	0.00120 U	0.00189 U	0.00195 U	0.00219 U	0.000882 U
	MW-307-55	10/03/19	PES	PACE	55	5.5	S	0.00125 U	0.00523 U	0.00126 U	0.00554 U	0.000570 U	0.00157 U	0.000516 U	0.00138 U	0.00117 U	0.00185 U	0.00190 U	0.00214 U	0.000861 U
	MW-307-60	10/03/19	PES	PACE	60	0.5	S	0.00130 U	0.00544 U	**0.00217 J**	0.00576 U	0.000593 U	0.00164 U	0.000536 U	0.00143 U	0.00122 U	0.00192 U	0.00198 U	0.00222 U	0.000896 U
	MW-307-65	10/03/19	PES	PACE	65	-4.5	S	0.00265 U	0.0111 U	**0.00355 J**	0.0117 U	0.00120 U	0.00333 U	0.00110 U	0.00293 U	0.00248 U	0.00392 U	0.00403 U	0.00454 U	0.00183 U
	MW-307-70	10/03/19	PES	PACE	70	-9.5	S	0.0132 U	0.0552 U	0.0133 U	0.0584 U	0.00601 U	0.0166 U	0.00544 U	0.0145 U	0.0123 U	0.0195 U	0.0200 U	0.0226 U	0.00909 U
	MW-307-75	10/03/19	PES	PACE	75	-14.5	S	0.00127 U	0.00532 U	0.00128 U	0.00562 U	0.000579 U	0.00160 U	0.000524 U	0.00140 U	0.00119 U	0.00187 U	0.00193 U	0.00217 U	0.000875 U
	MW-307-80	10/03/19	PES	PACE	80	-19.5	S	0.00134 U	0.00563 U	**0.00186 J**	0.00596 U	0.000614 U	0.00169 U	0.000555 U	0.00149 U	0.00126 U	0.00199 U	0.00204 U	0.00230 U	0.000927 U
	MW-307-85	10/03/19	PES	PACE	85	-24.5	S	0.00132 U	0.00552 U	**0.00182 J**	0.00584 U	0.000601 U	0.00166 U	0.000544 U	0.00145 U	0.00124 U	0.00195 U	0.00200 U	0.00226 U	0.000908 U
	MW-2016-85	10/03/19	PES	PACE	85 (dup)	-24.5	S	0.00124 U	0.00521 U	**0.00144 J**	0.00551 U	0.000567 U	0.00157 U	0.000513 U	0.00137 U	0.00117 U	0.00184 U	0.00189 U	0.00213 U	0.000857 U
MW-309 (-32.0 to -42.0)	MW-309-5	09/19/19	PES	PACE	5	25.4	V	**0.00159 J**	0.00575 U	**0.00362 J**	0.00609 U	0.000626 U	0.00173 U	0.000567 U	0.00152 U	**0.00143 J**	0.00203 U	0.00209 U	0.00235 U	0.000946 U
	MW-309-10	09/19/19	PES	PACE	10	20.4	S	**0.152 J**	0.304 U	**0.159 J**	0.321 U	0.0330 U	0.0912 U	0.0299 U	0.0799 U	0.0680 U	0.107 U	0.110 U	0.124 U	0.0499 U
	MW-309-13.5	09/19/19	PES	PACE	13.5	16.9	S	**0.0105**	0.00589 U	**0.00365 J**	0.00623 U	0.000641 U	0.00177 U	0.000580 U	0.00155 U	**0.00291 J**	0.00208 U	0.00214 U	0.00241 U	0.000969 U
	MW-309-15	09/19/19	PES	PACE	15	15.4	S	**0.130**	0.0454 U	**0.0333 J**	0.0480 U	0.00494 U	0.0137 U	0.00447 U	0.0120 U	**0.0458 J**	0.0160 U	0.0165 U	0.0186 U	0.00746 U
	MW-309-20	09/19/19	PES	PACE	20	10.4	S	**0.103**	0.00567 U	**0.0140**	0.00600 U	0.000618 U	0.00171 U	0.000559 U	0.00149 U	**0.0260**	0.00200 U	0.00206 U	0.00232 U	0.000933 U
	MW-309-25	09/19/19	PES	PACE	25	5.4	S	**0.0537**	0.00569 U	**0.0103**	0.00603 U	0.000620 U	0.00171 U	0.000561 U	0.00150 U	**0.0129**	0.00201 U	0.00207 U	0.00233 U	0.000937 U
	MW-309-30	09/19/19	PES	PACE	30	0.4	S	**0.00494 J**	0.00576 U	**0.00456 J**	0.00609 U	0.000627 U	0.00173 U	0.000567 U	0.00152 U	**0.00379 J**	0.00203 U	0.00209 U	0.00235 U	0.000947 U
	MW-309-35	09/19/19	PES	PACE	35	-4.6	S	0.00139 U	0.00584 U	0.00141 U	0.00618 U	0.000636 U	0.00176 U	0.000576 U	0.00154 U	0.00131 U	0.00206 U	0.00212 U	0.00239 U	0.000961 U
	MW-309-40	09/19/19	PES	PACE	40	-9.6	S	0.00139 U	0.00584 U	0.00141 U	0.00618 U	0.000637 U	0.00176 U	0.000576 U	0.00154 U	0.00131 U	0.00206 U	0.00212 U	0.00239 U	0.000962 U
	MW-309-45	09/19/19	PES	PACE	45	-14.6	S	0.00145 U	0.00608 U	0.00146 U	0.00643 U	0.000662 U	0.00183 U	**0.0128**	**0.00537 J**	0.00136 U	0.00214 U	0.00221 U	0.00248 U	0.00100 U
	MW-309-50	09/19/19	PES	PACE	50	-19.6	S	0.00137 U	0.00574 U	0.00138 U	0.00608 U	0.000626 U	0.00173 U	0.000566 U	0.00151 U	0.00129 U	0.00203 U	0.00209 U	0.00235 U	0.000945 U
	MW-309-55	09/19/19	PES	PACE	55	-24.6	S	0.00128 U	0.00535 U	0.00129 U	0.00566 U	0.000583 U	0.00161 U	0.000527 U	0.00141 U	0.00120 U	0.00189 U	0.00194 U	0.00219 U	0.000880 U
	MW-309-60	09/19/19	PES	PACE	60	-29.6	S	0.00129 U	0.00538 U	0.00130 U	0.00569 U	0.000587 U	0.00162 U	0.000531 U	0.00142 U	0.00120 U	0.00190 U	0.00196 U	0.00220 U	0.000886 U
	MW-309-65	09/19/19	PES	PACE	65	-34.6	S	0.00129 U	0.00541 U	0.00130 U	0.00573 U	0.000590 U	0.00163 U	0.000534 U	0.00143 U	0.00121 U	0.00191 U	0.00197 U	0.00221 U	0.000891 U
	MW-309-70	09/19/19	PES	PACE	70	-39.6	S	0.00131 U	0.00548 U	0.00132 U	0.00580 U	0.000597 U	0.00165 U	0.000540 U	0.00144 U	0.00123 U	0.00193 U	0.00199 U	0.00224 U	0.000902 U
	MW-309-75	09/19/19	PES	PACE	75	-44.6	S	0.00124 U	0.00521 U	0.00125 U	0.00551 U	0.000567 U	0.00157 U	0.000513 U	0.00137 U	0.00117 U	0.00184 U	0.00189 U	0.00213 U	0.000857 U
MW-311 (-29.0 to -39.0)	MW-311-5	09/18/19	PES	PACE	5	28.1	V	**0.00172 J**	0.00577 U	0.00139 U	0.00610 UJ	0.000628 U	0.00174 U	0.000569 U	0.00152 U	0.00129 U	0.00203 U	0.00209 U	0.00236 U	0.000949 U
	MW-311-10	09/18/19	PES	PACE	10	23.1	S	0.00132 U	0.00555 U	0.00134 U	0.00587 UJ	0.000604 U	0.00167 U	0.000547 U	0.00146 U	0.00124 U	0.00196 U	0.00201 U	0.00227 U	0.000913 U
	MW-311-15	09/18/19	PES	PACE	15	18.1	S	0.00309 U	0.0129 U	0.00311 U	0.0137 UJ	0.00141 U	0.00389 U	0.00127 U	0.00341 U	0.00290 U	0.00456 U	0.00470 U	0.00529 U	0.00213 U
	MW-311-20	09/18/19	PES	PACE	20	13.1	S	0.00322 U	0.0135 U	0.00325 U	0.0143 UJ	0.00147 U	0.00406 U	0.00133 U	0.00356 U	0.00302 U	0.00476 U	0.00489 U	0.00552 U	0.00221 U
	MW-311-25	09/18/19	PES	PACE	25	8.1	S	0.00571 U	0.0240 U	0.00576 U	0.0253 UJ	0.00261 U	0.00720 U	0.00236 U	0.00631 U	0.00536 U	0.00844 U	0.00869 U	0.00979 U	0.00394 U
	MW-311-30	09/18/19	PES	PACE	30	3.1	S	0.00302 U	0.0126 U	0.00304 U	0.0134 UJ	0.00138 U	0.00381 U	0.00125 U	0.00333 U	0.00283 U	0.00446 U	0.00459 U	0.00517 U	0.00208 U
	MW-311-35	09/18/19	PES	PACE	35	-1.9	S	0.00268 U	0.0112 U	0.00271 U	0.0119 UJ	0.00122 U	0.00338 U	0.00111 U	0.00296 U	0.00252 U	0.00397 U	0.00408 U	0.00460 U	0.00185 U
	MW-311-40	09/18/19	PES	PACE	40	-6.9	S	0.00135 U	0.00565 U	0.00136 U	0.00598 UJ	0.000615 U	0.00170 U	0.000557 U	0.00149 U	0.00127 U	0.00199 U	0.00205 U	0.00231 U	0.000929 U
	MW-311-45	09/18/19	PES	PACE	45	-11.9	S	0.00144 U	0.00605 U	0.00146 U	0.00640 UJ	0.000659 U	0.00182 U	0.000596 U	0.00159 U	0.00136 U	0.00213 U	0.00220 U	0.00247 U	0.000995 U
	MW-311-50	09/18/19	PES	PACE	50	-16.9	S	0.00134 U	0.00563 U	0.00135 U	0.00595 UJ	0.000613 U	0.00169 U	0.000555 U	0.00148 U	0.00126 U	0.00198 U	0.00204 U	0.00230 U	0.000926 U
	MW-311-55	09/18/19	PES	PACE	55	-21.9	S	0.00127 U	0.00533 U	0.00128 U	0.00564 UJ	0.000580 U	0.00160 U	0.000525 U	0.00140 U	0.00119 U	0.00188 U	0.00193 U	0.00218 U	0.000877 U
	MW-311-60	09/18/19	PES	PACE	60	-26.9	S	0.00252 U	0.0106 U	0.00254 U	0.0112 UJ	0.00115 U	0.00318 U	0.00104 U	0.00278 U	0.00237 U	0.00373 U	0.00384 U	0.00432 U	0.00174 U
	MW-311-65	09/18/19	PES	PACE	65	-31.9	S	0.00122 U	0.00511 U	0.00123 U	0.00541 UJ	0.000556 U	0.00154 U	0.000503 U	0.00135 U	0.00114 U	0.00180 U	0.00185 U	0.00209 U	0.000840 U
	MW-2005-65	09/18/19	PES	PACE	65 (dup)	-31.9	S	0.00126 U	0.00529 U	0.00127 U	0.00559 U	0.000576 U	0.00159 U	0.000521 U	0.00139 U	0.00118 U	0.00186 U	0.00192 U	0.00216 U	0.000870 U
	MW-311-70	09/18/19	PES	PACE	70	-36.9	S	0.00127 U	0.00531 U	0.00128 U	0.00562 U	0.000578 U	0.00160 U	0.000523 U	0.00140 U	0.00119 U	0.00187 U	0.00193 U	0.00217 U	0.000874 U
	MW-2007-70	09/18/19	PES	PACE	70 (dup)	-38.3	S	0.00245 U	0.0103 U	0.00247 U	0.0109 U	0.00112 U	0.00309 U	0.00101 U	0.00271 U	0.00230 U	0.00362 U	0.00373 U	0.00420 U	0.00169 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
MW-312	MW-312-6	09/16/19	PES	PACE	6	29.6	V	**0.00176 J**	0.00586 U	**0.00182 J**	0.00620 UJ	0.000639 U	0.00176 U	0.000578 U	0.00155 U	0.00131 U	0.00207 U	0.00213 U	0.00240 U	0.000965 U
(19.9 to9.9)	MW-312-10	09/16/19	PES	PACE	10	25.6	V	0.00233 U	0.00977 U	0.00235 U	0.0103 UJ	0.00106 U	0.00294 U	0.000965 U	0.00258 U	0.00219 U	0.00345 U	0.00356 U	0.00399 U	0.00161 U
	MW-312-15	09/16/19	PES	PACE	15	20.6	S	**0.00854**	**0.00710 J**	**0.00499 J**	0.00705 UJ	0.000726 U	0.00201 U	0.000657 U	0.00175 U	0.00149 U	0.00235 U	0.00242 U	0.00273 U	0.00110 U
	MW-312-20	09/16/19	PES	PACE	20	15.6	S	**0.0176**	**0.0271**	0.00126 U	0.00552 UJ	0.000568 U	0.00157 U	0.000514 U	0.00137 U	0.00117 U	0.00184 U	0.00189 U	0.00213 U	0.000858 U
	MW-2004-20	09/16/19	PES	PACE	20	15.6	S	0.00133 U	0.00557 U	0.00134 U	0.00589 UJ	0.000606 U	0.00167 U	0.000548 U	0.00147 U	0.00125 U	0.00196 U	0.00202 U	0.00227 U	0.000916 U
	MW-312-25	09/16/19	PES	PACE	25	10.6	S	**0.0132**	**0.0169**	**0.00219 J**	0.00570 UJ	0.000587 U	0.00162 U	0.000531 U	0.00142 U	0.00121 U	0.00190 U	0.00196 U	0.00220 U	0.000887 U
MW-314	MW-314-6	09/13/19	PES	PACE	6	33.8	V	**0.00365 J**	0.00548 U	**0.00465 J**	0.00579 UJ	0.000596 U	0.00165 U	0.000540 U	0.00144 U	**0.00156 J**	0.00193 U	0.00199 U	0.00224 U	0.000901 U
(-28.0 to -38.0)	MW-314-10	09/13/19	PES	PACE	10	29.8	V	0.00132 U	0.00553 U	0.00133 U	0.00586 UJ	0.000602 U	0.00167 U	0.000546 U	0.00146 U	0.00123 U	0.00195 U	0.00201 U	0.00226 U	0.000909 U
	MW-314-15	09/13/19	PES	PACE	15	24.8	V	0.00129 U	0.00542 U	0.00131 U	0.00574 UJ	0.000591 U	0.00163 U	0.000534 U	0.00143 U	0.00122 U	0.00191 U	0.00197 U	0.00222 U	0.000892 U
	MW-314-20	09/13/19	PES	PACE	20	19.8	S	0.00132 U	0.00553 U	0.00133 U	0.00585 UJ	0.000602 U	0.00166 U	0.000545 U	0.00146 U	0.00124 U	0.00195 U	0.00201 U	0.00226 U	0.000910 U
	MW-314-25	09/13/19	PES	PACE	25	14.8	S	0.00146 U	0.00612 U	0.00147 U	0.00648 UJ	0.000667 U	0.00184 U	0.000603 U	0.00161 U	0.00137 U	0.00216 U	0.00222 U	0.00250 U	0.00101 U
	MW-2002-25	09/13/19	PES	PACE	25	14.8	S	0.00145 U	0.00609 U	0.00146 U	0.00644 UJ	0.000663 U	0.00183 U	0.000600 U	0.00160 U	0.00136 U	0.00215 U	0.00221 U	0.00249 U	0.00100 U
	MW-314-30	09/13/19	PES	PACE	30	9.8	S	0.00143 U	0.00600 U	0.00144 U	0.00634 UJ	0.000653 U	0.00180 U	0.000591 U	0.00158 U	0.00134 U	0.00211 U	0.00218 U	0.00245 U	0.000986 U
	MW-314-35	09/13/19	PES	PACE	35	4.8	S	0.00123 U	0.00517 U	0.00124 U	0.00547 UJ	0.000563 U	0.00156 U	0.000510 U	0.00136 U	0.00116 U	0.00182 U	0.00188 U	0.00211 U	0.000851 U
	MW-314-40	09/13/19	PES	PACE	40	-0.2	S	0.00128 U	0.00538 U	0.00129 U	0.00569 UJ	0.000585 U	0.00161 U	0.000530 U	0.00141 U	0.00120 U	0.00190 U	0.00195 U	0.00220 U	0.000884 U
	MW-314-45	09/13/19	PES	PACE	45	-5.2	S	0.00127 U	0.00533 U	0.00128 U	0.00564 UJ	0.000581 U	0.00160 U	0.000526 U	0.00141 U	0.00120 U	0.00188 U	0.00194 U	0.00218 U	0.000878 U
	MW-314-50	09/13/19	PES	PACE	50	-10.2	S	0.00128 U	0.00537 U	0.00129 U	0.00568 UJ	0.000584 U	0.00161 U	0.000529 U	0.00141 U	0.00120 U	0.00189 U	0.00195 U	0.00219 U	0.000883 U
	MW-314-55	09/13/19	PES	PACE	55	-15.2	S	0.00139 U	0.00582 U	0.00140 U	0.00616 UJ	0.000634 U	0.00175 U	0.000574 U	0.00153 U	0.00130 U	0.00205 U	0.00211 U	0.00238 U	0.000957 U
	MW-314-60	09/13/19	PES	PACE	60	-20.2	S	0.00127 U	0.00533 U	0.00128 U	0.00564 UJ	0.000581 U	0.00160 U	0.000525 U	0.00140 U	0.00119 U	0.00188 U	0.00194 U	0.00218 U	0.000877 U
	MW-314-65	09/13/19	PES	PACE	65	-25.2	S	0.00131 U	0.00547 U	0.00132 U	0.00579 UJ	0.000596 U	0.00165 U	0.000539 U	0.00144 U	0.00123 U	0.00193 U	0.00199 U	0.00224 U	0.000900 U
	MW-314-70	09/13/19	PES	PACE	70	-30.2	S	0.0140 U	0.0585 U	0.0141 U	0.0620 UJ	0.00638 U	0.0176 U	0.00577 U	0.0154 U	0.0132 U	0.0207 U	0.0212 U	0.0239 U	0.00964 U
	MW-314-75	09/13/19	PES	PACE	75	-35.2	S	0.00263 U	0.0110 U	0.00265 U	0.0116 UJ	0.00120 U	0.00331 U	0.00108 U	0.00290 U	0.00247 U	0.00388 U	0.00400 U	0.00450 U	0.00182 U
	MW-314-80	09/13/19	PES	PACE	80	-40.2	S	0.00172 U	0.00720 U	0.00173 U	0.00761 UJ	0.000784 U	0.00216 U	0.000709 U	0.00189 U	0.00161 U	0.00253 U	0.00261 U	0.00295 U	0.00118 U
MW-316	MW-316-5	09/09/19	PES	PACE	5	44.8	V	0.00124 U	0.00522 U	0.00126 U	0.00552 U	0.000568 U	0.00157 U	0.000514 U	0.00137 U	0.00117 U	0.00184 U	0.00189 U	0.00213 U	0.000859 U
(-10.0 to -20.0)	MW-316-10	09/09/19	PES	PACE	10	39.8	V	0.00130 U	0.00545 U	0.00131 U	0.00577 U	0.000594 U	0.00164 U	0.000537 U	0.00144 U	0.00122 U	0.00192 U	0.00198 U	0.00223 U	0.000897 U
	MW-316-15	09/09/19	PES	PACE	15	34.8	V	0.00129 U	0.00542 U	0.00130 U	0.00573 U	0.000590 U	0.00163 U	0.000534 U	0.00143 U	0.00121 U	0.00191 U	0.00197 U	0.00222 U	0.000892 U
	MW-316-20	09/09/19	PES	PACE	20	29.8	V	0.00124 U	0.00520 U	0.00125 U	0.00550 U	0.000566 U	0.00156 U	0.000512 U	0.00137 U	0.00117 U	0.00183 U	0.00189 U	0.00213 U	0.000855 U
	MW-316-25	09/09/19	PES	PACE	25	24.8	S	0.00130 U	0.00547 U	0.00132 U	0.00579 U	0.000596 U	0.00165 U	0.000539 U	0.00144 U	0.00123 U	0.00193 U	0.00199 U	0.00223 U	0.000900 U
	MW-316-30	09/09/19	PES	PACE	30	19.8	S	0.00128 U	0.00535 U	0.00129 U	0.00566 U	0.000583 U	0.00161 U	0.000527 U	0.00141 U	0.00120 U	0.00189 U	0.00194 U	0.00219 U	0.000880 U
	MW-316-35	09/09/19	PES	PACE	35	14.8	S	0.00130 U	0.00544 U	0.00131 U	0.00576 U	0.000593 U	0.00164 U	0.000536 U	0.00143 U	0.00122 U	0.00192 U	0.00198 U	0.00222 U	0.000895 U
	MW-316-40	09/09/19	PES	PACE	40	9.8	S	0.00131 U	0.00549 U	0.00132 U	0.00580 U	0.000597 U	0.00165 U	0.000541 U	0.00145 U	0.00123 U	0.00193 U	0.00199 U	0.00224 U	0.000902 U
	MW-316-45	09/09/19	PES	PACE	45	4.8	S	0.00128 U	0.00536 U	0.00129 U	0.00567 U	0.000584 U	0.00161 U	0.000528 U	0.00141 U	0.00120 U	0.00189 U	0.00195 U	0.00219 U	0.000882 U
	MW-316-50	09/09/19	PES	PACE	50	-0.2	S	0.00138 U	0.00577 U	0.00139 U	0.00610 U	0.000628 U	0.00173 U	0.000568 U	0.00152 U	0.00129 U	0.00203 U	0.00209 U	0.00236 U	0.000949 U
	MW-316-55	09/09/19	PES	PACE	55	-5.2	S	0.00130 U	0.00546 U	0.00131 U	0.00578 U	0.000595 U	0.00164 U	0.000538 U	0.00144 U	0.00122 U	0.00193 U	0.00198 U	0.00223 U	0.000898 U
	MW-316-60	09/09/19	PES	PACE	60	-10.2	S	0.00129 U	0.00542 U	0.00130 U	0.00573 U	0.000590 U	0.00163 U	0.000534 U	0.00143 U	0.00121 U	0.00191 U	0.00197 U	0.00221 U	0.000892 U
	MW-316-65	09/10/19	PES	PACE	65	-15.2	S	0.00172 U	0.00721 U	0.00173 U	0.00763 U	0.000786 U	0.00217 U	0.000711 U	0.00190 U	0.00161 U	0.00254 U	0.00262 U	0.00295 U	0.00119 U
	MW-2001-65	09/10/19	PES	PACE	65	-15.2	S	0.00136 U	0.00571 U	0.00137 U	0.00604 U	0.000622 U	0.00172 U	0.000563 U	0.00150 U	0.00128 U	0.00201 U	0.00207 U	0.00233 U	0.000939 U
	MW-316-70	09/10/19	PES	PACE	70	-20.2	S	0.00130 U	0.00545 U	0.00131 U	0.00577 U	0.000594 U	0.00164 U	0.000538 U	0.00144 U	0.00122 U	0.00192 U	0.00198 U	0.00223 U	0.000897 U
MW-319	MW-319-6	09/18/19	PES	PACE	6	25.7	V	**0.00452 J**	0.00559 U	**0.00522 J**	0.00592 U	0.000609 U	0.00168 U	0.000551 U	0.00147 U	**0.00157 J**	0.00197 U	0.00203 U	0.00229 U	0.000920 U
(-42.8 to -52.8)	MW-319-10	09/18/19	PES	PACE	10	21.7	S	0.00133 U	0.00556 U	0.00134 U	0.00588 U	0.000605 U	0.00167 U	0.000548 U	0.00146 U	0.00125 U	0.00196 U	0.00202 U	0.00227 U	0.000914 U
	MW-319-15	09/18/19	PES	PACE	15	16.7	S	0.00132 U	0.00552 U	0.00133 U	0.00584 U	0.000601 U	0.00166 U	0.000544 U	0.00145 U	0.00124 U	0.00195 U	0.00200 U	0.00226 U	0.000908 U
	MW-319-20	09/18/19	PES	PACE	20	11.7	S	0.00142 U	0.00597 U	0.00144 U	0.00632 U	0.000650 U	0.00180 U	0.000588 U	0.00157 U	0.00134 U	0.00211 U	0.00217 U	0.00244 U	0.000982 U
	MW-319-30	09/18/19	PES	PACE	30	1.7	S	0.00131 U	0.00551 U	0.00133 U	0.00583 U	0.000600 U	0.00166 U	0.000543 U	0.00145 U	0.00123 U	0.00194 U	0.00200 U	0.00225 U	0.000906 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
MW-319	MW-319-35	09/18/19	PES	PACE	35	-3.3	S	0.00145 U	0.00608 U	0.00146 U	0.00643 U	0.000662 U	0.00183 U	0.000599 U	0.00160 U	0.00136 U	0.00214 U	0.00221 U	0.00248 U	0.00100 U
(continued)	MW-319-40	09/18/19	PES	PACE	40	-8.3	S	0.00136 U	0.00569 U	0.00137 U	0.00602 U	0.000620 U	0.00171 U	0.000561 U	0.00150 U	0.00127 U	0.00201 U	0.00207 U	0.00233 U	0.000936 U
	MW-319-45	09/18/19	PES	PACE	45	-13.3	S	0.00137 U	0.00572 U	0.00138 U	0.00606 U	0.000623 U	0.00172 U	0.000564 U	0.00151 U	0.00128 U	0.00202 U	0.00208 U	0.00234 U	0.000942 U
	MW-319-50	09/18/19	PES	PACE	50	-18.3	S	0.00140 U	0.00589 U	0.00142 U	0.00623 U	0.000641 U	0.00177 U	0.000580 U	0.00155 U	0.00132 U	0.00208 U	0.00214 U	0.00241 U	0.000968 U
	MW-319-55	09/18/19	PES	PACE	55	-23.3	S	0.00145 U	0.00609 U	0.00146 U	0.00644 U	0.000663 U	0.00183 U	0.000600 U	0.00160 U	0.00136 U	0.00215 U	0.00221 U	0.00249 U	0.00100 U
	MW-319-60	09/18/19	PES	PACE	60	-28.3	S	0.00137 U	0.00572 U	0.00138 U	0.00606 U	0.000623 U	0.00172 U	0.000564 U	0.00151 U	0.00128 U	0.00202 U	0.00208 U	0.00234 U	0.000942 U
	MW-319-65	09/18/19	PES	PACE	65	-33.3	S	0.00147 U	0.00614 U	0.00148 U	0.00650 U	0.000669 U	0.00185 U	0.000606 U	0.00162 U	0.00138 U	0.00217 U	0.00223 U	0.00251 U	0.00101 U
	MW-319-70	09/18/19	PES	PACE	70	-38.3	S	0.00140 U	0.00587 U	0.00141 U	0.00621 U	0.000640 U	0.00177 U	0.000579 U	0.00155 U	0.00132 U	0.00207 U	0.00213 U	0.00240 U	0.000966 U
	MW-2006-70	09/18/19	PES	PACE	70 (dup)	-36.9	S	0.00144 U	0.00604 U	0.00145 U	0.00639 UJ	0.000658 U	0.00182 U	0.000595 U	0.00159 U	0.00135 U	0.00213 U	0.00219 U	0.00247 U	0.000994 U
	MW-319-75	09/18/19	PES	PACE	75	-43.3	S	0.00127 U	0.00534 U	0.00128 U	0.00565 U	0.000582 U	0.00161 U	0.000526 U	0.00141 U	0.00120 U	0.00188 U	0.00194 U	0.00218 U	0.000878 U
	MW-319-80	09/18/19	PES	PACE	80	-48.3	S	0.00140 U	0.00586 U	0.00141 U	0.00620 UJ	0.000638 U	0.00176 U	0.000577 U	0.00154 U	0.00131 U	0.00207 U	0.00213 U	0.00239 U	0.000964 U
	MW-319-85	09/18/19	PES	PACE	85	-53.3	S	0.00138 U	0.00580 U	0.00140 U	0.00614 UJ	0.000632 U	0.00174 U	0.000571 U	0.00153 U	0.00130 U	0.00205 U	0.00211 U	0.00237 U	0.000954 U
MW-320	MW-320-19	09/29/19	PES	PACE	19	15.1	S	0.0257 U	0.108 U	0.0259 U	0.114 U	0.0117 U	0.0324 U	0.0106 U	0.0284 U	0.0241 U	0.0380 U	0.0391 U	0.0440 U	0.0178 UJ
(18.6 to 8.6)	MW-320-27	09/29/19	PES	PACE	27	7.1	S	0.00133 U	0.00558 U	0.00134 U	0.00591 U	0.000608 U	0.00168 U	0.000550 U	0.00147 U	0.00125 U	0.00197 U	0.00203 U	0.00228 U	0.000918 UJ
MW-323	MW-323-10	09/28/19	PES	PACE	10	24.7	V	0.00280 U	0.0118 U	0.00283 U	0.0124 U	0.00128 U	0.00354 U	0.00116 U	0.00310 U	0.00263 U	0.00415 U	0.00427 U	0.00480 U	0.00194 U
(-65.4 to -75.4)	MW-2012-10	09/28/19	PES	PACE	10 (dup)	24.7	V	0.00144 U	0.00602 U	0.00145 U	0.00637 U	0.000656 U	0.00181 U	0.000594 U	0.00159 U	0.00135 U	0.00212 U	0.00219 U	0.00247 U	0.000991 UJ
	MW-323-15	09/28/19	PES	PACE	15	19.7	S	0.00264 U	0.0110 U	0.00266 U	0.0117 U	0.00120 U	0.00333 U	0.00109 U	0.00291 U	0.00247 U	0.00390 U	0.00401 U	0.00452 U	0.00182 U
	MW-323-20	09/28/19	PES	PACE	20	14.7	S	**0.0136**	0.00544 U	**0.0193**	0.00576 U	0.000593 U	0.00164 U	0.000536 U	0.00143 U	**0.00251 J**	0.00192 U	0.00198 U	0.00222 U	0.000895 U
	MW-323-25	09/28/19	PES	PACE	25	9.7	S	0.00131 U	0.00550 U	**0.00146 J**	0.00582 U	0.000599 U	0.00165 U	0.000542 U	0.00145 U	0.00123 U	0.00194 U	0.00200 U	0.00225 U	0.000904 U
	MW-323-30	09/28/19	PES	PACE	30	4.7	S	0.00244 U	0.0102 U	0.00246 U	0.0108 U	0.00112 U	0.00308 U	0.00101 U	0.00270 U	0.00229 U	0.00361 U	0.00372 U	0.00418 U	0.00169 U
	MW-323-35	09/28/19	PES	PACE	35	-0.4	S	0.00148 U	0.00620 U	0.00149 U	0.00655 U	0.000675 U	0.00186 U	0.000611 U	0.00163 U	0.00139 U	0.00218 U	0.00225 U	0.00253 U	0.00102 U
	MW-323-40	09/28/19	PES	PACE	40	-5.4	S	0.00148 U	0.00619 U	0.00149 U	0.00655 U	0.000674 U	0.00186 U	0.000610 U	0.00163 U	0.00139 U	0.00218 U	0.00225 U	0.00253 U	0.00102 U
	MW-323-45	09/28/19	PES	PACE	45	-10.4	S	0.00147 U	0.00617 U	0.00148 U	0.00652 U	0.000672 U	0.00186 U	0.000608 U	0.00162 U	0.00138 U	0.00217 U	0.00224 U	0.00252 U	0.00101 U
	MW-323-50	09/28/19	PES	PACE	50	-15.4	S	0.00132 U	0.00555 U	0.00134 U	0.00587 U	0.000604 U	0.00167 U	0.000547 U	0.00146 U	0.00124 U	0.00196 U	0.00201 U	0.00227 U	0.000913 U
	MW-323-55	09/28/19	PES	PACE	55	-20.4	S	0.00134 U	0.00562 U	0.00135 U	0.00594 U	0.000612 U	0.00169 U	0.000553 U	0.00148 U	0.00126 U	0.00198 U	0.00204 U	0.00230 U	0.000924 U
	MW-323-60	09/28/19	PES	PACE	60	-25.4	S	0.00147 U	0.00618 U	0.00148 U	0.00654 U	0.000673 U	0.00185 U	0.000609 U	0.00162 U	0.00138 U	0.00218 U	0.00225 U	0.00253 U	0.00102 U
	MW-2010-60	09/28/19	PES	PACE	60 (dup)	-25.4	S	0.00140 U	0.00588 U	0.00141 U	0.00622 U	0.000640 U	0.00177 U	0.000579 U	0.00155 U	0.00132 U	0.00207 U	0.00213 U	0.00240 U	0.000967 UJ
	MW-323-65	09/28/19	PES	PACE	65	-30.4	S	0.00138 U	0.00579 U	0.00139 U	0.00613 U	0.000631 U	0.00174 U	0.000571 U	0.00153 U	0.00130 U	0.00204 U	0.00210 U	0.00237 U	0.000953 UJ
	MW-323-70	09/28/19	PES	PACE	70	-35.4	S	0.194 U	0.811 U	0.195 U	0.858 U	0.0884 U	0.244 U	0.0799 U	0.214 U	0.182 U	0.286 U	0.294 U	0.332 U	0.133 UJ
	MW-323-75	09/28/19	PES	PACE	75	-40.4	S	0.00135 U	0.00566 U	0.00136 U	0.00599 U	0.000617 U	0.00170 U	0.000558 U	0.00149 U	0.00127 U	0.00200 U	0.00206 U	0.00231 U	0.000932 UJ
	MW-323-80	09/28/19	PES	PACE	80	-45.4	S	0.00130 U	0.00545 U	0.00131 U	0.00576 U	0.000593 U	0.00164 U	0.000537 U	0.00144 U	0.00122 U	0.00192 U	0.00198 U	0.00223 U	0.000896 UJ
	MW-323-85	09/28/19	PES	PACE	85	-50.4	S	0.00138 U	0.00577 U	0.00139 U	0.00611 U	0.000629 U	0.00174 U	0.000569 U	0.00152 U	0.00129 U	0.00204 U	0.00210 U	0.00236 U	0.000950 UJ
	MW-323-91	09/28/19	PES	PACE	91	-56.4	S	0.00326 U	0.0137 U	0.00328 U	0.0144 U	0.00149 U	0.00410 U	0.00134 U	0.00360 U	0.00307 U	0.00481 U	0.00496 U	0.00558 U	0.00225 UJ
	MW-323-95	09/28/19	PES	PACE	95	-60.4	S	0.00138 U	0.00578 U	0.00139 U	0.00611 U	0.000629 U	0.00174 U	0.000569 U	0.00152 U	0.00129 U	0.00204 U	0.00210 U	0.00236 U	0.000951 UJ
	MW-323-99	09/28/19	PES	PACE	99	-64.4	S	0.00133 U	0.00557 U	0.00134 U	0.00590 U	0.000607 U	0.00168 U	0.000549 U	0.00147 U	0.00125 U	0.00197 U	0.00202 U	0.00228 U	0.000917 UJ
	MW-323-105	09/28/19	PES	PACE	105	-70.4	S	0.00136 U	0.00569 U	0.00137 U	0.00602 U	0.000620 U	0.00171 U	0.000561 U	0.00150 U	0.00128 U	0.00201 U	0.00207 U	0.00233 U	0.000936 UJ
	MW-323-110	09/28/19	PES	PACE	110	-75.4	S	0.00281 U	0.0118 U	0.00285 U	0.0125 U	0.00128 U	0.00355 U	0.00117 U	0.00311 U	0.00264 U	0.00416 U	0.00429 U	0.00483 U	0.00194 UJ
MW-324	MW-324-6	09/12/19	PES	PACE	6	28.3	V	0.00129 U	0.00542 U	0.00130 U	0.00574 UJ	0.000590 U	0.00163 U	0.000534 U	0.00143 U	0.00121 U	0.00191 U	0.00197 U	0.00222 U	0.000892 U
(-32.1 to -42.1)	MW-324-10	09/12/19	PES	PACE	10	24.3	V	0.00133 U	0.00558 U	0.00134 U	0.00591 UJ	0.000608 U	0.00168 U	0.000550 U	0.00147 U	0.00125 U	0.00197 U	0.00203 U	0.00228 U	0.000918 U
	MW-324-15	09/12/19	PES	PACE	15	19.3	S	0.00126 U	0.00526 U	0.00127 U	0.00557 UJ	0.000573 U	0.00158 U	0.000519 U	0.00139 U	0.00118 U	0.00186 U	0.00191 U	0.00215 U	0.000866 U
	MW-324-20	09/12/19	PES	PACE	20	14.3	S	0.00134 U	0.00562 U	0.00135 U	0.00595 UJ	0.000613 U	0.00169 U	0.000554 U	0.00148 U	0.00126 U	0.00198 U	0.00204 U	0.00230 U	0.000925 U
	MW-324-25	09/12/19	PES	PACE	25	9.3	S	0.00136 UJ	0.00569 U	**0.00208 J**	0.00602 UJ	0.000620 U	0.00171 U	0.000561 U	0.00150 U	0.00128 U	0.00201 U	0.00207 U	0.00233 U	0.000936 U
	MW-324-30	09/12/19	PES	PACE	30	4.3	S	0.00141 U	0.00593 U	0.00142 U	0.00627 UJ	0.000646 U	0.00178 U	0.000583 U	0.00157 U	0.00133 U	0.00208 U	0.00214 U	0.00242 U	0.000975 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
MW-324 (continued)	MW-324-35	09/12/19	PES	PACE	35	-0.7	S	0.00137 U	0.00575 U	0.00138 U	0.00609 UJ	0.000627 U	0.00173 U	0.000567 U	0.00152 U	0.00129 U	0.00203 U	0.00209 U	0.00235 U	0.000947 U
	MW-324-40	09/12/19	PES	PACE	40	-5.7	S	0.00139 U	0.00583 U	0.00140 U	0.00616 UJ	0.000635 U	0.00175 U	0.000574 U	0.00153 U	0.00131 U	0.00205 U	0.00212 U	0.00238 U	0.000958 U
	MW-324-45	09/12/19	PES	PACE	45	-10.7	S	0.00145 U	0.00607 U	0.00146 U	0.00642 UJ	0.000661 U	0.00183 U	0.000598 U	0.00160 U	0.00136 U	0.00214 U	0.00220 U	0.00248 U	0.000998 U
	MW-324-50	09/12/19	PES	PACE	50	-15.7	S	0.00115 U	0.00482 U	0.00116 U	0.00510 UJ	0.000525 U	0.00145 U	0.000475 U	0.00127 U	0.00108 U	0.00170 U	0.00175 U	0.00197 U	0.000793 U
	MW-324-55	09/12/19	PES	PACE	55	-20.7	S	0.00130 U	0.00546 U	0.00131 U	0.00578 UJ	0.000595 U	0.00164 U	0.000538 U	0.00144 U	0.00122 U	0.00193 U	0.00198 U	0.00223 U	0.000899 U
	MW-324-60	09/12/19	PES	PACE	60	-25.7	S	0.00130 U	0.00546 U	0.00131 U	0.00578 UJ	0.000595 U	0.00164 U	0.000538 U	0.00144 U	0.00122 U	0.00193 U	0.00198 U	0.00223 U	0.000899 U
	MW-324-65	09/12/19	PES	PACE	65	-30.7	S	0.00135 U	0.00567 U	0.00136 U	0.00600 UJ	0.000617 U	0.00170 U	0.000559 U	0.00149 U	0.00127 U	0.00200 U	0.00206 U	0.00232 U	0.000933 U
	MW-324-70	09/12/19	PES	PACE	70	-35.7	S	0.00143 U	0.00598 U	0.00144 U	0.00633 UJ	0.000651 U	0.00180 U	0.000590 U	0.00158 U	0.00133 U	0.00211 U	0.00218 U	0.00245 U	0.000983 U
	MW-324-75	09/12/19	PES	PACE	75	-40.7	S	0.00144 U	0.00604 U	0.00145 U	0.00640 UJ	0.000658 U	0.00182 U	0.000596 U	0.00159 U	0.00135 U	0.00213 U	0.00219 U	0.00247 U	0.000994 U
	MW-324-80	09/12/19	PES	PACE	80	-45.7	S	0.00144 U	0.00603 U	0.00145 U	0.00638 UJ	0.000657 U	0.00181 U	0.000594 U	0.00159 U	0.00135 U	0.00213 U	0.00219 U	0.00247 U	0.000992 U
MW-326 (-48.7 to -58.7)	MW-326-5	09/09/19	PES	PACE	5	36.3	V	**0.00216 J**	0.00531 U	**0.00325 J**	0.00562 U	0.000579 U	0.00160 U	0.000523 U	0.00140 U	**0.00151 J**	0.00187 U	0.00193 U	0.00217 U	0.000874 U
	MW-326-10	09/09/19	PES	PACE	10	31.3	V	0.00153 U	0.00642 U	0.00155 U	0.00679 U	0.000699 U	0.00193 U	0.000632 U	0.00169 U	0.00143 U	0.00227 U	0.00232 U	0.00262 U	0.00106 U
	MW-326-15	09/09/19	PES	PACE	15	26.3	V	0.00134 U	0.00564 U	0.00136 U	0.00596 U	0.000614 U	0.00170 U	0.000555 U	0.00149 U	0.00126 U	0.00199 U	0.00205 U	0.00230 U	0.000927 U
	MW-326-20	09/09/19	PES	PACE	20	21.3	S	0.00135 U	0.00564 U	0.00136 U	0.00597 U	0.000615 U	0.00170 U	0.000556 U	0.00149 U	0.00126 U	0.00199 U	0.00205 U	0.00231 U	0.000928 U
	MW-326-25	09/09/19	PES	PACE	25	16.3	S	0.00143 U	0.00598 U	0.00144 U	0.00633 U	0.000651 U	0.00180 U	0.000589 U	0.00158 U	0.00134 U	0.00211 U	0.00217 U	0.00244 U	0.000984 U
	MW-326-30	09/09/19	PES	PACE	30	11.3	S	0.00464 U	0.0195 U	0.00469 U	0.0206 U	0.00213 U	0.00586 U	0.00191 U	0.00513 U	0.00437 U	0.00687 U	0.00707 U	0.00796 U	0.00320 U
	MW-326-35	09/09/19	PES	PACE	35	6.3	S	0.00142 U	0.00596 U	0.00143 U	0.00631 U	0.000649 U	0.00179 U	0.000587 U	0.00157 U	0.00134 U	0.00210 U	0.00216 U	0.00244 U	0.000981 U
	MW-326-40	09/09/19	PES	PACE	40	1.3	S	0.00137 U	0.00575 U	0.00138 U	0.00608 U	0.000626 U	0.00173 U	0.000566 U	0.00151 U	0.00129 U	0.00203 U	0.00209 U	0.00235 U	0.000946 U
	MW-326-45	09/09/19	PES	PACE	45	-3.7	S	0.00139 U	0.00581 U	0.00140 U	0.00614 U	0.000632 U	0.00175 U	0.000572 U	0.00153 U	0.00130 U	0.00205 U	0.00211 U	0.00237 U	0.000955 U
	MW-326-50	09/09/19	PES	PACE	50	-8.7	S	0.00131 U	0.00551 U	0.00133 U	0.00583 U	0.000600 U	0.00166 U	0.000543 U	0.00145 U	0.00123 U	0.00194 U	0.00200 U	0.00225 U	0.000907 U
	MW-326-55	09/09/19	PES	PACE	55	-13.7	S	0.00140 U	0.00586 U	0.00141 U	0.00620 U	0.000639 U	0.00176 U	0.000578 U	0.00154 U	0.00131 U	0.00207 U	0.00213 U	0.00240 U	0.000965 U
	MW-326-60	09/09/19	PES	PACE	60	-18.7	S	0.00125 U	0.00524 U	0.00126 U	0.00554 UJ	0.000571 U	0.00158 U	0.000516 U	0.00138 U	0.00117 U	0.00185 U	0.00190 U	0.00214 U	0.000862 U
	MW-326-65	09/09/19	PES	PACE	65	-23.7	S	0.00133 U	0.00559 U	0.00134 U	0.00591 UJ	0.000609 U	0.00168 U	0.000551 U	0.00147 U	0.00125 U	0.00197 U	0.00203 U	0.00228 U	0.000919 U
	MW-326-70	09/09/19	PES	PACE	70	-28.7	S	0.00140 U	0.00587 U	0.00141 U	0.00621 UJ	0.000640 U	0.00177 U	0.000579 U	0.00155 U	0.00132 U	0.00207 U	0.00213 U	0.00240 U	0.000966 U
	MW-326-75	09/09/19	PES	PACE	75	-33.7	S	0.00139 U	0.00584 U	0.00141 U	0.00618 UJ	0.000636 U	0.00176 U	0.000576 U	0.00154 U	0.00131 U	0.00206 U	0.00212 U	0.00239 U	0.000961 U
	MW-326-80	09/09/19	PES	PACE	80	-38.7	S	0.00137 U	0.00573 U	0.00138 U	0.00606 UJ	0.000624 U	0.00172 U	0.000565 U	0.00151 U	0.00128 U	0.00202 U	0.00208 U	0.00234 U	0.000943 U
	MW-326-85	09/10/19	PES	PACE	85	-43.7	S	0.00134 U	0.00563 U	0.00136 U	0.00596 UJ	0.000614 U	0.00169 U	0.000555 U	0.00148 U	0.00126 U	0.00199 U	0.00205 U	0.00230 U	0.000927 U
	MW-326-90	09/10/19	PES	PACE	90	-48.7	S	0.00135 U	0.00568 U	0.00137 U	0.00601 UJ	0.000618 U	0.00171 U	0.000559 U	0.00150 U	0.00127 U	0.00200 U	0.00206 U	0.00232 U	0.000934 U
	MW-326-95	09/10/19	PES	PACE	95	-53.7	S	0.00129 U	0.00542 U	0.00130 U	0.00573 UJ	0.000590 U	0.00163 U	0.000534 U	0.00143 U	0.00121 U	0.00191 U	0.00197 U	0.00221 U	0.000891 U
	MW-200I-95	09/10/19	PES	PACE	95 (dup)	-53.7	S	0.00131 U	0.00550 U	0.00132 U	0.00582 U	0.000599 U	0.00165 U	0.000542 U	0.00145 U	0.00123 U	0.00194 U	0.00200 U	0.00225 U	0.000905 U
	MW-326-100	09/10/19	PES	PACE	100	-58.7	S	0.00139 U	0.00582 U	0.00140 U	0.00616 UJ	0.000634 U	0.00175 U	0.000574 U	0.00153 U	0.00130 U	0.00205 U	0.00211 U	0.00238 U	0.000958 U
MW-328 (-36.1 to -46.1)	MW-328-5	09/16/19	PES	PACE	5	23.4	V	0.00137 U	0.00573 U	0.00138 U	0.00606 UJ	0.000624 U	0.00172 U	0.000565 U	0.00151 U	0.00128 U	0.00202 U	0.00208 U	0.00234 U	0.000943 U
	MW-328-10	09/16/19	PES	PACE	10	18.4	S	0.00158 U	0.00662 U	0.00159 U	0.00701 UJ	0.000722 U	0.00199 U	0.000653 U	0.00175 U	0.00148 U	0.00234 U	0.00241 U	0.00271 U	0.00109 U
	MW-328-15	09/16/19	PES	PACE	15	13.4	S	0.00141 U	0.00592 U	0.00142 U	0.00626 UJ	0.000644 U	0.00178 U	0.000583 U	0.00156 U	0.00133 U	0.00209 U	0.00215 U	0.00242 U	0.000973 U
	MW-328-20	09/16/19	PES	PACE	20	8.4	S	0.00137 U	0.00576 U	0.00139 U	0.00609 UJ	0.000627 U	0.00173 U	0.000567 U	0.00152 U	0.00129 U	0.00203 U	0.00209 U	0.00235 U	0.000947 U
	MW-328-30	09/16/19	PES	PACE	30	-1.6	S	0.0271 U	0.114 U	0.0274 U	0.120 UJ	0.0124 U	0.0341 U	0.0112 U	0.0299 U	0.0255 U	0.0401 U	0.0412 U	0.0465 U	0.0187 U
	MW-328-35	09/16/19	PES	PACE	35	-6.6	S	0.00148 U	0.00620 U	0.00149 U	0.00656 UJ	0.000674 U	0.00187 U	0.000611 U	0.00164 U	0.00138 U	0.00218 U	0.00226 U	0.00253 U	0.00102 U
	MW-328-40	09/16/19	PES	PACE	40	-11.6	S	0.00335 U	0.0140 U	0.00338 U	0.0148 UJ	0.00153 U	0.00422 U	0.00138 U	0.00370 U	0.00314 U	0.00495 U	0.00510 U	0.00574 U	0.00231 U
	MW-328-45	09/16/19	PES	PACE	45	-16.6	S	0.00142 U	0.00594 U	0.00143 U	0.00629 UJ	0.000647 U	0.00179 U	0.000586 U	0.00157 U	0.00133 U	0.00210 U	0.00216 U	0.00243 U	0.000978 U
	MW-328-50	09/16/19	PES	PACE	50	-21.6	S	0.0422 U	0.177 U	0.0426 U	0.187 UJ	0.0192 U	0.0532 U	0.0175 U	0.0467 U	0.0397 U	0.0624 U	0.0643 U	0.0723 U	0.0291 U
	MW-328-55	09/16/19	PES	PACE	55	-26.6	S	0.00137 U	0.00574 U	0.00138 U	0.00607 UJ	0.000625 U	0.00173 U	0.000565 U	0.00151 U	0.00129 U	0.00202 U	0.00208 U	0.00234 U	0.000944 U
	MW-328-60	09/16/19	PES	PACE	60	-31.6	S	0.00138 U	0.00580 U	0.00139 U	0.00613 UJ	0.000631 U	0.00174 U	0.000571 U	0.00153 U	0.00130 U	0.00204 U	0.00210 U	0.00237 U	0.000954 U
	MW-328-65	09/16/19	PES	PACE	65	-36.6	S	0.00134 U	0.00562 U	0.00135 U	0.00595 UJ	0.000612 U	0.00169 U	0.000554 U	0.00148 U	0.00126 U	0.00198 U	0.00204 U	0.00230 U	0.000925 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
MW-328	MW-328-70	09/16/19	PES	PACE	70	-41.6	S	0.00138 U	0.00580 U	0.00140 U	0.00614 UJ	0.000632 U	0.00175 U	0.000572 U	0.00153 U	0.00130 U	0.00205 U	0.00211 U	0.00237 U	0.000955 U
(continued)	MW-328-75	09/16/19	PES	PACE	75	-46.6	S	0.00134 U	0.00562 U	0.00135 U	0.00595 UJ	0.000612 U	0.00169 U	0.000554 U	0.00148 U	0.00126 U	0.00198 U	0.00204 U	0.00230 U	0.000925 U
	MW-328-80	09/16/19	PES	PACE	80	-51.6	S	0.00152 U	0.00636 U	0.00153 U	0.00673 UJ	0.000693 U	0.00191 U	0.000627 U	0.00168 U	0.00142 U	0.00224 U	0.00231 U	0.00260 U	0.00105 U
MW-329	MW-329-5	09/12/19	PES	PACE	5	24.3	V	0.00123 U	0.00515 U	0.00124 U	0.00545 UJ	0.000561 U	0.00155 U	0.000508 U	0.00136 U	0.00115 U	0.00182 U	0.00187 U	0.00211 U	0.000848 U
(-69.0 to -79.0)	MW-329-10	09/12/19	PES	PACE	10	19.3	S	0.00121 U	0.00507 U	0.00122 U	0.00536 UJ	0.000552 U	0.00153 U	0.000500 U	0.00134 U	0.00114 U	0.00179 U	0.00184 U	0.00207 U	0.000834 U
	MW-329-15	09/12/19	PES	PACE	15	14.3	S	0.00126 U	0.00529 U	0.00127 U	0.00560 UJ	0.000576 U	0.00159 U	0.000522 U	0.00139 U	0.00119 U	0.00187 U	0.00192 U	0.00216 U	0.000871 U
	MW-329-20	09/12/19	PES	PACE	20	9.3	S	0.00159 U	0.00666 U	0.00160 U	0.00705 UJ	0.000726 U	0.00200 U	0.000657 U	0.00176 U	0.00149 U	0.00235 U	0.00242 U	0.00272 U	0.00110 U
	MW-329-25	09/12/19	PES	PACE	25	4.3	S	0.00165 U	0.00691 U	0.00166 U	0.00731 U	0.000752 U	0.00208 U	0.000681 U	0.00182 U	0.00155 U	0.00244 U	0.00251 U	0.00282 U	0.00114 U
	MW-329-30	09/12/19	PES	PACE	30	-0.7	S	0.00142 U	0.00595 U	0.00143 U	0.00630 U	0.000648 U	0.00179 U	0.000587 U	0.00157 U	0.00133 U	0.00210 U	0.00216 U	0.00243 U	0.000980 U
	MW-329-35	09/12/19	PES	PACE	35	-5.7	S	0.00141 U	0.00591 U	0.00142 U	0.00625 U	0.000643 U	0.00178 U	0.000582 U	0.00156 U	0.00132 U	0.00208 U	0.00214 U	0.00241 U	0.000972 U
	MW-329-40	09/12/19	PES	PACE	40	-10.7	S	0.00142 U	0.00594 U	0.00143 U	0.00629 U	0.000647 U	0.00179 U	0.000585 U	0.00157 U	0.00133 U	0.00210 U	0.00216 U	0.00243 U	0.000977 U
	MW-329-45	09/12/19	PES	PACE	45	-15.7	S	0.00137 U	0.00575 U	0.00138 U	0.00608 U	0.000626 U	0.00173 U	0.000567 U	0.00151 U	0.00129 U	0.00203 U	0.00209 U	0.00235 U	0.000946 U
	MW-329-50	09/12/19	PES	PACE	50	-20.7	S	0.00142 U	0.00594 U	0.00143 U	0.00629 U	0.000647 U	0.00179 U	0.000586 U	0.00157 U	0.00133 U	0.00210 U	0.00216 U	0.00243 U	0.000978 U
	MW-2003-50	09/12/19	PES	PACE	50 (dup)	-20.7	S	0.00126 U	0.00527 U	0.00127 U	0.00557 U	0.000574 U	0.00158 U	0.000519 U	0.00139 U	0.00118 U	0.00186 U	0.00191 U	0.00215 U	0.000866 U
	MW-329-55	09/12/19	PES	PACE	55	-25.7	S	0.00133 U	0.00556 U	0.00134 U	0.00589 U	0.000606 U	0.00167 U	0.000548 U	0.00147 U	0.00125 U	0.00196 U	0.00202 U	0.00227 U	0.000915 U
	MW-329-60	09/12/19	PES	PACE	60	-30.7	S	0.00135 U	0.00564 U	0.00136 U	0.00597 U	0.000614 U	0.00170 U	0.000556 U	0.00149 U	0.00126 U	0.00199 U	0.00205 U	0.00230 U	0.000928 U
	MW-329-65	09/12/19	PES	PACE	65	-35.7	S	0.00134 U	0.00563 U	0.00136 U	0.00596 U	0.000613 U	0.00169 U	0.000555 U	0.00148 U	0.00126 U	0.00199 U	0.00204 U	0.00230 U	0.000927 U
	MW-329-70	09/12/19	PES	PACE	70	-40.7	S	0.00134 U	0.00562 U	0.00135 U	0.00594 U	0.000612 U	0.00169 U	0.000554 U	0.00148 U	0.00126 U	0.00198 U	0.00204 U	0.00230 U	0.000924 U
	MW-329-75	09/12/19	PES	PACE	75	-45.7	S	0.00132 U	0.00552 U	0.00133 U	0.00584 U	0.000601 U	0.00166 U	0.000544 U	0.00146 U	0.00124 U	0.00195 U	0.00200 U	0.00226 U	0.000909 U
	MW-329-80	09/12/19	PES	PACE	80	-50.7	S	0.00140 U	0.00586 U	0.00141 U	0.00620 UJ	0.000638 U	0.00176 U	0.000577 U	0.00154 U	0.00131 U	0.00207 U	0.00213 U	0.00239 U	0.000963 U
	MW-329-85	09/12/19	PES	PACE	85	-55.7	S	0.00134 U	0.00564 U	0.00136 U	0.00596 U	0.000614 U	0.00170 U	0.000555 U	0.00148 U	0.00126 U	0.00199 U	0.00205 U	0.00230 U	0.000927 U
	MW-329-90	09/12/19	PES	PACE	90	-60.7	S	0.00135 U	0.00567 U	0.00136 U	0.00600 U	0.000617 U	0.00170 U	0.000558 U	0.00149 U	0.00127 U	0.00200 U	0.00206 U	0.00232 U	0.000932 U
	MW-329-95	09/12/19	PES	PACE	95	-65.7	S	0.00137 U	0.00572 U	0.00138 U	0.00606 U	0.000623 U	0.00172 U	0.000564 U	0.00151 U	0.00128 U	0.00202 U	0.00208 U	0.00234 U	0.000942 U
	MW-329-100	09/12/19	PES	PACE	100	-70.7	S	0.00137 U	0.00574 U	0.00138 U	0.00607 U	0.000625 U	0.00173 U	0.000566 U	0.00151 U	0.00129 U	0.00202 U	0.00208 U	0.00235 U	0.000944 U
	MW-329-105	09/12/19	PES	PACE	105	-75.7	S	0.00127 U	0.00531 U	0.00128 U	0.00561 U	0.000578 U	0.00160 U	0.000523 U	0.00140 U	0.00119 U	0.00187 U	0.00193 U	0.00217 U	0.000873 U
	MW-329-110	09/12/19	PES	PACE	110	-80.7	S	0.00126 U	0.00527 U	0.00127 U	0.00557 U	0.000574 U	0.00158 U	0.000519 U	0.00139 U	0.00118 U	0.00186 U	0.00191 U	0.00215 U	0.000866 U
MW-330	MW-330-6	04/20/20	PES	PACE	6	46.0	V	0.00179 U	0.00500 U	0.00179 U	0.00443 U	0.000736 U	0.000483 U	0.000737 U	0.00161 U	0.00227 U	0.000681 U	0.000569 U	0.000795 U	0.00157 U
	MW-330-10	04/20/20	PES	PACE	10	42.0	V	0.00174 U	0.00485 U	0.00174 U	0.00430 U	0.000715 U	0.000469 U	0.000716 U	0.00157 U	0.00221 U	0.000662 U	0.000553 U	0.000772 U	0.00152 U
	MW-330-11.5	04/20/20	PES	PACE	11.5	40.5	V	0.00184 U	0.00513 U	0.00184 U	0.00455 U	0.000755 U	0.000495 U	0.000757 U	0.00166 U	0.00233 U	0.000700 U	0.000584 U	0.000816 U	0.00161 U
	MW-330-16	04/20/20	PES	PACE	16	36.0	V	0.00179 U	0.00500 U	0.00179 U	0.00443 U	0.000736 U	0.000483 U	0.000737 U	0.00161 U	0.00227 U	0.000682 U	0.000569 U	0.000795 U	0.00157 U
	MW-330-21.5	04/20/20	PES	PACE	21.5	30.5	S	0.00168 U	0.00469 U	0.00168 U	0.00415 U	0.000690 U	0.000453 U	0.000691 U	0.00151 U	0.00213 U	0.000639 U	0.000533 U	0.000745 U	0.00147 U
	MW-330-27	04/20/20	PES	PACE	27	25.0	S	0.00170 U	0.00473 U	0.00170 U	0.00419 U	0.000697 U	0.000457 U	0.000698 U	0.00153 U	0.00215 U	0.000645 U	0.000539 U	0.000753 U	0.00148 U
	MW-330-32	04/20/20	PES	PACE	32	20.0	S	0.00170 U	0.00474 U	0.00170 U	0.00420 U	0.000698 U	0.000458 U	0.000699 U	0.00153 U	0.00215 U	0.000646 U	0.000540 U	0.000754 U	0.00149 U
	MW-330-38	04/20/20	PES	PACE	38	14.0	S	0.00170 U	0.00473 U	0.00170 U	0.00420 U	0.000697 U	0.000457 U	0.000698 U	0.00153 U	0.00215 U	0.000646 U	0.000539 U	0.000753 U	0.00148 U
	MW-330-42	04/20/20	PES	PACE	42	10.0	S	0.00165 U	0.00461 U	0.00165 U	0.00408 U	0.000678 U	0.000445 U	0.000679 U	0.00149 U	0.00209 U	0.000628 U	0.000525 U	0.000733 U	0.00144 U
	MW-330-47	04/20/20	PES	PACE	47	5.0	S	0.00179 U	0.00498 U	0.00179 U	0.00441 U	0.000734 U	0.000481 U	0.000735 U	0.00161 U	0.00226 U	0.000679 U	0.000567 U	0.000792 U	0.00156 U
	MW-330-52	04/20/20	PES	PACE	52	0.0	S	0.00173 U	0.00483 U	0.00173 U	0.00428 U	0.000711 U	0.000467 U	0.000712 U	0.00156 U	0.00220 U	0.000659 U	0.000550 U	0.000768 U	0.00151 U
	MW-330-58	04/20/20	PES	PACE	58	-6.0	S	0.00172 U	0.00479 U	0.00172 U	0.00424 U	0.000705 U	0.000462 U	0.000706 U	0.00155 U	0.00218 U	0.000653 U	0.000545 U	0.000762 U	0.00150 U
	MW-330-62	04/20/20	PES	PACE	62	-10.0	S	0.00174 U	0.00483 U	0.00174 U	0.00428 U	0.000712 U	0.000467 U	0.000713 U	0.00156 U	0.00220 U	0.000659 U	0.000550 U	0.000769 U	0.00152 U
MW-331	MW-331-7	04/17/20	PES	PACE	7	24.2	V	**0.0479**	0.00679 U	**0.124**	0.00602 U	0.00100 U	0.000656 U	0.00100 U	0.00219 U	**0.114**	0.000926 U	0.000774 U	0.00108 U	0.00213 UJ
	MW-331-11	04/17/20	PES	PACE	11	20.2	S	**0.512**	0.0394 UJ	**0.0557**	0.0349 U	0.00580 U	0.00381 U	0.00581 U	0.0128 U	**0.330**	0.00538 U	0.00449 U	0.00627 U	0.0123 U
	MW-331-16	04/17/20	PES	PACE	16	15.2	S	**0.0203**	0.00519 UJ	**0.00786**	0.00460 U	0.000765 U	0.000502 U	0.000766 U	0.00168 U	**0.00619**	0.000708 U	0.000591 U	0.000826 U	0.00163 U
	MW-331-20	04/17/20	PES	PACE	20	11.2	S	**0.00909**	0.00508 UJ	**0.00205 J**	0.00451 U	0.000749 U	0.000491 U	0.000750 U	0.00164 U	**0.00243 J**	0.000693 U	0.000579 U	0.000809 U	0.00159 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
MW-331 (continued)	MW-331-29.5	04/17/20	PES	PACE	29.5	1.7	S	**0.00387 J**	0.00510 U	0.00183 U	0.00452 U	0.000751 U	0.000493 U	0.000752 U	0.00165 U	0.00232 U	0.000695 U	0.000581 U	0.000811 U	0.00160 U
	MW-331-35	04/17/20	PES	PACE	35	-3.8	S	0.00187 U	0.00520 U	0.00187 U	0.00461 U	0.000765 U	0.000502 U	0.000766 U	0.00168 U	0.00236 U	0.000709 U	0.000592 U	0.000827 U	0.00163 U
	MW-2018-35	04/17/20	PES	PACE	35 (dup)	-3.8	S	0.00190 U	0.00529 UJ	0.00190 U	0.00469 U	0.000779 U	0.000511 U	0.000780 U	0.00171 U	0.00240 U	0.000721 U	0.000602 U	0.000841 U	0.00166 U
	MW-331-40	04/17/20	PES	PACE	40	-8.8	S	0.00191 U	0.00531 UJ	0.00191 U	0.00471 U	0.000782 U	0.000513 U	0.000783 U	0.00171 U	0.00241 U	0.000724 U	0.000604 U	0.000845 U	0.00166 U
	MW-331-45	04/17/20	PES	PACE	45	-13.8	S	0.00190 U	0.00529 UJ	0.00190 U	0.00469 U	0.000779 U	0.000511 U	0.000780 U	0.00171 U	0.00240 U	0.000721 U	0.000602 U	0.000842 U	0.00166 U
MW-332	MW-332-7	04/17/20	PES	PACE	7	29.3	V	**0.00188 J**	0.00493 U	**0.00740**	0.00437 U	0.000727 U	0.000477 U	0.000728 U	0.00159 U	**0.00565**	0.000673 U	0.000562 U	0.000785 U	0.00155 UJ
	MW-332-11	04/17/20	PES	PACE	11	25.3	V	**0.00647**	0.00518 U	**0.00910**	0.00459 U	0.000763 U	0.000501 U	0.000764 U	0.00167 U	**0.00440 J**	0.000707 U	0.000590 U	0.000824 U	0.00163 UJ
	MW-332-16	04/17/20	PES	PACE	16	20.3	S	0.00182 U	0.00508 U	0.00182 U	0.00450 U	0.000747 U	0.000490 U	0.000749 U	0.00164 U	0.00231 U	0.000692 U	0.000578 U	0.000807 U	0.00159 UJ
	MW-332-20	04/17/20	PES	PACE	20	16.3	S	0.00185 U	0.00516 U	0.00185 U	0.00457 U	0.000759 U	0.000498 U	0.000761 U	0.00166 U	0.00234 U	0.000703 U	0.000587 U	0.000820 U	0.00162 UJ
	MW-332-25	04/17/20	PES	PACE	25	11.3	S	0.00192 U	0.00534 U	0.00192 U	0.00473 U	0.000786 U	0.000516 U	0.000788 U	0.00172 U	0.00243 U	0.000728 U	0.000608 U	0.000849 U	0.00167 UJ
	MW-332-30	04/17/20	PES	PACE	30	6.3	S	0.00196 U	0.00545 U	0.00196 U	0.00483 U	0.000803 U	0.000527 U	0.000804 U	0.00176 U	0.00248 U	0.000744 U	0.000621 U	0.000868 U	0.00171 UJ
MW-334	MW-334-6	04/16/20	PES	PACE	6	25.4	V	**0.00695**	0.00535 U	**0.00757**	0.00474 U	0.000787 U	**0.00746**	0.000788 U	0.00173 U	**0.00268 J**	**0.00129 J**	0.000609 U	**0.00813**	0.00168 UJ
	MW-334-10	04/16/20	PES	PACE	10	21.4	V	**0.00490 J**	0.00535 U	**0.0184**	0.00474 U	0.000788 U	**0.0345**	0.000789 U	0.00173 U	0.00243 U	0.000730 U	0.000609 U	**0.00255 J**	0.00168 UJ
	MW-334-13	04/16/20	PES	PACE	13	18.4	S	**0.160**	0.0396 U	**0.0369 J**	0.0351 U	0.00583 U	**0.196**	0.00584 U	0.0128 U	0.0180 U	**0.0133 J**	0.00451 U	**0.0559**	0.0124 UJ
	MW-334-17	04/16/20	PES	PACE	17	14.4	S	0.00163 U	0.00455 U	**0.00333 J**	0.00403 U	0.000670 U	**0.00804**	0.000671 U	0.00147 U	0.00207 U	0.000620 U	0.000518 U	**0.00271 J**	0.00143 UJ
	MW-334-23	04/16/20	PES	PACE	23	8.4	S	0.00188 U	0.00524 U	0.00188 U	0.00464 U	0.000771 U	0.000506 U	0.000773 U	0.00169 U	0.00238 U	0.000714 U	0.000596 U	0.000833 U	0.00164 UJ
	MW-334-28	04/16/20	PES	PACE	28	3.4	S	0.00186 U	0.00518 U	0.00186 U	0.00459 U	0.000763 U	0.000501 U	0.000764 U	0.00167 U	0.00236 U	0.000707 U	0.000590 U	0.000824 U	0.00163 UJ
	MW-334-35	04/16/20	PES	PACE	35	-3.6	S	0.00200 U	0.00556 U	0.00200 U	0.00493 U	0.000819 U	0.000537 U	0.000820 U	0.00179 U	0.00253 U	0.000758 U	0.000633 U	0.000885 U	0.00174 UJ
	MW-334-40	04/16/20	PES	PACE	40	-8.6	S	0.00204 U	0.00568 U	0.00204 U	0.00504 U	0.000837 U	0.000549 U	0.000838 U	0.00183 U	0.00258 U	0.000775 U	0.000647 U	0.000904 U	0.00178 UJ
	MW-334-45.5	04/16/20	PES	PACE	45.5	-14.1	S	0.00192 U	0.00535 U	0.00192 U	0.00474 U	0.000788 U	0.000517 U	0.000790 U	0.00173 U	0.00243 U	0.000730 U	0.000609 U	0.000852 U	0.00168 UJ
	MW-334-50	04/16/20	PES	PACE	50	-18.6	S	0.00175 U	0.00487 U	0.00175 U	0.00432 U	0.000717 U	0.000470 U	0.000718 U	0.00157 U	0.00221 U	0.000664 U	0.000554 U	0.000775 U	0.00153 UJ
	MW-334-54.5	04/16/20	PES	PACE	54.5	-23.1	S	0.00195 U	0.00544 U	0.00195 U	0.00483 U	0.000802 U	0.000526 U	0.000803 U	0.00176 U	0.00247 U	0.000742 U	0.000620 U	0.000866 U	0.00171 UJ
	MW-334-60	04/16/20	PES	PACE	60	-28.6	S	0.00180 U	0.00501 U	0.00180 U	0.00444 U	0.000738 U	0.000484 U	0.000739 U	0.00162 U	0.00228 U	0.000683 U	0.000570 U	0.000797 U	0.00157 UJ
	MW-334-63	04/16/20	PES	PACE	63	-31.6	S	0.00189 U	0.00526 U	0.00189 U	0.00466 U	0.000775 U	0.000508 U	0.000776 U	0.00170 U	0.00239 U	0.000718 U	0.000599 U	0.000837 U	0.00165 UJ
MW-336	MW-336-7	04/22/20	PES	PACE	7	26.7	V	0.00176 U	0.00491 U	0.00176 U	0.00435 U	0.000723 U	0.000474 U	0.000724 U	0.00158 U	0.00223 U	0.000669 U	0.000559 U	0.000781 U	0.00154 U
	MW-336-11.5	04/22/20	PES	PACE	11.5	22.2	V	0.00188 U	0.00524 U	0.00188 U	0.00464 U	0.000772 U	0.000506 U	0.000773 U	0.00169 U	0.00238 U	0.000714 U	0.000597 U	0.000833 U	0.00164 U
	MW-2019-11.5	04/22/20	PES	PACE	11.5 (dup)	22.2	V	0.00193 U	0.00537 UJ	0.00193 U	0.00476 U	0.000790 U	0.000518 U	0.000791 U	**0.0107**	0.00244 U	0.000732 U	0.000611 U	0.000854 U	0.00168 U
	MW-336-14.5	04/22/20	PES	PACE	14.5	19.2	V	0.00203 U	0.00564 U	0.00203 U	0.00500 U	0.000831 U	0.000545 U	0.000832 U	0.00182 U	0.00256 U	0.000769 U	0.000642 U	0.000897 U	0.00177 U
	MW-336-20	04/22/20	PES	PACE	20	13.7	S	0.00193 U	0.00539 U	0.00193 U	0.00478 U	0.000794 U	0.000520 U	0.000795 U	0.00174 U	0.00245 U	0.000735 U	0.000613 U	0.000857 U	0.00169 U
	MW-336-25	04/22/20	PES	PACE	25	8.7	S	0.00260 U	0.00724 U	0.00260 U	0.00642 U	0.00107 U	0.000700 U	0.00107 U	0.00234 U	0.00329 U	0.000988 U	0.000825 U	0.00115 U	0.00227 U
	MW-336-30	04/22/20	PES	PACE	30	3.7	S	0.00241 U	0.00670 U	0.00241 U	0.00594 U	0.000987 U	0.000647 U	0.000988 U	0.00216 U	0.00305 U	0.000914 U	0.000763 U	0.00107 U	0.00210 U
	MW-336-35	04/22/20	PES	PACE	35	-1.3	S	0.00194 U	0.00540 U	0.00194 U	0.00479 U	0.000795 U	0.000521 U	0.000796 U	0.00174 U	0.00245 U	0.000736 U	0.000615 U	0.000859 U	0.00169 U
	MW-336-40	04/22/20	PES	PACE	40	-6.3	S	0.00190 U	0.00530 UJ	0.00190 U	0.00470 U	0.000781 U	0.000512 U	0.000782 U	0.00171 U	0.00241 U	0.000723 U	0.000604 U	0.000844 U	0.00166 U
	MW-336-45	04/22/20	PES	PACE	45	-11.3	S	0.00210 U	0.00584 UJ	0.00210 U	0.00518 U	0.000861 U	0.000564 U	0.000862 U	0.00189 U	0.00266 U	0.000797 U	0.000665 U	0.000930 U	0.00183 U
	MW-336-51	04/22/20	PES	PACE	51	-17.3	S	0.00182 U	0.00507 UJ	0.00182 U	0.00449 U	0.000746 U	0.000489 U	0.000747 U	0.00163 U	0.00230 U	0.000691 U	0.000577 U	0.000806 U	0.00159 U
	MW-336-55	04/22/20	PES	PACE	55	-21.3	S	0.00180 U	0.00503 UJ	0.00180 U	0.00446 U	0.000740 U	0.000485 U	0.000741 U	0.00162 U	0.00228 U	0.000685 U	0.000572 U	0.000800 U	0.00158 U
	MW-336-60	04/22/20	PES	PACE	60	-26.3	S	0.00185 U	0.00516 UJ	0.00185 U	0.00458 U	0.000761 U	0.000499 U	0.000762 U	0.00167 U	0.00235 U	0.000704 U	0.000588 U	0.000822 U	0.00162 U
	MW-336-65	04/22/20	PES	PACE	65	-31.3	S	0.00184 U	0.00513 UJ	0.00184 U	0.00455 U	0.000756 U	0.000496 U	0.000757 U	0.00166 U	0.00233 U	0.000700 U	0.000584 U	0.000817 U	0.00161 U
	MW-336-69	04/22/20	PES	PACE	69	-35.3	S	0.00196 U	0.00547 UJ	0.00196 U	0.00485 U	0.000805 U	0.000528 U	0.000807 U	0.00177 U	0.00249 U	0.000746 U	0.000623 U	0.000870 U	0.00172 U
	MW-336-74.5	04/22/20	PES	PACE	74.5	-40.8	S	0.00184 U	0.00512 UJ	0.00184 U	0.00454 U	0.000754 U	0.000495 U	0.000755 U	0.00165 U	0.00233 U	0.000698 U	0.000583 U	0.000815 U	0.00161 U
	MW-336-79	04/22/20	PES	PACE	79	-45.3	S	0.00190 U	0.00528 UJ	0.00190 U	0.00468 U	0.000778 U	0.000510 U	0.000779 U	0.00170 U	0.00240 U	0.000720 U	0.000601 U	0.000840 U	0.00166 U
	MW-336-85	04/22/20	PES	PACE	85	-51.3	S	0.00190 U	0.00529 UJ	0.00190 U	0.00469 U	0.000779 U	0.000511 U	0.000780 U	0.00171 U	0.00240 U	0.000721 U	0.000602 U	0.000841 U	0.00166 U
	MW-2021-85	05/04/20	PES	PACE	85 (dup)	-51.3	S	0.00182 U	0.00507 U	0.00182 U	0.00449 U	0.000746 U	0.000489 U	0.000747 U	0.00163 U	0.00230 U	0.000691 U	0.000577 U	0.000806 U	0.00159 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
MW-336 (continued)	MW-336-90	04/22/20	PES	PACE	90	-56.3	S	0.00191 U	0.00531 UJ	0.00191 U	0.00470 U	0.000781 U	0.000512 U	0.000783 U	0.00171 U	0.00241 U	0.000723 U	0.000604 U	0.000844 U	0.00166 U
	MW-336-95	04/22/20	PES	PACE	95	-61.3	S	0.00190 U	0.00529 UJ	0.00190 U	0.00469 U	0.000779 U	0.000511 U	0.000780 U	**0.0341**	0.00240 U	0.000721 U	0.000602 U	0.000841 U	0.00166 U
	MW-2020-95	04/22/20	PES	PACE	95 (dup)	-61.3	S	0.00188 U	0.00524 UJ	0.00188 U	0.00464 U	0.000772 U	0.000506 U	0.000773 U	**0.0260**	0.00238 U	0.000714 U	0.000597 U	0.000834 U	0.00164 U
MW-338	MW-338-10	05/01/20	PES	PACE	10	17.8	S	0.00192 U	0.00534 U	0.00192 U	0.00473 U	0.000786 U	0.000515 U	0.000787 U	0.00172 U	0.00243 U	0.000728 U	0.000608 U	0.000849 U	0.00167 U
	MW-338-15	05/01/20	PES	PACE	15	12.8	S	0.00209 U	0.00582 U	0.00209 U	0.00516 U	0.000857 U	0.000562 U	0.000858 U	0.00188 U	0.00264 U	0.000793 U	0.000663 U	0.000926 U	0.00182 U
	MW-338-20	05/01/20	PES	PACE	20	7.8	S	0.00183 U	0.00510 U	0.00183 U	0.00452 U	0.000751 U	0.000493 U	0.000752 U	0.00165 U	0.00232 U	0.000695 U	0.000581 U	0.000811 U	0.00160 U
	MW-338-23	05/01/20	PES	PACE	23	4.8	S	0.00201 U	0.00559 U	0.00201 U	0.00496 U	0.000823 U	0.000540 U	0.000825 U	0.00180 U	0.00254 U	0.000762 U	0.000637 U	0.000890 U	0.00175 U
	MW-338-28	05/01/20	PES	PACE	28	-0.2	S	0.00199 U	0.00553 U	0.00199 U	0.00490 U	0.000815 U	0.000534 U	0.000816 U	0.00179 U	0.00252 U	0.000755 U	0.000630 U	0.000880 U	0.00174 U
	MW-338-34	05/01/20	PES	PACE	34	-6.2	S	0.00177 U	0.00492 U	**0.00182 J**	0.00436 U	0.000724 U	0.000475 U	0.000725 U	0.00159 U	0.00224 U	0.000671 U	0.000560 U	0.000782 U	0.00154 U
	MW-338-39	05/01/20	PES	PACE	39	-11.2	S	0.00191 U	0.00533 U	0.00191 U	0.00472 U	0.000785 U	0.000515 U	0.000786 U	0.00172 U	0.00242 U	0.000727 U	0.000607 U	0.000848 U	0.00167 U
	MW-338-41	05/01/20	PES	PACE	41	-13.2	S	0.00195 U	0.00542 U	0.00195 U	0.00481 U	0.000799 U	0.000524 U	0.000800 U	0.00175 U	0.00247 U	0.000740 U	0.000618 U	0.000863 U	0.00170 U
	MW-338-45	05/01/20	PES	PACE	45	-17.2	S	0.00193 U	0.00537 U	0.00193 U	0.00476 U	0.000791 U	0.000519 U	0.000792 U	0.00173 U	0.00244 U	0.000732 U	0.000612 U	0.000854 U	0.00168 U
	MW-338-51	05/01/20	PES	PACE	51	-23.2	S	0.00196 U	0.00545 U	0.00196 U	0.00483 U	0.000803 U	0.000527 U	0.000804 U	0.00176 U	0.00248 U	0.000744 U	0.000621 U	0.000868 U	0.00171 U
	MW-338-55	05/01/20	PES	PACE	55	-27.2	S	0.00181 U	0.00505 U	0.00181 U	0.00448 U	0.000744 U	0.000488 U	0.000745 U	0.00163 U	0.00230 U	0.000689 U	0.000575 U	0.000804 U	0.00158 U
MW-341	MW-341-85	05/04/20	PES	PACE	85	-56.6	S	0.00179 U	0.00500 U	0.00179 U	0.00443 U	0.000736 U	0.000483 U	0.000737 U	0.00161 U	0.00227 U	0.000682 U	0.000569 U	0.000795 U	0.00157 U
	MW-341-90	05/04/20	PES	PACE	90	-61.6	S	0.00178 U	0.00495 U	0.00178 U	0.00439 U	0.000729 U	0.000478 U	0.000730 U	0.00160 U	0.00225 U	0.000675 U	0.000564 U	0.000787 U	0.00155 U
	MW-341-95	05/04/20	PES	PACE	95	-66.6	S	0.00184 U	0.00513 U	0.00184 U	0.00454 U	0.000755 U	0.000495 U	0.000756 U	0.00165 U	0.00233 U	0.000699 U	0.000584 U	0.000816 U	0.00161 U
	MW-341-99	05/04/20	PES	PACE	99	-70.6	S	0.00185 U	0.00516 U	0.00185 U	0.00457 U	0.000760 U	0.000498 U	0.000761 U	0.00166 U	0.00234 U	0.000703 U	0.000587 U	0.000821 U	0.00162 U
	MW-341-104	05/04/20	PES	PACE	104	-75.6	S	0.00188 U	0.00525 U	0.00188 U	0.00465 U	0.000773 U	0.000507 U	0.000774 U	0.00169 U	0.00239 U	0.000716 U	0.000598 U	0.000835 U	0.00165 U
MW-343	MW-343-5	04/13/20	PES	PACE	5	22.6	V	**0.00293 J**	0.00497 U	**0.00503 J**	0.00441 U	0.000732 U	0.000480 U	0.000733 U	0.00160 U	**0.00291 J**	0.000678 U	0.000566 U	0.000791 U	0.00156 U
	MW-343-10	04/13/20	PES	PACE	10	17.6	S	0.00187 U	0.00521 U	0.00187 U	0.00462 U	0.000767 U	0.000503 U	0.000768 U	0.00168 U	0.00237 U	0.000710 U	0.000593 U	0.000829 U	0.00163 U
	MW-343-12.5	04/13/20	PES	PACE	12.5	15.1	S	0.00194 U	0.00540 U	0.00194 U	0.00479 U	0.000795 U	0.000521 U	0.000796 U	0.00174 U	0.00245 U	0.000736 U	0.000615 U	0.000859 U	0.00169 U
	MW-343-17	04/13/20	PES	PACE	17	10.6	S	0.00182 U	0.00506 U	0.00182 U	0.00449 U	0.000746 U	0.000489 U	0.000747 U	0.00163 U	0.00230 U	0.000690 U	0.000576 U	0.000805 U	0.00159 U
	MW-343-24	04/13/20	PES	PACE	24	3.6	S	**0.00201 J**	0.00507 U	0.00182 U	0.00450 U	0.000747 U	0.000490 U	0.000748 U	0.00164 U	0.00231 U	0.000692 U	0.000578 U	0.000807 U	0.00159 U
	MW-343-28.5	04/13/20	PES	PACE	28.5	-0.9	S	0.00195 U	0.00544 U	0.00195 U	0.00482 U	0.000802 U	0.000526 U	0.000803 U	0.00176 U	0.00247 U	0.000742 U	0.000620 U	0.000866 U	0.00171 U
	MW-343-35	04/13/20	PES	PACE	35	-7.4	S	0.00198 U	0.00551 U	0.00198 U	0.00488 U	0.000811 U	0.000532 U	0.000812 U	0.00178 U	0.00250 U	0.000751 U	0.000627 U	0.000876 U	0.00173 U
	MW-343-38	04/13/20	PES	PACE	38	-10.4	S	0.00185 U	0.00515 U	0.00185 U	0.00456 U	0.000758 U	0.000497 U	0.000759 U	0.00166 U	0.00234 U	0.000702 U	0.000586 U	0.000819 U	0.00161 U
	MW-343-44	04/13/20	PES	PACE	44	-16.4	S	0.00174 U	0.00485 U	0.00174 U	0.00430 U	0.000714 U	0.000468 U	0.000715 U	0.00157 U	0.00220 U	0.000661 U	0.000552 U	0.000772 U	0.00152 U
	MW-343-47	04/13/20	PES	PACE	47	-19.4	S	0.00197 U	0.00548 U	0.00197 U	0.00485 U	0.000807 U	0.000529 U	0.000808 U	0.00177 U	0.00249 U	0.000747 U	0.000624 U	0.000871 U	0.00172 U
	MW-343-51	04/13/20	PES	PACE	51	-23.4	S	0.00176 U	0.00490 U	0.00176 U	0.00434 U	0.000721 U	0.000473 U	0.000722 U	0.00158 U	0.00223 U	0.000668 U	0.000557 U	0.000779 U	0.00154 U
	MW-343-55	04/13/20	PES	PACE	55	-27.4	S	0.00180 U	0.00500 U	0.00180 U	0.00443 U	0.000737 U	0.000483 U	0.000738 U	0.00161 U	0.00227 U	0.000682 U	0.000570 U	0.000796 U	0.00157 U
	MW-343-62	04/13/20	PES	PACE	62	-34.4	S	0.00183 U	0.00509 U	0.00183 U	0.00451 U	0.000750 U	0.000492 U	0.000751 U	0.00164 U	0.00231 U	0.000694 U	0.000580 U	0.000810 U	0.00160 U
	MW-343-68	04/13/20	PES	PACE	68	-40.4	S	0.00180 U	0.00502 U	0.00180 U	0.00445 U	0.000739 U	0.000485 U	0.000740 U	0.00162 U	0.00228 U	0.000684 U	0.000571 U	0.000798 U	0.00157 U
	MW-343-73	04/13/20	PES	PACE	73	-45.4	S	0.00182 U	0.00507 U	0.00182 U	0.00449 U	0.000746 U	0.000490 U	0.000748 U	0.00164 U	0.00230 U	0.000691 U	0.000577 U	0.000806 U	0.00159 U
	MW-343-79	04/13/20	PES	PACE	79	-51.4	S	0.00171 U	0.00476 U	0.00171 U	0.00422 U	0.000702 U	0.000460 U	0.000703 U	0.00154 U	0.00217 U	0.000650 U	0.000543 U	0.000758 U	0.00149 U
	MW-343-82	04/13/20	PES	PACE	82	-54.4	S	0.00172 U	0.00478 U	0.00172 U	0.00423 U	0.000704 U	0.000461 U	0.000705 U	0.00154 U	0.00217 U	0.000652 U	0.000544 U	0.000760 U	0.00150 U
	MW-343-86	04/13/20	PES	PACE	86	-58.4	S	0.00167 U	0.00466 U	0.00167 U	0.00413 U	0.000686 U	0.000450 U	0.000687 U	0.00150 U	0.00212 U	0.000636 U	0.000531 U	0.000741 U	0.00146 U
	MW-343-93	04/13/20	PES	PACE	93	-65.4	S	0.00177 U	0.00493 U	0.00177 U	0.00437 U	0.000726 U	0.000476 U	0.000727 U	0.00159 U	0.00224 U	0.000672 U	0.000561 U	0.000784 U	0.00155 U
	MW-343-99	04/13/20	PES	PACE	99	-71.4	S	0.00170 U	0.00472 U	0.00170 U	0.00419 U	0.000696 U	0.000456 U	0.000697 U	0.00152 U	0.00215 U	0.000644 U	0.000538 U	0.000751 U	0.00148 U
	MW-343-102	04/14/20	PES	PACE	102	-74.4	S	0.00174 U	0.00485 UJ	0.00174 U	0.00430 UJ	0.000715 U	0.000469 U	0.000716 U	0.00157 U	0.00221 U	0.000662 U	0.000553 U	0.000772 UJ	0.00152 U
	MW-2017-102	04/14/20	PES	PACE	102 (dup)	-74.4	S	0.00173 U	0.00480 UJ	0.00173 U	0.00426 UJ	0.000708 U	0.000464 U	0.000709 U	0.00155 U	0.00218 U	0.000655 U	0.000547 U	0.000764 UJ	0.00151 U
	MW-343-106	04/14/20	PES	PACE	106	-78.4	S	0.00169 U	0.00472 UJ	**0.00309 J**	0.00418 UJ	0.000695 U	0.000456 U	0.000696 U	0.00152 U	0.00214 U	0.000643 U	0.000537 U	0.000750 UJ	0.00148 U
	MW-343-108	04/14/20	PES	PACE	108	-80.4	S	0.00175 U	0.00488 UJ	**0.00182 J**	0.00432 UJ	0.000718 U	0.000471 U	0.000719 U	0.00157 U	0.00222 U	0.000665 U	0.000555 U	0.000776 UJ	0.00153 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	**–**	**0.88**	**1.2**	**–**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	**–**	**0.058**	**0.068**	**–**
PH22	PH22	04/17/18	PES	Fremont	0-3	–	V	–	0.0304 U	0.0243 U	0.608 UJ	0.00608 U	0.0243 U	0.0243 U	0.0243 U	0.0304 U	0.0243 U	0.0304 U	0.0243 U	0.122 UJ
PH34	PH34	04/17/18	PES	Fremont	1.5-6.5	–	V	–	0.0240 U	0.0192 U	0.481 UJ	0.00481 U	0.0192 U	0.0192 U	0.0192 U	0.0240 U	0.0192 U	0.0240 U	0.0192 U	0.0962 UJ
PH38	PH38	04/17/18	PES	Fremont	1.5-4	–	V	–	0.0292 U	0.0233 U	0.583 UJ	0.00583 U	0.0233 U	0.0233 U	0.0233 U	0.0292 U	0.0233 U	0.0292 U	0.0233 U	0.117 UJ
PH52	PH52	04/17/18	PES	Fremont	1-5	–	V	–	0.0282 U	0.0226 U	0.564 UJ	0.00564 U	0.0226 U	0.0226 U	0.0226 U	0.0282 U	0.0226 U	0.0282 U	0.0226 U	0.113 UJ
PW-1	Composite	01/01/98	B&V	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
PW-4	Composite	05/13/98	B&V	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
R-MW4	Unknown	10/22/92	Roux	Unknown	5	35.9	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	Unknown	10/22/92	Roux	Unknown	15	25.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	Unknown	10/22/92	Roux	Unknown	30	10.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
R-MW6	Unknown	10/27/92	Roux	Unknown	6	39.3	V	–	–	–	–	–	–	–	–	–	–	–	–	–
(33.3 to 23.3)	Unknown	10/27/92	Roux	Unknown	11	34.3	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	Unknown	10/27/92	Roux	Unknown	16	29.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
RB1	RB1-17.5	10/18/93	Retec	AAL	17.5	18.4	S	–	–	–	–	–	–	–	–	–	–	–	–	–
RB2	RB2-12.5	10/18/93	Retec	AAL	12.5	23.6	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	RB2-17.5	10/18/93	Retec	AAL	17.5	18.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–
RB3	RB3-17.5	10/18/93	Retec	AAL	17.5	20.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
SCL-B100	B-100, S1	06/10/02	Urban	F&BI	5-6.5	–	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	B-100, S2	06/10/02	Urban	F&BI	10-11.5	–	V	–	–	–	–	–	–	–	–	–	–	–	–	–
SCL-B101	B-101- S1&2	06/17/02	Urban	F&BI	0-6	–	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	B101-S3	06/17/02	Urban	F&BI	8	–	V	–	–	–	–	–	–	–	–	–	–	–	–	–
SCL-B102	B102-S1	06/17/02	Urban	F&BI	0-3	–	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-S2	06/17/02	Urban	F&BI	4	–	V	–	–	–	–	–	–	–	–	–	–	–	–	–
SCL-MW101	MW101-S3	06/14/02	Urban	F&BI	16	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
(25.0 to 15.0)																				
SCL-MW102	MW-102, S1	06/10/02	Urban	F&BI	5-6.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW-102, S2	06/10/02	Urban	F&BI	5-6.5, 10-11.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
SCL-MW103	MW103-S1&S2	06/14/02	Urban	F&BI	5-6.5, 10-11.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
SCL-MW105	MW-105, S2	06/10/02	Urban	F&BI	10-11.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
(10.8 to 0.8)	MW-105, S4	06/10/02	Urban	F&BI	20-21.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
SCLB-1	RS1-2.5/RS-1 7.5 (Comp)	03/12/93	EPJ	OnSite	2.5-7.5	–	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS1-12.5/RS1-17.5 (Comp)	03/12/93	EPJ	OnSite	12.5-17.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS-1 17.5	03/12/93	EPJ	OnSite	17.5	21.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS1-22.5/RS-27.5 (Comp)	03/12/93	EPJ	OnSite	22.5-27.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS1-32.5	03/12/93	EPJ	OnSite	32.5	6.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS1-37.5	03/12/93	EPJ	OnSite	37.5	1.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
SCLB-2	RS2-2.5/RS-2 7.5 (Comp)	03/12/93	EPJ	OnSite	2.5-7.5	–	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS2-12.5/RS2-17.5 (Comp)	03/12/93	EPJ	OnSite	12.5-17.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS2-17.5	03/12/93	EPJ	OnSite	17.5	21.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS2-22.5/RS2-27.5 (Comp)	03/12/93	EPJ	OnSite	22.5-27.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS2-32.5	03/12/93	EPJ	OnSite	32.5	6.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS2-37.5	03/12/93	EPJ	OnSite	37.5	1.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	**–**	**0.88**	**1.2**	**–**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	**–**	**0.058**	**0.068**	**–**
SSD-MW-1	MW-1 S-2	05/24/89	HC	Unknown	5-6.5	34.0	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW-1 S-6	05/24/89	HC	Unknown	15-16.5	24.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
SSD-MW-2	MW-2 S-3	05/24/89	HC	Unknown	7.5-9	31.0	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW-2 S-6	05/24/89	HC	Unknown	15-16.5	31.0	V	–	–	–	–	–	–	–	–	–	–	–	–	–
SSD-MW-3	MW-3 S-2	05/24/89	HC	Unknown	5-6.5	34.0	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW-3 S-5	05/24/89	HC	Unknown	12.5-14	34.0	V	–	–	–	–	–	–	–	–	–	–	–	–	–
SSD-MW-4	MW-4 S-6	05/25/89	HC	Unknown	14.5-16	36.8	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW-4 S-9	05/25/89	HC	Unknown	22-23	29.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
SV-04	SV-04-6	06/29/20	PES	PACE	6	–	V	0.00205 U	0.00570 U	0.00205 U	0.00505 UJ	0.000840 U	0.000551 U	0.000841 U	0.00184 U	0.00259 U	0.000778 U	0.000649 U	0.000907 U	0.00179 U
SV-05	SV-05-10	06/29/20	PES	PACE	10	–	V	0.00219 U	0.00609 UJ	0.00219 U	0.00540 UJ	0.000897 U	0.000588 UJ	0.000899 U	0.00197 U	0.00277 U	0.000831 U	0.000694 U	0.000969 U	0.00191 U
SV-06	SV-06-6	06/29/20	PES	PACE	6	–	V	0.00202 U	0.00561 UJ	0.00202 U	0.00498 UJ	0.000827 U	0.000542 UJ	0.000828 U	0.00181 U	0.00255 U	0.000765 U	0.000639 U	0.000893 U	0.00176 U
SV-07	SV-07-15	06/29/20	PES	PACE	15	–	V	0.00173 U	0.00482 UJ	0.00173 U	0.00427 UJ	0.000710 U	0.000466 UJ	0.000711 U	0.00156 U	0.00219 U	**0.000792 J**	0.000549 U	0.000767 U	0.00151 U
SV-08	SV-08-6	06/30/20	PES	PACE	6	–	V	**0.00254 J**	0.00612 UJ	**0.00261 J**	0.00542 UJ	0.000901 U	**0.00307 J**	0.000902 U	0.00197 U	0.00278 U	0.000834 U	0.000697 U	0.000973 U	0.00192 U
	SV-08-7.5	06/30/20	PES	PACE	7.5	–	V	0.00224 U	0.00624 U	0.00224 U	0.00553 UJ	0.000918 U	0.000602 U	0.000920 U	0.00201 U	0.00283 U	0.000850 U	0.000710 U	0.000992 U	0.00196 U
SV-09	SV-09-5.5	07/01/20	PES	PACE	5.5	–	V	0.00209 U	0.00582 U	0.00209 U	0.00516 UJ	0.000858 U	0.000563 U	0.000859 U	0.00188 U	0.00265 U	0.000794 U	0.000663 U	0.000926 U	0.00183 U
SV-10	SV-10-5.5	06/30/20	PES	PACE	5.5	–	V	0.00208 U	0.00580 U	0.00208 U	0.00514 UJ	0.000854 U	0.000560 U	0.000856 U	0.00187 U	0.00264 U	0.000791 U	0.000660 U	0.000923 U	0.00182 U
SV-11	SV-11-10	06/30/20	PES	PACE	10	–	V	0.00211 U	0.00588 U	0.00211 U	0.00521 UJ	0.000866 U	0.000568 U	0.000868 U	0.00190 U	0.00267 U	0.000802 U	0.000670 U	0.000936 U	0.00185 U
SV-12	SV-12-5.5	07/01/20	PES	PACE	5.5	–	V	0.00173 U	0.00481 U	0.00173 U	0.00426 UJ	0.000708 U	0.000465 U	0.000710 U	0.00155 U	0.00219 U	0.000656 U	0.000548 U	0.000765 U	0.00151 U
SV-13	SV-13-10.5	07/01/20	PES	PACE	10.5	–	V	0.00203 U	0.00564 U	0.00203 U	0.00500 UJ	0.000831 U	0.000545 U	0.000832 U	0.00182 U	0.00256 U	0.000769 U	0.000643 U	0.000898 U	0.00177 U
SV-14	SV-14-5.5	07/01/20	PES	PACE	5.5	–	V	0.00211 U	0.00588 U	0.00211 U	0.00521 UJ	0.000866 U	0.000568 U	0.000868 U	0.00190 U	0.00267 U	0.000802 U	0.000670 U	0.000936 U	0.00184 U
SV-15	SV-15-13	07/01/20	PES	PACE	13	–	V	0.00205 U	0.00571 U	0.00205 U	0.00506 UJ	0.000841 U	0.000552 U	0.000842 U	0.00184 U	0.00260 U	0.000779 U	0.000650 U	0.000908 U	0.00179 U
SV-16	SV-16-5	07/02/20	PES	PACE	5	–	V	**0.0321**	0.0117 U	**0.0356 J**	0.0104 UJ	0.00172 U	0.00113 U	0.00172 U	0.00377 U	**0.0206**	0.00159 U	0.00133 U	0.00186 U	0.00366 U
	SV-100-5	07/02/20	PES	PACE	5 (dup)	–	V	**0.0137 J**	0.0104 U	**0.0166**	0.00925 UJ	0.00154 U	0.00101 U	0.00154 U	0.00338 U	**0.0160**	0.00143 U	0.00119 U	0.00166 U	0.00327 U
SV-17	SV-17-4.5	07/02/20	PES	PACE	4.5	–	V	**0.0567**	0.00865 U	**0.0586**	0.00767 UJ	0.00127 U	0.000835 U	0.00128 U	0.00278 U	**0.0278**	0.00118 U	0.000985 U	0.00138 U	0.00271 U
SV-18	SV-18-5.5	07/02/20	PES	PACE	5.5	–	V	0.00170 U	0.00474 U	0.00170 U	0.00420 UJ	0.000698 U	0.000458 U	0.000699 U	0.00153 U	0.00216 U	0.000647 U	0.000540 U	0.000754 U	0.00149 U
SV-19	SV-19-5	07/09/20	PES	PACE	5	–	V	0.00170 U	0.00474 U	0.00170 U	0.00420 U	0.000698 U	0.000458 U	0.000699 U	0.00153 U	0.00215 U	0.000646 U	0.000540 U	0.000754 U	0.00149 U
SV-20	SV-20-9	07/09/20	PES	PACE	9	–	V	0.00224 U	0.00623 U	0.00224 U	0.00552 U	0.000917 U	0.000602 U	0.000919 U	0.00201 U	0.00283 U	0.000849 U	0.000709 U	0.000991 U	0.00195 U
SV-21	SV-21-6	07/09/20	PES	PACE	6	–	V	0.00173 U	0.00482 U	0.00173 U	0.00427 U	0.000710 U	0.000466 U	0.000711 U	0.00156 U	0.00219 U	0.000658 U	0.000549 U	0.000767 U	0.00151 U
SV-22	SV-22-8.5	07/09/20	PES	PACE	8.5	–	V	**0.00489 J**	0.00898 U	**0.00495 J**	0.00796 U	0.00132 U	0.000869 U	0.00133 U	0.00291 U	0.00409 U	0.00123 U	0.00102 U	0.00143 U	0.00281 U
SV-23	SV-23-4.5	07/09/20	PES	PACE	4.5	–	V	0.00239 U	0.00665 U	0.00239 U	0.00590 U	0.000980 U	0.000643 U	0.000981 U	0.00215 U	0.00302 U	0.000907 U	0.000757 U	0.00106 U	0.00209 U
SV-24	SV-24-8	07/09/20	PES	PACE	8	–	V	0.00172 U	0.00478 U	0.00172 U	0.00423 U	0.000703 U	0.000461 U	0.000705 U	0.00154 U	0.00217 U	0.000651 U	0.000544 U	0.000760 U	0.00150 U
SV-25	SV-25-4	07/10/20	PES	PACE	4	–	V	0.00208 U	0.00580 U	0.00208 U	0.00514 U	0.000853 U	0.000560 U	0.000855 U	0.00187 U	0.00263 U	0.000790 U	0.000660 U	0.000922 U	0.00182 U
SV-26	SV-26-12	07/10/20	PES	PACE	12	–	V	0.00231 U	0.00644 U	0.00231 U	0.00571 U	0.000948 U	0.000622 U	0.000950 U	0.00208 U	0.00293 U	0.000878 U	0.000733 U	0.00102 U	0.00202 U
SV-27	SV-27-5.5	07/10/20	PES	PACE	5.5	–	V	0.00207 U	0.00577 U	0.00207 U	0.00512 U	0.000850 U	0.000558 U	0.000852 U	0.00186 U	0.00262 U	0.000787 U	0.000657 U	0.000919 U	0.00181 U
	SV-27-13.5	07/10/20	PES	PACE	13.5	–	V	0.00208 U	0.00578 U	0.00208 U	0.00512 U	0.000851 U	0.000558 U	0.000853 U	0.00187 U	0.00263 U	0.000788 U	0.000658 U	0.000920 U	0.00181 U
TB-12	16	08/01/97	B&V	Unknown	62-63	-24.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
TB-18	S-2	03/17/98	B&V	Unknown	5-6.5	38.3	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	S-8	03/17/98	B&V	Unknown	20-21.5	23.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	S-21	03/17/98	B&V	Unknown	57.5-59	1.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	**–**	**0.88**	**1.2**	**–**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	**–**	**0.058**	**0.068**	**–**
T1	T1-2.5-071718	07/17/18	PES	Fremont	2.5	–	V	–	0.0265 U	0.0212 U	0.531 U	0.00531 U	0.0212 U	0.0212 U	0.0212 U	0.0265 U	0.0212 U	0.0265 U	0.0212 U	0.106 U
T-2	T-2-071618	07/16/18	PES	Fremont	2	–	V	–	0.0143 U	0.0115 U	0.287 U	0.00287 U	0.0115 U	0.0115 U	0.0115 U	0.0143 U	0.0115 U	0.0143 U	0.0115 U	0.0573 U
T-2B	T-2B-071618	07/16/18	PES	Fremont	2	–	V	–	0.0297 U	0.0237 U	0.593 U	0.00593 U	0.0237 U	0.0237 U	0.0237 U	0.0297 U	0.0237 U	0.0297 U	0.0237 U	0.119 U
T2	T2-6-071718	07/17/18	PES	Fremont	6	–	V	–	0.0307 U	0.0245 U	0.614 U	0.00614 U	0.0245 U	0.0245 U	0.0245 U	0.0307 U	0.0245 U	0.0307 U	0.0245 U	0.123 U
T3	T3-3-071718	07/17/18	PES	Fremont	3	–	V	–	0.0287 U	0.0229 U	0.573 U	0.00573 U	0.0229 U	0.0229 U	0.0229 U	0.0287 U	0.0229 U	0.0287 U	0.0229 U	0.115 U
T4	T4-6-071718	07/17/18	PES	Fremont	6	–	V	–	0.0258 U	0.0206 U	0.516 U	0.00516 U	0.0206 U	0.0206 U	0.0206 U	0.0258 U	0.0206 U	0.0258 U	0.0206 U	0.103 U
T-5	T-5-071618	07/16/18	PES	Fremont	5	–	V	–	0.0255 U	0.0204 U	0.509 U	0.00509 U	0.0204 U	0.0204 U	0.0204 U	0.0255 U	0.0204 U	0.0255 U	0.0204 U	0.102 U
T6	T6-4-071818	07/18/18	PES	Fremont	4	–	V	–	0.0237 U	**0.0217**	0.474 U	0.00474 U	0.0189 U	0.0189 U	0.0189 U	0.0237 U	0.0189 U	0.0237 U	0.0189 U	0.0947 U
T7	T7-7-071818	07/18/18	PES	Fremont	7	–	V	–	0.0342 U	**0.0332**	0.684 U	0.00684 U	0.0274 U	0.0274 U	0.0274 U	0.0342 U	0.0274 U	0.0342 U	0.0274 U	0.137 U
T8	T8-3-072018	07/20/18	PES	Fremont	3	–	V	–	0.0268 U	0.0214 U	0.536 U	0.00536 U	0.0214 U	0.0214 U	0.0214 U	0.0268 U	0.0214 U	0.0268 U	0.0214 U	0.107 U
T8	T8-6-072018	07/20/18	PES	Fremont	6	–	V	–	0.0377 U	0.0301 U	0.753 U	0.00753 U	0.0301 U	0.0301 U	0.0301 U	0.0377 U	0.0301 U	0.0377 U	0.0301 U	0.151 U
T9	T9-3-072018	07/20/18	PES	Fremont	3	–	V	–	0.0437 U	0.0350 U	0.875 U	0.00875 U	0.0350 U	0.0350 U	0.0350 U	0.0437 U	0.0350 U	0.0437 U	0.0350 U	0.175 U
T9	T9-3.5-072018	07/20/18	PES	Fremont	3.5	–	V	–	0.0291 U	0.0233 U	0.583 U	0.00583 U	0.0233 U	0.0233 U	0.0233 U	0.0291 U	0.0233 U	0.0291 U	0.0233 U	0.117 U
T9	T9-6-072018	07/20/18	PES	Fremont	6	–	V	–	0.0303 U	0.0242 U	0.605 U	0.00605 U	0.0242 U	0.0242 U	0.0242 U	0.0303 U	0.0242 U	0.0303 U	0.0242 U	0.121 U
T10	T10-3-072018	07/20/18	PES	Fremont	3	–	V	–	0.0513 U	0.0411 U	1.03 U	0.0103 U	0.0411 U	0.0411 U	0.0411 U	0.0513 U	0.0411 U	0.0513 U	0.0411 U	0.205 U
T10	T10-6-072018	07/20/18	PES	Fremont	6	–	V	–	0.0278 U	**0.0303**	0.556 U	0.00556 U	0.0222 U	0.0222 U	0.0222 U	0.0278 U	0.0222 U	0.0278 U	0.0222 U	0.111 U
T11	T11-3.5-073118	07/31/18	PES	Fremont	3.5	–	V	–	0.0358 U	0.0286 U	0.716 U	0.00716 U	0.0286 U	0.0286 U	0.0286 U	0.0358 U	0.0286 U	0.0358 U	0.0286 U	0.143 U
T12	T12-3-091818	09/18/18	PES	Fremont	3	–	V	–	0.0307 U	0.0245 U	0.614 U	0.00614 U	0.0245 U	0.0245 U	0.0245 U	0.0307 U	0.0245 U	0.0307 U	0.0245 U	0.123 UJ
T12	T12-7-091818	09/18/18	PES	Fremont	7	–	V	–	0.0303 U	0.0243 U	0.607 U	0.00607 U	0.0243 U	0.0243 U	0.0243 U	0.0303 U	0.0243 U	0.0303 U	0.0243 U	0.121 UJ
T12	T12-7.5-073118	07/31/18	PES	Fremont	7.5	–	V	–	0.0259 U	0.0207 U	0.519 U	0.00519 U	0.0207 U	0.0207 U	0.0207 U	0.0259 U	0.0207 U	0.0259 U	0.0207 U	0.104 U
T13	T13-3.5-091818	09/18/18	PES	Fremont	3.5	–	V	–	0.0283 U	0.0227 U	0.567 U	0.00567 U	0.0227 U	0.0227 U	0.0227 U	0.0283 U	0.0227 U	0.0283 U	0.0227 U	0.113 UJ
T13	T13-6.5-091818	09/18/18	PES	Fremont	6.5	–	V	–	0.0250 U	0.0200 U	0.500 U	0.00500 U	0.0200 U	0.0200 U	0.0200 U	0.0250 U	0.0200 U	0.0250 U	0.0200 U	0.100 UJ
T14	T14-3.5-091818	09/18/18	PES	Fremont	3.5	–	V	–	0.0300 U	0.0240 U	0.599 U	0.00599 U	0.0240 U	0.0240 U	0.0240 U	0.0300 U	0.0240 U	0.0300 U	0.0240 U	0.120 UJ
T14	T14-7-091818	09/18/18	PES	Fremont	7	–	V	–	0.0318 U	0.0254 U	0.635 U	0.00635 U	0.0254 U	0.0254 U	0.0254 U	0.0318 U	0.0254 U	0.0318 U	0.0254 U	0.127 UJ
TP-15	TP-15-3-092818	09/28/18	PES	Fremont	3	–	V	–	0.0304 U	0.0244 U	0.609 U	0.00609 U	0.0244 U	0.0244 U	0.0244 U	0.0304 U	0.0244 U	0.0304 U	0.0244 U	0.122 U
TP-15	TP-15-6.5-092818	09/28/18	PES	Fremont	6.5	–	V	–	0.0313 U	0.0250 U	0.625 U	0.00625 U	0.0250 U	0.0250 U	0.0250 U	0.0313 U	0.0250 U	0.0313 U	0.0250 U	0.125 U
TP-16	TP-16-3-092818	09/28/18	PES	Fremont	3	–	V	–	0.0426 U	0.0341 U	0.852 U	0.00852 U	0.0341 U	0.0341 U	0.0341 U	0.0426 U	0.0341 U	0.0426 U	0.0341 U	0.170 U
TP-16	TP-16-6-092818	09/28/18	PES	Fremont	6	–	V	–	0.0446 U	0.0357 U	0.892 U	0.00892 U	0.0357 U	0.0357 U	0.0357 U	0.0446 U	0.0357 U	0.0446 U	0.0357 U	0.178 U
TP-16	TP-16-9-092818	09/28/18	PES	Fremont	9	–	V	–	0.0263 U	0.0210 U	0.525 U	0.00525 U	0.0210 U	0.0210 U	0.0210 U	0.0263 U	0.0210 U	0.0263 U	0.0210 U	0.105 U
TP-SD-01	TP-SD-01-2	06/03/19	PES	Fremont	2	–	V	–	0.0214 U	**0.0709**	0.429 U	0.00429 U	0.0172 U	0.0172 U	0.0172 U	**0.0326**	0.0172 U	0.0214 U	0.0172 U	0.0858 U
TP-SD-01	TP-SD-01-5	06/03/19	PES	Fremont	5	–	V	–	0.0267 U	0.0213 U	0.534 U	0.00534 U	0.0213 U	0.0213 U	0.0213 U	0.0267 U	0.0213 U	0.0267 U	0.0213 U	0.107 U
TP-SD-04	TP-SD-04-2	06/03/19	PES	Fremont	2	–	V	–	0.0252 U	0.0202 U	0.504 U	0.00504 U	0.0202 U	0.0202 U	0.0202 U	0.0252 U	0.0202 U	0.0252 U	0.0202 U	0.101 U
TP-SD-04	TP-SD-04-5	06/03/19	PES	Fremont	5	–	V	–	0.0272 U	0.0218 U	0.544 U	0.00544 U	0.0218 U	0.0218 U	0.0218 U	0.0272 U	0.0218 U	0.0272 U	0.0218 U	0.109 U
TP-SD-05	TP-SD-05-2	06/03/19	PES	Fremont	2	–	V	–	0.0258 U	0.0207 U	0.517 U	0.00517 U	0.0207 U	0.0207 U	0.0207 U	0.0258 U	0.0207 U	0.0258 U	0.0207 U	0.103 U
TP-SD-05	TP-SD-05-5	06/03/19	PES	Fremont	5	–	V	–	0.0292 U	0.0234 U	0.585 U	0.00585 U	0.0234 U	0.0234 U	0.0234 U	0.0292 U	0.0234 U	0.0292 U	0.0234 U	0.117 U
TP-SD-06	TP-SD-06-2	06/03/19	PES	Fremont	2	–	V	–	0.0344 U	0.0275 U	0.688 U	0.00688 U	0.0275 U	0.0275 U	0.0275 U	0.0344 U	0.0275 U	0.0344 U	0.0275 U	0.138 U
TP-SD-06	TP-SD-06-5	06/03/19	PES	Fremont	5	–	V	–	0.0272 U	0.0218 U	0.544 U	0.00544 U	0.0218 U	0.0218 U	0.0218 U	0.0272 U	0.0218 U	0.0272 U	0.0218 U	0.109 U
TP-SD-07	TP-SD-07-2	06/03/19	PES	Fremont	2	–	V	–	0.0217 U	0.0174 U	0.435 U	0.00435 U	0.0174 U	0.0174 U	0.0174 U	0.0217 U	0.0174 U	0.0217 U	0.0174 U	0.0869 U
TP-SD-07	B-942-2	06/03/19	PES	Fremont	2 (dup)	–	V	–	0.0233 U	0.0186 U	0.466 U	0.00466 U	0.0186 U	0.0186 U	0.0186 U	0.0233 U	0.0186 U	0.0233 U	0.0186 U	0.0932 U
TP-SD-07	TP-SD-07-5	06/03/19	PES	Fremont	5	–	V	–	0.0212 U	0.0169 U	0.424 U	0.00424 U	0.0169 U	0.0169 U	0.0169 U	0.0212 U	0.0169 U	0.0212 U	0.0169 U	0.0847 U
TP-SD-08	TP-SD-08-2	06/03/19	PES	Fremont	2	–	V	–	0.0242 U	0.0193 U	0.483 U	0.00483 U	0.0193 U	0.0193 U	0.0193 U	0.0242 U	0.0193 U	0.0242 U	0.0193 U	0.0966 U
TP-SD-08	TP-SD-08-5	06/03/19	PES	Fremont	5	–	V	–	0.0207 U	0.0166 U	0.415 U	0.00415 U	0.0166 U	0.0166 U	0.0166 U	0.0207 U	0.0166 U	0.0207 U	0.0166 U	0.0829 U
TP-SD-08	TP-SD-08-8	06/03/19	PES	Fremont	8	–	S	–	0.0249 U	0.0199 U	0.498 U	0.00498 U	0.0199 U	0.0199 U	0.0199 U	0.0249 U	0.0199 U	0.0249 U	0.0199 U	0.0995 U
W-MW-01 (P-03)	SB-W-03-0160	01/27/12	WW	ARI	16-16.5	28.4	S	–	–	–	–	–	–	–	–	–	–	–	–	–
(-25.1 to -35.1)	SB-W-03-0225	01/27/12	WW	ARI	22.5-23	21.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-03-0315	01/27/12	WW	ARI	31.5-32	12.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-03-0450	01/27/12	WW	ARI	45-45.5	-0.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-03-0550	01/27/12	WW	ARI	55.5-56	-11.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	**–**	**0.88**	**1.2**	**–**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**0.000081**	**0.000018**	**0.4**	**0.004**	**0.009**	**0.071**	**–**	**0.058**	**0.068**	**–**
W-MW-01 (P-03)	SB-W-03-0645	01/27/12	WW	ARI	64.5-65	-20.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
(continued)	SB-W-03-0730	01/27/12	WW	ARI	73-73.5	-28.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–
W-MW-02 (P-06)	SB-W-06-0900	01/29/12	WW	ARI	9-9.5	34.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
(-26.5 to -36.5)	SB-W-06-0185	01/29/12	WW	ARI	18.5-19	24.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-06-0305	01/30/12	WW	ARI	30.5-31	12.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-06-0380	01/30/12	WW	ARI	38-38.5	5.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-06-0405	01/30/12	WW	ARI	40.5-41	2.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-06-0485	01/30/12	WW	ARI	48.5-49	-5.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-06-9485	01/30/12	WW	ARI	48.5-49 (dup)	-5.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-06-0590	01/30/12	WW	ARI	59-59.5	-16.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-06-0715	01/30/12	WW	ARI	71.5-72	-28.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-06-0790	01/31/12	WW	ARI	79-79.5	-36.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
All Data							Number of Analytes Measured	598	644	644	644	644	644	644	644	644	644	644	644	644
							Number of Analytes Detected	64	4	81	0	0	5	1	2	41	3	0	4	0
							Frequency of Detection	10.7%	0.6%	12.6%	0.0%	0.0%	0.8%	0.2%	0.3%	6.4%	0.5%	0.0%	0.6%	0.0%
							Maximum Detection	0.512	0.0271	0.159 J	–	–	0.196	0.0128	0.0341	0.33	0.0133 J	–	0.0559	–
							Minimum Detection	0.0003 U	0.000403 U	0.000221 U	0.00109 U	0.000356 U	0.000317 U	0.000275 U	0.000372 U	0.000278 U	0.000248 U	0.000215 U	0.000235 U	0.00029 U
							Number Of Vadose (V) Detections above SL	0	0	0	0	0	0	0	0	0	–	0	0	–
							Number of Saturated (S) Detections above SL	5	0	1	0	0	0	1	1	1	–	0	0	–
2017-2021							Number of Analytes Measured	598	644	644	644	644	644	644	644	644	644	644	644	644
							Number of Analytes Detected	64	4	81	0	0	5	1	2	41	3	0	4	0
							Frequency of Detection	10.7%	0.6%	12.6%	0.0%	0.0%	0.8%	0.2%	0.3%	6.4%	0.5%	0.0%	0.6%	0.0%
							Maximum Detection	0.512	0.0271	0.159 J	–	–	0.196	0.0128	0.0341	0.33	0.0133 J	–	0.0559	–
							Minimum Detection	0.0003 U	0.000403 U	0.000221 U	0.00109 U	0.000356 U	0.000317 U	0.000275 U	0.000372 U	0.000278 U	0.000248 U	0.000215 U	0.000235 U	0.00029 U
							Number Of Vadose (V) Detections above SL	0	0	0	0	0	0	0	0	0	–	0	0	–
							Number of Saturated (S) Detections above SL	5	0	1	0	0	0	1	1	1	–	0	0	–

Abbreviations:
AAL = Alden Analytical Laboratories, Inc., of Seattle, Washington
ARI = Analytical Resource, Incorporated, Seattle, Washington
B&V = Black Veatch
bgs = below ground surface
Comp = Composite Sample
dup = duplicate
EPJ = E.PJohnson Construction Inc., and Environmental
ESC = ESC Lab Services of Mt. Juliet, Tennessee
F&BI = Friedman & Bruya, Inc.
HC = Hart Crowser, Inc.
OnSite = OnSite Environmental Inc., of Redmond, Washington
Pace = Pace Analytical of Mt. Juliet, Tennessee (formerly ESC)
PES = PES Environmental, Inc.
Retec = Remediation Technologies, Inc.
Roux = Roux Associates
Urban = Urban Redevelopment LLC
WW = WW Environmental LLC

Notes:
Petroleum Hydrocarbons (PHCs) analyzed by Ecology Methods NWTPH-HCID, NWTPH-Gx, or NWTPH-Dx; or EPA Method 418.1, Method 8020, or Method 8015M.
VOCs analyzed by EPA Methods 8010, 8020, 8021B, 624/8240, or 8260B/C/D.
Well screen elevations provided below Sample Location. in parentheses when appliable.
PCUL = Preliminary Cleanup Level from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021. PCULs based on the practical quantitation limits (PQLs) italicized.
Detected results shown in **bold**.
Detections above the screening level in the vadose zone are shown in **bold and highlighted blue**.
Detections above the screening level in the saturated zone are shown in **bold and highlighted gray.**
– = Not available or results not analyzed.
B = Analyte detected in an associated method blank.
J = The reported concentration is an estimate based on detectable results between the method detection limit and reporting limit, laboratory QA/QC, or data validation review.
J+ = The result is an estimated quantity, but the result may be biased high.
J- = The result is an estimated quantity, but the result may be biased low.
ND = Not detected above laboratory reporting limit. Reporting limit not available.
R = The data is unusable. The sample result is rejected due to serious deficiencies in meeting QC criteria. The analyte may or may not be present in the sample
T = Analyte also detected in trip blank.
U = Not detected at a concentration exceeding laboratory reporting limit
ve = Estimated value. The reported range exceeds the calibration range of the analysis.
z = Gasoline/petroleum detection result is likely elevated due to high detections of CVOCs.

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
B-1A	B-1/S-2	12/01/89	HC	ARI	10.5	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
B-2A	B-2/S-1	12/01/89	HC	ARI	10	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
B-212	B-212-15	09/08/17	PES	ESC	15	42.6	V	0.00539 U	0.000347 U	0.00158 U	0.000276 U	0.000235 U	**0.0129 J**	0.00206 U	0.000311 U	0.000327 U	0.000449 U	0.000488 U	0.00154 U	0.000255 U
	B-212-21	09/08/17	PES	ESC	21	36.6	S	**0.0148**	0.000313 U	0.00142 U	0.000249 U	**0.00256**	**0.0605 J**	0.00186 U	**0.000346 J**	0.000295 U	0.000405 U	0.000441 U	0.00139 U	**0.00174**
	B-212-35	09/08/17	PES	ESC	35	22.6	S	0.00510 U	0.000328 U	0.00149 U	0.000262 U	0.000222 U	0.0109 U	0.00195 U	0.000294 U	0.000310 U	0.000425 U	0.000462 U	0.00146 U	**0.000626 J**
	B-212-45	09/08/17	PES	ESC	45	12.6	S	**0.00512 J**	0.000315 U	0.00143 U	0.000251 U	0.000213 U	**0.0221 J**	0.00187 U	**0.000303 J**	0.000297 U	0.000408 U	0.000444 U	0.00140 U	**0.00195**
	B-907-25	09/08/17	PES	ESC	45 (dup)	12.6	S	0.140 U	0.00899 U	0.0409 U	0.00717 U	0.00610 U	0.299 U	0.0536 U	0.00807 U	0.00849 U	0.0117 U	0.0127 U	0.0400 U	0.00660 U
	B-212-55	09/08/17	PES	ESC	55	2.6	S	0.00528 U	0.000340 U	0.00155 U	0.000271 U	0.000230 U	0.0113 U	0.00202 U	0.000305 U	0.000320 U	0.000440 U	0.000478 U	0.00151 U	**0.000278 J**
	B-212-65	09/08/17	PES	ESC	65	-7.4	S	0.00543 U	0.000349 U	0.00159 U	0.000279 U	0.000237 U	0.0116 U	0.00208 U	0.000313 U	0.000330 U	0.000453 U	0.000492 U	0.00156 U	**0.00107 J**
	B-212-75	09/08/17	PES	ESC	75	-17.4	S	0.00544 U	0.000350 U	0.00159 U	0.000279 U	0.000237 U	0.0116 U	0.00208 U	0.000314 U	0.000330 U	0.000454 U	0.000493 U	0.00156 U	**0.000919 J**
	B-212-85	09/11/17	PES	ESC	85	-27.4	S	0.00531 U	0.000342 U	0.00155 U	0.000272 U	0.000231 U	0.0113 U	0.00203 U	0.000306 U	0.000322 U	0.000443 U	0.000481 U	0.00152 U	**0.000454 J**
	B-212-95	09/11/17	PES	ESC	95	-37.4	S	0.00611 U	0.000394 U	0.00179 U	0.000314 U	0.000267 U	0.0131 U	0.00234 U	0.000354 U	0.000371 U	0.000511 U	0.000554 U	0.00176 U	0.000289 U
	B-212-100	09/11/17	PES	ESC	100	-42.4	S	0.00565 U	0.000363 U	0.00165 U	0.000290 U	0.000246 U	0.0121 U	0.00216 U	0.000326 U	0.000343 U	0.000471 U	0.000512 U	0.00162 U	0.000267 U
B-213	B-213-15	09/05/17	PES	ESC	15	42.4	V	0.00542 U	0.000349 U	0.00159 U	0.000278 U	0.000236 U	0.0116 U	0.00207 U	0.000313 U	0.000329 U	0.000452 U	0.000491 U	0.00155 U	0.000256 U
	B-213-21.5	09/05/17	PES	ESC	22	35.9	S	**0.00736 J**	0.000314 U	0.00143 U	0.000250 U	**0.00445**	**0.0143 J**	0.00187 U	**0.000385 J**	0.000296 U	0.000406 U	0.000442 U	0.00140 U	**0.000932 J**
	B-213-35	09/05/17	PES	ESC	35	22.4	S	0.00507 U	0.000326 U	0.00148 U	0.000260 U	0.000221 U	0.0108 U	0.00194 U	0.000292 U	0.000307 U	0.000422 U	0.000459 U	0.00145 U	0.000239 U
	B-213-45	09/05/17	PES	ESC	45	12.4	S	0.00519 U	0.000334 U	0.00152 U	0.000266 U	0.000226 U	0.0111 U	0.00198 U	0.000299 U	0.000315 U	0.000432 U	0.000470 U	0.00149 U	0.000245 U
	B-213-55	09/05/17	PES	ESC	55	2.4	S	0.00509 U	0.000328 U	0.00149 U	0.000261 U	0.000222 U	0.0109 U	0.00195 U	0.000294 U	0.000309 U	0.000425 U	0.000462 U	0.00146 U	**0.000834 J**
	B-213-65	09/05/17	PES	ESC	65	-7.6	S	0.00515 U	0.000331 U	0.00151 U	0.000264 U	0.000224 U	0.0110 U	0.00197 U	0.000297 U	0.000312 U	0.000429 U	0.000467 U	0.00147 U	**0.00140**
	B-213-75	09/05/17	PES	ESC	75	-17.6	S	0.00511 U	0.000329 U	0.00150 U	0.000262 U	0.000223 U	0.0109 U	0.00196 U	0.000295 U	0.000310 U	0.000426 U	0.000463 U	0.00146 U	0.000242 U
	B-213-85	09/05/17	PES	ESC	85	-27.6	S	0.00571 U	0.000367 U	0.00167 U	0.000293 U	0.000249 U	0.0122 U	0.00218 U	0.000329 U	0.000346 U	0.000475 U	0.000517 U	0.00163 U	**0.000882 J**
	B-213-95	09/06/17	PES	ESC	95	-37.6	S	0.00578 U	0.000372 U	0.00169 U	0.000296 U	0.000252 U	0.0124 U	0.00221 U	0.000334 U	0.000351 U	0.000482 U	0.000524 U	0.00166 U	0.000273 U
	B-213-105	09/06/17	PES	ESC	105	-47.6	S	0.00538 U	0.000346 U	0.00157 U	0.000276 U	0.000234 U	0.0115 U	0.00206 U	0.000310 U	0.000326 U	0.000448 U	0.000487 U	0.00154 U	0.000254 U
	B-906-110	09/06/17	PES	ESC	105 (dup)	-47.6	S	0.00537 U	0.000346 U	0.00157 U	0.000276 U	0.000234 U	0.0115 U	0.00206 U	0.000310 U	0.000326 U	0.000448 U	0.000487 U	0.00154 U	0.000254 U
	B-213-115	09/06/17	PES	ESC	115	-57.6	S	0.00574 U	0.000369 U	0.00168 U	0.000294 U	0.000250 U	0.0123 U	0.00219 U	0.000331 U	0.000348 U	0.000478 U	0.000520 U	0.00164 U	0.000271 U
	B-213-125	09/06/17	PES	ESC	125	-67.6	S	0.00692 U	0.000445 U	0.00202 U	0.000355 U	0.000302 U	0.0148 U	0.00265 U	0.000400 U	0.000420 U	0.000577 U	0.000628 U	0.00198 U	**0.000628 J**
B-214	B-214-15	09/07/17	PES	ESC	15	42.4	V	0.00502 U	0.000323 U	0.00147 U	0.000257 U	0.000219 U	0.0107 U	0.00192 U	0.000290 U	0.000305 U	0.000418 U	0.000455 U	0.00144 U	**0.000244 J**
	B-214-25	09/07/17	PES	ESC	25	32.4	S	0.00495 U	0.000318 U	0.00145 U	0.000254 U	0.000216 U	0.0106 U	0.00189 U	0.000285 U	0.000300 U	0.000412 U	0.000448 U	0.00142 U	0.000234 U
	B-214-35	09/07/17	PES	ESC	35	22.4	S	0.00508 U	0.000327 U	0.00149 U	0.000261 U	0.000222 U	**0.0139 J**	0.00194 U	0.000293 U	0.000308 U	0.000423 U	0.000460 U	0.00145 U	0.000240 U
	B-214-45	09/07/17	PES	ESC	45	12.4	S	0.00498 U	0.000320 U	0.00146 U	0.000255 U	0.000217 U	**0.0202 J**	0.00191 U	0.000287 U	0.000302 U	0.000415 U	0.000451 U	0.00143 U	**0.000703 J**
	B-214-55	09/07/17	PES	ESC	55	2.4	S	0.00520 U	0.000334 U	0.00152 U	0.000267 U	0.000227 U	**0.0224 J**	0.00199 U	**0.000343 J**	0.000315 U	0.000433 U	0.000471 U	0.00149 U	**0.00159**
	B-214-65	09/07/17	PES	ESC	65	-7.6	S	0.00602 U	0.000387 U	0.00176 U	0.000309 U	0.000263 U	0.0129 U	0.00230 U	0.000347 U	0.000366 U	0.000502 U	0.000546 U	0.00172 U	0.000284 U
	B-214-75	09/07/17	PES	ESC	75	-17.6	S	0.00520 U	0.000334 U	0.00152 U	0.000267 U	0.000227 U	**0.0121 J**	0.00199 U	0.000300 U	0.000316 U	0.000433 U	0.000471 U	0.00149 U	**0.000650 J**
	B-214-85	09/07/17	PES	ESC	85	-27.6	S	0.00563 U	0.000362 U	0.00165 U	0.000288 U	0.000245 U	**0.0150 J**	0.00215 U	0.000325 U	0.000341 U	0.000469 U	0.000510 U	0.00161 U	**0.00148**
	B-908-100	09/07/17	PES	ESC	85 (dup)	-27.6	S	0.00523 U	0.000336 U	0.00153 U	0.000268 U	0.000228 U	**0.0230 J**	0.00200 U	0.000302 U	0.000317 U	0.000436 U	0.000474 U	0.00150 U	**0.00203**
	B-214-95	09/07/17	PES	ESC	95	-37.6	S	0.00514 U	0.000330 U	0.00150 U	0.000263 U	0.000224 U	**0.0125 J**	0.00196 U	0.000296 U	0.000312 U	0.000428 U	0.000465 U	0.00147 U	**0.00135**
	B-214-105	09/07/17	PES	ESC	105	-47.6	S	0.00592 U	0.000381 U	0.00173 U	0.000304 U	0.000258 U	0.0127 U	0.00226 U	0.000342 U	0.000359 U	0.000493 U	0.000537 U	0.00170 U	0.000280 U
	B-214-115	09/11/17	PES	ESC	115	-57.6	S	0.00571 U	0.000367 U	0.00167 U	0.000293 U	0.000249 U	0.0122 U	0.00218 U	0.000329 U	0.000346 U	0.000476 U	0.000517 U	0.00163 U	0.000270 U
	B-214-120	09/11/17	PES	ESC	120	-62.6	S	0.00553 U	0.000355 U	0.00162 U	0.000283 U	0.000241 U	0.0118 U	0.00211 U	0.000319 U	0.000335 U	0.000461 U	0.000501 U	0.00158 U	0.000261 U
B-215	B-215-15	09/12/17	PES	ESC	15	39.0	V	0.00508 U	0.000326 U	0.00149 U	0.000260 U	0.000221 U	0.0108 U	0.00194 U	0.000293 U	0.000308 U	0.000423 U	0.000460 U	0.00145 U	0.000240 U
	B-215-25	09/12/17	PES	ESC	25	29.0	S	0.00501 U	0.000322 U	0.00147 U	0.000257 U	0.000218 U	0.0107 U	0.00192 U	0.000289 U	0.000304 U	0.000417 U	0.000454 U	0.00143 U	0.000237 U
	B-215-35	09/12/17	PES	ESC	35	19.0	S	0.00552 U	0.000355 U	0.00162 U	0.000283 U	0.000241 U	0.0118 U	0.00211 U	0.000318 U	0.000335 U	0.000460 U	0.000500 U	0.00158 U	0.000261 U
	B-215-45	09/12/17	PES	ESC	45	9.0	S	0.00498 U	0.000320 U	0.00146 U	0.000255 U	0.000217 U	0.0106 U	0.00190 U	0.000287 U	0.000302 U	0.000415 U	0.000451 U	0.00143 U	**0.000807 J**

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
B-215 (continued)	B-215-55	09/12/17	PES	ESC	55	-1.1	S	0.00518 U	0.000333 U	0.00152 U	0.000266 U	0.000226 U	0.0111 U	0.00198 U	0.000299 U	0.000315 U	0.000432 U	0.000470 U	0.00148 U	**0.000688 J**
	B-215-65	09/12/17	PES	ESC	65	-11.1	S	0.134 U	0.00860 U	0.0391 U	0.00686 U	0.00583 U	0.286 U	0.0512 U	0.00772 U	0.00812 U	0.0112 U	0.0121 U	0.0383 U	0.00631 U
	B-215-75	09/12/17	PES	ESC	75	-21.1	S	0.00516 U	0.000332 U	0.00151 U	0.000265 U	0.000225 U	0.0110 U	0.00197 U	0.000298 U	0.000313 U	0.000430 U	0.000468 U	0.00148 U	**0.000331 J**
	B-215-85	09/13/17	PES	ESC	85	-31.1	S	0.00564 U	0.000363 U	0.00165 U	0.000289 U	0.000246 U	0.0121 U	0.00216 U	0.000325 U	0.000342 U	0.000470 U	0.000511 U	0.00162 U	0.000266 U
	B-909-115	09/13/17	PES	ESC	85 (dup)	-31.1	S	0.00524 U	0.000337 U	0.00154 U	0.000269 U	0.000229 U	0.0112 U	0.00201 U	0.000303 U	0.000318 U	0.000437 U	0.000475 U	0.00150 U	**0.000492 J**
	B-215-95	09/13/17	PES	ESC	95	-41.1	S	0.00560 U	0.000360 U	0.00164 U	0.000287 U	0.000244 U	0.0120 U	0.00214 U	0.000323 U	0.000340 U	0.000467 U	0.000507 U	0.00160 U	0.000265 U
B-268	B-268-1	03/17/20	PES	PACE	1	–	V	0.0155 U	0.00114 U	0.0124 U	0.00140 U	0.00289 U	0.0170 UJ	0.00236 U	0.000496 U	0.00130 U	0.00140 UJ	0.00742 U	0.00459 U	0.00504 U
B-269	B-269-1.5	03/17/20	PES	PACE	1.5	–	V	0.0137 U	0.00100 U	0.0109 U	0.00123 U	0.00254 U	0.0150 UJ	0.00207 U	**0.000755 J**	0.00115 U	0.00123 UJ	0.00653 U	0.00404 U	0.00443 U
B-270	B-270-2	03/17/20	PES	PACE	2	–	V	0.0151 U	0.00111 U	0.0121 U	0.00137 U	**0.0129**	0.0166 UJ	0.00230 U	0.000484 U	0.00127 U	0.00137 UJ	0.00723 U	0.00448 U	0.00491 U
B-271	B-271-1	03/17/20	PES	PACE	1	–	V	**0.0458**	0.000988 U	0.0107 U	0.00121 U	0.00250 U	**0.0272**	0.00204 U	**0.000639 J**	0.00113 U	0.00121 UJ	0.00642 U	0.00397 U	0.00436 U
B-272	B-272-1	03/17/20	PES	PACE	1	–	V	0.0147 U	0.00108 U	0.0118 U	0.00133 U	0.00275 U	0.0162 UJ	0.00224 U	**0.182**	0.00124 U	0.00133 UJ	0.00705 U	0.00436 U	0.00479 U
	B-272-6	03/17/20	PES	PACE	6	–	V	**0.0249 J**	0.00114 U	0.0124 U	0.00140 U	0.00288 U	0.0170 UJ	0.00235 U	**0.0257**	0.00130 U	0.00140 UJ	0.00740 U	0.00458 U	0.00502 U
B-273	B-273-1	03/17/20	PES	PACE	1	–	V	0.0140 U	0.00103 U	0.0112 U	0.00127 U	0.00261 U	0.0154 UJ	0.00213 U	**0.000744 J**	0.00118 U	0.00127 UJ	0.00671 U	0.00415 U	0.00456 U
	B-273-3	03/17/20	PES	PACE	3	–	V	**0.0166 J**	0.00102 U	0.0111 U	0.00125 U	**0.00487 J**	0.0151 UJ	0.00210 U	**0.000493 J**	0.00116 U	0.00125 UJ	0.00661 U	0.00409 U	0.00449 U
	B-273-6	03/17/20	PES	PACE	6	–	V	0.0278 U	0.00204 U	0.0222 U	0.00250 U	**0.0549**	0.0303 UJ	0.00421 U	**0.0244**	0.00232 U	0.00250 UJ	0.0133 U	0.00821 U	0.00900 U
B-274	B-274-1	03/17/20	PES	PACE	1	–	V	0.0141 U	0.00103 U	0.0112 U	0.00127 U	**0.00586**	0.0154 UJ	0.00214 U	**0.00540**	0.00118 U	0.00127 UJ	0.00672 U	0.00416 U	0.00457 U
	B-274-3	03/17/20	PES	PACE	3	–	V	**0.0177 J**	0.000996 U	0.0108 U	0.00122 U	0.00252 U	0.0148 UJ	0.00206 U	0.000433 U	0.00114 U	0.00122 UJ	0.00648 U	0.00401 U	0.00440 U
	B-274-6	03/17/20	PES	PACE	6	–	V	0.0223 U	0.00164 U	0.0178 U	0.00201 U	**0.00608 J**	0.0243 UJ	0.00338 U	**0.00315**	0.00187 U	0.00201 UJ	0.0106 U	0.00658 U	0.00722 U
B-275	B-275-1	03/17/20	PES	PACE	1	–	V	0.0147 U	0.00108 U	0.0117 U	0.00133 U	0.00274 U	0.0161 UJ	0.00223 U	**0.00200**	0.00123 U	0.00133 UJ	0.00702 U	0.00434 U	0.00477 U
	B-275-6	03/17/20	PES	PACE	6	–	V	**0.0658**	0.00170 U	0.0185 U	0.00210 U	**0.0705**	0.0254 UJ	0.00352 U	**0.0103**	0.00195 U	0.00210 UJ	0.0111 U	0.00686 U	0.00751 U
	B-275-9	03/17/20	PES	PACE	9	–	S	**0.0391**	0.00142 U	0.0154 U	0.00174 U	**0.0126**	0.0211 UJ	0.00292 U	**0.00112 J**	0.00162 U	0.00174 UJ	0.00920 U	0.00569 U	**0.0171 J**
	B-275-10	03/17/20	PES	PACE	10	–	S	0.0137 U	0.00101 U	0.0110 U	0.00124 U	0.00256 U	0.0151 UJ	0.00209 U	0.000440 U	0.00115 U	0.00124 UJ	0.00658 U	0.00407 U	0.00446 U
B-276	B-276-1	03/17/20	PES	PACE	1	–	V	0.0231 U	0.00170 U	0.0184 U	0.00209 U	0.00430 U	0.0252 UJ	0.00351 U	0.000738 U	0.00194 U	0.00209 UJ	0.0110 U	0.00682 U	0.00749 U
	B-276-7	03/17/20	PES	PACE	7	–	V	0.0138 U	0.00102 U	0.0111 U	0.00125 U	0.00258 U	0.0152 UJ	0.00210 U	0.000442 U	0.00116 U	0.00125 UJ	0.00661 U	0.00409 U	0.00449 U
	B-970-6	03/17/20	PES	PACE	7 (dup)	–	V	0.0138 U	0.00102 U	0.0111 U	0.00125 U	0.00258 U	0.0152 U	0.00210 U	0.000443 U	0.00116 U	0.00125 U	0.00662 U	0.00409 U	0.00449 U
	B-276-11	03/17/20	PES	PACE	11	–	S	**0.0296**	0.00107 U	0.0117 U	0.00132 U	0.00272 U	0.0160 U	0.00222 U	**0.000491 J**	0.00123 U	0.00132 U	0.00699 U	0.00432 U	**0.0125 J**
B-277	B-277-1	03/18/20	PES	PACE	1	–	V	**0.0193 J**	0.00116 U	0.0126 U	0.00142 U	0.00294 U	0.0173 U	0.00239 U	0.000504 U	0.00132 U	0.00142 U	0.00754 U	0.00466 U	0.00512 U
	B-277-3	03/18/20	PES	PACE	3	–	V	**0.0277**	0.00101 U	0.0110 U	0.00124 U	0.00256 U	0.0151 U	0.00209 U	0.000440 U	0.00115 U	0.00124 U	0.00657 U	0.00407 U	0.00446 U
	B-277-5	03/18/20	PES	PACE	5	–	V	**0.0337 J**	0.00152 U	0.0165 U	0.00187 U	0.00385 U	0.0226 U	0.00314 U	0.000661 U	0.00173 U	0.00187 U	0.00988 U	0.00611 U	0.00671 U
	B-277-9.5	03/18/20	PES	PACE	9.5	–	V	**0.0656**	0.00219 U	0.0238 U	0.00268 U	**0.0331**	0.0326 U	0.00452 U	**0.00356**	0.00249 U	0.00268 U	0.0142 U	0.00879 U	0.00966 U
	B-277-11	03/18/20	PES	PACE	11	–	S	**0.0259 J**	0.000993 U	0.0108 U	0.00122 U	0.00251 U	0.0148 U	0.00205 U	0.000432 U	0.00113 U	0.00122 U	0.00645 U	0.00399 U	0.00438 U
B-278	B-278-3	03/18/20	PES	PACE	3	–	V	0.0140 U	0.00103 U	0.0112 U	0.00126 U	0.00260 U	0.0153 U	0.00212 U	0.000446 U	0.00117 U	0.00126 U	0.00667 U	0.00413 U	0.00453 U
	B-278-6	03/18/20	PES	PACE	6	–	V	**0.0225 J**	0.00102 U	0.0111 U	0.00125 U	0.00258 U	0.0152 U	0.00211 U	0.000444 U	0.00116 U	0.00125 U	0.00663 U	0.00410 U	0.00450 U
B-279	B-279-3	03/18/20	PES	PACE	3	–	V	**0.0202 J**	0.00104 U	0.0113 U	0.00128 U	0.00264 U	0.0155 U	0.00216 U	0.000454 U	0.00119 U	0.00128 U	0.00678 U	0.00420 U	0.00460 U
	B-279-5	03/18/20	PES	PACE	5	–	V	**0.0161 J**	0.00103 U	0.0112 U	0.00126 U	0.00261 U	0.0153 U	0.00212 U	0.000447 U	0.00117 U	0.00126 U	0.00669 U	0.00414 U	0.00454 U
	B-279-10	03/18/20	PES	PACE	10	–	V	**0.0185 J**	0.00100 U	0.0109 U	0.00123 U	0.00253 U	0.0149 U	0.00206 U	0.000435 U	0.00114 U	0.00123 U	0.00650 U	0.00402 U	0.00441 U
B-280	B-280-4.5	03/18/20	PES	PACE	4.5	–	V	**0.0308**	0.000953 U	0.0104 U	0.00117 U	0.00241 U	0.0142 U	0.00197 U	0.000414 U	0.00109 U	0.00117 U	0.00619 U	0.00383 U	0.00421 U
	B-280-6	03/18/20	PES	PACE	6	–	V	**0.0211 J**	0.00100 U	0.0109 U	0.00123 U	0.00254 U	0.0149 U	0.00207 U	0.000435 U	0.00114 U	0.00123 U	0.00651 U	0.00403 U	0.00442 U
B-281	B-281-2	03/18/20	PES	PACE	2	–	V	**0.0132 J**	0.000962 U	0.0105 U	0.00118 U	0.00244 U	0.0143 U	0.00199 U	0.000418 U	0.00110 U	0.00118 U	0.00625 U	0.00387 U	0.00424 U
	B-281-5	03/18/20	PES	PACE	5	–	V	**0.0228 J**	0.00104 U	0.0113 U	0.00128 U	0.00264 U	0.0155 U	0.00215 U	0.000453 U	0.00119 U	0.00128 U	0.00678 U	0.00419 U	0.00460 U
B-282	B-282-2	03/18/20	PES	PACE	2	–	V	**0.0154 J**	0.00105 U	0.0114 U	0.00129 U	0.00266 U	0.0156 U	0.00217 U	0.000456 U	0.00120 U	0.00129 U	0.00682 U	0.00422 U	0.00463 U
	B-282-4	03/18/20	PES	PACE	4	–	V	**0.0154 J**	0.00102 U	0.0110 U	0.00125 U	0.00257 U	0.0151 UJ	0.00210 U	0.000442 U	0.00116 U	0.00125 UJ	0.00661 U	0.00409 U	0.00448 U
	B-971-5	03/18/20	PES	PACE	4 (dup)	–	V	0.0133 U	0.000979 U	0.0106 U	0.00120 U	0.00248 U	0.0146 UJ	0.00202 U	0.000426 U	0.00112 U	0.00120 UJ	0.00636 U	0.00394 U	0.00432 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
B-283	B-283-0.5	08/19/20	PES	PACE	0.5	–	V	0.0764 U	0.00104 U	0.00404 U	0.000541 U	0.00307 U	0.0439 U	0.00434 U	0.000562 U	0.00108 U	0.000678 U	0.00141 U	0.00237 U	0.000842 U
B-284	B-284-1	08/19/20	PES	PACE	1	–	V	0.0762 U	0.00104 U	0.00403 U	0.000540 U	0.00306 U	**0.0551 J**	0.00433 U	0.000560 U	0.00108 U	0.000677 U	0.00140 U	0.00236 U	0.000840 U
B-285	B-285-1	08/19/20	PES	PACE	1	–	V	0.0829 U	0.00113 U	0.00439 U	0.000587 U	0.00334 U	**0.0931**	0.00472 U	**0.00252**	0.00118 U	0.000736 U	0.00153 U	0.00257 U	0.000914 U
B-286	B-286-0.5	08/19/20	PES	PACE	0.5	–	V	0.169 U	0.00231 U	0.00893 U	0.00120 U	0.00679 U	**0.103 J**	0.00960 U	**0.00651**	0.00240 U	0.00150 U	0.00312 U	0.00525 U	0.00187 U
B-287	B-287-1	08/19/20	PES	PACE	1	–	V	0.165 U	0.00225 U	0.00873 U	0.00117 U	0.00663 U	0.0948 U	0.00938 U	**0.00149 J**	0.00234 U	0.00147 U	0.00303 U	0.00511 U	0.00182 U
B-288	B-288-1	08/19/20	PES	PACE	1	–	V	0.337 U	0.00460 U	0.0178 U	0.00239 U	0.0135 U	0.194 U	0.0191 U	**0.0224**	0.00479 U	0.00299 U	0.00620 U	0.0105 U	0.00371 U
B-289	B-289-0.5	08/19/20	PES	PACE	0.5	–	V	0.277 U	0.00377 U	0.0147 U	0.00196 U	0.0111 U	0.159 U	0.0158 U	**0.00207 J**	0.00393 U	0.00246 U	0.00509 U	0.00861 U	0.00305 U
B-290	B-290-1	08/20/20	PES	PACE	1	–	V	0.100 U	0.00136 U	0.00530 U	0.000711 U	0.00402 U	**0.0708 J**	0.00570 U	**0.00628**	0.00142 U	0.000890 U	0.00185 U	0.00311 U	0.00110 U
B-291	B-291-1	08/20/20	PES	PACE	1	–	V	0.0861 U	0.00117 U	0.00455 U	0.000610 U	0.00346 U	0.0495 U	0.00489 U	**0.00302**	0.00122 U	0.000765 U	0.00159 U	0.00267 U	0.000949 U
B-292	B-292-3	08/22/20	PES	PACE	3	–	V	0.0799 U	0.00109 U	0.00423 U	0.000566 U	0.00321 U	0.0459 U	0.00454 U	0.000588 U	0.00113 U	0.000710 U	0.00147 U	0.00248 U	0.000881 U
	B-292-6	08/22/20	PES	PACE	6	–	V	0.0826 U	0.00112 U	0.00437 U	0.000585 U	0.00332 U	0.0475 U	0.00469 U	0.000607 U	0.00117 U	0.000733 U	0.00152 U	0.00256 U	0.000910 U
	B-292-9	08/22/20	PES	PACE	9	–	V	0.0750 U	0.00102 U	0.00397 U	0.000532 U	0.00301 U	0.0431 U	0.00427 U	0.000552 U	0.00106 U	0.000667 U	0.00138 U	0.00233 U	0.000827 U
	B-292-12	08/22/20	PES	PACE	12	–	V	0.0834 U	0.00114 U	0.00441 U	0.000591 U	0.00335 U	0.0479 U	0.00474 U	0.000613 U	0.00118 U	0.000740 U	0.00154 U	0.00259 U	0.000919 U
B-293	B-293-1	08/26/20	PES	PACE	1	–	V	0.0704 U	0.000959 U	0.00372 U	0.000499 U	0.00283 UJ	0.0405 U	0.00400 U	**0.000933 J**	0.000998 U	0.000625 U	0.00130 U	0.00218 UJ	0.000776 UJ
B-294	B-294-1	08/26/20	PES	PACE	1	–	V	0.0891 U	0.00121 U	0.00472 U	0.000632 U	0.0110	0.0512 U	0.00507 U	**0.125**	0.00126 U	0.000792 U	0.00164 U	0.00277 UJ	0.000983 UJ
	B-294-2	08/26/20	PES	PACE	2	–	V	0.185 U	0.00252 U	0.00976 U	0.00131 U	0.0298 UJ	0.106 U	0.0105 U	**3.50**	0.00261 U	0.00164 U	0.00340 U	0.00572 UJ	0.00203 UJ
	B-294-6	08/26/20	PES	PACE	6	–	V	0.181 U	0.00246 U	0.00959 U	0.00128 U	0.00728 UJ	0.104 U	0.0103 U	**0.0800**	0.00256 U	0.00161 U	0.00333 U	0.00562 UJ	0.00200 UJ
	B-294-10	08/26/20	PES	PACE	10	–	S	**0.0995 J**	0.00116 U	0.00452 U	0.000606 U	0.00343 UJ	0.0491 U	0.00486 U	**0.00115 J**	0.00121 U	0.000759 U	0.00157 U	0.00265 UJ	0.000942 UJ
B-295	B-295-1	08/26/20	PES	PACE	1	–	V	0.0764 U	0.00104 U	0.00404 U	0.000542 U	0.00307 UJ	0.0439 U	0.00434 U	0.000562 U	0.00108 U	0.000679 U	0.00141 U	0.00237 UJ	0.000843 UJ
	B-295-3	08/26/20	PES	PACE	3	–	V	0.113 U	0.00154 U	0.00599 U	0.000803 U	0.00455 U	0.0651 U	0.00644 U	**0.00155 J**	0.00161 U	0.00101 U	0.00209 U	0.00351 UJ	0.00125 UJ
	B-295-7	08/26/20	PES	PACE	7	–	V	0.0951 U	0.00130 U	0.00503 U	0.000674 U	0.00382 UJ	0.0547 U	0.00541 U	**0.00187**	0.00135 U	0.000845 U	0.00175 U	0.00295 UJ	0.00105 UJ
	B-295-10	08/26/20	PES	PACE	10	–	S	0.0893 U	0.00122 U	0.00472 U	0.000633 U	0.00358 UJ	0.0513 U	0.00507 U	**0.000922 J**	0.00127 U	0.000793 U	0.00164 U	0.00277 UJ	0.000984 UJ
B-296	B-296-1	08/26/20	PES	PACE	1	–	V	0.0721 U	0.000983 U	0.00382 U	0.000511 U	0.00290 UJ	0.0415 U	0.00410 U	0.000531 U	0.00102 U	0.000641 U	0.00133 U	0.00224 UJ	0.000795 UJ
B-297	B-297-1	08/26/20	PES	PACE	1	–	V	0.0782 U	0.00107 U	0.00414 U	0.000554 U	0.00314 UJ	0.0450 U	0.00445 U	0.000575 U	0.00111 U	0.000695 U	0.00144 U	0.00243 UJ	0.000862 UJ
	B-297-3	08/26/20	PES	PACE	3	–	V	0.0729 U	0.000994 U	0.00386 U	0.000517 U	0.00293 UJ	0.0419 U	0.00415 U	**0.00116**	0.00103 U	0.000648 U	0.00134 U	0.00226 UJ	0.000804 UJ
	B-500-1	08/26/20	PES	PACE	3 (dup)	–	V	0.0744 U	0.00101 U	0.00394 U	0.000527 U	0.00299 U	0.0428 UJ	0.00423 UJ	0.000547 U	0.00105 U	0.000661 U	0.00137 U	0.00231 U	0.000820 U
	B-297-5	08/26/20	PES	PACE	5	–	V	0.0726 U	0.000988 U	0.00384 U	0.000514 U	0.00291 U	0.0417 UJ	0.00413 UJ	**0.00117**	0.00103 U	0.000645 U	0.00134 U	0.00225 U	0.000800 U
B-298	B-298-5	08/26/20	PES	PACE	5	–	V	0.0670 U	0.000913 U	0.00354 U	0.000475 U	0.00270 U	0.0386 UJ	0.00381 UJ	0.000493 U	0.000950 U	0.000596 U	0.00123 U	0.00208 U	0.000739 U
	B-298-6	08/26/20	PES	PACE	6	–	V	0.0806 U	0.00110 U	0.00426 U	0.000571 U	0.00324 U	**0.0541 J**	0.00458 UJ	**0.00403**	0.00114 U	0.000716 U	0.00148 U	0.00250 U	0.000888 U
B-299	B-299-2	02/01/21	PES	PACE	2	–	V	0.0910 U	0.00114 UJ	0.00444 UJ	0.000594 U	0.00337 U	0.0482 U	0.00477 U	0.000616 U	0.00119 U	0.000745 U	0.00154 U	0.00260 U	0.000924 U
	B-299-5.5	02/01/21	PES	PACE	5.5	–	V	0.0884 U	0.00103 UJ	0.00400 UJ	0.000536 U	0.00304 U	0.0435 U	0.00430 U	0.000557 U	0.00107 U	0.000672 U	0.00139 U	0.00235 U	0.000834 U
	B-1003-10	02/01/21	PES	PACE	5.5 (dup)	–	V	0.103 U	0.00107 UJ	0.00416 UJ	0.000558 U	0.00316 U	0.0452 U	0.00447 U	0.000579 U	0.00112 U	0.000699 U	0.00145 U	0.00244 U	0.000868 U
B-300	B-300-2.5	02/01/21	PES	PACE	2.5	–	V	0.0839 U	0.00114 UJ	0.00444 UJ	0.000595 U	0.00337 U	0.0482 U	0.00477 U	0.000617 U	0.00119 U	0.000745 U	0.00155 U	0.00260 U	0.000925 U
	B-300-5.5	02/01/21	PES	PACE	5.5	–	V	0.0837 U	0.00112 UJ	0.00433 UJ	0.000580 U	0.00329 U	0.0471 U	0.00466 U	0.000602 U	0.00116 U	0.000727 U	0.00151 U	0.00254 U	0.000903 U
B-301	B-301-2	02/01/21	PES	PACE	2	–	V	0.0839 U	0.00111 UJ	0.00431 UJ	0.000577 U	0.00327 U	0.0468 U	0.00463 U	0.000599 U	0.00115 U	0.000723 U	0.00150 U	0.00253 U	0.000898 U
	B-301-5	02/01/21	PES	PACE	5	–	V	0.0891 U	0.00117 UJ	0.00454 UJ	0.000608 U	0.00345 U	0.0493 U	0.00488 U	0.000631 U	0.00122 U	0.000762 U	0.00158 U	0.00266 U	0.000946 U
B-302	B-302-2	02/01/21	PES	PACE	2	–	V	0.0800 U	0.00108 UJ	0.00421 UJ	0.000563 U	0.00319 U	0.0457 U	0.00452 U	0.000584 U	0.00113 U	0.000706 U	0.00146 U	0.00247 U	0.000876 U
	B-302-4	02/01/21	PES	PACE	4	–	V	0.0963 U	0.00123 UJ	0.00479 UJ	0.000642 U	0.00364 U	0.0521 U	0.00515 U	0.000666 U	0.00128 U	0.000805 U	0.00167 U	0.00281 U	0.000999 U
BB-5	S-6	03/09/97	B&V	Unknown	15-17	34.0	V	–	–	–	–	–	–	–	ND	–	–	–	–	–
	S-10	03/09/97	B&V	Unknown	25-27	24.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
BB-7	S-4	04/06/97	B&V	Unknown	10-12	17.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
BB-8 (13.6 to 3.6)	S-8	06/06/97	B&V	Unknown	20-22	23.6	S	–	–	–	–	–	–	–	ND	–	–	–	–	–
BB-10	S-6	08/29/97	B&V	Unknown	15-17	42.0	V	–	–	–	–	–	–	–	–	–	–	–	–	–
BB-12	S-3	03/18/98	B&V	Unknown	15-16.5	18.8	S	–	–	–	–	–	–	–	ND	–	–	–	–	–
	S-14	03/18/98	B&V	Unknown	45-46.5	-11.2	S	–	–	–	–	–	–	–	ND	–	–	–	–	–
BB-13	S-10	03/19/98	B&V	Unknown	25-27.5	1.9	S	–	–	–	–	–	–	–	ND	–	–	–	–	–
	S-16	03/19/98	B&V	Unknown	40-41.5	-13.1	S	–	–	–	–	–	–	–	ND	–	–	–	–	–
BB-14	S-2	03/03/98	B&V	Unknown	5-6.5	21.3	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	S-5	03/03/98	B&V	Unknown	12.5-14	14.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	S-9	03/03/98	B&V	Unknown	22.5-24	4.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	S-12	03/03/98	B&V	Unknown	30-31.5	-4.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CHB-07	CHB-07-12.5-13.5	04/14/05	CH2M	ARI	12.5-13.5	16.5	S	–	–	–	–	–	–	–	**0.0015**	–	–	–	–	–
	CHB-07-5.0-7.0	04/14/08	CH2M	ARI	5-7	23.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
CHB-08	CHB-08-15.0-16.0	04/15/08	CH2M	ARI	15-16	14.1	S	–	–	–	–	–	–	–	0.0008 U	–	–	–	–	–
CHB-09	CHB-09-20.0-21.5	04/16/08	CH2M	ARI	20-21.5	15.4	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	CHB-09-25.0-26.5	04/16/08	CH2M	ARI	25-26.5	10.4	S	–	–	–	–	–	–	–	0.0012 U	–	–	–	–	–
GEI-MW-1 (-9.7 to -29.7)	MW-1-1-2.5	08/22/14	GEI	Fremont	1	29.5	V	–	–	–	–	–	–	–	0.0181 U	–	–	–	–	–
GEI-MW-2 (4.0 to -6.0)	MW-2-2-5.0	08/23/14	GEI	Fremont	5	26.6	V	–	–	–	–	–	–	–	0.0391 U	–	–	–	–	–
	MW-2-4-10.0	08/23/14	GEI	Fremont	10	21.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	MW-2-8-20.0	08/23/14	GEI	Fremont	20	11.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–
GEI-MW-3 (-18.7 to -28.7)	MW-3-4-10.0	08/23/14	GEI	Fremont	10	20.8	S	–	–	–	–	–	–	–	0.0258 U	–	–	–	–	–
	MW-3-10-50.0	08/23/14	GEI	Fremont	50	-19.3	S	–	–	–	–	–	–	–	0.0166 U	–	–	–	–	–
GEI-4	GEI-4-2-5.0	08/23/14	GEI	Fremont	5	26.0	V	–	–	–	–	–	–	–	0.0214 U	–	–	–	–	–
	GEI-4-5-12.5	08/23/14	GEI	Fremont	12.5	18.5	S	–	–	–	–	–	–	–	0.0243 U	–	–	–	–	–
MW-1 (SCLB-3)	RS3-2.5	03/15/93	EPJ	OnSite	2.5	37.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS3-7.5	03/15/93	EPJ	OnSite	7.5	32.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS3-17.5	03/15/93	EPJ	OnSite	17.5	22.5	S	–	–	–	–	–	–	–	**10**	–	–	–	–	–
	RS3-22.5/RS3-27.5 (Comp)	03/15/93	EPJ	OnSite	22.5-27.5	–	S	–	–	–	–	–	–	–	**3.9**	–	–	–	–	–
	RS3-32.5	03/15/93	EPJ	OnSite	32.5	7.5	S	–	–	–	–	–	–	–	**0.15**	–	–	–	–	–
	RS3-37.5	03/15/93	EPJ	OnSite	37.5	2.5	S	–	–	–	–	–	–	–	0.050 U	–	–	–	–	–
MW-2 (SCLB-4)	RS4-2.5	03/15/93	EPJ	OnSite	2.5	37.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS4-7.5	03/15/93	EPJ	OnSite	7.5	32.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS4-12.5/RS4-17.5	03/15/93	EPJ	OnSite	12.5-17.5	–	S	–	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	RS4-22.5/RS4-27.5 (Comp)	03/15/93	EPJ	OnSite	22.5-27.5	–	S	–	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	RS4-37.5	03/15/93	EPJ	OnSite	37.5	2.5	S	–	–	–	–	–	–	–	0.05 U	–	–	–	–	–
MW-3 (SCLB-5)	RS5-2.5/RS5-7.5 (Comp)	03/16/93	EPJ	OnSite	2.5-7.5	–	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS5-12.5/RS5-17.5 (Comp)	03/16/93	EPJ	OnSite	12.5-17.5	–	S	–	–	–	–	–	–	–	**0.88**	–	–	–	–	–
	RS5-17.5	03/16/93	EPJ	OnSite	17.5	21.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS5-22.5	03/16/93	EPJ	OnSite	22.5	16.5	S	–	–	–	–	–	–	–	**0.2**	–	–	–	–	–
	RS5-32.5	03/16/93	EPJ	OnSite	32.5	6.5	S	–	–	–	–	–	–	–	**0.056 J**	–	–	–	–	–
	RS5-37.5	03/16/93	EPJ	OnSite	37.5	1.5	S	–	–	–	–	–	–	–	0.050 U	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
MW-4 (SCLB-6)	RS6-2.5	03/17/93	EPJ	OnSite	2.5	37.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS6-7.5	03/17/93	EPJ	OnSite	7.5	32.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS6-12.5	03/17/93	EPJ	OnSite	12.5	27.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS6-17.5/RS6-22.5 (Comp)	03/17/93	EPJ	OnSite	17.5-22.5	–	V	–	–	–	–	–	–	–	0.050 U	–	–	–	–	–
	RS6-27.5	03/17/93	EPJ	OnSite	27.5	12.5	S	–	–	–	–	–	–	–	0.050 U	–	–	–	–	–
MW-5 (SCLB-7)	RS7-2.5	03/17/93	EPJ	OnSite	2.5	37.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS7-7.5	03/17/93	EPJ	OnSite	7.5	32.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS7-12.5	03/17/93	EPJ	OnSite	12.5	27.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS7-17.5	03/17/93	EPJ	OnSite	17.5	22.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS7-22.5	03/17/93	EPJ	OnSite	22.5	17.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW-6	MW6-25	10/11/93	Retec	ARI	25	13.2	S	–	–	–	–	–	–	–	**3.5**	–	–	–	–	–
MW-7	MW7-16.5	10/11/93	Retec	ARI	16.5	18.6	S	–	–	–	–	–	–	–	**7.1**	–	–	–	–	–
	MW7-18.5	10/11/93	Retec	ARI	18.5	16.6	S	–	–	–	–	–	–	–	**2.2**	–	–	–	–	–
MW-8 (28.7 to 14.2)	MW8-20	10/18/93	Retec	AAL	20	13.2	S	–	–	–	–	–	–	–	0.059 U	–	–	–	–	–
MW-9 (33.7 to 18.7)	MW9-17.5	10/18/93	Retec	AAL	17.5	23.6	S	–	–	–	–	–	–	–	0.068 U	–	–	–	–	–
MW-10	MW10-17.5	10/19/93	Retec	AAL	17.5	20.5	S	–	–	–	–	–	–	–	0.068 U	–	–	–	–	–
MW102 (B102) (-65.8 to -75.8)	B102-20	07/17/12	SES	F&BI	20	29.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-30	07/17/12	SES	F&BI	30	19.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-38	07/17/12	SES	F&BI	38	11.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-40	07/17/12	SES	F&BI	40	9.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-49	07/17/12	SES	F&BI	49	0.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-60	07/17/12	SES	F&BI	60	-10.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-70	07/18/12	SES	F&BI	70	-20.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-80	07/19/12	SES	F&BI	80	-30.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-90	07/19/12	SES	F&BI	90	-40.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-100	07/20/12	SES	F&BI	100	-50.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-110	07/20/12	SES	F&BI	110	-60.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B102-120	07/23/12	SES	F&BI	120	-70.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW103 (B103) (-67.6 to -77.6)	B103-10	07/25/12	SES	F&BI	10	25.9	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-18	07/25/12	SES	F&BI	18	17.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-30	07/25/12	SES	F&BI	30	5.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-40	07/25/12	SES	F&BI	40	-4.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-45	07/25/12	SES	F&BI	45	-9.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-55	07/25/12	SES	F&BI	55	-19.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-62.5	07/26/12	SES	F&BI	62.5	-26.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-75	07/26/12	SES	F&BI	75	-39.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-83	07/26/12	SES	F&BI	83	-47.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-95	07/26/12	SES	F&BI	95	-59.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-105	07/27/12	SES	F&BI	105	-69.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B103-113	07/27/12	SES	F&BI	113	-77.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
MW104 (B104)	B104-10	07/30/12	SES	F&BI	10	32.7	S	–	–	–	–	–	–	–	–	–	–	–	–	–
(-76.3 to -86.3)	B104-20	07/30/12	SES	F&BI	20	22.7	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-30	07/30/12	SES	F&BI	30	12.7	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-35	07/30/12	SES	F&BI	35	7.7	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-50	07/30/12	SES	F&BI	50	-7.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-60	07/31/12	SES	F&BI	60	-17.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-69	07/31/12	SES	F&BI	69	-26.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-80	07/31/12	SES	F&BI	80	-37.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-90	08/01/12	SES	F&BI	90	-47.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-100	08/01/12	SES	F&BI	100	-57.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-110	08/01/12	SES	F&BI	110	-67.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-120	08/01/12	SES	F&BI	120	-77.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B104-130	08/01/12	SES	F&BI	130	-87.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW105 (B105)	B105-10	08/06/12	SES	F&BI	10	34.2	V	–	–	–	–	–	–	–	–	–	–	–	–	–
(-85.8 to -95.8)	B105-20	08/06/12	SES	F&BI	20	24.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-30	08/06/12	SES	F&BI	30	14.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-40	08/08/12	SES	F&BI	40	4.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-50	08/08/12	SES	F&BI	50	-5.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-60	08/09/12	SES	F&BI	60	-15.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-70	08/09/12	SES	F&BI	70	-25.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-80	08/09/12	SES	F&BI	80	-35.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-90	08/10/12	SES	F&BI	90	-45.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-100	08/10/12	SES	F&BI	100	-55.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-110	08/10/12	SES	F&BI	110	-65.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-120	08/10/12	SES	F&BI	120	-75.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-130	08/10/12	SES	F&BI	130	-85.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B105-138	08/10/12	SES	F&BI	138	-93.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW106 (B106)	B106-10	08/14/12	SES	F&BI	10	42.0	V	–	–	–	–	–	–	–	–	–	–	–	–	–
(-78.0 to -88.0)	B106-20	08/14/12	SES	F&BI	20	32.0	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-30	08/14/12	SES	F&BI	30	22.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-40	08/14/12	SES	F&BI	40	12.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-50	08/14/12	SES	F&BI	50	2.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-60	08/14/12	SES	F&BI	60	-8.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-70	08/15/12	SES	F&BI	70	-18.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-80	08/15/12	SES	F&BI	80	-28.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-90	08/15/12	SES	F&BI	90	-38.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-100	08/15/12	SES	F&BI	100	-48.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-110	08/15/12	SES	F&BI	110	-58.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-120	08/15/12	SES	F&BI	120	-68.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-130	08/15/12	SES	F&BI	130	-78.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B106-140	08/15/12	SES	F&BI	140	-88.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
MW107 (B107) (8.8 to -1.2)	B107-05	03/12/12	SES	F&BI	5	38.8	V	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B107-15	03/12/12	SES	F&BI	15	28.8	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B107-25	03/12/12	SES	F&BI	25	18.8	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B107-35	03/12/12	SES	F&BI	35	8.8	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B107-45	03/12/12	SES	F&BI	45	-1.2	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
MW108 (B108) (-7.2 to -17.2)	B108-15	12/14/12	SES	F&BI	15	17.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B108-25	12/14/12	SES	F&BI	25	7.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B108-35	12/14/12	SES	F&BI	35	-2.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B108-45	12/14/12	SES	F&BI	45	-12.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B108-50	12/14/12	SES	F&BI	50	-17.2	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW109 (B109) (0.0 to -10.0)	B109-05	04/12/12	SES	F&BI	5	30.0	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	B109-15	04/12/12	SES	F&BI	15	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B109-25	04/12/12	SES	F&BI	25	10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B109-35	04/12/12	SES	F&BI	35	0.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B109-45	04/12/12	SES	F&BI	45	-10.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW110 (B110) (4.7 to -5.3)	B110-15	04/12/12	SES	F&BI	15	24.7	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	B110-25	04/12/12	SES	F&BI	25	14.7	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B110-35	04/12/12	SES	F&BI	35	4.7	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B110-45	04/12/12	SES	F&BI	45	-5.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW111 (B111) (-33.5 to -43.5)	B111-10	05/12/12	SES	F&BI	10	26.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	B111-20	05/12/12	SES	F&BI	20	16.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B111-30	05/12/12	SES	F&BI	30	6.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B111-38	05/12/12	SES	F&BI	38	-1.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B111-50	05/12/12	SES	F&BI	50	-13.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B111-60	06/12/12	SES	F&BI	60	-23.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B111-70	06/12/12	SES	F&BI	70	-33.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B111-80	06/12/12	SES	F&BI	80	-43.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW112 (B112) (-17.5 to -27.5)	B112-10	11/12/12	SES	F&BI	10	47.5	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	B112-20	11/12/12	SES	F&BI	20	37.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B112-30	11/12/12	SES	F&BI	30	27.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B112-40	11/12/12	SES	F&BI	40	17.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B112-50	11/12/12	SES	F&BI	50	7.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B112-60	11/12/12	SES	F&BI	60	-2.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B112-75	11/12/12	SES	F&BI	75	-17.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B112-85	12/12/12	SES	F&BI	85	-27.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW113 (B113) (-37.1 to -47.1)	B113-10	12/18/12	SES	F&BI	10	22.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B113-20	12/18/12	SES	F&BI	20	12.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B113-30	12/18/12	SES	F&BI	30	2.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B113-40	12/18/12	SES	F&BI	40	-7.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B113-50	12/18/12	SES	F&BI	50	-17.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW114 (B114) (10.8 to 0.8)	B114-15	10/12/12	SES	F&BI	15	30.8	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	B114-25	10/12/12	SES	F&BI	25	20.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B114-35	10/12/12	SES	F&BI	35	10.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
MW114 (B114)	B114-40	10/12/12	SES	F&BI	40	5.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
(continued)	B114-45	10/12/12	SES	F&BI	45	0.8	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW115 (B115)	B115-10	12/13/12	SES	F&BI	10	24.1	V	–	–	–	–	–	–	–	–	–	–	–	–	–
(-0.9 to -10.9)	B115-15	12/13/12	SES	F&BI	15	19.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B115-25	12/13/12	SES	F&BI	25	9.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B115-35	12/13/12	SES	F&BI	35	-0.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B115-45	12/13/12	SES	F&BI	45	-10.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW116 (B116)	B116-15	07/12/12	SES	F&BI	15	16.4	S	–	–	–	–	–	–	–	–	–	–	–	–	–
(-3.6 to -13.6)	B116-25	07/12/12	SES	F&BI	25	6.4	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B116-35	07/12/12	SES	F&BI	35	-3.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B116-45	07/12/12	SES	F&BI	45	-13.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW117 (B117)	B117-10	02/04/13	SES	F&BI	10	46.9	V	–	–	–	–	–	–	–	–	–	–	–	–	–
(16.9 to 1.9)	B117-20	02/04/13	SES	F&BI	20	36.9	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	B117-30	02/04/13	SES	F&BI	30	26.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B117-40	02/04/13	SES	F&BI	40	16.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B117-50	02/04/13	SES	F&BI	50	6.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW118 (B118)	B118-10	03/21/13	SES	F&BI	10	42.9	V	–	–	–	–	–	–	–	–	–	–	–	–	–
(12.9 to 2.9)	B118-20	03/21/13	SES	F&BI	20	32.9	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	B118-30	03/21/13	SES	F&BI	30	22.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B118-40	03/21/13	SES	F&BI	40	12.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B118-50	03/21/13	SES	F&BI	50	2.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW119 (B119)	B119-10	03/21/13	SES	F&BI	10	27.4	V	–	–	–	–	–	–	–	–	–	–	–	–	–
(2.4 to -7.7)	B119-20	03/21/13	SES	F&BI	20	17.4	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B119-30	03/21/13	SES	F&BI	30	7.4	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B119-40	03/21/13	SES	F&BI	40	-2.7	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW120 (B120)	B120-20	12/16/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	0.3 U	–	–	–	–	–
(0 to -10)	B120-30	12/16/13	SES	F&BI	30	10.0	S	–	–	–	–	–	–	–	0.3 U	–	–	–	–	–
	B120-45	12/16/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	0.3 U	–	–	–	–	–
MW121 (B121)	B121-15	12/16/13	SES	F&BI	15	26.7	S	–	–	–	–	–	–	–	0.3 U	–	–	–	–	–
(26.7 to 16.7)	B121-25	12/16/13	SES	F&BI	25	16.7	S	–	–	–	–	–	–	–	0.3 U	–	–	–	–	–
MW122 (B122)	B122-15	12/17/13	SES	F&BI	15	15.0	S	–	–	–	–	–	–	–	**0.053**	–	–	–	–	–
(-75 to -89)	B122-25	12/17/13	SES	F&BI	25	5.0	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B122-40	12/17/13	SES	F&BI	40	-10.0	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B122-45	12/17/13	SES	F&BI	45	-15.0	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B122-50	12/17/13	SES	F&BI	50	-20.0	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B122-60	12/17/13	SES	F&BI	60	-30.0	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B122-70	12/17/13	SES	F&BI	70	-40.0	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B122-80	12/17/13	SES	F&BI	80	-50.0	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B122-100	12/17/13	SES	F&BI	100	-70.0	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
MW123 (B123)	B123-20	12/18/13	SES	F&BI	20	7.5	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
(-42.5 to -52.5)																				

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
MW124 (B124)	B124-10	12/19/13	SES	F&BI	10	46.2	V	–	–	–	–	–	–	–	–	–	–	–	–	–
(-53.8 to -63.8)	B124-20	12/19/13	SES	F&BI	20	36.2	V	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B124-30	12/19/13	SES	F&BI	30	26.2	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B124-40	12/19/13	SES	F&BI	40	16.2	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B124-50	12/19/13	SES	F&BI	50	6.2	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B124-60	12/19/13	SES	F&BI	60	-3.8	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B124-70	12/19/13	SES	F&BI	70	-13.8	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B124-80	12/19/13	SES	F&BI	80	-23.8	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B124-90	12/19/13	SES	F&BI	90	-33.8	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B124-100	12/19/13	SES	F&BI	100	-43.8	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B124-110	12/19/13	SES	F&BI	110	-53.8	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B124-120	12/19/13	SES	F&BI	120	-63.8	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
MW125 (B125)	B125-15	12/20/13	SES	F&BI	15	28.6	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
(28.6 to 13.6)	B125-20	12/20/13	SES	F&BI	20	23.6	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B125-25	12/20/13	SES	F&BI	25	18.6	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B125-30	12/20/13	SES	F&BI	30	13.6	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW126 (B126)	B126-20	12/30/13	SES	F&BI	20	10.9	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
(-54.1 to -64.1)	B126-35	12/30/13	SES	F&BI	35	-4.1	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B126-45	12/30/13	SES	F&BI	45	-14.1	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B126-55	12/30/13	SES	F&BI	55	-24.1	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B126-60	12/31/13	SES	F&BI	60	-29.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B126-65	01/01/14	SES	F&BI	65	-34.1	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B126-75	01/02/14	SES	F&BI	75	-44.1	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B126-80	01/03/14	SES	F&BI	80	-49.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B126-85	01/04/14	SES	F&BI	85	-54.1	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B126-95	01/05/14	SES	F&BI	95	-64.1	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MW127 (B127)	B127-15	12/31/13	SES	F&BI	15	24.0	V	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
(-1.0 to -11.0)	B127-25	12/31/13	SES	F&BI	25	14.0	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B127-40	12/31/13	SES	F&BI	40	-1.0	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B127-45	12/31/13	SES	F&BI	45	-6.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	B127-50	12/31/13	SES	F&BI	50	-11.0	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
MW128 (B128)	B128-25	01/09/14	SES	F&BI	25	2.9	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
(-30.8 to -40.8)	B128-45	01/09/14	SES	F&BI	45	-17.1	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
	B128-65	01/09/14	SES	F&BI	65	-37.1	S	–	–	–	–	–	–	–	0.03 U	–	–	–	–	–
MW-138	MW-138-15	09/12/17	PES	ESC	15	42.5	V	0.00556 U	0.000358 U	0.00163 U	0.000285 U	0.000243 U	0.0119 U	0.00213 U	0.000321 U	0.000338 U	0.000464 U	0.000504 U	0.00159 U	0.000263 U
(-47.5 to -57.5)	MW-138-25	09/12/17	PES	ESC	25	32.5	S	0.00539 U	0.000347 U	0.00158 U	0.000276 U	0.000235 U	0.0115 U	0.00206 U	0.000311 U	0.000327 U	0.000449 U	0.000488 U	0.00154 U	0.000254 U
	MW-138-35	09/12/17	PES	ESC	35	22.5	S	0.00500 U	0.000322 U	0.00146 U	0.000256 U	0.000218 U	0.0107 U	0.00191 U	0.000288 U	0.000303 U	0.000417 U	0.000453 U	0.00143 U	**0.000435 J**
	MW-138-45	09/12/17	PES	ESC	45	12.5	S	0.00495 U	0.000318 U	0.00145 U	0.000254 U	0.000216 U	0.0106 U	0.00189 U	0.000285 U	0.000300 U	0.000412 U	0.000448 U	0.00142 U	**0.000913 J**
	MW-138-56	09/12/17	PES	ESC	56	1.5	S	0.00526 U	0.000339 U	0.00154 U	0.000270 U	0.000229 U	0.0112 U	0.00201 U	0.000304 U	0.000319 U	0.000439 U	0.000477 U	0.00151 U	**0.00276**
	MW-138-65	09/13/17	PES	ESC	65	-7.5	S	0.00506 U	0.000326 U	0.00148 U	0.000260 U	0.000221 U	0.0108 U	0.00194 U	0.000292 U	0.000307 U	0.000422 U	0.000459 U	0.00145 U	**0.000333 J**
	B-910-90	09/13/17	PES	ESC	65 (dup)	-7.5	S	0.00542 U	0.000349 U	0.00159 U	0.000278 U	0.000236 U	0.0116 U	0.00207 U	0.000313 U	0.000329 U	0.000452 U	0.000491 U	0.00155 U	**0.000476 J**
	MW-138-75	09/13/17	PES	ESC	75	-17.5	S	0.00515 U	0.000331 U	0.00151 U	0.000264 U	0.000225 U	**0.0177 J**	0.00197 U	0.000297 U	0.000313 U	0.000429 U	0.000467 U	0.00148 U	**0.00122**
	MW-138-85	09/13/17	PES	ESC	85	-27.5	S	0.00563 U	0.000362 U	0.00165 U	0.000289 U	0.000245 U	**0.0124 J**	0.00215 U	0.000325 U	0.000341 U	0.000469 U	0.000510 U	0.00161 U	**0.000541 J**

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
MW-138	MW-138-95	09/13/17	PES	ESC	95	-37.5	S	0.00510 U	0.000328 U	0.00149 U	0.000262 U	0.000223 U	**0.0189 J**	0.00195 U	0.000295 U	0.000310 U	0.000425 U	0.000462 U	0.00146 U	**0.000930 J**
(continued)	MW-138-105	09/13/17	PES	ESC	105	-47.5	S	0.00582 U	0.000374 U	0.00170 U	0.000299 U	0.000254 U	0.0124 U	0.00223 U	0.000336 U	0.000353 U	0.000485 U	0.000527 U	0.00167 U	0.000275 U
	MW-138-115	09/14/17	PES	ESC	115	-57.5	S	0.00542 U	0.000349 U	0.00159 U	0.000278 U	0.000236 U	0.0116 U	0.00207 U	0.000313 U	0.000329 U	0.000452 U	0.000491 U	0.00155 U	0.000256 U
MW-140	MW-140-15	08/30/17	PES	ESC	15	35.6	V	0.00534 U	0.000343 U	0.00156 U	0.000274 U	0.000233 U	0.0114 U	0.00204 U	0.000308 U	0.000324 U	0.000445 U	0.000484 U	0.00153 U	0.000252 U
(-78.9 to -88.9)	MW-140-25	08/30/17	PES	ESC	25	25.6	S	0.00508 U	0.000326 U	0.00149 U	0.000260 U	0.000221 U	0.0108 U	0.00194 U	0.000293 U	0.000308 U	0.000423 U	0.000460 U	0.00145 U	**0.000278 J**
	MW-140-35	08/30/17	PES	ESC	35	15.6	S	0.136 U	0.00876 U	0.0398 U	0.00699 U	0.00594 U	0.291 U	0.0522 U	0.00786 U	0.00827 U	0.0114 U	0.0124 U	0.0390 U	0.00643 U
	MW-140-45	08/30/17	PES	ESC	45	5.6	S	0.00499 U	0.000321 U	0.00146 U	0.000256 U	0.000218 U	0.0107 U	0.00191 U	0.000288 U	0.000303 U	0.000416 U	0.000452 U	0.00143 U	**0.000774 J**
	MW-140-55	08/30/17	PES	ESC	55	-4.4	S	0.00514 U	0.000330 U	0.00150 U	0.000263 U	0.000224 U	0.0110 U	0.00196 U	**0.000379 J**	0.000312 U	0.000428 U	0.000465 U	0.00147 U	**0.00196**
	MW-140-65	08/30/17	PES	ESC	65	-14.4	S	0.00501 U	0.000322 U	0.00147 U	0.000257 U	0.000218 U	0.0107 U	0.00192 U	0.000289 U	0.000304 U	0.000418 U	0.000454 U	0.00143 U	**0.00384**
	MW-140-75	08/30/17	PES	ESC	75	-24.4	S	0.126 U	0.00811 U	0.0369 U	0.00647 U	0.00550 U	0.270 U	0.0483 U	0.00728 U	0.00766 U	0.0105 U	0.0114 U	0.0361 U	0.00595 U
	MW-140-90	08/30/17	PES	ESC	90	-39.4	S	0.00551 U	0.000354 U	0.00161 U	0.000282 U	0.000240 U	0.0118 U	0.00211 U	0.000318 U	0.000334 U	0.000459 U	0.000499 U	0.00158 U	0.000260 U
	MW-140-110	08/31/17	PES	ESC	110	-59.4	S	0.00542 U	0.000349 U	0.00159 U	0.000278 U	0.000236 U	0.0116 U	0.00207 U	0.000313 U	0.000329 U	0.000452 U	0.000491 U	0.00155 U	0.000256 U
	MW-140-130	08/31/17	PES	ESC	130	-79.4	S	0.00529 U	0.000340 U	0.00155 U	0.000271 U	0.000231 U	0.0113 U	0.00202 U	0.000305 U	0.000321 U	0.000441 U	0.000479 U	0.00152 U	0.000250 U
	MW-140-140	08/31/17	PES	ESC	140	-89.4	S	0.132 U	0.00849 U	0.0386 U	0.00678 U	0.00576 U	0.282 U	0.0506 U	0.00762 U	0.00802 U	0.0110 U	0.0120 U	0.0378 U	0.00623 U
MW-142 (2.4 to -7.6)	MW-142-5	04/12/18	PES	ESC	5	37.1	V	0.00563 U	0.000362 U	0.00165 U	0.000289 U	0.000245 U	0.0120 U	0.00215 U	**0.000392 J**	0.000342 U	0.000469 U	0.000510 U	0.00161 U	0.000266 U
MW-143	MW-143-10	04/11/18	PES	ESC	10	32.0	V	0.00649 U	0.000417 U	0.00190 U	0.000333 U	0.000283 U	**0.0437 J**	0.00248 U	**0.00459**	0.000394 U	0.000541 U	0.000588 U	0.00186 U	**0.000789 J**
(-27.7 to -37.7)	MW-143-20	04/11/18	PES	ESC	20	22.0	S	0.00544 U	0.000350 U	0.00159 U	0.000279 U	**0.000329 J**	**0.0142 J**	0.00208 U	0.000314 U	0.000330 U	0.000453 U	0.000493 U	0.00156 U	**0.000833 J**
	MW-143-30	04/11/18	PES	ESC	30	12.0	S	0.00533 U	0.000343 U	0.00156 U	0.000273 U	0.000232 U	0.0114 U	0.00204 U	0.000307 U	0.000323 U	0.000444 U	0.000483 U	0.00153 U	0.000252 U
	MW-143-40	04/11/18	PES	ESC	40	2.0	S	0.00558 U	0.000359 U	0.00163 U	0.000286 U	0.000243 U	0.0119 U	0.00214 U	0.000322 U	0.000339 U	0.000465 U	0.000506 U	0.00160 U	0.000264 U
	MW-143-50	04/11/18	PES	ESC	50	-8.0	S	0.00536 U	0.000345 U	0.00157 U	0.000275 U	0.000234 U	0.0115 U	0.00205 U	0.000309 U	0.000325 U	0.000447 U	0.000486 U	0.00153 U	0.000253 U
	MW-143-60	04/11/18	PES	ESC	60	-18.0	S	0.00520 U	0.000335 U	0.00152 U	0.000267 U	0.000227 U	0.0111 U	0.00199 U	0.000300 U	0.000316 U	0.000433 U	0.000471 U	0.00149 U	**0.000323 J**
	MW-143-70	04/11/18	PES	ESC	70	-28.0	S	0.00515 U	0.000331 U	0.00151 U	0.000264 U	0.000224 U	0.0110 U	0.00197 U	0.000297 U	0.000312 U	0.000429 U	0.000466 U	0.00147 U	**0.000487 J**
	MW-143-80	04/11/18	PES	ESC	80	-38.0	S	0.00532 U	0.000342 U	0.00156 U	0.000273 U	0.000232 U	0.0114 U	0.00203 U	0.000307 U	0.000323 U	0.000443 U	0.000482 U	0.00152 U	**0.000283 J**
	MW-902-20	04/11/18	PES	ESC	80 (dup)	-38.0	S	0.00524 U	0.000337 U	0.00153 U	0.000269 U	0.000228 U	0.0112 U	0.00200 U	0.000302 U	0.000318 U	0.000436 U	0.000474 U	0.00150 U	0.000247 U
MW-145	MW-145-10	04/17/18	PES	ESC	10	33.5	V	0.00588 U	0.000378 U	0.00172 U	0.000302 U	0.000256 U	**0.0194 J**	0.00225 U	0.000339 U	0.000357 U	0.000490 U	0.000533 U	0.00168 U	0.000278 U
(-26.1 to -36.1)	MW-145-20	04/17/18	PES	ESC	20	23.5	S	0.00546 U	0.000351 U	0.00160 U	0.000280 U	0.000238 U	0.0117 U	0.00209 U	0.000315 U	0.000332 U	0.000455 U	0.000495 U	0.00156 U	0.000258 U
	MW-145-30	04/17/18	PES	ESC	30	13.5	S	0.00555 U	0.000357 U	0.00162 U	0.000285 U	0.000242 U	0.0119 U	0.00212 U	0.000320 U	0.000337 U	0.000462 U	0.000503 U	0.00159 U	0.000262 U
	MW-145-40	04/17/18	PES	ESC	40	3.5	S	**0.00537 J**	0.000335 U	0.00153 U	0.000267 U	0.000227 U	**0.0144 J**	0.00199 U	0.000301 U	0.000316 U	0.000435 U	0.000472 U	0.00149 U	**0.000551 J**
	MW-145-50	04/17/18	PES	ESC	50	-6.5	S	**0.00735 J**	0.000330 U	0.00150 U	0.000263 U	0.000224 U	0.0110 U	0.00196 U	0.000296 U	0.000311 U	0.000427 U	0.000465 U	0.00147 U	0.000242 U
	MW-145-60	04/17/18	PES	ESC	60	-16.5	S	0.00516 U	0.000332 U	0.00151 U	0.000265 U	0.000225 U	0.0110 U	0.00197 U	0.000298 U	0.000313 U	0.000430 U	0.000467 U	0.00148 U	0.000244 U
	MW-145-70	04/17/18	PES	ESC	70	-26.5	S	0.00568 U	0.000365 U	0.00166 U	0.000291 U	0.000247 U	0.0121 U	0.00217 U	0.000327 U	0.000344 U	0.000473 U	0.000514 U	0.00163 U	**0.000275 J**
	MW-145-80	04/17/18	PES	ESC	80	-36.5	S	0.00538 U	0.000346 U	0.00157 U	0.000276 U	0.000234 U	0.0115 U	0.00206 U	0.000310 U	0.000326 U	0.000448 U	0.000487 U	0.00154 U	0.000254 U
	MW-903-40	04/17/18	PES	ESC	80 (dup)	-36.5	S	0.00525 U	0.000338 U	0.00154 U	0.000269 U	0.000229 U	**0.0125 J**	0.00201 U	0.000303 U	0.000319 U	0.000437 U	0.000476 U	0.00150 U	**0.000685 J**
MW-147	MW-147-10	04/02/18	PES	ESC	10	41.9	V	0.00508 U	0.000327 U	0.00149 U	0.000261 U	0.000222 U	**0.0111 J**	0.00194 U	**0.000566 J**	0.000308 U	0.000424 U	0.000460 U	0.00146 U	**0.000653 J**
(-17.6 to -27.6)	MW-147-20	04/02/18	PES	ESC	20	31.9	S	0.00506 U	0.000325 U	0.00148 U	0.000259 U	0.000220 U	0.0108 U	0.00193 U	0.000292 U	0.000307 U	0.000421 U	0.000458 U	0.00145 U	**0.00140**
	MW-147-30	04/02/18	PES	ESC	30	21.9	S	0.00523 U	0.000336 U	0.00153 U	0.000268 U	0.000228 U	0.0112 U	0.00200 U	0.000301 U	0.000317 U	0.000435 U	0.000473 U	0.00150 U	0.000247 U
	MW-147-40	04/02/18	PES	ESC	40	11.9	S	**0.00707 J**	0.000332 U	0.00151 U	0.000265 U	0.000225 U	**0.0113 J**	0.00198 U	0.000298 U	0.000313 U	0.000430 U	0.000468 U	0.00148 U	**0.000405 J**
	MW-147-50	04/02/18	PES	ESC	50	1.9	S	0.00518 U	0.000333 U	0.00152 U	0.000266 U	0.000226 U	**0.0121 J**	0.00198 U	0.000299 U	0.000315 U	0.000432 U	0.000470 U	0.00148 U	0.000245 U
	MW-147-60	04/02/18	PES	ESC	60	-8.2	S	0.00503 U	0.000324 U	0.00147 U	0.000258 U	0.000219 U	**0.0145 J**	0.00192 U	0.000290 U	0.000305 U	0.000419 U	0.000456 U	0.00144 U	0.000238 U
	MW-901-10	04/02/18	PES	ESC	60 (dup)	-8.2	S	0.00504 U	0.000324 U	0.00148 U	0.000258 U	0.000220 U	**0.0193 J**	0.00193 U	0.000291 U	0.000306 U	0.000420 U	0.000457 U	0.00144 U	**0.000480 J**
	MW-147-70	04/02/18	PES	ESC	70	-18.2	S	0.00524 U	0.000337 U	0.00153 U	0.000269 U	0.000228 U	0.0112 U	0.00200 U	0.000302 U	0.000318 U	0.000436 U	0.000475 U	0.00150 U	0.000247 U
	MW-147-80	04/02/18	PES	ESC	80	-28.2	S	0.00542 U	0.000348 U	0.00159 U	0.000278 U	0.000236 U	**0.0159 J**	0.00207 U	0.000312 U	0.000329 U	0.000451 U	0.000491 U	0.00155 U	0.000256 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
MW-148	MW-148-11	04/09/18	PES	ESC	11	32.9	V	**0.00585 J**	0.000347 U	0.00158 U	0.000277 U	0.000235 U	**0.0266 J**	0.00207 U	**0.000728 J**	0.000328 U	0.000450 U	0.000489 U	0.00155 U	**0.00130**
(-25.7 to -35.7)	MW-148-20	04/09/18	PES	ESC	20	23.9	S	0.00508 U	0.000327 U	0.00149 U	0.000260 U	0.000221 U	0.0108 U	0.00194 U	0.000293 U	0.000308 U	0.000423 U	0.000460 U	0.00145 U	**0.000247 J**
	MW-148-30	04/09/18	PES	ESC	30	13.9	S	0.00526 U	0.000338 U	0.00154 U	0.000269 U	0.000229 U	0.0112 U	0.00201 U	0.000303 U	0.000319 U	0.000438 U	0.000476 U	0.00150 U	0.000248 U
	MW-148-40	04/09/18	PES	ESC	40	3.9	S	0.00508 U	0.000327 U	0.00149 U	0.000261 U	0.000222 U	0.0109 U	0.00194 U	0.000293 U	0.000309 U	0.000424 U	0.000461 U	0.00146 U	**0.000261 J**
	MW-148-50	04/09/18	PES	ESC	50	-6.1	S	0.00516 U	0.000332 U	0.00151 U	0.000265 U	0.000225 U	0.0110 U	0.00197 U	0.000298 U	0.000313 U	0.000430 U	0.000468 U	0.00148 U	**0.000256 J**
	MW-148-60	04/09/18	PES	ESC	60	-16.1	S	0.00591 U	0.000380 U	0.00173 U	0.000303 U	0.000257 U	0.0126 U	0.00226 U	0.000341 U	0.000358 U	0.000492 U	0.000535 U	0.00169 U	0.000279 U
	MW-148-70	04/09/18	PES	ESC	70	-26.1	S	0.00590 U	0.000379 U	0.00173 U	0.000302 U	0.000257 U	**0.0198 J**	0.00226 U	0.000340 U	0.000358 U	0.000491 U	0.000534 U	0.00169 U	**0.000395 J**
	MW-148-80	04/09/18	PES	ESC	80	-36.1	S	0.00550 U	0.000354 U	0.00161 U	0.000282 U	0.000240 U	**0.0118 J**	0.00210 U	0.000317 U	0.000334 U	0.000458 U	0.000498 U	0.00157 U	0.000260 U
MW-153	MW-153-10	03/27/18	PES	ESC	10	44.4	V	0.00531 U	0.000341 U	0.00155 U	0.000272 U	0.000231 U	0.0113 U	0.00203 U	0.000306 U	0.000322 U	0.000442 U	0.000481 U	0.00152 U	0.000251 U
(-65.3 to -75.3)	MW-153-20	03/27/18	PES	ESC	20	34.4	V	0.00512 U	0.000329 U	0.00150 U	0.000263 U	0.000223 U	0.0109 U	0.00196 U	0.000296 U	0.000311 U	0.000427 U	0.000464 U	0.00147 U	0.000242 U
	MW-153-30	03/27/18	PES	ESC	30	24.4	S	0.00502 U	0.000323 U	0.00147 U	0.000257 U	0.000219 U	0.0107 U	0.00192 U	0.000290 U	0.000305 U	0.000418 U	0.000455 U	0.00144 U	0.000237 U
	MW-153-40	03/27/18	PES	ESC	40	14.4	S	0.00530 U	0.000341 U	0.00155 U	0.000272 U	0.000231 U	0.0113 U	0.00203 U	0.000306 U	0.000322 U	0.000442 U	0.000480 U	0.00152 U	**0.000332 J**
	MW-153-50	03/27/18	PES	ESC	50	4.4	S	0.00519 U	0.000334 U	0.00152 U	0.000266 U	0.000226 U	0.0111 U	0.00199 U	0.000299 U	0.000315 U	0.000433 U	0.000470 U	0.00149 U	0.000245 U
	MW-153-61	03/27/18	PES	ESC	61	-6.7	S	0.00532 U	0.000342 U	0.00156 U	0.000273 U	0.000232 U	0.0114 U	0.00203 U	0.000307 U	0.000323 U	0.000443 U	0.000482 U	0.00152 U	0.000251 U
	MW-153-70	03/27/18	PES	ESC	70	-15.7	S	0.00521 U	0.000335 U	0.00153 U	0.000267 U	0.000227 U	0.0111 U	0.00199 U	0.000301 U	0.000316 U	0.000434 U	0.000472 U	0.00149 U	0.000246 U
	MW-153-80	03/28/18	PES	ESC	80	-25.7	S	0.00516 U	0.000332 U	0.00151 U	0.000265 U	0.000225 U	0.0110 U	0.00197 U	0.000298 U	0.000313 U	0.000430 U	0.000468 U	0.00148 U	**0.000314 J**
	MW-153-90	03/28/18	PES	ESC	90	-35.7	S	0.00564 U	0.000362 U	0.00165 U	0.000289 U	0.000246 U	0.0120 U	0.00216 U	0.000325 U	0.000342 U	0.000470 U	0.000511 U	0.00161 U	**0.000436 J**
	MW-153-110	03/28/18	PES	ESC	110	-55.7	S	0.00551 U	0.000354 U	0.00161 U	0.000282 U	0.000240 U	0.0118 U	0.00211 U	0.000318 U	0.000334 U	0.000459 U	0.000499 U	0.00158 U	**0.000319 J**
	MW-153-130	03/29/18	PES	ESC	130	-75.7	S	0.00538 U	0.000346 U	0.00157 U	0.000276 U	0.000234 U	0.0115 U	0.00206 U	0.000310 U	0.000326 U	0.000448 U	0.000487 U	0.00154 U	0.000254 U
MW-158	MW-158-20	04/05/18	PES	ESC	20	21.1	S	0.00530 U	0.000341 U	0.00155 U	0.000272 U	0.000231 U	0.0113 U	0.00203 U	**0.000584 J**	0.000322 U	0.000442 U	0.000480 U	0.00152 U	**0.000327 J**
	MW-158-30	04/05/18	PES	ESC	30	11.1	S	0.552 U	0.0355 U	0.162 U	0.0283 U	0.0241 U	1.18 U	0.211 U	0.0318 U	0.0335 U	0.0460 U	0.0500 U	0.158 U	0.0261 U
MW-158A	MW-158A-40	04/05/18	PES	ESC	40	1.1	S	0.00577 U	0.000371 U	0.00169 U	0.000296 U	0.000251 U	0.0123 U	0.00221 U	**0.000424 J**	0.000350 U	0.000481 U	0.000523 U	0.00165 U	**0.000620 J**
(-47.2 to -58.5)	MW-158A-50	04/05/18	PES	ESC	50	-8.9	S	0.00541 U	0.000348 U	0.00158 U	0.000278 U	0.000236 U	0.0116 U	0.00207 U	0.000312 U	0.000328 U	0.000451 U	0.000490 U	0.00155 U	**0.000264 J**
	MW-158A-60	04/05/18	PES	ESC	60	-18.9	S	0.00539 U	0.000346 U	0.00158 U	0.000276 U	0.000235 U	0.0115 U	0.00206 U	0.000311 U	0.000327 U	0.000449 U	0.000488 U	0.00154 U	0.000254 U
	MW-158A-70	04/05/18	PES	ESC	70	-28.9	S	0.00525 U	0.000338 U	0.00154 U	0.000269 U	0.000229 U	0.0112 U	0.00201 U	0.000303 U	0.000319 U	0.000438 U	0.000476 U	0.00150 U	**0.000277 J**
	MW-158A-80	04/06/18	PES	ESC	80	-38.9	S	0.00519 U	0.000334 U	0.00152 U	0.000266 U	0.000226 U	0.0111 U	0.00199 U	0.000299 U	0.000315 U	0.000433 U	0.000470 U	0.00149 U	0.000245 U
	MW-158A-90	04/06/18	PES	ESC	90	-48.9	S	0.00537 U	0.000345 U	0.00157 U	0.000275 U	0.000234 U	0.0115 U	0.00205 U	0.000310 U	0.000326 U	0.000447 U	0.000486 U	0.00154 U	0.000254 U
	MW-158A-100	04/06/18	PES	ESC	100	-58.9	S	0.00550 U	0.000354 U	0.00161 U	0.000282 U	0.000240 U	0.0117 U	0.00210 U	0.000317 U	0.000334 U	0.000458 U	0.000498 U	0.00157 U	0.000260 U
MW-159	MW-159-20	04/16/18	PES	ESC	20	22.8	S	0.00566 U	0.000364 U	0.00166 U	0.000290 U	0.000247 U	0.0121 U	0.00216 U	0.000326 U	0.000343 U	0.000471 U	0.000513 U	0.00162 U	**0.000697 J**
(22.9 to 12.9)	MW-159-30	04/16/18	PES	ESC	30	12.8	S	0.00570 U	0.000367 U	0.00167 U	0.000292 U	0.000249 U	0.0122 U	0.00218 U	0.000329 U	0.000346 U	0.000475 U	0.000517 U	0.00163 U	0.000269 U
MW-160	MW-160-11	05/08/18	PES	ESC	11	31.5	S	0.0203 U	0.00149 U	0.0162 U	0.00183 U	0.00378 U	**0.0290 J**	0.00309 U	0.000649 U	0.00170 U	0.00183 U	0.00971 U	0.00601 U	**0.00861 J**
(-76.5 to -86.5)	MW-160-21	05/08/18	PES	ESC	21	21.5	S	0.0147 U	0.00108 U	0.0117 U	0.00132 U	0.00273 U	**0.0255 J**	0.00223 U	**0.000662 J**	0.00123 U	0.00132 U	0.00701 U	0.00434 U	0.00476 U
	MW-160-31	05/08/18	PES	ESC	31	11.5	S	0.0152 U	0.00112 U	0.0121 U	0.00137 U	0.00283 U	**0.0203 J**	0.00230 U	**0.000503 J**	0.00127 U	0.00137 U	0.00725 U	0.00449 U	0.00492 U
	MW-160-40	05/08/18	PES	ESC	40	2.5	S	0.0142 U	0.00104 U	0.0114 U	0.00128 U	0.00265 U	0.0156 U	0.00216 U	0.000454 U	0.00119 U	0.00128 U	0.00679 U	0.00420 U	0.00461 U
	MW-160-50	05/08/18	PES	ESC	50	-7.5	S	0.0143 U	0.00105 U	0.0114 U	0.00129 U	0.00266 U	0.0157 U	0.00217 U	0.000457 U	0.00120 U	0.00129 U	0.00683 U	0.00423 U	0.00464 U
	MW-160-55	05/08/18	PES	ESC	55	-12.5	S	0.0148 U	0.00109 U	0.0119 U	0.00134 U	0.00276 U	0.0162 U	0.00225 U	0.000474 U	0.00125 U	0.00134 U	0.00709 U	0.00439 U	0.00482 U
	MW-160-60	05/08/18	PES	ESC	60	-17.5	S	0.0136 U	0.00100 U	0.0109 U	0.00123 U	0.00254 U	**0.0178 J**	0.00207 U	**0.00134**	0.00114 U	0.00123 U	0.00652 U	0.00403 U	0.00442 U
	MW-160-70	05/08/18	PES	ESC	70	-27.5	S	0.0146 U	0.00107 U	0.0117 U	0.00132 U	0.00272 U	**0.0208 J**	0.00222 U	0.000467 U	0.00123 U	0.00132 U	0.00699 U	0.00432 U	0.00474 U
	MW-160-90	05/08/18	PES	ESC	90	-47.5	S	0.0147 U	0.00108 U	0.0118 U	0.00133 U	0.00274 U	**0.0176 J**	0.00224 U	0.000471 U	0.00124 U	0.00133 U	0.00704 U	0.00435 U	0.00478 U
	MW-160-100	05/08/18	PES	ESC	100	-57.5	S	0.0150 U	0.00111 U	0.0120 U	0.00136 U	0.00280 U	0.0165 U	0.00229 U	0.000481 U	0.00126 U	0.00136 U	0.00719 U	0.00445 U	0.00488 U
	MW-160-110	05/08/18	PES	ESC	110	-67.5	S	0.0142 U	0.00104 U	0.0113 U	0.00128 U	0.00264 U	0.0155 U	0.00215 U	0.000454 U	0.00119 U	0.00128 U	0.00678 U	0.00420 U	0.00460 U
	MW-160-125	05/10/18	PES	ESC	125	-82.5	S	0.0143 U	0.00105 U	0.0114 U	0.00129 U	0.00267 U	**0.0198 J**	0.00218 U	0.000458 U	0.00120 U	0.00129 U	0.00685 U	0.00424 U	0.00465 U
	MW-160-127.5	05/10/18	PES	ESC	128	-85.0	S	0.0144 U	0.00106 U	0.0115 U	0.00130 U	0.00269 U	0.0158 U	0.00219 U	0.000462 U	0.00121 U	0.00130 U	0.00691 U	0.00427 U	0.00469 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
MW-161	MW-161-11	05/14/18	PES	ESC	11	32.8	S	0.0154 U	0.00113 U	–	0.00139 U	0.00286 U	0.0168 U	0.00234 U	0.00123 U	0.00129 U	–	0.00735 U	0.00455 U	–
(-78.9 to -88.9)	MW-161-21	05/14/18	PES	ESC	21	22.8	S	0.0130 U	0.000956 U	–	0.00117 U	0.00242 U	0.0142 U	0.00198 U	0.00104 U	0.00109 U	–	0.00622 U	0.00385 U	–
	MW-161-31	05/14/18	PES	ESC	31	12.8	S	0.0143 U	0.00105 U	–	0.00129 U	0.00267 U	0.0157 U	0.00218 U	0.00114 U	0.00120 U	–	0.00685 U	0.00424 U	–
	MW-161-40	05/14/18	PES	ESC	40	3.8	S	0.0138 U	0.00102 U	–	0.00125 U	0.00257 U	0.0151 U	0.00210 U	0.00110 U	0.00116 U	–	0.00660 U	0.00408 U	–
	MW-161-50	05/14/18	PES	ESC	50	-6.2	S	0.0139 U	0.00103 U	–	0.00126 U	0.00260 U	0.0153 U	0.00212 U	0.00112 U	0.00117 U	–	0.00667 U	0.00413 U	–
	MW-161-60	05/14/18	PES	ESC	60	-16.2	S	0.0143 U	0.00105 U	–	0.00129 U	0.00266 U	0.0156 U	0.00217 U	0.00114 U	0.00120 U	–	0.00683 U	0.00423 U	–
	MW-161-70	05/14/18	PES	ESC	70	-26.2	S	0.0140 U	0.00103 U	–	0.00126 U	0.00260 U	0.0153 U	0.00212 U	0.00112 U	0.00117 U	–	0.00668 U	0.00413 U	–
	MW-161-80	05/14/18	PES	ESC	80	-36.2	S	0.0154 U	0.00113 U	–	0.00139 U	0.00287 U	0.0169 U	0.00234 U	0.00123 U	0.00129 U	–	0.00737 U	0.00456 U	–
	MW-161-90	05/14/18	PES	ESC	90	-46.2	S	0.0142 U	0.00105 U	–	0.00129 U	0.00265 U	0.0156 U	0.00216 U	0.00114 U	0.00119 U	–	0.00681 U	0.00421 U	–
	B-927-30	05/14/18	PES	ESC	90 (dup)	-46.2	S	0.0155 U	0.00114 U	–	0.00140 U	0.00289 U	0.0170 U	0.00236 U	0.00124 U	0.00130 U	–	0.00743 U	0.00459 U	–
	MW-161-100	05/14/18	PES	ESC	100	-56.2	S	0.0146 U	0.00107 U	–	0.00132 U	0.00271 U	0.0160 U	0.00221 U	0.00116 U	0.00122 U	–	0.00696 U	0.00431 U	–
	MW-161-110	05/14/18	PES	ESC	110	-66.2	S	0.0152 U	0.00112 U	–	0.00138 U	0.00284 U	0.0167 U	0.00232 U	0.00122 U	0.00128 U	–	0.00729 U	0.00451 U	–
	MW-161-120	05/14/18	PES	ESC	120	-76.2	S	0.0153 U	0.00112 U	–	0.00138 U	0.00284 U	0.0167 U	0.00232 U	0.00122 U	0.00128 U	–	0.00730 U	0.00451 U	–
	MW-161-130	05/14/18	PES	ESC	130	-86.2	S	0.0137 U	0.00101 U	–	0.00124 U	0.00256 U	0.0151 U	0.00209 U	0.00110 U	0.00115 U	–	0.00658 U	0.00407 U	–
	MW-161-140	05/15/18	PES	ESC	140	-96.2	S	0.0153 U	0.00113 U	0.0123 U	0.00139 U	0.00286 U	0.0168 U	0.00233 U	**0.000580 J**	0.00129 U	0.00139 U	0.00733 U	0.00454 U	0.00498 U
MW-190	MW-190-5	09/19/19	PES	PACE	5	43.7	V	**0.0188 J**	0.00106 U	0.0115 U	0.00130 U	0.00269 U	**0.0289**	0.00219 U	**0.000741 J**	0.00121 U	0.00130 U	0.00690 U	0.00427 U	0.00468 U
(-30.2 to -40.2)	MW-190-10	09/19/19	PES	PACE	10	38.7	V	**0.0597**	0.00191 U	0.0207 U	0.00234 U	**0.0104**	**0.0911**	0.00393 U	**0.00553**	0.00216 U	0.00234 U	0.0124 U	0.00765 U	0.00840 U
	MW-190-15	09/19/19	PES	PACE	15	33.7	S	**0.0360**	0.00122 U	0.0132 U	0.00150 U	0.00308 U	**0.0618**	0.00252 U	0.000530 U	0.00139 U	0.00150 U	0.00792 U	0.00490 U	0.00537 U
	MW-190-20	09/19/19	PES	PACE	20	28.7	S	**0.0454**	0.00115 U	0.0124 U	0.00141 U	0.00290 U	**0.0748**	0.00236 U	**0.00144**	0.00131 U	0.00141 U	0.00744 U	0.00461 U	**0.00676 J**
	MW-190-25	09/19/19	PES	PACE	25	23.7	S	**0.0238 J**	0.00108 U	0.0117 U	0.00133 U	0.00273 U	**0.0414**	0.00223 U	**0.000484 J**	0.00123 U	0.00133 U	0.00702 U	0.00434 U	0.00477 U
	MW-190-30	09/19/19	PES	PACE	30	18.7	S	**0.0201 J**	0.000964 U	0.0105 U	0.00118 U	0.00244 U	**0.0348**	0.00199 U	0.000419 U	0.00110 U	0.00118 U	0.00627 U	0.00388 U	0.00425 U
	MW-190-35	09/19/19	PES	PACE	35	13.7	S	**0.0213 J**	0.000977 U	0.0106 U	0.00120 U	0.00248 U	**0.0352**	0.00202 U	0.000425 U	0.00112 U	0.00120 U	0.00635 U	0.00393 U	0.00431 U
	MW-190-40	09/19/19	PES	PACE	40	8.7	S	**0.0157 J**	0.00103 U	0.0112 U	0.00127 U	0.00262 U	**0.0313**	0.00213 U	0.000449 U	0.00118 U	0.00127 U	0.00671 U	0.00415 U	0.00456 U
	MW-190-45	09/19/19	PES	PACE	45	3.7	S	**0.0151 J**	0.00105 U	0.0114 U	0.00129 U	0.00266 U	**0.0282 J**	0.00217 U	0.000457 U	0.00120 U	0.00129 U	0.00684 U	0.00423 U	0.00464 U
	MW-190-50	09/19/19	PES	PACE	50	-1.4	S	**0.0208 J**	0.000964 U	0.0105 U	0.00118 U	0.00244 U	**0.0337**	0.00199 U	**0.000610 J**	0.00110 U	0.00118 U	0.00626 U	0.00388 U	0.00425 U
	MW-190-55	09/19/19	PES	PACE	55	-6.4	S	**0.0189 J**	0.000998 U	0.0108 U	0.00123 U	0.00253 U	**0.0295**	0.00206 U	**0.000459 J**	0.00114 U	0.00123 U	0.00649 U	0.00401 U	0.00440 U
	MW-190-60	09/19/19	PES	PACE	60	-11.4	S	**0.0149 J**	0.00100 U	0.0109 U	0.00123 U	0.00254 U	**0.0266 J**	0.00207 U	**0.000462 J**	0.00114 U	0.00123 U	0.00652 U	0.00403 U	0.00442 U
	MW-2008-60	09/19/19	PES	PACE	60 (dup)	-11.4	S	0.0135 U	0.000994 U	0.0108 U	0.00122 U	0.00252 U	**0.0356**	0.00205 UJ	0.000432 U	0.00113 U	0.00122 U	0.00646 U	0.00400 U	0.00439 U
	MW-190-65	09/19/19	PES	PACE	65	-16.4	S	**0.0163 J**	0.00102 U	0.0110 U	0.00125 U	0.00257 U	**0.0369**	0.00210 U	**0.000683 J**	0.00116 U	0.00125 U	0.00660 U	0.00409 U	0.00448 U
	MW-190-70	09/19/19	PES	PACE	70	-21.4	S	0.0138 U	0.00102 U	0.0111 U	0.00125 U	0.00258 U	**0.0402**	0.00210 UJ	0.000443 U	0.00116 U	0.00125 U	0.00662 U	0.00410 U	0.00450 U
	MW-190-75	09/19/19	PES	PACE	75	-26.4	S	0.0137 U	0.00101 U	0.0109 U	0.00124 U	0.00255 U	**0.0363**	0.00208 UJ	0.000437 U	0.00115 U	0.00124 U	0.00654 U	0.00405 U	0.00444 U
	MW-190-80	09/19/19	PES	PACE	80	-31.4	S	0.0136 U	0.00100 U	0.0109 U	0.00123 U	0.00254 U	**0.0540**	0.00207 UJ	0.000437 U	0.00115 U	0.00123 U	0.00653 U	0.00404 U	0.00443 U
	MW-190-85	09/19/19	PES	PACE	85	-36.4	S	0.0144 U	0.00106 U	0.0115 U	0.00130 U	0.00268 U	**0.0590**	0.00218 UJ	0.000460 U	0.00121 U	0.00130 U	0.00687 U	0.00425 U	0.00467 U
	MW-190-87	09/19/19	PES	PACE	87	-38.4	S	0.0149 U	0.00110 U	0.0120 U	0.00135 U	0.00278 U	**0.0578**	0.00227 UJ	**0.000521 J**	0.00125 U	0.00135 U	0.00715 U	0.00442 U	0.00485 U
MW-301	MW-301-6	09/20/19	PES	PACE	6	47.8	V	**0.0224 J**	0.00108 U	0.0117 U	0.00132 U	0.00273 U	**0.0409**	0.00223 U	0.000469 U	0.00123 U	0.00132 U	0.00701 U	0.00434 U	0.00476 U
(35.6 to 25.6)	MW-301-10	09/20/19	PES	PACE	10	43.8	V	**0.0226 J**	0.00101 U	0.0110 U	0.00124 U	0.00256 U	**0.0380**	0.00209 U	0.000440 U	0.00115 U	0.00124 U	0.00658 U	0.00407 U	0.00446 U
	MW-301-15	09/20/19	PES	PACE	15	38.8	V	**0.0300**	0.00104 U	0.0114 U	0.00128 U	0.00265 U	**0.0512**	0.00216 U	0.000454 U	0.00119 U	0.00128 U	0.00679 U	0.00420 U	0.00461 U
	MW-301-20	09/20/19	PES	PACE	20	33.8	S	**0.0453 J**	0.00310 U	0.0338 U	0.00382 U	0.00787 U	**0.118**	0.00642 U	0.00135 U	0.00355 U	0.00382 U	0.0202 U	0.0125 U	0.0137 U
	MW-301-25	09/20/19	PES	PACE	25	28.8	S	**0.0291**	0.00105 U	0.0114 U	0.00128 U	0.00265 U	**0.0408**	0.00216 U	0.000455 U	0.00119 U	0.00128 U	0.00680 U	0.00421 U	0.00461 U
	MW-301-30	09/20/19	PES	PACE	30	23.8	S	**0.0301 J**	0.00113 U	0.0124 U	0.00139 U	0.00288 U	**0.0652**	0.00235 U	0.000495 U	0.00130 U	0.00139 U	0.00740 U	0.00458 U	0.00502 U
MW-302	MW-302-5	10/01/19	PES	PACE	5	52.3	V	0.0146 U	0.00108 U	0.0117 U	0.00132 U	0.00273 U	**0.0289 J**	0.00222 U	0.000468 U	0.00123 U	0.00132 U	0.00700 U	0.00433 U	0.00475 U
(3.0 to -7.0)	MW-302-10	10/01/19	PES	PACE	10	47.3	V	0.0156 U	0.00114 U	0.0124 U	0.00141 U	0.00290 U	0.0170 U	0.00236 U	0.000498 U	0.00131 U	0.00141 U	0.00744 U	0.00460 U	0.00505 U
	MW-302-15	10/01/19	PES	PACE	15	42.3	V	0.0170 U	0.00126 U	0.0136 U	0.00154 U	0.00317 U	**0.0476**	0.00259 U	0.000545 U	0.00143 U	0.00154 U	0.00816 U	0.00504 U	0.00554 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
MW-302 (continued)	MW-302-20	10/01/19	PES	PACE	20	37.3	S	0.0149 U	0.00110 U	0.0119 U	0.00135 U	0.00278 U	**0.0267 J**	0.00227 U	0.000477 U	0.00125 U	0.00135 U	0.00714 U	0.00442 U	0.00485 U
	MW-302-25	10/01/19	PES	PACE	25	32.3	S	0.0140 U	0.00103 U	0.0112 U	0.00127 U	0.00261 U	**0.0168 J**	0.00213 U	0.000448 U	0.00118 U	0.00127 U	0.00670 U	0.00415 U	0.00455 U
	MW-302-30	10/01/19	PES	PACE	30	27.3	S	0.0137 U	0.00101 U	0.0109 U	0.00124 U	0.00255 U	0.0150 U	0.00208 U	0.000438 U	0.00115 U	0.00124 U	0.00654 U	0.00405 U	0.00444 U
	MW-302-35	10/01/19	PES	PACE	35	22.3	S	0.0134 U	0.000989 U	0.0107 U	0.00121 U	0.00250 U	**0.0299**	0.00204 U	0.000430 U	0.00113 U	0.00121 U	0.00643 U	0.00398 U	0.00436 U
	MW-302-40	10/01/19	PES	PACE	40	17.3	S	0.0133 U	0.000979 U	0.0106 U	0.00120 U	0.00248 U	**0.0200 J**	0.00202 U	0.000425 U	0.00112 U	0.00120 U	0.00636 U	0.00394 U	0.00432 U
	MW-302-45	10/01/19	PES	PACE	45	12.3	S	0.0149 U	0.00110 U	0.0119 U	0.00135 U	0.00278 U	**0.0581**	0.00226 U	0.000477 U	0.00125 U	0.00135 U	0.00712 U	0.00441 U	0.00484 U
	MW-302-50	10/01/19	PES	PACE	50	7.3	S	0.0149 U	0.00110 U	0.0119 U	0.00135 U	0.00278 U	**0.0540**	0.00227 U	0.000478 U	0.00125 U	0.00135 U	0.00714 U	0.00442 U	0.00485 U
	MW-302-55	10/01/19	PES	PACE	55	2.3	S	0.0142 U	0.00105 U	0.0114 U	0.00128 U	0.00265 U	**0.0182 J**	0.00216 U	0.000455 U	0.00119 U	0.00128 U	0.00680 U	0.00420 U	**0.00497 J**
	MW-302-60	10/01/19	PES	PACE	60	-2.7	S	0.0178 U	0.00130 U	0.0142 U	0.00161 U	0.00332 U	**0.0342 J**	0.00270 U	0.000569 U	0.00149 U	0.00161 U	0.00850 U	0.00526 U	**0.00643 J**
	MW-302-65	10/01/19	PES	PACE	65	-7.7	S	0.0146 U	0.00108 U	0.0117 U	0.00132 U	0.00273 U	**0.0529**	0.00223 U	0.000468 U	0.00123 U	0.00132 U	0.00700 U	0.00433 U	0.00475 U
	MW-2014-65	10/01/19	PES	PACE	65 (dup)	-7.7	S	**0.0252 J**	0.00112 U	0.0121 U	0.00137 U	0.00282 U	**0.0515**	0.00230 U	0.000485 U	0.00127 U	0.00137 U	0.00725 U	0.00449 U	0.00492 U
MW-304 (-47.6 to -57.6)	MW-304-5	10/01/19	PES	PACE	5	52.6	V	**0.0178 J**	0.00104 U	0.0113 U	0.00127 U	0.00262 U	0.0154 U	0.00214 U	0.000451 U	0.00118 U	0.00127 U	0.00674 U	0.00417 U	0.00457 U
	MW-304-10	10/01/19	PES	PACE	10	47.6	V	**0.0216 J**	0.00105 U	0.0114 U	0.00129 U	0.00265 U	0.0156 U	0.00216 U	0.000456 U	0.00120 U	0.00129 U	0.00681 U	0.00422 U	0.00463 U
	MW-304-15	10/01/19	PES	PACE	15	42.6	V	**0.0241 J**	0.00109 U	0.0119 U	0.00134 U	0.00277 U	0.0163 U	0.00226 U	0.000476 U	0.00125 U	0.00134 U	0.00711 U	0.00440 U	0.00483 U
	MW-304-20	10/01/19	PES	PACE	20	37.6	S	**0.0364**	0.00108 U	0.0118 U	0.00133 U	**0.00579 J**	**0.0333**	0.00224 U	**0.00166**	0.00124 U	0.00133 U	0.00704 U	0.00436 U	0.00478 U
	MW-304-25	10/01/19	PES	PACE	25	32.6	S	**0.0254 J**	0.00101 U	0.0109 U	0.00124 U	0.00255 U	0.0150 U	0.00208 U	0.000438 U	0.00115 U	0.00124 U	0.00654 U	0.00405 U	0.00444 U
	MW-304-30	10/01/19	PES	PACE	30	27.6	S	**0.0222 J**	0.00108 U	0.0118 U	0.00133 U	0.00274 U	0.0161 U	0.00223 U	0.000470 U	0.00124 U	0.00133 U	0.00703 U	0.00435 U	0.00478 U
	MW-304-40	10/01/19	PES	PACE	40	17.6	S	**0.0220 J**	0.000998 U	0.0109 U	0.00123 U	0.00253 U	0.0149 U	0.00206 U	0.000434 U	0.00114 U	0.00123 U	0.00649 U	0.00402 U	0.00441 U
	MW-304-45	10/01/19	PES	PACE	45	12.6	S	**0.0207 J**	0.000935 U	0.0102 U	0.00115 U	0.00237 U	0.0139 U	0.00193 U	0.000406 U	0.00107 U	0.00115 U	0.00607 U	0.00376 U	0.00412 U
	MW-304-50	10/01/19	PES	PACE	50	7.6	S	**0.0173 J**	0.000991 U	0.0108 U	0.00122 U	0.00251 U	0.0147 U	0.00205 U	0.000431 U	0.00113 U	0.00122 U	0.00644 U	0.00398 U	0.00437 U
	MW-304-55	10/01/19	PES	PACE	55	2.6	S	**0.0163 J**	0.000927 U	0.0101 U	0.00114 U	0.00235 U	0.0138 U	0.00192 U	0.000403 U	0.00106 U	0.00114 U	0.00603 U	0.00373 U	0.00409 U
	MW-304-60	10/01/19	PES	PACE	60	-2.4	S	**0.0183 J**	0.000970 U	0.0105 U	0.00119 U	0.00246 U	0.0144 U	0.00200 U	**0.000423 J**	0.00111 U	0.00119 U	0.00631 U	0.00390 U	0.00428 U
	MW-304-65	10/01/19	PES	PACE	65	-7.4	S	**0.0199 J**	0.00107 U	0.0116 U	0.00131 U	0.00270 U	0.0159 U	0.00220 U	0.000463 U	0.00122 U	0.00131 U	0.00693 U	0.00429 U	0.00470 U
	MW-304-70	10/01/19	PES	PACE	70	-12.4	S	**0.0198 J**	0.00112 U	0.0121 U	0.00137 U	0.00283 U	0.0166 U	0.00231 U	0.000486 U	0.00128 U	0.00137 U	0.00726 U	0.00449 U	0.00493 U
	MW-304-75	10/01/19	PES	PACE	75	-17.4	S	**0.0396**	0.00105 U	0.0114 U	0.00129 U	0.00267 U	0.0157 U	0.00218 U	0.000458 U	0.00120 U	0.00129 U	0.00685 U	0.00424 U	0.00465 U
	MW-304-80	10/01/19	PES	PACE	80	-22.4	S	**0.0204 J**	0.00101 U	0.0109 U	0.00124 U	0.00255 U	0.0150 U	0.00208 U	0.000438 U	0.00115 U	0.00124 U	0.00655 U	0.00405 U	0.00444 U
	MW-304-85	10/01/19	PES	PACE	85	-27.4	S	**0.0196 J**	0.00101 U	0.0110 U	0.00124 U	0.00255 U	0.0150 U	0.00208 U	0.000438 U	0.00115 U	0.00124 U	0.00655 U	0.00405 U	0.00445 U
	MW-304-90	10/01/19	PES	PACE	90	-32.4	S	**0.0287 J**	0.00110 U	0.0120 U	0.00135 U	0.00279 U	0.0164 U	0.00228 U	0.000480 U	0.00126 U	0.00135 U	0.00717 U	0.00444 U	0.00487 U
	MW-304-95	10/01/19	PES	PACE	95	-37.4	S	0.0148 U	0.00109 U	0.0118 U	0.00134 U	0.00276 U	0.0162 UJ	0.00225 U	0.000474 U	0.00124 U	0.00134 U	0.00709 U	0.00438 U	0.00481 U
	MW-2009-95	10/01/19	PES	PACE	95 (dup)	-37.4	S	0.0150 U	0.00111 U	0.0120 U	0.00136 U	0.00280 U	0.0165 UJ	0.00228 U	0.000481 U	0.00126 U	0.00136 U	0.00718 U	0.00444 U	0.00488 U
	MW-304-100	10/02/19	PES	PACE	100	-42.4	S	0.0147 U	0.00108 U	0.0118 U	0.00133 U	0.00275 U	0.0161 UJ	0.00224 U	0.000471 U	0.00124 U	0.00133 U	0.00705 U	0.00436 U	0.00479 U
	MW-304-105	10/02/19	PES	PACE	105	-47.4	S	0.0146 U	0.00108 U	0.0117 U	0.00132 U	0.00273 U	0.0160 UJ	0.00222 U	0.000468 U	0.00123 U	0.00132 U	0.00700 U	0.00433 U	0.00475 U
	MW-304-110	10/02/19	PES	PACE	110	-52.4	S	**0.0327**	0.00116 U	0.0126 U	0.00143 U	0.00295 U	0.0173 U	0.00240 U	0.000506 U	0.00133 U	0.00143 U	0.00756 U	0.00468 U	0.00513 U
	MW-304-115	10/02/19	PES	PACE	115	-57.4	S	0.0146 U	0.00107 U	0.0117 U	0.00132 U	0.00271 U	0.0160 UJ	0.00221 U	0.000466 U	0.00122 U	0.00132 U	0.00697 U	0.00431 U	0.00473 U
MW-307 (-12.4 to -22.4)	MW-307-6	10/03/19	PES	PACE	6	54.5	V	**0.0171 J**	0.00103 U	0.0112 U	0.00126 U	0.00260 U	0.0153 U	0.00212 U	0.000447 U	0.00117 U	0.00126 U	0.00669 U	0.00414 U	0.00454 U
	MW-307-10	10/03/19	PES	PACE	10	50.5	V	**0.0262 J**	0.00106 U	0.0115 U	0.00130 U	0.00268 U	**0.0253 J**	0.00218 U	**0.000462 J**	0.00121 U	0.00130 U	0.00689 U	0.00426 U	0.00467 U
	MW-307-15	10/03/19	PES	PACE	15	45.5	V	0.0135 U	0.000991 U	0.0108 U	0.00122 U	0.00251 U	0.0148 U	0.00205 U	0.000431 U	0.00113 U	0.00122 U	0.00644 U	0.00399 U	0.00437 U
	MW-307-20	10/03/19	PES	PACE	20	40.5	V	**0.0139 J**	0.000984 U	0.0107 U	0.00121 U	0.00249 U	0.0146 U	0.00203 U	0.000428 U	0.00112 U	0.00121 U	0.00639 U	0.00396 U	0.00434 U
	MW-307-25	10/03/19	PES	PACE	25	35.5	S	0.0137 U	0.00101 U	0.0110 U	0.00124 U	0.00256 U	0.0150 U	0.00208 U	0.000439 U	0.00115 U	0.00124 U	0.00656 U	0.00406 U	0.00445 U
	MW-307-30	10/03/19	PES	PACE	30	30.5	S	0.0184 U	0.00135 U	0.0147 U	0.00166 U	0.00344 U	0.0202 U	0.00280 U	0.000589 U	0.00155 U	0.00166 U	0.00881 U	0.00545 U	0.00598 U
	MW-307-35	10/03/19	PES	PACE	35	25.5	S	**0.0154 J**	0.000984 U	0.0107 U	0.00121 U	0.00249 U	0.0147 U	0.00203 U	0.000428 U	0.00112 U	0.00121 U	0.00640 U	0.00396 U	0.00434 U
	MW-307-40	10/03/19	PES	PACE	40	20.5	S	0.0143 U	0.00105 U	0.0114 U	0.00129 U	0.00266 U	**0.0164 J**	0.00217 U	0.000457 U	0.00120 U	0.00129 U	0.00683 U	0.00422 U	0.00464 U
	MW-307-45	10/03/19	PES	PACE	45	15.5	S	**0.0160 J**	0.00101 U	0.0110 U	0.00125 U	0.00257 U	0.0151 U	0.00210 U	0.000441 U	0.00116 U	0.00125 U	0.00660 U	0.00408 U	0.00448 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
MW-307 (continued)	MW-307-50	10/03/19	PES	PACE	50	10.5	S	**0.0181 J**	0.00102 U	0.0111 U	0.00126 U	0.00259 U	0.0152 U	0.00211 U	0.000445 U	0.00117 U	0.00126 U	0.00665 U	0.00411 U	0.00451 U
	MW-307-55	10/03/19	PES	PACE	55	5.5	S	**0.0201 J**	0.000999 U	0.0109 U	0.00123 U	0.00253 U	0.0149 U	0.00206 U	0.000434 U	0.00114 U	0.00123 U	0.00649 U	0.00402 U	0.00441 U
	MW-307-60	10/03/19	PES	PACE	60	0.5	S	0.0141 U	0.00104 U	0.0113 U	0.00128 U	0.00263 U	0.0209 U	0.00215 U	0.000452 U	0.00119 U	0.00128 U	0.00675 U	0.00418 U	0.00458 U
	MW-307-65	10/03/19	PES	PACE	65	-4.5	S	0.0288 U	0.00212 U	0.0230 U	0.00260 U	0.00537 U	**0.0867 J**	0.00438 U	0.000921 U	0.00242 U	0.00260 U	0.0138 U	0.00852 U	0.00935 U
	MW-307-70	10/03/19	PES	PACE	70	-9.5	S	0.143 U	0.0105 U	0.115 U	0.0130 U	0.0267 U	0.242 U	0.0218 U	0.00458 U	0.0120 U	0.0130 U	0.0685 U	0.0424 U	0.0465 U
	MW-307-75	10/03/19	PES	PACE	75	-14.5	S	**0.0174 J**	0.00101 U	0.0110 U	0.00125 U	0.00257 U	**0.0351 J**	0.00210 U	0.000441 U	0.00116 U	0.00125 U	0.00659 U	0.00408 U	0.00448 U
	MW-307-80	10/03/19	PES	PACE	80	-19.5	S	**0.0201 J**	0.00108 U	0.0117 U	0.00132 U	0.00272 U	**0.0731 J**	0.00222 U	0.000467 U	0.00123 U	0.00132 U	0.00699 U	0.00432 U	0.00474 U
	MW-307-85	10/03/19	PES	PACE	85	-24.5	S	**0.0314**	0.00105 U	0.0115 U	0.00129 U	0.00267 U	**0.0667 J**	0.00218 U	**0.000836 J**	0.00120 U	0.00129 U	0.00685 U	0.00424 U	**0.00864 J**
	MW-2016-85	10/03/19	PES	PACE	85 (dup)	-24.5	S	**0.0274**	0.000994 U	0.0108 U	0.00122 U	0.00252 U	**0.0650 J**	0.00205 U	**0.000722 J**	0.00113 U	0.00122 U	0.00646 U	0.00400 U	0.00439 U
MW-309 (-32.0 to -42.0)	MW-309-5	09/19/19	PES	PACE	5	25.4	V	0.0149 U	0.00110 U	0.0119 U	0.00135 U	**0.0120**	**0.149**	0.00227 U	**0.00514**	0.00125 U	0.00135 U	0.00714 U	0.00441 U	0.00484 U
	MW-309-10	09/19/19	PES	PACE	10	20.4	S	0.787 U	0.0579 U	0.629 U	0.0711 U	0.147 U	**2.72**	0.120 U	**0.117**	0.0661 U	0.0711 U	0.376 U	0.233 U	0.255 U
	MW-309-13.5	09/19/19	PES	PACE	13.5	16.9	S	0.0153 U	0.00112 U	0.0122 U	0.00138 U	0.00285 U	0.0645 U	0.00232 U	**0.00485**	0.00128 U	0.00138 U	0.00730 U	0.00452 U	0.00496 U
	MW-309-15	09/19/19	PES	PACE	15	15.4	S	0.118 U	0.00866 U	0.0942 U	0.0106 U	0.0219 U	**0.591**	0.0179 U	**0.0766**	0.00989 U	0.0106 U	0.0563 U	0.0348 U	0.0383 U
	MW-309-20	09/19/19	PES	PACE	20	10.4	S	0.0147 U	0.00108 U	0.0118 U	0.00133 U	**0.00409 J**	**0.242**	0.00224 U	**0.150**	0.00124 U	0.00133 U	0.00704 U	0.00435 U	0.00478 U
	MW-309-25	09/19/19	PES	PACE	25	5.4	S	0.0148 U	0.00109 U	0.0118 U	0.00134 U	**0.00444 J**	**0.0961**	0.00224 U	**0.0796**	0.00124 U	0.00134 U	0.00707 U	0.00437 U	0.00480 U
	MW-309-30	09/19/19	PES	PACE	30	0.4	S	0.0149 U	0.00110 U	0.0119 U	0.00135 U	0.00278 U	**0.0899**	0.00227 U	**0.00545**	0.00125 U	0.00135 U	0.00714 U	0.00442 U	0.00485 U
	MW-309-35	09/19/19	PES	PACE	35	-4.6	S	0.0152 U	0.00112 U	0.0121 U	0.00137 U	0.00282 U	0.0166 U	0.00230 U	**0.0286**	0.00127 U	0.00137 U	0.00725 U	0.00449 U	0.00492 U
	MW-309-40	09/19/19	PES	PACE	40	-9.6	S	0.0152 U	0.00112 U	0.0121 U	0.00137 U	0.00283 U	0.0415 U	0.00230 U	**0.0387**	0.00127 U	0.00137 U	0.00725 U	0.00449 U	0.00492 U
	MW-309-45	09/19/19	PES	PACE	45	-14.6	S	0.0158 U	0.00116 U	0.0126 U	0.00143 U	0.00294 U	0.0472 U	0.00240 U	**0.00557**	0.00132 U	0.00143 U	0.00754 U	0.00467 U	0.00512 U
	MW-309-50	09/19/19	PES	PACE	50	-19.6	S	0.0149 U	0.00110 U	0.0119 U	0.00135 U	0.00278 U	0.0229 U	0.00226 U	0.000477 U	0.00125 U	0.00135 U	0.00713 U	0.00441 U	0.00484 U
	MW-309-55	09/19/19	PES	PACE	55	-24.6	S	0.0139 U	0.00102 U	0.0111 U	0.00125 U	0.00259 U	0.0295 U	0.00211 U	0.000444 U	0.00117 U	0.00125 U	0.00664 U	0.00411 U	0.00451 U
	MW-309-60	09/19/19	PES	PACE	60	-29.6	S	0.0140 U	0.00103 U	0.0112 U	0.00127 U	0.00260 U	0.0399 U	0.00213 U	0.000447 U	0.00117 U	0.00127 U	0.00668 U	0.00414 U	0.00453 U
	MW-309-65	09/19/19	PES	PACE	65	-34.6	S	0.0140 U	0.00103 U	0.0112 U	0.00127 U	0.00262 U	0.0571 U	0.00213 U	0.000449 U	0.00118 U	0.00127 U	0.00672 U	0.00416 U	0.00456 U
	MW-309-70	09/19/19	PES	PACE	70	-39.6	S	0.0142 U	0.00105 U	0.0114 U	0.00128 U	0.00265 U	0.0391 U	0.00216 U	0.000455 U	0.00119 U	0.00128 U	0.00680 U	0.00421 U	0.00462 U
	MW-309-75	09/19/19	PES	PACE	75	-44.6	S	0.0135 U	0.000994 U	0.0108 U	0.00122 U	0.00252 U	0.0493 U	0.00205 U	0.000432 U	0.00113 U	0.00122 U	0.00646 U	0.00400 U	0.00439 U
MW-311 (-29.0 to -39.0)	MW-311-5	09/18/19	PES	PACE	5	28.1	V	0.0150 U	0.00110 U	0.0120 U	0.00135 U	0.00279 U	**0.0791**	0.00227 UJ	**0.000644 J**	0.00126 U	0.00135 U	0.00716 U	0.00443 U	0.00486 U
	MW-311-10	09/18/19	PES	PACE	10	23.1	S	0.0144 U	0.00106 U	0.0115 U	0.00130 U	0.00268 U	**0.0194 J**	0.00219 UJ	0.000460 U	0.00121 U	0.00130 U	0.00688 U	0.00426 U	0.00467 U
	MW-311-15	09/18/19	PES	PACE	15	18.1	S	0.0335 U	0.00247 U	0.0268 U	0.00303 U	0.00625 U	**0.0509 J**	0.00510 UJ	0.00107 U	0.00282 U	0.00303 U	0.0161 U	0.00993 U	0.0109 U
	MW-311-20	09/18/19	PES	PACE	20	13.1	S	0.0351 U	0.00258 U	0.0280 U	0.00317 U	**0.00774 J**	**0.0986**	0.00531 UJ	0.00112 U	0.00293 U	0.00317 U	0.0167 U	0.0104 U	0.0114 U
	MW-311-25	09/18/19	PES	PACE	25	8.1	S	0.0621 U	0.00457 U	0.0497 U	0.00561 U	0.0116 U	**0.138**	0.00944 UJ	0.00199 U	0.00522 U	0.00561 U	0.0297 U	0.0184 U	0.0201 U
	MW-311-30	09/18/19	PES	PACE	30	3.1	S	0.0328 U	0.00242 U	0.0263 U	0.00296 U	0.00612 U	0.0360 U	0.00498 UJ	0.00105 U	0.00275 U	0.00296 U	0.0157 U	0.00972 U	0.0107 U
	MW-311-35	09/18/19	PES	PACE	35	-1.9	S	0.0292 U	0.00215 U	0.0233 U	0.00264 U	0.00544 U	**0.0793**	0.00443 UJ	0.000933 U	0.00245 U	0.00264 U	0.0140 U	0.00863 U	0.00947 U
	MW-311-40	09/18/19	PES	PACE	40	-6.9	S	0.0146 U	0.00108 U	0.0117 U	0.00132 U	0.00273 U	**0.0604**	0.00223 UJ	**0.000752 J**	0.00123 U	0.00132 U	0.00701 U	0.00434 U	0.00476 U
	MW-311-45	09/18/19	PES	PACE	45	-11.9	S	0.0157 U	0.00115 U	0.0126 U	0.00142 U	0.00292 U	**0.0437**	0.00238 UJ	0.000502 U	0.00132 U	0.00142 U	0.00751 U	0.00464 U	0.00510 U
	MW-311-50	09/18/19	PES	PACE	50	-16.9	S	0.0146 U	0.00107 U	0.0117 U	0.00132 U	0.00272 U	**0.0416**	0.00222 UJ	**0.000485 J**	0.00123 U	0.00132 U	0.00698 U	0.00432 U	0.00474 U
	MW-311-55	09/18/19	PES	PACE	55	-21.9	S	0.0138 U	0.00102 U	0.0111 U	0.00125 U	0.00258 U	**0.0466**	0.00210 UJ	**0.000690 J**	0.00116 U	0.00125 U	0.00661 U	0.00409 U	0.00449 U
	MW-311-60	09/18/19	PES	PACE	60	-26.9	S	0.0274 U	0.00202 U	0.0219 U	0.00248 U	0.00511 U	**0.0887**	0.00416 UJ	0.000877 U	0.00230 U	0.00248 U	0.0131 U	0.00811 U	0.00890 U
	MW-311-65	09/18/19	PES	PACE	65	-31.9	S	0.0132 U	0.000975 U	0.0106 U	0.00120 U	0.00247 U	**0.0265**	0.00201 UJ	0.000424 U	0.00111 U	0.00120 U	0.00634 U	0.00392 U	0.00430 U
	MW-2005-65	09/18/19	PES	PACE	65 (dup)	-31.9	S	**0.0153 J**	0.00101 U	0.0110 U	0.00124 U	0.00256 U	**0.0422**	0.00208 U	**0.000507 J**	0.00115 U	0.00124 U	0.00656 U	0.00406 U	0.00445 U
	MW-311-70	09/18/19	PES	PACE	70	-36.9	S	0.0138 U	0.00101 U	0.0110 U	0.00125 U	0.00257 U	**0.0230 J**	0.00209 UJ	0.000441 U	0.00116 U	0.00125 U	0.00659 U	0.00408 U	0.00447 U
	MW-2007-70	09/18/19	PES	PACE	70 (dup)	-38.3	S	0.0266 U	0.00196 U	0.0213 U	0.00241 U	0.00496 U	**0.0828**	0.00405 U	**0.00100 J**	0.00224 U	0.00241 U	0.0128 U	0.00788 U	0.00865 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
MW-312	MW-312-6	09/16/19	PES	PACE	6	29.6	V	0.0152 U	0.00112 U	0.0122 UJ	0.00137 U	0.00283 U	**0.0391**	0.00231 UJ	**0.000742 J**	0.00128 U	0.00137 U	0.00728 U	0.00450 U	0.00494 U
(19.9 to9.9)	MW-312-10	09/16/19	PES	PACE	10	25.6	V	**0.0306 J**	0.00187 U	0.0203 UJ	0.00230 U	0.00474 U	**0.187**	0.00386 UJ	**0.00135 J**	0.00214 U	0.00230 U	0.0121 U	0.00751 U	0.00824 U
	MW-312-15	09/16/19	PES	PACE	15	20.6	S	0.0173 U	0.00127 U	0.0138 UJ	0.00157 U	**0.00449 J**	**0.0511**	0.00263 UJ	**0.00168**	0.00145 U	0.00157 U	0.00827 U	0.00512 U	0.00561 U
	MW-312-20	09/16/19	PES	PACE	20	15.6	S	0.0135 U	0.000995 U	0.0108 UJ	0.00122 U	0.00252 U	**0.0328**	0.00206 UJ	0.000433 U	0.00114 U	0.00122 U	0.00647 U	0.00400 U	0.00439 U
	MW-2004-20	09/16/19	PES	PACE	20	15.6	S	**0.0168 J**	0.00106 U	0.0115 UJ	0.00130 U	0.00269 U	**0.0620**	0.00219 UJ	0.000462 U	0.00121 U	0.00130 U	0.00690 U	0.00427 U	0.00469 U
	MW-312-25	09/16/19	PES	PACE	25	10.6	S	**0.0263 J**	0.00103 U	0.0112 UJ	0.00126 U	0.00261 U	**0.0944**	0.00213 UJ	**0.00102 J**	0.00117 U	0.00126 U	0.00669 U	0.00414 U	0.00454 U
MW-314	MW-314-6	09/13/19	PES	PACE	6	33.8	V	**0.0191 J**	0.00105 U	0.0114 U	0.00128 U	0.00265 U	**0.0664**	0.00216 U	**0.000909 J**	0.00119 U	0.00128 U	0.00679 U	0.00420 U	0.00461 U
(-28.0 to -38.0)	MW-314-10	09/13/19	PES	PACE	10	29.8	V	**0.0286 J**	0.00106 U	0.0115 U	0.00130 U	0.00267 U	**0.0406**	0.00218 U	0.000459 U	0.00120 U	0.00130 U	0.00686 U	0.00424 U	0.00465 U
	MW-314-15	09/13/19	PES	PACE	15	24.8	V	**0.0245 J**	0.00104 U	0.0113 U	0.00127 U	0.00262 U	**0.0326**	0.00214 U	0.000450 U	0.00118 U	0.00127 U	0.00673 U	0.00416 U	0.00457 U
	MW-314-20	09/13/19	PES	PACE	20	19.8	S	**0.0267 J**	0.00106 U	0.0115 U	0.00130 U	0.00267 U	**0.0362**	0.00218 U	**0.000940 J**	0.00120 U	0.00130 U	0.00686 U	0.00425 U	0.00466 U
	MW-314-25	09/13/19	PES	PACE	25	14.8	S	**0.0257 J**	0.00117 U	0.0127 U	0.00143 U	0.00296 U	**0.0284 J**	0.00241 U	0.000508 U	0.00133 U	0.00143 U	0.00759 U	0.00470 U	0.00516 U
	MW-2002-25	09/13/19	PES	PACE	25	14.8	S	0.0158 UJ	0.00116 U	0.0126 U	0.00143 U	0.00294 U	**0.0406**	0.00240 UJ	0.000505 U	0.00133 U	0.00143 U	0.00755 U	0.00467 U	0.00513 UJ
	MW-314-30	09/13/19	PES	PACE	30	9.8	S	**0.0244 J**	0.00114 U	0.0124 U	0.00141 U	0.00290 U	**0.0320**	0.00236 U	0.000498 U	0.00131 U	0.00141 U	0.00744 U	0.00460 U	0.00505 U
	MW-314-35	09/13/19	PES	PACE	35	4.8	S	**0.0203 J**	0.000987 U	0.0107 U	0.00121 U	0.00250 U	**0.0380**	0.00204 U	0.000429 U	0.00113 U	0.00121 U	0.00641 U	0.00397 U	0.00436 U
	MW-314-40	09/13/19	PES	PACE	40	-0.2	S	**0.0311**	0.00103 U	0.0111 U	0.00126 U	0.00259 U	**0.0401**	0.00212 U	0.000446 U	0.00117 U	0.00126 U	0.00667 U	0.00413 U	0.00453 U
	MW-314-45	09/13/19	PES	PACE	45	-5.2	S	**0.0187 J**	0.00102 U	0.0111 U	0.00125 U	0.00258 U	**0.0406**	0.00210 U	**0.000799 J**	0.00116 U	0.00125 U	0.00662 U	0.00410 U	0.00449 U
	MW-314-50	09/13/19	PES	PACE	50	-10.2	S	**0.0173 J**	0.00102 U	0.0111 U	0.00126 U	0.00259 U	**0.0353**	0.00212 U	0.000445 U	0.00117 U	0.00126 U	0.00666 U	0.00412 U	0.00452 U
	MW-314-55	09/13/19	PES	PACE	55	-15.2	S	**0.0189 J**	0.00111 U	0.0121 U	0.00136 U	0.00281 U	**0.0283 J**	0.00229 U	0.000483 U	0.00127 U	0.00136 U	0.00722 U	0.00447 U	0.00490 U
	MW-314-60	09/13/19	PES	PACE	60	-20.2	S	**0.0205 J**	0.00102 U	0.0111 U	0.00125 U	0.00258 U	**0.0305**	0.00210 U	0.000442 U	0.00116 U	0.00125 U	0.00661 U	0.00409 U	0.00449 U
	MW-314-65	09/13/19	PES	PACE	65	-25.2	S	**0.0149 J**	0.00104 U	0.0114 U	0.00128 U	0.00265 U	**0.0316**	0.00216 UJ	0.000454 U	0.00119 U	0.00128 U	0.00679 U	0.00420 U	0.00461 UJ
	MW-314-70	09/13/19	PES	PACE	70	-30.2	S	0.152 U	0.0112 U	0.122 UJ	0.0137 U	0.0284 U	**0.253 J**	0.0231 UJ	0.00486 U	0.0127 U	0.0137 U	0.0727 U	0.0449 U	0.0494 U
	MW-314-75	09/13/19	PES	PACE	75	-35.2	S	0.0285 UJ	0.00210 U	0.0228 U	0.00258 U	0.00532 U	**0.0484 J**	0.00434 UJ	0.000913 U	0.00240 U	0.00258 U	0.0137 U	0.00845 U	0.00927 UJ
	MW-314-80	09/13/19	PES	PACE	80	-40.2	S	0.0187 UJ	0.00137 U	0.0149 U	0.00168 U	0.00348 U	**0.0667**	0.00284 UJ	0.000597 U	0.00157 U	0.00168 U	0.00893 U	0.00552 U	0.00607 UJ
MW-316	MW-316-5	09/09/19	PES	PACE	5	44.8	V	0.0135 U	0.000996 U	0.0108 U	0.00122 U	0.00252 U	0.0267 U	0.00206 U	0.000433 U	0.00114 U	0.00122 U	0.00647 U	0.00401 U	0.00440 U
(-10.0 to -20.0)	MW-316-10	09/09/19	PES	PACE	10	39.8	V	0.0141 U	0.00104 U	0.0113 U	0.00128 U	0.00264 U	**0.0346**	0.00215 U	0.000453 U	0.00119 U	0.00128 U	0.00677 U	0.00419 U	0.00459 U
	MW-316-15	09/09/19	PES	PACE	15	34.8	V	0.0141 U	0.00103 U	0.0112 U	0.00127 U	0.00262 U	0.0171 U	0.00214 U	0.000450 U	0.00118 U	0.00127 U	0.00672 U	0.00416 U	0.00457 U
	MW-316-20	09/09/19	PES	PACE	20	29.8	V	0.0135 U	0.000992 U	0.0108 U	0.00122 U	0.00251 U	**0.0282**	0.00205 U	0.000431 U	0.00113 U	0.00122 U	0.00645 U	0.00399 U	0.00438 U
	MW-316-25	09/09/19	PES	PACE	25	24.8	S	0.0142 U	0.00104 U	0.0113 U	0.00128 U	0.00264 U	**0.0400**	0.00216 U	0.000454 U	0.00119 U	0.00128 U	0.00678 U	0.00420 U	0.00461 U
	MW-316-30	09/09/19	PES	PACE	30	19.8	S	0.0139 U	0.00102 U	0.0111 U	0.00125 U	0.00259 U	**0.0301**	0.00211 U	0.000444 U	0.00117 U	0.00125 U	0.00664 U	0.00411 U	0.00450 U
	MW-316-35	09/09/19	PES	PACE	35	14.8	S	0.0141 U	0.00104 U	0.0113 U	0.00128 U	0.00263 U	0.0212 U	0.00214 U	0.000452 U	0.00119 U	0.00128 U	0.00675 U	0.00418 U	0.00458 U
	MW-316-40	09/09/19	PES	PACE	40	9.8	S	0.0142 U	0.00105 U	0.0114 U	0.00129 U	0.00265 U	0.0202 U	0.00216 U	0.000455 U	0.00119 U	0.00129 U	0.00681 U	0.00421 U	0.00462 U
	MW-316-45	09/09/19	PES	PACE	45	4.8	S	0.0139 U	0.00102 U	0.0111 U	0.00126 U	0.00259 U	0.0246 U	0.00211 U	0.000445 U	0.00117 U	0.00126 U	0.00665 U	0.00411 U	0.00451 U
	MW-316-50	09/09/19	PES	PACE	50	-0.2	S	0.0150 U	0.00110 U	0.0120 U	0.00135 U	0.00279 U	0.0273 U	0.00227 U	0.000479 U	0.00126 U	0.00135 U	0.00716 U	0.00443 U	0.00486 U
	MW-316-55	09/09/19	PES	PACE	55	-5.2	S	0.0142 U	0.00104 U	0.0113 U	0.00128 U	0.00264 U	0.0174 U	0.00215 U	0.000453 U	0.00119 U	0.00128 U	0.00677 U	0.00419 U	0.00460 U
	MW-316-60	09/09/19	PES	PACE	60	-10.2	S	0.0141 U	0.00103 U	0.0112 U	0.00127 U	0.00262 U	0.0250 U	0.00214 U	0.000450 U	0.00118 U	0.00127 U	0.00672 U	0.00416 U	0.00456 U
	MW-316-65	09/10/19	PES	PACE	65	-15.2	S	0.0187 U	0.00137 U	0.0150 U	0.00169 U	0.00349 U	0.0243 U	0.00285 U	0.000599 U	0.00158 U	0.00169 U	0.00895 U	0.00553 U	0.00608 U
	MW-2001-65	09/10/19	PES	PACE	65	-15.2	S	0.0148 U	0.00109 U	0.0118 U	0.00134 U	0.00276 U	**0.0474**	0.00225 U	0.000474 U	0.00124 U	0.00134 U	0.00708 U	0.00438 U	0.00481 U
	MW-316-70	09/10/19	PES	PACE	70	-20.2	S	0.0141 U	0.00104 U	0.0113 U	0.00128 U	0.00264 U	**0.0392**	0.00215 U	0.000453 U	0.00119 U	0.00128 U	0.00677 U	0.00419 U	0.00459 U
MW-319	MW-319-6	09/18/19	PES	PACE	6	25.7	V	0.0145 U	0.00107 U	0.0116 U	0.00131 U	0.00270 U	**0.105**	0.00220 UJ	**0.000468 J**	0.00122 U	0.00131 U	0.00694 U	0.00429 U	0.00471 U
(-42.8 to -52.8)	MW-319-10	09/18/19	PES	PACE	10	21.7	S	0.0144 U	0.00106 U	0.0115 U	0.00130 U	0.00269 U	**0.0480**	0.00219 UJ	0.000461 U	0.00121 U	0.00130 U	0.00689 U	0.00427 U	0.00468 U
	MW-319-15	09/18/19	PES	PACE	15	16.7	S	0.0143 U	0.00105 U	0.0115 U	0.00129 U	0.00267 U	**0.0449**	0.00218 UJ	0.000458 U	0.00120 U	0.00129 U	0.00685 U	0.00424 U	0.00465 U
	MW-319-20	09/18/19	PES	PACE	20	11.7	S	0.0155 U	0.00114 U	0.0124 U	0.00140 U	0.00289 U	0.0170 U	0.00235 UJ	0.000495 U	0.00130 U	0.00140 U	0.00741 U	0.00458 U	0.00503 U
	MW-319-30	09/18/19	PES	PACE	30	1.7	S	0.0143 U	0.00105 U	0.0114 U	0.00129 U	0.00266 U	**0.0418**	0.00217 UJ	0.000457 U	0.00120 U	0.00129 U	0.00683 U	0.00423 U	0.00464 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
MW-319 (continued)	MW-319-35	09/18/19	PES	PACE	35	-3.3	S	0.0158 U	0.00116 U	0.0126 U	0.00142 U	0.00294 U	**0.0739**	0.00240 UJ	**0.00112 J**	0.00132 U	0.00142 U	0.00754 U	0.00467 U	0.00512 U
	MW-319-40	09/18/19	PES	PACE	40	-8.3	S	0.0148 U	0.00109 U	0.0118 U	0.00133 U	0.00275 U	**0.0429**	0.00224 UJ	0.000472 U	0.00124 U	0.00133 U	0.00706 U	0.00437 U	0.00479 U
	MW-319-45	09/18/19	PES	PACE	45	-13.3	S	0.0148 U	0.00109 U	0.0119 U	0.00134 U	0.00277 U	**0.0414**	0.00226 UJ	0.000475 U	0.00125 U	0.00134 U	0.00710 U	0.00439 U	0.00482 U
	MW-319-50	09/18/19	PES	PACE	50	-18.3	S	0.0153 U	0.00112 U	0.0122 U	0.00138 U	0.00285 U	**0.0568**	0.00232 UJ	**0.0772**	0.00128 U	0.00138 U	0.00730 U	0.00452 U	0.00496 U
	MW-319-55	09/18/19	PES	PACE	55	-23.3	S	0.0158 U	0.00116 U	0.0126 U	0.00143 U	0.00294 U	0.0173 U	0.00240 UJ	**0.0431**	0.00133 U	0.00143 U	0.00755 U	0.00467 U	0.00513 U
	MW-319-60	09/18/19	PES	PACE	60	-28.3	S	0.0148 U	0.00109 U	0.0119 U	0.00134 U	0.00277 U	**0.0603**	0.00226 UJ	**0.0132**	0.00125 U	0.00134 U	0.00710 U	0.00439 U	0.00482 U
	MW-319-65	09/18/19	PES	PACE	65	-33.3	S	0.0159 U	0.00117 U	0.0127 U	0.00144 U	0.00297 U	**0.0593**	0.00242 UJ	**0.00411**	0.00134 U	0.00144 U	0.00762 U	0.00472 U	0.00518 U
	MW-319-70	09/18/19	PES	PACE	70	-38.3	S	0.0152 U	0.00112 U	0.0122 U	0.00138 U	0.00284 U	0.0167 U	0.00232 UJ	0.000487 U	0.00128 U	0.00138 U	0.00729 U	0.00451 U	0.00495 U
	MW-2006-70	09/18/19	PES	PACE	70 (dup)	-36.9	S	0.0157 U	0.00115 U	0.0125 U	0.00142 U	0.00292 U	**0.0439**	0.00238 UJ	0.000501 U	0.00132 U	0.00142 U	0.00749 U	0.00464 U	0.00509 U
	MW-319-75	09/18/19	PES	PACE	75	-43.3	S	0.0138 U	0.00102 U	0.0111 U	0.00125 U	0.00258 U	**0.0499**	0.00210 UJ	**0.000448 J**	0.00116 U	0.00125 U	0.00662 U	0.00410 U	0.00450 U
	MW-319-80	09/18/19	PES	PACE	80	-48.3	S	0.0152 U	0.00112 U	0.0122 U	0.00137 U	0.00283 U	**0.0428**	0.00231 UJ	0.000486 U	0.00128 U	0.00137 U	0.00727 U	0.00450 U	0.00494 U
	MW-319-85	09/18/19	PES	PACE	85	-53.3	S	0.0150 U	0.00111 U	0.0120 U	0.00136 U	0.00280 U	**0.0306**	0.00229 UJ	0.000481 U	0.00126 U	0.00136 U	0.00719 U	0.00445 U	0.00488 U
MW-320 (18.6 to 8.6)	MW-320-19	09/29/19	PES	PACE	19	15.1	S	0.279 U	0.0206 U	0.223 U	0.0252 U	0.0520 U	**0.427 J**	0.0424 U	0.00894 U	0.0235 U	0.0252 U	0.134 U	0.0827 U	0.0907 U
	MW-320-27	09/29/19	PES	PACE	27	7.1	S	0.0186 U	0.00107 U	0.0116 U	0.00131 U	0.00270 U	0.0159 U	**0.00396 J**	0.000463 U	0.00122 U	0.00131 U	0.00693 U	0.00429 U	0.00470 U
MW-323 (-65.4 to -75.4)	MW-323-10	09/28/19	PES	PACE	10	24.7	V	0.0305 U	0.00224 U	0.0244 U	0.00276 U	0.00568 U	**0.0425 J**	0.00463 U	**0.0151**	0.00256 U	0.00276 U	0.0146 U	0.00902 U	0.00990 U
	MW-2012-10	09/28/19	PES	PACE	10 (dup)	24.7	V	**0.0250 J**	0.00115 U	0.0125 U	0.00141 U	0.00291 U	**0.0237 J**	0.00237 U	0.000500 U	0.00131 U	0.00141 U	0.00748 U	0.00462 U	0.00508 U
	MW-323-15	09/28/19	PES	PACE	15	19.7	S	0.0369 U	0.00211 U	0.0229 U	0.00260 U	0.00534 U	**0.0497 J**	0.00436 U	**0.00140 J**	0.00240 U	0.00260 U	0.0137 U	0.00848 U	0.00930 U
	MW-323-20	09/28/19	PES	PACE	20	14.7	S	0.0141 U	0.00104 U	0.0113 U	0.00128 U	**0.00307 J**	0.0155 U	0.00215 U	**0.00348**	0.00119 U	0.00128 U	0.00675 U	0.00418 U	0.00458 U
	MW-323-25	09/28/19	PES	PACE	25	9.7	S	0.0187 U	0.00105 U	0.0114 U	0.00129 U	0.00266 U	0.0156 U	0.00217 U	0.000456 U	0.00120 U	0.00129 U	0.00682 U	0.00422 U	0.00463 U
	MW-323-30	09/28/19	PES	PACE	30	4.7	S	0.0265 U	0.00195 U	0.0212 U	0.00240 U	0.00495 U	**0.0460 J**	0.00404 U	0.000850 U	0.00223 U	0.00240 U	0.0127 U	0.00786 U	0.00862 U
	MW-323-35	09/28/19	PES	PACE	35	-0.4	S	0.0204 U	0.00118 U	0.0129 U	0.00145 U	0.00299 U	**0.0190 J**	0.00244 U	0.000514 U	0.00135 U	0.00145 U	0.00769 U	0.00476 U	0.00522 U
	MW-323-40	09/28/19	PES	PACE	40	-5.4	S	0.0176 U	0.00118 U	0.0128 U	0.00145 U	0.00299 U	0.0176 U	0.00244 U	0.000514 U	0.00135 U	0.00145 U	0.00768 U	0.00475 U	0.00521 U
	MW-323-45	09/28/19	PES	PACE	45	-10.4	S	0.0179 U	0.00118 U	0.0128 U	0.00145 U	0.00298 U	**0.0209 J**	0.00243 U	0.000512 U	0.00134 U	0.00145 U	0.00765 U	0.00473 U	0.00519 U
	MW-323-50	09/28/19	PES	PACE	50	-15.4	S	0.0208 U	0.00106 U	0.0115 U	0.00130 U	0.00268 U	**0.0295**	0.00219 U	**0.000730 J**	0.00121 U	0.00130 U	0.00688 U	0.00426 U	0.00467 U
	MW-323-55	09/28/19	PES	PACE	55	-20.4	S	0.0205 U	0.00107 U	0.0117 U	0.00132 U	0.00271 U	**0.0273 J**	0.00221 U	**0.00179**	0.00122 U	0.00132 U	0.00697 U	0.00431 U	0.00473 U
	MW-323-60	09/28/19	PES	PACE	60	-25.4	S	0.0282 U	0.00118 U	0.0128 U	0.00145 U	0.00298 U	**0.0619**	0.00244 U	**0.000767 J**	0.00135 U	0.00145 U	0.00767 U	0.00475 U	0.00520 U
	MW-2010-60	09/28/19	PES	PACE	60 (dup)	-25.4	S	0.0233 U	0.00112 U	0.0122 U	0.00138 U	0.00284 U	**0.0362**	0.00232 U	0.000488 U	0.00128 U	0.00138 U	0.00729 U	0.00451 U	0.00495 U
	MW-323-65	09/28/19	PES	PACE	65	-30.4	S	0.0161 U	0.00111 U	0.0120 U	0.00136 U	0.00280 U	0.0165 U	0.00228 U	0.000481 U	0.00126 U	0.00136 U	0.00719 U	0.00445 U	0.00488 U
	MW-323-70	09/28/19	PES	PACE	70	-35.4	S	2.11 U	0.155 U	1.68 U	0.190 U	0.392 U	**3.86 J**	0.320 U	0.0673 U	0.177 U	0.190 U	1.01 U	0.622 U	0.683 U
	MW-323-75	09/28/19	PES	PACE	75	-40.4	S	0.0221 U	0.00108 U	0.0118 U	0.00133 U	0.00274 U	**0.0297**	0.00223 U	0.000470 U	0.00123 U	0.00133 U	0.00703 U	0.00435 U	0.00477 U
	MW-323-80	09/28/19	PES	PACE	80	-45.4	S	0.0191 U	0.00104 U	0.0113 U	0.00128 U	0.00263 U	**0.0164 J**	0.00215 U	0.000452 U	0.00119 U	0.00128 U	0.00676 U	0.00418 U	0.00459 U
	MW-323-85	09/28/19	PES	PACE	85	-50.4	S	0.0196 U	0.00110 U	0.0120 U	0.00135 U	0.00279 U	**0.0234 J**	**0.00457 J**	0.000479 U	0.00126 U	0.00135 U	0.00716 U	0.00443 U	0.00486 U
	MW-323-91	09/28/19	PES	PACE	91	-56.4	S	0.0390 U	0.00260 U	0.0283 U	0.00320 U	0.00661 U	**0.0966**	0.00539 U	0.00113 U	0.00298 U	0.00320 U	0.0170 U	0.0105 U	0.0115 U
	MW-323-95	09/28/19	PES	PACE	95	-60.4	S	0.0215 U	0.00110 U	0.0120 U	0.00135 U	0.00279 U	**0.0212 J**	0.00228 U	0.000480 U	0.00126 U	0.00135 U	0.00717 U	0.00444 U	0.00487 U
	MW-323-99	09/28/19	PES	PACE	99	-64.4	S	0.0215 U	0.00106 U	0.0116 U	0.00131 U	0.00269 U	**0.0198 J**	0.00220 U	0.000462 U	0.00121 U	0.00131 U	0.00691 U	0.00428 U	0.00469 U
	MW-323-105	09/28/19	PES	PACE	105	-70.4	S	0.0224 U	0.00109 U	0.0118 U	0.00133 U	0.00275 U	**0.0201 J**	0.00224 U	0.000472 U	0.00124 U	0.00133 U	0.00706 U	0.00437 U	0.00479 U
	MW-323-110	09/28/19	PES	PACE	110	-75.4	S	0.0307 U	0.00226 U	0.0245 U	0.00277 U	0.00571 U	**0.0602 J**	0.00465 U	0.000980 U	0.00258 U	0.00277 U	0.0146 U	0.00906 U	0.00995 U
MW-324 (-32.1 to -42.1)	MW-324-6	09/12/19	PES	PACE	6	28.3	V	**0.0182 J**	0.00103 U	0.0112 U	0.00127 U	0.00262 U	**0.0221 J**	0.00214 U	0.000450 U	0.00118 U	0.00127 U	0.00673 U	0.00416 U	0.00457 U
	MW-324-10	09/12/19	PES	PACE	10	24.3	V	**0.0242 J**	0.00107 U	0.0116 U	0.00131 U	0.00270 U	**0.0322**	0.00220 U	0.000463 U	0.00122 U	0.00131 U	0.00692 U	0.00428 U	0.00470 U
	MW-324-15	09/12/19	PES	PACE	15	19.3	S	**0.0240 J**	0.00100 U	0.0109 U	0.00123 U	0.00254 U	**0.0335**	0.00207 U	0.000437 U	0.00115 U	0.00123 U	0.00653 U	0.00404 U	0.00443 U
	MW-324-20	09/12/19	PES	PACE	20	14.3	S	**0.0229 J**	0.00107 U	0.0117 U	0.00132 U	0.00272 U	**0.0388**	0.00222 U	**0.00362**	0.00123 U	0.00132 U	0.00698 U	0.00432 U	**0.0117 J**
	MW-324-25	09/12/19	PES	PACE	25	9.3	S	**0.0198 J**	0.00109 U	0.0118 U	0.00133 U	0.00275 U	**0.0328**	0.00224 U	**0.00177**	0.00124 U	0.00133 U	0.00706 U	0.00437 U	0.00479 U
	MW-324-30	09/12/19	PES	PACE	30	4.3	S	**0.0253 J**	0.00113 U	0.0123 U	0.00139 U	0.00287 U	**0.0418**	0.00234 U	0.000492 U	0.00129 U	0.00139 U	0.00735 U	0.00454 U	0.00499 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
MW-324 (continued)	MW-324-35	09/12/19	PES	PACE	35	-0.7	S	**0.0229 J**	0.00110 U	0.0119 U	0.00135 U	0.00278 U	**0.0249 J**	0.00227 U	0.000478 U	0.00125 U	0.00135 U	0.00714 U	0.00442 U	0.00485 U
	MW-324-40	09/12/19	PES	PACE	40	-5.7	S	**0.0232 J**	0.00111 U	0.0121 U	0.00137 U	0.00282 U	**0.0299 J**	0.00230 U	0.000483 U	0.00127 U	0.00137 U	0.00723 U	0.00447 U	0.00491 U
	MW-324-45	09/12/19	PES	PACE	45	-10.7	S	**0.0283 J**	0.00116 U	0.0126 U	0.00142 U	0.00293 U	**0.0383**	0.00239 U	0.000503 U	0.00132 U	0.00142 U	0.00753 U	0.00466 U	0.00511 U
	MW-324-50	09/12/19	PES	PACE	50	-15.7	S	**0.0187 J**	0.000920 U	0.0100 U	0.00113 U	0.00233 U	**0.0237 J**	0.00190 U	0.000400 U	0.00105 U	0.00113 U	0.00598 U	0.00370 U	0.00406 U
	MW-324-55	09/12/19	PES	PACE	55	-20.7	S	**0.0223 J**	0.00104 U	0.0113 U	0.00128 U	0.00264 U	**0.0299**	0.00215 U	**0.0148**	0.00119 U	0.00128 U	0.00678 U	0.00419 U	0.00460 U
	MW-324-60	09/12/19	PES	PACE	60	-25.7	S	**0.0233 J**	0.00104 U	0.0113 U	0.00128 U	0.00264 U	**0.0418**	0.00215 U	**0.00992**	0.00119 U	0.00128 U	0.00678 U	0.00419 U	0.00460 U
	MW-324-65	09/12/19	PES	PACE	65	-30.7	S	**0.0251 J**	0.00108 U	0.0118 U	0.00133 U	0.00274 U	**0.0439**	0.00224 U	**0.00303**	0.00123 U	0.00133 U	0.00703 U	0.00436 U	0.00478 U
	MW-324-70	09/12/19	PES	PACE	70	-35.7	S	**0.0256 J**	0.00114 U	0.0124 U	0.00140 U	0.00289 U	**0.0383**	0.00235 U	**0.00121 J**	0.00130 U	0.00140 U	0.00742 U	0.00459 U	0.00503 U
	MW-324-75	09/12/19	PES	PACE	75	-40.7	S	**0.0230 J**	0.00115 U	0.0125 U	0.00142 U	0.00292 U	**0.0359**	0.00238 U	**0.000555 J**	0.00132 U	0.00142 U	0.00750 U	0.00464 U	0.00509 U
	MW-324-80	09/12/19	PES	PACE	80	-45.7	S	**0.0282 J**	0.00115 U	0.0125 U	0.00141 U	0.00292 U	**0.0508**	0.00238 U	**0.000689 J**	0.00131 U	0.00141 U	0.00748 U	0.00463 U	0.00508 U
MW-326 (-48.7 to -58.7)	MW-326-5	09/09/19	PES	PACE	5	36.3	V	0.0138 U	0.00101 U	0.0110 U	0.00125 U	0.00257 U	**0.0283 J**	0.00209 U	**0.00274**	0.00116 U	0.00125 U	0.00659 U	0.00408 U	0.00447 U
	MW-326-10	09/09/19	PES	PACE	10	31.3	V	**0.0223 J**	0.00122 U	0.0133 U	0.00150 U	0.00310 U	**0.0420 J**	0.00253 U	0.000532 U	0.00140 U	0.00150 U	0.00796 U	0.00493 U	0.00540 U
	MW-326-15	09/09/19	PES	PACE	15	26.3	V	**0.0197 J**	0.00108 U	0.0117 U	0.00132 U	0.00272 U	**0.0298 J**	0.00222 U	0.000468 U	0.00123 U	0.00132 U	0.00699 U	0.00433 U	0.00475 U
	MW-326-20	09/09/19	PES	PACE	20	21.3	S	0.0146 U	0.00108 U	0.0117 U	0.00132 U	0.00273 U	0.0215 U	0.00222 U	0.000468 U	0.00123 U	0.00132 U	0.00700 U	0.00433 U	0.00475 U
	MW-326-25	09/09/19	PES	PACE	25	16.3	S	0.0155 U	0.00114 U	0.0124 U	0.00140 U	0.00289 U	0.0213 U	0.00236 U	0.000496 U	0.00130 U	0.00140 U	0.00742 U	0.00459 U	0.00504 U
	MW-326-30	09/09/19	PES	PACE	30	11.3	S	0.0505 U	0.00372 U	0.0404 U	0.00457 U	0.00941 U	**0.105 J**	0.00768 U	0.00161 U	0.00424 U	0.00457 U	0.0241 U	0.0150 U	0.0164 U
	MW-326-35	09/09/19	PES	PACE	35	6.3	S	**0.0175 J**	0.00114 U	0.0124 U	0.00140 U	0.00288 U	**0.0416 J**	0.00235 U	0.000495 U	0.00130 U	0.00140 U	0.00740 U	0.00458 U	0.00502 U
	MW-326-40	09/09/19	PES	PACE	40	1.3	S	0.0149 U	0.00110 U	0.0119 U	0.00135 U	0.00278 U	**0.0437 J**	0.00227 U	0.000477 U	0.00125 U	0.00135 U	0.00713 U	0.00441 U	0.00484 U
	MW-326-45	09/09/19	PES	PACE	45	-3.7	S	0.0151 U	0.00111 U	0.0120 U	0.00136 U	0.00281 U	0.0165 U	0.00229 U	0.000482 U	0.00126 U	0.00136 U	0.00720 U	0.00446 U	0.00489 U
	MW-326-50	09/09/19	PES	PACE	50	-8.7	S	**0.0161 J**	0.00105 U	0.0114 U	0.00129 U	0.00266 U	0.0157 U	0.00217 U	0.000457 U	0.00120 U	0.00129 U	0.00684 U	0.00423 U	0.00464 U
	MW-326-55	09/09/19	PES	PACE	55	-13.7	S	0.0152 U	0.00112 U	0.0122 U	0.00137 U	0.00283 U	0.0280 U	0.00231 U	0.000487 U	0.00128 U	0.00137 U	0.00727 U	0.00450 U	0.00494 U
	MW-326-60	09/09/19	PES	PACE	60	-18.7	S	0.0221 U	0.00100 U	0.0109 U	0.00123 U	0.00253 U	**0.0283**	0.00206 U	0.000435 U	0.00114 U	0.00123 U	0.00650 U	0.00402 U	0.00441 U
	MW-326-65	09/09/19	PES	PACE	65	-23.7	S	0.0145 U	0.00107 U	0.0116 U	0.00131 U	0.00270 U	**0.0224 J**	0.00220 U	**0.000517 J**	0.00122 U	0.00131 U	0.00693 U	0.00429 U	0.00471 U
	MW-326-70	09/09/19	PES	PACE	70	-28.7	S	0.0152 U	0.00112 U	0.0122 U	0.00138 U	0.00284 U	**0.0284 J**	0.00232 U	0.000487 U	0.00128 U	0.00138 U	0.00729 U	0.00451 U	0.00495 U
	MW-326-75	09/09/19	PES	PACE	75	-33.7	S	0.0152 U	0.00112 U	0.0121 U	0.00137 U	0.00282 U	0.0166 U	0.00230 U	0.000485 U	0.00127 U	0.00137 U	0.00725 U	0.00449 U	0.00492 U
	MW-326-80	09/09/19	PES	PACE	80	-38.7	S	0.0149 U	0.00109 U	0.0119 U	0.00134 U	0.00277 U	0.0163 U	0.00226 U	0.000475 U	0.00125 U	0.00134 U	0.00711 U	0.00440 U	0.00483 U
	MW-326-85	09/10/19	PES	PACE	85	-43.7	S	0.0146 U	0.00108 U	0.0117 U	0.00132 U	0.00272 U	**0.0195 J**	0.00222 U	0.000467 U	0.00123 U	0.00132 U	0.00699 U	0.00432 U	0.00474 U
	MW-326-90	09/10/19	PES	PACE	90	-48.7	S	**0.0237 J**	0.00108 U	0.0118 U	0.00133 U	0.00274 U	**0.0543**	0.00224 U	0.000471 U	0.00124 U	0.00133 U	0.00704 U	0.00436 U	0.00478 U
	MW-326-95	09/10/19	PES	PACE	95	-53.7	S	0.0140 U	0.00103 U	0.0112 U	0.00127 U	0.00262 U	**0.0322**	0.00213 U	0.000449 U	0.00118 U	0.00127 U	0.00672 U	0.00416 U	0.00456 U
	MW-200I-95	09/10/19	PES	PACE	95 (dup)	-53.7	S	**0.0147 J**	0.00105 U	0.0114 U	0.00129 U	0.00266 U	0.0188 U	0.00217 U	0.000456 U	0.00120 U	0.00129 U	0.00682 U	0.00422 U	0.00463 U
	MW-326-100	09/10/19	PES	PACE	100	-58.7	S	0.0151 U	0.00111 U	0.0121 U	0.00137 U	0.00282 U	0.0166 U	0.00230 U	0.000483 U	0.00127 U	0.00137 U	0.00722 U	0.00447 U	0.00491 U
MW-328 (-36.1 to -46.1)	MW-328-5	09/16/19	PES	PACE	5	23.4	V	0.0149 U	0.00109 U	0.0119 UJ	0.00134 U	0.00277 U	**0.0551**	0.00226 UJ	0.000476 U	0.00125 U	0.00134 U	0.00711 U	0.00440 U	0.00483 U
	MW-328-10	09/16/19	PES	PACE	10	18.4	S	**0.0178 J**	0.00126 U	0.0137 UJ	0.00155 U	0.00320 U	**0.0559**	0.00261 UJ	0.000550 U	0.00144 U	0.00155 U	0.00822 U	0.00509 U	0.00558 U
	MW-328-15	09/16/19	PES	PACE	15	13.4	S	0.0153 U	0.00113 U	0.0123 UJ	0.00139 U	0.00286 U	**0.0297 J**	0.00233 UJ	0.000491 U	0.00129 U	0.00139 U	0.00734 U	0.00454 U	0.00498 U
	MW-328-20	09/16/19	PES	PACE	20	8.4	S	0.0149 U	0.00110 U	0.0119 UJ	0.00135 U	**0.00631**	**0.0234 J**	0.00227 UJ	**0.000985 J**	0.00125 U	0.00135 U	0.00714 U	0.00442 U	0.00485 U
	MW-328-30	09/16/19	PES	PACE	30	-1.6	S	0.295 U	0.0216 U	0.236 UJ	0.0266 U	0.0550 U	**0.988**	0.0448 UJ	0.00943 U	0.0247 U	0.0266 U	0.141 U	0.0872 U	0.0957 U
	MW-328-35	09/16/19	PES	PACE	35	-6.6	S	**0.0240 J**	0.00118 U	0.0129 UJ	0.00145 U	**0.00376 J**	**0.0851**	0.00244 UJ	**0.00117 J**	0.00135 U	0.00145 U	0.00769 U	0.00475 U	0.00521 U
	MW-328-40	09/16/19	PES	PACE	40	-11.6	S	**0.0972**	0.00268 U	0.0291 UJ	0.00329 U	0.00678 U	**0.437**	0.00553 UJ	0.00116 U	0.00306 U	0.00329 U	0.0174 U	0.0108 U	0.0118 U
	MW-328-45	09/16/19	PES	PACE	45	-16.6	S	0.0154 U	0.00113 U	0.0123 UJ	0.00139 U	0.00287 U	**0.0423**	0.00234 UJ	0.000493 U	0.00129 U	0.00139 U	0.00737 U	0.00456 U	0.00501 U
	MW-328-50	09/16/19	PES	PACE	50	-21.6	S	0.459 UJ	0.0337 U	0.367 U	0.0414 U	0.0855 U	**1.39**	0.0698 UJ	0.0147 U	0.0386 U	0.0414 U	0.220 U	0.136 U	0.149 UJ
	MW-328-55	09/16/19	PES	PACE	55	-26.6	S	**0.0199 J**	0.00110 U	0.0119 U	0.00134 U	0.00277 U	**0.0665**	0.00226 UJ	0.000476 U	0.00125 U	0.00134 U	0.00712 U	0.00440 U	0.00483 UJ
	MW-328-60	09/16/19	PES	PACE	60	-31.6	S	0.0150 UJ	0.00111 U	0.0120 U	0.00136 U	0.00280 U	**0.0339**	0.00228 UJ	0.000481 U	0.00126 U	0.00136 U	0.00719 U	0.00445 U	0.00488 UJ
	MW-328-65	09/16/19	PES	PACE	65	-36.6	S	0.0146 UJ	0.00107 U	0.0117 U	0.00132 U	0.00272 U	**0.0345**	0.00222 UJ	0.000466 U	0.00122 U	0.00132 U	0.00697 U	0.00431 U	0.00473 UJ

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
MW-328	MW-328-70	09/16/19	PES	PACE	70	-41.6	S	0.0151 UJ	0.00111 U	0.0120 U	0.00136 U	0.00281 U	**0.0381**	0.00229 UJ	**0.0250**	0.00126 U	0.00136 U	0.00720 U	0.00446 U	0.00489 UJ
(continued)	MW-328-75	09/16/19	PES	PACE	75	-46.6	S	0.0146 UJ	0.00107 U	0.0117 U	0.00132 U	0.00272 U	**0.0426**	0.00222 UJ	**0.0475**	0.00122 U	0.00132 U	0.00697 U	0.00432 U	0.00474 UJ
	MW-328-80	09/16/19	PES	PACE	80	-51.6	S	0.0165 U	0.00121 U	0.0132 UJ	0.00149 U	0.00307 U	**0.0557**	0.00251 UJ	**0.0407**	0.00139 U	0.00149 U	0.00789 U	0.00488 U	0.00536 U
MW-329	MW-329-5	09/12/19	PES	PACE	5	24.3	V	0.0134 U	0.000983 U	0.0107 U	0.00121 U	0.00249 U	0.0146 U	0.00203 U	0.000428 U	0.00112 U	0.00121 U	0.00639 U	0.00395 U	0.00434 U
(-69.0 to -79.0)	MW-329-10	09/12/19	PES	PACE	10	19.3	S	0.0194 U	0.000968 U	0.0105 U	0.00119 U	0.00245 U	**0.0282**	0.00200 U	0.000421 U	0.00110 U	0.00119 U	0.00629 U	0.00389 U	0.00427 U
	MW-329-15	09/12/19	PES	PACE	15	14.3	S	0.0140 U	0.00101 U	0.0110 U	0.00124 U	0.00256 U	**0.0205 J**	0.00209 U	0.000439 U	0.00115 U	0.00124 U	0.00657 U	0.00406 U	0.00446 U
	MW-329-20	09/12/19	PES	PACE	20	9.3	S	0.0202 U	0.00127 U	0.0138 U	0.00156 U	0.00322 U	**0.0384**	0.00263 U	**0.00199**	0.00145 U	0.00156 U	0.00827 U	0.00511 U	0.00561 U
	MW-329-25	09/12/19	PES	PACE	25	4.3	S	0.0179 U	0.00132 U	0.0143 U	0.00162 U	0.00334 U	0.0205 U	0.00272 U	0.000573 U	0.00150 U	0.00162 U	0.00857 U	0.00530 U	0.00582 UJ
	MW-329-30	09/12/19	PES	PACE	30	-0.7	S	0.0154 U	0.00114 U	0.0124 U	0.00140 U	0.00288 U	0.0169 U	0.00235 U	**0.00404**	0.00130 U	0.00140 U	0.00739 U	0.00457 U	0.00501 UJ
	MW-329-35	09/12/19	PES	PACE	35	-5.7	S	0.0153 U	0.00113 U	0.0123 U	0.00138 U	0.00286 U	0.0237 U	0.00233 U	0.000490 U	0.00129 U	0.00138 U	0.00733 U	0.00453 U	0.00498 UJ
	MW-329-40	09/12/19	PES	PACE	40	-10.7	S	0.0154 U	0.00113 U	0.0123 U	0.00139 U	0.00287 U	0.0263 U	0.00234 U	0.000493 U	0.00129 U	0.00139 U	0.00737 U	0.00456 U	0.00500 UJ
	MW-329-45	09/12/19	PES	PACE	45	-15.7	S	0.0149 U	0.00110 U	0.0119 U	0.00135 U	0.00278 U	0.0249 U	0.00227 U	0.000477 U	0.00125 U	0.00135 U	0.00713 U	0.00441 U	0.00484 UJ
	MW-329-50	09/12/19	PES	PACE	50	-20.7	S	0.0154 U	0.00113 U	0.0123 U	0.00139 U	0.00287 U	0.0176 U	0.00234 U	0.000493 U	0.00129 U	0.00139 U	0.00737 U	0.00456 U	0.00500 UJ
	MW-2003-50	09/12/19	PES	PACE	50 (dup)	-20.7	S	0.0137 U	0.00101 U	0.0109 U	0.00123 U	0.00255 U	**0.0391**	0.00208 U	0.000437 U	0.00115 U	0.00123 UJ	0.00653 U	0.00404 U	0.00444 UJ
	MW-329-55	09/12/19	PES	PACE	55	-25.7	S	0.0144 U	0.00106 U	0.0115 U	0.00130 U	0.00269 U	0.0158 U	0.00219 U	0.000462 U	0.00121 U	0.00130 U	0.00690 U	0.00427 U	0.00469 UJ
	MW-329-60	09/12/19	PES	PACE	60	-30.7	S	0.0146 U	0.00108 U	0.0117 U	0.00132 U	0.00273 U	0.0199 U	0.00222 U	**0.00207**	0.00123 U	0.00132 U	0.00700 U	0.00433 U	0.00475 UJ
	MW-329-65	09/12/19	PES	PACE	65	-35.7	S	0.0146 U	0.00108 U	0.0117 U	0.00132 U	0.00272 U	**0.0349**	0.00222 U	**0.0241**	0.00123 U	0.00132 U	0.00699 U	0.00432 U	0.00474 UJ
	MW-329-70	09/12/19	PES	PACE	70	-40.7	S	0.0146 U	0.00107 U	0.0117 U	0.00132 U	0.00272 U	0.0228 U	0.00221 U	**0.0340**	0.00122 U	0.00132 U	0.00697 U	0.00431 U	0.00473 UJ
	MW-329-75	09/12/19	PES	PACE	75	-45.7	S	0.0143 U	0.00105 U	0.0115 U	0.00129 U	0.00267 U	0.0246 U	0.00218 U	**0.0265**	0.00120 U	0.00129 U	0.00685 U	0.00424 U	0.00465 UJ
	MW-329-80	09/12/19	PES	PACE	80	-50.7	S	**0.0156 J**	0.00112 U	0.0121 UJ	0.00137 U	0.00283 U	**0.0719**	0.00231 UJ	**0.0240**	0.00128 U	0.00137 U	0.00726 U	0.00449 U	0.00493 U
	MW-329-85	09/12/19	PES	PACE	85	-55.7	S	0.0146 U	0.00108 U	0.0117 U	0.00132 U	0.00272 U	0.0261 U	0.00222 U	**0.0597**	0.00123 U	0.00132 U	0.00699 U	0.00433 U	0.00475 UJ
	MW-329-90	09/12/19	PES	PACE	90	-60.7	S	0.0147 U	0.00108 U	0.0118 U	0.00133 U	0.00274 U	**0.0333**	0.00223 U	**0.0182**	0.00123 U	0.00133 U	0.00703 U	0.00435 U	0.00477 UJ
	MW-329-95	09/12/19	PES	PACE	95	-65.7	S	0.0148 U	0.00109 U	0.0119 U	0.00134 U	0.00277 U	0.0168 U	0.00226 U	**0.000753 J**	0.00125 U	0.00134 U	0.00710 U	0.00439 U	0.00482 UJ
	MW-329-100	09/12/19	PES	PACE	100	-70.7	S	0.0149 U	0.00110 U	0.0119 U	0.00135 U	0.00277 U	0.0195 U	0.00226 U	0.000476 U	0.00125 U	0.00135 U	0.00712 U	0.00441 U	0.00483 UJ
	MW-329-105	09/12/19	PES	PACE	105	-75.7	S	0.0138 U	0.00101 U	0.0110 U	0.00124 U	0.00257 U	0.0170 U	0.00209 U	0.000440 U	0.00116 U	0.00124 U	0.00658 U	0.00407 U	0.00447 UJ
	MW-329-110	09/12/19	PES	PACE	110	-80.7	S	0.0137 U	0.00101 U	0.0109 U	0.00123 U	0.00255 U	0.0150 U	0.00208 U	0.000437 U	0.00115 U	0.00123 U	0.00653 U	0.00404 U	0.00444 UJ
MW-330	MW-330-6	04/20/20	PES	PACE	6	46.0	V	0.0721 U	0.000982 U	0.00382 U	0.000511 U	0.00290 U	0.0415 U	0.00410 U	0.000530 U	0.00102 U	0.000641 U	0.00133 U	0.00224 U	0.000795 U
	MW-330-10	04/20/20	PES	PACE	10	42.0	V	0.0701 U	0.000954 U	0.00371 U	0.000497 U	0.00281 U	0.0403 U	0.00398 U	**0.00202**	0.000993 U	0.000622 U	0.00129 U	0.00217 U	0.000772 U
	MW-330-11.5	04/20/20	PES	PACE	11.5	40.5	V	0.0740 U	0.00101 U	0.00392 U	0.000525 U	**2.51**	**0.0470 J**	0.00421 U	0.000544 U	0.00105 U	0.000658 U	0.00136 U	0.00230 U	**0.00216 J**
	MW-330-16	04/20/20	PES	PACE	16	36.0	V	0.0721 U	0.000983 U	0.00382 U	0.000511 U	**0.00365 J**	0.0415 U	0.00410 U	0.000531 U	0.00102 U	0.000641 U	0.00133 U	0.00224 U	0.000795 U
	MW-330-21.5	04/20/20	PES	PACE	21.5	30.5	S	0.0676 U	0.000921 U	0.00358 U	0.000479 U	0.00272 U	0.0389 U	0.00384 U	0.000497 U	0.000958 U	0.000601 U	0.00125 U	0.00210 U	0.000745 U
	MW-330-27	04/20/20	PES	PACE	27	25.0	S	0.0683 U	0.000930 U	0.00361 U	0.000484 U	0.00274 U	0.0392 U	0.00388 U	0.000502 U	0.000968 U	0.000606 U	0.00126 U	0.00212 U	0.000753 U
	MW-330-32	04/20/20	PES	PACE	32	20.0	S	0.0684 U	0.000932 U	0.00362 U	0.000485 U	0.00275 U	0.0393 U	0.00389 U	0.000503 U	0.000969 U	0.000607 U	0.00126 U	0.00212 U	0.000754 U
	MW-330-38	04/20/20	PES	PACE	38	14.0	S	0.0683 U	0.000931 U	0.00361 U	0.000484 U	0.00274 U	0.0393 U	0.00388 U	0.000502 U	0.000968 U	0.000607 U	0.00126 U	0.00212 U	0.000753 U
	MW-330-42	04/20/20	PES	PACE	42	10.0	S	0.0665 U	0.000906 U	0.00352 U	0.000471 U	0.00267 U	0.0382 U	0.00378 U	0.000489 U	0.000942 U	0.000590 U	0.00122 U	0.00206 U	**0.00310 J**
	MW-330-47	04/20/20	PES	PACE	47	5.0	S	0.0719 U	0.000979 U	0.00380 U	0.000509 U	0.00289 U	0.0413 U	0.00409 U	0.000529 U	0.00102 U	0.000638 U	0.00132 U	0.00223 U	**0.00231 J**
	MW-330-52	04/20/20	PES	PACE	52	0.0	S	0.0697 U	0.000949 U	0.00369 U	0.000494 U	0.00280 U	0.0401 U	0.00396 U	0.000513 U	0.000988 U	0.000619 U	0.00128 U	0.00216 U	**0.00138 J**
	MW-330-58	04/20/20	PES	PACE	58	-6.0	S	0.0691 U	0.000941 U	0.00366 U	0.000490 U	0.00277 U	0.0397 U	0.00393 U	0.000508 U	0.000979 U	0.000614 U	0.00127 U	0.00214 U	**0.00466 J**
	MW-330-62	04/20/20	PES	PACE	62	-10.0	S	0.0697 U	0.000950 U	0.00369 U	0.000494 U	0.00280 U	0.0401 U	0.00396 U	0.000513 U	0.000989 U	0.000619 U	0.00129 U	0.00216 U	0.000769 U
MW-331	MW-331-7	04/17/20	PES	PACE	7	24.2	V	**0.181**	0.00134 U	**0.0122 J**	0.000695 U	**0.108**	**0.246**	0.00557 U	**0.259**	0.00139 U	0.000871 U	0.00181 U	0.00304 U	**0.0239**
	MW-331-11	04/17/20	PES	PACE	11	20.2	S	0.569 U	0.00775 U	0.0301 U	0.00403 U	**1.32**	0.327 U	0.0324 U	0.00419 U	0.00807 U	0.00505 UJ	0.0105 U	0.0177 U	0.00627 U
	MW-331-16	04/17/20	PES	PACE	16	15.2	S	0.0750 U	0.00102 U	0.00397 U	0.000531 U	**0.0110**	0.0431 U	0.00426 U	**0.00993**	0.00106 U	0.000666 UJ	0.00138 U	0.00233 U	**0.00107 J**
	MW-331-20	04/17/20	PES	PACE	20	11.2	S	0.0734 U	0.00100 U	0.00388 U	0.000520 U	0.00295 U	0.0422 U	**0.0289**	**0.0244**	0.00104 U	0.000652 UJ	0.00135 U	0.00228 U	0.000809 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
MW-331	MW-331-29.5	04/17/20	PES	PACE	29.5	1.7	S	0.0736 U	0.00100 U	0.00389 U	0.000522 U	0.00296 U	0.0423 U	0.00418 U	**0.0618**	0.00104 U	0.000654 UJ	0.00136 U	0.00228 U	0.000811 U
(continued)	MW-331-35	04/17/20	PES	PACE	35	-3.8	S	0.0750 U	0.00102 U	0.00397 U	0.000531 U	0.00301 U	0.0431 U	0.00426 U	0.000552 U	0.00106 U	0.000666 UJ	0.00138 U	0.00233 U	0.000827 U
	MW-2018-35	04/17/20	PES	PACE	35 (dup)	-3.8	S	0.0763 U	0.00104 U	0.00404 U	0.000541 U	0.00306 U	0.0439 U	0.00434 U	0.000561 U	0.00108 U	0.000678 UJ	0.00141 U	0.00237 U	0.000841 U
	MW-331-40	04/17/20	PES	PACE	40	-8.8	S	0.0766 U	0.00104 U	0.00405 U	0.000543 U	0.00308 U	0.0440 U	0.00436 U	**0.000668 J**	0.00109 U	0.000680 UJ	0.00141 U	0.00238 U	0.000845 U
	MW-331-45	04/17/20	PES	PACE	45	-13.8	S	0.0764 U	0.00104 U	0.00404 U	0.000541 U	0.00307 U	0.0439 U	0.00434 U	0.000562 U	0.00108 U	0.000678 UJ	0.00141 U	0.00237 U	0.000842 U
MW-332	MW-332-7	04/17/20	PES	PACE	7	29.3	V	0.0712 U	0.000970 U	0.00377 U	0.000505 U	0.00286 U	0.0409 U	0.00405 U	**0.00384**	0.00101 U	0.000632 U	0.00131 U	0.00221 U	**0.00133 J**
	MW-332-11	04/17/20	PES	PACE	11	25.3	V	0.0748 U	0.00102 U	0.00396 U	0.000530 U	0.00300 U	0.0430 U	0.00425 U	**0.00539**	0.00106 U	0.000664 U	0.00138 U	0.00232 U	0.000824 U
	MW-332-16	04/17/20	PES	PACE	16	20.3	S	0.0733 U	0.000998 U	0.00388 U	0.000519 U	0.00294 U	0.0421 U	0.00416 U	**0.00223**	0.00104 U	0.000651 U	0.00135 U	0.00227 U	0.000807 U
	MW-332-20	04/17/20	PES	PACE	20	16.3	S	0.0744 U	0.00101 U	0.00394 U	0.000527 U	0.00299 U	0.0428 U	0.00423 U	**0.00100 J**	0.00105 U	0.000661 U	0.00137 U	0.00231 U	0.000820 U
	MW-332-25	04/17/20	PES	PACE	25	11.3	S	0.0771 U	0.00105 U	0.00408 U	0.000546 U	0.00309 U	0.0443 U	0.00438 U	0.000567 U	0.00109 U	0.000684 U	0.00142 U	0.00239 U	0.000849 U
	MW-332-30	04/17/20	PES	PACE	30	6.3	S	0.0787 U	0.00107 U	0.00416 U	0.000558 U	0.00316 U	0.0452 U	0.00447 U	0.000579 U	0.00112 U	0.000699 U	0.00145 U	0.00244 U	0.000868 U
MW-334	MW-334-6	04/16/20	PES	PACE	6	25.4	V	0.0771 U	0.00105 U	0.00408 U	0.000547 U	0.00310 U	0.0443 U	0.00439 U	**0.00108 J**	0.00109 U	0.000685 U	0.00142 U	0.00239 U	**0.00300 J**
	MW-334-10	04/16/20	PES	PACE	10	21.4	V	0.0772 U	0.00105 U	0.00409 U	0.000547 U	**0.961**	**0.0495 J**	0.00439 U	0.000568 U	0.00109 U	0.000686 U	0.00142 U	0.00240 U	**0.0153**
	MW-334-13	04/16/20	PES	PACE	13	18.4	S	0.572 U	0.00779 U	0.0303 U	0.00405 U	0.0230 U	0.329 U	0.0325 U	0.00421 U	0.00810 U	0.00508 U	0.0105 U	0.0178 U	0.00630 U
	MW-334-17	04/16/20	PES	PACE	17	14.4	S	0.0656 U	0.000894 U	0.00347 U	0.000465 U	**0.0361**	0.0377 U	0.00373 U	0.000483 U	0.000930 U	0.000583 U	0.00121 U	0.00204 U	0.000723 U
	MW-334-23	04/16/20	PES	PACE	23	8.4	S	0.0756 U	0.00103 U	0.00400 U	0.000536 U	**0.0110**	0.0434 U	0.00430 U	**0.00177**	0.00107 U	0.000671 U	0.00139 U	0.00234 U	**0.00530 J**
	MW-334-28	04/16/20	PES	PACE	28	3.4	S	0.0748 U	0.00102 U	0.00396 U	0.000530 U	**0.00844**	0.0430 U	0.00425 U	**0.000841 J**	0.00106 U	0.000664 U	0.00138 U	0.00232 U	**0.00314 J**
	MW-334-35	04/16/20	PES	PACE	35	-3.6	S	0.0803 U	0.00109 U	0.00425 U	0.000569 U	0.00322 U	0.0461 U	0.00456 U	0.000590 U	0.00114 U	0.000713 U	0.00148 U	0.00249 U	0.000885 U
	MW-334-40	04/16/20	PES	PACE	40	-8.6	S	0.0820 U	0.00112 U	0.00434 U	0.000581 U	0.00329 U	0.0471 U	0.00466 U	0.000603 U	0.00116 U	0.000728 U	0.00151 U	0.00254 U	**0.00128 J**
	MW-334-45.5	04/16/20	PES	PACE	45.5	-14.1	S	0.0772 U	0.00105 U	0.00409 U	0.000547 U	0.00310 U	0.0444 U	0.00439 U	0.000568 U	0.00109 U	0.000686 U	0.00142 U	0.00240 U	0.000852 U
	MW-334-50	04/16/20	PES	PACE	50	-18.6	S	0.0703 U	0.000957 U	0.00372 U	0.000498 U	0.00282 U	0.0404 U	0.00399 U	0.000517 U	0.000996 U	0.000624 U	0.00129 U	0.00218 U	0.000775 U
	MW-334-54.5	04/16/20	PES	PACE	54.5	-23.1	S	0.0786 U	0.00107 U	0.00416 U	0.000557 U	0.00316 U	0.0452 U	0.00447 U	0.000578 U	0.00111 U	0.000698 U	0.00145 U	0.00244 U	**0.00131 J**
	MW-334-60	04/16/20	PES	PACE	60	-28.6	S	0.0723 U	0.000985 U	0.00383 U	0.000512 U	0.00290 U	0.0416 U	0.00411 U	0.000532 U	0.00102 U	0.000642 U	0.00133 U	0.00224 U	0.000797 U
	MW-334-63	04/16/20	PES	PACE	63	-31.6	S	0.0759 U	0.00103 U	0.00402 U	0.000538 U	0.00305 U	0.0437 U	0.00432 U	**0.000794 J**	0.00108 U	0.000675 U	0.00140 U	0.00236 U	0.000837 U
MW-336	MW-336-7	04/22/20	PES	PACE	7	26.7	V	0.0708 U	0.000965 U	0.00375 U	0.000502 U	0.00284 U	0.0407 U	0.00403 U	0.000521 U	0.00100 U	0.000629 U	0.00131 U	0.00220 U	0.000781 U
	MW-336-11.5	04/22/20	PES	PACE	11.5	22.2	V	0.0756 U	0.00103 U	0.00400 U	0.000536 U	**0.461 J**	0.0435 U	0.00430 U	0.000556 U	0.00107 U	0.000672 U	0.00139 U	0.00235 U	**0.00658 J**
	MW-2019-11.5	04/22/20	PES	PACE	11.5 (dup)	22.2	V	0.0774 U	0.00105 U	0.00410 U	**0.00474 J**	**0.184 J**	0.0445 U	0.00440 U	0.000570 U	0.00110 U	0.000688 U	0.00143 UJ	0.00240 U	**0.00409 J**
	MW-336-14.5	04/22/20	PES	PACE	14.5	19.2	V	0.0814 U	0.00111 U	0.00431 U	0.000577 U	**0.00660**	0.0468 U	0.00463 U	0.000599 U	0.00115 U	0.000723 U	0.00150 U	0.00253 U	0.000897 U
	MW-336-20	04/22/20	PES	PACE	20	13.7	S	0.0778 U	0.00106 U	0.00411 U	0.000551 U	0.00312 U	0.0447 U	0.00442 U	0.000572 U	0.00110 U	0.000691 U	0.00143 U	0.00241 U	0.000857 U
	MW-336-25	04/22/20	PES	PACE	25	8.7	S	**0.131 J**	0.00142 U	0.00553 U	0.000741 U	0.00420 U	**0.105 J**	0.00594 U	0.000769 U	0.00148 U	0.000928 U	0.00193 U	0.00324 U	0.00115 U
	MW-336-30	04/22/20	PES	PACE	30	3.7	S	0.0967 U	0.00132 U	0.00512 U	0.000685 U	0.00388 U	0.0556 U	0.00550 U	0.000711 U	0.00137 U	0.000859 U	0.00178 U	0.00300 U	0.00107 U
	MW-336-35	04/22/20	PES	PACE	35	-1.3	S	0.0779 U	0.00106 U	0.00412 U	0.000552 U	0.00313 U	0.0448 U	0.00443 U	0.000573 U	0.00110 U	0.000692 U	0.00144 U	0.00242 U	0.000859 U
	MW-336-40	04/22/20	PES	PACE	40	-6.3	S	0.0766 U	0.00104 U	0.00405 U	0.000543 U	0.00307 U	0.0440 U	0.00435 U	0.000563 U	0.00109 U	0.000680 U	0.00141 UJ	0.00238 U	0.000844 U
	MW-336-45	04/22/20	PES	PACE	45	-11.3	S	0.0843 U	0.00115 U	0.00446 U	0.000598 U	0.00339 U	0.0485 U	0.00479 U	0.000620 U	0.00120 U	0.000749 U	0.00155 UJ	0.00262 U	0.000930 U
	MW-336-51	04/22/20	PES	PACE	51	-17.3	S	0.0731 U	0.000996 U	0.00387 U	0.000518 U	0.00294 U	0.0420 U	0.00416 U	**0.00149**	0.00104 U	0.000649 U	0.00135 UJ	0.00227 U	0.000806 U
	MW-336-55	04/22/20	PES	PACE	55	-21.3	S	0.0725 U	0.000988 U	0.00384 U	0.000514 U	0.00291 U	0.0417 U	0.00412 U	**0.00153**	0.00103 U	0.000644 U	0.00134 UJ	0.00225 U	0.000800 U
	MW-336-60	04/22/20	PES	PACE	60	-26.3	S	**0.0813 J**	0.00102 U	0.00394 U	0.000528 U	0.00299 U	0.0428 U	0.00424 U	0.000548 U	0.00106 U	0.000662 U	0.00137 UJ	0.00231 U	0.000822 U
	MW-336-65	04/22/20	PES	PACE	65	-31.3	S	0.0741 U	0.00101 U	0.00392 U	0.000525 U	0.00297 U	0.0426 U	0.00421 U	0.000545 U	0.00105 U	0.000658 U	0.00136 UJ	0.00230 U	0.000817 U
	MW-336-69	04/22/20	PES	PACE	69	-35.3	S	0.0789 U	0.00108 U	0.00418 U	0.000559 U	0.00317 U	0.0454 U	0.00449 U	0.000580 U	0.00112 U	0.000701 U	0.00145 UJ	0.00245 U	0.000870 U
	MW-336-74.5	04/22/20	PES	PACE	74.5	-40.8	S	0.0739 U	0.00101 U	0.00391 U	0.000524 U	0.00297 U	0.0425 U	0.00420 U	0.000544 U	0.00105 U	0.000656 U	0.00136 UJ	0.00229 U	0.000815 U
	MW-336-79	04/22/20	PES	PACE	79	-45.3	S	0.0762 U	0.00104 U	0.00403 U	0.000540 U	0.00306 U	0.0438 U	0.00433 U	0.000560 U	0.00108 U	0.000677 U	0.00140 UJ	0.00236 U	0.000840 U
	MW-336-85	04/22/20	PES	PACE	85	-51.3	S	0.0763 U	0.00104 U	0.00404 U	0.000541 U	0.00306 U	0.0439 U	0.00434 U	0.000561 U	0.00108 U	0.000678 U	0.00141 UJ	0.00237 U	0.000841 U
	MW-2021-85	05/04/20	PES	PACE	85 (dup)	-51.3	S	0.0731 U	0.000996 U	0.00387 U	0.000518 U	0.00294 U	0.0420 U	0.00416 U	**0.0226**	0.00104 U	0.000649 U	0.00135 U	0.00227 U	0.000806 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
MW-336 (continued)	MW-336-90	04/22/20	PES	PACE	90	-56.3	S	0.0766 U	0.00104 U	0.00405 U	0.000543 U	0.00307 U	0.0440 U	0.00435 U	0.000563 U	0.00109 U	0.000680 U	0.00141 UJ	0.00238 U	0.000844 U
	MW-336-95	04/22/20	PES	PACE	95	-61.3	S	0.0763 U	0.00104 U	0.00404 U	0.000541 U	0.00306 U	0.0439 U	0.00434 U	0.000561 U	0.00108 U	0.000678 U	0.00141 UJ	0.00237 U	0.000841 U
	MW-2020-95	04/22/20	PES	PACE	95 (dup)	-61.3	S	0.0756 U	0.00103 U	0.00400 U	0.000536 U	0.00304 U	0.0435 U	0.00430 U	0.000556 U	0.00107 U	0.000672 U	0.00139 UJ	0.00235 U	0.000834 U
MW-338	MW-338-10	05/01/20	PES	PACE	10	17.8	S	0.0770 U	0.00105 U	0.00407 U	0.000546 U	0.00309 U	0.0443 U	0.00438 U	0.000566 U	0.00109 U	0.000684 U	0.00142 U	0.00239 U	0.000849 U
	MW-338-15	05/01/20	PES	PACE	15	12.8	S	0.0840 U	0.00114 U	0.00444 U	0.000595 U	0.00337 U	0.0483 U	0.00477 U	0.000618 U	0.00119 U	0.000746 U	0.00155 U	0.00261 U	0.000926 U
	MW-338-20	05/01/20	PES	PACE	20	7.8	S	0.0736 U	0.00100 U	0.00389 U	0.000522 U	0.00296 U	0.0423 U	0.00418 U	0.000541 U	0.00104 U	0.000654 U	0.00136 U	0.00228 U	0.000811 U
	MW-338-23	05/01/20	PES	PACE	23	4.8	S	0.0807 U	0.00110 U	0.00427 U	0.000572 U	0.00324 U	0.0464 U	0.00459 U	0.000593 U	0.00114 U	0.000717 U	0.00149 U	0.00250 U	0.000890 U
	MW-338-28	05/01/20	PES	PACE	28	-0.2	S	0.0799 U	0.00109 U	0.00423 U	0.000566 U	0.00321 U	0.0459 U	0.00454 U	0.000587 U	0.00113 U	0.000709 U	0.00147 U	0.00248 U	0.000880 U
	MW-338-34	05/01/20	PES	PACE	34	-6.2	S	0.0710 U	0.000967 U	0.00376 U	0.000503 U	0.00285 U	0.0408 U	0.00403 U	**0.000782 J**	0.00101 U	0.000630 U	0.00131 U	0.00220 U	**0.00182 J**
	MW-338-39	05/01/20	PES	PACE	39	-11.2	S	0.0769 U	0.00105 U	0.00407 U	0.000545 U	0.00309 U	0.0442 U	0.00437 U	0.000566 U	0.00109 U	0.000683 U	0.00142 U	0.00239 U	0.000848 U
	MW-338-41	05/01/20	PES	PACE	41	-13.2	S	0.0783 U	0.00107 U	0.00414 U	0.000555 U	0.00314 U	0.0450 U	0.00445 U	0.000576 U	0.00111 U	0.000695 U	0.00144 U	0.00243 U	0.000863 U
	MW-338-45	05/01/20	PES	PACE	45	-17.2	S	0.0775 U	0.00106 U	0.00410 U	0.000549 U	0.00311 U	0.0446 U	0.00441 U	0.000570 U	0.00110 U	0.000688 U	0.00143 U	0.00240 U	0.000854 U
	MW-338-51	05/01/20	PES	PACE	51	-23.2	S	0.0787 U	0.00107 U	0.00416 U	0.000558 U	0.00316 U	0.0452 U	0.00447 U	0.000579 U	0.00112 U	0.000699 U	0.00145 U	0.00244 U	0.000868 U
	MW-338-55	05/01/20	PES	PACE	55	-27.2	S	0.0729 U	0.000993 U	0.00386 U	0.000517 U	0.00293 U	0.0419 U	0.00414 U	0.000536 U	0.00103 U	0.000647 U	0.00134 U	0.00226 U	0.000804 U
MW-341	MW-341-85	05/04/20	PES	PACE	85	-56.6	S	0.0721 U	0.000983 U	0.00382 U	0.000511 U	0.00290 U	0.0415 U	0.00410 U	**0.0194**	0.00102 U	0.000641 U	0.00133 U	0.00224 U	0.000795 U
	MW-341-90	05/04/20	PES	PACE	90	-61.6	S	0.0714 U	0.000973 U	0.00378 U	0.000506 U	0.00287 U	0.0411 U	0.00406 U	**0.0278**	0.00101 U	0.000634 U	0.00132 U	0.00222 U	0.000787 U
	MW-341-95	05/04/20	PES	PACE	95	-66.6	S	0.0740 U	0.00101 U	0.00391 U	0.000524 U	0.00297 U	0.0425 U	0.00421 U	**0.0491**	0.00105 U	0.000657 U	0.00136 U	0.00230 U	0.000816 U
	MW-341-99	05/04/20	PES	PACE	99	-70.6	S	0.0744 U	0.00101 U	0.00394 U	0.000528 U	0.00299 U	0.0428 U	0.00423 U	**0.0400**	0.00106 U	0.000661 U	0.00137 U	0.00231 U	0.000821 U
	MW-341-104	05/04/20	PES	PACE	104	-75.6	S	0.0757 U	0.00103 U	0.00401 U	0.000537 U	0.00304 U	0.0435 U	0.00431 U	**0.0315**	0.00107 U	0.000673 U	0.00140 U	0.00235 U	0.000835 U
MW-343	MW-343-5	04/13/20	PES	PACE	5	22.6	V	0.0717 U	0.000977 U	0.00380 U	0.000508 U	**0.00439 J**	0.0412 U	0.00408 U	**0.119**	0.00102 U	0.000637 U	0.00132 U	0.00223 U	**0.00147 J**
	MW-343-10	04/13/20	PES	PACE	10	17.6	S	0.0752 U	0.00102 U	0.00398 U	0.000533 U	0.00302 U	0.0432 U	0.00427 U	**0.0536**	0.00107 U	0.000668 U	0.00139 U	0.00233 U	**0.00176 J**
	MW-343-12.5	04/13/20	PES	PACE	12.5	15.1	S	0.0779 U	0.00106 U	0.00412 U	0.000552 U	0.00313 U	0.0448 U	0.00443 U	0.000573 U	0.00110 U	0.000692 U	0.00144 U	0.00242 U	0.000859 U
	MW-343-17	04/13/20	PES	PACE	17	10.6	S	**0.0872 J**	0.000995 U	0.00387 U	0.000518 U	0.00293 U	0.0420 U	0.00415 U	0.000537 U	0.00104 U	0.000649 U	0.00135 U	0.00227 U	0.000805 U
	MW-343-24	04/13/20	PES	PACE	24	3.6	S	0.0732 U	0.000997 U	0.00387 U	0.000519 U	**0.00319 J**	0.0421 U	0.00416 U	**0.00400**	0.00104 U	0.000650 U	0.00135 U	0.00227 U	**0.00340 J**
	MW-343-28.5	04/13/20	PES	PACE	28.5	-0.9	S	0.0786 U	0.00107 U	0.00416 U	0.000557 U	**0.0107**	0.0452 U	0.00447 U	**0.00116 J**	0.00111 U	0.000698 U	0.00145 U	0.00244 U	0.000866 U
	MW-343-35	04/13/20	PES	PACE	35	-7.4	S	0.0795 U	0.00108 U	0.00420 U	0.000563 U	0.00319 U	0.0457 U	0.00452 U	0.000584 U	0.00113 U	0.000706 U	0.00146 U	0.00247 U	0.000876 U
	MW-343-38	04/13/20	PES	PACE	38	-10.4	S	0.0743 U	0.00101 U	0.00393 U	0.000526 U	0.00298 U	0.0427 U	0.00422 U	0.000546 U	0.00105 U	0.000660 U	0.00137 U	0.00230 U	0.000819 U
	MW-343-44	04/13/20	PES	PACE	44	-16.4	S	0.0700 U	0.000953 U	0.00370 U	0.000496 U	0.00281 U	0.0402 U	0.00398 U	0.000515 U	0.000992 U	0.000622 U	0.00129 U	0.00217 U	0.000772 U
	MW-343-47	04/13/20	PES	PACE	47	-19.4	S	0.0790 U	0.00108 U	0.00418 U	0.000560 U	0.00317 U	0.0454 U	0.00449 U	0.000581 U	0.00112 U	0.000702 U	0.00146 U	0.00245 U	0.000871 U
	MW-343-51	04/13/20	PES	PACE	51	-23.4	S	0.0706 U	0.000962 U	0.00374 U	0.000501 U	0.00284 U	0.0406 U	0.00402 U	0.000520 U	0.00100 U	0.000627 U	0.00130 U	0.00219 U	0.000779 U
	MW-343-55	04/13/20	PES	PACE	55	-27.4	S	0.0722 U	0.000984 U	0.00382 U	0.000512 U	0.00290 U	0.0415 U	0.00411 U	0.000531 U	0.00102 U	0.000641 U	0.00133 U	0.00224 U	0.000796 U
	MW-343-62	04/13/20	PES	PACE	62	-34.4	S	0.0735 U	0.00100 U	0.00389 U	0.000521 U	0.00295 U	0.0422 U	0.00418 U	**0.000572 J**	0.00104 U	0.000653 U	0.00135 U	0.00228 U	0.000810 U
	MW-343-68	04/13/20	PES	PACE	68	-40.4	S	0.0724 U	0.000986 U	0.00383 U	0.000513 U	0.00291 U	0.0416 U	0.00412 U	0.000532 U	0.00103 U	0.000643 U	0.00133 U	0.00225 U	0.000798 U
	MW-343-73	04/13/20	PES	PACE	73	-45.4	S	0.0731 U	0.000996 U	0.00387 U	0.000518 U	0.00294 U	0.0420 U	0.00416 U	**0.000727 J**	0.00104 U	0.000650 U	0.00135 U	0.00227 U	0.000806 U
	MW-343-79	04/13/20	PES	PACE	79	-51.4	S	0.0688 U	0.000937 U	0.00364 U	0.000487 U	0.00276 U	0.0395 U	0.00391 U	**0.000856 J**	0.000975 U	0.000611 U	0.00127 U	0.00213 U	0.000758 U
	MW-343-82	04/13/20	PES	PACE	82	-54.4	S	0.0690 U	0.000939 U	0.00365 U	0.000489 U	0.00277 U	0.0396 U	0.00392 U	**0.000828 J**	0.000977 U	0.000612 U	0.00127 U	0.00214 U	0.000760 U
	MW-343-86	04/13/20	PES	PACE	86	-58.4	S	0.0673 U	0.000916 U	0.00356 U	0.000477 U	0.00270 U	0.0387 U	0.00382 U	0.000495 U	0.000953 U	0.000597 U	0.00124 U	0.00209 U	0.000741 U
	MW-343-93	04/13/20	PES	PACE	93	-65.4	S	0.0711 U	0.000969 U	0.00376 U	0.000504 U	0.00286 U	0.0409 U	0.00404 U	0.000523 U	0.00101 U	0.000632 U	0.00131 U	0.00221 U	0.000784 U
	MW-343-99	04/13/20	PES	PACE	99	-71.4	S	0.0682 U	0.000929 U	0.00361 U	0.000483 U	0.00274 U	0.0392 U	0.00388 U	0.000501 U	0.000966 U	0.000605 U	0.00126 U	0.00211 U	0.000751 U
	MW-343-102	04/14/20	PES	PACE	102	-74.4	S	0.0701 UJ	0.000954 U	0.00371 U	0.000496 U	0.00281 U	0.0403 U	0.00398 UJ	**0.00125**	0.000993 U	0.000622 U	0.00129 U	0.00217 U	**0.00110 J**
	MW-2017-102	04/14/20	PES	PACE	102 (dup)	-74.4	S	0.0693 UJ	0.000945 U	0.00367 U	0.000491 U	0.00278 U	0.0399 U	0.00394 UJ	**0.00202**	0.000983 U	0.000616 U	0.00128 U	0.00215 U	0.000764 U
	MW-343-106	04/14/20	PES	PACE	106	-78.4	S	0.0681 UJ	0.000927 U	0.00360 U	0.000482 U	0.00273 U	0.0391 U	0.00387 UJ	**0.00459**	0.000965 U	0.000605 U	0.00125 U	0.00211 U	0.000750 U
	MW-343-108	04/14/20	PES	PACE	108	-80.4	S	0.0704 UJ	0.000959 U	0.00372 U	0.000499 U	0.00283 U	0.0405 U	0.00400 UJ	**0.00360**	0.000998 U	0.000625 U	0.00130 U	0.00218 U	0.000776 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
PH22	PH22	04/17/18	PES	Fremont	0-3	–	V	–	0.0304 U	–	0.0304 U	0.0608 U	–	–	0.0243 U	0.0243 U	–	0.0608 U	0.0608 UJ	–
PH34	PH34	04/17/18	PES	Fremont	1.5-6.5	–	V	–	0.0240 U	–	0.0240 U	0.0481 U	–	–	0.0192 U	0.0192 U	–	0.0481 U	0.0481 UJ	–
PH38	PH38	04/17/18	PES	Fremont	1.5-4	–	V	–	0.0292 U	–	0.0292 U	0.0583 U	–	–	0.0233 U	0.0233 U	–	0.0583 U	0.0583 UJ	–
PH52	PH52	04/17/18	PES	Fremont	1-5	–	V	–	0.0282 U	–	0.0282 U	0.0564 U	–	–	0.0226 U	0.0226 U	–	0.0564 U	0.0564 UJ	–
PW-1	Composite	01/01/98	B&V	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
PW-4	Composite	05/13/98	B&V	Unknown	–	–	–	–	–	–	–	–	–	–	ND	–	–	–	–	–
R-MW4	Unknown	10/22/92	Roux	Unknown	5	35.9	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	Unknown	10/22/92	Roux	Unknown	15	25.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	Unknown	10/22/92	Roux	Unknown	30	10.9	S	–	–	–	–	–	–	–	–	–	–	–	–	–
R-MW6	Unknown	10/27/92	Roux	Unknown	6	39.3	V	–	–	–	–	–	–	–	–	–	–	–	–	–
(33.3 to 23.3)	Unknown	10/27/92	Roux	Unknown	11	34.3	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	Unknown	10/27/92	Roux	Unknown	16	29.3	S	–	–	–	–	–	–	–	–	–	–	–	–	–
RB1	RB1-17.5	10/18/93	Retec	AAL	17.5	18.4	S	–	–	–	–	–	–	–	0.063 U	–	–	–	–	–
RB2	RB2-12.5	10/18/93	Retec	AAL	12.5	23.6	V	–	–	–	–	–	–	–	0.062 U	–	–	–	–	–
	RB2-17.5	10/18/93	Retec	AAL	17.5	18.6	S	–	–	–	–	–	–	–	**0.045 J**	–	–	–	–	–
RB3	RB3-17.5	10/18/93	Retec	AAL	17.5	20.5	S	–	–	–	–	–	–	–	0.061 U	–	–	–	–	–
SCL-B100	B-100, S1	06/10/02	Urban	F&BI	5-6.5	–	V	–	–	–	–	–	–	–	0.02 U	–	–	–	–	–
	B-100, S2	06/10/02	Urban	F&BI	10-11.5	–	V	–	–	–	–	–	–	–	0.02 U	–	–	–	–	–
SCL-B101	B-101- S1&2	06/17/02	Urban	F&BI	0-6	–	V	–	–	–	–	–	–	–	0.02 U	–	–	–	–	–
	B101-S3	06/17/02	Urban	F&BI	8	–	V	–	–	–	–	–	–	–	0.02 U	–	–	–	–	–
SCL-B102	B102-S1	06/17/02	Urban	F&BI	0-3	–	V	–	–	–	–	–	–	–	**0.03**	–	–	–	–	–
	B102-S2	06/17/02	Urban	F&BI	4	–	V	–	–	–	–	–	–	–	0.02 U	–	–	–	–	–
SCL-MW101	MW101-S3	06/14/02	Urban	F&BI	16	–	S	–	–	–	–	–	–	–	**0.07**	–	–	–	–	–
(25.0 to 15.0)																				
SCL-MW102	MW-102, S1	06/10/02	Urban	F&BI	5-6.5	–	S	–	–	–	–	–	–	–	**0.67**	–	–	–	–	–
	MW-102, S2	06/10/02	Urban	F&BI	5-6.5, 10-11.5	–	S	–	–	–	–	–	–	–	**0.05**	–	–	–	–	–
SCL-MW103	MW103-S1&S2	06/14/02	Urban	F&BI	5-6.5, 10-11.5	–	S	–	–	–	–	–	–	–	0.02 U	–	–	–	–	–
SCL-MW105	MW-105, S2	06/10/02	Urban	F&BI	10-11.5	–	S	–	–	–	–	–	–	–	**2.1**	–	–	–	–	–
(10.8 to 0.8)	MW-105, S4	06/10/02	Urban	F&BI	20-21.5	–	S	–	–	–	–	–	–	–	**0.05**	–	–	–	–	–
SCLB-1	RS1-2.5/RS-1 7.5 (Comp)	03/12/93	EPJ	OnSite	2.5-7.5	–	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS1-12.5/RS1-17.5 (Comp)	03/12/93	EPJ	OnSite	12.5-17.5	–	S	–	–	–	–	–	–	–	**2.0**	–	–	–	–	–
	RS-1 17.5	03/12/93	EPJ	OnSite	17.5	21.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS1-22.5/RS-27.5 (Comp)	03/12/93	EPJ	OnSite	22.5-27.5	–	S	–	–	–	–	–	–	–	**0.089 J**	–	–	–	–	–
	RS1-32.5	03/12/93	EPJ	OnSite	32.5	6.0	S	–	–	–	–	–	–	–	**0.18**	–	–	–	–	–
	RS1-37.5	03/12/93	EPJ	OnSite	37.5	1.0	S	–	–	–	–	–	–	–	0.050 U	–	–	–	–	–
SCLB-2	RS2-2.5/RS-2 7.5 (Comp)	03/12/93	EPJ	OnSite	2.5-7.5	–	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS2-12.5/RS2-17.5 (Comp)	03/12/93	EPJ	OnSite	12.5-17.5	–	S	–	–	–	–	–	–	–	**4.0**	–	–	–	–	–
	RS2-17.5	03/12/93	EPJ	OnSite	17.5	21.0	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	RS2-22.5/RS2-27.5 (Comp)	03/12/93	EPJ	OnSite	22.5-27.5	–	S	–	–	–	–	–	–	–	**0.8**	–	–	–	–	–
	RS2-32.5	03/12/93	EPJ	OnSite	32.5	6.0	S	–	–	–	–	–	–	–	**1.5**	–	–	–	–	–
	RS2-37.5	03/12/93	EPJ	OnSite	37.5	1.0	S	–	–	–	–	–	–	–	**0.74**	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
SSD-MW-1	MW-1 S-2	05/24/89	HC	Unknown	5-6.5	34.0	V	–	–	–	–	–	–	–	0.01 U	–	–	–	–	–
	MW-1 S-6	05/24/89	HC	Unknown	15-16.5	24.0	S	–	–	–	–	–	–	–	0.01 U	–	–	–	–	–
SSD-MW-2	MW-2 S-3	05/24/89	HC	Unknown	7.5-9	31.0	V	–	–	–	–	–	–	–	0.01 U	–	–	–	–	–
	MW-2 S-6	05/24/89	HC	Unknown	15-16.5	31.0	V	–	–	–	–	–	–	–	0.01 U	–	–	–	–	–
SSD-MW-3	MW-3 S-2	05/24/89	HC	Unknown	5-6.5	34.0	V	–	–	–	–	–	–	–	0.01 U	–	–	–	–	–
	MW-3 S-5	05/24/89	HC	Unknown	12.5-14	34.0	V	–	–	–	–	–	–	–	0.01 U	–	–	–	–	–
SSD-MW-4	MW-4 S-6	05/25/89	HC	Unknown	14.5-16	36.8	V	–	–	–	–	–	–	–	0.01 U	–	–	–	–	–
	MW-4 S-9	05/25/89	HC	Unknown	22-23	29.5	S	–	–	–	–	–	–	–	0.01 U	–	–	–	–	–
SV-04	SV-04-6	06/29/20	PES	PACE	6	–	V	0.0823 U	0.00112 U	0.00435 U	0.000583 U	0.00330 U	0.0473 U	0.00468 U	0.000605 U	0.00117 U	0.000731 U	0.00152 U	0.00255 U	0.000907 U
SV-05	SV-05-10	06/29/20	PES	PACE	10	–	V	0.0879 U	0.00120 U	0.00465 U	0.000623 U	0.00353 U	0.0505 U	0.00500 U	0.000647 U	0.00125 U	0.000781 U	0.00162 U	0.00273 U	0.000969 U
SV-06	SV-06-6	06/29/20	PES	PACE	6	–	V	0.0810 U	0.00110 U	0.00429 U	0.000574 U	0.00325 U	0.0466 U	0.00461 U	0.000596 U	0.00115 U	0.000720 U	0.00149 U	0.00251 U	0.000893 U
SV-07	SV-07-15	06/29/20	PES	PACE	15	–	V	0.0696 U	0.000948 U	0.00368 U	0.000493 U	0.00279 U	0.0400 U	0.00396 U	0.000512 U	0.000986 U	0.000618 U	0.00128 U	0.00216 U	0.000767 U
SV-08	SV-08-6	06/30/20	PES	PACE	6	–	V	0.0883 U	0.00120 U	0.00467 U	0.000626 U	0.00355 U	0.0508 U	0.00502 U	**0.00156**	0.00125 U	0.000784 U	0.00163 U	0.00274 U	0.000973 U
	SV-08-7.5	06/30/20	PES	PACE	7.5	–	V	0.0900 U	0.00123 U	0.00476 U	0.000638 U	0.00361 U	0.0517 U	0.00512 U	0.000662 U	0.00128 U	0.000799 U	0.00166 U	0.00279 U	0.000992 U
SV-09	SV-09-5.5	07/01/20	PES	PACE	5.5	–	V	0.0840 U	0.00114 U	0.00445 U	0.000596 U	0.00338 U	0.0483 U	0.00478 U	0.000618 U	0.00119 U	0.000746 U	0.00155 U	0.00261 U	0.000926 U
SV-10	SV-10-5.5	06/30/20	PES	PACE	5.5	–	V	0.0837 U	0.00114 U	0.00443 U	0.000593 U	0.00336 U	0.0481 U	0.00476 U	0.000616 U	0.00119 U	0.000743 U	0.00154 U	0.00260 U	0.000923 U
SV-11	SV-11-10	06/30/20	PES	PACE	10	–	V	0.0849 U	0.00116 U	0.00449 U	0.000602 U	0.00341 U	0.0488 U	0.00483 U	**0.000864 J**	0.00120 U	0.000754 U	0.00156 U	0.00263 U	0.000936 U
SV-12	SV-12-5.5	07/01/20	PES	PACE	5.5	–	V	0.0694 U	0.000946 U	0.00367 U	0.000492 U	0.00279 U	0.0399 U	0.00395 U	**0.0781**	0.000984 U	0.000617 U	0.00128 U	0.00215 U	0.000765 U
SV-13	SV-13-10.5	07/01/20	PES	PACE	10.5	–	V	0.0814 U	0.00111 U	0.00431 U	0.000577 U	0.00327 U	0.0468 U	0.00463 U	**0.000828 J**	0.00115 U	0.000723 U	0.00150 U	0.00253 U	0.000898 U
SV-14	SV-14-5.5	07/01/20	PES	PACE	5.5	–	V	0.0849 U	0.00116 U	0.00449 U	0.000602 U	0.00341 U	0.0488 U	0.00483 U	0.000624 U	0.00120 U	0.000754 U	0.00156 U	0.00263 U	0.000936 U
SV-15	SV-15-13	07/01/20	PES	PACE	13	–	V	0.0824 U	0.00112 U	0.00436 U	0.000584 U	0.00331 U	0.0474 U	0.00468 U	0.000606 U	0.00117 U	0.000732 U	0.00152 U	0.00256 U	0.000908 U
SV-16	SV-16-5	07/02/20	PES	PACE	5	–	V	**0.254 J**	0.00230 U	0.00892 U	0.00119 U	**0.950 J**	0.0969 U	0.00959 U	**0.0310**	0.00240 U	0.00150 U	0.00310 U	0.00524 U	0.00186 U
	SV-100-5	07/02/20	PES	PACE	5 (dup)	–	V	0.151 U	0.00205 U	0.00798 U	0.00107 U	**1.34 J**	0.0867 U	0.00858 U	**0.0271**	0.00214 U	0.00134 U	0.00278 U	0.00468 U	0.00166 U
SV-17	SV-17-4.5	07/02/20	PES	PACE	4.5	–	V	0.125 U	0.00170 U	0.00660 U	0.000886 U	**0.0428**	0.0719 U	0.00711 U	**0.0148**	0.00177 U	0.00111 U	0.00230 U	0.00388 U	0.00138 U
SV-18	SV-18-5.5	07/02/20	PES	PACE	5.5	–	V	0.0684 U	0.000932 U	0.00362 U	0.000485 U	0.00275 U	0.0393 U	0.00389 U	0.000503 U	0.000970 U	0.000608 U	0.00126 U	0.00212 U	0.000754 U
SV-19	SV-19-5	07/09/20	PES	PACE	5	–	V	0.0684 U	0.000932 U	0.00362 U	0.000485 U	0.00275 U	0.0393 U	0.00389 U	**0.00338**	0.000969 U	0.000607 U	0.00126 U	0.00212 U	0.000754 U
SV-20	SV-20-9	07/09/20	PES	PACE	9	–	V	0.0899 U	0.00122 U	0.00476 U	0.000637 U	0.00361 U	0.0517 U	0.00511 U	0.000661 U	0.00127 U	0.000798 U	0.00166 U	0.00279 U	0.000991 U
SV-21	SV-21-6	07/09/20	PES	PACE	6	–	V	0.0696 U	0.000948 U	0.00368 U	0.000493 U	0.00279 U	0.0400 U	0.00396 U	0.000512 U	0.000986 U	0.000618 U	0.00128 U	0.00216 U	0.000767 U
SV-22	SV-22-8.5	07/09/20	PES	PACE	8.5	–	V	0.130 U	0.00177 U	0.00686 U	0.000919 U	**0.0157**	0.0746 U	0.00738 U	**0.00128 J**	0.00184 U	0.00115 U	0.00239 U	0.00403 U	0.00143 U
SV-23	SV-23-4.5	07/09/20	PES	PACE	4.5	–	V	0.0960 U	0.00131 U	0.00508 U	0.000680 U	0.00386 U	0.0552 U	0.00546 U	0.000706 U	0.00136 U	0.000853 U	0.00177 U	0.00298 U	**0.00177 J**
SV-24	SV-24-8	07/09/20	PES	PACE	8	–	V	0.0689 U	0.000939 U	0.00365 U	0.000488 U	0.00277 U	0.0396 U	0.00392 U	0.000507 U	0.000977 U	0.000612 U	0.00127 U	0.00214 U	0.000760 U
SV-25	SV-25-4	07/10/20	PES	PACE	4	–	V	0.0836 U	0.00114 U	0.00443 U	0.000593 U	0.00336 U	0.0481 U	0.00475 U	0.000615 U	0.00119 U	0.000743 U	0.00154 U	0.00259 U	0.000922 U
SV-26	SV-26-12	07/10/20	PES	PACE	12	–	V	0.0929 U	0.00127 U	0.00492 U	0.000659 U	0.00373 U	0.0534 U	0.00528 U	0.000684 U	0.00132 U	0.000825 U	0.00171 U	0.00288 U	0.00102 U
SV-27	SV-27-5.5	07/10/20	PES	PACE	5.5	–	V	0.0833 U	0.00114 U	0.00441 U	0.000591 U	0.00335 U	0.0479 U	0.00474 U	0.000613 U	0.00118 U	0.000740 U	0.00154 U	0.00259 U	0.000919 U
	SV-27-13.5	07/10/20	PES	PACE	13.5	–	V	**0.107 J**	0.00114 U	0.00441 U	0.000591 U	0.00335 U	0.0480 U	0.00474 U	0.000614 U	0.00118 U	0.000741 U	0.00154 U	0.00259 U	0.000920 U
TB-12	16	08/01/97	B&V	Unknown	62-63	-24.5	S	–	–	–	–	–	–	–	–	–	–	–	–	–
TB-18	S-2	03/17/98	B&V	Unknown	5-6.5	38.3	V	–	–	–	–	–	–	–	ND	–	–	–	–	–
	S-8	03/17/98	B&V	Unknown	20-21.5	23.3	S	–	–	–	–	–	–	–	ND	–	–	–	–	–
	S-21	03/17/98	B&V	Unknown	57.5-59	1.2	S	–	–	–	–	–	–	–	ND	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
T1	T1-2.5-071718	07/17/18	PES	Fremont	2.5	–	V	0.265 U	0.0265 U	–	0.0265 U	0.0531 U	–	–	0.0212 U	0.0212 U	–	0.0531 UJ	0.0531 U	–
T-2	T-2-071618	07/16/18	PES	Fremont	2	–	V	0.143 U	0.0143 U	–	0.0143 U	0.0287 U	–	–	0.0115 U	0.0115 U	–	0.0287 U	0.0287 U	–
T-2B	T-2B-071618	07/16/18	PES	Fremont	2	–	V	0.297 U	0.0297 U	–	0.0297 U	0.0593 U	–	–	0.0237 U	0.0237 U	–	0.0593 U	0.0593 U	–
T2	T2-6-071718	07/17/18	PES	Fremont	6	–	V	0.307 U	0.0307 U	–	0.0307 U	0.0614 U	–	–	0.0245 U	0.0245 U	–	0.0614 UJ	0.0614 U	–
T3	T3-3-071718	07/17/18	PES	Fremont	3	–	V	0.287 U	0.0287 U	–	0.0287 U	0.0573 U	–	–	0.0229 U	0.0229 U	–	0.0573 UJ	0.0573 U	–
T4	T4-6-071718	07/17/18	PES	Fremont	6	–	V	0.258 U	0.0258 U	–	0.0258 U	0.0516 U	–	–	0.0206 U	0.0206 U	–	0.0516 UJ	0.0516 U	–
T-5	T-5-071618	07/16/18	PES	Fremont	5	–	V	0.255 U	0.0255 U	–	0.0255 U	0.0509 U	–	–	**0.0696**	0.0204 U	–	0.0509 U	0.0509 U	–
T6	T6-4-071818	07/18/18	PES	Fremont	4	–	V	0.237 U	0.0237 U	–	0.0237 U	0.0474 U	–	–	0.0189 U	0.0189 U	–	0.0474 U	0.0474 U	–
T7	T7-7-071818	07/18/18	PES	Fremont	7	–	V	0.342 U	0.0342 U	–	0.0342 U	0.0684 U	–	–	**0.0717**	0.0274 U	–	0.0684 U	0.0684 U	–
T8	T8-3-072018	07/20/18	PES	Fremont	3	–	V	0.268 U	0.0268 U	–	0.0268 U	0.0536 U	–	–	0.0214 U	0.0214 U	–	0.0536 U	0.0536 U	–
T8	T8-6-072018	07/20/18	PES	Fremont	6	–	V	0.377 U	0.0377 U	–	0.0377 U	0.0753 U	–	–	0.0301 U	0.0301 U	–	0.0753 U	0.0753 U	–
T9	T9-3-072018	07/20/18	PES	Fremont	3	–	V	0.437 U	0.0437 U	–	0.0437 U	0.0875 U	–	–	**0.0931**	0.0350 U	–	0.0875 U	0.0875 U	–
T9	T9-3.5-072018	07/20/18	PES	Fremont	3.5	–	V	0.291 U	0.0291 U	–	0.0291 U	0.0583 U	–	–	**0.183**	0.0233 U	–	0.0583 U	0.0583 U	–
T9	T9-6-072018	07/20/18	PES	Fremont	6	–	V	0.303 U	0.0303 U	–	0.0303 U	0.0605 U	–	–	**0.173**	0.0242 U	–	0.0605 U	0.0605 U	–
T10	T10-3-072018	07/20/18	PES	Fremont	3	–	V	0.513 U	0.0513 U	–	0.0513 U	0.103 U	–	–	**0.300**	0.0411 U	–	0.103 U	0.103 U	–
T10	T10-6-072018	07/20/18	PES	Fremont	6	–	V	0.278 U	0.0278 U	–	0.0278 U	0.0556 U	–	–	0.0222 U	0.0222 U	–	0.0556 U	0.0556 U	–
T11	T11-3.5-073118	07/31/18	PES	Fremont	3.5	–	V	–	0.0358 U	–	0.0358 U	0.0716 U	–	–	0.0286 U	0.0286 U	–	0.0716 U	0.0716 U	–
T12	T12-3-091818	09/18/18	PES	Fremont	3	–	V	–	0.0307 U	–	0.0307 U	0.0614 U	–	–	0.0245 U	0.0245 U	–	0.0614 U	0.0614 U	–
T12	T12-7-091818	09/18/18	PES	Fremont	7	–	V	–	0.0303 U	–	0.0303 U	0.0607 U	–	–	0.0243 U	0.0243 U	–	0.0607 U	0.0607 U	–
T12	T12-7.5-073118	07/31/18	PES	Fremont	7.5	–	V	–	0.0259 U	–	0.0259 U	0.0519 U	–	–	0.0207 U	0.0207 U	–	0.0519 U	0.0519 U	–
T13	T13-3.5-091818	09/18/18	PES	Fremont	3.5	–	V	–	0.0283 U	–	0.0283 U	0.0567 U	–	–	0.0227 U	0.0227 U	–	0.0567 U	0.0567 U	–
T13	T13-6.5-091818	09/18/18	PES	Fremont	6.5	–	V	–	0.0250 U	–	0.0250 U	0.0500 U	–	–	0.0200 U	0.0200 U	–	0.0500 U	0.0500 U	–
T14	T14-3.5-091818	09/18/18	PES	Fremont	3.5	–	V	–	0.0300 U	–	0.0300 U	0.0599 U	–	–	0.0240 U	0.0240 U	–	0.0599 U	0.0599 U	–
T14	T14-7-091818	09/18/18	PES	Fremont	7	–	V	–	0.0318 U	–	0.0318 U	0.0635 U	–	–	0.0254 U	0.0254 U	–	0.0635 U	0.0635 U	–
TP-15	TP-15-3-092818	09/28/18	PES	Fremont	3	–	V	–	0.0304 U	–	0.0304 U	0.0609 U	–	–	0.0244 U	0.0244 U	–	0.0609 U	0.0609 U	–
TP-15	TP-15-6.5-092818	09/28/18	PES	Fremont	6.5	–	V	–	0.0313 U	–	0.0313 U	0.0625 U	–	–	0.0250 U	0.0250 U	–	0.0625 U	0.0625 U	–
TP-16	TP-16-3-092818	09/28/18	PES	Fremont	3	–	V	–	0.0426 U	–	0.0426 U	0.0852 U	–	–	0.0341 U	0.0341 U	–	0.0852 U	0.0852 U	–
TP-16	TP-16-6-092818	09/28/18	PES	Fremont	6	–	V	–	0.0446 U	–	0.0446 U	0.0892 U	–	–	0.0357 U	0.0357 U	–	0.0892 U	0.0892 U	–
TP-16	TP-16-9-092818	09/28/18	PES	Fremont	9	–	V	–	0.0263 U	–	0.0263 U	0.0525 U	–	–	0.0210 U	0.0210 U	–	0.0525 U	0.0525 U	–
TP-SD-01	TP-SD-01-2	06/03/19	PES	Fremont	2	–	V	–	0.0214 U	–	0.0214 U	0.0429 U	–	–	0.0172 U	0.0172 U	–	0.0429 U	0.0429 U	–
TP-SD-01	TP-SD-01-5	06/03/19	PES	Fremont	5	–	V	–	0.0267 U	–	0.0267 U	0.0534 U	–	–	0.0213 U	0.0213 U	–	0.0534 U	0.0534 U	–
TP-SD-04	TP-SD-04-2	06/03/19	PES	Fremont	2	–	V	–	0.0252 U	–	0.0252 U	0.0504 U	–	–	0.0202 U	0.0202 U	–	0.0504 U	0.0504 U	–
TP-SD-04	TP-SD-04-5	06/03/19	PES	Fremont	5	–	V	–	0.0272 U	–	0.0272 U	0.0544 U	–	–	**0.0642**	0.0218 U	–	0.0544 U	0.0544 U	–
TP-SD-05	TP-SD-05-2	06/03/19	PES	Fremont	2	–	V	–	0.0258 U	–	0.0258 U	0.0517 U	–	–	**0.0372**	0.0207 U	–	0.0517 U	0.0517 U	–
TP-SD-05	TP-SD-05-5	06/03/19	PES	Fremont	5	–	V	–	0.0292 U	–	0.0292 U	0.0585 U	–	–	**0.605**	0.0234 U	–	0.0585 U	0.0585 U	–
TP-SD-06	TP-SD-06-2	06/03/19	PES	Fremont	2	–	V	–	0.0344 U	–	0.0344 U	0.0688 U	–	–	0.0275 U	0.0275 U	–	0.0688 U	0.0688 U	–
TP-SD-06	TP-SD-06-5	06/03/19	PES	Fremont	5	–	V	–	0.0272 U	–	0.0272 U	0.0544 U	–	–	**0.0226**	0.0218 U	–	0.0544 U	0.0544 U	–
TP-SD-07	TP-SD-07-2	06/03/19	PES	Fremont	2	–	V	–	0.0217 U	–	0.0217 U	0.0435 U	–	–	0.0174 U	0.0174 U	–	0.0435 U	0.0435 U	–
TP-SD-07	B-942-2	06/03/19	PES	Fremont	2 (dup)	–	V	–	0.0233 U	–	0.0233 U	0.0466 U	–	–	0.0186 U	0.0186 U	–	0.0466 U	0.0466 U	–
TP-SD-07	TP-SD-07-5	06/03/19	PES	Fremont	5	–	V	–	0.0212 U	–	0.0212 U	0.0424 U	–	–	0.0169 U	0.0169 U	–	0.0424 U	0.0424 U	–
TP-SD-08	TP-SD-08-2	06/03/19	PES	Fremont	2	–	V	–	0.0242 U	–	0.0242 U	0.0483 U	–	–	0.0193 U	0.0193 U	–	0.0483 U	0.0483 U	–
TP-SD-08	TP-SD-08-5	06/03/19	PES	Fremont	5	–	V	–	0.0207 U	–	0.0207 U	0.0415 U	–	–	0.0166 U	0.0166 U	–	0.0415 U	0.0415 U	–
TP-SD-08	TP-SD-08-8	06/03/19	PES	Fremont	8	–	S	–	0.0249 U	–	0.0249 U	0.0498 U	–	–	0.0199 U	0.0199 U	–	0.0498 U	0.0498 U	–
W-MW-01 (P-03)	SB-W-03-0160	01/27/12	WW	ARI	16-16.5	28.4	S	–	–	–	–	–	–	–	0.0010 U	–	–	–	–	–
(-25.1 to -35.1)	SB-W-03-0225	01/27/12	WW	ARI	22.5-23	21.9	S	–	–	–	–	–	–	–	0.0009 U	–	–	–	–	–
	SB-W-03-0315	01/27/12	WW	ARI	31.5-32	12.9	S	–	–	–	–	–	–	–	0.21 U	–	–	–	–	–
	SB-W-03-0450	01/27/12	WW	ARI	45-45.5	-0.6	S	–	–	–	–	–	–	–	0.0007 U	–	–	–	–	–
	SB-W-03-0550	01/27/12	WW	ARI	55.5-56	-11.1	S	–	–	–	–	–	–	–	0.045 U	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
W-MW-01 (P-03)	SB-W-03-0645	01/27/12	WW	ARI	64.5-65	-20.1	S	–	–	–	–	–	–	–	0.0008 U	–	–	–	–	–
(continued)	SB-W-03-0730	01/27/12	WW	ARI	73-73.5	-28.6	S	–	–	–	–	–	–	–	0.0007 U	–	–	–	–	–
W-MW-02 (P-06)	SB-W-06-0900	01/29/12	WW	ARI	9-9.5	34.0	S	–	–	–	–	–	–	–	**0.0009 J**	–	–	–	–	–
(-26.5 to -36.5)	SB-W-06-0185	01/29/12	WW	ARI	18.5-19	24.5	S	–	–	–	–	–	–	–	**0.0008 J**	–	–	–	–	–
	SB-W-06-0305	01/30/12	WW	ARI	30.5-31	12.6	S	–	–	–	–	–	–	–	0.27 U	–	–	–	–	–
	SB-W-06-0380	01/30/12	WW	ARI	38-38.5	5.0	S	–	–	–	–	–	–	–	0.046 U	–	–	–	–	–
	SB-W-06-0405	01/30/12	WW	ARI	40.5-41	2.5	S	–	–	–	–	–	–	–	0.036 U	–	–	–	–	–
	SB-W-06-0485	01/30/12	WW	ARI	48.5-49	-5.5	S	–	–	–	–	–	–	–	0.0008 U	–	–	–	–	–
	SB-W-06-9485	01/30/12	WW	ARI	48.5-49 (dup)	-5.5	S	–	–	–	–	–	–	–	0.0009 U	–	–	–	–	–
	SB-W-06-0590	01/30/12	WW	ARI	59-59.5	-16.0	S	–	–	–	–	–	–	–	0.043 U	–	–	–	–	–
	SB-W-06-0715	01/30/12	WW	ARI	71.5-72	-28.5	S	–	–	–	–	–	–	–	0.0008 U	–	–	–	–	–
	SB-W-06-0790	01/31/12	WW	ARI	79-79.5	-36.0	S	–	–	–	–	–	–	–	0.0009 U	–	–	–	–	–
All Data							Number of Analytes Measured	614	644	585	644	644	598	598	778	644	585	644	644	585
							Number of Analytes Detected	125	0	1	0	39	212	3	73	0	0	0	0	85
							Frequency of Detection	20.4%	0.0%	0.2%	0.0%	6.1%	35.5%	0.5%	9.4%	0.0%	0.0%	0.0%	0.0%	14.5%
							Maximum Detection	0.254 J	–	0.0122 U	0.00474 J	2.51	3.86 J	0.0289	10	–	–	–	–	0.0239
							Minimum Detection	0.00495 U	0.000313 U	0.00142 U	0.000249 U	0.000213 U	0.0106 U	0.00186 U	0.000285 U	0.000295 U	0.000405 U	0.000441 U	0.00139 U	0.000234 U
							Number Of Vadose (V) Detections above SL	0	0	0	–	–	0	0	18	0	–	0	0	0
							Number of Saturated (S) Detections above SL	0	0	0	–	–	2	0	65	0	–	0	0	0
2017-2021							Number of Analytes Measured	614	644	585	644	644	598	598	644	644	585	644	644	585
							Number of Analytes Detected	125	0	1	0	39	212	3	170	0	0	0	0	85
							Frequency of Detection	20.4%	0.0%	0.2%	0.0%	6.1%	35.5%	0.5%	26.4%	0.0%	0.0%	0.0%	0.0%	14.5%
							Maximum Detection	0.254 J	–	0.0122 U	0.00474 J	2.51	3.86 J	0.0289	3.5	–	–	–	–	0.0239
							Minimum Detection	0.00495 U	0.000313 U	0.00142 U	0.000249 U	0.000213 U	0.0106 U	0.00186 U	0.000285 U	0.000295 U	0.000405 U	0.000441 U	0.00139 U	0.000234 U
							Number Of Vadose (V) Detections above SL	0	0	0	–	–	0	0	17	0	–	0	0	0
							Number of Saturated (S) Detections above SL	0	0	0	–	–	2	0	42	0	–	0	0	0

Abbreviations:
AAL = Alden Analytical Laboratories, Inc., of Seattle, Washington
ARI = Analytical Resource, Incorporated, Seattle, Washington
B&V = Black Veatch
bgs = below ground surface
Comp = Composite Sample
dup = duplicate
EPJ = E.PJohnson Construction Inc., and Environmental
ESC = ESC Lab Services of Mt. Juliet, Tennessee
F&BI = Friedman & Bruya, Inc.
HC = Hart Crowser, Inc.
OnSite = OnSite Environmental Inc., of Redmond, Washington
Pace = Pace Analytical of Mt. Juliet, Tennessee (formerly ESC)
PES = PES Environmental, Inc.
Retec = Remediation Technologies, Inc.
Roux = Roux Associates
Urban = Urban Redevelopment LLC
WW = WW Environmental LLC

Notes:
Petroleum Hydrocarbons (PHCs) analyzed by Ecology Methods NWTPH-HCID, NWTPH-Gx, or NWTPH-Dx; or EPA Method 418.1, Method 8020, or Method 8015M.
VOCs analyzed by EPA Methods 8010, 8020, 8021B, 624/8240, or 8260B/C/D.
Well screen elevations provided below Sample Location. in parentheses when appliable.
PCUL = Preliminary Cleanup Level from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021. PCULs based on the practical quantitation limits (PQLs) italicized.
Detected results shown in **bold**.
Detections above the screening level in the vadose zone are shown in **bold and highlighted blue**.
Detections above the screening level in the saturated zone are shown in **bold and highlighted gray.**
– = Not available or results not analyzed.
B = Analyte detected in an associated method blank.
J = The reported concentration is an estimate based on detectable results between the method detection limit and reporting limit, laboratory QA/QC, or data validation review.
J+ = The result is an estimated quantity, but the result may be biased high.
J- = The result is an estimated quantity, but the result may be biased low.
ND = Not detected above laboratory reporting limit. Reporting limit not available.
R = The data is unusable. The sample result is rejected due to serious deficiencies in meeting QC criteria. The analyte may or may not be present in the sample
T = Analyte also detected in trip blank.
U = Not detected at a concentration exceeding laboratory reporting limit
ve = Estimated value. The reported range exceeds the calibration range of the analysis.
z = Gasoline/petroleum detection result is likely elevated due to high detections of CVOCs.

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	**–**	**0.074**	**–**	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	**–**	**0.007**	**–**	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
B-1A	B-1/S-2	12/01/89	HC	ARI	10.5	–	–	–	–	–	–	–	–	–				–	–
B-2A	B-2/S-1	12/01/89	HC	ARI	10	–	–	–	–	–	–	–	–	–				–	–
B-212	B-212-15	09/08/17	PES	ESC	15	42.6	V	0.000378 U	0.000244 U	0.000430 U	0.00109 U	0.000264 U	0.000432 U	0.000271 UJ	0.000302 U	0.000440 U	0.000293 U	0.000821 U	0.000342 U
	B-212-21	09/08/17	PES	ESC	21	36.6	S	0.000341 U	0.000220 U	0.000388 U	0.000983 U	0.000238 U	0.000390 U	0.000244 UJ	0.000272 U	0.000397 U	0.000264 U	0.000741 U	**0.00103 J**
	B-212-35	09/08/17	PES	ESC	35	22.6	S	0.000358 U	0.000231 U	0.000407 U	0.00103 U	0.000250 U	0.000409 U	0.000256 UJ	0.000286 U	0.000417 U	0.000277 U	0.000778 U	0.000324 U
	B-212-45	09/08/17	PES	ESC	45	12.6	S	0.000343 U	0.000222 U	0.000390 U	0.000990 U	0.000240 U	0.000392 U	0.000246 UJ	0.000274 U	0.000400 U	0.000266 U	0.000746 U	0.000311 U
	B-907-25	09/08/17	PES	ESC	45 (dup)	12.6	S	0.00980 U	0.00634 U	0.0111 U	0.0282 U	0.00684 U	0.0112 U	0.00703 U	0.00783 U	0.0114 U	0.00759 U	0.0213 U	0.00887 U
	B-212-55	09/08/17	PES	ESC	55	2.6	S	0.000370 U	0.000239 U	0.000421 U	0.00107 U	0.000258 U	0.000423 U	0.000265 UJ	0.000296 U	0.000431 U	0.000287 U	0.000804 U	0.000335 U
	B-212-65	09/08/17	PES	ESC	65	-7.4	S	0.000381 U	0.000246 U	0.000433 U	0.00110 U	0.000266 U	0.000435 U	0.000273 U	0.000304 U	0.000443 U	0.000295 U	0.000828 U	0.000345 U
	B-212-75	09/08/17	PES	ESC	75	-17.4	S	0.000381 U	0.000247 U	0.000434 U	0.00110 U	0.000266 U	0.000436 U	0.000273 U	0.000305 U	0.000444 U	0.000295 U	0.000829 U	0.000345 U
	B-212-85	09/11/17	PES	ESC	85	-27.4	S	0.000372 U	0.000241 U	0.000423 U	0.00107 U	0.000260 U	0.000425 U	0.000267 U	0.000297 U	0.000433 U	0.000288 U	0.000809 U	0.000337 U
	B-212-95	09/11/17	PES	ESC	95	-37.4	S	0.000428 U	0.000278 U	0.000488 U	0.00124 U	0.000299 U	0.000491 U	0.000308 U	0.000342 U	0.000499 U	0.000333 U	0.000933 U	0.000389 U
	B-212-100	09/11/17	PES	ESC	100	-42.4	S	0.000396 U	0.000256 U	0.000450 U	0.00114 U	0.000276 U	0.000453 U	0.000284 U	0.000316 U	0.000461 U	0.000307 U	0.000860 U	0.000358 U
B-213	B-213-15	09/05/17	PES	ESC	15	42.4	V	0.000380 U	0.000246 U	0.000432 U	0.00110 U	0.000265 U	0.000435 U	0.000272 U	0.000304 U	0.000443 U	0.000294 U	0.000826 U	0.000344 U
	B-213-21.5	09/05/17	PES	ESC	22	35.9	S	0.000342 U	0.000221 U	0.000389 U	0.000986 U	0.000239 U	0.000391 U	0.000245 U	0.000273 U	0.000398 U	0.000265 U	0.000743 U	**0.000991 J**
	B-213-35	09/05/17	PES	ESC	35	22.4	S	0.000355 U	0.000230 U	0.000404 U	0.00102 U	0.000248 U	0.000406 U	0.000254 U	0.000284 U	0.000414 U	0.000275 U	0.000772 U	0.000322 U
	B-213-45	09/05/17	PES	ESC	45	12.4	S	0.000364 U	0.000235 U	0.000413 U	0.00105 U	0.000254 U	0.000416 U	0.000260 U	0.000290 U	0.000423 U	0.000282 U	0.000790 U	0.000329 U
	B-213-55	09/05/17	PES	ESC	55	2.4	S	0.000357 U	0.000231 U	0.000406 U	0.00103 U	0.000249 U	0.000408 U	0.000256 U	0.000285 U	0.000416 U	0.000276 U	0.000776 U	0.000323 U
	B-213-65	09/05/17	PES	ESC	65	-7.6	S	0.000361 U	0.000233 U	0.000410 U	0.00104 U	0.000252 U	0.000413 U	0.000259 U	0.000288 U	0.000420 U	0.000279 U	0.000785 U	0.000327 U
	B-213-75	09/05/17	PES	ESC	75	-17.6	S	0.000358 U	0.000232 U	0.000408 U	0.00103 U	0.000250 U	0.000410 U	0.000257 U	0.000286 U	0.000417 U	0.000278 U	0.000779 U	0.000325 U
	B-213-85	09/05/17	PES	ESC	85	-27.6	S	0.000400 U	0.000258 U	0.000455 U	0.00115 U	0.000279 U	0.000457 U	0.000286 U	0.000319 U	0.000466 U	0.000310 U	0.000869 U	0.000362 U
	B-213-95	09/06/17	PES	ESC	95	-37.6	S	0.000405 U	0.000262 U	0.000461 U	0.00117 U	0.000283 U	0.000463 U	0.000290 U	0.000324 U	0.000472 U	0.000314 U	0.000881 U	0.000367 U
	B-213-105	09/06/17	PES	ESC	105	-47.6	S	0.000377 U	0.000244 U	0.000429 U	0.00109 U	0.000263 U	0.000431 U	0.000270 U	0.000301 U	0.000439 U	0.000292 U	0.000819 U	0.000341 U
	B-906-110	09/06/17	PES	ESC	105 (dup)	-47.6	S	0.000377 U	0.000243 U	0.000428 U	0.00109 U	0.000263 U	0.000431 U	0.000270 U	0.000301 U	0.000439 U	0.000292 U	0.000819 U	0.000341 U
	B-213-115	09/06/17	PES	ESC	115	-57.6	S	0.000402 U	0.000260 U	0.000457 U	0.00116 U	0.000281 U	0.000460 U	0.000288 U	0.000321 U	0.000468 U	0.000311 U	0.000874 U	0.000364 U
	B-213-125	09/06/17	PES	ESC	125	-67.6	S	0.000485 U	0.000314 U	0.000552 U	0.00140 U	0.000339 U	0.000555 U	0.000348 U	0.000388 U	0.000566 U	0.000376 U	0.00106 U	0.000440 U
B-214	B-214-15	09/07/17	PES	ESC	15	42.4	V	0.000352 U	0.000227 U	0.000400 U	0.00101 U	0.000246 U	0.000402 U	0.000252 UJ	0.000281 U	0.000410 U	0.000272 U	0.000765 U	0.000318 U
	B-214-25	09/07/17	PES	ESC	25	32.4	S	0.000347 U	0.000224 U	0.000394 U	0.00100 U	0.000242 U	0.000396 U	0.000248 UJ	0.000277 U	0.000404 U	0.000268 U	0.000754 U	0.000314 U
	B-214-35	09/07/17	PES	ESC	35	22.4	S	0.000356 U	0.000230 U	0.000405 U	0.00103 U	0.000249 U	0.000407 U	0.000255 UJ	0.000284 U	0.000415 U	0.000276 U	0.000774 U	0.000322 U
	B-214-45	09/07/17	PES	ESC	45	12.4	S	0.000349 U	0.000226 U	0.000397 U	0.00101 U	0.000244 U	0.000399 U	0.000250 UJ	0.000279 U	0.000407 U	0.000270 U	0.000759 U	0.000316 U
	B-214-55	09/07/17	PES	ESC	55	2.4	S	0.000364 U	0.000235 U	0.000414 U	0.00105 U	0.000254 U	0.000416 U	0.000261 UJ	0.000291 U	0.000424 U	0.000282 U	0.000792 U	0.000330 U
	B-214-65	09/07/17	PES	ESC	65	-7.6	S	0.000422 U	0.000273 U	0.000480 U	0.00122 U	0.000295 U	0.000483 U	0.000302 U	0.000337 U	0.000492 U	0.000327 U	0.000918 U	0.000382 U
	B-214-75	09/07/17	PES	ESC	75	-17.6	S	0.000364 U	0.000236 U	0.000414 U	0.00105 U	0.000254 U	0.000417 U	0.000261 U	0.000291 U	0.000424 U	0.000282 U	0.000792 U	0.000330 U
	B-214-85	09/07/17	PES	ESC	85	-27.6	S	0.000394 U	0.000255 U	0.000448 U	0.00114 U	0.000275 U	0.000451 U	0.000282 U	0.000315 U	0.000459 U	0.000305 U	0.000857 U	0.000357 U
	B-908-100	09/07/17	PES	ESC	85 (dup)	-27.6	S	0.000367 U	0.000237 U	0.000417 U	0.00106 U	0.000256 U	0.000419 U	0.000263 U	0.000293 U	0.000427 U	0.000284 U	0.000797 U	0.000332 U
	B-214-95	09/07/17	PES	ESC	95	-37.6	S	0.000360 U	0.000233 U	0.000409 U	0.00104 U	0.000251 U	0.000412 U	0.000258 U	0.000288 U	0.000419 U	0.000279 U	0.000783 U	0.000326 U
	B-214-105	09/07/17	PES	ESC	105	-47.6	S	0.000415 U	0.000268 U	0.000472 U	0.00120 U	0.000290 U	0.000475 U	0.000297 U	0.000332 U	0.000483 U	0.000321 U	0.000902 U	0.000376 U
	B-214-115	09/11/17	PES	ESC	115	-57.6	S	0.000400 U	0.000259 U	0.000455 U	0.00115 U	0.000279 U	0.000457 U	0.000287 U	0.000320 U	0.000466 U	0.000310 U	0.000870 U	0.000362 U
	B-214-120	09/11/17	PES	ESC	120	-62.6	S	0.000387 U	0.000250 U	0.000440 U	0.00112 U	0.000270 U	0.000443 U	0.000278 U	0.000309 U	0.000451 U	0.000300 U	0.000842 U	0.000351 U
B-215	B-215-15	09/12/17	PES	ESC	15	39.0	V	0.000356 U	0.000230 U	0.000405 U	0.00103 U	0.000248 U	0.000407 U	0.000255 U	0.000284 U	0.000414 U	0.000275 U	0.000773 U	0.000322 U
	B-215-25	09/12/17	PES	ESC	25	29.0	S	0.000351 U	0.000227 U	0.000399 U	0.00101 U	0.000245 U	0.000401 U	0.000252 U	0.000280 U	0.000409 U	0.000272 U	0.000763 U	0.000318 U
	B-215-35	09/12/17	PES	ESC	35	19.0	S	0.000387 U	0.000250 U	0.000440 U	0.00112 U	0.000270 U	0.000442 U	**0.0620**	0.000309 U	0.000450 U	0.000299 U	0.000841 U	0.000350 U
	B-215-45	09/12/17	PES	ESC	45	9.0	S	0.000349 U	0.000226 U	0.000397 U	0.00101 U	0.000244 U	0.000399 U	0.000250 U	0.000279 U	0.000406 U	0.000270 U	0.000759 U	0.000316 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
B-215 (continued)	B-215-55	09/12/17	PES	ESC	55	-1.1	S	0.000363 U	0.000235 U	0.000413 U	0.00105 U	0.000254 U	0.000415 U	0.000260 U	0.000290 U	0.000423 U	0.000281 U	0.000790 U	0.000329 U
	B-215-65	09/12/17	PES	ESC	65	-11.1	S	0.00938 U	0.00606 U	0.0107 U	0.0270 U	0.00654 U	0.0107 U	**1.55**	0.00749 U	0.0109 U	0.00726 U	0.0204 U	0.00849 U
	B-215-75	09/12/17	PES	ESC	75	-21.1	S	0.000362 U	0.000234 U	0.000411 U	0.00104 U	0.000253 U	0.000414 U	0.000259 U	0.000289 U	0.000421 U	0.000280 U	0.000786 U	0.000328 U
	B-215-85	09/13/17	PES	ESC	85	-31.1	S	0.000395 U	0.000256 U	0.000450 U	0.00114 U	0.000276 U	0.000452 U	0.000283 U	0.000316 U	0.000461 U	0.000306 U	0.000860 U	0.000358 U
	B-909-115	09/13/17	PES	ESC	85 (dup)	-31.1	S	0.000368 U	0.000238 U	0.000418 U	0.00106 U	0.000257 U	0.000420 U	0.000263 U	0.000294 U	0.000428 U	0.000285 U	0.000799 U	0.000333 U
	B-215-95	09/13/17	PES	ESC	95	-41.1	S	0.000393 U	0.000254 U	0.000446 U	0.00113 U	0.000274 U	0.000449 U	0.000281 U	0.000314 U	0.000457 U	0.000304 U	0.000853 U	0.000355 U
B-268	B-268-1	03/17/20	PES	PACE	1	–	V	0.00134 U	0.000711 U	0.000558 U	0.00134 U	0.000515 U	0.00172 U	0.000856 U	0.000841 U	0.00124 U	0.000977 U	0.00101 U	0.000657 U
B-269	B-269-1.5	03/17/20	PES	PACE	1.5	–	V	0.00118 U	0.000626 U	0.000491 U	0.00118 U	0.000453 U	0.00152 U	0.000754 U	0.000740 U	0.00109 U	0.000861 U	0.000893 U	**0.00356**
B-270	B-270-2	03/17/20	PES	PACE	2	–	V	0.00131 U	0.000693 U	0.000544 U	0.00131 U	0.000502 U	0.00168 U	0.000835 U	0.000820 U	0.00121 U	0.000953 U	0.000989 U	**0.00163 J**
B-271	B-271-1	03/17/20	PES	PACE	1	–	V	0.00116 U	0.000615 U	0.000483 U	0.00116 U	0.000446 U	0.00149 U	0.000741 U	0.000728 U	0.00107 U	0.000846 U	0.000878 U	0.000569 U
B-272	B-272-1	03/17/20	PES	PACE	1	–	V	0.00127 U	0.000676 U	0.000531 U	0.00127 U	0.000489 U	0.00164 U	0.000814 U	0.000799 U	0.00118 U	0.000929 U	0.000964 U	**0.00311**
	B-272-6	03/17/20	PES	PACE	6	–	V	0.00134 U	0.000709 U	0.000557 U	0.00134 U	0.000514 U	0.00172 U	0.000854 U	0.000839 U	0.00124 U	0.000975 U	0.00101 U	**0.00103 J**
B-273	B-273-1	03/17/20	PES	PACE	1	–	V	0.00121 U	0.000643 U	0.000505 U	0.00121 U	0.000466 U	0.00156 U	0.000774 U	0.000761 U	0.00112 U	0.000884 U	0.000918 U	**0.000897 J**
	B-273-3	03/17/20	PES	PACE	3	–	V	0.00119 U	0.000633 U	0.000497 U	0.00119 U	0.000459 U	0.00154 U	0.000763 U	0.000749 U	0.00111 U	0.000871 U	0.000904 U	**0.000627 J**
	B-273-6	03/17/20	PES	PACE	6	–	V	0.00240 U	0.00127 U	0.000997 U	0.00240 U	0.000920 U	0.00308 U	**0.00271 J**	0.00150 U	0.00222 U	0.00175 U	0.00181 U	**0.00410 J**
B-274	B-274-1	03/17/20	PES	PACE	1	–	V	0.00121 U	0.000644 U	0.000506 U	0.00121 U	0.000467 U	0.00156 U	**0.00215 J**	0.000762 U	0.00112 U	0.000886 U	0.000920 U	**0.00295**
	B-274-3	03/17/20	PES	PACE	3	–	V	0.00117 U	0.000620 U	0.000487 U	0.00117 U	0.000449 U	0.00151 U	0.000747 U	0.000734 U	0.00108 U	0.000853 U	0.000886 U	0.000574 U
	B-274-6	03/17/20	PES	PACE	6	–	V	0.00192 U	0.00102 U	0.000800 U	0.00192 U	0.000738 U	0.00246 U	**0.0270**	0.00121 U	0.00178 U	0.00140 U	0.00146 U	**0.00413 J**
B-275	B-275-1	03/17/20	PES	PACE	1	–	V	0.00127 U	0.000673 U	0.000528 U	0.00127 U	0.000487 U	0.00163 U	0.000810 U	0.000796 U	0.00117 U	0.000925 U	0.000960 U	0.000622 U
	B-275-6	03/17/20	PES	PACE	6	–	V	0.00200 U	0.00106 U	0.000834 U	0.00200 U	0.000768 U	0.00258 U	**0.0732**	0.00125 U	0.00185 U	0.00145 U	0.00151 U	**0.0343**
	B-275-9	03/17/20	PES	PACE	9	–	S	0.00166 U	0.000882 U	0.000692 U	0.00166 U	0.000638 U	0.00214 U	0.00106 U	0.00104 U	0.00154 U	0.00121 U	0.00126 U	**0.00163 J**
	B-275-10	03/17/20	PES	PACE	10	–	S	0.00119 U	0.000630 U	0.000495 U	0.00119 U	0.000456 U	0.00153 U	**0.00123 J**	0.000745 U	0.00110 U	0.000866 U	0.000899 U	0.000583 U
B-276	B-276-1	03/17/20	PES	PACE	1	–	V	0.00199 U	0.00106 U	0.000830 U	0.00199 U	0.000766 U	0.00256 U	0.00127 U	0.00125 U	0.00184 U	0.00146 U	0.00150 U	0.000978 U
	B-276-7	03/17/20	PES	PACE	7	–	V	0.00119 U	0.000634 U	0.000498 U	0.00119 U	0.000459 U	0.00154 U	**0.00751**	0.000750 U	0.00111 U	0.000871 U	0.000905 U	0.000586 U
	B-970-6	03/17/20	PES	PACE	7 (dup)	–	V	0.00120 U	0.000634 U	0.000498 U	0.00120 U	0.000459 U	0.00154 U	**0.00838**	0.000750 U	0.00111 U	0.000872 U	0.000905 U	0.000587 U
	B-276-11	03/17/20	PES	PACE	11	–	S	0.00126 U	0.000669 U	0.000526 U	0.00126 U	0.000485 U	0.00162 U	**0.00834**	0.000792 U	0.00117 U	0.000920 U	0.000955 U	0.000619 U
B-277	B-277-1	03/18/20	PES	PACE	1	–	V	0.00136 U	0.000722 U	0.000567 U	0.00136 U	**0.000971 J**	0.00175 UJ	0.000870 U	0.000855 U	0.00126 U	0.000993 U	0.00103 U	0.000668 U
	B-277-3	03/18/20	PES	PACE	3	–	V	0.00119 U	0.000630 U	0.000495 U	0.00119 U	**0.00107 J**	0.00153 UJ	0.000758 U	0.000745 U	0.00110 U	0.000866 U	0.000899 U	0.000582 U
	B-277-5	03/18/20	PES	PACE	5	–	V	0.00178 U	0.000946 U	0.000743 U	0.00178 U	**0.00107 J**	0.00230 UJ	0.00114 U	0.00112 U	0.00165 U	0.00130 U	0.00135 U	0.000875 U
	B-277-9.5	03/18/20	PES	PACE	9.5	–	V	0.00256 U	0.00136 U	0.00107 U	0.00256 U	**0.0159**	0.00330 UJ	**0.192**	0.00161 U	0.00238 U	0.00187 U	0.00194 U	**0.00517 J**
	B-277-11	03/18/20	PES	PACE	11	–	S	0.00117 U	0.000618 U	0.000486 U	0.00117 U	**0.000690 J**	0.00150 UJ	**0.00615**	0.000732 U	0.00108 U	0.000850 U	0.000883 U	0.000572 U
B-278	B-278-3	03/18/20	PES	PACE	3	–	V	0.00121 U	0.000640 U	0.000502 U	0.00121 U	**0.00107 J**	0.00155 UJ	0.000770 U	0.000757 U	0.00112 U	0.000880 U	0.000913 U	0.000592 U
	B-278-6	03/18/20	PES	PACE	6	–	V	0.00120 U	0.000635 U	0.000499 U	0.00120 U	**0.000823 J**	0.00154 UJ	0.000765 U	0.000752 U	0.00111 U	0.000874 U	0.000907 U	0.000588 U
B-279	B-279-3	03/18/20	PES	PACE	3	–	V	0.00122 U	0.000650 U	0.000510 U	0.00122 U	**0.000845 J**	0.00158 UJ	**0.00101 J**	0.000769 U	0.00113 U	0.000894 U	0.000928 U	0.000601 U
	B-279-5	03/18/20	PES	PACE	5	–	V	0.00121 U	0.000641 U	0.000503 U	0.00121 U	**0.000819 J**	0.00155 UJ	0.000772 U	0.000758 U	0.00112 U	0.000881 U	0.000915 U	0.000593 U
	B-279-10	03/18/20	PES	PACE	10	–	V	0.00117 U	0.000623 U	0.000489 U	0.00117 U	0.000451 U	0.00151 UJ	0.000750 U	0.000737 U	0.00109 U	0.000856 U	0.000889 U	0.000576 U
B-280	B-280-4.5	03/18/20	PES	PACE	4.5	–	V	0.00112 U	0.000593 U	0.000466 U	0.00112 U	0.000430 U	0.00144 UJ	0.000715 U	0.000702 U	0.00104 U	0.000816 U	0.000847 U	0.000549 U
	B-280-6	03/18/20	PES	PACE	6	–	V	0.00118 U	0.000623 U	0.000490 U	0.00118 U	0.000452 U	0.00151 UJ	0.000751 U	0.000738 U	0.00109 U	0.000857 U	0.000890 U	0.000577 U
B-281	B-281-2	03/18/20	PES	PACE	2	–	V	0.00113 U	0.000599 U	0.000470 U	0.00113 U	**0.000784 J**	0.00145 UJ	0.000721 U	0.000709 U	0.00105 U	0.000824 U	0.000855 U	0.000554 U
	B-281-5	03/18/20	PES	PACE	5	–	V	0.00122 U	0.000649 U	0.000510 U	0.00122 U	0.000470 U	0.00158 UJ	0.000782 U	0.000768 U	0.00113 U	0.000893 U	0.000927 U	0.000601 U
B-282	B-282-2	03/18/20	PES	PACE	2	–	V	0.00123 U	0.000653 U	0.000513 U	0.00123 U	0.000473 U	0.00158 UJ	0.000787 U	0.000773 U	0.00114 U	0.000898 U	0.000933 U	0.000604 U
	B-282-4	03/18/20	PES	PACE	4	–	V	0.00119 U	0.000633 U	0.000497 U	0.00119 U	0.000458 U	0.00154 U	0.000762 U	0.000749 U	0.00110 U	0.000870 U	0.000904 U	0.000585 U
	B-971-5	03/18/20	PES	PACE	4 (dup)	–	V	0.00115 U	0.000610 U	0.000479 U	0.00115 U	0.000442 U	0.00148 U	0.000734 U	0.000722 U	0.00106 U	0.000839 U	0.000871 U	0.000564 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
B-283	B-283-0.5	08/19/20	PES	PACE	0.5	–	V	0.00108 U	0.000253 U	0.000736 U	0.00204 U	0.00124 U	0.00523 U	0.000883 U	0.000910 U	0.000902 U	0.000872 U	0.00194 U	**0.000903 J**
B-284	B-284-1	08/19/20	PES	PACE	1	–	V	0.00108 U	0.000252 U	0.000734 U	0.00204 U	0.00124 U	0.00522 U	0.000881 U	0.000908 U	0.000900 U	0.000870 U	0.00193 U	**0.000900 J**
B-285	B-285-1	08/19/20	PES	PACE	1	–	V	0.00118 U	0.000274 U	0.000800 U	0.00222 U	0.00135 U	0.00568 U	0.000959 U	0.000989 U	0.000980 U	0.000947 U	0.00211 U	**0.00268 J**
B-286	B-286-0.5	08/19/20	PES	PACE	0.5	–	V	0.00240 U	0.000558 U	0.00163 U	0.00453 U	0.00273 U	0.0116 U	0.00195 U	0.00201 U	0.00200 U	0.00192 U	0.00428 U	**0.0110**
B-287	B-287-1	08/19/20	PES	PACE	1	–	V	0.00234 U	0.000546 U	0.00159 U	0.00442 U	0.00268 U	0.0113 U	0.00191 U	0.00197 U	0.00195 U	0.00188 U	0.00418 U	**0.00234 J**
B-288	B-288-1	08/19/20	PES	PACE	1	–	V	0.00475 U	0.00111 U	0.00325 U	0.00902 U	0.00546 U	0.0231 U	0.00390 U	0.00401 U	0.00397 U	0.00386 U	0.00854 U	**0.0479**
B-289	B-289-0.5	08/19/20	PES	PACE	0.5	–	V	0.00392 U	0.000917 U	0.00267 U	0.00743 U	0.00449 U	0.0190 U	0.00320 U	0.00331 U	0.00327 U	0.00316 U	0.00703 U	0.00322 U
B-290	B-290-1	08/20/20	PES	PACE	1	–	V	0.00142 U	0.000331 U	0.000966 U	0.00268 U	0.00162 U	0.00687 U	0.00116 U	0.00119 U	0.00118 U	0.00115 U	0.00254 U	**0.00860**
B-291	B-291-1	08/20/20	PES	PACE	1	–	V	0.00121 U	0.000284 U	0.000830 U	0.00230 U	0.00140 U	0.00590 U	0.000995 U	0.00103 U	0.00102 U	0.000983 U	0.00218 U	**0.00268 J**
B-292	B-292-3	08/22/20	PES	PACE	3	–	V	0.00113 U	0.000264 U	0.000770 U	0.00214 U	0.00130 U	0.00547 U	0.000924 U	0.000953 U	0.000944 U	0.000912 U	0.00203 U	0.000927 U
	B-292-6	08/22/20	PES	PACE	6	–	V	0.00117 U	0.000273 U	0.000796 U	0.00221 U	0.00134 U	0.00566 U	0.000954 U	0.000984 U	0.000975 U	0.000943 U	0.00209 U	0.000958 U
	B-292-9	08/22/20	PES	PACE	9	–	V	0.00106 U	0.000248 U	0.000723 U	0.00201 U	0.00122 U	0.00514 U	0.000867 U	0.000895 U	0.000886 U	0.000857 U	0.00190 U	0.000871 U
	B-292-12	08/22/20	PES	PACE	12	–	V	0.00118 U	0.000276 U	0.000803 U	0.00223 U	0.00135 U	0.00571 U	0.000963 U	0.000994 U	0.000984 U	0.000952 U	0.00211 U	0.000967 U
B-293	B-293-1	08/26/20	PES	PACE	1	–	V	0.000995 UJ	0.000233 U	0.000678 U	0.00188 UJ	0.00114 UJ	0.00482 UJ	0.000814 U	0.000839 U	0.000831 U	0.000804 U	0.00178 U	0.000817 U
B-294	B-294-1	08/26/20	PES	PACE	1	–	V	0.00126 UJ	0.000295 U	0.000859 U	0.00239 UJ	0.00145 UJ	0.00611 UJ	0.00103 U	0.00106 U	0.00105 U	0.00102 U	0.00226 U	**0.00438**
	B-294-2	08/26/20	PES	PACE	2	–	V	0.00261 UJ	0.000611 U	0.00178 U	0.00495 UJ	0.00299 UJ	0.0126 UJ	0.00213 U	0.00220 U	0.00218 U	0.00211 U	0.00468 U	**0.0277**
	B-294-6	08/26/20	PES	PACE	6	–	V	0.00256 UJ	0.000600 U	0.00175 U	0.00486 UJ	0.00294 UJ	0.0124 UJ	0.00209 U	0.00215 U	0.00215 U	0.00207 U	0.00459 U	**0.00250 J**
	B-294-10	08/26/20	PES	PACE	10	–	S	0.00121 UJ	0.000283 U	0.000824 U	0.00229 UJ	0.00139 UJ	0.00585 UJ	0.000988 U	0.00102 U	0.00101 U	0.000976 U	0.00217 U	0.000992 U
B-295	B-295-1	08/26/20	PES	PACE	1	–	V	0.00108 UJ	0.000253 U	0.000737 U	0.00205 UJ	0.00124 UJ	0.00524 UJ	0.000883 U	0.000911 U	0.000903 U	0.000873 U	0.00194 U	0.000887 U
	B-295-3	08/26/20	PES	PACE	3	–	V	0.00160 UJ	0.000375 U	0.00109 U	0.00303 UJ	0.00184 UJ	0.00776 UJ	0.00131 U	0.00135 U	0.00134 U	0.00129 U	0.00287 U	0.00131 U
	B-295-7	08/26/20	PES	PACE	7	–	V	0.00135 UJ	0.000315 U	0.000917 U	0.00255 UJ	0.00154 UJ	0.00652 UJ	0.00110 U	0.00113 U	0.00112 U	0.00109 U	0.00241 U	0.00110 U
	B-295-10	08/26/20	PES	PACE	10	–	S	0.00126 UJ	0.000295 U	0.000860 U	0.00239 UJ	0.00145 UJ	0.00611 UJ	**0.00423**	0.00106 U	0.00105 U	0.00102 U	0.00226 U	0.00104 U
B-296	B-296-1	08/26/20	PES	PACE	1	–	V	0.00102 UJ	0.000239 U	0.000695 U	0.00193 UJ	0.00117 UJ	0.00494 UJ	0.000834 U	0.000860 U	0.000852 U	0.000824 U	0.00183 U	0.000837 U
B-297	B-297-1	08/26/20	PES	PACE	1	–	V	0.00111 UJ	0.000259 U	0.000754 U	0.00209 UJ	0.00127 UJ	0.00536 UJ	0.000904 U	0.000933 U	0.000924 U	0.000893 U	0.00198 U	0.000908 U
	B-297-3	08/26/20	PES	PACE	3	–	V	0.00103 UJ	0.000241 U	0.000703 U	0.00195 UJ	0.00118 UJ	0.00500 UJ	0.000843 U	0.000870 U	0.000862 U	0.000833 U	0.00185 U	0.000847 U
	B-500-1	08/26/20	PES	PACE	3 (dup)	–	V	0.00105 U	0.000246 U	0.000717 U	0.00199 U	0.00121 U	0.00510 U	0.000860 U	0.000887 U	0.000879 U	0.000850 U	0.00189 U	0.000864 U
	B-297-5	08/26/20	PES	PACE	5	–	V	0.00103 U	0.000240 U	0.000699 U	0.00194 U	0.00118 U	0.00497 U	0.000839 U	0.000865 U	0.000857 U	0.000828 U	0.00184 U	0.000842 U
B-298	B-298-5	08/26/20	PES	PACE	5	–	V	0.000948 U	0.000222 U	0.000646 U	0.00180 U	0.00109 U	0.00459 U	0.000774 U	0.000799 U	0.000791 U	0.000765 U	0.00170 U	0.000777 U
	B-298-6	08/26/20	PES	PACE	6	–	V	0.00114 U	0.000267 U	0.000776 U	0.00216 U	0.00131 U	0.00552 U	0.000931 U	0.000960 U	0.000952 U	0.000921 U	0.00204 U	**0.00898**
B-299	B-299-2	02/01/21	PES	PACE	2	–	V	0.00119 U	0.000277 U	0.000808 U	0.00224 U	0.00136 U	0.00574 U	0.000969 U	0.000999 U	0.000990 U	0.000957 U	0.00213 U	0.000973 U
	B-299-5.5	02/01/21	PES	PACE	5.5	–	V	0.00107 U	0.000250 U	0.000729 U	0.00203 U	0.00123 U	0.00518 U	0.000875 U	0.000902 U	0.000894 U	0.000864 U	0.00192 U	0.000878 U
	B-1003-10	02/01/21	PES	PACE	5.5 (dup)	–	V	0.00111 U	0.000260 U	0.000759 U	0.00211 U	0.00128 U	0.00539 U	0.000910 U	0.000938 U	0.000930 U	0.000899 U	0.00200 U	0.000913 U
B-300	B-300-2.5	02/01/21	PES	PACE	2.5	–	V	0.00119 U	0.000278 U	0.000809 U	0.00225 U	0.00136 U	0.00575 U	0.000970 U	0.00100 U	0.000991 U	0.000958 U	0.00213 U	0.000974 U
	B-300-5.5	02/01/21	PES	PACE	5.5	–	V	0.00116 U	0.000271 U	0.000789 U	0.00219 U	0.00133 U	0.00561 U	0.000947 U	0.000976 U	0.000967 U	0.000935 U	0.00208 U	0.000951 U
B-301	B-301-2	02/01/21	PES	PACE	2	–	V	0.00115 U	0.000269 U	0.000785 U	0.00218 U	0.00132 U	0.00558 U	0.000941 U	0.000971 U	0.000962 U	0.000930 U	0.00207 U	0.000945 U
	B-301-5	02/01/21	PES	PACE	5	–	V	0.00121 U	0.000284 U	0.000827 U	0.00230 U	0.00139 U	0.00588 U	0.000992 U	0.00102 U	0.00101 U	0.000980 U	0.00218 U	0.000996 U
B-302	B-302-2	02/01/21	PES	PACE	2	–	V	0.00112 U	0.000263 U	0.000766 U	0.00213 U	0.00129 U	0.00544 U	0.000919 U	0.000947 U	0.000939 U	0.000907 U	0.00202 U	0.000922 U
	B-302-4	02/01/21	PES	PACE	4	–	V	0.00128 U	0.000300 U	0.000873 U	0.00243 U	0.00147 U	0.00621 U	0.00105 U	0.00108 U	0.00107 U	0.00103 U	0.00230 U	0.00105 U
BB-5	S-6	03/09/97	B&V	Unknown	15-17	34.0	V	–	–	–	–	–	–	–	–	–	–	–	ND
	S-10	03/09/97	B&V	Unknown	25-27	24.0	S	–	–	–	–	–	–	–	–	–	–	–	–
BB-7	S-4	04/06/97	B&V	Unknown	10-12	17.0	S	–	–	–	–	–	–	–	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
BB-8 (13.6 to 3.6)	S-8	06/06/97	B&V	Unknown	20-22	23.6	S	–	–	–	–	–	–	ND	–	–	–	–	ND
BB-10	S-6	08/29/97	B&V	Unknown	15-17	42.0	V	–	–	–	–	–	–	–	–	–	–	–	–
BB-12	S-3	03/18/98	B&V	Unknown	15-16.5	18.8	S	–	–	–	–	–	–	ND	–	–	–	–	ND
	S-14	03/18/98	B&V	Unknown	45-46.5	-11.2	S	–	–	–	–	–	–	ND	–	–	–	–	ND
BB-13	S-10	03/19/98	B&V	Unknown	25-27.5	1.9	S	–	–	–	–	–	–	ND	–	–	–	–	ND
	S-16	03/19/98	B&V	Unknown	40-41.5	-13.1	S	–	–	–	–	–	–	ND	–	–	–	–	ND
BB-14	S-2	03/03/98	B&V	Unknown	5-6.5	21.3	V	–	–	–	–	–	–	–	–	–	–	–	–
	S-5	03/03/98	B&V	Unknown	12.5-14	14.3	S	–	–	–	–	–	–	–	–	–	–	–	–
	S-9	03/03/98	B&V	Unknown	22.5-24	4.3	S	–	–	–	–	–	–	–	–	–	–	–	–
	S-12	03/03/98	B&V	Unknown	30-31.5	-4.3	S	–	–	–	–	–	–	–	–	–	–	–	–
CHB-07	CHB-07-12.5-13.5	04/14/05	CH2M	ARI	12.5-13.5	16.5	S	–	–	–	–	–	–	**1.1**	–	–	–	–	0.0011 U
	CHB-07-5.0-7.0	04/14/08	CH2M	ARI	5-7	23.5	S	–	–	–	–	–	–	–	–	–	–	–	–
CHB-08	CHB-08-15.0-16.0	04/15/08	CH2M	ARI	15-16	14.1	S	–	–	–	–	–	–	0.0008 U	–	–	–	–	0.0008 U
CHB-09	CHB-09-20.0-21.5	04/16/08	CH2M	ARI	20-21.5	15.4	S	–	–	–	–	–	–	–	–	–	–	–	–
	CHB-09-25.0-26.5	04/16/08	CH2M	ARI	25-26.5	10.4	S	–	–	–	–	–	–	0.0012 U	–	–	–	–	0.0012 U
GEI-MW-1 (-9.7 to -29.7)	MW-1-1-2.5	08/22/14	GEI	Fremont	1	29.5	V	–	–	–	–	–	–	0.0181 U	–	–	–	–	0.0271 U
GEI-MW-2 (4.0 to -6.0)	MW-2-2-5.0	08/23/14	GEI	Fremont	5	26.6	V	–	–	–	–	–	–	0.0391 U	–	–	–	–	0.0587 U
	MW-2-4-10.0	08/23/14	GEI	Fremont	10	21.6	S	–	–	–	–	–	–	–	–	–	–	–	–
	MW-2-8-20.0	08/23/14	GEI	Fremont	20	11.6	S	–	–	–	–	–	–	–	–	–	–	–	–
GEI-MW-3 (-18.7 to -28.7)	MW-3-4-10.0	08/23/14	GEI	Fremont	10	20.8	S	–	–	–	–	–	–	0.0258 U	–	–	–	–	0.0388 U
	MW-3-10-50.0	08/23/14	GEI	Fremont	50	-19.3	S	–	–	–	–	–	–	0.0166 U	–	–	–	–	0.0249 U
GEI-4	GEI-4-2-5.0	08/23/14	GEI	Fremont	5	26.0	V	–	–	–	–	–	–	0.0214 U	–	–	–	–	0.0321 U
	GEI-4-5-12.5	08/23/14	GEI	Fremont	12.5	18.5	S	–	–	–	–	–	–	0.0243 U	–	–	–	–	0.0365 U
MW-1 (SCLB-3)	RS3-2.5	03/15/93	EPJ	OnSite	2.5	37.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS3-7.5	03/15/93	EPJ	OnSite	7.5	32.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS3-17.5	03/15/93	EPJ	OnSite	17.5	22.5	S	–	–	–	–	–	–	–	–	–	–	–	**3.7**
	RS3-22.5/RS3-27.5 (Comp)	03/15/93	EPJ	OnSite	22.5-27.5	–	S	–	–	–	–	–	–	–	–	–	–	–	**0.76**
	RS3-32.5	03/15/93	EPJ	OnSite	32.5	7.5	S	–	–	–	–	–	–	–	–	–	–	–	0.050 U
	RS3-37.5	03/15/93	EPJ	OnSite	37.5	2.5	S	–	–	–	–	–	–	–	–	–	–	–	0.050 U
MW-2 (SCLB-4)	RS4-2.5	03/15/93	EPJ	OnSite	2.5	37.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS4-7.5	03/15/93	EPJ	OnSite	7.5	32.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS4-12.5/RS4-17.5	03/15/93	EPJ	OnSite	12.5-17.5	–	S	–	–	–	–	–	–	–	–	–	–	–	0.05 U
	RS4-22.5/RS4-27.5 (Comp)	03/15/93	EPJ	OnSite	22.5-27.5	–	S	–	–	–	–	–	–	–	–	–	–	–	0.05 U
	RS4-37.5	03/15/93	EPJ	OnSite	37.5	2.5	S	–	–	–	–	–	–	–	–	–	–	–	0.05 U
MW-3 (SCLB-5)	RS5-2.5/RS5-7.5 (Comp)	03/16/93	EPJ	OnSite	2.5-7.5	–	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS5-12.5/RS5-17.5 (Comp)	03/16/93	EPJ	OnSite	12.5-17.5	–	S	–	–	–	–	–	–	–	–	–	–	–	**0.97**
	RS5-17.5	03/16/93	EPJ	OnSite	17.5	21.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	RS5-22.5	03/16/93	EPJ	OnSite	22.5	16.5	S	–	–	–	–	–	–	–	–	–	–	–	**0.33**
	RS5-32.5	03/16/93	EPJ	OnSite	32.5	6.5	S	–	–	–	–	–	–	–	–	–	–	–	**0.061**
	RS5-37.5	03/16/93	EPJ	OnSite	37.5	1.5	S	–	–	–	–	–	–	–	–	–	–	–	0.050 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	**–**	**0.074**	**–**	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	**–**	**0.007**	**–**	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
MW-4 (SCLB-6)	RS6-2.5	03/17/93	EPJ	OnSite	2.5	37.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS6-7.5	03/17/93	EPJ	OnSite	7.5	32.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS6-12.5	03/17/93	EPJ	OnSite	12.5	27.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS6-17.5/RS6-22.5 (Comp)	03/17/93	EPJ	OnSite	17.5-22.5	–	V	–	–	–	–	–	–	–	–	–	–	–	0.050 U
	RS6-27.5	03/17/93	EPJ	OnSite	27.5	12.5	S	–	–	–	–	–	–	–	–	–	–	–	0.050 U
MW-5 (SCLB-7)	RS7-2.5	03/17/93	EPJ	OnSite	2.5	37.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS7-7.5	03/17/93	EPJ	OnSite	7.5	32.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS7-12.5	03/17/93	EPJ	OnSite	12.5	27.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS7-17.5	03/17/93	EPJ	OnSite	17.5	22.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	RS7-22.5	03/17/93	EPJ	OnSite	22.5	17.5	S	–	–	–	–	–	–	–	–	–	–	–	–
MW-6	MW6-25	10/11/93	Retec	ARI	25	13.2	S	–	–	–	–	–	–	–	–	–	–	–	**0.44**
MW-7	MW7-16.5	10/11/93	Retec	ARI	16.5	18.6	S	–	–	–	–	–	–	–	–	–	–	–	**54**
	MW7-18.5	10/11/93	Retec	ARI	18.5	16.6	S	–	–	–	–	–	–	–	–	–	–	–	**12**
MW-8 (28.7 to 14.2)	MW8-20	10/18/93	Retec	AAL	20	13.2	S	–	–	–	–	–	–	–	–	–	–	–	0.059 U
MW-9 (33.7 to 18.7)	MW9-17.5	10/18/93	Retec	AAL	17.5	23.6	S	–	–	–	–	–	–	–	–	–	–	–	0.068 U
MW-10	MW10-17.5	10/19/93	Retec	AAL	17.5	20.5	S	–	–	–	–	–	–	–	–	–	–	–	0.068 U
MW102 (B102) (-65.8 to -75.8)	B102-20	07/17/12	SES	F&BI	20	29.2	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B102-30	07/17/12	SES	F&BI	30	19.2	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B102-38	07/17/12	SES	F&BI	38	11.2	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B102-40	07/17/12	SES	F&BI	40	9.2	S	–	–	–	–	–	–	–	–	–	–	–	–
	B102-49	07/17/12	SES	F&BI	49	0.2	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B102-60	07/17/12	SES	F&BI	60	-10.8	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B102-70	07/18/12	SES	F&BI	70	-20.8	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B102-80	07/19/12	SES	F&BI	80	-30.8	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B102-90	07/19/12	SES	F&BI	90	-40.8	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B102-100	07/20/12	SES	F&BI	100	-50.8	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B102-110	07/20/12	SES	F&BI	110	-60.8	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B102-120	07/23/12	SES	F&BI	120	-70.8	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
MW103 (B103) (-67.6 to -77.6)	B103-10	07/25/12	SES	F&BI	10	25.9	V	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B103-18	07/25/12	SES	F&BI	18	17.9	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B103-30	07/25/12	SES	F&BI	30	5.9	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B103-40	07/25/12	SES	F&BI	40	-4.1	S	–	–	–	–	–	–	**0.12**	–	–	–	–	–
	B103-45	07/25/12	SES	F&BI	45	-9.1	S	–	–	–	–	–	–	**0.24**	–	–	–	–	–
	B103-55	07/25/12	SES	F&BI	55	-19.1	S	–	–	–	–	–	–	**0.18**	–	–	–	–	–
	B103-62.5	07/26/12	SES	F&BI	62.5	-26.6	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B103-75	07/26/12	SES	F&BI	75	-39.1	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B103-83	07/26/12	SES	F&BI	83	-47.1	S	–	–	–	–	–	–	**0.12**	–	–	–	–	–
	B103-95	07/26/12	SES	F&BI	95	-59.1	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B103-105	07/27/12	SES	F&BI	105	-69.1	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B103-113	07/27/12	SES	F&BI	113	-77.1	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
MW104 (B104) (-76.3 to -86.3)	B104-10	07/30/12	SES	F&BI	10	32.7	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B104-20	07/30/12	SES	F&BI	20	22.7	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B104-30	07/30/12	SES	F&BI	30	12.7	S	–	–	–	–	–	–	**0.14**	–	–	–	–	–
	B104-35	07/30/12	SES	F&BI	35	7.7	S	–	–	–	–	–	–	**0.099**	–	–	–	–	–
	B104-50	07/30/12	SES	F&BI	50	-7.3	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B104-60	07/31/12	SES	F&BI	60	-17.3	S	–	–	–	–	–	–	**0.12**	–	–	–	–	–
	B104-69	07/31/12	SES	F&BI	69	-26.3	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B104-80	07/31/12	SES	F&BI	80	-37.3	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B104-90	08/01/12	SES	F&BI	90	-47.3	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B104-100	08/01/12	SES	F&BI	100	-57.3	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B104-110	08/01/12	SES	F&BI	110	-67.3	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B104-120	08/01/12	SES	F&BI	120	-77.3	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B104-130	08/01/12	SES	F&BI	130	-87.3	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
MW105 (B105) (-85.8 to -95.8)	B105-10	08/06/12	SES	F&BI	10	34.2	V	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B105-20	08/06/12	SES	F&BI	20	24.2	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B105-30	08/06/12	SES	F&BI	30	14.2	S	–	–	–	–	–	–	**0.086**	–	–	–	–	–
	B105-40	08/08/12	SES	F&BI	40	4.2	S	–	–	–	–	–	–	**0.22**	–	–	–	–	–
	B105-50	08/08/12	SES	F&BI	50	-5.8	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B105-60	08/09/12	SES	F&BI	60	-15.8	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B105-70	08/09/12	SES	F&BI	70	-25.8	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B105-80	08/09/12	SES	F&BI	80	-35.8	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B105-90	08/10/12	SES	F&BI	90	-45.8	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B105-100	08/10/12	SES	F&BI	100	-55.8	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B105-110	08/10/12	SES	F&BI	110	-65.8	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B105-120	08/10/12	SES	F&BI	120	-75.8	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B105-130	08/10/12	SES	F&BI	130	-85.8	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B105-138	08/10/12	SES	F&BI	138	-93.8	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
MW106 (B106) (-78.0 to -88.0)	B106-10	08/14/12	SES	F&BI	10	42.0	V	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B106-20	08/14/12	SES	F&BI	20	32.0	V	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B106-30	08/14/12	SES	F&BI	30	22.0	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B106-40	08/14/12	SES	F&BI	40	12.0	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B106-50	08/14/12	SES	F&BI	50	2.0	S	–	–	–	–	–	–	**0.11**	–	–	–	–	–
	B106-60	08/14/12	SES	F&BI	60	-8.0	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B106-70	08/15/12	SES	F&BI	70	-18.0	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B106-80	08/15/12	SES	F&BI	80	-28.0	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B106-90	08/15/12	SES	F&BI	90	-38.0	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B106-100	08/15/12	SES	F&BI	100	-48.0	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B106-110	08/15/12	SES	F&BI	110	-58.0	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B106-120	08/15/12	SES	F&BI	120	-68.0	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B106-130	08/15/12	SES	F&BI	130	-78.0	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B106-140	08/15/12	SES	F&BI	140	-88.0	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
MW107 (B107) (8.8 to -1.2)	B107-05	03/12/12	SES	F&BI	5	38.8	V	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
	B107-15	03/12/12	SES	F&BI	15	28.8	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
	B107-25	03/12/12	SES	F&BI	25	18.8	S	–	–	–	–	–	–	**0.060**	–	–	–	–	0.05 U
	B107-35	03/12/12	SES	F&BI	35	8.8	S	–	–	–	–	–	–	**0.37**	–	–	–	–	0.05 U
	B107-45	03/12/12	SES	F&BI	45	-1.2	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
MW108 (B108) (-7.2 to -17.2)	B108-15	12/14/12	SES	F&BI	15	17.8	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B108-25	12/14/12	SES	F&BI	25	7.8	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B108-35	12/14/12	SES	F&BI	35	-2.2	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B108-45	12/14/12	SES	F&BI	45	-12.2	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B108-50	12/14/12	SES	F&BI	50	-17.2	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
MW109 (B109) (0.0 to -10.0)	B109-05	04/12/12	SES	F&BI	5	30.0	V	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B109-15	04/12/12	SES	F&BI	15	20.0	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B109-25	04/12/12	SES	F&BI	25	10.0	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B109-35	04/12/12	SES	F&BI	35	0.0	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B109-45	04/12/12	SES	F&BI	45	-10.0	S	–	–	–	–	–	–	**0.15**	–	–	–	–	–
MW110 (B110) (4.7 to -5.3)	B110-15	04/12/12	SES	F&BI	15	24.7	V	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B110-25	04/12/12	SES	F&BI	25	14.7	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B110-35	04/12/12	SES	F&BI	35	4.7	S	–	–	–	–	–	–	**0.31**	–	–	–	–	–
	B110-45	04/12/12	SES	F&BI	45	-5.3	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
MW111 (B111) (-33.5 to -43.5)	B111-10	05/12/12	SES	F&BI	10	26.5	V	–	–	–	–	–	–	0.1 U	–	–	–	–	–
	B111-20	05/12/12	SES	F&BI	20	16.5	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B111-30	05/12/12	SES	F&BI	30	6.5	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B111-38	05/12/12	SES	F&BI	38	-1.5	S	–	–	–	–	–	–	**0.28**	–	–	–	–	–
	B111-50	05/12/12	SES	F&BI	50	-13.5	S	–	–	–	–	–	–	**0.11**	–	–	–	–	–
	B111-60	06/12/12	SES	F&BI	60	-23.5	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B111-70	06/12/12	SES	F&BI	70	-33.5	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B111-80	06/12/12	SES	F&BI	80	-43.5	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
MW112 (B112) (-17.5 to -27.5)	B112-10	11/12/12	SES	F&BI	10	47.5	V	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B112-20	11/12/12	SES	F&BI	20	37.5	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B112-30	11/12/12	SES	F&BI	30	27.5	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B112-40	11/12/12	SES	F&BI	40	17.5	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B112-50	11/12/12	SES	F&BI	50	7.5	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B112-60	11/12/12	SES	F&BI	60	-2.5	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B112-75	11/12/12	SES	F&BI	75	-17.5	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B112-85	12/12/12	SES	F&BI	85	-27.5	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
MW113 (B113) (-37.1 to -47.1)	B113-10	12/18/12	SES	F&BI	10	22.9	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B113-20	12/18/12	SES	F&BI	20	12.9	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B113-30	12/18/12	SES	F&BI	30	2.9	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B113-40	12/18/12	SES	F&BI	40	-7.1	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B113-50	12/18/12	SES	F&BI	50	-17.1	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
MW114 (B114) (10.8 to 0.8)	B114-15	10/12/12	SES	F&BI	15	30.8	V	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B114-25	10/12/12	SES	F&BI	25	20.8	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B114-35	10/12/12	SES	F&BI	35	10.8	S	–	–	–	–	–	–	**0.11**	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	**–**	**0.074**	**–**	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	**–**	**0.007**	**–**	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
MW114 (B114)	B114-40	10/12/12	SES	F&BI	40	5.8	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
(continued)	B114-45	10/12/12	SES	F&BI	45	0.8	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
MW115 (B115)	B115-10	12/13/12	SES	F&BI	10	24.1	V	–	–	–	–	–	–	0.05 U	–	–	–	–	–
(-0.9 to -10.9)	B115-15	12/13/12	SES	F&BI	15	19.1	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B115-25	12/13/12	SES	F&BI	25	9.1	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B115-35	12/13/12	SES	F&BI	35	-0.9	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B115-45	12/13/12	SES	F&BI	45	-10.9	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
MW116 (B116)	B116-15	07/12/12	SES	F&BI	15	16.4	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
(-3.6 to -13.6)	B116-25	07/12/12	SES	F&BI	25	6.4	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B116-35	07/12/12	SES	F&BI	35	-3.6	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B116-45	07/12/12	SES	F&BI	45	-13.6	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
MW117 (B117)	B117-10	02/04/13	SES	F&BI	10	46.9	V	–	–	–	–	–	–	0.05 U	–	–	–	–	–
(16.9 to 1.9)	B117-20	02/04/13	SES	F&BI	20	36.9	V	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B117-30	02/04/13	SES	F&BI	30	26.9	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B117-40	02/04/13	SES	F&BI	40	16.9	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B117-50	02/04/13	SES	F&BI	50	6.9	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
MW118 (B118)	B118-10	03/21/13	SES	F&BI	10	42.9	V	–	–	–	–	–	–	0.05 U	–	–	–	–	–
(12.9 to 2.9)	B118-20	03/21/13	SES	F&BI	20	32.9	V	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B118-30	03/21/13	SES	F&BI	30	22.9	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B118-40	03/21/13	SES	F&BI	40	12.9	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B118-50	03/21/13	SES	F&BI	50	2.9	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
MW119 (B119)	B119-10	03/21/13	SES	F&BI	10	27.4	V	–	–	–	–	–	–	0.05 U	–	–	–	–	–
(2.4 to -7.7)	B119-20	03/21/13	SES	F&BI	20	17.4	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B119-30	03/21/13	SES	F&BI	30	7.4	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
	B119-40	03/21/13	SES	F&BI	40	-2.7	S	–	–	–	–	–	–	0.05 U	–	–	–	–	–
MW120 (B120)	B120-20	12/16/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
(0 to -10)	B120-30	12/16/13	SES	F&BI	30	10.0	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
	B120-45	12/16/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
MW121 (B121)	B121-15	12/16/13	SES	F&BI	15	26.7	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
(26.7 to 16.7)	B121-25	12/16/13	SES	F&BI	25	16.7	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
MW122 (B122)	B122-15	12/17/13	SES	F&BI	15	15.0	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
(-75 to -89)	B122-25	12/17/13	SES	F&BI	25	5.0	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
	B122-40	12/17/13	SES	F&BI	40	-10.0	S	–	–	–	–	–	–	**0.22**	–	–	–	–	0.05 U
	B122-45	12/17/13	SES	F&BI	45	-15.0	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
	B122-50	12/17/13	SES	F&BI	50	-20.0	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
	B122-60	12/17/13	SES	F&BI	60	-30.0	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
	B122-70	12/17/13	SES	F&BI	70	-40.0	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
	B122-80	12/17/13	SES	F&BI	80	-50.0	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
	B122-100	12/17/13	SES	F&BI	100	-70.0	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
MW123 (B123)	B123-20	12/18/13	SES	F&BI	20	7.5	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
(-42.5 to -52.5)																			

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
MW124 (B124)	B124-10	12/19/13	SES	F&BI	10	46.2	V	–	–	–	–	–	–	–	–	–	–	–	–
(-53.8 to -63.8)	B124-20	12/19/13	SES	F&BI	20	36.2	V	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
	B124-30	12/19/13	SES	F&BI	30	26.2	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
	B124-40	12/19/13	SES	F&BI	40	16.2	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
	B124-50	12/19/13	SES	F&BI	50	6.2	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
	B124-60	12/19/13	SES	F&BI	60	-3.8	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
	B124-70	12/19/13	SES	F&BI	70	-13.8	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
	B124-80	12/19/13	SES	F&BI	80	-23.8	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
	B124-90	12/19/13	SES	F&BI	90	-33.8	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
	B124-100	12/19/13	SES	F&BI	100	-43.8	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
	B124-110	12/19/13	SES	F&BI	110	-53.8	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
	B124-120	12/19/13	SES	F&BI	120	-63.8	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
MW125 (B125)	B125-15	12/20/13	SES	F&BI	15	28.6	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
(28.6 to 13.6)	B125-20	12/20/13	SES	F&BI	20	23.6	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
	B125-25	12/20/13	SES	F&BI	25	18.6	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
	B125-30	12/20/13	SES	F&BI	30	13.6	S	–	–	–	–	–	–	–	–	–	–	–	–
MW126 (B126)	B126-20	12/30/13	SES	F&BI	20	10.9	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
(-54.1 to -64.1)	B126-35	12/30/13	SES	F&BI	35	-4.1	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
	B126-45	12/30/13	SES	F&BI	45	-14.1	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
	B126-55	12/30/13	SES	F&BI	55	-24.1	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
	B126-60	12/31/13	SES	F&BI	60	-29.1	S	–	–	–	–	–	–	–	–	–	–	–	–
	B126-65	01/01/14	SES	F&BI	65	-34.1	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
	B126-75	01/02/14	SES	F&BI	75	-44.1	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
	B126-80	01/03/14	SES	F&BI	80	-49.1	S	–	–	–	–	–	–	–	–	–	–	–	–
	B126-85	01/04/14	SES	F&BI	85	-54.1	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
	B126-95	01/05/14	SES	F&BI	95	-64.1	S	–	–	–	–	–	–	–	–	–	–	–	–
MW127 (B127)	B127-15	12/31/13	SES	F&BI	15	24.0	V	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
(-1.0 to -11.0)	B127-25	12/31/13	SES	F&BI	25	14.0	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
	B127-40	12/31/13	SES	F&BI	40	-1.0	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
	B127-45	12/31/13	SES	F&BI	45	-6.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B127-50	12/31/13	SES	F&BI	50	-11.0	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
MW128 (B128)	B128-25	01/09/14	SES	F&BI	25	2.9	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
(-30.8 to -40.8)	B128-45	01/09/14	SES	F&BI	45	-17.1	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
	B128-65	01/09/14	SES	F&BI	65	-37.1	S	–	–	–	–	–	–	0.05 U	–	–	–	–	0.05 U
MW-138	MW-138-15	09/12/17	PES	ESC	15	42.5	V	0.000390 U	0.000252 U	0.000443 U	0.00112 U	0.000272 U	0.000446 U	0.000279 U	0.000311 U	0.000454 U	0.000302 U	0.000848 U	0.000353 U
(-47.5 to -57.5)	MW-138-25	09/12/17	PES	ESC	25	32.5	S	0.000378 U	0.000244 U	0.000429 U	0.00109 U	0.000264 U	0.000432 U	0.000271 U	0.000302 U	0.000440 U	0.000292 U	0.000821 U	0.000342 U
	MW-138-35	09/12/17	PES	ESC	35	22.5	S	0.000350 U	0.000227 U	0.000399 U	0.00101 U	0.000245 U	0.000401 U	0.000251 U	0.000280 U	0.000408 U	0.000271 U	0.000762 U	0.000317 U
	MW-138-45	09/12/17	PES	ESC	45	12.5	S	0.000347 U	0.000224 U	0.000394 U	0.00100 U	0.000242 U	0.000396 U	0.000248 U	0.000277 U	0.000404 U	0.000268 U	0.000754 U	0.000314 U
	MW-138-56	09/12/17	PES	ESC	56	1.5	S	0.000369 U	0.000238 U	0.000420 U	0.00106 U	0.000258 U	**0.00179 J**	0.000264 U	0.000295 U	0.000430 U	0.000286 U	0.000802 U	0.000334 U
	MW-138-65	09/13/17	PES	ESC	65	-7.5	S	0.000355 U	0.000229 U	0.000403 U	0.00102 U	0.000248 U	0.000406 U	0.000254 U	0.000283 U	0.000413 U	0.000275 U	0.000771 U	0.000321 U
	B-910-90	09/13/17	PES	ESC	65 (dup)	-7.5	S	0.000380 U	0.000246 U	0.000432 U	0.00110 U	0.000265 U	0.000435 U	0.000272 U	0.000304 U	0.000443 U	0.000294 U	0.000826 U	0.000344 U
	MW-138-75	09/13/17	PES	ESC	75	-17.5	S	0.000361 U	0.000233 U	0.000411 U	0.00104 U	0.000252 U	0.000413 U	0.000259 U	0.000289 U	0.000421 U	0.000280 U	0.000785 U	0.000327 U
	MW-138-85	09/13/17	PES	ESC	85	-27.5	S	0.000394 U	0.000255 U	0.000448 U	0.00114 U	0.000275 U	0.000451 U	0.000283 U	0.000315 U	0.000459 U	0.000305 U	0.000857 U	0.000357 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
MW-138 (continued)	MW-138-95	09/13/17	PES	ESC	95	-37.5	S	0.000358 U	0.000231 U	0.000407 U	0.00103 U	0.000250 U	0.000409 U	0.000256 U	0.000286 U	0.000417 U	0.000277 U	0.000778 U	0.000324 U
	MW-138-105	09/13/17	PES	ESC	105	-47.5	S	0.000408 U	0.000264 U	0.000464 U	0.00118 U	0.000285 U	0.000466 U	0.000292 U	0.000326 U	0.000475 U	0.000316 U	0.000887 U	0.000369 U
	MW-138-115	09/14/17	PES	ESC	115	-57.5	S	0.000380 U	0.000246 U	0.000432 U	0.00110 U	0.000265 U	0.000434 U	0.000272 U	0.000303 U	0.000443 U	0.000294 U	0.000826 U	0.000344 U
MW-140 (-78.9 to -88.9)	MW-140-15	08/30/17	PES	ESC	15	35.6	V	0.000374 U	0.000242 U	0.000425 U	0.00108 U	0.000261 U	0.000428 U	0.000268 U	0.000299 U	0.000436 U	0.000290 U	0.000813 U	0.000339 U
	MW-140-25	08/30/17	PES	ESC	25	25.6	S	0.000356 U	0.000230 U	0.000405 U	0.00103 U	0.000248 U	0.000407 U	**0.00199**	0.000284 U	0.000414 U	0.000275 U	0.000773 U	0.000322 U
	MW-140-35	08/30/17	PES	ESC	35	15.6	S	0.00955 U	0.00618 U	0.0109 U	0.0275 U	0.00666 U	0.0109 U	**0.387**	0.00763 U	0.0111 U	0.00740 U	0.0207 U	0.00865 U
	MW-140-45	08/30/17	PES	ESC	45	5.6	S	0.000350 U	0.000226 U	0.000398 U	0.00101 U	0.000244 U	0.000400 U	**0.0431**	0.000280 U	0.000408 U	0.000271 U	0.000761 U	0.000317 U
	MW-140-55	08/30/17	PES	ESC	55	-4.4	S	0.000360 U	0.000233 U	0.000409 U	0.00104 U	0.000251 U	0.000412 U	**0.130**	0.000288 U	0.000419 U	0.000279 U	0.000782 U	0.000326 U
	MW-140-65	08/30/17	PES	ESC	65	-14.4	S	0.000351 U	0.000227 U	0.000399 U	0.00101 U	0.000245 U	0.000402 U	0.000252 U	0.000281 U	0.000409 U	0.000272 U	0.000763 U	0.000318 U
	MW-140-75	08/30/17	PES	ESC	75	-24.4	S	0.00884 U	0.00572 U	0.0101 U	0.0255 U	0.00617 U	0.0101 U	0.00634 U	0.00706 U	0.0103 U	0.00685 U	0.0192 U	0.00800 U
	MW-140-90	08/30/17	PES	ESC	90	-39.4	S	0.000386 U	0.000249 U	0.000439 U	0.00111 U	0.000269 U	0.000441 U	0.000276 U	0.000308 U	0.000449 U	0.000299 U	0.000839 U	0.000349 U
	MW-140-110	08/31/17	PES	ESC	110	-59.4	S	0.000380 U	0.000245 U	0.000432 U	0.00110 U	0.000265 U	0.000434 U	0.000272 U	0.000303 U	0.000442 U	0.000294 U	0.000826 U	0.000344 U
	MW-140-130	08/31/17	PES	ESC	130	-79.4	S	0.000371 U	0.000240 U	0.000422 U	0.00107 U	0.000259 U	0.000424 U	0.000266 U	0.000296 U	0.000432 U	0.000287 U	0.000806 U	0.000336 U
	MW-140-140	08/31/17	PES	ESC	140	-89.4	S	0.00926 U	0.00599 U	0.0105 U	0.0267 U	0.00646 U	0.0106 U	0.00664 U	0.00740 U	0.0108 U	0.00717 U	0.0201 U	0.00838 U
MW-142 (2.4 to -7.6)	MW-142-5	04/12/18	PES	ESC	5	37.1	V	0.000395 U	0.000255 U	0.000449 U	0.00114 U	0.000276 U	0.000451 U	0.000283 U	0.000315 U	0.000460 U	0.000306 U	0.000858 U	0.000357 U
MW-143 (-27.7 to -37.7)	MW-143-10	04/11/18	PES	ESC	10	32.0	V	0.000455 U	0.000294 U	0.000517 U	0.00131 U	0.000317 U	0.000520 U	0.000326 U	0.000363 U	0.000530 U	0.000352 U	0.000988 U	0.000412 U
	MW-143-20	04/11/18	PES	ESC	20	22.0	S	0.000381 U	0.000246 U	0.000433 U	0.00110 U	0.000266 U	0.000436 U	0.000273 U	0.000304 U	0.000444 U	0.000295 U	0.000828 U	0.000345 U
	MW-143-30	04/11/18	PES	ESC	30	12.0	S	0.000373 U	0.000241 U	0.000425 U	0.00108 U	0.000261 U	0.000427 U	**0.000547 J**	0.000298 U	0.000435 U	0.000289 U	0.000812 U	0.000338 U
	MW-143-40	04/11/18	PES	ESC	40	2.0	S	0.000391 U	0.000253 U	0.000445 U	0.00113 U	0.000273 U	0.000447 U	**0.00203**	0.000313 U	0.000456 U	0.000303 U	0.000850 U	0.000354 U
	MW-143-50	04/11/18	PES	ESC	50	-8.0	S	0.000376 U	0.000243 U	0.000427 U	0.00108 U	0.000262 U	0.000429 U	**0.207**	0.000300 U	0.000438 U	0.000291 U	0.000817 U	0.000340 U
	MW-143-60	04/11/18	PES	ESC	60	-18.0	S	0.000365 U	0.000236 U	0.000415 U	0.00105 U	0.000255 U	0.000417 U	**0.00285**	0.000291 U	0.000425 U	0.000282 U	0.000792 U	0.000330 U
	MW-143-70	04/11/18	PES	ESC	70	-28.0	S	0.000361 U	0.000233 U	0.000410 U	0.00104 U	0.000252 U	0.000413 U	**0.0182**	0.000288 U	0.000420 U	0.000279 U	0.000784 U	0.000327 U
	MW-143-80	04/11/18	PES	ESC	80	-38.0	S	0.000373 U	0.000241 U	0.000424 U	0.00107 U	0.000260 U	0.000426 U	**0.00361**	0.000298 U	0.000434 U	0.000289 U	0.000810 U	0.000337 U
	MW-902-20	04/11/18	PES	ESC	80 (dup)	-38.0	S	0.000367 U	0.000237 U	0.000417 U	0.00106 U	0.000256 U	0.000420 U	**0.00256**	0.000293 U	0.000427 U	0.000284 U	0.000798 U	0.000332 U
MW-145 (-26.1 to -36.1)	MW-145-10	04/17/18	PES	ESC	10	33.5	V	0.000412 U	0.000266 U	0.000469 U	0.00119 U	0.000288 U	0.000471 U	0.000295 U	0.000329 U	0.000480 U	0.000319 U	0.000896 U	0.000373 U
	MW-145-20	04/17/18	PES	ESC	20	23.5	S	0.000383 U	0.000248 U	0.000435 U	0.00110 U	0.000267 U	0.000438 U	**0.00765**	0.000306 U	0.000446 U	0.000297 U	0.000832 U	0.000347 U
	MW-145-30	04/17/18	PES	ESC	30	13.5	S	0.000389 U	0.000251 U	0.000442 U	0.00112 U	0.000272 U	0.000445 U	**0.100**	0.000311 U	0.000453 U	0.000301 U	0.000846 U	0.000352 U
	MW-145-40	04/17/18	PES	ESC	40	3.5	S	0.000365 U	0.000236 U	0.000416 U	0.00105 U	0.000255 U	0.000418 U	**0.0691**	0.000292 U	0.000426 U	0.000283 U	0.000795 U	0.000331 U
	MW-145-50	04/17/18	PES	ESC	50	-6.5	S	0.000359 U	0.000232 U	0.000409 U	0.00104 U	0.000251 U	0.000411 U	**0.00555**	0.000287 U	0.000419 U	0.000278 U	0.000781 U	0.000325 U
	MW-145-60	04/17/18	PES	ESC	60	-16.5	S	0.000362 U	0.000234 U	0.000411 U	0.00104 U	0.000252 U	0.000413 U	0.000259 U	0.000289 U	0.000421 U	0.000280 U	0.000786 U	0.000327 U
	MW-145-70	04/17/18	PES	ESC	70	-26.5	S	0.000398 U	0.000257 U	0.000452 U	0.00115 U	0.000278 U	0.000455 U	**0.000290 J**	0.000318 U	0.000463 U	0.000308 U	0.000865 U	0.000360 U
	MW-145-80	04/17/18	PES	ESC	80	-36.5	S	0.000377 U	0.000243 U	0.000428 U	0.00109 U	0.000263 U	0.000431 U	**0.000380 J**	0.000301 U	0.000439 U	0.000292 U	0.000819 U	0.000341 U
	MW-903-40	04/17/18	PES	ESC	80 (dup)	-36.5	S	0.000368 U	0.000238 U	0.000418 U	0.00106 U	0.000257 U	0.000421 U	**0.000384 J**	0.000294 U	0.000428 U	0.000285 U	0.000800 U	0.000333 U
MW-147 (-17.6 to -27.6)	MW-147-10	04/02/18	PES	ESC	10	41.9	V	0.000356 U	0.000230 U	0.000405 U	0.00103 U	0.000249 U	0.000407 U	0.000255 U	0.000285 U	0.000415 U	0.000276 U	0.000774 U	0.000323 U
	MW-147-20	04/02/18	PES	ESC	20	31.9	S	0.000354 U	0.000229 U	0.000403 U	0.00102 U	0.000247 U	0.000405 U	0.000254 U	0.000283 U	0.000413 U	0.000275 U	0.000771 U	0.000321 U
	MW-147-30	04/02/18	PES	ESC	30	21.9	S	0.000366 U	0.000237 U	0.000416 U	0.00106 U	0.000256 U	0.000419 U	**0.00239**	0.000293 U	0.000427 U	0.000284 U	0.000796 U	0.000332 U
	MW-147-40	04/02/18	PES	ESC	40	11.9	S	0.000362 U	0.000234 U	0.000412 U	0.00104 U	0.000253 U	0.000414 U	**0.00488**	0.000289 U	0.000421 U	0.000280 U	0.000787 U	0.000328 U
	MW-147-50	04/02/18	PES	ESC	50	1.9	S	0.000363 U	0.000235 U	0.000413 U	0.00105 U	0.000254 U	0.000415 U	**0.00432**	0.000290 U	0.000423 U	0.000281 U	0.000790 U	0.000329 U
	MW-147-60	04/02/18	PES	ESC	60	-8.2	S	0.000353 U	0.000228 U	0.000401 U	0.00102 U	0.000246 U	0.000403 U	**0.000696 J**	0.000282 U	0.000411 U	0.000273 U	0.000767 U	0.000319 U
	MW-901-10	04/02/18	PES	ESC	60 (dup)	-8.2	S	0.000353 U	0.000228 U	0.000402 U	0.00102 U	0.000247 U	**0.00101 J**	0.000253 U	0.000282 U	0.000411 U	0.000274 U	0.000768 U	0.000320 U
	MW-147-70	04/02/18	PES	ESC	70	-18.2	S	0.000367 U	0.000237 U	0.000417 U	0.00106 U	0.000256 U	0.000420 U	0.000263 U	0.000293 U	0.000428 U	0.000284 U	0.000798 U	0.000332 U
	MW-147-80	04/02/18	PES	ESC	80	-28.2	S	0.000380 U	0.000245 U	0.000432 U	0.00109 U	0.000265 U	0.000434 U	0.000272 U	0.000303 U	0.000442 U	0.000294 U	0.000825 U	0.000334 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
MW-148	MW-148-11	04/09/18	PES	ESC	11	32.9	V	0.000378 U	0.000245 U	0.000430 U	0.00109 U	0.000264 U	0.000433 U	0.000271 U	0.000302 U	0.000441 U	0.000293 U	0.000823 U	0.000343 U
(-25.7 to -35.7)	MW-148-20	04/09/18	PES	ESC	20	23.9	S	0.000356 U	0.000230 U	0.000405 U	0.00103 U	0.000248 U	0.000407 U	0.000255 U	0.000284 U	0.000414 U	0.000276 U	0.000773 U	0.000322 U
	MW-148-30	04/09/18	PES	ESC	30	13.9	S	0.000368 U	0.000238 U	0.000419 U	0.00106 U	0.000257 U	0.000421 U	**0.00364**	0.000294 U	0.000429 U	0.000285 U	0.000801 U	0.000334 U
	MW-148-40	04/09/18	PES	ESC	40	3.9	S	0.000356 U	0.000230 U	0.000405 U	0.00103 U	0.000249 U	0.000407 U	**0.00113**	0.000285 U	0.000415 U	0.000276 U	0.000775 U	0.000323 U
	MW-148-50	04/09/18	PES	ESC	50	-6.1	S	0.000362 U	0.000234 U	0.000411 U	0.00104 U	0.000253 U	0.000414 U	0.000259 U	0.000289 U	0.000421 U	0.000280 U	0.000786 U	0.000328 U
	MW-148-60	04/09/18	PES	ESC	60	-16.1	S	0.000414 U	0.000268 U	0.000471 U	0.00119 U	0.000289 U	0.000473 U	0.000297 U	0.000331 U	0.000482 U	0.000321 U	0.000900 U	0.000375 U
	MW-148-70	04/09/18	PES	ESC	70	-26.1	S	0.000413 U	0.000267 U	0.000470 U	0.00119 U	0.000289 U	0.000473 U	**0.000380 J**	0.000330 U	0.000481 U	0.000320 U	0.000898 U	0.000374 U
	MW-148-80	04/09/18	PES	ESC	80	-36.1	S	0.000385 U	0.000249 U	0.000438 U	0.00111 U	0.000269 U	0.000441 U	**0.000314 J**	0.000308 U	0.000449 U	0.000298 U	0.000838 U	0.000349 U
MW-153	MW-153-10	03/27/18	PES	ESC	10	44.4	V	0.000372 U	0.000240 U	0.000423 U	0.00107 U	0.000260 U	0.000425 U	0.000266 U	0.000297 U	0.000433 U	0.000288 U	0.000809 U	0.000337 U
(-65.3 to -75.3)	MW-153-20	03/27/18	PES	ESC	20	34.4	V	0.000359 U	0.000232 U	0.000408 U	0.00104 U	0.000251 U	0.000410 U	0.000257 U	0.000287 U	0.000418 U	0.000278 U	0.000780 U	0.000325 U
	MW-153-30	03/27/18	PES	ESC	30	24.4	S	0.000352 U	0.000227 U	0.000400 U	0.00101 U	0.000246 U	0.000402 U	0.000252 U	0.000281 U	0.000410 U	0.000272 U	0.000765 U	0.000319 U
	MW-153-40	03/27/18	PES	ESC	40	14.4	S	0.000372 U	0.000240 U	0.000423 U	0.00107 U	0.000259 U	0.000425 U	**0.00421**	0.000297 U	0.000433 U	0.000288 U	0.000808 U	0.000336 U
	MW-153-50	03/27/18	PES	ESC	50	4.4	S	0.000364 U	0.000235 U	0.000414 U	0.00105 U	0.000254 U	0.000416 U	0.000261 U	0.000291 U	0.000424 U	0.000282 U	0.000791 U	0.000329 U
	MW-153-61	03/27/18	PES	ESC	61	-6.7	S	0.000373 U	0.000241 U	0.000424 U	0.00108 U	0.000260 U	0.000426 U	0.000267 U	0.000298 U	0.000434 U	0.000289 U	0.000810 U	0.000338 U
	MW-153-70	03/27/18	PES	ESC	70	-15.7	S	0.000365 U	0.000236 U	0.000415 U	0.00105 U	0.000255 U	0.000418 U	0.000262 U	0.000292 U	0.000425 U	0.000283 U	0.000794 U	0.000331 U
	MW-153-80	03/28/18	PES	ESC	80	-25.7	S	0.000362 U	0.000234 U	0.000412 U	0.00104 U	0.000253 U	0.000414 U	**0.000353 J**	0.000289 U	0.000421 U	0.000280 U	0.000787 U	0.000328 U
	MW-153-90	03/28/18	PES	ESC	90	-35.7	S	0.000395 U	0.000255 U	0.000449 U	0.00114 U	0.000276 U	0.000452 U	**0.000596 J**	0.000316 U	0.000460 U	0.000306 U	0.000859 U	0.000358 U
	MW-153-110	03/28/18	PES	ESC	110	-55.7	S	0.000386 U	0.000249 U	0.000439 U	0.00111 U	0.000269 U	0.000441 U	**0.000773 J**	0.000308 U	0.000450 U	0.000299 U	0.000839 U	0.000350 U
	MW-153-130	03/29/18	PES	ESC	130	-75.7	S	0.000377 U	0.000244 U	0.000428 U	0.00109 U	0.000263 U	0.000431 U	0.000270 U	0.000301 U	0.000439 U	0.000292 U	0.000819 U	0.000341 U
MW-158	MW-158-20	04/05/18	PES	ESC	20	21.1	S	0.000372 U	0.000240 U	0.000423 U	0.00107 U	0.000259 U	0.000425 U	0.000266 U	0.000297 U	0.000433 U	0.000288 U	0.000808 U	0.000336 U
	MW-158-30	04/05/18	PES	ESC	30	11.1	S	0.0387 U	0.0250 U	0.0440 U	0.112 U	0.0270 U	0.0442 U	**3.00**	0.0309 U	0.0451 U	0.0300 U	0.0841 U	0.0350 U
MW-158A	MW-158A-40	04/05/18	PES	ESC	40	1.1	S	0.000404 U	0.000261 U	0.000460 U	0.00117 U	0.000282 U	0.000462 U	**0.168**	0.000323 U	0.000471 U	0.000313 U	0.000879 U	0.000366 U
(-47.2 to -58.5)	MW-158A-50	04/05/18	PES	ESC	50	-8.9	S	0.000379 U	0.000245 U	0.000431 U	0.00109 U	0.000265 U	0.000434 U	**0.0631**	0.000303 U	0.000442 U	0.000294 U	0.000824 U	0.000343 U
	MW-158A-60	04/05/18	PES	ESC	60	-18.9	S	0.000377 U	0.000244 U	0.000429 U	0.00109 U	0.000264 U	0.000432 U	**0.111**	0.000302 U	0.000440 U	0.000292 U	0.000821 U	0.000342 U
	MW-158A-70	04/05/18	PES	ESC	70	-28.9	S	0.000368 U	0.000238 U	0.000419 U	0.00106 U	0.000257 U	0.000421 U	**0.946**	0.000294 U	0.000429 U	0.000285 U	0.000800 U	0.000333 U
	MW-158A-80	04/06/18	PES	ESC	80	-38.9	S	0.000364 U	0.000235 U	0.000414 U	0.00105 U	0.000254 U	0.000416 U	**0.00335**	0.000291 U	0.000424 U	0.000282 U	0.000791 U	0.000329 U
	MW-158A-90	04/06/18	PES	ESC	90	-48.9	S	0.000376 U	0.000243 U	0.000428 U	0.00109 U	0.000263 U	0.000430 U	**0.00789**	0.000301 U	0.000438 U	0.000291 U	0.000818 U	0.000341 U
	MW-158A-100	04/06/18	PES	ESC	100	-58.9	S	0.000385 U	0.000249 U	0.000438 U	0.00111 U	0.000269 U	0.000441 U	**0.00789**	0.000308 U	0.000449 U	0.000298 U	0.000838 U	0.000349 U
MW-159	MW-159-20	04/16/18	PES	ESC	20	22.8	S	0.000397 U	0.000256 U	0.000451 U	0.00114 U	0.000277 U	0.000453 U	0.000284 U	0.000317 U	0.000462 U	0.000307 U	0.000862 U	0.000359 U
(22.9 to 12.9)	MW-159-30	04/16/18	PES	ESC	30	12.8	S	0.000400 U	0.000258 U	0.000455 U	0.00115 U	0.000279 U	0.000457 U	**0.0506**	0.000319 U	0.000466 U	0.000310 U	0.000869 U	0.000362 U
MW-160	MW-160-11	05/08/18	PES	ESC	11	31.5	S	0.00175 U	0.000929 U	0.000730 U	0.00175 U	0.000674 U	0.00225 U	0.00112 U	0.00110 U	0.00162 U	0.00128 U	0.00132 U	0.000860 U
(-76.5 to -86.5)	MW-160-21	05/08/18	PES	ESC	21	21.5	S	0.00127 U	0.000672 U	0.000527 U	0.00127 U	0.000486 U	0.00163 U	**0.00357**	0.000795 U	0.00117 U	0.000924 U	0.000959 U	0.000621 U
	MW-160-31	05/08/18	PES	ESC	31	11.5	S	0.00131 U	0.000695 U	0.000546 U	0.00131 U	0.000503 U	0.00169 U	0.000837 U	0.000822 U	0.00121 U	0.000956 U	0.000992 U	0.000643 U
	MW-160-40	05/08/18	PES	ESC	40	2.5	S	0.00123 U	0.000651 U	0.000511 U	0.00123 U	0.000471 U	0.00158 U	**0.151**	0.000770 U	0.00114 U	0.000895 U	0.000929 U	0.000602 U
	MW-160-50	05/08/18	PES	ESC	50	-7.5	S	0.00123 U	0.000655 U	0.000514 U	0.00123 U	0.000474 U	0.00159 U	**0.00694**	0.000775 U	0.00114 U	0.000900 U	0.000935 U	0.000606 U
	MW-160-55	05/08/18	PES	ESC	55	-12.5	S	0.00128 U	0.000680 U	0.000534 U	0.00128 U	0.000492 U	0.00165 U	**1.50**	0.000804 U	0.00119 U	0.000935 U	0.000970 U	0.000629 U
	MW-160-60	05/08/18	PES	ESC	60	-17.5	S	0.00118 U	0.000624 U	0.000490 U	0.00118 U	0.000452 U	0.00151 U	**0.352**	0.000739 U	0.00109 U	0.000859 U	0.000891 U	**0.000699 J**
	MW-160-70	05/08/18	PES	ESC	70	-27.5	S	0.00126 U	0.000669 U	0.000526 U	0.00126 U	0.000485 U	0.00162 U	**0.00460**	0.000792 U	0.00117 U	0.000921 U	0.000956 U	0.000619 U
	MW-160-90	05/08/18	PES	ESC	90	-47.5	S	0.00127 U	0.000674 U	0.000530 U	0.00127 U	0.000488 U	0.00164 U	**0.00432**	0.000798 U	0.00118 U	0.000927 U	0.000963 U	0.000624 U
	MW-160-100	05/08/18	PES	ESC	100	-57.5	S	0.00130 U	0.000689 U	0.000541 U	0.00130 U	0.000499 U	0.00167 U	**0.00506**	0.000816 U	0.00120 U	0.000948 U	0.000984 U	0.000638 U
	MW-160-110	05/08/18	PES	ESC	110	-67.5	S	0.00122 U	0.000650 U	0.000510 U	0.00122 U	0.000471 U	0.00158 U	**0.0128**	0.000769 U	0.00113 U	0.000894 U	0.000928 U	0.000601 U
	MW-160-125	05/10/18	PES	ESC	125	-82.5	S	0.00124 U	0.000656 U	0.000515 U	0.00124 U	0.000475 U	0.00159 U	**0.000832 J**	0.000776 U	0.00114 U	0.000902 U	0.000937 U	0.000607 U
	MW-160-127.5	05/10/18	PES	ESC	128	-85.0	S	0.00125 U	0.000662 U	0.000520 U	0.00125 U	0.000479 U	0.00161 U	0.000797 U	0.000783 U	0.00115 U	0.000910 U	0.000945 U	0.000612 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
MW-161	MW-161-11	05/14/18	PES	ESC	11	32.8	S	0.00133 U	0.000705 U	0.000553 U	0.00133 U	0.000510 U	0.00171 U	**0.00563**	0.000834 U	0.00123 U	0.000969 U	0.00101 U	0.00307 U
(-78.9 to -88.9)	MW-161-21	05/14/18	PES	ESC	21	22.8	S	0.00112 U	0.000596 U	0.000468 U	0.00112 U	0.000431 U	0.00144 U	**0.00364**	0.000705 U	0.00104 U	0.000819 U	0.000850 U	0.00260 U
	MW-161-31	05/14/18	PES	ESC	31	12.8	S	0.00124 U	0.000656 U	0.000515 U	0.00124 U	0.000475 U	0.00159 U	**0.00387**	0.000776 U	0.00114 U	0.000902 U	0.000936 U	0.00286 U
	MW-161-40	05/14/18	PES	ESC	40	3.8	S	0.00119 U	0.000632 U	0.000497 U	0.00119 U	0.000458 U	0.00153 U	**0.376**	0.000748 U	0.00110 U	0.000870 U	0.000903 U	0.00276 U
	MW-161-50	05/14/18	PES	ESC	50	-6.2	S	0.00121 U	0.000639 U	0.000502 U	0.00121 U	0.000463 U	0.00155 U	**0.0356**	0.000757 U	0.00112 U	0.000879 U	0.000913 U	0.00279 U
	MW-161-60	05/14/18	PES	ESC	60	-16.2	S	0.00123 U	0.000654 U	0.000514 U	0.00123 U	0.000474 U	0.00159 U	**0.0316**	0.000774 U	0.00114 U	0.000900 U	0.000934 U	0.00286 U
	MW-161-70	05/14/18	PES	ESC	70	-26.2	S	0.00121 U	0.000640 U	0.000503 U	0.00121 U	0.000463 U	0.00155 U	0.00279 U	0.000757 U	0.00112 U	0.000880 U	0.000914 U	0.00279 U
	MW-161-80	05/14/18	PES	ESC	80	-36.2	S	0.00133 U	0.000706 U	0.000555 U	0.00133 U	0.000512 U	0.00171 U	0.00308 U	0.000836 U	0.00123 U	0.000971 U	0.00101 U	0.00308 U
	MW-161-90	05/14/18	PES	ESC	90	-46.2	S	0.00123 U	0.000652 U	0.000512 U	0.00123 U	0.000472 U	0.00158 U	0.00285 U	0.000772 U	0.00114 U	0.000897 U	0.000931 U	0.00285 U
	B-927-30	05/14/18	PES	ESC	90 (dup)	-46.2	S	0.00134 U	0.000712 U	0.000559 U	0.00134 U	0.000515 U	0.00173 U	0.00310 U	0.000842 U	0.00124 U	0.000979 U	0.00102 U	0.00310 U
	MW-161-100	05/14/18	PES	ESC	100	-56.2	S	0.00126 U	0.000667 U	0.000524 U	0.00126 U	0.000483 U	0.00162 U	0.00291 U	0.000789 U	0.00116 U	0.000918 U	0.000952 U	0.00291 U
	MW-161-110	05/14/18	PES	ESC	110	-66.2	S	0.00132 U	0.000699 U	0.000549 U	0.00132 U	0.000506 U	0.00170 U	0.00305 U	0.000827 U	0.00122 U	0.000961 U	0.000998 U	0.00305 U
	MW-161-120	05/14/18	PES	ESC	120	-76.2	S	0.00132 U	0.000699 U	0.000549 U	0.00132 U	0.000506 U	0.00170 U	0.00305 U	0.000827 U	0.00122 U	0.000961 U	0.000998 U	0.00305 U
	MW-161-130	05/14/18	PES	ESC	130	-86.2	S	0.00119 U	0.000630 U	0.000495 U	0.00119 U	0.000456 U	0.00153 U	0.00275 U	0.000746 U	0.00110 U	0.000867 U	0.000900 U	0.00275 U
	MW-161-140	05/15/18	PES	ESC	140	-96.2	S	0.00132 U	0.000702 U	0.000552 U	0.00132 U	0.000509 U	0.00170 U	0.000846 U	0.000831 U	0.00123 U	0.000966 U	0.00100 U	0.000650 U
MW-190	MW-190-5	09/19/19	PES	PACE	5	43.7	V	0.00125 U	0.000661 U	0.000519 U	0.00125 U	**0.000714 J**	0.00160 U	0.000796 U	0.000782 U	0.00115 U	0.000909 U	0.000943 U	0.000611 U
(-30.2 to -40.2)	MW-190-10	09/19/19	PES	PACE	10	38.7	V	0.00223 U	0.00118 U	0.000930 U	0.00223 U	0.000859 U	0.00288 U	0.00143 U	0.00140 U	0.00207 U	0.00162 U	0.00169 U	**0.00350 J**
	MW-190-15	09/19/19	PES	PACE	15	33.7	S	0.00143 U	0.000759 U	0.000596 U	0.00143 U	**0.000727 J**	0.00184 U	0.000913 U	0.000898 U	0.00132 U	0.00104 U	0.00108 U	0.000702 U
	MW-190-20	09/19/19	PES	PACE	20	28.7	S	0.00134 U	0.000713 U	0.000560 U	0.00134 U	**0.000922 J**	0.00173 U	**0.00477**	0.000844 U	0.00124 U	0.000981 U	0.00102 U	**0.00108 J**
	MW-190-25	09/19/19	PES	PACE	25	23.7	S	0.00127 U	0.000673 U	0.000528 U	0.00127 U	**0.000724 J**	0.00163 U	**0.00187 J**	0.000796 U	0.00117 U	0.000925 U	0.000960 U	0.000622 U
	MW-190-30	09/19/19	PES	PACE	30	18.7	S	0.00113 U	0.000600 U	0.000471 U	0.00113 U	**0.000696 J**	0.00146 U	**0.00418**	0.000710 U	0.00105 U	0.000826 U	0.000857 U	0.000555 U
	MW-190-35	09/19/19	PES	PACE	35	13.7	S	0.00115 U	0.000609 U	0.000478 U	0.00115 U	**0.000695 J**	0.00148 U	**0.00442**	0.000720 U	0.00106 U	0.000837 U	0.000869 U	0.000563 U
	MW-190-40	09/19/19	PES	PACE	40	8.7	S	0.00121 U	0.000643 U	0.000505 U	0.00121 U	**0.000916 J**	0.00156 U	0.000775 U	0.000761 U	0.00112 U	0.000885 U	0.000918 U	0.000595 U
	MW-190-45	09/19/19	PES	PACE	45	3.7	S	0.00123 U	0.000655 U	0.000515 U	0.00123 U	**0.000535 J**	0.00159 U	0.000789 U	0.000775 U	0.00114 U	0.000901 U	0.000935 U	0.000606 U
	MW-190-50	09/19/19	PES	PACE	50	-1.4	S	0.00113 U	0.000600 U	0.000471 U	0.00113 U	**0.000748 J**	0.00146 U	0.000723 U	0.000710 U	0.00105 U	0.000825 U	0.000857 U	0.000555 U
	MW-190-55	09/19/19	PES	PACE	55	-6.4	S	0.00117 U	0.000621 U	0.000488 U	0.00117 U	**0.000536 J**	0.00151 U	**0.0790**	0.000735 U	0.00108 U	0.000855 U	0.000887 U	0.000575 U
	MW-190-60	09/19/19	PES	PACE	60	-11.4	S	0.00118 U	0.000624 U	0.000490 U	0.00118 U	**0.000608 J**	0.00151 U	**0.00884 J**	0.000739 U	0.00109 U	0.000859 U	0.000891 U	0.000578 U
	MW-2008-60	09/19/19	PES	PACE	60 (dup)	-11.4	S	0.00117 U	0.000619 U	0.000486 U	0.00117 U	0.000449 U	0.00150 U	**0.0214 J**	0.000733 U	0.00108 U	0.000852 U	0.000884 U	0.000573 U
	MW-190-65	09/19/19	PES	PACE	65	-16.4	S	0.00119 U	0.000633 U	0.000497 U	0.00119 U	**0.000788 J**	0.00153 U	0.000762 U	0.000749 U	0.00110 U	0.000870 U	0.000903 U	**0.000853 J**
	MW-190-70	09/19/19	PES	PACE	70	-21.4	S	0.00120 U	0.000635 U	0.000498 U	0.00120 U	0.000460 U	0.00154 U	0.000764 U	0.000751 U	0.00111 U	0.000873 U	0.000906 U	0.000587 U
	MW-190-75	09/19/19	PES	PACE	75	-26.4	S	0.00118 U	0.000626 U	0.000492 U	0.00118 U	0.000454 U	0.00152 U	0.000754 U	0.000741 U	0.00109 U	0.000862 U	0.000894 U	0.000579 U
	MW-190-80	09/19/19	PES	PACE	80	-31.4	S	0.00118 U	0.000626 U	0.000491 U	0.00118 U	0.000453 U	0.00152 U	0.000753 U	0.000740 U	0.00109 U	0.000860 U	0.000893 U	0.000579 U
	MW-190-85	09/19/19	PES	PACE	85	-36.4	S	0.00124 U	0.000659 U	0.000517 U	0.00124 U	0.000477 U	0.00160 U	0.000793 U	0.000779 U	0.00115 U	0.000906 U	0.000940 U	0.000609 U
	MW-190-87	09/19/19	PES	PACE	87	-38.4	S	0.00129 U	0.000685 U	0.000538 U	0.00129 U	0.000496 U	0.00166 U	0.000825 U	0.000810 U	0.00120 U	0.000942 U	0.000978 U	0.000633 U
MW-301	MW-301-6	09/20/19	PES	PACE	6	47.8	V	0.00127 U	0.000671 U	0.000527 U	0.00127 U	**0.000796 J**	0.00163 U	0.000809 U	0.000794 U	0.00117 U	0.000923 U	0.000959 U	**0.000628 J**
(35.6 to 25.6)	MW-301-10	09/20/19	PES	PACE	10	43.8	V	0.00119 U	0.000630 U	0.000495 U	0.00119 U	**0.000762 J**	0.00153 U	0.000759 U	0.000745 U	0.00110 U	0.000866 U	0.000899 U	0.000583 U
	MW-301-15	09/20/19	PES	PACE	15	38.8	V	0.00123 U	0.000650 U	0.000511 U	0.00123 U	**0.000848 J**	0.00158 U	0.000783 U	0.000770 U	0.00114 U	0.000895 U	0.000929 U	0.000602 U
	MW-301-20	09/20/19	PES	PACE	20	33.8	S	0.00364 U	0.00194 U	0.00152 U	0.00364 U	**0.00226 J**	0.00470 U	0.00232 U	0.00229 U	0.00338 U	0.00266 U	0.00277 U	0.00178 U
	MW-301-25	09/20/19	PES	PACE	25	28.8	S	0.00123 U	0.000651 U	0.000511 U	0.00123 U	**0.000822 J**	0.00158 U	0.000784 U	0.000771 U	0.00114 U	0.000896 U	0.000930 U	**0.00121 J**
	MW-301-30	09/20/19	PES	PACE	30	23.8	S	0.00133 U	0.000709 U	0.000557 U	0.00133 U	**0.00122 J**	0.00172 U	0.000854 U	0.000839 U	0.00124 U	0.000975 U	0.00101 U	**0.00111 J**
MW-302	MW-302-5	10/01/19	PES	PACE	5	52.3	V	0.00126 U	0.000671 U	0.000527 U	0.00126 U	**0.000913 J**	0.00163 U	0.000808 U	0.000794 U	0.00117 U	0.000923 U	0.000958 U	**0.00110 J**
(3.0 to -7.0)	MW-302-10	10/01/19	PES	PACE	10	47.3	V	0.00134 U	0.000713 U	0.000560 U	0.00134 U	0.000516 U	0.00173 U	0.000859 U	0.000844 U	0.00124 U	0.000980 U	0.00102 U	0.000659 U
	MW-302-15	10/01/19	PES	PACE	15	42.3	V	0.00147 U	0.000782 U	0.000614 U	0.00147 U	0.000565 U	0.00189 U	0.000940 U	0.000924 U	0.00136 U	0.00107 U	0.00112 U	0.000723 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
MW-302	MW-302-20	10/01/19	PES	PACE	20	37.3	S	0.00129 U	0.000684 U	0.000537 U	0.00129 U	0.000495 U	0.00166 U	0.000823 U	0.000809 U	0.00119 U	0.000940 U	0.000976 U	0.000632 U
(continued)	MW-302-25	10/01/19	PES	PACE	25	32.3	S	0.00121 U	0.000642 U	0.000504 U	0.00121 U	0.000465 U	0.00156 U	0.000773 U	0.000760 U	0.00112 U	0.000883 U	0.000917 U	0.000594 U
	MW-302-30	10/01/19	PES	PACE	30	27.3	S	0.00118 U	0.000627 U	0.000492 U	0.00118 U	0.000454 U	0.00152 U	0.000755 U	0.000742 U	0.00109 U	0.000862 U	0.000895 U	0.000580 U
	MW-302-35	10/01/19	PES	PACE	35	22.3	S	0.00116 U	0.000616 U	0.000484 U	0.00116 U	0.000446 U	0.00149 U	0.000742 U	0.000729 U	0.00107 U	0.000847 U	0.000879 U	0.000570 U
	MW-302-40	10/01/19	PES	PACE	40	17.3	S	0.00115 U	0.000610 U	0.000479 U	0.00115 U	0.000441 U	0.00148 U	0.000734 U	0.000721 U	0.00106 U	0.000838 U	0.000870 U	0.000564 U
	MW-302-45	10/01/19	PES	PACE	45	12.3	S	0.00129 U	0.000683 U	0.000536 U	0.00129 U	0.000494 U	0.00166 U	0.000822 U	0.000808 U	0.00119 U	0.000939 U	0.000975 U	0.000631 U
	MW-302-50	10/01/19	PES	PACE	50	7.3	S	0.00129 U	0.000684 U	0.000537 U	0.00129 U	0.000496 U	0.00166 U	0.000824 U	0.000810 U	0.00119 U	0.000941 U	0.000977 U	0.000633 U
	MW-302-55	10/01/19	PES	PACE	55	2.3	S	0.00123 U	0.000651 U	0.000511 U	0.00123 U	0.000472 U	0.00158 U	0.000784 U	0.000770 U	0.00114 U	0.000895 U	0.000930 U	0.000602 U
	MW-302-60	10/01/19	PES	PACE	60	-2.7	S	0.00154 U	0.000815 U	0.000640 U	0.00154 U	0.000590 U	0.00198 U	0.000981 U	0.000964 U	0.00142 U	0.00112 U	0.00116 U	**0.00117 J**
	MW-302-65	10/01/19	PES	PACE	65	-7.7	S	0.00126 U	0.000671 U	0.000527 U	0.00126 U	0.000486 U	0.00163 U	0.000808 U	0.000794 U	0.00117 U	0.000923 U	0.000958 U	0.000621 U
	MW-2014-65	10/01/19	PES	PACE	65 (dup)	-7.7	S	0.00131 U	0.000695 U	0.000546 U	0.00131 U	0.000503 U	0.00169 U	0.000836 U	0.000822 U	0.00121 U	0.000955 U	0.000992 U	0.000643 U
MW-304	MW-304-5	10/01/19	PES	PACE	5	52.6	V	0.00122 U	0.000645 U	0.000507 U	0.00122 U	0.000467 U	0.00157 U	0.000777 U	0.000764 U	0.00113 U	0.000888 U	0.000921 U	0.000597 U
(-47.6 to -57.6)	MW-304-10	10/01/19	PES	PACE	10	47.6	V	0.00123 U	0.000653 U	0.000513 U	0.00123 U	**0.000522 J**	0.00158 U	0.000786 U	0.000773 U	0.00114 U	0.000898 U	0.000932 U	0.000604 U
	MW-304-15	10/01/19	PES	PACE	15	42.6	V	0.00128 U	0.000681 U	0.000535 U	0.00128 U	0.000493 U	0.00165 U	0.000820 U	0.000806 U	0.00119 U	0.000937 U	0.000973 U	0.000630 U
	MW-304-20	10/01/19	PES	PACE	20	37.6	S	0.00127 U	0.000675 U	0.000530 U	0.00127 U	**0.000674 J**	0.00164 U	0.000813 U	0.000799 U	0.00118 U	0.000928 U	0.000963 U	0.000624 U
	MW-304-25	10/01/19	PES	PACE	25	32.6	S	0.00118 U	0.000627 U	0.000492 U	0.00118 U	0.000454 U	0.00152 U	0.000755 U	0.000742 U	0.00109 U	0.000862 U	0.000895 U	0.000580 U
	MW-304-30	10/01/19	PES	PACE	30	27.6	S	0.00127 U	0.000674 U	0.000529 U	0.00127 U	0.000488 U	0.00163 U	0.000812 U	0.000797 U	0.00118 U	0.000927 U	0.000962 U	0.000623 U
	MW-304-40	10/01/19	PES	PACE	40	17.6	S	0.00117 U	0.000622 U	0.000488 U	0.00117 U	0.000450 U	0.00151 U	0.000749 U	0.000736 U	0.00109 U	0.000855 U	0.000888 U	0.000575 U
	MW-304-45	10/01/19	PES	PACE	45	12.6	S	0.00110 U	0.000582 U	0.000457 U	0.00110 U	0.000422 U	0.00141 U	0.000701 U	0.000689 U	0.00102 U	0.000800 U	0.000831 U	0.000538 U
	MW-304-50	10/01/19	PES	PACE	50	7.6	S	0.00116 U	0.000617 U	0.000484 U	0.00116 U	**0.000503 J**	0.00150 U	0.000743 U	0.000730 U	0.00108 U	0.000848 U	0.000881 U	0.000571 U
	MW-304-55	10/01/19	PES	PACE	55	2.6	S	0.00109 U	0.000578 U	0.000454 U	0.00109 U	**0.000454 J**	0.00140 U	0.000695 U	0.000683 U	0.00101 U	0.000794 U	0.000825 U	0.000534 U
	MW-304-60	10/01/19	PES	PACE	60	-2.4	S	0.00114 U	0.000604 U	0.000475 U	0.00114 U	0.000438 U	0.00147 U	0.000728 U	0.000715 U	0.00105 U	0.000831 U	0.000863 U	0.000559 U
	MW-304-65	10/01/19	PES	PACE	65	-7.4	S	0.00125 U	0.000664 U	0.000521 U	0.00125 U	0.000481 U	0.00161 U	0.000799 U	0.000785 U	0.00116 U	0.000913 U	0.000947 U	0.000614 U
	MW-304-70	10/01/19	PES	PACE	70	-12.4	S	0.00131 U	0.000696 U	0.000547 U	0.00131 U	0.000504 U	0.00169 U	0.000838 U	0.000824 U	0.00121 U	0.000957 U	0.000994 U	0.000644 U
	MW-304-75	10/01/19	PES	PACE	75	-17.4	S	0.00124 U	0.000656 U	0.000515 U	0.00124 U	**0.000661 J**	0.00159 U	0.000790 U	0.000776 U	0.00114 U	0.000902 U	0.000937 U	**0.000619 J**
	MW-304-80	10/01/19	PES	PACE	80	-22.4	S	0.00118 U	0.000627 U	0.000493 U	0.00118 U	0.000454 U	0.00152 U	0.000755 U	0.000742 U	0.00109 U	0.000862 U	0.000895 U	0.000580 U
	MW-304-85	10/01/19	PES	PACE	85	-27.4	S	0.00118 U	0.000628 U	0.000493 U	0.00118 U	0.000455 U	0.00152 U	0.000756 U	0.000743 U	0.00110 U	0.000863 U	0.000896 U	0.000580 U
	MW-304-90	10/01/19	PES	PACE	90	-32.4	S	0.00129 U	0.000687 U	0.000540 U	0.00129 U	**0.000587 J**	0.00167 U	0.000827 U	0.000813 U	0.00120 U	0.000945 U	0.000981 U	0.000635 U
	MW-304-95	10/01/19	PES	PACE	95	-37.4	S	0.00128 UJ	0.000679 U	0.000533 U	0.00128 U	0.000492 U	0.00165 U	0.000818 U	0.000803 U	0.00118 U	0.000934 U	0.000969 U	0.000628 U
	MW-2009-95	10/01/19	PES	PACE	95 (dup)	-37.4	S	0.00130 UJ	0.000688 U	0.000541 U	0.00130 U	0.000499 U	0.00167 U	0.000829 U	0.000814 U	0.00120 U	0.000947 U	0.000983 U	0.000637 U
	MW-304-100	10/02/19	PES	PACE	100	-42.4	S	0.00127 UJ	0.000675 U	0.000530 U	0.00127 U	**0.000500 J**	0.00164 U	0.000813 U	0.000799 U	0.00118 U	0.000929 U	0.000964 U	0.000625 U
	MW-304-105	10/02/19	PES	PACE	105	-47.4	S	0.00126 UJ	0.000671 U	0.000527 U	0.00126 U	0.000486 U	0.00163 U	0.000807 U	0.000793 U	0.00117 U	0.000922 U	0.000957 U	0.000620 U
	MW-304-110	10/02/19	PES	PACE	110	-52.4	S	0.00137 U	0.000725 U	0.000569 U	0.00137 U	0.000525 U	0.00176 UJ	0.000872 U	0.000857 U	0.00126 U	0.000996 U	0.00103 U	**0.000699 J**
	MW-304-115	10/02/19	PES	PACE	115	-57.4	S	0.00126 UJ	0.000668 U	0.000524 U	0.00126 U	0.000484 U	0.00162 U	0.000804 U	0.000790 U	0.00117 U	0.000918 U	0.000953 U	0.000617 U
MW-307	MW-307-6	10/03/19	PES	PACE	6	54.5	V	0.00121 U	0.000641 U	0.000503 U	0.00121 U	0.000464 U	0.00155 U	0.000771 U	0.000758 U	0.00112 U	0.000881 U	0.000914 U	**0.000603 J**
(-12.4 to -22.4)	MW-307-10	10/03/19	PES	PACE	10	50.5	V	0.00124 U	0.000659 U	0.000518 U	0.00124 U	**0.000843 J**	0.00160 U	0.000794 U	0.000781 U	0.00115 U	0.000907 U	0.000942 U	**0.000971 J**
	MW-307-15	10/03/19	PES	PACE	15	45.5	V	0.00116 U	0.000617 U	0.000485 U	0.00116 U	**0.000511 J**	0.00150 U	0.000743 U	0.000731 U	0.00108 U	0.000849 U	0.000881 U	0.000571 U
	MW-307-20	10/03/19	PES	PACE	20	40.5	V	0.00115 U	0.000613 U	0.000481 U	0.00115 U	**0.000716 J**	0.00149 U	0.000738 U	0.000725 U	0.00107 U	0.000843 U	0.000875 U	0.000567 U
	MW-307-25	10/03/19	PES	PACE	25	35.5	S	0.00118 U	0.000629 U	0.000494 U	0.00118 U	**0.000593 J**	0.00152 U	0.000757 U	0.000744 U	0.00110 U	0.000864 U	0.000897 U	0.000581 U
	MW-307-30	10/03/19	PES	PACE	30	30.5	S	0.00160 U	0.000844 U	0.000664 U	0.00160 U	**0.000776 J**	0.00205 U	0.00102 U	0.000999 U	0.00147 U	0.00116 U	0.00121 U	0.000781 U
	MW-307-35	10/03/19	PES	PACE	35	25.5	S	0.00116 U	0.000613 U	0.000481 U	0.00116 U	**0.000452 J**	0.00149 U	0.000738 U	0.000725 U	0.00107 U	0.000843 U	0.000875 U	0.000567 U
	MW-307-40	10/03/19	PES	PACE	40	20.5	S	0.00123 U	0.000654 U	0.000514 U	0.00123 U	**0.000730 J**	0.00159 U	0.000788 U	0.000774 U	0.00114 U	0.000900 U	0.000934 U	0.000605 U
	MW-307-45	10/03/19	PES	PACE	45	15.5	S	0.00119 U	0.000632 U	0.000496 U	0.00119 U	**0.000699 J**	0.00153 U	0.000761 U	0.000748 U	0.00110 U	0.000869 U	0.000902 U	0.000585 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
MW-307 (continued)	MW-307-50	10/03/19	PES	PACE	50	10.5	S	0.00120 U	0.000637 U	0.000500 U	0.00120 U	**0.000736 J**	0.00155 U	0.000767 U	0.000754 U	0.00111 U	0.000876 U	0.000910 U	0.000589 U
	MW-307-55	10/03/19	PES	PACE	55	5.5	S	0.00117 U	0.000622 U	0.000489 U	0.00117 U	0.000451 U	0.00151 U	0.000749 U	0.000736 U	0.00109 U	0.000856 U	0.000888 U	0.000575 U
	MW-307-60	10/03/19	PES	PACE	60	0.5	S	0.00122 UJ	0.000647 U	0.000508 U	0.00122 U	0.000469 U	0.00157 U	0.000779 U	0.000766 U	0.00113 U	0.000890 U	0.000924 U	0.000599 U
	MW-307-65	10/03/19	PES	PACE	65	-4.5	S	0.00248 UJ	0.00132 U	0.00104 U	0.00248 U	0.000955 U	0.00319 U	0.00159 U	0.00156 U	0.00230 U	0.00182 U	0.00188 U	**0.00148 J**
	MW-307-70	10/03/19	PES	PACE	70	-9.5	S	0.0123 UJ	0.00657 U	0.00516 U	0.0123 U	0.00476 U	0.0160 U	0.00791 U	0.00777 U	0.0115 U	0.00903 U	0.00937 U	0.00607 U
	MW-307-75	10/03/19	PES	PACE	75	-14.5	S	0.00119 UJ	0.000632 U	0.000496 U	0.00119 U	0.000458 U	0.00153 U	0.000761 U	0.000748 U	0.00110 U	0.000869 U	0.000902 U	0.000584 U
	MW-307-80	10/03/19	PES	PACE	80	-19.5	S	0.00126 UJ	0.000669 U	0.000526 U	0.00126 U	0.000484 U	0.00162 U	0.000807 U	0.000792 U	0.00117 U	0.000921 U	0.000956 U	0.000619 U
	MW-307-85	10/03/19	PES	PACE	85	-24.5	S	0.00124 UJ	0.000656 U	0.000516 U	0.00124 U	0.000475 U	0.00159 U	0.000790 U	0.000777 U	0.00115 U	0.000903 U	0.000937 U	**0.000962 J**
	MW-2016-85	10/03/19	PES	PACE	85 (dup)	-24.5	S	0.00117 UJ	0.000619 U	0.000486 U	0.00117 U	0.000448 U	0.00150 U	0.000745 U	0.000732 U	0.00108 U	0.000851 U	0.000884 U	**0.000584 J**
MW-309 (-32.0 to -42.0)	MW-309-5	09/19/19	PES	PACE	5	25.4	V	0.00129 U	0.000684 U	0.000537 U	0.00129 U	0.000577 U	0.00166 U	0.000823 U	0.000809 U	0.00119 U	0.000940 U	0.000976 U	**0.00118 J**
	MW-309-10	09/19/19	PES	PACE	10	20.4	S	0.0680 U	0.0360 U	0.0283 U	0.0680 U	0.0261 U	0.0875 U	0.0434 U	0.0426 U	0.0629 U	0.0496 U	0.0514 U	**0.121 J**
	MW-309-13.5	09/19/19	PES	PACE	13.5	16.9	S	0.00132 U	0.000700 U	0.000550 U	0.00132 U	0.00131 U	0.00170 U	0.000843 U	0.000828 U	0.00122 U	0.000962 U	0.000999 U	**0.137**
	MW-309-15	09/19/19	PES	PACE	15	15.4	S	0.0102 U	0.00539 U	0.00424 U	0.0102 U	0.00391 U	0.0131 U	0.00650 U	0.00638 U	0.00942 U	0.00742 U	0.00770 U	**1.45**
	MW-309-20	09/19/19	PES	PACE	20	10.4	S	0.00127 U	0.000674 U	0.000529 U	0.00127 U	0.000542 U	0.00164 U	0.000812 U	0.000798 U	0.00118 U	0.000927 U	0.000962 U	**0.505**
	MW-309-25	09/19/19	PES	PACE	25	5.4	S	0.00128 U	0.000677 U	0.000532 U	0.00128 U	0.000490 U	0.00164 U	0.000815 U	0.000801 U	0.00118 U	0.000931 U	0.000966 U	**0.258**
	MW-309-30	09/19/19	PES	PACE	30	0.4	S	0.00129 U	0.000684 U	0.000537 U	0.00129 U	0.00111 U	0.00166 U	0.000824 U	0.000810 U	0.00119 U	0.000941 U	0.000977 U	**0.00553**
	MW-309-35	09/19/19	PES	PACE	35	-4.6	S	0.00131 U	0.000695 U	0.000546 U	0.00131 U	0.000605 U	0.00169 U	**0.00721**	0.000822 U	0.00121 U	0.000955 U	0.000992 U	**0.000977 J**
	MW-309-40	09/19/19	PES	PACE	40	-9.6	S	0.00131 U	0.000695 U	0.000546 U	0.00131 U	0.000503 U	0.00169 U	**0.170**	0.000822 U	0.00121 U	0.000955 U	0.000992 U	**0.00116 J**
	MW-309-45	09/19/19	PES	PACE	45	-14.6	S	0.00136 U	0.000723 U	0.000568 U	0.00136 U	0.000686 U	0.00175 U	**0.0154**	0.000855 U	0.00126 U	0.000994 U	0.00103 U	0.000668 U
	MW-309-50	09/19/19	PES	PACE	50	-19.6	S	0.00129 U	0.000683 U	0.000536 U	0.00129 U	0.00111 U	0.00166 U	0.000822 U	0.000808 U	0.00119 U	0.000939 U	0.000975 U	0.000632 U
	MW-309-55	09/19/19	PES	PACE	55	-24.6	S	0.00120 U	0.000636 U	0.000500 U	0.00120 U	0.000645 U	0.00154 U	**0.00184 J**	0.000753 U	0.00111 U	0.000875 U	0.000908 U	**0.00151 J**
	MW-309-60	09/19/19	PES	PACE	60	-29.6	S	0.00120 U	0.000640 U	0.000503 U	0.00120 U	0.000714 U	0.00155 U	0.000771 U	0.000757 U	0.00112 U	0.000881 U	0.000914 U	0.000592 U
	MW-309-65	09/19/19	PES	PACE	65	-34.6	S	0.00121 U	0.000644 U	0.000505 U	0.00121 U	0.000593 U	0.00156 U	0.000775 U	0.000762 U	0.00112 U	0.000885 U	0.000919 U	**0.000785 J**
	MW-309-70	09/19/19	PES	PACE	70	-39.6	S	0.00123 U	0.000652 U	0.000512 U	0.00123 U	0.000674 U	0.00158 U	0.000785 U	0.000771 U	0.00114 U	0.000896 U	0.000930 U	**0.000668 J**
	MW-309-75	09/19/19	PES	PACE	75	-44.6	S	0.00117 U	0.000619 U	0.000486 U	0.00117 U	0.000449 U	0.00150 U	0.000746 U	0.000733 U	0.00108 U	0.000852 U	0.000884 U	0.000573 U
MW-311 (-29.0 to -39.0)	MW-311-5	09/18/19	PES	PACE	5	28.1	V	0.00129 U	0.000686 U	0.000539 U	0.00129 U	0.000497 U	0.00166 U	0.000826 U	0.000812 U	0.00120 U	0.000943 U	0.000979 U	0.000634 U
	MW-311-10	09/18/19	PES	PACE	10	23.1	S	0.00124 U	0.000660 U	0.000518 U	0.00124 U	0.000478 U	0.00160 U	0.000794 U	0.000780 U	0.00115 U	0.000907 U	0.000942 U	0.000610 U
	MW-311-15	09/18/19	PES	PACE	15	18.1	S	0.00290 U	0.00154 U	0.00121 U	0.00290 U	0.00111 U	0.00373 U	0.00185 U	0.00182 U	0.00268 U	0.00212 U	0.00220 U	0.00142 U
	MW-311-20	09/18/19	PES	PACE	20	13.1	S	0.00302 U	0.00160 U	0.00126 U	0.00302 U	0.00116 U	0.00389 U	0.00193 U	0.00190 U	0.00280 U	0.00220 U	0.00228 U	0.00148 U
	MW-311-25	09/18/19	PES	PACE	25	8.1	S	0.00536 U	0.00284 U	0.00224 U	0.00536 U	0.00206 U	0.00690 U	0.00343 U	0.00337 U	0.00497 U	0.00391 U	0.00406 U	**0.00620 J**
	MW-311-30	09/18/19	PES	PACE	30	3.1	S	0.00283 U	0.00150 U	0.00118 U	0.00283 U	0.00109 U	0.00365 U	0.00182 U	0.00178 U	0.00263 U	0.00207 U	0.00215 U	**0.00392 J**
	MW-311-35	09/18/19	PES	PACE	35	-1.9	S	0.00252 U	0.00134 U	0.00105 U	0.00252 U	0.000968 U	0.00324 U	0.00161 U	0.00159 U	0.00233 U	0.00184 U	0.00191 U	**0.00252 J**
	MW-311-40	09/18/19	PES	PACE	40	-6.9	S	0.00127 U	0.000672 U	0.000527 U	0.00127 U	0.000486 U	0.00163 U	**0.00613**	0.000795 U	0.00117 U	0.000924 U	0.000959 U	**0.000683 J**
	MW-311-45	09/18/19	PES	PACE	45	-11.9	S	0.00136 U	0.000719 U	0.000565 U	0.00136 U	0.000521 U	0.00174 U	**0.265**	0.000851 U	0.00126 U	0.000989 U	0.00103 U	0.000665 U
	MW-311-50	09/18/19	PES	PACE	50	-16.9	S	0.00126 U	0.000669 U	0.000525 U	0.00126 U	0.000485 U	0.00162 U	**0.232**	0.000792 U	0.00117 U	0.000920 U	0.000955 U	0.000619 U
	MW-311-55	09/18/19	PES	PACE	55	-21.9	S	0.00119 U	0.000633 U	0.000498 U	0.00119 U	0.000459 U	0.00154 U	**0.545**	0.000750 U	0.00111 U	0.000871 U	0.000904 U	0.000586 U
	MW-311-60	09/18/19	PES	PACE	60	-26.9	S	0.00237 U	0.00126 U	0.000986 U	0.00237 U	0.000910 U	0.00305 U	**0.141**	0.00149 U	0.00219 U	0.00173 U	0.00180 U	**0.00131 J**
	MW-311-65	09/18/19	PES	PACE	65	-31.9	S	0.00114 U	0.000607 U	0.000477 U	0.00114 U	0.000440 U	0.00147 U	**0.00153 J**	0.000719 U	0.00106 U	0.000835 U	0.000867 U	0.000562 U
	MW-2005-65	09/18/19	PES	PACE	65 (dup)	-31.9	S	0.00118 U	0.000629 U	0.000494 U	0.00118 U	**0.000755 J**	0.00152 U	0.000757 U	0.000744 U	0.00110 U	0.000864 U	0.000897 U	**0.000641 J**
	MW-311-70	09/18/19	PES	PACE	70	-36.9	S	0.00119 U	0.000631 U	0.000496 U	0.00119 U	**0.000674 J**	0.00153 U	0.000760 U	0.000747 U	0.00110 U	0.000868 U	0.000901 U	0.000584 U
	MW-2007-70	09/18/19	PES	PACE	70 (dup)	-38.3	S	0.00230 U	0.00123 U	0.000959 U	0.00230 U	**0.00158 J**	0.00296 U	0.00147 U	0.00145 U	0.00213 U	0.00168 U	0.00175 U	**0.00168 J**

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
MW-312	MW-312-6	09/16/19	PES	PACE	6	29.6	V	0.00131 U	0.000697 U	0.000547 U	0.00131 U	0.000505 U	0.00169 U	0.000839 U	0.000825 U	0.00122 U	0.000959 U	0.000995 U	0.000645 U
(19.9 to9.9)	MW-312-10	09/16/19	PES	PACE	10	25.6	V	0.00219 U	0.00116 U	0.000913 U	0.00219 U	0.000842 U	0.00281 U	0.00140 U	0.00138 U	0.00203 U	0.00160 U	0.00166 U	**0.00123 J**
	MW-312-15	09/16/19	PES	PACE	15	20.6	S	0.00149 U	0.000792 U	0.000622 U	0.00149 U	0.000574 U	0.00191 U	**0.00114 J**	0.000937 U	0.00138 U	0.00109 U	0.00113 U	**0.00573**
	MW-312-20	09/16/19	PES	PACE	20	15.6	S	0.00117 U	0.000620 U	0.000487 U	0.00117 U	0.000449 U	0.00150 U	0.000747 U	0.000734 U	0.00108 U	0.000853 U	0.000885 U	0.000573 U
	MW-2004-20	09/16/19	PES	PACE	20	15.6	S	0.00125 U	0.000662 U	0.000520 U	0.00125 U	0.000479 U	0.00160 U	0.000797 U	0.000783 U	0.00115 U	0.000910 U	0.000944 U	0.000612 U
	MW-312-25	09/16/19	PES	PACE	25	10.6	S	0.00121 U	0.000641 U	0.000503 U	0.00121 U	0.000464 U	0.00155 U	0.000772 U	0.000758 U	0.00112 U	0.000881 U	0.000915 U	0.000593 U
MW-314	MW-314-6	09/13/19	PES	PACE	6	33.8	V	0.00123 U	0.000651 U	0.000511 U	0.00123 U	0.000471 U	0.00158 U	0.000784 U	0.000770 U	0.00114 U	0.000895 U	0.000929 U	**0.000803 J**
(-28.0 to -38.0)	MW-314-10	09/13/19	PES	PACE	10	29.8	V	0.00123 U	0.000657 U	0.000516 U	0.00123 U	0.000476 U	0.00159 U	0.000791 U	0.000778 U	0.00115 U	0.000904 U	0.000938 U	0.000608 U
	MW-314-15	09/13/19	PES	PACE	15	24.8	V	0.00122 U	0.000645 U	0.000506 U	0.00122 U	0.000467 U	0.00156 U	0.000776 U	0.000763 U	0.00113 U	0.000887 U	0.000920 U	0.000596 U
	MW-314-20	09/13/19	PES	PACE	20	19.8	S	0.00124 U	0.000658 U	0.000516 U	0.00124 U	**0.000729 J**	0.00160 U	**0.00292**	0.000778 U	0.00115 U	0.000904 U	0.000939 U	0.000608 U
	MW-314-25	09/13/19	PES	PACE	25	14.8	S	0.00137 U	0.000728 U	0.000571 U	0.00137 U	0.000527 U	0.00177 U	**0.00456**	0.000861 U	0.00127 U	0.00100 U	0.00104 U	0.000673 U
	MW-2002-25	09/13/19	PES	PACE	25	14.8	S	0.00136 U	0.000723 U	0.000568 U	0.00136 U	0.000524 U	0.00175 U	**0.00211 J**	0.000856 U	0.00126 U	0.000995 U	0.00103 U	0.000669 U
	MW-314-30	09/13/19	PES	PACE	30	9.8	S	0.00134 U	0.000713 U	0.000560 U	0.00134 U	**0.000627 J**	0.00173 U	**0.0481**	0.000843 U	0.00124 U	0.000980 U	0.00102 U	0.000659 U
	MW-314-35	09/13/19	PES	PACE	35	4.8	S	0.00116 U	0.000615 U	0.000483 U	0.00116 U	0.000445 U	0.00149 U	**0.776**	0.000727 U	0.00107 U	0.000845 U	0.000877 U	0.000569 U
	MW-314-40	09/13/19	PES	PACE	40	-0.2	S	0.00120 U	0.000639 U	0.000501 U	0.00120 U	0.000463 U	0.00155 U	**2.55**	0.000756 U	0.00111 U	0.000879 U	0.000912 U	0.000591 U
	MW-314-45	09/13/19	PES	PACE	45	-5.2	S	0.00120 U	0.000634 U	0.000498 U	0.00120 U	0.000459 U	0.00154 U	**0.00457**	0.000750 U	0.00111 U	0.000872 U	0.000905 U	0.000587 U
	MW-314-50	09/13/19	PES	PACE	50	-10.2	S	0.00120 U	0.000638 U	0.000501 U	0.00120 U	**0.000505 J**	0.00155 U	**0.313**	0.000755 U	0.00111 U	0.000877 U	0.000911 U	0.000590 U
	MW-314-55	09/13/19	PES	PACE	55	-15.2	S	0.00130 U	0.000692 U	0.000543 U	0.00130 U	0.000501 U	0.00168 U	**0.406**	0.000819 U	0.00121 U	0.000951 U	0.000988 U	0.000640 U
	MW-314-60	09/13/19	PES	PACE	60	-20.2	S	0.00119 U	0.000634 U	0.000498 U	0.00119 U	0.000459 U	0.00154 U	**0.102**	0.000750 U	0.00111 U	0.000872 U	0.000905 U	0.000586 U
	MW-314-65	09/13/19	PES	PACE	65	-25.2	S	0.00123 U	0.000651 U	0.000511 U	0.00123 U	0.000471 U	0.00158 U	**0.0843**	0.000770 U	0.00114 U	0.000895 U	0.000929 U	0.000602 U
	MW-314-70	09/13/19	PES	PACE	70	-30.2	S	0.0132 U	0.00696 U	0.00547 U	0.0132 U	0.00505 U	0.0169 U	**0.0502**	0.00824 U	0.0122 U	0.00957 U	0.00994 U	0.00644 U
	MW-314-75	09/13/19	PES	PACE	75	-35.2	S	0.00247 U	0.00131 U	0.00103 U	0.00247 U	0.000948 U	0.00317 U	**0.153**	0.00155 U	0.00228 U	0.00180 U	0.00187 U	0.00121 U
	MW-314-80	09/13/19	PES	PACE	80	-40.2	S	0.00161 U	0.000856 U	0.000672 U	0.00161 U	0.000620 U	0.00208 U	**0.139**	0.00101 U	0.00149 U	0.00118 U	0.00122 U	0.000792 U
MW-316	MW-316-5	09/09/19	PES	PACE	5	44.8	V	0.00117 U	0.000620 U	0.000487 U	0.00117 U	0.000580 U	0.00150 U	0.000747 U	0.000734 U	0.00108 U	0.000853 U	0.000886 U	0.000574 U
(-10.0 to -20.0)	MW-316-10	09/09/19	PES	PACE	10	39.8	V	0.00122 U	0.000648 U	0.000509 U	0.00122 U	0.00102 U	0.00157 U	0.000781 U	0.000767 U	0.00113 U	0.000891 U	0.000925 U	0.000600 U
	MW-316-15	09/09/19	PES	PACE	15	34.8	V	0.00121 U	0.000644 U	0.000506 U	0.00121 U	0.000817 U	0.00156 U	0.000776 U	0.000762 U	0.00112 U	0.000886 U	0.000920 U	0.000596 U
	MW-316-20	09/09/19	PES	PACE	20	29.8	V	0.00117 U	0.000618 U	0.000485 U	0.00117 U	0.000702 U	0.00150 U	0.000744 U	0.000731 U	0.00108 U	0.000850 U	0.000882 U	0.000572 U
	MW-316-25	09/09/19	PES	PACE	25	24.8	S	0.00123 U	0.000650 U	0.000511 U	0.00123 U	0.000593 U	0.00158 U	**0.00142 J**	0.000769 U	0.00113 U	0.000894 U	0.000928 U	0.000601 U
	MW-316-30	09/09/19	PES	PACE	30	19.8	S	0.00120 U	0.000636 U	0.000499 U	0.00120 U	0.000984 U	0.00154 U	0.000766 U	0.000752 U	0.00111 U	0.000874 U	0.000908 U	0.000588 U
	MW-316-35	09/09/19	PES	PACE	35	14.8	S	0.00122 U	0.000647 U	0.000508 U	0.00122 U	0.000694 U	0.00157 U	0.000779 U	0.000765 U	0.00113 U	0.000890 U	0.000923 U	0.000598 U
	MW-316-40	09/09/19	PES	PACE	40	9.8	S	0.00123 U	0.000652 U	0.000512 U	0.00123 U	0.000542 U	0.00158 U	0.000785 U	0.000772 U	0.00114 U	0.000897 U	0.000931 U	0.000603 U
	MW-316-45	09/09/19	PES	PACE	45	4.8	S	0.00120 U	0.000637 U	0.000500 U	0.00120 U	0.000461 U	0.00155 U	0.000767 U	0.000754 U	0.00111 U	0.000876 U	0.000910 U	0.000589 U
	MW-316-50	09/09/19	PES	PACE	50	-0.2	S	0.00129 U	0.000686 U	0.000538 U	0.00129 U	0.000850 U	0.00166 U	0.000826 U	0.000811 U	0.00120 U	0.000943 U	0.000979 U	0.000634 U
	MW-316-55	09/09/19	PES	PACE	55	-5.2	S	0.00122 U	0.000649 U	0.000510 U	0.00122 U	0.000744 U	0.00157 U	0.000781 U	0.000768 U	0.00113 U	0.000892 U	0.000926 U	0.000600 U
	MW-316-60	09/09/19	PES	PACE	60	-10.2	S	0.00121 U	0.000644 U	0.000506 U	0.00121 U	0.000467 U	0.00156 U	0.000776 U	0.000762 U	0.00112 U	0.000886 U	0.000920 U	0.000596 U
	MW-316-65	09/10/19	PES	PACE	65	-15.2	S	0.00161 U	0.000857 U	0.000673 U	0.00161 U	0.00140 U	0.00207 U	0.00103 U	0.00101 U	0.00150 U	0.00118 U	0.00122 U	0.000794 U
	MW-2001-65	09/10/19	PES	PACE	65	-15.2	S	0.00128 U	0.000679 U	0.000533 U	0.00128 U	0.000801 U	0.00165 U	0.000817 U	0.000803 U	0.00118 U	0.000933 U	0.000969 U	0.000628 U
	MW-316-70	09/10/19	PES	PACE	70	-20.2	S	0.00122 U	0.000648 U	0.000509 U	0.00122 U	0.00103 U	0.00157 U	0.000781 U	0.000767 U	0.00113 U	0.000892 U	0.000926 U	0.000600 U
MW-319	MW-319-6	09/18/19	PES	PACE	6	25.7	V	0.00125 U	0.000665 U	0.000522 U	0.00125 U	0.000482 U	0.00161 U	0.000801 U	0.000787 U	0.00116 U	0.000914 U	0.000949 U	**0.00182 J**
(-42.8 to -52.8)	MW-319-10	09/18/19	PES	PACE	10	21.7	S	0.00125 U	0.000661 U	0.000519 U	0.00125 U	0.000478 U	0.00160 U	0.000796 U	0.000782 U	0.00115 U	0.000909 U	0.000943 U	0.000611 U
	MW-319-15	09/18/19	PES	PACE	15	16.7	S	0.00124 U	0.000656 U	0.000515 U	0.00124 U	0.000475 U	0.00159 U	0.000790 U	0.000777 U	0.00115 U	0.000903 U	0.000937 U	0.000607 U
	MW-319-20	09/18/19	PES	PACE	20	11.7	S	0.00134 U	0.000710 U	0.000557 U	0.00134 U	0.000514 U	0.00172 U	0.000855 U	0.000840 U	0.00124 U	0.000976 U	0.00101 U	0.000656 U
	MW-319-30	09/18/19	PES	PACE	30	1.7	S	0.00123 U	0.000655 U	0.000514 U	0.00123 U	0.000474 U	0.00159 U	0.000789 U	0.000775 U	0.00114 U	0.000901 U	0.000935 U	0.000606 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
MW-319 (continued)	MW-319-35	09/18/19	PES	PACE	35	-3.3	S	0.00136 U	0.000723 U	0.000567 U	0.00136 U	0.000523 U	0.00175 U	0.000870 U	0.000855 U	0.00126 U	0.000994 U	0.00103 U	0.000668 U
	MW-319-40	09/18/19	PES	PACE	40	-8.3	S	0.00127 U	0.000676 U	0.000531 U	0.00127 U	0.000490 U	0.00164 U	0.000815 U	0.000800 U	0.00118 U	0.000930 U	0.000966 U	0.000626 U
	MW-319-45	09/18/19	PES	PACE	45	-13.3	S	0.00128 U	0.000680 U	0.000534 U	0.00128 U	0.000493 U	0.00165 U	0.000819 U	0.000805 U	0.00119 U	0.000936 U	0.000971 U	0.000629 U
	MW-319-50	09/18/19	PES	PACE	50	-18.3	S	0.00132 U	0.000700 U	0.000549 U	0.00132 U	0.000507 U	0.00170 U	0.000843 U	0.000828 U	0.00122 U	0.000962 U	0.000999 U	0.000647 U
	MW-319-55	09/18/19	PES	PACE	55	-23.3	S	0.00136 U	0.000724 U	0.000568 U	0.00136 U	0.000524 U	0.00176 U	**0.00211 J**	0.000856 U	0.00126 U	0.000995 U	0.00103 U	**0.00373**
	MW-319-60	09/18/19	PES	PACE	60	-28.3	S	0.00128 U	0.000680 U	0.000534 U	0.00128 U	0.000493 U	0.00165 U	**0.00497**	0.000805 U	0.00119 U	0.000936 U	0.000971 U	**0.00761**
	MW-319-65	09/18/19	PES	PACE	65	-33.3	S	0.00138 U	0.000730 U	0.000574 U	0.00138 U	0.000529 U	0.00177 U	**0.0139**	0.000864 U	0.00127 U	0.00100 U	0.00104 U	**0.00104 J**
	MW-319-70	09/18/19	PES	PACE	70	-38.3	S	0.00132 U	0.000698 U	0.000548 U	0.00132 U	0.000506 U	0.00169 U	**0.0396**	0.000826 U	0.00122 U	0.000960 U	0.000997 U	0.000646 U
	MW-2006-70	09/18/19	PES	PACE	70 (dup)	-36.9	S	0.00135 U	0.000718 U	0.000564 U	0.00135 U	0.000520 U	0.00174 U	**0.0434**	0.000850 U	0.00125 U	0.000988 U	0.00103 U	0.000664 U
	MW-319-75	09/18/19	PES	PACE	75	-43.3	S	0.00120 U	0.000635 U	0.000498 U	0.00120 U	0.000460 U	0.00154 U	**0.194**	0.000751 U	0.00111 U	0.000873 U	0.000906 U	0.000587 U
	MW-319-80	09/18/19	PES	PACE	80	-48.3	S	0.00131 U	0.000696 U	0.000547 U	0.00131 U	0.000504 U	0.00169 U	**0.00625**	0.000824 U	0.00122 U	0.000958 U	0.000994 U	0.000644 U
	MW-319-85	09/18/19	PES	PACE	85	-53.3	S	0.00130 U	0.000689 U	0.000541 U	0.00130 U	0.000499 U	0.00167 U	**0.0308**	0.000816 U	0.00120 U	0.000948 U	0.000984 U	0.000638 U
MW-320 (18.6 to 8.6)	MW-320-19	09/29/19	PES	PACE	19	15.1	S	0.0241 U	0.0128 U	0.0101 U	0.0241 U	0.00927 U	0.0311 U	0.0154 U	0.0152 U	0.0223 U	0.0176 U	0.0183 UJ	0.0118 U
	MW-320-27	09/29/19	PES	PACE	27	7.1	S	0.00125 U	0.000664 U	0.000521 U	0.00125 U	0.000481 U	0.00161 U	0.000799 U	0.000785 U	0.00116 U	0.000913 U	0.000947 UJ	0.000614 U
MW-323 (-65.4 to -75.4)	MW-323-10	09/28/19	PES	PACE	10	24.7	V	0.00263 U	0.00140 U	0.00110 U	0.00263 U	0.00425 U	0.00339 U	**0.0168**	0.00166 U	0.00244 U	0.00193 U	0.00200 U	0.00129 U
	MW-2012-10	09/28/19	PES	PACE	10 (dup)	24.7	V	0.00135 U	0.000716 U	0.000562 U	0.00135 U	0.000519 U	0.00174 U	0.000862 U	0.000848 U	0.00125 U	0.000985 U	0.00102 UJ	0.000662 U
	MW-323-15	09/28/19	PES	PACE	15	19.7	S	0.00247 U	0.00131 U	0.00103 U	0.00247 U	0.00260 U	0.00319 U	0.00158 U	0.00155 U	0.00229 U	0.00181 U	0.00188 U	0.00121 U
	MW-323-20	09/28/19	PES	PACE	20	14.7	S	0.00122 U	0.000647 U	0.000508 U	0.00122 U	0.000469 U	0.00157 U	**0.000998 J**	0.000766 U	0.00113 U	0.000890 U	0.000924 U	**0.0194**
	MW-323-25	09/28/19	PES	PACE	25	9.7	S	0.00123 U	0.000653 U	0.000513 U	0.00123 U	0.000669 U	0.00159 U	**0.00136 J**	0.000773 U	0.00114 U	0.000899 U	0.000933 U	0.000604 U
	MW-323-30	09/28/19	PES	PACE	30	4.7	S	0.00229 U	0.00122 U	0.000956 U	0.00229 U	0.00143 U	0.00295 U	**0.00335 J**	0.00144 U	0.00212 U	0.00168 U	0.00174 U	0.00113 U
	MW-323-35	09/28/19	PES	PACE	35	-0.4	S	0.00139 U	0.000736 U	0.000578 U	0.00139 U	0.000952 U	0.00179 U	**0.00305 J**	0.000871 U	0.00129 U	0.00101 U	0.00105 U	0.000681 U
	MW-323-40	09/28/19	PES	PACE	40	-5.4	S	0.00139 U	0.000736 U	0.000578 U	0.00139 U	0.000690 U	0.00178 U	**0.00321 J**	0.000871 U	0.00128 U	0.00101 U	0.00105 U	0.000681 U
	MW-323-45	09/28/19	PES	PACE	45	-10.4	S	0.00138 U	0.000733 U	0.000576 U	0.00138 U	0.000531 U	0.00178 U	0.000883 U	0.000867 U	0.00128 U	0.00101 U	0.00105 U	0.000678 U
	MW-323-50	09/28/19	PES	PACE	50	-15.4	S	0.00124 U	0.000660 U	0.000518 U	0.00124 U	0.000478 U	0.00160 U	**0.00257 J**	0.000780 U	0.00115 U	0.000907 U	0.000942 U	0.000610 U
	MW-323-55	09/28/19	PES	PACE	55	-20.4	S	0.00126 U	0.000668 U	0.000524 U	0.00126 U	0.000484 U	0.00162 U	**0.682**	0.000790 U	0.00117 U	0.000918 U	0.000953 U	0.000618 U
	MW-323-60	09/28/19	PES	PACE	60	-25.4	S	0.00138 U	0.000735 U	0.000577 U	0.00138 U	0.000532 U	0.00178 U	**2.13**	0.000869 U	0.00128 U	0.00101 U	0.00105 U	**0.00146 J**
	MW-2010-60	09/28/19	PES	PACE	60 (dup)	-25.4	S	0.00132 U	0.000699 U	0.000549 U	0.00132 U	0.000506 U	0.00169 U	**1.93**	0.000827 U	0.00122 U	0.000961 U	0.000997 UJ	0.000646 U
	MW-323-65	09/28/19	PES	PACE	65	-30.4	S	0.00130 U	0.000689 U	0.000541 U	0.00130 U	0.000499 U	0.00167 U	**3.03**	0.000815 U	0.00120 U	0.000947 U	0.000983 UJ	0.000637 U
	MW-323-70	09/28/19	PES	PACE	70	-35.4	S	0.182 U	0.0963 U	0.0756 U	0.182 U	0.0698 U	0.234 U	0.116 U	0.114 U	0.168 U	0.133 U	0.138 UJ	0.0892 U
	MW-323-75	09/28/19	PES	PACE	75	-40.4	S	0.00127 U	0.000673 U	0.000529 U	0.00127 U	0.000488 U	0.00163 U	**2.13**	0.000797 U	0.00118 U	0.000926 U	0.000961 UJ	0.000623 U
	MW-323-80	09/28/19	PES	PACE	80	-45.4	S	0.00122 U	0.000648 U	0.000509 U	0.00122 U	0.000469 U	0.00157 U	**0.453**	0.000766 U	0.00113 U	0.000891 U	0.000924 UJ	0.000599 U
	MW-323-85	09/28/19	PES	PACE	85	-50.4	S	0.00129 U	0.000686 U	0.000539 U	0.00129 U	0.000497 U	0.00166 U	**0.794**	0.000812 U	0.00120 U	0.000944 U	0.000980 UJ	0.000635 U
	MW-323-91	09/28/19	PES	PACE	91	-56.4	S	0.00307 U	0.00162 U	0.00127 U	0.00307 U	0.00118 U	0.00393 U	**1.61**	0.00192 U	0.00283 U	0.00223 U	0.00232 UJ	0.00150 U
	MW-323-95	09/28/19	PES	PACE	95	-60.4	S	0.00129 U	0.000687 U	0.000539 U	0.00129 U	0.000498 U	0.00167 U	**0.433**	0.000813 U	0.00120 U	0.000945 U	0.000981 UJ	0.000635 U
	MW-323-99	09/28/19	PES	PACE	99	-64.4	S	0.00125 U	0.000662 U	0.000520 U	0.00125 U	0.000480 U	0.00161 U	**0.325**	0.000784 U	0.00116 U	0.000911 U	0.000946 UJ	0.000613 U
	MW-323-105	09/28/19	PES	PACE	105	-70.4	S	0.00128 U	0.000677 U	0.000531 U	0.00128 U	0.000490 U	0.00164 U	0.000815 U	0.000801 U	0.00118 U	0.000930 U	0.000966 UJ	0.000626 U
	MW-323-110	09/28/19	PES	PACE	110	-75.4	S	0.00264 U	0.00141 U	0.00110 U	0.00264 U	0.00102 U	0.00340 U	**0.0150**	0.00166 U	0.00245 U	0.00193 U	0.00201 UJ	0.00129 U
MW-324 (-32.1 to -42.1)	MW-324-6	09/12/19	PES	PACE	6	28.3	V	0.00121 U	0.000644 U	0.000506 U	0.00121 U	0.000467 U	0.00156 U	0.000776 U	0.000763 U	0.00112 U	0.000886 U	0.000920 U	0.000596 U
	MW-324-10	09/12/19	PES	PACE	10	24.3	V	0.00125 U	0.000663 U	0.000521 U	0.00125 U	**0.000661 J**	0.00161 U	**0.00566**	0.000785 U	0.00116 U	0.000912 U	0.000947 U	0.000614 U
	MW-324-15	09/12/19	PES	PACE	15	19.3	S	0.00118 U	0.000626 U	0.000491 U	0.00118 U	**0.000567 J**	0.00152 U	0.000754 U	0.000740 U	0.00109 U	0.000861 U	0.000893 U	0.000579 U
	MW-324-20	09/12/19	PES	PACE	20	14.3	S	0.00126 U	0.000669 U	0.000525 U	0.00126 U	0.000484 U	0.00162 U	0.000805 U	0.000791 U	0.00117 U	0.000919 U	0.000954 U	0.000618 U
	MW-324-25	09/12/19	PES	PACE	25	9.3	S	0.00128 U	0.000676 U	0.000531 U	0.00128 U	0.000490 U	0.00164 U	**0.0120**	0.000800 U	0.00118 U	0.000930 U	0.000966 U	**0.00114 J**
	MW-324-30	09/12/19	PES	PACE	30	4.3	S	0.00133 U	0.000704 U	0.000553 U	0.00133 U	**0.00112 J**	0.00171 U	**0.0354**	0.000834 U	0.00123 U	0.000969 U	0.00100 U	0.000652 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
MW-324 (continued)	MW-324-35	09/12/19	PES	PACE	35	-0.7	S	0.00129 U	0.000684 U	0.000537 U	0.00129 U	0.000495 U	0.00166 U	**0.000860 J**	0.000809 U	0.00119 U	0.000941 U	0.000977 U	0.000633 U
	MW-324-40	09/12/19	PES	PACE	40	-5.7	S	0.00131 U	0.000693 U	0.000544 U	0.00131 U	0.000502 U	0.00168 U	0.000834 U	0.000819 U	0.00121 U	0.000952 U	0.000989 U	0.000641 U
	MW-324-45	09/12/19	PES	PACE	45	-10.7	S	0.00136 U	0.000721 U	0.000566 U	0.00136 U	0.000522 U	0.00175 U	**0.00905**	0.000853 U	0.00126 U	0.000992 U	0.00103 U	0.000667 U
	MW-324-50	09/12/19	PES	PACE	50	-15.7	S	0.00108 U	0.000573 U	0.000450 U	0.00108 U	0.000415 U	0.00139 U	0.000690 U	0.000678 U	0.00100 U	0.000788 U	0.000818 U	0.000530 U
	MW-324-55	09/12/19	PES	PACE	55	-20.7	S	0.00122 U	0.000649 U	0.000510 U	0.00122 U	0.000470 U	0.00158 U	**0.0143**	0.000768 U	0.00113 U	0.000893 U	0.000927 U	0.000601 U
	MW-324-60	09/12/19	PES	PACE	60	-25.7	S	0.00122 U	0.000649 U	0.000510 U	0.00122 U	0.000470 U	0.00158 U	**0.213**	0.000768 U	0.00113 U	0.000893 U	0.000927 U	0.000601 U
	MW-324-65	09/12/19	PES	PACE	65	-30.7	S	0.00127 U	0.000674 U	0.000529 U	0.00127 U	0.000488 U	0.00163 U	**2.47**	0.000798 U	0.00118 U	0.000927 U	0.000962 U	0.000623 U
	MW-324-70	09/12/19	PES	PACE	70	-35.7	S	0.00133 U	0.000710 U	0.000558 U	0.00133 U	0.000515 U	0.00172 U	**2.15**	0.000841 U	0.00124 U	0.000977 U	0.00101 U	0.000658 U
	MW-324-75	09/12/19	PES	PACE	75	-40.7	S	0.00135 U	0.000719 U	0.000564 U	0.00135 U	0.000520 U	0.00174 U	**1.47**	0.000850 U	0.00125 U	0.000988 U	0.00103 U	0.000665 U
	MW-324-80	09/12/19	PES	PACE	80	-45.7	S	0.00135 U	0.000717 U	0.000563 U	0.00135 U	0.000519 U	0.00174 U	**2.01**	0.000848 U	0.00125 U	0.000986 U	0.00102 U	0.000663 U
MW-326 (-48.7 to -58.7)	MW-326-5	09/09/19	PES	PACE	5	36.3	V	0.00119 U	0.000631 U	0.000496 U	0.00119 U	0.000457 U	0.00153 U	0.000760 U	0.000747 U	0.00110 U	0.000868 U	0.000901 U	**0.00213 J**
	MW-326-10	09/09/19	PES	PACE	10	31.3	V	0.00143 U	0.000762 U	0.000599 U	0.00143 U	0.000553 U	0.00185 U	0.000918 U	0.000902 U	0.00133 U	0.00105 U	0.00109 U	0.000705 U
	MW-326-15	09/09/19	PES	PACE	15	26.3	V	0.00126 U	0.000670 U	0.000526 U	0.00126 U	0.000485 U	0.00163 U	0.000807 U	0.000793 U	0.00117 U	0.000922 U	0.000957 U	0.000620 U
	MW-326-20	09/09/19	PES	PACE	20	21.3	S	0.00126 U	0.000671 U	0.000527 U	0.00126 U	0.000486 U	0.00163 U	0.000808 U	0.000794 U	0.00117 U	0.000922 U	0.000958 U	0.000620 U
	MW-326-25	09/09/19	PES	PACE	25	16.3	S	0.00134 U	0.000711 U	0.000558 U	0.00134 U	0.000515 U	0.00172 U	0.000856 U	0.000841 U	0.00124 U	0.000978 U	0.00102 U	0.000658 U
	MW-326-30	09/09/19	PES	PACE	30	11.3	S	0.00437 U	0.00231 U	0.00181 U	0.00437 U	0.00168 U	0.00562 U	0.00279 U	0.00274 U	0.00404 U	0.00318 U	0.00330 U	0.00214 U
	MW-326-35	09/09/19	PES	PACE	35	6.3	S	0.00134 U	0.000709 U	0.000557 U	0.00134 U	0.000513 U	0.00172 U	0.000853 U	0.000838 U	0.00124 U	0.000975 U	0.00101 U	0.000655 U
	MW-326-40	09/09/19	PES	PACE	40	1.3	S	0.00129 U	0.000683 U	0.000537 U	0.00129 U	0.000495 U	0.00166 U	0.000823 U	0.000809 U	0.00119 U	0.000940 U	0.000976 U	0.000632 U
	MW-326-45	09/09/19	PES	PACE	45	-3.7	S	0.00130 U	0.000690 U	0.000542 U	0.00130 U	**0.000914 J**	0.00167 U	**0.0617**	0.000817 U	0.00120 U	0.000949 U	0.000985 U	0.000638 U
	MW-326-50	09/09/19	PES	PACE	50	-8.7	S	0.00123 U	0.000655 U	0.000514 U	0.00123 U	0.000474 U	0.00159 U	**0.00570**	0.000775 U	0.00114 U	0.000901 U	0.000935 U	0.000606 U
	MW-326-55	09/09/19	PES	PACE	55	-13.7	S	0.00131 U	0.000697 U	0.000547 U	0.00131 U	0.000505 U	0.00169 U	**0.0150**	0.000825 U	0.00122 U	0.000959 U	0.000995 U	0.000645 U
	MW-326-60	09/09/19	PES	PACE	60	-18.7	S	0.00117 U	0.000623 U	0.000489 U	0.00117 U	0.000525 U	0.00151 U	**0.00433**	0.000737 U	0.00109 U	0.000856 U	0.000889 U	0.000576 U
	MW-326-65	09/09/19	PES	PACE	65	-23.7	S	0.00125 U	0.000664 U	0.000522 U	0.00125 U	0.000481 U	0.00161 U	**0.00508**	0.000786 U	0.00116 U	0.000913 U	0.000948 U	0.000614 U
	MW-326-70	09/09/19	PES	PACE	70	-28.7	S	0.00132 U	0.000698 U	0.000548 U	0.00132 U	0.000660 U	0.00169 U	**0.00136 J**	0.000826 U	0.00122 U	0.000960 U	0.000997 U	0.000646 U
	MW-326-75	09/09/19	PES	PACE	75	-33.7	S	0.00131 U	0.000695 U	0.000546 U	0.00131 U	0.000503 U	0.00169 U	0.000836 U	0.000822 U	0.00121 U	0.000955 U	0.000992 U	0.000643 U
	MW-326-80	09/09/19	PES	PACE	80	-38.7	S	0.00128 U	0.000681 U	0.000535 U	0.00128 U	0.000493 U	0.00165 U	0.000820 U	0.000806 U	0.00119 U	0.000937 U	0.000972 U	0.000630 U
	MW-326-85	09/10/19	PES	PACE	85	-43.7	S	0.00126 U	0.000670 U	0.000526 U	0.00126 U	0.000485 U	0.00162 U	0.000806 U	0.000792 U	0.00117 U	0.000921 U	0.000956 U	0.000619 U
	MW-326-90	09/10/19	PES	PACE	90	-48.7	S	0.00127 U	0.000675 U	0.000530 U	0.00127 U	0.000933 U	0.00164 U	0.000812 U	0.000798 U	0.00118 U	0.000928 U	0.000963 U	0.000624 U
	MW-326-95	09/10/19	PES	PACE	95	-53.7	S	0.00121 U	0.000644 U	0.000506 U	0.00121 U	0.000466 U	0.00156 U	0.000775 U	0.000762 U	0.00112 U	0.000885 U	0.000919 U	0.000595 U
	MW-200I-95	09/10/19	PES	PACE	95 (dup)	-53.7	S	0.00123 U	0.000654 U	0.000513 U	0.00123 U	0.000473 U	0.00159 U	0.000787 U	0.000773 U	0.00114 U	0.000899 U	0.000933 U	**0.000891 J**
	MW-326-100	09/10/19	PES	PACE	100	-58.7	S	0.00130 U	0.000692 U	0.000544 U	0.00130 U	0.000715 U	0.00168 U	0.000834 U	0.000819 U	0.00121 U	0.000952 U	0.000988 U	0.000640 U
MW-328 (-36.1 to -46.1)	MW-328-5	09/16/19	PES	PACE	5	23.4	V	0.00128 U	0.000681 U	0.000535 U	0.00128 U	0.000493 U	0.00165 U	0.000820 U	0.000806 U	0.00119 U	0.000937 U	0.000972 U	**0.000952 J**
	MW-328-10	09/16/19	PES	PACE	10	18.4	S	0.00148 U	0.000788 U	0.000618 U	0.00148 U	0.000570 U	0.00191 U	0.000948 U	0.000932 U	0.00137 U	0.00108 U	0.00112 U	0.000728 U
	MW-328-15	09/16/19	PES	PACE	15	13.4	S	0.00133 U	0.000703 U	0.000552 U	0.00133 U	0.000509 U	0.00171 U	0.000847 U	0.000832 U	0.00123 U	0.000967 U	0.00100 U	0.000651 U
	MW-328-20	09/16/19	PES	PACE	20	8.4	S	0.00129 U	0.000684 U	0.000537 U	0.00129 U	0.000496 U	0.00166 U	**0.0304**	0.000810 U	0.00119 U	0.000941 U	0.000977 U	0.000633 U
	MW-328-30	09/16/19	PES	PACE	30	-1.6	S	0.0255 U	0.0135 U	0.0106 U	0.0255 U	0.00978 U	0.0327 U	0.0163 U	0.0160 U	0.0236 U	0.0186 U	0.0192 U	0.0125 U
	MW-328-35	09/16/19	PES	PACE	35	-6.6	S	0.00138 U	0.000736 U	0.000578 U	0.00138 U	0.000533 U	0.00178 U	0.000886 U	0.000872 U	0.00129 U	0.00101 U	0.00105 U	0.000681 U
	MW-328-40	09/16/19	PES	PACE	40	-11.6	S	0.00314 U	0.00167 U	0.00131 U	0.00314 U	0.00121 U	0.00405 U	0.00201 U	0.00197 U	0.00291 U	0.00229 U	0.00238 U	0.00154 U
	MW-328-45	09/16/19	PES	PACE	45	-16.6	S	0.00133 U	0.000707 U	0.000555 U	0.00133 U	0.000512 U	0.00171 U	0.000851 U	0.000836 U	0.00123 U	0.000972 U	0.00101 U	0.000654 U
	MW-328-50	09/16/19	PES	PACE	50	-21.6	S	0.0397 U	0.0210 U	0.0165 U	0.0397 U	0.0152 U	0.0510 U	0.0253 U	0.0248 U	0.0367 U	0.0290 U	0.0300 U	0.0195 U
	MW-328-55	09/16/19	PES	PACE	55	-26.6	S	0.00129 U	0.000682 U	0.000536 U	0.00129 U	**0.000538 J**	0.00165 U	0.000821 U	0.000807 U	0.00119 U	0.000938 U	0.000974 U	0.000631 U
	MW-328-60	09/16/19	PES	PACE	60	-31.6	S	0.00130 U	0.000689 U	0.000541 U	0.00130 U	0.000499 U	0.00167 U	0.000830 U	0.000815 U	0.00120 U	0.000947 U	0.000984 U	0.000637 U
	MW-328-65	09/16/19	PES	PACE	65	-36.6	S	0.00126 U	0.000668 U	0.000525 U	0.00126 U	0.000484 U	0.00162 U	**0.00706**	0.000791 U	0.00117 U	0.000919 U	0.000954 U	0.000618 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
MW-328 (continued)	MW-328-70	09/16/19	PES	PACE	70	-41.6	S	0.00130 U	0.000690 U	0.000542 U	0.00130 U	0.000500 U	0.00167 U	**0.0265**	0.000816 U	0.00120 U	0.000949 U	0.000985 U	0.000638 U
	MW-328-75	09/16/19	PES	PACE	75	-46.6	S	0.00126 U	0.000668 U	0.000525 U	0.00126 U	0.000484 U	0.00162 U	**0.0192**	0.000791 U	0.00117 U	0.000919 U	0.000954 U	0.000618 U
	MW-328-80	09/16/19	PES	PACE	80	-51.6	S	0.00142 U	0.000756 U	0.000594 U	0.00142 U	0.000547 U	0.00183 U	**0.0204**	0.000894 U	0.00132 U	0.00104 U	0.00108 U	0.000699 U
MW-329 (-69.0 to -79.0)	MW-329-5	09/12/19	PES	PACE	5	24.3	V	0.00115 U	0.000612 U	0.000481 U	0.00115 U	0.000444 U	0.00149 U	**0.00156 J**	0.000725 U	0.00107 U	0.000842 U	0.000874 U	0.000566 U
	MW-329-10	09/12/19	PES	PACE	10	19.3	S	0.00114 U	0.000603 U	0.000473 U	0.00114 U	0.000437 U	0.00146 U	**0.000902 J**	0.000713 U	0.00105 U	0.000829 U	0.000860 U	0.000558 U
	MW-329-15	09/12/19	PES	PACE	15	14.3	S	0.00119 U	0.000629 U	0.000494 U	0.00119 U	**0.000572 J**	0.00153 U	0.000758 U	0.000744 U	0.00110 U	0.000865 U	0.000898 U	0.000582 U
	MW-329-20	09/12/19	PES	PACE	20	9.3	S	0.00149 U	0.000792 U	0.000622 U	0.00149 U	0.000574 U	0.00192 U	0.000954 U	0.000937 U	0.00138 U	0.00109 U	0.00113 U	**0.00123 J**
	MW-329-25	09/12/19	PES	PACE	25	4.3	S	0.00155 U	0.000821 U	0.000645 U	0.00155 U	0.000595 U	0.00199 U	0.000989 U	0.000972 U	0.00143 U	0.00113 U	0.00117 U	0.000760 U
	MW-329-30	09/12/19	PES	PACE	30	-0.7	S	0.00133 U	0.000708 U	0.000556 U	0.00133 U	0.000522 U	0.00172 U	0.000852 U	0.000837 U	0.00124 U	0.000973 U	0.00101 U	0.000655 U
	MW-329-35	09/12/19	PES	PACE	35	-5.7	S	0.00132 U	0.000702 U	0.000551 U	0.00132 U	0.000509 U	0.00170 U	0.000846 U	0.000831 U	0.00123 U	0.000966 U	0.00100 U	0.000649 U
	MW-329-40	09/12/19	PES	PACE	40	-10.7	S	0.00133 U	0.000706 U	0.000555 U	0.00133 U	0.000512 U	0.00171 U	0.000850 U	0.000836 U	0.00123 U	0.000971 U	0.00101 U	0.000653 U
	MW-329-45	09/12/19	PES	PACE	45	-15.7	S	0.00129 U	0.000683 U	0.000537 U	0.00129 U	0.000495 U	0.00166 U	0.000823 U	0.000809 U	0.00119 U	0.000940 U	0.000976 U	0.000632 U
	MW-329-50	09/12/19	PES	PACE	50	-20.7	S	0.00133 U	0.000706 U	0.000555 U	0.00133 U	0.000512 U	0.00171 U	0.000851 U	0.000836 U	0.00123 U	0.000971 U	0.00101 U	0.000653 U
	MW-2003-50	09/12/19	PES	PACE	50 (dup)	-20.7	S	0.00118 U	0.000626 U	0.000492 U	0.00118 U	0.000453 U	0.00152 U	0.000754 U	0.000741 U	0.00109 U	0.000861 U	0.000894 U	0.000579 U
	MW-329-55	09/12/19	PES	PACE	55	-25.7	S	0.00125 U	0.000661 U	0.000519 U	0.00125 U	0.000479 U	0.00160 U	0.000797 U	0.000783 U	0.00115 U	0.000910 U	0.000944 U	0.000612 U
	MW-329-60	09/12/19	PES	PACE	60	-30.7	S	0.00126 U	0.000670 U	0.000526 U	0.00126 U	0.000485 U	0.00163 U	**0.00179 J**	0.000793 U	0.00117 U	0.000922 U	0.000957 U	0.000620 U
	MW-329-65	09/12/19	PES	PACE	65	-35.7	S	0.00126 U	0.000670 U	0.000526 U	0.00126 U	0.000485 U	0.00162 U	**0.0140**	0.000792 U	0.00117 U	0.000921 U	0.000956 U	0.000619 U
	MW-329-70	09/12/19	PES	PACE	70	-40.7	S	0.00126 U	0.000668 U	0.000524 U	0.00126 U	0.000484 U	0.00162 U	**0.0403**	0.000790 U	0.00117 U	0.000918 U	0.000953 U	0.000618 U
	MW-329-75	09/12/19	PES	PACE	75	-45.7	S	0.00124 U	0.000656 U	0.000516 U	0.00124 U	0.000475 U	0.00159 U	**0.0637**	0.000777 U	0.00115 U	0.000903 U	0.000937 U	0.000607 U
	MW-329-80	09/12/19	PES	PACE	80	-50.7	S	0.00131 U	0.000696 U	0.000547 U	0.00131 U	0.000504 U	0.00169 U	**0.103**	0.000824 U	0.00121 U	0.000957 U	0.000994 U	0.000644 U
	MW-329-85	09/12/19	PES	PACE	85	-55.7	S	0.00126 U	0.000670 U	0.000526 U	0.00126 U	0.000485 U	0.00163 U	**0.261**	0.000793 U	0.00117 U	0.000921 U	0.000956 U	0.000620 U
	MW-329-90	09/12/19	PES	PACE	90	-60.7	S	0.00127 U	0.000674 U	0.000529 U	0.00127 U	0.000488 U	0.00163 U	**0.136**	0.000797 U	0.00118 U	0.000926 U	0.000962 U	0.000623 U
	MW-329-95	09/12/19	PES	PACE	95	-65.7	S	0.00128 U	0.000680 U	0.000534 U	0.00128 U	0.000493 U	0.00165 U	**0.0246**	0.000805 U	0.00119 U	0.000936 U	0.000971 U	0.000629 U
	MW-329-100	09/12/19	PES	PACE	100	-70.7	S	0.00129 U	0.000682 U	0.000536 U	0.00129 U	0.000494 U	0.00166 U	**0.0119**	0.000807 U	0.00119 U	0.000938 U	0.000974 U	0.000631 U
	MW-329-105	09/12/19	PES	PACE	105	-75.7	S	0.00119 U	0.000631 U	0.000495 U	0.00119 U	0.000457 U	0.00153 U	**0.00860**	0.000746 U	0.00110 U	0.000868 U	0.000901 U	0.000583 U
	MW-329-110	09/12/19	PES	PACE	110	-80.7	S	0.00118 U	0.000626 U	0.000492 U	0.00118 U	0.000453 U	0.00152 U	0.000754 U	0.000741 U	0.00109 U	0.000861 U	0.000894 U	0.000579 U
MW-330	MW-330-6	04/20/20	PES	PACE	6	46.0	V	0.00102 U	0.000239 U	0.000695 U	0.00193 U	0.00117 U	0.00494 UJ	0.000834 U	0.000860 U	0.000852 U	0.000823 U	0.00183 U	0.000837 U
	MW-330-10	04/20/20	PES	PACE	10	42.0	V	0.000991 U	0.000232 U	0.000675 U	0.00188 U	0.00114 U	0.00480 UJ	0.000810 U	0.000835 U	0.000828 U	0.000800 U	0.00178 U	0.000813 U
	MW-330-11.5	04/20/20	PES	PACE	11.5	40.5	V	0.00105 U	0.000245 U	0.000713 U	0.00198 U	0.00120 U	0.00507 UJ	0.000856 U	0.000883 U	0.000874 U	0.000845 U	0.00188 U	0.000859 U
	MW-330-16	04/20/20	PES	PACE	16	36.0	V	0.00102 U	0.000239 U	0.000695 U	0.00193 U	0.00117 U	0.00494 UJ	0.000834 U	0.000860 U	0.000852 U	0.000824 U	0.00183 U	0.000837 U
	MW-330-21.5	04/20/20	PES	PACE	21.5	30.5	S	0.000956 U	0.000224 U	0.000652 U	0.00181 U	0.00110 U	0.00463 UJ	0.000782 U	0.000806 U	0.000799 U	0.000772 U	0.00171 U	0.000785 U
	MW-330-27	04/20/20	PES	PACE	27	25.0	S	0.000965 U	0.000226 U	0.000658 U	0.00183 U	0.00111 U	0.00468 UJ	0.000789 U	0.000814 U	0.000806 U	0.000779 U	0.00173 U	0.000792 U
	MW-330-32	04/20/20	PES	PACE	32	20.0	S	0.000967 U	0.000226 U	0.000659 U	0.00183 U	0.00111 U	0.00469 UJ	0.000791 U	0.000815 U	0.000808 U	0.000781 U	0.00173 U	0.000794 U
	MW-330-38	04/20/20	PES	PACE	38	14.0	S	0.000966 U	0.000226 U	0.000658 U	0.00183 U	0.00111 U	0.00468 UJ	0.000790 U	0.000814 U	0.000807 U	0.000780 U	0.00173 U	0.000793 U
	MW-330-42	04/20/20	PES	PACE	42	10.0	S	0.000940 U	0.000220 U	0.000641 U	0.00178 U	0.00108 U	0.00455 UJ	0.000768 U	0.000793 U	0.000785 U	0.000759 U	0.00169 U	0.000772 U
	MW-330-47	04/20/20	PES	PACE	47	5.0	S	0.00102 U	0.000238 U	0.000693 U	0.00192 U	0.00117 U	0.00492 UJ	0.000831 U	0.000857 U	0.000849 U	0.000821 U	0.00182 U	0.000834 U
	MW-330-52	04/20/20	PES	PACE	52	0.0	S	0.000986 U	0.000231 U	0.000672 U	0.00187 U	0.00113 U	0.00477 UJ	0.000806 U	0.000831 U	0.000823 U	0.000796 U	0.00177 U	0.000809 U
	MW-330-58	04/20/20	PES	PACE	58	-6.0	S	0.000977 U	0.000228 U	0.000666 U	0.00185 U	0.00112 U	0.00473 UJ	0.000799 U	0.000824 U	0.000816 U	0.000789 U	0.00175 U	0.000802 U
	MW-330-62	04/20/20	PES	PACE	62	-10.0	S	0.000986 U	0.000231 U	0.000672 U	0.00187 U	0.00113 U	0.00478 UJ	0.000806 U	0.000831 U	0.000824 U	0.000796 U	0.00177 U	0.000809 U
MW-331	MW-331-7	04/17/20	PES	PACE	7	24.2	V	0.00139 U	0.000324 U	0.000945 UJ	0.00262 U	0.00159 U	0.00672 U	0.00113 U	0.00117 U	0.00116 U	0.00112 U	0.00249 U	**0.133**
	MW-331-11	04/17/20	PES	PACE	11	20.2	S	0.00804 U	0.00188 U	0.00549 U	0.0152 U	0.00923 U	0.0390 U	0.00658 U	0.00679 U	0.00672 U	0.00650 U	0.0144 U	**3.01**
	MW-331-16	04/17/20	PES	PACE	16	15.2	S	0.00106 U	0.000248 U	0.000722 U	0.00201 U	0.00122 U	0.00513 U	0.000866 U	0.000894 U	0.000885 U	0.000856 U	0.00190 U	**0.0752**
	MW-331-20	04/17/20	PES	PACE	20	11.2	S	0.00104 U	0.000243 U	0.000707 U	0.00196 U	0.00119 U	0.00503 U	0.000848 U	0.000875 U	0.000867 U	0.000838 U	0.00186 U	**0.00404**

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
MW-331 (continued)	MW-331-29.5	04/17/20	PES	PACE	29.5	1.7	S	0.00104 U	0.000243 U	0.000709 U	0.00197 U	0.00119 U	0.00504 U	0.000851 U	0.000877 U	0.000869 U	0.000840 U	0.00187 U	**0.00189 J**
	MW-331-35	04/17/20	PES	PACE	35	-3.8	S	0.00106 U	0.000248 U	0.000723 U	0.00201 U	0.00122 U	0.00514 U	0.000867 U	0.000894 U	0.000886 U	0.000856 U	0.00190 U	0.000870 U
	MW-2018-35	04/17/20	PES	PACE	35 (dup)	-3.8	S	0.00108 U	0.000252 U	0.000735 U	0.00204 U	0.00124 U	0.00523 U	0.000882 U	0.000910 U	0.000901 U	0.000871 U	0.00193 U	0.000885 U
	MW-331-40	04/17/20	PES	PACE	40	-8.8	S	0.00108 U	0.000253 U	0.000738 U	0.00205 U	0.00124 U	0.00525 U	0.000886 U	0.000913 U	0.000905 U	0.000875 U	0.00194 U	0.000889 U
	MW-331-45	04/17/20	PES	PACE	45	-13.8	S	0.00108 U	0.000253 U	0.000736 U	0.00204 U	0.00124 U	0.00523 U	0.000883 U	0.000910 U	0.000902 U	0.000872 U	0.00194 U	0.000886 U
MW-332	MW-332-7	04/17/20	PES	PACE	7	29.3	V	0.00101 U	0.000235 U	0.000686 UJ	0.00191 U	0.00116 U	0.00488 U	0.000823 U	0.000849 U	0.000841 U	0.000813 U	0.00181 U	**0.00157 J**
	MW-332-11	04/17/20	PES	PACE	11	25.3	V	0.00106 U	0.000247 U	0.000721 UJ	0.00200 U	0.00121 U	0.00512 U	0.000864 U	0.000892 U	0.000883 U	0.000854 U	0.00190 U	**0.00137 J**
	MW-332-16	04/17/20	PES	PACE	16	20.3	S	0.00104 U	0.000242 U	0.000706 UJ	0.00196 U	0.00119 U	0.00502 U	0.000847 U	0.000873 U	0.000865 U	0.000836 U	0.00186 U	0.000850 U
	MW-332-20	04/17/20	PES	PACE	20	16.3	S	0.00105 U	0.000246 U	0.000717 UJ	0.00199 U	0.00121 U	0.00510 U	0.000860 U	0.000887 U	0.000879 U	0.000850 U	0.00189 U	0.000864 U
	MW-332-25	04/17/20	PES	PACE	25	11.3	S	0.00109 U	0.000255 U	0.000743 UJ	0.00206 U	0.00136 U	0.00528 U	0.000891 U	0.000919 U	0.000910 U	0.000880 U	0.00195 U	0.000894 U
	MW-332-30	04/17/20	PES	PACE	30	6.3	S	0.00111 U	0.000260 U	0.000759 UJ	0.00211 U	0.00128 U	0.00539 U	0.000910 U	0.000938 U	0.000930 U	0.000899 U	0.00200 U	0.000914 U
MW-334	MW-334-6	04/16/20	PES	PACE	6	25.4	V	0.00109 U	0.000255 U	0.000743 UJ	0.00207 U	0.00125 U	0.00528 U	0.000892 U	0.000920 U	0.000911 U	0.000881 U	0.00196 U	0.000895 U
	MW-334-10	04/16/20	PES	PACE	10	21.4	V	0.00109 U	**0.00224 J**	0.000744 UJ	0.00207 U	0.00125 U	0.00529 U	0.000893 U	0.000921 U	0.000912 U	0.000882 U	0.00196 U	**0.00150 J**
	MW-334-13	04/16/20	PES	PACE	13	18.4	S	0.00808 U	**0.0633**	0.00552 UJ	0.0153 U	0.00927 U	0.0392 U	0.00661 U	0.00682 U	0.00675 U	0.00653 U	0.0145 U	0.00664 U
	MW-334-17	04/16/20	PES	PACE	17	14.4	S	0.000928 U	**0.000622 J**	0.000632 UJ	0.00176 U	0.00131 U	0.00450 U	0.000759 U	0.000782 U	0.000775 U	0.000749 U	0.00166 U	**0.00116 J**
	MW-334-23	04/16/20	PES	PACE	23	8.4	S	0.00107 U	0.000250 U	0.000728 UJ	0.00202 U	0.00123 U	0.00518 U	0.000874 U	0.000901 U	0.000893 U	0.000863 U	0.00192 U	0.000877 U
	MW-334-28	04/16/20	PES	PACE	28	3.4	S	0.00106 U	0.000247 U	0.000721 UJ	0.00200 U	0.00121 U	0.00512 U	0.000865 U	0.000892 U	0.000883 U	0.000854 U	0.00190 U	0.000868 U
	MW-334-35	04/16/20	PES	PACE	35	-3.6	S	0.00114 U	0.000265 U	0.000774 UJ	0.00215 U	0.00130 U	0.00550 U	0.000928 U	0.000957 U	0.000948 U	0.000916 U	0.00204 U	0.000932 U
	MW-334-40	04/16/20	PES	PACE	40	-8.6	S	0.00116 U	0.000271 U	0.000790 UJ	0.00220 U	0.00133 U	0.00562 U	0.000948 U	0.000978 U	0.000969 U	0.000936 U	0.00208 U	0.000952 U
	MW-334-45.5	04/16/20	PES	PACE	45.5	-14.1	S	0.00109 U	0.000255 U	0.000745 UJ	0.00207 U	0.00125 U	0.00529 U	0.000893 U	0.000921 U	0.000912 U	0.000882 U	0.00196 U	0.000897 U
	MW-334-50	04/16/20	PES	PACE	50	-18.6	S	0.000994 U	0.000232 U	0.000677 UJ	0.00188 U	0.00114 U	0.00481 U	0.000812 U	0.000838 U	0.000830 U	0.000802 U	0.00178 U	0.000816 U
	MW-334-54.5	04/16/20	PES	PACE	54.5	-23.1	S	0.00111 U	0.000260 U	0.000757 UJ	0.00210 U	0.00127 U	0.00538 U	0.000908 U	0.000937 U	0.000928 U	0.000897 U	0.00199 U	0.000912 U
	MW-334-60	04/16/20	PES	PACE	60	-28.6	S	0.00102 U	0.000239 U	0.000697 UJ	0.00194 U	0.00117 U	0.00495 U	0.000836 U	0.000862 U	0.000854 U	0.000826 U	0.00183 U	0.000839 U
	MW-334-63	04/16/20	PES	PACE	63	-31.6	S	0.00107 U	0.000251 U	0.000732 UJ	0.00203 U	0.00157 U	0.00520 U	0.000878 U	0.000905 U	0.000897 U	0.000867 U	0.00193 U	0.000881 U
MW-336	MW-336-7	04/22/20	PES	PACE	7	26.7	V	0.00100 U	0.000234 U	0.000683 U	0.00190 U	0.00115 U	0.00485 UJ	0.000819 U	0.000845 U	0.000837 U	0.000809 U	0.00180 U	0.000822 U
	MW-336-11.5	04/22/20	PES	PACE	11.5	22.2	V	0.00107 U	0.000250 U	0.000729 U	0.00202 U	0.00123 U	0.00518 UJ	0.000874 U	0.000901 U	0.000893 U	0.000863 U	0.00192 U	0.000878 U
	MW-2019-11.5	04/22/20	PES	PACE	11.5 (dup)	22.2	V	0.00110 U	**0.000423 J**	0.000746 U	0.00207 U	0.00126 U	0.00530 U	0.000895 U	0.000923 U	0.000915 U	0.000884 U	0.00196 U	0.000899 U
	MW-336-14.5	04/22/20	PES	PACE	14.5	19.2	V	0.00115 U	0.000269 U	0.000784 U	0.00218 U	0.00132 U	0.00558 UJ	0.000941 U	0.000970 U	0.000961 U	0.000929 U	0.00206 U	0.000945 U
	MW-336-20	04/22/20	PES	PACE	20	13.7	S	0.00110 U	0.000257 U	0.000749 U	0.00208 U	0.00126 U	0.00533 UJ	0.000899 U	0.000927 U	0.000918 U	0.000888 U	0.00197 U	0.000902 U
	MW-336-25	04/22/20	PES	PACE	25	8.7	S	0.00148 U	0.000346 U	0.00101 U	0.00280 U	0.00170 U	0.00716 UJ	0.00121 U	0.00125 U	0.00123 U	0.00119 U	0.00265 U	0.00121 U
	MW-336-30	04/22/20	PES	PACE	30	3.7	S	0.00137 U	0.000320 U	0.000932 U	0.00259 U	0.00157 U	0.00662 UJ	0.00112 U	0.00115 U	0.00114 U	0.00110 U	0.00245 U	0.00112 U
	MW-336-35	04/22/20	PES	PACE	35	-1.3	S	0.00110 U	0.000258 U	0.000751 U	0.00209 U	0.00126 U	0.00534 UJ	**0.00302 J**	0.000929 U	0.000920 U	0.000890 U	0.00198 U	0.000904 U
	MW-336-40	04/22/20	PES	PACE	40	-6.3	S	0.00108 U	0.000253 U	0.000738 U	0.00205 U	0.00124 U	0.00524 U	0.000885 U	0.000913 U	0.000904 U	0.000874 U	0.00194 U	0.000889 U
	MW-336-45	04/22/20	PES	PACE	45	-11.3	S	0.00119 U	0.000279 U	0.000813 U	0.00226 U	0.00137 U	0.00578 U	**0.0159**	0.00101 U	0.000996 U	0.000963 U	0.00214 U	0.000979 U
	MW-336-51	04/22/20	PES	PACE	51	-17.3	S	0.00103 U	0.000242 U	0.000705 U	0.00196 U	0.00119 U	0.00501 U	**0.00694**	0.000872 U	0.000863 U	0.000835 U	0.00185 U	0.000848 U
	MW-336-55	04/22/20	PES	PACE	55	-21.3	S	0.00103 U	0.000240 U	0.000699 U	0.00194 U	0.00118 U	0.00497 U	**0.0138**	0.000865 U	0.000857 U	0.000828 U	0.00184 U	0.000842 U
	MW-336-60	04/22/20	PES	PACE	60	-26.3	S	0.00105 U	0.000246 U	0.000718 U	0.00200 U	0.00121 U	0.00511 U	**0.0379**	0.000888 U	0.000880 U	0.000851 U	0.00189 U	0.000865 U
	MW-336-65	04/22/20	PES	PACE	65	-31.3	S	0.00105 U	0.000245 U	0.000714 U	0.00198 U	0.00120 U	0.00507 U	**0.0419**	0.000883 U	0.000875 U	0.000846 U	0.00188 U	0.000860 U
	MW-336-69	04/22/20	PES	PACE	69	-35.3	S	0.00112 U	0.000261 U	0.000761 U	0.00211 U	0.00128 U	0.00541 U	**0.0743**	0.000941 U	0.000932 U	0.000901 U	0.00200 U	0.000916 U
	MW-336-74.5	04/22/20	PES	PACE	74.5	-40.8	S	0.00105 U	0.000244 U	0.000712 U	0.00198 U	0.00120 U	0.00506 U	**0.0517**	0.000881 U	0.000873 U	0.000844 U	0.00187 U	0.000858 U
	MW-336-79	04/22/20	PES	PACE	79	-45.3	S	0.00108 U	0.000252 U	0.000734 U	0.00204 U	0.00124 U	0.00522 U	**0.0673**	0.000908 U	0.000900 U	0.000870 U	0.00193 U	0.000884 U
	MW-336-85	04/22/20	PES	PACE	85	-51.3	S	0.00108 U	**0.000523 J**	0.000736 U	0.00204 U	0.00124 U	0.00523 U	**0.0560**	0.000910 U	0.000901 U	0.000871 U	0.00193 U	0.000886 U
	MW-2021-85	05/04/20	PES	PACE	85 (dup)	-51.3	S	0.00103 U	0.000242 U	0.000705 U	0.00196 U	0.00119 U	0.00501 U	**0.00774**	0.000871 U	0.000863 U	0.000835 U	0.00185 U	0.000848 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
MW-336 (continued)	MW-336-90	04/22/20	PES	PACE	90	-56.3	S	0.00108 U	**0.000434 J**	0.000738 U	0.00205 U	0.00124 U	0.00524 U	**0.0382**	0.000913 U	0.000904 U	0.000874 U	0.00194 U	0.000889 U
	MW-336-95	04/22/20	PES	PACE	95	-61.3	S	0.00108 U	**0.000517 J**	0.000735 U	0.00204 U	0.00124 U	0.00523 U	0.000882 U	0.000910 U	0.000901 U	0.000871 U	0.00193 U	0.000886 U
	MW-2020-95	04/22/20	PES	PACE	95 (dup)	-61.3	S	0.00107 U	**0.000512 J**	0.000729 U	0.00202 U	0.00123 U	0.00518 U	0.000874 U	0.000901 U	0.000893 U	0.000863 U	0.00192 U	0.000878 U
MW-338	MW-338-10	05/01/20	PES	PACE	10	17.8	S	0.00109 U	0.000255 U	0.000742 U	0.00206 U	0.00125 U	0.00528 U	0.000890 U	0.000918 U	0.000910 U	0.000879 U	0.00195 U	0.000894 U
	MW-338-15	05/01/20	PES	PACE	15	12.8	S	0.00119 U	0.000278 U	0.000809 U	0.00225 U	0.00136 U	0.00575 U	0.000971 U	0.00100 U	0.000992 U	0.000959 U	0.00213 U	0.000975 U
	MW-338-20	05/01/20	PES	PACE	20	7.8	S	0.00104 U	0.000243 U	0.000709 U	0.00197 U	0.00119 U	0.00504 U	0.000851 U	0.000877 U	0.000869 U	0.000840 U	0.00187 U	0.000854 U
	MW-338-23	05/01/20	PES	PACE	23	4.8	S	0.00114 U	0.000267 U	0.000778 U	0.00216 U	0.00131 U	0.00553 U	0.000933 U	0.000962 U	0.000953 U	0.000921 U	0.00205 U	0.000937 U
	MW-338-28	05/01/20	PES	PACE	28	-0.2	S	0.00113 U	0.000264 U	0.000770 U	0.00214 U	0.00130 U	0.00547 U	0.000923 U	0.000952 U	0.000943 U	0.000912 U	0.00202 U	0.000927 U
	MW-338-34	05/01/20	PES	PACE	34	-6.2	S	0.00100 U	0.000235 U	0.000684 U	0.00190 U	0.00115 U	0.00486 U	0.000820 U	0.000846 U	0.000838 U	0.000810 U	0.00180 U	0.000824 U
	MW-338-39	05/01/20	PES	PACE	39	-11.2	S	0.00109 U	0.000254 U	0.000741 U	0.00206 U	0.00125 U	0.00527 U	0.000889 U	0.000917 U	0.000908 U	0.000878 U	0.00195 U	0.000893 U
	MW-338-41	05/01/20	PES	PACE	41	-13.2	S	0.00111 U	0.000259 U	0.000754 U	0.00210 U	0.00127 U	0.00536 U	0.000905 U	0.000933 U	0.000925 U	0.000894 U	0.00198 U	0.000909 U
	MW-338-45	05/01/20	PES	PACE	45	-17.2	S	0.00110 U	0.000256 U	0.000747 U	0.00208 U	0.00126 U	0.00531 U	0.000896 U	0.000924 U	0.000916 U	0.000885 U	0.00197 U	0.000900 U
	MW-338-51	05/01/20	PES	PACE	51	-23.2	S	0.00111 U	0.000260 U	0.000758 U	0.00211 U	0.00128 U	0.00539 U	0.000910 U	0.000938 U	0.000930 U	0.000899 U	0.00200 U	0.000913 U
	MW-338-55	05/01/20	PES	PACE	55	-27.2	S	0.00103 U	0.000241 U	0.000703 U	0.00195 U	0.00118 U	0.00499 U	0.000843 U	0.000869 U	0.000861 U	0.000832 U	0.00185 U	0.000846 U
MW-341	MW-341-85	05/04/20	PES	PACE	85	-56.6	S	0.00102 U	0.000239 U	0.000695 U	0.00193 U	0.00117 U	0.00494 U	**0.00626**	0.000860 U	0.000852 U	0.000824 U	0.00183 U	0.000837 U
	MW-341-90	05/04/20	PES	PACE	90	-61.6	S	0.00101 U	0.000236 U	0.000688 U	0.00191 U	0.00116 U	0.00489 U	**0.0179**	0.000852 U	0.000844 U	0.000816 U	0.00181 U	0.000829 U
	MW-341-95	05/04/20	PES	PACE	95	-66.6	S	0.00105 U	0.000245 U	0.000713 U	0.00198 U	0.00120 U	0.00507 U	**0.0692**	0.000882 U	0.000874 U	0.000845 U	0.00188 U	0.000859 U
	MW-341-99	05/04/20	PES	PACE	99	-70.6	S	0.00105 U	0.000246 U	0.000718 U	0.00199 U	0.00121 U	0.00510 U	**0.0587**	0.000888 U	0.000879 U	0.000850 U	0.00189 U	0.000864 U
	MW-341-104	05/04/20	PES	PACE	104	-75.6	S	0.00107 U	0.000250 U	0.000730 U	0.00203 U	0.00123 U	0.00519 U	**0.0514**	0.000903 U	0.000895 U	0.000865 U	0.00192 U	0.000879 U
MW-343	MW-343-5	04/13/20	PES	PACE	5	22.6	V	0.00101 U	0.000237 U	0.000691 U	0.00192 U	0.00116 U	0.00491 U	0.000829 U	0.000855 U	0.000847 U	0.000819 U	0.00182 U	**0.0348**
	MW-343-10	04/13/20	PES	PACE	10	17.6	S	0.00106 U	0.000249 U	0.000725 U	0.00201 U	0.00122 U	0.00515 U	0.000869 U	0.000896 U	0.000888 U	0.000858 U	0.00191 U	**0.00373**
	MW-343-12.5	04/13/20	PES	PACE	12.5	15.1	S	0.00110 U	0.000258 U	0.000751 U	0.00209 U	0.00126 U	0.00534 U	0.000901 U	0.000929 U	0.000920 U	0.000890 U	0.00198 U	0.000904 U
	MW-343-17	04/13/20	PES	PACE	17	10.6	S	0.00103 U	0.000242 U	0.000704 U	0.00196 U	0.00119 U	0.00500 U	0.000844 U	0.000871 U	0.000863 U	0.000834 U	0.00185 U	0.000848 U
	MW-343-24	04/13/20	PES	PACE	24	3.6	S	0.00104 U	0.000242 U	0.000706 U	0.00196 U	0.00119 U	0.00502 U	0.000846 U	0.000873 U	0.000865 U	0.000836 U	0.00186 U	**0.00166 J**
	MW-343-28.5	04/13/20	PES	PACE	28.5	-0.9	S	0.00111 U	0.000260 U	0.000757 U	0.00210 U	0.00127 U	0.00538 U	0.000908 U	0.000936 U	0.000928 U	0.000897 U	0.00199 U	0.000912 U
	MW-343-35	04/13/20	PES	PACE	35	-7.4	S	0.00112 U	0.000263 U	0.000766 U	0.00213 U	0.00129 U	0.00544 U	0.000918 U	0.000947 U	0.000938 U	0.000907 U	0.00201 U	0.000922 U
	MW-343-38	04/13/20	PES	PACE	38	-10.4	S	0.00105 U	0.000246 U	0.000716 U	0.00199 U	0.00120 U	0.00509 U	0.000859 U	0.000886 U	0.000877 U	0.000848 U	0.00188 U	0.000862 U
	MW-343-44	04/13/20	PES	PACE	44	-16.4	S	0.000990 U	0.000231 U	0.000675 U	0.00187 U	0.00114 U	0.00479 U	0.000809 U	0.000834 U	0.000827 U	0.000799 U	0.00177 U	0.000812 U
	MW-343-47	04/13/20	PES	PACE	47	-19.4	S	0.00112 U	0.000261 U	0.000762 U	0.00212 U	0.00128 U	0.00541 U	0.000914 U	0.000942 U	0.000934 U	0.000902 U	0.00200 U	0.000917 U
	MW-343-51	04/13/20	PES	PACE	51	-23.4	S	0.000999 U	0.000234 U	0.000681 U	0.00189 U	0.00115 U	0.00484 U	0.000817 U	0.000842 U	0.000834 U	0.000807 U	0.00179 U	0.000820 U
	MW-343-55	04/13/20	PES	PACE	55	-27.4	S	0.00102 U	0.000239 U	0.000696 U	0.00193 U	0.00117 U	0.00495 U	**0.00202 J**	0.000861 U	0.000853 U	0.000824 U	0.00183 U	0.000838 U
	MW-343-62	04/13/20	PES	PACE	62	-34.4	S	0.00104 U	0.000243 U	0.000708 U	0.00197 U	0.00119 U	0.00503 U	**0.00389**	0.000876 U	0.000868 U	0.000839 U	0.00186 U	0.000853 U
	MW-343-68	04/13/20	PES	PACE	68	-40.4	S	0.00102 U	0.000239 U	0.000698 U	0.00194 U	0.00117 U	0.00496 U	**0.00841**	0.000863 U	0.000855 U	0.000827 U	0.00184 U	0.000840 U
	MW-343-73	04/13/20	PES	PACE	73	-45.4	S	0.00103 U	0.000242 U	0.000705 U	0.00196 U	0.00119 U	0.00501 U	**0.0158**	0.000872 U	0.000864 U	0.000835 U	0.00185 U	0.000849 U
	MW-343-79	04/13/20	PES	PACE	79	-51.4	S	0.000972 U	0.000227 U	0.000663 U	0.00184 U	0.00112 U	0.00471 U	**0.0144**	0.000820 U	0.000812 U	0.000785 U	0.00174 U	0.000798 U
	MW-343-82	04/13/20	PES	PACE	82	-54.4	S	0.000975 U	0.000228 U	0.000665 U	0.00185 U	0.00112 U	0.00472 U	**0.00844**	0.000822 U	0.000814 U	0.000787 U	0.00175 U	0.000800 U
	MW-343-86	04/13/20	PES	PACE	86	-58.4	S	0.000951 U	0.000222 U	0.000648 U	0.00180 U	0.00109 U	0.00461 U	**0.00200 J**	0.000802 U	0.000794 U	0.000768 U	0.00171 U	0.000781 U
	MW-343-93	04/13/20	PES	PACE	93	-65.4	S	0.00101 U	0.000235 U	0.000686 U	0.00190 U	0.00115 U	0.00487 U	0.000822 U	0.000848 U	0.000840 U	0.000812 U	0.00180 U	0.000826 U
	MW-343-99	04/13/20	PES	PACE	99	-71.4	S	0.000964 U	0.000225 U	0.000657 U	0.00183 U	0.00111 U	0.00467 U	0.000788 U	0.000813 U	0.000805 U	0.000778 U	0.00173 U	0.000791 U
	MW-343-102	04/14/20	PES	PACE	102	-74.4	S	0.000991 U	0.000232 U	0.000675 U	0.00188 U	0.00114 U	0.00480 U	0.000810 U	0.000835 U	0.000827 U	0.000800 U	0.00178 U	**0.00103 J**
	MW-2017-102	04/14/20	PES	PACE	102 (dup)	-74.4	S	0.000981 U	0.000229 U	0.000668 U	0.00186 U	0.00112 U	0.00475 U	0.000802 U	0.000827 U	0.000819 U	0.000792 U	0.00176 U	0.000805 U
	MW-343-106	04/14/20	PES	PACE	106	-78.4	S	0.000963 U	0.000225 U	0.000656 U	0.00182 U	0.00110 U	0.00466 U	0.000787 U	0.000812 U	0.000804 U	0.000777 U	0.00173 U	**0.00253 J**
	MW-343-108	04/14/20	PES	PACE	108	-80.4	S	0.000995 U	0.000233 U	0.000678 U	0.00188 U	0.00114 U	0.00482 U	0.000814 U	0.000839 U	0.000831 U	0.000804 U	0.00178 U	**0.00173 J**

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	**–**	**0.074**	**–**	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	**–**	**0.007**	**–**	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
PH22	PH22	04/17/18	PES	Fremont	0-3	–	V	0.0304 U	0.0304 U	0.0304 UJ	0.0608 U	0.0243 U	0.0608 UJ	0.0243 U	0.0243 U	0.0243 U	0.0243 U	0.0243 U	0.0304 U
PH34	PH34	04/17/18	PES	Fremont	1.5-6.5	–	V	0.0240 U	0.0240 U	0.0240 UJ	0.0481 U	0.0192 U	0.0481 UJ	0.0192 U	0.0192 U	0.0192 U	0.0192 U	0.0192 U	0.0240 U
PH38	PH38	04/17/18	PES	Fremont	1.5-4	–	V	0.0292 U	0.0292 U	0.0292 UJ	0.0583 U	0.0233 U	0.0583 UJ	0.0233 U	0.0233 U	0.0233 U	0.0233 U	0.0233 U	0.0292 U
PH52	PH52	04/17/18	PES	Fremont	1-5	–	V	0.0282 U	0.0282 U	0.0282 UJ	0.0564 UJ	0.0226 U	0.0564 UJ	0.0226 U	0.0226 U	0.0226 U	0.0226 U	0.0226 U	0.0282 U
PW-1	Composite	01/01/98	B&V	Unknown	–	–	–	–	–	–	–	–	–	**–**	–	–	–	–	**–**
PW-4	Composite	05/13/98	B&V	Unknown	–	–	–	–	–	–	–	–	–	ND	–	–	–	–	ND
R-MW4	Unknown	10/22/92	Roux	Unknown	5	35.9	V	–	–	–	–	–	–	**–**	–	–	–	–	**–**
	Unknown	10/22/92	Roux	Unknown	15	25.9	S	–	–	–	–	–	–	**–**	–	–	–	–	**–**
	Unknown	10/22/92	Roux	Unknown	30	10.9	S	–	–	–	–	–	–	**–**	–	–	–	–	**–**
R-MW6	Unknown	10/27/92	Roux	Unknown	6	39.3	V	–	–	–	–	–	–	**–**	–	–	–	–	**–**
(33.3 to 23.3)	Unknown	10/27/92	Roux	Unknown	11	34.3	V	–	–	–	–	–	–	**–**	–	–	–	–	**–**
	Unknown	10/27/92	Roux	Unknown	16	29.3	S	–	–	–	–	–	–	**–**	–	–	–	–	**–**
RB1	RB1-17.5	10/18/93	Retec	AAL	17.5	18.4	S	–	–	–	–	–	–	**–**	–	–	–	–	0.063 U
RB2	RB2-12.5	10/18/93	Retec	AAL	12.5	23.6	V	–	–	–	–	–	–	**–**	–	–	–	–	0.062 U
	RB2-17.5	10/18/93	Retec	AAL	17.5	18.6	S	–	–	–	–	–	–	**–**	–	–	–	–	**0.058 J**
RB3	RB3-17.5	10/18/93	Retec	AAL	17.5	20.5	S	–	–	–	–	–	–	**–**	–	–	–	–	0.061 U
SCL-B100	B-100, S1	06/10/02	Urban	F&BI	5-6.5	–	V	–	–	–	–	–	–	0.05 U	–	–	–	–	0.02 U
	B-100, S2	06/10/02	Urban	F&BI	10-11.5	–	V	–	–	–	–	–	–	0.05 U	–	–	–	–	0.02 U
SCL-B101	B-101- S1&2	06/17/02	Urban	F&BI	0-6	–	V	–	–	–	–	–	–	0.05 U	–	–	–	–	0.02 U
	B101-S3	06/17/02	Urban	F&BI	8	–	V	–	–	–	–	–	–	0.05 U	–	–	–	–	0.02 U
SCL-B102	B102-S1	06/17/02	Urban	F&BI	0-3	–	V	–	–	–	–	–	–	0.05 U	–	–	–	–	**0.04**
	B102-S2	06/17/02	Urban	F&BI	4	–	V	–	–	–	–	–	–	0.05 U	–	–	–	–	0.02 U
SCL-MW101	MW101-S3	06/14/02	Urban	F&BI	16	–	S	–	–	–	–	–	–	**–**	–	–	–	–	**0.04**
(25.0 to 15.0)																			
SCL-MW102	MW-102, S1	06/10/02	Urban	F&BI	5-6.5	–	S	–	–	–	–	–	–	**–**	–	–	–	–	**1.0**
	MW-102, S2	06/10/02	Urban	F&BI	5-6.5, 10-11.5	–	S	–	–	–	–	–	–	**–**	–	–	–	–	**0.12**
SCL-MW103	MW103-S1&S2	06/14/02	Urban	F&BI	5-6.5, 10-11.5	–	S	–	–	–	–	–	–	**–**	–	–	–	–	0.02 U
SCL-MW105	MW-105, S2	06/10/02	Urban	F&BI	10-11.5	–	S	–	–	–	–	–	–	**–**	–	–	–	–	**11**
(10.8 to 0.8)	MW-105, S4	06/10/02	Urban	F&BI	20-21.5	–	S	–	–	–	–	–	–	**–**	–	–	–	–	0.02 U
SCLB-1	RS1-2.5/RS-1 7.5 (Comp)	03/12/93	EPJ	OnSite	2.5-7.5	–	V	–	–	–	–	–	–	**–**	–	–	–	–	**–**
	RS1-12.5/RS1-17.5 (Comp)	03/12/93	EPJ	OnSite	12.5-17.5	–	S	–	–	–	–	–	–	**–**	–	–	–	–	**5.0**
	RS-1 17.5	03/12/93	EPJ	OnSite	17.5	21.0	S	–	–	–	–	–	–	**–**	–	–	–	–	**–**
	RS1-22.5/RS-27.5 (Comp)	03/12/93	EPJ	OnSite	22.5-27.5	–	S	–	–	–	–	–	–	**–**	–	–	–	–	**0.31**
	RS1-32.5	03/12/93	EPJ	OnSite	32.5	6.0	S	–	–	–	–	–	–	**–**	–	–	–	–	**0.96**
	RS1-37.5	03/12/93	EPJ	OnSite	37.5	1.0	S	–	–	–	–	–	–	**–**	–	–	–	–	0.05 U
SCLB-2	RS2-2.5/RS-2 7.5 (Comp)	03/12/93	EPJ	OnSite	2.5-7.5	–	V	–	–	–	–	–	–	**–**	–	–	–	–	**–**
	RS2-12.5/RS2-17.5 (Comp)	03/12/93	EPJ	OnSite	12.5-17.5	–	S	–	–	–	–	–	–	**–**	–	–	–	–	**23**
	RS2-17.5	03/12/93	EPJ	OnSite	17.5	21.0	S	–	–	–	–	–	–	**–**	–	–	–	–	**–**
	RS2-22.5/RS2-27.5 (Comp)	03/12/93	EPJ	OnSite	22.5-27.5	–	S	–	–	–	–	–	–	**–**	–	–	–	–	**0.85**
	RS2-32.5	03/12/93	EPJ	OnSite	32.5	6.0	S	–	–	–	–	–	–	**–**	–	–	–	–	**1.4**
	RS2-37.5	03/12/93	EPJ	OnSite	37.5	1.0	S	–	–	–	–	–	–	**–**	–	–	–	–	**0.11**

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	**–**	**0.074**	**–**	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	**–**	**0.007**	**–**	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
SSD-MW-1	MW-1 S-2	05/24/89	HC	Unknown	5-6.5	34.0	V	–	–	–	–	–	–	–	–	–	–	–	0.01 U
	MW-1 S-6	05/24/89	HC	Unknown	15-16.5	24.0	S	–	–	–	–	–	–	–	–	–	–	–	**2.84**
SSD-MW-2	MW-2 S-3	05/24/89	HC	Unknown	7.5-9	31.0	V	–	–	–	–	–	–	–	–	–	–	–	0.01 U
	MW-2 S-6	05/24/89	HC	Unknown	15-16.5	31.0	V	–	–	–	–	–	–	–	–	–	–	–	0.01 U
SSD-MW-3	MW-3 S-2	05/24/89	HC	Unknown	5-6.5	34.0	V	–	–	–	–	–	–	–	–	–	–	–	0.01 U
	MW-3 S-5	05/24/89	HC	Unknown	12.5-14	34.0	V	–	–	–	–	–	–	–	–	–	–	–	0.01 U
SSD-MW-4	MW-4 S-6	05/25/89	HC	Unknown	14.5-16	36.8	V	–	–	–	–	–	–	–	–	–	–	–	**0.069**
	MW-4 S-9	05/25/89	HC	Unknown	22-23	29.5	S	–	–	–	–	–	–	–	–	–	–	–	0.01 U
SV-04	SV-04-6	06/29/20	PES	PACE	6	–	V	0.00116 U	0.000272 U	0.000793 U	0.00220 U	0.00133 U	0.00564 U	0.000951 U	0.000981 U	0.000972 U	0.000940 U	0.00209 U	0.000955 U
SV-05	SV-05-10	06/29/20	PES	PACE	10	–	V	0.00124 U	0.000291 U	0.000847 U	0.00235 U	0.00143 U	0.00602 U	0.00102 UJ	0.00105 U	0.00104 U	0.00100 U	0.00223 U	0.00102 U
SV-06	SV-06-6	06/29/20	PES	PACE	6	–	V	0.00115 U	0.000268 U	0.000781 U	0.00217 U	0.00131 U	0.00555 U	0.000936 UJ	0.000966 U	0.000957 U	0.000925 U	0.00205 U	0.000940 U
SV-07	SV-07-15	06/29/20	PES	PACE	15	–	V	0.000984 U	0.000230 U	0.000671 U	0.00186 U	0.00113 U	0.00477 U	0.000804 UJ	0.000830 U	0.000822 U	0.000795 U	0.00176 U	0.000808 U
SV-08	SV-08-6	06/30/20	PES	PACE	6	–	V	0.00125 U	0.000292 U	0.000851 U	0.00236 U	0.00143 U	0.00605 U	0.00102 UJ	0.00105 U	0.00104 U	0.00101 U	0.00224 U	**0.00452**
	SV-08-7.5	06/30/20	PES	PACE	7.5	–	V	0.00127 U	0.000298 U	0.000867 U	0.00241 U	0.00146 U	0.00617 U	0.00104 U	0.00107 U	0.00106 U	0.00103 U	0.00228 U	0.00104 U
SV-09	SV-09-5.5	07/01/20	PES	PACE	5.5	–	V	0.00119 U	0.000278 U	0.000810 U	0.00225 U	0.00136 U	0.00576 U	0.000971 U	0.00100 U	0.000993 U	0.000960 U	0.00213 U	0.000975 U
SV-10	SV-10-5.5	06/30/20	PES	PACE	5.5	–	V	0.00118 U	0.000277 U	0.000807 U	0.00224 U	0.00136 U	0.00573 U	0.000968 U	0.000998 U	0.000989 U	0.000956 U	0.00212 U	0.000972 U
SV-11	SV-11-10	06/30/20	PES	PACE	10	–	V	0.00120 U	0.000281 U	0.000818 U	0.00227 U	0.00138 U	0.00582 U	0.000981 U	0.00101 U	0.00100 U	0.000969 U	0.00215 U	0.000985 U
SV-12	SV-12-5.5	07/01/20	PES	PACE	5.5	–	V	0.000982 U	0.000230 U	0.000669 U	0.00186 U	0.00113 U	0.00476 U	0.000802 U	0.000828 U	0.000820 U	0.000793 U	0.00176 U	**0.00223 J**
SV-13	SV-13-10.5	07/01/20	PES	PACE	10.5	–	V	0.00115 U	0.000269 U	0.000785 U	0.00218 U	0.00132 U	0.00558 U	0.000941 U	0.000971 U	0.000962 U	0.000930 U	0.00206 U	0.000945 U
SV-14	SV-14-5.5	07/01/20	PES	PACE	5.5	–	V	0.00120 U	0.000281 U	0.000818 U	0.00227 U	0.00138 U	0.00582 U	0.000981 U	0.00101 U	0.00100 U	0.000969 U	0.00215 U	0.000985 U
SV-15	SV-15-13	07/01/20	PES	PACE	13	–	V	0.00117 U	0.000273 U	0.000794 U	0.00221 U	0.00134 U	0.00565 U	0.000953 U	0.000982 U	0.000973 U	0.000941 U	0.00209 U	0.000956 U
SV-16	SV-16-5	07/02/20	PES	PACE	5	–	V	0.00237 U	0.000556 U	0.00163 U	0.00452 U	0.00272 U	0.0115 U	0.00195 U	0.00201 U	0.00199 U	0.00193 U	0.00428 U	**0.0102 J**
	SV-100-5	07/02/20	PES	PACE	5 (dup)	–	V	0.00213 U	0.000500 U	0.00145 U	0.00403 U	0.00244 U	0.0103 U	0.00174 U	0.00180 U	0.00178 U	0.00172 U	0.00383 U	**0.00350 J**
SV-17	SV-17-4.5	07/02/20	PES	PACE	4.5	–	V	0.00177 U	0.000413 U	0.00120 U	0.00335 U	0.00203 U	0.00855 U	0.00144 U	0.00149 U	0.00147 U	0.00143 U	0.00317 U	**0.0104**
SV-18	SV-18-5.5	07/02/20	PES	PACE	5.5	–	V	0.000968 U	0.000226 U	0.000660 U	0.00183 U	0.00111 U	0.00469 U	0.000791 U	0.000816 U	0.000808 U	0.000781 U	0.00173 U	0.000794 U
SV-19	SV-19-5	07/09/20	PES	PACE	5	–	V	0.000967 U	0.000226 U	0.000659 U	0.00183 U	0.00111 U	0.00468 U	0.000790 U	0.000815 U	0.000808 U	0.000781 U	0.00173 U	0.000794 U
SV-20	SV-20-9	07/09/20	PES	PACE	9	–	V	0.00127 U	0.000297 U	0.000866 U	0.00241 U	0.00146 U	0.00616 U	0.00104 U	0.00107 U	0.00106 U	0.00103 U	0.00228 U	0.00104 U
SV-21	SV-21-6	07/09/20	PES	PACE	6	–	V	0.000984 U	0.000230 U	0.000671 U	0.00186 U	0.00113 U	0.00477 U	0.000804 U	0.000830 U	0.000822 U	0.000795 U	0.00176 U	0.000808 U
SV-22	SV-22-8.5	07/09/20	PES	PACE	8.5	–	V	0.00183 U	0.000430 U	0.00125 U	0.00347 U	0.00210 U	0.00888 U	0.00150 U	0.00155 U	0.00153 U	0.00148 U	0.00330 U	0.00151 U
SV-23	SV-23-4.5	07/09/20	PES	PACE	4.5	–	V	0.00136 U	0.000318 U	0.000925 U	0.00257 U	0.00156 U	0.00658 U	0.00111 U	0.00114 U	0.00113 U	0.00110 U	0.00243 U	0.00111 U
SV-24	SV-24-8	07/09/20	PES	PACE	8	–	V	0.000975 U	0.000228 U	0.000664 U	0.00185 U	0.00112 U	0.00472 U	0.000797 U	0.000822 U	0.000814 U	0.000787 U	0.00175 U	0.000800 U
SV-25	SV-25-4	07/10/20	PES	PACE	4	–	V	0.00118 U	0.000277 U	0.000806 U	0.00224 U	0.00136 U	0.00573 U	0.000967 U	0.000997 U	0.000988 U	0.000955 U	0.00212 U	0.000971 U
SV-26	SV-26-12	07/10/20	PES	PACE	12	–	V	0.00131 U	0.000307 U	0.000896 U	0.00249 U	0.00151 U	0.00637 U	0.00107 U	0.00111 U	0.00110 U	0.00106 U	0.00236 U	0.00108 U
SV-27	SV-27-5.5	07/10/20	PES	PACE	5.5	–	V	0.00118 U	0.000276 U	0.000803 U	0.00223 U	0.00135 U	0.00571 U	0.000963 U	0.000993 U	0.000984 U	0.000951 U	0.00211 U	0.000967 U
	SV-27-13.5	07/10/20	PES	PACE	13.5	–	V	0.00118 U	0.000276 U	0.000804 U	0.00223 U	0.00135 U	0.00572 U	0.000964 U	0.000995 U	0.000985 U	0.000953 U	0.00212 U	0.000968 U
TB-12	16	08/01/97	B&V	Unknown	62-63	-24.5	S	–	–	–	–	–	–	–	–	–	–	–	–
TB-18	S-2	03/17/98	B&V	Unknown	5-6.5	38.3	V	–	–	–	–	–	–	ND	–	–	–	–	ND
	S-8	03/17/98	B&V	Unknown	20-21.5	23.3	S	–	–	–	–	–	–	ND	–	–	–	–	ND
	S-21	03/17/98	B&V	Unknown	57.5-59	1.2	S	–	–	–	–	–	–	ND	–	–	–	–	ND

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
T1	T1-2.5-071718	07/17/18	PES	Fremont	2.5	–	V	0.0265 U	0.0265 U	0.0265 U	0.0531 U	0.0212 U	0.0531 U	0.0212 U	0.0212 U	0.0212 U	0.0212 U	0.0212 U	0.0265 U
T-2	T-2-071618	07/16/18	PES	Fremont	2	–	V	0.0143 U	0.0143 U	0.0143 U	0.0287 U	0.0115 U	0.0287 U	0.0115 U	0.0115 U	0.0115 U	0.0115 U	0.0115 U	0.0143 U
T-2B	T-2B-071618	07/16/18	PES	Fremont	2	–	V	0.0297 U	0.0297 U	0.0297 U	0.0593 U	0.0237 U	0.0593 U	0.0237 U	0.0237 U	0.0237 U	0.0237 U	0.0237 U	0.0297 U
T2	T2-6-071718	07/17/18	PES	Fremont	6	–	V	0.0307 U	0.0307 U	0.0307 U	0.0614 U	0.0245 U	0.0614 U	0.0245 U	0.0245 U	0.0245 U	0.0245 U	0.0245 U	0.0307 U
T3	T3-3-071718	07/17/18	PES	Fremont	3	–	V	0.0287 U	0.0287 U	0.0287 U	0.0573 U	0.0229 U	0.0573 U	0.0229 U	0.0229 U	0.0229 U	0.0229 U	0.0229 U	0.0287 U
T4	T4-6-071718	07/17/18	PES	Fremont	6	–	V	0.0258 U	0.0258 U	0.0258 U	0.0516 U	0.0206 U	0.0516 U	0.0206 U	0.0206 U	0.0206 U	0.0206 U	0.0206 U	0.0258 U
T-5	T-5-071618	07/16/18	PES	Fremont	5	–	V	0.0255 U	0.0255 U	0.0255 U	0.0509 U	0.0204 U	0.0509 U	0.0204 U	0.0204 U	0.0204 U	0.0204 U	0.0204 U	0.0255 U
T6	T6-4-071818	07/18/18	PES	Fremont	4	–	V	0.0237 U	0.0237 U	0.0237 U	0.0474 U	0.0189 U	0.0474 U	0.0189 U	0.0189 U	0.0189 U	0.0189 U	0.0189 U	0.0237 U
T7	T7-7-071818	07/18/18	PES	Fremont	7	–	V	0.0342 U	0.0342 U	0.0342 U	0.0684 U	0.0274 U	0.0684 U	0.0274 U	0.0274 U	0.0274 U	0.0274 U	0.0274 U	0.0342 U
T8	T8-3-072018	07/20/18	PES	Fremont	3	–	V	0.0268 U	0.0268 U	0.0268 U	0.0536 U	0.0214 U	0.0536 U	0.0214 U	0.0214 U	0.0214 U	0.0214 U	0.0214 U	0.0268 U
T8	T8-6-072018	07/20/18	PES	Fremont	6	–	V	0.0377 U	0.0377 U	0.0377 U	0.0753 U	0.0301 U	0.0753 U	0.0301 U	0.0301 U	0.0301 U	0.0301 U	0.0301 U	0.0377 U
T9	T9-3-072018	07/20/18	PES	Fremont	3	–	V	0.0437 U	0.0437 U	0.0437 U	0.0875 U	0.0350 U	0.0875 U	0.0350 U	0.0350 U	0.0350 U	0.0350 U	0.0350 U	0.0437 U
T9	T9-3.5-072018	07/20/18	PES	Fremont	3.5	–	V	0.0291 U	0.0291 U	0.0291 U	0.0583 U	0.0233 U	0.0583 U	0.0233 U	0.0233 U	0.0233 U	0.0233 U	0.0233 U	0.0291 U
T9	T9-6-072018	07/20/18	PES	Fremont	6	–	V	0.0303 U	0.0303 U	0.0303 U	0.0605 U	0.0242 U	0.0605 U	0.0242 U	0.0242 U	0.0242 U	0.0242 U	0.0242 U	**0.0311**
T10	T10-3-072018	07/20/18	PES	Fremont	3	–	V	0.0513 U	0.0513 U	0.0513 U	0.103 U	0.0411 U	0.103 U	0.0411 U	0.0411 U	0.0411 U	0.0411 U	0.0411 U	**0.0528**
T10	T10-6-072018	07/20/18	PES	Fremont	6	–	V	0.0278 U	0.0278 U	0.0278 U	0.0556 U	0.0222 U	0.0556 U	0.0222 U	0.0222 U	0.0222 U	0.0222 U	0.0222 U	0.0278 U
T11	T11-3.5-073118	07/31/18	PES	Fremont	3.5	–	V	0.0358 U	0.0358 U	0.0358 U	0.0716 U	0.0286 U	0.0716 U	0.0286 U	0.0286 U	0.0286 U	0.0286 U	0.0286 U	0.0358 U
T12	T12-3-091818	09/18/18	PES	Fremont	3	–	V	0.0307 U	0.0307 U	0.0307 U	0.0614 U	0.0245 U	0.0614 U	0.0245 U	0.0245 U	0.0245 U	0.0245 U	0.0245 U	0.0307 U
T12	T12-7-091818	09/18/18	PES	Fremont	7	–	V	0.0303 U	0.0303 U	0.0303 U	0.0607 U	0.0243 U	0.0607 U	0.0243 U	0.0243 U	0.0243 U	0.0243 U	0.0243 U	0.0303 U
T12	T12-7.5-073118	07/31/18	PES	Fremont	7.5	–	V	0.0259 U	0.0259 U	0.0259 U	0.0519 U	0.0207 U	0.0519 U	0.0207 U	0.0207 U	0.0207 U	0.0207 U	0.0207 U	0.0259 U
T13	T13-3.5-091818	09/18/18	PES	Fremont	3.5	–	V	0.0283 U	0.0283 U	0.0283 U	0.0567 U	0.0227 U	0.0567 U	0.0227 U	0.0227 U	0.0227 U	0.0227 U	0.0227 U	0.0283 U
T13	T13-6.5-091818	09/18/18	PES	Fremont	6.5	–	V	0.0250 U	0.0250 U	0.0250 U	0.0500 U	0.0200 U	0.0500 U	0.0200 U	0.0200 U	0.0200 U	0.0200 U	0.0200 U	0.0250 U
T14	T14-3.5-091818	09/18/18	PES	Fremont	3.5	–	V	0.0300 U	0.0300 U	0.0300 U	0.0599 U	0.0240 U	0.0599 U	0.0240 U	0.0240 U	0.0240 U	0.0240 U	0.0240 U	0.0300 U
T14	T14-7-091818	09/18/18	PES	Fremont	7	–	V	0.0318 U	0.0318 U	0.0318 U	0.0635 U	0.0254 U	0.0635 U	0.0254 U	0.0254 U	0.0254 U	0.0254 U	0.0254 U	0.0318 U
TP-15	TP-15-3-092818	09/28/18	PES	Fremont	3	–	V	0.0304 U	0.0304 U	0.0304 U	0.0609 U	0.0244 U	0.0609 U	0.0244 U	0.0244 U	0.0244 U	0.0244 U	0.0244 U	0.0304 U
TP-15	TP-15-6.5-092818	09/28/18	PES	Fremont	6.5	–	V	0.0313 U	0.0313 U	0.0313 U	0.0625 U	0.0250 U	0.0625 U	0.0250 U	0.0250 U	0.0250 U	0.0250 U	0.0250 U	0.0313 U
TP-16	TP-16-3-092818	09/28/18	PES	Fremont	3	–	V	0.0426 U	0.0426 U	0.0426 U	0.0852 U	0.0341 U	0.0852 U	0.0341 U	0.0341 U	0.0341 U	0.0341 U	0.0341 U	0.0426 U
TP-16	TP-16-6-092818	09/28/18	PES	Fremont	6	–	V	0.0446 U	0.0446 U	0.0446 U	0.0892 U	0.0357 U	0.0892 U	0.0357 U	0.0357 U	0.0357 U	0.0357 U	0.0357 U	0.0446 U
TP-16	TP-16-9-092818	09/28/18	PES	Fremont	9	–	V	0.0263 U	0.0263 U	0.0263 U	0.0525 U	0.0210 U	0.0525 U	0.0210 U	0.0210 U	0.0210 U	0.0210 U	0.0210 U	0.0263 U
TP-SD-01	TP-SD-01-2	06/03/19	PES	Fremont	2	–	V	0.0214 U	0.0214 U	0.0214 U	0.0429 U	0.0172 U	0.0429 U	0.0172 U	0.0172 U	0.0172 U	0.0172 U	0.0172 UJ	**0.0736**
TP-SD-01	TP-SD-01-5	06/03/19	PES	Fremont	5	–	V	0.0267 U	0.0267 U	0.0267 U	0.0534 U	0.0213 U	0.0534 U	0.0213 U	0.0213 U	0.0213 U	0.0213 U	0.0213 UJ	0.0267 U
TP-SD-04	TP-SD-04-2	06/03/19	PES	Fremont	2	–	V	0.0252 U	0.0252 U	0.0252 U	0.0504 U	0.0202 U	0.0504 U	0.0202 U	0.0202 U	0.0202 U	0.0202 U	0.0202 UJ	0.0252 U
TP-SD-04	TP-SD-04-5	06/03/19	PES	Fremont	5	–	V	0.0272 U	0.0272 U	0.0272 U	0.0544 U	0.0218 U	0.0544 U	0.0218 U	0.0218 U	0.0218 U	0.0218 U	0.0218 UJ	0.0272 U
TP-SD-05	TP-SD-05-2	06/03/19	PES	Fremont	2	–	V	0.0258 U	0.0258 U	0.0258 U	0.0517 U	0.0207 U	0.0517 U	0.0207 U	0.0207 U	0.0207 U	0.0207 U	0.0207 UJ	0.0258 U
TP-SD-05	TP-SD-05-5	06/03/19	PES	Fremont	5	–	V	0.0292 U	0.0292 U	0.0292 U	0.0585 U	0.0234 U	0.0585 U	0.0234 U	0.0234 U	0.0234 U	0.0234 U	0.0234 UJ	0.0292 U
TP-SD-06	TP-SD-06-2	06/03/19	PES	Fremont	2	–	V	0.0344 U	0.0344 U	0.0344 U	0.0688 U	0.0275 U	0.0688 U	0.0275 U	0.0275 U	0.0275 U	0.0275 U	0.0275 UJ	0.0344 U
TP-SD-06	TP-SD-06-5	06/03/19	PES	Fremont	5	–	V	0.0272 U	0.0272 U	0.0272 U	0.0544 U	0.0218 U	0.0544 U	0.0218 U	0.0218 U	0.0218 U	0.0218 U	0.0218 UJ	0.0272 U
TP-SD-07	TP-SD-07-2	06/03/19	PES	Fremont	2	–	V	0.0217 U	0.0217 U	0.0217 U	0.0435 U	0.0174 U	0.0435 U	0.0174 U	0.0174 U	0.0174 U	0.0174 U	0.0174 UJ	0.0217 U
TP-SD-07	B-942-2	06/03/19	PES	Fremont	2 (dup)	–	V	0.0233 U	0.0233 U	0.0233 U	0.0466 U	0.0186 U	0.0466 U	0.0186 U	0.0186 U	0.0186 U	0.0186 U	0.0186 UJ	0.0233 U
TP-SD-07	TP-SD-07-5	06/03/19	PES	Fremont	5	–	V	0.0212 U	0.0212 U	0.0212 U	0.0424 U	0.0169 U	0.0424 U	0.0169 U	0.0169 U	0.0169 U	0.0169 U	0.0169 UJ	0.0212 U
TP-SD-08	TP-SD-08-2	06/03/19	PES	Fremont	2	–	V	0.0242 U	0.0242 U	0.0242 U	0.0483 U	0.0193 U	0.0483 U	0.0193 U	0.0193 U	0.0193 U	0.0193 U	0.0193 UJ	0.0242 U
TP-SD-08	TP-SD-08-5	06/03/19	PES	Fremont	5	–	V	0.0207 U	0.0207 U	0.0207 U	0.0415 U	0.0166 U	0.0415 U	0.0166 U	0.0166 U	0.0166 U	0.0166 U	0.0166 UJ	0.0207 U
TP-SD-08	TP-SD-08-8	06/03/19	PES	Fremont	8	–	S	0.0249 U	0.0249 U	0.0249 U	0.0498 U	0.0199 U	0.0498 U	0.0199 U	0.0199 U	0.0199 U	0.0199 U	0.0199 UJ	0.0249 U
W-MW-01 (P-03)	SB-W-03-0160	01/27/12	WW	ARI	16-16.5	28.4	S	–	–	–	–	–	–	**0.0006 J**	–	–	–	–	0.0010 U
(-25.1 to -35.1)	SB-W-03-0225	01/27/12	WW	ARI	22.5-23	21.9	S	–	–	–	–	–	–	**0.0021**	–	–	–	–	0.0009 U
	SB-W-03-0315	01/27/12	WW	ARI	31.5-32	12.9	S	–	–	–	–	–	–	**0.48**	–	–	–	–	0.21 U
	SB-W-03-0450	01/27/12	WW	ARI	45-45.5	-0.6	S	–	–	–	–	–	–	**0.041**	–	–	–	–	0.0007 U
	SB-W-03-0550	01/27/12	WW	ARI	55.5-56	-11.1	S	–	–	–	–	–	–	**0.13**	–	–	–	–	0.045 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
W-MW-01 (P-03)	SB-W-03-0645	01/27/12	WW	ARI	64.5-65	-20.1	S	–	–	–	–	–	–	0.0008 U	–	–	–	–	0.0008 U
(continued)	SB-W-03-0730	01/27/12	WW	ARI	73-73.5	-28.6	S	–	–	–	–	–	–	**0.025**	–	–	–	–	0.0007 U
W-MW-02 (P-06)	SB-W-06-0900	01/29/12	WW	ARI	9-9.5	34.0	S	–	–	–	–	–	–	0.0013 U	–	–	–	–	0.0013 U
(-26.5 to -36.5)	SB-W-06-0185	01/29/12	WW	ARI	18.5-19	24.5	S	–	–	–	–	–	–	0.0009 U	–	–	–	–	0.0009 U
	SB-W-06-0305	01/30/12	WW	ARI	30.5-31	12.6	S	–	–	–	–	–	–	**0.4**	–	–	–	–	0.27 U
	SB-W-06-0380	01/30/12	WW	ARI	38-38.5	5.0	S	–	–	–	–	–	–	**0.52**	–	–	–	–	0.046 U
	SB-W-06-0405	01/30/12	WW	ARI	40.5-41	2.5	S	–	–	–	–	–	–	**0.15**	–	–	–	–	0.036 U
	SB-W-06-0485	01/30/12	WW	ARI	48.5-49	-5.5	S	–	–	–	–	–	–	**0.0009**	–	–	–	–	0.0008 U
	SB-W-06-9485	01/30/12	WW	ARI	48.5-49 (dup)	-5.5	S	–	–	–	–	–	–	**0.0010**	–	–	–	–	0.0009 U
	SB-W-06-0590	01/30/12	WW	ARI	59-59.5	-16.0	S	–	–	–	–	–	–	0.043 U	–	–	–	–	0.043 U
	SB-W-06-0715	01/30/12	WW	ARI	71.5-72	-28.5	S	–	–	–	–	–	–	0.0008 U	–	–	–	–	0.0008 U
	SB-W-06-0790	01/31/12	WW	ARI	79-79.5	-36.0	S	–	–	–	–	–	–	0.0009 U	–	–	–	–	0.0009 U
All Data							Number of Analytes Measured	644	644	644	644	644	644	859	646	646	646	644	778
							Number of Analytes Detected	0	6	0	0	55	1	2	0	0	0	0	-8
							Frequency of Detection	0.0%	0.9%	0.0%	0.0%	8.5%	0.2%	0.2%	0.0%	0.0%	0.0%	0.0%	-1.0%
							Maximum Detection	–	0.0633	–	–	0.0159	0.00179 J	3.03	–	–	–	–	54
							Minimum Detection	0.000341 U	0.00022 U	0.000388 U	0.000983 U	0.000238 U	0.00039 U	0.000244 UJ	0.000272 U	0.000397 U	0.000264 U	0.000741 U	0.000311 U
							Number Of Vadose (V) Detections above SL	0	0	0	–	0	–	1	0	0	0	0	0
							Number of Saturated (S) Detections above SL	0	1	0	–	0	–	136	0	0	0	0	17
2017-2021							Number of Analytes Measured	644	644	644	644	644	644	644	644	644	644	644	644
							Number of Analytes Detected	0	6	0	0	55	1	179	0	0	0	0	93
							Frequency of Detection	0.0%	0.9%	0.0%	0.0%	8.5%	0.2%	27.8%	0.0%	0.0%	0.0%	0.0%	14.4%
							Maximum Detection	–	0.0633	–	–	0.0159	0.00179 J	3.03	–	–	–	–	3.01
							Minimum Detection	0.000341 U	0.00022 U	0.000388 U	0.000983 U	0.000238 U	0.00039 U	0.000244 UJ	0.000272 U	0.000397 U	0.000264 U	0.000741 U	0.000311 U
							Number Of Vadose (V) Detections above SL	0	0	0	–	0	–	1	0	0	0	0	0
							Number of Saturated (S) Detections above SL	0	1	0	–	0	–	110	0	0	0	0	3

Abbreviations:
AAL = Alden Analytical Laboratories, Inc., of Seattle, Washington
ARI = Analytical Resource, Incorporated, Seattle, Washington
B&V = Black Veatch
bgs = below ground surface
Comp = Composite Sample
dup = duplicate
EPJ = E.PJohnson Construction Inc., and Environmental
ESC = ESC Lab Services of Mt. Juliet, Tennessee
F&BI = Friedman & Bruya, Inc.
HC = Hart Crowser, Inc.
OnSite = OnSite Environmental Inc., of Redmond, Washington
Pace = Pace Analytical of Mt. Juliet, Tennessee (formerly ESC)
PES = PES Environmental, Inc.
Retec = Remediation Technologies, Inc.
Roux = Roux Associates
Urban = Urban Redevelopment LLC
WW = WW Environmental LLC

Notes:
Petroleum Hydrocarbons (PHCs) analyzed by Ecology Methods NWTPH-HCID, NWTPH-Gx, or NWTPH-Dx; or EPA Method 418.1, Method 8020, or Method 8015M.
VOCs analyzed by EPA Methods 8010, 8020, 8021B, 624/8240, or 8260B/C/D.
Well screen elevations provided below Sample Location. in parentheses when appliable.
PCUL = Preliminary Cleanup Level from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021. PCULs based on the practical quantitation limits (PQLs) italicized.
Detected results shown in **bold**.
Detections above the screening level in the vadose zone are shown in **bold and highlighted blue**.
Detections above the screening level in the saturated zone are shown in **bold and highlighted gray.**
– = Not available or results not analyzed.
B = Analyte detected in an associated method blank.
J = The reported concentration is an estimate based on detectable results between the method detection limit and reporting limit, laboratory QA/QC, or data validation review.
J+ = The result is an estimated quantity, but the result may be biased high.
J- = The result is an estimated quantity, but the result may be biased low.
ND = Not detected above laboratory reporting limit. Reporting limit not available.
R = The data is unusable. The sample result is rejected due to serious deficiencies in meeting QC criteria. The analyte may or may not be present in the sample
T = Analyte also detected in trip blank.
U = Not detected at a concentration exceeding laboratory reporting limit
ve = Estimated value. The reported range exceeds the calibration range of the analysis.
z = Gasoline/petroleum detection result is likely elevated due to high detections of CVOCs.

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
B-1A	B-1/S-2	12/01/89	HC	ARI	10.5	–	–	–	–	–	–		–	–	–	–	–	–	–
B-2A	B-2/S-1	12/01/89	HC	ARI	10	–	–	–	–	–	–		–	–	–	–	–	–	–
B-212	B-212-15	09/08/17	PES	ESC	15	42.6	V	0.000394 U	0.000334 U	0.00291 U	0.000286 U	0.000280 U	0.00217 U	0.000244 U	0.00115 U	0.00115 U	0.000297 U	0.000237 U	0.000232 U
	B-212-21	09/08/17	PES	ESC	21	36.6	S	0.000355 U	0.000301 U	0.00263 U	0.000258 U	**0.00134**	0.00195 U	0.000220 U	0.00104 U	**0.0257**	**0.00372**	**0.00280**	**0.00234**
	B-212-35	09/08/17	PES	ESC	35	22.6	S	0.000373 U	**0.00122 J**	0.00276 U	0.000270 U	0.000265 U	0.00205 U	0.000231 U	0.00109 U	0.00109 U	0.000281 U	0.000225 U	0.000219 U
	B-212-45	09/08/17	PES	ESC	45	12.6	S	0.000358 U	**0.0126**	0.00265 U	0.000259 U	0.000254 U	0.00197 U	0.000222 U	0.00105 U	0.00105 U	0.000270 U	0.000216 U	0.000210 U
	B-907-25	09/08/17	PES	ESC	45 (dup)	12.6	S	0.0102 U	0.00867 U	0.0755 U	0.00741 U	0.00727 U	0.0562 U	0.00634 U	0.0299 U	0.0299 U	0.00771 U	0.00616 U	0.00600 U
	B-212-55	09/08/17	PES	ESC	55	2.6	S	0.000386 U	0.000327 U	0.00285 U	0.000280 U	0.000274 U	0.00212 U	0.000239 U	0.00113 U	0.00113 U	0.000291 U	0.000232 U	0.000227 U
	B-212-65	09/08/17	PES	ESC	65	-7.4	S	0.000397 U	**0.00322 J**	0.00294 U	0.000288 U	0.000282 U	0.00218 U	0.000246 U	0.00116 U	0.00116 U	0.000299 U	0.000239 U	0.000233 U
	B-212-75	09/08/17	PES	ESC	75	-17.4	S	0.000398 U	**0.00125 J**	0.00294 U	0.000288 U	0.000283 U	0.00219 U	0.000247 U	0.00116 U	0.00116 U	0.000300 U	0.000240 U	0.000234 U
	B-212-85	09/11/17	PES	ESC	85	-27.4	S	0.00970 U	0.000329 U	0.00287 U	0.000281 U	0.000276 U	0.00213 U	0.000241 U	0.00113 U	0.00113 U	0.000293 U	0.000234 U	0.000228 U
	B-212-95	09/11/17	PES	ESC	95	-37.4	S	0.000447 U	0.000379 U	0.00331 U	0.000324 U	0.000318 U	0.00245 U	0.000278 U	0.00131 U	0.00131 U	0.000337 U	0.000269 U	0.000263 U
	B-212-100	09/11/17	PES	ESC	100	-42.4	S	0.000413 U	0.000350 U	0.00305 U	0.000299 U	0.000293 U	0.00227 U	0.000256 U	0.00121 U	0.00121 U	0.000311 U	0.000249 U	0.000243 U
B-213	B-213-15	09/05/17	PES	ESC	15	42.4	V	0.000396 U	0.000336 U	0.00293 U	0.000287 U	0.000282 U	0.00218 U	0.000246 U	0.00116 U	0.00116 U	0.000299 U	0.000239 U	0.000233 U
	B-213-21.5	09/05/17	PES	ESC	22	35.9	S	0.000356 U	**0.0375 J**	0.00264 U	0.000258 U	**0.00198**	0.00196 U	0.000221 U	0.00104 U	**0.0239**	**0.00519**	**0.00457**	**0.00362**
	B-213-35	09/05/17	PES	ESC	35	22.4	S	0.000370 U	0.000314 U	0.00274 U	0.000268 U	0.000263 U	0.00204 U	0.000230 U	0.00108 U	0.00108 U	0.000279 U	0.000223 U	0.000218 U
	B-213-45	09/05/17	PES	ESC	45	12.4	S	0.000379 U	0.000321 U	0.00280 U	0.000275 U	0.000269 U	0.00208 U	0.000235 U	0.00111 U	0.00111 U	0.000286 U	0.000228 U	0.000223 U
	B-213-55	09/05/17	PES	ESC	55	2.4	S	0.000372 U	**0.0237 J**	0.00275 U	0.000270 U	0.000265 U	0.00205 U	0.000231 U	0.00109 U	0.00109 U	0.000281 U	0.000224 U	0.000219 U
	B-213-65	09/05/17	PES	ESC	65	-7.6	S	0.000376 U	**0.0107 J**	0.00278 U	0.000273 U	0.000267 U	0.00207 U	0.000233 U	0.00110 U	0.00110 U	0.000284 U	0.000227 U	0.000221 U
	B-213-75	09/05/17	PES	ESC	75	-17.6	S	0.000374 U	0.000317 U	0.00276 U	0.000271 U	0.000266 U	0.00205 U	0.000232 U	0.00109 U	0.00109 U	0.000282 U	0.000225 U	0.000220 U
	B-213-85	09/05/17	PES	ESC	85	-27.6	S	0.000417 U	0.000354 U	0.00308 U	0.000302 U	0.000296 U	0.00229 U	0.000258 U	0.00122 U	0.00122 U	0.000315 U	0.000251 U	0.000245 U
	B-213-95	09/06/17	PES	ESC	95	-37.6	S	0.000422 U	0.000358 U	0.00313 U	0.000306 U	0.000300 U	0.00232 U	0.000262 U	0.00124 U	0.00124 U	0.000319 U	0.000254 U	0.000248 U
	B-213-105	09/06/17	PES	ESC	105	-47.6	S	0.000393 U	0.000333 U	0.00291 U	0.000285 U	0.000279 U	0.00216 U	0.000244 U	0.00115 U	0.00115 U	0.000296 U	0.000237 U	0.000231 U
	B-906-110	09/06/17	PES	ESC	105 (dup)	-47.6	S	0.000393 U	0.000333 U	0.00290 U	0.000285 U	0.000279 U	0.00216 U	0.000243 U	0.00115 U	0.00115 U	0.000296 U	0.000237 U	0.000231 U
	B-213-115	09/06/17	PES	ESC	115	-57.6	S	0.000419 U	0.000356 U	0.00310 U	0.000304 U	0.000298 U	0.00231 U	0.000260 U	0.00123 U	0.00123 U	0.000316 U	0.000253 U	0.000246 U
	B-213-125	09/06/17	PES	ESC	125	-67.6	S	0.000506 U	0.000429 U	0.00374 U	0.000367 U	0.000359 U	0.00279 U	0.000314 U	0.00148 U	0.00148 U	0.000382 U	0.000305 U	0.000297 U
B-214	B-214-15	09/07/17	PES	ESC	15	42.4	V	0.000367 U	0.000311 U	0.00271 U	0.000266 U	0.000261 U	0.00202 U	0.000227 U	0.00107 U	0.00107 U	0.000277 U	0.000221 U	0.000216 U
	B-214-25	09/07/17	PES	ESC	25	32.4	S	0.000361 U	**0.000623 J**	0.00267 U	0.000262 U	0.000257 U	0.00199 U	0.000224 U	0.00106 U	0.00106 U	0.000273 U	0.000218 U	0.000212 U
	B-214-35	09/07/17	PES	ESC	35	22.4	S	0.000371 U	0.000315 U	0.00275 U	0.000269 U	0.000264 U	0.00204 U	0.000230 U	0.00109 U	0.00109 U	0.000280 U	0.000224 U	0.000218 U
	B-214-45	09/07/17	PES	ESC	45	12.4	S	0.000364 U	**0.00110 J**	0.00269 U	0.000264 U	0.000259 U	0.00200 U	0.000226 U	0.00106 U	0.00106 U	0.000275 U	0.000219 U	0.000214 U
	B-214-55	09/07/17	PES	ESC	55	2.4	S	0.000380 U	**0.00245 J**	0.00281 U	0.000275 U	0.000270 U	0.00209 U	0.000235 U	0.00111 U	0.00111 U	0.000286 U	0.000229 U	0.000223 U
	B-214-65	09/07/17	PES	ESC	65	-7.6	S	0.000440 U	0.000373 U	0.00326 U	0.000319 U	0.000313 U	0.00242 U	0.000273 U	0.00129 U	0.00129 U	0.000332 U	0.000265 U	0.000259 U
	B-214-75	09/07/17	PES	ESC	75	-17.6	S	0.000380 U	**0.000642 J**	0.00281 U	0.000276 U	0.000270 U	0.00209 U	0.000236 U	0.00111 U	0.00111 U	0.000287 U	0.000229 U	0.000223 U
	B-214-85	09/07/17	PES	ESC	85	-27.6	S	0.000411 U	**0.000620 J**	0.00304 U	0.000298 U	0.000292 U	0.00226 U	0.000255 U	0.00120 U	0.00120 U	0.000310 U	0.000248 U	0.000242 U
	B-908-100	09/07/17	PES	ESC	85 (dup)	-27.6	S	0.000382 U	**0.000668 J**	0.00283 U	0.000277 U	0.000272 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000288 U	0.000230 U	0.000225 U
	B-214-95	09/07/17	PES	ESC	95	-37.6	S	0.000375 U	**0.00343 J**	0.00278 U	0.000272 U	0.000267 U	0.00206 U	0.000233 U	0.00110 U	0.00110 U	0.000283 U	0.000226 U	0.000221 U
	B-214-105	09/07/17	PES	ESC	105	-47.6	S	0.000433 U	**0.000426 J**	0.00320 U	0.000314 U	0.000307 U	0.00238 U	0.000268 U	0.00127 U	0.00127 U	0.000326 U	0.000261 U	0.000254 U
	B-214-115	09/11/17	PES	ESC	115	-57.6	S	0.000417 U	0.000354 U	0.00309 U	0.000302 U	0.000296 U	0.00229 U	0.000259 U	0.00122 U	0.00122 U	0.000315 U	0.000251 U	0.000245 U
	B-214-120	09/11/17	PES	ESC	120	-62.6	S	0.000404 U	0.000342 U	0.00299 U	0.000293 U	0.000287 U	0.00222 U	0.000250 U	0.00118 U	0.00118 U	0.000305 U	0.000243 U	0.000237 U
B-215	B-215-15	09/12/17	PES	ESC	15	39.0	V	0.000371 U	**0.000333 J**	0.00274 U	0.000269 U	0.000264 U	0.00204 U	0.000230 U	0.00108 U	0.00108 U	0.000280 U	0.000223 U	0.000218 U
	B-215-25	09/12/17	PES	ESC	25	29.0	S	0.000366 U	0.000310 U	0.00271 U	0.000265 U	0.000260 U	0.00201 U	0.000227 U	0.00107 U	0.00107 U	0.000276 U	0.000220 U	0.000215 U
	B-215-35	09/12/17	PES	ESC	35	19.0	S	0.000403 U	**0.000447 J**	0.00298 U	0.000292 U	0.000286 U	0.00222 U	0.000250 U	0.00118 U	0.00118 U	0.000304 U	0.000243 U	0.000237 U
	B-215-45	09/12/17	PES	ESC	45	9.0	S	0.000364 U	**0.00329 J**	0.00269 U	0.000264 U	0.000259 U	0.00200 U	0.000226 U	0.00106 U	0.00106 U	0.000275 U	0.000219 U	0.000214 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	–	–	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	–	–	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
B-215 (continued)	B-215-55	09/12/17	PES	ESC	55	-1.1	S	0.000379 U	**0.000446 J**	0.00280 U	0.000275 U	0.000269 U	0.00208 U	0.000235 U	0.00111 U	0.00111 U	0.000286 U	0.000228 U	0.000223 U
	B-215-65	09/12/17	PES	ESC	65	-11.1	S	0.00978 U	0.00829 U	0.0723 U	0.00709 U	0.00695 U	0.0538 U	0.00606 U	0.0286 U	0.0286 U	0.00738 U	0.00589 U	0.00574 U
	B-215-75	09/12/17	PES	ESC	75	-21.1	S	0.000377 U	0.000320 U	0.00279 U	0.000273 U	0.000268 U	0.00207 U	0.000234 U	0.00110 U	0.00110 U	0.000285 U	0.000227 U	0.000222 U
	B-215-85	09/13/17	PES	ESC	85	-31.1	S	0.000412 U	0.000350 U	0.00305 U	0.000299 U	0.000293 U	0.00227 U	0.000256 U	0.00121 U	0.00121 U	0.000311 U	0.000248 U	0.000242 U
	B-909-115	09/13/17	PES	ESC	85 (dup)	-31.1	S	0.000383 U	**0.000472 J**	0.00283 U	0.000278 U	0.000272 U	0.00211 U	0.000238 U	0.00112 U	0.00112 U	0.000289 U	0.000231 U	0.000225 U
	B-215-95	09/13/17	PES	ESC	95	-41.1	S	0.000409 U	0.000347 U	0.00303 U	0.000297 U	0.000291 U	0.00225 U	0.000254 U	0.00120 U	0.00120 U	0.000309 U	0.000247 U	0.000241 U
B-268	B-268-1	03/17/20	PES	PACE	1	–	V	0.0158 U	0.00131 U	0.00750 U	0.000434 U	0.00107 U	0.0124 U	0.000366 U	0.00824 U	0.00387 U	0.00476 U	0.00146 U	0.00314 U
B-269	B-269-1.5	03/17/20	PES	PACE	1.5	–	V	0.0139 U	**0.00615**	0.00661 U	0.000382 U	**0.00112 J**	0.0109 U	0.000322 U	0.00725 U	**0.00867 J**	0.00419 U	**0.00159 J**	0.00276 U
B-270	B-270-2	03/17/20	PES	PACE	2	–	V	0.0154 U	0.00128 U	0.00732 U	0.000423 U	**0.00347**	0.0121 U	0.000357 U	0.00803 U	0.00377 U	**0.0254**	**0.00824**	**0.0275**
B-271	B-271-1	03/17/20	PES	PACE	1	–	V	0.0136 U	0.00114 U	0.00650 U	0.000376 U	0.000927 U	0.0107 U	0.000317 U	0.00713 U	0.00335 U	0.00412 U	0.00127 U	0.00272 U
B-272	B-272-1	03/17/20	PES	PACE	1	–	V	0.0150 U	**0.0355**	0.00713 U	0.000413 U	0.00102 U	0.0118 U	0.000348 U	0.00783 U	**0.0129 J**	0.00453 U	0.00139 U	0.00298 U
	B-272-6	03/17/20	PES	PACE	6	–	V	0.0157 U	**0.00902**	0.00749 U	0.000433 U	0.00107 U	0.0124 U	0.000365 U	0.00822 U	0.00386 U	0.00475 U	0.00146 U	0.00313 U
B-273	B-273-1	03/17/20	PES	PACE	1	–	V	0.0143 U	0.00119 U	0.00679 U	0.000393 U	0.000969 U	0.0112 U	0.000331 U	0.00745 U	**0.00646 J**	0.00431 U	0.00132 U	0.00284 U
	B-273-3	03/17/20	PES	PACE	3	–	V	0.0140 U	**0.103**	0.00669 U	0.000387 U	0.000954 U	0.0111 U	0.000326 U	0.00734 U	0.00345 U	0.00424 U	0.00130 U	0.00280 U
	B-273-6	03/17/20	PES	PACE	6	–	V	0.0282 U	**0.635**	0.0134 U	0.000777 U	**0.00199 J**	0.0222 U	0.000655 U	0.0147 U	0.00692 U	0.00851 U	0.00261 U	0.00561 U
B-274	B-274-1	03/17/20	PES	PACE	1	–	V	0.0143 U	**0.0904**	0.00680 U	0.000394 U	0.000971 U	0.0112 U	0.000332 U	0.00747 U	**0.0180**	0.00432 U	**0.00171 J**	0.00285 U
	B-274-3	03/17/20	PES	PACE	3	–	V	0.0138 U	**0.0243**	0.00655 U	0.000379 U	0.000934 U	0.0108 U	0.000319 U	0.00719 U	0.00338 U	0.00416 U	0.00128 U	0.00274 U
	B-274-6	03/17/20	PES	PACE	6	–	V	0.0226 U	**0.967**	0.0108 U	0.000622 U	0.00153 U	0.0178 U	0.000524 U	0.0118 U	0.00555 U	0.00683 U	0.00211 U	0.00449 U
B-275	B-275-1	03/17/20	PES	PACE	1	–	V	0.0149 U	**0.00923**	0.00710 U	0.000411 U	0.00101 U	0.0117 U	0.000346 U	0.00779 U	0.00366 U	0.00451 U	0.00139 U	0.00297 U
	B-275-6	03/17/20	PES	PACE	6	–	V	0.0234 U	**0.568**	0.0112 U	0.000649 U	**0.00852**	0.0185 U	0.000546 U	0.0123 U	**0.0429**	**0.00949 J**	**0.0113**	0.00469 U
	B-275-9	03/17/20	PES	PACE	9	–	S	0.0195 U	**0.0189**	0.00931 U	0.000538 U	0.00133 U	0.0154 U	0.000454 U	0.0102 U	**0.00814 J**	0.00591 U	0.00182 U	0.00389 U
	B-275-10	03/17/20	PES	PACE	10	–	S	0.0140 U	**0.00531 J**	0.00665 U	0.000385 U	0.000949 U	0.0110 U	0.000324 U	0.00730 U	0.00343 U	0.00422 U	0.00130 U	0.00278 U
B-276	B-276-1	03/17/20	PES	PACE	1	–	V	0.0234 U	**0.00336 J**	0.0112 U	0.000646 U	0.00159 U	0.0184 U	0.000544 U	0.0123 U	0.00575 U	0.00709 U	0.00217 U	0.00467 U
	B-276-7	03/17/20	PES	PACE	7	–	V	0.0140 U	0.00117 U	0.00669 U	0.000387 U	0.000954 U	0.0111 U	0.000326 U	0.00734 U	0.00345 U	0.00425 U	0.00131 U	0.00280 U
	B-970-6	03/17/20	PES	PACE	7 (dup)	–	V	0.0141 U	0.00117 U	0.00669 U	0.000387 U	0.000955 U	0.0111 U	0.000326 U	0.00735 U	0.00345 U	0.00425 U	0.00131 U	0.00280 U
	B-276-11	03/17/20	PES	PACE	11	–	S	0.0148 U	**0.00869**	0.00707 U	0.000409 U	0.00101 U	0.0117 U	0.000345 U	0.00776 U	**0.0395**	0.00449 U	0.00138 U	0.00296 U
B-277	B-277-1	03/18/20	PES	PACE	1	–	V	0.0160 U	0.00134 U	0.00763 U	0.000441 U	0.00109 U	0.0126 U	0.000372 U	0.00837 U	**0.00421 J**	0.00484 U	0.00149 U	0.00319 U
	B-277-3	03/18/20	PES	PACE	3	–	V	0.0140 U	0.00116 U	0.00665 U	0.000385 U	0.000948 U	0.0110 U	0.000324 U	0.00730 U	**0.00373 J**	0.00422 U	0.00130 U	0.00278 U
	B-277-5	03/18/20	PES	PACE	5	–	V	0.0210 U	0.00175 U	0.00999 U	0.000578 U	0.00143 U	0.0165 U	0.000487 U	0.0110 U	0.00515 U	0.00634 U	0.00195 U	0.00418 U
	B-277-9.5	03/18/20	PES	PACE	9.5	–	V	0.0301 U	**0.00760 J**	0.0144 U	0.000832 U	0.00206 U	0.0238 U	0.000701 U	0.0158 U	**0.0109 J**	0.00912 U	0.00281 U	0.00601 U
	B-277-11	03/18/20	PES	PACE	11	–	S	0.0137 U	0.00114 U	0.00653 U	0.000378 U	0.000931 U	0.0108 U	0.000318 U	0.00717 U	0.00337 U	0.00414 U	0.00127 U	0.00273 U
B-278	B-278-3	03/18/20	PES	PACE	3	–	V	0.0142 U	0.00118 U	0.00675 U	0.000391 U	0.000963 U	0.0112 U	0.000329 U	0.00741 U	**0.00358 J**	0.00429 U	0.00132 U	0.00282 U
	B-278-6	03/18/20	PES	PACE	6	–	V	0.0141 U	0.00118 U	0.00671 U	0.000388 U	0.000957 U	0.0111 U	0.000327 U	0.00736 U	0.00346 U	0.00426 U	0.00131 U	0.00281 U
B-279	B-279-3	03/18/20	PES	PACE	3	–	V	0.0144 U	0.00120 U	0.00686 U	0.000397 U	0.000979 U	0.0113 U	0.000335 U	0.00753 U	**0.00366 J**	0.00436 U	0.00134 U	0.00287 U
	B-279-5	03/18/20	PES	PACE	5	–	V	0.0142 U	0.00119 U	0.00677 U	0.000391 U	0.000965 U	0.0112 U	0.000330 U	0.00742 U	0.00349 U	0.00429 U	0.00132 U	0.00283 U
	B-279-10	03/18/20	PES	PACE	10	–	V	0.0138 U	0.00115 U	0.00657 U	0.000380 U	0.000938 U	0.0109 U	0.000321 U	0.00721 U	0.00339 U	0.00417 U	0.00128 U	0.00275 U
B-280	B-280-4.5	03/18/20	PES	PACE	4.5	–	V	0.0132 U	0.00110 U	0.00627 U	0.000363 U	0.000894 U	0.0104 U	0.000306 U	0.00688 U	0.00323 U	0.00398 U	0.00122 U	0.00262 U
	B-280-6	03/18/20	PES	PACE	6	–	V	0.0138 U	0.00115 U	0.00658 U	0.000381 U	0.000939 U	0.0109 U	0.000321 U	0.00722 U	0.00339 U	0.00418 U	0.00128 U	0.00275 U
B-281	B-281-2	03/18/20	PES	PACE	2	–	V	0.0133 U	0.00111 U	0.00632 U	0.000366 U	0.000902 U	0.0105 U	0.000308 U	0.00694 U	**0.00433 J**	0.00401 U	0.00123 U	0.00264 U
	B-281-5	03/18/20	PES	PACE	5	–	V	0.0144 U	0.00120 U	0.00686 U	0.000397 U	0.000978 U	0.0113 U	0.000334 U	0.00753 U	**0.00373 J**	0.00435 U	0.00134 U	0.00287 U
B-282	B-282-2	03/18/20	PES	PACE	2	–	V	0.0145 U	0.00121 U	0.00690 U	0.000399 U	0.000984 U	0.0114 U	0.000336 U	0.00757 U	**0.00367 J**	0.00438 U	0.00135 U	0.00288 U
	B-282-4	03/18/20	PES	PACE	4	–	V	0.0140 U	0.00117 U	0.00668 U	0.000387 U	0.000953 U	0.0110 U	0.000326 U	0.00733 U	0.00345 U	0.00424 U	0.00130 U	0.00279 U
	B-971-5	03/18/20	PES	PACE	4 (dup)	–	V	0.0135 U	0.00113 U	0.00644 U	0.000372 U	0.000918 U	0.0106 U	0.000314 U	0.00707 U	0.00332 U	0.00409 U	0.00126 U	0.00269 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	–	–	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	–	–	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
B-283	B-283-0.5	08/19/20	PES	PACE	0.5	–	V	0.00722 UJ	0.00272 U	0.00279 U	0.000493 U	0.000511 U	0.00274 U	0.000421 U	0.00799 U	0.00587 UJ	0.00631 U	0.00114 U	0.00346 U
B-284	B-284-1	08/19/20	PES	PACE	1	–	V	0.00720 UJ	0.00271 U	0.00278 U	0.000492 U	0.000510 U	0.00274 U	0.000420 U	0.00797 U	0.00586 UJ	0.00630 U	0.00114 U	0.00346 U
B-285	B-285-1	08/19/20	PES	PACE	1	–	V	0.00784 UJ	0.00295 U	0.00303 U	0.000535 U	**0.00392**	0.00298 U	0.000457 U	0.00867 U	0.00637 UJ	0.00686 U	**0.00340 J**	0.00376 U
B-286	B-286-0.5	08/19/20	PES	PACE	0.5	–	V	0.0160 UJ	**0.0107 J**	0.00617 U	0.00109 U	0.00113 U	0.00607 U	0.000932 U	0.0176 U	0.0130 UJ	0.0140 U	0.00253 U	0.00766 U
B-287	B-287-1	08/19/20	PES	PACE	1	–	V	0.0156 UJ	0.00587 U	0.00602 U	0.00107 U	0.00110 U	0.00593 U	0.000909 U	0.0173 U	0.0127 UJ	0.0136 U	0.00247 U	0.00749 U
B-288	B-288-1	08/19/20	PES	PACE	1	–	V	0.0318 UJ	**0.0430**	0.0123 U	0.00217 U	**0.00318 J**	0.0121 U	0.00186 U	0.0353 U	0.0259 UJ	0.0279 U	**0.0211 J**	0.0153 U
B-289	B-289-0.5	08/19/20	PES	PACE	0.5	–	V	0.0262 UJ	0.00986 U	0.0101 U	0.00179 U	0.00185 U	0.00994 U	0.00153 U	0.0290 U	0.0213 UJ	0.0229 U	0.00416 U	0.0126 U
B-290	B-290-1	08/20/20	PES	PACE	1	–	V	0.00947 UJ	**0.00974**	0.00366 U	0.000647 U	0.000671 U	0.00360 U	0.000553 U	0.0105 U	0.00770 UJ	0.00829 U	**0.00225 J**	0.00454 U
B-291	B-291-1	08/20/20	PES	PACE	1	–	V	0.00813 UJ	0.00306 U	0.00314 U	0.000555 U	0.000576 U	0.00309 U	0.000475 U	0.00900 U	**0.0130 J**	0.00712 U	0.00129 U	0.00390 U
B-292	B-292-3	08/22/20	PES	PACE	3	–	V	0.00755 U	0.00284 U	0.00292 U	0.000516 U	0.000535 U	0.00287 U	0.000440 U	0.00836 U	0.00614 UJ	0.00661 U	0.00120 U	0.00362 U
	B-292-6	08/22/20	PES	PACE	6	–	V	0.00780 U	0.00294 U	0.00302 U	0.000533 U	0.000553 U	0.00296 U	0.000455 U	0.00863 U	0.00634 UJ	0.00683 U	0.00124 U	0.00374 U
	B-292-9	08/22/20	PES	PACE	9	–	V	0.00709 U	0.00267 U	0.00274 U	0.000485 U	0.000502 U	0.00269 U	0.000414 U	0.00785 U	0.00577 UJ	0.00620 U	0.00112 U	0.00340 U
	B-292-12	08/22/20	PES	PACE	12	–	V	0.00788 U	0.00297 U	0.00305 U	0.000538 U	0.000558 U	0.00299 U	0.000459 U	0.00872 U	0.00641 UJ	0.00689 U	0.00125 U	0.00378 U
B-293	B-293-1	08/26/20	PES	PACE	1	–	V	0.00665 UJ	0.00251 U	0.00257 UJ	0.000454 U	0.000471 UJ	0.00253 U	0.000388 U	0.00736 UJ	0.0286 U	0.00582 UJ	0.00105 UJ	0.00319 UJ
B-294	B-294-1	08/26/20	PES	PACE	1	–	V	0.00842 UJ	**0.0216**	0.00326 UJ	0.000575 U	**0.00199 J**	0.00320 U	0.000491 U	0.00932 UJ	**0.0431 J**	0.00737 UJ	**0.00222 J**	0.00404 UJ
	B-294-2	08/26/20	PES	PACE	2	–	V	0.0174 UJ	**0.159**	0.00675 UJ	0.00119 U	**0.0105**	0.00662 U	0.00102 U	0.0194 UJ	**0.110 J**	0.0153 UJ	**0.0224**	0.00944 UJ
	B-294-6	08/26/20	PES	PACE	6	–	V	0.0171 UJ	**0.00827 J**	0.00662 UJ	0.00117 U	0.00121 UJ	0.00651 U	0.000999 U	0.0189 UJ	**0.0792 J**	0.0150 UJ	0.00271 UJ	0.00821 UJ
	B-294-10	08/26/20	PES	PACE	10	–	S	0.00808 UJ	0.00304 U	0.00312 UJ	0.000552 U	0.000572 UJ	0.00307 U	0.000471 U	0.00894 UJ	0.0304 U	0.00707 UJ	0.00128 UJ	0.00388 UJ
B-295	B-295-1	08/26/20	PES	PACE	1	–	V	0.00722 UJ	0.00272 U	0.00279 UJ	0.000493 U	0.000512 UJ	0.00274 U	0.000421 U	0.00799 UJ	0.0250 U	0.00632 UJ	0.00114 UJ	0.00347 UJ
	B-295-3	08/26/20	PES	PACE	3	–	V	0.0107 UJ	**0.00567 J**	0.00414 UJ	0.000731 U	0.000758 UJ	0.00407 U	0.000624 U	0.0118 UJ	**0.0432 J**	0.00937 UJ	0.00169 UJ	0.00514 UJ
	B-295-7	08/26/20	PES	PACE	7	–	V	0.00899 UJ	**0.0150**	0.00348 UJ	0.000614 U	0.000637 UJ	0.00342 U	0.000524 U	0.00995 UJ	0.0334 U	0.00787 UJ	0.00142 UJ	0.00432 UJ
	B-295-10	08/26/20	PES	PACE	10	–	S	0.00843 UJ	**0.0170**	0.00326 UJ	0.000576 U	0.000597 UJ	0.00320 U	0.000492 U	0.00933 UJ	0.0287 U	0.00738 UJ	0.00134 UJ	0.00405 UJ
B-296	B-296-1	08/26/20	PES	PACE	1	–	V	0.00682 UJ	0.00257 U	0.00264 UJ	0.000466 U	0.000483 UJ	0.00259 U	0.000398 U	0.00754 UJ	0.0307 U	0.00596 UJ	0.00108 UJ	0.00327 UJ
B-297	B-297-1	08/26/20	PES	PACE	1	–	V	0.00739 UJ	0.00278 U	0.00286 UJ	0.000505 U	0.000524 UJ	0.00281 U	0.000431 U	0.00818 UJ	0.00601 U	0.00647 UJ	0.00117 UJ	0.00355 UJ
	B-297-3	08/26/20	PES	PACE	3	–	V	0.00689 UJ	**0.00335 J**	0.00267 UJ	0.000471 U	0.000488 UJ	0.00262 U	0.000402 U	0.00763 UJ	0.00561 U	0.00603 UJ	0.00109 UJ	0.00331 UJ
	B-500-1	08/26/20	PES	PACE	3 (dup)	–	V	0.00703 U	0.00265 U	0.00272 U	0.000480 U	0.000498 U	0.00267 U	0.000410 U	0.00778 U	0.0268 U	0.00615 U	0.00111 U	0.00338 U
	B-297-5	08/26/20	PES	PACE	5	–	V	0.00686 U	**0.00429 J**	0.00265 U	0.000469 U	0.000486 U	0.00261 U	0.000400 U	0.00759 U	**0.00999 J**	0.00600 U	0.00109 U	0.00329 U
B-298	B-298-5	08/26/20	PES	PACE	5	–	V	0.00633 U	0.00238 U	0.00244 U	0.000433 U	0.000448 U	0.00240 U	0.000369 U	0.00701 U	0.0322 U	0.00554 U	0.00100 U	0.00304 U
	B-298-6	08/26/20	PES	PACE	6	–	V	0.00761 U	**0.0115**	0.00295 U	0.000521 U	0.000540 U	0.00289 U	**0.000635 J**	0.00843 U	**0.0404**	0.00666 U	**0.00156 J**	0.00366 U
B-299	B-299-2	02/01/21	PES	PACE	2	–	V	0.00792 U	0.00298 U	0.00306 U	0.000541 U	0.000561 U	0.00301 UJ	0.000462 U	0.00877 U	0.00644 U	0.00693 U	0.00125 UJ	0.00380 U
	B-299-5.5	02/01/21	PES	PACE	5.5	–	V	0.00715 U	0.00269 U	0.00277 U	0.000489 U	0.000507 U	0.00272 UJ	0.000417 U	0.00791 U	0.00582 UJ	0.00626 U	0.00113 UJ	0.00343 U
	B-1003-10	02/01/21	PES	PACE	5.5 (dup)	–	V	0.00744 U	0.00280 U	0.00288 U	0.000508 U	0.000527 U	0.00283 UJ	0.000434 U	0.00823 U	0.00605 U	0.00651 U	0.00118 UJ	0.00357 U
B-300	B-300-2.5	02/01/21	PES	PACE	2.5	–	V	0.00793 U	0.00299 U	0.00307 U	0.000542 U	0.000562 U	0.00301 UJ	0.000463 U	0.00878 U	0.00645 U	0.00694 U	0.00126 UJ	0.00381 U
	B-300-5.5	02/01/21	PES	PACE	5.5	–	V	0.00774 U	0.00291 U	0.00299 U	0.000529 U	0.000548 U	0.00294 UJ	0.000451 U	0.00856 U	0.00629 U	0.00677 U	0.00123 UJ	0.00371 U
B-301	B-301-2	02/01/21	PES	PACE	2	–	V	0.00770 U	0.00290 U	0.00298 U	0.000526 U	0.000545 U	0.00292 UJ	0.000449 U	0.00852 U	0.00626 U	0.00673 U	0.00122 UJ	0.00369 U
	B-301-5	02/01/21	PES	PACE	5	–	V	0.00811 U	0.00305 U	0.00314 U	0.000554 U	0.000574 U	0.00308 UJ	0.000473 U	0.00897 U	0.00660 U	0.00710 U	0.00128 UJ	0.00389 U
B-302	B-302-2	02/01/21	PES	PACE	2	–	V	0.00751 U	0.00283 U	0.00290 U	0.000513 U	0.000532 U	0.00285 UJ	0.000438 U	0.00831 U	0.00611 U	0.00657 U	0.00119 UJ	0.00360 U
	B-302-4	02/01/21	PES	PACE	4	–	V	0.00856 U	0.00322 U	0.00331 U	0.000585 U	0.000606 U	0.00325 UJ	0.000499 U	0.00947 U	0.00696 U	0.00749 U	0.00136 UJ	0.00411 U
BB-5	S-6	03/09/97	B&V	Unknown	15-17	34.0	V	–	–	–	–	–	–	–	–	–	–	–	–
	S-10	03/09/97	B&V	Unknown	25-27	24.0	S	–	–	–	–	–	–	–	–	–	–	–	–
BB-7	S-4	04/06/97	B&V	Unknown	10-12	17.0	S	–	–	–	–	–	–	–	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
BB-8 (13.6 to 3.6)	S-8	06/06/97	B&V	Unknown	20-22	23.6	S	–	–	–	–	–	–	–	–	–	–	–	–
BB-10	S-6	08/29/97	B&V	Unknown	15-17	42.0	V	–	–	–	–	–	–	–	–	–	–	–	–
BB-12	S-3	03/18/98	B&V	Unknown	15-16.5	18.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	S-14	03/18/98	B&V	Unknown	45-46.5	-11.2	S	–	–	–	–	–	–	–	–	–	–	–	–
BB-13	S-10	03/19/98	B&V	Unknown	25-27.5	1.9	S	–	–	–	–	–	–	–	–	–	–	–	–
	S-16	03/19/98	B&V	Unknown	40-41.5	-13.1	S	–	–	–	–	–	–	–	–	–	–	–	–
BB-14	S-2	03/03/98	B&V	Unknown	5-6.5	21.3	V	–	–	–	–	–	–	–	–	–	–	–	–
	S-5	03/03/98	B&V	Unknown	12.5-14	14.3	S	–	–	–	–	–	–	–	–	–	–	–	–
	S-9	03/03/98	B&V	Unknown	22.5-24	4.3	S	–	–	–	–	–	–	–	–	–	–	–	–
	S-12	03/03/98	B&V	Unknown	30-31.5	-4.3	S	–	–	–	–	–	–	–	–	–	–	–	–
CHB-07	CHB-07-12.5-13.5	04/14/05	CH2M	ARI	12.5-13.5	16.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	CHB-07-5.0-7.0	04/14/08	CH2M	ARI	5-7	23.5	S	–	–	–	–	–	–	–	–	–	–	–	–
CHB-08	CHB-08-15.0-16.0	04/15/08	CH2M	ARI	15-16	14.1	S	–	–	–	–	–	–	–	–	–	–	–	–
CHB-09	CHB-09-20.0-21.5	04/16/08	CH2M	ARI	20-21.5	15.4	S	–	–	–	–	–	–	–	–	–	–	–	–
	CHB-09-25.0-26.5	04/16/08	CH2M	ARI	25-26.5	10.4	S	–	–	–	–	–	–	–	–	–	–	–	–
GEI-MW-1 (-9.7 to -29.7)	MW-1-1-2.5	08/22/14	GEI	Fremont	1	29.5	V	–	–	–	–	–	–	–	–	–	–	–	–
GEI-MW-2 (4.0 to -6.0)	MW-2-2-5.0	08/23/14	GEI	Fremont	5	26.6	V	–	–	–	–	–	–	–	–	–	–	–	–
	MW-2-4-10.0	08/23/14	GEI	Fremont	10	21.6	S	–	–	–	–	–	–	–	–	–	–	–	–
	MW-2-8-20.0	08/23/14	GEI	Fremont	20	11.6	S	–	–	–	–	–	–	–	–	–	–	–	–
GEI-MW-3 (-18.7 to -28.7)	MW-3-4-10.0	08/23/14	GEI	Fremont	10	20.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	MW-3-10-50.0	08/23/14	GEI	Fremont	50	-19.3	S	–	–	–	–	–	–	–	–	–	–	–	–
GEI-4	GEI-4-2-5.0	08/23/14	GEI	Fremont	5	26.0	V	–	–	–	–	–	–	–	–	–	–	–	–
	GEI-4-5-12.5	08/23/14	GEI	Fremont	12.5	18.5	S	–	–	–	–	–	–	–	–	–	–	–	–
MW-1 (SCLB-3)	RS3-2.5	03/15/93	EPJ	OnSite	2.5	37.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS3-7.5	03/15/93	EPJ	OnSite	7.5	32.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS3-17.5	03/15/93	EPJ	OnSite	17.5	22.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	RS3-22.5/RS3-27.5 (Comp)	03/15/93	EPJ	OnSite	22.5-27.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–
	RS3-32.5	03/15/93	EPJ	OnSite	32.5	7.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	RS3-37.5	03/15/93	EPJ	OnSite	37.5	2.5	S	–	–	–	–	–	–	–	–	–	–	–	–
MW-2 (SCLB-4)	RS4-2.5	03/15/93	EPJ	OnSite	2.5	37.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS4-7.5	03/15/93	EPJ	OnSite	7.5	32.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS4-12.5/RS4-17.5	03/15/93	EPJ	OnSite	12.5-17.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–
	RS4-22.5/RS4-27.5 (Comp)	03/15/93	EPJ	OnSite	22.5-27.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–
	RS4-37.5	03/15/93	EPJ	OnSite	37.5	2.5	S	–	–	–	–	–	–	–	–	–	–	–	–
MW-3 (SCLB-5)	RS5-2.5/RS5-7.5 (Comp)	03/16/93	EPJ	OnSite	2.5-7.5	–	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS5-12.5/RS5-17.5 (Comp)	03/16/93	EPJ	OnSite	12.5-17.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–
	RS5-17.5	03/16/93	EPJ	OnSite	17.5	21.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	RS5-22.5	03/16/93	EPJ	OnSite	22.5	16.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	RS5-32.5	03/16/93	EPJ	OnSite	32.5	6.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	RS5-37.5	03/16/93	EPJ	OnSite	37.5	1.5	S	–	–	–	–	–	–	–	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
MW-4 (SCLB-6)	RS6-2.5	03/17/93	EPJ	OnSite	2.5	37.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS6-7.5	03/17/93	EPJ	OnSite	7.5	32.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS6-12.5	03/17/93	EPJ	OnSite	12.5	27.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS6-17.5/RS6-22.5 (Comp)	03/17/93	EPJ	OnSite	17.5-22.5	–	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS6-27.5	03/17/93	EPJ	OnSite	27.5	12.5	S	–	–	–	–	–	–	–	–	–	–	–	–
MW-5 (SCLB-7)	RS7-2.5	03/17/93	EPJ	OnSite	2.5	37.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS7-7.5	03/17/93	EPJ	OnSite	7.5	32.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS7-12.5	03/17/93	EPJ	OnSite	12.5	27.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS7-17.5	03/17/93	EPJ	OnSite	17.5	22.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	RS7-22.5	03/17/93	EPJ	OnSite	22.5	17.5	S	–	–	–	–	–	–	–	–	–	–	–	–
MW-6	MW6-25	10/11/93	Retec	ARI	25	13.2	S	–	–	–	–	–	–	–	–	–	–	–	–
MW-7	MW7-16.5	10/11/93	Retec	ARI	16.5	18.6	S	–	–	–	–	–	–	–	–	–	–	–	–
	MW7-18.5	10/11/93	Retec	ARI	18.5	16.6	S	–	–	–	–	–	–	–	–	–	–	–	–
MW-8 (28.7 to 14.2)	MW8-20	10/18/93	Retec	AAL	20	13.2	S	–	–	–	–	–	–	–	–	–	–	–	–
MW-9 (33.7 to 18.7)	MW9-17.5	10/18/93	Retec	AAL	17.5	23.6	S	–	–	–	–	–	–	–	–	–	–	–	–
MW-10	MW10-17.5	10/19/93	Retec	AAL	17.5	20.5	S	–	–	–	–	–	–	–	–	–	–	–	–
MW102 (B102) (-65.8 to -75.8)	B102-20	07/17/12	SES	F&BI	20	29.2	S	–	–	–	–	–	–	–	–	–	–	–	–
	B102-30	07/17/12	SES	F&BI	30	19.2	S	–	–	–	–	–	–	–	–	–	–	–	–
	B102-38	07/17/12	SES	F&BI	38	11.2	S	–	–	–	–	–	–	–	–	–	–	–	–
	B102-40	07/17/12	SES	F&BI	40	9.2	S	–	–	–	–	–	–	–	–	–	–	–	–
	B102-49	07/17/12	SES	F&BI	49	0.2	S	–	–	–	–	–	–	–	–	–	–	–	–
	B102-60	07/17/12	SES	F&BI	60	-10.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	B102-70	07/18/12	SES	F&BI	70	-20.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	B102-80	07/19/12	SES	F&BI	80	-30.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	B102-90	07/19/12	SES	F&BI	90	-40.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	B102-100	07/20/12	SES	F&BI	100	-50.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	B102-110	07/20/12	SES	F&BI	110	-60.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	B102-120	07/23/12	SES	F&BI	120	-70.8	S	–	–	–	–	–	–	–	–	–	–	–	–
MW103 (B103) (-67.6 to -77.6)	B103-10	07/25/12	SES	F&BI	10	25.9	V	–	–	–	–	–	–	–	–	–	–	–	–
	B103-18	07/25/12	SES	F&BI	18	17.9	S	–	–	–	–	–	–	–	–	–	–	–	–
	B103-30	07/25/12	SES	F&BI	30	5.9	S	–	–	–	–	–	–	–	–	–	–	–	–
	B103-40	07/25/12	SES	F&BI	40	-4.1	S	–	–	–	–	–	–	–	–	–	–	–	–
	B103-45	07/25/12	SES	F&BI	45	-9.1	S	–	–	–	–	–	–	–	–	–	–	–	–
	B103-55	07/25/12	SES	F&BI	55	-19.1	S	–	–	–	–	–	–	–	–	–	–	–	–
	B103-62.5	07/26/12	SES	F&BI	62.5	-26.6	S	–	–	–	–	–	–	–	–	–	–	–	–
	B103-75	07/26/12	SES	F&BI	75	-39.1	S	–	–	–	–	–	–	–	–	–	–	–	–
	B103-83	07/26/12	SES	F&BI	83	-47.1	S	–	–	–	–	–	–	–	–	–	–	–	–
	B103-95	07/26/12	SES	F&BI	95	-59.1	S	–	–	–	–	–	–	–	–	–	–	–	–
	B103-105	07/27/12	SES	F&BI	105	-69.1	S	–	–	–	–	–	–	–	–	–	–	–	–
	B103-113	07/27/12	SES	F&BI	113	-77.1	S	–	–	–	–	–	–	–	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
MW104 (B104) (-76.3 to -86.3)	B104-10	07/30/12	SES	F&BI	10	32.7	S	–	–	–	–	–	–	–	–	–	–	–	–
	B104-20	07/30/12	SES	F&BI	20	22.7	S	–	–	–	–	–	–	–	–	–	–	–	–
	B104-30	07/30/12	SES	F&BI	30	12.7	S	–	–	–	–	–	–	–	–	–	–	–	–
	B104-35	07/30/12	SES	F&BI	35	7.7	S	–	–	–	–	–	–	–	–	–	–	–	–
	B104-50	07/30/12	SES	F&BI	50	-7.3	S	–	–	–	–	–	–	–	–	–	–	–	–
	B104-60	07/31/12	SES	F&BI	60	-17.3	S	–	–	–	–	–	–	–	–	–	–	–	–
	B104-69	07/31/12	SES	F&BI	69	-26.3	S	–	–	–	–	–	–	–	–	–	–	–	–
	B104-80	07/31/12	SES	F&BI	80	-37.3	S	–	–	–	–	–	–	–	–	–	–	–	–
	B104-90	08/01/12	SES	F&BI	90	-47.3	S	–	–	–	–	–	–	–	–	–	–	–	–
	B104-100	08/01/12	SES	F&BI	100	-57.3	S	–	–	–	–	–	–	–	–	–	–	–	–
	B104-110	08/01/12	SES	F&BI	110	-67.3	S	–	–	–	–	–	–	–	–	–	–	–	–
	B104-120	08/01/12	SES	F&BI	120	-77.3	S	–	–	–	–	–	–	–	–	–	–	–	–
	B104-130	08/01/12	SES	F&BI	130	-87.3	S	–	–	–	–	–	–	–	–	–	–	–	–
MW105 (B105) (-85.8 to -95.8)	B105-10	08/06/12	SES	F&BI	10	34.2	V	–	–	–	–	–	–	–	–	–	–	–	–
	B105-20	08/06/12	SES	F&BI	20	24.2	S	–	–	–	–	–	–	–	–	–	–	–	–
	B105-30	08/06/12	SES	F&BI	30	14.2	S	–	–	–	–	–	–	–	–	–	–	–	–
	B105-40	08/08/12	SES	F&BI	40	4.2	S	–	–	–	–	–	–	–	–	–	–	–	–
	B105-50	08/08/12	SES	F&BI	50	-5.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	B105-60	08/09/12	SES	F&BI	60	-15.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	B105-70	08/09/12	SES	F&BI	70	-25.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	B105-80	08/09/12	SES	F&BI	80	-35.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	B105-90	08/10/12	SES	F&BI	90	-45.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	B105-100	08/10/12	SES	F&BI	100	-55.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	B105-110	08/10/12	SES	F&BI	110	-65.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	B105-120	08/10/12	SES	F&BI	120	-75.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	B105-130	08/10/12	SES	F&BI	130	-85.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	B105-138	08/10/12	SES	F&BI	138	-93.8	S	–	–	–	–	–	–	–	–	–	–	–	–
MW106 (B106) (-78.0 to -88.0)	B106-10	08/14/12	SES	F&BI	10	42.0	V	–	–	–	–	–	–	–	–	–	–	–	–
	B106-20	08/14/12	SES	F&BI	20	32.0	V	–	–	–	–	–	–	–	–	–	–	–	–
	B106-30	08/14/12	SES	F&BI	30	22.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B106-40	08/14/12	SES	F&BI	40	12.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B106-50	08/14/12	SES	F&BI	50	2.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B106-60	08/14/12	SES	F&BI	60	-8.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B106-70	08/15/12	SES	F&BI	70	-18.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B106-80	08/15/12	SES	F&BI	80	-28.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B106-90	08/15/12	SES	F&BI	90	-38.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B106-100	08/15/12	SES	F&BI	100	-48.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B106-110	08/15/12	SES	F&BI	110	-58.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B106-120	08/15/12	SES	F&BI	120	-68.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B106-130	08/15/12	SES	F&BI	130	-78.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B106-140	08/15/12	SES	F&BI	140	-88.0	S	–	–	–	–	–	–	–	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
MW107 (B107) (8.8 to -1.2)	B107-05	03/12/12	SES	F&BI	5	38.8	V	–	–	–	–	–	–	–	–	–	–	–	–
	B107-15	03/12/12	SES	F&BI	15	28.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	B107-25	03/12/12	SES	F&BI	25	18.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	B107-35	03/12/12	SES	F&BI	35	8.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	B107-45	03/12/12	SES	F&BI	45	-1.2	S	–	–	–	–	–	–	–	–	–	–	–	–
MW108 (B108) (-7.2 to -17.2)	B108-15	12/14/12	SES	F&BI	15	17.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	B108-25	12/14/12	SES	F&BI	25	7.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	B108-35	12/14/12	SES	F&BI	35	-2.2	S	–	–	–	–	–	–	–	–	–	–	–	–
	B108-45	12/14/12	SES	F&BI	45	-12.2	S	–	–	–	–	–	–	–	–	–	–	–	–
	B108-50	12/14/12	SES	F&BI	50	-17.2	S	–	–	–	–	–	–	–	–	–	–	–	–
MW109 (B109) (0.0 to -10.0)	B109-05	04/12/12	SES	F&BI	5	30.0	V	–	–	–	–	–	–	–	–	–	–	–	–
	B109-15	04/12/12	SES	F&BI	15	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B109-25	04/12/12	SES	F&BI	25	10.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B109-35	04/12/12	SES	F&BI	35	0.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B109-45	04/12/12	SES	F&BI	45	-10.0	S	–	–	–	–	–	–	–	–	–	–	–	–
MW110 (B110) (4.7 to -5.3)	B110-15	04/12/12	SES	F&BI	15	24.7	V	–	–	–	–	–	–	–	–	–	–	–	–
	B110-25	04/12/12	SES	F&BI	25	14.7	S	–	–	–	–	–	–	–	–	–	–	–	–
	B110-35	04/12/12	SES	F&BI	35	4.7	S	–	–	–	–	–	–	–	–	–	–	–	–
	B110-45	04/12/12	SES	F&BI	45	-5.3	S	–	–	–	–	–	–	–	–	–	–	–	–
MW111 (B111) (-33.5 to -43.5)	B111-10	05/12/12	SES	F&BI	10	26.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	B111-20	05/12/12	SES	F&BI	20	16.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B111-30	05/12/12	SES	F&BI	30	6.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B111-38	05/12/12	SES	F&BI	38	-1.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B111-50	05/12/12	SES	F&BI	50	-13.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B111-60	06/12/12	SES	F&BI	60	-23.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B111-70	06/12/12	SES	F&BI	70	-33.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B111-80	06/12/12	SES	F&BI	80	-43.5	S	–	–	–	–	–	–	–	–	–	–	–	–
MW112 (B112) (-17.5 to -27.5)	B112-10	11/12/12	SES	F&BI	10	47.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	B112-20	11/12/12	SES	F&BI	20	37.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B112-30	11/12/12	SES	F&BI	30	27.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B112-40	11/12/12	SES	F&BI	40	17.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B112-50	11/12/12	SES	F&BI	50	7.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B112-60	11/12/12	SES	F&BI	60	-2.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B112-75	11/12/12	SES	F&BI	75	-17.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	B112-85	12/12/12	SES	F&BI	85	-27.5	S	–	–	–	–	–	–	–	–	–	–	–	–
MW113 (B113) (-37.1 to -47.1)	B113-10	12/18/12	SES	F&BI	10	22.9	S	–	–	–	–	–	–	–	–	–	–	–	–
	B113-20	12/18/12	SES	F&BI	20	12.9	S	–	–	–	–	–	–	–	–	–	–	–	–
	B113-30	12/18/12	SES	F&BI	30	2.9	S	–	–	–	–	–	–	–	–	–	–	–	–
	B113-40	12/18/12	SES	F&BI	40	-7.1	S	–	–	–	–	–	–	–	–	–	–	–	–
	B113-50	12/18/12	SES	F&BI	50	-17.1	S	–	–	–	–	–	–	–	–	–	–	–	–
MW114 (B114) (10.8 to 0.8)	B114-15	10/12/12	SES	F&BI	15	30.8	V	–	–	–	–	–	–	–	–	–	–	–	–
	B114-25	10/12/12	SES	F&BI	25	20.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	B114-35	10/12/12	SES	F&BI	35	10.8	S	–	–	–	–	–	–	–	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
MW114 (B114)	B114-40	10/12/12	SES	F&BI	40	5.8	S	–	–	–	–	–	–	–	–	–	–	–	–
(continued)	B114-45	10/12/12	SES	F&BI	45	0.8	S	–	–	–	–	–	–	–	–	–	–	–	–
MW115 (B115)	B115-10	12/13/12	SES	F&BI	10	24.1	V	–	–	–	–	–	–	–	–	–	–	–	–
(-0.9 to -10.9)	B115-15	12/13/12	SES	F&BI	15	19.1	S	–	–	–	–	–	–	–	–	–	–	–	–
	B115-25	12/13/12	SES	F&BI	25	9.1	S	–	–	–	–	–	–	–	–	–	–	–	–
	B115-35	12/13/12	SES	F&BI	35	-0.9	S	–	–	–	–	–	–	–	–	–	–	–	–
	B115-45	12/13/12	SES	F&BI	45	-10.9	S	–	–	–	–	–	–	–	–	–	–	–	–
MW116 (B116)	B116-15	07/12/12	SES	F&BI	15	16.4	S	–	–	–	–	–	–	–	–	–	–	–	–
(-3.6 to -13.6)	B116-25	07/12/12	SES	F&BI	25	6.4	S	–	–	–	–	–	–	–	–	–	–	–	–
	B116-35	07/12/12	SES	F&BI	35	-3.6	S	–	–	–	–	–	–	–	–	–	–	–	–
	B116-45	07/12/12	SES	F&BI	45	-13.6	S	–	–	–	–	–	–	–	–	–	–	–	–
MW117 (B117)	B117-10	02/04/13	SES	F&BI	10	46.9	V	–	–	–	–	–	–	–	–	–	–	–	–
(16.9 to 1.9)	B117-20	02/04/13	SES	F&BI	20	36.9	V	–	–	–	–	–	–	–	–	–	–	–	–
	B117-30	02/04/13	SES	F&BI	30	26.9	S	–	–	–	–	–	–	–	–	–	–	–	–
	B117-40	02/04/13	SES	F&BI	40	16.9	S	–	–	–	–	–	–	–	–	–	–	–	–
	B117-50	02/04/13	SES	F&BI	50	6.9	S	–	–	–	–	–	–	–	–	–	–	–	–
MW118 (B118)	B118-10	03/21/13	SES	F&BI	10	42.9	V	–	–	–	–	–	–	–	–	–	–	–	–
(12.9 to 2.9)	B118-20	03/21/13	SES	F&BI	20	32.9	V	–	–	–	–	–	–	–	–	–	–	–	–
	B118-30	03/21/13	SES	F&BI	30	22.9	S	–	–	–	–	–	–	–	–	–	–	–	–
	B118-40	03/21/13	SES	F&BI	40	12.9	S	–	–	–	–	–	–	–	–	–	–	–	–
	B118-50	03/21/13	SES	F&BI	50	2.9	S	–	–	–	–	–	–	–	–	–	–	–	–
MW119 (B119)	B119-10	03/21/13	SES	F&BI	10	27.4	V	–	–	–	–	–	–	–	–	–	–	–	–
(2.4 to -7.7)	B119-20	03/21/13	SES	F&BI	20	17.4	S	–	–	–	–	–	–	–	–	–	–	–	–
	B119-30	03/21/13	SES	F&BI	30	7.4	S	–	–	–	–	–	–	–	–	–	–	–	–
	B119-40	03/21/13	SES	F&BI	40	-2.7	S	–	–	–	–	–	–	–	–	–	–	–	–
MW120 (B120)	B120-20	12/16/13	SES	F&BI	20	20.0	S	–	–	–	–	–	–	–	–	–	–	–	–
(0 to -10)	B120-30	12/16/13	SES	F&BI	30	10.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B120-45	12/16/13	SES	F&BI	45	-5.0	S	–	–	–	–	–	–	–	–	–	–	–	–
MW121 (B121)	B121-15	12/16/13	SES	F&BI	15	26.7	S	–	–	–	–	–	–	–	–	–	–	–	–
(26.7 to 16.7)	B121-25	12/16/13	SES	F&BI	25	16.7	S	–	–	–	–	–	–	–	–	–	–	–	–
MW122 (B122)	B122-15	12/17/13	SES	F&BI	15	15.0	S	–	–	–	–	–	–	–	–	–	–	–	–
(-75 to -89)	B122-25	12/17/13	SES	F&BI	25	5.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B122-40	12/17/13	SES	F&BI	40	-10.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B122-45	12/17/13	SES	F&BI	45	-15.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B122-50	12/17/13	SES	F&BI	50	-20.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B122-60	12/17/13	SES	F&BI	60	-30.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B122-70	12/17/13	SES	F&BI	70	-40.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B122-80	12/17/13	SES	F&BI	80	-50.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B122-100	12/17/13	SES	F&BI	100	-70.0	S	–	–	–	–	–	–	–	–	–	–	–	–
MW123 (B123)	B123-20	12/18/13	SES	F&BI	20	7.5	S	–	–	–	–	–	–	–	–	–	–	–	–
(-42.5 to -52.5)																			

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
MW124 (B124)	B124-10	12/19/13	SES	F&BI	10	46.2	V	–	–	–	–	–	–	–	–	–	–	–	–
(-53.8 to -63.8)	B124-20	12/19/13	SES	F&BI	20	36.2	V	–	–	–	–	–	–	–	–	–	–	–	–
	B124-30	12/19/13	SES	F&BI	30	26.2	S	–	–	–	–	–	–	–	–	–	–	–	–
	B124-40	12/19/13	SES	F&BI	40	16.2	S	–	–	–	–	–	–	–	–	–	–	–	–
	B124-50	12/19/13	SES	F&BI	50	6.2	S	–	–	–	–	–	–	–	–	–	–	–	–
	B124-60	12/19/13	SES	F&BI	60	-3.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	B124-70	12/19/13	SES	F&BI	70	-13.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	B124-80	12/19/13	SES	F&BI	80	-23.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	B124-90	12/19/13	SES	F&BI	90	-33.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	B124-100	12/19/13	SES	F&BI	100	-43.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	B124-110	12/19/13	SES	F&BI	110	-53.8	S	–	–	–	–	–	–	–	–	–	–	–	–
	B124-120	12/19/13	SES	F&BI	120	-63.8	S	–	–	–	–	–	–	–	–	–	–	–	–
MW125 (B125)	B125-15	12/20/13	SES	F&BI	15	28.6	S	–	–	–	–	–	–	–	–	–	–	–	–
(28.6 to 13.6)	B125-20	12/20/13	SES	F&BI	20	23.6	S	–	–	–	–	–	–	–	–	–	–	–	–
	B125-25	12/20/13	SES	F&BI	25	18.6	S	–	–	–	–	–	–	–	–	–	–	–	–
	B125-30	12/20/13	SES	F&BI	30	13.6	S	–	–	–	–	–	–	–	–	–	–	–	–
MW126 (B126)	B126-20	12/30/13	SES	F&BI	20	10.9	S	–	–	–	–	–	–	–	–	–	–	–	–
(-54.1 to -64.1)	B126-35	12/30/13	SES	F&BI	35	-4.1	S	–	–	–	–	–	–	–	–	–	–	–	–
	B126-45	12/30/13	SES	F&BI	45	-14.1	S	–	–	–	–	–	–	–	–	–	–	–	–
	B126-55	12/30/13	SES	F&BI	55	-24.1	S	–	–	–	–	–	–	–	–	–	–	–	–
	B126-60	12/31/13	SES	F&BI	60	-29.1	S	–	–	–	–	–	–	–	–	–	–	–	–
	B126-65	01/01/14	SES	F&BI	65	-34.1	S	–	–	–	–	–	–	–	–	–	–	–	–
	B126-75	01/02/14	SES	F&BI	75	-44.1	S	–	–	–	–	–	–	–	–	–	–	–	–
	B126-80	01/03/14	SES	F&BI	80	-49.1	S	–	–	–	–	–	–	–	–	–	–	–	–
	B126-85	01/04/14	SES	F&BI	85	-54.1	S	–	–	–	–	–	–	–	–	–	–	–	–
	B126-95	01/05/14	SES	F&BI	95	-64.1	S	–	–	–	–	–	–	–	–	–	–	–	–
MW127 (B127)	B127-15	12/31/13	SES	F&BI	15	24.0	V	–	–	–	–	–	–	–	–	–	–	–	–
(-1.0 to -11.0)	B127-25	12/31/13	SES	F&BI	25	14.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B127-40	12/31/13	SES	F&BI	40	-1.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B127-45	12/31/13	SES	F&BI	45	-6.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B127-50	12/31/13	SES	F&BI	50	-11.0	S	–	–	–	–	–	–	–	–	–	–	–	–
MW128 (B128)	B128-25	01/09/14	SES	F&BI	25	2.9	S	–	–	–	–	–	–	–	–	–	–	–	–
(-30.8 to -40.8)	B128-45	01/09/14	SES	F&BI	45	-17.1	S	–	–	–	–	–	–	–	–	–	–	–	–
	B128-65	01/09/14	SES	F&BI	65	-37.1	S	–	–	–	–	–	–	–	–	–	–	–	–
MW-138	MW-138-15	09/12/17	PES	ESC	15	42.5	V	0.000407 U	0.000345 U	0.00301 U	0.000295 U	0.000289 U	0.00223 U	0.000252 U	0.00119 U	0.00119 U	0.000307 U	0.000245 U	0.000239 U
(-47.5 to -57.5)	MW-138-25	09/12/17	PES	ESC	25	32.5	S	0.000394 U	0.000334 U	0.00291 U	0.000285 U	0.000280 U	0.00216 U	0.000244 U	0.00115 U	0.00115 U	0.000297 U	0.000237 U	0.000231 U
	MW-138-35	09/12/17	PES	ESC	35	22.5	S	0.000365 U	0.000310 U	0.00270 U	0.000265 U	0.000260 U	0.00201 U	0.000227 U	0.00107 U	0.00107 U	0.000276 U	0.000220 U	0.000215 U
	MW-138-45	09/12/17	PES	ESC	45	12.5	S	0.000362 U	0.000307 U	0.00267 U	0.000262 U	0.000257 U	0.00199 U	0.000224 U	0.00106 U	0.00106 U	0.000273 U	0.000218 U	0.000212 U
	MW-138-56	09/12/17	PES	ESC	56	1.5	S	0.000385 U	**0.00365 J**	0.00285 U	0.000279 U	0.000273 U	0.00211 U	0.000238 U	0.00112 U	0.00112 U	0.000290 U	0.000232 U	0.000226 U
	MW-138-65	09/13/17	PES	ESC	65	-7.5	S	0.000370 U	**0.000387 J**	0.00274 U	0.000268 U	0.000263 U	0.00203 U	0.000229 U	0.00108 U	0.00108 U	0.000279 U	0.000223 U	0.000217 U
	B-910-90	09/13/17	PES	ESC	65 (dup)	-7.5	S	0.000396 U	**0.000629 J**	0.00293 U	0.000287 U	0.000282 U	0.00218 U	0.000246 U	0.00116 U	0.00116 U	0.000299 U	0.000239 U	0.000233 U
	MW-138-75	09/13/17	PES	ESC	75	-17.5	S	0.000377 U	**0.00110 J**	0.00279 U	0.000273 U	0.000268 U	0.00207 U	0.000233 U	0.00110 U	0.00110 U	0.000284 U	0.000227 U	0.000221 U
	MW-138-85	09/13/17	PES	ESC	85	-27.5	S	0.000411 U	0.000349 U	0.00304 U	0.000298 U	0.000292 U	0.00226 U	0.000255 U	0.00120 U	0.00120 U	0.000310 U	0.000248 U	0.000242 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	–	–	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	–	–	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
MW-138 (continued)	MW-138-95	09/13/17	PES	ESC	95	-37.5	S	0.000373 U	0.000316 U	0.00276 U	0.000271 U	0.000265 U	0.00205 U	0.000231 U	0.00109 U	0.00109 U	0.000281 U	0.000225 U	0.000219 U
	MW-138-105	09/13/17	PES	ESC	105	-47.5	S	0.000425 U	0.000361 U	0.00315 U	0.000308 U	0.000302 U	0.00234 U	0.000264 U	0.00124 U	0.00124 U	0.000321 U	0.000256 U	0.000250 U
	MW-138-115	09/14/17	PES	ESC	115	-57.5	S	0.000396 U	0.000336 U	0.00293 U	0.000287 U	0.000281 U	0.00218 U	0.000246 U	0.00116 U	0.00116 U	0.000299 U	0.000239 U	0.000233 U
MW-140 (-78.9 to -88.9)	MW-140-15	08/30/17	PES	ESC	15	35.6	V	0.000390 U	0.000331 U	0.00289 U	0.000283 U	0.000277 U	0.00214 U	0.000242 U	0.00114 U	0.00114 U	0.000294 U	0.000235 U	0.000229 U
	MW-140-25	08/30/17	PES	ESC	25	25.6	S	0.000371 U	**0.000406 J**	0.00274 U	0.000269 U	0.000264 U	0.00204 U	0.000230 U	0.00108 U	0.00108 U	0.000280 U	0.000223 U	0.000218 U
	MW-140-35	08/30/17	PES	ESC	35	15.6	S	0.00996 U	0.00845 U	0.0736 U	0.00722 U	0.00708 U	0.0548 U	0.00618 U	0.0291 U	0.0291 U	0.00752 U	0.00600 U	0.00585 U
	MW-140-45	08/30/17	PES	ESC	45	5.6	S	0.000365 U	**0.00107 J**	0.00270 U	0.000265 U	0.000259 U	0.00201 U	0.000226 U	0.00107 U	0.00107 U	0.000275 U	0.000220 U	0.000215 U
	MW-140-55	08/30/17	PES	ESC	55	-4.4	S	0.000375 U	**0.0134**	0.00278 U	0.000272 U	0.000267 U	0.00206 U	0.000233 U	0.00110 U	0.00110 U	0.000283 U	0.000226 U	0.000221 U
	MW-140-65	08/30/17	PES	ESC	65	-14.4	S	0.000366 U	**0.00870 J**	0.00271 U	0.000266 U	0.000260 U	0.00201 U	0.000227 U	0.00107 U	0.00107 U	0.000276 U	0.000221 U	0.000215 U
	MW-140-75	08/30/17	PES	ESC	75	-24.4	S	0.00922 U	0.00782 U	0.0682 U	0.00669 U	0.00656 U	0.0507 U	**0.00683 J**	0.0270 U	0.0270 U	0.00696 U	0.00555 U	0.00541 U
	MW-140-90	08/30/17	PES	ESC	90	-39.4	S	0.000402 U	**0.00188 J**	0.00298 U	0.000292 U	0.000286 U	0.00221 U	0.000249 U	0.00118 U	0.00118 U	0.000303 U	0.000242 U	0.000236 U
	MW-140-110	08/31/17	PES	ESC	110	-59.4	S	0.000396 U	**0.000364 J**	0.00293 U	0.000287 U	0.000281 U	0.00218 U	0.000245 U	0.00116 U	0.00116 U	0.000299 U	0.000239 U	0.000233 U
	MW-140-130	08/31/17	PES	ESC	130	-79.4	S	0.000387 U	**0.000357 J**	0.00286 U	0.000280 U	0.000275 U	0.00213 U	0.000240 U	0.00113 U	0.00113 U	0.000292 U	0.000233 U	0.000227 U
	MW-140-140	08/31/17	PES	ESC	140	-89.4	S	0.00966 U	**0.0157 J**	0.0714 U	0.00700 U	0.00687 U	0.0531 U	0.00599 U	0.0282 U	0.0282 U	0.00728 U	0.00582 U	0.00567 U
MW-142 (2.4 to -7.6)	MW-142-5	04/12/18	PES	ESC	5	37.1	V	0.000412 U	0.000349 U	0.00304 U	0.000298 U	0.000292 U	0.00226 U	0.000255 U	0.00120 U	0.00120 U	0.000310 U	0.000248 U	0.000242 U
MW-143 (-27.7 to -37.7)	MW-143-10	04/11/18	PES	ESC	10	32.0	V	0.000474 U	**0.00289 J**	0.00351 U	0.000344 U	0.000337 U	0.00261 U	0.000294 U	0.00139 U	0.00139 U	0.000358 U	0.000286 U	0.000279 U
	MW-143-20	04/11/18	PES	ESC	20	22.0	S	0.000397 U	0.000337 U	0.00294 U	0.000288 U	0.000282 U	0.00218 U	0.000246 U	0.00116 U	0.00116 U	0.000300 U	0.000239 U	0.000233 U
	MW-143-30	04/11/18	PES	ESC	30	12.0	S	0.000389 U	0.000330 U	0.00288 U	0.000282 U	0.000277 U	0.00214 U	0.000241 U	0.00114 U	0.00114 U	0.000294 U	0.000235 U	0.000229 U
	MW-143-40	04/11/18	PES	ESC	40	2.0	S	0.000408 U	**0.00257 J**	0.00302 U	0.000296 U	0.000290 U	0.00224 U	0.000253 U	0.00119 U	0.00119 U	0.000308 U	0.000246 U	0.000240 U
	MW-143-50	04/11/18	PES	ESC	50	-8.0	S	0.000392 U	**0.000594 J**	0.00290 U	0.000284 U	0.000278 U	0.00215 U	0.000243 U	0.00115 U	0.00115 U	0.000295 U	0.000236 U	0.000230 U
	MW-143-60	04/11/18	PES	ESC	60	-18.0	S	0.000380 U	0.000322 U	0.00281 U	0.000276 U	0.000270 U	0.00209 U	0.000236 U	0.00111 U	0.00111 U	0.000287 U	0.000229 U	0.000223 U
	MW-143-70	04/11/18	PES	ESC	70	-28.0	S	0.000376 U	0.000319 U	0.00278 U	0.000273 U	0.000267 U	0.00207 U	0.000233 U	0.00110 U	0.00110 U	0.000284 U	0.000227 U	0.000221 U
	MW-143-80	04/11/18	PES	ESC	80	-38.0	S	0.000389 U	0.000330 U	0.00287 U	0.000282 U	0.000276 U	0.00214 U	0.000241 U	0.00114 U	0.00114 U	0.000293 U	0.000234 U	0.000228 U
	MW-902-20	04/11/18	PES	ESC	80 (dup)	-38.0	S	0.000383 U	**0.000474 J**	0.00283 U	0.000278 U	0.000272 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000289 U	0.000231 U	0.000225 U
MW-145 (-26.1 to -36.1)	MW-145-10	04/17/18	PES	ESC	10	33.5	V	0.000430 U	0.000364 U	0.00318 U	0.000312 U	0.000305 U	0.00236 U	0.000266 U	0.00126 U	0.00126 U	0.000324 U	0.000259 U	0.000253 U
	MW-145-20	04/17/18	PES	ESC	20	23.5	S	0.000399 U	0.000339 U	0.00295 U	0.000290 U	0.000284 U	0.00219 U	0.000248 U	0.00117 U	0.00117 U	0.000301 U	0.000241 U	0.000235 U
	MW-145-30	04/17/18	PES	ESC	30	13.5	S	0.000406 U	0.000344 U	0.00300 U	0.000294 U	0.000288 U	0.00223 U	0.000251 U	0.00119 U	0.00119 U	0.000306 U	0.000244 U	0.000238 U
	MW-145-40	04/17/18	PES	ESC	40	3.5	S	0.000381 U	0.000323 U	0.00282 U	0.000276 U	0.000271 U	0.00209 U	0.000236 U	0.00111 U	0.00111 U	0.000287 U	0.000230 U	0.000224 U
	MW-145-50	04/17/18	PES	ESC	50	-6.5	S	0.000375 U	0.000318 U	0.00277 U	0.000272 U	0.000266 U	0.00206 U	0.000232 U	0.00110 U	0.00110 U	0.000283 U	0.000226 U	0.000220 U
	MW-145-60	04/17/18	PES	ESC	60	-16.5	S	0.000377 U	0.000320 U	0.00279 U	0.000273 U	0.000268 U	0.00207 U	0.000234 U	0.00110 U	0.00110 U	0.000284 U	0.000227 U	0.000222 U
	MW-145-70	04/17/18	PES	ESC	70	-26.5	S	0.000415 U	0.000352 U	0.00307 U	0.000301 U	0.000295 U	0.00228 U	0.000257 U	0.00121 U	0.00121 U	0.000313 U	0.000250 U	0.000244 U
	MW-145-80	04/17/18	PES	ESC	80	-36.5	S	0.000393 U	0.000333 U	0.00291 U	0.000285 U	0.000279 U	0.00216 U	0.000243 U	0.00115 U	0.00115 U	0.000296 U	0.000237 U	0.000231 U
	MW-903-40	04/17/18	PES	ESC	80 (dup)	-36.5	S	0.000384 U	0.000325 U	0.00284 U	0.000278 U	0.000273 U	0.00211 U	0.000238 U	0.00112 U	0.00112 U	0.000289 U	0.000231 U	0.000225 U
MW-147 (-17.6 to -27.6)	MW-147-10	04/02/18	PES	ESC	10	41.9	V	0.000371 U	0.000315 U	0.00275 U	0.000269 U	0.000264 U	0.00204 U	0.000230 U	0.00109 U	0.00109 U	0.000280 U	0.000224 U	0.000218 U
	MW-147-20	04/02/18	PES	ESC	20	31.9	S	0.000370 U	0.000313 U	0.00273 U	0.000268 U	0.000263 U	0.00203 U	0.000229 U	0.00108 U	0.00108 U	0.000279 U	0.000223 U	0.000217 U
	MW-147-30	04/02/18	PES	ESC	30	21.9	S	0.000382 U	0.000324 U	0.00282 U	0.000277 U	0.000271 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000288 U	0.000230 U	0.000224 U
	MW-147-40	04/02/18	PES	ESC	40	11.9	S	0.000377 U	0.000320 U	0.00279 U	0.000274 U	0.000268 U	0.00207 U	0.000234 U	0.00110 U	0.00110 U	0.000285 U	0.000227 U	0.000222 U
	MW-147-50	04/02/18	PES	ESC	50	1.9	S	0.000379 U	0.000321 U	0.00280 U	0.000275 U	0.000269 U	0.00208 U	0.000235 U	0.00111 U	0.00111 U	0.000286 U	0.000228 U	0.000223 U
	MW-147-60	04/02/18	PES	ESC	60	-8.2	S	0.000368 U	0.000312 U	0.00272 U	0.000267 U	0.000261 U	0.00202 U	0.000228 U	0.00108 U	0.00108 U	0.000277 U	0.000221 U	0.000216 U
	MW-901-10	04/02/18	PES	ESC	60 (dup)	-8.2	S	0.000368 U	**0.00203 J**	0.00272 U	0.000267 U	0.000262 U	0.00202 U	0.000228 U	0.00108 U	0.00108 U	0.000278 U	0.000222 U	0.000216 U
	MW-147-70	04/02/18	PES	ESC	70	-18.2	S	0.000383 U	0.000325 U	0.00283 U	0.000278 U	0.000272 U	0.00210 U	0.000237 U	0.00112 U	0.00112 U	0.000289 U	0.000231 U	0.000225 U
	MW-147-80	04/02/18	PES	ESC	80	-28.2	S	0.000396 U	0.000336 U	0.00293 U	0.000287 U	0.000281 U	0.00218 U	0.000245 U	0.00116 U	0.00116 U	0.000299 U	0.000238 U	0.000233 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	–	–	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	–	–	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
MW-148	MW-148-11	04/09/18	PES	ESC	11	32.9	V	0.000395 U	**0.00937 J**	0.00292 U	0.000286 U	0.000280 U	0.00217 U	0.000245 U	0.00115 U	0.00115 U	0.000298 U	0.000238 U	0.000232 U
(-25.7 to -35.7)	MW-148-20	04/09/18	PES	ESC	20	23.9	S	0.000371 U	0.000315 U	0.00274 U	0.000269 U	0.000264 U	0.00204 U	0.000230 U	0.00108 U	0.00108 U	0.000280 U	0.000223 U	0.000218 U
	MW-148-30	04/09/18	PES	ESC	30	13.9	S	0.000384 U	**0.000376 J**	0.00284 U	0.000278 U	0.000273 U	0.00211 U	0.000238 U	0.00112 U	0.00112 U	0.000290 U	0.000231 U	0.000226 U
	MW-148-40	04/09/18	PES	ESC	40	3.9	S	0.000372 U	0.000315 U	0.00275 U	0.000269 U	0.000264 U	0.00204 U	0.000230 U	0.00109 U	0.00109 U	0.000280 U	0.000224 U	0.000218 U
	MW-148-50	04/09/18	PES	ESC	50	-6.1	S	0.000377 U	0.000320 U	0.00279 U	0.000274 U	0.000268 U	0.00207 U	0.000234 U	0.00110 U	0.00110 U	0.000285 U	0.000227 U	0.000222 U
	MW-148-60	04/09/18	PES	ESC	60	-16.1	S	0.000432 U	0.000366 U	0.00319 U	0.000313 U	0.000307 U	0.00237 U	0.000268 U	0.00126 U	0.00126 U	0.000326 U	0.000260 U	0.000254 U
	MW-148-70	04/09/18	PES	ESC	70	-26.1	S	0.000431 U	**0.00557 J**	0.00319 U	0.000313 U	0.000306 U	0.00237 U	0.000267 U	0.00126 U	0.00126 U	0.000325 U	0.000260 U	0.000253 U
	MW-148-80	04/09/18	PES	ESC	80	-36.1	S	0.000402 U	**0.00183 J**	0.00297 U	0.000291 U	0.000286 U	0.00221 U	0.000249 U	0.00118 U	0.00118 U	0.000303 U	0.000242 U	0.000236 U
MW-153	MW-153-10	03/27/18	PES	ESC	10	44.4	V	0.000388 U	0.000329 U	0.00287 U	0.000281 U	0.000276 U	0.00213 U	0.000240 U	0.00113 U	0.00113 U	0.000293 U	0.000234 U	0.000228 U
(-65.3 to -75.3)	MW-153-20	03/27/18	PES	ESC	20	34.4	V	0.000374 U	0.000317 U	0.00277 U	0.000271 U	0.000266 U	0.00206 U	0.000232 U	0.00109 U	0.00109 U	0.000282 U	0.000225 U	0.000220 U
	MW-153-30	03/27/18	PES	ESC	30	24.4	S	0.000367 U	0.000311 U	0.00271 U	0.000266 U	0.000261 U	0.00202 U	0.000227 U	0.00107 U	0.00107 U	0.000277 U	0.000221 U	0.000216 U
	MW-153-40	03/27/18	PES	ESC	40	14.4	S	0.000387 U	0.000329 U	0.00287 U	0.000281 U	0.000275 U	0.00213 U	0.000240 U	0.00113 U	0.00113 U	0.000292 U	0.000233 U	0.000228 U
	MW-153-50	03/27/18	PES	ESC	50	4.4	S	0.000379 U	0.000322 U	0.00281 U	0.000275 U	0.000270 U	0.00209 U	0.000235 U	0.00111 U	0.00111 U	0.000286 U	0.000228 U	0.000223 U
	MW-153-61	03/27/18	PES	ESC	61	-6.7	S	0.000389 U	0.000330 U	0.00288 U	0.000282 U	0.000276 U	0.00214 U	0.000241 U	0.00114 U	0.00114 U	0.000293 U	0.000234 U	0.000228 U
	MW-153-70	03/27/18	PES	ESC	70	-15.7	S	0.000381 U	0.000323 U	0.00282 U	0.000276 U	0.000271 U	0.00209 U	0.000236 U	0.00111 U	0.00111 U	0.000287 U	0.000229 U	0.000224 U
	MW-153-80	03/28/18	PES	ESC	80	-25.7	S	0.000377 U	0.000320 U	0.00279 U	0.000274 U	0.000268 U	0.00207 U	0.000234 U	0.00110 U	0.00110 U	0.000285 U	0.000227 U	0.000222 U
	MW-153-90	03/28/18	PES	ESC	90	-35.7	S	0.000412 U	0.000349 U	0.00305 U	0.000299 U	0.000293 U	0.00226 U	0.000255 U	0.00120 U	0.00120 U	0.000311 U	0.000248 U	0.000242 U
	MW-153-110	03/28/18	PES	ESC	110	-55.7	S	0.000402 U	0.000341 U	0.00298 U	0.000292 U	0.000286 U	0.00221 U	0.000249 U	0.00118 U	0.00118 U	0.000304 U	0.000242 U	0.000237 U
	MW-153-130	03/29/18	PES	ESC	130	-75.7	S	0.000393 U	0.000333 U	0.00291 U	0.000285 U	0.000279 U	0.00216 U	0.000244 U	0.00115 U	0.00115 U	0.000296 U	0.000237 U	0.000231 U
MW-158	MW-158-20	04/05/18	PES	ESC	20	21.1	S	0.000387 U	0.000328 U	0.00287 U	0.000281 U	0.000275 U	0.00213 U	0.000240 U	0.00113 U	0.00113 U	0.000292 U	0.000233 U	0.000228 U
	MW-158-30	04/05/18	PES	ESC	30	11.1	S	0.0403 U	0.0342 U	0.298 U	0.0293 U	0.0287 U	0.222 U	0.0250 U	0.118 U	0.118 U	0.0304 U	0.0243 U	0.0237 U
MW-158A	MW-158A-40	04/05/18	PES	ESC	40	1.1	S	0.000422 U	0.000357 U	0.00312 U	0.000306 U	0.000300 U	0.00232 U	0.000261 U	0.00123 U	0.00123 U	0.000318 U	0.000254 U	0.000248 U
(-47.2 to -58.5)	MW-158A-50	04/05/18	PES	ESC	50	-8.9	S	0.000395 U	0.000335 U	0.00293 U	0.000287 U	0.000281 U	0.00217 U	0.000245 U	0.00116 U	0.00116 U	0.000298 U	0.000238 U	0.000232 U
	MW-158A-60	04/05/18	PES	ESC	60	-18.9	S	0.000394 U	0.000334 U	0.00291 U	0.000285 U	0.000280 U	0.00216 U	0.000244 U	0.00115 U	0.00115 U	0.000297 U	0.000237 U	0.000231 U
	MW-158A-70	04/05/18	PES	ESC	70	-28.9	S	0.000384 U	0.000325 U	0.00284 U	0.000278 U	0.000273 U	0.00211 U	0.000238 U	0.00112 U	0.00112 U	0.000290 U	0.000231 U	0.000226 U
	MW-158A-80	04/06/18	PES	ESC	80	-38.9	S	0.000379 U	0.000322 U	0.00281 U	0.000275 U	0.000269 U	0.00208 U	0.000235 U	0.00111 U	0.00111 U	0.000286 U	0.000228 U	0.000223 U
	MW-158A-90	04/06/18	PES	ESC	90	-48.9	S	0.000392 U	0.000333 U	0.00290 U	0.000285 U	0.000279 U	0.00216 U	0.000243 U	0.00115 U	0.00115 U	0.000296 U	0.000236 U	0.000231 U
	MW-158A-100	04/06/18	PES	ESC	100	-58.9	S	0.000402 U	0.000341 U	0.00297 U	0.000291 U	0.000286 U	0.00221 U	0.000249 U	0.00117 U	0.00117 U	0.000303 U	0.000242 U	0.000236 U
MW-159	MW-159-20	04/16/18	PES	ESC	20	22.8	S	0.000413 U	0.000351 U	0.00306 U	0.000300 U	0.000294 U	0.00227 U	0.000256 U	0.00121 U	0.00121 U	0.000312 U	0.000249 U	0.000243 U
(22.9 to 12.9)	MW-159-30	04/16/18	PES	ESC	30	12.8	S	0.000417 U	0.000353 U	0.00308 U	0.000302 U	0.000296 U	0.00229 U	0.000258 U	0.00122 U	0.00122 U	0.000314 U	0.000251 U	0.000245 U
MW-160	MW-160-11	05/08/18	PES	ESC	11	31.5	S	0.0206 U	0.00171 U	0.00982 U	0.000568 U	0.00140 U	0.0162 U	0.000479 U	0.0108 U	0.00507 U	0.00623 U	0.00191 U	0.00411 U
(-76.5 to -86.5)	MW-160-21	05/08/18	PES	ESC	21	21.5	S	0.0149 U	0.00124 U	0.00709 U	0.000410 U	0.00101 U	0.0117 U	0.000346 U	0.00778 U	0.00366 U	0.00450 U	0.00138 U	0.00297 U
	MW-160-31	05/08/18	PES	ESC	31	11.5	S	0.0154 U	0.00129 U	0.00734 U	0.000425 U	0.00105 U	0.0121 U	0.000358 U	0.00805 U	0.00378 U	0.00466 U	0.00143 U	0.00307 U
	MW-160-40	05/08/18	PES	ESC	40	2.5	S	0.0144 U	0.00120 U	0.00687 U	0.000397 U	0.000980 U	0.0114 U	0.000335 U	0.00754 U	0.00354 U	0.00436 U	0.00134 U	0.00287 U
	MW-160-50	05/08/18	PES	ESC	50	-7.5	S	0.0145 U	0.00121 U	0.00691 U	0.000400 U	0.000986 U	0.0114 U	0.000337 U	0.00759 U	0.00356 U	0.00439 U	0.00135 U	0.00289 U
	MW-160-55	05/08/18	PES	ESC	55	-12.5	S	0.0151 U	0.0101 U	0.00718 U	0.000415 U	0.00102 U	0.0119 U	0.000350 U	0.00788 U	0.00370 U	0.00455 U	0.00140 U	0.00300 U
	MW-160-60	05/08/18	PES	ESC	60	-17.5	S	0.0138 U	0.00115 U	0.00659 U	0.000381 U	0.000940 U	0.0109 U	0.000321 U	0.00723 U	0.00340 U	0.00418 U	0.00129 U	0.00276 U
	MW-160-70	05/08/18	PES	ESC	70	-27.5	S	0.0148 U	0.00124 U	0.00707 U	0.000409 U	0.00101 U	0.0117 U	0.000345 U	0.00776 U	0.00364 U	0.00449 U	0.00138 U	0.00296 U
	MW-160-90	05/08/18	PES	ESC	90	-47.5	S	0.0149 U	0.00125 U	0.00712 U	0.000412 U	0.00102 U	0.0118 U	0.000347 U	0.00781 U	0.00367 U	0.00452 U	0.00139 U	0.00298 U
	MW-160-100	05/08/18	PES	ESC	100	-57.5	S	0.0153 U	0.00128 U	0.00728 U	0.000421 U	0.00104 U	0.0120 U	0.000355 U	0.00799 U	0.00375 U	0.00462 U	0.00142 U	0.00304 U
	MW-160-110	05/08/18	PES	ESC	110	-67.5	S	0.0144 U	**0.00297 J**	0.00686 U	0.000397 U	0.000979 U	0.0113 U	0.000335 U	0.00753 U	0.00354 U	0.00435 U	0.00134 U	0.00287 U
	MW-160-125	05/10/18	PES	ESC	125	-82.5	S	0.0145 U	**0.00395 J**	0.00693 U	0.000401 U	0.000988 U	0.0114 U	0.000338 U	0.00760 U	0.00357 U	0.00440 U	0.00135 U	0.00290 U
	MW-160-127.5	05/10/18	PES	ESC	128	-85.0	S	0.0147 U	0.00122 U	0.00699 U	0.000404 U	0.000997 U	0.0115 U	**0.000468 J**	0.00767 U	0.00360 U	0.00443 U	0.00136 U	0.00292 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	–	–	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	–	–	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
MW-161	MW-161-11	05/14/18	PES	ESC	11	32.8	S	0.0156 U	–	–	0.000430 U	0.00106 U	0.0123 U	0.000363 U	0.00816 U	0.00384 U	0.00472 U	0.00145 U	0.00311 U
(-78.9 to -88.9)	MW-161-21	05/14/18	PES	ESC	21	22.8	S	0.0132 U	–	–	0.000364 U	0.000897 U	0.0104 U	0.000307 U	0.00690 U	0.00324 U	0.00399 U	0.00123 U	0.00263 U
	MW-161-31	05/14/18	PES	ESC	31	12.8	S	0.0145 U	–	–	0.000401 U	0.000988 U	0.0114 U	0.000338 U	0.00760 U	0.00357 U	0.00440 U	0.00135 U	0.00290 U
	MW-161-40	05/14/18	PES	ESC	40	3.8	S	0.0140 U	–	–	0.000386 U	0.000952 U	0.0110 U	0.000326 U	0.00733 U	0.00344 U	0.00424 U	0.00130 U	0.00279 U
	MW-161-50	05/14/18	PES	ESC	50	-6.2	S	0.0142 U	–	–	0.000391 U	0.000963 U	0.0112 U	0.000329 U	0.00741 U	0.00348 U	0.00429 U	0.00132 U	0.00282 U
	MW-161-60	05/14/18	PES	ESC	60	-16.2	S	0.0145 U	–	–	0.000400 U	0.000986 U	0.0114 U	0.000337 U	0.00758 U	0.00356 U	0.00439 U	0.00135 U	0.00289 U
	MW-161-70	05/14/18	PES	ESC	70	-26.2	S	0.0142 U	–	–	0.000391 U	0.000964 U	0.0112 U	0.000329 U	0.00742 U	0.00348 U	0.00429 U	0.00132 U	0.00283 U
	MW-161-80	05/14/18	PES	ESC	80	-36.2	S	0.0157 U	–	–	0.000431 U	0.00106 U	0.0123 U	0.000364 U	0.00818 U	0.00385 U	0.00473 U	0.00145 U	0.00312 U
	MW-161-90	05/14/18	PES	ESC	90	-46.2	S	0.0145 U	–	–	0.000398 U	0.000982 U	0.0114 U	0.000336 U	0.00756 U	0.00355 U	0.00437 U	0.00134 U	0.00288 U
	B-927-30	05/14/18	PES	ESC	90 (dup)	-46.2	S	0.0158 U	–	–	0.000435 U	0.00107 U	0.0124 U	0.000366 U	0.00825 U	0.00387 U	0.00477 U	0.00147 U	0.00314 U
	MW-161-100	05/14/18	PES	ESC	100	-56.2	S	0.0148 U	–	–	0.000408 U	0.00100 U	0.0116 U	0.000343 U	0.00773 U	0.00363 U	0.00447 U	0.00137 U	0.00295 U
	MW-161-110	05/14/18	PES	ESC	110	-66.2	S	0.0155 U	–	–	0.000427 U	0.00105 U	0.0122 U	0.000360 U	0.00810 U	0.00381 U	0.00468 U	0.00144 U	0.00309 U
	MW-161-120	05/14/18	PES	ESC	120	-76.2	S	0.0155 U	–	–	0.000427 U	0.00105 U	0.0122 U	0.000360 U	0.00810 U	0.00381 U	0.00469 U	0.00144 U	0.00309 U
	MW-161-130	05/14/18	PES	ESC	130	-86.2	S	0.0140 U	–	–	0.000385 U	0.000949 U	0.0110 U	0.000324 U	0.00730 U	0.00343 U	0.00422 U	0.00130 U	0.00278 U
	MW-161-140	05/15/18	PES	ESC	140	-96.2	S	0.0156 U	0.00130 U	0.00742 U	0.000429 U	0.00106 U	0.0123 U	0.000362 U	0.00814 U	0.00382 U	0.00471 U	0.00145 U	0.00310 U
MW-190	MW-190-5	09/19/19	PES	PACE	5	43.7	V	0.0146 U	**0.0166**	0.00698 U	0.000404 U	0.000995 U	0.0115 U	0.000340 U	0.00766 U	0.00360 U	0.00443 U	0.00136 U	0.00292 U
(-30.2 to -40.2)	MW-190-10	09/19/19	PES	PACE	10	38.7	V	0.0262 U	**0.0365**	0.0125 U	0.000724 U	0.00178 U	0.0207 U	0.000611 U	**0.0140 J**	0.00646 U	0.00794 U	0.00243 U	0.00523 U
	MW-190-15	09/19/19	PES	PACE	15	33.7	S	0.0168 U	**0.0229**	0.00801 U	0.000463 U	0.00114 U	0.0132 U	0.000391 U	0.00879 U	0.00413 U	0.00508 U	0.00156 U	0.00335 U
	MW-190-20	09/19/19	PES	PACE	20	28.7	S	0.0158 U	**0.0303**	0.00753 U	0.000436 U	**0.00113 J**	0.0124 U	0.000367 U	0.00826 U	0.00388 U	0.00478 U	0.00147 U	0.00315 U
	MW-190-25	09/19/19	PES	PACE	25	23.7	S	0.0149 U	**0.0252**	0.00710 U	0.000411 U	0.00101 U	0.0117 U	**0.000380 J**	**0.00805 J**	0.00366 U	0.00451 U	0.00139 U	0.00297 U
	MW-190-30	09/19/19	PES	PACE	30	18.7	S	0.0133 U	**0.0224**	0.00634 U	0.000367 U	0.000904 U	0.0105 U	0.000309 U	**0.00719 J**	0.00327 U	0.00402 U	0.00124 U	0.00265 U
	MW-190-35	09/19/19	PES	PACE	35	13.7	S	0.0135 U	**0.0211**	0.00643 U	0.000372 U	0.000917 U	0.0106 U	0.000313 U	**0.00739 J**	0.00331 U	0.00408 U	0.00125 U	0.00269 U
	MW-190-40	09/19/19	PES	PACE	40	8.7	S	0.0143 U	**0.0192**	0.00679 U	0.000393 U	0.000969 U	0.0112 U	0.000331 U	0.00745 U	0.00350 U	0.00431 U	0.00132 U	0.00284 U
	MW-190-45	09/19/19	PES	PACE	45	3.7	S	0.0145 U	**0.0119**	0.00692 U	0.000400 U	0.000987 U	0.0114 U	0.000337 U	0.00759 U	0.00357 U	0.00439 U	0.00135 U	0.00289 U
	MW-190-50	09/19/19	PES	PACE	50	-1.4	S	0.0133 U	**0.0233**	0.00634 U	0.000367 U	0.000904 U	0.0105 U	0.000309 U	**0.00833 J**	0.00327 U	0.00402 U	0.00124 U	0.00265 U
	MW-190-55	09/19/19	PES	PACE	55	-6.4	S	0.0138 U	**0.0429**	0.00656 U	0.000380 U	0.000936 U	0.0108 U	0.000320 U	**0.00853 J**	0.00338 U	0.00416 U	0.00128 U	0.00274 U
	MW-190-60	09/19/19	PES	PACE	60	-11.4	S	0.0138 U	**0.0107**	0.00659 U	0.000381 U	0.000940 U	0.0109 U	0.000321 U	**0.00805 J**	0.00340 U	0.00418 U	0.00129 U	0.00276 U
	MW-2008-60	09/19/19	PES	PACE	60 (dup)	-11.4	S	0.0137 U	**0.0131**	0.00654 U	0.000378 U	0.000933 U	0.0108 U	0.000319 U	**0.0108 J**	0.00337 U	0.00415 U	0.00128 U	0.00273 U
	MW-190-65	09/19/19	PES	PACE	65	-16.4	S	0.0140 U	**0.0267**	0.00668 U	0.000387 U	0.000953 U	0.0110 U	0.000326 U	**0.0104 J**	0.00345 U	0.00424 U	0.00130 U	0.00279 U
	MW-190-70	09/19/19	PES	PACE	70	-21.4	S	0.0141 U	0.00117 U	0.00670 U	0.000388 U	0.000956 U	0.0111 U	0.000327 U	**0.0122 J**	0.00346 U	0.00425 U	0.00131 U	0.00280 U
	MW-190-75	09/19/19	PES	PACE	75	-26.4	S	0.0139 U	**0.00849**	0.00661 U	0.000383 U	0.000944 U	0.0109 U	0.000323 U	**0.0117 J**	0.00341 U	0.00420 U	0.00129 U	0.00277 U
	MW-190-80	09/19/19	PES	PACE	80	-31.4	S	0.0139 U	**0.0119**	0.00661 U	0.000382 U	0.000942 U	0.0109 U	0.000322 U	**0.0139 J**	0.00341 U	0.00419 U	0.00129 U	0.00276 U
	MW-190-85	09/19/19	PES	PACE	85	-36.4	S	0.0146 U	0.00122 U	0.00696 U	0.000402 U	0.000992 U	0.0115 U	0.000339 U	**0.0138 J**	0.00359 U	0.00441 U	0.00136 U	0.00291 U
	MW-190-87	09/19/19	PES	PACE	87	-38.4	S	0.0152 U	**0.0123**	0.00723 U	0.000418 U	0.00103 U	0.0120 U	0.000353 U	**0.0131 J**	0.00373 U	0.00459 U	0.00141 U	0.00302 U
MW-301	MW-301-6	09/20/19	PES	PACE	6	47.8	V	0.0149 U	0.00124 U	0.00709 U	0.000410 U	0.00101 U	0.0117 U	0.000346 U	0.00778 U	0.00366 U	0.00450 U	0.00138 U	0.00296 U
(35.6 to 25.6)	MW-301-10	09/20/19	PES	PACE	10	43.8	V	0.0140 U	0.00117 U	0.00665 U	0.000385 U	0.000949 U	0.0110 U	0.000324 U	**0.00866 J**	0.00343 U	0.00422 U	0.00130 U	0.00278 U
	MW-301-15	09/20/19	PES	PACE	15	38.8	V	0.0144 U	0.00120 U	0.00687 U	0.000397 U	0.000980 U	0.0114 U	0.000335 U	**0.00859 J**	0.00354 U	0.00436 U	0.00134 U	0.00287 U
	MW-301-20	09/20/19	PES	PACE	20	33.8	S	0.0429 U	0.00358 U	0.0205 U	0.00118 U	0.00291 U	0.0338 U	0.000997 U	**0.0297 J**	0.0105 U	0.0129 U	0.00399 U	0.00854 U
	MW-301-25	09/20/19	PES	PACE	25	28.8	S	0.0144 U	0.00120 U	0.00688 U	0.000398 U	0.000981 U	0.0114 U	**0.000532 J**	**0.00891 J**	0.00355 U	0.00436 U	0.00134 U	0.00288 U
	MW-301-30	09/20/19	PES	PACE	30	23.8	S	0.0157 U	0.00131 U	0.00749 U	0.000433 U	0.00107 U	0.0124 U	0.000365 U	**0.0124 J**	0.00386 U	0.00475 U	0.00146 U	0.00313 U
MW-302	MW-302-5	10/01/19	PES	PACE	5	52.3	V	0.0149 U	**0.00507 J**	0.00708 U	0.000410 U	0.00101 U	0.0117 U	0.000345 U	0.00778 U	0.00365 U	0.00450 U	0.00138 U	0.00296 U
(3.0 to -7.0)	MW-302-10	10/01/19	PES	PACE	10	47.3	V	0.0158 U	0.00132 UJ	0.00753 U	0.000435 U	0.00107 U	0.0124 U	0.000367 U	0.00826 U	0.00388 U	0.00478 U	0.00147 U	0.00315 U
	MW-302-15	10/01/19	PES	PACE	15	42.3	V	0.0173 U	0.00145 UJ	0.00825 U	0.000477 U	0.00118 U	0.0136 U	0.000402 U	0.00905 U	0.00426 U	0.00523 U	0.00161 U	0.00344 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	–	–	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	–	–	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
MW-302 (continued)	MW-302-20	10/01/19	PES	PACE	20	37.3	S	0.0152 U	0.00126 UJ	0.00722 U	0.000418 U	0.00103 U	0.0119 U	0.000352 U	0.00792 U	0.00372 U	0.00458 U	0.00141 U	0.00302 U
	MW-302-25	10/01/19	PES	PACE	25	32.3	S	0.0142 U	0.00119 UJ	0.00678 U	0.000392 U	0.000967 U	0.0112 U	0.000331 U	0.00744 U	0.00350 U	0.00430 U	0.00132 U	0.00284 U
	MW-302-30	10/01/19	PES	PACE	30	27.3	S	0.0139 U	0.00116 UJ	0.00662 U	0.000383 U	0.000944 U	0.0109 U	0.000323 U	0.00726 U	0.00341 U	0.00420 U	0.00129 U	0.00277 U
	MW-302-35	10/01/19	PES	PACE	35	22.3	S	0.0136 U	0.00114 UJ	0.00650 U	0.000376 U	0.000928 U	0.0107 U	0.000317 U	0.00714 U	0.00335 U	0.00413 U	0.00127 U	0.00272 U
	MW-302-40	10/01/19	PES	PACE	40	17.3	S	0.0135 U	0.00113 UJ	0.00644 U	0.000372 U	0.000918 U	0.0106 U	0.000314 U	0.00706 U	0.00332 U	0.00408 U	0.00126 U	0.00269 U
	MW-302-45	10/01/19	PES	PACE	45	12.3	S	0.0151 U	0.00126 UJ	0.00721 U	0.000417 U	0.00103 U	0.0119 U	0.000351 U	0.00791 U	0.00372 U	0.00458 U	0.00141 U	0.00301 U
	MW-302-50	10/01/19	PES	PACE	50	7.3	S	0.0152 U	**0.0105 J**	0.00722 U	0.000418 U	0.00103 U	0.0119 U	0.000352 U	0.00793 U	0.00373 U	0.00459 U	0.00141 U	0.00302 U
	MW-302-55	10/01/19	PES	PACE	55	2.3	S	0.0144 U	0.00120 UJ	0.00687 U	0.000398 U	0.000981 U	0.0114 U	0.000335 U	0.00755 U	0.00355 U	0.00436 U	0.00134 U	0.00287 U
	MW-302-60	10/01/19	PES	PACE	60	-2.7	S	0.0180 U	0.00150 UJ	0.00860 U	0.000497 U	0.00123 U	0.0142 U	0.000419 U	0.00944 U	0.00443 U	0.00546 U	0.00168 U	0.00360 U
	MW-302-65	10/01/19	PES	PACE	65	-7.7	S	0.0149 U	0.00124 UJ	0.00709 U	0.000410 U	0.00101 U	0.0117 U	0.000345 U	0.00778 U	0.00365 U	0.00450 U	0.00138 U	0.00296 U
	MW-2014-65	10/01/19	PES	PACE	65 (dup)	-7.7	S	0.0154 U	0.00129 U	0.00733 U	0.000424 U	0.00105 U	0.0121 U	0.000358 U	0.00805 U	0.00378 U	0.00466 U	0.00143 U	0.00307 U
MW-304 (-47.6 to -57.6)	MW-304-5	10/01/19	PES	PACE	5	52.6	V	0.0143 U	0.00119 U	0.00681 U	0.000394 U	0.000972 U	0.0113 U	0.000332 U	0.00748 U	**0.00560 J**	0.00433 U	0.00133 U	0.00285 U
	MW-304-10	10/01/19	PES	PACE	10	47.6	V	0.0145 U	0.00121 U	0.00689 U	0.000399 U	0.000983 U	0.0114 U	0.000336 U	0.00757 U	0.00356 U	0.00438 U	0.00134 U	0.00288 U
	MW-304-15	10/01/19	PES	PACE	15	42.6	V	0.0151 U	0.00126 U	0.00719 U	0.000416 U	0.00103 U	0.0119 U	0.000351 U	0.00790 U	0.00371 U	0.00457 U	0.00140 U	0.00301 U
	MW-304-20	10/01/19	PES	PACE	20	37.6	S	0.0150 U	0.00125 U	0.00713 U	0.000412 U	0.00102 U	0.0118 U	0.000347 U	0.00782 U	0.00367 U	0.00452 U	0.00139 U	0.00298 U
	MW-304-25	10/01/19	PES	PACE	25	32.6	S	0.0139 U	0.00116 U	0.00662 U	0.000383 U	0.000944 U	0.0109 U	0.000323 U	0.00726 U	0.00341 U	0.00420 U	0.00129 U	0.00277 U
	MW-304-30	10/01/19	PES	PACE	30	27.6	S	0.0149 U	0.00125 U	0.00712 U	0.000412 U	0.00102 U	0.0118 U	0.000347 U	0.00781 U	0.00367 U	0.00452 U	0.00139 U	0.00298 U
	MW-304-40	10/01/19	PES	PACE	40	17.6	S	0.0138 U	0.00115 U	0.00657 U	0.000380 U	0.000936 U	0.0109 U	0.000320 U	0.00721 U	0.00339 U	0.00417 U	0.00128 U	0.00275 U
	MW-304-45	10/01/19	PES	PACE	45	12.6	S	0.0129 U	0.00108 U	0.00615 U	0.000356 U	0.000877 U	0.0102 U	0.000300 U	0.00675 U	0.00317 U	0.00390 U	0.00120 U	0.00257 U
	MW-304-50	10/01/19	PES	PACE	50	7.6	S	0.0137 U	0.00114 U	0.00651 U	0.000377 U	0.000929 U	0.0108 U	0.000318 U	0.00715 U	0.00336 U	0.00413 U	0.00127 U	0.00272 U
	MW-304-55	10/01/19	PES	PACE	55	2.6	S	0.0128 U	0.00107 U	0.00610 U	0.000353 U	0.000870 U	0.0101 U	0.000297 U	0.00669 U	0.00314 U	0.00387 U	0.00119 U	0.00255 U
	MW-304-60	10/01/19	PES	PACE	60	-2.4	S	0.0134 U	**0.00452 J**	0.00638 U	0.000369 U	0.000910 U	0.0105 U	0.000311 U	0.00700 U	0.00329 U	0.00405 U	0.00124 U	0.00267 U
	MW-304-65	10/01/19	PES	PACE	65	-7.4	S	0.0147 U	0.00123 U	0.00701 U	0.000405 U	0.000999 U	0.0116 U	0.000342 U	0.00769 U	0.00361 U	0.00445 U	0.00137 U	0.00293 U
	MW-304-70	10/01/19	PES	PACE	70	-12.4	S	0.0154 U	0.00129 U	0.00735 U	0.000425 U	0.00105 U	0.0121 U	0.000358 U	0.00807 U	0.00379 U	0.00467 U	0.00143 U	0.00307 U
	MW-304-75	10/01/19	PES	PACE	75	-17.4	S	0.0145 U	0.00121 U	0.00693 U	0.000401 U	0.000988 U	0.0114 U	0.000338 U	**0.00789 J**	0.00357 U	0.00440 U	0.00135 U	0.00290 U
	MW-304-80	10/01/19	PES	PACE	80	-22.4	S	0.0139 U	0.00116 U	0.00662 U	0.000383 U	0.000945 U	0.0109 U	0.000323 U	0.00727 U	0.00341 U	0.00420 U	0.00129 U	0.00277 U
	MW-304-85	10/01/19	PES	PACE	85	-27.4	S	0.0139 U	0.00116 U	0.00663 U	0.000383 U	0.000945 U	0.0110 U	0.000323 U	0.00727 U	0.00342 U	0.00421 U	0.00129 U	0.00277 U
	MW-304-90	10/01/19	PES	PACE	90	-32.4	S	0.0152 U	0.00127 U	0.00725 U	0.000420 U	0.00103 U	0.0120 U	0.000354 U	0.00796 U	0.00374 U	0.00460 U	0.00141 U	0.00303 U
	MW-304-95	10/01/19	PES	PACE	95	-37.4	S	0.0150 U	0.00126 U	0.00717 U	0.000415 U	0.00102 U	0.0118 U	0.000350 U	0.00787 U	0.00370 U	0.00455 U	0.00140 U	0.00300 U
	MW-2009-95	10/01/19	PES	PACE	95 (dup)	-37.4	S	0.0153 U	0.00127 U	0.00727 U	0.000420 U	0.00104 U	0.0120 U	0.000354 U	0.00798 U	0.00375 U	0.00461 U	0.00142 U	0.00304 U
	MW-304-100	10/02/19	PES	PACE	100	-42.4	S	0.0150 U	0.00125 U	0.00713 U	0.000413 U	0.00102 U	0.0118 U	0.000348 U	0.00783 U	0.00368 U	0.00453 U	0.00139 U	0.00298 U
	MW-304-105	10/02/19	PES	PACE	105	-47.4	S	0.0149 U	0.00124 U	0.00708 U	0.000410 U	0.00101 U	0.0117 U	0.000345 U	0.00777 U	0.00365 U	0.00449 U	0.00138 U	0.00296 U
	MW-304-110	10/02/19	PES	PACE	110	-52.4	S	0.0161 U	0.00134 U	0.00765 U	0.000443 U	0.00109 U	0.0126 U	0.000373 U	0.00840 U	0.00394 U	0.00486 U	0.00149 U	0.00320 U
	MW-304-115	10/02/19	PES	PACE	115	-57.4	S	0.0148 U	0.00123 U	0.00705 U	0.000408 U	0.00101 U	0.0117 U	0.000344 U	0.00774 U	0.00364 U	0.00447 U	0.00137 U	0.00295 U
MW-307 (-12.4 to -22.4)	MW-307-6	10/03/19	PES	PACE	6	54.5	V	0.0142 U	0.00119 U	0.00676 U	0.000391 U	0.000965 U	0.0112 U	0.000330 U	0.00742 U	0.00349 U	0.00429 U	0.00132 U	0.00283 U
	MW-307-10	10/03/19	PES	PACE	10	50.5	V	0.0147 U	0.00122 U	0.00696 U	0.000403 U	0.000994 U	0.0115 U	**0.000604 J**	0.00765 U	0.00359 U	0.00442 U	0.00136 U	0.00291 U
	MW-307-15	10/03/19	PES	PACE	15	45.5	V	0.0137 U	**0.0147**	0.00652 U	0.000377 U	0.000930 U	0.0108 U	0.000318 U	0.00715 U	0.00336 U	0.00414 U	0.00127 U	0.00273 U
	MW-307-20	10/03/19	PES	PACE	20	40.5	V	0.0136 U	0.00113 U	0.00647 U	0.000374 U	0.000923 U	0.0107 U	**0.000366 J**	0.00710 U	0.00334 U	0.00411 U	0.00126 U	0.00271 U
	MW-307-25	10/03/19	PES	PACE	25	35.5	S	0.0139 U	**0.0218**	0.00664 U	0.000384 U	0.000947 U	0.0110 U	0.000324 U	0.00728 U	0.00342 U	0.00421 U	0.00129 U	0.00278 U
	MW-307-30	10/03/19	PES	PACE	30	30.5	S	0.0187 U	**0.0151**	0.00892 U	0.000516 U	0.00127 U	0.0147 U	**0.000483 J**	0.00978 U	0.00460 U	0.00566 U	0.00174 U	0.00372 U
	MW-307-35	10/03/19	PES	PACE	35	25.5	S	0.0136 U	**0.0162**	0.00647 U	0.000374 U	0.000923 U	0.0107 U	0.000316 U	0.00710 U	0.00334 U	0.00411 U	0.00126 U	0.00271 U
	MW-307-40	10/03/19	PES	PACE	40	20.5	S	0.0145 U	0.00121 U	0.00691 U	0.000400 U	0.000985 U	0.0114 U	0.000337 U	0.00758 U	0.00356 U	0.00438 U	0.00135 U	0.00289 U
	MW-307-45	10/03/19	PES	PACE	45	15.5	S	0.0140 U	**0.00990**	0.00667 U	0.000386 U	0.000952 U	0.0110 U	0.000325 U	0.00732 U	0.00344 U	0.00424 U	0.00130 U	0.00279 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	–	–	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	–	–	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
MW-307 (continued)	MW-307-50	10/03/19	PES	PACE	50	10.5	S	0.0141 U	0.00118 U	0.00673 U	0.000389 U	0.000960 U	0.0111 U	0.000328 U	0.00738 U	0.00347 U	0.00427 U	0.00131 U	0.00281 U
	MW-307-55	10/03/19	PES	PACE	55	5.5	S	0.0138 U	0.00115 U	0.00657 U	0.000380 U	0.000937 U	0.0109 U	0.000320 U	0.00721 U	0.00339 U	0.00417 U	0.00128 U	0.00275 U
	MW-307-60	10/03/19	PES	PACE	60	0.5	S	0.0143 U	0.00120 U	0.00683 U	0.000395 U	0.000975 U	0.0113 U	0.000333 U	0.00750 U	0.00352 U	0.00434 U	0.00133 U	0.00286 U
	MW-307-65	10/03/19	PES	PACE	65	-4.5	S	0.0293 U	**0.0272**	0.0139 U	0.000806 U	0.00199 U	0.0230 U	0.000679 U	0.0153 U	0.00719 U	0.00884 U	0.00272 U	0.00582 U
	MW-307-70	10/03/19	PES	PACE	70	-9.5	S	0.145 U	0.0121 U	0.0693 U	0.00401 U	0.00989 U	0.115 U	0.00338 U	0.0761 U	0.0357 U	0.0440 U	0.0135 U	0.0290 U
	MW-307-75	10/03/19	PES	PACE	75	-14.5	S	0.0140 U	**0.0176**	0.00667 U	0.000386 U	0.000952 U	0.0110 U	0.000325 U	0.00732 U	0.00344 U	0.00423 U	0.00130 U	0.00279 U
	MW-307-80	10/03/19	PES	PACE	80	-19.5	S	0.0149 U	**0.0315**	0.00707 U	0.000410 U	0.00101 U	0.0117 U	0.000345 U	0.00776 U	0.00364 U	0.00449 U	0.00138 U	0.00296 U
	MW-307-85	10/03/19	PES	PACE	85	-24.5	S	0.0145 U	0.00121 U	0.00693 U	0.000401 U	0.000989 U	0.0115 U	0.000338 U	0.00761 U	0.00357 U	0.00440 U	0.00135 U	0.00290 U
	MW-2016-85	10/03/19	PES	PACE	85 (dup)	-24.5	S	0.0137 U	0.00115 U	0.00654 U	0.000378 U	0.000932 U	0.0108 U	0.000319 U	0.00717 U	0.00337 U	0.00415 U	0.00127 U	0.00273 U
MW-309 (-32.0 to -42.0)	MW-309-5	09/19/19	PES	PACE	5	25.4	V	0.0152 U	**0.0435**	0.00722 U	0.000418 U	**0.00147 J**	0.0119 U	0.000352 U	0.00792 U	**0.0426**	0.00458 U	**0.00223 J**	0.00302 U
	MW-309-10	09/19/19	PES	PACE	10	20.4	S	0.799 U	**0.568**	0.381 U	0.0220 U	**0.793**	0.629 U	0.0186 U	0.418 U	**0.305 J**	**0.856**	**2.05**	**0.374 J**
	MW-309-13.5	09/19/19	PES	PACE	13.5	16.9	S	0.0155 U	**0.0617**	0.00739 U	0.000427 U	**0.0235**	0.0122 U	0.000360 U	0.00811 U	**0.185**	**0.0215**	**0.0842**	**0.00672 J**
	MW-309-15	09/19/19	PES	PACE	15	15.4	S	0.120 U	**0.343**	0.0570 U	0.00330 U	**0.212**	0.0942 U	0.00278 U	0.0625 U	**0.963**	0.0361 U	**0.807**	**0.0279 J**
	MW-309-20	09/19/19	PES	PACE	20	10.4	S	0.0149 U	**0.0872**	0.00712 U	0.000412 U	**0.164**	0.0118 U	0.000347 U	0.00781 U	**0.0961**	0.00452 U	**0.221**	**0.00632 J**
	MW-309-25	09/19/19	PES	PACE	25	5.4	S	0.0150 U	**0.0465**	0.00715 U	0.000414 U	**0.0811**	0.0118 U	0.000349 U	0.00784 U	**0.117**	**0.0283**	**0.146**	**0.0105 J**
	MW-309-30	09/19/19	PES	PACE	30	0.4	S	0.0152 U	**0.00640**	0.00722 U	0.000418 U	**0.0215**	0.0119 U	0.000352 U	0.00793 U	**0.0193**	**0.0229**	**0.126**	**0.0114 J**
	MW-309-35	09/19/19	PES	PACE	35	-4.6	S	0.0154 U	**0.00516 J**	0.00733 U	0.000424 U	0.00105 U	0.0121 U	0.000358 U	0.00805 U	0.00378 U	0.00466 U	0.00143 U	0.00307 U
	MW-309-40	09/19/19	PES	PACE	40	-9.6	S	0.0154 U	0.00129 U	0.00734 U	0.000424 U	**0.00828**	0.0121 U	0.000358 U	0.00805 U	0.00378 U	0.00466 U	0.00143 U	0.00307 U
	MW-309-45	09/19/19	PES	PACE	45	-14.6	S	0.0160 U	0.00134 U	0.00763 U	0.000441 U	0.00109 U	0.0126 U	0.000372 U	0.00838 U	0.00394 U	0.00484 U	0.00149 U	0.00319 U
	MW-309-50	09/19/19	PES	PACE	50	-19.6	S	0.0151 U	0.00126 U	0.00721 U	0.000417 U	0.00103 U	0.0119 U	0.000352 U	0.00791 U	0.00372 U	0.00458 U	0.00141 U	0.00302 U
	MW-309-55	09/19/19	PES	PACE	55	-24.6	S	0.0141 U	**0.00152 J**	0.00672 U	0.000389 U	0.000958 U	0.0111 U	0.000327 U	0.00737 U	0.00346 U	0.00426 U	0.00131 U	0.00281 U
	MW-309-60	09/19/19	PES	PACE	60	-29.6	S	0.0142 U	**0.00377 J**	0.00676 U	0.000391 U	0.000965 U	0.0112 U	0.000330 U	0.00741 U	0.00348 U	0.00429 U	0.00132 U	0.00283 U
	MW-309-65	09/19/19	PES	PACE	65	-34.6	S	0.0143 U	**0.00641**	0.00680 U	0.000393 U	0.000969 U	0.0112 U	0.000331 U	0.00746 U	0.00350 U	0.00431 U	0.00133 U	0.00284 U
	MW-309-70	09/19/19	PES	PACE	70	-39.6	S	0.0144 U	0.00121 U	0.00688 U	0.000398 U	0.000981 U	0.0114 U	0.000335 U	0.00755 U	0.00355 U	0.00437 U	0.00134 U	0.00288 U
	MW-309-75	09/19/19	PES	PACE	75	-44.6	S	0.0137 U	**0.00807**	0.00654 U	0.000378 U	0.000933 U	0.0108 U	0.000319 U	0.00718 U	0.00337 U	0.00415 U	0.00128 U	0.00273 U
MW-311 (-29.0 to -39.0)	MW-311-5	09/18/19	PES	PACE	5	28.1	V	0.0152 U	**0.00436 J**	0.00724 U	0.000419 U	0.00103 U	0.0120 U	0.000353 U	**0.0128 J**	**0.00453 J**	0.00460 U	0.00141 U	0.00303 U
	MW-311-10	09/18/19	PES	PACE	10	23.1	S	0.0146 U	**0.00437 J**	0.00696 U	0.000403 U	0.000993 U	0.0115 U	0.000340 U	**0.0113 J**	0.00359 U	0.00442 U	0.00136 U	0.00291 U
	MW-311-15	09/18/19	PES	PACE	15	18.1	S	0.0341 U	0.00284 UJ	0.0162 U	0.000939 U	0.00232 U	0.0268 U	0.000792 U	**0.0273 J**	0.00837 U	0.0103 U	0.00317 U	0.00679 U
	MW-311-20	09/18/19	PES	PACE	20	13.1	S	0.0356 U	**0.0118 J**	0.0170 U	0.000980 U	0.00242 U	0.0280 U	0.000826 U	**0.0263 J**	0.00874 U	0.0107 U	0.00330 U	0.00708 U
	MW-311-25	09/18/19	PES	PACE	25	8.1	S	0.0631 U	0.00527 UJ	0.0301 U	0.00174 U	0.00428 U	0.0497 U	0.00147 U	**0.0517 J**	0.0155 U	0.0191 U	0.00586 U	0.0125 U
	MW-311-30	09/18/19	PES	PACE	30	3.1	S	0.0333 U	0.00279 UJ	0.0158 U	0.000918 U	0.00227 U	0.0263 U	0.000775 U	**0.0284 J**	0.00819 U	0.0101 U	0.00310 U	0.00664 U
	MW-311-35	09/18/19	PES	PACE	35	-1.9	S	0.0296 U	0.00247 UJ	0.0141 U	0.000816 U	0.00202 U	0.0233 U	0.000688 U	**0.0250 J**	0.00728 U	0.00896 U	0.00275 U	0.00590 U
	MW-311-40	09/18/19	PES	PACE	40	-6.9	S	0.0149 U	**0.00799**	0.00709 U	0.000410 U	0.00101 U	0.0117 U	0.000346 U	**0.0153 J**	0.00366 U	0.00450 U	0.00138 U	0.00297 U
	MW-311-45	09/18/19	PES	PACE	45	-11.9	S	0.0159 U	0.00133 UJ	0.00759 U	0.000439 U	0.00108 U	0.0126 U	0.000370 U	**0.0116 J**	0.00392 U	0.00482 U	0.00148 U	0.00318 U
	MW-311-50	09/18/19	PES	PACE	50	-16.9	S	0.0148 U	**0.00800**	0.00706 U	0.000409 U	0.00101 U	0.0117 U	0.000344 U	**0.0130 J**	0.00364 U	0.00448 U	0.00138 U	0.00295 U
	MW-311-55	09/18/19	PES	PACE	55	-21.9	S	0.0140 U	**0.00470 J**	0.00669 U	0.000387 U	0.000954 U	0.0111 U	0.000326 U	**0.00939 J**	0.00345 U	0.00425 U	0.00130 U	0.00280 U
	MW-311-60	09/18/19	PES	PACE	60	-26.9	S	0.0278 U	0.00232 UJ	0.0133 U	0.000767 U	0.00190 U	0.0219 U	0.000647 U	**0.0261 J**	0.00684 U	0.00842 U	0.00259 U	0.00554 U
	MW-311-65	09/18/19	PES	PACE	65	-31.9	S	0.0135 U	**0.00513 J**	0.00641 U	0.000371 U	0.000915 U	0.0106 U	0.000313 U	**0.00862 J**	0.00331 U	0.00407 U	0.00125 U	0.00268 U
	MW-2005-65	09/18/19	PES	PACE	65 (dup)	-31.9	S	0.0139 U	0.00116 U	0.00664 U	0.000384 U	0.000947 U	0.0110 U	0.000324 U	0.00728 U	0.00342 U	0.00421 U	0.00129 U	0.00278 U
	MW-311-70	09/18/19	PES	PACE	70	-36.9	S	0.0140 U	0.00117 U	0.00667 U	0.000386 U	0.000951 U	0.0110 U	0.000325 U	**0.00961 J**	0.00344 U	0.00423 U	0.00130 U	0.00279 U
	MW-2007-70	09/18/19	PES	PACE	70 (dup)	-38.3	S	0.0271 U	0.00226 U	0.0129 U	0.000746 U	0.00184 U	0.0213 U	0.000629 U	**0.0185 J**	0.00665 U	0.00818 U	0.00251 U	0.00539 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	–	–	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	–	–	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
MW-312	MW-312-6	09/16/19	PES	PACE	6	29.6	V	0.0155 U	0.00129 UJ	0.00736 U	0.000426 U	0.00105 U	0.0122 U	0.000359 U	0.00808 U	0.00380 U	0.00467 U	0.00144 U	0.00308 U
(19.9 to9.9)	MW-312-10	09/16/19	PES	PACE	10	25.6	V	0.0258 U	0.00215 UJ	0.0123 U	0.000710 U	0.00175 U	0.0203 U	0.000598 U	0.0135 U	0.00634 U	0.00780 U	0.00239 U	0.00513 U
	MW-312-15	09/16/19	PES	PACE	15	20.6	S	0.0175 U	0.00146 UJ	0.00836 U	0.000484 U	**0.00299 J**	0.0138 U	0.000408 U	0.00917 U	**0.00533 J**	**0.0240**	**0.0288**	**0.00548 J**
	MW-312-20	09/16/19	PES	PACE	20	15.6	S	0.0137 U	**0.00561**	0.00655 U	0.000379 U	0.000934 U	0.0108 U	0.000319 U	0.00718 U	0.00338 U	**0.0365**	0.00128 U	**0.0340**
	MW-2004-20	09/16/19	PES	PACE	20	15.6	S	0.0147 U	0.00122 UJ	0.00699 U	0.000404 U	0.000996 U	0.0115 U	0.000341 U	0.00767 U	0.00360 U	0.00443 U	0.00136 U	0.00292 U
	MW-312-25	09/16/19	PES	PACE	25	10.6	S	0.0142 U	0.00119 UJ	0.00677 U	0.000392 U	**0.00244 J**	0.0112 U	0.000330 U	0.00743 U	0.00349 U	**0.0153**	0.00132 U	**0.0161**
MW-314	MW-314-6	09/13/19	PES	PACE	6	33.8	V	0.0144 U	0.00120 U	0.00687 U	0.000398 U	0.000980 U	0.0114 U	0.000335 U	0.00754 U	**0.00398 J**	0.00436 U	0.00134 U	0.00287 U
(-28.0 to -38.0)	MW-314-10	09/13/19	PES	PACE	10	29.8	V	0.0146 U	0.00121 U	0.00694 U	0.000402 U	0.000990 U	0.0115 U	0.000339 U	0.00762 U	0.00358 U	0.00441 U	0.00135 U	0.00290 U
	MW-314-15	09/13/19	PES	PACE	15	24.8	V	0.0143 U	0.00119 U	0.00681 U	0.000394 U	0.000971 U	0.0113 U	0.000332 U	0.00747 U	0.00351 U	0.00432 U	0.00133 U	0.00285 U
	MW-314-20	09/13/19	PES	PACE	20	19.8	S	0.0146 U	0.00122 U	0.00694 U	0.000402 U	0.000990 U	0.0115 U	0.000339 U	0.00762 U	0.00358 U	0.00441 U	0.00135 U	0.00290 U
	MW-314-25	09/13/19	PES	PACE	25	14.8	S	0.0161 U	0.00135 U	0.00768 U	0.000444 U	0.00110 U	0.0127 U	0.000375 U	0.00843 U	0.00396 U	0.00488 U	0.00150 U	0.00321 U
	MW-2002-25	09/13/19	PES	PACE	25	14.8	S	0.0160 U	0.00134 UJ	0.00764 U	0.000442 U	0.00109 U	0.0126 U	0.000372 U	**0.00999 J**	0.00394 U	0.00485 U	0.00149 U	0.00319 U
	MW-314-30	09/13/19	PES	PACE	30	9.8	S	0.0158 U	0.00132 U	0.00753 U	0.000435 U	0.00107 U	0.0124 U	0.000367 U	0.00826 U	0.00388 U	0.00478 U	0.00147 U	0.00315 U
	MW-314-35	09/13/19	PES	PACE	35	4.8	S	0.0136 U	0.00114 U	0.00649 U	0.000375 U	0.000926 U	0.0107 U	0.000316 U	**0.00784 J**	0.00335 U	0.00412 U	0.00127 U	0.00271 U
	MW-314-40	09/13/19	PES	PACE	40	-0.2	S	0.0141 U	0.00118 U	0.00674 U	0.000391 U	0.000963 U	0.0111 U	0.000329 U	0.00741 U	0.00348 U	0.00428 U	0.00131 U	0.00283 U
	MW-314-45	09/13/19	PES	PACE	45	-5.2	S	0.0141 U	0.00117 U	0.00670 U	0.000387 U	0.000955 U	0.0111 U	0.000327 U	0.00735 U	0.00345 U	0.00425 U	0.00131 U	0.00280 U
	MW-314-50	09/13/19	PES	PACE	50	-10.2	S	0.0141 U	0.00118 U	0.00674 U	0.000390 U	0.000961 U	0.0111 U	0.000328 U	0.00739 U	0.00347 U	0.00428 U	0.00131 U	0.00282 U
	MW-314-55	09/13/19	PES	PACE	55	-15.2	S	0.0153 U	0.00128 U	0.00730 U	0.000423 U	0.00104 U	0.0121 U	0.000356 U	0.00802 U	0.00377 U	0.00464 U	0.00142 U	0.00305 U
	MW-314-60	09/13/19	PES	PACE	60	-20.2	S	0.0140 U	**0.0106**	0.00669 U	0.000387 U	0.000955 U	0.0111 U	0.000326 U	0.00734 U	0.00345 U	0.00425 U	0.00131 U	0.00280 U
	MW-314-65	09/13/19	PES	PACE	65	-25.2	S	0.0144 U	0.00120 UJ	0.00687 U	0.000397 U	0.000980 U	0.0114 U	0.000335 U	**0.0108 J**	0.00354 U	0.00436 U	0.00134 U	0.00287 U
	MW-314-70	09/13/19	PES	PACE	70	-30.2	S	0.154 U	0.0128 UJ	0.0735 U	0.00425 U	0.0105 U	0.122 U	0.00358 U	0.0806 U	0.0379 U	0.0467 U	0.0143 U	0.0307 U
	MW-314-75	09/13/19	PES	PACE	75	-35.2	S	0.0290 U	0.00242 UJ	0.0138 U	0.000799 U	0.00198 U	0.0228 U	0.000674 U	**0.0169 J**	0.00712 U	0.00877 U	0.00269 U	0.00578 U
	MW-314-80	09/13/19	PES	PACE	80	-40.2	S	0.0189 U	0.00159 UJ	0.00904 U	0.000523 U	0.00129 U	0.0149 U	0.000440 U	**0.0169 J**	0.00465 U	0.00573 U	0.00176 U	0.00377 U
MW-316	MW-316-5	09/09/19	PES	PACE	5	44.8	V	0.0137 U	**0.00567**	0.00655 U	0.000379 U	0.000934 U	0.0108 U	0.000319 U	0.0126 U	0.00338 U	0.00416 U	0.00128 U	0.00274 U
(-10.0 to -20.0)	MW-316-10	09/09/19	PES	PACE	10	39.8	V	0.0144 U	**0.00978**	0.00684 U	0.000396 U	0.000976 U	0.0113 U	0.000334 U	0.0161 U	0.00353 U	0.00434 U	0.00133 U	0.00286 U
	MW-316-15	09/09/19	PES	PACE	15	34.8	V	0.0143 U	**0.00364 J**	0.00680 U	0.000394 U	0.000970 U	0.0112 U	0.000332 U	0.0110 U	0.00351 U	0.00432 U	0.00133 U	0.00284 U
	MW-316-20	09/09/19	PES	PACE	20	29.8	V	0.0137 U	**0.00400 J**	0.00653 U	0.000378 U	0.000931 U	0.0108 U	0.000318 U	0.0111 U	0.00337 U	0.00414 U	0.00127 U	0.00273 U
	MW-316-25	09/09/19	PES	PACE	25	24.8	S	0.0144 U	**0.00626**	0.00686 U	0.000397 U	0.000979 U	0.0113 U	0.000335 U	0.0116 U	0.00354 U	0.00436 U	0.00134 U	0.00287 U
	MW-316-30	09/09/19	PES	PACE	30	19.8	S	0.0141 U	**0.00285 J**	0.00671 U	0.000388 U	0.000958 U	0.0111 U	0.000327 U	0.0125 U	0.00346 U	0.00426 U	0.00131 U	0.00281 U
	MW-316-35	09/09/19	PES	PACE	35	14.8	S	0.0143 U	**0.00409 J**	0.00683 U	0.000395 U	0.000974 U	0.0113 U	0.000333 U	0.0119 U	0.00352 U	0.00433 U	0.00133 U	0.00286 U
	MW-316-40	09/09/19	PES	PACE	40	9.8	S	0.0145 U	**0.00485 J**	0.00688 U	0.000398 U	0.000982 U	0.0114 U	0.000336 U	0.00847 U	0.00355 U	0.00437 U	0.00134 U	0.00288 U
	MW-316-45	09/09/19	PES	PACE	45	4.8	S	0.0141 U	**0.00338 J**	0.00673 U	0.000389 U	0.000960 U	0.0111 U	0.000328 U	0.0104 U	0.00347 U	0.00427 U	0.00131 U	0.00281 U
	MW-316-50	09/09/19	PES	PACE	50	-0.2	S	0.0152 U	**0.00718**	0.00724 U	0.000419 U	0.00103 U	0.0120 U	0.000353 U	0.0176 U	0.00373 U	0.00459 U	0.00141 U	0.00303 U
	MW-316-55	09/09/19	PES	PACE	55	-5.2	S	0.0144 U	**0.00267 J**	0.00685 U	0.000396 U	0.000977 U	0.0113 U	0.000334 U	0.0121 U	0.00353 U	0.00435 U	0.00134 U	0.00287 U
	MW-316-60	09/09/19	PES	PACE	60	-10.2	S	0.0143 U	**0.00484 J**	0.00680 U	0.000394 U	0.000970 U	0.0112 U	0.000332 U	0.0110 U	0.00351 U	0.00432 U	0.00133 U	0.00284 U
	MW-316-65	09/10/19	PES	PACE	65	-15.2	S	0.0190 U	**0.00602 J**	0.00906 U	0.000524 U	0.00129 U	0.0150 U	0.000441 U	0.0209 U	0.00467 U	0.00575 U	0.00177 U	0.00379 U
	MW-2001-65	09/10/19	PES	PACE	65	-15.2	S	0.0150 U	**0.00357 J**	0.00717 U	0.000415 U	0.00102 U	0.0118 U	0.000349 U	0.0137 U	0.00370 U	0.00455 U	0.00140 U	0.00300 U
	MW-316-70	09/10/19	PES	PACE	70	-20.2	S	0.0144 U	**0.00431 J**	0.00685 U	0.000396 U	0.000977 U	0.0113 U	0.000334 U	0.0125 U	0.00353 U	0.00435 U	0.00134 U	0.00286 U
MW-319	MW-319-6	09/18/19	PES	PACE	6	25.7	V	0.0147 U	**0.0157**	0.00702 U	0.000406 U	0.00100 U	0.0116 U	0.000342 U	**0.0139 J**	0.00362 U	0.00446 U	0.00137 U	0.00294 U
(-42.8 to -52.8)	MW-319-10	09/18/19	PES	PACE	10	21.7	S	0.0146 U	**0.0384**	0.00698 U	0.000404 U	0.000995 U	0.0115 U	0.000340 U	**0.00934 J**	0.00360 U	0.00443 U	0.00136 U	0.00292 U
	MW-319-15	09/18/19	PES	PACE	15	16.7	S	0.0145 U	**0.0376**	0.00693 U	0.000401 U	0.000989 U	0.0115 U	0.000338 U	**0.00832 J**	0.00357 U	0.00440 U	0.00135 U	0.00290 U
	MW-319-20	09/18/19	PES	PACE	20	11.7	S	0.0157 U	**0.0117**	0.00749 U	0.000434 U	0.00107 U	0.0124 U	0.000365 U	**0.00945 J**	0.00386 U	0.00476 U	0.00146 U	0.00313 U
	MW-319-30	09/18/19	PES	PACE	30	1.7	S	0.0145 U	**0.00567 J**	0.00691 U	0.000400 U	0.000986 U	0.0114 U	0.000337 U	**0.00924 J**	0.00357 U	0.00439 U	0.00135 U	0.00289 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	–	–	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	–	–	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
MW-319 (continued)	MW-319-35	09/18/19	PES	PACE	35	-3.3	S	0.0160 U	**0.0300**	0.00763 U	0.000441 U	0.00109 U	0.0126 U	0.000372 U	**0.00950 J**	**0.00502 J**	0.00484 U	0.00149 U	0.00319 U
	MW-319-40	09/18/19	PES	PACE	40	-8.3	S	0.0150 U	**0.0254**	0.00714 U	0.000413 U	0.00102 U	0.0118 U	0.000348 U	**0.00804 J**	0.00368 U	0.00453 U	0.00139 U	0.00299 U
	MW-319-45	09/18/19	PES	PACE	45	-13.3	S	0.0151 U	**0.00532 J**	0.00718 U	0.000416 U	0.00102 U	0.0119 U	0.000350 U	**0.00814 J**	0.00371 U	0.00456 U	0.00140 U	0.00300 U
	MW-319-50	09/18/19	PES	PACE	50	-18.3	S	0.0155 U	**0.0245**	0.00739 U	0.000427 U	0.00105 U	0.0122 U	0.000360 U	**0.0122 J**	0.00381 U	0.00469 U	0.00144 U	0.00309 U
	MW-319-55	09/18/19	PES	PACE	55	-23.3	S	0.0160 U	**0.00237 J**	0.00764 U	0.000442 U	0.00109 U	0.0126 U	0.000373 U	**0.0109 J**	0.00394 U	0.00485 U	0.00149 U	0.00320 U
	MW-319-60	09/18/19	PES	PACE	60	-28.3	S	0.0151 U	**0.0341**	0.00718 U	0.000416 U	0.00102 U	0.0119 U	0.000350 U	**0.00996 J**	0.00371 U	0.00456 U	0.00140 U	0.00300 U
	MW-319-65	09/18/19	PES	PACE	65	-33.3	S	0.0162 U	**0.0394**	0.00771 U	0.000446 U	0.00110 U	0.0127 U	0.000376 U	**0.0124 J**	0.00398 U	0.00490 U	0.00150 U	0.00323 U
	MW-319-70	09/18/19	PES	PACE	70	-38.3	S	0.0155 U	**0.0362**	0.00737 U	0.000426 U	0.00105 U	0.0122 U	0.000359 U	**0.00934 J**	0.00380 U	0.00468 U	0.00144 U	0.00308 U
	MW-2006-70	09/18/19	PES	PACE	70 (dup)	-36.9	S	0.0159 U	**0.0305**	0.00758 U	0.000439 U	0.00108 U	0.0125 U	0.000370 U	**0.0135 J**	0.00391 U	0.00481 U	0.00148 U	0.00317 U
	MW-319-75	09/18/19	PES	PACE	75	-43.3	S	0.0141 U	**0.0194**	0.00670 U	0.000388 U	0.000956 U	0.0111 U	0.000327 U	**0.00915 J**	0.00346 U	0.00425 U	0.00131 U	0.00280 U
	MW-319-80	09/18/19	PES	PACE	80	-48.3	S	0.0154 U	**0.0217**	0.00735 U	0.000425 U	0.00105 U	0.0122 U	0.000359 U	**0.0102 J**	0.00379 U	0.00467 U	0.00143 U	0.00308 U
	MW-319-85	09/18/19	PES	PACE	85	-53.3	S	0.0153 U	**0.0273**	0.00728 U	0.000421 U	0.00104 U	0.0120 U	0.000355 U	**0.0113 J**	0.00375 U	0.00462 U	0.00142 U	0.00304 U
MW-320 (18.6 to 8.6)	MW-320-19	09/29/19	PES	PACE	19	15.1	S	0.284 U	0.0237 U	0.135 U	0.00782 U	**1.35**	0.223 U	0.00659 U	**0.166 J**	0.0697 U	**0.264 J**	**1.81**	**1.75**
	MW-320-27	09/29/19	PES	PACE	27	7.1	S	0.0147 U	**0.0255**	0.00701 U	0.000405 U	0.000999 U	0.0116 U	0.000342 U	**0.00804 J**	0.00361 U	0.00445 U	0.00137 U	0.00293 U
MW-323 (-65.4 to -75.4)	MW-323-10	09/28/19	PES	PACE	10	24.7	V	0.0310 U	0.00258 U	0.0148 U	0.000853 U	0.00211 U	0.0244 U	0.000719 U	0.0165 U	0.00761 U	0.00936 U	0.00288 U	0.00617 U
	MW-2012-10	09/28/19	PES	PACE	10 (dup)	24.7	V	0.0159 U	**0.0259**	0.00756 U	0.000437 U	0.00108 U	0.0125 U	0.000369 U	**0.0109 J**	0.00390 U	0.00480 U	0.00148 U	0.00316 U
	MW-323-15	09/28/19	PES	PACE	15	19.7	S	0.0291 U	0.00243 U	0.0138 U	0.000802 U	0.00198 U	0.0229 U	0.000677 U	0.0172 U	0.00715 U	0.00880 U	0.00271 U	0.00580 U
	MW-323-20	09/28/19	PES	PACE	20	14.7	S	0.0143 U	**0.0473**	0.00683 U	0.000395 U	**0.00451**	0.0113 U	0.000333 U	0.00750 U	**0.00629 J**	**0.00502 J**	**0.0216**	0.00286 U
	MW-323-25	09/28/19	PES	PACE	25	9.7	S	0.0145 U	0.00121 U	0.00690 U	0.000399 U	0.000984 U	0.0114 U	0.000336 U	0.00789 U	0.00356 U	0.00438 U	0.00135 U	0.00288 U
	MW-323-30	09/28/19	PES	PACE	30	4.7	S	0.0270 U	0.00225 U	0.0128 U	0.000743 U	0.00184 U	0.0212 U	0.000627 U	0.0142 U	0.00663 U	0.00816 U	0.00251 U	0.00537 U
	MW-323-35	09/28/19	PES	PACE	35	-0.4	S	0.0163 U	0.00136 U	0.00778 U	0.000450 U	0.00111 U	0.0129 U	0.000379 U	0.00906 U	0.00401 U	0.00494 U	0.00152 U	0.00325 U
	MW-323-40	09/28/19	PES	PACE	40	-5.4	S	0.0163 U	**0.00998**	0.00777 U	0.000449 U	0.00111 U	0.0128 U	0.000379 U	0.00984 U	0.00401 U	0.00493 U	0.00152 U	0.00325 U
	MW-323-45	09/28/19	PES	PACE	45	-10.4	S	0.0162 U	**0.0265**	0.00774 U	0.000448 U	0.00110 U	0.0128 U	0.000377 U	0.00850 U	**0.0120 J**	0.00491 U	0.00151 U	0.00324 U
	MW-323-50	09/28/19	PES	PACE	50	-15.4	S	0.0146 U	**0.0373**	0.00696 U	0.000403 U	0.000993 U	0.0115 U	0.000340 U	0.00764 U	0.00359 U	0.00442 U	0.00136 U	0.00291 U
	MW-323-55	09/28/19	PES	PACE	55	-20.4	S	0.0148 U	**0.0289**	0.00705 U	0.000408 U	0.00101 U	0.0117 U	0.000344 U	0.0102 U	0.00364 U	0.00447 U	0.00137 U	0.00295 U
	MW-323-60	09/28/19	PES	PACE	60	-25.4	S	0.0162 U	**0.0289**	0.00775 U	0.000448 U	0.00111 U	0.0128 U	0.000378 U	0.0133 U	0.00400 U	0.00492 U	0.00151 U	0.00325 U
	MW-2010-60	09/28/19	PES	PACE	60 (dup)	-25.4	S	0.0155 U	**0.0300**	0.00738 U	0.000427 U	0.00105 U	0.0122 U	0.000360 U	**0.0105 J**	0.00380 U	0.00468 U	0.00144 U	0.00308 U
	MW-323-65	09/28/19	PES	PACE	65	-30.4	S	0.0153 U	**0.0130**	0.00727 U	0.000421 U	0.00104 U	0.0120 U	0.000355 U	**0.0101 J**	0.00375 U	0.00461 U	0.00142 U	0.00304 U
	MW-323-70	09/28/19	PES	PACE	70	-35.4	S	2.14 U	0.178 U	1.02 U	0.0589 U	0.145 U	1.68 U	0.0496 U	**1.15 J**	27.6 R	0.646 U	0.198 U	0.426 U
	MW-323-75	09/28/19	PES	PACE	75	-40.4	S	0.0149 U	**0.0159**	0.00711 U	0.000411 U	0.00101 U	0.0118 U	0.000347 U	**0.00973 J**	0.00367 U	0.00451 U	0.00139 U	0.00297 U
	MW-323-80	09/28/19	PES	PACE	80	-45.4	S	0.0144 U	**0.0278**	0.00684 U	0.000396 U	0.000975 U	0.0113 U	0.000333 U	**0.00919 J**	0.00353 U	0.00434 U	0.00133 U	0.00286 U
	MW-323-85	09/28/19	PES	PACE	85	-50.4	S	0.0152 U	**0.0298**	0.00725 U	0.000419 U	0.00103 U	0.0120 U	0.000353 U	0.00795 U	0.00374 U	0.00460 U	0.00141 U	0.00303 U
	MW-323-91	09/28/19	PES	PACE	91	-56.4	S	0.0360 U	**0.0145**	0.0171 U	0.000992 U	0.00244 U	0.0283 U	0.000835 U	**0.0253 J**	0.00884 U	0.0109 U	0.00335 U	0.00717 U
	MW-323-95	09/28/19	PES	PACE	95	-60.4	S	0.0152 U	**0.0175**	0.00725 U	0.000420 U	0.00103 U	0.0120 U	0.000354 U	**0.00910 J**	0.00374 U	0.00460 U	0.00141 U	0.00303 U
	MW-323-99	09/28/19	PES	PACE	99	-64.4	S	0.0147 U	**0.0188**	0.00699 U	0.000405 U	0.000998 U	0.0116 U	0.000341 U	**0.00955 J**	0.00361 U	0.00444 U	0.00136 U	0.00292 U
	MW-323-105	09/28/19	PES	PACE	105	-70.4	S	0.0150 U	**0.00978**	0.00714 U	0.000413 U	0.00102 U	0.0118 U	0.000348 U	0.00784 U	0.00368 U	0.00453 U	0.00139 U	0.00299 U
	MW-323-110	09/28/19	PES	PACE	110	-75.4	S	0.0311 U	**0.0179**	0.0149 U	0.000858 U	0.00211 U	0.0245 U	0.000723 U	**0.0183 J**	0.00765 U	0.00940 U	0.00289 U	0.00619 U
MW-324 (-32.1 to -42.1)	MW-324-6	09/12/19	PES	PACE	6	28.3	V	0.0143 U	0.00119 U	0.00680 U	0.000394 U	0.000971 U	0.0112 U	0.000332 U	0.00747 U	0.00351 U	0.00432 U	0.00133 U	0.00285 U
	MW-324-10	09/12/19	PES	PACE	10	24.3	V	0.0147 U	0.00123 U	0.00701 U	0.000405 U	0.000999 U	0.0116 U	0.000342 U	**0.00841 J**	0.00361 U	0.00445 U	0.00137 U	0.00293 U
	MW-324-15	09/12/19	PES	PACE	15	19.3	S	0.0139 U	0.00116 U	0.00661 U	0.000382 U	0.000942 U	0.0109 U	0.000322 U	**0.00819 J**	0.00341 U	0.00419 U	0.00129 U	0.00276 U
	MW-324-20	09/12/19	PES	PACE	20	14.3	S	0.0148 U	0.00124 U	0.00706 U	0.000408 U	0.00101 U	0.0117 U	0.000344 U	0.00775 U	0.00364 U	0.00448 U	0.00138 U	0.00295 U
	MW-324-25	09/12/19	PES	PACE	25	9.3	S	0.0150 U	0.00125 U	0.00714 U	0.000413 U	0.00102 U	0.0118 U	0.000348 U	0.00784 U	**0.0117 J**	0.00453 U	0.00139 U	0.00299 U
	MW-324-30	09/12/19	PES	PACE	30	4.3	S	0.0157 U	0.00130 U	0.00744 U	0.000430 U	0.00106 U	0.0123 U	0.000363 U	**0.00986 J**	0.00383 U	0.00472 U	0.00145 U	0.00311 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	–	–	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	–	–	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
MW-324 (continued)	MW-324-35	09/12/19	PES	PACE	35	-0.7	S	0.0152 U	0.00127 U	0.00722 U	0.000418 U	0.00103 U	0.0119 U	0.000352 U	0.00793 U	0.00372 U	0.00458 U	0.00141 U	0.00302 U
	MW-324-40	09/12/19	PES	PACE	40	-5.7	S	0.0153 U	0.00128 U	0.00731 U	0.000423 U	0.00104 U	0.0121 U	0.000357 U	**0.00821 J**	0.00377 U	0.00464 U	0.00143 U	0.00306 U
	MW-324-45	09/12/19	PES	PACE	45	-10.7	S	0.0160 U	**0.0128**	0.00762 U	0.000441 U	0.00109 U	0.0126 U	0.000371 U	**0.00943 J**	0.00393 U	0.00483 U	0.00149 U	0.00318 U
	MW-324-50	09/12/19	PES	PACE	50	-15.7	S	0.0127 U	0.00106 U	0.00605 U	0.000350 U	0.000863 U	0.0100 U	0.000295 U	0.00664 U	0.00312 U	0.00384 U	0.00118 U	0.00253 U
	MW-324-55	09/12/19	PES	PACE	55	-20.7	S	0.0144 U	0.00120 U	0.00686 U	0.000397 U	0.000978 U	0.0113 U	0.000334 U	**0.00805 J**	0.00354 U	0.00435 U	0.00134 U	0.00287 U
	MW-324-60	09/12/19	PES	PACE	60	-25.7	S	0.0144 U	**0.0181**	0.00686 U	0.000397 U	0.000978 U	0.0113 U	0.000334 U	0.00753 U	0.00354 U	0.00435 U	0.00134 U	0.00287 U
	MW-324-65	09/12/19	PES	PACE	65	-30.7	S	0.0149 U	0.00125 U	0.00712 U	0.000412 U	0.00102 U	0.0118 U	0.000347 U	**0.0111 J**	0.00367 U	0.00452 U	0.00139 U	0.00298 U
	MW-324-70	09/12/19	PES	PACE	70	-35.7	S	0.0158 U	0.00131 U	0.00750 U	0.000434 U	0.00107 U	0.0124 U	0.000366 U	**0.00894 J**	0.00387 U	0.00476 U	0.00146 U	0.00314 U
	MW-324-75	09/12/19	PES	PACE	75	-40.7	S	0.0159 U	0.00133 U	0.00759 U	0.000439 U	0.00108 U	0.0125 U	0.000370 U	0.00833 U	0.00391 U	0.00482 U	0.00148 U	0.00317 U
	MW-324-80	09/12/19	PES	PACE	80	-45.7	S	0.0159 U	0.00133 U	0.00757 U	0.000438 U	0.00108 U	0.0125 U	0.000369 U	**0.0112 J**	0.00390 U	0.00481 U	0.00148 U	0.00317 U
MW-326 (-48.7 to -58.7)	MW-326-5	09/09/19	PES	PACE	5	36.3	V	0.0140 U	**0.00634**	0.00667 U	0.000386 U	0.000951 U	0.0110 U	0.000325 U	**0.00943 J**	**0.00452 J**	0.00423 U	0.00130 U	0.00279 U
	MW-326-10	09/09/19	PES	PACE	10	31.3	V	0.0169 U	**0.00462 J**	0.00805 U	0.000466 U	0.00115 U	0.0133 U	0.000393 U	**0.0129 J**	0.00415 U	0.00511 U	0.00157 U	0.00336 U
	MW-326-15	09/09/19	PES	PACE	15	26.3	V	0.0149 U	**0.00338 J**	0.00708 U	0.000409 U	0.00101 U	0.0117 U	0.000345 U	**0.00875 J**	0.00365 U	0.00449 U	0.00138 U	0.00296 U
	MW-326-20	09/09/19	PES	PACE	20	21.3	S	0.0149 U	0.00124 U	0.00708 U	0.000410 U	0.00101 U	0.0117 U	0.000345 U	0.00777 U	0.00365 U	0.00450 U	0.00138 U	0.00296 U
	MW-326-25	09/09/19	PES	PACE	25	16.3	S	0.0158 U	**0.00347 J**	0.00751 U	0.000434 U	0.00107 U	0.0124 U	0.000366 U	**0.0105 J**	0.00387 U	0.00477 U	0.00146 U	0.00314 U
	MW-326-30	09/09/19	PES	PACE	30	11.3	S	0.0513 U	0.00428 U	0.0244 U	0.00141 U	0.00349 U	0.0404 U	0.00119 U	**0.0350 J**	0.0126 U	0.0155 U	0.00477 U	0.0102 U
	MW-326-35	09/09/19	PES	PACE	35	6.3	S	0.0157 U	**0.00352 J**	0.00748 U	0.000433 U	0.00107 U	0.0124 U	0.000365 U	**0.0120 J**	0.00386 U	0.00475 U	0.00146 U	0.00313 U
	MW-326-40	09/09/19	PES	PACE	40	1.3	S	0.0151 U	**0.00406 J**	0.00721 U	0.000417 U	0.00103 U	0.0119 U	0.000352 U	**0.00885 J**	0.00372 U	0.00458 U	0.00141 U	0.00302 U
	MW-326-45	09/09/19	PES	PACE	45	-3.7	S	0.0153 U	**0.00229 J**	0.00729 U	0.000422 U	0.00104 U	0.0120 U	0.000355 U	**0.00974 J**	0.00376 U	0.00462 U	0.00142 U	0.00305 U
	MW-326-50	09/09/19	PES	PACE	50	-8.7	S	0.0145 U	0.00121 U	0.00692 U	0.000400 U	0.000987 U	0.0114 U	0.000337 U	**0.0118 J**	0.00357 U	0.00439 U	0.00135 U	0.00289 U
	MW-326-55	09/09/19	PES	PACE	55	-13.7	S	0.0154 U	**0.00564 J**	0.00736 U	0.000426 U	0.00105 U	0.0122 U	0.000359 U	**0.0149 J**	0.00380 U	0.00467 U	0.00144 U	0.00308 U
	MW-326-60	09/09/19	PES	PACE	60	-18.7	S	0.0138 U	0.00115 U	0.00658 U	0.000380 U	0.000938 U	0.0109 U	0.000321 U	**0.0105 J**	0.00339 U	0.00417 U	0.00128 U	0.00275 U
	MW-326-65	09/09/19	PES	PACE	65	-23.7	S	0.0147 U	**0.00400 J**	0.00701 U	0.000406 U	0.00100 U	0.0116 U	0.000342 U	0.00785 U	0.00362 U	0.00445 U	0.00137 U	0.00293 U
	MW-326-70	09/09/19	PES	PACE	70	-28.7	S	0.0155 U	**0.00325 J**	0.00737 U	0.000426 U	0.00105 U	0.0122 U	0.000359 U	0.00839 U	0.00380 U	0.00468 U	0.00144 U	0.00308 U
	MW-326-75	09/09/19	PES	PACE	75	-33.7	S	0.0154 U	**0.00330 J**	0.00733 U	0.000424 U	0.00105 U	0.0121 U	0.000358 U	0.0122 U	0.00378 U	0.00466 U	0.00143 U	0.00307 U
	MW-326-80	09/09/19	PES	PACE	80	-38.7	S	0.0151 U	**0.00388 J**	0.00719 U	0.000416 U	0.00103 U	0.0119 U	0.000351 U	0.00789 U	0.00371 U	0.00456 U	0.00140 U	0.00301 U
	MW-326-85	09/10/19	PES	PACE	85	-43.7	S	0.0148 U	0.00124 U	0.00707 U	0.000409 U	0.00101 U	0.0117 U	0.000345 U	0.00776 U	0.00365 U	0.00449 U	0.00138 U	0.00296 U
	MW-326-90	09/10/19	PES	PACE	90	-48.7	S	0.0150 U	**0.00493 J**	0.00712 U	0.000412 U	0.00102 U	0.0118 U	0.000347 U	0.0103 U	0.00367 U	0.00452 U	0.00139 U	0.00298 U
	MW-326-95	09/10/19	PES	PACE	95	-53.7	S	0.0143 U	0.00119 U	0.00680 U	0.000393 U	0.000970 U	0.0112 U	0.000331 U	0.00980 U	0.00351 U	0.00431 U	0.00133 U	0.00284 U
	MW-200I-95	09/10/19	PES	PACE	95 (dup)	-53.7	S	0.0145 U	**0.00489 J**	0.00690 U	0.000399 U	0.000984 U	0.0114 U	0.000336 U	0.00757 U	0.00356 U	0.00438 U	0.00135 U	0.00289 U
	MW-326-100	09/10/19	PES	PACE	100	-58.7	S	0.0153 U	0.00128 U	0.00731 U	0.000423 U	0.00104 U	0.0121 U	0.000356 U	0.0117 U	0.00377 U	0.00464 U	0.00143 U	0.00306 U
MW-328 (-36.1 to -46.1)	MW-328-5	09/16/19	PES	PACE	5	23.4	V	0.0151 U	0.00126 UJ	0.00719 U	0.000416 U	0.00103 U	0.0119 U	0.000351 U	0.00789 U	0.00371 U	0.00457 U	0.00140 U	0.00301 U
	MW-328-10	09/16/19	PES	PACE	10	18.4	S	0.0175 U	0.00146 UJ	0.00832 U	0.000481 U	0.00119 U	0.0137 U	0.000405 U	0.00913 U	0.00429 U	0.00528 U	0.00162 U	0.00348 U
	MW-328-15	09/16/19	PES	PACE	15	13.4	S	0.0156 U	0.00130 UJ	0.00743 U	0.000430 U	0.00106 U	0.0123 U	0.000362 U	0.00815 U	0.00383 U	0.00471 U	0.00145 U	0.00311 U
	MW-328-20	09/16/19	PES	PACE	20	8.4	S	0.0152 U	0.00127 UJ	0.00722 U	0.000418 U	0.00103 U	0.0119 U	0.000352 U	0.00793 U	0.00373 U	0.00459 U	0.00141 U	0.00302 U
	MW-328-30	09/16/19	PES	PACE	30	-1.6	S	0.299 U	**0.130**	0.143 U	0.00825 U	0.0204 U	0.236 U	0.00695 U	0.157 U	0.0736 U	0.0905 U	0.0278 U	0.0596 U
	MW-328-35	09/16/19	PES	PACE	35	-6.6	S	0.0164 U	**0.00384 J**	0.00777 U	0.000450 U	0.00111 U	0.0129 U	0.000380 U	0.00854 U	0.00401 U	0.00493 U	0.00152 U	0.00325 U
	MW-328-40	09/16/19	PES	PACE	40	-11.6	S	0.0370 U	0.00309 UJ	0.0176 U	0.00102 U	0.00251 U	0.0291 U	0.000859 U	0.0193 U	0.00908 U	0.0112 U	0.00344 U	0.00737 U
	MW-328-45	09/16/19	PES	PACE	45	-16.6	S	0.0157 U	**0.00241 J**	0.00746 U	0.000432 U	0.00106 U	0.0123 U	0.000364 U	0.00819 U	0.00385 U	0.00473 U	0.00146 U	0.00312 U
	MW-328-50	09/16/19	PES	PACE	50	-21.6	S	0.467 U	**0.152 J**	0.222 U	0.0129 U	0.0317 U	0.367 U	0.0108 U	0.243 U	0.115 U	0.141 U	0.0433 U	0.0929 U
	MW-328-55	09/16/19	PES	PACE	55	-26.6	S	0.0151 U	0.00126 UJ	0.00720 U	0.000417 U	0.00103 U	0.0119 U	0.000351 U	0.00790 U	0.00371 U	0.00457 U	0.00140 U	0.00301 U
	MW-328-60	09/16/19	PES	PACE	60	-31.6	S	0.0153 U	**0.00311 J**	0.00727 U	0.000421 U	0.00104 U	0.0120 U	0.000355 U	0.00798 U	0.00375 U	0.00462 U	0.00142 U	0.00304 U
	MW-328-65	09/16/19	PES	PACE	65	-36.6	S	0.0148 U	**0.00536 J**	0.00705 U	0.000408 U	0.00101 U	0.0117 U	0.000344 U	0.00774 U	0.00364 U	0.00448 U	0.00138 U	0.00295 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	–	–	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	–	–	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
MW-328 (continued)	MW-328-70	09/16/19	PES	PACE	70	-41.6	S	0.0153 U	0.00128 UJ	0.00728 U	0.000421 U	0.00104 U	0.0120 U	0.000355 U	0.00800 U	0.00376 U	0.00462 U	0.00142 U	0.00305 U
	MW-328-75	09/16/19	PES	PACE	75	-46.6	S	0.0148 U	**0.00357 J**	0.00706 U	0.000408 U	0.00101 U	0.0117 U	0.000344 U	0.00774 U	0.00364 U	0.00448 U	0.00138 U	0.00295 U
	MW-328-80	09/16/19	PES	PACE	80	-51.6	S	0.0168 U	0.00140 UJ	0.00798 U	0.000462 U	0.00114 U	0.0132 U	0.000389 U	0.00876 U	0.00412 U	0.00507 U	0.00156 U	0.00334 U
MW-329 (-69.0 to -79.0)	MW-329-5	09/12/19	PES	PACE	5	24.3	V	0.0136 U	0.00113 U	0.00647 U	0.000374 U	0.000922 U	0.0107 U	0.000315 U	0.00710 U	0.00333 U	0.00410 U	0.00126 U	0.00270 U
	MW-329-10	09/12/19	PES	PACE	10	19.3	S	0.0134 U	0.00112 U	0.00636 U	0.000368 U	0.000908 U	0.0105 U	0.000310 U	0.00698 U	0.00328 U	0.00404 U	0.00124 U	0.00266 U
	MW-329-15	09/12/19	PES	PACE	15	14.3	S	0.0139 U	**0.00645**	0.00664 U	0.000384 U	0.000948 U	0.0110 U	0.000324 U	0.00729 U	0.00343 U	0.00422 U	0.00130 U	0.00278 U
	MW-329-20	09/12/19	PES	PACE	20	9.3	S	0.0176 U	0.00147 U	0.00836 U	**0.000791 J**	0.00119 U	0.0138 U	0.000408 U	0.00918 U	0.00431 U	0.00531 U	0.00163 U	0.00350 U
	MW-329-25	09/12/19	PES	PACE	25	4.3	S	0.0182 U	0.00152 U	0.00867 U	0.000502 U	0.00124 U	0.0143 U	0.000423 U	0.0104 U	0.00447 U	0.00550 U	0.00169 U	0.00363 U
	MW-329-30	09/12/19	PES	PACE	30	-0.7	S	0.0157 U	0.00131 U	0.00747 U	0.000432 U	0.00107 U	0.0124 U	0.000364 U	0.0101 U	0.00385 U	0.00474 U	0.00146 U	0.00313 U
	MW-329-35	09/12/19	PES	PACE	35	-5.7	S	0.0156 U	0.00130 U	0.00741 U	0.000429 U	0.00106 U	0.0123 U	0.000361 U	0.00814 U	0.00382 U	0.00471 U	0.00145 U	0.00310 U
	MW-329-40	09/12/19	PES	PACE	40	-10.7	S	0.0157 U	0.00131 U	0.00746 U	0.000431 U	0.00106 U	0.0123 U	0.000364 U	0.00818 U	0.00385 U	0.00473 U	0.00145 U	0.00312 U
	MW-329-45	09/12/19	PES	PACE	45	-15.7	S	0.0151 U	0.00126 U	0.00722 U	0.000417 U	0.00103 U	0.0119 U	0.000352 U	0.00792 U	0.00372 U	0.00458 U	0.00141 U	0.00302 U
	MW-329-50	09/12/19	PES	PACE	50	-20.7	S	0.0157 U	0.00131 U	0.00746 U	0.000431 U	0.00106 U	0.0123 U	0.000364 U	0.00818 U	0.00385 U	0.00473 U	0.00145 U	0.00312 U
	MW-2003-50	09/12/19	PES	PACE	50 (dup)	-20.7	S	0.0139 U	0.00116 UJ	0.00661 U	0.000382 U	0.000943 U	0.0109 U	0.000322 U	0.00725 U	0.00341 U	0.00419 U	0.00129 U	0.00276 U
	MW-329-55	09/12/19	PES	PACE	55	-25.7	S	0.0147 U	0.00122 U	0.00698 U	0.000404 U	0.000996 U	0.0115 U	0.000341 U	0.00766 U	0.00360 U	0.00443 U	0.00136 U	0.00292 U
	MW-329-60	09/12/19	PES	PACE	60	-30.7	S	0.0149 U	0.00124 U	0.00708 U	0.000409 U	0.00101 U	0.0117 U	0.000345 U	0.00777 U	0.00365 U	0.00449 U	0.00138 U	0.00296 U
	MW-329-65	09/12/19	PES	PACE	65	-35.7	S	0.0148 U	0.00124 U	0.00707 U	0.000409 U	0.00101 U	0.0117 U	0.000345 U	0.00776 U	0.00365 U	0.00449 U	0.00138 U	0.00296 U
	MW-329-70	09/12/19	PES	PACE	70	-40.7	S	0.0148 U	0.00124 U	0.00705 U	0.000408 U	0.00101 U	0.0117 U	0.000344 U	0.00774 U	0.00364 U	0.00448 U	0.00138 U	0.00295 U
	MW-329-75	09/12/19	PES	PACE	75	-45.7	S	0.0146 U	0.00121 U	0.00693 U	0.000401 U	0.000989 U	0.0115 U	0.000338 U	0.00761 U	0.00357 U	0.00440 U	0.00135 U	0.00290 U
	MW-329-80	09/12/19	PES	PACE	80	-50.7	S	0.0154 U	0.00129 UJ	0.00735 U	0.000425 U	0.00105 U	0.0121 U	0.000358 U	0.00807 U	0.00379 U	0.00466 U	0.00143 U	0.00307 U
	MW-329-85	09/12/19	PES	PACE	85	-55.7	S	0.0148 U	0.00124 U	0.00707 U	0.000409 U	0.00101 U	0.0117 U	0.000345 U	0.00776 U	0.00365 U	0.00449 U	0.00138 U	0.00296 U
	MW-329-90	09/12/19	PES	PACE	90	-60.7	S	0.0149 U	**0.00290 J**	0.00711 U	0.000412 U	0.00101 U	0.0118 U	0.000347 U	0.00781 U	0.00367 U	0.00451 U	0.00139 U	0.00297 U
	MW-329-95	09/12/19	PES	PACE	95	-65.7	S	0.0151 U	0.00126 U	0.00718 U	0.000416 U	0.00102 U	0.0119 U	0.000350 U	0.00788 U	0.00370 U	0.00456 U	0.00140 U	0.00300 U
	MW-329-100	09/12/19	PES	PACE	100	-70.7	S	0.0151 U	0.00126 U	0.00720 U	0.000417 U	0.00103 U	0.0119 U	0.000351 U	0.00791 U	0.00371 U	0.00457 U	0.00140 U	0.00301 U
	MW-329-105	09/12/19	PES	PACE	105	-75.7	S	0.0140 U	0.00117 U	0.00666 U	0.000385 U	0.000950 U	0.0110 U	0.000325 U	0.00731 U	0.00343 U	0.00423 U	0.00130 U	0.00279 U
	MW-329-110	09/12/19	PES	PACE	110	-80.7	S	0.0139 U	0.00116 U	0.00661 U	0.000382 U	0.000943 U	0.0109 U	0.000322 U	0.00725 U	0.00341 U	0.00420 U	0.00129 U	0.00276 U
MW-330	MW-330-6	04/20/20	PES	PACE	6	46.0	V	0.00681 UJ	0.00257 U	0.00264 U	0.000466 U	0.000483 U	0.00259 U	0.000398 U	0.00754 U	0.00554 UJ	0.00596 U	0.00108 U	0.00327 U
	MW-330-10	04/20/20	PES	PACE	10	42.0	V	0.00662 UJ	0.00249 U	0.00256 U	0.000452 U	0.000469 U	0.00252 U	0.000386 U	0.00733 U	0.00538 UJ	0.00579 U	0.00105 U	0.00318 U
	MW-330-11.5	04/20/20	PES	PACE	11.5	40.5	V	0.00700 UJ	0.00263 U	0.00270 U	0.000478 U	0.000495 U	0.00266 U	0.000408 U	0.00774 U	0.00569 UJ	0.00612 U	0.00111 U	0.00336 U
	MW-330-16	04/20/20	PES	PACE	16	36.0	V	0.00682 UJ	0.00257 U	0.00264 U	0.000466 U	0.000483 U	0.00259 U	0.000398 U	0.00754 U	0.00554 UJ	0.00596 U	0.00108 U	0.00327 U
	MW-330-21.5	04/20/20	PES	PACE	21.5	30.5	S	0.00639 UJ	0.00241 U	0.00247 U	0.000437 U	0.000453 U	0.00243 U	0.000373 U	0.00707 U	0.00520 UJ	0.00559 U	0.00101 U	0.00307 U
	MW-330-27	04/20/20	PES	PACE	27	25.0	S	0.00645 UJ	0.00243 U	0.00249 U	0.000441 U	0.000457 U	0.00245 U	0.000376 U	0.00714 U	0.00525 UJ	0.00564 U	0.00102 U	0.00310 U
	MW-330-32	04/20/20	PES	PACE	32	20.0	S	0.00646 UJ	0.00243 U	0.00250 U	0.000442 U	0.000458 U	0.00246 U	0.000377 U	0.00715 U	0.00526 UJ	0.00565 U	0.00102 U	0.00310 U
	MW-330-38	04/20/20	PES	PACE	38	14.0	S	0.00646 UJ	0.00243 U	0.00250 U	0.000441 U	0.000457 U	0.00245 U	0.000377 U	0.00714 U	0.00525 UJ	0.00565 U	0.00102 U	0.00310 U
	MW-330-42	04/20/20	PES	PACE	42	10.0	S	0.00628 UJ	0.00237 U	0.00243 U	0.000429 U	0.000445 U	0.00239 U	0.000366 U	0.00695 U	0.00511 UJ	0.00550 U	0.000995 U	0.00302 U
	MW-330-47	04/20/20	PES	PACE	47	5.0	S	0.00679 UJ	0.00256 U	0.00263 U	0.000464 U	0.000481 U	0.00258 U	0.000396 U	0.00752 U	0.00552 UJ	0.00594 U	0.00108 U	0.00326 U
	MW-330-52	04/20/20	PES	PACE	52	0.0	S	0.00659 UJ	0.00248 U	0.00255 U	0.000450 U	0.000467 U	0.00250 U	0.000384 U	0.00729 U	0.00536 UJ	0.00576 U	0.00104 U	0.00316 U
	MW-330-58	04/20/20	PES	PACE	58	-6.0	S	0.00653 UJ	0.00246 U	0.00252 U	0.000446 U	0.000462 U	0.00248 U	0.000381 U	0.00722 U	0.00531 UJ	0.00571 U	0.00103 U	0.00313 U
	MW-330-62	04/20/20	PES	PACE	62	-10.0	S	0.00659 UJ	0.00248 U	0.00255 U	0.000450 U	0.000467 U	0.00250 U	0.000384 U	0.00729 U	0.00536 UJ	0.00577 U	0.00104 U	0.00316 U
MW-331	MW-331-7	04/17/20	PES	PACE	7	24.2	V	0.00926 U	**0.889 J**	0.00358 U	0.000633 U	**0.0281**	0.00352 U	0.000540 U	0.0103 U	**0.0141 J**	0.00811 U	**0.0426**	**0.0205**
	MW-331-11	04/17/20	PES	PACE	11	20.2	S	0.0538 UJ	**3.06**	0.0208 U	0.00367 U	**4.94**	0.0204 U	0.00314 U	0.0595 U	**0.578**	**5.35**	**21.2**	**1.93**
	MW-331-16	04/17/20	PES	PACE	16	15.2	S	0.00708 UJ	**0.0879**	0.00274 U	0.000484 U	**0.137**	0.00269 U	0.000413 U	0.00784 U	**0.0284**	**0.0648**	**0.853**	**0.0335**
	MW-331-20	04/17/20	PES	PACE	20	11.2	S	0.00693 UJ	**0.0168**	0.00268 U	0.000474 U	**0.0417**	0.00263 U	0.000404 U	0.00767 U	0.00564 U	0.00607 U	**0.0704**	0.00333 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	–	–	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	–	–	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
MW-331 (continued)	MW-331-29.5	04/17/20	PES	PACE	29.5	1.7	S	0.00695 UJ	0.00262 U	0.00269 U	0.000475 U	**0.00654**	0.00264 U	0.000406 U	0.00770 U	0.00566 U	0.00608 U	**0.00563 J**	0.00334 U
	MW-331-35	04/17/20	PES	PACE	35	-3.8	S	0.00709 UJ	0.00267 U	0.00274 U	0.000484 U	0.000502 U	0.00269 U	0.000413 U	0.00784 U	0.00576 U	0.00620 U	0.00112 U	0.00340 U
	MW-2018-35	04/17/20	PES	PACE	35 (dup)	-3.8	S	0.00721 UJ	0.00272 U	0.00279 U	0.000493 U	0.000511 U	0.00274 U	0.000421 U	0.00798 U	0.00586 U	0.00631 U	0.00114 U	0.00346 U
	MW-331-40	04/17/20	PES	PACE	40	-8.8	S	0.00724 UJ	0.00273 U	0.00280 U	0.000495 U	0.000513 U	0.00275 U	0.000422 U	0.00801 U	0.00589 U	0.00633 U	**0.00200 J**	0.00347 U
	MW-331-45	04/17/20	PES	PACE	45	-13.8	S	0.00721 UJ	0.00272 U	0.00279 U	0.000493 U	0.000511 U	0.00274 U	0.000421 U	0.00798 U	0.00587 U	0.00631 U	0.00114 U	0.00346 U
MW-332	MW-332-7	04/17/20	PES	PACE	7	29.3	V	0.00673 U	0.00253 U	0.00260 U	0.000460 U	0.000477 U	0.00256 U	0.000392 U	0.00745 U	0.00547 U	0.00589 U	0.00107 U	0.00323 U
	MW-332-11	04/17/20	PES	PACE	11	25.3	V	0.00707 U	**0.0204 J**	0.00273 U	0.000483 U	0.000501 U	0.00269 U	0.000412 U	0.00782 U	0.00575 U	0.00618 U	**0.00112 J**	0.00339 U
	MW-332-16	04/17/20	PES	PACE	16	20.3	S	0.00692 U	0.00261 U	0.00268 U	0.000473 U	0.000490 U	0.00263 U	0.000404 U	0.00766 U	0.00563 U	0.00606 U	0.00110 U	0.00332 U
	MW-332-20	04/17/20	PES	PACE	20	16.3	S	0.00703 U	0.00265 U	0.00272 U	0.000480 U	0.000498 U	0.00267 U	0.000410 U	0.00778 U	0.00572 U	0.00615 U	0.00111 U	0.00338 U
	MW-332-25	04/17/20	PES	PACE	25	11.3	S	0.00728 U	0.00274 U	0.00282 U	0.000498 U	0.000516 U	0.00277 U	0.000425 U	0.00806 U	0.00592 U	0.00637 U	0.00115 U	0.00349 U
	MW-332-30	04/17/20	PES	PACE	30	6.3	S	0.00744 U	0.00280 U	0.00288 U	0.000508 U	0.000527 U	0.00283 U	0.000434 U	0.00823 U	0.00605 U	0.00651 U	0.00118 U	0.00357 U
MW-334	MW-334-6	04/16/20	PES	PACE	6	25.4	V	0.00729 U	0.00275 U	0.00282 U	0.000498 U	0.000516 U	0.00277 U	0.000425 U	0.00807 U	**0.00952 J**	0.00638 U	**0.00121 J**	0.00350 U
	MW-334-10	04/16/20	PES	PACE	10	21.4	V	0.00730 U	0.00275 U	0.00282 U	0.000499 U	**0.00730**	0.00277 U	0.000426 U	0.00808 U	0.00593 U	0.00638 U	**0.0135**	**0.00666 J**
	MW-334-13	04/16/20	PES	PACE	13	18.4	S	0.0540 U	**0.0312 J**	0.0209 U	0.00369 U	**0.294**	0.0205 U	0.00315 U	0.0598 U	0.0439 U	**1.02**	**0.934**	**0.665**
	MW-334-17	04/16/20	PES	PACE	17	14.4	S	0.00620 U	0.00234 U	0.00240 U	0.000424 U	**0.00207 J**	0.00236 U	0.000362 U	0.00686 U	**0.0113 J**	**0.00543 J**	**0.00433 J**	**0.00442 J**
	MW-334-23	04/16/20	PES	PACE	23	8.4	S	0.00714 U	0.00269 U	0.00276 U	0.000488 U	0.000506 U	0.00271 U	0.000417 U	0.00790 U	**0.00793 J**	0.00625 U	0.00113 U	0.00343 U
	MW-334-28	04/16/20	PES	PACE	28	3.4	S	0.00707 U	0.00266 U	0.00273 U	0.000483 U	0.000501 U	0.00269 U	0.000412 U	0.00782 U	0.00575 U	0.00618 U	0.00112 U	0.00339 U
	MW-334-35	04/16/20	PES	PACE	35	-3.6	S	0.00758 U	0.00286 U	0.00293 U	0.000518 U	0.000537 U	0.00288 U	0.000442 U	0.00839 U	0.00617 U	0.00664 U	0.00120 U	0.00364 U
	MW-334-40	04/16/20	PES	PACE	40	-8.6	S	0.00775 U	0.00292 U	0.00300 U	0.000530 U	0.000549 U	0.00294 U	0.000452 U	0.00858 U	0.00630 U	0.00678 U	0.00123 U	0.00372 U
	MW-334-45.5	04/16/20	PES	PACE	45.5	-14.1	S	0.00730 U	0.00275 U	0.00282 U	0.000499 U	0.000517 U	0.00277 U	0.000426 U	0.00808 U	0.00594 U	0.00639 U	0.00116 U	0.00350 U
	MW-334-50	04/16/20	PES	PACE	50	-18.6	S	0.00664 U	0.00250 U	0.00257 U	0.000454 U	0.000470 U	0.00252 U	0.000387 U	0.00735 U	0.00540 U	0.00581 U	0.00105 U	0.00319 U
	MW-334-54.5	04/16/20	PES	PACE	54.5	-23.1	S	0.00742 U	0.00280 U	0.00287 U	0.000507 U	0.000526 U	0.00282 U	0.000433 U	0.00822 U	0.00604 U	0.00650 U	0.00118 U	0.00356 U
	MW-334-60	04/16/20	PES	PACE	60	-28.6	S	0.00683 U	0.00257 U	0.00264 U	0.000467 U	0.000484 U	0.00260 U	0.000399 U	0.00756 U	0.00556 U	0.00598 U	0.00108 U	0.00328 U
	MW-334-63	04/16/20	PES	PACE	63	-31.6	S	0.00718 U	0.00270 U	0.00277 U	0.000490 U	0.000508 U	0.00273 U	0.000419 U	0.00794 U	0.00584 U	0.00628 U	0.00114 U	0.00344 U
MW-336	MW-336-7	04/22/20	PES	PACE	7	26.7	V	0.00669 UJ	0.00252 U	0.00259 U	0.000457 U	0.000474 U	0.00254 U	0.000390 U	0.00741 U	0.00544 UJ	0.00586 U	0.00106 U	0.00321 U
	MW-336-11.5	04/22/20	PES	PACE	11.5	22.2	V	0.00714 UJ	0.00269 U	0.00276 U	0.000488 U	0.000506 U	0.00271 U	0.000417 U	0.00791 U	0.00581 UJ	0.00625 U	0.00113 U	0.00343 U
	MW-2019-11.5	04/22/20	PES	PACE	11.5 (dup)	22.2	V	0.00732 UJ	**0.00294 J**	0.00283 U	0.000500 U	**0.000665 J**	0.00278 U	0.000427 U	0.00810 U	0.00595 U	**0.0119 J**	0.00116 U	**0.00480 J**
	MW-336-14.5	04/22/20	PES	PACE	14.5	19.2	V	0.00769 UJ	0.00290 U	0.00297 U	0.000526 U	0.000545 U	0.00292 U	0.000449 U	0.00851 U	0.00625 UJ	0.00673 U	0.00122 U	0.00369 U
	MW-336-20	04/22/20	PES	PACE	20	13.7	S	0.00735 UJ	0.00277 U	0.00284 U	0.000502 U	0.000520 U	0.00279 U	0.000429 U	0.00813 U	0.00598 UJ	0.00643 U	0.00116 U	0.00353 U
	MW-336-25	04/22/20	PES	PACE	25	8.7	S	0.00988 UJ	0.00372 U	0.00382 U	0.000675 U	0.000700 U	0.00375 U	0.000576 U	0.0109 U	0.00803 UJ	0.00864 U	0.00156 U	0.00474 U
	MW-336-30	04/22/20	PES	PACE	30	3.7	S	0.00914 UJ	0.00344 U	0.00353 U	0.000624 U	0.000647 U	0.00347 U	0.000533 U	0.0101 U	0.00743 UJ	0.00799 U	0.00145 U	0.00439 U
	MW-336-35	04/22/20	PES	PACE	35	-1.3	S	0.00736 UJ	0.00277 U	0.00285 U	0.000503 U	0.000521 U	0.00280 U	0.000429 U	0.00815 U	0.00599 UJ	0.00644 U	0.00117 U	0.00353 U
	MW-336-40	04/22/20	PES	PACE	40	-6.3	S	0.00723 UJ	0.00272 U	0.00280 U	0.000494 U	0.000512 U	0.00275 U	0.000422 U	0.00801 U	0.00588 U	0.00633 U	0.00115 U	0.00347 U
	MW-336-45	04/22/20	PES	PACE	45	-11.3	S	0.00797 UJ	0.00300 U	0.00308 U	0.000545 U	0.000564 U	0.00303 U	0.000465 U	0.00882 U	0.00648 U	0.00697 U	0.00126 U	0.00382 U
	MW-336-51	04/22/20	PES	PACE	51	-17.3	S	0.00691 UJ	0.00260 U	0.00267 U	0.000472 U	0.000489 U	0.00262 U	0.000403 U	0.00764 U	0.00562 U	0.00604 U	0.00109 U	0.00332 U
	MW-336-55	04/22/20	PES	PACE	55	-21.3	S	0.00685 UJ	0.00258 U	0.00265 U	0.000468 U	0.000485 U	0.00260 U	0.000400 U	0.00758 U	0.00557 U	0.00600 U	0.00109 U	0.00329 U
	MW-336-60	04/22/20	PES	PACE	60	-26.3	S	0.00704 UJ	0.00265 U	0.00272 U	0.000481 U	0.000499 U	0.00268 U	0.000411 U	0.00779 U	0.00573 U	0.00616 U	0.00111 U	0.00338 U
	MW-336-65	04/22/20	PES	PACE	65	-31.3	S	0.00700 UJ	0.00264 U	0.00271 U	0.000478 U	0.000496 U	0.00266 U	0.000408 U	0.00775 U	0.00569 U	0.00612 U	0.00111 U	0.00336 U
	MW-336-69	04/22/20	PES	PACE	69	-35.3	S	0.00746 UJ	0.00281 U	0.00288 U	0.000510 U	0.000528 U	0.00283 U	0.000435 U	0.00825 U	0.00607 U	0.00653 U	0.00118 U	0.00358 U
	MW-336-74.5	04/22/20	PES	PACE	74.5	-40.8	S	0.00698 UJ	0.00263 U	0.00270 U	0.000477 U	0.000495 U	0.00265 U	0.000407 U	0.00773 U	0.00568 U	0.00611 U	0.00111 U	0.00335 U
	MW-336-79	04/22/20	PES	PACE	79	-45.3	S	0.00720 UJ	0.00271 U	0.00278 U	0.000492 U	0.000510 U	0.00274 U	0.000420 U	0.00797 U	0.00586 U	0.00630 U	0.00114 U	0.00346 U
	MW-336-85	04/22/20	PES	PACE	85	-51.3	S	0.00721 UJ	0.00272 U	0.00279 U	0.000493 U	0.000511 U	0.00274 U	0.000421 U	0.00798 U	0.00586 U	0.00631 U	0.00114 U	0.00346 U
	MW-2021-85	05/04/20	PES	PACE	85 (dup)	-51.3	S	0.00691 U	0.00260 U	0.00267 U	0.000472 U	0.000489 U	0.00262 U	0.000403 U	0.00764 U	0.00562 U	0.00604 U	0.00109 U	0.00332 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	–	–	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	–	–	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
MW-336 (continued)	MW-336-90	04/22/20	PES	PACE	90	-56.3	S	0.00723 UJ	0.00272 U	0.00280 U	0.000494 U	0.000512 U	0.00275 U	0.000422 U	0.00801 U	0.00588 U	0.00633 U	0.00115 U	0.00347 U
	MW-336-95	04/22/20	PES	PACE	95	-61.3	S	0.00721 UJ	0.00272 U	0.00279 U	0.000493 U	0.000511 U	0.00274 U	0.000421 U	0.00798 U	0.00586 U	0.00631 U	0.00114 U	0.00346 U
	MW-2020-95	04/22/20	PES	PACE	95 (dup)	-61.3	S	0.00714 UJ	0.00269 U	0.00276 U	0.000488 U	0.000506 U	0.00272 U	0.000417 U	0.00791 U	0.00581 U	0.00625 U	0.00113 U	0.00343 U
MW-338	MW-338-10	05/01/20	PES	PACE	10	17.8	S	0.00728 U	0.00274 U	0.00281 U	0.000497 U	0.000515 U	0.00277 U	0.000424 U	0.00805 U	0.00592 U	0.00637 U	0.00115 U	0.00349 U
	MW-338-15	05/01/20	PES	PACE	15	12.8	S	0.00793 U	0.00299 U	0.00307 U	0.000542 U	0.000562 U	0.00302 U	0.000463 U	0.00878 U	0.00645 U	0.00694 U	0.00126 U	0.00381 U
	MW-338-20	05/01/20	PES	PACE	20	7.8	S	0.00695 U	0.00262 U	0.00269 U	0.000475 U	0.000493 U	0.00264 U	0.000406 U	0.00770 U	0.00566 U	0.00608 U	0.00110 U	0.00334 U
	MW-338-23	05/01/20	PES	PACE	23	4.8	S	0.00762 U	0.00287 U	0.00295 U	0.000521 U	0.000540 U	0.00290 U	0.000445 U	0.00844 U	0.00620 U	0.00667 U	0.00121 U	0.00366 U
	MW-338-28	05/01/20	PES	PACE	28	-0.2	S	0.00755 U	0.00284 U	0.00292 U	0.000516 U	0.000534 U	0.00287 U	0.000440 U	0.00835 U	0.00614 U	0.00660 U	0.00119 U	0.00362 U
	MW-338-34	05/01/20	PES	PACE	34	-6.2	S	0.00671 U	0.00253 U	0.00259 U	0.000458 U	0.000475 U	0.00255 U	0.000391 U	0.00742 U	0.00545 U	0.00587 U	0.00106 U	0.00322 U
	MW-338-39	05/01/20	PES	PACE	39	-11.2	S	0.00727 U	0.00274 U	0.00281 U	0.000497 U	0.000515 U	0.00276 U	0.000424 U	0.00804 U	0.00591 U	0.00636 U	0.00115 U	0.00349 U
	MW-338-41	05/01/20	PES	PACE	41	-13.2	S	0.00740 U	0.00279 U	0.00286 U	0.000505 U	0.000524 U	0.00281 U	0.000431 U	0.00819 U	0.00602 U	0.00647 U	0.00117 U	0.00355 U
	MW-338-45	05/01/20	PES	PACE	45	-17.2	S	0.00732 U	0.00276 U	0.00283 U	0.000500 U	0.000519 U	0.00278 U	0.000427 U	0.00811 U	0.00596 U	0.00641 U	0.00116 U	0.00352 U
	MW-338-51	05/01/20	PES	PACE	51	-23.2	S	0.00744 U	0.00280 U	0.00288 U	0.000508 U	0.000527 U	0.00283 U	0.000434 U	0.00823 U	0.00605 U	0.00651 U	0.00118 U	0.00357 U
	MW-338-55	05/01/20	PES	PACE	55	-27.2	S	0.00689 U	0.00259 U	0.00266 U	0.000471 U	0.000488 U	0.00262 U	0.000402 U	0.00762 U	0.00560 U	0.00603 U	0.00109 U	0.00331 U
MW-341	MW-341-85	05/04/20	PES	PACE	85	-56.6	S	0.00682 U	0.00257 U	0.00264 U	0.000466 U	0.000483 U	0.00259 U	0.000398 U	0.00754 U	0.00554 U	0.00596 U	0.00108 U	0.00327 U
	MW-341-90	05/04/20	PES	PACE	90	-61.6	S	0.00675 U	0.00254 U	0.00261 U	0.000461 U	0.000478 U	0.00256 U	0.000394 U	0.00747 U	0.00549 U	0.00591 U	0.00107 U	0.00324 U
	MW-341-95	05/04/20	PES	PACE	95	-66.6	S	0.00699 U	0.00263 U	0.00270 U	0.000478 U	0.000495 U	0.00266 U	0.000408 U	0.00774 U	0.00569 U	0.00612 U	0.00111 U	0.00336 U
	MW-341-99	05/04/20	PES	PACE	99	-70.6	S	0.00703 U	0.00265 U	0.00272 U	0.000481 U	0.000498 U	0.00267 U	0.000410 U	0.00778 U	0.00572 U	0.00616 U	0.00111 U	0.00338 U
	MW-341-104	05/04/20	PES	PACE	104	-75.6	S	0.00716 U	0.00270 U	0.00277 U	0.000489 U	0.000507 U	0.00272 U	0.000417 U	0.00792 U	0.00582 U	0.00626 U	0.00113 U	0.00344 U
MW-343	MW-343-5	04/13/20	PES	PACE	5	22.6	V	0.00678 U	**0.0198**	0.00262 U	0.000463 U	**0.00181 J**	0.00258 U	0.000395 U	0.00750 U	0.00551 U	0.00593 U	0.00107 U	0.00325 U
	MW-343-10	04/13/20	PES	PACE	10	17.6	S	0.00710 U	**0.0152**	0.00275 U	0.000485 U	**0.00136 J**	0.00270 U	0.000414 U	0.00786 U	**0.00772 J**	0.00622 U	0.00112 U	0.00341 U
	MW-343-12.5	04/13/20	PES	PACE	12.5	15.1	S	0.00736 U	0.00277 U	0.00285 U	0.000503 U	0.000521 U	0.00280 U	0.000429 U	0.00815 U	0.00599 U	0.00644 U	0.00117 U	0.00353 U
	MW-343-17	04/13/20	PES	PACE	17	10.6	S	0.00690 U	0.00260 U	0.00267 U	0.000472 U	0.000489 U	0.00262 U	0.000403 U	0.00764 U	**0.00810 J**	0.00604 U	0.00109 U	0.00331 U
	MW-343-24	04/13/20	PES	PACE	24	3.6	S	0.00692 U	0.00261 U	0.00268 U	0.000473 U	**0.000965 J**	0.00263 U	0.000404 U	0.00766 U	**0.0156**	0.00605 U	0.00110 U	0.00332 U
	MW-343-28.5	04/13/20	PES	PACE	28.5	-0.9	S	0.00742 U	0.00280 U	0.00287 U	0.000507 U	**0.000898 J**	0.00282 U	0.000433 U	0.00821 U	**0.0117 J**	0.00649 U	0.00118 U	0.00356 U
	MW-343-35	04/13/20	PES	PACE	35	-7.4	S	0.00751 U	0.00283 U	0.00290 U	0.000513 U	0.000532 U	0.00285 U	0.000438 U	0.00831 U	0.00611 U	0.00657 U	0.00119 U	0.00360 U
	MW-343-38	04/13/20	PES	PACE	38	-10.4	S	0.00702 U	0.00264 U	0.00271 U	0.000480 U	0.000497 U	0.00267 U	0.000409 U	0.00777 U	0.00571 U	0.00614 U	0.00111 U	0.00337 U
	MW-343-44	04/13/20	PES	PACE	44	-16.4	S	0.00661 U	0.00249 U	0.00256 U	0.000452 U	0.000468 U	0.00251 U	0.000386 U	0.00732 U	0.00538 U	0.00579 U	0.00105 U	0.00317 U
	MW-343-47	04/13/20	PES	PACE	47	-19.4	S	0.00747 U	0.00281 U	0.00289 U	0.000510 U	0.000529 U	0.00284 U	0.000436 U	0.00827 U	0.00607 U	0.00654 U	0.00118 U	0.00359 U
	MW-343-51	04/13/20	PES	PACE	51	-23.4	S	0.00668 U	0.00251 U	0.00258 U	0.000456 U	0.000473 U	0.00254 U	0.000389 U	0.00739 U	0.00543 U	0.00584 U	0.00106 U	0.00320 U
	MW-343-55	04/13/20	PES	PACE	55	-27.4	S	0.00682 U	0.00257 U	0.00264 U	0.000466 U	0.000483 U	0.00259 U	0.000398 U	0.00755 U	0.00555 U	0.00597 U	0.00108 U	0.00327 U
	MW-343-62	04/13/20	PES	PACE	62	-34.4	S	0.00694 U	0.00262 U	0.00268 U	0.000474 U	0.000492 U	0.00264 U	0.000405 U	0.00768 U	0.00565 U	0.00608 U	0.00110 U	0.00333 U
	MW-343-68	04/13/20	PES	PACE	68	-40.4	S	0.00684 U	0.00258 U	0.00264 U	0.000467 U	0.000485 U	0.00260 U	0.000399 U	0.00757 U	0.00556 U	0.00599 U	0.00108 U	0.00328 U
	MW-343-73	04/13/20	PES	PACE	73	-45.4	S	0.00691 U	0.00260 U	0.00267 U	0.000472 U	0.000490 U	0.00263 U	0.000403 U	0.00765 U	0.00562 U	0.00605 U	0.00109 U	0.00332 U
	MW-343-79	04/13/20	PES	PACE	79	-51.4	S	0.00650 U	0.00245 U	0.00251 U	0.000444 U	0.000460 U	0.00247 U	0.000379 U	0.00719 U	0.00528 U	0.00569 U	0.00103 U	0.00312 U
	MW-343-82	04/13/20	PES	PACE	82	-54.4	S	0.00652 U	0.00245 U	0.00252 U	0.000445 U	0.000461 U	0.00248 U	0.000380 U	0.00721 U	0.00530 U	0.00570 U	0.00103 U	0.00313 U
	MW-343-86	04/13/20	PES	PACE	86	-58.4	S	0.00636 U	0.00239 U	0.00246 U	0.000434 U	0.000450 U	0.00241 U	0.000371 U	0.00703 U	0.00517 U	0.00556 U	0.00101 U	0.00305 U
	MW-343-93	04/13/20	PES	PACE	93	-65.4	S	0.00672 U	0.00253 U	0.00260 U	0.000459 U	0.000476 U	0.00255 U	0.000392 U	0.00744 U	0.00547 U	0.00588 U	0.00106 U	0.00323 U
	MW-343-99	04/13/20	PES	PACE	99	-71.4	S	0.00644 U	0.00243 U	0.00249 U	0.000440 U	0.000456 U	0.00245 U	0.000376 U	0.00713 U	0.00524 U	0.00564 U	0.00102 U	0.00309 U
	MW-343-102	04/14/20	PES	PACE	102	-74.4	S	0.00662 U	0.00249 U	0.00256 U	0.000452 U	0.000469 U	0.00252 U	0.000386 U	0.00732 U	0.00538 UJ	0.00579 U	0.00105 U	0.00318 U
	MW-2017-102	04/14/20	PES	PACE	102 (dup)	-74.4	S	0.00655 U	**0.00452 J**	0.00253 U	0.000448 U	0.000464 U	0.00249 U	0.000382 U	0.00725 U	0.00533 UJ	0.00573 U	0.00104 U	0.00314 U
	MW-343-106	04/14/20	PES	PACE	106	-78.4	S	0.00643 U	**0.0163**	0.00249 U	0.000440 U	0.000456 U	0.00244 U	0.000375 U	0.00712 U	0.00523 UJ	0.00563 U	**0.00106 J**	0.00309 U
	MW-343-108	04/14/20	PES	PACE	108	-80.4	S	0.00665 U	**0.00787**	0.00257 U	0.000454 U	0.000471 U	0.00253 U	0.000388 U	0.00736 U	0.00541 UJ	0.00582 U	0.00105 U	0.00319 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
PH22	PH22	04/17/18	PES	Fremont	0-3	–	V	0.0608 U	–	–	–	0.0304 U	–	0.0608 U	0.0243 U	0.0608 U	0.0304 U	0.0304 U	0.0608 U
PH34	PH34	04/17/18	PES	Fremont	1.5-6.5	–	V	0.0481 U	–	–	–	0.0240 U	–	0.0481 U	0.0192 U	0.0481 U	0.0240 U	0.0240 U	0.0481 U
PH38	PH38	04/17/18	PES	Fremont	1.5-4	–	V	0.0583 U	–	–	–	0.0292 U	–	0.0583 U	0.0233 U	0.0583 U	0.0292 U	0.0292 U	0.0583 U
PH52	PH52	04/17/18	PES	Fremont	1-5	–	V	0.0564 U	–	–	–	0.0282 U	–	0.0564 U	0.0226 U	0.0564 U	0.0282 U	0.0282 U	0.0564 U
PW-1	Composite	01/01/98	B&V	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
PW-4	Composite	05/13/98	B&V	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
R-MW4	Unknown	10/22/92	Roux	Unknown	5	35.9	V	–	–	–	–	–	–	–	–	–	–	–	–
	Unknown	10/22/92	Roux	Unknown	15	25.9	S	–	–	–	–	–	–	–	–	–	–	–	–
	Unknown	10/22/92	Roux	Unknown	30	10.9	S	–	–	–	–	–	–	–	–	–	–	–	–
R-MW6 (33.3 to 23.3)	Unknown	10/27/92	Roux	Unknown	6	39.3	V	–	–	–	–	–	–	–	–	–	–	–	–
	Unknown	10/27/92	Roux	Unknown	11	34.3	V	–	–	–	–	–	–	–	–	–	–	–	–
	Unknown	10/27/92	Roux	Unknown	16	29.3	S	–	–	–	–	–	–	–	–	–	–	–	–
RB1	RB1-17.5	10/18/93	Retec	AAL	17.5	18.4	S	–	–	–	–	–	–	–	–	–	–	–	–
RB2	RB2-12.5	10/18/93	Retec	AAL	12.5	23.6	V	–	–	–	–	–	–	–	–	–	–	–	–
	RB2-17.5	10/18/93	Retec	AAL	17.5	18.6	S	–	–	–	–	–	–	–	–	–	–	–	–
RB3	RB3-17.5	10/18/93	Retec	AAL	17.5	20.5	S	–	–	–	–	–	–	–	–	–	–	–	–
SCL-B100	B-100, S1	06/10/02	Urban	F&BI	5-6.5	–	V	–	–	–	–	–	–	–	–	–	–	–	–
	B-100, S2	06/10/02	Urban	F&BI	10-11.5	–	V	–	–	–	–	–	–	–	–	–	–	–	–
SCL-B101	B-101- S1&2	06/17/02	Urban	F&BI	0-6	–	V	–	–	–	–	–	–	–	–	–	–	–	–
	B101-S3	06/17/02	Urban	F&BI	8	–	V	–	–	–	–	–	–	–	–	–	–	–	–
SCL-B102	B102-S1	06/17/02	Urban	F&BI	0-3	–	V	–	–	–	–	–	–	–	–	–	–	–	–
	B102-S2	06/17/02	Urban	F&BI	4	–	V	–	–	–	–	–	–	–	–	–	–	–	–
SCL-MW101 (25.0 to 15.0)	MW101-S3	06/14/02	Urban	F&BI	16	–	S	–	–	–	–	–	–	–	–	–	–	–	–
SCL-MW102	MW-102, S1	06/10/02	Urban	F&BI	5-6.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–
	MW-102, S2	06/10/02	Urban	F&BI	5-6.5, 10-11.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–
SCL-MW103	MW103-S1&S2	06/14/02	Urban	F&BI	5-6.5, 10-11.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–
SCL-MW105 (10.8 to 0.8)	MW-105, S2	06/10/02	Urban	F&BI	10-11.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–
	MW-105, S4	06/10/02	Urban	F&BI	20-21.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–
SCLB-1	RS1-2.5/RS-1 7.5 (Comp)	03/12/93	EPJ	OnSite	2.5-7.5	–	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS1-12.5/RS1-17.5 (Comp)	03/12/93	EPJ	OnSite	12.5-17.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–
	RS-1 17.5	03/12/93	EPJ	OnSite	17.5	21.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	RS1-22.5/RS-27.5 (Comp)	03/12/93	EPJ	OnSite	22.5-27.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–
	RS1-32.5	03/12/93	EPJ	OnSite	32.5	6.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	RS1-37.5	03/12/93	EPJ	OnSite	37.5	1.0	S	–	–	–	–	–	–	–	–	–	–	–	–
SCLB-2	RS2-2.5/RS-2 7.5 (Comp)	03/12/93	EPJ	OnSite	2.5-7.5	–	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS2-12.5/RS2-17.5 (Comp)	03/12/93	EPJ	OnSite	12.5-17.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–
	RS2-17.5	03/12/93	EPJ	OnSite	17.5	21.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	RS2-22.5/RS2-27.5 (Comp)	03/12/93	EPJ	OnSite	22.5-27.5	–	S	–	–	–	–	–	–	–	–	–	–	–	–
	RS2-32.5	03/12/93	EPJ	OnSite	32.5	6.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	RS2-37.5	03/12/93	EPJ	OnSite	37.5	1.0	S	–	–	–	–	–	–	–	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
SSD-MW-1	MW-1 S-2	05/24/89	HC	Unknown	5-6.5	34.0	V	–	–	–	–	–	–	–	–	–	–	–	–
	MW-1 S-6	05/24/89	HC	Unknown	15-16.5	24.0	S	–	–	–	–	–	–	–	–	–	–	–	–
SSD-MW-2	MW-2 S-3	05/24/89	HC	Unknown	7.5-9	31.0	V	–	–	–	–	–	–	–	–	–	–	–	–
	MW-2 S-6	05/24/89	HC	Unknown	15-16.5	31.0	V	–	–	–	–	–	–	–	–	–	–	–	–
SSD-MW-3	MW-3 S-2	05/24/89	HC	Unknown	5-6.5	34.0	V	–	–	–	–	–	–	–	–	–	–	–	–
	MW-3 S-5	05/24/89	HC	Unknown	12.5-14	34.0	V	–	–	–	–	–	–	–	–	–	–	–	–
SSD-MW-4	MW-4 S-6	05/25/89	HC	Unknown	14.5-16	36.8	V	–	–	–	–	–	–	–	–	–	–	–	–
	MW-4 S-9	05/25/89	HC	Unknown	22-23	29.5	S	–	–	–	–	–	–	–	–	–	–	–	–
SV-04	SV-04-6	06/29/20	PES	PACE	6	–	V	0.00778 U	0.00293 U	0.00301 U	0.000531 U	0.000551 U	0.00295 U	0.000454 U	0.00860 U	0.00632 U	0.00680 U	0.00123 U	0.00373 U
SV-05	SV-05-10	06/29/20	PES	PACE	10	–	V	0.00831 U	0.00313 U	0.00321 U	0.000568 U	0.000588 U	0.00316 U	0.000485 U	0.00919 U	0.00676 UJ	0.00727 U	0.00132 U	0.00399 U
SV-06	SV-06-6	06/29/20	PES	PACE	6	–	V	0.00765 U	0.00288 U	0.00296 U	0.000523 U	0.000542 U	0.00291 U	0.000447 U	0.00847 U	0.00623 UJ	0.00670 U	0.00121 U	0.00367 U
SV-07	SV-07-15	06/29/20	PES	PACE	15	–	V	0.00658 U	0.00248 U	0.00254 U	0.000449 U	0.000466 U	0.00250 U	0.000384 U	0.00728 U	0.00535 UJ	0.00575 U	0.00104 U	0.00316 U
SV-08	SV-08-6	06/30/20	PES	PACE	6	–	V	0.00834 U	**0.0112**	0.00323 U	0.000570 U	**0.00106 J**	0.00317 U	0.000487 U	0.00923 U	0.00679 UJ	0.00730 U	**0.00202 J**	0.00400 U
	SV-08-7.5	06/30/20	PES	PACE	7.5	–	V	0.00850 U	**0.00398 J**	0.00329 U	0.000581 U	0.000602 U	0.00323 U	0.000496 U	0.00941 U	0.00692 U	0.00744 U	0.00135 U	0.00408 U
SV-09	SV-09-5.5	07/01/20	PES	PACE	5.5	–	V	0.00794 U	0.00299 U	0.00307 U	0.000543 U	0.000563 U	0.00302 U	0.000463 U	0.00879 U	0.00646 U	0.00695 U	0.00126 U	0.00381 U
SV-10	SV-10-5.5	06/30/20	PES	PACE	5.5	–	V	0.00791 U	0.00298 U	0.00306 U	0.000540 U	0.000560 U	0.00301 U	0.000461 U	0.00875 U	0.00643 U	0.00692 U	0.00125 U	0.00380 U
SV-11	SV-11-10	06/30/20	PES	PACE	10	–	V	0.00802 U	0.00302 U	0.00310 U	0.000548 U	0.000568 U	0.00305 U	0.000468 U	0.00888 U	0.00652 U	0.00702 U	0.00127 U	0.00385 U
SV-12	SV-12-5.5	07/01/20	PES	PACE	5.5	–	V	0.00656 U	**0.00980**	0.00254 U	0.000448 U	0.000465 U	0.00249 U	0.000383 U	0.00726 U	0.00534 U	0.00574 U	0.00104 U	0.00315 U
SV-13	SV-13-10.5	07/01/20	PES	PACE	10.5	–	V	0.00769 U	0.00290 U	0.00298 U	0.000526 U	0.000545 U	0.00292 U	0.000449 U	0.00852 U	0.00626 U	0.00673 U	0.00122 U	0.00369 U
SV-14	SV-14-5.5	07/01/20	PES	PACE	5.5	–	V	0.00802 U	0.00302 U	0.00310 U	0.000548 U	0.000568 U	0.00305 U	0.000468 U	0.00888 U	0.00652 U	0.00702 U	0.00127 U	0.00385 U
SV-15	SV-15-13	07/01/20	PES	PACE	13	–	V	0.00779 U	0.00293 U	0.00301 U	0.000532 U	0.000552 U	0.00296 U	0.000454 U	0.00862 U	0.00633 U	0.00681 U	0.00123 U	0.00374 U
SV-16	SV-16-5	07/02/20	PES	PACE	5	–	V	0.0159 U	**0.0373 J**	0.00615 U	0.00109 U	**0.00843**	0.00605 U	0.000929 U	0.0176 U	**0.0190 J**	0.0139 U	**0.00782 J**	**0.00850 J**
	SV-100-5	07/02/20	PES	PACE	5 (dup)	–	V	0.0143 U	**0.0235 J**	0.00551 U	0.000975 U	**0.00500 J**	0.00542 U	0.000831 U	0.0158 U	**0.0120 J**	0.0125 U	**0.00350 J**	0.00683 U
SV-17	SV-17-4.5	07/02/20	PES	PACE	4.5	–	V	0.0118 U	**0.0539**	0.00456 U	0.000806 U	**0.00654**	0.00448 U	0.000687 U	0.0131 U	**0.0724**	0.0103 U	**0.00906 J**	**0.00606 J**
SV-18	SV-18-5.5	07/02/20	PES	PACE	5.5	–	V	0.00647 U	**0.00345 J**	0.00250 U	0.000442 U	0.000458 U	0.00246 U	0.000377 U	0.00716 U	0.00526 U	0.00566 U	0.00102 U	0.00310 U
SV-19	SV-19-5	07/09/20	PES	PACE	5	–	V	0.00646 U	0.00243 U	0.00250 U	0.000442 U	0.000458 U	0.00246 U	0.000377 U	0.00715 U	0.00526 U	0.00565 U	0.00102 U	0.00310 U
SV-20	SV-20-9	07/09/20	PES	PACE	9	–	V	0.00849 U	0.00320 U	0.00328 U	0.000580 U	0.000602 U	0.00323 U	0.000495 U	0.00940 U	0.00691 U	0.00743 U	0.00134 U	0.00408 U
SV-21	SV-21-6	07/09/20	PES	PACE	6	–	V	0.00658 U	0.00248 U	0.00254 U	0.000449 U	0.000466 U	0.00250 U	0.000384 U	0.00728 U	0.00535 U	0.00575 U	0.00104 U	0.00316 U
SV-22	SV-22-8.5	07/09/20	PES	PACE	8.5	–	V	0.0123 U	0.00516 U	0.00474 U	0.000838 U	0.000869 U	0.00466 U	0.000715 U	0.0136 U	0.00996 U	0.0107 U	0.00195 U	0.00588 U
SV-23	SV-23-4.5	07/09/20	PES	PACE	4.5	–	V	0.00907 U	0.00342 U	0.00351 U	0.000620 U	0.000643 U	0.00345 U	0.000529 U	0.0100 U	0.00738 U	0.00794 U	0.00144 U	0.00435 U
SV-24	SV-24-8	07/09/20	PES	PACE	8	–	V	0.00651 U	0.00245 U	0.00252 U	0.000445 U	0.000461 U	0.00248 U	0.000380 U	0.00721 U	0.00530 U	0.00570 U	0.00103 U	0.00313 U
SV-25	SV-25-4	07/10/20	PES	PACE	4	–	V	0.00790 U	0.00298 U	0.00306 U	0.000540 U	0.000560 U	0.00300 U	0.000461 U	0.00875 U	0.00643 U	0.00691 U	0.00125 U	0.00379 U
SV-26	SV-26-12	07/10/20	PES	PACE	12	–	V	0.00878 U	0.00331 U	0.00340 U	0.000600 U	0.000622 U	0.00334 U	0.000512 U	0.00972 U	0.00714 U	0.00768 U	0.00139 U	0.00422 U
SV-27	SV-27-5.5	07/10/20	PES	PACE	5.5	–	V	0.00787 U	0.00297 U	0.00304 U	0.000538 U	0.000558 U	0.00299 U	0.000459 U	0.00871 U	0.00640 U	0.00689 U	0.00125 U	0.00378 U
	SV-27-13.5	07/10/20	PES	PACE	13.5	–	V	0.00788 U	0.00297 U	0.00305 U	0.000539 U	0.000558 U	0.00300 U	0.000460 U	0.00872 U	0.00641 U	0.00690 U	0.00125 U	0.00378 U
TB-12	16	08/01/97	B&V	Unknown	62-63	-24.5	S	–	–	–	–	–	–	–	–	–	–	–	–
TB-18	S-2	03/17/98	B&V	Unknown	5-6.5	38.3	V	–	–	–	–	–	–	–	–	–	–	–	–
	S-8	03/17/98	B&V	Unknown	20-21.5	23.3	S	–	–	–	–	–	–	–	–	–	–	–	–
	S-21	03/17/98	B&V	Unknown	57.5-59	1.2	S	–	–	–	–	–	–	–	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	–	–	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	–	–	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
T1	T1-2.5-071718	07/17/18	PES	Fremont	2.5	–	V	0.0531 U	–	–	–	0.0265 U	–	0.0531 U	0.0212 U	0.0531 U	0.0265 U	0.0265 U	0.0531 U
T-2	T-2-071618	07/16/18	PES	Fremont	2	–	V	0.0287 U	–	–	–	0.0143 U	–	0.0287 U	0.0115 U	0.0287 U	0.0143 U	0.0143 U	0.0287 U
T-2B	T-2B-071618	07/16/18	PES	Fremont	2	–	V	0.0593 U	–	–	–	0.0297 U	–	0.0593 U	0.0237 U	0.0593 U	0.0297 U	0.0297 U	0.0593 U
T2	T2-6-071718	07/17/18	PES	Fremont	6	–	V	0.0614 U	–	–	–	0.0307 U	–	0.0614 U	0.0245 U	0.0614 U	0.0307 U	0.0307 U	0.0614 U
T3	T3-3-071718	07/17/18	PES	Fremont	3	–	V	0.0573 U	–	–	–	0.0287 U	–	0.0573 U	0.0229 U	0.0573 U	0.0287 U	0.0287 U	0.0573 U
T4	T4-6-071718	07/17/18	PES	Fremont	6	–	V	0.0516 U	–	–	–	0.0258 U	–	0.0516 U	0.0206 U	0.0516 U	0.0258 U	0.0258 U	0.0516 U
T-5	T-5-071618	07/16/18	PES	Fremont	5	–	V	0.0509 U	–	–	–	0.0255 U	–	0.0509 U	0.0204 U	0.0509 U	0.0255 U	0.0255 U	0.0509 U
T6	T6-4-071818	07/18/18	PES	Fremont	4	–	V	0.0474 U	–	–	–	0.0237 U	–	0.0474 U	0.0189 U	0.0474 U	0.0237 U	0.0237 U	0.0474 U
T7	T7-7-071818	07/18/18	PES	Fremont	7	–	V	0.0684 U	–	–	–	0.0342 U	–	0.0684 U	0.0274 U	0.0684 U	0.0342 U	0.0342 U	0.0684 U
T8	T8-3-072018	07/20/18	PES	Fremont	3	–	V	0.0536 U	–	–	–	0.0268 U	–	0.0536 U	0.0214 U	0.0536 U	0.0268 U	0.0268 U	0.0536 U
T8	T8-6-072018	07/20/18	PES	Fremont	6	–	V	0.0753 U	–	–	–	0.0377 U	–	0.0753 U	0.0301 U	0.0753 U	0.0377 U	0.0377 U	0.0753 U
T9	T9-3-072018	07/20/18	PES	Fremont	3	–	V	0.0875 U	–	–	–	0.0437 U	–	0.0875 U	0.0350 U	0.0875 U	0.0437 U	0.0437 U	0.0875 U
T9	T9-3.5-072018	07/20/18	PES	Fremont	3.5	–	V	0.0583 U	–	–	–	0.0291 U	–	0.0583 U	0.0233 U	**0.404**	0.0291 U	0.0291 U	0.0583 U
T9	T9-6-072018	07/20/18	PES	Fremont	6	–	V	0.0605 U	–	–	–	0.0303 U	–	0.0605 U	0.0242 U	0.0605 U	0.0303 U	0.0303 U	0.0605 U
T10	T10-3-072018	07/20/18	PES	Fremont	3	–	V	0.103 U	–	–	–	0.0513 U	–	0.103 U	0.0411 U	0.103 U	0.0513 U	0.0513 U	0.103 U
T10	T10-6-072018	07/20/18	PES	Fremont	6	–	V	0.0556 U	–	–	–	0.0278 U	–	0.0556 U	0.0222 U	0.0556 U	0.0278 U	0.0278 U	0.0556 U
T11	T11-3.5-073118	07/31/18	PES	Fremont	3.5	–	V	0.0716 U	–	–	–	0.0358 U	–	0.0716 U	0.0286 U	0.0716 U	0.0358 U	0.0358 U	0.0716 U
T12	T12-3-091818	09/18/18	PES	Fremont	3	–	V	0.0614 U	–	–	–	0.0307 U	–	0.0614 U	0.0245 U	0.0614 U	0.0307 U	0.0307 U	0.0614 U
T12	T12-7-091818	09/18/18	PES	Fremont	7	–	V	0.0607 U	–	–	–	0.0303 U	–	0.0607 U	0.0243 U	0.0607 U	0.0303 U	0.0303 U	0.0607 U
T12	T12-7.5-073118	07/31/18	PES	Fremont	7.5	–	V	0.0519 U	–	–	–	0.0259 U	–	0.0519 U	0.0207 U	0.0519 U	0.0259 U	0.0259 U	0.0519 U
T13	T13-3.5-091818	09/18/18	PES	Fremont	3.5	–	V	0.0567 U	–	–	–	0.0283 U	–	0.0567 U	0.0227 U	0.0567 U	0.0283 U	0.0283 U	0.0567 U
T13	T13-6.5-091818	09/18/18	PES	Fremont	6.5	–	V	0.0500 U	–	–	–	0.0250 U	–	0.0500 U	0.0200 U	0.0500 U	0.0250 U	0.0250 U	0.0500 U
T14	T14-3.5-091818	09/18/18	PES	Fremont	3.5	–	V	0.0599 U	–	–	–	0.0300 U	–	0.0599 U	0.0240 U	0.0599 U	0.0300 U	0.0300 U	0.0599 U
T14	T14-7-091818	09/18/18	PES	Fremont	7	–	V	0.0635 U	–	–	–	0.0318 U	–	0.0635 U	0.0254 U	0.0635 U	0.0318 U	0.0318 U	0.0635 U
TP-15	TP-15-3-092818	09/28/18	PES	Fremont	3	–	V	0.0609 U	–	–	–	0.0304 U	–	0.0609 U	0.0244 U	0.0609 U	0.0304 U	0.0304 U	0.0609 U
TP-15	TP-15-6.5-092818	09/28/18	PES	Fremont	6.5	–	V	0.0625 U	–	–	–	0.0313 U	–	0.0625 U	0.0250 U	0.0625 U	0.0313 U	0.0313 U	0.0625 U
TP-16	TP-16-3-092818	09/28/18	PES	Fremont	3	–	V	0.0852 U	–	–	–	0.0426 U	–	0.0852 U	0.0341 U	0.0852 U	0.0426 U	0.0426 U	0.0852 U
TP-16	TP-16-6-092818	09/28/18	PES	Fremont	6	–	V	0.0892 U	–	–	–	0.0446 U	–	0.0892 U	0.0357 U	0.0892 U	0.0446 U	0.0446 U	0.0892 U
TP-16	TP-16-9-092818	09/28/18	PES	Fremont	9	–	V	0.0525 U	–	–	–	0.0263 U	–	0.0525 U	0.0210 U	0.0525 U	0.0263 U	0.0263 U	0.0525 U
TP-SD-01	TP-SD-01-2	06/03/19	PES	Fremont	2	–	V	0.0429 U	–	–	–	0.0214 U	–	0.0429 U	0.0172 U	0.0429 U	0.0214 U	0.0214 U	0.0429 U
TP-SD-01	TP-SD-01-5	06/03/19	PES	Fremont	5	–	V	0.0534 U	–	–	–	0.0267 U	–	0.0534 U	0.0213 U	0.0534 U	0.0267 U	0.0267 U	0.0534 U
TP-SD-04	TP-SD-04-2	06/03/19	PES	Fremont	2	–	V	0.0504 U	–	–	–	0.0252 U	–	0.0504 U	0.0202 U	0.0504 U	0.0252 U	0.0252 U	0.0504 U
TP-SD-04	TP-SD-04-5	06/03/19	PES	Fremont	5	–	V	0.0544 U	–	–	–	0.0272 U	–	0.0544 U	0.0218 U	0.0544 U	0.0272 U	0.0272 U	0.0544 U
TP-SD-05	TP-SD-05-2	06/03/19	PES	Fremont	2	–	V	0.0517 U	–	–	–	0.0258 U	–	0.0517 U	0.0207 U	**0.114**	0.0258 U	0.0258 U	0.0517 U
TP-SD-05	TP-SD-05-5	06/03/19	PES	Fremont	5	–	V	0.0585 U	–	–	–	0.0292 U	–	0.0585 U	0.0234 U	**0.0665**	0.0292 U	0.0292 U	0.0585 U
TP-SD-06	TP-SD-06-2	06/03/19	PES	Fremont	2	–	V	0.0688 U	–	–	–	0.0344 U	–	0.0688 U	0.0275 U	0.0688 U	0.0344 U	0.0344 U	0.0688 U
TP-SD-06	TP-SD-06-5	06/03/19	PES	Fremont	5	–	V	0.0544 U	–	–	–	0.0272 U	–	0.0544 U	0.0218 U	0.0544 U	0.0272 U	0.0272 U	0.0544 U
TP-SD-07	TP-SD-07-2	06/03/19	PES	Fremont	2	–	V	0.0435 U	–	–	–	0.0217 U	–	0.0435 U	0.0174 U	0.0435 U	0.0217 U	0.0217 U	0.0435 U
TP-SD-07	B-942-2	06/03/19	PES	Fremont	2 (dup)	–	V	0.0466 U	–	–	–	0.0233 U	–	0.0466 U	0.0186 U	0.0466 U	0.0233 U	0.0233 U	0.0466 U
TP-SD-07	TP-SD-07-5	06/03/19	PES	Fremont	5	–	V	0.0424 U	–	–	–	0.0212 U	–	0.0424 U	0.0169 U	0.0424 U	0.0212 U	0.0212 U	0.0424 U
TP-SD-08	TP-SD-08-2	06/03/19	PES	Fremont	2	–	V	0.0483 U	–	–	–	0.0242 U	–	0.0483 U	0.0193 U	0.0483 U	0.0242 U	0.0242 U	0.0483 U
TP-SD-08	TP-SD-08-5	06/03/19	PES	Fremont	5	–	V	0.0415 U	–	–	–	0.0207 U	–	0.0415 U	0.0166 U	0.0415 U	0.0207 U	0.0207 U	0.0415 U
TP-SD-08	TP-SD-08-8	06/03/19	PES	Fremont	8	–	S	0.0498 U	–	–	–	0.0249 U	–	0.0498 U	0.0199 U	0.0498 U	0.0249 U	0.0249 U	0.0498 U
W-MW-01 (P-03)	SB-W-03-0160	01/27/12	WW	ARI	16-16.5	28.4	S	–	–	–	–	–	–	–	–	–	–	–	–
(-25.1 to -35.1)	SB-W-03-0225	01/27/12	WW	ARI	22.5-23	21.9	S	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-03-0315	01/27/12	WW	ARI	31.5-32	12.9	S	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-03-0450	01/27/12	WW	ARI	45-45.5	-0.6	S	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-03-0550	01/27/12	WW	ARI	55.5-56	-11.1	S	–	–	–	–	–	–	–	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
W-MW-01 (P-03)	SB-W-03-0645	01/27/12	WW	ARI	64.5-65	-20.1	S	–	–	–	–	–	–	–	–	–	–	–	–
(continued)	SB-W-03-0730	01/27/12	WW	ARI	73-73.5	-28.6	S	–	–	–	–	–	–	–	–	–	–	–	–
W-MW-02 (P-06)	SB-W-06-0900	01/29/12	WW	ARI	9-9.5	34.0	S	–	–	–	–	–	–	–	–	–	–	–	–
(-26.5 to -36.5)	SB-W-06-0185	01/29/12	WW	ARI	18.5-19	24.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-06-0305	01/30/12	WW	ARI	30.5-31	12.6	S	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-06-0380	01/30/12	WW	ARI	38-38.5	5.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-06-0405	01/30/12	WW	ARI	40.5-41	2.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-06-0485	01/30/12	WW	ARI	48.5-49	-5.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-06-9485	01/30/12	WW	ARI	48.5-49 (dup)	-5.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-06-0590	01/30/12	WW	ARI	59-59.5	-16.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-06-0715	01/30/12	WW	ARI	71.5-72	-28.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	SB-W-06-0790	01/31/12	WW	ARI	79-79.5	-36.0	S	–	–	–	–	–	–	–	–	–	–	–	–
All Data							Number of Analytes Measured	644	585	585	598	646	598	644	644	644	644	644	644
							Number of Analytes Detected	0	200	0	1	38	0	8	84	56	17	37	21
							Frequency of Detection	0.0%	34.2%	0.0%	0.2%	5.9%	0.0%	1.2%	13.0%	8.7%	2.6%	5.7%	3.3%
							Maximum Detection	–	3.06	–	0.000791 J	4.94	–	0.00683 J	1.15 J	27.6 R	5.35	21.2	1.93
							Minimum Detection	0.000355 U	0.000301 U	0.0024 U	0.000258 U	0.000254 U	0.00195 U	0.00022 U	0.00104 U	0.00105 U	0.00027 U	0.000216 U	0.00021 U
							Number Of Vadose (V) Detections above SL	0	0	–	–	0	0	0	0	0	0	0	0
							Number of Saturated (S) Detections above SL	0	1	–	–	3	0	0	3	4	3	4	2
2017-2021							Number of Analytes Measured	644	585	585	598	644	598	644	644	644	644	644	644
							Number of Analytes Detected	0	200	0	1	38	0	8	84	56	17	37	21
							Frequency of Detection	0.0%	34.2%	0.0%	0.2%	5.9%	0.0%	1.2%	13.0%	8.7%	2.6%	5.7%	3.3%
							Maximum Detection	–	3.06	–	0.000791 J	4.94	–	0.00683 J	1.15 J	27.6 R	5.35	21.2	1.93
							Minimum Detection	0.000355 U	0.000301 U	0.0024 U	0.000258 U	0.000254 U	0.00195 U	0.00022 U	0.00104 U	0.00105 U	0.00027 U	0.000216 U	0.00021 U
							Number Of Vadose (V) Detections above SL	0	0	–	–	0	0	0	0	0	0	0	0
							Number of Saturated (S) Detections above SL	0	1	–	–	3	0	0	3	4	3	4	2

Abbreviations:
AAL = Alden Analytical Laboratories, Inc., of Seattle, Washington
ARI = Analytical Resource, Incorporated, Seattle, Washington
B&V = Black Veatch
bgs = below ground surface
Comp = Composite Sample
dup = duplicate
EPJ = E.PJohnson Construction Inc., and Environmental
ESC = ESC Lab Services of Mt. Juliet, Tennessee
F&BI = Friedman & Bruya, Inc.
HC = Hart Crowser, Inc.
OnSite = OnSite Environmental Inc., of Redmond, Washington
Pace = Pace Analytical of Mt. Juliet, Tennessee (formerly ESC)
PES = PES Environmental, Inc.
Retec = Remediation Technologies, Inc.
Roux = Roux Associates
Urban = Urban Redevelopment LLC
WW = WW Environmental LLC

Notes:
Petroleum Hydrocarbons (PHCs) analyzed by Ecology Methods NWTPH-HCID, NWTPH-Gx, or NWTPH-Dx; or EPA Method 418.1, Method 8020, or Method 8015M.
VOCs analyzed by EPA Methods 8010, 8020, 8021B, 624/8240, or 8260B/C/D.
Well screen elevations provided below Sample Location. in parentheses when appliable.
PCUL = Preliminary Cleanup Level from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021. PCULs based on the practical quantitation limits (PQLs) italicized.
Detected results shown in **bold**.
Detections above the screening level in the vadose zone are shown in **bold and highlighted blue**.
Detections above the screening level in the saturated zone are shown in **bold and highlighted gray.**
– = Not available or results not analyzed.
B = Analyte detected in an associated method blank.
J = The reported concentration is an estimate based on detectable results between the method detection limit and reporting limit, laboratory QA/QC, or data validation review.
J+ = The result is an estimated quantity, but the result may be biased high.
J- = The result is an estimated quantity, but the result may be biased low.
ND = Not detected above laboratory reporting limit. Reporting limit not available.
R = The data is unusable. The sample result is rejected due to serious deficiencies in meeting QC criteria. The analyte may or may not be present in the sample
T = Analyte also detected in trip blank.
U = Not detected at a concentration exceeding laboratory reporting limit
ve = Estimated value. The reported range exceeds the calibration range of the analysis.
z = Gasoline/petroleum detection result is likely elevated due to high detections of CVOCs.

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
B-1A	B-1/S-2	12/01/89	HC	ARI	10.5	–	–	–	–	–	–	–	–	–	–	–	–	–	–
B-2A	B-2/S-1	12/01/89	HC	ARI	10	–	–	–	–	–	–	–	–	–	–	–	–	–	–
B-212	B-212-15	09/08/17	PES	ESC	15	42.6	V	0.000270 U	0.000237 U	0.000318 U	0.000500 U	0.000304 U	0.000308 U	0.000896 U	0.000321 U	0.000440 U	0.00275 U	0.000335 U	0.000804 U
	B-212-21	09/08/17	PES	ESC	21	36.6	S	0.000243 U	0.000214 U	**0.000490 J**	**0.000649 J**	0.000274 U	0.000277 U	0.000808 U	0.000290 U	0.000397 U	0.00248 U	0.000302 U	**0.0131**
	B-212-35	09/08/17	PES	ESC	35	22.6	S	0.000255 U	0.000225 U	**0.000955 J**	0.000473 U	0.000288 U	0.000291 U	0.000848 U	0.000304 U	0.000417 U	0.00261 U	0.000317 U	0.000761 U
	B-212-45	09/08/17	PES	ESC	45	12.6	S	0.000245 U	0.000216 U	0.000289 U	0.000454 U	0.000276 U	0.000279 U	0.000814 U	0.000292 U	0.000400 U	0.00250 U	0.000304 U	0.000730 U
	B-907-25	09/08/17	PES	ESC	45 (dup)	12.6	S	0.00699 U	0.00616 U	0.00825 U	0.0129 U	0.00789 U	0.00799 U	0.0232 U	0.00834 U	0.0114 U	0.0715 U	0.00870 U	0.0208 U
	B-212-55	09/08/17	PES	ESC	55	2.6	S	0.000264 U	0.000232 U	0.000311 U	0.000490 U	0.000298 U	0.000301 U	0.000878 U	0.000315 U	0.000431 U	0.00270 U	0.000328 U	0.000787 U
	B-212-65	09/08/17	PES	ESC	65	-7.4	S	0.000272 U	0.000239 U	0.000320 U	0.000504 U	0.000306 U	0.000310 U	0.000903 U	0.000324 U	0.000443 U	0.00277 U	0.000338 U	0.000810 U
	B-212-75	09/08/17	PES	ESC	75	-17.4	S	0.000272 U	0.000240 U	0.000321 U	0.000505 U	0.000307 U	0.000311 U	0.000905 U	0.000324 U	0.000444 U	0.00278 U	0.000338 U	0.000812 U
	B-212-85	09/11/17	PES	ESC	85	-27.4	S	0.000266 U	0.000234 U	0.000313 U	0.000492 U	0.000300 U	0.000303 U	0.000883 U	0.000317 U	0.000433 U	0.00271 U	0.000330 U	0.000792 U
	B-212-95	09/11/17	PES	ESC	95	-37.4	S	0.000306 U	0.000269 U	0.000361 U	0.000568 U	0.000345 U	0.000349 U	0.00102 U	0.000365 U	0.000499 U	0.00313 U	0.000381 U	0.000913 U
	B-212-100	09/11/17	PES	ESC	100	-42.4	S	0.000282 U	0.000249 U	0.000333 U	0.000524 U	0.000319 U	0.000322 U	0.000939 U	0.000337 U	0.000461 U	0.00288 U	0.000351 U	0.000842 U
B-213	B-213-15	09/05/17	PES	ESC	15	42.4	V	0.000271 U	0.000239 U	**0.00289**	0.000503 U	0.000306 U	0.000309 U	0.000902 U	0.000323 U	0.000443 U	0.00277 U	0.000337 U	0.000809 U
	B-213-21.5	09/05/17	PES	ESC	22	35.9	S	0.000244 U	0.000215 U	**0.00263**	**0.000540 J**	0.000275 U	0.000278 U	0.000811 U	0.000291 U	0.000398 U	0.00249 U	0.000303 U	**0.0126 J**
	B-213-35	09/05/17	PES	ESC	35	22.4	S	0.000253 U	0.000223 U	0.000299 U	0.000470 U	0.000286 U	0.000289 U	0.000842 U	0.000302 U	0.000414 U	0.00259 U	0.000315 U	0.000756 U
	B-213-45	09/05/17	PES	ESC	45	12.4	S	0.000259 U	0.000228 U	0.000306 U	0.000481 U	0.000293 U	0.000296 U	0.000862 U	0.000309 U	0.000423 U	0.00265 U	0.000323 U	0.000774 U
	B-213-55	09/05/17	PES	ESC	55	2.4	S	0.000255 U	0.000224 U	0.000300 U	0.000472 U	0.000287 U	0.000291 U	0.000847 U	0.000304 U	0.000416 U	0.00260 U	0.000317 U	0.000760 U
	B-213-65	09/05/17	PES	ESC	65	-7.6	S	0.000257 U	0.000227 U	0.000304 U	0.000478 U	0.000290 U	0.000294 U	0.000856 U	0.000307 U	0.000420 U	0.00263 U	0.000320 U	0.000768 U
	B-213-75	09/05/17	PES	ESC	75	-17.6	S	0.000256 U	0.000225 U	0.000302 U	0.000474 U	0.000289 U	0.000292 U	0.000850 U	0.000305 U	0.000417 U	0.00261 U	0.000318 U	0.000763 U
	B-213-85	09/05/17	PES	ESC	85	-27.6	S	0.000285 U	0.000251 U	0.000336 U	0.000529 U	0.000322 U	0.000325 U	0.000948 U	0.000340 U	0.000466 U	0.00291 U	0.000355 U	0.000851 U
	B-213-95	09/06/17	PES	ESC	95	-37.6	S	0.000289 U	0.000254 U	0.000341 U	0.000536 U	0.000326 U	0.000330 U	0.000961 U	0.000345 U	0.000472 U	0.00295 U	0.000359 U	0.000862 U
	B-213-105	09/06/17	PES	ESC	105	-47.6	S	0.000269 U	0.000237 U	0.000317 U	0.000499 U	0.000303 U	0.000307 U	0.000894 U	0.000321 U	0.000439 U	0.00275 U	0.000334 U	0.000802 U
	B-906-110	09/06/17	PES	ESC	105 (dup)	-47.6	S	0.000269 U	0.000237 U	0.000317 U	0.000498 U	0.000303 U	0.000307 U	0.000893 U	0.000320 U	0.000439 U	0.00274 U	0.000334 U	0.000801 U
	B-213-115	09/06/17	PES	ESC	115	-57.6	S	0.000287 U	0.000253 U	0.000338 U	0.000532 U	0.000324 U	0.000327 U	0.000954 U	0.000342 U	0.000468 U	0.00293 U	0.000357 U	0.000856 U
	B-213-125	09/06/17	PES	ESC	125	-67.6	S	0.000346 U	0.000305 U	0.000408 U	0.000642 U	0.000391 U	0.000395 U	0.00115 U	0.000413 U	0.000566 U	0.00354 U	0.000431 U	0.00103 U
B-214	B-214-15	09/07/17	PES	ESC	15	42.4	V	0.000251 U	0.000221 U	0.000296 U	0.000465 U	0.000283 U	0.000286 U	0.000834 U	0.000299 U	0.000410 U	0.00256 U	0.000312 U	0.000748 U
	B-214-25	09/07/17	PES	ESC	25	32.4	S	0.000247 U	0.000218 U	0.000292 U	0.000459 U	0.000279 U	0.000282 U	0.000822 U	0.000295 U	0.000404 U	0.00253 U	0.000308 U	0.000738 U
	B-214-35	09/07/17	PES	ESC	35	22.4	S	0.000254 U	0.000224 U	0.000300 U	0.000471 U	0.000287 U	0.000290 U	0.000845 U	0.000303 U	0.000415 U	0.00260 U	0.000316 U	0.000758 U
	B-214-45	09/07/17	PES	ESC	45	12.4	S	0.000249 U	0.000219 U	0.000294 U	0.000462 U	0.000281 U	0.000284 U	0.000828 U	0.000297 U	0.000407 U	0.00254 U	0.000310 U	0.000743 U
	B-214-55	09/07/17	PES	ESC	55	2.4	S	0.000260 U	0.000229 U	0.000306 U	0.000482 U	0.000293 U	0.000296 U	0.000864 U	0.000310 U	0.000424 U	0.00265 U	0.000323 U	0.000775 U
	B-214-65	09/07/17	PES	ESC	65	-7.6	S	0.000301 U	0.000265 U	0.000355 U	0.000559 U	0.000340 U	0.000344 U	0.00100 U	0.000359 U	0.000492 U	0.00308 U	0.000375 U	0.000898 U
	B-214-75	09/07/17	PES	ESC	75	-17.6	S	0.000260 U	0.000229 U	0.000307 U	0.000482 U	0.000293 U	0.000297 U	0.000864 U	0.000310 U	0.000424 U	0.00266 U	0.000323 U	0.000775 U
	B-214-85	09/07/17	PES	ESC	85	-27.6	S	0.000281 U	0.000248 U	0.000332 U	0.000522 U	0.000317 U	0.000321 U	0.000935 U	0.000335 U	0.000459 U	0.00287 U	0.000350 U	0.000839 U
	B-908-100	09/07/17	PES	ESC	85 (dup)	-27.6	S	0.000262 U	0.000230 U	0.000309 U	0.000485 U	0.000295 U	0.000298 U	0.000870 U	0.000312 U	0.000427 U	0.00267 U	0.000325 U	0.000780 U
	B-214-95	09/07/17	PES	ESC	95	-37.6	S	0.000257 U	0.000226 U	0.000303 U	0.000476 U	0.000290 U	0.000293 U	0.000854 U	0.000306 U	0.000419 U	0.00262 U	0.000319 U	0.000766 U
	B-214-105	09/07/17	PES	ESC	105	-47.6	S	0.000296 U	0.000261 U	0.000349 U	0.000549 U	0.000334 U	0.000338 U	0.000984 U	0.000353 U	0.000483 U	0.00302 U	0.000368 U	0.000883 U
	B-214-115	09/11/17	PES	ESC	115	-57.6	S	0.000285 U	0.000251 U	0.000337 U	0.000529 U	0.000322 U	0.000326 U	0.000949 U	0.000340 U	0.000466 U	0.00292 U	0.000355 U	0.000851 U
	B-214-120	09/11/17	PES	ESC	120	-62.6	S	0.000276 U	0.000243 U	0.000326 U	0.000513 U	0.000312 U	0.000315 U	0.000919 U	0.000329 U	0.000451 U	0.00282 U	0.000344 U	0.000824 U
B-215	B-215-15	09/12/17	PES	ESC	15	39.0	V	0.000254 U	0.000223 U	0.000299 U	0.000471 U	0.000286 U	0.000290 U	0.000844 U	0.000303 U	0.000414 U	0.00259 U	0.000316 U	0.000757 U
	B-215-25	09/12/17	PES	ESC	25	29.0	S	0.000250 U	0.000220 U	**0.00480**	0.000464 U	0.000283 U	0.000286 U	0.000833 U	0.000299 U	0.000409 U	0.00256 U	0.000311 U	0.000747 U
	B-215-35	09/12/17	PES	ESC	35	19.0	S	0.000276 U	0.000243 U	**0.0277**	0.000512 U	0.000311 U	0.000315 U	0.000917 U	**0.00195**	0.000450 U	0.00282 U	0.000343 U	0.000823 U
	B-215-45	09/12/17	PES	ESC	45	9.0	S	0.000249 U	0.000219 U	0.000294 U	0.000462 U	0.000281 U	0.000284 U	0.000828 U	0.000297 U	0.000406 U	0.00254 U	0.000310 U	0.000743 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
B-215 (continued)	B-215-55	09/12/17	PES	ESC	55	-1.1	S	0.000259 U	0.000228 U	0.000306 U	0.000481 U	0.000292 U	0.000296 U	0.000862 U	0.000309 U	0.000423 U	0.00265 U	0.000322 U	0.000773 U
	B-215-65	09/12/17	PES	ESC	65	-11.1	S	0.00669 U	0.00589 U	**11.1**	0.0124 U	0.00755 U	0.00764 U	0.0222 U	**1.02**	0.0109 U	0.0684 U	0.00833 U	0.0199 U
	B-215-75	09/12/17	PES	ESC	75	-21.1	S	0.000258 U	0.000227 U	0.000304 U	0.000479 U	0.000291 U	0.000294 U	0.000858 U	0.000308 U	0.000421 U	0.00264 U	0.000321 U	0.000770 U
	B-215-85	09/13/17	PES	ESC	85	-31.1	S	0.000282 U	0.000248 U	0.000333 U	0.000523 U	0.000318 U	0.000322 U	0.000938 U	0.000336 U	0.000461 U	0.00288 U	0.000351 U	0.000841 U
	B-909-115	09/13/17	PES	ESC	85 (dup)	-31.1	S	0.000262 U	0.000231 U	0.000309 U	0.000486 U	0.000296 U	0.000299 U	0.000872 U	0.000313 U	0.000428 U	0.00268 U	0.000326 U	0.000782 U
	B-215-95	09/13/17	PES	ESC	95	-41.1	S	0.000280 U	0.000247 U	0.000330 U	0.000519 U	0.000316 U	0.000320 U	0.000931 U	0.000334 U	0.000457 U	0.00286 U	0.000348 U	0.000835 U
B-268	B-268-1	03/17/20	PES	PACE	1	–	V	0.00339 U	0.00192 U	**0.00381**	0.00155 U	0.00177 U	0.00190 U	0.00174 U	0.000496 U	0.000620 U	0.00437 UJ	0.000847 U	0.00593 U
B-269	B-269-1.5	03/17/20	PES	PACE	1.5	–	V	0.00298 U	0.00169 U	0.000764 U	**0.0161**	0.00156 U	0.00167 U	0.00153 U	0.000437 U	0.000546 U	0.00384 UJ	0.000746 U	**0.0659**
B-270	B-270-2	03/17/20	PES	PACE	2	–	V	0.00330 U	0.00187 U	0.000847 U	0.00151 U	0.00173 U	0.00185 U	0.00169 U	0.000484 U	0.000605 U	0.00426 UJ	0.000826 U	**0.0269**
B-271	B-271-1	03/17/20	PES	PACE	1	–	V	0.00293 U	0.00166 U	**0.00661**	**0.00144 J**	0.00154 U	0.00164 U	0.00150 U	0.000429 U	0.000537 U	0.00378 UJ	0.000733 U	0.00513 U
B-272	B-272-1	03/17/20	PES	PACE	1	–	V	0.00322 U	0.00183 U	**0.0126**	**0.0400**	0.00169 U	0.00180 U	0.00165 U	0.000472 U	0.000590 U	0.00415 UJ	0.000805 U	**0.0141**
	B-272-6	03/17/20	PES	PACE	6	–	V	0.00338 U	0.00192 U	**0.0126**	**0.00613 J**	0.00177 U	0.00189 U	0.00173 U	0.000495 U	0.000619 U	0.00436 UJ	0.000845 U	0.00592 U
B-273	B-273-1	03/17/20	PES	PACE	1	–	V	0.00306 U	0.00174 U	0.000786 U	**0.00210 J**	0.00160 U	0.00172 U	0.00157 U	0.000449 U	0.000561 U	0.00395 UJ	0.000767 U	0.00536 U
	B-273-3	03/17/20	PES	PACE	3	–	V	0.00302 U	0.00171 U	**0.144**	0.00138 U	0.00158 U	0.00169 U	0.00155 U	**0.00179**	0.000553 U	0.00389 UJ	0.000755 U	0.00528 U
	B-273-6	03/17/20	PES	PACE	6	–	V	0.00605 U	0.00344 U	**0.220**	**0.0104 J**	0.00317 U	0.00339 U	0.00311 U	**0.00122 J**	0.00111 U	0.00780 UJ	0.00151 U	**0.0163**
B-274	B-274-1	03/17/20	PES	PACE	1	–	V	0.00307 U	0.00174 U	**0.00690**	**0.00750**	0.00161 U	0.00172 U	0.00157 U	0.000450 U	0.000562 U	0.00396 UJ	0.000768 U	**0.0144**
	B-274-3	03/17/20	PES	PACE	3	–	V	0.00296 U	0.00168 U	**0.0175**	0.00135 U	0.00155 U	0.00166 U	0.00152 U	0.000433 U	0.000541 U	0.00381 UJ	0.000740 U	0.00518 U
	B-274-6	03/17/20	PES	PACE	6	–	V	0.00485 U	0.00276 U	**0.134**	**0.0123**	**0.00401 J**	0.00271 U	0.00250 U	**0.00613**	0.000889 U	0.00625 UJ	0.00121 U	**0.0149**
B-275	B-275-1	03/17/20	PES	PACE	1	–	V	0.00320 U	0.00182 U	**0.110**	0.00147 U	0.00168 U	0.00180 U	0.00164 U	**0.00466**	0.000587 U	0.00413 UJ	0.000802 U	0.00561 U
	B-275-6	03/17/20	PES	PACE	6	–	V	0.00506 U	0.00287 U	**2.41**	**0.0938**	**0.00518 J**	0.00284 U	0.00259 U	**0.108**	0.000926 U	0.00651 UJ	0.00126 U	**0.189**
	B-275-9	03/17/20	PES	PACE	9	–	S	0.00420 U	0.00238 U	0.00108 U	**0.00665 J**	0.00220 U	0.00235 U	0.00215 U	0.000615 U	0.000769 U	0.00542 UJ	0.00105 U	0.00735 U
	B-275-10	03/17/20	PES	PACE	10	–	S	0.00300 U	0.00170 U	**0.0164**	**0.00142 J**	0.00157 U	0.00168 U	0.00154 U	0.000440 U	0.000550 U	0.00387 UJ	0.000751 U	0.00526 U
B-276	B-276-1	03/17/20	PES	PACE	1	–	V	0.00504 U	0.00286 U	**0.00336 J**	0.00231 U	0.00263 U	0.00283 U	0.00259 U	0.000738 U	0.000922 U	0.00649 UJ	0.00126 U	0.00882 U
	B-276-7	03/17/20	PES	PACE	7	–	V	0.00302 U	0.00171 U	**0.00811**	0.00138 U	0.00158 U	0.00169 U	0.00155 U	**0.00341**	0.000553 U	0.00389 UJ	0.000755 U	0.00529 U
	B-970-6	03/17/20	PES	PACE	7 (dup)	–	V	0.00302 U	0.00172 U	**0.00976**	0.00138 U	0.00158 U	0.00169 U	0.00155 U	**0.00361**	0.000553 U	0.00390 U	0.000756 U	0.00529 U
	B-276-11	03/17/20	PES	PACE	11	–	S	0.00319 U	0.00181 U	0.000818 U	**0.00217 J**	0.00167 U	0.00179 U	0.00164 U	0.000467 U	0.000584 U	0.00411 U	**0.00682**	0.00558 U
B-277	B-277-1	03/18/20	PES	PACE	1	–	V	0.00344 U	0.00195 U	**0.00434**	0.00158 U	0.00180 U	0.00193 U	0.00176 U	0.000504 U	0.000630 U	0.00444 UJ	0.000861 U	0.00602 U
	B-277-3	03/18/20	PES	PACE	3	–	V	0.00300 U	0.00170 U	**0.00327**	0.00137 U	0.00157 U	0.00168 U	0.00154 U	0.000440 U	0.000549 U	0.00387 UJ	0.000751 U	0.00525 U
	B-277-5	03/18/20	PES	PACE	5	–	V	0.00451 U	0.00256 U	**0.00401 J**	0.00206 U	0.00236 U	0.00253 U	0.00231 U	0.000661 U	0.000826 U	0.00581 UJ	0.00113 U	0.00789 U
	B-277-9.5	03/18/20	PES	PACE	9.5	–	V	0.00649 U	0.00368 U	**2.44**	**0.0644**	**0.0162**	0.00363 U	0.00333 U	**0.969**	0.00119 U	0.00837 UJ	0.00162 U	**0.0251**
	B-277-11	03/18/20	PES	PACE	11	–	S	0.00295 U	0.00167 U	**0.00190 J**	0.00135 U	0.00154 U	0.00165 U	0.00151 U	**0.000747 J**	0.000540 U	0.00380 UJ	0.000737 U	0.00516 U
B-278	B-278-3	03/18/20	PES	PACE	3	–	V	0.00305 U	0.00173 U	**0.288**	0.00140 U	0.00160 U	0.00171 U	0.00156 U	**0.00194**	0.000558 U	0.00393 UJ	0.000762 U	0.00534 U
	B-278-6	03/18/20	PES	PACE	6	–	V	0.00303 U	0.00172 U	**0.00924**	0.00139 U	0.00159 U	0.00170 U	0.00155 U	0.000444 U	0.000554 U	0.00390 UJ	0.000757 U	0.00530 U
B-279	B-279-3	03/18/20	PES	PACE	3	–	V	0.00310 U	0.00176 U	**0.235**	0.00142 U	0.00162 U	0.00174 U	0.00159 U	**0.0119**	0.000567 U	0.00399 UJ	0.000775 U	0.00542 U
	B-279-5	03/18/20	PES	PACE	5	–	V	0.00305 U	0.00173 U	**0.277**	0.00140 U	0.00160 U	0.00171 U	0.00157 U	**0.00906**	0.000559 U	0.00394 UJ	0.000764 U	0.00534 U
	B-279-10	03/18/20	PES	PACE	10	–	V	0.00297 U	0.00168 U	**0.0349**	0.00136 U	0.00155 U	0.00166 U	0.00152 U	0.000435 U	0.000543 U	0.00382 UJ	0.000742 U	0.00519 U
B-280	B-280-4.5	03/18/20	PES	PACE	4.5	–	V	0.00283 U	0.00161 U	**0.00185 J**	0.00129 U	0.00148 U	0.00158 U	0.00145 U	0.000414 U	0.000518 U	0.00365 UJ	0.000707 U	0.00495 U
	B-280-6	03/18/20	PES	PACE	6	–	V	0.00297 U	0.00169 U	**0.00510**	0.00136 U	0.00156 U	0.00166 U	0.00152 U	0.000435 U	0.000544 U	0.00383 UJ	0.000743 U	0.00520 U
B-281	B-281-2	03/18/20	PES	PACE	2	–	V	0.00285 U	0.00162 U	**0.0103**	0.00131 U	0.00149 U	0.00160 U	0.00146 U	0.000418 U	0.000523 U	0.00368 UJ	0.000714 U	0.00500 U
	B-281-5	03/18/20	PES	PACE	5	–	V	0.00309 U	0.00176 U	**0.0143**	0.00142 U	0.00162 U	0.00173 U	0.00159 U	0.000453 U	0.000567 U	0.00399 UJ	0.000774 U	0.00542 U
B-282	B-282-2	03/18/20	PES	PACE	2	–	V	0.00311 U	0.00177 U	**0.00386**	0.00143 U	0.00163 U	0.00174 U	0.00160 U	0.000456 U	0.000570 U	0.00401 UJ	0.000779 U	0.00545 U
	B-282-4	03/18/20	PES	PACE	4	–	V	0.00302 U	0.00171 U	**0.00214 J**	0.00138 U	0.00158 U	0.00169 U	0.00155 U	0.000442 U	0.000552 U	0.00389 UJ	0.000754 U	0.00528 U
	B-971-5	03/18/20	PES	PACE	4 (dup)	–	V	0.00291 U	0.00165 U	**0.00200 J**	0.00133 U	0.00152 U	0.00163 U	0.00149 U	0.000426 U	0.000532 U	0.00375 UJ	0.000727 U	0.00509 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
B-283	B-283-0.5	08/19/20	PES	PACE	0.5	–	V	0.000275 U	0.00235 U	0.00108 U	**0.00345 J**	0.00125 U	0.00137 U	0.00224 U	0.000702 U	0.000995 U	0.00305 U	0.00140 U	**0.00414 J**
B-284	B-284-1	08/19/20	PES	PACE	1	–	V	**0.00128 J**	0.00234 U	0.00108 U	0.00156 U	0.00125 U	0.00137 U	0.00223 U	0.000701 U	0.000992 U	0.00305 U	0.00139 U	**0.00490 J**
B-285	B-285-1	08/19/20	PES	PACE	1	–	V	0.000299 U	0.00255 U	**0.00437**	**0.00323 J**	0.00136 U	0.00149 U	0.00243 U	0.000763 U	0.00108 U	0.00331 U	0.00151 U	**0.00542 J**
B-286	B-286-0.5	08/19/20	PES	PACE	0.5	–	V	0.000608 U	0.00519 U	0.00238 U	**0.0970**	0.00276 U	0.00303 U	0.00495 U	0.00156 U	0.00220 U	0.00676 U	0.00309 U	**0.0567**
B-287	B-287-1	08/19/20	PES	PACE	1	–	V	0.000595 U	0.00507 U	**0.00422 J**	**0.0100 J**	0.00271 U	0.00297 U	0.00483 U	0.00152 U	0.00215 U	0.00660 U	0.00301 U	**0.0105 J**
B-288	B-288-1	08/19/20	PES	PACE	1	–	V	0.00121 U	0.0104 U	**0.0145**	**0.382**	0.00553 U	0.00605 U	0.00987 U	0.00310 U	0.00438 U	0.0135 U	0.00616 U	**0.241**
B-289	B-289-0.5	08/19/20	PES	PACE	0.5	–	V	0.000998 U	0.00853 U	0.00391 U	**0.0134 J**	0.00453 U	0.00497 U	0.00812 U	0.00255 U	0.00361 U	0.0111 U	0.00505 U	**0.0115 J**
B-290	B-290-1	08/20/20	PES	PACE	1	–	V	**0.00169 J**	0.00308 U	**0.00142 J**	**0.0690**	0.00165 U	0.00179 U	0.00294 U	0.000922 U	0.00131 U	0.00401 U	0.00183 U	**0.0439**
B-291	B-291-1	08/20/20	PES	PACE	1	–	V	**0.000813 J**	0.00264 U	0.00121 U	**0.0252**	0.00141 U	0.00154 U	0.00252 U	0.000791 U	0.00112 U	0.00344 U	0.00158 U	**0.0159**
B-292	B-292-3	08/22/20	PES	PACE	3	–	V	0.000288 U	0.00245 U	**0.00258 J**	0.00164 U	0.00131 U	0.00143 U	0.00234 U	0.000735 U	0.00104 U	0.00320 U	0.00146 U	0.00111 U
	B-292-6	08/22/20	PES	PACE	6	–	V	0.000298 U	0.00254 U	**0.00315 J**	0.00169 U	0.00135 U	0.00148 U	0.00242 U	0.000759 U	0.00108 U	0.00330 U	0.00151 U	0.00114 U
	B-292-9	08/22/20	PES	PACE	9	–	V	0.000271 U	0.00230 U	**0.00273 J**	0.00154 U	0.00123 U	0.00135 U	0.00220 U	0.000690 U	0.000977 U	0.00300 U	0.00137 U	0.00104 U
	B-292-12	08/22/20	PES	PACE	12	–	V	0.000301 U	0.00256 U	**0.00158 J**	0.00171 U	0.00137 U	0.00150 U	0.00244 U	0.000767 U	0.00109 U	0.00333 U	0.00152 U	**0.00130 J**
B-293	B-293-1	08/26/20	PES	PACE	1	–	V	0.000254 UJ	0.00216 UJ	**0.00365**	0.00351 U	0.00115 UJ	0.00126 U	0.00206 U	0.000647 U	0.000917 UJ	0.00282 U	0.00129 U	0.00154 U
B-294	B-294-1	08/26/20	PES	PACE	1	–	V	0.000321 UJ	0.00274 UJ	**0.0664**	**0.00762**	0.00146 UJ	0.00160 U	0.00261 U	**0.00143**	0.00116 UJ	0.00357 U	0.00163 U	**0.0233**
	B-294-2	08/26/20	PES	PACE	2	–	V	0.000666 UJ	0.00567 UJ	**0.518**	**0.0692**	0.00303 UJ	0.00331 U	0.00541 U	0.00170 U	0.00240 UJ	0.00738 U	0.00336 U	**0.139**
	B-294-6	08/26/20	PES	PACE	6	–	V	0.000653 UJ	0.00556 UJ	**0.0748**	0.00449 U	0.00298 UJ	0.00325 U	0.00531 U	0.00167 U	0.00236 UJ	0.00726 U	0.00331 U	0.0106 U
	B-294-10	08/26/20	PES	PACE	10	–	S	0.000308 UJ	0.00262 UJ	0.00121 U	0.00672 U	0.00140 UJ	0.00153 U	0.00250 U	0.000786 U	0.00111 UJ	0.00342 U	0.00156 U	0.00191 U
B-295	B-295-1	08/26/20	PES	PACE	1	–	V	0.000276 UJ	0.00235 UJ	**0.00220 J**	0.00156 U	0.00125 UJ	0.00137 U	0.00224 U	0.000703 U	0.000995 UJ	0.00306 U	0.00140 U	0.00140 U
	B-295-3	08/26/20	PES	PACE	3	–	V	0.000409 UJ	0.00348 UJ	**0.129**	0.00232 U	0.00186 UJ	0.00203 U	0.00332 U	0.00104 U	0.00148 UJ	0.00453 U	0.00207 U	0.00466 U
	B-295-7	08/26/20	PES	PACE	7	–	V	0.000343 UJ	0.00292 UJ	**0.0995**	0.00361 U	0.00156 UJ	0.00171 U	0.00279 U	0.000875 U	0.00124 UJ	0.00381 U	0.00174 U	0.00811 U
	B-295-10	08/26/20	PES	PACE	10	–	S	0.000322 UJ	0.00274 UJ	0.00126 U	0.00703 U	0.00146 UJ	0.00160 U	0.00261 U	0.000821 U	0.00116 UJ	0.00357 U	0.00163 U	0.00231 U
B-296	B-296-1	08/26/20	PES	PACE	1	–	V	0.000260 UJ	0.00222 UJ	0.00102 U	0.00148 U	0.00118 UJ	0.00130 U	0.00211 U	0.000663 U	0.000939 UJ	0.00289 U	0.00132 U	0.00362 U
B-297	B-297-1	08/26/20	PES	PACE	1	–	V	0.000282 UJ	0.00240 UJ	**0.00839**	0.00160 U	0.00128 UJ	0.00140 U	0.00229 U	0.000719 U	0.00102 UJ	0.00313 U	0.00143 U	0.00108 U
	B-297-3	08/26/20	PES	PACE	3	–	V	0.000263 UJ	0.00224 UJ	**0.0173**	0.00304 U	0.00119 UJ	0.00131 U	0.00214 U	0.000671 U	0.000950 UJ	0.00292 U	0.00133 U	0.00137 U
	B-500-1	08/26/20	PES	PACE	3 (dup)	–	V	0.000268 U	0.00229 U	**0.0162**	0.00152 U	0.00122 U	0.00134 U	0.00218 U	0.000684 U	0.000969 U	0.00298 U	0.00136 U	0.00214 U
	B-297-5	08/26/20	PES	PACE	5	–	V	0.000262 U	0.00223 U	**0.0181**	0.00320 U	0.00119 U	0.00130 U	0.00213 U	0.000667 U	0.000945 U	0.00290 U	0.00133 U	0.00179 U
B-298	B-298-5	08/26/20	PES	PACE	5	–	V	0.000241 U	0.00206 U	0.000946 U	0.00208 U	0.00110 U	0.00120 U	0.00196 U	0.000616 U	0.000872 U	0.00269 U	0.00122 U	0.00343 U
	B-298-6	08/26/20	PES	PACE	6	–	V	**0.00120 J**	0.00247 U	**0.00352**	**0.0757**	0.00132 U	0.00145 U	0.00236 U	0.000741 U	0.00105 U	0.00323 U	0.00147 U	**0.0430**
B-299	B-299-2	02/01/21	PES	PACE	2	–	V	0.000302 U	0.00257 U	0.00118 U	0.00172 U	0.00137 U	0.00150 U	0.00246 UJ	0.000771 U	0.00109 U	0.00335 UJ	0.00153 U	0.00116 U
	B-299-5.5	02/01/21	PES	PACE	5.5	–	V	0.000273 U	0.00232 U	**0.00126 J**	0.00155 U	0.00124 U	0.00136 U	0.00222 UJ	0.000696 U	0.000986 U	0.00303 UJ	0.00138 U	**0.00170 J**
	B-1003-10	02/01/21	PES	PACE	5.5 (dup)	–	V	0.000284 U	0.00242 U	**0.00214 J**	0.00161 U	0.00129 U	0.00141 U	0.00231 UJ	0.000724 U	0.00103 U	0.00315 UJ	0.00144 U	0.00109 U
B-300	B-300-2.5	02/01/21	PES	PACE	2.5	–	V	0.000303 U	0.00258 U	0.00118 U	0.00172 U	0.00137 U	0.00151 U	0.00246 UJ	0.000772 U	0.00109 U	0.00336 UJ	0.00153 U	**0.00608 J**
	B-300-5.5	02/01/21	PES	PACE	5.5	–	V	0.000295 U	0.00251 U	**0.00172 J**	0.00168 U	0.00134 U	0.00147 U	0.00240 UJ	0.000753 U	0.00107 U	0.00328 UJ	0.00150 U	0.00113 U
B-301	B-301-2	02/01/21	PES	PACE	2	–	V	0.000294 U	0.00250 U	**0.00156 J**	0.00167 U	0.00133 U	0.00146 U	0.00239 UJ	0.000749 U	0.00106 U	0.00326 UJ	0.00149 U	0.00113 U
	B-301-5	02/01/21	PES	PACE	5	–	V	0.000310 U	0.00264 U	**0.00141 J**	0.00176 U	0.00141 U	0.00154 U	0.00251 UJ	0.000789 U	0.00112 U	0.00343 UJ	0.00157 U	0.00119 U
B-302	B-302-2	02/01/21	PES	PACE	2	–	V	0.000287 U	0.00244 U	0.00112 U	0.00163 U	0.00130 U	0.00143 U	0.00233 UJ	0.000731 U	0.00104 U	0.00318 UJ	0.00145 U	0.00110 U
	B-302-4	02/01/21	PES	PACE	4	–	V	0.000327 U	0.00278 U	0.00128 U	0.00185 U	0.00148 U	0.00163 U	0.00265 UJ	0.000833 U	0.00118 U	0.00362 UJ	0.00165 U	0.00126 U
BB-5	S-6	03/09/97	B&V	Unknown	15-17	34.0	V	–	–	–	ND	–	–	–	–	–	–	–	ND
	S-10	03/09/97	B&V	Unknown	25-27	24.0	S	–	–	–	–	–	–	–	–	–	–	–	–
BB-7	S-4	04/06/97	B&V	Unknown	10-12	17.0	S	–	–	–	–	–	–	–	–	–	–	–	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	**–**	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	**–**	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
BB-8 (13.6 to 3.6)	S-8	06/06/97	B&V	Unknown	20-22	23.6	S	–	–	ND	ND	ND	–	–	ND	–	–	ND	ND
BB-10	S-6	08/29/97	B&V	Unknown	15-17	42.0	V	–	–	–	–	–	–	–	–	–	–	–	–
BB-12	S-3	03/18/98	B&V	Unknown	15-16.5	18.8	S	–	–	ND	ND	ND	–	–	ND	–	–	ND	ND
	S-14	03/18/98	B&V	Unknown	45-46.5	-11.2	S	–	–	ND	ND	ND	–	–	ND	–	–	ND	ND
BB-13	S-10	03/19/98	B&V	Unknown	25-27.5	1.9	S	–	–	ND	ND	ND	–	–	ND	–	–	ND	ND
	S-16	03/19/98	B&V	Unknown	40-41.5	-13.1	S	–	–	ND	ND	ND	–	–	ND	–	–	ND	ND
BB-14	S-2	03/03/98	B&V	Unknown	5-6.5	21.3	V	–	–	–	–	–	–	–	–	–	–	–	–
	S-5	03/03/98	B&V	Unknown	12.5-14	14.3	S	–	–	–	–	–	–	–	–	–	–	–	–
	S-9	03/03/98	B&V	Unknown	22.5-24	4.3	S	–	–	–	–	–	–	–	–	–	–	–	–
	S-12	03/03/98	B&V	Unknown	30-31.5	-4.3	S	–	–	–	–	–	–	–	–	–	–	–	–
CHB-07	CHB-07-12.5-13.5	04/14/05	CH2M	ARI	12.5-13.5	16.5	S	–	–	0.0011 U	0.0011 U	**0.0083**	–	–	0.0011 U	–	–	**0.027**	0.0022 U
	CHB-07-5.0-7.0	04/14/08	CH2M	ARI	5-7	23.5	S	–	–	–	–	–	–	–	–	–	–	–	–
CHB-08	CHB-08-15.0-16.0	04/15/08	CH2M	ARI	15-16	14.1	S	–	–	0.0008 U	0.0008 U	0.0008 U	–	–	0.0008 U	–	–	0.0008 U	0.0016 U
CHB-09	CHB-09-20.0-21.5	04/16/08	CH2M	ARI	20-21.5	15.4	S	–	–	–	–	–	–	–	–	–	–	–	–
	CHB-09-25.0-26.5	04/16/08	CH2M	ARI	25-26.5	10.4	S	–	–	0.0012 U	0.0012 U	0.0012 U	–	–	0.0012 U	–	–	0.0012 U	0.0024 U
GEI-MW-1 (-9.7 to -29.7)	MW-1-1-2.5	08/22/14	GEI	Fremont	1	29.5	V	–	–	0.0181 U	0.0181 U	–	–	–	0.0181 U	–	–	0.0181 U	18.1 U
GEI-MW-2 (4.0 to -6.0)	MW-2-2-5.0	08/23/14	GEI	Fremont	5	26.6	V	–	–	0.0391 U	0.0391 U	–	–	–	0.0391 U	–	–	0.0391 U	39.1 U
	MW-2-4-10.0	08/23/14	GEI	Fremont	10	21.6	S	–	–	–	–	–	–	–	–	–	–	–	–
	MW-2-8-20.0	08/23/14	GEI	Fremont	20	11.6	S	–	–	–	–	–	–	–	–	–	–	–	–
GEI-MW-3	MW-3-4-10.0	08/23/14	GEI	Fremont	10	20.8	S	–	–	0.0258 U	0.0258 U	–	–	–	0.0258 U	–	–	0.0258 U	25.8 U
(-18.7 to -28.7)	MW-3-10-50.0	08/23/14	GEI	Fremont	50	-19.3	S	–	–	0.0166 U	0.0166 U	–	–	–	0.0166 U	–	–	0.0166 U	16.6 U
GEI-4	GEI-4-2-5.0	08/23/14	GEI	Fremont	5	26.0	V	–	–	0.0214 U	0.0214 U	–	–	–	0.0214 U	–	–	0.0214 U	21.4 U
	GEI-4-5-12.5	08/23/14	GEI	Fremont	12.5	18.5	S	–	–	0.0243 U	0.0243 U	–	–	–	0.0243 U	–	–	0.0243 U	24.3 U
MW-1 (SCLB-3)	RS3-2.5	03/15/93	EPJ	OnSite	2.5	37.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS3-7.5	03/15/93	EPJ	OnSite	7.5	32.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS3-17.5	03/15/93	EPJ	OnSite	17.5	22.5	S	–	–	–	**7.3**	–	–	–	–	–	–	–	**15.8**
	RS3-22.5/RS3-27.5 (Comp)	03/15/93	EPJ	OnSite	22.5-27.5	–	S	–	–	–	**0.8**	–	–	–	–	–	–	–	**2.49**
	RS3-32.5	03/15/93	EPJ	OnSite	32.5	7.5	S	–	–	–	0.050 U	–	–	–	–	–	–	–	1.00 U
	RS3-37.5	03/15/93	EPJ	OnSite	37.5	2.5	S	–	–	–	0.050 U	–	–	–	–	–	–	–	1.00 U
MW-2 (SCLB-4)	RS4-2.5	03/15/93	EPJ	OnSite	2.5	37.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS4-7.5	03/15/93	EPJ	OnSite	7.5	32.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS4-12.5/RS4-17.5	03/15/93	EPJ	OnSite	12.5-17.5	–	S	–	–	–	0.05 U	–	–	–	–	–	–	–	0.05 U
	RS4-22.5/RS4-27.5 (Comp)	03/15/93	EPJ	OnSite	22.5-27.5	–	S	–	–	–	0.05 U	–	–	–	–	–	–	–	**0.096** J
	RS4-37.5	03/15/93	EPJ	OnSite	37.5	2.5	S	–	–	–	0.05 U	–	–	–	–	–	–	–	0.05 U
MW-3 (SCLB-5)	RS5-2.5/RS5-7.5 (Comp)	03/16/93	EPJ	OnSite	2.5-7.5	–	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS5-12.5/RS5-17.5 (Comp)	03/16/93	EPJ	OnSite	12.5-17.5	–	S	–	–	–	**0.28**	–	–	–	–	–	–	–	**1.37**
	RS5-17.5	03/16/93	EPJ	OnSite	17.5	21.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	RS5-22.5	03/16/93	EPJ	OnSite	22.5	16.5	S	–	–	–	**0.099 J**	–	–	–	–	–	–	–	**0.446**
	RS5-32.5	03/16/93	EPJ	OnSite	32.5	6.5	S	–	–	–	0.05 U	–	–	–	–	–	–	–	**0.15**
	RS5-37.5	03/16/93	EPJ	OnSite	37.5	1.5	S	–	–	–	0.050 U	–	–	–	–	–	–	–	1.00 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
MW-4 (SCLB-6)	RS6-2.5	03/17/93	EPJ	OnSite	2.5	37.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS6-7.5	03/17/93	EPJ	OnSite	7.5	32.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS6-12.5	03/17/93	EPJ	OnSite	12.5	27.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS6-17.5/RS6-22.5 (Comp)	03/17/93	EPJ	OnSite	17.5-22.5	–	V	–	–	–	0.050 U	–	–	–	–	–	–	–	**0.092 J**
	RS6-27.5	03/17/93	EPJ	OnSite	27.5	12.5	S	–	–	–	0.050 U	–	–	–	–	–	–	–	1.00 U
MW-5 (SCLB-7)	RS7-2.5	03/17/93	EPJ	OnSite	2.5	37.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS7-7.5	03/17/93	EPJ	OnSite	7.5	32.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS7-12.5	03/17/93	EPJ	OnSite	12.5	27.5	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS7-17.5	03/17/93	EPJ	OnSite	17.5	22.5	S	–	–	–	–	–	–	–	–	–	–	–	–
	RS7-22.5	03/17/93	EPJ	OnSite	22.5	17.5	S	–	–	–	–	–	–	–	–	–	–	–	–
MW-6	MW6-25	10/11/93	Retec	ARI	25	13.2	S	–	–	–	**0.23**	–	–	–	–	–	–	–	**0.93**
MW-7	MW7-16.5	10/11/93	Retec	ARI	16.5	18.6	S	–	–	–	**160**	–	–	–	–	–	–	–	**300**
	MW7-18.5	10/11/93	Retec	ARI	18.5	16.6	S	–	–	–	**30**	–	–	–	–	–	–	–	**62**
MW-8 (28.7 to 14.2)	MW8-20	10/18/93	Retec	AAL	20	13.2	S	–	–	–	0.059 U	–	–	–	–	–	–	–	0.12 U
MW-9 (33.7 to 18.7)	MW9-17.5	10/18/93	Retec	AAL	17.5	23.6	S	–	–	–	0.068 U	–	–	–	–	–	–	–	0.14 U
MW-10	MW10-17.5	10/19/93	Retec	AAL	17.5	20.5	S	–	–	–	0.068 U	–	–	–	–	–	–	–	0.14 U
MW102 (B102) (-65.8 to -75.8)	B102-20	07/17/12	SES	F&BI	20	29.2	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B102-30	07/17/12	SES	F&BI	30	19.2	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B102-38	07/17/12	SES	F&BI	38	11.2	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B102-40	07/17/12	SES	F&BI	40	9.2	S	–	–	–	–	–	–	–	–	–	–	–	–
	B102-49	07/17/12	SES	F&BI	49	0.2	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B102-60	07/17/12	SES	F&BI	60	-10.8	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B102-70	07/18/12	SES	F&BI	70	-20.8	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B102-80	07/19/12	SES	F&BI	80	-30.8	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B102-90	07/19/12	SES	F&BI	90	-40.8	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B102-100	07/20/12	SES	F&BI	100	-50.8	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B102-110	07/20/12	SES	F&BI	110	-60.8	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B102-120	07/23/12	SES	F&BI	120	-70.8	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
MW103 (B103) (-67.6 to -77.6)	B103-10	07/25/12	SES	F&BI	10	25.9	V	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B103-18	07/25/12	SES	F&BI	18	17.9	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B103-30	07/25/12	SES	F&BI	30	5.9	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B103-40	07/25/12	SES	F&BI	40	-4.1	S	–	–	**4.6**	–	0.05 U	–	–	**0.77**	–	–	0.05 U	–
	B103-45	07/25/12	SES	F&BI	45	-9.1	S	–	–	**5.3**	–	0.05 U	–	–	**0.48**	–	–	0.05 U	–
	B103-55	07/25/12	SES	F&BI	55	-19.1	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B103-62.5	07/26/12	SES	F&BI	62.5	-26.6	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B103-75	07/26/12	SES	F&BI	75	-39.1	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B103-83	07/26/12	SES	F&BI	83	-47.1	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B103-95	07/26/12	SES	F&BI	95	-59.1	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B103-105	07/27/12	SES	F&BI	105	-69.1	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B103-113	07/27/12	SES	F&BI	113	-77.1	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
MW104 (B104)	B104-10	07/30/12	SES	F&BI	10	32.7	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
(-76.3 to -86.3)	B104-20	07/30/12	SES	F&BI	20	22.7	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B104-30	07/30/12	SES	F&BI	30	12.7	S	–	–	**1.8**	–	0.05 U	–	–	**0.086**	–	–	0.05 U	–
	B104-35	07/30/12	SES	F&BI	35	7.7	S	–	–	**7.1**	–	0.05 U	–	–	**0.23**	–	–	0.05 U	–
	B104-50	07/30/12	SES	F&BI	50	-7.3	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B104-60	07/31/12	SES	F&BI	60	-17.3	S	–	–	**2.1**	–	0.05 U	–	–	**0.21**	–	–	0.05 U	–
	B104-69	07/31/12	SES	F&BI	69	-26.3	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B104-80	07/31/12	SES	F&BI	80	-37.3	S	–	–	**0.12**	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B104-90	08/01/12	SES	F&BI	90	-47.3	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B104-100	08/01/12	SES	F&BI	100	-57.3	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B104-110	08/01/12	SES	F&BI	110	-67.3	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B104-120	08/01/12	SES	F&BI	120	-77.3	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B104-130	08/01/12	SES	F&BI	130	-87.3	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
MW105 (B105)	B105-10	08/06/12	SES	F&BI	10	34.2	V	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
(-85.8 to -95.8)	B105-20	08/06/12	SES	F&BI	20	24.2	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B105-30	08/06/12	SES	F&BI	30	14.2	S	–	–	**1.3**	–	0.05 U	–	–	**0.16**	–	–	0.05 U	–
	B105-40	08/08/12	SES	F&BI	40	4.2	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B105-50	08/08/12	SES	F&BI	50	-5.8	S	–	–	**0.18**	–	0.05 U	–	–	**0.040**	–	–	0.05 U	–
	B105-60	08/09/12	SES	F&BI	60	-15.8	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B105-70	08/09/12	SES	F&BI	70	-25.8	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B105-80	08/09/12	SES	F&BI	80	-35.8	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B105-90	08/10/12	SES	F&BI	90	-45.8	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B105-100	08/10/12	SES	F&BI	100	-55.8	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B105-110	08/10/12	SES	F&BI	110	-65.8	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B105-120	08/10/12	SES	F&BI	120	-75.8	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B105-130	08/10/12	SES	F&BI	130	-85.8	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B105-138	08/10/12	SES	F&BI	138	-93.8	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
MW106 (B106)	B106-10	08/14/12	SES	F&BI	10	42.0	V	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
(-78.0 to -88.0)	B106-20	08/14/12	SES	F&BI	20	32.0	V	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B106-30	08/14/12	SES	F&BI	30	22.0	S	–	–	**0.038**	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B106-40	08/14/12	SES	F&BI	40	12.0	S	–	–	**3.1**	–	0.05 U	–	–	**0.15**	–	–	0.05 U	–
	B106-50	08/14/12	SES	F&BI	50	2.0	S	–	–	**0.73**	–	0.05 U	–	–	**0.17**	–	–	0.05 U	–
	B106-60	08/14/12	SES	F&BI	60	-8.0	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B106-70	08/15/12	SES	F&BI	70	-18.0	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B106-80	08/15/12	SES	F&BI	80	-28.0	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B106-90	08/15/12	SES	F&BI	90	-38.0	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B106-100	08/15/12	SES	F&BI	100	-48.0	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B106-110	08/15/12	SES	F&BI	110	-58.0	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B106-120	08/15/12	SES	F&BI	120	-68.0	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B106-130	08/15/12	SES	F&BI	130	-78.0	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B106-140	08/15/12	SES	F&BI	140	-88.0	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
MW107 (B107) (8.8 to -1.2)	B107-05	03/12/12	SES	F&BI	5	38.8	V	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B107-15	03/12/12	SES	F&BI	15	28.8	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B107-25	03/12/12	SES	F&BI	25	18.8	S	–	–	**0.60**	0.05 U	0.05 U	–	–	**0.063**	–	–	0.05 U	0.15 U
	B107-35	03/12/12	SES	F&BI	35	8.8	S	–	–	**19**	0.05 U	0.05 U	–	–	**0.59**	–	–	0.05 U	0.15 U
	B107-45	03/12/12	SES	F&BI	45	-1.2	S	–	–	**0.028**	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
MW108 (B108) (-7.2 to -17.2)	B108-15	12/14/12	SES	F&BI	15	17.8	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B108-25	12/14/12	SES	F&BI	25	7.8	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B108-35	12/14/12	SES	F&BI	35	-2.2	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B108-45	12/14/12	SES	F&BI	45	-12.2	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B108-50	12/14/12	SES	F&BI	50	-17.2	S	–	–	**0.037**	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
MW109 (B109) (0.0 to -10.0)	B109-05	04/12/12	SES	F&BI	5	30.0	V	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B109-15	04/12/12	SES	F&BI	15	20.0	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B109-25	04/12/12	SES	F&BI	25	10.0	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B109-35	04/12/12	SES	F&BI	35	0.0	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B109-45	04/12/12	SES	F&BI	45	-10.0	S	–	–	**1.6**	–	0.05 U	–	–	**0.94**	–	–	0.05 U	–
MW110 (B110) (4.7 to -5.3)	B110-15	04/12/12	SES	F&BI	15	24.7	V	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B110-25	04/12/12	SES	F&BI	25	14.7	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B110-35	04/12/12	SES	F&BI	35	4.7	S	–	–	**3.4**	–	0.05 U	–	–	**0.21**	–	–	0.05 U	–
	B110-45	04/12/12	SES	F&BI	45	-5.3	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
MW111 (B111) (-33.5 to -43.5)	B111-10	05/12/12	SES	F&BI	10	26.5	V	–	–	0.05 U	–	0.1 U	–	–	0.06 U	–	–	0.1 U	–
	B111-20	05/12/12	SES	F&BI	20	16.5	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B111-30	05/12/12	SES	F&BI	30	6.5	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B111-38	05/12/12	SES	F&BI	38	-1.5	S	–	–	**0.078**	–	0.05 U	–	–	**0.40**	–	–	0.05 U	–
	B111-50	05/12/12	SES	F&BI	50	-13.5	S	–	–	**1.4**	–	0.05 U	–	–	**0.56**	–	–	0.05 U	–
	B111-60	06/12/12	SES	F&BI	60	-23.5	S	–	–	**0.085**	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B111-70	06/12/12	SES	F&BI	70	-33.5	S	–	–	**0.033**	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B111-80	06/12/12	SES	F&BI	80	-43.5	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
MW112 (B112) (-17.5 to -27.5)	B112-10	11/12/12	SES	F&BI	10	47.5	V	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B112-20	11/12/12	SES	F&BI	20	37.5	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B112-30	11/12/12	SES	F&BI	30	27.5	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B112-40	11/12/12	SES	F&BI	40	17.5	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B112-50	11/12/12	SES	F&BI	50	7.5	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B112-60	11/12/12	SES	F&BI	60	-2.5	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B112-75	11/12/12	SES	F&BI	75	-17.5	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B112-85	12/12/12	SES	F&BI	85	-27.5	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
MW113 (B113) (-37.1 to -47.1)	B113-10	12/18/12	SES	F&BI	10	22.9	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B113-20	12/18/12	SES	F&BI	20	12.9	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B113-30	12/18/12	SES	F&BI	30	2.9	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B113-40	12/18/12	SES	F&BI	40	-7.1	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B113-50	12/18/12	SES	F&BI	50	-17.1	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
MW114 (B114) (10.8 to 0.8)	B114-15	10/12/12	SES	F&BI	15	30.8	V	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B114-25	10/12/12	SES	F&BI	25	20.8	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B114-35	10/12/12	SES	F&BI	35	10.8	S	–	–	**8.8**	–	0.05 U	–	–	**0.45**	–	–	0.05 U	–

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	**–**	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	**–**	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
MW114 (B114)	B114-40	10/12/12	SES	F&BI	40	5.8	S	–	–	**0.59**	–	0.05 U	–	–	**0.071**	–	–	0.05 U	–
(continued)	B114-45	10/12/12	SES	F&BI	45	0.8	S	–	–	**0.25**	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
MW115 (B115)	B115-10	12/13/12	SES	F&BI	10	24.1	V	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
(-0.9 to -10.9)	B115-15	12/13/12	SES	F&BI	15	19.1	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B115-25	12/13/12	SES	F&BI	25	9.1	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B115-35	12/13/12	SES	F&BI	35	-0.9	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B115-45	12/13/12	SES	F&BI	45	-10.9	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
MW116 (B116)	B116-15	07/12/12	SES	F&BI	15	16.4	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
(-3.6 to -13.6)	B116-25	07/12/12	SES	F&BI	25	6.4	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B116-35	07/12/12	SES	F&BI	35	-3.6	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B116-45	07/12/12	SES	F&BI	45	-13.6	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
MW117 (B117)	B117-10	02/04/13	SES	F&BI	10	46.9	V	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
(16.9 to 1.9)	B117-20	02/04/13	SES	F&BI	20	36.9	V	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B117-30	02/04/13	SES	F&BI	30	26.9	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B117-40	02/04/13	SES	F&BI	40	16.9	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B117-50	02/04/13	SES	F&BI	50	6.9	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
MW118 (B118)	B118-10	03/21/13	SES	F&BI	10	42.9	V	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
(12.9 to 2.9)	B118-20	03/21/13	SES	F&BI	20	32.9	V	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B118-30	03/21/13	SES	F&BI	30	22.9	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B118-40	03/21/13	SES	F&BI	40	12.9	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B118-50	03/21/13	SES	F&BI	50	2.9	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
MW119 (B119)	B119-10	03/21/13	SES	F&BI	10	27.4	V	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
(2.4 to -7.7)	B119-20	03/21/13	SES	F&BI	20	17.4	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B119-30	03/21/13	SES	F&BI	30	7.4	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
	B119-40	03/21/13	SES	F&BI	40	-2.7	S	–	–	0.025 U	–	0.05 U	–	–	0.03 U	–	–	0.05 U	–
MW120 (B120)	B120-20	12/16/13	SES	F&BI	20	20.0	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
(0 to -10)	B120-30	12/16/13	SES	F&BI	30	10.0	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B120-45	12/16/13	SES	F&BI	45	-5.0	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
MW121 (B121)	B121-15	12/16/13	SES	F&BI	15	26.7	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
(26.7 to 16.7)	B121-25	12/16/13	SES	F&BI	25	16.7	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
MW122 (B122)	B122-15	12/17/13	SES	F&BI	15	15.0	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
(-75 to -89)	B122-25	12/17/13	SES	F&BI	25	5.0	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B122-40	12/17/13	SES	F&BI	40	-10.0	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B122-45	12/17/13	SES	F&BI	45	-15.0	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B122-50	12/17/13	SES	F&BI	50	-20.0	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B122-60	12/17/13	SES	F&BI	60	-30.0	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B122-70	12/17/13	SES	F&BI	70	-40.0	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B122-80	12/17/13	SES	F&BI	80	-50.0	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B122-100	12/17/13	SES	F&BI	100	-70.0	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
MW123 (B123)	B123-20	12/18/13	SES	F&BI	20	7.5	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
(-42.5 to -52.5)																			

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	**–**	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	**–**	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
MW124 (B124)	B124-10	12/19/13	SES	F&BI	10	46.2	V	–	–	–	–	–	–	–	–	–	–	–	–
(-53.8 to -63.8)	B124-20	12/19/13	SES	F&BI	20	36.2	V	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B124-30	12/19/13	SES	F&BI	30	26.2	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B124-40	12/19/13	SES	F&BI	40	16.2	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B124-50	12/19/13	SES	F&BI	50	6.2	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B124-60	12/19/13	SES	F&BI	60	-3.8	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B124-70	12/19/13	SES	F&BI	70	-13.8	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B124-80	12/19/13	SES	F&BI	80	-23.8	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B124-90	12/19/13	SES	F&BI	90	-33.8	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B124-100	12/19/13	SES	F&BI	100	-43.8	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B124-110	12/19/13	SES	F&BI	110	-53.8	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B124-120	12/19/13	SES	F&BI	120	-63.8	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
MW125 (B125)	B125-15	12/20/13	SES	F&BI	15	28.6	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
(28.6 to 13.6)	B125-20	12/20/13	SES	F&BI	20	23.6	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B125-25	12/20/13	SES	F&BI	25	18.6	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B125-30	12/20/13	SES	F&BI	30	13.6	S	–	–	–	–	–	–	–	–	–	–	–	–
MW126 (B126)	B126-20	12/30/13	SES	F&BI	20	10.9	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
(-54.1 to -64.1)	B126-35	12/30/13	SES	F&BI	35	-4.1	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B126-45	12/30/13	SES	F&BI	45	-14.1	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B126-55	12/30/13	SES	F&BI	55	-24.1	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B126-60	12/31/13	SES	F&BI	60	-29.1	S	–	–	–	–	–	–	–	–	–	–	–	–
	B126-65	01/01/14	SES	F&BI	65	-34.1	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B126-75	01/02/14	SES	F&BI	75	-44.1	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B126-80	01/03/14	SES	F&BI	80	-49.1	S	–	–	–	–	–	–	–	–	–	–	–	–
	B126-85	01/04/14	SES	F&BI	85	-54.1	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B126-95	01/05/14	SES	F&BI	95	-64.1	S	–	–	–	–	–	–	–	–	–	–	–	–
MW127 (B127)	B127-15	12/31/13	SES	F&BI	15	24.0	V	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
(-1.0 to -11.0)	B127-25	12/31/13	SES	F&BI	25	14.0	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B127-40	12/31/13	SES	F&BI	40	-1.0	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B127-45	12/31/13	SES	F&BI	45	-6.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	B127-50	12/31/13	SES	F&BI	50	-11.0	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
MW128 (B128)	B128-25	01/09/14	SES	F&BI	25	2.9	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
(-30.8 to -40.8)	B128-45	01/09/14	SES	F&BI	45	-17.1	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
	B128-65	01/09/14	SES	F&BI	65	-37.1	S	–	–	0.025 U	0.05 U	0.05 U	–	–	0.03 U	–	–	0.05 U	0.15 U
MW-138	MW-138-15	09/12/17	PES	ESC	15	42.5	V	0.000278 U	0.000245 U	0.000328 U	0.000516 U	0.000314 U	0.000317 U	0.000925 U	0.000332 U	0.000454 U	0.00284 U	0.000346 U	0.000830 U
(-47.5 to -57.5)	MW-138-25	09/12/17	PES	ESC	25	32.5	S	0.000269 U	0.000237 U	0.000318 U	0.000500 U	0.000304 U	0.000307 U	0.000896 U	0.000321 U	0.000440 U	0.00275 U	0.000335 U	0.000804 U
	MW-138-35	09/12/17	PES	ESC	35	22.5	S	0.000250 U	0.000220 U	0.000295 U	0.000464 U	0.000282 U	0.000285 U	0.000831 U	0.000298 U	0.000408 U	0.00255 U	0.000311 U	0.000746 U
	MW-138-45	09/12/17	PES	ESC	45	12.5	S	0.000247 U	0.000218 U	0.000292 U	0.000459 U	0.000279 U	0.000282 U	0.000822 U	0.000295 U	0.000404 U	0.00253 U	0.000308 U	0.000738 U
	MW-138-56	09/12/17	PES	ESC	56	1.5	S	0.000263 U	0.000232 U	0.000310 U	0.000488 U	0.000297 U	0.000300 U	0.000875 U	0.000314 U	0.000430 U	0.00269 U	0.000327 U	0.000785 U
	MW-138-65	09/13/17	PES	ESC	65	-7.5	S	0.000253 U	0.000223 U	0.000299 U	0.000469 U	0.000286 R	0.000289 U	0.000841 U	0.000302 U	0.000413 U	0.00258 U	0.000315 R	0.000755 U
	B-910-90	09/13/17	PES	ESC	65 (dup)	-7.5	S	0.000271 U	0.000239 U	0.000320 U	0.000503 U	0.000306 R	0.000309 U	0.000901 U	0.000323 U	0.000443 U	0.00277 U	0.000337 R	0.000809 U
	MW-138-75	09/13/17	PES	ESC	75	-17.5	S	0.000258 U	0.000227 U	0.000304 U	0.000478 U	0.000291 U	0.000294 U	0.000857 U	0.000307 U	0.000421 U	0.00263 U	0.000320 U	0.000769 U
	MW-138-85	09/13/17	PES	ESC	85	-27.5	S	0.000281 U	0.000248 U	0.000332 U	0.000522 U	0.000317 U	0.000321 U	0.000935 U	0.000335 U	0.000459 U	0.00287 U	0.000350 U	0.000839 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
MW-138 (continued)	MW-138-95	09/13/17	PES	ESC	95	-37.5	S	0.000255 U	0.000225 U	0.000301 U	0.000473 U	0.000288 U	0.000291 U	0.000849 U	0.000304 U	0.000417 U	0.00261 U	0.000317 U	0.000761 U
	MW-138-105	09/13/17	PES	ESC	105	-47.5	S	0.000291 U	0.000256 U	0.000343 U	0.000540 U	0.000328 U	0.000332 U	0.000968 U	0.000347 U	0.000475 U	0.00297 U	0.000362 U	0.000868 U
	MW-138-115	09/14/17	PES	ESC	115	-57.5	S	0.000271 U	0.000239 U	0.000320 U	0.000503 U	0.000306 U	0.000309 U	0.000901 U	0.000323 U	0.000443 U	0.00277 U	0.000337 U	0.000809 U
MW-140 (-78.9 to -88.9)	MW-140-15	08/30/17	PES	ESC	15	35.6	V	0.000267 U	0.000235 U	0.000315 U	0.000495 U	0.000301 U	0.000304 U	0.000887 U	0.000318 U	0.000436 U	0.00273 U	0.000332 U	0.000796 U
	MW-140-25	08/30/17	PES	ESC	25	25.6	S	0.000254 U	0.000223 U	**0.147**	0.000471 U	0.000286 U	0.000290 U	0.000844 U	**0.0107**	0.000414 U	0.00259 U	0.000316 U	0.000757 U
	MW-140-35	08/30/17	PES	ESC	35	15.6	S	0.00682 U	0.00600 U	**15.1**	0.0126 U	0.00769 U	0.00778 U	0.0226 U	**0.629**	0.0111 U	0.0697 U	**0.0107 J**	0.0203 U
	MW-140-45	08/30/17	PES	ESC	45	5.6	S	0.000250 U	0.000220 U	**4.27**	0.000463 U	0.000282 U	0.000285 U	0.000830 U	**0.0793**	0.000408 U	0.00255 U	**0.00160**	0.000745 U
	MW-140-55	08/30/17	PES	ESC	55	-4.4	S	0.000257 U	0.000226 U	**1.56**	**0.000498 J**	**0.000500 J**	0.000293 U	0.000854 U	**0.0496**	0.000419 U	0.00262 U	**0.0990**	0.000766 U
	MW-140-65	08/30/17	PES	ESC	65	-14.4	S	0.000251 U	0.000221 U	0.00746 U	0.000465 U	0.000283 U	0.000286 U	0.000833 U	0.000299 U	0.000409 U	0.00256 U	0.000312 U	0.000747 U
	MW-140-75	08/30/17	PES	ESC	75	-24.4	S	0.00631 U	0.00555 U	0.00744 U	0.0116 U	0.00712 U	0.00720 U	0.0209 U	0.00753 U	0.0103 U	0.0645 U	0.00785 U	0.0188 U
	MW-140-90	08/30/17	PES	ESC	90	-39.4	S	0.000275 U	0.000242 U	0.000325 U	0.000511 U	0.000311 U	0.000314 U	0.000915 U	0.000328 U	0.000449 U	0.00281 U	0.000342 U	0.000821 U
	MW-140-110	08/31/17	PES	ESC	110	-59.4	S	0.000271 U	0.000239 U	0.000320 U	0.000503 U	0.000306 U	0.000309 U	0.000901 U	0.000323 U	0.000442 U	0.00277 U	0.000337 U	0.000808 U
	MW-140-130	08/31/17	PES	ESC	130	-79.4	S	0.000265 U	0.000233 U	0.000312 U	0.000491 U	0.000298 U	0.000302 U	0.000880 U	0.000315 U	0.000432 U	0.00270 U	0.000329 U	0.000789 U
	MW-140-140	08/31/17	PES	ESC	140	-89.4	S	0.00661 U	0.00582 U	0.00779 U	0.0122 U	0.00745 U	0.00754 U	0.0219 U	0.00788 U	0.0108 U	0.0675 U	0.00822 U	0.0197 U
MW-142 (2.4 to -7.6)	MW-142-5	04/12/18	PES	ESC	5	37.1	V	0.000282 U	0.000248 U	0.000332 U	0.000522 U	0.000318 U	0.000321 U	0.000936 U	0.000336 U	0.000460 U	0.00288 U	0.000350 U	0.000840 U
MW-143 (-27.7 to -37.7)	MW-143-10	04/11/18	PES	ESC	10	32.0	V	0.000324 U	0.000286 U	**0.000499 J**	0.000602 U	0.000366 U	0.000370 U	0.00108 U	0.000387 U	0.000530 U	0.00331 U	0.000403 U	0.000968 U
	MW-143-20	04/11/18	PES	ESC	20	22.0	S	0.000272 U	0.000239 U	0.000321 U	0.000504 U	0.000307 U	0.000310 U	0.000904 U	0.000324 U	0.000444 U	0.00278 U	0.000338 U	0.000811 U
	MW-143-30	04/11/18	PES	ESC	30	12.0	S	0.000266 U	0.000235 U	0.000314 U	0.000494 U	0.000301 U	0.000304 U	0.000886 U	0.000318 U	0.000435 U	0.00272 U	**0.000928 J**	0.000795 U
	MW-143-40	04/11/18	PES	ESC	40	2.0	S	0.000279 U	0.000246 U	0.000329 U	0.000518 U	0.000315 U	0.000318 U	0.000928 U	0.000333 U	0.000456 U	0.00285 U	**0.000521 J**	0.000833 U
	MW-143-50	04/11/18	PES	ESC	50	-8.0	S	0.000268 U	0.000236 U	**0.00589**	0.000497 U	**0.00117**	0.000306 U	0.000891 U	**0.00729**	0.000438 U	0.00274 U	**0.0227**	0.000799 U
	MW-143-60	04/11/18	PES	ESC	60	-18.0	S	0.000260 U	0.000229 U	**0.00270**	0.000482 U	**0.00136**	0.000297 U	0.000865 U	**0.000443 J**	0.000425 U	0.00266 U	**0.656**	0.000776 U
	MW-143-70	04/11/18	PES	ESC	70	-28.0	S	0.000257 U	0.000227 U	**0.00164**	0.000477 U	0.000290 U	0.000294 U	0.000856 U	**0.00106 J**	0.000420 U	0.00263 U	**0.0137**	0.000768 U
	MW-143-80	04/11/18	PES	ESC	80	-38.0	S	0.000266 U	0.000234 U	0.000314 U	0.000493 U	0.000300 U	0.000303 U	0.000884 U	0.000317 U	0.000434 U	0.00272 U	**0.00320**	0.000793 U
	MW-902-20	04/11/18	PES	ESC	80 (dup)	-38.0	S	0.000262 U	0.000231 U	0.000309 U	0.000486 U	0.000295 U	0.000299 U	0.000871 U	0.000312 U	0.000427 U	0.00267 U	**0.00587**	0.000781 U
MW-145 (-26.1 to -36.1)	MW-145-10	04/17/18	PES	ESC	10	33.5	V	0.000294 U	0.000259 U	0.000347 U	0.000545 U	0.000332 U	0.000335 U	0.000977 U	0.000351 U	0.000480 U	0.00300 U	0.000366 U	0.000877 U
	MW-145-20	04/17/18	PES	ESC	20	23.5	S	0.000273 U	0.000241 U	**0.000505 J**	0.000507 U	0.000308 U	0.000312 U	0.000908 U	**0.000332 J**	0.000446 U	0.00279 U	0.000340 U	0.000815 U
	MW-145-30	04/17/18	PES	ESC	30	13.5	S	0.000277 U	0.000244 U	**0.790**	0.000515 U	**0.00118 J**	0.000317 U	0.000923 U	**0.0668**	0.000453 U	0.00283 U	0.000345 U	0.000828 U
	MW-145-40	04/17/18	PES	ESC	40	3.5	S	0.000261 U	0.000230 U	**0.00641**	0.000484 U	0.000294 U	0.000298 U	0.000867 U	**0.00474**	0.000426 U	0.00266 U	**0.0160**	0.000778 U
	MW-145-50	04/17/18	PES	ESC	50	-6.5	S	0.000256 U	0.000226 U	**0.00390**	0.000476 U	0.000289 U	0.000293 U	0.000852 U	**0.00180**	0.000419 U	0.00262 U	**0.00329**	**0.00329**
	MW-145-60	04/17/18	PES	ESC	60	-16.5	S	0.000258 U	0.000227 U	0.000304 U	0.000478 U	0.000291 U	0.000294 U	0.000858 U	0.000308 U	0.000421 U	0.00263 U	**0.00255**	0.000769 U
	MW-145-70	04/17/18	PES	ESC	70	-26.5	S	0.000284 U	0.000250 U	0.000335 U	0.000526 U	0.000320 U	0.000324 U	0.000944 U	0.000338 U	0.000463 U	0.00290 U	**0.000544 J**	0.000847 U
	MW-145-80	04/17/18	PES	ESC	80	-36.5	S	0.000269 U	0.000237 U	**0.000464 J**	0.000498 U	0.000303 U	0.000307 U	0.000894 U	0.000320 U	0.000439 U	0.00274 U	**0.000723 J**	0.000802 U
	MW-903-40	04/17/18	PES	ESC	80 (dup)	-36.5	S	0.000262 U	0.000231 U	**0.000450 J**	0.000487 U	0.000296 U	0.000299 U	0.000873 U	0.000313 U	0.000428 U	0.00268 U	**0.00180**	0.000783 U
MW-147 (-17.6 to -27.6)	MW-147-10	04/02/18	PES	ESC	10	41.9	V	0.000254 U	0.000224 U	**0.000697 J**	0.000471 U	0.000287 U	0.000290 U	0.000845 U	0.000303 U	0.000415 U	0.00260 U	0.000316 U	0.000758 U
	MW-147-20	04/02/18	PES	ESC	20	31.9	S	0.000253 U	0.000223 U	**0.000759 J**	0.000469 U	0.000285 U	0.000289 U	0.000841 U	0.000302 U	0.000413 U	0.00258 U	0.000314 U	0.000754 U
	MW-147-30	04/02/18	PES	ESC	30	21.9	S	0.000261 U	0.000230 U	**0.0238**	0.000485 U	0.000295 U	0.000298 U	0.000869 U	**0.00330**	0.000427 U	0.00267 U	0.000325 U	0.000779 U
	MW-147-40	04/02/18	PES	ESC	40	11.9	S	0.000258 U	0.000227 U	**0.0146**	0.000479 U	0.000291 U	0.000295 U	0.000858 U	**0.00118**	0.000421 U	0.00264 U	**0.0615**	0.000770 U
	MW-147-50	04/02/18	PES	ESC	50	1.9	S	0.000259 U	0.000228 U	**0.00175**	0.000481 U	0.000292 U	0.000296 U	0.000862 U	**0.00105 J**	0.000423 U	0.00265 U	**0.00322**	0.000773 U
	MW-147-60	04/02/18	PES	ESC	60	-8.2	S	0.000252 U	0.000221 U	**0.000607 J**	0.000467 U	0.000284 U	0.000287 U	0.000837 U	0.000300 U	0.000411 U	0.00257 U	0.000313 U	0.000751 U
	MW-901-10	04/02/18	PES	ESC	60 (dup)	-8.2	S	0.000252 U	0.000222 U	**0.000377 J**	0.000467 U	0.000284 U	0.000288 U	0.000838 U	0.000300 U	0.000411 U	0.00257 U	0.000313 U	0.000752 U
	MW-147-70	04/02/18	PES	ESC	70	-18.2	S	0.000262 U	0.000231 U	0.000309 U	0.000486 U	0.000295 U	0.000299 U	0.000871 U	0.000312 U	0.000428 U	0.00267 U	**0.000502 J**	0.000781 U
	MW-147-80	04/02/18	PES	ESC	80	-28.2	S	0.000271 U	0.000238 U	0.000319 U	0.000502 U	0.000305 U	0.000309 U	0.000900 U	0.000323 U	0.000442 U	0.00277 U	0.000337 U	0.000808 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
MW-148	MW-148-11	04/09/18	PES	ESC	11	32.9	V	0.000270 U	0.000238 U	0.000318 U	0.000501 U	0.000305 U	0.000308 U	0.000898 U	0.000322 U	0.000441 U	0.00276 U	0.000336 U	0.000805 U
(-25.7 to -35.7)	MW-148-20	04/09/18	PES	ESC	20	23.9	S	0.000254 U	0.000223 U	**0.00188**	0.000471 U	0.000286 U	0.000290 U	0.000844 U	0.000303 U	0.000414 U	0.00259 U	0.000316 U	0.000757 U
	MW-148-30	04/09/18	PES	ESC	30	13.9	S	0.000263 U	0.000231 U	0.000310 U	0.000487 U	0.000296 U	0.000300 U	0.000874 U	0.000313 U	0.000429 U	0.00268 U	**0.0144**	0.000784 U
	MW-148-40	04/09/18	PES	ESC	40	3.9	S	0.000254 U	0.000224 U	**0.000801 J**	0.000471 U	0.000287 U	0.000290 U	0.000845 U	**0.000551 J**	0.000415 U	0.00260 U	0.000316 U	0.000758 U
	MW-148-50	04/09/18	PES	ESC	50	-6.1	S	0.000258 U	0.000227 U	0.000304 U	0.000479 U	0.000291 U	0.000294 U	0.000858 U	0.000308 U	0.000421 U	0.00264 U	0.000321 U	0.000770 U
	MW-148-60	04/09/18	PES	ESC	60	-16.1	S	0.000295 U	0.000260 U	0.000348 U	0.000548 U	0.000333 U	0.000337 U	0.000982 U	0.000352 U	0.000482 U	0.00302 U	0.000367 U	0.000881 U
	MW-148-70	04/09/18	PES	ESC	70	-26.1	S	0.000295 U	0.000260 U	**0.000618 J**	0.000547 U	0.000333 U	0.000336 U	0.000980 U	0.000352 U	0.000481 U	0.00301 U	0.000367 U	0.000880 U
	MW-148-80	04/09/18	PES	ESC	80	-36.1	S	0.000275 U	0.000242 U	**0.000585 J**	0.000510 U	0.000310 U	0.000314 U	0.000914 U	0.000328 U	0.000449 U	0.00281 U	0.000342 U	0.000820 U
MW-153	MW-153-10	03/27/18	PES	ESC	10	44.4	V	0.000265 U	0.000234 U	0.000313 U	0.000492 U	0.000299 U	0.000303 U	0.000882 U	0.000316 U	0.000433 U	0.00271 U	0.000330 U	0.000792 U
(-65.3 to -75.3)	MW-153-20	03/27/18	PES	ESC	20	34.4	V	0.000256 U	0.000225 U	**0.000561 J**	0.000475 U	0.000289 U	0.000292 U	0.000852 U	0.000305 U	0.000418 U	0.00262 U	0.000318 U	0.000764 U
	MW-153-30	03/27/18	PES	ESC	30	24.4	S	0.000251 U	0.000221 U	0.000296 U	0.000466 U	0.000283 U	0.000286 U	0.000835 U	0.000299 U	0.000410 U	0.00256 U	0.000312 U	0.000749 U
	MW-153-40	03/27/18	PES	ESC	40	14.4	S	0.000265 U	0.000233 U	0.000313 U	0.000492 U	0.000299 U	0.000302 U	0.000881 U	**0.000486 J**	0.000433 U	0.00271 U	0.000330 U	0.000791 U
	MW-153-50	03/27/18	PES	ESC	50	4.4	S	0.000260 U	0.000228 U	0.000306 U	0.000481 U	0.000293 U	0.000296 U	0.000863 U	0.000309 U	0.000424 U	0.00265 U	**0.00767**	0.000774 U
	MW-153-61	03/27/18	PES	ESC	61	-6.7	S	0.000266 U	0.000234 U	0.000314 U	0.000493 U	0.000300 U	0.000303 U	0.000884 U	0.000317 U	0.000434 U	0.00272 U	**0.000344 J**	0.000793 U
	MW-153-70	03/27/18	PES	ESC	70	-15.7	S	0.000261 U	0.000229 U	0.000307 U	0.000483 U	0.000294 U	0.000297 U	0.000866 U	0.000311 U	0.000425 U	0.00266 U	**0.000902 J**	0.000777 U
	MW-153-80	03/28/18	PES	ESC	80	-25.7	S	0.000258 U	0.000227 U	0.000305 U	0.000479 U	0.000291 U	0.000295 U	0.000858 U	0.000308 U	0.000421 U	0.00264 U	**0.00148**	0.000770 U
	MW-153-90	03/28/18	PES	ESC	90	-35.7	S	0.000282 U	0.000248 U	**0.000799 J**	0.000523 U	0.000318 U	0.000322 U	0.000937 U	0.000336 U	0.000460 U	0.00288 U	**0.00176**	0.000841 U
	MW-153-110	03/28/18	PES	ESC	110	-55.7	S	0.000275 U	0.000242 U	**0.00254**	0.000511 U	0.000311 U	0.000314 U	0.000916 U	0.000328 U	0.000450 U	0.00281 U	**0.00311**	0.000821 U
	MW-153-130	03/29/18	PES	ESC	130	-75.7	S	0.000269 U	0.000237 U	**0.000648 J**	0.000499 U	0.000303 U	0.000307 U	0.000894 U	0.000321 U	0.000439 U	0.00275 U	0.000334 U	0.000802 U
MW-158	MW-158-20	04/05/18	PES	ESC	20	21.1	S	0.000265 U	0.000233 U	0.000313 U	0.000492 U	0.000299 U	0.000302 U	0.000881 U	0.000316 U	0.000433 U	0.00271 U	0.000330 U	0.000791 U
	MW-158-30	04/05/18	PES	ESC	30	11.1	S	0.0276 U	0.0243 U	**15.1**	**0.0512**	0.0311 U	0.0315 U	0.0918 U	**3.57**	0.0451 U	0.282 U	**0.382**	0.0823 U
MW-158A	MW-158A-40	04/05/18	PES	ESC	40	1.1	S	0.000288 U	0.000254 U	**1.76**	**0.000626 J**	**0.000547 J**	0.000329 U	0.000959 U	**0.684**	0.000471 U	0.00295 U	**0.00972**	0.000860 U
(-47.2 to -58.5)	MW-158A-50	04/05/18	PES	ESC	50	-8.9	S	0.000271 U	0.000238 U	**0.922**	0.000502 U	**0.000423 J**	0.000309 U	0.000900 U	**0.0628**	0.000442 U	0.00276 U	**0.000709 J**	0.000807 U
	MW-158A-60	04/05/18	PES	ESC	60	-18.9	S	0.000269 U	0.000237 U	**4.08**	0.000499 U	**0.000810 J**	0.000307 U	0.000895 U	**0.0528**	0.000440 U	0.00275 U	**0.000703 J**	0.000803 U
	MW-158A-70	04/05/18	PES	ESC	70	-28.9	S	0.000263 U	0.000231 U	**0.00466**	0.000487 U	**0.000460 J**	0.000300 U	0.000873 U	**0.0431**	0.000429 U	0.00268 U	**0.0164**	0.000783 U
	MW-158A-80	04/06/18	PES	ESC	80	-38.9	S	0.000260 U	0.000228 U	**0.00242**	0.000481 U	0.000293 U	0.000296 U	0.000863 U	**0.000599 J**	0.000424 U	0.00265 U	**0.000339 J**	0.000774 U
	MW-158A-90	04/06/18	PES	ESC	90	-48.9	S	0.000268 U	0.000236 U	**0.00622**	0.000498 U	0.000303 U	0.000306 U	0.000893 U	**0.00209**	0.000438 U	0.00274 U	**0.00160**	0.000801 U
	MW-158A-100	04/06/18	PES	ESC	100	-58.9	S	0.000275 U	0.000242 U	**0.00683**	0.000510 U	0.000310 U	0.000314 U	0.000914 U	**0.00229**	0.000449 U	0.00281 U	**0.000880 J**	0.000820 U
MW-159	MW-159-20	04/16/18	PES	ESC	20	22.8	S	0.000283 U	0.000249 U	0.000334 U	0.000525 U	0.000319 U	0.000323 U	0.000941 U	0.000337 U	0.000462 U	0.00289 U	0.000352 U	0.000844 U
(22.9 to 12.9)	MW-159-30	04/16/18	PES	ESC	30	12.8	S	0.000285 U	0.000251 U	**0.0196**	0.000529 U	**0.000365 J**	0.000325 U	0.000948 U	**0.0234**	0.000466 U	0.00291 U	0.000355 U	0.000851 U
MW-160	MW-160-11	05/08/18	PES	ESC	11	31.5	S	0.00442 U	0.00251 U	0.00114 U	**0.00635 J**	0.00232 U	0.00249 U	0.00228 U	0.000649 U	0.000812 U	0.00571 U	0.00110 U	0.00776 U
(-76.5 to -86.5)	MW-160-21	05/08/18	PES	ESC	21	21.5	S	0.00320 U	0.00182 U	**0.000966 J**	**0.00421 J**	0.00168 U	0.00179 U	0.00164 U	0.000469 U	0.000586 U	0.00413 U	0.000801 U	0.00560 U
	MW-160-31	05/08/18	PES	ESC	31	11.5	S	0.00331 U	0.00188 U	0.000849 U	**0.00285 J**	0.00173 U	0.00186 U	0.00170 U	0.000485 U	0.000606 U	0.00427 U	0.000828 U	0.00580 U
	MW-160-40	05/08/18	PES	ESC	40	2.5	S	0.00310 U	0.00176 U	**0.281**	**0.00196 J**	**0.00373 J**	0.00174 U	0.00159 U	**0.100**	0.000568 U	0.00400 U	0.000775 U	0.00543 U
	MW-160-50	05/08/18	PES	ESC	50	-7.5	S	0.00312 U	0.00177 U	**0.00276 J**	**0.00144 J**	0.00163 U	0.00175 U	0.00160 U	**0.000714 J**	0.000571 U	0.00402 U	0.000780 U	0.00546 U
	MW-160-55	05/08/18	PES	ESC	55	-12.5	S	0.00324 U	0.00184 U	**6.27**	**0.00185 J**	**0.0221**	0.00181 U	0.00166 U	**1.11**	0.000593 U	0.00418 U	**0.0107**	0.00567 U
	MW-160-60	05/08/18	PES	ESC	60	-17.5	S	0.00297 U	0.00169 U	**0.111**	**0.00595**	**0.00162 J**	0.00167 U	0.00153 U	**0.0907**	0.000545 U	0.00384 U	0.000744 U	0.00521 U
	MW-160-70	05/08/18	PES	ESC	70	-27.5	S	0.00319 U	0.00181 U	**0.00208 J**	**0.00221 J**	0.00167 U	0.00179 U	0.00164 U	**0.00150**	0.000584 U	0.00411 U	0.000798 U	0.00558 U
	MW-160-90	05/08/18	PES	ESC	90	-47.5	S	0.00321 U	0.00182 U	0.000824 U	**0.00240 J**	0.00168 U	0.00180 U	0.00165 U	**0.00151**	0.000588 U	0.00414 U	0.000804 U	0.00563 U
	MW-160-100	05/08/18	PES	ESC	100	-57.5	S	0.00328 U	0.00186 U	0.000842 U	0.00150 U	0.00172 U	0.00184 U	0.00168 U	**0.00153**	0.000601 U	0.00423 U	0.000822 U	0.00575 U
	MW-160-110	05/08/18	PES	ESC	110	-67.5	S	0.00310 U	0.00176 U	**0.0113**	**0.00144 J**	0.00162 U	0.00173 U	0.00159 U	**0.00478**	0.000567 U	0.00399 U	0.000774 U	0.00542 U
	MW-160-125	05/10/18	PES	ESC	125	-82.5	S	0.00313 U	0.00177 U	**0.00262 J**	**0.00265 J**	0.00164 U	0.00175 U	0.00160 U	**0.000576 J**	0.000572 U	0.00403 U	0.000782 U	0.00547 U
	MW-160-127.5	05/10/18	PES	ESC	128	-85.0	S	0.00315 U	0.00179 U	0.000808 U	0.00144 U	0.00165 U	0.00177 U	0.00162 U	0.000462 U	0.000577 U	0.00406 U	0.000789 U	0.00552 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
MW-161 (-78.9 to -88.9)	MW-161-11	05/14/18	PES	ESC	11	32.8	S	0.00336 U	0.00191 U	**0.00523**	0.00615 U	0.00615 U	0.00188 U	–	0.00123 U	0.000615 U	–	0.00307 U	0.00799 U
	MW-161-21	05/14/18	PES	ESC	21	22.8	S	0.00284 U	0.00161 U	0.00260 U	0.00520 U	0.00520 U	0.00159 U	–	0.00104 U	0.000520 U	–	0.00260 U	0.00676 U
	MW-161-31	05/14/18	PES	ESC	31	12.8	S	0.00313 U	0.00177 U	**0.0159**	0.00572 U	0.00572 U	0.00175 U	–	**0.00196**	0.000572 U	–	0.00286 U	0.00744 U
	MW-161-40	05/14/18	PES	ESC	40	3.8	S	0.00301 U	0.00171 U	**0.00438**	0.00552 U	0.00552 U	0.00169 U	–	**0.00132**	0.000552 U	–	0.00276 U	0.00717 U
	MW-161-50	05/14/18	PES	ESC	50	-6.2	S	0.00305 U	0.00173 U	**0.0173**	0.00558 U	0.00558 U	0.00171 U	–	**0.00956**	0.000558 U	–	0.00279 U	0.00725 U
	MW-161-60	05/14/18	PES	ESC	60	-16.2	S	0.00312 U	0.00177 U	**0.0356**	0.00571 U	0.00571 U	0.00175 U	–	**0.00328**	0.000571 U	–	0.00286 U	0.00742 U
	MW-161-70	05/14/18	PES	ESC	70	-26.2	S	0.00305 U	0.00173 U	0.00279 U	0.00558 U	0.00558 U	0.00171 U	–	0.00112 U	0.000558 U	–	0.00279 U	0.00726 U
	MW-161-80	05/14/18	PES	ESC	80	-36.2	S	0.00337 U	0.00191 U	0.00308 U	0.00616 U	0.00616 U	0.00189 U	–	0.00123 U	0.000616 U	–	0.00308 U	0.00801 U
	MW-161-90	05/14/18	PES	ESC	90	-46.2	S	0.00311 U	0.00176 U	0.00285 U	0.00569 U	0.00569 U	0.00174 U	–	0.00114 U	0.000569 U	–	0.00285 U	0.00740 U
	B-927-30	05/14/18	PES	ESC	90 (dup)	-46.2	S	0.00339 U	0.00192 U	0.00310 U	0.00621 U	0.00621 U	0.00190 U	–	0.00124 U	0.000621 U	–	0.00310 U	0.00807 U
	MW-161-100	05/14/18	PES	ESC	100	-56.2	S	0.00318 U	0.00180 U	0.00291 U	0.00582 U	0.00582 U	0.00178 U	–	0.00116 U	0.000582 U	–	0.00291 U	0.00757 U
	MW-161-110	05/14/18	PES	ESC	110	-66.2	S	0.00333 U	0.00189 U	0.00305 U	0.00610 U	0.00610 U	0.00187 U	–	0.00122 U	0.000610 U	–	0.00305 U	0.00793 U
	MW-161-120	05/14/18	PES	ESC	120	-76.2	S	0.00333 U	0.00189 U	0.00305 U	0.00610 U	0.00610 U	0.00187 U	–	0.00122 U	0.000610 U	–	0.00305 U	0.00793 U
	MW-161-130	05/14/18	PES	ESC	130	-86.2	S	0.00300 U	0.00170 U	**0.0307**	0.00550 U	0.00550 U	0.00168 U	–	**0.0114**	0.000550 U	–	0.00275 U	0.00715 U
	MW-161-140	05/15/18	PES	ESC	140	-96.2	S	0.00335 U	0.00190 U	0.000858 U	**0.00175 J**	0.00175 U	0.00188 U	0.00172 U	0.000490 U	0.000613 U	0.00431 U	0.000837 UJ	0.00586 U
MW-190 (-30.2 to -40.2)	MW-190-5	09/19/19	PES	PACE	5	43.7	V	0.00315 U	0.00179 U	**0.0166**	**0.00891**	0.00165 U	0.00176 U	0.00161 U	0.000461 U	0.000577 U	0.00406 U	0.000788 U	0.00551 U
	MW-190-10	09/19/19	PES	PACE	10	38.7	V	0.00565 U	0.00321 U	**0.0965**	**0.0371**	0.00296 U	0.00317 U	0.00289 U	0.000827 U	0.00103 U	0.00728 U	0.00141 U	**0.0280**
	MW-190-15	09/19/19	PES	PACE	15	33.7	S	0.00361 U	0.00205 U	0.000927 U	**0.0200**	0.00189 U	0.00203 U	0.00185 U	0.000530 U	0.000662 U	0.00466 U	0.000904 U	0.00633 U
	MW-190-20	09/19/19	PES	PACE	20	28.7	S	0.00340 U	0.00193 U	0.000871 U	**0.0172**	0.00178 U	0.00190 U	0.00174 U	0.000498 U	0.000622 U	0.00438 U	**0.00116 J**	0.00595 U
	MW-190-25	09/19/19	PES	PACE	25	23.7	S	0.00320 U	0.00182 U	0.000822 U	**0.0138**	0.00168 U	0.00180 U	0.00164 U	0.000470 U	0.000587 U	0.00413 U	0.000802 U	0.00561 U
	MW-190-30	09/19/19	PES	PACE	30	18.7	S	0.00286 U	0.00162 U	**0.0585**	**0.0122**	0.00150 U	0.00160 U	0.00147 U	**0.0109**	0.000524 U	0.00369 U	0.000716 U	0.00501 U
	MW-190-35	09/19/19	PES	PACE	35	13.7	S	0.00290 U	0.00165 U	**0.0786**	**0.00948**	0.00152 U	0.00163 U	0.00149 U	**0.0108**	0.000531 U	0.00374 U	0.000726 U	0.00508 U
	MW-190-40	09/19/19	PES	PACE	40	8.7	S	0.00306 U	0.00174 U	**0.0108**	**0.0117**	0.00161 U	0.00172 U	0.00157 U	**0.00134**	0.000561 U	0.00395 U	0.000767 U	0.00537 U
	MW-190-45	09/19/19	PES	PACE	45	3.7	S	0.00312 U	0.00177 U	0.000800 U	**0.00557 J**	0.00163 U	0.00175 U	0.00160 U	0.000457 U	0.000572 U	0.00402 U	0.000781 U	0.00547 U
	MW-190-50	09/19/19	PES	PACE	50	-1.4	S	0.00286 U	0.00162 U	**0.00158 J**	**0.0175**	0.00150 U	0.00160 U	0.00147 U	0.000419 U	0.000524 U	0.00369 U	0.000715 U	0.00501 U
	MW-190-55	09/19/19	PES	PACE	55	-6.4	S	0.00296 U	0.00168 U	0.000759 U	**0.00877**	0.00155 U	0.00166 U	0.00152 U	0.000434 U	**0.00272**	0.00382 U	**0.00676**	0.00518 U
	MW-190-60	09/19/19	PES	PACE	60	-11.4	S	0.00297 U	0.00169 U	**0.00369 J**	**0.00549**	0.00156 U	0.00167 U	0.00153 U	0.000436 U	0.000545 U	0.00384 U	**0.0173**	0.00521 U
	MW-2008-60	09/19/19	PES	PACE	60 (dup)	-11.4	S	0.00295 U	0.00168 U	**0.00950 J**	**0.0129**	0.00155 U	0.00165 U	0.00151 U	0.000432 U	0.000540 U	0.00380 U	**0.0138**	0.00517 U
	MW-190-65	09/19/19	PES	PACE	65	-16.4	S	0.00301 U	0.00171 U	0.000773 U	**0.0191**	0.00158 U	0.00169 U	0.00155 U	0.000442 U	0.000552 U	0.00389 U	0.000754 U	0.00528 U
	MW-190-70	09/19/19	PES	PACE	70	-21.4	S	0.00302 U	0.00172 U	0.000775 U	**0.00717**	0.00158 U	0.00169 U	0.00155 U	0.000443 U	0.000554 U	0.00390 U	0.000757 U	0.00529 U
	MW-190-75	09/19/19	PES	PACE	75	-26.4	S	0.00298 U	0.00169 U	0.000765 U	**0.00803**	0.00156 U	0.00167 U	0.00153 U	0.000437 U	0.000547 U	0.00385 U	0.000747 U	0.00523 U
	MW-190-80	09/19/19	PES	PACE	80	-31.4	S	0.00298 U	0.00169 U	**0.00132 J**	**0.0117**	0.00156 U	0.00167 U	0.00153 U	0.000437 U	0.000546 U	0.00384 U	0.000746 U	0.00522 U
	MW-190-85	09/19/19	PES	PACE	85	-36.4	S	0.00314 U	0.00178 U	0.000805 U	**0.00843**	0.00164 U	0.00176 U	0.00161 U	0.000460 U	0.000575 U	0.00405 U	0.000785 U	0.00550 U
	MW-190-87	09/19/19	PES	PACE	87	-38.4	S	0.00326 U	0.00185 U	0.000837 U	**0.00903**	0.00171 U	0.00183 U	0.00167 U	0.000478 U	0.000598 U	0.00421 U	0.000816 U	0.00571 U
MW-301 (35.6 to 25.6)	MW-301-6	09/20/19	PES	PACE	6	47.8	V	0.00320 U	0.00182 U	**0.00260 J**	**0.0191**	0.00168 U	0.00179 U	0.00164 U	0.000469 U	0.000586 U	0.00412 U	0.000800 U	0.00560 U
	MW-301-10	09/20/19	PES	PACE	10	43.8	V	0.00300 U	0.00170 U	**0.00463 J**	**0.00321 J**	0.00157 U	0.00168 U	0.00154 U	0.000440 U	0.000550 U	0.00387 U	0.000751 U	0.00526 U
	MW-301-15	09/20/19	PES	PACE	15	38.8	V	0.00310 U	0.00176 U	**0.00396 J**	**0.0258**	0.00162 U	0.00174 U	0.00159 U	0.000454 U	0.000568 U	0.00400 U	0.000775 U	0.00543 U
	MW-301-20	09/20/19	PES	PACE	20	33.8	S	0.00922 U	0.00523 U	**0.00927 J**	**0.0402**	0.00483 U	0.00516 U	0.00473 U	0.00135 U	0.00169 U	0.0119 U	0.00231 U	0.0162 U
	MW-301-25	09/20/19	PES	PACE	25	28.8	S	0.00310 U	0.00176 U	**0.0326 J**	**0.0329**	0.00163 U	0.00174 U	0.00159 U	**0.00173**	0.000568 U	0.00400 U	0.000776 U	0.00543 U
	MW-301-30	09/20/19	PES	PACE	30	23.8	S	0.00338 U	0.00191 U	**0.0141 J**	**0.0376**	0.00177 U	0.00189 U	0.00174 U	0.000495 U	0.000619 U	0.00436 U	0.000845 U	0.00592 U
MW-302 (3.0 to -7.0)	MW-302-5	10/01/19	PES	PACE	5	52.3	V	0.00320 U	0.00182 U	**0.0461**	**0.00938**	0.00167 U	0.00179 U	0.00164 U	0.000468 U	0.000585 U	0.00412 UJ	0.000800 U	**0.00584 J**
	MW-302-10	10/01/19	PES	PACE	10	47.3	V	0.00340 U	0.00193 U	0.000871 U	0.00156 U	0.00178 U	0.00190 U	0.00174 U	0.000498 U	0.000622 U	0.00438 UJ	0.000850 U	0.00595 U
	MW-302-15	10/01/19	PES	PACE	15	42.3	V	0.00373 U	0.00212 U	**0.00215 J**	**0.0142**	0.00195 U	0.00208 U	0.00190 U	0.000545 U	0.000682 U	0.00480 UJ	0.000931 U	0.00651 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
MW-302 (continued)	MW-302-20	10/01/19	PES	PACE	20	37.3	S	0.00326 U	0.00185 U	**0.00541**	**0.00524 J**	0.00171 U	0.00183 U	0.00167 U	0.000477 U	0.000597 U	0.00420 UJ	0.000815 U	0.00570 U
	MW-302-25	10/01/19	PES	PACE	25	32.3	S	0.00306 U	0.00174 U	0.000784 U	**0.00443 J**	0.00160 U	0.00171 U	0.00157 U	0.000448 U	0.000560 U	0.00394 UJ	0.000765 U	0.00536 U
	MW-302-30	10/01/19	PES	PACE	30	27.3	S	0.00299 U	0.00170 U	0.000766 U	**0.00287 J**	0.00156 U	0.00167 U	0.00153 U	0.000438 U	0.000547 U	0.00385 UJ	0.000747 U	0.00523 U
	MW-302-35	10/01/19	PES	PACE	35	22.3	S	0.00293 U	0.00167 U	0.000752 U	**0.00440 J**	0.00154 U	0.00164 U	0.00150 U	0.000430 U	0.000537 U	0.00378 UJ	0.000734 U	0.00514 U
	MW-302-40	10/01/19	PES	PACE	40	17.3	S	0.00290 U	0.00165 U	0.000745 U	**0.00484 J**	0.00152 U	0.00163 U	0.00149 U	0.000425 U	0.000532 U	0.00374 UJ	0.000727 U	0.00508 U
	MW-302-45	10/01/19	PES	PACE	45	12.3	S	0.00325 U	0.00185 U	0.000834 U	**0.0222**	0.00170 U	0.00182 U	0.00167 U	0.000477 U	0.000596 U	0.00419 UJ	0.000814 U	0.00570 U
	MW-302-50	10/01/19	PES	PACE	50	7.3	S	0.00326 U	0.00185 U	0.000836 U	**0.0158**	0.00171 U	0.00183 U	0.00167 U	0.000478 U	0.000597 U	0.00420 UJ	0.000816 U	0.00571 U
	MW-302-55	10/01/19	PES	PACE	55	2.3	S	0.00310 U	0.00176 U	0.000795 U	**0.00449 J**	0.00162 U	0.00174 U	0.00159 U	0.000455 U	0.000568 U	0.00400 UJ	0.000776 U	0.00543 U
	MW-302-60	10/01/19	PES	PACE	60	-2.7	S	0.00389 U	0.00220 U	0.000995 U	**0.0216**	0.00204 U	0.00218 U	0.00199 U	0.000569 U	0.000711 U	0.00500 UJ	0.000971 U	0.00680 U
	MW-302-65	10/01/19	PES	PACE	65	-7.7	S	0.00320 U	0.00182 U	0.000820 U	**0.00508 J**	0.00167 U	0.00179 U	0.00164 U	0.000468 U	0.000586 U	0.00412 UJ	0.000800 U	0.00560 U
	MW-2014-65	10/01/19	PES	PACE	65 (dup)	-7.7	S	0.00331 U	0.00188 U	0.000849 U	**0.0138**	0.00173 U	0.00185 U	0.00170 U	0.000485 U	0.000606 U	0.00427 UJ	0.000828 U	0.00579 U
MW-304 (-47.6 to -57.6)	MW-304-5	10/01/19	PES	PACE	5	52.6	V	0.00307 U	0.00175 U	**0.0250**	**0.00212 J**	0.00161 U	0.00172 U	0.00158 U	0.000451 U	0.000563 U	0.00396 U	0.000769 U	0.00538 U
	MW-304-10	10/01/19	PES	PACE	10	47.6	V	0.00311 U	0.00177 U	**0.0198**	**0.00202 J**	0.00163 U	0.00174 U	0.00160 U	0.000456 U	0.000570 U	0.00401 U	0.000778 U	0.00545 U
	MW-304-15	10/01/19	PES	PACE	15	42.6	V	0.00325 U	0.00184 U	**0.00806**	0.00149 U	0.00170 U	0.00182 U	0.00166 U	0.000476 U	0.000595 U	0.00419 U	0.000812 U	0.00568 U
	MW-304-20	10/01/19	PES	PACE	20	37.6	S	0.00322 U	0.00183 U	0.000824 U	**0.00496 J**	0.00168 U	0.00180 U	0.00165 U	0.000471 U	0.000589 U	0.00415 U	0.000804 U	0.00563 U
	MW-304-25	10/01/19	PES	PACE	25	32.6	S	0.00299 U	0.00170 U	0.000766 U	0.00137 U	0.00156 U	0.00167 U	0.00153 U	0.000438 U	0.000547 U	0.00385 U	0.000747 U	0.00523 U
	MW-304-30	10/01/19	PES	PACE	30	27.6	S	0.00321 U	0.00182 U	0.000823 U	0.00147 U	0.00168 U	0.00180 U	0.00165 U	0.000470 U	0.000588 U	0.00414 U	0.000803 U	0.00562 U
	MW-304-40	10/01/19	PES	PACE	40	17.6	S	0.00296 U	0.00168 U	0.000760 U	**0.00211 J**	0.00155 U	0.00166 U	0.00152 U	0.000434 U	0.000543 U	0.00382 U	0.000741 U	0.00519 U
	MW-304-45	10/01/19	PES	PACE	45	12.6	S	0.00277 U	0.00157 U	0.000711 U	**0.00130 J**	0.00145 U	0.00155 U	0.00142 U	0.000406 U	0.000508 U	0.00358 U	0.000694 U	0.00486 U
	MW-304-50	10/01/19	PES	PACE	50	7.6	S	0.00294 U	0.00167 U	0.000754 U	**0.00241 J**	0.00154 U	0.00165 U	0.00151 U	0.000431 U	0.000538 U	0.00379 U	0.000735 U	0.00515 U
	MW-304-55	10/01/19	PES	PACE	55	2.6	S	0.00275 U	0.00156 U	0.000706 U	**0.00212 J**	0.00144 U	0.00154 U	0.00141 U	0.000403 U	0.000504 U	0.00355 U	0.000688 U	0.00482 U
	MW-304-60	10/01/19	PES	PACE	60	-2.4	S	0.00288 U	0.00163 U	0.000738 U	**0.00355 J**	0.00151 U	0.00161 U	0.00148 U	0.000422 U	0.000527 U	0.00371 U	0.000720 U	0.00504 U
	MW-304-65	10/01/19	PES	PACE	65	-7.4	S	0.00316 U	0.00180 U	0.000811 U	**0.00168 J**	0.00166 U	0.00177 U	0.00162 U	0.000463 U	0.000579 U	0.00408 U	0.000791 U	0.00554 U
	MW-304-70	10/01/19	PES	PACE	70	-12.4	S	0.00332 U	0.00188 U	0.000850 U	**0.00270 J**	0.00174 U	0.00186 U	0.00170 U	0.000486 U	0.000607 U	0.00428 U	0.000830 U	0.00581 U
	MW-304-75	10/01/19	PES	PACE	75	-17.4	S	0.00313 U	0.00177 U	0.000801 U	**0.0284**	**0.00185 J**	0.00175 U	0.00160 U	0.000458 U	0.000572 U	0.00403 U	0.000782 U	0.00547 U
	MW-304-80	10/01/19	PES	PACE	80	-22.4	S	0.00299 U	0.00170 U	0.000766 U	**0.00188 J**	0.00157 U	0.00167 U	0.00153 U	0.000438 U	0.000547 U	0.00385 U	0.000748 U	0.00523 U
	MW-304-85	10/01/19	PES	PACE	85	-27.4	S	0.00299 U	0.00170 U	0.000767 U	**0.00264 J**	0.00157 U	0.00168 U	0.00153 U	0.000438 U	0.000548 U	0.00386 U	0.000748 U	0.00524 U
	MW-304-90	10/01/19	PES	PACE	90	-32.4	S	0.00327 U	0.00186 U	0.000839 U	**0.00223 J**	0.00171 U	0.00183 U	0.00168 U	0.000480 U	0.000599 U	0.00422 U	0.000819 U	0.00573 U
	MW-304-95	10/01/19	PES	PACE	95	-37.4	S	0.00323 U	0.00184 U	0.000829 U	**0.00263 J**	0.00169 U	0.00181 U	0.00166 U	0.000474 U	0.000592 U	0.00417 UJ	0.000809 U	0.00566 U
	MW-2009-95	10/01/19	PES	PACE	95 (dup)	-37.4	S	0.00328 U	0.00186 U	0.000841 U	**0.00217 J**	0.00172 U	0.00184 U	0.00168 U	0.000481 U	0.000601 U	0.00423 UJ	0.000820 U	0.00574 U
	MW-304-100	10/02/19	PES	PACE	100	-42.4	S	0.00322 U	0.00183 U	0.000825 U	**0.00206 J**	0.00169 U	0.00180 U	0.00165 U	0.000471 U	0.000589 U	0.00415 UJ	0.000805 U	0.00563 U
	MW-304-105	10/02/19	PES	PACE	105	-47.4	S	0.00319 U	0.00181 U	0.000819 U	**0.00166 J**	0.00167 U	0.00179 U	0.00164 U	0.000468 U	0.000585 U	0.00412 UJ	0.000799 U	0.00559 U
	MW-304-110	10/02/19	PES	PACE	110	-52.4	S	0.00345 U	0.00196 U	0.000885 U	**0.00321 J**	0.00181 U	0.00193 U	0.00177 U	0.000506 U	0.000632 U	0.00445 UJ	0.000864 U	0.00604 U
	MW-304-115	10/02/19	PES	PACE	115	-57.4	S	0.00318 U	0.00181 U	0.000816 U	**0.00223 J**	0.00167 U	0.00178 U	0.00163 U	0.000466 U	0.000583 U	0.00410 UJ	0.000796 U	0.00557 U
MW-307 (-12.4 to -22.4)	MW-307-6	10/03/19	PES	PACE	6	54.5	V	0.00305 U	0.00173 U	0.000783 U	**0.0131**	0.00160 U	0.00171 U	0.00157 U	0.000447 U	0.000559 U	0.00394 U	0.000764 U	0.00534 U
	MW-307-10	10/03/19	PES	PACE	10	50.5	V	0.00314 U	0.00178 U	0.000806 U	**0.0260**	0.00165 U	0.00176 U	0.00161 U	0.000460 U	0.000576 U	0.00405 U	0.000786 U	0.00551 U
	MW-307-15	10/03/19	PES	PACE	15	45.5	V	0.00294 U	0.00167 U	0.000754 U	**0.00403 J**	0.00154 U	0.00165 U	0.00151 U	0.000431 U	0.000539 U	0.00379 U	0.000736 U	0.00515 U
	MW-307-20	10/03/19	PES	PACE	20	40.5	V	0.00292 U	0.00166 U	0.000749 U	**0.00602**	0.00153 U	0.00164 U	0.00150 U	0.000428 U	0.000535 U	0.00376 U	0.000730 U	0.00511 U
	MW-307-25	10/03/19	PES	PACE	25	35.5	S	0.00299 U	0.00170 U	0.000768 U	**0.00675**	0.00157 U	0.00168 U	0.00154 U	0.000439 U	0.000549 U	0.00386 U	0.000749 U	0.00524 U
	MW-307-30	10/03/19	PES	PACE	30	30.5	S	0.00402 U	0.00228 U	0.00103 U	**0.0148**	0.00211 U	0.00225 U	0.00206 U	0.000589 U	0.000737 U	0.00519 U	0.00101 U	0.00705 U
	MW-307-35	10/03/19	PES	PACE	35	25.5	S	0.00292 U	0.00166 U	0.000749 U	**0.0111**	0.00153 U	0.00164 U	0.00150 U	0.000428 U	0.000535 U	0.00377 U	0.000731 U	0.00511 U
	MW-307-40	10/03/19	PES	PACE	40	20.5	S	0.00312 U	0.00177 U	0.000799 U	**0.00815**	0.00163 U	0.00175 U	0.00160 U	0.000457 U	0.000571 U	0.00402 U	0.000780 U	0.00546 U
	MW-307-45	10/03/19	PES	PACE	45	15.5	S	0.00301 U	0.00171 U	0.000772 U	**0.00846**	0.00158 U	0.00169 U	0.00154 U	0.000441 U	0.000551 U	0.00388 U	0.000753 U	0.00527 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
MW-307 (continued)	MW-307-50	10/03/19	PES	PACE	50	10.5	S	0.00304 U	0.00172 U	0.000778 U	**0.0157**	0.00159 U	0.00170 U	0.00156 U	0.000445 U	0.000556 U	0.00391 U	0.000759 U	0.00532 U
	MW-307-55	10/03/19	PES	PACE	55	5.5	S	0.00296 U	0.00168 U	0.000760 U	**0.0104**	0.00155 U	0.00166 U	0.00152 U	0.000434 U	0.000543 U	0.00382 U	0.000742 U	0.00519 U
	MW-307-60	10/03/19	PES	PACE	60	0.5	S	0.00308 U	0.00175 U	0.000790 U	**0.00583**	0.00161 U	0.00173 U	0.00158 U	0.000452 U	0.000565 U	0.00397 UJ	0.000771 U	0.00540 U
	MW-307-65	10/03/19	PES	PACE	65	-4.5	S	0.00628 U	0.00357 U	0.00161 U	**0.0687**	0.00329 U	0.00352 U	0.00323 U	0.000921 U	0.00115 U	0.00810 UJ	0.00157 U	0.0110 U
	MW-307-70	10/03/19	PES	PACE	70	-9.5	S	0.0313 U	0.0177 U	0.00802 U	**0.0561 J**	0.0164 U	0.0175 U	0.0161 U	0.00458 U	0.00573 U	0.0403 UJ	0.00782 U	0.0547 U
	MW-307-75	10/03/19	PES	PACE	75	-14.5	S	0.00301 U	0.00171 U	0.000772 U	**0.0160**	0.00158 U	0.00169 U	0.00154 U	0.000441 U	0.000551 U	0.00388 UJ	0.000753 U	0.00527 U
	MW-307-80	10/03/19	PES	PACE	80	-19.5	S	0.00319 U	0.00182 U	0.000818 U	**0.0261**	0.00167 U	0.00179 U	0.00163 U	0.000467 U	0.000584 U	0.00412 UJ	0.000798 U	0.00558 U
	MW-307-85	10/03/19	PES	PACE	85	-24.5	S	0.00313 U	0.00178 U	0.000802 U	**0.0293**	0.00164 U	0.00175 U	0.00160 U	0.000458 U	0.000573 U	0.00403 UJ	0.000782 U	0.00548 U
	MW-2016-85	10/03/19	PES	PACE	85 (dup)	-24.5	S	0.00295 U	0.00167 U	0.000756 U	**0.0113**	0.00154 U	0.00165 U	0.00151 U	0.000432 U	0.000540 U	0.00380 UJ	0.000738 U	0.00516 U
MW-309 (-32.0 to -42.0)	MW-309-5	09/19/19	PES	PACE	5	25.4	V	0.00326 U	0.00185 U	**0.00188 J**	**0.0102**	0.00171 U	0.00183 U	0.00167 U	0.000477 U	0.000597 U	0.00420 U	0.000815 U	**0.00734 J**
	MW-309-10	09/19/19	PES	PACE	10	20.4	S	0.171 U	0.0975 U	0.0440 U	0.0787 U	0.0900 U	0.0963 U	0.0881 U	0.0252 U	0.0315 U	0.222 U	0.0429 U	**0.400 J**
	MW-309-13.5	09/19/19	PES	PACE	13.5	16.9	S	0.00333 U	0.00189 U	0.000855 U	0.00153 U	0.00175 U	0.00187 U	0.00171 U	0.000489 U	0.000611 U	0.00430 U	0.000834 U	0.00584 U
	MW-309-15	09/19/19	PES	PACE	15	15.4	S	0.0257 U	0.0146 U	0.00659 U	**0.0503**	0.0134 U	0.0144 U	0.0132 U	0.00377 U	0.00471 U	0.0332 U	0.00643 U	**0.174**
	MW-309-20	09/19/19	PES	PACE	20	10.4	S	0.00321 U	0.00182 U	0.000824 U	**0.0593**	0.00168 U	0.00180 U	0.00165 U	0.000471 U	0.000588 U	0.00414 U	0.000804 U	**0.252**
	MW-309-25	09/19/19	PES	PACE	25	5.4	S	0.00323 U	0.00183 U	0.000827 U	**0.0132**	0.00169 U	0.00181 U	0.00165 U	0.000473 U	0.000591 U	0.00416 U	0.000807 U	**0.0896**
	MW-309-30	09/19/19	PES	PACE	30	0.4	S	0.00326 U	0.00185 U	0.000836 U	**0.0250**	0.00171 U	0.00183 U	0.00167 U	0.000478 U	0.000597 U	0.00420 U	0.000816 U	**0.0159**
	MW-309-35	09/19/19	PES	PACE	35	-4.6	S	0.00331 U	0.00188 U	0.000849 U	**0.0200**	0.00173 U	0.00185 U	0.00170 U	0.000485 U	**0.00150 J**	0.00427 U	0.000828 U	0.00579 U
	MW-309-40	09/19/19	PES	PACE	40	-9.6	S	0.00331 U	0.00188 U	0.000849 U	**0.0381**	0.00173 U	0.00186 U	0.00170 U	0.000485 U	0.000606 U	0.00427 U	0.000828 U	0.00580 U
	MW-309-45	09/19/19	PES	PACE	45	-14.6	S	0.00344 U	0.00196 U	0.000883 U	**0.0229**	0.00180 U	0.00193 U	0.00177 U	0.000505 U	0.000631 U	0.00444 U	0.000861 U	0.00603 U
	MW-309-50	09/19/19	PES	PACE	50	-19.6	S	0.00325 U	0.00185 U	0.000834 U	0.00149 U	0.00170 U	0.00182 U	0.00167 U	0.000477 U	0.000596 U	0.00420 U	0.000814 U	0.00570 U
	MW-309-55	09/19/19	PES	PACE	55	-24.6	S	0.00303 U	0.00172 U	0.000777 U	**0.0257**	0.00159 U	0.00170 U	0.00155 U	0.000444 U	0.000555 U	0.00391 U	0.000758 U	**0.00583 J**
	MW-309-60	09/19/19	PES	PACE	60	-29.6	S	0.00305 U	0.00173 U	0.000782 U	**0.0170**	0.00160 U	0.00171 U	0.00157 U	0.000447 U	0.000559 U	0.00393 U	0.000763 U	0.00534 U
	MW-309-65	09/19/19	PES	PACE	65	-34.6	S	0.00307 U	0.00174 U	0.000786 U	**0.0164**	0.00161 U	0.00172 U	0.00157 U	0.000449 U	0.000562 U	0.00395 U	0.000767 U	0.00537 U
	MW-309-70	09/19/19	PES	PACE	70	-39.6	S	0.00310 U	0.00176 U	0.000796 U	**0.0129**	0.00163 U	0.00174 U	0.00159 U	0.000455 U	0.000569 U	0.00400 U	0.000777 U	0.00544 U
	MW-309-75	09/19/19	PES	PACE	75	-44.6	S	0.00295 U	0.00168 U	0.000757 U	**0.0100**	0.00155 U	0.00165 U	0.00151 U	0.000432 U	0.000540 U	0.00380 U	0.000738 U	0.00517 U
MW-311 (-29.0 to -39.0)	MW-311-5	09/18/19	PES	PACE	5	28.1	V	0.00327 U	0.00186 U	**0.00286 J**	**0.00756**	0.00171 U	0.00183 U	0.00168 U	0.000479 U	0.000599 U	0.00421 UJ	0.000818 U	0.00572 U
	MW-311-10	09/18/19	PES	PACE	10	23.1	S	0.00314 U	0.00178 U	0.000806 U	**0.00875**	0.00165 U	0.00176 U	0.00161 U	0.000460 U	0.000576 U	0.00405 UJ	0.000786 U	0.00550 U
	MW-311-15	09/18/19	PES	PACE	15	18.1	S	0.00733 U	0.00416 U	0.00188 U	**0.0223**	0.00384 U	0.00411 U	0.00376 U	0.00107 U	0.00134 U	0.00945 UJ	0.00184 U	0.0128 U
	MW-311-20	09/18/19	PES	PACE	20	13.1	S	0.00764 U	0.00433 U	0.00196 U	**0.0469**	0.00399 U	0.00428 U	0.00391 U	0.00112 U	0.00140 U	0.00985 UJ	0.00192 U	0.0134 U
	MW-311-25	09/18/19	PES	PACE	25	8.1	S	0.0135 U	0.00770 U	0.00348 U	**0.196**	0.00710 U	0.00760 U	0.00695 U	0.00199 U	0.00248 U	0.0175 UJ	0.00339 U	0.0237 U
	MW-311-30	09/18/19	PES	PACE	30	3.1	S	0.00717 U	0.00407 U	0.00184 U	**0.0804**	0.00376 U	0.00401 U	0.00368 U	0.00105 U	0.00132 U	0.00924 UJ	0.00179 U	**0.0180**
	MW-311-35	09/18/19	PES	PACE	35	-1.9	S	0.00637 U	0.00362 U	0.00163 U	**0.0325**	0.00334 U	0.00357 U	0.00327 U	0.000933 U	0.00117 U	0.00821 UJ	0.00160 U	0.0112 U
	MW-311-40	09/18/19	PES	PACE	40	-6.9	S	0.00320 U	0.00182 U	**0.00251 J**	**0.0152**	0.00168 U	0.00179 U	0.00164 U	**0.00304**	0.000586 U	0.00413 UJ	0.000800 U	0.00560 U
	MW-311-45	09/18/19	PES	PACE	45	-11.9	S	0.00343 U	0.00195 U	**1.25**	**0.00613 J**	**0.00184 J**	0.00192 U	0.00176 U	**0.169**	0.000628 U	0.00442 UJ	0.000857 U	0.00600 U
	MW-311-50	09/18/19	PES	PACE	50	-16.9	S	0.00319 U	0.00181 U	**1.31**	**0.0181**	**0.00195 J**	0.00179 U	0.00163 U	**0.151**	0.000584 U	0.00411 UJ	0.000797 U	0.00558 U
	MW-311-55	09/18/19	PES	PACE	55	-21.9	S	0.00302 U	0.00171 U	**2.31**	**0.0106**	**0.00191 J**	0.00169 U	0.00155 U	**0.895**	0.000553 U	0.00389 UJ	**0.0235**	0.00528 U
	MW-311-60	09/18/19	PES	PACE	60	-26.9	S	0.00598 U	0.00340 U	**0.00274 J**	**0.0290**	0.00313 U	0.00335 U	0.00307 U	**0.0106**	0.00110 U	0.00771 UJ	**0.0232**	0.0105 U
	MW-311-65	09/18/19	PES	PACE	65	-31.9	S	0.00289 U	0.00164 U	0.000742 U	**0.0112**	0.00152 U	0.00162 U	0.00148 U	**0.000817 J**	0.000530 U	0.00373 UJ	**0.00565**	0.00507 U
	MW-2005-65	09/18/19	PES	PACE	65 (dup)	-31.9	S	0.00299 U	0.00170 U	**0.00113 J**	**0.0123**	0.00157 U	0.00168 U	0.00154 U	0.000439 U	0.000549 U	0.00386 U	**0.00442**	0.00524 U
	MW-311-70	09/18/19	PES	PACE	70	-36.9	S	0.00301 U	0.00171 U	**0.00142 J**	**0.00420 J**	0.00158 U	0.00169 U	0.00154 U	**0.000483 J**	0.000551 U	0.00388 UJ	0.000753 U	0.00527 U
	MW-2007-70	09/18/19	PES	PACE	70 (dup)	-38.3	S	0.00582 U	0.00330 U	**0.00375 J**	**0.0366**	0.00305 U	0.00326 U	0.00298 U	0.000852 U	0.00107 U	0.00750 U	0.00146 U	0.0102 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
MW-312	MW-312-6	09/16/19	PES	PACE	6	29.6	V	0.00332 U	0.00189 U	0.000852 U	**0.00946**	0.00174 U	0.00186 U	0.00170 U	0.000487 U	0.000608 U	0.00428 UJ	0.000831 U	0.00582 U
(19.9 to9.9)	MW-312-10	09/16/19	PES	PACE	10	25.6	V	0.00554 U	0.00315 U	0.00142 U	**0.0225**	0.00290 U	0.00310 U	0.00285 U	0.000812 U	0.00101 U	0.00714 UJ	0.00139 U	0.00970 U
	MW-312-15	09/16/19	PES	PACE	15	20.6	S	0.00378 U	0.00214 U	0.000968 U	**0.0408**	0.00198 U	0.00211 U	0.00194 U	0.000553 U	0.000691 U	0.00487 UJ	0.000944 U	**0.0241**
	MW-312-20	09/16/19	PES	PACE	20	15.6	S	0.00295 U	0.00168 U	0.000757 U	**0.00520 J**	0.00155 U	0.00166 U	0.00151 U	0.000433 U	0.000541 U	0.00381 UJ	0.000739 U	0.00517 U
	MW-2004-20	09/16/19	PES	PACE	20	15.6	S	0.00315 U	0.00179 U	0.000808 U	**0.00987**	0.00165 U	0.00177 U	0.00162 U	0.000462 U	0.000577 U	0.00406 UJ	0.000789 U	0.00552 U
	MW-312-25	09/16/19	PES	PACE	25	10.6	S	0.00305 U	0.00173 U	0.000783 U	**0.00658**	0.00160 U	0.00171 U	0.00157 U	0.000447 U	0.000559 U	0.00394 UJ	0.000764 U	**0.00660 J**
MW-314	MW-314-6	09/13/19	PES	PACE	6	33.8	V	0.00310 U	0.00176 U	**0.00325**	**0.00468 J**	0.00162 U	0.00174 U	0.00159 U	0.000454 U	0.000568 U	0.00400 U	0.000776 U	**0.00561 J**
(-28.0 to -38.0)	MW-314-10	09/13/19	PES	PACE	10	29.8	V	0.00313 U	0.00178 U	0.000803 U	**0.00970**	0.00165 U	0.00175 U	0.00160 U	0.000459 U	0.000574 U	0.00404 U	0.000784 U	0.00549 U
	MW-314-15	09/13/19	PES	PACE	15	24.8	V	0.00307 U	0.00174 U	0.000788 U	**0.0101**	0.00161 U	0.00172 U	0.00158 U	0.000450 U	0.000563 U	0.00396 U	0.000768 U	0.00538 U
	MW-314-20	09/13/19	PES	PACE	20	19.8	S	0.00313 U	0.00178 U	0.000803 U	**0.00875**	0.00164 U	0.00176 U	0.00161 U	**0.00105 J**	0.000574 U	0.00404 U	0.000784 U	0.00549 U
	MW-314-25	09/13/19	PES	PACE	25	14.8	S	0.00347 U	0.00197 U	0.000889 U	**0.00372 J**	0.00182 U	0.00194 U	0.00178 U	0.000508 U	0.000635 U	0.00447 U	**0.00563**	0.00607 U
	MW-2002-25	09/13/19	PES	PACE	25	14.8	S	0.00345 U	0.00196 U	0.000884 U	**0.00170 J**	0.00181 U	0.00193 U	0.00177 U	0.000505 U	0.000631 U	0.00444 UJ	0.000862 U	0.00603 U
	MW-314-30	09/13/19	PES	PACE	30	9.8	S	0.00340 U	0.00193 U	**0.0637**	**0.00696**	0.00178 U	0.00190 U	0.00174 U	**0.116**	0.000622 U	0.00438 U	**0.00230 J**	0.00595 U
	MW-314-35	09/13/19	PES	PACE	35	4.8	S	0.00293 U	0.00166 U	**1.14**	**0.0118**	**0.00420 J**	0.00164 U	0.00150 U	**0.449**	0.000536 U	0.00378 U	**0.0238**	0.00513 U
	MW-314-40	09/13/19	PES	PACE	40	-0.2	S	0.00305 U	0.00172 U	**0.0258**	**0.00627**	**0.00469 J**	0.00170 U	0.00156 U	**0.199**	0.000557 U	0.00393 U	**0.0515**	0.00533 U
	MW-314-45	09/13/19	PES	PACE	45	-5.2	S	0.00302 U	0.00172 U	**0.00151 J**	**0.00815**	0.00158 U	0.00169 U	0.00155 U	**0.00106 J**	0.000553 U	0.00390 U	**0.00391**	0.00529 U
	MW-314-50	09/13/19	PES	PACE	50	-10.2	S	0.00304 U	0.00173 U	**0.000779** U	**0.00713**	0.00159 U	0.00170 U	0.00156 U	0.000445 U	0.000557 U	0.00392 U	0.000760 U	0.00532 U
	MW-314-55	09/13/19	PES	PACE	55	-15.2	S	0.00330 U	0.00187 U	0.000845 U	**0.00644**	0.00173 U	0.00185 U	0.00169 U	0.000483 U	0.000604 U	0.00425 U	**0.0756**	0.00577 U
	MW-314-60	09/13/19	PES	PACE	60	-20.2	S	0.00302 U	0.00171 U	0.000774 U	**0.00757**	0.00158 U	0.00169 U	0.00155 U	0.000442 U	0.000553 U	0.00389 U	**0.0239**	0.00529 U
	MW-314-65	09/13/19	PES	PACE	65	-25.2	S	0.00310 U	0.00176 U	0.000795 U	**0.00364 J**	0.00162 U	0.00174 U	0.00159 U	0.000454 U	0.000568 U	0.00400 UJ	0.000775 U	0.00543 U
	MW-314-70	09/13/19	PES	PACE	70	-30.2	S	0.0332 U	0.0189 U	**0.298**	**0.0338 J**	0.0174 U	0.0185 U	0.0170 U	**0.138**	0.00607 U	0.0428 U	0.00830 U	0.0581 U
	MW-314-75	09/13/19	PES	PACE	75	-35.2	S	0.00623 U	0.00354 U	**0.0441**	**0.00677 J**	0.00327 U	0.00349 U	0.00320 U	**0.124**	0.00114 U	0.00804 UJ	0.00156 U	0.0109 U
	MW-314-80	09/13/19	PES	PACE	80	-40.2	S	0.00408 U	0.00232 U	**0.0160**	**0.00446 J**	0.00213 U	0.00228 U	0.00209 U	**0.100**	0.000747 U	0.00525 UJ	0.00102 U	0.00713 U
MW-316	MW-316-5	09/09/19	PES	PACE	5	44.8	V	0.00296 U	0.00168 U	0.000758 U	**0.00780**	0.00155 U	0.00166 U	0.00152 U	0.000433 U	0.000541 U	0.00381 U	0.000739 U	0.00517 U
(-10.0 to -20.0)	MW-316-10	09/09/19	PES	PACE	10	39.8	V	0.00309 U	0.00175 U	0.000792 U	**0.0197**	0.00162 U	0.00173 U	0.00158 U	0.000453 U	**0.00346**	0.00398 U	0.000773 U	0.00541 U
	MW-316-15	09/09/19	PES	PACE	15	34.8	V	0.00307 U	0.00174 U	0.000787 U	**0.00457 J**	0.00161 U	0.00172 U	0.00157 U	0.000450 U	**0.00179 J**	0.00396 U	0.000768 U	0.00537 U
	MW-316-20	09/09/19	PES	PACE	20	29.8	V	0.00294 U	0.00167 U	**0.00305**	**0.00535 J**	0.00154 U	0.00165 U	0.00151 U	0.000431 U	**0.00182 J**	0.00380 U	0.000737 U	0.00516 U
	MW-316-25	09/09/19	PES	PACE	25	24.8	S	0.00310 U	0.00176 U	0.000794 U	**0.00791**	0.00162 U	0.00174 U	0.00159 U	0.000454 U	**0.00190 J**	0.00399 U	0.000775 U	0.00542 U
	MW-316-30	09/09/19	PES	PACE	30	19.8	S	0.00303 U	0.00172 U	0.000777 U	**0.00612**	0.00159 U	0.00170 U	0.00155 U	0.000444 U	0.000555 U	0.00391 U	0.000758 U	0.00530 U
	MW-316-35	09/09/19	PES	PACE	35	14.8	S	0.00308 U	0.00175 U	0.000790 U	**0.00707**	0.00161 U	0.00173 U	0.00158 U	0.000452 U	**0.00170 J**	0.00397 U	0.000771 U	0.00540 U
	MW-316-40	09/09/19	PES	PACE	40	9.8	S	0.00311 U	0.00176 U	0.000797 U	**0.00483 J**	0.00163 U	0.00174 U	0.00159 U	0.000455 U	0.000569 U	0.00401 U	0.000777 U	0.00544 U
	MW-316-45	09/09/19	PES	PACE	45	4.8	S	0.00304 U	0.00172 U	0.000778 U	**0.00703**	0.00159 U	0.00170 U	0.00156 U	0.000445 U	**0.00156 J**	0.00391 U	0.000759 U	0.00532 U
	MW-316-50	09/09/19	PES	PACE	50	-0.2	S	0.00327 U	0.00185 U	0.000838 U	**0.0112**	0.00171 U	0.00183 U	0.00168 U	0.000479 U	**0.00236 J**	0.00421 U	0.000817 U	0.00572 U
	MW-316-55	09/09/19	PES	PACE	55	-5.2	S	0.00309 U	0.00176 U	0.000793 U	**0.00464 J**	0.00162 U	0.00173 U	0.00159 U	0.000453 U	0.000566 U	0.00399 U	0.000774 U	0.00541 U
	MW-316-60	09/09/19	PES	PACE	60	-10.2	S	0.00307 U	0.00174 U	0.000787 U	**0.00596**	0.00161 U	0.00172 U	0.00157 U	0.000450 U	**0.00162 J**	0.00396 U	0.000768 U	0.00537 U
	MW-316-65	09/10/19	PES	PACE	65	-15.2	S	0.00408 U	0.00232 U	0.00105 U	**0.0131**	0.00214 U	0.00229 U	0.00210 U	0.000599 U	**0.00346 J**	0.00527 U	0.00102 U	0.00715 U
	MW-2001-65	09/10/19	PES	PACE	65	-15.2	S	0.00323 U	0.00184 U	0.000829 U	**0.00811**	0.00169 U	0.00181 U	0.00166 U	0.000474 U	0.000592 U	0.00417 U	0.000809 U	0.00566 U
	MW-316-70	09/10/19	PES	PACE	70	-20.2	S	0.00309 U	0.00175 U	0.000792 U	**0.00694**	0.00162 U	0.00173 U	0.00158 U	0.000453 U	**0.00167 J**	0.00398 U	0.000773 U	0.00541 U
MW-319	MW-319-6	09/18/19	PES	PACE	6	25.7	V	0.00317 U	0.00180 U	0.000812 U	**0.0154**	0.00166 U	0.00178 U	0.00162 U	0.000464 U	0.000580 U	0.00408 U	0.000792 U	**0.0102**
(-42.8 to -52.8)	MW-319-10	09/18/19	PES	PACE	10	21.7	S	0.00315 U	0.00179 U	**0.00247 J**	**0.00939**	0.00165 U	0.00176 U	0.00161 U	0.000461 U	**0.00658**	0.00406 U	0.000787 U	0.00551 U
	MW-319-15	09/18/19	PES	PACE	15	16.7	S	0.00313 U	0.00178 U	0.000802 U	**0.0147**	0.00164 U	0.00175 U	0.00160 U	0.000458 U	**0.00647**	0.00403 U	0.000782 U	0.00548 U
	MW-319-20	09/18/19	PES	PACE	20	11.7	S	0.00338 U	0.00192 U	0.000867 U	**0.00844**	0.00177 U	0.00190 U	0.00173 U	0.000495 U	**0.00313**	0.00436 U	0.000846 U	0.00592 U
	MW-319-30	09/18/19	PES	PACE	30	1.7	S	0.00312 U	0.00177 U	0.000800 U	**0.0140**	0.00163 U	0.00175 U	0.00160 U	0.000457 U	**0.00188 J**	0.00402 U	0.000781 U	0.00546 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
MW-319 (continued)	MW-319-35	09/18/19	PES	PACE	35	-3.3	S	0.00344 U	0.00195 U	0.000883 U	**0.0151**	0.00180 U	0.00193 U	0.00177 U	0.000504 U	**0.00661**	0.00444 U	0.000861 U	0.00603 U
	MW-319-40	09/18/19	PES	PACE	40	-8.3	S	0.00322 U	0.00183 U	0.000826 U	**0.00939**	0.00169 U	0.00181 U	0.00165 U	0.000472 U	**0.00495**	0.00416 U	0.000806 U	0.00564 U
	MW-319-45	09/18/19	PES	PACE	45	-13.3	S	0.00324 U	0.00184 U	0.000831 U	**0.00874**	0.00170 U	0.00182 U	0.00166 U	0.000475 U	**0.00186 J**	0.00418 U	0.000811 U	0.00568 U
	MW-319-50	09/18/19	PES	PACE	50	-18.3	S	0.00333 U	0.00189 U	0.000855 U	**0.00662**	0.00175 U	0.00187 U	0.00171 U	0.000488 U	**0.00575**	0.00430 U	0.000834 U	0.00584 U
	MW-319-55	09/18/19	PES	PACE	55	-23.3	S	0.00345 U	0.00196 U	0.000884 U	**0.0279**	0.00181 U	0.00193 U	0.00177 U	0.000505 U	0.000631 U	0.00445 U	0.000863 U	**0.0102**
	MW-319-60	09/18/19	PES	PACE	60	-28.3	S	0.00324 U	0.00184 U	0.000831 U	**0.0130**	0.00170 U	0.00182 U	0.00166 U	0.000475 U	**0.00578**	0.00418 U	0.000811 U	**0.0217**
	MW-319-65	09/18/19	PES	PACE	65	-33.3	S	0.00348 U	0.00198 U	**0.0230**	**0.0141**	0.00182 U	0.00195 U	0.00178 U	**0.00875**	**0.00817**	0.00449 U	0.000871 U	**0.00713 J**
	MW-319-70	09/18/19	PES	PACE	70	-38.3	S	0.00333 U	0.00189 U	0.000853 U	**0.0148**	0.00174 U	0.00186 U	0.00171 U	0.000487 U	**0.00749**	0.00429 U	0.000832 U	0.00582 U
	MW-2006-70	09/18/19	PES	PACE	70 (dup)	-36.9	S	0.00342 U	0.00194 U	**0.000894 J**	**0.0128**	0.00179 U	0.00192 U	0.00175 U	0.000501 U	**0.00788**	0.00441 UJ	0.000856 U	0.00599 U
	MW-319-75	09/18/19	PES	PACE	75	-43.3	S	0.00302 U	0.00172 U	**0.0181**	**0.00954**	0.00158 U	0.00169 U	0.00155 U	**0.00318**	**0.00458**	0.00390 U	0.000757 U	0.00529 U
	MW-319-80	09/18/19	PES	PACE	80	-48.3	S	0.00332 U	0.00188 U	**0.0693**	**0.00815**	0.00174 U	0.00186 U	0.00170 U	**0.0662**	**0.00576**	0.00428 UJ	0.000830 U	0.00581 U
	MW-319-85	09/18/19	PES	PACE	85	-53.3	S	0.00328 U	0.00186 U	**0.0387**	**0.0106**	0.00172 U	0.00184 U	0.00168 U	**0.0562**	**0.00588**	0.00423 UJ	0.000822 U	0.00575 U
MW-320 (18.6 to 8.6)	MW-320-19	09/29/19	PES	PACE	19	15.1	S	0.0610 U	**0.0875 J**	0.0156 U	0.0279 U	0.0319 U	0.0342 U	0.0313 U	0.00894 U	0.0112 U	0.0786 U	0.0153 U	0.107 U
	MW-320-27	09/29/19	PES	PACE	27	7.1	S	0.00316 U	0.00180 U	0.000811 U	**0.0110**	0.00166 U	0.00177 U	0.00162 U	0.000463 U	0.000579 U	0.00408 U	0.000791 U	0.00554 U
MW-323 (-65.4 to -75.4)	MW-323-10	09/28/19	PES	PACE	10	24.7	V	0.00666 U	0.00378 U	**0.0312**	**0.0310**	0.00349 U	0.00373 U	0.00341 U	0.000975 U	0.00122 U	0.00858 U	0.00167 U	0.0117 U
	MW-2012-10	09/28/19	PES	PACE	10 (dup)	24.7	V	0.00341 U	0.00194 U	**0.000875** U	**0.0132**	0.00178 U	0.00191 U	0.00175 U	0.000500 U	0.000625 U	0.00440 U	0.000853 U	0.00598 U
	MW-323-15	09/28/19	PES	PACE	15	19.7	S	0.00626 U	0.00355 U	**0.0106**	**0.0548**	0.00328 U	0.00351 U	0.00321 U	0.000917 U	0.00115 U	0.00807 U	0.00156 U	0.0110 U
	MW-323-20	09/28/19	PES	PACE	20	14.7	S	0.00308 U	0.00175 U	0.000790 U	**0.0313**	0.00161 U	0.00173 U	0.00158 U	0.000452 U	0.000565 U	0.00397 U	0.000771 U	**0.0535**
	MW-323-25	09/28/19	PES	PACE	25	9.7	S	0.00311 U	0.00177 U	0.000798 U	**0.0107**	0.00163 U	0.00174 U	0.00160 U	0.000456 U	0.000570 U	0.00401 U	0.000779 U	0.00545 U
	MW-323-30	09/28/19	PES	PACE	30	4.7	S	0.00580 U	0.00329 U	0.00149 U	**0.0475**	0.00304 U	0.00325 U	0.00297 U	0.000850 U	0.00106 U	0.00748 U	0.00145 U	0.0102 U
	MW-323-35	09/28/19	PES	PACE	35	-0.4	S	0.00351 U	0.00199 U	0.000900 U	**0.0141**	0.00184 U	0.00197 U	0.00180 U	0.000514 U	0.000643 U	0.00452 U	0.000878 U	0.00614 U
	MW-323-40	09/28/19	PES	PACE	40	-5.4	S	0.00351 U	0.00199 U	0.000899 U	**0.0104**	0.00184 U	0.00196 U	0.00180 U	0.000514 U	0.000642 U	0.00452 U	0.000877 U	0.00614 U
	MW-323-45	09/28/19	PES	PACE	45	-10.4	S	0.00349 U	0.00198 U	0.000896 U	**0.0145**	0.00183 U	0.00196 U	0.00179 U	0.000512 U	0.000640 U	0.00450 U	0.000874 U	0.00612 U
	MW-323-50	09/28/19	PES	PACE	50	-15.4	S	0.00314 U	0.00178 U	0.000806 U	**0.0193**	0.00165 U	0.00176 U	0.00161 U	**0.00121**	0.000575 U	0.00405 U	0.000786 U	0.00550 U
	MW-323-55	09/28/19	PES	PACE	55	-20.4	S	0.00318 U	0.00181 U	**0.120**	**0.0178**	**0.00530 J**	0.00178 U	0.00163 U	**0.0144**	0.000583 U	0.00410 U	**0.00604**	0.00557 U
	MW-323-60	09/28/19	PES	PACE	60	-25.4	S	0.00350 U	0.00199 U	**0.0806**	**0.0510**	**0.0110**	0.00197 U	0.00179 U	**0.0165**	0.000641 U	0.00452 U	**0.0218**	0.00613 U
	MW-2010-60	09/28/19	PES	PACE	60 (dup)	-25.4	S	0.00333 U	0.00189 U	**0.0928**	**0.0171**	**0.00987**	0.00187 U	0.00171 U	**0.0177**	0.000610 U	0.00429 U	**0.0239**	0.00583 U
	MW-323-65	09/28/19	PES	PACE	65	-30.4	S	0.00328 U	0.00186 U	**0.0696**	**0.00820**	**0.0114**	0.00184 U	0.00168 U	**0.0520**	0.000601 U	0.00423 U	**0.0403**	0.00574 U
	MW-323-70	09/28/19	PES	PACE	70	-35.4	S	0.459 U	0.260 U	0.118 U	0.211 U	0.241 U	0.258 U	0.236 U	0.0673 U	0.0841 U	0.592 U	0.115 U	0.804 U
	MW-323-75	09/28/19	PES	PACE	75	-40.4	S	0.00321 U	0.00182 U	**0.0408**	**0.0181**	**0.00790**	0.00180 U	0.00165 U	**0.0322**	0.000588 U	0.00414 U	**0.0186**	0.00562 U
	MW-323-80	09/28/19	PES	PACE	80	-45.4	S	0.00309 U	0.00175 U	**0.0303**	**0.0101**	0.00162 U	0.00173 U	0.00158 U	**0.321**	0.000565 U	0.00398 U	**0.00582**	0.00540 U
	MW-323-85	09/28/19	PES	PACE	85	-50.4	S	0.00327 U	0.00186 U	**0.0231**	**0.0140**	**0.00811**	0.00183 U	0.00168 U	**0.416**	0.000599 U	0.00422 U	**0.0151**	0.00572 U
	MW-323-91	09/28/19	PES	PACE	91	-56.4	S	0.00773 U	0.00440 U	**0.0125**	**0.0482**	0.00405 U	0.00434 U	0.00397 U	**0.0990**	0.00142 U	0.00998 U	**0.0225**	0.0136 U
	MW-323-95	09/28/19	PES	PACE	95	-60.4	S	0.00327 U	0.00186 U	**0.00833**	**0.00831**	0.00171 U	0.00183 U	0.00168 U	**0.0303**	0.000599 U	0.00422 U	**0.0195**	0.00573 U
	MW-323-99	09/28/19	PES	PACE	99	-64.4	S	0.00316 U	0.00179 U	0.000809 U	**0.00869**	0.00165 U	0.00177 U	0.00162 U	**0.0115**	0.000578 U	0.00407 U	**0.0146**	0.00553 U
	MW-323-105	09/28/19	PES	PACE	105	-70.4	S	0.00322 U	0.00183 U	0.000827 U	**0.00492 J**	0.00169 U	0.00181 U	0.00165 U	0.000472 U	0.000590 U	0.00416 U	0.000806 U	0.00564 U
	MW-323-110	09/28/19	PES	PACE	110	-75.4	S	0.00669 U	0.00380 U	0.00171 U	**0.0546**	0.00351 U	0.00374 U	0.00343 U	0.000980 U	0.00123 U	0.00862 U	0.00168 U	0.0117 U
MW-324 (-32.1 to -42.1)	MW-324-6	09/12/19	PES	PACE	6	28.3	V	0.00307 U	0.00174 U	0.000787 U	**0.00454 J**	0.00161 U	0.00172 U	0.00157 U	0.000450 U	0.000562 U	0.00396 U	0.000768 U	0.00538 U
	MW-324-10	09/12/19	PES	PACE	10	24.3	V	0.00316 U	0.00179 U	**0.00158 J**	**0.00790**	0.00166 U	0.00177 U	0.00162 U	0.000463 U	0.000579 U	0.00408 U	0.000791 U	0.00553 U
	MW-324-15	09/12/19	PES	PACE	15	19.3	S	0.00298 U	0.00169 U	0.000764 U	**0.00601**	0.00156 U	0.00167 U	0.00153 U	0.000437 U	0.000546 U	0.00384 U	0.000746 U	0.00522 U
	MW-324-20	09/12/19	PES	PACE	20	14.3	S	0.00319 U	0.00181 U	0.000817 U	**0.00659**	0.00167 U	0.00179 U	0.00163 U	0.000467 U	0.000583 U	0.00411 U	0.000797 U	0.00558 U
	MW-324-25	09/12/19	PES	PACE	25	9.3	S	0.00322 U	0.00183 U	0.000826 U	**0.0111**	0.00169 U	0.00181 U	0.00165 U	0.000472 U	0.000590 U	0.00416 U	0.000806 U	**0.00688 J**
	MW-324-30	09/12/19	PES	PACE	30	4.3	S	0.00335 U	0.00190 U	0.000860 U	**0.0128**	0.00176 U	0.00188 U	0.00172 U	0.000492 U	0.000615 U	0.00433 U	0.000840 U	0.00588 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
MW-324 (continued)	MW-324-35	09/12/19	PES	PACE	35	-0.7	S	0.00326 U	0.00185 U	0.000836 U	**0.00528 J**	0.00171 U	0.00183 U	0.00167 U	0.000478 U	0.000597 U	0.00420 U	0.000815 U	0.00571 U
	MW-324-40	09/12/19	PES	PACE	40	-5.7	S	0.00330 U	0.00187 U	0.000846 U	**0.00569 J**	0.00173 U	0.00185 U	0.00169 U	0.000483 U	0.000604 U	0.00425 U	0.000826 U	0.00578 U
	MW-324-45	09/12/19	PES	PACE	45	-10.7	S	0.00344 U	0.00195 U	0.000881 U	**0.00913**	0.00180 U	0.00193 U	0.00176 U	0.000503 U	0.000629 U	0.00443 U	0.000860 U	0.00602 U
	MW-324-50	09/12/19	PES	PACE	50	-15.7	S	0.00273 U	0.00155 U	0.000700 U	**0.00369 J**	0.00143 U	0.00153 U	0.00140 U	0.000400 U	0.000500 U	0.00352 U	0.000683 U	0.00478 U
	MW-324-55	09/12/19	PES	PACE	55	-20.7	S	0.00309 U	0.00176 U	0.000793 U	**0.00501 J**	0.00162 U	0.00173 U	0.00159 U	0.000453 U	0.000567 U	0.00399 U	**0.00110 J**	0.00542 U
	MW-324-60	09/12/19	PES	PACE	60	-25.7	S	0.00309 U	0.00176 U	0.000793 U	**0.00977**	**0.00171 J**	0.00173 U	0.00159 U	0.000453 U	0.000567 U	0.00399 U	**0.0200**	0.00542 U
	MW-324-65	09/12/19	PES	PACE	65	-30.7	S	0.00321 U	0.00182 U	**0.0115**	**0.0132**	**0.0113**	0.00179 U	0.00164 U	**0.0441**	0.000588 U	0.00415 U	**0.0467**	0.00563 U
	MW-324-70	09/12/19	PES	PACE	70	-35.7	S	0.00338 U	0.00192 U	**0.00674**	**0.00820**	**0.00850**	0.00190 U	0.00173 U	**0.0806**	0.000620 U	0.00437 U	**0.0218**	0.00593 U
	MW-324-75	09/12/19	PES	PACE	75	-40.7	S	0.00342 U	0.00194 U	**0.0516**	**0.00848**	**0.00586 J**	0.00192 U	0.00176 U	**0.0194**	0.000627 U	0.00441 U	**0.00486**	0.00599 U
	MW-324-80	09/12/19	PES	PACE	80	-45.7	S	0.00342 U	0.00194 U	0.000876 U	**0.0129**	**0.00696**	0.00191 U	0.00175 U	0.000501 U	0.000626 U	0.00440 U	**0.0106**	0.00598 U
MW-326 (-48.7 to -58.7)	MW-326-5	09/09/19	PES	PACE	5	36.3	V	0.00301 U	0.00171 U	0.000771 U	**0.00961**	0.00158 U	0.00169 U	0.00154 U	0.000441 U	**0.00358**	0.00388 U	0.000753 U	**0.00846**
	MW-326-10	09/09/19	PES	PACE	10	31.3	V	0.00363 U	0.00206 U	0.000932 U	**0.00821**	0.00191 U	0.00203 U	0.00186 U	0.000532 U	**0.00306 J**	0.00468 U	0.000909 U	0.00636 U
	MW-326-15	09/09/19	PES	PACE	15	26.3	V	0.00319 U	0.00181 U	0.000819 U	**0.00821**	0.00167 U	0.00179 U	0.00164 U	0.000468 U	0.000585 U	0.00412 U	0.000799 U	0.00559 U
	MW-326-20	09/09/19	PES	PACE	20	21.3	S	0.00320 U	0.00181 U	0.000819 U	**0.00613**	0.00167 U	0.00179 U	0.00164 U	0.000468 U	**0.00261 J**	0.00412 U	0.000800 U	0.00560 U
	MW-326-25	09/09/19	PES	PACE	25	16.3	S	0.00339 U	0.00192 U	0.000869 U	**0.00595 J**	0.00177 U	0.00190 U	0.00174 U	0.000496 U	**0.00253 J**	0.00437 U	0.000848 U	0.00593 U
	MW-326-30	09/09/19	PES	PACE	30	11.3	S	0.0110 U	0.00627 U	0.00283 U	**0.0174 J**	0.00578 U	0.00618 U	0.00566 U	0.00161 U	0.00203 U	0.0143 U	0.00277 U	0.0193 U
	MW-326-35	09/09/19	PES	PACE	35	6.3	S	0.00338 U	0.00192 U	0.000866 U	**0.00819**	0.00177 U	0.00189 U	0.00173 U	0.000495 U	0.000618 U	0.00435 U	0.000845 U	0.00591 U
	MW-326-40	09/09/19	PES	PACE	40	1.3	S	0.00326 U	0.00185 U	0.000835 U	**0.00812**	0.00171 U	0.00182 U	0.00167 U	0.000477 U	**0.00319**	0.00420 U	0.000815 U	0.00570 U
	MW-326-45	09/09/19	PES	PACE	45	-3.7	S	0.00329 U	0.00187 U	0.000843 U	**0.00790**	0.00172 U	0.00184 U	0.00169 U	**0.00169**	**0.00224 J**	0.00424 U	0.000823 U	0.00576 U
	MW-326-50	09/09/19	PES	PACE	50	-8.7	S	0.00312 U	0.00177 U	**0.101 J**	**0.00480 J**	0.00163 U	0.00175 U	0.00160 U	**0.0145**	**0.00227 J**	0.00402 U	0.000781 U	0.00546 U
	MW-326-55	09/09/19	PES	PACE	55	-13.7	S	0.00332 U	0.00189 U	0.00106 U	**0.0143**	0.00174 U	0.00186 U	0.00170 U	0.000487 U	**0.00346**	0.00428 U	0.000831 U	0.00581 U
	MW-326-60	09/09/19	PES	PACE	60	-18.7	S	0.00297 U	0.00168 U	0.000761 U	**0.00380 J**	0.00155 U	0.00166 U	0.00152 U	0.000435 U	0.000543 U	0.00383 U	0.000742 U	0.00520 U
	MW-326-65	09/09/19	PES	PACE	65	-23.7	S	0.00316 U	0.00180 U	**0.00753**	**0.00667**	0.00166 U	0.00177 U	0.00162 UJ	**0.00243**	0.000580 U	0.00408 U	0.000792 U	0.00554 U
	MW-326-70	09/09/19	PES	PACE	70	-28.7	S	0.00333 U	0.00189 U	0.000853 U	**0.00699**	0.00174 U	0.00186 U	0.00171 UJ	0.000487 U	**0.00210 J**	0.00429 U	0.000832 U	0.00582 U
	MW-326-75	09/09/19	PES	PACE	75	-33.7	S	0.00331 U	0.00188 U	0.000849 U	**0.00783**	0.00173 U	0.00185 U	0.00170 UJ	0.000485 U	0.000606 U	0.00427 U	0.000828 U	0.00579 U
	MW-326-80	09/09/19	PES	PACE	80	-38.7	S	0.00324 U	0.00184 U	0.000832 U	**0.00436 J**	0.00170 U	0.00182 U	0.00166 UJ	0.000475 U	**0.00217 J**	0.00418 U	0.000812 U	0.00568 U
	MW-326-85	09/10/19	PES	PACE	85	-43.7	S	0.00319 U	0.00181 U	0.000818 U	**0.00342 J**	0.00167 U	0.00179 U	0.00164 UJ	0.000467 U	0.000584 U	0.00411 U	0.000798 U	0.00559 U
	MW-326-90	09/10/19	PES	PACE	90	-48.7	S	0.00321 U	0.00183 U	0.000824 U	**0.00651**	0.00168 U	0.00180 U	0.00165 UJ	0.000471 U	0.000589 U	0.00414 U	0.000804 U	0.00563 U
	MW-326-95	09/10/19	PES	PACE	95	-53.7	S	0.00307 U	0.00174 U	0.000786 U	**0.0102**	0.00161 U	0.00172 U	0.00157 UJ	0.000449 U	0.000562 U	0.00395 U	0.000767 U	0.00537 U
	MW-200I-95	09/10/19	PES	PACE	95 (dup)	-53.7	S	**0.0102 J**	0.00177 U	0.000798 U	**0.00797**	0.00163 U	0.00175 U	0.00160 U	0.000456 U	0.000570 U	0.00401 U	0.000779 U	0.00545 U
	MW-326-100	09/10/19	PES	PACE	100	-58.7	S	0.00330 U	0.00187 U	0.000846 U	**0.0108**	0.00173 U	0.00185 U	0.00169 UJ	0.000483 U	0.000604 U	0.00425 U	0.000825 U	0.00578 U
MW-328 (-36.1 to -46.1)	MW-328-5	09/16/19	PES	PACE	5	23.4	V	0.00325 U	0.00184 U	0.000832 U	**0.0262**	0.00170 U	0.00182 U	0.00166 U	0.000476 U	0.000594 U	0.00418 UJ	0.000812 U	0.00568 U
	MW-328-10	09/16/19	PES	PACE	10	18.4	S	0.00375 U	0.00213 U	0.000962 U	**0.00851**	0.00197 U	0.00210 U	0.00192 U	0.000550 U	0.000687 U	0.00484 UJ	0.000939 U	0.00657 U
	MW-328-15	09/16/19	PES	PACE	15	13.4	S	0.00335 U	0.00190 U	0.000859 U	**0.00559 J**	0.00176 U	0.00188 U	0.00172 U	0.000491 U	0.000614 U	0.00432 UJ	0.000838 U	0.00587 U
	MW-328-20	09/16/19	PES	PACE	20	8.4	S	0.00326 U	0.00185 U	0.000836 U	**0.0178**	0.00171 U	0.00183 U	0.00167 U	0.000478 U	0.000597 U	0.00420 UJ	0.000816 U	0.00571 U
	MW-328-30	09/16/19	PES	PACE	30	-1.6	S	0.0644 U	0.0365 U	0.0165 U	**0.207**	0.0337 U	0.0360 U	0.0330 U	0.00943 U	**0.0466 J**	0.0830 UJ	0.0160 U	0.113 U
	MW-328-35	09/16/19	PES	PACE	35	-6.6	S	0.00350 U	0.00199 U	0.000900 U	**0.00781**	0.00184 U	0.00196 U	0.00179 U	0.000514 U	0.000643 U	0.00452 UJ	0.000878 U	0.00615 U
	MW-328-40	09/16/19	PES	PACE	40	-11.6	S	0.00795 U	0.00451 U	0.00204 U	**0.00849 J**	0.00416 U	0.00445 U	0.00408 U	0.00116 U	0.00146 U	0.0102 UJ	0.00199 U	0.0139 U
	MW-328-45	09/16/19	PES	PACE	45	-16.6	S	0.00337 U	0.00191 U	0.000863 U	**0.00519 J**	0.00176 U	0.00189 U	0.00173 U	0.000493 U	**0.00134 J**	0.00434 UJ	0.000842 U	0.00589 U
	MW-328-50	09/16/19	PES	PACE	50	-21.6	S	0.100 U	0.0569 U	0.0257 U	**0.299**	0.0524 U	0.0562 U	0.0514 U	0.0147 U	**0.0638 J**	0.130 UJ	0.0251 U	0.175 U
	MW-328-55	09/16/19	PES	PACE	55	-26.6	S	0.00325 U	0.00184 U	0.000833 U	**0.00690**	0.00170 U	0.00182 U	0.00167 U	0.000476 U	0.000595 U	0.00419 UJ	0.000813 U	0.00569 U
	MW-328-60	09/16/19	PES	PACE	60	-31.6	S	0.00328 U	0.00186 U	0.000842 U	**0.00798**	0.00172 U	0.00184 U	0.00168 U	0.000481 U	0.000601 U	0.00423 UJ	0.000821 U	0.00575 U
	MW-328-65	09/16/19	PES	PACE	65	-36.6	S	0.00318 U	0.00181 U	0.000816 U	**0.00736**	0.00167 U	0.00178 U	0.00163 U	0.000466 U	0.000583 U	0.00410 UJ	0.000796 U	0.00557 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
MW-328 (continued)	MW-328-70	09/16/19	PES	PACE	70	-41.6	S	0.00329 U	0.00187 U	0.000843 U	**0.00601 J**	0.00172 U	0.00184 U	0.00169 U	0.000482 U	0.000602 U	0.00424 UJ	0.000822 U	0.00576 U
	MW-328-75	09/16/19	PES	PACE	75	-46.6	S	0.00318 U	0.00181 U	0.000816 U	**0.00701**	0.00167 U	0.00178 U	0.00163 U	0.000467 U	0.000583 U	0.00411 UJ	0.000797 U	0.00558 U
	MW-328-80	09/16/19	PES	PACE	80	-51.6	S	0.00360 U	0.00204 U	0.000923 U	**0.00605 J**	0.00189 U	0.00202 U	0.00185 U	0.000528 U	0.000660 U	0.00464 UJ	0.000901 U	0.00631 U
MW-329 (-69.0 to -79.0)	MW-329-5	09/12/19	PES	PACE	5	24.3	V	0.00292 U	0.00166 U	0.000748 U	**0.00386 J**	0.00153 U	0.00164 U	0.00150 U	0.000428 U	0.000534 U	0.00376 U	0.000730 U	0.00511 U
	MW-329-10	09/12/19	PES	PACE	10	19.3	S	0.00287 U	0.00163 U	0.000736 U	**0.0318**	0.00150 U	0.00161 U	0.00147 U	0.000421 U	0.000526 U	0.00370 U	0.000718 U	0.00503 U
	MW-329-15	09/12/19	PES	PACE	15	14.3	S	0.00300 U	0.00170 U	0.000769 U	**0.00428 J**	0.00157 U	0.00168 U	0.00154 U	0.000439 U	0.000549 U	0.00386 U	0.000750 U	0.00525 U
	MW-329-20	09/12/19	PES	PACE	20	9.3	S	0.00377 U	0.00214 U	0.000968 U	**0.00671 J**	0.00198 U	0.00212 U	0.00194 U	0.000553 U	0.000691 U	0.00487 U	0.000944 U	**0.00687 J**
	MW-329-25	09/12/19	PES	PACE	25	4.3	S	0.00391 U	0.00222 U	0.00100 U	**0.00417 J**	0.00205 U	0.00219 U	0.00201 U	0.000573 U	0.000717 U	0.00504 U	0.000979 U	0.00685 U
	MW-329-30	09/12/19	PES	PACE	30	-0.7	S	0.00337 U	0.00191 U	0.000865 U	**0.00491 J**	0.00177 U	0.00189 U	0.00173 U	0.000494 U	0.000618 U	0.00435 U	0.000844 U	0.00590 U
	MW-329-35	09/12/19	PES	PACE	35	-5.7	S	0.00335 U	0.00190 U	0.000858 U	**0.00574 J**	0.00175 U	0.00187 U	0.00172 U	0.000490 U	**0.00169 J**	0.00431 U	0.000837 U	0.00586 U
	MW-329-40	09/12/19	PES	PACE	40	-10.7	S	0.00336 U	0.00191 U	0.000863 U	**0.00891**	0.00176 U	0.00189 U	0.00173 U	0.000493 U	0.000616 U	0.00434 U	0.000842 U	0.00589 U
	MW-329-45	09/12/19	PES	PACE	45	-15.7	S	0.00326 U	0.00185 U	0.000835 U	**0.00430 J**	0.00171 U	0.00182 U	0.00167 U	0.000477 U	0.000596 U	0.00420 U	0.000815 U	0.00570 U
	MW-329-50	09/12/19	PES	PACE	50	-20.7	S	0.00337 U	0.00191 U	0.000863 U	**0.00912**	0.00176 U	0.00189 U	0.00173 U	0.000493 U	0.000616 U	0.00434 U	0.000842 U	0.00589 U
	MW-2003-50	09/12/19	PES	PACE	50 (dup)	-20.7	S	0.00298 U	0.00169 U	0.000765 U	**0.00455 J**	0.00156 U	0.00167 U	0.00153 UJ	0.000437 U	0.000546 U	0.00385 U	0.000746 U	0.00522 U
	MW-329-55	09/12/19	PES	PACE	55	-25.7	S	0.00315 U	0.00179 U	0.000808 U	**0.00740**	0.00165 U	0.00177 U	0.00162 U	0.000462 U	0.000577 U	0.00406 U	0.000788 U	0.00552 U
	MW-329-60	09/12/19	PES	PACE	60	-30.7	S	0.00319 U	0.00181 U	0.000819 U	**0.00462 J**	0.00167 U	0.00179 U	0.00164 U	0.000468 U	0.000585 U	0.00412 U	0.000799 U	0.00559 U
	MW-329-65	09/12/19	PES	PACE	65	-35.7	S	0.00319 U	0.00181 U	0.000818 U	**0.00466 J**	0.00167 U	0.00179 U	0.00164 U	0.000467 U	0.000584 U	0.00411 U	0.000798 U	0.00559 U
	MW-329-70	09/12/19	PES	PACE	70	-40.7	S	0.00318 U	0.00181 U	0.000816 U	**0.00431 J**	0.00167 U	0.00178 U	0.00163 U	0.000466 U	0.000583 U	0.00410 U	**0.0167**	0.00557 U
	MW-329-75	09/12/19	PES	PACE	75	-45.7	S	0.00313 U	0.00178 U	0.000802 U	**0.0104**	0.00164 U	0.00175 U	0.00160 U	0.000458 U	0.000573 U	0.00403 U	0.000783 U	0.00548 U
	MW-329-80	09/12/19	PES	PACE	80	-50.7	S	0.00332 U	0.00188 U	0.000850 U	**0.00376 J**	0.00174 U	0.00186 U	0.00170 U	0.000486 U	0.000607 U	0.00428 UJ	0.000830 U	0.00581 U
	MW-329-85	09/12/19	PES	PACE	85	-55.7	S	0.00319 U	0.00181 U	0.000818 U	**0.00654**	0.00167 U	0.00179 U	0.00164 U	0.000468 U	0.000585 U	0.00412 U	**0.0751**	0.00559 U
	MW-329-90	09/12/19	PES	PACE	90	-60.7	S	0.00321 U	0.00182 U	0.000823 U	**0.00704**	0.00168 U	0.00180 U	0.00165 U	0.000470 U	0.000588 U	0.00414 U	0.000803 U	0.00562 U
	MW-329-95	09/12/19	PES	PACE	95	-65.7	S	0.00324 U	0.00184 U	0.000831 U	**0.00569 J**	0.00170 U	0.00182 U	0.00166 U	0.000475 U	0.000594 U	0.00418 U	0.000811 U	0.00568 U
	MW-329-100	09/12/19	PES	PACE	100	-70.7	S	0.00325 U	0.00185 U	0.000833 U	**0.00926**	0.00170 U	0.00182 U	0.00167 U	0.000476 U	0.000595 U	0.00419 U	0.000813 U	0.00569 U
	MW-329-105	09/12/19	PES	PACE	105	-75.7	S	0.00301 U	0.00171 U	0.000771 U	**0.00362 J**	0.00157 U	0.00168 U	0.00154 U	0.000440 U	0.000550 U	0.00388 U	0.000752 U	0.00526 U
	MW-329-110	09/12/19	PES	PACE	110	-80.7	S	0.00298 U	0.00169 U	0.000765 U	0.00137 U	0.00156 U	0.00167 U	0.00153 U	0.000437 U	0.000546 U	0.00385 U	0.000746 U	0.00522 U
MW-330	MW-330-6	04/20/20	PES	PACE	6	46.0	V	0.000260 U	0.00221 U	0.00102 U	0.00148 U	0.00118 U	0.00129 U	0.00211 U	0.000663 U	0.000939 U	0.00288 U	0.00132 U	0.00100 U
	MW-330-10	04/20/20	PES	PACE	10	42.0	V	0.000253 U	0.00215 U	0.000989 U	**0.00717**	0.00115 U	0.00126 U	0.00205 U	0.000644 U	0.000913 U	0.00280 U	0.00128 U	**0.00404 J**
	MW-330-11.5	04/20/20	PES	PACE	11.5	40.5	V	0.000267 U	0.00227 U	0.00104 U	0.00152 U	0.00121 U	0.00133 U	0.00217 U	0.000681 U	0.000964 U	0.00296 U	0.00135 U	0.00103 U
	MW-330-16	04/20/20	PES	PACE	16	36.0	V	0.000260 U	0.00222 U	0.00102 U	**0.00260 J**	0.00118 U	0.00130 U	0.00211 U	0.000663 U	0.000940 U	0.00289 U	0.00132 U	0.00100 U
	MW-330-21.5	04/20/20	PES	PACE	21.5	30.5	S	0.000244 U	0.00208 U	0.000954 U	0.00138 U	0.00111 U	0.00121 U	0.00198 U	**0.00194**	0.000881 U	0.00270 U	0.00124 U	0.000937 U
	MW-330-27	04/20/20	PES	PACE	27	25.0	S	0.000246 U	0.00210 U	0.000963 U	0.00140 U	0.00112 U	0.00123 U	0.00200 U	**0.00335**	0.000889 U	0.00273 U	0.00125 U	0.000946 U
	MW-330-32	04/20/20	PES	PACE	32	20.0	S	0.000247 U	0.00210 U	**0.00128 J**	0.00140 U	0.00112 U	0.00123 U	0.00200 U	**0.00868**	0.000891 U	0.00274 U	0.00125 U	0.000948 U
	MW-330-38	04/20/20	PES	PACE	38	14.0	S	0.000246 U	0.00210 U	0.000964 U	0.00140 U	0.00112 U	0.00123 U	0.00200 U	0.000628 U	0.000890 U	0.00273 U	0.00125 U	0.000947 U
	MW-330-42	04/20/20	PES	PACE	42	10.0	S	0.000240 U	0.00204 U	0.000938 U	0.00136 U	0.00109 U	0.00119 U	0.00195 U	0.000611 U	0.000866 U	0.00266 U	0.00121 U	**0.00161 J**
	MW-330-47	04/20/20	PES	PACE	47	5.0	S	0.000259 U	0.00221 U	0.00101 U	0.00147 U	0.00118 U	0.00129 U	0.00211 U	0.000661 U	0.000936 U	0.00288 U	0.00131 U	0.000996 U
	MW-330-52	04/20/20	PES	PACE	52	0.0	S	0.000251 U	0.00214 U	0.000984 U	**0.00272 J**	0.00114 U	0.00125 U	0.00204 U	0.000641 U	0.000908 U	0.00279 U	0.00127 U	**0.00382 J**
	MW-330-58	04/20/20	PES	PACE	58	-6.0	S	0.000249 U	0.00212 U	0.000975 U	**0.00143 J**	0.00113 U	0.00124 U	0.00202 U	0.000635 U	0.000900 U	0.00276 U	0.00126 U	**0.00374 J**
	MW-330-62	04/20/20	PES	PACE	62	-10.0	S	0.000252 U	0.00214 U	0.000984 U	0.00143 U	0.00114 U	0.00125 U	0.00204 U	0.000641 U	0.000908 U	0.00279 U	0.00127 U	0.000967 U
MW-331	MW-331-7	04/17/20	PES	PACE	7	24.2	V	0.000354 U	0.00301 U	0.00138 U	**0.126**	0.00161 U	0.00176 U	**0.0202**	0.000902 U	0.00128 U	**0.0588 J**	0.00179 UJ	**0.891**
	MW-331-11	04/17/20	PES	PACE	11	20.2	S	0.00205 U	**0.0213 J**	0.00803 U	0.0116 U	0.00932 U	0.0102 U	**0.456**	0.00523 U	0.00742 U	0.0227 U	0.0104 U	**0.612**
	MW-331-16	04/17/20	PES	PACE	16	15.2	S	0.000270 U	0.00230 U	0.00106 U	**0.00643**	0.00123 U	0.00135 U	0.00220 U	0.000689 U	0.000976 U	0.00300 U	0.00137 U	**0.0511**
	MW-331-20	04/17/20	PES	PACE	20	11.2	S	0.000265 U	0.00225 U	0.00104 U	**0.00564 J**	0.00120 U	0.00132 U	0.00215 U	0.000675 U	0.000956 U	0.00294 U	0.00134 U	**0.0336**

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
MW-331 (continued)	MW-331-29.5	04/17/20	PES	PACE	29.5	1.7	S	**0.00167 J**	0.00226 U	0.00104 U	**0.00724**	0.00121 U	0.00132 U	0.00216 U	0.000677 U	0.000958 U	0.00294 U	0.00134 U	**0.00932**
	MW-331-35	04/17/20	PES	PACE	35	-3.8	S	0.000270 U	0.00230 U	0.00106 U	0.00154 U	0.00123 U	0.00135 U	0.00220 U	0.000690 U	0.000977 U	0.00300 U	0.00137 U	**0.00196 J**
	MW-2018-35	04/17/20	PES	PACE	35 (dup)	-3.8	S	0.000275 U	0.00234 U	0.00108 U	0.00156 U	0.00125 U	0.00137 U	0.00223 U	0.000702 U	0.000994 U	0.00305 U	0.00139 U	**0.00142 J**
	MW-331-40	04/17/20	PES	PACE	40	-8.8	S	0.000276 U	0.00235 U	0.00108 U	0.00157 U	0.00125 U	0.00138 U	0.00224 U	0.000705 U	0.000998 U	0.00306 U	0.00140 U	**0.00176 J**
	MW-331-45	04/17/20	PES	PACE	45	-13.8	S	0.000275 U	0.00234 U	0.00108 U	0.00156 U	0.00125 U	0.00137 U	0.00224 U	0.000702 U	0.000994 U	0.00305 U	0.00139 U	**0.00170 J**
MW-332	MW-332-7	04/17/20	PES	PACE	7	29.3	V	**0.00155 J**	0.00219 U	**0.00835**	**0.00963**	0.00117 U	0.00128 U	0.00209 U	0.000655 U	0.000927 U	0.00285 U	0.00130 UJ	**0.0289**
	MW-332-11	04/17/20	PES	PACE	11	25.3	V	0.000270 U	0.00230 U	**0.00309**	**0.00790**	0.00122 U	0.00134 U	0.00219 U	0.000688 U	0.000974 U	0.00299 U	0.00137 UJ	**0.0199**
	MW-332-16	04/17/20	PES	PACE	16	20.3	S	0.000264 U	0.00225 U	**0.00161 J**	**0.0121**	0.00120 U	0.00132 U	0.00215 U	0.000674 U	0.000954 U	0.00293 U	0.00134 UJ	**0.00232 J**
	MW-332-20	04/17/20	PES	PACE	20	16.3	S	0.000268 U	0.00229 U	0.00105 U	**0.00648**	0.00122 U	0.00134 U	0.00218 U	0.000684 U	0.000969 U	0.00298 U	0.00136 UJ	**0.00156 J**
	MW-332-25	04/17/20	PES	PACE	25	11.3	S	0.000278 U	0.00237 U	0.00109 U	0.00158 U	0.00126 U	0.00138 U	0.00226 U	0.000709 U	0.00100 U	0.00308 U	0.00141 UJ	0.00107 U
	MW-332-30	04/17/20	PES	PACE	30	6.3	S	0.000284 U	0.00242 U	0.00111 U	0.00161 U	0.00129 U	0.00141 U	0.00231 U	0.000724 U	0.00103 U	0.00315 U	0.00144 UJ	0.00109 U
MW-334	MW-334-6	04/16/20	PES	PACE	6	25.4	V	0.000278 U	0.00237 U	**0.00163 J**	**0.00335 J**	0.00126 U	0.00138 U	**0.0124**	0.000709 U	0.00100 U	0.00309 U	0.00141 UJ	**0.00773 J**
	MW-334-10	04/16/20	PES	PACE	10	21.4	V	0.000279 U	0.00237 U	0.00109 U	**0.00452 J**	0.00126 U	0.00139 U	0.00226 U	0.000710 U	0.00101 U	0.00309 U	0.00141 UJ	**0.00677 J**
	MW-334-13	04/16/20	PES	PACE	13	18.4	S	0.00206 U	**0.0421 J**	0.00807 U	0.0117 U	0.00936 U	0.0103 U	**0.332**	0.00526 U	0.00745 U	0.0228 U	0.0104 UJ	**0.0684**
	MW-334-17	04/16/20	PES	PACE	17	14.4	S	**0.00349 J**	0.00202 U	0.000926 U	**0.0102**	0.00107 U	0.00118 U	**0.00324 J**	0.000604 U	0.000855 U	0.00262 U	0.00120 UJ	**0.00349 J**
	MW-334-23	04/16/20	PES	PACE	23	8.4	S	0.000273 U	0.00232 U	0.00107 U	0.00155 U	0.00124 U	0.00136 U	0.00221 U	0.000695 U	0.000984 U	0.00302 U	0.00138 UJ	**0.00275 J**
	MW-334-28	04/16/20	PES	PACE	28	3.4	S	0.000270 U	0.00230 U	0.00106 U	**0.00446 J**	0.00122 U	0.00134 U	**0.00254 J**	0.000688 U	0.000974 U	0.00299 U	0.00137 UJ	**0.00171 J**
	MW-334-35	04/16/20	PES	PACE	35	-3.6	S	0.000289 U	0.00246 U	0.00113 U	0.00164 U	0.00131 U	0.00144 U	0.00235 U	0.000738 U	0.00105 U	0.00321 U	0.00147 UJ	0.00111 U
	MW-334-40	04/16/20	PES	PACE	40	-8.6	S	0.000296 U	0.00252 U	0.00116 U	0.00168 U	0.00134 U	0.00147 U	0.00240 U	0.000754 U	0.00107 U	0.00328 U	0.00150 UJ	0.00114 U
	MW-334-45.5	04/16/20	PES	PACE	45.5	-14.1	S	0.000279 U	0.00237 U	0.00109 U	0.00158 U	0.00127 U	0.00139 U	0.00226 U	0.000710 U	0.00101 U	0.00309 U	0.00141 UJ	0.00107 U
	MW-334-50	04/16/20	PES	PACE	50	-18.6	S	0.000253 U	0.00216 U	0.000992 U	0.00144 U	0.00115 U	0.00126 U	0.00206 U	0.000646 U	0.000915 U	0.00281 U	0.00128 UJ	0.000974 U
	MW-334-54.5	04/16/20	PES	PACE	54.5	-23.1	S	0.000283 U	0.00241 U	0.00111 U	0.00161 U	0.00129 U	0.00141 U	0.00230 U	0.000723 U	0.00102 U	0.00314 U	0.00144 UJ	0.00109 U
	MW-334-60	04/16/20	PES	PACE	60	-28.6	S	0.000261 U	0.00222 U	0.00102 U	0.00148 U	0.00118 U	0.00130 U	0.00212 U	0.000665 U	0.000942 U	0.00289 U	0.00132 UJ	0.00100 U
	MW-334-63	04/16/20	PES	PACE	63	-31.6	S	0.000274 U	0.00233 U	0.00107 U	0.00155 U	0.00124 U	0.00136 U	**0.00240 J**	0.000698 U	0.000989 U	0.00304 U	0.00139 UJ	**0.00127 J**
MW-336	MW-336-7	04/22/20	PES	PACE	7	26.7	V	0.000255 U	0.00218 U	0.00100 U	0.00145 U	0.00116 U	0.00127 U	0.00208 U	0.000652 U	0.000923 U	0.00283 U	0.00129 U	0.000982 U
	MW-336-11.5	04/22/20	PES	PACE	11.5	22.2	V	0.000273 U	0.00232 U	0.00107 U	**0.00195 J**	0.00124 U	0.00136 U	0.00221 U	0.000695 U	0.000985 U	0.00302 U	0.00138 U	0.00105 U
	MW-2019-11.5	04/22/20	PES	PACE	11.5 (dup)	22.2	V	**0.00272 J**	0.00238 U	0.00109 U	**0.00239 J**	0.00127 U	0.00139 U	0.00227 U	0.000712 U	0.00101 U	0.00310 U	0.00141 U	0.00107 U
	MW-336-14.5	04/22/20	PES	PACE	14.5	19.2	V	0.000294 U	0.00250 U	0.00115 U	0.00167 U	0.00133 U	0.00146 U	0.00238 U	0.000749 U	0.00106 U	0.00326 U	0.00149 U	0.00113 U
	MW-336-20	04/22/20	PES	PACE	20	13.7	S	0.000280 U	0.00239 U	0.00110 U	0.00159 U	0.00127 U	0.00140 U	0.00228 U	0.000715 U	0.00101 U	0.00311 U	0.00142 U	0.00108 U
	MW-336-25	04/22/20	PES	PACE	25	8.7	S	0.000377 U	0.00321 U	0.00147 U	0.00214 U	0.00171 U	0.00188 U	0.00306 U	0.000961 U	0.00136 U	0.00418 U	0.00191 U	0.00145 U
	MW-336-30	04/22/20	PES	PACE	30	3.7	S	0.000349 U	0.00297 U	**0.00262 J**	0.00198 U	0.00158 U	0.00174 U	0.00283 U	0.000889 U	0.00126 U	0.00387 U	0.00177 U	0.00134 U
	MW-336-35	04/22/20	PES	PACE	35	-1.3	S	0.000281 U	0.00239 U	0.00110 U	**0.00193 J**	0.00128 U	0.00140 U	0.00228 U	0.000717 U	0.00101 U	0.00312 U	0.00142 U	0.00108 U
	MW-336-40	04/22/20	PES	PACE	40	-6.3	S	0.000276 U	0.00235 U	0.00108 U	**0.00174 J**	0.00125 U	0.00137 U	0.00224 U	0.000704 U	0.000997 U	0.00306 U	0.00140 U	0.00106 U
	MW-336-45	04/22/20	PES	PACE	45	-11.3	S	0.000304 U	0.00259 U	0.00119 U	0.00173 U	0.00138 U	0.00151 U	0.00247 U	**0.00301**	0.00110 U	0.00337 U	0.00154 U	0.00117 U
	MW-336-51	04/22/20	PES	PACE	51	-17.3	S	0.000264 U	0.00225 U	0.00103 U	0.00150 U	0.00120 U	0.00131 U	0.00214 U	**0.00297**	0.000952 U	0.00292 U	0.00134 U	0.00101 U
	MW-336-55	04/22/20	PES	PACE	55	-21.3	S	0.000262 U	0.00223 U	**0.00129 J**	**0.00151 J**	0.00119 U	0.00130 U	0.00212 U	**0.00609**	0.000945 U	0.00290 U	0.00133 U	0.00101 U
	MW-336-60	04/22/20	PES	PACE	60	-26.3	S	0.000269 U	0.00229 U	**0.0527**	0.00153 U	0.00122 U	0.00134 U	0.00218 U	**0.0750**	0.000971 U	0.00298 U	0.00136 U	0.00103 U
	MW-336-65	04/22/20	PES	PACE	65	-31.3	S	0.000267 U	0.00227 U	**0.148**	0.00152 U	0.00121 U	0.00133 U	0.00217 U	**0.125**	0.000965 U	0.00296 U	0.00135 U	0.00103 U
	MW-336-69	04/22/20	PES	PACE	69	-35.3	S	0.000285 U	0.00242 U	**0.0849**	0.00162 U	0.00129 U	0.00142 U	0.00231 U	**0.116**	0.00103 U	0.00316 U	0.00144 U	0.00109 U
	MW-336-74.5	04/22/20	PES	PACE	74.5	-40.8	S	0.000267 U	0.00227 U	0.00104 U	0.00151 U	0.00121 U	0.00133 U	0.00216 U	0.000680 U	0.000963 U	0.00296 U	0.00135 U	0.00102 U
	MW-336-79	04/22/20	PES	PACE	79	-45.3	S	0.000275 U	0.00234 U	0.00108 U	0.00156 U	0.00125 U	0.00137 U	0.00223 U	0.000701 U	0.000992 U	0.00305 U	0.00139 U	0.00106 U
	MW-336-85	04/22/20	PES	PACE	85	-51.3	S	0.000275 U	0.00234 U	0.00108 U	**0.00214 J**	0.00125 U	0.00137 U	0.00224 U	0.000702 U	0.000994 U	0.00305 U	0.00139 U	0.00106 U
	MW-2021-85	05/04/20	PES	PACE	85 (dup)	-51.3	S	0.000264 U	0.00224 U	**0.0670**	0.00150 U	0.00120 U	0.00131 U	0.00214 U	**0.0132**	0.000952 U	0.00292 U	0.00134 U	0.00101 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
MW-336 (continued)	MW-336-90	04/22/20	PES	PACE	90	-56.3	S	0.000276 U	0.00235 U	0.00108 U	**0.00210 J**	0.00125 U	0.00137 U	0.00224 U	0.000704 U	0.000997 U	0.00306 U	0.00140 U	0.00106 U
	MW-336-95	04/22/20	PES	PACE	95	-61.3	S	0.000275 U	0.00234 U	0.00108 U	0.00156 U	0.00125 U	0.00137 U	0.00224 U	0.000702 U	0.000994 U	0.00305 U	0.00139 U	0.00106 U
	MW-2020-95	04/22/20	PES	PACE	95 (dup)	-61.3	S	0.000273 U	0.00232 U	0.00107 U	0.00155 U	0.00124 U	0.00136 U	0.00221 U	0.000695 U	0.000985 U	0.00302 U	0.00138 U	0.00105 U
MW-338	MW-338-10	05/01/20	PES	PACE	10	17.8	S	0.000278 U	0.00236 U	0.00109 U	0.00158 U	0.00126 U	0.00138 U	0.00226 U	0.000708 U	0.00100 U	0.00308 U	0.00141 U	0.00107 U
	MW-338-15	05/01/20	PES	PACE	15	12.8	S	0.000303 U	0.00258 U	0.00118 U	**0.00262 J**	0.00138 U	0.00151 U	0.00246 U	0.000772 U	0.00109 U	0.00336 U	0.00153 U	0.00116 U
	MW-338-20	05/01/20	PES	PACE	20	7.8	S	0.000265 U	0.00226 U	0.00104 U	0.00151 U	0.00121 U	0.00132 U	0.00216 U	0.000677 U	0.000959 U	0.00294 U	0.00134 U	0.00102 U
	MW-338-23	05/01/20	PES	PACE	23	4.8	S	0.000291 U	0.00248 U	0.00114 U	0.00165 U	0.00132 U	0.00145 U	0.00236 U	0.000742 U	0.00105 U	0.00323 U	0.00147 U	0.00112 U
	MW-338-28	05/01/20	PES	PACE	28	-0.2	S	0.000288 U	0.00245 U	0.00113 U	0.00163 U	0.00131 U	0.00143 U	0.00234 U	0.000734 U	0.00104 U	0.00319 U	0.00146 U	0.00111 U
	MW-338-34	05/01/20	PES	PACE	34	-6.2	S	0.000256 U	0.00218 U	0.00100 U	**0.00219 J**	0.00116 U	0.00127 U	0.00208 U	0.000653 U	0.000924 U	0.00284 U	0.00130 U	**0.00329 J**
	MW-338-39	05/01/20	PES	PACE	39	-11.2	S	0.000277 U	0.00236 U	0.00109 U	0.00157 U	0.00126 U	0.00138 U	0.00225 U	0.000707 U	0.00100 U	0.00308 U	0.00140 U	0.00107 U
	MW-338-41	05/01/20	PES	PACE	41	-13.2	S	0.000282 U	0.00240 U	0.00110 U	0.00160 U	0.00128 U	0.00141 U	0.00229 U	0.000720 U	0.00102 U	0.00313 U	0.00143 U	0.00108 U
	MW-338-45	05/01/20	PES	PACE	45	-17.2	S	0.000280 U	0.00238 U	0.00109 U	0.00159 U	0.00127 U	0.00139 U	0.00227 U	0.000713 U	0.00101 U	0.00310 U	0.00142 U	0.00107 U
	MW-338-51	05/01/20	PES	PACE	51	-23.2	S	0.000284 U	0.00242 U	0.00111 U	0.00161 U	0.00129 U	0.00141 U	0.00231 U	0.000724 U	0.00102 U	0.00315 U	0.00144 U	0.00109 U
	MW-338-55	05/01/20	PES	PACE	55	-27.2	S	0.000263 U	0.00224 U	0.00103 U	0.00149 U	0.00119 U	0.00131 U	0.00214 U	0.000670 U	0.000949 U	0.00292 U	0.00133 U	0.00101 U
MW-341	MW-341-85	05/04/20	PES	PACE	85	-56.6	S	0.000260 U	0.00222 U	**0.0488**	0.00148 U	0.00118 U	0.00130 U	0.00211 U	**0.00855**	0.000940 U	0.00289 U	0.00132 U	0.00100 U
	MW-341-90	05/04/20	PES	PACE	90	-61.6	S	0.000258 U	0.00219 U	**0.0603**	0.00146 U	0.00117 U	0.00128 U	0.00209 U	**0.0549**	0.000930 U	0.00286 U	0.00130 U	0.000990 U
	MW-341-95	05/04/20	PES	PACE	95	-66.6	S	0.000267 U	0.00227 U	0.00104 U	0.00151 U	0.00121 U	0.00133 U	0.00217 U	0.000680 U	0.000964 U	0.00296 U	0.00135 U	0.00103 U
	MW-341-99	05/04/20	PES	PACE	99	-70.6	S	0.000268 U	0.00229 U	0.00105 U	0.00152 U	0.00122 U	0.00134 U	0.00218 U	0.000685 U	0.000970 U	0.00298 U	0.00136 U	0.00103 U
	MW-341-104	05/04/20	PES	PACE	104	-75.6	S	0.000273 U	0.00233 U	0.00107 U	0.00155 U	0.00124 U	0.00136 U	0.00222 U	0.000697 U	0.000986 U	0.00303 U	0.00138 U	0.00105 U
MW-343	MW-343-5	04/13/20	PES	PACE	5	22.6	V	0.000259 U	0.00220 U	0.00101 U	**0.0154**	0.00117 U	0.00129 U	0.00210 U	0.000660 U	0.000934 U	0.00287 U	0.00131 U	**0.0811**
	MW-343-10	04/13/20	PES	PACE	10	17.6	S	0.000271 U	0.00231 U	0.00106 U	**0.00605**	0.00123 U	0.00135 U	0.00220 U	0.000691 U	0.000979 U	0.00301 U	0.00137 U	**0.00855**
	MW-343-12.5	04/13/20	PES	PACE	12.5	15.1	S	0.000281 U	0.00239 U	0.00110 U	0.00160 U	0.00128 U	0.00140 U	0.00228 U	0.000717 U	0.00101 U	0.00312 U	0.00142 U	0.00108 U
	MW-343-17	04/13/20	PES	PACE	17	10.6	S	0.000263 U	0.00224 U	0.00103 U	**0.00795**	0.00120 U	0.00131 U	0.00214 U	0.000672 U	0.000951 U	0.00292 U	0.00133 U	0.00101 U
	MW-343-24	04/13/20	PES	PACE	24	3.6	S	0.000264 U	0.00225 U	0.00103 U	**0.0190**	0.00120 U	0.00131 U	0.00214 U	0.000673 U	0.000954 U	0.00293 U	0.00134 U	**0.00490 J**
	MW-343-28.5	04/13/20	PES	PACE	28.5	-0.9	S	0.000283 U	0.00241 U	0.00111 U	**0.0209**	0.00129 U	0.00141 U	0.00230 U	0.000722 U	0.00102 U	0.00314 U	0.00143 U	0.00109 U
	MW-343-35	04/13/20	PES	PACE	35	-7.4	S	0.000287 U	0.00244 U	0.00112 U	**0.00277 J**	0.00130 U	0.00143 U	0.00233 U	0.000731 U	0.00103 U	0.00318 U	0.00145 U	0.00110 U
	MW-343-38	04/13/20	PES	PACE	38	-10.4	S	0.000268 U	0.00228 U	0.00105 U	0.00152 U	0.00122 U	0.00133 U	0.00218 U	0.000683 U	0.000967 U	0.00297 U	0.00136 U	0.00103 U
	MW-343-44	04/13/20	PES	PACE	44	-16.4	S	0.000252 U	0.00215 U	0.000988 U	0.00143 U	0.00115 U	0.00126 U	0.00205 U	0.000644 U	0.000912 U	0.00280 U	0.00128 U	0.000970 U
	MW-343-47	04/13/20	PES	PACE	47	-19.4	S	0.000285 U	0.00243 U	0.00112 U	0.00162 U	0.00129 U	0.00142 U	0.00232 U	0.000727 U	0.00103 U	0.00316 U	0.00144 U	0.00110 U
	MW-343-51	04/13/20	PES	PACE	51	-23.4	S	0.000255 U	0.00217 U	0.000997 U	0.00145 U	0.00116 U	0.00127 U	0.00207 U	0.000650 U	0.000920 U	0.00283 U	0.00129 U	0.000979 U
	MW-343-55	04/13/20	PES	PACE	55	-27.4	S	0.000260 U	0.00222 U	0.00102 U	0.00148 U	0.00118 U	0.00130 U	0.00212 U	0.000664 U	0.000940 U	0.00289 U	0.00132 U	0.00100 U
	MW-343-62	04/13/20	PES	PACE	62	-34.4	S	0.000265 U	0.00226 U	0.00104 U	0.00150 U	0.00120 U	0.00132 U	0.00215 U	0.000676 U	0.000957 U	0.00294 U	0.00134 U	0.00102 U
	MW-343-68	04/13/20	PES	PACE	68	-40.4	S	0.000261 U	0.00222 U	0.00102 U	0.00148 U	0.00119 U	0.00130 U	0.00212 U	0.000666 U	0.000943 U	0.00290 U	0.00132 U	0.00100 U
	MW-343-73	04/13/20	PES	PACE	73	-45.4	S	0.000264 U	0.00225 U	0.00103 U	0.00150 U	0.00120 U	0.00131 U	0.00214 U	0.000673 U	0.000953 U	0.00293 U	0.00134 U	0.00101 U
	MW-343-79	04/13/20	PES	PACE	79	-51.4	S	0.000248 U	0.00211 U	0.000970 U	0.00141 U	0.00113 U	0.00123 U	0.00201 U	0.000632 U	0.000896 U	0.00275 U	0.00126 U	0.000953 U
	MW-343-82	04/13/20	PES	PACE	82	-54.4	S	0.000249 U	0.00212 U	0.000973 U	0.00141 U	0.00113 U	0.00124 U	0.00202 U	0.000634 U	0.000898 U	0.00276 U	0.00126 U	0.000956 U
	MW-343-86	04/13/20	PES	PACE	86	-58.4	S	0.000243 U	0.00207 U	0.000949 U	0.00138 U	0.00110 U	0.00121 U	0.00197 U	0.000619 U	0.000876 U	0.00269 U	0.00123 U	0.000932 U
	MW-343-93	04/13/20	PES	PACE	93	-65.4	S	0.000257 U	0.00218 U	0.00100 U	**0.00336 J**	0.00116 U	0.00128 U	0.00208 U	0.000654 U	0.000926 U	0.00285 U	0.00130 U	0.000986 U
	MW-343-99	04/13/20	PES	PACE	99	-71.4	S	0.000246 U	0.00209 U	0.000962 U	0.00140 U	0.00112 U	0.00122 U	0.00200 U	0.000627 U	0.000888 U	0.00273 U	0.00125 U	0.000945 U
	MW-343-102	04/14/20	PES	PACE	102	-74.4	S	0.000253 U	0.00215 U	0.000988 U	**0.00314 J**	0.00115 U	0.00126 U	0.00205 U	0.000644 U	0.000912 U	0.00280 U	0.00128 U	**0.00169 J**
	MW-2017-102	04/14/20	PES	PACE	102 (dup)	-74.4	S	0.000250 U	0.00213 U	0.000978 U	**0.00442 J**	0.00114 U	0.00124 U	0.00203 U	0.000638 U	0.000903 U	0.00277 U	0.00127 U	**0.00297 J**
	MW-343-106	04/14/20	PES	PACE	106	-78.4	S	**0.000289 J**	0.00209 U	0.000961 U	**0.00864**	0.00112 U	0.00122 U	0.00199 U	0.000626 U	0.000887 U	0.00272 U	0.00124 U	**0.00681 J**
	MW-343-108	04/14/20	PES	PACE	108	-80.4	S	0.000254 U	0.00216 U	0.000993 U	**0.00672**	0.00115 U	0.00126 U	0.00206 U	0.000647 U	0.000917 U	0.00282 U	0.00129 U	**0.00550 J**

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
PH22	PH22	04/17/18	PES	Fremont	0-3	–	V	0.0304 U	0.0304 U	0.0304 U	0.0243 U	0.0243 U	0.0243 U	–	0.0243 U	0.0243 U	–	0.0304 U	0.0912 U
PH34	PH34	04/17/18	PES	Fremont	1.5-6.5	–	V	0.0240 U	0.0240 U	0.0240 U	0.0192 U	0.0192 U	0.0192 U	–	0.0192 U	0.0192 U	–	0.0240 U	0.0721 U
PH38	PH38	04/17/18	PES	Fremont	1.5-4	–	V	0.0292 U	0.0292 U	0.0292 U	0.0233 U	0.0233 U	0.0233 U	–	0.0233 U	0.0233 U	–	0.0292 U	0.0875 U
PH52	PH52	04/17/18	PES	Fremont	1-5	–	V	0.0282 U	0.0282 U	0.0282 U	0.0226 U	0.0226 U	0.0226 U	–	0.0226 U	0.0226 U	–	0.0282 U	0.0846 U
PW-1	Composite	01/01/98	B&V	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
PW-4	Composite	05/13/98	B&V	Unknown	–	–	–	–	–	ND	ND	ND	–	–	ND	–	–	ND	ND
R-MW4	Unknown	10/22/92	Roux	Unknown	5	35.9	V	–	–	0.005 U	–	0.005 U	–	–	0.005 U	–	–	0.010 U	–
	Unknown	10/22/92	Roux	Unknown	15	25.9	S	–	–	0.005 U	–	0.005 U	–	–	0.005 U	–	–	0.010 U	–
	Unknown	10/22/92	Roux	Unknown	30	10.9	S	–	–	0.005 U	–	0.005 U	–	–	0.005 U	–	–	0.010 U	–
R-MW6	Unknown	10/27/92	Roux	Unknown	6	39.3	V	–	–	0.005 U	–	0.005 U	–	–	0.005 U	–	–	0.010 U	–
(33.3 to 23.3)	Unknown	10/27/92	Roux	Unknown	11	34.3	V	–	–	0.005 U	–	0.005 U	–	–	0.005 U	–	–	0.010 U	–
	Unknown	10/27/92	Roux	Unknown	16	29.3	S	–	–	0.005 U	–	0.005 U	–	–	0.005 U	–	–	0.010 U	–
RB1	RB1-17.5	10/18/93	Retec	AAL	17.5	18.4	S	–	–	–	0.063 U	–	–	–	–	–	–	–	0.13 U
RB2	RB2-12.5	10/18/93	Retec	AAL	12.5	23.6	V	–	–	–	0.062 U	–	–	–	–	–	–	–	0.012 U
	RB2-17.5	10/18/93	Retec	AAL	17.5	18.6	S	–	–	–	0.062 U	–	–	–	–	–	–	–	**0.18**
RB3	RB3-17.5	10/18/93	Retec	AAL	17.5	20.5	S	–	–	–	0.061 U	–	–	–	–	–	–	–	0.12 U
SCL-B100	B-100, S1	06/10/02	Urban	F&BI	5-6.5	–	V	–	–	0.05 U	0.02 U	0.05 U	–	–	0.05 U	–	–	0.05 U	0.02 U
	B-100, S2	06/10/02	Urban	F&BI	10-11.5	–	V	–	–	0.05 U	0.02 U	0.05 U	–	–	0.05 U	–	–	0.05 U	0.02 U
SCL-B101	B-101- S1&2	06/17/02	Urban	F&BI	0-6	–	V	–	–	0.05 U	0.02 U	0.05 U	–	–	0.05 U	–	–	0.05 U	0.02 U
	B101-S3	06/17/02	Urban	F&BI	8	–	V	–	–	0.05 U	0.02 U	0.05 U	–	–	0.05 U	–	–	0.05 U	0.02 U
SCL-B102	B102-S1	06/17/02	Urban	F&BI	0-3	–	V	–	–	0.05 U	**0.09**	0.05 U	–	–	0.05 U	–	–	0.05 U	**0.13**
	B102-S2	06/17/02	Urban	F&BI	4	–	V	–	–	0.05 U	0.02 U	0.05 U	–	–	0.05 U	–	–	0.05 U	0.02 U
SCL-MW101	MW101-S3	06/14/02	Urban	F&BI	16	–	S	–	–	–	0.02 U	–	–	–	–	–	–	–	**0.05**
(25.0 to 15.0)																			
SCL-MW102	MW-102, S1	06/10/02	Urban	F&BI	5-6.5	–	S	–	–	–	**0.47**	–	–	–	–	–	–	–	**2.5**
	MW-102, S2	06/10/02	Urban	F&BI	5-6.5, 10-11.5	–	S	–	–	–	0.02 U	–	–	–	–	–	–	–	**0.07**
SCL-MW103	MW103-S1&S2	06/14/02	Urban	F&BI	5-6.5, 10-11.5	–	S	–	–	–	0.02 U	–	–	–	–	–	–	–	0.02 U
SCL-MW105	MW-105, S2	06/10/02	Urban	F&BI	10-11.5	–	S	–	–	–	**1.5**	–	–	–	–	–	–	–	**24**
(10.8 to 0.8)	MW-105, S4	06/10/02	Urban	F&BI	20-21.5	–	S	–	–	–	0.02 U	–	–	–	–	–	–	–	**0.03**
SCLB-1	RS1-2.5/RS-1 7.5 (Comp)	03/12/93	EPJ	OnSite	2.5-7.5	–	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS1-12.5/RS1-17.5 (Comp)	03/12/93	EPJ	OnSite	12.5-17.5	–	S	–	–	–	**0.66**	–	–	–	–	–	–	–	**25.2** ve
	RS-1 17.5	03/12/93	EPJ	OnSite	17.5	21.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	RS1-22.5/RS-27.5 (Comp)	03/12/93	EPJ	OnSite	22.5-27.5	–	S	–	–	–	**0.14**	–	–	–	–	–	–	–	**1.53**
	RS1-32.5	03/12/93	EPJ	OnSite	32.5	6.0	S	–	–	–	**0.35**	–	–	–	–	–	–	–	**4.8**
	RS1-37.5	03/12/93	EPJ	OnSite	37.5	1.0	S	–	–	–	0.05 U	–	–	–	–	–	–	–	1 U
SCLB-2	RS2-2.5/RS-2 7.5 (Comp)	03/12/93	EPJ	OnSite	2.5-7.5	–	V	–	–	–	–	–	–	–	–	–	–	–	–
	RS2-12.5/RS2-17.5 (Comp)	03/12/93	EPJ	OnSite	12.5-17.5	–	S	–	–	–	**24**	–	–	–	–	–	–	–	**115** ve
	RS2-17.5	03/12/93	EPJ	OnSite	17.5	21.0	S	–	–	–	–	–	–	–	–	–	–	–	–
	RS2-22.5/RS2-27.5 (Comp)	03/12/93	EPJ	OnSite	22.5-27.5	–	S	–	–	–	**1.1**	–	–	–	–	–	–	–	**3.9**
	RS2-32.5	03/12/93	EPJ	OnSite	32.5	6.0	S	–	–	–	**2.7**	–	–	–	–	–	–	–	**6.8**
	RS2-37.5	03/12/93	EPJ	OnSite	37.5	1.0	S	–	–	–	0.05 U	–	–	–	–	–	–	–	**1.34**

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	**–**	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	**–**	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
SSD-MW-1	MW-1 S-2	05/24/89	HC	Unknown	5-6.5	34.0	V	–	–	–	0.01 U	–	–	–	–	–	–	–	0.01 U
	MW-1 S-6	05/24/89	HC	Unknown	15-16.5	24.0	S	–	–	–	**1.03**	–	–	–	–	–	–	–	**6.25**
SSD-MW-2	MW-2 S-3	05/24/89	HC	Unknown	7.5-9	31.0	V	–	–	–	0.01 U	–	–	–	–	–	–	–	0.01 U
	MW-2 S-6	05/24/89	HC	Unknown	15-16.5	31.0	V	–	–	–	**0.53**	–	–	–	–	–	–	–	0.01 U
SSD-MW-3	MW-3 S-2	05/24/89	HC	Unknown	5-6.5	34.0	V	–	–	–	0.01 U	–	–	–	–	–	–	–	0.01 U
	MW-3 S-5	05/24/89	HC	Unknown	12.5-14	34.0	V	–	–	–	0.01 U	–	–	–	–	–	–	–	0.01 U
SSD-MW-4	MW-4 S-6	05/25/89	HC	Unknown	14.5-16	36.8	V	–	–	–	0.01 U	–	–	–	–	–	–	–	**0.096**
	MW-4 S-9	05/25/89	HC	Unknown	22-23	29.5	S	–	–	–	0.01 U	–	–	–	–	–	–	–	0.01 U
SV-04	SV-04-6	06/29/20	PES	PACE	6	–	V	0.000297 U	0.00253 U	**0.00158 J**	0.00168 U	0.00135 UJ	0.00148 U	0.00241 UJ	0.000757 U	0.00107 U	0.00329 U	0.00150 U	0.00114 U
SV-05	SV-05-10	06/29/20	PES	PACE	10	–	V	0.000317 U	0.00270 U	**0.00184 J**	0.00180 U	0.00144 U	0.00158 U	0.00258 U	0.000809 U	0.00114 U	0.00352 UJ	0.00161 U	0.00122 U
SV-06	SV-06-6	06/29/20	PES	PACE	6	–	V	0.000292 U	0.00249 U	**0.00273 J**	0.00166 U	0.00133 U	0.00145 U	0.00237 U	0.000745 U	0.00106 U	0.00324 UJ	0.00148 U	0.00112 U
SV-07	SV-07-15	06/29/20	PES	PACE	15	–	V	0.000251 U	0.00214 U	0.000982 U	0.00142 U	0.00114 U	0.00125 U	0.00204 U	0.000640 U	0.000906 U	0.00278 UJ	0.00127 U	0.000965 U
SV-08	SV-08-6	06/30/20	PES	PACE	6	–	V	0.000318 U	0.00271 U	**0.00538**	**0.00495 J**	0.00145 U	0.00159 U	0.00259 U	0.000812 U	0.00115 U	0.00353 UJ	0.00161 U	**0.0259**
	SV-08-7.5	06/30/20	PES	PACE	7.5	–	V	0.000325 U	0.00276 U	0.00127 U	0.00184 U	0.00147 UJ	0.00162 U	0.00264 UJ	0.000828 U	0.00117 U	0.00360 U	0.00164 U	**0.00276 J**
SV-09	SV-09-5.5	07/01/20	PES	PACE	5.5	–	V	0.000303 U	0.00258 U	0.00119 U	0.00172 U	0.00138 UJ	0.00151 U	0.00246 UJ	0.000773 U	0.00109 U	0.00336 U	0.00154 U	0.00116 U
SV-10	SV-10-5.5	06/30/20	PES	PACE	5.5	–	V	0.000302 U	0.00257 U	0.00118 U	0.00171 U	0.00137 UJ	0.00150 U	0.00245 UJ	0.000770 U	0.00109 U	0.00335 U	0.00153 U	0.00116 U
SV-11	SV-11-10	06/30/20	PES	PACE	10	–	V	0.000306 U	0.00261 U	0.00120 U	0.00174 U	0.00139 UJ	0.00152 U	0.00249 UJ	0.000781 U	0.00111 U	0.00340 U	0.00155 U	0.00118 U
SV-12	SV-12-5.5	07/01/20	PES	PACE	5.5	–	V	0.000250 U	0.00213 U	0.000980 U	**0.0160**	0.00114 UJ	0.00125 U	0.00203 UJ	0.000638 U	0.000904 U	0.00278 U	0.00127 U	**0.00542 J**
SV-13	SV-13-10.5	07/01/20	PES	PACE	10.5	–	V	0.000294 U	0.00250 U	0.00115 U	0.00167 U	0.00133 UJ	0.00146 U	0.00239 UJ	0.000749 U	0.00106 U	0.00326 U	0.00149 U	0.00113 U
SV-14	SV-14-5.5	07/01/20	PES	PACE	5.5	–	V	0.000306 U	0.00261 U	0.00120 U	0.00174 U	0.00139 UJ	0.00152 U	0.00249 UJ	0.000781 U	0.00111 U	0.00340 U	0.00155 U	0.00118 U
SV-15	SV-15-13	07/01/20	PES	PACE	13	–	V	0.000297 U	0.00253 U	0.00116 U	0.00169 U	0.00135 UJ	0.00148 U	0.00241 UJ	0.000758 U	0.00107 U	0.00330 U	0.00151 U	0.00114 U
SV-16	SV-16-5	07/02/20	PES	PACE	5	–	V	0.000608 U	0.00517 U	**0.0237 J**	**0.0538 J**	0.00277 UJ	0.00303 U	0.00494 UJ	0.00155 U	0.00220 U	0.00675 U	0.00307 U	**0.0743 J**
	SV-100-5	07/02/20	PES	PACE	5 (dup)	–	V	0.000545 U	0.00464 U	**0.0175 J**	**0.0381 J**	0.00246 UJ	0.00271 U	0.00441 UJ	0.00139 U	0.00197 U	0.00603 U	0.00276 U	**0.0441 J**
SV-17	SV-17-4.5	07/02/20	PES	PACE	4.5	–	V	0.000450 U	0.00384 U	**0.00584**	**0.0678**	0.00204 UJ	0.00224 U	0.00366 UJ	0.00115 U	0.00163 U	0.00500 U	0.00228 U	**0.126**
SV-18	SV-18-5.5	07/02/20	PES	PACE	5.5	–	V	0.000247 U	0.00210 U	0.000966 U	0.00140 U	0.00112 UJ	0.00123 U	0.00200 UJ	0.000629 U	0.000891 U	0.00274 U	0.00125 U	0.000948 U
SV-19	SV-19-5	07/09/20	PES	PACE	5	–	V	0.000247 U	0.00210 U	**0.00169 J**	0.00140 U	0.00112 U	0.00123 U	0.00200 U	0.000629 U	0.000891 U	0.00274 U	0.00125 U	0.000948 U
SV-20	SV-20-9	07/09/20	PES	PACE	9	–	V	0.000324 U	0.00276 U	**0.00275 J**	0.00184 U	0.00147 U	0.00161 U	0.00263 U	0.000827 U	0.00117 U	0.00360 U	0.00164 U	0.00125 U
SV-21	SV-21-6	07/09/20	PES	PACE	6	–	V	0.000251 U	0.00214 U	**0.00117 J**	0.00142 U	0.00114 U	0.00125 U	0.00204 U	0.000640 U	0.000906 U	0.00278 U	0.00127 U	0.000964 U
SV-22	SV-22-8.5	07/09/20	PES	PACE	8.5	–	V	0.000468 U	0.00399 U	**0.00705**	**0.00520 J**	0.00212 U	0.00233 U	0.00380 U	0.00119 U	0.00169 U	0.00518 U	0.00237 U	**0.0113 J**
SV-23	SV-23-4.5	07/09/20	PES	PACE	4.5	–	V	0.000346 U	0.00295 U	0.00135 U	0.00197 U	0.00157 U	0.00172 U	0.00281 U	0.000883 U	0.00125 U	0.00384 U	0.00175 U	0.00133 U
SV-24	SV-24-8	07/09/20	PES	PACE	8	–	V	0.000249 U	0.00212 U	0.000973 U	0.00141 U	0.00113 U	0.00124 U	0.00202 U	0.000634 U	0.000898 U	0.00276 U	0.00126 U	0.000955 U
SV-25	SV-25-4	07/10/20	PES	PACE	4	–	V	0.000302 U	0.00257 U	**0.0100**	0.00171 U	0.00137 U	0.00150 U	0.00245 U	0.000769 U	0.00109 U	0.00335 U	0.00153 U	0.00116 U
SV-26	SV-26-12	07/10/20	PES	PACE	12	–	V	0.000335 U	0.00285 U	0.00131 U	0.00190 U	0.00152 U	0.00167 U	0.00272 U	0.000855 U	0.00121 U	0.00372 U	0.00170 U	0.00129 U
SV-27	SV-27-5.5	07/10/20	PES	PACE	5.5	–	V	0.000301 U	0.00256 U	0.00118 U	0.00171 U	0.00136 U	0.00150 U	0.00244 U	0.000766 U	0.00109 U	0.00333 U	0.00152 U	0.00115 U
	SV-27-13.5	07/10/20	PES	PACE	13.5	–	V	0.000301 U	0.00256 U	**0.00372**	0.00171 U	0.00137 U	0.00150 U	0.00244 U	0.000767 U	0.00109 U	0.00334 U	0.00152 U	0.00116 U
TB-12	16	08/01/97	B&V	Unknown	62-63	-24.5	S	–	–	–	–	–	–	–	–	–	–	–	–
TB-18	S-2	03/17/98	B&V	Unknown	5-6.5	38.3	V	–	–	ND	ND	ND	–	–	ND	–	–	ND	ND
	S-8	03/17/98	B&V	Unknown	20-21.5	23.3	S	–	–	ND	ND	ND	–	–	ND	–	–	ND	ND
	S-21	03/17/98	B&V	Unknown	57.5-59	1.2	S	–	–	ND	ND	ND	–	–	ND	–	–	ND	ND

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	**–**	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	**–**	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
T1	T1-2.5-071718	07/17/18	PES	Fremont	2.5	–	V	0.0265 U	0.0265 U	**0.0734**	0.0212 U	0.0212 U	0.0212 U	–	0.0212 U	0.0212 U	–	0.0265 U	0.0796 U
T-2	T-2-071618	07/16/18	PES	Fremont	2	–	V	0.0143 U	0.0143 U	0.0143 U	0.0115 U	0.0115 U	0.0115 U	–	0.0115 U	0.0115 U	–	0.0143 U	0.0143 U
T-2B	T-2B-071618	07/16/18	PES	Fremont	2	–	V	0.0297 U	0.0297 U	0.0297 U	0.0237 U	0.0237 U	0.0237 U	–	0.0237 U	0.0237 U	–	0.0297 U	0.0297 U
T2	T2-6-071718	07/17/18	PES	Fremont	6	–	V	0.0307 U	0.0307 U	**0.0524**	0.0245 U	0.0245 U	0.0245 U	–	0.0245 U	0.0245 U	–	0.0307 U	**0.0524**
T3	T3-3-071718	07/17/18	PES	Fremont	3	–	V	0.0287 U	0.0287 U	0.0287 U	0.0229 U	0.0229 U	0.0229 U	–	0.0229 U	0.0229 U	–	0.0287 U	0.0287 U
T4	T4-6-071718	07/17/18	PES	Fremont	6	–	V	0.0258 U	0.0258 U	0.0258 U	0.0206 U	0.0206 U	0.0206 U	–	0.0206 U	0.0206 U	–	0.0258 U	0.0258 U
T-5	T-5-071618	07/16/18	PES	Fremont	5	–	V	0.0255 U	0.0255 U	0.0255 U	0.0204 U	0.0204 U	0.0204 U	–	0.0204 U	0.0204 U	–	0.0255 U	0.0255 U
T6	T6-4-071818	07/18/18	PES	Fremont	4	–	V	0.0237 U	0.0237 U	0.0237 U	0.0189 U	0.0189 U	0.0189 U	–	0.0189 U	0.0189 U	–	0.0237 U	0.0237 U
T7	T7-7-071818	07/18/18	PES	Fremont	7	–	V	0.0342 U	0.0342 U	**0.0678**	0.0274 U	0.0274 U	0.0274 U	–	0.0274 U	0.0274 U	–	0.0342 U	**0.0678**
T8	T8-3-072018	07/20/18	PES	Fremont	3	–	V	0.0268 U	0.0268 U	0.0268 U	0.0214 U	0.0214 U	0.0214 U	–	0.0214 U	0.0214 U	–	0.0268 U	0.0268 U
T8	T8-6-072018	07/20/18	PES	Fremont	6	–	V	0.0377 U	0.0377 U	**0.0586**	0.0301 U	0.0301 U	0.0301 U	–	0.0301 U	0.0301 U	–	0.0377 U	**0.0586**
T9	T9-3-072018	07/20/18	PES	Fremont	3	–	V	0.0437 U	0.0437 U	0.0437 U	0.0350 U	0.0350 U	0.0350 U	–	0.0350 U	0.0350 U	–	0.0437 U	0.0437 U
T9	T9-3.5-072018	07/20/18	PES	Fremont	3.5	–	V	0.0291 U	0.0291 U	0.0291 U	0.0233 U	0.0233 U	0.0233 U	–	0.0233 U	0.0233 U	–	0.0291 U	0.0291 U
T9	T9-6-072018	07/20/18	PES	Fremont	6	–	V	0.0303 U	0.0303 U	0.0303 U	0.0242 U	0.0242 U	0.0242 U	–	0.0242 U	0.0242 U	–	0.0303 U	0.0303 U
T10	T10-3-072018	07/20/18	PES	Fremont	3	–	V	0.0513 U	0.0513 U	0.0513 U	**0.0461**	0.0411 U	0.0411 U	–	0.0411 U	0.0411 U	–	0.0513 U	0.0513 U
T10	T10-6-072018	07/20/18	PES	Fremont	6	–	V	0.0278 U	0.0278 U	0.0278 U	0.0222 U	0.0222 U	0.0222 U	–	0.0222 U	0.0222 U	–	0.0278 U	0.0278 U
T11	T11-3.5-073118	07/31/18	PES	Fremont	3.5	–	V	0.0358 U	0.0358 U	0.0358 UJ	0.0286 U	0.0286 U	0.0286 U	–	0.0286 U	0.0286 U	–	0.0358 U	0.0358 U
T12	T12-3-091818	09/18/18	PES	Fremont	3	–	V	0.0307 U	0.0307 U	0.0307 U	0.0245 U	0.0245 U	0.0245 U	–	0.0245 U	0.0245 U	–	0.0307 U	0.0614 U
T12	T12-7-091818	09/18/18	PES	Fremont	7	–	V	0.0303 U	0.0303 U	0.0303 U	0.0243 U	0.0243 U	0.0243 U	–	0.0243 U	0.0243 U	–	0.0303 U	0.0607 U
T12	T12-7.5-073118	07/31/18	PES	Fremont	7.5	–	V	0.0259 U	0.0259 U	0.0259 UJ	0.0207 U	0.0207 U	0.0207 U	–	0.0207 U	0.0207 U	–	0.0259 U	0.0259 U
T13	T13-3.5-091818	09/18/18	PES	Fremont	3.5	–	V	0.0283 U	0.0283 U	**0.0323**	0.0227 U	0.0227 U	0.0227 U	–	0.0227 U	0.0227 U	–	0.0283 U	0.0567 U
T13	T13-6.5-091818	09/18/18	PES	Fremont	6.5	–	V	0.0250 U	0.0250 U	**0.154**	0.0200 U	0.0200 U	0.0200 U	–	0.0200 U	0.0200 U	–	0.0250 U	0.0500 U
T14	T14-3.5-091818	09/18/18	PES	Fremont	3.5	–	V	0.0300 U	0.0300 U	**0.0364**	0.0240 U	0.0240 U	0.0240 U	–	0.0240 U	0.0240 U	–	0.0300 U	0.0599 U
T14	T14-7-091818	09/18/18	PES	Fremont	7	–	V	0.0318 U	0.0318 U	**0.0353**	0.0254 U	0.0254 U	0.0254 U	–	0.0254 U	0.0254 U	–	0.0318 U	0.0635 U
TP-15	TP-15-3-092818	09/28/18	PES	Fremont	3	–	V	0.0304 U	0.0304 U	0.0304 U	0.0244 U	0.0244 U	0.0244 U	–	0.0244 U	0.0244 U	–	0.0304 U	0.0609 U
TP-15	TP-15-6.5-092818	09/28/18	PES	Fremont	6.5	–	V	0.0313 U	0.0313 U	0.0313 U	0.0250 U	0.0250 U	0.0250 U	–	0.0250 U	0.0250 U	–	0.0313 U	0.0625 U
TP-16	TP-16-3-092818	09/28/18	PES	Fremont	3	–	V	0.0426 U	0.0426 U	0.0426 U	0.0341 U	0.0341 U	0.0341 U	–	0.0341 U	0.0341 U	–	0.0426 U	0.0426 U
TP-16	TP-16-6-092818	09/28/18	PES	Fremont	6	–	V	0.0446 U	0.0446 U	0.0446 U	0.0357 U	0.0357 U	0.0357 U	–	0.0357 U	0.0357 U	–	0.0446 U	0.0446 U
TP-16	TP-16-9-092818	09/28/18	PES	Fremont	9	–	V	0.0263 U	0.0263 U	0.0263 U	0.0210 U	0.0210 U	0.0210 U	–	0.0210 U	0.0210 U	–	0.0263 U	0.0263 U
TP-SD-01	TP-SD-01-2	06/03/19	PES	Fremont	2	–	V	0.0214 U	0.0214 U	**0.0546**	**0.0196**	0.0172 U	0.0172 U	–	0.0172 U	0.0172 U	–	0.0214 U	**0.169**
TP-SD-01	TP-SD-01-5	06/03/19	PES	Fremont	5	–	V	0.0267 U	0.0267 U	0.0267 U	0.0213 U	0.0213 U	0.0213 U	–	0.0213 U	0.0213 U	–	0.0267 U	0.0534 U
TP-SD-04	TP-SD-04-2	06/03/19	PES	Fremont	2	–	V	0.0252 U	0.0252 U	0.0252 U	0.0202 U	0.0202 U	0.0202 U	–	0.0202 U	0.0202 U	–	0.0252 U	0.0504 U
TP-SD-04	TP-SD-04-5	06/03/19	PES	Fremont	5	–	V	0.0272 U	0.0272 U	0.0272 U	0.0218 U	0.0218 U	0.0218 U	–	0.0218 U	0.0218 U	–	0.0272 U	0.0544 U
TP-SD-05	TP-SD-05-2	06/03/19	PES	Fremont	2	–	V	0.0258 U	0.0258 U	0.0258 U	0.0207 U	0.0207 U	0.0207 U	–	0.0207 U	0.0207 U	–	0.0258 U	0.0517 U
TP-SD-05	TP-SD-05-5	06/03/19	PES	Fremont	5	–	V	0.0292 U	0.0292 U	0.0292 U	0.0234 U	0.0234 U	0.0234 U	–	0.0234 U	0.0234 U	–	0.0292 U	0.0585 U
TP-SD-06	TP-SD-06-2	06/03/19	PES	Fremont	2	–	V	0.0344 U	0.0344 U	0.0344 U	0.0275 U	0.0275 U	0.0275 U	–	0.0275 U	0.0275 U	–	0.0344 U	0.0688 U
TP-SD-06	TP-SD-06-5	06/03/19	PES	Fremont	5	–	V	0.0272 U	0.0272 U	0.0272 U	0.0218 U	0.0218 U	0.0218 U	–	0.0218 U	0.0218 U	–	0.0272 U	0.0544 U
TP-SD-07	TP-SD-07-2	06/03/19	PES	Fremont	2	–	V	0.0217 U	0.0217 U	0.0217 U	0.0174 U	0.0174 U	0.0174 U	–	0.0174 U	0.0174 U	–	0.0217 U	0.0435 U
TP-SD-07	B-942-2	06/03/19	PES	Fremont	2 (dup)	–	V	0.0233 U	0.0233 U	0.0233 U	0.0186 U	0.0186 U	0.0186 U	–	0.0186 U	0.0186 U	–	0.0233 U	0.0466 U
TP-SD-07	TP-SD-07-5	06/03/19	PES	Fremont	5	–	V	0.0212 U	0.0212 U	0.0212 U	0.0169 U	0.0169 U	0.0169 U	–	0.0169 U	0.0169 U	–	0.0212 U	0.0424 U
TP-SD-08	TP-SD-08-2	06/03/19	PES	Fremont	2	–	V	0.0242 U	0.0242 U	0.0242 U	0.0193 U	0.0193 U	0.0193 U	–	0.0193 U	0.0193 U	–	0.0242 U	0.0483 U
TP-SD-08	TP-SD-08-5	06/03/19	PES	Fremont	5	–	V	0.0207 U	0.0207 U	0.0207 U	0.0166 U	0.0166 U	0.0166 U	–	0.0166 U	0.0166 U	–	0.0207 U	0.0415 U
TP-SD-08	TP-SD-08-8	06/03/19	PES	Fremont	8	–	S	0.0249 U	0.0249 U	0.0249 U	0.0199 U	0.0199 U	0.0199 U	–	0.0199 U	0.0199 U	–	0.0249 U	0.0498 U
W-MW-01 (P-03)	SB-W-03-0160	01/27/12	WW	ARI	16-16.5	28.4	S	–	–	0.0010 U	**0.0006 J**	0.0010 U	–	–	0.0010 U	–	–	0.0010 U	0.0020 U
(-25.1 to -35.1)	SB-W-03-0225	01/27/12	WW	ARI	22.5-23	21.9	S	–	–	**0.03 B**	**0.0007 J**	0.0009 U	–	–	**0.0018**	–	–	0.0009 U	0.0018 U
	SB-W-03-0315	01/27/12	WW	ARI	31.5-32	12.9	S	–	–	**16 B**	0.21 U	0.21 U	–	–	**0.59**	–	–	0.21 U	0.42 U
	SB-W-03-0450	01/27/12	WW	ARI	45-45.5	-0.6	S	–	–	**0.38 B**	**0.0006 J**	**0.0005 J**	–	–	**0.022**	–	–	0.0007 U	0.0014 U
	SB-W-03-0550	01/27/12	WW	ARI	55.5-56	-11.1	S	–	–	**1.9 J**	0.045 U	0.045 U	–	–	**0.17**	–	–	0.045 U	0.09 U

Table G-3

Off Property Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	**–**	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	**–**	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
W-MW-01 (P-03)	SB-W-03-0645	01/27/12	WW	ARI	64.5-65	-20.1	S	–	–	0.0008 U	0.0008 U	0.0008 U	–	–	0.0008 U	–	–	0.0008 U	0.0016 U
(continued)	SB-W-03-0730	01/27/12	WW	ARI	73-73.5	-28.6	S	–	–	**0.1 B**	**0.0006 J**	0.0007 U	–	–	**0.0081**	–	–	0.0007 U	0.0014 U
W-MW-02 (P-06)	SB-W-06-0900	01/29/12	WW	ARI	9-9.5	34.0	S	–	–	**0.058 T**	0.0013 U	0.0013 U	–	–	**0.0081**	–	–	0.0013 U	0.0026 U
(-26.5 to -36.5)	SB-W-06-0185	01/29/12	WW	ARI	18.5-19	24.5	S	–	–	0.0009 UT	**0.0006 J**	0.0009 U	–	–	0.0009 U	–	–	0.0009 U	0.0018 U
	SB-W-06-0305	01/30/12	WW	ARI	30.5-31	12.6	S	–	–	**18**	0.27 U	0.27 U	–	–	**0.41**	–	–	0.27 U	0.34 U
	SB-W-06-0380	01/30/12	WW	ARI	38-38.5	5.0	S	–	–	**0.14**	0.046 U	0.046 U	–	–	**0.057**	–	–	0.046 U	0.092 U
	SB-W-06-0405	01/30/12	WW	ARI	40.5-41	2.5	S	–	–	**5.2**	0.036 U	0.036 U	–	–	**0.2**	–	–	0.036 U	0.072 U
	SB-W-06-0485	01/30/12	WW	ARI	48.5-49	-5.5	S	–	–	**0.033**	0.0008 U	0.0008 U	–	–	**0.0007 J**	–	–	0.0008 U	0.0016 U
	SB-W-06-9485	01/30/12	WW	ARI	48.5-49 (dup)	-5.5	S	–	–	**0.052**	0.0009 U	0.0009 U	–	–	**0.0011**	–	–	0.0009 U	0.0018 U
	SB-W-06-0590	01/30/12	WW	ARI	59-59.5	-16.0	S	–	–	**0.53**	0.043 U	0.043 U	–	–	**0.037 J**	–	–	0.043 U	0.086 U
	SB-W-06-0715	01/30/12	WW	ARI	71.5-72	-28.5	S	–	–	**0.0009**	0.0008 U	0.0008 U	–	–	0.0008 U	–	–	0.0008 U	0.0016 U
	SB-W-06-0790	01/31/12	WW	ARI	79-79.5	-36.0	S	–	–	**0.0022**	0.0009 U	0.0009 U	–	–	0.0009 U	–	–	0.0009 U	0.0018 U
All Data	Number of Analytes Measured							644	644	865	778	859	644	585	865	644	585	865	778
	Number of Analytes Detected							8	3	26	227	-172	0	7	-81	40	1	-146	-11
	Frequency of Detection							1.2%	0.5%	3.0%	29.2%	-20.0%	0.0%	1.2%	-9.4%	6.2%	0.2%	-16.9%	-1.4%
	Maximum Detection							0.0102 J	0.0875 J	19	160	0.0221	–	0.456	3.57	0.0638 J	0.0588 J	0.656	300
	Minimum Detection							0.00024 U	0.000214 U	0.000289 U	0.000454 U	0.000274 U	0.000277 U	0.000808 U	0.00029 U	0.000397 U	0.00248 U	0.000302 U	0.00073 U
	Number Of Vadose (V) Detections above SL							0	0	21	0	0	0	–	2	0	0	0	0
	Number of Saturated (S) Detections above SL							0	0	102	14	0	0	–	91	0	0	41	16
2017-2021	Number of Analytes Measured							644	644	644	644	644	644	585	644	644	585	644	644
	Number of Analytes Detected							8	3	201	328	32	0	7	103	40	1	65	87
	Frequency of Detection							1.2%	0.5%	31.2%	50.9%	5.0%	0.0%	1.2%	16.0%	6.2%	0.2%	10.1%	13.5%
	Maximum Detection							0.0102 J	0.0875 J	15.1	0.382	0.0221	–	0.456	3.57	0.0638 J	0.0588 J	0.656	0.891
	Minimum Detection							0.00024 U	0.000214 U	0.000289 U	0.000454 U	0.000274 U	0.000277 U	0.000808 U	0.00029 U	0.000397 U	0.00248 U	0.000302 U	0.00073 U
	Number Of Vadose (V) Detections above SL							0	0	21	0	0	0	–	2	0	0	0	0
	Number of Saturated (S) Detections above SL							0	0	67	1	0	0	–	65	0	0	40	0

Abbreviations:
AAL = Alden Analytical Laboratories, Inc., of Seattle, Washington
ARI = Analytical Resource, Incorporated, Seattle, Washington
B&V = Black Veatch
bgs = below ground surface
Comp = Composite Sample
dup = duplicate
EPJ = E.PJohnson Construction Inc., and Environmental
ESC = ESC Lab Services of Mt. Juliet, Tennessee
F&BI = Friedman & Bruya, Inc.
HC = Hart Crowser, Inc.
OnSite = OnSite Environmental Inc., of Redmond, Washington
Pace = Pace Analytical of Mt. Juliet, Tennessee (formerly ESC)
PES = PES Environmental, Inc.
Retec = Remediation Technologies, Inc.
Roux = Roux Associates
Urban = Urban Redevelopment LLC
WW = WW Environmental LLC

Notes:
Petroleum Hydrocarbons (PHCs) analyzed by Ecology Methods NWTPH-HCID, NWTPH-Gx, or NWTPH-Dx; or EPA Method 418.1, Method 8020, or Method 8015M.
VOCs analyzed by EPA Methods 8010, 8020, 8021B, 624/8240, or 8260B/C/D.
Well screen elevations provided below Sample Location. in parentheses when appliable.
PCUL = Preliminary Cleanup Level from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021. PCULs based on the practical quantitation limits (PQLs) italicized.
Detected results shown in **bold**.
Detections above the screening level in the vadose zone are shown in **bold and highlighted blue**.
Detections above the screening level in the saturated zone are shown in **bold and highlighted gray.**
– = Not available or results not analyzed.
B = Analyte detected in an associated method blank.
J = The reported concentration is an estimate based on detectable results between the method detection limit and reporting limit, laboratory QA/QC, or data validation review.
J+ = The result is an estimated quantity, but the result may be biased high.
J- = The result is an estimated quantity, but the result may be biased low.
ND = Not detected above laboratory reporting limit. Reporting limit not available.
R = The data is unusable. The sample result is rejected due to serious deficiencies in meeting QC criteria. The analyte may or may not be present in the sample
T = Analyte also detected in trip blank.
U = Not detected at a concentration exceeding laboratory reporting limit
ve = Estimated value. The reported range exceeds the calibration range of the analysis.
z = Gasoline/petroleum detection result is likely elevated due to high detections of CVOCs.

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	**–**	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	**–**	**0.030**	**1.5E-07**
615 Dexter Avenue																					
DGW-1	DGW1-10	03/06/19	HC	AAL	10	37	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW1-12.5	03/06/19	HC	AAL	12.5	34.5	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW1-15	03/06/19	HC	AAL	15	32	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW1-25	03/06/19	HC	AAL	25	22	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW1-30	03/06/19	HC	AAL	30	17	S	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
DGW-2	DGW2-5	03/04/19	HC	AAL	5	54	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW2-10	03/04/19	HC	AAL	10	49	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW2-25	03/04/19	HC	AAL	25	34	S	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW2-30	03/04/19	HC	AAL	30	29	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
DGW-3	DGW3-2.5	03/06/19	HC	AAL	2.5	44.5	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW3-12.5	03/06/19	HC	AAL	12.5	34.5	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW3-15	03/06/19	HC	AAL	15	32	S	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW3-20	03/06/19	HC	AAL	20	27	S	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW3-25	03/06/19	HC	AAL	25	22	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
DGW-4	DGW4-5	03/04/19	HC	AAL	5	60	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW4-10	03/04/19	HC	AAL	10	55	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW4-15	03/04/19	HC	AAL	15	50	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW4-20	03/04/19	HC	AAL	20	45	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW4-35	03/04/19	HC	AAL	35	30	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW4-50	03/04/19	HC	AAL	50	15	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
DMW-1S	DMW1S-5	03/05/19	HC	AAL	5	42	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DMW1S-10	03/05/19	HC	AAL	10	37	V	**29**	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DMW1S-12.5	03/05/19	HC	AAL	12.5	34.5	S	**1,200**	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DMW1S-15	03/05/19	HC	AAL	15	32	S	**67**	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DMW1S-20	03/05/19	HC	AAL	20	27	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
DMW-2S	DMW-2S-05	03/02/20	HC	AAL	5	51.03	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	DMW-2S-10	03/02/20	HC	AAL	10	46.03	V	**83**	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	DMW-2S-15	03/02/20	HC	AAL	15	41.03	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	DMW-2S-20	03/02/20	HC	AAL	20	36.03	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	DMW-2S-25	03/02/20	HC	AAL	25	31.03	S	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
DMW-3IA	DMW-3IA-5	02/27/20	HC	AAL	5	51.09	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	DMW-3IA-10	02/27/20	HC	AAL	10	46.09	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	DMW-3IA-15	02/27/20	HC	AAL	15	41.09	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	DMW-3IA-20	02/27/20	HC	AAL	20	36.09	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	DMW-3IA-25	02/27/20	HC	AAL	25	31.09	S	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
DMW-4S	DMW-4S-5	02/26/20	HC	AAL	5	56.76	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	DMW-4S-10	02/26/20	HC	AAL	10	51.76	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	DMW-4S-15	02/26/20	HC	AAL	15	46.76	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	DMW-4S-20	02/26/20	HC	AAL	20	41.76	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	DMW-4S-25	02/26/20	HC	AAL	25	36.76	S	**35**	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	DMW-4S-30	02/26/20	HC	AAL	30	31.76	S	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
DMW-5IA	DMW-5IA-5	02/28/20	HC	AAL	5	64.48	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	DMW-5IA-10	02/28/20	HC	AAL	10	59.48	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	DMW-5IA-15	02/28/20	HC	AAL	15	54.48	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	DMW-5IA-20	02/28/20	HC	AAL	20	49.48	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	DMW-5IA-25	02/28/20	HC	AAL	25	44.48	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
DPP-1	DPP1-5	03/04/19	HC	AAL	5	54.5	V	5.0 U	–	5.0 U	5.0 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP1-7.5	03/05/19	HC	AAL	7.5	52	V	–	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP1-10	03/04/19	HC	AAL	10	49.5	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP1-20	03/04/19	HC	AAL	20	39.5	V	–	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
DPP-2	DPP2-5	03/04/19	HC	AAL	5	54	V	–	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP2-10	03/04/19	HC	AAL	10	49	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
DPP-3	DPP3-5	03/05/19	HC	AAL	5	42	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP3-15	03/05/19	HC	AAL	15	32	S	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP3-30	03/05/19	HC	AAL	30	17	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
DPP-4	DPP4-10	03/04/19	HC	AAL	10	49	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP4-12.5	03/04/19	HC	AAL	12.5	46.5	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP4-17.5	03/04/19	HC	AAL	17.5	41.5	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP4-20	03/04/19	HC	AAL	20	39	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
DPP-5	DPP5-10	03/04/19	HC	AAL	10	49	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP5-17.5	03/04/19	HC	AAL	17.5	41.5	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP5-20	03/04/19	HC	AAL	20	39	V	–	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
DPP-6	DPP6-5	03/05/19	HC	AAL	5	42	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP6-7.5	03/05/19	HC	AAL	7.5	39.5	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP6-12.5	03/05/19	HC	AAL	12.5	34.5	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP6-17.5	03/05/19	HC	AAL	17.5	29.5	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	**–**	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	**–**	**0.030**	**1.5E-07**
Seattle DOT Mercer Parcels																					
HMW-1IB	HMW1IB-7.5	03/12/19	HC	AAL	7.5	30.5	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW1IB-15	03/12/19	HC	AAL	15	23	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW1IB-20.5	03/12/19	HC	AAL	20.5	18	S	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW1IB-27.5	03/12/19	HC	AAL	27.5	10.5	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW1IB-50	03/12/19	HC	AAL	50	-12	S	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW1IB-65	03/12/19	HC	AAL	65	-27	S	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
HMW-2IB	HMW2IB-7.5	03/12/19	HC	AAL	7.5	39.5	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW2IB-15	03/12/19	HC	AAL	15	32	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW2IB-22.5	03/12/19	HC	AAL	22.5	24.5	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW2IB-30	03/12/19	HC	AAL	30	17	S	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW2IB-45	03/12/19	HC	AAL	45	2	S	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW2IB-65	03/12/19	HC	AAL	65	-18	S	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
HMW-3IA	HMW3IA-15	03/15/19	HC	AAL	15	40.5	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW3IA-20	03/15/19	HC	AAL	20	35.5	V	–	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW3IA-22.5	03/15/19	HC	AAL	22.5	33	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW3IA-25	03/15/19	HC	AAL	25	30.5	S	–	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
HMW-4IA	HMW4IA-5	03/07/19	HC	AAL	5	51	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW4IA-7.5	03/07/19	HC	AAL	7.5	48.5	V	5.0 UJ	**160**	50 U	**160**	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW4IA-10	03/07/19	HC	AAL	10	46	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW4IA-25	03/07/19	HC	AAL	25	31	S	–	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
HMW-5IB	HMW5IB-5	02/28/20	HC	AAL	5	53.44	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW5IB-10	02/28/20	HC	AAL	10	48.44	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW5IB-15	02/28/20	HC	AAL	15	43.44	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW5IB-20	02/28/20	HC	AAL	20	38.44	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW5IB-25	02/28/20	HC	AAL	25	33.44	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
HMW-6D	HMW-6D-5	03/02/20	HC	AAL	5	53.58	V	5.0 U	50 U	**500**	**500**	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-6D-10	03/02/20	HC	AAL	10	48.58	V	5.0 U	50 U	**440**	**440**	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-6D-15	03/02/20	HC	AAL	15	43.58	V	5.0 U	50 U	**470**	**470**	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-6D-25	03/02/20	HC	AAL	25	33.58	V	5.0 U	50 U	**490**	**490**	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-6D-30	03/02/20	HC	AAL	30	28.58	S	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-6D-30-Dup	03/02/20	HC	AAL	30 (dup)	28.58	S	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
HMW-6IA	HMW-6IA-5	03/02/20	HC	AAL	5	53.65	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-6IA-10	03/02/20	HC	AAL	10	48.65	V	5.0 U	**67 J**	**670**	**737 J**	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-6IA-15	03/02/20	HC	AAL	15	43.65	V	5.0 U	**61 J**	**600**	**661 J**	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-6IA-20	03/02/20	HC	AAL	20	38.65	V	5.0 U	50 U	**450**	**450**	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-6IA-30	03/02/20	HC	AAL	30	28.65	S	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
HMW-6IB	HMW-6IB-5	03/03/20	HC	AAL	5	53.67	V	5.0 U	**64 J**	**740**	**804 J**	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-6IB-10	03/03/20	HC	AAL	10	48.67	V	5.0 U	50 U	**350**	**350**	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-6IB-10a	03/03/20	HC	AAL	10 (dup)	48.67	V	5.0 U	50 U	**660**	**660**	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-6IB-15	03/03/20	HC	AAL	15	43.67	V	5.0 U	**59**	**720**	**779**	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-6IB-20	03/03/20	HC	AAL	20	38.67	V	5.0 U	50 U	**600**	**600**	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-6IB-25	03/03/20	HC	AAL	25	33.67	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
HMW-7IB	HMW7IB-5	02/28/20	HC	AAL	5	53.69	V	5.0 U	**69 J**	**760**	**829**	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW7IB-10	02/28/20	HC	AAL	10	48.69	V	5.0 U	**94 J**	**860**	**954 J**	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW7IB-15	02/28/20	HC	AAL	15	43.69	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW7IB-20	02/28/20	HC	AAL	20	38.69	V	5.0 U	50 U	**440**	**440**	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW7IB-25	02/28/20	HC	AAL	25	33.69	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW7IB-25a	02/28/20	HC	AAL	25 (dup)	33.69	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
HMW-8IB	HMW-8IB-5	03/02/20	HC	AAL	5	52.97	V	5.0 U	**68 J**	**520**	**588 J**	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-8IB-10	03/02/20	HC	AAL	10	47.97	V	5.0 U	50 U	**480**	**480**	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-8IB-15	03/02/20	HC	AAL	15	42.97	V	5.0 U	**58 J**	**590**	**648 J**	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-8IB-20	03/02/20	HC	AAL	20	37.97	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-8IB-25	03/02/20	HC	AAL	25	32.97	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-8IB-25a	03/02/20	HC	AAL	25 (dup)	32.97	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
HMW-9D	HMW-9D-5	02/27/20	HC	AAL	5	50.32	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-9D-10	02/27/20	HC	AAL	10	45.32	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-9D-15	02/27/20	HC	AAL	15	40.32	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-9D-20	02/27/20	HC	AAL	20	35.32	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-9D-25	02/27/20	HC	AAL	25	30.32	S	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
HMW-9IA	HMW9IA-5	02/28/20	HC	AAL	5	50.26	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW9IA-10	02/28/20	HC	AAL	10	45.26	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW9IA-15	02/28/20	HC	AAL	15	40.26	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW9IA-20	02/28/20	HC	AAL	20	35.26	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW9IA-25	02/28/20	HC	AAL	25	30.26	S	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
HMW-9IB	HMW9IB-5	02/28/20	HC	AAL	5	50.36	V	5.0 U	50 U	**1,100**	**1,100**	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW9IB-13	02/28/20	HC	AAL	13	42.36	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW9IB-15	02/28/20	HC	AAL	15	40.36	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW9IB-20	02/28/20	HC	AAL	20	35.36	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW9IB-25	02/28/20	HC	AAL	25	30.36	S	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
HMW-9S	HMW-9S-5	03/02/20	HC	AAL	5	50.39	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-9S-14	03/02/20	HC	AAL	14	41.39	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-9S-17	03/02/20	HC	AAL	17	38.39	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-9S-20	03/02/20	HC	AAL	20	35.39	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-9S-25	03/02/20	HC	AAL	25	30.39	S	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
HMW-10D	HMW-10D-5	03/05/20	HC	F&BI	5	43.16	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-10D-10	03/05/20	HC	F&BI	10	38.16	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-10D-15	03/05/20	HC	F&BI	15	33.16	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-10D-15a	03/05/20	HC	F&BI	15 (dup)	33.16	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-10D-20	03/05/20	HC	F&BI	20	28.16	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-10D-25	03/05/20	HC	F&BI	25	23.16	S	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
HMW-10S	HMW10S-5	03/03/20	HC	F&BI	5	43.21	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-10S-10	03/03/20	HC	F&BI	10	38.21	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-10S-10a	03/03/20	HC	F&BI	10 (dup)	38.21	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-10S-15	03/03/20	HC	F&BI	15	33.21	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-10S-20	03/03/20	HC	F&BI	20	28.21	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-10S-25	03/03/20	HC	F&BI	25	23.21	S	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
HMW-11IB	HMW-11IB-5	02/24/20	HC	F&BI	5	34.7	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-11IB-10	02/24/20	HC	F&BI	10	29.7	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-11IB-15	02/24/20	HC	F&BI	15	24.7	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-11IB-20	02/24/20	HC	F&BI	20	19.7	S	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-11IB-25	02/24/20	HC	F&BI	25	14.7	S	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
HMW-11S	HMW-11S-5	02/25/20	HC	F&BI	5	36.47	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-11S-10	02/25/20	HC	F&BI	10	31.47	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-11S-15	02/25/20	HC	F&BI	15	26.47	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-11S-20	02/25/20	HC	F&BI	20	21.47	S	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-11S-30	02/25/20	HC	F&BI	30	11.47	S	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
HMW-17S	HMW-17S-5	09/03/20	HC	F&BI	5	52.21	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-17S-10	09/03/20	HC	F&BI	10	47.21	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-17S-15	09/03/20	HC	F&BI	15	42.21	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-17S-20	09/03/20	HC	F&BI	20	37.21	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-17S-25	09/03/20	HC	F&BI	25	32.21	S	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
HMW-18S	HMW-18S-5	09/03/20	HC	F&BI	5	52.61	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-18S-10	09/03/20	HC	F&BI	10	47.61	V	**45**	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-18S-15	09/03/20	HC	F&BI	15	42.61	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-18S-20	09/03/20	HC	F&BI	20	37.61	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-18S-25	09/03/20	HC	F&BI	25	32.61	S	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-18S-30	09/03/20	HC	F&BI	30	27.61	S	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
HMW-19S	HMW-19S-5	09/08/20	HC	F&BI	5	53.2	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-19S-10	09/08/20	HC	F&BI	10	48.2	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-19S-15	09/08/20	HC	F&BI	15	43.2	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-19S-20	09/08/20	HC	F&BI	20	38.2	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-19S-26	09/08/20	HC	F&BI	26	32.2	S	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-19S-30	09/08/20	HC	F&BI	30	28.2	S	**26**	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
HMW-20S	HMW-20S-5	09/08/20	HC	F&BI	5	48.81	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-20S-10	09/08/20	HC	F&BI	10	43.81	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-20S-15	09/08/20	HC	F&BI	15	38.81	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-20S-20	09/08/20	HC	F&BI	20	33.81	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-20S-25	09/08/20	HC	F&BI	25	28.81	S	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	HMW-20S-30	09/08/20	HC	F&BI	30	23.81	S	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
MBB-1	MBB-1-5	02/27/20	HC	AAL	5	50.02	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-1-10	02/27/20	HC	AAL	10	45.02	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-1-15	02/27/20	HC	AAL	15	40.02	V	**7.7**	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-1-20	02/27/20	HC	AAL	20	35.02	V	**570**	50 U	250 U	250 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.25 U	0.050 U
	MBB-1-25	02/27/20	HC	AAL	25	30.02	S	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
MBB-2	MBB-2-5	02/27/20	HC	AAL	5	50.45	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-2-10	02/27/20	HC	AAL	10	45.45	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-2-15	02/27/20	HC	AAL	15	40.45	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-2-20	02/27/20	HC	AAL	20	35.45	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-2-20a	02/27/20	HC	AAL	20 (dup)	35.45	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-2-25	02/27/20	HC	AAL	25	30.45	S	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
MBB-3	MBB-3-5	02/27/20	HC	AAL	5	49.84	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-3-10	02/27/20	HC	AAL	10	44.84	V	**350**	50 U	250 U	250 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.25 U	0.050 U
	MBB-3-15	02/27/20	HC	AAL	15	39.84	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-3-20	02/27/20	HC	AAL	20	34.84	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-3-25	02/27/20	HC	AAL	25	29.84	S	**52**	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
MBB-4	MBB-4-5	02/27/20	HC	AAL	5	49.61	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-4-10	02/27/20	HC	AAL	10	44.61	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-4-10a	02/27/20	HC	AAL	10 (dup)	44.61	V	**7.3**	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-4-15	02/27/20	HC	AAL	15	39.61	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-4-20	02/27/20	HC	AAL	20	34.61	V	**210**	**140**	250 U	250 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.25 U	0.050 U
	MBB-4-25	02/27/20	HC	AAL	25	29.61	S	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
MBB-5	MBB-5-5	03/02/20	HC	AAL	5	45.3	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-5-10	03/02/20	HC	AAL	10	40.3	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-5-15	03/02/20	HC	AAL	15	35.3	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-5-20	03/02/20	HC	AAL	20	30.3	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-5-25	03/02/20	HC	AAL	25	25.3	S	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
MBB-6	MBB-6-5	03/03/20	HC	AAL	5	45.33	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-6-10	03/03/20	HC	AAL	10	40.33	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-6-15	03/03/20	HC	AAL	15	35.33	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-6-20	03/03/20	HC	AAL	20	30.33	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-6-25	03/03/20	HC	AAL	25	25.33	S	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
MBB-7	MBB-7-5	02/25/20	HC	AAL	5	44.41	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-7-10	02/25/20	HC	AAL	10	39.41	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-7-15	02/25/20	HC	AAL	15	34.41	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-7-20	02/25/20	HC	AAL	20	29.41	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-7-25	02/25/20	HC	AAL	25	24.41	S	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
MBB-8	MBB-8-5	02/26/20	HC	AAL	5	44.66	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-8-10	02/26/20	HC	AAL	10	39.66	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-8-15	02/26/20	HC	AAL	15	34.66	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-8-15 dup	02/26/20	HC	AAL	15 (dup)	34.66	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-8-20	02/26/20	HC	AAL	20	29.66	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-8-25	02/26/20	HC	AAL	25	24.66	S	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	**–**	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	**–**	**0.030**	**1.5E-07**
MBB-9	MBB-9-5	02/26/20	HC	AAL	5	42.55	V	5.0 U	50 U	**320**	**320**	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-9-10	02/26/20	HC	AAL	10	37.55	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-9-15	02/26/20	HC	AAL	15	32.55	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-9-20	02/26/20	HC	AAL	20	27.55	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-9-25	02/26/20	HC	AAL	25	22.55	S	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
MBB-10	MBB-10-5	02/26/20	HC	AAL	5	44.66	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-10-10	02/26/20	HC	AAL	10	39.66	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-10-15	02/26/20	HC	AAL	15	34.66	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-10-20	02/26/20	HC	AAL	20	29.66	V	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-10-25	02/26/20	HC	AAL	25	24.66	S	5.0 U	50 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
MBB-14	MBB-14-5	03/03/20	HC	AAL	5	42.15	V	–	50 U	250 U	250 U	–	–	–	–	–	–	–	–	–	–
	MBB-14-10	03/03/20	HC	AAL	10	37.15	V	–	50 U	250 U	250 U	–	–	–	–	–	–	–	–	–	–
	MBB-14-15	03/03/20	HC	AAL	15	32.15	V	–	50 U	250 U	250 U	–	–	–	–	–	–	–	–	–	–
	MBB-14-20	03/03/20	HC	AAL	20	27.15	V	–	50 U	250 U	250 U	–	–	–	–	–	–	–	–	–	–
	MBB-14-25	03/03/20	HC	AAL	25	22.15	V	–	50 U	250 U	250 U	–	–	–	–	–	–	–	–	–	–
MBB-15	MBB-15-5	03/04/20	HC	AAL	5	32.73	V	–	50 U	250 U	250 U	–	–	–	–	–	–	–	–	–	–
	MBB-15-10	03/04/20	HC	AAL	10	27.73	V	–	50 U	250 U	250 U	–	–	–	–	–	–	–	–	–	–
	MBB-15-15	03/04/20	HC	AAL	15	22.73	V	–	50 U	250 U	250 U	–	–	–	–	–	–	–	–	–	–
	MBB-15-20	03/04/20	HC	AAL	20	17.73	S	–	50 U	250 U	250 U	–	–	–	–	–	–	–	–	–	–
	MBB-15-25	03/04/20	HC	AAL	25	12.73	S	–	50 U	250 U	250 U	–	–	–	–	–	–	–	–	–	–
MBB-16	MBB16-5	09/02/20	HC	F&BI	5	48.7	V	**1,200**	**350**	250 U	250 U	0.0050 U	0.0050 U	–	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB16-10	09/02/20	HC	F&BI	10	43.7	V	**200**	250 U	250 U	250 U	0.0050 U	0.0050 U	–	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB16-15	09/02/20	HC	F&BI	15	38.7	V	**20**	250 U	250 U	250 U	0.0050 U	0.0050 U	–	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB16-20	09/02/20	HC	F&BI	20	33.7	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	–	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
MBB-17	MBB17-5	09/01/20	HC	F&BI	5	49.88	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB17-10	09/01/20	HC	F&BI	10	44.88	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB17-15	09/01/20	HC	F&BI	15	39.88	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB17-25	09/01/20	HC	F&BI	25	29.88	S	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
MBB-18	MBB18-5	09/01/20	HC	F&BI	5	46.33	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB18-10	09/01/20	HC	F&BI	10	41.33	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB18-15	09/01/20	HC	F&BI	15	36.33	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB18-20	09/01/20	HC	F&BI	20	31.33	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
MBB-19	MBB19-5	09/01/20	HC	F&BI	5	46.68	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB19-10	09/01/20	HC	F&BI	10	41.68	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB19-15	09/01/20	HC	F&BI	15	36.68	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB19-20	09/01/20	HC	F&BI	20	31.68	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
MBB-20	MBB20-5	09/02/20	HC	F&BI	5	42.53	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB20-10	09/02/20	HC	F&BI	10	37.53	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB20-15	09/02/20	HC	F&BI	15	32.53	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB20-20	09/02/20	HC	F&BI	20	27.53	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
MBB-21	MBB21-5	09/02/20	HC	F&BI	5	42.6	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB21-10	09/02/20	HC	F&BI	10	37.6	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB21-15	09/02/20	HC	F&BI	15	32.6	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB21-20	09/02/20	HC	F&BI	20	27.6	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
MBB-22	MBB-22-5	09/21/20	HC	F&BI	5	37.05	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-22-15	09/21/20	HC	F&BI	15	27.05	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-22-20	09/21/20	HC	F&BI	20	22.05	S	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-22-25	09/21/20	HC	F&BI	25	17.05	S	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-22-30	09/21/20	HC	F&BI	30	12.05	S	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
MBB-23	MBB-23-5	09/21/20	HC	F&BI	5	42.18	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-23-10	09/21/20	HC	F&BI	10	37.18	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-23-15	09/21/20	HC	F&BI	15	32.18	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-23-20	09/21/20	HC	F&BI	20	27.18	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-23-25	09/21/20	HC	F&BI	25	22.18	S	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MBB-23-30	09/21/20	HC	F&BI	30	17.18	S	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
MBB-24	MMB24-5	09/09/20	HC	F&BI	5	49.1	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MMB24-10	09/09/20	HC	F&BI	10	44.1	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MMB24-15	09/09/20	HC	F&BI	15	39.1	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MMB24-20	09/09/20	HC	F&BI	20	34.1	V	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MMB24-25	09/09/20	HC	F&BI	25	29.1	S	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
	MMB24-30	09/09/20	HC	F&BI	30	24.1	S	5.0 U	250 U	250 U	250 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	–	0.0050 U	0.0050 U	0.0050 U	0.025 U	0.0050 U
MBGW-1	MBGW1-5	03/06/19	HC	AAL	5	34.95	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW1-12.5	03/06/19	HC	AAL	12.5	27.45	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW1-17.5	03/06/19	HC	AAL	17.5	22.45	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW1-25	03/06/19	HC	AAL	25	14.95	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW1-30	03/06/19	HC	AAL	30	9.95	S	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-2	MBGW2-5	03/04/19	HC	AAL	5	41.11	V	–	20 U	50 U	50 U	–	–	–	–	–	–	–	–	–	–
	MBGW2-10	03/04/19	HC	AAL	10	36.11	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	–	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW2-12.5	03/04/19	HC	AAL	12.5	33.61	V	5.0 UJ	20 U	50 U	50 U	0.050 U	0.050 U	–	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW2-25	03/04/19	HC	AAL	25	21.11	S	5.0 UJ	20 U	50 U	50 U	0.050 U	0.050 U	–	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW2-30	03/04/19	HC	AAL	30	16.11	S	5.0 UJ	20 U	50 U	50 U	0.050 U	0.050 U	–	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-3	MBGW3-5	03/07/19	HC	AAL	5	42.77	V	–	20 U	50 U	50 U	–	–	–	–	–	–	–	–	–	–
	MBGW3-7.5	03/07/19	HC	AAL	7.5	40.27	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	–	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW3-10	03/07/19	HC	AAL	10	37.77	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	–	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW3-12.5	03/07/19	HC	AAL	12.5	35.27	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	–	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW3-25	03/07/19	HC	AAL	25	22.77	S	–	20 U	50 U	50 U	0.050 U	0.050 U	–	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW3-26	03/07/19	HC	AAL	26	21.77	S	5.0 U	20 U	50 U	50 U	–	–	–	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	**–**	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	**–**	**0.030**	**1.5E-07**
MBGW-4	MBGW4-5	03/06/19	HC	AAL	5	42.3	V	–	20 U	50 U	50 U	–	–	–	–	–	–	–	–	–	–
	MBGW4-7.5	03/06/19	HC	AAL	7.5	39.8	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW4-10	03/06/19	HC	AAL	10	37.3	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW4-12.5	03/06/19	HC	AAL	12.5	34.8	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW4-25	03/06/19	HC	AAL	25	22.3	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-5	MBGW5-10	03/11/19	HC	AAL	10	39.87	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW5-15	03/11/19	HC	AAL	15	34.87	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW5-20	03/11/19	HC	AAL	20	29.87	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW5-27.5	03/11/19	HC	AAL	27.5	22.37	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW5-45	03/11/19	HC	AAL	45	4.87	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-6	MBGW6-10	03/14/19	HC	AAL	10	42.5	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW6-15	03/14/19	HC	AAL	15	37.5	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW6-20	03/14/19	HC	AAL	20	32.5	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW6-30	03/14/19	HC	AAL	30	22.5	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-7	MBGW7-30	03/06/19	HC	AAL	30	23.76	S	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-8	MBGW8-10	03/15/19	HC	AAL	10	37.08	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW8-15	03/15/19	HC	AAL	15	32.08	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW8-25	03/15/19	HC	AAL	25	22.08	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW8-35	03/15/19	HC	AAL	35	12.08	S	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-9	MBGW9-10	03/13/19	HC	AAL	10	46.84	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW9-15	03/13/19	HC	AAL	15	41.84	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW9-20	03/13/19	HC	AAL	20	36.84	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW9-25	03/13/19	HC	AAL	25	31.84	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW9-30	03/13/19	HC	AAL	30	26.84	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-10	MBGW10-10	03/13/19	HC	AAL	10	45.25	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW10-15	03/13/19	HC	AAL	15	40.25	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW10-20	03/13/19	HC	AAL	20	35.25	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW10-25	03/13/19	HC	AAL	25	30.25	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW10-30	03/13/19	HC	AAL	30	25.25	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-11	MBGW11-5	03/12/19	HC	AAL	5	52.55	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW11-10	03/12/19	HC	AAL	10	47.55	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-12	MBGW12-5	03/15/19	HC	AAL	5	49.00	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW12-20	03/15/19	HC	AAL	20	34.00	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW12-25	03/15/19	HC	AAL	25	29.00	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW12-30	03/15/19	HC	AAL	30	24.00	S	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
MBGW-13	MBGW13-5	03/14/19	HC	AAL	5	49.72	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW13-7.5	03/14/19	HC	AAL	7.5	47.22	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW13-10	03/14/19	HC	AAL	10	44.72	V	**730 J**	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW13-12.5	03/14/19	HC	AAL	12.5	42.22	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW13-15	03/14/19	HC	AAL	15	39.72	V	**16**	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW13-20	03/14/19	HC	AAL	20	34.72	V	5.0 U	–	5.0 U	5.0 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-14	MBGW14-10	03/06/19	HC	AAL	10	36.09	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW14-15	03/06/19	HC	AAL	15	31.09	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW14-20	03/06/19	HC	AAL	20	26.09	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW14-30	03/06/19	HC	AAL	30	16.09	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-16	MBGW16-10	03/08/19	HC	AAL	10	42.14	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW16-15	03/08/19	HC	AAL	15	37.14	V	–	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW16-30	03/08/19	HC	AAL	30	22.14	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-1	MBPP1-20	03/05/19	HC	AAL	20	25.28	V	5.0 UJ	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP1-25	03/05/19	HC	AAL	25	20.28	S	5.0 UJ	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-2	MBPP2-10	03/05/19	HC	AAL	10	34.46	V	5.0 UJ	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP2-20	03/05/19	HC	AAL	20	24.46	V	5.0 UJ	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP2-27.5	03/05/19	HC	AAL	27.5	16.96	S	5.0 UJ	–	5.0 UJ	5.0 UJ	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-3	MBPP3-10	03/06/19	HC	AAL	10	35.89	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP3-20	03/06/19	HC	AAL	20	25.89	V	–	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP3-25	03/06/19	HC	AAL	25	20.89	S	5.0 U	–	5.0 U	5.0 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-4	MBPP4-2.5	03/07/19	HC	AAL	2.5	45.84	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP4-10	03/07/19	HC	AAL	10	38.34	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP4-15	03/07/19	HC	AAL	15	33.34	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP4-17	03/07/19	HC	AAL	17	31.34	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP4-18	03/07/19	HC	AAL	18	30.34	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-5	MBPP5-10	03/07/19	HC	AAL	10	35.92	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP5-15	03/07/19	HC	AAL	15	30.92	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP5-17.5	03/07/19	HC	AAL	17.5	28.42	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP5-20	03/07/19	HC	AAL	20	25.92	S	5.0 U	–	5.0 U	5.0 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP5-25	03/07/19	HC	AAL	25	20.92	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-6	MBPP6-7.5	03/08/19	HC	AAL	7.5	44.76	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP6-10	03/08/19	HC	AAL	10	42.26	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP6-12.5	03/08/19	HC	AAL	12.5	39.76	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP6-15	03/08/19	HC	AAL	15	37.26	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
MBPP-6	MBPP6-17.5	03/08/19	HC	AAL	17.5	34.76	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
(continued)	MBPP6-20	03/08/19	HC	AAL	20	32.26	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP6-25	03/08/19	HC	AAL	25	27.26	S	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP6-30	03/08/19	HC	AAL	30	22.26	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-7	MBPP7-5	03/08/19	HC	AAL	5	44.77	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP7-15	03/08/19	HC	AAL	15	34.77	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP7-23	03/08/19	HC	AAL	23	26.77	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-8	MBPP8-10	03/08/19	HC	AAL	10	47.52	V	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP8-15	03/08/19	HC	AAL	15	42.52	V	5.0 U	20 U	**150**	**150**	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP8-22.5	03/08/19	HC	AAL	22.5	35.02	V	–	–	–	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP8-30	03/08/19	HC	AAL	30	27.52	S	5.0 U	20 U	50 U	50 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MW-345	MW-345-41	05/20/21	PES	PACE	41	11.85	S	–	–	–	–	0.00117 U	0.00114 U	0.000857 U	0.000736 U	0.000930 U	0.000605 U	0.000747 U	0.000998 U	0.00904 UJ	0.00200 U
	MW-345-47	05/20/21	PES	PACE	47	5.85	S	–	–	–	–	0.00111 U	0.00108 U	0.000817 U	0.000702 U	0.000886 U	0.000577 U	0.000712 U	0.000951 U	0.00861 UJ	0.00190 U
	MW-2023-47	05/20/21	PES	PACE	47 (dup)	5.85	S	–	–	–	–	0.00137 U	0.00133 U	0.00101 U	0.000863 U	0.00109 U	0.000711 U	0.000877 U	0.00117 U	0.0106 UJ	0.00235 U
	MW-345-53	05/20/21	PES	PACE	53	-0.15	S	–	–	–	–	0.00111 U	0.00108 U	0.000813 U	0.000698 U	0.000882 U	0.000574 U	0.000709 U	0.000946 U	0.00857 UJ	0.00190 U
	MW-345-58	05/20/21	PES	PACE	58	-5.15	S	–	–	–	–	0.00138 U	0.00135 U	0.00102 U	0.000874 U	0.00110 U	0.000720 U	0.000888 U	0.00119 U	0.0107 UJ	0.00238 U
	MW-345-63	05/20/21	PES	PACE	63	-10.15	S	–	–	–	–	0.00127 U	0.00124 U	0.000933 U	0.000801 U	0.00101 U	0.000659 U	0.000813 U	0.00109 U	0.00984 UJ	0.00217 U
MW-346	MW-346-41.5	05/19/21	PES	PACE	41.5	10.28	S	–	–	–	–	0.00115 U	0.00112 U	0.000843 U	0.000725 U	0.000915 U	0.000596 U	**0.00121 J**	0.000982 U	0.00890 U	0.00197 U
	MW-346-47	05/19/21	PES	PACE	47	4.78	S	–	–	–	–	0.00111 U	0.00108 U	0.000814 U	0.000699 U	0.000883 U	0.000575 U	**0.00111 J**	0.000948 U	0.00859 U	0.00190 U
	MW-346-52	05/19/21	PES	PACE	52	-0.22	S	–	–	–	–	0.00111 U	0.00108 U	0.000812 U	0.000697 U	0.000880 U	0.000573 U	0.000708 U	0.000945 U	0.00856 U	0.00189 U
	MW-346-54.5	05/19/21	PES	PACE	54.5	-2.72	S	–	–	–	–	0.00460 U	0.00447 U	0.00337 U	0.00290 U	0.00366 U	0.00238 U	0.00293 U	0.00393 U	0.0355 U	0.00786 U
	MW-346-57.5	05/19/21	PES	PACE	57.5	-5.72	S	–	–	–	–	0.00111 U	0.00108 U	0.000812 U	0.000698 U	0.000881 U	0.000574 U	0.000708 U	0.000945 U	0.00857 U	0.00189 U
	MW-346-62	05/19/21	PES	PACE	62	-10.22	S	–	–	–	–	0.00121 U	0.00118 U	0.000888 U	0.000763 U	0.000964 U	0.000628 U	0.000775 U	0.00103 U	0.00937 U	0.00207 U
MW-347	MW-347-44.5	05/19/21	PES	PACE	44.5	8.29	S	–	–	–	–	0.00133 U	0.00130 U	0.000976 U	0.000838 U	0.00106 U	0.000690 U	**0.00558**	0.00114 U	0.0103 U	0.00228 U
	MW-2022-44.5	05/19/21	PES	PACE	44.5 (dup)	8.29	S	–	–	–	–	0.00124 U	0.00120 U	0.000907 U	0.000779 U	0.000984 U	0.000641 U	**0.00525**	0.00106 U	0.00957 U	0.00211 U
	MW-347-48	05/19/21	PES	PACE	48	4.79	S	–	–	–	–	0.00111 U	0.00108 U	0.000812 U	0.000698 U	0.000881 U	0.000574 U	0.000708 U	0.000945 U	0.00857 U	0.00189 U
	MW-347-54.5	05/19/21	PES	PACE	54.5	-1.71	S	–	–	–	–	0.00114 U	0.00111 U	0.000838 U	0.000719 U	0.000909 U	0.000592 U	0.000730 U	0.000975 U	0.00883 U	0.00195 U
	MW-347-58	05/19/21	PES	PACE	58	-5.21	S	–	–	–	–	0.00113 U	0.00110 U	0.000827 U	0.000711 U	0.000898 U	0.000584 U	0.000721 U	0.000963 U	0.00873 U	0.00193 U
	MW-347-65	05/19/21	PES	PACE	65	-12.21	S	–	–	–	–	0.00120 U	0.00117 U	0.000883 U	0.000759 U	0.000958 U	0.000624 U	0.000770 U	0.00103 U	0.00932 U	0.00206 U
MW-348	MW-348-41	05/18/21	PES	PACE	41	12.96	S	–	–	–	–	0.00122 U	0.00119 U	0.000893 U	0.000767 U	0.000969 U	0.000631 U	**0.0173**	0.00104 U	0.00942 U	0.00208 U
	MW-348-49	05/18/21	PES	PACE	49	4.96	S	–	–	–	–	0.00122 U	0.00119 U	0.000894 U	0.000768 U	0.000970 U	0.000632 U	**0.00394**	0.00104 U	0.00943 U	0.00208 U
	MW-348-54.5	05/18/21	PES	PACE	54.5	-0.54	S	–	–	–	–	0.00110 U	0.00107 U	0.000804 U	0.000691 U	0.000873 U	0.000568 U	0.000701 U	0.000936 U	0.00848 U	0.00187 U
	MW-348-60	05/18/21	PES	PACE	60	-6.04	S	–	–	–	–	0.00109 U	0.00106 U	0.000801 U	0.000688 U	0.000869 U	0.000566 U	0.000698 U	0.000932 U	0.00844 U	0.00187 U
	MW-348-65	05/18/21	PES	PACE	65	-11.04	S	–	–	–	–	0.00118 U	0.00115 U	0.000869 U	0.000746 U	0.000942 U	0.000614 U	0.000757 U	0.00101 U	0.00916 U	0.00202 U
	MW-348-69	05/18/21	PES	PACE	69	-15.04	S	–	–	–	–	0.00116 U	0.00113 U	0.000850 U	0.000730 U	0.000922 U	0.000600 U	0.000741 U	0.000989 U	0.00896 U	0.00198 U
MW-349	MW-349-49	05/17/21	PES	PACE	49	6.84	S	–	–	–	–	0.00121 U	0.00118 U	0.000890 U	0.000765 U	0.000966 U	0.000629 U	0.000776 U	0.00104 U	0.00939 U	0.00207 U
	MW-349-51	05/17/21	PES	PACE	51	4.84	S	–	–	–	–	0.00113 U	0.00110 U	0.000829 U	0.000712 U	0.000900 U	0.000586 U	0.000723 U	0.000965 U	0.00875 U	0.00193 U
	MW-349-56	05/17/21	PES	PACE	56	-0.16	S	–	–	–	–	0.00113 U	0.00110 U	0.000827 U	0.000711 U	0.000898 U	0.000585 U	0.000721 U	0.000963 U	0.00873 U	0.00193 U
	MW-349-61	05/17/21	PES	PACE	61	-5.16	S	–	–	–	–	0.00116 U	0.00112 U	0.000847 U	0.000727 U	0.000919 U	0.000598 U	0.000738 U	0.000986 U	0.00893 U	0.00197 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Oil Range Organics/Lube Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC-113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.0098**	**1.5**	**0.0040**	**0.017**	**7,600**	**0.041**	**0.046**	–	**0.20**	**2.4E-06**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**30**	**2,000**	**2,000**	**2,000**	**0.004**	**0.084**	**0.004**	**0.004**	**120**	**0.004**	**0.004**	–	**0.030**	**1.5E-07**
MW-349	MW-349-66	05/17/21	PES	PACE	66	-10.16	S	–	–	–	–	0.00116 U	0.00113 U	0.000847 U	0.000728 U	0.000919 U	0.000599 U	0.000739 U	0.000986 U	0.00893 U	0.00197 U
(continued)	MW-349-68	05/17/21	PES	PACE	68	-12.16	S	–	–	–	–	0.00119 U	0.00116 U	0.000872 U	0.000749 U	0.000946 U	0.000616 U	0.000760 U	0.00101 U	0.00920 U	0.00203 U
MW-350	MW-350-41	05/21/21	PES	PACE	41	16.77	S	–	–	–	–	0.00122 U	0.00119 U	0.000897 U	0.000770 U	0.000973 U	0.000634 U	0.000782 U	0.00104 U	0.00946 UJ	0.00209 U
	MW-350-53	05/21/21	PES	PACE	53	4.77	S	–	–	–	–	0.00112 U	0.00109 U	0.000820 U	0.000705 U	0.000890 U	0.000580 U	0.000715 U	0.000955 U	0.00865 UJ	0.00191 U
	MW-350-58	05/21/21	PES	PACE	58	-0.23	S	–	–	–	–	0.00111 U	0.00108 U	0.000814 U	0.000699 U	0.000883 U	0.000575 U	0.000709 U	0.000947 U	0.00858 UJ	0.00190 U
	MW-350-64.5	05/21/21	PES	PACE	64.5	-6.73	S	–	–	–	–	0.00116 U	0.00113 U	0.000854 U	0.000733 U	0.000926 U	0.000603 U	0.000744 U	0.000994 U	0.00900 UJ	0.00199 U
	MW-350-69	05/21/21	PES	PACE	69	-11.23	S	–	–	–	–	0.00120 U	0.00117 U	0.000881 U	0.000757 U	0.000956 U	0.000623 U	0.000769 U	0.00103 U	0.00930 UJ	0.00205 U
All Data	Number of Analytes Measured							307	325	330	330	396	396	384	397	33	397	397	397	397	397
	Number of Analytes Detected							17	11	20	21	0	0	0	0	0	0	5	0	0	0
	Frequency of Detection							5.5%	3.4%	6.1%	6.4%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	1.3%	0.0%	0.0%	0.0%
	Maximum Detection							1200	350	1100	1100	–	–	–	–	–	–	0.0173	–	–	–
	Minimum Detection							5 U	20 U	5 U	5 U	0.00109 U	0.00106 U	0.0008 U	0.00069 U	0.00087 U	0.00057 U	0.0007 U	0.00093 U	0.00844 U	0.00187 U
	Number Of Vadose (V) Detections above SL							8	0	0	0	0	0	-8	0	0	0	0	–	0	-8
	Number of Saturated (S) Detections above SL							4	0	0	0	0	0	0	0	0	0	2	–	0	0
2017-2021	Number of Analytes Measured							307	325	330	330	396	396	384	397	33	397	397	397	397	397
	Number of Analytes Detected							17	11	20	21	0	0	0	0	0	0	5	0	0	0
	Frequency of Detection							5.5%	3.4%	6.1%	6.4%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	1.3%	0.0%	0.0%	0.0%
	Maximum Detection							1200	350	1100	1100	–	–	–	–	–	–	0.0173	–	–	–
	Minimum Detection							5 U	20 U	5 U	5 U	0.00109 U	0.00106 U	0.0008 U	0.00069 U	0.00087 U	0.00057 U	0.0007 U	0.00093 U	0.00844 U	0.00187 U
	Number Of Vadose (V) Detections above SL							8	0	0	0	0	0	0	0	0	0	0	–	0	0
	Number of Saturated (S) Detections above SL							4	0	0	0	0	0	0	0	0	0	2	–	0	0

Notes and Abbreviations:
Petroleum Hydrocarbons (PHCs) analyzed by Ecology Methods NWTPH-Gx and NWTPH-Dx.
VOCs analyzed by EPA Method 8260 C/D.
PCUL = Preliminary Cleanup Level from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021. PCULs based on the practical quantitation limits (PQLs) italicized.
Detected results shown in **bold**.
Detections above the screening level in the vadose zone are shown in **bold** and **highlighted blue**.
Detections above the screening level in the saturated zone are shown in **bold** and **highlighted gray.**
– = Not available or results not analyzed.
J = The reported concentration is an estimate based on detectable results between the method detection limit and reporting limit, laboratory QA/QC, or data validation review.
J+ = The result is an estimated quantity, but the result may be biased high.
J- = The result is an estimated quantity, but the result may be biased low.
U = Not detected at a concentration exceeding laboratory reporting limit
z = Gasoline/petroleum detection result is likely elevated due to high detections of CVOCs.
AAL = Alden Analytical Laboratories, Inc., of Seattle, Washington
bgs = below ground surface
dup = duplicate
F&BI = Friedman & Bruya, Inc.
HC = Hart Crowser, Inc.
Pace = Pace Analytical of Mt. Juliet, Tennessee (formerly ESC)
PES = PES Environmental, Inc.

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**8.1E-05**	**1.8E-05**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
615 Dexter Avenue																				
DGW-1	DGW1-10	03/06/19	HC	AAL	10	37	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW1-12.5	03/06/19	HC	AAL	12.5	34.5	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW1-15	03/06/19	HC	AAL	15	32	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW1-25	03/06/19	HC	AAL	25	22	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW1-30	03/06/19	HC	AAL	30	17	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
DGW-2	DGW2-5	03/04/19	HC	AAL	5	54	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW2-10	03/04/19	HC	AAL	10	49	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW2-25	03/04/19	HC	AAL	25	34	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW2-30	03/04/19	HC	AAL	30	29	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
DGW-3	DGW3-2.5	03/06/19	HC	AAL	2.5	44.5	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW3-12.5	03/06/19	HC	AAL	12.5	34.5	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW3-15	03/06/19	HC	AAL	15	32	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW3-20	03/06/19	HC	AAL	20	27	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW3-25	03/06/19	HC	AAL	25	22	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
DGW-4	DGW4-5	03/04/19	HC	AAL	5	60	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW4-10	03/04/19	HC	AAL	10	55	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW4-15	03/04/19	HC	AAL	15	50	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW4-20	03/04/19	HC	AAL	20	45	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW4-35	03/04/19	HC	AAL	35	30	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW4-50	03/04/19	HC	AAL	50	15	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
DMW-1S	DMW1S-5	03/05/19	HC	AAL	5	42	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DMW1S-10	03/05/19	HC	AAL	10	37	V	–	0.050 U	**0.51**	0.050 U	0.050 U	–	0.020 U	0.050 U	**0.19**	0.050 U	0.050 U	0.050 U	0.050 U
	DMW1S-12.5	03/05/19	HC	AAL	12.5	34.5	S	–	0.050 U	**13**	0.050 U	0.050 U	–	0.020 U	0.050 U	**6.2**	0.050 U	0.050 U	0.050 U	0.050 U
	DMW1S-15	03/05/19	HC	AAL	15	32	S	–	0.050 U	**1.9**	0.050 U	0.050 U	–	0.020 U	0.050 U	**0.76**	0.050 U	0.050 U	0.050 U	0.050 U
	DMW1S-20	03/05/19	HC	AAL	20	27	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
DMW-2S	DMW-2S-05	03/02/20	HC	AAL	5	51.03	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	DMW-2S-10	03/02/20	HC	AAL	10	46.03	V	–	–	**0.31 J**	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	DMW-2S-15	03/02/20	HC	AAL	15	41.03	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	DMW-2S-20	03/02/20	HC	AAL	20	36.03	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	DMW-2S-25	03/02/20	HC	AAL	25	31.03	S	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
DMW-3IA	DMW-3IA-5	02/27/20	HC	AAL	5	51.09	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	DMW-3IA-10	02/27/20	HC	AAL	10	46.09	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	DMW-3IA-15	02/27/20	HC	AAL	15	41.09	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	DMW-3IA-20	02/27/20	HC	AAL	20	36.09	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	DMW-3IA-25	02/27/20	HC	AAL	25	31.09	S	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**8.1E-05**	**1.8E-05**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
DMW-4S	DMW-4S-5	02/26/20	HC	AAL	5	56.76	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	DMW-4S-10	02/26/20	HC	AAL	10	51.76	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	DMW-4S-15	02/26/20	HC	AAL	15	46.76	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	DMW-4S-20	02/26/20	HC	AAL	20	41.76	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	DMW-4S-25	02/26/20	HC	AAL	25	36.76	S	–	–	**0.016**	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	DMW-4S-30	02/26/20	HC	AAL	30	31.76	S	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
DMW-5IA	DMW-5IA-5	02/28/20	HC	AAL	5	64.48	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	DMW-5IA-10	02/28/20	HC	AAL	10	59.48	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	DMW-5IA-15	02/28/20	HC	AAL	15	54.48	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	DMW-5IA-20	02/28/20	HC	AAL	20	49.48	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	DMW-5IA-25	02/28/20	HC	AAL	25	44.48	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
DPP-1	DPP1-5	03/04/19	HC	AAL	5	54.5	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP1-7.5	03/05/19	HC	AAL	7.5	52	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP1-10	03/04/19	HC	AAL	10	49.5	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP1-20	03/04/19	HC	AAL	20	39.5	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
DPP-2	DPP2-5	03/04/19	HC	AAL	5	54	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP2-10	03/04/19	HC	AAL	10	49	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
DPP-3	DPP3-5	03/05/19	HC	AAL	5	42	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP3-15	03/05/19	HC	AAL	15	32	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP3-30	03/05/19	HC	AAL	30	17	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
DPP-4	DPP4-10	03/04/19	HC	AAL	10	49	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP4-12.5	03/04/19	HC	AAL	12.5	46.5	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP4-17.5	03/04/19	HC	AAL	17.5	41.5	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP4-20	03/04/19	HC	AAL	20	39	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
DPP-5	DPP5-10	03/04/19	HC	AAL	10	49	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP5-17.5	03/04/19	HC	AAL	17.5	41.5	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP5-20	03/04/19	HC	AAL	20	39	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
DPP-6	DPP6-5	03/05/19	HC	AAL	5	42	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP6-7.5	03/05/19	HC	AAL	7.5	39.5	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP6-12.5	03/05/19	HC	AAL	12.5	34.5	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP6-17.5	03/05/19	HC	AAL	17.5	29.5	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	**–**	**0.88**	**1.2**	**–**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**8.1E-05**	**1.8E-05**	**0.4**	**0.004**	**0.009**	**0.071**	**–**	**0.058**	**0.068**	**–**
Seattle DOT Mercer Parcels																				
HMW-1IB	HMW1IB-7.5	03/12/19	HC	AAL	7.5	30.5	V	–	0.050 U	0.050 U	0.050 U	0.0050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW1IB-15	03/12/19	HC	AAL	15	23	V	–	0.050 U	0.050 U	0.050 U	0.0050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW1IB-20.5	03/12/19	HC	AAL	20.5	18	S	–	0.050 U	0.050 U	0.050 U	0.0050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW1IB-27.5	03/12/19	HC	AAL	27.5	10.5	S	–	0.050 U	0.050 U	0.050 U	0.0050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW1IB-50	03/12/19	HC	AAL	50	-12	S	–	0.050 U	0.050 U	0.050 U	0.0050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW1IB-65	03/12/19	HC	AAL	65	-27	S	–	0.050 U	0.050 U	0.050 U	0.0050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
HMW-2IB	HMW2IB-7.5	03/12/19	HC	AAL	7.5	39.5	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW2IB-15	03/12/19	HC	AAL	15	32	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW2IB-22.5	03/12/19	HC	AAL	22.5	24.5	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW2IB-30	03/12/19	HC	AAL	30	17	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW2IB-45	03/12/19	HC	AAL	45	2	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW2IB-65	03/12/19	HC	AAL	65	-18	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
HMW-3IA	HMW3IA-15	03/15/19	HC	AAL	15	40.5	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW3IA-20	03/15/19	HC	AAL	20	35.5	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW3IA-22.5	03/15/19	HC	AAL	22.5	33	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW3IA-25	03/15/19	HC	AAL	25	30.5	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
HMW-4IA	HMW4IA-5	03/07/19	HC	AAL	5	51	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW4IA-7.5	03/07/19	HC	AAL	7.5	48.5	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW4IA-10	03/07/19	HC	AAL	10	46	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW4IA-25	03/07/19	HC	AAL	25	31	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
HMW-5IB	HMW5IB-5	02/28/20	HC	AAL	5	53.44	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW5IB-10	02/28/20	HC	AAL	10	48.44	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW5IB-15	02/28/20	HC	AAL	15	43.44	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW5IB-20	02/28/20	HC	AAL	20	38.44	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW5IB-25	02/28/20	HC	AAL	25	33.44	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
HMW-6D	HMW-6D-5	03/02/20	HC	AAL	5	53.58	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-6D-10	03/02/20	HC	AAL	10	48.58	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-6D-15	03/02/20	HC	AAL	15	43.58	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-6D-25	03/02/20	HC	AAL	25	33.58	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-6D-30	03/02/20	HC	AAL	30	28.58	S	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-6D-30-Dup	03/02/20	HC	AAL	30 (dup)	28.58	S	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
HMW-6IA	HMW-6IA-5	03/02/20	HC	AAL	5	53.65	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-6IA-10	03/02/20	HC	AAL	10	48.65	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-6IA-15	03/02/20	HC	AAL	15	43.65	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-6IA-20	03/02/20	HC	AAL	20	38.65	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-6IA-30	03/02/20	HC	AAL	30	28.65	S	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
HMW-6IB	HMW-6IB-5	03/03/20	HC	AAL	5	53.67	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-6IB-10	03/03/20	HC	AAL	10	48.67	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-6IB-10a	03/03/20	HC	AAL	10 (dup)	48.67	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-6IB-15	03/03/20	HC	AAL	15	43.67	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-6IB-20	03/03/20	HC	AAL	20	38.67	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-6IB-25	03/03/20	HC	AAL	25	33.67	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**8.1E-05**	**1.8E-05**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
HMW-7IB	HMW7IB-5	02/28/20	HC	AAL	5	53.69	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW7IB-10	02/28/20	HC	AAL	10	48.69	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW7IB-15	02/28/20	HC	AAL	15	43.69	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW7IB-20	02/28/20	HC	AAL	20	38.69	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW7IB-25	02/28/20	HC	AAL	25	33.69	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW7IB-25a	02/28/20	HC	AAL	25 (dup)	33.69	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
HMW-8IB	HMW-8IB-5	03/02/20	HC	AAL	5	52.97	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-8IB-10	03/02/20	HC	AAL	10	47.97	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-8IB-15	03/02/20	HC	AAL	15	42.97	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-8IB-20	03/02/20	HC	AAL	20	37.97	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-8IB-25	03/02/20	HC	AAL	25	32.97	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-8IB-25a	03/02/20	HC	AAL	25 (dup)	32.97	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
HMW-9D	HMW-9D-5	02/27/20	HC	AAL	5	50.32	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-9D-10	02/27/20	HC	AAL	10	45.32	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-9D-15	02/27/20	HC	AAL	15	40.32	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-9D-20	02/27/20	HC	AAL	20	35.32	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-9D-25	02/27/20	HC	AAL	25	30.32	S	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
HMW-9IA	HMW9IA-5	02/28/20	HC	AAL	5	50.26	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW9IA-10	02/28/20	HC	AAL	10	45.26	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW9IA-15	02/28/20	HC	AAL	15	40.26	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW9IA-20	02/28/20	HC	AAL	20	35.26	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW9IA-25	02/28/20	HC	AAL	25	30.26	S	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
HMW-9IB	HMW9IB-5	02/28/20	HC	AAL	5	50.36	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW9IB-13	02/28/20	HC	AAL	13	42.36	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW9IB-15	02/28/20	HC	AAL	15	40.36	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW9IB-20	02/28/20	HC	AAL	20	35.36	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW9IB-25	02/28/20	HC	AAL	25	30.36	S	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
HMW-9S	HMW-9S-5	03/02/20	HC	AAL	5	50.39	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-9S-14	03/02/20	HC	AAL	14	41.39	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-9S-17	03/02/20	HC	AAL	17	38.39	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-9S-20	03/02/20	HC	AAL	20	35.39	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-9S-25	03/02/20	HC	AAL	25	30.39	S	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
HMW-10D	HMW-10D-5	03/05/20	HC	F&BI	5	43.16	V	–	–	0.0050 U	0.050 U	–	0.0050 U	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-10D-10	03/05/20	HC	F&BI	10	38.16	V	–	–	0.0050 U	0.050 U	–	0.0050 U	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-10D-15	03/05/20	HC	F&BI	15	33.16	V	–	–	0.0050 U	0.050 U	–	0.0050 U	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-10D-15a	03/05/20	HC	F&BI	15 (dup)	33.16	V	–	–	0.0050 U	0.050 U	–	0.0050 U	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-10D-20	03/05/20	HC	F&BI	20	28.16	V	–	–	0.0050 U	0.050 U	–	0.0050 U	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-10D-25	03/05/20	HC	F&BI	25	23.16	S	–	–	0.0050 U	0.050 U	–	0.0050 U	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**8.1E-05**	**1.8E-05**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
HMW-10S	HMW10S-5	03/03/20	HC	F&BI	5	43.21	V	–	–	0.0050 U	0.050 U	–	0.0050 U	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-10S-10	03/03/20	HC	F&BI	10	38.21	V	–	–	0.0050 U	0.050 U	–	0.0050 U	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-10S-10a	03/03/20	HC	F&BI	10 (dup)	38.21	V	–	–	0.0050 U	0.050 U	–	0.0050 U	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-10S-15	03/03/20	HC	F&BI	15	33.21	V	–	–	0.0050 U	0.050 U	–	0.0050 U	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-10S-20	03/03/20	HC	F&BI	20	28.21	V	–	–	0.0050 U	0.050 U	–	0.0050 U	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-10S-25	03/03/20	HC	F&BI	25	23.21	S	–	–	0.0050 U	0.050 U	–	0.0050 U	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
HMW-11IB	HMW-11IB-5	02/24/20	HC	F&BI	5	34.7	V	–	–	0.0050 U	0.050 U	–	0.0050 U	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-11IB-10	02/24/20	HC	F&BI	10	29.7	V	–	–	0.0050 U	0.050 U	–	0.0050 U	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-11IB-15	02/24/20	HC	F&BI	15	24.7	V	–	–	0.0050 U	0.050 U	–	0.0050 U	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-11IB-20	02/24/20	HC	F&BI	20	19.7	S	–	–	0.0050 U	0.050 U	–	0.0050 U	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-11IB-25	02/24/20	HC	F&BI	25	14.7	S	–	–	0.0050 U	0.050 U	–	0.0050 U	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
HMW-11S	HMW-11S-5	02/25/20	HC	F&BI	5	36.47	V	–	–	0.0050 U	0.050 U	–	0.0050 U	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-11S-10	02/25/20	HC	F&BI	10	31.47	V	–	–	0.0050 U	0.050 U	–	0.0050 U	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-11S-15	02/25/20	HC	F&BI	15	26.47	V	–	–	0.0050 U	0.050 U	–	0.0050 U	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-11S-20	02/25/20	HC	F&BI	20	21.47	S	–	–	0.0050 U	0.050 U	–	0.0050 U	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-11S-30	02/25/20	HC	F&BI	30	11.47	S	–	–	0.0050 U	0.050 U	–	0.0050 U	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
HMW-17S	HMW-17S-5	09/03/20	HC	F&BI	5	52.21	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-17S-10	09/03/20	HC	F&BI	10	47.21	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-17S-15	09/03/20	HC	F&BI	15	42.21	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-17S-20	09/03/20	HC	F&BI	20	37.21	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-17S-25	09/03/20	HC	F&BI	25	32.21	S	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
HMW-18S	HMW-18S-5	09/03/20	HC	F&BI	5	52.61	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-18S-10	09/03/20	HC	F&BI	10	47.61	V	–	0.025 U	**0.0068**	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-18S-15	09/03/20	HC	F&BI	15	42.61	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-18S-20	09/03/20	HC	F&BI	20	37.61	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-18S-25	09/03/20	HC	F&BI	25	32.61	S	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-18S-30	09/03/20	HC	F&BI	30	27.61	S	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
HMW-19S	HMW-19S-5	09/08/20	HC	F&BI	5	53.2	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-19S-10	09/08/20	HC	F&BI	10	48.2	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-19S-15	09/08/20	HC	F&BI	15	43.2	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-19S-20	09/08/20	HC	F&BI	20	38.2	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-19S-26	09/08/20	HC	F&BI	26	32.2	S	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-19S-30	09/08/20	HC	F&BI	30	28.2	S	–	0.025 U	**0.11**	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	**0.030**	0.0050 U	0.0050 U	0.0050 U	0.0050 U
HMW-20S	HMW-20S-5	09/08/20	HC	F&BI	5	48.81	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-20S-10	09/08/20	HC	F&BI	10	43.81	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-20S-15	09/08/20	HC	F&BI	15	38.81	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-20S-20	09/08/20	HC	F&BI	20	33.81	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-20S-25	09/08/20	HC	F&BI	25	28.81	S	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	HMW-20S-30	09/08/20	HC	F&BI	30	23.81	S	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**8.1E-05**	**1.8E-05**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
MBB-1	MBB-1-5	02/27/20	HC	AAL	5	50.02	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-1-10	02/27/20	HC	AAL	10	45.02	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-1-15	02/27/20	HC	AAL	15	40.02	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-1-20	02/27/20	HC	AAL	20	35.02	V	–	–	**1.9 J**	0.50 U	0.050 U	–	–	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U
	MBB-1-25	02/27/20	HC	AAL	25	30.02	S	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
MBB-2	MBB-2-5	02/27/20	HC	AAL	5	50.45	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-2-10	02/27/20	HC	AAL	10	45.45	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-2-15	02/27/20	HC	AAL	15	40.45	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-2-20	02/27/20	HC	AAL	20	35.45	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-2-20a	02/27/20	HC	AAL	20 (dup)	35.45	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-2-25	02/27/20	HC	AAL	25	30.45	S	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
MBB-3	MBB-3-5	02/27/20	HC	AAL	5	49.84	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-3-10	02/27/20	HC	AAL	10	44.84	V	–	–	**5.9 J**	0.50 U	0.050 U	–	–	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U
	MBB-3-15	02/27/20	HC	AAL	15	39.84	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-3-20	02/27/20	HC	AAL	20	34.84	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-3-25	02/27/20	HC	AAL	25	29.84	S	–	–	**0.096**	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
MBB-4	MBB-4-5	02/27/20	HC	AAL	5	49.61	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-4-10	02/27/20	HC	AAL	10	44.61	V	–	–	**0.022**	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-4-10a	02/27/20	HC	AAL	10 (dup)	44.61	V	–	–	**0.11**	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-4-15	02/27/20	HC	AAL	15	39.61	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-4-20	02/27/20	HC	AAL	20	34.61	V	–	–	**1.2 J**	0.50 U	0.050 U	–	–	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U
	MBB-4-25	02/27/20	HC	AAL	25	29.61	S	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
MBB-5	MBB-5-5	03/02/20	HC	AAL	5	45.3	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-5-10	03/02/20	HC	AAL	10	40.3	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-5-15	03/02/20	HC	AAL	15	35.3	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-5-20	03/02/20	HC	AAL	20	30.3	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-5-25	03/02/20	HC	AAL	25	25.3	S	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
MBB-6	MBB-6-5	03/03/20	HC	AAL	5	45.33	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-6-10	03/03/20	HC	AAL	10	40.33	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-6-15	03/03/20	HC	AAL	15	35.33	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-6-20	03/03/20	HC	AAL	20	30.33	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-6-25	03/03/20	HC	AAL	25	25.33	S	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
MBB-7	MBB-7-5	02/25/20	HC	AAL	5	44.41	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-7-10	02/25/20	HC	AAL	10	39.41	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-7-15	02/25/20	HC	AAL	15	34.41	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-7-20	02/25/20	HC	AAL	20	29.41	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-7-25	02/25/20	HC	AAL	25	24.41	S	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
MBB-8	MBB-8-5	02/26/20	HC	AAL	5	44.66	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-8-10	02/26/20	HC	AAL	10	39.66	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-8-15	02/26/20	HC	AAL	15	34.66	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-8-15 dup	02/26/20	HC	AAL	15 (dup)	34.66	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-8-20	02/26/20	HC	AAL	20	29.66	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-8-25	02/26/20	HC	AAL	25	24.66	S	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	**–**	**0.88**	**1.2**	**–**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**8.1E-05**	**1.8E-05**	**0.4**	**0.004**	**0.009**	**0.071**	**–**	**0.058**	**0.068**	**–**
MBB-9	MBB-9-5	02/26/20	HC	AAL	5	42.55	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-9-10	02/26/20	HC	AAL	10	37.55	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-9-15	02/26/20	HC	AAL	15	32.55	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-9-20	02/26/20	HC	AAL	20	27.55	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-9-25	02/26/20	HC	AAL	25	22.55	S	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
MBB-10	MBB-10-5	02/26/20	HC	AAL	5	44.66	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-10-10	02/26/20	HC	AAL	10	39.66	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-10-15	02/26/20	HC	AAL	15	34.66	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-10-20	02/26/20	HC	AAL	20	29.66	V	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-10-25	02/26/20	HC	AAL	25	24.66	S	–	–	0.0050 U	0.050 U	0.0050 U	–	–	0.0010 U	–	0.0050 U	0.0050 U	0.0050 U	0.0050 U
MBB-14	MBB-14-5	03/03/20	HC	AAL	5	42.15	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-14-10	03/03/20	HC	AAL	10	37.15	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-14-15	03/03/20	HC	AAL	15	32.15	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-14-20	03/03/20	HC	AAL	20	27.15	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-14-25	03/03/20	HC	AAL	25	22.15	V	–	–	–	–	–	–	–	–	–	–	–	–	–
MBB-15	MBB-15-5	03/04/20	HC	AAL	5	32.73	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-15-10	03/04/20	HC	AAL	10	27.73	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-15-15	03/04/20	HC	AAL	15	22.73	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-15-20	03/04/20	HC	AAL	20	17.73	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-15-25	03/04/20	HC	AAL	25	12.73	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MBB-16	MBB16-5	09/02/20	HC	F&BI	5	48.7	V	–	0.025 U	**2.8**	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	**1.3**	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB16-10	09/02/20	HC	F&BI	10	43.7	V	–	0.025 U	**0.49**	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	**0.25**	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB16-15	09/02/20	HC	F&BI	15	38.7	V	–	0.025 U	**0.014**	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	**0.0086**	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB16-20	09/02/20	HC	F&BI	20	33.7	V	–	0.025 U	**0.0081**	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
MBB-17	MBB17-5	09/01/20	HC	F&BI	5	49.88	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB17-10	09/01/20	HC	F&BI	10	44.88	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB17-15	09/01/20	HC	F&BI	15	39.88	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB17-25	09/01/20	HC	F&BI	25	29.88	S	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
MBB-18	MBB18-5	09/01/20	HC	F&BI	5	46.33	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB18-10	09/01/20	HC	F&BI	10	41.33	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB18-15	09/01/20	HC	F&BI	15	36.33	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB18-20	09/01/20	HC	F&BI	20	31.33	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
MBB-19	MBB19-5	09/01/20	HC	F&BI	5	46.68	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB19-10	09/01/20	HC	F&BI	10	41.68	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB19-15	09/01/20	HC	F&BI	15	36.68	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB19-20	09/01/20	HC	F&BI	20	31.68	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
MBB-20	MBB20-5	09/02/20	HC	F&BI	5	42.53	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB20-10	09/02/20	HC	F&BI	10	37.53	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB20-15	09/02/20	HC	F&BI	15	32.53	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB20-20	09/02/20	HC	F&BI	20	27.53	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	**–**	**0.88**	**1.2**	**–**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**8.1E-05**	**1.8E-05**	**0.4**	**0.004**	**0.009**	**0.071**	**–**	**0.058**	**0.068**	**–**
MBB-21	MBB21-5	09/02/20	HC	F&BI	5	42.6	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB21-10	09/02/20	HC	F&BI	10	37.6	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB21-15	09/02/20	HC	F&BI	15	32.6	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB21-20	09/02/20	HC	F&BI	20	27.6	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
MBB-22	MBB-22-5	09/21/20	HC	F&BI	5	37.05	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-22-15	09/21/20	HC	F&BI	15	27.05	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-22-20	09/21/20	HC	F&BI	20	22.05	S	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-22-25	09/21/20	HC	F&BI	25	17.05	S	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-22-30	09/21/20	HC	F&BI	30	12.05	S	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
MBB-23	MBB-23-5	09/21/20	HC	F&BI	5	42.18	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-23-10	09/21/20	HC	F&BI	10	37.18	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-23-15	09/21/20	HC	F&BI	15	32.18	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-23-20	09/21/20	HC	F&BI	20	27.18	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-23-25	09/21/20	HC	F&BI	25	22.18	S	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-23-30	09/21/20	HC	F&BI	30	17.18	S	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
MBB-24	MMB24-5	09/09/20	HC	F&BI	5	49.1	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MMB24-10	09/09/20	HC	F&BI	10	44.1	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MMB24-15	09/09/20	HC	F&BI	15	39.1	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MMB24-20	09/09/20	HC	F&BI	20	34.1	V	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MMB24-25	09/09/20	HC	F&BI	25	29.1	S	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
	MMB24-30	09/09/20	HC	F&BI	30	24.1	S	–	0.025 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0010 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U
MBGW-1	MBGW1-5	03/06/19	HC	AAL	5	34.95	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW1-12.5	03/06/19	HC	AAL	12.5	27.45	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW1-17.5	03/06/19	HC	AAL	17.5	22.45	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW1-25	03/06/19	HC	AAL	25	14.95	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW1-30	03/06/19	HC	AAL	30	9.95	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-2	MBGW2-5	03/04/19	HC	AAL	5	41.11	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	MBGW2-10	03/04/19	HC	AAL	10	36.11	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW2-12.5	03/04/19	HC	AAL	12.5	33.61	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW2-25	03/04/19	HC	AAL	25	21.11	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW2-30	03/04/19	HC	AAL	30	16.11	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-3	MBGW3-5	03/07/19	HC	AAL	5	42.77	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	MBGW3-7.5	03/07/19	HC	AAL	7.5	40.27	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW3-10	03/07/19	HC	AAL	10	37.77	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW3-12.5	03/07/19	HC	AAL	12.5	35.27	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW3-25	03/07/19	HC	AAL	25	22.77	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW3-26	03/07/19	HC	AAL	26	21.77	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	**–**	**0.88**	**1.2**	**–**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**8.1E-05**	**1.8E-05**	**0.4**	**0.004**	**0.009**	**0.071**	**–**	**0.058**	**0.068**	**–**
MBGW-4	MBGW4-5	03/06/19	HC	AAL	5	42.3	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	MBGW4-7.5	03/06/19	HC	AAL	7.5	39.8	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW4-10	03/06/19	HC	AAL	10	37.3	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW4-12.5	03/06/19	HC	AAL	12.5	34.8	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW4-25	03/06/19	HC	AAL	25	22.3	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-5	MBGW5-10	03/11/19	HC	AAL	10	39.87	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW5-15	03/11/19	HC	AAL	15	34.87	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW5-20	03/11/19	HC	AAL	20	29.87	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW5-27.5	03/11/19	HC	AAL	27.5	22.37	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW5-45	03/11/19	HC	AAL	45	4.87	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-6	MBGW6-10	03/14/19	HC	AAL	10	42.5	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW6-15	03/14/19	HC	AAL	15	37.5	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW6-20	03/14/19	HC	AAL	20	32.5	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW6-30	03/14/19	HC	AAL	30	22.5	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-7	MBGW7-30	03/06/19	HC	AAL	30	23.76	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-8	MBGW8-10	03/15/19	HC	AAL	10	37.08	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW8-15	03/15/19	HC	AAL	15	32.08	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW8-25	03/15/19	HC	AAL	25	22.08	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW8-35	03/15/19	HC	AAL	35	12.08	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-9	MBGW9-10	03/13/19	HC	AAL	10	46.84	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW9-15	03/13/19	HC	AAL	15	41.84	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW9-20	03/13/19	HC	AAL	20	36.84	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW9-25	03/13/19	HC	AAL	25	31.84	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW9-30	03/13/19	HC	AAL	30	26.84	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-10	MBGW10-10	03/13/19	HC	AAL	10	45.25	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW10-15	03/13/19	HC	AAL	15	40.25	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW10-20	03/13/19	HC	AAL	20	35.25	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW10-25	03/13/19	HC	AAL	25	30.25	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW10-30	03/13/19	HC	AAL	30	25.25	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-11	MBGW11-5	03/12/19	HC	AAL	5	52.55	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW11-10	03/12/19	HC	AAL	10	47.55	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-12	MBGW12-5	03/15/19	HC	AAL	5	49.00	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW12-20	03/15/19	HC	AAL	20	34.00	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW12-25	03/15/19	HC	AAL	25	29.00	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW12-30	03/15/19	HC	AAL	30	24.00	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**8.1E-05**	**1.8E-05**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
MBGW-13	MBGW13-5	03/14/19	HC	AAL	5	49.72	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW13-7.5	03/14/19	HC	AAL	7.5	47.22	V	–	0.050 U	**0.55 J**	0.050 U	0.050 U	–	0.020 U	0.050 U	**0.20 J**	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW13-10	03/14/19	HC	AAL	10	44.72	V	–	0.050 U	**15**	0.050 U	0.050 U	–	0.020 U	0.050 U	**5.7**	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW13-12.5	03/14/19	HC	AAL	12.5	42.22	V	–	0.050 U	**1.6 J**	0.050 U	0.050 U	–	0.020 U	0.050 U	**0.51 J**	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW13-15	03/14/19	HC	AAL	15	39.72	V	–	0.050 U	**0.21**	0.050 U	0.050 U	–	0.020 U	0.050 U	**0.079**	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW13-20	03/14/19	HC	AAL	20	34.72	V	–	0.050 U	**0.12 J**	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-14	MBGW14-10	03/06/19	HC	AAL	10	36.09	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW14-15	03/06/19	HC	AAL	15	31.09	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW14-20	03/06/19	HC	AAL	20	26.09	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW14-30	03/06/19	HC	AAL	30	16.09	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-16	MBGW16-10	03/08/19	HC	AAL	10	42.14	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW16-15	03/08/19	HC	AAL	15	37.14	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW16-30	03/08/19	HC	AAL	30	22.14	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-1	MBPP1-20	03/05/19	HC	AAL	20	25.28	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP1-25	03/05/19	HC	AAL	25	20.28	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-2	MBPP2-10	03/05/19	HC	AAL	10	34.46	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP2-20	03/05/19	HC	AAL	20	24.46	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP2-27.5	03/05/19	HC	AAL	27.5	16.96	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-3	MBPP3-10	03/06/19	HC	AAL	10	35.89	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP3-20	03/06/19	HC	AAL	20	25.89	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP3-25	03/06/19	HC	AAL	25	20.89	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-4	MBPP4-2.5	03/07/19	HC	AAL	2.5	45.84	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP4-10	03/07/19	HC	AAL	10	38.34	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP4-15	03/07/19	HC	AAL	15	33.34	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP4-17	03/07/19	HC	AAL	17	31.34	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP4-18	03/07/19	HC	AAL	18	30.34	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-5	MBPP5-10	03/07/19	HC	AAL	10	35.92	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP5-15	03/07/19	HC	AAL	15	30.92	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP5-17.5	03/07/19	HC	AAL	17.5	28.42	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP5-20	03/07/19	HC	AAL	20	25.92	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP5-25	03/07/19	HC	AAL	25	20.92	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-6	MBPP6-7.5	03/08/19	HC	AAL	7.5	44.76	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP6-10	03/08/19	HC	AAL	10	42.26	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP6-12.5	03/08/19	HC	AAL	12.5	39.76	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP6-15	03/08/19	HC	AAL	15	37.26	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**8.1E-05**	**1.8E-05**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
MBPP-6 (continued)	MBPP6-17.5	03/08/19	HC	AAL	17.5	34.76	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP6-20	03/08/19	HC	AAL	20	32.26	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP6-25	03/08/19	HC	AAL	25	27.26	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP6-30	03/08/19	HC	AAL	30	22.26	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-7	MBPP7-5	03/08/19	HC	AAL	5	44.77	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP7-15	03/08/19	HC	AAL	15	34.77	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP7-23	03/08/19	HC	AAL	23	26.77	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-8	MBPP8-10	03/08/19	HC	AAL	10	47.52	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP8-15	03/08/19	HC	AAL	15	42.52	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP8-22.5	03/08/19	HC	AAL	22.5	35.02	V	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP8-30	03/08/19	HC	AAL	30	27.52	S	–	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MW-345	MW-345-41	05/20/21	PES	PACE	41	11.85	S	0.00195 U	0.00543 UJ	0.00195 U	0.00481 U	0.000799 U	0.000524 U	0.000800 U	0.00175 U	0.00247 U	0.000740 U	0.000618 U	0.000863 U	0.00170 U
	MW-345-47	05/20/21	PES	PACE	47	5.85	S	0.00186 U	0.00517 UJ	0.00186 U	0.00458 U	0.000762 U	0.000499 U	0.000763 U	0.00167 U	0.00235 U	0.000705 U	0.000589 U	0.000823 U	0.00162 U
	MW-2023-47	05/20/21	PES	PACE	47 (dup)	5.85	S	0.00229 U	0.00637 UJ	0.00229 U	0.00564 U	0.000937 U	0.000615 U	0.000939 U	0.00205 U	0.00289 U	0.000868 U	0.000724 U	0.00101 U	0.00199 U
	MW-345-53	05/20/21	PES	PACE	53	-0.15	S	0.00185 U	0.00515 UJ	0.00185 U	0.00456 U	0.000758 U	0.000497 U	0.000759 U	0.00166 U	0.00234 U	0.000702 U	0.000586 U	0.000819 U	0.00161 U
	MW-345-58	05/20/21	PES	PACE	58	-5.15	S	0.00232 U	0.00645 UJ	0.00232 U	0.00571 U	0.000949 U	0.000623 U	0.000950 U	0.00208 U	0.00293 U	0.000879 U	0.000733 U	0.00103 U	0.00202 U
	MW-345-63	05/20/21	PES	PACE	63	-10.15	S	0.00212 U	0.00590 UJ	0.00212 U	0.00523 U	0.000870 U	0.000570 U	0.000871 U	0.00191 U	0.00268 U	0.000805 U	0.000672 U	0.000939 U	0.00185 U
MW-346	MW-346-41.5	05/19/21	PES	PACE	41.5	10.28	S	0.00192 U	0.00534 U	0.00192 U	0.00473 U	0.000786 U	0.000516 U	0.000788 U	0.00172 U	0.00243 U	0.000728 U	0.000608 U	0.000850 U	0.00167 U
	MW-346-47	05/19/21	PES	PACE	47	4.78	S	0.00185 U	0.00516 U	0.00185 U	0.00457 U	0.000759 U	0.000498 U	0.000760 U	0.00166 U	0.00234 U	0.000703 U	0.000587 U	0.000820 U	0.00162 U
	MW-346-52	05/19/21	PES	PACE	52	-0.22	S	0.00185 U	0.00514 U	0.00185 U	0.00455 U	0.000757 U	0.000496 U	0.000758 U	0.00166 U	0.00234 U	0.000701 U	0.000585 U	0.000817 U	0.00161 U
	MW-346-54.5	05/19/21	PES	PACE	54.5	-2.72	S	0.00766 U	0.0213 U	0.00766 U	0.0189 U	0.00314 U	0.00206 U	0.00315 U	0.00689 U	0.00970 U	0.00291 U	0.00243 U	0.00340 U	0.00669 U
	MW-346-57.5	05/19/21	PES	PACE	57.5	-5.72	S	0.00185 U	0.00514 U	0.00185 U	0.00456 U	0.000757 U	0.000497 U	0.000758 U	0.00166 U	0.00234 U	0.000701 U	0.000585 U	0.000818 U	0.00161 U
	MW-346-62	05/19/21	PES	PACE	62	-10.22	S	0.00202 U	0.00562 U	0.00202 U	0.00499 U	0.000828 U	0.000543 U	0.000830 U	0.00182 U	0.00256 U	0.000767 U	0.000640 U	0.000895 U	0.00176 U
MW-347	MW-347-44.5	05/19/21	PES	PACE	44.5	8.29	S	0.00222 U	0.00618 U	0.00222 U	0.00548 U	0.000910 U	0.000597 U	0.000911 U	0.00199 U	0.00281 U	0.000843 U	0.000704 U	0.000983 U	0.00194 U
	MW-2022-44.5	05/19/21	PES	PACE	44.5 (dup)	8.29	S	0.00206 U	0.00574 U	0.00206 U	0.00509 U	0.000846 U	0.000555 U	0.000847 U	0.00185 U	0.00261 U	0.000783 U	0.000654 U	0.000914 U	0.00180 U
	MW-347-48	05/19/21	PES	PACE	48	4.79	S	0.00185 U	0.00514 U	0.00185 U	0.00456 U	0.000757 U	0.000497 U	0.000758 U	0.00166 U	0.00234 U	0.000701 U	0.000585 U	0.000818 U	0.00161 U
	MW-347-54.5	05/19/21	PES	PACE	54.5	-1.71	S	0.00190 U	0.00530 U	0.00190 U	0.00470 U	0.000781 U	0.000512 U	0.000782 U	0.00171 U	0.00241 U	0.000723 U	0.000604 U	0.000844 U	0.00166 U
	MW-347-58	05/19/21	PES	PACE	58	-5.21	S	0.00188 U	0.00524 U	0.00188 U	0.00464 U	0.000771 U	0.000506 U	0.000773 U	0.00169 U	0.00238 U	0.000714 U	0.000596 U	0.000833 U	0.00164 U
	MW-347-65	05/19/21	PES	PACE	65	-12.21	S	0.00201 U	0.00559 U	0.00201 U	0.00496 U	0.000824 U	0.000540 U	0.000825 U	0.00180 U	0.00254 U	0.000763 U	0.000637 U	0.000890 U	0.00175 U
MW-348	MW-348-41	05/18/21	PES	PACE	41	12.96	S	0.00203 U	0.00565 U	0.00203 U	0.00501 U	0.000833 U	0.000546 U	0.000834 U	0.00182 U	0.00257 U	0.000771 U	0.000644 U	0.000900 U	0.00177 U
	MW-348-49	05/18/21	PES	PACE	49	4.96	S	0.00203 U	0.00566 U	0.00203 U	0.00502 U	0.000834 U	0.000547 U	0.000835 U	0.00183 U	0.00257 U	0.000772 U	0.000645 U	0.000901 U	0.00178 U
	MW-348-54.5	05/18/21	PES	PACE	54.5	-0.54	S	0.00183 U	0.00509 U	0.00183 U	0.00451 U	0.000750 U	0.000492 U	0.000751 U	0.00164 U	0.00231 U	0.000694 U	0.000580 U	0.000810 U	0.00160 U
	MW-348-60	05/18/21	PES	PACE	60	-6.04	S	0.00182 U	0.00507 U	0.00182 U	0.00449 U	0.000747 U	0.000490 U	0.000748 U	0.00164 U	0.00230 U	0.000691 U	0.000577 U	0.000806 U	0.00159 U
	MW-348-65	05/18/21	PES	PACE	65	-11.04	S	0.00197 U	0.00550 U	0.00197 U	0.00487 U	0.000810 U	0.000531 U	0.000811 U	0.00177 U	0.00250 U	0.000750 U	0.000626 U	0.000875 U	0.00172 U
	MW-348-69	05/18/21	PES	PACE	69	-15.04	S	0.00193 U	0.00538 U	0.00193 U	0.00477 U	0.000792 U	0.000520 U	0.000793 U	0.00174 U	0.00245 U	0.000734 U	0.000613 U	0.000856 U	0.00169 U
MW-349	MW-349-49	05/17/21	PES	PACE	49	6.84	S	0.00202 U	0.00563 U	0.00202 U	0.00499 U	0.000830 U	0.000544 U	0.000831 U	0.00182 U	0.00256 U	0.000768 U	0.000642 U	0.000896 U	0.00177 U
	MW-349-51	05/17/21	PES	PACE	51	4.84	S	0.00189 U	0.00525 U	0.00189 U	0.00465 U	0.000773 U	0.000507 U	0.000774 U	0.00169 U	0.00239 U	0.000716 U	0.000598 U	0.000835 U	0.00165 U
	MW-349-56	05/17/21	PES	PACE	56	-0.16	S	0.00188 U	0.00524 U	0.00188 U	0.00464 U	0.000771 U	0.000506 U	0.000773 U	0.00169 U	0.00238 U	0.000714 U	0.000596 U	0.000833 U	0.00164 U
	MW-349-61	05/17/21	PES	PACE	61	-5.16	S	0.00193 U	0.00536 U	0.00193 U	0.00475 U	0.000790 U	0.000518 U	0.000791 U	0.00173 U	0.00244 U	0.000731 U	0.000611 U	0.000853 U	0.00168 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	1,2,3-Trimethylbenzene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane (Ethylene Dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**1.3**	**0.56**	**1.3**	**0.0013**	**0.00027**	**7**	**0.023**	**0.025**	**1.3**	–	**0.88**	**1.2**	–
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.073**	**0.03**	**0.072**	**8.1E-05**	**1.8E-05**	**0.4**	**0.004**	**0.009**	**0.071**	–	**0.058**	**0.068**	–
MW-349	MW-349-66	05/17/21	PES	PACE	66	-10.16	S	0.00193 U	0.00536 U	0.00193 U	0.00475 U	0.000790 U	0.000518 U	0.000791 U	0.00173 U	0.00244 U	0.000731 U	0.000611 U	0.000853 U	0.00168 U
(continued)	MW-349-68	05/17/21	PES	PACE	68	-12.16	S	0.00198 U	0.00552 U	0.00198 U	0.00489 U	0.000813 U	0.000533 U	0.000814 U	0.00178 U	0.00251 U	0.000753 U	0.000629 U	0.000878 U	0.00173 U
MW-350	MW-350-41	05/21/21	PES	PACE	41	16.77	S	**1.05**	0.00568 UJ	**2.19**	0.00503 U	0.000836 U	0.000548 U	0.000838 U	0.00183 U	**0.746**	0.000774 U	0.000647 U	0.000903 U	0.00178 U
	MW-350-53	05/21/21	PES	PACE	53	4.77	S	**0.0119**	0.00519 UJ	**0.0144**	0.00460 U	0.000765 U	0.000502 U	0.000766 U	0.00168 U	**0.00916**	0.000708 U	0.000591 U	0.000826 U	0.00163 U
	MW-350-58	05/21/21	PES	PACE	58	-0.23	S	0.00185 U	0.00515 UJ	**0.00514 J**	0.00457 U	0.000759 U	0.000498 U	0.000760 U	0.00166 U	0.00234 U	0.000702 U	0.000587 U	0.000820 U	0.00162 U
	MW-350-64.5	05/21/21	PES	PACE	64.5	-6.73	S	0.00194 U	0.00541 UJ	0.00194 U	0.00479 U	0.000796 U	0.000522 U	0.000797 U	0.00174 U	0.00246 U	0.000737 U	0.000615 U	0.000860 U	0.00170 U
	MW-350-69	05/21/21	PES	PACE	69	-11.23	S	**0.0145**	0.00558 UJ	**0.0330**	0.00495 U	0.000822 U	0.000539 U	0.000823 U	0.00180 U	**0.0104**	0.000761 U	0.000635 U	0.000888 U	0.00175 U
All Data	Number of Analytes Measured							33	256	397	397	377	123	256	397	256	397	397	397	397
	Number of Analytes Detected							3	0	25	0	0	0	0	0	14	0	0	0	0
	Frequency of Detection							9.1%	0.0%	6.3%	0.0%	0.0%	0.0%	0.0%	0.0%	5.5%	0.0%	0.0%	0.0%	0.0%
	Maximum Detection							1.05	–	15	–	–	–	–	–	6.2	–	–	–	–
	Minimum Detection							0.00182 U	0.00507 U	0.00182 U	0.00449 U	0.00075 U	0.00049 U	0.00075 U	0.001 U	0.0023 U	0.00069 U	0.00058 U	0.00081 U	0.00159 U
	Number Of Vadose (V) Detections above SL							0	0	5	-8	-6	0	0	0	2	–	0	0	–
	Number of Saturated (S) Detections above SL							1	0	5	0	0	0	0	0	3	–	0	0	–
2017-2021	Number of Analytes Measured							33	256	397	397	377	123	256	397	256	397	397	397	397
	Number of Analytes Detected							3	0	25	0	0	0	0	0	14	0	0	0	0
	Frequency of Detection							9.1%	0.0%	6.3%	0.0%	0.0%	0.0%	0.0%	0.0%	5.5%	0.0%	0.0%	0.0%	0.0%
	Maximum Detection							1.05	–	15	–	–	–	–	–	6.2	–	–	–	–
	Minimum Detection							0.00182 U	0.00507 U	0.00182 U	0.00449 U	0.00075 U	0.00049 U	0.00075 U	0.001 U	0.0023 U	0.00069 U	0.00058 U	0.00081 U	0.00159 U
	Number Of Vadose (V) Detections above SL							0	0	5	0	0	0	0	0	2	–	0	0	–
	Number of Saturated (S) Detections above SL							1	0	5	0	0	0	0	0	3	–	0	0	–

Notes and Abbreviations:
Petroleum Hydrocarbons (PHCs) analyzed by Ecology Methods NWTPH-Gx and NWTPH-Dx.
VOCs analyzed by EPA Method 8260 C/D.
PCUL = Preliminary Cleanup Level from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021. PCULs based on the practical quantitation limits (PQLs) italicized. Detected results shown in bold.
Detections above the screening level in the vadose zone are shown in **bold and highlighted blue.**
Detections above the screening level in the saturated zone are shown in **bold and highlighted gray.**
– = Not available or results not analyzed.
J = The reported concentration is an estimate based on detectable results between the method detection limit and reporting limit, laboratory QA/QC, or data validation review.
J+ = The result is an estimated quantity, but the result may be biased high.
J- = The result is an estimated quantity, but the result may be biased low.
U = Not detected at a concentration exceeding laboratory reporting limit
z = Gasoline/petroleum detection result is likely elevated due to high detections of CVOCs.
AAL = Alden Analytical Laboratories, Inc., of Seattle, Washington
bgs = below ground surface
dup = duplicate
F&BI = Friedman & Bruya, Inc.
HC = Hart Crowser, Inc.
Pace = Pace Analytical of Mt. Juliet, Tennessee (formerly ESC)
PES = PES Environmental, Inc.

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
615 Dexter Avenue																				
DGW-1	DGW1-10	03/06/19	HC	AAL	10	37	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DGW1-12.5	03/06/19	HC	AAL	12.5	34.5	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DGW1-15	03/06/19	HC	AAL	15	32	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DGW1-25	03/06/19	HC	AAL	25	22	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DGW1-30	03/06/19	HC	AAL	30	17	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
DGW-2	DGW2-5	03/04/19	HC	AAL	5	54	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DGW2-10	03/04/19	HC	AAL	10	49	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DGW2-25	03/04/19	HC	AAL	25	34	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DGW2-30	03/04/19	HC	AAL	30	29	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
DGW-3	DGW3-2.5	03/06/19	HC	AAL	2.5	44.5	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DGW3-12.5	03/06/19	HC	AAL	12.5	34.5	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DGW3-15	03/06/19	HC	AAL	15	32	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DGW3-20	03/06/19	HC	AAL	20	27	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DGW3-25	03/06/19	HC	AAL	25	22	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
DGW-4	DGW4-5	03/04/19	HC	AAL	5	60	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DGW4-10	03/04/19	HC	AAL	10	55	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DGW4-15	03/04/19	HC	AAL	15	50	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DGW4-20	03/04/19	HC	AAL	20	45	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DGW4-35	03/04/19	HC	AAL	35	30	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DGW4-50	03/04/19	HC	AAL	50	15	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
DMW-1S	DMW1S-5	03/05/19	HC	AAL	5	42	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DMW1S-10	03/05/19	HC	AAL	10	37	V	–	0.050 U	–	0.050 U	**0.12**	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DMW1S-12.5	03/05/19	HC	AAL	12.5	34.5	S	–	0.050 U	–	0.050 U	**3.2**	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DMW1S-15	03/05/19	HC	AAL	15	32	S	–	0.050 U	–	0.050 U	**0.48**	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DMW1S-20	03/05/19	HC	AAL	20	27	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
DMW-2S	DMW-2S-05	03/02/20	HC	AAL	5	51.03	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	DMW-2S-10	03/02/20	HC	AAL	10	46.03	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	DMW-2S-15	03/02/20	HC	AAL	15	41.03	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	DMW-2S-20	03/02/20	HC	AAL	20	36.03	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	DMW-2S-25	03/02/20	HC	AAL	25	31.03	S	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
DMW-3IA	DMW-3IA-5	02/27/20	HC	AAL	5	51.09	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	DMW-3IA-10	02/27/20	HC	AAL	10	46.09	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	DMW-3IA-15	02/27/20	HC	AAL	15	41.09	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	DMW-3IA-20	02/27/20	HC	AAL	20	36.09	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	DMW-3IA-25	02/27/20	HC	AAL	25	31.09	S	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
DMW-4S	DMW-4S-5	02/26/20	HC	AAL	5	56.76	V	–	0.0050 U	–	0.0050 U	–	–	–	0.020 U	–	–	–	–	–
	DMW-4S-10	02/26/20	HC	AAL	10	51.76	V	–	0.0050 U	–	0.0050 U	–	–	–	0.020 U	–	–	–	–	–
	DMW-4S-15	02/26/20	HC	AAL	15	46.76	V	–	0.0050 U	–	0.0050 U	–	–	–	0.020 U	–	–	–	–	–
	DMW-4S-20	02/26/20	HC	AAL	20	41.76	V	–	0.0050 U	–	0.0050 U	–	–	–	0.020 U	–	–	–	–	–
	DMW-4S-25	02/26/20	HC	AAL	25	36.76	S	–	0.0050 U	–	0.0050 U	–	–	–	0.020 U	–	–	–	–	–
	DMW-4S-30	02/26/20	HC	AAL	30	31.76	S	–	0.0050 U	–	0.0050 U	–	–	–	0.020 U	–	–	–	–	–
DMW-5IA	DMW-5IA-5	02/28/20	HC	AAL	5	64.48	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	DMW-5IA-10	02/28/20	HC	AAL	10	59.48	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	DMW-5IA-15	02/28/20	HC	AAL	15	54.48	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	DMW-5IA-20	02/28/20	HC	AAL	20	49.48	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	DMW-5IA-25	02/28/20	HC	AAL	25	44.48	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
DPP-1	DPP1-5	03/04/19	HC	AAL	5	54.5	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DPP1-7.5	03/05/19	HC	AAL	7.5	52	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DPP1-10	03/04/19	HC	AAL	10	49.5	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DPP1-20	03/04/19	HC	AAL	20	39.5	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
DPP-2	DPP2-5	03/04/19	HC	AAL	5	54	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DPP2-10	03/04/19	HC	AAL	10	49	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
DPP-3	DPP3-5	03/05/19	HC	AAL	5	42	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DPP3-15	03/05/19	HC	AAL	15	32	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DPP3-30	03/05/19	HC	AAL	30	17	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
DPP-4	DPP4-10	03/04/19	HC	AAL	10	49	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DPP4-12.5	03/04/19	HC	AAL	12.5	46.5	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DPP4-17.5	03/04/19	HC	AAL	17.5	41.5	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DPP4-20	03/04/19	HC	AAL	20	39	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
DPP-5	DPP5-10	03/04/19	HC	AAL	10	49	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DPP5-17.5	03/04/19	HC	AAL	17.5	41.5	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DPP5-20	03/04/19	HC	AAL	20	39	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
DPP-6	DPP6-5	03/05/19	HC	AAL	5	42	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DPP6-7.5	03/05/19	HC	AAL	7.5	39.5	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DPP6-12.5	03/05/19	HC	AAL	12.5	34.5	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	DPP6-17.5	03/05/19	HC	AAL	17.5	29.5	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
Seattle DOT Mercer Parcels																				
HMW-1IB	HMW1IB-7.5	03/12/19	HC	AAL	7.5	30.5	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	HMW1IB-15	03/12/19	HC	AAL	15	23	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	HMW1IB-20.5	03/12/19	HC	AAL	20.5	18	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	HMW1IB-27.5	03/12/19	HC	AAL	27.5	10.5	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	HMW1IB-50	03/12/19	HC	AAL	50	-12	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	HMW1IB-65	03/12/19	HC	AAL	65	-27	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
HMW-2IB	HMW2IB-7.5	03/12/19	HC	AAL	7.5	39.5	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	HMW2IB-15	03/12/19	HC	AAL	15	32	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	HMW2IB-22.5	03/12/19	HC	AAL	22.5	24.5	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	HMW2IB-30	03/12/19	HC	AAL	30	17	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	HMW2IB-45	03/12/19	HC	AAL	45	2	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	HMW2IB-65	03/12/19	HC	AAL	65	-18	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
HMW-3IA	HMW3IA-15	03/15/19	HC	AAL	15	40.5	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	HMW3IA-20	03/15/19	HC	AAL	20	35.5	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	HMW3IA-22.5	03/15/19	HC	AAL	22.5	33	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	HMW3IA-25	03/15/19	HC	AAL	25	30.5	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
HMW-4IA	HMW4IA-5	03/07/19	HC	AAL	5	51	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	HMW4IA-7.5	03/07/19	HC	AAL	7.5	48.5	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	HMW4IA-10	03/07/19	HC	AAL	10	46	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	HMW4IA-25	03/07/19	HC	AAL	25	31	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
HMW-5IB	HMW5IB-5	02/28/20	HC	AAL	5	53.44	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW5IB-10	02/28/20	HC	AAL	10	48.44	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW5IB-15	02/28/20	HC	AAL	15	43.44	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW5IB-20	02/28/20	HC	AAL	20	38.44	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW5IB-25	02/28/20	HC	AAL	25	33.44	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
HMW-6D	HMW-6D-5	03/02/20	HC	AAL	5	53.58	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-6D-10	03/02/20	HC	AAL	10	48.58	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-6D-15	03/02/20	HC	AAL	15	43.58	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-6D-25	03/02/20	HC	AAL	25	33.58	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-6D-30	03/02/20	HC	AAL	30	28.58	S	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-6D-30-Dup	03/02/20	HC	AAL	30 (dup)	28.58	S	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
HMW-6IA	HMW-6IA-5	03/02/20	HC	AAL	5	53.65	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-6IA-10	03/02/20	HC	AAL	10	48.65	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-6IA-15	03/02/20	HC	AAL	15	43.65	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-6IA-20	03/02/20	HC	AAL	20	38.65	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-6IA-30	03/02/20	HC	AAL	30	28.65	S	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
HMW-6IB	HMW-6IB-5	03/03/20	HC	AAL	5	53.67	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-6IB-10	03/03/20	HC	AAL	10	48.67	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-6IB-10a	03/03/20	HC	AAL	10 (dup)	48.67	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-6IB-15	03/03/20	HC	AAL	15	43.67	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-6IB-20	03/03/20	HC	AAL	20	38.67	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-6IB-25	03/03/20	HC	AAL	25	33.67	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
HMW-7IB	HMW7IB-5	02/28/20	HC	AAL	5	53.69	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW7IB-10	02/28/20	HC	AAL	10	48.69	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW7IB-15	02/28/20	HC	AAL	15	43.69	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW7IB-20	02/28/20	HC	AAL	20	38.69	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW7IB-25	02/28/20	HC	AAL	25	33.69	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW7IB-25a	02/28/20	HC	AAL	25 (dup)	33.69	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
HMW-8IB	HMW-8IB-5	03/02/20	HC	AAL	5	52.97	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-8IB-10	03/02/20	HC	AAL	10	47.97	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-8IB-15	03/02/20	HC	AAL	15	42.97	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-8IB-20	03/02/20	HC	AAL	20	37.97	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-8IB-25	03/02/20	HC	AAL	25	32.97	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-8IB-25a	03/02/20	HC	AAL	25 (dup)	32.97	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
HMW-9D	HMW-9D-5	02/27/20	HC	AAL	5	50.32	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-9D-10	02/27/20	HC	AAL	10	45.32	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-9D-15	02/27/20	HC	AAL	15	40.32	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-9D-20	02/27/20	HC	AAL	20	35.32	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-9D-25	02/27/20	HC	AAL	25	30.32	S	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
HMW-9IA	HMW9IA-5	02/28/20	HC	AAL	5	50.26	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW9IA-10	02/28/20	HC	AAL	10	45.26	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW9IA-15	02/28/20	HC	AAL	15	40.26	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW9IA-20	02/28/20	HC	AAL	20	35.26	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW9IA-25	02/28/20	HC	AAL	25	30.26	S	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
HMW-9IB	HMW9IB-5	02/28/20	HC	AAL	5	50.36	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW9IB-13	02/28/20	HC	AAL	13	42.36	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW9IB-15	02/28/20	HC	AAL	15	40.36	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW9IB-20	02/28/20	HC	AAL	20	35.36	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW9IB-25	02/28/20	HC	AAL	25	30.36	S	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
HMW-9S	HMW-9S-5	03/02/20	HC	AAL	5	50.39	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-9S-14	03/02/20	HC	AAL	14	41.39	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-9S-17	03/02/20	HC	AAL	17	38.39	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-9S-20	03/02/20	HC	AAL	20	35.39	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-9S-25	03/02/20	HC	AAL	25	30.39	S	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
HMW-10D	HMW-10D-5	03/05/20	HC	F&BI	5	43.16	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-10D-10	03/05/20	HC	F&BI	10	38.16	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-10D-15	03/05/20	HC	F&BI	15	33.16	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-10D-15a	03/05/20	HC	F&BI	15 (dup)	33.16	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-10D-20	03/05/20	HC	F&BI	20	28.16	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-10D-25	03/05/20	HC	F&BI	25	23.16	S	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
HMW-10S	HMW10S-5	03/03/20	HC	F&BI	5	43.21	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-10S-10	03/03/20	HC	F&BI	10	38.21	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-10S-10a	03/03/20	HC	F&BI	10 (dup)	38.21	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-10S-15	03/03/20	HC	F&BI	15	33.21	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-10S-20	03/03/20	HC	F&BI	20	28.21	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-10S-25	03/03/20	HC	F&BI	25	23.21	S	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
HMW-11IB	HMW-11IB-5	02/24/20	HC	F&BI	5	34.7	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-11IB-10	02/24/20	HC	F&BI	10	29.7	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-11IB-15	02/24/20	HC	F&BI	15	24.7	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-11IB-20	02/24/20	HC	F&BI	20	19.7	S	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-11IB-25	02/24/20	HC	F&BI	25	14.7	S	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
HMW-11S	HMW-11S-5	02/25/20	HC	F&BI	5	36.47	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-11S-10	02/25/20	HC	F&BI	10	31.47	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-11S-15	02/25/20	HC	F&BI	15	26.47	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-11S-20	02/25/20	HC	F&BI	20	21.47	S	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	HMW-11S-30	02/25/20	HC	F&BI	30	11.47	S	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
HMW-17S	HMW-17S-5	09/03/20	HC	F&BI	5	52.21	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	HMW-17S-10	09/03/20	HC	F&BI	10	47.21	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	HMW-17S-15	09/03/20	HC	F&BI	15	42.21	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	HMW-17S-20	09/03/20	HC	F&BI	20	37.21	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	HMW-17S-25	09/03/20	HC	F&BI	25	32.21	S	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
HMW-18S	HMW-18S-5	09/03/20	HC	F&BI	5	52.61	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	HMW-18S-10	09/03/20	HC	F&BI	10	47.61	V	0.050 U	0.0050 U	0.050 U	0.0050 U	**0.015**	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	HMW-18S-15	09/03/20	HC	F&BI	15	42.61	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	HMW-18S-20	09/03/20	HC	F&BI	20	37.61	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	HMW-18S-25	09/03/20	HC	F&BI	25	32.61	S	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	HMW-18S-30	09/03/20	HC	F&BI	30	27.61	S	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
HMW-19S	HMW-19S-5	09/08/20	HC	F&BI	5	53.2	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	HMW-19S-10	09/08/20	HC	F&BI	10	48.2	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	HMW-19S-15	09/08/20	HC	F&BI	15	43.2	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	HMW-19S-20	09/08/20	HC	F&BI	20	38.2	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	HMW-19S-26	09/08/20	HC	F&BI	26	32.2	S	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	HMW-19S-30	09/08/20	HC	F&BI	30	28.2	S	0.050 U	0.0050 U	0.050 U	0.0050 U	**0.0060**	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
HMW-20S	HMW-20S-5	09/08/20	HC	F&BI	5	48.81	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	HMW-20S-10	09/08/20	HC	F&BI	10	43.81	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	HMW-20S-15	09/08/20	HC	F&BI	15	38.81	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	HMW-20S-20	09/08/20	HC	F&BI	20	33.81	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	HMW-20S-25	09/08/20	HC	F&BI	25	28.81	S	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	HMW-20S-30	09/08/20	HC	F&BI	30	23.81	S	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
MBB-1	MBB-1-5	02/27/20	HC	AAL	5	50.02	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	MBB-1-10	02/27/20	HC	AAL	10	45.02	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	MBB-1-15	02/27/20	HC	AAL	15	40.02	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	MBB-1-20	02/27/20	HC	AAL	20	35.02	V	–	0.050 U	–	0.050 U	–	–	–	0.030 U	–	–	–	–	–
	MBB-1-25	02/27/20	HC	AAL	25	30.02	S	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
MBB-2	MBB-2-5	02/27/20	HC	AAL	5	50.45	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	MBB-2-10	02/27/20	HC	AAL	10	45.45	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	MBB-2-15	02/27/20	HC	AAL	15	40.45	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	MBB-2-20	02/27/20	HC	AAL	20	35.45	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	MBB-2-20a	02/27/20	HC	AAL	20 (dup)	35.45	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	MBB-2-25	02/27/20	HC	AAL	25	30.45	S	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
MBB-3	MBB-3-5	02/27/20	HC	AAL	5	49.84	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	MBB-3-10	02/27/20	HC	AAL	10	44.84	V	–	0.050 U	–	0.050 U	–	–	–	0.030 U	–	–	–	–	–
	MBB-3-15	02/27/20	HC	AAL	15	39.84	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	MBB-3-20	02/27/20	HC	AAL	20	34.84	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	MBB-3-25	02/27/20	HC	AAL	25	29.84	S	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
MBB-4	MBB-4-5	02/27/20	HC	AAL	5	49.61	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	MBB-4-10	02/27/20	HC	AAL	10	44.61	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	MBB-4-10a	02/27/20	HC	AAL	10 (dup)	44.61	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	MBB-4-15	02/27/20	HC	AAL	15	39.61	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	MBB-4-20	02/27/20	HC	AAL	20	34.61	V	–	0.050 U	–	0.050 U	–	–	–	0.030 U	–	–	–	–	–
	MBB-4-25	02/27/20	HC	AAL	25	29.61	S	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
MBB-5	MBB-5-5	03/02/20	HC	AAL	5	45.3	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	MBB-5-10	03/02/20	HC	AAL	10	40.3	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	MBB-5-15	03/02/20	HC	AAL	15	35.3	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	MBB-5-20	03/02/20	HC	AAL	20	30.3	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	MBB-5-25	03/02/20	HC	AAL	25	25.3	S	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
MBB-6	MBB-6-5	03/03/20	HC	AAL	5	45.33	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	MBB-6-10	03/03/20	HC	AAL	10	40.33	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	MBB-6-15	03/03/20	HC	AAL	15	35.33	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	MBB-6-20	03/03/20	HC	AAL	20	30.33	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	MBB-6-25	03/03/20	HC	AAL	25	25.33	S	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
MBB-7	MBB-7-5	02/25/20	HC	AAL	5	44.41	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	MBB-7-10	02/25/20	HC	AAL	10	39.41	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	MBB-7-15	02/25/20	HC	AAL	15	34.41	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	MBB-7-20	02/25/20	HC	AAL	20	29.41	V	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
	MBB-7-25	02/25/20	HC	AAL	25	24.41	S	–	0.0050 U	–	0.0050 U	–	–	–	0.0030 U	–	–	–	–	–
MBB-8	MBB-8-5	02/26/20	HC	AAL	5	44.66	V	–	0.0050 U	–	0.0050 U	–	–	–	0.020 U	–	–	–	–	–
	MBB-8-10	02/26/20	HC	AAL	10	39.66	V	–	0.0050 U	–	0.0050 U	–	–	–	0.020 U	–	–	–	–	–
	MBB-8-15	02/26/20	HC	AAL	15	34.66	V	–	0.0050 U	–	0.0050 U	–	–	–	0.020 U	–	–	–	–	–
	MBB-8-15 dup	02/26/20	HC	AAL	15 (dup)	34.66	V	–	0.0050 U	–	0.0050 U	–	–	–	0.020 U	–	–	–	–	–
	MBB-8-20	02/26/20	HC	AAL	20	29.66	V	–	0.0050 U	–	0.0050 U	–	–	–	0.020 U	–	–	–	–	–
	MBB-8-25	02/26/20	HC	AAL	25	24.66	S	–	0.0050 U	–	0.0050 U	–	–	–	0.020 U	–	–	–	–	–

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
MBB-9	MBB-9-5	02/26/20	HC	AAL	5	42.55	V	–	0.0050 U	–	0.0050 U	–	–	–	0.020 U	–	–	–	–	–
	MBB-9-10	02/26/20	HC	AAL	10	37.55	V	–	0.0050 U	–	0.0050 U	–	–	–	0.020 U	–	–	–	–	–
	MBB-9-15	02/26/20	HC	AAL	15	32.55	V	–	0.0050 U	–	0.0050 U	–	–	–	0.020 U	–	–	–	–	–
	MBB-9-20	02/26/20	HC	AAL	20	27.55	V	–	0.0050 U	–	0.0050 U	–	–	–	0.020 U	–	–	–	–	–
	MBB-9-25	02/26/20	HC	AAL	25	22.55	S	–	0.0050 U	–	0.0050 U	–	–	–	0.020 U	–	–	–	–	–
MBB-10	MBB-10-5	02/26/20	HC	AAL	5	44.66	V	–	0.0050 U	–	0.0050 U	–	–	–	0.020 U	–	–	–	–	–
	MBB-10-10	02/26/20	HC	AAL	10	39.66	V	–	0.0050 U	–	0.0050 U	–	–	–	0.020 U	–	–	–	–	–
	MBB-10-15	02/26/20	HC	AAL	15	34.66	V	–	0.0050 U	–	0.0050 U	–	–	–	0.020 U	–	–	–	–	–
	MBB-10-20	02/26/20	HC	AAL	20	29.66	V	–	0.0050 U	–	0.0050 U	–	–	–	0.020 U	–	–	–	–	–
	MBB-10-25	02/26/20	HC	AAL	25	24.66	S	–	0.0050 U	–	0.0050 U	–	–	–	0.020 U	–	–	–	–	–
MBB-14	MBB-14-5	03/03/20	HC	AAL	5	42.15	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-14-10	03/03/20	HC	AAL	10	37.15	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-14-15	03/03/20	HC	AAL	15	32.15	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-14-20	03/03/20	HC	AAL	20	27.15	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-14-25	03/03/20	HC	AAL	25	22.15	V	–	–	–	–	–	–	–	–	–	–	–	–	–
MBB-15	MBB-15-5	03/04/20	HC	AAL	5	32.73	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-15-10	03/04/20	HC	AAL	10	27.73	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-15-15	03/04/20	HC	AAL	15	22.73	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-15-20	03/04/20	HC	AAL	20	17.73	S	–	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-15-25	03/04/20	HC	AAL	25	12.73	S	–	–	–	–	–	–	–	–	–	–	–	–	–
MBB-16	MBB16-5	09/02/20	HC	F&BI	5	48.7	V	0.050 U	0.0050 U	0.050 U	0.0050 U	**0.59**	0.10 U	–	**0.0060**	0.0050 U	–	0.0050 U	0.050 U	–
	MBB16-10	09/02/20	HC	F&BI	10	43.7	V	0.050 U	0.0050 U	0.050 U	0.0050 U	**0.16**	0.10 U	–	**0.011**	0.0050 U	–	0.0050 U	0.050 U	–
	MBB16-15	09/02/20	HC	F&BI	15	38.7	V	0.050 U	0.0050 U	0.050 U	0.0050 U	**0.0059**	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	MBB16-20	09/02/20	HC	F&BI	20	33.7	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
MBB-17	MBB17-5	09/01/20	HC	F&BI	5	49.88	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 UJ	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	MBB17-10	09/01/20	HC	F&BI	10	44.88	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 UJ	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	MBB17-15	09/01/20	HC	F&BI	15	39.88	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 UJ	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	MBB17-25	09/01/20	HC	F&BI	25	29.88	S	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 UJ	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
MBB-18	MBB18-5	09/01/20	HC	F&BI	5	46.33	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 UJ	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	MBB18-10	09/01/20	HC	F&BI	10	41.33	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 UJ	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	MBB18-15	09/01/20	HC	F&BI	15	36.33	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 UJ	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	MBB18-20	09/01/20	HC	F&BI	20	31.33	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 UJ	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
MBB-19	MBB19-5	09/01/20	HC	F&BI	5	46.68	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 UJ	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	MBB19-10	09/01/20	HC	F&BI	10	41.68	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 UJ	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	MBB19-15	09/01/20	HC	F&BI	15	36.68	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 UJ	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	MBB19-20	09/01/20	HC	F&BI	20	31.68	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 UJ	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
MBB-20	MBB20-5	09/02/20	HC	F&BI	5	42.53	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	MBB20-10	09/02/20	HC	F&BI	10	37.53	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	MBB20-15	09/02/20	HC	F&BI	15	32.53	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	MBB20-20	09/02/20	HC	F&BI	20	27.53	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
MBB-21	MBB21-5	09/02/20	HC	F&BI	5	42.6	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	MBB21-10	09/02/20	HC	F&BI	10	37.6	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	MBB21-15	09/02/20	HC	F&BI	15	32.6	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	MBB21-20	09/02/20	HC	F&BI	20	27.6	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
MBB-22	MBB-22-5	09/21/20	HC	F&BI	5	37.05	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	MBB-22-15	09/21/20	HC	F&BI	15	27.05	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	MBB-22-20	09/21/20	HC	F&BI	20	22.05	S	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	MBB-22-25	09/21/20	HC	F&BI	25	17.05	S	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	MBB-22-30	09/21/20	HC	F&BI	30	12.05	S	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
MBB-23	MBB-23-5	09/21/20	HC	F&BI	5	42.18	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	MBB-23-10	09/21/20	HC	F&BI	10	37.18	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	MBB-23-15	09/21/20	HC	F&BI	15	32.18	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	MBB-23-20	09/21/20	HC	F&BI	20	27.18	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	MBB-23-25	09/21/20	HC	F&BI	25	22.18	S	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	MBB-23-30	09/21/20	HC	F&BI	30	17.18	S	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
MBB-24	MMB24-5	09/09/20	HC	F&BI	5	49.1	V	0.050 UJ	0.0050 U	0.050 UJ	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	MMB24-10	09/09/20	HC	F&BI	10	44.1	V	0.050 UJ	0.0050 U	0.050 UJ	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
	MMB24-15	09/09/20	HC	F&BI	15	39.1	V	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 UJ	0.050 U	–
	MMB24-20	09/09/20	HC	F&BI	20	34.1	V	0.050 UJ	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 UJ	0.050 U	–
	MMB24-25	09/09/20	HC	F&BI	25	29.1	S	0.050 UJ	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 UJ	0.050 U	–
	MMB24-30	09/09/20	HC	F&BI	30	24.1	S	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.10 U	–	0.0030 U	0.0050 U	–	0.0050 U	0.050 U	–
MBGW-1	MBGW1-5	03/06/19	HC	AAL	5	34.95	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW1-12.5	03/06/19	HC	AAL	12.5	27.45	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW1-17.5	03/06/19	HC	AAL	17.5	22.45	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW1-25	03/06/19	HC	AAL	25	14.95	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW1-30	03/06/19	HC	AAL	30	9.95	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
MBGW-2	MBGW2-5	03/04/19	HC	AAL	5	41.11	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	MBGW2-10	03/04/19	HC	AAL	10	36.11	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW2-12.5	03/04/19	HC	AAL	12.5	33.61	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW2-25	03/04/19	HC	AAL	25	21.11	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW2-30	03/04/19	HC	AAL	30	16.11	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
MBGW-3	MBGW3-5	03/07/19	HC	AAL	5	42.77	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	MBGW3-7.5	03/07/19	HC	AAL	7.5	40.27	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW3-10	03/07/19	HC	AAL	10	37.77	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW3-12.5	03/07/19	HC	AAL	12.5	35.27	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW3-25	03/07/19	HC	AAL	25	22.77	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW3-26	03/07/19	HC	AAL	26	21.77	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
MBGW-4	MBGW4-5	03/06/19	HC	AAL	5	42.3	V	–	–	–	–	–	–	–	–	–	–	–	–	–
	MBGW4-7.5	03/06/19	HC	AAL	7.5	39.8	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW4-10	03/06/19	HC	AAL	10	37.3	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW4-12.5	03/06/19	HC	AAL	12.5	34.8	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW4-25	03/06/19	HC	AAL	25	22.3	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
MBGW-5	MBGW5-10	03/11/19	HC	AAL	10	39.87	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW5-15	03/11/19	HC	AAL	15	34.87	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW5-20	03/11/19	HC	AAL	20	29.87	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW5-27.5	03/11/19	HC	AAL	27.5	22.37	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW5-45	03/11/19	HC	AAL	45	4.87	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
MBGW-6	MBGW6-10	03/14/19	HC	AAL	10	42.5	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW6-15	03/14/19	HC	AAL	15	37.5	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW6-20	03/14/19	HC	AAL	20	32.5	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW6-30	03/14/19	HC	AAL	30	22.5	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
MBGW-7	MBGW7-30	03/06/19	HC	AAL	30	23.76	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
MBGW-8	MBGW8-10	03/15/19	HC	AAL	10	37.08	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW8-15	03/15/19	HC	AAL	15	32.08	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW8-25	03/15/19	HC	AAL	25	22.08	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW8-35	03/15/19	HC	AAL	35	12.08	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
MBGW-9	MBGW9-10	03/13/19	HC	AAL	10	46.84	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW9-15	03/13/19	HC	AAL	15	41.84	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW9-20	03/13/19	HC	AAL	20	36.84	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW9-25	03/13/19	HC	AAL	25	31.84	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW9-30	03/13/19	HC	AAL	30	26.84	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
MBGW-10	MBGW10-10	03/13/19	HC	AAL	10	45.25	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW10-15	03/13/19	HC	AAL	15	40.25	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW10-20	03/13/19	HC	AAL	20	35.25	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW10-25	03/13/19	HC	AAL	25	30.25	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW10-30	03/13/19	HC	AAL	30	25.25	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
MBGW-11	MBGW11-5	03/12/19	HC	AAL	5	52.55	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW11-10	03/12/19	HC	AAL	10	47.55	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
MBGW-12	MBGW12-5	03/15/19	HC	AAL	5	49.00	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW12-20	03/15/19	HC	AAL	20	34.00	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW12-25	03/15/19	HC	AAL	25	29.00	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW12-30	03/15/19	HC	AAL	30	24.00	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
MBGW-13	MBGW13-5	03/14/19	HC	AAL	5	49.72	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW13-7.5	03/14/19	HC	AAL	7.5	47.22	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW13-10	03/14/19	HC	AAL	10	44.72	V	–	0.050 U	–	0.050 U	**0.97**	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW13-12.5	03/14/19	HC	AAL	12.5	42.22	V	–	0.050 U	–	0.050 U	**0.10 J**	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW13-15	03/14/19	HC	AAL	15	39.72	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW13-20	03/14/19	HC	AAL	20	34.72	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
MBGW-14	MBGW14-10	03/06/19	HC	AAL	10	36.09	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW14-15	03/06/19	HC	AAL	15	31.09	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW14-20	03/06/19	HC	AAL	20	26.09	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW14-30	03/06/19	HC	AAL	30	16.09	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
MBGW-16	MBGW16-10	03/08/19	HC	AAL	10	42.14	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW16-15	03/08/19	HC	AAL	15	37.14	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBGW16-30	03/08/19	HC	AAL	30	22.14	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
MBPP-1	MBPP1-20	03/05/19	HC	AAL	20	25.28	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBPP1-25	03/05/19	HC	AAL	25	20.28	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
MBPP-2	MBPP2-10	03/05/19	HC	AAL	10	34.46	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBPP2-20	03/05/19	HC	AAL	20	24.46	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBPP2-27.5	03/05/19	HC	AAL	27.5	16.96	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
MBPP-3	MBPP3-10	03/06/19	HC	AAL	10	35.89	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBPP3-20	03/06/19	HC	AAL	20	25.89	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBPP3-25	03/06/19	HC	AAL	25	20.89	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
MBPP-4	MBPP4-2.5	03/07/19	HC	AAL	2.5	45.84	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBPP4-10	03/07/19	HC	AAL	10	38.34	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBPP4-15	03/07/19	HC	AAL	15	33.34	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBPP4-17	03/07/19	HC	AAL	17	31.34	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBPP4-18	03/07/19	HC	AAL	18	30.34	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
MBPP-5	MBPP5-10	03/07/19	HC	AAL	10	35.92	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBPP5-15	03/07/19	HC	AAL	15	30.92	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBPP5-17.5	03/07/19	HC	AAL	17.5	28.42	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBPP5-20	03/07/19	HC	AAL	20	25.92	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBPP5-25	03/07/19	HC	AAL	25	20.92	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
MBPP-6	MBPP6-7.5	03/08/19	HC	AAL	7.5	44.76	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBPP6-10	03/08/19	HC	AAL	10	42.26	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBPP6-12.5	03/08/19	HC	AAL	12.5	39.76	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBPP6-15	03/08/19	HC	AAL	15	37.26	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
MBPP-6	MBPP6-17.5	03/08/19	HC	AAL	17.5	34.76	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
(continued)	MBPP6-20	03/08/19	HC	AAL	20	32.26	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBPP6-25	03/08/19	HC	AAL	25	27.26	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBPP6-30	03/08/19	HC	AAL	30	22.26	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
MBPP-7	MBPP7-5	03/08/19	HC	AAL	5	44.77	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBPP7-15	03/08/19	HC	AAL	15	34.77	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBPP7-23	03/08/19	HC	AAL	23	26.77	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
MBPP-8	MBPP8-10	03/08/19	HC	AAL	10	47.52	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBPP8-15	03/08/19	HC	AAL	15	42.52	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBPP8-22.5	03/08/19	HC	AAL	22.5	35.02	V	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
	MBPP8-30	03/08/19	HC	AAL	30	27.52	S	–	0.050 U	–	0.050 U	0.050 U	–	–	0.020 U	0.050 U	–	0.050 U	0.050 U	–
MW-345	MW-345-41	05/20/21	PES	PACE	41	11.85	S	0.0783 U	0.00107 U	0.00414 U	0.000555 U	0.00314 U	0.0450 U	0.00445 U	0.000576 U	0.00111 U	0.000695 U	0.00144 U	0.00243 U	0.000863 UJ
	MW-345-47	05/20/21	PES	PACE	47	5.85	S	0.0746 U	0.00102 U	0.00395 U	0.000529 U	0.00300 U	0.0429 U	0.00424 U	0.000549 U	0.00106 U	0.000663 U	0.00137 U	0.00232 U	**0.00116 J**
	MW-2023-47	05/20/21	PES	PACE	47 (dup)	5.85	S	0.0918 U	0.00125 U	0.00486 U	0.000650 U	0.00369 U	0.0529 U	0.00522 U	0.000675 U	0.00130 U	0.000816 U	0.00170 U	0.00285 U	0.00101 UJ
	MW-345-53	05/20/21	PES	PACE	53	-0.15	S	0.0743 U	0.00101 U	0.00393 U	0.000526 U	0.00298 U	0.0427 U	0.00422 U	0.000546 U	0.00105 U	0.000660 U	0.00137 U	0.00230 U	0.000819 UJ
	MW-345-58	05/20/21	PES	PACE	58	-5.15	S	0.0929 U	0.00127 U	0.00492 U	0.000658 U	0.00374 U	0.0535 U	0.00528 U	0.000684 U	0.00131 U	0.000826 U	0.00172 U	0.00288 U	**0.00611 J**
	MW-345-63	05/20/21	PES	PACE	63	-10.15	S	0.0852 U	0.00116 U	0.00451 U	0.000604 U	0.00342 U	0.0490 U	0.00484 U	0.000627 U	0.00121 U	0.000757 U	0.00157 U	0.00264 U	0.000939 UJ
MW-346	MW-346-41.5	05/19/21	PES	PACE	41.5	10.28	S	0.0771 U	0.00105 U	0.00408 U	0.000546 U	0.00309 U	0.0443 U	**0.00627 J**	0.000567 U	0.00109 U	0.000685 U	0.00142 U	0.00239 U	**0.00144 J**
	MW-346-47	05/19/21	PES	PACE	47	4.78	S	0.0744 U	0.00101 U	0.00394 U	0.000527 U	0.00299 U	0.0428 U	0.00423 U	0.000547 U	0.00105 U	0.000661 U	0.00137 U	0.00231 U	**0.00213 J**
	MW-346-52	05/19/21	PES	PACE	52	-0.22	S	0.0742 U	0.00101 U	0.00392 U	0.000525 U	0.00298 U	0.0426 U	0.00422 U	0.000545 U	0.00105 U	0.000659 U	0.00137 U	0.00230 U	0.000817 U
	MW-346-54.5	05/19/21	PES	PACE	54.5	-2.72	S	0.308 U	0.00420 U	0.0162 U	0.00218 U	0.0124 U	0.177 U	0.0175 U	0.00227 U	0.00437 U	0.00274 U	0.00567 U	0.00956 U	0.00340 U
	MW-346-57.5	05/19/21	PES	PACE	57.5	-5.72	S	0.0742 U	0.00101 U	0.00393 U	0.000526 U	0.00298 U	0.0427 U	0.00422 U	0.000546 U	0.00105 U	0.000659 U	0.00137 U	0.00230 U	0.000818 U
	MW-346-62	05/19/21	PES	PACE	62	-10.22	S	0.0812 U	0.00111 U	**0.0243 J**	0.000575 U	0.00326 U	0.0467 U	0.00461 U	0.000597 U	0.00115 U	0.000721 U	0.00150 U	0.00252 U	0.000895 U
MW-347	MW-347-44.5	05/19/21	PES	PACE	44.5	8.29	S	0.0892 U	0.00121 U	0.00472 U	0.000632 U	0.00358 U	0.0513 U	0.00507 U	0.000656 U	0.00126 U	0.000792 U	0.00164 U	0.00277 U	0.000983 U
	MW-2022-44.5	05/19/21	PES	PACE	44.5 (dup)	8.29	S	0.0829 U	0.00113 U	0.00438 U	0.000587 U	0.00333 U	0.0476 U	0.00471 U	0.000609 U	0.00117 U	0.000736 U	0.00153 U	0.00257 U	0.000914 U
	MW-347-48	05/19/21	PES	PACE	48	4.79	S	0.0742 U	0.00101 U	0.00393 U	0.000526 U	0.00298 U	0.0427 U	0.00422 U	0.000546 U	0.00105 U	0.000659 U	0.00137 U	0.00230 U	0.000818 U
	MW-347-54.5	05/19/21	PES	PACE	54.5	-1.71	S	0.0765 U	0.00104 U	0.00405 U	0.000542 U	0.00307 U	0.0440 U	0.00435 U	0.000563 U	0.00108 U	0.000680 U	0.00141 U	0.00237 U	0.000844 U
	MW-347-58	05/19/21	PES	PACE	58	-5.21	S	0.0756 U	0.00103 U	0.00400 U	0.000536 U	0.00304 U	0.0434 U	0.00430 U	**0.000836 J**	0.00107 U	0.000671 U	0.00139 U	0.00235 U	**0.00564 J**
	MW-347-65	05/19/21	PES	PACE	65	-12.21	S	0.0807 U	0.00110 U	0.00427 U	0.000572 U	0.00324 U	0.0464 U	0.00459 U	0.000594 U	0.00114 U	0.000717 U	0.00149 U	0.00250 U	0.000890 U
MW-348	MW-348-41	05/18/21	PES	PACE	41	12.96	S	0.0816 U	0.00111 U	0.00432 U	0.000578 U	0.00328 U	0.0469 U	0.00464 U	0.000600 U	0.00116 U	0.000725 U	0.00150 U	0.00253 U	0.000900 U
	MW-348-49	05/18/21	PES	PACE	49	4.96	S	0.0817 U	0.00111 U	0.00432 U	0.000579 U	0.00328 U	0.0470 U	0.00465 U	0.000601 U	0.00116 U	0.000726 U	0.00151 U	0.00253 U	0.000901 U
	MW-348-54.5	05/18/21	PES	PACE	54.5	-0.54	S	0.0735 U	0.00100 U	0.00389 U	0.000521 U	0.00295 U	0.0422 U	0.00418 U	0.000540 U	0.00104 U	0.000653 U	0.00135 U	0.00228 U	0.000810 U
	MW-348-60	05/18/21	PES	PACE	60	-6.04	S	0.0732 U	0.000997 U	0.00387 U	0.000518 U	0.00294 U	0.0421 U	0.00416 U	0.000538 U	0.00104 U	0.000650 U	0.00135 U	0.00227 U	0.000806 U
	MW-348-65	05/18/21	PES	PACE	65	-11.04	S	0.0794 U	0.00108 U	0.00420 U	0.000562 U	0.00319 U	0.0456 U	0.00451 U	0.000584 U	0.00112 U	0.000705 U	0.00146 U	0.00246 U	0.000875 U
	MW-348-69	05/18/21	PES	PACE	69	-15.04	S	0.0776 U	0.00106 U	0.00411 U	0.000550 U	0.00312 U	0.0446 U	0.00441 U	0.000571 U	0.00110 U	0.000690 U	0.00143 U	0.00241 U	0.000856 U
MW-349	MW-349-49	05/17/21	PES	PACE	49	6.84	S	0.0813 U	0.00111 U	0.00430 U	0.000576 U	0.00327 U	0.0467 U	0.00462 U	0.000598 U	0.00115 U	0.000722 U	0.00150 U	0.00252 U	0.000896 U
	MW-349-51	05/17/21	PES	PACE	51	4.84	S	0.0758 U	0.00103 U	0.00401 U	0.000537 U	0.00304 U	**0.0527 J**	0.00431 U	0.000557 U	0.00107 U	0.000673 U	0.00140 U	0.00235 U	0.000835 U
	MW-349-56	05/17/21	PES	PACE	56	-0.16	S	0.0756 U	0.00103 U	0.00400 U	0.000536 U	0.00304 U	0.0435 U	0.00430 U	0.000556 U	0.00107 U	0.000671 U	0.00139 U	0.00235 U	0.000833 U
	MW-349-61	05/17/21	PES	PACE	61	-5.16	S	0.0774 U	0.00105 U	0.00409 U	0.000548 U	0.00311 U	0.0445 U	0.00440 U	0.000569 U	0.00110 U	0.000687 U	0.00143 U	0.00240 U	0.000853 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene	4-Isopropyltoluene (p-Isopropyltoluene)	Acetone	Acrylonitrile	Benzene	Bromobenzene	Bromochloromethane	Bromoform	Bromomethane	Carbon Disulfide
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**20**	**1.9**	**0.17**	–	–	**29**	**0.030**	**0.027**	**0.56**	–	**0.36**	**0.05**	**5**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**1.4**	**0.11**	**0.012**	–	–	**2.1**	**0.030**	**0.002**	**0.033**	–	**0.023**	**0.0033**	**0.27**
MW-349	MW-349-66	05/17/21	PES	PACE	66	-10.16	S	0.0774 U	0.00105 U	0.00410 U	0.000549 U	0.00311 U	0.0445 U	0.00440 U	0.000569 U	0.00110 U	0.000687 U	0.00143 U	0.00240 U	0.000853 U
(continued)	MW-349-68	05/17/21	PES	PACE	68	-12.16	S	0.0797 U	0.00109 U	0.00422 U	0.000565 U	0.00320 U	0.0458 U	0.00453 U	0.000586 U	0.00113 U	0.000708 U	0.00147 U	0.00247 U	0.000878 U
MW-350	MW-350-41	05/21/21	PES	PACE	41	16.77	S	0.0819 U	0.00112 U	0.00434 U	0.000581 U	**0.119**	0.0471 U	0.00466 U	**0.0786**	0.00116 U	0.000728 U	0.00151 U	0.00254 U	**0.00210 J**
	MW-350-53	05/21/21	PES	PACE	53	4.77	S	0.0750 U	0.00102 U	0.00397 U	0.000531 U	**0.00336 J**	0.0431 U	0.00426 U	0.000551 U	0.00106 U	0.000666 U	0.00138 U	0.00233 U	0.000826 UJ
	MW-350-58	05/21/21	PES	PACE	58	-0.23	S	0.0743 U	0.00101 U	0.00393 U	0.000527 U	0.00299 U	0.0427 U	0.00423 U	0.000547 U	0.00105 U	0.000660 U	0.00137 U	0.00231 U	0.000820 UJ
	MW-350-64.5	05/21/21	PES	PACE	64.5	-6.73	S	0.0780 U	0.00106 U	0.00413 U	0.000553 U	0.00313 U	0.0448 U	0.00443 U	0.000574 U	0.00111 U	0.000693 U	0.00144 U	0.00242 U	**0.00119 J**
	MW-350-69	05/21/21	PES	PACE	69	-11.23	S	0.0805 U	0.00110 U	0.00426 U	0.000571 U	0.00323 U	0.0463 U	0.00458 U	**0.000690 J**	0.00114 U	0.000715 U	0.00148 U	0.00250 U	**0.00562 J**
All Data	Number of Analytes Measured							97	397	97	397	256	97	33	397	256	33	256	256	33
	Number of Analytes Detected							0	0	1	0	12	1	1	5	0	0	0	0	8
	Frequency of Detection							0.0%	0.0%	1.0%	0.0%	4.7%	1.0%	3.0%	1.3%	0.0%	0.0%	0.0%	0.0%	24.2%
	Maximum Detection							–	–	0.0243 J	–	3.2	0.0527 J	0.00627 J	0.0786	–	–	–	–	0.00611 J
	Minimum Detection							0.05 U	0.001 U	0.00387 U	0.00052 U	0.00294 U	0.0421 U	0.00416 U	0.000538 U	0.00104 U	0.00065 U	0.00135 U	0.00227 U	0.00081 U
	Number Of Vadose (V) Detections above SL							0	0	0	–	–	0	0	0	0	–	0	0	0
	Number of Saturated (S) Detections above SL							0	0	1	–	–	0	0	1	0	–	0	0	0
2017-2021	Number of Analytes Measured							97	397	97	397	256	97	33	397	256	33	256	256	33
	Number of Analytes Detected							0	0	1	0	12	1	1	5	0	0	0	0	8
	Frequency of Detection							0.0%	0.0%	1.0%	0.0%	4.7%	1.0%	3.0%	1.3%	0.0%	0.0%	0.0%	0.0%	24.2%
	Maximum Detection							–	–	0.0243 J	–	3.2	0.0527 J	0.00627 J	0.0786	–	–	–	–	0.00611 J
	Minimum Detection							0.05 U	0.001 U	0.00387 U	0.00052 U	0.00294 U	0.0421 U	0.00416 U	0.000538 U	0.00104 U	0.00065 U	0.00135 U	0.00227 U	0.00081 U
	Number Of Vadose (V) Detections above SL							0	0	0	–	–	0	0	0	0	–	0	0	0
	Number of Saturated (S) Detections above SL							0	0	1	–	–	0	0	1	0	–	0	0	0

Notes and Abbreviations:
Petroleum Hydrocarbons (PHCs) analyzed by Ecology Methods NWTPH-Gx and NWTPH-Dx.
VOCs analyzed by EPA Method 8260 C/D.
PCUL = Preliminary Cleanup Level from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021. PCULs based on the practical quantitation limits (PQLs) italicized. Detected results shown in bold.
Detections above the screening level in the vadose zone are shown in **bold and highlighted blue.**
Detections above the screening level in the saturated zone are shown in **bold and highlighted gray.**
– = Not available or results not analyzed.
J = The reported concentration is an estimate based on detectable results between the method detection limit and reporting limit, laboratory QA/QC, or data validation review.
J+ = The result is an estimated quantity, but the result may be biased high.
J- = The result is an estimated quantity, but the result may be biased low.
U = Not detected at a concentration exceeding laboratory reporting limit
z = Gasoline/petroleum detection result is likely elevated due to high detections of CVOCs.
AAL = Alden Analytical Laboratories, Inc., of Seattle, Washington
bgs = below ground surface
dup = duplicate
F&BI = Friedman & Bruya, Inc.
HC = Hart Crowser, Inc.
Pace = Pace Analytical of Mt. Juliet, Tennessee (formerly ESC)
PES = PES Environmental, Inc.

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
615 Dexter Avenue																			
DGW-1	DGW1-10	03/06/19	HC	AAL	10	37	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW1-12.5	03/06/19	HC	AAL	12.5	34.5	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW1-15	03/06/19	HC	AAL	15	32	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW1-25	03/06/19	HC	AAL	25	22	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW1-30	03/06/19	HC	AAL	30	17	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
DGW-2	DGW2-5	03/04/19	HC	AAL	5	54	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW2-10	03/04/19	HC	AAL	10	49	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW2-25	03/04/19	HC	AAL	25	34	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW2-30	03/04/19	HC	AAL	30	29	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
DGW-3	DGW3-2.5	03/06/19	HC	AAL	2.5	44.5	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW3-12.5	03/06/19	HC	AAL	12.5	34.5	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW3-15	03/06/19	HC	AAL	15	32	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW3-20	03/06/19	HC	AAL	20	27	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW3-25	03/06/19	HC	AAL	25	22	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
DGW-4	DGW4-5	03/04/19	HC	AAL	5	60	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW4-10	03/04/19	HC	AAL	10	55	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW4-15	03/04/19	HC	AAL	15	50	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW4-20	03/04/19	HC	AAL	20	45	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW4-35	03/04/19	HC	AAL	35	30	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW4-50	03/04/19	HC	AAL	50	15	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
DMW-1S	DMW1S-5	03/05/19	HC	AAL	5	42	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DMW1S-10	03/05/19	HC	AAL	10	37	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	**0.053**	
	DMW1S-12.5	03/05/19	HC	AAL	12.5	34.5	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	**2.1**	
	DMW1S-15	03/05/19	HC	AAL	15	32	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	**0.12**	
	DMW1S-20	03/05/19	HC	AAL	20	27	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
DMW-2S	DMW-2S-05	03/02/20	HC	AAL	5	51.03	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	DMW-2S-10	03/02/20	HC	AAL	10	46.03	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	DMW-2S-15	03/02/20	HC	AAL	15	41.03	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	DMW-2S-20	03/02/20	HC	AAL	20	36.03	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	DMW-2S-25	03/02/20	HC	AAL	25	31.03	S	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
DMW-3IA	DMW-3IA-5	02/27/20	HC	AAL	5	51.09	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	DMW-3IA-10	02/27/20	HC	AAL	10	46.09	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	DMW-3IA-15	02/27/20	HC	AAL	15	41.09	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	DMW-3IA-20	02/27/20	HC	AAL	20	36.09	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	DMW-3IA-25	02/27/20	HC	AAL	25	31.09	S	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
DMW-4S	DMW-4S-5	02/26/20	HC	AAL	5	56.76	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.020 U
	DMW-4S-10	02/26/20	HC	AAL	10	51.76	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.020 U
	DMW-4S-15	02/26/20	HC	AAL	15	46.76	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.020 U
	DMW-4S-20	02/26/20	HC	AAL	20	41.76	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.020 U
	DMW-4S-25	02/26/20	HC	AAL	25	36.76	S	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	**0.13**
	DMW-4S-30	02/26/20	HC	AAL	30	31.76	S	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.020 U
DMW-5IA	DMW-5IA-5	02/28/20	HC	AAL	5	64.48	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	DMW-5IA-10	02/28/20	HC	AAL	10	59.48	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	DMW-5IA-15	02/28/20	HC	AAL	15	54.48	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	DMW-5IA-20	02/28/20	HC	AAL	20	49.48	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	DMW-5IA-25	02/28/20	HC	AAL	25	44.48	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
DPP-1	DPP1-5	03/04/19	HC	AAL	5	54.5	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP1-7.5	03/05/19	HC	AAL	7.5	52	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP1-10	03/04/19	HC	AAL	10	49.5	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP1-20	03/04/19	HC	AAL	20	39.5	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
DPP-2	DPP2-5	03/04/19	HC	AAL	5	54	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP2-10	03/04/19	HC	AAL	10	49	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
DPP-3	DPP3-5	03/05/19	HC	AAL	5	42	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP3-15	03/05/19	HC	AAL	15	32	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP3-30	03/05/19	HC	AAL	30	17	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
DPP-4	DPP4-10	03/04/19	HC	AAL	10	49	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP4-12.5	03/04/19	HC	AAL	12.5	46.5	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP4-17.5	03/04/19	HC	AAL	17.5	41.5	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP4-20	03/04/19	HC	AAL	20	39	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
DPP-5	DPP5-10	03/04/19	HC	AAL	10	49	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP5-17.5	03/04/19	HC	AAL	17.5	41.5	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP5-20	03/04/19	HC	AAL	20	39	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
DPP-6	DPP6-5	03/05/19	HC	AAL	5	42	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP6-7.5	03/05/19	HC	AAL	7.5	39.5	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP6-12.5	03/05/19	HC	AAL	12.5	34.5	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP6-17.5	03/05/19	HC	AAL	17.5	29.5	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
Seattle DOT Mercer Parcels																			
HMW-1IB	HMW1IB-7.5	03/12/19	HC	AAL	7.5	30.5	V	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW1IB-15	03/12/19	HC	AAL	15	23	V	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW1IB-20.5	03/12/19	HC	AAL	20.5	18	S	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW1IB-27.5	03/12/19	HC	AAL	27.5	10.5	S	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW1IB-50	03/12/19	HC	AAL	50	-12	S	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW1IB-65	03/12/19	HC	AAL	65	-27	S	0.050 U	0.050 U	–	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
HMW-2IB	HMW2IB-7.5	03/12/19	HC	AAL	7.5	39.5	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW2IB-15	03/12/19	HC	AAL	15	32	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW2IB-22.5	03/12/19	HC	AAL	22.5	24.5	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW2IB-30	03/12/19	HC	AAL	30	17	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW2IB-45	03/12/19	HC	AAL	45	2	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW2IB-65	03/12/19	HC	AAL	65	-18	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
HMW-3IA	HMW3IA-15	03/15/19	HC	AAL	15	40.5	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW3IA-20	03/15/19	HC	AAL	20	35.5	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW3IA-22.5	03/15/19	HC	AAL	22.5	33	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW3IA-25	03/15/19	HC	AAL	25	30.5	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
HMW-4IA	HMW4IA-5	03/07/19	HC	AAL	5	51	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW4IA-7.5	03/07/19	HC	AAL	7.5	48.5	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW4IA-10	03/07/19	HC	AAL	10	46	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW4IA-25	03/07/19	HC	AAL	25	31	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
HMW-5IB	HMW5IB-5	02/28/20	HC	AAL	5	53.44	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW5IB-10	02/28/20	HC	AAL	10	48.44	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW5IB-15	02/28/20	HC	AAL	15	43.44	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW5IB-20	02/28/20	HC	AAL	20	38.44	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW5IB-25	02/28/20	HC	AAL	25	33.44	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
HMW-6D	HMW-6D-5	03/02/20	HC	AAL	5	53.58	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-6D-10	03/02/20	HC	AAL	10	48.58	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-6D-15	03/02/20	HC	AAL	15	43.58	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-6D-25	03/02/20	HC	AAL	25	33.58	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-6D-30	03/02/20	HC	AAL	30	28.58	S	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-6D-30-Dup	03/02/20	HC	AAL	30 (dup)	28.58	S	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
HMW-6IA	HMW-6IA-5	03/02/20	HC	AAL	5	53.65	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-6IA-10	03/02/20	HC	AAL	10	48.65	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-6IA-15	03/02/20	HC	AAL	15	43.65	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-6IA-20	03/02/20	HC	AAL	20	38.65	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-6IA-30	03/02/20	HC	AAL	30	28.65	S	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
HMW-6IB	HMW-6IB-5	03/03/20	HC	AAL	5	53.67	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-6IB-10	03/03/20	HC	AAL	10	48.67	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-6IB-10a	03/03/20	HC	AAL	10 (dup)	48.67	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-6IB-15	03/03/20	HC	AAL	15	43.67	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-6IB-20	03/03/20	HC	AAL	20	38.67	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-6IB-25	03/03/20	HC	AAL	25	33.67	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
HMW-7IB	HMW7IB-5	02/28/20	HC	AAL	5	53.69	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW7IB-10	02/28/20	HC	AAL	10	48.69	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW7IB-15	02/28/20	HC	AAL	15	43.69	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW7IB-20	02/28/20	HC	AAL	20	38.69	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW7IB-25	02/28/20	HC	AAL	25	33.69	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW7IB-25a	02/28/20	HC	AAL	25 (dup)	33.69	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
HMW-8IB	HMW-8IB-5	03/02/20	HC	AAL	5	52.97	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-8IB-10	03/02/20	HC	AAL	10	47.97	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-8IB-15	03/02/20	HC	AAL	15	42.97	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-8IB-20	03/02/20	HC	AAL	20	37.97	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-8IB-25	03/02/20	HC	AAL	25	32.97	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-8IB-25a	03/02/20	HC	AAL	25 (dup)	32.97	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
HMW-9D	HMW-9D-5	02/27/20	HC	AAL	5	50.32	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-9D-10	02/27/20	HC	AAL	10	45.32	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-9D-15	02/27/20	HC	AAL	15	40.32	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-9D-20	02/27/20	HC	AAL	20	35.32	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-9D-25	02/27/20	HC	AAL	25	30.32	S	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
HMW-9IA	HMW9IA-5	02/28/20	HC	AAL	5	50.26	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW9IA-10	02/28/20	HC	AAL	10	45.26	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW9IA-15	02/28/20	HC	AAL	15	40.26	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW9IA-20	02/28/20	HC	AAL	20	35.26	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW9IA-25	02/28/20	HC	AAL	25	30.26	S	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
HMW-9IB	HMW9IB-5	02/28/20	HC	AAL	5	50.36	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW9IB-13	02/28/20	HC	AAL	13	42.36	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW9IB-15	02/28/20	HC	AAL	15	40.36	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW9IB-20	02/28/20	HC	AAL	20	35.36	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW9IB-25	02/28/20	HC	AAL	25	30.36	S	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
HMW-9S	HMW-9S-5	03/02/20	HC	AAL	5	50.39	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-9S-14	03/02/20	HC	AAL	14	41.39	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-9S-17	03/02/20	HC	AAL	17	38.39	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-9S-20	03/02/20	HC	AAL	20	35.39	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-9S-25	03/02/20	HC	AAL	25	30.39	S	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
HMW-10D	HMW-10D-5	03/05/20	HC	F&BI	5	43.16	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-10D-10	03/05/20	HC	F&BI	10	38.16	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-10D-15	03/05/20	HC	F&BI	15	33.16	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-10D-15a	03/05/20	HC	F&BI	15 (dup)	33.16	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-10D-20	03/05/20	HC	F&BI	20	28.16	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-10D-25	03/05/20	HC	F&BI	25	23.16	S	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
HMW-10S	HMW10S-5	03/03/20	HC	F&BI	5	43.21	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-10S-10	03/03/20	HC	F&BI	10	38.21	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-10S-10a	03/03/20	HC	F&BI	10 (dup)	38.21	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-10S-15	03/03/20	HC	F&BI	15	33.21	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-10S-20	03/03/20	HC	F&BI	20	28.21	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-10S-25	03/03/20	HC	F&BI	25	23.21	S	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
HMW-11IB	HMW-11IB-5	02/24/20	HC	F&BI	5	34.7	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-11IB-10	02/24/20	HC	F&BI	10	29.7	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-11IB-15	02/24/20	HC	F&BI	15	24.7	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-11IB-20	02/24/20	HC	F&BI	20	19.7	S	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-11IB-25	02/24/20	HC	F&BI	25	14.7	S	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
HMW-11S	HMW-11S-5	02/25/20	HC	F&BI	5	36.47	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-11S-10	02/25/20	HC	F&BI	10	31.47	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-11S-15	02/25/20	HC	F&BI	15	26.47	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-11S-20	02/25/20	HC	F&BI	20	21.47	S	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	HMW-11S-30	02/25/20	HC	F&BI	30	11.47	S	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
HMW-17S	HMW-17S-5	09/03/20	HC	F&BI	5	52.21	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	HMW-17S-10	09/03/20	HC	F&BI	10	47.21	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	HMW-17S-15	09/03/20	HC	F&BI	15	42.21	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	HMW-17S-20	09/03/20	HC	F&BI	20	37.21	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	HMW-17S-25	09/03/20	HC	F&BI	25	32.21	S	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
HMW-18S	HMW-18S-5	09/03/20	HC	F&BI	5	52.61	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	HMW-18S-10	09/03/20	HC	F&BI	10	47.61	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	**0.0059**
	HMW-18S-15	09/03/20	HC	F&BI	15	42.61	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	HMW-18S-20	09/03/20	HC	F&BI	20	37.61	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	HMW-18S-25	09/03/20	HC	F&BI	25	32.61	S	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	HMW-18S-30	09/03/20	HC	F&BI	30	27.61	S	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
HMW-19S	HMW-19S-5	09/08/20	HC	F&BI	5	53.2	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	HMW-19S-10	09/08/20	HC	F&BI	10	48.2	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	HMW-19S-15	09/08/20	HC	F&BI	15	43.2	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	HMW-19S-20	09/08/20	HC	F&BI	20	38.2	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	HMW-19S-26	09/08/20	HC	F&BI	26	32.2	S	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	HMW-19S-30	09/08/20	HC	F&BI	30	28.2	S	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	**0.013**
HMW-20S	HMW-20S-5	09/08/20	HC	F&BI	5	48.81	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	HMW-20S-10	09/08/20	HC	F&BI	10	43.81	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	HMW-20S-15	09/08/20	HC	F&BI	15	38.81	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	HMW-20S-20	09/08/20	HC	F&BI	20	33.81	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	HMW-20S-25	09/08/20	HC	F&BI	25	28.81	S	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	HMW-20S-30	09/08/20	HC	F&BI	30	23.81	S	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
MBB-1	MBB-1-5	02/27/20	HC	AAL	5	50.02	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	MBB-1-10	02/27/20	HC	AAL	10	45.02	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	MBB-1-15	02/27/20	HC	AAL	15	40.02	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	MBB-1-20	02/27/20	HC	AAL	20	35.02	V	0.050 U	0.050 U	0.050 U	0.50 U	0.050 U	0.50 U	0.050 U	–	–	0.050 U	–	**0.72**
	MBB-1-25	02/27/20	HC	AAL	25	30.02	S	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
MBB-2	MBB-2-5	02/27/20	HC	AAL	5	50.45	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	MBB-2-10	02/27/20	HC	AAL	10	45.45	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	MBB-2-15	02/27/20	HC	AAL	15	40.45	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	MBB-2-20	02/27/20	HC	AAL	20	35.45	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	MBB-2-20a	02/27/20	HC	AAL	20 (dup)	35.45	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	MBB-2-25	02/27/20	HC	AAL	25	30.45	S	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
MBB-3	MBB-3-5	02/27/20	HC	AAL	5	49.84	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	MBB-3-10	02/27/20	HC	AAL	10	44.84	V	0.050 U	0.050 U	0.050 U	0.50 U	0.050 U	0.50 U	0.050 U	–	–	0.050 U	–	**0.82 J**
	MBB-3-15	02/27/20	HC	AAL	15	39.84	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	MBB-3-20	02/27/20	HC	AAL	20	34.84	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	MBB-3-25	02/27/20	HC	AAL	25	29.84	S	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	**0.021**
MBB-4	MBB-4-5	02/27/20	HC	AAL	5	49.61	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	MBB-4-10	02/27/20	HC	AAL	10	44.61	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	**0.0052**
	MBB-4-10a	02/27/20	HC	AAL	10 (dup)	44.61	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	**0.025**
	MBB-4-15	02/27/20	HC	AAL	15	39.61	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	MBB-4-20	02/27/20	HC	AAL	20	34.61	V	0.050 U	0.050 U	0.050 U	0.50 U	0.050 U	0.50 U	0.050 U	–	–	0.050 U	–	**0.15 J**
	MBB-4-25	02/27/20	HC	AAL	25	29.61	S	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	**0.0060**
MBB-5	MBB-5-5	03/02/20	HC	AAL	5	45.3	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	MBB-5-10	03/02/20	HC	AAL	10	40.3	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	MBB-5-15	03/02/20	HC	AAL	15	35.3	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	MBB-5-20	03/02/20	HC	AAL	20	30.3	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	MBB-5-25	03/02/20	HC	AAL	25	25.3	S	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
MBB-6	MBB-6-5	03/03/20	HC	AAL	5	45.33	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	MBB-6-10	03/03/20	HC	AAL	10	40.33	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	MBB-6-15	03/03/20	HC	AAL	15	35.33	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	MBB-6-20	03/03/20	HC	AAL	20	30.33	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	MBB-6-25	03/03/20	HC	AAL	25	25.33	S	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
MBB-7	MBB-7-5	02/25/20	HC	AAL	5	44.41	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	MBB-7-10	02/25/20	HC	AAL	10	39.41	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	MBB-7-15	02/25/20	HC	AAL	15	34.41	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	MBB-7-20	02/25/20	HC	AAL	20	29.41	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
	MBB-7-25	02/25/20	HC	AAL	25	24.41	S	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.0050 U
MBB-8	MBB-8-5	02/26/20	HC	AAL	5	44.66	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.020 U
	MBB-8-10	02/26/20	HC	AAL	10	39.66	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.020 U
	MBB-8-15	02/26/20	HC	AAL	15	34.66	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.020 U
	MBB-8-15 dup	02/26/20	HC	AAL	15 (dup)	34.66	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.020 U
	MBB-8-20	02/26/20	HC	AAL	20	29.66	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.020 U
	MBB-8-25	02/26/20	HC	AAL	25	24.66	S	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.020 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
MBB-9	MBB-9-5	02/26/20	HC	AAL	5	42.55	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.020 U
	MBB-9-10	02/26/20	HC	AAL	10	37.55	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.020 U
	MBB-9-15	02/26/20	HC	AAL	15	32.55	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.020 U
	MBB-9-20	02/26/20	HC	AAL	20	27.55	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.020 U
	MBB-9-25	02/26/20	HC	AAL	25	22.55	S	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.020 U
MBB-10	MBB-10-5	02/26/20	HC	AAL	5	44.66	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.020 U
	MBB-10-10	02/26/20	HC	AAL	10	39.66	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.020 U
	MBB-10-15	02/26/20	HC	AAL	15	34.66	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.020 U
	MBB-10-20	02/26/20	HC	AAL	20	29.66	V	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.020 U
	MBB-10-25	02/26/20	HC	AAL	25	24.66	S	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U	0.050 U	0.0050 U	–	–	0.0050 U	–	0.020 U
MBB-14	MBB-14-5	03/03/20	HC	AAL	5	42.15	V	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-14-10	03/03/20	HC	AAL	10	37.15	V	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-14-15	03/03/20	HC	AAL	15	32.15	V	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-14-20	03/03/20	HC	AAL	20	27.15	V	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-14-25	03/03/20	HC	AAL	25	22.15	V	–	–	–	–	–	–	–	–	–	–	–	–
MBB-15	MBB-15-5	03/04/20	HC	AAL	5	32.73	V	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-15-10	03/04/20	HC	AAL	10	27.73	V	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-15-15	03/04/20	HC	AAL	15	22.73	V	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-15-20	03/04/20	HC	AAL	20	17.73	S	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-15-25	03/04/20	HC	AAL	25	12.73	S	–	–	–	–	–	–	–	–	–	–	–	–
MBB-16	MBB16-5	09/02/20	HC	F&BI	5	48.7	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	**0.91**
	MBB16-10	09/02/20	HC	F&BI	10	43.7	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	**0.13**
	MBB16-15	09/02/20	HC	F&BI	15	38.7	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	**0.014**
	MBB16-20	09/02/20	HC	F&BI	20	33.7	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
MBB-17	MBB17-5	09/01/20	HC	F&BI	5	49.88	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	MBB17-10	09/01/20	HC	F&BI	10	44.88	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	MBB17-15	09/01/20	HC	F&BI	15	39.88	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	MBB17-25	09/01/20	HC	F&BI	25	29.88	S	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
MBB-18	MBB18-5	09/01/20	HC	F&BI	5	46.33	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	MBB18-10	09/01/20	HC	F&BI	10	41.33	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	MBB18-15	09/01/20	HC	F&BI	15	36.33	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	MBB18-20	09/01/20	HC	F&BI	20	31.33	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
MBB-19	MBB19-5	09/01/20	HC	F&BI	5	46.68	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	MBB19-10	09/01/20	HC	F&BI	10	41.68	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	MBB19-15	09/01/20	HC	F&BI	15	36.68	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	MBB19-20	09/01/20	HC	F&BI	20	31.68	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
MBB-20	MBB20-5	09/02/20	HC	F&BI	5	42.53	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	MBB20-10	09/02/20	HC	F&BI	10	37.53	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	MBB20-15	09/02/20	HC	F&BI	15	32.53	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	MBB20-20	09/02/20	HC	F&BI	20	27.53	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
MBB-21	MBB21-5	09/02/20	HC	F&BI	5	42.6	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	MBB21-10	09/02/20	HC	F&BI	10	37.6	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	MBB21-15	09/02/20	HC	F&BI	15	32.6	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	MBB21-20	09/02/20	HC	F&BI	20	27.6	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
MBB-22	MBB-22-5	09/21/20	HC	F&BI	5	37.05	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	MBB-22-15	09/21/20	HC	F&BI	15	27.05	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	MBB-22-20	09/21/20	HC	F&BI	20	22.05	S	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	MBB-22-25	09/21/20	HC	F&BI	25	17.05	S	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	MBB-22-30	09/21/20	HC	F&BI	30	12.05	S	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
MBB-23	MBB-23-5	09/21/20	HC	F&BI	5	42.18	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	MBB-23-10	09/21/20	HC	F&BI	10	37.18	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	MBB-23-15	09/21/20	HC	F&BI	15	32.18	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	MBB-23-20	09/21/20	HC	F&BI	20	27.18	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	MBB-23-25	09/21/20	HC	F&BI	25	22.18	S	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	MBB-23-30	09/21/20	HC	F&BI	30	17.18	S	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	**0.014**	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
MBB-24	MMB24-5	09/09/20	HC	F&BI	5	49.1	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	MMB24-10	09/09/20	HC	F&BI	10	44.1	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	MMB24-15	09/09/20	HC	F&BI	15	39.1	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	MMB24-20	09/09/20	HC	F&BI	20	34.1	V	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	MMB24-25	09/09/20	HC	F&BI	25	29.1	S	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
	MMB24-30	09/09/20	HC	F&BI	30	24.1	S	0.0050 U	0.0050 U	–	0.050 U	0.0050 U	0.050 U	0.0050 U	0.0050 U	0.0050 U	0.0050 U	0.050 U	0.0050 U
MBGW-1	MBGW1-5	03/06/19	HC	AAL	5	34.95	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW1-12.5	03/06/19	HC	AAL	12.5	27.45	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW1-17.5	03/06/19	HC	AAL	17.5	22.45	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW1-25	03/06/19	HC	AAL	25	14.95	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW1-30	03/06/19	HC	AAL	30	9.95	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-2	MBGW2-5	03/04/19	HC	AAL	5	41.11	V	–	–	–	–	–	–	–	–	–	–	–	–
	MBGW2-10	03/04/19	HC	AAL	10	36.11	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW2-12.5	03/04/19	HC	AAL	12.5	33.61	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW2-25	03/04/19	HC	AAL	25	21.11	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW2-30	03/04/19	HC	AAL	30	16.11	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-3	MBGW3-5	03/07/19	HC	AAL	5	42.77	V	–	–	–	–	–	–	–	–	–	–	–	–
	MBGW3-7.5	03/07/19	HC	AAL	7.5	40.27	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW3-10	03/07/19	HC	AAL	10	37.77	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW3-12.5	03/07/19	HC	AAL	12.5	35.27	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW3-25	03/07/19	HC	AAL	25	22.77	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW3-26	03/07/19	HC	AAL	26	21.77	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
MBGW-4	MBGW4-5	03/06/19	HC	AAL	5	42.3	V	–	–	–	–	–	–	–	–	–	–	–	–
	MBGW4-7.5	03/06/19	HC	AAL	7.5	39.8	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW4-10	03/06/19	HC	AAL	10	37.3	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW4-12.5	03/06/19	HC	AAL	12.5	34.8	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW4-25	03/06/19	HC	AAL	25	22.3	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-5	MBGW5-10	03/11/19	HC	AAL	10	39.87	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW5-15	03/11/19	HC	AAL	15	34.87	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW5-20	03/11/19	HC	AAL	20	29.87	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW5-27.5	03/11/19	HC	AAL	27.5	22.37	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW5-45	03/11/19	HC	AAL	45	4.87	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	**0.26**	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-6	MBGW6-10	03/14/19	HC	AAL	10	42.5	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW6-15	03/14/19	HC	AAL	15	37.5	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW6-20	03/14/19	HC	AAL	20	32.5	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW6-30	03/14/19	HC	AAL	30	22.5	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-7	MBGW7-30	03/06/19	HC	AAL	30	23.76	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-8	MBGW8-10	03/15/19	HC	AAL	10	37.08	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW8-15	03/15/19	HC	AAL	15	32.08	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW8-25	03/15/19	HC	AAL	25	22.08	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW8-35	03/15/19	HC	AAL	35	12.08	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-9	MBGW9-10	03/13/19	HC	AAL	10	46.84	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW9-15	03/13/19	HC	AAL	15	41.84	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW9-20	03/13/19	HC	AAL	20	36.84	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW9-25	03/13/19	HC	AAL	25	31.84	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW9-30	03/13/19	HC	AAL	30	26.84	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-10	MBGW10-10	03/13/19	HC	AAL	10	45.25	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW10-15	03/13/19	HC	AAL	15	40.25	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW10-20	03/13/19	HC	AAL	20	35.25	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW10-25	03/13/19	HC	AAL	25	30.25	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW10-30	03/13/19	HC	AAL	30	25.25	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-11	MBGW11-5	03/12/19	HC	AAL	5	52.55	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW11-10	03/12/19	HC	AAL	10	47.55	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-12	MBGW12-5	03/15/19	HC	AAL	5	49.00	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW12-20	03/15/19	HC	AAL	20	34.00	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW12-25	03/15/19	HC	AAL	25	29.00	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW12-30	03/15/19	HC	AAL	30	24.00	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
MBGW-13	MBGW13-5	03/14/19	HC	AAL	5	49.72	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW13-7.5	03/14/19	HC	AAL	7.5	47.22	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	**0.17 J**
	MBGW13-10	03/14/19	HC	AAL	10	44.72	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	**3.9**
	MBGW13-12.5	03/14/19	HC	AAL	12.5	42.22	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	**0.50 J**
	MBGW13-15	03/14/19	HC	AAL	15	39.72	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	**0.11**
	MBGW13-20	03/14/19	HC	AAL	20	34.72	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	**0.060 J**
MBGW-14	MBGW14-10	03/06/19	HC	AAL	10	36.09	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW14-15	03/06/19	HC	AAL	15	31.09	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW14-20	03/06/19	HC	AAL	20	26.09	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW14-30	03/06/19	HC	AAL	30	16.09	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-16	MBGW16-10	03/08/19	HC	AAL	10	42.14	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW16-15	03/08/19	HC	AAL	15	37.14	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW16-30	03/08/19	HC	AAL	30	22.14	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-1	MBPP1-20	03/05/19	HC	AAL	20	25.28	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP1-25	03/05/19	HC	AAL	25	20.28	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-2	MBPP2-10	03/05/19	HC	AAL	10	34.46	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP2-20	03/05/19	HC	AAL	20	24.46	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP2-27.5	03/05/19	HC	AAL	27.5	16.96	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-3	MBPP3-10	03/06/19	HC	AAL	10	35.89	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP3-20	03/06/19	HC	AAL	20	25.89	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP3-25	03/06/19	HC	AAL	25	20.89	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-4	MBPP4-2.5	03/07/19	HC	AAL	2.5	45.84	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP4-10	03/07/19	HC	AAL	10	38.34	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP4-15	03/07/19	HC	AAL	15	33.34	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP4-17	03/07/19	HC	AAL	17	31.34	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP4-18	03/07/19	HC	AAL	18	30.34	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-5	MBPP5-10	03/07/19	HC	AAL	10	35.92	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP5-15	03/07/19	HC	AAL	15	30.92	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP5-17.5	03/07/19	HC	AAL	17.5	28.42	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP5-20	03/07/19	HC	AAL	20	25.92	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP5-25	03/07/19	HC	AAL	25	20.92	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-6	MBPP6-7.5	03/08/19	HC	AAL	7.5	44.76	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP6-10	03/08/19	HC	AAL	10	42.26	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP6-12.5	03/08/19	HC	AAL	12.5	39.76	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP6-15	03/08/19	HC	AAL	15	37.26	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
MBPP-6	MBPP6-17.5	03/08/19	HC	AAL	17.5	34.76	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
(continued)	MBPP6-20	03/08/19	HC	AAL	20	32.26	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP6-25	03/08/19	HC	AAL	25	27.26	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP6-30	03/08/19	HC	AAL	30	22.26	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-7	MBPP7-5	03/08/19	HC	AAL	5	44.77	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP7-15	03/08/19	HC	AAL	15	34.77	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP7-23	03/08/19	HC	AAL	23	26.77	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-8	MBPP8-10	03/08/19	HC	AAL	10	47.52	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP8-15	03/08/19	HC	AAL	15	42.52	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP8-22.5	03/08/19	HC	AAL	22.5	35.02	V	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP8-30	03/08/19	HC	AAL	30	27.52	S	0.050 U	0.050 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U
MW-345	MW-345-41	05/20/21	PES	PACE	41	11.85	S	0.00111 U	0.000259 U	0.000755 U	0.00210 U	0.00127 U	0.00536 U	**0.984**	0.000933 U	0.000925 U	0.000894 U	0.00199 U	0.000909 U
	MW-345-47	05/20/21	PES	PACE	47	5.85	S	0.00106 U	0.000247 U	0.000719 U	0.00200 U	0.00121 U	0.00511 U	**0.0973**	0.000890 U	0.000881 U	0.000852 U	0.00189 U	0.000866 U
	MW-2023-47	05/20/21	PES	PACE	47 (dup)	5.85	S	0.00130 U	0.000304 U	0.000885 U	0.00246 U	0.00149 U	0.00629 U	**0.122**	0.00109 U	0.00109 U	0.00105 U	0.00232 U	0.00107 U
	MW-345-53	05/20/21	PES	PACE	53	-0.15	S	0.00105 U	0.000246 U	0.000716 U	0.00199 U	0.00120 U	0.00509 U	0.000859 U	0.000886 U	0.000877 U	0.000848 U	0.00188 U	0.000862 U
	MW-345-58	05/20/21	PES	PACE	58	-5.15	S	0.00131 U	0.000308 U	0.000896 U	0.00249 U	0.00151 U	0.00636 U	**0.108**	0.00111 U	0.00110 U	0.00106 U	0.00235 U	0.00108 U
	MW-345-63	05/20/21	PES	PACE	63	-10.15	S	0.00120 U	0.000282 U	0.000821 U	0.00228 U	0.00138 U	0.00584 U	0.000985 U	0.00102 U	0.00101 U	0.000973 U	0.00216 U	0.000989 U
MW-346	MW-346-41.5	05/19/21	PES	PACE	41.5	10.28	S	0.00109 U	0.000255 U	0.000743 U	0.00206 U	0.00125 U	0.00528 U	**0.661**	0.000919 U	0.000910 U	0.000880 U	0.00195 U	0.000894 U
	MW-346-47	05/19/21	PES	PACE	47	4.78	S	0.00105 U	0.000246 U	0.000717 U	0.00199 U	0.00121 U	0.00510 U	**0.148**	0.000887 U	0.000879 U	0.000849 U	0.00189 U	0.000864 U
	MW-346-52	05/19/21	PES	PACE	52	-0.22	S	0.00105 U	0.000245 U	0.000715 U	0.00199 U	0.00120 U	0.00508 U	**0.0516**	0.000884 U	0.000876 U	0.000847 U	0.00188 U	0.000861 U
	MW-346-54.5	05/19/21	PES	PACE	54.5	-2.72	S	0.00435 U	0.00102 U	0.00297 U	0.00825 U	0.00500 U	0.0211 U	**0.0694**	0.00367 U	0.00364 U	0.00352 U	0.00781 U	0.00358 U
	MW-346-57.5	05/19/21	PES	PACE	57.5	-5.72	S	0.00105 U	0.000245 U	0.000715 U	0.00199 U	0.00120 U	0.00508 U	0.000858 U	0.000885 U	0.000876 U	0.000847 U	0.00188 U	0.000861 U
	MW-346-62	05/19/21	PES	PACE	62	-10.22	S	0.00115 U	0.000268 U	0.000782 U	0.00217 U	0.00132 U	0.00556 U	**0.00167 J**	0.000968 U	0.000959 U	0.000927 U	0.00206 U	0.000942 U
MW-347	MW-347-44.5	05/19/21	PES	PACE	44.5	8.29	S	0.00126 U	0.000295 U	0.000859 U	0.00239 U	0.00145 U	0.00611 U	**0.954**	0.00106 U	0.00105 U	0.00102 U	0.00226 U	0.00104 U
	MW-2022-44.5	05/19/21	PES	PACE	44.5 (dup)	8.29	S	0.00117 U	0.000274 U	0.000799 U	0.00222 U	0.00134 U	0.00568 U	**0.753**	0.000988 U	0.000979 U	0.000946 U	0.00210 U	0.000962 U
	MW-347-48	05/19/21	PES	PACE	48	4.79	S	0.00105 U	0.000245 U	0.000715 U	0.00199 U	0.00120 U	0.00508 U	0.000858 U	0.000885 U	0.000876 U	0.000847 U	0.00188 U	0.000861 U
	MW-347-54.5	05/19/21	PES	PACE	54.5	-1.71	S	0.00108 U	0.000253 U	0.000738 U	0.00205 U	0.00124 U	0.00524 U	**0.00202 J**	0.000912 U	0.000904 U	0.000874 U	0.00194 U	0.000888 U
	MW-347-58	05/19/21	PES	PACE	58	-5.21	S	0.00107 U	0.000250 U	0.000729 U	0.00202 U	0.00123 U	0.00518 U	**0.0781**	0.000901 U	0.000893 U	0.000863 U	0.00192 U	0.000877 U
	MW-347-65	05/19/21	PES	PACE	65	-12.21	S	0.00114 U	0.000267 U	0.000778 U	0.00216 U	0.00131 U	0.00553 U	**0.00183 J**	0.000962 U	0.000953 U	0.000921 U	0.00205 U	0.000937 U
MW-348	MW-348-41	05/18/21	PES	PACE	41	12.96	S	0.00115 U	0.000270 U	0.000786 U	0.00218 U	0.00132 U	0.00559 U	**6.55**	0.000973 U	0.000964 U	0.000932 U	0.00207 U	0.000947 U
	MW-348-49	05/18/21	PES	PACE	49	4.96	S	0.00116 U	0.000270 U	0.000787 U	0.00219 U	0.00133 U	0.00560 U	**0.472**	0.000974 U	0.000965 U	0.000933 U	0.00207 U	0.000948 U
	MW-348-54.5	05/18/21	PES	PACE	54.5	-0.54	S	0.00104 U	0.000243 U	0.000708 U	0.00197 U	0.00119 U	0.00503 U	**0.0299**	0.000876 U	0.000868 U	0.000839 U	0.00186 U	0.000853 U
	MW-348-60	05/18/21	PES	PACE	60	-6.04	S	0.00103 U	0.000242 U	0.000705 U	0.00196 U	0.00119 U	0.00501 U	**0.0190**	0.000872 U	0.000864 U	0.000835 U	0.00185 U	0.000849 U
	MW-348-65	05/18/21	PES	PACE	65	-11.04	S	0.00112 U	0.000262 U	0.000765 U	0.00212 U	0.00129 U	0.00544 U	**0.00259 J**	0.000946 U	0.000937 U	0.000906 U	0.00201 U	0.000921 U
	MW-348-69	05/18/21	PES	PACE	69	-15.04	S	0.00110 U	0.000257 U	0.000748 U	0.00208 U	0.00126 U	0.00532 U	**0.0198**	0.000926 U	0.000917 U	0.000886 U	0.00197 U	0.000901 U
MW-349	MW-349-49	05/17/21	PES	PACE	49	6.84	S	0.00115 U	0.000269 U	0.000784 U	0.00218 U	0.00132 U	0.00557 U	**0.572**	0.000969 U	0.000961 U	0.000928 U	0.00206 U	0.000944 U
	MW-349-51	05/17/21	PES	PACE	51	4.84	S	0.00107 U	0.000251 U	0.000730 U	0.00203 U	0.00123 U	0.00519 U	**0.0675**	0.000903 U	0.000895 U	0.000865 U	0.00192 U	**0.00101 J**
	MW-349-56	05/17/21	PES	PACE	56	-0.16	S	0.00107 U	0.000250 U	0.000729 U	0.00202 U	0.00123 U	0.00518 U	**0.00200 J**	0.000901 U	0.000893 U	0.000863 U	0.00192 U	0.000877 U
	MW-349-61	05/17/21	PES	PACE	61	-5.16	S	0.00109 U	0.000256 U	0.000746 U	0.00207 U	0.00126 U	0.00530 U	0.000894 U	0.000922 U	0.000914 U	0.000883 U	0.00196 U	0.000898 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Carbon Tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform	Chloromethane	Cis-1,2-Dichloroethene (cDCE)	Cis-1,3-Dichloropropene	Dibromomethane	Dichlorobromomethane	Dichlorodifluoromethane (CFC-12)	Ethylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.042**	**0.86**	**0.028**	–	**0.074**	–	**0.078**	**0.0023**	**0.42**	**0.036**	**38**	**5.9**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.0022**	**0.051**	**0.004**	–	**0.007**	–	**0.0052**	**0.00014**	**0.028**	**0.0024**	**0.53**	**0.34**
MW-349	MW-349-66	05/17/21	PES	PACE	66	-10.16	S	0.00109 U	0.000256 U	0.000746 U	0.00207 U	0.00126 U	0.00530 U	0.000895 U	0.000923 U	0.000914 U	0.000884 U	0.00196 U	0.000898 U
(continued)	MW-349-68	05/17/21	PES	PACE	68	-12.16	S	0.00113 U	0.000263 U	0.000768 U	0.00213 U	0.00129 U	0.00546 U	**0.00213 J**	0.000950 U	0.000941 U	0.000910 U	0.00202 U	0.000925 U
MW-350	MW-350-41	05/21/21	PES	PACE	41	16.77	S	0.00116 U	0.000271 U	0.000790 U	0.00219 U	0.00133 U	0.00561 U	0.000947 U	0.000977 U	0.000968 U	0.000936 U	0.00208 U	**0.920**
	MW-350-53	05/21/21	PES	PACE	53	4.77	S	0.00106 U	0.000248 U	0.000722 U	0.00201 U	0.00122 U	0.00513 U	0.000866 U	0.000894 U	0.000885 U	0.000856 U	0.00190 U	**0.00117 J**
	MW-350-58	05/21/21	PES	PACE	58	-0.23	S	0.00105 U	0.000246 U	0.000716 U	0.00199 U	0.00121 U	0.00509 U	0.000859 U	0.000886 U	0.000878 U	0.000849 U	0.00188 U	0.000863 U
	MW-350-64.5	05/21/21	PES	PACE	64.5	-6.73	S	0.00110 U	0.000258 U	0.000752 U	0.00209 U	0.00127 U	0.00534 U	0.000902 U	0.000930 U	0.000921 U	0.000891 U	0.00198 U	0.000905 U
	MW-350-69	05/21/21	PES	PACE	69	-11.23	S	0.00114 U	0.000266 U	0.000776 U	0.00216 U	0.00131 U	0.00552 U	0.000931 U	0.000960 U	0.000951 U	0.000919 U	0.00204 U	**0.00834**
All Data	Number of Analytes Measured							397	397	307	397	397	397	397	256	256	397	256	397
	Number of Analytes Detected							0	0	0	0	0	0	24	0	0	0	0	24
	Frequency of Detection							0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	6.0%	0.0%	0.0%	0.0%	0.0%	6.0%
	Maximum Detection							–	–	–	–	–	–	6.55	–	–	–	–	3.9
	Minimum Detection							0.00103 U	0.00024 U	0.00071 U	0.00196 U	0.00119 U	0.00501 U	0.00086 U	0.00087 U	0.00086 U	0.00084 U	0.00185 U	0.00085 U
	Number Of Vadose (V) Detections above SL							0	0	0	–	0	–	0	0	0	0	0	0
	Number of Saturated (S) Detections above SL							0	0	0	–	0	–	18	0	0	0	0	2
2017-2021	Number of Analytes Measured							397	397	307	397	397	397	397	256	256	397	256	397
	Number of Analytes Detected							0	0	0	0	0	0	24	0	0	0	0	24
	Frequency of Detection							0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	6.0%	0.0%	0.0%	0.0%	0.0%	6.0%
	Maximum Detection							–	–	–	–	–	–	6.55	–	–	–	–	3.9
	Minimum Detection							0.00103 U	0.00024 U	0.00071 U	0.00196 U	0.00119 U	0.00501 U	0.00086 U	0.00087 U	0.00086 U	0.00084 U	0.00185 U	0.00085 U
	Number Of Vadose (V) Detections above SL							0	0	0	–	0	–	0	0	0	0	0	0
	Number of Saturated (S) Detections above SL							0	0	0	–	0	–	18	0	0	0	0	2

Notes and Abbreviations:
Petroleum Hydrocarbons (PHCs) analyzed by Ecology Methods NWTPH-Gx and NWTPH-Dx.
VOCs analyzed by EPA Method 8260 C/D.
PCUL = Preliminary Cleanup Level from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021. PCULs based on the practical quantitation limits (PQLs) italicized. Detected results shown in bold.
Detections above the screening level in the vadose zone are shown in **bold and highlighted blue.**
Detections above the screening level in the saturated zone are shown in **bold and highlighted gray.**
– = Not available or results not analyzed.
J = The reported concentration is an estimate based on detectable results between the method detection limit and reporting limit, laboratory QA/QC, or data validation review.
J+ = The result is an estimated quantity, but the result may be biased high.
J- = The result is an estimated quantity, but the result may be biased low.
U = Not detected at a concentration exceeding laboratory reporting limit
z = Gasoline/petroleum detection result is likely elevated due to high detections of CVOCs.
AAL = Alden Analytical Laboratories, Inc., of Seattle, Washington
bgs = below ground surface
dup = duplicate
F&BI = Friedman & Bruya, Inc.
HC = Hart Crowser, Inc.
Pace = Pace Analytical of Mt. Juliet, Tennessee (formerly ESC)
PES = PES Environmental, Inc.

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
615 Dexter Avenue																			
DGW-1	DGW1-10	03/06/19	HC	AAL	10	37	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	1.0 U	0.050 U	0.050 U	0.050 U
	DGW1-12.5	03/06/19	HC	AAL	12.5	34.5	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW1-15	03/06/19	HC	AAL	15	32	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW1-25	03/06/19	HC	AAL	25	22	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW1-30	03/06/19	HC	AAL	30	17	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
DGW-2	DGW2-5	03/04/19	HC	AAL	5	54	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW2-10	03/04/19	HC	AAL	10	49	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW2-25	03/04/19	HC	AAL	25	34	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW2-30	03/04/19	HC	AAL	30	29	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
DGW-3	DGW3-2.5	03/06/19	HC	AAL	2.5	44.5	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW3-12.5	03/06/19	HC	AAL	12.5	34.5	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW3-15	03/06/19	HC	AAL	15	32	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW3-20	03/06/19	HC	AAL	20	27	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW3-25	03/06/19	HC	AAL	25	22	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
DGW-4	DGW4-5	03/04/19	HC	AAL	5	60	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW4-10	03/04/19	HC	AAL	10	55	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW4-15	03/04/19	HC	AAL	15	50	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW4-20	03/04/19	HC	AAL	20	45	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW4-35	03/04/19	HC	AAL	35	30	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW4-50	03/04/19	HC	AAL	50	15	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
DMW-1S	DMW1S-5	03/05/19	HC	AAL	5	42	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DMW1S-10	03/05/19	HC	AAL	10	37	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	**0.18**	**0.11**	**0.071**
	DMW1S-12.5	03/05/19	HC	AAL	12.5	34.5	S	0.050 U	–	–	–	**1.5**	–	0.10 U	0.020 U	0.050 U	**0.82**	**3.2**	**1.9**
	DMW1S-15	03/05/19	HC	AAL	15	32	S	0.050 U	–	–	–	**0.12**	–	0.10 U	0.020 U	1.0 U	**0.58**	**0.28**	**0.25**
	DMW1S-20	03/05/19	HC	AAL	20	27	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
DMW-2S	DMW-2S-05	03/02/20	HC	AAL	5	51.03	V	0.025 UJ	–	–	–	–	–	–	**0.029 J**	–	–	–	–
	DMW-2S-10	03/02/20	HC	AAL	10	46.03	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	DMW-2S-15	03/02/20	HC	AAL	15	41.03	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	DMW-2S-20	03/02/20	HC	AAL	20	36.03	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	DMW-2S-25	03/02/20	HC	AAL	25	31.03	S	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
DMW-3IA	DMW-3IA-5	02/27/20	HC	AAL	5	51.09	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	DMW-3IA-10	02/27/20	HC	AAL	10	46.09	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	DMW-3IA-15	02/27/20	HC	AAL	15	41.09	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	DMW-3IA-20	02/27/20	HC	AAL	20	36.09	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	DMW-3IA-25	02/27/20	HC	AAL	25	31.09	S	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
DMW-4S	DMW-4S-5	02/26/20	HC	AAL	5	56.76	V	0.025 U	–	–	–	–	–	–	0.020 UJ	0.010 U	–	–	–
	DMW-4S-10	02/26/20	HC	AAL	10	51.76	V	0.025 U	–	–	–	–	–	–	0.020 UJ	0.010 U	–	–	–
	DMW-4S-15	02/26/20	HC	AAL	15	46.76	V	0.025 U	–	–	–	–	–	–	0.020 UJ	0.010 U	–	–	–
	DMW-4S-20	02/26/20	HC	AAL	20	41.76	V	0.025 U	–	–	–	–	–	–	0.020 UJ	0.010 U	–	–	–
	DMW-4S-25	02/26/20	HC	AAL	25	36.76	S	0.025 U	–	–	–	–	–	–	0.020 UJ	**0.014**	–	–	–
	DMW-4S-30	02/26/20	HC	AAL	30	31.76	S	0.025 U	–	–	–	–	–	–	0.020 UJ	0.010 U	–	–	–
DMW-5IA	DMW-5IA-5	02/28/20	HC	AAL	5	64.48	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	DMW-5IA-10	02/28/20	HC	AAL	10	59.48	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	DMW-5IA-15	02/28/20	HC	AAL	15	54.48	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	DMW-5IA-20	02/28/20	HC	AAL	20	49.48	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	DMW-5IA-25	02/28/20	HC	AAL	25	44.48	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
DPP-1	DPP1-5	03/04/19	HC	AAL	5	54.5	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP1-7.5	03/05/19	HC	AAL	7.5	52	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP1-10	03/04/19	HC	AAL	10	49.5	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP1-20	03/04/19	HC	AAL	20	39.5	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
DPP-2	DPP2-5	03/04/19	HC	AAL	5	54	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP2-10	03/04/19	HC	AAL	10	49	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
DPP-3	DPP3-5	03/05/19	HC	AAL	5	42	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP3-15	03/05/19	HC	AAL	15	32	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP3-30	03/05/19	HC	AAL	30	17	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
DPP-4	DPP4-10	03/04/19	HC	AAL	10	49	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP4-12.5	03/04/19	HC	AAL	12.5	46.5	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP4-17.5	03/04/19	HC	AAL	17.5	41.5	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP4-20	03/04/19	HC	AAL	20	39	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
DPP-5	DPP5-10	03/04/19	HC	AAL	10	49	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP5-17.5	03/04/19	HC	AAL	17.5	41.5	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP5-20	03/04/19	HC	AAL	20	39	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
DPP-6	DPP6-5	03/05/19	HC	AAL	5	42	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP6-7.5	03/05/19	HC	AAL	7.5	39.5	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP6-12.5	03/05/19	HC	AAL	12.5	34.5	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP6-17.5	03/05/19	HC	AAL	17.5	29.5	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
Seattle DOT Mercer Parcels																			
HMW-1IB	HMW1IB-7.5	03/12/19	HC	AAL	7.5	30.5	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW1IB-15	03/12/19	HC	AAL	15	23	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW1IB-20.5	03/12/19	HC	AAL	20.5	18	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW1IB-27.5	03/12/19	HC	AAL	27.5	10.5	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW1IB-50	03/12/19	HC	AAL	50	-12	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW1IB-65	03/12/19	HC	AAL	65	-27	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
HMW-2IB	HMW2IB-7.5	03/12/19	HC	AAL	7.5	39.5	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW2IB-15	03/12/19	HC	AAL	15	32	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW2IB-22.5	03/12/19	HC	AAL	22.5	24.5	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW2IB-30	03/12/19	HC	AAL	30	17	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW2IB-45	03/12/19	HC	AAL	45	2	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW2IB-65	03/12/19	HC	AAL	65	-18	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
HMW-3IA	HMW3IA-15	03/15/19	HC	AAL	15	40.5	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW3IA-20	03/15/19	HC	AAL	20	35.5	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW3IA-22.5	03/15/19	HC	AAL	22.5	33	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW3IA-25	03/15/19	HC	AAL	25	30.5	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
HMW-4IA	HMW4IA-5	03/07/19	HC	AAL	5	51	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW4IA-7.5	03/07/19	HC	AAL	7.5	48.5	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	1.0 U	0.050 U	0.050 U	0.050 U
	HMW4IA-10	03/07/19	HC	AAL	10	46	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW4IA-25	03/07/19	HC	AAL	25	31	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
HMW-5IB	HMW5IB-5	02/28/20	HC	AAL	5	53.44	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.010 U	–	–	–
	HMW5IB-10	02/28/20	HC	AAL	10	48.44	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.010 U	–	–	–
	HMW5IB-15	02/28/20	HC	AAL	15	43.44	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.010 U	–	–	–
	HMW5IB-20	02/28/20	HC	AAL	20	38.44	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.010 U	–	–	–
	HMW5IB-25	02/28/20	HC	AAL	25	33.44	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.010 U	–	–	–
HMW-6D	HMW-6D-5	03/02/20	HC	AAL	5	53.58	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.050 U	–	–	–
	HMW-6D-10	03/02/20	HC	AAL	10	48.58	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.050 U	–	–	–
	HMW-6D-15	03/02/20	HC	AAL	15	43.58	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.050 U	–	–	–
	HMW-6D-25	03/02/20	HC	AAL	25	33.58	V	0.025 UJ	–	–	–	–	–	–	**0.028 J**	0.050 U	–	–	–
	HMW-6D-30	03/02/20	HC	AAL	30	28.58	S	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.010 U	–	–	–
	HMW-6D-30-Dup	03/02/20	HC	AAL	30 (dup)	28.58	S	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
HMW-6IA	HMW-6IA-5	03/02/20	HC	AAL	5	53.65	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.050 U	–	–	–
	HMW-6IA-10	03/02/20	HC	AAL	10	48.65	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.050 U	–	–	–
	HMW-6IA-15	03/02/20	HC	AAL	15	43.65	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.050 U	–	–	–
	HMW-6IA-20	03/02/20	HC	AAL	20	38.65	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.050 U	–	–	–
	HMW-6IA-30	03/02/20	HC	AAL	30	28.65	S	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.010 U	–	–	–
HMW-6IB	HMW-6IB-5	03/03/20	HC	AAL	5	53.67	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.050 U	–	–	–
	HMW-6IB-10	03/03/20	HC	AAL	10	48.67	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.050 U	–	–	–
	HMW-6IB-10a	03/03/20	HC	AAL	10 (dup)	48.67	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	HMW-6IB-15	03/03/20	HC	AAL	15	43.67	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.050 U	–	–	–
	HMW-6IB-20	03/03/20	HC	AAL	20	38.67	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.050 U	–	–	–
	HMW-6IB-25	03/03/20	HC	AAL	25	33.67	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.010 U	–	–	–

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
HMW-7IB	HMW7IB-5	02/28/20	HC	AAL	5	53.69	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.050 U	–	–	–
	HMW7IB-10	02/28/20	HC	AAL	10	48.69	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.050 U	–	–	–
	HMW7IB-15	02/28/20	HC	AAL	15	43.69	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.050 U	–	–	–
	HMW7IB-20	02/28/20	HC	AAL	20	38.69	V	0.025 UJ	–	–	–	–	–	–	**0.024 J**	0.050 U	–	–	–
	HMW7IB-25	02/28/20	HC	AAL	25	33.69	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.050 U	–	–	–
	HMW7IB-25a	02/28/20	HC	AAL	25 (dup)	33.69	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
HMW-8IB	HMW-8IB-5	03/02/20	HC	AAL	5	52.97	V	0.025 UJ	–	–	–	–	–	–	**0.024 J**	0.050 U	–	–	–
	HMW-8IB-10	03/02/20	HC	AAL	10	47.97	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.050 U	–	–	–
	HMW-8IB-15	03/02/20	HC	AAL	15	42.97	V	0.025 UJ	–	–	–	–	–	–	**0.037 J**	0.050 U	–	–	–
	HMW-8IB-20	03/02/20	HC	AAL	20	37.97	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.050 U	–	–	–
	HMW-8IB-25	03/02/20	HC	AAL	25	32.97	V	0.025 UJ	–	–	–	–	–	–	**0.024 J**	0.010 U	–	–	–
	HMW-8IB-25a	03/02/20	HC	AAL	25 (dup)	32.97	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
HMW-9D	HMW-9D-5	02/27/20	HC	AAL	5	50.32	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	HMW-9D-10	02/27/20	HC	AAL	10	45.32	V	0.025 UJ	–	–	–	–	–	–	**0.027 J**	–	–	–	–
	HMW-9D-15	02/27/20	HC	AAL	15	40.32	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	HMW-9D-20	02/27/20	HC	AAL	20	35.32	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	HMW-9D-25	02/27/20	HC	AAL	25	30.32	S	0.025 UJ	–	–	–	–	–	–	**0.022 J**	–	–	–	–
HMW-9IA	HMW9IA-5	02/28/20	HC	AAL	5	50.26	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	HMW9IA-10	02/28/20	HC	AAL	10	45.26	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	HMW9IA-15	02/28/20	HC	AAL	15	40.26	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	HMW9IA-20	02/28/20	HC	AAL	20	35.26	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	HMW9IA-25	02/28/20	HC	AAL	25	30.26	S	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
HMW-9IB	HMW9IB-5	02/28/20	HC	AAL	5	50.36	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	HMW9IB-13	02/28/20	HC	AAL	13	42.36	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	HMW9IB-15	02/28/20	HC	AAL	15	40.36	V	0.025 UJ	–	–	–	–	–	–	**0.032 J**	–	–	–	–
	HMW9IB-20	02/28/20	HC	AAL	20	35.36	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	HMW9IB-25	02/28/20	HC	AAL	25	30.36	S	0.025 UJ	–	–	–	–	–	–	**0.032 J**	–	–	–	–
HMW-9S	HMW-9S-5	03/02/20	HC	AAL	5	50.39	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	HMW-9S-14	03/02/20	HC	AAL	14	41.39	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	HMW-9S-17	03/02/20	HC	AAL	17	38.39	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	HMW-9S-20	03/02/20	HC	AAL	20	35.39	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	HMW-9S-25	03/02/20	HC	AAL	25	30.39	S	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
HMW-10D	HMW-10D-5	03/05/20	HC	F&BI	5	43.16	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	HMW-10D-10	03/05/20	HC	F&BI	10	38.16	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	HMW-10D-15	03/05/20	HC	F&BI	15	33.16	V	0.025 UJ	–	–	–	–	–	–	**0.030 J**	–	–	–	–
	HMW-10D-15a	03/05/20	HC	F&BI	15 (dup)	33.16	V	0.025 UJ	–	–	–	–	–	–	**0.024 J**	–	–	–	–
	HMW-10D-20	03/05/20	HC	F&BI	20	28.16	V	0.025 U	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	HMW-10D-25	03/05/20	HC	F&BI	25	23.16	S	0.025 U	–	–	–	–	–	–	0.020 UJ	–	–	–	–

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
HMW-10S	HMW10S-5	03/03/20	HC	F&BI	5	43.21	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	HMW-10S-10	03/03/20	HC	F&BI	10	38.21	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	HMW-10S-10a	03/03/20	HC	F&BI	10 (dup)	38.21	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	HMW-10S-15	03/03/20	HC	F&BI	15	33.21	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	HMW-10S-20	03/03/20	HC	F&BI	20	28.21	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	HMW-10S-25	03/03/20	HC	F&BI	25	23.21	S	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
HMW-11IB	HMW-11IB-5	02/24/20	HC	F&BI	5	34.7	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	HMW-11IB-10	02/24/20	HC	F&BI	10	29.7	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	HMW-11IB-15	02/24/20	HC	F&BI	15	24.7	V	0.025 UJ	–	–	–	–	–	–	**0.21 J**	–	–	–	–
	HMW-11IB-20	02/24/20	HC	F&BI	20	19.7	S	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	HMW-11IB-25	02/24/20	HC	F&BI	25	14.7	S	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
HMW-11S	HMW-11S-5	02/25/20	HC	F&BI	5	36.47	V	0.025 UJ	–	–	–	–	–	–	**0.020 J**	–	–	–	–
	HMW-11S-10	02/25/20	HC	F&BI	10	31.47	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	HMW-11S-15	02/25/20	HC	F&BI	15	26.47	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	HMW-11S-20	02/25/20	HC	F&BI	20	21.47	S	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	HMW-11S-30	02/25/20	HC	F&BI	30	11.47	S	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
HMW-17S	HMW-17S-5	09/03/20	HC	F&BI	5	52.21	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.015 J**	0.0050 U	–	0.0050 U	0.0050 U
	HMW-17S-10	09/03/20	HC	F&BI	10	47.21	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.0081 J**	0.0050 U	–	0.0050 U	0.0050 U
	HMW-17S-15	09/03/20	HC	F&BI	15	42.21	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	0.0078 UJ	0.0050 U	–	0.0050 U	0.0050 U
	HMW-17S-20	09/03/20	HC	F&BI	20	37.21	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.020 J**	0.0050 U	–	0.0050 U	0.0050 U
	HMW-17S-25	09/03/20	HC	F&BI	25	32.21	S	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.012 J**	0.0050 U	–	0.0050 U	0.0050 U
HMW-18S	HMW-18S-5	09/03/20	HC	F&BI	5	52.61	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	0.0078 UJ	0.0050 U	–	0.0050 U	0.0050 U
	HMW-18S-10	09/03/20	HC	F&BI	10	47.61	V	0.025 U	0.025 U	–	–	**0.0079**	0.050 U	0.0050 U	**0.018 J**	0.0050 U	–	**0.0077**	**0.011**
	HMW-18S-15	09/03/20	HC	F&BI	15	42.61	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.016 J**	0.0050 U	–	0.0050 U	0.0050 U
	HMW-18S-20	09/03/20	HC	F&BI	20	37.61	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	0.0078 UJ	0.0050 U	–	0.0050 U	0.0050 U
	HMW-18S-25	09/03/20	HC	F&BI	25	32.61	S	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.026 J**	0.0050 U	–	0.0050 U	0.0050 U
	HMW-18S-30	09/03/20	HC	F&BI	30	27.61	S	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.019 J**	0.0050 U	–	0.0050 U	0.0050 U
HMW-19S	HMW-19S-5	09/08/20	HC	F&BI	5	53.2	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.025 J**	0.0050 U	–	0.0050 U	0.0050 U
	HMW-19S-10	09/08/20	HC	F&BI	10	48.2	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.011 J**	0.0050 U	–	0.0050 U	0.0050 U
	HMW-19S-15	09/08/20	HC	F&BI	15	43.2	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.017 J**	0.0050 U	–	0.0050 U	0.0050 U
	HMW-19S-20	09/08/20	HC	F&BI	20	38.2	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.023 J**	0.0050 U	–	0.0050 U	0.0050 U
	HMW-19S-26	09/08/20	HC	F&BI	26	32.2	S	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.011 J**	0.0050 U	–	0.0050 U	0.0050 U
	HMW-19S-30	09/08/20	HC	F&BI	30	28.2	S	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	0.0078 U	**0.036**	–	**0.0099**	0.0050 U
HMW-20S	HMW-20S-5	09/08/20	HC	F&BI	5	48.81	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	0.0078 U	0.0050 U	–	0.0050 U	0.0050 U
	HMW-20S-10	09/08/20	HC	F&BI	10	43.81	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.0092 J**	0.0050 U	–	0.0050 U	0.0050 U
	HMW-20S-15	09/08/20	HC	F&BI	15	38.81	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	0.0078 UJ	0.0050 U	–	0.0050 U	0.0050 U
	HMW-20S-20	09/08/20	HC	F&BI	20	33.81	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.010 J**	0.0050 U	–	0.0050 U	0.0050 U
	HMW-20S-25	09/08/20	HC	F&BI	25	28.81	S	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.0096 J**	0.0050 U	–	0.0050 U	0.0050 U
	HMW-20S-30	09/08/20	HC	F&BI	30	23.81	S	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	0.0078 UJ	0.0050 U	–	0.0050 U	0.0050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
MBB-1	MBB-1-5	02/27/20	HC	AAL	5	50.02	V	0.025 UJ	–	–	–	–	–	–	**0.020 J**	0.010 U	–	–	–
	MBB-1-10	02/27/20	HC	AAL	10	45.02	V	0.025 UJ	–	–	–	–	–	–	**0.023 J**	0.010 U	–	–	–
	MBB-1-15	02/27/20	HC	AAL	15	40.02	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.010 U	–	–	–
	MBB-1-20	02/27/20	HC	AAL	20	35.02	V	0.25 UJ	–	–	–	–	–	–	0.50 UJ	**0.024**	–	–	–
	MBB-1-25	02/27/20	HC	AAL	25	30.02	S	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.010 U	–	–	–
MBB-2	MBB-2-5	02/27/20	HC	AAL	5	50.45	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.010 U	–	–	–
	MBB-2-10	02/27/20	HC	AAL	10	45.45	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.010 U	–	–	–
	MBB-2-15	02/27/20	HC	AAL	15	40.45	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.010 U	–	–	–
	MBB-2-20	02/27/20	HC	AAL	20	35.45	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.010 U	–	–	–
	MBB-2-20a	02/27/20	HC	AAL	20 (dup)	35.45	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.010 U	–	–	–
	MBB-2-25	02/27/20	HC	AAL	25	30.45	S	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.010 U	–	–	–
MBB-3	MBB-3-5	02/27/20	HC	AAL	5	49.84	V	0.025 UJ	–	–	–	–	–	–	**0.024 J**	0.010 U	–	–	–
	MBB-3-10	02/27/20	HC	AAL	10	44.84	V	0.25 UJ	–	–	–	–	–	–	0.50 UJ	0.010 U	–	–	–
	MBB-3-15	02/27/20	HC	AAL	15	39.84	V	0.025 U	–	–	–	–	–	–	0.020 UJ	0.010 U	–	–	–
	MBB-3-20	02/27/20	HC	AAL	20	34.84	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.010 U	–	–	–
	MBB-3-25	02/27/20	HC	AAL	25	29.84	S	0.025 UJ	–	–	–	–	–	–	0.020 UJ	**0.092**	–	–	–
MBB-4	MBB-4-5	02/27/20	HC	AAL	5	49.61	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.010 U	–	–	–
	MBB-4-10	02/27/20	HC	AAL	10	44.61	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	**0.011**	–	–	–
	MBB-4-10a	02/27/20	HC	AAL	10 (dup)	44.61	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.010 U	–	–	–
	MBB-4-15	02/27/20	HC	AAL	15	39.61	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.010 U	–	–	–
	MBB-4-20	02/27/20	HC	AAL	20	34.61	V	0.25 UJ	–	–	–	–	–	–	0.50 UJ	**0.74**	–	–	–
	MBB-4-25	02/27/20	HC	AAL	25	29.61	S	0.025 UJ	–	–	–	–	–	–	0.020 UJ	0.010 U	–	–	–
MBB-5	MBB-5-5	03/02/20	HC	AAL	5	45.3	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	MBB-5-10	03/02/20	HC	AAL	10	40.3	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	MBB-5-15	03/02/20	HC	AAL	15	35.3	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	MBB-5-20	03/02/20	HC	AAL	20	30.3	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	MBB-5-25	03/02/20	HC	AAL	25	25.3	S	0.025 UJ	–	–	–	–	–	–	**0.021 J**	–	–	–	–
MBB-6	MBB-6-5	03/03/20	HC	AAL	5	45.33	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	MBB-6-10	03/03/20	HC	AAL	10	40.33	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	MBB-6-15	03/03/20	HC	AAL	15	35.33	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	MBB-6-20	03/03/20	HC	AAL	20	30.33	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	MBB-6-25	03/03/20	HC	AAL	25	25.33	S	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
MBB-7	MBB-7-5	02/25/20	HC	AAL	5	44.41	V	0.025 UJ	–	–	–	–	–	–	**0.020 J**	–	–	–	–
	MBB-7-10	02/25/20	HC	AAL	10	39.41	V	0.025 UJ	–	–	–	–	–	–	**0.021 J**	–	–	–	–
	MBB-7-15	02/25/20	HC	AAL	15	34.41	V	0.025 UJ	–	–	–	–	–	–	**0.025 J**	–	–	–	–
	MBB-7-20	02/25/20	HC	AAL	20	29.41	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	MBB-7-25	02/25/20	HC	AAL	25	24.41	S	0.025 UJ	–	–	–	–	–	–	**0.036 J**	–	–	–	–
MBB-8	MBB-8-5	02/26/20	HC	AAL	5	44.66	V	0.025 U	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	MBB-8-10	02/26/20	HC	AAL	10	39.66	V	0.025 U	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	MBB-8-15	02/26/20	HC	AAL	15	34.66	V	0.025 U	–	–	–	–	–	–	**0.030 J**	–	–	–	–
	MBB-8-15 dup	02/26/20	HC	AAL	15 (dup)	34.66	V	0.025 U	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	MBB-8-20	02/26/20	HC	AAL	20	29.66	V	0.025 U	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	MBB-8-25	02/26/20	HC	AAL	25	24.66	S	0.025 U	–	–	–	–	–	–	0.020 UJ	–	–	–	–

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	–	–	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	–	–	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
MBB-9	MBB-9-5	02/26/20	HC	AAL	5	42.55	V	0.025 U	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	MBB-9-10	02/26/20	HC	AAL	10	37.55	V	0.025 U	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	MBB-9-15	02/26/20	HC	AAL	15	32.55	V	0.025 U	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	MBB-9-20	02/26/20	HC	AAL	20	27.55	V	0.025 UJ	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	MBB-9-25	02/26/20	HC	AAL	25	22.55	S	0.025 U	–	–	–	–	–	–	0.020 UJ	–	–	–	–
MBB-10	MBB-10-5	02/26/20	HC	AAL	5	44.66	V	0.025 U	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	MBB-10-10	02/26/20	HC	AAL	10	39.66	V	0.025 U	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	MBB-10-15	02/26/20	HC	AAL	15	34.66	V	0.025 U	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	MBB-10-20	02/26/20	HC	AAL	20	29.66	V	0.025 U	–	–	–	–	–	–	0.020 UJ	–	–	–	–
	MBB-10-25	02/26/20	HC	AAL	25	24.66	S	0.025 U	–	–	–	–	–	–	0.020 UJ	–	–	–	–
MBB-14	MBB-14-5	03/03/20	HC	AAL	5	42.15	V	–	–	–	–	–	–	–	–	0.050 U	–	–	–
	MBB-14-10	03/03/20	HC	AAL	10	37.15	V	–	–	–	–	–	–	–	–	**0.028**	–	–	–
	MBB-14-15	03/03/20	HC	AAL	15	32.15	V	–	–	–	–	–	–	–	–	0.010 U	–	–	–
	MBB-14-20	03/03/20	HC	AAL	20	27.15	V	–	–	–	–	–	–	–	–	0.010 U	–	–	–
	MBB-14-25	03/03/20	HC	AAL	25	22.15	V	–	–	–	–	–	–	–	–	0.010 U	–	–	–
MBB-15	MBB-15-5	03/04/20	HC	AAL	5	32.73	V	–	–	–	–	–	–	–	–	0.010 U	–	–	–
	MBB-15-10	03/04/20	HC	AAL	10	27.73	V	–	–	–	–	–	–	–	–	0.010 U	–	–	–
	MBB-15-15	03/04/20	HC	AAL	15	22.73	V	–	–	–	–	–	–	–	–	0.010 U	–	–	–
	MBB-15-20	03/04/20	HC	AAL	20	17.73	S	–	–	–	–	–	–	–	–	0.010 U	–	–	–
	MBB-15-25	03/04/20	HC	AAL	25	12.73	S	–	–	–	–	–	–	–	–	0.010 U	–	–	–
MBB-16	MBB16-5	09/02/20	HC	F&BI	5	48.7	V	0.025 U	0.25 U	–	–	**0.55**	0.050 U	0.0050 U	**0.043**	**1.9**	–	**1.2**	**0.42**
	MBB16-10	09/02/20	HC	F&BI	10	43.7	V	0.025 U	0.25 U	–	–	**0.075**	0.050 U	0.0050 U	**0.032**	**0.22**	–	**0.17**	0.0050 U
	MBB16-15	09/02/20	HC	F&BI	15	38.7	V	0.025 U	0.025 U	–	–	**0.0062**	0.050 U	0.0050 U	**0.039**	**0.024**	–	**0.010**	0.0050 U
	MBB16-20	09/02/20	HC	F&BI	20	33.7	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.049**	**0.0057**	–	0.0050 U	0.0050 U
MBB-17	MBB17-5	09/01/20	HC	F&BI	5	49.88	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	0.0078 U	0.0050 U	–	0.0050 U	0.0050 U
	MBB17-10	09/01/20	HC	F&BI	10	44.88	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	0.0078 U	0.0050 U	–	0.0050 U	0.0050 U
	MBB17-15	09/01/20	HC	F&BI	15	39.88	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	0.0078 U	0.0050 U	–	0.0050 U	0.0050 U
	MBB17-25	09/01/20	HC	F&BI	25	29.88	S	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	0.0078 U	0.0050 U	–	0.0050 U	0.0050 U
MBB-18	MBB18-5	09/01/20	HC	F&BI	5	46.33	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	0.0078 U	**0.0062**	–	0.0050 U	0.0050 U
	MBB18-10	09/01/20	HC	F&BI	10	41.33	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.12 J**	0.0050 U	–	0.0050 U	0.0050 U
	MBB18-15	09/01/20	HC	F&BI	15	36.33	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	0.0078 U	0.0050 U	–	0.0050 U	0.0050 U
	MBB18-20	09/01/20	HC	F&BI	20	31.33	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	0.0078 U	0.0050 U	–	0.0050 U	0.0050 U
MBB-19	MBB19-5	09/01/20	HC	F&BI	5	46.68	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	0.0078 U	0.0050 U	–	0.0050 U	0.0050 U
	MBB19-10	09/01/20	HC	F&BI	10	41.68	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	0.0078 U	0.0050 U	–	0.0050 U	0.0050 U
	MBB19-15	09/01/20	HC	F&BI	15	36.68	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.022 J**	0.0050 U	–	0.0050 U	0.0050 U
	MBB19-20	09/01/20	HC	F&BI	20	31.68	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.022 J**	0.0050 U	–	0.0050 U	0.0050 U
MBB-20	MBB20-5	09/02/20	HC	F&BI	5	42.53	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.067**	0.0050 U	–	0.0050 U	0.0050 U
	MBB20-10	09/02/20	HC	F&BI	10	37.53	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.12**	0.0050 U	–	0.0050 U	0.0050 U
	MBB20-15	09/02/20	HC	F&BI	15	32.53	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.096**	0.0050 U	–	0.0050 U	0.0050 U
	MBB20-20	09/02/20	HC	F&BI	20	27.53	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	0.0078 U	0.0050 U	–	0.0050 U	0.0050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	–	–	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	–	–	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
MBB-21	MBB21-5	09/02/20	HC	F&BI	5	42.6	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.057**	0.0050 U	–	0.0050 U	0.0050 U
	MBB21-10	09/02/20	HC	F&BI	10	37.6	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.084**	0.0050 U	–	0.0050 U	0.0050 U
	MBB21-15	09/02/20	HC	F&BI	15	32.6	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.080**	0.0050 U	–	0.0050 U	0.0050 U
	MBB21-20	09/02/20	HC	F&BI	20	27.6	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.062**	0.0050 U	–	0.0050 U	0.0050 U
MBB-22	MBB-22-5	09/21/20	HC	F&BI	5	37.05	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	0.0078 UJ	0.0050 U	–	0.0050 U	0.0050 U
	MBB-22-15	09/21/20	HC	F&BI	15	27.05	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	0.0078 UJ	0.0050 U	–	0.0050 U	0.0050 U
	MBB-22-20	09/21/20	HC	F&BI	20	22.05	S	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	0.0078 UJ	0.0050 U	–	0.0050 U	0.0050 U
	MBB-22-25	09/21/20	HC	F&BI	25	17.05	S	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.067 J**	0.0050 U	–	0.0050 U	0.0050 U
	MBB-22-30	09/21/20	HC	F&BI	30	12.05	S	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	0.0078 UJ	0.0050 U	–	0.0050 U	0.0050 U
MBB-23	MBB-23-5	09/21/20	HC	F&BI	5	42.18	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.0096 J**	0.0050 U	–	0.0050 U	0.0050 U
	MBB-23-10	09/21/20	HC	F&BI	10	37.18	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.013 J**	**0.019**	–	0.0050 U	0.0050 U
	MBB-23-15	09/21/20	HC	F&BI	15	32.18	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	0.0078 UJ	0.0050 U	–	0.0050 U	0.0050 U
	MBB-23-20	09/21/20	HC	F&BI	20	27.18	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.029 J**	0.0050 U	–	0.0050 U	0.0050 U
	MBB-23-25	09/21/20	HC	F&BI	25	22.18	S	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	0.0078 UJ	0.0050 U	–	0.0050 U	0.0050 U
	MBB-23-30	09/21/20	HC	F&BI	30	17.18	S	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.078 J**	0.0050 U	–	0.0050 U	0.0050 U
MBB-24	MMB24-5	09/09/20	HC	F&BI	5	49.1	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.030 J**	0.0050 U	–	0.0050 U	0.0050 U
	MMB24-10	09/09/20	HC	F&BI	10	44.1	V	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	**0.011 J**	0.0050 U	–	0.0050 U	0.0050 U
	MMB24-15	09/09/20	HC	F&BI	15	39.1	V	0.025 U	0.025 UJ	–	–	0.0050 U	0.050 U	0.0050 U	0.0078 UJ	0.0050 U	–	0.0050 U	0.0050 U
	MMB24-20	09/09/20	HC	F&BI	20	34.1	V	0.025 U	0.025 UJ	–	–	0.0050 U	0.050 U	0.0050 U	0.0078 UJ	0.0050 U	–	0.0050 U	0.0050 U
	MMB24-25	09/09/20	HC	F&BI	25	29.1	S	0.025 U	0.025 UJ	–	–	0.0050 U	0.050 U	0.0050 U	0.0078 UJ	0.0050 U	–	0.0050 U	0.0050 U
	MMB24-30	09/09/20	HC	F&BI	30	24.1	S	0.025 U	0.025 U	–	–	0.0050 U	0.050 U	0.0050 U	0.0078 U	0.0050 U	–	0.0050 U	0.0050 U
MBGW-1	MBGW1-5	03/06/19	HC	AAL	5	34.95	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW1-12.5	03/06/19	HC	AAL	12.5	27.45	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW1-17.5	03/06/19	HC	AAL	17.5	22.45	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW1-25	03/06/19	HC	AAL	25	14.95	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	1.0 U	0.050 U	0.050 U	0.050 U
	MBGW1-30	03/06/19	HC	AAL	30	9.95	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-2	MBGW2-5	03/04/19	HC	AAL	5	41.11	V	–	–	–	–	–	–	–	–	–	–	–	–
	MBGW2-10	03/04/19	HC	AAL	10	36.11	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW2-12.5	03/04/19	HC	AAL	12.5	33.61	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW2-25	03/04/19	HC	AAL	25	21.11	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	1.0 U	0.050 U	0.050 U	0.050 U
	MBGW2-30	03/04/19	HC	AAL	30	16.11	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	1.0 U	0.050 U	0.050 U	0.050 U
MBGW-3	MBGW3-5	03/07/19	HC	AAL	5	42.77	V	–	–	–	–	–	–	–	–	–	–	–	–
	MBGW3-7.5	03/07/19	HC	AAL	7.5	40.27	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW3-10	03/07/19	HC	AAL	10	37.77	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW3-12.5	03/07/19	HC	AAL	12.5	35.27	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	–	0.050 U	0.050 U	0.050 U
	MBGW3-25	03/07/19	HC	AAL	25	22.77	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW3-26	03/07/19	HC	AAL	26	21.77	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	1.0 U	0.050 U	0.050 U	0.050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
MBGW-4	MBGW4-5	03/06/19	HC	AAL	5	42.3	V	–	–	–	–	–	–	–	–	–	–	–	–
	MBGW4-7.5	03/06/19	HC	AAL	7.5	39.8	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW4-10	03/06/19	HC	AAL	10	37.3	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW4-12.5	03/06/19	HC	AAL	12.5	34.8	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW4-25	03/06/19	HC	AAL	25	22.3	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-5	MBGW5-10	03/11/19	HC	AAL	10	39.87	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW5-15	03/11/19	HC	AAL	15	34.87	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW5-20	03/11/19	HC	AAL	20	29.87	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW5-27.5	03/11/19	HC	AAL	27.5	22.37	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW5-45	03/11/19	HC	AAL	45	4.87	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-6	MBGW6-10	03/14/19	HC	AAL	10	42.5	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW6-15	03/14/19	HC	AAL	15	37.5	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW6-20	03/14/19	HC	AAL	20	32.5	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW6-30	03/14/19	HC	AAL	30	22.5	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-7	MBGW7-30	03/06/19	HC	AAL	30	23.76	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-8	MBGW8-10	03/15/19	HC	AAL	10	37.08	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW8-15	03/15/19	HC	AAL	15	32.08	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW8-25	03/15/19	HC	AAL	25	22.08	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW8-35	03/15/19	HC	AAL	35	12.08	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-9	MBGW9-10	03/13/19	HC	AAL	10	46.84	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW9-15	03/13/19	HC	AAL	15	41.84	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW9-20	03/13/19	HC	AAL	20	36.84	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW9-25	03/13/19	HC	AAL	25	31.84	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW9-30	03/13/19	HC	AAL	30	26.84	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-10	MBGW10-10	03/13/19	HC	AAL	10	45.25	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW10-15	03/13/19	HC	AAL	15	40.25	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW10-20	03/13/19	HC	AAL	20	35.25	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW10-25	03/13/19	HC	AAL	25	30.25	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW10-30	03/13/19	HC	AAL	30	25.25	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-11	MBGW11-5	03/12/19	HC	AAL	5	52.55	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW11-10	03/12/19	HC	AAL	10	47.55	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-12	MBGW12-5	03/15/19	HC	AAL	5	49.00	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW12-20	03/15/19	HC	AAL	20	34.00	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW12-25	03/15/19	HC	AAL	25	29.00	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW12-30	03/15/19	HC	AAL	30	24.00	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
MBGW-13	MBGW13-5	03/14/19	HC	AAL	5	49.72	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW13-7.5	03/14/19	HC	AAL	7.5	47.22	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	**0.055 J**	**0.10 J**	0.050 U
	MBGW13-10	03/14/19	HC	AAL	10	44.72	V	0.050 U	–	–	–	**0.97**	–	0.10 U	0.020 U	0.050 U	**2.2**	**3.0**	0.050 U
	MBGW13-12.5	03/14/19	HC	AAL	12.5	42.22	V	0.050 U	–	–	–	**0.085 J**	–	0.10 U	0.020 U	0.050 U	**0.23 J**	**0.25 J**	0.050 U
	MBGW13-15	03/14/19	HC	AAL	15	39.72	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW13-20	03/14/19	HC	AAL	20	34.72	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-14	MBGW14-10	03/06/19	HC	AAL	10	36.09	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW14-15	03/06/19	HC	AAL	15	31.09	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW14-20	03/06/19	HC	AAL	20	26.09	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW14-30	03/06/19	HC	AAL	30	16.09	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-16	MBGW16-10	03/08/19	HC	AAL	10	42.14	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW16-15	03/08/19	HC	AAL	15	37.14	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW16-30	03/08/19	HC	AAL	30	22.14	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-1	MBPP1-20	03/05/19	HC	AAL	20	25.28	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP1-25	03/05/19	HC	AAL	25	20.28	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-2	MBPP2-10	03/05/19	HC	AAL	10	34.46	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP2-20	03/05/19	HC	AAL	20	24.46	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP2-27.5	03/05/19	HC	AAL	27.5	16.96	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-3	MBPP3-10	03/06/19	HC	AAL	10	35.89	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP3-20	03/06/19	HC	AAL	20	25.89	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP3-25	03/06/19	HC	AAL	25	20.89	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-4	MBPP4-2.5	03/07/19	HC	AAL	2.5	45.84	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP4-10	03/07/19	HC	AAL	10	38.34	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP4-15	03/07/19	HC	AAL	15	33.34	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP4-17	03/07/19	HC	AAL	17	31.34	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP4-18	03/07/19	HC	AAL	18	30.34	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-5	MBPP5-10	03/07/19	HC	AAL	10	35.92	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP5-15	03/07/19	HC	AAL	15	30.92	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP5-17.5	03/07/19	HC	AAL	17.5	28.42	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP5-20	03/07/19	HC	AAL	20	25.92	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP5-25	03/07/19	HC	AAL	25	20.92	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-6	MBPP6-7.5	03/08/19	HC	AAL	7.5	44.76	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP6-10	03/08/19	HC	AAL	10	42.26	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP6-12.5	03/08/19	HC	AAL	12.5	39.76	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP6-15	03/08/19	HC	AAL	15	37.26	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	**–**	**–**	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	**–**	**–**	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
MBPP-6	MBPP6-17.5	03/08/19	HC	AAL	17.5	34.76	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
(continued)	MBPP6-20	03/08/19	HC	AAL	20	32.26	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP6-25	03/08/19	HC	AAL	25	27.26	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP6-30	03/08/19	HC	AAL	30	22.26	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-7	MBPP7-5	03/08/19	HC	AAL	5	44.77	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP7-15	03/08/19	HC	AAL	15	34.77	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP7-23	03/08/19	HC	AAL	23	26.77	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-8	MBPP8-10	03/08/19	HC	AAL	10	47.52	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP8-15	03/08/19	HC	AAL	15	42.52	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP8-22.5	03/08/19	HC	AAL	22.5	35.02	V	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP8-30	03/08/19	HC	AAL	30	27.52	S	0.050 U	–	–	–	0.050 U	–	0.10 U	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MW-345	MW-345-41	05/20/21	PES	PACE	41	11.85	S	0.00740 U	0.00279 U	0.00286 U	0.000506 U	0.000524 U	0.00281 U	0.000432 U	0.00819 U	0.00602 U	0.00647 U	0.00117 U	0.00355 U
	MW-345-47	05/20/21	PES	PACE	47	5.85	S	0.00705 U	**0.00549 J**	0.00273 U	0.000482 U	0.000499 U	0.00268 U	0.000411 U	0.00780 U	0.00573 U	0.00617 U	0.00112 U	0.00338 U
	MW-2023-47	05/20/21	PES	PACE	47 (dup)	5.85	S	0.00868 U	0.00327 U	0.00336 U	0.000593 U	0.000615 U	0.00330 U	0.000507 U	0.00960 U	0.00706 U	0.00760 U	0.00138 U	0.00417 U
	MW-345-53	05/20/21	PES	PACE	53	-0.15	S	0.00702 U	0.00264 U	0.00271 U	0.000480 U	0.000497 U	0.00267 U	0.000409 U	0.00777 U	0.00571 U	0.00614 U	0.00111 U	0.00337 U
	MW-345-58	05/20/21	PES	PACE	58	-5.15	S	0.00879 U	**0.0100**	0.00340 U	0.000601 U	0.000623 U	0.00334 U	0.000513 U	0.00972 U	0.00715 U	0.00769 U	0.00140 U	0.00422 U
	MW-345-63	05/20/21	PES	PACE	63	-10.15	S	0.00805 U	0.00303 U	0.00311 U	0.000550 U	0.000570 U	0.00306 U	0.000470 U	0.00891 U	0.00655 U	0.00704 U	0.00127 U	0.00386 U
MW-346	MW-346-41.5	05/19/21	PES	PACE	41.5	10.28	S	0.00728 U	0.00274 U	0.00282 U	0.000498 U	0.000516 U	0.00277 U	0.000425 U	0.00806 U	0.00592 U	0.00637 U	0.00115 U	0.00350 U
	MW-346-47	05/19/21	PES	PACE	47	4.78	S	0.00703 U	**0.00486 J**	0.00272 U	0.000480 U	0.000498 U	0.00267 U	0.000410 U	0.00778 U	0.00572 U	0.00615 U	0.00111 U	0.00337 U
	MW-346-52	05/19/21	PES	PACE	52	-0.22	S	0.00701 U	**0.00447 J**	0.00271 U	0.000479 U	0.000496 U	0.00266 U	0.000409 U	0.00775 U	0.00570 U	0.00613 U	0.00111 U	0.00336 U
	MW-346-54.5	05/19/21	PES	PACE	54.5	-2.72	S	0.0291 U	**0.0244**	0.0113 U	0.00199 U	0.00206 U	0.0111 U	0.00170 U	0.0323 U	0.0236 U	0.0255 U	0.00461 U	0.0139 U
	MW-346-57.5	05/19/21	PES	PACE	57.5	-5.72	S	0.00701 U	0.00264 U	0.00271 U	0.000479 U	0.000497 U	0.00266 U	0.000409 U	0.00776 U	0.00570 U	0.00614 U	0.00111 U	0.00337 U
	MW-346-62	05/19/21	PES	PACE	62	-10.22	S	0.00767 U	0.00289 U	0.00297 U	0.000524 U	0.000543 U	0.00291 U	0.000447 U	0.00849 U	0.00624 U	0.00671 U	0.00121 U	0.00368 U
MW-347	MW-347-44.5	05/19/21	PES	PACE	44.5	8.29	S	0.00843 U	0.00317 U	0.00326 U	0.000576 U	0.000597 U	0.00320 U	0.000492 U	0.00933 U	0.00685 U	0.00737 U	0.00133 U	0.00404 U
	MW-2022-44.5	05/19/21	PES	PACE	44.5 (dup)	8.29	S	0.00783 U	0.00295 U	0.00303 U	0.000535 U	0.000555 U	0.00298 U	0.000457 U	0.00867 U	0.00637 U	0.00685 U	0.00124 U	0.00376 U
	MW-347-48	05/19/21	PES	PACE	48	4.79	S	0.00701 U	0.00264 U	0.00271 U	0.000479 U	0.000497 U	0.00266 U	0.000409 U	0.00776 U	0.00570 U	0.00613 U	0.00111 U	0.00337 U
	MW-347-54.5	05/19/21	PES	PACE	54.5	-1.71	S	0.00723 U	0.00272 U	0.00280 U	0.000494 U	0.000512 U	0.00275 U	0.000422 U	0.00800 U	0.00588 U	0.00633 U	0.00114 U	0.00347 U
	MW-347-58	05/19/21	PES	PACE	58	-5.21	S	0.00714 U	**0.0112**	0.00276 U	0.000488 U	0.000506 U	0.00271 U	0.000417 U	0.00790 U	0.00581 U	0.00625 U	0.00113 U	0.00343 U
	MW-347-65	05/19/21	PES	PACE	65	-12.21	S	0.00763 U	0.00287 U	0.00295 U	0.000521 U	0.000540 U	0.00290 U	0.000445 U	0.00844 U	0.00620 U	0.00667 U	0.00121 U	0.00366 U
MW-348	MW-348-41	05/18/21	PES	PACE	41	12.96	S	0.00771 U	0.00290 U	0.00298 U	0.000527 U	0.000546 U	0.00293 U	0.000450 U	0.00853 U	0.00627 U	0.00675 U	0.00122 U	0.00370 U
	MW-348-49	05/18/21	PES	PACE	49	4.96	S	0.00772 U	0.00291 U	0.00299 U	0.000528 U	0.000547 U	0.00293 U	0.000450 U	0.00854 U	0.00628 U	0.00676 U	0.00122 U	0.00371 U
	MW-348-54.5	05/18/21	PES	PACE	54.5	-0.54	S	0.00694 U	0.00262 U	0.00268 U	0.000474 U	0.000492 U	0.00264 U	0.000405 U	0.00768 U	0.00565 U	0.00608 U	0.00110 U	0.00333 U
	MW-348-60	05/18/21	PES	PACE	60	-6.04	S	0.00691 U	0.00260 U	0.00267 U	0.000472 U	0.000490 U	0.00263 U	0.000403 U	0.00765 U	0.00562 U	0.00605 U	0.00109 U	0.00332 U
	MW-348-65	05/18/21	PES	PACE	65	-11.04	S	0.00750 U	0.00282 U	0.00290 U	0.000512 U	0.000531 U	0.00285 U	0.000437 U	0.00830 U	0.00610 U	0.00656 U	0.00119 U	0.00360 U
	MW-348-69	05/18/21	PES	PACE	69	-15.04	S	0.00734 U	0.00276 U	0.00284 U	0.000501 U	0.000520 U	0.00279 U	0.000428 U	0.00812 U	0.00597 U	0.00642 U	0.00116 U	0.00352 U
MW-349	MW-349-49	05/17/21	PES	PACE	49	6.84	S	0.00768 U	0.00289 U	0.00297 U	0.000525 U	0.000544 U	0.00292 U	0.000448 U	0.00850 U	0.00625 U	0.00672 U	0.00122 U	0.00369 U
	MW-349-51	05/17/21	PES	PACE	51	4.84	S	0.00716 U	0.00270 U	0.00277 U	0.000489 U	0.000507 U	0.00272 U	0.000418 U	0.00792 U	0.00582 U	0.00626 U	0.00113 U	0.00344 U
	MW-349-56	05/17/21	PES	PACE	56	-0.16	S	0.00714 U	0.00269 U	0.00276 U	0.000488 U	0.000506 U	0.00271 U	0.000417 U	0.00791 U	0.00581 U	0.00625 U	0.00113 U	0.00343 U
	MW-349-61	05/17/21	PES	PACE	61	-5.16	S	0.00731 U	0.00275 U	0.00283 U	0.000500 U	0.000518 U	0.00278 U	0.000426 U	0.00809 U	0.00595 U	0.00640 U	0.00116 U	0.00351 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Hexachlorobutadiene	Hexane (n-Hexane)	Iodomethane (Methyl Iodide)	Isopropyl ether (di-Isopropyl ether)	Isopropylbenzene (Cumene)	Methyl isobutyl ketone (4-Methyl-2-pentanone/ MIBK)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene	Sec-Butylbenzene
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**0.6**	**72**	–	–	**15**	**2.7**	**0.1**	**0.040**	**4.5**	**14**	**16**	**25**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.03**	**1.8**	–	–	**0.79**	**0.19**	**0.0072**	**0.040**	**0.24**	**0.71**	**0.88**	**1.3**
MW-349	MW-349-66	05/17/21	PES	PACE	66	-10.16	S	0.00731 U	0.00275 U	0.00283 U	0.000500 U	0.000518 U	0.00278 U	0.000427 U	0.00809 U	0.00595 U	0.00640 U	0.00116 U	0.00351 U
(continued)	MW-349-68	05/17/21	PES	PACE	68	-12.16	S	0.00753 U	0.00284 U	0.00291 U	0.000514 U	0.000533 U	0.00286 U	0.000439 U	0.00833 U	0.00612 U	0.00659 U	0.00119 U	0.00361 U
MW-350	MW-350-41	05/21/21	PES	PACE	41	16.77	S	0.00774 U	**2.77**	0.00299 U	0.000529 U	**0.199**	0.00294 U	0.000452 U	0.00857 U	**0.408**	**0.185**	**0.346**	**0.0648**
	MW-350-53	05/21/21	PES	PACE	53	4.77	S	0.00708 U	**0.0162**	0.00274 U	0.000484 U	**0.00104 J**	0.00269 U	0.000413 U	0.00784 U	**0.0229**	0.00620 U	**0.00392 J**	0.00340 U
	MW-350-58	05/21/21	PES	PACE	58	-0.23	S	0.00702 U	0.00265 U	0.00272 U	0.000480 U	0.000498 U	0.00267 U	0.000410 U	0.00777 U	0.00571 U	0.00615 U	0.00111 U	0.00337 U
	MW-350-64.5	05/21/21	PES	PACE	64.5	-6.73	S	0.00737 U	0.00278 U	0.00285 U	0.000504 U	0.000522 U	0.00280 U	0.000430 U	0.00816 U	0.00599 U	0.00645 U	0.00117 U	0.00354 U
	MW-350-69	05/21/21	PES	PACE	69	-11.23	S	0.00761 U	**0.0214**	0.00294 U	0.000520 U	**0.00155 J**	0.00289 U	0.000444 U	0.00842 U	**0.00883 J**	0.00666 U	**0.00487 J**	0.00365 U
All Data	Number of Analytes Measured							397	97	33	33	256	97	256	397	321	192	256	256
	Number of Analytes Detected							0	9	0	0	11	0	0	59	16	7	14	6
	Frequency of Detection							0.0%	9.3%	0.0%	0.0%	4.3%	0.0%	0.0%	14.9%	5.0%	3.6%	5.5%	2.3%
	Maximum Detection							–	2.77	–	–	1.5	–	–	0.21 J	1.9	2.2	3.2	1.9
	Minimum Detection							0.00691 U	0.0026 U	0.00267 U	0.00047 U	0.00049 U	0.00263 U	0.0004 U	0.00765 U	0.005 U	0.00605 U	0.00109 U	0.00332 U
	Number Of Vadose (V) Detections above SL							0	0	–	–	0	0	0	11	0	0	0	0
	Number of Saturated (S) Detections above SL							0	1	–	–	1	0	0	2	1	1	1	1
2017-2021	Number of Analytes Measured							397	97	33	33	256	97	256	397	321	192	256	256
	Number of Analytes Detected							0	9	0	0	11	0	0	59	16	7	14	6
	Frequency of Detection							0.0%	9.3%	0.0%	0.0%	4.3%	0.0%	0.0%	14.9%	5.0%	3.6%	5.5%	2.3%
	Maximum Detection							–	2.77	–	–	1.5	–	–	0.21 J	1.9	2.2	3.2	1.9
	Minimum Detection							0.00691 U	0.0026 U	0.00267 U	0.00047 U	0.00049 U	0.00263 U	0.0004 U	0.00765 U	0.005 U	0.00605 U	0.00109 U	0.00332 U
	Number Of Vadose (V) Detections above SL							0	0	–	–	0	0	0	11	0	0	0	0
	Number of Saturated (S) Detections above SL							0	1	–	–	1	0	0	2	1	1	1	1

Notes and Abbreviations:
Petroleum Hydrocarbons (PHCs) analyzed by Ecology Methods NWTPH-Gx and NWTPH-Dx.
VOCs analyzed by EPA Method 8260 C/D.
PCUL = Preliminary Cleanup Level from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021. PCULs based on the practical quantitation limits (PQLs) italicized. Detected results shown in bold.
Detections above the screening level in the vadose zone are shown in **bold and highlighted blue.**
Detections above the screening level in the saturated zone are shown in **bold and highlighted gray.**
– = Not available or results not analyzed.
J = The reported concentration is an estimate based on detectable results between the method detection limit and reporting limit, laboratory QA/QC, or data validation review.
J+ = The result is an estimated quantity, but the result may be biased high.
J- = The result is an estimated quantity, but the result may be biased low.
U = Not detected at a concentration exceeding laboratory reporting limit
z = Gasoline/petroleum detection result is likely elevated due to high detections of CVOCs.
AAL = Alden Analytical Laboratories, Inc., of Seattle, Washington
bgs = below ground surface
dup = duplicate
F&BI = Friedman & Bruya, Inc.
HC = Hart Crowser, Inc.
Pace = Pace Analytical of Mt. Juliet, Tennessee (formerly ESC)
PES = PES Environmental, Inc.

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
615 Dexter Avenue																			
DGW-1	DGW1-10	03/06/19	HC	AAL	10	37	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW1-12.5	03/06/19	HC	AAL	12.5	34.5	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW1-15	03/06/19	HC	AAL	15	32	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW1-25	03/06/19	HC	AAL	25	22	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW1-30	03/06/19	HC	AAL	30	17	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
DGW-2	DGW2-5	03/04/19	HC	AAL	5	54	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW2-10	03/04/19	HC	AAL	10	49	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW2-25	03/04/19	HC	AAL	25	34	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW2-30	03/04/19	HC	AAL	30	29	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
DGW-3	DGW3-2.5	03/06/19	HC	AAL	2.5	44.5	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW3-12.5	03/06/19	HC	AAL	12.5	34.5	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW3-15	03/06/19	HC	AAL	15	32	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW3-20	03/06/19	HC	AAL	20	27	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW3-25	03/06/19	HC	AAL	25	22	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
DGW-4	DGW4-5	03/04/19	HC	AAL	5	60	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW4-10	03/04/19	HC	AAL	10	55	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW4-15	03/04/19	HC	AAL	15	50	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW4-20	03/04/19	HC	AAL	20	45	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW4-35	03/04/19	HC	AAL	35	30	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DGW4-50	03/04/19	HC	AAL	50	15	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
DMW-1S	DMW1S-5	03/05/19	HC	AAL	5	42	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DMW1S-10	03/05/19	HC	AAL	10	37	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	**0.071**
	DMW1S-12.5	03/05/19	HC	AAL	12.5	34.5	S	0.050 U	**0.105**	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	**4.4**
	DMW1S-15	03/05/19	HC	AAL	15	32	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	**0.20**
	DMW1S-20	03/05/19	HC	AAL	20	27	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
DMW-2S	DMW-2S-05	03/02/20	HC	AAL	5	51.03	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	DMW-2S-10	03/02/20	HC	AAL	10	46.03	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	DMW-2S-15	03/02/20	HC	AAL	15	41.03	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	DMW-2S-20	03/02/20	HC	AAL	20	36.03	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	DMW-2S-25	03/02/20	HC	AAL	25	31.03	S	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
DMW-3IA	DMW-3IA-5	02/27/20	HC	AAL	5	51.09	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	DMW-3IA-10	02/27/20	HC	AAL	10	46.09	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	DMW-3IA-15	02/27/20	HC	AAL	15	41.09	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	DMW-3IA-20	02/27/20	HC	AAL	20	36.09	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	DMW-3IA-25	02/27/20	HC	AAL	25	31.09	S	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
DMW-4S	DMW-4S-5	02/26/20	HC	AAL	5	56.76	V	–	–	0.025 U	0.020 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.060 U
	DMW-4S-10	02/26/20	HC	AAL	10	51.76	V	–	–	0.025 U	0.020 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.060 U
	DMW-4S-15	02/26/20	HC	AAL	15	46.76	V	–	–	0.025 U	0.020 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.060 U
	DMW-4S-20	02/26/20	HC	AAL	20	41.76	V	–	–	0.025 U	0.020 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.060 U
	DMW-4S-25	02/26/20	HC	AAL	25	36.76	S	–	–	0.025 U	**0.046**	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	**0.25**
	DMW-4S-30	02/26/20	HC	AAL	30	31.76	S	–	–	0.025 U	0.020 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.060 U
DMW-5IA	DMW-5IA-5	02/28/20	HC	AAL	5	64.48	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	DMW-5IA-10	02/28/20	HC	AAL	10	59.48	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	DMW-5IA-15	02/28/20	HC	AAL	15	54.48	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	DMW-5IA-20	02/28/20	HC	AAL	20	49.48	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	DMW-5IA-25	02/28/20	HC	AAL	25	44.48	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
DPP-1	DPP1-5	03/04/19	HC	AAL	5	54.5	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP1-7.5	03/05/19	HC	AAL	7.5	52	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP1-10	03/04/19	HC	AAL	10	49.5	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP1-20	03/04/19	HC	AAL	20	39.5	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
DPP-2	DPP2-5	03/04/19	HC	AAL	5	54	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP2-10	03/04/19	HC	AAL	10	49	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
DPP-3	DPP3-5	03/05/19	HC	AAL	5	42	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP3-15	03/05/19	HC	AAL	15	32	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP3-30	03/05/19	HC	AAL	30	17	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
DPP-4	DPP4-10	03/04/19	HC	AAL	10	49	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP4-12.5	03/04/19	HC	AAL	12.5	46.5	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP4-17.5	03/04/19	HC	AAL	17.5	41.5	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP4-20	03/04/19	HC	AAL	20	39	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
DPP-5	DPP5-10	03/04/19	HC	AAL	10	49	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP5-17.5	03/04/19	HC	AAL	17.5	41.5	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP5-20	03/04/19	HC	AAL	20	39	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
DPP-6	DPP6-5	03/05/19	HC	AAL	5	42	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP6-7.5	03/05/19	HC	AAL	7.5	39.5	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP6-12.5	03/05/19	HC	AAL	12.5	34.5	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	DPP6-17.5	03/05/19	HC	AAL	17.5	29.5	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
Seattle DOT Mercer Parcels																			
HMW-1IB	HMW1IB-7.5	03/12/19	HC	AAL	7.5	30.5	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	–	0.050 U	0.050 U
	HMW1IB-15	03/12/19	HC	AAL	15	23	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	–	0.050 U	0.050 U
	HMW1IB-20.5	03/12/19	HC	AAL	20.5	18	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	–	0.050 U	0.050 U
	HMW1IB-27.5	03/12/19	HC	AAL	27.5	10.5	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	–	0.050 U	0.050 U
	HMW1IB-50	03/12/19	HC	AAL	50	-12	S	0.050 U	0.050 U	**0.12 J**	0.050 U	0.050 U	0.050 U	–	**0.024 J**	0.050 U	–	0.050 U	0.050 U
	HMW1IB-65	03/12/19	HC	AAL	65	-27	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	–	0.050 U	0.050 U
HMW-2IB	HMW2IB-7.5	03/12/19	HC	AAL	7.5	39.5	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW2IB-15	03/12/19	HC	AAL	15	32	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW2IB-22.5	03/12/19	HC	AAL	22.5	24.5	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW2IB-30	03/12/19	HC	AAL	30	17	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW2IB-45	03/12/19	HC	AAL	45	2	S	0.050 U	0.050 U	**0.12 J**	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW2IB-65	03/12/19	HC	AAL	65	-18	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
HMW-3IA	HMW3IA-15	03/15/19	HC	AAL	15	40.5	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW3IA-20	03/15/19	HC	AAL	20	35.5	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW3IA-22.5	03/15/19	HC	AAL	22.5	33	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW3IA-25	03/15/19	HC	AAL	25	30.5	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
HMW-4IA	HMW4IA-5	03/07/19	HC	AAL	5	51	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW4IA-7.5	03/07/19	HC	AAL	7.5	48.5	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW4IA-10	03/07/19	HC	AAL	10	46	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	HMW4IA-25	03/07/19	HC	AAL	25	31	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
HMW-5IB	HMW5IB-5	02/28/20	HC	AAL	5	53.44	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW5IB-10	02/28/20	HC	AAL	10	48.44	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW5IB-15	02/28/20	HC	AAL	15	43.44	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW5IB-20	02/28/20	HC	AAL	20	38.44	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW5IB-25	02/28/20	HC	AAL	25	33.44	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
HMW-6D	HMW-6D-5	03/02/20	HC	AAL	5	53.58	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW-6D-10	03/02/20	HC	AAL	10	48.58	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW-6D-15	03/02/20	HC	AAL	15	43.58	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW-6D-25	03/02/20	HC	AAL	25	33.58	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW-6D-30	03/02/20	HC	AAL	30	28.58	S	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW-6D-30-Dup	03/02/20	HC	AAL	30 (dup)	28.58	S	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
HMW-6IA	HMW-6IA-5	03/02/20	HC	AAL	5	53.65	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW-6IA-10	03/02/20	HC	AAL	10	48.65	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW-6IA-15	03/02/20	HC	AAL	15	43.65	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW-6IA-20	03/02/20	HC	AAL	20	38.65	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW-6IA-30	03/02/20	HC	AAL	30	28.65	S	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
HMW-6IB	HMW-6IB-5	03/03/20	HC	AAL	5	53.67	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW-6IB-10	03/03/20	HC	AAL	10	48.67	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW-6IB-10a	03/03/20	HC	AAL	10 (dup)	48.67	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW-6IB-15	03/03/20	HC	AAL	15	43.67	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW-6IB-20	03/03/20	HC	AAL	20	38.67	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW-6IB-25	03/03/20	HC	AAL	25	33.67	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	**–**	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
HMW-7IB	HMW7IB-5	02/28/20	HC	AAL	5	53.69	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW7IB-10	02/28/20	HC	AAL	10	48.69	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW7IB-15	02/28/20	HC	AAL	15	43.69	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW7IB-20	02/28/20	HC	AAL	20	38.69	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW7IB-25	02/28/20	HC	AAL	25	33.69	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW7IB-25a	02/28/20	HC	AAL	25 (dup)	33.69	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
HMW-8IB	HMW-8IB-5	03/02/20	HC	AAL	5	52.97	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW-8IB-10	03/02/20	HC	AAL	10	47.97	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW-8IB-15	03/02/20	HC	AAL	15	42.97	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW-8IB-20	03/02/20	HC	AAL	20	37.97	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW-8IB-25	03/02/20	HC	AAL	25	32.97	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW-8IB-25a	03/02/20	HC	AAL	25 (dup)	32.97	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
HMW-9D	HMW-9D-5	02/27/20	HC	AAL	5	50.32	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW-9D-10	02/27/20	HC	AAL	10	45.32	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW-9D-15	02/27/20	HC	AAL	15	40.32	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW-9D-20	02/27/20	HC	AAL	20	35.32	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW-9D-25	02/27/20	HC	AAL	25	30.32	S	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
HMW-9IA	HMW9IA-5	02/28/20	HC	AAL	5	50.26	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW9IA-10	02/28/20	HC	AAL	10	45.26	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW9IA-15	02/28/20	HC	AAL	15	40.26	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW9IA-20	02/28/20	HC	AAL	20	35.26	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW9IA-25	02/28/20	HC	AAL	25	30.26	S	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
HMW-9IB	HMW9IB-5	02/28/20	HC	AAL	5	50.36	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW9IB-13	02/28/20	HC	AAL	13	42.36	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW9IB-15	02/28/20	HC	AAL	15	40.36	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW9IB-20	02/28/20	HC	AAL	20	35.36	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW9IB-25	02/28/20	HC	AAL	25	30.36	S	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
HMW-9S	HMW-9S-5	03/02/20	HC	AAL	5	50.39	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW-9S-14	03/02/20	HC	AAL	14	41.39	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW-9S-17	03/02/20	HC	AAL	17	38.39	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW-9S-20	03/02/20	HC	AAL	20	35.39	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	HMW-9S-25	03/02/20	HC	AAL	25	30.39	S	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
HMW-10D	HMW-10D-5	03/05/20	HC	F&BI	5	43.16	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-10D-10	03/05/20	HC	F&BI	10	38.16	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-10D-15	03/05/20	HC	F&BI	15	33.16	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-10D-15a	03/05/20	HC	F&BI	15 (dup)	33.16	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-10D-20	03/05/20	HC	F&BI	20	28.16	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-10D-25	03/05/20	HC	F&BI	25	23.16	S	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	–	0.0050 U	0.010 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	**–**	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
HMW-10S	HMW10S-5	03/03/20	HC	F&BI	5	43.21	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-10S-10	03/03/20	HC	F&BI	10	38.21	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-10S-10a	03/03/20	HC	F&BI	10 (dup)	38.21	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-10S-15	03/03/20	HC	F&BI	15	33.21	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-10S-20	03/03/20	HC	F&BI	20	28.21	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-10S-25	03/03/20	HC	F&BI	25	23.21	S	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
HMW-11IB	HMW-11IB-5	02/24/20	HC	F&BI	5	34.7	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-11IB-10	02/24/20	HC	F&BI	10	29.7	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-11IB-15	02/24/20	HC	F&BI	15	24.7	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-11IB-20	02/24/20	HC	F&BI	20	19.7	S	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-11IB-25	02/24/20	HC	F&BI	25	14.7	S	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
HMW-11S	HMW-11S-5	02/25/20	HC	F&BI	5	36.47	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-11S-10	02/25/20	HC	F&BI	10	31.47	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-11S-15	02/25/20	HC	F&BI	15	26.47	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-11S-20	02/25/20	HC	F&BI	20	21.47	S	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-11S-30	02/25/20	HC	F&BI	30	11.47	S	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
HMW-17S	HMW-17S-5	09/03/20	HC	F&BI	5	52.21	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-17S-10	09/03/20	HC	F&BI	10	47.21	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-17S-15	09/03/20	HC	F&BI	15	42.21	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-17S-20	09/03/20	HC	F&BI	20	37.21	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-17S-25	09/03/20	HC	F&BI	25	32.21	S	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
HMW-18S	HMW-18S-5	09/03/20	HC	F&BI	5	52.61	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-18S-10	09/03/20	HC	F&BI	10	47.61	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-18S-15	09/03/20	HC	F&BI	15	42.61	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-18S-20	09/03/20	HC	F&BI	20	37.61	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-18S-25	09/03/20	HC	F&BI	25	32.61	S	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-18S-30	09/03/20	HC	F&BI	30	27.61	S	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
HMW-19S	HMW-19S-5	09/08/20	HC	F&BI	5	53.2	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-19S-10	09/08/20	HC	F&BI	10	48.2	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-19S-15	09/08/20	HC	F&BI	15	43.2	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-19S-20	09/08/20	HC	F&BI	20	38.2	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-19S-26	09/08/20	HC	F&BI	26	32.2	S	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-19S-30	09/08/20	HC	F&BI	30	28.2	S	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	**0.044**
HMW-20S	HMW-20S-5	09/08/20	HC	F&BI	5	48.81	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-20S-10	09/08/20	HC	F&BI	10	43.81	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-20S-15	09/08/20	HC	F&BI	15	38.81	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-20S-20	09/08/20	HC	F&BI	20	33.81	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-20S-25	09/08/20	HC	F&BI	25	28.81	S	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	HMW-20S-30	09/08/20	HC	F&BI	30	23.81	S	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
MBB-1	MBB-1-5	02/27/20	HC	AAL	5	50.02	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-1-10	02/27/20	HC	AAL	10	45.02	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-1-15	02/27/20	HC	AAL	15	40.02	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-1-20	02/27/20	HC	AAL	20	35.02	V	–	–	0.025 U	0.050 U	0.050 U	–	–	0.020 U	0.50 U	0.050 U	0.050 U	**0.34**
	MBB-1-25	02/27/20	HC	AAL	25	30.02	S	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.0050 U
MBB-2	MBB-2-5	02/27/20	HC	AAL	5	50.45	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	MBB-2-10	02/27/20	HC	AAL	10	45.45	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	MBB-2-15	02/27/20	HC	AAL	15	40.45	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	MBB-2-20	02/27/20	HC	AAL	20	35.45	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	MBB-2-20a	02/27/20	HC	AAL	20 (dup)	35.45	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	MBB-2-25	02/27/20	HC	AAL	25	30.45	S	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
MBB-3	MBB-3-5	02/27/20	HC	AAL	5	49.84	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-3-10	02/27/20	HC	AAL	10	44.84	V	–	–	0.025 U	**0.093**	0.050 U	–	–	0.020 U	0.50 U	0.050 U	0.050 U	**3.0 J**
	MBB-3-15	02/27/20	HC	AAL	15	39.84	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-3-20	02/27/20	HC	AAL	20	34.84	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.0050 U
	MBB-3-25	02/27/20	HC	AAL	25	29.84	S	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	**0.045**
MBB-4	MBB-4-5	02/27/20	HC	AAL	5	49.61	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	MBB-4-10	02/27/20	HC	AAL	10	44.61	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	**0.0183**
	MBB-4-10a	02/27/20	HC	AAL	10 (dup)	44.61	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	**0.050**
	MBB-4-15	02/27/20	HC	AAL	15	39.61	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	MBB-4-20	02/27/20	HC	AAL	20	34.61	V	–	–	0.025 U	0.050 UJ	0.050 U	–	–	0.020 U	0.50 U	0.050 U	0.050 U	**0.69 J**
	MBB-4-25	02/27/20	HC	AAL	25	29.61	S	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
MBB-5	MBB-5-5	03/02/20	HC	AAL	5	45.3	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	MBB-5-10	03/02/20	HC	AAL	10	40.3	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	MBB-5-15	03/02/20	HC	AAL	15	35.3	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	MBB-5-20	03/02/20	HC	AAL	20	30.3	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	MBB-5-25	03/02/20	HC	AAL	25	25.3	S	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
MBB-6	MBB-6-5	03/03/20	HC	AAL	5	45.33	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	MBB-6-10	03/03/20	HC	AAL	10	40.33	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	MBB-6-15	03/03/20	HC	AAL	15	35.33	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	MBB-6-20	03/03/20	HC	AAL	20	30.33	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	MBB-6-25	03/03/20	HC	AAL	25	25.33	S	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
MBB-7	MBB-7-5	02/25/20	HC	AAL	5	44.41	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	MBB-7-10	02/25/20	HC	AAL	10	39.41	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	MBB-7-15	02/25/20	HC	AAL	15	34.41	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	MBB-7-20	02/25/20	HC	AAL	20	29.41	V	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
	MBB-7-25	02/25/20	HC	AAL	25	24.41	S	–	–	0.025 U	0.0050 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.010 U
MBB-8	MBB-8-5	02/26/20	HC	AAL	5	44.66	V	–	–	0.025 U	0.020 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.060 U
	MBB-8-10	02/26/20	HC	AAL	10	39.66	V	–	–	0.025 U	0.020 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.060 U
	MBB-8-15	02/26/20	HC	AAL	15	34.66	V	–	–	0.025 U	0.020 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.060 U
	MBB-8-15 dup	02/26/20	HC	AAL	15 (dup)	34.66	V	–	–	0.025 U	0.020 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.060 U
	MBB-8-20	02/26/20	HC	AAL	20	29.66	V	–	–	0.025 U	0.020 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.060 U
	MBB-8-25	02/26/20	HC	AAL	25	24.66	S	–	–	0.025 U	0.020 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.060 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	**–**	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
MBB-9	MBB-9-5	02/26/20	HC	AAL	5	42.55	V	–	–	0.025 U	0.020 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.060 U
	MBB-9-10	02/26/20	HC	AAL	10	37.55	V	–	–	0.025 U	0.020 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.060 U
	MBB-9-15	02/26/20	HC	AAL	15	32.55	V	–	–	0.025 U	0.020 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.060 U
	MBB-9-20	02/26/20	HC	AAL	20	27.55	V	–	–	0.025 U	0.020 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.060 U
	MBB-9-25	02/26/20	HC	AAL	25	22.55	S	–	–	0.025 U	0.020 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.060 U
MBB-10	MBB-10-5	02/26/20	HC	AAL	5	44.66	V	–	–	0.025 U	0.020 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.060 U
	MBB-10-10	02/26/20	HC	AAL	10	39.66	V	–	–	0.025 U	0.020 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.060 U
	MBB-10-15	02/26/20	HC	AAL	15	34.66	V	–	–	0.025 U	0.020 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.060 U
	MBB-10-20	02/26/20	HC	AAL	20	29.66	V	–	–	0.025 U	0.020 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.060 U
	MBB-10-25	02/26/20	HC	AAL	25	24.66	S	–	–	0.025 U	0.020 U	0.0010 U	–	–	0.030 U	0.050 U	0.0050 U	0.0050 U	0.060 U
MBB-14	MBB-14-5	03/03/20	HC	AAL	5	42.15	V	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-14-10	03/03/20	HC	AAL	10	37.15	V	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-14-15	03/03/20	HC	AAL	15	32.15	V	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-14-20	03/03/20	HC	AAL	20	27.15	V	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-14-25	03/03/20	HC	AAL	25	22.15	V	–	–	–	–	–	–	–	–	–	–	–	–
MBB-15	MBB-15-5	03/04/20	HC	AAL	5	32.73	V	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-15-10	03/04/20	HC	AAL	10	27.73	V	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-15-15	03/04/20	HC	AAL	15	22.73	V	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-15-20	03/04/20	HC	AAL	20	17.73	S	–	–	–	–	–	–	–	–	–	–	–	–
	MBB-15-25	03/04/20	HC	AAL	25	12.73	S	–	–	–	–	–	–	–	–	–	–	–	–
MBB-16	MBB16-5	09/02/20	HC	F&BI	5	48.7	V	0.0050 U	**0.018**	0.025 U	**0.018**	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	**0.26**
	MBB16-10	09/02/20	HC	F&BI	10	43.7	V	0.0050 U	0.0050 U	0.025 U	**0.032**	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	**0.13**
	MBB16-15	09/02/20	HC	F&BI	15	38.7	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	MBB16-20	09/02/20	HC	F&BI	20	33.7	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
MBB-17	MBB17-5	09/01/20	HC	F&BI	5	49.88	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	MBB17-10	09/01/20	HC	F&BI	10	44.88	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	MBB17-15	09/01/20	HC	F&BI	15	39.88	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	MBB17-25	09/01/20	HC	F&BI	25	29.88	S	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
MBB-18	MBB18-5	09/01/20	HC	F&BI	5	46.33	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	MBB18-10	09/01/20	HC	F&BI	10	41.33	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	MBB18-15	09/01/20	HC	F&BI	15	36.33	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	MBB18-20	09/01/20	HC	F&BI	20	31.33	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
MBB-19	MBB19-5	09/01/20	HC	F&BI	5	46.68	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	MBB19-10	09/01/20	HC	F&BI	10	41.68	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	MBB19-15	09/01/20	HC	F&BI	15	36.68	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	MBB19-20	09/01/20	HC	F&BI	20	31.68	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
MBB-20	MBB20-5	09/02/20	HC	F&BI	5	42.53	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	MBB20-10	09/02/20	HC	F&BI	10	37.53	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	MBB20-15	09/02/20	HC	F&BI	15	32.53	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	MBB20-20	09/02/20	HC	F&BI	20	27.53	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
MBB-21	MBB21-5	09/02/20	HC	F&BI	5	42.6	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	MBB21-10	09/02/20	HC	F&BI	10	37.6	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	MBB21-15	09/02/20	HC	F&BI	15	32.6	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	MBB21-20	09/02/20	HC	F&BI	20	27.6	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
MBB-22	MBB-22-5	09/21/20	HC	F&BI	5	37.05	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	MBB-22-15	09/21/20	HC	F&BI	15	27.05	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	MBB-22-20	09/21/20	HC	F&BI	20	22.05	S	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	MBB-22-25	09/21/20	HC	F&BI	25	17.05	S	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	MBB-22-30	09/21/20	HC	F&BI	30	12.05	S	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
MBB-23	MBB-23-5	09/21/20	HC	F&BI	5	42.18	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	MBB-23-10	09/21/20	HC	F&BI	10	37.18	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	MBB-23-15	09/21/20	HC	F&BI	15	32.18	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	MBB-23-20	09/21/20	HC	F&BI	20	27.18	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	MBB-23-25	09/21/20	HC	F&BI	25	22.18	S	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	MBB-23-30	09/21/20	HC	F&BI	30	17.18	S	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
MBB-24	MMB24-5	09/09/20	HC	F&BI	5	49.1	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	MMB24-10	09/09/20	HC	F&BI	10	44.1	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	MMB24-15	09/09/20	HC	F&BI	15	39.1	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	MMB24-20	09/09/20	HC	F&BI	20	34.1	V	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	MMB24-25	09/09/20	HC	F&BI	25	29.1	S	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
	MMB24-30	09/09/20	HC	F&BI	30	24.1	S	0.0050 U	0.0050 U	0.025 U	0.0050 U	0.0010 U	0.0050 U	–	0.030 U	0.050 U	–	0.0050 U	0.010 U
MBGW-1	MBGW1-5	03/06/19	HC	AAL	5	34.95	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	– U
	MBGW1-12.5	03/06/19	HC	AAL	12.5	27.45	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW1-17.5	03/06/19	HC	AAL	17.5	22.45	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW1-25	03/06/19	HC	AAL	25	14.95	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW1-30	03/06/19	HC	AAL	30	9.95	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-2	MBGW2-5	03/04/19	HC	AAL	5	41.11	V	–	–	–	–	–	–	–	–	–	–	–	–
	MBGW2-10	03/04/19	HC	AAL	10	36.11	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW2-12.5	03/04/19	HC	AAL	12.5	33.61	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW2-25	03/04/19	HC	AAL	25	21.11	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW2-30	03/04/19	HC	AAL	30	16.11	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-3	MBGW3-5	03/07/19	HC	AAL	5	42.77	V	–	–	–	–	–	–	–	–	–	–	–	–
	MBGW3-7.5	03/07/19	HC	AAL	7.5	40.27	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW3-10	03/07/19	HC	AAL	10	37.77	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW3-12.5	03/07/19	HC	AAL	12.5	35.27	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW3-25	03/07/19	HC	AAL	25	22.77	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW3-26	03/07/19	HC	AAL	26	21.77	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
MBGW-4	MBGW4-5	03/06/19	HC	AAL	5	42.3	V	–	–	–	–	–	–	–	–	–	–	–	–
	MBGW4-7.5	03/06/19	HC	AAL	7.5	39.8	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW4-10	03/06/19	HC	AAL	10	37.3	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW4-12.5	03/06/19	HC	AAL	12.5	34.8	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW4-25	03/06/19	HC	AAL	25	22.3	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-5	MBGW5-10	03/11/19	HC	AAL	10	39.87	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW5-15	03/11/19	HC	AAL	15	34.87	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW5-20	03/11/19	HC	AAL	20	29.87	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW5-27.5	03/11/19	HC	AAL	27.5	22.37	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW5-45	03/11/19	HC	AAL	45	4.87	S	0.050 U	0.050 U	**3.4**	0.050 U	0.050 U	0.050 U	–	**0.47**	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-6	MBGW6-10	03/14/19	HC	AAL	10	42.5	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW6-15	03/14/19	HC	AAL	15	37.5	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW6-20	03/14/19	HC	AAL	20	32.5	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW6-30	03/14/19	HC	AAL	30	22.5	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-7	MBGW7-30	03/06/19	HC	AAL	30	23.76	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-8	MBGW8-10	03/15/19	HC	AAL	10	37.08	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW8-15	03/15/19	HC	AAL	15	32.08	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW8-25	03/15/19	HC	AAL	25	22.08	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW8-35	03/15/19	HC	AAL	35	12.08	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-9	MBGW9-10	03/13/19	HC	AAL	10	46.84	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW9-15	03/13/19	HC	AAL	15	41.84	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW9-20	03/13/19	HC	AAL	20	36.84	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW9-25	03/13/19	HC	AAL	25	31.84	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW9-30	03/13/19	HC	AAL	30	26.84	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-10	MBGW10-10	03/13/19	HC	AAL	10	45.25	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW10-15	03/13/19	HC	AAL	15	40.25	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW10-20	03/13/19	HC	AAL	20	35.25	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW10-25	03/13/19	HC	AAL	25	30.25	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW10-30	03/13/19	HC	AAL	30	25.25	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-11	MBGW11-5	03/12/19	HC	AAL	5	52.55	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW11-10	03/12/19	HC	AAL	10	47.55	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-12	MBGW12-5	03/15/19	HC	AAL	5	49.00	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW12-20	03/15/19	HC	AAL	20	34.00	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW12-25	03/15/19	HC	AAL	25	29.00	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW12-30	03/15/19	HC	AAL	30	24.00	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
MBGW-13	MBGW13-5	03/14/19	HC	AAL	5	49.72	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW13-7.5	03/14/19	HC	AAL	7.5	47.22	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	**0.19 J**
	MBGW13-10	03/14/19	HC	AAL	10	44.72	V	0.050 U	0.050 U	0.050 U	**0.14**	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	**7.0**
	MBGW13-12.5	03/14/19	HC	AAL	12.5	42.22	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	**0.63 J**
	MBGW13-15	03/14/19	HC	AAL	15	39.72	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW13-20	03/14/19	HC	AAL	20	34.72	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-14	MBGW14-10	03/06/19	HC	AAL	10	36.09	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW14-15	03/06/19	HC	AAL	15	31.09	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW14-20	03/06/19	HC	AAL	20	26.09	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW14-30	03/06/19	HC	AAL	30	16.09	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBGW-16	MBGW16-10	03/08/19	HC	AAL	10	42.14	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW16-15	03/08/19	HC	AAL	15	37.14	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBGW16-30	03/08/19	HC	AAL	30	22.14	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-1	MBPP1-20	03/05/19	HC	AAL	20	25.28	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP1-25	03/05/19	HC	AAL	25	20.28	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-2	MBPP2-10	03/05/19	HC	AAL	10	34.46	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP2-20	03/05/19	HC	AAL	20	24.46	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP2-27.5	03/05/19	HC	AAL	27.5	16.96	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-3	MBPP3-10	03/06/19	HC	AAL	10	35.89	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP3-20	03/06/19	HC	AAL	20	25.89	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP3-25	03/06/19	HC	AAL	25	20.89	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-4	MBPP4-2.5	03/07/19	HC	AAL	2.5	45.84	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP4-10	03/07/19	HC	AAL	10	38.34	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP4-15	03/07/19	HC	AAL	15	33.34	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP4-17	03/07/19	HC	AAL	17	31.34	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP4-18	03/07/19	HC	AAL	18	30.34	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-5	MBPP5-10	03/07/19	HC	AAL	10	35.92	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP5-15	03/07/19	HC	AAL	15	30.92	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP5-17.5	03/07/19	HC	AAL	17.5	28.42	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP5-20	03/07/19	HC	AAL	20	25.92	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP5-25	03/07/19	HC	AAL	25	20.92	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-6	MBPP6-7.5	03/08/19	HC	AAL	7.5	44.76	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP6-10	03/08/19	HC	AAL	10	42.26	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP6-12.5	03/08/19	HC	AAL	12.5	39.76	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP6-15	03/08/19	HC	AAL	15	37.26	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
MBPP-6 (continued)	MBPP6-17.5	03/08/19	HC	AAL	17.5	34.76	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP6-20	03/08/19	HC	AAL	20	32.26	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP6-25	03/08/19	HC	AAL	25	27.26	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP6-30	03/08/19	HC	AAL	30	22.26	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-7	MBPP7-5	03/08/19	HC	AAL	5	44.77	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP7-15	03/08/19	HC	AAL	15	34.77	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP7-23	03/08/19	HC	AAL	23	26.77	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MBPP-8	MBPP8-10	03/08/19	HC	AAL	10	47.52	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP8-15	03/08/19	HC	AAL	15	42.52	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP8-22.5	03/08/19	HC	AAL	22.5	35.02	V	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
	MBPP8-30	03/08/19	HC	AAL	30	27.52	S	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	0.050 U	–	0.020 U	0.050 U	0.050 U	0.050 U	0.050 U
MW-345	MW-345-41	05/20/21	PES	PACE	41	11.85	S	0.000282 U	0.00240 U	**0.275**	0.00160 U	**0.00746**	0.00141 U	0.00229 U	**0.0273**	0.00102 U	0.00313 U	**0.189**	0.00109 U
	MW-345-47	05/20/21	PES	PACE	47	5.85	S	**0.000555 J**	0.00229 U	**0.0228 J**	0.00220 U	0.00122 U	0.00134 U	0.00219 U	**0.00257**	0.000972 U	0.00299 U	**0.181**	0.00103 U
	MW-2023-47	05/20/21	PES	PACE	47 (dup)	5.85	S	0.000331 U	0.00282 U	**0.00622 J**	0.00188 U	0.00150 U	0.00165 U	0.00269 U	**0.00105 J**	0.00120 U	0.00368 U	**0.136**	0.00128 U
	MW-345-53	05/20/21	PES	PACE	53	-0.15	S	0.000268 U	0.00228 U	0.00105 U	0.00152 U	0.00122 U	0.00133 U	0.00218 U	0.000683 U	0.000967 U	0.00297 U	0.00136 U	0.00103 U
	MW-345-58	05/20/21	PES	PACE	58	-5.15	S	0.000336 U	0.00286 U	**0.181**	0.00259 U	0.00152 U	0.00167 U	0.00272 U	**0.0175**	0.00121 U	0.00372 U	**0.0184**	0.00129 U
	MW-345-63	05/20/21	PES	PACE	63	-10.15	S	0.000307 U	0.00262 U	0.00120 U	0.00174 U	0.00140 U	0.00153 U	0.00250 U	0.000784 U	0.00111 U	0.00341 U	0.00156 U	0.00118 U
MW-346	MW-346-41.5	05/19/21	PES	PACE	41.5	10.28	S	0.000278 U	0.00237 U	**4.43**	0.00187 U	**0.00216 J**	0.00138 U	0.00226 U	**0.415**	0.00100 U	**0.00541 J**	**0.124**	0.00161 U
	MW-346-47	05/19/21	PES	PACE	47	4.78	S	0.000268 U	0.00228 U	**1.98**	0.00170 U	0.00122 U	0.00134 U	0.00218 U	**0.228**	0.000969 U	0.00298 U	**0.0149**	0.00191 U
	MW-346-52	05/19/21	PES	PACE	52	-0.22	S	0.000267 U	0.00228 U	**0.736**	0.00152 U	0.00121 U	0.00133 U	0.00217 U	**0.0726**	0.000966 U	0.00297 U	**0.00481**	0.00103 U
	MW-346-54.5	05/19/21	PES	PACE	54.5	-2.72	S	0.00111 U	0.00946 U	**0.483**	0.00631 U	0.00504 U	0.00553 U	0.00902 U	**0.0531**	0.00401 U	**0.0194 J**	0.00563 U	0.00469 U
	MW-346-57.5	05/19/21	PES	PACE	57.5	-5.72	S	0.000268 U	0.00228 U	**0.00118 J**	0.00152 U	0.00122 U	0.00133 U	0.00217 U	0.000682 U	0.000966 U	0.00297 U	0.00136 U	0.00103 U
	MW-346-62	05/19/21	PES	PACE	62	-10.22	S	0.000293 U	0.00249 U	**0.0119**	0.00166 U	0.00133 U	0.00146 U	0.00238 U	**0.00165**	0.00106 U	**0.00556 J**	0.00148 U	0.00112 U
MW-347	MW-347-44.5	05/19/21	PES	PACE	44.5	8.29	S	0.000322 U	0.00274 U	**1.36**	0.00183 U	**0.00465 J**	0.00160 U	0.00261 U	**0.699 J**	0.00116 U	0.00357 U	**0.466 J**	0.00124 U
	MW-2022-44.5	05/19/21	PES	PACE	44.5 (dup)	8.29	S	0.000299 U	0.00254 U	**1.08**	0.00170 U	**0.00442 J**	0.00149 U	0.00243 U	**0.509 J**	0.00108 U	0.00331 U	**0.321 J**	0.00115 U
	MW-347-48	05/19/21	PES	PACE	48	4.79	S	0.000268 U	0.00228 U	**0.00171 J**	0.00152 U	0.00122 U	0.00133 U	0.00217 U	0.000682 U	0.000966 U	0.00297 U	0.00136 U	0.00103 U
	MW-347-54.5	05/19/21	PES	PACE	54.5	-1.71	S	0.000276 U	0.00235 U	**0.00129 J**	0.00157 U	0.00125 U	0.00137 U	0.00224 U	**0.000733 J**	0.000997 U	**0.00637 J**	0.00140 U	0.00129 U
	MW-347-58	05/19/21	PES	PACE	58	-5.21	S	0.000273 U	0.00232 U	**0.138**	0.00404 U	0.00124 U	0.00136 U	0.00221 U	**0.0215**	0.000984 U	**0.00576 J**	**0.0150**	0.00211 U
	MW-347-65	05/19/21	PES	PACE	65	-12.21	S	0.000291 U	0.00248 U	**0.00224 J**	0.00165 U	0.00132 U	0.00145 U	0.00236 U	0.000742 U	0.00105 U	**0.00580 J**	0.00147 U	0.00112 U
MW-348	MW-348-41	05/18/21	PES	PACE	41	12.96	S	0.000294 U	0.00251 U	**0.749**	0.00167 U	**0.0186**	0.00146 U	0.00239 U	**0.249**	0.00106 U	0.00326 U	**0.569**	0.00113 U
	MW-348-49	05/18/21	PES	PACE	49	4.96	S	0.000295 U	0.00251 U	**2.48**	0.00167 U	0.00134 U	0.00147 U	0.00239 U	**0.421**	0.00106 U	0.00327 U	**0.0668**	0.00113 U
	MW-348-54.5	05/18/21	PES	PACE	54.5	-0.54	S	0.000265 U	0.00226 U	**0.0324**	0.00150 U	0.00120 U	0.00132 U	0.00215 U	**0.00636**	0.000957 U	0.00294 U	**0.00172 J**	0.00102 U
	MW-348-60	05/18/21	PES	PACE	60	-6.04	S	0.000264 U	0.00225 U	**0.00803**	0.00157 U	0.00120 U	0.00131 U	0.00214 U	**0.00294**	0.000953 U	0.00293 U	0.00134 U	0.00123 U
	MW-348-65	05/18/21	PES	PACE	65	-11.04	S	0.000286 U	0.00244 U	**0.00157 J**	0.00162 U	0.00130 U	0.00142 U	0.00232 U	**0.000740 J**	0.00103 U	0.00317 U	0.00145 U	0.00110 U
	MW-348-69	05/18/21	PES	PACE	69	-15.04	S	0.000280 U	0.00238 U	**0.00913**	0.00260 U	0.00127 U	0.00139 U	0.00227 U	**0.00300**	0.00101 U	0.00311 U	0.00142 U	0.00108 U
MW-349	MW-349-49	05/17/21	PES	PACE	49	6.84	S	0.000293 U	0.00250 U	**1.05**	0.00166 U	0.00133 U	0.00146 U	0.00238 U	**0.209**	0.00106 U	0.00325 U	**0.0752**	0.00113 U
	MW-349-51	05/17/21	PES	PACE	51	4.84	S	0.000273 U	0.00233 U	**0.00546**	**0.0114**	0.00124 U	0.00136 U	0.00222 U	**0.00274**	0.000987 U	0.00303 U	**0.00802**	0.00105 U
	MW-349-56	05/17/21	PES	PACE	56	-0.16	S	0.000273 U	0.00232 U	0.00107 U	0.00206 U	0.00124 U	0.00136 U	0.00221 U	0.000695 U	0.000985 U	0.00302 U	0.00138 U	0.00105 U
	MW-349-61	05/17/21	PES	PACE	61	-5.16	S	0.000279 U	0.00238 U	0.00109 U	0.00158 U	0.00127 U	0.00139 U	0.00227 U	0.000712 U	0.00101 U	0.00310 U	0.00141 U	0.00107 U

Table G-4
615 Dexter and SDOT Mercer Soil Results for Petroleum Hydrocarbons and VOCs
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Sample ID	Sample Date	Sampled By	Lab	Sample Depth (ft bgs)	Sample Elevation (feet NAVD 88)	Water Table Status (V/S)	Styrene	Tert-Butylbenzene	Tetrachloroethene (PCE)	Toluene	Trans-1,2-Dichloroethene (tDCE)	Trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Acetate	Vinyl Chloride	Xylenes, Total
Vadose Zone (V) Preliminary Cleanup Level (PCUL)								**2.2**	**19**	**0.050**	**4.5**	**0.52**	**0.0023**	–	**0.025**	**23**	**33**	**0.004**	**14**
Saturated Zone (S) Preliminary Cleanup Level (PCUL)								**0.12**	**1**	**0.0050**	**0.27**	**0.032**	**0.00014**	–	**0.002**	**0.79**	**2.3**	**0.004**	**0.83**
MW-349	MW-349-66	05/17/21	PES	PACE	66	-10.16	S	0.000279 U	0.00238 U	0.00109 U	0.00160 U	0.00127 U	0.00139 U	0.00227 U	0.000712 U	0.00101 U	0.00310 U	0.00141 U	0.00126 U
(continued)	MW-349-68	05/17/21	PES	PACE	68	-12.16	S	0.000287 U	0.00245 U	0.00112 U	0.00396 U	0.00130 U	0.00143 U	0.00233 U	0.000733 U	0.00104 U	0.00319 U	0.00146 U	0.00110 U
MW-350	MW-350-41	05/21/21	PES	PACE	41	16.77	S	0.000296 U	0.00252 U	0.00116 U	**0.852**	0.00134 U	0.00147 U	0.00240 U	0.000754 U	0.00107 U	0.00328 U	0.00150 U	**4.90**
	MW-350-53	05/21/21	PES	PACE	53	4.77	S	0.000270 U	0.00230 U	0.00106 U	0.00153 U	0.00123 U	0.00135 U	0.00220 U	0.000689 U	0.000976 U	0.00300 U	0.00137 U	**0.00682 J**
	MW-350-58	05/21/21	PES	PACE	58	-0.23	S	0.000268 U	0.00228 U	0.00105 U	0.00152 U	0.00122 U	0.00133 U	0.00218 U	0.000684 U	0.000968 U	0.00297 U	0.00136 U	**0.00173 J**
	MW-350-64.5	05/21/21	PES	PACE	64.5	-6.73	S	0.000281 U	0.00240 U	0.00110 U	0.00201 U	0.00128 U	0.00140 U	0.00228 U	0.000717 U	0.00102 U	0.00312 U	0.00143 U	**0.00190 J**
	MW-350-69	05/21/21	PES	PACE	69	-11.23	S	0.000290 U	0.00247 U	0.00114 U	**0.00992**	0.00132 U	0.00145 U	0.00236 U	0.000741 U	0.00105 U	0.00322 U	0.00147 U	**0.0384**
All Data	Number of Analytes Measured							256	256	397	397	397	256	33	397	397	307	397	396
	Number of Analytes Detected							1	2	25	8	4	0	0	21	0	6	13	19
	Frequency of Detection							0.4%	0.8%	6.3%	2.0%	1.0%	0.0%	0.0%	5.3%	0.0%	2.0%	3.3%	4.8%
	Maximum Detection							0.000555 J	0.105	4.43	0.852	0.0186	–	–	0.699 J	–	0.0194 J	0.569	7
	Minimum Detection							0.000264 U	0.00225 U	0.00105 U	0.0015 U	0.001 U	0.00131 U	0.00214 U	0.000682 U	0.00095 U	0.00293 U	0.00134 U	0.00102 U
	Number Of Vadose (V) Detections above SL							0	0	0	0	0	0	–	-8	0	0	-8	0
	Number of Saturated (S) Detections above SL							0	0	20	1	0	0	–	18	0	0	12	2
2017-2021	Number of Analytes Measured							256	256	397	397	397	256	33	397	397	307	397	396
	Number of Analytes Detected							1	2	25	8	4	0	0	21	0	6	13	19
	Frequency of Detection							0.4%	0.8%	6.3%	2.0%	1.0%	0.0%	0.0%	5.3%	0.0%	2.0%	3.3%	4.8%
	Maximum Detection							0.000555 J	0.105	4.43	0.852	0.0186	–	–	0.699 J	–	0.0194 J	0.569	7
	Minimum Detection							0.000264 U	0.00225 U	0.00105 U	0.0015 U	0.001 U	0.00131 U	0.00214 U	0.000682 U	0.00095 U	0.00293 U	0.00134 U	0.00102 U
	Number Of Vadose (V) Detections above SL							0	0	0	0	0	0	–	0	0	0	0	0
	Number of Saturated (S) Detections above SL							0	0	20	1	0	0	–	18	0	0	12	2

Notes and Abbreviations:
Petroleum Hydrocarbons (PHCs) analyzed by Ecology Methods NWTPH-Gx and NWTPH-Dx.
VOCs analyzed by EPA Method 8260 C/D.
PCUL = Preliminary Cleanup Level from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021. PCULs based on the practical quantitation limits (PQLs) italicized. Detected results shown in bold.
Detections above the screening level in the vadose zone are shown in **bold and highlighted blue.**
Detections above the screening level in the saturated zone are shown in **bold and highlighted gray.**
– = Not available or results not analyzed.
J = The reported concentration is an estimate based on detectable results between the method detection limit and reporting limit, laboratory QA/QC, or data validation review.
J+ = The result is an estimated quantity, but the result may be biased high.
J- = The result is an estimated quantity, but the result may be biased low.
U = Not detected at a concentration exceeding laboratory reporting limit
z = Gasoline/petroleum detection result is likely elevated due to high detections of CVOCs.
AAL = Alden Analytical Laboratories, Inc., of Seattle, Washington
bgs = below ground surface
dup = duplicate
F&BI = Friedman & Bruya, Inc.
HC = Hart Crowser, Inc.
Pace = Pace Analytical of Mt. Juliet, Tennessee (formerly ESC)
PES = PES Environmental, Inc.

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	–	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	–	–	–	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	–	–	–	**410**
Shallow Water Bearing Zone																		
DMW-1S	615 Dexter, SE quadrant	03/25/19[a]	Unknown	**350**	200 U	500 U	500 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–
		03/25/19[a]	Unknown	**300**	200 U	500 U	500 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–
		03/18/20[a]	Unknown	**1,800**	**580 J**	250 U	**580 J**	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	0.04 UJ	–
DMW-2S	615 Dexter, SE quadrant	03/18/20[a]	Unknown	100 U	50 U	250 U	250 U	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	0.04 UJ	–
DMW-4S	Alley S of SE quadrant of 615 Dexter	03/19/20[a]	Unknown	**670**	**790 J**	250 U	**790 J**	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	0.04 UJ	–
DMW-5IA	Alley S of 615 Dexter	03/19/20[a]	Unknown	100 U	**760 J**	250 U	**760 J**	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	0.04 UJ	–
DMW-6	615 Dexter, NE quadrant	03/18/20[a]	Unknown	100 U	50 U	250 U	250 U	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	0.04 UJ	–
F5	Property, NW quadrant Decommissioned March, 2019	03/28/17	Peristaltic	**234 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		06/22/17	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
F9	Property, NE quadrant Decommissioned March, 2019	03/27/17	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		06/22/17	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
F13	Property, NE quadrant Decommissioned March, 2019	03/27/17	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		06/22/17	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/05/18	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
FMW-143	9th Ave N ROW, E side	07/30/19[c]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		10/31/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 UJ	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/22/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 UJ	0.247 U	0.0739 U
		05/14/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 UJ	0.237 U	0.104 U
		07/22/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
G12	Property, NE quadrant Decommissioned March, 2019	03/27/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.55**	0.128 U	0.164 U	0.247 U	0.0739 U
		06/30/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**2.31**	0.128 U	0.164 U	0.247 U	0.0739 U
HMW-1S	SDOT Mercer Parcels, NE quadrant	3/25/19[a]	Peristaltic	100 U	200 U	500 U	500 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–
		03/11/20[a]	Unknown	100 U	**200 J**	250 U	**200 J**	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	0.04 UJ	–
HMW-2S	SDOT Mercer Parcels, NE quadrant	3/25/19[a]	Peristaltic	100 U	200 U	500 U	500 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–
		03/12/20[a]	Unknown	100 U	**56 J**	260 U	**56 J**	0.20 U	**0.20**	0.20 U	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	0.03 UJ	–
HMW-9S	SDOT Mercer Parcels, SW quadrant	03/17/20[a]	Unknown	100 U	**61 J**	250 U	**61 J**	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	0.03 UJ	–
HMW-10S	SDOT Mercer Parcels, SE quadrant	03/16/20[a]	Unknown	100 U	**66 J**	250 U	**66 J**	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	0.03 UJ	–
HMW-11S	SDOT Mercer Parcels, SE quadrant	03/11/20[a]	Unknown	100 U	**620 J**	250 U	**620 J**	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	0.04 UJ	–
HMW-20S	SDOT Mercer Parcels, NW quadrant	9/18/20[a]	Unknown	100 U	50 U	250 U	250 U	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	0.080 U	–

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	–	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	–	–	–	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	–	–	–	**410**
HMW-21S	SDOT Mercer Parcels, SE quadrant	11/3/20[a]	Unknown	–	50 U	250 U	250 U	–	–	–	–	–	–	–	–	–	–	–
HMW-22S	SDOT Mercer Parcels, SE quadrant	11/3/20[a]	Unknown	–	62 U	250 U	250 U	–	–	–	–	–	–	–	–	–	–	–
J5	Property, SW quadrant	03/21/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.453 J**	0.128 U	0.164 U	0.247 U	0.0739 U
		06/26/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.425 J**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/05/18	Peristaltic	**207 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.371 J**	0.128 U	0.164 U	0.247 U	0.0739 U
	Decommissioned March, 2019																	
J15	Property, SE quadrant	03/27/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.78**	0.128 U	0.164 U	0.247 U	0.0739 U
		06/26/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.84**	0.128 U	0.164 U	0.247 U	0.0739 U
(dup)		06/26/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.81**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/05/18	Peristaltic	**41.2 J**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.10**	0.128 U	0.164 U	0.247 U	0.0739 U
	Decommissioned March, 2019																	
K8	Property, SW quadrant	03/21/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.47**	0.128 U	0.164 U	0.247 U	0.0739 U
		06/26/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.34**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/05/18	Peristaltic	**156 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.822**	0.128 U	0.164 U	0.247 U	0.0739 U
	Decommissioned March, 2019																	
M15	Property, SE quadrant	03/27/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.631**	0.128 U	0.164 U	0.247 U	0.0739 U
(dup)		03/27/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.588**	0.128 U	0.164 U	0.247 U	0.0739 U
		06/26/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.508**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/05/18	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.198 J**	0.128 U	0.164 U	0.247 U	0.0739 U
	Decommissioned March, 2019																	
MW-8	Seattle Roy Aloha Shops, N end	03/20/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/13/18	Peristaltic		–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/18/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/10/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/16/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		05/06/20	Peristaltic	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/14/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-9	8th Ave N ROW, E side	03/20/17	Peristaltic	**52.8 J**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		06/20/17	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
(dup)		06/20/17	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/05/18	Peristaltic	**32.9 J**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/21/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/26/19	Peristaltic	**121 zJ+**	–	–	–	0.120 U	**0.298 J**	0.130 U	0.186 U	**0.465 J**	**1.57**	**0.893**	0.128 U	0.164 U	0.247 U	0.0739 U
		07/16/19	Peristaltic	57.4 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/17/19	Peristaltic	62.0 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		11/24/20	Peristaltic	**41.0 J**	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		02/05/21	Peristaltic	73.2 U	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/12/21	Peristaltic	31.6 U	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		05/12/21	Peristaltic	31.6 U	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
MW121	8th Ave N ROW, E side	03/28/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		06/20/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/05/18	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	**–**	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**–**	**–**	**–**	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	**–**	**–**	**–**	**410**
MW121		01/31/19	Peristaltic	38.0 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
(continued)		04/29/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/19/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		11/30/20	Bladder	31.6 U	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.0320 J**	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		02/05/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.0430 J**	**0.0270 J**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/12/21	Peristaltic	31.6 U	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.0280 J**	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
	(dup)	05/12/21	Peristaltic	31.6 U	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
MW125	Valley Street ROW, N side	03/22/17	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		06/28/17	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/06/18	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/21/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/23/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/18/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/18/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 UJ	0.130 U	0.186 U	0.164 UJ	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/29/20	Bladder	51.1 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		11/17/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	**0.110 J**
		02/02/21	Peristaltic	38.5 U	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/11/21	Peristaltic	46.2 U	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
	(dup)	05/11/21	Peristaltic	33.2 U	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-154	Roy St ROW S side	04/30/18	Bladder	32.1 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/21/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/24/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/15/19	Bladder	68.0 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/14/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/21/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/30/20	Bladder	**47.5 J**	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/10/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/09/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/08/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		05/10/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-155	Roy Street ROW, S side	04/27/18	Peristaltic	60.9 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/21/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/23/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.249 J**	0.128 U	0.164 U	0.247 U	0.0739 U
		07/23/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/16/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/20/20	Bladder	**44.9 J**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		05/05/20	Bladder	31.6 U	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 UJ	0.237 U	0.104 U
		08/03/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/11/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-159	8th Ave N ROW, E side	04/26/18	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/21/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/26/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	(dup)	04/26/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	–	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	–	–	–	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	–	–	–	**410**
MW-159 (continued)		07/22/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/29/20	Bladder	33.9 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		11/11/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		02/08/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		05/11/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-210[c]	Valley Street ROW, N side	03/30/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		06/21/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/09/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/11/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/17/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.262 U
		04/09/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/07/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-214	Valley Street ROW,	03/30/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
(dup)	S side	03/30/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/09/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/11/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	**2.69**
		01/20/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/07/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/06/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-301	Valley Street ROW,	11/30/20	Bladder	31.6 U	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
(dup)	S side	11/30/20	Bladder	31.6 U	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		02/05/21	Bladder	43.3 U	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/14/21	Bladder	31.6 U	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
	(dup)	05/14/21	Bladder	31.6 U	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-305	Roy St ROW,	10/15/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 UJ	0.186 UJ	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	S side	01/15/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/28/20	Bladder	**54.4 J**	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/27/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 UJ	0.0460 U
		11/06/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/18/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 UJ	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-310	Alley E of Seattle	10/10/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	Roy Aloha Shops	01/14/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 UJ	0.247 U	0.0739 U
		04/08/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		08/04/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
	(dup)	08/04/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/06/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/03/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-312	Alley E of Seattle	10/11/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	Roy Aloha Shops	01/21/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/22/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		08/04/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.0350 J**	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/11/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	**–**	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**–**	**–**	**–**	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	**–**	**–**	**–**	**410**
MW-312 (continued)		05/03/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.0290 J**	0.0200 UJ	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-313	Alley E of Seattle Roy Aloha Shops	10/10/19	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/14/20	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 UJ	0.247 U	0.0739 U
		05/04/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
MW-320	9th Ave N ROW, W side	10/07/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/20/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/29/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/28/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 UJ	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		11/12/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		05/20/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 UJ	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-332	Roy St ROW, N side	05/04/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/30/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 UJ	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/12/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		05/20/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
MW-337	Lake Union Park, N end	05/07/20	Peristaltic	–	–	–	–	0.147 U	0.149 U	0.133 UJ	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 UJ	0.104 U
		07/23/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/10/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/04/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-339	Lake Union Park, S end	05/14/20	Peristaltic	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 UJ	0.237 U	0.104 U
(dup)		05/14/20	Peristaltic	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 UJ	0.237 U	0.104 U
		07/23/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/09/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/25/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
N7	Property, SW quadrant	03/30/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.773**	0.128 U	0.164 U	0.247 U	0.0739 U
		06/27/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.00**	0.128 U	0.164 U	0.247 U	0.0739 U
	Decommissioned March, 2019																	
R-MW2	Property, NE quadrant	03/21/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		06/15/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/02/18	Peristaltic	38.0 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	Decommissioned March, 2019																	
R-MW3	Property, NE quadrant	03/21/17	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		06/28/17	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/04/18	Peristaltic	**33.7 J**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	Decommissioned March, 2019																	
R-MW5	Dexter Ave N ROW, E side	03/23/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		06/16/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/11/18	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/03/19	Peristaltic	**81.5 J**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/22/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/16/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/21/19	Bladder	**95.3 J**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/24/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	**–**	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**–**	**–**	**–**	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	**–**	**–**	**–**	**410**
R-MW5		11/18/20	Bladder	43.8 U	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
(continued)		02/11/21	Bladder	31.6 U	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
(dup)		02/11/21	Bladder	**45.1 J**	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 UJ	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 UJ
		05/17/21	Bladder	31.6 U	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
R-MW6	8th Ave N ROW, E side	03/21/17	Peristaltic	**42.8 J**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		06/20/17	Peristaltic	**38.5 J**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.337 J**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/06/18	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.347 J**	0.128 U	0.164 U	0.247 U	0.0739 U
		01/25/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.310 J**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/25/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		12/01/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	**0.0260 J**	0.0280 U	0.0250 U	0.204 UJ	0.0460 UJ
		02/03/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/17/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 UJ	0.0230 U	**0.206**	0.0280 U	0.0250 U	0.204 U	0.0460 U
SCL-MW101	Alley E of Seattle Roy Aloha Shops	03/28/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	**1.50**
		06/14/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	**2.03**
		04/06/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	**3.51**
		10/09/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	**7.95**
		01/17/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	**2.93**
		04/07/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	**1.93**
		11/24/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	**2.92**
		05/04/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	**0.631**
SCL-MW105	Alley E of Seattle Roy Aloha Shops	03/28/17	Peristaltic	–	–	–	–	0.600 U	0.470 U	0.650 U	0.930 U	0.820 U	0.570 U	0.940 U	0.640 U	0.820 U	1.24 U	**8.81**
		06/15/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	**9.29**
		04/06/18	Peristaltic	–	–	–	–	1.20 U	0.940 U	1.30 U	1.86 U	1.64 U	1.14 U	1.88 U	1.28 U	1.64 U	2.47 U	**7.86**
		10/10/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	**14.4**
		01/17/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	**12.2**
		04/01/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 UJ	0.247 U	**8.88**
		07/24/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 UJ	**9.87**
SCS-2	Seattle Roy Aloha Shops, N End	03/20/17	Peristaltic	**1,660**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	**59.3**
		06/12/17	Peristaltic	**901**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	**51.2**
		04/13/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	**12.5**
		07/18/19	Peristaltic	**2,190 J+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	**88.3**
(dup)		07/18/19	Peristaltic	**2,320 J+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	**82.3**
		10/10/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	**119**
		01/16/20	Peristaltic	–	–	–	–	1.20 U	0.940 U	1.30 U	1.86 U	1.64 U	1.14 U	1.88 U	1.28 U	1.64 U	2.47 U	**68.4**
Intermediate A Water-Bearing Zone																		
BB-8	Roy Street ROW, S side	03/22/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		06/14/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/11/18	Peristaltic	40.9 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
(dup)		04/11/18	Peristaltic	41.5 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/23/19	Peristaltic	**99.6 J**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.403 J**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/23/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	–	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	–	–	–	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	–	–	–	**410**
BB-8		07/17/19	Bladder	**112 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
(continued)		10/22/19	Bladder	**176 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
(dup)		10/22/19	Bladder	**174 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/20/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
(dup)		01/20/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		05/12/20	Bladder	**101 zJ+**	–	–	–	0.147 U	0.149 U	0.133 UJ	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 UJ	0.237 U	0.104 U
		07/27/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	**0.227**	0.0280 U	0.0250 U	0.204 UJ	0.0460 U
(dup)		07/27/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	**0.229**	0.0280 U	0.0250 U	0.204 UJ	0.0460 U
		11/17/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.553**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/11/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 UJ	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 UJ
		06/07/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.0490 J**	0.0280 U	0.0250 U	0.204 U	0.0460 U
DMW-3IA	615 Dexter, NE quadrant	03/18/20[a]	Unknown	100 U	50 U	250 U	250 U	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	0.04 UJ	–
FMW-142	9th Ave N ROW, E side	07/29/19[a]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		10/31/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 UJ	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/22/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 UJ	0.247 U	0.0739 U
		04/28/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/08/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/04/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/25/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
GEI-1	Block 37, SW quadrant	03/24/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		06/13/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	**0.200 J**
		04/22/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/16/19	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/21/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/22/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 UJ	0.247 U	0.0739 U
		04/29/20	Peristaltic	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
(dup)		04/29/20	Peristaltic	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/30/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 UJ	0.0280 U	0.0250 U	0.204 U	0.0460 U
GEI-MW-1	Block 79 East, N end	01/23/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/29/20	Peristaltic	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		08/07/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/10/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		05/13/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
HC-4	601 Dexter, NE quadrant	04/12/19[a]	Unknown	100 U	200 U	500 U	500 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–
HMW-2IA	SDOT Mercer Parcels, NE quadrant	03/25/19[a]	Peristaltic	100 U	200 U	500 U	500 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–
		03/12/20[a]	Unknown	**160**	51 U	250 U	250 U	2.0 U	2.0 U	2.0 U	2.0 U	–	2.0 U	**1.5**	2.0 U	2.0 U	0.30 UJ	–
HMW-3IA	SDOT Mercer Parcels, NW quadrant	03/25/19[a]	Peristaltic	100 U	200 U	500 U	500 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–
		03/13/20[a]	Unknown	100 U	50 U	250 U	250 U	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	0.04 UJ	–
HMW-6IA	SDOT Mercer Parcels, SW quadrant	03/13/20[a]	Unknown	100 U	**160 J**	250 U	**160 J**	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	0.04 UJ	–

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	–	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	–	–	–	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	–	–	–	**410**
HMW-9IA	SDOT Mercer Parcels, SW quadrant	03/19/20[a]	Unknown	100 U	50 U	250 U	250 U	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	0.04 UJ	–
		06/02/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.265**	0.0280 U	0.0250 U	0.204 U	0.0460 U
HMW-20IA	SDOT Mercer Parcels, NW quadrant	09/18/20[a]	Unknown	100 U	50 U	250 U	250 U	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	**2.5**	0.20 U	0.20 U	0.080 UJ	–
		06/02/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.139**	**10.9**	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW107	8th Ave N ROW, W side	03/27/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		06/19/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/09/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/30/19	Peristaltic	**663** zJ+	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**9.01**	0.128 U	0.164 U	0.247 U	0.0739 UJ
		05/01/19	Peristaltic	**481** zJ+	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**13.0**	0.128 U	0.164 U	0.247 U	0.0739 U
		07/22/19	Bladder	**210** zJ+	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.825**	0.128 U	0.164 U	0.247 U	0.0739 U
		10/15/19	Bladder	**365** zJ+	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**3.27**	0.128 U	0.164 U	0.247 U	0.0739 U
		01/28/20	Bladder	**1,890** zJ+	–	–	–	2.40 U	1.88 U	2.60 U	3.72 U	3.28 U	2.28 U	**22.1**	2.56 U	3.28 U	4.94 U	1.48 U
		04/03/20	Bladder	**1,420** zJ+	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**14.5**	0.128 U	0.164 U	0.247 U	0.0739 U
		07/31/20	Bladder	–	–	–	–	0.500 U	0.275 U	0.390 U	0.883 U	0.675 U	0.575 U	**1.19 J**	0.700 U	0.625 U	5.10 U	1.15 U
		12/01/20	Peristaltic	–	–	–	–	0.500 U	0.275 U	0.390 U	0.883 U	0.675 U	0.575 U	0.500 U	0.700 U	0.625 U	5.10 U	1.15 U
		02/02/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		06/02/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW108	Alley E of Seattle Roy Aloha Shops	03/28/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.588**	0.128 U	0.164 U	0.247 U	0.0739 U
		06/27/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.512**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/06/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	**0.285 J**	**11.9**	0.128 U	0.164 U	0.247 U	0.0739 U
	(dup)	04/06/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	**0.251 J**	**11.2**	0.128 U	0.164 U	0.247 U	0.0739 U
		01/22/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**10.1**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/29/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**3.57**	0.128 U	0.164 U	0.247 U	0.0739 U
		07/15/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**4.09**	0.128 U	0.164 U	0.247 U	0.0739 U
		10/10/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**9.11**	0.128 U	0.164 U	0.247 U	**0.556**
		01/14/20	Peristaltic	–	–	–	–	3.00 U	2.35 U	3.25 U	4.65 U	4.10 U	2.85 U	4.70 U	3.20 U	4.10 UJ	6.17 U	1.85 U
		04/22/20	Bladder	–	–	–	–	3.68 U	3.73 U	3.33 U	3.95 U	3.95 U	2.50 U	4.70 U	3.55 U	4.10 U	5.93 U	2.60 U
		07/16/20	Bladder	–	–	–	–	0.500 U	0.275 U	0.390 UJ	0.883 U	0.675 U	0.575 U	**1.63 J**	0.700 U	0.625 U	5.10 U	1.15 U
	(dup)	07/16/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	**0.139**	**2.03**	0.0280 U	0.0250 U	0.204 U	**0.926**
		11/04/20	Bladder	–	–	–	–	0.500 U	0.275 U	0.390 U	0.883 U	0.675 U	0.575 U	0.500 U	0.700 U	0.625 UJ	5.10 U	1.15 U
		02/09/21	Peristaltic	–	–	–	–	0.100 U	0.0550 U	0.0780 U	0.177 U	0.135 U	0.115 U	**1.25**	0.140 U	0.125 U	1.02 U	0.230 U
		05/03/21	Peristaltic	–	–	–	–	0.100 U	0.0550 U	0.0780 U	0.177 U	0.135 U	0.115 U	**1.46**	0.140 U	0.125 U	1.02 U	0.230 U
MW109	Alley E of Seattle Roy Aloha Shops	03/29/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		06/27/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.583**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/06/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.21**	0.128 U	0.164 U	0.247 U	0.0739 U
		01/23/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.739**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/29/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/15/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/15/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 UJ	0.186 UJ	0.164 U	0.114 U	**0.768**	0.128 U	0.164 U	0.247 U	0.0739 U
		01/21/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/22/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/06/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 J	**0.116**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/02/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.0900 J**	0.0280 U	0.0250 U	0.204 U	0.0460 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	**–**	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**–**	**–**	**–**	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	**–**	**–**	**–**	**410**
MW109		02/09/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.0250 J**	**0.0420 J**	0.0280 U	0.0250 U	0.204 U	0.0460 U
(continued)		05/03/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW110	Alley E of Seattle	03/23/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**5.23**	0.128 U	0.164 U	0.247 U	0.0739 U
	Roy Aloha Shops	06/27/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**5.30**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/09/18	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**5.17**	0.128 U	0.164 U	0.247 U	0.0739 U
		01/23/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**6.44**	0.128 U	0.164 U	0.247 U	0.0739 U
(dup)		01/23/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**6.88**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/26/19	Bladder	–	–	–	–	0.120 U	4.70 U	0.130 U	0.186 U	0.164 U	5.70 U	**7.03**	0.128 U	0.164 U	0.247 U	0.0739 U
		07/15/19	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**8.44**	0.128 U	0.164 U	0.247 U	0.0739 U
		10/15/19	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 UJ	0.186 UJ	0.164 U	0.114 U	**5.01**	0.128 U	0.164 U	0.247 U	0.0739 U
		01/16/20	Bladder	–	–	–	–	0.600 U	0.470 U	0.650 U	0.930 U	0.820 U	0.570 U	**1.21 J**	0.640 U	0.820 U	1.23 U	0.369 U
		04/22/20	Bladder	–	–	–	–	0.735 U	0.745 U	0.665 U	0.790 U	0.900 U	0.500 U	**5.46**	0.710 U	0.820 U	1.19 U	0.520 U
		07/16/20	Bladder	–	–	–	–	0.100 U	0.0550 U	0.0780 UJ	0.177 U	0.135 U	0.115 U	**4.23**	0.140 U	0.125 U	1.02 U	0.230 U
		11/04/20	Bladder	–	–	–	–	1.00 U	0.550 U	0.780 U	1.77 U	1.35 U	1.15 U	**5.82**	1.40 U	1.25 UJ	10.2 U	2.30 U
		02/09/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**3.21**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		05/04/21	Bladder	–	–	–	–	0.200 U	0.110 U	0.156 U	0.353 U	0.270 U	0.230 U	**1.92**	0.280 U	0.250 U	2.04 U	0.460 U
MW115	9th Ave N ROW,	03/22/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	W side	06/22/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/11/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/30/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 UJ
		07/17/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/22/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/20/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		05/05/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 UJ	0.237 U	0.104 U
		07/28/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 UJ	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		11/12/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		02/12/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/25/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
MW116	9th Ave N ROW,	03/21/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	W side	06/16/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/11/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/30/19	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 UJ
		07/17/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/31/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 UJ	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/21/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/29/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/28/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 UJ	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		11/12/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		02/11/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/25/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
MW119	9th Ave N ROW,	03/29/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	W side	06/28/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	**0.165**	0.247 U	0.0739 U
		04/05/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	–	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	–	–	–	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	–	–	–	**410**
MW119		01/21/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
(continued)		04/29/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/19/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/10/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		11/11/19[v]	Peristaltic	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/14/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 UJ	0.247 U	0.0739 U
(split)		01/14/20[v]	Peristaltic	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/18/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		03/24/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/27/20	Peristaltic	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		05/19/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/08/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		07/28/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		09/17/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/11/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		12/03/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/10/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 UJ	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 UJ
(split)		02/10/21[v]	Peristaltic	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/20/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
MW120	8th Ave N ROW, E side	03/28/17	Peristaltic	–	–	–	–	0.120 U	**0.277 J**	0.130 U	0.186 U	**0.417 J**	**1.88**	**0.303 J**	0.128 U	0.164 U	0.247 U	0.0739 U
		06/28/17	Bladder	–	–	–	–	0.120 U	**0.278 J**	0.130 U	0.186 U	**0.418 J**	**1.57**	**0.251 J**	0.128 U	**0.456**	0.247 U	0.0739 U
		04/09/18	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	**0.501**	**0.471 J**	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/24/19	Peristaltic	**105 zJ+**	–	–	–	0.120 U	**0.255 J**	0.130 U	0.186 U	**0.394 J**	**1.61**	**0.883**	0.128 U	0.164 U	0.247 U	0.0739 UJ
		05/03/19	Peristaltic	**111 J+**	–	–	–	0.120 U	**0.261 J**	0.130 U	0.186 U	**0.477 J**	**1.70**	**0.812**	0.128 U	0.164 U	0.247 U	0.0739 U
(dup)		05/03/19	Peristaltic	**138 J+**	–	–	–	0.120 U	**0.290 J**	0.130 U	0.186 U	**0.412 J**	**1.76**	**0.866**	0.128 U	0.164 U	0.247 U	0.0739 U
		07/16/19	Peristaltic	**152 zJ+**	–	–	–	0.120 U	**0.302 J**	0.130 U	0.186 U	**0.631**	**1.43**	**0.738**	0.128 U	0.164 U	0.247 U	0.0739 U
		10/17/19	Bladder	**106 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 UJ	**1.52**	**0.552**	0.128 U	0.164 U	0.247 U	0.0739 U
(dup)		10/17/19	Bladder	**113 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	**1.29**	**0.478 J**	0.128 U	0.164 U	0.247 U	0.0739 U
		01/17/20	Bladder	**124 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	**1.80**	**0.586**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/23/20	Bladder	**481 zJ+**	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	**1.47**	**0.341 J**	0.142 U	0.164 UJ	0.237 U	0.104 U
		07/14/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	**0.0870 J**	**1.37**	**0.412**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/30/20	Bladder	–	–	–	–	0.0200 U	**0.164**	0.0156 U	0.0353 U	**0.321**	**2.17**	**0.565**	0.0280 U	0.0250 U	0.204 U	0.0460 U
(dup)		11/30/20	Bladder	–	–	–	–	0.0200 U	**0.179**	0.0156 U	0.0353 U	**0.338**	**2.15**	**0.557**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		02/05/21	Peristaltic	–	–	–	–	0.0200 U	**0.243 J**	0.0156 U	0.0353 U	**0.479**	**2.60**	**0.650 J**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/12/21	Peristaltic	–	–	–	–	0.0200 U	**0.163**	0.0156 U	0.0353 U	**0.242**	**2.09**	**0.425**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
MW127	8th Ave N ROW, E side	08/01/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	**0.542**	**0.495 J**	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/17/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	**0.547**	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/17/20	Bladder	61.3 U	–	–	–	0.120 U	**0.111 J**	0.130 U	0.186 U	**0.425 J**	**0.568**	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/23/20	Bladder	**121 zJ+**	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	**0.446 J**	**0.511**	0.188 U	0.142 U	0.164 UJ	0.237 U	0.104 U
		07/14/20	Bladder	–	–	–	–	0.0200 U	**0.136**	0.0156 U	0.0353 U	**0.477**	**0.421**	**0.0620 J**	0.0280 U	0.0250 U	0.204 U	0.0460 U
(dup)		07/14/20	Bladder	–	–	–	–	0.0200 U	**0.148**	0.0156 U	0.0353 U	**0.500**	**0.420**	**0.0770 J**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/13/20	Bladder	–	–	–	–	0.0200 U	**0.0917 J**	0.0156 U	0.0353 U	**0.458 J**	**0.366**	0.0200 UJ	0.0280 U	0.0250 U	0.204 U	0.0460 U
		05/11/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	**0.194**	**0.394**	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	**–**	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**–**	**–**	**–**	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	**–**	**–**	**–**	**410**
MW131	Property,	03/27/17	Peristaltic	**91.9 J**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	SE quadrant	06/20/17	Peristaltic	31.6 U	–	–	–	0.600 U	0.0940 U	0.650 U	0.930 U	0.820 U	0.570 U	0.940 U	0.640 U	0.820 U	1.24 U	0.370 U
		04/16/18	Peristaltic	55.3 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/25/18	Peristaltic	57.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		12/12/18	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/29/19	Peristaltic	**43.7 J**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 UJ
		03/11/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	Decommissioned March, 2019																	
MW-142	8th Ave N ROW,	04/27/18	Peristaltic	49.3 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.244 J**	0.128 U	0.164 U	0.247 U	0.0739 U
	E side	01/28/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 UJ
	(dup)	01/28/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 UJ
		04/24/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/25/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/16/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/22/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.235 J**	0.128 U	0.164 UJ	0.247 U	0.0739 U
		04/24/20	Bladder	62.4 U	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	**0.221 J**	0.142 U	0.164 U	0.237 U	0.104 U
		07/30/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.626 J**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/24/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.0250 J**	**0.905**	0.0280 U	0.0250 U	0.204 U	0.0460 U
	(dup)	11/24/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.0310 J**	**1.09 J+**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/08/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.370**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		05/19/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 UJ	0.0230 U	**0.175**	0.0280 U	0.0250 U	0.204 U	**0.331**
MW-144	8th Ave N ROW,	04/27/18	Peristaltic	**364 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.15**	0.128 U	0.164 U	0.247 U	0.0739 U
	E side	01/28/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 UJ
		04/23/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	Decommissioned December 2019																	
MW-144R	8th Ave N ROW,	12/16/19	Bladder	**325 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.589**	0.128 U	0.164 U	0.247 U	0.0739 U
	E side	01/21/20	Bladder	**60.7 J**	–	–	–	1.20 U	0.940 U	1.30 U	1.86 U	1.64 U	1.14 U	1.88 U	1.28 U	1.64 U	2.47 U	0.739 U
		04/02/20	Bladder	31.6 U	–	–	–	0.120 UJ	0.0940 UJ	0.130 UJ	0.186 UJ	0.164 UJ	0.114 UJ	0.188 UJ	0.128 UJ	0.164 UJ	0.247 UJ	0.0739 UJ
		08/03/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/23/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/02/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/12/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
MW-146	Roy St ROW,	04/30/18	Bladder	**597 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**4.02**	0.128 U	0.164 U	0.247 U	0.0739 U
	S side	01/22/19	Peristaltic	**509 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**4.44**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/24/19	Bladder	**88.0 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.04**	0.128 U	0.164 U	0.247 U	0.0739 U
		07/19/19	Bladder	**46.3 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.15**	0.128 U	0.164 U	0.247 U	0.0739 U
	(dup)	07/19/19	Bladder	**262 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.37**	0.128 U	0.164 U	0.247 U	0.0739 U
		10/14/19	Bladder	**1,310 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**2.83**	0.128 U	0.164 U	0.247 U	0.0739 U
		01/24/20	Bladder	**1,140 zJ+**	–	–	–	12.0 U	9.40 U	13.0 U	18.6 U	16.4 U	11.4 U	18.8 U	12.8 U	16.4 U	24.7 U	7.39 U
	(dup)	01/24/20	Bladder	**423 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**2.59**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/30/20	Bladder	**1,080 zJ+**	–	–	–	14.7 U	14.9 U	13.3 U	15.8 U	18.0 U	10.0 U	18.8 U	14.2 U	16.4 U	23.7 U	10.4 U
		07/09/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	**3.77**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/10/20	Bladder	**2,850 zJ+**	–	–	–	1.00 U	0.550 U	0.780 U	1.77 U	1.35 U	1.15 U	**5.58 J-**	1.40 U	1.25 U	10.2 U	2.30 U
	(split)	11/10/20	Bladder	100 U	50.0 U	250 U	250 U	500 U	500 U	500 U	500 U	–	500 U	500 U	500 U	500 U	500 U	–

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	–	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	–	–	–	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	–	–	–	**410**
MW-146		02/08/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**3.02**	0.0280 U	0.0250 U	0.204 U	0.0460 U
(continued)		05/04/21	Bladder	–	–	–	–	1.00 U	0.550 U	0.780 UJ	1.77 U	1.35 U	1.15 U	1.00 U	1.40 U	1.25 UJ	10.2 U	2.30 U
MW-149	Property,	04/10/18	Peristaltic	**11,700 zJ+**	–	–	–	0.600 U	0.470 U	0.650 U	0.930 U	0.820 U	0.570 U	**35.5**	0.640 U	0.820 U	1.24 U	**0.465 J**
	NE quadrant	10/25/18	Peristaltic	**4,570 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**25.7**	0.128 U	0.164 U	0.247 U	0.0739 U
		12/13/18	Peristaltic	**11,400 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**30.4**	0.128 U	0.164 U	0.247 U	**0.178 J**
(dup)		12/13/18	Peristaltic	**11,400 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**31.1**	0.128 U	0.164 U	0.247 U	**0.182 J**
		01/29/19	Peristaltic	**14,400 zJ+**	–	–	–	12.0 U	9.40 U	13.0 U	18.6 U	16.4 U	11.4 U	18.8 U	12.8 U	16.4 U	24.7 U	7.39 UJ
		03/13/19	Peristaltic	**15,300 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**34.0**	0.128 U	0.164 U	0.247 U	**0.338 J**
	Decommissioned March, 2019																	
MW-151	Property,	04/10/18	Peristaltic	74.6 U	–	–	–	0.120 U	0.0940 UJ	0.130 U	0.186 U	0.164 UJ	0.114 UJ	0.188 UJ	0.128 U	0.164 U	0.247 U	0.0739 UJ
	SW quadrant	10/25/18	Peristaltic	99.4 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		12/14/18	Peristaltic	**1,040 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**7.05**	0.128 U	0.164 U	0.247 U	0.0739 U
		01/31/19	Peristaltic	**340 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**3.15**	0.128 U	0.164 U	0.247 U	0.0739 U
		03/12/19	Peristaltic	**143 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	Decommissioned March, 2019																	
MW-156	8th Ave N ROW,	04/26/18	Peristaltic	**1,690 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**20.7**	0.128 U	0.164 U	0.247 U	0.0739 U
	E side	01/24/19	Peristaltic	**1,480 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**14.1**	0.128 U	0.164 U	0.247 U	0.0739 UJ
		04/24/19	Peristaltic	**2,570 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**12.3**	0.128 U	0.164 U	0.247 U	0.0739 U
(dup)		04/24/19	Peristaltic	**2,600 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**11.8**	0.128 U	0.164 U	0.247 U	0.0739 U
		07/22/19	Bladder	**3,100 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**13.2**	0.128 U	0.164 U	0.247 U	0.0739 U
		10/17/19	Bladder	**1,450 zJ+**	–	–	–	1.20 U	0.940 U	1.30 U	1.86 U	1.64 U	1.14 U	**6.70**	1.28 U	1.64 U	2.47 U	0.739 U
		01/20/20	Bladder	**2,160 zJ+**	–	–	–	1.20 U	0.940 U	1.30 U	1.86 U	1.64 U	1.14 U	**7.48**	1.28 U	1.64 U	2.47 U	0.739 U
		04/24/20	Bladder	**770 zJ+**	–	–	–	7.35 U	7.45 U	6.65 U	7.90 U	9.00 U	5.00 U	9.40 U	7.10 U	8.20 U	11.9 U	5.20 U
		07/15/20	Bladder	–	–	–	–	1.00 U	0.550 U	0.780 U	1.77 U	1.35 U	1.15 U	**6.40**	1.40 U	1.25 U	10.2 U	2.30 U
		11/11/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.361**	**3.10**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		02/08/21	Peristaltic	–	–	–	–	0.200 U	0.110 U	0.156 U	0.353 U	0.270 U	0.230 U	**2.58**	0.280 U	0.250 U	2.04 U	0.460 U
		05/10/21	Bladder	–	–	–	–	1.00 U	0.550 U	0.780 UJ	1.77 U	1.35 U	1.15 U	**2.65 J**	1.40 U	1.25 U	10.2 U	2.30 U
MW-189	Valley St ROW,	10/14/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	S side	01/23/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/03/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
(dup)		04/03/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		08/04/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/17/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/03/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/14/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-302	Dexter Ave N	10/21/19	Bladder	**98.5 J**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	ROW	01/24/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		05/07/20	Bladder	31.6 U	–	–	–	0.147 U	0.149 U	0.133 UJ	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 UJ	0.104 U
		07/28/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 UJ	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		11/17/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/17/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-306	Dexter Ave N ROW,	10/15/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 UJ	0.186 UJ	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	E side	01/16/20	Bladder	34.3 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	**–**	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**–**	**–**	**–**	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	**–**	**–**	**–**	**410**
MW-306		04/28/20	Bladder	**42.7 J**	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
(continued)		07/29/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/06/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/18/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 UJ	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-308	Alley E of Seattle	10/11/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	Roy Aloha Shops	01/16/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/08/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/06/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.0710 J**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/06/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	**0.106 J**
		05/04/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-315	Mercer St ROW,	10/03/19	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	N side	01/16/20	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/24/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/24/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	**0.154 J**
		11/02/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/17/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 UJ	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-317	9th Ave N ROW,	10/09/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	W side	01/16/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/27/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/30/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 UJ	0.0280 U	0.0250 U	0.204 U	**0.0651 J**
		11/10/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		05/19/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 UJ	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-325	Mercer St ROW,	10/03/19	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	N side	01/17/20	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/21/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/23/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/02/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/08/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		05/17/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 UJ	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-327	Lake Union Park,	10/02/19	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	S end	01/17/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/09/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/07/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/09/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/25/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-330	Valley St ROW,	05/14/20	Bladder	31.6 U	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 UJ	0.237 U	0.104 U
(dup)	N side	05/14/20	Bladder	31.6 U	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 UJ	0.237 U	0.104 U
		07/16/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		12/01/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 UJ	0.0460 UJ
	(dup)	12/01/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 UJ	0.0460 UJ
		05/25/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	**–**	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**–**	**–**	**–**	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	**–**	**–**	**–**	**410**
MW-331	Alley E of Seattle	04/24/20	Peristaltic	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	**0.953**	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
	Roy Aloha Shops	07/06/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.916**	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/06/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**1.08**	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/04/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.831**	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-333	900 Roy St,	04/29/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
	S end	07/24/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 UJ	0.0460 U
		11/05/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		05/18/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 UJ	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-344	SDOT Mercer Parcels,	06/01/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
Intermediate B Water-Bearing Zone																		
FMW-141	Alley E of Seattle	07/26/19[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	Roy Aloha Shops	10/30/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**2.51 J**	0.128 U	0.164 U	0.247 U	0.0739 U
(dup)		10/30/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**4.63 J**	0.128 U	0.164 U	0.247 U	0.0739 U
		11/11/19[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/14/20	Bladder	–	–	–	–	0.600 U	0.470 U	0.650 U	0.930 U	0.820 U	0.570 U	**1.01 J**	0.640 U	0.820 UJ	1.23 U	0.369 U
(split)		01/14/20[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/17/20[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		03/24/20[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/27/20[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/28/20	Bladder	–	–	–	–	0.735 U	0.745 U	0.665 U	0.790 U	0.900 U	0.500 U	0.940 U	0.710 U	0.820 U	1.19 U	0.520 U
		05/19/20[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/22/20	Bladder	–	–	–	–	0.400 U	0.220 U	0.312 U	0.706 U	0.540 U	0.460 U	**1.72 J**	0.560 U	0.500 U	4.08 U	0.920 U
		07/28/20[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		09/17/20[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/02/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.727**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		12/03/20[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/10/21[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/03/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
HMW-1IB	SDOT Mercer Parcels,	03/25/19[a]	Peristaltic	100 U	200 U	500 U	500 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–
	NE quadrant	03/10/20[a]	Unknown	100 U	60 U	300 U	300 U	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	0.040 UJ	–
HMW-2IB	SDOT Mercer Parcels,	03/25/19[a]	Peristaltic	100 U	200 U	500 U	500 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–
	NE quadrant	03/12/20[a]	Unknown	100 U	51 U	260 U	260 U	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	0.030 UJ	–
HMW-4IA	SDOT Mercer Parcels,	03/25/19[a]	Peristaltic	100 U	200 U	500 U	500 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–
	SW quadrant	03/10/20[a]	Unknown	100 U	50 U	250 U	250 U	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	0.040 UJ	–
HMW-5IB	SDOT Mercer Parcels,	03/17/20[a]	Unknown	100 U	50 U	250 U	250 U	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	0.030 UJ	–
	SW quadrant																	
HMW-6IB	SDOT Mercer Parcels,	03/13/20[a]	Unknown	100 U	**83 J**	250 U	**83 J**	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	0.040 UJ	–
	SW quadrant																	
HMW-7IB	SDOT Mercer Parcels,	03/12/20[a]	Unknown	100 U	52 U	260 U	260 U	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	0.030 UJ	–
	SW quadrant																	
HMW-8IB	SDOT Mercer Parcels,	03/11/20[a]	Unknown	100 U	50 U	250 U	250 U	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	0.040 UJ	–
	SW quadrant																	

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	–	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	–	–	–	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	–	–	–	**410**
HMW-9IB	SDOT Mercer Parcels, SW quadrant	03/19/20[a]	Unknown	**580 J**	**60 J**	250 U	**60 J**	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	**13**	0.20 U	0.20 U	0.040 UJ	–
		01/26/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.0340 J**	**6.03 J+**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		06/02/21	Bladder	–	–	–	–	2.00 U	1.10 U	1.56 U	3.53 U	2.70 U	2.30 U	**5.30 J**	2.80 U	2.50 U	20.4 U	4.60 U
HMW-11IB	SDOT Mercer Parcels, SE quadrant	03/16/20[a]	Unknown	100 U	**74 J**	250 U	**74 J**	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	0.030 UJ	–
MW111	Alley E of Seattle Roy Aloha Shops	03/23/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		06/14/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/06/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/23/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/22/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/15/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/14/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/16/20	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/23/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 UJ	0.237 U	0.104 U
		07/06/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.232**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/02/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.358**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/09/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.121**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		05/03/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.0420 J**	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW112	Dexter Ave N ROW, W side	03/22/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		06/16/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/12/18	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		12/21/18	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/22/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/16/19	Bladder	31.7 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/21/19	Bladder	**96.6 J**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/24/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		05/07/20	Bladder	31.6 U	–	–	–	0.147 U	0.149 U	0.133 UJ	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 UJ	0.104 U
		07/27/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/17/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/11/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/14/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW126	Alley E of Seattle Roy Aloha Shops	03/28/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		06/15/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/06/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/22/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/29/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/18/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/15/19	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 UJ	0.186 UJ	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
(dup)		10/15/19	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 UJ	0.186 UJ	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/14/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 UJ	0.247 U	**0.199 J**
		04/09/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	**–**	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**–**	**–**	**–**	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	**–**	**–**	**–**	**410**
MW126		07/24/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 UJ	0.0460 U
(continued)		11/09/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/10/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 UJ	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 UJ
		05/04/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
	(dup)	05/04/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW130	Property,	03/29/17	Bladder	**8,890 zJ+**	–	–	–	2.40 U	1.88 U	2.60 U	3.72 U	3.28 U	2.28 U	**102**	2.56 U	3.28 U	4.94 U	1.48 U
	NW quadrant	06/30/17	Bladder	**10,300 zJ+**	–	–	–	1.20 U	0.940 U	1.30 U	1.86 U	1.64 U	1.14 U	**94.3**	1.28 U	1.64 U	2.47 U	0.739 U
	(dup)	06/30/17	Bladder	**15,000 zJ+**	–	–	–	1.20 U	0.940 U	1.30 U	1.86 U	1.64 U	1.14 U	**85.0**	1.28 U	1.64 U	2.47 U	0.739 U
		05/21/18	Bladder	**19,700 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**124**	0.128 U	0.164 U	0.247 U	**0.502**
		12/17/18	Bladder	**16,400 zJ+**	–	–	–	6.00 U	4.70 U	6.50 U	9.30 U	8.20 U	5.70 U	**124**	6.40 U	8.20 U	12.4 U	3.70 U
		01/31/19	Bladder	**22,400 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**130**	0.128 U	0.164 U	0.247 U	**0.622**
	Decommissioned March, 2019																	
MW-132	Property,	09/25/17	Bladder	95.9 U	–	–	–	0.600 U	0.470 U	0.650 U	0.930 U	0.820 U	0.570 U	0.940 U	0.640 U	0.820 U	1.24 U	0.370 U
	SE quadrant	04/26/18	Bladder	**2,630 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**18.1**	0.128 U	0.164 U	0.247 U	0.0739 U
		10/25/18	Peristaltic	48.3 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		12/13/18	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.450 J**	0.128 U	0.164 U	0.247 U	0.0739 U
		01/31/19	Peristaltic	**104 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.366 J**	0.128 U	0.164 U	0.247 U	0.0739 U
		03/11/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	Decommissioned March, 2019																	
MW-134	Property,	09/22/17	Bladder	–	–	–	–	0.600 U	0.470 U	0.650 U	0.930 U	0.820 U	0.570 U	0.940 U	0.640 U	0.820 U	1.24 U	0.370 U
	NE quadrant	04/16/18	Peristaltic	42.1 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/25/18	Bladder	38.2 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		12/12/18	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/28/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 UJ
		03/12/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	Decommissioned March, 2019																	
MW-135	Property,	09/25/17	Bladder	**10,900 zJ+**	–	–	–	12.0 U	9.40 U	13.0 U	18.6 U	16.4 U	11.4 U	**87.2**	12.8 U	16.4 U	24.7 U	7.39 U
	NE quadrant	04/25/18	Peristaltic	**347,000 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	**0.512**	**188**	0.128 U	0.164 U	0.247 U	**1.12**
		10/25/18	Peristaltic	**31,800 zJ+**	–	–	–	3.00 U	2.35 U	3.25 U	4.65 U	4.10 U	2.85 U	**167**	3.20 U	4.10 U	6.18 U	1.85 U
		12/13/18	Peristaltic	**80,000 zJ+**	–	–	–	6.00 U	4.70 U	6.50 U	9.30 U	8.20 U	5.70 U	**240**	6.40 U	8.20 U	12.4 U	3.70 U
		01/31/19	Bladder	**42,700 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	**0.396 J**	**225 J**	0.128 U	0.164 U	0.247 U	**1.08 J**
		03/13/19	Bladder	**32,700 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	**0.347 J**	**173**	0.128 U	0.164 U	0.247 U	**1.07**
	Decommissioned March, 2019																	
MW-136	Property,	09/25/17	Bladder	55.2 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	SW quadrant	04/16/18	Submersible	**256**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188	0.128 U	0.164 U	0.247 U	**4.40**
		10/29/18	Bladder	31.9 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		12/13/18	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		02/01/19	Bladder	44.5 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		03/12/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	(dup)	03/12/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	Decommissioned March, 2019																	
MW-139	Property,	09/25/17	Bladder	62.2 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	SE quadrant	04/25/18	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/25/18	Peristaltic	47.4 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		12/12/18	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	**–**	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**–**	**–**	**–**	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	**–**	**–**	**–**	**410**
MW-139		01/28/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 UJ
(continued)		03/11/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	Decommissioned March, 2019																	
MW-143	8th Ave N ROW,	04/30/18	Peristaltic	**154**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.342 J**	0.128 U	0.164 U	0.247 U	**0.192 J**
	E side	01/29/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 UJ
		04/24/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/19/19	Bladder	**31.6**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/16/19	Bladder	**2,000 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**8.47**	0.128 U	0.164 U	0.247 U	0.0739 U
		01/22/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/24/20	Bladder	88.2 U	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/29/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/24/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.589**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		02/08/21	Peristaltic	–	–	–	–	1.00 U	0.550 U	0.780 U	1.77 U	1.35 U	1.15 U	**6.60**	1.40 U	1.25 U	10.2 U	2.30 U
		05/19/21	Bladder	–	–	–	–	1.00 U	0.550 U	0.780 U	1.77 U	1.35 UJ	1.15 U	**7.15**	1.40 U	1.25 U	10.2 U	2.30 U
MW-145	8th Ave N ROW,	04/27/18	Bladder	52.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	E side	01/29/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 UJ
		04/26/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	Decommissioned December 2019																	
MW-145R	8th Ave N ROW,	12/16/19	Bladder	**140 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	E side	01/21/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/02/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		08/03/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/23/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/05/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/12/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-147	Roy St ROW,	05/01/18	Bladder	**484 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**4.59**	0.128 U	0.164 U	0.247 U	0.0739 U
	S side	01/22/19	Bladder	**663 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**6.83**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/23/19	Bladder	**139 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.75**	0.128 U	0.164 U	0.247 U	0.0739 U
		07/18/19	Bladder	**175 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.33**	0.128 U	0.164 U	0.247 U	1.48 U
	(dup)	07/18/19	Bladder	**170 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.30**	0.128 U	0.164 U	0.247 U	0.0739 U
		10/14/19	Bladder	**513 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.92**	0.128 U	0.164 U	0.247 U	0.0739 U
		01/24/20	Bladder	**1,200 zJ+**	–	–	–	3.00 U	2.35 U	3.25 U	4.65 U	4.10 U	2.85 U	4.70 U	3.20 U	4.10 U	6.17 U	1.85 U
		04/29/20	Bladder	**1,150 zJ+**	–	–	–	3.68 U	3.73 U	3.33 U	3.95 U	4.50 U	2.50 U	4.70 U	3.55 U	4.10 U	5.93 U	2.60 U
		07/09/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	**0.0510 J**	**4.11**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/10/20	Bladder	**2,930 zJ+**	–	–	–	2.00 U	1.10 U	1.56 U	3.53 U	2.70 U	2.30 U	2.00 UJ	2.80 U	2.50 U	20.4 U	4.60 U
	(split)	11/10/20	Bladder	100 U	50.0 U	250 U	250 U	500 U	500 U	500 U	500 U	–	500 U	500 U	500 U	500 U	500 U	–
		02/09/21	Bladder	–	–	–	–	1.00 U	0.550 U	0.780 U	1.77 U	1.35 U	1.15 U	**3.20 J**	1.40 U	1.25 U	10.2 U	2.30 U
		05/04/21	Bladder	–	–	–	–	2.00 U	1.10 U	1.56 UJ	3.53 U	2.70 U	2.30 U	2.00 U	2.80 U	2.50 UJ	20.4 U	4.60 U
MW-148	Roy St ROW,	05/01/18	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
(dup)	S side	05/01/18	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/23/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/26/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/22/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/16/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	–	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	–	–	–	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	–	–	–	**410**
MW-148		01/20/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
(continued)		04/30/20	Bladder	**36.8 J**	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/15/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/11/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-150	Property,	04/10/18	Peristaltic	**7,040 z**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**36.9**	0.128 U	0.164 U	0.247 U	0.0739 U
	NW quadrant	10/25/18	Peristaltic	**14,600 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**61.9**	0.128 U	0.164 U	0.247 U	**0.317 J**
		12/12/18	Peristaltic	**17,500 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**74.5**	0.128 U	0.164 U	0.247 U	0.0739 U
		01/29/19	Peristaltic	**11,900 zJ+**	–	–	–	12.0 U	9.40 U	13.0 U	18.6 U	16.4 U	11.4 U	**35.9 J**	12.8 U	16.4 U	24.7 U	7.39 UJ
		03/13/19	Peristaltic	**7,540 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**19.1**	0.128 U	0.164 U	0.247 U	0.0739 U
	Decommissioned March, 2019				–	–	–											
MW-152	Property,	04/10/18	Peristaltic	**40,600 z**	–	–	–	2.40 U	1.88 U	2.60 U	3.72 U	3.28 U	2.28 U	**107**	2.56 U	3.28 U	4.94 U	**1.91 J**
	SW quadrant	10/26/18	Peristaltic	**36,700 zJ+**	–	–	–	6.00 U	4.70 U	6.50 U	9.30 U	8.20 U	5.70 U	**86.9**	6.40 U	8.20 U	12.4 U	3.70 U
		12/14/18	Peristaltic	**47,300 zJ+**	–	–	–	3.00 U	2.35 U	3.25 U	4.65 U	4.10 U	2.85 U	**108 J+**	3.20 U	4.10 U	6.18 U	1.85 U
		01/31/19	Peristaltic	**44,300 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**86.3**	0.128 U	0.164 U	0.247 U	**0.932**
		03/12/19	Peristaltic	**55,900 zJ+**	–	–	–	3.00 U	2.35 U	3.25 U	4.65 U	4.10 U	2.85 U	**112**	3.20 U	4.10 U	6.18 U	1.85 U
	Decommissioned March, 2019																	
MW-157	8th Ave N ROW,	04/26/18	Peristaltic	**65.7 J**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	E side	01/24/19	Peristaltic	**1,870 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**16.7**	0.128 U	0.164 U	0.247 U	0.0739 UJ
		04/24/19	Peristaltic	**3,210 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**11.7**	0.128 U	0.164 U	0.247 U	0.0739 U
		07/22/19	Bladder	**3,880 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**17.5**	0.128 U	0.164 U	0.247 U	0.0739 U
		10/16/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/20/20	Bladder	**1,650 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**7.81**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/24/20	Bladder	**756 zJ+**	–	–	–	2.94 U	2.98 U	2.66 U	3.16 U	3.60 UJ	2.00 U	3.76 U	2.84 U	3.28 U	4.74 U	2.08 U
		07/15/20	Bladder	–	–	–	–	0.400 U	0.220 U	0.312 U	0.706 U	0.540 U	0.460 U	**3.28**	0.560 U	0.500 U	4.08 U	0.920 U
		11/23/20	Bladder	–	–	–	–	0.400 U	0.220 U	0.312 U	0.706 U	0.540 U	0.460 U	**15.6 J+**	0.560 U	0.500 UJ	4.08 U	0.920 U
MW-190	Valley Street ROW,	10/14/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	S side	01/23/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/02/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		08/04/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/18/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.0430 J**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/03/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/14/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-303	Dexter Ave N ROW,	10/21/19	Submersible	**99.6 J**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	E side	01/24/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		05/07/20	Bladder	**41.5 J**	–	–	–	0.147 U	0.149 U	0.133 UJ	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 UJ	0.104 U
		07/27/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/17/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/18/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 UJ	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-307	Roy St ROW,	10/11/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	S side	01/15/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/28/20	Bladder	**146 zJ+**	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/29/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	**–**	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**–**	**–**	**–**	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	**–**	**–**	**–**	**410**
MW-307		11/06/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
(continued)		05/18/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 UJ	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-309	Alley E of Seattle	10/14/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	Roy Aloha Shops	01/16/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/08/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/06/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.0430 J**	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/06/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/04/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.0300 J**	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-311	Alley E of Seattle	10/10/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.665**	0.128 U	0.164 U	0.247 U	0.0739 U
	Roy Aloha Shops	01/14/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.281 J**	0.128 U	0.164 UJ	0.247 U	0.0739 U
		04/23/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 UJ	0.237 U	0.104 U
		07/16/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	**0.0450 J**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/04/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/03/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-314	Alley E of Seattle	10/10/19	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**3.21**	0.128 U	0.164 U	0.247 U	0.0739 U
	Roy Aloha Shops	01/15/20	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**2.74**	0.128 U	0.164 U	0.247 U	0.0739 U
(dup)		01/15/20	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**2.95**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/22/20	Bladder	–	–	–	–	1.47 U	1.49 U	1.33 U	1.58 U	1.80 U	1.00 U	**4.90 J**	1.42 U	1.64 U	2.37 U	1.04 U
		07/16/20	Bladder	–	–	–	–	2.00 U	1.10 U	1.56 UJ	3.53 U	2.70 U	2.30 U	**9.60 J**	2.80 U	2.50 U	20.4 U	4.60 U
		11/04/20	Bladder	–	–	–	–	2.00 U	1.10 U	1.56 U	3.53 U	2.70 U	2.30 U	**13.6**	2.80 U	2.50 UJ	20.4 U	4.60 U
		05/03/21	Bladder	–	–	–	–	1.00 U	0.550 U	0.780 U	1.77 U	1.35 U	1.15 U	1.00 U	1.40 U	1.25 U	10.2 U	2.30 U
MW-316	Mercer St ROW,	10/02/19	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	N side	01/16/20	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/21/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/24/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/02/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/17/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 UJ	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-318	9th Ave N ROW,	10/08/19	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	**0.490 J**	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	W side	01/16/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	**0.521**	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/27/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	**0.222 J**	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/30/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.0964 J**	0.0200 UJ	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/12/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		05/19/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 UJ	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-322	9th Ave N ROW,	10/07/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.23**	0.128 U	0.164 U	0.247 U	0.0739 U
	W side	01/21/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**7.05**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/29/20	Bladder	–	–	–	–	14.7 U	14.9 U	13.3 U	15.8 U	18.0 U	10.0 U	18.8 U	14.2 U	16.4 U	23.7 U	10.4 U
		07/07/20	Bladder	–	–	–	–	0.200 U	0.110 U	0.156 U	0.353 U	0.270 U	**0.700 J**	**9.85**	0.280 U	0.250 U	2.04 U	0.460 U
		11/24/20	Bladder	–	–	–	–	0.200 U	0.110 U	0.156 U	0.353 U	0.270 U	**0.510 J**	**3.17**	0.280 U	0.250 U	2.04 U	0.460 U
		05/19/21	Peristaltic	–	–	–	–	0.200 U	0.110 U	0.156 U	0.353 U	0.270 UJ	**0.640 J**	**4.04**	0.280 U	0.250 U	2.04 U	0.460 U
MW-334	900 Roy St,	04/24/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
	S end	07/07/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	**–**	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**–**	**–**	**–**	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	**–**	**–**	**–**	**410**
MW-334		11/05/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
(continued)		05/13/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-335	Mercer St ROW, N side	05/01/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	**0.726**	0.142 U	0.164 U	0.237 U	0.104 U
		07/08/20	Bladder	–	–	–	–	0.200 U	0.110 U	0.156 UJ	0.353 U	0.270 U	0.230 U	0.200 U	0.280 U	0.250 U	2.04 U	0.460 U
		11/02/20	Bladder	–	–	–	–	0.200 U	0.110 U	0.156 U	0.353 U	0.270 U	0.230 U	**2.02**	0.280 U	0.250 UJ	2.04 U	0.460 U
		02/10/21	Bladder	–	–	–	–	0.200 U	0.110 U	0.156 U	0.353 UJ	0.270 U	0.230 U	**1.93**	0.280 U	0.250 U	2.04 U	0.460 UJ
		05/26/21	Peristaltic	–	–	–	–	0.200 U	0.110 U	0.156 U	0.353 U	0.270 U	0.230 U	0.200 U	0.280 U	0.250 U	2.04 U	0.460 U
MW-338	Lake Union Park, N end	05/07/20	Peristaltic	–	–	–	–	0.147 U	0.149 U	0.133 UJ	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 UJ	0.104 U
		07/23/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/10/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		05/04/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-340	Lake Union Park, S end	05/12/20	Peristaltic	–	–	–	–	0.147 U	0.149 U	0.133 UJ	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 UJ	0.237 U	0.104 U
		07/17/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/09/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/13/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-345	SDOT Mercer Parcels,	06/01/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-346	SDOT Mercer Parcels,	06/02/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.0590 J**	0.0280 U	0.0250 U	0.204 U	0.0460 U
(dup)	NW quadrant	06/02/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.0610 J**	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-347	SDOT Mercer Parcels,	06/01/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.147**	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-348	SDOT Mercer Parcels,	06/01/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.0940 J**	**1.29**	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-349	SDOT Mercer Parcels,	06/01/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-350	SDOT Mercer Parcels,	06/01/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	**20.9 J**
W-MW-01	8th Ave N ROW, W side	03/30/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		06/19/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/13/18	Bladder	37.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/29/18	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		12/13/18	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/25/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		03/11/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/25/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/23/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/15/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 UJ	0.186 UJ	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/27/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/03/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/31/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 UJ	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/24/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.0630 J**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/03/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.0320 J**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/17/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.0480 J**	0.0280 U	0.0250 U	0.204 U	0.0460 U
W-MW-02	8th Ave N ROW, W side	03/27/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		06/19/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	**–**	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**–**	**–**	**–**	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	**–**	**–**	**–**	**410**
W-MW-02		06/12/18	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
(continued)		10/26/18	Peristaltic	90.2 UJ	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
(dup)		10/26/18	Peristaltic	**246 J+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	**0.181**	0.247 U	0.0739 U
		12/12/18	Peristaltic	158 UJ	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/25/19	Peristaltic	**37.4 J**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		03/11/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/23/19	Peristaltic	**429 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.96**	0.128 U	0.164 U	0.247 U	0.0739 U
		07/23/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/18/19	Bladder	316 U	–	–	–	0.120 U	0.0940 UJ	0.130 U	0.186 U	0.164 UJ	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/28/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/01/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 UJ	0.247 U	0.0739 U
		07/31/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 UJ	0.0280 U	0.0250 U	0.204 U	0.0460 U
Deep Water-Bearing Zone																		
FMW-129	SDOT Mercer Parcels,	04/10/17	Peristaltic	–	–	–	–	–	0.470 U	0.650 U	0.930 U	0.820 U	0.570 U	**4.86**	0.640 U	0.820 U	1.24 U	0.370 U
	NE quadrant	06/23/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.37**	0.128 U	0.164 U	0.247 U	0.0739 U
		05/01/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.26**	0.128 U	0.164 U	0.247 U	0.0739 U
		07/16/19	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.69**	0.128 U	0.164 U	0.247 U	0.0739 U
		10/21/19	Peristaltic	**141 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.62**	0.128 U	0.164 U	0.247 U	0.0739 U
		11/12/19[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/14/20	Bladder	–	–	–	–	1.20 U	0.940 U	1.30 U	1.86 U	1.64 U	1.14 U	1.88 U	1.28 U	1.64 UJ	2.47 U	0.739 U
(split)		01/14/20[v]	Bladder	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/18/20[p]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		03/25/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/27/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/06/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	**0.589**	0.142 U	0.164 U	0.237 U	0.104 U
		05/19/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/10/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.331**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		07/28/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		09/17/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/10/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.219**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		12/03/20[p]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/10/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 UJ	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 UJ
(split)		02/10/21[v]	Peristaltic	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/26/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**2.11**	0.0280 U	0.0250 U	0.204 U	0.0460 U
(dup)		05/26/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**2.27**	0.0280 U	0.0250 U	0.204 U	0.0460 U
FMW-131	Block 37,	03/24/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	SE quadrant	06/23/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		12/18/17[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/22/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/21/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/22/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 UJ	0.247 U	0.0739 U
		04/29/20	Peristaltic	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/30/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 UJ	0.0280 U	0.0250 U	0.204 U	0.0460 U
		08/26/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	–	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	–	–	–	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	–	–	–	**410**
FMW-131 (continued)		11/19/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.0680 J**	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		12/04/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/11/21[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/12/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	**0.0400 J**	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/13/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.0270 J**	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
FMW-137	Alley E of Block 38 West	11/20/18[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		12/28/18[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/06/19[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/08/19[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		10/14/19[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/06/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 UJ	0.0739 U
		11/11/19[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/22/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 UJ	0.247 U	0.0739 U
		05/06/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/31/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 UJ	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/24/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/12/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	**0.0350 J**	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		06/02/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.0390 J**	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
FMW-138	Alley E of Block 38 West	11/20/18[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		12/28/18[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/6/19[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/8/19[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		10/14/19[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/11/19[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
FMW-3D	Terry Ave N ROW, E side	03/24/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		06/23/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
FMW-140	900 Roy St, S end	07/17/19[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		10/31/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 UJ	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		11/12/19[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/14/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/22/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	**0.510**	**1.19**	0.128 U	0.164 UJ	0.247 U	0.0739 U
		02/18/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		03/25/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/27/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/28/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	**0.370 J**	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		05/19/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/07/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.703**	**0.0780 J**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		07/29/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		09/17/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/13/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.279**	0.0200 UJ	0.0280 U	0.0250 U	0.204 U	0.0460 U
		12/04/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/10/21[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/18/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 UJ	**0.146**	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	**–**	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**–**	**–**	**–**	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	**–**	**–**	**–**	**410**
GEI-2	Block 37, NW quadrant	03/24/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		06/23/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		12/29/18[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/22/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/16/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/21/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		11/11/19[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/14/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/22/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 UJ	0.247 U	0.0739 U
		02/17/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		03/25/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/27/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/29/20	Peristaltic	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		05/19/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		06/29/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/29/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/30/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 UJ	0.0280 U	0.0250 U	0.204 U	0.0460 U
		08/26/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		09/17/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/19/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.0240 J**	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		12/04/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/11/21[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/12/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/13/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
HMW-1D	SDOT Mercer Parcels, NE quadrant	03/25/19[a]	Peristaltic	100 U	200 U	500 U	500 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–
		03/09/20[a]	Unknown	**140**	**94 J**	250 U	**94 J**	20 U	20 U	20 U	20 U	–	20 U	20 U	20 U	20 U	4.0 UJ	–
HMW-2D	SDOT Mercer Parcels, NE quadrant	03/25/19[a]	Peristaltic	100 U	200 U	500 U	500 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–
		03/12/20[a]	Unknown	100 U	**86 J**	250 U	**86 J**	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	0.03 UJ	–
HMW-3D	SDOT Mercer Parcels, NW quadrant	03/25/19[a]	Peristaltic	100 U	200 U	500 U	500 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 UJ	–
		03/13/20[a]	Unknown	100 U	**480 J**	250 U	**480 J**	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	0.04 UJ	–
HMW-6D	SDOT Mercer Parcels, SW quadrant	03/16/20[a]	Unknown	100 U	50 U	250 U	250 U	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	0.03 UJ	–
HMW-9D	SDOT Mercer Parcels, SW quadrant	03/17/20[a]	Unknown	100 U	**230 J**	250 U	**230 J**	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	0.03 UJ	–
HMW-10D	SDOT Mercer Parcels, SE quadrant	03/16/20[a]	Unknown	100 U	50 U	250 U	250 U	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	0.03 UJ	–
MW102	Valley Street ROW, S side	03/29/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		06/15/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/25/18	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/24/19	Bladder	31.6 U	**–**	**–**	**–**	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 UJ
		05/01/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/18/19	Bladder	31.6 U	**–**	**–**	**–**	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	–	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	–	–	–	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	–	–	–	**410**
MW102		11/14/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
(continued)		01/23/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
(dup)		01/23/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/02/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		08/04/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
(dup)		08/04/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/18/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/03/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/14/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW103	Alley E of Seattle	03/23/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	**0.195 J**	**3.69**	0.128 U	0.164 U	0.247 U	0.0739 U
	Roy Aloha Shops	06/14/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.98**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/06/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.396 J**	0.128 U	0.164 U	0.247 U	0.0739 U
		01/23/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/22/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.22**	0.128 U	0.164 U	0.247 U	0.0739 U
		07/15/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.36**	0.128 U	0.164 U	0.247 U	0.0739 U
		10/14/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.08**	0.128 U	0.164 U	0.247 U	0.0739 U
		01/16/20	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.479 J**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/23/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	**0.305 J**	0.142 U	0.164 UJ	0.237 U	0.104 U
(dup)		04/23/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	**0.291 J**	0.142 U	0.164 UJ	0.237 U	**0.272 J**
		07/06/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.169**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/02/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.111**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/10/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 UJ	0.0270 U	0.0230 U	**0.190**	0.0280 U	0.0250 U	0.204 U	0.0460 UJ
		05/03/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.554**	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW104	8th Ave N ROW,	03/30/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	W side	06/30/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.387 J**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/09/18	Peristaltic	**81.3 J**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.16**	0.128 U	0.164 U	0.247 U	0.0739 U
		10/26/18	Bladder	**1,570 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.374 J**	0.128 U	0.164 U	0.247 U	0.0739 U
		12/13/18	Bladder	**54.0 J**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.16**	0.128 U	0.164 U	0.247 U	0.0739 U
		02/01/19	Bladder	**191 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.415 J**	0.128 U	0.164 U	0.247 U	0.0739 U
		03/13/19	Bladder	**124 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**4.72**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/23/19	Bladder	**174 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**5.86**	0.128 U	0.164 U	0.247 U	0.0739 U
		07/22/19	Bladder	**50.4 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**5.38**	0.128 U	0.164 U	0.247 U	0.0739 U
		10/18/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 UJ	0.130 U	0.186 U	0.164 UJ	0.114 U	**0.799**	0.128 U	0.164 U	0.247 U	0.0739 U
		01/29/20	Bladder	**447 ZJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.02**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/01/20	Bladder	92.4 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**6.47**	0.128 U	0.164 UJ	0.247 U	0.0739 U
		07/31/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**2.45 J**	0.0280 U	0.0250 U	0.204 U	0.0460 U
(dup)		07/31/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**2.46 J**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/17/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**2.80**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/10/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 UJ	0.0270 U	0.0230 U	**2.34**	0.0280 U	0.0250 U	0.204 U	0.0460 UJ
MW105	Roy Street ROW,	04/21/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	S side	06/14/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/11/18	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.225 J**	0.128 U	0.164 U	0.247 U	0.0739 U
		01/23/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/23/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	–	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	–	–	–	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	–	–	–	**410**
MW105		07/17/19	Bladder	37.8 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
(continued)		10/22/19	Bladder	**96.4 J**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
(dup)		10/22/19	Bladder	**90.8 J**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/20/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		05/12/20	Bladder	**52.7 J**	–	–	–	0.147 U	0.149 U	0.133 UJ	0.158 U	0.180 U	0.100 U	**0.194 J**	0.142 U	0.164 UJ	0.237 U	0.104 U
		07/27/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.539**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/17/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.961**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/11/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 UJ	0.0270 U	0.0230 U	**1.07**	0.0280 U	0.0250 U	0.204 U	0.0460 UJ
		06/07/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**1.50**	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW106	SDOT Mercer Parcels, NW quadrant	04/14/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		06/30/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		05/04/18	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/26/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/19/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/18/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 UJ	0.130 U	0.186 U	0.164 UJ	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/14/20	Bladder	33.1 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 UJ	0.247 U	0.0739 U
		05/06/20	Bladder	**32.3 J**	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
(dup)		05/06/20	Bladder	**48.8 J**	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/10/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/10/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
(dup)		11/10/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		02/12/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
(dup)		02/12/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/13/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW113	9th Ave N ROW, W side	03/22/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**10.7**	0.128 U	0.164 U	0.247 U	0.0739 U
		06/16/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	**0.474 J**	**5.93**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/11/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**7.83**	0.128 U	0.164 U	0.247 U	0.0739 U
		01/30/19	Peristaltic	–	–	–	–	0.600 U	0.470 U	0.650 U	0.930 U	0.620 U	0.570 U	**8.61**	0.640 U	0.820 U	1.24 U	0.370 UJ
		02/07/19	Peristaltic	**3,100 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	**0.141 J**	**9.92**	0.128 U	0.164 U	0.247 U	0.0739 U
		07/17/19	Peristaltic	**2,560 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**3.40**	0.128 U	0.164 U	0.247 U	0.0739 U
		10/22/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.78**	0.128 U	0.164 U	0.247 U	0.0739 U
		11/11/19[p]	Peristaltic	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/14/20	Bladder	–	–	–	–	1.20 U	0.940 U	1.30 U	1.86 U	1.64 U	1.14 U	**15.0**	1.28 U	1.64 UJ	2.47 U	0.739 U
(split)		01/14/20[v]	Peristaltic	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/18/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		03/24/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/27/20	Peristaltic	–	–	–	–	14.7 U	14.9 U	13.3 U	15.8 U	18.0 U	10.0 U	18.8 U	14.2 U	16.4 U	23.7 U	10.4 U
(split)		04/27/20[v]	Peristaltic	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/19/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/28/20	Bladder	–	–	–	–	14.7 U	14.9 U	13.3 U	15.8 U	18.0 UJ	10.0 U	18.8 U	14.2 U	16.4 U	23.7 U	10.4 U
(split)		07/28/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		09/17/20[p]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/24/20	Bladder	–	–	–	–	2.00 U	1.10 U	1.56 U	3.53 U	2.70 U	2.30 U	**3.00 J**	2.80 U	2.50 U	20.4 U	4.60 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	**–**	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**–**	**–**	**–**	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	**–**	**–**	**–**	**410**
MW113		12/03/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(continued)		02/10/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	**0.0630 J**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
(split)		02/10/21[o]	Peristaltic	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/25/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.999**	**4.28**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
MW122	Alley E of Seattle Roy Aloha Shops	03/28/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		06/14/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/06/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/14/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/17/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/07/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/24/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/06/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		05/03/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW123	Westlake Ave N ROW, W side	04/01/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		06/24/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/14/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	**0.159 J**	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/18/19	Peristaltic	–	–	–	–	0.120 U	0.0940 UJ	0.130 U	0.186 U	0.164 UJ	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/22/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 UJ	0.247 U	0.0739 U
		05/05/20	Peristaltic	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 UJ	0.237 U	0.104 U
		07/30/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.102**	0.0200 UJ	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/12/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.103**	0.0200 UJ	0.0280 U	0.0250 U	0.204 U	0.0460 U
		05/26/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW124	Valley Street ROW, S side	03/29/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
(dup)		03/29/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		06/15/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/13/18	Bladder	39.4 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/11/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/30/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/03/20	Bladder	38.9 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		08/03/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 UJ	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/18/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		06/08/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
MW128	Westlake Ave N ROW, E side	03/29/17	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		06/21/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/09/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		12/30/18[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/18/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/11/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
(dup)		10/11/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		11/11/19[o]	Peristaltic	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/20/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		02/18/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	**–**	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**–**	**–**	**–**	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	**–**	**–**	**–**	**410**
MW128		04/27/20	Peristaltic	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
(continued)		06/29/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.0730 J**	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
(split)		06/29/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		08/26/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/09/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.0570 J**	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		12/20/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/11/21[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/25/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-133	Property,	09/25/17	Bladder	41.2 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.87**	0.128 U	0.164 U	0.247 U	0.0739 U
	SW quadrant	04/25/18	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.899**	0.128 U	0.164 U	0.247 U	0.0739 U
		10/26/18	Bladder	**458 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.619**	0.128 U	0.164 U	0.247 U	0.0739 U
		12/12/18	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.67**	0.128 U	0.164 U	0.247 U	0.0739 U
		02/01/19	Bladder	46.4 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.94**	0.128 U	0.164 U	0.247 U	0.0739 U
		03/13/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.33**	0.128 U	0.164 U	0.247 U	0.0739 U
	Decommissioned March, 2019																	
MW-137	Property,	09/25/17	Bladder	58.5 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	SW quadrant	04/12/18	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/26/18	Bladder	86.9 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		12/12/18	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		02/01/19	Bladder	58.4 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		03/11/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	Decommissioned March, 2019																	
MW-138	Dexter Ave N ROW,	09/21/17	Bladder	**63.3 J**	–	–	–	0.240 U	0.188 U	0.260 U	0.372 U	0.328 U	0.228 U	0.376 U	0.256 U	0.328 U	0.494 U	0.148 U
	E side	04/11/18	Bladder	91.1 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/29/18	Bladder	38.5 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		12/17/18	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/03/19	Bladder	31.6 U	1.05 U	–	1.05 U	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		03/14/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/22/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/19/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/21/19	Bladder	**92.7 J**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/27/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		05/08/20	Bladder	53.4 U	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/27/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/18/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/11/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		06/07/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-140	Roy Street ROW,	09/22/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.226 J**	0.128 U	0.164 U	0.247 U	0.0739 U
(dup)	E side	09/22/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.211 J**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/12/18	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.355 J+**	0.128 U	0.164 U	0.247 U	0.0739 U
MW-141	Property,	09/22/17	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	SE quadrant	04/12/18	Submersible	**326 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.389 J+**	0.128 U	0.164 U	0.247 U	0.0739 U
		10/25/18	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		12/12/18	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	**–**	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**–**	**–**	**–**	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	**–**	**–**	**–**	**410**
MW-141		01/30/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 UJ
(continued)		03/11/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	Decommissioned March, 2019																	
MW-153	Roy St ROW,	05/01/18	Bladder	**31.6 J**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	S side	01/22/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/24/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	(dup)	04/24/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/22/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	**0.139 J**
		10/15/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/21/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/30/20	Bladder	**38.2 J**	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/15/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/09/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/09/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
	(dup)	02/09/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		05/10/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-158A	8th Ave N ROW,	04/30/18	Bladder	**101**	–	–	–	–	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.189 J**	0.128 U	0.164 U	0.247 U	0.0739 U
	E side	01/24/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 UJ
		04/25/19	Bladder	31.6 U	–	–	–	–	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/19/19	Bladder	31.6 U	–	–	–	–	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/16/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/21/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/24/20	Bladder	38.0 U	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/15/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/23/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/02/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/10/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-160	8th Ave N ROW,	05/21/18	Bladder	**51.0 J**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	W side	01/25/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		05/01/19	Bladder	31.6 U	–	–	–	–	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/23/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/17/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/29/20	Bladder	35.0 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/01/20	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 UJ	0.247 U	0.0739 U
		08/03/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.316**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/30/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.483**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		02/05/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.302 J**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/12/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.119**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
MW-161	8th Ave N ROW,	05/21/18	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.779**	0.128 U	0.164 U	0.247 U	0.0739 U
	W side	01/25/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.489 J**	0.128 U	0.164 U	0.247 U	0.0739 U
		05/01/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.517**	0.128 U	0.164 U	0.247 U	0.0739 U
		07/18/19	Bladder	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.609**	0.128 U	0.164 U	0.247 U	0.0739 U
		10/14/19	Bladder	54.7 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.451 J**	0.128 U	0.164 U	0.247 U	0.0739 U
		01/28/20	Bladder	72.8 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.33**	0.128 U	0.164 UJ	0.247 U	0.0739 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	–	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	–	–	–	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	–	–	–	**410**
MW-161		04/03/20	Bladder	49.3 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**2.67**	0.128 U	0.164 U	0.247 U	0.0739 U
(continued)		07/31/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**2.97 J**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		12/01/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**4.27**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		02/05/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**5.03 J**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/25/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**2.94**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
MW-162	Property,	02/05/19	Bladder	–	–	–	–	1.00 U	1.00 U	1.00 U	1.00 U	–	1.00 U	**4.23**	1.00 U	4.00 U	1.00 U	1.00 U
	NE quadrant	03/12/19	Peristaltic	**690 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**2.39**	0.128 U	0.164 U	0.247 U	0.0739 U
	Decommissioned March, 2019																	
MW-163	Property, NW quadrant	02/05/19	Bladder	–	–	–	–	1.00 U	1.00 U	1.00 U	1.00 U	–	1.00 U	**9.12**	1.00 U	4.00 U	1.00 U	1.00 U
	(dup)	02/05/19	Bladder	–	–	–	–	1.00 U	1.00 U	1.00 U	1.00 U	–	1.00 U	**9.31**	1.00 U	4.00 U	1.00 U	1.00 U
		03/12/19	Bladder	**319 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**14.1**	0.128 U	0.164 U	0.247 U	0.0739 U
	Decommissioned March, 2019																	
MW-164	Property,	02/05/19	Bladder	–	–	–	–	1.00 U	1.00 U	1.00 U	1.00 U	–	1.00 U	**8.74**	1.00 U	4.00 U	1.00 U	1.00 U
	SW quadrant	03/12/19	Bladder	**565 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**8.58**	0.128 U	0.164 U	0.247 U	0.0739 U
	Decommissioned March, 2019																	
MW-304	Dexter Ave N ROW,	10/21/19	Bladder	**97.9 J**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	E side	01/27/20	Bladder	42.2 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		05/07/20	Bladder	31.6 U	–	–	–	0.147 U	0.149 U	0.133 UJ	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 UJ	0.104 U
		07/27/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		05/18/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 UJ	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-319	9th Ave N ROW,	10/08/19	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	**0.641**	**0.292 J**	0.128 U	0.164 U	0.247 U	0.0739 U
	W side	01/16/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	**0.667**	**0.281 J**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/27/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	**0.438 J**	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/27/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.246**	**0.138**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/12/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.176**	**0.143**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		05/19/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 UJ	**0.270**	**0.156**	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-323	9th Ave N ROW,	10/09/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.276 J**	0.128 U	0.164 U	0.247 U	0.0739 U
	W side	01/20/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.12**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/23/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/07/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.0670 J**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/24/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.0780 J**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/20/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.686**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
MW-324	Roy St ROW,	10/02/19	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.53**	0.128 U	0.164 U	0.247 U	0.0739 U
	N side	01/20/20	Peristaltic	–	–	–	–	6.00 U	4.70 U	6.50 U	9.30 U	8.20 U	5.70 U	9.40 U	6.40 U	8.20 U	12.3 U	3.69 U
		04/24/20	Bladder	–	–	–	–	7.35 U	7.45 U	6.65 U	7.90 U	9.00 U	5.00 U	9.40 U	7.10 U	8.20 U	11.9 U	5.20 U
		07/07/20	Bladder	–	–	–	–	1.00 U	0.550 U	0.780 U	1.77 U	1.35 U	1.15 U	**6.60**	1.40 U	1.25 U	10.2 U	2.30 U
		11/13/20	Bladder	–	–	–	–	1.00 U	0.550 U	0.780 U	1.77 U	1.35 U	1.15 U	**7.97 J-**	1.40 U	1.25 U	10.2 U	2.30 U
		05/20/21	Peristaltic	–	–	–	–	1.00 U	0.550 U	0.780 U	1.77 U	1.35 U	1.15 U	**6.05**	1.40 U	1.25 UJ	10.2 U	2.30 U
MW-326	Mercer Street ROW,	10/03/19	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	N side	01/17/20	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/21/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/23/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	**–**	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**–**	**–**	**–**	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	**–**	**–**	**–**	**410**
MW-326 (continued)		11/02/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/09/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		05/18/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 UJ	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-328	Lake Union Park, S end	10/02/19	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/17/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/08/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/07/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/09/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/25/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-329 (dup)	Westlake Ave N ROW, E side	10/03/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		10/03/19	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/20/20	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/27/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		08/03/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.0290 J**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/09/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.0440 J**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/25/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-336	Mercer St ROW, N side	05/05/20	Bladder	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 UJ	0.237 U	0.104 U
		07/08/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.139**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/02/20	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.203**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/10/21	Bladder	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 UJ	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 UJ
		05/26/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-341	Lake Union Park, S end	05/12/20	Peristaltic	–	–	–	–	0.147 U	0.149 U	0.133 UJ	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 UJ	0.237 U	0.104 U
		07/07/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.0840 J**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/09/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.0440 J**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/25/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
MW-342	Valley St ROW, S side	05/04/20	Peristaltic	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/30/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 UJ	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/17/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		06/04/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
MW-343	Valley St ROW, S side	05/04/20	Peristaltic	–	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/30/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 UJ	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/24/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		06/04/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
Treatment Zone A Wells																		
IW-4A	Property, NW quadrant Decommissioned March, 2019	03/28/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**8.95**	0.128 U	0.164 U	0.247 U	0.0739 U
IW-7A	Property, NE quadrant Decommissioned March, 2019	04/02/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
IW-9A	Property, NW quadrant Decommissioned March, 2019	03/29/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.85**	0.128 U	0.164 U	0.247 U	0.0739 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	**–**	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**–**	**–**	**–**	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	**–**	**–**	**–**	**410**
IW-18A	Property, NE quadrant Decommissioned March, 2019	03/30/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**12.9**	0.128 U	0.164 U	0.247 U	**0.372 J**
IW-22A	Property, NE quadrant Decommissioned March, 2019	04/02/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.07**	0.128 U	0.164 U	0.247 U	0.0739 U
IW-37A	Property, SW quadrant Decommissioned March, 2019	03/28/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
IW-41A	Property, SW quadrant Decommissioned March, 2019	04/10/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**1.48**	0.128 U	0.164 U	0.247 U	**0.157 J**
IW-42A	Property, SW quadrant Decommissioned March, 2019	04/10/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**13.7**	0.128 U	0.164 U	0.247 U	**0.930**
IW-45A	Property, SW quadrant Decommissioned March, 2019	04/04/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**19.6**	0.128 U	0.164 U	0.247 U	**0.289 J**
IW-46A	Property, SE quadrant Decommissioned March, 2019	03/28/18	Peristaltic		–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
IW-48A	Property, SE quadrant Decommissioned March, 2019	04/02/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
MW-165	Property, NE quadrant	11/04/19	Peristaltic	**3,940 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**8.92**	0.128 U	0.164 U	0.247 U	0.0739 U
		01/30/20	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		05/01/20	Peristaltic	**74.3 J**	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/09/20	Peristaltic	31.6 U	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	**0.253**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/05/20	Flowing	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.516**	0.0280 U	0.0250 U	0.204 U	0.0460 U
(dup)		11/05/20	Flowing	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.553**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		02/04/21	Flowing	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**1.19**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/06/21	Flowing	–	–	–	–	0.200 U	0.110 U	0.156 U	0.353 U	0.270 U	0.230 U	0.200 U	0.280 U	0.250 U	2.04 U	0.460 U
MW-169	Property, SW quadrant	11/05/19	Peristaltic	**83.4 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.197 J**	0.128 U	0.164 U	0.247 U	0.0739 U
		01/23/20	Peristaltic	158 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		05/05/20	Peristaltic	158 U	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/10/20	Peristaltic	**2,400 zJ+**	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/03/20	Flowing	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/17/21	Flowing	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		05/07/21	Flowing	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
MW-173	Property, SE quadrant	11/01/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/28/20	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		05/01/20	Peristaltic	31.6 U	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	**–**	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**–**	**–**	**–**	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	**–**	**–**	**–**	**410**
MW-173		07/09/20	Peristaltic	31.6 U	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
(continued)		11/05/20	Flowing	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		02/04/21	Flowing	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/05/21	Flowing	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
MW-177	Property, SW quadrant	11/06/19	Peristaltic	**127,000 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**268**	0.128 U	0.164 U	247 UJ	**1.96**
		01/24/20	Peristaltic	**89,400 zJ+**	–	–	–	6.00 U	4.70 U	6.50 U	9.30 U	8.20 U	5.70 U	**120**	6.40 U	8.20 U	12.3 U	3.69 U
		04/01/20	Peristaltic	**77,100 zJ+**	–	–	–	600 U	470 U	650 U	930 U	820 U	570 U	940 U	640 U	820 UJ	1,230 U	370 U
		07/10/20	Peristaltic	**92,500 zJ+**	–	–	–	100 U	55.0 U	78.0 U	177 U	135 U	115 U	100 U	140 U	125 U	1,020 U	230 U
		11/03/20	Flowing	–	–	–	–	20.0 U	11.0 U	15.6 U	35.3 U	27.0 U	23.0 U	20.0 U	28.0 U	25.0 U	204.0 U	46.0 U
		02/18/21	Flowing	–	–	–	–	4.00 U	2.20 U	3.12 U	7.06 U	5.40 U	4.60 U	**34.4**	5.60 U	5.00 UJ	40.8 U	9.20 U
		05/06/21	Flowing	–	–	–	–	4.00 U	2.20 U	3.12 UJ	7.06 U	5.40 U	4.60 U	**38.2**	5.60 U	5.00 UJ	40.8 U	9.20 U
MW-181	Property, SW quadrant	11/08/19	Peristaltic	**23,900 zJ+**	–	–	–	0.120 U	0.470 U	0.130 U	0.186 U	0.820 U	0.570 U	**116**	0.128 U	0.164 U	123 UJ	0.369 U
		01/27/20	Peristaltic	**9,090 zJ+**	–	–	–	60.0 U	47.0 U	65.0 U	93.0 U	82.0 U	57.0 U	94.0 U	64.0 U	82.0 U	123 U	36.9 U
		04/01/20	Peristaltic	**12,200 zJ+**	–	–	–	60.0 U	47.0 U	65.0 U	93.0 U	82.0 U	57.0 U	94.0 U	64.0 U	82.0 UJ	123 U	36.9 U
		07/08/20	Peristaltic	**15,400 zJ+**	–	–	–	10.0 U	5.50 U	7.80 U	17.7 U	13.5 U	11.5 U	**31.0 J**	14.0 U	12.5 U	102 U	23.0 U
		11/04/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**8.27**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/19/21	Flowing	–	–	–	–	2.00 U	1.10 U	1.56 U	3.53 U	2.70 U	2.30 U	**9.60 J**	2.80 U	2.50 UJ	20.4 U	4.60 U
		05/06/21	Peristaltic	–	–	–	–	2.00 U	1.10 U	1.56 UJ	3.53 U	2.70 U	2.30 U	**12.2**	2.80 U	2.50 UJ	20.4 U	4.60 U
MW-185	Property, SE quadrant	10/31/19	Flowing	**446 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 UJ	0.186 U	0.164 U	0.114 U	**0.897**	0.128 U	0.164 U	0.247 U	0.0739 U
		01/29/20	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 UJ	0.247 U	0.0739 U
		04/02/20	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/08/20	Peristaltic	56.3 U	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/04/20	Flowing	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/16/21	Flowing	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		05/07/21	Flowing	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.0390 J**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
Treatment Zone B Wells																		
IW-3B	Property, NW quadrant Decommissioned March, 2019	03/28/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**9.84**	0.128 U	0.164 U	0.247 U	0.0739 U
IW-6B	Property, SW quadrant Decommissioned March, 2019	04/02/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**12.2**	0.128 U	0.164 U	0.247 U	0.0739 U
IW-8B	Property, SW quadrant Decommissioned March, 2019	03/30/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
IW-17B	Property, NE quadrant Decommissioned March, 2019	03/30/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**184**	0.128 U	0.164 U	0.247 U	**1.05**
IW-21B	Property, NE quadrant Decommissioned March, 2019	04/02/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**14.3**	0.128 U	0.164 U	0.247 U	0.0739 U
IW-22B	Property, NW quadrant Decommissioned March, 2019	04/25/18	Peristaltic	–	–	–	–	2.40 U	1.88 U	2.60 U	3.72 U	3.28 U	2.28 U	**62.7**	2.56 U	3.28 U	4.94 U	1.48 U
IW-24B	Property, NE quadrant Decommissioned March, 2019	03/30/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**149 J**	0.128 U	0.164 U	0.247 U	**1.61 J+**
IW-28B	Property, NW quadrant Decommissioned March, 2019	04/09/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	–	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	–	–	–	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	–	–	–	**410**
IW-33B	Property, NE quadrant Decommissioned March, 2019	04/02/18	Peristaltic	–	–	–	–	0.120 U	1.88 U	0.130 U	0.186 U	0.164 U	0.114 U	**49.7**	0.128 U	0.164 U	0.247 U	0.0739 U
IW-37B	Property, SW quadrant Decommissioned March, 2019	03/29/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**4.56**	0.128 U	0.164 U	0.247 U	0.0739 U
IW-45B	Property, SE quadrant Decommissioned March, 2019	03/28/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.641**	0.128 U	0.164 U	0.247 U	0.0739 U
IW-47B	Property, SW quadrant Decommissioned March, 2019	04/10/18	Bladder	–	–	–	–	0.600 U	0.470 U	0.650 U	0.930 U	0.820 U	0.570 U	**92.7**	0.640 U	0.820 U	1.24 U	0.370 U
IW-49B	Property, SE quadrant Decommissioned March, 2019	03/28/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**3.52**	0.128 U	0.164 U	0.247 U	0.0739 U
IW-51B	Property, SE quadrant Decommissioned March, 2019	03/28/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
MW-166	Property, NE quadrant	11/04/19	Peristaltic	**4,360 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**7.81**	0.128 U	0.164 U	0.247 U	0.0739 U
		01/30/20	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		05/01/20	Peristaltic	**49.1 J**	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/09/20	Peristaltic	31.6 U	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.0420 J**	0.0280 U	0.0250 U	0.204 U	0.0460 U
(dup)		07/09/20	Peristaltic	31.6 U	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/05/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**9.04**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		02/04/21	Flowing	–	–	–	–	10.0 U	5.50 U	7.80 U	17.7 U	13.5 U	11.5 U	**19.0 J**	14.0 U	12.5 UJ	102 U	23.0 U
		05/05/21	Flowing	–	–	–	–	4.00 U	2.20 U	3.12 U	7.06 U	5.40 U	4.60 U	4.00 U	5.60 U	5.00 U	40.8 U	9.20 U
MW-170	Property, SW quadrant	11/05/19	Peristaltic	**22,700 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**73.1**	0.128 U	0.164 U	0.247 U	**0.315 J**
		01/23/20	Peristaltic	**20,000 zJ+**	–	–	–	3.00 U	2.35 U	3.25 U	4.65 U	4.10 U	2.85 U	**63.6**	3.20 U	4.10 U	6.17 U	1.85 U
		04/02/20	Peristaltic	**17,000 zJ+**	–	–	–	60.0 U	47.0 U	65.0 U	93.0 U	82.0 U	57.0 U	94.0 U	64.0 U	82.0 U	123 U	36.9 U
		07/09/20	Peristaltic	**24,300 zJ+**	–	–	–	0.200 U	0.110 U	0.156 UJ	0.353 U	0.270 U	0.230 U	**82.9**	0.280 U	0.250 U	2.04 U	0.460 U
		11/03/20	Peristaltic	–	–	–	–	0.200 U	0.110 U	0.156 U	0.353 U	0.270 U	0.230 U	**30.7**	0.280 U	0.250 UJ	2.04 U	0.460 U
		02/17/21	Peristaltic	–	–	–	–	0.200 U	0.110 U	0.156 U	0.353 U	0.270 U	0.230 U	**18.7**	0.280 U	0.250 U	2.04 U	0.460 U
		05/07/21	Peristaltic	–	–	–	–	10.0 U	5.50 U	7.80 U	17.7 U	13.5 U	11.5 U	**15.5 J**	14.0 U	12.5 UJ	102 U	23.0 U
MW-174	Property, SE quadrant	11/01/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/28/20	Peristaltic	**531 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		05/01/20	Peristaltic	**51.1 J**	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/09/20	Peristaltic	31.6 U	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/05/20	Flowing	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		02/04/21	Flowing	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/05/21	Flowing	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
MW-178	Property, SW quadrant	11/06/19	Peristaltic	**249 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	4.94 UJ	0.0739 U
		01/24/20	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/02/20	Peristaltic	31.7 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 UJ	0.247 U	0.0739 U
		07/10/20	Peristaltic	**66.6 zJ+**	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/03/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**4.54**	0.0280 U	0.0250 UJ	0.204 U	**0.0670 J**
		02/18/21	Peristaltic	–	–	–	–	0.400 U	0.220 U	0.312 U	0.706 U	0.540 U	0.460 U	**3.02**	0.560 U	0.500 U	4.08 U	0.920 U
		05/06/21	Peristaltic	–	–	–	–	0.400 U	0.220 U	0.312 UJ	0.706 U	0.540 U	0.460 U	**3.66**	0.560 U	0.500 UJ	4.08 U	0.920 U
MW-182	Property, SW quadrant	11/08/19	Peristaltic	**14,100 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**15.0**	0.128 U	0.164 U	123 UJ	**0.506**
		01/27/20	Peristaltic	**2,420 zJ+**	–	–	–	60.0 U	47.0 U	65.0 U	93.0 U	82.0 U	57.0 U	94.0 U	64.0 U	82.0 U	123 U	36.9 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	**–**	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**–**	**–**	**–**	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	**–**	**–**	**–**	**410**
MW-182		04/01/20	Peristaltic	**1,760 zJ+**	–	–	–	6.00 U	4.70 U	6.50 U	9.30 U	8.20 U	5.70 U	9.40 U	6.40 U	8.20 U	12.3 U	3.69 U
(continued)		07/08/20	Peristaltic	**1,000 zJ+**	–	–	–	1.00 U	0.550 U	0.780 U	1.77 U	1.35 U	1.15 U	**2.45 J**	1.40 U	1.25 U	10.2 U	2.30 U
		11/04/20	Peristaltic	–	–	–	–	1.00 U	0.550 U	0.780 U	1.77 U	1.35 U	1.15 U	**72.3**	1.40 U	1.25 UJ	10.2 U	2.30 U
		02/19/21	Peristaltic	–	–	–	–	10.0 U	5.50 U	7.80 U	17.7 U	13.5 U	11.5 U	**163**	14.0 U	12.5 U	102 U	23.0 U
		05/06/21	Peristaltic	–	–	–	–	40.0 U	22.0 U	31.2 U	70.6 U	54.0 U	46.0 U	**92.0 J**	56.0 U	50.0 UJ	408 U	92.0 UJ
(dup)		05/06/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	**98.5**	0.0280 U	0.0250 UJ	0.204 U	**3.62 J**
MW-186	Property, SE quadrant	10/31/19	Flowing	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 UJ	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/29/20	Peristaltic	42.7 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/02/20	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/08/20	Peristaltic	54.3 U	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	**0.0660 J**
		11/04/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/16/21	Flowing	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		05/07/21	Flowing	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
Treatment Zone C Wells																		
IW-1C	Property, NE quadrant Decommissioned March, 2019	03/29/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
IW-4C	Property, NE quadrant Decommissioned March, 2019	04/26/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**9.35**	0.128 U	0.164 U	0.247 U	**0.311 J**
IW-8C	Property, NE quadrant Decommissioned March, 2019	04/04/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**11.3**	0.128 U	0.164 U	0.247 U	**0.712**
IW-9C	Property, NE quadrant Decommissioned March, 2019	04/02/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**55.4**	0.128 U	0.164 U	0.247 U	0.0739 U
IW-13C	Property, SW quadrant Decommissioned March, 2019	04/25/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**4.12 J**	0.128 U	0.164 U	0.247 U	0.0739 U
IW-15C	Property, SW quadrant Decommissioned March, 2019	03/30/18	Bladder	–	–	–	–	1.20 U	0.940 U	1.30 U	1.86 U	1.64 U	1.14 U	**103**	1.28 U	1.64 U	2.47 U	0.739 U
IW-19C	Property, SW quadrant Decommissioned March, 2019	03/29/18	Peristaltic	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.201 J**	0.128 U	0.164 U	0.247 U	0.0739 U
IW-20C	Property, SW quadrant	03/30/18	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**64.8**	0.128 U	0.164 U	0.247 U	0.0739 U
(dup)	Decommissioned March, 2019	03/30/18	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	**0.143 J**	**69.0**	0.128 U	0.164 U	0.247 U	0.0739 U
MW-167	Property, NE quadrant	11/04/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/28/20	Peristaltic	57.8 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 UJ	0.247 U	0.0739 U
		05/01/20	Peristaltic	**68.3 J**	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/09/20	Peristaltic	31.6 U	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/05/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		02/04/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/05/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
MW-171	Property, SW quadrant	11/05/19	Peristaltic	**371 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.923**	0.128 U	0.164 U	0.247 U	0.0739 U
		01/23/20	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/02/20	Peristaltic	35.3 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/09/20	Peristaltic	31.6 U	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	**–**	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**–**	**–**	**–**	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	**–**	**–**	**–**	**410**
MW-171		11/03/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.0330 J**	**0.180**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
(continued)		02/17/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.0290 J**	**7.56**	0.0280 U	0.0250 U	0.204 U	0.0460 U
(dup)		02/17/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**7.50**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		05/07/21	Peristaltic	–	–	–	–	1.00 U	0.550 U	0.780 U	1.77 U	1.35 U	1.15 U	**9.60**	1.40 U	1.25 UJ	10.2 U	2.30 U
MW-175	Property,	11/01/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.661**	0.128 U	0.164 U	0.247 U	0.0739 U
	SE quadrant	01/28/20	Peristaltic	66.5 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 UJ	0.247 U	0.0739 U
		05/01/20	Peristaltic	**65.8 J**	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/09/20	Peristaltic	31.6 U	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/05/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		02/04/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/05/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
MW-179	Property,	11/06/19	Peristaltic	**2,310 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	**0.148 J**	**13.0**	0.128 U	0.164 U	24.7 UJ	0.0739 U
	SW quadrant	01/27/20	Peristaltic	**501 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**2.51**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/02/20	Peristaltic	**424 zJ+**	–	–	–	2.40 U	1.88 U	2.60 U	3.72 U	3.28 U	2.28 U	3.76 U	2.56 U	3.28 UJ	4.94 U	1.48 U
		07/10/20	Peristaltic	**924 zJ+**	–	–	–	0.400 U	0.220 U	0.312 U	0.706 U	0.540 U	0.460 U	**2.06**	0.560 U	0.500 U	4.08 U	0.920 U
		11/03/20	Peristaltic	–	–	–	–	0.400 U	0.220 U	0.312 U	0.706 U	0.540 U	0.460 U	**24.3**	0.560 U	0.500 UJ	4.08 U	0.920 U
		02/18/21	Peristaltic	–	–	–	–	10.0 U	5.50 U	7.80 U	17.7 U	13.5 U	11.5 U	**170**	14.0 U	12.5 U	102 U	23.0 U
		05/06/21	Peristaltic	–	–	–	–	5.00 U	2.75 U	3.90 U	8.83 U	6.75 U	5.75 U	5.00 U	7.00 U	6.25 U	51.0 U	11.5 U
MW-183	Property,	11/08/19	Peristaltic	**45.0 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 UJ	0.0739 U
	SW quadrant	01/27/20	Peristaltic	41.5 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/02/20	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/08/20	Peristaltic	76.2 U	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/04/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**3.48**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/19/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**16.2**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		05/06/21	Peristaltic	–	–	–	–	2.00 U	1.10 U	1.56 U	3.53 U	2.70 U	2.30 U	**10.5**	2.80 U	2.50 U	20.4 U	4.60 U
MW-187	Property,	11/01/19	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	SE quadrant	01/29/20	Peristaltic	39.3 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/02/20	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/08/20	Peristaltic	55.6 U	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	**0.0710 J**
		11/04/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/16/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		05/07/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
Treatment Zone D Wells																		
IW-1D	Property, NE quadrant	04/03/18	Bladder	–	–	–	–	1.20 U	0.940 U	1.30 U	1.86 U	1.64 U	1.14 U	**98.8**	1.28 U	1.64 U	2.47 U	0.739 U
	Decommissioned March, 2019																	
IW-3D	Property, NE quadrant	04/03/18	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	**0.168 J**	**61.5**	0.128 U	0.164 U	0.247 U	**0.145 J**
	Decommissioned March, 2019																	
IW-4D	Property, SW quadrant	03/29/18	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	Decommissioned March, 2019																	
IW-6D	Property, SW quadrant	04/03/18	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
	Decommissioned March, 2019																	

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	–	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	–	–	–	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	–	–	–	**410**
IW-8D	Property, SW quadrant Decommissioned March, 2019	04/04/18	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**50.3**	0.128 U	0.164 U	0.247 U	**0.201 J**
IW-9D	Property, SW quadrant Decommissioned March, 2019	04/04/18	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**30.8**	0.128 U	0.164 U	0.247 U	0.0739 U
IW-11D	Property, NE quadrant Decommissioned March, 2019	05/01/18	Bladder	–	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**18.0**	0.128 U	0.164 U	0.247 U	0.0739 U
MW-168	Property, NE quadrant	11/04/19	Peristaltic	**65.0 J**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/31/20	Flowing	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 UJ	0.247 U	0.0739 U
		05/01/20	Peristaltic	**76.0 J**	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/09/20	Peristaltic	31.6 U	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/05/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		02/04/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/05/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
MW-172	Property, SW quadrant	11/05/19	Flowing	**4,960 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	**0.305 J**	**32.0**	0.128 U	0.164 U	0.247 U	0.0739 U
		01/23/20	Flowing	**10,700 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	**0.330 J**	**50.6**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/02/20	Peristaltic	**5,310 zJ+**	–	–	–	60.0 U	47.0 U	65.0 U	93.0 U	82.0 U	57.0 U	94.0 U	64.0 U	82.0 U	123 U	36.9 U
		07/09/20	Peristaltic	**4,430 zJ+**	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	**0.270**	**66.1**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/03/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.309**	**85.5**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/17/21	Flowing	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	**0.137**	**89.8**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		05/07/21	Peristaltic	–	–	–	–	2.00 U	1.10 U	1.56 U	3.53 U	2.70 U	2.30 U	**27.8**	2.80 U	2.50 UJ	20.4 U	4.60 U
MW-176	Property, SE quadrant	11/01/19	Flowing	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/28/20	Flowing	48.0 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/28/20	Flowing	74.7 U	–	–	–	0.120 U	0.0940 UJ	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		05/01/20	Peristaltic	**83.5 J**	–	–	–	0.147 U	0.149 U	0.133 U	0.158 U	0.180 U	0.100 U	0.188 U	0.142 U	0.164 U	0.237 U	0.104 U
		07/09/20	Peristaltic	31.6 U	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/05/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		02/04/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		05/05/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
MW-180	Property, SW quadrant	11/06/19	Flowing	**220 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.940 U	0.128 U	0.164 U	1.23 UJ	0.0739 U
		01/24/20	Peristaltic	**186 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**0.293 J**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/01/20	Peristaltic	69.1 U	–	–	–	0.600 U	0.470 U	0.650 U	0.930 U	0.820 U	0.570 U	0.940 U	0.640 U	0.820 UJ	1.23 U	0.369 U
		07/10/20	Peristaltic	**122 zJ+**	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.163**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/03/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**0.468**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/18/21	Flowing	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**2.59**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		05/06/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	**2.14**	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
MW-184	Property, SW quadrant	11/08/19	Flowing	**2,310 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**16.0**	0.128 U	0.164 U	24.7 UJ	0.0739 U
		01/27/20	Flowing	**462 zJ+**	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	**6.84**	0.128 U	0.164 U	0.247 U	0.0739 U
		04/01/20	Peristaltic	**212 zJ+**	–	–	–	1.20 U	0.940 U	1.30 U	1.86 U	1.64 U	1.14 U	1.88 U	1.28 U	1.64 U	2.47 U	0.739 U
		07/08/20	Peristaltic	**260 zJ+**	–	–	–	0.0200 U	0.0110 U	0.0156 UJ	0.0353 U	0.0270 U	0.0230 U	**3.41**	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/04/20	Peristaltic	–	–	–	–	0.200 U	0.110 U	0.156 U	0.353 U	0.270 U	0.230 U	**3.77**	0.280 U	0.250 UJ	2.04 U	0.460 U
		02/19/21	Flowing	–	–	–	–	0.200 U	0.110 U	0.156 U	0.353 U	0.270 U	0.230 U	**19.2**	0.280 U	0.250 UJ	2.04 U	0.460 U
		05/06/21	Peristaltic	–	–	–	–	0.100 U	0.0550 U	0.0780 U	0.177 U	0.135 U	0.115 U	**1.82**	0.140 U	0.125 U	1.02 U	0.230 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Gasoline Range Organics (GRO)	Diesel Range Organics (DRO)	Heavy Oil (ORO)	DRO + ORO	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane (1,1,1-TCA)	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane (CFC 113)	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,3-Trimethylbenzene
Preliminary Cleanup Level (PCUL)				**800**	**500**	**500**	**500**	**1.7**	**200**	**0.22**	**3.0**	**240,000**	**7.7**	**7.0**	**–**	**6.4**	**0.00038**	**80**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**–**	**–**	**–**	**7.1**	**5,500**	**6.2**	**4.6**	**180**	**11**	**130**	**–**	**–**	**–**	**410**
MW-188	Property, SE quadrant	10/31/19	Flowing	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 UJ	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		01/29/20	Flowing	31.9 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		04/02/20	Peristaltic	31.6 U	–	–	–	0.120 U	0.0940 U	0.130 U	0.186 U	0.164 U	0.114 U	0.188 U	0.128 U	0.164 U	0.247 U	0.0739 U
		07/08/20	Peristaltic	61.9 U	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		11/04/20	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
		02/16/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 U	0.204 U	0.0460 U
		05/07/21	Peristaltic	–	–	–	–	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.0280 U	0.0250 UJ	0.204 U	0.0460 U
			Number of Analytes Measured	518	50	49	50	1,265	1,270	1,270	1,270	1,221	1,270	1,270	1,270	1,270	1,270	1,225
			Number of Analytes Detected	196	16	0	16	0	13	0	0	17	86	394	0	2	0	61
			Frequency of Detection	38%	32%	0%	32%	0%	1%	0%	0%	1%	7%	31%	0%	0.2%	0%	5%
			Maximum Detection	2,320 J+	790 J	–	790 J	–	0.302 J	–	–	0.631	2.60	268	–	0.456	–	119
			Minimum Detection	31.6 U	1.05 U	250 U	1.05 U	0.0200 U	0.0110 U	0.0156 U	0.0353 U	0.0270 U	0.0230 U	0.0200 U	0.028 U	0.0250 U	0.030 UJ	0.0460 U
			Number of Detections Above SL	4	4	0	4	0	0	0	0	0	0	125	–	0	0	2
			Frequency of Detection Above SL	1%	8%	0%	8%	0%	0%	0%	0%	0%	0%	10%	–	0%	0%	0.2%

Notes:

Gasoline Range Organics Analyzed by NWTPH-Gx.

Diesel Range Organics and Heavy Oil analyzed by NWTPH-Dx.

VOCs analyzed by EPA Method 8260C or 8260D.

Results shown in micrograms per liter (µg/L).

PCULs and Screening Levels from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021.

All groundwater sampling performed by PES Environmental, Inc. unless otherwise indicated.

a = Results provided by Hart Crowser.

b = Results provided by Farallon Consulting.

c = Select sample results for MW-210 incorrectly identified with location SMW-3 on lab reports and sampling forms.

(split) = Split samples collected consecutively.

(dup) = Field duplicate sample.

– = Not analyzed, results not available, or information not applicable.

Detected results shown in **bold.**

Detections above the groundwater PCUL level are shown in **bold and highlighted in gray.**

Shallow Zone detections above the groundwater screening level for soil vapor are shown in **bold and highlighted in orange.**

Shallow Zone detections above the groundwater PCUL and screening level for soil vapor are shown in **bold highlighted in grayish-orange.**

U = Not detected at or above the laboratory method detection limit (MDL); detections above the MDL but below the laboratory reported detection limit (RDL) are qualified with a "J."

J = The identification of the analyte is acceptable; the reported value is an estimate.

J+ = The result is an estimated quantity, but the result may be biased high.

J- = The result is an estimated quantity, but the result may be biased low.

z = Elevated chlorinated VOCs detected within the GRO elution range. No discernible petroleum pattern present. Project level qualifier assigned per laboratory review.

GRO results above the screening level and qualified with "z" are not considered in the Maximum Detection and are not included in the Number of Detections Above SL.

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
Shallow Water Bearing Zone																			
DMW-1S	615 Dexter, SE quadrant	03/25/19[a]	Unknown	1.0 U	1.0 U	1.0 U	0.01 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	–	1.0 U
		03/25/19[a]	Unknown	1.0 U	1.0 U	1.0 U	0.01 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	–	1.0 U
		03/18/20[a]	Unknown	–	**0.44**	0.80 UJ	–	0.20 U	–	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	–	0.20 U
DMW-2S	615 Dexter, SE quadrant	03/18/20[a]	Unknown	–	0.20 U	0.80 UJ	–	0.20 U	–	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	–	0.20 U
DMW-4S	Alley S of SE quadrant of 615 Dexter	03/19/20[a]	Unknown	–	**7.1**	0.80 UJ	–	0.20 U	–	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	–	0.20 U
DMW-5IA	Alley S of 615 Dexter	03/19/20[a]	Unknown	–	0.20 U	0.80 UJ	–	0.20 U	–	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	–	0.20 U
DMW-6	615 Dexter, NE quadrant	03/18/20[a]	Unknown	–	0.20 U	0.80 UJ	–	0.20 U	–	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	–	0.20 U
F5	Property, NW quadrant Decommissioned March, 2019	03/28/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**93.1 J**	0.111 U	0.757 U	0.0972 U
		06/22/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**41.2**	0.111 U	0.757 U	0.0972 U
F9	Property, NE quadrant Decommissioned March, 2019	03/27/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/22/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
F13	Property, NE quadrant Decommissioned March, 2019	03/27/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/22/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/05/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
FMW-143	9th Ave N ROW, E side	07/30/19[a]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		10/31/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/22/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		05/14/20	Bladder	0.481 U	0.322 U	0.276 UJ	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/22/20	Bladder	0.193 U	**0.117 J**	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
G12	Property, NE quadrant Decommissioned March, 2019	03/27/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/30/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
HMW-1S	SDOT Mercer Parcels, NE quadrant	3/25/19[a]	Peristaltic	1.0 U	1.0 U	1.0 U	0.010 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	–	1.0 U
		03/11/20[a]	Unknown	–	0.20 U	0.11 UJ	–	0.20 U	–	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	–	0.20 U
HMW-2S	SDOT Mercer Parcels, NE quadrant	3/25/19[a]	Peristaltic	1.0 U	1.0 U	1.0 U	0.010 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	–	1.0 U
		03/12/20[a]	Unknown	–	0.20 U	0.80 UJ	–	0.20 U	–	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	–	0.20 U
HMW-9S	SDOT Mercer Parcels, SW quadrant	03/17/20[a]	Unknown	–	0.20 U	0.80 UJ	–	0.20 U	–	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	–	0.20 U
HMW-10S	SDOT Mercer Parcels, SE quadrant	03/16/20[a]	Unknown	–	0.20 U	0.80 UJ	–	0.20 U	–	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	–	0.20 U
HMW-11S	SDOT Mercer Parcels, SE quadrant	03/11/20[a]	Unknown	–	0.20 U	0.11 UJ	–	0.20 U	–	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	–	0.20 U
HMW-20S	SDOT Mercer Parcels, NW quadrant	9/18/20[a]	Unknown	1.0 U	0.20 U	3.0 U	1.0 U	0.20 U	1.0 U	0.20 U	1 U	0.20 U	0.20 U	0.20 U	0.20 U	20 UJ	0.20 U	–	0.20 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
HMW-21S	SDOT Mercer Parcels, SE quadrant	11/3/20[a]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
HMW-22S	SDOT Mercer Parcels, SE quadrant	11/3/20[a]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
J5	Property, SW quadrant	03/21/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/26/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/05/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	Decommissioned March, 2019																		
J15	Property, SE quadrant	03/27/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/26/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
(dup)		06/26/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/05/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	Decommissioned March, 2019																		
K8	Property, SW quadrant	03/21/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/26/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/05/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	Decommissioned March, 2019																		
M15	Property, SE quadrant	03/27/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
(dup)		03/27/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/26/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/05/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	Decommissioned March, 2019																		
MW-8	Seattle Roy Aloha Shops, N end	03/20/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/13/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/18/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/10/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	**0.253 J**	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		01/16/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		05/06/20	Peristaltic	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/14/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 UJ	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-9	8th Ave N ROW, E side	03/20/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/20/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 UJ	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
(dup)		06/20/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 UJ	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		04/05/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 UJ	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/21/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/26/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	**0.229 J**	**0.878**	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/16/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/17/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		11/24/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/05/21	Peristaltic	0.193 UJ	**0.0730 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/12/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/12/21	Peristaltic	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW121	8th Ave N ROW, E side	03/28/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		06/20/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 UJ	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		04/05/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
MW121		01/31/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
(continued)		04/29/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/19/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	**0.133 J**	0.147 U	0.121 U	0.0929 UJ	1.28 U	0.111 U	0.757 U	0.0972 U
		11/30/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/05/21	Peristaltic	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/12/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
	(dup)	05/12/21	Peristaltic	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW125	Valley Street ROW, N side	03/22/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/28/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/06/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/21/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/23/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/18/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 UJ	1.28 U	0.111 U	0.757 U	0.0972 U
		10/18/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/29/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		11/17/20	Bladder	0.193 U	**0.169 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 UJ	0.0368 U	–	0.0452 U
		02/02/21	Peristaltic	0.193 U	**0.0640 J**	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/11/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
	(dup)	05/11/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-154	Roy St ROW S side	04/30/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/21/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/24/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/15/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/14/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 UJ	0.0972 U
		01/21/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/30/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/10/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 UJ	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/09/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/08/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/10/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-155	Roy Street ROW, S side	04/27/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/21/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/23/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/23/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/16/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/20/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		05/05/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		08/03/20	Bladder	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 UJ	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/11/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-159	8th Ave N ROW, E side	04/26/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/21/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/26/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	(dup)	04/26/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
MW-159 (continued)		07/22/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/29/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		11/11/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/08/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/11/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-210[c]	Valley Street ROW, N side	03/30/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/21/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		04/09/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/11/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 UJ	0.0972 U
		01/17/20	Peristaltic	0.355 U	0.193 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/09/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/07/20	Peristaltic	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 UJ	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-214 (dup)	Valley Street ROW, S side	03/30/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		03/30/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/09/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/11/19	Peristaltic	0.355 U	**0.174 J**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 UJ	0.0972 U
		01/20/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**1.30 J**	0.111 U	0.757 U	0.0972 U
		04/07/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/06/20	Peristaltic	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	**0.0440 J**	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-301 (dup)	Valley Street ROW, S side	11/30/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/30/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/05/21	Bladder	0.193 UJ	**0.0970 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/14/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/14/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-305	Roy St ROW, S side	10/15/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 UJ	0.108 U	0.190 U	0.124 U	0.130 UJ	0.147 UJ	0.121 UJ	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/15/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/28/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/27/20	Bladder	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 UJ	0.0788 UJ	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/06/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/18/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	**0.0720 J**	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-310	Alley E of Seattle Roy Aloha Shops	10/10/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/14/20	Peristaltic	0.355 U	0.123 U	0.325 UJ	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/08/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		08/04/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		08/04/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/06/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/03/21	Peristaltic	0.193 U	**0.223**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-312	Alley E of Seattle Roy Aloha Shops	10/11/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 UJ	0.0972 U
		01/21/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/22/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		08/04/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/11/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	**0.563 J**	0.0368 U	–	0.0452 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
MW-312 (continued)		05/03/21	Peristaltic	0.193 U	**0.203**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-313	Alley E of Seattle Roy Aloha Shops	10/10/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/14/20	Bladder	0.355 U	0.123 U	0.325 UJ	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		05/04/21	Bladder	0.193 UJ	**0.106 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-320	9th Ave N ROW, W side	10/07/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/20/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/29/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/28/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 UJ	1.19 U	0.106 U	0.787 U	0.114 U
		11/12/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/20/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-332	Roy St ROW, N side	05/04/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 UJ	0.106 U	0.787 U	0.114 U
		07/30/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
		11/12/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/20/21	Peristaltic	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-337	Lake Union Park, N end	05/07/20	Peristaltic	0.481 U	0.322 UJ	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 UJ	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 UJ	0.787 U	0.114 UJ
		07/23/20	Peristaltic	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/10/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	**0.0500 J**	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/04/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-339 (dup)	Lake Union Park, S end	05/14/20	Peristaltic	0.481 U	0.322 U	0.276 UJ	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		05/14/20	Peristaltic	0.481 U	0.322 U	0.276 UJ	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/23/20	Peristaltic	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/09/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/25/21	Peristaltic	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
N7	Property, SW quadrant	03/30/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/27/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
	Decommissioned March, 2019																		
R-MW2	Property, NE quadrant	03/21/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/15/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	**0.199 J**	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/02/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	**0.141 J**	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	Decommissioned March, 2019																		
R-MW3	Property, NE quadrant	03/21/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/28/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/04/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	**0.144 J**	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	Decommissioned March, 2019																		
R-MW5	Dexter Ave N ROW, E side	03/23/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/16/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/11/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 UJ	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		01/03/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/22/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/16/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/21/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/24/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
R-MW5		11/18/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
(continued)		02/11/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
(dup)		02/11/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/17/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
R-MW6	8th Ave N ROW, E side	03/21/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/20/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 UJ	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		04/06/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/25/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/25/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		12/01/20	Peristaltic	0.193 U	**0.109 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	**0.665 J**	0.0368 U	–	0.0452 U
		02/03/21	Peristaltic	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/17/21	Peristaltic	0.193 U	0.0980 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
SCL-MW101	Alley E of Seattle Roy Aloha Shops	03/28/17	Peristaltic	0.355 U	**4.84**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/14/17	Peristaltic	0.355 U	**1.12**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	**0.185 J**	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/06/18	Peristaltic	0.355 U	**1.70**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/09/19	Peristaltic	0.355 U	**4.11**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	**0.379 J**	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/17/20	Peristaltic	0.355 U	**2.48**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.500 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/07/20	Peristaltic	0.355 U	**0.970**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	**0.149 J**	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	3.78 U	0.0972 U
		11/24/20	Peristaltic	0.193 U	**0.734**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	**0.290**	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	0.757 U	0.0452 U
		05/04/21	Peristaltic	0.193 U	**0.582**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	**0.164 J**	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
SCL-MW105	Alley E of Seattle Roy Aloha Shops	03/28/17	Peristaltic	1.78 U	0.615 U	1.62 U	0.965 U	0.505 U	0.540 U	0.950 U	**3.51**	0.650 U	0.735 U	0.605 U	0.464 U	6.40 U	0.555 U	0.757 U	0.486 U
		06/15/17	Peristaltic	0.355 U	**0.562**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	**3.45**	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/06/18	Peristaltic	3.55 U	1.23 U	3.25 U	1.93 U	1.01 U	1.08 U	1.90 U	**2.77 J**	1.30 U	1.47 U	1.21 U	0.929 U	12.8 U	1.11 U	7.57 U	0.972 U
		10/10/19	Peristaltic	0.355 U	**0.510**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	**5.00**	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/17/20	Peristaltic	0.355 U	0.477 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	**3.53**	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/01/20	Peristaltic	0.355 UJ	0.329 U	0.325 UJ	0.193 U	0.101 U	0.108 U	0.190 U	**2.50**	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/24/20	Peristaltic	0.193 U	**0.275**	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	**2.72**	0.0680 U	0.0700 UJ	0.0788 UJ	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
SCS-2	Seattle Roy Aloha Shops, N End	03/20/17	Peristaltic	0.355 U	**60.3**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	**5.36**	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/12/17	Peristaltic	0.355 U	**41.7**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	**2.83**	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/13/18	Peristaltic	0.355 U	**23.3**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	**2.65**	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		07/18/19	Peristaltic	0.355 U	**157**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	**12.8**	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
(dup)		07/18/19	Peristaltic	0.355 U	**145**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	**11.6**	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/10/19	Peristaltic	0.355 U	**130**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	**8.19**	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/16/20	Peristaltic	3.55 U	**11.5**	3.25 U	1.93 U	1.01 U	1.08 U	1.90 U	1.24 U	1.30 U	1.47 U	1.21 U	0.929 U	12.8 U	1.11 U	7.57 U	0.972 U
Intermediate A Water-Bearing Zone																			
BB-8	Roy Street ROW, S side	03/22/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/14/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/11/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 UJ	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
(dup)		04/11/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 UJ	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		01/23/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/23/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
BB-8		07/17/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
(continued)		10/22/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
(dup)		10/22/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/20/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
(dup)		01/20/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		05/12/20	Bladder	0.481 UJ	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/27/20	Bladder	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 UJ	0.0788 UJ	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
(dup)		07/27/20	Bladder	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 UJ	0.0788 UJ	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/17/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 UJ	0.0368 U	–	0.0452 U
		02/11/21	Peristaltic	0.193 U	**0.140 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		06/07/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	**0.433**	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
DMW-3IA	615 Dexter, NE quadrant	03/18/20[a]	Unknown	–	**0.39**	0.80 UJ	–	0.20 U	–	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	–	0.20 U
FMW-142	9th Ave N ROW, E side	07/29/19[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		10/31/19	Peristaltic	0.355 U	0.123 U	0.325 UJ	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		01/22/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/28/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/08/20	Bladder	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/04/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/25/21	Peristaltic	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
GEI-1	Block 37, SW quadrant	03/24/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/13/17	Bladder	0.355 U	**0.200 J**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/22/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/16/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/21/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		01/22/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/29/20	Peristaltic	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
(dup)		04/29/20	Peristaltic	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/30/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	**0.0432 J**	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
GEI-MW-1	Block 79 East, N end	01/23/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/29/20	Peristaltic	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		08/07/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/10/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/13/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
HC-4	601 Dexter, NE quadrant	04/12/19[a]	Unknown	1.0 U	1.0 U	1.0 U	0.01 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	–	1.0 U
HMW-2IA	SDOT Mercer Parcels, NE quadrant	03/25/19[a]	Peristaltic	1.0 U	1.0 U	1.0 U	0.010 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	–	1.0 U
		03/12/20[a]	Unknown	–	2.0 U	8.0 UJ	–	2.0 U	–	2.0 U	–	2.0 U	2.0 U	2.0 U	2.0 U	–	2.0 U	–	2.0 U
HMW-3IA	SDOT Mercer Parcels, NW quadrant	03/25/19[a]	Peristaltic	1.0 U	1.0 U	1.0 U	0.010 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	–	1.0 U
		03/13/20[a]	Unknown	–	**0.39**	0.80 UJ	–	0.20 U	–	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	–	0.20 U
HMW-6IA	SDOT Mercer Parcels, SW quadrant	03/13/20[a]	Unknown	–	0.20 U	0.80 UJ	–	0.20 U	–	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	–	0.20 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
HMW-9IA	SDOT Mercer Parcels, SW quadrant	03/19/20[a]	Unknown	–	0.20 U	0.80 UJ	–	0.20 U	–	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	–	0.20 U
		06/02/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	**0.185**	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
HMW-20IA	SDOT Mercer Parcels, NW quadrant	09/18/20[a]	Unknown	1.0 U	0.20 U	3.0 UJ	1.0 U	0.20 U	1.0 U	0.20 U	1.0 U	0.20 U	0.20 U	0.20 U	0.20 U	20 UJ	0.20 U	–	–
		06/02/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	**0.0270 J**	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW107	8th Ave N ROW, W side	03/27/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.787 U	0.0972 U
		06/19/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 UJ	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.787 U	0.0972 U
		04/09/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.787 U	0.0972 U
		01/30/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.787 U	0.0972 U
		05/01/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.787 U	0.0972 U
		07/22/19	Bladder	0.355 U	0.144 J	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.787 U	0.0972 U
		10/15/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.787 U	0.0972 U
		01/28/20	Bladder	7.10 U	2.46 U	6.50 U	3.86 U	2.02 U	2.16 U	3.80 U	2.48 U	2.60 U	2.94 U	2.42 U	1.86 U	25.6 U	2.22 U	15.1 U	1.94 U
		04/03/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 UJ	0.0929 U	1.28 UJ	0.111 U	–	0.0972 U
		07/31/20	Bladder	4.83 U	1.16 U	5.10 U	0.525 U	1.45 U	0.475 U	1.27 U	1.08 U	1.70 U	1.75 U	1.97 U	0.793 UJ	12.5 U	0.920 U	–	1.13 U
		12/01/20	Peristaltic	4.83 U	1.16 U	5.10 U	0.525 U	1.45 U	0.475 U	1.27 U	1.08 U	1.70 U	1.75 U	1.97 U	0.793 U	**32.9**	0.920 U	–	1.13 U
		02/02/21	Peristaltic	0.193 U	**0.130 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		06/02/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	**0.0640 J**	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW108	Alley E of Seattle Roy Aloha Shops	03/28/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/27/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		04/06/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
(dup)		04/06/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/22/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/29/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/15/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/10/19	Peristaltic	0.355 U	**0.392 J**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/14/20	Peristaltic	8.88 U	3.08 U	8.13 UJ	4.83 U	2.53 U	2.70 U	4.75 U	3.10 U	3.25 U	3.68 U	3.03 U	2.32 U	32.0 U	2.78 U	18.9 U	2.43 U
		04/22/20	Bladder	12.0 U	8.05 U	6.90 U	3.15 U	2.68 U	2.05 U	3.73 U	2.60 U	7.48 U	2.73 U	3.00 U	4.03 U	29.8 U	2.65 U	19.7 U	2.85 U
		07/16/20	Bladder	4.83 U	1.16 U	5.10 U	0.525 U	1.45 U	0.475 U	1.27 U	1.08 U	1.70 U	1.75 U	1.97 U	0.793 U	12.5 U	0.920 U	–	1.13 U
(dup)		07/16/20	Bladder	0.193 U	**0.0730 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	**0.229**	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/04/20	Bladder	4.83 U	1.16 U	5.10 U	0.525 U	1.45 U	0.475 U	1.27 U	1.08 U	1.70 U	1.75 U	1.97 U	0.793 U	12.5 U	0.920 U	–	1.13 U
		02/09/21	Peristaltic	0.965 U	0.232 U	1.02 U	0.105 U	0.290 U	0.0950 U	0.254 U	0.216 U	0.340 U	0.350 U	0.394 U	0.159 U	2.50 U	0.184 U	–	0.226 U
		05/03/21	Peristaltic	0.965 U	0.232 U	1.02 U	0.105 U	0.290 U	0.0950 U	0.254 U	0.216 U	0.340 U	0.350 U	0.394 U	0.159 U	2.50 U	0.184 U	–	0.226 U
MW109	Alley E of Seattle Roy Aloha Shops	03/29/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/27/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		04/06/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/23/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/29/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/15/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/15/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 UJ	0.108 U	0.190 U	0.124 U	0.130 UJ	0.147 UJ	0.121 UJ	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/21/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/22/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/06/20	Bladder	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/02/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
MW109		02/09/21	Bladder	0.193 U	**0.0710 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
(continued)		05/03/21	Peristaltic	0.193 U	**0.228**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW110	Alley E of Seattle	03/23/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	Roy Aloha Shops	06/27/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		04/09/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/23/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	(dup)	01/23/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/26/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/15/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/15/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 UJ	0.108 U	0.190 U	0.124 U	0.130 UJ	0.147 UJ	0.121 UJ	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/16/20	Bladder	1.78 U	0.615 U	1.63 U	0.965 U	0.505 U	0.540 U	0.950 U	0.620 U	0.650 U	0.735 U	0.605 U	0.465 U	6.40 U	0.555 U	3.78 U	0.486 U
		04/22/20	Bladder	2.41 U	1.61 U	1.38 U	0.630 U	0.535 U	0.409 U	0.745 U	0.520 U	1.49 U	0.545 U	0.600 U	0.805 U	5.95 U	0.530 U	3.94 U	0.570 U
		07/16/20	Bladder	0.965 U	0.232 U	1.02 U	0.105 U	0.290 U	0.0950 U	0.254 U	0.216 U	0.340 U	0.350 U	0.394 U	0.159 U	2.50 U	0.184 U	–	0.226 U
		11/04/20	Bladder	9.65 U	2.32 U	10.2 U	1.05 U	2.90 U	0.950 U	2.54 U	2.16 U	3.40 U	3.50 U	3.94 U	1.59 U	25.0 U	1.84 U	–	2.26 U
		02/09/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/04/21	Bladder	1.93 U	0.464 U	2.04 U	0.210 U	0.580 U	**0.320 J**	0.508 U	0.432 U	0.680 U	0.700 U	0.788 U	0.317 U	5.00 U	0.368 U	–	0.452 U
MW115	9th Ave N ROW,	03/22/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	W side	06/22/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/11/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 UJ	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		01/30/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		07/17/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/22/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/20/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		05/05/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/28/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 UJ	1.19 U	0.106 U	0.787 U	0.114 U
		11/12/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/12/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
		05/25/21	Peristaltic	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW116	9th Ave N ROW,	03/21/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	W side	06/16/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/11/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 UJ	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		01/30/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		07/17/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/31/19	Peristaltic	0.355 U	0.123 U	0.325 UJ	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/21/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/29/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/28/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 UJ	1.19 U	0.106 U	0.787 U	0.114 U
		11/12/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/11/21	Peristaltic	0.193 U	**0.143 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
		05/25/21	Peristaltic	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW119	9th Ave N ROW,	03/29/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	W side	06/28/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/05/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
MW119		01/21/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
(continued)		04/29/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/19/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 UJ	1.28 U	0.111 U	0.757 U	0.0972 U
		10/10/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		11/11/19[o]	Peristaltic	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/14/20	Peristaltic	0.355 U	0.123 U	0.325 UJ	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
(split)		01/14/20[o]	Peristaltic	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/18/20[p]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		03/24/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/27/20	Peristaltic	0.481 UJ	0.322 U	0.276 UJ	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		05/19/20[p]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/08/20	Bladder	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	**0.0290 J**	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		07/28/20[p]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		09/17/20[p]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/11/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		12/03/20[p]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/10/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
(split)		02/10/21[p]	Peristaltic	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/20/21	Bladder	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW120	8th Ave N ROW, E side	03/28/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	**0.768**	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/28/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	**0.211 J**	**0.762**	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/09/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/24/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	**0.756**	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		05/03/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
(dup)		05/03/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/16/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	**0.271 J**	**0.746**	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/17/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	**0.605**	**1.12 J**	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
(dup)		10/17/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	**0.485 J**	0.190 UJ	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/17/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	**0.751**	**1.20**	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/23/20	Bladder	0.481 UJ	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	**1.07**	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/14/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 UJ	**0.895**	**1.11**	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/30/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	**0.511**	**0.781**	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
(dup)		11/30/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	**0.502**	**0.933**	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/05/21	Peristaltic	0.193 UJ	**0.0960 J**	0.204 U	0.0210 U	0.0580 U	**0.423**	**0.860**	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/12/21	Peristaltic	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	**0.311**	**0.689**	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW127	8th Ave N ROW, E side	08/01/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/17/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/17/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/23/20	Bladder	0.481 UJ	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/14/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 UJ	0.0190 U	**0.0970 J**	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
(dup)		07/14/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 UJ	0.0190 U	**0.0860 J**	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/13/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	**0.0576 J**	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 UJ	0.0368 U	–	0.0452 U
		05/11/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	**0.0750 J**	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
MW131	Property,	03/27/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	SE quadrant	06/20/17	Peristaltic	1.78 U	0.615 U	1.62 U	0.965 U	0.505 U	0.540 UJ	0.950 U	0.620 U	0.650 U	0.735 U	0.605 U	0.464 U	6.40 UJ	0.555 U	3.78 U	0.486 U
		04/16/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**13.2**	0.111 U	0.757 U	0.0972 U
		10/25/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 UJ	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**2.26 J**	0.111 U	0.757 U	0.0972 U
		12/12/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**3.89 J**	0.111 U	0.757 U	0.0972 U
		01/29/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**3.81 J**	0.111 U	0.757 U	0.0972 U
		03/11/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**25.4**	0.111 U	**1.26 J**	0.0972 U
	Decommissioned March, 2019																		
MW-142	8th Ave N ROW,	04/27/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	E side	01/28/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
(dup)		01/28/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/24/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/25/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/16/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		01/22/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/24/20	Bladder	0.481 UJ	0.322 U	0.276 UJ	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/30/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	**0.0395 J**	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
		11/24/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
(dup)		11/24/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/08/21	Peristaltic	0.193 U	**0.145 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	**23.2 J**	0.0368 U	–	0.0452 U
		05/19/21	Peristaltic	0.193 U	**0.737**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	**0.184 J**	0.0680 U	0.0700 U	0.0788 U	0.0317 U	**15.8 J+**	0.0368 U	–	0.0452 U
MW-144	8th Ave N ROW,	04/27/18	Peristaltic	0.355 U	**0.145 J**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**3.85 J**	0.111 U	0.757 U	0.0972 U
	E side	01/28/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/23/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	Decommissioned December 2019																		
MW-144R	8th Ave N ROW,	12/16/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**2.23 J**	0.111 U	0.757 U	0.0972 U
	E side	01/21/20	Bladder	3.55 U	1.23 U	3.25 U	1.93 U	1.01 U	1.08 U	1.90 U	1.24 U	1.30 U	1.47 U	1.21 U	0.929 U	12.8 U	1.11 U	7.57 U	0.972 U
		04/02/20	Bladder	0.355 UJ	0.123 UJ	0.325 UJ	0.193 UJ	0.101 UJ	0.108 UJ	0.190 UJ	0.124 UJ	0.130 UJ	0.147 UJ	0.121 UJ	0.0929 UJ	**2.50 J**	0.111 UJ	0.757 UJ	0.0972 UJ
		08/03/20	Bladder	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 UJ	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/23/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/02/21	Peristaltic	0.193 U	**0.0730 J**	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/12/21	Peristaltic	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-146	Roy St ROW,	04/30/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	S side	01/22/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/24/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/19/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 UJ	1.28 U	0.111 U	0.757 U	0.0972 U
(dup)		07/19/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 UJ	1.28 U	0.111 U	0.757 U	0.0972 U
		10/14/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 UJ	0.0972 U
		01/24/20	Bladder	35.5 U	12.3 U	32.5 U	19.3 U	10.1 U	10.8 U	19.0 U	12.4 U	13.0 U	14.7 U	12.1 U	9.29 U	128 U	11.1 U	75.7 U	9.72 U
(dup)		01/24/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/30/20	Bladder	48.1 U	32.2 U	27.6 U	12.6 U	10.7 U	8.19 U	14.9 U	10.4 U	29.9 U	10.9 U	12.0 U	16.1 U	119 U	10.6 U	78.7 U	11.4 U
		07/09/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/10/20	Bladder	9.65 U	2.32 U	10.2 U	1.05 U	2.90 U	0.950 U	2.54 U	2.16 U	3.40 U	3.50 U	3.94 U	1.59 U	25.0 UJ	1.84 U	–	2.26 U
(split)		11/10/20	Bladder	500 U	500 U	5,000 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	10,000 U	500 U	5,000 U	500 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
MW-146		02/08/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
(continued)		05/04/21	Bladder	9.65 UJ	2.32 U	10.2 U	1.05 U	2.90 U	0.950 U	2.54 U	2.16 U	3.40 U	3.50 U	3.94 U	1.59 U	25.0 U	1.84 U	–	2.26 U
MW-149	Property,	04/10/18	Peristaltic	1.78 U	**1.37 J**	1.62 U	0.965 U	0.505 U	0.540 U	0.950 U	0.620 U	0.650 U	0.735 U	0.605 U	0.464 U	6.40 U	0.555 U	3.78 U	0.486 U
	NE quadrant	10/25/18	Peristaltic	0.355 U	**0.139 J**	0.325 U	0.193 U	0.101 U	0.108 UJ	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		12/13/18	Peristaltic	0.355 U	**0.451 J**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	**0.144 J**	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
(dup)		12/13/18	Peristaltic	0.355 U	**0.476 J**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/29/19	Peristaltic	35.5 U	12.3 U	32.5 U	19.3 U	10.1 U	10.8 U	19.0 U	12.4 U	13.0 U	14.7 U	12.1 U	9.29 U	128 UJ	11.1 U	75.7 U	9.72 U
		03/13/19	Peristaltic	0.355 U	**0.524**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	**0.159 J**	0.130 U	0.147 U	0.121 U	0.0929 U	**44.9**	0.111 U	0.757 U	0.0972 U
	Decommissioned March, 2019																		
MW-151	Property,	04/10/18	Peristaltic	0.355 U	0.123 UJ	0.325 U	0.193 U	0.101 UJ	0.108 UJ	0.190 UJ	0.124 UJ	0.130 U	0.147 U	0.121 UJ	0.0929 U	**9.14 J-**	0.111 U	0.757 U	0.0972 U
	SW quadrant	10/25/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 UJ	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**31.7 J**	0.111 U	0.757 U	0.0972 U
		12/14/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**4.26 J**	0.111 U	0.757 U	0.0972 U
		01/31/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**1.71 J**	0.111 U	0.757 U	0.0972 U
		03/12/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**23.3**	0.111 U	0.757 U	0.0972 U
	Decommissioned March, 2019																		
MW-156	8th Ave N ROW,	04/26/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	E side	01/24/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/24/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
(dup)		04/24/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/22/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/17/19	Bladder	3.55 U	**1.36 J**	3.25 U	1.93 U	1.01 U	1.08 U	1.90 U	1.24 U	1.30 U	1.47 U	1.21 U	0.929 U	12.8 U	1.11 U	7.57 U	0.972 U
		01/20/20	Bladder	3.55 U	1.23 U	3.25 U	1.93 U	1.01 U	1.08 U	1.90 U	1.24 U	1.30 U	1.47 U	1.21 U	0.929 U	12.8 U	1.11 U	7.57 U	0.972 U
		04/24/20	Bladder	24.1 UJ	16.1 U	13.8 UJ	6.30 U	5.35 U	4.09 U	7.45 U	5.20 U	14.9 U	5.45 U	6.00 U	8.05 U	59.5 U	5.30 U	39.4 U	5.70 U
		07/15/20	Bladder	9.65 U	2.32 U	10.2 UJ	1.05 U	2.90 U	0.950 U	2.54 U	2.16 U	3.40 U	3.50 U	3.94 U	1.59 U	25.0 U	1.84 U	–	2.26 U
		11/11/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	**0.183**	**0.331**	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/08/21	Peristaltic	1.93 U	0.464 U	2.04 U	0.210 U	0.580 U	0.190 U	0.508 U	0.432 U	0.680 U	0.700 U	0.788 U	0.317 U	5.00 U	0.368 U	–	0.452 U
		05/10/21	Bladder	9.65 U	2.32 U	10.2 U	1.05 U	2.90 U	0.950 U	2.54 U	2.16 U	3.40 U	3.50 U	3.94 U	1.59 U	25.0 U	1.84 U	–	2.26 U
MW-189	Valley St ROW,	10/14/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 UJ	0.0972 U
	S side	01/23/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/03/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 UJ	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
(dup)		04/03/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 UJ	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		08/04/20	Bladder	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 UJ	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/17/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 UJ	0.0368 U	–	0.0452 U
		02/03/21	Bladder	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/14/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-302	Dexter Ave N	10/21/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	ROW	01/24/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		05/07/20	Bladder	0.481 U	0.322 UJ	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 UJ	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 UJ	0.787 U	0.114 UJ
		07/28/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 UJ	1.19 U	0.106 U	0.787 U	0.114 U
		11/17/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 UJ	0.0368 U	–	0.0452 U
		05/17/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-306	Dexter Ave N ROW,	10/15/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 UJ	0.108 U	0.190 U	0.124 U	0.130 UJ	0.147 UJ	0.121 UJ	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	E side	01/16/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
MW-306 (continued)		04/28/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/29/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/06/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/18/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-308	Alley E of Seattle Roy Aloha Shops	10/11/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	**0.133 J**	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 UJ	0.0972 U
		01/16/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/08/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/06/20	Peristaltic	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/06/20	Peristaltic	0.193 U	0.0797 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/04/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-315	Mercer St ROW, N side	10/03/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/16/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/24/20	Bladder	0.481 UJ	0.322 U	0.276 UJ	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/24/20	Bladder	0.193 U	**0.326**	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	**0.112 J**	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/02/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/17/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-317	9th Ave N ROW, W side	10/09/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/16/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/27/20	Bladder	0.481 UJ	0.322 U	0.276 UJ	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/30/20	Peristaltic	0.193 U	**0.170 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
		11/10/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/19/21	Peristaltic	0.193 U	0.101 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-325	Mercer St ROW, N side	10/03/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/17/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/21/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 UJ	1.19 U	0.106 U	0.787 U	0.114 U
		07/23/20	Bladder	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/02/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/08/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/17/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-327	Lake Union Park, S end	10/02/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/17/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/09/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/07/20	Peristaltic	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 UJ	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/09/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/25/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-330 (dup)	Valley St ROW, N side	05/14/20	Bladder	0.481 U	0.322 U	0.276 UJ	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		05/14/20	Bladder	0.481 U	0.322 U	0.276 UJ	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/16/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		12/01/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
(dup)		12/01/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
		05/25/21	Bladder	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
MW-331	Alley E of Seattle	04/24/20	Peristaltic	0.481 UJ	0.322 U	0.276 UJ	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
	Roy Aloha Shops	07/06/20	Peristaltic	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	**0.0380 J**	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/06/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/04/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-333	900 Roy St,	04/29/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
	S end	07/24/20	Bladder	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 UJ	0.0788 UJ	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/05/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/18/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-344	SDOT Mercer Parcels,	06/01/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
Intermediate B Water-Bearing Zone																			
FMW-141	Alley E of Seattle	07/26/19[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	Roy Aloha Shops	10/30/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
(dup)		10/30/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		11/11/19[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/14/20	Bladder	1.78 U	0.615 U	1.63 U	0.965 U	0.505 U	0.540 U	0.950 U	0.620 U	0.650 U	0.735 U	0.605 U	0.465 U	6.40 U	0.555 U	3.78 U	0.486 U
(split)		01/14/20[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/17/20[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		03/24/20[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/27/20[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/28/20	Bladder	2.41 U	1.61 U	1.38 U	0.630 U	0.535 U	0.409 U	0.745 U	0.520 U	1.49 U	0.545 U	0.600 U	0.805 U	5.95 U	0.530 U	3.94 U	0.570 U
		05/19/20[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/22/20	Bladder	3.86 U	0.928 U	4.08 UJ	0.420 U	1.16 U	0.380 U	1.02 U	0.864 U	1.36 U	1.40 U	1.58 U	0.634 U	10.0 U	0.736 U	–	0.904 U
		07/28/20[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		09/17/20[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/02/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		12/03/20[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/10/21[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/03/21	Peristaltic	0.193 U	0.133 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
HMW-1IB	SDOT Mercer Parcels,	03/25/19[a]	Peristaltic	1.0 U	1.0 U	1.0 U	0.010 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.00 U	–	1.0 U
	NE quadrant	03/10/20[a]	Unknown	–	0.20 U	0.11 UJ	–	0.20 U	–	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	–	0.20 U
HMW-2IB	SDOT Mercer Parcels,	03/25/19[a]	Peristaltic	1.0 U	1.0 U	1.0 U	0.010 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.00 U	–	1.0 U
	NE quadrant	03/12/20[a]	Unknown	–	0.20 U	0.80 UJ	–	0.20 U	–	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	–	0.20 U
HMW-4IA	SDOT Mercer Parcels,	03/25/19[a]	Peristaltic	1.0 U	1.0 U	1.0 U	0.010 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	–	1.0 U
	SW quadrant	03/10/20[a]	Unknown	–	0.20 U	0.11 UJ	–	0.20 U	–	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	–	0.20 U
HMW-5IB	SDOT Mercer Parcels,	03/17/20[a]	Unknown	–	0.20 U	0.80 UJ	–	0.20 U	–	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	–	0.20 U
	SW quadrant																		
HMW-6IB	SDOT Mercer Parcels,	03/13/20[a]	Unknown	–	0.20 U	0.80 UJ	–	0.20 U	–	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	–	0.20 U
	SW quadrant																		
HMW-7IB	SDOT Mercer Parcels,	03/12/20[a]	Unknown	–	0.20 U	0.80 UJ	–	0.20 U	–	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	–	0.20 U
	SW quadrant																		
HMW-8IB	SDOT Mercer Parcels,	03/11/20[a]	Unknown	–	0.20 U	0.11 UJ	–	0.20 U	–	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	–	0.20 U
	SW quadrant																		

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
HMW-9IB	SDOT Mercer Parcels, SW quadrant	03/19/20[a]	Unknown	–	0.20 U	0.80 UJ	–	0.20 U	–	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	–	0.20 U
		01/26/21	Bladder	0.193 U	**0.125 J**	0.204 U	0.0210 U	0.0580 U	**0.858**	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		06/02/21	Bladder	19.3 U	4.64 U	20.4 U	2.10 U	5.80 U	**2.60 J**	5.08 U	4.32 U	6.80 U	7.00 U	7.88 U	3.17 U	50.0 U	3.68 U	–	4.52 U
HMW-11IB	SDOT Mercer Parcels, SE quadrant	03/16/20[a]	Unknown	–	0.20 U	0.80 UJ	–	0.20 U	–	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	–	0.20 U
MW111	Alley E of Seattle Roy Aloha Shops	03/23/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/14/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/06/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/23/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/22/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/15/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/14/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 UJ	0.0972 U
		01/16/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/23/20	Bladder	0.481 UJ	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/06/20	Bladder	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/02/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/09/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/03/21	Bladder	0.193 U	0.195 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW112	Dexter Ave N ROW, W side	03/22/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/16/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/12/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		12/21/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/22/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/16/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/21/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		01/24/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		05/07/20	Bladder	0.481 U	0.322 UJ	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 UJ	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 UJ	0.787 U	0.114 UJ
		07/27/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/17/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 UJ	0.0368 U	–	0.0452 U
		02/11/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
		05/14/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW126	Alley E of Seattle Roy Aloha Shops	03/28/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/15/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/06/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/22/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/29/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/18/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/15/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 UJ	0.147 UJ	0.121 UJ	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	(dup)	10/15/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 UJ	0.108 U	0.190 U	0.124 U	0.130 UJ	0.147 UJ	0.121 UJ	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/14/20	Peristaltic	0.355 U	**0.291 J**	0.325 UJ	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/09/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
MW126		07/24/20	Peristaltic	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 UJ	0.0788 UJ	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
(continued)		11/09/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/10/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/04/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
	(dup)	05/04/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW130	Property,	03/29/17	Bladder	7.10 U	2.46 U	6.50 U	3.86 U	2.02 U	2.16 U	3.80 U	12.9 U	2.60 U	2.94 U	2.42 U	1.86 U	25.6 U	2.22 U	15.1 U	1.94 U
	NW quadrant	06/30/17	Bladder	3.55 U	1.23 U	3.25 U	1.93 U	1.01 U	1.08 U	1.90 U	1.24 U	1.30 U	1.47 U	1.21 U	0.929 U	12.8 U	1.11 U	7.57 U	0.972 U
	(dup)	06/30/17	Bladder	3.55 U	1.23 U	3.25 U	1.93 U	1.01 U	1.08 U	1.90 U	1.24 U	1.30 U	1.47 U	1.21 U	0.929 U	12.8 U	1.11 U	7.57 U	0.972 U
		05/21/18	Bladder	0.355 U	**0.816**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	**0.303 J**	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		12/17/18	Bladder	17.8 U	6.15 U	16.2 U	9.65 U	5.05 U	5.40 U	9.50 U	6.20 U	6.50 U	7.35 U	6.05 U	4.64 U	64.0 U	5.55 U	37.8 U	4.86 U
		01/31/19	Bladder	0.355 U	**1.09**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	**0.394 J**	0.130 U	0.147 U	0.121 U	**0.128 J**	1.28 U	0.111 U	0.757 U	0.0972 U
	Decommissioned March, 2019																		
MW-132	Property,	09/25/17	Bladder	1.78 U	0.615 U	1.62 U	0.965 U	0.505 U	0.540 U	0.950 U	0.620 U	0.650 U	0.735 U	0.605 U	0.464 U	6.40 U	0.555 U	3.78 U	0.486 U
	SE quadrant	04/26/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/25/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 UJ	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		12/13/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/31/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		03/11/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	Decommissioned March, 2019																		
MW-134	Property,	09/22/17	Bladder	1.78 U	0.615 U	1.62 U	0.965 U	0.505 U	0.540 U	0.950 U	0.620 U	0.650 U	0.735 U	0.605 U	0.464 U	6.40 U	0.555 U	3.78 U	0.486 U
	NE quadrant	04/16/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/25/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 UJ	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		12/12/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/28/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		03/12/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	Decommissioned March, 2019																		
MW-135	Property,	09/25/17	Bladder	35.5 U	12.3 U	32.5 U	19.3 U	10.1 U	10.8 U	19.0 U	12.4 U	13.0 U	14.7 U	12.1 U	9.29 U	128 U	11.1 U	75.7 U	9.72 U
	NE quadrant	04/25/18	Peristaltic	0.355 U	**2.26**	0.325 U	0.193 U	**0.143 J**	0.108 U	0.190 U	**0.708**	0.130 U	0.147 U	0.121 U	0.0929 U	**2.24 J**	0.111 U	0.757 U	0.0972 U
		10/25/18	Peristaltic	8.88 U	3.08 U	8.12 U	4.82 U	2.52 U	2.70 UJ	4.75 U	3.10 U	3.25 U	3.68 U	3.02 U	2.32 U	32.0 UJ	2.78 U	18.9 U	2.43 U
		12/13/18	Peristaltic	17.8 U	6.15 U	16.2 U	9.65 U	5.05 U	5.40 U	9.50 U	6.20 U	6.50 U	7.35 U	6.05 U	4.64 U	64.0 U	5.55 U	37.8 U	4.86 U
		01/31/19	Bladder	0.355 U	**2.50 J**	0.325 U	0.193 U	**0.147 J**	0.108 U	0.190 U	**0.786 J**	0.130 U	0.147 U	0.121 U	0.0929 U	**4.87 J**	0.111 U	0.757 U	0.0972 U
		03/13/19	Bladder	0.355 U	**2.09**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	**0.655**	0.130 U	0.147 U	0.121 U	0.0929 U	**6.73**	0.111 U	0.757 U	0.0972 U
	Decommissioned March, 2019																		
MW-136	Property,	09/25/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**1.43 J**	0.111 U	0.757 U	0.0972 U
	SW quadrant	04/16/18	Submersible	0.355 U	**17.4**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	**5.31**	0.130 U	0.147 U	0.121 U	0.0929 U	**76.4**	0.111 U	0.757 U	0.0972 U
		10/29/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		12/13/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		02/01/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		03/12/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	(dup)	03/12/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	Decommissioned March, 2019																		
MW-139	Property,	09/25/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	SE quadrant	04/25/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**2.67 J**	0.111 U	0.757 U	0.0972 U
		10/25/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 UJ	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		12/12/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
MW-139		01/28/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
(continued)		03/11/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	Decommissioned March, 2019																		
MW-143	8th Ave N ROW,	04/30/18	Peristaltic	0.355 U	**0.482 J**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	**0.173 J**	0.130 U	0.147 U	0.121 U	0.0929 U	**1.81 J**	0.111 U	0.757 U	0.0972 U
	E side	01/29/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		04/24/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/19/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 UJ	1.28 U	0.111 U	0.757 U	0.0972 U
		10/16/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/22/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/24/20	Bladder	0.481 UJ	0.322 U	0.276 UJ	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/29/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/24/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/08/21	Peristaltic	9.65 U	2.32 U	10.2 U	1.05 U	2.90 U	0.950 U	2.54 U	2.16 U	3.40 U	3.50 U	3.94 U	1.59 U	25.0 U	1.84 U	–	2.26 U
		05/19/21	Bladder	9.65 U	2.32 U	10.2 U	1.05 U	2.90 U	0.950 U	2.54 U	2.16 U	3.40 U	3.50 U	3.94 U	1.59 U	25.0 U	1.84 U	–	2.26 U
MW-145	8th Ave N ROW,	04/27/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	E side	01/29/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		04/26/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	Decommissioned December 2019																		
MW-145R	8th Ave N ROW,	12/16/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	E side	01/21/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/02/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		08/03/20	Bladder	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 UJ	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/23/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/05/21	Peristaltic	0.193 UJ	**0.128 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/12/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-147	Roy St ROW,	05/01/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	S side	01/22/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/23/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/18/19	Bladder	0.355 U	2.46 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	(dup)	07/18/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/14/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 UJ	0.0972 U
		01/24/20	Bladder	8.88 U	3.08 U	8.13 U	4.83 U	2.53 U	2.70 U	4.75 U	3.10 U	3.25 U	3.68 U	3.03 U	2.32 U	32.0 U	2.78 U	18.9 U	2.43 U
		04/29/20	Bladder	12.0 U	8.05 U	6.90 U	3.15 U	2.68 U	2.05 U	3.73 U	2.60 U	7.48 U	2.73 U	3.00 U	4.03 U	29.8 U	2.65 U	19.7 U	2.85 U
		07/09/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/10/20	Bladder	19.3 U	4.64 U	20.4 U	2.10 U	5.80 U	1.90 U	5.08 U	4.32 U	6.80 U	7.00 U	7.88 U	3.17 U	50.0 UJ	3.68 U	–	4.52 U
	(split)	11/10/20	Bladder	500 U	500 U	5,000 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	10,000 U	500 U	5,000 U	500 U
		02/09/21	Bladder	9.65 U	2.32 U	10.2 U	1.05 U	2.90 U	0.950 U	2.54 U	2.16 U	3.40 U	3.50 U	3.94 U	1.59 U	25.0 U	1.84 U	–	2.26 U
		05/04/21	Bladder	19.3 UJ	4.64 U	20.4 U	2.10 U	5.80 U	1.90 U	5.08 U	4.32 U	6.80 U	7.00 U	7.88 U	3.17 U	50.0 U	3.68 U	–	4.52 U
MW-148	Roy St ROW,	05/01/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
(dup)	S side	05/01/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/23/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/26/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/22/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/16/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
MW-148 (continued)		01/20/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/30/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.757 U	0.114 U
		07/15/20	Bladder	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	0.787 U	0.0452 U
		11/11/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-150	Property, NW quadrant	04/10/18	Peristaltic	0.355 U	**0.272 J**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/25/18	Peristaltic	0.355 U	**0.576**	0.325 U	0.193 U	0.101 U	0.108 UJ	0.190 U	**0.162 J**	0.130 U	0.147 U	0.121 U	0.0929 U	**3.56 J**	0.111 U	0.757 U	0.0972 U
		12/12/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/29/19	Peristaltic	35.5 U	12.3 U	32.5 U	19.3 U	10.1 U	10.8 U	19.0 U	12.4 U	13.0 U	14.7 U	12.1 U	9.29 U	128 UJ	11.1 U	75.7 U	9.72 U
		03/13/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**12.8**	0.111 U	0.757 U	0.0972 U
	Decommissioned March, 2019																		
MW-152	Property, SW quadrant	04/10/18	Peristaltic	7.10 U	**3.63 J**	6.50 U	3.86 U	2.02 U	2.16 U	3.80 U	2.48 U	2.60 U	2.94 U	2.42 U	1.86 U	25.6 U	2.22 U	15.1 U	1.94 U
		10/26/18	Peristaltic	17.8 U	6.15 U	16.2 U	9.65 U	5.05 U	5.40 UJ	9.50 U	6.20 U	6.50 U	7.35 U	6.05 U	4.64 U	**213 J**	5.55 U	37.8 U	4.86 U
		12/14/18	Peristaltic	8.88 U	3.49 U	8.12 U	4.82 U	2.52 U	2.70 U	4.75 U	3.10 U	3.25 U	3.68 U	3.02 U	2.32 U	32.0 U	2.78 U	18.9 U	2.43 U
		01/31/19	Peristaltic	0.355 U	**2.37**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	**0.615**	0.130 U	0.147 U	0.121 U	0.0929 U	**9.01**	0.111 U	0.757 U	0.0972 U
		03/12/19	Peristaltic	8.88 U	3.08 U	8.12 U	4.82 U	2.52 U	2.70 U	4.75 U	3.10 U	3.25 U	3.68 U	3.02 U	2.32 U	**37.0 J**	2.78 U	18.9 U	2.43 U
	Decommissioned March, 2019																		
MW-157	8th Ave N ROW, E side	04/26/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/24/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/24/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/22/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/16/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/20/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/24/20	Bladder	9.62 U	6.44 U	5.52 UJ	2.52 U	2.14 U	1.64 UJ	2.98 U	2.08 U	5.98 U	2.18 U	2.40 U	3.22 U	23.8 UJ	2.12 U	15.7 UJ	2.28 U
		07/15/20	Bladder	3.86 U	**1.30 J**	4.08 UJ	0.420 U	1.16 U	0.380 U	1.02 U	0.864 U	1.36 U	1.40 U	1.58 U	0.634 U	10.0 U	0.736 U	–	0.904 U
		11/23/20	Bladder	3.86 U	0.928 U	4.08 U	0.420 U	1.16 U	0.380 U	1.02 U	0.864 U	1.36 U	1.40 U	1.58 U	0.634 U	**456**	0.736 U	–	0.904 U
MW-190	Valley Street ROW, S side	10/14/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 UJ	0.0972 U
		01/23/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/02/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		08/04/20	Bladder	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 UJ	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/18/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/03/21	Bladder	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/14/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-303	Dexter Ave N ROW, E side	10/21/19	Submersible	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**1.48 J**	0.111 U	0.757 U	0.0972 U
		01/24/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		05/07/20	Bladder	0.481 U	0.322 UJ	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 UJ	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 UJ	0.787 U	0.114 UJ
		07/27/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/17/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 UJ	0.0368 U	–	0.0452 U
		05/18/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-307	Roy St ROW, S side	10/11/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 UJ	0.0972 U
		01/15/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/28/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/29/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
MW-307		11/06/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
(continued)		05/18/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-309	Alley E of Seattle	10/14/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 UJ	0.0972 U
	Roy Aloha Shops	01/16/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/08/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/06/20	Peristaltic	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/06/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/04/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-311	Alley E of Seattle	10/10/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**2.39 J**	0.111 U	0.757 U	0.0972 U
	Roy Aloha Shops	01/14/20	Peristaltic	0.355 U	0.123 U	0.325 UJ	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/23/20	Bladder	0.481 UJ	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/16/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/04/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/03/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-314	Alley E of Seattle	10/10/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	Roy Aloha Shops	01/15/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
(dup)		01/15/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/22/20	Bladder	4.81 U	3.22 U	2.76 U	1.26 U	1.07 U	0.819 U	1.49 U	1.04 U	2.99 U	1.09 U	1.20 U	1.61 U	11.9 U	1.06 U	7.87 U	1.14 U
		07/16/20	Bladder	19.3 U	4.64 U	20.4 U	2.10 U	5.80 U	1.90 U	5.08 U	4.32 U	6.80 U	7.00 U	7.88 U	3.17 U	50.0 U	3.68 U	–	4.52 U
		11/04/20	Bladder	19.3 U	4.64 U	20.4 U	2.10 U	5.80 U	1.90 U	5.08 U	4.32 U	6.80 U	7.00 U	7.88 U	3.17 U	50.0 U	3.68 U	–	4.52 U
		05/03/21	Bladder	9.65 U	2.32 U	10.2 U	1.05 U	2.90 U	0.950 U	2.54 U	2.16 U	3.40 U	3.50 U	3.94 U	1.59 U	25.0 U	1.84 U	–	2.26 U
MW-316	Mercer St ROW,	10/02/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	N side	01/16/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/21/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/24/20	Bladder	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/02/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/17/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-318	9th Ave N ROW,	10/08/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	**1.55**	**0.274 J**	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	W side	01/16/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	**1.40**	**0.298 J**	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/27/20	Bladder	0.481 UJ	0.322 U	0.276 UJ	0.126 U	0.107 U	**0.578**	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/30/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	**0.207**	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
		11/12/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/19/21	Peristaltic	0.193 U	0.0660 U	0.204 U	0.0210 U	0.0580 U	**0.104**	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-322	9th Ave N ROW,	10/07/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	W side	01/21/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/29/20	Bladder	48.1 U	32.2 U	27.6 U	12.6 U	10.7 U	8.19 U	14.9 U	10.4 U	29.9 U	10.9 U	12.0 U	16.1 U	119 U	10.6 U	78.7 U	11.4 U
		07/07/20	Bladder	1.93 U	0.464 U	2.04 UJ	0.210 U	0.580 U	**0.720 J**	**0.710 J**	0.432 U	0.680 U	0.700 U	0.788 U	0.317 U	5.00 U	0.368 U	–	0.452 U
		11/24/20	Bladder	1.93 U	0.464 U	2.04 U	0.210 U	0.580 U	**2.15**	0.508 U	0.432 U	0.680 U	0.700 U	0.788 U	0.317 U	5.00 U	0.368 U	–	0.452 U
		05/19/21	Peristaltic	1.93 U	0.464 U	2.04 U	0.210 U	0.580 U	**1.15**	0.508 U	0.432 U	0.680 U	0.700 U	0.788 U	0.317 U	5.00 U	0.368 U	–	0.452 U
MW-334	900 Roy St,	04/24/20	Bladder	0.481 UJ	0.322 U	0.276 UJ	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
	S end	07/07/20	Bladder	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 UJ	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
MW-334		11/05/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
(continued)		05/13/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-335	Mercer St ROW,	05/01/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
	N side	07/08/20	Bladder	1.93 U	0.464 U	2.04 U	0.210 U	0.580 U	0.190 U	0.508 U	0.432 U	0.680 U	0.700 U	0.788 U	0.317 U	5.00 U	0.368 U	–	0.452 U
		11/02/20	Bladder	1.93 U	0.464 U	2.04 U	0.210 U	0.580 U	0.190 U	0.508 U	0.432 U	0.680 U	0.700 U	0.788 U	0.317 U	5.00 U	0.368 U	–	0.452 U
		02/10/21	Bladder	1.93 U	0.464 U	2.04 U	0.210 U	0.580 U	0.190 U	0.508 U	0.432 U	0.680 U	0.700 U	0.788 U	0.317 U	5.00 U	0.368 U	–	0.452 U
		05/26/21	Peristaltic	1.93 U	0.464 U	2.04 U	0.210 U	0.580 U	0.190 U	0.508 U	0.432 U	0.680 U	0.700 U	0.788 U	0.317 U	5.00 U	0.368 U	–	0.452 U
MW-338	Lake Union Park,	05/07/20	Peristaltic	0.481 U	0.322 UJ	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 UJ	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 UJ	0.787 U	0.114 UJ
	N end	07/23/20	Peristaltic	0.193 U	**0.0800 J**	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/10/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/04/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-340	Lake Union Park,	05/12/20	Peristaltic	0.481 UJ	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
	S end	07/17/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 UJ	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/09/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/13/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-345	SDOT Mercer Parcels,	06/01/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-346	SDOT Mercer Parcels,	06/02/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
(dup)	NW quadrant	06/02/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-347	SDOT Mercer Parcels,	06/01/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-348	SDOT Mercer Parcels,	06/01/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-349	SDOT Mercer Parcels,	06/01/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	3.47 U	0.0368 U	–	0.0452 U
MW-350	SDOT Mercer Parcels,	06/01/21	Bladder	0.193 U	**34.8**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	**13.2**	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
W-MW-01	8th Ave N ROW,	03/30/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	W side	06/19/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 UJ	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		04/13/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/29/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		12/13/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/25/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		03/11/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/25/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/23/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/15/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 UJ	0.108 U	0.190 U	0.124 U	0.130 UJ	0.147 UJ	0.121 UJ	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/27/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/03/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 UJ	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		07/31/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
		11/24/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	**2.98**	0.0368 U	–	0.0452 U
		02/03/21	Bladder	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	**34.2**	0.0368 U	–	0.0452 U
		05/17/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	**135**	0.0368 U	–	0.0452 U
W-MW-02	8th Ave N ROW,	03/27/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**13.8**	0.111 U	0.757 U	0.0972 U
	W side	06/19/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 UJ	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**3.57 J**	0.111 U	0.757 U	0.0972 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
W-MW-02		06/12/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 UJ	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**2.73 J**	0.111 U	0.757 U	0.0972 U
(continued)		10/26/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 UJ	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
(dup)		10/26/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		12/12/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/25/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		03/11/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/23/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/23/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/18/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/28/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/01/20	Bladder	0.355 UJ	0.123 U	0.325 UJ	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/31/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
Deep Water-Bearing Zone																			
FMW-129	SDOT Mercer Parcels,	04/10/17	Peristaltic	1.78 U	0.615 U	1.62 U	0.965 U	0.505 U	0.540 U	0.950 U	0.620 U	0.650 U	0.735 U	0.605 U	0.464 U	6.40 U	0.555 U	3.78 U	0.486 U
	NE quadrant	06/23/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		05/01/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/16/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/21/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		11/12/19[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/14/20	Bladder	3.55 U	1.23 U	3.25 UJ	1.93 U	1.01 U	1.08 U	1.90 U	1.24 U	1.30 U	1.47 U	1.21 U	0.929 U	12.8 U	1.11 U	7.57 U	0.972 U
(split)		01/14/20[v]	Bladder	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/18/20[p]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		03/25/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/27/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/06/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		05/19/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/10/20	Bladder	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
		07/28/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		09/17/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/10/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		12/03/20[p]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/10/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
(split)		02/10/21[v]	Peristaltic	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/26/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
(dup)		05/26/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
FMW-131	Block 37,	03/24/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	SE quadrant	06/23/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		12/18/17[b]	Unknown	–	–	–		–	–	–	–	–	–	–	–	–	–		–
		04/22/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/21/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		01/22/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.787 U	0.0972 U
		04/29/20	Peristaltic	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	–	0.114 U
		07/30/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
		08/26/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
FMW-131 (continued)		11/19/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		12/04/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/11/21[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/12/21	Peristaltic	0.193 U	**0.143 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
		05/13/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
FMW-137	Alley E of Block 38 West	11/20/18[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		12/28/18[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/06/19[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/08/19[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		10/14/19[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/06/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		11/11/19[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/22/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		05/06/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/31/20	Bladder	0.193 U	**0.0987 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
		11/24/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/12/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
		06/02/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
FMW-138	Alley E of Block 38 West	11/20/18[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		12/28/18[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/6/19[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/8/19[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		10/14/19[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/11/19[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
FMW-3D	Terry Ave N ROW, E side	03/24/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/23/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
FMW-140	900 Roy St, S end	07/17/19[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		10/31/19	Peristaltic	0.355 U	0.123 U	0.325 UJ	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**1.50 J**	0.111 U	0.757 U	0.0972 U
		11/12/19[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/14/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/22/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		02/18/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		03/25/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/27/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/28/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	**0.239 J**	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		05/19/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/07/20	Bladder	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 UJ	**0.445**	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		07/29/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		09/17/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/13/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	**0.478**	**0.110 J**	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 UJ	0.0368 U	–	0.0452 U
		12/04/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/10/21[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/18/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	**0.139**	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
GEI-2	Block 37, NW quadrant	03/24/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		06/23/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		12/29/18[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/22/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/16/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/21/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		11/11/19[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/14/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/22/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		02/17/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		03/25/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/27/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/29/20	Peristaltic	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		05/19/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		06/29/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/29/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/30/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
		08/26/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		09/17/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/19/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		12/04/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/11/21[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/12/21	Peristaltic	0.193 U	**0.188 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
		05/13/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
HMW-1D	SDOT Mercer Parcels, NE quadrant	03/25/19[a]	Peristaltic	1.0 U	1.0 U	1.0 U	0.010 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	–	1.0 U
		03/09/20[a]	Unknown	–	20 U	75 UJ	–	20 U	–	20 U	–	20 U	20 U	20 U	20 U	–	20 U	–	20 U
HMW-2D	SDOT Mercer Parcels, NE quadrant	03/25/19[a]	Peristaltic	1.0 U	1.0 U	1.0 U	0.010 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	–	1.0 U
		03/12/20[a]	Unknown	–	0.20 U	0.80 UJ	–	0.20 U	–	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	–	0.20 U
HMW-3D	SDOT Mercer Parcels, NW quadrant	03/25/19[a]	Peristaltic	1.0 U	1.0 U	1.0 U	0.010 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	–	1.0 U
		03/13/20[a]	Unknown	–	0.20 U	0.80 UJ	–	0.20 U	–	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	–	0.20 U
HMW-6D	SDOT Mercer Parcels, SW quadrant	03/16/20[a]	Unknown	–	0.20 U	0.80 UJ	–	0.20 U	–	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	–	0.20 U
HMW-9D	SDOT Mercer Parcels, SW quadrant	03/17/20[a]	Unknown	–	0.20 U	0.80 UJ	–	0.20 U	–	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	–	0.20 U
HMW-10D	SDOT Mercer Parcels, SE quadrant	03/16/20[a]	Unknown	–	0.20 U	0.80 UJ	–	0.20 U	–	0.20 U	–	0.20 U	0.20 U	0.20 U	0.20 U	–	0.20 U	–	0.20 U
MW102	Valley Street ROW, S side	03/29/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/15/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/25/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/24/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		05/01/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/18/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
MW102		11/14/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
(continued)		01/23/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
(dup)		01/23/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/02/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		08/04/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
(dup)		08/04/20	Bladder	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 UJ	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/18/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/03/21	Bladder	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/14/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW103	Alley E of Seattle	03/23/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	Roy Aloha Shops	06/14/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/06/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/23/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**8.78**	0.111 U	0.757 U	0.0972 U
		04/22/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/15/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/14/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 UJ	0.0972 U
		01/16/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/23/20	Bladder	0.481 UJ	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
(dup)		04/23/20	Bladder	0.481 UJ	**0.492 J**	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/06/20	Bladder	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	**0.0370 J**	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/02/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/10/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/03/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW104	8th Ave N ROW,	03/30/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	W side	06/30/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/09/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/26/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 UJ	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		12/13/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		02/01/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**68.5**	0.111 U	0.757 U	0.0972 U
		03/13/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**2.04 J**	0.111 U	0.757 U	0.0972 U
		04/23/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**4.72 J**	0.111 U	0.757 U	0.0972 U
		07/22/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/18/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/29/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/01/20	Bladder	0.355 UJ	0.123 U	0.325 UJ	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/31/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
(dup)		07/31/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
		11/17/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 UJ	0.0368 U	–	0.0452 U
		02/10/21	Bladder	0.193 U	**0.0830 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW105	Roy Street ROW,	04/21/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	S side	06/14/17	Bladder	0.355 U	**0.216 J**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/11/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 UJ	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		01/23/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/23/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
MW105		07/17/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
(continued)		10/22/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
(dup)		10/22/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 UJ	0.757 U	0.0972 U
		01/20/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		05/12/20	Bladder	0.481 UJ	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 UJ	0.106 U	0.787 U	0.114 U
		07/27/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/17/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 UJ	0.0368 U	–	0.0452 U
		02/11/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		06/07/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW106	SDOT Mercer Parcels, NW quadrant	04/14/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/30/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		05/04/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/26/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/19/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 UJ	1.28 U	0.111 U	0.757 U	0.0972 U
		10/18/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/14/20	Bladder	0.355 U	0.123 U	0.325 UJ	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		05/06/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
(dup)		05/06/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/10/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 UJ	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/10/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
(dup)		11/10/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/12/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
(dup)		02/12/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
		05/13/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW113	9th Ave N ROW, W side	03/22/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	**0.240 J**	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/16/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/11/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 UJ	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		01/30/19	Peristaltic	1.78 U	0.615 U	1.62 U	0.965 U	0.505 U	0.540 U	0.950 U	0.620 U	0.650 U	0.735 U	0.605 U	0.464 U	6.40 UJ	0.555 U	3.78 U	0.486 U
		02/07/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/17/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/22/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		11/11/19[p]	Peristaltic	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/14/20	Bladder	3.55 U	1.23 U	3.25 UJ	1.93 U	1.01 U	1.08 U	1.90 U	1.24 U	1.30 U	1.47 U	1.21 U	0.929 U	12.8 U	1.11 U	78.7 U	0.972 U
(split)		01/14/20[v]	Peristaltic	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/18/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		03/24/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/27/20	Peristaltic	48.1 UJ	32.2 U	27.6 UJ	12.6 U	10.7 U	8.19 U	14.9 U	10.4 U	29.9 U	10.9 U	12.0 U	16.1 U	119 U	10.6 U	–	11.4 U
(split)		04/27/20[v]	Peristaltic	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/19/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/28/20	Bladder	48.1 U	32.2 U	27.6 U	12.6 U	10.7 U	8.19 U	14.9 U	10.4 U	29.9 U	10.9 U	12.0 U	16.1 UJ	119 U	10.6 U	–	11.4 U
(split)		07/28/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		09/17/20[p]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/24/20	Bladder	19.3 U	4.64 U	20.4 U	2.10 U	5.80 U	1.90 U	5.08 U	4.32 U	6.80 U	7.00 U	7.88 U	3.17 U	50.0 U	3.68 U	–	4.52 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
MW113		12/03/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(continued)		02/10/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
(split)		02/10/21[o]	Peristaltic	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/25/21	Peristaltic	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	**0.237**	**0.376**	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW122	Alley E of Seattle Roy Aloha Shops	03/28/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/14/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/06/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/14/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 UJ	0.0972 U
		01/17/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/07/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/24/20	Peristaltic	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/06/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/03/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW123	Westlake Ave N ROW, W side	04/01/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/24/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/14/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/18/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/22/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		05/05/20	Peristaltic	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/30/20	Peristaltic	0.193 U	**0.127 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
		11/12/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 UJ	0.0368 U	–	0.0452 U
		05/26/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW124	Valley Street ROW, S side	03/29/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
(dup)		03/29/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/15/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/13/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/11/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 UJ	0.0972 U
		01/30/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/03/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 UJ	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		08/03/20	Bladder	0.193 U	**0.0532 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
		11/18/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		06/08/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW128	Westlake Ave N ROW, E side	03/29/17	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		06/21/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 UJ	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		04/09/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		12/30/18[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/18/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/11/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 UJ	0.0972 U
(dup)		10/11/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 UJ	0.0972 U
		11/11/19[o]	Peristaltic	–	–	–	–	–	–	–	–	–	–	–	–	–	–	0.757 U	–
		01/20/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.787 U	0.0972 U
		02/18/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
MW128		04/27/20	Peristaltic	0.481 UJ	0.322 U	0.276 UJ	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	–	0.114 U
(continued)		06/29/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
(split)		06/29/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		08/26/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/09/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		12/20/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/11/21[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/25/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-133	Property,	09/25/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	SW quadrant	04/25/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/26/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 UJ	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		12/12/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		02/01/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		03/13/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	Decommissioned March, 2019																		
MW-137	Property,	09/25/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	SW quadrant	04/12/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		10/26/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 UJ	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		12/12/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		02/01/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		03/11/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	Decommissioned March, 2019																		
MW-138	Dexter Ave N ROW,	09/21/17	Bladder	0.710 U	0.246 U	0.650 U	0.386 U	0.202 U	0.216 U	0.380 U	0.248 U	0.260 U	0.294 U	0.242 U	0.186 U	2.56 U	0.222 U	1.51 U	0.194 U
	E side	04/11/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 UJ	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		10/29/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		12/17/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/03/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		03/14/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/22/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/19/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 UJ	1.28 U	0.111 U	0.757 U	0.0972 U
		10/21/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/27/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		05/08/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/27/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/18/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/11/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
		06/07/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-140	Roy Street ROW,	09/22/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
(dup)	E side	09/22/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/12/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	–	0.0972 U
MW-141	Property,	09/22/17	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	SE quadrant	04/12/18	Submersible	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		10/25/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 UJ	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		12/12/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
MW-141		01/30/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
(continued)		03/11/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	Decommissioned March, 2019																		
MW-153	Roy St ROW,	05/01/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	S side	01/22/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/24/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	(dup)	04/24/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/22/19	Bladder	0.355 U	**0.225 J**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	**0.141 J**	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/15/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/21/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/30/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/15/20	Bladder	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/09/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/09/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
	(dup)	02/09/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/10/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-158A	8th Ave N ROW,	04/30/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	E side	01/24/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/25/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/19/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 UJ	1.28 U	0.111 U	0.757 U	0.0972 U
		10/16/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/21/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/24/20	Bladder	0.481 UJ	0.322 U	0.276 UJ	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/15/20	Bladder	0.193 U	**0.0660 J**	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/23/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/02/21	Bladder	0.193 U	**0.0870 J**	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/10/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-160	8th Ave N ROW,	05/21/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	W side	01/25/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		05/01/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/23/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/17/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/29/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/01/20	Bladder	0.355 UJ	0.123 U	0.325 UJ	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		08/03/20	Bladder	0.193 U	**0.0510 J**	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 UJ	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/30/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/05/21	Bladder	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/12/21	Bladder	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-161	8th Ave N ROW,	05/21/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
	W side	01/25/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		05/01/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/18/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/14/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 UJ	0.111 U	0.757 UJ	0.0972 U
		01/28/20	Bladder	0.355 UJ	0.123 U	0.325 UJ	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
MW-161 (continued)		04/03/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 UJ	0.0929 U	1.28 UJ	0.111 U	0.757 U	0.0972 U
		07/31/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
		12/01/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/05/21	Bladder	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/25/21	Bladder	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-162	Property, NE quadrant Decommissioned March, 2019	02/05/19	Bladder	2.00 U	1.00 U	1.00 U	0.250 U	1.00 U	1.00 U	1.00 U	1.00 U	1.00 U	1.00 U	1.00 U	2.00 U	–	1.00 U	–	1.00 U
		03/12/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	–	0.0972 U
MW-163	Property, NW quadrant	02/05/19	Bladder	2.00 U	1.00 U	1.00 U	0.250 U	1.00 U	1.00 U	1.00 U	1.00 U	1.00 U	1.00 U	1.00 U	2.00 U	–	1.00 U	–	1.00 U
	(dup)	02/05/19	Bladder	2.00 U	1.00 U	1.00 U	0.250 U	1.00 U	1.00 U	1.00 U	1.00 U	1.00 U	1.00 U	1.00 U	2.00 U	–	1.00 U	–	1.00 U
	Decommissioned March, 2019	03/12/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	–	0.0972 U
MW-164	Property, SW quadrant Decommissioned March, 2019	02/05/19	Bladder	2.00 U	1.00 U	1.00 U	0.250 U	1.00 U	1.00 U	1.00 U	1.00 U	1.00 U	1.00 U	1.00 U	2.00 U	–	1.00 U	–	1.00 U
		03/12/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	–	0.0972 U
MW-304	Dexter Ave N ROW, E side	10/21/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/27/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		05/07/20	Bladder	0.481 U	0.322 UJ	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 UJ	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 UJ	0.787 U	0.114 UJ
		07/27/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/18/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-319	9th Ave N ROW, W side	10/08/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	**0.140 J**	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/16/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/27/20	Bladder	0.481 UJ	0.322 U	0.276 UJ	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/27/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/12/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/19/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	**0.0660 J**	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-323	9th Ave N ROW, W side	10/09/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/20/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/23/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/07/20	Bladder	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 UJ	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/24/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/20/21	Peristaltic	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-324	Roy St ROW, N side	10/02/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/20/20	Peristaltic	17.8 U	6.15 U	16.3 U	9.65 U	5.05 U	5.40 U	9.50 U	6.20 U	6.50 U	7.35 U	6.05 U	4.65 U	64.0 U	5.55 U	37.9 U	4.86 U
		04/24/20	Bladder	24.1 UJ	16.1 U	13.8 UJ	6.30 U	5.35 U	4.09 U	7.45 U	5.20 U	14.9 U	5.45 U	6.00 U	8.05 U	59.5 U	5.30 U	39.4 U	5.70 U
		07/07/20	Bladder	9.65 U	2.32 U	10.2 UJ	1.05 U	2.90 UJ	0.950 U	2.54 U	2.16 U	3.40 U	3.50 U	3.94 U	1.59 U	25.0 U	1.84 U	–	2.26 U
		11/13/20	Bladder	9.65 U	2.32 U	10.2 U	1.05 U	2.90 U	0.950 U	2.54 U	2.16 U	3.40 U	3.50 U	3.94 U	1.59 U	25.0 UJ	1.84 U	–	2.26 U
		05/20/21	Peristaltic	9.65 UJ	2.32 U	10.2 U	1.05 U	2.90 U	0.950 U	2.54 U	2.16 U	3.40 U	3.50 U	3.94 U	1.59 U	25.0 U	1.84 U	–	2.26 U
MW-326	Mercer Street ROW, N side	10/03/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/17/20	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/21/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 UJ	1.19 U	0.106 U	0.787 U	0.114 U
		07/23/20	Bladder	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
MW-326 (continued)		11/02/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/09/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/18/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-328	Lake Union Park, S end	10/02/19	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/17/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/08/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/07/20	Peristaltic	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 UJ	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/09/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/25/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-329 (dup)	Westlake Ave N ROW, E side	10/03/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		10/03/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/20/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/27/20	Bladder	0.481 UJ	0.322 U	0.276 UJ	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		08/03/20	Bladder	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 UJ	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/09/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/25/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-336	Mercer St ROW, N side	05/05/20	Bladder	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/08/20	Bladder	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	**0.0330 J**	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/02/20	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/10/21	Bladder	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/26/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-341	Lake Union Park, S end	05/12/20	Peristaltic	0.481 UJ	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/07/20	Peristaltic	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 UJ	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/09/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/25/21	Peristaltic	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-342	Valley St ROW, S side	05/04/20	Peristaltic	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 UJ	0.106 U	0.787 U	0.114 U
		07/30/20	Peristaltic	0.193 U	**0.0959 J**	0.204 U	0.0210 U	0.0580 U	**0.0380 J**	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
		11/17/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 UJ	0.0368 U	–	0.0452 U
		06/04/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-343	Valley St ROW, S side	05/04/20	Peristaltic	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 UJ	0.106 U	0.787 U	0.114 U
		07/30/20	Peristaltic	0.193 U	**0.117 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 UJ	0.500 U	0.0368 U	–	0.0452 U
		11/24/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		06/04/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
Treatment Zone A Wells																			
IW-4A	Property, NW quadrant Decommissioned March, 2019	03/28/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
IW-7A	Property, NE quadrant Decommissioned March, 2019	04/02/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
IW-9A	Property, NW quadrant Decommissioned March, 2019	03/29/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
IW-18A	Property, NE quadrant Decommissioned March, 2019	03/30/18	Peristaltic	0.355 U	**0.984**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	**0.293 J**	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
IW-22A	Property, NE quadrant Decommissioned March, 2019	04/02/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
IW-37A	Property, SW quadrant Decommissioned March, 2019	03/28/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
IW-41A	Property, SW quadrant Decommissioned March, 2019	04/10/18	Peristaltic	0.355 U	2.46 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
IW-42A	Property, SW quadrant Decommissioned March, 2019	04/10/18	Peristaltic	0.355 U	30.8 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	**0.403 J**	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
IW-45A	Property, SW quadrant Decommissioned March, 2019	04/04/18	Peristaltic	0.355 U	**0.490 J**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	**0.138 J**	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
IW-46A	Property, SE quadrant Decommissioned March, 2019	03/28/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
IW-48A	Property, SE quadrant Decommissioned March, 2019	04/02/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**119**	0.111 U	0.757 U	0.0972 U
MW-165	Property, NE quadrant	11/04/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/30/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		05/01/20	Peristaltic	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	**23.5**	0.106 U	0.787 U	0.114 U
		07/09/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/05/20	Flowing	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	**1.30**	0.0368 U	–	0.0452 U
	(dup)	11/05/20	Flowing	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	**1.44**	0.0368 U	–	0.0452 U
		02/04/21	Flowing	0.193 U	**0.0920 J**	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	**1.12**	0.0368 U	–	0.0452 U
		05/06/21	Flowing	1.93 U	0.464 UJ	2.04 U	0.210 U	0.580 U	**0.380 J**	0.508 U	0.432 U	0.680 U	0.700 U	0.788 U	0.317 U	5.00 U	0.368 U	–	0.452 UJ
MW-169	Property, SW quadrant	11/05/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/23/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		05/05/20	Peristaltic	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/10/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 UJ	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/03/20	Flowing	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/17/21	Flowing	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/07/21	Flowing	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-173	Property, SE quadrant	11/01/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/28/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		05/01/20	Peristaltic	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
MW-173		07/09/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
(continued)		11/05/20	Flowing	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/04/21	Flowing	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/05/21	Flowing	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-177	Property, SW quadrant	11/06/19	Peristaltic	0.355 U	**3.88**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	**1.24**	0.130 U	0.147 U	0.121 U	0.0929 U	**10.3**	0.111 U	0.757 U	0.0972 U
		01/24/20	Peristaltic	17.8 U	6.15 U	16.3 U	9.65 U	5.05 U	5.40 U	9.50 U	6.20 U	6.50 U	7.35 U	6.05 U	4.65 U	64.0 U	5.55 U	0.757 U	4.86 U
		04/01/20	Peristaltic	1,780 UJ	615 U	1,630 UJ	965 U	505 U	540 U	950 U	620 U	650 U	735 U	605 U	465 U	6,400 U	555 U	37.9 U	486 U
		07/10/20	Peristaltic	965 U	232 U	1,020 U	105 U	290 UJ	95.0 U	254 U	216 U	340 U	350 U	394 U	159 U	2,500 U	184 U	3,780 U	226 U
		11/03/20	Flowing	193 U	46.4 U	204.0 U	21.0 U	58.0 U	19.0 U	50.8 U	43.2 U	68.0 U	70.0 U	78.8 U	31.7 U	500 U	36.8 U	–	45.2 U
		02/18/21	Flowing	38.6 UJ	9.28 U	40.8 U	4.20 U	11.6 U	3.80 U	10.2 U	8.64 U	13.6 U	14.0 U	15.8 U	6.34 U	100 U	7.36 U	–	9.04 U
		05/06/21	Flowing	38.6 UJ	9.28 U	40.8 U	4.20 U	11.6 U	3.80 U	10.2 U	8.64 U	13.6 U	14.0 U	15.8 U	6.34 U	100 U	7.36 U	–	9.04 U
MW-181	Property, SW quadrant	11/08/19	Peristaltic	0.355 U	0.615 U	0.325 U	0.193 U	0.505 U	0.540 U	0.950 U	0.620 U	0.130 U	0.147 U	0.605 U	0.0929 U	6.40 U	0.111 U	0.757 U	0.0972 U
		01/27/20	Peristaltic	178 U	61.5 U	163.0 U	96.5 U	50.5 U	54.0 U	95.0 U	62.0 U	65.0 U	73.5 U	60.5 U	46.5 U	640 U	55.5 U	3.78 U	48.6 U
		04/01/20	Peristaltic	178 UJ	61.5 U	163.0 UJ	96.5 U	50.5 U	54.0 U	95.0 U	62.0 U	65.0 U	73.5 U	60.5 U	46.5 U	640 U	55.5 U	379 U	48.6 U
		07/08/20	Peristaltic	96.5 U	23.2 U	102.0 UJ	10.5 U	29.0 U	9.50 U	25.4 U	21.6 U	34.0 U	35.0 U	39.4 U	15.9 U	250 U	18.4 U	379 U	22.6 U
		11/04/20	Peristaltic	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	**1.53**	0.0368 U	–	0.0452 U
		02/19/21	Flowing	19.3 UJ	4.64 U	20.4 U	2.10 U	5.80 U	1.90 U	5.08 U	4.32 U	6.80 U	7.00 U	7.88 U	3.17 U	50.0 U	3.68 U	–	4.52 U
		05/06/21	Peristaltic	19.3 UJ	4.64 U	20.4 U	2.10 U	5.80 U	1.90 U	5.08 U	4.32 U	6.80 U	7.00 U	7.88 U	3.17 U	50.0 U	3.68 U	–	4.52 U
MW-185	Property, SE quadrant	10/31/19	Flowing	0.355 U	0.123 U	0.325 UJ	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**16.0**	0.111 U	0.757 U	0.0972 U
		01/29/20	Peristaltic	0.355 UJ	0.123 U	0.325 UJ	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**31.0**	0.111 U	**0.925 J**	0.0972 U
		04/02/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/08/20	Peristaltic	0.193 U	**0.0720 J**	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/04/20	Flowing	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/16/21	Flowing	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/07/21	Flowing	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
Treatment Zone B Wells																			
IW-3B	Property, NW quadrant Decommissioned March, 2019	03/28/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
IW-6B	Property, SW quadrant Decommissioned March, 2019	04/02/18	Peristaltic	0.355 U	**0.212 J**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
IW-8B	Property, SW quadrant Decommissioned March, 2019	03/30/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
IW-17B	Property, NE quadrant Decommissioned March, 2019	03/30/18	Peristaltic	0.355 U	**2.04**	0.325 U	0.193 U	**0.134 J**	0.108 U	0.190 U	**0.613**	0.130 U	0.147 U	0.121 U	0.0929 U	**2.93 J**	0.111 U	0.757 U	0.0972 U
IW-21B	Property, NE quadrant Decommissioned March, 2019	04/02/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
IW-22B	Property, NW quadrant Decommissioned March, 2019	04/25/18	Peristaltic	7.10 U	**5.42 J**	6.50 U	3.86 U	2.02 U	2.16 U	3.80 U	2.48 U	2.60 U	2.94 U	2.42 U	1.86 U	25.6 U	2.22 U	15.1 U	1.94 U
IW-24B	Property, NE quadrant Decommissioned March, 2019	03/30/18	Peristaltic	0.355 U	**3.07 J+**	0.325 U	0.193 U	**0.172 J+**	0.108 U	0.190 U	**0.906 J+**	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
IW-28B	Property, NW quadrant Decommissioned March, 2019	04/09/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
IW-33B	Property, NE quadrant Decommissioned March, 2019	04/02/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**1.35 J**	0.111 U	0.757 U	0.0972 U
IW-37B	Property, SW quadrant Decommissioned March, 2019	03/29/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
IW-45B	Property, SE quadrant Decommissioned March, 2019	03/28/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
IW-47B	Property, SW quadrant Decommissioned March, 2019	04/10/18	Bladder	1.78 U	123 U	1.62 U	0.965 U	0.505 U	0.540 U	0.950 U	0.620 U	0.650 U	0.735 U	0.605 U	0.464 U	**11.5 J**	0.555 U	3.78 U	0.486 U
IW-49B	Property, SE quadrant Decommissioned March, 2019	03/28/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**33.1**	0.111 U	–	0.0972 U
IW-51B	Property, SE quadrant Decommissioned March, 2019	03/28/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**1.43 J**	0.111 U	–	0.0972 U
MW-166	Property, NE quadrant	11/04/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**19.6**	0.111 U	0.757 U	0.0972 U
		01/30/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**26.2**	0.111 U	0.757 U	0.0972 U
		05/01/20	Peristaltic	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/09/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 UJ	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
(dup)		07/09/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/05/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/04/21	Flowing	96.5 UJ	23.2 U	102 U	10.5 U	29.0 U	9.50 U	25.4 U	21.6 U	34.0 U	35.0 U	39.4 U	15.9 U	250 U	18.4 U	–	22.6 U
		05/05/21	Flowing	38.6 U	9.28 UJ	40.8 U	4.20 U	11.6 U	3.80 U	10.2 U	8.64 U	13.6 U	14.0 U	15.8 U	6.34 U	100 U	7.36 U	–	9.04 UJ
MW-170	Property, SW quadrant	11/05/19	Peristaltic	0.355 U	**0.437 J**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	**0.154 J**	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/23/20	Peristaltic	8.88 U	3.08 U	8.13 U	4.83 U	2.53 U	2.70 U	4.75 U	3.10 U	3.25 U	3.68 U	3.03 U	2.32 U	32.0 U	2.78 U	18.9 U	2.43 U
		04/02/20	Peristaltic	178 U	61.5 U	163.0 U	96.5 U	50.5 U	54.0 U	95.0 U	62.0 U	65.0 U	73.5 U	60.5 U	46.5 U	640 U	55.5 U	379 U	48.6 U
		07/09/20	Peristaltic	1.93 U	**0.850 J**	2.04 U	0.210 U	0.580 U	0.190 U	0.508 U	0.432 U	0.680 U	0.700 U	0.788 U	0.317 U	5.00 U	0.368 U	–	0.452 U
		11/03/20	Peristaltic	1.93 U	0.464 U	2.04 U	0.210 U	0.580 U	0.190 U	0.508 U	0.432 U	0.680 U	0.700 U	0.788 U	0.317 U	5.00 U	0.368 U	–	0.452 U
		02/17/21	Peristaltic	1.93 U	**1.46 J**	2.04 U	0.210 U	0.580 U	0.190 U	0.508 U	0.432 U	0.680 U	0.700 U	0.788 U	0.317 U	5.00 U	0.368 U	–	0.452 U
		05/07/21	Peristaltic	96.5 UJ	23.2 U	102 U	10.5 U	29.0 U	9.50 U	25.4 U	21.6 U	34.0 U	35.0 U	39.4 U	15.9 U	250 U	18.4 U	–	22.6 U
MW-174	Property, SE quadrant	11/01/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/28/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		05/01/20	Peristaltic	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/09/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/05/20	Flowing	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/04/21	Flowing	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/05/21	Flowing	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-178	Property, SW quadrant	11/06/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**165**	0.111 U	**3.30 J**	0.0972 U
		01/24/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**200**	0.111 U	**3.36 J**	0.0972 U
		04/02/20	Peristaltic	0.355 UJ	0.123 U	0.325 UJ	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**23.1**	0.111 U	0.757 U	0.0972 U
		07/10/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 UJ	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/03/20	Peristaltic	0.193 U	**0.114 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	**3.29 J**	0.0368 U	–	0.0452 U
		02/18/21	Peristaltic	3.86 U	0.928 U	4.08 U	0.420 U	1.16 U	0.380 U	1.02 U	0.864 U	1.36 U	1.40 U	1.58 U	0.634 U	10.0 U	0.736 U	–	0.904 U
		05/06/21	Peristaltic	3.86 UJ	0.928 U	4.08 U	0.420 U	1.16 U	0.380 U	1.02 U	0.864 U	1.36 U	1.40 U	1.58 U	0.634 U	10.0 U	0.736 U	–	0.904 U
MW-182	Property, SW quadrant	11/08/19	Peristaltic	0.355 U	**0.326 J**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**88.9**	0.111 U	**1.26 J**	0.0972 U
		01/27/20	Peristaltic	178 U	61.5 U	163.0 U	96.5 U	50.5 U	54.0 U	95.0 U	62.0 U	65.0 U	73.5 U	60.5 U	46.5 U	640 U	55.5 U	379 U	48.6 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
MW-182		04/01/20	Peristaltic	17.8 U	6.15 U	16.3 U	9.65 U	5.05 U	5.40 U	9.50 U	6.20 U	6.50 U	7.35 U	6.05 U	4.65 U	64.0 U	5.55 U	37.9 U	4.86 U
(continued)		07/08/20	Peristaltic	9.65 U	2.32 U	10.2 UJ	1.05 U	2.90 U	**2.20 J**	2.54 U	2.16 U	3.40 U	3.50 U	3.94 U	1.59 U	25.0 U	1.84 U	–	2.26 U
		11/04/20	Peristaltic	9.65 U	3.05 UJ	10.2 U	1.05 U	2.90 U	0.950 U	2.54 U	2.16 U	3.40 U	3.50 U	3.94 U	1.59 U	**32.9 J**	1.84 U	–	2.26 U
		02/19/21	Peristaltic	96.5 U	23.2 U	102 U	10.5 U	29.0 U	9.50 U	25.4 U	21.6 U	34.0 U	35.0 U	39.4 U	15.9 U	250 U	18.4 U	–	22.6 U
		05/06/21	Peristaltic	386 UJ	92.8 UJ	408 U	42.0 U	116 U	38.0 U	102 U	86.4 UJ	136 U	140 U	158 U	63.4 U	1,000 UJ	73.6 U	–	90.4 U
	(dup)	05/06/21	Peristaltic	0.193 UJ	**4.95 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	**1.07 J**	0.0680 U	0.0700 U	0.0788 U	0.0317 U	**9.37 J**	0.0368 U	–	0.0452 U
MW-186	Property, SE quadrant	10/31/19	Flowing	0.355 U	0.123 U	0.325 UJ	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/29/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/02/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/08/20	Peristaltic	0.193 U	**0.105 J**	0.204 UJ	0.0210 U	0.0580 U	**0.0330 J**	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/04/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/16/21	Flowing	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/07/21	Flowing	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
Treatment Zone C Wells																			
IW-1C	Property, NE quadrant Decommissioned March, 2019	03/29/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
IW-4C	Property, NE quadrant Decommissioned March, 2019	04/26/18	Peristaltic	0.355 U	**0.642**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	**0.207 J**	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
IW-8C	Property, NE quadrant Decommissioned March, 2019	04/04/18	Peristaltic	0.355 U	**1.28**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	**0.376 J**	0.130 U	0.147 U	0.121 U	0.0929 U	**2.06 J**	0.111 U	0.757 U	0.0972 U
IW-9C	Property, NE quadrant Decommissioned March, 2019	04/02/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
IW-13C	Property, SW quadrant Decommissioned March, 2019	04/25/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
IW-15C	Property, SW quadrant Decommissioned March, 2019	03/30/18	Bladder	3.55 U	1.23 U	3.25 U	1.93 U	1.01 U	1.08 U	1.90 U	1.24 U	1.30 U	1.47 U	1.21 U	0.929 U	12.8 U	1.11 U	7.57 U	0.972 U
IW-19C	Property, SW quadrant Decommissioned March, 2019	03/29/18	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
IW-20C	Property, SW quadrant	03/30/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
(dup)	Decommissioned March, 2019	03/30/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
MW-167	Property, NE quadrant	11/04/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/28/20	Peristaltic	0.355 UJ	0.123 U	0.325 UJ	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		05/01/20	Peristaltic	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/09/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 UJ	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/05/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/04/21	Peristaltic	0.193 UJ	**0.0650 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	**0.0560 J**	0.500 U	0.0368 U	–	0.0452 U
		05/05/21	Peristaltic	0.193 UJ	**0.124 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-171	Property, SW quadrant	11/05/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**1.34 J**	0.111 U	0.757 U	0.0972 U
		01/23/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/02/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/09/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
MW-171		11/03/20	Peristaltic	0.193 U	**0.0900 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
(continued)		02/17/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
(dup)		02/17/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/07/21	Peristaltic	9.65 UJ	2.32 U	10.2 U	1.05 U	2.90 U	0.950 U	2.54 U	2.16 U	3.40 U	3.50 U	3.94 U	1.59 U	25.0 U	1.84 U	–	2.26 U
MW-175	Property, SE quadrant	11/01/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/28/20	Peristaltic	0.355 UJ	0.123 U	0.325 UJ	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		05/01/20	Peristaltic	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/09/20	Peristaltic	0.193 U	**0.0650 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/05/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/04/21	Peristaltic	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/05/21	Peristaltic	0.193 UJ	**0.0820 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-179	Property, SW quadrant	11/06/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**30.6**	0.111 U	0.757 U	0.0972 U
		01/27/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**22.2**	0.111 U	0.757 U	0.0972 U
		04/02/20	Peristaltic	7.10 UJ	2.46 U	6.50 UJ	3.86 U	2.02 U	2.16 U	3.80 U	2.48 U	2.60 U	2.94 U	2.42 U	1.86 U	25.6 U	2.22 U	15.1 U	1.94 U
		07/10/20	Peristaltic	3.86 U	0.928 U	4.08 U	0.420 U	1.16 UJ	0.380 U	1.02 U	0.864 U	1.36 U	1.40 U	1.58 U	0.634 U	10.0 U	0.736 U	–	0.904 U
		11/03/20	Peristaltic	3.86 U	0.928 U	4.08 U	0.420 U	1.16 U	0.380 U	1.02 U	0.864 U	1.36 U	1.40 U	1.58 U	0.634 U	10.0 U	0.736 U	–	0.904 U
		02/18/21	Peristaltic	96.5 U	23.2 U	102 U	10.5 U	29.0 U	9.50 U	25.4 U	21.6 U	34.0 U	35.0 U	39.4 U	15.9 U	250 U	18.4 U	–	22.6 U
		05/06/21	Peristaltic	48.3 U	11.6 UJ	51.0 U	5.25 U	14.5 U	4.75 U	12.7 U	10.8 U	17.0 U	17.5 U	19.7 U	7.93 U	125 U	9.20 U	–	11.3 UJ
MW-183	Property, SW quadrant	11/08/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/27/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/02/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/08/20	Peristaltic	0.193 U	**0.110 J**	0.204 UJ	0.0210 U	0.0580 U	**0.0480 J**	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/04/20	Peristaltic	0.193 U	0.0625 UJ	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/19/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/06/21	Peristaltic	19.3 U	4.64 UJ	20.4 U	2.10 U	5.80 U	**3.10 J**	5.08 U	4.32 U	6.80 U	7.00 U	7.88 U	3.17 U	50.0 U	3.68 U	–	4.52 UJ
MW-187	Property, SE quadrant	11/01/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/29/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/02/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/08/20	Peristaltic	0.193 U	**0.105 J**	0.204 UJ	0.0210 U	0.0580 U	**0.0480 J**	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/04/20	Peristaltic	0.193 U	0.0516 UJ	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/16/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/07/21	Peristaltic	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
Treatment Zone D Wells																			
IW-1D	Property, NE quadrant Decommissioned March, 2019	04/03/18	Bladder	3.55 U	**2.23 J**	3.25 U	1.93 U	1.01 U	1.08 U	1.90 U	1.24 U	1.30 U	1.47 U	1.21 U	0.929 U	**13.9 J**	1.11 U	7.57 U	0.972 U
IW-3D	Property, NE quadrant Decommissioned March, 2019	04/03/18	Bladder	0.355 U	**0.391 J**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	**0.134 J**	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
IW-4D	Property, SW quadrant Decommissioned March, 2019	03/29/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
IW-6D	Property, SW quadrant Decommissioned March, 2019	04/03/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
IW-8D	Property, SW quadrant Decommissioned March, 2019	04/04/18	Bladder	0.355 U	**0.289 J**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
IW-9D	Property, SW quadrant Decommissioned March, 2019	04/04/18	Bladder	0.355 U	**0.142 J**	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
IW-11D	Property, NE quadrant Decommissioned March, 2019	05/01/18	Bladder	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
MW-168	Property, NE quadrant	11/04/19	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/31/20	Flowing	0.355 UJ	0.123 U	0.325 UJ	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		05/01/20	Peristaltic	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/09/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/05/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	**3.86**	0.0368 U	–	0.0452 U
		02/04/21	Peristaltic	0.193 U	0.0464 U	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/05/21	Peristaltic	0.193 UJ	**0.112 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-172	Property, SW quadrant	11/05/19	Flowing	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/23/20	Flowing	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/02/20	Peristaltic	178.0 U	61.5 U	163.0 U	96.5 U	50.5 U	54.0 U	95.0 U	62.0 U	65.0 U	73.5 U	60.5 U	46.5 U	640 U	55.5 U	379 U	48.6 U
		07/09/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/03/20	Peristaltic	0.193 U	**0.0640 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/17/21	Flowing	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/07/21	Peristaltic	19.3 UJ	4.64 U	20.4 U	2.10 U	5.80 U	1.90 U	5.08 U	4.32 U	6.80 U	7.00 U	7.88 U	3.17 U	50.0 U	3.68 U	–	4.52 U
MW-176	Property, SE quadrant	11/01/19	Flowing	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/28/20	Flowing	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/28/20	Flowing	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		05/01/20	Peristaltic	0.481 U	0.322 U	0.276 U	0.126 U	0.107 U	0.0819 U	0.149 U	0.104 U	0.299 U	0.109 U	0.120 U	0.161 U	1.19 U	0.106 U	0.787 U	0.114 U
		07/09/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/05/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/04/21	Peristaltic	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/05/21	Peristaltic	0.193 UJ	**0.0830 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-180	Property, SW quadrant	11/06/19	Flowing	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**55.1**	0.111 U	0.757 U	0.0972 U
		01/24/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	**33.4**	0.111 U	0.757 U	0.0972 U
		04/01/20	Peristaltic	1.78 UJ	0.615 U	1.63 UJ	0.965 U	0.505 U	0.540 U	0.950 U	0.620 U	0.650 U	0.735 U	0.605 U	0.465 U	**24.0 J**	0.555 U	3.78 U	0.486 U
		07/10/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 UJ	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/03/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/18/21	Flowing	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/06/21	Peristaltic	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
MW-184	Property, SW quadrant	11/08/19	Flowing	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/27/20	Flowing	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/01/20	Peristaltic	3.55 U	1.23 U	3.25 U	1.93 U	1.01 U	1.08 U	1.90 U	1.24 U	1.30 U	1.47 U	1.21 U	0.929 U	12.8 U	1.11 U	7.57 U	0.972 U
		07/08/20	Peristaltic	0.193 U	**0.0690 J**	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/04/20	Peristaltic	1.93 U	0.464 U	2.04 U	0.210 U	0.580 U	0.190 U	0.508 U	0.432 U	0.680 U	0.700 U	0.788 U	0.317 U	5.00 U	0.368 U	–	0.452 U
		02/19/21	Flowing	1.93 UJ	0.464 U	2.04 U	0.210 U	0.580 U	0.190 U	0.508 U	0.432 U	0.680 U	0.700 U	0.788 U	0.317 U	5.00 U	0.368 U	–	0.452 U
		05/06/21	Peristaltic	0.965 U	0.232 UJ	1.02 U	0.105 U	0.290 U	0.0950 U	0.254 U	0.216 U	0.340 U	0.350 U	0.394 U	0.159 U	2.50 U	0.184 U	–	0.226 UJ

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromo-3-Chloropropane	1,2-Dibromoethane	1,2-Dichlorobenzene	1,2-Dichloroethane (EDC)	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichlorobenzene	1,3-Dichloropropane	1,4-Dichlorobenzene	2,2-Dichloropropane	2-Butanone (Methyl Ethyl Ketone/MEK)	2-Chlorotoluene	2-Hexanone	4-Chlorotoluene
Preliminary Cleanup Level (PCUL)				**15**	**80**	**0.20**	**0.050**	**600**	**4.8**	**5.0**	**80**	–	**160**	**75**	–	**4,800**	**160**	**40**	–
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**38**	**240**	–	–	**2,600**	**4.2**	**10**	**170**	–	–	**4.9**	–	**1.7E+06**	–	**7,300**	–
MW-188	Property, SE quadrant	10/31/19	Flowing	0.355 U	0.123 U	0.325 UJ	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		01/29/20	Flowing	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		04/02/20	Peristaltic	0.355 U	0.123 U	0.325 U	0.193 U	0.101 U	0.108 U	0.190 U	0.124 U	0.130 U	0.147 U	0.121 U	0.0929 U	1.28 U	0.111 U	0.757 U	0.0972 U
		07/08/20	Peristaltic	0.193 U	**0.0680 J**	0.204 UJ	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		11/04/20	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		02/16/21	Peristaltic	0.193 U	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
		05/07/21	Peristaltic	0.193 UJ	0.0464 U	0.204 U	0.0210 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	–	0.0452 U
			Number of Analytes Measured	1,240	1,270	1,270	1,240	1,270	1,240	1,270	1,240	1,270	1,270	1,270	1,270	1,223	1,270	775	1,269
			Number of Analytes Detected	0	114	0	0	4	50	24	43	1	0	1	2	78	0	5	0
			Frequency of Detection	0%	9%	0%	0%	0.3%	4%	2%	3%	0.1%	0%	0.1%	0.2%	6%	0%	1%	0%
			Maximum Detection	–	157	–	–	0.172 J+	3.10 J	1.20	13.2	0.133 J	–	0.144 J	0.128 J	456	–	3.36 J	–
			Minimum Detection	0.193 U	0.0464 U	0.110 UJ	0.010 U	0.0580 U	0.0190 U	0.0508 U	0.0432 U	0.0680 U	0.0700 U	0.0788 U	0.0317 U	0.500 U	0.0368 U	0.757 U	0.0452 U
			Number of Detections Above SL	0	2	0	0	0	0	0	0	–	0	0	–	0	0	0	–
			Frequency of Detection Above SL	0%	0%	0%	0%	0%	0%	0%	0%	–	0%	0%	–	0%	0%	0%	–

Notes:

Gasoline Range Organics Analyzed by NWTPH-Gx.
Diesel Range Organics and Heavy Oil analyzed by NWTPH-Dx.
VOCs analyzed by EPA Method 8260C or 8260D.
Results shown in micrograms per liter (µg/L).
PCULs and Screening Levels from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021.
All groundwater sampling performed by PES Environmental, Inc. unless otherwise indicated.
a = Results provided by Hart Crowser.
b = Results provided by Farallon Consulting.
c = Select sample results for MW-210 incorrectly identified with location SMW-3 on lab reports and sampling forms.
(split) = Split samples collected consecutively.
(dup) = Field duplicate sample.
– = Not analyzed, results not available, or information not applicable.
Detected results shown in **bold.**
Detections above the groundwater PCUL level are shown in **bold and highlighted in gray.**
Shallow Zone detections above the groundwater screening level for soil vapor are shown in **bold and highlighted in orange.**
Shallow Zone detections above the groundwater PCUL and screening level for soil vapor are shown in **bold highlighted in grayish-orange.**
U = Not detected at or above the laboratory method detection limit (MDL); detections above the MDL but below the laboratory reported detection limit (RDL) are qualified with a "J."
J = The identification of the analyte is acceptable; the reported value is an estimate.
J+ = The result is an estimated quantity, but the result may be biased high.
J- = The result is an estimated quantity, but the result may be biased low.
z = Elevated chlorinated VOCs detected within the GRO elution range. No discernible petroleum pattern present. Project level qualifier assigned per laboratory review.
GRO results above the screening level and qualified with "z" are not considered in the Maximum Detection and are not included in the Number of Detections Above SL.

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	–	**2.4**	–	**1.8**	–	**13**	**400**	**0.56**	**290**	–	**18,000**	**1.2**
Shallow Water Bearing Zone																			
DMW-1S	615 Dexter, SE quadrant	03/25/19[a]	Unknown	**1.5**	–	–	–	–	**1.5**	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U
		03/25/19[a]	Unknown	**2.5**	–	–	–	–	**1.8**	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U
		03/18/20[a]	Unknown	–	–	–	–	–	**2.9**	–	0.20 U	–	–	–	0.20 U	0.20 U	0.20 U	0.20 U	0.20 U
DMW-2S	615 Dexter, SE quadrant	03/18/20[a]	Unknown	–	–	–	–	–	0.20 U	–	0.20 U	–	–	–	0.20 U	0.20 U	0.20 U	0.20 U	0.20 U
DMW-4S	Alley S of SE quadrant of 615 Dexter	03/19/20[a]	Unknown	–	–	–	–	–	0.20 U	–	0.20 U	–	–	–	0.20 U	0.20 U	0.20 U	0.20 UJ	0.20 U
DMW-5IA	Alley S of 615 Dexter	03/19/20[a]	Unknown	–	–	–	–	–	0.20 U	–	0.20 U	–	–	–	0.20 U	0.20 U	0.20 U	0.20 UJ	0.20 U
DMW-6	615 Dexter, NE quadrant	03/18/20[a]	Unknown	–	–	–	–	–	0.20 U	–	0.20 U	–	–	–	0.20 U	0.20 U	0.20 U	0.20 U	0.20 U
F5	Property, NW quadrant Decommissioned March, 2019	03/28/17	Peristaltic	0.138 U	**0.888 J**	**38.3**	0.873 U	–	**0.515**	0.133 U	0.0800 U	0.186 U	0.157 U	**0.202 J**	0.159 U	0.140 U	0.128 U	**0.769**	0.0860 U
		06/22/17	Peristaltic	0.138 U	0.823 U	**37.9**	0.873 U	–	**0.374 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 UJ	0.159 U	0.140 U	0.128 U	**2.89**	0.0860 U
F9	Property, NE quadrant Decommissioned March, 2019	03/27/17	Peristaltic	0.138 U	0.823 U	**1.40 J**	0.873 U	–	**0.529**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/22/17	Peristaltic	0.138 U	0.823 U	**1.74 J**	0.873 U	–	**0.471 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 UJ	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
F13	Property, NE quadrant Decommissioned March, 2019	03/27/17	Peristaltic	0.138 U	0.823 U	**1.42 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/22/17	Peristaltic	0.138 U	0.823 U	**1.38 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 UJ	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/05/18	Peristaltic	0.138 U	0.823 U	2.35 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.136 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
FMW-143	9th Ave N ROW, E side	07/30/19[a]	Unknown	–	–	**–**	–	–	–	–	–	–	–	–	–	–	–	–	–
		10/31/19	Peristaltic	0.138 U	0.823 U	**1.15 J**	0.873 U	–	0.0896 U	0.133 UJ	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/22/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		05/14/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 UJ	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/22/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
G12	Property, NE quadrant Decommissioned March, 2019	03/27/17	Peristaltic	0.138 U	0.823 U	**2.71 J**	0.873 U	–	**0.243 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**0.344 J**	0.0860 U
		06/30/17	Peristaltic	0.138 U	0.823 U	**1.65 J**	0.873 U	–	**0.282 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**0.539 J**	0.0860 U
HMW-1S	SDOT Mercer Parcels, NE quadrant	3/25/19[a]	Peristaltic	1.0 U	–	–	–	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U
		03/11/20[a]	Unknown	–	–	–	–	–	0.20 U	–	0.20 U	–	–	–	0.20 U	0.20 U	0.20 U	0.20 U	0.20 U
HMW-2S	SDOT Mercer Parcels, NE quadrant	3/25/19[a]	Peristaltic	1.0 U	–	–	–	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U
		03/12/20[a]	Unknown	–	–	–	–	–	0.20 U	–	0.20 U	–	–	–	0.20 U	0.20 U	0.20 U	0.20 U	**0.26**
HMW-9S	SDOT Mercer Parcels, SW quadrant	03/17/20[a]	Unknown	–	–	–	–	–	0.20 U	–	0.20 U	–	–	–	0.20 U	0.20 U	0.20 U	0.20 U	0.20 U
HMW-10S	SDOT Mercer Parcels, SE quadrant	03/16/20[a]	Unknown	–	–	–	–	–	0.20 U	–	0.20 U	–	–	–	0.20 U	0.20 U	0.20 U	0.20 U	**0.26**
HMW-11S	SDOT Mercer Parcels, SE quadrant	03/11/20[a]	Unknown	–	–	–	–	–	0.20 U	–	0.20 U	–	–	–	0.20 U	0.20 U	0.20 U	0.20 U	**0.26**
HMW-20S	SDOT Mercer Parcels, NW quadrant	9/18/20[a]	Unknown	1.0 U	10 U	50 UJ	–	–	0.20 U	1.0 U	0.20 U	5.0 U	5.0 U		0.20 U	0.20 U	0.50 U	0.20 U	0.20 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	–	**2.4**	–	**1.8**	–	**13**	**400**	**0.56**	**290**	–	**18,000**	**1.2**
HMW-21S	SDOT Mercer Parcels, SE quadrant	11/3/20[a]	Unknown	–	–	–	–	–	–	–	–	–	–		–	–	–	–	–
HMW-22S	SDOT Mercer Parcels, SE quadrant	11/3/20[a]	Unknown	–	–	–	–	–	–	–	–	–	–		–	–	–	–	–
J5	Property, SW quadrant	03/21/17	Peristaltic	0.138 U	0.823 U	3.24 U	0.873 U	–	**0.580**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/26/17	Peristaltic	0.138 U	0.823 U	**1.15 J**	0.873 U	–	**0.252 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 UJ	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/05/18	Peristaltic	0.138 U	0.823 U	2.25 U	0.873 U	–	**0.638**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**1.09 J**	0.0860 U
	Decommissioned March, 2019																		
J15	Property, SE quadrant	03/27/17	Peristaltic	0.138 U	0.823 U	**1.82 J**	0.873 U	–	**0.188 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/26/17	Peristaltic	0.138 U	0.823 U	**1.49 J**	0.873 U	–	**0.173 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 UJ	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
(dup)		06/26/17	Peristaltic	0.138 U	0.823 U	**1.91 J**	0.873 U	–	**0.173 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 UJ	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/05/18	Peristaltic	0.138 U	0.823 U	**7.35 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	Decommissioned March, 2019																		
K8	Property, SW quadrant	03/21/17	Peristaltic	0.138 U	0.823 U	3.26 U	0.873 U	–	**0.239 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/26/17	Peristaltic	0.138 U	0.823 U	**1.07 J**	0.873 U	–	**0.246 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 UJ	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/05/18	Peristaltic	0.138 U	0.823 U	2.89 U	0.873 U	–	**0.251 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	Decommissioned March, 2019																		
M15	Property, SE quadrant	03/27/17	Peristaltic	0.138 U	0.823 U	**1.45 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
(dup)		03/27/17	Peristaltic	0.138 U	0.823 U	**1.79 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**0.196 J**	0.0860 U
		06/26/17	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 UJ	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/05/18	Peristaltic	0.138 U	0.823 U	2.37 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.144 U	0.159 U	0.140 U	0.128 U	**2.81**	0.0860 U
	Decommissioned March, 2019																		
MW-8	Seattle Roy Aloha Shops, N end	03/20/17	Peristaltic	0.138 U	0.823 U	3.68 U	0.873 U	–	**0.145 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/13/18	Peristaltic	0.138 U	0.823 U	**2.85 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		07/18/19	Peristaltic	0.138 U	0.823 U	2.98 UJ	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/10/19	Peristaltic	0.138 U	0.823 UJ	1.05 UJ	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/16/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	**0.156 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		05/06/20	Peristaltic	0.120 U	0.478 U	11.3 UJ	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/14/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-9	8th Ave N ROW, E side	03/20/17	Peristaltic	0.138 U	0.823 U	4.08 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/20/17	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
(dup)		06/20/17	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/05/18	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/21/19	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/26/19	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		07/16/19	Peristaltic	0.138 U	0.823 U	2.40 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/17/19	Peristaltic	0.138 U	0.823 U	1.05 UJ	0.873 U	–	0.0896 U	0.133 UJ	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		11/24/20	Peristaltic	0.0932 U	0.400 U	**6.84 J+**	0.0760 U	0.580 U	**0.0250 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/05/21	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0420**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/12/21	Peristaltic	0.0932 U	0.400 U	**3.55 J+**	0.0760 U	0.580 U	**0.0290 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
(dup)		05/12/21	Peristaltic	0.0932 U	0.400 U	0.548 UJ	0.0760 U	0.580 U	**0.0280 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW121	8th Ave N ROW, E side	03/28/17	Peristaltic	0.138 U	0.823 U	**2.32 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/20/17	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	**0.186 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/05/18	Peristaltic	0.138 U	0.823 U	2.74 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	–	**2.4**	–	**1.8**	–	**13**	**400**	**0.56**	**290**	–	**18,000**	**1.2**
MW121		01/31/19	Peristaltic	0.138 U	0.823 U	**7.53 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
(continued)		04/29/19	Peristaltic	0.138 U	0.823 U	4.49 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		07/19/19	Peristaltic	0.138 U	0.823 U	**1.70 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		11/30/20	Bladder	0.0932 U	0.400 U	**5.49 J+**	0.0760 U	0.580 U	**0.0290 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/05/21	Peristaltic	0.0932 U	0.400 U	3.27 U	0.0760 U	0.580 U	**0.0850**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/12/21	Peristaltic	0.0932 U	0.400 U	**5.76 J+**	0.0760 U	0.580 U	**0.0260 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
	(dup)	05/12/21	Peristaltic	0.0932 U	0.400 U	**4.04 J**	0.0760 U	0.580 U	**0.0290 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW125	Valley Street ROW, N side	03/22/17	Peristaltic	0.138 U	0.823 U	3.20 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/28/17	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/06/18	Peristaltic	0.138 U	0.823 U	1.33 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/21/19	Peristaltic	0.138 U	0.823 U	**1.66 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/23/19	Peristaltic	0.138 U	0.823 U	**6.93 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		07/18/19	Peristaltic	0.138 U	0.823 U	**1.89 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/18/19	Bladder	0.138 U	0.823 U	**1.79 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/29/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		11/17/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/02/21	Peristaltic	0.0932 U	0.400 U	1.98 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/11/21	Peristaltic	0.0932 U	0.400 U	**1.77 J+**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 UJ	0.0166 U
	(dup)	05/11/21	Peristaltic	0.0932 U	0.400 U	**1.99 J+**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 UJ	0.0166 U
MW-154	Roy St ROW S side	04/30/18	Bladder	0.138 U	0.823 U	**12.9 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/21/19	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/24/19	Bladder	0.138 U	0.823 U	2.68 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	**0.369 J**	0.0860 U
		07/15/19	Bladder	0.138 U	0.823 U	3.42 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/14/19	Bladder	0.138 U	0.823 UJ	1.05 UJ	0.873 UJ	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/21/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		04/30/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 UJ	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/10/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/09/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0230 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	**0.117**
		02/08/21	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0220 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/10/21	Bladder	0.0932 U	0.400 U	**1.04 J+**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 UJ	0.0166 U
MW-155	Roy Street ROW, S side	04/27/18	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/21/19	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/23/19	Peristaltic	0.138 U	0.823 U	**1.86 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		07/23/19	Bladder	0.138 U	0.823 U	1.69 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/16/19	Bladder	0.138 U	0.823 U	1.06 U	0.873 U	–	0.0896 U	0.133 UJ	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/20/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		05/05/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		08/03/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0310 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/11/20	Bladder	0.0932 U	0.400 UJ	0.548 UJ	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-159	8th Ave N ROW, E side	04/26/18	Peristaltic	0.138 U	0.823 U	1.86 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/21/19	Peristaltic	0.138 U	0.823 U	**1.98 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/26/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	**0.179 J**	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
	(dup)	04/26/19	Bladder	0.138 U	0.823 U	1.65 U	0.873 U	–	**0.193 J**	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	–	**2.4**	–	**1.8**	–	**13**	**400**	**0.56**	**290**	–	**18,000**	**1.2**
MW-159 (continued)		07/22/19	Bladder	0.138 U	0.823 U	**2.13 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/29/20	Bladder	0.138 U	0.823 U	**1.19 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		11/11/20	Bladder	0.0932 U	0.400 UJ	**2.27 J**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/08/21	Peristaltic	0.0932 U	0.400 U	**6.07 J**	0.0760 U	0.580 U	**0.0340 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/11/21	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0200 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 UJ	0.0166 U
MW-210[c]	Valley Street ROW, N side	03/30/17	Peristaltic	0.138 U	0.823 U	1.40 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/21/17	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/09/18	Peristaltic	0.138 U	0.823 U	1.05 UJ	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/11/19	Peristaltic	0.138 U	0.823 UJ	1.05 UJ	0.873 UJ	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/17/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		04/09/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		07/07/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 UJ	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-214 (dup)	Valley Street ROW, S side	03/30/17	Peristaltic	0.138 U	0.823 U	1.75 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		03/30/17	Peristaltic	0.138 U	0.823 U	1.27 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/09/18	Peristaltic	0.138 U	0.823 U	1.05 UJ	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/11/19	Peristaltic	0.138 U	0.823 UJ	1.05 UJ	0.873 UJ	–	**1.95**	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/20/20	Peristaltic	0.138 U	0.823 U	**7.48 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/07/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		07/06/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-301 (dup)	Valley Street ROW, S side	11/30/20	Bladder	0.0932 U	0.400 U	**1.25 J+**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	**0.524**
		11/30/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	**0.515**
		02/05/21	Bladder	0.0932 U	0.400 U	1.46 U	0.0760 U	0.580 U	**0.0790**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	**0.0770 J**
		05/14/21	Bladder	0.0932 U	0.400 U	1.73 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	**0.209**
		05/14/21	Bladder	0.0932 U	0.400 U	2.23 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	**0.250**
MW-305	Roy St ROW, S side	10/15/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 UJ	0.141 U	0.0860 U
		01/15/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/28/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 UJ	**0.273 J**	0.117 U	0.140 U	0.192 U	0.111 U
		07/27/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/06/20	Bladder	0.0932 U	0.400 U	0.548 UJ	0.0760 U	0.580 U	**0.0314 J**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	**0.118 J**	0.0229 U	0.0180 U	0.0432 UJ	**0.0515 J**
		05/18/21	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 UJ	0.0166 U
MW-310	Alley E of Seattle Roy Aloha Shops	10/10/19	Peristaltic	0.138 U	0.823 U	**1.91 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/14/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/08/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		08/04/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0270 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		08/04/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0360 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/06/20	Bladder	0.0932 U	0.400 U	0.548 UJ	0.0760 U	0.580 U	**0.0275 J**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 UJ	0.0166 U
		05/03/21	Peristaltic	0.0932 U	0.400 U	0.548 UJ	0.0760 UJ	0.580 U	**0.0420**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-312	Alley E of Seattle Roy Aloha Shops	10/11/19	Peristaltic	0.138 U	0.823 UJ	**1.53 J**	0.873 UJ	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/21/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		04/22/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		08/04/20	Bladder	0.0932 U	0.400 U	**3.29**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/11/20	Bladder	0.0932 U	0.400 UJ	**2.42 J-**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	–	**2.4**	–	**1.8**	–	**13**	**400**	**0.56**	**290**	–	**18,000**	**1.2**
MW-312 (continued)		05/03/21	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0260 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-313	Alley E of Seattle Roy Aloha Shops	10/10/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/14/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		05/04/21	Bladder	0.0932 U	0.400 U	**2.16**	0.0760 U	0.580 U	**0.0300 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-320	9th Ave N ROW, W side	10/07/19	Peristaltic	0.138 U	0.823 U	2.81 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/20/20	Peristaltic	0.138 U	0.823 U	**1.59 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/29/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 UJ	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/28/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 UJ	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		11/12/20	Bladder	0.0932 U	0.400 UJ	0.783 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/20/21	Peristaltic	0.0932 U	0.400 U	1.74 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 UJ	0.0166 U
MW-332	Roy St ROW, N side	05/04/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/30/20	Bladder	0.0932 U	0.400 U	0.548 UJ	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/12/20	Bladder	0.0932 U	0.400 U	0.618 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/20/21	Peristaltic	0.0932 U	0.400 U	1.63 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-337	Lake Union Park, N end	05/07/20	Peristaltic	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 UJ	0.136 U	0.129 U	0.605 UJ	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 UJ	0.111 U
		07/23/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/10/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0190 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/04/21	Peristaltic	0.0932 U	0.400 U	0.548 UJ	0.0760 UJ	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-339 (dup)	Lake Union Park, S end	05/14/20	Peristaltic	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 UJ	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		05/14/20	Peristaltic	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 UJ	0.605 U	**0.0964 J**	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/23/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/09/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0190 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/25/21	Peristaltic	0.0932 U	0.400 U	**2.75**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
N7	Property, SW quadrant Decommissioned March, 2019	03/30/17	Peristaltic	0.138 U	0.823 U	2.16 U	0.873 U	–	**0.178 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/27/17	Peristaltic	0.138 U	0.823 U	**1.41 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**0.313 J**	0.0860 U
R-MW2	Property, NE quadrant Decommissioned March, 2019	03/21/17	Peristaltic	0.138 U	0.823 U	3.29 U	0.873 U	–	**0.272 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/15/17	Peristaltic	0.138 U	0.823 U	**1.48 J**	0.873 U	–	**0.694**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/02/18	Peristaltic	0.138 U	0.823 U	**3.51 J**	0.873 U	–	**0.568**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
R-MW3	Property, NE quadrant Decommissioned March, 2019	03/21/17	Peristaltic	0.138 U	0.823 U	14.3 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/28/17	Peristaltic	0.138 U	0.823 U	5.00 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/04/18	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
R-MW5	Dexter Ave N ROW, E side	03/23/17	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/16/17	Bladder	0.138 U	0.823 U	1.05 UJ	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/11/18	Bladder	0.138 U	0.823 UJ	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/03/19	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/22/19	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	**1.28**
		07/16/19	Bladder	0.138 U	0.823 U	1.65 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	**0.152 J**
		10/21/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 UJ	–	0.0896 U	0.133 U	0.0800 UJ	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/24/20	Bladder	0.138 U	0.823 U	1.05 UJ	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	–	**2.4**	–	**1.8**	–	**13**	**400**	**0.56**	**290**	–	**18,000**	**1.2**
R-MW5		11/18/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
(continued)		02/11/21	Bladder	0.0932 U	0.400 U	1.45 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
(dup)		02/11/21	Bladder	0.0932 U	0.400 U	2.31 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/17/21	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	**0.296**
R-MW6	8th Ave N ROW, E side	03/21/17	Peristaltic	0.138 U	0.823 U	3.14 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**0.977**	0.0860 U
		06/20/17	Peristaltic	0.138 U	0.823 UJ	1.05 U	0.873 U	–	**0.167 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/06/18	Peristaltic	0.138 U	0.823 U	1.55 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/25/19	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	**0.142 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/25/19	Peristaltic	0.138 U	0.823 U	2.91 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		12/01/20	Peristaltic	0.0932 U	0.400 U	**5.51 J-**	0.0760 U	0.580 U	**0.0490**	0.0420 U	0.0315 UJ	0.239 U	0.148 U	–	0.0432 UJ	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/03/21	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	**0.132**
		05/17/21	Peristaltic	0.0932 U	0.400 U	**2.19 J+**	0.0760 U	0.580 U	**0.0770**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 UJ	0.0166 U
SCL-MW101	Alley E of Seattle Roy Aloha Shops	03/28/17	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	**6.74**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/14/17	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	**18.6**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/06/18	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	**10.6**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/09/19	Peristaltic	**0.312 J**	0.823 U	1.05 U	0.873 U	–	**11.2**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/17/20	Peristaltic	0.138 U	0.823 U	**7.66 J**	0.873 U	–	**15.4**	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		04/07/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	**7.26**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		11/24/20	Peristaltic	**0.218**	0.400 U	0.548 U	0.0760 U	0.580 U	**14.6**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/04/21	Peristaltic	0.0932 U	0.400 U	0.548 UJ	0.0760 UJ	0.580 U	**6.04**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
SCL-MW105	Alley E of Seattle Roy Aloha Shops	03/28/17	Peristaltic	**0.915 J**	4.12 U	5.25 U	4.36 U	–	**257**	0.665 U	0.400 U	0.930 U	0.785 U	0.505 U	0.795 U	0.700 U	0.640 U	0.705 U	**20.9**
		06/15/17	Peristaltic	**1.08**	0.823 U	1.05 UJ	0.873 U	–	**208**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/06/18	Peristaltic	1.38 U	8.23 U	10.5 U	8.73 U	–	**181**	1.33 U	0.800 U	1.86 U	1.57 U	1.01 U	1.59 U	1.40 U	1.28 U	1.41 U	0.860 U
		10/10/19	Peristaltic	**1.96**	0.823 U	1.05 U	0.873 U	–	**133**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/17/20	Peristaltic	**1.01**	0.823 U	1.05 U	0.873 U	–	**142**	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		04/01/20	Peristaltic	**0.721**	0.823 U	1.05 U	0.873 U	–	**95.1**	0.133 U	0.0800 U	0.186 UJ	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		07/24/20	Peristaltic	**1.26**	0.400 U	0.548 U	0.0760 U	0.580 U	**86.6**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
SCS-2	Seattle Roy Aloha Shops, N End	03/20/17	Peristaltic	**0.379 J**	0.823 U	**78.8**	0.873 U	–	**51.8**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/12/17	Peristaltic	**0.298 J**	0.823 U	**7.95 J**	0.873 U	–	**58.9**	0.133 U	0.0800 U	0.186 U	0.157 U	**0.147 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/13/18	Peristaltic	**0.547**	0.823 U	**24.1 J**	0.873 U	–	**44.3**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		07/18/19	Peristaltic	**0.760**	0.823 U	1.05 U	0.873 U	–	**15.5**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
(dup)		07/18/19	Peristaltic	**0.698**	0.823 U	1.05 U	0.873 U	–	**15.0**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/10/19	Peristaltic	**0.676**	0.823 U	1.05 U	0.873 U	–	**20.3**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/16/20	Peristaltic	1.38 U	8.23 U	10.5 U	8.73 U	–	**16.9**	1.33 U	0.800 U	1.86 U	1.57 U	1.01 U	1.59 U	1.40 U	1.28 U	1.41 U	0.860 U
Intermediate A Water-Bearing Zone																			
BB-8	Roy Street ROW, S side	03/22/17	Peristaltic	0.138 U	0.823 U	2.52 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/14/17	Peristaltic	0.138 U	0.823 U	**1.50 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/11/18	Peristaltic	0.138 U	0.823 UJ	**1.16 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
(dup)		04/11/18	Peristaltic	0.138 U	0.823 UJ	**1.25 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/23/19	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/23/19	Peristaltic	0.138 U	0.823 U	**2.03 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	–	**2.4**	–	**1.8**	–	**13**	**400**	**0.56**	**290**	–	**18,000**	**1.2**
BB-8		07/17/19	Bladder	0.138 U	0.823 U	**2.06 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
(continued)		10/22/19	Bladder	0.138 U	0.823 U	**1.24 J**	0.873 UJ	–	0.0896 U	0.133 U	0.0800 UJ	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
(dup)		10/22/19	Bladder	0.138 U	0.823 U	**1.77 J**	0.873 UJ	–	0.0896 U	0.133 U	0.0800 UJ	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/20/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
(dup)		01/20/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		05/12/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/27/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0570**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
(dup)		07/27/20	Bladder	0.0932 U	0.400 U	1.66 U	0.0760 U	0.580 U	**0.0660**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/17/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0950**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/11/21	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0490**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		06/07/21	Bladder	0.0932 U	0.400 U	**1.67**	0.0760 U	0.580 U	**0.0190 J**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
DMW-3IA	615 Dexter, NE quadrant	03/18/20[a]	Unknown	–	–	–	–	–	0.20 U	–	0.20 U	–	–	–	0.20 U	0.20 U	0.20 U	0.20 U	0.20 U
FMW-142	9th Ave N ROW, E side	07/29/19[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		10/31/19	Peristaltic	0.138 U	0.823 U	**3.11 J**	0.873 UJ	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.894**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/22/20	Peristaltic	0.138 U	0.823 U	**1.20 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/28/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 UJ	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/08/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/04/20	Bladder	0.0932 U	0.400 U	0.548 UJ	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/25/21	Peristaltic	0.0932 U	0.400 U	**1.38**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
GEI-1	Block 37, SW quadrant	03/24/17	Peristaltic	0.138 U	0.823 U	**2.90 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/13/17	Bladder	0.138 U	0.823 U	1.05 UJ	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/22/19	Peristaltic	0.138 U	0.823 U	**1.91 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		07/16/19	Bladder	0.138 U	0.823 U	2.32 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/21/19	Peristaltic	0.138 U	0.823 UJ	**1.45 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/22/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/29/20	Peristaltic	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 UJ	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
(dup)		04/29/20	Peristaltic	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 UJ	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/30/20	Peristaltic	0.0932 U	0.400 U	0.548 UJ	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
GEI-MW-1	Block 79 East, N end	01/23/20	Peristaltic	0.138 U	0.823 U	1.05 UJ	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/29/20	Peristaltic	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 UJ	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		08/07/20	Peristaltic	0.0932 U	0.400 U	**3.48 J**	0.0760 U	0.580 U	**0.0320 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/10/20	Peristaltic	0.0932 U	0.400 UJ	0.578 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U		0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/13/21	Peristaltic	0.0932 U	0.400 U	**1.23 J+**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
HC-4	601 Dexter, NE quadrant	04/12/19[a]	Unknown	1.0 U	–	–	–	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U
HMW-2IA	SDOT Mercer Parcels, NE quadrant	03/25/19[a]	Peristaltic	1.0 U	–	–	–	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U
		03/12/20[a]	Unknown	–	–	–	–	–	2.0 U	–	2.0 U	–	–		2.0 U	2.0 U	2.0 U	2.0 U	2.0 U
HMW-3IA	SDOT Mercer Parcels, NW quadrant	03/25/19[a]	Peristaltic	1.0 U	–	–	–	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U
		03/13/20[a]	Unknown	–	–	–	–	–	0.20 U	–	0.20 U	–	–		0.20 U	0.20 U	0.20 U	0.20 U	0.20 U
HMW-6IA	SDOT Mercer Parcels, SW quadrant	03/13/20[a]	Unknown	–	–	–	–	–	0.20 U	–	0.20 U	–	–	–	0.20 U	0.20 U	0.20 U	0.20 U	0.20 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	**–**	**2.4**	**–**	**1.8**	**–**	**13**	**400**	**0.56**	**290**	**–**	**18,000**	**1.2**
HMW-9IA	SDOT Mercer Parcels, SW quadrant	03/19/20[a]	Unknown	–	–	–	–	–	0.20 U	–	0.20 U	–	–	–	0.20 U	0.20 U	0.20 U	0.20 UJ	0.20 U
		06/02/21	Bladder	0.0932 U	0.400 U	**1.81**	0.0760 U	0.580 U	**0.0450**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
HMW-20IA	SDOT Mercer Parcels, NW quadrant	09/18/20[a]	Unknown	1.0 U	–	–	–	–	–		–	–	–		–	–	0.50 U	0.20 U	0.20 U
		06/02/21	Bladder	0.0932 U	0.400 U	**1.56**	0.0760 U	0.580 U	**0.0840**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW107	8th Ave N ROW, W side	03/27/17	Peristaltic	0.138 U	0.823 U	**11.0 J**	0.873 U	–	**0.204 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**0.406 J**	0.0860 U
		06/19/17	Peristaltic	0.138 U	0.823 UJ	**2.99 J**	0.873 U	–	**0.238 J**	0.133 U	0.0800 U	0.186 U	0.157 U	**0.162 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/09/18	Peristaltic	0.138 U	0.823 U	**59.3 J**	0.873 U	–	**0.193 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**4.31**	0.0860 U
		01/30/19	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	**0.215 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**3.52**	0.0860 U
		05/01/19	Peristaltic	0.138 U	0.823 U	5.66 U	0.873 U	–	**0.188 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**4.02 J**	0.0860 U
		07/22/19	Bladder	0.138 U	0.823 U	**1.28 J**	0.873 U	–	**0.188 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**3.61**	0.0860 U
		10/15/19	Bladder	0.138 U	0.823 U	**1.21 J**	0.873 U	–	**0.167 J**	0.133 UJ	0.0800 U	0.186 U	0.157 U	**0.342 J**	0.159 U	0.140 U	0.128 U	**3.45**	0.0860 U
		01/28/20	Bladder	2.76 U	16.5 U	21.0 U	17.5 U	–	1.79 U	2.66 U	1.60 U	3.72 U	3.14 U	2.02 U	3.18 U	2.80 U	2.56 U	2.82 U	1.72 U
		04/03/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	**0.298 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**2.32 J**	0.0860 U
		07/31/20	Bladder	2.33 U	10.0 U	13.7 UJ	1.90 U	14.5 U	0.400 U	1.05 U	0.788 U	5.98 U	3.70 UJ	–	1.08 U	0.573 U	0.450 U	1.08 U	0.415 U
		12/01/20	Peristaltic	2.33 U	10.0 U	**76.3 J+**	1.90 U	14.5 U	**1.65**	1.05 U	0.788 U	5.98 U	3.70 U	–	1.08 U	0.573 U	0.450 U	1.08 U	0.415 U
		02/02/21	Peristaltic	0.0932 U	**2.97**	**6.13**	0.0760 U	0.580 U	**0.112**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		06/02/21	Peristaltic	0.0932 U	**1.16**	**3.74**	0.0760 U	0.580 U	**0.0960**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	**0.251**	0.0166 U
MW108	Alley E of Seattle Roy Aloha Shops	03/28/17	Peristaltic	0.138 U	0.823 U	**1.40 J**	0.873 U	–	**1.59**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/27/17	Bladder	0.138 U	0.823 U	**2.03 J**	0.873 U	–	**1.26**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/06/18	Peristaltic	0.138 U	0.823 U	1.16 U	0.873 U	–	**4.00**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**0.595 J**	0.0860 U
	(dup)	04/06/18	Peristaltic	0.138 U	0.823 U	1.11 U	0.873 U	–	**3.83**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/22/19	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	**1.67**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/29/19	Peristaltic	0.138 U	0.823 U	3.41 U	0.873 U	–	**3.20**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		07/15/19	Peristaltic	0.138 U	0.823 U	1.90 U	0.873 U	–	**2.90**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/10/19	Peristaltic	0.138 U	0.823 U	**1.73 J**	0.873 U	–	**3.16**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/14/20	Peristaltic	3.45 U	20.6 U	26.3 U	21.8 U	–	**4.55 J**	3.33 U	2.00 U	4.65 U	3.93 U	2.53 U	3.97 U	3.50 U	3.20 U	3.53 U	2.15 U
		04/22/20	Bladder	3.00 U	12.0 U	282 U	16.8 U	–	**25.6**	2.95 U	3.40 U	3.22 U	15.1 U	–	3.20 U	2.93 U	3.50 U	4.80 U	2.78 U
		07/16/20	Bladder	2.33 U	10.0 U	13.7 U	1.90 U	14.5 U	**29.7**	1.05 U	0.788 U	5.98 U	3.70 U	–	1.08 U	0.573 U	0.450 U	1.08 U	**1.15 J**
	(dup)	07/16/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**34.3**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/04/20	Bladder	2.33 U	10.0 U	**98.4 J-**	1.90 U	14.5 U	**46.6**	1.05 U	0.788 U	5.98 U	3.70 U	–	1.08 U	0.573 U	0.450 U	1.08 U	0.415 U
		02/09/21	Peristaltic	0.466 U	2.00 U	2.74 U	0.380 U	2.90 U	**2.89**	0.210 U	0.158 U	1.20 U	0.740 U	–	0.216 U	0.115 U	0.0900 U	0.216 U	0.0830 U
		05/03/21	Peristaltic	0.466 U	2.00 U	2.74 UJ	0.380 UJ	2.90 U	**2.28**	0.210 U	0.158 U	1.20 U	0.740 U	–	0.216 U	0.115 U	0.0900 U	0.216 U	0.0830 U
MW109	Alley E of Seattle Roy Aloha Shops	03/29/17	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/27/17	Bladder	0.138 U	0.823 U	**1.20 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/06/18	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/23/19	Peristaltic	0.138 U	0.823 U	**1.54 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/29/19	Peristaltic	0.138 U	0.823 U	3.78 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		07/15/19	Peristaltic	0.138 U	0.823 U	1.78 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/15/19	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 UJ	0.141 U	0.0860 U
		01/21/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		04/22/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/06/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0340 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/02/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0550**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	–	**2.4**	–	**1.8**	–	**13**	**400**	**0.56**	**290**	–	**18,000**	**1.2**
MW109		02/09/21	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0520**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
(continued)		05/03/21	Peristaltic	0.0932 U	0.400 U	0.548 UJ	0.0760 UJ	0.580 U	**0.0430**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW110	Alley E of Seattle	03/23/17	Peristaltic	0.138 U	0.823 U	2.62 U	0.873 U	–	**0.330 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	Roy Aloha Shops	06/27/17	Bladder	0.138 U	0.823 U	2.62 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/09/18	Bladder	0.138 U	0.823 U	**1.55 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/23/19	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
(dup)		01/23/19	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/26/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	**0.291 J**	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	7.05 UJ	0.0860 U
		07/15/19	Bladder	0.138 U	0.823 U	2.38 U	0.873 U	–	**0.285 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/15/19	Bladder	0.138 U	0.823 U	**1.11 J**	0.873 U	–	**0.233 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 UJ	0.141 U	0.0860 U
		01/16/20	Bladder	0.690 U	4.12 U	5.25 U	4.37 U	–	0.448 U	0.665 U	0.400 U	0.930 U	0.785 U	0.505 U	0.795 U	0.700 U	0.640 U	0.705 U	0.430 U
		04/22/20	Bladder	0.600 U	2.39 U	56.5 U	3.36 U	–	**0.487 J**	0.590 U	0.680 U	0.645 U	3.03 U	0.481 U	0.640 U	0.585 U	0.700 U	0.960 U	0.555 U
		07/16/20	Bladder	0.466 U	2.00 U	2.74 U	0.380 U	2.90 U	**0.335**	0.210 U	0.158 U	1.20 U	0.740 U	–	0.216 U	0.115 U	0.0900 U	0.216 U	0.0830 U
		11/04/20	Bladder	4.66 U	20.0 U	**179 J-**	3.80 U	29.0 U	0.800 U	2.10 U	1.58 U	12.0 U	7.40 U	–	2.16 U	1.15 U	0.900 U	2.16 U	**1.39 J**
		02/09/21	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.125**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/04/21	Bladder	0.932 U	4.00 U	5.48 U	0.760 U	5.80 U	0.160 U	0.420 U	0.315 U	2.39 U	1.48 U	–	0.432 U	0.229 U	0.180 U	0.432 U	0.166 U
MW115	9th Ave N ROW, W side	03/22/17	Peristaltic	0.138 U	0.823 U	2.67 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/22/17	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 UJ	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/11/18	Peristaltic	0.138 U	0.823 UJ	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/30/19	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		07/17/19	Peristaltic	0.138 U	0.823 U	**2.55 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/22/19	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 UJ	–	0.0896 U	0.133 U	0.0800 UJ	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/20/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		05/05/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/28/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 UJ	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		11/12/20	Bladder	0.0932 U	0.400 UJ	0.691 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/12/21	Bladder	0.0932 U	0.400 U	3.76 U	0.0760 U	0.580 U	**0.0330 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/25/21	Peristaltic	0.0932 U	0.400 U	**1.34**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW116	9th Ave N ROW, W side	03/21/17	Peristaltic	0.138 U	0.823 U	3.32 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/16/17	Bladder	0.138 U	0.823 U	1.05 UJ	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/11/18	Peristaltic	0.138 U	0.823 UJ	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/30/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		07/17/19	Peristaltic	0.138 U	0.823 U	**1.28 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/31/19	Peristaltic	0.138 U	0.823 U	**3.74 J**	0.873 UJ	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/21/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		04/29/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 UJ	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/28/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 UJ	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		11/12/20	Bladder	0.0932 U	0.400 UJ	0.548 UJ	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 UJ	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/11/21	Peristaltic	0.0932 U	0.400 U	**1.12 J+**	0.0760 U	0.580 U	**0.0370 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/25/21	Peristaltic	0.0932 U	0.400 U	**1.34**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW119	9th Ave N ROW, W side	03/29/17	Peristaltic	0.138 U	0.823 U	**1.28 J**	0.873 U	–	**0.139 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/28/17	Bladder	0.138 U	0.823 U	3.73 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/05/18	Peristaltic	0.138 U	0.823 U	2.04 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	–	**2.4**	–	**1.8**	–	**13**	**400**	**0.56**	**290**	–	**18,000**	**1.2**
MW119		01/21/19	Peristaltic	0.138 U	0.823 U	**4.46 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
(continued)		04/29/19	Peristaltic	0.138 U	0.823 U	1.90 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		07/19/19	Peristaltic	0.138 U	0.823 U	**5.73 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/10/19	Peristaltic	0.138 U	0.823 U	**1.20 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		11/11/19[o]	Peristaltic	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/14/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
(split)		01/14/20[o]	Peristaltic	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/18/20[p]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		03/24/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/27/20	Peristaltic	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 UJ	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		05/19/20[p]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/08/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0430**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		07/28/20[p]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		09/17/20[p]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/11/20	Bladder	0.0932 U	0.400 UJ	0.936 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		12/03/20[p]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/10/21	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0470**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
(split)		02/10/21[p]	Peristaltic	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/20/21	Bladder	0.0932 U	0.400 U	**2.27**	0.0760 U	0.580 U	**0.0410**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW120	8th Ave N ROW, E side	03/28/17	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/28/17	Bladder	0.138 U	0.823 U	3.40 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/09/18	Peristaltic	0.138 U	0.823 U	**1.83 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/24/19	Peristaltic	0.138 U	0.823 U	1.05 UJ	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		05/03/19	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
(dup)		05/03/19	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	**0.142 J**
		07/16/19	Peristaltic	0.138 U	0.823 U	2.01 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/17/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
(dup)		10/17/19	Bladder	0.138 U	0.823 U	1.20 U	0.873 U	–	0.0896 U	0.133 UJ	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/17/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	**0.0983 J**	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		04/23/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/14/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0680**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/30/20	Bladder	0.0932 U	0.400 U	**1.06 J+**	0.0760 U	0.580 U	**0.0560**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
(dup)		11/30/20	Bladder	0.0932 U	0.400 U	**2.21 J+**	0.0760 U	0.580 U	**0.0580**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	**0.0590 J**
		02/05/21	Peristaltic	0.0932 U	0.400 U	1.20 U	0.0760 U	0.580 U	**0.0500**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	**0.0810 J**
		05/12/21	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0220 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	**0.0570 J**
MW127	8th Ave N ROW, E side	08/01/19	Peristaltic	0.138 U	0.823 U	1.59 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/17/19	Bladder	0.138 U	0.823 U	1.43 U	0.873 U	–	0.0896 U	0.133 UJ	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/17/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		04/23/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/14/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
(dup)		07/14/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/13/20	Bladder	0.0932 U	0.400 UJ	0.548 UJ	0.0760 UJ	0.580 U	**0.0453**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/11/21	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 UJ	0.0166 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	640	7,200	0.81	2.1	5.0	64	7.1	55	11	800	5	100	5.2	–	14
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	4.7E+05	1.5E+07	12	–	2.4	–	1.8	–	13	400	0.56	290	–	18,000	1.2
MW131	Property,	03/27/17	Peristaltic	0.138 U	0.823 U	**1.93 J**	0.873 U	–	**0.199 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**0.462 J**	0.0860 U
	SE quadrant	06/20/17	Peristaltic	0.690 U	4.12 U	5.25 U	4.36 U	–	0.448 U	0.665 U	0.400 U	0.930 U	0.785 U	0.505 U	0.795 U	0.140 U	0.640 U	0.705 U	0.430 U
		04/16/18	Peristaltic	0.138 U	0.823 U	**58.4**	0.873 U	–	**0.142 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/25/18	Peristaltic	0.138 U	0.823 U	**6.30 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.152 J**	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		12/12/18	Peristaltic	0.138 U	0.823 U	**8.19 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/29/19	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	**0.182 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**0.367 J**	0.0860 U
		03/11/19	Peristaltic	0.138 U	0.823 U	**52.6**	0.873 U	–	**0.152 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**0.386 J**	0.0860 U
	Decommissioned March, 2019																		
MW-142	8th Ave N ROW,	04/27/18	Peristaltic	0.138 U	0.823 U	**1.40 J**	0.873 U	–	**0.514**	0.113 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	E side	01/28/19	Peristaltic	0.138 U	0.823 U	6.98 U	0.873 U	–	**0.442 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	(dup)	01/28/19	Peristaltic	0.138 U	0.823 U	8.44 U	0.873 U	–	**0.410 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/24/19	Peristaltic	0.138 U	0.823 U	**2.52 J**	0.873 U	–	**0.361 J**	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		07/25/19	Bladder	0.138 U	0.823 U	2.50 U	0.873 U	–	**0.413 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.465 U	0.128 U	0.141 U	0.300 U
		10/16/19	Bladder	0.138 U	0.823 U	1.46 U	0.873 U	–	**0.380 J**	0.133 UJ	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/22/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	**0.438 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/24/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	**0.359 J**	0.118 U	0.136 U	0.129 U	0.605 UJ	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/30/20	Bladder	0.0932 U	0.400 U	0.548 UJ	0.0760 U	0.580 U	**0.451**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/24/20	Bladder	0.0932 U	0.400 U	**1.69 J+**	0.0760 U	0.580 U	**0.408**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
	(dup)	11/24/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.509**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/08/21	Peristaltic	0.0932 U	0.400 U	**6.10 J**	0.0760 U	0.580 U	**0.327**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/19/21	Peristaltic	0.0932 U	0.400 U	**3.80 J+**	0.0760 U	0.580 U	**0.320**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 UJ	0.0166 U
MW-144	8th Ave N ROW,	04/27/18	Peristaltic	0.138 U	0.823 U	**2.44 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	E side	01/28/19	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.716**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/23/19	Peristaltic	0.138 U	0.823 U	**2.38 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	**0.210 J**	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
	Decommissioned December 2019																		
MW-144R	8th Ave N ROW,	12/16/19	Bladder	0.138 U	0.823 U	3.99 U	0.873 U		0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.470 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	E side	01/21/20	Bladder	1.38 U	8.23 U	10.5 U	8.73 U		0.896 U	1.33 U	0.800 U	1.86 U	1.57 U	1.01 U	1.59 U	1.40 U	1.28 U	1.41 UJ	0.860 U
		04/02/20	Bladder	0.138 UJ	0.823 UJ	9.03 U	0.873 UJ		0.0896 UJ	0.133 UJ	0.0800 UJ	0.186 UJ	0.157 UJ	**0.283 J**	0.159 UJ	0.140 UJ	0.128 UJ	0.141 UJ	0.0860 UJ
		08/03/20	Bladder	0.0932 U	0.400 U	**28.4 J**	0.0760 U	0.580 U	**0.0510**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	**0.431 J**	0.0166 U
		11/23/20	Bladder	0.0932 U	0.400 U	**27.4 J+**	0.0760 U	0.580 U	**0.0440**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/02/21	Peristaltic	0.0932 U	0.400 U	**55.7**	0.0760 U	0.580 U	**0.0460**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	**0.405 J**	0.0166 U
		05/12/21	Peristaltic	0.0932 U	0.400 U	**25.7**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	**0.237**	**0.0610 J**
MW-146	Roy St ROW,	04/30/18	Bladder	0.138 U	0.823 U	**4.54 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**1.05 J**	0.0860 U
	S side	01/22/19	Peristaltic	0.138 U	0.823 U	**1.98 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**1.60 J**	0.0860 U
		04/24/19	Bladder	0.138 U	0.823 U	1.58 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	**0.719 J**	0.0860 U
		07/19/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	(dup)	07/19/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/14/19	Bladder	0.138 U	0.823 UJ	1.05 UJ	0.873 UJ	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/24/20	Bladder	13.8 U	82.3 U	105 UJ	87.3 U	–	8.96 U	13.3 U	8.00 U	18.6 U	15.7 U	10.1 U	15.9 U	14.0 U	12.8 U	14.1 U	8.60 U
	(dup)	01/24/20	Bladder	0.138 U	0.823 U	1.05 UJ	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/30/20	Bladder	12.0 U	47.8 U	1,130 UJ	67.1 U	–	9.41 U	11.8 U	13.6 U	12.9 U	60.5 U	9.62 UJ	12.8 U	11.7 U	14.0 U	19.2 U	11.1 U
		07/09/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0740**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/10/20	Bladder	4.66 U	20.0 UJ	27.4 UJ	3.80 UJ	29.0 U	**0.842 J**	2.10 U	1.58 U	12.0 U	7.40 U	–	2.16 U	1.15 U	0.900 U	2.16 U	0.830 U
	(split)	11/10/20	Bladder	500 U	5,000 U	25,000 U	–	–	170 U	500 U	500 U	2,500 U	2,500 U	–	500 U	500 U	500 U	500 U	500 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	640	7,200	0.81	2.1	5.0	64	7.1	55	11	800	5	100	5.2	–	14
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	4.7E+05	1.5E+07	12	–	2.4	–	1.8	–	13	400	0.56	290	–	18,000	1.2
MW-146		02/08/21	Peristaltic	0.0932 U	0.400 U	**3.21 J**	0.0760 U	0.580 U	**0.105**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
(continued)		05/04/21	Bladder	4.66 U	20.0 U	27.4 U	3.80 U	29.0 U	0.800 U	2.10 U	1.58 U	12.0 U	7.40 U	–	2.16 U	1.15 U	0.900 U	2.16 U	0.830 U
MW-149	Property,	04/10/18	Peristaltic	0.690 U	4.12 U	5.25 U	4.36 U	–	44.8 U	0.665 U	0.400 U	0.930 U	0.785 U	0.505 UJ	0.795 U	0.700 U	0.640 U	**28.8**	0.430 U
	NE quadrant	10/25/18	Peristaltic	0.138 U	0.823 U	**1.71 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.181 J**	0.159 U	0.140 U	0.128 U	**14.2 J**	**0.395 J**
		12/13/18	Peristaltic	0.138 U	0.823 U	525 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**10.3**	**0.776**
(dup)		12/13/18	Peristaltic	0.138 U	0.823 U	525 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**10.6**	**0.747**
		01/29/19	Peristaltic	13.8 U	82.3 U	105 U	87.3 U	–	8.96 U	13.3 U	8.00 U	18.6 U	15.7 U	10.1 U	15.9 U	14.0 U	12.8 U	14.1 U	8.60 U
		03/13/19	Peristaltic	0.138 U	0.823 U	**17.2 J**	0.873 U	–	**0.222 J**	0.133 U	0.0800 U	0.186 U	0.157 U	**1.38**	0.159 U	0.140 U	0.128 U	**14.1**	**0.270 J**
	Decommissioned March, 2019																		
MW-151	Property,	04/10/18	Peristaltic	0.138 UJ	0.823 UJ	**52.0 J-**	0.873 U	–	**0.253 J**	0.133 U	0.0800 U	0.186 U	0.157 U	**1.15 J-**	0.159 U	0.140 UJ	0.128 U	0.141 UJ	0.0860 UJ
	SW quadrant	10/25/18	Peristaltic	0.138 U	0.823 U	**107 J**	0.873 U	–	**0.167 J**	0.133 U	0.0800 U	0.186 U	0.157 U	**9.13**	0.159 U	0.140 U	0.128 U	0.141 UJ	**1.02**
		12/14/18	Peristaltic	0.138 U	0.823 U	**16.6 J**	0.873 U	–	**0.342 J**	0.133 U	0.0800 U	0.186 U	0.157 U	**4.43**	0.159 U	0.140 U	0.128 U	**2.63**	**0.285 J**
		01/31/19	Peristaltic	0.138 U	0.823 U	**14.0 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.344 J**	0.159 U	0.140 U	0.128 U	**6.11**	0.0860 U
		03/12/19	Peristaltic	0.138 U	0.823 U	**34.5**	0.873 U	–	**0.159 J**	0.133 U	0.0800 U	0.186 U	0.157 U	**1.55**	0.159 U	0.140 U	0.128 U	**10.4**	0.0860 U
	Decommissioned March, 2019																		
MW-156	8th Ave N ROW,	04/26/18	Peristaltic	0.138 U	0.823 U	3.25 U	0.873 U	–	**0.283 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	E side	01/24/19	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/24/19	Peristaltic	0.138 U	0.823 U	**2.00 J**	0.873 U	–	**0.339 J**	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
(dup)		04/24/19	Peristaltic	0.138 U	0.823 U	**2.50 J**	0.873 U	–	**0.330 J**	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		07/22/19	Bladder	0.138 U	0.823 U	**4.94 J**	0.873 U	–	**0.492 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/17/19	Bladder	1.38 U	8.23 U	12.9 U	8.73 U	–	0.896 U	1.33 UJ	0.800 U	1.86 U	1.57 U	1.01 U	1.59 U	1.40 U	1.28 U	1.41 U	0.860 U
		01/20/20	Bladder	1.38 U	8.23 U	10.5 U	8.73 U	–	**1.64 J**	1.33 U	0.800 U	1.86 U	1.57 U	1.01 U	1.59 U	1.40 U	1.28 U	1.41 U	0.860 U
		04/24/20	Bladder	6.00 U	23.9 U	565 U	33.6 U	–	4.71 U	5.90 U	6.80 U	6.45 U	30.3 UJ	4.81 U	6.40 U	5.85 U	7.00 U	9.60 U	5.55 U
		07/15/20	Bladder	4.66 U	20.0 U	27.4 U	3.80 U	29.0 U	**1.60 J**	2.10 U	1.58 U	12.0 U	7.40 U	–	2.16 U	1.15 U	0.900 U	2.16 U	0.830 U
		11/11/20	Bladder	0.0932 U	0.400 UJ	0.548 UJ	0.0760 U	0.580 U	**0.149**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/08/21	Peristaltic	0.932 U	4.00 U	5.48 U	0.760 U	5.80 U	**0.240 J**	0.420 U	0.315 U	2.39 U	1.48 U	–	0.432 U	0.229 U	0.180 U	0.432 U	0.166 U
		05/10/21	Bladder	4.66 U	20.0 U	27.4 U	3.80 U	29.0 U	0.800 U	2.10 U	1.58 U	12.0 U	7.40 U	–	2.16 U	1.15 U	0.900 U	2.16 UJ	0.830 U
MW-189	Valley St ROW,	10/14/19	Bladder	0.138 U	0.823 UJ	1.05 UJ	0.873 UJ	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	**0.362 J**	0.0860 U
	S side	01/23/20	Bladder	0.138 U	0.823 U	1.05 UJ	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/03/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
(dup)		04/03/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		08/04/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/17/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	**0.287**	0.0166 U
		02/03/21	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	**1.95 J**	0.0166 U
		05/14/21	Bladder	0.0932 U	0.400 U	1.09 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	**2.99**	0.0166 U
MW-302	Dexter Ave N	10/21/19	Bladder	0.138 U	0.823 U	**1.19 J**	0.873 UJ	–	0.0896 U	0.133 U	0.0800 UJ	0.186 U	0.157 U	**0.357 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	ROW	01/24/20	Bladder	0.138 U	0.823 U	1.21 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.718**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		05/07/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 UJ	0.136 U	0.129 U	0.605 UJ	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 UJ	0.111 U
		07/28/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 UJ	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		11/17/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0480**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/17/21	Bladder	0.0932 U	0.400 U	**1.01 J+**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-306	Dexter Ave N ROW,	10/15/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 UJ	0.141 U	0.0860 U
	E side	01/16/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	–	**2.4**	–	**1.8**	–	**13**	**400**	**0.56**	**290**	–	**18,000**	**1.2**
MW-306 (continued)		04/28/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 UJ	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/29/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/06/20	Bladder	0.0932 U	0.400 U	0.548 UJ	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 UJ	0.0166 U
		05/18/21	Bladder	0.0932 U	0.400 U	**1.25 J+**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	**0.236**	0.0229 U	0.0180 U	0.0432 UJ	**0.0980 J**
MW-308	Alley E of Seattle Roy Aloha Shops	10/11/19	Peristaltic	0.138 U	0.823 UJ	**1.27 J**	0.873 UJ	–	**12.5**	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/16/20	Peristaltic	0.138 U	0.823 U	**2.33 J**	0.873 U	–	**29.3**	0.133 U	0.0800 U	0.186 U	0.157 U	**0.713**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/08/20	Peristaltic	0.138 U	0.823 U	**1.42 J**	0.873 U	–	**21.2**	0.133 U	0.0800 U	0.186 U	0.157 U	**3.85**	0.159 U	0.140 U	0.128 U	0.141 U	**0.230 J**
		07/06/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**15.4**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/06/20	Peristaltic	0.0932 U	0.400 U	0.548 UJ	0.0760 U	0.580 U	**38.4**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 UJ	0.0166 U
		05/04/21	Peristaltic	0.0932 U	0.400 U	0.548 UJ	0.0760 UJ	0.580 U	**20.8**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-315	Mercer St ROW, N side	10/03/19	Bladder	0.138 U	0.823 U	3.36 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/16/20	Bladder	0.138 U	0.823 U	**1.06 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/24/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 UJ	**0.430 J**	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/24/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0430**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/02/20	Bladder	0.0932 U	0.400 U	**2.05 J**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/17/21	Bladder	0.0932 U	0.400 U	**1.27 J+**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 UJ	0.0166 U
MW-317	9th Ave N ROW, W side	10/09/19	Peristaltic	0.138 U	0.823 U	**1.66 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/16/20	Peristaltic	0.138 U	0.823 U	**1.55 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/27/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 UJ	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/30/20	Peristaltic	0.0932 U	0.400 U	0.548 UJ	0.0760 U	0.580 U	**0.0457**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/10/20	Peristaltic	0.0932 U	0.400 UJ	**1.56 J-**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/19/21	Peristaltic	0.0932 U	0.400 U	**2.01 J+**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 UJ	0.0166 U
MW-325	Mercer St ROW, N side	10/03/19	Bladder	0.138 U	0.823 U	1.57 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/17/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		04/21/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/23/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0190 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/02/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/08/21	Bladder	0.0932 U	0.400 U	**2.49 J**	0.0760 U	0.580 U	**0.0650**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/17/21	Bladder	0.0932 U	0.400 U	**1.41 J+**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 UJ	0.0166 U
MW-327	Lake Union Park, S end	10/02/19	Bladder	0.138 U	0.823 U	2.99 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/17/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		04/09/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		07/07/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 UJ	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/09/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0200 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/25/21	Peristaltic	0.0932 U	0.400 U	**1.40**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-330 (dup)	Valley St ROW, N side	05/14/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 UJ	0.605 U	**0.125 J**	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		05/14/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 UJ	0.605 U	**0.142 J**	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/16/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0500**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		12/01/20	Bladder	0.0932 U	0.400 U	0.741 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 UJ	0.239 U	0.148 U	–	0.0432 UJ	0.0229 U	0.0180 U	0.0432 U	0.0166 U
(dup)		12/01/20	Bladder	0.0932 U	0.400 U	**1.30 J-**	0.0760 U	0.580 U	**0.0200 J**	0.0420 U	0.0315 UJ	0.239 U	0.148 U	–	0.0432 UJ	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/25/21	Bladder	0.0932 U	0.400 U	3.78 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	–	**2.4**	–	**1.8**	–	**13**	**400**	**0.56**	**290**	–	**18,000**	**1.2**
MW-331	Alley E of Seattle	04/24/20	Peristaltic	0.120 U	0.478 U	11.3 U	0.671 U	–	**0.226 J**	0.118 U	0.136 U	0.129 U	0.605 UJ	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
	Roy Aloha Shops	07/06/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0610**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/06/20	Peristaltic	0.0932 U	0.400 U	0.548 UJ	0.0760 U	0.580 U	**0.0407**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 UJ	0.0166 U
		05/04/21	Peristaltic	0.0932 U	0.400 U	0.548 UJ	0.0760 UJ	0.580 U	**0.0240 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-333	900 Roy St,	04/29/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 UJ	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
	S end	07/24/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0200 J**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/05/20	Bladder	0.0932 U	0.400 U	**0.938 J**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/18/21	Peristaltic	0.0932 U	0.400 U	**26.3 J+**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 UJ	0.0166 U
MW-344	SDOT Mercer Parcels,	06/01/21	Bladder	0.0932 U	0.400 U	1.10 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
Intermediate B Water-Bearing Zone																			
FMW-141	Alley E of Seattle	07/26/19[a]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	Roy Aloha Shops	10/30/19	Peristaltic	0.138 U	0.823 U	105 U	0.873 U	–	**0.230 J**	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
(dup)		10/30/19	Peristaltic	0.138 U	0.823 U	105 U	0.873 U	–	**0.212 J**	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		11/11/19[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/14/20	Bladder	0.690 U	4.12 U	5.25 U	4.37 U	–	0.448 U	0.665 U	0.400 U	0.930 U	0.785 U	0.505 UJ	0.795 U	0.700 U	0.640 U	0.705 U	0.430 U
(split)		01/14/20[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/17/20[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		03/24/20[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/27/20[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/28/20	Bladder	0.600 U	2.39 U	56.5 U	3.36 U	–	0.471 U	0.590 U	0.680 U	0.645 U	3.03 U	0.481 UJ	0.640 U	0.585 U	0.700 U	0.960 U	0.555 U
		05/19/20[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/22/20	Bladder	1.86 U	8.00 U	11.0 U	1.52 U	11.6 U	0.320 U	0.840 U	0.630 U	4.78 U	2.96 U	–	0.864 U	0.458 U	0.360 U	0.864 U	0.332 U
		07/28/20[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		09/17/20[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/02/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0620**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		12/03/20[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/10/21[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/03/21	Peristaltic	0.0932 U	0.400 U	0.548 UJ	0.0760 UJ	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
HMW-1IB	SDOT Mercer Parcels,	03/25/19[a]	Peristaltic	1.0 U	–	–	–	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U
	NE quadrant	03/10/20[a]	Unknown	–	–	–	–	–	0.20 U	–	0.20 U	–	–	–	0.20 U	0.20 U	0.20 U	0.20 U	0.20 U
HMW-2IB	SDOT Mercer Parcels,	03/25/19[a]	Peristaltic	1.0 U	–	–	–	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U
	NE quadrant	03/12/20[a]	Unknown	–	–	–	–	–	0.20 U	–	0.20 U	–	–	–	0.20 U	0.20 U	0.20 U	0.20 U	0.20 U
HMW-4IA	SDOT Mercer Parcels,	03/25/19[a]	Peristaltic	1.0 U	–	–	–	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U
	SW quadrant	03/10/20[a]	Unknown	–	–	–	–	–	0.20 U	–	0.20 U	–	–	–	0.20 U	0.20 U	0.20 U	0.20 U	0.20 U
HMW-5IB	SDOT Mercer Parcels, SW quadrant	03/17/20[a]	Unknown	–	–	–	–	–	0.20 U	–	0.20 U	–	–	–	0.20 U	0.20 U	0.20 U	0.20 U	0.20 U
HMW-6IB	SDOT Mercer Parcels, SW quadrant	03/13/20[a]	Unknown	–	–	–	–	–	0.20 U	–	0.20 U	–	–	–	0.20 U	0.20 U	0.20 U	0.20 U	0.20 U
HMW-7IB	SDOT Mercer Parcels, SW quadrant	03/12/20[a]	Unknown	–	–	–	–	–	0.20 U	–	0.20 U	–	–	–	0.20 U	0.20 U	0.20 U	0.20 U	0.20 U
HMW-8IB	SDOT Mercer Parcels, SW quadrant	03/11/20[a]	Unknown	–	–	–	–	–	0.20 U	–	0.20 U	–	–	–	0.20 U	0.20 U	0.20 U	0.20 U	0.20 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	–	**2.4**	–	**1.8**	–	**13**	**400**	**0.56**	**290**	–	**18,000**	**1.2**
HMW-9IB	SDOT Mercer Parcels, SW quadrant	03/19/20[a]	Unknown	–	–	–	–	–	0.20 U	–	0.20 U	–	–	–	0.20 U	0.20 U	0.20 U	0.20 UJ	0.20 U
		01/26/21	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0760**	0.0420 U	0.0315 U	0.239 U	0.148 U		0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		06/02/21	Bladder	9.32 U	40.0 U	54.8 U	7.60 U	58.0 U	1.60 U	4.20 U	3.15 U	23.9 U	14.8 UJ	–	4.32 U	2.29 U	1.80 U	4.32 U	1.66 U
HMW-11IB	SDOT Mercer Parcels, SE quadrant	03/16/20[a]	Unknown	–	–	–	–	–	0.20 U	–	0.20 U	–	–	–	0.20 U	0.20 U	0.20 U	0.20 U	**0.26**
MW111	Alley E of Seattle Roy Aloha Shops	03/23/17	Peristaltic	0.138 U	0.823 U	3.09 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/14/17	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/06/18	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.201 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/23/19	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/22/19	Peristaltic	0.138 U	0.823 U	**1.17 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	**0.255 J**	0.0860 U
		07/15/19	Peristaltic	0.138 U	0.823 U	2.55 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**0.275 J**	0.0860 U
		10/14/19	Peristaltic	0.138 U	0.823 UJ	1.25 U	0.873 UJ	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/16/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/23/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/06/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0210 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/02/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0230 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/09/21	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0420**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/03/21	Bladder	0.0932 U	0.400 U	0.548 UJ	0.0760 UJ	0.580 U	**0.0430**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW112	Dexter Ave N ROW, W side	03/22/17	Bladder	0.138 U	0.823 U	2.80 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/16/17	Bladder	0.138 U	**8.50**	**9.22 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/12/18	Bladder	0.138 U	**2.35 J+**	6.34 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		12/21/18	Bladder	0.138 U	**1.06 J**	**1.50 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/22/19	Bladder	0.138 U	0.823 U	**2.37 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		07/16/19	Bladder	0.138 U	0.823 U	2.24 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/21/19	Bladder	0.138 U	0.823 UJ	**2.72 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/24/20	Bladder	0.138 U	0.823 U	2.33 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		05/07/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 UJ	0.136 U	0.129 U	0.605 UJ	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 UJ	0.111 U
		07/27/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/17/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0270 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/11/21	Bladder	0.0932 U	0.400 U	1.41 U	0.0760 U	0.580 U	**0.0200 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/14/21	Bladder	0.0932 U	0.400 U	1.08 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW126	Alley E of Seattle Roy Aloha Shops	03/28/17	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	**0.148 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	**0.826**
		06/15/17	Bladder	0.138 U	0.823 U	1.05 UJ	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/06/18	Peristaltic	0.138 U	0.823 U	2.06 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.155 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/22/19	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/29/19	Peristaltic	0.138 U	0.823 U	2.18 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		07/18/19	Peristaltic	0.138 U	0.823 U	1.96 UJ	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/15/19	Bladder	0.138 U	0.823 U	**1.30 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 UJ	0.141 U	0.0860 U
(dup)		10/15/19	Bladder	0.138 U	0.823 U	**1.34 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 UJ	0.141 U	0.0860 U
		01/14/20	Peristaltic	0.138 U	0.823 U	4.16 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/09/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	640	7,200	0.81	2.1	5.0	64	7.1	55	11	800	5	100	5.2	–	14
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	4.7E+05	1.5E+07	12	–	2.4	–	1.8	–	13	400	0.56	290	–	18,000	1.2
MW126		07/24/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
(continued)		11/09/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0210 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/10/21	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/04/21	Peristaltic	0.0932 U	0.400 U	0.548 UJ	0.0760 UJ	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
	(dup)	05/04/21	Peristaltic	0.0932 U	0.400 U	0.548 UJ	0.0760 UJ	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW130	Property,	03/29/17	Bladder	2.76 U	16.5 U	**23.7 J**	17.5 U	–	1.79 U	2.66 U	1.60 U	3.72 U	3.14 U	2.02 U	3.18 U	2.80 U	2.56 U	2.82 U	1.72 U
	NW quadrant	06/30/17	Bladder	1.38 U	8.23 U	10.5 U	8.73 U	–	0.896 U	1.33 U	0.800 U	1.86 U	1.57 U	1.01 U	1.59 U	1.40 U	1.28 U	1.41 U	0.860 U
	(dup)	06/30/17	Bladder	1.38 U	8.23 U	10.5 U	8.73 U	–	0.896 U	1.33 U	0.800 U	1.86 U	1.57 U	1.01 U	1.59 U	1.40 U	1.28 U	1.41 U	0.860 U
		05/21/18	Bladder	0.138 U	0.823 U	**3.48 J**	0.873 U	–	**0.403 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		12/17/18	Bladder	6.90 U	41.2 U	**65.0 J**	43.6 U	–	4.48 U	6.65 U	4.00 U	9.30 U	7.85 U	**5.74 J**	7.95 U	7.00 U	6.40 U	7.05 U	4.30 U
		01/31/19	Bladder	0.138 U	0.823 U	**9.13 J**	0.873 U	–	**0.377 J**	0.133 U	0.0800 U	0.186 U	0.157 U	**4.57**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	Decommissioned March, 2019																		
MW-132	Property,	09/25/17	Bladder	0.690 U	4.12 U	**5.91 J**	4.36 U	–	0.448 U	0.665 U	0.400 U	0.930 U	0.785 U	0.505 U	0.795 U	0.700 U	0.640 U	0.705 U	0.430 U
	SE quadrant	04/26/18	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	**0.422 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/25/18	Peristaltic	0.138 U	0.823 U	1.05 UJ	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		12/13/18	Peristaltic	0.138 U	0.823 U	5.25 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/31/19	Peristaltic	0.138 U	0.823 U	**7.79 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		03/11/19	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	Decommissioned March, 2019																		
MW-134	Property,	09/22/17	Bladder	0.690 U	4.12 U	5.64 U	4.36 U	–	0.448 U	0.665 U	0.400 U	0.930 U	0.785 U	0.505 U	0.795 U	0.700 U	0.640 U	0.705 U	0.430 U
	NE quadrant	04/16/18	Peristaltic	0.138 U	0.823 U	3.11 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.874**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/25/18	Bladder	0.138 U	0.823 U	1.05 UJ	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		12/12/18	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/28/19	Bladder	0.138 U	0.823 U	7.59 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		03/12/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	Decommissioned March, 2019																		
MW-135	Property,	09/25/17	Bladder	13.8 U	82.3 U	105 UJ	87.3 U	–	8.96 U	13.3 U	8.00 U	18.6 U	15.7 U	10.1 U	15.9 U	14.0 U	12.8 U	14.1 U	8.60 U
	NE quadrant	04/25/18	Peristaltic	0.138 U	0.823 U	**9.87 J**	0.873 U	–	**0.434 J**	0.133 U	0.0800 U	0.186 U	0.157 U	**0.591**	0.159 U	0.140 U	0.128 U	**0.553 J**	0.0860 U
		10/25/18	Peristaltic	3.45 U	20.6 U	26.2 UJ	21.8 U	–	2.24 U	3.32 U	2.00 U	4.65 U	3.92 U	2.52 U	3.98 U	3.50 U	3.20 U	3.52 UJ	2.15 U
		12/13/18	Peristaltic	6.90 U	41.2 U	2620 U	43.6 U	–	4.48 U	6.65 U	4.00 U	9.30 U	7.85 U	5.05 U	7.95 U	7.00 U	6.40 U	7.05 U	4.30 U
		01/31/19	Bladder	**0.195 J**	0.823 U	**27.6 J**	0.873 U	–	**0.695 J**	0.133 U	0.0800 U	0.186 U	0.157 U	**0.462 J**	0.159 U	0.140 U	0.128 U	**1.40 J**	0.0860 U
		03/13/19	Bladder	0.138 U	0.823 U	**30.5**	0.873 U	–	**0.496 J**	0.133 U	0.0800 U	0.186 U	0.157 U	**0.707**	0.159 U	0.140 U	0.128 U	**2.69**	0.0860 U
	Decommissioned March, 2019																		
MW-136	Property,	09/25/17	Bladder	0.138 U	0.823 U	**7.30 J**	0.873 U	–	**0.332 J**	0.133 U	0.0800 U	0.186 U	0.157 U	**0.685**	0.159 U	0.140 U	0.128 U	0.141 U	**0.198 J**
	SW quadrant	04/16/18	Submersible	**0.573**	0.823 U	**14.5 J**	0.873 U	–	**0.260 J**	0.133 U	0.0800 U	0.186 U	0.157 U	**0.378 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/29/18	Bladder	0.138 U	0.823 U	1.75 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		12/13/18	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		02/01/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		03/12/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	(dup)	03/12/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	Decommissioned March, 2019																		
MW-139	Property,	09/25/17	Bladder	0.138 U	0.823 U	**2.87 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**1.18**	0.159 U	0.140 U	0.128 U	0.141 U	**1.33**
	SE quadrant	04/25/18	Peristaltic	0.138 U	0.823 U	**4.71 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/25/18	Peristaltic	0.138 U	0.823 U	**1.08 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.156 J**	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		12/12/18	Peristaltic	0.138 U	0.823 U	**1.89 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	–	**2.4**	–	**1.8**	–	**13**	**400**	**0.56**	**290**	–	**18,000**	**1.2**
MW-139		01/28/19	Peristaltic	0.138 U	0.823 U	7.66 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
(continued)		03/11/19	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**0.385 J**	0.0860 U
	Decommissioned March, 2019																		
MW-143	8th Ave N ROW,	04/30/18	Peristaltic	0.138 U	0.823 U	**6.00 J**	0.873 U	–	**0.244 J**	0.133 U	0.0800 U	0.186 U	0.157 U	**1.45**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	E side	01/29/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	**0.141 J**	0.133 U	0.0800 U	0.186 U	0.157 U	**0.226 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/24/19	Peristaltic	0.138 U	0.823 U	**2.44 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	**0.308 J**	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		07/19/19	Bladder	0.138 U	0.823 U	**2.80 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/16/19	Bladder	0.138 U	0.823 U	1.18 U	0.873 U	–	**0.211 J**	0.133 UJ	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/22/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/24/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 UJ	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/29/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0401**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/24/20	Bladder	0.0932 U	0.400 U	**1.24 J+**	0.0760 U	0.580 U	**0.584**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/08/21	Peristaltic	4.66 U	20.0 U	27.4 U	3.80 U	29.0 U	0.800 U	2.10 U	1.58 U	12.0 U	7.40 U	–	2.16 U	1.15 U	0.900 U	2.16 U	0.830 U
		05/19/21	Bladder	4.66 U	20.0 U	27.4 U	3.80 U	29.0 U	0.800 U	2.10 U	1.58 U	12.0 U	7.40 UJ	–	2.16 U	1.15 U	0.900 U	2.16 UJ	0.830 U
MW-145	8th Ave N ROW,	04/27/18	Bladder	0.138 U	0.823 U	**6.71 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	E side	01/29/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/26/19	Bladder	0.138 U	0.823 U	3.01 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	**0.365 J**	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
	Decommissioned December 2019																		
MW-145R	8th Ave N ROW,	12/16/19	Bladder	0.138 U	0.823 U	1.35 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	E side	01/21/20	Bladder	0.138 U	0.823 U	1.41 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.299 J**	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		04/02/20	Bladder	0.138 U	0.823 U	**3.73 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	**0.398 J**	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		08/03/20	Bladder	0.0932 U	0.400 U	**0.808 J**	0.0760 U	0.580 U	**0.0190 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/23/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/05/21	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.159**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/12/21	Bladder	0.0932 U	0.400 U	**1.06 J+**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-147	Roy St ROW,	05/01/18	Bladder	0.138 U	0.823 U	3.16 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**2.01 J**	0.0860 U
	S side	01/22/19	Bladder	0.138 U	0.823 U	**1.51 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/23/19	Bladder	0.138 U	0.823 U	**1.91 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		07/18/19	Bladder	0.138 U	0.823 U	**2.11 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	(dup)	07/18/19	Bladder	0.138 U	0.823 U	**2.34 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/14/19	Bladder	0.138 U	0.823 UJ	1.05 UJ	0.873 UJ	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/24/20	Bladder	3.45 U	20.6 U	26.3 UJ	21.8 U	–	2.24 U	3.33 U	2.00 U	4.65 U	3.93 U	2.53 U	3.97 U	3.50 U	3.20 U	3.53 U	2.15 U
		04/29/20	Bladder	3.00 U	12.0 U	282 U	16.8 U	–	2.35 U	2.95 U	3.40 U	3.22 U	15.1 U	2.41 UJ	3.20 U	2.93 U	3.50 U	4.80 U	2.78 U
		07/09/20	Bladder	0.0932 U	0.400 U	**1.48**	0.0760 U	0.580 U	**0.0890**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/10/20	Bladder	9.32 U	40.0 UJ	54.8 UJ	7.60 UJ	58.0 U	1.60 U	4.20 U	3.15 U	23.9 U	14.8 U	–	4.32 U	2.29 U	1.80 U	4.32 U	1.66 U
	(split)	11/10/20	Bladder	500 U	5,000 U	25,000 U	–	–	170 U	500 U	500 U	2,500 U	2,500 U	–	500 U	500 U	500 U	500 U	500 U
		02/09/21	Bladder	4.66 U	20.0 U	27.4 U	3.80 U	29.0 U	0.800 U	2.10 U	1.58 U	12.0 U	7.40 U	–	2.16 U	1.15 U	0.900 U	2.16 U	0.830 U
		05/04/21	Bladder	9.32 U	40.0 U	54.8 U	7.60 U	58.0 U	1.60 U	4.20 U	3.15 U	23.9 U	14.8 U	–	4.32 U	2.29 U	1.80 U	4.32 U	1.66 U
MW-148	Roy St ROW,	05/01/18	Bladder	0.138 U	0.823 U	6.56 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**1.01**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
(dup)	S side	05/01/18	Bladder	0.138 U	0.823 U	5.73 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**1.14**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/23/19	Bladder	0.138 U	0.823 U	1.90 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/26/19	Bladder	0.138 U	0.823 U	1.70 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.198 J**	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		07/22/19	Bladder	0.138 U	0.823 U	**2.48 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/16/19	Bladder	0.138 U	0.823 U	1.05 UJ	0.873 U	–	0.0896 U	0.133 UJ	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	–	**2.4**	–	**1.8**	–	**13**	**400**	**0.56**	**290**	–	**18,000**	**1.2**
MW-148 (continued)		01/20/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/30/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 UJ	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/15/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/11/20	Bladder	0.0932 U	0.400 UJ	0.548 UJ	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-150	Property, NW quadrant	04/10/18	Peristaltic	0.138 U	0.823 U	**1.72 J**	0.873 U	–	22.4 U	0.133 U	0.0800 U	0.186 U	0.157 U	**1.02 J**	0.159 U	0.140 U	0.128 U	**4.08**	0.0860 U
		10/25/18	Peristaltic	0.138 U	0.823 U	**9.83 J**	0.873 U	–	**0.413 J**	0.133 U	0.0800 U	0.186 U	0.157 U	**1.76**	0.159 U	0.140 U	0.128 U	0.141 UJ	**0.591**
		12/12/18	Peristaltic	0.138 U	0.823 U	262 U	0.873 U	–	**0.429 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**3.42**	**0.132 J**
		01/29/19	Peristaltic	13.8 U	82.3 U	105 U	87.3 U	–	8.96 U	13.3 U	8.00 U	18.6 U	15.7 U	10.1 U	15.9 U	14.0 U	12.8 U	14.1 U	8.60 U
		03/13/19	Peristaltic	0.138 U	0.823 U	**7.76 J**	0.873 U	–	**0.165 J**	0.133 U	0.0800 U	0.186 U	0.157 U	**1.63**	0.159 U	0.140 U	0.128 U	**2.94**	**0.210 J**
	Decommissioned March, 2019																		
MW-152	Property, SW quadrant	04/10/18	Peristaltic	2.76 U	16.5 U	**22.5 J**	17.5 U	–	224 U	2.66 U	1.60 U	3.72 U	3.14 U	2.02 UJ	3.18 U	2.80 U	2.56 U	2.82 U	1.72 U
		10/26/18	Peristaltic	6.90 U	41.2 U	**65.4 J**	43.6 U	–	4.48 U	6.65 U	4.00 U	9.30 U	7.85 U	5.05 U	7.95 U	7.00 U	6.40 U	7.05 UJ	**4.46 J**
		12/14/18	Peristaltic	3.45 U	20.6 U	26.2 U	21.8 U	–	2.24 U	3.32 U	2.00 U	4.65 U	3.92 U	**13.7 J+**	3.98 U	3.50 U	3.20 U	3.52 U	2.15 U
		01/31/19	Peristaltic	**0.196 J**	0.823 U	**30.9**	0.873 U	–	**0.416 J**	0.133 U	0.0800 U	0.186 U	0.157 U	**16.4**	0.159 U	0.140 U	0.128 U	0.141 U	**0.137 J**
		03/12/19	Peristaltic	3.45 U	20.6 U	**51.5 J**	21.8 U	–	2.24 U	3.32 U	2.00 U	4.65 U	3.92 U	**11.3 J**	3.98 U	3.50 U	3.20 U	3.52 U	2.15 U
	Decommissioned March, 2019																		
MW-157	8th Ave N ROW, E side	04/26/18	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/24/19	Peristaltic	0.138 U	0.823 U	**1.31 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**0.505 J**	0.0860 U
		04/24/19	Peristaltic	0.138 U	0.823 U	3.28 U	0.873 U	–	**0.254 J**	0.133 U	0.0800 U	0.186 U	0.157 UJ	**0.137 J**	0.159 U	0.140 U	0.128 U	**0.752 J**	0.0860 U
		07/22/19	Bladder	0.138 U	0.823 U	**2.65 J**	0.873 U	–	**0.327 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/16/19	Bladder	0.138 U	0.823 U	1.05 UJ	0.873 U	–	0.0896 U	0.133 UJ	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/20/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	**0.308 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/24/20	Bladder	2.40 U	9.56 UJ	226 U	13.4 UJ	–	1.88 U	2.36 U	2.72 U	2.58 U	12.1 U	1.92 UJ	2.56 U	2.34 U	2.80 U	3.84 U	2.22 U
		07/15/20	Bladder	1.86 U	8.00 U	11.0 U	1.52 U	11.6 U	**0.480 J**	0.840 U	0.630 U	4.78 U	2.96 U	–	0.864 U	0.458 U	0.360 U	0.864 U	0.332 U
		11/23/20	Bladder	1.86 U	8.00 U	11.0 U	1.52 U	11.6 U	0.740 U	0.840 U	0.630 U	4.78 U	2.96 U	–	0.864 U	0.458 U	0.360 U	0.864 U	0.332 U
MW-190	Valley Street ROW, S side	10/14/19	Bladder	0.138 U	0.823 UJ	1.05 UJ	0.873 UJ	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/23/20	Bladder	0.138 U	0.823 U	**1.84 J**	0.873 U	–	**0.150 J**	0.133 U	0.0800 U	0.186 U	0.157 U	**0.625**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/02/20	Bladder	0.138 U	0.823 U	**2.03 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	**1.63**	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		08/04/20	Bladder	0.0932 U	0.400 U	**0.846 J**	0.0760 U	0.580 U	**0.0270 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/18/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/03/21	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/14/21	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-303	Dexter Ave N ROW, E side	10/21/19	Submersible	0.138 U	0.823 U	**2.03 J**	0.873 UJ	–	0.0896 U	0.133 U	0.0800 UJ	0.186 U	0.157 U	**0.224 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/24/20	Bladder	0.138 U	0.823 U	2.64 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.941**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		05/07/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 UJ	0.136 U	0.129 U	0.605 UJ	**0.385 J**	0.128 U	0.117 U	0.140 U	0.192 UJ	0.111 U
		07/27/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/17/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/18/21	Bladder	0.0932 U	0.400 U	**1.02 J+**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 UJ	0.0166 U
MW-307	Roy St ROW, S side	10/11/19	Bladder	0.138 U	0.823 UJ	**1.17 J**	0.873 UJ	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/15/20	Bladder	0.138 U	0.823 U	**1.22 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**6.72**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/28/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	**0.172 J**	0.118 U	0.136 U	0.129 U	0.605 U	**6.95 J**	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/29/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0211 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	–	**2.4**	–	**1.8**	–	**13**	**400**	**0.56**	**290**	–	**18,000**	**1.2**
MW-307		11/06/20	Bladder	0.0932 U	0.400 U	**0.643 J**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
(continued)		05/18/21	Bladder	0.0932 U	0.400 U	**1.26 J+**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 UJ	0.0166 U
MW-309	Alley E of Seattle	10/14/19	Peristaltic	0.138 U	0.823 UJ	1.05 UJ	0.873 UJ	–	**0.295 J**	0.133 U	0.0800 U	0.186 U	0.157 UJ	**5.84**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	Roy Aloha Shops	01/16/20	Peristaltic	0.138 U	0.823 U	**1.14 J**	0.873 U	–	**0.585**	0.133 U	0.0800 U	0.186 U	0.157 U	**0.950**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/08/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	**1.92**	0.133 U	0.0800 U	0.186 U	0.157 U	**0.446 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		07/06/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.524**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/06/20	Peristaltic	0.0932 U	0.400 U	**0.582 J-**	0.0760 U	0.580 U	**0.473**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 UJ	0.0166 U
		05/04/21	Peristaltic	0.0932 U	0.400 U	0.548 UJ	0.0760 UJ	0.580 U	**0.252**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-311	Alley E of Seattle	10/10/19	Peristaltic	0.138 U	0.823 U	**3.51 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.343 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	Roy Aloha Shops	01/14/20	Peristaltic	0.138 U	0.823 U	2.13 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**2.05**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/23/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	**1.15**	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/16/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0650**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/04/20	Bladder	0.0932 U	0.400 U	0.548 UJ	0.0760 U	0.580 U	**0.0287 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/03/21	Peristaltic	0.0932 U	0.400 U	0.548 UJ	0.0760 UJ	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-314	Alley E of Seattle	10/10/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	Roy Aloha Shops	01/15/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
(dup)		01/15/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/22/20	Bladder	1.20 U	4.78 U	113 U	6.71 U	–	0.941 U	1.18 U	1.36 U	1.29 U	6.05 U	0.962 U	1.28 U	1.17 U	1.40 U	1.92 U	1.11 U
		07/16/20	Bladder	9.32 U	40.0 U	54.8 U	7.60 U	58.0 U	1.60 U	4.20 U	3.15 U	23.9 U	14.8 U	–	4.32 U	2.29 U	1.80 U	4.32 U	1.66 U
		11/04/20	Bladder	9.32 U	40.0 U	**364 J-**	7.60 U	58.0 U	1.60 U	4.20 U	3.15 U	23.9 U	14.8 U	–	4.32 U	2.29 U	1.80 U	4.32 U	1.66 U
		05/03/21	Bladder	4.66 U	20.0 U	27.4 U	3.80 U	29.0 U	0.800 U	2.10 U	1.58 U	12.0 U	7.40 U	–	2.16 U	1.15 U	0.900 U	2.16 U	0.830 U
MW-316	Mercer St ROW,	10/02/19	Bladder	0.138 U	0.823 U	2.73 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.485 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	N side	01/16/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.814**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/21/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	**0.642**	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/24/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0250 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/02/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0190 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/17/21	Bladder	0.0932 U	0.400 U	**1.42 J+**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 UJ	0.0166 U
MW-318	9th Ave N ROW,	10/08/19	Bladder	0.138 U	0.823 U	1.15 U	0.873 U	–	**5.75**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	W side	01/16/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	**25.4**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/27/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	**22.6**	0.118 U	0.136 U	0.129 U	0.605 UJ	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/30/20	Bladder	0.0932 U	0.400 U	0.548 UJ	0.0760 U	0.580 U	**5.79**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/12/20	Bladder	0.0932 U	0.400 UJ	0.548 UJ	0.0760 U	0.580 U	**4.20**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/19/21	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**3.97**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 UJ	0.0166 U
MW-322	9th Ave N ROW,	10/07/19	Peristaltic	0.138 U	0.823 U	3.40 U	0.873 U	–	**7.12**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	W side	01/21/20	Peristaltic	0.138 U	0.823 U	**1.19 J**	0.873 U	–	**7.41**	0.133 U	0.0800 U	0.186 U	0.157 U	**0.295 J**	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		04/29/20	Bladder	12.0 U	47.8 U	1,130 U	67.1 U	–	**15.5 J**	11.8 U	13.6 U	12.9 U	60.5 U	9.62 UJ	12.8 U	11.7 U	14.0 U	19.2 U	11.1 U
		07/07/20	Bladder	0.932 U	4.00 U	5.48 U	0.760 U	5.80 U	**28.8**	0.420 U	0.315 U	2.39 U	1.48 U	–	0.432 U	0.229 U	0.180 U	0.432 U	**0.600 J**
		11/24/20	Bladder	0.932 U	4.00 U	5.48 U	0.760 U	5.80 U	**23.9**	0.420 U	0.315 U	2.39 U	1.48 U	–	0.432 U	0.229 U	0.180 U	0.432 U	0.166 U
		05/19/21	Peristaltic	0.932 U	4.00 U	5.48 U	0.760 U	5.80 U	**22.4**	0.420 U	0.315 U	2.39 U	1.48 UJ	–	0.432 U	0.229 U	0.180 U	0.432 UJ	0.166 U
MW-334	900 Roy St,	04/24/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 UJ	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
	S end	07/07/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 UJ	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	–	**2.4**	–	**1.8**	–	**13**	**400**	**0.56**	**290**	–	**18,000**	**1.2**
MW-334		11/05/20	Bladder	0.0932 U	0.400 U	**0.777 J**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
(continued)		05/13/21	Peristaltic	0.0932 U	0.400 U	**1.61 J+**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-335	Mercer St ROW, N side	05/01/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	**0.113 J**	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/08/20	Bladder	0.932 U	4.00 U	5.48 U	0.760 U	5.80 U	0.160 U	0.420 U	0.315 U	2.39 U	1.48 U	–	0.432 U	0.229 U	0.180 U	0.432 U	0.166 U
		11/02/20	Bladder	0.932 U	4.00 U	5.48 U	0.760 U	5.80 U	**0.380 J**	0.420 U	0.315 U	2.39 U	1.48 U	–	0.432 U	0.229 U	0.180 U	0.432 U	0.166 U
		02/10/21	Bladder	0.932 U	4.00 U	5.48 U	0.760 U	5.80 U	**0.790**	0.420 U	**1.76**	2.39 U	1.48 U	–	0.432 U	0.229 U	0.180 U	0.432 U	0.166 U
		05/26/21	Peristaltic	0.932 U	4.00 U	5.48 U	0.760 U	5.80 U	**0.930**	0.420 U	0.315 U	2.39 U	1.48 U	–	0.432 U	0.229 U	0.180 U	0.432 U	0.166 U
MW-338	Lake Union Park, N end	05/07/20	Peristaltic	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 UJ	0.136 U	0.129 U	0.605 UJ	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 UJ	0.111 U
		07/23/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/10/20	Peristaltic	0.0932 U	0.400 UJ	**1.31 J-**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/04/21	Peristaltic	0.0932 U	0.400 U	0.548 UJ	0.0760 UJ	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-340	Lake Union Park, S end	05/12/20	Peristaltic	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/17/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/09/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	**0.0450 J**
		05/13/21	Peristaltic	0.0932 U	0.400 U	**1.13 J+**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	**0.162**
MW-345	SDOT Mercer Parcels,	06/01/21	Bladder	0.0932 U	0.400 U	1.52 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-346	SDOT Mercer Parcels,	06/02/21	Bladder	0.0932 U	0.400 U	**2.30**	0.0760 U	0.580 U	**0.0290 J**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
(dup)	NW quadrant	06/02/21	Bladder	0.0932 U	0.400 U	**2.34**	0.0760 U	0.580 U	**0.0290 J**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-347	SDOT Mercer Parcels,	06/01/21	Bladder	0.0932 U	0.400 U	3.27 U	0.0760 U	0.580 U	**0.0300 J**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	**0.316**
MW-348	SDOT Mercer Parcels,	06/01/21	Bladder	0.0932 U	0.400 U	1.69 U	0.0760 U	0.580 U	**0.0190 J**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-349	SDOT Mercer Parcels,	06/01/21	Bladder	0.0932 U	0.400 U	**12.9 J+**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-350	SDOT Mercer Parcels,	06/01/21	Bladder	**1.13**	0.400 U	0.548 U	0.0760 U	0.580 U	**1.16**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
W-MW-01	8th Ave N ROW, W side	03/30/17	Peristaltic	0.138 U	0.823 U	1.56 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/19/17	Bladder	0.138 U	0.823 UJ	1.05 U	0.873 U	–	**0.158 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/13/18	Bladder	0.138 U	0.823 U	**1.20 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.184 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/29/18	Bladder	0.138 U	0.823 U	**1.39 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		12/13/18	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/25/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		03/11/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/25/19	Bladder	0.138 U	0.823 U	2.03 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		07/23/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/15/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 UJ	0.141 U	0.0860 U
		01/27/20	Bladder	0.138 U	0.823 U	**1.65 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/03/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		07/31/20	Bladder	0.0932 U	0.400 U	0.548 UJ	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/24/20	Bladder	0.0932 U	0.400 U	**2.84 J+**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/03/21	Bladder	0.0932 U	0.400 U	**4.83**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/17/21	Bladder	0.0932 U	0.400 U	**13.0 J+**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
W-MW-02	8th Ave N ROW, W side	03/27/17	Peristaltic	0.138 U	0.823 U	**19.3 J**	0.873 U	–	**0.270 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**0.204 J**	0.0860 U
		06/19/17	Bladder	0.138 U	**0.929 J**	**8.12 J**	0.873 U	–	**0.307 J**	0.133 U	0.0800 U	0.186 U	0.157 U	**0.386 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	–	**2.4**	–	**1.8**	–	**13**	**400**	**0.56**	**290**	–	**18,000**	**1.2**
W-MW-02		06/12/18	Bladder	0.138 U	0.823 U	**7.44 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.142 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
(continued)		10/26/18	Peristaltic	0.138 U	0.823 U	**1.42 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.214 J**	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
(dup)		10/26/18	Peristaltic	0.138 U	0.823 U	**3.87 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		12/12/18	Peristaltic	0.138 U	0.823 U	**2.12 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/25/19	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	**0.133 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		03/11/19	Peristaltic	0.138 U	0.823 U	**3.26 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/23/19	Peristaltic	0.138 U	0.823 U	**2.25 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	**0.160 J**	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		07/23/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/18/19	Bladder	0.138 U	0.823 U	**2.54 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	**0.262 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/28/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.195 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/01/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 UJ	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		07/31/20	Bladder	0.0932 U	0.400 U	**6.40 J**	0.0760 U	0.580 U	**0.0502**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
Deep Water-Bearing Zone																			
FMW-129	SDOT Mercer Parcels,	04/10/17	Peristaltic	0.690 U	4.12 U	5.25 U	4.36 U	–	0.448 U	0.665 U	0.400 U	0.930 U	0.785 U	0.505 U	0.795 U	0.700 U	0.640 U	0.705 U	0.430 U
	NE quadrant	06/23/17	Bladder	0.138 U	0.823 U	**1.15 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 UJ	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		05/01/19	Peristaltic	0.138 U	0.823 U	4.93 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		07/16/19	Bladder	0.138 U	0.823 U	2.75 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/21/19	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 UJ	–	0.0896 U	0.133 U	0.0800 UJ	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		11/12/19[u]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/14/20	Bladder	1.38 U	8.23 U	10.5 U	8.73 U	–	0.896 U	1.33 U	0.800 U	1.86 U	1.57 U	1.01 U	1.59 U	1.40 U	1.28 U	1.41 U	0.860 U
(split)		01/14/20[u]	Bladder	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/18/20[p]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		03/25/20[u]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/27/20[u]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/06/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		05/19/20[u]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/10/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		07/28/20[u]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		09/17/20[u]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/10/20	Bladder	0.0932 U	0.400 UJ	0.548 UJ	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		12/03/20[p]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/10/21	Peristaltic	0.0932 U	0.400 U	**1.56**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
(split)		02/10/21[u]	Peristaltic	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/26/21	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0910**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
(dup)		05/26/21	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.127**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
FMW-131	Block 37,	03/24/17	Peristaltic	0.138 U	0.823 U	**2.31 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	SE quadrant	06/23/17	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 UJ	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		12/18/17[b]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/22/19	Peristaltic	0.138 U	0.823 U	**1.80 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		10/21/19	Peristaltic	0.138 U	0.823 UJ	**2.58 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/22/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/29/20	Peristaltic	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 UJ	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/30/20	Bladder	0.0932 U	0.400 U	0.548 UJ	0.0760 U	0.580 U	**0.0459**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		08/26/20[u]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	–	**2.4**	–	**1.8**	–	**13**	**400**	**0.56**	**290**	–	**18,000**	**1.2**
FMW-131 (continued)		11/19/20	Bladder	0.0932 U	0.400 U	**2.73 J+**	0.0760 U	0.580 U	**0.0850**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		12/04/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/11/21[p]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/12/21	Peristaltic	0.0932 U	0.400 U	2.25 U	0.0760 U	0.580 U	**0.0900**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/13/21	Peristaltic	0.0932 U	0.400 U	**1.11 J+**	0.0760 U	0.580 U	**0.0650**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
FMW-137	Alley E of Block 38 West	11/20/18[p]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		12/28/18[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/06/19[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/08/19[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		10/14/19[p]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/06/19	Peristaltic	0.138 U	0.823 U	**1.32 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.990**	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		11/11/19[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/22/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		05/06/20	Bladder	0.120 U	0.478 U	11.3 UJ	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/31/20	Bladder	0.0932 U	0.400 U	0.548 UJ	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/24/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/12/21	Bladder	0.0932 U	0.400 U	1.71 U	0.0760 U	0.580 U	**0.0330 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		06/02/21	Peristaltic	0.0932 U	0.400 U	**0.645 J**	0.0760 U	0.580 U	**0.0240 J**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
FMW-138	Alley E of Block 38 West	11/20/18[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		12/28/18[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/6/19[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/8/19[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		10/14/19[p]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/11/19[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
FMW-3D	Terry Ave N ROW, E side	03/24/17	Peristaltic	0.138 U	0.823 U	**1.89 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/23/17	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 UJ	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
FMW-140	900 Roy St, S end	07/17/19[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		10/31/19	Peristaltic	0.138 U	0.823 U	**5.97 J**	0.873 UJ	–	**18.5**	0.133 U	0.0800 U	0.186 U	0.157 U	**3.49**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		11/12/19[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/14/20[p]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/22/20	Peristaltic	0.138 U	0.823 U	**9.51 J**	0.873 U	–	**39.6**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		02/18/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		03/25/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/27/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/28/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	**43.3**	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		05/19/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/07/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 UJ	0.580 U	**37.6**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		07/29/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		09/17/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/13/20	Bladder	0.0932 U	0.400 UJ	**0.607 J**	0.0760 UJ	0.580 U	**44.1**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		12/04/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/10/21[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/18/21	Peristaltic	0.0932 U	0.400 U	**1.35 J+**	0.0760 U	0.580 U	**41.0**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 UJ	0.0166 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	**–**	**2.4**	**–**	**1.8**	**–**	**13**	**400**	**0.56**	**290**	**–**	**18,000**	**1.2**
GEI-2	Block 37, NW quadrant	03/24/17	Peristaltic	0.138 U	0.823 U	**1.74 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/23/17	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 UJ	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		12/29/18[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/22/19	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	**1.05**	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		07/16/19	Peristaltic	0.138 U	0.823 U	1.77 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/21/19	Peristaltic	0.138 U	0.823 UJ	**1.37 J**	0.873 U	–	**3.80**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		11/11/19[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/14/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/22/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		02/17/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		03/25/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/27/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/29/20	Peristaltic	0.120 U	0.478 U	11.3 U	0.671 U	–	**2.22**	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 UJ	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		05/19/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		06/29/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/29/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/30/20	Bladder	0.0932 U	0.400 U	0.548 UJ	0.0760 U	0.580 U	**1.76**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		08/26/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		09/17/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/19/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**2.97**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		12/04/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/11/21[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/12/21	Peristaltic	0.0932 U	0.400 U	2.95 U	0.0760 U	0.580 U	**2.79**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/13/21	Peristaltic	0.0932 U	0.400 U	**1.85 J+**	0.0760 U	0.580 U	**2.19**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
HMW-1D	SDOT Mercer Parcels, NE quadrant	03/25/19[a]	Peristaltic	1.0 U	–	–	–	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U
		03/09/20[a]	Unknown	–	–	–	–	–	20 U	–	20 U	–	–		20 U	20 U	20 U	20 U	20 U
HMW-2D	SDOT Mercer Parcels, NE quadrant	03/25/19[a]	Peristaltic	1.0 U	–	–	–	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U
		03/12/20[a]	Unknown	–	–	–	–	–	0.20 U	–	0.20 U	–	–		0.20 U	0.20 U	0.20 U	0.20 U	0.20 U
HMW-3D	SDOT Mercer Parcels, NW quadrant	03/25/19[a]	Peristaltic	1.0 U	–	–	–	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U
		03/13/20[a]	Unknown	–	–	–	–	–	0.20 U	–	0.20 U	–	–		0.20 U	0.20 U	0.20 U	0.20 U	0.20 U
HMW-6D	SDOT Mercer Parcels, SW quadrant	03/16/20[a]	Unknown	–	–	–	–	–	**0.42**	–	0.20 U	–	–	–	0.20 U	0.20 U	0.20 U	0.20 U	**0.42**
HMW-9D	SDOT Mercer Parcels, SW quadrant	03/17/20[a]	Unknown	–	–	–	–	–	**0.21**	–	0.20 U	–	–	–	0.20 U	0.20 U	0.20 U	0.20 U	0.20 U
HMW-10D	SDOT Mercer Parcels, SE quadrant	03/16/20[a]	Unknown	–	–	–	–	–	0.20 U	–	0.20 U	–	–	–	0.20 U	0.20 U	0.20 U	0.20 U	**0.34**
MW102	Valley Street ROW, S side	03/29/17	Bladder	0.138 U	0.823 U	**1.36 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.161 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/15/17	Bladder	0.138 U	0.823 U	1.05 UJ	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/25/18	Bladder	0.138 U	0.823 U	**3.43 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/24/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		05/01/19	Bladder	0.138 U	0.823 U	1.75 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	**0.158 J**	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		07/18/19	Bladder	0.138 U	0.823 U	**2.74 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	–	**2.4**	–	**1.8**	–	**13**	**400**	**0.56**	**290**	–	**18,000**	**1.2**
MW102		11/14/19	Bladder	0.138 U	0.823 U	**1.19 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
(continued)		01/23/20	Bladder	0.138 U	0.823 U	1.05 UJ	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
(dup)		01/23/20	Bladder	0.138 U	0.823 U	1.05 UJ	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/02/20	Bladder	0.138 U	0.823 U	1.05 UJ	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		08/04/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
(dup)		08/04/20	Bladder	0.0932 U	0.400 U	**1.03 J**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/18/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/03/21	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/14/21	Bladder	0.0932 U	0.400 U	1.19 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW103	Alley E of Seattle	03/23/17	Peristaltic	0.138 U	0.823 U	2.87 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**0.301 J**	0.0860 U
	Roy Aloha Shops	06/14/17	Bladder	0.138 U	0.823 U	**1.76 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/06/18	Peristaltic	0.138 U	0.823 U	1.25 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.132 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/23/19	Peristaltic	0.138 U	0.823 U	**23.0 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/22/19	Peristaltic	0.138 U	0.823 U	**1.66 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		07/15/19	Peristaltic	0.138 U	0.823 U	2.13 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/14/19	Peristaltic	0.138 U	0.823 UJ	1.05 UJ	0.873 UJ	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/16/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/23/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
(dup)		04/23/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/06/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0210 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/02/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0270 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/10/21	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0200 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/03/21	Bladder	0.0932 U	0.400 U	0.548 UJ	0.0760 UJ	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW104	8th Ave N ROW,	03/30/17	Peristaltic	0.138 U	0.823 U	1.84 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	W side	06/30/17	Bladder	0.138 U	0.823 U	**1.45 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/09/18	Peristaltic	0.138 U	0.823 U	**3.33 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.147 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/26/18	Bladder	0.138 U	0.823 U	2.91 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.675**	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		12/13/18	Bladder	0.138 U	0.823 U	**2.23 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.243 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		02/01/19	Bladder	0.138 U	0.823 U	**72.7**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.179 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		03/13/19	Bladder	0.138 U	0.823 U	**9.26 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.232 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/23/19	Bladder	0.138 U	0.823 U	**23.4 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		07/22/19	Bladder	0.138 U	0.823 U	**4.88 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/18/19	Bladder	0.138 U	0.823 U	**2.88 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/29/20	Bladder	0.138 U	0.823 U	**11.3 J**	0.873 U	–	**0.167 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/01/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 UJ	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		07/31/20	Bladder	0.0932 U	0.400 U	0.548 UJ	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
(dup)		07/31/20	Bladder	0.0932 U	0.400 U	0.548 UJ	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/17/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	**0.551**	0.0166 U
		02/10/21	Bladder	0.0932 U	0.400 U	**1.91**	0.0760 U	0.580 U	**0.0450**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	**1.20**	0.0166 U
MW105	Roy Street ROW,	04/21/17	Bladder	0.138 U	0.823 U	**1.44 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.192 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	S side	06/14/17	Bladder	0.138 U	0.823 U	**1.18 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/11/18	Bladder	0.138 U	0.823 UJ	**4.51 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/23/19	Bladder	0.138 U	0.823 U	1.73 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/23/19	Bladder	0.138 U	0.823 U	**1.22 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	–	**2.4**	–	**1.8**	–	**13**	**400**	**0.56**	**290**	–	**18,000**	**1.2**
MW105		07/17/19	Bladder	0.138 U	0.823 U	**2.18 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
(continued)		10/22/19	Bladder	0.138 U	0.823 U	**1.40 J**	0.873 UJ	–	0.0896 U	0.133 U	0.0800 UJ	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
(dup)		10/22/19	Bladder	0.138 U	0.823 U	**1.47 J**	0.873 U	–	0.0896 U	0.133 UJ	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/20/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		05/12/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/27/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/17/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/11/21	Bladder	0.0932 U	0.400 U	1.89 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		06/07/21	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.161**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW106	SDOT Mercer Parcels, NW quadrant	04/14/17	Bladder	0.138 U	0.823 U	**1.53 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.641**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/30/17	Bladder	0.138 U	0.823 U	**1.65 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		05/04/18	Bladder	0.138 U	0.823 U	**6.52 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	–	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/26/19	Bladder	0.138 U	0.823 U	1.65 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	**0.142 J**	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		07/19/19	Bladder	0.138 U	0.823 U	**2.16 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/18/19	Bladder	0.138 U	0.823 U	**2.01 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/14/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		05/06/20	Bladder	0.120 U	0.478 U	11.3 UJ	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
(dup)		05/06/20	Bladder	0.120 U	0.478 U	11.3 UJ	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/10/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/10/20	Bladder	0.0932 U	0.400 UJ	0.548 UJ	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
(dup)		11/10/20	Bladder	0.0932 U	0.400 UJ	0.731 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/12/21	Bladder	0.0932 U	0.400 U	1.34 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
(dup)		02/12/21	Bladder	0.0932 U	0.400 U	1.63 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/13/21	Bladder	0.0932 U	0.400 U	**1.47 J+**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW113	9th Ave N ROW, W side	03/22/17	Peristaltic	0.138 U	0.823 U	3.28 U	0.873 U	–	**2.60**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/16/17	Bladder	0.138 U	0.823 U	**1.90 J**	0.873 U	–	**0.468 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/11/18	Peristaltic	0.138 U	0.823 UJ	1.05 U	0.873 U	–	**0.880**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/30/19	Peristaltic	0.690 U	4.12 U	5.25 U	4.36 U	–	**1.02 J**	0.665 U	0.400 U	0.930 U	0.785 U	0.505 U	0.795 U	0.700 U	0.640 U	0.705 U	0.430 U
		02/07/19	Peristaltic	0.138 U	0.823 U	**2.79 J**	0.873 U	–	**0.811**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		07/17/19	Peristaltic	0.138 U	0.823 U	**2.54 J**	0.873 U	–	**0.172 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	**0.226 J**
		10/22/19	Peristaltic	0.138 U	0.823 U	**1.45 J**	0.873 UJ	–	0.0896 U	0.133 U	0.0800 UJ	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	**0.239 J**
		11/11/19[p]	Peristaltic	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/14/20	Bladder	1.38 U	8.23 U	10.5 U	8.73 U	–	0.896 U	1.33 U	0.800 U	1.86 U	1.57 U	1.01 U	1.59 U	1.40 U	1.28 U	1.41 U	0.860 U
(split)		01/14/20[v]	Peristaltic	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/18/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		03/24/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/27/20	Peristaltic	12.0 U	47.8 U	1,130 U	67.1 U	–	9.41 U	11.8 U	13.6 U	12.9 U	60.5 UJ	9.62 U	12.8 U	11.7 U	14.0 U	19.2 U	11.1 U
(split)		04/27/20[v]	Peristaltic	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/19/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/28/20	Bladder	12.0 U	47.8 U	1,130 U	67.1 U	–	9.41 U	11.8 U	13.6 U	12.9 U	60.5 U	9.62 UJ	12.8 U	11.7 U	14.0 U	19.2 U	11.1 U
(split)		07/28/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		09/17/20[p]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/24/20	Bladder	9.32 U	40.0 U	54.8 U	7.60 U	58.0 U	1.60 U	4.20 U	3.15 U	23.9 U	14.8 U	–	4.32 U	2.29 U	1.80 U	4.32 U	1.66 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	**–**	**2.4**	**–**	**1.8**	**–**	**13**	**400**	**0.56**	**290**	**–**	**18,000**	**1.2**
MW113		12/03/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(continued)		02/10/21	Peristaltic	0.0932 U	0.400 U	**1.65 J+**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
(split)		02/10/21[o]	Peristaltic	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/25/21	Peristaltic	0.0932 U	0.400 U	**2.19**	0.0760 U	0.580 U	**0.331**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW122	Alley E of Seattle Roy Aloha Shops	03/28/17	Peristaltic	0.138 U	0.823 U	**1.11 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/14/17	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/06/18	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/14/19	Peristaltic	0.138 U	0.823 UJ	1.05 UJ	0.873 UJ	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/17/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		04/07/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		07/24/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/06/20	Peristaltic	0.0932 U	0.400 U	**0.854 J**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/03/21	Peristaltic	0.0932 U	0.400 U	0.548 UJ	0.0760 UJ	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW123	Westlake Ave N ROW, W side	04/01/17	Peristaltic	0.138 U	0.823 U	2.83 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/24/17	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/14/18	Peristaltic	0.138 U	0.823 U	2.82 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/18/19	Peristaltic	0.138 U	0.823 U	**3.19 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/22/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		05/05/20	Peristaltic	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/30/20	Peristaltic	0.0932 U	0.400 U	0.548 UJ	0.0760 U	0.580 U	**0.0388 J**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/12/20	Peristaltic	0.0932 U	0.400 UJ	**0.640 J**	0.0760 UJ	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/26/21	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW124	Valley Street ROW, S side	03/29/17	Bladder	0.138 U	0.823 U	**1.35 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	**1.37**
(dup)		03/29/17	Bladder	0.138 U	0.823 U	**1.21 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	**1.30**
		06/15/17	Bladder	0.138 U	0.823 U	1.05 UJ	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	**0.614**
		04/13/18	Bladder	0.138 U	0.823 U	**2.58 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	**0.224 J**
		10/11/19	Bladder	0.138 U	0.823 UJ	**9.24 J**	0.873 UJ	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	**1.06**
		01/30/20	Bladder	0.138 U	0.823 U	1.53 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	**0.510**
		04/03/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		08/03/20	Bladder	0.0932 U	0.400 U	0.548 UJ	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/18/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		06/08/21	Bladder	0.0932 U	0.400 U	**1.76**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	**0.126**
MW128	Westlake Ave N ROW, E side	03/29/17	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		06/21/17	Bladder	0.138 U	0.823 U	**1.07 J**	0.873 U	–	**3.84**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/09/18	Peristaltic	0.138 U	0.823 U	1.05 UJ	0.873 U	–	**28.3**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		12/30/18[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/18/19	Peristaltic	0.138 U	0.823 U	**2.24 J**	0.873 U	–	**12.2**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/11/19	Peristaltic	0.138 U	0.823 UJ	1.05 UJ	0.873 UJ	–	**0.984**	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
(dup)		10/11/19	Peristaltic	0.138 U	0.823 UJ	1.05 UJ	0.873 UJ	–	**1.34**	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		11/11/19[o]	Peristaltic	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/20/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	**17.8**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		02/18/20[o]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	**–**	**2.4**	**–**	**1.8**	**–**	**13**	**400**	**0.56**	**290**	**–**	**18,000**	**1.2**
MW128		04/27/20	Peristaltic	0.120 U	0.478 U	11.3 U	0.671 U	–	**18.3**	0.118 U	0.136 U	0.129 U	0.605 UJ	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
(continued)		06/29/20	Peristaltic	0.0932 U	0.400 U	**1.64**	0.0760 U	0.580 U	**16.9**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 UJ	0.0229 U	0.0180 UJ	0.0432 U	0.0166 U
(split)		06/29/20[p]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		08/26/20[p]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/09/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**17.0**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		12/20/20[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/11/21[v]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/25/21	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**14.2**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-133	Property,	09/25/17	Bladder	0.138 U	0.823 U	**2.02 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.439 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	SW quadrant	04/25/18	Bladder	0.138 U	0.823 U	**3.72 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.236 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/26/18	Bladder	0.138 U	0.823 U	1.14 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.205 J**	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		12/12/18	Bladder	0.138 U	0.823 U	1.76 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		02/01/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		03/13/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	Decommissioned March, 2019																		
MW-137	Property,	09/25/17	Bladder	0.138 U	0.823 U	2.84 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**2.27**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	SW quadrant	04/12/18	Bladder	0.138 U	0.823 UJ	**3.31 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.210 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/26/18	Bladder	0.138 U	0.823 U	1.05 UJ	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.282 J**	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		12/12/18	Bladder	0.138 U	0.823 U	**1.62 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		02/01/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.114 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		03/11/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	Decommissioned March, 2019																		
MW-138	Dexter Ave N ROW,	09/21/17	Bladder	0.276 U	1.65 U	**5.55 J**	1.75 U	–	0.179 U	0.266 U	0.160 U	0.372 U	0.314 U	0.202 U	0.318 U	0.280 U	0.256 U	0.282 U	0.172 U
	E side	04/11/18	Bladder	0.138 U	0.823 UJ	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.214 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/29/18	Bladder	0.138 U	0.823 U	1.23 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		12/17/18	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.382 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/03/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		03/14/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.286 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/22/19	Bladder	0.138 U	0.823 U	**2.56 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	**0.405 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		07/19/19	Bladder	0.138 U	0.823 U	**1.82 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/21/19	Bladder	0.138 U	0.823 U	**1.23 J**	0.873 UJ	–	0.0896 U	0.133 U	0.0800 UJ	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/27/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		05/08/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/27/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/18/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/11/21	Bladder	0.0932 U	0.400 U	1.27 U	0.0760 U	0.580 U	**0.0240 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		06/07/21	Bladder	0.0932 U	0.400 U	**1.53**	0.0760 U	0.580 U	**0.100**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-140	Roy Street ROW,	09/22/17	Bladder	0.138 U	0.823 U	2.11 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
(dup)	E side	09/22/17	Bladder	0.138 U	0.823 U	3.74 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/12/18	Bladder	0.138 U	0.823 UJ	2.13 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.699 J+**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
MW-141	Property,	09/22/17	Bladder	0.138 U	0.823 U	4.56 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	SE quadrant	04/12/18	Submersible	0.138 U	0.823 UJ	1.38 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	**0.305 J+**
		10/25/18	Bladder	0.138 U	0.823 U	1.05 UJ	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.317 J**	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		12/12/18	Bladder	0.138 U	0.823 U	1.11 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	640	7,200	0.81	2.1	5.0	64	7.1	55	11	800	5	100	5.2	–	14
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	4.7E+05	1.5E+07	12	–	2.4	–	1.8	–	13	400	0.56	290	–	18,000	1.2
MW-141		01/30/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
(continued)		03/11/19	Bladder	0.138 U	0.823 U	**1.24 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	Decommissioned March, 2019																		
MW-153	Roy St ROW,	05/01/18	Bladder	0.138 U	0.823 U	2.65 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**4.54**	0.159 U	0.140 U	0.128 U	0.141 U	**0.870**
	S side	01/22/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/24/19	Bladder	0.138 U	0.823 U	3.82 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	**0.394 J**	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
	(dup)	04/24/19	Bladder	0.138 U	0.823 U	2.21 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	**0.303 J**	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		07/22/19	Bladder	0.138 U	0.823 U	**1.98 J**	0.873 U	–	**0.177 J**	0.133 U	0.0800 U	0.186 U	0.157 U	**0.250 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/15/19	Bladder	0.138 U	0.823 U	1.05 UJ	0.873 U	–	0.0896 U	0.133 UJ	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/21/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		04/30/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 UJ	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/15/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/09/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/09/21	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0200 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
	(dup)	02/09/21	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0220 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/10/21	Bladder	0.0932 U	0.400 U	**1.09 J+**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 UJ	0.0166 U
MW-158A	8th Ave N ROW,	04/30/18	Bladder	0.138 U	0.823 U	**5.00 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.580**	0.159 U	0.140 U	0.128 U	0.141 U	**1.29**
	E side	01/24/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.491 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/25/19	Bladder	0.138 U	0.823 U	3.23 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	**0.351 J**	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		07/19/19	Bladder	0.138 U	0.823 U	1.79 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	**0.437 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/16/19	Bladder	0.138 U	0.823 U	1.05 UJ	0.873 U	–	0.0896 U	0.133 UJ	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/21/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		04/24/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 UJ	**0.152 J**	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/15/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0520**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/23/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0240 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/02/21	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0270 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/10/21	Bladder	0.0932 U	0.400 U	**1.05 J+**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 UJ	0.0166 U
MW-160	8th Ave N ROW,	05/21/18	Bladder	0.138 U	0.823 U	**2.05 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	**0.186 J**
	W side	01/25/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		05/01/19	Bladder	0.138 U	0.823 U	4.06 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		07/23/19	Bladder	0.138 U	0.823 U	1.98 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/17/19	Bladder	0.138 U	0.823 U	3.26 U	0.873 U	–	0.0896 U	0.133 UJ	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/29/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/01/20	Bladder	0.138 U	0.823 U	5.85 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 UJ	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		08/03/20	Bladder	0.0932 U	0.400 U	**0.606 J**	0.0760 U	0.580 U	**0.0180 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	**0.929 J**	0.0166 U
		11/30/20	Bladder	0.0932 U	0.400 U	**1.67 J+**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	**1.31**	0.0166 U
		02/05/21	Bladder	0.0932 U	0.400 U	1.52 U	0.0760 U	0.580 U	0.0310 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	**1.16 J**	0.0166 U
		05/12/21	Bladder	0.0932 U	0.400 U	**1.90**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	**0.497**	0.0166 U
MW-161	8th Ave N ROW,	05/21/18	Bladder	0.138 U	0.823 U	**1.83 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	W side	01/25/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		05/01/19	Bladder	0.138 U	0.823 U	1.21 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		07/18/19	Bladder	0.138 U	0.823 U	**2.22 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/14/19	Bladder	0.138 U	0.823 UJ	1.05 UJ	0.873 UJ	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/28/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	–	**2.4**	–	**1.8**	–	**13**	**400**	**0.56**	**290**	–	**18,000**	**1.2**
MW-161 (continued)		04/03/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		07/31/20	Bladder	0.0932 U	0.400 U	0.548 UJ	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	**0.881**	0.0166 U
		12/01/20	Bladder	0.0932 U	0.400 U	**1.42 J+**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	**1.15**	0.0166 U
		02/05/21	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	**1.37 J**	0.0166 U
		05/25/21	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	**0.676**	0.0166 U
MW-162	Property, NE quadrant Decommissioned March, 2019	02/05/19	Bladder	1.00 U	–	–	–	–	1.00 U	1.00 U	1.00 U	2.00 U	1.00 U	–	1.00 U	1.00 U	1.00 U	1.00 U	1.00 U
		03/12/19	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	**0.521**
MW-163	Property, NW quadrant	02/05/19	Bladder	1.00 U	–	–	–	–	1.00 U	1.00 U	1.00 U	2.00 U	1.00 U	–	1.00 U	1.00 U	1.00 U	1.00 U	1.00 U
	(dup)	02/05/19	Bladder	1.00 U	–	–	–	–	1.00 U	1.00 U	1.00 U	2.00 U	1.00 U	–	1.00 U	1.00 U	1.00 U	1.00 U	1.00 U
	Decommissioned March, 2019	03/12/19	Bladder	0.138 U	0.823 U	**1.13 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.248 J**	0.159 U	0.140 U	0.128 U	0.141 U	**0.436 J**
MW-164	Property, SW quadrant Decommissioned March, 2019	02/05/19	Bladder	1.00 U	–	–	–	–	1.00 U	1.00 U	1.00 U	2.00 U	1.00 U	–	1.00 U	1.00 U	1.00 U	1.00 U	**3.83**
		03/12/19	Bladder	0.138 U	0.823 U	**1.27 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**1.07**	0.159 U	0.140 U	0.128 U	0.141 U	**2.99**
MW-304	Dexter Ave N ROW, E side	10/21/19	Bladder	0.138 U	0.823 U	**1.66 J**	0.873 UJ	–	0.0896 U	0.133 U	0.0800 UJ	0.186 U	0.157 U	**0.290 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/27/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.870**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		05/07/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 UJ	0.136 U	0.129 U	0.605 UJ	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 UJ	0.111 U
		07/27/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/18/21	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 UJ	0.0166 U
MW-319	9th Ave N ROW, W side	10/08/19	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.505**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/16/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**1.01**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/27/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 UJ	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/27/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0336 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/12/20	Bladder	0.0932 U	0.400 UJ	0.548 UJ	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 UJ	0.0166 U
		05/19/21	Peristaltic	0.0932 U	0.400 U	1.01 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 UJ	0.0166 U
MW-323	9th Ave N ROW, W side	10/09/19	Peristaltic	0.138 U	0.823 U	**2.67 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/20/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/23/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/07/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 UJ	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/24/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/20/21	Peristaltic	0.0932 U	0.400 U	1.38 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-324	Roy St ROW, N side	10/02/19	Bladder	0.138 U	0.823 U	6.39 U	0.873 U	–	**0.401 J**	0.133 U	0.0800 U	0.186 U	0.157 U	**5.63**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/20/20	Peristaltic	6.90 U	41.2 U	**114 J**	43.7 U	–	4.48 U	6.65 U	4.00 U	9.30 U	7.85 U	5.05 U	7.95 U	7.00 U	6.40 U	7.05 U	4.30 U
		04/24/20	Bladder	6.00 U	23.9 U	565 U	33.6 U	–	4.71 U	5.90 U	6.80 U	6.45 U	30.3 UJ	4.81 U	6.40 U	5.85 U	7.00 U	9.60 U	5.55 U
		07/07/20	Bladder	4.66 U	20.0 U	27.4 U	3.80 UJ	29.0 U	**1.25 J**	2.10 U	1.58 U	12.0 U	7.40 U	–	2.16 U	1.15 U	0.900 U	2.16 U	0.830 U
		11/13/20	Bladder	4.66 U	20.0 UJ	27.4 UJ	3.80 UJ	29.0 U	**2.51**	2.10 U	1.58 U	12.0 U	7.40 U	–	2.16 U	1.15 U	0.900 U	2.16 U	0.830 U
		05/20/21	Peristaltic	4.66 U	20.0 U	27.4 U	3.80 U	29.0 U	0.800 U	2.10 U	1.58 U	12.0 U	7.40 U	–	2.16 U	1.15 U	0.900 U	2.16 U	0.830 U
MW-326	Mercer Street ROW, N side	10/03/19	Bladder	0.138 U	0.823 U	4.34 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**4.09**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/17/20	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	**0.113 J**	0.133 U	0.0800 U	0.186 U	0.157 UJ	**0.792**	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		04/21/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	**0.108 J**	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/23/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0390 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	–	**2.4**	–	**1.8**	–	**13**	**400**	**0.56**	**290**	–	**18,000**	**1.2**
MW-326 (continued)		11/02/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0740**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/09/21	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0680**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/18/21	Bladder	0.0932 U	0.400 U	**1.20 J+**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 UJ	0.0166 U
MW-328	Lake Union Park, S end	10/02/19	Bladder	0.138 U	0.823 U	2.16 U	0.873 U	–	**17.0**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/17/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	**17.6**	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		04/08/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	**9.53**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		07/07/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 UJ	0.580 U	**10.3**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/09/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.630**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/25/21	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**6.19**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-329 (dup)	Westlake Ave N ROW, E side	10/03/19	Peristaltic	0.138 U	0.823 U	3.15 U	0.873 U	–	**0.206 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		10/03/19	Peristaltic	0.138 U	0.823 U	3.08 U	0.873 U	–	**0.215 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/20/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	**0.279 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/27/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	**0.704**	0.118 U	0.136 U	0.129 U	0.605 UJ	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		08/03/20	Bladder	0.0932 U	0.400 U	**0.630 J**	0.0760 U	0.580 U	**0.628**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/09/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.862**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/25/21	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.601**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-336	Mercer St ROW, N side	05/05/20	Bladder	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/08/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0490**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/02/20	Bladder	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.215**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/10/21	Bladder	0.0932 U	0.400 U	**1.64**	0.0760 U	0.580 U	**0.0660**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/26/21	Peristaltic	0.0932 U	0.400 U	**1.11**	0.0760 U	0.580 U	**0.128**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-341	Lake Union Park, S end	05/12/20	Peristaltic	0.120 U	0.478 U	11.3 U	0.671 U	–	**16.2**	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/07/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 UJ	0.580 U	**15.6**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/09/20	Peristaltic	0.0932 U	0.400 U	**2.51**	0.0760 U	0.580 U	**9.87**	0.0420 U	0.0315 U	0.239 U	0.148 U		0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/25/21	Peristaltic	0.0932 U	0.400 U	**3.69**	0.0760 U	0.580 U	**17.6**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-342	Valley St ROW, S side	05/04/20	Peristaltic	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	**0.643**	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/30/20	Peristaltic	0.0932 U	0.400 U	0.548 UJ	0.0760 U	0.580 U	**0.316**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/17/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.113**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		06/04/21	Peristaltic	0.0932 U	0.400 U	**0.852 J**	0.0760 U	0.580 U	**0.526**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-343	Valley St ROW, S side	05/04/20	Peristaltic	0.120 U	0.478 U	11.3 U	0.671 U	–	**0.114 J**	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/30/20	Peristaltic	0.0932 U	0.400 U	0.548 UJ	0.0760 U	0.580 U	**0.0471**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/24/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		06/04/21	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.139**	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
Treatment Zone A Wells																			
IW-4A	Property, NW quadrant Decommissioned March, 2019	03/28/18	Peristaltic	0.138 U	0.823 U	2.01 U	0.873 U	–	**0.205 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**17.2**	**0.526**
IW-7A	Property, NE quadrant Decommissioned March, 2019	04/02/18	Peristaltic	0.138 U	0.823 U	**4.08 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.144 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
IW-9A	Property, NW quadrant Decommissioned March, 2019	03/29/18	Peristaltic	0.138 U	0.823 U	2.70 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**4.90**	**0.173 J**

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	–	**2.4**	–	**1.8**	–	**13**	**400**	**0.56**	**290**	–	**18,000**	**1.2**
IW-18A	Property, NE quadrant Decommissioned March, 2019	03/30/18	Peristaltic	0.138 U	0.823 U	2.19 U	0.873 U	–	**0.306 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**3.63**	**0.292 J**
IW-22A	Property, NE quadrant Decommissioned March, 2019	04/02/18	Peristaltic	0.138 U	0.823 U	**3.74 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**0.395 J**	0.0860 U
IW-37A	Property, SW quadrant Decommissioned March, 2019	03/28/18	Peristaltic	0.138 U	0.823 U	1.64 U	0.873 U	–	**0.157 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
IW-41A	Property, SW quadrant Decommissioned March, 2019	04/10/18	Peristaltic	0.138 U	0.823 U	**7.16 J**	0.873 U	–	1.79 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.256 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
IW-42A	Property, SW quadrant Decommissioned March, 2019	04/10/18	Peristaltic	0.138 U	0.823 U	**1.94 J**	0.873 U	–	22.4 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.186 J**	0.159 U	0.140 U	0.128 U	**1.75 J**	0.0860 U
IW-45A	Property, SW quadrant Decommissioned March, 2019	04/04/18	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	**0.202 J**	0.133 U	0.0800 U	0.186 U	0.157 U	**0.143 J**	0.159 U	0.140 U	0.128 U	**4.93**	0.0860 U
IW-46A	Property, SE quadrant Decommissioned March, 2019	03/28/18	Peristaltic	0.138 U	0.823 U	**188**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.152 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
IW-48A	Property, SE quadrant Decommissioned March, 2019	04/02/18	Peristaltic	0.138 U	0.823 U	**117**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
MW-165	Property,	11/04/19	Peristaltic	0.138 U	0.823 U	**16.1 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	**0.357 J**	0.159 U	0.140 U	0.128 U	**0.723 J**	0.0860 U
	NE quadrant	01/30/20	Peristaltic	0.138 U	0.823 U	3.58 U	0.873 U	–	**0.176 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		05/01/20	Peristaltic	0.120 U	0.478 U	11.3 U	0.671 U	–	**0.162 J**	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/09/20	Peristaltic	0.0932 U	0.400 U	**7.42**	0.0760 U	0.580 U	**0.0900**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/05/20	Flowing	0.0932 U	0.400 U	**5.04**	0.0760 U	0.580 U	**0.138**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
	(dup)	11/05/20	Flowing	0.0932 U	**0.402 J**	**5.40**	0.0760 U	0.580 U	**0.152**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/04/21	Flowing	0.0932 U	0.400 U	3.43 U	7.60 U	0.580 U	**0.183**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/06/21	Flowing	0.932 U	4.00 U	8.04 U	0.760 U	5.80 U	0.160 U	0.420 U	0.315 U	2.39 U	1.48 U	–	0.432 U	0.229 U	0.180 U	0.432 UJ	0.166 U
MW-169	Property,	11/05/19	Peristaltic	0.138 U	0.823 U	**11.7 J**	0.873 U	–	**0.130 J**	0.133 U	0.0800 U	0.186 U	0.157 UJ	**0.962**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
	SW quadrant	01/23/20	Peristaltic	0.138 U	0.823 U	**2.10 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.508**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		05/05/20	Peristaltic	0.120 U	0.478 U	11.3 U	0.671 U	–	**0.127 J**	0.118 U	0.136 U	0.129 U	0.605 U	**0.527**	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/10/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0830**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/03/20	Flowing	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.113**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/17/21	Flowing	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.106**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/07/21	Flowing	0.0932 U	0.400 U	**1.53**	0.0760 U	0.580 U	**0.0800**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-173	Property,	11/01/19	Peristaltic	0.138 U	0.823 U	**3.84 J**	0.873 U	–	**0.141 J**	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	**0.850**
	SE quadrant	01/28/20	Peristaltic	0.138 U	0.823 U	2.88 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		05/01/20	Peristaltic	0.120 U	0.478 U	11.3 U	0.671 U	–	**0.139 J**	0.118 U	0.136 U	0.129 U	0.605 U	**0.168 J**	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	–	**2.4**	–	**1.8**	–	**13**	**400**	**0.56**	**290**	–	**18,000**	**1.2**
MW-173		07/09/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.103**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
(continued)		11/05/20	Flowing	0.0932 U	0.400 U	**0.873 J**	0.0760 U	0.580 U	**0.179**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/04/21	Flowing	0.0932 U	0.400 U	1.15 U	0.0760 U	0.580 U	**0.242**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/05/21	Flowing	0.0932 U	0.400 U	1.78 U	0.0760 U	0.580 U	**0.199**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-177	Property, SW quadrant	11/06/19	Peristaltic	0.138 U	0.823 U	**15.0 J**	0.873 U	–	**0.744**	0.133 U	0.0800 U	0.186 U	157 U	**38.3**	0.159 U	0.140 U	0.128 U	**6.29**	0.0860 U
		01/24/20	Peristaltic	6.90 U	41.2 U	**72.6 J**	43.7 U	–	4.48 U	6.65 U	4.00 U	9.30 U	7.85 U	5.05 U	7.95 U	7.00 U	6.40 U	7.05 UJ	4.30 U
		04/01/20	Peristaltic	690 U	4,110 U	**5,380 J**	4,370 U	–	448 U	665 U	400 U	930 UJ	785 UJ	505 U	795 U	700 U	640 U	705 U	430 U
		07/10/20	Peristaltic	466 U	2,000 U	2,740 U	380 U	2,900 U	80.0 U	210 U	158 U	1,200 U	740 U	–	216 U	115 U	90.0 U	216 U	83.0 U
		11/03/20	Flowing	93.2 U	400 U	548 U	76.0 U	580.0 U	16.0 U	42.0 U	31.5 U	239.0 U	148 U	–	43.2 U	22.9 U	18.0 U	43.2 U	16.6 U
		02/18/21	Flowing	18.6 U	80.0 U	110 U	15.2 U	116 U	3.20 U	8.40 U	6.30 U	47.8 U	29.6 U	–	8.64 U	4.58 U	3.60 U	**50.2**	3.32 U
		05/06/21	Flowing	18.6 U	80.0 U	110 U	15.2 U	116 U	3.20 U	8.40 U	6.30 U	47.8 U	29.6 U	–	8.64 U	4.58 U	3.60 U	**47.6**	3.32 U
MW-181	Property, SW quadrant	11/08/19	Peristaltic	0.690 U	4.12 U	**24.4 J**	0.873 U	–	**0.672 J**	0.133 U	0.0800 U	0.186 U	78.5 U	**3.91**	0.159 U	0.700 U	0.128 U	0.705 U	0.430 U
		01/27/20	Peristaltic	69.0 U	412 U	525 U	437.0 U	–	44.8 U	66.5 U	40.0 U	93.0 U	78.5 U	50.5 U	79.5 U	70.0 U	64.0 U	70.5 U	43.0 U
		04/01/20	Peristaltic	69.0 U	412 U	**647 J**	437.0 U	–	44.8 U	66.5 U	40.0 U	93.0 UJ	78.5 UJ	50.5 U	79.5 U	70.0 U	64.0 U	70.5 U	43.0 U
		07/08/20	Peristaltic	46.6 U	200 U	274 U	38.0 U	290.0 U	8.00 U	21.0 U	15.8 U	120.0 U	74.0 U	–	21.6 U	11.5 U	9.00 U	21.6 U	8.30 U
		11/04/20	Peristaltic	0.0932 U	**0.777 J**	**6.48**	0.0760 U	0.580 U	**0.336**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/19/21	Flowing	9.32 U	40.0 U	54.8 U	7.60 U	58.0 U	1.60 U	4.20 U	3.15 U	23.9 U	14.8 U	–	4.32 U	2.29 U	1.80 U	4.32 U	1.66 U
		05/06/21	Peristaltic	9.32 U	40.0 U	**112**	7.60 U	58.0 U	1.60 U	4.20 U	3.15 U	23.9 U	14.8 U	–	4.32 U	2.29 U	1.80 U	4.32 U	1.66 U
MW-185	Property, SE quadrant	10/31/19	Flowing	0.138 U	0.823 U	**79.4**	0.873 U	–	**0.140 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**0.930 J**	**0.504**
		01/29/20	Peristaltic	0.138 U	**1.15 J**	**108**	0.873 U	–	**0.228 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**0.325 J**	0.0860 U
		04/02/20	Peristaltic	0.138 U	**1.00 J**	**2.34 J**	0.873 U	–	**0.192 J**	0.133 U	0.0800 U	0.186 U	0.157 UJ	**0.168 J**	0.159 U	0.140 U	0.128 U	**0.309 J**	0.0860 U
		07/08/20	Peristaltic	0.0932 U	**0.864 J**	**3.06**	0.0760 U	0.580 U	**0.127**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	**0.650**	0.0166 U
		11/04/20	Flowing	0.0932 U	**0.426 J**	**0.922 J-**	0.0760 U	0.580 U	**0.148**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	**0.422**	0.0166 U
		02/16/21	Flowing	0.0932 U	0.400 U	**5.00 J+**	0.0760 U	0.580 U	**0.117**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/07/21	Flowing	0.0932 U	0.400 U	**0.782 J**	0.0760 U	0.580 U	**0.112**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
Treatment Zone B Wells																			
IW-3B	Property, NW quadrant Decommissioned March, 2019	03/28/18	Peristaltic	0.138 U	0.823 U	1.82 U	0.873 U	–	**0.158 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**15.0**	0.0860 U
IW-6B	Property, SW quadrant Decommissioned March, 2019	04/02/18	Peristaltic	0.138 U	0.823 U	**2.27 J**	0.873 U	–	**0.350 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
IW-8B	Property, SW quadrant Decommissioned March, 2019	03/30/18	Peristaltic	0.138 U	0.823 U	2.33 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
IW-17B	Property, NE quadrant Decommissioned March, 2019	03/30/18	Peristaltic	**0.141 J**	0.823 U	8.11 U	0.873 U	–	**0.838**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**5.32**	0.0860 U
IW-21B	Property, NE quadrant Decommissioned March, 2019	04/02/18	Peristaltic	0.138 U	0.823 U	**1.92 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**3.64**	0.159 U	0.140 U	0.128 U	**1.28 J**	**0.182 J**
IW-22B	Property, NW quadrant Decommissioned March, 2019	04/25/18	Peristaltic	2.76 U	16.5 U	21.0 U	17.5 U	–	1.79 U	2.66 U	1.60 U	3.72 U	3.14 U	2.02 U	3.18 U	2.80 U	2.56 U	2.82 U	1.72 U
IW-24B	Property, NE quadrant Decommissioned March, 2019	03/30/18	Peristaltic	**0.266 J+**	0.823 U	5.27 U	0.873 U	–	**0.754 J+**	0.133 U	0.0800 U	0.186 U	0.157 U	**0.806 J+**	0.159 U	**0.278 J+**	0.128 U	**3.05 J+**	0.0860 U
IW-28B	Property, NW quadrant Decommissioned March, 2019	04/09/18	Peristaltic	0.138 U	0.823 U	**7.35 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	–	**2.4**	–	**1.8**	–	**13**	**400**	**0.56**	**290**	–	**18,000**	**1.2**
IW-33B	Property, NE quadrant Decommissioned March, 2019	04/02/18	Peristaltic	0.138 U	0.823 U	**2.69 J**	0.873 U	–	**0.560**	0.133 U	0.0800 U	0.186 U	0.157 U	**0.915**	0.159 U	0.140 U	0.128 U	0.141 U	**0.200 J**
IW-37B	Property, SW quadrant Decommissioned March, 2019	03/29/18	Peristaltic	0.138 U	0.823 U	3.13 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.447 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
IW-45B	Property, SE quadrant Decommissioned March, 2019	03/28/18	Peristaltic	0.138 U	0.823 U	1.12 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.168 J**	0.159 U	0.140 U	0.128 U	**0.552 J**	0.0860 U
IW-47B	Property, SW quadrant Decommissioned March, 2019	04/10/18	Bladder	0.690 U	4.12 U	**51.7 J**	4.36 U	–	89.6 U	0.665 U	0.400 U	0.930 U	0.785 U	**1.08 J**	0.795 U	0.700 U	0.640 U	0.705 U	0.430 U
IW-49B	Property, SE quadrant Decommissioned March, 2019	03/28/18	Peristaltic	0.138 U	0.823 U	**221**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
IW-51B	Property, SE quadrant Decommissioned March, 2019	03/28/18	Peristaltic	0.138 U	0.823 U	**4.66 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.944**	0.159 U	0.140 U	0.128 U	**0.292 J**	0.0860 U
MW-166	Property, NE quadrant	11/04/19	Peristaltic	0.138 U	0.823 U	**46.4**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	**1.41**	0.159 U	0.140 U	0.128 U	**1.33 J**	**0.278 J**
		01/30/20	Peristaltic	0.138 U	0.823 U	20.5 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.309 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		05/01/20	Peristaltic	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	**0.0963 J**	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/09/20	Peristaltic	0.0932 U	0.400 U	**2.73 J**	0.0760 U	0.580 U	**0.0400 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
	(dup)	07/09/20	Peristaltic	0.0932 U	0.400 U	**4.04 J**	0.0760 U	0.580 U	**0.0460**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/05/20	Peristaltic	0.0932 U	0.400 U	**2.40**	0.0760 U	0.580 U	**0.0909**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/04/21	Flowing	46.6 U	200 U	274 U	38.0 U	290 U	8.00 U	21.0 U	15.8 U	120 U	74.0 U	–	21.6 U	11.5 U	9.00 U	21.6 U	8.30 U
		05/05/21	Flowing	18.6 U	80.0 U	110 U	15.2 U	116 U	3.20 U	8.40 U	6.30 U	47.8 U	29.6 U	–	8.64 U	4.58 U	3.60 U	8.64 UJ	3.32 U
MW-170	Property, SW quadrant	11/05/19	Peristaltic	0.138 U	0.823 U	**8.46 J**	0.873 U	–	**0.269 J**	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/23/20	Peristaltic	3.45 U	20.6 U	26.3 UJ	21.8 U	–	2.24 U	3.33 U	2.00 U	4.65 U	3.93 U	2.53 U	3.97 U	3.50 U	3.20 U	3.53 U	2.15 U
		04/02/20	Peristaltic	69.0 U	412 U	**1,040 J**	437.0 U	–	44.8 U	66.5 U	40.0 U	93.0 U	78.5 UJ	50.5 U	79.5 U	70.0 U	64.0 U	70.5 UJ	43.0 U
		07/09/20	Peristaltic	0.932 U	4.00 U	5.48 U	0.760 U	5.80 U	**0.450**	0.420 U	0.315 U	2.39 U	1.48 U	–	0.432 U	0.229 U	0.180 U	0.432 U	0.166 U
		11/03/20	Peristaltic	0.932 U	4.00 U	5.48 U	0.760 U	5.80 U	**0.290 J**	0.420 U	0.315 U	2.39 U	1.48 U	–	0.432 U	0.229 U	0.180 U	0.432 U	0.166 U
		02/17/21	Peristaltic	0.932 U	4.00 U	5.48 U	0.760 U	5.80 U	**0.320 J**	0.420 U	0.315 U	2.39 U	1.48 U	–	0.432 U	0.229 U	0.180 U	**28.5 J+**	0.166 U
		05/07/21	Peristaltic	46.6 U	200 U	**529**	38.0 U	290 U	8.00 U	21.0 U	15.8 U	120 U	74.0 U	–	21.6 U	11.5 U	9.00 U	21.6 U	8.30 U
MW-174	Property, SE quadrant	11/01/19	Peristaltic	0.138 U	0.823 U	**3.56 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	**1.28**
		01/28/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		05/01/20	Peristaltic	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	**0.149 J**	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/09/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/05/20	Flowing	0.0932 U	0.400 U	**0.562 J**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/04/21	Flowing	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	**0.102 J**	0.0166 U
		05/05/21	Flowing	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	**0.341**	0.0166 U
MW-178	Property, SW quadrant	11/06/19	Peristaltic	0.138 U	0.823 U	**245**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	3.14 U	**1.16**	0.159 U	0.140 U	0.128 U	0.141 U	**0.362 J**
		01/24/20	Peristaltic	0.138 U	**1.99 J**	**410 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	**0.265 J**	0.0860 U
		04/02/20	Peristaltic	0.138 U	**1.73 J**	**28.6**	0.873 U	–	**0.150 J**	0.133 U	0.0800 U	0.186 UJ	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		07/10/20	Peristaltic	0.0932 U	**1.32**	**6.27**	0.0760 U	0.580 U	**0.0510**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	**0.492**	0.0166 U
		11/03/20	Peristaltic	0.0932 U	**0.672 J**	**12.8 J**	0.0760 U	0.580 U	**0.282**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/18/21	Peristaltic	1.86 U	8.00 U	**29.5**	1.52 U	11.6 U	**0.500 J**	0.840 U	0.630 U	4.78 U	2.96 U	–	0.864 U	0.458 U	0.360 U	0.864 U	0.332 U
		05/06/21	Peristaltic	1.86 U	8.00 U	11.0 U	1.52 U	11.6 U	0.320 U	0.840 U	0.630 U	4.78 U	2.96 U	–	0.864 U	0.458 U	0.360 U	0.864 U	0.332 U
MW-182	Property, SW quadrant	11/08/19	Peristaltic	0.138 U	0.823 U	**56.6**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	78.5 U	**2.06**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/27/20	Peristaltic	69.0 U	412 U	525 U	437.0 U	–	44.8 U	66.5 U	40.0 U	93.0 U	78.5 U	50.5 U	79.5 U	70.0 U	64.0 U	70.5 U	43.0 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	–	**2.4**	–	**1.8**	–	**13**	**400**	**0.56**	**290**	–	**18,000**	**1.2**
MW-182		04/01/20	Peristaltic	6.90 U	41.2 U	52.5 UJ	43.7 UJ	–	4.48 U	6.65 U	4.00 U	9.30 U	7.85 U	5.05 U	7.95 U	7.00 U	6.40 U	7.05 U	4.30 U
(continued)		07/08/20	Peristaltic	4.66 U	20.0 U	27.4 U	3.80 U	29.0 U	0.800 U	2.10 U	1.58 U	12.0 U	7.40 U	–	2.16 U	1.15 U	0.900 U	2.16 U	0.830 U
		11/04/20	Peristaltic	4.66 U	20.0 U	**211 J-**	3.80 U	29.0 U	0.800 U	2.10 U	1.58 U	12.0 U	7.40 U	–	2.16 U	1.15 U	0.900 U	2.16 U	0.830 U
		02/19/21	Peristaltic	46.6 U	200 U	**667**	38.0 U	290 U	8.00 U	21.0 U	15.8 U	120 U	74.0 U	–	21.6 U	11.5 U	9.00 U	21.6 U	8.30 U
		05/06/21	Peristaltic	186 UJ	800 U	**2,080 J**	152 U	1,160 U	32.0 UJ	84.0 U	63.0 U	478 U	296 U	–	86.4 U	45.8 U	36.0 U	86.4 U	33.2 U
	(dup)	05/06/21	Peristaltic	**0.220 J**	0.400 U	**9.11 J**	0.0760 U	0.580 U	**0.362 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-186	Property, SE quadrant	10/31/19	Flowing	0.138 U	0.823 U	**4.13 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	**0.170 J**
		01/29/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/02/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 UJ	0.140 U	0.128 U	0.141 U	0.0860 U
		07/08/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/04/20	Peristaltic	0.0932 U	0.400 U	**0.816 J-**	0.0760 U	0.580 U	**0.0379 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/16/21	Flowing	0.0932 U	0.400 U	2.04 U	0.0760 U	0.580 U	**0.0570**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/07/21	Flowing	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0440**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
Treatment Zone C Wells																			
IW-1C	Property, NE quadrant Decommissioned March, 2019	03/29/18	Peristaltic	0.138 U	0.823 U	2.31 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**2.19**	0.159 U	0.140 U	0.128 U	**0.372 J**	**0.511**
IW-4C	Property, NE quadrant Decommissioned March, 2019	04/26/18	Peristaltic	0.138 U	0.823 U	2.54 U	0.873 U	–	**0.158 J**	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
IW-8C	Property, NE quadrant Decommissioned March, 2019	04/04/18	Peristaltic	0.138 U	0.823 U	**8.17 J**	0.873 U	–	**0.276 J**	0.133 U	0.0800 U	0.186 U	0.157 U	**0.850**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
IW-9C	Property, NE quadrant Decommissioned March, 2019	04/02/18	Peristaltic	0.138 U	0.823 U	**3.49 J**	0.873 U	–	**0.285 J**	0.133 U	0.0800 U	0.186 U	0.157 U	**1.07**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
IW-13C	Property, SW quadrant Decommissioned March, 2019	04/25/18	Peristaltic	0.138 U	0.823 U	**2.64 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.287 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
IW-15C	Property, SW quadrant Decommissioned March, 2019	03/30/18	Bladder	1.38 U	8.23 U	17.7 U	8.73 U	–	0.896 U	1.33 U	0.800 U	1.86 U	1.57 U	1.01 U	1.59 U	1.40 U	1.28 U	1.41 U	0.860 U
IW-19C	Property, SW quadrant Decommissioned March, 2019	03/29/18	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
IW-20C	Property, SW quadrant	03/30/18	Bladder	0.138 U	0.823 U	5.01 U	0.873 U	–	**0.208 J**	0.133 U	0.0800 U	0.186 U	0.157 U	**0.734**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
(dup)	Decommissioned March, 2019	03/30/18	Bladder	0.138 U	0.823 U	6.11 U	0.873 U	–	**0.198 J**	0.133 U	0.0800 U	0.186 U	0.157 U	**0.803**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
MW-167	Property, NE quadrant	11/04/19	Peristaltic	0.138 U	0.823 U	**1,120**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	**1.15**	0.159 U	0.140 U	0.128 U	0.141 U	**0.131 J**
		01/28/20	Peristaltic	0.138 U	0.823 U	**3.89 J**	0.873 U	–	**0.100 J**	0.133 U	0.0800 U	0.186 U	0.157 U	**1.76**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		05/01/20	Peristaltic	0.120 U	0.478 U	11.3 U	0.671 U	–	**0.0967 J**	0.118 U	0.136 U	0.129 U	0.605 U	**0.738**	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/09/20	Peristaltic	0.0932 U	0.400 U	**4.16**	0.0760 U	0.580 U	**0.0440**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/05/20	Peristaltic	0.0932 U	0.400 U	**0.818 J**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/04/21	Peristaltic	0.0932 U	0.400 U	1.09 U	0.0760 U	0.580 U	0.0340 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/05/21	Peristaltic	0.0932 U	0.400 U	**1.23**	0.0760 U	0.580 U	**0.0250 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-171	Property, SW quadrant	11/05/19	Peristaltic	0.138 U	0.823 U	**1,130**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	**0.332 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/23/20	Peristaltic	0.138 U	0.823 U	**1.94 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.595**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/02/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.494 J**	0.159 UJ	0.140 U	0.128 U	0.141 U	0.0860 U
		07/09/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0280 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	–	**2.4**	–	**1.8**	–	**13**	**400**	**0.56**	**290**	–	**18,000**	**1.2**
MW-171		11/03/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0440**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
(continued)		02/17/21	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.101**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	**1.54 J**	0.0166 U
(dup)		02/17/21	Peristaltic	0.0932 U	0.400 U	2.12 U	0.0760 U	0.580 U	**0.0880**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 UJ	0.0166 U
		05/07/21	Peristaltic	4.66 U	20.0 U	**55.3**	3.80 U	29.0 U	0.800 U	2.10 U	1.58 U	12.0 U	7.40 U	–	2.16 U	1.15 U	0.900 U	2.16 U	0.830 U
MW-175	Property, SE quadrant	11/01/19	Peristaltic	0.138 U	0.823 U	**12.5 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	**0.573**	0.159 U	0.140 U	0.128 U	0.141 U	**0.810**
		01/28/20	Peristaltic	0.138 U	0.823 U	**15.7 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**1.18**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		05/01/20	Peristaltic	0.120 U	0.478 U	11.3 U	0.671 U	–	**0.137 J**	0.118 U	0.136 U	0.129 U	0.605 U	**0.338 J**	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/09/20	Peristaltic	0.0932 U	0.400 U	**10.0**	0.0760 U	0.580 U	**0.0420**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/05/20	Peristaltic	0.0932 U	0.400 U	**1.08**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/04/21	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0400 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/05/21	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0270 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-179	Property, SW quadrant	11/06/19	Peristaltic	0.138 U	0.823 U	**19.1 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	15.7 U	**4.06**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/27/20	Peristaltic	0.138 U	0.823 U	**18.0 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.289 J**	0.159 U	0.140 U	0.128 U	**4.62**	0.0860 U
		04/02/20	Peristaltic	2.76 U	16.5 U	**44.3 J**	17.5 U	–	1.79 U	2.66 U	1.60 U	3.72 UJ	3.14 UJ	2.02 U	3.18 U	2.80 U	2.56 U	**23.3 J**	1.72 U
		07/10/20	Peristaltic	1.86 U	8.00 U	11.0 U	1.52 U	11.6 U	0.320 U	0.840 U	0.630 U	4.78 U	2.96 U	–	0.864 U	0.458 U	0.360 U	**23.9**	0.332 U
		11/03/20	Peristaltic	1.86 U	8.00 U	11.0 U	1.52 U	11.6 U	0.320 U	0.840 U	0.630 U	4.78 U	2.96 U	–	0.864 U	0.458 U	0.360 U	0.864 U	0.332 U
		02/18/21	Peristaltic	46.6 U	200 U	**524**	38.0 U	290 U	8.00 U	21.0 U	15.8 U	120 U	74.0 U	–	21.6 U	11.5 U	9.00 U	21.6 U	8.30 U
		05/06/21	Peristaltic	23.3 U	100 U	137 U	19.0 U	145 U	4.00 U	10.5 U	7.88 U	59.8 U	37.0 U	–	10.8 U	5.73 U	4.50 U	10.8 UJ	4.15 U
MW-183	Property, SW quadrant	11/08/19	Peristaltic	0.138 U	0.823 U	**15.4 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.597**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/27/20	Peristaltic	0.138 U	0.823 U	**75.8**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.304 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/02/20	Peristaltic	0.138 U	0.823 U	**32.3**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.576**	0.159 UJ	0.140 U	0.128 U	0.141 U	0.0860 U
		07/08/20	Peristaltic	0.0932 U	0.400 U	**1.51**	0.0760 U	0.580 U	**0.0270 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/04/20	Peristaltic	0.0932 U	0.400 U	**0.580 J-**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 UJ	–	0.0432 U	0.0229 U	0.0180 U	**2.58 J**	0.0166 U
		02/19/21	Peristaltic	0.0932 U	0.400 U	1.94 U	0.0760 U	0.580 U	**0.0510**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/06/21	Peristaltic	9.32 U	40.0 U	54.8 U	7.60 U	58.0 U	1.60 U	4.20 U	3.15 U	23.9 U	14.8 U	–	4.32 U	2.29 U	1.80 U	4.32 UJ	1.66 U
MW-187	Property, SE quadrant	11/01/19	Peristaltic	0.138 U	0.823 U	**12.3 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	**0.353 J**	0.159 U	0.140 U	0.128 U	0.141 U	**0.223 J**
		01/29/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/02/20	Peristaltic	0.138 U	0.823 U	1.05 UJ	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 UJ	0.0860 U
		07/08/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	**0.121 J**	0.0166 U
		11/04/20	Peristaltic	0.0932 U	0.400 U	**1.10 J-**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	**0.111 J**	0.0166 U
		02/16/21	Peristaltic	0.0932 U	0.400 U	2.20 U	0.0760 U	0.580 U	**0.0430**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/07/21	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
Treatment Zone D Wells																			
IW-1D	Property, NE quadrant Decommissioned March, 2019	04/03/18	Bladder	1.38 U	8.23 U	**29.1 J**	8.73 U	–	0.896 U	1.33 U	0.800 U	1.86 U	1.57 U	1.01 U	1.59 U	1.40 U	1.28 U	1.41 U	**0.968 J**
IW-3D	Property, NE quadrant Decommissioned March, 2019	04/03/18	Bladder	0.138 U	0.823 U	**5.37 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**3.26**	0.159 U	0.140 U	0.128 U	0.141 U	**0.408 J**
IW-4D	Property, SW quadrant Decommissioned March, 2019	03/29/18	Bladder	0.138 U	0.823 U	2.02 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**3.06**	0.159 U	0.140 U	0.128 U	0.141 U	**0.242 J**
IW-6D	Property, SW quadrant Decommissioned March, 2019	04/03/18	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**3.29**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	–	**2.4**	–	**1.8**	–	**13**	**400**	**0.56**	**290**	–	**18,000**	**1.2**
IW-8D	Property, SW quadrant Decommissioned March, 2019	04/04/18	Bladder	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**1.17**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
IW-9D	Property, SW quadrant Decommissioned March, 2019	04/04/18	Bladder	0.138 U	0.823 U	**4.46 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.969**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
IW-11D	Property, NE quadrant Decommissioned March, 2019	05/01/18	Bladder	0.138 U	0.823 U	3.92 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.792**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
MW-168	Property, NE quadrant	11/04/19	Peristaltic	0.138 U	0.823 U	**1.38 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	**0.219 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/31/20	Flowing	0.138 U	0.823 U	1.70 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 UJ	0.157 U	**0.198 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		05/01/20	Peristaltic	0.120 U	0.478 U	11.3 U	0.671 U	–	**0.104 J**	0.118 U	0.136 U	0.129 U	0.605 U	**0.244 J**	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/09/20	Peristaltic	0.0932 U	0.400 U	**8.47**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/05/20	Peristaltic	0.0932 U	**0.559 J**	**20.3**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/04/21	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0200 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/05/21	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0210 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-172	Property, SW quadrant	11/05/19	Flowing	0.138 U	0.823 U	**1.97 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	**0.244 J**
		01/23/20	Flowing	0.138 U	0.823 U	1.05 UJ	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	**0.155 J**
		04/02/20	Peristaltic	69.0 U	412 U	**930 J**	437.0 U	–	44.8 U	66.5 U	40.0 U	93.0 U	78.5 UJ	50.5 U	79.5 U	70.0 U	64.0 U	70.5 UJ	43.0 U
		07/09/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0550**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/03/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0830**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	**0.133**
		02/17/21	Flowing	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	**0.0490**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	**8.22 J+**	**0.0680 J**
		05/07/21	Peristaltic	9.32 U	40.0 U	54.8 U	7.60 U	58.0 U	1.60 U	4.20 U	3.15 U	23.9 U	14.8 U	–	4.32 U	2.29 U	1.80 U	4.32 U	1.66 U
MW-176	Property, SE quadrant	11/01/19	Flowing	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 UJ	**0.195 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/28/20	Flowing	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.247 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/28/20	Flowing	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.158 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		05/01/20	Peristaltic	0.120 U	0.478 U	11.3 U	0.671 U	–	0.0941 U	0.118 U	0.136 U	0.129 U	0.605 U	0.0962 U	0.128 U	0.117 U	0.140 U	0.192 U	0.111 U
		07/09/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/05/20	Peristaltic	0.0932 U	0.400 U	**1.36**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/04/21	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0280 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		05/05/21	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
MW-180	Property, SW quadrant	11/06/19	Flowing	0.138 U	0.823 U	**12.0 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.785 U	**3.81**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/24/20	Peristaltic	0.138 U	0.823 U	**4.52 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.469 J**	0.159 U	0.140 U	0.128 U	**6.73 J**	0.0860 U
		04/01/20	Peristaltic	0.690 U	4.12 U	9.35 U	4.37 U	–	0.448 U	0.665 U	0.400 U	0.930 UJ	0.785 UJ	0.505 U	0.795 U	0.700 U	0.640 U	0.705 U	0.430 U
		07/10/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	**3.23**	0.0166 U
		11/03/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	**2.66**	0.0166 U
		02/18/21	Flowing	0.0932 U	0.400 U	1.24 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	**5.00**	0.0166 U
		05/06/21	Peristaltic	0.0932 U	0.400 U	**1.96**	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	**5.21**	0.0166 U
MW-184	Property, SW quadrant	11/08/19	Flowing	0.138 U	0.823 U	**1.38 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	15.7 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/27/20	Flowing	0.138 U	0.823 U	**3.31 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/01/20	Peristaltic	1.38 U	8.23 U	10.5 UJ	8.73 UJ	–	0.896 U	1.33 U	0.800 U	1.86 U	1.57 U	1.01 U	1.59 U	1.40 U	1.28 U	1.41 U	0.860 U
		07/08/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/04/20	Peristaltic	0.932 U	4.00 U	**39.9 J-**	0.760 U	5.80 U	0.160 U	0.420 U	0.315 U	2.39 U	1.48 U	–	0.432 U	0.229 U	0.180 U	**9.41**	0.166 U
		02/19/21	Flowing	0.932 U	4.00 U	5.48 U	0.760 U	5.80 U	0.160 U	0.420 U	0.315 U	2.39 U	1.48 U	–	0.432 U	0.229 U	0.180 U	**33.8**	0.166 U
		05/06/21	Peristaltic	0.466 U	2.00 U	2.74 U	0.380 U	2.90 U	0.0800 U	0.210 U	0.158 U	1.20 U	0.740 U	–	0.216 U	0.115 U	0.0900 U	0.216 UJ	0.0830 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	4-Isopropyltoluene (p-Isopropyltoluene)	4-Methyl-2-pentanone (Methyl Isobutyl Ketone/MIBK)	Acetone	Acrylonitrile	Allyl chloride	Benzene	Bromobenzene	Bromodichloromethane	Bromoform	Bromomethane	Carbon Disulfide	Carbon tetrachloride	Chlorobenzene	Chlorodibromomethane	Chloroethane (Ethyl Chloride)	Chloroform
Preliminary Cleanup Level (PCUL)				–	**640**	**7,200**	**0.81**	**2.1**	**5.0**	**64**	**7.1**	**55**	**11**	**800**	**5**	**100**	**5.2**	–	**14**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				–	**4.7E+05**	**1.5E+07**	**12**	–	**2.4**	**–**	**1.8**	**–**	**13**	**400**	**0.56**	**290**	**–**	**18,000**	**1.2**
MW-188	Property, SE quadrant	10/31/19	Flowing	0.138 U	0.823 U	**2.54 J**	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		01/29/20	Flowing	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	**0.348 J**	0.159 U	0.140 U	0.128 U	0.141 U	0.0860 U
		04/02/20	Peristaltic	0.138 U	0.823 U	1.05 U	0.873 U	–	0.0896 U	0.133 U	0.0800 U	0.186 U	0.157 U	0.101 U	0.159 UJ	0.140 U	0.128 U	0.141 U	0.0860 U
		07/08/20	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		11/04/20	Peristaltic	0.0932 U	0.400 U	**0.702 J-**	0.0760 U	0.580 U	**0.0161 J**	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
		02/16/21	Peristaltic	0.0932 U	0.400 U	1.55 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	**1.76 J+**	0.0166 U
		05/07/21	Peristaltic	0.0932 U	0.400 U	0.548 U	0.0760 U	0.580 U	0.0160 U	0.0420 U	0.0315 U	0.239 U	0.148 U	–	0.0432 U	0.0229 U	0.0180 U	**2.42**	0.0166 U
			Number of Analytes Measured	1,240	1,222	1,222	1,221	440	1,269	1,239	1,269	1,239	1,239	779	1,269	1,269	1,270	1,270	1,270
			Number of Analytes Detected	21	17	419	0	0	409	0	1	0	0	176	3	1	0	107	78
			Frequency of Detection	2%	1%	34%	0%	0%	32%	0%	0%	0%	0%	23%	0.2%	0.1%	0.0%	8%	6%
			Maximum Detection	2.50	8.50	5,380 J	–	–	257	–	1.76	–	–	38.3	0.273 J	0.278 J+	–	50.2	20.9
			Minimum Detection	0.0932 U	0.400 U	0.548 U	0.0760 U	0.5800 U	0.0160 U	0.0420 U	0.0315 U	0.129 UJ	0.148 U	0.0962 U	0.043 U	0.0229 U	0.0180 U	0.0432 U	0.0166 U
			Number of Detections Above SL	–	0	0	0	0	62	0	0	0	0	0	0	0	0	–	1
			Frequency of Detection Above SL	–	0%	0%	0%	0%	5%	0%	0.0%	0%	0%	0%	0%	0%	0%	–	0.1%

Notes:

Gasoline Range Organics Analyzed by NWTPH-Gx.
Diesel Range Organics and Heavy Oil analyzed by NWTPH-Dx.
VOCs analyzed by EPA Method 8260C or 8260D.
Results shown in micrograms per liter (µg/L).
PCULs and Screening Levels from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021.
All groundwater sampling performed by PES Environmental, Inc. unless otherwise indicated.
a = Results provided by Hart Crowser.
b = Results provided by Farallon Consulting.
c = Select sample results for MW-210 incorrectly identified with location SMW-3 on lab reports and sampling forms.
(split) = Split samples collected consecutively.
(dup) = Field duplicate sample.
– = Not analyzed, results not available, or information not applicable.
Detected results shown in **bold.**
Detections above the groundwater PCUL level are shown in **bold and highlighted in gray.**
Shallow Zone detections above the groundwater screening level for soil vapor are shown in **bold and highlighted in orange.**
Shallow Zone detections above the groundwater PCUL and screening level for soil vapor are shown in **bold highlighted in grayish-orange.**
U = Not detected at or above the laboratory method detection limit (MDL); detections above the MDL but below the laboratory reported detection limit (RDL) are qualified with a "J."
J = The identification of the analyte is acceptable; the reported value is an estimate.
J+ = The result is an estimated quantity, but the result may be biased high.
J- = The result is an estimated quantity, but the result may be biased low.
z = Elevated chlorinated VOCs detected within the GRO elution range. No discernible petroleum pattern present. Project level qualifier assigned per laboratory review.
GRO results above the screening level and qualified with "z" are not considered in the Maximum Detection and are not included in the Number of Detections Above SL.

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
Shallow Water Bearing Zone																				
DMW-1S	615 Dexter, SE quadrant	03/25/19[a]	Unknown	1.0 U	1.0 U	1.0 U	1.0 U	–	–	1.0 U	1.0 U	–	–	1.0 U	–	5.0 U	1.0 U	1.0 U	1.0 U	1.0 U
		03/25/19[a]	Unknown	1.0 U	1.0 U	1.0 U	1.0 U	–	–	1.0 U	1.0 U	–	–	1.0 U	–	5.0 U	1.0 U	1.0 U	1.0 U	1.0 U
		03/18/20[a]	Unknown	2.0 U	0.20 U	–	–	–	–	**12**	0.20 U	–	–	–	–	–	5.0 U	–	–	–
DMW-2S	615 Dexter, SE quadrant	03/18/20[a]	Unknown	2.0 U	0.20 U	–	–	–	–	0.20 U	0.20 U	–	–	–	–	–	5.0 U	–	–	–
DMW-4S	Alley S of SE quadrant of 615 Dexter	03/19/20[a]	Unknown	2.0 U	0.20 U	–	–	–	–	**5.5**	0.20 U	–	–	–	–	–	5.0 U	0.40 U	–	–
DMW-5IA	Alley S of 615 Dexter	03/19/20[a]	Unknown	2.0 U	0.20 U	–	–	–	–	0.20 U	0.20 U	–	–	–	–	–	5.0 U	–	–	–
DMW-6	615 Dexter, NE quadrant	03/18/20[a]	Unknown	2.0 U	0.20 U	–	–	–	–	0.20 U	0.20 U	–	–	–	–	–	5.0 U	–	–	–
F5	Property, NW quadrant	03/28/17	Peristaltic	0.153 U	**516**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/22/17	Peristaltic	0.153 U	**10.4**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	Decommissioned March, 2019																			
F9	Property, NE quadrant	03/27/17	Peristaltic	0.153 U	**0.158 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/22/17	Peristaltic	0.153 U	**6.10**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	Decommissioned March, 2019																			
F13	Property, NE quadrant	03/27/17	Peristaltic	0.153 U	**0.218 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/22/17	Peristaltic	0.153 U	**0.194 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/05/18	Peristaltic	0.153 U	**0.375 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	Decommissioned March, 2019																			
FMW-143	9th Ave N ROW, E side	07/30/19[a]	Unknown	–	0.20 U	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		10/31/19	Peristaltic	0.153 UJ	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 UJ	0.162 UJ
		01/22/20	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		05/14/20	Bladder	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 U
		07/22/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0490 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 UJ	0.0472 U
G12	Property, NE quadrant	03/27/17	Peristaltic	0.153 U	**95.9**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/30/17	Peristaltic	0.153 U	**115**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	Decommissioned March, 2019																			
HMW-1S	SDOT Mercer Parcels, NE quadrant	3/25/19[a]	Peristaltic	1.0 U	1.0 U	1.0 U	1.0 U	–	–	1.0 U	1.0 U	–	–	1.0 U	–	5.0 U	1.0 U	1.0 U	1.0 U	1.0 U
		03/11/20[a]	Unknown	2.0 U	0.20 U	–	–	–	–	0.20 U	0.20 U	–	–	–	–	–	5.0 U	–	–	–
HMW-2S	SDOT Mercer Parcels, NE quadrant	3/25/19[a]	Peristaltic	1.0 U	1.0 U	1.0 U	1.0 U	–	–	1.0 U	1.0 U	–	–	1.0 U	–	5.0 U	1.0 U	1.0 U	1.0 U	1.0 U
		03/12/20[a]	Unknown	2.0 U	0.20 U	–	–	–	–	0.20 U	0.20 U	–	–	–	–	–	5.0 U	–	–	–
HMW-9S	SDOT Mercer Parcels, SW quadrant	03/17/20[a]	Unknown	2.0 U	0.20 U	–	–	–	–	0.20 U	0.20 U	–	–	–	–	–	5.0 U	–	–	–
HMW-10S	SDOT Mercer Parcels, SE quadrant	03/16/20[a]	Unknown	2.0 U	0.20 U	–	–	–	–	0.20 U	0.20 U	–	–	–	–	–	5.0 U	–	–	–
HMW-11S	SDOT Mercer Parcels, SE quadrant	03/11/20[a]	Unknown	2.0 U	**0.20**	–	–	–	–	0.20 U	0.20 U	–	–	–	–	–	5.0 U	–	–	–
HMW-20S	SDOT Mercer Parcels, NW quadrant	9/18/20[a]	Unknown	2.0 U	**1.4**	1.0 U	1.0 U	1.0 U	–	0.20 U	0.20 U		–	1.0 U	–	1.0 U	5.0 U	1.0 U	–	1.0 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
HMW-21S	SDOT Mercer Parcels, SE quadrant	11/3/20[a]	Unknown	–	–	–	–	–	–	–	–		–	–	–	–	–	–	–	–
HMW-22S	SDOT Mercer Parcels, SE quadrant	11/3/20[a]	Unknown	–	–	–	–	–	–	–	–		–	–	–	–	–	–	–	–
J5	Property, SW quadrant	03/21/17	Peristaltic	0.153 U	**253**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/26/17	Peristaltic	0.153 U	**366**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/05/18	Peristaltic	0.153 U	**222**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	Decommissioned March, 2019																			
J15	Property, SE quadrant	03/27/17	Peristaltic	0.153 U	**46.3**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/26/17	Peristaltic	0.153 U	**39.8**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
(dup)		06/26/17	Peristaltic	0.153 U	**39.3**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/05/18	Peristaltic	0.153 U	**26.3**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	Decommissioned March, 2019																			
K8	Property, SW quadrant	03/21/17	Peristaltic	0.153 U	**123**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/26/17	Peristaltic	0.153 U	**140**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/05/18	Peristaltic	0.153 U	**104**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	Decommissioned March, 2019																			
M15	Property, SE quadrant	03/27/17	Peristaltic	0.153 U	**32.7**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
(dup)		03/27/17	Peristaltic	0.153 U	**31.7**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/26/17	Peristaltic	0.153 U	**25.8**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/05/18	Peristaltic	0.153 U	**8.89**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	Decommissioned March, 2019																			
MW-8	Seattle Roy Aloha Shops, N end	03/20/17	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	**0.175 J**	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.195 U	0.143 U	0.162 U
		04/13/18	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	**0.341 J**	0.143 U	0.162 U
		07/18/19	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		10/10/19	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.886 U	0.143 U	0.162 U
		01/16/20	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		05/06/20	Peristaltic	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
		07/14/20	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 UJ	0.0472 U
MW-9	8th Ave N ROW, E side	03/20/17	Peristaltic	0.153 U	**0.140 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	**0.311 J**	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/20/17	Peristaltic	0.153 U	**0.214 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 UJ	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
(dup)		06/20/17	Peristaltic	0.153 U	**0.211 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 UJ	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		04/05/18	Peristaltic	0.153 U	**0.246 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 UJ	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/21/19	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/26/19	Peristaltic	0.153 U	**75.1**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/16/19	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/17/19	Peristaltic	0.153 UJ	**0.786**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		11/24/20	Peristaltic	0.0556 U	**0.221**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/05/21	Peristaltic	0.0556 U	**0.121**	0.0271 U	0.0400 U	0.0327 U	**0.179**	**0.0510 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/12/21	Peristaltic	0.0556 U	**0.117**	0.0271 U	0.0400 U	0.0327 U	0.0170 UJ	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/12/21	Peristaltic	0.0556 U	**0.119**	0.0271 U	0.0400 U	0.0327 U	**0.281 J**	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW121	8th Ave N ROW, E side	03/28/17	Peristaltic	0.153 U	**0.768**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/20/17	Peristaltic	0.153 U	**1.13**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 UJ	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		04/05/18	Peristaltic	0.153 U	**0.959**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
MW121		01/31/19	Peristaltic	0.153 U	**5.53**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
(continued)		04/29/19	Peristaltic	0.153 UJ	**5.39**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		07/19/19	Peristaltic	0.153 UJ	**1.01**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		11/30/20	Bladder	0.0556 U	**0.193**	0.0271 U	0.0400 U	0.0327 U	**0.199**	**0.0410 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/05/21	Peristaltic	0.0556 U	**3.85**	0.0271 U	0.0400 U	0.0327 U	**0.189**	**0.0410 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/12/21	Peristaltic	0.0556 U	**0.418**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0560 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
	(dup)	05/12/21	Peristaltic	0.0556 U	**0.380**	0.0271 U	0.0400 U	0.0327 U	**0.176**	**0.0580 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW125	Valley Street ROW, N side	03/22/17	Peristaltic	0.153 U	**0.341 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/28/17	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		04/06/18	Peristaltic	0.153 U	**0.278 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/21/19	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/23/19	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/18/19	Peristaltic	0.153 UJ	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/18/19	Bladder	0.153 U	**0.496 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 UJ	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/29/20	Bladder	0.153 U	**0.369 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		11/17/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	**0.478 J**	0.153 U	0.0472 U
		02/02/21	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 UJ	0.0170 U	**0.101**	0.508 UJ	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		05/11/21	Peristaltic	0.0556 UJ	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
	(dup)	05/11/21	Peristaltic	0.0556 UJ	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-154	Roy St ROW S side	04/30/18	Bladder	0.153 U	**1.77**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 UJ	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/21/19	Peristaltic	0.153 U	**2.03**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/24/19	Bladder	0.153 U	**1.76**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/15/19	Bladder	**0.161 J**	**2.55**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/14/19	Bladder	0.153 U	**1.40**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		01/21/20	Bladder	0.153 U	**2.26**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/30/20	Bladder	0.960 U	**2.58**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
		07/10/20	Bladder	0.0556 U	**1.83**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 UJ	0.0472 U
		11/09/20	Bladder	0.0556 U	**1.77**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/08/21	Bladder	0.0556 U	**0.203**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.106**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/10/21	Bladder	0.0556 UJ	**0.134**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-155	Roy Street ROW, S side	04/27/18	Peristaltic	0.153 U	**0.466 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/21/19	Peristaltic	0.153 U	**0.274 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/23/19	Peristaltic	0.153 U	**71.9**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/23/19	Bladder	0.153 U	**12.1**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/16/19	Bladder	0.153 UJ	**36.2**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/20/20	Bladder	0.153 U	**12.7**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		05/05/20	Bladder	0.960 U	**16.4**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 U
		08/03/20	Bladder	0.0556 U	**9.74**	0.0271 UJ	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 UJ
		11/11/20	Bladder	0.0556 U	**11.7**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-159	8th Ave N ROW, E side	04/26/18	Peristaltic	0.153 U	**1.09**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/21/19	Peristaltic	0.153 U	**0.651**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/26/19	Bladder	0.153 U	**1.23**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	(dup)	04/26/19	Bladder	0.153 U	**1.12**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
MW-159 (continued)		07/22/19	Bladder	0.153 U	**0.918**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/29/20	Bladder	0.153 U	**0.811**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		11/11/20	Bladder	0.0556 U	**0.561**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/08/21	Peristaltic	0.0556 U	**0.525**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0860 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/11/21	Peristaltic	0.0556 UJ	**0.518**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-210[c]	Valley Street ROW, N side	03/30/17	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/21/17	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 UJ	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/09/18	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/11/19	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		01/17/20	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	**2.44**	0.0924 U	0.102 U	1.07 U	**0.460 J**	0.143 U	**9.81**
		04/09/20	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/07/20	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-214 (dup)	Valley Street ROW, S side	03/30/17	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		03/30/17	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/09/18	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/11/19	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	**0.355 J**	0.157 U	0.305 U	0.377 UJ	**1.11**	0.0924 U	0.102 U	1.07 U	**4.32 J**	0.143 U	**0.521**
		01/20/20	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.250 U	0.143 U	0.162 U
		04/07/20	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/06/20	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-301 (dup)	Valley Street ROW, S side	11/30/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/30/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/05/21	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.209**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/14/21	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/14/21	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-305	Roy St ROW, S side	10/15/19	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/15/20	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/28/20	Bladder	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 UJ	0.105 U	0.105 U	0.101 U	0.430 UJ	0.174 U	0.157 U	0.0993 U
		07/27/20	Bladder	0.0556 U	0.0276 U	0.0271 UJ	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 UJ
		11/06/20	Bladder	0.0556 U	**0.107**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	**0.0704 J**	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/18/21	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-310	Alley E of Seattle Roy Aloha Shops	10/10/19	Peristaltic	0.153 U	**0.148 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	**0.352 J**	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/14/20	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	**0.203 J**	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		04/08/20	Peristaltic	0.153 U	**0.193 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	**2.04**	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	**1.38**
		08/04/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 UJ	–	0.242 U	**0.129**	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
(dup)		08/04/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 UJ	–	0.242 U	**0.128**	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/06/20	Bladder	0.0556 U	**0.134**	0.0271 U	0.0400 U	0.0327 U	**0.0585 J**	0.0212 U	0.508 U	–	0.242 U	**0.0868 J**	**0.0445**	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/03/21	Peristaltic	0.0556 U	**0.203**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.138**	0.508 U	–	0.242 U	**0.236**	**0.0230 J**	0.0118 U	0.265 U	0.124 U	0.153 U	**0.162 J**
MW-312	Alley E of Seattle Roy Aloha Shops	10/11/19	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		01/21/20	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/22/20	Bladder	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
		08/04/20	Bladder	0.0556 U	**0.0440 J**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/11/20	Bladder	0.0556 U	**0.0820 J**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
MW-312 (continued)		05/03/21	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	**0.0550 J**	**0.182**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 UJ	0.0472 U
MW-313	Alley E of Seattle Roy Aloha Shops	10/10/19	Bladder	0.153 U	**7.34**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		01/14/20	Bladder	0.153 U	**2.67**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		05/04/21	Bladder	0.0556 U	**2.31**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.160**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-320	9th Ave N ROW, W side	10/07/19	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	**2.62**	0.0924 U	0.102 U	1.07 U	0.174 U	**0.200 J**	**3.22**
		01/20/20	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	**6.56**	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	**4.76**
		04/29/20	Bladder	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 UJ	0.105 U	0.105 U	0.101 U	0.430 UJ	0.174 U	0.157 U	0.0993 U
		07/28/20	Bladder	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 UJ	0.105 U	0.105 U	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
		11/12/20	Bladder	0.0556 U	**0.0350 J**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/20/21	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	**0.107**	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-332	Roy St ROW, N side	05/04/20	Bladder	0.960 U	**0.419 J**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
		07/30/20	Bladder	0.0556 U	**0.110 J**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 UJ	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/12/20	Bladder	0.0556 U	**0.202**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/20/21	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-337	Lake Union Park, N end	05/07/20	Peristaltic	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 UJ
		07/23/20	Peristaltic	0.0556 U	**0.0560 J**	0.0271 U	0.0400 U	0.0327 U	**0.0930 J**	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/10/20	Peristaltic	0.0556 U	**0.0870 J**	0.0271 U	0.0400 U	0.0327 U	**0.0940 J**	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/04/21	Peristaltic	0.0556 U	**0.0490 J**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-339 (dup)	Lake Union Park, S end	05/14/20	Peristaltic	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 U
		05/14/20	Peristaltic	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 U
		07/23/20	Peristaltic	0.0556 U	**0.164**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/09/20	Peristaltic	0.0556 U	**0.238**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/25/21	Peristaltic	0.0556 U	**0.120**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
N7	Property, SW quadrant Decommissioned March, 2019	03/30/17	Peristaltic	0.153 U	**125**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.189 U	0.143 U	0.162 U
		06/27/17	Peristaltic	0.153 U	**153**	0.0976 U	0.117 U	0.127 U	–	0.158 UJ	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
R-MW2	Property, NE quadrant Decommissioned March, 2019	03/21/17	Peristaltic	0.153 U	**0.341 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/15/17	Peristaltic	0.153 U	**0.682**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/02/18	Peristaltic	0.153 U	**2.48**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
R-MW3	Property, NE quadrant Decommissioned March, 2019	03/21/17	Peristaltic	0.153 U	**0.575**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/28/17	Peristaltic	0.153 U	**0.735**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		04/04/18	Peristaltic	0.153 U	**1.35**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
R-MW5	Dexter Ave N ROW, E side	03/23/17	Peristaltic	0.153 U	0.933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/16/17	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/11/18	Bladder	0.153 UJ	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 UJ	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/03/19	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/22/19	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/16/19	Bladder	0.153 U	**0.131 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/21/19	Bladder	0.153 U	**0.302 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/24/20	Bladder	0.153 U	**0.265 J**	0.0976 U	0.117 U	0.127 UJ	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
R-MW5		11/18/20	Bladder	0.0556 U	**0.505**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
(continued)		02/11/21	Bladder	0.0556 U	**0.357**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
(dup)		02/11/21	Bladder	0.0556 UJ	**0.382**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/17/21	Bladder	0.0556 U	**0.186**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
R-MW6	8th Ave N ROW, E side	03/21/17	Peristaltic	0.153 U	**20.0**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/20/17	Peristaltic	0.153 U	**37.3**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 UJ	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		04/06/18	Peristaltic	0.153 U	**19.4**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/25/19	Peristaltic	0.153 U	**12.5**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/25/19	Peristaltic	0.153 U	**11.8**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		12/01/20	Peristaltic	0.0556 U	**2.15**	0.0271 U	0.0400 U	0.0327 UJ	0.0170 UJ	**0.0670 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		02/03/21	Peristaltic	0.0556 U	**1.22**	0.0271 U	0.0400 U	0.0327 UJ	0.0170 U	**0.0810 J**	0.508 UJ	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		05/17/21	Peristaltic	0.0556 U	**12.2**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.129**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
SCL-MW101	Alley E of Seattle Roy Aloha Shops	03/28/17	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	**0.598**	0.157 U	**0.612 J**	0.377 U	**19.3**	0.0924 U	0.102 U	1.07 U	**2.09**	**7.17**	**62.7**
		06/14/17	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	**17.1**	0.157 U	**3.39 J**	0.377 U	**29.9**	0.0924 U	0.102 U	1.07 U	**4.76**	**6.97**	**75.3**
		04/06/18	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	**11.7**	0.157 U	**4.87 J**	0.377 U	**29.7**	0.0924 U	0.102 U	1.07 U	**6.70**	**8.28**	**92.3**
		10/09/19	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	**16.6**	0.157 U	**4.81 J**	0.377 U	**49.9**	0.0924 U	0.102 U	1.07 U	**36.7**	**8.26**	**152**
		01/17/20	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	**1.61**	0.157 U	0.305 U	0.377 U	**37.2**	**0.133 J**	0.102 U	1.07 U	0.174 U	**14.2**	**125**
		04/07/20	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	**5.54**	0.157 U	0.305 U	0.377 U	**17.1**	0.0924 U	0.102 U	1.07 U	**9.28**	**4.08**	**39.9**
		11/24/20	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**3.53**	0.508 U	–	0.242 U	**32.9**	**0.215 J+**	0.0118 U	0.265 U	**14.7 J-**	**10.1**	**88.9**
		05/04/21	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	**0.0880 J**	**1.22**	0.508 U	–	0.242 U	**14.2**	**0.0570**	0.0118 U	0.265 U	0.124 U	**2.23**	**39.6**
SCL-MW105	Alley E of Seattle Roy Aloha Shops	03/28/17	Peristaltic	0.765 U	0.466 U	0.488 U	0.585 U	0.635 U	–	**26.5**	0.785 U	**58.6**	1.88 U	**66.9**	0.462 U	0.510 U	5.35 U	**3.64**	**4.61**	**134**
		06/15/17	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	**109**	0.157 U	**65.1**	0.377 U	**67.3**	0.0924 U	0.102 U	1.07 U	**5.20**	**4.77**	**126**
		04/06/18	Peristaltic	1.53 U	0.933 U	0.976 U	1.17 U	1.27 U	–	**26.6**	1.57 U	**36.9 J**	3.77 U	**53.2**	0.924 U	1.02 U	10.7 U	4.50 U	1.43	**88.0**
		10/10/19	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	**41.0**	0.157 U	**55.0**	0.377 U	**149**	0.0924 U	0.102 U	1.07 U	**4.44**	0.143 U	**359**
		01/17/20	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	**54.6**	0.157 U	0.305 U	0.377 U	**97.7**	0.0924 U	0.102 U	1.07 U	**4.55**	0.143 U	**187**
		04/01/20	Peristaltic	0.153 UJ	**0.550**	0.0976 U	0.117 U	0.127 U	–	**47.4**	0.157 U	**24.0**	0.377 UJ	**72.5**	0.0924 U	0.102 U	1.07 U	**2.74 J**	**3.02**	**128**
		07/24/20	Peristaltic	0.0556 U	0.0276 U	0.0271 UJ	0.0400 U	0.0327 U	0.0170 U	**35.1**	0.508 U	–	0.242 U	**97.0**	**0.0430**	0.0118 U	0.265 U	**3.49**	**4.24**	**185**
SCS-2	Seattle Roy Aloha Shops, N End	03/20/17	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	**155**	0.157 U	**3.96**	0.377 U	**19.0**	**1.41**	0.102 U	1.07 U	**61.8 J**	**2.49**	**43.9**
		06/12/17	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	**141**	0.157 U	**4.86 J**	0.377 U	**16.3**	**1.07**	0.102 U	1.07 U	**54.3**	**1.97**	**34.2**
		04/13/18	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	**37.3**	0.157 U	**12.5 J**	0.377 U	**15.6**	**0.759**	0.102 U	1.07 U	**21.2**	0.143 U	**23.8**
		07/18/19	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	**141**	0.157 U	**12.6**	0.377 UJ	**18.7**	**0.893**	0.102 U	1.07 U	**115 J**	**3.10**	**46.2**
(dup)		07/18/19	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	**187**	0.157 U	**12.2**	0.377 UJ	**17.5**	**0.854**	0.102 U	1.07 U	**104 J**	**3.05**	**43.2**
		10/10/19	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	**307**	0.157 U	**14.1**	0.377 U	**28.7**	**0.813**	0.102 U	1.07 U	**89.5 J**	0.143 U	**58.4**
		01/16/20	Peristaltic	1.53 U	0.933 U	0.976 U	1.17 U	1.27 U	–	**135**	1.57 U	3.05 U	3.77 U	**10.9**	0.924 U	1.02 U	10.7 U	**94.2**	1.43 U	**30.2**
Intermediate A Water-Bearing Zone																				
BB-8	Roy Street ROW, S side	03/22/17	Peristaltic	0.153 U	**3.10**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/14/17	Peristaltic	0.153 U	**12.6**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	**0.184 J**	0.143 U	0.162 U
		04/11/18	Peristaltic	0.153 UJ	**4.64 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 UJ	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
(dup)		04/11/18	Peristaltic	0.153 UJ	**6.28 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 UJ	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/23/19	Peristaltic	0.153 U	**81.5**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/23/19	Peristaltic	0.153 U	**7.57**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
BB-8		07/17/19	Bladder	0.153 U	**19.3**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
(continued)		10/22/19	Bladder	0.153 U	**31.8**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
(dup)		10/22/19	Bladder	0.153 U	**30.4**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/20/20	Bladder	0.153 U	**16.5**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
(dup)		01/20/20	Bladder	0.153 U	**16.0**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		05/12/20	Bladder	0.960 U	**17.6**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 UJ	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 U
		07/27/20	Bladder	0.0556 U	**26.3**	0.0271 UJ	0.0400 U	0.0327 U	0.0170 U	**0.0320 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	**0.0180 J**	0.265 U	0.124 U	0.153 U	0.0472 UJ
(dup)		07/27/20	Bladder	0.0556 U	**26.0**	0.0271 UJ	0.0400 U	0.0327 U	0.0170 U	**0.0710 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 UJ
		11/17/20	Bladder	0.0556 U	**101**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/11/21	Peristaltic	0.0556 UJ	**2.19**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.242**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		06/07/21	Bladder	0.0556 U	**6.94**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
DMW-3IA	615 Dexter, NE quadrant	03/18/20[a]	Unknown	2.0 U	0.20 U	–	–	–	–	0.20 U	0.20 U	–	–	–	–	–	5.0 U	–	–	–
FMW-142	9th Ave N ROW, E side	07/29/19[a]	Unknown	–	**0.36**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		10/31/19	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 UJ	0.174 U	0.143 UJ	0.162 U
		01/22/20	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		04/28/20	Bladder	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 UJ	0.105 U	0.105 U	0.101 U	0.430 UJ	0.174 U	0.157 U	0.0993 U
		07/08/20	Bladder	0.0556 U	**0.0320 J**	0.0271 U	0.0400 U	0.0327 U	**0.0510 J**	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/04/20	Bladder	0.0556 U	**0.0977 J**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/25/21	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	**0.0670 J**	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
GEI-1	Block 37, SW quadrant	03/24/17	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.207 U	0.143 U	0.162 U
		06/13/17	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	**0.244 J**	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	**1.02 J**	0.143 U	0.162 U
		04/22/19	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	**0.282 J**	0.143 U	0.162 U
		07/16/19	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	**0.189 J**	0.143 U	0.162 U
		10/21/19	Peristaltic	0.153 UJ	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	**0.239 J**	0.143 U	0.162 U
		01/22/20	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		04/29/20	Peristaltic	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 UJ	0.105 U	0.105 U	0.101 U	0.430 UJ	0.174 U	0.157 U	0.0993 U
(dup)		04/29/20	Peristaltic	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 UJ	0.105 U	0.105 U	0.101 U	0.430 UJ	0.174 U	0.157 U	0.0993 U
		07/30/20	Peristaltic	0.0556 U	0.0276 UJ	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 UJ	0.0345 U	**0.0386 J**	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
GEI-MW-1	Block 79 East, N end	01/23/20	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 UJ	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/29/20	Peristaltic	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	**0.161 J**	0.337 U	0.749 U	0.554 UJ	0.105 U	0.105 U	0.101 U	0.430 UJ	0.174 U	0.157 U	0.0993 U
		08/07/20	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 UJ	–	0.242 U	0.0345 U	**0.0860 J**	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/10/20	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	**0.300 J+**	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/13/21	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	**0.339**	0.0212 U	0.508 U	–	0.242 U	0.0345 U	**0.0800**	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
HC-4	601 Dexter, NE quadrant	04/12/19[a]	Unknown	1.0 U	1.0 U	1.0 U	1.0 U	–	–	1.0 U	1.0 U	–	–	1.0 U	–	–	–	0.10 U	–	–
HMW-2IA	SDOT Mercer Parcels, NE quadrant	03/25/19[a]	Peristaltic	1.0 U	**120**	1.0 U	1.0 U	–	–	1.0 U	1.0 U	–	–	1.0 U	–	5.0 U	1.0 U	1.0 U	1.0 U	1.0 U
		03/12/20[a]	Unknown	20 U	**180**	–	–	–	–	2.0 U	2.0 U		–	–	–	–	**50**	–	–	–
HMW-3IA	SDOT Mercer Parcels, NW quadrant	03/25/19[a]	Peristaltic	1.0 U	1.0 U	1.0 U	1.0 U	–	–	1.0 U	1.0 U	–	–	1.0 U	–	5.0 U	1.0 U	1.0 U	1.0 U	1.0 U
		03/13/20[a]	Unknown	2.0 U	0.20 U	–	–	–	–	0.20 U	0.20 U		–	–	–	–	5.0 U	–	–	–
HMW-6IA	SDOT Mercer Parcels, SW quadrant	03/13/20[a]	Unknown	2.0 U	0.20 U	–	–	–	–	0.20 U	0.20 U	–	–	–	–	–	5.0 U	0.40 U	–	–

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
HMW-9IA	SDOT Mercer Parcels, SW quadrant	03/19/20[a]	Unknown	2.0 U	**3.7**	–	–	–	–	0.20 U	0.20 U	–	–	–	–	–	5.0 U	–	–	–
		06/02/21	Bladder	0.0556 U	**136**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	**0.267 J+**	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
HMW-20IA	SDOT Mercer Parcels, NW quadrant	09/18/20[a]	Unknown	2.0 U	**840**	1.0 U	1.0 U	1.0 U	–	0.20 U	0.20 U		–	1.0 U	–	1.0 U	5.0 U	1.0 U	–	1.0 U
		06/02/21	Bladder	0.0556 U	**6,400**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	**0.0580 J+**	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW107	8th Ave N ROW, W side	03/27/17	Peristaltic	0.153 U	**6.82**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/19/17	Peristaltic	0.153 U	**7.29**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 UJ	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		04/09/18	Peristaltic	0.153 U	**72.1 J-**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/30/19	Peristaltic	0.153 U	**1,130**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		05/01/19	Peristaltic	0.153 UJ	**1,250**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		07/22/19	Bladder	0.153 U	**290**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/15/19	Bladder	0.153 UJ	**333**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/28/20	Bladder	3.06 U	**3,590**	1.95 U	2.34 U	2.54 U	–	3.16 U	3.14 U	6.10 U	7.54 U	2.52 U	1.85 U	2.04 U	21.4 U	3.48 U	2.86 U	3.24 U
		04/03/20	Bladder	0.153 U	**2,720**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/31/20	Bladder	1.39 U	**491 J**	0.678 U	1.00 U	0.818 U	0.425 U	0.530 U	12.7 U	–	6.05 UJ	0.863 U	0.350 U	0.295 U	6.63 U	3.10 U	3.83 U	1.18 U
		12/01/20	Peristaltic	1.39 U	**13.3**	0.678 U	1.00 U	0.818 U	0.425 U	0.530 U	12.7 U	–	6.05 U	0.863 U	0.350 U	0.295 U	6.63 U	3.10 U	3.83 U	1.18 U
		02/02/21	Peristaltic	0.0556 U	**5.36**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.166**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		06/02/21	Peristaltic	0.0556 U	**3.20**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW108	Alley E of Seattle Roy Aloha Shops	03/28/17	Peristaltic	0.153 U	**278**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/27/17	Bladder	0.153 U	**165**	0.0976 U	0.117 U	0.127 U	–	0.158 UJ	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/06/18	Peristaltic	0.153 U	**1,030**	0.0976 U	0.117 U	0.127 U	–	0.158 UJ	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
(dup)		04/06/18	Peristaltic	0.153 U	**1,020**	0.0976 U	0.117 U	0.127 U	–	0.158 UJ	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/22/19	Peristaltic	0.153 U	**1,180**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/29/19	Peristaltic	0.153 UJ	**970**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		07/15/19	Peristaltic	0.153 U	**918**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/10/19	Peristaltic	0.153 U	**1,080**	0.0976 U	0.117 U	0.127 U	–	**0.327 J**	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	23.8 U	0.143 U	**0.177 J**
		01/14/20	Peristaltic	3.83 U	**749**	2.44 U	2.93 U	3.18 U	–	3.95 U	3.93 U	7.63 U	9.43 U	3.15 U	2.31 U	2.55 U	26.8 U	4.35 UJ	3.58 U	4.05 U
		04/22/20	Bladder	24.0 U	**178**	2.78 U	3.05 U	9.35 U	–	3.43 U	8.43 U	18.7 U	150 U	2.63 U	2.63 U	2.53 U	10.7 U	4.35 U	3.93 U	2.48 U
		07/16/20	Bladder	1.39 U	**216**	0.678 U	1.00 U	0.818 U	0.425 U	0.530 U	12.7 U	–	6.05 U	0.863 U	**1.17**	0.295 U	6.63 U	3.10 U	3.83 U	1.18 U
(dup)		07/16/20	Bladder	0.0556 U	**264**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	**0.671**	**1.15**	**0.257**	0.265 U	0.124 U	0.153 U	0.0472 U
		11/04/20	Bladder	1.39 U	**413**	0.678 U	1.00 U	0.818 U	0.425 U	0.530 U	12.7 U	–	6.05 U	0.863 U	0.350 U	0.295 U	**23.3 J**	3.10 U	3.83 U	1.18 U
		02/09/21	Peristaltic	0.278 U	**269**	0.136 U	0.200 U	0.164 U	0.0850 U	0.106 U	2.54 U	–	1.21 U	0.173 U	0.0700 U	0.0590 U	1.33 U	0.620 U	0.765 U	0.236 U
		05/03/21	Peristaltic	0.278 U	**491**	0.136 U	0.200 U	0.164 U	0.0850 U	0.106 U	2.54 U	–	1.21 U	0.173 U	0.0700 U	0.0590 U	1.33 U	0.620 U	0.765 U	0.236 U
MW109	Alley E of Seattle Roy Aloha Shops	03/29/17	Peristaltic	0.153 U	**12.6**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/27/17	Bladder	0.153 U	**163**	0.0976 U	0.117 U	0.127 U	–	0.158 UJ	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/06/18	Peristaltic	0.153 U	**629**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/23/19	Peristaltic	0.153 U	**403**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/29/19	Peristaltic	0.153 UJ	**4.78**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		07/15/19	Peristaltic	0.153 U	**30.8**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/15/19	Peristaltic	0.153 U	**397**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/21/20	Peristaltic	0.153 U	**10.4**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/22/20	Bladder	0.960 U	**46.8**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	6.00 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
		07/06/20	Bladder	0.0556 U	**45.4**	0.0271 U	0.0400 U	0.0327 U	**0.217**	0.0212 U	0.508 U	–	0.242 U	0.0345 U	**0.0230 J**	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/02/20	Bladder	0.0556 U	**32.1**	0.0271 U	0.0400 U	0.0327 UJ	**0.391**	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
MW109		02/09/21	Bladder	0.0556 U	**9.89**	0.0271 U	0.0400 U	0.0327 U	**0.231**	**0.139**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
(continued)		05/03/21	Peristaltic	0.0556 U	**6.16**	0.0271 U	0.0400 U	0.0327 U	**0.138**	**0.154**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW110	Alley E of Seattle	03/23/17	Peristaltic	0.153 U	**644**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	Roy Aloha Shops	06/27/17	Bladder	0.153 U	**1,120**	0.0976 U	0.117 U	0.127 U	–	0.158 UJ	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/09/18	Bladder	0.153 U	**675** J-	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/23/19	Peristaltic	0.153 U	**673**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
(dup)		01/23/19	Peristaltic	0.153 U	**718**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/26/19	Bladder	0.153 U	**710**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/15/19	Bladder	0.153 U	**578**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/15/19	Bladder	0.153 U	**574**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/16/20	Bladder	0.765 U	**187**	0.488 U	0.585 U	0.635 U	–	0.790 U	0.785 U	1.53 U	1.89 U	0.630 U	0.462 U	0.510 U	5.35 U	0.870 U	0.715 U	0.810 U
		04/22/20	Bladder	4.80 U	**683**	0.555 U	0.610 U	1.87 U	–	0.685 U	1.69 U	3.74 U	30.0 U	0.525 U	0.525 U	0.505 U	2.15 U	0.870 U	0.785 U	0.497 U
		07/16/20	Bladder	0.278 U	**791**	0.136 U	0.200 U	0.164 U	0.0850 U	0.106 U	2.54 U	–	1.21 U	0.173 U	0.0700 U	0.0590 U	1.33 U	0.620 U	0.765 U	0.236 U
		11/04/20	Bladder	2.78 U	**894**	1.36 U	2.00 U	1.64 U	**7.07**	1.06 U	25.4 U	–	12.1 U	1.73 U	0.700 U	0.590 U	**46.0** J	6.20 U	7.65 U	2.36 U
		02/09/21	Bladder	0.0556 U	**401**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.158**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/04/21	Bladder	0.556 U	**334**	0.271 U	0.400 U	0.327 U	0.170 U	0.212 U	5.08 U	–	2.42 U	0.345 U	0.140 U	0.118 U	2.65 U	1.24 U	1.53 U	0.472 U
MW115	9th Ave N ROW, W side	03/22/17	Peristaltic	0.153 U	**0.643**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/22/17	Bladder	0.153 U	**0.523**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/11/18	Peristaltic	0.153 UJ	**0.272** J	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 UJ	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/30/19	Peristaltic	0.153 U	**0.316** J	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		07/17/19	Peristaltic	0.153 U	**0.787**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		10/22/19	Peristaltic	0.153 U	**0.819**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/20/20	Peristaltic	0.153 U	**0.880**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		05/05/20	Bladder	0.960 U	**0.654**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 U
		07/28/20	Bladder	0.960 U	**0.354** J	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 UJ	0.105 U	0.105 U	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
		11/12/20	Bladder	0.0556 U	**0.308**	0.0271 U	0.0400 U	0.0327 U	**0.195** J+	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/12/21	Bladder	0.0556 U	**0.244**	0.0271 U	0.0400 U	0.0327 U	**0.306**	**0.0730** J	0.508 U	–	0.242 U	0.0345 U	**0.0390** J	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		05/25/21	Peristaltic	0.0556 U	**0.140**	0.0271 U	0.0400 U	0.0327 U	**0.298**	0.0212 U	0.508 U	–	0.242 U	0.0345 U	**0.0420**	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW116	9th Ave N ROW, W side	03/21/17	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/16/17	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/11/18	Peristaltic	0.153 UJ	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 UJ	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/30/19	Bladder	0.153 U	**0.655**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		07/17/19	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		10/31/19	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 UJ	0.174 U	0.143 UJ	0.162 U
		01/21/20	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/29/20	Bladder	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 UJ	0.105 U	0.105 U	0.101 U	0.430 UJ	0.174 U	0.157 U	0.0993 U
		07/28/20	Bladder	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 UJ	0.105 U	0.105 U	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
		11/12/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/11/21	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.161**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	**0.0470**	0.265 U	0.124 UJ	0.153 U	0.0472 U
		05/25/21	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	**0.0170** J	**0.0300** J	0.265 U	0.124 U	0.153 U	0.0472 U
MW119	9th Ave N ROW, W side	03/29/17	Peristaltic	0.153 U	**42.9**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/28/17	Bladder	0.153 U	**5.99**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		04/05/18	Peristaltic	0.153 U	**18.3**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
MW119		01/21/19	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
(continued)		04/29/19	Peristaltic	0.153 UJ	**10.9**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		07/19/19	Peristaltic	0.153 UJ	**0.340 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/10/19	Peristaltic	0.153 U	**12.6**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		11/11/19[v]	Peristaltic	–	**10**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/14/20	Peristaltic	0.153 U	**9.63**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
(split)		01/14/20[v]	Peristaltic	–	**7.4**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/18/20[p]	Unknown	–	**6.6**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		03/24/20[p]	Unknown	–	**4.7**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/27/20	Peristaltic	0.960 U	**6.88**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 UJ	0.749 U	6.00 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
		05/19/20[p]	Unknown	–	**6.1**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/08/20	Bladder	0.0556 U	**6.67**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		07/28/20[p]	Unknown	–	**7.5**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		09/17/20[p]	Unknown	–	**7.8**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/11/20	Bladder	0.0556 U	**12.9**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		12/03/20[p]	Unknown	–	**6.6**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/10/21	Peristaltic	0.0556 UJ	**6.05**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
(split)		02/10/21[p]	Peristaltic	–	**5.0**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/20/21	Bladder	0.0556 U	**10.6**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW120	8th Ave N ROW, E side	03/28/17	Peristaltic	0.153 U	**18.4**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/28/17	Bladder	0.153 U	**16.0**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	**0.384 J**	0.143 U	0.162 U
		04/09/18	Peristaltic	0.153 U	**0.811**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/24/19	Peristaltic	0.153 U	**60.5**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		05/03/19	Peristaltic	0.153 U	**87.2**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
(dup)		05/03/19	Peristaltic	0.153 U	**89.0**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/16/19	Peristaltic	0.153 U	**74.9**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/17/19	Bladder	0.153 U	**48.8**	0.0976 U	0.117 U	0.127 UJ	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
(dup)		10/17/19	Bladder	0.153 U	**49.8**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/17/20	Bladder	0.153 U	**45.0**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 UJ	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/23/20	Bladder	0.960 U	**41.0**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 UJ	0.749 U	6.00 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 U
		07/14/20	Bladder	0.0556 U	**28.8**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 UJ	0.0472 U
		11/30/20	Bladder	0.0556 U	**36.6**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0660 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
(dup)		11/30/20	Bladder	0.0556 U	**37.0**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/05/21	Peristaltic	0.0556 U	**43.5**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0790 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/12/21	Peristaltic	0.0556 U	**29.7**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW127	8th Ave N ROW, E side	08/01/19	Peristaltic	0.153 U	**0.489 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/17/19	Bladder	0.153 UJ	**0.656**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/17/20	Bladder	0.153 U	**0.630**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/23/20	Bladder	0.960 U	**0.861**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 UJ	0.749 U	6.00 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
		07/14/20	Bladder	0.0556 U	**0.683**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 UJ	0.0472 U
(dup)		07/14/20	Bladder	0.0556 U	**0.662**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 UJ	0.0472 U
		11/13/20	Bladder	0.0556 UJ	**0.898**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 UJ	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/11/21	Peristaltic	0.0556 UJ	**0.737**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
MW131	Property,	03/27/17	Peristaltic	0.153 U	**243**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	SE quadrant	06/20/17	Peristaltic	0.765 U	**2.55**	0.488 U	0.585 U	0.635 U	–	0.790 U	0.785 U	1.52 U	1.88 U	0.630 U	0.462 UJ	0.510 U	5.35 U	0.870 UJ	0.715 U	0.810 U
		04/16/18	Peristaltic	0.153 U	**10.4**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/25/18	Peristaltic	0.153 U	**1.65** J+	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 UJ	0.162 U
		12/12/18	Peristaltic	**6.51**	**1.20**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/29/19	Peristaltic	0.153 U	**0.774**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		03/11/19	Peristaltic	0.153 U	**0.250** J	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	Decommissioned March, 2019																			
MW-142	8th Ave N ROW,	04/27/18	Peristaltic	0.153 U	**46.1**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	E side	01/28/19	Peristaltic	0.153 U	**5.62**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
(dup)		01/28/19	Peristaltic	0.153 U	**5.67**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/24/19	Peristaltic	0.153 U	**5.67**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/25/19	Bladder	0.153 U	**7.70**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/16/19	Bladder	0.153 UJ	**50.4**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/22/20	Bladder	0.153 U	**45.6**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		04/24/20	Bladder	0.960 U	**53.6**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 UJ	0.749 U	6.00 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
		07/30/20	Bladder	0.0556 U	**91.2** J	0.0271 U	0.0400 U	0.0327 U	**0.267**	0.0212 U	0.508 U	–	0.242 UJ	0.0345 U	**0.0322** J	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/24/20	Bladder	0.0556 U	**136**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0390 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
(dup)		11/24/20	Bladder	0.0556 U	**142**	0.0271 U	0.0400 U	0.0327 U	**0.293**	0.0340 U	0.508 U	–	0.242 U	0.0345 U	**0.0350** J	0.0118 U	0.265 U	0.124 UJ	0.153 U	**0.0480** J
		02/08/21	Peristaltic	0.0556 U	**80.5**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.220**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/19/21	Peristaltic	0.0556 U	**31.6**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.106**	0.508 U	–	0.242 U	**0.0560** J	0.0140 U	0.0118 U	0.265 U	**1.80**	**0.255** J	**0.329**
MW-144	8th Ave N ROW,	04/27/18	Peristaltic	0.153 U	**662**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	E side	01/28/19	Peristaltic	0.153 U	**10.4**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/23/19	Peristaltic	0.153 U	**4.09**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	Decommissioned December 2019																			
MW-144R	8th Ave N ROW,	12/16/19	Bladder	0.153 U	**251**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	E side	01/21/20	Bladder	1.53 U	**200**	0.976 U	1.17 U	1.27 U	–	1.58 U	1.57 U	3.05 U	3.77 U	1.26 U	0.924 U	1.02 U	10.7 U	1.74 U	1.43 U	1.62 U
		04/02/20	Bladder	0.153 U	**2.01**	0.0976 UJ	0.117 UJ	0.127 UJ	–	0.158 UJ	0.157 UJ	0.305 UJ	0.377 U	0.126 UJ	0.0924 UJ	0.102 UJ	1.07 UJ	0.174 UJ	0.143 UJ	0.162 UJ
		08/03/20	Bladder	0.0556 U	**0.459**	0.0271 UJ	0.0400 U	0.0327 U	0.0170 U	**0.0670** J	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 UJ
		11/23/20	Bladder	0.0556 U	**0.500**	0.0271 U	0.0400 U	0.0327 U	**0.0360** J	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		02/02/21	Peristaltic	0.0556 U	**0.450**	0.0271 U	0.0400 U	0.0327 UJ	0.0170 U	**0.150**	0.508 UJ	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		05/12/21	Peristaltic	0.0556 U	**0.405**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-146	Roy St ROW,	04/30/18	Bladder	0.153 U	**900**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	S side	01/22/19	Peristaltic	0.153 U	**1,080**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/24/19	Bladder	0.153 U	**257**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/19/19	Bladder	0.153 UJ	**257** J	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
(dup)		07/19/19	Bladder	0.153 U	**371** J	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/14/19	Bladder	0.153 U	**1,350**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		01/24/20	Bladder	15.3 U	**1,460**	9.76 U	11.7 U	12.7 UJ	–	15.8 U	15.7 U	30.5 U	37.7 U	12.6 U	9.24 U	10.2 U	107 U	17.4 U	14.3 U	16.2 U
(dup)		01/24/20	Bladder	0.153 U	**1,510**	0.0976 U	0.117 U	0.127 UJ	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/30/20	Bladder	96.0 U	**2,100**	11.1 U	12.2 U	37.4 U	–	13.7 U	33.7 U	74.9 U	55.4 U	10.5 U	10.5 U	10.1 U	43.0 U	17.4 U	15.7 U	9.93 U
		07/09/20	Bladder	0.0556 U	**2,750**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/10/20	Bladder	2.78 UJ	**3,900**	1.36 U	2.00 U	1.64 U	0.850 U	1.06 UJ	25.4 U	–	12.1 U	1.73 U	0.700 UJ	0.590 U	13.3 U	6.20 U	7.65 U	2.36 U
(split)		11/10/20	Bladder	5,000 U	**3,800**	500 U	500 U	500 U	–	500 U	500 U	2,500 U	–	500 U	–	500 U	2,500 U	500 U	–	500 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
MW-146		02/08/21	Peristaltic	0.0556 U	**2,690**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.183**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
(continued)		05/04/21	Bladder	2.78 U	**536**	1.36 U	2.00 U	1.64 U	0.850 U	1.06 U	25.4 U	–	12.1 U	1.73 U	0.700 U	0.590 U	13.3 U	6.20 U	7.65 U	2.36 U
MW-149	Property,	04/10/18	Peristaltic	0.765 U	**10,500**	0.488 U	0.585 U	0.635 U	–	**0.813 J**	0.785 U	1.52 UJ	1.88 U	0.630 U	0.462 U	0.510 U	5.35 U	0.870 U	0.715 U	0.810 UJ
	NE quadrant	10/25/18	Peristaltic	30.6 U	**3,320**	0.0976 U	0.117 U	25.4 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 UJ	0.162 U
		12/13/18	Peristaltic	0.153 U	**5,150**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	**0.164 J**
(dup)		12/13/18	Peristaltic	0.153 U	**5,210**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	**0.164 J**
		01/29/19	Peristaltic	15.3 U	**4,350**	9.76 U	11.7 U	12.7 U	–	15.8 U	15.7 U	30.5 U	37.7 U	12.6 U	9.24 U	10.2 U	107 U	17.4 UJ	14.3 U	16.2 U
		03/13/19	Peristaltic	0.153 U	**30,800**	0.0976 U	0.117 U	0.127 U	–	**0.843**	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	Decommissioned March, 2019																			
MW-151	Property,	04/10/18	Peristaltic	0.153 UJ	**59.1 J-**	0.0976 U	0.117 U	0.127 U	–	0.158 UJ	0.157 U	0.305 UJ	0.377 U	0.126 UJ	0.0924 UJ	0.102 UJ	1.07 UJ	0.174 UJ	0.143 UJ	0.162 UJ
	SW quadrant	10/25/18	Peristaltic	0.153 U	**5.80**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 UJ	0.162 U
		12/14/18	Peristaltic	0.153 U	**1,690**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/31/19	Peristaltic	0.153 U	**466**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	**0.560 J**	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		03/12/19	Peristaltic	0.153 U	**196**	0.0976 U	0.117 U	0.127 U	–	**4.88**	0.157 U	**0.589 J**	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	Decommissioned March, 2019																			
MW-156	8th Ave N ROW,	04/26/18	Peristaltic	0.153 U	**2,850**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	E side	01/24/19	Peristaltic	0.153 U	**2,050**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/24/19	Peristaltic	0.153 U	**1,770**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
(dup)		04/24/19	Peristaltic	0.153 U	**1,760**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/22/19	Bladder	0.153 U	**2,310**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/17/19	Bladder	1.53 UJ	**1,420**	0.976 U	1.17 U	1.27 U	–	1.58 U	1.57 U	3.05 U	3.77 U	1.26 U	0.924 U	1.02 U	10.7 U	1.74 U	1.43 U	1.62 U
		01/20/20	Bladder	1.53 U	**1,590**	0.976 U	1.17 U	1.27 U	–	1.58 U	1.57 U	3.05 U	3.77 U	1.26 U	0.924 U	1.02 U	10.7 U	1.74 U	1.43 U	1.62 U
		04/24/20	Bladder	48.0 U	**1,240**	5.55 U	6.10 U	18.7 U	–	6.85 U	16.9 UJ	37.4 U	300 U	5.25 U	5.25 U	5.05 U	21.5 U	8.70 U	7.85 U	4.97 U
		07/15/20	Bladder	2.78 U	**1,040**	1.36 U	2.00 U	1.64 U	0.850 U	1.06 U	25.4 U	–	12.1 U	1.73 U	0.700 U	0.590 U	13.3 U	6.20 U	7.65 U	2.36 U
		11/11/20	Bladder	0.0556 U	**850**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/08/21	Peristaltic	0.556 U	**703**	0.271 U	0.400 U	0.327 U	0.170 U	0.212 U	5.08 U	–	2.42 U	0.345 U	0.140 U	0.118 U	2.65 U	1.24 U	1.53 U	0.472 U
		05/10/21	Bladder	2.78 UJ	**580**	1.36 U	2.00 U	1.64 U	0.850 U	1.06 U	25.4 U	–	12.1 U	1.73 U	0.700 U	0.590 U	**18.2 J**	6.20 U	7.65 U	2.36 U
MW-189	Valley St ROW,	10/14/19	Bladder	0.153 U	**2.23**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
	S side	01/23/20	Bladder	0.153 U	**0.514**	0.0976 U	0.117 U	0.127 UJ	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/03/20	Bladder	0.153 U	0.435 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
(dup)		04/03/20	Bladder	0.153 U	0.449 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		08/04/20	Bladder	0.0556 U	**0.115**	0.0271 UJ	0.0400 U	0.0327 U	0.0170 U	**0.0240 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 UJ
		11/17/20	Bladder	0.0556 U	**0.0910 J**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/03/21	Bladder	0.0556 U	**1.74**	0.0271 U	0.0400 U	0.0327 UJ	0.0170 U	0.0212 U	0.508 UJ	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		05/14/21	Bladder	0.0556 U	**6.63**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-302	Dexter Ave N	10/21/19	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	ROW	01/24/20	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 UJ	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		05/07/20	Bladder	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 UJ
		07/28/20	Bladder	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 UJ	0.105 U	0.105 U	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
		11/17/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0600 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/17/21	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-306	Dexter Ave N ROW,	10/15/19	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	E side	01/16/20	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	16	0.44	80	1,600	1,600	700	0.56	480	–	800	–	24	5	160	400	800
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				150	–	–	–	6	–	1,200	–	8	–	720	–	600	4,800	8.9	–	2,300
MW-306 (continued)		04/28/20	Bladder	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 UJ	0.105 U	0.105 U	0.101 U	0.430 UJ	0.174 U	0.157 U	0.0993 U
		07/29/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/06/20	Bladder	0.0556 U	**0.0418 J**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/18/21	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-308	Alley E of Seattle Roy Aloha Shops	10/11/19	Peristaltic	0.153 U	**38.9**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		01/16/20	Peristaltic	0.153 U	**11.9**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	**0.675**	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/08/20	Peristaltic	0.153 U	**12.5**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	**0.582**	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/06/20	Peristaltic	0.0556 U	**16.0**	0.0271 U	0.0400 U	0.0327 U	**0.253**	**0.0620 J**	0.508 U	–	0.242 U	**1.83**	**0.105**	0.0118 U	0.265 U	0.124 U	0.153 U	**0.229**
		11/06/20	Peristaltic	0.0556 U	**6.38**	0.0271 U	0.0400 U	0.0327 U	**0.356**	**0.115**	0.508 U	–	0.242 U	**5.05**	**0.245**	0.0118 U	0.265 U	0.124 U	0.153 U	**0.845**
		05/04/21	Peristaltic	0.0556 U	**3.98**	0.0271 U	0.0400 U	0.0327 U	**0.105**	**0.104**	0.508 U	–	0.242 U	**3.77**	**0.0760**	**0.0500**	0.265 U	0.124 U	0.153 U	**0.735**
MW-315	Mercer St ROW, N side	10/03/19	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/16/20	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/24/20	Bladder	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 UJ	0.749 U	6.00 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
		07/24/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0760 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	**0.558**	0.153 U	0.0472 U
		11/02/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 UJ	0.0170 U	**0.0460 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/17/21	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-317	9th Ave N ROW, W side	10/09/19	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/16/20	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	**0.136 J**	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/27/20	Bladder	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 UJ	0.749 U	6.00 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
		07/30/20	Peristaltic	0.0556 U	**0.0545 J**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.205**	0.508 U	–	0.242 UJ	0.0345 U	**0.0431**	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/10/20	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/19/21	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	**0.135**	**0.0640**	0.265 U	**0.274 J**	0.153 U	0.0472 U
MW-325	Mercer St ROW, N side	10/03/19	Bladder	0.153 U	**0.607**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/17/20	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 UJ	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/21/20	Bladder	0.960 U	**0.696**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	6.00 U	0.105 U	0.105 UJ	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
		07/23/20	Bladder	0.0556 U	**0.262**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0450 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/02/20	Bladder	0.0556 U	**0.802**	0.0271 U	0.0400 U	0.0327 UJ	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/08/21	Bladder	0.0556 U	**1.50**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.230**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/17/21	Bladder	0.0556 U	**0.973**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-327	Lake Union Park, S end	10/02/19	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/17/20	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/09/20	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/07/20	Peristaltic	0.0556 U	**0.0580 J**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/09/20	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 UJ	0.0170 U	**0.0340 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/25/21	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 UJ	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 UJ	0.0118 U	0.265 U	0.124 U	0.153 UJ	0.0472 U
MW-330 (dup)	Valley St ROW, N side	05/14/20	Bladder	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 U
		05/14/20	Bladder	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 U
		07/16/20	Bladder	0.0556 U	**0.0583 J**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0690 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		12/01/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 UJ	0.0170 UJ	**0.113**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
(dup)		12/01/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 UJ	0.0170 UJ	**0.127**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		05/25/21	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
MW-331	Alley E of Seattle	04/24/20	Peristaltic	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	**0.257 J**	0.337 UJ	0.749 U	6.00 U	**0.604**	0.105 U	0.101 U	0.430 U	0.174 U	0.157 U	**1.64**
	Roy Aloha Shops	07/06/20	Peristaltic	0.0556 U	**0.0460 J**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0340 J**	0.508 U	–	0.242 U	**0.0770 J**	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	**0.196 J**
		11/06/20	Peristaltic	0.0556 U	**0.0728 J**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0354 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	**0.0566 J**
		05/04/21	Peristaltic	0.0556 U	**0.0370 J**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-333	900 Roy St,	04/29/20	Bladder	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	**0.189 J**	0.337 U	0.749 U	0.554 UJ	0.105 U	**0.158 J**	0.101 U	0.430 UJ	0.174 U	0.157 U	0.0993 U
	S end	07/24/20	Bladder	0.0556 U	0.0276 U	0.0271 UJ	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	**0.239**	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 UJ
		11/05/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	**0.217**	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/18/21	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	**0.276**	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-344	SDOT Mercer Parcels,	06/01/21	Bladder	0.0556 U	**8.50**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
Intermediate B Water-Bearing Zone																				
FMW-141	Alley E of Seattle	07/26/19[b]	Unknown	–	**6,200**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
	Roy Aloha Shops	10/30/19	Peristaltic	0.153 UJ	**1,200 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
(dup)		10/30/19	Peristaltic	0.153 UJ	**2,250 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		11/11/19[b]	Unknown	–	**3,500**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/14/20	Bladder	0.765 U	**414**	0.488 U	0.585 U	0.635 U	–	0.790 U	0.785 U	1.53 UJ	1.89 U	0.630 U	0.462 U	0.510 U	5.35 U	0.903 U	0.715 U	0.810 U
(split)		01/14/20[b]	Unknown	–	**250**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/17/20[b]	Unknown	–	**280**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		03/24/20[b]	Unknown	–	**1,200**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/27/20[b]	Unknown	–	**440**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/28/20	Bladder	4.80 U	**1,300**	0.555 U	0.610 U	1.87 U	–	0.685 U	1.69 U	3.74 U	2.77 UJ	0.525 U	0.525 U	0.505 U	2.15 UJ	0.870 U	0.785 U	0.497 U
		05/19/20[b]	Unknown	–	**2,400**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/22/20	Bladder	1.11 U	**790**	0.542 U	0.800 U	0.654 U	0.340 U	0.424 U	10.2 U	–	4.84 U	0.690 U	0.280 U	0.236 U	5.30 U	2.48 U	3.06 U	0.944 U
		07/28/20[b]	Unknown	–	**8,100**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		09/17/20[b]	Unknown	–	**600**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/02/20	Bladder	**2.80**	**276**	0.0271 U	0.0400 U	0.0327 UJ	**0.325**	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		12/03/20[b]	Unknown	–	**68**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/10/21[b]	Unknown	–	**120**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/03/21	Peristaltic	0.0556 U	**5.41**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0800 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
HMW-1IB	SDOT Mercer Parcels,	03/25/19[a]	Peristaltic	1.0 U	**22**	1.0 U	1.0 U	–	–	1.0 U	1.0 U	–	–	1.0 U	–	5.0 U	1.0 U	1.0 U	1.0 U	1.0 U
	NE quadrant	03/10/20[a]	Unknown	2.0 U	**16**	–	–	–	–	0.20 U	0.20 U	–	–	–	–	–	5.0 U	–	–	–
HMW-2IB	SDOT Mercer Parcels,	03/25/19[a]	Peristaltic	1.0 U	1.0 U	1.0 U	1.0 U	–	–	1.0 U	1.0 U	–	–	1.0 U	–	5.0 U	1.0 U	1.0 U	1.0 U	1.0 U
	NE quadrant	03/12/20[a]	Unknown	2.0 U	**0.59**	–	–	–	–	0.20 U	0.20 U	–	–	–	–	–	5.0 U	–	–	–
HMW-4IA	SDOT Mercer Parcels,	03/25/19[a]	Peristaltic	1.0 U	1.0 U	1.0 U	1.0 U	–	–	1.0 U	1.0 U	–	–	1.0 U	–	5.0 U	1.0 U	1.0 U	1.0 U	1.0 U
	SW quadrant	03/10/20[a]	Unknown	2.0 U	0.20 U	–	–	–	–	0.20 U	0.20 U	–	–	–	–	–	5.0 U	0.40 U	–	–
HMW-5IB	SDOT Mercer Parcels,	03/17/20[a]	Unknown	2.0 U	0.20 U	–	–	–	–	0.20 U	0.20 U	–	–	–	–	–	5.0 U	0.40 U	–	–
	SW quadrant																			
HMW-6IB	SDOT Mercer Parcels,	03/13/20[a]	Unknown	2.0 U	0.20 U	–	–	–	–	0.20 U	0.20 U	–	–	–	–	–	5.0 U	0.40 U	–	–
	SW quadrant																			
HMW-7IB	SDOT Mercer Parcels,	03/12/20[a]	Unknown	2.0 U	0.20 U	–	–	–	–	0.20 U	0.20 U	–	–	–	–	–	5.0 U	0.40 U	–	–
	SW quadrant																			
HMW-8IB	SDOT Mercer Parcels,	03/11/20[a]	Unknown	2.0 U	0.20 U	–	–	–	–	0.20 U	0.20 U	–	–	–	–	–	5.0 U	0.40 U	–	–
	SW quadrant																			

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
HMW-9IB	SDOT Mercer Parcels, SW quadrant	03/19/20[a]	Unknown	2.0 U	**9,100**	–	–	–	–	0.20 U	0.20 U	–	–	–	–	–	5.0 U	–	–	–
		01/26/21	Bladder	0.0556 U	**3,360**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.218**	0.508 U		24.2 UJ	0.0345 U	**1.45**	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		06/02/21	Bladder	5.56 U	**3,060**	2.71 U	4.00 U	3.27 U	1.70 U	2.12 U	50.8 U	–	24.2 U	3.45 U	1.40 U	1.18 U	26.5 U	12.4 U	15.3 U	4.72 U
HMW-11IB	SDOT Mercer Parcels, SE quadrant	03/16/20[a]	Unknown	2.0 U	**3.6**	–	–	–	–	0.20 U	0.20 U	–	–	–	–	–	5.0 U	–	–	–
MW111	Alley E of Seattle Roy Aloha Shops	03/23/17	Peristaltic	0.153 U	**1.40**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	**0.306 J**	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/14/17	Bladder	0.153 U	**1.24**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/06/18	Peristaltic	0.153 U	**16.5**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/23/19	Peristaltic	0.153 U	**1.70**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/22/19	Peristaltic	0.153 U	**3.18**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/15/19	Peristaltic	0.153 U	**0.596**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/14/19	Peristaltic	0.153 U	**0.413 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		01/16/20	Bladder	0.153 U	**5.08**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/23/20	Bladder	0.960 U	**24.3**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 UJ	0.749 U	6.00 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 U
		07/06/20	Bladder	0.0556 U	**27.1**	0.0271 U	0.0400 U	0.0327 U	**0.0990 J**	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/02/20	Bladder	0.0556 U	**56.2**	0.0271 U	0.0400 U	0.0327 UJ	**0.103**	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/09/21	Bladder	0.0556 U	**14.5**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.103**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/03/21	Bladder	0.0556 U	**5.80**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.174 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW112	Dexter Ave N ROW, W side	03/22/17	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/16/17	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/12/18	Bladder	0.153 UJ	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 UJ	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		12/21/18	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/22/19	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/16/19	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/21/19	Bladder	0.153 UJ	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/24/20	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 UJ	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		05/07/20	Bladder	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 UJ
		07/27/20	Bladder	0.0556 UJ	0.0276 U	0.0271 U	0.0400 U	0.0327 UJ	0.0170 U	**0.0221 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/17/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/11/21	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		05/14/21	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW126	Alley E of Seattle Roy Aloha Shops	03/28/17	Peristaltic	0.153 U	**0.283 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	**0.466 J**	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/15/17	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	**0.179 J**	0.157 U	0.305 U	0.377 U	**0.245 J**	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	**0.636**
		04/06/18	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/22/19	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/29/19	Peristaltic	0.153 UJ	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		07/18/19	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		10/15/19	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
(dup)		10/15/19	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/14/20	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	**0.162 J**	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	1.09 U	0.143 U	0.162 U
		04/09/20	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
MW126		07/24/20	Peristaltic	0.0556 U	0.0276 U	0.0271 UJ	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 UJ
(continued)		11/09/20	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/10/21	Peristaltic	0.0556 UJ	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/04/21	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	**0.0450 J**	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	**0.203**
	(dup)	05/04/21	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW130	Property,	03/29/17	Bladder	3.06 U	**7,880**	1.95 U	2.34 U	2.54 U	–	3.16 U	3.14 U	6.10 U	7.54 U	2.52 U	1.85 U	2.04 U	21.4 U	3.48 U	2.86 U	3.24 U
	NW quadrant	06/30/17	Bladder	1.53 U	**20,100**	0.976 U	1.17 U	1.27 U	–	1.58 U	1.57 U	3.05 U	3.77 U	1.26 U	0.924 U	1.02 U	10.7 U	1.74 U	1.43 U	1.62 U
	(dup)	06/30/17	Bladder	1.53 U	**21,300**	0.976 U	1.17 U	1.27 U	–	1.58 U	1.57 U	3.05 U	3.77 U	1.26 U	0.924 U	1.02 U	10.7 U	1.74 U	1.43 U	1.62 U
		05/21/18	Bladder	0.153 U	**29,500**	0.0976 U	0.117 U	0.127 U	–	**0.227 J**	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	**0.241 J**	0.143 U	0.162 U
		12/17/18	Bladder	7.65 U	**26,400**	4.88 U	5.85 U	6.35 U	–	7.90 U	7.85 U	15.2 U	18.8 U	6.30 U	4.62 U	5.10 U	53.5 U	8.70 U	7.15 U	8.10 U
		01/31/19	Bladder	0.153 U	**27,700**	0.0976 U	0.117 U	0.127 U	–	**0.279 J**	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	**0.204 J**	0.143 U	0.162 U
	Decommissioned March, 2019																			
MW-132	Property,	09/25/17	Bladder	0.765 U	**196**	0.488 U	0.585 U	0.635 U	–	0.790 U	0.785 U	1.52 U	1.88 U	0.630 U	0.462 U	0.510 U	5.35 U	0.870 U	0.715 U	0.810 U
	SE quadrant	04/26/18	Bladder	0.153 U	**3,300**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/25/18	Peristaltic	0.153 U	**12.1**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 UJ	0.162 U
		12/13/18	Peristaltic	0.153 U	**39.8**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/31/19	Peristaltic	0.153 U	**108**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		03/11/19	Peristaltic	0.153 U	**22.8**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	Decommissioned March, 2019																			
MW-134	Property,	09/22/17	Bladder	0.765 U	**86.2**	0.488 U	0.585 U	0.635 U	–	0.790 U	0.785 U	1.52 U	1.88 U	0.630 U	0.462 U	0.510 U	5.35 U	0.870 U	0.715 U	0.810 U
	NE quadrant	04/16/18	Peristaltic	0.153 U	**0.287 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/25/18	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 UJ	0.162 U
		12/12/18	Bladder	0.153 U	**0.259 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/28/19	Bladder	0.153 U	**0.609**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		03/12/19	Bladder	0.153 U	**0.550**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	Decommissioned March, 2019																			
MW-135	Property,	09/25/17	Bladder	15.3 U	**16,100**	9.76 U	11.7 U	12.7 U	–	15.8 U	15.7 U	30.5 U	37.7 U	12.6 U	9.24 U	10.2 U	107 U	17.4 U	14.3 U	16.2 U
	NE quadrant	04/25/18	Peristaltic	0.153 U	**27,700**	0.0976 U	0.117 U	0.127 U	–	**0.484 J**	0.157 U	0.305 U	0.377 U	**0.145 J**	0.0924 U	0.102 U	1.07 U	**0.469 J**	0.143 U	**0.348 J**
		10/25/18	Peristaltic	153 U	**40,400**	2.44 U	2.92 U	127.00 U	–	3.95 U	3.92 U	7.62 U	9.42 U	3.15 U	2.31 U	2.55 U	26.8 U	4.35 UJ	3.58 UJ	4.05 U
		12/13/18	Peristaltic	7.65 U	**42,100**	4.88 U	5.85 U	6.35 U	–	7.90 U	7.85 U	15.2 U	18.8 U	6.30 U	4.62 U	5.10 U	53.5 U	8.70 U	7.15 U	8.10 U
		01/31/19	Bladder	0.153 U	**37,400**	0.0976 U	0.117 U	0.127 U	–	**0.571 J**	0.157 U	0.305 U	0.377 U	**0.136 J**	0.0924 U	0.102 U	1.07 U	**0.227 J**	0.143 U	**0.376 J**
		03/13/19	Bladder	0.153 U	**37,200**	0.0976 U	0.117 U	0.127 U	–	**0.329 J**	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	**0.327 J**	0.143 U	**0.322 J**
	Decommissioned March, 2019																			
MW-136	Property,	09/25/17	Bladder	0.153 U	**18.7**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	SW quadrant	04/16/18	Submersible	0.153 U	**4.73**	0.0976 U	0.117 U	0.127 U	–	**4.83**	0.157 U	0.305 U	0.377 U	**0.582**	0.0924 U	0.102 U	1.07 U	**1.18 J**	0.143 U	**2.04**
		10/29/18	Bladder	0.153 U	**1.44**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	**0.461**	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		12/13/18	Bladder	0.153 U	**0.962**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		02/01/19	Bladder	0.153 U	**0.851**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		03/12/19	Bladder	0.153 U	**0.330 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	(dup)	03/12/19	Bladder	0.153 U	**0.378 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	Decommissioned March, 2019																			
MW-139	Property,	09/25/17	Bladder	0.153 U	**1.42**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	**1.10 J**	0.174 U	0.143 U	0.162 U
	SE quadrant	04/25/18	Peristaltic	0.153 U	**0.175 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/25/18	Peristaltic	0.153 U	0.454 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 UJ	0.162 U
		12/12/18	Peristaltic	0.153 U	**0.216 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
MW-139		01/28/19	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
(continued)		03/11/19	Peristaltic	0.153 U	**0.187 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	Decommissioned March, 2019																			
MW-143	8th Ave N ROW,	04/30/18	Peristaltic	0.153 U	**129**	0.0976 U	0.117 U	0.127 U	–	**0.212 J**	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	E side	01/29/19	Bladder	0.153 U	**0.241 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		04/24/19	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/19/19	Bladder	0.153 UJ	**0.309 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/16/19	Bladder	0.153 U	**2,510**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/22/20	Bladder	0.153 U	**0.171 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/24/20	Bladder	0.960 U	**0.135 J**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 UJ	0.749 U	6.00 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
		07/29/20	Bladder	0.0556 U	**0.0754 J**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0229 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/24/20	Bladder	0.0556 U	**113**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0610 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/08/21	Peristaltic	2.78 U	**3,260**	1.36 U	2.00 U	1.64 U	0.850 U	1.06 U	25.4 U	–	12.1 U	1.73 U	0.700 U	0.590 U	13.3 U	6.20 U	7.65 U	2.36 U
		05/19/21	Bladder	2.78 U	**4,240**	1.36 U	2.00 U	1.64 U	0.850 U	1.06 U	25.4 U	–	12.1 U	1.73 U	0.700 U	0.590 U	13.3 U	6.20 U	7.65 U	2.36 U
MW-145	8th Ave N ROW,	04/27/18	Bladder	0.153 U	**2.29**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	E side	01/29/19	Bladder	0.153 U	**0.316 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		04/26/19	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	Decommissioned December 2019																			
MW-145R	8th Ave N ROW,	12/16/19	Bladder	0.153 U	**0.193 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	E side	01/21/20	Bladder	0.153 U	**0.230 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/02/20	Bladder	0.153 U	**0.293 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		08/03/20	Bladder	0.0556 U	**0.228**	0.0271 UJ	0.0400 U	0.0327 U	0.0170 U	**0.0460 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 UJ
		11/23/20	Bladder	0.0556 U	**0.151**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		02/05/21	Peristaltic	0.0556 U	**0.0680 J**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.300**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/12/21	Bladder	0.0556 U	**0.0760 J**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-147	Roy St ROW,	05/01/18	Bladder	0.153 U	**399**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	S side	01/22/19	Bladder	0.153 U	**1,230**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/23/19	Bladder	0.153 U	**322**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/18/19	Bladder	0.153 U	**219**	0.0976 U	0.117 U	0.127 U	–	3.16 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	**5.94 J**	0.143 U	3.24 U
	(dup)	07/18/19	Bladder	0.153 U	**286**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/14/19	Bladder	0.153 U	**597**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		01/24/20	Bladder	3.83 U	**1,100**	2.44 U	2.93 U	3.18 UJ	–	3.95 U	3.93 U	7.63 U	9.43 U	3.15 U	2.31 U	2.55 U	26.8 U	4.35 U	3.58 U	4.05 U
		04/29/20	Bladder	24.0 U	**2,410**	2.78 U	3.05 U	9.35 U	–	3.43 U	8.43 U	18.7 U	13.9 UJ	2.63 U	2.63 U	2.53 U	10.7 UJ	4.35 U	3.93 U	2.48 U
		07/09/20	Bladder	0.0556 U	**2,220**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/10/20	Bladder	5.56 UJ	**3,740**	2.71 U	4.00 U	3.27 U	1.70 UJ	2.12 U	50.8 U	–	24.2 U	3.45 U	1.40 UJ	1.18 U	26.5 U	12.4 U	15.3 U	4.72 U
	(split)	11/10/20	Bladder	5,000 U	**3,500**	500 U	500 U	500 U	–	500 U	500 U	2,500 U	–	500 U	–	500 U	2,500 U	500 U	–	500 U
		02/09/21	Bladder	2.78 U	**1,750**	1.36 U	2.00 U	1.64 U	0.850 U	1.06 U	25.4 U	–	12.1 U	1.73 U	0.700 U	0.590 U	13.3 U	6.20 U	7.65 U	2.36 U
		05/04/21	Bladder	5.56 U	**1,300**	2.71 U	4.00 U	3.27 U	1.70 U	2.12 U	50.8 U	–	24.2 U	3.45 U	1.40 U	1.18 U	26.5 U	12.4 U	15.3 U	4.72 U
MW-148	Roy St ROW,	05/01/18	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
(dup)	S side	05/01/18	Bladder	0.153 U	**0.216 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/23/19	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/26/19	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/22/19	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/16/19	Bladder	0.153 UJ	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
MW-148 (continued)		01/20/20	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/30/20	Bladder	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
		07/15/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/11/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-150	Property, NW quadrant	04/10/18	Peristaltic	0.153 U	**9,710**	0.0976 U	0.117 U	0.127 U	–	39.5 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	43.5 U	0.143 U	0.162 UJ
		10/25/18	Peristaltic	76.5 U	**17,700**	0.0976 U	0.117 U	63.5 U	–	**0.226 J**	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	**0.209 J**	0.143 UJ	0.162 U
		12/12/18	Peristaltic	0.153 U	**32,800**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	**1.24 J**	0.174 U	0.143 U	0.162 U
		01/29/19	Peristaltic	15.3 U	**18,100**	9.76 U	11.7 U	12.7 U	–	15.8 U	15.7 U	30.5 U	37.7 U	12.6 U	9.24 U	10.2 U	107 U	17.4 UJ	14.3 U	16.2 U
		03/13/19	Peristaltic	0.153 U	**15,000**	0.0976 U	0.117 U	0.127 U	–	**0.185 J**	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	Decommissioned March, 2019																			
MW-152	Property, SW quadrant	04/10/18	Peristaltic	3.06 U	**35,300**	1.95 U	2.34 U	2.54 U	–	**3.27 J**	3.14 U	6.10 UJ	7.54 U	2.52 U	1.85 U	2.04 U	21.4 U	3.48 U	2.86 U	3.24 UJ
		10/26/18	Peristaltic	306 U	**73,000**	4.88 U	5.85 U	254.00 U	–	7.90 U	7.85 U	15.2 U	18.8 U	6.30 U	4.62 U	5.10 U	53.5 U	8.70 UJ	7.15 UJ	8.10 U
		12/14/18	Peristaltic	3.82 U	**77,100 J+**	2.44 U	2.92 U	3.18 U	–	3.95 U	3.92 U	7.62 U	9.42 U	3.15 U	2.31 U	2.55 U	26.8 U	4.35 U	3.58 U	4.05 U
		01/31/19	Peristaltic	0.153 U	**58,400**	0.0976 U	0.117 U	0.127 U	–	**0.342 J**	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	**0.266 J**	0.143 U	**0.281 J**
		03/12/19	Peristaltic	3.82 U	**127,000**	2.44 U	2.92 U	3.18 U	–	3.95 U	3.92 U	7.62 U	9.42 U	3.15 U	2.31 U	2.55 U	26.8 U	4.35 U	3.58 U	4.05 U
	Decommissioned March, 2019																			
MW-157	8th Ave N ROW, E side	04/26/18	Peristaltic	0.153 U	**10.4**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/24/19	Peristaltic	0.153 U	**4,250**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/24/19	Peristaltic	0.153 U	**3,550**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/22/19	Bladder	0.153 U	**4,530**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/16/19	Bladder	0.153 UJ	**0.188 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/20/20	Bladder	0.153 U	**2,040**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/24/20	Bladder	19.2 UJ	**1,040**	2.22 U	2.44 U	7.48 U	–	2.74 U	6.74 UJ	15.0 UJ	11.1 U	2.10 U	2.10 UJ	2.02 U	8.60 U	3.48 U	3.14 U	1.99 U
		07/15/20	Bladder	1.11 U	**888**	0.542 U	0.800 U	0.654 U	0.340 U	0.424 U	10.2 U	–	4.84 U	0.690 U	0.280 U	0.236 U	5.30 U	2.48 U	3.06 U	0.944 U
		11/23/20	Bladder	1.11 U	**2,770**	0.542 U	0.800 U	0.654 U	0.340 U	0.424 U	10.2 U	–	4.84 U	0.690 U	0.280 U	0.236 U	5.30 U	2.48 UJ	3.06 U	0.944 U
MW-190	Valley Street ROW, S side	10/14/19	Bladder	0.153 U	**7.78**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		01/23/20	Bladder	0.153 U	**0.389 J**	0.0976 U	0.117 U	0.127 UJ	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/02/20	Bladder	0.153 U	**2.13**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		08/04/20	Bladder	0.0556 U	**1.74**	0.0271 UJ	0.0400 U	0.0327 U	0.0170 U	**0.0330 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 UJ
		11/18/20	Bladder	0.0556 U	**21.8**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		02/03/21	Bladder	0.0556 U	**12.5**	0.0271 U	0.0400 U	0.0327 UJ	0.0170 U	**0.0450 J**	0.508 UJ	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		05/14/21	Bladder	0.0556 U	**8.12**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0330 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-303	Dexter Ave N ROW, E side	10/21/19	Submersible	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/24/20	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 UJ	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		05/07/20	Bladder	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 UJ
		07/27/20	Bladder	0.0556 UJ	0.0276 U	0.0271 U	0.0400 U	0.0327 UJ	0.0170 U	**0.0263 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/17/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/18/21	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-307	Roy St ROW, S side	10/11/19	Bladder	0.153 U	**0.935**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		01/15/20	Bladder	0.153 U	**0.172 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/28/20	Bladder	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 UJ	0.105 U	0.105 U	0.101 U	0.430 UJ	0.174 U	0.157 U	0.0993 U
		07/29/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
MW-307		11/06/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
(continued)		05/18/21	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-309	Alley E of Seattle	10/14/19	Peristaltic	0.153 U	**1.47**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
	Roy Aloha Shops	01/16/20	Peristaltic	0.153 U	**0.487 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/08/20	Peristaltic	0.153 U	**0.231 J**	0.0976 U	0.117 U	0.127 U	–	**0.239 J**	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/06/20	Peristaltic	0.0556 U	**0.170**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0640 J**	0.508 U	–	0.242 U	**0.0490 J**	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/06/20	Peristaltic	0.0556 U	**0.187**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0388 J**	0.508 U	–	0.242 U	**0.0465 J**	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/04/21	Peristaltic	0.0556 U	**0.212**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-311	Alley E of Seattle	10/10/19	Peristaltic	0.153 U	**173**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	Roy Aloha Shops	01/14/20	Peristaltic	0.153 U	**75.0**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		04/23/20	Bladder	0.960 U	**45.8**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 UJ	0.749 U	6.00 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
		07/16/20	Bladder	0.0556 U	**5.24**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/04/20	Bladder	0.0556 U	**2.66**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0319 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/03/21	Peristaltic	0.0556 U	**0.981**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0510 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-314	Alley E of Seattle	10/10/19	Bladder	0.153 U	**491**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	Roy Aloha Shops	01/15/20	Bladder	0.153 U	**596**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
(dup)		01/15/20	Bladder	0.153 U	**569**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/22/20	Bladder	9.60 U	**3,190**	1.11 U	1.22 U	3.74 U	–	1.37 U	3.37 U	7.49 U	60.0 U	1.05 U	1.05 U	1.01 U	4.30 U	**3.69 J**	1.57 U	0.993 U
		07/16/20	Bladder	5.56 U	**4,020**	2.71 U	4.00 U	3.27 U	1.70 U	2.12 U	50.8 U	–	24.2 U	3.45 U	1.40 U	1.18 U	26.5 U	12.4 U	15.3 U	4.72 U
		11/04/20	Bladder	5.56 U	**4,240**	2.71 U	4.00 U	3.27 U	**16.1**	2.12 U	50.8 U	–	24.2 U	3.45 U	1.40 U	1.18 U	**89.3 J**	12.4 U	15.3 U	4.72 U
		05/03/21	Bladder	2.78 U	**977**	1.36 U	2.00 U	1.64 U	0.850 U	1.06 U	25.4 U	–	12.1 U	1.73 U	0.700 U	0.590 U	13.3 U	6.20 U	7.65 U	2.36 U
MW-316	Mercer St ROW,	10/02/19	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	N side	01/16/20	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/21/20	Bladder	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	6.00 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
		07/24/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/02/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 UJ	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/17/21	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-318	9th Ave N ROW,	10/08/19	Bladder	0.153 U	**6.52**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	W side	01/16/20	Peristaltic	0.153 U	**9.86**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/27/20	Bladder	0.960 U	**2.08**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 UJ	0.749 U	6.00 U	0.105 U	**0.243 J**	**0.250 J**	0.430 U	0.174 U	0.157 U	0.0993 U
		07/30/20	Bladder	0.0556 U	**0.525 J**	0.0271 U	0.0400 U	0.0327 U	**0.569**	**0.0775 J**	0.508 U	–	0.242 UJ	0.0345 U	**0.199**	**0.116**	0.265 U	0.124 U	0.153 U	0.0472 U
		11/12/20	Bladder	0.0556 U	**0.499**	0.0271 U	0.0400 U	0.0327 U	**1.20 J+**	0.0212 U	0.508 U	–	0.242 U	0.0345 U	**0.330**	**0.270**	0.265 U	0.124 U	0.153 U	0.0472 U
		05/19/21	Peristaltic	0.0556 U	**0.570**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	**0.303**	**0.0810**	0.265 U	0.124 U	0.153 U	0.0472 U
MW-322	9th Ave N ROW,	10/07/19	Peristaltic	0.153 U	**497**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	**0.112 J**	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	W side	01/21/20	Peristaltic	0.153 U	**2,740**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/29/20	Bladder	96.0 U	**1,510**	11.1 U	12.2 U	37.4 U	–	13.7 U	33.7 U	74.9 U	55.4 UJ	10.5 U	10.5 U	10.1 U	43.0 UJ	17.4 U	15.7 U	9.93 U
		07/07/20	Bladder	0.556 U	**547**	0.271 U	0.400 U	0.327 U	**0.400 J**	0.212 U	5.08 U	–	2.42 U	0.345 U	**0.250 J**	**0.400 J**	2.65 U	1.24 U	1.53 U	0.472 U
		11/24/20	Bladder	0.556 U	**257**	0.271 U	0.400 U	0.327 U	0.170 U	0.212 U	5.08 U	–	2.42 U	0.345 U	0.140 U	0.118 U	2.65 U	1.24 U	1.53 U	0.472 U
		05/19/21	Peristaltic	0.556 U	**496**	0.271 U	0.400 U	0.327 U	0.170 U	0.212 U	5.08 U	–	2.42 U	0.345 U	**0.520**	**1.18**	2.65 U	1.24 U	1.53 U	0.472 U
MW-334	900 Roy St,	04/24/20	Bladder	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 UJ	0.749 U	6.00 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
	S end	07/07/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	16	0.44	80	1,600	1,600	700	0.56	480	–	800	–	24	5	160	400	800
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				150	–	–	–	6	–	1,200	–	8	–	720	–	600	4,800	8.9	–	2,300
MW-334		11/05/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
(continued)		05/13/21	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-335	Mercer St ROW,	05/01/20	Bladder	0.960 U	**138**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 U
	N side	07/08/20	Bladder	0.556 U	**89.2**	0.271 U	0.400 U	0.327 U	0.170 U	0.212 U	5.08 U	–	2.42 U	0.345 U	0.140 U	0.118 U	2.65 U	1.24 U	1.53 U	0.472 U
		11/02/20	Bladder	0.556 U	**1,160**	0.271 U	0.400 U	0.327 UJ	0.170 U	0.212 U	5.08 U	–	2.42 U	0.345 U	0.140 U	0.118 U	2.65 U	1.24 U	1.53 U	0.472 U
		02/10/21	Bladder	0.556 UJ	**1,350**	0.271 U	0.400 U	0.327 U	0.170 U	0.212 U	5.08 U	–	2.42 U	0.345 U	0.140 U	0.118 U	2.65 U	1.24 U	1.53 U	0.472 U
		05/26/21	Peristaltic	0.556 U	**1,490**	0.271 U	0.400 U	0.327 U	0.170 UJ	0.212 U	5.08 U	–	2.42 U	0.345 U	0.140 UJ	0.118 U	2.65 U	1.24 U	1.53 UJ	0.472 U
MW-338	Lake Union Park,	05/07/20	Peristaltic	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 UJ
	N end	07/23/20	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0720 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/10/20	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/04/21	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-340	Lake Union Park,	05/12/20	Peristaltic	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 UJ	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 U
	S end	07/17/20	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/09/20	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/13/21	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-345	SDOT Mercer Parcels,	06/01/21	Bladder	0.0556 U	**13.9**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
MW-346	SDOT Mercer Parcels,	06/02/21	Bladder	0.0556 U	**18.1**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
(dup)	NW quadrant	06/02/21	Bladder	0.0556 U	**18.3**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-347	SDOT Mercer Parcels,	06/01/21	Bladder	0.0556 U	**123**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
MW-348	SDOT Mercer Parcels,	06/01/21	Bladder	0.0556 U	**104**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
MW-349	SDOT Mercer Parcels,	06/01/21	Bladder	0.0556 U	**7.23**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0400 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
MW-350	SDOT Mercer Parcels,	06/01/21	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**11.5**	0.508 U	–	0.242 U	**2.67**	0.0140 U	0.0118 U	0.265 U	**4.60 J-**	**0.756**	**5.12**
W-MW-01	8th Ave N ROW,	03/30/17	Peristaltic	0.153 U	**0.491 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	W side	06/19/17	Bladder	0.153 U	**0.320 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 UJ	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		04/13/18	Bladder	0.153 U	**1.31**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/29/18	Bladder	0.153 U	**0.629**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	**0.659**	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		12/13/18	Bladder	0.153 U	**0.538**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/25/19	Bladder	0.153 U	**0.459 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		03/11/19	Bladder	0.153 U	**0.396 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/25/19	Bladder	0.153 U	**0.572**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	**0.211 J**	0.143 U	0.162 U
		07/23/19	Bladder	0.153 U	**0.547**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	**0.211 J**	0.143 U	0.162 U
		10/15/19	Bladder	0.153 U	**0.408 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/27/20	Bladder	0.153 U	**0.553**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/03/20	Bladder	0.153 U	**0.588**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/31/20	Bladder	0.0556 U	**0.431 J**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 UJ	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/24/20	Bladder	0.0556 U	**0.451**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		02/03/21	Bladder	0.0556 U	**0.495**	0.0271 U	0.0400 U	0.0327 UJ	0.0170 U	0.0212 U	0.508 UJ	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		05/17/21	Bladder	0.0556 U	**0.367**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
W-MW-02	8th Ave N ROW,	03/27/17	Peristaltic	0.153 U	**33.0**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	W side	06/19/17	Bladder	0.153 U	**18.2**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 UJ	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
W-MW-02		06/12/18	Bladder	0.153 U	**4.72**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
(continued)		10/26/18	Peristaltic	0.153 U	**2.01**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 UJ	0.162 U
(dup)		10/26/18	Peristaltic	0.153 U	**2.11** J+	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	**0.191 J**	0.143 U	0.162 U
		12/12/18	Peristaltic	0.153 U	**1.80**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/25/19	Peristaltic	0.153 U	**1.83**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		03/11/19	Peristaltic	0.153 U	**2.41**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/23/19	Peristaltic	0.153 U	**672**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/23/19	Bladder	0.153 U	**3.30**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/18/19	Bladder	0.153 U	**2.07**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 UJ	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/28/20	Bladder	0.153 U	**1.52**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/01/20	Bladder	0.153 UJ	**1.44**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		07/31/20	Bladder	0.0556 U	**1.39** J	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 UJ	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
Deep Water-Bearing Zone																				
FMW-129	SDOT Mercer Parcels,	04/10/17	Peristaltic	0.765 U	**1,420**	0.488 U	0.585 U	0.635 U	–	0.790 U	0.785 U	1.52 U	18.8 U	0.630 U	0.462 U	0.510 U	5.35 U	**1.42 J**	0.715 U	0.810 U
	NE quadrant	06/23/17	Bladder	0.153 U	**474**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	5.35 U	0.174 U	0.143 U	0.162 U
		05/01/19	Peristaltic	0.153 UJ	**372**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		07/16/19	Bladder	0.153 U	**272**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/21/19	Peristaltic	0.153 U	**350**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		11/12/19[o]	Unknown	–	**340**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/14/20	Bladder	1.53 U	**385**	0.976 U	1.17 U	1.27 U	–	1.58 U	1.57 U	3.05 U	3.77 U	1.26 U	0.924 U	1.02 U	10.7 U	1.74 UJ	1.43 U	1.62 U
(split)		01/14/20[o]	Bladder	–	**290**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/18/20[o]	Unknown	–	**310**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		03/25/20[o]	Unknown	–	**290**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/27/20[o]	Unknown	–	**190**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/06/20	Bladder	0.960 U	**157**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 U
		05/19/20[o]	Unknown	–	**120**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/10/20	Bladder	0.0556 U	**92.5**	0.0271 U	0.0400 U	0.0327 UJ	0.0170 U	0.0212 U	0.508 UJ	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		07/28/20[o]	Unknown	–	**100**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		09/17/20[o]	Unknown	–	**70**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/10/20	Bladder	0.0556 U	**58.8**	0.0271 U	0.0400 U	0.0327 U	**0.0809 J**	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		12/03/20[o]	Unknown	–	**57**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/10/21	Peristaltic	0.0556 UJ	**42.5**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
(split)		02/10/21[o]	Peristaltic	–	**31**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/26/21	Bladder	0.0556 U	**517**	0.0271 U	0.0400 U	0.0327 U	0.0170 UJ	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 UJ	0.0118 U	0.265 U	0.124 U	0.153 UJ	0.0472 U
(dup)		05/26/21	Bladder	0.0556 U	**526**	0.0271 U	0.0400 U	0.0327 U	0.0170 UJ	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 UJ	0.0118 U	0.265 U	0.124 U	0.153 UJ	0.0472 U
FMW-131	Block 37,	03/24/17	Peristaltic	0.153 U	**45.6**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.273 U	0.143 U	0.162 U
	SE quadrant	06/23/17	Bladder	0.153 U	**3.61**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		12/18/17[b]	Unknown	–	**0.61**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/22/19	Peristaltic	0.153 U	**10.8**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/21/19	Peristaltic	0.153 UJ	**10.5**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/22/20	Peristaltic	0.153 U	**15.1**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		04/29/20	Peristaltic	0.960 U	**13.9**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 UJ	0.105 U	0.105 U	0.101 U	0.430 UJ	0.174 U	0.157 U	0.0993 U
		07/30/20	Bladder	0.0556 U	**6.73** J	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 UJ	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		08/26/20[o]	Unknown	–	**6.5**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
FMW-131 (continued)		11/19/20	Bladder	0.0556 U	**7.91**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		12/04/20[v]	Unknown	–	**3.5**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/11/21[o]	Unknown	–	**0.27**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/12/21	Peristaltic	0.0556 U	**7.89**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.172**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		05/13/21	Peristaltic	0.0556 U	**9.83**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	**0.0230 J**	**0.0170 J**	0.265 U	0.124 U	0.153 U	0.0472 U
FMW-137	Alley E of Block 38 West	11/20/18[v]	Unknown	–	**1.2**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		12/28/18[v]	Unknown	–	**1.1**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/06/19[v]	Unknown	–	**1.3**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/08/19[v]	Unknown	–	**1.3**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		10/14/19[o]	Unknown	–	**1.1**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/06/19	Peristaltic	0.153 U	**1.27**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		11/11/19[v]	Unknown	–	**1.3**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/22/20	Peristaltic	0.153 U	**1.99**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		05/06/20	Bladder	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
		07/31/20	Bladder	0.0556 U	**0.0343 J**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.137**	0.508 U	–	0.242 UJ	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/24/20	Bladder	0.0556 U	**0.0540 J**	0.0271 U	0.0400 U	0.0327 U	**0.0460 J**	0.0480 U	0.508 U	–	0.242 U	**0.119**	0.0140 U	0.0118 U	0.265 U	**0.658 J-**	**0.315 J**	0.0472 U
		02/12/21	Bladder	0.0556 U	**2.66**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0800 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		06/02/21	Peristaltic	0.0556 U	**2.99**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	**0.0420 J+**	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
FMW-138	Alley E of Block 38 West	11/20/18[v]	Unknown	–	**0.29**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		12/28/18[v]	Unknown	–	**0.34**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/6/19[v]	Unknown	–	**0.38**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/8/19[o]	Unknown	–	**0.34**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		10/14/19[o]	Unknown	–	**0.33**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/11/19[v]	Unknown	–	**0.37**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
FMW-3D	Terry Ave N ROW, E side	03/24/17	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/23/17	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
FMW-140	900 Roy St, S end	07/17/19[v]	Unknown	–	**280**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		10/31/19	Peristaltic	0.153 U	**0.160 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	**0.327 J**	**0.200 J**	1.07 UJ	0.174 U	0.143 UJ	0.162 U
		11/12/19[v]	Unknown	–	**310**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/14/20[o]	Unknown	–	**340**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/22/20	Peristaltic	0.153 U	**406**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	**0.492 J**	**0.453 J**	1.07 U	0.174 UJ	0.143 U	0.162 U
		02/18/20[v]	Unknown	–	**280**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		03/25/20[v]	Unknown	–	**100**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/27/20[v]	Unknown	–	**33**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/28/20	Bladder	0.960 U	**27.1**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	**0.479 J**	**0.333 J**	0.430 U	0.174 U	0.157 U	0.0993 U
		05/19/20[v]	Unknown	–	**16**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/07/20	Bladder	0.0556 U	**8.76**	0.0271 U	0.0400 U	0.0327 U	**0.458**	0.0212 U	0.508 U	–	0.242 U	0.0345 U	**0.507**	**0.685**	0.265 U	0.124 U	0.153 U	0.0472 U
		07/29/20[v]	Unknown	–	**9.7**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		09/17/20[o]	Unknown	–	**25**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/13/20	Bladder	0.0556 UJ	**6.15**	0.0271 U	0.0400 U	0.0327 U	**0.394**	0.0212 U	0.508 U	–	0.242 U	0.0345 U	**0.189 J-**	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		12/04/20[v]	Unknown	–	**3.3**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/10/21[v]	Unknown	–	**0.72**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/18/21	Peristaltic	0.0556 U	**2.12**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	**0.299**	**0.0330 J**	0.265 U	0.124 U	0.153 U	0.0472 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
GEI-2	Block 37, NW quadrant	03/24/17	Peristaltic	0.153 U	**2.25**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.271 U	0.143 U	0.162 U
		06/23/17	Bladder	0.153 U	**16.3**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	**0.130 J**	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		12/29/18[o]	Unknown	–	**6.7**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/22/19	Peristaltic	0.153 U	**11.5**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	**0.217 J**	**0.154 J**	1.07 U	0.174 U	0.143 U	0.162 U
		07/16/19	Peristaltic	0.153 U	**1.37**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/21/19	Peristaltic	0.153 UJ	**20.1**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	**0.194 J**	**0.252 J**	1.07 U	0.174 U	0.143 U	0.162 U
		11/11/19[o]	Unknown	–	**18**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/14/20[o]	Unknown	–	**2.0**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/22/20	Peristaltic	0.153 U	**0.308 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		02/17/20[o]	Unknown	–	**5.6**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		03/25/20[o]	Unknown	–	**4.3**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/27/20[o]	Unknown	–	**3.2**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/29/20	Peristaltic	0.960 U	**4.49**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 UJ	0.105 U	0.105 U	0.101 U	0.430 UJ	0.174 U	0.157 U	0.0993 U
		05/19/20[o]	Unknown	–	**2.7**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		06/29/20[o]	Unknown	–	**1.6**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/29/20[o]	Unknown	–	**1.3**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/30/20	Bladder	0.0556 U	**1.38 J**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 UJ	0.0345 U	**0.0492**	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		08/26/20[o]	Unknown	–	0.20 U	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		09/17/20[o]	Unknown	–	**1.0**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/19/20	Bladder	0.0556 U	**0.997**	0.0271 U	0.0400 U	0.0327 U	**0.103**	0.0212 U	0.508 U	–	0.242 U	0.0345 U	**0.0670 J+**	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		12/04/20[o]	Unknown	–	**0.52**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/11/21[o]	Unknown	–	**0.43**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/12/21	Peristaltic	0.0556 U	**0.711**	0.0271 U	0.0400 U	0.0327 U	**0.0640 J**	**0.216**	0.508 U	–	0.242 U	0.0345 U	**0.0570**	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		05/13/21	Peristaltic	0.0556 U	**0.379**	0.0271 U	0.0400 U	0.0327 U	**0.0520 J**	0.0212 U	0.508 U	–	0.242 U	0.0345 U	**0.0560**	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
HMW-1D	SDOT Mercer Parcels, NE quadrant	03/25/19[a]	Peristaltic	1.0 U	**410**	1.0 U	1.0 U	–	–	1.0 U	1.0 U	–	–	1.0 U	–	5.0 U	1.0 U	1.0 U	1.0 U	1.0 U
		03/09/20[a]	Unknown	200 U	**910**	–	–	–	–	20 U	20 U		–	–	–	–	500 U	–	–	–
HMW-2D	SDOT Mercer Parcels, NE quadrant	03/25/19[a]	Peristaltic	1.0 U	1.0 U	1.0 U	1.0 U	–	–	1.0 U	1.0 U	–	–	1.0 U	–	5.0 U	1.0 U	1.0 U	1.0 U	1.0 U
		03/12/20[a]	Unknown	2.0 U	**1.1**	–	–	–	–	0.20 U	0.20 U		–	–	–	–	5.0 U	–	–	–
HMW-3D	SDOT Mercer Parcels, NW quadrant	03/25/19[a]	Peristaltic	1.0 U	1.0 U	1.0 U	1.0 U	–	–	1.0 U	1.0 U	–	–	1.0 U	–	5.0 U	1.0 U	1.0 U	1.0 U	1.0 U
		03/13/20[a]	Unknown	2.0 U	0.20 UJ	–	–	–	–	0.20 U	0.20 U		–	–	–	–	5.0 U	–	–	–
HMW-6D	SDOT Mercer Parcels, SW quadrant	03/16/20[a]	Unknown	2.0 U	0.20 U	–	–	–	–	0.20 U	0.20 U	–	–	–	–	–	5.0 U	0.40 U	–	–
HMW-9D	SDOT Mercer Parcels, SW quadrant	03/17/20[a]	Unknown	2.0 U	**5.1**	–	–	–	–	0.20 U	0.20 U	–	–	–	–	–	5.0 U	–	–	–
HMW-10D	SDOT Mercer Parcels, SE quadrant	03/16/20[a]	Unknown	2.0 U	0.20 U	–	–	–	–	0.20 U	0.20 U	–	–	–	–	–	5.0 U	–	–	–
MW102	Valley Street ROW, S side	03/29/17	Bladder	0.153 U	**0.223 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/15/17	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/25/18	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/24/19	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		05/01/19	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/18/19	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	**2.11 J**	0.143 U	0.162 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	16	0.44	80	1,600	1,600	700	0.56	480	–	800	–	24	5	160	400	800
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				150	–	–	–	6	–	1,200	–	8	–	720	–	600	4,800	8.9	–	2,300
MW102		11/14/19	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
(continued)		01/23/20	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 UJ	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
(dup)		01/23/20	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 UJ	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/02/20	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		08/04/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 UJ	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
(dup)		08/04/20	Bladder	0.0556 U	0.0276 U	0.0271 UJ	0.0400 U	0.0327 U	0.0170 U	**0.0340 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 UJ
		11/18/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		02/03/21	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 UJ	0.0170 U	**0.0390 J**	0.508 UJ	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		05/14/21	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW103	Alley E of Seattle	03/23/17	Peristaltic	0.153 U	**240**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	Roy Aloha Shops	06/14/17	Bladder	0.153 U	**120**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/06/18	Peristaltic	0.153 U	**32.4**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/23/19	Peristaltic	0.153 U	**11.4**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/22/19	Peristaltic	0.153 U	**88.0**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/15/19	Peristaltic	0.153 U	**118**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/14/19	Peristaltic	0.153 U	**91.7**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		01/16/20	Bladder	0.153 U	**40.6**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/23/20	Bladder	0.960 U	**12.8**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 UJ	0.749 U	6.00 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 U
(dup)		04/23/20	Bladder	0.960 U	**12.9**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 UJ	0.749 U	6.00 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
		07/06/20	Bladder	0.0556 U	**4.21**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/02/20	Bladder	0.0556 U	**2.75**	0.0271 U	0.0400 U	0.0327 UJ	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/10/21	Bladder	0.0556 UJ	**9.05**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0450 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/03/21	Bladder	0.0556 U	**34.0**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW104	8th Ave N ROW,	03/30/17	Peristaltic	0.153 U	**3.97**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.217 U	0.143 U	0.162 U
	W side	06/30/17	Bladder	0.153 U	**1.54**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/09/18	Peristaltic	0.153 U	**176**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/26/18	Bladder	0.153 U	**71.2**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 UJ	0.162 U
		12/13/18	Bladder	0.153 U	**48.3**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		02/01/19	Bladder	0.153 U	**30.6**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		03/13/19	Bladder	0.153 U	**83.0**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/23/19	Bladder	0.153 U	**162**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/22/19	Bladder	0.153 U	**160**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/18/19	Bladder	0.153 U	**16.3**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 UJ	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/29/20	Bladder	0.153 U	**44.6**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/01/20	Bladder	0.153 UJ	**21.1**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		07/31/20	Bladder	0.0556 U	**12.8 J**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 UJ	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
(dup)		07/31/20	Bladder	0.0556 U	**12.6 J**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 UJ	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/17/20	Bladder	0.0556 U	**28.6**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/10/21	Bladder	0.0556 UJ	**43.9**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.225**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW105	Roy Street ROW,	04/21/17	Bladder	0.153 U	**0.155 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	S side	06/14/17	Bladder	0.153 U	**0.180 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	**1.41 J**	0.143 U	0.162 U
		04/11/18	Bladder	0.153 UJ	**1.67**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 UJ	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/23/19	Bladder	0.153 U	**1.51**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/23/19	Bladder	0.153 U	**0.917**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
MW105		07/17/19	Bladder	0.153 U	**0.891**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
(continued)		10/22/19	Bladder	0.153 U	**0.945**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
(dup)		10/22/19	Bladder	0.153 U	**0.720**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/20/20	Bladder	0.153 U	**1.38**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		05/12/20	Bladder	0.960 U	**0.805**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 UJ	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 U
		07/27/20	Bladder	0.0556 UJ	**1.56**	0.0271 U	0.0400 U	0.0327 UJ	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/17/20	Peristaltic	0.0556 U	**4.83**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/11/21	Bladder	0.0556 UJ	**6.78**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0690 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		06/07/21	Bladder	0.0556 U	**11.5**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0490 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW106	SDOT Mercer Parcels, NW quadrant	04/14/17	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/30/17	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		05/04/18	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	–	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.305 U
		04/26/19	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/19/19	Bladder	0.153 UJ	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/18/19	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 UJ	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/14/20	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		05/06/20	Bladder	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
(dup)		05/06/20	Bladder	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
		07/10/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 UJ	0.0472 U
		11/10/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
(dup)		11/10/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/12/21	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
(dup)		02/12/21	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		05/13/21	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW113	9th Ave N ROW, W side	03/22/17	Peristaltic	0.153 U	**7,280**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/16/17	Bladder	0.153 U	**4,750**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/11/18	Peristaltic	0.153 UJ	**3,720**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 UJ	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/30/19	Peristaltic	0.765 U	**6,330**	0.488 U	0.585 U	0.635 U	–	0.790 U	0.785 U	1.52 U	1.88 U	0.630 U	0.462 U	0.510 U	5.35 U	0.870 UJ	0.715 U	0.810 U
		02/07/19	Peristaltic	0.153 U	**6,990**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/17/19	Peristaltic	0.153 U	**4,940**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		10/22/19	Peristaltic	0.153 U	**1,420**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		11/11/19[p]	Peristaltic	–	**8,200**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/14/20	Bladder	1.53 U	**10,300**	0.976 U	1.17 U	1.27 U	–	1.58 U	1.57 U	3.05 U	3.77 U	1.26 U	0.924 U	1.02 U	10.7 U	1.74 UJ	1.43 U	1.62 U
(split)		01/14/20[v]	Peristaltic	–	**8,000**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/18/20[v]	Unknown	–	**9,600**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		03/24/20[v]	Unknown	–	**4,100**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		04/27/20	Peristaltic	96.0 U	**4,320**	11.1 U	12.2 U	37.4 U	–	13.7 U	33.7 UJ	74.9 U	600.0 U	10.5 U	10.5 U	10.1 U	43.0 U	17.4 U	15.7 U	9.93 U
(split)		04/27/20[v]	Peristaltic	–	**3,500**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/19/20[v]	Unknown	–	**3,700**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/28/20	Bladder	96.0 U	**3,100**	11.1 U	12.2 U	37.4 U	–	13.7 U	33.7 U	74.9 U	55.4 UJ	10.5 U	10.5 U	10.1 U	43.0 U	17.4 U	15.7 U	9.93 U
(split)		07/28/20[v]	Unknown	–	**2,300**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		09/17/20[p]	Unknown	–	**1,900**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/24/20	Bladder	5.56 U	**1,290**	2.71 U	4.00 U	3.27 U	1.70 U	2.12 U	50.8 U	–	24.2 U	3.45 U	1.40 U	1.18 U	26.5 U	12.4 U	15.3 U	4.72 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
MW113		12/03/20[p]	Unknown	–	**540**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(continued)		02/10/21	Peristaltic	0.0556 U	**39.1**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
(split)		02/10/21[o]	Peristaltic	–	**26**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/25/21	Peristaltic	0.0556 U	**1,380**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	**0.0810**	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW122	Alley E of Seattle Roy Aloha Shops	03/28/17	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/14/17	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	**0.382 J**
		04/06/18	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/14/19	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		01/17/20	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 UJ	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/07/20	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/24/20	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/06/20	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/03/21	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW123	Westlake Ave N ROW, W side	04/01/17	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	**0.141 J**	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/24/17	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/14/18	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/18/19	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 UJ	**0.163 J**	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/22/20	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	**0.144 J**	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		05/05/20	Peristaltic	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 U
		07/30/20	Peristaltic	0.0556 U	0.0276 UJ	0.0271 U	0.0400 U	0.0327 U	**0.213**	**0.141**	0.508 U	–	0.242 UJ	0.0345 U	**0.0318 J**	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/12/20	Peristaltic	0.0556 UJ	0.0276 U	0.0271 U	0.0400 U	0.0327 U	**0.112**	**0.0217 J**	0.508 U	–	0.242 U	0.0345 U	**0.0222 J**	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/26/21	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 UJ	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 UJ	0.0118 U	0.265 U	0.124 U	0.153 UJ	0.0472 U
MW124	Valley Street ROW, S side	03/29/17	Bladder	0.153 U	**0.661**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
(dup)		03/29/17	Bladder	0.153 U	**0.600**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/15/17	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/13/18	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/11/19	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		01/30/20	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/03/20	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		08/03/20	Bladder	0.0556 U	0.0276 UJ	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.102**	0.508 U	–	0.242 UJ	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/18/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		06/08/21	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW128	Westlake Ave N ROW, E side	03/29/17	Peristaltic	0.153 U	**7.16**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		06/21/17	Bladder	0.153 U	**109**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 UJ	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		04/09/18	Peristaltic	0.153 U	**3.07**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		12/30/18[v]	Unknown	–	**5.0**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		07/18/19	Peristaltic	0.153 U	**1.88**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	**0.161 J**	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		10/11/19	Peristaltic	0.153 U	**0.619**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
(dup)		10/11/19	Peristaltic	0.153 U	**0.841**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	**0.137 J**	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		11/11/19[v]	Peristaltic	–	**1.4**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		01/20/20	Peristaltic	0.153 U	**1.67**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	**0.182 J**	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		02/18/20[v]	Unknown	–	**1.4**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
MW128		04/27/20	Peristaltic	0.960 U	**1.04**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 UJ	0.749 U	6.00 U	0.105 U	**0.119 J**	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
(continued)		06/29/20	Peristaltic	0.0556 U	**0.618**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 UJ	–	0.242 U	0.0345 U	**0.0840**	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
(split)		06/29/20[p]	Unknown	–	**0.51**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		08/26/20[p]	Unknown	–	**0.46**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		11/09/20	Bladder	0.0556 U	**0.671**	0.0271 U	0.0400 U	0.0327 U	**0.0810 J**	0.0212 U	0.508 U	–	0.242 U	0.0345 U	**0.127**	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		12/20/20[v]	Unknown	–	**0.40**	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		02/11/21[v]	Unknown	–	0.40 U	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
		05/25/21	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 UJ	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 UJ	0.0118 U	0.265 U	0.124 U	0.153 UJ	0.0472 U
MW-133	Property,	09/25/17	Bladder	0.153 U	**13.3**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	**1.07 J**	0.143 U	0.162 U
	SW quadrant	04/25/18	Bladder	0.153 U	**10.7**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	**0.739 J**	0.143 U	0.162 U
		10/26/18	Bladder	0.153 U	**7.94**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	**0.411 J**	0.143 U	0.162 U
		12/12/18	Bladder	**0.233 J**	**7.88**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	**0.251 J**	0.143 U	0.162 U
		02/01/19	Bladder	0.153 U	**12.4**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		03/13/19	Bladder	0.153 U	**7.48**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	Decommissioned March, 2019																			
MW-137	Property,	09/25/17	Bladder	0.153 U	**62.0**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	SW quadrant	04/12/18	Bladder	0.153 UJ	**1.79**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 UJ	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/26/18	Bladder	0.153 U	**0.893 J+**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		12/12/18	Bladder	0.153 U	**0.437 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		02/01/19	Bladder	0.153 U	**0.616**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		03/11/19	Bladder	0.153 U	**0.275 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	Decommissioned March, 2019																			
MW-138	Dexter Ave N ROW,	09/21/17	Bladder	0.306 U	0.187 U	0.195 U	0.234 U	0.254 U	–	0.316 U	0.314 U	**1.91 J**	0.754 U	0.252 U	0.185 U	0.204 U	2.14 U	0.348 U	0.286 U	0.324 U
	E side	04/11/18	Bladder	0.153 UJ	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 UJ	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/29/18	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	**0.609**	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		12/17/18	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/03/19	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		03/14/19	Bladder	0.153 U	**0.262 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/22/19	Bladder	0.153 UJ	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/19/19	Bladder	0.153 UJ	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/21/19	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/27/20	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		05/08/20	Bladder	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	**0.184 J**	0.157 U	0.0993 U
		07/27/20	Bladder	0.0556 UJ	0.0276 U	0.0271 U	0.0400 U	0.0327 UJ	0.0170 U	**0.0657 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/18/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		02/11/21	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.105**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		06/07/21	Bladder	0.0556 U	**0.0730 J**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0370 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-140	Roy Street ROW,	09/22/17	Bladder	**0.754 J**	**0.477 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
(dup)	E side	09/22/17	Bladder	**2.13**	**0.523**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/12/18	Bladder	0.153 UJ	**2.47 J+**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 UJ	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
MW-141	Property,	09/22/17	Bladder	**2.07**	**0.345 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	SE quadrant	04/12/18	Submersible	0.153 UJ	**91.6 J+**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 UJ	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/25/18	Bladder	0.153 U	**3.10**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 UJ	0.162 U
		12/12/18	Bladder	0.153 U	**1.46**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
MW-141		01/30/19	Bladder	0.153 U	**0.479 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
(continued)		03/11/19	Bladder	0.153 U	**1.30**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	Decommissioned March, 2019																			
MW-153	Roy St ROW,	05/01/18	Bladder	0.153 U	**0.612**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	S side	01/22/19	Bladder	0.153 U	**1.41**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/24/19	Bladder	0.153 U	**1.07**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
(dup)		04/24/19	Bladder	0.153 U	**0.975**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/22/19	Bladder	0.153 U	**0.384 J**	0.0976 U	0.117 U	0.127 U	–	**0.227 J**	0.157 U	0.305 U	0.377 U	**0.134 J**	0.0924 U	0.102 U	1.07 U	0.174 U	**0.162 J**	0.162 U
		10/15/19	Bladder	0.153 UJ	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/21/20	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/30/20	Bladder	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
		07/15/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/09/20	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/09/21	Bladder	0.0556 U	**0.105**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.147**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
(dup)		02/09/21	Bladder	0.0556 U	**0.107**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.160**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/10/21	Bladder	0.0556 UJ	**0.101**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0430 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-158A	8th Ave N ROW,	04/30/18	Bladder	0.153 U	**59.6 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	E side	01/24/19	Bladder	0.153 U	**2.54**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/25/19	Bladder	0.153 U	**0.974**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/19/19	Bladder	0.153 UJ	**0.290 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/16/19	Bladder	0.153 UJ	**0.848**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/21/20	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	**0.269 J**	0.143 U	0.162 U
		04/24/20	Bladder	0.960 U	**1.15**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 UJ	0.749 U	6.00 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
		07/15/20	Bladder	0.0556 U	**0.379**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/23/20	Bladder	0.0556 U	**0.127**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		02/02/21	Bladder	0.0556 U	**0.0890 J**	0.0271 U	0.0400 U	0.0327 UJ	0.0170 U	**0.197**	0.508 UJ	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		05/10/21	Bladder	0.0556 UJ	**0.0900 J**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-160	8th Ave N ROW,	05/21/18	Bladder	0.153 U	**2.96**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
	W side	01/25/19	Bladder	0.153 U	**5.08**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		05/01/19	Bladder	0.153 U	**2.58**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/23/19	Bladder	0.153 U	**0.217 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/17/19	Bladder	0.153 UJ	**0.445 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/29/20	Bladder	0.153 U	**0.176 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/01/20	Bladder	0.153 UJ	**2.09**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		08/03/20	Bladder	0.0556 U	**15.2**	0.0271 UJ	0.0400 U	0.0327 U	0.0170 U	**0.0670 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 UJ
		11/30/20	Bladder	0.0556 U	**43.2**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.108**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/05/21	Bladder	0.0556 U	**26.4**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.177**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/12/21	Bladder	0.0556 U	**11.1**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-161	8th Ave N ROW,	05/21/18	Bladder	0.153 U	**1.89**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	W side	01/25/19	Bladder	0.153 U	**1.26**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		05/01/19	Bladder	0.153 UJ	**1.15**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		07/18/19	Bladder	0.153 U	**1.58**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	**0.353 J**	0.143 U	0.162 U
		10/14/19	Bladder	0.153 U	**1.30**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		01/28/20	Bladder	0.153 U	**9.02**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
MW-161		04/03/20	Bladder	0.153 U	**23.4**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
(continued)		07/31/20	Bladder	0.0556 U	**59.2 J**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 UJ	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		12/01/20	Bladder	0.0556 U	**84.2**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/05/21	Bladder	0.0556 U	**85.8**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/25/21	Bladder	0.0556 U	**69.8**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-162	Property,	02/05/19	Bladder	2.00 UJ	**1,070**	1.00 U	1.00 U	1.00 U	–	1.00 U	4.00 U	–	–	1.00 U	–	1.00 U	1.00 U	1.00 U	1.00 U	1.00 U
	NE quadrant	03/12/19	Peristaltic	0.153 U	**758**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	Decommissioned March, 2019																			
MW-163	Property, NW quadrant	02/05/19	Bladder	2.00 UJ	**42.2**	1.00 U	1.00 U	1.00 U	–	1.00 U	4.00 U	–	–	1.00 U	–	1.00 U	1.00 U	1.00 U	1.00 U	1.00 U
	(dup)	02/05/19	Bladder	2.00 UJ	**40.3**	1.00 U	1.00 U	1.00 U	–	1.00 U	4.00 U	–	–	1.00 U	–	1.00 U	1.00 U	1.00 U	1.00 U	1.00 U
		03/12/19	Bladder	0.153 U	**56.9**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	Decommissioned March, 2019																			
MW-164	Property,	02/05/19	Bladder	2.00 UJ	**385**	1.00 U	1.00 U	1.00 U	–	1.00 U	4.00 U	–	–	1.00 U	–	1.00 U	1.00 U	1.00 U	1.00 U	1.00 U
	SW quadrant	03/12/19	Bladder	0.153 U	**529**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	Decommissioned March, 2019																			
MW-304	Dexter Ave N ROW,	10/21/19	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	E side	01/27/20	Bladder	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		05/07/20	Bladder	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 UJ
		07/27/20	Bladder	0.0556 UJ	0.0276 U	0.0271 U	0.0400 U	0.0327 UJ	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/18/21	Bladder	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-319	9th Ave N ROW,	10/08/19	Bladder	0.153 U	**53.4**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	W side	01/16/20	Peristaltic	0.153 U	**63.7**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/27/20	Bladder	0.960 U	**54.1**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 UJ	0.749 U	6.00 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
		07/27/20	Bladder	0.0556 U	**49.2**	0.0271 U	0.0400 U	0.0327 UJ	0.0170 U	**0.0450 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/12/20	Bladder	0.0556 U	**47.6**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/19/21	Peristaltic	0.0556 U	**37.4**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-323	9th Ave N ROW,	10/09/19	Peristaltic	0.153 U	**66.5**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	**0.308 J**	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	W side	01/20/20	Peristaltic	0.153 U	**229**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/23/20	Bladder	0.960 U	**5.11**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	6.00 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
		07/07/20	Bladder	0.0556 U	**2.55**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/24/20	Bladder	0.0556 U	**2.68**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		05/20/21	Peristaltic	0.0556 U	**115**	0.0271 U	0.0400 U	0.0327 U	**0.0460 J**	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-324	Roy St ROW,	10/02/19	Bladder	0.153 U	**1,550**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	N side	01/20/20	Peristaltic	7.65 U	**3,170**	4.88 U	5.85 U	6.35 U	–	7.90 U	7.85 U	15.3 U	18.9 U	6.30 U	4.62 U	5.10 U	53.5 U	8.70 U	7.15 U	8.10 U
		04/24/20	Bladder	48.0 U	**8,520**	5.55 U	6.10 U	18.7 U	–	6.85 U	16.9 UJ	37.4 U	300 U	5.25 U	5.25 U	5.05 U	21.5 U	8.70 U	7.85 U	4.97 U
		07/07/20	Bladder	2.78 U	**8,410**	1.36 U	2.00 U	1.64 U	0.850 U	1.06 U	25.4 U	–	12.1 U	1.73 U	0.700 U	0.590 U	13.3 U	6.20 U	7.65 U	2.36 U
		11/13/20	Bladder	2.78 UJ	**7,210**	1.36 U	2.00 U	1.64 U	0.850 U	1.06 U	25.4 U	–	12.1 U	1.73 U	0.700 UJ	0.590 U	13.3 U	6.20 U	7.65 U	2.36 U
		05/20/21	Peristaltic	2.78 U	**3,470**	1.36 U	2.00 U	1.64 U	0.850 U	1.06 U	25.4 U	–	12.1 U	1.73 U	0.700 U	0.590 U	13.3 U	6.20 U	7.65 U	2.36 U
MW-326	Mercer Street ROW,	10/03/19	Bladder	0.153 U	**6.87**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
	N side	01/17/20	Bladder	0.153 U	**9.38**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 UJ	**0.371 J**	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/21/20	Bladder	0.960 U	**0.971**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	6.00 U	0.105 U	0.105 UJ	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
		07/23/20	Bladder	0.0556 U	**0.277**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
MW-326 (continued)		11/02/20	Bladder	0.0556 U	**0.224**	0.0271 U	0.0400 U	0.0327 UJ	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/09/21	Bladder	0.0556 U	**3.40**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0570 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/18/21	Bladder	0.0556 U	**3.53**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-328	Lake Union Park, S end	10/02/19	Bladder	0.153 U	**1.26**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/17/20	Peristaltic	0.153 U	**1.03**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 UJ	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/08/20	Peristaltic	0.153 U	**0.631**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/07/20	Peristaltic	0.0556 U	**1.03**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	**0.0570**	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/09/20	Peristaltic	0.0556 U	**0.607**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/25/21	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 UJ	0.0212 U	0.508 U	–	0.242 U	0.0345 U	**0.0400 J**	0.0118 U	0.265 U	0.124 U	0.153 UJ	0.0472 U
MW-329 (dup)	Westlake Ave N ROW, E side	10/03/19	Peristaltic	0.153 U	**9.25**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		10/03/19	Peristaltic	0.153 U	**9.26**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/20/20	Peristaltic	0.153 U	**11.0**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/27/20	Bladder	0.960 U	**17.5**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 UJ	0.749 U	6.00 U	0.105 U	**0.113 J**	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
		08/03/20	Bladder	0.0556 U	**14.7**	0.0271 UJ	0.0400 U	0.0327 U	**0.0923 J**	**0.0290 J**	0.508 U	–	0.242 U	0.0345 U	**0.167**	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 UJ
		11/09/20	Bladder	0.0556 U	**21.0**	0.0271 U	0.0400 U	0.0327 U	**0.139**	0.0212 U	0.508 U	–	0.242 U	0.0345 U	**0.174**	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/25/21	Peristaltic	0.0556 U	**15.2**	0.0271 U	0.0400 U	0.0327 U	0.0170 UJ	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.109 UJ	0.0118 U	0.265 U	0.124 U	0.153 UJ	0.0472 U
MW-336	Mercer St ROW, N side	05/05/20	Bladder	0.960 U	**57.1**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 U
		07/08/20	Bladder	0.0556 U	**61.1**	0.0271 U	0.0400 U	0.0327 U	**0.0570 J**	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/02/20	Bladder	0.0556 U	**137**	0.0271 U	0.0400 U	0.0327 UJ	**0.0730 J**	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/10/21	Bladder	0.0556 UJ	**107**	0.0271 U	0.0400 U	0.0327 U	**0.0510 J**	**0.0550 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/26/21	Peristaltic	0.0556 U	**150**	0.0271 U	0.0400 U	0.0327 U	0.0170 UJ	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 UJ	0.0118 U	0.265 U	0.124 U	0.153 UJ	0.0472 U
MW-341	Lake Union Park, S end	05/12/20	Peristaltic	0.960 U	**41.4**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 UJ	0.749 U	0.554 U	0.105 U	**0.179 J**	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 U
		07/07/20	Peristaltic	0.0556 U	**32.9**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	**0.146**	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/09/20	Peristaltic	0.0556 U	**25.1**	0.0271 U	0.0400 U	0.0327 U	**0.0510 J**	0.0212 U	0.508 U	–	0.242 U	0.0345 U	**0.127**	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/25/21	Peristaltic	0.0556 U	**2.43**	0.0271 U	0.0400 U	0.0327 U	**0.121**	0.0212 U	0.508 U	–	0.242 U	0.0345 U	**0.148**	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-342	Valley St ROW, S side	05/04/20	Peristaltic	0.960 U	**1.34**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	**0.261 J**	0.105 U	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
		07/30/20	Peristaltic	0.0556 U	**5.56 J**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.116**	0.508 U	–	0.242 UJ	0.0345 U	**0.0172 J**	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/17/20	Peristaltic	0.0556 U	**1.22**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		06/04/21	Peristaltic	0.0556 U	**6.45**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-343	Valley St ROW, S side	05/04/20	Peristaltic	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 U	0.157 U	0.0993 U
		07/30/20	Peristaltic	0.0556 U	0.0276 UJ	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.163**	0.508 U	–	0.242 UJ	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/24/20	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		06/04/21	Peristaltic	0.0556 U	**3.17**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
Treatment Zone A Wells																				
IW-4A	Property, NW quadrant Decommissioned March, 2019	03/28/18	Peristaltic	0.153 U	**2,010**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
IW-7A	Property, NE quadrant Decommissioned March, 2019	04/02/18	Peristaltic	0.153 U	**8.74**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
IW-9A	Property, NW quadrant Decommissioned March, 2019	03/29/18	Peristaltic	0.153 U	**510**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
IW-18A	Property, NE quadrant Decommissioned March, 2019	03/30/18	Peristaltic	0.153 U	**3,680**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	**0.258 J**	0.143 U	**0.186 J**
IW-22A	Property, NE quadrant Decommissioned March, 2019	04/02/18	Peristaltic	0.153 U	**128**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
IW-37A	Property, SW quadrant Decommissioned March, 2019	03/28/18	Peristaltic	0.153 U	**10.5**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
IW-41A	Property, SW quadrant Decommissioned March, 2019	04/10/18	Peristaltic	0.153 U	**510**	0.0976 U	0.117 U	0.127 U	–	3.16 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 U	**0.184 J**	1.07 U	3.48 U	0.143 U	0.162 UJ
IW-42A	Property, SW quadrant Decommissioned March, 2019	04/10/18	Peristaltic	0.153 U	**10,500**	0.0976 U	0.117 U	0.127 U	–	39.5 U	0.157 U	0.305 UJ	0.377 U	**0.174 J**	0.0924 U	25.5 U	1.07 U	43.5 U	0.143 U	**0.372 J**
IW-45A	Property, SW quadrant Decommissioned March, 2019	04/04/18	Peristaltic	0.153 U	**18,800**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	**0.235 J**	0.143 U	0.162 U
IW-46A	Property, SE quadrant Decommissioned March, 2019	03/28/18	Peristaltic	0.153 U	**8.86**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
IW-48A	Property, SE quadrant Decommissioned March, 2019	04/02/18	Peristaltic	0.153 U	**1.16**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
MW-165	Property, NE quadrant	11/04/19	Peristaltic	0.153 UJ	**4,180**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/30/20	Peristaltic	0.153 U	**6.89**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		05/01/20	Peristaltic	0.960 U	**61.4**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 U
		07/09/20	Peristaltic	0.0556 U	**40.8**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/05/20	Flowing	0.0556 U	**578**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
(dup)		11/05/20	Flowing	0.0556 U	**578**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/04/21	Flowing	5.56 U	**1,570**	0.0271 U	0.0400 U	0.0327 UJ	0.0170 U	**0.0800 J**	0.508 UJ	–	0.242 U	**0.0630 J**	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		05/06/21	Flowing	0.556 U	**260**	0.271 U	0.400 U	0.327 U	0.170 U	0.212 U	5.08 U	–	2.42 U	0.345 U	0.140 U	0.118 U	2.65 U	1.24 U	1.53 UJ	0.472 UJ
MW-169	Property, SW quadrant	11/05/19	Peristaltic	0.153 UJ	**48.8**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/23/20	Peristaltic	0.153 U	**0.665 J**	0.0976 U	0.117 U	0.127 UJ	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		05/05/20	Peristaltic	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	**1.32 J**	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	**0.176 J**	0.157 U	0.0993 U
		07/10/20	Peristaltic	0.0556 U	**0.194**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.105**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 UJ	0.0472 U
		11/03/20	Flowing	0.0556 U	**0.853**	0.0271 U	0.0400 U	0.0327 UJ	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/17/21	Flowing	0.0556 U	**0.158**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/07/21	Flowing	0.0556 U	0.0680 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-173	Property, SE quadrant	11/01/19	Peristaltic	0.153 UJ	**15.6**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/28/20	Peristaltic	0.153 U	**5.48**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		05/01/20	Peristaltic	0.960 U	**0.493 J**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
MW-173		07/09/20	Peristaltic	0.0556 U	**0.402**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
(continued)		11/05/20	Flowing	0.0556 U	**0.616**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/04/21	Flowing	0.0556 U	**0.272**	0.0271 U	0.0400 U	0.0327 UJ	0.0170 U	0.0212 U	0.508 UJ	–	0.242 U	**0.0380 J**	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		05/05/21	Flowing	0.0556 U	0.142 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	**0.106**	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-177	Property, SW quadrant	11/06/19	Peristaltic	0.153 U	**131,000**	0.0976 U	0.117 U	0.127 U	–	**0.579**	0.157 U	0.305 U	0.377 UJ	**0.184 J**	0.0924 U	0.102 U	1.07 U	**0.677 J**	0.143 U	**0.558**
		01/24/20	Peristaltic	7.65 U	**99,800**	4.88 U	5.85 U	6.35 U	–	7.90 U	7.85 U	15.3 U	18.9 U	6.30 U	4.62 U	5.10 U	53.5 U	8.70 U	7.15 U	8.10 U
		04/01/20	Peristaltic	765 UJ	**123,000**	488 U	585 U	635 U	–	790 U	785 U	1,530 U	1,890 UJ	630 U	462 U	510 U	5,350 U	870 UJ	715 U	810 U
		07/10/20	Peristaltic	278 U	**76,100**	136 U	200 U	164 U	85.0 U	106 U	2,540 U	–	1,210 U	172 U	70.0 U	59.0 U	1,330 U	620 U	765 UJ	236 U
		11/03/20	Flowing	55.6 U	**16,900**	27.1 U	40.0 U	32.7 U	17.0 U	21.2 U	508.0 U	–	242.0 U	34.5 U	14.0 U	11.8 U	265 U	124 U	153 U	47.2 U
		02/18/21	Flowing	11.1 U	**12,800**	5.42 U	8.00 U	6.54 U	3.40 U	4.24 U	102 U	–	48.4 U	6.90 U	2.80 U	2.36 U	53.0 U	24.8 UJ	30.6 U	9.44 U
		05/06/21	Flowing	11.1 U	**11,800**	5.42 U	8.00 U	6.54 U	3.40 U	4.24 U	102 U	–	48.4 U	6.90 U	2.80 U	2.36 U	53.0 U	24.8 U	30.6 U	9.44 U
MW-181	Property, SW quadrant	11/08/19	Peristaltic	0.765 U	**30,800**	0.0976 U	0.117 U	0.127 U	–	0.790 U	0.157 U	1.53 U	0.377 UJ	0.630 U	0.462 U	0.510 U	5.35 U	0.870 U	0.715 U	0.810 U
		01/27/20	Peristaltic	76.5 U	**18,400**	48.8 U	58.5 U	63.5 U	–	79.0 U	78.5 U	153 U	189.0 UJ	63.0 U	46.2 U	51.0 U	535 U	87.0 U	71.5 U	81.0 U
		04/01/20	Peristaltic	76.5 UJ	**24,300**	48.8 U	58.5 U	63.5 U	–	79.0 U	78.5 U	153 U	189.0 UJ	63.0 U	46.2 U	51.0 U	535 U	87.0 UJ	71.5 U	81.0 U
		07/08/20	Peristaltic	27.8 U	**11,100**	13.6 U	20.0 U	16.4 U	8.50 U	10.6 U	254.0 U	–	121.0 U	17.2 U	7.00 U	5.90 U	133 U	62.0 U	76.5 U	23.6 U
		11/04/20	Peristaltic	0.0556 U	**1,360**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/19/21	Flowing	5.56 U	**1,460**	2.71 U	4.00 U	3.27 U	1.70 U	2.12 U	50.8 U	–	24.2 U	3.45 U	1.40 U	1.18 U	26.5 U	12.4 UJ	15.3 U	4.72 U
		05/06/21	Peristaltic	5.56 U	**381**	2.71 U	4.00 U	3.27 U	1.70 U	2.12 U	50.8 U	–	24.2 U	3.45 U	1.40 U	1.18 U	26.5 U	12.4 U	15.3 U	4.72 U
MW-185	Property, SE quadrant	10/31/19	Flowing	0.153 U	**547**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/29/20	Peristaltic	0.153 U	**1.09**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		04/02/20	Peristaltic	0.153 U	**1.18**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/08/20	Peristaltic	0.0556 U	**0.752**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0630 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/04/20	Flowing	0.0556 U	**0.351**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/16/21	Flowing	0.0556 U	**0.203**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/07/21	Flowing	0.0556 U	0.257 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
Treatment Zone B Wells																				
IW-3B	Property, NW quadrant Decommissioned March, 2019	03/28/18	Peristaltic	0.153 U	**3,170**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
IW-6B	Property, SW quadrant Decommissioned March, 2019	04/02/18	Peristaltic	0.153 U	**2,270**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
IW-8B	Property, SW quadrant Decommissioned March, 2019	03/30/18	Peristaltic	0.153 U	**6.43**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
IW-17B	Property, NE quadrant Decommissioned March, 2019	03/30/18	Peristaltic	0.153 U	**51,400**	0.0976 U	0.117 U	0.127 U	–	**0.451 J**	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	**0.480 J**	0.143 U	**0.307 J**
IW-21B	Property, NE quadrant Decommissioned March, 2019	04/02/18	Peristaltic	0.153 U	**4,600**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
IW-22B	Property, NW quadrant Decommissioned March, 2019	04/25/18	Peristaltic	3.06 U	**26,600**	1.95 U	2.34 U	2.54 U	–	3.16 U	3.14 U	6.10 U	7.54 U	2.52 U	1.85 U	2.04 U	21.4 U	3.48 U	2.86 U	3.24 U
IW-24B	Property, NE quadrant Decommissioned March, 2019	03/30/18	Peristaltic	0.153 U	**48,200**	0.0976 U	0.117 U	0.127 U	–	**0.777 J+**	0.157 U	0.305 UJ	0.377 U	**0.158 J+**	0.0924 U	0.102 U	1.07 U	**0.975 J+**	0.143 U	**0.429 J+**
IW-28B	Property, NW quadrant Decommissioned March, 2019	04/09/18	Peristaltic	0.153 U	**19.4**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
IW-33B	Property, NE quadrant Decommissioned March, 2019	04/02/18	Peristaltic	0.153 U	**18,200**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
IW-37B	Property, SW quadrant Decommissioned March, 2019	03/29/18	Peristaltic	0.153 U	**3,240**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
IW-45B	Property, SE quadrant Decommissioned March, 2019	03/28/18	Peristaltic	0.153 U	**213**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
IW-47B	Property, SW quadrant Decommissioned March, 2019	04/10/18	Bladder	0.765 U	**40,900**	0.488 U	0.585 U	0.635 U	–	158 U	0.785 U	1.52 UJ	1.88 U	0.630 U	0.462 U	0.510 U	5.35 U	174 U	0.715 U	0.810 UJ
IW-49B	Property, SE quadrant Decommissioned March, 2019	03/28/18	Peristaltic	0.153 U	**974**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	**0.197 J**	0.143 U	0.162 U
IW-51B	Property, SE quadrant Decommissioned March, 2019	03/28/18	Peristaltic	0.153 U	**4.60**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	**0.208 J**	0.143 U	0.162 U
MW-166	Property, NE quadrant	11/04/19	Peristaltic	0.153 UJ	**5,130**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/30/20	Peristaltic	0.153 U	**118**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		05/01/20	Peristaltic	0.960 U	**20.4**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 U
		07/09/20	Peristaltic	0.0556 U	**21.7**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0510 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 UJ	0.0472 U
(dup)		07/09/20	Peristaltic	0.0556 U	**24.3**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/05/20	Peristaltic	0.0556 U	**6,090**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/04/21	Flowing	27.8 U	**9,810**	13.6 U	20.0 U	16.4 U	8.50 U	10.6 U	254 U	–	121 U	17.2 U	7.00 U	5.90 U	133 U	62.0 U	76.5 U	23.6 U
		05/05/21	Flowing	11.1 U	**7,150**	5.42 U	8.00 U	6.54 U	3.40 U	4.24 U	102 U	–	48.4 U	6.90 U	2.80 U	2.36 U	53.0 U	24.8 U	30.6 UJ	9.44 UJ
MW-170	Property, SW quadrant	11/05/19	Peristaltic	0.153 UJ	**27,600**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/23/20	Peristaltic	3.83 U	**21,900**	2.44 U	2.93 U	3.18 UJ	–	3.95 U	3.93 U	7.63 U	9.43 U	3.15 U	2.31 U	2.55 U	26.8 U	4.35 U	3.58 U	4.05 U
		04/02/20	Peristaltic	76.5 U	**30,900**	48.8 U	58.5 U	63.5 U	–	79.0 U	78.5 U	153 U	189.0 U	63.0 U	46.2 U	51.0 U	535 U	87.0 U	71.5 U	81.0 U
		07/09/20	Peristaltic	0.556 U	**32,700**	0.271 U	0.400 U	0.327 U	0.170 U	0.212 U	5.08 U	–	2.42 U	0.345 U	0.140 U	0.118 U	2.65 U	1.24 U	1.53 U	0.472 U
		11/03/20	Peristaltic	0.556 U	**9,090**	0.271 U	0.400 U	0.327 UJ	0.170 U	0.212 U	5.08 U	–	2.42 U	0.345 U	0.140 U	0.118 U	2.65 U	1.24 U	1.53 U	0.472 U
		02/17/21	Peristaltic	0.556 U	**5,450**	0.271 U	0.400 U	0.327 U	0.170 U	**0.700 J**	5.08 U	–	2.42 U	0.345 U	0.140 U	0.118 U	2.65 U	1.24 U	1.53 U	0.472 U
		05/07/21	Peristaltic	27.8 U	**3,980**	13.6 U	20.0 U	16.4 U	8.50 U	10.6 U	254 U	–	121 U	17.2 U	7.00 U	5.90 U	133 U	62.0 U	76.5 U	23.6 U
MW-174	Property, SE quadrant	11/01/19	Peristaltic	0.153 UJ	**0.286 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/28/20	Peristaltic	0.153 U	**0.484 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		05/01/20	Peristaltic	0.960 U	**0.877**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 U
		07/09/20	Peristaltic	0.0556 U	**1.19**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/05/20	Flowing	0.0556 U	**0.609**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/04/21	Flowing	0.0556 U	**0.247**	0.0271 U	0.0400 U	0.0327 UJ	0.0170 U	0.0212 U	0.508 UJ	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		05/05/21	Flowing	0.0556 U	**0.245**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-178	Property, SW quadrant	11/06/19	Peristaltic	0.153 U	**5.28 J**	0.0976 U	0.117 U	0.127 U	–	**0.321 J**	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/24/20	Peristaltic	0.153 U	**0.565**	0.0976 U	0.117 U	0.127 U	–	**0.245 J**	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/02/20	Peristaltic	0.153 UJ	**1.03**	0.0976 U	0.117 U	0.127 U	–	**0.202 J**	0.157 U	0.305 U	0.377 UJ	**0.351 J**	0.0924 U	0.102 U	1.07 U	0.204 U	0.143 U	**0.965**
		07/10/20	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.102**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	**0.0560**	0.265 U	0.124 U	0.153 UJ	0.0472 U
		11/03/20	Peristaltic	**7.95**	**54.3**	0.0271 U	0.0400 U	0.0327 UJ	0.0170 U	**0.0700 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/18/21	Peristaltic	1.11 U	**2,540**	0.542 U	0.800 U	0.654 U	0.340 U	0.424 U	10.2 U	–	4.84 U	0.690 U	0.280 U	0.236 U	5.30 U	2.48 U	3.06 U	0.944 U
		05/06/21	Peristaltic	1.11 U	**1,620**	0.542 U	0.800 U	0.654 U	0.340 U	0.424 U	10.2 U	–	4.84 U	0.690 U	0.280 U	0.236 U	5.30 U	2.48 U	3.06 U	0.944 U
MW-182	Property, SW quadrant	11/08/19	Peristaltic	0.153 U	**19,200**	0.0976 U	0.117 U	0.127 U	–	**0.344 J**	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	**0.215 J**	0.143 U	0.162 U
		01/27/20	Peristaltic	76.5 U	**4,500**	48.8 U	58.5 U	63.5 U	–	79.0 U	78.5 U	153 U	189.0 UJ	63.0 U	46.2 U	51.0 U	535 U	87.0 U	71.5 U	81.0 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
MW-182		04/01/20	Peristaltic	7.65 U	**2,600**	4.88 U	5.85 U	6.35 U	–	7.90 U	7.85 U	15.3 UJ	18.9 U	6.30 U	4.62 U	5.10 U	53.5 U	8.70 U	7.15 U	8.10 U
(continued)		07/08/20	Peristaltic	2.78 U	**715**	1.36 U	2.00 U	1.64 U	0.850 U	1.06 U	25.4 U	–	12.1 U	1.73 U	0.700 U	0.590 U	13.3 U	6.20 U	7.65 U	2.36 U
		11/04/20	Peristaltic	2.78 U	**84,900**	1.36 U	2.00 U	1.64 U	**6.70**	1.06 U	25.4 U	–	12.1 U	1.73 U	0.700 U	0.590 U	**46.2 J**	6.20 U	7.65 U	2.36 U
		02/19/21	Peristaltic	27.8 U	**87,400**	13.6 U	20.0 U	16.4 U	8.50 U	10.6 U	254 U	–	121 U	17.2 U	7.00 U	5.90 U	133 U	62.0 U	76.5 U	23.6 U
		05/06/21	Peristaltic	111 U	**68,400**	54.2 U	80.0 U	65.4 U	34.0 U	42.4 UJ	1,020 U	–	484 U	69.0 UJ	28.0 U	23.6 U	530 U	248 UJ	306 U	94.4 UJ
	(dup)	05/06/21	Peristaltic	0.0556 U	**64,900**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.530 J**	0.508 U	–	0.242 U	**0.123 J**	0.0140 U	0.0118 U	0.265 U	**2.58 J**	**0.388 J**	**0.332 J**
MW-186	Property, SE quadrant	10/31/19	Flowing	0.153 U	**4.15**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/29/20	Peristaltic	0.153 U	**0.777**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/02/20	Peristaltic	0.153 U	**0.476 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/08/20	Peristaltic	0.0556 U	**0.101**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.107**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/04/20	Peristaltic	0.0556 U	**0.552**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/16/21	Flowing	0.0556 U	**0.459**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/07/21	Flowing	0.0556 U	**0.393**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
Treatment Zone C Wells																				
IW-1C	Property, NE quadrant Decommissioned March, 2019	03/29/18	Peristaltic	0.153 U	**12.7**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
IW-4C	Property, NE quadrant Decommissioned March, 2019	04/26/18	Peristaltic	0.153 U	**5,080**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
IW-8C	Property, NE quadrant Decommissioned March, 2019	04/04/18	Peristaltic	0.153 U	**4,160**	0.0976 U	0.117 U	0.127 U	–	**0.206 J**	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	**0.580 J**	0.143 U	**0.164 J**
IW-9C	Property, NE quadrant Decommissioned March, 2019	04/02/18	Peristaltic	0.153 U	**20,400**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
IW-13C	Property, SW quadrant Decommissioned March, 2019	04/25/18	Peristaltic	0.153 U	**412**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
IW-15C	Property, SW quadrant Decommissioned March, 2019	03/30/18	Bladder	1.53 U	**26,800**	0.976 U	1.17 U	1.27 U	–	1.58 U	1.57 U	3.05 UJ	3.77 U	1.26 U	0.924 U	1.02 U	10.7 U	1.74 U	1.43 U	1.62 U
IW-19C	Property, SW quadrant Decommissioned March, 2019	03/29/18	Peristaltic	0.153 U	**103**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
IW-20C	Property, SW quadrant	03/30/18	Bladder	0.153 U	**6,830**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
(dup)	Decommissioned March, 2019	03/30/18	Bladder	0.153 U	**6,690**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
MW-167	Property, NE quadrant	11/04/19	Peristaltic	0.153 UJ	**14.6**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/28/20	Peristaltic	0.153 U	**8.08**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		05/01/20	Peristaltic	0.960 U	**0.715**	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 U
		07/09/20	Peristaltic	0.0556 U	**0.473**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0870 J**	0.508 U	–	0.242 U	**0.0650 J**	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 UJ	0.0472 U
		11/05/20	Peristaltic	0.0556 U	**0.675**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/04/21	Peristaltic	0.0556 U	**0.470**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0590 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/05/21	Peristaltic	0.0556 U	**0.353**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0920 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-171	Property, SW quadrant	11/05/19	Peristaltic	0.153 UJ	**509**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/23/20	Peristaltic	0.153 U	**81.9**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/02/20	Peristaltic	0.153 U	**11.4**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/09/20	Peristaltic	0.0556 U	**1.53**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
MW-171		11/03/20	Peristaltic	0.0556 U	**32.6**	0.0271 U	0.0400 U	0.0327 UJ	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
(continued)		02/17/21	Peristaltic	0.0556 U	**588 J**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0910 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
(dup)		02/17/21	Peristaltic	0.0556 U	**878 J**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0610 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/07/21	Peristaltic	2.78 U	**1,050**	1.36 U	2.00 U	1.64 U	0.850 U	1.06 U	25.4 U	–	12.1 U	1.73 U	0.700 U	0.590 U	13.3 U	6.20 U	7.65 U	2.36 U
MW-175	Property, SE quadrant	11/01/19	Peristaltic	0.153 UJ	**258**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/28/20	Peristaltic	0.153 U	**8.95**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 UJ	0.143 U	0.162 U
		05/01/20	Peristaltic	0.960 U	**0.478 J**	0.111 U	0.122 U	0.374 U	–	**0.186 J**	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 U
		07/09/20	Peristaltic	0.0556 U	**0.400**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/05/20	Peristaltic	0.0556 U	**0.744**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/04/21	Peristaltic	0.0556 U	**0.698**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0450 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/05/21	Peristaltic	0.0556 U	**0.305**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0570 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-179	Property, SW quadrant	11/06/19	Peristaltic	0.153 U	**3,780**	0.0976 U	0.117 U	0.127 U	–	**0.273 J**	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/27/20	Peristaltic	0.153 U	**941**	0.0976 U	0.117 U	0.127 U	–	**0.198 J**	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/02/20	Peristaltic	3.06 UJ	**817**	1.95 U	2.34 U	2.54 U	–	3.16 U	3.14 U	6.10 U	7.54 UJ	2.52 U	1.85 U	2.04 U	21.4 U	3.48 UJ	2.86 U	3.24 U
		07/10/20	Peristaltic	1.11 U	**939**	0.542 U	0.800 U	0.654 U	0.340 U	0.424 U	10.2 U	–	4.84 U	0.690 U	0.280 U	0.236 U	5.30 U	2.48 U	3.06 UJ	0.944 U
		11/03/20	Peristaltic	1.11 U	**17,700**	0.542 U	0.800 U	0.654 UJ	0.340 U	0.424 U	10.2 U	–	4.84 U	0.690 U	0.280 U	0.236 U	5.30 U	2.48 U	3.06 U	0.944 U
		02/18/21	Peristaltic	27.8 U	**16,600**	13.6 U	20.0 U	16.4 U	8.50 U	10.6 U	254 U	–	121 U	17.2 U	7.00 U	5.90 U	133 U	62.0 U	76.5 U	23.6 U
		05/06/21	Peristaltic	13.9 U	**4,960**	6.78 U	10.0 U	8.18 U	4.25 U	5.30 U	127 U	–	60.5 U	8.63 U	3.50 U	2.95 U	66.3 U	31.0 U	38.3 UJ	11.8 UJ
MW-183	Property, SW quadrant	11/08/19	Peristaltic	0.153 U	**59.9**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/27/20	Peristaltic	0.153 U	**21.8**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/02/20	Peristaltic	0.153 U	**3.03**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/08/20	Peristaltic	0.0556 U	**0.893**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.128**	0.508 U	–	0.242 U	**0.0370 J**	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/04/20	Peristaltic	0.0556 U	**752**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/19/21	Peristaltic	0.0556 U	**4,950**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/06/21	Peristaltic	5.56 U	**4,470**	2.71 U	4.00 U	3.27 U	1.70 U	2.12 U	50.8 U	–	24.2 U	3.45 U	1.40 U	1.18 U	26.5 U	12.4 U	15.3 UJ	4.72 UJ
MW-187	Property, SE quadrant	11/01/19	Peristaltic	0.153 UJ	**2.34**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	**0.306 J**	0.143 U	0.162 U
		01/29/20	Peristaltic	0.153 U	**0.319 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/02/20	Peristaltic	0.153 U	**0.234 J**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/08/20	Peristaltic	0.0556 U	**0.123**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.126**	0.508 U	–	0.242 U	**0.0390 J**	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/04/20	Peristaltic	0.0556 U	**0.631**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0250 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/16/21	Peristaltic	0.0556 U	**0.241**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0870 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/07/21	Peristaltic	0.0556 U	0.185 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
Treatment Zone D Wells																				
IW-1D	Property, NE quadrant Decommissioned March, 2019	04/03/18	Bladder	1.53 U	**5,920**	0.976 U	1.17 U	1.27 U	–	1.58 U	1.57 U	3.05 U	3.77 U	1.26 U	0.924 U	1.02 U	10.7 U	1.74 U	1.43 U	1.62 U
IW-3D	Property, NE quadrant Decommissioned March, 2019	04/03/18	Bladder	0.153 U	**9,860**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
IW-4D	Property, SW quadrant Decommissioned March, 2019	03/29/18	Bladder	0.153 U	**5.29**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 UJ	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
IW-6D	Property, SW quadrant Decommissioned March, 2019	04/03/18	Bladder	0.153 U	**2.97**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
IW-8D	Property, SW quadrant Decommissioned March, 2019	04/04/18	Bladder	0.153 U	**3,200**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
IW-9D	Property, SW quadrant Decommissioned March, 2019	04/04/18	Bladder	0.153 U	**3,380**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
IW-11D	Property, NE quadrant Decommissioned March, 2019	05/01/18	Bladder	0.153 U	**1,640**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
MW-168	Property, NE quadrant	11/04/19	Peristaltic	0.153 UJ	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/31/20	Flowing	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.361 U	0.143 U	0.162 U
		05/01/20	Peristaltic	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	**0.161 J**	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	**0.339 J**	0.157 U	0.0993 U
		07/09/20	Peristaltic	0.0556 U	**0.175**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/05/20	Peristaltic	0.0556 U	**1.92**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/04/21	Peristaltic	0.0556 U	**0.490**	0.0271 U	0.0400 U	0.0327 UJ	0.0170 U	**0.0480 J**	0.508 UJ	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 UJ	0.153 U	0.0472 U
		05/05/21	Peristaltic	0.0556 U	**1.29**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0970 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-172	Property, SW quadrant	11/05/19	Flowing	0.153 UJ	**643**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/23/20	Flowing	0.153 U	**623**	0.0976 U	0.117 U	0.127 UJ	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/02/20	Peristaltic	76.5 U	**452**	48.8 U	58.5 U	63.5 U	–	79.0 U	78.5 U	153 U	189.0 U	63.0 U	46.2 U	51.0 U	535 U	87.0 U	71.5 U	81.0 U
		07/09/20	Peristaltic	0.0556 U	**668**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/03/20	Peristaltic	0.0556 U	**582**	0.0271 U	0.0400 U	0.0327 UJ	0.0170 U	**0.177**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/17/21	Flowing	0.0556 U	**955**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0680 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/07/21	Peristaltic	5.56 U	**538**	2.71 U	4.00 U	3.27 U	1.70 U	2.12 U	50.8 U	–	24.2 U	3.45 U	1.40 U	1.18 U	26.5 U	12.4 U	15.3 U	4.72 U
MW-176	Property, SE quadrant	11/01/19	Flowing	0.153 UJ	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/28/20	Flowing	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/28/20	Flowing	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		05/01/20	Peristaltic	0.960 U	0.126 U	0.111 U	0.122 U	0.374 U	–	0.137 U	0.337 U	0.749 U	0.554 U	0.105 U	0.105 U	0.101 U	0.430 U	0.174 UJ	0.157 U	0.0993 U
		07/09/20	Peristaltic	0.0556 U	**0.0300 J**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/05/20	Peristaltic	0.0556 U	**1.22**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/04/21	Peristaltic	0.0556 U	**1.28**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/05/21	Peristaltic	0.0556 U	**0.816**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0570 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-180	Property, SW quadrant	11/06/19	Flowing	0.153 U	**155**	0.0976 U	0.117 U	0.127 U	–	**0.247 J**	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/24/20	Peristaltic	0.153 U	**222**	0.0976 U	0.117 U	0.127 U	–	**0.184 J**	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/01/20	Peristaltic	0.765 UJ	**89.9**	0.488 U	0.585 U	0.635 U	–	0.790 U	0.785 U	1.53 U	1.89 UJ	0.630 U	0.462 U	0.510 U	5.35 U	0.870 UJ	0.715 U	0.810 U
		07/10/20	Peristaltic	0.0556 U	**50.7**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 UJ	0.0472 U
		11/03/20	Peristaltic	0.0556 U	**156**	0.0271 U	0.0400 U	0.0327 UJ	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/18/21	Flowing	0.0556 U	**162**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/06/21	Peristaltic	0.0556 U	**407**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0370 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
MW-184	Property, SW quadrant	11/08/19	Flowing	0.153 U	**79.0**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/27/20	Flowing	0.153 U	**22.3**	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 UJ	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/01/20	Peristaltic	1.53 U	**370**	0.976 U	1.17 U	1.27 U	–	1.58 U	1.57 U	3.05 UJ	3.77 U	1.26 U	0.924 U	1.02 U	10.7 U	1.74 U	1.43 U	1.62 U
		07/08/20	Peristaltic	0.0556 U	**75.7**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/04/20	Peristaltic	0.556 U	**134**	0.271 U	0.400 U	0.327 U	**1.36**	0.212 U	5.08 U	–	2.42 U	0.345 U	0.140 U	0.118 U	**9.02 J**	1.24 U	1.53 U	0.472 U
		02/19/21	Flowing	0.556 U	**432**	0.271 U	0.400 U	0.327 U	0.170 U	0.212 U	5.08 U	–	2.42 U	0.345 U	0.140 U	0.118 U	2.65 U	1.24 UJ	1.53 U	0.472 U
		05/06/21	Peristaltic	0.278 U	**101**	0.136 U	0.200 U	0.164 U	0.0850 U	0.106 U	2.54 U	–	1.21 U	0.173 U	0.0700 U	0.0590 U	1.33 U	0.620 U	0.765 UJ	0.236 UJ

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Dibromomethane	Dichlorodifluoromethane (CFC-12)	Ethyl Ether	Ethylbenzene	Hexachloro-1,3-butadiene	Hexane (n-Hexane)	Iodomethane	Isopropylbenzene (Cumene)	Isopropyl ether (di-isopropyl ether)	Methyl tert-butyl ether (MTBE)	Methylene Chloride	Naphthalene	n-Butylbenzene	n-Propylbenzene
Preliminary Cleanup Level (PCUL)				–	**16**	**0.44**	**80**	**1,600**	**1,600**	**700**	**0.56**	**480**	–	**800**	–	**24**	**5**	**160**	**400**	**800**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**150**	–	–	–	**6**	–	**1,200**	–	**8**	–	**720**	–	**600**	**4,800**	**8.9**	–	**2,300**
MW-188	Property, SE quadrant	10/31/19	Flowing	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		01/29/20	Flowing	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		04/02/20	Peristaltic	0.153 U	0.0933 U	0.0976 U	0.117 U	0.127 U	–	0.158 U	0.157 U	0.305 U	0.377 U	0.126 U	0.0924 U	0.102 U	1.07 U	0.174 U	0.143 U	0.162 U
		07/08/20	Peristaltic	0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	**0.0830 J**	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		11/04/20	Peristaltic	0.0556 U	**0.220**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		02/16/21	Peristaltic	0.0556 U	**0.589**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
		05/07/21	Peristaltic	0.0556 U	**0.448**	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.508 U	–	0.242 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.124 U	0.153 U	0.0472 U
Number of Analytes Measured				1,270	1,349	1,240	1,240	1,227	440	1,270	1,270	780	1,221	1,240	1,221	1,239	1,269	1,248	1,237	1,239
Number of Analytes Detected				7	1003	0	0	0	52	176	0	22	3	63	76	21	9	67	21	52
Frequency of Detection				1%	74%	0%	0%	0%	12%	14%	0%	3%	0.2%	5%	6%	2%	1%	5%	2%	4%
Maximum Detection				7.95	131,000	–	–	–	16.1	307	–	65.1	1	149	1.45	1.180 U	89.3 J	115 J	14.2	359
Minimum Detection				0.0556 U	0.0276 U	0.0271 U	0.0400 U	0.0327 U	0.0170 U	0.0212 U	0.1570 U	0.305 U	0.2420 U	0.0345 U	0.0140 U	0.0118 U	0.265 U	0.100 U	0.143 U	0.0472 U
Number of Detections Above SL				–	471	0	0	0	0	0	0	0	–	0	–	0	7	0	0	0
Frequency of Detection Above SL				–	35%	0%	0%	0%	0%	0%	0%	0%	–	0%	–	0%	1%	0%	0%	0%

Notes:

Gasoline Range Organics Analyzed by NWTPH-Gx.
Diesel Range Organics and Heavy Oil analyzed by NWTPH-Dx.
VOCs analyzed by EPA Method 8260C or 8260D.
Results shown in micrograms per liter (µg/L).
PCULs and Screening Levels from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021.
All groundwater sampling performed by PES Environmental, Inc. unless otherwise indicated.
a = Results provided by Hart Crowser.
b = Results provided by Farallon Consulting.
c = Select sample results for MW-210 incorrectly identified with location SMW-3 on lab reports and sampling forms.
(split) = Split samples collected consecutively.
(dup) = Field duplicate sample.
– = Not analyzed, results not available, or information not applicable.
Detected results shown in **bold.**
Detections above the groundwater PCUL level are shown in **bold and highlighted in gray.**
Shallow Zone detections above the groundwater screening level for soil vapor are shown in **bold and highlighted in orange.**
Shallow Zone detections above the groundwater PCUL and screening level for soil vapor are shown in **bold highlighted in grayish-orange.**
U = Not detected at or above the laboratory method detection limit (MDL); detections above the MDL but below the laboratory reported detection limit (RDL) are qualified with a "J."
J = The identification of the analyte is acceptable; the reported value is an estimate.
J+ = The result is an estimated quantity, but the result may be biased high.
J- = The result is an estimated quantity, but the result may be biased low.
z = Elevated chlorinated VOCs detected within the GRO elution range. No discernible petroleum pattern present. Project level qualifier assigned per laboratory review.
GRO results above the screening level and qualified with "z" are not considered in the Maximum Detection and are not included in the Number of Detections Above SL.

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
Shallow Water Bearing Zone																
DMW-1S	615 Dexter, SE quadrant	03/25/19[a]	Unknown	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	0.20 U	1.0 U
		03/25/19[a]	Unknown	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	0.20 U	1.0 U
		03/18/20[a]	Unknown	–	–	–	0.20 U	–	**1.6**	0.20 U	–	–	0.20 U	0.20 UJ	0.20 U	**1.8**
DMW-2S	615 Dexter, SE quadrant	03/18/20[a]	Unknown	–	–	–	0.20 U	–	0.20 U	0.20 U	–	–	0.20 U	0.20 UJ	0.20 U	0.40 U
DMW-4S	Alley S of SE quadrant of 615 Dexter	03/19/20[a]	Unknown	–	–	–	0.20 U	–	**0.26**	0.20 U	–	–	0.20 U	0.20 UJ	0.20 U	**3.0**
DMW-5IA	Alley S of 615 Dexter	03/19/20[a]	Unknown	–	–	–	0.20 U	–	**0.64**	0.20 U	–	–	0.20 U	0.20 UJ	0.20 U	0.40 U
DMW-6	615 Dexter, NE quadrant	03/18/20[a]	Unknown	–	–	–	0.20 U	–	0.20 U	0.20 U	–	–	0.20 U	0.20 UJ	0.20 U	0.40 U
F5	Property, NW quadrant	03/28/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.727 U	**4.31**	0.222 U	0.257 U	**0.241 J**	0.130 U	**90.6**	0.316 U
		06/22/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.708**	**0.485 J**	0.222 U	0.257 U	0.153 U	0.130 U	**63.9**	0.316 U
	Decommissioned March, 2019															
F9	Property, NE quadrant	03/27/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**2.04**	**0.539**	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		06/22/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**1.70**	**0.610**	0.222 U	0.257 U	0.153 U	0.130 U	**3.57**	0.316 U
	Decommissioned March, 2019															
F13	Property, NE quadrant	03/27/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**0.936**	0.316 U
		06/22/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**1.32**	0.316 U
		04/05/18	Peristaltic	0.134 U	0.117 U	0.183 U	**20.3**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.346 J**	0.130 U	**0.843**	0.316 U
	Decommissioned March, 2019															
FMW-143	9th Ave N ROW, E side	07/30/19[a]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	0.20 U	–	0.20 U	–
		10/31/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		01/22/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		05/14/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	**0.319 J**	0.149 U	0.118 U	0.467 UJ	0.190 U	0.160 U	0.234 U	**0.201 J**
		07/22/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.146 J**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	**0.331**
G12	Property, NE quadrant	03/27/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**1.97**	0.222 U	0.257 U	**0.233 J**	0.130 U	**28.4**	0.316 U
		06/30/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**2.94**	0.222 U	0.257 U	**0.323 J**	0.130 U	**31.5**	0.316 U
	Decommissioned March, 2019															
HMW-1S	SDOT Mercer Parcels, NE quadrant	3/25/19[a]	Peristaltic	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	0.20 U	1.0 U
		03/11/20[a]	Unknown	–	–	–	0.20 U	–	0.20 U	0.20 U	–	–	0.20 U	0.20 UJ	0.20 U	0.40 U
HMW-2S	SDOT Mercer Parcels, NE quadrant	3/25/19[a]	Peristaltic	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	0.20 U	1.0 U
		03/12/20[a]	Unknown	–	–	–	0.20 U	–	0.20 U	0.20 U	–	–	0.20 U	0.20 UJ	0.20 U	0.40 U
HMW-9S	SDOT Mercer Parcels, SW quadrant	03/17/20[a]	Unknown	–	–	–	0.20 U	–	0.20 U	0.20 U	–	–	0.20 U	0.20 UJ	0.20 U	0.40 U
HMW-10S	SDOT Mercer Parcels, SE quadrant	03/16/20[a]	Unknown	–	–	–	0.20 U	–	0.20 U	0.20 U	–	–	0.20 U	0.20 UJ	0.20 U	0.40 U
HMW-11S	SDOT Mercer Parcels, SE quadrant	03/11/20[a]	Unknown	–	–	–	0.20 U	–	0.20 U	0.20 U	–	–	0.20 U	0.20 UJ	0.20 U	0.40 U
HMW-20S	SDOT Mercer Parcels, NW quadrant	9/18/20[a]	Unknown	1.0 U	1.0 U	0.20 U	**4.7**	–	0.20 U	0.20 U	1.0 U	–	**0.38**	0.20 U	**0.99**	0.40 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
HMW-21S	SDOT Mercer Parcels, SE quadrant	11/3/20[a]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–
HMW-22S	SDOT Mercer Parcels, SE quadrant	11/3/20[a]	Unknown	–	–	–	–	–	–	–	–	–	–	–	–	–
J5	Property, SW quadrant	03/21/17	Peristaltic	0.134 U	0.117 U	0.183 U	**285**	–	0.412 U	**1.73**	0.222 U	0.257 U	**78.5**	0.130 U	**29.6**	0.316 U
		06/26/17	Peristaltic	0.134 U	0.117 U	0.183 U	**36.1**	–	**0.506**	**1.94**	0.222 U	0.257 U	**37.1**	0.130 U	**77.7**	0.316 U
		04/05/18	Peristaltic	0.134 U	0.117 U	0.183 U	**267**	–	0.412 U	**1.00**	0.222 U	0.257 U	**70.5**	0.130 U	**17.6**	0.316 U
	Decommissioned March, 2019															
J15	Property, SE quadrant	03/27/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.495 J**	**1.18**	0.222 U	0.257 U	0.153 U	0.130 U	**6.99**	0.316 U
		06/26/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.459 J**	**1.06**	0.222 U	0.257 U	0.153 U	0.130 U	**6.30**	0.316 U
(dup)		06/26/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.551**	**1.03**	0.222 U	0.257 U	0.153 U	0.130 U	**6.73**	0.316 U
		04/05/18	Peristaltic	0.134 U	0.117 U	0.183 U	**12.8**	–	0.412 U	**0.709**	0.222 U	0.257 U	**0.358 J**	0.130 U	**6.07**	0.316 U
	Decommissioned March, 2019															
K8	Property, SW quadrant	03/21/17	Peristaltic	0.134 U	0.117 U	0.183 U	**82.5**	–	0.412 U	**0.680**	0.222 U	0.257 U	**22.0**	0.130 U	**0.461 J**	0.316 U
		06/26/17	Peristaltic	0.134 U	0.117 U	0.183 U	**67.9**	–	0.412 U	**0.750**	0.222 U	0.257 U	**28.7**	0.130 U	**0.456 J**	0.316 U
		04/05/18	Peristaltic	0.134 U	0.117 U	0.183 U	**229**	–	0.412 U	**0.750**	0.222 U	0.257 U	**26.3**	0.130 U	**1.45**	0.316 U
	Decommissioned March, 2019															
M15	Property, SE quadrant	03/27/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**0.561**	0.222 U	0.257 U	**0.733**	0.130 U	**13.2**	0.316 U
(dup)		03/27/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**0.513**	0.222 U	0.257 U	**0.670**	0.130 U	**12.0**	0.316 U
		06/26/17	Peristaltic	0.134 U	0.117 U	0.183 U	**0.233 J**	–	0.412 U	**0.523**	0.222 U	0.257 U	**1.80**	0.130 U	**15.0**	0.316 U
		04/05/18	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**0.300 J**	0.222 U	0.257 U	**0.563**	0.130 U	**11.1**	0.316 U
	Decommissioned March, 2019															
MW-8	Seattle Roy Aloha Shops, N end	03/20/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/13/18	Peristaltic	0.134 U	0.117 U	0.183 U	**0.570**	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		07/18/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		10/10/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	**0.167 J**	0.130 U	0.118 U	0.316 U
		01/16/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**1.96**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	**0.569 J**
		05/06/20	Peristaltic	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	0.174 U
		07/14/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.161 J**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	0.191 U
MW-9	8th Ave N ROW, E side	03/20/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**0.324 J**	0.316 U
		06/20/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.562**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
(dup)		06/20/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.548**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/05/18	Peristaltic	0.134 U	0.117 U	0.183 U	**1.58**	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**0.210 J**	0.316 U
		01/21/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/26/19	Peristaltic	0.134 U	0.117 U	0.183 U	**157**	–	0.412 U	**0.261 J**	0.222 U	0.257 U	**45.2**	0.130 UJ	0.861 UJ	0.316 U
		07/16/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 UJ	**0.619**	0.316 U
		10/17/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	**0.416 J**	0.316 U
		11/24/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.0800 J**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**0.288**	0.191 U
		02/05/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.117**	0.0900 UJ	**0.241**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**0.138 J**	**0.321**
		05/12/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**0.223 J**	0.191 U
(dup)		05/12/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 UJ	0.191 U
MW121	8th Ave N ROW, E side	03/28/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**5.82**	0.316 U
		06/20/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.774**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**7.68**	0.316 U
		04/05/18	Peristaltic	0.134 U	0.117 U	0.183 U	**2.93**	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**6.45**	0.316 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
MW121		01/31/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**19.8**	0.316 U
(continued)		04/29/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 UJ	**15.2 J**	0.316 U
		07/19/19	Peristaltic	0.134 U	0.117 UJ	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	**5.04**	0.316 U
		11/30/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.0670 J**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**1.73**	**0.272**
		02/05/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.0460 J**	0.258 U	**0.240**	0.0572 U	0.0612 U	0.0560 U	**0.0530**	0.0200 U	**5.64 J**	**0.247 J**
		05/12/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.484**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**1.79**	**0.346**
	(dup)	05/12/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.0490 J**	**0.473 J**	**0.448**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**1.67**	**0.351**
MW125	Valley Street ROW, N side	03/22/17	Peristaltic	0.134 U	0.117 U	0.183 U	**0.285 J**	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		06/28/17	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/06/18	Peristaltic	0.134 U	0.117 U	0.183 U	**0.580**	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		01/21/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/23/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 UJ	0.118 UJ	0.316 U
		07/18/19	Peristaltic	0.134 U	0.117 UJ	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		10/18/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 UJ	0.130 U	0.118 U	0.316 U
		01/29/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		11/17/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.0910 J**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
		02/02/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.158 J**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	**0.716**
		05/11/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 UJ	0.0273 UJ	0.191 U
	(dup)	05/11/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 UJ	0.0273 UJ	0.191 U
MW-154	Roy St ROW S side	04/30/18	Bladder	0.134 U	0.117 U	0.183 U	**4.46**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.230 J**	0.130 U	**7.48**	0.316 U
		01/21/19	Peristaltic	0.134 U	0.117 U	0.183 U	**1.70**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.330 J**	0.130 U	**3.52**	0.316 U
		04/24/19	Bladder	0.134 U	0.117 U	0.183 U	**1.02**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.214 J**	0.130 UJ	**0.797**	0.316 U
		07/15/19	Bladder	0.134 U	0.117 U	0.183 U	**69.5**	–	0.412 U	0.152 U	0.222 U	0.257 UJ	**5.75**	0.130 UJ	**0.211 J**	0.316 U
		10/14/19	Bladder	0.134 U	0.117 U	0.183 U	**4.99**	–	0.412 U	0.152 U	0.222 U	0.257 UJ	**0.445 J**	0.130 U	0.118 U	0.316 U
		01/21/20	Bladder	0.134 U	0.117 U	0.183 U	**11.6**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.999**	0.130 U	0.118 U	0.316 U
		04/30/20	Bladder	0.125 U	0.118 U	0.127 U	**12.1**	–	0.278 U	0.149 U	0.118 U	0.467 U	**1.06**	0.160 U	0.234 U	0.174 U
		07/10/20	Bladder	0.101 U	0.109 U	0.0620 U	**10.9**	0.0900 U	**0.771**	0.0572 U	0.0612 U	0.0560 UJ	**0.786**	0.0200 U	0.0273 U	0.191 U
		11/09/20	Bladder	0.101 U	0.109 U	0.0620 U	**73.9**	0.0900 U	**0.317**	0.0572 U	0.0612 U	**0.121 J**	**6.84**	0.0200 U	0.0273 U	0.191 U
		02/08/21	Bladder	0.101 U	0.109 U	0.0620 U	**4.72 J**	0.0900 U	**0.794**	0.0572 U	0.0612 U	0.0560 U	**0.501**	0.0200 U	0.0273 U	**0.593**
		05/10/21	Bladder	0.101 U	0.109 U	0.0620 U	**3.41**	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 UJ	**0.453**	0.0200 UJ	0.0273 UJ	0.191 U
MW-155	Roy Street ROW, S side	04/27/18	Peristaltic	0.134 U	0.117 U	0.183 U	**3.48**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.334 J**	0.130 U	**0.447 J**	0.316 U
		01/21/19	Peristaltic	0.134 U	0.117 U	0.183 U	**3.72**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.581**	0.130 U	0.118 U	0.316 U
		04/23/19	Peristaltic	0.134 U	0.117 U	0.183 U	**14.6**	–	0.412 U	0.152 U	0.222 U	0.257 U	**4.75**	0.130 UJ	**6.54 J**	0.316 U
		07/23/19	Bladder	0.134 U	0.117 U	0.183 U	**92.7**	–	0.412 U	0.152 U	0.222 U	0.257 U	**19.9**	0.130 UJ	**0.350 J**	0.316 U
		10/16/19	Bladder	0.134 U	0.117 U	0.183 U	**121**	–	0.412 U	0.160 U	0.222 U	0.257 UJ	**27.6**	0.130 U	0.118 U	0.316 U
		01/20/20	Bladder	0.134 U	0.117 U	0.183 U	**98.3**	–	0.412 U	0.152 U	0.222 U	0.257 U	**21.8**	0.130 U	0.118 U	0.316 U
		05/05/20	Bladder	0.125 U	0.118 U	0.127 U	**140**	–	0.278 U	**0.158 J**	0.118 U	0.467 UJ	**27.3**	0.160 U	0.234 U	0.174 U
		08/03/20	Bladder	0.101 U	0.109 U	0.0620 U	**63.4**	0.0900 U	**0.355**	**0.216**	0.0612 U	0.0560 UJ	**28.0**	0.0200 U	0.0273 U	0.191 U
		11/11/20	Bladder	0.101 U	0.109 U	0.0620 U	**119**	0.0900 U	0.0500 UJ	**0.108 J**	0.0612 U	0.0560 UJ	**26.0**	0.0200 U	**0.190 J+**	0.191 U
MW-159	8th Ave N ROW, E side	04/26/18	Peristaltic	0.134 U	0.117 U	0.183 U	**0.964**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.358 J**	0.130 U	0.118 U	0.316 U
		01/21/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**0.666**	0.316 U
		04/26/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 UJ	**1.03 J**	0.316 U
	(dup)	04/26/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 UJ	**1.04 J**	0.316 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
MW-159		07/22/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**0.691**	0.316 U
(continued)		01/29/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		11/11/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.457 J-**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	**0.214 J+**	0.191 U
		02/08/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.126 J**	0.0900 U	**0.182 J**	0.0572 U	0.0612 U	0.0560 U	**0.0380 J**	0.0200 U	**0.504 J**	**0.486**
		05/11/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 UJ	**0.0360 J**	0.0200 UJ	**0.350 J-**	0.191 U
MW-210[c]	Valley Street ROW, N side	03/30/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 UJ	0.316 U
		06/21/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 UJ	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/09/18	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		10/11/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		01/17/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 UJ	0.316 U
		04/09/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		07/07/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
MW-214	Valley Street ROW, S side	03/30/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
(dup)		03/30/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/09/18	Peristaltic	0.134 U	0.117 U	0.183 U	**0.725**	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		10/11/19	Peristaltic	**0.384 J**	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		01/20/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/07/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		07/06/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	0.0500 U	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	0.191 U
MW-301	Valley Street ROW, S side	11/30/20	Bladder	0.101 U	0.109 U	0.0620 U	**1.96**	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	**0.157**	0.0200 U	0.0273 U	**0.196 J**
(dup)		11/30/20	Bladder	0.101 U	0.109 U	0.0620 U	**1.94**	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	**0.156**	0.0200 U	0.0273 U	**0.202 J**
		02/05/21	Bladder	0.101 U	0.109 U	0.0620 U	**1.62**	**0.558 J-**	**1.44**	0.0572 U	0.0612 U	0.0560 U	**0.101**	0.0200 U	0.0273 U	**1.17**
		05/14/21	Bladder	0.101 U	0.109 U	0.0620 U	**1.85**	0.0900 U	0.0930 U	0.0572 U	0.0612 U	0.0560 U	**0.110**	0.0200 U	0.0273 U	0.191 U
(dup)		05/14/21	Bladder	0.101 U	0.109 U	0.0620 U	**1.81**	**0.398 J**	0.108 U	0.0572 U	0.0612 U	0.0560 U	**0.108**	0.0200 U	0.0273 U	0.191 U
MW-305	Roy St ROW, S side	10/15/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		01/15/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/28/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	0.174 U
		07/27/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.199 J**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	0.191 U
		11/06/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.234**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	0.191 U
		05/18/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.109 J**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 UJ	0.0273 U	0.191 U
MW-310	Alley E of Seattle Roy Aloha Shops	10/10/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		01/14/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/08/20	Peristaltic	**0.354 J**	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		08/04/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.982**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
(dup)		08/04/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.959**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
		11/06/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.348**	0.0572 U	0.0612 U	0.0560 UJ	**0.0554**	0.0200 U	0.0273 UJ	0.191 U
		05/03/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.413**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	**0.909**
MW-312	Alley E of Seattle Roy Aloha Shops	10/11/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		01/21/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**1.22**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	**0.713 J**
		04/22/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	0.174 U
		08/04/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.0690 J**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
		11/11/20	Bladder	0.101 U	0.109 U	0.0620 U	**0.137**	**0.150 J**	**1.12 J-**	0.0572 U	0.0612 U	0.0560 UJ	**0.0407**	0.0200 U	0.0273 U	0.191 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
MW-312 (continued)		05/03/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	**1.33**	**0.748**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	**1.07**
MW-313	Alley E of Seattle Roy Aloha Shops	10/10/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**1.09**	0.316 U
		01/14/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**2.59**	0.316 U
		05/04/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.824**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**0.524**	**0.946**
MW-320	9th Ave N ROW, W side	10/07/19	Peristaltic	**2.82**	0.117 U	**1.89**	0.199 U	–	**0.459 J**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		01/20/20	Peristaltic	**2.96**	0.117 U	**1.54**	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/29/20	Bladder	0.125 U	0.118 U	**0.865**	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	0.174 U
		07/28/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	0.174 U
		11/12/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.338 J-**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	0.191 U
		05/20/21	Peristaltic	**0.207 J**	0.109 U	**1.13**	0.0280 U	0.0900 U	0.0520 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 UJ	0.0273 U	0.191 U
MW-332	Roy St ROW, N side	05/04/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 UJ	0.190 U	0.160 U	0.234 U	0.174 U
		07/30/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	0.0500 U	0.0572 UJ	0.0612 U	0.0560 UJ	0.0160 U	0.0200 UJ	**0.145**	0.191 U
		11/12/20	Bladder	0.101 U	0.109 U	0.0620 U	**0.112**	0.0900 U	**0.584 J-**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**0.102 J+**	0.191 U
		05/20/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0710 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 UJ	0.0273 U	0.191 U
MW-337	Lake Union Park, N end	05/07/20	Peristaltic	0.125 UJ	0.118 U	0.127 UJ	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	0.174 U
		07/23/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.145 J**	0.0572 U	0.0612 U	0.0560 UJ	**0.0260 J**	0.0200 U	0.0273 U	0.191 U
		11/10/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	**0.360 J**	0.0500 U	0.0572 U	0.0612 U	**0.122 J**	0.0160 U	0.0200 U	0.0273 U	0.191 U
		05/04/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**0.0670 J**	0.191 U
MW-339 (dup)	Lake Union Park, S end	05/14/20	Peristaltic	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 UJ	0.190 U	0.160 U	0.234 U	0.174 U
		05/14/20	Peristaltic	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 UJ	0.190 U	0.160 U	0.234 U	0.174 U
		07/23/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 UJ	**0.0280 J**	0.0200 U	0.0273 U	0.191 U
		11/09/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	**0.116 J**	0.0160 U	0.0200 U	0.0273 U	0.191 U
		05/25/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 UJ	0.0273 U	0.191 U
N7	Property, SW quadrant	03/30/17	Peristaltic	0.134 U	0.117 U	0.183 U	**280**	–	0.412 U	**0.396 J**	0.222 U	0.257 U	**50.4**	0.130 U	**0.310 J**	0.316 U
		06/27/17	Peristaltic	0.134 U	0.117 U	0.183 U	**205**	–	0.412 U	**0.955**	0.222 U	0.257 U	**85.1**	0.130 U	**0.386 J**	0.316 U
	Decommissioned March, 2019															
R-MW2	Property, NE quadrant	03/21/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**0.522**	0.316 U
		06/15/17	Peristaltic	**0.180 J**	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**0.609**	0.316 U
		04/02/18	Peristaltic	0.134 U	0.117 U	0.183 U	**0.866**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.620**	0.130 U	**1.33**	0.316 U
	Decommissioned March, 2019															
R-MW3	Property, NE quadrant	03/21/17	Peristaltic	0.134 U	0.117 U	0.183 U	**1.38**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.714**	0.130 U	0.118 U	0.316 U
		06/28/17	Peristaltic	0.134 U	0.117 U	0.183 U	**0.834**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.582**	0.130 U	**0.424 J**	0.316 U
		04/04/18	Peristaltic	0.134 U	0.117 U	0.183 U	**16.4**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.972**	0.130 U	**0.214 J**	0.316 U
	Decommissioned March, 2019															
R-MW5	Dexter Ave N ROW, E side	03/23/17	Peristaltic	0.134 U	0.117 U	0.183 U	**0.338 J**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.186 J**	0.130 U	0.118 U	0.316 U
		06/16/17	Bladder	0.134 U	0.117 U	0.183 U	**0.257 J**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.245 J**	0.130 U	0.118 U	0.316 U
		04/11/18	Bladder	0.134 U	0.117 U	0.183 U	**0.621**	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		01/03/19	Peristaltic	0.134 U	0.117 U	0.183 U	**0.477 J**	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/22/19	Peristaltic	0.134 U	0.117 U	0.183 U	**0.499 J**	–	**0.428 J**	0.152 U	0.222 U	0.257 U	**0.155 J**	0.130 UJ	0.118 UJ	0.316 U
		07/16/19	Bladder	0.134 U	0.117 U	0.183 U	**0.736**	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 UJ	0.118 U	0.316 U
		10/21/19	Bladder	0.134 U	0.117 U	0.183 U	**0.523**	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		01/24/20	Bladder	0.134 U	0.117 U	0.183 U	**0.931**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.374 J**	0.130 U	0.118 U	0.316 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
R-MW5		11/18/20	Bladder	0.101 U	0.109 U	0.0620 U	**0.607**	**0.166 J**	**0.205**	0.0572 U	0.0612 U	0.0560 U	**0.318**	0.0200 U	0.0273 U	0.191 U
(continued)		02/11/21	Bladder	0.101 U	0.109 U	0.0620 U	**0.741**	0.224 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	**0.271**	0.0200 U	0.0273 U	0.191 U
(dup)		02/11/21	Bladder	0.101 U	0.109 U	0.0620 U	**0.990**	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	**0.286**	0.0200 U	0.0273 U	0.191 U
		05/17/21	Bladder	0.101 U	0.109 U	0.0620 U	**0.671**	0.0900 U	**0.147 J**	0.0572 U	0.0612 U	0.0560 U	**0.232**	0.0200 U	0.0273 U	0.191 U
R-MW6	8th Ave N ROW, E side	03/21/17	Peristaltic	0.134 U	0.117 U	0.183 U	**1.08**	–	0.412 U	**0.242 J**	0.222 U	0.257 U	**3.17**	0.130 U	**8.65**	0.316 U
		06/20/17	Peristaltic	0.134 U	0.117 U	0.183 U	**1.19**	–	**0.619**	**0.445 J**	0.222 U	0.257 U	**0.878**	0.130 U	**43.9**	0.316 U
		04/06/18	Peristaltic	0.134 U	0.117 U	0.183 U	**1.85**	–	0.412 U	**0.277 J**	0.222 U	0.257 U	**2.24**	0.130 U	**26.9**	0.316 U
		01/25/19	Peristaltic	0.134 U	0.117 U	0.183 U	**0.328 J**	–	0.412 U	0.152 U	0.222 U	0.257 U	**1.07**	0.130 U	**9.14**	0.316 U
		04/25/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**0.168 J**	0.222 U	0.257 U	**0.370 J**	0.130 UJ	**7.16 J**	0.316 U
		12/01/20	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.670**	**0.476 J**	**0.336**	0.0572 U	0.0612 U	0.0560 UJ	**1.07**	0.0200 UJ	**0.583**	**0.513**
		02/03/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.371**	0.0900 U	**0.198 J**	0.0572 U	0.0612 U	0.0560 U	**0.341**	0.0200 U	**0.248**	**0.550**
		05/17/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.0670 J**	0.0900 U	**1.02**	**0.0930 J**	0.0612 U	0.0560 U	**0.349**	0.0200 UJ	**2.86**	**0.696**
SCL-MW101	Alley E of Seattle Roy Aloha Shops	03/28/17	Peristaltic	**7.33**	0.117 U	0.183 U	0.199 U	–	0.624 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	**2.08**
		06/14/17	Peristaltic	**8.01**	0.117 U	**0.219 J**	0.199 U	–	**1.68**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	**3.50**
		04/06/18	Peristaltic	**10.1**	0.117 U	**0.248 J**	0.199 U	–	**1.24**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	**3.32**
		10/09/19	Peristaltic	**14.4**	0.117 U	**0.365 J**	0.199 U	–	**2.39**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	**3.77**
		01/17/20	Peristaltic	**15.6**	0.117 U	0.183 U	0.199 U	–	**0.611**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 UJ	**3.66**
		04/07/20	Peristaltic	**5.16**	0.117 U	**0.186 J**	0.199 U	–	**0.868**	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	**1.74**
		11/24/20	Peristaltic	**13.6**	0.109 U	**0.290**	0.0280 U	0.0900 U	**1.24**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	**3.95**
		05/04/21	Peristaltic	**5.17**	0.109 U	**0.168 J**	0.0280 U	0.0900 U	**0.395**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	**1.48**
SCL-MW105	Alley E of Seattle Roy Aloha Shops	03/28/17	Peristaltic	**3.67**	0.585 U	0.915 U	0.995 U	–	**16.3**	0.760 U	1.11 U	1.28 U	0.765 U	0.650 U	0.590 U	**33.9**
		06/15/17	Peristaltic	**4.25**	0.117 U	0.183 U	0.199 U	–	**14.3**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	**40.8**
		04/06/18	Peristaltic	**2.31 J**	1.17 U	1.83 U	1.99 U	–	**12.1**	1.52 U	2.22 U	2.57 U	1.53 U	1.30 U	1.18 U	**28.4**
		10/10/19	Peristaltic	**8.08**	0.117 U	**0.260 J**	0.199 U	–	**15.5**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	**34.6**
		01/17/20	Peristaltic	**5.10**	0.117 U	0.183 U	0.199 U	–	**14.9**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 UJ	**28.6**
		04/01/20	Peristaltic	**3.00**	0.117 U	0.183 U	0.199 U	–	**11.3**	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	**23.4**
		07/24/20	Peristaltic	**4.48**	0.109 U	**0.192 J**	0.0280 U	0.0900 UJ	**12.0**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	**22.5**
SCS-2	Seattle Roy Aloha Shops, N End	03/20/17	Peristaltic	**2.02**	0.117 U	0.183 U	0.199 U	–	**9.54**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	**181**
		06/12/17	Peristaltic	**1.78**	0.117 U	0.183 U	0.199 U	–	**4.49**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	**70.4**
		04/13/18	Peristaltic	**2.09**	0.117 U	0.183 U	0.199 U	–	**5.18**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	**47.7**
		07/18/19	Peristaltic	**2.39**	0.117 U	0.183 U	0.199 U	–	**3.71**	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	**149**
(dup)		07/18/19	Peristaltic	**2.44**	0.117 U	0.183 U	0.199 U	–	**3.37**	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	**0.242 J**	**131**
		10/10/19	Peristaltic	**2.75**	0.117 U	0.183 U	0.199 U	–	**6.00**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	**123**
		01/16/20	Peristaltic	1.34 U	1.17 U	1.83 U	1.99 U	–	**5.00 J**	1.52 U	2.22 U	2.57 U	1.53 U	1.30 U	1.18 U	**32.2**
Intermediate A Water-Bearing Zone																
BB-8	Roy Street ROW, S side	03/22/17	Peristaltic	0.134 U	0.117 U	0.183 U	**30.4**	–	0.412 U	0.152 U	0.222 U	0.257 U	**4.95**	0.130 U	0.118 U	0.316 U
		06/14/17	Peristaltic	0.134 U	0.117 U	0.183 U	**26.0**	–	0.412 U	**0.155 J**	0.222 U	0.257 U	**8.57**	0.130 U	0.118 U	0.316 U
		04/11/18	Peristaltic	0.134 U	0.117 U	0.183 U	**33.7 J**	–	0.412 U	0.152 U	0.222 U	0.257 U	**6.13 J**	0.130 U	0.118 U	0.316 U
(dup)		04/11/18	Peristaltic	0.134 U	0.117 U	0.183 U	**46.8 J**	–	0.412 U	0.152 U	0.222 U	0.257 U	**8.41 J**	0.130 U	0.118 U	0.316 U
		01/23/19	Peristaltic	0.134 U	0.117 U	0.183 U	**133**	–	0.412 U	**0.402 J**	0.222 U	0.257 U	**43.1**	0.130 U	**0.618**	0.316 U
		04/23/19	Peristaltic	0.134 U	0.117 U	0.183 U	**48.8**	–	0.412 U	0.152 U	0.222 U	0.257 U	**9.09**	0.130 UJ	0.118 UJ	0.316 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
BB-8		07/17/19	Bladder	0.134 U	0.117 U	0.183 U	**169**	–	0.412 U	**0.262 J**	0.222 U	0.257 UJ	**28.9**	0.130 U	0.118 U	0.316 U
(continued)		10/22/19	Bladder	0.134 U	0.117 U	0.183 U	**135**	–	0.412 U	**0.398 J**	0.222 U	0.257 UJ	**46.6**	0.130 U	**0.162 J**	0.316 U
(dup)		10/22/19	Bladder	0.134 U	0.117 U	0.183 U	**169**	–	0.412 U	**0.426 J**	0.222 U	0.257 UJ	**48.3**	0.130 U	**0.152 J**	0.316 U
		01/20/20	Bladder	0.134 U	0.117 U	0.183 U	**138**	–	0.412 U	**0.232 J**	0.222 U	0.257 U	**25.4**	0.130 U	0.118 U	0.316 U
(dup)		01/20/20	Bladder	0.134 U	0.117 U	0.183 U	**132**	–	0.412 U	**0.199 J**	0.222 U	0.257 U	**24.6**	0.130 U	0.118 U	0.316 U
		05/12/20	Bladder	0.125 U	0.118 U	0.127 U	**142**	–	**0.682**	**0.282 J**	0.118 U	0.467 U	**30.8**	0.160 U	0.234 U	**0.387 J**
		07/27/20	Bladder	0.101 U	0.109 U	0.0620 U	**165**	0.0900 UJ	**0.268 J**	**0.531**	0.0612 U	0.0560 UJ	**46.8**	0.0200 U	0.0273 U	**0.217 J**
(dup)		07/27/20	Bladder	0.101 U	0.109 U	0.0620 U	**162**	0.0900 UJ	**0.470 J**	**0.496**	0.0612 U	0.0560 UJ	**45.5**	0.0200 U	**0.194**	**0.306**
		11/17/20	Bladder	0.101 U	0.109 U	0.0620 U	**215**	0.0900 UJ	**0.339**	**0.802**	0.0612 U	0.0560 U	**107 J+**	0.0200 U	**0.302**	0.191 U
		02/11/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**20.1**	0.0900 U	**1.58**	0.0572 U	0.0612 U	0.0560 U	**3.83**	0.0200 U	0.0273 U	**1.28**
		06/07/21	Bladder	0.101 U	0.109 U	0.0620 U	**54.4**	0.0900 U	0.0500 U	**0.0980 J**	0.0612 U	0.0560 U	**12.3**	0.0200 U	**0.0790 J**	0.191 U
DMW-3IA	615 Dexter, NE quadrant	03/18/20[a]	Unknown	–	–	–	0.20 U	–	0.20 U	0.20 U	–	–	0.20 U	0.20 UJ	0.20 U	0.40 U
FMW-142	9th Ave N ROW, E side	07/29/19[b]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	**0.38**	–	0.20 U	–
		10/31/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		01/22/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/28/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	0.174 U
		07/08/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**1.37**	0.0572 U	0.0612 UJ	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	0.191 U
		11/04/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.179 J**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	0.191 U
		05/25/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	**0.221 J**	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 UJ	0.0273 U	0.191 U
GEI-1	Block 37, SW quadrant	03/24/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		06/13/17	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/22/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 UJ	0.118 UJ	0.316 U
		07/16/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 UJ	0.118 U	0.316 U
		10/21/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		01/22/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/29/20	Peristaltic	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	**0.254 J**
(dup)		04/29/20	Peristaltic	0.125 U	0.118 U	0.127 U	0.300 U	–	**0.286 J**	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	0.174 U
		07/30/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.142 J**	0.0572 UJ	0.0612 U	0.0560 UJ	0.0160 U	0.0200 UJ	0.0273 U	0.191 U
GEI-MW-1	Block 79 East, N end	01/23/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.230 J**	0.130 U	0.118 U	0.316 U
		04/29/20	Peristaltic	0.125 U	0.118 U	0.127 U	0.300 U	–	**1.06**	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	**0.938 J**
		08/07/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.162 J**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
		11/10/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.435 J-**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	**0.316**
		05/13/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
HC-4	601 Dexter, NE quadrant	04/12/19[a]	Unknown	–	–	–	1.0 U	–	1.0 U	1.0 U	–	–	1.0 U	1.0 U	0.20 U	1.0 U
HMW-2IA	SDOT Mercer Parcels, NE quadrant	03/25/19[a]	Peristaltic	1.0 U	1.0 U	1.0 U	**240**	–	1.0 U	1.0 U	1.0 U	1.0 U	**74**	1.0 U	**1.2**	1.0 U
		03/12/20[a]	Unknown	–	–	–	**210**	–	2.0 U	2.0 U	–	–	**69**	2.0 UJ	2.0 U	4.0 U
HMW-3IA	SDOT Mercer Parcels, NW quadrant	03/25/19[a]	Peristaltic	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	0.20 U	1.0 U
		03/13/20[a]	Unknown	–	–	–	0.20 U	–	0.20 U	0.20 U	–	–	0.20 U	0.20 UJ	0.20 U	0.40 U
HMW-6IA	SDOT Mercer Parcels, SW quadrant	03/13/20[a]	Unknown	–	–	–	0.20 U	–	0.20 U	0.20 U	–	–	0.20 U	0.20 UJ	0.20 U	0.40 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
HMW-9IA	SDOT Mercer Parcels, SW quadrant	03/19/20[a]	Unknown	–	–	–	**0.42**	–	0.20 U	0.20 U	–	–	**0.23**	0.20 UJ	**0.95**	0.40 U
		06/02/21	Bladder	0.101 U	0.109 U	0.0620 U	**0.243**	0.0900 U	**0.0850 J**	**0.197 J**	0.0612 U	0.0560 U	**0.916**	0.0200 U	**196**	0.191 U
HMW-20IA	SDOT Mercer Parcels, NW quadrant	09/18/20[a]	Unknown	–	1.0 U	0.20 U	**5.5**	–	0.20 U	**2.5**	1.0 U	–	**18**	0.20 U	**520**	0.40 U
		06/02/21	Bladder	0.101 U	0.109 U	0.0620 U	**1.37**	0.0900 U	**0.152 J**	**17.1**	0.0612 U	0.0560 U	**31.9**	0.0200 U	**5,940**	0.191 U
MW107	8th Ave N ROW, W side	03/27/17	Peristaltic	0.134 U	0.117 U	0.183 U	**0.224 J**	–	**0.690 J**	**14.0**	0.222 U	0.257 U	**0.370 J**	0.130 U	**34.5**	0.316 U
		06/19/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.700**	**12.6**	0.222 U	0.257 U	**0.290 J**	0.130 U	**15.0**	0.316 U
		04/09/18	Peristaltic	0.134 U	0.117 U	0.183 U	**0.879 J-**	–	0.412 U	**10.5**	0.222 U	0.257 U	**0.581 J-**	0.130 U	**123**	0.316 U
		01/30/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.715 J+**	**14.4**	0.222 U	0.257 U	**41.1**	0.130 U	**474**	0.316 U
		05/01/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**14.1**	0.222 U	0.257 U	**99.9**	0.130 UJ	**374**	0.316 U
		07/22/19	Bladder	0.134 U	0.117 U	0.183 U	1.99 U	–	**0.758**	**7.08**	0.222 U	0.257 U	**2.62 J**	0.130 UJ	**307**	**0.609 J**
		10/15/19	Bladder	0.134 U	0.117 U	0.183 U	**41.7**	–	**0.572**	**7.04**	0.222 U	0.257 UJ	**138**	0.130 U	**216**	0.316 U
		01/28/20	Bladder	2.68 U	2.34 U	3.66 U	3.98 U	–	8.24 U	**22.2**	4.44 U	5.14 U	**168**	2.60 U	**674**	6.32 U
		04/03/20	Bladder	0.134 U	0.117 U	0.183 U	**63.8**	–	0.412 U	**15.4**	0.222 U	0.257 U	**700**	0.130 U	**216**	0.316 U
		07/31/20	Bladder	2.53 U	2.73 U	1.55 U	0.700 U	**5.86 J**	1.25 U	**5.36 J**	1.53 U	1.40 UJ	**6.98**	0.500 UJ	**378**	4.78 U
		12/01/20	Peristaltic	2.53 U	2.73 U	1.55 U	0.700 U	**124**	**4.45 J**	**5.85**	1.53 U	1.40 U	0.400 U	0.500 U	0.682 U	**4.81 J**
		02/02/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.0510 J**	**46.0**	**0.704**	**6.09**	0.0612 U	0.0560 U	**0.266**	0.0200 U	**1.80**	**1.04**
		06/02/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.0590 J**	**32.2**	**0.580**	**3.98**	0.0612 U	0.0560 U	**0.336**	0.0200 U	**1.16**	0.191 U
MW108	Alley E of Seattle Roy Aloha Shops	03/28/17	Peristaltic	0.134 U	0.117 U	0.183 U	**73.1**	–	0.479 U	**0.899**	0.222 U	0.257 U	**12.5**	0.130 U	**52.3**	0.316 U
		06/27/17	Bladder	0.134 U	0.117 U	0.183 U	**194**	–	0.479 U	**0.748**	0.222 U	0.257 U	**22.1**	0.130 U	**52.8**	0.316 U
		04/06/18	Peristaltic	0.134 U	0.117 U	0.183 U	**1,970**	–	**0.599**	**7.13**	0.222 U	0.257 U	**284**	0.130 U	**217**	0.316 U
(dup)		04/06/18	Peristaltic	0.134 U	0.117 U	0.183 U	**1,980**	–	**0.597**	**7.91**	0.222 U	0.257 U	**287**	0.130 U	**231**	0.316 U
		01/22/19	Peristaltic	0.134 U	0.117 U	0.183 U	**4,190**	–	**0.562**	**6.03**	0.222 U	0.257 U	**587**	0.130 U	**90.8**	0.316 U
		04/29/19	Peristaltic	0.134 U	0.117 U	0.183 U	**419**	–	0.412 U	**3.22**	0.222 U	0.257 U	**171**	0.130 UJ	**125 J**	0.316 U
		07/15/19	Peristaltic	0.134 U	0.117 U	0.183 U	**567**	–	0.412 U	**3.48**	0.222 U	0.257 UJ	**189**	0.130 UJ	**197**	0.316 U
		10/10/19	Peristaltic	0.134 U	0.117 U	0.183 U	**524**	–	0.412 U	**5.55**	0.222 U	0.257 U	**483**	0.130 U	**194**	0.316 U
		01/14/20	Peristaltic	3.35 U	2.93 U	4.58 U	**243**	–	10.3 U	3.80 U	5.55 U	6.43 U	**235**	3.25 U	**224**	7.90 U
		04/22/20	Bladder	3.13 U	2.95 U	3.18 U	**53.1**	–	6.95 U	3.73 U	2.95 U	11.7 U	**96.3**	4.00 U	**19.3**	4.35 U
		07/16/20	Bladder	2.53 U	2.73 U	1.55 U	**189**	**5.98 J**	**1.73 J**	**1.88 J**	1.53 U	1.40 UJ	**162**	0.500 U	**11.3**	4.78 U
(dup)		07/16/20	Bladder	0.101 U	0.109 U	0.0620 U	**226 J**	0.0900 U	**2.20**	**2.37**	0.0612 U	0.0560 UJ	**170**	0.0200 U	**16.5**	**3.06**
		11/04/20	Bladder	2.53 U	2.73 U	1.55 U	**10.2**	2.25 UJ	**2.12 J**	1.43 U	1.53 U	1.40 UJ	**32.6**	0.500 U	**107**	**6.15 J**
		02/09/21	Peristaltic	0.505 U	0.545 U	0.310 U	**238 J**	0.450 U	**0.440 J**	**1.48**	0.306 U	0.280 U	**106**	0.100 U	**172 J**	0.955 U
		05/03/21	Peristaltic	0.505 U	0.545 U	0.310 U	**182**	0.450 U	**0.290 J**	**1.92**	0.306 U	0.280 U	**91.9**	0.100 U	**140**	0.955 U
MW109	Alley E of Seattle Roy Aloha Shops	03/29/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.198 J**	0.130 U	**3.49**	0.316 U
		06/27/17	Bladder	0.134 U	0.117 U	0.183 U	**9.69 J**	–	0.412 U	**1.17**	0.222 U	0.257 U	**141**	0.130 U	**6.06**	0.316 U
		04/06/18	Peristaltic	0.134 U	0.117 U	0.183 U	1.99 UJ	–	0.412 U	**3.34**	0.222 U	0.257 U	**210**	0.130 U	**42.2**	0.316 U
		01/23/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.995 U	–	0.412 U	**2.08**	0.222 U	0.257 U	**43.8**	0.130 U	**36.8**	0.316 U
		04/29/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 UJ	**3.06 J**	0.316 U
		07/15/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**0.199 J**	0.222 U	0.257 UJ	**0.265 J**	0.130 UJ	**24.4**	0.316 U
		10/15/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**0.891**	0.222 U	0.257 UJ	**1.03**	0.130 U	**109**	0.316 U
		01/21/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.782**	0.152 U	0.222 U	0.257 U	**0.372 J**	0.130 U	**1.02**	0.316 U
		04/22/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	**0.229 J**	0.118 U	0.467 U	0.190 U	0.160 U	**15.2**	0.174 U
		07/06/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.967**	**0.293**	0.0612 U	0.0560 UJ	**0.162**	0.0200 U	**12.4**	0.191 U
		11/02/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.105 J**	**0.220**	0.0612 U	0.0560 U	**0.126**	0.0200 U	**14.5**	0.191 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
MW109		02/09/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.634**	**0.125 J**	0.0612 U	0.0560 U	**0.0860**	0.0200 U	**13.7 J**	**0.791**
(continued)		05/03/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.751**	0.0572 U	0.0612 U	0.0560 U	**0.0550**	0.0200 U	**3.49**	**0.987**
MW110	Alley E of Seattle	03/23/17	Peristaltic	0.134 U	0.117 U	0.183 U	**1,070**	–	0.412 U	**4.72**	0.222 U	0.257 U	**389**	0.130 U	**1.45**	0.316 U
	Roy Aloha Shops	06/27/17	Bladder	0.134 U	0.117 U	0.183 U	**259**	–	0.412 U	**2.66**	0.222 U	0.257 U	**176**	0.130 U	**152**	0.316 U
		04/09/18	Bladder	0.134 U	**0.164 J**	0.183 U	**375 J-**	–	0.412 U	**3.72**	0.222 U	0.257 U	**253 J-**	0.130 U	**3.54**	0.316 U
		01/23/19	Peristaltic	0.134 U	0.117 U	0.183 U	**1,260**	–	0.412 U	**5.83**	0.222 U	0.257 U	**490**	0.130 U	**1.39**	0.316 U
(dup)		01/23/19	Peristaltic	0.134 U	0.117 U	0.183 U	**1,120**	–	0.412 U	**6.49**	0.222 U	0.257 U	**499**	0.130 U	**1.51**	0.316 U
		04/26/19	Bladder	0.134 U	0.117 U	0.183 U	**1,500**	–	0.412 U	**5.59**	0.222 U	0.257 U	**613**	0.130 UJ	**0.900 J**	0.316 U
		07/15/19	Bladder	0.134 U	0.117 U	0.183 U	**1,220**	–	0.412 U	**5.87**	0.222 U	0.257 UJ	**455**	0.130 UJ	**1.26**	0.316 U
		10/15/19	Bladder	0.134 U	0.117 U	0.183 U	**1,180**	–	0.412 U	**3.86**	0.222 U	0.257 UJ	**498**	0.130 U	**0.853**	0.316 U
		01/16/20	Bladder	0.670 U	0.585 U	0.915 U	**459**	–	2.06 U	**1.95 J**	1.11 U	1.29 U	**176**	0.650 U	**0.706 J**	1.58 U
		04/22/20	Bladder	0.625 U	0.590 U	0.635 U	**946**	–	1.39 U	**4.25**	0.590 U	2.34 U	**384**	0.800 U	**5.06**	0.870 U
		07/16/20	Bladder	0.505 U	0.545 U	0.310 U	**741**	**1.73 J**	**0.465 J**	**7.79**	0.306 U	0.280 UJ	**349**	0.100 U	**12.5**	0.955 U
		11/04/20	Bladder	5.05 U	5.45 U	3.10 U	**640**	4.50 UJ	2.50 U	**2.96 J**	3.06 U	2.80 UJ	**343**	1.00 U	**29.6**	9.55 U
		02/09/21	Bladder	0.101 U	0.109 U	0.0620 U	**602**	**0.805**	**0.784**	**2.99**	0.0612 U	0.0560 U	**302 J+**	0.0200 U	**0.833 J**	**0.791**
		05/04/21	Bladder	1.01 U	1.09 U	0.620 U	**484**	**1.50 J**	**0.730 J**	**2.27**	0.612 U	0.560 U	**214**	0.200 U	0.273 U	1.91 U
MW115	9th Ave N ROW,	03/22/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**15.7**	0.316 U
	W side	06/22/17	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**8.45**	0.316 U
		04/11/18	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**5.81**	0.316 U
		01/30/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**12.4**	0.316 U
		07/17/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	**24.3**	0.316 U
		10/22/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	**23.2**	0.316 U
		01/20/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**26.9**	0.316 U
		05/05/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 UJ	0.190 U	0.160 U	**8.86**	0.174 U
		07/28/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	**1.16**	0.174 U
		11/12/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.221 J-**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	**0.808 J+**	0.191 U
		02/12/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.515**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**1.02**	**0.453**
		05/25/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0540 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 UJ	**0.989**	0.191 U
MW116	9th Ave N ROW,	03/21/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
	W side	06/16/17	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.303 J**	0.130 U	0.118 U	0.316 U
		04/11/18	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		01/30/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		07/17/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		10/31/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		01/21/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.775**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	**0.351 J**
		04/29/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	0.174 U
		07/28/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	0.174 U
		11/12/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 UJ	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	0.191 U
		02/11/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.0480 J**	0.0900 UJ	**1.23**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	**0.968**
		05/25/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0560 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 UJ	0.0273 U	0.191 U
MW119	9th Ave N ROW,	03/29/17	Peristaltic	0.134 U	0.117 U	0.183 U	**5.47**	–	0.412 U	**0.334 J**	0.222 U	0.257 U	**10.7**	0.130 U	**0.272 J**	0.316 U
	W side	06/28/17	Bladder	0.134 U	0.117 U	0.183 U	**19.0**	–	**0.726**	**0.167 J**	0.222 U	0.257 U	**12.4**	0.130 U	0.118 U	**0.562 J**
		04/05/18	Peristaltic	0.134 U	0.117 U	0.183 U	**2.14**	–	0.412 U	**0.203 J**	0.222 U	0.257 U	**3.02**	0.130 U	0.118 U	0.316 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
MW119		01/21/19	Peristaltic	0.134 U	0.117 U	0.183 U	**1.24**	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
(continued)		04/29/19	Peristaltic	0.134 U	0.117 U	0.183 U	**0.224 J**	–	0.412 U	**0.161 J**	0.222 U	0.257 U	**1.12**	0.130 UJ	0.118 UJ	0.316 U
		07/19/19	Peristaltic	0.134 U	0.117 UJ	0.183 U	**0.303 J**	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		10/10/19	Peristaltic	0.134 U	0.117 U	0.183 U	**0.876**	–	0.412 U	**0.159 J**	0.222 U	0.257 U	**7.54**	0.130 U	0.118 U	0.316 U
		11/11/19[v]	Peristaltic	–	–	–	**3.7**	–	–	0.20 U	–	–	**9.5**	–	0.20 U	–
		01/14/20	Peristaltic	0.134 U	0.117 U	0.183 U	**5.90**	–	0.412 U	0.152 U	0.222 U	0.257 U	**5.81**	0.130 U	0.118 U	0.316 U
(split)		01/14/20[v]	Peristaltic	–	–	–	**4.8**	–	–	0.20 U	–	–	**5.1**	–	0.20 U	–
		02/18/20[n]	Unknown	–	–	–	**1.3**	–	–	0.20 U	–	–	**2.5**	–	0.20 U	–
		03/24/20[v]	Unknown	–	–	–	**0.24**	–	–	0.20 U	–	–	**0.87**	–	0.20 U	–
		04/27/20	Peristaltic	0.125 U	0.118 UJ	0.127 U	**0.595**	–	0.278 U	0.149 U	0.118 U	0.467 UJ	**1.62**	0.160 U	0.234 U	0.174 U
		05/19/20[n]	Unknown	–	–	–	**0.91**	–	–	0.20 U	–	–	**2.8**	–	0.20 U	–
		07/08/20	Bladder	0.101 U	0.109 U	0.0620 U	**0.306**	**0.227**	**0.644**	**0.163**	0.0612 U	0.0560 UJ	**1.96**	0.0200 U	**0.0480 J**	0.191 U
		07/28/20[n]	Unknown	–	–	–	**0.92**	–	–	0.20 U	–	–	**2.6**	–	0.20 U	–
		09/17/20[n]	Unknown	–	–	–	**0.27**	–	–	0.20 U	–	–	**1.8**	–	0.20 U	–
		11/11/20	Bladder	0.101 U	0.109 U	0.0620 U	**0.420**	0.0900 U	0.0500 UJ	**0.0983 J**	0.0612 U	0.0560 UJ	**2.63**	0.0200 U	**0.212 J+**	0.191 U
		12/03/20[n]	Unknown	–	–	–	**0.28**	–	–	0.20 U	–	–	**1.2**	–	0.20 U	–
		02/10/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.0410 J**	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	**0.511**	0.0200 U	**0.134**	0.191 U
(split)		02/10/21[n]	Peristaltic	–	–	–	0.20 U	–	–	0.20 U	–	–	**0.46**	–	0.20 U	–
		05/20/21	Bladder	0.101 U	0.109 U	0.0620 U	**0.210**	0.353 U	0.0710 U	**0.165 J**	0.0612 U	0.0560 U	**1.70**	0.0200 UJ	**0.252**	0.191 U
MW120	8th Ave N ROW, E side	03/28/17	Peristaltic	0.134 U	0.117 U	0.183 U	**13.9**	–	0.458 U	0.152 U	0.222 U	0.257 U	**5.81**	0.130 U	**0.871**	0.316 U
		06/28/17	Bladder	0.134 U	0.117 U	0.183 U	**18.0**	–	0.412 U	0.152 U	0.222 U	0.257 U	**6.97**	0.130 U	**0.988**	0.316 U
		04/09/18	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		01/24/19	Peristaltic	0.134 U	0.117 U	0.183 U	**125**	–	0.412 U	**0.194 J**	0.222 U	0.257 U	**34.3**	0.130 U	**1.64**	0.316 U
		05/03/19	Peristaltic	0.134 U	0.117 U	0.183 U	**155**	–	0.412 U	**0.258 J**	0.222 U	0.257 U	**46.9**	0.130 U	**1.28**	0.316 U
(dup)		05/03/19	Peristaltic	0.134 U	0.117 U	0.183 U	**182**	–	0.412 U	**0.227 J**	0.222 U	0.257 U	**51.1**	0.130 U	**1.30**	0.316 U
		07/16/19	Peristaltic	0.134 U	0.117 U	0.183 U	**134**	–	0.412 U	**0.217 J**	0.222 U	0.257 UJ	**40.1**	0.130 UJ	**1.01**	0.316 U
		10/17/19	Bladder	0.134 U	0.117 U	0.183 U	**61.5**	–	0.412 U	**0.220 J**	0.222 U	0.257 U	**22.3**	0.130 U	**2.31**	0.316 U
(dup)		10/17/19	Bladder	0.134 U	0.117 U	0.183 U	**73.9**	–	0.412 U	**0.243 J**	0.222 U	0.257 UJ	**26.9**	0.130 U	**2.25**	0.316 U
		01/17/20	Bladder	0.134 U	0.117 U	0.183 U	**61.2**	–	0.412 U	**0.241 J**	0.222 U	0.257 U	**21.6**	0.130 U	**2.38 J**	0.316 U
		04/23/20	Bladder	0.125 U	0.118 U	0.127 U	**39.7**	–	0.278 U	**0.154 J**	0.118 U	0.467 U	**15.4**	0.160 U	**2.92**	0.174 U
		07/14/20	Bladder	0.101 U	0.109 U	0.0620 U	**44.0**	**0.154 J**	**0.511**	**0.249**	0.0612 U	0.0560 UJ	**16.2**	0.0200 U	**2.78**	0.191 U
		11/30/20	Bladder	0.101 U	0.109 U	0.0620 U	**39.3**	0.0900 U	**0.208**	**0.188 J**	0.0612 U	0.0560 U	**15.6**	0.0200 U	**1.47**	**0.435**
(dup)		11/30/20	Bladder	0.101 U	0.109 U	0.0620 U	**44.4**	0.0900 U	**0.172 J**	**0.196 J**	0.0612 U	0.0560 U	**16.2**	0.0200 U	**1.52**	**0.376**
		02/05/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**41.6**	0.251 U	**0.332**	**0.212 J**	0.0612 U	0.0560 U	**17.4**	0.0200 U	**1.17 J**	**0.516**
		05/12/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**31.7**	–	**0.137 J**	**0.151 J**	0.0612 U	0.0560 U	**13.8**	0.0200 U	**0.633**	0.191 U
MW127	8th Ave N ROW, E side	08/01/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		10/17/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		01/17/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.689**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 UJ	**0.342 J**
		04/23/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	0.174 U
		07/14/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	**0.274 J**	**0.360**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	**0.0790 J**	0.191 U
(dup)		07/14/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	**0.304 J**	**0.375**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	**0.0730 J**	0.191 U
		11/13/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.0726 J**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	0.191 U
		05/11/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0740 U	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 UJ	0.0273 UJ	0.191 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
MW131	Property, SE quadrant	03/27/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.462 J**	**0.981**	0.222 U	0.257 U	0.153 U	0.130 U	**804**	0.316 U
		06/20/17	Peristaltic	0.670 U	0.585 U	0.915 U	0.995 U	–	2.06 U	0.760 U	1.11 U	1.28 U	0.765 U	0.650 U	**435**	1.58 U
		04/16/18	Peristaltic	0.134 U	0.117 U	0.183 U	**7.05**	–	0.412 U	**0.276 J**	0.222 U	0.257 U	**3.25**	0.130 U	**18.0**	0.316 U
		10/25/18	Peristaltic	0.134 U	0.117 U	0.183 U	**0.895**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.347 J**	0.130 U	**1.83**	0.316 U
		12/12/18	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.172 J**	0.130 U	**1.39**	0.316 U
		01/29/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.516 J+**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**0.539**	0.316 U
		03/11/19	Peristaltic	0.134 U	**0.145 J**	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
	Decommissioned March, 2019															
MW-142	8th Ave N ROW, E side	04/27/18	Peristaltic	0.134 U	0.117 U	0.183 U	**0.523**	–	0.412 U	**0.474 J**	0.222 U	0.257 U	**1.40**	0.130 U	**17.2 J**	0.316 U
		01/28/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**3.45**	0.316 U
(dup)		01/28/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.208 J**	0.130 U	**3.38**	0.316 U
		04/24/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.156 J**	0.130 UJ	**4.39 J**	0.316 U
		07/25/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**0.169 J**	0.222 U	0.257 U	**0.218 J**	0.130 U	**6.57**	0.316 U
		10/16/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.282 U	0.222 U	0.257 UJ	**0.360 J**	0.130 U	**11.3**	0.316 U
		01/22/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**0.379 J**	0.222 U	0.257 U	**0.311 J**	0.130 U	**8.19**	0.316 U
		04/24/20	Bladder	0.125 U	0.118 UJ	0.127 U	0.300 U	–	0.278 U	**0.454 J**	0.118 U	0.467 UJ	**0.206 J**	0.160 U	**9.14**	0.174 U
		07/30/20	Bladder	0.101 U	0.109 U	0.0620 U	**3.34**	0.0900 UJ	**0.0790 J**	**0.472 J**	0.0612 U	0.0560 UJ	**9.74**	0.0200 UJ	**6.05**	0.191 U
		11/24/20	Bladder	0.101 U	0.109 U	0.0620 U	**0.164**	**2.53**	0.0850 U	**0.734**	0.0612 U	0.0560 U	**24.5**	0.0200 U	**34.6**	0.258 U
(dup)		11/24/20	Bladder	0.101 U	0.109 U	0.0620 U	**0.163**	**2.81 J+**	0.0930 U	**0.827**	0.0612 U	0.0560 U	**22.2**	0.0200 U	**46.1**	**0.265**
		02/08/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.0940 J**	**14.6**	**1.42**	**0.498**	0.0612 U	0.0560 U	**1.11**	0.0200 U	**33.9 J**	**1.18**
		05/19/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	**7.95 J+**	0.143 U	**0.361**	0.0612 U	0.0560 U	**0.243**	0.0200 UJ	**10.1**	**0.343**
MW-144	8th Ave N ROW, E side	04/27/18	Peristaltic	0.134 U	0.117 U	0.183 U	**1.86**	–	**1.40**	**4.65**	0.222 U	0.257 U	**3.31**	0.130 U	**888**	0.316 U
		01/28/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**0.489 J**	0.222 U	0.257 U	**0.251 J**	0.130 U	**40.4**	0.316 U
		04/23/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**0.472 J**	0.222 U	0.257 U	**0.158 J**	0.130 UJ	**7.30 J**	0.316 U
	Decommissioned December 2019															
MW-144R	8th Ave N ROW, E side	12/16/19	Bladder	0.134 U	0.117 U	0.183 U	**11.0**	–	0.412 U	**0.818**	0.222 U	0.257 UJ	**11.5**	0.130 U	**71.6**	0.316 U
		01/21/20	Bladder	1.34 U	1.17 U	1.83 U	1.99 U	–	4.12 U	1.52 U	2.22 U	2.57 U	1.53 U	1.30 U	**90.2**	3.16 U
		04/02/20	Bladder	0.134 UJ	0.117 UJ	0.183 UJ	0.199 UJ	–	0.412 UJ	0.152 UJ	0.222 UJ	0.257 UJ	0.153 UJ	0.130 UJ	**14.1 J-**	0.316 UJ
		08/03/20	Bladder	0.101 U	0.109 U	0.0620 U	**0.0500 J**	0.0900 U	**1.53**	0.0572 U	0.0612 U	0.0560 UJ	**0.0960**	0.0200 U	**1.58 J**	**0.341**
		11/23/20	Bladder	0.101 U	0.109 U	0.0620 U	**0.0420 J**	0.0900 U	0.101 U	0.0572 U	0.0612 U	0.0560 U	**0.0840**	0.0200 U	**0.411**	0.191 U
		02/02/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.393**	0.0572 U	0.0612 U	0.0560 U	**0.0750**	0.0200 U	**0.632**	**1.03**
		05/12/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	**0.420 J**	**0.0990 J**	0.0572 U	0.0612 U	0.0560 U	**0.0690**	0.0200 U	**0.365**	0.191 U
MW-146	Roy St ROW, S side	04/30/18	Bladder	0.134 U	0.117 U	0.183 U	**3.56**	–	0.412 U	**6.12**	0.222 U	0.257 U	**48.4**	0.130 U	**2,100**	0.316 U
		01/22/19	Peristaltic	0.134 U	0.117 U	0.183 U	**2.29**	–	0.412 U	**7.25**	0.222 U	0.257 U	**21.6**	0.130 U	**1,370**	0.316 U
		04/24/19	Bladder	0.134 U	0.117 U	0.183 U	**1.50**	–	0.412 U	**1.94**	0.222 U	0.257 U	**12.4**	0.130 UJ	**383**	0.316 U
		07/19/19	Bladder	0.134 U	0.117 UJ	0.183 U	**3.08**	–	0.412 U	**3.29**	0.222 U	0.257 UJ	**14.4**	0.130 U	**580 J**	0.316 U
(dup)		07/19/19	Bladder	0.134 U	0.117 UJ	0.183 U	**2.80**	–	0.412 U	**3.50**	0.222 U	0.257 UJ	**15.9**	0.130 U	**842 J**	0.316 U
		10/14/19	Bladder	0.134 U	0.117 U	0.183 U	**2.03**	–	0.412 U	**7.85**	0.222 U	0.257 UJ	**6.77**	0.130 U	**2,830**	0.316 U
		01/24/20	Bladder	13.4 U	11.7 U	18.3 U	**21.1 J**	–	41.2 U	15.2 U	22.2 U	25.7 U	15.3 U	13.0 U	**3,900**	31.6 U
(dup)		01/24/20	Bladder	0.134 U	0.117 U	0.183 U	**1.39 J**	–	0.412 U	**8.45**	0.222 U	0.257 U	**4.80**	0.130 U	**5,800**	0.316 U
		04/30/20	Bladder	12.5 U	11.8 U	12.7 U	30.0 U	–	27.8 U	14.9 U	11.8 U	46.7 U	19.0 U	16.0 U	**6,040**	17.4 U
		07/09/20	Bladder	0.101 U	0.109 U	0.0620 U	**0.781**	0.0900 U	**1.13**	**15.5**	0.0612 U	0.0560 UJ	**3.17**	0.0200 U	**8,610**	0.191 U
		11/10/20	Bladder	5.05 U	5.45 U	3.10 U	1.40 U	4.50 UJ	2.50 U	**12.5**	3.06 U	2.80 UJ	**2.60**	1.00 U	**4,930**	9.55 U
(split)		11/10/20	Bladder	500 U	500 U	500 U	500 U	–	500 U	500 U	500 U	–	500 U	500 U	**5,200**	1,500 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
MW-146		02/08/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.704 J**	0.0900 U	**1.26**	**8.01**	0.0612 U	0.0560 U	**3.52**	0.0200 U	**3,910**	**0.958**
(continued)		05/04/21	Bladder	5.05 U	5.45 U	3.10 U	1.40 U	4.50 U	2.50 U	**6.30 J**	3.06 U	2.80 U	0.800 U	1.00 U	**4,310**	9.55 U
MW-149	Property,	04/10/18	Peristaltic	0.670 U	0.585 UJ	0.915 U	**19,200**	–	2.06 U	**29.8**	1.11 U	1.28 U	**8,050**	0.650 U	**863**	**1.64 J**
	NE quadrant	10/25/18	Peristaltic	0.134 U	0.117 U	0.183 U	**6,100**	–	0.412 U	**15.3**	0.222 U	51.4 U	**2,720**	0.130 U	**100**	0.316 U
		12/13/18	Peristaltic	0.134 U	0.117 U	0.183 U	**23,300**	–	**0.717**	**18.2**	0.222 U	0.257 U	**5,470**	0.130 U	**253**	**0.414 J**
(dup)		12/13/18	Peristaltic	0.134 U	0.117 U	0.183 U	**24,500**	–	**0.717**	**18.2**	0.222 U	0.257 U	**5,780**	0.130 U	**243 J**	**0.392 J**
		01/29/19	Peristaltic	13.4 U	11.7 U	18.3 U	**23,700**	–	41.2 U	15.2 U	22.2 U	25.7 U	**3,800**	13.0 U	**155**	31.6 U
		03/13/19	Peristaltic	0.134 U	0.117 U	0.183 U	**2,630**	–	**0.862**	**129**	0.222 U	0.257 U	**2,770**	0.130 U	**285**	**0.490 J**
	Decommissioned March, 2019															
MW-151	Property,	04/10/18	Peristaltic	0.134 UJ	0.117 UJ	0.183 UJ	**1.13**	–	0.412 UJ	**0.388 J-**	0.222 U	0.257 U	**0.310 J**	0.130 U	**11.4**	0.316 U
	SW quadrant	10/25/18	Peristaltic	0.134 U	0.117 U	0.183 U	**2.28**	–	0.412 U	**0.346 J**	0.222 U	0.257 U	**1.38**	0.130 U	**7.70**	0.316 U
		12/14/18	Peristaltic	0.134 U	0.117 U	0.183 U	**1,460**	–	**0.440 J**	**4.56**	0.222 U	0.257 U	**155**	0.130 U	**530**	0.316 U
		01/31/19	Peristaltic	0.134 U	0.117 U	0.183 U	**106**	–	0.412 U	**3.52**	0.222 U	0.257 U	**40.4**	0.130 U	**158**	0.316 U
		03/12/19	Peristaltic	0.134 U	0.117 U	0.183 U	**0.981**	–	0.412 U	**1.60**	0.222 U	0.257 U	**1.36**	0.130 U	**24.9**	0.316 U
	Decommissioned March, 2019															
MW-156	8th Ave N ROW,	04/26/18	Peristaltic	0.134 U	0.117 U	0.183 U	9.95 UJ	–	**0.479 J**	**9.97**	0.222 U	0.257 U	**581**	0.130 U	**407**	0.316 U
	E side	01/24/19	Peristaltic	0.134 U	0.117 U	0.183 U	**1,720**	–	0.412 U	**11.5**	0.222 U	25.7 U	**723**	0.130 U	11.8 U	0.316 U
		04/24/19	Peristaltic	0.134 U	0.117 U	0.183 U	**1,430**	–	0.412 U	**9.41**	0.222 U	0.257 U	**727**	0.130 UJ	**3.21 J**	0.316 U
(dup)		04/24/19	Peristaltic	0.134 U	0.117 U	0.183 U	**1,440**	–	0.412 U	**9.31**	0.222 U	0.257 U	**717**	0.130 UJ	**3.34 J**	0.316 U
		07/22/19	Bladder	0.134 U	0.117 U	0.183 U	**232**	–	0.412 U	**14.5**	0.222 U	0.257 U	**1,270**	0.130 UJ	**82.0**	0.316 U
		10/17/19	Bladder	1.34 U	1.17 U	1.83 U	**682**	–	4.12 U	**6.04**	2.22 U	2.57 UJ	**430**	1.30 U	**51.1**	3.16 U
		01/20/20	Bladder	1.34 U	1.17 U	1.83 U	**792**	–	4.12 U	**7.04**	2.22 U	2.57 U	**534**	1.30 U	**99.6**	3.16 U
		04/24/20	Bladder	6.25 U	5.90 UJ	6.35 U	**347**	–	13.9 U	7.45 U	5.90 U	23.4 UJ	**355**	8.00 U	**104**	8.70 U
		07/15/20	Bladder	5.05 U	5.45 U	3.10 U	**597**	4.50 U	2.50 U	**6.50 J**	3.06 U	2.80 UJ	**486**	1.00 U	**110**	9.55 U
		11/11/20	Bladder	0.101 U	0.109 U	0.0620 U	**719**	**0.872**	**0.453**	**4.29 J-**	0.0612 U	0.0560 UJ	**363**	0.0200 U	**2.14 J+**	0.191 U
		02/08/21	Peristaltic	1.01 U	1.09 U	0.620 U	**492 J**	0.900 U	**0.540 J**	**4.04**	0.612 U	0.560 U	**228**	0.200 U	0.273 U	1.91 U
		05/10/21	Bladder	5.05 U	5.45 U	3.10 U	**442**	4.50 U	2.50 U	2.86 U	3.06 U	2.80 UJ	**184**	1.00 UJ	1.36 UJ	9.55 U
MW-189	Valley St ROW,	10/14/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	**18.2**	0.316 U
	S side	01/23/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.501**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**3.01**	0.316 U
		04/03/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**1.58**	0.316 U
(dup)		04/03/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**1.55**	0.316 U
		08/04/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.300**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	**0.879 J**	**0.207 J**
		11/17/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.0620 J**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**1.13**	0.191 U
		02/03/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.121 J**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**28.1**	**0.226 J**
		05/14/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0640 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**45.0**	0.191 U
MW-302	Dexter Ave N	10/21/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
	ROW	01/24/20	Bladder	0.134 U	0.117 U	0.183 U	**0.353 J**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.164 J**	0.130 U	0.118 U	0.316 U
		05/07/20	Bladder	0.125 UJ	0.118 U	0.127 UJ	0.300 U	–	**0.308 J**	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	0.174 U
		07/28/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	0.174 U
		11/17/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.743**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	**0.243 J**
		05/17/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.0860 J**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
MW-306	Dexter Ave N ROW,	10/15/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
	E side	01/16/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
MW-306		04/28/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	0.174 U
(continued)		07/29/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.362**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 UJ	0.0273 U	0.191 U
		11/06/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.182 J**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 UJ	0.191 U
		05/18/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.0550 J**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 UJ	0.0273 U	0.191 U
MW-308	Alley E of Seattle	10/11/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**4.38**	**0.492 J**	0.222 U	0.257 UJ	0.153 U	0.130 U	**20.3**	0.316 U
	Roy Aloha Shops	01/16/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**0.411 J**	0.222 U	0.257 U	0.153 U	0.130 U	**16.3**	0.316 U
		04/08/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**0.360 J**	0.222 U	0.257 UJ	0.153 U	0.130 U	**12.9**	0.316 U
		07/06/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	**0.304 J**	**0.174 J**	**0.608**	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	**6.98**	0.191 U
		11/06/20	Peristaltic	**0.159 J**	0.109 U	0.0620 U	**0.0324 J**	0.0900 UJ	**0.480**	**0.260**	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	**2.73**	**0.516**
		05/04/21	Peristaltic	**0.116 J**	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.186 J**	**0.219**	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**11.7**	**0.332**
MW-315	Mercer St ROW,	10/03/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
	N side	01/16/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/24/20	Bladder	0.125 U	0.118 UJ	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 UJ	0.190 U	0.160 U	0.234 U	0.174 U
		07/24/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.632**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	**0.437**
		11/02/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.162 J**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	**0.198 J**
		05/17/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.167 J**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 UJ	0.0273 U	0.191 U
MW-317	9th Ave N ROW,	10/09/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
	W side	01/16/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/27/20	Bladder	0.125 U	0.118 UJ	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 UJ	0.190 U	0.160 U	0.234 U	0.174 U
		07/30/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**1.98**	0.0572 UJ	0.0612 U	0.0560 UJ	0.0160 U	0.0200 UJ	0.0273 U	**1.36**
		11/10/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.836 J-**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	**0.419**
		05/19/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 UJ	0.0273 U	0.191 U
MW-325	Mercer St ROW,	10/03/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
	N side	01/17/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 UJ	0.316 U
		04/21/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	0.174 U
		07/23/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.298**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	**0.256 J**
		11/02/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
		02/08/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**2.03**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	**1.10**
		05/17/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.0930 J**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 UJ	0.0273 U	0.191 U
MW-327	Lake Union Park,	10/02/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
	S end	01/17/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 UJ	0.316 U
		04/09/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		07/07/20	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.260**	0.0900 U	**0.351**	0.0572 U	0.0612 U	0.0560 U	**0.267**	0.0200 U	0.0273 U	0.191 U
		11/09/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.173 J**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	**0.219 J**
		05/25/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
MW-330	Valley St ROW,	05/14/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	**0.580**	0.149 U	0.118 U	0.467 UJ	0.190 U	0.160 U	0.234 U	**0.278 J**
(dup)	N side	05/14/20	Bladder	0.125 UJ	0.118 U	0.127 U	0.300 U	–	**0.547**	0.149 U	0.118 U	0.467 UJ	0.190 U	0.160 U	0.234 U	**0.278 J**
		07/16/20	Bladder	0.101 U	0.109 U	0.0620 U	**0.0625 J**	0.0900 U	**2.49**	0.0572 U	0.0612 U	0.0560 UJ	**0.0646**	0.0200 U	0.0273 U	**0.263**
		12/01/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.215**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 UJ	0.0273 U	**0.801**
(dup)		12/01/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.212**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 UJ	0.0273 U	**0.789**
		05/25/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.202 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 UJ	0.0273 U	0.191 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
MW-331	Alley E of Seattle	04/24/20	Peristaltic	0.125 U	0.118 UJ	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 UJ	0.190 U	0.160 U	**0.249 J**	0.174 U
	Roy Aloha Shops	07/06/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	0.0500 U	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	**0.306**	0.191 U
		11/06/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.230**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	**0.264**	**0.219 J**
		05/04/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**0.339**	0.191 U
MW-333	900 Roy St,	04/29/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	**1.08**	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	**0.854 J**
	S end	07/24/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.253**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	0.191 U
		11/05/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.253**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	0.191 U
		05/18/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.0870 J**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 UJ	0.0273 U	0.191 U
MW-344	SDOT Mercer Parcels,	06/01/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0920 U	0.0900 U	**0.0700 J**	0.0572 U	0.0612 U	0.0560 U	**0.0940**	0.0200 UJ	**9.95**	0.191 U
Intermediate B Water-Bearing Zone																
FMW-141	Alley E of Seattle	07/26/19[b]	Unknown	–	–	–	30 U	–	–	30 U	–	–	**2,800**	–	**820**	–
	Roy Aloha Shops	10/30/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**7.13 J**	0.222 U	0.257 UJ	**2.18 J**	0.130 U	**1,760**	0.316 U
(dup)		10/30/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**10.5 J**	0.222 U	0.257 UJ	**12.7 J**	0.130 U	**1,710**	0.316 U
		11/11/19[b]	Unknown	–	–	–	20 U	–	–	20 U	–	–	20 U	–	**2,900**	–
		01/14/20	Bladder	0.670 U	0.585 U	0.915 U	0.995 U	–	2.06 U	**1.98 J**	1.11 U	1.29 UJ	**2.91**	0.650 U	**532**	1.58 U
(split)		01/14/20[b]	Unknown	–	–	–	4.0 U	–	–	4.0 U	–	–	4.0 U	–	**380**	–
		02/17/20[b]	Unknown	–	–	–	2.0 U	–	–	2.0 U	–	–	2.0 U	–	**240**	–
		03/24/20[b]	Unknown	–	–	–	10 U	–	–	10 U	–	–	10 U	–	**820**	–
		04/27/20[b]	Unknown	–	–	–	2.0 U	–	–		–	–	**6.5**	–	**490**	–
		04/28/20	Bladder	0.625 U	0.590 U	0.635 U	1.50 U	–	1.39 U	**4.62**	0.590 U	2.34 U	**3.08**	0.800 U	**468**	0.870 U
		05/19/20[b]	Unknown	–	–	–	20 U	–	–	20 U	–	–	20 U	–	**910**	–
		07/22/20	Bladder	2.02 U	2.18 U	1.24 U	0.560 U	1.80 U	1.00 U	**3.19 J**	1.22 U	1.12 UJ	**2.30**	0.400 U	**561**	3.82 U
		07/28/20[b]	Unknown	–	–	–	10 U	–	–	10 U	–	–	10 U	–	**780**	–
		09/17/20[b]	Unknown	–	–	–	4.0 U	–	–	4.0 U	–	–	4.0 U	–	**620**	–
		11/02/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.430**	**1.31**	0.0612 U	0.0560 U	**0.766**	0.0200 U	**489**	0.191 U
		12/03/20[b]	Unknown	–	–	–	1.0 U	–	–	1.0 U	–	–	1.0 U	–	**190**	–
		02/10/21[b]	Unknown	–	–	–	1.0 U	–	–	1.0 U	–	–	1.0 U	–	**180**	–
		05/03/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	**0.560**	0.0200 U	**0.218**	**0.508**
HMW-1IB	SDOT Mercer Parcels,	03/25/19[a]	Peristaltic	1.0 U	1.0 U	1.0 U	**20**	–	1.0 U	1.0 U	1.0 U	–	**6.7**	1.0 U	0.20 U	1.0 U
	NE quadrant	03/10/20[a]	Unknown	–	–	–	**13**	–	0.20 U	0.20 U	–	–	**5.6**	0.20 UJ	0.20 U	0.40 U
HMW-2IB	SDOT Mercer Parcels,	03/25/19[a]	Peristaltic	1.0 U	1.0 U	1.0 U	1.0 U	–	**3.4**	1.0 U	1.0 U	–	1.0 U	1.0 U	0.20 U	1.0 U
	NE quadrant	03/12/20[a]	Unknown	–	–	–	**0.38**	–	0.20 U	0.20 U	–	–	0.20 U	0.20 UJ	0.20 U	0.40 U
HMW-4IA	SDOT Mercer Parcels,	03/25/19[a]	Peristaltic	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	**3.6**	1.0 U
	SW quadrant	03/10/20[a]	Unknown	–	–	–	0.20 U	–	0.20 U	0.20 U	–	–	0.20 U	0.20 UJ	**0.41**	0.40 U
HMW-5IB	SDOT Mercer Parcels,	03/17/20[a]	Unknown	–	–	–	0.20 U	–	0.20 U	0.20 U	–	–	0.20 U	0.20 UJ	0.20 U	0.40 U
	SW quadrant															
HMW-6IB	SDOT Mercer Parcels,	03/13/20[a]	Unknown	–	–	–	0.20 U	–	0.20 U	0.20 U	–	–	0.20 U	0.20 UJ	0.20 U	0.40 U
	SW quadrant															
HMW-7IB	SDOT Mercer Parcels,	03/12/20[a]	Unknown	–	–	–	0.20 U	–	0.20 U	0.20 U	–	–	0.20 U	0.20 UJ	0.20 U	0.40 U
	SW quadrant															
HMW-8IB	SDOT Mercer Parcels,	03/11/20[a]	Unknown	–	–	–	0.20 U	–	**0.22**	0.20 U	–	–	0.20 U	0.20 UJ	0.20 U	0.40 U
	SW quadrant															

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
HMW-9IB	SDOT Mercer Parcels, SW quadrant	03/19/20[a]	Unknown	–	–	–	**660**	–	**0.23**	**8.3**	–	–	**420**	0.20 UJ	**1,900**	0.40 U
		01/26/21	Bladder	0.101 U	0.109 U	0.0620 U	**32.1 J+**	**0.249 J**	**0.590**	**4.24 J+**	0.0612 U	0.0560 U	**112**	0.0200 U	**1,400**	**1.21**
		06/02/21	Bladder	10.1 U	10.9 U	6.20 U	**16.2**	9.00 U	5.00 U	**6.30 J**	6.12 U	5.60 U	**81.6**	2.00 U	**1,230**	19.1 U
HMW-11IB	SDOT Mercer Parcels, SE quadrant	03/16/20[a]	Unknown	–	–	–	**6.9**	–	0.20 U	0.20 U	–	–	**2.5**	0.20 UJ	0.20 U	0.40 U
MW111	Alley E of Seattle Roy Aloha Shops	03/23/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**5.22**	0.316 U
		06/14/17	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.408 J**	0.130 U	**3.22**	0.316 U
		04/06/18	Peristaltic	0.134 U	0.117 U	0.183 U	**0.618**	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**121**	0.316 U
		01/23/19	Peristaltic	0.134 U	0.117 U	0.183 U	**0.492 J**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.176 J**	0.130 U	**37.6**	0.316 U
		04/22/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 UJ	**19.5 J**	0.316 U
		07/15/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 UJ	**15.0**	0.316 U
		10/14/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	**8.63**	0.316 U
		01/16/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**34.0**	0.316 U
		04/23/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	**112**	0.174 U
		07/06/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**2.63**	0.0572 U	0.0612 U	0.0560 UJ	**0.140**	0.0200 U	**116**	0.191 U
		11/02/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.225**	0.0572 U	0.0612 U	0.0560 U	**0.161**	0.0200 U	**118**	0.191 U
		02/09/21	Bladder	0.101 U	0.109 U	0.0620 U	**0.320 J**	0.0900 U	**0.955**	**0.0720 J**	0.0612 U	0.0560 U	0.0800 U	0.0200 U	**112**	**0.606**
		05/03/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.880**	0.0572 U	0.0612 U	0.0560 U	**0.0790**	0.0200 U	**44.3**	**1.21**
MW112	Dexter Ave N ROW, W side	03/22/17	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		06/16/17	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/12/18	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		12/21/18	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/22/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 UJ	0.118 UJ	0.316 U
		07/16/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 UJ	0.118 U	0.316 U
		10/21/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		01/24/20	Bladder	0.134 U	0.117 U	0.183 U	**0.248 J**	–	**1.24**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		05/07/20	Bladder	0.125 UJ	0.118 U	0.127 UJ	0.300 U	–	**0.390 J**	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	0.174 U
		07/27/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**1.93**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 UJ	0.0273 U	0.191 U
		11/17/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.322**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
		02/11/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.152 U	**0.112 J**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
		05/14/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0600 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
MW126	Alley E of Seattle Roy Aloha Shops	03/28/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.563 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		06/15/17	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/06/18	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		01/22/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/29/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 UJ	0.118 UJ	0.316 U
		07/18/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		10/15/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
(dup)		10/15/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		01/14/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	**0.441 J**
		04/09/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
MW126		07/24/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	0.0500 U	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	0.191 U
(continued)		11/09/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
		02/10/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
		05/04/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
	(dup)	05/04/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
MW130	Property,	03/29/17	Bladder	2.68 U	2.34 U	3.66 U	**721**	–	8.24 U	**39.3**	4.44 U	5.14 U	**830**	2.60 U	**186**	6.32 U
	NW quadrant	06/30/17	Bladder	1.34 U	1.17 U	1.83 U	**6,760 J**	–	4.12 U	**55.6**	2.22 U	2.57 U	**4,020**	1.30 U	**597**	3.16 U
	(dup)	06/30/17	Bladder	1.34 U	1.17 U	1.83 U	**11,100 J**	–	4.12 U	**57.3**	2.22 U	2.57 U	**5,310**	1.30 U	**549**	3.16 U
		05/21/18	Bladder	0.134 U	0.117 U	0.183 U	**13,500**	–	**1.37**	**114**	0.222 U	0.257 U	**7,400**	0.130 U	**1,650**	**1.12 J**
		12/17/18	Bladder	6.70 U	5.85 U	9.15 U	**9,650**	–	20.6 U	**83.5**	11.1 U	12.8 U	**3,220**	6.50 U	**1,420**	15.8 U
		01/31/19	Bladder	0.134 U	0.117 U	0.183 U	**23,700**	–	**1.51 J+**	**107**	0.222 U	0.257 U	**4,640**	0.130 U	**1,740**	**1.22 J**
	Decommissioned March, 2019															
MW-132	Property,	09/25/17	Bladder	0.670 U	0.585 U	0.915 U	0.995 U	–	2.06 U	0.760 U	1.11 U	1.28 U	**1.95 J**	0.650 U	**1.76 J**	1.58 U
	SE quadrant	04/26/18	Bladder	0.134 U	0.117 U	0.183 U	**2,830**	–	0.412 U	**16.3**	0.222 U	0.257 U	**840**	0.130 U	**10.2**	0.316 U
		10/25/18	Peristaltic	0.134 U	0.117 U	0.183 U	**3.53**	–	0.412 U	**0.254 J**	0.222 U	0.257 U	**0.750**	0.130 U	**158**	0.316 U
		12/13/18	Peristaltic	0.134 U	0.117 U	0.183 U	0.995 U	–	0.412 U	**0.497 J**	0.222 U	0.257 U	0.765 U	0.130 U	**199**	0.316 U
		01/31/19	Peristaltic	0.134 U	0.117 U	0.183 U	**22.9**	–	0.412 U	**0.506**	0.222 U	0.257 U	**1.95**	0.130 U	**269**	0.316 U
		03/11/19	Peristaltic	0.134 U	0.117 U	0.183 U	**7.03**	–	0.412 U	**0.302 J**	0.222 U	0.257 U	**1.22**	0.130 U	**57.3**	0.316 U
	Decommissioned March, 2019															
MW-134	Property,	09/22/17	Bladder	0.670 U	0.585 U	0.915 U	0.995 U	–	2.06 U	0.760 U	1.11 U	1.28 U	0.765 U	0.650 U	**229**	1.58 U
	NE quadrant	04/16/18	Peristaltic	0.134 U	0.117 U	0.183 U	**1.49**	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**68.6**	0.316 U
		10/25/18	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**20.9**	0.316 U
		12/12/18	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**21.9**	0.316 U
		01/28/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**32.4**	0.316 U
		03/12/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**17.7**	0.316 U
	Decommissioned March, 2019															
MW-135	Property,	09/25/17	Bladder	13.4 U	11.7 U	18.3 U	**10,400**	–	41.2 U	15.2 U	22.2 U	25.7 U	**2,480**	13.0 U	**82.0 J**	31.6 U
	NE quadrant	04/25/18	Peristaltic	0.134 U	0.117 U	0.183 U	**75,800**	–	**3.09**	**30.7**	0.222 U	0.257 U	**7,890**	0.130 U	**989**	**2.61**
		10/25/18	Peristaltic	3.35 U	2.92 U	4.58 U	**45,900**	–	10.3 U	**54.4**	5.55 U	257 U	**8,330**	3.25 U	**1,170**	7.90 U
		12/13/18	Peristaltic	6.70 U	5.85 U	9.15 U	**97,200**	–	20.6 U	**66.6**	11.1 U	12.8 U	**11,000**	6.50 U	**1,380**	15.8 U
		01/31/19	Bladder	0.134 U	0.117 U	0.183 U	**56,500**	–	**5.12 J+**	**68.6 J**	0.222 U	0.257 U	**9,530**	0.130 U	**1,090**	**3.43 J**
		03/13/19	Bladder	0.134 U	0.117 U	0.183 U	**57,300**	–	**2.43**	**74.3**	0.222 U	0.257 U	**8,150**	0.130 U	**706**	**1.90**
	Decommissioned March, 2019															
MW-136	Property,	09/25/17	Bladder	0.134 U	0.117 U	0.183 U	**15.4**	–	0.412 U	0.152 U	0.222 U	0.257 U	**10.7**	0.130 U	0.118 U	0.316 U
	SW quadrant	04/16/18	Submersible	**0.175 J**	0.117 U	0.183 U	**2.59**	–	**1.83**	0.152 U	0.222 U	0.257 U	**0.365 J**	0.130 U	**8.57**	**25.9**
		10/29/18	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.177 J**	0.130 U	**0.236 J**	0.316 U
		12/13/18	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.237 J**	0.130 U	0.118 U	0.316 U
		02/01/19	Bladder	0.134 U	0.117 U	0.183 U	**1.26**	–	0.412 U	0.152 U	0.222 U	0.257 U	0.293 U	0.130 U	**0.186 J**	0.316 U
		03/12/19	Bladder	0.134 U	0.117 U	0.183 U	**0.206 J**	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
	(dup)	03/12/19	Bladder	0.134 U	0.117 U	0.183 U	**0.262 J**	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
	Decommissioned March, 2019															
MW-139	Property,	09/25/17	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.516**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**0.246 J**	0.316 U
	SE quadrant	04/25/18	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		10/25/18	Peristaltic	0.134 U	0.117 U	0.183 U	**1.29**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.282 J**	0.130 U	0.118 U	0.316 U
		12/12/18	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
MW-139		01/28/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
(continued)		03/11/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**5.77**	0.316 U
	Decommissioned March, 2019															
MW-143	8th Ave N ROW,	04/30/18	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.797**	**0.512**	0.222 U	0.257 U	0.153 U	0.130 U	**193**	**1.08 J**
	E side	01/29/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/24/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 UJ	0.118 UJ	0.316 U
		07/19/19	Bladder	0.134 U	0.117 UJ	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		10/16/19	Bladder	0.134 U	0.117 U	0.183 U	**2.35**	–	0.412 U	**11.0**	0.222 U	0.257 UJ	**28.0**	0.130 U	**1,180**	0.316 U
		01/22/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**0.254 J**	0.316 U
		04/24/20	Bladder	0.125 U	0.118 UJ	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 UJ	0.190 U	0.160 U	0.234 U	0.174 U
		07/29/20	Bladder	0.101 U	0.109 U	0.0620 U	**0.0307 J**	0.0900 U	**1.63**	0.0572 U	0.0612 U	0.0560 U	**0.0167 J**	0.0200 UJ	0.0273 U	0.191 U
		11/24/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.203**	**0.633**	0.0612 U	0.0560 U	**9.64**	0.0200 U	**26.0**	**0.474**
		02/08/21	Peristaltic	5.05 U	5.45 U	3.10 U	1.40 U	4.50 U	**3.00 J**	**14.1**	3.06 U	2.80 U	0.800 U	1.00 U	**514 J**	9.55 U
		05/19/21	Bladder	5.05 U	5.45 U	3.10 U	1.40 U	4.50 U	2.50 U	**21.6**	3.06 U	2.80 U	0.800 U	1.00 UJ	**1,200**	9.55 U
MW-145	8th Ave N ROW,	04/27/18	Bladder	0.134 U	0.117 U	0.183 U	**0.305 J**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.212 J**	0.130 U	**3.88 J**	0.316 U
	E side	01/29/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**0.335 J**	0.316 U
		04/26/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 UJ	**0.392 J**	0.316 U
	Decommissioned December 2019															
MW-145R	8th Ave N ROW,	12/16/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
	E side	01/21/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/02/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		08/03/20	Bladder	0.101 U	0.109 U	0.0620 U	**0.0570 J**	0.0900 U	**1.45**	0.0572 U	0.0612 U	0.0560 UJ	**0.0270 J**	0.0200 U	0.0273 U	0.191 U
		11/23/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0570 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
		02/05/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**2.79**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	**1.65**
		05/12/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
MW-147	Roy St ROW,	05/01/18	Bladder	0.134 U	0.117 U	0.183 U	**19.8**	–	0.412 U	**2.09**	0.222 U	0.257 U	**83.4**	0.130 U	**1,150**	0.316 U
	S side	01/22/19	Bladder	0.134 U	0.117 U	0.183 U	**98.2**	–	0.412 U	**2.88**	0.222 U	0.257 U	**179**	0.130 U	**738**	0.316 U
		04/23/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**1.47**	0.222 U	0.257 U	**5.13**	0.130 UJ	**499**	0.316 UJ
		07/18/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**2.49**	0.222 U	0.257 UJ	**4.79**	0.130 U	**446**	6.32 U
	(dup)	07/18/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**2.12**	0.222 U	0.257 UJ	**4.72**	0.130 U	**425**	0.316 U
		10/14/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**2.91**	0.222 U	0.257 UJ	**3.38**	0.130 U	**1,410**	0.316 U
		01/24/20	Bladder	3.35 U	2.93 U	4.58 U	4.98 U	–	10.3 U	3.80 U	5.55 U	6.43 U	**4.63 J**	3.25 U	**1,340**	7.90 U
		04/29/20	Bladder	3.13 U	2.95 U	3.18 U	7.50 U	–	6.95 U	**3.90 J**	2.95 U	11.7 U	**5.10 J**	4.00 U	**3,470**	4.35 U
		07/09/20	Bladder	0.101 U	0.109 U	0.0620 U	**4.29**	0.0900 U	**3.52**	**11.9**	0.0612 U	0.0560 UJ	**12.4**	0.0200 U	**6,970**	0.191 U
		11/10/20	Bladder	10.1 U	10.9 U	6.20 U	2.80 U	9.00 UJ	5.00 U	**9.23 J**	6.12 U	5.60 UJ	**4.73**	2.00 U	**7,290**	19.1 U
	(split)	11/10/20	Bladder	500 U	500 U	500 U	500 U	–	500 U	500 U	500 U	–	500 U	500 U	**7,400**	1,500 U
		02/09/21	Bladder	5.05 U	5.45 U	3.10 U	1.40 U	4.50 U	2.50 U	**7.80 J**	3.06 U	2.80 U	**9.90**	1.00 U	**3,450 J**	9.55 U
		05/04/21	Bladder	10.1 U	10.9 U	6.20 U	2.80 U	9.00 U	5.00 U	5.72 U	6.12 U	5.60 U	**3.00 J**	2.00 U	**2,200**	19.1 U
MW-148	Roy St ROW,	05/01/18	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
(dup)	S side	05/01/18	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		01/23/19	Bladder	0.134 U	0.117 U	0.183 U	**1.24**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.347 J**	0.130 U	0.118 U	0.316 U
		04/26/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**0.277 J**	0.316 U
		07/22/19	Bladder	0.134 U	0.117 U	0.183 U	0.415 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**0.253 J**	0.316 U
		10/16/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	**0.463 J**	0.316 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
MW-148		01/20/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.163 J**	0.130 U	**0.305 J**	0.316 U
(continued)		04/30/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	0.174 U
		07/15/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**1.32**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	**0.224**	0.191 U
		11/11/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.310 J**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	0.191 U
MW-150	Property,	04/10/18	Peristaltic	0.134 U	0.117 UJ	0.183 U	**2,500**	–	**1.63**	**21.1**	0.222 U	0.257 U	**3,200**	0.130 U	**766**	79.0 U
	NW quadrant	10/25/18	Peristaltic	0.134 U	0.117 U	0.183 U	**15,200**	–	**2.53**	**49.7**	0.222 U	128 U	**8,800**	0.130 U	**1,430**	**1.13 J**
		12/12/18	Peristaltic	0.134 U	0.117 U	0.183 U	**75.6**	–	**1.04**	**242**	0.222 U	0.257 U	**533**	0.130 U	**2,040**	0.316 U
		01/29/19	Peristaltic	13.4 U	11.7 U	18.3 U	**303**	–	41.2 U	**36.7 J**	22.2 U	25.7 U	**548**	13.0 U	**1,370**	31.6 U
		03/13/19	Peristaltic	0.134 U	0.117 U	0.183 U	**36.0**	–	0.412 U	**50.5**	0.222 U	0.257 U	**262**	0.130 U	**479**	0.316 U
	Decommissioned March, 2019															
MW-152	Property,	04/10/18	Peristaltic	2.68 U	2.34 UJ	3.66 U	**67,300**	–	8.24 U	**42.1**	4.44 U	5.14 U	**6,550**	2.60 U	**3,660**	790 U
	SW quadrant	10/26/18	Peristaltic	6.70 U	5.85 U	9.15 U	**1,960**	–	20.6 U	**109**	11.1 U	514 U	**3,150**	6.50 U	**4,510**	15.8 U
		12/14/18	Peristaltic	3.35 U	2.92 U	4.58 U	**23,600 J+**	–	10.3 U	**134 J+**	5.55 U	6.42 U	**6,870 J+**	3.25 U	**7,830 J+**	7.90 U
		01/31/19	Peristaltic	0.134 U	0.117 U	0.183 U	**38,300**	–	**2.61 J+**	**101**	0.222 U	0.257 U	**3,920**	0.130 U	**9,600**	**2.10**
		03/12/19	Peristaltic	3.35 U	2.92 U	4.58 U	398 U	–	10.3 U	**781**	5.55 U	6.42 U	**18,700**	3.25 U	**11,000**	7.90 U
	Decommissioned March, 2019															
MW-157	8th Ave N ROW,	04/26/18	Peristaltic	0.134 U	0.117 U	0.183 U	**0.950**	–	0.412 U	**0.246 J**	0.222 U	0.257 U	**0.240 J**	0.130 U	**104**	0.316 U
	E side	01/24/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**14.2**	0.222 U	51.4 U	**1.65**	0.130 U	**674**	0.316 U
		04/24/19	Peristaltic	0.134 U	0.117 U	0.183 U	9.95 U	–	0.412 U	**15.9**	0.222 U	0.257 U	**8.52 J**	0.130 UJ	**622**	0.316 U
		07/22/19	Bladder	0.134 U	0.117 U	0.183 U	19.9 U	–	0.412 U	**18.4**	0.222 U	0.257 U	**27.6**	0.130 UJ	**666**	0.316 U
		10/16/19	Bladder	0.134 U	**0.141 J**	0.183 U	0.199 U	–	**0.561**	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		01/20/20	Bladder	0.134 U	0.117 U	0.183 U	**39.4**	–	0.412 U	**8.95**	0.222 U	0.257 U	**109**	0.130 U	**941**	0.316 U
		04/24/20	Bladder	2.50 U	2.36 U	2.54 U	6.00 U	–	5.56 U	**8.86 J**	2.36 U	9.34 UJ	3.80 U	3.20 U	**980**	3.48 U
		07/15/20	Bladder	2.02 U	2.18 U	1.24 U	0.560 U	1.80 U	1.00 U	**7.20**	1.22 U	1.12 UJ	**3.06**	0.400 U	**668**	3.82 U
		11/23/20	Bladder	2.02 U	2.18 U	1.24 U	**3.04**	1.80 U	1.00 U	**9.98**	1.22 U	1.12 U	**24.7**	0.400 U	**528**	3.82 U
MW-190	Valley Street ROW,	10/14/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	**0.994**	0.316 U
	S side	01/23/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	**1.57**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	**0.344 J**
		04/02/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**1.81**	0.316 U
		08/04/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**2.09**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	**3.77 J**	0.191 U
		11/18/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.0820 J**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**64.9**	0.191 U
		02/03/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.164 J**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**68.4**	**0.252 J**
		05/14/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.149 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**32.2**	**0.195 J**
MW-303	Dexter Ave N ROW,	10/21/19	Submersible	0.134 U	0.117 U	0.183 U	0.199 U	–	**1.63**	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
	E side	01/24/20	Bladder	0.134 U	0.117 U	0.183 U	**0.313 J**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.153 J**	0.130 U	0.118 U	0.316 U
		05/07/20	Bladder	0.125 UJ	0.118 U	0.127 UJ	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	0.174 U
		07/27/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**1.56**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 UJ	0.0273 U	0.191 U
		11/17/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.0750 J**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
		05/18/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.240**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 UJ	0.0273 U	0.191 U
MW-307	Roy St ROW,	10/11/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	**1.05**	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	**0.289 J**	0.316 U
	S side	01/15/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/28/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	**0.452 J**	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	0.174 U
		07/29/20	Bladder	0.101 U	0.109 U	0.0620 U	**0.0492 J**	0.0900 U	**0.780**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 UJ	0.0273 U	0.191 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
MW-307		11/06/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.427**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	0.191 U
(continued)		05/18/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.272**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 UJ	0.0273 U	0.191 U
MW-309	Alley E of Seattle	10/14/19	Peristaltic	0.134 U	0.117 U	0.183 U	**1.11**	–	**2.01**	0.152 U	0.222 U	0.257 UJ	**0.497 J**	0.130 U	**6.37**	0.316 U
	Roy Aloha Shops	01/16/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**12.6**	0.316 U
		04/08/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	**12.6**	0.316 U
		07/06/20	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.0930 J**	0.0900 UJ	0.0500 U	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	**16.0**	0.191 U
		11/06/20	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.0726 J**	0.0900 UJ	0.0500 U	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	**10.5**	0.191 U
		05/04/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.0370 J**	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**13.1**	0.191 U
MW-311	Alley E of Seattle	10/10/19	Peristaltic	0.134 U	0.117 U	0.183 U	**20.4**	–	0.412 U	**0.221 J**	0.222 U	0.257 U	**46.1**	0.130 U	**25.1**	0.316 U
	Roy Aloha Shops	01/14/20	Peristaltic	0.134 U	0.117 U	0.183 U	**1.99**	–	0.412 U	**0.204 J**	0.222 U	0.257 U	**11.4**	0.130 U	**13.6**	0.316 U
		04/23/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	**0.624**	0.160 U	**10.9**	0.174 U
		07/16/20	Bladder	0.101 U	0.109 U	0.0620 U	**0.0470 J**	0.0900 U	**3.39**	**0.144 J**	0.0612 U	0.0560 UJ	**0.334**	0.0200 U	**24.0**	0.191 U
		11/04/20	Bladder	0.101 U	0.109 U	0.0620 U	**0.169**	0.0900 UJ	**0.578**	**0.0593 J**	0.0612 U	0.0560 UJ	**0.524**	0.0200 U	**13.5**	0.191 U
		05/03/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.0660 J**	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	**0.361**	0.0200 U	**4.68**	**0.249 J**
MW-314	Alley E of Seattle	10/10/19	Bladder	0.134 U	0.117 U	0.183 U	**26.1**	–	0.412 U	**1.63**	0.222 U	0.257 U	**106**	0.130 U	**43.6**	0.316 U
	Roy Aloha Shops	01/15/20	Bladder	0.134 U	0.117 U	0.183 U	**22.7**	–	0.412 U	**2.12**	0.222 U	0.257 U	**98.3**	0.130 U	**17.9**	0.316 U
(dup)		01/15/20	Bladder	0.134 U	0.117 U	0.183 U	**19.8**	–	0.412 U	**1.85**	0.222 U	0.257 U	**88.5**	0.130 U	**17.9**	0.316 U
		04/22/20	Bladder	1.25 U	1.18 U	1.27 U	3.00 U	–	2.78 U	**14.8**	1.18 U	4.67 U	**229**	1.60 U	**410**	1.74 U
		07/16/20	Bladder	10.1 U	10.9 U	6.20 U	**4.20 J**	**21.6 J**	5.00 U	**22.3**	6.12 U	5.60 UJ	**313**	2.00 U	**442**	19.1 U
		11/04/20	Bladder	10.1 U	10.9 U	6.20 U	**13.2**	9.00 UJ	5.00 U	**16.4 J**	6.12 U	5.60 UJ	**807**	2.00 U	**360**	19.1 U
		05/03/21	Bladder	5.05 U	5.45 U	3.10 U	1.40 U	4.50 U	2.50 U	**3.15 J**	3.06 U	2.80 U	**54.5**	1.00 U	**42.9**	9.55 U
MW-316	Mercer St ROW,	10/02/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.570**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
	N side	01/16/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/21/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	0.174 U
		07/24/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.362**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	0.191 U
		11/02/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.120 J**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
		05/17/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.220**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 UJ	0.0273 U	0.191 U
MW-318	9th Ave N ROW,	10/08/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.495 J**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**8.65**	0.316 U
	W side	01/16/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.519**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**31.0**	0.316 U
		04/27/20	Bladder	0.125 U	0.118 UJ	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 UJ	0.190 U	0.160 U	**3.84**	0.174 U
		07/30/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.117 J**	0.0572 UJ	0.0612 U	0.0560 UJ	0.0160 U	0.0200 UJ	**0.941**	0.191 U
		11/12/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.224 J-**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	**0.865 J+**	**0.229 J**
		05/19/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.108 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 UJ	**1.56**	**0.257 J**
MW-322	9th Ave N ROW,	10/07/19	Peristaltic	0.134 U	0.117 U	0.183 U	**0.699**	–	**0.612**	**1.17**	0.222 U	0.257 U	**21.0**	0.130 U	**268**	0.316 U
	W side	01/21/20	Peristaltic	0.134 U	0.117 U	0.183 U	**0.218 J**	–	**0.955**	**6.06**	0.222 U	0.257 U	**8.62**	0.130 U	**221**	0.316 U
		04/29/20	Bladder	12.5 U	11.8 U	12.7 U	30.0 U	–	27.8 U	14.9 U	11.8 U	46.7 U	**661**	16.0 U	**280**	17.4 U
		07/07/20	Bladder	1.01 U	1.09 U	0.620 U	**117**	0.900 U	**0.970 J**	**3.91**	0.612 U	0.560 UJ	**494**	0.200 U	**123**	1.91 U
		11/24/20	Bladder	1.01 U	1.09 U	0.620 U	**3.35**	0.900 U	0.550 U	**1.35 J**	0.612 U	0.560 U	**70.9**	0.200 U	**41.2**	1.91 U
		05/19/21	Peristaltic	1.01 U	1.09 U	0.620 U	**8.80**	0.900 U	0.500 U	**2.41**	0.612 U	0.560 U	**259**	0.200 UJ	**43.0**	1.91 U
MW-334	900 Roy St,	04/24/20	Bladder	0.125 U	0.118 UJ	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 UJ	0.190 U	0.160 U	0.234 U	0.174 U
	S end	07/07/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**1.61**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
MW-334		11/05/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.195 J**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	0.191 U
(continued)		05/13/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.143 J**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
MW-335	Mercer St ROW,	05/01/20	Bladder	0.125 U	0.118 U	0.127 U	**295**	–	0.278 U	**1.11**	0.118 U	0.467 U	**294**	0.160 U	0.234 U	0.174 U
	N side	07/08/20	Bladder	1.01 U	1.09 U	0.620 U	**203**	0.900 U	**1.40 J**	0.572 U	0.612 U	0.560 UJ	**215**	0.200 U	0.273 U	1.91 U
		11/02/20	Bladder	1.01 U	1.09 U	0.620 U	**235 J**	0.900 UJ	0.500 U	**3.16**	0.612 U	0.560 U	**302**	0.200 U	**5.08**	1.91 U
		02/10/21	Bladder	1.01 U	1.09 U	0.620 U	**135**	0.900 U	0.500 U	**6.34**	0.612 U	0.560 U	**230**	0.200 U	0.273 U	1.91 U
		05/26/21	Peristaltic	1.01 U	1.09 U	0.620 U	**58.2**	0.900 U	0.500 U	**4.06**	0.612 U	0.560 U	**131 J+**	0.200 U	0.273 U	1.91 U
MW-338	Lake Union Park,	05/07/20	Peristaltic	0.125 UJ	0.118 U	0.127 UJ	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	0.174 U
	N end	07/23/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**1.16**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	**0.617**
		11/10/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 UJ	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	0.191 U
		05/04/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
MW-340	Lake Union Park,	05/12/20	Peristaltic	0.125 U	0.118 U	0.127 U	0.300 U	–	**0.428 J**	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	**0.635 J**
	S end	07/17/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	0.191 U
		11/09/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	**0.115 J**	0.0160 U	0.0200 U	0.0273 U	0.191 U
		05/13/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
MW-345	SDOT Mercer Parcels,	06/01/21	Bladder	0.101 U	0.109 U	0.0620 U	**0.717**	0.0900 U	**0.176 J**	**0.0600 J**	0.0612 U	0.0560 U	**0.456**	0.0200 UJ	**8.76**	0.191 U
MW-346	SDOT Mercer Parcels,	06/02/21	Bladder	0.101 U	0.109 U	0.0620 U	**25.3**	0.0900 U	**0.206**	0.0572 U	0.0612 U	0.0560 U	**6.09**	0.0200 U	**1.90**	0.191 U
(dup)	NW quadrant	06/02/21	Bladder	0.101 U	0.109 U	0.0620 U	**25.1**	0.0900 U	**0.194 J**	0.0572 U	0.0612 U	0.0560 U	**6.16**	0.0200 U	**1.93**	0.191 U
MW-347	SDOT Mercer Parcels,	06/01/21	Bladder	0.101 U	0.109 U	0.0620 U	**5.19**	0.0900 U	**0.346**	**0.291**	0.0612 U	0.0560 U	**3.83**	0.0200 UJ	**66.9**	0.191 U
MW-348	SDOT Mercer Parcels,	06/01/21	Bladder	0.101 U	0.109 U	0.0620 U	**12.6**	0.0900 U	**0.170 J**	**0.107 J**	0.0612 U	0.0560 U	**8.62**	0.0200 UJ	**55.4**	0.191 U
MW-349	SDOT Mercer Parcels,	06/01/21	Bladder	0.101 U	0.109 U	0.0620 U	**0.611**	0.0900 U	**2.60**	0.0572 U	0.0612 U	0.0560 U	**0.474**	0.0200 UJ	**11.6**	**0.191 J**
MW-350	SDOT Mercer Parcels,	06/01/21	Bladder	**0.730**	0.109 U	0.0620 U	0.0280 U	0.0900 U	**10.9**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 UJ	0.0273 U	**56.7**
W-MW-01	8th Ave N ROW,	03/30/17	Peristaltic	0.134 U	0.117 U	0.183 U	**0.330 J**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.203 J**	0.130 U	**1.83**	0.316 U
	W side	06/19/17	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.931**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**1.09**	0.316 U
		04/13/18	Bladder	0.134 U	0.117 U	0.183 U	**5.33**	–	0.412 U	0.152 U	0.222 U	0.257 U	**1.68**	0.130 U	**8.79**	0.316 U
		10/29/18	Bladder	0.134 U	**0.242 J**	0.183 U	**0.220 J**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.696**	0.130 U	**3.90**	0.316 U
		12/13/18	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	**1.77**	0.130 U	**3.86**	0.316 U
		01/25/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.587**	0.130 U	**5.46**	0.316 U
		03/11/19	Bladder	0.134 U	0.117 U	0.183 U	**0.520**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.301 J**	0.130 U	**7.24**	0.316 U
		04/25/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.373 J**	0.130 UJ	**6.61 J**	0.316 U
		07/23/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.304 J**	0.130 UJ	**9.00**	0.316 U
		10/15/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	**0.350 J**	0.130 U	**7.36**	0.316 U
		01/27/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.349 J**	0.130 U	**5.16**	0.316 U
		04/03/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.244 J**	0.130 U	**3.79**	0.316 U
		07/31/20	Bladder	0.101 U	0.109 U	0.0620 U	**0.0742 J**	**4.22 J**	0.0500 U	0.0572 UJ	0.0612 U	0.0560 UJ	**0.299**	0.0200 UJ	**2.98**	0.191 U
		11/24/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	**18.1 J+**	0.0500 U	0.0572 U	0.0612 U	0.0560 U	**0.214**	0.0200 U	**5.82**	0.191 U
		02/03/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	**13.3**	0.0500 U	0.0572 U	0.0612 U	0.0560 U	**0.191**	0.0200 U	**3.62**	0.191 U
		05/17/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	**21.0**	**0.828**	0.0572 U	0.0612 U	0.0560 U	**0.197**	0.0200 U	**9.41**	0.191 U
W-MW-02	8th Ave N ROW,	03/27/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.961 J**	**2.16**	0.222 U	0.257 U	**0.259 J**	0.130 U	**36.4**	0.316 U
	W side	06/19/17	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.970**	**0.746**	0.222 U	0.257 U	0.153 U	0.130 U	**25.6**	0.316 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
W-MW-02		06/12/18	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.829**	**0.279 J**	0.222 U	0.257 U	0.153 U	0.130 U	**4.95**	0.316 U
(continued)		10/26/18	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.641**	**0.410 J**	0.222 U	0.257 U	0.153 U	0.130 U	**1.41**	0.316 U
(dup)		10/26/18	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.587**	**0.435 J**	0.222 U	0.257 U	0.153 U	0.130 U	**1.80**	0.316 U
		12/12/18	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**1.05**	**0.463 J**	0.222 U	0.257 U	0.153 U	0.130 U	**2.30**	0.316 U
		01/25/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**2.09**	**0.263 J**	0.222 U	0.257 U	0.153 U	0.130 U	**2.01**	0.316 U
		03/11/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**1.12**	**0.316 J**	0.222 U	0.257 U	0.153 U	0.130 U	**2.43**	0.316 U
		04/23/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.560**	**2.35**	0.222 U	0.257 U	**40.1**	0.130 UJ	**81.0 J**	0.316 U
		07/23/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	**1.35**	**0.386 J**	0.222 U	0.257 U	0.153 U	0.130 UJ	**6.79**	0.316 U
		10/18/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	**1.79**	**0.278 J**	0.222 U	0.257 U	0.153 UJ	0.130 U	**3.56**	0.316 U
		01/28/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	**2.93**	**0.252 J**	0.222 U	0.257 U	0.153 U	0.130 U	**1.70**	0.316 U
		04/01/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	**2.51**	**0.166 J**	0.222 U	0.257 UJ	0.153 U	0.130 U	**1.42**	0.316 U
		07/31/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	**0.844 J**	**0.387**	**0.204 J**	0.0612 U	0.0560 UJ	**0.136**	0.0200 UJ	**1.08**	0.191 U
Deep Water-Bearing Zone																
FMW-129	SDOT Mercer Parcels, NE quadrant	04/10/17	Peristaltic	0.670 U	0.585 U	0.915 U	**194**	–	2.06 U	**5.05**	1.11 U	1.28 U	**492**	0.650 U	**0.885 J**	1.58 U
		06/23/17	Bladder	0.134 U	0.117 U	0.183 U	**81.1**	–	0.412 U	**1.21**	0.222 U	0.257 U	**182**	0.130 U	**4.13**	0.316 U
		05/01/19	Peristaltic	0.134 U	0.117 U	0.183 U	**101**	–	0.412 U	**1.22**	0.222 U	0.257 U	**166**	0.130 UJ	0.590 U	0.316 U
		07/16/19	Bladder	0.134 U	0.117 U	0.183 U	**159**	–	0.412 U	**1.61**	0.222 U	0.257 UJ	**84.1**	0.130 UJ	**0.296 J**	0.316 U
		10/21/19	Peristaltic	0.134 U	0.117 U	0.183 U	**114**	–	0.412 U	**1.61**	0.222 U	0.257 UJ	**198**	0.130 U	**0.259 J**	0.316 U
		11/12/19[v]	Unknown	–	–	–	**79**	–	–	2.0 U	–	–	**130**	–	2.0 U	–
		01/14/20	Bladder	1.34 U	1.17 U	1.83 U	**113**	–	4.12 U	**1.60 J**	2.22 U	2.57 U	**170**	1.30 U	1.18 U	3.16 U
(split)		01/14/20[v]	Bladder	–	–	–	**130**	–	–	2.0 U	–	–	**170**	–	2.0 U	–
		02/18/20[p]	Unknown	–	–	–	**110**	–	–	2.0 U	–	–	**170**	–	2.0 U	–
		03/25/20[v]	Unknown	–	–	–	**88**	–	–	2.0 U	–	–	**140**	–	**2.6**	–
		04/27/20[v]	Unknown	–	–	–	**74**	–	–	1.0 U	–	–	**88**	–	1.0 U	–
		05/06/20	Bladder	0.125 U	0.118 U	0.127 U	**34.6**	–	0.278 U	**0.433 J**	0.118 U	0.467 U	**61.9**	0.160 U	**14.2**	0.174 U
		05/19/20[v]	Unknown	–	–	–	**18**	–	–	1.0 U	–	–	**42**	–	**6.5**	–
		07/10/20	Bladder	0.101 U	0.109 U	0.0620 U	**10.8**	**0.155 J**	**1.47**	**0.224**	0.0612 U	0.0560 UJ	**27.1**	0.0200 U	**0.430**	0.191 U
		07/28/20[v]	Unknown	–	–	–	**5.4**	–	–	0.80 U	–	–	**11**	–	0.80 U	–
		09/17/20[v]	Unknown	–	–	–	**6.1**	–	–	0.40 U	–	–	**13**	–	0.40 U	–
		11/10/20	Bladder	0.101 U	0.109 U	0.0620 U	**6.43**	0.0900 U	**0.136 J-**	**0.135 J**	0.0612 U	0.0560 UJ	**22.3**	0.0200 U	**8.49 J+**	0.191 U
		12/03/20[p]	Unknown	–	–	–	**9.0**	–	–	0.40 U	–	–	**14**	–	0.40 U	–
		02/10/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**2.42**	0.0900 U	0.0500 U	**0.276**	0.0612 U	0.0560 U	**4.97**	0.0200 U	0.0273 U	0.191 U
(split)		02/10/21[v]	Peristaltic	–	–	–	**1.9**	–	–	0.20 U	–	–	**4.6**	–	0.20 U	–
		05/26/21	Bladder	0.101 U	0.109 U	0.0620 U	**91.1**	0.0900 U	0.0860 U	**1.53**	0.0612 U	0.0560 U	**197**	0.0200 U	0.0273 U	0.191 U
(dup)		05/26/21	Bladder	0.101 U	0.109 U	0.0620 U	**97.2**	0.0900 U	0.102 U	**1.56**	0.0612 U	0.0560 U	**201**	0.0200 U	0.0273 U	0.191 U
FMW-131	Block 37, SE quadrant	03/24/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**0.249 J**	0.316 U
		06/23/17	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**0.264 J**	0.316 U
		12/18/17[b]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	0.20 U	–	0.20 U	–
		04/22/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 UJ	**0.195 J**	0.316 U
		10/21/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	**0.140 J**	0.316 U
		01/22/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**0.162 J**	0.316 U
		04/29/20	Peristaltic	0.125 U	0.118 U	0.127 U	0.300 U	–	**0.954**	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	**0.309 J**	**0.726 J**
		07/30/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	0.0500 J	0.0572 UJ	0.0612 U	0.0560 UJ	0.0160 U	0.0200 UJ	**0.147**	0.191 U
		08/26/20[v]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	0.20 U	–	0.20 U	–

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
FMW-131 (continued)		11/19/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.0520 J**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**0.109**	0.191 U
		12/04/20[v]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	0.20 U	–	0.20 U	–
		02/11/21[o]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	0.20 U	–	0.20 U	–
		02/12/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.0450 J**	0.0900 UJ	**1.04**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**0.287**	**0.952**
		05/13/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.115 J**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**0.428**	0.191 U
FMW-137	Alley E of Block 38 West	11/20/18[o]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	0.20 U	–	0.20 U	–
		12/28/18[v]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	0.20 U	–	0.20 U	–
		05/06/19[v]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	0.20 U	–	0.20 U	–
		07/08/19[v]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	0.20 U	–	0.20 U	–
		10/14/19[o]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	0.20 U	–	0.20 U	–
		11/06/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		11/11/19[v]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	0.20 U	–	0.20 U	–
		01/22/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.506**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		05/06/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	0.174 U
		07/31/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.884**	0.0572 UJ	0.0612 U	0.0560 UJ	0.0160 U	0.0200 UJ	0.0273 U	**0.637**
		11/24/20	Bladder	**0.277 J**	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0900 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	**0.294**
		02/12/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.448**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**0.0920 J**	**0.442**
		06/02/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
FMW-138	Alley E of Block 38 West	11/20/18[o]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	0.20 U	–	0.20 U	–
		12/28/18[v]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	0.20 U	–	0.20 U	–
		05/6/19[o]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	0.20 U	–	0.20 U	–
		07/8/19[o]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	0.20 U	–	0.20 U	–
		10/14/19[o]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	0.20 U	–	0.20 U	–
		11/11/19[v]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	0.20 U	–	0.20 U	–
FMW-3D	Terry Ave N ROW, E side	03/24/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		06/23/17	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
FMW-140	900 Roy St, S end	07/17/19[o]	Unknown	–	–	–	2.0 U	–	–	0.20 U	–	–	2.0 U	–	**320**	–
		10/31/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**1.43**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**189**	0.316 U
		11/12/19[v]	Unknown	–	–	–	4.0 U	–	–	0.20 U	–	–	4.0 U	–	**510**	–
		01/14/20[o]	Unknown	–	–	–	4.0 U	–	–	0.20 U	–	–	4.0 U	–	**460**	–
		01/22/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**0.729**	0.222 U	0.257 U	0.153 U	0.130 U	**527**	0.316 U
		02/18/20[v]	Unknown	–	–	–	4.0 U	–	–	0.20 U	–	–	4.0 U	–	**530**	–
		03/25/20[v]	Unknown	–	–	–	2.0 U	–	–	0.20 U	–	–	2.0 U	–	**290**	–
		04/27/20[v]	Unknown	–	–	–	1.0 U	–	–	0.20 U	–	–	1.0 U	–	**130**	–
		04/28/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	**0.217 J**	0.118 U	0.467 U	0.190 U	0.160 U	**147**	0.174 U
		05/19/20[v]	Unknown	–	–	–	1.0 U	–	–	0.20 U	–	–	1.0 U	–	**130**	–
		07/07/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**2.79**	**0.202**	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**188**	0.191 U
		07/29/20[v]	Unknown	–	–	–	1.0 U	–	–	0.20 U	–	–	1.0 U	–	**170**	–
		09/17/20[v]	Unknown	–	–	–	1.0 U	–	–	0.20 U	–	–	1.0 U	–	**43**	–
		11/13/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.147 J**	**0.0665 J**	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	**30.8**	0.191 U
		12/04/20[v]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	0.20 U	–	**18**	–
		02/10/21[v]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	0.20 U	–	**3.2**	–
		05/18/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.152 J**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 UJ	**15.8**	0.191 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
GEI-2	Block 37, NW quadrant	03/24/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**6.94**	0.316 U
		06/23/17	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**127**	0.316 U
		12/29/18[o]	Unknown	–	–	–	0.40 U	–	–	0.40 U	–	–	0.40 U	–	**60**	–
		04/22/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 UJ	**57.7 J**	0.316 U
		07/16/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 UJ	**46.4**	0.316 U
		10/21/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	**88.2**	0.316 U
		11/11/19[w]	Unknown	–	–	–	1.0 U	–	–	1.0 U	–	–	1.0 U	–	**92**	–
		01/14/20[o]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	0.20 U	–	**36**	–
		01/22/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.192 J**	0.130 U	0.118 U	0.316 U
		02/17/20[w]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	0.20 U	–	**34**	–
		03/25/20[w]	Unknown	–	–	–	0.40 U	–	–	0.40 U	–	–	0.40 U	–	**52**	–
		04/27/20[w]	Unknown	–	–	–	0.40 U	–	–	0.40 U	–	–	0.40 U	–	**50**	–
		04/29/20	Peristaltic	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	**67.8**	0.174 U
		05/19/20[o]	Unknown	–	–	–	0.40 U	–	–	0.40 U	–	–	0.40 U	–	**55**	–
		06/29/20[w]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	0.20 U	–	**33**	–
		07/29/20[w]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	0.20 U	–	**46**	–
		07/30/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.0707 J**	0.0572 UJ	0.0612 U	0.0560 UJ	0.0160 U	0.0200 UJ	**44.9**	0.191 U
		08/26/20[o]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	0.20 U	–	0.20 U	–
		09/17/20[o]	Unknown	–	–	–	0.40 U	–	–	0.40 U	–	–	0.40 U	–	**48**	–
		11/19/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**42.7**	0.191 U
		12/04/20[w]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	0.20 U	–	**21**	–
		02/11/21[w]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	0.20 U	–	**16**	–
		02/12/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.282 U	**1.22**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**18.4**	**1.09**
		05/13/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.149 J**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**9.14**	0.191 U
HMW-1D	SDOT Mercer Parcels, NE quadrant	03/25/19[a]	Peristaltic	1.0 U	1.0 U	1.0 U	**3.4**	–	1.0 U	**1.2**	1.0 U	–	**27**	1.0 U	**4.0**	1.0 U
		03/09/20[a]	Unknown	–	–	–	**21**	–	20 U	20 U	–	–	**110**	20 UJ	6.0 U	40 U
HMW-2D	SDOT Mercer Parcels, NE quadrant	03/25/19[a]	Peristaltic	1.0 U	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	1.0 U	–	1.0 U	1.0 U	0.20 U	1.0 U
		03/12/20[a]	Unknown	–	–	–	0.20 U	–	0.20 U	0.20 U	–	–	0.20 U	0.20 UJ	0.20 U	0.40 U
HMW-3D	SDOT Mercer Parcels, NW quadrant	03/25/19[a]	Peristaltic	1.0 U	1.0 U	1.0 U	1.0 U	–	**1.1**	1.0 U	1.0 U	–	1.0 U	1.0 U	0.20 U	1.0 U
		03/13/20[a]	Unknown	–	–	–	0.20 U	–	0.20 U	0.20 U	–	–	0.20 U	0.20 UJ	0.20 U	0.40 U
HMW-6D	SDOT Mercer Parcels, SW quadrant	03/16/20[a]	Unknown	–	–	–	0.20 U	–	**0.64**	0.20 U	–	–	0.20 U	0.20 UJ	0.20 U	0.40 U
HMW-9D	SDOT Mercer Parcels, SW quadrant	03/17/20[a]	Unknown	–	–	–	**0.89**	–	**0.42**	0.20 U	–	–	0.20 U	0.20 UJ	**0.97**	0.40 U
HMW-10D	SDOT Mercer Parcels, SE quadrant	03/16/20[a]	Unknown	–	–	–	0.20 U	–	0.20 U	0.20 U	–	–	0.20 U	0.20 UJ	0.20 U	0.40 U
MW102	Valley Street ROW, S side	03/29/17	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		06/15/17	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/25/18	Bladder	0.134 U	0.117 U	0.183 U	**0.352 J**	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		01/24/19	Bladder	0.134 U	0.117 U	0.183 U	**0.220 J**	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		05/01/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 UJ	0.118 UJ	0.316 U
		07/18/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
MW102		11/14/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
(continued)		01/23/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
(dup)		01/23/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/02/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		08/04/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**1.00**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
(dup)		08/04/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.880**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	0.191 U
		11/18/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.0710 J**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
		02/03/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.0880 J**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	**0.282**
		05/14/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.196 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
MW103	Alley E of Seattle	03/23/17	Peristaltic	0.134 U	0.117 U	0.183 U	1.99 U	–	**0.464 J**	**0.405 J**	0.222 U	0.257 U	**23.1**	0.130 U	**157**	0.316 U
	Roy Aloha Shops	06/14/17	Bladder	0.134 U	0.117 U	0.183 U	**0.626**	–	0.412 U	**0.369 J**	0.222 U	0.257 U	**23.0**	0.130 U	**69.2**	0.316 U
		04/06/18	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	**1.81**	0.130 U	**22.4**	0.316 U
		01/23/19	Peristaltic	0.134 U	0.117 U	0.183 U	**0.365 J**	–	**1.35**	0.152 U	0.222 U	0.257 U	**1.48**	0.130 U	**6.68**	0.316 U
		04/22/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**0.209 J**	0.222 U	0.257 U	**3.09**	0.130 UJ	**32.3 J**	0.316 U
		07/15/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**0.232 J**	0.222 U	0.257 UJ	**2.37**	0.130 UJ	**55.4**	0.316 U
		10/14/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**0.158 J**	0.222 U	0.257 UJ	0.153 U	0.130 U	**51.8**	0.316 U
		01/16/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**77.9**	0.316 U
		04/23/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	**0.233 J**	0.160 U	**4.80**	0.174 U
(dup)		04/23/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	**0.244 J**	0.160 U	**4.71**	0.433 U
		07/06/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**2.12**	0.0572 UJ	0.0612 U	0.0560 UJ	**0.185**	0.0200 U	**2.18**	0.191 U
		11/02/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.158 J**	**0.0590 J**	0.0612 U	0.0560 U	**0.0800**	0.0200 U	**2.22**	0.191 U
		02/10/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.542**	0.0572 U	0.0612 U	0.0560 U	**0.602**	0.0200 U	**5.37**	**0.433**
		05/03/21	Bladder	0.101 U	0.109 U	0.0620 U	**0.569**	0.0900 U	**0.0950 J**	**0.108 J**	0.0612 U	0.0560 U	**8.73**	0.0200 U	**15.8**	0.191 U
MW104	8th Ave N ROW,	03/30/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
	W side	06/30/17	Bladder	0.134 U	0.117 U	0.183 U	**5.83**	–	**0.903**	0.152 U	0.222 U	0.257 U	**5.21**	0.130 U	0.118 U	**0.396 J**
		04/09/18	Peristaltic	0.134 U	0.117 U	0.183 U	**0.541**	–	0.412 U	**1.02**	0.222 U	0.257 U	**2.00**	0.130 U	**32.3**	0.316 U
		10/26/18	Bladder	0.134 U	0.117 U	0.183 U	**1.87 J+**	–	**0.618 J+**	**0.257 J**	0.222 U	0.257 U	**2.94 J+**	0.130 U	**43.5**	0.316 U
		12/13/18	Bladder	0.134 U	0.117 U	0.183 U	**0.381 J**	–	0.412 U	**0.559**	0.222 U	0.257 U	**2.36**	0.130 U	**43.8**	0.316 U
		02/01/19	Bladder	0.134 U	0.117 U	0.183 U	**12.1**	–	0.412 U	**0.326 J**	0.222 U	0.257 U	**3.22**	0.130 U	**32.4**	0.316 U
		03/13/19	Bladder	0.134 U	0.117 U	0.183 U	**31.6**	–	**0.455 J**	**1.93**	0.222 U	0.257 U	**75.7**	0.130 U	**25.9**	0.316 U
		04/23/19	Bladder	0.134 U	0.117 U	0.183 U	**15.9**	–	0.412 U	**2.49**	0.222 U	0.257 U	**56.9**	0.130 UJ	**21.1 J**	0.316 U
		07/22/19	Bladder	0.134 U	0.117 U	0.183 U	**0.282 J**	–	0.412 U	**2.10**	0.222 U	0.257 U	**28.3**	0.130 U	**57.1**	0.316 U
		10/18/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**0.329 J**	0.222 U	0.257 U	**1.54 J**	0.130 U	**33.2**	0.316 U
		01/29/20	Bladder	0.134 U	0.117 U	0.183 U	**0.894**	–	0.412 U	**0.481 J**	0.222 U	0.257 U	**6.44**	0.130 U	**31.7**	0.316 U
		04/01/20	Bladder	0.134 U	0.117 U	0.183 U	**53.1**	–	0.412 U	**2.50**	0.222 U	0.257 UJ	**108**	0.130 U	**4.63**	0.316 U
		07/31/20	Bladder	0.101 U	0.109 U	0.0620 U	**18.8**	**1.19 J**	**0.251**	**1.01 J**	0.0612 U	0.0560 UJ	**55.0**	0.0200 UJ	**2.68**	0.191 U
(dup)		07/31/20	Bladder	0.101 U	0.109 U	0.0620 U	**19.2**	**1.17 J**	**0.242**	**1.04 J**	0.0612 U	0.0560 UJ	**55.0**	0.0200 UJ	**2.65**	0.191 U
		11/17/20	Bladder	0.101 U	0.109 U	0.0620 U	**10.6**	**2.43 J-**	**0.0730 J**	**1.61**	0.0612 U	0.0560 U	**59.5 J+**	0.0200 U	**4.68**	0.191 U
		02/10/21	Bladder	0.101 U	0.109 U	0.0620 U	**1.52**	**3.54 J+**	**2.03**	**1.15**	0.0612 U	0.0560 U	**29.8**	0.0200 U	**9.58**	**1.18**
MW105	Roy Street ROW,	04/21/17	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.544 J**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**1.95**	0.316 U
	S side	06/14/17	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.356 J**	0.130 U	**0.514**	0.316 U
		04/11/18	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**0.205 J**	0.316 U
		01/23/19	Bladder	0.134 U	0.117 U	0.183 U	**0.790**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.317 J**	0.130 U	**0.392 J**	0.316 U
		04/23/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 UJ	**0.238 J**	0.316 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
MW105		07/17/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	**0.265 J**	0.316 U
(continued)		10/22/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	**0.214 J**	0.316 U
(dup)		10/22/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		01/20/20	Bladder	0.134 U	0.117 U	0.183 U	**0.208 J**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.348 J**	0.130 U	**0.568**	0.316 U
		05/12/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	**0.635**	0.149 U	0.118 U	0.467 U	**1.02**	0.160 U	0.234 U	**0.193 J**
		07/27/20	Bladder	0.101 U	0.109 U	0.0620 U	**0.324**	0.0900 U	**1.25**	**0.0983 J**	0.0612 U	0.0560 U	**2.12**	0.0200 UJ	**0.135**	0.191 U
		11/17/20	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.553**	0.0900 UJ	**0.139 J**	**0.248**	0.0612 U	0.0560 U	**4.95 J+**	0.0200 U	**0.150**	0.191 U
		02/11/21	Bladder	0.101 U	0.109 U	0.0620 U	**0.335**	0.0900 U	**0.373**	**0.403**	0.0612 U	0.0560 U	**3.53**	0.0200 U	**0.178**	**0.528**
		06/07/21	Bladder	0.101 U	0.109 U	0.0620 U	**0.128**	0.0900 U	**1.09**	**0.300**	0.0612 U	0.0560 U	**1.37**	0.0200 U	**0.359**	**0.234 J**
MW106	SDOT Mercer Parcels, NW quadrant	04/14/17	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		06/30/17	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.419 J**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		05/04/18	Bladder	0.134 U	**0.273 J**	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/26/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 UJ	0.118 UJ	0.316 U
		07/19/19	Bladder	0.134 U	0.117 UJ	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		10/18/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 UJ	0.130 U	0.118 U	0.316 U
		01/14/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		05/06/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	0.174 U
(dup)		05/06/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	0.174 U
		07/10/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**1.74**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	0.191 U
		11/10/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.415 J-**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	**0.233 J**
(dup)		11/10/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.339 J-**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	**0.216 J**
		02/12/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
(dup)		02/12/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
		05/13/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.0570 J**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
MW113	9th Ave N ROW, W side	03/22/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**25.4**	0.222 U	0.257 U	**27.1**	0.130 U	**63.5**	0.316 U
		06/16/17	Bladder	0.134 U	0.117 U	0.183 U	**0.522**	–	0.412 U	**28.2**	0.222 U	0.257 U	**148**	0.130 U	**53.3**	0.316 U
		04/11/18	Peristaltic	0.134 U	0.117 U	0.183 U	**191**	–	0.412 U	**21.3**	0.222 U	0.257 U	**1,100**	0.130 U	**34.9**	0.316 U
		01/30/19	Peristaltic	0.670 U	0.585 U	0.915 U	0.995 U	–	2.06 U	**22.8**	1.11 U	1.28 U	**2.81**	0.650 U	**34.8**	1.58 U
		02/07/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**25.7**	0.222 U	0.257 U	**1.77**	0.130 U	**46.0**	0.316 U
		07/17/19	Peristaltic	0.134 U	0.117 U	0.183 U	**3.14**	–	0.412 U	**13.1**	0.222 U	0.257 UJ	**20.4**	0.130 U	**103**	0.316 U
		10/22/19	Peristaltic	0.134 U	0.117 U	0.183 U	1.99 U	–	0.412 U	**4.45**	0.222 U	0.257 UJ	**6.77**	0.130 U	**66.2**	0.316 U
		11/11/19[p]	Peristaltic	–	–	–	50 U	–	–	50 U	–	–	50 U	–	**950**	–
		01/14/20	Bladder	1.34 U	1.17 U	1.83 U	1.99 U	–	4.12 U	**32.9**	2.22 U	2.57 U	1.53 U	1.30 U	**1,410**	3.16 U
(split)		01/14/20[v]	Peristaltic	–	–	–	50 U	–	–	50 U	–	–	50 U	–	**1,400**	–
		02/18/20[v]	Unknown	–	–	–	50 U	–	–	50 U	–	–	50 U	–	**1,800**	–
		03/24/20[v]	Unknown	–	–	–	20 U	–	–	20 U	–	–	20 U	–	**200**	–
		04/27/20	Peristaltic	12.5 U	11.8 UJ	12.7 U	30.0 U	–	27.8 U	14.9 U	11.8 U	46.7 UJ	19.0 U	16.0 U	**75.9**	17.4 U
(split)		04/27/20[v]	Peristaltic	–	–	–	20 U	–	–	20 U	–	–	20 U	–	**94**	–
		05/19/20[v]	Unknown	–	–	–	20 U	–	–	20 U	–	–	20 U	–	**110**	–
		07/28/20	Bladder	12.5 U	11.8 U	12.7 U	**212**	–	27.8 U	14.9 U	11.8 U	46.7 U	**1,540**	16.0 U	**76.0**	17.4 U
(split)		07/28/20[v]	Unknown	–	–	–	**170**	–	–	10 U	–	–	**1,300**	–	**82**	–
		09/17/20[p]	Unknown	–	–	–	**390**	–	–	10 U	–	–	**1,500**	–	**45**	–
		11/24/20	Bladder	10.1 U	10.9 U	6.20 U	**706**	9.00 U	5.00 U	**8.30 J**	6.12 U	5.60 U	**1,380**	2.00 U	**11.9**	19.1 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
MW113		12/03/20[o]	Unknown	–	–	–	**480**	–	–	4.0 U	–	–	**800**	–	**6.4**	–
(continued)		02/10/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**3.04**	**0.183 J**	0.0500 U	**0.0780 J**	0.0612 U	0.0560 U	**4.18**	0.0200 U	**0.0710 J**	0.191 U
(split)		02/10/21[o]	Peristaltic	–	–	–	**2.7**	–	–	0.20 U	–	–	**8.4**	–	0.20 U	–
		05/25/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**249**	0.0900 U	0.127 U	**8.60**	0.0612 U	0.0560 U	**944**	0.0200 UJ	**6.91**	0.191 U
MW122	Alley E of Seattle Roy Aloha Shops	03/28/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		06/14/17	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.162 J**	0.130 U	0.118 U	0.316 U
		04/06/18	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		10/14/19	Peristaltic	0.134 U	0.117 U	0.183 U	**0.223 J**	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		01/17/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 UJ	0.316 U
		04/07/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		07/24/20	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.0540 J**	0.0900 U	**0.0880 J**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	0.191 U
		11/06/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	0.191 U
		05/03/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.0360 J**	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
MW123	Westlake Ave N ROW, W side	04/01/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		06/24/17	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/14/18	Peristaltic	0.134 U	0.117 U	0.183 U	**0.284 J**	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		10/18/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 UJ	0.130 U	0.118 U	0.316 U
		01/22/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		05/05/20	Peristaltic	0.125 U	0.118 U	0.127 U	0.300 U	–	**0.293 J**	0.149 U	0.118 U	0.467 UJ	0.190 U	0.160 U	0.234 U	0.174 U
		07/30/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**1.62**	0.0572 UJ	0.0612 U	0.0560 UJ	0.0160 U	0.0200 UJ	0.0273 U	**0.948**
		11/12/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.296**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	**0.236 J**
		05/26/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
MW124	Valley Street ROW, S side	03/29/17	Bladder	0.134 U	0.117 U	0.183 U	**1.60**	–	0.785 U	0.152 U	0.222 U	0.257 U	**0.596**	0.130 U	0.118 U	0.316 U
(dup)		03/29/17	Bladder	0.134 U	0.117 U	0.183 U	**1.22**	–	0.675 U	0.152 U	0.222 U	0.257 U	**0.433**	0.130 U	0.118 U	0.316 U
		06/15/17	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/13/18	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		10/11/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		01/30/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/03/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		08/03/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**1.14**	0.0572 UJ	0.0612 U	0.0560 UJ	0.0160 U	0.0200 UJ	0.0273 U	**0.526**
		11/18/20	Bladder	0.101 U	0.109 U	0.0620 U	**0.0480 J**	0.0900 U	**0.464**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
		06/08/21	Bladder	0.101 U	0.109 U	0.0620 U	**0.0480 J**	0.0900 U	**0.111 J**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 UJ	0.0273 U	0.191 U
MW128	Westlake Ave N ROW, E side	03/29/17	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**72.4**	0.316 U
		06/21/17	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.541**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**195**	0.316 U
		04/09/18	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**31.0**	0.316 U
		12/30/18[v]	Unknown	–	–	–	1.0 U	–	–	1.0 U	–	–	1.0 U	–	**110**	–
		07/18/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	**108**	0.316 U
		10/11/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	**13.3 J**	0.316 U
(dup)		10/11/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	**24.1 J**	0.316 U
		11/11/19[v]	Peristaltic	–	–	–	0.40 U	–	–	0.40 U	–	–	0.40 U	–	**60**	–
		01/20/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**47.4**	0.316 U
		02/18/20[v]	Unknown	–	–	–	0.40 U	–	–	0.40 U	–	–	0.40 U	–	**54**	–

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
MW128		04/27/20	Peristaltic	0.125 U	0.118 UJ	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 UJ	0.190 U	0.160 U	**53.2**	0.174 U
(continued)		06/29/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**31.3**	0.191 U
(split)		06/29/20[p]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	0.20 U	–	**34**	–
		08/26/20[p]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	0.20 U	–	**29**	–
		11/09/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.132 J**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**56.1**	0.191 U
		12/20/20[v]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	0.20 U	–	**34**	–
		02/11/21[v]	Unknown	–	–	–	0.20 U	–	–	0.20 U	–	–	0.20 U	–	**29**	–
		05/25/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**37.3**	0.191 U
MW-133	Property,	09/25/17	Bladder	0.134 U	0.117 U	0.183 U	**12.7**	–	**0.748**	**1.13**	0.222 U	0.257 U	**16.2**	0.130 U	**0.239 J**	0.316 U
	SW quadrant	04/25/18	Bladder	0.134 U	0.117 U	0.183 U	**0.646**	–	**0.837**	**0.315 J**	0.222 U	0.257 U	**0.516**	0.130 U	**3.51**	0.316 U
		10/26/18	Bladder	0.134 U	0.117 U	0.183 U	**1.92 J+**	–	0.412 U	**0.257 J**	0.222 U	0.257 U	**1.63 J+**	0.130 U	**3.43**	0.316 U
		12/12/18	Bladder	0.134 U	0.117 U	0.183 U	**1.71**	–	0.412 U	**0.454 J**	0.222 U	0.257 U	**2.75**	0.130 U	**5.95**	0.316 U
		02/01/19	Bladder	0.134 U	0.117 U	0.183 U	**22.4**	–	0.412 U	**0.588**	0.222 U	0.257 U	**9.29**	0.130 U	**4.36**	0.316 U
		03/13/19	Bladder	0.134 U	0.117 U	0.183 U	**4.45**	–	0.412 U	**0.483 J**	0.222 U	0.257 U	**5.92**	0.130 U	**10.8**	0.316 U
	Decommissioned March, 2019															
MW-137	Property,	09/25/17	Bladder	0.134 U	0.117 U	0.183 U	**15.0**	–	**3.90**	0.152 U	0.222 U	0.257 U	**19.1**	0.130 U	0.118 U	0.316 U
	SW quadrant	04/12/18	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**4.26**	0.316 U
		10/26/18	Bladder	0.134 U	0.117 U	0.183 U	**0.896 J+**	–	0.412 U	0.152 U	0.222 U	0.257 U	0.463 U	0.130 U	0.118 U	0.316 U
		12/12/18	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**0.357 J**	0.316 U
		02/01/19	Bladder	0.134 U	0.117 U	0.183 U	**1.48**	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**0.365 J**	0.316 U
		03/11/19	Bladder	0.134 U	0.117 U	0.183 U	**0.344 J**	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**0.179 J**	0.316 U
	Decommissioned March, 2019															
MW-138	Dexter Ave N ROW,	09/21/17	Bladder	0.268 U	0.234 U	0.366 U	0.398 U	–	**2.60**	0.304 U	0.444 U	0.514 U	0.306 U	0.260 U	0.236 U	0.632 U
	E side	04/11/18	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		10/29/18	Bladder	0.134 U	**0.146 J**	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**0.169 J**	0.316 U
		12/17/18	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		01/03/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.442 J**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		03/14/19	Bladder	0.134 U	0.117 U	0.183 U	**1.49**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.167 J**	0.130 U	0.118 U	0.316 U
		04/22/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 UJ	0.118 UJ	0.316 U
		07/19/19	Bladder	0.134 U	0.117 UJ	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		10/21/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		01/27/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		05/08/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	0.174 U
		07/27/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.468**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 UJ	0.0273 U	**0.356**
		11/18/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
		02/11/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.481**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	**0.686**
		06/07/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.589**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**0.0760 J**	0.191 U
MW-140	Roy Street ROW,	09/22/17	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.450 J**	0.130 U	0.118 U	0.316 U
(dup)	E side	09/22/17	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.456 J**	0.130 U	0.118 U	0.316 U
		04/12/18	Bladder	0.134 U	**0.178 J+**	0.183 U	**0.402 J+**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.572 J+**	0.130 U	**0.246 J+**	0.316 U
MW-141	Property,	09/22/17	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.941**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**0.457 J**	0.316 U
	SE quadrant	04/12/18	Submersible	0.134 U	0.117 U	0.183 U	**71.3 J+**	–	0.412 U	**5.68 J+**	0.222 U	0.257 U	**25.6 J+**	0.130 U	**7.01 J+**	0.316 U
		10/25/18	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		12/12/18	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**0.520**	0.316 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
MW-141		01/30/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
(continued)		03/11/19	Bladder	0.134 U	0.117 U	0.183 U	**0.701**	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**0.557**	0.316 U
	Decommissioned March, 2019															
MW-153	Roy St ROW, S side	05/01/18	Bladder	0.134 U	0.117 U	0.183 U	**0.756**	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**9.56**	0.316 U
		01/22/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**15.9**	0.316 U
		04/24/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 UJ	**2.69 J**	0.316 U
(dup)		04/24/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 UJ	**1.66 J**	0.316 U
		07/22/19	Bladder	**0.159 J**	0.117 U	0.183 U	0.199 U	–	**0.716**	0.152 U	0.222 U	0.257 U	**0.190 J**	0.130 UJ	**0.235 J**	**0.819 J**
		10/15/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		01/21/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/30/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	0.174 U
		07/15/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**1.79**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	0.191 U
		11/09/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.314**	0.0572 U	0.0612 U	**0.131 J**	0.0160 U	0.0200 U	**0.333**	0.191 U
		02/09/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.860**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**2.42**	**1.01**
(dup)		02/09/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.918**	**0.0680 J**	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**2.48**	**1.02**
		05/10/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 UJ	**1.15 J-**	**0.323**
MW-158A	8th Ave N ROW, E side	04/30/18	Bladder	0.134 U	0.117 U	0.183 U	**17.7**	–	**2.66**	**0.205 J**	0.222 U	0.257 U	**18.7**	0.130 U	**8.91**	0.316 U
		01/24/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.325 J**	0.130 U	**7.58**	0.316 U
		04/25/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.240 J**	0.130 UJ	**3.08 J**	0.316 U
		07/19/19	Bladder	0.134 U	0.117 UJ	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	**0.177 J**	0.130 U	**1.24**	0.316 U
		10/16/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	**0.318 J**	0.130 U	**2.18**	0.316 U
		01/21/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**0.195 J**	0.316 U
		04/24/20	Bladder	0.125 U	0.118 UJ	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 UJ	**0.251 J**	0.160 U	**1.45**	0.174 U
		07/15/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**1.11**	0.0572 U	0.0612 U	0.0560 UJ	**0.247**	0.0200 U	**0.882**	**0.366**
		11/23/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.104 U	0.0572 U	0.0612 U	0.0560 U	**0.0840**	0.0200 U	**0.447**	0.191 U
		02/02/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.532**	0.0572 U	0.0612 U	0.0560 U	**0.0680**	0.0200 U	**0.526**	**1.17**
		05/10/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.0750 J**	0.0572 U	0.0612 U	0.0560 UJ	**0.0920**	0.0200 UJ	**0.326 J-**	0.191 U
MW-160	8th Ave N ROW, W side	05/21/18	Bladder	0.134 U	0.117 U	0.183 U	**0.380 J**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.835**	0.130 U	0.118 U	**0.342 J**
		01/25/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.263 J**	0.130 U	0.118 U	0.316 U
		05/01/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.513**	0.130 UJ	0.118 UJ	0.316 U
		07/23/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 UJ	**0.326 J**	0.316 U
		10/17/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		01/29/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.195 J**	0.130 U	**0.744**	0.316 U
		04/01/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	**3.18**	0.130 U	0.118 U	0.316 U
		08/03/20	Bladder	0.101 U	0.109 U	0.0620 U	**0.203**	0.0900 U	**1.04**	**0.144 J**	0.0612 U	0.0560 UJ	**3.61**	0.0200 U	**1.17 J**	**0.321**
		11/30/20	Bladder	0.101 U	0.109 U	0.0620 U	**0.828**	0.0900 U	**0.177 J**	**0.228**	0.0612 U	0.0560 U	**10.2**	0.0200 U	**3.59**	**0.827**
		02/05/21	Bladder	0.101 U	0.109 U	0.0620 U	**0.0550 J**	0.229 U	**0.526**	**0.192 J+**	0.0612 U	0.0560 U	**1.65**	0.0200 U	**17.1 J**	**1.17**
		05/12/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.237**	**0.0700 J**	0.0612 U	0.0560 U	**0.353**	0.0200 U	**4.05**	0.191 U
MW-161	8th Ave N ROW, W side	05/21/18	Bladder	0.134 U	0.117 U	0.183 U	**2.01**	–	0.412 U	0.152 U	0.222 U	0.257 U	**1.79**	0.130 U	0.118 U	**0.329 J**
		01/25/19	Bladder	0.134 U	0.117 U	0.183 U	**0.472 J**	–	0.412 U	0.152 U	0.222 U	0.257 U	**1.66**	0.130 U	0.118 U	0.316 U
		05/01/19	Bladder	0.134 U	0.117 U	0.183 U	**0.482 J**	–	0.412 U	0.152 U	0.222 U	0.257 U	**1.66**	0.130 UJ	0.118 UJ	0.316 U
		07/18/19	Bladder	0.134 U	0.117 U	0.183 U	**0.264 J**	–	0.412 U	0.152 U	0.222 U	0.257 UJ	**1.53**	0.130 U	0.118 U	0.316 U
		10/14/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	**0.978**	0.130 U	0.118 U	0.316 U
		01/28/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**0.388 J**	0.222 U	0.257 U	**6.05**	0.130 U	**1.10**	0.316 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
MW-161 (continued)		04/03/20	Bladder	0.134 U	0.117 U	0.183 U	**16.7**	–	0.412 U	**1.27**	0.222 U	0.257 U	**27.0**	0.130 U	**1.92**	0.316 U
		07/31/20	Bladder	0.101 U	0.109 U	0.0620 U	**40.6**	0.0900 UJ	**0.0536 J**	**1.17 J**	0.0612 U	0.0560 UJ	**42.5**	0.0200 UJ	**4.27**	0.191 U
		12/01/20	Bladder	0.101 U	0.109 U	0.0620 U	**49.0**	0.0900 U	**0.0740 J**	**1.74**	0.0612 U	0.0560 U	**50.3**	0.0200 U	**5.47**	0.191 U
		02/05/21	Bladder	0.101 U	0.109 U	0.0620 U	**24.4**	0.0900 UJ	**0.0590 J**	**2.32 J**	0.0612 U	0.0560 U	**55.8**	0.0200 U	**9.28 J**	0.191 U
		05/25/21	Bladder	0.101 U	0.109 U	0.0620 U	**1.08**	0.0900 U	0.165 U	**1.11**	0.0612 U	0.0560 U	**28.3**	0.0200 UJ	**5.35**	0.191 U
MW-162	Property, NE quadrant	02/05/19	Bladder	1.00 U	1.00 U	1.00 U	**2,800**	–	1.00 U	**9.58**	1.00 U	–	**613**	1.00 U	**128**	1.00 U
		03/12/19	Peristaltic	0.134 U	0.117 U	0.183 U	**613**	–	0.412 U	**2.63**	0.222 U	0.257 U	**538**	0.130 U	**46.5**	0.316 U
	Decommissioned March, 2019															
MW-163	Property, NW quadrant	02/05/19	Bladder	1.00 U	1.00 U	1.00 U	**218**	–	1.00 U	1.00 U	1.00 U	–	**150**	1.00 U	**2.95**	1.00 U
	(dup)	02/05/19	Bladder	1.00 U	1.00 U	1.00 U	**220**	–	1.00 U	1.00 U	1.00 U	–	**153**	1.00 U	**3.45**	1.00 U
		03/12/19	Bladder	0.134 U	0.117 U	0.183 U	**282**	–	0.412 U	**2.87**	0.222 U	0.257 U	**334**	0.130 U	**1.10**	0.316 U
	Decommissioned March, 2019															
MW-164	Property, SW quadrant	02/05/19	Bladder	1.00 U	1.00 U	1.00 U	**871**	–	**1.80**	**3.41**	1.00 U	–	**372**	1.00 U	**4.41**	1.00 U
		03/12/19	Bladder	0.134 U	0.117 U	0.183 U	**444**	–	0.412 U	**4.24**	0.222 U	0.257 U	**327**	0.130 U	**7.80**	0.316 U
	Decommissioned March, 2019															
MW-304	Dexter Ave N ROW, E side	10/21/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.728**	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		01/27/20	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		05/07/20	Bladder	0.125 UJ	0.118 U	0.127 UJ	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	0.174 U
		07/27/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**2.63**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 UJ	0.0273 U	0.191 U
		05/18/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.357**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 UJ	0.0273 U	0.191 U
MW-319	9th Ave N ROW, W side	10/08/19	Bladder	0.134 U	0.117 U	0.183 U	**0.609**	–	0.412 U	0.152 U	0.222 U	0.257 U	**8.12**	0.130 U	**5.76**	0.316 U
		01/16/20	Peristaltic	0.134 U	0.117 U	0.183 U	**0.414 J**	–	0.412 U	0.152 U	0.222 U	0.257 U	**11.4**	0.130 U	**6.78**	0.316 U
		04/27/20	Bladder	0.125 U	0.118 UJ	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 UJ	**10.7**	0.160 U	**4.52**	0.174 U
		07/27/20	Bladder	0.101 U	0.109 U	0.0620 U	**0.0933 J**	0.0900 U	**0.399**	**0.0806 J**	0.0612 U	0.0560 U	**13.6**	0.0200 UJ	**4.77**	**0.207 J**
		11/12/20	Bladder	0.101 U	0.109 U	0.0620 U	**0.110**	0.0900 U	0.0500 UJ	0.0572 U	0.0612 U	0.0560 UJ	**13.9**	0.0200 U	**4.58 J+**	0.191 U
		05/19/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.0900 J**	0.0900 U	0.0700 U	**0.104 J**	0.0612 U	0.0560 U	**8.52**	0.0200 UJ	**4.16**	0.191 U
MW-323	9th Ave N ROW, W side	10/09/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**4.97**	0.152 U	0.222 U	0.257 U	**0.891**	0.130 U	**13.4**	0.316 U
		01/20/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.549**	0.152 U	0.222 U	0.257 U	**0.178 J**	0.130 U	**64.9**	0.316 U
		04/23/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	**4.14**	0.174 U
		07/07/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**1.76**	0.0572 U	0.0612 U	0.0560 U	**0.0300 J**	0.0200 U	**4.58**	0.191 U
		11/24/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0960 U	0.0572 U	0.0612 U	0.0560 U	**0.0260 J**	0.0200 U	**4.89**	0.191 U
		05/20/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.114 U	**0.111 J**	0.0612 U	0.0560 U	**0.0900**	0.0200 UJ	**31.4**	0.191 U
MW-324	Roy St ROW, N side	10/02/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	**5.45**	**3.21**	0.222 U	0.257 U	**0.642**	0.130 U	**61.9**	0.316 U
		01/20/20	Peristaltic	6.70 U	5.85 U	9.15 U	9.95 U	–	20.6 U	7.60 U	11.1 U	12.9 U	7.65 U	6.50 U	**113**	15.8 U
		04/24/20	Bladder	6.25 U	5.90 UJ	6.35 U	15.0 U	–	13.9 U	**16.8 J**	5.90 U	23.4 UJ	9.50 U	8.00 U	**362**	8.70 U
		07/07/20	Bladder	5.05 U	5.45 U	3.10 U	1.40 U	4.50 U	2.50 U	**13.6**	3.06 U	2.80 U	0.800 U	1.00 U	**244**	9.55 U
		11/13/20	Bladder	5.05 U	5.45 U	3.10 U	1.40 U	4.50 UJ	2.50 U	**13.7**	3.06 U	2.80 UJ	0.800 U	1.00 U	**184**	9.55 U
		05/20/21	Peristaltic	5.05 U	5.45 U	3.10 U	1.40 U	4.50 U	2.50 U	**10.5**	3.06 U	2.80 U	**1.95 J**	1.00 UJ	**45.6**	9.55 U
MW-326	Mercer Street ROW, N side	10/03/19	Bladder	0.134 U	0.117 U	0.183 U	**0.769**	–	**1.31**	0.152 U	0.222 U	0.257 U	**0.297 J**	0.130 U	0.118 U	0.316 U
		01/17/20	Bladder	0.134 U	0.117 U	0.183 U	**0.834**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.470 J**	0.130 U	0.118 UJ	0.316 U
		04/21/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	**0.515 J**	0.174 U
		07/23/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.120 J**	0.0572 U	0.0612 U	0.0560 UJ	**0.0430**	0.0200 U	**0.201**	0.191 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
MW-326 (continued)		11/02/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.165 J**	0.0572 U	0.0612 U	0.0560 U	**0.0260 J**	0.0200 U	**0.332**	0.191 U
		02/09/21	Bladder	0.101 U	0.109 U	0.0620 U	**0.183**	0.0900 U	**0.540**	0.0572 U	0.0612 U	0.0560 U	**0.263 J+**	0.0200 U	**0.182 J**	**0.427**
		05/18/21	Bladder	0.101 U	0.109 U	0.0620 U	**0.219**	0.0900 U	**0.206**	0.0572 U	0.0612 U	0.0560 U	**0.496**	0.0200 UJ	**0.109**	0.191 U
MW-328	Lake Union Park, S end	10/02/19	Bladder	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.535**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**23.3**	0.316 U
		01/17/20	Peristaltic	0.134 U	0.117 U	0.183 U	**1.66**	–	**0.448 J**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**13.1 J**	0.316 U
		04/08/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	**11.1**	0.316 U
		07/07/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**20.7**	0.191 U
		11/09/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**7.99**	0.191 U
		05/25/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0540 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**8.57**	0.191 U
MW-329 (dup)	Westlake Ave N ROW, E side	10/03/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.435 J**	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**28.8**	0.316 U
		10/03/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**29.2**	0.316 U
		01/20/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**26.2**	0.316 U
		04/27/20	Bladder	0.125 U	0.118 UJ	0.127 U	0.300 U	–	**0.434 J**	0.149 U	0.118 U	0.467 UJ	0.190 U	0.160 U	**23.6**	0.174 U
		08/03/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**1.06**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	**32.2**	0.191 U
		11/09/20	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.106 J**	0.0572 U	0.0612 U	**0.116 J**	0.0160 U	0.0200 U	**23.0**	0.191 U
		05/25/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**23.0**	0.191 U
MW-336	Mercer St ROW, N side	05/05/20	Bladder	0.125 U	0.118 U	0.127 U	0.300 U	–	**0.318 J**	0.149 U	0.118 U	0.467 UJ	**0.304 J**	0.160 U	**6.03**	0.174 U
		07/08/20	Bladder	0.101 U	0.109 U	0.0620 U	**0.600**	0.0900 UJ	**1.21**	**0.127**	0.0612 U	0.0560 UJ	**6.08**	0.0200 U	**7.71**	0.191 U
		11/02/20	Bladder	0.101 U	0.109 U	0.0620 U	**0.172**	**0.170 J**	**0.301**	**0.0910 J**	0.0612 U	0.0560 U	**3.52**	0.0200 U	**5.80**	0.191 U
		02/10/21	Bladder	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.328**	**0.189 J**	0.0612 U	0.0560 U	**1.86**	0.0200 U	**8.18**	**0.225 J**
		05/26/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.120**	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	**3.12 J+**	0.0200 U	**10.7**	0.191 U
MW-341	Lake Union Park, S end	05/12/20	Peristaltic	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	**10.4**	0.174 U
		07/07/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	**0.0500**	0.0200 U	**9.86**	0.191 U
		11/09/20	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.0740 J**	0.0900 U	**0.167 J**	0.0572 U	0.0612 U	0.0560 U	**0.102**	0.0200 U	**5.99**	0.191 U
		05/25/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	**2.71 J+**	0.105 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 UJ	**26.7**	0.191 U
MW-342	Valley St ROW, S side	05/04/20	Peristaltic	0.125 U	0.118 U	0.127 U	0.300 U	–	**0.366 J**	0.149 U	0.118 U	0.467 UJ	0.190 U	0.160 U	**1.51**	0.174 U
		07/30/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**1.24**	0.0572 UJ	0.0612 U	0.0560 UJ	0.0160 U	0.0200 UJ	**3.12**	**0.723**
		11/17/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**1.87**	0.191 U
		06/04/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**2.54**	0.191 U
MW-343	Valley St ROW, S side	05/04/20	Peristaltic	0.125 U	0.118 U	0.127 U	0.300 U	–	**0.620**	0.149 U	0.118 U	0.467 UJ	0.190 U	0.160 U	0.234 U	**0.207 J**
		07/30/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**1.57**	0.0572 UJ	0.0612 U	0.0560 UJ	0.0160 U	0.0200 UJ	0.0273 U	**0.931**
		11/24/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	0.0273 U	0.191 U
		06/04/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**3.81**	0.191 U
Treatment Zone A Wells																
IW-4A	Property, NW quadrant Decommissioned March, 2019	03/28/18	Peristaltic	0.134 U	0.117 U	0.183 U	**9,470**	–	**0.589**	**9.77**	0.222 U	0.257 U	**1,100**	0.130 U	**306**	0.316 U
IW-7A	Property, NE quadrant Decommissioned March, 2019	04/02/18	Peristaltic	0.134 U	0.117 U	0.183 U	**0.335 J**	–	0.412 U	**0.295 J**	0.222 U	0.257 U	**2.09**	0.130 U	**1.20**	0.316 U
IW-9A	Property, NW quadrant Decommissioned March, 2019	03/29/18	Peristaltic	0.134 U	0.117 U	0.183 U	**3,230**	–	0.412 U	**2.36**	0.222 U	0.257 U	**299**	0.130 U	**102**	0.316 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
IW-18A	Property, NE quadrant Decommissioned March, 2019	03/30/18	Peristaltic	0.134 U	0.117 U	0.183 U	**16,500**	–	**2.07**	**13.6**	0.222 U	0.257 U	**3,300**	0.130 U	**478**	**0.507 J**
IW-22A	Property, NE quadrant Decommissioned March, 2019	04/02/18	Peristaltic	0.134 U	0.117 U	0.183 U	**3.88**	–	0.412 U	**6.88**	0.222 U	0.257 U	0.153 U	0.130 U	**232**	0.316 U
IW-37A	Property, SW quadrant Decommissioned March, 2019	03/28/18	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**0.419 J**	0.222 U	0.257 U	0.153 U	0.130 U	**55.9**	0.316 U
IW-41A	Property, SW quadrant Decommissioned March, 2019	04/10/18	Peristaltic	0.134 U	0.117 UJ	0.183 U	**37.3**	–	0.412 U	**1.89**	0.222 U	0.257 U	**28.0**	0.130 U	**78.2**	6.32 U
IW-42A	Property, SW quadrant Decommissioned March, 2019	04/10/18	Peristaltic	0.134 U	0.117 UJ	0.183 U	**7,700**	–	**0.726**	**14.5**	0.222 U	0.257 U	**1,840**	0.130 U	**1,280**	79.0 U
IW-45A	Property, SW quadrant Decommissioned March, 2019	04/04/18	Peristaltic	0.134 U	0.117 U	0.183 U	**9,250**	–	**0.749**	**14.5**	0.222 U	0.257 U	**7,460**	0.130 U	**2,020**	**0.361 J**
IW-46A	Property, SE quadrant Decommissioned March, 2019	03/28/18	Peristaltic	0.134 U	0.117 U	0.183 U	**0.200 J**	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**284**	0.316 U
IW-48A	Property, SE quadrant Decommissioned March, 2019	04/02/18	Peristaltic	0.134 U	0.117 U	0.183 U	**0.425 J**	–	0.412 U	**1.04**	0.222 U	0.257 U	**0.622**	0.130 U	**16.3**	0.316 U
MW-165	Property, NE quadrant	11/04/19	Peristaltic	0.134 U	0.117 U	0.183 U	**3.95**	–	0.412 U	**91.1**	0.222 U	0.257 U	**20.2**	0.130 U	**642**	0.316 U
		01/30/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**2.56**	0.222 U	0.257 U	0.153 U	0.130 U	**9.64**	0.316 U
		05/01/20	Peristaltic	0.125 U	0.118 U	0.127 U	**0.423 J**	–	**0.311 J**	**2.19**	0.118 U	0.467 U	**0.353 J**	0.160 U	**24.3**	0.174 U
		07/09/20	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.130**	0.0900 U	**0.389**	**3.78**	0.0612 U	0.0560 UJ	**0.250**	0.0200 U	**77.3**	0.191 U
		11/05/20	Flowing	0.101 U	0.109 U	0.0620 U	0.0280 U	1.46 U	**0.633**	**12.6**	0.0612 U	0.0560 UJ	**0.276**	0.0200 U	**1,160**	0.191 U
(dup)		11/05/20	Flowing	0.101 U	0.109 U	0.0620 U	0.0280 U	1.50 U	**0.625**	**13.0**	0.0612 U	0.0560 UJ	**0.280**	0.0200 U	**1,170**	0.191 U
		02/04/21	Flowing	0.101 U	0.109 U	0.0620 U	0.0280 U	**10.1**	**1.30**	**23.5**	0.0612 U	0.0560 U	**0.167**	0.0200 U	**1,690**	**0.369**
		05/06/21	Flowing	1.01 U	1.09 U	0.620 UJ	0.280 U	**7.75**	0.820 U	**15.2**	0.612 U	0.560 UJ	0.160 U	0.200 U	**301**	1.91 U
MW-169	Property, SW quadrant	11/05/19	Peristaltic	0.134 U	0.117 U	0.183 U	**2.72**	–	0.412 U	**11.9**	0.222 U	0.257 U	**1.15**	0.130 U	**1,500**	0.316 U
		01/23/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.995 U	–	0.412 U	**6.97**	0.222 U	0.257 U	**1.51 J**	0.130 U	**275**	0.316 U
		05/05/20	Peristaltic	0.125 U	0.118 U	0.127 U	0.300 U	–	**0.388 J**	**2.20**	0.118 U	0.467 U	0.190 U	0.160 U	**40.5**	**0.493 J**
		07/10/20	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.0390 J**	**0.265 J**	**1.01**	**3.06**	0.0612 U	0.0560 UJ	**0.0490**	0.0200 U	**77.9**	**0.834**
		11/03/20	Flowing	0.101 U	0.109 U	0.0620 U	**6.26**	0.0900 UJ	**0.123 J**	**1.00**	0.0612 U	0.0560 U	**1.78**	0.0200 U	**5.57**	0.191 U
		02/17/21	Flowing	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.0570 J**	**0.704**	0.0612 U	0.0560 U	**0.0460**	0.0200 U	**1.72**	0.191 U
		05/07/21	Flowing	0.101 U	0.109 U	0.0620 U	0.0280 U	**2.23**	0.179 U	**0.469**	0.0612 U	0.0560 UJ	**0.0340 J**	0.0200 U	**0.680**	0.191 U
MW-173	Property, SE quadrant	11/01/19	Peristaltic	0.134 U	0.117 U	0.183 U	**0.704**	–	0.412 U	**2.31**	0.222 U	0.257 U	**0.484 J**	0.130 U	**67.2**	0.316 U
		01/28/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**2.43**	0.222 U	0.257 U	**0.302 J**	0.130 U	**116**	0.316 U
		05/01/20	Peristaltic	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	**1.88**	0.118 U	0.467 U	0.190 U	0.160 U	**7.87**	**0.225 J**

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
MW-173		07/09/20	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.360**	0.0900 U	**0.632**	**2.87**	0.0612 U	0.0560 UJ	**0.218**	0.0200 U	**26.2**	**0.371**
(continued)		11/05/20	Flowing	0.101 U	0.109 U	0.0620 U	0.0280 U	**0.844**	0.0500 U	**3.30**	0.0612 U	0.0560 UJ	**0.0865**	0.0200 U	**105**	0.191 U
		02/04/21	Flowing	0.101 U	0.109 U	0.0620 U	0.0280 U	**13.5**	**0.191 J**	**3.85**	0.0612 U	0.0560 U	**0.0520**	0.0200 U	**33.6**	0.191 U
		05/05/21	Flowing	0.101 U	0.109 U	0.0620 U	0.0280 U	**9.19**	0.192 U	**2.68**	0.0612 U	0.0560 U	**0.0530**	0.0200 U	**15.8**	**0.229 J**
MW-177	Property, SW quadrant	11/06/19	Peristaltic	**0.161 J**	0.117 U	0.183 U	**3,180**	–	**4.14**	**395 J**	0.222 U	0.257 UJ	**1,710**	0.130 U	**11,000**	**2.77**
		01/24/20	Peristaltic	6.70 U	5.85 U	9.15 U	**26,400**	–	20.6 U	**265**	11.1 U	12.9 U	**7,440**	6.50 U	**8,440**	15.8 U
		04/01/20	Peristaltic	670 U	585 U	915 U	**27,900**	–	2,060 U	760 U	1,110 U	1,290 UJ	**6,980**	650 U	**9,860**	1,580 U
		07/10/20	Peristaltic	505 U	545 U	310 U	**29,400**	450 U	250 U	**345 J**	306 U	280 UJ	**6,520**	100 U	**9,450**	955 U
		11/03/20	Flowing	101 U	109 U	62.0 U	**7,170**	90.0 U	50.0 U	57.2 U	61.2 U	56.0 UJ	**861**	20.0 U	**6,740**	191 U
		02/18/21	Flowing	20.2 U	21.8 U	12.4 U	**10,900**	18.0 U	10.0 U	**50.0**	12.2 U	11.2 U	**2,010**	4.00 U	**6,310**	38.2 U
		05/06/21	Flowing	20.2 U	21.8 U	12.4 U	**10,100**	18.0 U	10.0 U	**50.2**	12.2 U	11.2 U	**2,440**	4.00 U	**4,900**	38.2 U
MW-181	Property, SW quadrant	11/08/19	Peristaltic	0.670 U	0.585 U	0.915 U	99.5 U	–	2.06 U	**237**	0.222 U	0.257 UJ	76.5 U	0.130 U	**10,700**	1.58 U
		01/27/20	Peristaltic	67.0 U	58.5 U	91.5 U	99.5 U	–	206 U	**151 J**	111 U	129.0 U	76.5 U	65.0 U	**9,660**	158 U
		04/01/20	Peristaltic	67.0 U	58.5 U	91.5 U	99.5 U	–	206 U	**120 J**	111 U	129.0 UJ	76.5 U	65.0 U	**10,000**	158 U
		07/08/20	Peristaltic	50.5 U	54.5 U	31.0 U	14.0 U	45.0 UJ	25.0 U	**121**	30.6 U	28.0 UJ	8.00 U	10.0 U	**6,150**	95.5 U
		11/04/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	**0.409 J-**	**0.188 J**	**58.9**	0.0612 U	0.0560 UJ	**0.147**	0.0200 U	**6,650**	0.191 U
		02/19/21	Flowing	10.1 U	10.9 U	6.20 U	2.80 U	9.00 U	5.00 U	**43.4**	6.12 U	5.60 U	1.60 U	2.00 U	**7,850**	19.1 U
		05/06/21	Peristaltic	10.1 U	10.9 U	6.20 U	**23.8**	9.00 U	5.00 U	**23.2**	6.12 U	5.60 U	1.60 U	2.00 U	**6,960**	19.1 U
MW-185	Property, SE quadrant	10/31/19	Flowing	0.134 U	0.117 U	0.183 U	**2.57**	–	0.412 U	**5.47**	0.222 U	0.257 U	**3.51**	0.130 U	**179**	0.316 U
		01/29/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**1.52**	0.222 U	0.257 U	0.153 U	0.130 U	**1.66**	0.316 U
		04/02/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**0.729**	0.222 U	0.257 U	0.153 U	0.130 U	**0.512**	0.316 U
		07/08/20	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.0570 J**	**2.24 J**	**0.545**	**0.375**	0.0612 U	0.0560 UJ	**0.0760**	0.0200 U	**0.883**	**0.432**
		11/04/20	Flowing	0.101 U	0.109 U	0.0620 U	**0.0313 J**	**6.76 J-**	**0.0656 J**	**0.0586 J**	0.0612 U	0.0560 UJ	**0.0895**	0.0200 U	**0.900**	0.191 U
		02/16/21	Flowing	0.101 U	0.109 U	0.0620 U	0.0280 U	**4.60**	**0.0550 J**	0.0572 U	0.0612 U	0.0560 U	**0.0790**	0.0200 U	**1.19 J+**	0.191 U
		05/07/21	Flowing	0.101 U	0.109 U	0.0620 U	**0.168**	**2.42**	0.0640 U	**0.0820 J**	0.0612 U	0.0560 UJ	**0.0870**	0.0200 U	**4.73**	0.191 U
Treatment Zone B Wells																
IW-3B	Property, NW quadrant Decommissioned March, 2019	03/28/18	Peristaltic	0.134 U	0.117 U	0.183 U	**360**	–	**0.446 J**	**10.7**	0.222 U	0.257 U	**459**	0.130 U	**395**	0.316 U
IW-6B	Property, SW quadrant Decommissioned March, 2019	04/02/18	Peristaltic	0.134 U	0.117 U	0.183 U	**590**	–	**0.453 J**	**13.6**	0.222 U	0.257 U	**847**	0.130 U	**24.1**	0.316 U
IW-8B	Property, SW quadrant Decommissioned March, 2019	03/30/18	Peristaltic	0.134 U	0.117 U	0.183 U	**25.2**	–	0.412 U	0.152 U	0.222 U	0.257 U	**21.8**	0.130 U	**0.403 J**	0.316 U
IW-17B	Property, NE quadrant Decommissioned March, 2019	03/30/18	Peristaltic	0.134 U	0.117 U	0.183 U	**60,100**	–	**3.71**	**228 J**	0.222 U	0.257 U	**11,500**	0.130 U	**3,230**	**2.54**
IW-21B	Property, NE quadrant Decommissioned March, 2019	04/02/18	Peristaltic	0.134 U	0.117 U	0.183 U	**1.51**	–	**0.438 J**	**58.5**	0.222 U	0.257 U	**148**	0.130 U	**1,200**	0.316 U
IW-22B	Property, NW quadrant Decommissioned March, 2019	04/25/18	Peristaltic	2.68 U	2.34 U	3.66 U	**62,600**	–	**17.7**	**128**	4.44 U	5.14 U	**6,000**	2.60 U	**9,680**	6.32 U
IW-24B	Property, NE quadrant Decommissioned March, 2019	03/30/18	Peristaltic	0.134 U	0.117 U	0.183 U	**48,800**	–	**6.26 J+**	**274**	0.222 U	0.257 U	**20,100**	0.130 U	**2,040**	**4.55**
IW-28B	Property, NW quadrant Decommissioned March, 2019	04/09/18	Peristaltic	0.134 U	0.117 U	0.183 U	**4.71**	–	0.412 U	**0.174 J**	0.222 U	0.257 U	**2.42**	0.130 U	**3.66**	0.316 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
IW-33B	Property, NE quadrant Decommissioned March, 2019	04/02/18	Peristaltic	0.134 U	0.117 U	0.183 U	**31.6**	–	**2.30**	**228**	0.222 U	0.257 U	**1,800**	0.130 U	**2,410**	0.316 U
IW-37B	Property, SW quadrant Decommissioned March, 2019	03/29/18	Peristaltic	0.134 U	0.117 U	0.183 U	**1.82**	–	0.412 U	**33.0**	0.222 U	0.257 U	**0.497 J**	0.130 U	**2,420**	0.316 U
IW-45B	Property, SE quadrant Decommissioned March, 2019	03/28/18	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**7.09**	0.222 U	0.257 U	**0.215 J**	0.130 U	**150**	0.316 U
IW-47B	Property, SW quadrant Decommissioned March, 2019	04/10/18	Bladder	0.670 U	0.585 UJ	0.915 U	**144**	–	2.06 U	**46.3**	1.11 U	1.28 U	**170**	0.650 U	**3,360**	316 U
IW-49B	Property, SE quadrant Decommissioned March, 2019	03/28/18	Peristaltic	0.134 U	0.117 U	0.183 U	**0.307 J**	–	0.412 U	**1.49**	0.222 U	0.257 U	**0.572**	0.130 U	**668**	0.316 U
IW-51B	Property, SE quadrant Decommissioned March, 2019	03/28/18	Peristaltic	0.134 U	0.117 U	0.183 U	**0.437 J**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.817**	0.130 U	**20.5**	0.316 U
MW-166	Property, NE quadrant	11/04/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.526**	**47.0**	0.222 U	0.257 U	**0.467 J**	0.130 U	**1,420**	0.316 U
		01/30/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**11.4**	0.222 U	0.257 U	0.153 U	0.130 U	**250**	0.316 U
		05/01/20	Peristaltic	0.125 U	0.118 U	0.127 U	0.300 U	–	0.278 U	**2.03**	0.118 U	0.467 U	0.190 U	0.160 U	**29.5**	0.174 U
		07/09/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	**2.31**	**1.13**	**1.41**	0.0612 U	0.0560 UJ	**0.0520**	0.0200 U	**42.3**	**0.605**
(dup)		07/09/20	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.130**	**2.24**	**1.04**	**1.50**	0.0612 U	0.0560 UJ	**0.0930**	0.0200 U	**45.1**	**0.602**
		11/05/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	**0.855**	**0.143 J**	**27.4**	0.0612 U	0.0560 UJ	**0.271**	0.0200 U	**3,380**	0.191 U
		02/04/21	Flowing	50.5 U	54.5 U	31.0 U	14.0 U	45.0 UJ	25.0 U	**63.0 J+**	30.6 U	28.0 U	8.00 U	10.0 U	**3,760 J**	95.5 U
		05/05/21	Flowing	20.2 U	21.8 U	12.4 UJ	5.60 U	18.0 U	10.0 U	**42.4**	12.2 U	11.2 UJ	3.20 U	4.00 U	**2,020**	38.2 U
MW-170	Property, SW quadrant	11/05/19	Peristaltic	0.134 U	0.117 U	0.183 U	**105**	–	**0.916**	**172**	0.222 U	0.257 U	**125**	0.130 U	**6,710**	**0.796 J**
		01/23/20	Peristaltic	3.35 U	2.93 U	4.58 U	**7,070**	–	10.3 U	**136**	5.55 U	6.43 U	**5,780**	3.25 U	**5,920**	7.90 U
		04/02/20	Peristaltic	67.0 U	58.5 U	91.5 U	**2,470**	–	206 U	**160 J**	111 U	129 UJ	**3,100**	65.0 U	**5,940**	158 U
		07/09/20	Peristaltic	1.01 U	1.09 U	0.620 U	**2,340**	0.900 U	**2.54**	**211**	0.612 U	0.560 UJ	**3,050**	0.200 U	**7,520**	1.91 U
		11/03/20	Peristaltic	1.01 U	1.09 U	0.620 U	**17.6 J**	0.900 UJ	0.500 U	**160**	0.612 U	0.560 U	**18.3**	0.200 U	**11,500**	1.91 U
		02/17/21	Peristaltic	1.01 U	1.09 U	0.620 U	**0.730 J**	0.900 U	**0.670 J**	**156**	0.612 U	0.560 U	**4.90**	0.200 U	**14,400**	**2.82**
		05/07/21	Peristaltic	50.5 U	54.5 U	31.0 U	14.0 U	45.0 U	25.0 U	**178**	30.6 U	28.0 UJ	8.00 U	10.0 U	**12,000**	95.5 U
MW-174	Property, SE quadrant	11/01/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**1.07**	0.222 U	0.257 U	0.153 U	0.130 U	**6.85**	0.316 U
		01/28/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**1.05**	0.222 U	0.257 U	0.153 U	0.130 U	**0.529**	0.316 U
		05/01/20	Peristaltic	0.125 U	0.118 U	0.127 U	0.300 U	–	**0.701**	**0.653**	0.118 U	0.467 U	0.190 U	0.160 U	**1.04**	**0.710 J**
		07/09/20	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.259**	0.0900 U	**0.901**	**1.31**	0.0612 U	0.0560 UJ	**0.184**	0.0200 U	**2.32**	**0.511**
		11/05/20	Flowing	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	**2.05**	0.0612 U	0.0560 UJ	**0.177**	0.0200 U	**3.11**	0.191 U
		02/04/21	Flowing	0.101 U	0.109 U	0.0620 U	**0.0400 J**	0.0900 U	**0.121 J**	**1.17**	0.0612 U	0.0560 U	**0.0980**	0.0200 U	**2.38**	0.191 U
		05/05/21	Flowing	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.0500 U	**0.911**	0.0612 U	0.0560 U	**0.102**	0.0200 U	**1.85**	0.191 U
MW-178	Property, SW quadrant	11/06/19	Peristaltic	0.134 U	0.117 U	0.183 U	3.98 U	–	**0.477 J**	**24.6**	0.222 U	0.257 UJ	3.06 U	0.130 U	**877**	0.316 U
		01/24/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**9.15**	0.222 U	0.257 U	0.153 U	0.130 U	**2.14**	**0.383 J**
		04/02/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**4.20**	0.222 U	0.257 UJ	0.153 U	0.130 U	**2.79**	0.316 U
		07/10/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	**0.784**	**1.12**	**3.35**	0.0612 U	0.0560 UJ	**0.0750**	0.0200 U	**0.562**	**0.749**
		11/03/20	Peristaltic	0.101 U	0.109 U	0.0620 U	**1.41 J**	0.0900 UJ	**0.524**	**44.0**	0.0612 U	0.0560 U	**0.895**	0.0200 U	**15.3**	**0.414**
		02/18/21	Peristaltic	2.02 U	2.18 U	1.24 U	**2.40**	**4.24 J**	1.00 U	**34.3**	1.22 U	1.12 U	**0.840**	0.400 U	**1,230**	3.82 U
		05/06/21	Peristaltic	2.02 U	2.18 U	1.24 U	**10.3**	1.80 U	1.00 U	**33.6**	1.22 U	1.12 U	0.320 U	0.400 U	**2,680**	3.82 U
MW-182	Property, SW quadrant	11/08/19	Peristaltic	0.134 U	0.117 U	0.183 U	**1,570**	–	**0.519**	**89.4 J**	0.222 U	0.257 UJ	**794**	0.130 U	**1,560**	**0.573 J**
		01/27/20	Peristaltic	67.0 U	58.5 U	91.5 U	**160 J**	–	206 U	76.0 U	111 U	129 U	**115 J**	65.0 U	**1,550**	158 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
MW-182		04/01/20	Peristaltic	6.70 U	5.85 U	9.15 U	**1,480**	–	20.6 U	**25.0 J**	11.1 U	12.9 U	**169**	6.50 U	**2,040**	15.8 U
(continued)		07/08/20	Peristaltic	5.05 U	5.45 U	3.10 U	**126**	4.50 UJ	2.50 U	**16.2**	3.06 U	2.80 UJ	**28.0**	1.00 U	**1,350**	9.55 U
		11/04/20	Peristaltic	5.05 U	5.45 U	3.10 U	**208**	4.50 UJ	**2.51 J**	**281**	3.06 U	2.80 UJ	**226**	1.00 U	**18,900**	9.55 U
		02/19/21	Peristaltic	50.5 U	54.5 U	31.0 U	**259**	45.0 U	25.0 U	**269**	30.6 U	28.0 U	**99.5**	10.0 U	**31,100**	95.5 U
		05/06/21	Peristaltic	202 U	218 U	124 U	**6,650**	180 U	100 UJ	**226 J**	122 U	112 UJ	**384**	40.0 U	**31,000**	382 UJ
(dup)		05/06/21	Peristaltic	**0.176 J**	0.109 U	0.0620 U	**8,900**	0.0900 U	**1.05 J**	**195**	0.0612 U	0.0560 U	**469**	0.0200 U	**30,600**	**2.99 J**
MW-186	Property, SE quadrant	10/31/19	Flowing	0.134 U	0.117 U	0.183 U	**0.199 J**	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**23.4**	0.316 U
		01/29/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**28.2**	0.316 U
		04/02/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.205 U	0.130 U	**5.93**	0.316 U
		07/08/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	**0.264 J**	**1.91**	0.0572 U	0.0612 U	0.0560 UJ	**0.0850**	0.0200 U	**4.02**	**0.688**
		11/04/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	**0.574 J-**	**0.112 J**	**1.06**	0.0612 U	0.0560 UJ	**0.177**	0.0200 U	**2.26**	0.191 U
		02/16/21	Flowing	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.0770 J**	**1.26**	0.0612 U	0.0560 U	**0.143**	0.0200 U	**6.52 J+**	0.191 U
		05/07/21	Flowing	0.101 U	0.109 U	0.0620 U	**0.179**	**1.07**	0.0950 U	**0.892**	0.0612 U	0.0560 UJ	**0.123**	0.0200 U	**4.67**	0.191 U
Treatment Zone C Wells																
IW-1C	Property, NE quadrant Decommissioned March, 2019	03/29/18	Peristaltic	0.134 U	0.117 U	0.183 U	**5.07**	–	**0.524**	0.152 U	0.222 U	0.257 U	**56.5**	0.130 U	**1.69**	0.316 U
IW-4C	Property, NE quadrant Decommissioned March, 2019	04/26/18	Peristaltic	0.134 U	0.117 U	0.183 U	**22,300**	–	**0.918**	**2.17**	0.222 U	0.257 U	**1,860**	0.130 U	**29.7**	**0.647 J**
IW-8C	Property, NE quadrant Decommissioned March, 2019	04/04/18	Peristaltic	0.134 U	0.117 U	0.183 U	**27,400**	–	**2.77**	**9.22**	0.222 U	0.257 U	**1,160**	0.130 U	**169**	**1.54**
IW-9C	Property, NE quadrant Decommissioned March, 2019	04/02/18	Peristaltic	0.134 U	0.117 U	0.183 U	**3.15**	–	**0.690**	**107**	0.222 U	0.257 U	**49.7**	0.130 U	**3,780**	0.316 U
IW-13C	Property, SW quadrant Decommissioned March, 2019	04/25/18	Peristaltic	0.134 U	0.117 U	0.183 U	**155**	–	0.412 U	**0.292 J**	0.222 U	0.257 U	**111**	0.130 U	**30.0**	0.316 U
IW-15C	Property, SW quadrant Decommissioned March, 2019	03/30/18	Bladder	1.34 U	1.17 U	1.83 U	**670**	–	4.12 U	**51.3**	2.22 U	2.57 U	**166**	1.30 U	**7,350**	3.16 U
IW-19C	Property, SW quadrant Decommissioned March, 2019	03/29/18	Peristaltic	0.134 U	0.117 U	0.183 U	**1.12**	–	0.412 U	**0.305 J**	0.222 U	0.257 U	**0.192 J**	0.130 U	**168**	0.316 U
IW-20C	Property, SW quadrant	03/30/18	Bladder	0.134 U	0.117 U	0.183 U	**721**	–	**1.54**	**9.44**	0.222 U	0.257 U	**1,020**	0.130 U	**111**	0.316 U
(dup)	Decommissioned March, 2019	03/30/18	Bladder	0.134 U	0.117 U	0.183 U	**678**	–	**1.53**	**10.2**	0.222 U	0.257 U	**1,020**	0.130 U	**111**	0.316 U
MW-167	Property, NE quadrant	11/04/19	Peristaltic	0.134 U	0.117 U	0.183 U	**0.326 J**	–	**0.567**	**0.599**	0.222 U	0.257 U	**0.297 J**	0.130 U	**17.3**	0.316 U
		01/28/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**0.158 J**	0.222 U	0.257 U	0.153 U	0.130 U	**11.5**	0.316 U
		05/01/20	Peristaltic	0.125 U	0.118 U	0.127 U	0.300 U	–	**0.693**	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	**0.641**	**0.629 J**
		07/09/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	**0.721**	**2.23**	0.0572 U	0.0612 U	0.0560 UJ	**0.0670**	0.0200 U	**0.948**	**0.926**
		11/05/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.462 U	**0.255**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	**0.897**	0.191 U
		02/04/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.0600 J**	0.335 U	**0.349**	0.0572 U	0.0612 U	0.0560 U	**0.0480**	0.0200 U	**2.22 J**	**0.345**
		05/05/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.544**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**1.06**	**0.565**
MW-171	Property, SW quadrant	11/05/19	Peristaltic	0.134 U	0.117 U	0.183 U	1.99 U	–	**0.497 J**	**1.47**	0.222 U	0.257 U	1.53 U	0.130 U	**13.3**	0.316 U
		01/23/20	Peristaltic	0.134 U	0.117 U	0.183 U	**0.407 J**	–	0.412 U	**0.281 J**	0.222 U	0.257 UJ	**0.687**	0.130 U	**20.7**	0.316 U
		04/02/20	Peristaltic	0.134 U	0.117 U	0.183 U	**0.255 J**	–	0.412 U	0.152 U	0.222 U	0.257 U	0.257 U	0.130 U	**26.2**	0.316 U
		07/09/20	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.103**	0.0900 U	**0.0850 J**	0.0572 U	0.0612 U	0.0560 UJ	**0.288**	0.0200 U	**8.43**	0.191 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
MW-171		11/03/20	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.0460 J**	0.0900 UJ	**0.175 J**	**0.289**	0.0612 U	0.0560 U	**0.277**	0.0200 U	**56.1**	**0.234 J**
(continued)		02/17/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.101 J+**	0.0900 U	**1.14**	**4.50**	0.0612 U	0.0560 U	**1.02**	0.0200 U	**396 J**	**0.290**
(dup)		02/17/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.0540 J**	0.0900 U	**1.16**	**4.72**	0.0612 U	0.0560 U	**0.901**	0.0200 U	**891 J**	**0.332**
		05/07/21	Peristaltic	5.05 U	5.45 U	3.10 U	1.40 U	4.50 U	2.50 U	**5.35 J**	3.06 U	2.80 UJ	0.800 U	1.00 U	**907**	9.55 U
MW-175	Property, SE quadrant	11/01/19	Peristaltic	0.134 U	0.117 U	0.183 U	**1.25**	–	**0.671**	**6.03**	0.222 U	0.257 U	**1.73**	0.130 U	**41.5**	0.316 U
		01/28/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	**0.479 J**	0.222 U	0.257 U	0.153 U	0.130 U	**10.3**	0.316 U
		05/01/20	Peristaltic	0.125 U	0.118 U	0.127 U	0.300 U	–	**0.950**	**0.188 J**	0.118 U	0.467 U	0.190 U	0.160 U	**5.75**	**0.971 J**
		07/09/20	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.196**	0.0900 U	**2.19**	0.0572 U	0.0612 U	0.0560 UJ	**0.0830**	0.0200 U	**1.65**	**1.17**
		11/05/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.105 U	**0.204**	**1.99**	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	**3.58**	0.191 U
		02/04/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.208 U	**0.221**	**5.29 J**	0.0612 U	0.0560 U	**0.0480**	0.0200 U	**2.55 J**	**0.248 J**
		05/05/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.307**	**3.60**	0.0612 U	0.0560 U	**0.0240 J**	0.0200 U	**1.12**	**0.398**
MW-179	Property, SW quadrant	11/06/19	Peristaltic	0.134 U	0.117 U	0.183 U	**50.5**	–	**0.443 J**	15.2 U	0.222 U	0.257 UJ	**46.2 J**	0.130 U	**533**	0.316 U
		01/27/20	Peristaltic	0.134 U	0.117 U	0.183 U	**38.8**	–	0.412 U	**7.07**	0.222 U	0.257 U	**33.3**	0.130 U	**156**	0.316 U
		04/02/20	Peristaltic	2.68 U	2.34 U	3.66 U	**62.3**	–	8.24 U	**5.99 J**	4.44 U	5.14 UJ	**45.0**	2.60 U	**152**	6.32 U
		07/10/20	Peristaltic	2.02 U	2.18 U	1.24 U	**27.3**	**3.40 J**	1.00 U	**7.40**	1.22 U	1.12 UJ	**19.6**	0.400 U	**105**	3.82 U
		11/03/20	Peristaltic	2.02 U	2.18 U	1.24 U	**36.1 J**	1.80 UJ	1.00 U	**45.5**	1.22 U	1.12 U	**19.6**	0.400 U	**1,670**	3.82 U
		02/18/21	Peristaltic	50.5 U	54.5 U	31.0 U	**489**	45.0 U	25.0 U	**279**	30.6 U	28.0 U	**110**	10.0 U	**31,300**	95.5 U
		05/06/21	Peristaltic	25.3 U	27.3 U	15.5 UJ	7.00 U	22.5 U	12.5 U	**29.5 J**	15.3 U	14.0 UJ	**21.3**	5.00 U	**5,860**	47.8 U
MW-183	Property, SW quadrant	11/08/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	**0.459 J**	**0.167 J**	0.222 U	0.257 UJ	**0.193 J**	0.130 U	**4.29**	0.316 U
		01/27/20	Peristaltic	0.134 U	0.117 U	0.183 U	**0.237 J**	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**15.5**	**0.369 J**
		04/02/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 UJ	0.130 U	**10.0**	0.316 U
		07/08/20	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.0750 J**	**0.170 J**	**2.39**	0.0572 U	0.0612 U	0.0560 UJ	**0.0630**	0.0200 U	**4.24**	**0.844**
		11/04/20	Peristaltic	0.101 U	0.109 U	0.0620 U	**22.5**	0.0900 UJ	**0.140 J**	**1.83**	0.0612 U	0.0560 UJ	**34.7**	0.0200 U	**208**	0.191 U
		02/19/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**2.28**	0.0900 U	**0.131 J**	**12.3**	0.0612 U	0.0560 U	**17.3**	0.0200 U	**2,260**	0.191 U
		05/06/21	Peristaltic	10.1 U	10.9 U	6.20 UJ	2.80 U	9.00 U	5.00 U	**12.5 J**	6.12 U	5.60 UJ	1.60 U	2.00 U	**2,340**	19.1 U
MW-187	Property, SE quadrant	11/01/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**2.80**	0.316 U
		01/29/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	**0.254 J**	0.316 U
		04/02/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		07/08/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**2.40**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	**1.18**
		11/04/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.298**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	**0.519**	**0.213 J**
		02/16/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.0780 J**	0.0900 U	**1.16**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**2.57 J+**	**0.310**
		05/07/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	0.124 U	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	**1.77**	0.191 U
Treatment Zone D Wells																
IW-1D	Property, NE quadrant Decommissioned March, 2019	04/03/18	Bladder	1.34 U	1.17 U	1.83 U	**64,100**	–	**6.74**	**16.0**	2.22 U	2.57 U	**2,830**	1.30 U	**118**	3.16 U
IW-3D	Property, NE quadrant Decommissioned March, 2019	04/03/18	Bladder	0.134 U	0.117 U	0.183 U	**4,240**	–	**1.28**	**16.4**	0.222 U	0.257 U	**4,600**	0.130 U	**37.1**	**0.409 J**
IW-4D	Property, SW quadrant Decommissioned March, 2019	03/29/18	Bladder	0.134 U	0.117 U	0.183 U	**2.86**	–	**0.604**	0.152 U	0.222 U	0.257 U	**0.653**	0.130 U	**2.56**	0.316 U
IW-6D	Property, SW quadrant Decommissioned March, 2019	04/03/18	Bladder	0.134 U	0.117 U	0.183 U	**16.3**	–	0.412 U	0.152 U	0.222 U	0.257 U	**0.826**	0.130 U	**1.27**	0.316 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
IW-8D	Property, SW quadrant Decommissioned March, 2019	04/04/18	Bladder	0.134 U	**0.188 J**	0.183 U	**6,010**	–	0.412 U	**39.1**	0.222 U	0.257 U	**4,310**	0.130 U	**631**	**0.384 J**
IW-9D	Property, SW quadrant Decommissioned March, 2019	04/04/18	Bladder	0.134 U	0.117 U	0.183 U	**3,610**	–	**1.12**	**10.0**	0.222 U	0.257 U	**1,510**	0.130 U	**31.6**	0.316 U
IW-11D	Property, NE quadrant Decommissioned March, 2019	05/01/18	Bladder	0.134 U	0.117 U	0.183 U	**18.9**	–	**0.643**	**2.27**	0.222 U	0.257 U	**282**	0.130 U	**34.1**	0.316 U
MW-168	Property, NE quadrant	11/04/19	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 UJ	0.316 U
		01/31/20	Flowing	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 UJ	0.153 U	0.130 U	0.118 U	0.316 U
		05/01/20	Peristaltic	0.125 U	0.118 U	0.127 U	0.300 U	–	**0.827**	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	**0.712 J**
		07/09/20	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.147**	0.0900 U	**2.61**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	**1.20**
		11/05/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.314**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	**0.407**	0.191 U
		02/04/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	**0.616**	**0.296**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**0.324**	**0.276**
		05/05/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	**1.11**	**0.667**	0.0572 U	0.0612 U	0.0560 U	**0.0320 J**	0.0200 U	**0.185**	**0.602**
MW-172	Property, SW quadrant	11/05/19	Flowing	0.134 U	0.117 U	0.183 U	**8,810**	–	**0.460 J**	**22.8**	0.222 U	0.257 U	**3,280**	0.130 U	**2.64**	0.316 U
		01/23/20	Flowing	0.134 U	0.117 U	0.183 U	**31,100**	–	**1.02**	**38.1**	0.222 U	0.257 U	**10,100**	0.130 U	59.0 U	**0.550 J**
		04/02/20	Peristaltic	67.0 U	58.5 U	91.5 U	**9,670**	–	206 U	76.0 U	111 U	129.0 UJ	**4,480**	65.0 U	59.0 U	158 U
		07/09/20	Peristaltic	0.101 U	0.109 U	0.0620 U	**6,570**	0.0900 U	**0.757**	**56.9**	0.0612 U	0.0560 UJ	**4,660**	0.0200 U	**5.57**	**0.402**
		11/03/20	Peristaltic	0.101 U	0.109 U	0.0620 U	**5,780**	0.0900 UJ	**0.750**	**44.1**	0.0612 U	0.0560 U	**4,130**	0.0200 U	**12.9**	**0.565**
		02/17/21	Flowing	0.101 U	0.109 U	0.0620 U	**5,370**	0.0900 U	**0.481**	**44.3**	0.0612 U	0.0560 U	**3,740**	0.0200 U	**179**	**0.216 J**
		05/07/21	Peristaltic	10.1 U	10.9 U	6.20 U	**1,100**	9.00 U	5.00 U	**20.4**	6.12 U	5.60 UJ	**1,410**	2.00 U	**21.0**	19.1 U
MW-176	Property, SE quadrant	11/01/19	Flowing	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		01/28/20	Flowing	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		01/28/20	Flowing	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		05/01/20	Peristaltic	0.125 U	0.118 U	0.127 U	0.300 U	–	**0.831**	0.149 U	0.118 U	0.467 U	0.190 U	0.160 U	0.234 U	**0.684 J**
		07/09/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.709**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	**0.294**
		11/05/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.157 U	**0.204**	**1.64**	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	**2.92**	0.191 U
		02/04/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.191 U	**0.146 J**	**3.64 J**	0.0612 U	0.0560 U	**0.0360 J**	0.0200 U	**1.51 J**	0.191 U
		05/05/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.350**	**2.73**	0.0612 U	0.0560 U	**0.0320 J**	0.0200 U	**0.858**	**0.385**
MW-180	Property, SW quadrant	11/06/19	Flowing	0.134 U	0.117 U	0.183 U	**2.10 J**	–	0.412 U	0.760 U	0.222 U	0.257 UJ	**1.87 J**	0.130 U	**76.6**	0.316 U
		01/24/20	Peristaltic	0.134 U	0.117 U	0.183 U	**2.80**	–	0.412 U	**1.20**	0.222 U	0.257 U	**3.18**	0.130 U	**146**	0.316 U
		04/01/20	Peristaltic	0.670 U	0.585 U	0.915 U	0.995 U	–	2.06 U	0.760 U	1.11 U	1.29 UJ	0.765 U	0.650 U	**22.9**	1.58 U
		07/10/20	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.614**	**0.187 J**	0.0500 U	**0.628**	0.0612 U	0.0560 UJ	**1.58**	0.0200 U	**17.8**	0.191 U
		11/03/20	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.335**	0.0900 UJ	**0.0840 J**	**1.31**	0.0612 U	0.0560 U	**1.08**	0.0200 U	**59.0**	0.191 U
		02/18/21	Flowing	0.101 U	0.109 U	0.0620 U	**46.8**	**0.235 J**	0.0500 U	**3.46**	0.0612 U	0.0560 U	**8.00**	0.0200 U	**308**	0.191 U
		05/06/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**1.29**	0.0900 U	**0.204**	**2.83**	0.0612 U	0.0560 UJ	**1.68**	0.0200 U	**237**	**0.195 J**
MW-184	Property, SW quadrant	11/08/19	Flowing	0.134 U	0.117 U	0.183 U	**1,590**	–	0.412 U	**2.77**	0.222 U	0.257 UJ	**733**	0.130 U	11.8 U	0.316 U
		01/27/20	Flowing	0.134 U	0.117 U	0.183 U	**886**	–	0.412 U	**1.65**	0.222 U	0.257 U	**325**	0.130 U	**0.287 J**	0.316 U
		04/01/20	Peristaltic	1.34 U	1.17 U	1.83 U	1.99 U	–	4.12 U	1.52 U	2.22 U	2.57 U	1.53 U	1.30 U	1.18 U	3.16 U
		07/08/20	Peristaltic	0.101 U	0.109 U	0.0620 U	**154**	0.0900 U	**1.04**	**0.646**	0.0612 U	0.0560 UJ	**88.4**	0.0200 U	**0.971**	**0.411**
		11/04/20	Peristaltic	1.01 U	1.09 U	0.620 U	**162**	0.900 UJ	0.500 U	**1.52 J**	0.612 U	0.560 UJ	**102**	0.200 U	**3.97**	1.91 U
		02/19/21	Flowing	1.01 U	1.09 U	0.620 U	**305**	0.900 U	0.500 U	**5.52**	0.612 U	0.560 U	**271**	0.200 U	**8.80**	1.91 U
		05/06/21	Peristaltic	0.505 U	0.545 U	0.310 UJ	**46.2**	0.450 U	0.250 U	**0.690 J**	0.306 U	0.280 UJ	**47.2**	0.100 U	**31.4**	0.955 U

Table G-5

Petroleum Hydrocarbons and VOCs in Groundwater – 2017 through 2021
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Property	Sample Date	Sampling Method	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trans-1,4-Dichloro-2-butene	Trichloroethene (TCE)	Trichlorofluoromethane (CFC-11)	Vinyl Chloride (VC)	Xylenes, Total
Preliminary Cleanup Level (PCUL)				**800**	**100**	**800**	**5.0**	**7,200**	**640**	**100**	**0.44**	**–**	**4.0**	**2,400**	**0.29**	**1,600**
Groundwater Screening Level for Vapor Intrusion (Shallow Zone Only)				**–**	**8,200**	**–**	**24**	**520,000**	**15,000**	**77**	**–**	**–**	**1.4**	**120**	**0.35**	**320**
MW-188	Property, SE quadrant	10/31/19	Flowing	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		01/29/20	Flowing	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 U	0.130 U	0.118 U	0.316 U
		04/02/20	Peristaltic	0.134 U	0.117 U	0.183 U	0.199 U	–	0.412 U	0.152 U	0.222 U	0.257 U	0.153 UJ	0.130 U	0.118 U	0.316 U
		07/08/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**1.86**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	**0.786**
		11/04/20	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	**0.149 J**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	**0.197**	**0.224 J**
		02/16/21	Peristaltic	0.101 U	0.109 U	0.0620 U	**0.0600 J**	0.0900 U	**0.352**	0.0572 U	0.0612 U	0.0560 U	0.0160 U	0.0200 U	**5.14 J+**	0.191 U
		05/07/21	Peristaltic	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 U	**0.130 J**	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	**2.14**	0.191 U
			Number of Analytes Measured	1,238	1,239	1,239	1,349	439	1,270	1,348	1,239	1,224	1,349	1,270	1,349	1,270
			Number of Analytes Detected	33	8	12	516	64	462	480	0	6	630	0	839	204
			Frequency of Detection	3%	1%	1%	38%	15%	36%	36%	0%	0%	47%	0%	62%	16%
			Maximum Detection	15.6	0.273 J	1.890	97,200	124	17.7	781	–	0 J	20,100	–	31,300	181
			Minimum Detection	0.101 U	0.109 U	0.0620 U	0.0280 U	0.0900 UJ	0.050 U	0.0572 U	0.0612 U	0.0560 UJ	0.0160 U	0.0200 U	0.0273 U	0.174 U
			Number of Detections Above SL	0	0	0	269	0	0	31	0	–	322	0	776	0
			Frequency of Detection Above SL	0%	0%	0%	20%	0%	0%	2%	0%	–	24%	0%	58%	0.0%

Notes:

Gasoline Range Organics Analyzed by NWTPH-Gx.
Diesel Range Organics and Heavy Oil analyzed by NWTPH-Dx.
VOCs analyzed by EPA Method 8260C or 8260D.
Results shown in micrograms per liter (µg/L).
PCULs and Screening Levels from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021.
All groundwater sampling performed by PES Environmental, Inc. unless otherwise indicated.
a = Results provided by Hart Crowser.
b = Results provided by Farallon Consulting.
c = Select sample results for MW-210 incorrectly identified with location SMW-3 on lab reports and sampling forms.
(split) = Split samples collected consecutively.
(dup) = Field duplicate sample.
– = Not analyzed, results not available, or information not applicable.
Detected results shown in **bold.**
Detections above the groundwater PCUL level are shown in **bold and highlighted in gray.**
Shallow Zone detections above the groundwater screening level for soil vapor are shown in **bold and highlighted in orange.**
Shallow Zone detections above the groundwater PCUL and screening level for soil vapor are shown in **bold highlighted in grayish-orange.**
U = Not detected at or above the laboratory method detection limit (MDL); detections above the MDL but below the laboratory reported detection limit (RDL) are qualified with a "J."
J = The identification of the analyte is acceptable; the reported value is an estimate.
J+ = The result is an estimated quantity, but the result may be biased high.
J- = The result is an estimated quantity, but the result may be biased low.
z = Elevated chlorinated VOCs detected within the GRO elution range. No discernible petroleum pattern present. Project level qualifier assigned per laboratory review.
GRO results above the screening level and qualified with "z" are not considered in the Maximum Detection and are not included in the Number of Detections Above SL.

Table G-6

Petroleum Hydrocarbons and CVOCs in Shallow Zone Groundwater
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																					
					GRO		DRO		ORO		DRO+ORO		Benzene		Toluene		Ethylbenzene		Total Xylenes		PCE		TCE		cDCE		tDCE		VC	
Preliminary Cleanup Level (PCUL)					**800**		**500**		**500**		**500**		**5.0**		**640**		**700**		**1,600**		**5.0**		**4.0**		**16**		**100**		**0.29**	
Groundwater Screening Level for Vapor Intrusion					–		–		–		–		**2.4**		**15,000**		**1,200**		**320**		**24**		**1.4**		–		**77**		**0.35**	
DMW-1S (38.8 to 28.8)	615 Dexter, SE quadrant	03/25/19	HC	Unknown	**350**		200	U	500	U	200	U	**1.5**		1.0	U	1.0	U	1.0	U	1.0	U	1.0	U	1.0	U	1.0	U	0.20	U
		03/25/19	HC	Unknown	**300**		200	U	500	U	200	U	**1.8**		1.0	U	1.0	U	1.0	U	1.0	U	1.0	U	1.0	U	1.0	U	0.20	U
		03/18/20	HC	Peristaltic	**1,800**		**580**	**J**	250	U	**580**	**J**	**2.9**		**1.6**		**12**		**1.8**		0.20	U	0.20	U	0.20	U	0.20	U	0.20	U
DMW-2S (30.7 to 20.7)	615 Dexter, SE quadrant	03/18/20	HC	Peristaltic	100	U	50	U	250	U	50	U	0.20	U	0.20	U	0.20	U	0.40	U	0.20	U	0.20	U	0.20	U	0.20	U	0.20	U
DMW-4S (38.5 to 28.5)	Alley S of SE quadrant of 615 Dexter	03/19/20	HC	Peristaltic	**670**		**790**	**J**	250	U	**790**	**J**	0.20	U	**0.26**		**5.5**		**3.0**		0.20	U	0.20	U	0.20	U	0.20	U	0.20	U
DMW-5IA (29.4 to 19.4)	Alley S of 615 Dexter	03/19/20	HC	Submersible	100	U	**760**	**J**	250	U	**760**	**J**	0.20	U	**0.64**		0.20	U	0.40	U	0.20	U	0.20	U	0.20	U	0.20	U	0.20	U
DMW-6 (32.1 to 22.1)	615 Dexter, NE quadrant	03/18/20	HC	Submersible	100	U	50	U	250	U	50	U	0.20	U	0.20	U	0.20	U	0.40	U	0.20	U	0.20	U	0.20	U	0.20	U	0.20	U
F5 (29.1 to -1.0)	Property, NW quadrant	07/19/13	SES	Peristaltic	–		–		–		–		–		–		–		–		**120,000**		**50**		**700**		**5.2**		**4.2**	
		10/24/13	SES	Peristaltic	–		–		–		–		–		–		–		–		**21,000**		**1,200**		**1,000**		**1,000**		200	U
		03/28/17	PES	Peristaltic	**234**	**zJ+**	–		–		–		**0.515**		0.727	U	0.158	U	0.316	U	0.199	U	**0.241**	**J**	**516**		**4.31**		**90.6**	
		06/22/17	PES	Peristaltic	31.6	U	–		–		–		**0.374**	**J**	**0.708**		0.158	U	0.316	U	0.199	U	**0.485**		**10.4**		**0.485**	**J**	**63.9**	
		Decommissioned March 2019																												
F9 (28.5 to -1.5)	Property, NE quadrant	07/19/13	SES	Peristaltic	–		–		–		–		–		–		–		–		**140,000**		**3,400**		**50**		**8.6**		**78**	
		06/16/15	SES	Peristaltic	–		–		–		–		–		–		–		–		**3.7**		**1.8**		**680**		**12**		**74**	
		10/19/15	SES	Peristaltic	–		–		–		–		–		–		–		–		**15.0**		**6.6**		**840**		**13**		**75**	
		02/01/16	SES	Peristaltic	–		–		–		–		–		–		–		–		**2.9**		1	U	**1.3**		1	U	**20**	
		03/27/17	PES	Peristaltic	31.6	U	–		–		–		**0.529**		**2.04**		0.158	U	0.316	U	0.199	U	0.153	U	**0.158**	**J**	**0.539**		0.118	U
		06/22/17	PES	Peristaltic	31.6	U	–		–		–		**0.471**	**J**	**1.70**		0.158	U	0.316	U	0.199	U	0.153	U	**6.10**		**0.485**		**3.57**	
		Decommissioned March 2019																												
F13 (28.4 to -1.6)	Property, NE quadrant	07/19/13	SES	Peristaltic	–		–		–		–		–		–		–		–		**2,900**		**280**		**370**		100	U	**49**	
		10/24/13	SES	Peristaltic	–		–		–		–		–		–		–		–		**7,300**		**3,100**		**490**		50	U	10	U
		11/18/13	SES	Peristaltic	–		–		–		–		–		–		–		–		**67,000**		**6,600**		**3,200**		**85**		**48**	
		12/12/13	SES	Peristaltic	–		–		–		–		–		–		–		–		**50**		**340**		**670**		10	U	**20**	
		03/07/14	SES	Peristaltic	–		–		–		–		–		–		–		–		**84**		**11**		**10**		1	U	**0.36**	
		06/16/15	SES	Peristaltic	–		–		–		–		–		–		–		–		**8.4**		1	U	**1.8**		1	U	**0.31**	
		10/19/15	SES	Peristaltic	–		–		–		–		–		–		–		–		1	U	**2.0**		**210**		**2.3**		**4.1**	
		02/02/16	SES	Peristaltic	–		–		–		–		–		–		–		–		**3.4**		1	U	1	U	1	U	**0.97**	
		03/27/17	PES	Peristaltic	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.218**	**J**	0.152	U	**0.936**	
		06/22/17	PES	Peristaltic	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.194**	**J**	0.152	U	**1.32**	
		04/05/18	PES	Peristaltic	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**20.3**		**0.346**	**J**	**0.375**	**J**	0.152	U	**0.843**	
		Decommissioned March 2019																												
FMW-143 (10.0 to 5.0)	9th Ave N ROW, E side	07/30/19	Farallon	Unknown	–		–		–		–		–		–		–		–		0.20	U	0.20	U	0.20	U	0.20	U	0.20	U
		10/31/19	PES	Peristaltic	–		–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		01/22/20	PES	Peristaltic	–		–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		05/14/20	PES	Bladder	–		–		–		–		0.0941	U	**0.319**	**J**	0.137	U	**0.201**	**J**	0.300	U	0.190	U	0.126	U	0.149	U	0.234	U
		07/22/20	PES	Bladder	–		–		–		–		0.0160	U	**0.146**	**J**	**0.0490**	**J**	**0.331**		0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U

Table G-6

Petroleum Hydrocarbons and CVOCs in Shallow Zone Groundwater
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																	
					GRO	DRO	ORO	DRO+ORO	Benzene	Toluene	Ethylbenzene	Total Xylenes	PCE	TCE	cDCE	tDCE	VC
Preliminary Cleanup Level (PCUL)					**800**	**500**	**500**	**500**	**5.0**	**640**	**700**	**1,600**	**5.0**	**4.0**	**16**	**100**	**0.29**
G12 (29.4 to -0.6)	Property, NE quadrant	07/19/13	SES	Peristaltic	–	–	–	–	–	–	–	–	**64,000**	**3,100**	**9,200**	**88**	**130**
		10/24/13	SES	Peristaltic	–	–	–	–	–	–	–	–	**1,700**	**150**	100 U	100 U	20 U
		11/18/13	SES	Peristaltic	–	–	–	–	–	–	–	–	**760**	**84**	**42**	10 U	2 U
		03/27/17	PES	Peristaltic	–	–	–	–	**0.243 J**	0.412 U	0.158 U	0.316 U	0.199 U	**0.233 J**	**95.9**	**1.97**	**28.4**
		06/30/17	PES	Peristaltic	–	–	–	–	**0.282 J**	0.412 U	0.158 U	0.316 U	0.199 U	**0.323 J**	**115**	**2.94**	**31.5**
		Decommissioned March 2019															
G-MW2 (31 to 21)	Property	07/24/01	GeoE	Peristaltic	–	–	–	–	**0.375**	**48.3 E**	**2.01**	**12.88**	**176,000**	**237 g**	**129 g**	**1.02**	**0.457**
		01/29/09	DOF	Peristaltic	**39,600 qp**	–	–	–	20.0 U	20.0 U	20.0 U	**48.9**	**59,000 f**	**210**	**373**	**1.33**	0.200 U
		06/02/11	SES	Peristaltic	**59,000 xy**	**200**	250 U	**200**	350 U	1,000 U	1,000 U	3,000 U	**150,000**	1,000 U	1,000 U	1,000 U	200 U
		09/06/12	SES	Peristaltic	–	–	–	–	0.35 U	**12**	**1.1**	**4.7**	**150,000**	**320**	**260**	**1.4**	0.2 U
		Decommissioned															
HMW-1S (16.0 to 6.0)	Seattle DOT Mercer Parcels, NE quadrant	03/25/19	HC	Peristaltic	100 U	–	–	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	0.2 U
		03/11/20	HC	Peristaltic	100 U	**200 J**	250 U	**200 J**	0.20 U	0.20 U	0.20 U	0.40 U	0.20 U	0.20 U	0.20 U	0.20 U	0.20 U
HMW-2S (27.6 to 17.6)	Seattle DOT Mercer Parcels, NE quadrant	03/25/19	HC	Peristaltic	100 U	–	–	–	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	0.2 U
		03/12/20	HC	Peristaltic	100 U	**56 J**	260 U	**56 J**	0.20 U	0.20 U	0.20 U	0.40 U	0.20 U	0.20 U	0.20 U	0.20 U	0.20 U
HMW-9S (30.4 to 20.4)	Seattle DOT Mercer Parcels, SW quadrant	03/17/20	HC	Submersible	100 U	**61 J**	250 U	**61 J**	0.20 U	0.20 U	0.20 U	0.40 U	0.20 U	0.20 U	0.20 U	0.20 U	0.20 U
HMW-10S (23.5 to 13.5)	Seattle DOT Mercer Parcels, SE quadrant	03/16/20	HC	Submersible	100 U	**66 J**	250 U	**66 J**	0.20 U	0.20 U	0.20 U	0.40 U	0.20 U	0.20 U	0.20 U	0.20 U	0.20 U
HMW-11S (16.5 to 6.5)	Seattle DOT Mercer Parcels, SE quadrant	03/11/20	HC	Submersible	100 U	**620 J**	250 U	**620 J**	0.20 U	0.20 U	0.20 U	0.40 U	0.20 U	0.20 U	0.20 U	0.20 U	0.20 U
HMW-17S (22.2 to 12.2)	Seattle DOT Mercer Parcels, NW quadrant	09/17/20	HC	Unknown	100 U	50 U	–	50 U	0.20 U	0.20 U	0.20 U	0.40 U	0.20 U	0.20 U	0.20 U	0.20 U	0.20 U
HMW-18S (22.6 to 12.6)	Seattle DOT Mercer Parcels, NW quadrant	09/17/20	HC	Unknown	100 U	50 U	–	50 U	0.20 U	0.20 U	0.20 U	0.40 U	0.20 U	0.20 U	0.20 U	0.20 U	0.20 U
HMW-19S (23.2 to 13.2)	Seattle DOT Mercer Parcels, NW quadrant	09/17/20	HC	Unknown	**170**	50 U	–	50 U	0.20 U	0.20 U	**0.20**	**0.60**	0.20 U	0.20 U	0.20 U	0.20 U	0.20 U
HMW-20S (28.8 to 18.8)	Seattle DOT Mercer Parcels, NW quadrant	09/18/20	HC	Unknown	100 U	50 U	–	50 U	0.20 U	0.20 U	0.20 U	0.40 U	**4.7**	**0.38**	**1.4**	0.20 U	**0.99**
HMW-21S (8.2 to -1.8)	Seattle DOT Mercer Parcels, SE quadrant	11/03/20	HC	Unknown	–	50 U	–	50 U	–	–	–	–	–	–	–	–	–
HMW-22S (11.8 to 1.8)	Seattle DOT Mercer Parcels, SE quadrant	11/03/20	HC	Unknown	–	62 U	–	62 U	–	–	–	–	–	–	–	–	–
J5 (29.8 to -0.2)	Property, SW quadrant	07/19/13	SES	Peristaltic	–	–	–	–	–	–	–	–	**46,000**	**660**	100 U	100 U	20 U
		10/24/13	SES	Peristaltic	–	–	–	–	–	–	–	–	**48,000**	**13,000**	**1,400**	100 U	20 U
		06/16/15	SES	Peristaltic	–	–	–	–	–	–	–	–	**50**	**340**	**250**	**51**	**1.0**
		10/19/15	SES	Peristaltic	–	–	–	–	–	–	–	–	**1,400**	**470**	**890**	**51**	**1.3**
		02/02/16	SES	Peristaltic	–	–	–	–	–	–	–	–	**1,500**	**5**	**280**	**14**	**0.31**
		03/21/17	PES	Peristaltic	–	–	–	–	**0.580**	0.412 U	0.158 U	0.316 U	**285**	**78.5**	**253**	**1.73**	**29.6**
		06/26/17	PES	Peristaltic	–	–	–	–	**0.252 J**	**0.506**	0.158 U	0.316 U	**36.1**	**37.1**	**366**	**1.94**	**77.7**
		04/05/18	PES	Peristaltic	**207**	–	–	–	**0.638**	0.412 U	0.158 U	0.316 U	**267**	**70.5**	**222**	**1.00**	**17.6**
		Decommissioned March 2019															

Table G-6

Petroleum Hydrocarbons and CVOCs in Shallow Zone Groundwater
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																	
					GRO		DRO	ORO	DRO+ORO	Benzene		Toluene		Ethylbenzene		Total Xylenes		PCE		TCE		cDCE		tDCE		VC	
Preliminary Cleanup Level (PCUL)					**800**		**500**	**500**	**500**	**5.0**		**640**		**700**		**1,600**		**5.0**		**4.0**		**16**		**100**		**0.29**	
J15	Property, SE quadrant	07/19/13	SES	Peristaltic	–		–	–	–	–		–		–		–		**4,100**		**220**		**580**		**6.8**		**20**	
(28.7 to -1.3)		10/24/13	SES	Peristaltic	–		–	–	–	–		–		–		–		**10,000**		**50**		**680**		100	U	20	U
		03/07/14	SES	Peristaltic	–		–	–	–	–		–		–		–		**2,200**		**170**		**120**		50	U	10	U
		06/16/15	SES	Peristaltic	–		–	–	–	–		–		–		–		**9.0**		**12**		**310**		**8.8**		**3.1**	
		10/19/15	SES	Peristaltic	–		–	–	–	–		–		–		–		**3.6**		1	U	**5**		**3.0**		**1.7**	
		02/02/16	SES	Peristaltic	–		–	–	–	–		–		–		–		**2.4**		1	U	**35**		1	U	**0.39**	
		03/27/17	PES	Peristaltic	–		–	–	–	**0.188**	**J**	**0.495**	**J**	0.158	U	0.316	U	0.199	U	0.153	U	**43.3**		**1.18**		**6.99**	
		06/26/17	PES	Peristaltic	–		–	–	–	**0.173**	**J**	**0.459**	**J**	0.158	U	0.316	U	0.199	U	0.153	U	**39.8**		**1.06**		**6.30**	
(duplicate)		06/26/17	PES	Peristaltic	–		–	–	–	**0.173**	**J**	**0.551**		0.158	U	0.316	U	0.199	U	0.153	U	**39.3**		**1.03**		**6.73**	
		04/05/18	PES	Peristaltic	**41.2**	**J**	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**12.8**		**0.358**	**J**	**26.3**		**0.709**		**6.07**	
		Decommissioned March 2019																									
K8	Property, SW quadrant	07/19/13	SES	Peristaltic	–		–	–	–	–		–		–		–		**8,700**		**330**		**1,400**		**5.6**		**6.3**	
(29.9 to -0.1)		06/17/15	SES	Peristaltic	–		–	–	–	–		–		–		–		**63**		**16**		**500**		**67**		2	U
		10/19/15	SES	Peristaltic	–		–	–	–	–		–		–		–		**360**		**82**		**43**		**3.2**		**0.44**	
		02/01/16	SES	Peristaltic	–		–	–	–	–		–		–		–		**250**		**44**		**82**		**1.8**		**0.31**	
		03/21/17	PES	Peristaltic	–		–	–	–	**0.239**	**J**	0.412	U	0.158	U	0.316	U	**82.5**		**22.0**		**123**		**0.680**		**0.461**	**J**
		06/26/17	PES	Peristaltic	–		–	–	–	**0.246**	**J**	0.412	U	0.158	U	0.316	U	**67.9**		**28.7**		**140**		**0.750**		**0.456**	**J**
		04/05/18	PES	Peristaltic	**156**	**zJ+**	–	–	–	**0.251**	**J**	0.412	U	0.158	U	0.316	U	**229**		**26.3**		**104**		**0.750**		**1.45**	
		Decommissioned March 2019																									
M15	Property, SE quadrant	07/19/13	SES	Peristaltic	–		–	–	–	–		–		–		–		**3,200**		**5**		**180**		**1.7**		**0.22**	
(29.5 to -0.5)		10/24/13	SES	Peristaltic	–		–	–	–	–		–		–		–		**56,000**		**50**		**770**		50	U	10	U
		03/07/14	SES	Peristaltic	–		–	–	–	–		–		–		–		**2,100**		**190**		**290**		**2.9**		**2.60**	
		06/16/15	SES	Peristaltic	–		–	–	–	–		–		–		–		**58**		**44**		**76**		**2.7**		**1.1**	
		10/19/15	SES	Peristaltic	–		–	–	–	–		–		–		–		**48**		**29**		**5**		**2.3**		**0.74**	
		02/02/16	SES	Peristaltic	–		–	–	–	–		–		–		–		**11**		**10**		**84**		**1.8**		**0.39**	
		03/27/17	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**0.733**		**32.7**		**0.561**		**13.2**	
(duplicate)		03/27/17	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**0.670**		**31.7**		**0.513**		**12.0**	
		06/26/17	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**0.233**	**J**	**1.80**		**25.8**		**0.523**		**15.0**	
		04/05/18	PES	Peristaltic	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**0.563**		**8.89**		**0.300**	**J**	**11.1**	
		Decommissioned March 2019																									
MW-1	800 Aloha St Parcel	03/22/93	EPJ	Bailer	**5,100**		500	U 1000	U 500	U **10,000**		**270**		**480**		**427**		–		–		–		–		–	
(--)		06/17/93	Retec	Unknown	–		–	–	–	**20,000**		**14,000**		**840**		**6,700**		–		–		–		–		–	
		Decommissioned October 1993																									
MW-2	8th Ave North ROW	03/22/93	EPJ	Bailer	**650**		500	U 1000	U 500	U **100**		**42**		**24**		**67**		–		–		–		–		–	
(--)		06/17/93	Retec	Unknown	–		–	–	–	**28**		**7.2**		1	U	2	U	**170**		**1,400**		**9,300**		**25**		**50**	
		Decommissioned October 1993																									
MW-3	800 Aloha St Parcel	03/22/93	EPJ	Bailer	**27,000**		500	U 1000	U 500	U **1,500**		**3,300**		**690**		**3,500**		–		–		–		–		–	
(--)		06/17/93	Retec	Unknown	–		–	–	–	**4,800**		**21,000**		**1,900**		**12,300**		–		–		–		–		–	
		Decommissioned October 1993																									
MW-4	Seattle Roy Aloha Shops, N end	03/22/93	EPJ	Bailer	**940**		500	U 1000	U 500	U **82**		**390**		**39**		**108**		–		–		–		–		–	
(--)		06/17/93	Retec	Unknown	–		–	–	–	1	U	1	U	1	U	2	U	–		–		–		–		–	
		Decommissioned October 1993																									
MW-5	8th Ave North ROW	03/22/93	EPJ	Bailer	**670**		500	U 1000	U 500	U **49**		**140**		**9.8**		**80**		–		–		–		–		–	
(--)		06/17/93	Retec	Unknown	–		–	–	–	1	U	1	U	1	U	2	U	–		–		–		–		–	
		Decommissioned October 1993																									

Table G-6

Petroleum Hydrocarbons and CVOCs in Shallow Zone Groundwater
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)												
					GRO	DRO	ORO	DRO+ORO	Benzene	Toluene	Ethylbenzene	Total Xylenes	PCE	TCE	cDCE	tDCE	VC
Preliminary Cleanup Level (PCUL)					**800**	**500**	**500**	**500**	**5.0**	**640**	**700**	**1,600**	**5.0**	**4.0**	**16**	**100**	**0.29**
MW-6	Seattle Roy Aloha Shops, N end	10/12/93	Retec	Unknown	**150,000**	–	–	–	**9,100**	**6,800**	**2,600**	**7,300**	–	–	–	–	–
(31.2 to 16.2)		10/26/93	Retec	Unknown	**100,000**	–	–	–	**17,000**	**14,000**	**1,400**	**500**	–	–	–	–	–
		01/25/94	Retec	Unknown	**66,000**	–	–	–	**8,800**	**4,600**	**1,500**	**8,100**	–	–	–	–	–
		04/25/94	Retec	Unknown	**120,000**	–	–	–	**15,000**	**7,200**	**2,600**	**13,300**	–	–	–	–	–
		09/15/94	Retec	Unknown	**56,000**	–	–	–	**15,000**	**2,000**	**1,500**	**7,100**	–	–	–	–	–
		06/20/02	Urban	Unknown	**8,500**	–	–	–	**1,900**	**14**	**250**	**53**	–	–	–	–	–
MW-7	Seattle Roy Aloha Shops, N end	10/12/93	Retec	Unknown	**75,000**	–	–	–	**20,000**	**22,000**	**3,000**	**15,000**	–	–	–	–	–
(26.1 to 16.1)		10/26/93	Retec	Unknown	**74,000**	–	–	–	**8,300**	**7,400**	**50**	**8,300**	–	–	–	–	–
		01/25/94	Retec	Unknown	**53,000**	–	–	–	**1,600**	**2,700**	**1,400**	**5,100**	–	–	–	–	–
		04/25/94	Retec	Unknown	**140,000**	–	–	–	**3,900**	**7,400**	**3,100**	**14,100**	–	–	–	–	–
		09/15/94	Retec	Unknown	**66,000**	–	–	–	**3,400**	**2,700**	**1,900**	**7,700**	–	–	–	–	–
(duplicate)		09/15/94	Retec	Unknown	**77,000**	–	–	–	**3,600**	**3,000**	**2,100**	**8,700**	–	–	–	–	–
		06/20/02	Urban	Unknown	**8,400**	–	–	–	**650**	**37**	**470**	**150**	–	–	–	–	–
MW-8	Seattle Roy Aloha Shops, N end	10/26/93	Retec	Unknown	**280**	–	–	–	**19**	**1**	1 U	**48**	–	–	–	–	–
(28.7 to 14.2)		01/25/94	Retec	Unknown	**230 J**	–	–	–	**13**	**0.7 J**	1 U	**4.5**	–	–	–	–	–
(duplicate)		01/25/94	Retec	Unknown	**210 J**	–	–	–	**12**	**0.6 J**	1 U	**3.7**	–	–	–	–	–
		04/25/94	Retec	Unknown	250 U	–	–	–	**2.2**	1 U	1 U	**1.7**	–	–	–	–	–
		09/15/94	Retec	Unknown	**210 J**	–	–	–	1 U	**0.5 J**	1 U	**1.6 J**	–	–	–	–	–
(duplicate)		09/15/94	Retec	Unknown	**250**	–	–	–	1 U	**0.5 J**	1 U	**1.7 J**	–	–	–	–	–
		06/21/02	Urban	Unknown	50 U	–	–	–	1 U	1 U	1 U	1 U	–	–	–	–	–
		03/20/17	PES	Peristaltic	–	–	–	–	**0.145 J**	0.412 U	**0.175 J**	0.316 U	0.199 U	0.153 U	0.0933 U	0.152 U	0.118 U
		04/13/18	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	**0.570**	0.153 U	0.0933 U	0.152 U	0.118 U
		07/18/19	PES	Peristaltic	31.6 U	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	0.0933 U	0.152 U	0.118 U
		10/10/19	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	**0.167 J**	0.0933 U	0.152 U	0.118 U
		01/16/20	PES	Peristaltic	–	–	–	–	**0.156 J**	**1.96**	0.158 U	**0.569 J**	0.199 U	0.153 U	0.0933 U	0.152 U	0.118 U
		05/06/20	PES	Peristaltic	–	–	–	–	0.0941 U	0.278 U	0.137 U	0.174 U	0.300 U	0.190 U	0.126 U	0.149 U	0.234 U
		07/14/20	PES	Peristaltic	–	–	–	–	0.0160 U	**0.161 J**	0.0212 U	0.191 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U
MW-9	8th Ave N ROW, E side	10/26/93	Retec	Unknown	**210 J**	–	–	–	**9.5**	**1.3**	1 U	2 U	–	–	–	–	–
(34.1 to 19.1)		01/25/94	Retec	Unknown	250 U	–	–	–	**5.7**	**1.1**	1 U	2 U	–	–	–	–	–
		04/25/94	Retec	Unknown	250 U	–	–	–	0.001 U	1 U	1 U	2 U	–	–	–	–	–
		09/15/94	Retec	Unknown	250 U	–	–	–	**3.5**	**0.6 J**	1 U	2 U	–	–	–	–	–
		06/20/02	Urban	Unknown	50 U	–	–	–	1 U	1 U	1 U	2 U	1 U	1 U	1 U	1 U	1 U
		06/02/11	SES	Peristaltic	100 U	**150 x**	250 U	**150 x**	1 U	1 U	1 U	3 U	–	–	–	–	–
		09/04/12	SES	Peristaltic	–	–	–	–	0.35 U	1 U	1 U	3 U	1 U	1 U	1 U	1 U	**0.61**
		12/16/13	SES	Peristaltic	100 U	50 U	250 U	50 U	0.35 U	1 U	1 U	3 U	1 U	1 U	1 U	1 U	0.2 U

Table G-6

Petroleum Hydrocarbons and CVOCs in Shallow Zone Groundwater
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																					
					GRO		DRO		ORO		DRO+ORO		Benzene		Toluene		Ethylbenzene		Total Xylenes		PCE		TCE		cDCE		tDCE		VC	
Preliminary Cleanup Level (PCUL)					**800**		**500**		**500**		**500**		**5.0**		**640**		**700**		**1,600**		**5.0**		**4.0**		**16**		**100**		**0.29**	
MW-9		03/20/17	PES	Peristaltic	**52.8**	**J**	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.140**	**J**	0.152	U	**0.324**	**J**
(continued)		06/20/17	PES	Peristaltic	31.6	U	–		–		–		0.0896	U	**0.562**		0.158	U	0.316	U	0.199	U	0.153	U	**0.214**	**J**	0.152	U	0.118	U
(duplicate)		06/20/17	PES	Peristaltic	31.6	U	–		–		–		0.0896	U	**0.548**		0.158	U	0.316	U	0.199	U	0.153	U	**0.211**	**J**	0.152	U	0.118	U
		04/05/18	PES	Peristaltic	**32.9**	**J**	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**1.58**		0.153	U	**0.246**	**J**	0.152	U	**0.210**	**J**
		01/21/19	PES	Peristaltic	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		04/26/19	PES	Peristaltic	**121**	**zJ+**	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**157**		**45.2**		**75.1**		**0.261**	**J**	0.861	UJ
		07/16/19	PES	Peristaltic	57.4	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	**0.619**	
		10/17/19	PES	Peristaltic	62.0	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.786**		0.152	U	**0.416**	**J**
		11/24/20	PES	Peristaltic	**41.0**	**J**	–		–		–		**0.0250**	**J**	**0.0800**	**J**	0.0212	U	0.191	U	0.0280	U	0.0160	U	**0.221**		0.0572	U	**0.288**	
		02/05/21	PES	Peristaltic	73.2	U	–		–		–		**0.0420**		**0.241**		**0.0510**	**J**	**0.321**		**0.117**		0.0160	U	**0.121**		0.0572	U	**0.138**	**J**
		05/12/21	PES	Peristaltic	31.6	U	–		–		–		**0.0290**	**J**	0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	**0.117**		0.0572	U	**0.223**	**J**
(duplicate)		05/12/21	PES	Peristaltic	31.6	U	–		–		–		**0.0280**	**J**	0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	**0.119**		0.0572	U	0.0273	UJ
MW-10	Seattle Roy Aloha Shops, N end	10/26/93	Retec	Unknown	250	U	–		–		–		1	U	**1.3**		1	U	2	U	–		–		–		–		–	
(31.0 to 16.0)		01/25/94	Retec	Unknown	**190**	**J**	–		–		–		1	U	**3.2**		1	U	2	U	–		–		–		–		–	
		04/25/94	Retec	Unknown	250	U	–		–		–		1	U	**2.5**		1	U	2	U	–		–		–		–		–	
		09/15/94	Retec	Unknown	250	U	–		–		–		1	U	**0.9**	**J**	1	U	2	U	–		–		–		–		–	
		06/20/02	Urban	Unknown	50	U	–		–		–		1	U	1	U	1	U	1	U	1	U	1	U	1	U	1	U	1	U
MW121	8th Ave N ROW, E side	12/26/13	SES	Peristaltic	100	U	**200**	**x**	250	U	**200**	**x**	0.35	U	1	U	1	U	3	U	1	U	1	U	1	U	1	U	**1.3**	
(26.7 to 16.7)		03/28/17	PES	Peristaltic	–		–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.768**		0.152	U	**5.82**	
		06/20/17	PES	Peristaltic	–		–		–		–		**0.186**	**J**	**0.774**		0.158	U	0.316	U	0.199	U	0.153	U	**1.13**		0.152	U	**7.68**	
		04/05/18	PES	Peristaltic	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**2.93**		0.153	U	**0.959**		0.152	U	**6.45**	
		01/31/19	PES	Peristaltic	38.0	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**5.53**		0.152	U	**19.8**	
		04/29/19	PES	Peristaltic	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**5.39**		0.152	U	**15.2**	**J**
		07/19/19	PES	Peristaltic	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**1.01**		0.152	U	**5.04**	
		11/30/20	PES	Bladder	31.6	U	–		–		–		**0.0290**	**J**	**0.0670**	**J**	**0.0410**	**J**	**0.272**		0.0280	U	0.0160	U	**0.193**		0.0572	U	**1.73**	
		02/05/21	PES	Peristaltic	41.1	U	–		–		–		**0.0850**		**0.240**		**0.0410**	**J**	**0.247**	**J**	**0.0460**	**J**	**0.0530**		**3.85**		0.0572	U	**5.64**	**J**
		05/12/21	PES	Peristaltic	31.6	U	–		–		–		**0.0260**	**J**	**0.484**		**0.0560**	**J**	**0.346**		0.0280	U	0.0160	U	**0.418**		0.0572	U	**1.79**	
(duplicate)		05/12/21	PES	Peristaltic	31.6	U	–		–		–		**0.0290**	**J**	**0.448**		**0.0580**	**J**	**0.351**		**0.0490**	**J**	0.0160	U	**0.380**		0.0572	U	**1.67**	
MW125	Valley St ROW, N side	12/26/13	SES	Peristaltic	100	U	**300**	**x**	250	U	**300**	**x**	**1.4**		1	U	1	U	3	U	1	U	1	U	1	U	1	U	0.2	U
(28.6 to 13.6)		03/22/17	PES	Peristaltic	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**0.285**	**J**	0.153	U	**0.341**	**J**	0.152	U	0.118	U
		06/28/17	PES	Bladder	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		04/06/18	PES	Peristaltic	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**0.580**		0.153	U	**0.278**	**J**	0.152	U	0.118	U
		01/21/19	PES	Peristaltic	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		04/23/19	PES	Peristaltic	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	UJ
		07/18/19	PES	Peristaltic	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		10/18/19	PES	Bladder	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.496**	**J**	0.152	U	0.118	U
		01/29/20	PES	Bladder	51.1	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.369**	**J**	0.152	U	0.118	U
		11/17/20	PES	Bladder	–		–		–		–		0.0160	U	**0.0910**	**J**	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
		02/02/21	PES	Peristaltic	38.5	U	–		–		–		0.0160	U	**0.158**	**J**	**0.101**		**0.716**		0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
		05/11/21	PES	Peristaltic	46.2	U	–		–		–		0.0160	U	0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	UJ
(duplicate)		05/11/21	PES	Peristaltic	33.2	U	–		–		–		0.0160	U	0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	UJ
MW-154	Roy St ROW, S side	04/30/18	PES	Bladder	**32.1**	**J**	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**4.46**		**0.230**	**J**	**1.77**		0.152	U	**7.48**	
(27.8 to 17.9)		01/21/19	PES	Peristaltic	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**1.70**		**0.330**	**J**	**2.03**		0.152	U	**3.52**	
		04/24/19	PES	Bladder	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**1.02**		**0.214**	**J**	**1.76**		0.152	U	**0.797**	

Table G-6

Petroleum Hydrocarbons and CVOCs in Shallow Zone Groundwater
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																	
					GRO		DRO	ORO	DRO+ORO	Benzene		Toluene		Ethylbenzene		Total Xylenes		PCE		TCE		cDCE		tDCE		VC	
Preliminary Cleanup Level (PCUL)					**800**		**500**	**500**	**500**	**5.0**		**640**		**700**		**1,600**		**5.0**		**4.0**		**16**		**100**		**0.29**	
MW-154 (continued)		07/15/19	PES	Bladder	68.0	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**69.5**		**5.75**		**2.55**		0.152	U	**0.211**	**J**
		10/14/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**4.99**		**0.445**	**J**	**1.40**		0.152	U	0.118	U
		01/21/20	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**11.6**		**0.999**		**2.26**		0.152	U	0.118	U
		04/30/20	PES	Bladder	**47.5**	**J**	–	–	–	0.0941	U	0.278	U	0.137	U	0.174	U	**12.1**		**1.06**		**2.58**		0.149	U	0.234	U
		07/10/20	PES	Bladder	–		–	–	–	0.0160	U	**0.771**		0.0212	U	0.191	U	**10.9**		**0.786**		**1.83**		0.0572	U	0.0273	U
		11/09/20	PES	Bladder	–		–	–	–	**0.0230**	**J**	**0.317**		0.0212	U	0.191	U	**73.9**		**6.84**		**1.77**		0.0572	U	0.0273	U
		02/08/21	PES	Bladder	–		–	–	–	**0.0220**	**J**	**0.794**		**0.106**		**0.593**		**4.72**	**J**	**0.501**		**0.203**		0.0572	U	0.0273	U
		05/10/21	PES	Bladder	–		–	–	–	0.0160	U	0.0500	U	0.0212	U	0.191	U	**3.41**		**0.453**		**0.134**		0.0572	U	0.0273	UJ
MW-155 (24.4 to 14.4)	Roy St ROW, S side	04/27/18	PES	Peristaltic	60.9	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**3.48**		**0.334**	**J**	**0.466**	**J**	0.152	U	**0.447**	**J**
		01/21/19	PES	Peristaltic	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**3.72**		**0.581**		**0.274**	**J**	0.152	U	0.118	U
		04/23/19	PES	Peristaltic	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**14.6**		**4.75**		**71.9**		0.152	U	**6.54**	**J**
		07/23/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**92.7**		**19.9**		**12.1**		0.152	U	**0.350**	**J**
		10/16/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**121**		**27.6**		**36.2**		**0.160**	**J**	0.118	U
		01/20/20	PES	Bladder	**44.9**	**J**	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**98.3**		**21.8**		**12.7**		0.152	U	0.118	U
		05/05/20	PES	Bladder	31.6	U	–	–	–	0.0941	U	0.278	U	0.137	U	0.174	U	**140**		**27.3**		**16.4**		**0.158**	**J**	0.234	U
		08/03/20	PES	Bladder	–		–	–	–	**0.0310**	**J**	**0.355**		0.0212	U	0.191	U	**63.4**		**28.0**		**9.74**		**0.216**		0.0273	UJ
		11/11/20	PES	Bladder	–		–	–	–	0.0160	U	0.0500	U	0.0212	UJ	0.191	U	**119**		**26.0**		**11.7**		**0.108**	**J**	**0.190**	**J+**
MW-159 (22.9 to 12.9)	8th Ave N ROW, E side	04/26/18	PES	Peristaltic	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**0.964**		**0.358**	**J**	**1.09**		0.152	U	0.118	U
		01/21/19	PES	Peristaltic	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.651**		0.152	U	**0.666**	
		04/26/19	PES	Bladder	31.6	U	–	–	–	**0.179**	**J**	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**1.23**		0.152	U	**1.03**	**J**
(duplicate)		04/26/19	PES	Bladder	31.6	U	–	–	–	**0.193**	**J**	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**1.12**		0.152	U	**1.04**	**J**
		07/22/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.918**		0.152	U	**0.691**	
		01/29/20	PES	Bladder	33.9	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.811**		0.152	U	0.118	U
		11/11/20	PES	Bladder	–		–	–	–	0.0160	U	**0.457**	**J-**	0.0212	U	0.191	U	0.0280	U	0.0160	U	**0.561**		0.0572	U	**0.214**	**J+**
		02/08/21	PES	Peristaltic	–		–	–	–	**0.0340**	**J**	**0.182**	**J**	**0.0860**	**J**	**0.486**		**0.126**	**J**	**0.0380**	**J**	**0.525**		0.0572	U	**0.504**	**J**
		05/11/21	PES	Peristaltic	–		–	–	–	**0.0200**	**J**	0.0500	U	0.0212	U	0.191	U	0.0280	U	**0.0360**	**J**	**0.518**		0.0572	U	**0.350**	**J-**
MW-210[a] (17.1 to 7.1)	Valley St ROW, N side	03/30/17	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	UJ
		06/21/17	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		04/09/18	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		10/11/19	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		01/17/20	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	UJ
		04/09/20	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		07/07/20	PES	Peristaltic	–		–	–	–	0.0160	U	0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
MW-214 (duplicate) (20.8 to 10.8)	Valley St ROW, S side	03/30/17	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		03/30/17	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		04/09/18	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**0.725**		0.153	U	0.0933	U	0.152	U	0.118	U
		10/11/19	PES	Peristaltic	–		–	–	–	**1.95**		0.412	U	**0.355**	**J**	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		01/20/20	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		04/07/20	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		07/06/20	PES	Peristaltic	–		–	–	–	0.0160	U	0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
MW-301 (duplicate) (35.6 to 25.6)	Valley St ROW, S side	11/30/20	PES	Bladder	31.6	U	–	–	–	0.0160	U	0.0500	U	0.0212	U	**0.196**	**J**	**1.96**		**0.157**		0.0276	U	0.0572	U	0.0273	U
		11/30/20	PES	Bladder	31.6	U	–	–	–	0.0160	U	0.0500	U	0.0212	U	**0.202**	**J**	**1.94**		**0.156**		0.0276	U	0.0572	U	0.0273	U
		02/05/21	PES	Bladder	43.3	U	–	–	–	**0.0790**		**1.44**		**0.209**		**1.17**		**1.62**		**0.101**		0.0276	U	0.0572	U	0.0273	U
		05/14/21	PES	Bladder	31.6	U	–	–	–	0.0160	U	0.0930	U	0.0212	U	0.191	U	**1.85**		**0.110**		0.0276	U	0.0572	U	0.0273	U
(duplicate)		05/14/21	PES	Bladder	31.6	U	–	–	–	0.0160	U	0.108	U	0.0212	U	0.191	U	**1.81**		**0.108**		0.0276	U	0.0572	U	0.0273	U

Table G-6

Petroleum Hydrocarbons and CVOCs in Shallow Zone Groundwater
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																	
					GRO		DRO	ORO	DRO+ORO	Benzene		Toluene		Ethylbenzene		Total Xylenes		PCE		TCE		cDCE		tDCE		VC	
Preliminary Cleanup Level (PCUL)					**800**		**500**	**500**	**500**	**5.0**		**640**		**700**		**1,600**		**5.0**		**4.0**		**16**		**100**		**0.29**	
MW-305	Roy St ROW, S side	10/15/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
(37.4 to 27.4)		01/15/20	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		04/28/20	PES	Bladder	**54.4**	**J**	–	–	–	0.0941	U	0.278	U	0.137	U	0.174	U	0.300	U	0.190	U	0.126	U	0.149	U	0.234	U
		07/27/20	PES	Bladder	–		–	–	–	0.0160	U	**0.199**	**J**	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
		11/06/20	PES	Bladder	–		–	–	–	**0.0314**	**J**	**0.234**		0.0212	U	0.191	U	0.0280	U	0.0160	U	**0.107**		0.0572	U	0.0273	U
		05/18/21	PES	Bladder	–		–	–	–	0.0160	U	**0.109**	**J**	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
MW-310	Alley E of Seattle Roy Aloha Shops	10/10/19	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.148**	**J**	0.152	U	0.118	U
(19.2 to 9.2)		01/14/20	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		04/08/20	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.193**	**J**	0.152	U	0.118	U
		08/04/20	PES	Bladder	–		–	–	–	**0.0270**	**J**	**0.982**		0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
(duplicate)		08/04/20	PES	Bladder	–		–	–	–	**0.0360**	**J**	**0.959**		0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
		11/06/20	PES	Bladder	–		–	–	–	**0.0275**	**J**	**0.348**		0.0212	U	0.191	U	0.0280	U	**0.0554**		**0.134**		0.0572	U	0.0273	UJ
		05/03/21	PES	Peristaltic	–		–	–	–	**0.0420**		**0.413**		**0.138**		**0.909**		0.0280	U	0.0160	U	**0.203**		0.0572	U	0.0273	U
MW-312	Alley E of Seattle Roy Aloha Shops	10/11/19	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
(19.9 to 9.9)		01/21/20	PES	Peristaltic	–		–	–	–	0.0896	U	**1.22**		0.158	U	**0.713**	**J**	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		04/22/20	PES	Bladder	–		–	–	–	0.0941	U	0.278	U	0.137	U	0.174	U	0.300	U	0.190	U	0.126	U	0.149	U	0.234	U
		08/04/20	PES	Bladder	–		–	–	–	0.0160	U	**0.0690**	**J**	0.0212	U	0.191	U	0.0280	U	0.0160	U	**0.0440**	**J**	0.0572	U	0.0273	U
		11/11/20	PES	Bladder	–		–	–	–	0.0160	U	**1.12**	**J-**	0.0212	U	0.191	U	**0.137**		**0.0407**		**0.0820**	**J**	0.0572	U	0.0273	U
		05/03/21	PES	Peristaltic	–		–	–	–	**0.0260**	**J**	**0.748**		**0.182**		**1.07**		0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
MW-313	Alley E of Seattle Roy Aloha Shops	10/10/19	PES	Bladder	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**7.34**		0.152	U	**1.09**	
(20.4 to 10.4)		01/14/20	PES	Bladder	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**2.67**		0.152	U	**2.59**	
		05/04/21	PES	Bladder	–		–	–	–	**0.0300**	**J**	**0.824**		**0.160**		**0.946**		0.0280	U	0.0160	U	**2.31**		0.0572	U	**0.524**	
MW-320	9th Ave N ROW, W side	10/07/19	PES	Peristaltic	–		–	–	–	0.0896	U	**0.459**	**J**	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
(18.6 to 8.6)		01/20/20	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		04/29/20	PES	Bladder	–		–	–	–	0.0941	U	0.278	U	0.137	U	0.174	U	0.300	U	0.190	U	0.126	U	0.149	U	0.234	U
		07/28/20	PES	Bladder	–		–	–	–	0.0941	U	0.278	U	0.137	U	0.174	U	0.300	U	0.190	U	0.126	U	0.149	U	0.234	U
		11/12/20	PES	Bladder	–		–	–	–	0.0160	U	**0.338**	**J-**	0.0212	U	0.191	U	0.0280	U	0.0160	U	**0.0350**	**J**	0.0572	U	0.0273	U
		05/20/21	PES	Peristaltic	–		–	–	–	0.0160	U	0.0520	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
MW-332	Roy St ROW, N side	05/04/20	PES	Bladder	–		–	–	–	0.0941	U	0.278	U	0.137	U	0.174	U	0.300	U	0.190	U	**0.419**	**J**	0.149	U	0.234	U
(16.0 to 6.0)		07/30/20	PES	Bladder	–		–	–	–	0.0160	U	0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	**0.110**	**J**	0.0572	UJ	**0.145**	
		11/12/20	PES	Bladder	–		–	–	–	0.0160	U	**0.584**	**J-**	0.0212	U	0.191	U	**0.112**		0.0160	U	**0.202**		0.0572	U	**0.102**	**J+**
		05/20/21	PES	Peristaltic	–		–	–	–	0.0160	U	0.0710	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
MW-337	Lake Union Park, N end	05/07/20	PES	Peristaltic	–		–	–	–	0.0941	U	0.278	U	0.137	U	0.174	U	0.300	U	0.190	U	0.126	U	0.149	U	0.234	U
(18.1 to 8.1)		07/23/20	PES	Peristaltic	–		–	–	–	0.0160	U	**0.145**	**J**	0.0212	U	0.191	U	0.0280	U	**0.0260**	**J**	**0.0560**	**J**	0.0572	U	0.0273	U
		11/10/20	PES	Peristaltic	–		–	–	–	**0.0190**	**J**	0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	**0.0870**	**J**	0.0572	U	0.0273	U
		05/04/21	PES	Peristaltic	–		–	–	–	0.0160	U	0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	**0.0490**	**J**	0.0572	U	**0.0670**	**J**
MW-339	Lake Union Park, S end	05/14/20	PES	Peristaltic	–		–	–	–	0.0941	U	0.278	U	0.137	U	0.174	U	0.300	U	0.190	U	0.126	U	0.149	U	0.234	U
(duplicate)		05/14/20	PES	Peristaltic	–		–	–	–	0.0941	U	0.278	U	0.137	U	0.174	U	0.300	U	0.190	U	0.126	U	0.149	U	0.234	U
(18.2 to 8.2)		07/23/20	PES	Peristaltic	–		–	–	–	0.0160	U	0.0500	U	0.0212	U	0.191	U	0.0280	U	**0.0280**	**J**	**0.164**		0.0572	U	0.0273	U
		11/09/20	PES	Peristaltic	–		–	–	–	**0.0190**	**J**	0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	**0.238**		0.0572	U	0.0273	U
		05/25/21	PES	Peristaltic	–		–	–	–	0.0160	U	0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	**0.120**		0.0572	U	0.0273	U

Table G-6

Petroleum Hydrocarbons and CVOCs in Shallow Zone Groundwater
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																					
					GRO		DRO		ORO		DRO+ORO		Benzene		Toluene		Ethylbenzene		Total Xylenes		PCE		TCE		cDCE		tDCE		VC	
Preliminary Cleanup Level (PCUL)					**800**		**500**		**500**		**500**		**5.0**		**640**		**700**		**1,600**		**5.0**		**4.0**		**16**		**100**		**0.29**	
N7 (41.8 to 11.8)	Property, SW quadrant	07/19/13	SES	Peristaltic	–		–		–		–		–		–		–		–		**640**		**50**		**18**		1	U	0.2	U
		10/19/15	SES	Peristaltic	–		–		–		–		–		–		–		–		**2,900**		**99**		**9.9**		1	U	0.2	U
		02/02/16	SES	Peristaltic	–		–		–		–		–		–		–		–		**230**		**79**		**1,700**		**2.9**		**0.92**	
		03/30/17	PES	Peristaltic	–		–		–		–		**0.178**	**J**	0.412	U	0.158	U	0.316	U	**280**		**50.4**		**125**		**0.396**	**J**	**0.310**	**J**
		06/27/17	PES	Peristaltic	–		–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**205**		**85.1**		**153**		**0.955**		**0.386**	**J**
		Decommissioned March 2019																												
R-MW1 (33.8 to 23.8)	Property	10/24/92	Roux	Unknown	**57**		**1,345**		**6,000**		**7,345**		**1**		**1**		0.5	U	0.5	U	5	U	5	U	–		5	U	**100**	
		10/24/92	DOF	Unknown	**53**		**26,000**		**12,000**		**3,800**		**0.61**		**0.83**		0.50	U	1.0	U	**4.2**		**0.82**		**12.0**	**c**	–		**170**	
		10/24/92	Roux	Unknown	**54**		**290**		**5,000**		**5000**		**0.58**		**1**		0.5	U	0.5	U	**2.3**		2	U	**14**		–		**140**	
		01/29/09	DOF	Peristaltic	50.0	U	–		–		–		0.500	U	0.500	U	0.500	U	1.00	U	**17.1**		**4.26**		**1.60**		0.200	U	**0.630**	
		06/02/11	SES	Peristaltic	100	U	**1,000**	**x**	**740**		**1,740**	**x**	0.35	U	1	U	1	U	3	U	**7.9**		**2.7**		**1.9**		1	U	**0.68**	
		09/05/12	SES	Peristaltic	–		–		–		–		0.35	U	1	U	1	U	3	U	**16**		**3.6**		**2.1**		1	U	**2.20**	
		Decommissioned																												
R-MW2 (36.7 to 26.7)	Property, NE quadrant	10/24/92	Roux	Unknown	**4,200**		**34**		**2,000**		**2,034**		**684**		**17**		**301**		**403**		5	U	5	U	–		5	U	5	U
		10/24/92	DOF	Unknown	**4,000**		**16,000**		**25,000**		**41,000**		**310**		0.50	U	**140**		**180**		–		–		–		–		–	
		01/29/09	DOF	Peristaltic	**657**		–		–		–		0.500	U	**0.557**		**0.513**		**2.08**		**5.05**		0.200	U	0.200	U	0.200	U	0.200	U
		06/02/11	SES	Peristaltic	**1,700**		**3,100**		**290**	**x**	**3,390**	**x**	**19**		1	U	1	U	3	U	1	U	1	U	1	U	1	U	0.2	U
		09/04/12	SES	Peristaltic	–		–		–		–		0.35	U	1	U	1	U	3	U	1	U	1	U	1	U	1	U	0.2	U
		03/21/17	PES	Peristaltic	–		–		–		–		**0.272**	**J**	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.341**	**J**	0.152	U	**0.522**	
		06/15/17	PES	Peristaltic	–		–		–		–		**0.694**		0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.682**		0.152	U	**0.609**	
		04/02/18	PES	Peristaltic	38.0	U	–		–		–		**0.568**		0.412	U	0.158	U	0.316	U	**0.866**		**0.620**		**2.48**		0.152	U	**1.33**	
		Decommissioned March 2019																												
R-MW3 (34.7 to 24.7)	Property, NE quadrant	10/24/92	Roux	Unknown	**87**		**3,015**		**1,200**		**4,215**		0.5	U	0.5	U	0.5	U	0.5	U	5	U	5	U	–		5	U	5	U
		10/24/92	DOF	Unknown	50	U	–		–		–		0.50	U	0.50	U	0.50	U	1.0	U	–		–		–		–		–	
		01/29/09	DOF	Peristaltic	50.0	U	–		–		–		0.500	U	0.500	U	0.500	U	1.00	U	**4.26**		0.200	U	0.200	U	0.200	U	0.200	U
		06/02/11	SES	Peristaltic	100	U	**240**	**x**	250	U	**240**	**x**	0.35	U	1	U	1	U	3	U	1	U	1	U	1	U	1	U	0.2	U
		09/04/12	SES	Peristaltic	–		–		–		–		0.35	U	1	U	1	U	3	U	**6.4**		1	U	1	U	1	U	0.2	U
		03/21/17	PES	Peristaltic	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**1.38**		**0.714**		**0.575**		0.152	U	0.118	U
		06/28/17	PES	Peristaltic	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**0.834**		**0.582**		**0.735**		0.152	U	**0.424**	**J**
		04/04/18	PES	Peristaltic	**33.7**	**J**	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**16.4**		**0.972**		**1.35**		0.152	U	**0.214**	**J**
		Decommissioned March 2019																												
R-MW4 (25.9 to 10.9)	Roy St ROW	10/24/92	Roux	Unknown	**410**		**201**		1000	U	**201**		0.5	U	**2**		**1**		**4**		**814**		**64**		–		5	U	5	U
		10/24/92	DOF	Unknown	**640**		–		–		–		0.5	U	**1.8**		0.5	U	**3.1**		**31**		**2.8**		2.0	U	–		2.0	U
		Decommissioned before 2009																												
R-MW5 (42.4 to 27.4)	Dexter Ave N ROW, E side	10/28/92	Roux	Unknown	**93**		**86**		1000	U	**86**		0.5	U	**1**		0.5	U	0.5	U	0.5	U	0.5	U	0.5	U	–		0.5	U
		01/29/09	DOF	Peristaltic	50	U	–		–		–		0.500	U	0.500	U	0.500	U	1.00	U	**0.800**		0.200	U	0.200	U	0.200	U	0.200	U
		06/02/11	SES	Peristaltic	100	U	50	U	250	U	50	U	0.35	U	1	U	1	U	3	U	1	U	1	U	1	U	1	U	0.2	U
		09/05/12	SES	Peristaltic	–		–		–		–		0.35	U	1	U	1	U	3	U	1	U	1	U	1	U	1	U	0.2	U
		12/18/13	SES	Peristaltic	100	U	50	U	250	U	50	U	0.35	U	1	U	1	U	3	U	1	U	1	U	1	U	1	U	0.2	U
		03/23/17	PES	Peristaltic	–		–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**0.338**	**J**	**0.186**	**J**	0.0933	U	0.152	U	0.118	U
		06/16/17	PES	Bladder	–		–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**0.257**	**J**	**0.245**	**J**	0.0933	U	0.152	U	0.118	U
		04/11/18	PES	Bladder	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**0.621**		0.153	U	0.0933	U	0.152	U	0.118	U
		01/03/19	PES	Peristaltic	**81.5**	**J**	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**0.477**	**J**	0.153	U	0.0933	U	0.152	U	0.118	U
		04/22/19	PES	Peristaltic	31.6	U	–		–		–		0.0896	U	**0.428**	**J**	0.158	U	0.316	U	**0.499**	**J**	**0.155**	**J**	0.0933	U	0.152	U	0.118	UJ
		07/16/19	PES	Bladder	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**0.736**		0.153	U	**0.131**	**J**	0.152	U	0.118	U
		10/21/19	PES	Bladder	**95.3**	**J**	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**0.523**		0.153	U	**0.302**	**J**	0.152	U	0.118	U

Table G-6

Petroleum Hydrocarbons and CVOCs in Shallow Zone Groundwater
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																					
					GRO		DRO		ORO		DRO+ORO		Benzene		Toluene		Ethylbenzene		Total Xylenes		PCE		TCE		cDCE		tDCE		VC	
Preliminary Cleanup Level (PCUL)					**800**		**500**		**500**		**500**		**5.0**		**640**		**700**		**1,600**		**5.0**		**4.0**		**16**		**100**		**0.29**	
R-MW5 (continued)		01/24/20	PES	Bladder	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**0.931**		**0.374**	**J**	**0.265**	**J**	0.152	U	0.118	U
		11/18/20	PES	Bladder	43.8	U	–		–		–		0.0160	U	**0.205**		0.0212	U	0.191	U	**0.607**		**0.318**		**0.505**		0.0572	U	0.0273	U
		02/11/21	PES	Bladder	31.6	U	–		–		–		0.0160	U	0.0500	U	0.0212	U	0.191	U	**0.741**		**0.271**		**0.357**		0.0572	U	0.0273	U
(duplicate)		02/11/21	PES	Bladder	**45.1**	**J**	–		–		–		0.0160	U	0.0500	U	0.0212	U	0.191	U	**0.990**		**0.286**		**0.382**		0.0572	U	0.0273	U
		05/17/21	PES	Bladder	31.6	U	–		–		–		0.0160	U	**0.147**	**J**	0.0212	U	0.191	U	**0.671**		**0.232**		**0.186**		0.0572	U	0.0273	U
R-MW6 (33.3 to 23.3)	8th Ave N ROW, W side	10/28/92	Roux	Unknown	50	U	50	U	1000	U	50	U	0.5	U	**2**		0.5	U	**2**		**4,500**		**920**		**2,600**		–		**240**	
		11/03/92	DOF	Unknown	–		–		–		–		–		–		–		–		**690**		**160**		**620**		–		40	U
		01/29/09	DOF	Peristaltic	50.0	U	–		–		–		0.500	U	0.500	U	0.500	U	1.00	U	**1.78**		0.200	U	**2.64**		0.200	U	**2.75**	
		05/03/10	SES	Peristaltic	–		–		–		–		–		–		–		–		1	U	1	U	**1.2**		1	U	**2.8**	
		06/02/11	SES	Peristaltic	100	U	**120**	**x**	250	U	**120**	**x**	0.35	U	1	U	1	U	3	U	1	U	1	U	1	U	1	U	**2.1**	
		09/05/12	SES	Peristaltic	–		–		–		–		0.35	U	1	U	1	U	3	U	1	U	1	U	1	U	1	U	0.2	U
		03/21/17	PES	Peristaltic	**42.8**	**J**	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**1.08**		**3.17**		**20.0**		**0.242**	**J**	**8.65**	
		06/20/17	PES	Peristaltic	**38.5**		–		–		–		**0.167**	**J**	**0.619**		0.158	U	0.316	U	**1.19**		**0.878**		**37.3**		**0.445**	**J**	**43.9**	
		04/06/18	PES	Peristaltic	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**1.85**		**2.24**		**19.4**		**0.277**	**J**	**26.9**	
		01/25/19	PES	Peristaltic	–		–		–		–		**0.142**	**J**	0.412	U	0.158	U	0.316	U	**0.328**	**J**	**1.07**		**12.5**		0.152	U	**9.14**	
		04/25/19	PES	Peristaltic	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**0.370**	**J**	**11.8**		**0.168**	**J**	**7.16**	**J**
		12/01/20	PES	Peristaltic	–		–		–		–		**0.0490**		**0.336**		**0.0670**	**J**	**0.513**		**0.670**		**1.07**		**2.15**		0.0572	U	**0.583**	
		02/03/21	PES	Peristaltic	–		–		–		–		0.0160	U	**0.198**	**J**	**0.0810**	**J**	**0.550**		**0.371**		**0.341**		**1.22**		0.0572	U	**0.248**	
		05/17/21	PES	Peristaltic	–		–		–		–		**0.0770**		**1.02**		**0.129**		**0.696**		**0.0670**	**J**	**0.349**		**12.2**		**0.0930**	**J**	**2.86**	
SCL-MW101 (25.5 to 15.5)	Alley E of Seattle Roy Aloha Shops	03/28/17	PES	Peristaltic	–		–		–		–		**6.74**		0.624	U	**0.598**		**2.08**		0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		06/14/17	PES	Peristaltic	–		–		–		–		**18.6**		**1.68**		**17.1**		**3.50**		0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		04/06/18	PES	Peristaltic	–		–		–		–		**10.6**		**1.24**		**11.7**		**3.32**		0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		10/09/19	PES	Peristaltic	–		–		–		–		**11.2**		**2.39**		**16.6**		**3.77**		0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		01/17/20	PES	Peristaltic	–		–		–		–		**15.4**		**0.611**		**1.61**		**3.66**		0.199	U	0.153	U	0.0933	U	0.152	U	0.118	UJ
		04/07/20	PES	Peristaltic	–		–		–		–		**7.26**		**0.868**		**5.54**		**1.74**		0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		11/24/20	PES	Peristaltic	–		–		–		–		**14.6**		**1.24**		**3.53**		**3.95**		0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
		05/04/21	PES	Peristaltic	–		–		–		–		**6.04**		**0.395**		**1.22**		**1.48**		0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
SCL-MW105 (11.1 to 1.1)	Alley E of Seattle Roy Aloha Shops	03/28/17	PES	Peristaltic	–		–		–		–		**257**		**16.3**		**26.5**		**33.9**		0.995	U	0.765	U	0.466	U	0.760	U	0.590	U
		06/15/17	PES	Peristaltic	–		–		–		–		**208**		**14.3**		**109**		**40.8**		0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		04/06/18	PES	Peristaltic	–		–		–		–		**181**		**12.1**		**26.6**		**28.4**		1.99	U	1.53	U	0.933	U	1.52	U	1.18	U
		10/10/19	PES	Peristaltic	–		–		–		–		**133**		**15.5**		**41.0**		**34.6**		0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		01/17/20	PES	Peristaltic	–		–		–		–		**142**		**14.9**		**54.6**		**28.6**		0.199	U	0.153	U	0.0933	U	0.152	U	0.118	UJ
		04/01/20	PES	Peristaltic	–		–		–		–		**95.1**		**11.3**		**47.4**		**23.4**		0.199	U	0.153	U	**0.550**		0.152	U	0.118	U
		07/24/20	PES	Peristaltic	–		–		–		–		**86.6**		**12.0**		**35.1**		**22.5**		0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U

Table G-6

Petroleum Hydrocarbons and CVOCs in Shallow Zone Groundwater
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)															
					GRO	DRO	ORO	DRO+ORO	Benzene	Toluene	Ethylbenzene	Total Xylenes	PCE	TCE	cDCE	tDCE	VC
Preliminary Cleanup Level (PCUL)					**800**	**500**	**500**	**500**	**5.0**	**640**	**700**	**1,600**	**5.0**	**4.0**	**16**	**100**	**0.29**
SCS-2	Seattle Roy Aloha Shops, N end	03/20/17	PES	Peristaltic	**1,660**	–	–	–	**51.8**	**9.54**	**155**	**181**	0.199 U	0.153 U	0.0933 U	0.152 U	0.118 U
(28.2 to 18.2)		06/12/17	PES	Peristaltic	**901**	–	–	–	**58.9**	**4.49**	**141**	**70.4**	0.199 U	0.153 U	0.0933 U	0.152 U	0.118 U
		04/13/18	PES	Peristaltic	–	–	–	–	**44.3**	**5.18**	**37.3**	**47.7**	0.199 U	0.153 U	0.0933 U	0.152 U	0.118 U
		07/18/19	PES	Peristaltic	**2,190 J+**	–	–	–	**15.5**	**3.71**	**141**	**149**	0.199 U	0.153 U	0.0933 U	0.152 U	0.118 U
(duplicate)		07/18/19	PES	Peristaltic	**2,320 J+**	–	–	–	**15.0**	**3.37**	**187**	**131**	0.199 U	0.153 U	0.0933 U	0.152 U	**0.242 J**
		10/10/19	PES	Peristaltic	–	–	–	–	**20.3**	**6.00**	**307**	**123**	0.199 U	0.153 U	0.0933 U	0.152 U	0.118 U
		01/16/20	PES	Peristaltic	–	–	–	–	**16.9**	**5.00 J**	**135**	**32.2**	1.99 U	1.53 U	0.933 U	1.52 U	1.18 U
Number of Analytes Measured					162	18	12	18	211	211	211	211	212	212	212	212	212
Number of Analytes Detected					60	8	0	8	71	71	41	43	70	70	114	30	72
Frequency of Detection					37%	44%	0%	44%	34%	34%	19%	20%	33%	33%	54%	14%	34%
Maximum Detection					150,000	790 J	–	790 J	257	16.3	307	181	285	85.1	516	4.31	90.6
Minimum Detection					31.6 U	50.0 U	250 U	50.0 U	0.0160 U	0.0500 U	0.0212 U	0.1740 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U
Number of Analytes Detected Above PCUL					4	4	0	4	21	0	0	0	24	18	23	0	60
Frequency of Detection Above PCUL					2%	22%	0%	22%	10%	0%	0%	0%	11%	8%	11%	0%	28%

Notes:

PCULs and screening levels from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021.

Detected results are shown in **bold.**

Detections above the groundwater PCUL level are shown in **bold and highlighted in gray.**

Detections above the groundwater screening level for soil vapor are shown in **bold and highlighted in orange.**

Detections above the groundwater PCUL and screening level for soil vapor are shown in **bold highlighted in grayish-orange.**

cDCE = cis-1,2-Dichloroethene.

DOF = Dalton, Olmsted & Fuglevand, Inc.

DRO = Diesel-range organics.

(duplicate) = field duplicate.

EPJ = EP Johnson Construction Inc. and Environmental

GeoE = GeoEngineers, Inc.

GRO = Gasoline-range organics.

HC = Hart Crowser.

ORO = Oil-range organics.

PCE = Perchloroethylene (tetrachloroethene).

Retec = Remediation Technologies, Inc.

Roux = Roux Associates.

ROW = Right of way.

SES = SoundEarth Strategies, Inc.

TCE = Trichloroethene.

tDCE = trans-1,2-Dichloroethene.

Urban = Urban Redevelopment LLC.

VC = Vinyl chloride.

Well screen elevations indicated below Sample Location in parentheses.

(--) = Well screen elevation unknown.

a = Select sample results for MW-210 incorrectly identified with location SMW-3 on lab reports and sampling forms.

Laboratory and Results Notes:

Petroleum hydrocarbons analyzed by EPA Method 418.1, NWTPH-HCID, NWTPH-Gx, NWTPH-Dx, or 8015-M.

VOCs analyzed by EPA Method 601, 8010S, 8015, 8020, 8021B, 8240, 8260B, 8260C, or 8260D, or by Purge and Trap Gas Chromatogram/Mass Spectrometry.

– = Not analyzed or results not available.

B = The same analyte is found in the associated blank.

c = Reported as total 1,2,-DCE (sum of cis,-1,2- and trans,1-2-DCE isomers).

E = Estimated value. The reported range exceeds the calibration range of the analysis.

f = Analyte was detected in the associated method blank. Analyte concentration in the sample is greater than 10x the concentration found in the method blank.

g = Estimated value. The reported range exceeds the calibration range of the analysis.

J = The identification of the analyte is acceptable; the reported value is an estimate.

J+ = The result is an estimated quantity, but the result may be biased high.

J- = The result is an estimated quantity, but the result may be biased low.

qp = Hydrocarbon result partly due to individual peak(s) in quantitation range.

U = Not detected at or above the laboratory method detection limit (MDL).

x = The sample chromatographic pattern does not resemble the fuel standard used for quantitation.

y = The GRO result in the sample is due to a pattern of peaks that is consistent with the chlorinated volatiles detected by the 8260C analysis.

z = No/low level gasoline/petroleum detection; result is likely elevated due to high detections of CVOCs.

Groundwater statistics are for data collected during the Remediation Investigation, 2017-2021.

Groundwater statistics for GRO exclude "z" qualified data.

Table G-7

Groundwater Petroleum Hydrocarbons and CVOCs in Intermediate A Zone Wells
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																					
					GRO		DRO		ORO		DRO+ORO		Benzene		Toluene		Ethylbenzene		Total Xylenes		PCE		TCE		cDCE		tDCE		VC	
Preliminary Cleanup Level (PCUL)					**800**		**500**		**500**		**500**		**5.0**		**640**		**700**		**1,600**		**5.0**		**4.0**		**16**		**100**		**0.29**	
BB-5 (--)	Seattle DOT Mercer Parcels, SE quadrant	11/17/97	B&V	Bailer	250	U	630	U	630	U	630	U	ND		ND		ND		ND		ND		ND		**1.1**		ND		ND	
		Decommissioned																												
BB-7 (--)	Valley St ROW, N side	11/17/97	B&V	Bailer	250	U	630	U	630	U	630	U	ND		ND		ND		ND		ND		ND		ND		ND		ND	
		Decommissioned																												
BB-8 (14.0 to 4.0)	Roy St ROW, S side	06/24/97	B&V	Bailer	200	U	500	U	1000	U	500	U	**1.8**		**1.3**		1.0	U	1.0	U	**11,000**		**1,500**		**4,200**		**14**		**280**	
		01/29/09	DOF	Unknown	**499**		–		–		–		**0.694**		0.500	U	0.500	U	1.00	U	**896**	**f**	**258**		**441**		**2.45**		**1.48**	
		05/03/10	SES	Peristaltic	–		–		–		–		–		–		–		–		**510**		**120**		**110**		1	U	**0.27**	
		06/02/11	SES	Peristaltic	**130**	**xy**	50	U	250	U	50	U	0.35	U	1	U	1	U	3	U	**170**		**59**		**44**		1	U	0.2	U
		09/05/12	SES	Peristaltic	–		–		–		–		0.35	U	1	U	1	U	3	U	**200**		**41**		**28**		1	U	0.2	U
		12/29/13	SES	Bladder	–		–		–		–		0.35	U	1	U	1	U	3	U	**200**		**38**		**24**		1	U	0.2	U
		06/17/15	SES	Peristaltic	–		–		–		–		–		–		–		–		**170**		**40**		**37**		10	U	**2.0**	
		03/22/17	PES	Peristaltic	–		–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**30.4**		**4.95**		**3.10**		0.152	U	0.118	U
		06/14/17	PES	Peristaltic	–		–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**26.0**		**8.57**		**12.6**		**0.155**	**J**	0.118	U
		04/11/18	PES	Peristaltic	40.9	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**33.7**	**J**	**6.13**	**J**	**4.64**	**J**	0.152	U	0.118	U
(duplicate)		04/11/18	PES	Peristaltic	41.5	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**46.8**	**J**	**8.41**	**J**	**6.28**	**J**	0.152	U	0.118	U
		01/23/19	PES	Peristaltic	**99.6**	**J**	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**133**		**43.1**		**81.5**		**0.402**	**J**	**0.618**	
		04/23/19	PES	Peristaltic	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**48.8**		**9.09**		**7.57**		0.152	U	0.118	UJ
		07/17/19	PES	Bladder	**112**	**zJ+**	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**169**		**28.9**		**19.3**		**0.262**	**J**	0.118	U
		10/22/19	PES	Bladder	**176**	**zJ+**	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**135**		**46.6**		**31.8**		**0.398**	**J**	**0.162**	**J**
(duplicate)		10/22/19	PES	Bladder	**174**	**zJ+**	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**169**		**48.3**		**30.4**		**0.426**	**J**	**0.152**	**J**
		01/20/20	PES	Bladder	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**138**		**25.4**		**16.5**		**0.232**	**J**	0.118	U
(duplicate)		01/20/20	PES	Bladder	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**132**		**24.6**		**16.0**		**0.199**	**J**	0.118	U
		05/12/20	PES	Bladder	**101**	**zJ+**	–		–		–		0.0941	U	**0.682**		0.137	U	**0.387**	**J**	**142**		**30.8**		**17.6**		**0.282**	**J**	0.234	U
		07/27/20	PES	Bladder	–		–		–		–		**0.0570**		**0.268**		**0.0320**	**J**	**0.217**	**J**	**165**		**46.8**		**26.3**		**0.531**		0.0273	U
(duplicate)		07/27/20	PES	Bladder	–		–		–		–		**0.0660**		**0.470**		**0.0710**	**J**	**0.306**		**162**		**45.5**		**26.0**		**0.496**		**0.194**	
		11/17/20	PES	Bladder	–		–		–		–		**0.0950**		**0.339**		0.0212	U	0.191	U	**215**		**107**	**J+**	**101**		**0.802**		**0.302**	
		02/11/21	PES	Peristaltic	–		–		–		–		**0.0490**		**1.58**		**0.242**		**1.28**		**20.1**		**3.83**		**2.19**		0.0572	U	0.0273	U
		06/07/21	PES	Bladder	–		–		–		–		**0.0190**	**J**	0.0500	U	0.0212	U	0.191	U	**54.4**		**12.3**		**6.94**		**0.0980**	**J**	**0.0790**	**J**
BB-8A (--)	Roy St ROW, S side	01/29/09	DOF	Peristaltic	**669**		–		–		–		0.500	U	0.500	U	0.500	U	1.00	U	**1,290**	**f**	**285**		**549**		**2.96**		**3.86**	
		05/03/10	SES	Peristaltic	–		–		–		–		–		–		–		–		**810**		**180**		**140**		**1.6**		**0.78**	
		06/02/11	SES	Peristaltic	**380**	**xy**	50	U	250	U	50	U	3.5	U	10	U	10	U	30	U	**710**		**170**		**170**		10	U	2	U
		Decommissioned																												
BB-12 (--)	9th Ave N ROW, center	05/19/98	B&V	Bailer	250	U	630	U	630	U	630	U	ND		ND		ND		ND		ND		ND		**540**		ND		**380**	
		05/02/10	SES	Peristaltic	–		–		–		–		–		–		–		–		1	U	1	U	1	U	1	U	0.2	U
		Decommissioned																												
BB-12A (--)	9th Ave N ROW, center	05/02/10	SES	Peristaltic	–		–		–		–		–		–		–		–		1	U	1	U	1	U	1	U	0.2	U
		Decommissioned																												
DMW-3IA (16.8 to 6.8)	615 Dexter, NE quadrant	03/18/20	HC	Submersible	100	U	50	U	250	U	50	U	0.20	U	0.20	U	0.20	U	0.40	U	0.20	U	0.20	U	0.20	U	0.20	U	0.20	U
FMW-142 (2.4 to -7.6)	9th Ave N ROW, E side	07/26/19	Farallon	Unknown	–		–		–		–		–		–		–		–		0.20	U	**0.38**		**0.36**		0.20	U	0.20	U
		10/31/19	PES	Peristaltic	–		–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		01/22/20	PES	Peristaltic	–		–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		04/28/20	PES	Bladder	–		–		–		–		0.0941	U	0.278	U	0.137	U	0.174	U	0.300	U	0.190	U	0.126	U	0.149	U	0.234	U
		07/08/20	PES	Bladder	–		–		–		–		0.0160	U	**1.37**		0.0212	U	0.191	U	0.0280	U	0.0160	U	**0.0320**	**J**	0.0572	U	0.0273	U
		11/04/20	PES	Bladder	–		–		–		–		0.0160	U	**0.179**	**J**	0.0212	U	0.191	U	0.0280	U	0.0160	U	**0.0977**	**J**	0.0572	U	0.0273	U
		05/25/21	PES	Peristaltic	–		–		–		–		0.0160	U	0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U

Table G-7

Groundwater Petroleum Hydrocarbons and CVOCs in Intermediate A Zone Wells
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																	
					GRO	DRO	ORO	DRO+ORO	Benzene	Toluene	Ethylbenzene	Total Xylenes	PCE	TCE	cDCE	tDCE	VC					
Preliminary Cleanup Level (PCUL)					**800**	**500**	**500**	**500**	**5.0**	**640**	**700**	**1,600**	**5.0**	**4.0**	**16**	**100**	**0.29**					
GEI-1	Block 37, SW quadrant	03/24/17	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	0.0933 U	0.152 U	0.118 U					
(1.2 to -8.9)		06/13/17	PES	Bladder	–	–	–	–	0.0896 U	0.412 U	**0.244 J**	0.316 U	0.199 U	0.153 U	0.0933 U	0.152 U	0.118 U					
		04/22/19	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	0.0933 U	0.152 U	0.118 UJ					
		07/16/19	PES	Bladder	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	0.0933 U	0.152 U	0.118 U					
		10/21/19	PES	Peristaltic	–				0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	0.0933 U	0.152 U	0.118 U					
		01/22/20	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	0.0933 U	0.152 U	0.118 U					
		04/29/20	PES	Peristaltic	–	–	–	–	0.0941 U	0.278 U	0.137 U	**0.254 J**	0.300 U	0.190 U	0.126 U	0.149 U	0.234 U					
(duplicate)		04/29/20	PES	Peristaltic	–	–	–	–	0.0941 U	**0.286 J**	0.137 U	0.174 U	0.300 U	0.190 U	0.126 U	0.149 U	0.234 U					
		07/30/20	PES	Peristaltic	–	–	–	–	0.0160 U	**0.142 J**	0.0212 U	0.191 U	0.0280 U	0.0160 U	0.0276 UJ	0.0572 UJ	0.0273 U					
GEI-MW-1	Block 79 East, N end	09/06/14	GeoE	Peristaltic	50.0 U	50.0 U	100 U	50.0 U	1.00 U	1.00 U	–	1.00 U	**0.250**	**0.240**	1.00 U	0.500 U	0.200 U					
(-9.7 to -29.7)		01/23/20	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	**0.230 J**	0.0933 U	0.152 U	0.118 U					
		04/29/20	PES	Peristaltic	–	–	–	–	0.0941 U	**1.06**	**0.161 J**	**0.938 J**	0.300 U	0.190 U	0.126 U	0.149 U	0.234 U					
		08/07/20	PES	Peristaltic	–	–	–	–	**0.0320 J**	**0.162 J**	0.0212 U	0.191 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U					
		11/10/20	PES	Peristaltic	–	–	–	–	0.0160 U	**0.435 J-**	0.0212 U	**0.316**	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U					
		05/13/21	PES	Peristaltic	–	–	–	–	0.0160 U	0.0500 U	0.0212 U	0.191 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U					
GEI-MW-2	Block 79 East, S end	09/06/14	GeoE	Peristaltic	**28.9**	50.0 U	100 U	50.0 U	**14.1**	**4.44**	–	1.00 U	1.00 U	**0.410**	1.00 U	0.500 U	**1.34**					
GEI-MW-3	Block 79 East, S end	09/06/14	GeoE	Peristaltic	50.0 U	50.0 U	100 U	50.0 U	1.00 U	**9.03**	–	1.00 U	1.00 U	**0.610**	1.00 U	0.500 U	**3.14**					
G-MW1	Property	07/24/01	GeoE	Peristaltic	–	–	–	–	**0.449**	**17.6 E**	**0.798**	**5.52**	**85,500**	**1,130**	**23.3 g**	**0.956**	**74.5 g**					
(9.0 to 4.0)		01/29/09	DOF	Peristaltic	**41,300 qp**	–	–	–	20.0 U	20.0 U	**28.6**	**55.1**	**78,400 f**	**1,160**	**34.4**	**1.49**	0.200 U					
		06/03/11	SES	Peristaltic	**29,000 x**	**92 x**	250 U	**92 x**	–	–	–	–	**78,000**	**1,100**	**22**	–	**33**					
		09/06/12	SES	Peristaltic	–	–	–	–	0.35 U	**7.4**	1 U	**1.1**	**66,000**	**1,100**	**32**	**1.5**	**35**					
(duplicate)		09/06/12	SES	Peristaltic	–	–	–	–	0.35 U	**7.6**	1 U	**1.0**	**64,000**	**1,100**	**30**	**1.4**	**33**					
		Decommissioned																				
G-MW3	Property	07/24/01	GeoE	Peristaltic	–	–	–	–	**0.524**	**6.93 E**	**0.459**	**2.10**	**47,700**	**385 g**	0.200 U	**3.71**	**42.5 g**					
(13.6 to 3.6)		12/10/04	DOF	Bailer	–	–	–	–	2 U	**7**	2 U	**2**	**220,000**	**1,200**	**570**	**6**	**19**					
		01/29/09	DOF	Peristaltic	**26,600 qp**	–	–	–	12.5 U	12.5 U	12.5 U	25.0 U	**64,000 f**	**1,580**	**4,050**	**13.9**	0.200 U					
		06/02/11	SES	Peristaltic	**19,000 xy**	**210 x**	250 U	**210 x**	350 U	1,000 U	1,000 U	3,000 U	**33,000**	**1,400**	**1,500**	1000 U	**290**					
		09/06/12	SES	Peristaltic	–	–	–	–	0.35 U	**1.5**	1 U	3 U	**31,000**	**1,200**	**1,600**	**5.9**	**290**					
		Decommissioned																				
HMW-2IA	Seattle DOT Mercer Parcels	03/25/19	HC	Peristaltic	100 U	200 U	500 U	200 U	1.0 U	1.0 U	1.0 U	1.0 U	**240**	**74**	**120**	1.0 U	**1.2**					
(10.8 to 0.8)	NE quadrant	03/12/20	HC	Unknown	**160**	51 U	250 U	51 U	2.0 U	2.0 U	2.0 U	4.0 U	**210**	**69**	**180**	2.0 U	2.0 U					
HMW-3IA	Seattle DOT Mercer Parcels	03/25/19	HC	Peristaltic	100 U	200 U	500 U	200 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	0.2 U					
(20.2 to 10.2)	NW quadrant	03/13/20	HC	Unknown	**190**	**150 J**	250 U	**150 J**	**1.4**	0.20 U	0.20 U	0.40 U	0.20 U	0.20 U	0.20 U	0.20 U	0.20 U					
HMW-6IA	Seattle DOT Mercer Parcels	03/13/20	HC	Unknown	100 U	**160 J**	250 U	**160 J**	0.20 U	0.20 U	0.20 U	0.40 U	0.20 U	0.20 U	0.20 U	0.20 U	0.20 U					
(21.2 to 11.2)	SW quadrant																					
HMW-9IA	Seattle DOT Mercer Parcels	03/19/20	HC	Unknown	100 U	50 U	250 U	50 U	0.20 U	0.20 U	0.20 U	0.40 U	**0.42**	**0.23**	**3.7**	0.20 U	**0.95**					
(18.6 to 8.6)	SW quadrant	06/02/21	PES	Bladder	–	–	–	–	**0.0450**	**0.0850 J**	0.0212 U	0.191 U	**0.243**	**0.916**	**136**	**0.197 J**	**196**					
HMW-20IA	Seattle DOT Mercer Parcels	09/18/20	HC	Unknown	100 U	50 U	–	50 U	0.20 U	0.20 U	0.20 U	0.40 U	**5.5**	**18**	**840**	**2.5**	**520**					
(12.8 to 2.8)	NW quadrant	06/02/21	PES	Bladder	–	–	–	–	**0.0840**	**0.152 J**	0.0212 U	0.191 U	**1.37**	**31.9**	**6,400**	**17.1**	**5,940**					
MW107	8th Ave N ROW, W side	12/21/12	SES	Peristaltic	**240,000 xy**	**190 x**	250 U	**190 x**	3.5 U	10 U	10 U	30 U	**47,000**	**2,800**	**5,100**	**41**	**200**					
(duplicate)		12/21/12	SES	Peristaltic	–	–	–	–	–	–	–	–	**50,000**	**3,000**	**5,200**	**44**	**270**					
(8.8 to -1.2)		12/16/13	SES	Peristaltic	–	–	–	–	0.37 U	**1.8**	1 U	**3.3**	**32,000**	**2,400**	**4,000**	**34**	**76**					

Table G-7

Groundwater Petroleum Hydrocarbons and CVOCs in Intermediate A Zone Wells
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																					
					GRO		DRO	ORO	DRO+ORO	Benzene		Toluene		Ethylbenzene		Total Xylenes		PCE		TCE		cDCE		tDCE		VC	
Preliminary Cleanup Level (PCUL)					**800**		**500**	**500**	**500**	**5.0**		**640**		**700**		**1,600**		**5.0**		**4.0**		**16**		**100**		**0.29**	
MW107 (continued)		06/17/15	SES	Peristaltic	–		–	–	–	–		–		–		–		**1,900**		**5,000**		**5,000**		100	U	**40**	
		10/20/15	SES	Peristaltic	–		–	–	–	–		–		–		–		**2,300**		**5,100**		**3,600**		**60**		**27**	
		11/10/15	SES	Peristaltic	–		–	–	–	–		–		–		–		**620**		**3,800**		**4,400**		**54**		**31**	
		12/11/15	SES	Peristaltic	–		–	–	–	–		–		–		–		**1,200**		**4,200**		**4,200**		**57**		**22**	
		01/08/16	SES	Peristaltic	–		–	–	–	–		–		–		–		**1,000**		**3,600**		**3,900**		**50**		**20**	
		02/01/16	SES	Peristaltic	–		–	–	–	–		–		–		–		**61**		**220**		**10,000**		**33**		**73**	
		03/27/17	PES	Peristaltic	–		–	–	–	**0.204**	**J**	**0.690**	**J**	0.158	U	0.316	U	**0.224**	**J**	**0.370**	**J**	**6.82**		**14.0**		**34.5**	
		06/19/17	PES	Peristaltic	–		–	–	–	**0.238**	**J**	**0.700**		0.158	U	0.316	U	0.199	U	**0.290**	**J**	**7.29**		**12.6**		**15.0**	
		04/09/18	PES	Peristaltic	–		–	–	–	**0.193**	**J**	0.412	U	0.158	U	0.316	U	**0.879**	**J-**	**0.581**	**J-**	**72.1**	**J-**	**10.5**		**123**	
		01/30/19	PES	Peristaltic	**663**	**zJ+**	–	–	–	**0.215**	**J**	**0.715**		0.158	U	0.316	U	0.199	U	**41.1**		**1,130**		**14.4**		**474**	
		05/01/19	PES	Peristaltic	**481**	**zJ+**	–	–	–	**0.188**	**J**	0.412	U	0.158	U	0.316	U	0.199	U	**99.9**		**1,250**		**14.1**		**374**	
		07/22/19	PES	Bladder	**210**	**zJ+**	–	–	–	**0.188**	**J**	**0.758**		0.158	U	**0.609**	**J**	1.99	U	**2.62**	**J**	**290**		**7.08**		**307**	
		10/15/19	PES	Bladder	**365**	**zJ+**	–	–	–	**0.167**	**J**	**0.572**		0.158	U	0.316	U	**41.7**		**138**		**333**		**7.04**		**216**	
		01/28/20	PES	Bladder	**1,890**	**zJ+**	–	–	–	1.79	U	8.24	U	3.16	U	6.32	U	3.98	U	**168**		**3,590**		**22.2**		**674**	
		04/03/20	PES	Bladder	**1,420**	**zJ+**	–	–	–	**0.298**	**J**	0.412	U	0.158	U	0.316	U	**63.8**		**700**		**2,720**		**15.4**		**216**	
		07/31/20	PES	Bladder	–		–	–	–	0.400	U	1.25	U	0.530	U	4.78	U	0.700	U	**6.98**	**J**	**491**	**J**	**5.36**		**378**	
		12/01/20	PES	Peristaltic	–		–	–	–	**1.65**		**4.45**	**J**	0.530	U	**4.81**	**J**	0.700	U	0.400	U	**13.3**		**5.85**		0.682	U
		02/02/21	PES	Peristaltic	–		–	–	–	**0.112**		**0.704**		**0.166**		**1.04**		**0.0510**	**J**	**0.266**		**5.36**		**6.09**		**1.80**	
		06/02/21	PES	Peristaltic	–		–	–	–	**0.0960**		**0.580**		0.0212	U	0.191	U	**0.0590**	**J**	**0.336**		**3.20**		**3.98**		**1.16**	
MW108 (-7.2 to -17.2)	Alley E of Seattle Roy Aloha Shops	12/21/12	SES	Peristaltic	–		–	–	–	–		–		–		–		**3.4**		**1.8**		**400**		**2.1**		**210**	**pr**
		12/17/13	SES	Peristaltic	–		–	–	–	**1.9**		1	U	1	U	3	U	**3.8**		**4.6**		**360**		**3.6**		**150**	
		06/17/15	SES	Peristaltic	–		–	–	–	–		–		–		–		**4.0**		**11**		**370**		**3.5**		**260**	
		10/20/15	SES	Peristaltic	–		–	–	–	–		–		–		–		**3.0**		**6.4**		**220**		**1.8**		**140**	
		02/02/16	SES	Peristaltic	–		–	–	–	–		–		–		–		**15**		**7.9**		**290**		**1.8**		**180**	
		03/28/17	PES	Peristaltic	–		–	–	–	**1.59**		0.479	U	0.158	U	0.316	U	**73.1**		**12.5**		**278**		**0.899**		**52.3**	
		06/27/17	PES	Bladder	–		–	–	–	**1.26**		0.479	U	0.158	UJ	0.316	U	**194**		**22.1**		**165**		**0.748**		**52.8**	
		04/06/18	PES	Peristaltic	–		–	–	–	**4.00**		**0.599**		0.158	UJ	0.316	U	**1,970**		**284**		**1,030**		**7.13**		**217**	
(duplicate)		04/06/18	PES	Peristaltic	–		–	–	–	**3.83**		**0.597**		0.158	UJ	0.316	U	**1,980**		**287**		**1,020**		**7.91**		**231**	
		01/22/19	PES	Peristaltic	–		–	–	–	**1.67**		**0.562**		0.158	U	0.316	U	**4,190**		**587**		**1,180**		**6.03**		**90.8**	
		04/29/19	PES	Peristaltic	–		–	–	–	**3.20**		0.412	U	0.158	U	0.316	U	**419**		**171**		**970**		**3.22**		**125**	**J**
		07/15/19	PES	Peristaltic	–		–	–	–	**2.90**		0.412	U	0.158	U	0.316	U	**567**		**189**		**918**		**3.48**		**197**	
		10/10/19	PES	Peristaltic	–		–	–	–	**3.16**		0.412	U	**0.327**	**J**	0.316	U	**524**		**483**		**1,080**		**5.55**		**194**	
		01/14/20	PES	Peristaltic	–		–	–	–	**4.55**	**J**	10.3	U	3.95	U	7.90	U	**243**		**235**		**749**		3.80	U	**224**	
		04/22/20	PES	Bladder	–		–	–	–	**25.6**		6.95	U	3.43	U	4.35	U	**53.1**		**96.3**		**178**		3.73	U	**19.3**	
		07/16/20	PES	Bladder	–		–	–	–	**29.7**		**1.73**	**J**	0.530	U	4.78	U	**189**	**J**	**162**		**216**		**1.88**	**J**	**11.3**	
(duplicate)		07/16/20	PES	Bladder	–		–	–	–	**34.3**		**2.20**		0.0212	U	**3.06**		**226**	**J**	**170**		**264**		**2.37**		**16.5**	
		11/04/20	PES	Bladder	–		–	–	–	**46.6**		**2.12**	**J**	0.530	U	**6.15**	**J**	**10.2**		**32.6**		**413**		1.43	U	**107**	
		02/09/21	PES	Peristaltic	–		–	–	–	**2.89**		**0.440**	**J**	0.106	U	0.955	U	**238**	**J**	**106**		**269**		**1.48**		**172**	**J**
		05/03/21	PES	Peristaltic	–		–	–	–	**2.28**		**0.290**	**J**	0.106	U	0.955	U	**182**		**91.9**		**491**		**1.92**		**140**	
MW109 (0.0 to -10.0)	Alley E of Seattle Roy Aloha Shops	12/21/12	SES	Peristaltic	–		–	–	–	–		–		–		–		**91**		**64**		**18**		1	U	**1.5**	
		12/17/13	SES	Peristaltic	–		–	–	–	0.35	U	1	U	1	U	3	U	**4.0**		**18**		**310**		1	U	**27**	
		06/17/15	SES	Peristaltic	–		–	–	–	–		–		–		–		**370**		**890**		**520**		**1.2**		**26**	
		10/20/15	SES	Peristaltic	–		–	–	–	–		–		–		–		**230**		**790**		**400**		20	U	**22**	
		02/02/16	SES	Peristaltic	–		–	–	–	–		–		–		–		**34**		**330**		**270**		1	U	**19**	
		03/29/17	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**0.198**	**J**	**12.6**		0.152	U	**3.49**	
		06/27/17	PES	Bladder	–		–	–	–	0.0896	U	0.412	U	0.158	UJ	0.316	U	**9.69**	**J**	**1.17**		**163**		**1.17**		**6.06**	
		04/06/18	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	1.99	UJ	**210**		**629**		**3.34**		**42.2**	

Table G-7

Groundwater Petroleum Hydrocarbons and CVOCs in Intermediate A Zone Wells
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)															
					GRO	DRO	ORO	DRO+ORO	Benzene	Toluene	Ethylbenzene	Total Xylenes	PCE	TCE	cDCE	tDCE	VC
Preliminary Cleanup Level (PCUL)					**800**	**500**	**500**	**500**	**5.0**	**640**	**700**	**1,600**	**5.0**	**4.0**	**16**	**100**	**0.29**
MW109 (continued)		01/23/19	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.995 U	**43.8**	**403**	**2.08**	**36.8**
		04/29/19	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	**4.78**	0.152 U	**3.06 J**
		07/15/19	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	**0.265 J**	**30.8**	**0.199 J**	**24.4**
		10/15/19	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	**1.03**	**397**	**0.891**	**109**
		01/21/20	PES	Peristaltic	–	–	–	–	0.0896 U	**0.782**	0.158 U	0.316 U	0.199 U	**0.372 J**	**10.4**	0.152 U	**1.02**
		04/22/20	PES	Bladder	–	–	–	–	0.0941 U	0.278 U	0.137 U	0.174 U	0.300 U	0.190 U	**46.8**	**0.229 J**	**15.2**
		07/06/20	PES	Bladder	–	–	–	–	**0.0340 J**	**0.967**	0.0212 U	0.191 U	0.0280 U	**0.162**	**45.4**	**0.293**	**12.4**
		11/02/20	PES	Bladder	–	–	–	–	**0.0550**	**0.105 J**	0.0212 U	0.191 U	0.0280 U	**0.126**	**32.1**	**0.220**	**14.5**
		02/09/21	PES	Bladder	–	–	–	–	**0.0520**	**0.634**	**0.139**	**0.791**	0.0280 U	**0.0860**	**9.89**	**0.125 J**	**13.7 J**
		05/03/21	PES	Peristaltic	–	–	–	–	**0.0430**	**0.751**	**0.154**	**0.987**	0.0280 U	**0.0550**	**6.16**	0.0572 U	**3.49**
MW110 (4.7 to -5.3)	Alley E of Seattle Roy Aloha Shops	12/21/12	SES	Bladder	–	–	–	–	–	–	–	–	**1,100**	**220**	**470**	**3.0**	**33**
		12/19/13	SES	Peristaltic	–	–	–	–	0.35 U	1 U	1 U	3 U	**930**	**240**	**840**	**3.9**	**31**
		04/22/15	SES	Peristaltic	–	–	–	–	–	–	–	–	**1,000**	**210**	**340**	**2.4**	**1**
		06/17/15	SES	Peristaltic	–	–	–	–	–	–	–	–	**1,000**	**200**	**470**	10 U	**12**
		10/20/15	SES	Peristaltic	–	–	–	–	–	–	–	–	**890**	**180**	**380**	**2.2**	**13**
		02/01/16	SES	Peristaltic	–	–	–	–	–	–	–	–	**1,300**	**290**	**460**	**3.0**	**1.1**
		03/23/17	PES	Peristaltic	–	–	–	–	**0.330 J**	0.412 U	0.158 U	0.316 U	**1,070**	**389**	**644**	**4.72**	**1.45**
		06/27/17	PES	Bladder	–	–	–	–	0.0896 U	0.412 U	0.158 UJ	0.316 U	**259**	**176**	**1,120**	**2.66**	**152**
		04/09/18	PES	Bladder	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	**375 J-**	**253 J-**	**675 J-**	**3.72**	**3.54**
		01/23/19	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	**1,260**	**490**	**673**	**5.83**	**1.39**
(duplicate)		01/23/19	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	**1,120**	**499**	**718**	**6.49**	**1.51**
		04/26/19	PES	Bladder	–	–	–	–	**0.291 J**	0.412 U	0.158 U	0.316 U	**1,500**	**613**	**710**	**5.59**	**0.900 J**
		07/15/19	PES	Bladder	–	–	–	–	**0.285 J**	0.412 U	0.158 U	0.316 U	**1,220**	**455**	**578**	**5.87**	**1.26**
		10/15/19	PES	Bladder	–	–	–	–	**0.233 J**	0.412 U	0.158 U	0.316 U	**1,180**	**498**	**574**	**3.86**	**0.853**
		01/16/20	PES	Bladder	–	–	–	–	0.448 U	2.06 U	0.790 U	1.58 U	**459**	**176**	**187**	**1.95 J**	**0.706 J**
		04/22/20	PES	Bladder	–	–	–	–	**0.487 J**	1.39 U	0.685 U	0.870 U	**946**	**384**	**683**	**4.25**	**5.06**
		07/16/20	PES	Bladder	–	–	–	–	**0.335**	**0.465 J**	0.106 U	0.955 U	**741**	**349**	**791**	**7.79**	**12.5**
		11/04/20	PES	Bladder	–	–	–	–	0.800 U	2.50 U	1.06 U	9.55 U	**640**	**343**	**894**	**2.96 J**	**29.6**
		02/09/21	PES	Bladder	–	–	–	–	**0.125**	**0.784**	**0.158**	**0.791**	**602**	**302 J+**	**401**	**2.99**	**0.833 J**
		05/04/21	PES	Bladder	–	–	–	–	0.160 U	**0.730 J**	0.212 U	1.91 U	**484**	**214**	**334**	**2.27**	0.273 U
MW114 (10.8 to 0.8)	Seattle DOT Mercer Parcels NW quadrant	12/21/12	SES	Peristaltic	–	–	–	–	–	–	–	–	**1,400**	**290**	**260**	1 U	**14**
		12/18/13	SES	Peristaltic	–	–	–	–	17 U	50 U	50 U	150 U	**8,400**	**1,300**	**640**	50 U	**22**
		Destroyed															
MW115 (-0.6 to -10.6)	9th Ave N ROW, W side	12/13/12	SES	Peristaltic	–	–	–	–	–	–	–	–	**15**	**1.1**	**3.0**	1 U	**2.6**
		12/21/12	SES	Peristaltic	–	–	–	–	–	–	–	–	1 U	**3.0**	**38**	1 U	**16**
		12/19/13	SES	Peristaltic	–	–	–	–	0.35 U	1 U	1 U	3 U	1 U	1 U	1 U	1 U	**0.75**
		04/21/15	SES	Peristaltic	–	–	–	–	–	–	–	–	1 U	**17**	**170**	1 U	**20**
		06/25/15	SES	Peristaltic	–	–	–	–	–	–	–	–	1 U	1 U	1 U	1 U	**6.2**
		10/27/15	SES	Peristaltic	–	–	–	–	–	–	–	–	1 U	1 U	1 U	1 U	**0.31**
		02/03/16	SES	Peristaltic	–	–	–	–	–	–	–	–	1 U	1 U	1 U	1 U	**2.3**
		03/22/17	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	**0.643**	0.152 U	**15.7**
		06/22/17	PES	Bladder	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	**0.523**	0.152 U	**8.45**
		04/11/18	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	**0.272 J**	0.152 U	**5.81**
		01/30/19	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	**0.316 J**	0.152 U	**12.4**
		07/17/19	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	**0.787**	0.152 U	**24.3**
		10/22/19	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	**0.819**	0.152 U	**23.2**
		01/20/20	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	**0.880**	0.152 U	**26.9**
		05/05/20	PES	Bladder	–	–	–	–	0.0941 U	0.278 U	0.137 U	0.174 U	0.300 U	0.190 U	**0.654**	0.149 U	**8.86**

Table G-7

Groundwater Petroleum Hydrocarbons and CVOCs in Intermediate A Zone Wells
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)															
					GRO	DRO	ORO	DRO+ORO	Benzene	Toluene	Ethylbenzene	Total Xylenes	PCE	TCE	cDCE	tDCE	VC
Preliminary Cleanup Level (PCUL)					**800**	**500**	**500**	**500**	**5.0**	**640**	**700**	**1,600**	**5.0**	**4.0**	**16**	**100**	**0.29**
MW115 (continued)		07/28/20	PES	Bladder	–	–	–	–	0.0941 U	0.278 U	0.137 U	0.174 U	0.300 U	0.190 U	**0.354 J**	0.149 U	**1.16**
		11/12/20	PES	Bladder	–	–	–	–	0.0160 U	**0.221 J-**	0.0212 U	0.191 U	0.0280 U	0.0160 U	**0.308**	0.0572 U	**0.808 J+**
		02/12/21	PES	Bladder	–	–	–	–	**0.0330 J**	**0.515**	**0.0730 J**	**0.453**	0.0280 U	0.0160 U	**0.244**	0.0572 U	**1.02**
		05/25/21	PES	Peristaltic	–	–	–	–	0.0160 U	0.0540 U	0.0212 U	0.191 U	0.0280 U	0.0160 U	**0.140**	0.0572 U	**0.989**
MW116 (-3.1 to -13.1)	9th Ave N ROW, W side	12/07/12	SES	Peristaltic	–	–	–	–	–	–	–	–	**6.8**	1 U	1 U	1 U	0.2 U
		12/21/12	SES	Peristaltic	–	–	–	–	–	–	–	–	**2.7**	1 U	1 U	1 U	0.2 U
		12/19/13	SES	Peristaltic	–	–	–	–	0.35 U	1 U	1 U	3 U	1 U	1 U	1 U	1 U	0.2 U
		06/25/15	SES	Peristaltic	–	–	–	–	–	–	–	–	1 U	1 U	1 U	1 U	0.2 U
		10/27/15	SES	Peristaltic	–	–	–	–	–	–	–	–	1 U	1 U	1 U	1 U	0.2 U
		02/03/16	SES	Peristaltic	–	–	–	–	–	–	–	–	1 U	1 U	1 U	1 U	0.2 U
		03/21/17	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	0.0933 U	0.152 U	0.118 U
		06/16/17	PES	Bladder	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	**0.303 J**	0.0933 U	0.152 U	0.118 U
		04/11/18	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	0.0933 U	0.152 U	0.118 U
		01/30/19	PES	Bladder	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	**0.655**	0.152 U	0.118 U
		07/17/19	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	0.0933 U	0.152 U	0.118 U
		10/31/19	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	0.0933 U	0.152 U	0.118 U
		01/21/20	PES	Peristaltic	–	–	–	–	0.0896 U	**0.775**	0.158 U	**0.351 J**	0.199 U	0.153 U	0.0933 U	0.152 U	0.118 U
		04/29/20	PES	Bladder	–	–	–	–	0.0941 U	0.278 U	0.137 U	0.174 U	0.300 U	0.190 U	0.126 U	0.149 U	0.234 U
		07/28/20	PES	Bladder	–	–	–	–	0.0941 U	0.278 U	0.137 U	0.174 U	0.300 U	0.190 U	0.126 U	0.149 U	0.234 U
		11/12/20	PES	Bladder	–	–	–	–	0.0160 U	0.0500 UJ	0.0212 U	0.191 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U
		02/11/21	PES	Peristaltic	–	–	–	–	**0.0370 J**	**1.23**	**0.161**	**0.968**	**0.0480 J**	0.0160 U	0.0276 U	0.0572 U	0.0273 U
		05/25/21	PES	Peristaltic	–	–	–	–	0.0160 U	0.0560 U	0.0212 U	0.191 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U
MW117 (16.9 to 1.9)	Dexter Ave N ROW, E side	02/08/13	SES	Peristaltic	–	–	–	–	–	–	–	–	1 U	1 U	1 U	1 U	0.2 U
		12/18/13	SES	Peristaltic	100 U	50 U	250 U	50 U	0.35 U	1 U	1 U	3 U	1 U	1 U	1 U	1 U	0.2 U
		Destroyed															
MW118 (12.9 to 2.9)	Mercer St ROW, N side	03/25/13	SES	Peristaltic	–	–	–	–	–	–	–	–	1 U	1 U	1 U	1 U	0.2 U
		12/18/13	SES	Peristaltic	100 U	50 U	250 U	50 U	0.35 U	1 U	1 U	3 U	1 U	1 U	1 U	1 U	0.2 U
		Destroyed															
MW119 (2.7 to -7.3)	9th Ave N ROW, W side	03/25/13	SES	Peristaltic	–	–	–	–	–	–	–	–	1 U	1 U	**3.3**	1 U	0.2 U
		12/19/13	SES	Peristaltic	–	–	–	–	0.35 U	1 U	1 U	3 U	1 U	1 U	**2.5**	1 U	**0.76**
		04/21/15	SES	Peristaltic	–	–	–	–	–	–	–	–	**34**	**42**	**50**	1 U	**3.1**
		06/17/15	SES	Peristaltic	–	–	–	–	–	–	–	–	**4.9**	**7.1**	**52**	1 U	**2.7**
		10/20/15	SES	Peristaltic	–	–	–	–	–	–	–	–	**15**	**22**	**74**	1 U	**0.45**
		02/02/16	SES	Peristaltic	–	–	–	–	–	–	–	–	**7.3**	**24**	**100**	1 U	**0.45**
		03/29/17	PES	Peristaltic	–	–	–	–	**0.139**	0.412 U	0.158 U	0.316 U	**5.47**	**10.7**	**42.9**	**0.334 J**	**0.272 J**
		06/28/17	PES	Bladder	–	–	–	–	0.0896 U	**0.726**	0.158 U	**0.562 J**	**19.0**	**12.4**	**5.99**	**0.167 J**	0.118 U
		04/05/18	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	**2.14**	**3.02**	**18.3**	**0.203 J**	0.118 U
		01/21/19	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	**1.24**	0.153 U	0.0933 U	0.152 U	0.118 U
		04/29/19	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	**0.224 J**	**1.12**	**10.9**	**0.161 J**	0.118 UJ
		07/19/19	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	**0.303 J**	0.153 U	**0.340 J**	0.152 U	0.118 U
		10/10/19	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	**0.876**	**7.54**	**12.6**	**0.159 J**	0.118 U
		11/11/19	Farallon	Unknown	–	–	–	–	–	–	–	–	**3.70**	**9.50**	**10**	0.20 U	0.20 U
		01/14/20	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	**5.90**	**5.81**	**9.63**	0.200 U	0.200 U
(split)		01/14/20	Farallon	Unknown	–	–	–	–	–	–	–	–	**4.8**	**5.1**	**7.4**	0.20 U	0.20 U
		02/18/20	Farallon	Unknown	–	–	–	–	–	–	–	–	**1.3**	**2.5**	**6.6**	0.20 U	0.20 U
		03/24/20	Farallon	Unknown	–	–	–	–	–	–	–	–	**0.24**	**0.87**	**4.7**	0.20 U	0.20 U
		04/27/20	PES	Peristaltic	–	–	–	–	0.0941 U	0.278 U	0.137 U	0.174 U	**0.595**	**1.62**	**6.88**	0.149 U	0.234 U

Table G-7

Groundwater Petroleum Hydrocarbons and CVOCs in Intermediate A Zone Wells
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																	
					GRO		DRO		ORO		DRO+ORO		Benzene		Toluene		Ethylbenzene		Total Xylenes		PCE		TCE		cDCE		tDCE		VC	
Preliminary Cleanup Level (PCUL)					**800**		**500**		**500**		**500**		**5.0**		**640**		**700**		**1,600**		**5.0**		**4.0**		**16**		**100**		**0.29**	
MW119		05/19/20	Farallon	Unknown	–		–		–		–		–		–		–		–		**0.91**		**2.8**		**6.1**		0.20	U	0.20	U
(continued)		07/08/20	PES	Bladder	–		–		–		–		**0.0430**		**0.644**		0.0212	U	0.191	U	**0.306**		**1.96**		**6.67**		**0.163**		**0.0480**	**J**
		07/28/20	Farallon	Unknown	–		–		–		–		–		–		–		–		**0.92**		**2.6**		**7.5**		0.20	U	0.20	U
		09/17/20	Farallon	Unknown	–		–		–		–		–		–		–		–		**0.27**		**1.8**		**7.8**		0.20	U	0.20	U
		11/11/20	PES	Bladder	–		–		–		–		0.0160	U	0.0500	UJ	0.0212	U	0.191	U	**0.420**		**2.63**		**12.9**		**0.0983**	**J**	**0.212**	**J+**
		12/03/20	Farallon	Unknown	–		–		–		–		–		–		–		–		**0.28**		**1.2**		**6.6**		0.20	U	0.20	U
		02/10/21	PES	Peristaltic	–		–		–		–		**0.0470**		0.0500	U	0.0212	U	0.191	U	**0.0410**	**J**	**0.511**		**6.05**		0.0572	U	**0.134**	
(split)		02/10/21	Farallon	Unknown	–		–		–		–		–		–		–		–		0.20	U	**0.46**		**5.0**		0.20	U	0.20	U
		05/20/21	PES	Bladder	–		–		–		–		**0.0410**		0.0710	U	0.0212	U	0.191	U	**0.210**		**1.70**		**10.6**		**0.165**	**J**	**0.252**	
MW120	8th Ave N ROW, E side	12/19/13	SES	Peristaltic	100	U	50	U	**440**	**x**	50	U	0.35	U	1	U	1	U	3	U	**2.8**		**2.3**		**19**		1	U	**9.6**	
(0.0 to -10.0)		06/16/15	SES	Peristaltic	–		–		–		–		–		–		–		–		1	U	1	U	**4.3**		1	U	0.2	U
		10/20/15	SES	Peristaltic	–		–		–		–		–		–		–		–		1	U	**1.1**		**5.2**		1	U	**0.94**	
		02/01/16	SES	Peristaltic	–		–		–		–		–		–		–		–		**1.3**		**1.6**		**6.7**		1	U	**1.1**	
		03/28/17	PES	Peristaltic	–		–		–		–		0.0896	U	0.458	U	0.158	U	0.316	U	**13.9**		**5.81**		**18.4**		0.152	U	**0.871**	
		06/28/17	PES	Bladder	–		–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**18.0**		**6.97**		**16.0**		0.152	U	**0.988**	
		04/09/18	PES	Peristaltic	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.811**		0.152	U	0.118	U
		01/24/19	PES	Peristaltic	**105**	**J+**	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**125**		**34.3**		**60.5**		**0.194**	**J**	**1.64**	
		05/03/19	PES	Peristaltic	**111**	**J+**	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**155**		**46.9**		**87.2**		**0.258**	**J**	**1.28**	
(duplicate)		05/03/19	PES	Peristaltic	**138**	**zJ+**	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**182**		**51.1**		**89.0**		**0.227**	**J**	**1.30**	
		07/16/19	PES	Peristaltic	**152**	**zJ+**	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**134**		**40.1**		**74.9**		**0.217**	**J**	**1.01**	
		10/17/19	PES	Bladder	**106**	**zJ+**	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**61.5**		**22.3**		**48.8**		**0.220**	**J**	**2.31**	
(duplicate)		10/17/19	PES	Bladder	**113**	**zJ+**	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**73.9**		**26.9**		**49.8**		**0.243**	**J**	**2.25**	
		01/17/20	PES	Bladder	**124**	**zJ+**	–		–		–		**0.0983**	**J**	0.412	U	0.158	U	0.316	U	**61.2**		**21.6**		**45.0**		**0.241**	**J**	**2.38**	**J**
		04/23/20	PES	Bladder	**481**	**zJ+**	–		–		–		0.0941	U	0.278	U	0.137	U	0.174	U	**39.7**		**15.4**		**41.0**		**0.154**	**J**	**2.92**	
		07/14/20	PES	Bladder	–		–		–		–		**0.0680**		**0.511**		0.0212	U	0.191	U	**44.0**		**16.2**		**28.8**		**0.249**		**2.78**	
		11/30/20	PES	Bladder	–		–		–		–		**0.0560**		**0.208**		**0.0660**	**J**	**0.435**		**39.3**		**15.6**		**36.6**		**0.188**	**J**	**1.47**	
(duplicate)		11/30/20	PES	Bladder	–		–		–		–		**0.0580**		**0.172**	**J**	0.0212	U	**0.376**		**44.4**		**16.2**		**37.0**		**0.196**	**J**	**1.52**	
		02/05/21	PES	Peristaltic	–		–		–		–		**0.0500**		**0.332**		**0.0790**	**J**	**0.516**		**41.6**		**17.4**		**43.5**		**0.212**	**J**	**1.17**	**J**
		05/12/21	PES	Peristaltic	–		–		–		–		**0.0220**	**J**	**0.137**	**J**	0.0212	U	0.191	U	**31.7**		**13.8**		**29.7**		**0.151**	**J**	**0.633**	
MW127	8th Ave N ROW, E side	01/03/14	SES	Peristaltic	–		–		–		–		0.35	U	1	U	1	U	3	U	1	U	1	U	1	U	1	U	**0.29**	
(-1.0 to -11.0)		01/13/14	SES	Peristaltic	–		–		–		–		0.35	U	1	U	1	U	3	U	1	U	1	U	1	U	1	U	**0.30**	
		08/01/19	PES	Peristaltic	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.489**	**J**	0.152	U	0.118	U
		10/17/19	PES	Bladder	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.656**		0.152	U	0.118	U
		01/17/20	PES	Bladder	61.3	U	–		–		–		0.0896	U	**0.689**		0.158	U	**0.342**	**J**	0.199	U	0.153	U	**0.630**		0.152	U	0.118	UJ
		04/23/20	PES	Bladder	**121**	**zJ+**	–		–		–		0.0941	U	0.278	U	0.137	U	0.174	U	0.300	U	0.190	U	**0.861**		0.149	U	0.234	U
		07/14/20	PES	Bladder	–		–		–		–		0.0160	U	**0.360**		0.0212	U	0.191	U	0.0280	U	0.0160	U	**0.683**		0.0572	U	**0.0790**	**J**
(duplicate)		07/14/20	PES	Bladder	–		–		–		–		0.0160	U	**0.375**		0.0212	U	0.191	U	0.0280	U	0.0160	U	**0.662**		0.0572	U	**0.0730**	**J**
		11/13/20	PES	Bladder	–		–		–		–		**0.0453**		**0.0726**	**J**	0.0212	U	0.191	U	0.0280	U	0.0160	U	**0.898**		0.0572	U	0.0273	U
		05/11/21	PES	Peristaltic	–		–		–		–		0.0160	U	0.0740	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	**0.737**		0.0572	U	0.0273	UJ
MW131	Property, SE quadrant	03/27/17	SES	Peristaltic	**91.9**	**J**	–		–		–		**0.199**	**J**	**0.462**	**J**	0.158	U	0.316	U	0.199	U	0.153	U	**243**		**0.981**		**804**	
(-4.6 to -14.6)		06/20/17	PES	Peristaltic	31.6	U	–		–		–		0.448	U	2.06	U	0.790	U	1.58	U	0.995	U	0.765	U	**2.55**		0.760	U	**435**	
		04/16/18	PES	Peristaltic	55.3	U	–		–		–		**0.142**	**J**	0.412	U	0.158	U	0.316	U	**7.05**		**3.25**		**10.4**		**0.276**	**J**	**18.0**	
		10/25/18	PES	Peristaltic	57.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**0.895**		**0.347**	**J**	**1.65**	**J+**	0.152	U	**1.83**	
		12/12/18	PES	Peristaltic	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**0.172**	**J**	**1.2**		0.152	U	**1.39**	
		01/29/19	PES	Peristaltic	**43.7**	**J**	–		–		–		**0.182**	**J**	**0.516**	**J+**	0.158	U	0.316	U	0.199	U	0.153	U	**0.774**		0.152	U	**0.539**	
		03/11/19	PES	Peristaltic	31.6	U	–		–		–		**0.152**	**J**	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.250**	**J**	0.152	U	0.118	U
		Decommissioned March 2019																												

Table G-7

Groundwater Petroleum Hydrocarbons and CVOCs in Intermediate A Zone Wells
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																					
					GRO		DRO		ORO		DRO+ORO		Benzene		Toluene		Ethylbenzene		Total Xylenes		PCE		TCE		cDCE		tDCE		VC	
Preliminary Cleanup Level (PCUL)					**800**		**500**		**500**		**500**		**5.0**		**640**		**700**		**1,600**		**5.0**		**4.0**		**16**		**100**		**0.29**	
MW-142	8th Ave N ROW, E side	04/27/18	PES	Peristaltic	49.3	U	–		–		–		**0.514**		0.412	U	0.158	U	0.316	U	**0.523**		**1.40**		**46.1**		**0.474**	**J**	**17.2**	
(2.4 to -7.6)		01/28/19	PES	Peristaltic	31.6	U	–		–		–		**0.442**	**J**	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**5.62**		0.152	U	**3.45**	
(duplicate)		01/28/19	PES	Peristaltic	31.6	U	–		–		–		**0.410**	**J**	0.412	U	0.158	U	0.316	U	0.199	U	**0.208**	**J**	**5.67**		0.152	U	**3.38**	
		04/24/19	PES	Peristaltic	31.6	U	–		–		–		**0.361**	**J**	0.412	U	0.158	U	0.316	U	0.199	U	**0.156**	**J**	**5.67**		0.152	U	**4.39**	**J**
		07/25/19	PES	Bladder	31.6	U	–		–		–		**0.413**	**J**	0.412	U	0.158	U	0.316	U	0.199	U	**0.218**	**J**	**7.70**		**0.169**	**J**	**6.57**	
		10/16/19	PES	Bladder	31.6	U	–		–		–		**0.380**	**J**	0.412	U	0.158	U	0.316	U	0.199	U	**0.360**	**J**	**50.4**		**0.282**	**J**	**11.3**	
		01/22/20	PES	Bladder	31.6	U	–		–		–		**0.438**	**J**	0.412	U	0.158	U	0.316	U	0.199	U	**0.311**	**J**	**45.6**		**0.379**	**J**	**8.19**	
		04/24/20	PES	Bladder	62.4	U	–		–		–		**0.359**	**J**	0.278	U	0.137	U	0.174	U	0.300	U	**0.206**	**J**	**53.6**		**0.454**	**J**	**9.14**	
		07/30/20	PES	Bladder	–		–		–		–		**0.451**		**0.0790**	**J**	0.0212	U	0.191	U	**3.34**		**9.74**		**91.2**	**J**	**0.472**	**J**	**6.05**	
		11/24/20	PES	Bladder	–		–		–		–		**0.408**		0.0850	U	0.0390	U	**0.258**	**J**	**0.164**		**24.5**		**136**		**0.734**		**34.6**	
(duplicate)		11/24/20	PES	Bladder	–		–		–		–		**0.509**		0.0930	U	0.0340	U	0.265	U	**0.163**		**22.2**		**142**		**0.827**		**46.1**	
		02/08/21	PES	Peristaltic	–		–		–		–		**0.327**		**1.42**		**0.220**		**1.18**		**0.0940**	**J**	**1.11**		**80.5**		**0.498**		**33.9**	**J**
		05/19/21	PES	Peristaltic	–		–		–		–		**0.320**		0.143	U	**0.106**		**0.343**		0.0280	U	**0.243**		**31.6**		**0.361**		**10.1**	
MW-144	8th Ave N ROW, E side	04/27/18	PES	Peristaltic	**364**	**zJ+**	–		–		–		0.0896	U	**1.40**		0.158	U	0.316	U	**1.86**		**3.31**		**662**		**4.65**		**888**	
(3.9 to -6.1)		01/28/19	PES	Peristaltic	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**0.251**	**J**	**10.4**		**0.489**	**J**	**40.4**	
		04/23/19	PES	Peristaltic	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**0.158**	**J**	**4.09**		**0.472**	**J**	**7.30**	**J**
		Decommissioned December 2019																												
MW-144R	8th Ave N ROW, E side	12/16/19	PES	Bladder	**325**	**zJ+**	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**11.0**		**11.5**		**251**		**0.818**		**71.6**	
(3.9 to -6.5)		01/21/20	PES	Bladder	**60.7**	**J**	–		–		–		0.896	U	4.12	U	1.58	U	3.16	U	1.99	U	1.53	U	**200**		1.52	U	**90.2**	
		04/02/20	PES	Bladder	31.6	U	–		–		–		0.0896	UJ	0.412	UJ	0.158	UJ	0.316	UJ	0.199	UJ	0.153	UJ	**2.01**		0.152	UJ	**14.1**	**J-**
		08/03/20	PES	Bladder	–		–		–		–		**0.0510**		**1.53**		**0.0670**	**J**	**0.341**		**0.0500**	**J**	**0.0960**		**0.459**		0.0572	UJ	**1.58**	**J**
		11/23/20	PES	Bladder	–		–		–		–		**0.0440**		0.101	U	0.0212	U	0.191	U	**0.0420**	**J**	**0.0840**		**0.500**		0.0572	U	**0.411**	
		02/02/21	PES	Peristaltic	–		–		–		–		**0.0460**		**0.393**		**0.150**		**1.03**		0.0280	U	**0.0750**		**0.450**		0.0572	U	**0.632**	
		05/12/21	PES	Peristaltic	–		–		–		–		0.0160	U	**0.0990**	**J**	0.0212	U	0.191	U	0.0280	U	**0.0690**		**0.405**		0.0572	U	**0.365**	
MW-146	Roy St ROW, S side	04/30/18	PES	Bladder	**597**	**zJ+**	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**3.56**		**48.4**		**900**		**6.12**		**2,100**	
(12.8 to 2.8)		01/22/19	PES	Peristaltic	**509**	**zJ+**	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**2.29**		**21.6**		**1,080**		**7.25**		**1,370**	
		04/24/19	PES	Bladder	**88.0**	**zJ+**	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**1.50**		**12.4**		**257**		**1.94**		**383**	
		07/19/19	PES	Bladder	**46.3**	**zJ+**	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**3.08**		**14.4**		**257**	**J**	**3.29**		**580**	**J**
(duplicate)		07/19/19	PES	Bladder	**262**	**zJ+**	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**2.80**		**15.9**		**371**		**3.50**		**842**	**J**
		10/14/19	PES	Bladder	**1,310**	**zJ+**	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**2.03**		**6.77**		**1,350**		**7.85**		**2,830**	
		01/24/20	PES	Bladder	**1,140**	**zJ+**	–		–		–		8.96	U	41.2	U	15.8	U	31.6	U	**21.1**	**J**	15.3	U	**1,460**		15.2	U	**3,900**	
(duplicate)		01/24/20	PES	Bladder	**423**	**ZJ+**	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**1.39**	**J**	**4.80**		**1,510**		**8.45**		**5,800**	
		04/30/20	PES	Bladder	**1,080**	**zJ+**	–		–		–		9.41	U	27.8	U	13.7	U	17.4	U	30.0	U	19.0	U	**2,100**		14.9	U	**6,040**	
		07/09/20	PES	Bladder	–		–		–		–		**0.0740**		**1.13**		0.0212	U	0.191	U	**0.781**		**3.17**		**2,750**		**15.5**		**8,610**	
		11/10/20	PES	Bladder	**2,850**	**zJ+**	–		–		–		**0.842**	**J**	2.50	U	1.06	U	9.55	U	1.40	U	**2.60**		**3,900**		**12.5**		**4,930**	
(split)		11/10/20	HC	Bladder	100	U	50	U	250	U	50	U	170	U	500	U	500	U	1,500	U	500	U	500	U	**3,800**		500	U	**5,200**	
		02/08/21	PES	Peristaltic	–		–		–		–		**0.105**		**1.26**		**0.183**		**0.958**		**0.704**	**J**	**3.52**		**2,690**		**8.01**		**3,910**	
		05/04/21	PES	Bladder	–		–		–		–		0.800	U	2.50	U	1.06	U	9.55	U	1.40	U	0.800	U	**536**		**6.30**	**J**	**4,310**	
MW-149	Property, NE quadrant	04/10/18	PES	Peristaltic	**11,700**	**zJ+**	–		–		–		44.8	U	2.06	U	**0.813**	**J**	**1.64**	**J**	**19,200**		**8,050**		**10,500**		**29.8**		**863**	
(0.7 to -9.3)		10/25/18	PES	Peristaltic	**4,570**	**zJ+**	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**6,100**		**2,720**		**3,320**		**15.3**		**100**	
		12/13/18	PES	Peristaltic	**11,400**	**zJ+**	–		–		–		0.0896	U	**0.717**		0.158	U	**0.414**	**J**	**23,300**		**5,470**		**5,150**		**18.2**		**253**	
(duplicate)		12/13/18	PES	Peristaltic	**11,400**	**zJ+**	–		–		–		0.0896	U	**0.717**		0.158	U	**0.392**	**J**	**24,500**		**5,780**		**5,210**		**18.2**		**243**	**J**
		01/29/19	PES	Peristaltic	**14,400**	**zJ+**	–		–		–		8.96	U	41.2	U	15.8	U	31.6	U	**23,700**		**3,800**		**4,350**		15.2	U	**155**	
		03/13/19	PES	Peristaltic	**15,300**	**zJ+**	–		–		–		**0.222**	**J**	**0.862**		**0.843**		**0.490**	**J**	**2,630**		**2,770**		**30,800**		**129**		**285**	
		Decommissioned March 2019																												
MW-151	Property, SW quadrant	04/10/18	PES	Peristaltic	74.6	U	–		–		–		**0.253**	**J**	0.412	UJ	0.158	UJ	0.316	U	**1.13**		**0.310**	**J**	**59.1**	**J-**	**0.388**	**J-**	**11.4**	
(4.9 to -5.1)		10/25/18	PES	Peristaltic	99.4	U	–		–		–		**0.167**	**J**	0.412	U	0.158	U	0.316	U	**2.28**		**1.38**		**5.80**		**0.346**	**J**	**7.7**	
		12/14/18	PES	Peristaltic	**1,040**	**zJ+**	–		–		–		**0.342**	**J**	**0.440**	**J**	0.158	U	0.316	U	**1,460**		**155**		**1,690**		**4.56**		**530**	

Table G-7

Groundwater Petroleum Hydrocarbons and CVOCs in Intermediate A Zone Wells
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																	
					GRO		DRO	ORO	DRO+ORO	Benzene		Toluene		Ethylbenzene		Total Xylenes		PCE		TCE		cDCE		tDCE		VC	
Preliminary Cleanup Level (PCUL)					**800**		**500**	**500**	**500**	**5.0**		**640**		**700**		**1,600**		**5.0**		**4.0**		**16**		**100**		**0.29**	
MW-151 (continued)		01/31/19	PES	Peristaltic	**340**	**zJ+**	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**106**		**40.4**		**466**		**3.52**		**158**	
		03/12/19	PES	Peristaltic	**143**	**zJ+**	–	–	–	**0.159**	**J**	0.412	U	**4.88**		0.316	U	**0.981**		**1.36**		**196**		**1.60**		**24.9**	
		Decommissioned March 2019																								
MW-156 (2.0 to -8.0)	8th Ave N ROW, E side	04/26/18	PES	Peristaltic	**1,690**	**zJ+**	–	–	–	**0.283**	**J**	**0.479**	**J**	0.158	U	0.316	U	9.95	U	**581**		**2,850**		**9.97**		**407**	
		01/24/19	PES	Peristaltic	**1,480**	**zJ+**	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**1,720**		**723**		**2,050**		**11.5**		11.8	U
		04/24/19	PES	Peristaltic	**2,570**	**zJ+**	–	–	–	**0.339**	**J**	0.412	U	0.158	U	0.316	U	**1,430**		**727**		**1,770**		**9.41**		**3.21**	**J**
(duplicate)		04/24/19	PES	Peristaltic	**2,600**	**zJ+**	–	–	–	**0.330**	**J**	0.412	U	0.158	U	0.316	U	**1,440**		**717**		**1,760**		**9.31**		**3.34**	**J**
		07/22/19	PES	Bladder	**3,100**	**zJ+**	–	–	–	**0.492**	**J**	0.412	U	0.158	U	0.316	U	**232**		**1,270**		**2,310**		**14.5**		**82.0**	
		10/17/19	PES	Bladder	**1,450**	**zJ+**	–	–	–	0.896	U	4.12	U	1.58	U	3.16	U	**682**		**430**		**1,420**		**6.04**		**51.1**	
		01/20/20	PES	Bladder	**2,160**	**zJ+**	–	–	–	**1.64**	**J**	4.12	U	1.58	U	3.16	U	**792**		**534**		**1,590**		**7.04**		**99.6**	
		04/24/20	PES	Bladder	**770**	**zJ+**	–	–	–	4.71	U	13.9	U	6.85	U	8.70	U	**347**		**355**		**1,240**		7.45	U	**104**	
		07/15/20	PES	Bladder	–		–	–	–	**1.60**	**J**	2.50	U	1.06	U	9.55	U	**597**		**486**		**1,040**		**6.50**	**J**	**110**	
		11/11/20	PES	Bladder	–		–	–	–	**0.149**		**0.453**	**J-**	0.0212	U	0.191	U	**719**		**363**		**850**		**4.29**		**2.14**	**J+**
		02/08/21	PES	Peristaltic	–		–	–	–	**0.240**	**J**	**0.540**	**J**	0.212	U	1.91	U	**492**	**J**	**228**		**703**		**4.04**		0.273	U
		05/10/21	PES	Bladder	–		–	–	–	0.800	U	2.50	U	1.06	U	9.55	U	**442**		**184**		**580**		2.86	U	1.36	UJ
MW-189 (-1.2 to -11.2)	Valley St ROW, S side	10/14/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**2.23**		0.152	U	**18.2**	
		01/23/20	PES	Bladder	31.6	U	–	–	–	0.0896	U	**0.501**		0.158	U	0.316	U	0.199	U	0.153	U	**0.514**		0.152	U	**3.01**	
		04/03/20	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.435	U	0.152	U	**1.58**	
(duplicate)		04/03/20	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.449	U	0.152	U	**1.55**	
		08/04/20	PES	Bladder	–		–	–	–	0.0160	U	**0.300**		**0.0240**	**J**	**0.207**	**J**	0.0280	U	0.0160	U	**0.115**		0.0572	UJ	**0.879**	**J**
		11/17/20	PES	Bladder	–		–	–	–	0.0160	U	**0.0620**	**J**	0.0212	U	0.191	U	0.0280	U	0.0160	U	**0.0910**	**J**	0.0572	U	**1.13**	
		02/03/21	PES	Bladder	–		–	–	–	0.0160	U	**0.121**	**J**	0.0212	U	**0.226**	**J**	0.0280	U	0.0160	U	**1.74**		0.0572	U	**28.1**	
		05/14/21	PES	Bladder	–		–	–	–	0.0160	U	0.0640	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	**6.63**		0.0572	U	**45.0**	
MW-302 (3.0 to -7.0)	Dexter Ave N ROW, E side	10/21/19	PES	Bladder	**98.5**	**J**	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		01/24/20	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**0.353**	**J**	**0.164**	**J**	0.0933	U	0.152	U	0.118	U
		05/07/20	PES	Bladder	31.6	U	–	–	–	0.0941	U	**0.308**	**J**	0.137	U	0.174	U	0.300	U	0.190	U	0.126	U	0.149	U	0.234	U
		07/28/20	PES	Bladder	–		–	–	–	0.0941	U	0.278	U	0.137	U	0.174	U	0.300	U	0.190	U	0.126	U	0.149	U	0.234	U
		11/17/20	PES	Bladder	–		–	–	–	**0.0480**		**0.743**		**0.0600**	**J**	**0.243**	**J**	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
		05/17/21	PES	Bladder	–		–	–	–	0.0160	U	**0.0860**	**J**	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
MW-306 (17.2 to 7.2)	Roy St ROW, S side	10/15/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		01/16/20	PES	Bladder	34.3	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		04/28/20	PES	Bladder	**42.7**	**J**	–	–	–	0.0941	U	0.278	U	0.137	U	0.174	U	0.300	U	0.190	U	0.126	U	0.149	U	0.234	U
		07/29/20	PES	Bladder	–		–	–	–	0.0160	U	**0.362**		0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
		11/06/20	PES	Bladder	–		–	–	–	0.0160	U	**0.182**	**J**	0.0212	U	0.191	U	0.0280	U	0.0160	U	**0.0418**	**J**	0.0572	U	0.0273	UJ
		05/18/21	PES	Bladder	–		–	–	–	0.0160	U	**0.0550**	**J**	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
MW-308 (-4.7 to -14.7)	Alley E of Seattle Roy Aloha Shops	10/11/19	PES	Peristaltic	–		–	–	–	**12.5**		**4.38**		0.158	U	0.316	U	0.199	U	0.153	U	**38.9**		**0.492**	**J**	**20.3**	
		01/16/20	PES	Peristaltic	–		–	–	–	**29.3**		0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**11.9**		**0.411**	**J**	**16.3**	
		04/08/20	PES	Peristaltic	–		–	–	–	**21.2**		0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**12.5**		**0.360**	**J**	**12.9**	
		07/06/20	PES	Peristaltic	–		–	–	–	**15.4**		**0.174**	**J**	**0.0620**	**J**	0.191	U	0.0280	U	0.0160	U	**16.0**		**0.608**		**6.98**	
		11/06/20	PES	Peristaltic	–		–	–	–	**38.4**		**0.480**		**0.115**		**0.516**		**0.0324**	**J**	0.0160	U	**6.38**		**0.260**		**2.73**	
		05/04/21	PES	Peristaltic	–		–	–	–	**20.8**		**0.186**	**J**	**0.104**		**0.332**		0.0280	U	0.0160	U	**3.98**		**0.219**		**11.7**	
MW-315 (12.2 to 2.3)	Mercer St ROW, N side	10/03/19	PES	Bladder	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		01/16/20	PES	Bladder	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		04/24/20	PES	Bladder	–		–	–	–	0.0941	U	0.278	U	0.137	U	0.174	U	0.300	U	0.190	U	0.126	U	0.149	U	0.234	U
		07/24/20	PES	Bladder	–		–	–	–	**0.0430**		**0.632**		**0.0760**	**J**	**0.437**		0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
		11/02/20	PES	Bladder	–		–	–	–	0.0160	U	**0.162**	**J**	**0.0460**	**J**	**0.198**	**J**	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
		05/17/21	PES	Bladder	–		–	–	–	0.0160	U	**0.167**	**J**	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U

Table G-7

Groundwater Petroleum Hydrocarbons and CVOCs in Intermediate A Zone Wells
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)													
					GRO	DRO	ORO	DRO+ORO	Benzene	Toluene	Ethylbenzene	Total Xylenes	PCE	TCE	cDCE	tDCE	VC	
Preliminary Cleanup Level (PCUL)					**800**	**500**	**500**	**500**	**5.0**	**640**	**700**	**1,600**	**5.0**	**4.0**	**16**	**100**	**0.29**	
MW-317 (3.4 to -6.6)	9th Ave N ROW, W side	10/09/19	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	0.0933 U	0.152 U	0.118 U	
		01/16/20	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	0.0933 U	0.152 U	0.118 U	
		04/27/20	PES	Bladder	–	–	–	–	0.0941 U	0.278 U	0.137 U	0.174 U	0.300 U	0.190 U	0.126 U	0.149 U	0.234 U	
		07/30/20	PES	Peristaltic	–	–	–	–	**0.0457**	**1.98**	**0.205**	**1.36**	0.0280 U	0.0160 U	**0.0545 J**	0.0572 UJ	0.0273 U	
		11/10/20	PES	Peristaltic	–	–	–	–	0.0160 U	**0.836 J-**	0.0212 U	**0.419**	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U	
		05/19/21	PES	Peristaltic	–	–	–	–	0.0160 U	0.0500 U	0.0212 U	0.191 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U	
MW-325 (7.0 to -3.0)	Mercer St ROW, N side	10/03/19	PES	Bladder	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	**0.607**	0.152 U	0.118 U	
		01/17/20	PES	Bladder	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	0.0933 U	0.152 U	0.118 UJ	
		04/21/20	PES	Bladder	–	–	–	–	0.0941 U	0.278 U	0.137 U	0.174 U	0.300 U	0.190 U	**0.696**	0.149 U	0.234 U	
		07/23/20	PES	Bladder	–	–	–	–	**0.0190 J**	**0.298**	**0.0450 J**	**0.256 J**	0.0280 U	0.0160 U	**0.262**	0.0572 U	0.0273 U	
		11/02/20	PES	Bladder	–	–	–	–	0.0160 U	0.0500 U	0.0212 U	0.191 U	0.0280 U	0.0160 U	**0.802**	0.0572 U	0.0273 U	
		02/08/21	PES	Bladder	–	–	–	–	**0.0650**	**2.03**	**0.230**	**1.10**	0.0280 U	0.0160 U	**1.50**	0.0572 U	0.0273 U	
		05/17/21	PES	Bladder	–	–	–	–	0.0160 U	**0.0930 J**	0.0212 U	0.191 U	0.0280 U	0.0160 U	**0.973**	0.0572 U	0.0273 U	
MW-327 (3.6 to -6.3)	Lake Union Park, S end	10/02/19	PES	Bladder	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	0.0933 U	0.152 U	0.118 U	
		01/17/20	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	0.0933 U	0.152 U	0.118 UJ	
		04/09/20	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	0.0933 U	0.152 U	0.118 U	
		07/07/20	PES	Peristaltic	–	–	–	–	0.0160 U	**0.351**	0.0212 U	0.191 U	**0.260**	**0.267**	**0.0580 J**	0.0572 U	0.0273 U	
		11/09/20	PES	Peristaltic	–	–	–	–	**0.0200 J**	**0.173 J**	**0.0340 J**	**0.219 J**	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U	
		05/25/21	PES	Peristaltic	–	–	–	–	0.0160 U	0.0500 U	0.0212 U	0.191 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U	
MW-330 (duplicate) (-0.01 to -10.1)	Valley St ROW, N side	05/14/20	PES	Bladder	31.6 U	–	–	–	0.0941 U	**0.580**	0.137 U	**0.278 J**	0.300 U	0.190 U	0.126 U	0.149 U	0.234 U	
		05/14/20	PES	Bladder	31.6 U	–	–	–	0.0941 U	**0.547**	0.137 U	**0.278 J**	0.300 U	0.190 U	0.126 U	0.149 U	0.234 U	
		07/16/20	PES	Bladder	–	–	–	–	**0.0500**	**2.49**	**0.0690 J**	**0.263**	**0.0625 J**	**0.0646**	**0.0583 J**	0.0572 U	0.0273 U	
		12/01/20	PES	Bladder	–	–	–	–	0.0160 U	**0.215**	**0.113**	**0.801**	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U	
(duplicate)		12/01/20	PES	Bladder	–	–	–	–	**0.0200 J**	**0.212**	**0.127**	**0.789**	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U	
		05/25/21	PES	Bladder	–	–	–	–	0.0160 U	0.202 U	0.0212 U	0.191 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U	
MW-331 (-4.3 to -14.3)	Alley E of Seattle Roy Aloha Shops	04/24/20	PES	Peristaltic	–	–	–	–	**0.226 J**	0.278 U	**0.257 J**	0.174 U	0.300 U	0.190 U	0.126 U	0.149 U	**0.249 J**	
		07/06/20	PES	Peristaltic	–	–	–	–	**0.0610**	0.0500 U	**0.0340 J**	0.191 U	0.0280 U	0.0160 U	**0.046 J**	0.0572 U	**0.306**	
		11/06/20	PES	Peristaltic	–	–	–	–	**0.0407**	**0.230**	**0.0354 J**	**0.219 J**	0.0280 U	0.0160 U	**0.0728 J**	0.0572 U	**0.264**	
		05/04/21	PES	Peristaltic	–	–	–	–	**0.0240 J**	0.0500 U	0.0212 U	0.191 U	0.0280 U	0.0160 U	**0.0370 J**	0.0572 U	**0.339**	
MW-333 (-1.5 to -11.5)	900 Roy St, S end	04/29/20	PES	Bladder	–	–	–	–	0.0941 U	**1.08**	**0.189 J**	**0.854 J**	0.300 U	0.190 U	0.126 U	0.149 U	0.234 U	
		07/24/20	PES	Bladder	–	–	–	–	**0.0200 J**	**0.253**	0.0212 U	0.191 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U	
		11/05/20	PES	Bladder	–	–	–	–	0.0160 U	**0.253**	0.0212 U	0.191 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U	
		05/18/21	PES	Peristaltic	–	–	–	–	0.0160 U	**0.0870 J**	0.0212 U	0.191 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U	

Table G-7

Groundwater Petroleum Hydrocarbons and CVOCs in Intermediate A Zone Wells
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)												
					GRO	DRO	ORO	DRO+ORO	Benzene	Toluene	Ethylbenzene	Total Xylenes	PCE	TCE	cDCE	tDCE	VC
Preliminary Cleanup Level (PCUL)					**800**	**500**	**500**	**500**	**5.0**	**640**	**700**	**1,600**	**5.0**	**4.0**	**16**	**100**	**0.29**
MW-344 (13.6 to 3.6)	Seattle DOT Mercer Parcels	06/01/21	PES	Bladder	–	–	–	–	0.0160 U	**0.0700 J**	0.0212 U	0.191 U	**0.0920 J**	**0.0940**	**8.50**	0.0572 U	**9.95**
Number of Analytes Measured					107	21	22	21	274	274	274	274	282	282	282	282	282
Number of Analytes Detected					59	2	0	2	106	96	38	46	128	155	212	123	163
Frequency of Detection					55%	10%	0%	10%	39%	35%	14%	17%	45%	55%	75%	44%	58%
Maximum Detection					669	–	–	–	46.6	4.5 J	4.9	6.2 J	24,500	8,050	30,800	129.0	8,610
Minimum Detection					28.9	50 U	100 U	50 U	0.0160 U	0.0500 U	0.0212 U	0.1740 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U
Number of Analytes Detected Above SL					0	0	0	0	9	0	0	0	80	93	111	1	153
Frequency of Detection Above SL					0%	0%	0%	0%	3%	0%	0%	0%	28%	33%	39%	0%	54%

Notes:
PCULs from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021.
Detected results are shown in **bold.**
Detections above the groundwater PCUL level are shown in **bold and highlighted in gray.**
B&V = Black & Veatch.
cDCE = cis-1,2-Dichloroethene.
DOF = Dalton, Olmsted & Fuglevand, Inc.
DRO = Diesel-range organics.
(duplicate) = field duplicate.
GeoE = GeoEngineers Inc.
GRO = Gasoline-range organics.
HC = Hart Crowser.
ORO = Oil-range organics.
PCE = Perchloroethylene (Tetrachloroethene).
ROW = right-of-way.
SES = SES Strategies, Inc.
TCE = Trichloroethene.
tDCE = trans-1,2-Dichloroethene.
VC = Vinyl chloride.
WW = Windward.
Well screen elevations indicated below Sample Location in parentheses.
(--) = unknown screen elevation.

Laboratory and Results Notes:
Petroleum hydrocarbons analyzed by EPA Method 418.1, NWTPH-HCID, or NWTPH-Gx, NWTPH-Dx, or 8015-M.
VOCs analyzed by EPA Method 601, 8010S, 8015, 8020, 8021B, 8240, 8260B, 8260C, or 8260D, or by Purge and Trap Gas Chromatogram/Mass Spectrometry.
– = Not analyzed or results not available.
E = Estimated value. The reported range exceeds the calibration range of the analysis.
f = Analyte was detected in the associated method blank. Analyte concentration in the sample is greater than 10x the concentration found in the method blank.
g = Estimated value. The reported range exceeds the calibration range of the analysis.
ht = The analysis was performed outside the method the method or client-specified holding time requirement.
J = The identification of the analyte is acceptable; the reported value is an estimate.
J+ = The result is an estimated quantity, but the result may be biased high.
J- = The result is an estimated quantity, but the result may be biased low.
ND = Not detected at a concentration exceeding laboratory reporting limit; detection limit not provided.
pr = The sample was received with incorrect preservation. The value reported should be considered an estimate.
U = Not detected at or above the laboratory method detection limit (MDL).
qp = Hydrocarbon result partly due to individual peak(s) in quantitation range.
x = The sample chromatographic pattern does not resemble the fuel standard used for quantitation.
y = The GRO result in the sample is due to a pattern of peaks that is consistent with the chlorinated volatiles detected by the 8260C analysis.
z = No/low level gasoline/petroleum detection; result is likely elevated due to high detections of CVOCs.
Groundwater statistics are for data collected during the Remediation Investigation, 2017-2021.
Groundwater statistics for GRO exclude "z" qualified data.

Table G-8

Groundwater Petroleum Hydrocarbons and CVOCs in Intermediate B Zone Wells
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																					
					GRO		DRO		ORO		DRO+ORO		Benzene		Toluene		Ethylbenzene		Total Xylenes		PCE		TCE		cDCE		tDCE		VC	
		Preliminary Cleanup Level			**800**		**500**		**500**		**500**		**5.0**		**640**		**700**		**1,600**		**5.0**		**4.0**		**16**		**100**		**0.29**	
BB-10	Dexter Ave North ROW	11/13/97	B&V	Bailer	250	U	630	U	630	U	630	U	ND		ND		ND		ND		ND		ND		ND		ND	
BB-13	Westlake Ave North ROW	06/20/05	B&V	Bailer	250	U	630	U	630	U	630	U	ND		ND		ND		ND		ND		ND		**2.6**		ND		**1.1**	
(--)		05/02/10	SES	Peristaltic	–		–		–		–		–		–		–		–		1	U	1	U	1	U	1	U	0.2	U
		Decommissioned Prior to 2017																												
BB-14	North Valley St ROW	06/20/05	B&V	Bailer	300	U	630	U	630	U	630	U	–		–		–		–		–		–		–		–		–	
(--)		Decommissioned Prior to 2017																												
FMW-141	Alley E of Seattle Roy Aloha Shops	07/26/19	Farallon	Unknown	–		–		–		–		–		–		–		–		30	U	**2,800**		**6,200**		30	U	**820**	
(-12.1 to -22.1)		10/30/19	PES	Peristaltic	–		–		–		–		**0.230**	**J**	0.412	U	0.158	U	0.316	U	0.199	U	**2.18**	**J**	**1,200**	**J**	**7.13**	**J**	**1,760**	
(duplicate)		10/30/19	PES	Peristaltic	–		–		–		–		**0.212**	**J**	0.412	U	0.158	U	0.316	U	0.199	U	**12.7**	**J**	**2,250**	**J**	**10.5**	**J**	**1,710**	
		11/11/19	Farallon	Unknown	–		–		–		–		–		–		–		–		20	U	20	U	**3,500**		20	U	**2,900**	
		01/14/20	PES	Bladder	–		–		–		–		0.448	U	2.06	U	0.790	U	1.58	U	0.995	U	**2.91**		**414**		**1.98**	**J**	**532**	
(split)		01/14/20	Farallon	Bladder	–		–		–		–		–		–		–		–		4.0	U	4.0	U	**250**		4.0	U	**380**	
		02/17/20	Farallon	Unknown	–		–		–		–		–		–		–		–		2.0	U	2.0	U	**280**		2.0	U	**240**	
		03/24/20	Farallon	Unknown	–		–		–		–		–		–		–		–		10	U	10	U	**1,200**		10	U	**820**	
		04/27/20	Farallon	Unknown	–		–		–		–		–		–		–		–		2.0	U	**6.5**		**440**				**490**	
		04/28/20	PES	Bladder	–		–		–		–		0.471	U	1.39	U	0.685	U	0.870	U	1.50	U	**3.08**		**1,300**		**4.62**		**468**	
		05/19/20	Farallon	Unknown	–		–		–		–		–		–		–		–		20	U	20	U	**2,400**		20	U	**910**	
		07/22/20	PES	Bladder	–		–		–		–		0.320	U	1.00	U	0.424	U	3.82	U	0.560	U	**2.30**		**790**		**3.19**	**J**	**561**	
		07/28/20	Farallon	Unknown	–		–		–		–		–		–		–		–		10	U	10	U	**8,100**		10	U	**780**	
		09/17/20	Farallon	Unknown	–		–		–		–		–		–		–		–		4.0	U	4.0	U	**600**		4.0	U	**620**	
		11/02/20	PES	Bladder	–		–		–		–		**0.0620**		**0.430**		0.0212	U	0.191	U	0.0280	U	**0.766**		**276**		**1.31**		**489**	
		12/03/20	Farallon	Unknown	–		–		–		–		–		–		–		–		1.0	U	1.0	U	**68**		1.0	U	**190**	
		02/10/21	Farallon	Unknown	–		–		–		–		–		–		–		–		1.0	U	1.0	U	**120**		1.0	U	**180**	
		05/03/21	PES	Peristaltic	–		–		–		–		0.0160	U	0.0500	U	0.0800	U	**0.508**		0.0280	U	**0.560**		**5.41**		0.0572	U	**0.218**	
HMW-1IB	Seattle DOT Mercer Parcels,	03/25/19	HC	Peristaltic	100	U	200	U	500	U	500	U	1.0	U	1.0	U	1.0	U	1.0	U	**20**		**6.7**		**22**		1.0	U	0.2	U
(-16.0 to -26.0)	NE quadrant	03/10/20	HC	Unknown	100	U	60	U	300	U	300	U	0.20	U	0.20	U	0.20	U	0.40	U	**13**		**5.6**		**16**		0.20	U	0.20	U
HMW-2IB	Seattle DOT Mercer Parcels,	03/25/19	HC	Peristaltic	100	U	200	U	500	U	500	U	1.0	U	**3.4**		1.0	U	1.0	U	1.0	U	1.0	U	1.0	U	1.0	U	0.2	U
(-5.4 to -15.4)	NE quadrant	03/12/20	HC	Submersible	100	U	51	U	260	U	260	U	0.20	U	0.20	U	0.20	U	0.40	U	**0.38**		0.20	U	**0.59**		0.20	U	0.20	U
HMW-4IA	Seattle DOT Mercer Parcels,	03/25/19	HC	Peristaltic	100	U	200	U	500	U	500	U	1.0	U	1.0	U	1.0	U	1.0	U	1.0	U	1.0	U	1.0	U	1.0	U	**3.6**	
(8.7 to -1.3)	SW quadrant	03/10/20	HC	Submersible	100	U	50	U	250	U	250	U	0.20	U	0.20	U	0.20	U	0.40	U	0.20	U	0.20	U	0.20	U	0.20	U	**0.41**	
HMW-5IB	Seattle DOT Mercer Parcels,	03/17/20	HC	Submersible	100	U	50	U	250	U	250	U	0.20	U	0.20	U	0.20	U	0.40	U	0.20	U	0.20	U	0.20	U	0.20	U	0.20	U
(8.7 to -1.3)	SW quadrant																													
HMW-6IB	Seattle DOT Mercer Parcels,	03/13/20	HC	Submersible	100	U	**83**	**J**	250	U	**83**	**J**	0.20	U	0.20	U	0.20	U	0.40	U	0.20	U	0.20	U	0.20	U	0.20	U	0.20	U
(8.7 to -1.3)	SW quadrant																													
HMW-7IB	Seattle DOT Mercer Parcels,	03/12/20	HC	Submersible	100	U	52	U	260	U	260	U	0.20	U	0.20	U	0.20	U	0.40	U	0.20	U	0.20	U	0.20	U	0.20	U	0.20	U
(9.0 to -1.0)	SW quadrant																													
HMW-8IB	Seattle DOT Mercer Parcels,	03/11/20	HC	Submersible	100	U	50	U	250	U	250	U	0.20	U	**0.22**		0.20	U	0.40	U	0.20	U	0.20	U	0.20	U	0.20	U	0.20	U
(7.5 to -2.5)	SW quadrant																													
HMW-9IB	Seattle DOT Mercer Parcels,	03/19/20	HC	Unknown	**580**	**J**	**60**	**J**	250	U	**60**	**J**	0.20	U	**0.23**		0.20	U	0.40	U	**660**		**420**		**9,100**		**8.3**		**1,900**	
(-1.6 to -11.6)	SW quadrant	01/26/21	PES	Bladder	–		–		–		–		**0.0760**		**0.590**		**0.218**		**1.21**		**32.1**	**J+**	**112**		**3,360**		**4.24**	**J+**	**1,400**	
		06/02/21	PES	Bladder	–		–		–		–		1.60	U	5.00	U	2.12	U	19.1	U	**16.2**		**81.6**		**3,060**		**6.30**	**J**	**1,230**	

Table G-8

Groundwater Petroleum Hydrocarbons and CVOCs in Intermediate B Zone Wells
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																					
					GRO		DRO		ORO		DRO+ORO		Benzene		Toluene		Ethylbenzene		Total Xylenes		PCE		TCE		cDCE		tDCE		VC	
Preliminary Cleanup Level					**800**		**500**		**500**		**500**		**5.0**		**640**		**700**		**1,600**		**5.0**		**4.0**		**16**		**100**		**0.29**	
HMW-11IB (-5.2 to -15.2)	Seattle DOT Mercer Parcels, SE quadrant	03/16/20	HC	Submersible	100	U	**74**	**J**	250	U	**74**	**J**	0.20	U	0.20	U	0.20	U	0.40	U	**6.9**		**2.5**		**3.6**		0.20	U	0.20	U
HMW-15IB (-5.1 to -14.1)	Seattle DOT Mercer Parcels, SW quadrant	09/16/20	HC	Unknown	100	U	50	U	–		50	U	0.20	U	0.20	U	0.20	U	0.40	U	0.20	U	0.20	U	0.20	U	0.20	U	0.20	U
HMW-16IB (2.0 to -8.0)	Seattle DOT Mercer Parcels, NW quadrant	09/18/20	HC	Unknown	100	U	**210**		–		**210**		0.20	U	0.20	U	0.20	U	0.40	U	0.20	U	0.20	U	**3.3**		0.20	U	**15**	
MW111 (-33.5 to -43.5)	Alley E of Seattle Roy Aloha Shops	12/21/12	SES	Bladder	–		–		–		–		–		–		–		–		**110**		**32**		**37**		1	U	**1.8**	
		12/17/13	SES	Peristaltic	–		–		–		–		0.35	U	1	U	1	U	3	U	1	U	1	U	**4.7**		1	U	**17**	
		04/22/15	SES	Peristaltic	–		–		–		–		–		–		–		–		1	U	1	U	**1.7**		1	U	**18**	
		06/17/15	SES	Peristaltic	–		–		–		–		–		–		–		–		1	U	1	U	**1.5**		1	U	**20**	
		10/20/15	SES	Peristaltic	–		–		–		–		–		–		–		–		1	U	1	U	1	U	1	U	**8.2**	
		02/02/16	SES	Peristaltic	–		–		–		–		–		–		–		–		1	U	1	U	**2.3**		1	U	**5.8**	
		03/23/17	PES	Peristaltic	–		–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**1.40**		0.152	U	**5.22**	
		06/14/17	PES	Bladder	–		–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**0.408**	**J**	**1.24**		0.152	U	**3.22**	
		04/06/18	PES	Peristaltic	–		–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**0.618**		0.153	U	**16.5**		0.152	U	**121**	
		01/23/19	PES	Peristaltic	–		–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**0.492**	**J**	**0.176**	**J**	**1.70**		0.152	U	**37.6**	
		04/22/19	PES	Peristaltic	–		–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**3.18**		0.152	U	**19.5**	**J**
		07/15/19	PES	Peristaltic	–		–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.596**		0.152	U	**15.0**	
		10/14/19	PES	Peristaltic	–		–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.413**	**J**	0.152	U	**8.63**	
		01/16/20	PES	Bladder	–		–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**5.08**		0.152	U	**34.0**	
		04/23/20	PES	Bladder	–		–		–		–		0.0941	U	0.278	U	0.137	U	0.174	U	0.300	U	0.190	U	**24.3**		0.149	U	**112**	
		07/06/20	PES	Bladder	–		–		–		–		**0.0210**	**J**	**2.63**		0.0212	U	0.191	U	0.0280	U	**0.140**		**27.1**		0.0572	U	**116**	
		11/02/20	PES	Bladder	–		–		–		–		**0.0230**	**J**	**0.225**		0.0212	U	0.191	U	0.0280	U	**0.161**		**56.2**		0.0572	U	**118**	
		02/09/21	PES	Bladder	–		–		–		–		**0.0420**		**0.955**		**0.103**		**0.606**		**0.320**	**J**	0.0800	U	**14.5**		**0.0720**	**J**	**112**	
		05/03/21	PES	Bladder	–		–		–		–		**0.0430**		**0.880**		0.174	U	**1.21**		0.0280	U	**0.0790**		**5.80**		0.0572	U	**44.3**	
MW112 (-17.2 to -27.2)	Dexter Ave N ROW, W side	01/00/00	SES	Bladder	–		–		–		–		–		–		–		–		1	U	1	U	1	U	1	U	0.2	U
		12/26/13	SES	Bladder	–		–		–		–		0.35	U	1	U	1	U	3	U	1	U	1	U	1	U	1	U	0.2	U
		03/22/17	PES	Bladder	–		–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		06/16/17	PES	Bladder	–		–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		04/12/18	PES	Bladder	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		12/21/18	PES	Bladder	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		04/22/19	PES	Bladder	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	UJ
		07/16/19	PES	Bladder	31.7	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		10/21/19	PES	Bladder	**96.6**	**J**	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		01/24/20	PES	Bladder	31.6	U	–		–		–		0.0896	U	**1.24**		0.158	U	0.316	U	**0.248**	**J**	0.153	U	0.0933	U	0.152	U	0.118	U
		05/07/20	PES	Bladder	31.6	U	–		–		–		0.0941	U	**0.390**	**J**	0.137	U	0.174	U	0.300	U	0.190	U	0.126	U	0.149	U	0.234	U
		07/27/20	PES	Bladder	–		–		–		–		0.0160	U	**1.93**		**0.0221**	**J**	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
		11/17/20	PES	Bladder	–		–		–		–		**0.0270**	**J**	**0.322**		0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
		02/11/21	PES	Bladder	–		–		–		–		**0.0200**	**J**	**0.112**	**J**	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
		05/14/21	PES	Bladder	–		–		–		–		0.0160	U	0.0600	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
MW126 (-54.1 to -64.1)	Alley E of Seattle Roy Aloha Shops	01/03/14	SES	Peristaltic	–		–		–		–		0.35	U	1	U	1	U	3	U	1	U	1	U	1	U	1	U	0.2	U
		03/28/17	PES	Peristaltic	–		–		–		–		**0.148**	**J**	0.563	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.283**	**J**	0.152	U	0.118	U
		06/15/17	PES	Bladder	–		–		–		–		0.0896	U	0.412	U	**0.179**	**J**	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		04/06/18	PES	Peristaltic	–		–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U

Table G-8

Groundwater Petroleum Hydrocarbons and CVOCs in Intermediate B Zone Wells
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																	
					GRO		DRO	ORO	DRO+ORO	Benzene		Toluene		Ethylbenzene		Total Xylenes		PCE		TCE		cDCE		tDCE		VC	
Preliminary Cleanup Level					**800**		**500**	**500**	**500**	**5.0**		**640**		**700**		**1,600**		**5.0**		**4.0**		**16**		**100**		**0.29**	
MW126		01/22/19	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
(continued)		04/29/19	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	UJ
		07/18/19	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		10/15/19	PES	Bladder	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
(duplicate)		10/15/19	PES	Bladder	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		01/14/20	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	**0.162**	**J**	**0.441**	**J**	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		04/09/20	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		07/24/20	PES	Peristaltic	–		–	–	–	0.0160	U	0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
		11/09/20	PES	Peristaltic	–		–	–	–	**0.0210**	**J**	0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
		02/10/21	PES	Peristaltic	–		–	–	–	0.0160	U	0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
		05/04/21	PES	Peristaltic	–		–	–	–	0.0160	U	0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
(duplicate)		05/04/21	PES	Peristaltic	–		–	–	–	0.0160	U	0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
MW130	Property, NW quadrant	03/03/16	SES	Bladder	–		–	–	–	–		–		–		–		**6,200**		**430**		**300**		1	U	**38**	
(-30.9 to -40.9)		03/29/17	PES	Bladder	**8,890**	**zJ+**	–	–	–	1.79	U	8.24	U	3.16	U	6.32	U	**721**		**830**		**7,880**		**39.3**		**186**	
		06/30/17	PES	Bladder	**10,300**	**zJ+**	–	–	–	0.896	U	4.12	U	1.58	U	3.16	U	**6,760**	**J**	**4,020**		**20,100**		**55.6**		**597**	
(duplicate)		06/30/17	PES	Bladder	**15,000**	**zJ+**	–	–	–	0.896	U	4.12	U	1.58	U	3.16	U	**11,100**	**J**	**5,310**		**21,300**		**57.3**		**549**	
		05/21/18	PES	Bladder	**19,700**	**zJ+**	–	–	–	**0.403**	**J**	**1.37**		**0.227**	**J**	**1.12**	**J**	**13,500**		**7,400**		**29,500**		**114**		**1,650**	
		12/17/18	PES	Bladder	**16,400**	**zJ+**	–	–	–	4.48	U	20.6	U	7.90	U	15.8	U	**9,650**		**3,220**		**26,400**		**83.5**		**1,420**	
		01/31/19	PES	Bladder	**22,400**	**zJ+**	–	–	–	**0.377**	**J**	**1.51**	**J+**	**0.279**	**J**	**1.22**	**J**	**23,700**		**4,640**		**27,700**		**107**		**1,740**	
		Decommissioned March 2019																									
MW-132	Property, SE quadrant	09/25/17	PES	Bladder	95.9	U	–	–	–	0.448	U	2.06	U	0.790	U	1.58	U	0.995	U	**1.95**	**J**	**196**		0.760	U	**1.76**	**J**
(-29.9 to -39.9)		04/26/18	PES	Bladder	**2,630**	**zJ+**	–	–	–	**0.422**	**J**	0.412	U	0.158	U	0.32	U	**2,830**		**840**		**3,300**		**16.3**		**10.2**	
		10/25/18	PES	Peristaltic	48.3	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**3.53**		**0.750**		**12.1**		**0.254**	**J**	**158**	
		12/13/18	PES	Peristaltic	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.995	U	0.765	U	**39.8**		**0.497**	**J**	**199**	
		01/31/19	PES	Peristaltic	**104**	**zJ+**	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**22.9**		**1.95**		**108**		**0.506**		**269**	
		03/11/19	PES	Peristaltic	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**7.03**		**1.22**		**22.8**		**0.302**	**J**	**57.3**	
		Decommissioned March 2019																									
MW-134	Property, NE quadrant	09/22/17	PES	Bladder	–		–	–	–	0.448	U	2.06	U	0.790	U	1.58	U	0.995	U	0.765	U	**86.2**		0.760	U	**229**	
(-38.6 to -48.6)		04/16/18	PES	Peristaltic	42.1	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**1.49**		0.153	U	**0.287**	**J**	0.152	U	**68.6**	
		10/25/18	PES	Bladder	38.2	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	**20.9**	
		12/12/18	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.259**	**J**	0.152	U	**21.9**	
		01/28/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.609**		0.152	U	**32.4**	
		03/12/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.550**		0.152	U	**17.7**	
		Decommissioned March 2019																									
MW-135	Property, NE quadrant	09/25/17	PES	Bladder	**10,900**	**zJ+**	–	–	–	8.96	U	41.2	U	15.8	U	31.6	U	**10,400**		**2,480**		**16,100**		15.2	U	**82.0**	**J**
(-30.9 to -40.9)		04/25/18	PES	Peristaltic	**347,000**	**zJ+**	–	–	–	**0.434**	**J**	**3.09**		**0.484**	**J**	**2.61**		**75,800**		**7,890**		**27,700**		**30.7**		**989**	
		10/25/18	PES	Peristaltic	**31,800**	**zJ+**	–	–	–	2.24	U	10.3	U	3.95	U	7.90	U	**45,900**		**8,330**		**40,400**		**54.4**		**1,170**	
		12/13/18	PES	Peristaltic	**80,000**	**zJ+**	–	–	–	4.48	U	20.6	U	7.90	U	15.8	U	**97,200**		**11,000**		**42,100**		**66.6**		**1,380**	
		01/31/19	PES	Bladder	**42,700**	**zJ+**	–	–	–	**0.695**	**J**	**5.12**	**J+**	**0.571**	**J**	**3.43**	**J**	**56,500**		**9,530**		**37,400**		**68.6**		**1,090**	
		03/13/19	PES	Bladder	**32,700**	**zJ+**	–	–	–	**0.496**	**J**	**2.43**		**0.329**	**J**	**1.90**		**57,300**		**8,150**		**37,200**		**74.3**		**706**	
		Decommissioned March 2019																									
MW-136	Property, SW quadrant	09/25/17	PES	Bladder	55.2	U	–	–	–	**0.332**	**J**	0.412	U	0.158	U	0.316	U	**15.4**		**10.7**		**18.7**		0.152	U	0.118	U
(-32.7 to -42.7)		04/16/18	PES	Submersible	**256**		–	–	–	**0.260**	**J**	**1.83**		**4.83**		**25.9**		**2.59**		**0.365**	**J**	**4.73**		0.152	U	**8.57**	
		10/29/18	PES	Bladder	31.9	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**0.177**	**J**	**1.44**		0.152	U	**0.236**	**J**
		12/13/18	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**0.237**	**J**	**0.962**		0.152	U	0.118	U

Table G-8

Groundwater Petroleum Hydrocarbons and CVOCs in Intermediate B Zone Wells
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																	
					GRO		DRO	ORO	DRO+ORO	Benzene		Toluene		Ethylbenzene		Total Xylenes		PCE		TCE		cDCE		tDCE		VC	
		Preliminary Cleanup Level			800		500	500	500	5.0		640		700		1,600		5.0		4.0		16		100		0.29	
MW-136 (continued) (duplicate)		02/01/19	PES	Bladder	44.5	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**1.26**		0.293	U	**0.851**		0.152	U	**0.186**	**J**
		03/12/19	PES	Peristaltic	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**0.206**	**J**	0.153	U	**0.330**	**J**	0.152	U	0.118	U
		03/12/19	PES	Peristaltic	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**0.262**	**J**	0.153	U	**0.378**	**J**	0.152	U	0.118	U
		Decommissioned March 2019																								
MW-139 (-30.2 to -40.2)	Property, SE quadrant	09/25/17	PES	Bladder	62.2	U	–	–	–	0.0896	U	**0.516**		0.158	U	0.316	U	0.199	U	0.153	U	**1.42**		0.152	U	**0.246**	**J**
		04/25/18	PES	Peristaltic	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.175**	**J**	0.152	U	0.118	U
		10/25/18	PES	Peristaltic	47.4	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**1.29**		**0.282**	**J**	0.454	U	0.152	U	0.118	U
		12/12/18	PES	Peristaltic	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.216**	**J**	0.152	U	0.118	U
		01/28/19	PES	Peristaltic	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		03/11/19	PES	Peristaltic	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.187**	**J**	0.152	U	**5.77**	
		Decommissioned March 2019																								
MW-143 (-27.7 to -37.76)	8th Ave N ROW, E side	04/30/18	PES	Peristaltic	**154**		–	–	–	**0.244**	**J**	**0.797**		**0.212**	**J**	**1.08**	**J**	0.199	U	0.153	U	**129**		**0.512**		**193**	
		01/29/19	PES	Bladder	31.6	U	–	–	–	**0.141**	**J**	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.241**	**J**	0.152	U	0.118	U
		04/24/19	PES	Peristaltic	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	UJ
		07/19/19	PES	Bladder	**31.6**		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.309**	**J**	0.152	U	0.118	U
		10/16/19	PES	Bladder	**2,000**	**zJ+**	–	–	–	**0.211**	**J**	0.412	U	0.158	U	0.316	U	**2.35**		**28.0**		**2,510**		**11.0**		**1,180**	
		01/22/20	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.171**	**J**	0.152	U	**0.254**	**J**
		04/24/20	PES	Bladder	88.2	U	–	–	–	0.0941	U	0.278	U	0.137	U	0.174	U	0.300	U	0.190	U	**0.135**	**J**	0.149	U	0.234	U
		07/29/20	PES	Bladder	–		–	–	–	**0.0401**		**1.63**		**0.0229**	**J**	0.191	U	**0.0307**	**J**	**0.0167**	**J**	**0.0754**	**J**	0.0572	U	0.0273	U
		11/24/20	PES	Bladder	–		–	–	–	**0.584**		**0.203**		0.0610	U	**0.474**		0.0280	U	**9.64**		**113**		**0.633**		**26.0**	
		02/08/21	PES	Peristaltic	–		–	–	–	0.800	U	**3.00**	**J**	1.06	U	9.55	U	1.40	U	0.800	U	**3,260**		**14.1**		**514**	**J**
		05/19/21	PES	Bladder	–		–	–	–	0.800	U	2.50	U	1.06	U	9.55	U	1.40	U	0.800	U	**4,240**		**21.6**		**1,200**	
MW-145 (-26.1 to -36.1)	8th Ave N ROW, E side	04/27/18	PES	Bladder	52.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**0.212**	**J**	**2.29**		0.152	U	**3.88**	
		01/29/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.316**	**J**	0.152	U	**0.335**	**J**
		04/26/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	**0.392**	**J**
		Decommissioned December 2019																								
MW-145R (-27.2 to -37.2)	8th Ave N ROW, E side	12/16/19	PES	Bladder	**140**	**zJ+**	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.193**	**J**	0.152	U	0.118	U
		01/21/20	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.230**	**J**	0.152	U	0.118	U
		04/02/20	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.293**	**J**	0.152	U	0.118	U
		08/03/20	PES	Bladder	–		–	–	–	**0.0190**	**J**	**1.45**		**0.0460**	**J**	0.191	U	**0.0570**	**J**	**0.0270**	**J**	**0.228**		0.0572	UJ	0.0273	U
		11/23/20	PES	Bladder	–		–	–	–	0.0160	U	0.0570	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	**0.151**		0.0572	U	0.0273	U
		02/05/21	PES	Peristaltic	–		–	–	–	**0.159**		**2.79**		**0.300**		**1.65**		0.0280	U	0.0160	U	**0.0680**	**J**	0.0572	U	0.0273	U
		05/12/21	PES	Bladder	–		–	–	–	0.0160	U	0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	**0.0760**	**J**	0.0572	U	0.0273	U
MW-147 (-17.6 to -27.6)	Roy St ROW, S side	05/01/18	PES	Bladder	**484**	**zJ+**	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**19.8**		**83.4**		**399**		**2.09**		**1,150**	
		01/22/19	PES	Bladder	**663**	**zJ+**	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**98.2**		**179**		**1,230**		**2.88**		**738**	
		04/23/19	PES	Bladder	**139**	**zJ+**	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	UJ	0.199	U	**5.13**		**322**		**1.47**		**499**	
		07/18/19	PES	Bladder	**175**	**zJ+**	–	–	–	0.0896	U	0.412	U	3.16	U	6.32	U	0.199	U	**4.79**		**219**		**2.49**		**446**	
(duplicate)		07/18/19	PES	Bladder	**170**	**zJ+**	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**4.72**		**286**		**2.12**		**425**	
		10/14/19	PES	Bladder	**513**	**zJ+**	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**3.38**		**597**		**2.91**		**1,410**	
		01/24/20	PES	Bladder	**1,200**	**zJ+**	–	–	–	2.24	U	10.3	U	3.95	U	7.90	U	4.98	U	**4.63**	**J**	**1,100**		3.80	U	**1,340**	
		04/29/20	PES	Bladder	**1,150**	**zJ+**	–	–	–	2.35	U	6.95	U	3.43	U	4.35	U	7.50	U	**5.10**	**J**	**2,410**		**3.90**	**J**	**3,470**	
		07/09/20	PES	Bladder	–		–	–	–	**0.0890**		**3.52**		0.0212	U	0.191	U	**4.29**		**12.4**		**2,220**		**11.9**		**6,970**	
		11/10/20	PES	Bladder	**2,930**	**zJ+**	–	–	–	1.60	U	5.00	U	2.12	U	19.1	U	2.80	U	**4.73**		**3,740**		**9.23**	**J**	**7,290**	
(split)		11/10/20	HC	Bladder	100	U	50	U 250	U 250	U 170	U	500	U	500	U	1,500	U	500	U	500	U	**3,500**		500	U	**7,400**	
		02/09/21	PES	Bladder	–		–	–	–	0.800	U	2.50	U	1.06	U	9.55	U	1.40	U	**9.90**		**1,750**		**7.80**	**J**	**3,450**	**J**
		05/04/21	PES	Bladder	–		–	–	–	1.60	U	5.00	U	2.12	U	19.1	U	2.80	U	**3.00**	**J**	**1,300**		5.72	U	**2,200**	

Table G-8

Groundwater Petroleum Hydrocarbons and CVOCs in Intermediate B Zone Wells
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																	
					GRO	DRO	ORO	DRO+ORO	Benzene	Toluene	Ethylbenzene	Total Xylenes	PCE	TCE	cDCE	tDCE	VC					
		Preliminary Cleanup Level			800	500	500	500	5.0	640	700	1,600	5.0	4.0	16	100	0.29					
MW-148	Roy St ROW, S side	05/01/18	PES	Bladder	31.6 U	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	0.0933 U	0.152 U	0.118 U					
(duplicate)		05/01/18	PES	Bladder	31.6 U	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	**0.216 J**	0.152 U	0.118 U					
(-25.7 to -35.7)		01/23/19	PES	Bladder	31.6 U	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	**1.24**	**0.347 J**	0.0933 U	0.152 U	0.118 U					
		04/26/19	PES	Bladder	31.6 U	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	0.0933 U	0.152 U	**0.277 J**					
		07/22/19	PES	Bladder	31.6 U	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.415 U	0.153 U	0.0933 U	0.152 U	**0.253 J**					
		10/16/19	PES	Bladder	31.6 U	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	0.0933 U	0.152 U	**0.463 J**					
		01/20/20	PES	Bladder	31.6 U	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	**0.163 J**	0.0933 U	0.152 U	**0.305 J**					
		04/30/20	PES	Bladder	**36.8 J**	–	–	–	0.0941 U	0.278 U	0.137 U	0.174 U	0.300 U	0.190 U	0.126 U	0.149 U	0.234 U					
		07/15/20	PES	Bladder	–	–	–	–	0.0160 U	**1.32**	0.0212 U	0.191 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	**0.224**					
		11/11/20	PES	Bladder	–	–	–	–	0.0160 U	**0.310 J**	0.0212 U	0.191 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U					
MW-150	Property, NE quadrant	04/10/18	PES	Peristaltic	**7,040 zJ+**	–	–	–	22.4 U	**1.63**	39.5 U	79.0 U	**2,500**	**3,200**	**9,710**	**21.1**	**766**					
(-13.3 to -23.3)		10/25/18	PES	Peristaltic	**14,600 zJ+**	–	–	–	**0.413 J**	**2.53**	**0.226 J**	**1.13 J**	**15,200**	**8,800**	**17,700**	**49.7**	**1,430**					
		12/12/18	PES	Peristaltic	**17,500 zJ+**	–	–	–	**0.429 J**	**1.04**	0.158 U	0.316 U	**75.6**	**533**	**32,800**	**242**	**2,040**					
		01/29/19	PES	Peristaltic	**11,900 zJ+**	–	–	–	8.96 U	41.2 U	15.8 U	31.6 U	**303**	**548**	**18,100**	**36.7 J**	**1,370**					
		03/13/19	PES	Peristaltic	**7,540 zJ+**	–	–	–	**0.165 J**	0.412 U	**0.185 J**	0.316 U	**36.0**	**262**	**15,000**	**50.5**	**479**					
		Decommissioned March 2019																				
MW-152	Property, SW quadrant	04/10/18	PES	Peristaltic	**40,600 zJ+**	–	–	–	224 U	8.24 U	**3.27 J**	790 U	**67,300**	**6,550**	**35,300**	**42.1**	**3,660**					
(-10.2 to -20.2)		10/26/18	PES	Peristaltic	**36,700 zJ+**	–	–	–	4.48 U	20.6 U	7.90 U	15.8 U	**1,960**	**3,150**	**73,000**	**109**	**4,510**					
		12/14/18	PES	Peristaltic	**47,300 zJ+**	–	–	–	2.24 U	10.3 U	3.95 U	7.90 U	**23,600 J+**	**6,870 J+**	**77,100 J+**	**134 J+**	**7,830 J+**					
		01/31/19	PES	Peristaltic	**44,300 zJ+**	–	–	–	**0.416 J**	**2.61 J+**	**0.342 J**	**2.10**	**38,300**	**3,920**	**58,400**	**101**	**9,600**					
		03/12/19	PES	Peristaltic	**55,900 zJ+**	–	–	–	2.24 U	10.3 U	3.95 U	7.90 U	398 U	**18,700**	**127,000**	**781**	**11,000**					
		Decommissioned March 2019																				
MW-157	8th Ave N ROW, E side	04/26/18	PES	Peristaltic	**65.7 J**	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	**0.950**	**0.240 J**	**10.4**	**0.246 J**	**104**					
(-28.3 to -38.2)		01/24/19	PES	Peristaltic	**1,870 zJ+**	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	**1.65**	**4,250**	**14.2**	**674**					
		04/24/19	PES	Peristaltic	**3,210 zJ+**	–	–	–	**0.254 J**	0.412 U	0.158 U	0.316 U	9.95 U	**8.52 J**	**3,550**	**15.9**	**622**					
		07/22/19	PES	Bladder	**3,880 zJ+**	–	–	–	**0.327 J**	0.412 U	0.158 U	0.316 U	19.9 U	**27.6**	**4,530**	**18.4**	**666**					
		10/16/19	PES	Bladder	31.6 U	–	–	–	0.0896 U	**0.561**	0.158 U	0.316 U	0.199 U	0.153 U	**0.188 J**	0.152 U	0.118 U					
		01/20/20	PES	Bladder	**1,650 zJ+**	–	–	–	**0.308 J**	0.412 U	0.158 U	0.316 U	**39.4**	**109**	**2,040**	**8.95**	**941**					
		04/24/20	PES	Bladder	**756 zJ+**	–	–	–	1.88 U	5.56 U	2.74 U	3.48 U	6.00 U	3.80 U	**1,040**	**8.86 J**	**980**					
		07/15/20	PES	Bladder	–	–	–	–	**0.480 J**	1.00 U	0.424 U	3.82 U	0.560 U	**3.06**	**888**	**7.20**	**668**					
		11/23/20	PES	Bladder	–	–	–	–	0.740 U	1.00 U	0.424 U	3.82 U	**3.04**	**24.7**	**2,770**	**9.98**	**528**					
MW-190	Valley St ROW, S side	10/14/19	PES	Bladder	31.6 U	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	**7.78**	0.152 U	**0.994**					
(-30.2 to -40.2)		01/23/20	PES	Bladder	31.6 U	–	–	–	**0.150 J**	**1.57**	0.158 U	**0.344 J**	0.199 U	0.153 U	**0.389 J**	0.152 U	0.118 U					
		04/02/20	PES	Bladder	31.6 U	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	**2.13**	0.152 U	**1.81**					
		08/04/20	PES	Bladder	–	–	–	–	**0.0270 J**	**2.09**	**0.0330 J**	0.191 U	0.0280 U	0.0160 U	**1.74**	0.0572 UJ	**3.77 J**					
		11/18/20	PES	Bladder	–	–	–	–	0.0160 U	**0.0820 J**	0.0212 U	0.191 U	0.0280 U	0.0160 U	**21.8**	0.0572 U	**64.9**					
		02/03/21	PES	Bladder	–	–	–	–	0.0160 U	**0.164 J**	**0.0450 J**	**0.252 J**	0.0280 U	0.0160 U	**12.5**	0.0572 U	**68.4**					
		05/14/21	PES	Bladder	–	–	–	–	0.0160 U	0.149 U	**0.0330 J**	**0.195 J**	0.0280 U	0.0160 U	**8.12**	0.0572 U	**32.2**					
MW-303	Dexter Ave N ROW,	10/21/19	PES	Submersible	**99.6 J**	–	–	–	0.0896 U	**1.63**	0.158 U	0.316 U	0.199 U	0.153 U	0.0933 U	0.152 U	0.118 U					
(-13.8 to -23.8)	E side	01/24/20	PES	Bladder	31.6 U	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	**0.313 J**	**0.153 J**	0.0933 U	0.152 U	0.118 U					
		05/07/20	PES	Bladder	**41.5 J**	–	–	–	0.0941 U	0.278 U	0.137 U	0.174 U	0.300 U	0.190 U	0.126 U	0.149 U	0.234 U					
		07/27/20	PES	Bladder	–	–	–	–	0.0160 U	**1.56**	**0.0263 J**	0.191 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U					
		11/17/20	PES	Bladder	–	–	–	–	0.0160 U	**0.0750 J**	0.0212 U	0.191 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U					
		05/18/21	PES	Bladder	–	–	–	–	0.0160 U	**0.240**	0.0212 U	0.191 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U					
MW-307	Roy St ROW, S side	10/11/19	PES	Bladder	31.6 U	–	–	–	0.0896 U	**1.05**	0.158 U	0.316 U	0.199 U	0.153 U	**0.935**	0.152 U	**0.289 J**					
(-12.4 to -22.4)		01/15/20	PES	Bladder	31.6 U	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	**0.172 J**	0.152 U	0.118 U					
		04/28/20	PES	Bladder	**146 zJ+**	–	–	–	**0.172 J**	**0.452 J**	0.137 U	0.174 U	0.300 U	0.190 U	0.126 U	0.149 U	0.234 U					

Table G-8

Groundwater Petroleum Hydrocarbons and CVOCs in Intermediate B Zone Wells
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)													
					GRO	DRO	ORO	DRO+ORO	Benzene	Toluene	Ethylbenzene	Total Xylenes	PCE	TCE	cDCE	tDCE	VC	
		Preliminary Cleanup Level			800	500	500	500	5.0	640	700	1,600	5.0	4.0	16	100	0.29	
MW-307 (continued)		07/29/20	PES	Bladder	–	–	–	–	**0.0211 J**	**0.780**	0.0212 U	0.191 U	**0.0492 J**	0.0160 U	0.0276 U	0.0572 U	0.0273 U	
		11/06/20	PES	Bladder	–	–	–	–	0.0160 U	**0.427**	0.0212 U	0.191 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U	
		05/18/21	PES	Bladder	–	–	–	–	0.0160 U	**0.272**	0.0212 U	0.191 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U	
MW-309 (-32.0 to -42.0)	Alley E of Seattle Roy Aloha Shops	10/14/19	PES	Peristaltic	–	–	–	–	**0.295 J**	**2.01**	0.158 U	0.316 U	**1.11**	**0.497 J**	**1.47**	0.152 U	**6.37**	
		01/16/20	PES	Peristaltic	–	–	–	–	**0.585**	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	**0.487 J**	0.152 U	**12.6**	
		04/08/20	PES	Peristaltic	–	–	–	–	**1.92**	0.412 U	**0.239 J**	0.316 U	0.199 U	0.153 U	**0.231 J**	0.152 U	**12.6**	
		07/06/20	PES	Peristaltic	–	–	–	–	**0.524**	0.0500 U	**0.0640 J**	0.191 U	**0.0930 J**	0.0160 U	**0.170**	0.0572 U	**16.0**	
		11/06/20	PES	Peristaltic	–	–	–	–	**0.473**	0.0500 U	**0.0388 J**	0.191 U	**0.0726 J**	0.0160 U	**0.187**	0.0572 U	**10.5**	
		05/04/21	PES	Peristaltic	–	–	–	–	**0.252**	0.0500 U	0.0212 U	0.191 U	**0.0370 J**	0.0160 U	**0.212**	0.0572 U	**13.1**	
MW-311 (-29.1 to -39.1)	Alley E of Seattle Roy Aloha Shops	10/10/19	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	**20.4**	**46.1**	**173**	**0.221 J**	**25.1**	
		01/14/20	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	**1.99**	**11.4**	**75.0**	**0.204 J**	**13.6**	
		04/23/20	PES	Bladder	–	–	–	–	0.0941 U	0.278 U	0.137 U	0.174 U	0.300 U	**0.624**	**45.8**	0.149 U	**10.9**	
		07/16/20	PES	Bladder	–	–	–	–	**0.0650**	**3.39**	0.0212 U	0.191 U	**0.0470 J**	**0.334**	**5.24**	**0.144 J**	**24.0**	
		11/04/20	PES	Bladder	–	–	–	–	**0.0287 J**	**0.578**	**0.0319 J**	0.191 U	**0.169**	**0.524**	**2.66**	**0.0593 J**	**13.5**	
		05/03/21	PES	Peristaltic	–	–	–	–	0.0160 U	0.0500 U	0.0510 U	**0.249 J**	**0.0660 J**	**0.361**	**0.981**	0.0572 U	**4.68**	
MW-314 (-28.0 to -38.0) (duplicate)	Alley E of Seattle Roy Aloha Shops	10/10/19	PES	Bladder	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	**26.1**	**106**	**491**	**1.63**	**43.6**	
		01/15/20	PES	Bladder	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	**22.7**	**98.3**	**596**	**2.12**	**17.9**	
		01/15/20	PES	Bladder	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	**19.8**	**88.5**	**569**	**1.85**	**17.9**	
		04/22/20	PES	Bladder	–	–	–	–	0.941 U	2.78 U	1.37 U	1.74 U	3.00 U	**229**	**3,190**	**14.8**	**410**	
		07/16/20	PES	Bladder	–	–	–	–	1.60 U	5.00 U	2.12 U	19.1 U	**4.20 J**	**313**	**4,020**	**22.3**	**442**	
		11/04/20	PES	Bladder	–	–	–	–	1.60 U	5.00 U	2.12 U	19.1 U	**13.2**	**807**	**4,240**	**16.4 J**	**360**	
		05/03/21	PES	Bladder	–	–	–	–	0.800 U	2.50 U	1.06 U	9.55 U	1.40 U	**54.5**	**977**	**3.15 J**	**42.9**	
MW-316 (-10.0 to -20.0)	Mercer St ROW, N side	10/02/19	PES	Bladder	–	–	–	–	0.0896 U	**0.570**	0.158 U	0.316 U	0.199 U	0.153 U	0.0933 U	0.152 U	0.118 U	
		01/16/20	PES	Bladder	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	0.153 U	0.0933 U	0.152 U	0.118 U	
		04/21/20	PES	Bladder	–	–	–	–	0.0941 U	0.278 U	0.137 U	0.174 U	0.300 U	0.190 U	0.126 U	0.149 U	0.234 U	
		07/24/20	PES	Bladder	–	–	–	–	**0.0250 J**	**0.362**	0.0212 U	0.191 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U	
		11/02/20	PES	Bladder	–	–	–	–	**0.0190 J**	**0.120 J**	0.0212 U	0.191 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U	
		05/17/21	PES	Bladder	–	–	–	–	0.0160 U	**0.220**	0.0212 U	0.191 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U	
MW-318 (-23.1 to -33.1)	9th Ave N ROW, W side	10/08/19	PES	Bladder	–	–	–	–	**5.75**	**0.495 J**	0.158 U	0.316 U	0.199 U	0.153 U	**6.52**	0.152 U	**8.65**	
		01/16/20	PES	Peristaltic	–	–	–	–	**25.4**	**0.519**	0.158 U	0.316 U	0.199 U	0.153 U	**9.86**	0.152 U	**31.0**	
		04/27/20	PES	Bladder	–	–	–	–	**22.6**	0.278 U	0.137 U	0.174 U	0.300 U	0.190 U	**2.08**	0.149 U	**3.84**	
		07/30/20	PES	Bladder	–	–	–	–	**5.79**	**0.117 J**	**0.0775 J**	0.191 U	0.0280 U	0.0160 U	**0.525 J**	0.0572 UJ	**0.941**	
		11/12/20	PES	Bladder	–	–	–	–	**4.20**	**0.224 J-**	0.0212 U	**0.229 J**	0.0280 U	0.0160 U	**0.499**	0.0572 U	**0.865 J+**	
		05/19/21	PES	Peristaltic	–	–	–	–	**3.97**	0.108 U	0.0212 U	**0.257 J**	0.0280 U	0.0160 U	**0.570**	0.0572 U	**1.56**	
MW-322 (-21.3 to -31.3)	9th Ave N ROW, W side	10/07/19	PES	Peristaltic	–	–	–	–	**7.12**	**0.612**	0.158 U	0.316 U	**0.699**	**21.0**	**497**	**1.17**	**268**	
		01/21/20	PES	Peristaltic	–	–	–	–	**7.41**	**0.955**	0.158 U	0.316 U	**0.218 J**	**8.62**	**2,740**	**6.06**	**221**	
		04/29/20	PES	Bladder	–	–	–	–	**15.5 J**	27.8 U	13.7 U	17.4 U	30.0 U	**661**	**1,510**	14.9 U	**280**	
		07/07/20	PES	Bladder	–	–	–	–	**28.8**	**0.970 J**	0.212 U	1.91 U	**117**	**494**	**547**	**3.91**	**123**	
		11/24/20	PES	Bladder	–	–	–	–	**23.9**	0.550 U	0.212 U	1.91 U	**3.35**	**70.9**	**257**	**1.35 J**	**41.2**	
		05/19/21	PES	Peristaltic	–	–	–	–	**22.4**	0.500 U	0.212 U	1.91 U	**8.80**	**259**	**496**	**2.41**	**43.0**	
MW-334 (-21.7 to -31.7)	900 Roy St, S end	04/24/20	PES	Bladder	–	–	–	–	0.0941 U	0.278 U	0.137 U	0.174 U	0.300 U	0.190 U	0.126 U	0.149 U	0.234 U	
		07/07/20	PES	Bladder	–	–	–	–	0.0160 U	**1.61**	0.0212 U	0.191 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U	

Table G-8

Groundwater Petroleum Hydrocarbons and CVOCs in Intermediate B Zone Wells
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)													
					GRO	DRO	ORO	DRO+ORO	Benzene	Toluene	Ethylbenzene	Total Xylenes	PCE	TCE	cDCE	tDCE	VC	
		Preliminary Cleanup Level			800	500	500	500	5.0	640	700	1,600	5.0	4.0	16	100	0.29	
MW-334		11/05/20	PES	Bladder	–	–	–	–	0.0160 U	**0.195 J**	0.0212 U	0.191 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U	
(continued)		05/13/21	PES	Peristaltic	–	–	–	–	0.0160 U	**0.143 J**	0.0212 U	0.191 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U	
MW-335	Mercer St ROW, N side	05/01/20	PES	Bladder	–	–	–	–	**0.113 J**	0.278 U	0.137 U	0.174 U	**295**	**294**	**138**	**1.11**	0.234 U	
(-25.6 to -35.6)		07/08/20	PES	Bladder	–	–	–	–	0.160 U	**1.40 J**	0.212 U	1.91 U	**203**	**215**	**89.2**	0.572 U	0.273 U	
		11/02/20	PES	Bladder	–	–	–	–	**0.380 J**	0.500 U	0.212 U	1.91 U	**235 J**	**302**	**1,160**	**3.16**	**5.08**	
		02/10/21	PES	Bladder	–	–	–	–	**0.790**	0.500 U	0.212 U	1.91 U	**135**	**230**	**1,350**	**6.34**	0.273 U	
		05/26/21	PES	Peristaltic	–	–	–	–	**0.930**	0.500 U	0.212 U	1.91 U	**58.2**	**131 J+**	**1,490**	**4.06**	0.273 U	
MW-338	Lake Union Park, N end	05/07/20	PES	Peristaltic	–	–	–	–	0.0941 U	0.278 U	0.137 U	0.174 U	0.300 U	0.190 U	0.126 U	0.149 U	0.234 U	
(-16.6 to -26.6)		07/23/20	PES	Peristaltic	–	–	–	–	0.0160 U	**1.16**	**0.0720 J**	**0.617**	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U	
		11/10/20	PES	Peristaltic	–	–	–	–	0.0160 U	0.0500 UJ	0.0212 U	0.191 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U	
		05/04/21	PES	Peristaltic	–	–	–	–	0.0160 U	0.0500 U	0.0212 U	0.191 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U	
MW-340	Lake Union Park, S end	05/12/20	PES	Peristaltic	–	–	–	–	0.0941 U	**0.428 J**	0.137 U	**0.635 J**	0.300 U	0.190 U	0.126 U	0.149 U	0.234 U	
(-16.1 to -26.1)		07/17/20	PES	Peristaltic	–	–	–	–	0.0160 U	0.0500 U	0.0212 U	0.191 U	0.0280 U	0.0160 U	0.0276 UJ	0.0572 U	0.0273 U	
		11/09/20	PES	Peristaltic	–	–	–	–	0.0160 U	0.0500 U	0.0212 U	0.191 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U	
		05/13/21	PES	Peristaltic	–	–	–	–	0.0160 U	0.0500 U	0.0212 U	0.191 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U	
MW-345	Seattle DOT Mercer Parcels	06/01/21	PES	Bladder	–	–	–	–	0.0160 U	**0.176 J**	0.0212 U	0.191 U	**0.717**	**0.456**	**13.9**	**0.0600 J**	**8.76**	
MW-346	Seattle DOT Mercer Parcels	06/02/21	PES	Bladder	–	–	–	–	**0.0290 J**	**0.206**	0.0212 U	0.191 U	**25.3**	**6.09**	**18.1**	0.0572 U	**1.90**	
(duplicate)	NW quadrant	06/02/21	PES	Bladder	–	–	–	–	**0.0290 J**	**0.194 J**	0.0212 U	0.191 U	**25.1**	**6.16**	**18.3**	0.0572 U	**1.93**	
MW-347	Seattle DOT Mercer Parcels	06/01/21	PES	Bladder	–	–	–	–	**0.0300 J**	**0.346**	0.0212 U	0.191 U	**5.19**	**3.83**	**123**	**0.291**	**66.9**	
MW-348	Seattle DOT Mercer Parcels	06/01/21	PES	Bladder	–	–	–	–	**0.0190 J**	**0.170 J**	0.0212 U	0.191 U	**12.6**	**8.62**	**104**	**0.107 J**	**55.4**	
MW-349	Seattle DOT Mercer Parcels	06/01/21	PES	Bladder	–	–	–	–	0.0160 U	**2.60**	**0.0400 J**	**0.191 J**	**0.611**	**0.474**	**7.23**	0.0572 U	**11.6**	
MW-350	Seattle DOT Mercer Parcels	06/01/21	PES	Bladder	–	–	–	–	**1.16**	**10.9**	**11.5**	**56.7**	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U	
PW-1	North Valley St ROW	1997 (8 hour)	B&V	Bailer	250 U	630 U	630 U	630 U	ND	ND	ND	ND	**1.0**	ND	ND	ND	ND	
(--)		1997 (Final)	B&V	Bailer	250 U	630 U	630 U	630 U	ND	ND	ND	ND	ND	ND	ND	ND	ND	
		Decommissioned Prior to 2017																
W-MW-01	8th Ave N ROW, W side	02/02/12	WW	Bladder	–	–	–	–	20 U	**0.1 J**	0.2 U	0.6 U	**46**	**3.9**	**11**	0.2 U	**0.5**	
(-25.1 to -35.1)		09/06/12	SES	Peristaltic	–	–	–	–	0.35 U	**1.7**	1 U	3 U	1 U	1 U	**2.0**	1 U	**2.8**	
		06/17/15	SES	Peristaltic	–	–	–	–	–	–	–	–	1 U	1 U	1 U	1 U	**0.46**	
		10/20/15	SES	Peristaltic	–	–	–	–	–	–	–	–	1 U	1 U	1 U	1 U	**0.88**	
		01/08/16	SES	Peristaltic	–	–	–	–	–	–	–	–	1 U	1 U	1 U	1 U	**2.5**	
		02/01/16	SES	Peristaltic	–	–	–	–	–	–	–	–	1 U	1 U	1 U	1 U	**2.8**	
		03/30/17	PES	Peristaltic	–	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	**0.330 J**	**0.203 J**	**0.491 J**	0.152 U	**1.83 J**	
		06/19/17	PES	Bladder	–	–	–	–	**0.158 J**	**0.931**	0.158 U	0.316 U	0.199 U	0.153 U	**0.320 J**	0.152 U	**1.09**	
		04/13/18	PES	Bladder	37.6 U	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	**5.33**	**1.68**	**1.31**	0.152 U	**8.79**	
		10/29/18	PES	Bladder	31.6 U	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	**0.220 J**	**0.696**	**0.629**	0.152 U	**3.90**	
		12/13/18	PES	Bladder	31.6 U	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	**1.77**	**0.538**	0.152 U	**3.86**	
		01/25/19	PES	Bladder	31.6 U	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	0.199 U	**0.587**	**0.459 J**	0.152 U	**5.46**	
		03/11/19	PES	Bladder	31.6 U	–	–	–	0.0896 U	0.412 U	0.158 U	0.316 U	**0.520**	**0.301 J**	**0.396 J**	0.152 U	**7.24**	

Table G-8

Groundwater Petroleum Hydrocarbons and CVOCs in Intermediate B Zone Wells
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																					
					GRO		DRO	ORO	DRO+ORO	Benzene		Toluene		Ethylbenzene		Total Xylenes		PCE		TCE		cDCE		tDCE		VC	
Preliminary Cleanup Level					**800**		**500**	**500**	**500**	**5.0**		**640**		**700**		**1,600**		**5.0**		**4.0**		**16**		**100**		**0.29**	
W-MW-01 (continued)		04/25/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**0.373**	**J**	**0.572**		0.152	U	**6.61**	**J**
		07/23/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**0.304**	**J**	**0.547**		0.152	U	**9.00**	
		10/15/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**0.350**	**J**	**0.408**	**J**	0.152	U	**7.36**	
		01/27/20	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**0.349**	**J**	**0.553**		0.152	U	**5.16**	
		04/03/20	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**0.244**	**J**	**0.588**		0.152	U	**3.79**	
		07/31/20	PES	Bladder	–		–	–	–	0.0160	U	0.0500	U	0.0212	U	0.191	U	**0.0742**	**J**	**0.299**		**0.431**	**J**	0.0572	UJ	**2.98**	
		11/24/20	PES	Bladder	–		–	–	–	0.0160	U	0.0500	U	0.0212	U	0.191	U	0.0280	U	**0.214**		**0.451**		0.0572	U	**5.82**	
		02/03/21	PES	Bladder	–		–	–	–	0.0160	U	0.0500	U	0.0212	U	0.191	U	0.0280	U	**0.191**		**0.495**		0.0572	U	**3.62**	
		05/17/21	PES	Bladder	–		–	–	–	0.0160	U	**0.828**		0.0212	U	0.191	U	0.0280	U	**0.197**		**0.367**		0.0572	U	**9.41**	
W-MW-02 (-26.3 to -36.3)	8th Ave N ROW, W side	02/03/12	WW	Bladder	–		–	–	–	20	U	20	U	20	U	60	U	**6,900**		**1,700**		**2,000**		20	U	**120**	
		08/13/12	SES	Peristaltic	–		–	–	–	–		–		–		–		**3,000**		**1,300**		**2,200**		**4.1**		**66**	
		09/05/12	SES	Peristaltic	–		–	–	–	0.35	U	**1.4**		1	U	3	U	**2,600**		**1,300**		**2,800**		**5.0**		**69**	
		01/03/14	SES	Peristaltic	–		–	–	–	0.35	U	1	U	1	U	3	U	**490**		**1,200**		**4,400**		**7.3**		**67**	
		06/17/15	SES	Peristaltic	–		–	–	–	–		–		–		–		10	U	10	U	**13,000**		**95**		**2,400**	
		10/20/15	SES	Peristaltic	–		–	–	–	–		–		–		–		5	Uht	5	Uht	**12,000**	**ht**	**97**	**ht**	**1,700**	**ht**
		11/10/15	SES	Peristaltic	–		–	–	–	–		–		–		–		1	U	**3.4**		**480**		**3.6**		**110**	
		12/11/15	SES	Peristaltic	–		–	–	–	–		–		–		–		1	U	**4.9**		**900**		**6.2**		**2,900**	
		01/08/16	SES	Peristaltic	–		–	–	–	–		–		–		–		1	U	**3.1**		**750**		**26**		**7,500**	
		02/01/16	SES	Peristaltic	–		–	–	–	–		–		–		–		1	U	**4.6**		**2,900**		**35**		**2,800**	
		03/27/17	PES	Peristaltic	–		–	–	–	**0.270**	**J**	**0.961**	**J**	0.158	U	0.316	U	0.199	U	**0.259**	**J**	**33.0**		**2.16**		**36.4**	
		06/19/17	PES	Bladder	–		–	–	–	**0.307**	**J**	**0.970**		0.158	U	0.316	U	0.199	U	0.153	U	**18.2**		**0.746**		**25.6**	
		06/12/18	PES	Bladder	31.6	U	–	–	–	0.0896	U	**0.829**		0.158	U	0.316	U	0.199	U	0.153	U	**4.72**		**0.279**	**J**	**4.95**	
		10/26/18	PES	Peristaltic	90.2	UJ	–	–	–	0.0896	U	**0.641**		0.158	U	0.316	U	0.199	U	0.153	U	**2.01**		**0.410**	**J**	**1.41**	
(duplicate)		10/26/18	PES	Peristaltic	**246**	**J+**	–	–	–	0.0896	U	**0.587**		0.158	U	0.316	U	0.199	U	0.153	U	**2.11**	**J+**	**0.435**	**J**	**1.80**	
		12/12/18	PES	Peristaltic	158	UJ	–	–	–	0.0896	U	**1.05**		0.158	U	0.316	U	0.199	U	0.153	U	**1.80**		**0.463**	**J**	**2.30**	
		01/25/19	PES	Peristaltic	**37.4**	**J**	–	–	–	**0.133**	**J**	**2.09**		0.158	U	0.316	U	0.199	U	0.153	U	**1.83**		**0.263**	**J**	**2.01**	
		03/11/19	PES	Peristaltic	31.6	U	–	–	–	0.0896	U	**1.12**		0.158	U	0.316	U	0.199	U	0.153	U	**2.41**		**0.316**	**J**	**2.43**	
		04/23/19	PES	Peristaltic	**429**	**zJ+**	–	–	–	0.0896	U	**0.56**		0.158	U	0.316	U	0.199	U	**40.1**		**672**		**2.35**		**81.0**	**J**
		07/23/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	**1.35**		0.158	U	0.316	U	0.199	U	0.153	U	**3.30**		**0.386**	**J**	**6.79**	
		10/18/19	PES	Bladder	316	U	–	–	–	0.0896	U	**1.79**		0.158	U	0.316	U	0.199	U	0.153	U	**2.07**		**0.278**	**J**	**3.56**	
		01/28/20	PES	Bladder	31.6	U	–	–	–	0.0896	U	**2.93**		0.158	U	0.316	U	0.199	U	0.153	U	**1.52**		**0.252**	**J**	**1.70**	
		04/01/20	PES	Bladder	31.6	U	–	–	–	0.0896	U	**2.51**		0.158	U	0.316	U	0.199	U	0.153	U	**1.44**		**0.166**	**J**	**1.42**	
		07/31/20	PES	Bladder	–		–	–	–	**0.0502**		**0.387**		0.0212	U	0.191	U	0.0280	U	**0.136**		**1.39**	**J**	**0.204**	**J**	**1.08**	
W-MW-03 (-30.8 to -40.8)	Property	02/03/12	WW	Bladder	–		–	–	–	20	U	20	U	20	U	60	U	**5,300**		**220**		**160**		20	U	20	U
		09/06/12	SES	Peristaltic	–		–	–	–	0.35	U	1	U	1	U	3	U	**13**		**2.6**		**20**		1	U	**120**	
		Decommissioned Prior to 2017																									

Table G-8

Groundwater Petroleum Hydrocarbons and CVOCs in Intermediate B Zone Wells
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)												
					GRO	DRO	ORO	DRO+ORO	Benzene	Toluene	Ethylbenzene	Total Xylenes	PCE	TCE	cDCE	tDCE	VC
Preliminary Cleanup Level					**800**	**500**	**500**	**500**	**5.0**	**640**	**700**	**1,600**	**5.0**	**4.0**	**16**	**100**	**0.29**
W-MW-04[a] (-32.5 to -41.5)	Property	02/03/12	WW	Bladder	–	–	–	–	20 U	20 U	20 U	60 U	**5,400**	**160**	**54**	20 U	20 U
		09/06/12	SES	Peristaltic	–	–	–	–	0.35 U	1 U	1 U	3 U	**460**	**440**	**1,900**	**4.0**	**630**
		Decommissioned Prior to 2017															
Number of Analytes Measured					135	20	18	20	263	263	263	263	273	273	273	273	273
Number of Analytes Detected					50	4	0	4	74	89	31	26	86	123	197	92	178
Frequency of Detection					37%	20%	0%	20%	28%	34%	12%	10%	32%	45%	72%	34%	65%
Maximum Detection					580 J	–	–	–	28.8	10.9	11.5	56.7	97,200	18,700	127,000	781	11,000
Minimum Detection					31.6 U	50 U	250 U	50 U	0.0160 U	0.0500 U	0.0212 U	0.1740 U	0.0280 U	0.0160 U	0.0276 U	0.0572 U	0.0273 U
Number of Analytes Detected Above SL					0	0	0	0	10	0	0	0	48	67	101	7	169
Frequency of Detection Above SL					0%	0%	0%	0%	4%	0%	0%	0%	18%	25%	37%	3%	62%

Notes:

PCULs from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021.

Detected results are shown in **bold.**

Detections above the groundwater PCUL level are shown in **bold and highlighted in gray.**

B&V = Black & Veatch.
cDCE = cis-1,2-Dichloroethene.
DOF = Dalton, Olmsted & Fuglevand, Inc.
DRO = Diesel-range organics.
GeoE = GeoEngineers Inc.
GRO = Gasoline-range organics.
HC = Hart Crowser.
ORO = Oil-range organics.
PCE = Perchloroethylene (Tetrachloroethene).
ROW = right-of-way.
SES = SES Strategies, Inc.
TCE = Trichloroethene.
tDCE = trans-1,2-Dichloroethene.
VC = Vinyl chloride.
WW = Windward.
Well screen elevations indicated below Sample Location in parentheses.
(--) = unknown screen elevation.
a = Monitoring well was installed at a 25 degree angle from the vertical point of penetration.

Laboratory and Results Notes:

Petroleum hydrocarbons analyzed by EPA Method 418.1, NWTPH-HCID, or NWTPH-Gx, NWTPH-Dx, or 8015-M.
VOCs analyzed by EPA Method 601, 8010S, 8015, 8020, 8021B, 8240, 8260B, 8260C, or 8260D, or by Purge and Trap Gas Chromatogram/Mass Spectrometry.
– = Not analyzed or results not available.
E = Estimated value. The reported range exceeds the calibration range of the analysis.
f = Analyte was detected in the associated method blank. Analyte concentration in the sample is greater than 10x the concentration found in the method blank.
g = Estimated value. The reported range exceeds the calibration range of the analysis.
ht = The analysis was performed outside the method the method or client-specified holding time requirement.
J = The identification of the analyte is acceptable; the reported value is an estimate.
J+ = The result is an estimated quantity, but the result may be biased high.
J- = The result is an estimated quantity, but the result may be biased low.
ND = Not detected at a concentration exceeding laboratory reporting limit; detection limit not provided.
pr = The sample was received with incorrect preservation. The value reported should be considered an estimate.
U = Not detected at or above the laboratory method detection limit (MDL).
qp = Hydrocarbon result partly due to individual peak(s) in quantitation range.
x = The sample chromatographic pattern does not resemble the fuel standard used for quantitation.
y = The GRO result in the sample is due to a pattern of peaks that is consistent with the chlorinated volatiles detected by the 8260C analysis.
z = No/low level gasoline/petroleum detection; result is likely elevated due to high detections of CVOCs.
Groundwater statistics are for data collected during the Remediation Investigation, 2017-2021.
Groundwater statistics for GRO exclude "z" qualified data.

Table G-9

Groundwater Petroleum Hydrocarbons and CVOCs in Deep Zone Wells
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																					
					GRO		DRO	ORO	DRO+ORO	Benzene		Toluene		Ethylbenzene		Total Xylenes		PCE		TCE		cDCE		tDCE		VC	
Preliminary Cleanup Level (PCUL)					**800**		**500**	**500**	**500**	**5.0**		**640**		**700**		**1,600**		**5.0**		**4.0**		**16**		**100**		**0.29**	
FMW-3D	Terry Ave N ROW, E side	03/24/17	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
(-31.1 to -41.1)		06/23/17	PES	Bladder	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
FMW-129	Seattle DOT Mercer Parcels,	05/23/14	Farallon	Unknown	–		–	–	–	–		–		–		–		**0.40**		**0.57**		**17**		ND		**7.6**	
(-45.6 to -50.6)	NE quadrant	10/20/15	SES	Peristaltic	–		–	–	–	–		–		–		–		**25**		**39**		**250**		1	U	0.2	U
		02/02/16	SES	Peristaltic	–		–	–	–	–		–		–		–		**13**		**61**		**240**		1	U	**0.330**	
		04/10/17	PES	Peristaltic	–		–	–	–	0.448	U	2.06	U	0.790	U	1.58	U	**194**		**492**		**1,420**		**5.05**		**0.885**	**J**
		06/23/17	PES	Bladder	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**81.1**		**182**		**474**		**1.21**		**0.413**	
		05/01/19	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**101**		**166**		**372**		**1.22**		0.590	U
		07/16/19	PES	Bladder	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**159**		**84.1**		**272**		**1.61**		**0.296**	**J**
		10/21/19	PES	Peristaltic	**141**	**zJ+**	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**114**		**198**		**350**		**1.61**		**0.259**	**J**
		11/12/19	Farallon	Unknown	–		–	–	–	–		–		–		–		**79**		**130**		**340**		2.0	U	2.0	U
		01/14/20	PES	Bladder	–		–	–	–	0.896	U	4.12	U	1.58	U	3.16	U	**113**		**170**		**385**		**1.60**	**J**	1.18	U
		01/14/20	Farallon	Unknown	–		–	–	–	–		–		–		–		**130**		**170**		**290**		2.0	U	2.0	U
		02/18/20	Farallon	Unknown	–		–	–	–	–		–		–		–		**110**		**170**		**310**		2.0	U	2.0	U
		03/25/20	Farallon	Unknown	–		–	–	–	–		–		–		–		**88**		**140**		**290**		2.0	U	**2.6**	
		04/27/20	Farallon	Unknown	–		–	–	–	–		–		–		–		**74**		**88**		**190**		1.0	U	1.0	U
		05/06/20	PES	Bladder	–		–	–	–	0.0941	U	0.278	U	0.137	U	0.174	U	**34.6**		**61.9**		**157**		**0.433**	**J**	**14.2**	
		05/19/20	Farallon	Unknown	–		–	–	–	–		–		–		–		**18**		**42**		**120**		1.0	U	**6.5**	
		07/10/20	PES	Bladder	–		–	–	–	0.0160	U	**1.47**		0.0212	U	0.191	U	**10.8**		**27.1**		**92.5**		**0.224**		**0.430**	
		07/28/20	Farallon	Unknown	–		–	–	–	–		–		–		–		**5.4**		**11**		**100**		0.80	U	0.80	U
		09/17/20	Farallon	Unknown	–		–	–	–	–		–		–		–		**6.1**		**13**		**70**		0.40	U	0.40	U
		11/10/20	PES	Bladder	–		–	–	–	0.0160	U	**0.136**	**J-**	0.0212	U	0.191	U	**6.43**		**22.3**		**58.8**		**0.135**	**J**	**8.49**	**J+**
		12/03/20	Farallon	Unknown	–		–	–	–	–		–		–		–		**9.0**		**14**		**57**		0.40	U	0.40	U
		02/10/21	PES	Peristaltic	–		–	–	–	0.0160	U	0.0500	U	0.0212	U	0.191	U	**2.42**		**4.97**		**42.5**		**0.276**		0.0273	U
(split)		02/10/21	Farallon	Peristaltic	–		–	–	–	–		–		–		–		**1.9**		**4.6**		**31**		0.20	U	0.20	U
		05/26/21	PES	Bladder	–		–	–	–	**0.0910**		0.0860	U	0.0212	U	0.191	U	**91.1**		**197**		**517**		**1.53**		0.0273	U
(duplicate)		05/26/21	PES	Bladder	–		–	–	–	**0.127**		0.102	U	0.0212	U	0.191	U	**97.2**		**201**		**526**		**1.56**		0.0273	U
FMW-131	Block 37, SE quadrant	09/02/16	Farallon	Unknown	–		–	–	–	–		–		–		–		0.20	U	0.20	U	**41**		0.20	U	**1.7**	
(-34.7 to -44.7)		03/24/17	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**45.6**		0.152	U	**0.249**	**J**
		06/23/17	PES	Bladder	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**3.61**		0.152	U	**0.264**	**J**
		12/18/17	Farallon	Unknown	–		–	–	–	–		–		–		–		0.20	U	0.20	U	**0.61**		0.20	U	0.20	U
		04/22/19	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**10.8**		0.152	U	**0.195**	**J**
		10/21/19	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**10.5**		0.152	U	**0.140**	**J**
		01/22/20	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**15.1**		0.152	U	**0.162**	**J**
		04/29/20	PES	Peristaltic	–		–	–	–	0.0941	U	**0.954**		0.137	U	**0.726**	**J**	0.300	U	0.190	U	**13.9**		0.149	U	**0.309**	**J**
		07/30/20	PES	Bladder	–		–	–	–	**0.0459**		**0.0500**	**J**	0.0212	U	0.191	U	0.0280	U	0.0160	U	**6.73**	**J**	0.0572	UJ	**0.147**	
		08/26/20	Farallon	Unknown	–		–	–	–	–		–		–		–		0.20	U	0.20	U	**6.5**		0.20	U	0.20	U
		11/19/20	PES	Bladder	–		–	–	–	**0.0850**		**0.0520**	**J**	0.0212	U	0.191	U	0.0280	U	0.0160	U	**7.91**		0.0572	U	**0.109**	
		12/04/20	Farallon	Unknown	–		–	–	–	–		–		–		–		0.20	U	0.20	U	**3.5**		0.20	U	0.20	U
		02/11/21	Farallon	Unknown	–		–	–	–	–		–		–		–		0.20	U	0.20	U	**0.27**		0.20	U	0.20	U
		02/12/21	PES	Peristaltic	–		–	–	–	**0.0900**		**1.04**		**0.172**		**0.952**		**0.0450**	**J**	0.0160	U	**7.89**		0.0572	U	**0.287**	
		05/13/21	PES	Peristaltic	–		–	–	–	**0.0650**		**0.115**	**J**	0.0212	U	0.191	U	0.0280	U	0.0160	U	**9.83**		0.0572	U	**0.428**	
FMW-137	Alley E of Block 38W	11/20/18	Farallon	Unknown	–		–	–	–	–		–		–		–		0.20	U	0.20	U	**1.2**		0.20	U	0.20	U
(-39.9 to -54.9)		12/28/18	Farallon	Unknown	–		–	–	–	–		–		–		–		0.20	U	0.20	U	**1.1**		0.20	U	0.20	U
		05/06/19	Farallon	Unknown	–		–	–	–	–		–		–		–		0.20	U	0.20	U	**1.3**		0.20	U	0.20	U
		07/08/19	Farallon	Unknown	–		–	–	–	–		–		–		–		0.20	U	0.20	U	**1.3**		0.20	U	0.20	U
		10/14/19	Farallon	Unknown	–		–	–	–	–		–		–		–		0.20	U	0.20	U	**1.1**		0.20	U	0.20	U
		11/06/19	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**1.27**		0.152	U	0.118	U

Table G-9

Groundwater Petroleum Hydrocarbons and CVOCs in Deep Zone Wells
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																	
					GRO	DRO	ORO	DRO+ORO	Benzene		Toluene		Ethylbenzene		Total Xylenes		PCE		TCE		cDCE		tDCE		VC	
Preliminary Cleanup Level (PCUL)					**800**	**500**	**500**	**500**	**5.0**		**640**		**700**		**1,600**		**5.0**		**4.0**		**16**		**100**		**0.29**	
FMW-137 (continued)		11/11/19	Farallon	Unknown	–	–	–	–	–		–		–		–		0.20	U	0.20	U	**1.3**		0.20	U	0.20	U
		01/22/20	PES	Peristaltic	–	–	–	–	0.0896	U	**0.506**		0.158	U	0.316	U	0.199	U	0.153	U	**1.99**		0.152	U	0.118	U
		05/06/20	PES	Bladder	–	–	–	–	0.0941	U	0.278	U	0.137	U	0.174	U	0.300	U	0.190	U	0.126	U	0.149	U	0.234	U
		07/31/20	PES	Bladder	–	–	–	–	0.0160	U	**0.884**		**0.137**		**0.637**		0.0280	U	0.0160	U	**0.0343**	**J**	0.0572	UJ	0.0273	U
		11/24/20	PES	Bladder	–	–	–	–	0.0160	U	0.0900	U	0.0480	U	**0.294**		0.0280	U	0.0160	U	**0.0540**	**J**	0.0572	U	0.0273	U
		02/12/21	PES	Bladder	–	–	–	–	**0.0330**	**J**	**0.448**		**0.0800**	**J**	**0.442**		0.0280	U	0.0160	U	**2.66**		0.0572	U	**0.0920**	**J**
		06/02/21	PES	Peristaltic	–	–	–	–	**0.0240**	**J**	0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	**2.99**		0.0572	U	0.0273	U
FMW-138 (-50.0 to -60.0)	Alley E of Block 38W	11/20/18	Farallon	Unknown	–	–	–	–	–		–		–		–		0.20	U	0.20	U	**0.29**		0.20	U	0.20	U
		12/28/18	Farallon	Unknown	–	–	–	–	–		–		–		–		0.20	U	0.20	U	**0.34**		0.20	U	0.20	U
		05/06/19	Farallon	Unknown	–	–	–	–	–		–		–		–		0.20	U	0.20	U	**0.38**		0.20	U	0.20	U
		07/08/19	Farallon	Unknown	–	–	–	–	–		–		–		–		0.20	U	0.20	U	**0.34**		0.20	U	0.20	U
		10/14/19	Farallon	Unknown	–	–	–	–	–		–		–		–		0.20	U	0.20	U	**0.33**		0.20	U	0.20	U
		11/11/19	Farallon	Unknown	–	–	–	–	–		–		–		–		0.20	U	0.20	U	**0.37**		0.20	U	0.20	U
FMW-140 (-38.0 to -48.0)	900 Roy St, S end	07/17/19	Farallon	Unknown	–	–	–	–	–		–		–		–		2.0	U	2.0	U	**280**		2.0	U	**320**	
		10/31/19	PES	Peristaltic	–	–	–	–	**18.5**		**1.43**		0.158	**U**	0.316	U	0.199	U	0.153	U	**0.160**	**J**	0.152	U	**189**	
		11/12/19	Farallon	Unknown	–	–	–	–	–		–		–		–		4.0	U	4.0	U	**310**		4.0	U	**510**	
		01/14/20	Farallon	Unknown	–	–	–	–	–		–		–		–		4.0	U	4.0	U	**340**		4.0	U	**460**	
		01/22/20	PES	Peristaltic	–	–	–	–	**39.6**		0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**406**		**0.729**		**527**	
		02/18/20	Farallon	Unknown	–	–	–	–	–		–		–		–		4.0	U	4.0	U	**280**		4.0	U	**530**	
		03/25/20	Farallon	Unknown	–	–	–	–	–		–		–		–		2.0	U	2.0	U	**100**		2.0	U	**290**	
		04/27/20	Farallon	Unknown	–	–	–	–	–		–		–		–		1.0	U	1.0	U	**33**		1.0	U	**130**	
		04/28/20	PES	Bladder	–	–	–	–	**43.3**		0.278	U	0.137	U	0.174	U	0.300	U	0.190	U	**27.1**		**0.217**	**J**	**147**	
		05/19/20	Farallon	Unknown	–	–	–	–	–		–		–		–		1.0	U	1.0	U	**16**		1.0	U	**130**	
		07/07/20	PES	Bladder	–	–	–	–	**37.6**		**2.79**		0.0212	U	0.191	U	0.0280	U	0.0160	U	**8.76**		**0.202**		**188**	
		07/29/20	Farallon	Unknown	–	–	–	–	–		–		–		–		1.0	U	1.0	U	**9.7**		1.0	U	**170**	
		09/17/20	Farallon	Unknown	–	–	–	–	–		–		–		–		1.0	U	1.0	U	**25**		1.0	U	**43**	
		11/13/20	PES	Bladder	–	–	–	–	**44.1**		**0.147**	**J**	0.0212	U	0.191	U	0.0280	U	0.0160	U	**6.15**		**0.0665**	**J**	**30.8**	
		12/04/20	Farallon	Unknown	–	–	–	–	–		–		–		–		0.20	U	0.20	U	**3.3**		0.20	U	**18**	
		02/10/21	Farallon	Unknown	–	–	–	–	–		–		–		–		0.20	U	0.20	U	**0.72**		0.20	U	**3.2**	
		05/18/21	PES	Peristaltic	–	–	–	–	**41.0**		**0.152**	**J**	0.0212	U	0.191	U	0.0280	U	0.0160	U	**2.12**		0.0572	U	**15.8**	
GEI-2 (-21.1 to -31.1)	Block 37, NW quadrant	03/24/17	PES	Peristaltic	–	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**2.25**		0.152	U	**6.94**	
		06/23/17	PES	Bladder	–	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**16.3**		0.152	U	**127**	
		12/29/18	Farallon	Unknown	–	–	–	–	–		–		–		–		0.40	U	0.40	U	**6.7**		0.40	U	**60**	
		04/22/19	PES	Peristaltic	–	–	–	–	**1.05**		0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**11.5**		0.152	U	**57.7**	**J**
		07/16/19	PES	Peristaltic	–	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**1.37**		0.152	U	**46.4**	
		10/21/19	PES	Peristaltic	–	–	–	–	**3.80**		0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**20.1**		0.152	U	**88.2**	
		11/11/19	Farallon	Unknown	–	–	–	–	–		–		–		–		1.0	U	1.0	U	**18**		1.0	U	**92**	
		01/14/20	Farallon	Unknown	–	–	–	–	–		–		–		–		0.20	U	0.20	U	**2.0**		0.20	U	**36**	
		01/22/20	PES	Peristaltic	–	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**0.192**	**J**	**0.308**	**J**	0.152	U	0.118	U
		02/17/20	Farallon	Unknown	–	–	–	–	–		–		–		–		0.20	U	0.20	U	**5.6**		0.20	U	**34**	
		03/25/20	Farallon	Unknown	–	–	–	–	–		–		–		–		0.40	U	0.40	U	**4.3**		0.40	U	**52**	
		04/27/20	Farallon	Unknown	–	–	–	–	–		–		–		–		0.40	U	0.40	U	**3.2**		0.40	U	**50**	
		04/29/20	PES	Peristaltic	–	–	–	–	**2.22**		0.278	U	0.137	U	0.174	U	0.300	U	0.190	U	**4.49**		0.149	U	**67.8**	
		05/19/20	Farallon	Unknown	–	–	–	–	–		–		–		–		0.40	U	0.40	U	**2.7**		0.40	U	**55**	
		06/29/20	Farallon	Unknown	–	–	–	–	–		–		–		–		0.20	U	0.20	U	**1.6**		0.20	U	**33**	
		07/29/20	Farallon	Unknown	–	–	–	–	–		–		–		–		0.20	U	0.20	U	**1.3**		0.20	U	**46**	

Table G-9

Groundwater Petroleum Hydrocarbons and CVOCs in Deep Zone Wells
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																					
					GRO		DRO		ORO		DRO+ORO		Benzene		Toluene		Ethylbenzene		Total Xylenes		PCE		TCE		cDCE		tDCE		VC	
Preliminary Cleanup Level (PCUL)					**800**		**500**		**500**		**500**		**5.0**		**640**		**700**		**1,600**		**5.0**		**4.0**		**16**		**100**		**0.29**	
GEI-2 (continued)		07/30/20	PES	Bladder	–		–		–		–		**1.76**		**0.0707**	**J**	0.0212	U	0.191	U	0.0280	U	0.0160	U	**1.38**	**J**	0.0572	UJ	**44.9**	
		08/26/20	Farallon	Unknown	–		–		–		–		–		–		–		–		0.20	U	0.20	U	0.20	U	0.20	U	0.20	U
		09/17/20	Farallon	Unknown	–		–		–		–		–		–		–		–		0.40	U	0.40	U	**1.0**		0.40	U	**48**	
		11/19/20	PES	Bladder	–		–		–		–		**2.97**		0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	**0.997**		0.0572	U	**42.7**	
		12/04/20	Farallon	Unknown	–		–		–		–		–		–		–		–		0.20	U	0.20	U	**0.52**		0.20	U	**21**	
		02/11/21	Farallon	Unknown	–		–		–		–		–		–		–		–		0.20	U	0.20	U	**0.43**		0.20	U	**16**	
		02/12/21	PES	Peristaltic	–		–		–		–		**2.79**		**1.22**		**0.216**		**1.09**		0.0280	U	0.0160	U	**0.711**		0.0572	U	**18.4**	
		05/13/21	PES	Peristaltic	–		–		–		–		**2.19**		**0.149**	**J**	0.0212	U	0.191	U	0.0280	U	0.0160	U	**0.379**		0.0572	U	**9.14**	
HMW-1D (-41.9 to -51.9)	Seattle DOT Mercer Parcels, NE quadrant	03/25/19	HC	Peristaltic	100	U	200	U	500	U	500	U	1.0	U	1.0	U	1.0	U	1.0	U	**3.4**		**27**		**410**		**1.2**		**4.0**	
		03/09/20	HC	Submersible	**140**		**94**	**J**	250	U	**94**	**J**	20	U	20	U	20	U	40	U	**21**		**110**		**910**		20	U	6.0	U
HMW-2D (-32.7 to -42.7)	Seattle DOT Mercer Parcels, NE quadrant	03/25/19	HC	Peristaltic	100	U	200	U	500	U	500	U	1.0	U	1.0	U	1.0	U	1.0	U	1.0	U	1.0	U	1.0	U	1.0	U	0.2	U
		03/12/20	HC	Submersible	100	U	**86**	**J**	250	U	**86**	**J**	0.20	U	0.20	U	0.20	U	0.40	U	0.20	U	0.20	U	**1.1**		0.20	U	0.20	U
HMW-3D (-23.4 to -33.4)	Seattle DOT Mercer Parcels, NW quadrant	03/25/19	HC	Peristaltic	100	U	200	U	500	U	500	U	1.0	U	**1.1**		1.0	U	1.0	U	1.0	U	1.0	U	1.0	U	1.0	U	0.2	U
		03/13/20	HC	Submersible	100	U	**480**	**J**	250	U	**480**	**J**	0.20	U	0.20	U	0.20	U	0.40	U	0.20	U	0.20	U	0.20	UJ	0.20	U	0.20	U
HMW-6D (-21.1 to -31.1)	Seattle DOT Mercer Parcels, SW quadrant	03/16/20	HC	Submersible	100	U	50	U	250	U	250	U	**0.42**		**0.64**		0.20	U	0.40	U	0.20	U	0.20	U	0.20	U	0.20	U	0.20	U
HMW-9D (-24.4 to -34.4)	Seattle DOT Mercer Parcels, SW quadrant	03/17/20	HC	Submersible	100	U	**230**	**J**	250	U	**230**	**J**	**0.21**		**0.42**		0.20	U	0.40	U	**0.89**		0.20	U	**5.1**		0.20	U	**0.97**	
HMW-10D (-30.8 to -40.8)	Seattle DOT Mercer Parcels, SE quadrant	03/16/20	HC	Submersible	100	U	50	U	250	U	250	U	0.20	U	0.20	U	0.20	U	0.40	U	0.20	U	0.20	U	0.20	U	0.20	U	0.20	U
HMW-12D (-48.5 to -58.5)	Seattle DOT Mercer Parcels, NE quadrant	09/10/20	HC	–	100	U	50	U	–		50	U	0.20	U	0.20	U	0.20	U	0.40	U	0.20	U	0.20	U	**200**	**J**	**0.22**		**3.9**	
HMW-13D (-44.2 to -54.2)	Seattle DOT Mercer Parcels, SE quadrant	09/10/20	HC	–	100	U	50	U	–		50	U	0.20	U	0.20	U	0.20	U	0.40	U	0.20	U	0.20	U	0.20	U	0.20	U	0.20	U
HMW-14D (-23.7 to -33.7)	Seattle DOT Mercer Parcels, SE quadrant	09/16/20	HC	–	100	U	50	U	–		50	U	0.20	U	0.20	U	0.20	U	0.40	U	0.20	U	0.20	U	0.20	U	0.20	U	0.20	U
MW101 (-65.5 to -75.5)	Property, NE quadrant	07/20/12	SES	Bladder	–		–		–		–		–		–		–		–		1	U	1	U	1	U	1	U	0.2	U
		09/06/12	SES	Peristaltic	–		–		–		–		0.35	U	**1.4**		1	U	3	U	1	U	1	U	1	U	1	U	0.2	U
		Decommissioned Prior to 2017																												
MW102 (-65.8 to -75.8)	Valley St ROW, S side	08/16/12	SES	Peristaltic	–		–		–		–		–		–		–		–		1	U	1	U	1	U	1	U	0.2	U
		09/05/12	SES	Bladder	–		–		–		–		0.35	U	1	U	1	U	3	U	1	U	1	U	1	U	1	U	0.2	U
		12/17/13	SES	Bladder	–		–		–		–		0.35	U	1	U	1	U	3	U	1	U	1	U	1	U	1	U	0.2	U
		10/27/15	SES	Bladder	–		–		–		–		–		–		–		–		1	U	1	U	1	U	1	U	0.2	U
		02/02/16	SES	Bladder	–		–		–		–		–		–		–		–		1	U	1	U	1	U	1	U	0.2	U
		03/29/17	PES	Bladder	–		–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.289**	**J**	0.152	U	0.118	U
		06/15/17	PES	Bladder	–		–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		04/25/18	PES	Bladder	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**0.352**	**J**	0.153	U	0.0933	U	0.152	U	0.118	U
		01/24/19	PES	Bladder	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	**0.220**	**J**	0.153	U	0.0933	U	0.152	U	0.118	U
		05/01/19	PES	Bladder	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	UJ
		07/18/19	PES	Bladder	31.6	U	–		–		–		0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U

Table G-9

Groundwater Petroleum Hydrocarbons and CVOCs in Deep Zone Wells
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																					
					GRO		DRO	ORO	DRO+ORO	Benzene		Toluene		Ethylbenzene		Total Xylenes		PCE		TCE		cDCE		tDCE		VC	
Preliminary Cleanup Level (PCUL)					800		500	500	500	5.0		640		700		1,600		5.0		4.0		16		100		0.29	
MW102		11/14/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
(continued)		01/23/20	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
(duplicate)		01/23/20	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		04/02/20	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		08/04/20	PES	Bladder	–		–	–	–	0.0160	U	**1.00**		0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
(duplicate)		08/04/20	PES	Bladder	–		–	–	–	0.0160	U	**0.880**		**0.0340**	**J**	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	UJ	0.0273	U
		11/18/20	PES	Bladder	–		–	–	–	0.0160	U	**0.0710**	**J**	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
		02/03/21	PES	Bladder	–		–	–	–	0.0160	U	**0.0880**	**J**	**0.0390**	**J**	**0.282**		0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
		05/14/21	PES	Bladder	–		–	–	–	0.0160	U	0.196	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
MW103	Alley E of Seattle Roy Aloha Shops	07/31/12	SES	Peristaltic	–		–	–	–	–		–		–		–		**12**		**25**		**150**		10	U	**79**	
(-67.6 to -77.6)		09/05/12	SES	Peristaltic	–		–	–	–	0.35	U	**1.6**		1	U	3	U	**8.3**		**22**		**80**		1	U	**110**	
(duplicate)		09/05/12	SES	Peristaltic	–		–	–	–	0.35	U	**1.6**		1	U	3	U	**8.1**		**22**		**85**		1	U	**120**	
		12/18/13	SES	Peristaltic	–		–	–	–	0.35	U	**2.4**		1	U	3	U	**4.3**		**6.1**		**8.6**		1	U	**1.2**	
(duplicate)		12/18/13	SES	Peristaltic	–		–	–	–	0.35	U	**2.4**		1	U	3	U	**4.0**		**5.2**		**7.1**		1	U	**0.94**	
		06/17/15	SES	Peristaltic	–		–	–	–	–		–		–		–		**1.8**		**1.4**		1	U	1	U	**0.94**	
		10/20/15	SES	Peristaltic	–		–	–	–	–		–		–		–		**3.6**		**1.4**		1	U	1	U	**1.6**	
		02/02/16	SES	Peristaltic	–		–	–	–	–		–		–		–		**1.0**		1	U	**1.2**		1	U	**0.53**	
		03/29/17	PES	Peristaltic	–		–	–	–	0.0896	U	**0.464**	**J**	0.158	U	0.316	U	1.99	U	**23.1**		**240**		**0.405**	**J**	**157**	
		06/14/17	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**0.626**		**23.0**		**120**		**0.369**	**J**	**69.2**	
		04/06/18	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**1.81**		**32.4**		0.152	U	**22.4**	
		01/23/19	PES	Peristaltic	–		–	–	–	0.0896	U	**1.35**		0.158	U	0.316	U	**0.365**	**J**	**1.48**		**11.4**		0.152	U	**6.68**	
		04/22/19	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**3.09**		**88.0**		**0.209**	**J**	**32.3**	**J**
		07/15/19	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**2.37**		**118**		**0.232**	**J**	**55.4**	
		10/14/19	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**91.7**		**0.158**	**J**	**51.8**	
		01/16/20	PES	Bladder	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**40.6**		0.152	U	**77.9**	
		04/23/20	PES	Bladder	–		–	–	–	0.0941	U	0.278	U	0.137	U	0.174	U	0.300	U	**0.233**	**J**	**12.8**		0.149	U	**4.80**	
(duplicate)		04/23/20	PES	Bladder	–		–	–	–	0.0941	U	0.278	U	0.137	U	0.433	U	0.300	U	**0.244**	**J**	**12.9**		0.149	U	**4.71**	
		07/06/20	PES	Bladder	–		–	–	–	**0.0210**	**J**	**2.12**		0.0212	U	0.191	U	0.0280	U	**0.185**		**4.21**		0.0572	UJ	**2.18**	
		11/02/20	PES	Bladder	–		–	–	–	**0.0270**	**J**	**0.158**	**J**	0.0212	U	0.191	U	0.0280	U	**0.0800**		**2.75**		**0.0590**	**J**	**2.22**	
		02/10/21	PES	Bladder	–		–	–	–	**0.0200**	**J**	**0.542**		**0.0450**	**J**	**0.433**		0.0280	U	**0.602**		**9.05**		0.0572	U	**5.37**	
		05/03/21	PES	Bladder	–		–	–	–	0.0160	U	**0.0950**	**J**	0.0212	U	0.191	U	**0.569**		**8.73**		**34.0**		**0.108**	**J**	**15.8**	
MW104	8th Ave N ROW, W side	08/16/12	SES	Peristaltic	–		–	–	–	–		–		–		–		1	U	1	U	1	U	1	U	0.2	U
(-76.3 to -86.3)		09/06/12	SES	Bladder	–		–	–	–	0.35	U	1	U	1	U	3	U	1	U	1	U	1	U	1	U	0.2	U
		12/17/13	SES	Bladder	–		–	–	–	0.35	U	1	U	1	U	3	U	1	U	1	U	1	U	1	U	0.2	U
		10/27/15	SES	Peristaltic	–		–	–	–	–		–		–		–		**2.6**		**4.4**		**4.3**		1	U	0.2	U
		02/02/16	SES	Bladder	–		–	–	–	–		–		–		–		1	U	**1.2**		**19**		1	U	0.2	U
		03/30/17	PES	Bladder	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**3.97**		0.152	U	0.118	UJ
		06/30/17	PES	Bladder	–		–	–	–	**0.387**	**J**	**0.903**		0.158	U	**0.396**	**J**	**5.83**		**5.21**		**1.54**		0.152	U	0.118	U
		04/09/18	PES	Peristaltic	**81.3**	**J**	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**0.541**		**2.00**		**176**		**1.02**		**32.3**	
		10/26/18	PES	Bladder	**1,570**	**zJ+**	–	–	–	0.0896	U	**0.618**	**J+**	0.158	U	0.316	U	**1.87**	**J+**	**2.94**	**J+**	**71.2**		**0.257**	**J**	**43.5**	
		12/13/18	PES	Bladder	**54.0**	**J**	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**0.381**	**J**	**2.36**		**48.3**		**0.559**		**43.8**	
		02/01/19	PES	Bladder	**191**	**zJ+**	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**12.1**		**3.22**		**30.6**		**0.326**	**J**	**32.4**	
		03/13/19	PES	Bladder	**124**	**zJ+**	–	–	–	0.0896	U	**0.455**	**J**	0.158	U	0.316	U	**31.6**		**75.7**		**83.0**		**1.93**		**25.9**	
		04/23/19	PES	Bladder	**174**	**zJ+**	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**15.9**		**56.9**		**162**		**2.49**		**21.1**	**J**
		07/22/19	PES	Bladder	**50.4**	**zJ+**	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**0.282**	**J**	**28.3**		**160**		**2.10**		**57.1**	
		10/18/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**1.54**		**16.3**		**0.329**	**J**	**33.2**	

Table G-9

Groundwater Petroleum Hydrocarbons and CVOCs in Deep Zone Wells
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																					
					GRO		DRO	ORO	DRO+ORO	Benzene		Toluene		Ethylbenzene		Total Xylenes		PCE		TCE		cDCE		tDCE		VC	
Preliminary Cleanup Level (PCUL)					800		500	500	500	5.0		640		700		1,600		5.0		4.0		16		100		0.29	
MW104		01/29/20	PES	Bladder	**447**	**zJ+**	–	–	–	**0.167**	**J**	0.412	U	0.158	U	0.316	U	**0.894**		**6.44**		**44.6**		**0.481**	**J**	**31.7**	
(continued)		04/01/20	PES	Bladder	92.4	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**53.1**		**108**		**21.1**		**2.50**		**4.63**	
		07/31/20	PES	Bladder	–		–	–	–	0.0160	U	**0.251**		0.0212	U	0.191	U	**18.8**		**55.0**		**12.8**	**J**	**1.01**		**2.68**	
(duplicate)		07/31/20	PES	Bladder	–		–	–	–	0.0160	U	**0.242**		0.0212	U	0.191	U	**19.2**		**55.0**		**12.6**	**J**	**1.04**	**J**	**2.65**	
		11/17/20	PES	Bladder	–		–	–	–	0.0160	U	**0.0730**	**J**	0.0212	U	0.191	U	**10.6**		**59.5**	**J+**	**28.6**		**1.61**		**4.68**	
		02/10/21	PES	Bladder	–		–	–	–	**0.0450**		**2.03**		**0.225**		**1.18**		**1.52**		**29.8**		**43.9**		**1.15**		**9.58**	
MW105	Roy St ROW, S side	08/16/12	SES	Peristaltic	–		–	–	–	–		–		–		–		1	U	1	U	1	U	1	U	**0.32**	
(-85.8 to -95.8)		09/05/12	SES	Peristaltic	–		–	–	–	0.35	U	1	U	1	U	3	U	1	U	1	U	1	U	1	U	**0.23**	
		12/29/13	SES	Bladder	–		–	–	–	0.35	U	1	U	1	U	3	U	1	U	1	U	1	U	1	U	0.2	U
		04/12/15	SES	Peristaltic	–		–	–	–	–		–		–		–		**1.2**		**1.6**		1	U	1	U	0.2	U
		06/17/15	SES	Peristaltic	–		–	–	–	–		–		–		–		1	U	1	U	1	U	1	U	0.2	U
		10/27/15	SES	Bladder	–		–	–	–	–		–		–		–		1	U	1	U	1	U	1	U	0.2	U
		02/03/16	SES	Bladder	–		–	–	–	–		–		–		–		1	U	1	U	1	U	1	U	**1.6**	
		04/21/17	PES	Bladder	–		–	–	–	0.0896	U	**0.544**	**J**	0.158	U	0.316	U	0.199	U	0.153	U	**0.155**	**J**	0.152	U	**1.95**	
		06/14/17	PES	Bladder	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**0.356**	**J**	**0.180**	**J**	0.152	U	**0.514**	
		04/11/18	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**1.67**		0.152	U	**0.205**	**J**
		01/23/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**0.790**		**0.317**	**J**	**1.51**		0.152	U	**0.392**	**J**
		04/23/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.917**		0.152	U	**0.238**	**J**
		07/17/19	PES	Bladder	37.8	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.891**		0.152	U	**0.265**	**J**
		10/22/19	PES	Bladder	**96.4**	**J**	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.945**		0.152	U	**0.214**	**J**
(duplicate)		10/22/19	PES	Bladder	**90.8**	**J**	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.720**		0.152	U	0.118	U
		01/20/20	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**0.208**	**J**	**0.348**	**J**	**1.38**		0.152	U	**0.568**	
		05/12/20	PES	Bladder	**52.7**	**J**	–	–	–	0.0941	U	**0.635**		0.137	U	**0.193**	**J**	0.300	U	**1.02**		**0.805**		0.149	U	0.234	U
		07/27/20	PES	Bladder	–		–	–	–	0.0160	U	**1.25**		0.0212	U	0.191	U	**0.324**		**2.12**		**1.56**		**0.0983**	**J**	**0.135**	
		11/17/20	PES	Peristaltic	–		–	–	–	0.0160	U	**0.139**	**J**	0.0212	U	0.191	U	**0.553**		**4.95**	**J+**	**4.83**		**0.248**		**0.150**	
		02/11/21	PES	Bladder	–		–	–	–	0.0160	U	**0.373**		**0.0690**	**J**	**0.528**		**0.335**		**3.53**		**6.78**		**0.403**		**0.178**	
		06/07/21	PES	Bladder	–		–	–	–	**0.161**		**1.09**		**0.0490**	**J**	**0.234**	**J**	**0.128**		**1.37**		**11.5**		**0.300**		**0.359**	
MW106	Seattle DOT Mercer Parcels,	08/22/12	SES	Bladder	–		–	–	–	–		–		–		–		1	U	1	U	1	U	1	U	1	U
(-78.0 to -88.0)	NW quadrant	09/05/12	SES	Bladder	–		–	–	–	0.35	U	1	U	1	U	3	U	1	U	1	U	1	U	1	U	0.2	U
		12/17/13	SES	Bladder	–		–	–	–	0.35	U	1	U	1	U	3	U	1	U	1	U	1	U	1	U	0.2	U
		10/27/15	SES	Bladder	–		–	–	–	–		–		–		–		1	U	1	U	1	U	1	U	0.2	U
		02/02/16	SES	Bladder	–		–	–	–	–		–		–		–		1	U	1	U	1	U	1	U	0.2	U
		04/14/17	PES	Bladder	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		06/30/17	PES	Bladder	–		–	–	–	0.0896	U	**0.419**	**J**	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		05/04/18	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		04/26/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	UJ
		07/19/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		10/18/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		01/14/20	PES	Bladder	33.1	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		05/06/20	PES	Bladder	**32.3**	**J**	–	–	–	0.0941	U	0.278	U	0.137	U	0.174	U	0.300	U	0.190	U	0.126	U	0.149	U	0.234	U
(duplicate)		05/06/20	PES	Bladder	**48.8**	**J**	–	–	–	0.0941	U	0.278	U	0.137	U	0.174	U	0.300	U	0.190	U	0.126	U	0.149	U	0.234	U
		07/10/20	PES	Bladder	–		–	–	–	0.0160	U	**1.74**		0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
		11/10/20	PES	Bladder	–		–	–	–	0.0160	U	**0.415**	**J-**	0.0212	U	**0.233**	**J**	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
(duplicate)		11/10/20	PES	Bladder	–		–	–	–	0.0160	U	**0.339**	**J-**	0.0212	U	**0.216**	**J**	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
		02/12/21	PES	Bladder	–		–	–	–	0.0160	U	0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
(duplicate)		02/12/21	PES	Bladder	–		–	–	–	0.0160	U	0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
		05/13/21	PES	Bladder	–		–	–	–	0.0160	U	**0.0570**	**J**	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U

Table G-9

Groundwater Petroleum Hydrocarbons and CVOCs in Deep Zone Wells
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																					
					GRO		DRO	ORO	DRO+ORO	Benzene		Toluene		Ethylbenzene		Total Xylenes		PCE		TCE		cDCE	tDCE		VC	
Preliminary Cleanup Level (PCUL)					800		500	500	500	5.0		640		700		1,600		5.0		4.0		16	100		0.29	
MW113	9th Ave N ROW, W side	12/21/12	SES	Peristaltic	–		–	–	–	–		–		–		–		**1.3**	**i**	**440**		**5,500**	**4.1**		**150**	
(-37.1 to -47.1)		12/19/13	SES	Peristaltic	–		–	–	–	0.35	U	1	U	1	U	3	U	1	U	**13**		**140**	1	U	**0.41**	
		06/25/15	SES	Peristaltic	–		–	–	–	–		–		–		–		1	U	**19**		**670**	1	U	**17**	
		10/27/15	SES	Peristaltic	–		–	–	–	–		–		–		–		1	U	**4.5**		**670**	**1.2**		**17**	
		02/03/16	SES	Peristaltic	–		–	–	–	–		–		–		–		1	U	**1.1**		**1,500**	**2.2**		**13**	
		03/22/17	PES	Peristaltic	–		–	–	–	**2.60**		0.412	U	0.158	U	0.316	U	0.199	U	**27.1**		**7,280**	**25.4**		**63.5**	
		06/16/17	PES	Bladder	–		–	–	–	**0.468**	**J**	0.412	U	0.158	U	0.316	U	**0.522**		**148**		**4,750**	**28.2**		**53.3**	
		04/11/18	PES	Peristaltic	–		–	–	–	**0.880**		0.412	U	0.158	U	0.316	U	**191**		**1,100**		**3,720**	**21.3**		**34.9**	
		01/30/19	PES	Peristaltic	–		–	–	–	**1.02**	**J**	2.06	U	0.790	U	1.580	U	0.995	U	**2.81**		**6,330**	**22.8**		**34.8**	
		02/07/19	PES	Peristaltic	**3,100**	**zJ+**	–	–	–	**0.811**		0.412	U	0.158	U	0.316	U	0.199	U	**1.77**		**6,990**	**25.7**		**46.0**	
		07/17/19	PES	Peristaltic	**2,560**	**zJ+**	–	–	–	**0.172**	**J**	0.412	U	0.158	U	0.316	U	**3.14**		**20.4**		**4,940**	**13.1**		**103**	
		10/22/19	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	1.99	U	0.153	U	**1,420**	**4.45**		**66.2**	
		11/11/19	Farallon	Unknown	–		–	–	–	–		–		–		–		50	U	50	U	**8,200**	50	U	**950**	
		01/14/20	PES	Bladder	–		–	–	–	0.896	U	4.12	U	1.58	U	3.16	U	1.99	U	1.53	U	**10,300**	**32.9**		**1,410**	
(split)		01/14/20	Farallon	Bladder	–		–	–	–	–		–		–		–		50	U	50	U	**8,000**	50	U	**1,400**	
		02/18/20	Farallon	Peristaltic	–		–	–	–	–		–		–		–		50	U	50	U	**9,600**	50	U	**1,800**	
		03/24/20	Farallon	Peristaltic	–		–	–	–	–		–		–		–		20	U	20	U	**4,100**	20	U	**200**	
		04/27/20	PES	Peristaltic	–		–	–	–	9.41	U	27.8	U	13.7	U	17.4	U	30.0	U	19.0	U	**4,320**	14.9	U	**75.9**	
(split)		04/27/20	Farallon	Peristaltic	–		–	–	–	–		–		–		–		20	U	20	U	**3,500**	20	U	**94**	
		05/19/20	Farallon	Unknown	–		–	–	–	–		–		–		–		20	U	20	U	**3,700**	20	U	**110**	
		07/28/20	PES	Bladder	–		–	–	–	9.41	U	27.8	U	13.7	U	17.4	U	**212**		**1,540**		**3,100**	14.9	U	**76.0**	
(split)		07/28/20	Farallon	Bladder	–		–	–	–	–		–		–		–		**170**		**1,300**		**2,300**	10	U	**82**	
		09/17/20	Farallon	Unknown	–		–	–	–	–		–		–		–		**390**		**1,500**		**1,900**	10	U	**45**	
		11/24/20	PES	Bladder	–		–	–	–	1.60	U	5.00	U	2.12	U	19.1	U	**706**		**1,380**		**1,290**	**8.30**	**J**	**11.9**	
		12/03/20	Farallon	Unknown	–		–	–	–	–		–		–		–		**480**		**800**		**540**	4.0	U	**6.4**	
		02/10/21	PES	Peristaltic	–		–	–	–	0.0160	U	0.0500	U	0.0212	U	0.191	U	**3.04**		**4.18**		**39.1**	**0.0780**	**J**	**0.0710**	**J**
(split)		02/10/21	Farallon	Peristaltic	–		–	–	–	–		–		–		–		**2.7**		**8.4**		**26**	0.20	U	0.20	U
		05/25/21	PES	Peristaltic	–		–	–	–	**0.331**		0.127	U	0.0212	U	0.191	U	**249**		**944**		**1,380**	**8.60**		**6.91**	
MW122	Alley E of Seattle Roy Aloha Shops	12/23/13	SES	Peristaltic	–		–	–	–	0.35	U	1	U	1	U	3	U	1	U	1	U	1	U	1	U	0.2	U
(-75 to -89)		10/20/15	SES	Peristaltic	–		–	–	–	–		–		–		–		1	U	1	U	1	U	1	U	0.2	U
		02/02/16	SES	Peristaltic	–		–	–	–	–		–		–		–		1	U	1	U	1	U	1	U	0.2	U
		03/28/17	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		06/14/17	PES	Bladder	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**0.162**	**J**	0.0933	U	0.152	U	0.118	U
		04/06/18	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		10/14/19	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**0.289**	**J**	0.153	U	0.0933	U	0.152	U	0.118	U
		01/17/20	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	UJ
		04/07/20	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		07/24/20	PES	Peristaltic	–		–	–	–	0.0160	U	**0.0880**	**J**	0.0212	U	0.191	U	**0.0540**	**J**	0.0160	U	0.0276	U	0.0572	UJ	0.0273	U
		11/06/20	PES	Peristaltic	–		–	–	–	0.0160	U	0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
		05/03/21	PES	Peristaltic	–		–	–	–	0.0160	U	0.0500	U	0.0212	U	0.191	U	**0.0360**	**J**	0.0160	U	0.0276	U	0.0572	U	0.0273	U
MW123	Westlake Ave N ROW, W side	12/23/13	SES	Peristaltic	–		–	–	–	0.35	U	1	U	1	U	3	U	1	U	1	U	1	U	1	U	0.2	U
(-42.5 to -52.5)		04/01/17	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		06/24/17	PES	Bladder	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		04/14/18	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**0.284**	**J**	0.153	U	0.0933	U	0.152	U	0.118	U
		10/18/19	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		01/22/20	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U

Table G-9

Groundwater Petroleum Hydrocarbons and CVOCs in Deep Zone Wells
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																					
					GRO		DRO	ORO	DRO+ORO	Benzene		Toluene		Ethylbenzene		Total Xylenes		PCE		TCE		cDCE		tDCE		VC	
Preliminary Cleanup Level (PCUL)					800		500	500	500	5.0		640		700		1,600		5.0		4.0		16		100		0.29	
MW123 (continued)		05/05/20	PES	Peristaltic	–		–	–	–	0.0941	U	**0.293**	**J**	0.137	U	0.174	U	0.300	U	0.190	U	0.126	U	0.149	U	0.234	U
		07/30/20	PES	Peristaltic	–		–	–	–	**0.0388**	**J**	**1.62**		**0.141**		**0.948**		0.0280	U	0.0160	U	0.0276	UJ	0.0572	U	0.0273	U
		11/12/20	PES	Peristaltic	–		–	–	–	0.0160	U	**0.296**		**0.0217**	**J**	**0.236**	**J**	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
		05/26/21	PES	Peristaltic	–		–	–	–	0.0160	U	0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
MW124 (-53.8 to -63.8)	Valley St ROW, S side	12/26/13	SES	Bladder	–		–	–	–	0.35	U	1	U	1	U	3	U	1	U	1	U	1	U	1	U	0.2	U
		03/29/17	PES	Bladder	–		–	–	–	0.0896	U	0.785	U	0.158	U	0.316	U	**1.60**		**0.596**		**0.661**		0.152	U	0.118	U
(duplicate)		03/29/17	PES	Bladder	–		–	–	–	0.0896	U	0.675	U	0.158	U	0.316	U	**1.22**		**0.433**		**0.600**		0.152	U	0.118	U
		06/15/17	PES	Bladder	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		04/13/18	PES	Bladder	39.4	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		10/11/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		01/30/20	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		04/03/20	PES	Bladder	38.9	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		08/03/20	PES	Bladder	–		–	–	–	0.0160	U	**1.14**		**0.102**		**0.526**		0.0280	U	0.0160	U	0.0276	UJ	0.0572	UJ	0.0273	U
		11/18/20	PES	Bladder	–		–	–	–	0.0160	U	**0.464**		0.0212	U	0.191	U	**0.0480**	**J**	0.0160	U	0.0276	U	0.0572	U	0.0273	U
		06/08/21	PES	Bladder	–		–	–	–	0.0160	U	**0.111**	**J**	0.0212	U	0.191	U	**0.0480**	**J**	0.0160	U	0.0276	U	0.0572	U	0.0273	U
MW128 (-30.8 to -40.8)	Westlake Ave N ROW, E side	01/13/14	SES	Peristaltic	–		–	–	–	0.35	U	1.0	U	1.0	U	3.0	U	1.0	U	1.0	U	**960**	**ve**	1.0	U	**290**	**ve**
		04/22/15	SES	Peristaltic	–		–	–	–	–		–		–		–		1.0	U	1.0	U	**150**		1.0	U	**59**	
		10/20/15	SES	Peristaltic	–		–	–	–	–		–		–		–		1.0	U	1.0	U	**7.0**		1.0	U	**95**	
		02/02/16	SES	Peristaltic	–		–	–	–	–		–		–		–		1.0	U	1.0	U	**70**		1.0	U	**140**	
		03/29/17	PES	Peristaltic	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**7.16**		0.152	U	**72.4**	
		06/21/17	PES	Bladder	–		–	–	–	**3.84**		**0.541**		0.158	U	0.316	U	0.199	U	0.153	U	**109**		0.152	U	**195**	
		04/09/18	PES	Peristaltic	–		–	–	–	**28.3**		0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**3.07**		0.152	U	**31.0**	
		12/30/18	Farallon	Unknown	–		–	–	–	–		–		–		–		1.0	U	1.0	U	**5.0**		1.0	U	**110**	
		07/18/19	PES	Peristaltic	–		–	–	–	**12.2**		0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**1.88**		0.152	U	**108**	
		10/11/19	PES	Peristaltic	–		–	–	–	**0.984**		0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.619**		0.152	U	**13.3**	
(duplicate)		10/11/19	PES	Peristaltic	–		–	–	–	**1.34**		0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.841**		0.152	U	**24.1**	
		11/11/19	Farallon	Unknown	–		–	–	–	–		–		–		–		0.40	U	0.40	U	**1.4**		0.40	U	**60**	
		01/20/20	PES	Peristaltic	–		–	–	–	**17.8**		0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**1.67**		0.152	U	**47.4**	
		02/18/20	Farallon	Peristaltic	–		–	–	–	–		–		–		–		0.40	U	0.40	U	**1.4**		0.40	U	**54**	
		04/27/20	PES	Peristaltic	–		–	–	–	**18.3**		0.278	U	0.137	U	0.174	U	0.300	U	0.190	U	**1.04**		0.149	U	**53.2**	
		06/29/20	PES	Peristaltic	–		–	–	–	**16.9**		0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	**0.618**		0.0572	U	**31.3**	
(split)		06/29/20	Farallon	Peristaltic	–		–	–	–	–		–		–		–		0.20	U	0.20	U	**0.51**		0.20	U	**34**	
		08/26/20	Farallon	Unknown	–		–	–	–	–		–		–		–		0.20	U	0.20	U	**0.46**		0.20	U	**29**	
		11/09/20	PES	Bladder	–		–	–	–	**17.0**		**0.132**	**J**	0.0212	U	0.191	U	0.0280	U	0.0160	U	**0.671**		0.0572	U	**56.1**	
		12/20/20	Farallon	Unknown	–		–	–	–	–		–		–		–		0.20	U	0.20	U	**0.40**		0.20	U	**46**	
		02/11/21	Farallon	Unknown	–		–	–	–	–		–		–		–		0.40	U	0.40	U	0.40	U	0.40	U	**55**	
		05/25/21	PES	Peristaltic	–		–	–	–	**14.2**		0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	**37.3**	
MW-133 (-88.9 to -98.9)	Property, SW quadrant	09/25/17	PES	Bladder	41.2	U	–	–	–	0.0896	U	**0.748**		0.158	U	0.316	U	**12.7**		**16.2**		**13.3**		**1.13**		**0.239**	**J**
		04/25/18	PES	Bladder	31.6	U	–	–	–	0.0896	U	**0.837**		0.158	U	0.316	U	**0.646**		**0.516**		**10.7**		**0.315**	**J**	**3.51**	
		10/26/18	PES	Bladder	**458**	**zJ+**	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**1.92**	**J+**	**1.63**	**J+**	**7.94**		**0.257**	**J**	**3.43**	
		12/12/18	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**1.71**		**2.75**		**7.88**		**0.454**	**J**	**5.95**	
		02/01/19	PES	Bladder	46.4	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**22.4**		**9.29**		**12.4**		**0.588**		**4.36**	
		03/13/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**4.45**		**5.92**		**7.48**		**0.483**	**J**	**10.8**	
		Decommissioned March 2019																								

Table G-9

Groundwater Petroleum Hydrocarbons and CVOCs in Deep Zone Wells
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																					
					GRO		DRO	ORO	DRO+ORO	Benzene		Toluene		Ethylbenzene		Total Xylenes		PCE		TCE		cDCE		tDCE		VC	
Preliminary Cleanup Level (PCUL)					800		500	500	500	5.0		640		700		1,600		5.0		4.0		16		100		0.29	
MW-137	Property, SW quadrant	09/25/17	PES	Bladder	58.5	U	–	–	–	0.0896	U	**3.90**		0.158	U	0.316	U	**15.0**		**19.1**		**62.0**		0.152	U	0.118	U
(-53.3 to -63.3)		04/12/18	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**1.79**		0.152	U	**4.26**	
		10/26/18	PES	Bladder	86.9	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**0.896**	J+	0.463	U	**0.893**	J+	0.152	U	0.118	U
		12/12/18	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.437**	J	0.152	U	**0.357**	J
		02/01/19	PES	Bladder	58.4	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**1.48**		0.153	U	**0.616**		0.152	U	**0.365**	J
		03/11/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**0.344**	J	0.153	U	**0.275**	J	0.152	U	**0.179**	J
		Decommissioned March 2019																								
MW-138	Dexter Ave N ROW, E side	09/21/17	PES	Bladder	**63.3**	J	–	–	–	0.179	U	**2.60**		0.316	U	0.632	U	0.398	U	0.306	U	0.187	U	0.304	U	0.236	U
(-47.5 to -57.5)		04/11/18	PES	Bladder	91.1	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		10/29/18	PES	Bladder	38.5	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	**0.169**	J
		01/03/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	**0.442**	J	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		03/14/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**1.49**		**0.167**	J	**0.262**	J	0.152	U	0.118	U
		04/22/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	UJ
		07/19/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		10/21/19	PES	Bladder	**92.7**	J	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		01/27/20	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		05/08/20	PES	Bladder	53.4	U	–	–	–	0.0941	U	0.278	U	0.137	U	0.174	U	0.300	U	0.190	U	0.126	U	0.149	U	0.234	U
		07/27/20	PES	Bladder	–		–	–	–	0.0160	U	**0.468**		**0.0657**	J	**0.356**		0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
		11/18/20	PES	Bladder	–		–	–	–	0.0160	U	0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
		02/11/21	PES	Bladder	–		–	–	–	**0.0240**	J	**0.481**		**0.105**		**0.686**		0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
		06/07/21	PES	Bladder	–		–	–	–	**0.100**		**0.589**		**0.0370**	J	0.191	U	0.0280	U	0.0160	U	**0.0730**	J	0.0572	U	**0.0760**	J
MW-140	Roy St ROW, N side	09/22/17	PES	Bladder	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**0.450**	J	**0.477**	J	0.152	U	0.118	U
(duplicate)		09/22/17	PES	Bladder	–		–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**0.456**	J	**0.523**		0.152	U	0.118	U
(-78.9 to -88.9)		04/12/18	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**0.402**	J+	**0.572**	J+	**2.47**	J+	0.152	U	**0.246**	J+
		Decommissioned September 2018																								
MW-141	Property, SE quadrant	09/22/17	PES	Bladder	–		–	–	–	0.0896	U	**0.941**		0.158	U	0.316	U	0.199	U	0.153	U	**0.345**	J	0.152	U	**0.457**	J
(-55.4 to -65.4)		04/12/18	PES	Submersible	**326**	zJ+	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**71.3**	J+	**25.6**	J+	**91.6**	J+	**5.68**	J+	**7.01**	J+
		10/25/18	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**3.10**		0.152	U	0.118	U
		12/12/18	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**1.46**		0.152	U	**0.520**	
		01/30/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.479**	J	0.152	U	0.118	U
		03/11/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**0.701**		0.153	U	**1.30**		0.152	U	**0.557**	
		Decommissioned March 2019																								
MW-153	Roy St ROW, S side	05/01/18	PES	Bladder	**31.6**	J	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**0.756**		0.153	U	**0.612**		0.152	U	**9.56**	
(-65.3 to -75.3)		01/22/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**1.41**		0.152	U	**15.9**	
		04/24/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**1.07**		0.152	U	**2.69**	J
(duplicate)		04/24/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.975**		0.152	U	**1.66**	J
		07/22/19	PES	Bladder	31.6	U	–	–	–	**0.177**	J	**0.716**		**0.227**	J	**0.819**	J	0.199	U	**0.190**	J	**0.384**	J	0.152	U	**0.235**	J
		10/15/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		01/21/20	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		04/30/20	PES	Bladder	**38.2**	J	–	–	–	0.0941	U	0.278	U	0.137	U	0.174	U	0.300	U	0.190	U	0.126	U	0.149	U	0.234	U
		07/15/20	PES	Bladder	–		–	–	–	0.0160	U	**1.79**		0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
		11/09/20	PES	Bladder	–		–	–	–	0.0160	U	**0.314**		0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	**0.333**	
		02/09/21	PES	Bladder	–		–	–	–	**0.0200**	J	**0.860**		**0.147**		**1.01**		0.0280	U	0.0160	U	**0.105**		0.0572	U	**2.42**	
(duplicate)		02/09/21	PES	Bladder	–		–	–	–	**0.0220**	J	**0.918**		**0.160**		**1.02**		0.0280	U	0.0160	U	**0.107**		**0.0680**	J	**2.48**	
		05/10/21	PES	Bladder	–		–	–	–	0.0160	U	0.0500	U	**0.0430**	J	**0.323**		0.0280	U	0.0160	U	**0.101**		0.0572	U	**1.15**	J-
MW-158A	8th Ave N ROW, E side	04/30/18	PES	Bladder	**101**		–	–	–	0.0896	U	**2.66**		0.158	U	0.316	U	**17.7**		**18.7**		**59.6**	J	**0.205**	J	**8.91**	
(-47.2 to -58.5)		01/24/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**0.325**	J	**2.54**		0.152	U	**7.58**	
		04/25/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**0.240**	J	**0.974**		0.152	U	**3.08**	J

Table G-9

Groundwater Petroleum Hydrocarbons and CVOCs in Deep Zone Wells
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																					
					GRO		DRO	ORO	DRO+ORO	Benzene		Toluene		Ethylbenzene		Total Xylenes		PCE		TCE		cDCE		tDCE		VC	
Preliminary Cleanup Level (PCUL)					800		500	500	500	5.0		640		700		1,600		5.0		4.0		16		100		0.29	
MW-158A (continued)		07/19/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**0.177**	**J**	**0.290**	**J**	0.152	U	**1.24**	
		10/16/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**0.318**	**J**	**0.848**		0.152	U	**2.18**	
		01/21/20	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	**0.195**	**J**
		04/24/20	PES	Bladder	38.0	U	–	–	–	0.0941	U	0.278	U	0.137	U	0.174	U	0.300	U	**0.251**	**J**	**1.15**		0.149	U	**1.45**	
		07/15/20	PES	Bladder	–		–	–	–	**0.0520**		**1.11**		0.0212	U	**0.366**		0.0280	U	**0.247**		**0.379**		0.0572	U	**0.882**	
		11/23/20	PES	Bladder	–		–	–	–	0.0240	U	0.104	U	0.0212	U	0.191	U	0.0280	U	**0.0840**		**0.127**		0.0572	U	**0.447**	
		02/02/21	PES	Bladder	–		–	–	–	**0.0270**	**J**	**0.532**		**0.197**		**1.17**		0.0280	U	**0.0680**		**0.0890**	**J**	0.0572	U	**0.526**	
		05/10/21	PES	Bladder	–		–	–	–	0.0160	U	**0.0750**	**J**	0.0212	U	0.191	U	0.0280	U	**0.0920**		**0.0900**	**J**	0.0572	U	**0.326**	**J-**
MW-160 (-76.5 to -86.5)	8th Ave N ROW, W side	05/21/18	PES	Bladder	**51.0**	**J**	–	–	–	0.0896	U	0.412	U	0.158	U	**0.342**	**J**	**0.380**	**J**	**0.835**		**2.96**		0.152	U	0.118	U
		01/25/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**0.263**	**J**	**5.08**		0.152	U	0.118	U
		05/01/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**0.513**		**2.58**		0.152	U	0.118	UJ
		07/23/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.217**	**J**	0.152	U	**0.326**	**J**
		10/17/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.445**	**J**	0.152	U	0.118	U
		01/29/20	PES	Bladder	35.0	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**0.195**	**J**	**0.176**	**J**	0.152	U	**0.744**	
		04/01/20	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**3.18**		**2.09**		0.152	U	0.118	U
		08/03/20	PES	Bladder	–		–	–	–	**0.0180**	**J**	**1.04**		**0.0670**	**J**	**0.321**		**0.203**		**3.61**		**15.2**		**0.144**	**J**	**1.17**	**J**
		11/30/20	PES	Bladder	–		–	–	–	0.0160	U	**0.177**	**J**	**0.108**		**0.827**		**0.828**		**10.2**		**43.2**		**0.228**		**3.59**	
		02/05/21	PES	Bladder	–		–	–	–	0.0310	U	**0.526**		**0.177**		**1.17**		**0.0550**	**J**	**1.65**		**26.4**		**0.192**	**J+**	**17.1**	**J**
		05/12/21	PES	Bladder	–		–	–	–	0.0160	U	**0.237**		0.0212	U	0.191	U	0.0280	U	**0.353**		**11.1**		**0.0700**	**J**	**4.05**	
MW-161 (-78.9 to -88.9)	8th Ave N ROW, W side	05/21/18	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	**0.329**	**J**	**2.01**		**1.79**		**1.89**		0.152	U	0.118	U
		01/25/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**0.472**	**J**	**1.66**		**1.26**		0.152	U	0.118	U
		05/01/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**0.482**	**J**	**1.66**		**1.15**		0.152	U	0.118	UJ
		07/18/19	PES	Bladder	31.6	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**0.264**	**J**	**1.53**		**1.58**		0.152	U	0.118	U
		10/14/19	PES	Bladder	**54.7**	**J**	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**0.978**		**1.30**		0.152	U	0.118	U
		01/28/20	PES	Bladder	72.8	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	**6.05**		**9.02**		**0.388**	**J**	**1.10**	
		04/03/20	PES	Bladder	49.3	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**16.7**		**27.0**		**23.4**		**1.27**		**1.92**	
		07/31/20	PES	Bladder	–		–	–	–	0.0160	U	**0.0536**	**J**	0.0212	U	0.191	U	**40.6**		**42.5**		**59.2**	**J**	**1.17**	**J**	**4.27**	
		12/01/20	PES	Bladder	–		–	–	–	0.0160	U	**0.0740**	**J**	0.0212	U	0.191	U	**49.0**		**50.3**		**84.2**		**1.74**		**5.47**	
		02/05/21	PES	Bladder	–		–	–	–	0.0160	U	**0.0590**	**J**	0.0212	U	0.191	U	**24.4**		**55.8**		**85.8**		**2.32**	**J**	**9.28**	**J**
		05/25/21	PES	Bladder	–		–	–	–	0.0160	U	0.165	U	0.0212	U	0.191	U	**1.08**		**28.3**		**69.8**		**1.11**		**5.35**	
MW-162 (-61.6 to -71.6)	Property, NE quadrant	02/05/19	PES	Bladder	–		–	–	–	1.00	U	1.00	U	1.00	U	1.00	U	**2,800**		**613**		**1,070**		**9.58**		**128**	
		03/12/19	PES	Peristaltic	**690**	**zJ+**	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**613**		**538**		**758**		**2.63**		**46.5**	
		Decommissioned March 2019																								
MW-163 (duplicate) (-61.0 to -71.0)	Property, NW quadrant	02/05/19	PES	Bladder	–		–	–	–	1.00	U	1.00	U	1.00	U	1.00	U	**218**		**150**		**42.2**		1.00	U	**2.95**	
		02/05/19	PES	Bladder	–		–	–	–	1.00	U	1.00	U	1.00	U	1.00	U	**220**		**153**		**40.3**		1.00	U	**3.45**	
		03/12/19	PES	Bladder	**319**	**zJ+**	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**282**		**334**		**56.9**		**2.87**		**1.10**	
		Decommissioned March 2019																								
MW-164 (-59.9 to -69.9)	Property, SW quadrant	02/05/19	PES	Bladder	–		–	–	–	1.00	U	**1.80**		1.00	U	1.00	U	**871**		**372**		**385**		**3.41**		**4.41**	
		03/12/19	PES	Bladder	**565**	**zJ+**	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**444**		**327**		**529**		**4.24**		**7.80**	
		Decommissioned March 2019																								
MW-304 (-47.6 to -57.6)	Dexter Ave N ROW, E side	10/21/19	PES	Bladder	**97.9**	**J**	–	–	–	0.0896	U	**0.728**		0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		01/27/20	PES	Bladder	42.2	U	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
		05/07/20	PES	Bladder	31.6	U	–	–	–	0.0941	U	0.278	U	0.137	U	0.174	U	0.300	U	0.190	U	0.126	U	0.149	U	0.234	U
		07/27/20	PES	Bladder	–		–	–	–	0.0160	U	**2.63**		0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
		05/18/21	PES	Bladder	–		–	–	–	0.0160	U	**0.357**		0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U

Table G-9

Groundwater Petroleum Hydrocarbons and CVOCs in Deep Zone Wells
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																					
					GRO	DRO	ORO	DRO+ORO	Benzene		Toluene		Ethylbenzene		Total Xylenes		PCE		TCE		cDCE		tDCE		VC	
Preliminary Cleanup Level (PCUL)					800	500	500	500	5.0		640		700		1,600		5.0		4.0		16		100		0.29	
MW-319	9th Ave N ROW, W side	10/08/19	PES	Bladder	–	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**0.609**		**8.12**		**53.4**		0.152	U	**5.76**	
(-42.8 to -52.8)		01/16/20	PES	Peristaltic	–	–	–	–	0.0896	U	0.412	U	0.158	U	0.316	U	**0.414**	**J**	**11.4**		**63.7**		0.152	U	**6.78**	
		04/27/20	PES	Bladder	–	–	–	–	0.0941	U	0.278	U	0.137	U	0.174	U	0.300	U	**10.7**		**54.1**		0.149	U	**4.52**	
		07/27/20	PES	Bladder	–	–	–	–	**0.0336**	**J**	**0.399**		**0.0450**	**J**	**0.207**	**J**	**0.0933**	**J**	**13.6**		**49.2**		**0.0806**	**J**	**4.77**	
		11/12/20	PES	Bladder	–	–	–	–	0.0160	U	0.0500	UJ	0.0212	U	0.191	U	**0.110**		**13.9**		**47.6**		0.0572	U	**4.58**	J+
		05/19/21	PES	Peristaltic	–	–	–	–	0.0160	U	0.0700	U	0.0212	U	0.191	U	**0.0900**	**J**	**8.52**		**37.4**		**0.104**	**J**	**4.16**	
MW-323	9th Ave N ROW, W side	10/09/19	PES	Peristaltic	–	–	–	–	0.0896	U	**4.97**		0.158	U	0.316	U	0.199	U	**0.891**		**66.5**		0.152	U	**13.4**	
(-65.4 to -75.4)		01/20/20	PES	Peristaltic	–	–	–	–	0.0896	U	**0.549**		0.158	U	0.316	U	0.199	U	**0.178**	**J**	**229**		0.152	U	**64.9**	
		04/23/20	PES	Bladder	–	–	–	–	0.0941	U	0.278	U	0.137	U	0.174	U	0.300	U	0.190	U	**5.11**		0.149	U	**4.14**	
		07/07/20	PES	Bladder	–	–	–	–	0.0160	U	**1.76**		0.0212	U	0.191	U	0.0280	U	**0.0300**	**J**	**2.55**		0.0572	U	**4.58**	
		11/24/20	PES	Bladder	–	–	–	–	0.0160	U	0.0960	U	0.0212	U	0.191	U	0.0280	U	**0.0260**	**J**	**2.68**		0.0572	U	**4.89**	
		05/20/21	PES	Peristaltic	–	–	–	–	0.0160	U	0.114	U	0.0212	U	0.191	U	0.0280	U	**0.0900**		**115**		**0.111**	**J**	**31.4**	
MW-324	Roy St ROW, N side	10/02/19	PES	Bladder	–	–	–	–	**0.401**	**J**	**5.45**		0.158	U	0.316	U	0.199	U	**0.642**		**1,550**		**3.21**		**61.9**	
(-32.1 to -42.1)		01/20/20	PES	Peristaltic	–	–	–	–	4.48	U	20.6	U	7.90	U	15.8	U	9.95	U	7.65	U	**3,170**		7.60	U	**113**	
		04/24/20	PES	Bladder	–	–	–	–	4.71	U	13.9	U	6.85	U	8.70	U	15.0	U	9.50	U	**8,520**		**16.8**	**J**	**362**	
		07/07/20	PES	Bladder	–	–	–	–	**1.25**	**J**	2.50	U	1.06	U	9.55	U	1.400	U	0.800	U	**8,410**		**13.6**		**244**	
		11/13/20	PES	Bladder	–	–	–	–	**2.51**		2.50	U	1.06	U	9.55	U	1.40	U	0.800	U	**7,210**		**13.7**		**184**	
		05/20/21	PES	Peristaltic	–	–	–	–	0.800	U	2.50	U	1.06	U	9.55	U	1.40	U	**1.95**	**J**	**3,470**		**10.5**		**45.6**	
MW-326	Mercer St ROW, N side	10/03/19	PES	Bladder	–	–	–	–	0.0896	U	**1.31**		0.158	U	0.316	U	**0.769**		**0.297**	**J**	**6.87**		0.152	U	0.118	U
(-48.7 to -58.7)		01/17/20	PES	Bladder	–	–	–	–	**0.113**	**J**	0.412	U	0.158	U	0.316	U	**0.834**		**0.470**	**J**	**9.38**		0.152	U	0.118	UJ
		04/21/20	PES	Bladder	–	–	–	–	**0.108**	**J**	0.278	U	0.137	U	0.174	U	0.300	U	0.190	U	**0.971**		0.149	U	**0.515**	**J**
		07/23/20	PES	Bladder	–	–	–	–	**0.0390**	**J**	**0.120**	**J**	0.0212	U	0.191	U	0.0280	U	**0.0430**		**0.277**		0.0572	U	**0.201**	
		11/02/20	PES	Bladder	–	–	–	–	**0.0740**		**0.165**	**J**	0.0212	U	0.191	U	0.0280	U	**0.0260**	**J**	**0.224**		0.0572	U	**0.332**	
		02/09/21	PES	Bladder	–	–	–	–	**0.0680**		**0.540**		**0.0570**	**J**	**0.427**		**0.183**		**0.263**	**J+**	**3.40**		0.0572	U	**0.182**	**J**
		05/18/21	PES	Bladder	–	–	–	–	0.0160	U	**0.206**		0.0212	U	0.191	U	**0.219**		**0.496**		**3.53**		0.0572	U	**0.109**	
MW-328	Lake Union Park, S end	10/02/19	PES	Bladder	–	–	–	–	**17.0**		**0.535**		0.158	U	0.316	U	0.199	U	0.153	U	**1.26**		0.152	U	**23.3**	
(-36.1 to -46.1)		01/17/20	PES	Peristaltic	–	–	–	–	**17.6**		**0.448**	**J**	0.158	U	0.316	U	**1.66**		0.153	U	**1.03**		0.152	U	**13.1**	**J**
		04/08/20	PES	Peristaltic	–	–	–	–	**9.53**		0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**0.631**		0.152	U	**11.1**	
		07/07/20	PES	Peristaltic	–	–	–	–	**10.3**		0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	**1.03**		0.0572	U	**20.7**	
		11/09/20	PES	Peristaltic	–	–	–	–	**0.630**		0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	**0.607**		0.0572	U	**7.99**	
		05/25/21	PES	Peristaltic	–	–	–	–	**6.19**		0.0540	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	**8.57**	
MW-329	Westlake Ave N ROW, E side	10/03/19	PES	Peristaltic	–	–	–	–	**0.206**	**J**	**0.435**	**J**	0.158	U	0.316	U	0.199	U	0.153	U	**9.25**		0.152	U	**28.8**	
(duplicate)		10/03/19	PES	Peristaltic	–	–	–	–	**0.215**	**J**	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**9.26**		0.152	U	**29.2**	
(-69.0 to -79.0)		01/20/20	PES	Peristaltic	–	–	–	–	**0.279**	**J**	0.412	U	0.158	U	0.316	U	0.199	U	0.153	U	**11.0**		0.152	U	**26.2**	
		04/27/20	PES	Bladder	–	–	–	–	**0.704**		**0.434**	**J**	0.137	U	0.174	U	0.300	U	0.190	U	**17.5**		0.149	U	**23.6**	
		08/03/20	PES	Bladder	–	–	–	–	**0.628**		**1.06**		**0.0290**	**J**	0.191	U	0.0280	U	0.0160	U	**14.7**		0.0572	UJ	**32.2**	
		11/09/20	PES	Bladder	–	–	–	–	**0.862**		**0.106**	**J**	0.0212	U	0.191	U	0.0280	U	0.0160	U	**21.0**		0.0572	U	**23.0**	
		05/25/21	PES	Peristaltic	–	–	–	–	**0.601**		0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	**15.2**		0.0572	U	**23.0**	
MW-336	Mercer St ROW, N side	05/05/20	PES	Bladder	–	–	–	–	0.0941	U	**0.318**	**J**	0.137	U	0.174	U	0.300	U	**0.304**	**J**	**57.1**		0.149	U	**6.03**	
(-51.6 to -61.6)		07/08/20	PES	Bladder	–	–	–	–	**0.0490**		**1.21**		0.0212	U	0.191	U	**0.600**		**6.08**		**61.1**		**0.127**		**7.71**	
		11/02/20	PES	Bladder	–	–	–	–	**0.215**		**0.301**		0.0212	U	0.191	U	**0.172**		**3.52**		**137**		**0.0910**	**J**	**5.80**	
		02/10/21	PES	Bladder	–	–	–	–	**0.0660**		**0.328**		**0.0550**	**J**	**0.225**	**J**	0.0280	U	**1.86**		**107**		**0.189**	**J**	**8.18**	
		05/26/21	PES	Peristaltic	–	–	–	–	**0.128**		0.0500	U	0.0212	U	0.191	U	**0.120**		**3.12**	**J+**	**150**		0.0572	U	**10.7**	
MW-341	Lake Union Park, S end	05/12/20	PES	Peristaltic	–	–	–	–	**16.2**		0.278	U	0.137	U	0.174	U	0.300	U	0.190	U	**41.4**		0.149	U	**10.4**	
(-66.8 to -76.8)		07/07/20	PES	Peristaltic	–	–	–	–	**15.6**		0.0500	U	0.0212	U	0.191	U	0.0280	U	**0.0500**		**32.9**		0.0572	U	**9.86**	
		11/09/20	PES	Peristaltic	–	–	–	–	**9.87**		**0.167**	**J**	0.0212	U	0.191	U	**0.0740**	**J**	**0.102**		**25.1**		0.0572	U	**5.99**	
		05/25/21	PES	Peristaltic	–	–	–	–	**17.6**		0.105	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	**2.43**		0.0572	U	**26.7**	

Table G-9

Groundwater Petroleum Hydrocarbons and CVOCs in Deep Zone Wells
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sampling Method	Analytical Results (micrograms per liter)																					
					GRO		DRO		ORO		DRO+ORO		Benzene		Toluene		Ethylbenzene		Total Xylenes		PCE		TCE		cDCE		tDCE		VC	
Preliminary Cleanup Level (PCUL)					**800**		**500**		**500**		**500**		**5.0**		**640**		**700**		**1,600**		**5.0**		**4.0**		**16**		**100**		**0.29**	
MW-342	Valley St ROW, S side	05/04/20	PES	Peristaltic	–		–		–		–		0.0941	U	**0.366**	**J**	0.137	U	0.174	U	0.300	U	0.190	U	**1.34**		0.149	U	**1.51**	
(-32.4 to -42.4)		07/30/20	PES	Peristaltic	–		–		–		–		**0.316**		**1.24**		**0.116**		**0.723**		0.0280	U	0.0160	U	**5.56**	**J**	0.0572	UJ	**3.12**	
		11/17/20	PES	Peristaltic	–		–		–		–		**0.113**		0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	**1.22**		0.0572	U	**1.87**	
		06/04/21	PES	Peristaltic	–		–		–		–		**0.526**		0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	**6.45**		0.0572	U	**2.54**	
MW-343	Valley St ROW, S side	05/04/20	PES	Peristaltic	–		–		–		–		**0.114**	**J**	**0.620**		0.137	U	**0.207**	**J**	0.300	U	0.190	U	0.126	U	0.149	U	0.234	U
(-71.5 to -81.5)		07/30/20	PES	Peristaltic	–		–		–		–		**0.0471**		**1.57**		**0.163**		**0.931**		0.0280	U	0.0160	U	0.0276	UJ	0.0572	UJ	0.0273	U
		11/24/20	PES	Peristaltic	–		–		–		–		0.0160	U	0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	0.0276	U	0.0572	U	0.0273	U
		06/04/21	PES	Peristaltic	–		–		–		–		**0.139**		0.0500	U	0.0212	U	0.191	U	0.0280	U	0.0160	U	**3.17**		0.0572	U	**3.81**	
Number of Samples					111		12		9		12		316		316		316		316		377		377		377		377		377	
Number of Detections					28		4		0		4		88		107		28		35		113		144		289		86		237	
Frequency of Detection					25%		33%		0%		33%		28%		34%		9%		11%		30%		38%		77%		23%		63%	
Maximum					140		480		0		480		44.1		5.45		0.227	J	1.18		2,800		1,540		10,300		32.9		1,800	
Minimum					31.6	U	50	U	250	U	50	U	0.0160	U	0.0500	U	0.0212	U	0.174	U	0.0280	U	0.0160	U	0.0276	U	0.0572	UJ	0.0273	U
Number of Samples Above SL					0		0		0		0		22		0		0		0		48		71		118		0		209	
Frequency of Detection Above SL					0%		0%		0%		0%		7%		0%		0%		0%		13%		19%		31%		0%		55%	

Notes:

PCULs from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021.

Detected results shown in **bold.**

Detections above the groundwater PCUL are shown in **bold and highlighted in gray.**

Petroleum hydrocarbons analyzed by EPA Method 418.1, NWTPH-HCID, or NWTPH-Gx, NWTPH-Dx, or 8015-M.

VOCs analyzed by EPA Method 601, 8010S, 8015, 8020, 8021B, 8240, 8260B, 8260C, or 8260D, or by Purge and Trap Gas Chromatogram/Mass Spectrometry.

cDCE = cis-1,2-Dichloroethene.

DRO = Diesel-range organics.

GRO = Gasoline-range organics.

HC = Hart Crowser.

ORO = Oil-range organics.

PCE = Perchloroethylene (Tetrachloroethene).

ROW = right-of-way.

SES = SES Strategies, Inc.

TCE = Trichloroethene.

tDCE = trans-1,2-Dichloroethene.

VC = Vinyl chloride.

Well screen elevations indicated below Sample Location in parentheses.

(--) = unknown screen elevation.

Laboratory and Results Notes:

Petroleum hydrocarbons analyzed by EPA Method 418.1, NWTPH-HCID, or NWTPH-Gx, NWTPH-Dx, or 8015-M.

VOCs analyzed by EPA Method 601, 8010S, 8015, 8020, 8021B, 8240, 8260B, 8260C, or 8260D, or by Purge and Trap Gas Chromatogram/Mass Spectrometry.

– = Not analyzed or results not available.

i = The presence of the analyte indicated may be due to carryover from previous sample injections.

J = The identification of the analyte is acceptable; the reported value is an estimate.

J+ = The result is an estimated quantity, but the result may be biased high.

J- = The result is an estimated quantity, but the result may be biased low.

ND = Not detected at a concentration exceeding laboratory reporting limit; detection limit not provided.

U = Not detected at or above the laboratory method detection limit (MDL).

z = No/low level gasoline/petroleum detection; result is likely elevated due to high detections of CVOCs.

Groundwater statistics are for data collected during the Remediation Investigation, 2017-2021.

Groundwater statistics for GRO exclude "z" qualified data.

Table G-10

Summary of Reconnaissance Groundwater Analytical Data
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sample Interval (FT BTOC)	Color Tec (µg/L)	Analytical Results (micrograms per liter, µg/L)									
						GRO	Benzene	Toluene	Ethylbenzene	Total Xylenes	PCE	TCE	cDCE	tDCE	VC
				Preliminary Cleanup Level (PCUL)	–	800	5.0	640	700	1,600	5.0	4	16	100	0.29
On Property															
B-2	Property	6/23/00	Retec	11.5	–	–	250 U	250 U	250 U	500 U	**37,000**	**600**	**4,100**	250 U	250 U
B-6	Property	6/24/00	Retec	14.5	–	–	50 U	50 U	50 U	100 U	**6,800**	**54**	**57**	50 U	50 U
B-7	Property	6/24/00	Retec	12.5	–	–	50 U	50 U	50 U	100 U	**21,000**	**310**	**880**	50 U	50 U
B-8	Property	6/24/00	Retec	8	–	–	–	–	–	–	**3,100**	50 U	50 U	–	50 U
B-9	Property	6/24/00	Retec	12	–	–	–	–	–	–	**120,000**	**210**	**270**	–	50 U
B-10	Property	6/24/00	Retec	12.5	–	–	–	–	–	–	**9,100**	**1,100**	**7,600**	–	**98**
B101/MW101	Property	7/11/12	SES	75 to 80	–	–	–	–	–	–	**32**	1 U	**2.9**	1 U	0.2 U
	(duplicate)	7/11/12	SES	75 to 80	–	–	–	–	–	–	**150**	**6.1**	**25**	1 U	**1.1**
		7/12/12	SES	95 to 100	–	–	–	–	–	–	**3.4**	1 U	1 U	1 U	0.2 U
		7/12/12	SES	110 to 120	–	–	–	–	–	–	1 U	1 U	1 U	1 U	0.2 U
		7/12/12	SES	134 to 139	–	–	–	–	–	–	1 U	1 U	1 U	1 U	0.2 U
B-205	Property, NE quadrant	8/30/17	PES	40 - 42	65,000	**6,550 z**	8.96 U	**55.6**	15.8 U	31.6 U	**10,300**	**1,130**	**5,670**	**30.1 J**	**1,010**
B-211	Property, SW quadrant	8/18/17	PES	85 - 87[a]	–	–	–	–	–	–	–	–	–	–	–
		8/18/17	PES	100 - 102[b]	900	–	–	–	–	–	–	–	–	–	–
		8/21/17	PES	120 - 122	–	**2,880 z**	**1.65**	**297**	**0.557**	**1.67**	**19.8**	**8.34**	**4.86**	**0.168 J**	**0.160 J**
DB01	Property	3/18/13	SES	35 to 40	–	–	–	–	–	–	**1.4**	1 U	**2.4**	1 U	0.2 U
DB02	Property	3/18/13	SES	39 to 44	–	–	–	–	–	–	**140**	**19**	**14.0**	1 U	**0.35**
DB03	Property	3/27/13	SES	55 to 60	–	–	–	–	–	–	**6,700**	**420**	**420**	1 U	**12**
DB04	Property	3/22/13	SES	55 to 60	–	–	–	–	–	–	**15**	1 U	1 U	1 U	0.2 U
DB05	Property	3/26/13	SES	65 to 70	–	–	–	–	–	–	**1,400**	**11**	**1.7**	1 U	0.2 U
DB05A	Property	3/28/13	SES	40 to 45	–	–	–	–	–	–	**230,000**	**790 ve**	**42**	1 U	**1.2**
DB06	Property	3/25/13	SES	75 to 80	–	–	–	–	–	–	**170**	**4.4**	**5.0**	1 U	0.2 U
DB07	Property	3/28/13	SES	65 to 80	–	–	–	–	–	–	**15,000**	1,000 U	1,000 U	1,000 U	200 U
DB08	Property	3/21/13	SES	65 to 70	–	–	–	–	–	–	**7,300**	**1,100**	**1,300**	10 U	**38.0**
DB09	Property	3/19/13	SES	35 to40	–	–	–	–	–	–	**5,000**	**400**	**700**	**3.1**	**4.8**
		3/19/13	SES	65 to 70	–	–	–	–	–	–	**1,900**	**460**	**460**	1 U	**2.3**
DB10	Property	3/29/13	SES	35 to 40	–	–	–	–	–	–	**200,000**	**1,700**	1,000 U	1,000 U	200 U
		4/1/13	SES	65 to 70	–	–	–	–	–	–	**6,900**	100 U	100 U	100 U	20 U
DB12	Property	4/3/13	SES	10 to 15	–	–	–	–	–	–	**170,000**	**4,800**	**3,100**	2,000 U	400 U
		4/3/13	SES	40 to 45	–	–	–	–	–	–	**46,000**	**1,100**	1,000 U	1,000 U	200 U
DB13	Property	4/3/13	SES	10 to 15	–	–	–	–	–	–	**2,500**	**100**	**160**	**1.8**	0.2 U
		4/3/13	SES	40 to 45	–	–	–	–	–	–	**8,200**	**800 ve**	**430 ve**	1 U	**3.0**
DB14	Property	4/4/13	SES	10 to 15	–	**7,200**	**100**	40 U	**90**	**130**	–	–	–	–	–
		4/4/13	SES	40 to 45	–	–	–	–	–	–	**470**	**210**	**840**	100 U	**140**
IW06	Property	1/15/15	SES	70	–	–	–	–	–	–	**1,600**	**33**	**73**	1 U	**2.3**
MW-133	Property, SW quadrant	8/15/17	PES	80 to 82	–	**2,990 Jz**	**0.808**	**774**	**0.228 J**	**0.708 J**	**6,690**	**797**	**182**	**3.00**	**46.2**
		8/15/17	PES	90 to 92	–	**2,210 Jz**	**64.3**	**711**	**1.44 J**	**2.92 J**	**413**	**34.4**	**22.2**	0.760 U	**1.56 J**
		8/16/17	PES	100.5 - 102.5[a]	390	–	–	–	–	–	–	–	–	–	–
MW-137	Property, SW quadrant	8/31/17	PES	76 - 78	<3	**745**	**0.658 J**	**151**	0.790 U	1.58 U	0.995 U	0.765 U	**4.46**	0.760 U	0.590 U
		8/31/17	PES	76 - 78 (dup)	–	**631**	0.448 U	**105**	0.790 U	1.58 U	0.995 U	0.765 U	**2.86**	0.760 U	0.590 U
		9/1/17	PES	107 - 109	<3	31.6 U	0.0896 U	**41.1**	0.158 U	0.316 U	0.199 U	0.153 U	0.0933 U	0.152 U	0.118 U
MW-141	Property, SE quadrant	9/19/17	PES	105 - 107	<3	–	**0.286 J**	**88.5**	**0.158 J**	**0.472 J**	0.199 U	0.153 U	**0.148 J**	0.152 U	0.118 U
W-MW-04	Property, NE quadrant	1/28/12	WW	10 to 20	–	–	**0.7**	**0.2 J**	0.2 U	**0.3 J**	**19**	**8.4**	**37**	**0.4**	**37**
		1/28/12	WW	30 to 40	–	–	**0.2**	**0.2 J**	0.2 U	**0.1 J**	**2,800**	**26**	**47**	**0.4**	**12**
		1/28/12	WW	50 to 60	–	–	**0.4**	**0.6**	**0.1 J**	**0.6 J**	**12,000**	**230**	**270**	**0.2**	**3.4**

Table G-10

Summary of Reconnaissance Groundwater Analytical Data
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sample Interval (FT BTOC)	Color Tec (µg/L)	Analytical Results (micrograms per liter, µg/L)															
						GRO		Benzene		Toluene		Ethylbenzene		Total Xylenes		PCE		TCE		cDCE		tDCE		VC	
Preliminary Cleanup Level (PCUL)					–	**800**		**5.0**		**640**		**700**		**1,600**		**5.0**		**4**		**16**		**100**		**0.29**	
Off Property																									
B102/MW102	Property	7/17/12	SES	25 to 30	–	–		–		–		–		–		**5.0**		**2.5**		**9.0**		1	U	**0.84**	
		7/17/12	SES	25 to 30	–	–		–		–		–		–		1	U	1	U	1	U	1	U	0.2	U
		7/17/12	SES	45 to 50	–	–		–		–		–		–		1	U	1	U	**2.4**		1	U	**0.20**	
		7/17/12	SES	45 to 50	–	–		–		–		–		–		1	U	1	U	**1.2**		1	U	0.2	U
		7/19/12	SES	85 to 90	–	–		–		–		–		–		1	U	1	U	1	U	1	U	0.2	U
		7/19/12	SES	85 to 90	–	–		–		–		–		–		1	U	1	U	1	U	1	U	0.2	U
B103/MW103	Alley Between 8th and 9th Ave	7/25/12	SES	20 to 25	–	–		–		–		–		–		1	U	1	U	1	U	1	U	0.2	U
		7/25/12	SES	20 to 25	–	–		–		–		–		–		1	U	1	U	1	U	1	U	0.2	U
		7/25/12	SES	35 to 40	–	–		–		–		–		–		**1,800**		**860**		**400**		**2.4**		**42**	
		7/25/12	SES	35 to 40	–	–		–		–		–		–		**840**		**350**		**140**		1	U	**14**	
		7/26/12	SES	75 to 80	–	–		–		–		–		–		**320**		**62**		**100**		1	U	**3.4**	
		7/26/12	SES	75 to 80	–	–		–		–		–		–		**170**		**50**		**85**		1	U	**2.3**	
B104/MW104	8th Ave ROW	7/31/12	SES	55 to 60	–	–		**0.77**		**3.4**		1	U	3	U	**900**		**150**		**480**		1	U	**17**	
		7/31/12	SES	75 to 80	–	–		**1.0**		**2.6**		1	U	3	U	**220**		**45**		**180**		1	U	**6.1**	
		8/1/12	SES	95 to 100	–	–		–		–		–		–		**15**		**5.3**		**11**		1	U	**0.24**	
B105/MW105	Roy St	8/9/12	SES	75 to 80	–	–		–		–		–		–		1	U	1	U	1	U	1	U	0.2	U
		8/10/12	SES	95 to 100	–	–		–		–		–		–		1	U	1	U	1	U	1	U	0.2	U
B106/MW106	SDOT property south of Roy Street	8/14/12	SES	30 to 35	–	–		–		–		–		–		**8.2**		1	U	**1.0**		1	U	**0.36**	
		8/14/12	SES	45 to 50	–	–		–		–		–		–		**1,100**		**110**		**210**		1	U	**20**	
		8/15/12	SES	85 to 90	–	–		–		–		–		–		**19**		**2.3**		**9.7**		1	U	**0.62**	
B122/MW122	Alley East of 800 Aloha St	12/17/13	SES	25	–	–		**29**		**1.5**		**2.5**		**3**		1	U	1	U	1	U	1	U	0.2	U
		12/17/13	SES	40	–	–		**13**		**1.2**		**1.9**		3	U	1	U	1	U	**120**		1	U	**14**	
		12/17/13	SES	85	–	–		0.35	U	1	U	1	U	3	U	1	U	1	U	1	U	1	U	**0.72**	
B124/MW124	Valley St ROW	12/19/13	SES	45	–	**170**		0.35	U	1	U	**7.1**		**49.7**		1	U	1	U	1	U	1	U	0.2	U
		12/19/13	SES	60	–	–		0.35	U	1	U	**20**		**144**		1	U	1	U	1	U	1	U	0.2	U
		12/19/13	SES	100	–	–		0.35	U	1	U	1	U	3	U	1	U	1	U	1	U	1	U	0.2	U
B126/MW126	Alley E of 800 Aloha St	12/30/13	SES	40	–	–		**3.5**		**2.4**		**3.6**		3	U	1	U	1	U	1	U	1	U	0.2	U
B-213	Dexter Avenue North	9/6/17	PES	90 - 92	<3	**712**		**3.22**		**436**		0.158	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	**0.424**	
CHB-07	Westlake Ave N ROW	4/14/08	CH2M	–	–	250	U	**0.7**		0.2	U	0.2	U	0.6	U	0.2	U	0.2	U	**480**		**1.8**		**220**	
CHB-08	9th Ave N ROW	4/15/08	CH2M	–	–	250	U	0.2	U	0.2	U	0.2	U	0.6	U	0.2	U	0.2	U	0.2	U	0.2	U	0.2	U
CHB-09	9th Ave N ROW	4/16/08	CH2M	–	–	250	U	**0.3**		**0.3**		0.2	U	0.6	U	0.2	U	0.2	U	0.2	U	0.2	U	0.2	U
MW-138	Dexter Avenue North	9/14/17	PES	115 - 117	<3	–		**0.275**	**J**	**10.4**		1.58	U	0.316	U	0.199	U	0.153	U	0.0933	U	0.152	U	0.118	U
RS-20	800 Aloha Street Parcel	3/5/93	EPJ	–	–	**99,000**		**96**		**230**		**1,500**		**7,000**		5	U	–		–		–		–	
SCL-B101	800 Aloha Street Parcel	6/17/02	Urban	–	–	50	U	1	U	1	U	1	U	1	U	1	U	1	U	1	U	1	U	1.0	U
SCL-B102	800 Aloha Street Parcel	6/17/02	Urban	–	–	**150**		1	U	1	U	1	U	**3**		1	U	1	U	1	U	1	U	1.0	U

Table G-10

Summary of Reconnaissance Groundwater Analytical Data
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Area Location	Sample Date	Sampled By	Sample Interval (FT BTOC)	Color Tec (µg/L)	Analytical Results (micrograms per liter, µg/L)									
						GRO	Benzene	Toluene	Ethylbenzene	Total Xylenes	PCE	TCE	cDCE	tDCE	VC
Preliminary Cleanup Level (PCUL)					–	**800**	**5.0**	**640**	**700**	**1,600**	**5.0**	**4**	**16**	**100**	**0.29**
W-MW-02	8th Ave ROW	1/30/12	WW	10 to 20	–	–	0.2 U	0.2 U	0.2 U	0.2 U	**1.6**	**1.4**	**8.0**	**0.3**	**0.3**
		1/30/12	WW	30 to 40	–	–	20 U	20 U	20 U	60 U	**24,000**	**940**	**1,700**	**13 J**	**70**
		1/30/12	WW	50 to 60	–	–	20 U	20 U	20 U	60 U	**7,200**	**1,300**	**1,800**	20 U	**85**

Notes:

PCULs from Washington State Department of Ecology, Memorandum from P. Tomlinson to TCP File for American Linen Supply Co. Dexter Ave. (FSID 3573, CSID 12004) re: Development of site-specific preliminary cleanup levels, December 14, 2021.

B&V = Black & Veatch.
cDCE = cis-1,2-Dichloroethene.
CH2M = CH2M HILL.
EPJ = E.P. Johnson Construction Inc., and Environmental.
DRO = Diesel-range organics.
FTBTOC = feet below top of casing.
Farallon = Farallon Consulting, LLC.
GRO = Gasoline-range organics.
HC = Hart Crowser, Inc..
ORO = Oil-range organics.
PCE = Perchloroethylene (Tetrachloroethene).
Retec = Remediation Technologies, Inc.
ROW = right-of-way.
SES = SoundEarth Strategies, Inc.
TCE = Trichloroethene.
tDCE = trans-1,2-Dichloroethene.
Urban = Urban Redevelopment.
VC = Vinyl chloride.

Laboratory and Results Notes:

Petroleum hydrocarbons analyzed by EPA Method 418.1 or 8015-M, NWTPH-HCID, or NWTPH-Gx, NWTPH-Dx.
VOCs analyzed by EPA Method 601, 8010S, 8015, 8020, 8021B, 8240, 8260B, 8260C, or 8260D, or by Purge and Trap Gas Chromatogram/Mass Spectrometry.
Detected results are shown in **bold**.
Detected results above the groundwater PCUL are shown in **bold and highlighted in gray.**
– = Not analyzed or not measured.
a = Sample extremely turbid; held at lab.
b = Insufficient groundwater volume for laboratory analysis; ColorTec test run instead.
i = The presence of the analyte indicated may be due to carryover from previous sample injections.
J = Estimated concentration.
ND = not detected at a concentration exceeding laboratory reporting limit; detection limit not provided.
U = Not detected at a concentration exceeding laboratory reporting limit.
ve = Estimated value. The reported range exceeds the calibration range of the analysis.
z = No/low level gasoline/petroleum detection; result is likely elevated due to high detections of CVOCs.

Table G-11

Soil Vapor Analytical Results
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Location Description	Sample Name	Sample Date	1,1,1-Trichloroethane	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromoethane (ethylene dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (ethylene dichloride)	1,2-Dichloropropane	1,2-Dichlorotetrafluoroethane	1,3,5-Trimethylbenzene	1,3-Butadiene	1,3-Dichlorobenzene	1,4-Dichlorobenzene
Screening Level				**76,000**	**1.4**	**3.0**	**76,000**	**52**	**3,000**	**30**	**910**	**0.14**	**3,000**	**3.2**	**23**	**–**	**910**	**2.8**	**–**	**7.6**
SV01	8th Avenue	SV01-20130311	03/11/13	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(30.4 to 29.9)	North	SV01-092518	09/25/18	**96.7**	2.75 U	2.18 U	3.07 U	**6.92**	1.59 U	9.33 U	1.96 U	3.08 U	2.40 U	1.62 U	1.85 U	2.80 U	1.96 U	8.85 U	2.40 U	2.40 U
(duplicate)		SV01-092518-D	09/25/18	**93.2**	2.75 U	2.18 U	3.07 U	**6.54**	1.59 U	9.33 U	1.96 U	3.08 U	2.40 U	1.62 U	1.85 U	2.80 U	1.96 U	8.85 U	2.40 U	2.40 U
		SV01-020619	02/06/19	**22.0**	2.75 U	2.18 U	3.07 U	1.60 U	1.59 U	9.33 U	1.96 U	3.08 U	2.40 U	1.62 U	1.85 U	2.80 U	1.96 U	8.85 U	2.40 U	2.40 U
		SV01-042919	04/29/19	**11.0**	2.75 U	2.18 U	3.07 U	1.60 U	1.59 U	9.33 U	1.96 U	3.08 U	2.40 U	1.62 U	1.85 U	2.80 U	1.96 U	8.85 U	2.40 U	2.40 U
(duplicate)		SV01-042919-D	04/29/19	**12.6**	2.75 U	2.18 U	3.07 U	1.60 U	1.59 U	9.33 U	1.96 U	3.08 U	2.40 U	1.62 U	1.85 U	2.80 U	1.96 U	8.85 U	2.40 U	2.40 U
		SV-01-071919	07/19/19	**49.9**	2.75 U	2.18 U	3.07 U	**3.03**	1.59 U	9.33 U	1.96 U	3.08 U	2.40 U	1.62 U	1.85 U	2.80 U	1.96 U	8.85 U	2.40 U	2.40 U
(duplicate)		SV-01-071919-D	07/19/19	**58.3**	2.75 U	2.18 U	3.07 U	**3.57**	1.59 U	9.33 U	1.96 U	3.08 U	2.40 U	1.62 U	1.85 U	2.80 U	1.96 U	8.85 U	2.40 U	2.40 U
		SV01-110119	11/01/19	**19.7**	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
(duplicate)		SV01-110119-D	11/01/19	**68.5**	1.37 U	1.09 U	1.53 U	**3.42**	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV01-012720	01/27/20	**11.2 J**	1.37 U	1.09 U	1.53 U	0.802 UJ	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
(duplicate)		SV01-012720-D	01/27/20	**37.2 J**	1.37 U	1.09 U	1.53 U	**1.80 J**	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV01-071520	07/15/20	**54.4**	1.37 U	1.09 U	1.53 U	**2.97**	0.793 U	4.66 U	**21.6**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	**4.14**	4.43 U	1.20 U	1.20 U
		SV-01-110820	11/08/20	**52.3**	1.37 U	1.09 U	1.53 U	**3.10**	0.793 U	4.66 U	**2.29**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV01-020721	02/07/21	**27.3**	1.37 U	1.09 U	1.53 U	**7.50**	0.793 U	4.66 U	**2.39**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV01-051221	05/12/21	**5.71**	1.37 U	1.09 U	1.53 U	**12.1**	**0.923**	4.66 U	**4.24**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	**1.23**	4.43 U	1.20 U	1.20 U
(duplicate)		SV-907-051121	05/11/21	**6.64**	1.37 U	1.09 U	1.53 U	**14.1**	0.793 U	4.66 U	**5.40**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	**1.67**	4.43 U	1.20 U	1.20 U
SV02	8th Avenue	SV02-20130311	03/11/13	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(32.1 to 31.6)	North	SV02-092518	09/25/18	2.18 U	2.75 U	2.18 U	3.07 U	1.60 U	1.59 U	9.33 U	**9.01**	3.08 U	2.40 U	1.62 U	1.85 U	2.80 U	**2.39**	8.85 U	2.40 U	2.40 U
		SV02-020619	02/06/19	2.18 U	2.75 U	2.18 U	3.07 U	1.60 U	1.59 U	9.33 U	1.96 U	3.08 U	2.40 U	1.62 U	1.85 U	2.80 U	1.96 U	8.85 U	2.40 U	2.40 U
		SV02-042919	04/29/19	2.18 U	2.75 U	2.18 U	3.07 U	1.60 U	1.59 U	9.33 U	1.96 U	3.08 U	2.40 U	1.62 U	1.85 U	2.80 U	1.96 U	8.85 U	2.40 U	2.40 U
		SV-02-071919	07/19/19	**2.66**	2.75 U	2.18 U	3.07 U	1.60 U	1.59 U	9.33 U	1.96 U	3.08 U	2.40 U	1.62 U	1.85 U	2.80 U	1.96 U	8.85 U	2.40 U	2.40 U
		SV02-110119	11/01/19	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV02-071720	07/17/20	1.18	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**5.25**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	**1.72**	4.43 U	1.20 U	1.20 U
SV03	8th Avenue	SV03-20130311	03/11/13	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(31.8 to 31.3)	North	SV03-092518	09/25/18	2.18 U	2.75 U	2.18 U	3.07 U	1.60 U	1.59 U	9.33 U	**2.49**	3.08 U	2.40 U	1.62 U	1.85 U	2.80 U	1.96 U	8.85 U	2.40 U	2.40 U
		SV03-020619	02/06/19	2.18 U	2.75 U	2.18 U	3.07 U	1.60 U	1.59 U	9.33 U	1.96 U	3.08 U	2.40 U	1.62 U	1.85 U	2.80 U	1.96 U	8.85 U	2.40 U	2.40 U
		SV03-042919	04/29/19	2.18 U	2.75 U	2.18 U	3.07 U	1.60 U	1.59 U	9.33 U	**4.60**	3.08 U	2.40 U	1.62 U	1.85 U	2.80 U	1.96 U	8.85 U	2.40 U	2.40 U
SV-04	Roy Street	SV-04-071620	07/16/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**0.996**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
(38.6 to 38.1)		SV-04-111020	11/10/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
SV-05	Roy Street	SV-05-071620	07/16/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**3.82**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	**1.07**	4.43 U	1.20 U	1.20 U
(31.6 to 31.1)		SV-05-111020	11/10/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**1.60**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
SV-06	Roy Street	SV-06-071620	07/16/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
(47.9 to 47.4)		SV-06-111020	11/10/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-06-020321	02/03/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**1.36**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-06-050621	05/06/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U

Table G-11

Soil Vapor Analytical Results
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Location Description	Sample Name	Sample Date	1,4-Dioxane	2,2,4-Trimethylpentane	2-Butanone (MEK)	2-Chlorotoluene	2-Propanol (isopropanol)	4-Ethyltoluene	4-Methyl-2-pentanone (MIBK)	Acetone	Allyl chloride	Benzene	Benzyl chloride	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon tetrachloride	Chlorobenzene
Screening Level				**17**	**–**	**76,000**	**–**	**–**	**–**	**46,000**	**470,000**	**14**	**11**	**1.7**	**2.3**	**76**	**76**	**11,000**	**14**	**760**
SV01	8th Avenue	SV01-20130311	03/11/13	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(30.4 to 29.9)	North	SV01-092518	09/25/18	**6.59 J**	1.87 U	7.37 U	2.06 U	6.15 U	1.96 U	10.2 U	**27.4**	1.25 U	1.28 U	2.08 U	2.68 U	12.4 U	1.55 U	1.24 U	2.52 U	1.85 U
(duplicate)		SV01-092518-D	09/25/18	1.44 UJ	1.87 U	7.37 U	2.06 U	6.15 U	1.96 U	10.2 U	**20.3**	1.25 U	1.28 U	2.08 U	2.68 U	12.4 U	1.55 U	1.24 U	2.52 U	1.85 U
		SV01-020619	02/06/19	1.44 U	1.87 U	7.37 U	2.06 U	6.15 U	1.96 U	10.2 U	5.94 U	1.25 U	1.28 U	2.08 U	2.68 U	12.4 U	1.55 U	1.24 U	2.52 U	1.85 U
		SV01-042919	04/29/19	1.44 U	1.87 U	7.37 U	2.06 U	6.15 U	1.96 U	10.2 U	**11.3**	1.25 U	1.28 U	2.08 U	2.68 U	12.4 U	1.55 U	1.24 U	2.52 U	1.85 U
(duplicate)		SV01-042919-D	04/29/19	1.44 U	1.87 U	7.37 U	2.06 U	6.15 U	1.96 U	10.2 U	**13.6**	1.25 U	1.28 U	2.08 U	2.68 U	12.4 U	1.55 U	1.24 U	2.52 U	1.85 U
		SV-01-071919	07/19/19	1.44 U	1.87 U	7.37 U	2.06 U	6.15 U	1.96 U	10.2 U	**17.8**	1.25 U	1.28 U	2.08 U	2.68 U	12.4 U	1.55 U	1.24 U	2.52 U	1.85 U
(duplicate)		SV-01-071919-D	07/19/19	1.44 U	1.87 U	7.37 U	2.06 U	6.15 U	1.96 U	10.2 U	**8.07**	1.25 U	1.28 U	2.08 U	2.68 U	12.4 U	1.55 U	1.24 U	2.52 U	1.85 U
		SV01-110119	11/01/19	0.721 U	0.934 U	3.69 U	1.03 U	**16.3**	0.982 U	5.12 U	**27.6**	0.626 U	**0.719**	1.04 U	1.34 U	6.21 U	0.776 U	0.622 U	1.26 U	0.924 U
(duplicate)		SV01-110119-D	11/01/19	**0.796**	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**20.7**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	0.622 U	1.26 U	0.924 U
		SV01-012720	01/27/20	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**21.5 J**	0.626 U	**0.776**	1.04 U	1.34 U	6.21 U	0.776 U	0.622 U	1.26 U	0.924 U
(duplicate)		SV01-012720-D	01/27/20	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**4.42 J**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	0.622 U	1.26 U	0.924 U
		SV01-071520	07/15/20	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	**8.25**	5.12 U	**12.5**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**1.15**	1.26 U	0.924 U
		SV-01-110820	11/08/20	0.721 U	0.934 U	3.69 U	1.03 U	**10.5**	0.982 U	5.12 U	**6.94**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**4.05**	1.26 U	0.924 U
		SV01-020721	02/07/21	0.721 U	**186**	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	2.97 U	0.626 U	**7.54**	1.04 U	1.34 U	6.21 U	0.776 U	**7.59**	1.26 U	0.924 U
		SV01-051221	05/12/21	0.721 U	**412**	3.69 U	1.03 U	3.07 UJ	0.982 U	5.12 U	2.97 U	0.626 U	**12.2**	1.04 U	1.34 U	6.21 U	0.776 U	0.622 U	1.26 U	0.924 U
(duplicate)		SV-907-051121	05/11/21	0.721 U	**406**	**5.69**	1.03 U	**7.69 J**	0.982 U	5.12 U	2.97 U	0.626 U	**14.5**	1.04 U	1.34 U	6.21 U	0.776 U	0.622 U	1.26 U	0.924 U
SV02	8th Avenue	SV02-20130311	03/11/13	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(32.1 to 31.6)	North	SV02-092518	09/25/18	**2.70**	1.87 U	7.37 U	2.06 U	**19.5**	**3.05**	10.2 U	**73.2**	1.25 U	1.28 U	2.08 U	2.68 U	12.4 U	1.55 U	1.24 U	2.52 U	1.85 U
		SV02-020619	02/06/19	1.44 U	1.87 U	7.37 U	2.06 U	6.15 U	1.96 U	10.2 U	**27.3**	1.25 U	1.28 U	2.08 U	2.68 U	12.4 U	1.55 U	1.24 U	2.52 U	1.85 U
		SV02-042919	04/29/19	1.44 U	1.87 U	7.37 U	2.06 U	**6.60**	1.96 U	10.2 U	**14.0**	1.25 U	1.28 U	2.08 U	2.68 U	12.4 U	1.55 U	1.24 U	2.52 U	1.85 U
		SV-02-071919	07/19/19	**6.52**	1.87 U	**12.2**	2.06 U	**50.8**	1.96 U	10.2 U	**114**	1.25 U	1.28 U	2.08 U	2.68 U	12.4 U	1.55 U	1.24 U	2.52 U	1.85 U
		SV02-110119	11/01/19	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	2.97 U	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	0.622 U	1.26 U	0.924 U
		SV02-071720	07/17/20	0.721 U	**2.20**	3.69 U	1.03 U	**3.79**	**4.37**	5.12 U	**13.2**	0.626 U	**1.01**	1.04 U	1.34 U	6.21 U	0.776 U	0.622 U	1.26 U	0.924 U
SV03	8th Avenue	SV03-20130311	03/11/13	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–	–
(31.8 to 31.3)	North	SV03-092518	09/25/18	1.44 U	1.87 U	7.37 U	2.06 U	6.15 U	1.96 U	10.2 U	**18.6**	1.25 U	1.28 U	2.08 U	2.68 U	12.4 U	1.55 U	1.24 U	2.52 U	1.85 U
		SV03-020619	02/06/19	1.44 U	1.87 U	7.37 U	2.06 U	6.15 U	1.96 U	10.2 U	**22.4**	1.25 U	1.28 U	2.08 U	2.68 U	12.4 U	1.55 U	1.24 U	2.52 U	1.85 U
		SV03-042919	04/29/19	1.44 U	1.87 U	7.37 U	2.06 U	6.15 U	1.96 U	10.2 U	**23.9**	1.25 U	1.28 U	2.08 U	2.68 U	12.4 U	1.55 U	1.24 U	2.52 U	1.85 U
SV-04	Roy Street	SV-04-071620	07/16/20	0.721 U	0.934 U	3.69 U	1.03 U	**5.01**	0.982 U	5.12 U	**17.2**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**12.4**	1.26 U	0.924 U
(38.6 to 38.1)		SV-04-111020	11/10/20	**1.47**	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**40.6**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**8.96**	1.26 U	0.924 U
SV-05	Roy Street	SV-05-071620	07/16/20	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	**1.53**	5.12 U	**14.7**	0.626 U	**3.71**	1.04 U	1.34 U	6.21 U	0.776 U	**132**	1.26 U	0.924 U
(31.6 to 31.1)		SV-05-111020	11/10/20	**1.12**	**2.15**	3.69 U	1.03 U	**7.42**	0.982 U	5.12 U	**16.1**	0.626 U	**1.24**	1.04 U	1.34 U	6.21 U	0.776 U	**49.2**	1.26 U	0.924 U
SV-06	Roy Street	SV-06-071620	07/16/20	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**11.3**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**10.5**	**2.30**	0.924 U
(47.9 to 47.4)		SV-06-111020	11/10/20	**1.43**	0.934 U	**13.2**	1.03 U	3.07 U	0.982 U	5.12 U	**49.2**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**4.45**	**2.23**	0.924 U
		SV-06-020321	02/03/21	0.721 U	**1.04**	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**4.32**	0.626 U	**1.01**	1.04 U	1.34 U	6.21 U	0.776 U	**4.26**	1.26 U	0.924 U
		SV-06-050621	05/06/21	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**7.01**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	0.622 U	**1.40**	0.924 U

Table G-11

Soil Vapor Analytical Results
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Location Description	Sample Name	Sample Date	Chloroethane	Chloroform	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Cyclohexane	Dibromochloromethane	Dichlorodifluoromethane	Ethanol	Ethylbenzene	Heptane	Hexachloro-1,3-butadiene	Isopropylbenzene (cumene)	m&p-Xylene	Methyl butyl ketone (2-hexanone)	Methyl methacrylate	Methyl tert-butyl ether (MTBE)
		Screening Level		**150,000**	**3.6**	**1,400**	**–**	**–**	**91,000**	**–**	**1,500**	**–**	**15,000**	**6,100**	**3.8**	**6,100**	**1,500**	**460**	**11,000**	**320**
SV01	8th Avenue	SV01-20130311	03/11/13	–	–	–	**0.31**	–	–	–	–	–	–	–	–	–	–	–	–	–
(30.4 to 29.9)	North	SV01-092518	09/25/18	1.06 U	**2.32**	0.826 U	1.59 U	1.82 U	1.38 U	3.40 U	1.98 U	**27.5**	1.73 U	1.64 U	13.5 U	1.97 U	3.47 U	10.2 U	1.64 U	1.44 U
(duplicate)		SV01-092518-D	09/25/18	1.06 U	**2.04**	0.826 U	1.59 U	1.82 U	1.38 U	3.40 U	1.98 U	**23.2**	1.73 U	1.64 U	13.5 U	1.97 U	3.47 U	10.2 U	1.64 U	1.44 U
		SV01-020619	02/06/19	1.06 U	1.95 U	0.826 U	1.59 U	1.82 U	1.38 U	3.40 U	1.98 U	**7.11**	1.73 U	1.64 U	13.5 U	1.97 U	3.47 U	10.2 U	1.64 U	1.44 U
		SV01-042919	04/29/19	1.06 U	1.95 U	0.826 U	1.59 U	1.82 U	1.38 U	3.40 U	**2.11**	**24.6**	1.73 U	1.64 U	13.5 U	1.97 U	**3.60**	10.2 U	1.64 U	1.44 U
(duplicate)		SV01-042919-D	04/29/19	1.06 U	1.95 U	**0.861**	1.59 U	1.82 U	1.38 U	3.40 U	**2.04**	**28.7**	1.73 U	1.64 U	13.5 U	1.97 U	**4.03**	10.2 U	1.64 U	1.44 U
		SV-01-071919	07/19/19	1.06 U	1.95 U	0.826 U	1.59 U	1.82 U	1.38 U	3.40 U	**2.18**	**9.97**	1.73 U	1.64 U	13.5 U	1.97 U	3.47 U	10.2 U	1.64 U	1.44 U
(duplicate)		SV-01-071919-D	07/19/19	1.06 U	1.95 U	0.826 U	1.59 U	1.82 U	1.38 U	3.40 U	**2.03**	**6.80**	1.73 U	1.64 U	13.5 U	1.97 U	3.47 U	10.2 U	1.64 U	1.44 U
		SV01-110119	11/01/19	0.528 U	0.973 U	**0.793**	0.793 U	0.908 U	0.689 U	1.70 U	**2.41**	**42.0**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
(duplicate)		SV01-110119-D	11/01/19	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	0.989 U	**19.2**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV01-012720	01/27/20	0.528 U	0.973 U	**0.865 J**	0.793 U	0.908 U	**1.55 J**	1.70 U	**2.18**	**37.0 J**	0.867 U	**1.61 J**	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
(duplicate)		SV01-012720-D	01/27/20	0.528 U	0.973 U	0.413 UJ	0.793 U	0.908 U	0.689 UJ	1.70 U	**1.53**	**4.30 J**	0.867 U	0.818 UJ	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV01-071520	07/15/20	0.528 U	0.973 U	**0.843**	0.793 U	0.908 U	0.689 U	1.70 U	**2.27**	**16.4**	**1.27**	0.818 U	6.73 U	0.983 U	**5.68**	5.11 U	0.819 U	0.721 U
		SV-01-110820	11/08/20	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**1.43**	**28.3**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV01-020721	02/07/21	0.528 U	0.973 U	0.413 U	**1.09**	0.908 U	**31.8**	1.70 U	0.989 U	**5.43**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV01-051221	05/12/21	0.528 U	0.973 U	0.413 U	**8.60**	0.908 U	**67.2**	1.70 U	**1.02**	**58.6 J**	**2.90**	0.818 U	6.73 U	0.983 U	**8.54**	5.11 U	0.819 U	0.721 U
(duplicate)		SV-907-051121	05/11/21	0.528 U	0.973 U	0.413 U	**9.99**	0.908 U	**78.9**	1.70 U	0.989 U	**82.0 J**	**3.52**	0.818 U	6.73 U	0.983 U	**11.1**	5.11 U	0.819 U	0.721 U
SV02	8th Avenue	SV02-20130311	03/11/13	–	–	–	0.12 U	–	–	–	–	–	–	–	–	–	–	–	–	–
(32.1 to 31.6)	North	SV02-092518	09/25/18	1.06 U	1.95 U	**1.23**	1.59 U	1.82 U	1.38 U	3.40 U	**2.22**	**21.7**	1.73 U	1.64 U	13.5 U	1.97 U	**5.58**	10.2 U	1.64 U	1.44 U
		SV02-020619	02/06/19	1.06 U	1.95 U	**1.18**	1.59 U	1.82 U	1.38 U	3.40 U	**2.47**	**56.9**	1.73 U	1.64 U	13.5 U	1.97 U	3.47 U	10.2 U	1.64 U	1.44 U
		SV02-042919	04/29/19	1.06 U	1.95 U	**0.851**	1.59 U	1.82 U	1.38 U	3.40 U	**2.42**	**26.0**	1.73 U	1.64 U	13.5 U	1.97 U	3.47 U	10.2 U	1.64 U	1.44 U
		SV-02-071919	07/19/19	1.06 U	1.95 U	**1.89**	1.59 U	1.82 U	1.38 U	3.40 U	**2.85**	**11.1**	1.73 U	1.64 U	13.5 U	1.97 U	3.47 U	10.2 U	**2.60**	1.44 U
		SV02-110119	11/01/19	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	0.989 U	**31.3**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV02-071720	07/17/20	0.528 U	0.973 U	**0.768**	0.793 U	0.908 U	**2.93**	1.70 U	**2.08**	**39.4**	**2.01**	**2.45**	6.73 U	0.983 U	**14.5**	5.11 U	0.819 U	0.721 U
SV03	8th Avenue	SV03-20130311	03/11/13	–	–	–	0.12 U	–	–	–	–	–	–	–	–	–	–	–	–	–
(31.8 to 31.3)	North	SV03-092518	09/25/18	1.06 U	1.95 U	0.826 U	1.59 U	1.82 U	1.38 U	3.40 U	1.98 U	**26.1**	1.73 U	1.64 U	13.5 U	1.97 U	3.47 U	10.2 U	1.64 U	1.44 U
		SV03-020619	02/06/19	1.06 U	1.95 U	**1.68**	1.59 U	1.82 U	1.38 U	3.40 U	1.98 U	**19.0**	1.73 U	**3.3**	13.5 U	1.97 U	3.47 U	10.2 U	1.64 U	1.44 U
		SV03-042919	04/29/19	1.06 U	1.95 U	**1.44**	1.59 U	1.82 U	1.38 U	3.40 U	**2.25**	**39.6**	1.73 U	1.64 U	13.5 U	1.97 U	**4.36**	10.2 U	1.64 U	1.44 U
SV-04	Roy Street	SV-04-071620	07/16/20	0.528 U	0.973 U	**1.21**	0.793 U	0.908 U	0.689 U	1.70 U	**3.05**	**25.6**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
(38.6 to 38.1)		SV-04-111020	11/10/20	0.528 U	0.973 U	**0.595**	0.793 U	0.908 U	**3.07**	1.70 U	**2.14**	**21.5**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
SV-05	Roy Street	SV-05-071620	07/16/20	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	**1.88**	1.70 U	**3.09**	**16.5**	**1.71**	0.818 U	6.73 U	0.983 U	**4.42**	5.11 U	0.819 U	0.721 U
(31.6 to 31.1)		SV-05-111020	11/10/20	0.528 U	0.973 U	**1.14**	0.793 U	0.908 U	**1.79**	1.70 U	**2.07**	**39.6**	**1.48**	0.818 U	6.73 U	0.983 U	**3.74**	5.11 U	0.819 U	0.721 U
SV-06	Roy Street	SV-06-071620	07/16/20	0.528 U	**1.62**	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**3.03**	**7.09**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
(47.9 to 47.4)		SV-06-111020	11/10/20	0.528 U	0.973 U	**0.690**	0.793 U	0.908 U	0.689 U	1.70 U	**3.17**	**10.1**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-06-020321	02/03/21	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	**1.43**	1.70 U	**3.03**	**18.0**	0.867 U	0.818 U	6.73 U	0.983 U	**2.49**	5.11 U	0.819 U	0.721 U
		SV-06-050621	05/06/21	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**2.76**	**21.1**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U

Table G-11

Soil Vapor Analytical Results
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Location Description	Sample Name	Sample Date	Methylene chloride	Naphthalene	n-Hexane (hexane)	o-Xylene	Propene	Styrene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trichloroethene (TCE)	Trichlorofluoromethane	Vinyl acetate	Vinyl bromide (bromoethene)	Vinyl chloride
Screening Level				**2,200**	**2.5**	**11,000**	**1,500**	**–**	**15,000**	**320**	**30,000**	**76,000**	**610**	**–**	**11**	**11,000**	**3,000**	**5.6**	**9.5**
SV01	8th Avenue	SV01-20130311	03/11/13	–	–	–	–	–	–	**1.5**	–	–	0.58 U	–	0.16 U	–	–	–	**0.71**
(30.4 to 29.9)	North	SV01-092518	09/25/18	**1.40**	6.60 U	1.41 U	1.73 U	1.38 U	1.70 U	2.72 UJ	**3.64 J**	1.51 U	1.59 U	1.82 U	2.14 U	2.25 U	1.41 U	1.75 U	1.02 U
(duplicate)		SV01-092518-D	09/25/18	1.39 U	6.60 U	1.41 U	1.73 U	1.38 U	1.70 U	**137 J**	1.18 UJ	1.51 U	1.59 U	1.82 U	2.14 U	2.25 U	1.41 U	1.75 U	1.02 U
		SV01-020619	02/06/19	**2.35**	6.60 U	1.41 U	1.73 U	1.38 U	1.70 U	2.72 U	1.18 U	**1.83**	1.59 U	1.82 U	2.14 U	2.25 U	1.41 U	1.75 U	1.02 U
		SV01-042919	04/29/19	**7.00**	6.60 U	**1.46**	1.73 U	1.38 U	1.70 U	2.72 U	1.18 U	**6.41**	1.59 U	1.82 U	2.14 U	2.25 U	1.41 U	1.75 U	1.02 U
(duplicate)		SV01-042919-D	04/29/19	**11.1**	6.60 U	**1.87**	1.73 U	**1.55**	1.70 U	2.72 U	1.18 U	**6.74**	1.59 U	1.82 U	2.14 U	2.25 U	1.41 U	1.75 U	1.02 U
		SV-01-071919	07/19/19	**1.90**	6.60 U	1.41 U	1.73 U	**1.38**	1.70 U	2.72 U	1.18 U	**2.06**	1.59 U	1.82 U	2.14 U	2.25 U	1.41 U	1.75 U	1.02 U
(duplicate)		SV-01-071919-D	07/19/19	1.39 U	6.60 U	1.41 U	1.73 U	1.38 U	1.70 U	2.72 U	1.18 U	1.51 U	1.59 U	1.82 U	2.14 U	2.25 U	1.41 U	1.75 U	1.02 U
		SV01-110119	11/01/19	**24.9**	3.30 U	**7.90**	0.867 U	0.689 U	0.851 U	1.36 U	0.590 U	**5.39**	0.793 U	0.908 U	1.07 U	1.12 U	0.704 U	0.875 U	0.511 U
(duplicate)		SV01-110119-D	11/01/19	0.694 U	3.30 U	0.705 U	0.867 U	0.689 U	0.851 U	**2.75**	0.590 U	**1.62**	0.793 U	0.908 U	1.07 U	1.12 U	0.704 U	0.875 U	0.511 U
		SV01-012720	01/27/20	**0.705**	3.30 U	**1.88 J**	0.867 U	0.689 U	0.851 U	1.36 U	0.590 U	**2.65 J**	0.793 U	0.908 U	1.07 U	1.12 U	0.704 U	0.875 U	0.511 U
(duplicate)		SV01-012720-D	01/27/20	0.694 U	3.30 U	0.705 U	0.867 U	0.689 U	0.851 U	1.36 U	0.590 U	0.753 UJ	0.793 U	0.908 U	1.07 U	1.12 U	0.704 U	0.875 U	0.511 U
		SV01-071520	07/15/20	0.694 U	3.30 U	2.22 U	**2.42**	0.689 U	0.851 U	**1.79**	0.590 U	**3.71**	0.793 U	0.908 U	1.07 U	1.12 U	0.704 U	0.875 U	0.511 U
		SV-01-110820	11/08/20	**3.10**	3.30 U	**3.77**	0.867 U	0.689 U	0.851 U	**1.55**	0.590 U	1.88 U	0.793 U	0.908 U	1.07 U	1.12 U	0.704 U	0.875 U	0.511 U
		SV01-020721	02/07/21	0.694 U	3.30 U	**14.5**	0.867 U	0.689 U	0.851 U	1.36 U	0.590 U	1.88 U	0.793 U	0.908 U	1.07 U	1.12 U	0.704 U	0.875 U	**180**
		SV01-051221	05/12/21	0.694 U	3.30 U	2.22 U	**3.60**	2.15 U	0.851 U	**2.76**	0.590 UJ	**12.6 J**	0.793 U	0.908 U	1.07 U	1.12 U	0.704 U	0.875 U	**409**
(duplicate)		SV-907-051121	05/11/21	0.694 U	3.30 U	2.22 U	**4.55**	2.15 U	0.851 U	**2.97**	**15.2 J**	**18.3 J**	**0.816**	0.908 U	**1.19**	1.12 U	0.704 U	0.875 U	**473**
SV02	8th Avenue	SV02-20130311	03/11/13	–	–	–	–	–	–	**2.3**	–	–	0.61 U	–	0.17 U	–	–	–	0.040 U
(32.1 to 31.6)	North	SV02-092518	09/25/18	**3.81**	6.60 U	**2.32**	**2.76**	**8.03**	1.70 U	2.72 U	**1.87**	**1.83**	1.59 U	1.82 U	2.14 U	**4.35**	1.41 U	1.75 U	1.02 U
		SV02-020619	02/06/19	**3.27**	6.60 U	**1.99**	1.73 U	1.38 U	1.70 U	2.72 U	1.18 U	**3.16**	1.59 U	1.82 U	2.14 U	2.25 U	1.41 U	1.75 U	1.02 U
		SV02-042919	04/29/19	**9.58**	6.60 U	**1.71**	1.73 U	**1.47**	1.70 U	2.72 U	1.18 U	**4.08**	1.59 U	1.82 U	2.14 U	2.25 U	1.41 U	1.75 U	1.02 U
		SV-02-071919	07/19/19	1.39 U	6.60 U	1.41 U	1.73 U	1.38 U	1.70 U	**31.3**	**5.06**	**2.92**	1.59 U	1.82 U	2.14 U	**3.13**	1.41 U	1.75 U	1.02 U
		SV02-110119	11/01/19	**4.44**	3.30 U	**1.09**	0.867 U	0.689 U	0.851 U	**14.5**	0.590 U	**1.45**	0.793 U	0.908 U	1.07 U	**4.78**	0.704 U	0.875 U	0.511 U
		SV02-071720	07/17/20	**0.816**	3.30 U	**3.51**	**5.25**	0.689 U	0.851 U	**9.51**	0.590 U	**9.08**	0.793 U	0.908 U	1.07 U	**17.1**	0.704 U	0.875 U	0.511 U
SV03	8th Avenue	SV03-20130311	03/11/13	–	–	–	–	–	–	**4.6**	–	–	0.58 U	–	**0.39**	–	–	–	0.037 U
(31.8 to 31.3)	North	SV03-092518	09/25/18	1.39 U	6.60 U	1.41 U	1.73 U	**2.75**	1.70 U	2.72 U	1.180 U	**2.15**	1.59 U	1.82 U	2.14 U	2.25 U	1.41 U	1.75 U	1.02 U
		SV03-020619	02/06/19	**2.53**	6.60 U	**12.2**	1.73 U	1.38 U	1.70 U	2.72 U	1.180 U	**1.73**	1.59 U	1.82 U	2.14 U	2.25 U	1.41 U	1.75 U	1.02 U
		SV03-042919	04/29/19	**2.69**	6.60 U	1.41 U	**1.90**	1.38 U	1.70 U	2.72 U	1.180 U	**2.03**	1.59 U	1.82 U	2.14 U	2.25 U	1.41 U	1.75 U	1.02 U
SV-04	Roy Street	SV-04-071620	07/16/20	**2.24**	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	**31.8**	0.590 U	**4.14**	0.793 U	0.908 U	1.07 U	**4.62**	0.704 U	0.875 U	0.511 U
(38.6 to 38.1)		SV-04-111020	11/10/20	**1.15**	3.30 U	2.22 U	0.867 U	**0.828**	0.851 U	**21.8**	**2.67**	1.88 U	0.793 U	0.908 U	1.07 U	**4.99**	0.704 U	0.875 U	0.511 U
SV-05	Roy Street	SV-05-071620	07/16/20	**3.05**	3.30 U	2.22 U	**2.34**	**53.0**	0.851 U	**34.5**	0.590 U	**9.83**	0.793 U	0.908 U	1.07 U	**5.14**	0.704 U	0.875 U	0.511 U
(31.6 to 31.1)		SV-05-111020	11/10/20	**2.00**	3.30 U	**3.32**	**1.63**	**4.58**	0.851 U	**55.2**	**2.64**	**7.99**	0.793 U	0.908 U	1.07 U	**5.28**	0.704 U	0.875 U	0.511 U
SV-06	Roy Street	SV-06-071620	07/16/20	0.694 U	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	**105**	0.590 U	**0.78**	0.793 U	0.908 U	1.07 U	**3.37**	0.704 U	0.875 U	0.511 U
(47.9 to 47.4)		SV-06-111020	11/10/20	0.694 U	3.30 U	2.22 U	0.867 U	**0.832**	0.851 U	**79.4**	**0.708**	1.88 U	0.793 U	0.908 U	1.07 U	**3.11**	0.704 U	0.875 U	0.511 U
		SV-06-020321	02/03/21	0.694 U	3.30 U	2.22 U	0.867 U	**4.13**	0.851 U	**58.3**	0.590 U	**5.99**	0.793 U	0.908 U	1.07 U	**2.29**	0.704 U	0.875 U	0.511 U
		SV-06-050621	05/06/21	0.694 U	3.30 U	2.22 U	0.867 U	2.15 U	0.851 U	**61.8**	0.590 U	1.88 U	0.793 U	0.908 U	1.07 U	**2.15**	0.704 U	0.875 U	0.511 U

Table G-11

Soil Vapor Analytical Results
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Location Description	Sample Name	Sample Date	1,1,1-Trichloroethane	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromoethane (ethylene dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (ethylene dichloride)	1,2-Dichloropropane	1,2-Dichlorotetrafluoroethane	1,3,5-Trimethylbenzene	1,3-Butadiene	1,3-Dichlorobenzene	1,4-Dichlorobenzene
			Screening Level	**76,000**	**1.4**	**3.0**	**76,000**	**52**	**3,000**	**30**	**910**	**0.14**	**3,000**	**3.2**	**23**	**–**	**910**	**2.8**	**–**	**7.6**
SV-07 (duplicate) (38.9 to 38.4)	Roy Street	SV-07-071620	07/16/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**4.75 J**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	**1.33**	4.43 U	1.20 U	1.20 U
		SV-901-071620	07/16/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**2.22 J**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-07-111020	11/10/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**1.00**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-07-020321	02/03/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**2.10**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.39
		SV-07-050621	05/06/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**1.03**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
SV-08 (31.4 to 30.9)	8th Avenue North	SV-08-071420	07/14/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**1.12**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-08-110220	11/02/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**1.74**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-08-020321	02/03/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-08-050521	05/05/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**1.88**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
SV-09 (duplicate) (35.3 to 34.8)	8th Avenue North	SV-09-071420	07/14/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**3.36**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-900-071420	07/14/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**3.23**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-09-110220	11/02/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**1.14**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-09-020321	02/03/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
(duplicate)		SV-904-020321	02/03/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-09-050521	05/05/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**1.49**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
SV-10 (46.3 to 45.8)	Valley Street	SV-10-071620	07/16/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**5.55**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	**2.13**	4.43 U	1.20 U	1.20 U
		SV-10-110820	11/08/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**1.34**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-10-020521	02/05/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**1.25**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-10-050521	05/05/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**1.59**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
SV-11 (37.4 to 36.9) (duplicate)	Valley Street	SV-11-071620	07/16/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**2.20**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-11-110820	11/08/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-902-110820	11/08/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-11-020621	02/06/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-11-050521	05/05/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
SV-12 (39.1 to 38.6)	Valley Street	SV-12-071620	07/16/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**1.65**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-12-110820	11/08/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-12-020521	02/05/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-12-050221	05/02/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**1.73**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
SV-13 (32.9 to 32.4)	Valley Street	SV-13-071620	07/16/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**1.20**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-13-110820	11/08/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-13-020521	02/05/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**1.60**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
SV-14 (35.4 to 34.9)	Roy Street	SV-14-071620	07/16/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**39.9**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	**12.2**	4.43 U	1.20 U	1.20 U
		SV-14-120220	12/02/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**1.86**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-14-020321	02/03/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-14-050421	05/04/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
SV-15 (28.5 to 28.0)	Roy Street	SV-15-071620	07/16/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**1.26**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-15-120220	12/02/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-15-020321	02/03/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**1.62**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-15-050421	05/04/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**1.01**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U

Table G-11

Soil Vapor Analytical Results
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Location Description	Sample Name	Sample Date	1,4-Dioxane	2,2,4-Trimethylpentane	2-Butanone (MEK)	2-Chlorotoluene	2-Propanol (isopropanol)	4-Ethyltoluene	4-Methyl-2-pentanone (MIBK)	Acetone	Allyl chloride	Benzene	Benzyl chloride	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon tetrachloride	Chlorobenzene
		Screening Level		**17**	**–**	**76,000**	**–**	**–**	**–**	**46,000**	**470,000**	**14**	**11**	**1.7**	**2.3**	**76**	**76**	**11,000**	**14**	**760**
SV-07	Roy Street	SV-07-071620	07/16/20	0.721 U	0.934 U	**3.86**	1.03 U	3.07 U	**2.99 J**	5.12 U	**11.0**	0.626 U	**6.07**	1.04 U	1.34 U	6.21 U	0.776 U	**52.9**	**6.80**	0.924 U
(duplicate)		SV-901-071620	07/16/20	0.721 U	0.934 U	**4.28**	1.03 U	**3.98**	0.982 UJ	5.12 U	**12.9**	0.626 U	**5.81**	1.04 U	1.34 U	6.21 U	0.776 U	**48.6**	**6.68**	0.924 U
(38.9 to 38.4)		SV-07-111020	11/10/20	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**8.93**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**5.73**	**7.43**	0.924 U
		SV-07-020321	02/03/21	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**5.16**	0.626 U	**0.974**	1.04 U	1.34 U	6.21 U	0.776 U	**3.89**	**5.35**	0.924 U
		SV-07-050621	05/06/21	0.721 U	0.934 U	3.69 U	1.03 U	**4.10**	0.982 U	5.12 U	**10.2**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**12.0**	**4.79**	0.924 U
SV-08	8th Avenue	SV-08-071420	07/14/20	0.721 U	0.934 U	3.69 U	1.03 U	**3.22**	0.982 U	5.12 U	**15.2**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**5.26**	1.26 U	0.924 U
(31.4 to 30.9)	North	SV-08-110220	11/02/20	0.721 U	0.934 U	3.69 U	1.03 U	**16.9**	0.982 U	5.12 U	**12.7**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**11.4**	1.26 U	0.924 U
		SV-08-020321	02/03/21	0.721 U	**1.65**	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**4.32**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**10.6**	1.26 U	0.924 U
		SV-08-050521	05/05/21	0.721 U	**1.60**	**8.58**	1.03 U	**28.0**	0.982 U	5.12 U	**25.4**	0.626 U	**0.754**	1.04 U	1.34 U	6.21 U	0.776 U	**39.8**	1.26 U	0.924 U
SV-09	8th Avenue	SV-09-071420	07/14/20	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	**1.88**	5.12 U	**11.4**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**6.44**	1.26 U	0.924 U
(duplicate)	North	SV-900-071420	07/14/20	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	**1.48**	5.12 U	**10.1**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**9.93**	1.26 U	0.924 U
(35.3 to 34.8)		SV-09-110220	11/02/20	0.721 U	0.934 U	3.69 U	1.03 U	**12.3**	0.982 U	5.12 U	**7.51**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**6.26**	1.26 U	0.924 U
		SV-09-020321	02/03/21	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**4.51**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**3.05**	1.26 U	0.924 U
(duplicate)		SV-904-020321	02/03/21	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**5.85**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**1.79**	1.26 U	0.924 U
		SV-09-050521	05/05/21	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**5.54**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**9.28**	1.26 U	0.924 U
SV-10	Valley Street	SV-10-071620	07/16/20	0.721 U	**1.00**	**7.58**	1.03 U	3.07 U	**2.53**	5.12 U	**35.9**	0.626 U	**0.891**	1.04 U	1.34 U	6.21 U	**1.45**	**140**	**2.88**	0.924 U
(46.3 to 45.8)		SV-10-110820	11/08/20	0.721 U	0.934 U	3.69 U	1.03 U	**10.2**	0.982 U	5.12 U	**14.6**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**5.48**	**2.54**	0.924 U
		SV-10-020521	02/05/21	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**4.75**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**3.08**	1.26 U	0.924 U
		SV-10-050521	05/05/21	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**7.39**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**8.87**	1.26 U	0.924 U
SV-11	Valley Street	SV-11-071620	07/16/20	0.721 U	**1.36**	**3.69**	1.03 U	3.07 U	**1.01**	5.12 U	**18.4**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**22.9**	1.26 U	0.924 U
(37.4 to 36.9)		SV-11-110820	11/08/20	0.721 U	**3.17**	3.69 U	1.03 U	**5.43**	0.982 U	5.12 U	**7.91 J**	0.626 U	**0.719**	1.04 U	1.34 U	6.21 U	0.776 U	**3.77**	1.26 U	0.924 U
(duplicate)		SV-902-110820	11/08/20	0.721 U	**3.89**	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**4.25 J**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**4.20**	1.26 U	0.924 U
		SV-11-020621	02/06/21	**2.66**	**1.03**	**4.42**	1.03 U	**6.00**	0.982 U	5.12 U	**15.4**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**10.5**	1.26 U	0.924 U
		SV-11-050521	05/05/21	0.721 U	**0.958**	**277**	1.03 U	3.07 U	0.982 U	5.12 U	**57.7**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**12.0**	1.26 U	0.924 U
SV-12	Valley Street	SV-12-071620	07/16/20	0.721 U	0.934 U	**4.31**	1.03 U	**5.21**	0.982 U	5.12 U	**14.4**	0.626 U	**0.811**	1.04 U	1.34 U	6.21 U	0.776 U	**16.5**	1.26 U	0.924 U
(39.1 to 38.6)		SV-12-110820	11/08/20	0.721 U	0.934 U	3.69 U	1.03 U	**11.9**	0.982 U	5.12 U	**5.89**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**5.10**	1.26 U	0.924 U
		SV-12-020521	02/05/21	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**7.37**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**6.63**	1.26 U	0.924 U
		SV-12-050221	05/02/21	0.721 U	0.934 U	**3.75**	1.03 U	**19.3**	0.982 U	5.12 U	**10.1**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	0.622 U	1.26 U	0.924 U
SV-13	Valley Street	SV-13-071620	07/16/20	**1.79**	0.934 U	**4.31**	1.03 U	**5.65**	0.982 U	5.12 U	**36.4**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**12.0**	1.26 U	0.924 U
(32.9 to 32.4)		SV-13-110820	11/08/20	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**42.8**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**5.35**	1.26 U	0.924 U
		SV-13-020521	02/05/21	**3.68**	0.934 U	**8.52**	1.03 U	**4.42**	0.982 U	5.12 U	**30.2**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**7.41**	1.26 U	0.924 U
SV-14	Roy Street	SV-14-071620	07/16/20	0.721 U	0.934 U	**15.4**	**1.30**	**33.4**	**9.37**	5.12 U	**114**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**17.1**	1.26 U	0.924 U
(35.4 to 34.9)		SV-14-120220	12/02/20	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**3.92**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 UJ	0.776 U	**9.90**	1.26 U	0.924 U
		SV-14-020321	02/03/21	**0.757**	0.934 U	3.69 U	1.03 U	**3.27**	0.982 U	5.12 U	**10.2**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**6.38**	1.26 U	0.924 U
		SV-14-050421	05/04/21	**1.87**	0.934 U	**7.37**	1.03 U	**4.42**	0.982 U	5.12 U	**38.3**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**23.7**	1.26 U	0.924 U
SV-15	Roy Street	SV-15-071620	07/16/20	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**12.2**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**10.6**	1.26 U	0.924 U
(28.5 to 28.0)		SV-15-120220	12/02/20	0.721 U	0.934 U	**4.10**	1.03 U	**27.5**	0.982 U	5.12 U	**17.6**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 UJ	0.776 U	**4.14**	1.26 U	0.924 U
		SV-15-020321	02/03/21	0.721 U	**1.19**	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**41.6**	0.626 U	**0.898**	1.04 U	1.34 U	6.21 U	0.776 U	**6.10**	1.26 U	0.924 U
		SV-15-050421	05/04/21	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**31.1**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**30.0**	1.26 U	0.924 U

Table G-11

Soil Vapor Analytical Results
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Location Description	Sample Name	Sample Date	Chloroethane	Chloroform	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Cyclohexane	Dibromochloromethane	Dichlorodifluoromethane	Ethanol	Ethylbenzene	Heptane	Hexachloro-1,3-butadiene	Isopropylbenzene (cumene)	m&p-Xylene	Methyl butyl ketone (2-hexanone)	Methyl methacrylate	Methyl tert-butyl ether (MTBE)
			Screening Level	**150,000**	**3.6**	**1,400**	**–**	**–**	**91,000**	**–**	**1,500**	**–**	**15,000**	**6,100**	**3.8**	**6,100**	**1,500**	**460**	**11,000**	**320**
SV-07	Roy Street	SV-07-071620	07/16/20	0.528 U	0.973 U	**24.2**	0.793 U	0.908 U	**51.3**	1.70 U	**2.73**	**9.13 J**	**1.45**	0.818 U	6.73 U	0.983 U	**6.55 J**	5.11 U	0.819 U	0.721 U
(duplicate)		SV-901-071620	07/16/20	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	**49.9**	1.70 U	**2.78**	**44.5 J**	**1.02**	**1.81**	6.73 U	0.983 U	**2.43 J**	5.11 U	0.819 U	0.721 U
(38.9 to 38.4)		SV-07-111020	11/10/20	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**3.22**	**20.7**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-07-020321	02/03/21	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**2.61**	**45.4**	0.867 U	0.818 U	6.73 U	0.983 U	**2.61**	5.11 U	0.819 U	0.721 U
		SV-07-050621	05/06/21	0.528 U	0.973 U	**0.537**	0.793 U	0.908 U	0.689 U	1.70 U	**2.45**	**48.6**	0.867 U	0.818 U	6.73 U	0.983 U	**1.83**	5.11 U	0.819 U	0.721 U
SV-08	8th Avenue North	SV-08-071420	07/14/20	0.528 U	0.973 U	**1.20**	0.793 U	0.908 U	0.689 U	1.70 U	**2.68**	**28.5**	0.867 U	0.818 U	6.73 U	0.983 U	**2.10**	5.11 U	0.819 U	0.721 U
(31.4 to 30.9)		SV-08-110220	11/02/20	0.528 U	**3.11**	**0.547**	0.793 U	0.908 U	0.689 U	1.70 U	**1.50**	**90.5**	0.867 U	**1.01**	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-08-020321	02/03/21	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**1.41**	**18.3**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-08-050521	05/05/21	0.528 U	0.973 U	**1.18**	0.793 U	0.908 U	**1.27**	1.70 U	**1.55**	**447 J**	**0.910**	**1.39**	6.73 U	0.983 U	**3.32**	5.11 U	0.819 U	0.721 U
SV-09	8th Avenue North	SV-09-071420	07/14/20	0.528 U	0.973 U	**1.17**	0.793 U	0.908 U	0.689 U	1.70 U	**2.94**	**17.0**	**0.871**	0.818 U	6.73 U	0.983 U	**2.57**	5.11 U	0.819 U	0.721 U
(duplicate)		SV-900-071420	07/14/20	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**2.88**	**16.5**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
(35.3 to 34.8)		SV-09-110220	11/02/20	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	**1.05**	1.70 U	**1.17**	**60.7**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-09-020321	02/03/21	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**1.71**	**9.97**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
(duplicate)		SV-904-020321	02/03/21	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**1.79**	**11.5**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-09-050521	05/05/21	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**2.98**	**12.1**	0.867 U	0.818 U	6.73 U	0.983 U	**2.46**	5.11 U	0.819 U	0.721 U
SV-10	Valley Street	SV-10-071620	07/16/20	0.528 U	**3.70**	**2.06**	0.793 U	0.908 U	**1.37**	1.70 U	**2.78**	**9.90**	**0.984**	**3.46**	6.73 U	0.983 U	**5.12**	5.11 U	0.819 U	0.721 U
(46.3 to 45.8)		SV-10-110820	11/08/20	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**2.31**	**23.4**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-10-020521	02/05/21	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	**0.727**	1.70 U	**1.68**	**10.5**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-10-050521	05/05/21	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	**0.830**	1.70 U	**1.84**	**23.2**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
SV-11	Valley Street	SV-11-071620	07/16/20	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	0.989 U	**30.2**	**1.02**	0.818 U	6.73 U	0.983 U	**1.74**	5.11 U	0.819 U	0.721 U
(37.4 to 36.9)		SV-11-110820	11/08/20	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	0.989 U	**48.3 J**	**1.24**	**0.834**	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
(duplicate)		SV-902-110820	11/08/20	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	0.989 U	**12.7 J**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-11-020621	02/06/21	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	0.989 U	**52.6**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-11-050521	05/05/21	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	0.989 U	**15.0**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
SV-12	Valley Street	SV-12-071620	07/16/20	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	0.989 U	**51.9**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
(39.1 to 38.6)		SV-12-110820	11/08/20	0.528 U	0.973 U	0.413 U	**1.20**	0.908 U	0.689 U	1.70 U	**2.32**	**33.4**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-12-020521	02/05/21	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	**0.899**	1.70 U	**1.86**	**18.0**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-12-050221	05/02/21	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**2.08**	**354 J**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
SV-13	Valley Street	SV-13-071620	07/16/20	0.528 U	**5.69**	**1.02**	0.793 U	0.908 U	0.689 U	1.70 U	**1.90**	**59.0**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
(32.9 to 32.4)		SV-13-110820	11/08/20	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**2.16**	**98.4**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-13-020521	02/05/21	0.528 U	**7.69**	**6.61**	0.793 U	0.908 U	0.689 U	1.70 U	**1.69**	**35.3**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
SV-14	Roy Street	SV-14-071620	07/16/20	0.528 U	0.973 U	**1.63**	0.793 U	0.908 U	**1.09**	1.70 U	**2.91**	**41.3**	**2.26**	0.818 U	6.73 U	0.983 U	**10.4**	5.11 U	0.819 U	0.721 U
(35.4 to 34.9)		SV-14-120220	12/02/20	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**1.67**	**12.4**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-14-020321	02/03/21	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**1.88**	**20.6**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-14-050421	05/04/21	0.528 U	0.973 U	**0.506**	0.793 U	0.908 U	**2.03**	1.70 U	**1.86**	**18.2**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
SV-15	Roy Street	SV-15-071620	07/16/20	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	0.989 U	**19.4**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
(28.5 to 28.0)		SV-15-120220	12/02/20	0.528 U	0.973 U	**0.535**	0.793 U	0.908 U	**0.740**	1.70 U	**2.00**	**64.3**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-15-020321	02/03/21	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**1.94**	**23.9**	**0.945**	**0.982**	6.73 U	0.983 U	**3.25**	5.11 U	0.819 U	0.721 U
		SV-15-050421	05/04/21	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	**1.29**	1.70 U	**1.47**	**14.0**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U

Table G-11

Soil Vapor Analytical Results
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Location Description	Sample Name	Sample Date	Methylene chloride	Naphthalene	n-Hexane (hexane)	o-Xylene	Propene	Styrene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trichloroethene (TCE)	Trichlorofluoromethane	Vinyl acetate	Vinyl bromide (bromoethene)	Vinyl chloride
		Screening Level		**2,200**	**2.5**	**11,000**	**1,500**	**–**	**15,000**	**320**	**30,000**	**76,000**	**610**	**–**	**11**	**11,000**	**3,000**	**5.6**	**9.5**
SV-07	Roy Street	SV-07-071620	07/16/20	0.694 U	3.30 U	**6.73**	**2.73**	**456**	0.851 U	**43.5**	0.590 UJ	**6.93**	0.793 U	0.908 U	1.07 U	**3.00**	0.704 U	0.875 U	0.511 U
(duplicate)		SV-901-071620	07/16/20	0.694 U	3.30 U	**5.82**	**1.33**	**401**	0.851 U	**42.5**	0.590 UJ	**12.1**	0.793 U	0.908 U	**1.18**	**2.96**	0.704 U	0.875 U	0.511 U
(38.9 to 38.4)		SV-07-111020	11/10/20	**2.21**	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	**51.6**	0.590 U	1.88 U	0.793 U	0.908 U	**1.32**	**3.39**	0.704 U	0.875 U	0.511 U
		SV-07-020321	02/03/21	**2.83**	3.30 U	**2.27**	**1.02**	0.689 U	0.851 U	**30.3**	0.590 U	4.60	0.793 U	0.908 U	1.07 U	**2.50**	0.704 U	0.875 U	0.511 U
		SV-07-050621	05/06/21	0.694 U	3.30 U	2.22 U	0.867 U	2.15 U	0.851 U	**26.4**	**1.54**	1.88 U	0.793 U	0.908 U	1.07 U	**2.11**	0.704 U	0.875 U	0.511 U
SV-08	8th Avenue	SV-08-071420	07/14/20	**2.95**	3.30 U	2.22 U	**0.919**	0.689 U	0.851 U	**2.91**	0.590 U	**6.03**	0.793 U	0.908 U	1.07 U	**1.52**	0.704 U	0.875 U	0.511 U
(31.4 to 30.9)	North	SV-08-110220	11/02/20	**8.26**	3.30 U	**4.62**	0.867 U	0.689 U	0.851 U	**14.6**	0.590 U	**2.99**	0.793 U	0.908 U	1.07 U	**1.97**	0.704 U	0.875 U	0.511 U
		SV-08-020321	02/03/21	0.694 U	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	**6.26**	0.590 U	**2.49**	0.793 U	0.908 U	1.07 U	**1.29**	0.704 U	0.875 U	0.511 U
		SV-08-050521	05/05/21	**0.747**	3.30 U	**2.72**	**1.09**	2.15 U	0.851 U	**7.06**	**20.1**	**8.51**	0.793 U	0.908 U	1.07 U	**1.42**	0.704 U	0.875 U	0.511 U
SV-09	8th Avenue	SV-09-071420	07/14/20	**12.9**	3.30 U	**4.58**	**0.993**	0.689 U	0.851 U	**20.2**	0.590 U	**3.76**	0.793 U	0.908 U	1.07 U	**2.84**	0.704 U	0.875 U	0.511 U
(duplicate)	North	SV-900-071420	07/14/20	**3.51**	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	**28.3**	0.590 U	**3.09**	0.793 U	0.908 U	1.07 U	**3.34**	0.704 U	0.875 U	0.511 U
(35.3 to 34.8)		SV-09-110220	11/02/20	**1.56**	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	**9.30**	0.590 U	**6.48**	0.793 U	0.908 U	**17.4**	**1.51**	0.704 U	0.875 U	0.511 U
		SV-09-020321	02/03/21	0.694 U	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	**6.99**	0.590 U	1.88 U	0.793 U	0.908 U	1.07 U	**1.74**	0.704 U	0.875 U	0.511 U
(duplicate)		SV-904-020321	02/03/21	0.694 U	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	**6.93**	0.590 U	1.88 U	0.793 U	0.908 U	1.07 U	**1.76**	0.704 U	0.875 U	0.511 U
		SV-09-050521	05/05/21	0.694 U	3.30 U	2.22 U	0.867 U	2.15 U	**1.42**	**12.6**	0.590 U	1.88 U	0.793 U	0.908 U	1.07 U	**2.37**	0.704 U	0.875 U	0.511 U
SV-10	Valley Street	SV-10-071620	07/16/20	**1.44**	3.30 U	**2.96**	**2.12**	**7.23**	0.851 U	**7.13**	0.590 U	**4.37**	0.793 U	0.908 U	1.07 U	**1.66**	0.704 U	0.875 U	0.511 U
(46.3 to 45.8)		SV-10-110820	11/08/20	**2.49**	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	**5.17**	0.590 U	1.88 U	0.793 U	0.908 U	1.07 U	**1.47**	0.704 U	0.875 U	0.511 U
		SV-10-020521	02/05/21	0.694 U	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	**1.89**	0.590 U	1.88 U	0.793 U	0.908 U	1.07 U	1.12 U	0.704 U	0.875 U	0.511 U
		SV-10-050521	05/05/21	0.694 U	3.30 U	**2.58**	0.867 U	2.15 U	0.851 U	**3.27**	0.590 U	1.88 U	0.793 U	0.908 U	1.07 U	1.12 U	0.704 U	0.875 U	0.511 U
SV-11	Valley Street	SV-11-071620	07/16/20	**1.31**	3.30 U	2.22 U	**0.867**	0.689 U	0.851 U	**55.8**	0.590 U	**3.35**	0.793 U	0.908 U	**1.43**	1.12 U	0.704 U	0.875 U	0.511 U
(37.4 to 36.9)		SV-11-110820	11/08/20	**3.51 J**	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	1.36 U	0.590 U	**2.85**	0.793 U	0.908 U	1.07 U	1.12 U	0.704 U	0.875 U	0.511 U
(duplicate)		SV-902-110820	11/08/20	**1.79 J**	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	1.36 U	0.590 U	1.88 U	0.793 U	0.908 U	1.07 U	1.12 U	0.704 U	0.875 U	0.511 U
		SV-11-020621	02/06/21	0.694 U	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	1.36 U	0.590 U	1.88 U	0.793 U	0.908 U	1.07 U	1.12 U	0.704 U	0.875 U	0.511 U
		SV-11-050521	05/05/21	0.694 U	3.30 U	2.22 U	0.867 U	2.15 U	0.851 U	**3.03**	**120**	1.88 U	0.793 U	0.908 U	1.07 U	1.12 U	0.704 U	0.875 U	0.511 U
SV-12	Valley Street	SV-12-071620	07/16/20	**1.21**	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	**7.40**	0.590 U	**6.40**	0.793 U	0.908 U	1.07 U	**1.88**	0.704 U	0.875 U	0.511 U
(39.1 to 38.6)		SV-12-110820	11/08/20	**3.47**	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	**3.19**	0.590 U	1.88 U	0.793 U	0.908 U	**2.14**	**1.90**	0.704 U	0.875 U	0.511 U
		SV-12-020521	02/05/21	0.694 U	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	**1.72**	0.590 U	1.88 U	0.793 U	0.908 U	1.07 U	1.12 U	0.704 U	0.875 U	0.511 U
		SV-12-050221	05/02/21	0.694 U	3.30 U	2.22 U	0.867 U	2.15 U	0.851 U	**2.41**	**3.51**	**3.92**	0.793 U	0.908 U	1.07 U	**1.42**	0.704 U	0.875 U	0.511 U
SV-13	Valley Street	SV-13-071620	07/16/20	0.694 U	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	**3.23**	**1.04**	**9.57**	0.793 U	0.908 U	1.07 U	**1.64**	0.704 U	0.875 U	0.511 U
(32.9 to 32.4)		SV-13-110820	11/08/20	**3.47**	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	**3.46**	0.590 U	1.88 U	0.793 U	0.908 U	1.07 U	**2.51**	0.704 U	0.875 U	0.511 U
		SV-13-020521	02/05/21	0.694 U	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	**2.62**	**5.90**	1.88 U	0.793 U	0.908 U	1.07 U	**1.17**	0.704 U	0.875 U	0.511 U
SV-14	Roy Street	SV-14-071620	07/16/20	0.694 U	**11.3**	**12.5**	**5.20**	**1.57**	0.851 U	**3.61**	0.590 U	**6.48**	0.793 U	0.908 U	1.07 U	**6.01**	0.704 U	0.875 U	0.511 U
(35.4 to 34.9)		SV-14-120220	12/02/20	**1.74**	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	1.36 U	0.590 U	**2.11**	0.793 U	0.908 U	1.07 U	**5.36**	0.704 U	0.875 U	0.511 U
		SV-14-020321	02/03/21	0.694 U	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	1.36 U	0.590 U	1.88 U	0.793 U	0.908 U	1.07 U	**3.70**	0.704 U	0.875 U	0.511 U
		SV-14-050421	05/04/21	0.694 U	3.30 U	2.22 U	0.867 U	2.15 U	0.851 U	**1.42**	**1.96**	1.88 U	0.793 U	0.908 U	1.07 U	**4.55**	0.704 U	0.875 U	0.511 U
SV-15	Roy Street	SV-15-071620	07/16/20	**2.79**	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	1.36 U	0.590 U	**3.88**	0.793 U	0.908 U	1.07 U	**4.89**	0.704 U	0.875 U	0.511 U
(28.5 to 28.0)		SV-15-120220	12/02/20	**4.20**	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	1.36 U	0.590 U	**26.0**	0.793 U	0.908 U	1.07 U	**4.50**	0.704 U	0.875 U	0.511 U
		SV-15-020321	02/03/21	0.694 U	3.30 U	2.22 U	0.867 U	0.689 U	**0.889**	1.36 U	0.590 U	**15.3**	0.793 U	0.908 U	1.07 U	**2.84**	0.704 U	0.875 U	0.511 U
		SV-15-050421	05/04/21	0.694 U	3.30 U	2.22 U	0.867 U	2.15 U	0.851 U	1.36 U	**0.970**	1.88 U	0.793 U	0.908 U	1.07 U	**2.66**	0.704 U	0.875 U	**31.7**

Table G-11

Soil Vapor Analytical Results
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Location Description	Sample Name	Sample Date	1,1,1-Trichloroethane	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromoethane (ethylene dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (ethylene dichloride)	1,2-Dichloropropane	1,2-Dichlorotetrafluoroethane	1,3,5-Trimethylbenzene	1,3-Butadiene	1,3-Dichlorobenzene	1,4-Dichlorobenzene
			Screening Level	**76,000**	**1.4**	**3.0**	**76,000**	**52**	**3,000**	**30**	**910**	**0.14**	**3,000**	**3.2**	**23**	**–**	**910**	**2.8**	**–**	**7.6**
SV-16	8th Avenue	SV-16-071520	07/15/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**1.37**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
(37.5 to 37.0)	North	SV-16-111920	11/19/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**8.79**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	**2.23**	4.43 U	1.20 U	1.20 U
		SV-16-020721	02/07/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**1.15**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-16-051021	05/10/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**3.72**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
SV-17	8th Avenue	SV-17-071620	07/16/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**1.78**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
(36.6 to 36.1)	North	SV-17-110220	11/02/20	**31.1**	1.37 U	1.09 U	1.53 U	**1.23**	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-17-020721	02/07/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**3.96**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	**1.38**	4.43 U	1.20 U	1.20 U
		SV-17-050621	05/06/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
SV-18	8th Avenue	SV-18-071620	07/16/20	**48.2**	1.37 U	1.09 U	1.53 U	**2.02**	0.793 U	4.66 U	**1.44**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
(36.6 to 36.1)	North	SV-18-110220	11/02/20	**115**	1.37 U	1.09 U	1.53 U	**4.37**	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-18-020721	02/07/21	**75.6**	1.37 U	1.09 U	1.53 U	**3.86**	0.793 U	4.66 U	**3.42**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	**1.36**	4.43 U	1.20 U	1.20 U
		SV-18-050621	05/06/21	**105**	1.37 U	1.09 U	1.53 U	**4.89**	0.793 U	4.66 U	**3.67**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	**1.01**	4.43 U	1.20 U	1.20 U
SV-19	9th Avenue	SV-19-071520	07/15/20	**3.61**	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**2.59**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
(29.7 to 29.2)	North	SV-19-110820	11/08/20	**1.76**	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-19-020721	02/07/21	**3.23**	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-19-050421	05/04/21	**3.37**	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
SV-20	9th Avenue	SV-20-071520	07/15/20	**3.62**	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**2.95**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
(25.7 to 25.2)	North	SV-20-110820	11/08/20	**5.71**	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-20-020721	02/07/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-20-050521	05/05/21	**3.42**	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
SV-21	Alley Between	SV-21-071520	07/15/20	**5.49**	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**2.11**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
(29.8 to 29.3)	8th & 9th	SV-21-110920	11/09/20	**3.37**	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-21-020321	02/03/21	**1.56**	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**3.88**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	**1.36**	4.43 U	1.20 U	**1.90**
		SV-21-050421	05/04/21	**2.51**	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
(duplicate)		SV-906-050421	05/04/21	**2.67**	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
SV-22	Alley Between	SV-22-071520	07/15/20	**7.02**	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**2.26**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
(25.7 to 25.2)	8th & 9th	SV-22-110920	11/09/20	**5.15**	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-22-020321	02/03/21	**3.57**	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-22-050421	05/04/21	**2.86**	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**1.09**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
SV-23	Alley Between	SV-23-071420	07/14/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**1.24**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
(27.9 to 27.4)	8th & 9th	SV-23-110920	11/09/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-23-020321	02/03/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**3.65**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	**1.12**	4.43 U	1.20 U	1.20 U
		SV-23-050421	05/04/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
SV-24	Alley Between	SV-24-071420	07/14/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
(23.8 to 23.3)	8th & 9th	SV-24-110920	11/09/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-24-020321	02/03/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**448 J**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	**127 J**	4.43 U	1.20 U	1.20 U
		SV-24-050421	05/04/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U

Table G-11

Soil Vapor Analytical Results
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Location Description	Sample Name	Sample Date	1,4-Dioxane	2,2,4-Trimethylpentane	2-Butanone (MEK)	2-Chlorotoluene	2-Propanol (isopropanol)	4-Ethyltoluene	4-Methyl-2-pentanone (MIBK)	Acetone	Allyl chloride	Benzene	Benzyl chloride	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon tetrachloride	Chlorobenzene
Screening Level				**17**	**–**	**76,000**	**–**	**–**	**–**	**46,000**	**470,000**	**14**	**11**	**1.7**	**2.3**	**76**	**76**	**11,000**	**14**	**760**
SV-16	8th Avenue	SV-16-071520	07/15/20	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**8.60**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**7.38**	1.26 U	0.924 U
(37.5 to 37.0)	North	SV-16-111920	11/19/20	**1.31**	0.934 U	**4.07**	1.03 U	3.07 U	0.982 U	5.12 U	**32.1**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**5.23**	1.26 U	0.924 U
		SV-16-020721	02/07/21	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**13.3**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**6.79**	1.26 U	0.924 U
		SV-16-051021	05/10/21	0.721 U	0.934 U	**14.7**	1.03 U	3.39 U	0.982 U	5.12 U	**9.24**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	0.622 U	1.26 U	0.924 U
SV-17	8th Avenue	SV-17-071620	07/16/20	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	**1.03**	5.12 U	**11.0**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**20.5**	1.26 U	0.924 U
(36.6 to 36.1)	North	SV-17-110220	11/02/20	0.721 U	0.934 U	3.69 U	1.03 U	**5.68**	0.982 U	5.12 U	**10.0**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**16.6**	1.26 U	0.924 U
		SV-17-020721	02/07/21	0.721 U	**13.7**	3.69 U	1.03 U	3.07 U	**1.02**	5.12 U	**83.4**	0.626 U	**7.03**	1.04 U	1.34 U	6.21 U	0.776 U	**7.66**	1.26 U	0.924 U
		SV-17-050621	05/06/21	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**6.34**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**25.2**	1.26 U	0.924 U
SV-18	8th Avenue	SV-18-071620	07/16/20	0.721 U	**1.32**	3.69 U	1.03 U	**3.39**	**1.29**	5.12 U	**8.44**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**4.95**	1.26 U	0.924 U
(36.6 to 36.1)	North	SV-18-110220	11/02/20	**1.03**	0.934 U	3.69 U	1.03 U	**3.42**	0.982 U	5.12 U	**11.6**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**13.2**	1.26 U	0.924 U
		SV-18-020721	02/07/21	**2.07**	0.934 U	**6.10**	1.03 U	**46.5**	0.982 U	5.12 U	**54.4**	0.626 U	**0.716**	1.04 U	1.34 U	6.21 U	0.776 U	**12.9**	1.26 U	0.924 U
		SV-18-050621	05/06/21	0.721 U	**5.28**	**4.75**	1.03 U	**18.7**	0.982 U	5.12 U	**33.5**	0.626 U	**4.92**	1.04 U	1.34 U	6.21 U	0.776 U	0.622 U	1.26 U	0.924 U
SV-19	9th Avenue	SV-19-071520	07/15/20	0.721 U	**1.19**	3.69 U	1.03 U	3.07 U	**1.96**	5.12 U	**17.9**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**2.08**	1.26 U	0.924 U
(29.7 to 29.2)	North	SV-19-110820	11/08/20	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	2.97 U	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	0.622 U	1.26 U	0.924 U
		SV-19-020721	02/07/21	**6.27**	0.934 U	**19.2**	1.03 U	**26.5**	0.982 U	5.12 U	**30.2**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**4.08**	1.26 U	0.924 U
		SV-19-050421	05/04/21	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**12.0**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**4.45**	1.26 U	0.924 U
SV-20	9th Avenue	SV-20-071520	07/15/20	0.721 U	0.934 U	**18.4**	1.03 U	3.07 U	**2.33**	5.12 U	**9.89**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**2.95**	1.26 U	0.924 U
(25.7 to 25.2)	North	SV-20-110820	11/08/20	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**5.68**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**5.23**	1.26 U	0.924 U
		SV-20-020721	02/07/21	0.721 U	0.934 U	**5.34**	1.03 U	3.07 U	0.982 U	5.12 U	**39.2**	0.626 U	**8.82**	1.04 U	1.34 U	6.21 U	0.776 U	**27.8**	1.26 U	0.924 U
		SV-20-050521	05/05/21	0.721 U	0.934 U	3.69 U	1.03 U	**9.86**	0.982 U	5.12 U	**6.77**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**10.1**	1.26 U	0.924 U
SV-21	Alley Between	SV-21-071520	07/15/20	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	**1.60**	5.12 U	**10.8**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**14.4**	1.26 U	0.924 U
(29.8 to 29.3)	8th & 9th	SV-21-110920	11/09/20	0.721 U	0.934 U	3.69 U	1.03 U	**4.84**	0.982 U	5.12 U	**5.13**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**6.94**	1.26 U	0.924 U
		SV-21-020321	02/03/21	0.721 U	**15.7**	**3.77**	1.03 U	**8.50**	0.982 U	5.12 U	**34.0**	0.626 U	**7.99**	1.04 U	1.34 U	6.21 U	0.776 U	0.622 U	1.26 U	0.924 U
		SV-21-050421	05/04/21	0.721 U	0.934 U	**9.05**	1.03 U	3.07 U	0.982 U	5.12 U	**7.70 J**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	0.622 U	1.26 U	0.924 U
(duplicate)		SV-906-050421	05/04/21	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**3.52 J**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	0.622 U	1.26 U	0.924 U
SV-22	Alley Between	SV-22-071520	07/15/20	0.721 U	0.934 U	3.69 U	1.03 U	**3.39**	**1.54**	5.12 U	**23.7**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**31.4**	1.26 U	0.924 U
(25.7 to 25.2)	8th & 9th	SV-22-110920	11/09/20	0.721 U	0.934 U	3.69 U	1.03 U	**11.9**	0.982 U	5.12 U	2.97 U	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**10.2**	1.26 U	0.924 U
		SV-22-020321	02/03/21	**0.767**	0.934 U	**4.92**	1.03 U	**3.81**	0.982 U	5.12 U	**21.3**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**13.0**	1.26 U	0.924 U
		SV-22-050421	05/04/21	0.721 U	**1.28**	**6.07**	1.03 U	**17.9**	0.982 U	5.12 U	**17.8**	0.626 U	**0.639**	1.04 U	1.34 U	6.21 U	0.776 U	**30.0**	1.26 U	0.924 U
SV-23	Alley Between	SV-23-071420	07/14/20	0.721 U	0.934 U	3.69 U	1.03 U	**4.01**	**1.02**	5.12 U	**10.3**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**11.1**	1.26 U	0.924 U
(27.9 to 27.4)	8th & 9th	SV-23-110920	11/09/20	0.721 U	**2.71**	3.69 U	1.03 U	**14.7**	0.982 U	5.12 U	**9.32**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**9.43**	1.26 U	0.924 U
		SV-23-020321	02/03/21	0.721 U	**8.41**	3.69 U	1.03 U	**5.73**	0.982 U	5.12 U	**8.98**	0.626 U	**5.30**	1.04 U	1.34 U	6.21 U	0.776 U	**11.4**	1.26 U	0.924 U
		SV-23-050421	05/04/21	0.721 U	0.934 U	**8.91**	1.03 U	3.07 U	0.982 U	5.12 U	**17.1**	0.626 U	**5.49**	1.04 U	1.34 U	6.21 U	0.776 U	0.622 U	1.26 U	0.924 U
SV-24	Alley Between	SV-24-071420	07/14/20	0.721 U	**7570**	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**11.5 J**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**9.03 J**	1.26 U	0.924 U
(23.8 to 23.3)	8th & 9th	SV-24-110920	11/09/20	0.721 U	**7990**	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**4.09 J**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	0.622 U	1.26 U	0.924 U
		SV-24-020321	02/03/21	0.721 U	**5,050**	3.69 U	1.03 U	3.07 U	**108** J	5.12 U	**3.61 J**	0.626 U	**273 J**	1.04 U	1.34 U	6.21 U	0.776 U	0.622 U	1.26 U	0.924 U
		SV-24-050421	05/04/21	0.721 U	**5,190**	**247 J**	1.03 U	3.07 U	0.982 U	5.12 U	2.97 U	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	0.622 U	1.26 U	0.924 U

Table G-11

Soil Vapor Analytical Results
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Location Description	Sample Name	Sample Date	Chloroethane	Chloroform	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Cyclohexane	Dibromochloromethane	Dichlorodifluoromethane	Ethanol	Ethylbenzene	Heptane	Hexachloro-1,3-butadiene	Isopropylbenzene (cumene)	m&p-Xylene	Methyl butyl ketone (2-hexanone)	Methyl methacrylate	Methyl tert-butyl ether (MTBE)
			Screening Level	**150,000**	**3.6**	**1,400**	**–**	**–**	**91,000**	**–**	**1,500**	**–**	**15,000**	**6,100**	**3.8**	**6,100**	**1,500**	**460**	**11,000**	**320**
SV-16	8th Avenue	SV-16-071520	07/15/20	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**3.18**	**26.8**	0.867 U	0.818 U	6.73 U	0.983 U	**2.34**	5.11 U	0.819 U	0.721 U
(37.5 to 37.0)	North	SV-16-111920	11/19/20	0.528 U	0.973 U	**1.63**	0.793 U	0.908 U	0.689 U	1.70 U	**1.92**	**30.4**	0.867 U	0.818 U	6.73 U	0.983 U	**5.98**	5.11 U	0.819 U	0.721 U
		SV-16-020721	02/07/21	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	**6.68**	1.70 U	**2.49**	**31.1**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-16-051021	05/10/21	0.528 U	0.973 U	**0.725**	**1.17**	0.908 U	0.689 U	1.70 U	**2.22**	**36.8**	**2.28**	0.818 U	6.73 U	0.983 U	**7.85**	5.11 U	0.819 U	0.721 U
SV-17	8th Avenue	SV-17-071620	07/16/20	0.528 U	**9.00**	0.413 U	0.793 U	0.908 U	**0.758**	1.70 U	**2.64**	**13.9**	0.867 U	**1.30**	6.73 U	0.983 U	**2.72**	5.11 U	0.819 U	0.721 U
(36.6 to 36.1)	North	SV-17-110220	11/02/20	0.528 U	**12.3**	**0.558**	0.793 U	0.908 U	0.689 U	1.70 U	**1.53**	**21.9**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-17-020721	02/07/21	0.528 U	**33.7**	0.413 U	0.793 U	0.908 U	**9.75**	1.70 U	**2.23**	**42.4**	**2.28**	**10.1**	6.73 U	0.983 U	**8.11**	5.11 U	0.819 U	0.721 U
		SV-17-050621	05/06/21	0.528 U	**84.2**	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**2.14**	**67.9**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
SV-18	8th Avenue	SV-18-071620	07/16/20	0.528 U	0.973 U	**1.22**	0.793 U	0.908 U	0.689 U	1.70 U	**2.72**	**23.8**	0.867 U	**0.949**	6.73 U	0.983 U	**4.29**	5.11 U	0.819 U	0.721 U
(36.6 to 36.1)	North	SV-18-110220	11/02/20	0.528 U	**12.9**	**0.640**	0.793 U	0.908 U	0.689 U	1.70 U	**1.03**	**18.2**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-18-020721	02/07/21	0.528 U	**8.57**	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**1.17**	**224** J+	**1.08**	0.818 U	6.73 U	0.983 U	**3.58**	5.11 U	0.819 U	0.721 U
		SV-18-050621	05/06/21	0.528 U	**7.11**	**0.958**	0.793 U	0.908 U	**9.75**	1.70 U	**1.23**	**251** J	**3.72**	**4.50**	6.73 U	0.983 U	**14.3**	5.11 U	0.819 U	0.721 U
SV-19	9th Avenue	SV-19-071520	07/15/20	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**30.1**	**17.3**	**0.902**	**1.07**	6.73 U	0.983 U	**5.51**	5.11 U	0.819 U	0.721 U
(29.7 to 29.2)	North	SV-19-110820	11/08/20	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**10.8**	**86.2**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-19-020721	02/07/21	0.528 U	0.973 U	**0.485**	0.793 U	0.908 U	**6.16**	1.70 U	**31.4**	**47.3**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-19-050421	05/04/21	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**21.2**	**76.9**	0.867 U	0.818 U	6.73 U	0.983 U	**2.15**	5.11 U	0.819 U	0.721 U
SV-20	9th Avenue	SV-20-071520	07/15/20	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**38.1**	**16.1**	**1.02**	0.818 U	6.73 U	0.983 U	**4.31**	5.11 U	0.819 U	0.721 U
(25.7 to 25.2)	North	SV-20-110820	11/08/20	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**41.1**	**33.6**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-20-020721	02/07/21	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	**73.0**	1.70 U	0.989 U	**11.6**	**0.871**	**19.7**	6.73 U	0.983 U	**2.58**	5.11 U	0.819 U	0.721 U
		SV-20-050521	05/05/21	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**25.6**	**209** J	**0.936**	0.818 U	6.73 U	0.983 U	**3.25**	5.11 U	0.819 U	0.721 U
SV-21	Alley Between	SV-21-071520	07/15/20	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**3.26**	**14.1**	0.867 U	0.818 U	6.73 U	0.983 U	**2.69**	5.11 U	0.819 U	0.721 U
(29.8 to 29.3)	8th & 9th	SV-21-110920	11/09/20	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**1.91**	**19.2**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-21-020321	02/03/21	0.528 U	0.973 U	**0.527**	0.793 U	0.908 U	**5.54**	1.70 U	**2.06**	**39.4**	**2.32**	**10.3**	6.73 U	0.983 U	**8.02**	5.11 U	0.819 U	0.721 U
		SV-21-050421	05/04/21	0.528 U	0.973 U	**0.492**	0.793 U	0.908 U	0.689 U	1.70 U	**1.93**	**55.8** J	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
(duplicate)		SV-906-050421	05/04/21	0.528 U	0.973 U	**0.436**	0.793 U	0.908 U	0.689 U	1.70 U	**1.98**	**12.6** J	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
SV-22	Alley Between	SV-22-071520	07/15/20	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	0.989 U	**11.1**	0.867 U	**0.875**	6.73 U	0.983 U	**3.43**	5.11 U	0.819 U	0.721 U
(25.7 to 25.2)	8th & 9th	SV-22-110920	11/09/20	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**1.68**	**54.1**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-22-020321	02/03/21	0.528 U	0.973 U	**0.744**	0.793 U	0.908 U	0.689 U	1.70 U	**1.68**	**12.9**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-22-050421	05/04/21	0.528 U	0.973 U	**0.500**	0.793 U	0.908 U	**1.03**	1.70 U	**1.88**	**236** J	**0.884**	**0.961**	6.73 U	0.983 U	**2.90**	5.11 U	0.819 U	0.721 U
SV-23	Alley Between	SV-23-071420	07/14/20	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	0.989 U	**17.9**	0.867 U	0.818 U	6.73 U	0.983 U	**2.52**	5.11 U	0.819 U	0.721 U
(27.9 to 27.4)	8th & 9th	SV-23-110920	11/09/20	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	**0.971**	1.70 U	**1.48**	**37.9**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-23-020321	02/03/21	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	**4.92**	1.70 U	**1.48**	**45.4**	**1.90**	**6.22**	6.73 U	0.983 U	**6.59**	5.11 U	0.819 U	0.721 U
		SV-23-050421	05/04/21	0.528 U	0.973 U	**0.653**	0.793 U	0.908 U	0.689 U	1.70 U	**1.38**	**23.2**	**1.98**	0.818 U	6.73 U	0.983 U	**6.11**	5.11 U	0.819 U	0.721 U
SV-24	Alley Between	SV-24-071420	07/14/20	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	0.989 U	**18.7** J	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
(23.8 to 23.3)	8th & 9th	SV-24-110920	11/09/20	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	0.989 U	**11.0** J	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-24-020321	02/03/21	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	0.989 U	**13.0** J	**166** J	**67.1** J	6.73 U	**10.6** J	**607** J	5.11 U	0.819 U	0.721 U
		SV-24-050421	05/04/21	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	0.989 U	**6.88** J	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U

Table G-11

Soil Vapor Analytical Results
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Location Description	Sample Name	Sample Date	Methylene chloride	Naphthalene	n-Hexane (hexane)	o-Xylene	Propene	Styrene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trichloroethene (TCE)	Trichlorofluoromethane	Vinyl acetate	Vinyl bromide (bromoethene)	Vinyl chloride
Screening Level				**2,200**	**2.5**	**11,000**	**1,500**	**–**	**15,000**	**320**	**30,000**	**76,000**	**610**	**–**	**11**	**11,000**	**3,000**	**5.6**	**9.5**
SV-16	8th Avenue	SV-16-071520	07/15/20	0.694 U	3.30 U	2.22 U	**0.958**	0.689 U	0.851 U	**6.86**	0.590 U	**3.54**	0.793 U	0.908 U	1.07 U	**11.6**	0.704 U	0.875 U	0.511 U
(37.5 to 37.0)	North	SV-16-111920	11/19/20	0.694 U	3.30 U	2.22 U	**2.24**	0.689 U	0.851 U	**4.20**	0.590 U	1.88 U	0.793 U	0.908 U	1.07 U	**8.65**	0.704 U	0.875 U	0.511 U
		SV-16-020721	02/07/21	0.694 U	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	**2.83**	0.590 U	1.88 U	0.793 U	0.908 U	1.07 U	**5.37**	0.704 U	0.875 U	0.511 U
		SV-16-051021	05/10/21	0.694 U	3.30 U	2.22 U	**2.51**	2.15 U	0.851 U	**153**	**16.3**	1.88 U	**1.29**	0.908 U	**12.8**	**4.96**	0.704 U	0.875 U	0.511 U
SV-17	8th Avenue	SV-17-071620	07/16/20	0.694 U	3.30 U	2.22 U	**0.98**	0.689 U	0.851 U	**4.80**	0.590 U	**3.45**	0.793 U	0.908 U	1.07 U	**10.6**	0.704 U	0.875 U	0.511 U
(36.6 to 36.1)	North	SV-17-110220	11/02/20	0.694 U	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	**6.65**	0.590 U	1.88 U	0.793 U	0.908 U	1.07 U	**5.84**	0.704 U	0.875 U	0.511 U
		SV-17-020721	02/07/21	**0.705**	3.30 U	**27.8**	**2.14**	0.689 U	0.851 U	**1.51**	0.590 U	**23.0**	0.793 U	0.908 U	1.07 U	**2.62**	0.704 U	0.875 U	0.511 U
		SV-17-050621	05/06/21	0.694 U	3.30 U	2.22 U	0.867 U	2.15 U	0.851 U	**1.79**	0.590 U	1.88 U	0.793 U	0.908 U	1.07 U	**3.03**	0.704 U	0.875 U	0.511 U
SV-18	8th Avenue	SV-18-071620	07/16/20	**4.93**	3.30 U	2.22 U	**1.58**	0.689 U	0.851 U	1.36 U	0.590 U	**6.22**	0.793 U	0.908 U	1.07 U	**1.53**	0.704 U	0.875 U	0.511 U
(36.6 to 36.1)	North	SV-18-110220	11/02/20	0.694 U	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	1.36 U	0.590 U	1.88 U	0.793 U	0.908 U	1.07 U	1.12 U	0.704 U	0.875 U	0.511 U
		SV-18-020721	02/07/21	0.694 U	3.30 U	2.22 U	**0.997**	0.689 U	0.851 U	1.36 U	0.590 U	**3.55**	0.793 U	0.908 U	1.07 U	1.12 U	0.704 U	0.875 U	0.511 U
		SV-18-050621	05/06/21	**1.14**	3.30 U	**8.81**	**4.60**	2.15 U	0.851 U	1.36 U	0.590 U	**33.4**	0.793 U	0.908 U	1.07 U	1.12 U	0.704 U	0.875 U	0.511 U
SV-19	9th Avenue	SV-19-071520	07/15/20	**2.32**	3.30 U	**2.41**	**1.99**	0.689 U	0.851 U	**46.7**	0.590 U	**5.20**	0.793 U	0.908 U	1.07 U	**54.4**	0.704 U	0.875 U	0.511 U
(29.7 to 29.2)	North	SV-19-110820	11/08/20	**4.48**	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	**15.1**	0.590 U	**4.86**	0.793 U	0.908 U	1.07 U	**19.8**	0.704 U	0.875 U	0.511 U
		SV-19-020721	02/07/21	0.694 U	3.30 U	2.22 U	0.867 U	**0.811**	0.851 U	**20.4**	**3.16**	1.88 U	0.793 U	0.908 U	1.07 U	**45.5**	0.704 U	0.875 U	0.511 U
		SV-19-050421	05/04/21	0.694 U	3.30 U	2.22 U	0.867 U	2.15 U	0.851 U	**29.8**	**2.90**	**3.03**	0.793 U	0.908 U	1.07 U	**39.2**	0.704 U	0.875 U	0.511 U
SV-20	9th Avenue	SV-20-071520	07/15/20	**1.64**	3.30 U	**2.60**	**1.59**	0.689 U	0.851 U	**74.7**	0.590 U	**3.96**	0.793 U	0.908 U	1.07 U	**67.4**	0.704 U	0.875 U	0.511 U
(25.7 to 25.2)	North	SV-20-110820	11/08/20	**0.795**	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	**99.8**	0.590 U	1.88 U	0.793 U	0.908 U	1.07 U	**80.9**	0.704 U	0.875 U	0.511 U
		SV-20-020721	02/07/21	0.694 U	3.30 U	**34.7**	**1.62**	**2.34**	0.851 U	1.36 U	0.590 U	**8.32**	0.793 U	0.908 U	1.07 U	1.12 U	0.704 U	0.875 U	0.511 U
		SV-20-050521	05/05/21	0.694 U	3.30 U	2.22 U	0.867 U	2.15 U	0.851 U	**49.4**	**1.75**	1.88 U	0.793 U	0.908 U	1.07 U	**45.4**	0.704 U	0.875 U	0.511 U
SV-21	Alley Between	SV-21-071520	07/15/20	0.694 U	3.30 U	2.22 U	**0.915**	0.689 U	0.851 U	**36.4**	0.590 U	**3.92**	0.793 U	0.908 U	1.07 U	**4.10**	0.704 U	0.875 U	0.511 U
(29.8 to 29.3)	8th & 9th	SV-21-110920	11/09/20	**1.03**	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	**19.8**	0.590 U	1.88 U	0.793 U	0.908 U	1.07 U	**1.88**	0.704 U	0.875 U	0.511 U
		SV-21-020321	02/03/21	**1.39**	3.30 U	**30.0**	**2.13**	**1.86**	0.851 U	**7.81**	0.590 U	**17.1**	0.793 U	0.908 U	**6.38**	1.12 U	0.704 U	0.875 U	0.511 U
		SV-21-050421	05/04/21	0.694 U	3.30 U	2.22 U	0.867 U	2.15 U	0.851 U	**13.6**	**3.16 J**	1.88 U	0.793 U	0.908 U	1.07 U	**1.66**	0.704 U	0.875 U	0.511 U
(duplicate)		SV-906-050421	05/04/21	0.694 U	3.30 U	2.22 U	0.867 U	2.15 U	0.851 U	**13.8**	0.590 UJ	1.88 U	0.793 U	0.908 U	1.07 U	**1.62**	0.704 U	0.875 U	0.511 U
SV-22	Alley Between	SV-22-071520	07/15/20	0.694 U	3.30 U	2.22 U	**1.28**	0.689 U	0.851 U	**14.9**	0.590 U	**4.78**	0.793 U	0.908 U	1.07 U	**4.86**	0.704 U	0.875 U	0.511 U
(25.7 to 25.2)	8th & 9th	SV-22-110920	11/09/20	**15.9**	3.30 U	**5.89**	0.867 U	0.689 U	0.851 U	**11.1**	0.590 U	**2.26**	0.793 U	0.908 U	1.07 U	**2.50**	0.704 U	0.875 U	0.511 U
		SV-22-020321	02/03/21	0.694 U	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	**8.08**	0.590 U	1.88 U	0.793 U	0.908 U	1.07 U	**1.26**	0.704 U	0.875 U	0.511 U
		SV-22-050421	05/04/21	0.694 U	3.30 U	**3.51**	**0.906**	2.15 U	0.851 U	**7.26**	**13.4**	**10.5**	0.793 U	0.908 U	1.07 U	**1.50**	0.704 U	0.875 U	0.511 U
SV-23	Alley Between	SV-23-071420	07/14/20	**2.99**	3.30 U	2.22 U	**0.98**	0.689 U	0.851 U	**9.30**	0.590 U	**4.52**	0.793 U	0.908 U	1.07 U	**2.23**	0.704 U	0.875 U	0.511 U
(27.9 to 27.4)	8th & 9th	SV-23-110920	11/09/20	**5.28**	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	**5.97**	0.590 U	**2.22**	0.793 U	0.908 U	1.07 U	1.12 U	0.704 U	0.875 U	0.511 U
		SV-23-020321	02/03/21	0.694 U	3.30 U	**18.4**	**1.82**	0.689 U	0.851 U	**3.23**	0.590 U	**11.2**	0.793 U	0.908 U	1.07 U	1.12 U	0.704 U	0.875 U	0.511 U
		SV-23-050421	05/04/21	**0.774**	3.30 U	2.22 U	0.867 U	**6.20**	0.851 U	**3.98**	0.590 U	1.88 U	0.793 U	0.908 U	1.07 U	1.12 U	0.704 U	0.875 U	0.511 U
SV-24	Alley Between	SV-24-071420	07/14/20	0.694 U	3.30 U	**9.73 J**	0.867 U	0.689 U	0.851 U	1.36 U	0.590 U	0.753 U	0.793 U	0.908 U	1.07 U	1.12 U	0.704 U	0.875 U	0.511 U
(23.8 to 23.3)	8th & 9th	SV-24-110920	11/09/20	0.694 U	**19.7 J**	**19.6 J**	0.867 U	0.689 U	0.851 U	1.36 U	0.590 U	1.88 U	0.793 U	0.908 U	1.07 U	1.12 U	0.704 U	0.875 U	0.511 U
		SV-24-020321	02/03/21	0.694 U	**44.8 J**	**127 J**	**163 J**	0.689 U	0.851 U	1.36 U	0.590 U	**535**	0.793 U	0.908 U	1.07 U	1.12 U	0.704 U	0.875 U	0.511 U
		SV-24-050421	05/04/21	0.694 U	3.30 U	**7.30 J**	0.867 U	2.15 U	0.851 U	1.36 U	0.590 U	**2.21 J**	0.793 U	0.908 U	1.07 U	1.12 U	0.704 U	0.875 U	0.511 U

Table G-11

Soil Vapor Analytical Results
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Location Description	Sample Name	Sample Date	1,1,1-Trichloroethane	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1,2-Trichlorotrifluoroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2,4-Trichlorobenzene	1,2,4-Trimethylbenzene	1,2-Dibromoethane (ethylene dibromide)	1,2-Dichlorobenzene	1,2-Dichloroethane (ethylene dichloride)	1,2-Dichloropropane	1,2-Dichlorotetrafluoroethane	1,3,5-Trimethylbenzene	1,3-Butadiene	1,3-Dichlorobenzene	1,4-Dichlorobenzene
			Screening Level	76,000	1.4	3.0	76,000	52	3,000	30	910	0.14	3,000	3.2	23	–	910	2.8	–	7.6
SV-25 (52.7 to 52.2) (duplicate)	Dexter Avenue North	SV-25-071520	07/15/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**9.33**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	**2.62**	4.43 U	1.20 U	1.20 U
		SV-25-110920	11/09/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**10.5 J**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	**2.12 J**	4.43 U	1.20 U	1.20 U
		SV-903-110920	11/09/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**6.38 J**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	**1.49 J**	4.43 U	1.20 U	1.20 U
		SV-25-020621	02/06/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-25-050521	05/05/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**2.09**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
SV-26 (46.7 to 46.2)	Dexter Avenue North	SV-26-071520	07/15/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**9.87**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	**3.16**	4.43 U	1.20 U	1.20 U
		SV-26-111120	11/11/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-26-050621	05/06/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**1.02**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
SV-27 (44.1 to 43.6) (duplicate)	Dexter Avenue North	SV-27-071520	07/15/20	**1.25**	1.37 U	1.09 U	**1.57**	0.802 U	0.793 U	4.66 U	**1.82**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-27-110920	11/09/20	**1.50**	1.37 U	1.09 U	**1.60**	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-27-020621	02/06/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-905-020621	02/06/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-27-050521	05/05/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**1.01**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
SV-28 (53.1 to 52.6)	Dexter Avenue North	SV-28-071720	07/17/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**1.95**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-28-110920	11/09/20	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-28-020621	02/06/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**1.40**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		SV-28-050521	05/05/21	1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	**1.20**	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		Number of Analytes Measured		113	113	113	113	113	113	113	113	113	113	113	113	113	113	113	113	113
		Number of Analytes Detected		34	0	0	2	11	1	0	64	0	0	0	0	0	18	0	0	2
		Frequency of Detection		30.1%	0.0%	0.0%	1.8%	9.7%	0.9%	0.0%	56.6%	0.0%	0.0%	0.0%	0.0%	0.0%	15.9%	0.0%	0.0%	1.8%
		Maximum Detection		115	–	–	1.60	14.1	0.923	–	448 J	–	–	–	–	–	127 J	–	–	1.90
		Minimum Detection		1.09 U	1.37 U	1.09 U	1.53 U	0.802 U	0.793 U	4.66 U	0.982 U	1.54 U	1.20 U	0.810 U	0.924 U	1.40 U	0.982 U	4.43 U	1.20 U	1.20 U
		Number Of Detections above SL		0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
		Frequency of Detection Above SL		0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%

Notes:
Laboratory analyses conducted by Air Toxics Ltd. of Folsom, CA (2013 samples) and Pace Analytical of Mount Juliet, TN (2018-2021 samples).
Volatile Organic Compounds (VOCs) analyzed by EPA Method TO-15 or Modified TO-15 Low Level Analysis.
Analytical results in micrograms per cubic meter (µg/m3).
Screening levels based on CLARC, July 2021, Vapor Intrusion Method B table, Sub-Slab Soil Gas Screening Levels. See Appendix K for complete Screening Level evaluation.
Screening level for m&p-xylenes and o-xylenes is applicable to total xylenes.
Probe screen elevations indicated below sample probe in parentheses.
– = Screening level not established or results not available
U = Not detected at a concentration exceeding laboratory reporting limit.
Detected results shown in **bold.**
Detections exceeding the screening level are shown in **bold and highlighted in gray.**
J = The identification of the analyte is acceptable; the reported value is an estimate.
J = The identification of the analyte is acceptable; the reported value is an estimate and likely biased high.
(duplicate) = Field duplicate. Samples collected concurrently.
Samples collected by SoundEarth Strategies in 2013 were only analyzed for PCE, TCE, cDCE, tDCE, and VC

Table G-11

Soil Vapor Analytical Results
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Location Description	Sample Name	Sample Date	1,4-Dioxane	2,2,4-Trimethylpentane	2-Butanone (MEK)	2-Chlorotoluene	2-Propanol (isopropanol)	4-Ethyltoluene	4-Methyl-2-pentanone (MIBK)	Acetone	Allyl chloride	Benzene	Benzyl chloride	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon tetrachloride	Chlorobenzene
Screening Level				**17**	**–**	**76,000**	**–**	**–**	**–**	**46,000**	**470,000**	**14**	**11**	**1.7**	**2.3**	**76**	**76**	**11,000**	**14**	**760**
SV-25	Dexter Avenue	SV-25-071520	07/15/20	0.721 U	0.934 U	3.69 U	**4.19**	3.07 U	**5.89**	5.12 U	**14.4**	0.626 U	**1.49**	1.04 U	1.34 U	6.21 U	0.776 U	**20.9**	1.26 U	0.924 U
(52.7 to 52.2)	North	SV-25-110920	11/09/20	0.721 U	**2.61 J**	3.69 U	1.03 U	3.07 UJ	**2.61 J**	5.12 U	**9.03 J**	0.626 U	**1.01**	1.04 U	1.34 U	6.21 U	0.776 U	0.622 UJ	1.26 U	0.924 U
(duplicate)		SV-903-110920	11/09/20	**0.789**	**1.70 J**	3.69 U	1.03 U	**8.11 J**	**1.89 J**	5.12 U	**18.0 J**	0.626 U	**0.818**	1.04 U	1.34 U	6.21 U	0.776 U	**4.45 J**	1.26 U	0.924 U
		SV-25-020621	02/06/21	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**9.17**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**5.01**	1.26 U	0.924 U
		SV-25-050521	05/05/21	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**11.6**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**16.2**	1.26 U	0.924 U
SV-26	Dexter Avenue	SV-26-071520	07/15/20	0.721 U	0.934 U	3.69 U	**3.98**	**5.19**	**6.18**	5.12 U	**18.8**	0.626 U	**4.57**	1.04 U	1.34 U	6.21 U	0.776 U	**20.2**	1.26 U	0.924 U
(46.7 to 46.2)	North	SV-26-111120	11/11/20	**1.21**	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**24.7**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**6.07**	1.26 U	0.924 U
		SV-26-050621	05/06/21	0.721 U	0.934 U	3.69 U	1.03 U	7.79 U	0.982 U	5.12 U	**12.8**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**111**	1.26 U	0.924 U
SV-27	Dexter Avenue	SV-27-071520	07/15/20	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	**1.78**	5.12 U	**15.8**	0.626 U	0.639 U	1.04 U	**2.75**	6.21 U	0.776 U	**7.56**	1.26 U	0.924 U
(44.1 to 43.6)	North	SV-27-110920	11/09/20	**14.9**	0.934 U	**5.54**	1.03 U	**5.73**	0.982 U	5.12 U	**73.0**	0.626 U	**0.661**	1.04 U	**2.13**	6.21 U	0.776 U	**5.20**	1.26 U	0.924 U
		SV-27-020621	02/06/21	0.721 U	0.934 UJ	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**4.71 J**	0.626 U	**0.901 J**	1.04 U	1.34 U	6.21 U	0.776 U	0.622 UJ	1.26 U	0.924 U
(duplicate)		SV-905-020621	02/06/21	0.721 U	**27.2 J**	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**15.2 J**	0.626 U	**4.25 J**	1.04 U	1.34 U	6.21 U	0.776 U	**44.8 J**	1.26 U	0.924 U
		SV-27-050521	05/05/21	0.721 U	**1.10**	3.69 U	1.03 U	3.07 U	**2.19**	5.12 U	**7.08**	0.626 U	0.639 U	1.04 U	**1.47**	6.21 U	0.776 U	**11.1**	1.26 U	0.924 U
SV-28	Dexter Avenue	SV-28-071720	07/17/20	0.721 U	0.934 U	3.69 U	1.03 U	**4.87**	**1.16**	5.12 U	**96.2**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**6.63**	1.26 U	0.924 U
(53.1 to 52.6)	North	SV-28-110920	11/09/20	0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**6.08**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**3.49**	1.26 U	0.924 U
		SV-28-020621	02/06/21	0.721 U	0.934 U	3.69 U	1.03 U	**4.01**	0.982 U	5.12 U	**17.8**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**4.89**	1.26 U	0.924 U
		SV-28-050521	05/05/21	0.721 U	**1.79**	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	**11.2**	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	**39.5**	1.26 U	0.924 U
Number of Analytes Measured				113	113	113	113	113	113	113	113	113	113	113	113	113	113	113	113	113
Number of Analytes Detected				18	28	29	3	45	24	0	106	0	29	0	3	0	1	84	9	0
Frequency of Detection				15.9%	24.8%	25.7%	2.7%	39.8%	21.2%	0.0%	93.8%	0.0%	25.7%	0.0%	2.7%	0.0%	0.9%	74.3%	8.0%	0.0%
Maximum Detection				14.9	7,990	277	4.19	50.8	108 J	–	114	–	273 J	–	2.75	–	1.45	140	7.43	–
Minimum Detection				0.721 U	0.934 U	3.69 U	1.03 U	3.07 U	0.982 U	5.12 U	2.97 U	0.626 U	0.639 U	1.04 U	1.34 U	6.21 U	0.776 U	0.622 U	1.26 U	0.924 U
Number Of Detections above SL				0	0	0	0	3	0	0	0	0	2	0	1	0	0	0	0	0
Frequency of Detection Above SL				0.0%	0.0%	0.0%	0.0%	2.7%	0.0%	0.0%	0.0%	0.0%	1.8%	0.0%	0.9%	0.0%	0.0%	0.0%	0.0%	0.0%

Notes:
Laboratory analyses conducted by Air Toxics Ltd. of Folsom, CA (2013 samples) and Pace Analytical of Mount Juliet, TN (2018-2021 samples).
Volatile Organic Compounds (VOCs) analyzed by EPA Method TO-15 or Modified TO-15 Low Level Analysis.
Analytical results in micrograms per cubic meter (µg/m3).
Screening levels based on CLARC, July 2021, Vapor Intrusion Method B table, Sub-Slab Soil Gas Screening Levels. See Appendix K for complete Screening Level evaluation.
Screening level for m&p-xylenes and o-xylenes is applicable to total xylenes.
Probe screen elevations indicated below sample probe in parentheses.
– = Screening level not established or results not available
U = Not detected at a concentration exceeding laboratory reporting limit.
Detected results shown in **bold.**
Detections exceeding the screening level are shown in **bold and highlighted in gray.**
J = The identification of the analyte is acceptable; the reported value is an estimate.
J = The identification of the analyte is acceptable; the reported value is an estimate and likely biased high.
(duplicate) = Field duplicate. Samples collected concurrently.
Samples collected by SoundEarth Strategies in 2013 were only analyzed for PCE, TCE, cDCE, tDCE, and VC

Table G-11

Soil Vapor Analytical Results
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Location Description	Sample Name	Sample Date	Chloroethane	Chloroform	Chloromethane	cis-1,2-Dichloroethene (cDCE)	cis-1,3-Dichloropropene	Cyclohexane	Dibromochloromethane	Dichlorodifluoromethane	Ethanol	Ethylbenzene	Heptane	Hexachloro-1,3-butadiene	Isopropylbenzene (cumene)	m&p-Xylene	Methyl butyl ketone (2-hexanone)	Methyl methacrylate	Methyl tert-butyl ether (MTBE)
Screening Level				**150,000**	**3.6**	**1,400**	**–**	**–**	**91,000**	**–**	**1,500**	**–**	**15,000**	**6,100**	**3.8**	**6,100**	**1,500**	**460**	**11,000**	**320**
SV-25	Dexter Avenue	SV-25-071520	07/15/20	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**3.26**	**14.2**	**3.58**	**1.24**	6.73 U	0.983 U	**14.7**	5.11 U	0.819 U	0.721 U
(52.7 to 52.2)	North	SV-25-110920	11/09/20	0.528 U	0.973 U	**1.25 J**	0.793 U	0.908 U	**0.868**	1.70 U	**2.58**	**25.8 J**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
(duplicate)		SV-903-110920	11/09/20	0.528 U	0.973 U	**0.865 J**	0.793 U	0.908 U	0.689 U	1.70 U	**2.58**	**87.5 J**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-25-020621	02/06/21	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**2.15**	**15.9**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-25-050521	05/05/21	0.528 U	0.973 U	**1.20**	0.793 U	0.908 U	**0.988**	1.70 U	**53.9**	**25.8**	**1.60**	0.818 U	6.73 U	0.983 U	**3.53**	5.11 U	0.819 U	0.721 U
SV-26	Dexter Avenue	SV-26-071520	07/15/20	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**3.60**	**20.2**	**3.85**	**9.98**	6.73 U	0.983 U	**13.0**	5.11 U	0.819 U	0.721 U
(46.7 to 46.2)	North	SV-26-111120	11/11/20	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**2.59**	**24.1**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-26-050621	05/06/21	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	**1.55**	1.70 U	**2.94**	**84.3**	0.867 U	0.818 U	6.73 U	0.983 U	**2.01**	5.11 U	**23.9**	0.721 U
SV-27	Dexter Avenue	SV-27-071520	07/15/20	0.528 U	**84.2**	**1.22**	0.793 U	0.908 U	0.689 U	1.70 U	**3.47**	**20.9**	**0.958**	0.818 U	6.73 U	0.983 U	**4.26**	5.11 U	0.819 U	0.721 U
(44.1 to 43.6)	North	SV-27-110920	11/09/20	0.528 U	**63.8**	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**2.88**	**52.6**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-27-020621	02/06/21	0.528 U	0.973 U	**1.05 J**	0.793 U	0.908 U	0.689 UJ	1.70 U	**2.24**	**10.2 J**	0.867 U	0.818 UJ	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
(duplicate)		SV-905-020621	02/06/21	0.528 U	0.973 U	0.413 UJ	0.793 U	0.908 U	**19.9 J**	1.70 U	**1.77**	**6.81 J**	0.867 U	**22.2 J**	6.73 U	0.983 U	**2.13**	5.11 U	0.819 U	0.721 U
		SV-27-050521	05/05/21	0.528 U	**46.8**	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**2.16**	**25.1**	**4.27**	**0.924**	6.73 U	0.983 U	**6.68**	5.11 U	0.819 U	0.721 U
SV-28	Dexter Avenue	SV-28-071720	07/17/20	0.528 U	**1.73**	**0.832**	0.793 U	0.908 U	**0.802**	1.70 U	**2.37**	**51.9**	**0.915**	0.818 U	6.73 U	0.983 U	**2.81**	5.11 U	0.819 U	0.721 U
(53.1 to 52.6)	North	SV-28-110920	11/09/20	0.528 U	**1.45**	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**2.84**	**12.9**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-28-020621	02/06/21	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	**15.4**	1.70 U	**2.11**	**30.7**	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
		SV-28-050521	05/05/21	0.528 U	0.973 U	0.413 U	0.793 U	0.908 U	0.689 U	1.70 U	**2.11**	**76.2**	0.867 U	0.818 U	6.73 U	0.983 U	**3.09**	5.11 U	0.819 U	0.721 U
Number of Analytes Measured				113	113	113	116	113	113	113	113	113	113	113	113	113	113	113	113	113
Number of Analytes Detected				0	18	43	5	0	34	0	94	113	32	22	0	1	49	0	2	0
Frequency of Detection				0.0%	15.9%	38.1%	4.3%	0.0%	30.1%	0.0%	83.2%	#####	28.3%	19.5%	0.0%	0.9%	43.4%	0.0%	1.8%	0.0%
Maximum Detection				–	84.2	24.2	9.99	–	78.9	–	53.9	447 J	166 J	67.1 J	–	10.6 J	607 J	–	23.9	–
Minimum Detection				0.528 U	0.973 U	0.413 U	0.120 U	0.908 U	0.689 U	1.70 U	0.989 U	4.30 J	0.867 U	0.818 U	6.73 U	0.983 U	1.73 U	5.11 U	0.819 U	0.721 U
Number Of Detections above SL				0	13	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Frequency of Detection Above SL				0.0%	11.5%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%

Notes:
Laboratory analyses conducted by Air Toxics Ltd. of Folsom, CA (2013 samples) and Pace Analytical of Mount Juliet, TN (2018-2021 samples).
Volatile Organic Compounds (VOCs) analyzed by EPA Method TO-15 or Modified TO-15 Low Level Analysis.
Analytical results in micrograms per cubic meter (µg/m3).
Screening levels based on CLARC, July 2021, Vapor Intrusion Method B table, Sub-Slab Soil Gas Screening Levels. See Appendix K for complete Screening Level evaluation.
Screening level for m&p-xylenes and o-xylenes is applicable to total xylenes.
Probe screen elevations indicated below sample probe in parentheses.
– = Screening level not established or results not available
U = Not detected at a concentration exceeding laboratory reporting limit.
Detected results shown in **bold.**
Detections exceeding the screening level are shown in **bold and highlighted in gray.**
J = The identification of the analyte is acceptable; the reported value is an estimate.
J = The identification of the analyte is acceptable; the reported value is an estimate and likely biased high.
(duplicate) = Field duplicate. Samples collected concurrently.
Samples collected by SoundEarth Strategies in 2013 were only analyzed for PCE, TCE, cDCE, tDCE, and VC

Table G-11

Soil Vapor Analytical Results
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Sample Location	Location Description	Sample Name	Sample Date	Methylene chloride	Naphthalene	n-Hexane (hexane)	o-Xylene	Propene	Styrene	Tetrachloroethene (PCE)	Tetrahydrofuran	Toluene	trans-1,2-Dichloroethene (tDCE)	trans-1,3-Dichloropropene	Trichloroethene (TCE)	Trichlorofluoromethane	Vinyl acetate	Vinyl bromide (bromoethene)	Vinyl chloride
Screening Level				**2,200**	**2.5**	**11,000**	**1,500**	**–**	**15,000**	**320**	**30,000**	**76,000**	**610**	**–**	**11**	**11,000**	**3,000**	**5.6**	**9.5**
SV-25	Dexter Avenue	SV-25-071520	07/15/20	0.694 U	3.30 U	2.22 U	**4.94**	0.689 U	0.851 U	**215**	0.590 U	**14.2**	0.793 U	0.908 U	1.07 U	**6.52**	0.704 U	0.875 U	0.511 U
(52.7 to 52.2)	North	SV-25-110920	11/09/20	**1.16**	3.30 U	2.22 U	0.867 U	0.689 UJ	0.851 U	**14.8 J**	**0.952**	**2.03**	0.793 U	0.908 U	1.07 U	**1.48 J**	0.704 U	0.875 U	0.511 U
(duplicate)		SV-903-110920	11/09/20	**1.53**	3.30 U	2.22 U	0.867 U	**1.58 J**	0.851 U	**54.0 J**	**0.708**	**2.09**	0.793 U	0.908 U	1.07 U	**2.33 J**	0.704 U	0.875 U	0.511 U
		SV-25-020621	02/06/21	0.694 U	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	**73.3**	0.590 U	1.88 U	0.793 U	0.908 U	1.07 U	**2.08**	0.704 U	0.875 U	0.511 U
		SV-25-050521	05/05/21	0.694 U	3.30 U	2.22 U	0.867 U	2.15 U	0.851 U	**121**	0.590 U	1.88 U	0.793 U	0.908 U	1.07 U	**4.11**	0.704 U	0.875 U	0.511 U
SV-26	Dexter Avenue	SV-26-071520	07/15/20	0.694 U	3.30 U	**39.5**	**5.12**	**480**	0.851 U	**66.9**	0.590 U	**15.4**	0.793 U	0.908 U	**2.61**	1.12 U	0.704 U	0.875 U	0.511 U
(46.7 to 46.2)	North	SV-26-111120	11/11/20	0.694 U	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	**105**	**1.11**	1.88 U	0.793 U	0.908 U	**2.37**	**1.44**	0.704 U	0.875 U	0.511 U
		SV-26-050621	05/06/21	0.694 U	3.30 U	2.22 U	0.867 U	2.15 U	0.851 U	**51.6**	0.590 U	1.88 U	0.793 U	0.908 U	1.07 U	1.12 U	0.704 U	0.875 U	0.511 U
SV-27	Dexter Avenue	SV-27-071520	07/15/20	0.694 U	3.30 U	2.22 U	**1.60**	0.689 U	0.851 U	**95.7**	0.590 U	**5.09**	0.793 U	0.908 U	1.07 U	**3.07**	0.704 U	0.875 U	0.511 U
(44.1 to 43.6)	North	SV-27-110920	11/09/20	**2.92**	3.30 U	2.22 U	0.867 U	**1.30**	0.851 U	**87.6**	**6.96**	1.88 U	0.793 U	0.908 U	1.07 U	**3.09**	0.704 U	0.875 U	0.511 U
		SV-27-020621	02/06/21	0.694 U	3.30 U	2.22 UJ	0.867 U	0.689 U	0.851 U	1.36 U	0.590 U	1.88 UJ	0.793 U	0.908 U	1.07 U	**1.16 J**	0.704 U	0.875 U	0.511 U
(duplicate)		SV-905-020621	02/06/21	0.694 U	3.30 U	**127 J**	0.867 U	0.689 U	0.851 U	1.36 U	0.590 U	**6.37 J**	0.793 U	0.908 U	1.07 U	**3.10 J**	0.704 U	0.875 U	0.511 U
		SV-27-050521	05/05/21	0.694 U	3.30 U	2.22 U	0.867 U	2.15 U	0.851 U	**65.9**	0.590 U	1.88 U	0.793 U	0.908 U	1.07 U	**1.84**	0.704 U	0.875 U	0.511 U
SV-28	Dexter Avenue	SV-28-071720	07/17/20	**5.69**	3.30 U	**4.37**	**1.23**	**1.89**	0.851 U	**31.6**	**1.09**	**5.54**	0.793 U	0.908 U	1.07 U	**1.78**	0.704 U	0.875 U	0.511 U
(53.1 to 52.6)	North	SV-28-110920	11/09/20	0.694 U	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	**79.4**	0.590 U	1.88 U	0.793 U	0.908 U	1.07 U	**2.09**	0.704 U	0.875 U	0.511 U
		SV-28-020621	02/06/21	0.694 U	3.30 U	2.22 U	0.867 U	0.689 U	0.851 U	**36.0**	0.590 U	1.88 U	0.793 U	0.908 U	1.07 U	**1.33**	0.704 U	0.875 U	0.511 U
		SV-28-050521	05/05/21	0.694 U	3.30 U	2.22 U	0.867 U	2.15 U	0.851 U	**55.7**	**4.28**	**4.60**	0.793 U	0.908 U	1.07 U	**1.76**	0.704 U	0.875 U	0.511 U
Number of Analytes Measured				113	113	113	113	113	113	116	113	113	116	113	116	113	113	113	116
Number of Analytes Detected				51	3	35	37	19	2	85	25	67	1	0	9	77	0	0	4
Frequency of Detection				45.1%	2.7%	31.0%	32.7%	16.8%	1.8%	73.3%	22.1%	59.3%	0.9%	0.0%	7.8%	68.1%	0.0%	0.0%	3.4%
Maximum Detection				24.9	44.8 J	127 J	163 J	480	1.42	215	120	535	1.29	–	17.4	80.9	–	–	473
Minimum Detection				0.694 U	3.30 U	0.705 U	0.867 U	0.689 U	0.851 U	1.36 U	0.590 U	0.753 UJ	0.580 U	0.908 U	0.160 U	1.12 U	0.704 U	0.875 U	0.037 U
Number Of Detections above SL				0	3	0	0	0	0	0	0	0	0	0	2	0	0	0	3
Frequency of Detection Above SL				0.0%	2.7%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	1.7%	0.0%	0.0%	0.0%	2.6%

Notes:
Laboratory analyses conducted by Air Toxics Ltd. of Folsom, CA (2013 samples) and Pace Analytical of Mount Juliet, TN (2018-2021 samples).
Volatile Organic Compounds (VOCs) analyzed by EPA Method TO-15 or Modified TO-15 Low Level Analysis.
Analytical results in micrograms per cubic meter (µg/m3).
Screening levels based on CLARC, July 2021, Vapor Intrusion Method B table, Sub-Slab Soil Gas Screening Levels. See Appendix K for complete Screening Level evaluation.
Screening level for m&p-xylenes and o-xylenes is applicable to total xylenes.
Probe screen elevations indicated below sample probe in parentheses.
– = Screening level not established or results not available
U = Not detected at a concentration exceeding laboratory reporting limit.
Detected results shown in **bold.**
Detections exceeding the screening level are shown in **bold and highlighted in gray.**
J = The identification of the analyte is acceptable; the reported value is an estimate.
J = The identification of the analyte is acceptable; the reported value is an estimate and likely biased high.
(duplicate) = Field duplicate. Samples collected concurrently.
Samples collected by SoundEarth Strategies in 2013 were only analyzed for PCE, TCE, cDCE, tDCE, and VC

Table G-12a

Estimated Hydraulic Conductivity Based On Grain Size Analyses
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Particle Type	Screen Size (microns)	Screen Size (cm)	B-205 (63 feet bgs)		B-206 (47 feet bgs)	
			Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$
Coarse Gravel	1"	2.5002	0.0000	–	0.0000	–
Fine Gravel	½"	1.2501	0.0000	0.00000	0.0224	0.01355
	3/8"	0.9500	0.0000	0.00000	0.0221	0.02082
	1/4"	0.6351	0.0034	0.00455	0.0108	0.01445
	4,757 (No. 4)	0.4757	0.0092	0.01720	0.0118	0.02206
Coarse Sand	3,364 (No. 6)	0.3364	0.0053	0.01368	0.0151	0.03898
	2,000 (No. 10)	0.2000	0.0078	0.03156	0.0176	0.07121
Medium Sand	1414 (No. 14)	0.1414	0.0038	0.02332	0.0129	0.07915
	1000 (No. 18)	0.1000	0.0059	0.05118	0.0187	0.16220
	707 (No. 25)	0.0707	0.0135	0.16555	0.0339	0.41571
	500 (No. 35)	0.0500	0.0351	0.60849	0.0469	0.81306
	420 (No. 40)	0.0420	0.0200	0.44240	0.0246	0.54415
Fine Sand	354 (No. 45)	0.0354	0.0364	0.95643	0.0525	1.37946
	250 (No. 60)	0.0250	0.1109	3.84025	0.0998	3.45588
	177 (No. 80)	0.0177	0.1207	5.90739	0.0657	3.21554
	125 (No. 120)	0.0125	0.1108	7.66826	0.0942	6.51941
	74 (No. 200)	0.0074	0.1328	14.44952	0.1007	10.95683
Silt and Clay	53 (No. 270)	0.0053	0.1280	20.99405	0.1222	20.04276
	37 (No. 400)	0.0037	0.0965	22.43055	0.0844	19.61801
	25	0.0025	0.0533	18.09968	0.0479	16.25578
	15.6	0.00156	0.0533	28.07513	0.0479	25.21498
	5	0.0005	0.0533	66.84813	0.0479	60.03797
		Sum	1.00	190.627	1.00	168.892
		Estimated Maximum k (cm/sec)		2.62E-03		3.33E-03
		Estimated Median k (cm/sec)		1.12E-03		1.43E-03
		Estimated Minimum k (cm/sec)		3.71E-04		4.73E-04
		% Gravel	1.3		6.7	
		% Sand	60.3		58.3	
		% Silt and Clay	38.5		35.0	

Notes:

1. Kozeny-Carman Equation:

$$k = [\Theta^3/(1-\Theta)^2]*(1.99 \times 10^4)/\{(\Sigma[f_i/(d_{li}^{0.404} \times d_{si}^{0.595})])^2 * SF^2\}$$

where Θ = total porosity

1.99×10^4 = constant incorporating unit weight and viscosity of water and the empirical Kozeny-Carman coefficient (1/cm-sec)

f_i = fraction of particles retained on the smaller sieve of adjacent sieve pairs (dimensionless)

d_{li} = diameter of larger sieve in pair (cm)

d_{si} = diameter of smaller sieve in pair (cm)

SF = grain shape factor (dimensionless)

2. Frac retained = fraction (by weight) retained on screen

3. Estimated shape factors:

Rounded	6.1
Median	6.25
Worn	6.4

4. Estimated porosities:

Maximum	0.40
Median	0.33
Minimum	0.25

Table G-12a

Estimated Hydraulic Conductivity Based On Grain Size Analyses
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Particle Type	Screen Size (microns)	Screen Size (cm)	B-207 (50 feet bgs)		B-208 (56 - 57 feet bgs)	
			Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$
Coarse Gravel	1"	2.5002	0.0000	–	0.0000	–
Fine Gravel	½"	1.2501	0.1085	0.06561	0.0000	0.00000
	3/8"	0.9500	0.0089	0.00838	0.0253	0.02383
	1/4"	0.6351	0.0107	0.01431	0.0173	0.02314
	4,757 (No. 4)	0.4757	0.0053	0.00991	0.0056	0.01047
Coarse Sand	3,364 (No. 6)	0.3364	0.0101	0.02607	0.0092	0.02375
	2,000 (No. 10)	0.2000	0.0126	0.05098	0.0149	0.06029
Medium Sand	1414 (No. 14)	0.1414	0.0082	0.05031	0.0103	0.06320
	1000 (No. 18)	0.1000	0.0099	0.08587	0.0161	0.13965
	707 (No. 25)	0.0707	0.0178	0.21828	0.0290	0.35563
	500 (No. 35)	0.0500	0.0315	0.54608	0.0564	0.97775
	420 (No. 40)	0.0420	0.0378	0.83613	0.0491	1.08609
Fine Sand	354 (No. 45)	0.0354	0.0311	0.81717	0.0439	1.15349
	250 (No. 60)	0.0250	0.1098	3.80216	0.1267	4.38738
	177 (No. 80)	0.0177	0.0971	4.75234	0.0691	3.38194
	125 (No. 120)	0.0125	0.1020	7.05923	0.1096	7.58522
	74 (No. 200)	0.0074	0.0797	8.67189	0.0883	9.60763
Silt and Clay	53 (No. 270)	0.0053	0.0997	16.35240	0.0992	16.27039
	37 (No. 400)	0.0037	0.0799	18.57203	0.0894	20.78022
	25	0.0025	0.0464	15.74672	0.0470	15.93903
	15.6	0.00156	0.0464	24.42537	0.0470	24.72366
	5	0.0005	0.0464	58.15787	0.0470	58.86813
		Sum	1.00	160.269	1.00	165.461
		Estimated Maximum k (cm/sec)		3.70E-03		3.47E-03
		Estimated Median k (cm/sec)		1.59E-03		1.49E-03
		Estimated Minimum k (cm/sec)		5.25E-04		4.93E-04
		% Gravel	13.3		4.8	
		% Sand	54.8		62.3	
		% Silt and Clay	31.9		33.0	

Notes:

1. Kozeny-Carman Equation:

$$k = [\Theta^3/(1-\Theta)^2]*(1.99\times10^4)/\{(\Sigma[f_i/(d_{li}^{0.404} \times d_{si}^{0.595})])^2*SF^2\}$$

where Θ = total porosity

1.99×10^4 = constant incorporating unit weight and viscosity of water and the empirical Kozeny-Carman coefficient (1/cm-sec)

f_i = fraction of particles retained on the smaller sieve of adjacent sieve pairs (dimensionless)

d_{li} = diameter of larger sieve in pair (cm)

d_{si} = diameter of smaller sieve in pair (cm)

SF = grain shape factor (dimensionless)

2. Frac retained = fraction (by weight) retained on screen

3. Estimated shape factors:

Rounded	6.1
Median	6.25
Worn	6.4

4. Estimated porosities:

Maximum	0.40
Median	0.33
Minimum	0.25

Table G-12a

Estimated Hydraulic Conductivity Based On Grain Size Analyses
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Particle Type	Screen Size (microns)	Screen Size (cm)	B-209 (57 feet bgs)		B-210 (59 - 60 feet bgs)	
			Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$
Coarse Gravel	1"	2.5002	0.0000	–	0.0000	–
Fine Gravel	½"	1.2501	0.0000	0.00000	0.0378	0.02286
	3/8"	0.9500	0.0216	0.02035	0.0172	0.01620
	1/4"	0.6351	0.0132	0.01766	0.0108	0.01445
	4,757 (No. 4)	0.4757	0.0057	0.01065	0.0036	0.00673
Coarse Sand	3,364 (No. 6)	0.3364	0.0056	0.01446	0.0016	0.00413
	2,000 (No. 10)	0.2000	0.0154	0.06231	0.0047	0.01902
Medium Sand	1414 (No. 14)	0.1414	0.0112	0.06872	0.0024	0.01473
	1000 (No. 18)	0.1000	0.0155	0.13445	0.0050	0.04337
	707 (No. 25)	0.0707	0.0265	0.32497	0.0090	0.11037
	500 (No. 35)	0.0500	0.0392	0.67957	0.0246	0.42646
	420 (No. 40)	0.0420	0.0436	0.96443	0.0293	0.64811
Fine Sand	354 (No. 45)	0.0354	0.0358	0.94066	0.0248	0.65163
	250 (No. 60)	0.0250	0.1037	3.59093	0.1053	3.64634
	177 (No. 80)	0.0177	0.0893	4.37059	0.0801	3.92031
	125 (No. 120)	0.0125	0.0910	6.29794	0.1150	7.95894
	74 (No. 200)	0.0074	0.0807	8.78070	0.0864	9.40090
Silt and Clay	53 (No. 270)	0.0053	0.1255	20.58401	0.1236	20.27238
	37 (No. 400)	0.0037	0.0944	21.94242	0.0991	23.03489
	25	0.0025	0.0607	20.58839	0.0732	24.84181
	15.6	0.00156	0.0607	31.93546	0.0732	38.53312
	5	0.0005	0.0607	76.03974	0.0732	91.74905
		Sum	1.00	197.368	1.00	225.336
		Estimated Maximum k (cm/sec)		2.44E-03		1.87E-03
		Estimated Median k (cm/sec)		1.05E-03		8.03E-04
		Estimated Minimum k (cm/sec)		3.46E-04		2.66E-04
		% Gravel	4.1		6.9	
		% Sand	55.8		48.8	
		% Silt and Clay	40.2		44.2	

Notes:

1. Kozeny-Carman Equation:

$$k = [\Theta^3/(1-\Theta)^2]*(1.99 \times 10^4)/\{(\Sigma[f_i/(d_{li}^{0.404} \times d_{si}^{0.595})])^2 * SF^2\}$$

where Θ = total porosity

1.99×10^4 = constant incorporating unit weight and viscosity of water and the empirical Kozeny-Carman coefficient (1/cm-sec)

f_i = fraction of particles retained on the smaller sieve of adjacent sieve pairs (dimensionless)

d_{li} = diameter of larger sieve in pair (cm)

d_{si} = diameter of smaller sieve in pair (cm)

SF = grain shape factor (dimensionless)

2. Frac retained = fraction (by weight) retained on screen

3. Estimated shape factors:

Rounded	6.1
Median	6.25
Worn	6.4

4. Estimated porosities:

Maximum	0.40
Median	0.33
Minimum	0.25

Table G-12a

Estimated Hydraulic Conductivity Based On Grain Size Analyses
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Particle Type	Screen Size (microns)	Screen Size (cm)	B-211 (83 feet bgs)		B-213 (99 feet bgs)	
			Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$
Coarse Gravel	1"	2.5002	0.0000	–	0.0000	–
Fine Gravel	½"	1.2501	0.0161	0.00974	0.0193	0.01167
	3/8"	0.9500	0.0100	0.00942	0.0000	0.00000
	1/4"	0.6351	0.0067	0.00896	0.0000	0.00000
	4,757 (No. 4)	0.4757	0.0209	0.03906	0.0117	0.02187
Coarse Sand	3,364 (No. 6)	0.3364	0.0110	0.02840	0.0067	0.01730
	2,000 (No. 10)	0.2000	0.0166	0.06717	0.0140	0.05665
Medium Sand	1414 (No. 14)	0.1414	0.0290	0.17794	0.0135	0.08283
	1000 (No. 18)	0.1000	0.0855	0.74163	0.0335	0.29058
	707 (No. 25)	0.0707	0.2184	2.67823	0.0921	1.12942
	500 (No. 35)	0.0500	0.2392	4.14676	0.1702	2.95058
	420 (No. 40)	0.0420	0.0654	1.44664	0.1217	2.69199
Fine Sand	354 (No. 45)	0.0354	0.1055	2.77206	0.0884	2.32275
	250 (No. 60)	0.0250	0.0733	2.53824	0.1524	5.27732
	177 (No. 80)	0.0177	0.0133	0.65094	0.0185	0.90544
	125 (No. 120)	0.0125	0.0350	2.42229	0.0842	5.82733
	74 (No. 200)	0.0074	0.0109	1.18599	0.0233	2.53520
Silt and Clay	53 (No. 270)	0.0053	0.0198	3.24752	0.0448	7.34792
	37 (No. 400)	0.0037	0.0069	1.60384	0.0251	5.83427
	25	0.0025	0.0055	1.85522	0.0269	9.12903
	15.6	0.00156	0.0055	2.87770	0.0269	14.16040
	5	0.0005	0.0055	6.85193	0.0269	33.71652
		Sum	1.00	35.360	1.00	94.309
		Estimated Maximum k (cm/sec)		7.60E-02		1.07E-02
		Estimated Median k (cm/sec)		3.26E-02		4.59E-03
		Estimated Minimum k (cm/sec)		1.08E-02		1.52E-03
		% Gravel	5.4		3.1	
		% Sand	90.3		81.9	
		% Silt and Clay	4.3		15.1	

Notes:

1. Kozeny-Carman Equation:

$$k = [\Theta^3/(1-\Theta)^2]*(1.99 \times 10^4)/\{(\Sigma[f_i/(d_{li}^{0.404} \times d_{si}^{0.595})])^2 * SF^2\}$$

where Θ = total porosity

1.99×10^4 = constant incorporating unit weight and viscosity of water and the empirical Kozeny-Carman coefficient (1/cm-sec)

f_i = fraction of particles retained on the smaller sieve of adjacent sieve pairs (dimensionless)

d_{li} = diameter of larger sieve in pair (cm)

d_{si} = diameter of smaller sieve in pair (cm)

SF = grain shape factor (dimensionless)

2. Frac retained = fraction (by weight) retained on screen

3. Estimated shape factors:

Rounded	6.1
Median	6.25
Worn	6.4

4. Estimated porosities:

Maximum	0.40
Median	0.33
Minimum	0.25

Table G-12a

Estimated Hydraulic Conductivity Based On Grain Size Analyses
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Particle Type	Screen Size (microns)	Screen Size (cm)	B-216 (77 feet bgs)		B-217 (97 - 99 feet bgs)	
			Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$
Coarse Gravel	1"	2.5002	0.0000	–	0.0000	–
Fine Gravel	½"	1.2501	0.0000	0.00000	0.2494	0.15081
	3/8"	0.9500	0.0066	0.00622	0.0000	0.00000
	1/4"	0.6351	0.0131	0.01752	0.0517	0.06915
	4,757 (No. 4)	0.4757	0.0091	0.01701	0.0195	0.03645
Coarse Sand	3,364 (No. 6)	0.3364	0.0025	0.00645	0.0124	0.03201
	2,000 (No. 10)	0.2000	0.0109	0.04410	0.0253	0.10237
Medium Sand	1414 (No. 14)	0.1414	0.0099	0.06074	0.0245	0.15033
	1000 (No. 18)	0.1000	0.0139	0.12057	0.0441	0.38252
	707 (No. 25)	0.0707	0.0251	0.30780	0.0742	0.90991
	500 (No. 35)	0.0500	0.0375	0.65010	0.1594	2.76335
	420 (No. 40)	0.0420	0.0350	0.77420	0.0823	1.82047
Fine Sand	354 (No. 45)	0.0354	0.0309	0.81191	0.0436	1.14561
	250 (No. 60)	0.0250	0.1635	5.66169	0.0681	2.35817
	177 (No. 80)	0.0177	0.1164	5.69693	0.0153	0.74882
	125 (No. 120)	0.0125	0.1125	7.78592	0.0394	2.72680
	74 (No. 200)	0.0074	0.0922	10.03197	0.0216	2.35022
Silt and Clay	53 (No. 270)	0.0053	0.0948	15.54872	0.0212	3.47714
	37 (No. 400)	0.0037	0.0976	22.68623	0.0141	3.27742
	25	0.0025	0.0429	14.54762	0.0113	3.82356
	15.6	0.00156	0.0429	22.56539	0.0113	5.93087
	5	0.0005	0.0429	53.72918	0.0113	14.12167
		Sum	1.00	161.070	1.00	46.378
		Estimated Maximum k (cm/sec)		3.66E-03		4.42E-02
		Estimated Median k (cm/sec)		1.57E-03		1.90E-02
		Estimated Minimum k (cm/sec)		5.20E-04		6.27E-03
		% Gravel	2.9		32.1	
		% Sand	65.0		61.0	
		% Silt and Clay	32.1		6.9	

Notes:

1. Kozeny-Carman Equation:

$$k = [\Theta^3/(1-\Theta)^2]*(1.99 \times 10^4)/\{(\Sigma[f_i/(d_{li}^{0.404} \times d_{si}^{0.595})])^2 * SF^2\}$$

where Θ = total porosity

1.99×10^4 = constant incorporating unit weight and viscosity of water and the empirical Kozeny-Carman coefficient (1/cm-sec)

f_i = fraction of particles retained on the smaller sieve of adjacent sieve pairs (dimensionless)

d_{li} = diameter of larger sieve in pair (cm)

d_{si} = diameter of smaller sieve in pair (cm)

SF = grain shape factor (dimensionless)

2. Frac retained = fraction (by weight) retained on screen

3. Estimated shape factors:

Rounded	6.1
Median	6.25
Worn	6.4

4. Estimated porosities:

Maximum	0.40
Median	0.33
Minimum	0.25

Table G-12a

Estimated Hydraulic Conductivity Based On Grain Size Analyses
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Particle Type	Screen Size (microns)	Screen Size (cm)	B-219 (73 feet bgs)		MW-132 (53 feet bgs)	
			Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$
Coarse Gravel	1"	2.5002	0.0000	–	0.0000	–
Fine Gravel	½"	1.2501	0.0000	0.00000	0.0298	0.01802
	3/8"	0.9500	0.0214	0.02016	0.0000	0.00000
	1/4"	0.6351	0.0085	0.01137	0.0037	0.00495
	4,757 (No. 4)	0.4757	0.0115	0.02149	0.0103	0.01925
Coarse Sand	3,364 (No. 6)	0.3364	0.0142	0.03666	0.0116	0.02995
	2,000 (No. 10)	0.2000	0.0254	0.10277	0.0309	0.12502
Medium Sand	1414 (No. 14)	0.1414	0.0156	0.09572	0.0186	0.11412
	1000 (No. 18)	0.1000	0.0268	0.23246	0.0390	0.33829
	707 (No. 25)	0.0707	0.0539	0.66097	0.0657	0.80568
	500 (No. 35)	0.0500	0.0756	1.31060	0.0863	1.49609
	420 (No. 40)	0.0420	0.0836	1.84922	0.0352	0.77862
Fine Sand	354 (No. 45)	0.0354	0.0559	1.46880	0.0693	1.82089
	250 (No. 60)	0.0250	0.1211	4.19346	0.1047	3.62556
	177 (No. 80)	0.0177	0.0550	2.69185	0.0485	2.37372
	125 (No. 120)	0.0125	0.1186	8.20809	0.0986	6.82393
	74 (No. 200)	0.0074	0.0799	8.69365	0.0897	9.75996
Silt and Clay	53 (No. 270)	0.0053	0.0721	11.82555	0.0726	11.90756
	37 (No. 400)	0.0037	0.0609	14.15565	0.0519	12.06368
	25	0.0025	0.0333	11.28968	0.0445	15.11323
	15.6	0.00156	0.0333	17.51186	0.0445	23.44274
	5	0.0005	0.0333	41.69652	0.0445	55.81819
		Sum	1.00	126.077	1.00	146.479
		Estimated Maximum k (cm/sec)		5.98E-03		4.43E-03
		Estimated Median k (cm/sec)		2.57E-03		1.90E-03
		Estimated Minimum k (cm/sec)		8.49E-04		6.29E-04
		% Gravel	4.1		4.4	
		% Sand	72.6		69.8	
		% Silt and Clay	23.3		25.8	

Notes:

1. Kozeny-Carman Equation:

$$k = [\Theta^3/(1-\Theta)^2]*(1.99\times10^4)/\{(\Sigma[f_i/(d_{li}^{0.404} \times d_{si}^{0.595})])^2*SF^2\}$$

where Θ = total porosity

1.99×10^4 = constant incorporating unit weight and viscosity of water and the empirical Kozeny-Carman coefficient (1/cm-sec)

f_i = fraction of particles retained on the smaller sieve of adjacent sieve pairs (dimensionless)

d_{li} = diameter of larger sieve in pair (cm)

d_{si} = diameter of smaller sieve in pair (cm)

SF = grain shape factor (dimensionless)

2. Frac retained = fraction (by weight) retained on screen

3. Estimated shape factors:

Rounded	6.1
Median	6.25
Worn	6.4

4. Estimated porosities:

Maximum	0.40
Median	0.33
Minimum	0.25

Table G-12a

Estimated Hydraulic Conductivity Based On Grain Size Analyses
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Particle Type	Screen Size (microns)	Screen Size (cm)	MW-133 (106 feet bgs)		MW-135 (50 feet bgs)	
			Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$
Coarse Gravel	1"	2.5002	0.0906	–	0.0000	–
Fine Gravel	½"	1.2501	0.2316	0.14005	0.0000	0.00000
	3/8"	0.9500	0.0568	0.05351	0.0192	0.01809
	1/4"	0.6351	0.0844	0.11289	0.0223	0.02983
	4,757 (No. 4)	0.4757	0.0595	0.11121	0.0182	0.03402
Coarse Sand	3,364 (No. 6)	0.3364	0.0660	0.17038	0.0198	0.05111
	2,000 (No. 10)	0.2000	0.0800	0.32369	0.0462	0.18693
Medium Sand	1414 (No. 14)	0.1414	0.0393	0.24113	0.0361	0.22150
	1000 (No. 18)	0.1000	0.0326	0.28277	0.0574	0.49789
	707 (No. 25)	0.0707	0.0310	0.38015	0.0768	0.94180
	500 (No. 35)	0.0500	0.0252	0.43687	0.0898	1.55677
	420 (No. 40)	0.0420	0.0076	0.16811	0.0632	1.39798
Fine Sand	354 (No. 45)	0.0354	0.0206	0.54127	0.0520	1.36632
	250 (No. 60)	0.0250	0.0371	1.28470	0.1007	3.48705
	177 (No. 80)	0.0177	0.0108	0.52858	0.0478	2.33946
	125 (No. 120)	0.0125	0.0364	2.51918	0.0871	6.02803
	74 (No. 200)	0.0074	0.0247	2.68752	0.0734	7.98641
Silt and Clay	53 (No. 270)	0.0053	0.0176	2.88668	0.0587	9.62774
	37 (No. 400)	0.0037	0.0128	2.97524	0.0390	9.06519
	25	0.0025	0.0118	4.01587	0.0307	10.42994
	15.6	0.00156	0.0118	6.22917	0.0307	16.17830
	5	0.0005	0.0118	14.83193	0.0307	38.52123
		Sum	1.00	40.921	1.00	109.966
		Estimated Maximum k (cm/sec)		5.68E-02		7.86E-03
		Estimated Median k (cm/sec)		2.44E-02		3.37E-03
		Estimated Minimum k (cm/sec)		8.06E-03		1.12E-03
		% Gravel	52.3		6.0	
		% Sand	41.1		75.0	
		% Silt and Clay	6.6		19.0	

Notes:

1. Kozeny-Carman Equation:

$$k = [\Theta^3/(1-\Theta)^2]*(1.99 \times 10^4)/\{(\Sigma[f_i/(d_{li}^{0.404} \times d_{si}^{0.595})])^2 * SF^2\}$$

where Θ = total porosity

1.99×10^4 = constant incorporating unit weight and viscosity of water and the empirical Kozeny-Carman coefficient (1/cm-sec)

f_i = fraction of particles retained on the smaller sieve of adjacent sieve pairs (dimensionless)

d_{li} = diameter of larger sieve in pair (cm)

d_{si} = diameter of smaller sieve in pair (cm)

SF = grain shape factor (dimensionless)

2. Frac retained = fraction (by weight) retained on screen

3. Estimated shape factors:

Rounded	6.1
Median	6.25
Worn	6.4

4. Estimated porosities:

Maximum	0.40
Median	0.33
Minimum	0.25

Table G-12a

Estimated Hydraulic Conductivity Based On Grain Size Analyses
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Particle Type	Screen Size (microns)	Screen Size (cm)	MW-137 (115 feet bgs)		MW-138 (65 feet bgs)	
			Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$
Coarse Gravel	1"	2.5002	0.0000	–	0.0000	–
Fine Gravel	½"	1.2501	0.0554	0.03350	0.0467	0.02824
	3/8"	0.9500	0.0090	0.00848	0.0113	0.01065
	1/4"	0.6351	0.0337	0.04508	0.0178	0.02381
	4,757 (No. 4)	0.4757	0.0137	0.02561	0.0204	0.03813
Coarse Sand	3,364 (No. 6)	0.3364	0.0107	0.02762	0.0243	0.06273
	2,000 (No. 10)	0.2000	0.0215	0.08699	0.0307	0.12422
Medium Sand	1414 (No. 14)	0.1414	0.0187	0.11474	0.0247	0.15155
	1000 (No. 18)	0.1000	0.0258	0.22379	0.0291	0.25241
	707 (No. 25)	0.0707	0.0536	0.65729	0.0444	0.54448
	500 (No. 35)	0.0500	0.1169	2.02657	0.0696	1.20658
	420 (No. 40)	0.0420	0.1216	2.68978	0.0466	1.03079
Fine Sand	354 (No. 45)	0.0354	0.1293	3.39742	0.0541	1.42150
	250 (No. 60)	0.0250	0.2037	7.05374	0.1479	5.12149
	177 (No. 80)	0.0177	0.0291	1.42423	0.1077	5.27113
	125 (No. 120)	0.0125	0.0509	3.52270	0.0931	6.44328
	74 (No. 200)	0.0074	0.0338	3.67767	0.0629	6.84394
Silt and Clay	53 (No. 270)	0.0053	0.0245	4.01839	0.0696	11.41551
	37 (No. 400)	0.0037	0.0140	3.25417	0.0448	10.41335
	25	0.0025	0.0114	3.86881	0.0181	6.14258
	15.6	0.00156	0.0114	6.00106	0.0181	9.52800
	5	0.0005	0.0114	14.28879	0.0181	22.68658
		Sum	1.00	56.446	1.00	88.761
		Estimated Maximum k (cm/sec)		2.98E-02		1.21E-02
		Estimated Median k (cm/sec)		1.28E-02		5.18E-03
		Estimated Minimum k (cm/sec)		4.24E-03		1.71E-03
		% Gravel	11.2		9.6	
		% Sand	81.6		73.5	
		% Silt and Clay	7.3		16.9	

Notes:

1. Kozeny-Carman Equation:

$$k = [\Theta^3/(1-\Theta)^2]*(1.99\times10^4)/\{(\Sigma[f_i/(d_{li}^{0.404} \times d_{si}^{0.595})])^2*SF^2\}$$

where Θ = total porosity

1.99×10^4 = constant incorporating unit weight and viscosity of water and the empirical Kozeny-Carman coefficient (1/cm-sec)

f_i = fraction of particles retained on the smaller sieve of adjacent sieve pairs (dimensionless)

d_{li} = diameter of larger sieve in pair (cm)

d_{si} = diameter of smaller sieve in pair (cm)

SF = grain shape factor (dimensionless)

2. Frac retained = fraction (by weight) retained on screen

3. Estimated shape factors:

Rounded	6.1
Median	6.25
Worn	6.4

4. Estimated porosities:

Maximum	0.40
Median	0.33
Minimum	0.25

Table G-12a

Estimated Hydraulic Conductivity Based On Grain Size Analyses
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Particle Type	Screen Size (microns)	Screen Size (cm)	MW-138 (115 feet bgs)		MW-139 (80 feet bgs)	
			Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$
Coarse Gravel	1"	2.5002	0.0000	–	0.0000	–
Fine Gravel	½"	1.2501	0.1147	0.06936	0.0000	0.00000
	3/8"	0.9500	0.0404	0.03806	0.0000	0.00000
	1/4"	0.6351	0.0177	0.02367	0.0000	0.00000
	4,757 (No. 4)	0.4757	0.0245	0.04579	0.0032	0.00598
Coarse Sand	3,364 (No. 6)	0.3364	0.0161	0.04156	0.0019	0.00490
	2,000 (No. 10)	0.2000	0.0256	0.10358	0.0040	0.01618
Medium Sand	1414 (No. 14)	0.1414	0.0238	0.14603	0.0031	0.01902
	1000 (No. 18)	0.1000	0.0429	0.37211	0.0085	0.07373
	707 (No. 25)	0.0707	0.0787	0.96510	0.0403	0.49420
	500 (No. 35)	0.0500	0.1212	2.10112	0.1556	2.69747
	420 (No. 40)	0.0420	0.0895	1.97973	0.1689	3.73605
Fine Sand	354 (No. 45)	0.0354	0.0909	2.38844	0.1299	3.41318
	250 (No. 60)	0.0250	0.1487	5.14920	0.1631	5.64784
	177 (No. 80)	0.0177	0.0264	1.29209	0.0491	2.40309
	125 (No. 120)	0.0125	0.0356	2.46381	0.0594	4.11097
	74 (No. 200)	0.0074	0.0314	3.41653	0.0434	4.72221
Silt and Clay	53 (No. 270)	0.0053	0.0264	4.33002	0.0484	7.93837
	37 (No. 400)	0.0037	0.0118	2.74280	0.0377	8.76302
	25	0.0025	0.0113	3.83487	0.0279	9.45708
	15.6	0.00156	0.0113	5.94842	0.0279	14.66926
	5	0.0005	0.0113	14.16345	0.0279	34.92815
		Sum	1.00	51.616	1.00	103.101
		Estimated Maximum k (cm/sec)		3.57E-02		8.94E-03
		Estimated Median k (cm/sec)		1.53E-02		3.84E-03
		Estimated Minimum k (cm/sec)		5.07E-03		1.27E-03
		% Gravel	19.7		0.3	
		% Sand	73.1		82.7	
		% Silt and Clay	7.2		17.0	

Notes:

1. Kozeny-Carman Equation:

$$k = [\Theta^3/(1-\Theta)^2]*(1.99 \times 10^4)/\{(\Sigma[f_i/(d_{li}^{0.404} \times d_{si}^{0.595})])^2 * SF^2\}$$

where Θ = total porosity

1.99×10^4 = constant incorporating unit weight and viscosity of water and the empirical Kozeny-Carman coefficient (1/cm-sec)

f_i = fraction of particles retained on the smaller sieve of adjacent sieve pairs (dimensionless)

d_{li} = diameter of larger sieve in pair (cm)

d_{si} = diameter of smaller sieve in pair (cm)

SF = grain shape factor (dimensionless)

2. Frac retained = fraction (by weight) retained on screen

3. Estimated shape factors:

Rounded	6.1
Median	6.25
Worn	6.4

4. Estimated porosities:

Maximum	0.40
Median	0.33
Minimum	0.25

Table G-12a

Estimated Hydraulic Conductivity Based On Grain Size Analyses
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Particle Type	Screen Size (microns)	Screen Size (cm)	MW-140 (80 - 80.5 feet bgs)		MW-140 (100 feet bgs)	
			Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$
Coarse Gravel	1"	2.5002	0.0000	–	0.0000	–
Fine Gravel	½"	1.2501	0.0000	0.00000	0.1104	0.06676
	3/8"	0.9500	0.0345	0.03250	0.0388	0.03655
	1/4"	0.6351	0.0238	0.03183	0.0269	0.03598
	4,757 (No. 4)	0.4757	0.0091	0.01701	0.0085	0.01589
Coarse Sand	3,364 (No. 6)	0.3364	0.0112	0.02891	0.0077	0.01988
	2,000 (No. 10)	0.2000	0.0132	0.05341	0.0156	0.06312
Medium Sand	1414 (No. 14)	0.1414	0.0097	0.05952	0.0219	0.13437
	1000 (No. 18)	0.1000	0.0133	0.11536	0.0542	0.47013
	707 (No. 25)	0.0707	0.0184	0.22564	0.1483	1.81860
	500 (No. 35)	0.0500	0.0397	0.68824	0.1829	3.17074
	420 (No. 40)	0.0420	0.0315	0.69678	0.0762	1.68553
Fine Sand	354 (No. 45)	0.0354	0.0304	0.79877	0.0572	1.50296
	250 (No. 60)	0.0250	0.1023	3.54245	0.1413	4.89295
	177 (No. 80)	0.0177	0.0736	3.60218	0.0286	1.39976
	125 (No. 120)	0.0125	0.0994	6.87929	0.0268	1.85478
	74 (No. 200)	0.0074	0.1024	11.14180	0.0261	2.83985
Silt and Clay	53 (No. 270)	0.0053	0.1257	20.61681	0.0111	1.82058
	37 (No. 400)	0.0037	0.0726	16.87521	0.0051	1.18545
	25	0.0025	0.0630	21.39156	0.0042	1.41404
	15.6	0.00156	0.0630	33.18130	0.0042	2.19337
	5	0.0005	0.0630	79.00613	0.0042	5.22251
		Sum	1.00	198.985	1.00	31.844
		Estimated Maximum k (cm/sec)		2.40E-03		9.38E-02
		Estimated Median k (cm/sec)		1.03E-03		4.02E-02
		Estimated Minimum k (cm/sec)		3.41E-04		1.33E-02
		% Gravel	6.7		18.5	
		% Sand	54.5		78.7	
		% Silt and Clay	38.7		2.9	

Notes:

1. Kozeny-Carman Equation:

$$k = [\Theta^3/(1-\Theta)^2]*(1.99 \times 10^4)/\{(\Sigma[f_i/(d_{li}^{0.404} \times d_{si}^{0.595})])^2 * SF^2\}$$

where Θ = total porosity

1.99×10^4 = constant incorporating unit weight and viscosity of water and the empirical Kozeny-Carman coefficient (1/cm-sec)

f_i = fraction of particles retained on the smaller sieve of adjacent sieve pairs (dimensionless)

d_{li} = diameter of larger sieve in pair (cm)

d_{si} = diameter of smaller sieve in pair (cm)

SF = grain shape factor (dimensionless)

2. Frac retained = fraction (by weight) retained on screen

3. Estimated shape factors:

Rounded	6.1
Median	6.25
Worn	6.4

4. Estimated porosities:

Maximum	0.40
Median	0.33
Minimum	0.25

Table G-12b

Estimated Hydraulic Conductivity Based On Grain Size Analyses
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Particle Type	Screen Size (microns)	Screen Size (cm)	B-212 (54 feet bgs)		MW-136 (77 feet bgs)		MW-137 (50 feet bgs)	
			Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$
Gravel	1/4"	0.6351	0.000	–	0.000	–	0.000	–
	4,757 (No. 4)	0.4757	0.000	0.00000	0.000	0.00000	0.000	0.00000
Course Sand	3,364 (No. 6)	0.3364	0.000	0.00000	0.000	0.00000	0.000	0.00000
	2,000 (No. 10)	0.2000	0.000	0.00000	0.000	0.00000	0.000	0.00000
Medium Sand	1,189 (No. 16)	0.1189	0.000	0.00000	0.000	0.00000	0.000	0.00000
	841 (No. 20)	0.0841	0.000	0.00000	0.000	0.00000	0.000	0.00000
	707 (No. 25)	0.0707	0.000	0.00000	0.000	0.00000	0.000	0.00000
	595 (No. 30)	0.0595	0.000	0.00000	0.000	0.00000	0.000	0.00000
	500 (No. 35)	0.0500	0.000	0.00000	0.000	0.00000	0.000	0.00000
	420 (No. 40)	0.0420	0.000	0.00000	0.000	0.00000	0.000	0.00000
Fine Sand	354 (No. 45)	0.0354	0.000	0.00000	0.000	0.00000	0.000	0.00000
	297 (No. 50)	0.0297	0.000	0.00000	0.000	0.00000	0.000	0.00000
	250 (No. 60)	0.0250	0.000	0.00000	0.000	0.00000	0.000	0.00000
	210 (No. 70)	0.0210	0.000	0.00000	0.000	0.00000	0.000	0.00000
	177 (No. 80)	0.0177	0.000	0.00000	0.000	0.00000	0.000	0.00000
	149 (No. 100)	0.0149	0.000	0.00000	0.000	0.00000	0.000	0.00000
	125 (No. 120)	0.0125	0.0007	0.05194	0.0007	0.05194	0.000	0.00000
	105 (No. 140)	0.0105	0.0025	0.22089	0.0026	0.22973	0.000	0.00000
	88 (No. 170)	8.80E-03	0.0050	0.52655	0.0032	0.33699	0.0001	0.01053
	74 (No. 200)	7.40E-03	0.0081	1.01560	0.0021	0.26330	0.0006	0.07523
Silt	63 (No. 230)	6.30E-03	0.0128	1.89423	0.0014	0.20718	0.0018	0.26638
	53 (No. 270)	5.30E-03	0.0197	3.44817	0.0021	0.36757	0.0037	0.64763
	44.2 (No. 325)	4.42E-03	0.0276	5.77132	0.0042	0.87824	0.0066	1.38010
	37.2 (No. 400)	3.72E-03	0.0367	9.15045	0.0060	1.49599	0.0124	3.09170
	31.3 (No. 450)	3.13E-03	0.0458	13.56804	0.0069	2.04409	0.0206	6.10266
	25.0 (No. 500)	2.50E-03	0.0539	19.57107	0.0084	3.05004	0.0295	10.71144
	20.1 (No. 635)	2.01E-03	0.0766	34.67842	0.0157	7.10772	0.0485	21.95697
	15.6	1.56E-03	0.0817	46.97012	0.0244	14.02780	0.0585	33.63222
	11.0	1.10E-03	0.0931	72.99594	0.0358	28.06933	0.0750	58.80446
	7.81	7.81E-04	0.1275	141.14327	0.0735	81.36494	0.1235	136.71525
	5.00	5.00E-04	0.1094	181.34231	0.1069	177.19829	0.1316	218.14121

Table G-12b

Estimated Hydraulic Conductivity Based On Grain Size Analyses
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Particle Type	Screen Size (microns)	Screen Size (cm)	B-212 (54 feet bgs)		MW-136 (77 feet bgs)		MW-137 (50 feet bgs)	
			Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$
Clay	1.95	1.95E-04	0.1044	362.86579	0.1623	564.11032	0.1517	527.26762
	0.977	0.0000977	0.1104	846.85260	0.3055	2343.41910	0.2019	1548.72772
	0.488	0.0000488	0.0502	769.44312	0.1532	2348.18099	0.0850	1302.84193
	0.375	0.0000375	0.0339	804.50637	0.0850	2017.19886	0.0491	1165.22899
		Sum	1.00	3316.016	1.00	7589.602	1.00	5035.602
		Estimated Maximum k (cm/sec)		8.65E-06		1.65E-06		3.75E-06
		Estimated Median k (cm/sec)		3.71E-06		7.08E-07		1.61E-06
		Estimated Minimum k (cm/sec)		1.23E-06		2.34E-07		5.32E-07
		% Gravel	0.0		0.0		0.0	
		% Sand	1.6		0.9		0.1	
		% Silt	68.5		28.5		51.2	
		% Clay	29.9		70.6		48.8	

Notes:

1. Kozeny-Carman Equation:

$$k = [\Theta^3/(1-\Theta)^2]*(1.99 \times 10^4)/\{(\Sigma[f_i/(d_{li}^{0.404} \times d_{si}^{0.595})])^2 * SF^2\}$$

where Θ = total porosity

1.99×10^4 = constant incorporating unit weight and viscosity of water and the empirical Kozeny-Carmon coefficient (1/cm-sec)

f_i = fraction of particles retained on the smaller sieve of adjacent sieve pairs (dimensionless)

d_{li} = diameter of larger sieve in pair (cm)

d_{si} = diameter of smaller sieve in pair (cm)

SF = grain shape factor (dimensionless)

2. Frac retained = fraction (by weight) retained on screen

3. Estimated shape factors:

Rounded	6.1
Median	6.25
Worn	6.4

4. Estimated porosities:

Maximum	0.40
Median	0.33
Minimum	0.25

Table G-12c

Estimated Hydraulic Conductivity Based On Grain Size Analyses
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Particle Type	Screen Size (microns)	Screen Size (cm)	B-206 (48 feet bgs)	
			Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$
Coarse Gravel	2"	5.08	0.000	–
	1½"	3.81	0.000	0.00000
	1"	2.54	0.000	0.00000
	¾"	1.905	0.000	0.00000
Fine Gravel	½"	1.27	0.000	0.00000
	3/8"	0.9525	0.000	0.00000
	4,750 (No. 4)	0.4750	0.030	0.04765
Coarse Sand	2,000 (No. 10)	0.2000	0.056	0.19710
Medium Sand	850 (No. 20)	0.0850	0.072	0.59802
	425 (No. 40)	0.0425	0.163	2.88942
Fine Sand	250 (No. 60)	0.0250	0.236	7.59047
	150 (No. 100)	0.0150	0.154	8.31723
	75 (No. 200)	0.0075	0.089	8.92458
Silt	32	0.0032	0.065	14.31609
	22	0.0022	0.023	8.93112
	13	0.0013	0.031	19.15255
	9	0.0009	0.015	14.26540
	7	0.0007	0.012	15.37567
Clay	3.2	0.00032	0.015	33.89280
	1.3	0.00013	0.038	201.32917
		Sum	1.00	335.827
		Estimated Maximum k (cm/sec)		8.43E-04
		Estimated Median k (cm/sec)		3.62E-04
		Estimated Minimum k (cm/sec)		1.20E-04
		% Gravel	3.0	
		% Sand	77.0	
		% Silt	14.6	
		% Clay	5.3	

Notes:

1. Kozeny-Carman Equation:

$$k = [\Theta^3/(1-\Theta)^2]*(1.99 \times 10^4)/\{(\Sigma[f_i/(d_{li}^{0.404} \times d_{si}^{0.595})])^2*SF^2\}$$

where

1.99×10^4 = constant incorporating unit weight and viscosity of water and the empirical Kozeny-Carmon coefficient (1/cm-sec)

f_i = fraction of particles retained on the smaller sieve of adjacent sieve pairs (dimensionless)

d_{li} = diameter of larger sieve in pair (cm)

d_{si} = diameter of smaller sieve in pair (cm)

SF = grain shape factor (dimensionless)

2. Frac retained = fraction (by weight) retained on screen

3. Estimated shape factors: Rounded 6.1; Median 6.25; Worn 6.4

4. Estimated porosities: Maximum 0.40; Median 0.33; Minimum 0.25

Table G-12d

Estimated Hydraulic Conductivity Based On Grain Size Analyses
American Linen Suply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Particle Type	Screen Size (microns)	Screen Size (cm)	MW-145 (80 feet bgs)		MW-147 (81 feet bgs)	
			Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$
Coarse Gravel	1"	2.5002	0.0000	–	0.0000	–
Fine Gravel	½"	1.2501	0.0000	0.00000	0.2900	0.17536
	3/8"	0.9500	0.0080	0.00754	0.0880	0.08290
	1/4"	0.6351	0.0260	0.03478	0.0960	0.12840
	4,757 (No. 4)	0.4757	0.0110	0.02056	0.0430	0.08037
Coarse Sand	3,364 (No. 6)	0.3364	0.0120	0.03098	0.0530	0.13682
	2,000 (No. 10)	0.2000	0.0160	0.06474	0.0480	0.19421
Medium Sand	1414 (No. 14)	0.1414	0.0120	0.07363	0.0290	0.17794
	1000 (No. 18)	0.1000	0.0120	0.10409	0.0260	0.22552
	707 (No. 25)	0.0707	0.0180	0.22073	0.0300	0.36789
	500 (No. 35)	0.0500	0.0350	0.60676	0.0430	0.74545
	420 (No. 40)	0.0420	0.0230	0.50876	0.0220	0.48664
Fine Sand	354 (No. 45)	0.0354	0.0330	0.86709	0.0250	0.65689
	250 (No. 60)	0.0250	0.0810	2.80487	0.0420	1.45438
	177 (No. 80)	0.0177	0.0710	3.47493	0.0260	1.27251
	125 (No. 120)	0.0125	0.0480	3.32199	0.0170	1.17654
Silt	5	0.0005	0.1530	82.72802	0.0240	12.97694
Clay	2	0.0002	0.1210	414.27492	0.0200	68.47519
	1	0.0001	0.1740	1302.96614	0.0130	97.34804
	0.5	0.00005	0.0920	1376.89453	0.0300	448.98735
	0.4	0.00004	0.0540	1221.19265	0.0350	791.51376
		Sum	1.00	4410.198	1.00	1426.663
		Estimated Maximum k (cm/sec)		4.89E-06		4.67E-05
		Estimated Median k (cm/sec)		2.10E-06		2.00E-05
		Estimated Minimum k (cm/sec)		6.94E-07		6.63E-06
		% Gravel	4.5		51.7	
		% Sand	36.1		36.1	
		% Silt	15.3		2.4	
		% Clay	44.1		9.8	

Notes:

1. Kozeny-Carman Equation:

$$k = [\Theta^3/(1-\Theta)^2]*(1.99 \times 10^4)/\{(\Sigma[f_i/(d_{li}^{0.404} \times d_{si}^{0.595})])^2 * SF^2\}$$

where Θ = total porosity

1.99×10^4 = constant incorporating unit weight and viscosity of water and the empirical Kozeny-Carmon coefficient (1/cm-sec)

f_i = fraction of particles retained on the smaller sieve of adjacent sieve pairs (dimensionless)

d_{li} = diameter of larger sieve in pair (cm)

d_{si} = diameter of smaller sieve in pair (cm)

SF = grain shape factor (dimensionless)

2. Frac retained = fraction (by weight) retained on screen

3. Estimated shape factors:

Rounded	6.1
Median	6.25
Worn	6.4

4. Estimated porosities:

Maximum	0.40
Median	0.33
Minimum	0.25

Table G-12d

Estimated Hydraulic Conductivity Based On Grain Size Analyses
American Linen Suply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Particle Type	Screen Size (microns)	Screen Size (cm)	MW-148 (60 feet bgs)		MW-153 (80 feet bgs)	
			Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$
Coarse Gravel	1"	2.5002	0.0000	–	0.0000	–
Fine Gravel	½"	1.2501	0.0000	0.00000	0.0170	0.01028
	3/8"	0.9500	0.0000	0.00000	0.0000	0.00000
	1/4"	0.6351	0.0000	0.00000	0.0130	0.01739
	4,757 (No. 4)	0.4757	0.0000	0.00000	0.0140	0.02617
Coarse Sand	3,364 (No. 6)	0.3364	0.0010	0.00258	0.0140	0.03614
	2,000 (No. 10)	0.2000	0.0010	0.00405	0.0220	0.08901
Medium Sand	1414 (No. 14)	0.1414	0.0020	0.01227	0.0390	0.23929
	1000 (No. 18)	0.1000	0.0110	0.09541	0.0250	0.21685
	707 (No. 25)	0.0707	0.0490	0.60089	0.0410	0.50278
	500 (No. 35)	0.0500	0.1560	2.70441	0.0600	1.04016
	420 (No. 40)	0.0420	0.1260	2.78711	0.0350	0.77420
Fine Sand	354 (No. 45)	0.0354	0.1700	4.46683	0.0410	1.07729
	250 (No. 60)	0.0250	0.2840	9.83437	0.0860	2.97801
	177 (No. 80)	0.0177	0.0880	4.30696	0.0670	3.27916
	125 (No. 120)	0.0125	0.0280	1.93783	0.0450	3.11437
Silt	5	0.0005	0.0040	2.16282	0.3720	201.14264
Clay	2	0.0002	0.0170	58.20391	0.0300	102.71279
	1	0.0001	0.0430	321.99738	0.0380	284.55582
	0.5	0.00005	0.0100	149.66245	0.0250	374.15612
	0.4	0.00004	0.0100	226.14679	0.0160	361.83486
		Sum	1.00	784.926	1.00	1337.803
		Estimated Maximum k (cm/sec)		1.54E-04		5.31E-05
		Estimated Median k (cm/sec)		6.62E-05		2.28E-05
		Estimated Minimum k (cm/sec)		2.19E-05		7.54E-06
		% Gravel	0.0		4.4	
		% Sand	91.6		47.5	
		% Silt	0.4		37.2	
		% Clay	8.0		10.9	

Notes:

1. Kozeny-Carman Equation:

$$k = [\Theta^3/(1-\Theta)^2]*(1.99 \times 10^4)/\{(\Sigma[f_i/(d_{li}^{0.404} \times d_{si}^{0.595})])^2 * SF^2\}$$

where Θ = total porosity

1.99×10^4 = constant incorporating unit weight and viscosity of water and the empirical Kozeny-Carmon coefficient (1/cm-sec)

f_i = fraction of particles retained on the smaller sieve of adjacent sieve pairs (dimensionless)

d_{li} = diameter of larger sieve in pair (cm)

d_{si} = diameter of smaller sieve in pair (cm)

SF = grain shape factor (dimensionless)

2. Frac retained = fraction (by weight) retained on screen

3. Estimated shape factors:

Rounded	6.1
Median	6.25
Worn	6.4

4. Estimated porosities:

Maximum	0.40
Median	0.33
Minimum	0.25

Table G-12d

Estimated Hydraulic Conductivity Based On Grain Size Analyses
American Linen Suply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Particle Type	Screen Size (microns)	Screen Size (cm)	MW-153 (90 to 100 feet bgs)		MW-158A (100 feet bgs)	
			Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$
Coarse Gravel	1"	2.5002	0.0000	–	0.0000	–
Fine Gravel	½"	1.2501	0.0000	0.00000	0.0000	0.00000
	3/8"	0.9500	0.0010	0.00094	0.0400	0.03768
	1/4"	0.6351	0.0000	0.00000	0.1190	0.15917
	4,757 (No. 4)	0.4757	0.0000	0.00000	0.1070	0.20000
Coarse Sand	3,364 (No. 6)	0.3364	0.0000	0.00000	0.1500	0.38723
	2,000 (No. 10)	0.2000	0.0020	0.00809	0.1660	0.67165
Medium Sand	1414 (No. 14)	0.1414	0.0060	0.03681	0.1320	0.80992
	1000 (No. 18)	0.1000	0.0160	0.13878	0.0730	0.63320
	707 (No. 25)	0.0707	0.0650	0.79709	0.0580	0.71125
	500 (No. 35)	0.0500	0.2310	4.00460	0.0270	0.46807
	420 (No. 40)	0.0420	0.1640	3.62766	0.0170	0.37604
Fine Sand	354 (No. 45)	0.0354	0.1590	4.17780	0.0090	0.23648
	250 (No. 60)	0.0250	0.1850	6.40619	0.0050	0.17314
	177 (No. 80)	0.0177	0.0680	3.32811	0.0040	0.19577
	125 (No. 120)	0.0125	0.0290	2.00704	0.0030	0.20762
Silt	5	0.0005	0.0240	12.97694	0.0490	26.49459
Clay	2	0.0002	0.0140	47.93264	0.0110	37.66136
	1	0.0001	0.0180	134.78960	0.0170	127.30129
	0.5	0.00005	0.0100	149.66245	0.0080	119.72996
	0.4	0.00004	0.0070	158.30275	0.0050	113.07339
		Sum	1.00	528.198	1.00	429.528
		Estimated Maximum k (cm/sec)		3.41E-04		5.15E-04
		Estimated Median k (cm/sec)		1.46E-04		2.21E-04
		Estimated Minimum k (cm/sec)		4.84E-05		7.31E-05
		% Gravel	0.1		26.6	
		% Sand	92.5		64.4	
		% Silt	2.4		4.9	
		% Clay	4.9		4.1	

Notes:

1. Kozeny-Carman Equation:

$$k = [\Theta^3/(1-\Theta)^2]*(1.99 \times 10^4)/\{(\Sigma[f_i/(d_{li}^{0.404} \times d_{si}^{0.595})])^2 * SF^2\}$$

where Θ = total porosity

1.99×10^4 = constant incorporating unit weight and viscosity of water and the empirical Kozeny-Carmon coefficient (1/cm-sec)

f_i = fraction of particles retained on the smaller sieve of adjacent sieve pairs (dimensionless)

d_{li} = diameter of larger sieve in pair (cm)

d_{si} = diameter of smaller sieve in pair (cm)

SF = grain shape factor (dimensionless)

2. Frac retained = fraction (by weight) retained on screen

3. Estimated shape factors:

Rounded	6.1
Median	6.25
Worn	6.4

4. Estimated porosities:

Maximum	0.40
Median	0.33
Minimum	0.25

Table G-12d

Estimated Hydraulic Conductivity Based On Grain Size Analyses
American Linen Suply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Particle Type	Screen Size (microns)	Screen Size (cm)	MW-159 (25 feet bgs)		MW-160 (100 feet bgs)	
			Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$
Coarse Gravel	1"	2.5002	0.0000	–	0.0000	–
Fine Gravel	½"	1.2501	0.0000	0.00000	0.0000	0.00000
	3/8"	0.9500	0.0000	0.00000	0.0000	0.00000
	1/4"	0.6351	0.0000	0.00000	0.0000	0.00000
	4,757 (No. 4)	0.4757	0.0000	0.00000	0.0030	0.00561
Coarse Sand	3,364 (No. 6)	0.3364	0.0020	0.00516	0.0010	0.00258
	2,000 (No. 10)	0.2000	0.0110	0.04451	0.0020	0.00809
Medium Sand	1414 (No. 14)	0.1414	0.0130	0.07976	0.0020	0.01227
	1000 (No. 18)	0.1000	0.0120	0.10409	0.0050	0.04337
	707 (No. 25)	0.0707	0.0170	0.20847	0.0110	0.13489
	500 (No. 35)	0.0500	0.0370	0.64143	0.0430	0.74545
	420 (No. 40)	0.0420	0.0250	0.55300	0.0520	1.15023
Fine Sand	354 (No. 45)	0.0354	0.0340	0.89337	0.1010	2.65382
	250 (No. 60)	0.0250	0.0820	2.83950	0.3730	12.91627
	177 (No. 80)	0.0177	0.0860	4.20907	0.1750	8.56498
	125 (No. 120)	0.0125	0.0740	5.12140	0.0500	3.46041
Silt	5	0.0005	0.4180	226.01511	0.1190	64.34402
Clay	2	0.0002	0.0750	256.78197	0.0170	58.20391
	1	0.0001	0.0620	464.27529	0.0250	187.20778
	0.5	0.00005	0.0290	434.02110	0.0120	179.59494
	0.4	0.00004	0.0230	520.13761	0.0090	203.53211
		Sum	1.00	1915.931	1.00	722.581
		Estimated Maximum k (cm/sec)		2.59E-05		1.82E-04
		Estimated Median k (cm/sec)		1.11E-05		7.81E-05
		Estimated Minimum k (cm/sec)		3.68E-06		2.58E-05
		% Gravel	0.0		0.3	
		% Sand	39.3		81.5	
		% Silt	41.8		11.9	
		% Clay	18.9		6.3	

Notes:

1. Kozeny-Carman Equation:

$$k = [\Theta^3/(1-\Theta)^2]*(1.99 \times 10^4)/\{(\Sigma[f_i/(d_{li}^{0.404} \times d_{si}^{0.595})])^2 * SF^2\}$$

where Θ = total porosity

1.99×10^4 = constant incorporating unit weight and viscosity of water and the empirical Kozeny-Carmon coefficient (1/cm-sec)

f_i = fraction of particles retained on the smaller sieve of adjacent sieve pairs (dimensionless)

d_{li} = diameter of larger sieve in pair (cm)

d_{si} = diameter of smaller sieve in pair (cm)

SF = grain shape factor (dimensionless)

3. Estimated shape factors:

Rounded	6.1
Median	6.25
Worn	6.4

4. Estimated porosities:

Maximum	0.40
Median	0.33
Minimum	0.25

Table G-12d

Estimated Hydraulic Conductivity Based On Grain Size Analyses
American Linen Suply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Particle Type	Screen Size (microns)	Screen Size (cm)	MW-160 (127.5 feet bgs)		MW-161 (100 feet bgs)	
			Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$
Coarse Gravel	1"	2.5002	0.0000	–	0.0000	–
Fine Gravel	½"	1.2501	0.0690	0.04172	0.0000	0.00000
	3/8"	0.9500	0.0270	0.02544	0.0000	0.00000
	1/4"	0.6351	0.0590	0.07892	0.0090	0.01204
	4,757 (No. 4)	0.4757	0.0350	0.06542	0.0210	0.03925
Coarse Sand	3,364 (No. 6)	0.3364	0.0410	0.10584	0.0130	0.03356
	2,000 (No. 10)	0.2000	0.0700	0.28323	0.0210	0.08497
Medium Sand	1414 (No. 14)	0.1414	0.0540	0.33133	0.0170	0.10431
	1000 (No. 18)	0.1000	0.0480	0.41635	0.0260	0.22552
	707 (No. 25)	0.0707	0.0400	0.49052	0.0490	0.60089
	500 (No. 35)	0.0500	0.0480	0.83213	0.1080	1.87228
	420 (No. 40)	0.0420	0.0210	0.46452	0.1000	2.21199
Fine Sand	354 (No. 45)	0.0354	0.0240	0.63061	0.1570	4.12525
	250 (No. 60)	0.0250	0.0460	1.59289	0.2950	10.21528
	177 (No. 80)	0.0177	0.0380	1.85982	0.0930	4.55167
	125 (No. 120)	0.0125	0.0310	2.14545	0.0220	1.52258
Silt	5	0.0005	0.2120	114.62968	0.0260	14.05836
Clay	2	0.0002	0.0310	106.13655	0.0110	37.66136
	1	0.0001	0.0540	404.36880	0.0180	134.78960
	0.5	0.00005	0.0320	478.91984	0.0090	134.69620
	0.4	0.00004	0.0190	429.67890	0.0060	135.68807
		Sum	1.00	1543.098	1.00	482.493
		Estimated Maximum k (cm/sec)		3.99E-05		4.08E-04
		Estimated Median k (cm/sec)		1.71E-05		1.75E-04
		Estimated Minimum k (cm/sec)		5.67E-06		5.80E-05
		% Gravel	19.0		3.0	
		% Sand	46.1		90.1	
		% Silt	21.2		2.6	
		% Clay	13.6		4.4	

Notes:

1. Kozeny-Carman Equation:

$$k = [\Theta^3/(1-\Theta)^2]*(1.99 \times 10^4)/\{(\Sigma[f_i/(d_{li}^{0.404} \times d_{si}^{0.595})])^2 * SF^2\}$$

where Θ = total porosity

1.99×10^4 = constant incorporating unit weight and viscosity of water and the empirical Kozeny-Carmon coefficient (1/cm-sec)

f_i = fraction of particles retained on the smaller sieve of adjacent sieve pairs (dimensionless)

d_{li} = diameter of larger sieve in pair (cm)

d_{si} = diameter of smaller sieve in pair (cm)

SF = grain shape factor (dimensionless)

3. Estimated shape factors:

Rounded	6.1
Median	6.25
Worn	6.4

4. Estimated porosities:

Maximum	0.40
Median	0.33
Minimum	0.25

Table G-12d

Estimated Hydraulic Conductivity Based On Grain Size Analyses
American Linen Suply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Particle Type	Screen Size (microns)	Screen Size (cm)	MW-161 (140 feet bgs)	
			Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$
Coarse Gravel	1"	2.5002	0.0000	–
Fine Gravel	½"	1.2501	0.0150	0.00907
	3/8"	0.9500	0.0090	0.00848
	1/4"	0.6351	0.0750	0.10032
	4,757 (No. 4)	0.4757	0.0550	0.10280
Coarse Sand	3,364 (No. 6)	0.3364	0.0640	0.16522
	2,000 (No. 10)	0.2000	0.0990	0.40056
Medium Sand	1414 (No. 14)	0.1414	0.0670	0.41109
	1000 (No. 18)	0.1000	0.0540	0.46839
	707 (No. 25)	0.0707	0.0430	0.52731
	500 (No. 35)	0.0500	0.0470	0.81479
	420 (No. 40)	0.0420	0.0200	0.44240
Fine Sand	354 (No. 45)	0.0354	0.0220	0.57806
	250 (No. 60)	0.0250	0.0420	1.45438
	177 (No. 80)	0.0177	0.0340	1.66405
	125 (No. 120)	0.0125	0.0270	1.86862
Silt	5	0.0005	0.2130	115.17038
Clay	2	0.0002	0.0240	82.17023
	1	0.0001	0.0450	336.97400
	0.5	0.00005	0.0270	404.08861
	0.4	0.00004	0.0170	384.44954
		Sum	1.00	1331.868
		Estimated Maximum k (cm/sec)		5.36E-05
		Estimated Median k (cm/sec)		2.30E-05
		Estimated Minimum k (cm/sec)		7.61E-06
		% Gravel	15.4	
		% Sand	51.9	
		% Silt	21.3	
		% Clay	11.3	

Notes: See previous page for notes.

Table G-12e

Estimated Hydraulic Conductivity Based On Grain Size Analyses
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Particle Type	Screen Size (microns)	Screen Size (cm)	MW-190 (48 feet bgs)		MW-302 (33 feet bgs)		MW-302 (60 feet bgs)		MW-304 (81 feet bgs)		MW-304 (108 feet bgs)		MW-307 (44 feet bgs)		MW-309 (59 feet bgs)	
			Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$
Coarse Gravel	1"	2.5002	0.0000	–	0.0000	–	0.0000	–	0.0000	–	0.0000	–	0.0000	–	0.0000	–
Fine Gravel	½"	1.2501	0.0202	0.01219	0.0212	0.01281	0.0213	0.01288	0.0000	0.00000	0.0445	0.02689	0.0000	0.00000	0.0245	0.01484
	3/8"	0.9500	0.0084	0.00790	0.0247	0.02328	0.0414	0.03896	0.0000	0.00000	0.0000	0.00000	0.0000	0.00000	0.0095	0.00899
	1/4"	0.6351	0.0224	0.02995	0.0191	0.02556	0.0279	0.03729	0.0000	0.00000	0.0266	0.03556	0.0140	0.01868	0.0233	0.03114
	4,757 (No. 4)	0.4757	0.0163	0.03044	0.0237	0.04422	0.0248	0.04635	0.0007	0.00137	0.0180	0.03367	0.0196	0.03657	0.0123	0.02297
Coarse Sand	3,364 (No. 6)	0.3364	0.0164	0.04237	0.0227	0.05859	0.0207	0.05342	0.0000	0.00000	0.0232	0.06000	0.0145	0.03748	0.0123	0.03179
	2,000 (No. 10)	0.2000	0.0260	0.10521	0.0381	0.15410	0.0241	0.09743	0.0003	0.00125	0.0424	0.17143	0.0253	0.10239	0.0206	0.08342
Medium Sand	1414 (No. 14)	0.1414	0.0204	0.12504	0.0256	0.15729	0.0205	0.12582	0.0005	0.00331	0.0500	0.30691	0.0209	0.12812	0.0150	0.09192
	1000 (No. 18)	0.1000	0.0200	0.17310	0.0253	0.21917	0.0208	0.18016	0.0010	0.00901	0.0977	0.84757	0.0226	0.19634	0.0138	0.11994
	707 (No. 25)	0.0707	0.0259	0.31806	0.0363	0.44563	0.0286	0.35114	0.0015	0.01793	0.2295	2.81485	0.0476	0.58387	0.0229	0.28114
	500 (No. 35)	0.0500	0.0417	0.72235	0.0600	1.04014	0.0487	0.84406	0.0012	0.02068	0.0940	1.62930	0.1180	2.04638	0.0423	0.73389
	420 (No. 40)	0.0420	0.0293	0.64849	0.0030	0.06605	0.0021	0.04744	0.0002	0.00340	0.0778	1.71997	0.0226	0.49989	0.0032	0.07114
Fine Sand	354 (No. 45)	0.0354	0.0544	1.42962	0.0685	1.79982	0.0632	1.66094	0.0003	0.00809	0.1230	3.23260	0.1245	3.27074	0.0001	0.00332
	250 (No. 60)	0.0250	0.0786	2.72144	0.1106	3.83077	0.0908	3.14268	0.0010	0.03465	0.0911	3.15292	0.2458	8.51329	0.0200	0.69256
	177 (No. 80)	0.01768	0.0709	3.47018	0.0897	4.39199	0.0753	3.68925	0.0017	0.08481	0.0289	1.41461	0.1095	5.36503	0.0649	3.17883
	149 (No. 100)	0.01487	0.0254	1.58639	0.2366	14.77235	0.0407	2.53906	0.0015	0.09612	0.0300	1.87200	0.0278	1.73832	0.0101	0.63030
	125 (No. 120)	0.0125	0.0271	1.87360	0.0173	1.19881	0.0241	1.67202	0.0000	-0.00037	0.0013	0.08989	0.0118	0.81817	0.0030	0.20772
	105 (No. 140)	0.01051	0.0216	1.78214	0.0138	1.13700	0.0201	1.65805	0.0010	0.08233	0.0008	0.06495	0.0066	0.54411	0.0030	0.24698
	88 (No. 170)	0.00884	0.0178	1.74617	0.0113	1.10697	0.0165	1.61831	0.0010	0.09788	0.0005	0.04790	0.0050	0.49010	0.0020	0.19577
	74 (No. 200)	0.00743	0.0157	1.83185	0.0098	1.14185	0.0139	1.62151	0.0005	0.05821	0.0004	0.05115	0.0053	0.61790	0.0025	0.29105
Silt	63 (No. 230)	0.00625	0.0148	1.78451	0.0091	1.09569	0.0126	1.51894	0.0005	0.06015	0.0005	0.05767	0.0047	0.56625	0.0037	0.44506
	53 (No. 270)	0.00526	0.0148	2.12082	0.0087	1.24495	0.0125	1.79088	0.0026	0.37742	0.0005	0.06996	0.0029	0.41523	0.0289	4.13289
	44 (No. 325)	0.00442	0.0157	2.67586	0.0085	1.44668	0.0128	2.18115	0.0102	1.72950	0.0005	0.07812	0.0023	0.39169	0.0283	4.81317
	37 (No. 400)	0.00372	0.0175	3.54521	0.0086	1.73978	0.0137	2.77484	0.0126	2.54420	0.0005	0.09689	0.0041	0.82993	0.0281	5.68042
	31 (No. 450)	0.00313	0.0195	4.69469	0.0088	2.11566	0.0148	3.56243	0.0158	3.79759	0.0006	0.13434	0.0069	1.65987	0.0279	6.70248
	25 (No. 500)	0.0025	0.0210	6.19617	0.0089	2.62232	0.0158	4.66095	0.0193	5.69170	0.0006	0.18228	0.0084	2.47648	0.0276	8.12559
	20 (No. 635)	0.00201	0.0283	10.16374	0.0112	4.03101	0.0211	7.60326	0.0292	10.50119	0.0008	0.30166	0.0107	3.85336	0.0349	12.56036
	16	0.00156	0.0293	13.11991	0.0106	4.75603	0.0222	9.97273	0.0354	15.89012	0.0009	0.41189	0.0106	4.75889	0.0361	16.19828
	11	0.0011	0.0334	19.75023	0.0108	6.39651	0.0262	15.47681	0.0503	29.79438	0.0012	0.70917	0.0125	7.40781	0.0435	25.71783
	8	0.00078	0.0464	36.89550	0.0130	10.34491	0.0382	30.35501	0.0974	77.42039	0.0020	1.58804	0.0186	14.81008	0.0675	53.70640
	5	0.0005	0.0423	47.85095	0.0103	11.66290	0.0366	41.37938	0.1198	135.56936	0.0023	2.59864	0.0176	19.94081	0.0697	78.80542
Clay	2	0.0002	0.0443	54.66765	0.0098	12.10390	0.0403	49.71039	0.1581	195.09414	0.0028	3.45069	0.0185	22.86293	0.0821	101.31644
	1	0.0001	0.0609	456.29316	0.0127	95.17769	0.0585	438.19376	0.2568	1922.72423	0.0045	33.65063	0.0236	176.97190	0.1245	931.92415
	0.5	0.00005	0.0326	487.47541	0.0071	106.34542	0.0305	455.88562	0.1168	1748.08994	0.0025	37.36368	0.0105	157.36588	0.0590	883.21243
	0.4	0.00004	0.0206	466.88954	0.0045	101.84753	0.0185	419.20998	0.0626	1416.36030	0.0002	4.96832	0.0063	142.67222	0.0327	739.91703
		Sum	1.00	1632.780	1.00	394.557	1.00	1503.713	1.00	5566.163	1.00	103.234	1.00	581.991	1.00	2880.196
		Estimated Maximum k (cm/sec)		3.57E-05		6.11E-04		4.20E-05		3.07E-06		8.92E-03		2.81E-04		1.15E-05
		Estimated Median k (cm/sec)		1.53E-05		2.62E-04		1.80E-05		1.32E-06		3.83E-03		1.20E-04		4.92E-06
		Estimated Minimum k (cm/sec)		5.06E-06		8.67E-05		5.97E-06		4.36E-07		1.27E-03		3.98E-05		1.63E-06
		% Gravel	6.7		8.9		11.5		0.1		8.9		3.4		7.0	
		% Sand	49.1		76.9		51.0		1.2		89.1		80.8		23.6	
		% Silt	28.3		10.9		22.7		39.3		1.0		9.9		39.6	
		% Clay	15.8		3.4		14.8		59.4		1.0		5.9		29.8	

Notes:

1. Kozeny-Carman Equation:

$$k = [\Theta^3/(1-\Theta)^2]*(1.99 \times 10^4)/\{(\Sigma[f_i/(d_{li}^{0.404} \times d_{si}^{0.595})])^2 * SF^2\}$$

where Θ = total porosity

1.99×10^4 = constant incorporating unit weight and viscosity of water and the empirical Kozeny-Carmon coefficient (1/cm-sec)

f_i = fraction of particles retained on the smaller sieve of adjacent sieve pairs (dimensionless)

d_{li} = diameter of larger sieve in pair (cm)

d_{si} = diameter of smaller sieve in pair (cm)

SF = grain shape factor (dimensionless)

2. Frac retained = fraction (by weight) retained on screen

3. Estimated shape factors:

Rounded	6.1
Median	6.25
Worn	6.4

4. Estimated porosities:

Maximum	0.40
Median	0.33
Minimum	0.25

Table G-12e

Estimated Hydraulic Conductivity Based On Grain Size Analyses
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Particle Type	Screen Size (microns)	Screen Size (cm)	MW-311 (40 feet bgs)		MW-311 (48 feet bgs)		MW-314 (43 feet bgs)		MW-316 (37 feet bgs)		MW-316 (58 feet bgs)		MW-319 (28 feet bgs)		MW-322 (32 feet bgs)	
			Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$
Coarse Gravel	1"	2.5002	0.0000	–	0.0000	–	0.0000	–	0.0000	–	0.0000	–	0.0000	–	0.0000	–
Fine Gravel	½"	1.2501	0.0000	0.00000	0.0000	0.00000	0.0000	0.00000	0.0161	0.00972	0.0557	0.03366	0.0727	0.04396	0.0184	0.01114
	3/8"	0.9500	0.0000	0.00000	0.0000	0.00000	0.0000	0.00000	0.0185	0.01747	0.0000	0.00000	0.0336	0.03166	0.0133	0.01255
	1/4"	0.6351	0.0000	0.00000	0.0000	0.00000	0.0108	0.01448	0.0096	0.01289	0.0665	0.08898	0.0693	0.09272	0.0198	0.02655
	4,757 (No. 4)	0.4757	0.0000	0.00000	0.0000	0.00000	0.0066	0.01230	0.0145	0.02701	0.0454	0.08479	0.0300	0.05611	0.0175	0.03262
Coarse Sand	3,364 (No. 6)	0.3364	0.0002	0.00056	0.0000	0.00000	0.0074	0.01918	0.0160	0.04118	0.0438	0.11315	0.0273	0.07039	0.0210	0.05430
	2,000 (No. 10)	0.2000	0.0007	0.00278	0.0004	0.00157	0.0157	0.06333	0.0247	0.09975	0.0681	0.27573	0.0321	0.13001	0.0350	0.14157
Medium Sand	1414 (No. 14)	0.1414	0.0004	0.00244	0.0001	0.00079	0.0108	0.06642	0.0172	0.10581	0.0418	0.25634	0.0201	0.12304	0.0267	0.16384
	1000 (No. 18)	0.1000	0.0003	0.00251	0.0003	0.00253	0.0111	0.09618	0.0191	0.16609	0.0392	0.34007	0.0191	0.16530	0.0222	0.19246
	707 (No. 25)	0.0707	0.0003	0.00399	0.0006	0.00794	0.0202	0.24720	0.0346	0.42396	0.0562	0.68925	0.0262	0.32100	0.0200	0.24543
	500 (No. 35)	0.0500	0.0003	0.00564	0.0001	0.00225	0.0414	0.71770	0.0700	1.21272	0.0702	1.21698	0.0469	0.81296	0.0276	0.47915
	420 (No. 40)	0.0420	0.0000	0.00080	0.0001	0.00143	0.0090	0.19868	0.0242	0.53460	0.0110	0.24239	0.0044	0.09659	0.0009	0.02010
Fine Sand	354 (No. 45)	0.0354	0.0009	0.02281	0.0017	0.04509	0.0518	1.36071	0.0754	1.98167	0.0630	1.65537	0.0234	0.61514	0.0267	0.70092
	250 (No. 60)	0.0250	0.0154	0.53476	0.0573	1.98471	0.0830	2.87428	0.1394	4.82651	0.0867	3.00156	0.0440	1.52364	0.0342	1.18398
	177 (No. 80)	0.01768	0.1199	5.86999	0.3394	16.62020	0.0711	3.48342	0.1044	5.11526	0.0474	2.32363	0.0710	3.47727	0.0389	1.90510
	149 (No. 100)	0.01487	0.2221	13.86657	0.2230	13.92641	0.0979	6.11121	0.1428	8.91525	0.0135	0.84353	0.0475	2.96846	0.0388	2.42041
	125 (No. 120)	0.0125	0.1350	9.35018	0.1449	10.03549	0.0242	1.67879	0.0152	1.05318	0.0196	1.35846	0.0223	1.54606	0.0080	0.55073
	105 (No. 140)	0.01051	0.1220	10.04669	0.0948	7.80110	0.0232	1.91358	0.0117	0.96388	0.0126	1.03834	0.0178	1.46730	0.0107	0.88088
	88 (No. 170)	0.00884	0.0977	9.56608	0.0526	5.14648	0.0229	2.24580	0.0098	0.95993	0.0085	0.83284	0.0161	1.57797	0.0387	3.78809
	74 (No. 200)	0.00743	0.0733	8.53628	0.0270	3.14205	0.0230	2.68280	0.0090	1.04853	0.0066	0.76915	0.0158	1.84186	0.0041	0.47733
Silt	63 (No. 230)	0.00625	0.0536	6.45052	0.0145	1.74374	0.0229	2.76033	0.0085	1.02335	0.0058	0.69849	0.0155	1.86722	0.0110	1.32340
	53 (No. 270)	0.00526	0.0388	5.54943	0.0088	1.25772	0.0225	3.22325	0.0084	1.20190	0.0052	0.74426	0.0152	2.17618	0.0141	2.01607
	44 (No. 325)	0.00442	0.0277	4.71213	0.0056	0.95194	0.0219	3.73145	0.0087	1.48057	0.0048	0.81711	0.0156	2.65642	0.0100	1.70062
	37 (No. 400)	0.00372	0.0193	3.90243	0.0036	0.72739	0.0216	4.37449	0.0093	1.88120	0.0048	0.97123	0.0170	3.44082	0.0024	0.48513
	31 (No. 450)	0.00313	0.0135	3.24399	0.0025	0.60030	0.0215	5.17464	0.0098	2.35584	0.0055	1.32255	0.0180	4.32965	0.0217	5.21285
	25 (No. 500)	0.0025	0.0094	2.76825	0.0020	0.58856	0.0214	6.31229	0.0101	2.97559	0.0066	1.94503	0.0181	5.33569	0.0354	10.42199
	20 (No. 635)	0.00201	0.0081	2.91382	0.0021	0.75489	0.0273	9.80037	0.0132	4.75035	0.0100	3.59983	0.0227	8.17407	0.0326	11.72372
	16	0.00156	0.0053	2.37683	0.0017	0.76183	0.0281	12.57695	0.0137	6.14633	0.0122	5.47502	0.0227	10.19019	0.0287	12.86688
	11	0.0011	0.0043	2.54548	0.0017	1.00562	0.0330	19.50713	0.0156	9.23847	0.0164	9.71516	0.0251	14.87339	0.0141	8.34431
	8	0.00078	0.0048	3.81775	0.0023	1.82801	0.0479	38.07937	0.0226	17.98244	0.0278	22.12663	0.0337	26.83063	0.0200	15.90252
	5	0.0005	0.0040	4.52702	0.0021	2.37496	0.0449	50.78385	0.0218	24.68211	0.0297	33.63664	0.0309	35.00621	0.0151	17.08436
Clay	2	0.0002	0.0042	5.18479	0.0022	2.71387	0.0476	58.73151	0.0240	29.63923	0.0348	42.98980	0.0342	42.26128	0.0692	85.39997
	1	0.0001	0.0070	52.43391	0.0033	24.70090	0.0627	469.66063	0.0344	257.77835	0.0489	366.54496	0.0517	386.89983	0.0976	730.71605
	0.5	0.00005	0.0063	94.31564	0.0036	53.85554	0.0292	436.34679	0.0172	257.59973	0.0204	305.61701	0.0253	379.13888	0.1291	1932.77864
	0.4	0.00004	0.0050	113.10733	0.0017	38.42858	0.0172	389.71293	0.0104	235.35741	0.0110	249.01048	0.0143	323.81086	0.0765	1729.49348
		Sum	1.00	365.661	1.00	191.012	1.00	1534.562	1.00	881.608	1.00	1060.378	1.00	1263.953	1.00	4578.757
		Estimated Maximum k (cm/sec)		7.11E-04		2.61E-03		4.04E-05		1.22E-04		8.46E-05		5.95E-05		4.53E-06
		Estimated Median k (cm/sec)		3.05E-04		1.12E-03		1.73E-05		5.25E-05		3.63E-05		2.55E-05		1.95E-06
		Estimated Minimum k (cm/sec)		1.01E-04		3.70E-04		5.73E-06		1.74E-05		1.20E-05		8.45E-06		6.44E-07
		% Gravel	0.0		0.0		1.7		5.9		16.8		20.6		6.9	
		% Sand	78.9		94.2		51.3		71.3		58.8		43.4		35.3	
		% Silt	18.9		4.7		31.3		14.2		12.9		23.5		20.5	
		% Clay	2.3		1.1		15.7		8.6		11.5		12.6		37.2	

Notes:

1. Kozeny-Carman Equation:

$$k = [\Theta^3/(1-\Theta)^2]*(1.99x10^4)/\{(\Sigma[f_i/(d_{li}^{0.404} \times d_{si}^{0.595})])^2*SF^2\}$$

where Θ = total porosity

1.99×10^4 = constant incorporating unit weight and viscosity of water and the empirical Kozeny-Carmon coefficient (1/cm-sec)

f_i = fraction of particles retained on the smaller sieve of adjacent sieve pairs (dimensionless)

d_{li} = diameter of larger sieve in pair (cm)

d_{si} = diameter of smaller sieve in pair (cm)

SF = grain shape factor (dimensionless)

2. Frac retained = fraction (by weight) retained on screen

3. Estimated shape factors:

Rounded	6.1
Median	6.25
Worn	6.4

4. Estimated porosities:

Maximum	0.40
Median	0.33
Minimum	0.25

Table G-12e

Estimated Hydraulic Conductivity Based On Grain Size Analyses
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Particle Type	Screen Size (microns)	Screen Size (cm)	MW-324 (30 feet bgs)		MW-324 (38 feet bgs)		MW-326 (39 feet bgs)		MW-328 (45 feet bgs)		MW-328 (70 feet bgs)		MW-329 (70 feet bgs)		MW-329 (105 feet bgs)	
			Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$
Coarse Gravel	1"	2.5002	0.0000	–	0.0000	–	0.0000	–	0.0000	–	0.0000	–	0.0000	–	0.0000	–
Fine Gravel	½"	1.2501	0.0000	0.00000	0.0000	0.00000	0.0000	0.00000	0.0000	0.00000	0.0000	0.00000	0.0000	0.00000	0.0622	0.03764
	3/8"	0.9500	0.0000	0.00000	0.0078	0.00733	0.0000	0.00000	0.0000	0.00000	0.0000	0.00000	0.0000	0.00000	0.0518	0.04878
	1/4"	0.6351	0.0000	0.00000	0.0186	0.02485	0.0007	0.00092	0.0013	0.00177	0.0000	0.00000	0.0000	0.00000	0.0756	0.10116
	4,757 (No. 4)	0.4757	0.0000	0.00000	0.0089	0.01661	0.0005	0.00087	0.0011	0.00205	0.0000	0.00000	0.0000	0.00000	0.0448	0.08380
Coarse Sand	3,364 (No. 6)	0.3364	0.0000	0.00000	0.0091	0.02361	0.0000	0.00000	0.0019	0.00500	0.0001	0.00038	0.0000	0.00000	0.0567	0.14649
	2,000 (No. 10)	0.2000	0.0003	0.00126	0.0142	0.05737	0.0005	0.00214	0.0035	0.01409	0.0006	0.00251	0.0037	0.01516	0.2154	0.87134
Medium Sand	1414 (No. 14)	0.1414	0.0003	0.00190	0.0101	0.06179	0.0005	0.00324	0.0023	0.01413	0.0008	0.00471	0.0190	0.11675	0.0586	0.35954
	1000 (No. 18)	0.1000	0.0005	0.00423	0.0093	0.08108	0.0006	0.00540	0.0029	0.02509	0.0019	0.01649	0.0437	0.37934	0.0588	0.51025
	707 (No. 25)	0.0707	0.0007	0.00870	0.0107	0.13131	0.0040	0.04882	0.0043	0.05303	0.0070	0.08561	0.0968	1.18726	0.0160	0.19607
	500 (No. 35)	0.0500	0.0011	0.01921	0.0139	0.24182	0.0216	0.37362	0.0087	0.15043	0.0299	0.51894	0.1518	2.63146	0.0110	0.19070
	420 (No. 40)	0.0420	0.0002	0.00392	0.0006	0.01408	0.0059	0.13070	0.0006	0.01242	0.0052	0.11400	0.0369	0.81526	0.0140	0.30968
Fine Sand	354 (No. 45)	0.0354	0.0022	0.05707	0.0170	0.44787	0.0342	0.89805	0.0217	0.57113	0.1134	2.98000	0.1764	4.63465	0.0070	0.18393
	250 (No. 60)	0.0250	0.0070	0.24097	0.0283	0.98007	0.1388	4.80518	0.0554	1.91768	0.3376	11.68951	0.2527	8.74994	0.0080	0.27702
	177 (No. 80)	0.01768	0.0103	0.50363	0.0450	2.20536	0.2974	14.56704	0.0667	3.26514	0.2724	13.34121	0.1337	6.55028	0.0199	0.97657
	149 (No. 100)	0.01487	0.0839	5.24122	0.0183	1.14508	0.2105	13.14233	0.3234	20.19519	0.1187	7.40963	0.0590	3.68189	0.0091	0.56950
	125 (No. 120)	0.0125	0.0146	1.01265	0.0021	0.14386	0.0984	6.81524	0.0406	2.80871	0.0379	2.62288	0.0071	0.49249	0.0076	0.52738
	105 (No. 140)	0.01051	0.0095	0.78054	0.0335	2.76098	0.0651	5.36098	0.0351	2.88600	0.0210	1.72797	0.0035	0.28866	0.0067	0.55279
	88 (No. 170)	0.00884	0.0105	1.02678	0.0304	2.97808	0.0381	3.73048	0.0318	3.10788	0.0119	1.16423	0.0019	0.18631	0.0062	0.60822
	74 (No. 200)	0.00743	0.0098	1.13904	0.0268	3.12126	0.0213	2.48053	0.0298	3.47493	0.0072	0.83782	0.0011	0.12829	0.0061	0.71174
Silt	63 (No. 230)	0.00625	0.0072	0.86157	0.0238	2.86307	0.0124	1.49228	0.0281	3.38611	0.0046	0.55315	0.0008	0.09281	0.0064	0.77168
	53 (No. 270)	0.00526	0.0053	0.76436	0.0219	3.12987	0.0078	1.11561	0.0258	3.69489	0.0031	0.44303	0.0006	0.08881	0.0067	0.96010
	44 (No. 325)	0.00442	0.0048	0.82334	0.0216	3.67138	0.0052	0.88459	0.0229	3.90066	0.0022	0.37395	0.0006	0.09370	0.0071	1.21010
	37 (No. 400)	0.00372	0.0052	1.06019	0.0237	4.79009	0.0038	0.76835	0.0200	4.04923	0.0018	0.36367	0.0005	0.10328	0.0079	1.60041
	31 (No. 450)	0.00313	0.0054	1.30841	0.0275	6.60922	0.0030	0.72089	0.0173	4.16253	0.0015	0.36016	0.0005	0.11792	0.0088	2.11863
	25 (No. 500)	0.0025	0.0055	1.63322	0.0317	9.34155	0.0024	0.70679	0.0149	4.39369	0.0014	0.41196	0.0005	0.14157	0.0096	2.83253
	20 (No. 635)	0.00201	0.0085	3.04692	0.0447	16.06912	0.0025	0.89933	0.0163	5.87125	0.0015	0.53917	0.0006	0.21616	0.0131	4.72145
	16	0.00156	0.0116	5.20023	0.0475	21.29300	0.0021	0.94176	0.0145	6.51111	0.0014	0.62734	0.0006	0.27397	0.0140	6.29037
	11	0.0011	0.0152	9.01326	0.0536	31.73196	0.0021	1.24314	0.0161	9.54317	0.0016	0.94640	0.0007	0.43279	0.0167	9.90477
	8	0.00078	0.0330	26.22511	0.0726	57.72428	0.0029	2.30656	0.0248	19.75073	0.0022	1.74840	0.0011	0.87622	0.0257	20.40011
	5	0.0005	0.0647	73.14982	0.0648	73.27665	0.0028	3.16891	0.0269	30.48382	0.0022	2.48787	0.0011	1.24680	0.0262	29.59502
Clay	2	0.0002	0.1281	158.08436	0.0681	84.01669	0.0031	3.82687	0.0337	41.53233	0.0024	2.96037	0.0012	1.48359	0.0311	38.34156
	1	0.0001	0.3097	2318.76011	0.0994	744.39482	0.0050	37.45279	0.0566	423.76761	0.0040	29.93828	0.0021	15.75381	0.0497	372.23916
	0.5	0.00005	0.1614	2415.27393	0.0575	861.09633	0.0039	58.38587	0.0316	472.19222	0.0032	47.86805	0.0016	23.98917	0.0261	389.98032
	0.4	0.00004	0.0835	1888.66235	0.0368	831.10477	0.0029	65.60225	0.0192	434.89767	0.0014	31.64473	0.0001	3.17176	0.0151	342.23457
		Sum	1.00	6913.908	1.00	2765.555	1.00	231.882	1.00	1506.642	1.00	163.782	1.00	77.940	1.00	1230.463
		Estimated Maximum k (cm/sec)		1.99E-06		1.24E-05		1.77E-03		4.19E-05		3.54E-03		1.57E-02		6.28E-05
		Estimated Median k (cm/sec)		8.53E-07		5.33E-06		7.58E-04		1.80E-05		1.52E-03		6.71E-03		2.69E-05
		Estimated Minimum k (cm/sec)		2.82E-07		1.76E-06		2.51E-04		5.95E-06		5.03E-04		2.22E-03		8.91E-06
		% Gravel	0.0		3.5		0.1		0.2		0.0		0.0		23.4	
		% Sand	15.1		27.0		93.7		62.9		96.6		98.7		50.1	
		% Silt	16.7		43.3		4.7		22.8		2.3		0.8		14.2	
		% Clay	68.3		26.2		1.5		14.1		1.1		0.5		12.2	

Notes:

1. Kozeny-Carman Equation:

$$k = [\Theta^3/(1-\Theta)^2]*(1.99 \times 10^4)/\{(\Sigma[f_i/(d_{li}^{0.404} \times d_{si}^{0.595})])^2 * SF^2\}$$

where Θ = total porosity

1.99×10^4 = constant incorporating unit weight and viscosity of water and the empirical Kozeny-Carmon coefficient (1/cm-sec)

f_i = fraction of particles retained on the smaller sieve of adjacent sieve pairs (dimensionless)

d_{li} = diameter of larger sieve in pair (cm)

d_{si} = diameter of smaller sieve in pair (cm)

SF = grain shape factor (dimensionless)

2. Frac retained = fraction (by weight) retained on screen

3. Estimated shape factors:

Rounded	6.1
Median	6.25
Worn	6.4

4. Estimated porosities:

Maximum	0.40
Median	0.33
Minimum	0.25

Table G-12f

Estimated Hydraulic Conductivity Based On Grain Size Analyses
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Particle Type	Screen Size (microns)	Screen Size (cm)	MW-331 (44 to 45 feet bgs)		MW-334 (26 to 27 feet bgs)	
			Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$
Coarse Gravel	1"	2.5002	0.0000	–	0.0000	–
Fine Gravel	½"	1.2501	0.0000	0.00000	0.0000	0.00000
	3/8"	0.9500	0.0000	0.00000	0.0000	0.00000
	1/4"	0.6351	0.0000	0.00000	0.0012	0.00159
	4,757 (No. 4)	0.4757	0.0000	0.00000	0.0064	0.01201
Coarse Sand	3,364 (No. 6)	0.3364	0.0000	0.00000	0.0177	0.04567
	2,000 (No. 10)	0.2000	0.0004	0.00162	0.0291	0.11763
Medium Sand	1414 (No. 14)	0.1414	0.0004	0.00246	0.0468	0.28693
	1000 (No. 18)	0.1000	0.0014	0.01182	0.0695	0.60267
	707 (No. 25)	0.0707	0.0048	0.05923	0.0833	1.02099
	500 (No. 35)	0.0500	0.0005	0.00869	0.0651	1.12887
	420 (No. 40)	0.0420	0.0007	0.01507	0.0244	0.53923
Fine Sand	354 (No. 45)	0.0354	0.0021	0.05424	0.0738	1.93966
	250 (No. 60)	0.0250	0.0083	0.28592	0.1147	3.97192
	177 (No. 80)	0.0177	0.0332	1.62727	0.1234	6.03747
	125 (No. 120)	0.0125	0.0027	0.19002	0.0686	4.74791
	74 (No. 200)	0.0074	0.5401	58.76349	0.0924	10.04984
Silt	53 (No. 270)	0.0053	0.2915	47.80746	0.0893	14.64359
	37 (No. 400)	0.0037	0.0681	15.83395	0.0683	15.88006
Clay	18 (assumed)	0.0018	0.0458	18.91259	0.0262	10.80251
		Sum	1.00	143.574	1.00	71.829
		Estimated Maximum k (cm/sec)		4.61E-03		1.84E-02
		Estimated Median k (cm/sec)		1.98E-03		7.90E-03
		Estimated Minimum k (cm/sec)		6.55E-04		2.62E-03
		% Gravel	0.0		0.8	
		% Sand	59.5		80.9	
		% Silt	36.0		15.8	
		% Clay	4.6		2.6	

Notes:

1. Kozeny-Carman Equation:

$$k = [\Theta^3/(1-\Theta)^2]*(1.99 \times 10^4)/\{(\Sigma[f_i/(d_{li}^{0.404} \times d_{si}^{0.595})])^2 * SF^2\}$$

where Θ = total porosity

1.99×10^4 = constant incorporating unit weight and viscosity of water and the empirical Kozeny-Carmon coefficient (1/cm-sec)

f_i = fraction of particles retained on the smaller sieve of adjacent sieve pairs (dimensionless)

d_{li} = diameter of larger sieve in pair (cm)

d_{si} = diameter of smaller sieve in pair (cm)

SF = grain shape factor (dimensionless)

2. Frac retained = fraction (by weight) retained on screen
3. Estimated shape factors:

Rounded	6.1
Median	6.25
Worn	6.4

4. Estimated porosities:

Maximum	0.40
Median	0.33
Minimum	0.25

Table G-12f

Estimated Hydraulic Conductivity Based On Grain Size Analyses
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Particle Type	Screen Size (microns)	Screen Size (cm)	MW-335 (19 to 20 feet bgs)		MW-335 (39 to 40 feet bgs)	
			Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$
Coarse Gravel	1"	2.5002	0.0000	–	0.0000	–
Fine Gravel	½"	1.2501	0.1186	0.07170	0.0000	0.00000
	3/8"	0.9500	0.0205	0.01931	0.0000	0.00000
	1/4"	0.6351	0.0173	0.02308	0.0000	0.00000
	4,757 (No. 4)	0.4757	0.0121	0.02263	0.0000	0.00000
Coarse Sand	3,364 (No. 6)	0.3364	0.0098	0.02519	0.0000	0.00000
	2,000 (No. 10)	0.2000	0.0116	0.04705	0.0020	0.00794
Medium Sand	1414 (No. 14)	0.1414	0.0176	0.10817	0.0057	0.03512
	1000 (No. 18)	0.1000	0.0412	0.35699	0.0128	0.11132
	707 (No. 25)	0.0707	0.0798	0.97858	0.0241	0.29495
	500 (No. 35)	0.0500	0.0559	0.96943	0.0053	0.09204
	420 (No. 40)	0.0420	0.0225	0.49836	0.0047	0.10314
Fine Sand	354 (No. 45)	0.0354	0.0740	1.94564	0.0102	0.26869
	250 (No. 60)	0.0250	0.1042	3.60676	0.0216	0.74816
	177 (No. 80)	0.0177	0.0805	3.94119	0.0302	1.47883
	125 (No. 120)	0.0125	0.0025	0.17389	0.0335	2.31802
	74 (No. 200)	0.0074	0.1241	13.50424	0.1298	14.12010
Silt	53 (No. 270)	0.0053	0.0576	9.44425	0.4388	71.96381
	37 (No. 400)	0.0037	0.0761	17.67995	0.1753	40.75039
Clay	18 (assumed)	0.0018	0.0742	30.59714	0.1061	43.76595
		Sum	1.00	84.014	1.00	176.058
		Estimated Maximum k (cm/sec)		1.35E-02		3.07E-03
		Estimated Median k (cm/sec)		5.78E-03		1.32E-03
		Estimated Minimum k (cm/sec)		1.91E-03		4.35E-04
		% Gravel	16.8		0.0	
		% Sand	62.4		28.0	
		% Silt	13.4		61.4	
		% Clay	7.4		10.6	

Notes:

1. Kozeny-Carman Equation:

$$k = [\Theta^3/(1-\Theta)^2]*(1.99 \times 10^4)/\{(\Sigma[f_i/(d_{li}^{0.404} \times d_{si}^{0.595})])^2 * SF^2\}$$

where Θ = total porosity

1.99×10^4 = constant incorporating unit weight and viscosity of water and the empirical Kozeny-Carmon coefficient (1/cm-sec)

f_i = fraction of particles retained on the smaller sieve of adjacent sieve pairs (dimensionless)

d_{li} = diameter of larger sieve in pair (cm)

d_{si} = diameter of smaller sieve in pair (cm)

SF = grain shape factor (dimensionless)

2. Frac retained = fraction (by weight) retained on screen
3. Estimated shape factors: Rounded 6.1; Median 6.25; Worn 6.4
4. Estimated porosities: Maximum 0.40; Median 0.33; Minimum 0.25

Table G-12f

Estimated Hydraulic Conductivity Based On Grain Size Analyses
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Particle Type	Screen Size (microns)	Screen Size (cm)	MW-335 (68 to 69 feet bgs)		MW-336 (23.5 to 24.5 feet bgs)	
			Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$
Coarse Gravel	1"	2.5002	0.0000	–	0.0000	–
Fine Gravel	½"	1.2501	0.0000	0.00000	0.0000	0.00000
	3/8"	0.9500	0.0000	0.00000	0.0000	0.00000
	1/4"	0.6351	0.0000	0.00000	0.0000	0.00000
	4,757 (No. 4)	0.4757	0.0000	0.00000	0.0000	0.00000
Coarse Sand	3,364 (No. 6)	0.3364	0.0000	0.00000	0.0009	0.00235
	2,000 (No. 10)	0.2000	0.0000	0.00000	0.0264	0.10670
Medium Sand	1414 (No. 14)	0.1414	0.0003	0.00172	0.0652	0.40019
	1000 (No. 18)	0.1000	0.0026	0.02254	0.0809	0.70198
	707 (No. 25)	0.0707	0.0179	0.22008	0.0789	0.96709
	500 (No. 35)	0.0500	0.1348	2.33650	0.0565	0.98023
	420 (No. 40)	0.0420	0.0715	1.58214	0.0114	0.25234
Fine Sand	354 (No. 45)	0.0354	0.2814	7.39408	0.0751	1.97223
	250 (No. 60)	0.0250	0.2385	8.25806	0.0778	2.69364
	177 (No. 80)	0.0177	0.0793	3.88212	0.0894	4.37762
	125 (No. 120)	0.0125	0.0028	0.19502	0.0080	0.55495
	74 (No. 200)	0.0074	0.0534	5.81239	0.1463	15.92029
Silt	53 (No. 270)	0.0053	0.0252	4.13334	0.0646	10.60267
	37 (No. 400)	0.0037	0.0439	10.20105	0.0494	11.47121
Clay	18 (assumed)	0.0018	0.0483	19.94781	0.1691	69.78905
		Sum	1.00	63.987	1.00	120.793
		Estimated Maximum k (cm/sec)		2.32E-02		6.52E-03
		Estimated Median k (cm/sec)		9.96E-03		2.80E-03
		Estimated Minimum k (cm/sec)		3.30E-03		9.25E-04
		% Gravel	0.0		0.0	
		% Sand	88.3		71.7	
		% Silt	6.9		11.4	
		% Clay	4.8		16.9	

Notes:

1. Kozeny-Carman Equation:

$$k = [\Theta^3/(1-\Theta)^2]*(1.99 \times 10^4)/\{(\Sigma[f_i/(d_{li}^{0.404} \times d_{si}^{0.595})])^2 * SF^2\}$$

where Θ = total porosity

1.99×10^4 = constant incorporating unit weight and viscosity of water and the empirical Kozeny-Carmon coefficient (1/cm-sec)

f_i = fraction of particles retained on the smaller sieve of adjacent sieve pairs (dimensionless)

d_{li} = diameter of larger sieve in pair (cm)

d_{si} = diameter of smaller sieve in pair (cm)

SF = grain shape factor (dimensionless)

2. Frac retained = fraction (by weight) retained on screen
3. Estimated shape factors: Rounded 6.1; Median 6.25; Worn 6.4
4. Estimated porosities: Maximum 0.40; Median 0.33; Minimum 0.25

Table G-12f

Estimated Hydraulic Conductivity Based On Grain Size Analyses
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Particle Type	Screen Size (microns)	Screen Size (cm)	MW-336 (94 to 95 feet bgs)		MW-337 (15 to 15.5 feet bgs)	
			Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$
Coarse Gravel	1"	2.5002	0.0000	–	0.0000	–
Fine Gravel	½"	1.2501	0.0000	0.00000	0.0000	0.00000
	3/8"	0.9500	0.0000	0.00000	0.0333	0.03136
	1/4"	0.6351	0.0000	0.00000	0.0393	0.05256
	4,757 (No. 4)	0.4757	0.0000	0.00000	0.0291	0.05441
Coarse Sand	3,364 (No. 6)	0.3364	0.0002	0.00061	0.0273	0.07044
	2,000 (No. 10)	0.2000	0.0014	0.00563	0.0290	0.11721
Medium Sand	1414 (No. 14)	0.1414	0.0080	0.04900	0.0250	0.15346
	1000 (No. 18)	0.1000	0.0310	0.26882	0.0255	0.22157
	707 (No. 25)	0.0707	0.2047	2.50965	0.0316	0.38692
	500 (No. 35)	0.0500	0.1905	3.30239	0.0301	0.52265
	420 (No. 40)	0.0420	0.0179	0.39503	0.0160	0.35331
Fine Sand	354 (No. 45)	0.0354	0.2543	6.68161	0.0360	0.94557
	250 (No. 60)	0.0250	0.1320	4.57056	0.0559	1.93437
	177 (No. 80)	0.0177	0.0570	2.78892	0.0507	2.48258
	125 (No. 120)	0.0125	0.0024	0.16480	0.0039	0.26810
	74 (No. 200)	0.0074	0.0464	5.04423	0.0608	6.61258
Silt	53 (No. 270)	0.0053	0.0149	2.45145	0.0863	14.15296
	37 (No. 400)	0.0037	0.0095	2.19690	0.1748	40.63018
Clay	18 (assumed)	0.0018	0.0300	12.37243	0.2455	101.30390
		Sum	1.00	42.802	1.00	170.294
		Estimated Maximum k (cm/sec)		5.19E-02		3.28E-03
		Estimated Median k (cm/sec)		2.23E-02		1.41E-03
		Estimated Minimum k (cm/sec)		7.37E-03		4.65E-04
		% Gravel	0.0		10.2	
		% Sand	94.6		39.2	
		% Silt	2.4		26.1	
		% Clay	3.0		24.6	

Notes:

1. Kozeny-Carman Equation:

$$k = [\Theta^3/(1-\Theta)^2]*(1.99 \times 10^4)/\{(\Sigma[f_i/(d_{li}^{0.404} \times d_{si}^{0.595})])^2 * SF^2\}$$

where Θ = total porosity

1.99×10^4 = constant incorporating unit weight and viscosity of water and the empirical Kozeny-Carmon coefficient (1/cm-sec)

f_i = fraction of particles retained on the smaller sieve of adjacent sieve pairs (dimensionless)

d_{li} = diameter of larger sieve in pair (cm)

d_{si} = diameter of smaller sieve in pair (cm)

SF = grain shape factor (dimensionless)

3. Estimated shape factors:

Rounded	6.1
Median	6.25
Worn	6.4

4. Estimated porosities:

Maximum	0.40
Median	0.33
Minimum	0.25

Table G-12f

Estimated Hydraulic Conductivity Based On Grain Size Analyses
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Particle Type	Screen Size (microns)	Screen Size (cm)	MW-338 (47 to 48 feet bgs)		MW-338 (54 to 55 feet bgs)	
			Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$
Coarse Gravel	1"	2.5002	0.0000	–	0.0000	–
Fine Gravel	½"	1.2501	0.0000	0.00000	0.0000	0.00000
	3/8"	0.9500	0.0000	0.00000	0.0000	0.00000
	1/4"	0.6351	0.0000	0.00000	0.0000	0.00000
	4,757 (No. 4)	0.4757	0.0000	0.00000	0.0000	0.00000
Coarse Sand	3,364 (No. 6)	0.3364	0.0000	0.00000	0.0000	0.00000
	2,000 (No. 10)	0.2000	0.0000	0.00000	0.0008	0.00306
Medium Sand	1414 (No. 14)	0.1414	0.0002	0.00111	0.0002	0.00136
	1000 (No. 18)	0.1000	0.0013	0.01146	0.0010	0.00847
	707 (No. 25)	0.0707	0.0070	0.08606	0.0039	0.04768
	500 (No. 35)	0.0500	0.0020	0.03502	0.0102	0.17697
	420 (No. 40)	0.0420	0.0017	0.03781	0.0059	0.13084
Fine Sand	354 (No. 45)	0.0354	0.0033	0.08778	0.0353	0.92816
	250 (No. 60)	0.0250	0.0121	0.42058	0.0660	2.28433
	177 (No. 80)	0.0177	0.0241	1.18000	0.0814	3.98620
	125 (No. 120)	0.0125	0.0102	0.70436	0.0290	2.00602
	74 (No. 200)	0.0074	0.0825	8.97447	0.3269	35.56782
Silt	53 (No. 270)	0.0053	0.2079	34.09868	0.2737	44.88687
	37 (No. 400)	0.0037	0.2613	60.73620	0.0977	22.70056
Clay	18 (assumed)	0.0018	0.3863	159.39871	0.0681	28.09454
		Sum	1.00	265.772	1.00	140.823
		Estimated Maximum k (cm/sec)		1.35E-03		4.79E-03
		Estimated Median k (cm/sec)		5.77E-04		2.06E-03
		Estimated Minimum k (cm/sec)		1.91E-04		6.81E-04
		% Gravel	0.0		0.0	
		% Sand	14.5		56.1	
		% Silt	46.9		37.1	
		% Clay	38.6		6.8	

Notes:

1. Kozeny-Carman Equation:

$$k = [\Theta^3/(1-\Theta)^2]*(1.99 \times 10^4)/\{(\Sigma[f_i/(d_{li}^{0.404} \times d_{si}^{0.595})])^2 * SF^2\}$$

where Θ = total porosity

1.99×10^4 = constant incorporating unit weight and viscosity of water and the empirical Kozeny-Carmon coefficient (1/cm-sec)

f_i = fraction of particles retained on the smaller sieve of adjacent sieve pairs (dimensionless)

d_{li} = diameter of larger sieve in pair (cm)

d_{si} = diameter of smaller sieve in pair (cm)

SF = grain shape factor (dimensionless)

3. Estimated shape factors:

Rounded	6.1
Median	6.25
Worn	6.4

4. Estimated porosities:

Maximum	0.40
Median	0.33
Minimum	0.25

Table G-12f

Estimated Hydraulic Conductivity Based On Grain Size Analyses
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Particle Type	Screen Size (microns)	Screen Size (cm)	MW-340 (47 to 47.5 feet bgs)		MW-341 (90 to 91 feet bgs)	
			Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$
Coarse Gravel	1"	2.5002	0.0000	–	0.0000	–
Fine Gravel	½"	1.2501	0.0000	0.00000	0.0044	0.00266
	3/8"	0.9500	0.0000	0.00000	0.0179	0.01685
	1/4"	0.6351	0.0000	0.00000	0.0555	0.07421
	4,757 (No. 4)	0.4757	0.0000	0.00000	0.0278	0.05196
Coarse Sand	3,364 (No. 6)	0.3364	0.0000	0.00000	0.0583	0.15060
	2,000 (No. 10)	0.2000	0.0004	0.00145	0.0791	0.31989
Medium Sand	1414 (No. 14)	0.1414	0.0002	0.00146	0.0536	0.32871
	1000 (No. 18)	0.1000	0.0005	0.00414	0.0667	0.57834
	707 (No. 25)	0.0707	0.0009	0.01097	0.0984	1.20639
	500 (No. 35)	0.0500	0.0016	0.02689	0.0713	1.23574
	420 (No. 40)	0.0420	0.0037	0.08183	0.1218	2.69447
Fine Sand	354 (No. 45)	0.0354	0.0176	0.46326	0.0991	2.60262
	250 (No. 60)	0.0250	0.0756	2.61872	0.1072	3.71272
	177 (No. 80)	0.0177	0.1027	5.02845	0.0923	4.51843
	125 (No. 120)	0.0125	0.0166	1.14999	0.0094	0.65155
	74 (No. 200)	0.0074	0.0896	9.75401	0.0308	3.35097
Silt	53 (No. 270)	0.0053	0.1386	22.72767	0.0032	0.52255
	37 (No. 400)	0.0037	0.2320	53.93411	0.0012	0.27353
Clay	18 (assumed)	0.0018	0.3199	132.00768	0.0022	0.88825
		Sum	1.00	227.811	1.00	23.180
		Estimated Maximum k (cm/sec)		1.83E-03		1.77E-01
		Estimated Median k (cm/sec)		7.86E-04		7.59E-02
		Estimated Minimum k (cm/sec)		2.60E-04		2.51E-02
		% Gravel	0.0		10.6	
		% Sand	30.9		88.8	
		% Silt	37.1		0.4	
		% Clay	32.0		0.2	

Notes:

1. Kozeny-Carman Equation:

$$k = [\Theta^3/(1-\Theta)^2]*(1.99 \times 10^4)/\{(\Sigma[f_i/(d_{li}^{0.404} \times d_{si}^{0.595})])^2 * SF^2\}$$

where Θ = total porosity

1.99×10^4 = constant incorporating unit weight and viscosity of water and the empirical Kozeny-Carmon coefficient (1/cm-sec)

f_i = fraction of particles retained on the smaller sieve of adjacent sieve pairs (dimensionless)

d_{li} = diameter of larger sieve in pair (cm)

d_{si} = diameter of smaller sieve in pair (cm)

SF = grain shape factor (dimensionless)

3. Estimated shape factors:

Rounded	6.1
Median	6.25
Worn	6.4

4. Estimated porosities:

Maximum	0.40
Median	0.33
Minimum	0.25

Table G-12f

Estimated Hydraulic Conductivity Based On Grain Size Analyses
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Particle Type	Screen Size (microns)	Screen Size (cm)	MW-341 (102 to 103 feet bgs)		MW-343 (77 to 78 feet bgs)	
			Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$	Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$
Coarse Gravel	1"	2.5002	0.0000	–	0.0409	–
Fine Gravel	½"	1.2501	0.0053	0.00321	0.2721	0.16454
	3/8"	0.9500	0.0000	0.00000	0.1223	0.11525
	1/4"	0.6351	0.0000	0.00000	0.1472	0.19690
	4,757 (No. 4)	0.4757	0.0002	0.00037	0.0674	0.12604
Coarse Sand	3,364 (No. 6)	0.3364	0.0000	0.00000	0.0601	0.15525
	2,000 (No. 10)	0.2000	0.0022	0.00891	0.0604	0.24425
Medium Sand	1414 (No. 14)	0.1414	0.0006	0.00338	0.0323	0.19836
	1000 (No. 18)	0.1000	0.0019	0.01649	0.0245	0.21291
	707 (No. 25)	0.0707	0.0052	0.06361	0.0189	0.23168
	500 (No. 35)	0.0500	0.0156	0.27008	0.0151	0.26194
	420 (No. 40)	0.0420	0.0177	0.39255	0.0052	0.11493
Fine Sand	354 (No. 45)	0.0354	0.0571	1.49924	0.0167	0.43770
	250 (No. 60)	0.0250	0.2379	8.23857	0.0278	0.96332
	177 (No. 80)	0.0177	0.2790	13.65437	0.0247	1.21099
	125 (No. 120)	0.0125	0.1032	7.14174	0.0043	0.29703
	74 (No. 200)	0.0074	0.1560	16.96860	0.0276	3.00315
Silt	53 (No. 270)	0.0053	0.0598	9.81596	0.0104	1.71296
	37 (No. 400)	0.0037	0.0485	11.27664	0.0072	1.67394
Clay	18 (assumed)	0.0018	0.0099	4.06816	0.0147	6.05892
		Sum	1.00	73.422	1.00	17.380
		Estimated Maximum k (cm/sec)		1.76E-02		3.15E-01
		Estimated Median k (cm/sec)		7.57E-03		1.35E-01
		Estimated Minimum k (cm/sec)		2.50E-03		4.47E-02
		% Gravel	0.6		65.0	
		% Sand	87.6		31.8	
		% Silt	10.8		1.8	
		% Clay	1.0		1.5	

Notes:

1. Kozeny-Carman Equation:

$$k = [\Theta^3/(1-\Theta)^2]*(1.99 \times 10^4)/\{(\Sigma[f_i/(d_{li}^{0.404} \times d_{si}^{0.595})])^2 * SF^2\}$$

where Θ = total porosity

1.99×10^4 = constant incorporating unit weight and viscosity of water and the empirical Kozeny-Carmon coefficient (1/cm-sec)

f_i = fraction of particles retained on the smaller sieve of adjacent sieve pairs (dimensionless)

d_{li} = diameter of larger sieve in pair (cm)

d_{si} = diameter of smaller sieve in pair (cm)

SF = grain shape factor (dimensionless)

3. Estimated shape factors:

Rounded	6.1
Median	6.25
Worn	6.4

4. Estimated porosities:

Maximum	0.40
Median	0.33
Minimum	0.25

Table G-12f

Estimated Hydraulic Conductivity Based On Grain Size Analyses
American Linen Supply Co Dexter Ave Site
700 Dexter Avenue North, Seattle, Washington

Particle Type	Screen Size (microns)	Screen Size (cm)	MW-343 (103 to 104 feet bgs)	
			Frac Retained	$f_i/(d_{li}^{0.404} \times d_{si}^{0.595})$
Coarse Gravel	1"	2.5002	0.0284	–
Fine Gravel	½"	1.2501	0.0876	0.05298
	3/8"	0.9500	0.0505	0.04759
	1/4"	0.6351	0.0722	0.09660
	4,757 (No. 4)	0.4757	0.0505	0.09437
Coarse Sand	3,364 (No. 6)	0.3364	0.0478	0.12331
	2,000 (No. 10)	0.2000	0.0544	0.22006
Medium Sand	1414 (No. 14)	0.1414	0.0547	0.33532
	1000 (No. 18)	0.1000	0.0518	0.44944
	707 (No. 25)	0.0707	0.0959	1.17596
	500 (No. 35)	0.0500	0.0725	1.25717
	420 (No. 40)	0.0420	0.0460	1.01735
Fine Sand	354 (No. 45)	0.0354	0.0670	1.76166
	250 (No. 60)	0.0250	0.0814	2.81793
	177 (No. 80)	0.0177	0.0417	2.03941
	125 (No. 120)	0.0125	0.0156	1.07831
	74 (No. 200)	0.0074	0.0378	4.11789
Silt	53 (No. 270)	0.0053	0.0167	2.73992
	37 (No. 400)	0.0037	0.0136	3.17143
Clay	18 (assumed)	0.0018	0.0139	5.72787
		Sum	1.00	28.325
		Estimated Maximum k (cm/sec)		1.19E-01
		Estimated Median k (cm/sec)		5.08E-02
		Estimated Minimum k (cm/sec)		1.68E-02
		% Gravel	28.9	
		% Sand	66.7	
		% Silt	3.0	
		% Clay	1.4	

Notes: See previous page for notes.