

APPENDIX G
EnviroBlend® SDS

Issue Date 02-Dec-2014

Revision Date 01-12-2022

Version 1

1. IDENTIFICATION OF THE SUBSTANCE/PREPARATION AND OF THE COMPANY/UNDERTAKING

Product identifier

Product Name ENVIROBLEND® CS

Other means of identification

Product Code ENVIROBLEND® CS

Synonyms None

Recommended use of the chemical and restrictions on use

Recommended Use A specialty blend of magnesium oxide, magnesium hydroxide used for heavy metals remediation.

Uses advised against No information available

Details of the supplier of the safety data sheet

Manufacturer Address

Premier Magnesia, LLC, 75 Giles Place, Waynesville, NC 28786

Emergency telephone number

Company Phone Number 828-452-4784

24 Hour Emergency Phone Number Chemtrec 1-800-424-9300

Emergency Telephone Chemtrec 1-800-424-9300

2. HAZARDS IDENTIFICATION

Classification

OSHA Regulatory Status

Product dust is classified as a "nuisance particulate, not otherwise regulated" as specified by ACGHI and OSHA. The excessive, long-term inhalation of mineral dusts may contribute to the development of industrial bronchitis, reduced breathing capacity, and may lead to the increased susceptibility to lung disease. Contact with water may cause product to swell, generate some heat and burst its container. Low toxicity.

Not a dangerous substance or mixture according to the Globally Harmonized System (GHS)

Label elements

Emergency Overview

The product contains no substances which at their given concentration, are considered to be hazardous to health

Appearance Fine powder to fine granular

Physical state Solid

Odor Odorless

Causes mild irritation to the eyes

Low toxicity by skin contact.

Chronic overexposure by inhalation of airborne particulate may irritate upper respiratory system as well as the throat.

Ingestion is an unlikely route of exposure. If ingested in large amounts it may cause irritation, nausea, vomiting, diarrhea, abdominal pain, black stool, pink urine, coma and possibly death.

Hazards not otherwise classified (HNOC)

Other Information

Unknown Acute Toxicity

100% of the mixture consists of ingredient(s) of unknown toxicity

3. COMPOSITION/INFORMATION ON INGREDIENTS

Chemical Name	CAS No.	Weight-%	Trade Secret
Magnesium Oxide	1309-48-4	70	
Magnesium Hydroxide	1309-42-8	30	

4. FIRST AID MEASURES

First aid measures

Eye contact	Rinse thoroughly with plenty of water, also under the eyelids.
Skin Contact	Wash with soap and water. Low toxicity by skin contact.
Inhalation	Move victim to fresh air. If breathing has stopped, give artificial respiration. Get medical attention immediately.
Ingestion	Ingestion is an unlikely route of exposure. If ingested in sufficient quantity and victim is conscious, give 1-2 glasses of water or milk. Never give anything by mouth to an unconscious person. Leave decision to induce vomiting to qualified medical personnel, since particles may be aspirated into the lungs. Seek immediate medical attention.

Most important symptoms and effects, both acute and delayed

Symptoms No information available.

Indication of any immediate medical attention and special treatment needed

Note to physicians Treat symptomatically.

5. FIRE-FIGHTING MEASURES

Suitable extinguishing media

Use extinguishing measures that are appropriate to local circumstances and the surrounding environment.

Unsuitable extinguishing media Water reacts with magnesium oxide producing magnesium hydroxide and heat. Do not allow water to get inside containers: reaction with water will cause product to swell, generate heat, and burst its container. If contact is unavoidable, use sufficient water to safely absorb the heat that may be generated.

Specific hazards arising from the chemical

No information available.

Explosion data

Sensitivity to Mechanical Impact None.

Sensitivity to Static Discharge None.

Protective equipment and precautions for firefighters

Firefighters should wear NIOSH approved, positive pressure, self-contained breathing apparatus and full protective clothing when appropriate.

6. ACCIDENTAL RELEASE MEASURES

Personal precautions, protective equipment and emergency procedures

Personal precautions Ensure adequate ventilation, especially in confined areas.

Environmental precautions

Environmental precautions See Section 12 for additional ecological information.

Methods and material for containment and cleaning up

Methods for containment Prevent further leakage or spillage if safe to do so.

Methods for cleaning up Carefully clean up and place material into a suitable container, being careful to avoid creating excessive dust. If conditions warrant, clean up personnel should wear approved respiratory protection, gloves and goggles to prevent irritation from contact and/or inhalation.

7. HANDLING AND STORAGE

Precautions for safe handling

Advice on safe handling Use personal protective equipment as required.

Conditions for safe storage, including any incompatibilities

Storage Conditions Keep container tightly closed in a dry and well-ventilated place. Avoid generation of dust. Do not allow water to get inside containers; reaction with water will cause product to swell, generate heat and burst its container. Exposed, unprotected magnesium oxide will absorb moisture and carbon dioxide from the air.

Incompatible materials Magnesium Oxide component is soluble in aqueous acids generating heat and steam; violent reaction or ignition with interhalogens (e.g., bromine pentafluoride; chlorine trifluoride). Incandescent reaction with phosphorus pentachloride.

8. EXPOSURE CONTROLS/PERSONAL PROTECTION

Control parameters

Exposure Guidelines This product, as supplied, does not contain any hazardous materials with occupational exposure limits established by the region specific regulatory bodies.

Chemical Name	ACGIH TLV	OSHA PEL	NIOSH IDLH
Magnesium Oxide 1309-48-4	TWA: 10 mg/m ³ inhalable fraction	TWA: 15 mg/m ³ fume, total particulate (vacated) TWA: 10 mg/m ³ fume and total particulate	IDLH: 750 mg/m ³ fume

NIOSH IDLH Provide workers with NIOSH approved respirators in accordance with requirements of 29 CFR 1910. 134 for level of exposure incurred.

Appropriate engineering controls

Engineering Controls Provide sufficient ventilation, in both volume and air flow patterns to control mist/dust concentrations below allowable exposure limits. Showers. Eyewash stations.

Individual protection measures, such as personal protective equipment

Eye/face protection Avoid contact with eyes. The use of eye protection is recommended.

Skin and body protection The use of eye protection, gloves and long sleeve clothing is recommended.

Respiratory protection Provide workers with NIOSH approved respirators in accordance with requirements of 29 CFR 1910. 134 for level of exposure incurred.

General Hygiene Considerations Wash hands thoroughly after handling.

9. PHYSICAL AND CHEMICAL PROPERTIES

Information on basic physical and chemical properties

Physical state	Solid	Odor	Odorless
Appearance	Fine powder to fine granular	Odor threshold	No information available
Color	Brownish		

<u>Property</u>	<u>Values</u>	<u>Remarks</u>	<u>Method</u>
pH	10-11		
Melting point/freezing point	Melting pt >2100 °C Melting pt >3800 °F		
Boiling point / boiling range	No information available		
Flash point	No information available		
Evaporation rate	Not Applicable		
Flammability (solid, gas)	No information available		
Flammability Limit in Air			
Upper flammability limit:	No information available		
Lower flammability limit:	No information available		
Vapor pressure	No information available		
Vapor density	No information available		
Specific Gravity	3.56 g/cc		
Water solubility	Slight <1%		
Solubility in other solvents	No information available		
Partition coefficient	No information available		
Autoignition temperature	No information available		
Decomposition temperature	No information available		
Kinematic viscosity	No information available		
Dynamic viscosity	No information available		
Explosive properties	No information available		
Oxidizing properties	No information available		

Other Information

Softening point	No information available
Molecular weight	No information available
VOC Content (%)	No information available
Density	No information available
Bulk density	70-80lb/ft3

10. STABILITY AND REACTIVITY

Reactivity

No data available

Chemical stability

Stable under recommended storage conditions.

Possibility of Hazardous Reactions

None under normal processing.

Hazardous polymerization

Hazardous polymerization does not occur.

Conditions to avoid

Extremes of temperature and direct sunlight.

Incompatible materials

Magnesium Oxide component is soluble in aqueous acids generating heat and steam; violent reaction or ignition with interhalogens (e.g., bromine pentafluoride; chlorine trifluoride). Incandescent reaction with phosphorus pentachloride.

Hazardous Decomposition Products

Heat and steam.

11. TOXICOLOGICAL INFORMATION

Information on likely routes of exposure

Product Information	Magnesium Oxide # 1309-48-4 Magnesium Hydroxide #1309-42-8 Product does not present an acute toxicity hazard based on known or supplied information.
Inhalation	Inhalation of fume (not MgO dust particulate) produced upon decomposition of magnesium compounds can produce a febrile reaction and leukocytosis in humans.
Eye contact	Irritating to eyes.
Skin Contact	Low toxicity by skin contact.
Ingestion	Ingestion is an unlikely route of exposure. If ingested in large amounts it may cause irritation, nausea, vomiting, diarrhea, abdominal pain, black stool, pink urine, coma and possibly death.

Chemical Name	Oral LD50	Dermal LD50	Inhalation LC50
Magnesium Hydroxide 1309-42-8	= 8500 mg/kg (Rat)	-	-

Information on toxicological effects

Symptoms No information available.

Delayed and immediate effects as well as chronic effects from short and long-term exposure

Sensitization	No information available.
Germ cell mutagenicity	No information available.
Carcinogenicity	No information available.
Reproductive toxicity	No information available.
STOT - single exposure	No information available.
STOT - repeated exposure	No information available.
Aspiration hazard	No information available.

Numerical measures of toxicity - Product Information

Unknown Acute Toxicity 100% of the mixture consists of ingredient(s) of unknown toxicity

12. ECOLOGICAL INFORMATION

Ecotoxicity

No data available on any adverse effects of this material on the environment

100% of the mixture consists of components(s) of unknown hazards to the aquatic environment

Persistence and degradability

No information available.

Bioaccumulation

No information available.

Other adverse effects

No information available

13. DISPOSAL CONSIDERATIONS

Waste treatment methods

Disposal of wastes This product does not exhibit any characteristics of a hazardous waste. The product is suitable for landfill disposal. Follow all applicable federal, state and local regulations for safe disposal.

Contaminated packaging Do not reuse container.

14. TRANSPORT INFORMATION

DOT Not regulated Not regulated by DOT as a hazardous material. No hazard class, label or placard required, no UN or NA number assigned.

15. REGULATORY INFORMATION

International Inventories

Chemical Name	Complies							
	TSCA	DSL/NDSL	EINECS/ELINCS	ENCS	IECSC	KECL	PICCS	AICS
Magnesium Oxide	X	X	X	X	X	X	X	X
Magnesium Hydroxide	X	X	X	X	X	X	X	X

X - Listed

- TSCA - United States Toxic Substances Control Act Section 8(b) Inventory
- DSL/NDSL - Canadian Domestic Substances List/Non-Domestic Substances List
- EINECS/ELINCS - European Inventory of Existing Chemical Substances/European List of Notified Chemical Substances
- ENCS - Japan Existing and New Chemical Substances
- IECSC - China Inventory of Existing Chemical Substances
- KECL - Korean Existing and Evaluated Chemical Substances
- PICCS - Philippines Inventory of Chemicals and Chemical Substances
- AICS - Australian Inventory of Chemical Substances

US Federal Regulations

SARA 313

This product does not contain any substances reportable under Sections 302, 304 or 313. Sections 311 and 312 do apply. (Routine Reporting and Chemical Inventories)

SARA 311/312 Hazard Categories

Acute health hazard	No
Chronic Health Hazard	No
Fire hazard	No
Sudden release of pressure hazard	No
Reactive Hazard	No

CWA (Clean Water Act)

This product does not contain any substances regulated as pollutants pursuant to the Clean Water Act (40 CFR 122.21 and 40 CFR 122.42)

CERCLA

This material, as supplied, does not contain any substances regulated as hazardous substances under the Comprehensive Environmental Response Compensation and Liability Act (CERCLA) (40 CFR 302) or the Superfund Amendments and Reauthorization Act (SARA) (40 CFR 355). There may be specific reporting requirements at the local, regional, or state level pertaining to releases of this material

US State Regulations

California Proposition 65

This product does not contain chemicals known to the State of California to cause cancer, birthdefects or other reproductive toxins.

U.S. State Right-to-Know Regulations

Chemical Name	New Jersey	Massachusetts	Pennsylvania
Magnesium Oxide 1309-48-4	X	X	X

U.S. EPA Label Information

EPA Pesticide Registration Number Not Applicable

16. OTHER INFORMATION

NFPA	Health hazards 1	Flammability 0	Instability 0	Physical and Chemical Properties - Personal protection X
HMIS	Health hazards 0	Flammability 0	Physical hazards 0	

Issue Date 02-Dec-2014

Revision Date 01-12-2022

Revision Note

No information available

Disclaimer

The information provided in this Safety Data Sheet is correct to the best of our knowledge, information and belief at the date of its publication. The information given is designed only as a guidance for safe handling, use, processing, storage, transportation, disposal and release and is not to be considered a warranty or quality specification. The information relates only to the specific material designated and may not be valid for such material used in combination with any other materials or in any process, unless specified in the text.

End of Safety Data Sheet

APPENDIX H
Drone Photo Log

**FORMER SPOKANE GUN CLUB
LIBERTY LAKE, WASHINGTON
File No. 0202349-002
Date Photographs Taken: October 2024 to May 2025**



Photo 01: Excavation aerial taken October 10, 2024, looking northwest.

**FORMER SPOKANE GUN CLUB
LIBERTY LAKE, WASHINGTON
File No. 0202349-002
Date Photographs Taken: October 2024 to May 2025**



Photo 02: Excavation aerial taken October 28, 2024, looking northwest.

**FORMER SPOKANE GUN CLUB
LIBERTY LAKE, WASHINGTON
File No. 0202349-002
Date Photographs Taken: October 2024 to May 2025**



Photo 03: Excavation aerial taken November 7, 2024, looking northwest.

FORMER SPOKANE GUN CLUB

LIBERTY LAKE, WASHINGTON

File No. 0202349-002

Date Photographs Taken: October 2024 to May 2025



Photo 04: Stockpile aerial taken November 7, 2024, looking southeast.

**FORMER SPOKANE GUN CLUB
LIBERTY LAKE, WASHINGTON
File No. 0202349-002**

Date Photographs Taken: October 2024 to May 2025



Photo 05: Excavation aerial taken December 5, 2024, looking northwest.

**FORMER SPOKANE GUN CLUB
LIBERTY LAKE, WASHINGTON
File No. 0202349-002
Date Photographs Taken: October 2024 to May 2025**



Photo 06: Repository aerial taken December 5, 2024, looking northwest.

FORMER SPOKANE GUN CLUB
LIBERTY LAKE, WASHINGTON
File No. 0202349-002

Date Photographs Taken: October 2024 to May 2025



Photo 07: Excavation aerial taken January 8, 2025, looking northwest.

**FORMER SPOKANE GUN CLUB
LIBERTY LAKE, WASHINGTON
File No. 0202349-002
Date Photographs Taken: October 2024 to May 2025**



Photo 08: Repository aerial taken January 8, 2025, looking northwest.

FORMER SPOKANE GUN CLUB
LIBERTY LAKE, WASHINGTON
File No. 0202349-002

Date Photographs Taken: October 2024 to May 2025



Photo 09: Excavation aerial taken January 23, 2025, looking northwest.

**FORMER SPOKANE GUN CLUB
LIBERTY LAKE, WASHINGTON
File No. 0202349-002
Date Photographs Taken: October 2024 to May 2025**



Photo 10: Repository aerial taken January 23, 2025, looking northwest.

FORMER SPOKANE GUN CLUB
LIBERTY LAKE, WASHINGTON
File No. 0202349-002

Date Photographs Taken: October 2024 to May 2025



Photo 11: Excavation aerial taken February 13, 2025, looking northwest.

**FORMER SPOKANE GUN CLUB
LIBERTY LAKE, WASHINGTON
File No. 0202349-002
Date Photographs Taken: October 2024 to May 2025**



Photo 12: Repository aerial taken February 13, 2025, looking northwest.

FORMER SPOKANE GUN CLUB
LIBERTY LAKE, WASHINGTON
File No. 0202349-002

Date Photographs Taken: October 2024 to May 2025



Photo 13: Excavation aerial taken March 26, 2025, looking northwest.

**FORMER SPOKANE GUN CLUB
LIBERTY LAKE, WASHINGTON
File No. 0202349-002**

Date Photographs Taken: October 2024 to May 2025



Photo 14: Repository aerial taken March 26, 2025, looking northwest.

**FORMER SPOKANE GUN CLUB
LIBERTY LAKE, WASHINGTON
File No. 0202349-002
Date Photographs Taken: October 2024 to May 2025**




Photo 15: Excavation aerial taken May 14, 2025, looking northwest.

**FORMER SPOKANE GUN CLUB
LIBERTY LAKE, WASHINGTON
File No. 0202349-002
Date Photographs Taken: October 2024 to May 2025**



Photo 16: Repository aerial taken May 14, 2025, looking northwest.

APPENDIX I
Certificates of Disposal

W Facility
 1820 ... Road
 Waste Management 9022

Reprint
 Ticket# /43195
 Ph: (509)244-0151

Customer Name HALMBROCKS INC HALMB CONS[®] Carrier HALMB HALMB CONSTRUCTION
 Ticket Date 03/04/2025 Vehicle# 1
 Payment Type Credit Account Container
 Manual Ticket# Driver
 Route Check#
 Hauling Ticket# Billing# 0000084
 Destination Grid
 Manifest 119570WA
 Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
 Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
 PO# 119570WA

Time	Scale	Operator	Inbound	Gross	105500 lb
In: 03/04/2025 12:41:46	Scale1	amaruric		Tare	46260 lb
Out: 03/04/2025 13:00:10	Scale1	amaruric		Net	59240 lb
				Tons	29.62

Comments

Product	UOM	Qty	UOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons-	100	29.62	Tons				SPOKANE
2 ENRPCY-Energy Surcharge	100						SPOKANE
3 WWM-P-Waste Water Manag	100						SPOKANE
4 SRHD1-Spokane Regional	100	29.62	Tons				SPOKANE

Total Tax/Fees
 Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.

WASTE MANAGEMENT
 Facility
 1820 ...ham Road
 9022

Reprint
 Ticket# 713180
 Ph: (509)244-0151

Customer Name HALMECONSINC HALME CONS Carrier HALME HALME CONSTRUCTION
 Ticket Date 03/04/2025 Vehicle# RICK
 Payment Type Credit Account Container
 Manual Ticket# Driver RICK
 Route Check#
 Hauling Ticket# Billing# 0000084
 Destination Grid
 Manifest 119570WA
 Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
 Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
 PO# 119570WA

Time	Scale	Operator	Inbound	Gross	118700 lb
In 03/04/2025 10:53:21	Scale1	amanuria		Tare	46360 lb
Out 03/04/2025 11:08:00	Scale1	amanuria		Net	72340 lb
				Tons	36.17

Comments

Product	UOM	Qty	UOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons-	100	36.17	Tons				SPOKANE
2 ENERGY-Energy Surcharge	100		\$				SPOKANE
3 WWM-P-Waste Water Manag	100		\$				SPOKANE
4 SRHD1-Spokane Regional	100	36.17	Tons				SPOKANE

Total Tax/Fees
 Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.

W Facility
 1820 Ham Road
 Waste Management 9022

Reprint
 Ticket# 743217
 Ph: (509)244-0151

Customer Name HALMECONSINC HALME CONS Carrier HALME HALME CONSTRUCTION
 Ticket Date 03/04/2025 Vehicle# 1
 Payment Type Credit Account Container
 Manual Ticket# Driver
 Route Check#
 Hauling Ticket# Billing# 0000084
 Destination Grid
 Manifest 119570WA
 Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
 Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
 PO# 119570WA

Time	Scale	Operator	Inbound	Gross	
In 03/04/2025 14:36:07	Scale1	amanurin		107360 lb	
Out 03/04/2025 14:49:34	Scale1	amanurin		Tare 46120 lb	
				Net 61240 lb	
				Tons 30.62	

Comments

Product	Rate	Qty	UOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons- 100		30.62	Tons				SPOKANE
2 ENERGY-Energy Surcharge 100							SPOKANE
3 WWM-P-Waste Water Manag 100							SPOKANE
4 SRHD1-Spokane Regional 100		30.62	Tons				SPOKANE

Total Tax/Fees
 Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.

W Facility
 1820 ... Road
 Waste Management 9022

Reprint
 Ticket# 743235
 Ph: (509)244-0151

Customer Name HALMECONS INC HALME CONS Carrier HALME HALME CONSTRUCTION
 Ticket Date 03/05/2025 Vehicle# 1
 Payment Type Credit Account Container
 Manual Ticket# Driver
 Route Check#
 Hauling Ticket# Billing# 0000084
 Destination Grid
 Manifest 119570wa
 Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
 Generator CVSD GUN-19615 CVSD GUN CLUB 19615 F SPRAGUE AVE LIBERTY LAKE
 PO# 119570wa

Time	Scale	Operator	Inbound	Gross	
In 03/05/2025 07:49:59	Scales	amahirin		97880 lb	Tare
Out 03/05/2025 08:05:31	Scales	amahirin		46420 lb	Net
				51460 lb	Tons
				25.73	

Comments

Product	UOM	Qty	UOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons-	100	25.73	Tons				SPOKANE
2 ENERGY-Energy Surcharge	100						SPOKANE
3 WWM-P-Waste Water Manag	100						SPOKANE
4 SR01-Spokane Regional	100	25.73	Tons				SPOKANE

Total Tax/Fees
 Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.

W Facility
 1820 Ham Road
 Waste Management 9022

Reprint
 Ticket# 143254
 Ph: (509) 244-0151

Customer Name HALMECONSINC HALME CONST Carrier HALME HALME CONSTRUCTION
 Ticket Date 03/05/2025 Vehicle# RICK
 Payment Type Credit Account Container
 Manual Ticket# Driver RICK
 Route Check#
 Hauling Ticket# Billing# 0000084
 Destination Grid
 Manifest 119570wa
 Profile 119570WA (LP01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
 Generator CVSD GUN-19615 CVSD SUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
 PO# 119570wa

Time	Scale	Operator	Inbound	Gross	
In 03/05/2025 09:33:04	Scale1	amahiric		101720	lb
Out 03/05/2025 09:45:54	Scale1	amahiric		Tare	46360 lb
				Net	55360 lb
				Tons	27.68

Comments

Product	Code	Qty	UOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons-	100	27.68	Tons				SPOKANE
2 ENERGY-Energy Surcharge	100						SPOKANE
3 WWX-P-Waste Water Manag	100						SPOKANE
4 SRHD1-Spokane Regional	100	27.68	Tons				SPOKANE

Total Tax/Fees
 Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.

W
 Facility
 1820 ... Road
 Medi... 99022

Reprint
 Ticket# /13273
 Ph: (509)244-0151

Customer Name HALMECCONSINC HALME CONST Carrier HALME HALME CONSTRUCTION
 Ticket Date 03/05/2025 Vehicle# RICK
 Payment Type Credit Account Container
 Manual Ticket# Driver RICK
 Route Check#
 Hauling Ticket# Billing# 0000084
 Destination Grid
 Manifest 119570WA
 Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
 Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
 PO# 119570WA

Time	Scale	Operator	Inbound	Gross	
In: 03/05/2025 11:07:54	Scale1	amanurin			110840 lb
Out: 03/05/2025 11:23:47	Scale1	amanurin			46240 lb
				Net	64600 lb
				Tons	32.30

Comments

Product	UOM	Qty	UOM	Rate	Tax/fee	Amount	Origin
1 Spwaste Solid Oth-Tons-	100	32.30	Tons				SPOKANE
2 ENERGY-Energy Surcharge	100						
3 WWM-P-Waste Water Manag	100						
4 SRHD1-Spokane Regional	100	32.30	Tons				

Total Tax/Fees
 Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.

W
 Grant Facility
 1820 Sham Road
 Waste Management 9022

Reprint
 Ticket# 713295
 Ph: (509)244-0151

Customer Name HALNECONSINC HALME CONST Carrier HALME HALME CONSTRUCTION
 Ticket Date 03/05/2025 Vehicle# RICK
 Payment Type Credit Account Container
 Manual Ticket# Driver RICK
 Route Check#
 Hauling Ticket# Billing# 0000084
 Destination Grid
 Manifest 119570wa
 Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
 Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
 PO# 119570wa

Time	Scale	Operator	Inbound	Gross	
In 03/05/2025 12:48:14	Scale1	amahirin		103000	lb
Out 03/05/2025 13:05:18	Scale1	amahirin		Tare	46140 lb
				Net	56860 lb
				Tons	28.43

Comments

Product	LD#	Qty	UOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons-	100	28.43	Tons				SPOKANE
2 ENERGY-Energy Surcharge	100						SPOKANE
3 WWM-P-Waste Water Manag	100						SPOKANE
4 SRHDI-Spokane Regional	100	28.43	Tons				SPOKANE

Total Tax/Fees
 Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.

W Facility
 1820 ...ham Road
 Medi**WASTE MANAGEMENT** 9022

Reprint
 Ticket# 743328
 Ph: (509)244-0151

Customer Name HALMECONSINC HALME CONS# Carrier HALME HALME CONSTRUCTION
 Ticket Date 03/06/2025 Vehicle# RICK
 Payment Type Credit Account Container
 Manual Ticket# Driver RICK
 Route Check#
 Hauling Ticket# Billing# 0000084
 Destination Grid
 Manifest 119570WA
 Profile 119570WA (LF01: BIRSEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
 Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
 PO# 119570WA

Time	Scale	Operator	Inbound	Gross	
In 03/06/2025 01:42:25	Scale1	aranuric			99420 lb
Out 03/06/2025 01:56:39	Scale1	aranuric			46380 lb
					53040 lb
					Tons 26.52

Comments

Product	Rate	Qty	UOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons- 100		26.52	Tons				SPOKANE
2 ENERGY-Energy Surcharge 100							SPOKANE
3 WWM-P-Waste Water Manag 100							SPOKANE
4 SRHDI-Spokane Regional 100		26.52	Tons				SPOKANE

Total Tax/Fees
 Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.

W Facility
 1820 ... Road
 MediWASTE MANAGEMENT 9022

Reprint
 Ticket# /13341
 Ph: (509)244-0151

Customer Name HALMECONS INC HALME CONS? Carrier HALME HALME CONSTRUCTION
 Ticket Date 03/06/2025 Vehicle# RICK
 Payment Type Credit Account Container
 Manual Ticket# Driver RICK
 Route Check#
 Hauling Ticket# Billing# 0000084
 Destination Grid
 Manifest 119570WA
 Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
 Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
 PO# 119570WA

Time	Scale	Operator	Inbound	Gross	99540 lb
In 03/06/2025 09:19:20	Scale1	amahirin		Tare	46300 lb
Out 03/06/2025 09:30:49	Scale1	amahirin		Net	53240 lb
				Tons	26.62

Comments

Product	Unit	Qty	UOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons-	100	26.62	Tons				SPOKANE
2 ENERGY-Energy Surcharge	100						
3 WWM-P-Waste Water Manag	100						
4 SRFD1-Spokane Regional	100	26.62	Tons				

Total Tax/Fees
 Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.


 Facility
 1820 ...ham Road
 MediWASTE MANAGEMENT 9022

Reprint
 Ticket# 743362
 Ph: (509)244-0151

Customer Name HALMECONS INC HALME CONST Carrier HALME HALME CONSTRUCTION
 Ticket Date 03/06/2025 Vehicle# RICK
 Payment Type Credit Account Container
 Manual Ticket# Driver RICK
 Route Check#
 Hauling Ticket# Billing# 0000084
 Destination Grid
 Manifest 119570WA
 Profile 119570WA (LF01: RESSEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
 Generator CVSD GUN-19615 CVSD GUN CILLS 19615 E SPRAGUE AVE LIBERTY LAKE
 PO# 119570WA

Time	Scale	Operator	Inbound	Gross	103780 lb
In 03/06/2025 10:50:34	Scale1	amahurin		Tare	46180 lb
Out 03/06/2025 11:02:39	Scale1	amahurin		Net	57600 lb
				Tons	28.80

Comments

Product	UOM	Qty	JOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons-	100	28.80	Tons				SPOKANE
2 ENERGY-Energy Surcharge	100						SPOKANE
3 WWM-P-Waste Water Manag	100						SPOKANE
4 SRHD1-Spokane Regional	100	28.80	Tons				SPOKANE

Total Tax/Fees
 Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.

WASTE MANAGEMENT
 Grant Facility
 1820 ...ham Road
 Medi... 9022

Reprint
 Ticket# 713382
 Ph: (509)244-0151

Customer Name HALMECONSINC HALME CONST Carrier HALME HALME CONSTRUCTION
 Ticket Date 03/06/2025 Vehicle# RICK
 Payment Type Credit Account Container
 Manual Ticket# Driver RICK
 Route Check#
 Hauling Ticket# Billing# 0000084
 Destination Grid
 Manifest 119570WA
 Profile 119570WA (LF01: MISSEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
 Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGLE AVE LIBERTY LAKE
 PO# 119570WA

Time	Scale	Operator	Inbound	Gross	
In 03/06/2025 12:28:43	Scale1	amahurin		96400 lb	
Out 03/06/2025 12:40:42	Scale1	amahurin		Tare 46060 lb	
				Net 50340 lb	
				Tons 25.17	

Comments

Product	UOM	Qty	UOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons-	100	25.17	Tons				SPOKANE
2 ENERGY-Energy Surcharge	100						SPOKANE
3 WWM-P-Waste Water Manag	100						SPOKANE
4 SRBD1-Spokane Regional	100	25.17	Tons				SPOKANE

Total Tax/Fees
 Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.

WASTE MANAGEMENT
 Facility
 1820 ... Road
 Medi... 9022

Reprint
 Ticket# 743399
 Ph: (509)244-0151

Customer Name HALMECONSINC HALME CONST Carrier HALME HALME CONSTRUCTION
 Ticket Date 03/06/2025 Vehicle# RICK
 Payment Type Credit Account Container
 Manual Ticket# Driver RICK
 Route Check#
 Hauling Ticket# Billing# C000084
 Destination Grid
 Manifest 119570WA
 Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
 Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
 PO# 119570WA

Time	Scale	Operator	Inbound	Gross	
In 03/06/2025 14:09:50	Scale1	amanurin		100740	lb
Out 03/06/2025 14:20:49	Scale1	amanurin		Tare	46000 lb
				Net	54740 lb
				Toss	27.12

Comments

#product	UOM	Qty	UOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons-	100	27.12	Tons				SPOKANE
2 ENERGY-Energy Surcharge	100						SPOKANE
3 WWM-P-Waste Water Manag	100						SPOKANE
4 SRHD1-Spokane Regional	100	27.12	Tons				SPOKANE

Total Tax/Fees
 Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.

W Facility
 1820 Chan Road
 MediWASTE MANAGEMENT 9022

Reprint
 Ticket# 743422
 Ph: (509)244-0151

Customer Name HALMCONSINC HA MK CONS Carrier HALME HALME CONSTRUCTION
 Ticket Date 03/07/2025 Vehicle# RICK
 Payment Type Credit Account Container
 Manual Ticket# Driver RICK
 Route Check#
 Hauling Ticket# Billing# 0000084
 Destination Grid
 Manifest 119570WA
 Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
 Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
 PO# 119570WA

Time	Scale	Operator	Inbound	Gross	
In 03/07/2025 07:49:59	Scale1	amanurin		98160 lb	
Out 03/07/2025 08:01:58	Scale1	amanurin		Tare 46360 lb	
				Net 51800 lb	
				Tons 25.90	

Comments

Product	Rate	Qty	JOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons- 100		25.90	Tons				SPOKANE
2 ENERGY-Energy Surcharge 100							SPOKANE
3 WWM-P-Waste Water Manag 100							SPOKANE
4 SRHD1-Spokane Regional 100		25.90	Tons				SPOKANE

Total Tax/Fees
 Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.

WWM
 Grant Facility
 1820 Cham Road
 Medi WASTE MANAGEMENT 9022

Reprint
 Ticket# 743438
 Ph: (509) 244-0151

Customer Name HALMECONSINC HALME CONS Carrier HALME HALME CONSTRUCTION
 Ticket Date 03/07/2025 Vehicle# RICK
 Payment Type Credit Account Container
 Manual Ticket# Driver RICK
 Route Check#
 Hauling Ticket# Billing# 0000084
 Destination Grid
 Manifest 119570WA
 Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
 Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
 PO# 119570WA

Time	Scale	Operator	Inbound	Gross	
In 03/07/2025 09:21:20	Scale1	AMAHURTN			100180 lb
Out 03/07/2025 09:33:23	Scale1	AMAHURTN		Tare	46260 lb
				Net	53920 lb
				Tons	26.96

Comments

Product	UOM	Qty	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons-	100	26.96				SPOKANE
2 ENERGY-Energy Surcharge	100					SPOKANE
3 WWM-P-Waste Water Manag	100					SPOKANE
4 SRHD1-Spokane Regional	100	26.96				SPOKANE

Total Tax/Fees
 Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.

W Facility
 1820 ...ham Road
 MediWASTE MANAGEMENT 99022

Reprint
 Ticket# 743457
 Ph: (509)244-0151

Customer Name HALMECONSINC HALME CONSTRUCTION Carrier HALME HALME CONSTRUCTION
 Ticket Date 03/07/2025 Vehicle# RICK
 Payment Type Credit Account Container
 Manual Ticker# Driver RICK
 Route Check#
 Hauling Ticket# Billing# 0000084
 Destination Grid
 Manifest 119570WA
 Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
 Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
 PO# 119570WA

Time	Scale	Operator	Inbound	Gross	97260 lb
In 03/07/2025 10:53:38	Scale1	AMAHURTN		Tare	46140 lb
Out 03/07/2025 11:07:35	Scale1	AMAHURTN		Net	51120 lb
				Tons	25.56

Comments

Product	Rate	Qty	UOM	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons- 100		25.56	Tons			SPOKANE
2 ENERGY-Energy Surcharge 100						SPOKANE
3 WWM-P-Waste Water Manag 100						SPOKANE
4 SRHDI-Spokane Regional 100		25.56	Tons			SPOKANE

Total Tax/Fees
 Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.


 Facility
 1820 ...ham Road
 Medi...WASTE MANAGEMENT...9022

Reprint
 Ticket# /43477
 Ph: (509)244-0151

Customer Name HALMECONSINC HALME CONST Carrier HALME HALME CONSTRUCTION
 Ticket Date 03/07/2025 Vehicle# RICK
 Payment Type Credit Account Container
 Manual Ticket# Driver RICK
 Route Check#
 Hauling Ticket# Billing# 0000084
 Destination Grid
 Manifest 1
 Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
 Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
 PO# 1

Time	Scale	Operator	Inbound	Gross	
In 03/07/2025 12:32:06	Scale1	AMAHURTN		100020	lb
Out 03/07/2025 12:44:33	Scale1	AMAHURTN		46060	lb
				53960	lb
					Tons 26.98

Comments

Product	Rate	Qty	UOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons-	100	26.98	Tons				SPOKANE
2 ENERGY-Energy Surcharge	100						SPOKANE
3 WWM-P-Waste Water Manag	100						SPOKANE
4 SPR01-Spokane Regional	100	26.98	Tons				SPOKANE

Total Tax/Fees
 Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.

W Facility
 1820 ...ham Road
 Medi...WASTE MANAGEMENT...9022

Reprint
 Ticket# /13494
 Ph: (509)244-0151

Customer Name HALMECONSINC HALME CONS Carrier HALME HALME CONSTRUCTION
 Ticket Date 03/07/2025 Vehicle# RICK
 Payment Type Credit Account Container
 Manual Ticket# Driver RICK
 Route Check#
 Hauling Ticket# Billing# 0000084
 Destination Grid
 Manifest 119570wa
 Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
 Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
 PO# 119570wa

Time	Scale	Operator	Inbound	Gross	
In 03/07/2025 14:14:2	Scale1	AMARJRTN		99700	lb
Out 03/07/2025 14:26:48	Scale1	AMARJRTN		Tare	45960 lb
				Net	53740 lb
				Tons	26.87

Comments

Product	Rate	Qty	UOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons- 100		26.87	Tons				SPOKANE
2 ENERGY-Energy Surcharge 100							SPOKANE
3 WWM-P-Waste Water Manag 100							SPOKANE
4 SRHD1-Spokane Regional 100		26.87	Tons				SPOKANE

Total Tax/Fees
 Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.

WWM
 Facility
 1820 ... Road
 WASTE MANAGEMENT 9022

Reprint
 Ticket# /43517
 Ph: (509)244-0151

Customer Name HALMECONSINC HALME CONS Carrier HALME HALME CONSTRUCTION
 Ticket Date 03/10/2025 Vehicle# RICK
 Payment Type Credit Account Container
 Manual Ticket# Driver RICK
 Route Check#
 Hauling Ticket# Billing# 0000084
 Destination Grid
 Manifest 119570wa
 Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
 Generator CVSD SUN-19615 CVSD SUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
 PO# 119570wa

Time	Scale	Operator	Inbound	Gross	96760 lb
In 03/10/2025 08:02:13	Scale1	amanurin		Tare	46420 lb
Out 03/10/2025 08:15:53	Scale1	amanurin		Net	50340 lb
				Tons	25.17

Comments

Product	UOM	Qty	UOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons-100	100	25.17	Tons				SPOKANE
2 ENERGY-Energy Surcharge	100						SPOKANE
3 WWM-P-Waste Water Manag	100						SPOKANE
4 SRHD1-Spokane Regional	100	25.17	Tons				SPOKANE

Total Tax/Fees
 Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.

WWM
 Facility
 1820 ... Road
 WASTE MANAGEMENT 9022

Reprint
 Ticket# 743535
 Ph: (509)244-0151

Customer Name HALMECONSINC HALME CONS Carrier HALME HALME CONSTRUCTION
 Ticket Date 03/10/2025 Vehicle# RICK
 Payment Type Credit Account Container
 Manual Ticket# Driver RICK
 Route Check#
 Hauling Ticket# Billing# 0000084
 Destination Grid
 Manifest 119570wa
 Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
 Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
 PO# 119570wa

Time	Scale	Operator	Inbound	Gross	105620 lb
In 03/10/2025 09:38:09	Scale1	amanurin		Tare	46300 lb
Out 03/10/2025 09:51:33	Scale1	amanurin		Net	59320 lb
				Tons	29.66

Comments

Product	UOM	Qty	UOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons-	100	29.66	Tons				SPOKANE
2 ENERGY-Energy Surcharge	100		\$				
3 WWM-P-Waste Water Manag	100		\$				
4 SRHD1-Spokane Regional	100	29.66	Tons				

Total Tax/Fees
 Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.

WWM
 Grant Facility
 18200 Han Road
 Medical Waste Management 9022

Reprint
 Ticket# 743555
 Ph: (509)244-0151

Customer Name HALMECCONSINC HALME CONST Carrier HALME HALME CONSTRUCTION
 Ticket Date 03/10/2025 Vehicle# RICK
 Payment Type Credit Account Container
 Manual Ticket# Driver RICK
 Route Check#
 Hauling Ticket# Billing# 0000084
 Destination Grid
 Manifest 119570wa
 Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
 Generator CVSD SUN-19615 CVSD SUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
 PO# 119570wa

Time	Scale	Operator	Inbound	Gross	
In 03/10/2025 11:11:28	Scale 01	amahurin		100400	lb
Out 03/10/2025 11:23:16	Scale 01	amahurin		Tare	46200 lb
				Net	54200 lb
				Tons	27.10

Comments

Product	UOM	Qty	JOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons- 100		27.10	Tons				SPOKANE
2 ENERGY-Energy Surcharge 100							SPOKANE
3 WWM-P-Waste Water Manag 100							SPOKANE
4 SRHD1-Spokane Regional 100		27.10	Tons				SPOKANE

Total Tax/Fees
 Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.

W Facility
 1820 ... Road
 Medi... 9022

Reprint
 Ticket# 713569
 Ph: (509)244-0151

Customer Name HALMECONSINC HALME CONS
 Ticket Date 03/10/2025
 Payment Type Credit Account
 Manual Ticket#
 Route
 Hauling Ticket#
 Destination
 Manifest 119570WA
 Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
 Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
 PO# 119570WA

Time	Scale	Operator	Inbound	Gross	
In 03/10/2025 12:44:44	Scale1	amarurin		Tare	36260 lb
Out 03/10/2025 12:59:20	Scale1	amarurin		Net	46100 lb
				Tons	50160 lb
					25.08

Comments

Product	UOM	Qty	JOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons- 100		25.08	Tons				SPOKANE
2 ENERGY-Energy Surcharge 100							SPOKANE
3 WWM-P-Waste Water Manag 100							SPOKANE
4 SRHD1-Spokane Regional 100		25.08	Tons				SPOKANE

Total Tax/Fees
 Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.

W Facility
 1820 ...ham Road
 Medi**WASTE MANAGEMENT** 9022

Reprint
 Ticket# 743582
 Ph: (509)244-0151

Customer Name HALMECONS INC HALME CONSR Carrier HALME HALME CONSTRUCTION
 Ticket Date 03/10/2025 Vehicle# RICK
 Payment Type Credit Account Container
 Manual Ticket# Driver RICK
 Route Check#
 Hauling Ticket# Billing# 0000084
 Destination Grid
 Manifest 119570WA
 Profile 119570WA (LF01: WRESEL POPL IMPACTED SOIL AND/OR DEBR S CLEANUP)
 Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
 PO# 119570WA

Time	Scale	Operator	Inbound	Gross	
In 03/10/2025 14:20:30	Scale1	amanurin			97520 lb
Out 03/10/2025 14:32:37	Scale1	amanurin			46020 lb
					Net 51500 lb
					Tons 25.75

Comments

Product	UOM	Qty	UOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons-	100	25.75	Tons				SPOKANE
2 ENERGY-Energy Surcharge	100		*				
3 WWM-P-Waste Water Manag	100		*				
4 SRHD1-Spokane Regional	100	25.75	Tons				

Total Tax/Fees
 Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.

WWM
 Facility
 1820 ... Road
 Waste Management 9022

Reprint
 Ticket# /43616
 Ph: (509)244-0151

Customer Name HALMECONSINC HALME CONST Carrier HALME HALME CONSTRUCTION
 Ticket Date 03/11/2025 Vehicle# RICK
 Payment Type Credit Account Container
 Manual Ticket# Driver RICK
 Route Check#
 Hauling Ticket# Billing# 0000084
 Destination Grid
 Manifest 119570wa
 Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
 Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
 PO# 119570wa

Time	Scale	Operator	Inbound	Gross	Weight
In 03/11/2025 08:03:11	Scale1	amahurin			607320 lb
Out 03/11/2025 08:16:30	Scale1	amahurin			46400 lb
					Net 60920 lb
					Tons 30.46

Comments

Product	UOM	Qty	DOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons-	100	30.46	Tons				SPOKANE
2 ENERGY-Energy Surcharge	100						
3 WWM-P-Waste Water Manag	100						
4 SRHD1-Spokane Regional	100	30.46	Tons				

Total Tax/Fees
 Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.

W
 Graham Road Facility
 1820 S. Graham Road
 Medical Waste Management 99022

Original
 Ticket# 743632
 Ph: (509)244-0151

Customer Name HALMECONSINC HALME CONST Carrier HALME HALME CONSTRUCTION
 Ticket Date 03/11/2025 Vehicle# RICK
 Payment Type Credit Account Container
 Manual Ticket# Driver RICK
 Route Check#
 Hauling Ticket# Billing# 0000084
 Destination Grid
 Manifest 119570WA
 Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
 Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
 PO# 119570WA

Time	Scale	Operator	Inbound	Gross	
In 03/11/2025 09:38:09	Scale1	amahurin		Tare	103720 lb
Out 03/11/2025 09:50:26	Scale1	amahurin		Net	46300 lb
				Tons	57420 lb
					28.71

Comments

Product	LD%	Qty	UOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons-	100	28.71	Tons				SPOKANE
2 ENERGY-Energy Surcharge	100		%				SPOKANE
3 WWM-P-Waste Water Manag	100		%				SPOKANE
4 SRHD1-Spokane Regional	100	28.71	Tons				SPOKANE

Total Tax/Fees
 Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.

W
 Graham Road Facility
 1820 S. Graham Road
 Medical Waste Management 99022

Original
 Ticket# 743649
 Ph: (509)244-0151

Customer Name HALMECONSINC HALME CONST Carrier HALME HALME CONSTRUCTION
 Ticket Date 03/11/2025 Vehicle# RICK
 Payment Type Credit Account Container
 Manual Ticket# Driver RICK
 Route Check#
 Hauling Ticket# Billing# 0000084
 Destination Grid
 Manifest 119570wa
 Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
 Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
 PO# 119570wa

Time	Scale	Operator	Inbound	Gross	98620 lb
In 03/11/2025 11:15:26	Scale1	amahurin		Tare	46200 lb
Out 03/11/2025 11:28:18	Scale1	amahurin		Net	52420 lb
				Tons	26.21

Comments

Product	LD%	Qty	UOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons-	100	26.21	Tons				SPOKANE
2 ENERGY-Energy Surcharge	100		%				SPOKANE
3 WWM-P-Waste Water Manag	100		%				SPOKANE
4 SRHD1-Spokane Regional	100	26.21	Tons				SPOKANE

Total Tax/Fees
 Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.

W
Graham Road Facility
1820 S. Graham Road
Medi WASTE MANAGEMENT 99022

Original
Ticket# 743669
Ph: (509)244-0151

Customer Name HALMECONSINC HALME CONST Carrier HALME HALME CONSTRUCTION
Ticket Date 03/11/2025 Vehicle# RICK
Payment Type Credit Account Container
Manual Ticket# Driver RICK
Route Check#
Hauling Ticket# Billing# 0000084
Destination Grid
Manifest 119570WA
Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
PO# 119570WA

Time	Scale	Operator	Inbound	Gross	93680 lb
In 03/11/2025 12:49:15	Scale1	amahurin		Tare	46140 lb
Out 03/11/2025 13:01:43	Scale1	amahurin		Net	47540 lb
				Tons	23.77

Comments

Product	LD%	Qty	UOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons-	100	23.77	Tons				SPOKANE
2 ENERGY-Energy Surcharge	100		%				SPOKANE
3 WWM-P-Waste Water Manag	100		%				SPOKANE
4 SRHD1-Spokane Regional	100	23.77	Tons				SPOKANE

Total Tax/Fees
Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.

W
Graham Road Facility
1820 S. Graham Road
Medi WASTE WASTE WASTE 99022

Original
Ticket# 743683
Ph: (509)244-0151

Customer Name HALMECONSINC HALME CONST Carrier HALME HALME CONSTRUCTION
Ticket Date 03/11/2025 Vehicle# RICK
Payment Type Credit Account Container
Manual Ticket# Driver RICK
Route Check#
Hauling Ticket# Billing# 0000084
Destination Grid
Manifest 119570WA
Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
PO# 119570WA

Time	Scale	Operator	Inbound	Gross	
In 03/11/2025 14:25:12	Scale1	amahurin		Tare	100180 lb 46020 lb
Out 03/11/2025 14:38:51	Scale1	amahurin		Net	54160 lb
				Tons	27.08

Comments

Product	LD	Qty	UOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons-	100	27.08	Tons				SPOKANE
2 ENERGY-Energy Surcharge	100		%				SPOKANE
3 WWM-P-Waste Water Manag	100		%				SPOKANE
4 SRHD1-Spokane Regional	100	27.08	Tons				SPOKANE

Total Tax/Fees
Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.

W
Graham Road Facility
1820 S. Graham Road
Mediast Lake, WA 99022

Original
Ticket# 743711
Ph: (509)244-0151

Customer Name HALMECONSINC HALME CONST Carrier HALME HALME CONSTRUCTION
Ticket Date 03/12/2025 Vehicle# RICK
Payment Type Credit Account Container
Manual Ticket# Driver RICK
Route Check#
Hauling Ticket# Billing# 0000084
Destination Grid
Manifest 119570WA
Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
PO# 119570WA

Time	Scale	Operator	Inbound	Gross	
In 03/12/2025 07:54:26	Scale1	amahurin		97220 lb	
Out 03/12/2025 08:07:53	Scale1	amahurin		46500 lb	
				Net	50720 lb
				Tons	25.36

Comments

Product	LD%	Qty	UOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons-	100	25.36	Tons				SPOKANE
2 ENERGY-Energy Surcharge	100		%				SPOKANE
3 WWM-P-Waste Water Manag	100		%				SPOKANE
4 SRHD1-Spokane Regional	100	25.36	Tons				SPOKANE

Total Tax/Fees
Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.

W
Graham Road Facility
1820 S. Graham Road
Medi ~~WASTE~~ ~~LIBERTY LAKE~~ 9022

Original
Ticket# 743748
Ph: (509)244-0151

Customer Name HALMECONSINC HALME CONST Carrier HALME HALME CONSTRUCTION
Ticket Date 03/12/2025 Vehicle# RICK
Payment Type Credit Account Container
Manual Ticket# Driver RICK
Route Check#
Hauling Ticket# Billing# 0000084
Destination Grid
Manifest 1
Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
PO# 119570WA

Time	Scale	Operator	Inbound	Gross	101980 lb
In 03/12/2025 11:59:00	Scale1	amahurin		Tare	46460 lb
Out 03/12/2025 12:11:25	Scale1	amahurin		Net	55520 lb
				Tons	27.76

Comments

Product	LDW	Qty	UOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons-	100	27.76	Tons				SPOKANE
2 ENERGY-Energy Surcharge	100		%				SPOKANE
3 WWM-P-Waste Water Manag	100		%				SPOKANE
4 SRHD1-Spokane Regional	100	27.76	Tons				SPOKANE

Total Tax/Fees
Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technic limitation.

W
 Graham Road Facility
 1820 S. Graham Road
 Medical Lake, WA 99022

Original
 Ticket# 743785
 Ph: (509)244-0151

Customer Name HALMECONSINC HALME CONST Carrier HALME HALME CONSTRUCTION
 Ticket Date 03/13/2025 Vehicle# RICK
 Payment Type Credit Account Container
 Manual Ticket# Driver RICK
 Route Check#
 Hauling Ticket# Billing# 0000084
 Destination Grid
 Manifest 119570wa
 Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
 Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
 PO# 119570wa

Time	Scale	Operator	Inbound	Gross	99000 lb
In 03/13/2025 07:48:42	Scale1	amahurin		Tare	46620 lb
Out 03/13/2025 08:01:17	Scale1	amahurin		Net	52380 lb
				Tons	26.19

Comments

Product	LD%	Qty	UOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons-	100	26.19	Tons				SPOKANE
2 ENERGY-Energy Surcharge	100		%				SPOKANE
3 WWM-P-Waste Water Manag	100		%				SPOKANE
4 SRHD1-Spokane Regional	100	26.19	Tons				SPOKANE

Total Tax/Fees
 Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technic limitation.

W
Graham Road Facility
1820 S. Graham Road
Medi WASTE MANAGEMENT 9022

Original
Ticket# 743795
Ph: (509)244-0151

Customer Name HALMECONSINC HALME CONST Carrier HALME HALME CONSTRUCTION
Ticket Date 03/13/2025 Vehicle# RICK
Payment Type Credit Account Container
Manual Ticket# Driver RICK
Route Check#
Hauling Ticket# Billing# 0000084
Destination Grid
Manifest 119570wa
Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
PO# 119570wa

Time	Scale	Operator	Inbound	Gross	105940 lb
In 03/13/2025 09:27:45	Scale1	amahurin		Tare	46620 lb
Out 03/13/2025 09:41:06	Scale1	amahurin		Net	59320 lb
				Tons	29.66

Comments

Product	LD	Qty	UOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons-	100	29.66	Tons				SPOKANE
2 ENERGY-Energy Surcharge	100		%				SPOKANE
3 WWM-P-Waste Water Manag	100		%				SPOKANE
4 SRHD1-Spokane Regional	100	29.66	Tons				SPOKANE

Total Tax/Fees
Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.

W
Graham Road Facility
1820 S. Graham Road
Mediast Lake, ID 83802

Original
Ticket# 743806
Ph: (509)244-0151

Customer Name HALMECONSINC HALME CONST Carrier HALME HALME CONSTRUCTION
Ticket Date 03/13/2025 Vehicle# RICK
Payment Type Credit Account Container
Manual Ticket# Driver RICK
Route Check#
Hauling Ticket# Billing# 0000084
Destination Grid
Manifest 119570wa
Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
PO# 119570wa

Time	Scale	Operator	Inbound	Gross	100360 lb
In 03/13/2025 11:03:01	Scale1	amahurin		Tare	46540 lb
Out 03/13/2025 11:19:18	Scale1	amahurin		Net	53820 lb
				Tons	26.91

Comments

Product	LD%	Qty	UOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons-	100	26.91	Tons				SPOKANE
2 ENERGY-Energy Surcharge	100		%				SPOKANE
3 WWM-P-Waste Water Manag	100		%				SPOKANE
4 SRHD1-Spokane Regional	100	26.91	Tons				SPOKANE

Total Tax/Fees
Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technic limitation.

W
 Graham Road Facility
 1820 S. Graham Road
 Liberty Lake, WA 99022

Original
 Ticket# 743815
 Ph: (509)244-0151

Customer Name HALMECONSINC HALME CONST Carrier HALME HALME CONSTRUCTION
 Ticket Date 03/13/2025 Vehicle# RICK
 Payment Type Credit Account Container
 Manual Ticket# Driver RICK
 Route Check#
 Hauling Ticket# Billing# 0000084
 Destination Grid
 Manifest 119570WA
 Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
 Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
 PO# 119570WA

Time	Scale	Operator	Inbound	Gross	97080 lb
In 03/13/2025 12:46:38	Scale1	amahurin		Tare	46420 lb
Out 03/13/2025 12:59:12	Scale1	amahurin		Net	50660 lb
				Tons	25.33

Comments

Product	LD%	Qty	UOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons-	100	25.33	Tons				SPOKANE
2 ENERGY-Energy Surcharge	100		%				SPOKANE
3 WWM-P-Waste Water Manag	100		%				SPOKANE
4 SRHD1-Spokane Regional	100	25.33	Tons				SPOKANE

Total Tax/Fees
 Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.

W
Graham Road Facility
1820 S. Graham Road
Mediaville, OH 44130-9022

Original
Ticket# 743848
Ph: (509)244-0151

Customer Name HALMECONSINC HALME CONST Carrier HALME HALME CONSTRUCTION
Ticket Date 03/14/2025 Vehicle# RICK
Payment Type Credit Account Container
Manual Ticket# Driver RICK
Route Check#
Hauling Ticket# Billing# 0000084
Destination Grid
Manifest 119570WA
Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
PO# 119570WA

Time	Scale	Operator	Inbound	Gross	
In 03/14/2025 07:54:57	Scale1	amahurin		Tare	94300 lb 46600 lb
Out 03/14/2025 08:08:30	Scale1	amahurin		Net	47700 lb
				Tons	23.85

Comments

Product	LD%	Qty	UOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons-	100	23.85	Tons				SPOKANE
2 ENERGY-Energy Surcharge	100		%				
3 WWM-P-Waste Water Manag	100		%				
4 SRHD1-Spokane Regional	100	23.85	Tons				

Total Tax/Fees
Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technic limitation.

W
 Graham Road Facility
 1820 S. Graham Road
 Medical Center 89022

Original
 Ticket# 743861
 Ph: (509)244-0151

Customer Name HALMECONSINC HALME CONST Carrier HALME HALME CONSTRUCTION
 Ticket Date 03/14/2025 Vehicle# RICK
 Payment Type Credit Account Container
 Manual Ticket# Driver RICK
 Route Check#
 Hauling Ticket# Billing# 0000084
 Destination Grid
 Manifest 119570WA
 Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
 Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
 PO# 119570WA

Time	Scale	Operator	Inbound	Gross	
In 03/14/2025 09:32:53	Scale1	amahurin		104280	lb
Out 03/14/2025 09:48:31	Scale1	amahurin		46560	lb
				57720	lb
				28.86	

Comments

Product	LD%	Qty	UOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons-	100	28.86	Tons				SPOKANE
2 ENERGY-Energy Surcharge	100		%				SPOKANE
3 WWM-P-Waste Water Manag	100		%				SPOKANE
4 SRHD1-Spokane Regional	100	28.86	Tons				SPOKANE

Total Tax/Fees
 Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.

W
Graham Road Facility
1820 S. Graham Road
Mediast Lake, WA 99022

Original
Ticket# 744344
Ph: (509)244-0151

Customer Name HALMECONSINC HALME CONST Carrier HALME HALME CONSTRUCTION
Ticket Date 03/21/2025 Vehicle# RICK
Payment Type Credit Account Container
Manual Ticket# Driver RICK
Route Check#
Hauling Ticket# Billing# 0000084
Destination Grid
Manifest 119570WA
Profile 119570WA (LF01: DIESEL FUEL IMPACTED SOIL AND/OR DEBRIS CLEANUP)
Generator CVSD GUN-19615 CVSD GUN CLUB 19615 E SPRAGUE AVE LIBERTY LAKE
PO# 119570WA

Time	Scale	Operator	Inbound	Gross	111840 lb
In 03/21/2025 08:24:24	Scale1	AMAHURIN		Tare	46520 lb
Out 03/21/2025 08:38:23	Scale1	AMAHURIN		Net	65320 lb
				Tons	32.66

Comments


Product	LD%	Qty	UOM	Rate	Tax/Fee	Amount	Origin
1 Spwaste Solid Oth-Tons-	100	32.66	Tons				SPOKANE
2 ENERGY-Energy Surcharge	100		%				SPOKANE
3 WWM-P-Waste Water Manag	100		%				SPOKANE
4 SRHD1-Spokane Regional	100	32.66	Tons				SPOKANE

Total Tax/Fees
Total Ticket

Driver's Signature

The total amount includes fees and taxes that may not all be listed on this ticket due to technical limitation.

APPENDIX J
Laboratory Proctor Results



Test specification: ASTM D 1557-07 Method C Modified
 ASTM D4718-15 Oversize Corr. Applied to Each Test Point

Elev/ Depth	Classification		Nat. Moist.	Sp.G.	LL	PI	% > 3/4 in.	% < No.200
	USCS	AASHTO						
grab	GM	-	5.8	2.5	NT	NT	6.0	26.8

ROCK CORRECTED TEST RESULTS	UNCORRECTED	MATERIAL DESCRIPTION
Maximum dry density = 131.2 pcf	129.4 pcf	SILTY GRAVEL WITH SAND
Optimum moisture = 6.7 %	7.1 %	

Project No. 0208895000 Client: Project: CVSD Soil Characterization and SEPA Date: 11/20/23 <input type="radio"/> Source of Sample: Site Soil Sample Number: Soil #1	Remarks: Significant organic constituent (fines and rootlets). SpG estimated.
	

Figure



Proudly serving the Inland Northwest since 1976

Breeyn Greer
Haley & Aldrich, Inc.
505 W Riverside Ave, Ste 550
Spokane, WA 99201

January 10, 2025

Project Number L25027

PROJECT: CVSD- Haley & Aldrich 2025 Materials

**SUBJECT: Results of Laboratory Testing
Report #1**

At your request, we provided laboratory testing services for the subject project. Services were limited to the performance of specific laboratory tests, selected at your discretion.

For this period, our involvement was limited to laboratory testing of six samples delivered to our laboratory on January 7, 2025. Laboratory tests were performed in general accordance with methods listed in the attached *Laboratory Summary* sheets.

If you have questions regarding this report, please call.

Respectfully Submitted,
Budinger & Associates, Inc.

Kiel Couch
Laboratory Manager


KC/lat/Addressee –
Breeyn Greer – bgreer@haleyaldrich.com

Attachments:
Proctor Laboratory Summary – 1 page
Moisture-Unit Weight Relationship Report – 6 pages

**PROCTOR
LABORATORY SUMMARY**

LABORATORY NUMBER			25-0009	25-0010	25-0011	25-0012	25-0013	25-0014
SAMPLED BY			Client	Client	Client	Client	Client	Client
SAMPLE TYPE			Bulk	Bulk	Bulk	Bulk	Bulk	Bulk
DATE RECEIVED			1/7/25	1/7/25	1/7/25	1/7/25	1/7/25	1/7/25
SAMPLE DESCRIPTION			Silty sand with gravel, trace clay (Clean 1)	Silty sand with gravel (Clean 2)	Gravelly sand with silt (Clean 3)	Silty sand with gravel (CS-NW-1)	Silty sand and gravel (CS-WR-2)	Sand and gravel with silt (CS-SE-3)
SAMPLE SOURCE			On site	On site	On site	On site	On site	On site
	<u>UNITS</u>	<u>TEST METHOD</u>						
PROCTOR		ASTM D1557						
Maximum Unit Weight	pcf		130.0	136.3	142.1	129.6	130.5	140.0
Optimum Moisture	%		8.4	6.2	6.0	8.2	8.3	6.6
Sample Moisture	%		4.7	4.8	7.4	10.2	5.7	6.0
Bulk Specific Gravity (+3/4")		ASTM C127	2.562	2.673	2.665	2.542	2.582	2.648
Maximum Unit Weight, Corrected	pcf		136.3	144.5	147.0	134.7	137.1	147.1
Optimum Moisture, Corrected	%		6.7	4.5	4.8	6.9	6.7	4.9

Moisture-Unit Weight Relationship



Test specification: ASTM D 1557-12 Method C Modified
 ASTM D4718-15 Oversize Corr. Applied to Each Test Point

Elev/ Depth	Classification		Nat. Moist.	Sp.G.	LL	PI	% > 3/4 in.	% < No.200
	USCS	AASHTO						
			4.7	+3/4"= 2.562			23.5	

ROCK CORRECTED TEST RESULTS	UNCORRECTED	MATERIAL DESCRIPTION
Maximum dry density = 136.3 pcf	130.0 pcf	Silty sand with gravel and trace clay (Clean 1)
Optimum moisture = 6.7 %	8.4 %	


Project No. L25027 Client: Haley & Aldrich Project: CVSD- Haley & Aldrich 2025 Materials ○Source of Sample: On-site Sample Number: 25-0009	Remarks: Sampled by Client
--	-------------------------------

BUDINGER & ASSOCIATES, INC.

Date: 1/10/25

Tested By: PK _____ Checked By: KC _____

Moisture-Unit Weight Relationship



Test specification: ASTM D 1557-12 Method C Modified
 ASTM D4718-15 Oversize Corr. Applied to Each Test Point

Elev/ Depth	Classification		Nat. Moist.	Sp.G.	LL	PI	% > 3/4 in.	% < No.200
	USCS	AASHTO						
			7.4	+3/4"= 2.665			21.9	

ROCK CORRECTED TEST RESULTS	UNCORRECTED	MATERIAL DESCRIPTION
Maximum dry density = 147.0 pcf	142.1 pcf	Gravelly sand with silt (Clean 3)
Optimum moisture = 4.8 %	6.0 %	


Project No. L25027 Client: Haley & Aldrich Project: CVSD- Haley & Aldrich 2025 Materials ○Source of Sample: On-site Sample Number: 25-0011	Remarks: Sampled by Client
--	-------------------------------

BUDINGER & ASSOCIATES, INC.

Date: 1/10/25

Tested By: TS Checked By: KC

Moisture-Unit Weight Relationship



Test specification: ASTM D 1557-12 Method C Modified
 ASTM D4718-15 Oversize Corr. Applied to Each Test Point

Elev/ Depth	Classification		Nat. Moist.	Sp.G.	LL	PI	% > 3/4 in.	% < No.200
	USCS	AASHTO						
			5.7	+3/4"= 2.582			24.0	

ROCK CORRECTED TEST RESULTS	UNCORRECTED	MATERIAL DESCRIPTION
Maximum dry density = 137.1 pcf	130.5 pcf	Silty sand and gravel (CS-WR-2)
Optimum moisture = 6.7 %	8.3 %	


Project No. L25027 Client: Haley & Aldrich Project: CVSD- Haley & Aldrich 2025 Materials ○Source of Sample: On-site Sample Number: 25-0013	Remarks: Sampled by Client
--	-------------------------------

BUDINGER & ASSOCIATES, INC.

Date: 1/10/25

Tested By: PK _____ Checked By: KC _____

Moisture-Unit Weight Relationship



Test specification: ASTM D 1557-12 Method C Modified
 ASTM D4718-15 Oversize Corr. Applied to Each Test Point

Elev/ Depth	Classification		Nat. Moist.	Sp.G.	LL	PI	% > 3/4 in.	% < No.200
	USCS	AASHTO						
			6.0	+3/4"= 2.648			30.0	

ROCK CORRECTED TEST RESULTS	UNCORRECTED	MATERIAL DESCRIPTION
Maximum dry density = 147.1 pcf	140.0 pcf	Sand and gravel with silt (CS-SE-3)
Optimum moisture = 4.9 %	6.6 %	

Project No. L25027 Client: Haley & Aldrich
 Project: CVSD- Haley & Aldrich 2025 Materials

○Source of Sample: On-site Sample Number: 25-0014

Remarks:
 Sampled by Client
FOR INFORMATIONAL USE ONLY.
 Sample contained 30.5% retained on the 3/4" sieve, Max allowed per ASTM D1557 is 30%. Report only reflects 30% retained

BUDINGER & ASSOCIATES, INC.

Date: 1/10/25

Tested By: GP Checked By: KC

APPENDIX K
Northwest Linings Installation Report

NORTHWEST LININGS & GEOTEXTILE PRODUCTS, INC.

• 20824 77th Avenue South • Kent, WA 98032 •

Phone: (253) 872-0244 • Fax: (253) 872-0245

www.northwestlinings.com

LETTER OF TRANSMITTAL

TO:	Halme Construction
	8727 W Hwy 2 #100
	Spokane WA 99224

DATE: July 16, 2025	JOB #: N23072
ATTENTION: Dylan Miller 509-951-2986 <dylanm@halmeconstruction.com>	
RE: CVSD Gun Club Cleanup Project – Cap Liner - As-built Liner Submittal Package	

WE ARE SENDING YOU: Attached Under Separate Cover via _____ the following items:

- Shop Drawings Prints Plans Specifications Samples
 Copy of Letter Change Order Submittals Warranties Other

Copies	Specification #	Description
1		NWL shop drawing of As-built 60-mil textured HDPE geomembrane liner Panel Layout.
1		As-built QC documentation, including: Panel Placement Form, Trial Weld Log, Panel Seaming Form, Non Destructive Testing Form, Destructive Testing Form, and Repair Report.

These are transmitted as checked below:

- For Approval Approved as submitted Resubmit Copies for Approval
 For your use Approved as noted Submit Copies for distribution
 For review and comment Returned for corrections Return Corrected Prints
 For bids due _____ Other _____
 Prints returned after loan to us


REMARKS:

COPY TO: _____ **SIGNED:** S.T. Snethen



Legend:


- x - Repair
- ▨ - Destructive Test/Repair
- - Patch



CVSD Gun Club Cleanup Project
 As-built 60-mil textured HDPE liner Panel Layout

JOB NAME:	CVSD Gun Club Cleanup Project		
JOB NO.:	N 2 3 0 7 2		
DATE:	7 16 25	CHECKED:	CS
BY:	TS	SCALE:	AS SHOWN

NORTHWEST LININGS & GEOTEXTILE PRODUCTS, Inc.
www.northwestlinings.com
 21000 77TH AVE. SOUTH
 KENT, WA. 98032
 (253) 872-0244 (253) 872-0245 FAX



DETAIL

1 of 1



**NORTHWEST LININGS &
GEOTEXTILE PRODUCTS, Inc.**
"Helping to Protect the Environment"
 21000 77th Avenue South
 Kent, WA 98032
 (253) 872-0244 / (800) 729-6954
 FAX: (253) 872-0245

Date: 5/13/2025
 Job #: N23072

Panel Placement Form

Project Name: CVSD GUN CLUB CLEAN UP
 Project Location: SPOKANE, WA
 Project Description: CAP
 Project Manager: CS

Supervisor: R FLACO ARELLANO
 Engineer: BRADY/CODY
 Contractor: HALME CONSTRUCTION
 Contact: BRADY/CODY

Material: 60-MIL HDPE T2

Date	Panel #	Length	Width	Roll Number	Panel Location / Comment
5/13/25	P-1	53'	23.8'	4754	AT WEST SIDE SLOPE
5/13/25	P-2	53'	23.8'	4754	AT WEST SIDE SLOPE
5/13/25	P-3	55'	23.8'	4754	AT WEST SIDE SLOPE
5/13/25	P-4	55'	23.8'	4754	AT WEST SIDE SLOPE
5/13/25	P-5	53'	23.8'	4754	AT WEST SIDE SLOPE
5/13/25	P-6	53'	23.8'	4754	AT WEST SIDE SLOPE
5/13/25	P-7	49'	23.8'	4754	AT WEST SIDE SLOPE
5/13/25	P-8	48'	23.8'	4754	AT WEST SIDE SLOPE
5/13/25	P-9	49'	23.8'	4754	AT WEST SIDE SLOPE
5/13/25	P-10	20'	23.8'	4754	AT WEST SIDE SLOPE
5/13/25	P-11	27'	23.8'	4750	AT WEST SIDE SLOPE
5/13/25	P-12	45'	23.8'	4750	AT WEST SIDE SLOPE
5/13/25	P-13	44'	23.8'	4750	AT WEST SIDE SLOPE
5/13/25	P-14	44'	23.8'	4750	AT WEST SIDE SLOPE
5/13/25	P-15	26'	23.8'	4750	AT WEST SIDE SLOPE
5/13/25	P-16	32'	23.8'	4750	AT WEST SIDE SLOPE
5/13/25	P-17	71'	23.8'	4752	NORTH SIDE END
5/13/25	P-18	276'	23.8'	4750	SOUTH TO NORTH SIDE
5/13/25	P-19	351'	23.8'	4752	N-S ACROSS
5/13/25	P-20	292'	23.8'	4747	N-S ACROSS
5/13/25	P-21	67'	23.8'	4752	AT SOUTH SIDE END
5/13/25	P-22	167'	23.8'	4751	AT NORTH SIDE TO S
5/13/25	P-23	196'	23.8'	4747	SOUTH TO N SIDE END
5/13/25	P-24	318'	23.8'	4751	NORTH TO S SIDE END
5/13/25	P-25	49'	23.8'	4753	AT SOUTH SIDE END
5/14/25	P-26	380'	23.8'	4753	N-S ACROSS
5/14/25	P-27	58'	23.8'	4753	AT SOUTH SIDE END
5/14/25	P-28	329'	23.8'	4748	S-N SIDE END
5/14/25	P-29	166'	23.8'	4748	S-N SIDE END
5/14/25	P-30	228'	23.8'	4762	N-S SIDE
5/14/25	P-31	260'	23.8'	4762	S-N SIDE END
5/14/25	P-32	138'	23.8'	4745	AT NORTH SIDE TO S
5/14/25	P-33	352'	23.8'	4745	AT NORTH SIDE TO S
5/14/25	P-34	60'	23.8'	4762	AT SOUTH SIDE END
5/14/25	P-35	416'	23.8'	4764	N-S ACROSS
5/15/25	P-36	420'	23.8'	4749	S-N SIDE END

Notes: CONTINUED NEXT PAGE.



**NORTHWEST LININGS &
GEOTEXTILE PRODUCTS, Inc.**
"Helping to Protect the Environment"

21000 77th Avenue South
Kent, WA 98032
(253) 872-0244 / (800) 729-6954
FAX: (253) 872-0245

Date: 5/13/2025
Job #: N23072

Geomembrane Fusion Weld Trial Log

Project Name: CVSD GUN CLUB CLEAN UP
Project Location: SPOKANE, WA
Project Description: CAP
Project Manager: CS

Supervisor: R FLACO ARELLANO
Engineer: BRADY/CODY
Contractor: HALME CONSTRUCTION
Contact: BRADY/CODY

Material: 60-MIL HDPE T2

Date/ Time	Seamer Initials	Machine Number	Wedge Welder		Extruder		Track Peel Values			Tensile Value		
			Wedge Temp	Nip Roller Speed	Barrel Temp	Preheat Temp	In- side	Out- side	Pass/ Fail	LBS/I nch	Rate	Pass/ Fail
5/13/2025 AM	IV	2929	800	6			131	132	Pass	212	2 FM	Pass
Comments: 60-MIL HDPE T2							132	137	Pass	211	2 FM	Pass
Ambient Temp: 60							141	135	Pass			
5/13/2025 AM	RP	4478	800	6			125	128	Pass	215	2 FM	Pass
Comments: 60-MIL HDPE T2							122	124	Pass	218	2 FM	Pass
Ambient Temp: 60							125	123	Pass			
5/13/2025 PM	RP	4478	800	6			121	124	Pass	211	2 FM	Pass
Comments:							119	127	Pass	206	2 FM	Pass
Ambient Temp: 68							122	131	Pass			
5/13/2025 PM	IV	2929	800	6			131	123	Pass	202	2 FM	Pass
Comments: 60-MIL HDPE T2							132	127	Pass	200	2 FM	Pass
Ambient Temp: 68							122	128	Pass			
5/14/2025 AM	RP	4478	800	6			121	128	Pass	203	2 FM	Pass
Comments:							128	138	Pass	200	2 FM	Pass
Ambient Temp: 55							127	122	Pass			
5/14/2025 AM	IV	2929	800	6			140	136	Pass	198	2 FM	Pass
Comments: 60-MIL HDPE T2							129	126	Pass	195	2 FM	Pass
Ambient Temp: 55							143	145	Pass			
5/14/2025 PM	RP	6984			500	500		131	Pass	201	2 FM	Pass
Comments: 60-MIL HDPE T2								122	Pass	189	2 FM	Pass
Ambient Temp: 60								129	Pass			
5/15/2025 AM	RP	4478	800	6			133	123	Pass	189	2 FM	Pass
Comments: 60-MIL JHDPE T2							122	131	Pass	190	2 FM	Pass
Ambient Temp: 50							124	127	Pass			



**NORTHWEST LININGS &
GEOTEXTILE PRODUCTS, Inc.**
"Helping to Protect the Environment"

21000 77th Avenue South
Kent, WA 98032
(253) 872-0244 / (800) 729-6954
FAX: (253) 872-0245

Date: 5/15/2025
Job #: N23072

Geomembrane Fusion Weld Trial Log

Project Name: CVSD GUN CLUB CLEAN UP
Project Location: SPOKANE, WA
Project Description: CAP
Project Manager: CS

Supervisor: R FLACO ARELLANO
Engineer: BRADY/CODY
Contractor: HALME CONSTRUCTION
Contact: BRADY/CODY

Material: 60-MIL HDPE T2

Date/ Time	Seamer Initials	Machine Number	Wedge Welder		Extruder		Track Peel Values			Tensile Value		
			Wedge Temp	Nip Roller Speed	Barrel Temp	Preheat Temp	In- side	Out- side	Pass/ Fail	LBS/I nch	Rate	Pass/ Fail
5/15/2025 AM	IV	4047	800	6			120	133	Pass	189	2 FM	Pass
Comments: 60-MIL HDPE T2							131	131	Pass	168	2 FM	Pass
Ambient Temp: 50							123	123	Pass			
5/15/2025 PM	RP	4478	800	6			120	130	Pass	170	2 FM	Pass
Comments:							122	133	Pass	180	2 FM	Pass
Ambient Temp: 60							118	120	Pass			
5/15/2025 PM	IV	4047	800	6			122	123	Pass	167	2 FM	Pass
Comments: 60-MIL HDPE T2							131	123	Pass	177	2 FM	Pass
Ambient Temp: 60							134	127	Pass			
5/17/2025 AM	RP	6984			500	500		124	Pass	175	2 FM	Pass
Comments: 60-MIL HDPE T2								122	Pass	181	2 FM	Pass
Ambient Temp: 45								126	Pass			
5/17/2025 AM	GN	7082			500	500		134	Pass	177	2 FM	Pass
Comments: 60-MIL HDPE T2								125	Pass	179	2 FM	Pass
Ambient Temp: 45								127	Pass			
5/19/2025 AM	IV	4047	600	6			135	125	Pass	185	2 FM	Pass
Comments: 60-MIL HDPE T2							131	127	Pass	191	2 FM	Pass
Ambient Temp: 45							123	122	Pass			
5/19/2025 AM	RP	4478	800	6			135	125	Pass	192	2 FM	Pass
Comments:							134	119	Pass	187	2 FM	Pass
Ambient Temp: 45							125	126	Pass			
5/19/2025 AM	MM	6984			500	500		126	Pass	169	2 FM	Pass
Comments: 60-MIL HDPE T2								131	Pass	172	2 FM	Pass
Ambient Temp: 45								124	Pass			



**NORTHWEST LININGS &
GEOTEXTILE PRODUCTS, Inc.**
"Helping to Protect the Environment"
 21000 77th Avenue South
 Kent, WA 98032
 (253) 872-0244 / (800) 729-6954
 FAX: (253) 872-0245

Date: 5/13/2025
 Job #: N23072

Panel Seaming Form

Project Name: CVSD GUN CLUB CLEAN UP
 Project Location: SPOKANE, WA
 Project Description: CAP
 Project Manager: CS

Supervisor: R FLACO ARELLANO
 Engineer: BRADY/CODY
 Contractor: HALME CONSTRUCTION
 Contact: BRADY/CODY

Material: 60-MIL HDPE T2

Date/ Time	Panel Numbers	Seam Length	Seamer Initials	Machine Number	Machine Temp	Ambient Temp	Weather / Comments
5/13/25 AM	P-1/P-2	54'	IV	2929	800	60	P/C TOP-TRENCH END W SLOPE
5/13/25 AM	P-2/P-3	54'	IV	2929	800	60	P/C TOP-TRENCH END W SLOPE
5/13/25 AM	P-3/P-4	53'	IV	2929	800	60	P/C TOP-TRENCH END W SLOPE
5/13/25 AM	P-4/P-5	53'	IV	2929	800	60	P/C TOP-TRENCH END W SLOPE
5/13/25 AM	P-5/P-6	52'	IV	2929	800	60	P/C TOP-TRENCH END W SLOPE
	P-6/P-7	49'	RP	4478	800	60	P/C TOP-TRENCH END W SLOPE
	P-7/P-8	48'	RP	4478	800	60	P/C TOP-TRENCH END W SLOPE
	P-8/P-9	48'	RP	4478	800	60	P/C TOP-TRENCH END W SLOPE
5/13/25 AM	P-10/P-11	24'	RP	4478	800	60	P/C TIE-IN BUTT AT W SLOPE
5/13/25 AM	P-9/10,11	47'	RP	4478	800	60	P/C TOP-TRENCH END W SLOPE
5/13/25 AM	10,11/12	45'	IV	2929	800	60	P/C TOP-TRENCH END W SLOPE
	P-12/P-13	44'	IV	2929	800	60	P/C TOP-TRENCH END W SLOPE
	P-13/P-14	44'	IV	292	800	60	P/C TOP-TRENCH END W SLOPE
	P-15/P-16	28'	RP	4478	800	60	P/C NW CORNER SLOPE
5/13/25 AM	14/15,16	43'	RP	4478	800	60	P/C NW CORNER SLOPE
5/13/25 AM	17/18	24'	RP	4478	800	60	P/C TIE-IN BUTT TOP FLOOR
5/13/25 AM	14,16-1/17,18	346'	RP	4478	800	60	P/C S-N ACROSS
5/13/25 AM	17,18/19	351'	IV	2929	800	60	P/C S-N ACROSS
5/13/25 PM	20/21	24'	IV	2929	800	68	P/C TIE-IN BUTT TOP FLOOR
5/13/25 PM	19/20,21	351'	RP	4478	800	68	P/C S-N ACROSS



**NORTHWEST LININGS &
GEOTEXTILE PRODUCTS, Inc.**
"Helping to Protect the Environment"

21000 77th Avenue South
Kent, WA 98032
(253) 872-0244 / (800) 729-6954
FAX: (253) 872-0245

Date: 5/13/2025
Job #: N23072

Panel Seaming Form

Project Name: CVSD GUN CLUB CLEAN UP
Project Location: SPOKANE, WA
Project Description: CAP
Project Manager: CS

Supervisor: R FLACO ARELLANO
Engineer: BRADY/CODY
Contractor: HALME CONSTRUCTION
Contact: BRADY/CODY

Material: 60-MIL HDPE T2

Date/ Time	Panel Numbers	Seam Length	Seamer Initials	Machine Number	Machine Temp	Ambient Temp	Weather / Comments
5/13/25 PM	22/23	24'	IV	2929	800	68	P/C TIE-IN BUTTSEAM AT FLOOR
5/13/25 PM	20,21/22,23	362'	IV	2929	800	68	P/C S-N ACROSS OF AREA
5/13/25 PM	24/25	24'	IV	2929	800	68	P/C TIE-IN BUTTSEAM AT FLOOR
5/13/25 PM	22,23/24,25	383'	RP	4478	800	68	P/C S-N ACROSS OF AREA
5/14/25 AM	24,25/26	380'	RP	4478	800	60	P/C N-S ACROSS
5/14/25 AM	27/28	24'	RP	4478	800	60	P/C TIE-IN BUTTSEAM AT FLOOR
5/14/25 AM	26/27,28	387'	IV	4047	800	60	P/C N-S ACROSS
5/14/25 AM	29/30	24'	IV	4047	800	60	P/C TIE-IN BUTTSEAM AT FLOOR
5/14/25 AM	27,28/29,30	394'	IV	4047	800	60	P/C N-S ACROSS
5/14/25 AM	31/32	24'	RP	4478	800	60	P/C TIE-IN BUTTSEAM AT FLOOR
5/14/25 AM	33/34	24'	RP	4478	800	60	P/C TIE-IN BUTTSEAM AT FLOOR
5/14/25 AM	29,30/31,32	398'	RP	4478	800	60	P/C N-S ACROSS
5/14/25 AM	31,32/33,34	412'	IV	4047	800	60	P/C N-S ACROSS
5/14/25 AM	33,34/35	415'	RP	4478	800	60	P/C S-N ACROSS OF AREA
5/15/25 AM	35/36	418'	RP	4478	800	55	P/C N-S ACROSS
5/15/25 AM	36/37	396'	IV	4047	800	55	P/C N-S ACROSS
5/15/25 AM	38/39	24'	RP	4478	800	55	P/C TIE-IN BUTTSEAM AT FLOOR
5/15/25 AM	39/40	24'	RP	4478	800	55	P/C TIE-IN BUTTSEAM AT FLOOR
5/15/25 AM	37/38-40	375'	IV	4047	800	55	P/C N-S ACROSS
5/15/25 AM	41/42	24'	IV	4047	800	55	P/C TIE-IN BUTTSEAM AT FLOOR



**NORTHWEST LININGS &
GEOTEXTILE PRODUCTS, Inc.**
"Helping to Protect the Environment"
 21000 77th Avenue South
 Kent, WA 98032
 (253) 872-0244 / (800) 729-6954
 FAX: (253) 872-0245

Date: 5/15/2025
 Job #: N23072

Panel Seaming Form

Project Name: CVSD GUN CLUB CLEAN UP
 Project Location: SPOKANE, WA
 Project Description: CAP
 Project Manager: CS

Supervisor: R FLACO ARELLANO
 Engineer: BRADY/CODY
 Contractor: HALME CONSTRUCTION
 Contact: BRADY/CODY

Material: 60-MIL HDPE T2

Date/ Time	Panel Numbers	Seam Length	Seamer Initials	Machine Number	Machine Temp	Ambient Temp	Weather / Comments
5/15/25 AM	38-4.0/41,42	350'	RP	4478	800	55	P/C N-S ACROSS
5/15/25 AM	43/44	24'	RP	4478	800	55	P/C TIE-IN BUTTSEAM AT FLOOR
5/15/25 PM	41,42/43,44	330'	IV	4047	800	64	P/C N-S ACROSS
5/15/25 PM	45/46	18'	IV	4047	800	64	P/C TIE-IN BUTTSEAM AT FLOOR
5/15/25 PM	46/47	18'	IV	4047	800	64	P/C TIE-IN BUTTSEAM AT FLOOR
5/15/25 PM	43,44/45-48	305'	IV	4047	800	64	P/C N-S ACROSS
5/15/25 PM	48/49	211'	RP	4478	800	64	P/C N-S ACROSS
5/15/25 PM	50/51	24'	RP	4478	800	64	P/C TIE-IN BUTTSEAM AT FLOOR
5/15/25 PM	49/50,51	160'	RP	4478	800	64	P/C N-S ACROSS
5/15/25 PM	51/52	155'	IV	4047	800	64	P/C N-S ACROSS
5/19/25 AM	53/54	24'	IV	4047	800	45	P/C TIE-IN BUTTSEAM AT FLOOR
5/19/25 AM	55/56	24'	IV	4047	800	45	P/C TIE-IN BUTTSEAM AT FLOOR
5/19/25 AM	57/58	24'	IV	4047	800	45	P/C TIE-IN BUTTSEAM AT FLOOR
5/19/25 AM	52/53,54	134'	RP	4478	800	45	P/C S-N ACROSS
5/19/25 AM	53,54/55,56	110'	IV	4047	800	45	P/C N-S ACROSS
5/19/25 AM	55,56/57,58	90'	RP	4478	800	45	P/C N-S ACROSS
5/19/25 AM	57,58/59	65'	RP	4478	800	45	P/C N-S ACROSS
5/19/25 AM	59/60	41'	IV	4047	800	45	P/C S-N ACROSS



**NORTHWEST LININGS &
GEOTEXTILE PRODUCTS, Inc.**

"Helping to Protect the Environment"

21000 77th Avenue South
Kent, WA 98032
(253) 872-0244 / (800) 729-6954
FAX: (253) 872-0245

Date: 5/13/2025
Job #: N23072

Non Destructive Testing Form

Project Name: CVSD GUN CLUB CLEAN UP
Project Location: SPOKANE, WA
Project Description: CAP
Project Manager: CS

Supervisor: R FLACO ARELLANO
Engineer: BRADY/CODY
Contractor: HALME CONSTRUCTION
Contact: BRADY/CODY

Material: 60-MIL HDPE T2

Date/ Time	Panel Numbers	Seamer Initials	Air Pressure Testing					Pass/ Fail	V-Box Pass/ Fail	Comments / Location
			Start Pressure	Start Time	Ending Pressure	End Time	Pressure Loss			
5/13/25 AM	P-1/P-2	IL	30	10:00	30	10:05	0	Pass		AT W SLOPE TOP- END
5/13/25 AM	P-2/P-3	IL	30	10:00	30	10:05	0	Pass		AT W SLOPE TOP- END
5/13/25 AM	P-3/P-4	IL	30	10:00	30	10:05	0	Pass		AT W SLOPE TOP- END
5/13/25 AM	P-4/P-5	IL	30	10:00	30	10:05	0	Pass		AT W SLOPE TOP- END
	P-5/P-6	IL	30	10:00	30	10:05	0	Pass		AT W SLOPE TOP- END
	P-6/P-7	IL	30	10:10	30	10:15	0	Pass		AT W SLOPE TOP- END
	P-7/P-8	IL	30	10:10	30	10:15	0	Pass		AT W SLOPE TOP- END
5/13/25 AM	P-8/P-9	IL	30	10:10	30	10:15	0	Pass		AT W SLOPE TOP- END
5/13/25 AM	P-9/P-10,11	IL	30	10:10	30	10:15	0	Pass		AT W SLOPE TOP- END
5/13/25 AM	10,11/P-12	IL	30	10:10	30	10:15	0	Pass		AT W SLOPE TOP- END
5/13/25 AM	P-10/P-11	IL	30	10:10	30	10:15	0	Pass		24' TIE-IN BUTT W LOPE
	P-12/P-13	IL	30	10:20	30	10:25	0	Pass		AT W SLOPE TOP- END
	P-13/P-14	IL	30	10:20	30	10:25	0	Pass		AT W SLOPE TOP- END
	14,16,15	IL	30	10:20	29	10:25	1	Pass		AT W SLOPE TOP- END
5/13/25 AM	P-15/P-16	IL	30	10:20	30	10:25	0	Pass		NW CORNER TIE-IN SEAM
5/13/25 AM	16,14-1/17,18	IL	30	11:30	29	11:35	1	Pass		N-S ACROSS W TIE-IN BUTT.
5/13/25 AM	P-17/P-18	IL	30	11:40	30	11:45	0	Pass		24' TIE-IN BUTT TOP FLOOR
5/13/25 AM	17,18/19	IL	30	11:40	30	11:45	0	Pass		S-N ACROSS
5/14/25 PM	19/20,21	IL	30	4:00	30	4:05	0	Pass		S-N ACROSS
5/14/25 PM	20/21	IL	30	4:00	30	4:05	0	Pass		24' TIE-IN BUTT TOP FLOOR



**NORTHWEST LININGS &
GEOTEXTILE PRODUCTS, Inc.**
"Helping to Protect the Environment"
 21000 77th Avenue South
 Kent, WA 98032
 (253) 872-0244 / (800) 729-6954
 FAX: (253) 872-0245

Date: 5/14/2025
 Job #: N23072

Non Destructive Testing Form

Project Name: CVSD GUN CLUB CLEAN UP
 Project Location: SPOKANE, WA
 Project Description: CAP
 Project Manager: CS

Supervisor: R FLACO ARELLANO
 Engineer: BRADY/CODY
 Contractor: HALME CONSTRUCTION
 Contact: BRADY/CODY

Material: 60-MIL HDPE T2

Date/ Time	Panel Numbers	Seamer Initials	Air Pressure Testing					Pass/ Fail	V-Box Pass/ Fail	Comments / Location
			Start Pressure	Start Time	Ending Pressure	End Time	Pressure Loss			
5/14/25 PM	20,21/22,23	IL	30	4:00	28	4:05	2	Pass		S-N ACROSS
5/14/25 PM	22,23/24,25	IL	30	4:00	29	4:05	1	Pass		S-N ACROSS
5/14/25 PM	22/23	IL	30	4:00	30	4:05	0	Pass		24' TIE-IN BUTTSEAM
5/14/25 PM	24/25	IL	30	4:00	30	4:05	0	Pass		24' TIE-IN BUTTSEAM
5/17/25 AM	24,25/26	IL	30	10:00	30	10:05	0	Pass		S-N ACROSS
5/17/25 AM	26/27,28	IL	30	10:00	30	10:05	0	Pass		S-N ACROSS
5/17/25 AM	27/28	IL	30	10:00	30	10:05	0	Pass		24' TIE-IN BUTTSEAM
5/17/25 AM	27,28/29,30	IL	30	10:00	29	10:05	1	Pass		S-N ACROSS
5/17/25 AM	29/30	IL	30	10:00	30	10:05	0	Pass		24' TIE-IN BUTTSEAM
5/17/25 AM	29,30/31,32	IL	30	10:00	29	10:05	1	Pass		S-N ACROSS
5/17/25 AM	31,32/33,34	IL	30	10:05	28	10:10	2	Pass		S-N ACROSS
5/17/25 AM	34/33	IL	30	10:05	30	10:10	0	Pass		24' TIE-IN BUTTSEAM
5/17/25 AM	31/32	IL	30	10:05	30	10:10	0	Pass		24' TIE-IN BUTTSEAM
5/17/25 AM	29/30	IL	30	10:05	30	10:10	0	Pass		24' TIE-IN BUTTSEAM
5/17/25 AM	33,34/35	IL	30	10:05	29	10:10	1	Pass		S-N ACROSS
5/17/25 AM	35/36	IL	30	10:20	30	10:25	0	Pass		S-N ACROSS
5/17/25 AM	36/37	IL	30	10:20	30	10:25	0	Pass		S-N ACROSS
5/17/25 AM	37/38-40	IL	30	10:20	29	10:25	1	Pass		S-N ACROSS
5/17/25 AM	38-40/41,42	IL	30	10:20	29	10:25	1	Pass		S-N ACROSS
5/17/25 AM	39/40	IL	30	10:20	30	10:25	0	Pass		24' TIE-IN BUTTSEAM



**NORTHWEST LININGS &
GEOTEXTILE PRODUCTS, Inc.**

"Helping to Protect the Environment"

21000 77th Avenue South
Kent, WA 98032
(253) 872-0244 / (800) 729-6954
FAX: (253) 872-0245

Date: 5/17/2025
Job #: N23072

Non Destructive Testing Form

Project Name: CVSD GUN CLUB CLEAN UP
Project Location: SPOKANE, WA
Project Description: CAP
Project Manager: CS

Supervisor: R FLACO ARELLANO
Engineer: BRADY/CODY
Contractor: HALME CONSTRUCTION
Contact: BRADY/CODY

Material: 60-MIL HDPE T2

Date/ Time	Panel Numbers	Seamer Initials	Air Pressure Testing					Pass/ Fail	V-Box Pass/ Fail	Comments / Location
			Start Pressure	Start Time	Ending Pressure	End Time	Pressure Loss			
5/17/25 AM	39/38	IL	30	10:35	30	10:40	0	Pass		24' TIE-IN BUTTSEAM
5/17/25 AM	41/42	IL	30	10:35	30	10:40	0	Pass		24' TIE-IN BUTTSEAM
5/17/25 AM	43/44	IL	30	10:35	30	10:40	0	Pass		24' TIE-IN BUTTSEAM
5/17/25 AM	41,42/43,44	IL	30	10:35	30	10:40	1	Pass		S-N ACROSS
5/17/25 AM	43,44/48-45	IL	30	10:35	30	10:40	1	Pass		S-N ACROSS
5/17/25 AM	48/49	IL	30	10:45	30	10:50	0	Pass		S-N ACROSS
5/17/25 AM	49/50,51	IL	30	10:45	30	10:50	0	Pass		S-N ACROSS
5/17/25 AM	50,51/52	IL	30	10:45	30	10:50	0	Pass		S-N ACROSS
5/17/25 AM	50/51	IL	30	10:45	30	10:50	0	Pass		24' TIE-IN BUTTSEAM
5/17/25 AM	48/47	IL	30	10:45	30	10:50	0	Pass		24' TIE-IN BUTTSEAM
5/17/25 AM	47/46	IL	30	10:50	30	10:55	0	Pass		18' TIE-IN BUTTSEAM
5/17/25 AM	46/45	IL	30	10:50	30	10:55	0	Pass		18' TIE-IN BUTTSEAM
5/19/25 AM	52/53,54	GBG	30	9:30	30	9:05	0	Pass		S-N ACROSS
5/19/25 AM	53,54/55,56	GBG	30	9:30	29	9:35	1	Pass		S-N ACROSS
5/19/25 AM	55,56/57,58	GBG	30	9:30	30	9:35	0	Pass		S-N ACROSS
5/19/25 AM	57,58/59	GBG	30	9:30	29	9:35	1	Pass		S-N ACROSS
5/19/25 AM	59/60	GBG	30	9:30	30	9:35	0	Pass		24' TIE-IN BUTTSEAM
5/19/25 AM	57/58	GBG	30	9:45	30	9:50	0	Pass		24' TIE-IN BUTTSEAM
5/19/25 AM	55/56	GBG	30	9:45	30	9:50	0	Pass		24' TIE-IN BUTTSEAM
5/19/25 AM	53/54	GBG	30	9:45	30	9:50	0	Pass		24' TIE-IN BUTTSEAM



**NORTHWEST LININGS &
GEOTEXTILE PRODUCTS, Inc.**
"Helping to Protect the Environment"

21000 77th Avenue South
Kent, WA 98032
(253) 872-0244 / (800) 729-6954
FAX: (253) 872-0245

Date: 5/17/2025
Job #: N23072

Destructive Testing Form

Project Name: CVSD GUN CLUB CLEAN UP Supervisor: R FLACO ARELLANO
Project Location: SPOKANE, WA Engineer: BRADY/CODY
Project Description: CAP Contractor: HALME CONSTRUCTION
Project Manager: CS Contact: BRADY/CODY

Material: 60-MIL HDPE T2

Date/ Time	Panel Numbers	Sample I.D.	Tester Initials	Machine Number	Track Peel Values			Tensile Value			Lab						
					In- side	Out- side	Pass/ Fail	LBS/ Inch	Rate	Pass/ Fail	Pass / Fail	Peel/ Tensile					
5/17/2025 AM	P-13/P-12	DS-1	CS	PT7585	129	133	Pass	2000	2 FM	Pass							
					133	123	Pass	188	2 FM	Pass							
					Comments: 60-MIL HDPE T2							132	124	Pass	167	2 FM	Pass
					146	15	Pass	190	2 FM	Pass							
					127	120	Pass	188	2 FM	Pass							
-----	P-20/P-19	DS-2	CS	PT7585	124	133	Pass	200	2 FM	Pass							
					128	130	Pass	188	2 FM	Pass							
					Comments: _____							140	123	Pass	167	2 FM	Pass
					132	133	Pass	170	2 FM	Pass							
					125	125	Pass	188	2 FM	Pass							
5/17/2025 AM	P-23/P-20	DS-3	CS	PT7585	131	130	Pass	200	2 FM	Pass							
					126	123	Pass	183	2 FM	Pass							
					Comments: 60-MIL HDPE T2							129	133	Pass	181	2 FM	Pass
					133	130	Pass	178	2 FM	Pass							
					125	123	Pass	171	2 FM	Pass							
-----	30/32	DS-4	CS	PT8005	126	122	Pass	167	2 FM	Pass							
					124	123	Pass	166	2 FM	Pass							
					Comments: _____							128	133	Pass	160	2 FM	Pass
					125	133	Pass	177	2 FM	Pass							
					126	120	Pass	181	2 FM	Pass							
5/15/2025 AM	31/33	DS-5	CS	PT8005	133	123	Pass	191	2 FM	Pass							
					120	133	Pass	171	2 FM	Pass							
					Comments: 60-MIL HDPE T2							124	120	Pass	168	2 FM	Pass
					126	126	Pass	181	2 FM	Pass							
					123	130	Pass	180	2 FM	Pass							
-----	33/34	DS-6	CS	PT8005	130	133	Pass	188	2 FM	Pass							
					134	122	Pass	167	2 FM	Pass							
					Comments: _____							133	123	Pass	171	2 FM	Pass
					122	123	Pass	173	2 FM	Pass							
					123	130	Pass	177	2 FM	Pass							
5/17/2025 AM	33/35	DS-7	CS	PT8005	120	123	Pass	192	2 FM	Pass							
					133	130	Pass	174	2 FM	Pass							
					Comments: _____							123	133	Pass	188	2 FM	Pass
					120	129	Pass	190	2 FM	Pass							
					127	133	Pass	193	2 FM	Pass							
5/17/2025 AM	37/38	DS-8	CS	PT8005	122	120	Pass	167	2 FM	Pass							
					123	133	Pass	173	2 FM	Pass							
					Comments: 60-MIL HDPE T2							133	120	Pass	165	2 FM	Pass
					124	123	Pass	168	2 FM	Pass							
					125	122	Pass	167	2 FM	Pass							



**NORTHWEST LININGS &
GEOTEXTILE PRODUCTS, Inc.**
"Helping to Protect the Environment"

21000 77th Avenue South
Kent, WA 98032
(253) 872-0244 / (800) 729-6954
FAX: (253) 872-0245

Date: 5/17/2025
Job #: N23072

Destructive Testing Form

Project Name: CVSD GUN CLUB CLEAN UP Supervisor: R FLACO ARELLANO
 Project Location: SPOKANE, WA Engineer: BRADY/CODY
 Project Description: CAP Contractor: HALME CONSTRUCTION
 Project Manager: CS Contact: BRADY/CODY

Material: 60-MIL HDPE T2

Date/ Time	Panel Numbers	Sample I.D.	Tester Initials	Machine Number	Track Peel Values			Tensile Value			Lab	
					In- side	Out- side	Pass/ Fail	LBS/ Inch	Rate	Pass/ Fail	Pass / Fail	Peel/ Tensile
5/17/2025 AM	41/44	DS-9	CS	PT8005	123	133	Pass	188	2 FM	Pass		
Comments: 60-MIL HDPE T2					120	123	Pass	170	2 FM	Pass		
					132	120	Pass	166	2 FM	Pass		
					129	123	Pass	159	2 FM	Pass		
					127	129	Pass	171	2 FM	Pass		
5/17/2025 AM	49/51	DS-10	CS	PT8005	119	123	Pass	170	2 FM	Pass		
Comments: 60-MIL HDPE T2					123	131	Pass	189	2 FM	Pass		
					131	123	Pass	170	2 FM	Pass		
					130	129	Pass	166	2 FM	Pass		
					123	127	Pass	177	2 FM	Pass		
5/19/2025 AM	54/55	DS-11	CS	PT8005	126	124	Pass	187	2 FM	Pass		
Comments: 60-MIL HDPE T2					123	122	Pass	183	2 FM	Pass		
					121	124	Pass	191	2 FM	Pass		
					124	122	Pass	182	2 FM	Pass		
					127	125	Pass	185	2 FM	Pass		
Comments:												
Comments:												
Comments:												
Comments:												



**NORTHWEST LININGS &
GEOTEXTILE PRODUCTS, Inc.**
"Helping to Protect the Environment"

21000 77th Avenue South
Kent, WA 98032
(253) 872-0244 / (800) 729-6954
FAX: (253) 872-0245

Date: 5/14/2025
Job #: N23072

Repair Report

Project Name: CVSD GUN CLUB CLEAN UP
Project Location: SPOKANE, WA
Project Description: CAP
Project Manager: CS

Supervisor: R FLACO ARELLANO
Engineer: BRADY/CODY
Contractor: HALME CONSTRUCTION
Contact: BRADY/CODY

Date	Repair ID#	Panel Numbers	Extruder Number	Operator Initials	Type of Repair/Detail/Location (I.E.: DS Patch, Rock Hole, Burnout, Failed Seam, ETC.)	V-Box Pass/Fail
5/14/25	R-1	1,2,3/18	6984	RP/GN	2 1'x1' patches over W side tie-in buttseam	Pass
5/14/25	R-2	3,4,5/18	6984	RP/GN	2 1'x1' patches over W side tie-in buttseam	Pass
5/14/25	R-3	5,6,7/18	6984	RP/GN	2 1'x1' patches over W side tie-in buttseam	Pass
5/14/25	R-4	7,8,9/18	6984	RP/GN	2 1'x1' patches over W side tie-in buttseam	Pass
5/14/25	R-5	9,11,12/18	6984	RP/GN	2 1'x1' patches over W side tie-in buttseam	Pass
5/14/25	R-6	9,10/11,12	6984	RP/GN	2 1'x1' patches over 24' tie-in buttseam at W slope	Pass
5/14/25	R-7	12,13/18	6984	RP/GN	DS-1 1'x5' patch over W side tie-in buttseam	Pass
5/14/25	R-8	13/18,17/19	6984	RP/GN	2 1'x1' patches over 24' tie-in buttseam at top	Pass
5/14/25	R-9	13,14,16/17	6984	RP/GN	2 1'x1' patches over W side tie-in buttseam	Pass
5/14/25	R-10	14/15,16	6984	RP/GN	1'x1' patch over NW corner tie-in buttseam	Pass
5/17/25	R-11	19,20/21,23	6984	RP/GN	DS-2 1'x5' and 1'x1' patches over 24' tie-in buttseam	Pass
5/17/25	R-12	23,24/25,26	6984	RP/GN	2 1'x1' patches over 24' tie-in buttseam at top	Pass
5/17/25	R-13	20,22/23,24	6984	RP/GN	DS-3 1'x5' and 1'x1' patches over 24' tie-in buttseam	Pass
5/17/25	R-14	26,27/28,29	6984	RP/GN	2 1'x1' patches over 24' tie-in buttseam at top	Pass
5/17/25	R-15	28,29/30,31	6984	RP/GN	2 1'x1' patches over 24' tie-in buttseam at top	Pass
5/17/25	R-16	30,31/32,33	6984	RP/GN	DS-4-5 1'x5' patches over 24' tie-in buttseam at top	Pass
5/17/25	R-17	31,33/34,35	6984	RP/GN	DS-6-7 1'x5' patches over 24' tie-in buttseam at top	Pass
5/17/25	R-18	37,39/40,42	6984	RP/GN	2 1'x1' patches over 24' tie-in buttseam at top	Pass
5/17/25	R-19	39,41/42,44	6984	RP/GN	2 1'x1' patches over 24' tie-in buttseam at top	Pass
5/17/25	R-20	49,50/51,52	6984	RP/GN	DS-10 1'x5' and 1'x1' patches over 24' tie-in buttseam at top	Pass

APPENDIX L
Stormwater Swale Sizing Technical Memorandum



HALEY & ALDRICH, INC.
505 W. Riverside Avenue
Suite 450
Spokane, WA 99201
509.960.7447

TECHNICAL MEMORANDUM

April 10, 2025
File No. 0202349-002

TO: City of Liberty Lake
Luke Michels, P.E.

C: Central Valley School District; Attn: Jay Rowell
Washington State Department of Ecology; Attn: Ted Uecker

FROM: Haley & Aldrich, Inc.
Breeyn Greer, P.E., Senior Technical Specialist
John Haney, P.E., Senior Environmental Engineer

SUBJECT: Former Gun Club Cleanup Action

Dear Luke Michels:

Haley & Aldrich Inc. (Haley & Aldrich), acting on behalf of the Central Valley School District (CVSD), received your email inquiry regarding the Former Gun Club Cleanup, dated February 21, 2025. The Former Gun Club Cleanup action is permitted under City of Liberty Lake (City) Grading Permit GRD2023-0010, dated March 19, 2024, and Mitigated Determination of Non-Significance LUA2023-0046, dated March 1, 2024. Please see the City's comments listed below and our replies *in italics*.

1. **City Comment:** The [Stormwater Pollution Prevention Plan] provided by the contractor only calls for silt fence at the north end of the site around the repository. Although the site is relatively flat in undisturbed areas, there are very large stockpiles of soil around the perimeter of the site (not sure if they are contaminated or clean). I am concerned about erosion from the stockpiles spreading to the neighboring property from late winter/spring rains. The property to the east is owned by the school district, so I will leave it up to them on whether they would like silt fences placed along the east boundary. I am mostly concerned about the residential properties to the west of the site. Do you agree that silt fences should be installed along the western boundary of the site?

Haley & Aldrich Reply: *The western property perimeter was monitored after the heavy rainfall on Sunday, February 23, 2025, and there was no evidence of offsite stormwater discharge to the west. We concur that offsite sediment discharge would not be tolerated, and, should additional silt fence be warranted in the future, it will be installed at that time.*

2. **City Comment:** I am concerned that there is no discharge for the composite drainage net. Typically, subsurface drainage systems have a pipe and discharge to a disposal location (drywell, infiltration trench, etc.). Based on the relatively shallow geomembrane and the lack of discharge, the cover soil will likely become completely saturated at times from irrigation, snow melt, and rain. This could essentially create an impermeable surface that will create stormwater runoff. The current plans only have a small swale on the west and northwest portions of the repository. My concern is that runoff from the other sides of the repository does not have a safe disposal area. Based on the Spokane Regional Stormwater Manual, could you please provide drainage calcs to show that water from a 10-year storm event will be contained, and that water from a 100-year storm event will have a safe overflow path (at minimum)?

Haley & Aldrich Reply: *A hydrologic analysis of stormwater flow was conducted under the Spokane Regional Stormwater Manual¹ in response to this comment. The hydrologic analysis was completed for the northern portion of the repository (approximately 80,000 square feet) that drains to the north from the repository crown along alignment 2 shown on the Repository Final Grading Plan, Attachment A. The southern portion of the repository flows freely onto CVSD-owned property and is not at risk of leaving the site.*

The SRSW specifies the Natural Resource Conservation Service (NRCS) Type 1A 24-hour design storm with the retention of runoff from the 10-year storm and safe conveyance of runoff from the 100-year storm. We modeled the runoff volume generated using the Curve Number Method in Hydraulic Modeling Software (HMS; Version 4.12) for a variety of potentially applicable curve numbers (74 = U.S. Department of Agriculture [USDA] Soil Type C grass, and 100 = smooth HDPE liner surface); see Attachment B. Conservative curve number 100 was ultimately utilized for design; curve number 100 translates precipitation directly to runoff and HMS modeling was not required. To retain the 10-year storm (395 cubic yards; Attachment C) in the infiltration swale, the swale was expanded along the north side of the repository, between the repository and the northern property line (see Attachment A). The expanded swale will retain greater than 400 cubic yards of stormwater. Safe conveyance of the 100-year storm (modeled at 553 cubic yards) will occur via overland flow in the vicinity.

3. **City Comment:** What compaction is specified for the backfill of excavations that are outside of the repository? Is this compaction sufficient for future building construction?

Haley & Aldrich Reply: *The compaction specified for backfill outside of the repository is 90 percent maximum dry density in accordance with the International Building Code (IBC) Appendix J Section J107.5². Future site use is to be determined by the future owner and compaction will be evaluated at that time. The future developer will likely conduct their own geotechnical evaluation as a component of due diligence in advance of purchase. We understand that City design standards call for 95 percent maximum dry density compaction, below public roadways, sidewalks, and curb and gutter. It will be the responsibility of the future developer to ensure that design standards are met on publicly-owned land.*

¹ Spokane County, City of Spokane, and City of Spokane Valley, 2008. "Spokane Regional Stormwater Manual," April.

² International Code Council (ICC), 2024. "2024 International Building Code."

City of Liberty Lake

April 10, 2025

Page 3

Attachments:

A – Repository Final Grading Plan; Rev 1 Markup (C-307)


B – HMS Output Files for Curve Number 74

C – Hydrologic Volumetric Analysis

https://haleyaldrich.sharepoint.com/sites/CentralValleySchoolDistrict356/Shared Documents/0202349.Gun Club - Bid and Tech Support/-002 Construction Support/Communication/City of Liberty Lake/Final/2025_0410_HAI_CVSD_Memo Response to City of LL_F.docx

NOTES

1. MATERIAL SALVAGED FROM THE TOP 0.0 TO 0.5 FEET OF THE REPOSITORY EXCAVATION SHALL BE USED AS TOPSOIL IN THIS AREA AND IS EXPECTED TO COVER THE TOP 0.2 FEET OF DISTURBANCE.
2. TOPSOIL PLACEMENT OVER THE PROPOSED SOCCER FIELD AND PRACTICE AREA SHALL BE 0.3 FEET THICK WITH THE REMAINING TOPSOIL TO BE PLACED OVER THE SLOPES AND AREA NORTH OF THE PROPOSED SOCCER FIELD.
3. SIDE SLOPE TRANSITION FROM 4H:1V TO 3H:1V AT THE CORNER TO PROVIDE LARGE ENOUGH AREA FOR FUTURE SOCCER FIELD.
4. A SINGLE ROW OF STRAW WATTLES SHALL BE PLACED MIDDLE OF SLOPE ON CONTOUR BETWEEN THE CREST AND TOE OF THE REPOSITORY FILL SLOPE, OR TO THE BOTTOM OF SWALE AS SHOWN.



Project No.:	202349-001
Scale:	SHOWN
Date:	10/17/2023
Drawn By:	ZS/MO
Designed By:	BD
Checked By:	KH
Approved By:	JH/KH
Stamp:	


Rev.	Description	By	Date
1	ISSUED FOR ECOLOGY	BD	05/18/23
0	ISSUED FOR BID	BD	10/18/23

CVSD GUN CLUB
CLEANUP PROJECT
19615 E. SPRAGUE AVE. #9656
SPOKANE VALLEY,
WASHINGTON

**REPOSITORY FINAL
GRADING PLAN**

C-307

Saved by: MOCANNELL
 Date: 10/24/2023 10:00 AM
 Sheet: 12 of 21
 Project: 19615 E SPRAGUE AVE GUN CLUB CLEANUP PROJECT



Project: Site Volume

Simulation Run: 010YR_24HR

Simulation Start: 31 December 2024, 24:00

Simulation End: 1 January 2025, 24:00

HMS Version: 4.12

Executed: 27 February 2025, 17:02

Global Parameter Summary - Subbasin

Area (MI²)

Element Name	Area (MI ²)
Field	0

Loss Rate: SCS

Element Name	Percent Impervious Area	Curve Number
Field	0	74

Transform: SCS

Element Name	Lag	Unitgraph Type
Field	10	Standard

Global Results Summary

Hydrologic Element	Drainage Area (MI ²)	Peak Discharge (CFS)	Time of Peak	Volume (IN)
Field	0	0.04	01Jan2025, 08:55	0.35

Subbasin: Field

Area (MI²) : 0

Loss Rate: Scs

Percent Impervious Area	0
Curve Number	74


Transform: Scs

Lag	10
Unitgraph Type	Standard

Results: Field

Peak Discharge (CFS)	0.04
Time of Peak Discharge	01Jan2025, 08:55
Volume (IN)	0.35
Precipitation Volume (AC - FT)	0.27
Loss Volume (AC - FT)	0.22
Excess Volume (AC - FT)	0.05
Direct Runoff Volume (AC - FT)	0.05
Baseflow Volume (AC - FT)	0

Precipitation and Outflow



Project: Site Volume

Simulation Run: 100YR_24HR

Simulation Start: 31 December 2024, 24:00

Simulation End: 1 January 2025, 24:00

HMS Version: 4.12

Executed: 27 February 2025, 17:02

Global Parameter Summary - Subbasin

Area (MI²)

Element Name	Area (MI ²)
Field	0

Loss Rate: SCS

Element Name	Percent Impervious Area	Curve Number
Field	0	74

Transform: SCS

Element Name	Lag	Unitgraph Type
Field	10	Standard

Global Results Summary

Hydrologic Element	Drainage Area (MI ²)	Peak Discharge (CFS)	Time of Peak	Volume (IN)
Field	0	0.24	01Jan2025, 08:05	0.9

Subbasin: Field

Area (MI²) : 0

Loss Rate: Scs

Percent Impervious Area	0
Curve Number	74


Transform: Scs

Lag	10
Unitgraph Type	Standard

Results: Field

Peak Discharge (CFS)	0.24
Time of Peak Discharge	01Jan2025, 08:05
Volume (IN)	0.9
Precipitation Volume (AC - FT)	0.4
Loss Volume (AC - FT)	0.28
Excess Volume (AC - FT)	0.12
Direct Runoff Volume (AC - FT)	0.12
Baseflow Volume (AC - FT)	0

Precipitation and Outflow



Former Gun Club Stormwater Analysis

Rational Method
 Q (CIA)/Kc
 Area 80000 sf
 0.0025 mi²

Q (cfs) Return (i)
 I (in/hr) 10 2 24-hr
 A (Ac) 100 3 24-hr
 Kc conversion factor 1

Curve No
 74 Class C Grass USDA Web Soil Survey
 61 No Runoff
 99 Parking Lot

Hydraulic Modeling System (HMS) output

	Runoff Depth (in)	Volume (ft ³)	Volume (CY)	
CN 74				
10 (yr)	0.35	2333	86	
100 (yr)	0.9	6000	222	
	Runoff Depth (in)	Storage 20% porosity (ft ³)	Volume (ft ³)	Volume (CY)
CN 100				
10 (yr)	2	0.13	10667	395
100 (yr)	2.8	0.19	14933	553

Current Swale Volume (CY)	240
Approximate Addition (CY)	215
Sum	455 > 395

APPENDIX M
ProUCL Output

	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O
1	UCL Statistics for Data Sets with Non-Detects														
2															
3	User Selected Options														
4	Date/Time of Computation		ProUCL 5.2 5/15/2025 2:14:20 PM												
5	From File		20250515_SO-ProUCL_import_file.xls												
6	Full Precision		OFF												
7	Confidence Coefficient		95%												
8	Number of Bootstrap Operations		2000												
9															
10	1-Methylnaphthalene - Semi-Volatile Organic Compounds (SIM)														
11															
12	General Statistics														
13	Total Number of Observations		41		Number of Distinct Observations		14								
14					Number of Missing Observations		282								
15	Number of Detects		0		Number of Non-Detects		41								
16	Number of Distinct Detects		0		Number of Distinct Non-Detects		14								
17															
18	Warning: All observations are Non-Detects (NDs), therefore all statistics and estimates should also be NDs!														
19	Specifically, sample mean, UCLs, UPLs, and other statistics are also NDs lying below the largest detection limit!														
20	The Project Team may decide to use alternative site specific values to estimate environmental parameters (e.g., EPC, BTV).														
21															
22	The data set for variable 1-Methylnaphthalene - Semi-Volatile Organic Compounds (SIM) was not processed!														
23															
24															
25	2-Methylnaphthalene - Semi-Volatile Organic Compounds (SIM)														
26															
27	General Statistics														
28	Total Number of Observations		41		Number of Distinct Observations		14								
29					Number of Missing Observations		282								
30	Number of Detects		1		Number of Non-Detects		40								
31	Number of Distinct Detects		1		Number of Distinct Non-Detects		13								
32															
33	Warning: Only one distinct data value was detected! ProUCL (or any other software) should not be used on such a data set!														
34	It is suggested to use alternative site specific values determined by the Project Team to estimate environmental parameters (e.g., EPC, BTV).														
35															
36	The data set for variable 2-Methylnaphthalene - Semi-Volatile Organic Compounds (SIM) was not processed!														
37															
38															
39	Arsenic - Inorganic Compounds														
40															
41	General Statistics														
42	Total Number of Observations		84		Number of Distinct Observations		36								
43					Number of Missing Observations		232								
44	Number of Detects		29		Number of Non-Detects		55								
45	Number of Distinct Detects		20		Number of Distinct Non-Detects		27								
46	Minimum Detect		4.2		Minimum Non-Detect		0.84								
47	Maximum Detect		20		Maximum Non-Detect		11								
48	Variance Detects		8.378		Percent Non-Detects		65.48%								
49	Mean Detects		9.072		SD Detects		2.895								
50	Median Detects		9.2		CV Detects		0.319								
51	Skewness Detects		1.576		Kurtosis Detects		6.663								
52	Mean of Logged Detects		2.159		SD of Logged Detects		0.314								
53															
54	Normal GOF Test on Detects Only														
55	Shapiro Wilk Test Statistic		0.834		Shapiro Wilk GOF Test										
56	1% Shapiro Wilk Critical Value		0.898		Detected Data Not Normal at 1% Significance Level										
57	Lilliefors Test Statistic		0.202		Lilliefors GOF Test										
58	1% Lilliefors Critical Value		0.189		Detected Data Not Normal at 1% Significance Level										
59	Detected Data Not Normal at 1% Significance Level														
60															
61	Kaplan-Meier (KM) Statistics using Normal Critical Values and other Nonparametric UCLs														
62	KM Mean		6.614		KM Standard Error of Mean		0.563								
63	90KM SD		3.113		95% KM (BCA) UCL		7.558								
64	95% KM (t) UCL		7.55		95% KM (Percentile Bootstrap) UCL		7.529								
65	95% KM (z) UCL		7.54		95% KM Bootstrap t UCL		7.455								
66	90% KM Chebyshev UCL		8.302		95% KM Chebyshev UCL		9.067								
67	97.5% KM Chebyshev UCL		10.13		99% KM Chebyshev UCL		12.21								
68															
69	Gamma GOF Tests on Detected Observations Only														
70	A-D Test Statistic		1.286		Anderson-Darling GOF Test										
71	5% A-D Critical Value		0.746		Detected Data Not Gamma Distributed at 5% Significance Level										
72	K-S Test Statistic		0.19		Kolmogorov-Smirnov GOF										
73	5% K-S Critical Value		0.162		Detected Data Not Gamma Distributed at 5% Significance Level										
74	Detected Data Not Gamma Distributed at 5% Significance Level														
75															
76	Gamma Statistics on Detected Data Only														
77	k hat (MLE)		10.93		k star (bias corrected MLE)		9.822								
78	Theta hat (MLE)		0.83		Theta star (bias corrected MLE)		0.924								
79	nu hat (MLE)		633.9		nu star (bias corrected)		569.7								
80	Mean (detects)		9.072												
81															
82	Gamma ROS Statistics using Imputed Non-Detects														
83	GROS may not be used when data set has > 50% NDs with many tied observations at multiple DLs														
84	GROS may not be used when kstar of detects is small such as <1.0, especially when the sample size is small (e.g., <15-20)														
85	For such situations, GROS method may yield incorrect values of UCLs and BTVs														

86	This is especially true when the sample size is small.						
87	For gamma distributed detected data, BTVs and UCLs may be computed using gamma distribution on KM estimates						
88	Minimum	2.538	Mean	6.753			
89	Maximum	20	Median	6.062			
90	SD	2.574	CV	0.381			
91	k hat (MLE)	8.393	k star (bias corrected MLE)	8.101			
92	Theta hat (MLE)	0.805	Theta star (bias corrected MLE)	0.834			
93	nu hat (MLE)	1410	nu star (bias corrected)	1361			
94	Adjusted Level of Significance (β)	0.0471					
95	Approximate Chi Square Value (N/A, α)	1276	Adjusted Chi Square Value (N/A, β)	1275			
96	95% Gamma Approximate UCL	7.201	95% Gamma Adjusted UCL	7.209			
97							
98	Estimates of Gamma Parameters using KM Estimates						
99	Mean (KM)	6.614	SD (KM)	3.113			
100	Variance (KM)	9.689	SE of Mean (KM)	0.563			
101	k hat (KM)	4.514	k star (KM)	4.361			
102	nu hat (KM)	758.4	nu star (KM)	732.7			
103	theta hat (KM)	1.465	theta star (KM)	1.517			
104	80% gamma percentile (KM)	9.028	90% gamma percentile (KM)	10.86			
105	95% gamma percentile (KM)	12.53	99% gamma percentile (KM)	16.1			
106							
107	Gamma Kaplan-Meier (KM) Statistics						
108	Approximate Chi Square Value (732.66, α)	670.9	Adjusted Chi Square Value (732.66, β)	669.8			
109	95% KM Approximate Gamma UCL	7.223	95% KM Adjusted Gamma UCL	7.234			
110							
111	Lognormal GOF Test on Detected Observations Only						
112	Shapiro Wilk Test Statistic	0.898	Shapiro Wilk GOF Test				
113	10% Shapiro Wilk Critical Value	0.937	Detected Data Not Lognormal at 10% Significance Level				
114	Lilliefors Test Statistic	0.21	Lilliefors GOF Test				
115	10% Lilliefors Critical Value	0.148	Detected Data Not Lognormal at 10% Significance Level				
116	Detected Data Not Lognormal at 10% Significance Level						
117							
118	Lognormal ROS Statistics Using Imputed Non-Detects						
119	Mean in Original Scale	6.879	Mean in Log Scale	1.878			
120	SD in Original Scale	2.45	SD in Log Scale	0.307			
121	95% t UCL (assumes normality of ROS data)	7.324	95% Percentile Bootstrap UCL	7.349			
122	95% BCA Bootstrap UCL	7.4	95% Bootstrap t UCL	7.406			
123	95% H-UCL (Log ROS)	7.272					
124							
125	Statistics using KM estimates on Logged Data and Assuming Lognormal Distribution						
126	KM Mean (logged)	1.719	KM Geo Mean	5.578			
127	KM SD (logged)	0.695	95% Critical H Value (KM-Log)	1.997			
128	KM Standard Error of Mean (logged)	0.174	95% H-UCL (KM -Log)	8.267			
129	KM SD (logged)	0.695	95% Critical H Value (KM-Log)	1.997			
130	KM Standard Error of Mean (logged)	0.174					
131							
132	DL/2 Statistics						
133	DL/2 Normal		DL/2 Log-Transformed				
134	Mean in Original Scale	6.015	Mean in Log Scale	1.694			
135	SD in Original Scale	2.859	SD in Log Scale	0.474			
136	95% t UCL (Assumes normality)	6.534	95% H-Stat UCL	6.694			
137	DL/2 is not a recommended method, provided for comparisons and historical reasons						
138							
139	Nonparametric Distribution Free UCL Statistics						
140	Data do not follow a Discernible Distribution						
141							
142	Suggested UCL to Use						
143	95% KM (t) UCL	7.55					
144							
145	Note: Suggestions regarding the selection of a 95% UCL are provided to help the user to select the most appropriate 95% UCL.						
146	Recommendations are based upon data size, data distribution, and skewness using results from simulation studies.						
147	However, simulations results will not cover all Real World data sets; for additional insight the user may want to consult a statistician.						
148							
149	Benzo(a)anthracene - Semi-Volatile Organic Compounds (SIM)						
150							
151	General Statistics						
152	Total Number of Observations	41	Number of Distinct Observations	34			
153			Number of Missing Observations	282			
154	Number of Detects	38	Number of Non-Detects	3			316
155	Number of Distinct Detects	32	Number of Distinct Non-Detects	2			
156	Minimum Detect	0.0043	Minimum Non-Detect	0.0055			
157	Maximum Detect	0.1	Maximum Non-Detect	0.006			
158	Variance Detects	4.8551E-4	Percent Non-Detects	7.317%			
159	Mean Detects	0.0314	SD Detects	0.022			
160	Median Detects	0.0255	CV Detects	0.703			
161	Skewness Detects	1.06	Kurtosis Detects	1.143			
162	Mean of Logged Detects	-3.742	SD of Logged Detects	0.823			
163							
164	Normal GOF Test on Detects Only						
165	Shapiro Wilk Test Statistic	0.915	Shapiro Wilk GOF Test				
166	1% Shapiro Wilk Critical Value	0.916	Detected Data Not Normal at 1% Significance Level				
167	Lilliefors Test Statistic	0.154	Lilliefors GOF Test				
168	1% Lilliefors Critical Value	0.165	Detected Data appear Normal at 1% Significance Level				
169	Detected Data appear Approximate Normal at 1% Significance Level						
170							

A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	
171	Kaplan-Meier (KM) Statistics using Normal Critical Values and other Nonparametric UCLs														
172		KM Mean	0.0294			KM Standard Error of Mean	0.00349								
173		90KM SD	0.0221			95% KM (BCA) UCL	0.0351								
174		95% KM (t) UCL	0.0353			95% KM (Percentile Bootstrap) UCL	0.0351								
175		95% KM (z) UCL	0.0351			95% KM Bootstrap t UCL	0.0361								
176		90% KM Chebyshev UCL	0.0399			95% KM Chebyshev UCL	0.0446								
177		97.5% KM Chebyshev UCL	0.0512			99% KM Chebyshev UCL	0.0641								
178															
179	Gamma GOF Tests on Detected Observations Only														
180		A-D Test Statistic	0.264			Anderson-Darling GOF Test									
181		5% A-D Critical Value	0.76			Detected data appear Gamma Distributed at 5% Significance Level									
182		K-S Test Statistic	0.0802			Kolmogorov-Smirnov GOF									
183		5% K-S Critical Value	0.145			Detected data appear Gamma Distributed at 5% Significance Level									
184	Detected data appear Gamma Distributed at 5% Significance Level														
185															
186	Gamma Statistics on Detected Data Only														
187		k hat (MLE)	1.936			k star (bias corrected MLE)	1.801								
188		Theta hat (MLE)	0.0162			Theta star (bias corrected MLE)	0.0174								
189		nu hat (MLE)	147.2			nu star (bias corrected)	136.9								
190		Mean (detects)	0.0314												
191															
192	Gamma ROS Statistics using Imputed Non-Detects														
193	GROS may not be used when data set has > 50% NDs with many tied observations at multiple DLs														
194	GROS may not be used when kstar of detects is small such as <1.0, especially when the sample size is small (e.g., <15-20)														
195	For such situations, GROS method may yield incorrect values of UCLs and BTVs														
196	This is especially true when the sample size is small.														
197	For gamma distributed detected data, BTVs and UCLs may be computed using gamma distribution on KM estimates														
198		Minimum	0.0043			Mean	0.0298								
199		Maximum	0.1			Median	0.025								
200		SD	0.0219			CV	0.736								
201		k hat (MLE)	1.862			k star (bias corrected MLE)	1.742								
202		Theta hat (MLE)	0.016			Theta star (bias corrected MLE)	0.0171								
203		nu hat (MLE)	152.7			nu star (bias corrected)	142.9								
204		Adjusted Level of Significance (β)	0.0441												
205		Approximate Chi Square Value (142.86, α)	116.2			Adjusted Chi Square Value (142.86, β)	115.4								
206		95% Gamma Approximate UCL	0.0366			95% Gamma Adjusted UCL	0.0369								
207															
208	Estimates of Gamma Parameters using KM Estimates														
209		Mean (KM)	0.0294			SD (KM)	0.0221								
210		Variance (KM)	4.8704E-4			SE of Mean (KM)	0.00349								
211		k hat (KM)	1.773			k star (KM)	1.659								
212		nu hat (KM)	145.4			nu star (KM)	136.1								
213		theta hat (KM)	0.0166			theta star (KM)	0.0177								
214		80% gamma percentile (KM)	0.045			90% gamma percentile (KM)	0.0598								
215		95% gamma percentile (KM)	0.074			99% gamma percentile (KM)	0.106								
216															
217	Gamma Kaplan-Meier (KM) Statistics														
218		Approximate Chi Square Value (136.08, α)	110.1			Adjusted Chi Square Value (136.08, β)	109.3								
219		95% KM Approximate Gamma UCL	0.0363			95% KM Adjusted Gamma UCL	0.0366								
220															
221	Lognormal GOF Test on Detected Observations Only														
222		Shapiro Wilk Test Statistic	0.946			Shapiro Wilk GOF Test									
223		10% Shapiro Wilk Critical Value	0.947			Detected Data Not Lognormal at 10% Significance Level									
224		Lilliefors Test Statistic	0.129			Lilliefors GOF Test									
225		10% Lilliefors Critical Value	0.13			Detected Data appear Lognormal at 10% Significance Level									
226	Detected Data appear Approximate Lognormal at 10% Significance Level														
227															
228	Lognormal ROS Statistics Using Imputed Non-Detects														
229		Mean in Original Scale	0.0295			Mean in Log Scale	-3.849								
230		SD in Original Scale	0.0223			SD in Log Scale	0.881								
231		95% t UCL (assumes normality of ROS data)	0.0353			95% Percentile Bootstrap UCL	0.0352								
232		95% BCA Bootstrap UCL	0.0354			95% Bootstrap t UCL	0.0359								
233		95% H-UCL (Log ROS)	0.0428												
234															
235	Statistics using KM estimates on Logged Data and Assuming Lognormal Distribution														
236		KM Mean (logged)	-3.864			KM Geo Mean	0.021								
237		KM SD (logged)	0.894			95% Critical H Value (KM-Log)	2.24								
238		KM Standard Error of Mean (logged)	0.141			95% H-UCL (KM -Log)	0.0429								
239		KM SD (logged)	0.894			95% Critical H Value (KM-Log)	2.24								
240		KM Standard Error of Mean (logged)	0.141												
241															
242	DL/2 Statistics														
243	DL/2 Normal						DL/2 Log-Transformed								
244		Mean in Original Scale	0.0293			Mean in Log Scale	-3.896								
245		SD in Original Scale	0.0225			SD in Log Scale	0.965								
246		95% t UCL (Assumes normality)	0.0352			95% H-Stat UCL	0.0461								
247	DL/2 is not a recommended method, provided for comparisons and historical reasons														
248															
249	Nonparametric Distribution Free UCL Statistics														
250	Detected Data appear Approximate Normal Distributed at 1% Significance Level														
251															
252	Suggested UCL to Use														
253		95% KM (t) UCL	0.0353												
254															
255	When a data set follows an approximate distribution passing only one of the GOF tests,														

A	B	C	D	E	F	G	H	I	J	K	L	M	N	O		
256	it is suggested to use a UCL based upon a distribution passing both GOF tests in ProUCL															
257																
258	Note: Suggestions regarding the selection of a 95% UCL are provided to help the user to select the most appropriate 95% UCL.															
259	Recommendations are based upon data size, data distribution, and skewness using results from simulation studies.															
260	However, simulations results will not cover all Real World data sets; for additional insight the user may want to consult a statistician.															
261																
262	Benzo(a)pyrene - Semi-Volatile Organic Compounds (SIM)															
263																
264	General Statistics															
265	Total Number of Observations		41	Number of Distinct Observations		35										
266				Number of Missing Observations		282										
267	Number of Detects		39	Number of Non-Detects		2										
268	Number of Distinct Detects		33	Number of Distinct Non-Detects		2										
269	Minimum Detect		0.0061	Minimum Non-Detect		0.006										
270	Maximum Detect		0.089	Maximum Non-Detect		0.05										
271	Variance Detects		5.6599E-4	Percent Non-Detects		4.878%										
272	Mean Detects		0.0404	SD Detects		0.0238										
273	Median Detects		0.038	CV Detects		0.589										
274	Skewness Detects		0.418	Kurtosis Detects		-0.679										
275	Mean of Logged Detects		-3.438	SD of Logged Detects		0.763										
276																
277	Normal GOF Test on Detects Only															
278	Shapiro Wilk Test Statistic		0.939	Shapiro Wilk GOF Test												
279	1% Shapiro Wilk Critical Value		0.917	Detected Data appear Normal at 1% Significance Level												
280	Lilliefors Test Statistic		0.13	Lilliefors GOF Test												
281	1% Lilliefors Critical Value		0.163	Detected Data appear Normal at 1% Significance Level												
282	Detected Data appear Normal at 1% Significance Level															
283																
284	Kaplan-Meier (KM) Statistics using Normal Critical Values and other Nonparametric UCLs															
285	KM Mean		0.0392	KM Standard Error of Mean		0.00376										
286	90KM SD		0.0237	95% KM (BCA) UCL		0.045										
287	95% KM (t) UCL		0.0455	95% KM (Percentile Bootstrap) UCL		0.0452										
288	95% KM (z) UCL		0.0454	95% KM Bootstrap t UCL		0.046										
289	90% KM Chebyshev UCL		0.0505	95% KM Chebyshev UCL		0.0556										
290	97.5% KM Chebyshev UCL		0.0627	99% KM Chebyshev UCL		0.0766										
291																
292	Gamma GOF Tests on Detected Observations Only															
293	A-D Test Statistic		0.606	Anderson-Darling GOF Test												
294	5% A-D Critical Value		0.758	Detected data appear Gamma Distributed at 5% Significance Level												
295	K-S Test Statistic		0.135	Kolmogorov-Smirnov GOF												
296	5% K-S Critical Value		0.143	Detected data appear Gamma Distributed at 5% Significance Level												
297	Detected data appear Gamma Distributed at 5% Significance Level															
298																
299	Gamma Statistics on Detected Data Only															
300	k hat (MLE)		2.343	k star (bias corrected MLE)		2.18										
301	Theta hat (MLE)		0.0172	Theta star (bias corrected MLE)		0.0185										
302	nu hat (MLE)		182.8	nu star (bias corrected)		170.1										
303	Mean (detects)		0.0404													
304																
305	Gamma ROS Statistics using Imputed Non-Detects															
306	GROS may not be used when data set has > 50% NDs with many tied observations at multiple DLs															
307	GROS may not be used when kstar of detects is small such as <1.0, especially when the sample size is small (e.g., <15-20)															
308	For such situations, GROS method may yield incorrect values of UCLs and BTVs															
309	This is especially true when the sample size is small.															
310	For gamma distributed detected data, BTVs and UCLs may be computed using gamma distribution on KM estimates															
311	Minimum		0.0061	Mean		0.0393										
312	Maximum		0.089	Median		0.037										
313	SD		0.0238	CV		0.605										
314	k hat (MLE)		2.286	k star (bias corrected MLE)		2.135										
315	Theta hat (MLE)		0.0172	Theta star (bias corrected MLE)		0.0184										
316	nu hat (MLE)		187.5	nu star (bias corrected)		175.1										
317	Adjusted Level of Significance (β)		0.0441													
318	Approximate Chi Square Value (175.08, α)		145.5	Adjusted Chi Square Value (175.08, β)		144.5										
319	95% Gamma Approximate UCL		0.0473	95% Gamma Adjusted UCL		0.0476										
320																
321	Estimates of Gamma Parameters using KM Estimates															
322	Mean (KM)		0.0392	SD (KM)		0.0237										
323	Variance (KM)		5.6110E-4	SE of Mean (KM)		0.00376										
324	k hat (KM)		2.736	k star (KM)		2.552										
325	nu hat (KM)		224.4	nu star (KM)		209.3										
326	theta hat (KM)		0.0143	theta star (KM)		0.0154										
327	80% gamma percentile (KM)		0.057	90% gamma percentile (KM)		0.072										
328	95% gamma percentile (KM)		0.0862	99% gamma percentile (KM)		0.117										
329																
330	Gamma Kaplan-Meier (KM) Statistics															
331	Approximate Chi Square Value (209.29, α)		176.8	Adjusted Chi Square Value (209.29, β)		175.7										
332	95% KM Approximate Gamma UCL		0.0464	95% KM Adjusted Gamma UCL		0.0467										
333																
334	Lognormal GOF Test on Detected Observations Only															
335	Shapiro Wilk Test Statistic		0.899	Shapiro Wilk GOF Test												
336	10% Shapiro Wilk Critical Value		0.948	Detected Data Not Lognormal at 10% Significance Level												
337	Lilliefors Test Statistic		0.175	Lilliefors GOF Test												
338	10% Lilliefors Critical Value		0.129	Detected Data Not Lognormal at 10% Significance Level												
339	Detected Data Not Lognormal at 10% Significance Level															
340																

A	B	C	D	E	F	G	H	I	J	K	L	M	N	O
341	Lognormal ROS Statistics Using Imputed Non-Detects													
342	Mean in Original Scale		0.0391	Mean in Log Scale		-3.492								
343	SD in Original Scale		0.024	SD in Log Scale		0.799								
344	95% t UCL (assumes normality of ROS data)		0.0454	95% Percentile Bootstrap UCL		0.0451								
345	95% BCA Bootstrap UCL		0.0451	95% Bootstrap t UCL		0.0456								
346	95% H-UCL (Log ROS)		0.0549											
347														
348	Statistics using KM estimates on Logged Data and Assuming Lognormal Distribution													
349	KM Mean (logged)		-3.489	KM Geo Mean		0.0305								
350	KM SD (logged)		0.788	95% Critical H Value (KM-Log)		2.135								
351	KM Standard Error of Mean (logged)		0.126	95% H-UCL (KM -Log)		0.0544								
352	KM SD (logged)		0.788	95% Critical H Value (KM-Log)		2.135								
353	KM Standard Error of Mean (logged)		0.126											
354														
355	DL/2 Statistics													
356	DL/2 Normal			DL/2 Log-Transformed										
357	Mean in Original Scale		0.0391	Mean in Log Scale		-3.502								
358	SD in Original Scale		0.024	SD in Log Scale		0.831								
359	95% t UCL (Assumes normality)		0.0454	95% H-Stat UCL		0.0567								
360	DL/2 is not a recommended method, provided for comparisons and historical reasons													
361														
362	Nonparametric Distribution Free UCL Statistics													
363	Detected Data appear Normal Distributed at 1% Significance Level													
364														
365	Suggested UCL to Use													
366	95% KM (t) UCL		0.0455											
367														
368	Note: Suggestions regarding the selection of a 95% UCL are provided to help the user to select the most appropriate 95% UCL.													
369	Recommendations are based upon data size, data distribution, and skewness using results from simulation studies.													
370	However, simulations results will not cover all Real World data sets; for additional insight the user may want to consult a statistician.													
371														
372	Benzo(b)fluoranthene - Semi-Volatile Organic Compounds (SIM)													
373														
374	General Statistics													
375	Total Number of Observations		41	Number of Distinct Observations		34								
376				Number of Missing Observations		282								
377	Number of Detects		39	Number of Non-Detects		2								
378	Number of Distinct Detects		33	Number of Distinct Non-Detects		2								
379	Minimum Detect		0.0061	Minimum Non-Detect		0.0054								
380	Maximum Detect		0.11	Maximum Non-Detect		0.05								
381	Variance Detects		7.9504E-4	Percent Non-Detects		4.878%								
382	Mean Detects		0.0433	SD Detects		0.0282								
383	Median Detects		0.04	CV Detects		0.651								
384	Skewness Detects		0.782	Kurtosis Detects		0.0382								
385	Mean of Logged Detects		-3.392	SD of Logged Detects		0.789								
386														
387	Normal GOF Test on Detects Only													
388	Shapiro Wilk Test Statistic		0.925	Shapiro Wilk GOF Test										
389	1% Shapiro Wilk Critical Value		0.917	Detected Data appear Normal at 1% Significance Level										
390	Lilliefors Test Statistic		0.123	Lilliefors GOF Test										
391	1% Lilliefors Critical Value		0.163	Detected Data appear Normal at 1% Significance Level										
392	Detected Data appear Normal at 1% Significance Level													
393														
394	Kaplan-Meier (KM) Statistics using Normal Critical Values and other Nonparametric UCLs													
395	KM Mean		0.042	KM Standard Error of Mean		0.00444								
396	90KM SD		0.028	95% KM (BCA) UCL		0.0491								
397	95% KM (t) UCL		0.0495	95% KM (Percentile Bootstrap) UCL		0.0491								
398	95% KM (z) UCL		0.0493	95% KM Bootstrap t UCL		0.0501								
399	90% KM Chebyshev UCL		0.0553	95% KM Chebyshev UCL		0.0613								
400	97.5% KM Chebyshev UCL		0.0697	99% KM Chebyshev UCL		0.0862								
401														
402	Gamma GOF Tests on Detected Observations Only													
403	A-D Test Statistic		0.294	Anderson-Darling GOF Test										
404	5% A-D Critical Value		0.759	Detected data appear Gamma Distributed at 5% Significance Level										
405	K-S Test Statistic		0.0836	Kolmogorov-Smirnov GOF										
406	5% K-S Critical Value		0.143	Detected data appear Gamma Distributed at 5% Significance Level										
407	Detected data appear Gamma Distributed at 5% Significance Level													
408														
409	Gamma Statistics on Detected Data Only													
410	k hat (MLE)		2.127	k star (bias corrected MLE)		1.98								
411	Theta hat (MLE)		0.0204	Theta star (bias corrected MLE)		0.0219								
412	nu hat (MLE)		165.9	nu star (bias corrected)		154.4								
413	Mean (detects)		0.0433											
414														
415	Gamma ROS Statistics using Imputed Non-Detects													
416	GROS may not be used when data set has > 50% NDs with many tied observations at multiple DLs													
417	GROS may not be used when kstar of detects is small such as <1.0, especially when the sample size is small (e.g., <15-20)													
418	For such situations, GROS method may yield incorrect values of UCLs and BTVs													
419	This is especially true when the sample size is small.													
420	For gamma distributed detected data, BTVs and UCLs may be computed using gamma distribution on KM estimates													
421	Minimum		0.0061	Mean		0.0421								
422	Maximum		0.11	Median		0.038								
423	SD		0.0281	CV		0.668								
424	k hat (MLE)		2.073	k star (bias corrected MLE)		1.937								
425	Theta hat (MLE)		0.0203	Theta star (bias corrected MLE)		0.0217								

	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O
426					nu hat (MLE)	170					nu star (bias corrected)	158.9			
427					Adjusted Level of Significance (β)	0.0441									
428					Approximate Chi Square Value (158.86, α)	130.7					Adjusted Chi Square Value (158.86, β)	129.8			
429					95% Gamma Approximate UCL	0.0511					95% Gamma Adjusted UCL	0.0515			
430															
431					Estimates of Gamma Parameters using KM Estimates										
432					Mean (KM)	0.042					SD (KM)	0.028			
433					Variance (KM)	7.8193E-4					SE of Mean (KM)	0.00444			
434					k hat (KM)	2.255					k star (KM)	2.106			
435					nu hat (KM)	184.9					nu star (KM)	172.7			
436					theta hat (KM)	0.0186					theta star (KM)	0.0199			
437					80% gamma percentile (KM)	0.0625					90% gamma percentile (KM)	0.0807			
438					95% gamma percentile (KM)	0.098					99% gamma percentile (KM)	0.136			
439															
440					Gamma Kaplan-Meier (KM) Statistics										
441					Approximate Chi Square Value (172.68, α)	143.3					Adjusted Chi Square Value (172.68, β)	142.3			
442					95% KM Approximate Gamma UCL	0.0506					95% KM Adjusted Gamma UCL	0.0509			
443															
444					Lognormal GOF Test on Detected Observations Only										
445					Shapiro Wilk Test Statistic	0.933					Shapiro Wilk GOF Test				
446					10% Shapiro Wilk Critical Value	0.948					Detected Data Not Lognormal at 10% Significance Level				
447					Lilliefors Test Statistic	0.131					Lilliefors GOF Test				
448					10% Lilliefors Critical Value	0.129					Detected Data Not Lognormal at 10% Significance Level				
449					Detected Data Not Lognormal at 10% Significance Level										
450															
451					Lognormal ROS Statistics Using Imputed Non-Detects										
452					Mean in Original Scale	0.0419					Mean in Log Scale	-3.45			
453					SD in Original Scale	0.0283					SD in Log Scale	0.829			
454					95% t UCL (assumes normality of ROS data)	0.0493					95% Percentile Bootstrap UCL	0.0492			
455					95% BCA Bootstrap UCL	0.0495					95% Bootstrap t UCL	0.0501			
456					95% H-UCL (Log ROS)	0.0596									
457															
458					Statistics using KM estimates on Logged Data and Assuming Lognormal Distribution										
459					KM Mean (logged)	-3.448					KM Geo Mean	0.0318			
460					KM SD (logged)	0.82					95% Critical H Value (KM-Log)	2.165			
461					KM Standard Error of Mean (logged)	0.131					95% H-UCL (KM -Log)	0.059			
462					KM SD (logged)	0.82					95% Critical H Value (KM-Log)	2.165			
463					KM Standard Error of Mean (logged)	0.131									
464															
465					DL/2 Statistics										
466					DL/2 Normal						DL/2 Log-Transformed				
467					Mean in Original Scale	0.0419					Mean in Log Scale	-3.461			
468					SD in Original Scale	0.0283					SD in Log Scale	0.865			
469					95% t UCL (Assumes normality)	0.0493					95% H-Stat UCL	0.0617			
470					DL/2 is not a recommended method, provided for comparisons and historical reasons										
471															
472					Nonparametric Distribution Free UCL Statistics										
473					Detected Data appear Normal Distributed at 1% Significance Level										
474															
475					Suggested UCL to Use										
476					95% KM (t) UCL	0.0495									
477															
478					Note: Suggestions regarding the selection of a 95% UCL are provided to help the user to select the most appropriate 95% UCL.										
479					Recommendations are based upon data size, data distribution, and skewness using results from simulation studies.										
480					However, simulations results will not cover all Real World data sets; for additional insight the user may want to consult a statistician.										
481															
482					Benzo(k)fluoranthene - Semi-Volatile Organic Compounds (SIM)										
483															
484					General Statistics										
485					Total Number of Observations	41					Number of Distinct Observations	28			
486											Number of Missing Observations	282			
487					Number of Detects	32					Number of Non-Detects	9			
488					Number of Distinct Detects	23					Number of Distinct Non-Detects	5			
489					Minimum Detect	0.0026					Minimum Non-Detect	0.005			
490					Maximum Detect	0.037					Maximum Non-Detect	0.05			
491					Variance Detects	7.7266E-5					Percent Non-Detects	21.95%			
492					Mean Detects	0.0156					SD Detects	0.00879			
493					Median Detects	0.0145					CV Detects	0.563			
494					Skewness Detects	0.884					Kurtosis Detects	0.422			
495					Mean of Logged Detects	-4.331					SD of Logged Detects	0.631			
496															
497					Normal GOF Test on Detects Only										
498					Shapiro Wilk Test Statistic	0.921					Shapiro Wilk GOF Test				
499					1% Shapiro Wilk Critical Value	0.904					Detected Data appear Normal at 1% Significance Level				
500					Lilliefors Test Statistic	0.142					Lilliefors GOF Test				
501					1% Lilliefors Critical Value	0.18					Detected Data appear Normal at 1% Significance Level				
502					Detected Data appear Normal at 1% Significance Level										
503															
504					Kaplan-Meier (KM) Statistics using Normal Critical Values and other Nonparametric UCLs										
505					KM Mean	0.014					KM Standard Error of Mean	0.00147			
506					90KM SD	0.00888					95% KM (BCA) UCL	0.0165			
507					95% KM (t) UCL	0.0165					95% KM (Percentile Bootstrap) UCL	0.0163			
508					95% KM (z) UCL	0.0165					95% KM Bootstrap t UCL	0.0166			
509					90% KM Chebyshev UCL	0.0185					95% KM Chebyshev UCL	0.0205			
510					97.5% KM Chebyshev UCL	0.0232					99% KM Chebyshev UCL	0.0287			

	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O
511															
512	Gamma GOF Tests on Detected Observations Only														
513	A-D Test Statistic		0.323	Anderson-Darling GOF Test											
514	5% A-D Critical Value		0.753	Detected data appear Gamma Distributed at 5% Significance Level											
515	K-S Test Statistic		0.127	Kolmogorov-Smirnov GOF											
516	5% K-S Critical Value		0.157	Detected data appear Gamma Distributed at 5% Significance Level											
517	Detected data appear Gamma Distributed at 5% Significance Level														
518															
519	Gamma Statistics on Detected Data Only														
520	k hat (MLE)		3.097	k star (bias corrected MLE)		2.827									
521	Theta hat (MLE)		0.00504	Theta star (bias corrected MLE)		0.00552									
522	nu hat (MLE)		198.2	nu star (bias corrected)		180.9									
523	Mean (detects)		0.0156												
524															
525	Gamma ROS Statistics using Imputed Non-Detects														
526	GROS may not be used when data set has > 50% NDs with many tied observations at multiple DLs														
527	GROS may not be used when kstar of detects is small such as <1.0, especially when the sample size is small (e.g., <15-20)														
528	For such situations, GROS method may yield incorrect values of UCLs and BTVs														
529	This is especially true when the sample size is small.														
530	For gamma distributed detected data, BTVs and UCLs may be computed using gamma distribution on KM estimates														
531	Minimum		0.0026	Mean		0.0147									
532	Maximum		0.037	Median		0.014									
533	SD		0.00802	CV		0.544									
534	k hat (MLE)		3.609	k star (bias corrected MLE)		3.361									
535	Theta hat (MLE)		0.00408	Theta star (bias corrected MLE)		0.00438									
536	nu hat (MLE)		295.9	nu star (bias corrected)		275.6									
537	Adjusted Level of Significance (β)		0.0441												
538	Approximate Chi Square Value (275.61, α)		238.2	Adjusted Chi Square Value (275.61, β)		236.9									
539	95% Gamma Approximate UCL		0.017	95% Gamma Adjusted UCL		0.0171									
540															
541	Estimates of Gamma Parameters using KM Estimates														
542	Mean (KM)		0.014	SD (KM)		0.00888									
543	Variance (KM)		7.8806E-5	SE of Mean (KM)		0.00147									
544	k hat (KM)		2.5	k star (KM)		2.333									
545	nu hat (KM)		205	nu star (KM)		191.3									
546	theta hat (KM)		0.00561	theta star (KM)		0.00602									
547	80% gamma percentile (KM)		0.0206	90% gamma percentile (KM)		0.0263									
548	95% gamma percentile (KM)		0.0317	99% gamma percentile (KM)		0.0436									
549															
550	Gamma Kaplan-Meier (KM) Statistics														
551	Approximate Chi Square Value (191.33, α)		160.3	Adjusted Chi Square Value (191.33, β)		159.3									
552	95% KM Approximate Gamma UCL		0.0167	95% KM Adjusted Gamma UCL		0.0169									
553															
554	Lognormal GOF Test on Detected Observations Only														
555	Shapiro Wilk Test Statistic		0.953	Shapiro Wilk GOF Test											
556	10% Shapiro Wilk Critical Value		0.941	Detected Data appear Lognormal at 10% Significance Level											
557	Lilliefors Test Statistic		0.164	Lilliefors GOF Test											
558	10% Lilliefors Critical Value		0.142	Detected Data Not Lognormal at 10% Significance Level											
559	Detected Data appear Approximate Lognormal at 10% Significance Level														
560															
561	Lognormal ROS Statistics Using Imputed Non-Detects														
562	Mean in Original Scale		0.014	Mean in Log Scale		-4.464									
563	SD in Original Scale		0.00859	SD in Log Scale		0.659									
564	95% t UCL (assumes normality of ROS data)		0.0162	95% Percentile Bootstrap UCL		0.0162									
565	95% BCA Bootstrap UCL		0.0164	95% Bootstrap t UCL		0.0167									
566	95% H-UCL (Log ROS)		0.0177												
567															
568	Statistics using KM estimates on Logged Data and Assuming Lognormal Distribution														
569	KM Mean (logged)		-4.501	KM Geo Mean		0.0111									
570	KM SD (logged)		0.739	95% Critical H Value (KM-Log)		2.089									
571	KM Standard Error of Mean (logged)		0.125	95% H-UCL (KM -Log)		0.0186									
572	KM SD (logged)		0.739	95% Critical H Value (KM-Log)		2.089									
573	KM Standard Error of Mean (logged)		0.125												
574															
575	DL/2 Statistics														
576	DL/2 Normal			DL/2 Log-Transformed											
577	Mean in Original Scale		0.0146	Mean in Log Scale		-4.457									
578	SD in Original Scale		0.00897	SD in Log Scale		0.749									
579	95% t UCL (Assumes normality)		0.0169	95% H-Stat UCL		0.0197									
580	DL/2 is not a recommended method, provided for comparisons and historical reasons														
581															
582	Nonparametric Distribution Free UCL Statistics														
583	Detected Data appear Normal Distributed at 1% Significance Level														
584															
585	Suggested UCL to Use														
586	95% KM (t) UCL		0.0165												
587															
588	Note: Suggestions regarding the selection of a 95% UCL are provided to help the user to select the most appropriate 95% UCL.														
589	Recommendations are based upon data size, data distribution, and skewness using results from simulation studies.														
590	However, simulations results will not cover all Real World data sets; for additional insight the user may want to consult a statistician.														
591															
592	Chrysene - Semi-Volatile Organic Compounds (SIM)														
593															
594	General Statistics														
595	Total Number of Observations		41	Number of Distinct Observations		34									

596										Number of Missing Observations	282						
597					Number of Detects	40				Number of Non-Detects	1						
598					Number of Distinct Detects	33				Number of Distinct Non-Detects	1						
599					Minimum Detect	0.0047				Minimum Non-Detect	0.0054						
600					Maximum Detect	0.083				Maximum Non-Detect	0.0054						
601					Variance Detects	4.7346E-4				Percent Non-Detects	2.439%						
602					Mean Detects	0.0347				SD Detects	0.0218						
603					Median Detects	0.031				CV Detects	0.627						
604					Skewness Detects	0.668				Kurtosis Detects	-0.293						
605					Mean of Logged Detects	-3.601				SD of Logged Detects	0.772						
606																	
607					Normal GOF Test on Detects Only												
608					Shapiro Wilk Test Statistic	0.926				Shapiro Wilk GOF Test							
609					1% Shapiro Wilk Critical Value	0.919				Detected Data appear Normal at 1% Significance Level							
610					Lilliefors Test Statistic	0.163				Lilliefors GOF Test							
611					1% Lilliefors Critical Value	0.162				Detected Data Not Normal at 1% Significance Level							
612					Detected Data appear Approximate Normal at 1% Significance Level												
613																	
614					Kaplan-Meier (KM) Statistics using Normal Critical Values and other Nonparametric UCLs												
615					KM Mean	0.034				KM Standard Error of Mean	0.00343						
616					90KM SD	0.0217				95% KM (BCA) UCL	0.0395						
617					95% KM (t) UCL	0.0398				95% KM (Percentile Bootstrap) UCL	0.0394						
618					95% KM (z) UCL	0.0396				95% KM Bootstrap t UCL	0.0403						
619					90% KM Chebyshev UCL	0.0443				95% KM Chebyshev UCL	0.049						
620					97.5% KM Chebyshev UCL	0.0554				99% KM Chebyshev UCL	0.0682						
621																	
622					Gamma GOF Tests on Detected Observations Only												
623					A-D Test Statistic	0.421				Anderson-Darling GOF Test							
624					5% A-D Critical Value	0.758				Detected data appear Gamma Distributed at 5% Significance Level							
625					K-S Test Statistic	0.127				Kolmogorov-Smirnov GOF							
626					5% K-S Critical Value	0.141				Detected data appear Gamma Distributed at 5% Significance Level							
627					Detected data appear Gamma Distributed at 5% Significance Level												
628																	
629					Gamma Statistics on Detected Data Only												
630					k hat (MLE)	2.234				k star (bias corrected MLE)	2.083						
631					Theta hat (MLE)	0.0155				Theta star (bias corrected MLE)	0.0167						
632					nu hat (MLE)	178.7				nu star (bias corrected)	166.7						
633					Mean (detects)	0.0347											
634																	
635					Gamma ROS Statistics using Imputed Non-Detects												
636					GROS may not be used when data set has > 50% NDs with many tied observations at multiple DLs												
637					GROS may not be used when kstar of detects is small such as <1.0, especially when the sample size is small (e.g., <15-20)												
638					For such situations, GROS method may yield incorrect values of UCLs and BTVs												
639					This is especially true when the sample size is small.												
640					For gamma distributed detected data, BTVs and UCLs may be computed using gamma distribution on KM estimates												
641					Minimum	0.0047				Mean	0.0341						
642					Maximum	0.083				Median	0.031						
643					SD	0.0218				CV	0.64						
644					k hat (MLE)	2.175				k star (bias corrected MLE)	2.032						
645					Theta hat (MLE)	0.0157				Theta star (bias corrected MLE)	0.0168						
646					nu hat (MLE)	178.3				nu star (bias corrected)	166.6						
647					Adjusted Level of Significance (β)	0.0441											
648					Approximate Chi Square Value (166.63, α)	137.8				Adjusted Chi Square Value (166.63, β)	136.8						
649					95% Gamma Approximate UCL	0.0413				95% Gamma Adjusted UCL	0.0415						
650																	
651					Estimates of Gamma Parameters using KM Estimates												
652					Mean (KM)	0.034				SD (KM)	0.0217						
653					Variance (KM)	4.7145E-4				SE of Mean (KM)	0.00343						
654					k hat (KM)	2.451				k star (KM)	2.288						
655					nu hat (KM)	201				nu star (KM)	187.6						
656					theta hat (KM)	0.0139				theta star (KM)	0.0149						
657					80% gamma percentile (KM)	0.0501				90% gamma percentile (KM)	0.0641						
658					95% gamma percentile (KM)	0.0773				99% gamma percentile (KM)	0.106						
659																	
660					Gamma Kaplan-Meier (KM) Statistics												
661					Approximate Chi Square Value (187.62, α)	156.9				Adjusted Chi Square Value (187.62, β)	155.9						
662					95% KM Approximate Gamma UCL	0.0406				95% KM Adjusted Gamma UCL	0.0409						
663																	
664					Lognormal GOF Test on Detected Observations Only												
665					Shapiro Wilk Test Statistic	0.925				Shapiro Wilk GOF Test							
666					10% Shapiro Wilk Critical Value	0.949				Detected Data Not Lognormal at 10% Significance Level							
667					Lilliefors Test Statistic	0.175				Lilliefors GOF Test							
668					10% Lilliefors Critical Value	0.128				Detected Data Not Lognormal at 10% Significance Level							
669					Detected Data Not Lognormal at 10% Significance Level												
670																	
671					Lognormal ROS Statistics Using Imputed Non-Detects												
672					Mean in Original Scale	0.034				Mean in Log Scale	-3.637						
673					SD in Original Scale	0.0219				SD in Log Scale	0.798						
674					95% t UCL (assumes normality of ROS data)	0.0398				95% Percentile Bootstrap UCL	0.0397						
675					95% BCA Bootstrap UCL	0.0398				95% Bootstrap t UCL	0.0403						
676					95% H-UCL (Log ROS)	0.0474											
677																	
678					Statistics using KM estimates on Logged Data and Assuming Lognormal Distribution												
679					KM Mean (logged)	-3.642				KM Geo Mean	0.0262						
680					KM SD (logged)	0.798				95% Critical H Value (KM-Log)	2.144						

681		KM Standard Error of Mean (logged)	0.126		95% H-UCL (KM -Log)	0.0472			
682		KM SD (logged)	0.798		95% Critical H Value (KM-Log)	2.144			
683		KM Standard Error of Mean (logged)	0.126						
684									
685		DL/2 Statistics							
686		DL/2 Normal			DL/2 Log-Transformed				
687		Mean in Original Scale	0.0339		Mean in Log Scale	-3.657			
688		SD in Original Scale	0.0221		SD in Log Scale	0.844			
689		95% t UCL (Assumes normality)	0.0397		95% H-Stat UCL	0.0493			
690		DL/2 is not a recommended method, provided for comparisons and historical reasons							
691									
692		Nonparametric Distribution Free UCL Statistics							
693		Detected Data appear Approximate Normal Distributed at 1% Significance Level							
694									
695		Suggested UCL to Use							
696		95% KM (t) UCL	0.0398						
697									
698		When a data set follows an approximate distribution passing only one of the GOF tests,							
699		it is suggested to use a UCL based upon a distribution passing both GOF tests in ProUCL							
700									
701		Note: Suggestions regarding the selection of a 95% UCL are provided to help the user to select the most appropriate 95% UCL.							
702		Recommendations are based upon data size, data distribution, and skewness using results from simulation studies.							
703		However, simulations results will not cover all Real World data sets; for additional insight the user may want to consult a statistician.							
704									
705		cPAHs-TEQ - Other							
706									
707		General Statistics							
708		Total Number of Observations	300		Number of Distinct Observations	59			
709					Number of Missing Observations	23			
710		Number of Detects	139		Number of Non-Detects	161			
711		Number of Distinct Detects	49		Number of Distinct Non-Detects	12			
712		Minimum Detect	0.0081		Minimum Non-Detect	0.0045			
713		Maximum Detect	0.2		Maximum Non-Detect	0.01			
714		Variance Detects	0.00156		Percent Non-Detects	53.67%			
715		Mean Detects	0.0569		SD Detects	0.0395			
716		Median Detects	0.05		CV Detects	0.693			
717		Skewness Detects	1.223		Kurtosis Detects	1.681			
718		Mean of Logged Detects	-3.118		SD of Logged Detects	0.752			
719									
720		Normal GOF Test on Detects Only							
721		Shapiro Wilk Test Statistic	0.888		Normal GOF Test on Detected Observations Only				
722		1% Shapiro Wilk P Value	4.441E-16		Detected Data Not Normal at 1% Significance Level				
723		Lilliefors Test Statistic	0.138		Lilliefors GOF Test				
724		1% Lilliefors Critical Value	0.0873		Detected Data Not Normal at 1% Significance Level				
725		Detected Data Not Normal at 1% Significance Level							
726									
727		Kaplan-Meier (KM) Statistics using Normal Critical Values and other Nonparametric UCLs							
728		KM Mean	0.0289		KM Standard Error of Mean	0.00216			
729		90KM SD	0.0374		95% KM (BCA) UCL	0.034			
730		95% KM (t) UCL	0.0324		95% KM (Percentile Bootstrap) UCL	0.0331			
731		95% KM (z) UCL	0.0324		95% KM Bootstrap t UCL	0.0323			
732		90% KM Chebyshev UCL	0.0354		95% KM Chebyshev UCL	0.0383			
733		97.5% KM Chebyshev UCL	0.0424		99% KM Chebyshev UCL	0.0504			
734									
735		Gamma GOF Tests on Detected Observations Only							
736		A-D Test Statistic	0.629		Anderson-Darling GOF Test				
737		5% A-D Critical Value	0.765		Detected data appear Gamma Distributed at 5% Significance Level				
738		K-S Test Statistic	0.078		Kolmogorov-Smirnov GOF				
739		5% K-S Critical Value	0.0804		Detected data appear Gamma Distributed at 5% Significance Level				
740		Detected data appear Gamma Distributed at 5% Significance Level							
741									
742		Gamma Statistics on Detected Data Only							
743		k hat (MLE)	2.137		k star (bias corrected MLE)	2.095			
744		Theta hat (MLE)	0.0266		Theta star (bias corrected MLE)	0.0272			
745		nu hat (MLE)	594		nu star (bias corrected)	582.5			
746		Mean (detects)	0.0569						
747									
748		Gamma ROS Statistics using Imputed Non-Detects							
749		GROS may not be used when data set has > 50% NDs with many tied observations at multiple DLs							
750		GROS may not be used when kstar of detects is small such as <1.0, especially when the sample size is small (e.g., <15-20)							
751		For such situations, GROS method may yield incorrect values of UCLs and BTVs							
752		This is especially true when the sample size is small.							
753		For gamma distributed detected data, BTVs and UCLs may be computed using gamma distribution on KM estimates							
754		Minimum	0.0081		Mean	0.0318			
755		Maximum	0.2		Median	0.01			
756		SD	0.0356		CV	1.12			
757		k hat (MLE)	1.219		k star (bias corrected MLE)	1.209			
758		Theta hat (MLE)	0.0261		Theta star (bias corrected MLE)	0.0263			
759		nu hat (MLE)	731.1		nu star (bias corrected)	725.2			
760		Adjusted Level of Significance (β)	0.0492						
761		Approximate Chi Square Value (725.17, α)	663.7		Adjusted Chi Square Value (725.17, β)	663.4			
762		95% Gamma Approximate UCL	0.0347		95% Gamma Adjusted UCL	0.0347			
763									
764		Estimates of Gamma Parameters using KM Estimates							
765		Mean (KM)	0.0289		SD (KM)	0.0374			

766			Variance (KM)	0.0014		SE of Mean (KM)	0.00216				
767			k hat (KM)	0.597		k star (KM)	0.594				
768			nu hat (KM)	358.5		nu star (KM)	356.2				
769			theta hat (KM)	0.0483		theta star (KM)	0.0486				
770			80% gamma percentile (KM)	0.0476		90% gamma percentile (KM)	0.0753				
771			95% gamma percentile (KM)	0.104		99% gamma percentile (KM)	0.175				
772											
773			Gamma Kaplan-Meier (KM) Statistics								
774			Approximate Chi Square Value (356.22, α)	313.5		Adjusted Chi Square Value (356.22, β)	313.3				
775			95% KM Approximate Gamma UCL	0.0328		95% KM Adjusted Gamma UCL	0.0328				
776											
777			Lognormal GOF Test on Detected Observations Only								
778			Shapiro Wilk Approximate Test Statistic	0.954		Shapiro Wilk GOF Test					
779			10% Shapiro Wilk P Value	6.5580E-4		Detected Data Not Lognormal at 10% Significance Level					
780			Lilliefors Test Statistic	0.0827		Lilliefors GOF Test					
781			10% Lilliefors Critical Value	0.0691		Detected Data Not Lognormal at 10% Significance Level					
782			Detected Data Not Lognormal at 10% Significance Level								
783											
784			Lognormal ROS Statistics Using Imputed Non-Detects								
785			Mean in Original Scale	0.0306		Mean in Log Scale	-4.149				
786			SD in Original Scale	0.0365		SD in Log Scale	1.194				
787			95% t UCL (assumes normality of ROS data)	0.034		95% Percentile Bootstrap UCL	0.0342				
788			95% BCA Bootstrap UCL	0.0344		95% Bootstrap t UCL	0.0341				
789			95% H-UCL (Log ROS)	0.0377							
790											
791			Statistics using KM estimates on Logged Data and Assuming Lognormal Distribution								
792			KM Mean (logged)	-4.331		KM Geo Mean	0.0132				
793			KM SD (logged)	1.24		95% Critical H Value (KM-Log)	2.349				
794			KM Standard Error of Mean (logged)	0.0723		95% H-UCL (KM -Log)	0.0336				
795			KM SD (logged)	1.24		95% Critical H Value (KM-Log)	2.349				
796			KM Standard Error of Mean (logged)	0.0723							
797											
798			DL/2 Statistics								
799			DL/2 Normal			DL/2 Log-Transformed					
800			Mean in Original Scale	0.0288		Mean in Log Scale	-4.348				
801			SD in Original Scale	0.0375		SD in Log Scale	1.257				
802			95% t UCL (Assumes normality)	0.0324		95% H-Stat UCL	0.0338				
803			DL/2 is not a recommended method, provided for comparisons and historical reasons								
804											
805			Nonparametric Distribution Free UCL Statistics								
806			Detected Data appear Gamma Distributed at 5% Significance Level								
807											
808			Suggested UCL to Use								
809			95% KM Approximate Gamma UCL	0.0328		95% GROS Approximate Gamma UCL	0.0347				
810											
811			Note: Suggestions regarding the selection of a 95% UCL are provided to help the user to select the most appropriate 95% UCL.								
812			Recommendations are based upon data size, data distribution, and skewness using results from simulation studies.								
813			However, simulations results will not cover all Real World data sets; for additional insight the user may want to consult a statistician.								
814											
815			Dibenz(a,h)anthracene - Semi-Volatile Organic Compounds (SIM)								
816											
817			General Statistics								
818			Total Number of Observations	41		Number of Distinct Observations	24				
819						Number of Missing Observations	282				
820			Number of Detects	14		Number of Non-Detects	27				
821			Number of Distinct Detects	14		Number of Distinct Non-Detects	14				
822			Minimum Detect	0.0046		Minimum Non-Detect	0.005				
823			Maximum Detect	0.014		Maximum Non-Detect	0.05				
824			Variance Detects	7.8148E-6		Percent Non-Detects	65.85%				
825			Mean Detects	0.00804		SD Detects	0.0028				
826			Median Detects	0.0071		CV Detects	0.348				
827			Skewness Detects	0.853		Kurtosis Detects	-0.113				
828			Mean of Logged Detects	-4.877		SD of Logged Detects	0.333				
829											
830			Normal GOF Test on Detects Only								
831			Shapiro Wilk Test Statistic	0.913		Shapiro Wilk GOF Test					
832			1% Shapiro Wilk Critical Value	0.825		Detected Data appear Normal at 1% Significance Level					
833			Lilliefors Test Statistic	0.209		Lilliefors GOF Test					
834			1% Lilliefors Critical Value	0.263		Detected Data appear Normal at 1% Significance Level					
835			Detected Data appear Normal at 1% Significance Level								
836											
837			Kaplan-Meier (KM) Statistics using Normal Critical Values and other Nonparametric UCLs								
838			KM Mean	0.00599		KM Standard Error of Mean	4.0988E-4				
839			90KM SD	0.00235		95% KM (BCA) UCL	0.00687				
840			95% KM (t) UCL	0.00668		95% KM (Percentile Bootstrap) UCL	0.00674				
841			95% KM (z) UCL	0.00667		95% KM Bootstrap t UCL	0.0068				
842			90% KM Chebyshev UCL	0.00722		95% KM Chebyshev UCL	0.00778				
843			97.5% KM Chebyshev UCL	0.00855		99% KM Chebyshev UCL	0.0101				
844											
845			Gamma GOF Tests on Detected Observations Only								
846			A-D Test Statistic	0.407		Anderson-Darling GOF Test					
847			5% A-D Critical Value	0.735		Detected data appear Gamma Distributed at 5% Significance Level					
848			K-S Test Statistic	0.201		Kolmogorov-Smirnov GOF					
849			5% K-S Critical Value	0.229		Detected data appear Gamma Distributed at 5% Significance Level					
850			Detected data appear Gamma Distributed at 5% Significance Level								

	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O
851															
852	Gamma Statistics on Detected Data Only														
853					k hat (MLE)	9.644					k star (bias corrected MLE)	7.625			
854					Theta hat (MLE)	8.3327E-4					Theta star (bias corrected MLE)	0.00105			
855					nu hat (MLE)	270					nu star (bias corrected)	213.5			
856					Mean (detects)	0.00804									
857															
858	Gamma ROS Statistics using Imputed Non-Detects														
859	GROS may not be used when data set has > 50% NDs with many tied observations at multiple DLs														
860	GROS may not be used when kstar of detects is small such as <1.0, especially when the sample size is small (e.g., <15-20)														
861	For such situations, GROS method may yield incorrect values of UCLs and BTVs														
862	This is especially true when the sample size is small.														
863	For gamma distributed detected data, BTVs and UCLs may be computed using gamma distribution on KM estimates														
864					Minimum	0.0046					Mean	0.00933			
865					Maximum	0.014					Median	0.01			
866					SD	0.00185					CV	0.198			
867					k hat (MLE)	21.67					k star (bias corrected MLE)	20.1			
868					Theta hat (MLE)	4.3061E-4					Theta star (bias corrected MLE)	4.6423E-4			
869					nu hat (MLE)	1777					nu star (bias corrected)	1648			
870					Adjusted Level of Significance (β)	0.0441									
871					Approximate Chi Square Value (N/A, α)	1555					Adjusted Chi Square Value (N/A, β)	1551			
872					95% Gamma Approximate UCL	0.00989					95% Gamma Adjusted UCL	0.00991			
873															
874	Estimates of Gamma Parameters using KM Estimates														
875					Mean (KM)	0.00599					SD (KM)	0.00235			
876					Variance (KM)	5.5343E-6					SE of Mean (KM)	4.0988E-4			
877					k hat (KM)	6.487					k star (KM)	6.029			
878					nu hat (KM)	531.9					nu star (KM)	494.4			
879					theta hat (KM)	9.2364E-4					theta star (KM)	9.9387E-4			
880					80% gamma percentile (KM)	0.00789					90% gamma percentile (KM)	0.00925			
881					95% gamma percentile (KM)	0.0105					99% gamma percentile (KM)	0.0131			
882															
883	Gamma Kaplan-Meier (KM) Statistics														
884					Approximate Chi Square Value (494.36, α)	443.8					Adjusted Chi Square Value (494.36, β)	442.1			
885					95% KM Approximate Gamma UCL	0.00667					95% KM Adjusted Gamma UCL	0.0067			
886															
887	Lognormal GOF Test on Detected Observations Only														
888					Shapiro Wilk Test Statistic	0.953					Shapiro Wilk GOF Test				
889					10% Shapiro Wilk Critical Value	0.895					Detected Data appear Lognormal at 10% Significance Level				
890					Lilliefors Test Statistic	0.184					Lilliefors GOF Test				
891					10% Lilliefors Critical Value	0.208					Detected Data appear Lognormal at 10% Significance Level				
892	Detected Data appear Lognormal at 10% Significance Level														
893															
894	Lognormal ROS Statistics Using Imputed Non-Detects														
895					Mean in Original Scale	0.00544					Mean in Log Scale	-5.3			
896					SD in Original Scale	0.00258					SD in Log Scale	0.401			
897					95% t UCL (assumes normality of ROS data)	0.00612					95% Percentile Bootstrap UCL	0.0061			
898					95% BCA Bootstrap UCL	0.0062					95% Bootstrap t UCL	0.00629			
899					95% H-UCL (Log ROS)	0.00607									
900															
901	Statistics using KM estimates on Logged Data and Assuming Lognormal Distribution														
902					KM Mean (logged)	-5.174					KM Geo Mean	0.00566			
903					KM SD (logged)	0.314					95% Critical H Value (KM-Log)	1.78			
904					KM Standard Error of Mean (logged)	0.0551					95% H-UCL (KM -Log)	0.00649			
905					KM SD (logged)	0.314					95% Critical H Value (KM-Log)	1.78			
906					KM Standard Error of Mean (logged)	0.0551									
907															
908	DL/2 Statistics														
909					DL/2 Normal						DL/2 Log-Transformed				
910					Mean in Original Scale	0.00638					Mean in Log Scale	-5.322			
911					SD in Original Scale	0.00554					SD in Log Scale	0.693			
912					95% t UCL (Assumes normality)	0.00784					95% H-Stat UCL	0.00778			
913	DL/2 is not a recommended method, provided for comparisons and historical reasons														
914															
915	Nonparametric Distribution Free UCL Statistics														
916	Detected Data appear Normal Distributed at 1% Significance Level														
917															
918	Suggested UCL to Use														
919					95% KM (t) UCL	0.00668									
920															
921	Note: Suggestions regarding the selection of a 95% UCL are provided to help the user to select the most appropriate 95% UCL.														
922	Recommendations are based upon data size, data distribution, and skewness using results from simulation studies.														
923	However, simulations results will not cover all Real World data sets; for additional insight the user may want to consult a statistician.														
924															
925	Indeno(1,2,3-cd)pyrene - Semi-Volatile Organic Compounds (SIM)														
926															
927	General Statistics														
928					Total Number of Observations	41					Number of Distinct Observations	28			
929											Number of Missing Observations	282			
930					Number of Detects	36					Number of Non-Detects	5			
931					Number of Distinct Detects	24					Number of Distinct Non-Detects	5			
932					Minimum Detect	0.0023					Minimum Non-Detect	0.005			
933					Maximum Detect	0.065					Maximum Non-Detect	0.05			
934					Variance Detects	2.8350E-4					Percent Non-Detects	12.2%			
935					Mean Detects	0.025					SD Detects	0.0168			

A	B	C	D	E	F	G	H	I	J	K	L	M	N	O
936				Median Detects	0.022					CV Detects	0.675			
937				Skewness Detects	0.911					Kurtosis Detects	0.251			
938				Mean of Logged Detects	-3.966					SD of Logged Detects	0.845			
939														
940				Normal GOF Test on Detects Only										
941				Shapiro Wilk Test Statistic	0.907					Shapiro Wilk GOF Test				
942				1% Shapiro Wilk Critical Value	0.912					Detected Data Not Normal at 1% Significance Level				
943				Lilliefors Test Statistic	0.17					Lilliefors GOF Test				
944				1% Lilliefors Critical Value	0.17					Detected Data Not Normal at 1% Significance Level				
945				Detected Data Not Normal at 1% Significance Level										
946														
947				Kaplan-Meier (KM) Statistics using Normal Critical Values and other Nonparametric UCLs										
948				KM Mean	0.0227					KM Standard Error of Mean	0.0027			
949				90KM SD	0.017					95% KM (BCA) UCL	0.027			
950				95% KM (t) UCL	0.0272					95% KM (Percentile Bootstrap) UCL	0.027			
951				95% KM (z) UCL	0.0271					95% KM Bootstrap t UCL	0.0278			
952				90% KM Chebyshev UCL	0.0308					95% KM Chebyshev UCL	0.0344			
953				97.5% KM Chebyshev UCL	0.0395					99% KM Chebyshev UCL	0.0495			
954														
955				Gamma GOF Tests on Detected Observations Only										
956				A-D Test Statistic	0.432					Anderson-Darling GOF Test				
957				5% A-D Critical Value	0.76					Detected data appear Gamma Distributed at 5% Significance Level				
958				K-S Test Statistic	0.12					Kolmogorov-Smirnov GOF				
959				5% K-S Critical Value	0.149					Detected data appear Gamma Distributed at 5% Significance Level				
960				Detected data appear Gamma Distributed at 5% Significance Level										
961														
962				Gamma Statistics on Detected Data Only										
963				k hat (MLE)	1.964					k star (bias corrected MLE)	1.819			
964				Theta hat (MLE)	0.0127					Theta star (bias corrected MLE)	0.0137			
965				nu hat (MLE)	141.4					nu star (bias corrected)	131			
966				Mean (detects)	0.025									
967														
968				Gamma ROS Statistics using Imputed Non-Detects										
969				GROS may not be used when data set has > 50% NDs with many tied observations at multiple DLs										
970				GROS may not be used when kstar of detects is small such as <1.0, especially when the sample size is small (e.g., <15-20)										
971				For such situations, GROS method may yield incorrect values of UCLs and BTVs										
972				This is especially true when the sample size is small.										
973				For gamma distributed detected data, BTVs and UCLs may be computed using gamma distribution on KM estimates										
974				Minimum	0.0023					Mean	0.0233			
975				Maximum	0.065					Median	0.02			
976				SD	0.0164					CV	0.705			
977				k hat (MLE)	1.987					k star (bias corrected MLE)	1.858			
978				Theta hat (MLE)	0.0117					Theta star (bias corrected MLE)	0.0125			
979				nu hat (MLE)	162.9					nu star (bias corrected)	152.3			
980				Adjusted Level of Significance (β)	0.0441									
981				Approximate Chi Square Value (152.34, α)	124.8					Adjusted Chi Square Value (152.34, β)	123.9			
982				95% Gamma Approximate UCL	0.0284					95% Gamma Adjusted UCL	0.0286			
983														
984				Estimates of Gamma Parameters using KM Estimates										
985				Mean (KM)	0.0227					SD (KM)	0.017			
986				Variance (KM)	2.8740E-4					SE of Mean (KM)	0.0027			
987				k hat (KM)	1.787					k star (KM)	1.673			
988				nu hat (KM)	146.5					nu star (KM)	137.2			
989				theta hat (KM)	0.0127					theta star (KM)	0.0135			
990				80% gamma percentile (KM)	0.0346					90% gamma percentile (KM)	0.046			
991				95% gamma percentile (KM)	0.0569					99% gamma percentile (KM)	0.0815			
992														
993				Gamma Kaplan-Meier (KM) Statistics										
994				Approximate Chi Square Value (137.16, α)	111.1					Adjusted Chi Square Value (137.16, β)	110.2			
995				95% KM Approximate Gamma UCL	0.028					95% KM Adjusted Gamma UCL	0.0282			
996														
997				Lognormal GOF Test on Detected Observations Only										
998				Shapiro Wilk Test Statistic	0.918					Shapiro Wilk GOF Test				
999				10% Shapiro Wilk Critical Value	0.945					Detected Data Not Lognormal at 10% Significance Level				
1000				Lilliefors Test Statistic	0.171					Lilliefors GOF Test				
1001				10% Lilliefors Critical Value	0.134					Detected Data Not Lognormal at 10% Significance Level				
1002				Detected Data Not Lognormal at 10% Significance Level										
1003														
1004				Lognormal ROS Statistics Using Imputed Non-Detects										
1005				Mean in Original Scale	0.0227					Mean in Log Scale	-4.105			
1006				SD in Original Scale	0.0169					SD in Log Scale	0.888			
1007				95% t UCL (assumes normality of ROS data)	0.0272					95% Percentile Bootstrap UCL	0.0271			
1008				95% BCA Bootstrap UCL	0.0274					95% Bootstrap t UCL	0.0275			
1009				95% H-UCL (Log ROS)	0.0335									
1010														
1011				Statistics using KM estimates on Logged Data and Assuming Lognormal Distribution										
1012				KM Mean (logged)	-4.153					KM Geo Mean	0.0157			
1013				KM SD (logged)	0.964					95% Critical H Value (KM-Log)	2.313			
1014				KM Standard Error of Mean (logged)	0.155					95% H-UCL (KM -Log)	0.0356			
1015				KM SD (logged)	0.964					95% Critical H Value (KM-Log)	2.313			
1016				KM Standard Error of Mean (logged)	0.155									
1017														
1018				DL/2 Statistics										
1019				DL/2 Normal						DL/2 Log-Transformed				
1020				Mean in Original Scale	0.0228					Mean in Log Scale	-4.142			

A	B	C	D	E	F	G	H	I	J	K	L	M	N	O
1021	SD in Original Scale				0.0171	SD in Log Scale				0.973				
1022	95% t UCL (Assumes normality)				0.0273	95% H-Stat UCL				0.0365				
1023	DL/2 is not a recommended method, provided for comparisons and historical reasons													
1024														
1025	Nonparametric Distribution Free UCL Statistics													
1026	Detected Data appear Gamma Distributed at 5% Significance Level													
1027														
1028	Suggested UCL to Use													
1029	95% KM Adjusted Gamma UCL				0.0282	95% GROS Adjusted Gamma UCL				0.0286				
1030														
1031	Note: Suggestions regarding the selection of a 95% UCL are provided to help the user to select the most appropriate 95% UCL.													
1032	Recommendations are based upon data size, data distribution, and skewness using results from simulation studies.													
1033	However, simulations results will not cover all Real World data sets; for additional insight the user may want to consult a statistician.													
1034														
1035	Lead - Inorganic Compounds													
1036														
1037	General Statistics													
1038	Total Number of Observations				104	Number of Distinct Observations				35				
1039						Number of Missing Observations				212				
1040	Number of Detects				37	Number of Non-Detects				67				
1041	Number of Distinct Detects				28	Number of Distinct Non-Detects				13				
1042	Minimum Detect				11	Minimum Non-Detect				2				
1043	Maximum Detect				240	Maximum Non-Detect				26				
1044	Variance Detects				6029	Percent Non-Detects				64.42%				
1045	Mean Detects				103.1	SD Detects				77.65				
1046	Median Detects				73	CV Detects				0.753				
1047	Skewness Detects				0.52	Kurtosis Detects				-1.271				
1048	Mean of Logged Detects				4.274	SD of Logged Detects				0.941				
1049														
1050	Normal GOF Test on Detects Only													
1051	Shapiro Wilk Test Statistic				0.865	Shapiro Wilk GOF Test								
1052	1% Shapiro Wilk Critical Value				0.814	Detected Data appear Normal at 1% Significance Level								
1053	Lilliefors Test Statistic				0.199	Lilliefors GOF Test								
1054	1% Lilliefors Critical Value				0.168	Detected Data Not Normal at 1% Significance Level								
1055	Detected Data appear Approximate Normal at 1% Significance Level													
1056														
1057	Kaplan-Meier (KM) Statistics using Normal Critical Values and other Nonparametric UCLs													
1058	KM Mean				39.84	KM Standard Error of Mean				6.589				
1059	90KM SD				65.67	95% KM (BCA) UCL				55.26				
1060	95% KM (t) UCL				50.78	95% KM (Percentile Bootstrap) UCL				52.13				
1061	95% KM (z) UCL				50.68	95% KM Bootstrap t UCL				51.23				
1062	90% KM Chebyshev UCL				59.61	95% KM Chebyshev UCL				68.56				
1063	97.5% KM Chebyshev UCL				80.99	99% KM Chebyshev UCL				105.4				
1064														
1065	Gamma GOF Tests on Detected Observations Only													
1066	A-D Test Statistic				0.818	Anderson-Darling GOF Test								
1067	5% A-D Critical Value				0.766	Detected Data Not Gamma Distributed at 5% Significance Level								
1068	K-S Test Statistic				0.126	Kolmogorov-Smirnov GOF								
1069	5% K-S Critical Value				0.148	Detected data appear Gamma Distributed at 5% Significance Level								
1070	Detected data follow Appr. Gamma Distribution at 5% Significance Level													
1071														
1072	Gamma Statistics on Detected Data Only													
1073	k hat (MLE)				1.529	k star (bias corrected MLE)				1.423				
1074	Theta hat (MLE)				67.42	Theta star (bias corrected MLE)				72.44				
1075	nu hat (MLE)				113.1	nu star (bias corrected)				105.3				
1076	Mean (detects)				103.1									
1077														
1078	Gamma ROS Statistics using Imputed Non-Detects													
1079	GROS may not be used when data set has > 50% NDs with many tied observations at multiple DLs													
1080	GROS may not be used when kstar of detects is small such as <1.0, especially when the sample size is small (e.g., <15-20)													
1081	For such situations, GROS method may yield incorrect values of UCLs and BTVs													
1082	This is especially true when the sample size is small.													
1083	For gamma distributed detected data, BTVs and UCLs may be computed using gamma distribution on KM estimates													
1084	Minimum				0.01	Mean				37.64				
1085	Maximum				240	Median				0.01				
1086	SD				67.14	CV				1.784				
1087	k hat (MLE)				0.17	k star (bias corrected MLE)				0.172				
1088	Theta hat (MLE)				221.1	Theta star (bias corrected MLE)				219.1				
1089	nu hat (MLE)				35.41	nu star (bias corrected)				35.72				
1090	Adjusted Level of Significance (β)				0.0477									
1091	Approximate Chi Square Value (35.72, α)				23.05	Adjusted Chi Square Value (35.72, β)				22.9				
1092	95% Gamma Approximate UCL				58.34	95% Gamma Adjusted UCL				58.71				
1093														
1094	Estimates of Gamma Parameters using KM Estimates													
1095	Mean (KM)				39.84	SD (KM)				65.67				
1096	Variance (KM)				4313	SE of Mean (KM)				6.589				
1097	k hat (KM)				0.368	k star (KM)				0.364				
1098	nu hat (KM)				76.56	nu star (KM)				75.68				
1099	theta hat (KM)				108.2	theta star (KM)				109.5				
1100	80% gamma percentile (KM)				63.48	90% gamma percentile (KM)				114.4				
1101	95% gamma percentile (KM)				171	99% gamma percentile (KM)				314.9				
1102														
1103	Gamma Kaplan-Meier (KM) Statistics													
1104	Approximate Chi Square Value (75.68, α)				56.64	Adjusted Chi Square Value (75.68, β)				56.41				
1105	95% KM Approximate Gamma UCL				53.23	95% KM Adjusted Gamma UCL				53.45				

A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	
1106															
1107	Lognormal GOF Test on Detected Observations Only														
1108	Shapiro Wilk Test Statistic		0.916	Shapiro Wilk GOF Test											
1109	10% Shapiro Wilk Critical Value		0.946	Detected Data Not Lognormal at 10% Significance Level											
1110	Lilliefors Test Statistic		0.127	Lilliefors GOF Test											
1111	10% Lilliefors Critical Value		0.132	Detected Data appear Lognormal at 10% Significance Level											
1112	Detected Data appear Approximate Lognormal at 10% Significance Level														
1113															
1114	Lognormal ROS Statistics Using Imputed Non-Detects														
1115	Mean in Original Scale		41.78	Mean in Log Scale				2.651							
1116	SD in Original Scale		65.01	SD in Log Scale				1.497							
1117	95% t UCL (assumes normality of ROS data)		52.36	95% Percentile Bootstrap UCL				52.45							
1118	95% BCA Bootstrap UCL		52.88	95% Bootstrap t UCL				53.28							
1119	95% H-UCL (Log ROS)		64.85												
1120															
1121	Statistics using KM estimates on Logged Data and Assuming Lognormal Distribution														
1122	KM Mean (logged)		2.28	KM Geo Mean				9.78							
1123	KM SD (logged)		1.715	95% Critical H Value (KM-Log)				2.962							
1124	KM Standard Error of Mean (logged)		0.229	95% H-UCL (KM -Log)				70.19							
1125	KM SD (logged)		1.715	95% Critical H Value (KM-Log)				2.962							
1126	KM Standard Error of Mean (logged)		0.229												
1127															
1128	DL/2 Statistics														
1129	DL/2 Normal			DL/2 Log-Transformed											
1130	Mean in Original Scale		43.24	Mean in Log Scale				2.987							
1131	SD in Original Scale		64.09	SD in Log Scale				1.15							
1132	95% t UCL (Assumes normality)		53.67	95% H-Stat UCL				50.08							
1133	DL/2 is not a recommended method, provided for comparisons and historical reasons														
1134															
1135	Nonparametric Distribution Free UCL Statistics														
1136	Detected Data appear Approximate Normal Distributed at 1% Significance Level														
1137															
1138	Suggested UCL to Use														
1139	95% KM (t) UCL		50.78												
1140															
1141	When a data set follows an approximate distribution passing only one of the GOF tests,														
1142	it is suggested to use a UCL based upon a distribution passing both GOF tests in ProUCL														
1143															
1144	Note: Suggestions regarding the selection of a 95% UCL are provided to help the user to select the most appropriate 95% UCL.														
1145	Recommendations are based upon data size, data distribution, and skewness using results from simulation studies.														
1146	However, simulations results will not cover all Real World data sets; for additional insight the user may want to consult a statistician.														
1147															
1148	Naphthalene - Semi-Volatile Organic Compounds (SIM)														
1149															
1150	General Statistics														
1151	Total Number of Observations		41	Number of Distinct Observations				15							
1152				Number of Missing Observations				282							
1153	Number of Detects		5	Number of Non-Detects				36							
1154	Number of Distinct Detects		5	Number of Distinct Non-Detects				12							
1155	Minimum Detect		0.0023	Minimum Non-Detect				0.0048							
1156	Maximum Detect		0.0069	Maximum Non-Detect				0.01							
1157	Variance Detects		3.0530E-6	Percent Non-Detects				87.8%							
1158	Mean Detects		0.00526	SD Detects				0.00175							
1159	Median Detects		0.0057	CV Detects				0.332							
1160	Skewness Detects		-1.643	Kurtosis Detects				3.31							
1161	Mean of Logged Detects		-5.311	SD of Logged Detects				0.437							
1162															
1163	Normal GOF Test on Detects Only														
1164	Shapiro Wilk Test Statistic		0.84	Shapiro Wilk GOF Test											
1165	1% Shapiro Wilk Critical Value		0.686	Detected Data appear Normal at 1% Significance Level											
1166	Lilliefors Test Statistic		0.332	Lilliefors GOF Test											
1167	1% Lilliefors Critical Value		0.396	Detected Data appear Normal at 1% Significance Level											
1168	Detected Data appear Normal at 1% Significance Level														
1169	Note GOF tests may be unreliable for small sample sizes														
1170															
1171	Kaplan-Meier (KM) Statistics using Normal Critical Values and other Nonparametric UCLs														
1172	KM Mean		0.00269	KM Standard Error of Mean				2.1016E-4							
1173	90KM SD		0.00115	95% KM (BCA) UCL				0.00511							
1174	95% KM (t) UCL		0.00305	95% KM (Percentile Bootstrap) UCL				0.00509							
1175	95% KM (z) UCL		0.00304	95% KM Bootstrap t UCL				0.00291							
1176	90% KM Chebyshev UCL		0.00332	95% KM Chebyshev UCL				0.00361							
1177	97.5% KM Chebyshev UCL		0.00401	99% KM Chebyshev UCL				0.00479							
1178	Note: KM UCLs may be biased low with this dataset. Other substitution method recommended														
1179															
1180	Gamma GOF Tests on Detected Observations Only														
1181	A-D Test Statistic		0.692	Anderson-Darling GOF Test											
1182	5% A-D Critical Value		0.68	Detected Data Not Gamma Distributed at 5% Significance Level											
1183	K-S Test Statistic		0.376	Kolmogorov-Smirnov GOF											
1184	5% K-S Critical Value		0.358	Detected Data Not Gamma Distributed at 5% Significance Level											
1185	Detected Data Not Gamma Distributed at 5% Significance Level														
1186															
1187	Gamma Statistics on Detected Data Only														
1188	k hat (MLE)		8.035	k star (bias corrected MLE)				3.347							
1189	Theta hat (MLE)		6.5467E-4	Theta star (bias corrected MLE)				0.00157							
1190	nu hat (MLE)		80.35	nu star (bias corrected)				33.47							

A	B	C	D	E	F	G	H	I	J	K	L	M	N	O
1191				Mean (detects)	0.00526									
1192														
1193				Gamma ROS Statistics using Imputed Non-Detects										
1194				GROS may not be used when data set has > 50% NDs with many tied observations at multiple DLs										
1195				GROS may not be used when kstar of detects is small such as <1.0, especially when the sample size is small (e.g., <15-20)										
1196				For such situations, GROS method may yield incorrect values of UCLs and BTVs										
1197				This is especially true when the sample size is small.										
1198				For gamma distributed detected data, BTVs and UCLs may be computed using gamma distribution on KM estimates										
1199				Minimum	0.0023			Mean		0.00942				
1200				Maximum	0.01			Median		0.01				
1201				SD	0.00166			CV		0.177				
1202				k hat (MLE)	19			k star (bias corrected MLE)		17.62				
1203				Theta hat (MLE)	4.9598E-4			Theta star (bias corrected MLE)		5.3465E-4				
1204				nu hat (MLE)	1558			nu star (bias corrected)		1445				
1205				Adjusted Level of Significance (β)	0.0441									
1206				Approximate Chi Square Value (N/A, α)	1358			Adjusted Chi Square Value (N/A, β)		1355				
1207				95% Gamma Approximate UCL	0.01			95% Gamma Adjusted UCL		0.0101				
1208														
1209				Estimates of Gamma Parameters using KM Estimates										
1210				Mean (KM)	0.00269			SD (KM)		0.00115				
1211				Variance (KM)	1.3289E-6			SE of Mean (KM)		2.1016E-4				
1212				k hat (KM)	5.462			k star (KM)		5.079				
1213				nu hat (KM)	447.9			nu star (KM)		416.5				
1214				theta hat (KM)	4.9324E-4			theta star (KM)		5.3048E-4				
1215				80% gamma percentile (KM)	0.00362			90% gamma percentile (KM)		0.00429				
1216				95% gamma percentile (KM)	0.00491			99% gamma percentile (KM)		0.00622				
1217														
1218				Gamma Kaplan-Meier (KM) Statistics										
1219				Approximate Chi Square Value (416.47, α)	370.2			Adjusted Chi Square Value (416.47, β)		368.6				
1220				95% KM Approximate Gamma UCL	0.00303			95% KM Adjusted Gamma UCL		0.00304				
1221				Note: KM UCLs may be biased low with this dataset. Other substitution method recommended										
1222														
1223				Lognormal GOF Test on Detected Observations Only										
1224				Shapiro Wilk Test Statistic	0.749			Shapiro Wilk GOF Test						
1225				10% Shapiro Wilk Critical Value	0.806			Detected Data Not Lognormal at 10% Significance Level						
1226				Lilliefors Test Statistic	0.381			Lilliefors GOF Test						
1227				10% Lilliefors Critical Value	0.319			Detected Data Not Lognormal at 10% Significance Level						
1228				Detected Data Not Lognormal at 10% Significance Level										
1229														
1230				Lognormal ROS Statistics Using Imputed Non-Detects										
1231				Mean in Original Scale	0.00283			Mean in Log Scale		-5.943				
1232				SD in Original Scale	0.00125			SD in Log Scale		0.383				
1233				95% t UCL (assumes normality of ROS data)	0.00316			95% Percentile Bootstrap UCL		0.00316				
1234				95% BCA Bootstrap UCL	0.00318			95% Bootstrap t UCL		0.00325				
1235				95% H-UCL (Log ROS)	0.00315									
1236														
1237				Statistics using KM estimates on Logged Data and Assuming Lognormal Distribution										
1238				KM Mean (logged)	-5.973			KM Geo Mean		0.00255				
1239				KM SD (logged)	0.296			95% Critical H Value (KM-Log)		1.771				
1240				KM Standard Error of Mean (logged)	0.054			95% H-UCL (KM -Log)		0.00289				
1241				KM SD (logged)	0.296			95% Critical H Value (KM-Log)		1.771				
1242				KM Standard Error of Mean (logged)	0.054									
1243				Note: KM UCLs may be biased low with this dataset. Other substitution method recommended										
1244														
1245				DL/2 Statistics										
1246				DL/2 Normal				DL/2 Log-Transformed						
1247				Mean in Original Scale	0.00303			Mean in Log Scale		-5.849				
1248				SD in Original Scale	0.00114			SD in Log Scale		0.288				
1249				95% t UCL (Assumes normality)	0.00333			95% H-Stat UCL		0.00326				
1250				DL/2 is not a recommended method, provided for comparisons and historical reasons										
1251														
1252				Nonparametric Distribution Free UCL Statistics										
1253				Detected Data appear Normal Distributed at 1% Significance Level										
1254														
1255				Suggested UCL to Use										
1256				95% KM (t) UCL	0.00305									
1257														
1258				Note: Suggestions regarding the selection of a 95% UCL are provided to help the user to select the most appropriate 95% UCL.										
1259				Recommendations are based upon data size, data distribution, and skewness using results from simulation studies.										
1260				However, simulations results will not cover all Real World data sets; for additional insight the user may want to consult a statistician.										
1261														
1262				Naphthalene, Total - Semi-Volatile Organic Compounds (SIM)										
1263														
1264				General Statistics										
1265				Total Number of Observations	41			Number of Distinct Observations		17				
1266								Number of Missing Observations		282				
1267				Number of Detects	5			Number of Non-Detects		36				
1268				Number of Distinct Detects	5			Number of Distinct Non-Detects		13				
1269				Minimum Detect	0.0023			Minimum Non-Detect		0.005				
1270				Maximum Detect	0.015			Maximum Non-Detect		0.01				
1271				Variance Detects	2.2583E-5			Percent Non-Detects		87.8%				
1272				Mean Detects	0.00706			SD Detects		0.00475				
1273				Median Detects	0.0057			CV Detects		0.673				
1274				Skewness Detects	1.497			Kurtosis Detects		3.027				
1275				Mean of Logged Detects	-5.128			SD of Logged Detects		0.669				

A	B	C	D	E	F	G	H	I	J	K	L	M	N	O
1276														
1277	Normal GOF Test on Detects Only													
1278	Shapiro Wilk Test Statistic		0.858	Shapiro Wilk GOF Test										
1279	1% Shapiro Wilk Critical Value		0.686	Detected Data appear Normal at 1% Significance Level										
1280	Lilliefors Test Statistic		0.313	Lilliefors GOF Test										
1281	1% Lilliefors Critical Value		0.396	Detected Data appear Normal at 1% Significance Level										
1282	Detected Data appear Normal at 1% Significance Level													
1283	Note GOF tests may be unreliable for small sample sizes													
1284														
1285	Kaplan-Meier (KM) Statistics using Normal Critical Values and other Nonparametric UCLs													
1286	KM Mean		0.00306	KM Standard Error of Mean		4.3136E-4								
1287	90KM SD		0.00223	95% KM (BCA) UCL		0.00574								
1288	95% KM (t) UCL		0.00379	95% KM (Percentile Bootstrap) UCL		0.00563								
1289	95% KM (z) UCL		0.00377	95% KM Bootstrap t UCL		0.00367								
1290	90% KM Chebyshev UCL		0.00436	95% KM Chebyshev UCL		0.00495								
1291	97.5% KM Chebyshev UCL		0.00576	99% KM Chebyshev UCL		0.00736								
1292														
1293	Gamma GOF Tests on Detected Observations Only													
1294	A-D Test Statistic		0.329	Anderson-Darling GOF Test										
1295	5% A-D Critical Value		0.683	Detected data appear Gamma Distributed at 5% Significance Level										
1296	K-S Test Statistic		0.239	Kolmogorov-Smirnov GOF										
1297	5% K-S Critical Value		0.359	Detected data appear Gamma Distributed at 5% Significance Level										
1298	Detected data appear Gamma Distributed at 5% Significance Level													
1299	Note GOF tests may be unreliable for small sample sizes													
1300														
1301	Gamma Statistics on Detected Data Only													
1302	k hat (MLE)		3.02	k star (bias corrected MLE)		1.342								
1303	Theta hat (MLE)		0.00234	Theta star (bias corrected MLE)		0.00526								
1304	nu hat (MLE)		30.2	nu star (bias corrected)		13.42								
1305	Mean (detects)		0.00706											
1306														
1307	Gamma ROS Statistics using Imputed Non-Detects													
1308	GROS may not be used when data set has > 50% NDs with many tied observations at multiple DLs													
1309	GROS may not be used when kstar of detects is small such as <1.0, especially when the sample size is small (e.g., <15-20)													
1310	For such situations, GROS method may yield incorrect values of UCLs and BTVs													
1311	This is especially true when the sample size is small.													
1312	For gamma distributed detected data, BTVs and UCLs may be computed using gamma distribution on KM estimates													
1313	Minimum		0.0023	Mean		0.00964								
1314	Maximum		0.015	Median		0.01								
1315	SD		0.00179	CV		0.186								
1316	k hat (MLE)		18.52	k star (bias corrected MLE)		17.19								
1317	Theta hat (MLE)		5.2046E-4	Theta star (bias corrected MLE)		5.6102E-4								
1318	nu hat (MLE)		1519	nu star (bias corrected)		1409								
1319	Adjusted Level of Significance (β)		0.0441											
1320	Approximate Chi Square Value (N/A, α)		1323	Adjusted Chi Square Value (N/A, β)		1320								
1321	95% Gamma Approximate UCL		0.0103	95% Gamma Adjusted UCL		0.0103								
1322														
1323	Estimates of Gamma Parameters using KM Estimates													
1324	Mean (KM)		0.00306	SD (KM)		0.00223								
1325	Variance (KM)		4.9927E-6	SE of Mean (KM)		4.3136E-4								
1326	k hat (KM)		1.881	k star (KM)		1.76								
1327	nu hat (KM)		154.3	nu star (KM)		144.3								
1328	theta hat (KM)		0.00163	theta star (KM)		0.00174								
1329	80% gamma percentile (KM)		0.00466	90% gamma percentile (KM)		0.00614								
1330	95% gamma percentile (KM)		0.00757	99% gamma percentile (KM)		0.0108								
1331														
1332	Gamma Kaplan-Meier (KM) Statistics													
1333	Approximate Chi Square Value (144.33, α)		117.6	Adjusted Chi Square Value (144.33, β)		116.7								
1334	95% KM Approximate Gamma UCL		0.00376	95% KM Adjusted Gamma UCL		0.00379								
1335														
1336	Lognormal GOF Test on Detected Observations Only													
1337	Shapiro Wilk Test Statistic		0.951	Shapiro Wilk GOF Test										
1338	10% Shapiro Wilk Critical Value		0.806	Detected Data appear Lognormal at 10% Significance Level										
1339	Lilliefors Test Statistic		0.244	Lilliefors GOF Test										
1340	10% Lilliefors Critical Value		0.319	Detected Data appear Lognormal at 10% Significance Level										
1341	Detected Data appear Lognormal at 10% Significance Level													
1342	Note GOF tests may be unreliable for small sample sizes													
1343														
1344	Lognormal ROS Statistics Using Imputed Non-Detects													
1345	Mean in Original Scale		0.00292	Mean in Log Scale		-6.003								
1346	SD in Original Scale		0.00231	SD in Log Scale		0.536								
1347	95% t UCL (assumes normality of ROS data)		0.00353	95% Percentile Bootstrap UCL		0.00355								
1348	95% BCA Bootstrap UCL		0.00373	95% Bootstrap t UCL		0.00401								
1349	95% H-UCL (Log ROS)		0.00336											
1350														
1351	Statistics using KM estimates on Logged Data and Assuming Lognormal Distribution													
1352	KM Mean (logged)		-5.91	KM Geo Mean		0.00271								
1353	KM SD (logged)		0.412	95% Critical H Value (KM-Log)		1.838								
1354	KM Standard Error of Mean (logged)		0.0875	95% H-UCL (KM -Log)		0.00333								
1355	KM SD (logged)		0.412	95% Critical H Value (KM-Log)		1.838								
1356	KM Standard Error of Mean (logged)		0.0875											
1357	Note: KM UCLs may be biased low with this dataset. Other substitution method recommended													
1358														
1359	DL/2 Statistics													
1360	DL/2 Normal						DL/2 Log-Transformed							

	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O
1361				Mean in Original Scale		0.00349					Mean in Log Scale	-5.742			
1362				SD in Original Scale		0.0021					SD in Log Scale	0.356			
1363				95% t UCL (Assumes normality)		0.00404					95% H-Stat UCL	0.00378			
1364	DL/2 is not a recommended method, provided for comparisons and historical reasons														
1365															
1366	Nonparametric Distribution Free UCL Statistics														
1367	Detected Data appear Normal Distributed at 1% Significance Level														
1368															
1369	Suggested UCL to Use														
1370				95% KM (t) UCL		0.00379									
1371															
1372	Note: Suggestions regarding the selection of a 95% UCL are provided to help the user to select the most appropriate 95% UCL.														
1373	Recommendations are based upon data size, data distribution, and skewness using results from simulation studies.														
1374	However, simulations results will not cover all Real World data sets; for additional insight the user may want to consult a statistician.														
1375															