


WELL MONITORING

NORTHWEST PROCESSING










**LEGEND**

**A-10** Well number and approximate location

**REFERENCE:**  
Undated, untitleed site utility plan provided by Solidus, Inc.


**Applied Geotechnology Inc.**  
 Geotechnical Engineering  
 Geology & Hydrogeology

**SITE PLAN**  
 Solidus, Inc. - Accurate Packaging Property  
 Tacoma, Washington


JOB NUMBER: 15.181.001  
 DESIGN: NS  
 APPROVED:   
 DATE: 2/2/87  
 REVISED: \_\_\_\_\_  
 DATE: \_\_\_\_\_

FIGURE **2**




Applied Geotechnology Inc.  
Geotechnical Engineering  
Geology & Hydrogeology

# LOG AND INSTALLATION - WELL A-1

Solidus, Inc. - Accurate Packaging Property  
Tacoma, Washington

PLATE 3



Equipment: Mobile 861

Elevation: Not measured Date: 1/6/87



Applied Geotechnology Inc.  
Geotechnical Engineering  
Geology & Hydrogeology

**SOIL CLASSIFICATION/LEGEND**  
Solidus, Inc. - Accurate Packaging Property  
Tacoma, Washington

PLATE

**LEGEND**

<p><b>SAMPLE</b></p> <p> <input type="checkbox"/> "Undisturbed"  <input checked="" type="checkbox"/> Bulk  <input type="checkbox"/> Not Recovered         </p>	<p><b>GRAPHIC LOG</b></p> <p>  Well Defined Change   Gradational Change   Obscure Change   End of Exploration         </p>	<p><b>BLOWS/FOOT</b></p> <p>           Hammer is 140 pounds with 30 inch drop, unless otherwise noted            S - SPT Sampler (2.0 inch O.D.)            T - Thin Wall Sampler (2.8 inch Sample)            H - Split Barrel Sampler (2.4 inch Sample)         </p>	<p><b>MOISTURE DESCRIPTION</b></p> <p>           Dry - Considerably less than optimum for compaction            Moist - Near optimum moisture content            Wet - Over optimum moisture content            Saturated - Below water table, in capillary zone, or in perched groundwater         </p>
<p><b>LABORATORY TESTS</b></p> <p>           Consol - Consolidation            LL - Liquid Limit            PL - Plastic Limit            GS - Specific Gravity            SA - Size Analysis            TX - Triaxial Shear            DS - Direct Shear            VS - Vane Shear            Comp - Compaction         </p>	<p>           UU - Unconsolidated • Undrained            CU - Consolidated • Undrained            CD - Consolidated • Drained         </p>		

**UNIFIED SOIL CLASSIFICATION SYSTEM**

MAJOR DIVISIONS	TYPICAL NAMES	SCHEMATIC	SOIL CLASSIFICATION	DESCRIPTION	
FINE GRAINED SOILS MORE THAN HALF IS SMALLER THAN NO. 200 SIEVE	SILTS AND CLAYS LIQUID LIMIT GREATER THAN 50	PR	PEAT AND OTHER HIGHLY ORGANIC SOILS		
		OH	ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTS		
		CH	INORGANIC CLAYS OF HIGH PLASTICITY FAT CLAYS		
		MH	INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SANDY OR SILTY SOILS, ELASTIC SILTS		
	SILTS AND CLAYS LIQUID LIMIT LESS THAN 50	OL	ORGANIC CLAYS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY		
		CL	INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS		
		ML	INORGANIC SILTS AND VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS, OR CLAYEY SILTS WITH SLIGHT PLASTICITY		
COARSE GRAINED SOILS MORE THAN HALF IS LARGER THAN NO. 4 SIEVE SIZE	SANDS MORE THAN HALF IS LARGER THAN NO. 4 SIEVE SIZE IS LARGER THAN COARSE FRACTION	SC	CLAYEY SANDS, POORLY GRADED SAND - CLAY MIXTURES		
		SM	SILTY SANDS, POORLY GRADED SAND - SILT MIXTURES		
	SANDS LITTLE OR NO FINES	SP	POORLY GRADED SANDS, GRAVELLY SANDS		
		SW	WELL GRADED SANDS, GRAVELLY SANDS		
	GRAVELS MORE THAN HALF IS LARGER THAN NO. 4 SIEVE SIZE IS LARGER THAN COARSE FRACTION	GRAVELS WITH OVER 12% FINES	GC	CLAYEY GRAVELS, POORLY GRADED GRAVEL - SAND - CLAY MIXTURES	
			GM	SILTY GRAVELS, POORLY GRADED GRAVEL - SAND - SILT MIXTURES	
		GRAVELS WITH LITTLE OR NO FINES	GP	POORLY GRADED GRAVELS GRAVEL-SAND MIXTURES	
			GW	WELL GRADED GRAVELS, GRAVEL-SAND MIXTURES	




Applied Geotechnology Inc.  
Geotechnical Engineering  
Geology & Hydrogeology

Solidus, Inc. - Accurate Packaging Property  
Tacoma, Washington

# WELL INSTALLATION LEGEND


2  
PLATE













**LEGEND**

A-1 Well number and approximate location

**REFERENCE:**  
Undated, untitled site utility plan provided by Solidus, Inc.

 Applied Geotechnology Inc. Geotechnical Engineering Geology & Hydrogeology	<b>SITE PLAN</b>		Solidus, Inc. - Accurate Packaging Property Tacoma, Washington
	DRAWN HB	APPROVED 	
JOB NUMBER 15.181.001			SHEET <b>2</b>




Applied Geotechnology Inc.  
Geotechnical Engineering  
Geology & Hydrogeology

Solidus, Inc. - Accurate Packaging Property  
Tacoma, Washington

# LOG AND INSTALLATION - WELL A-2

PLATE 4



Equipment: Mobile B61  
 Elevation: Not measured  
 Date: 1/8/87



Applied Geotechnology Inc.  
Geotechnical Engineering  
Geology & Hydrogeology

Solidus, Inc. - Accurate Packaging Property  
Tacoma, Washington

**SOIL CLASSIFICATION/LEGEND**

PLATE

**LEGEND**

**MOISTURE DESCRIPTION**

Dry - Considerably less than optimum for compaction  
Moist - Near optimum moisture content  
Wet - Over optimum moisture content  
Saturated - Below water table, in capillary zone, or in perched groundwater

---

**BLOWS/FOOT**

Hammer is 140 pounds with 30 inch drop, unless otherwise noted  
S - SPT Sampler (2.0 inch O.D.)  
T - Thin Wall Sampler (2.8 inch Sample)  
H - Split Barrel Sampler (2.4 inch Sample)

---

**GRAPHIC LOG**

Well Defined Change (solid line)  
Gradational Change (dashed line)  
Obscure Change (dotted line)  
End of Exploration (dash-dot line)

---

**LABORATORY TESTS**

Consol - Consolidation  
LL - Liquid Limit  
PL - Plastic Limit  
Gs - Specific Gravity  
SA - Size Analysis  
Tx - Triaxial Shear  
DS - Direct Shear  
VS - Vane Shear  
Comp - Compaction  
UU - Unconsolidated • Undrained  
CU - Consolidated • Undrained  
CD - Consolidated • Drained

**UNIFIED SOIL CLASSIFICATION SYSTEM**

MAJOR DIVISIONS		TYPICAL NAMES	
FINE GRAINED SOILS MORE THAN HALF IS SMALLER THAN NO. 200 SIEVE	SILTS AND CLAYS LIQUID LIMIT LESS THAN 50	ML	INORGANIC SILTS AND VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS, OR CLAYEY SILTS WITH SLIGHT PLASTICITY
		CL	INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS
		OL	ORGANIC CLAYS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY
		MH	INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SANDY OR SILTY SILTS, ELASTIC SILTS
		CH	INORGANIC CLAYS OF HIGH PLASTICITY FAT
		OH	ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTS
COARSE GRAINED SOILS MORE THAN HALF IS LARGER THAN NO. 200 SIEVE	SANDS MORE THAN HALF COARSE FRACTION IS LARGER THAN NO. 4 SIEVE SIZE IS LARGER THAN NO. 4 SIEVE SIZE	SC	CLAYEY SANDS, POORLY GRADED SAND - CLAY MIXTURES
		SM	SILTY SANDS, POORLY GRADED SAND - SILT MIXTURES
		SP	POORLY GRADED SANDS, GRAVELLY SANDS
		SW	WELL GRADED SANDS, GRAVELLY SANDS
	GRAVELS MORE THAN HALF COARSE FRACTION IS LARGER THAN NO. 4 SIEVE SIZE IS LARGER THAN NO. 4 SIEVE SIZE	GC	CLAYEY GRAVELS, POORLY GRADED GRAVEL - SAND - CLAY MIXTURES
		GM	SILTY GRAVELS, POORLY GRADED GRAVEL - SAND - SILT MIXTURES
		GP	POORLY GRADED GRAVELS - SAND MIXTURES
		GW	WELL GRADED GRAVELS, GRAVEL - SAND MIXTURES




Applied Geotechnology Inc.  
Geotechnical Engineering  
Geology & Hydrogeology

Solidus, Inc. - Accurate Packaging Property  
Tacoma, Washington

# WELL INSTALLATION LEGEND


2

PLATE









**LEGEND**

**A-1** Well number and approximate location

REFERENCE: Undated, unutilized site utility plan provided by Solidus, Inc.

Applied Geotechnology Inc.  
 Geotechnical Engineering  
 Geology & Hydrogeology

**SITE PLAN**  
 Solidus, Inc. - Accurate Packaging Property  
 Tacoma, Washington

FIGURE NUMBER 15, 181, 001  
 DRAWN NB  
 APPROVED WJW  
 DATE 2/2/87  
 REVISED  
 DATE






Applied Geotechnical Engineering & Hydrogeology, Inc.

# LOG AND INSTALLATION - WELL A-3

Solidus, Inc. - Accurate Packaging Property Tacoma, Washington

5  
PLATE





Applied Geotechnology Inc.  
Geotechnical Engineering  
Geology & Hydrogeology

Solidus, Inc. - Accurate Packaging Property  
Tacoma, Washington

**SOIL CLASSIFICATION/LEGEND**

PLATE

**LEGEND**

**MOISTURE DESCRIPTION**

Dry - Considerably less than optimum for compaction  
Moist - Near optimum moisture content  
Wet - Over optimum moisture content  
Saturated - Below water table, in capillary zone, or in perched groundwater

---

**BLOWS/FOOT**

Hammer is 140 pounds with 30 inch drop, unless otherwise noted  
S - SPT Sampler (2.0 inch O.D.)  
T - Thin Wall Sampler (2.8 inch Sample)  
H - Split Barrel Sampler (2.4 inch Sample)

---

**GRAPHIC LOG**

Well Defined Change (solid line)  
Gradational Change (dashed line)  
Obscure Change (dotted line)  
End of Exploration (dash-dot line)

---

**SAMPLE**

Undisturbed (solid square)  
Bulk (cross-hatched square)  
Not Recovered (open square)

---

**LABORATORY TESTS**

Consol - Consolidation  
LL - Liquid Limit  
PL - Plastic Limit  
Gs - Specific Gravity  
SA - Size Analysis  
Tx - Triaxial Shear  
DS - Direct Shear  
VS - Vane Shear  
Comp - Compaction  
UU - Unconsolidated • Undrained  
CU - Consolidated • Undrained  
CD - Consolidated • Drained

**UNIFIED SOIL CLASSIFICATION SYSTEM**

MAJOR DIVISIONS		TYPICAL NAMES	
FINE GRAINED SOILS MORE THAN HALF IS SMALLER THAN NO. 200 SIEVE	SILTS AND CLAYS LIQUID LIMIT GREATER THAN 50	PI	PEAT AND OTHER HIGHLY ORGANIC SOILS
		OH	ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTS
		CH	INORGANIC CLAYS OF HIGH PLASTICITY FAT CLAYS
		MH	INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SANDY OR SILTY SOILS, ELASTIC SILTS
	SILTS AND CLAYS LIQUID LIMIT LESS THAN 50	OL	ORGANIC CLAYS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY
		CL	INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS
		ML	INORGANIC SILTS AND VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS, OR CLAYEY SILTS WITH SLIGHT PLASTICITY
COARSE GRAINED SOILS MORE THAN HALF IS LARGER THAN NO. 200 SIEVE	SANDS MORE THAN HALF IS LARGER THAN NO. 4 SIEVE SIZE IS LARGER THAN COARSE FRACTION LITTLE OR NO FINES	SC	CLAYEY SANDS, POORLY GRADED SAND - CLAY MIXTURES
		SM	SILTY SANDS, POORLY GRADED SAND - SILT MIXTURES
		SP	POORLY GRADED SANDS, GRAVELLY SANDS
		SW	WELL GRADED SANDS, GRAVELLY SANDS
	GRAVELS MORE THAN HALF IS LARGER THAN NO. 4 SIEVE SIZE IS LARGER THAN COARSE FRACTION LITTLE OR NO FINES	GC	CLAYEY GRAVELS, POORLY GRADED GRAVEL - SAND - CLAY MIXTURES
		GM	SILTY GRAVELS, POORLY GRADED GRAVEL - SAND - SILT MIXTURES
		GP	POORLY GRADED GRAVELS, GRAVEL - SAND MIXTURES
		GW	WELL GRADED GRAVELS, GRAVEL - SAND MIXTURES




Applied Geotechnology Inc.  
Geotechnical Engineering  
Geology & Hydrogeology

Solidus, Inc. - Accurate Packaging Property  
Tacoma, Washington

# WELL INSTALLATION LEGEND

PLATE 2



# SOUND ANALYTICAL SERVICES, INC.


Lilyblad Petroleum  
Page 2 of 2  
Lab No. A 6023  
May 10, 1989

IDENTIFICATION:  
Sample Received on 4-26-89  
P.O. No. 4813

Sample No. 2 : N.W. Processing Well A-3

ANALYSIS:

	Concentration	Detection Limit	
	< 5.0		Oil and Grease, mg/l
	5.9		pH
	< 0.05	0.05	Methylene chloride, mg/l
	< 0.05	0.05	1,1,1-Trichloroethylene, mg/l
	< 0.05	0.05	Tetrachloroethylene, mg/l
	< 0.05	0.05	Acetone, mg/l
	< 0.05	0.05	Ethanol, mg/l
	< 10	10.0	Isopropanol, mg/l
	< 10	10.0	Methanol, mg/l
	< 0.05	0.05	Methyl ethyl ketone, mg/l
	< 0.05	0.05	Methyl isobutyl ketone, mg/l
	< 0.05	0.05	Toluene, mg/l
	< 0.05	0.05	Xylenes, mg/l

SOUND ANALYTICAL SERVICES  
  
STAN P. PALMQUIST

This report is issued solely for the use of the person or company to whom it is addressed. This laboratory accepts responsibility only for the due performance of analysis in accordance with industry acceptable practice. In no event shall Sound Analytical Services, Inc. or its employees be responsible for consequential or special damages in any kind or in any amount.

4813

4813

4812

TO Sound  
 ADDRESS  
 SHIP TO Lilyblad  
 ADDRESS

REQ. NO.	DATE	TERMS	HOW SHIP	PLEASE SUPPLY ITEMS LISTED BELOW	PRICE	UNIT
1	4-26-89			Oil & Grease	25 00	
2				pH	5 00	
3				methylene chloride	↑	
4				1,1,1-trichloroethylene	110 00	
5				tetrachloroethylene	↓	
6				acetone	↑	
7				methyl ethyl ketone	↓	
8				methyl isobutyl ketone	175 00	
9				xylene	↓	
10				toluene	↓	
11				methanol	↓	

DISPOSITION OF MATERIAL  
 RECEIVING CLERK  
 PURCHASING AGENT

REDIFORM, RECEIVING DEPT. COPY  
 POLY PAK (50 SL IP141 15 141

TO Sound  
 ADDRESS  
 SHIP TO Lilyblad  
 ADDRESS

REQ. NO.	DATE	TERMS	HOW SHIP	PLEASE SUPPLY ITEMS LISTED BELOW	PRICE	UNIT
1	4-26-89			ethanol	175.00	
2				isopropanol	cont.	
3				tests for lead	40 00	
4				Arsenic, Chromium	↓	
5				Zinc	↓	
6						
7						
8						
9						
10						
11						

DISPOSITION OF MATERIAL  
 RECEIVING CLERK  
 PURCHASING AGENT

REDIFORM, RECEIVING DEPT. COPY  
 POLY PAK (50 SETS) IP141 15 141

# SOUND ANALYTICAL SERVICES, INC.

Lillyblad Petroleum

Page 2 of 2

Lab No. A 6023

May 10, 1989

Revised May 25, 1989

IDENTIFICATION:

Sample Received on 4-26-89

P.O. No. 4813

Sample No. 2 : N.W. Processing Well A-3

ANALYSIS:

Detection Limit	Concentration	
	< 5.0	Oil and Grease, mg/l
	5.9	pH
0.05	< 0.05	Methylene chloride, mg/l
0.05	< 0.05	1,1,1-Trichloroethylene, mg/l
0.05	< 0.05	Tetrachloroethylene, mg/l
0.05	< 0.05	Acetone, mg/l
0.05	< 0.05	Ethanol, mg/l
10.0	< 10	Isopropanol, mg/l
10.0	< 10	Methanol, mg/l
0.05	< 0.05	Methyl ethyl ketone, mg/l
0.05	< 0.05	Methyl isobutyl ketone, mg/l
0.05	< 0.05	Toluene, mg/l
0.05	< 0.05	Xylenes, mg/l
		<u>Total Metals:</u>
	< 0.1	Arsenic, mg/l
	< 0.1	Chromium, mg/l
	< 0.1	Lead, mg/l
	< 0.1	Zinc, mg/l

The Original Lab Report was revised to include additional testing.


SOUND ANALYTICAL SERVICES

STAN P. PALMQUIST











**LEGEND**

**L-1** Well number and approximate location

**REFERENCE:**  
 Undated, unutilized site utility plan provided by Solisus, Inc.


**Applied Geotechnology Inc.**  
 Geotechnical Engineering  
 Geology & Hydrogeology

**SITE PLAN**  
 Solisus Inc. - Parcel A/Lindal Property  
 Tacoma, Washington

JOB NUMBER: 15.181.001  
 SCALE: N8  
 APPROVED:   
 DATE: 2/2/17  
 REVISION:   
 DATE:

PAGE 2



Applied Geotechnology Inc.  
Geotechnical Engineering  
& Hydrogeology

Sollidus Inc. - Parcel A/Lindal Property  
Tacoma, Washington

# LOG AND INSTALLATION - WELL L-1

PLATE  
**3**

DATE

REVISED


2/2/87

APPROVED

DRAWN

NB

JOB NUMBER  
15,181,001



Equipment  
Mobile B61

Sample  
Date 1/7/87

Elevation  
Not measured



Applied Geotechnology Inc.  
Geotechnical Engineering  
& Hydrogeology

**SOIL CLASSIFICATION/LEGEND**  
Solidus Inc. - Parcel A/Lindal Property  
Tacoma, Washington

PLATE

**LEGEND**

<p><b>SAMPLE</b></p> <p> <input type="checkbox"/> Not Recovered  <input checked="" type="checkbox"/> Bulk  <input checked="" type="checkbox"/> "Undisturbed"                 </p>		<p><b>GRAPHIC LOG</b></p> <p>                     Well Defined Change                      Gradational Change                      Obscure Change                      End of Exploration                 </p>	<p><b>BLOWS/FOOT</b></p> <p>                     Hammer is 140 pounds with 30 inch drop, unless otherwise noted                      S - SPT Sampler (2.0 Inch O.D.)                      T - Thin Wall Sampler (2.8 Inch Sample)                      H - Split Barrel Sampler (2.4 Inch Sample)                 </p>	<p><b>MOISTURE DESCRIPTION</b></p> <p>                     Dry - Considerably less than optimum for compaction                      Moist - Near optimum moisture content                      Wet - Over optimum moisture content                      Saturated - Below water table, in capillary zone, or in perched groundwater                 </p>
<p><b>LABORATORY TESTS</b></p> <p>                     Consol - Consolidation                      LL - Liquid Limit                      PL - Plastic Limit                      GS - Specific Gravity                      SA - Size Analysis                      TX - Triaxial Shear                      DS - Direct Shear                      VS - Vane Shear                      Comp - Compaction                 </p>		<p>                     UU - Unconsolidated • Undrained                      CU - Consolidated • Undrained                      CD - Consolidated • Drained                 </p>		

**UNIFIED SOIL CLASSIFICATION SYSTEM**

MAJOR DIVISIONS		TYPICAL NAMES	
<p><b>FINE GRAINED SOILS</b> MORE THAN HALF IS SMALLER THAN NO. 200 SIEVE</p>	<p><b>SILTS AND CLAYS</b> LIQUID LIMIT LESS THAN 50</p>	ML	INORGANIC SILTS AND VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS, OR CLAYEY SILTS WITH SLIGHT PLASTICITY
		CL	INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS
		OL	ORGANIC CLAYS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY
	<p><b>SILTS AND CLAYS</b> LIQUID LIMIT GREATER THAN 50</p>	MH	INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SANDY OR SILTY SOILS, ELASTIC SILTS
		CH	INORGANIC CLAYS OF HIGH PLASTICITY FAT CLAYS
		OH	ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTS
<p><b>COARSE GRAINED SOILS</b> MORE THAN HALF IS LARGER THAN NO. 200 SIEVE</p>	<p><b>SANDS</b> MORE THAN HALF COARSE FRACTION IS LARGER THAN NO. 4 SIEVE SIZE</p>	SW	WELL GRADED SANDS, GRAVELLY SANDS
		SP	POORLY GRADED SANDS, GRAVELLY SANDS
		SM	SILTY SANDS, POORLY GRADED SAND - SILT MIXTURES
		SC	CLAYEY SANDS, POORLY GRADED SAND - CLAY MIXTURES
		GM	SILTY GRAVELS, POORLY GRADED GRAVEL - SAND - SILT MIXTURES
	<p><b>GRAVELS</b> MORE THAN HALF COARSE FRACTION IS LARGER THAN NO. 4 SIEVE SIZE</p>	GW	WELL GRADED GRAVELS, GRAVEL - SAND MIXTURES
		GP	POORLY GRADED GRAVELS GRAVEL - SAND MIXTURES
		GM	SILTY GRAVELS, POORLY GRADED GRAVEL - SAND - SILT MIXTURES
		GC	CLAYEY GRAVELS, POORLY GRADED GRAVEL - SAND - CLAY MIXTURES
		GW	WELL GRADED GRAVELS, GRAVEL - SAND MIXTURES




Applied Geotechnology Inc.  
Geotechnical Engineering  
Geology & Hydrogeology


# WELL INSTALLATION LEGEND

Solidus Inc. - Parcel A/Lindal Property  
Tacoma, Washington

PLATE  
**2**

DATE: 1/26/87  
REVISED: DATE: 1/19/87  
NB  
15,181,001






ANALYSIS OF WATER


I-2

OK


SAMPLE NO.	DATE	TIME COLLECTED	LOCATION	SAMPLING METHOD RESULTS		
A-6023 <i>Sample Analyzed</i>	4-26	1:30 PM	<i>water level from top of casing</i>	<i>52.1</i>	<i>---</i>	<i>---</i>
OIL & GREASE (mg/l)	< 5.0					
pH	5.7					
TOTAL ORGANIC CARBON (mg/l)	< 0.05					
HYDROCARBONS (mg/l)	< 0.05					
METHYLENE CHLORIDE	< 0.05					
1,1,1-TRICHLOROETHYLENE	< 0.05					
TETRACHLOROETHYLENE	< 0.05					
ACETONE	< 0.05					
METHYL ETHYL KETONE	< 0.05					
METHYL ISOBUTYL KETONE	< 0.05					
XYLENE	< 0.05					
TOLUENE	< 0.05					
METHANOL	< 0.05					
METHANOL	< 1.0					
ETHANOL	< 1.0					
ISOPROPANOL	< 1.0					
SPECIFIC CONDUCTANCE	< 10					
LEAD (mg/l)	< 0.1					
CHROMIUM (mg/l)	< 0.1					
ZINC (mg/l)	< 0.1					
ARSENIC (mg/l)	< 0.1					
CADIUM	< 0.1					
HEXAVALENT CHROMIUM						
NITRATE as N						
OTHER						




**LEGEND**

L-1  Well number and approximate location

REFERENCE:  
 Underred, unitted site utility plan provided by  
 Solidus, Inc.


**Applied Geotechnology Inc.**  
 Geotechnical Engineering  
 Geology & Hydrogeology

**SITE PLAN**  
 Solidus Inc. - Parcel A/Lindal Property  
 Tacoma, Washington

DRAWING NUMBER: 15.181.001  
 SCALE: N8  
 APPROVED:   
 DATE: 2/2/87  
 REVISION:   
 DATE:

PAGE 2




Applied Geotechnology Inc.  
Geotechnical Engineering  
Geology & Hydrogeology

Solidus Inc. - Parcel A/Lindal Property  
Tacoma, Washington

LOG AND INSTALLATION - WELL L-2



PLATE







Applied Geotechnology Inc.  
Geotechnical Engineering  
Geology & Hydrogeology

**SOIL CLASSIFICATION/LEGEND**  
Solidus Inc. - Parcel A/Indal Property  
Tacoma, Washington

PLATE

**LEGEND**

**MOISTURE DESCRIPTION**  
 Hammer is 140 pounds with 30 inch drop, unless otherwise noted  
 S - SPT Sampler (2.0 inch O.D.)  
 T - Thin Wall Sampler (2.8 inch Sample)  
 H - Split Barrel Sampler (2.4 inch Sample)

**BLOWS/FOOT**  
 Dry - Considerably less than optimum for compaction  
 Moist - Near optimum moisture content  
 Wet - Over optimum moisture content  
 Saturated - Below water table, in capillary zone, or in perched groundwater

**GRAPHIC LOG**  
 Well Defined Change (solid line)  
 Gradational Change (dashed line)  
 Obscure Change (dotted line)  
 End of Exploration (dash-dot line)

**SAMPLE**  
 "Undisturbed" (solid square)  
 Bulk (cross-hatched square)  
 Not Recovered (open square)

**LABORATORY TESTS**  
 Consol - Consolidation  
 LL - Liquid Limit  
 PL - Plastic Limit  
 GS - Specific Gravity  
 SA - Size Analysis  
 TX - Triaxial Shear  
 DS - Direct Shear  
 VS - Vane Shear  
 Comp - Compaction  
 UU - Unconsolidated • Undrained  
 CU - Consolidated • Undrained  
 CD - Consolidated • Drained

**UNIFIED SOIL CLASSIFICATION SYSTEM**

MAJOR DIVISIONS		TYPICAL NAMES		
FINE GRAINED SOILS MORE THAN HALF IS SMALLER THAN NO. 200 SIEVE	SILTS AND CLAYS LIQUID LIMIT LESS THAN 50	ML	INORGANIC SILTS AND VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS, OR CLAYEY SILTS WITH SLIGHT PLASTICITY	
		CL	INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS	
		OL	ORGANIC CLAYS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY	
		MH	INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SANDY OR SILTY SOILS, ELASTIC SILTS	
		CH	INORGANIC CLAYS OF HIGH PLASTICITY FAT CLAYS	
		OH	ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTS	
	COARSE GRAINED SOILS MORE THAN HALF IS LARGER THAN NO. 200 SIEVE	SANDS MORE THAN HALF IS LARGER THAN NO. 4 SIEVE SIZE COARSE FRACTION IS LARGER THAN NO. 4 SIEVE SIZE	SW	WELL GRADED SANDS, GRAVELLY SANDS
			SP	POORLY GRADED SANDS, GRAVELLY SANDS
			SM	SILTY SANDS, POORLY GRADED SAND - SILT MIXTURES
			SC	CLAYEY SANDS, POORLY GRADED SAND - CLAY MIXTURES
GRAVELS MORE THAN HALF IS LARGER THAN NO. 4 SIEVE SIZE COARSE FRACTION IS LARGER THAN NO. 4 SIEVE SIZE		GW	WELL GRADED GRAVELS, GRAVEL-SAND MIXTURES	
		GP	POORLY GRADED GRAVELS, GRAVEL-SAND MIXTURES	
		GM	SILTY GRAVELS, POORLY GRADED GRAVEL-SAND - SILT MIXTURES	
		GC	CLAYEY GRAVELS, POORLY GRADED GRAVEL-SAND - CLAY MIXTURES	
SANDS CLEAN SANDS WITH LITTLE OR NO FINES		SW	WELL GRADED SANDS, GRAVELLY SANDS	
		SP	POORLY GRADED SANDS, GRAVELLY SANDS	
SANDS CLEAN SANDS WITH LITTLE OR NO FINES	SM	SILTY SANDS, POORLY GRADED SAND - SILT MIXTURES		
	SC	CLAYEY SANDS, POORLY GRADED SAND - CLAY MIXTURES		




Applied Geotechnology Inc.  
Geotechnical Engineering  
Geology & Hydrogeology

Solidus Inc. - Parcel A/Lindal Property  
Tacoma, Washington

# WELL INSTALLATION LEGEND

PLATE 2



# SOUND ANALYTICAL SERVICES, INC.

SPECIALIZING IN INDUSTRIAL & TOXIC WASTE ANALYSIS

4630 PACIFIC HIGHWAY EAST, SUITE B-14, TACOMA, WASHINGTON 98424 - TELEPHONE (206) 922-2310 - FAX (206) 922-5047

Report To: Lillyblad Petroleum

Date: May 10, 1989

Report On: Analysis of Liquid

Lab No.: A 6023

Page 1 of 2

**IDENTIFICATION:**

Sample Received on 4-26-89  
P.O. No. 4813

Sample No. 1: N.W. Processing Well T-2

**ANALYSIS:**

Concentration	Detection Limit
Oil and Grease, mg/l	< 5.0
pH	5.7
Methylene chloride, mg/l	< 0.05
1,1,1-Trichloroethylene, mg/l	< 0.05
Tetrachloroethylene, mg/l	< 0.05
Acetone, mg/l	< 0.05
Ethanol, mg/l	< 10
Isopropanol, mg/l	< 10
Methanol, mg/l	< 10
Methyl ethyl ketone, mg/l	< 0.05
Methyl isobutyl ketone, mg/l	< 0.05
Toluene, mg/l	< 0.05
Xylenes, mg/l	< 0.05

Continued . . . . .

This report is issued solely for the use of the person or company to whom it is addressed. This laboratory accepts responsibility only for the due performance of analysis in accordance with industry acceptable practice. In no event shall Sound Analytical Services, Inc. or its employees be responsible for consequential or special damages in any kind or in any amount.

# SOUND ANALYTICAL SERVICES, INC.

SPECIALIZING IN INDUSTRIAL & TOXIC WASTE ANALYSIS

4630 PACIFIC HIGHWAY EAST, SUITE B-14, TACOMA, WASHINGTON 98424 • TELEPHONE (206) 922-2310 • FAX (206) 922-5047

Report To: Lilyblad Petroleum

Report On: Analysis of Liquid

Date: May 10, 1989  
Revised May 25, 1989

Lab No.: A 6023  
Page 1 of 2

**IDENTIFICATION:**

Sample Received on 4-26-89  
P.O. No. 4813

Sample No. 1: N.W. Processing Well L-2

**ANALYSIS:**

Detection Limit	Concentration	
	< 5.0	Oil and Grease, mg/l
	5.7	pH
0.05	< 0.05	Methylene Chloride, mg/l
0.05	< 0.05	1,1,1-Trichloroethylene, mg/l
0.05	< 0.05	Tetrachloroethylene, mg/l
0.05	< 0.05	Acetone, mg/l
10.0	< 10	Ethanol, mg/l
10.0	< 10	Isopropanol, mg/l
10.0	< 10	Methanol, mg/l
0.05	< 0.05	Methyl ethyl ketone, mg/l
0.05	< 0.05	Methyl isobutyl ketone, mg/l
0.05	< 0.05	Toluene, mg/l
0.05	< 0.05	Xylenes, mg/l
		<b>Total Metals:</b>
	< 0.1	Arsenic, mg/l
	< 0.1	Chromium, mg/l
	< 0.1	Lead, mg/l
	< 0.1	Zinc, mg/l

Continued . . . . .

This report is issued solely for the use of the person or company to whom it is addressed. This laboratory accepts responsibility only for the due performance of analysis in accordance with industry acceptable practice. In no event shall Sound Analytical Services, Inc. or its employees be responsible for consequential or special damages in any kind or in any amount.

# SOUND ANALYTICAL SERVICES, INC.

SPECIALIZING IN INDUSTRIAL & TOXIC WASTE ANALYSIS

4630 PACIFIC HIGHWAY EAST, SUITE B-14, TACOMA, WASHINGTON 98424 - TELEPHONE (206) 922-2310 - FAX (206) 922-5047

Report To: Lillyblad Petroleum

Date: May 10, 1989

Report On: Analysis of Liquid

Lab No.: A 6023

Page 1 of 2

IDENTIFICATION:

Sample Received on 4-26-89  
P.O. No. 4813

Sample No. 1: N.W. Processing Well T-2

ANALYSIS:

Detection Limit	Concentration	
	< 5.0	Oil and Grease, mg/l
	5.7	pH
0.05	< 0.05	Methylene Chloride, mg/l
0.05	< 0.05	1,1,1-Trichloroethylene, mg/l
0.05	< 0.05	Tetrachloroethylene, mg/l
0.05	< 0.05	Acetone, mg/l
10.0	< 10	Ethanol, mg/l
10.0	< 10	Isopropanol, mg/l
10.0	< 10	Methanol, mg/l
0.05	< 0.05	Methyl ethyl ketone, mg/l
0.05	< 0.05	Methyl isobutyl ketone, mg/l
0.05	< 0.05	Toluene, mg/l
0.05	< 0.05	Xylenes, mg/l

Continued . . . . .

This report is issued solely for the use of the person or company to whom it is addressed. This laboratory accepts responsibility only for the due performance of analysis in accordance with industry acceptable practice. In no event shall Sound Analytical Services, Inc. or its employees be responsible for consequential or special damages in any kind or in any amount.

REDIFORM

427898

PURCHASING AGENT

PLEASE SEND COPIES OF YOUR INVOICE

INVOICES PASSED FOR PAYMENT

QUANTITY	PLEASE SUPPLY ITEMS LISTED BELOW	PRICE	UNIT
2	Oil # Grease	25 00	
2	pH	5 00	
2	methylene chloride	110 00	
2	1,1,1-trichloroethylene		
2	tetra chloroethylene		
2	acetone		
2	methyl ethyl ketone		
2	methyl isobutyl ketone	175 00	
2	xylene		
2	toluene		
2	methanol		

OK

REQ. NO. DATE 4-26-89 NMP FOR WELLS A-3 # L-2 DATE REQUIRED ASAP HOW SHIP TERMS

TO Sound

ADDRESS

SHIP TO L:14141

ADDRESS

4813


PURCHASE ORDER

ORDER NO.











**LEGEND**

L-1  Well number and approximate location

**REFERENCE:**  
 Undated, unissued site utility plan provided by Solidus, Inc.

 <p>Applied Geotechnology Inc.        Geotechnical Engineering        Geology &amp; Hydrogeology</p>	<p><b>SITE PLAN</b>        Solidus Inc. - Parcel A Lindal Property        Tacoma, Washington</p>	<p>DATE</p>	<p>DATE</p>
		<p>15.181.001</p>	<p>2/2/17</p>

PAGE 2




Applied Geotechnology Inc.  
Geotechnical Engineering  
Geology & Hydrogeology

Solidus Inc. - Parcel A Lindal Property  
Tacoma, Washington

LOG AND INSTALLATION - WELL L-3

PLATE 5





Applied Geotechnical Engineering & Hydrogeology  
 Geotechnical Engineering  
 Tacoma, Washington

**SOIL CLASSIFICATION/LEGEND**

Solidus Inc. - Parcel A/Alndal Property  
 Tacoma, Washington

PLATE

**LEGEND**

**MOISTURE DESCRIPTION**

Saturated - Below water table, in capillary zone, or in perched groundwater  
 Wet - Over optimum moisture content  
 Moist - Near optimum moisture content  
 Dry - Considerably less than optimum for compaction

**BLOWS/FOOT**

Hammer is 140 pounds with 30 inch drop, unless otherwise noted  
 S - SPT Sampler (2.0 inch O.D.)  
 T - Thin Wall Sampler (2.8 inch Sample)  
 H - Split Barrel Sampler (2.4 inch Sample)

**GRAPHIC LOG**

Well Defined Change (solid line)  
 Gradational Change (dashed line)  
 Obscure Change (dotted line)  
 End of Exploration (dash-dot line)

**SAMPLE**

Undisturbed (solid black square)  
 Bulk (square with 'X')  
 Not Recovered (open square)

**LABORATORY TESTS**

Consol - Consolidation  
 LL - Liquid Limit  
 PL - Plastic Limit  
 GS - Specific Gravity  
 SA - Size Analysis  
 TX - Triaxial Shear  
 DS - Direct Shear  
 VS - Vane Shear  
 Comp - Compaction  
 UU - Unconsolidated • Undrained  
 CU - Consolidated • Undrained  
 CD - Consolidated • Drained

MAJOR DIVISIONS		TYPICAL NAMES		
FINE GRAINED SOILS MORE THAN HALF IS SMALLER THAN NO. 200 SIEVE	SILTS AND CLAYS LIQUID LIMIT LESS THAN 50	ML	INORGANIC SILTS AND VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS, OR CLAYEY SILTS WITH SLIGHT PLASTICITY	
		CL	INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS	
		OL	ORGANIC CLAYS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY	
		MH	INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SANDY OR SILTY SOILS, ELASTIC SILTS	
		CH	INORGANIC CLAYS OF HIGH PLASTICITY FAT CLAYS	
	SILTS AND CLAYS LIQUID LIMIT GREATER THAN 50	OH	ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTS	
		PI	PEAT AND OTHER HIGHLY ORGANIC SOILS	
		SANDS	GW	WELL GRADED GRAVELS, GRAVEL-SAND MIXTURES
			GP	POORLY GRADED GRAVELS GRAVEL-SAND MIXTURES
			GM	SILTY GRAVELS, POORLY GRADED GRAVEL-SAND - SILT MIXTURES
GC	CLAYEY GRAVELS, POORLY GRADED GRAVEL-SAND - CLAY MIXTURES			
COARSE GRAINED SOILS MORE THAN HALF IS LARGER THAN NO. 200 SIEVE	GRAVELS CLEAN GRAVELS WITH LITTLE OR NO FINES	SM	SILTY SANDS, POORLY GRADED SAND - SILT MIXTURES	
		SC	CLAYEY SANDS, POORLY GRADED SAND - CLAY MIXTURES	
	SANDS CLEAN SANDS WITH LITTLE OR NO FINES	SW	WELL GRADED SANDS, GRAVELLY SANDS	
		SP	POORLY GRADED SANDS, GRAVELLY SANDS	




Applied Geotechnology Inc.  
Geotechnical Engineering  
Geology & Hydrogeology

# WELL INSTALLATION LEGEND

Solidus Inc. - Parcel A/Lindal Property  
Tacoma, Washington


2

PLATE











**LEGEND**

L-1 Well number and approximate location

**REFERENCE:**  
 Updated, unutilized site utility plan provided by Solidus, Inc.

 <p><b>Applied Geotechnology Inc.</b>          Geotechnical Engineering          Geology &amp; Hydrogeology</p>	<p><b>SITE PLAN</b>          Solidus Inc. - Parcel A/Lindal Property          Tacoma, Washington</p>	DRAWN NB	APPROVED 	DATE 2/2/87	REVISION 	DATE 
		JOB NUMBER 15.181.001	SCALE 1" = 30'	2		




Applied Geotechnics Inc.  
Geotechnical Engineering  
Geology & Hydrogeology

Solidus Inc. - Parcel A/Lndal Property  
Tacoma, Washington

# LOG AND INSTALLATION - WELL L-4

6  
PLATE







Applied Geotechnology Inc.

Geotechnical Engineering  
Geology & Hydrogeology

**SOIL CLASSIFICATION/LEGEND**

Solidus Inc. - Parcel A/Indal Property  
Tacoma, Washington

PLATE

**LEGEND**

<p><b>MOISTURE DESCRIPTION</b></p> <p>Dry - Considerably less than optimum for compaction</p> <p>Moist - Near optimum moisture content</p> <p>Wet - Over optimum moisture content</p> <p>Saturated - Below water table, in capillary zone, or in perched groundwater</p>	
<p><b>BLOWS/FOOT</b></p> <p>Hammer is 140 pounds with 30 inch drop, unless otherwise noted</p> <p>S - SPT Sampler (2.0 Inch O.D.)</p> <p>T - Thin Wall Sampler (2.8 Inch Sample)</p> <p>H - Split Barrel Sampler (2.4 Inch Sample)</p>	
<p><b>GRAPHIC LOG</b></p> <p>Well Defined Change</p> <p>Gradational Change</p> <p>Obscure Change</p> <p>End of Exploration</p>	<p><b>SAMPLE</b></p> <p>Undisturbed</p> <p>Bulk</p> <p>Not Recovered</p>
<p><b>LABORATORY TESTS</b></p> <p>Consol - Consolidation</p> <p>LL - Liquid Limit</p> <p>PL - Plastic Limit</p> <p>Gs - Specific Gravity</p> <p>SA - Size Analysis</p> <p>TX - Triaxial Shear</p> <p>DS - Direct Shear</p> <p>VS - Vane Shear</p> <p>Comp - Compaction</p> <p>UU - Unconsolidated • Undrained</p> <p>CU - Consolidated • Undrained</p> <p>CD - Consolidated • Drained</p>	

**UNIFIED SOIL CLASSIFICATION SYSTEM**

MAJOR DIVISIONS		TYPICAL NAMES		
<p><b>FINE GRAINED SOILS</b></p> <p>MORE THAN HALF IS SMALLER THAN NO. 200 SIEVE</p>	<p><b>SILTS AND CLAYS</b></p> <p>LIQUID LIMIT LESS THAN 50</p>	<p>GW</p> <p>WELL GRADED GRAVELS, GRAVEL-SAND MIXTURES</p>	<p>GW</p> <p>WELL GRADED GRAVELS, GRAVEL-SAND MIXTURES</p>	
		<p>GP</p> <p>POORLY GRADED GRAVELS, GRAVEL-SAND MIXTURES</p>	<p>GP</p> <p>POORLY GRADED GRAVELS, GRAVEL-SAND MIXTURES</p>	
		<p>GM</p> <p>SILTY GRAVELS, POORLY GRADED GRAVEL-SAND • SILT MIXTURES</p>	<p>GM</p> <p>SILTY GRAVELS, POORLY GRADED GRAVEL-SAND • SILT MIXTURES</p>	
		<p>GC</p> <p>CLAYEY GRAVELS, POORLY GRADED GRAVEL-SAND • CLAY MIXTURES</p>	<p>GC</p> <p>CLAYEY GRAVELS, POORLY GRADED GRAVEL-SAND • CLAY MIXTURES</p>	
		<p>SW</p> <p>WELL GRADED SANDS, GRAVELLY SANDS</p>	<p>SW</p> <p>WELL GRADED SANDS, GRAVELLY SANDS</p>	
	<p><b>SANDS</b></p> <p>MORE THAN HALF IS LARGER THAN NO. 4 SIEVE SIZE IS LARGER THAN COARSE FRACTION</p>	<p><b>GRAVELS</b></p> <p>LIQUID LIMIT LESS THAN 50</p>	<p>SC</p> <p>CLAYEY SANDS, POORLY GRADED SAND - CLAY MIXTURES</p>	<p>SC</p> <p>CLAYEY SANDS, POORLY GRADED SAND - CLAY MIXTURES</p>
			<p>SM</p> <p>SILTY SANDS, POORLY GRADED SAND - SILT MIXTURES</p>	<p>SM</p> <p>SILTY SANDS, POORLY GRADED SAND - SILT MIXTURES</p>
		<p><b>SILTS AND CLAYS</b></p> <p>LIQUID LIMIT GREATER THAN 50</p>	<p>ML</p> <p>INORGANIC SILTS AND VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS, OR CLAYEY SILTS WITH SLIGHT PLASTICITY</p>	<p>ML</p> <p>INORGANIC SILTS AND VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS, OR CLAYEY SILTS WITH SLIGHT PLASTICITY</p>
			<p>CL</p> <p>INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS</p>	<p>CL</p> <p>INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS</p>
			<p>OL</p> <p>ORGANIC CLAYS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY</p>	<p>OL</p> <p>ORGANIC CLAYS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY</p>
<p><b>COARSE GRAINED SOILS</b></p> <p>MORE THAN HALF IS SMALLER THAN NO. 200 SIEVE</p>	<p><b>SANDS</b></p> <p>LIQUID LIMIT GREATER THAN 50</p>	<p>MH</p> <p>INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SANDY OR SILTY SOILS, ELASTIC SILTS</p>	<p>MH</p> <p>INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SANDY OR SILTY SOILS, ELASTIC SILTS</p>	
		<p>CH</p> <p>INORGANIC CLAYS OF HIGH PLASTICITY FAT CLAYS</p>	<p>CH</p> <p>INORGANIC CLAYS OF HIGH PLASTICITY FAT CLAYS</p>	
		<p>OH</p> <p>ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTS</p>	<p>OH</p> <p>ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTS</p>	
		<p>P</p> <p>PEAT AND OTHER HIGHLY ORGANIC SOILS</p>	<p>P</p> <p>PEAT AND OTHER HIGHLY ORGANIC SOILS</p>	




Applied Geotechnology Inc.  
Geotechnical Engineering  
Geology & Hydrogeology

# WELL INSTALLATION LEGEND

Solidus Inc. - Parcel A/Lindal Property  
Tacoma, Washington

2

PLATE



# SOUND ANALYTICAL SERVICES, INC.

SPECIALIZING IN INDUSTRIAL & TOXIC WASTE ANALYSIS

4630 PACIFIC HIGHWAY EAST, SUITE B-14, TACOMA, WASHINGTON 98424 - TELEPHONE (206) 922-2310 - FAX (206) 922-5047

Report To: Lilyblad Petroleum

Date: May 16, 1989  
Revised May 25, 1989

Report on: Analysis of Liquid

Lab No.: A 6207

IDENTIFICATION:

Sample Received on 5-11-89  
P.O. No. 4840

Sample No. 1: Well Sample Nearest Centrifuge Room L-4  
5-11-89 3:15 PM

ANALYSIS:

Detection Limit	Concentration	
5.0	12.1	Oil and Grease, mg/l
	6.7	pH
0.05	< 0.05	Methylene chloride, mg/l
0.05	< 0.05	1,1,1-Trichloroethylene, mg/l
0.05	< 0.05	Tetrachloroethylene, mg/l
0.05	< 0.05	Acetone, mg/l
0.05	< 0.05	Ethanol, mg/l
10.0	< 10.0	Isopropanol, mg/l
10.0	< 10.0	Methanol, mg/l
0.05	< 0.05	Methyl ethyl ketone, mg/l
0.05	< 0.05	Methyl isobutyl ketone, mg/l
0.05	< 0.05	Toluene, mg/l
0.05	< 0.05	Xylenes, mg/l
		<u>Total Metals:</u>
	0.4	Arsenic, mg/l
	< 0.1	Chromium, mg/l
	< 0.1	Lead, mg/l
	< 0.1	Zinc, mg/l

Original Lab Report was revised to include additional testing.

SOUND ANALYTICAL SERVICES

STAN P. PALMQUIST

This report is issued solely for the use of the person or company to whom it is addressed. This laboratory accepts responsibility only for the due performance of analysis in accordance with industry acceptable practice. In no event shall Sound Analytical Services, Inc. or its employees be responsible for consequential or special damages in any kind or in any amount.

REDIFORM

OFFICE COPY

POLY PAK (50 SETS) 1P141 1S 141

PURCHASING AGENT

PLEASE SEND COPIES OF YOUR INVOICE

INVOICES PASSED FOR PAYMENT

QUANTITY	PLEASE SUPPLY ITEMS LISTED BELOW	PRICE	UNIT
1	methanol		
1	ethanol		
1	isopropanol		
1	tests for lead	40.00	
5	Zinc Chromium		
6	Arsenic		
7			
8			
9	5-15-89 AA		
10	Copy & CT for well bank		
11	(GK)		

FOR **Well L-2**  
 DATE REQUIRED **ASAP**  
 HOW SHIP \_\_\_\_\_  
 TERMS \_\_\_\_\_  
 DATE **5-11-89**

TO **Sound Analytical**  
 ADDRESS \_\_\_\_\_  
 SHIP TO **Lilyblad**  
 ADDRESS \_\_\_\_\_  
 change Northwest Processing  
 ADDRESS \_\_\_\_\_

PURCHASE ORDER

4840

(cont)

~~1843~~

ORDER NO.

OK FOR PYMT \_\_\_\_\_  
 CHG ACCT # 612108 \_\_\_\_\_  
 VENDOR \_\_\_\_\_  
 TERMS 138179 \_\_\_\_\_  
 Net 30

POSTED

NET AMOUNT: 40.00  
 TAX: 0.00  
 TOTAL DUE: 40.00

40.00

1 METALS @ \$40.00 EA

CUST ID : LILY  
 DUE DATE: 06/25/89  
 TERMS: : NET 30

RE: P.O. NO. 4840

INVOICE NUMBER: A6207a  
 INVOICE DATE : 05/26/89  
 Lybia Petroleum, Inc.  
 P.O. Box 1556  
 Tacoma, WA 98401

4630 Pacific Hwy E, Suite B-14 • Tacoma, Washington 98424 • (206) 922-2310

# SOUND ANALYTICAL SERVICES, INC.

# SOUND ANALYTICAL SERVICES, INC.

SPECIALIZING IN INDUSTRIAL & TOXIC WASTE ANALYSIS

4630 PACIFIC HIGHWAY EAST, SUITE B-14, TACOMA, WASHINGTON 98424 - TELEPHONE (206) 922-2310 - FAX (206) 922-5047

Report To: Lilyblad Petroleum

Date: May 16, 1989

Report On: Analysis of Liquid

Lab No.: A 6207

IDENTIFICATION:

Sample Received on 5-11-89  
P.O. No. 4840

Sample No. 1: Well Sample Nearest Centrifuge Room L-4  
5-11-89 3:15 PM

ANALYSIS:

Detection Limit	Concentration	
5.0	12.1	Oil and Grease, mg/l
	6.7	pH
0.05	< 0.05	Methylene chloride, mg/l
0.05	< 0.05	1,1,1-Trichloroethylene, mg/l
0.05	< 0.05	Tetrachloroethylene, mg/l
0.05	< 0.05	Acetone, mg/l
0.05	< 0.05	Ethanol, mg/l
10.0	< 10.0	Isopropanol, mg/l
10.0	< 10.0	Methanol, mg/l
0.05	< 0.05	Methyl ethyl ketone, mg/l
0.05	< 0.05	Methyl isobutyl ketone, mg/l
0.05	< 0.05	Toluene, mg/l
0.05	< 0.05	Xylenes, mg/l

SOUND ANALYTICAL SERVICES

STAN P. PALMQUIST

This report is issued solely for the use of the person or company to whom it is addressed. This laboratory accepts responsibility only for the due performance of analysis in accordance with industry acceptable practice. In no event shall Sound Analytical Services, Inc. or its employees be responsible for consequential or special damages in any kind or in any amount.

# SOUND ANALYTICAL SERVICES, INC.

SPECIALIZING IN INDUSTRIAL & TOXIC WASTE ANALYSIS

4630 PACIFIC HIGHWAY EAST, SUITE B-14, TACOMA, WASHINGTON 98424 - TELEPHONE (206) 922-2310 - FAX (206) 922-5047

Report To: Lillyblad Petroleum

Date: May 16, 1989

Report on: Analysis of Liquid

Lab No.: A 6207

**IDENTIFICATION:**

Sample Received on 5-11-89  
P.O. No. 4840

Sample No. 1: Well Sample Nearest Centrifuge Room L-4  
5-11-89 3:15 PM

**ANALYSIS:**

Detection Limit	Concentration	
5.0	12.1	Oil and Grease, mg/l
	6.7	pH
0.05	< 0.05	Methylene chloride, mg/l
0.05	< 0.05	1,1,1-Trichloroethylene, mg/l
0.05	< 0.05	Tetrachloroethylene, mg/l
0.05	< 0.05	Acetone, mg/l
0.05	< 0.05	Ethanol, mg/l
10.0	< 10.0	Isopropanol, mg/l
10.0	< 10.0	Methanol, mg/l
10.0	< 10.0	Methyl ethyl ketone, mg/l
0.05	< 0.05	Methyl isobutyl ketone, mg/l
0.05	< 0.05	Toluene, mg/l
0.05	< 0.05	Xylenes, mg/l

SOUND ANALYTICAL SERVICES

STAN P. PALMQUIST

This report is issued solely for the use of the person or company to whom it is addressed. This laboratory accepts responsibility only for the due performance of analysis in accordance with industry acceptable practice. In no event shall Sound Analytical Services, Inc. or its employees be responsible for consequential or special damages in any kind or in any amount.

ORDER NO. 4840

PURCHASE ORDER

TO Sound Analytical  
 ADDRESS  
 SHIP TO Lillyblad  
 ADDRESS change Northwest Processing

REQ. NO. DATE 5-11-89  
 FOR well L-2 DATE REQUIRED ASAP  
 HOW SHIP TERMS

QUANTITY PLEASE SUPPLY ITEMS LISTED BELOW UNIT

QUANTITY	PLEASE SUPPLY ITEMS LISTED BELOW	UNIT
1	oil # grade	25.00
1	pH	5.00
<del>1</del>	<del>impurities</del>	
1	methylene chloride	
1	1,1,1-trichloroethylene	110.00
1	tetra chloroethylene	
1	acetone	
1	methyl ethyl ketone	
1	methyl isobutyl ketone	175.00
1	xylene	
1	toluene (SK)	


INVOICES PASSED FOR PAYMENT  
 PLEASE SEND COPIES OF YOUR INVOICE  
 PURCHASING AGENT  
 Day & Night  
 5/15/89

REDIFORM POLY PAK (50 SETS) 1P141 IS 141 OFFICE COPY










**LEGEND**

**L-1** Well number and approximate location

**REFERENCE:**  
Undated, unutilized site utility plan provided by Solidus, Inc.



 <p><b>Applied Geotechnology Inc.</b> Geotechnical Engineering Geology &amp; Hydrogeology</p>	<p><b>SITE PLAN</b> Solidus Inc. - Parcel A/Lindal Property Tacoma, Washington</p>	<p>DATE 2/2/87</p>	<p>DATE</p>
	<p>15.181.001</p>	<p>2</p>	<p>DATE</p>




Applied Geotechnology Inc.  
Geotechnical Engineering  
Geology & Hydrogeology

Sollidus Inc. - Parcel A Lindal Property  
Tacoma, Washington

# LOG AND INSTALLATION - WELL L-5

PLATE 7



Equipment \_\_\_\_\_ Mobile B61  
 Elevation \_\_\_\_\_ Not measured  
 Date 1/8/87



Applied Geotechnology Inc.  
Geotechnical Engineering  
& Hydrogeology

**SOIL CLASSIFICATION/LEGEND**

Solidus Inc. - Parcel A/Lindal Property  
Tacoma, Washington

PLATE

**LEGEND**

<p><b>SAMPLE</b></p> <ul style="list-style-type: none"> <li><input type="checkbox"/> Not Recovered</li> <li><input checked="" type="checkbox"/> Bulk</li> <li><input checked="" type="checkbox"/> "Undisturbed"</li> </ul>	<p><b>GRAPHIC LOG</b></p> <ul style="list-style-type: none"> <li>Well Defined Change</li> <li>Gradational Change</li> <li>Obscure Change</li> <li>End of Exploration</li> </ul>	<p><b>BLOWS/FOOT</b></p> <p>Hammer is 140 pounds with 30 inch drop, unless otherwise noted</p> <p>S - SPT Sampler (20 inch O.D.) T - Thin Wall Sampler (2.8 inch Sample) H - Split Barrel Sampler (2.4 inch Sample)</p>	<p><b>MOISTURE DESCRIPTION</b></p> <p>Dry - Considerably less than optimum for compaction Moist - Near optimum moisture content Wet - Over optimum moisture content</p> <p>Saturated - Below water table, in capillary zone, or in perched groundwater</p>
<p><b>LABORATORY TESTS</b></p> <ul style="list-style-type: none"> <li>Consol - Consolidation</li> <li>LL - Liquid Limit</li> <li>PL - Plastic Limit</li> <li>Gs - Specific Gravity</li> <li>SA - Size Analysis</li> <li>Tx - Triaxial Shear</li> <li>DS - Direct Shear</li> <li>VS - Vane Shear</li> <li>Comp - Compaction</li> <li>UU - Unconsolidated • Undrained</li> <li>CU - Consolidated • Undrained</li> <li>CD - Consolidated • Drained</li> </ul>			

**UNIFIED SOIL CLASSIFICATION SYSTEM**

MAJOR DIVISIONS	TYPICAL NAMES	SCHEMATIC	DESCRIPTION	LIQUID LIMIT	PLASTICITY INDEX
<b>FINE GRAINED SOILS</b> MORE THAN HALF IS SMALLER THAN NO. 200 SIEVE	<b>SILTS AND CLAYS</b> LIQUID LIMIT GREATER THAN 50	PI	PEAT AND OTHER HIGHLY ORGANIC SOILS		
		OH	ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTS		
		CH	INORGANIC CLAYS OF HIGH PLASTICITY FAT CLAYS		
		MH	INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SANDY OR SILTY SOILS, ELASTIC SILTS		
	<b>SILTS AND CLAYS</b> LIQUID LIMIT LESS THAN 50	OL	ORGANIC CLAYS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY		
		CL	INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS		
		ML	INORGANIC SILTS AND VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS, OR CLAYEY SILTS WITH SLIGHT PLASTICITY		
		SC	CLAYEY SANDS, POORLY GRADED SAND - CLAY MIXTURES		
		SM	SILTY SANDS, POORLY GRADED SAND - SILT MIXTURES		
		<b>COARSE GRAINED SOILS</b> MORE THAN HALF IS LARGER THAN NO. 200 SIEVE	<b>SANDS</b> COARSE FRACTION IS LARGER THAN NO. 4 SIEVE SIZE LITTLE OR NO FINES	SP	POORLY GRADED SANDS, GRAVELLY SANDS
SW	WELL GRADED SANDS, GRAVELLY SANDS				
GC	CLAYEY GRAVELS, POORLY GRADED GRAVEL - SAND - CLAY MIXTURES				
GM	SILTY GRAVELS, POORLY GRADED GRAVEL - SAND - SILT MIXTURES				
<b>GRAVELS</b> COARSE FRACTION IS LARGER THAN NO. 4 SIEVE SIZE LITTLE OR NO FINES	GP		POORLY GRADED GRAVELS GRAVEL-SAND MIXTURES		
	GW		WELL GRADED GRAVELS, GRAVEL-SAND MIXTURES		




Applied Geotechnology Inc.  
Geotechnical Engineering  
Geology & Hydrogeology

Sollidus Inc. - Parcel A/Lindal Property  
Tacoma, Washington

# WELL INSTALLATION LEGEND

PLATE 2





Rec'd and  
3-30-88

98115

Seattle, Washington  
9618 Roosevelt Way, NE  
ROY F. WESTON, INC.

Prepared by

March 1988

LILYBLAD PETROLEUM, INC.  
TACOMA, WASHINGTON

for

GROUNDWATER SAMPLING  
AND ANALYSIS (S&A) PLAN



TABLE OF CONTENTS

SECTION	TITLE	PAGE
SECTION 1	INTRODUCTION	1
1.1	SAMPLE COLLECTION AND HANDLING PROCEDURES	1
1.2	SAMPLE HANDLING PROCEDURES	1
1.3	CHAIN-OF-CUSTODY PROGRAM	2
1.4	FIELD QA/QC PROGRAM	3
SECTION 2		
2.1	MEASUREMENT OF STATIC WATER LEVEL ELEVATION	4
2.2	DETECTION OF IMMISCIBLE LAYERS	4
2.3	WELL EVACUATION	4
2.4	COLLECTION	6
2.5	IN-SITU OR FIELD ANALYSES	7
2.6	SAMPLING EQUIPMENT DECONTAMINATION PROCEDURES	8
SECTION 3		
3.1	SAMPLE CONTAINERS	10
3.1.1	sample Preservation	10
3.1.2	Special Handling Considerations	11
3.2	CHAIN-OF-CUSTODY PROGRAM	12
3.2.1	sample Labels	12
3.2.2	sample Seal	12
3.2.3	Field Logbook	13
3.2.4	chain-of-custody Record	13
3.2.5	sample Analysis Request Sheet	13
3.3	FIELD QA/QC PROGRAM	14

Nominal Well Diameter (in inches)	Approximate Gallons Per Foot
2	0.164
3	0.367
4	0.653
6	1.468
8	2.610
10	4.078
12	5.872

Static Water Level Elevation - The depth to standing water and total depth of the well should be taken in order to calculate the volume of water in the well, to enable groundwater flow directions to be calculated and to provide an integrity check of the well. Measurements should be collected from a standard surveyed reference point and should be made to the nearest tenth of a foot. A variety of manufacturers produce quality well measurement instruments.

Immiscible Layers - If an immiscible layer is suspected the layer should be measured by procedures detailed in Section 2.2 and removed prior to well evacuation.

Well Evacuation - A minimum of three well volumes should be removed prior to sampling. Well volumes may be conveniently calculated by use of the following table:

### 1.1 SAMPLE COLLECTION AND HANDLING PROCEDURES

A summary of sampling procedures for quick reference is outlined below. Detailed procedures and guidelines for the four categories are presented in the following sections.

- o Sample collection
- o Handling Procedures
- o Chain-of-custody Program
- o Field quality assurance/quality control program

The following presents the Lilyblad Petroleum, Inc. Groundwater Sampling and Analysis (S&A) Plan. The plan includes procedures and guidelines for sampling the four on-site wells and one off-site well at the Lilyblad facility. Sampling procedures are provided for the following four categories:

### INTRODUCTION

#### SECTION 1

- Samples requiring organic analysis should not be filtered
- Samples should not be transferred from one container to another
- No headspace should exist in containers that are to be analyzed for volatile organics

Sample Preservation - Samples should be preserved based on the specific parameters to be analyzed. Table 3-1 presents the type of preservative recommended for each specific parameter. In addition samples should be refrigerated (4° Celsius) and protected from light following collection. Samples should be analyzed in accordance with holding time specified in Table 3-1. Other general sampling procedures include:

Sample Containers - Sample containers should be selected based on the specific parameters to be analyzed and the detection limits required. Table 3-1 presents the type of container recommended for each specific parameter. Containers should be thoroughly cleaned based on the analyte of interest.

SAMPLE HANDLING PROCEDURES

Decontamination Procedures - Sample equipment should be dedicated to an individual well or decontaminated between wells following procedures in Section 2.6.

Sample Collection - Samples should be collected using dedicated gas-operated fluorocarbon resin (teflon) bladder pumps or teflon/stainless steel bailers with dedicated ropes. Sampling should be conducted starting at the least contaminated well (usually upgradient) and proceeding to more contaminated wells.

Chemical stabilization parameters (conductivity and pH) should be measured during evacuation. Low-yield wells (wells incapable of yielding three case volumes) should be evacuated to dryness and sampled following sufficient recovery. Sample collection should not begin until either the appropriate volumes of water has been purged/evacuated or the well has been evacuated to dryness and allowed to recover and the pH and conductivity measurements have stabilized.

1.3 CHAIN-OF-CUSTODY PROGRAM

A program should be initiated that includes the following methodology for documenting the possession and handling of individual samples

- Sample labels should be affixed to each container identifying the sample and analysis

- Sample seals should be affixed to shipping containers or individual bottles to insure that samples are not disturbed during transportation

- A field logbook should be used for documenting all activity conducted during the sampling program

- A chain-of-custody form that includes the requested sample analysis should accompany every shipping container and document every sample

1.4 FIELD QA/QC PROGRAM

o The following field samples should be prepared and analyzed during all sampling programs:

- Trip blank containing Type II reagent grade water

- Equipment blank containing Type II reagent grade water that has been passed through the sampling device

- Duplicate samples should be collected at one per day or ten percent of the total number of samples collected per day

1. Remove the locking and protective caps.
2. Sample the air in the well head for organic vapors using either a photionization analyzer or an organic vapor analyzer, and record measurements in a field log book.
3. Determine the static liquid level using a manometer and record the depth.

The following procedures which should be incorporated for detecting the presence of light (floaters) and/or dense (sinkers) phase immiscible organic layers. These procedures should be undertaken if immiscible organic layers are suspected, before the well is evacuated for conventional sampling:

### 2.2 DETECTION OF IMMISCIBLE LAYERS

Field measurements should include depth to standing water and total depth of the well to the bottom of the intake screen structure. This information is required to calculate the volume of stagnant water in the well and provide a check on the integrity of the well (e.g., identify siltation problems). The measurements should be taken to 0.01 foot. Each well should have a permanent, easily identified reference point from which its water level measurement is taken. The references points should be established in relation to an established National Geodetic Vertical Datum (NGVD). The device used to detect the water level surface must be sufficiently sensitive so that a measurement to  $\pm 0.01$  foot can be obtained reliably. A steel tape will usually suffice; however, it is recommended that an electronic device be used to measure depth to the surface of the groundwater or light phase immiscibles.

Static water elevations should be measured in each well prior to each sampling event. Collection of water elevation on a continuing basis is important to determine if horizontal and vertical flow gradients have changed since initial site characterization. A change in hydrologic conditions may necessitate a modification of the design of the groundwater monitoring system.

### 2.1 MEASUREMENT OF STATIC WATER LEVEL ELEVATION

#### SAMPLE COLLECTION

#### SECTION 2

4. Lower an interface probe into the well to determine the existence of any immiscible layer(s), light and/or dense.

The air above the well head should be monitored in order to determine the potential for fire, explosion, and/or toxic effects on workers. This test also serves as a first indication of the presence of light phase immiscible organics. A manometer or acoustic sounder (for very shallow wells) will provide an accurate reading of the depth to the surface of the liquid in the well, but neither are capable of differentiating between the potentiometric surface, and the surface of an immiscible layer. Nonetheless, it is very useful to determine that surface depth first to guide the lowering of the interface probe. The interface probe serves two related purposes. First, as it is lowered into the well, the probe registers when it is exposed to an organic liquid and thus identifies the presence of immiscible layers. Careful recording of the depths of the air/floater and floater/water interfaces establishes a measurement of the thickness of the light phase immiscible layer, the probe indicates the depth to the water level. The presence of floaters precludes the exclusive use of sounders to make a determination of static water level. Dense phase immiscible layers are detected by lowering the device to the bottom of the well where, again, the interface probe registers the presence/absence of organic liquids.

The immiscible phase must be collected prior to any purging activities. If the thickness of this phase is 2 feet or greater, a bottom valve bailer is the equipment of choice.

When the thickness of the floating layer is less than 2 feet, but the depth to the surface of the floating layer is less than 25 feet, a peristaltic pump can be used to "vacuum" a sample.

When the thickness of the floating layer is less than 2 feet and the depth to the surface of the floating layer is beyond the effective "reach" of a peristaltic pump (greater than 25 feet), a bailer must be modified to allow filling only from the top.

The best method for collecting dense phase immiscibles is to use a double check valve bailer. The key to sample collection is controlled, slow lowering (and raising) of the bailer to the bottom of the well. The dense phase must be collected prior to any purging activities.

2.3 WELL EVACUATION

The water standing in a well prior to sampling may not be representative of in-situ groundwater quality. Therefore, the standing water in the well and filter pack should be removed so that formation water can replace the stagnant water. Water should be drawn down from above the screen in the uppermost part of the water column in high yield formations to ensure that fresh water from the formation will move upward in the screen. Water should be removed from the bottom of the screened interval in low-yield formations.

The procedure used for well evacuation depends on the hydraulic yield characteristics of the well. When evacuating low-yield wells (wells that are incapable of yielding three casing volumes), the owner/operator should evacuate wells to dryness once. As soon as the well recovers sufficiently, the first sample should be tested for pH, temperature, and specific conductance. The well should be retested for pH, temperature, and specific conductance during evacuation and after sampling as a measure of purging efficiency and as a check on the stability of the water samples over time. Whenever full recovery to static level exceeds two hours, the sample should be extracted as soon as sufficient volume is available for a sample for each parameter. A well should not be pumped to dryness if the recharge rate causes the formation water to vigorously cascade down the sides of the screen which could cause an accelerated loss of volatiles. For higher yielding wells, the three casing volumes should be evacuated prior to sampling.

In order to minimize the introduction of contamination into the well, positive-gas displacement, fluorocarbon resin bladder pumps are recommended for purging wells. Fluoro-carbon resin or stainless steel bailers are also recommended for purging equipment. Where these devices cannot be used, peristaltic pumps, gas-lift pumps, centrifugal pumps, and venturi pumps may be used. Some of these pumps cause volatilization and produce high pressure differentials, which result in variability in the analysis of pH, specific conductance, metals, and volatile organic samples. They are, however, acceptable for purging the wells if sufficient time is allowed to let the water stabilize prior to sampling.

When purging equipment must be reused for subsequent wells, it should be decontaminated, following the same procedures required for the sampling equipment.

2.4 COLLECTION

To ensure the groundwater sample is representative of the formation, it is important to minimize physically altering or chemically contaminating the sample during the withdrawal process.

When collecting samples where volatile constituents or gases are of interest, using a positive gas displacement bladder pump, pumping rates should not exceed 100 milliliters/minute. Higher rates can increase the loss of volatile constituents and can cause fluctuation in pH and pH-sensitive analytes. Once the portions of the sample reserved for the analysis of volatile components have been collected, higher pumping rates may be used particularly if a large sample volume must be collected. The sampling flow rate should not exceed the flow rate used while purging.

Samples should be collected and containerized in the order of the parameter volatilization sensitivity. A preferred collection order for some common groundwater parameters follows:

- o Volatile organics (VOA)
- o Purgable organic carbon (POC)
- o Purgable organic halogens (POX)
- o Total organic halogens (TOX)
- o Total organic carbon (TOC)
- o Extractable organics
- o Total metals
- o Dissolved metals
- o Phenols
- o Cyanide
- o Sulfate and chloride
- o Turbidity
- o Nitrate and ammonia
- o Radionuclides

Temperature, pH, and specific conductance measurements should be made in the field before and after sample collection as a check on the stability of the water sampled over time.

Sampling equipment and procedures that minimize agitation and reduce/eliminate contact with the atmosphere during sample transfer must be used. Sampling equipment should be constructed of inert materials. When used properly, the following are acceptable sampling devices for all parameters:



Several constituents of the parameters being evaluated are physically or chemically unstable and must be tested either in the borehole using a probe (in-situ) or immediately after collection using a field test kit. Examples of unstable elements or properties include pH, redox potential, chlorine, dissolved oxygen, and temperature. Although

2.5 IN-SITU OR FIELD ANALYSES

- o Clean sampling equipment should not be placed directly on the ground or other contaminated surfaces prior to insertion into the well.
- o The contents should be transferred to a sample container in a way that will minimize agitation and aeration.
- o Sampling equipment (e.g., especially bailers) should never be dropped into the well, because this will cause degassing of the water upon impact.
- o Check valves should be designed and inspected to assure that fouling problems do not reduce delivery capabilities or result in aeration of the sample.
- o Positive gas displacement bladder pumps should be operated in a continuous manner so that they do not produce pulsating samples that are aerated in the return tube or upon discharge.
- o Sampling should first be conducted at background wells and then proceeding to downgrading wells.
- o Several criteria should be incorporated in the field to ensure proper sample collection.
- o Sampling equipment should be constructed of inert material.
- o Single check valve fluorocarbon resin or stainless steel bailer.
- o Syringe bailer (stainless steel or fluorocarbon resin); and
- o Bottom emptying device!
- o Bailer (fluorocarbon resin or stainless steel), provided it is equipped with double check valves and
- o Gas-operated, fluorocarbon resin or stainless steel squeeze pump (also referred to as a bladder pump with adjustable flow control);

specific conductivity (analogous to electrical resistance of a substance) is relatively stable, it is recommended that this characteristic be determined in the field. Most conductivity instruments require temperature compensation; therefore, the temperature of the samples should be measured at the time conductivity is determined. Conductivity and pH should be monitored during well evacuation to ensure chemical stabilization of the water has occurred prior to sampling.

Calibration of any in-situ monitoring equipment or field-test probes and kits should be completed at the beginning of each use, according to the manufacturers' specifications and consistent with Test Methods for Evaluating Solid Waste - Physical/Chemical Methods (SW-846), 2nd Edition, 1982.

## 2.6 SAMPLING EQUIPMENT DECONTAMINATION PROCEDURES

When dedicated equipment is not used for sampling (or well evacuation), disassembly and cleaning of equipment must be complete before each use. If the constituents of interest are inorganic, the equipment should be cleaned with a nonphosphate detergent/soap mixture. The first rinse should be a dilute (0.1 N) hydrochloric acid or nitric acid, followed by a rinse of tap water and finally Type II reagent grade water. Dilute hydrochloric acid is generally preferred to nitric acid when cleaning stainless steel because nitric acid may oxidize the stainless steel.

When organics are the constituents of concern, the equipment should be washed with a nonphosphate detergent and rinsed with tap water, distilled water, acetone, and pesticide-quality hexane, in that order. The sampling equipment should be thoroughly dried before use to ensure that the residual cleaning agents (e.g., HCl) are not carried over to the sample.

Similarly, an EPA-approved procedure is available for cleaning containers used to store samples for organics analysts. The sampling container should be emptied of any residual materials, followed by a washing with a nonphosphate detergent in hot water. It should then be rinsed with tap water, distilled water, acetone, and finally with pesticide-quality hexane. Dirty or contaminated glassware does not form a very thin sheet of water on its surface and may require treatment with chromic acid and/or baking in a muffle furnace at 400 degrees centigrade for 15 to 30 minutes to ensure that the glass is clean. Chromic acid may be useful to remove organic deposits from glassware; however, the analyst should be cautioned that the glassware must be thoroughly rinsed with water to remove the last traces of chromium. The use of chromic acid can cause a contamination problem and must be avoided if chromium is an analyte of interest.

Containers should be cleaned based on the analyte of interest. When samples are to be analyzed for metals, the sample containers as well as the laboratory glassware should be thoroughly washed with nonphosphate detergent and tap water, and rinsed with (1.1) nitric acid, tap water, (1.1) hydrochloric acid, tap water, and finally Type II water, in that order.

When metals are the analytes of interest, fluorocarbon resin or polyethylene containers with polypropylene caps should be used. When organics are the analytes of interest, glass bottles with fluorocarbon resin-lined caps should be used. Table 2-1 presents specific parameters and recommended types of sample containers.

Samples should be transferred in the field from the sampling equipment directly into the container that has been specifically prepared for that analysis or set of compatible parameters. It is not an acceptable practice for samples to be composited in a common container in the field and then split in the laboratory, or poured first into a wide mouth container and then transferred into smaller containers. Test methods for evaluating solid waste-physical/chemical Methods (SW-846) specify that sample containers should be used for each constituent or common set of parameters.

### 3.1 SAMPLE CONTAINERS

## SAMPLE HANDLING PROCEDURES

### SECTION 3

Glassware should be sealed and stored in a clean environment immediately after drying or cooling to prevent any accumulation of dust or other contaminants. It should be stored, capped with aluminum foil and inverted.

3.1.1 Sample Preservation

Many of the chemical constituents and physiochemical parameters that are to be measured or evaluated in groundwater monitoring programs are not chemically stable, and therefore sample preservation is required. (SW-846) includes a discussion by analyte of the appropriate sample preservation procedures.

Preservation methods are generally limited to pH, control, chemical addition, refrigeration, and protection from light. Specific preservation methods presented in SW-846 should be used for the constituent in the sample. A summary list of appropriate sample container types and sample preservation measures is presented in Table 3-1.

3.1.2 Special Handling Considerations

Samples requiring analysis for organics should not be filtered. Samples should not be transferred from one container to another, because losses of organic material onto the walls of the container or aeration may occur. Total organic halogens (TOX) and total organic carbon (TOC) samples should be handled and analyzed as materials containing volatile organics. No headspace should exist in the sample containers to minimize the possibility of volatilization of organics.

Metallic ions that migrate through the unsaturated (vadose) and saturated zones and arrive at a groundwater monitoring well may be present in the well. Particles (e.g., silt, clay), which may be present in the well even after well evacuation procedures, may absorb or absorb various ionic species to effectively lower the dissolved metal content in the well water. Groundwater samples on which metals analysis will be conducted should be split into two portions. One portion should be filtered through a 0.45-micron membrane filter, transferred to a bottle, preserved with nitric acid to a pH less than 2 (Table 4-1), and analyzed for dissolved metals. The remaining portion should be transferred to a bottle, preserved with nitric acid, and analyzed for total metals. Any difference in concentration between the total and dissolved fractions may be attributed to the original metallic ion content of the particles and any portion of ions to the particles.

An adequate chain-of-custody program will allow for the tracing of possession and handling of individual samples from the time of field collection through laboratory analysis. A chain-of-custody program should include:

- o Sample labels, which prevent misidentification of samples;
- o Sample seals to preserve the integrity of the sample from the time it is collected until it is opened in the laboratory;
- o Field logbook to record information about each sample collection during the groundwater monitoring program;
- o Chain-of-custody record to establish the documentation program;
- o Sample analysis request sheets, which serve as official communication to the laboratory of the particular analysis(es) required for each sample and provide further evidence that the chain of custody is complete. This sheet may be incorporated onto the chain-of-custody form.

3.2 CHAIN-OF-CUSTODY PROGRAM

3.2.1 Sample Labels

To prevent misidentification of samples, affix legible labels to each sample container. An indelible ink pen should be used when completing sample labels. The labels should be sufficiently durable to remain legible even when wet and should contain the following types of information:

- o Sample identification number
- o Name of collector
- o Date and time of collection
- o Place and collection
- o Parameter(s) requested (if space permits)
- o Internal temperature of shipping container at time sample was placed
- o Internal temperature of shipping container upon opening at laboratory

- o Sample number
- o Signature of collector
- o Date and time of collection
- o Sample type (e.g., ground water, immiscible layer)
- o Identification of well
- o Number of containers
- o Parameters requested for analysis

To establish the documentation necessary to trace sample possession from time of collection, a chain-of-custody record should be filled out and should accompany every sample. The record should contain the following types of information:

### 3.2.4 Chain-of-custody Record

- o Identification of well
- o Well depth
- o Static water level depth and measurement technique
- o Well yield - high or low
- o Purge volume and pumping rate
- o Time well purged
- o Collection method for immiscible layers and sample identification numbers
- o Preservative(s) used
- o Parameters requested for analysis
- o Field analysis data and method(s)
- o Sample distribution and transporter
- o Field observations on sampling event
- o Name of collector
- o Climatic conditions including air temperature
- o Internal temperature of field and shipping (refrigerated) containers

The individual designated to perform groundwater monitoring operations should keep an up-to-date field logbook that documents the following:

### 3.2.3 Field Logbook

In cases where samples may leave the sampler's immediate control, such as shipment to a laboratory by a common carrier (e.g., air freight), a seal should be provided on the shipping container or individual sample bottles to ensure that the samples have not been disturbed during transportation.

### 3.2.2 Sample Seal

Equipment Blank - To ensure the nondedicated sampling device has been effectively cleaned (in the laboratory or field), fill the device with Type II reagent grade water through the device, transfer to sample bottle(s), and return to the laboratory for analysis. A minimum of one equipment blank for each day that groundwater monitoring wells are sampled is recommended.

Trip Blank - Fill one of each type of sample bottle with Type II reagent grade water, transport to the site, handle like a sample, and return to the laboratory for analysis. One trip blank per sampling sent is recommended.

During each sampling episode two types of GC blanks should be collected and analyzed to ensure the reliability and validity of the field and laboratory data. The two types of GC blanks are: trip blanks and equipment blanks. A trip blank should be subjected to the same analysis as the groundwater. Any contaminants found in the trip blanks could be attributed to (1) interaction between the sample and the container, (2) contaminated rinse water, or (3) a handling procedure that alters the sample analysis results. The following field blanks should be prepared and analyzed for all of the required monitoring parameters:

3.3 FIELD QA/QC PROGRAM

- o Name of person receiving the sample
- o Laboratory sample number (if different from field number)
- o Date of sample receipt
- o Analyses to be performed
- o Internal temperature of shipping (refrigerated) container upon opening in the laboratory

This document should accompany the sample(s) on delivery to the laboratory and clearly identify which sample containers have been designated (e.g., use of preservatives) for each requested parameter. This document is commonly incorporated into the chain-of-custody form. The record should include the following types of information:

3.2.5 Sample Analysis Request Sheet

- o Signature of person(s) involved in the chain of possession
- o Inclusive dates of possession
- o Internal temperature of shipping (refrigerated) container (chest) when samples were sealed into the shipping container
- o Internal temperatures of shipping (refrigerated) container upon opening in the laboratory

Duplicate Sample(s). A duplicate set of samples should be collected one per day or 10 percent of the total number of samples collected whichever is greater. If both solid and liquid samples are taken, a set of duplicate samples should be taken from each media. If at all possible, duplicate samples should be taken at sampling points where contamination is expected such as downgradient wells. These samples should be labeled so as to be indistinguishable from the initial samples and submitted to the laboratory as blind duplicates.

The results of the analysis of the blanks should not be used to correct the groundwater data. If contaminants are found in the blanks, the source of the contamination should be identified and corrective action, including resampling, should be initiated.



TABLE 3 - 1

EPA Regulated Containers, Preservation Techniques, and Holding Times

Measurement Table/Parameter	Container 1	Preservative 2, 3	Maximum Holding Time 4
<b>IA</b>	<b>Bacterial Tests</b>		
1-4. Coliform, fecal and total	P, G	Cool, 4°C 0.0008 Na <sub>2</sub> S <sub>2</sub> O <sub>3</sub>	6 hours
5. Fecal streptococci	P, G	Cool, 4°C 0.0008 Na <sub>2</sub> S <sub>2</sub> O <sub>3</sub>	6 hours
<b>IB</b>	<b>Inorganic Tests</b>		
1. Acidity	P, G	Cool, 4°C	14 days
2. Alkalinity	P, G	Cool, 4°C	14 days
4. Ammonia	P, G	Cool, 4°C H <sub>2</sub> SO <sub>4</sub> to pH < 2	28 days
9. Biochemical oxygen demand	P, G	Cool, 4°C	48 hours
10. Biochemical oxygen demand, carbonaceous	P, G	Cool, 4°C	48 hours
12. Bromide	P, G	None required	20 days
15. Chemical oxygen demand	P, G	Cool, 4°C H <sub>2</sub> SO <sub>4</sub> to pH < 2	28 days

EPA Required Containers, Preservation Techniques, and Holding Times

Measurement Table/Parameter	Container	Preservative	Holding Time	Maximum
<u>Inorganic Tests</u>				
16. Chloride	P,G	None required	20 days	Analyze immediately
17. Chlorine, total residual	P,G	None required	20 days	Analyze immediately
21. Color	P,G	Cool, 4°C	40 hours	Analyze immediately
23-24. Cyanide, total and amenable to chlorination	P,G	Cool, 4°C NaOH to pH > 12 0.6g ascorbic acid	14 days	Analyze immediately
25. Fluoride	P	None required	20 days	Analyze immediately
27. Hardness	P,G	None required	6 months	Analyze immediately
28. Hydrogen Ion (pH)	P,G	None required	20 days	Analyze immediately
31, 33. Kjeldahl and organic Nitrogen	P,G	Cool, 4°C H <sub>2</sub> SO <sub>4</sub> to pH < 2	20 days	Analyze immediately
<u>Metals</u>				
38. Chromium VI	P,G	Cool, 4°C	24 hours	Analyze immediately
35. Mercury	P,G	None required	28 days	Analyze immediately

RPA Required Containers, Preservation Techniques, and Holding Times

Measurement Table/Parameter	Container 1	Preservative 2,3	Maximum Holding Time 4
ID 3, 5-8, 11, Metals, 13, 14, 19, except above (Cont) 20, 22, 26 29, 30, 32-34, 36, 37, 45, 47, 51, 52, 50, 59, 60, 62, 63, 70-72, 74, 75.	P,G	MIN <sub>3</sub> to pH < 2	6 Months
30. Nitrate	P,G	Cool, 4°C	40 hours
39. Nitrate-nitrite	P,G	Cool, 4°C H <sub>2</sub> SO <sub>4</sub> to pH < 2	28 days
40. Nitrite	P,G	Cool, 4°C	40 hours
41. Oil and grease	G	Cool, 4°C H <sub>2</sub> SO <sub>4</sub> to pH < 2	20 days
42. Organic carbon	P,G	Cool, 4°C HCl or H <sub>2</sub> SO <sub>4</sub> to pH < 2	28 days
44. Orthophosphate	P,G	Filter Immediately Cool, 4°C	48 hours

EPA Required Containers, Preservation Techniques, and Holding Times

Measurement Table/Parameter	Container <sup>1</sup>	Preservative <sup>2,3</sup>	Maximum Holding Time <sup>4</sup>
<u>ID</u>			
(Con't)			
46. Oxygen, Dissolved Probe	G bottle and top	None required	Analyze Immediately
Winkler	G bottle and top	Fix on site and store in dark	0 hours
48. Phenols	G only	Cool, 4°C H <sub>2</sub> SO <sub>4</sub> to pH < 2	28 days
49. Phosphorus (elemental)	G	Cool, 4°C	40 hours
50. Phosphorus, total	P,G	Cool, 4°C H <sub>2</sub> SO <sub>4</sub> to pH < 2	20 days
53. Residue, total	P,G	Cool, 4°C	7 days
54. Residue, filterable	P,G	Cool, 4°C	7 days
55. Residue, Non-filterable (TSS)	P,G	Cool, 4°C	7 days
56. Residue, settleable	P,G	Cool, 4°C	40 hours
57. Residue, volatile	P,G	Cool, 4°C	7 days

## RPA Required Containers, Preservation Techniques, and Holding Times

Measurement Table/Parameter	Container 1	Preservative 2,3	Maximum Holding Time 4
61. $\frac{10}{\text{ID}}$ Silica (Con't)	P	Cool, 4°C	20 days
64. Specific conductance	P,G	Cool, 4°C	20 days
65. Sulfate	P,G	Cool, 4°C	20 days
66. Sulfide	P,G	Cool, 4°C, add zinc acetate plus sodium hydroxide to pH > 9	7 days
67. Sulfite	P,G	None required	Analyze Immediately
68. Surfactants	P,G	Cool, 4°C	48 hours
69. Temperature	P,G	None required	Analyze Immediately
73. Turbidity	P,G	Cool, 4°C	48 hours

EPA Required Containers, Preservation Techniques, and Holding Times

Measurement Table/Parameter	Container <sup>1</sup>	Preservative <sup>2,3</sup>	Maximum Holding Time <sup>4</sup>
<u>Organic Tests</u>			
<u>IC</u>			
13,			
19, 20, 21, 23, furgeable	G, Teflon-	Cool, 4°C	14 days
25, 26, 27, 28, halocarbons	lined septum	0.0008 Na <sub>2</sub> S <sub>2</sub> O <sub>3</sub>	
29, 35, 36, 37,			
38, 40, 41, 42,			
43, 44, 46, 47,			
48, 57, 67, 68,			
69, 92, 93, 94,			
95, 97,			
6, 50, 90	Purgeable aromatic	Cool, 4°C	14 days
		0.0008 Na <sub>2</sub> S <sub>2</sub> O <sub>3</sub>	
		HCl to pH < 2 <sup>9</sup>	
3,4. Acrolein and acrylonitrile	G, Teflon-lined septum	Cool, 4°C	14 days
		0.0008 Na <sub>2</sub> S <sub>2</sub> O <sub>3</sub>	
		Adjust pH to 4-5 <sup>10</sup>	
24, 31, 45, 50, Phenols <sup>11</sup>	G, Teflon-lined cap	Cool, 4°C	7 days until extraction, 40 days after extraction
54, 60, 71, 72,		0.0008 Na <sub>2</sub> S <sub>2</sub> O <sub>3</sub>	
83, 85, 96.			

**RPA Required Containers, Preservation Techniques, and Holding Times**

Measurement Table/Parameter	Container	Preservation	Holding Time
IC (Cont) 7, 39. Benzidine <sup>11</sup>	G, Teflon-lined cap	Cool, 4°C 0.000M Na <sub>2</sub> SO <sub>3</sub> pH 2-7	7 days until extraction <sup>11</sup>
14, 18, 49, 51, Phthalate esters <sup>11</sup> 52, 53.	G, Teflon-lined cap	Cool, 4°C	7 days until extraction 7 days after ex.
73, 74, 75 Microamines <sup>11, 14</sup>	G, Teflon-lined cap	Cool, 4°C store in dark 0.000M Na <sub>2</sub> SO <sub>3</sub>	7 days " " " "
76, 77, 78, 79, PCBs <sup>11</sup> 80, 81, 82	G, Teflon-lined cap	Cool 4°C	7 days " " " "
55, 56, 66, 70 Ultraaromatics and Isophorone <sup>11</sup>	G, Teflon-lined cap	Cool, 4°C	7 days " " " "
1, 2, 5, 8, 9, Polynuclear Aromatic 10, 11, 12, 33, hydrocarbons <sup>11</sup> 34, 59, 60, 65, 69, 84, 86	G, Teflon-lined cap	Cool, 4°C 0.000M Na <sub>2</sub> SO <sub>3</sub> store in dark	7 days " " " "
15, 16, 17, 22, Haloethers <sup>11</sup> 32	G, Teflon-lined cap	Cool, 4°C 0.000M Na <sub>2</sub> SO <sub>3</sub>	7 days " " " "

**EPA Required Containers, Preservation Techniques, and Holding Times**

Measurement Table/Parameter	Container	Preservative	Holding Time
<u>IC</u> (Con't)	D, Teflon- cap	Cool, 4°C	7 days until extraction, 40 days after extraction
			30, 36, 37, 38, Chlorinated 61, 62, 63, 64 Hydrocarbons 91
			07 TCDD II
<u>ID</u>	G, Teflon- cap	Cool, 4°C 0.000N Na <sub>2</sub> SO <sub>3</sub>	7 days " " "
			<u>Pesticides Tests</u>
<u>IS</u>	G, Teflon- lined cap	Cool, 4°C pH 5-9	7 days " " "
			<u>Pesticides II</u>
1-5. Alpha, beta and radium	P, G	HNO <sub>3</sub> to pH < 2	6 months
			<u>Radiological Tests</u>



1. Polyethylene (P) or Glass (G).
2. Sample preservation should be performed immediately upon sample collection. For composite samples, each aliquot should be preserved at the time of collection: when use of an automated sampler makes it impossible to preserve each aliquot, then samples may be preserved by maintaining at 4°C until compositing and sample splitting is completed.
3. When any sample is to be shipped by common carrier or sent through the United States Mails, it must comply with the Department of Transportation Hazardous Materials Regulations (49 CFR Part 172). The person offering such material for transportation is responsible for ensuring such compliance. For the preservation requirements of Table F-1, the Office of Hazardous Materials, Materials Transportation Bureau, Department of Transportation has determined that the Hazardous Materials Regulations do not apply to the following materials: Hydrochloric acid (HCL) in water solutions at concentrations of 0.04% by weight or less (pH about 1.96 or greater); Nitric acid (HNO<sub>3</sub>) in water solutions at concentrations of 0.15% by weight or less (pH about 1.62 or greater); Sulfuric acid (H<sub>2</sub>SO<sub>4</sub>) in water solutions at concentrations of 0.35% by weight or less (pH about 1.15 or greater); and Sodium hydroxide (NaOH) in weight or less (pH about 12.30 or less).

Notes

or GC/MS for specific compounds.

8. Guidance applies to samples to be analyzed by GC, LC,

adding preservative for dissolved metals.

7. Samples should be filtered immediately on-site before

pH 12.

spot test is obtained. The sample is filtered and then NaOH is added to

can be removed by the addition of cadmium nitrate powder until a negative

in order to determine if sulfide is present. If sulfide is present, it

all samples may be tested with lead acetate paper before the pH adjustment

6. Maximum holding time is 24 hours when sulfide is present. Optionally,

chlorine.

5. Should only be used in the presence of residual

maintain sample stability. See § 136.3(e) for details.

time if knowledge exists to show this is necessary to

laboratory, is obligated to hold the sample for a shorter

period given in the table. A permittee, or monitoring

Some samples may not be stable for the maximum time

and has received a variance from the Regional Administrator.

of samples under study are stable for the longer time,

copy, has data on file to show that the specific types

periods only if the permittee, or monitoring labora-

considered valid. Samples may be held for longer

that samples may be held before analysis and still

collection. The times listed are the maximum times

4. Samples should be analyzed as soon as possible after

atmosphere.

If storage is conducted under an inert (oxidant-free) atmosphere, extracts may be stored up to 7 days before analysis.

13.

rearrangement to benzidine.

adjust the pH of the sample to  $4.0 \pm 0.2$  to prevent

the 1,2-diphenylhydrazine is likely to be present,

12.

analysis of benzidine).

reduction of residual chlorite, and footnotes 13, 14 (in the

are noted in footnote 6 (in the requirement for chlorite)

exceptions to this optional preservation and holding time procedure

seven days before extraction and for forty days after extraction.

the pH to 6-9; samples preserved in this manner may be held for

with 0.005% sodium chlorite, sorting in the dark, and adjusting

the sample may be preserved by cooling to 4°C, reducing residual chlorite

when the analyses of concern fall within two or more chemical categories,

times should be observed for optimum safeguard of sample integrity.

chemical category, the specified preservative and maximum holding

When the extractable analyses of concern fall within a single

11.

adjustment must be analyzed within 3 days of sampling.

be measured. Samples for acetoin receiving no pH

10. The pH adjustment is not required if acetoin will not

within seven days of sampling.

9. Sample receiving no pH adjustment must be analyzed

16. For the analysis of diphenylpicramide, add 0.0083  $\text{Na}_2\text{S}_2\text{O}_3$  and adjust pH to 7-10 with NaOH within 24 hours of sampling.
15. The pH adjustment may be performed upon receipt at the laboratory and may be omitted if the samples are extracted within 2 hours of collection. For the analysis of aldrin, add 0.0083  $\text{Na}_2\text{S}_2\text{O}_3$ .