

International Paper Facility, Longview

Maintenance Facility Area Remedial Investigation and Feasibility Study

Responsiveness Summary

Department of Ecology's response to comments received from stakeholders and the public

Revised July 2018 Publication 18-04-014

Publication and Contact Information

This report is available on the Department of Ecology's <u>International Paper Longview cleanup</u> website.¹

For more information contact: Hazardous Waste and Toxics Reduction Program P.O. Box 47600

Olympia, WA 98504-7600 Phone: (360) 407-6700

Website: www.ecology.wa.gov

Department of Ecology's Regional Offices

Map of Counties Served



Southwest Region | Central Region | Eastern Region

Region	Counties served	Mailing Address	Phone
Southwest	Clallam, Clark, Cowlitz, Grays Harbor, Jefferson, Mason, Lewis, Pacific, Pierce, Skamania, Thurston, Wahkiakum	PO Box 47775 Olympia, WA 98504	360-407-6300
Northwest	Island, King, Kitsap, San Juan, Skagit, Snohomish, Whatcom	3190 160th Ave SE Bellevue, WA 98008	425-649-7000
Central	Benton, Chelan, Douglas, Kittitas, Klickitat, Okanogan, Yakima	1250 W Alder St Union Gap, WA 98903	509-575-2490
Eastern	Adams, Asotin, Columbia, Ferry, Franklin, Garfield, Grant, Lincoln, Pend Oreille, Spokane, Stevens, Walla Walla, Whitman	4601 N Monroe Spokane, WA 99205	509-329-3400

Accommodation Requests:

To request ADA accommodation including materials in a format for the visually impaired, call Ecology at 360-407-6700 or visit https://ecology.wa.gov/accessibility. People with impaired hearing may call Washington Relay Service at 711. People with speech disability may call TTY at 877-833-6341.

¹ https://fortress.wa.gov/ecy/gsp/Sitepage.aspx?csid=3685



International Paper Facility, Longview

Maintenance Facility Area Remedial Investigation and Feasibility Study Report

Responsiveness Summary

Department of Ecology's response to comments received from stakeholders and the public

Prepared by Bridgette Valdez-Kogle

Hazardous Waste and Toxics Reduction Program Washington State Department of Ecology Lacey, Washington

Table of Contents

Introduction	1
Cleanup process	1
Public outreach and involvement	2
Informing the public about the comment period	2
Public meetings	2
Responses to comments	2
Support for specific remedy	3
Community and economic development	3
Protectiveness and permanence	3
Financial responsibility and cost	4
Long-term monitoring and responsibility	4
Our decisions	5
Conditional approval of the draft RI/FS Report	5
Setting cleanup levels for this site	5
Setting points of compliance for this site	6
Public comments	10
Memorandum: Review of Draft Remedial Investigation/Feasibility Study Report for the Por of Longview Maintenance Facility Area	

Introduction

Ecology held a public comment period from August 17 - October 2, 2017 on draft environmental cleanup documents for the International Paper Company's former facility at 10 International Way in Longview, WA. These documents included a remedial investigation and feasibility report (RI/FS) for the Maintenance Facility Area. The draft RI/FS describes:

- Where potentially harmful chemicals are located.
- How the chemicals may affect people and the environment.
- Different cleanup options.

In addition to draft cleanup documents, we made administrative documents available for public comment. These letters between Ecology, International Paper Company, and the Port of Longview help form how we view this cleanup site.

You can view the final documents and learn more about this site on our <u>International Paper</u>, Longview cleanup website.²

Cleanup process

We use our state's cleanup law, the Model Toxics Control Act (MTCA), to clean up hazardous waste sites. There are many steps in the cleanup process. The first is the remedial investigation (RI) that describes where potentially harmful chemicals are located. It also describes how the chemicals may affect people and the environment. The next step is the feasibility study (FS) that describes cleanup levels, points of compliance, and describes and compares different cleanup options.

The next step is the draft cleanup plan (CAP). This plan will describe which proposed cleanup option Ecology has chosen to clean up the site.

Figure 1. Ecology's basic cleanup process



² https://fortress.wa.gov/ecy/gsp/Sitepage.aspx?csid=3685

Public outreach and involvement

Informing the public about the comment period

We followed our public participation plan for this site, ensuring the public and stakeholders were informed about the public comment period for the draft Remedial Investigation and Feasibility Study (RI/FS).

We posted a public notice of the draft document availability on <u>Ecology's International Paper</u> website,³ <u>public event listing</u>,⁴ and <u>Site Register</u>.⁵ We sent initial public notice to 310 interested parties and 183 <u>email listserv addresses</u>.⁶ Ecology published a legal ad in The Daily News on Aug. 17, 2017.

Public meetings

On Sept. 28, 2017, we hosted an open house and public hearing about this site at the Cowlitz Event Center. Handouts, display boards, and Ecology staff provided more information about the draft documents. We gave a brief presentation followed by a question and answer session. We accepted oral public comments formally during the public hearing.

In addition to our public open house and hearing, we met with several interested parties including environmental staff from United States Environmental Protection Agency Region X, The Cowlitz Indian Tribe, and the Confederated Tribes and Bands of the Yakama Tribe.

These meetings allowed us to engage with others about the challenges we face in solving the problems stemming from historical contamination. We appreciate the thoughtful contributions of the individuals and organizations who commented.

We will continue to keep our website up to date. You can stay informed during formal comment periods by signing up for our mailing list by contacting Bridgette Valdez-Kogle.⁷

Responses to comments

We received 24 comments through email, letter, and oral testimony. This Responsiveness Summary combines comments that either ask the same question or express the same or similar concerns. We believe our responses address the major concerns from the public. We sought to provide a complete and comprehensive response to each concern. However, we realize this approach may not answer detailed individual questions.

³ https://fortress.wa.gov/ecy/gsp/Sitepage.aspx?csid=3685

⁴ https://ecology.wa.gov/Events/Search/Listing

⁵ https://ecology.wa.gov/Regulations-Permits/Guidance-technical-assistance/Site-Register-lists-and-data

⁶ https://ecology.wa.gov/Events/Search/Listing

⁷ bridgette.valdez-kogle@ecy.wa.gov

Support for specific remedy

Many people commented in support of the Port of Longview's preferred alternative; we thank you for your comments. We are not making a decision at this time on how to clean up this site. However, your comments about how to clean up this site will help us make a decision in the next phase – the draft Cleanup Action Plan (CAP). We will make our proposed decision on the cleanup available for public comment during the draft CAP phase of the cleanup.

Community and economic development

Many comments focused on ensuring productive current and future use of this property. We determine whether a cleanup option restores the in a reasonable amount of time. As part of this determination, we consider whether the time required to restore the site will affect current use of the site, potential future use of the site, surrounding areas, and resources.

Recently, the Port of Longview released information on their plans for this site and Berth 4. We are taking their plans and the public comments into consideration for the next phase of the cleanup – the revised disproportionate cost analysis (DCA) and the draft CAP.

Protectiveness and permanence

We heard from the public that they want a cleanup that is as permanent as possible and is protective of human health and the environment. We evaluate and compare the permanence of each cleanup alternative when we select cleanup actions. We give preference to permanent solutions to the maximum extent practicable. This includes how much the cleanup option reduces the toxicity, mobility, or volume of hazardous substances. We consider the following issues when analyzing potential cleanup options:

- How well they destroy the hazardous substance.
- How well they reduce or eliminate releases of hazardous substances.
- How reversible waste treatment process is.
- The amount and type of treatment wastes created.

We also evaluate and compare how well each cleanup option protects human health and the environment. This includes:

- How much existing risks are reduced.
- How much time is required to reduce risk and meet cleanup standards.
- The on-site and off-site risks from implementing the cleanup alternative.
- Overall improvements to environmental quality.

We will analyze protectiveness and permanence under a revised DCA, available for public comment during the next phase, the draft CAP.

Financial responsibility and cost

Many comments focused on who is responsible for paying the cleanup costs. There were also comments about the cost difference between International Paper's preferred cleanup option and the Port of Longview's preferred cleanup option.

Federal and Washington state regulations require the responsible parties performing the cleanup to have the financial ability to clean up the site. The responsible parties are also required to have the financial ability to pay for long-term maintenance and monitoring of contamination left in place. Our financial assurance specialist and the site manager review and approve the amount of money set aside and the financial mechanism (trust funds, insurance, bonds, or other) used to set money aside. This financial responsibility will continue as long as contamination remains above cleanup levels in the Maintenance Facility Area.

We evaluate and compare the cost of each cleanup action alternative presented during the public comment period. This includes the costs of construction, long-term costs, and Ecology's oversight costs. Long-term costs include costs for operating and maintaining a constructed remedy, monitoring, equipment replacement, and maintaining institutional controls. Cost estimates for treatment technologies should include discussions of pretreatment, sample analysis, labor, and waste management.

Ecology has hired a third-party consultant to review cost estimates for all the alternatives presented during the public comment period. The review memo is included as an attachment to this Responsiveness Summary.⁸ This review of cost estimates and Ecology's evaluation will be available in a revised DCA in the draft CAP.

Long-term monitoring and responsibility

Because contaminated soil and groundwater will remain on site after cleanup, International Paper is required to monitor this site for many years. We will conduct periodic reviews of site conditions and monitoring data to ensure human health and the environment continue to be protected. During those reviews, we will consider:

- The effectiveness of the cleanup action.
- New scientific information.
- New regulations for hazardous substances present at the site.
- The availability and practicability of more permanent remedies.
- New analytical methods.

⁸ Memorandum, Review of Public Review Draft Remedial Investigation/Feasibility Study Report for the Port of Longview Maintenance Facility Area in Longview, Washington, from Ridolfi Environmental to Department of Ecology, dated April 13, 2018

Groundwater and soil monitoring reports will be available to the public. Periodic review reports will be available for public review and comment at least every 5 years.

Our decisions

Conditional approval of the draft RI/FS Report

We are conditionally approving the draft Remedial Investigation and Feasibility Report for the Maintenance Facility Area, without the disproportionate cost analysis (DCA). The DCA in the draft RI/FS does not completely describe and evaluate the remedy proposed by the Port of Longview. We have provided an addendum to the report that includes the Port of Longview's proposed alternative and related documents. Ecology will draft a revised DCA with assistance of a contractor. We will present the revised DCA in the draft cleanup action plan (CAP), which outlines Ecology's proposed cleanup plan to address contamination at this site. Other documents for review with the CAP will include documents concerning State Environmental Policy Act (SEPA) review. While we have not made a decision on our preferred cleanup option, your comments during public comment period for the draft RI/FS will help us make our proposed decision. We expect Ecology's draft CAP to go out for public comment in 2019.

Setting cleanup levels for this site

Ecology sets cleanup levels for soil and groundwater to protect people and the environment. For this site, soil must meet Method C industrial cleanup levels to protect groundwater, surface water, and protect current and future workers from dangerous vapors from contamination. This site, like many cleanup sites, will likely have some contamination left on the property. However, the soil cannot be disturbed without consulting with and receiving permission from Ecology.

The draft RI/FS proposed the use of Method C industrial cleanup levels for groundwater within the Maintenance Facility Area. This cleanup level may be used when:

- All practicable methods of treatment are used.
- Method A or B cleanup levels are below area background.
- Meeting Method A or B cleanup levels has the potential to create a significantly greater threat to human health or the environment than attainment of Method C.
- Meeting Method A or B cleanup levels is technically impossible.

The public review draft of the RI/FS does not clearly demonstrate that the responsible parties will use all practicable methods of treatment to clean up the site. This demonstration is necessary for us to allow using Method C cleanup levels for groundwater within the deed-restricted portion of the Maintenance Facility Area. The fact that the site qualifies for Method C cleanup levels for soil does not mean that it also qualifies for Method C cleanup levels for groundwater. We evaluate each medium (soil, groundwater, air) separately using the criteria applicable to that medium.

The draft Cleanup Action Plan for the Maintenance Facility Area will include a revised demonstration for setting cleanup levels.

Setting points of compliance for this site

"Point of compliance" means the point or points on a site where cleanup levels must be met. MTCA allows us to establish less stringent "conditional" points of compliance for groundwater - if certain criteria are met. Responsible parties must demonstrate that it is not possible (due to technological limitations, environmental conditions, or other factors) to meet the cleanup level throughout the site within a reasonable time. Ecology may approve a conditional point of compliance if the point is located as close to the source of contamination as possible. Any contamination left on the site must be contained within a specified area that protects people and animals from exposure to the contaminants.

Ecology has determined that the draft review RI/FS does not adequately demonstrate the support of a conditional point of compliance for groundwater. Where a conditional point of compliance is proposed, the person responsible for the cleanup must demonstrate that all practicable methods of treatment are to be used in the site cleanup. MTCA defines "all practicable methods of treatment" as "all technologies and/or methods currently available and demonstrated to work under similar site circumstances or through pilot studies, and applicable to the site at reasonable cost."

The draft Cleanup Action Plan will include a revised demonstration for establishing a conditional point of compliance for groundwater. This will contain information showing that all practicable methods of treatment will be used to clean up this site.

Table 1. Conditional approval of Public Review Draft Remedial Investigation/Feasibility Study Report, Port of Longview Maintenance Facility Area, Longview, Washington, dated July 12, 2016

Section	Topic	Ecology Decision
Section 1	Introduction	Approved
Section 2	Hydrogeologic Setting	Approved
Section 3	Remedial Investigation Activities	Approved
Section 4	Additional Action Feasibility Study	Approved

Section	Topic	Ecology Decision
Section 5	Exposure Pathways	Approved
Section 6	Cleanup Standards and Remediation Levels	See notes below.
Section 6.1	Preliminary Cleanup Levels	Revised discussion of Method C cleanup levels for groundwater will be in the draft CAP for the MFA.
Section 6.2	Preliminary Remediation Levels	Revised discussion of remediation levels will be in the draft CAP for the MFA.
Section 6.3	Preliminary Points of Compliance	Revised discussion of conditional point of compliance will be in the draft CAP for the MFA.
Section 6.4	Applicable or Relevant and Appropriate Requirements	Approved
Section 7	Development of Cleanup Action Alternatives	See notes below.
Section 7.1	Quantities and Location of Environmental Media Requiring Cleanup	Approved
Section 7.2	Screening of Cleanup Action Alternative Components	Revised screening of cleanup action alternative components will be in the revised DCA and the draft CAP for the MFA.

Section	Торіс	Ecology Decision
Section 7.3	In Situ Soil Remediation Treatability Studies	Approved
Section 7.4	Soil Alternatives	Revised discussion of soil remedial alternatives will be in the revised DCA and the draft CAP for the MFA.
Section 7.5	Groundwater Alternatives	Revised discussion of groundwater remedial alternatives will be in the revised DCA and the draft CAP for the MFA.
Section 8	Analysis of Cleanup Action Alternatives	See notes below.
Section 8.1	Evaluation of Soil Alternatives	Revised evaluation of soil remedial alternatives will be in the revised DCA and the draft CAP for the MFA.
Section 8.2	Evaluation of Groundwater Alternatives	Revised evaluation of groundwater remedial alternatives will be in the revised DCA and the draft CAP for the MFA.
Section 9	Selection of Preferred Cleanup Action Alternatives	Revised selection of preferred cleanup action alternatives will be in the revised DCA and in draft CAP for the MFA.
Section 10	References	Approved

Table 2. Appendices for Conditional approval of Public Review Draft

Section	Topic	Ecology Decision
Appendix A	General Facility Information	Approved
Appendix B	MFA Boring Logs and Monitoring Wells Construction Diagrams/Summary of Soil DRO, cPAH, and Naphthalene Results Figure (1997-2011)	Approved
Appendix C	Previous Investigation Figures	Approved
Appendix D	Biosparging/Bioventing System Design	Approved
Appendix E	MFA Biosparging/Bioventing Performance Monitoring Data	Approved
Appendix F	Groundwater Sampling Logs – 2008/2009	Approved
Appendix G	Laboratory Analytical Reports	Approved
Appendix H	Environmental Visualization System Model Outputs – 2009	Approved
Appendix I	Feasibility Study Cleanup Action Alternative Calculations	Approved
Appendix J	Feasibility Study Cost Estimates	Revised cost estimates for remedial alternatives will be in revised DCA and draft CAP for MFA.

Section	Topic	Ecology Decision
Appendix K	Revised Alternative S5B Cleanup Action Alternative Technical Memorandum	Revised cost estimate for remedial alternative S5B will be in revised DCA and draft CAP for MFA.
Appendix L	Draft Interim Feasibility Study Clarification Deliverables	Revisions to calculations of long- term effectiveness and ranking of groundwater remedial alternatives will in the revised DCA and draft CAP for the MFA.
Appendix M	Alternative S5B Site Grade Cross Sections	Additional cross section for remedial alternative S5B will be in the draft CAP for MFA.

Public comments

You can view the public comments on our <u>International Paper</u>, <u>Longview cleanup website</u>.⁹

Table 3. List of public comments submitted.

Commenter	Representing	Topic
Doug Averett	Self	 Community and economic development. Support for specific remedy Protectiveness Other
Commissioner Dale Boon	Port of Woodland	Support for specific remedy
Cowlitz County		Support for specific remedy

⁹ https://fortress.wa.gov/ecy/gsp/Sitepage.aspx?csid=3685

Commenter	Representing	Topic
Cowlitz County Board of Commissioners		 Community and economic development Financial responsibility Support for specific remedy
Cowlitz Wahkiakum Council of Governments		Support for specific remedy
Sandra Davis	Self	 Financial responsibility Long-term monitoring and responsibility Support for specific remedy Protectiveness Permanence
David Futcher	Self	 Community and economic development Support for specific remedy
Commissioner Joe Gardener	Cowlitz County Board of Commissioners	Support for specific remedy
Mayor Paul Helenberg,	City of Castle Rock	 Community and economic development Financial responsibility Support for specific remedy Public outreach and communications
Mayor Don Jensen	City of Longview	Support for specific remedy
Marvin Kallwick	Self	Support for specific remedyOther

Commenter	Representing	Торіс
Norm Krehbiel	Port of Longview	 Community and economic development Support for specific remedy Current use of site Long-term monitoring and responsibility Cost Permanence Protectiveness Public outreach and communications
Phillip Miller	Self	Financial responsibility
Gerry O'Keefe	Self	Support for specific remedy
Philip Slowiak	International Paper Company	 Community and economic development Support of specific remedy Financial responsibility Current use of site Long-term monitoring and responsibility Protectiveness Cost
Ted Sprague	Cowlitz Economic Development Council	 Community and economic development Support for specific remedy
Sen. Dean Tako	Self	Support for specific remedy
Three Rivers Regional Wastewater Authority	Self	Other

Commenter	Representing	Торіс
Rep. Jim Walsh	Self	 Community and economic development Support for specific remedy
Dennis Weber	Self	Community and economic development
Jeff Wilson	Self	 Community and economic development Support for specific remedy

Memorandum: Review of Draft Remedial Investigation/Feasibility Study Report for the Port of Longview Maintenance Facility Area



MEMORANDUM

DATE: April 13, 2018

TO: Kerry Graber and Kaia Petersen, Washington Department of Ecology

Hazardous Waste and Toxics Reduction Program

FROM: Bill Beckley, Paul Bianco, and Bruno Ridolfi, RIDOLFI Inc.

SUBJECT: Review of Public Review Draft Remedial Investigation/Feasibility Study

Report for the Port of Longview Maintenance Facility Area in Longview,

Washington

At the request of Ecology's project manager, the Ridolfi project team has reviewed the public review draft of the *Remedial Investigation/Feasibility Study Report for the Port of Longview Maintenance Facility Area in Longview, Washington* dated July 12, 2016 and prepared for International Paper Company by AECOM.

Based on our review, we have prepared comments for Ecology's review and consideration, including general comments by topic area, and specific comments by section and page. Note that these comments are primarily focused on the Feasibility Study (FS) portion of the subject document.

The FS presented 10 alternatives to remediate the site soils:

- Alternative S1: Comprehensive Excavation (Baseline Alternative)
- Alternative S2: Comprehensive Excavation Outside Building Footprint
- Alternative S3: DNAPL Excavation Outside Building Footprint
- Alternative S4: DNAPL Excavation Outside Building Footprint, Limited Excavation Inside
- Alternative S5: Solidification Outside Building Footprint
- Alternative S5A: Solidification Outside Building Footprint, DNAPL Recovery Underneath Mechanics Shop
- Alternative S5B: Solidification Outside and Inside Building Footprint with Relocation of Soil Near Railroad Tracks



- Alternative S5C: Solidification Outside Building Footprint, ERH Treatment Under Mechanics Shop
- Alternative S6: DNAPL Treatment by Electrical Resistance Heating
- Alternative S7: DNAPL Excavation and Electrical Resistance Heating

The FS also presented four alternatives to remediate site groundwater:

- Alternative GW1 Electrical Resistance Heating and Enhanced Biodegradation (Baseline Alternative)
- Alternative GW2 Chemical Oxidation and Monitored Natural Attenuation
- Alternative GW3 Active Biosparging
- Alternative GW4 Monitored Natural Attenuation

Through the FS, International Paper selected Alternative S5B as their preferred alternative for the remediation of soils at the site. However, one result of Alternative S5B will be substantial soil expansion caused by the solidification process that will impact the existing site grades and elevations. In an attempt to eliminate the grading and elevation impacts to the site, the Port of Longview retained GeoEngineers to develop an alternative using technologies presented in the FS that would eliminate the grade and elevation changes caused by Alternative S5B. In addition, GeoEngineers estimated the cost of the Port of Longview's preferred alternative to compare to the estimated cost of Alternative S5B.

At Ecology's request, we have conducted a review and comparison of cost estimates developed for International Paper's preferred soil alternative (Alternative S5B) and the alternative proposed by the Port of Longview, which was not evaluated in the Remedial Investigation and Feasibility Study (RI/FS). Our evaluation of cost estimates included review of background project correspondence provided by the Ecology project manager, including updated cost estimates provided to Ecology by AECOM in a technical memorandum dated July 21, 2017. We also evaluated a revised cost estimate for the Port of Longview alternative provided by GeoEngineers to Ridolfi on March 6, 2018.

We prepared a set of spreadsheets to facilitate our evaluation of the cost estimates of all the alternatives evaluated in the FS, and these spreadsheets are provided as Attachments A1 and A2.



Specific comments on the FS cost estimates are included in the attached spreadsheets and in Specific Comments 13 and 14 of this memorandum.

Additionally, a separate comparison of cost estimates for International Paper's preferred soil cleanup alternative (Alternative S5B) and the Port of Longview's preferred alternative (not included in the FS) is provided following the specific comments on the FS. A separate spreadsheet supporting this cost comparison is provided as Attachment B.

GENERAL COMMENTS

Cleanup Levels

The RI/FS does not provide a clear demonstration, as required by Section 706 of the Model Toxics Control Act (MTCA) to support the use of Method C groundwater cleanup levels [WAC 173-340-706(1)(a)]. The rationale provided in the document for applying Method C groundwater cleanup levels includes the following: the site qualifies for Method C soil cleanup levels; there is a proposed deed restriction; and Method C levels for groundwater were approved at the adjacent treated wood products (TWP) site. However, none of these conditions meet the requirements for establishing Method C groundwater cleanup levels at this site, including the requirement that all practicable methods of treatment are used, and that: 1) Method A or B cleanup levels has the potential for creating a significantly greater overall threat to human health or the environment than attainment of Method C; or 3) Method A or B cleanup levels are below technically possible concentrations.

The fact that the site qualifies for Method C soil cleanup levels does not by itself mean that the site also qualifies for Method C groundwater cleanup levels. Section 745 of MTCA notes that "[a] property that qualifies for an industrial soil cleanup level under this section does not necessarily qualify for a Method C cleanup level in other media. Each medium must be evaluated separately using the criteria applicable to that medium" [WAC 173-340-745(2)(c)].

If conditions at the Maintenance Facility Area (MFA) site meet the conditions for establishing Method C groundwater cleanup levels, that demonstration should be provided.



Point of Compliance

The document does not appear to include a demonstration to support the approval of a conditional point of compliance for ground water, as required in section 720 of MTCA [WAC 173-340-720(8)(c)]. Ecology may approve a conditional point of compliance "where it can be demonstrated...that it is not practicable to meet the cleanup level throughout the site within a reasonable restoration time frame". A demonstration to support the approval of a conditional point of compliance for groundwater should be provided, including the requirement that "where a conditional point of compliance is proposed, the person responsible for undertaking the cleanup action shall demonstrate that all practicable methods of treatment are to be used in the site cleanup." MTCA defines "all practicable methods of treatment" as "all technologies and/or methods currently available and demonstrated to work under similar site circumstances or through pilot studies, and applicable to the site at reasonable cost" (WAC-173-340-200).

International Paper's preferred groundwater alternative (GW-4, Monitored Natural Attenuation) is unlikely to meet the requirement that all practicable methods of treatment have been used prior to being granted a conditional point of compliance for groundwater.

Chemicals of Concern (CoCs)

Dioxins are often found in association with wood-treating chemicals. It is not clear from the document why dioxins were not included as a COC. If they have been eliminated based on sampling and analysis or site history, then this information should be provided. If dioxins have not been evaluated, any future efforts to determine whether dioxins are present at the site above cleanup levels should be identified.

Evaluation of Soil Alternatives

The evaluation of soil alternatives based on MTCA criteria that is provided in Sections 8 and 9 of the subject document appears to be detailed, comprehensive, and generally consistent with Ecology regulations and guidance. However, it may be warranted to consider the likelihood of future disturbance of site soils related to Port of Longview operations when evaluating and ranking the permanence and long-term effectiveness criteria. Although MTCA guidance ranks immobilization or solidification (the preferred soil alternative) as being more effective over the long-term in comparison to off-site disposal, site-specific circumstances (i.e. being located beneath an active operating facility) should be thoroughly considered.



SPECIFIC COMMENTS

<u>Section 7 – Development of Cleanup Action Alternatives</u>

1. Section 7.4.3, Alternative S3 - DNAPL Excavation Outside Building Footprint, Page 7-13: The first paragraph includes the statement: "... long-term groundwater monitoring would be performed for a period of 2 years following completion of excavation." Since 2 years does not constitute long-term groundwater monitoring, this statement should be corrected here and in any other place it occurs within the RI/FS Report. Long-term groundwater monitoring is usually scheduled for 20 to 30 years.

[Per Section 410 of MTCA "Long-term monitoring shall be required if on-site disposal, isolation, or containment is the selected cleanup action for a site or a portion of a site. Such measures shall be required until residual hazardous substance concentrations no longer exceed site cleanup levels" (WAC 173-340-410(3)).]

- 2. Section 7.4.6, Alternative S5A Solidification Outside Building Footprint, DNAPL Recovery under Mechanics Shop, Page 7-20: Alternative S5A includes a DNAPL recovery system inside the mechanics' shop building footprint to remove DNAPL beneath the building. It is anticipated that the passive DNAPL collection system proposed would require long-term operations, and the probability is low that enough of the DNAPL will be removed to sufficiently reduce the concentrations of hazardous substances below site cleanup levels. The addition of heating elements to the DNAPL collection system would only increase DNAPL collection close to the recovery well due to the low power and limited heating capacity of these heating elements.
- 3. Section 7.4.7, Alternative S5B Solidification Outside and Inside Building Footprint with Relocation of Soil near Railroad Tracks, Page 7-23: The third paragraph that begins on Page 7-22 includes the statement: "Any soil identified as containing concentrations of COCs below cleanup levels could be placed above solidified soil within Zones 2 and 3 to provide additional depth in which the Port could work during potential future development or could be used as backfill in Zone 1." This additional soil in Zones 2 and 3 in combination with the increase in volume due to the solidification process in these zones could pose an adverse impact on Port of Longview operations. Information should be included in this section to address these potential impacts. Such information should



include a summary of the expected material balance in each zone that accounts for material moved into and out of each zone and volume increases due to material swell. The post-soil-handling volumes expected and anticipated surface grades in each zone should be shown in plan and cross-sectional views. Based on this information, mitigation measures should be identified and included as necessary to address potential adverse impacts from this soil placement.

4. Section 7.4.8, Alternative S5C – Solidification Outside Building Footprint, ERH Treatment under Mechanics Shop, Page 7-27: Alternative S5C includes in situ treatment by electrical resistance heating (ERH) inside the shop building footprint. One of the proposed ERH designs incorporates a subsurface system that begins heating at 2 feet below ground surface (bgs) and incorporates multi-phase extraction from the electrodes. Although a subsurface electrode could be designed to begin heating at 2 feet below ground surface, it's highly unlikely that such a system could be operated without exposing personnel working above the system to serious safety hazards such as stray electrical current, high temperatures, contaminated steam, and contaminated vapor migration within an enclosed space. Based on this concern, the design of a system that begins heating at 2 feet bgs is not technically feasible and should not be included in this RI/FS. In addition to these serious safety concerns, there are operational limitations. A multi-phase extraction could only be performed manually on an intermittent basis if the electrodes are installed below grade.

Section 9 - Selection of Preferred Cleanup Action Alternatives

- 5. <u>Table 9-6, MTCA Criteria Rankings Summary for Soil Alternatives</u>: The sum of individual risks for Alternative S1, which is listed as 77 in the table, should actually be 38; and the combined rank, which is listed as 10 in the table, should be 5.
- 6. <u>Table 9.7, MTCA Criteria Rankings Summary for Groundwater Alternatives</u>: Public Concerns for Alternative GW4 are ranked as 3 out of 4; however, Protectiveness is ranked as 4, which is the lowest of all alternatives presented. It seems inconsistent that the alternative ranked least protective would not be of the most concern to the public.



Appendix J - Cost Estimates

- 7. <u>Alternative S5C, Page 8 of 9</u>: The cost estimates for ERH installation, startup, and operation are based on the proposed subsurface ERH system. Since designing, constructing, and operating this ERH system in a safe manner is not technically feasible (see Comment 4 above), the cost estimate should be based on an above-ground ERH system.
- 8. <u>General Comment</u>: The cost estimates for several alternatives use the same amounts for work plans, mobilization, and design even though the work needed to complete these tasks would be substantially different. For example, the costs of completing work plans and designs for Alternatives S1 and S2 are the same, even though Alternative S1 would require additional planning, design work, and equipment selection for demolition of the existing facility.
- 9. <u>General Comment</u>: The cost estimates for ERH alternatives seem high for design, review, and long-term O&M. For example, for Alternative S6 Contractor Design and Work Plans are valued at \$86,000, and Engineering Design cost is estimated at \$193,000. The allocation of these costs should be revisited, and justification should be provided for the higher engineering design cost, since most of the design work for an ERH system would be completed by the ERH contractor.
- 10. <u>General Comment</u>: The FS should clarify and confirm the 30-year O&M period on which each cost estimate is based. For example, the text in Section 7.4.3 states, "... long-term groundwater monitoring would be performed for a period of 2 years following completion of excavation." This reference to 2 years with respect to long-term monitoring should be removed from the RI/FS Report. For removal actions, such as in Alternative S1, long-term O&M should be reduced with respect to other alternatives (such as Alternative S5) in which removal actions do not occur.
- 11. <u>Engineering Costs (Capital Indirect) and Alternative Cost Summary</u>: Line item 2 under Engineering Costs applies a 1-percent Direct Capital Costs (DCC) factor to estimate the cost of Regulatory Review, Coordination, and Meetings. Then, under Alternative Cost Summary, 3 percent of Capital Costs is added to the budget for Agency Oversight. The difference between these budget line items should be explained. If the Agency Oversight



tasks are associated with O&M, should the budget for Agency Oversight be based on a percentage of the O&M costs?

- 12. Groundwater (GW) Remediation Alternatives: The same contingency factor was applied to each groundwater remediation alternative (GW1, GW2, GW3, and GW4); however, the RI/FS Report recognizes that monitored natural attenuation (MNA) carries a greater risk. The following statement is taken from the RI/FS Report: "... if progress towards achieving the cleanup levels cannot be demonstrated during the 5-year reviews, the need for implementing the contingent cleanup action, chemical oxidation (Alternative GW2), would be assessed." In addition to this contingent GW cleanup alternative, the RI/FS proposes the future use of chemical oxidation if MNA is not successful. These contingent actions are included in the analysis of cleanup action alternatives to reduce the hazard rankings of MNA, and this assumes that chemical oxidation will be used in the event that MNA is unsuccessful. Since MNA carries a greater risk of not being successful, the contingency factor should be much greater than the 25 percent applied in the cost estimate. This contingency factor should recognize and account for the higher uncertainty, greater risk, and higher probability of increased costs of chemical oxidation that would probably be required in the future. If a substantially higher contingency factor is not applied to Alternative GW4, the hazard rankings should be revised based on MNA without the application and benefit of chemical oxidation.
- 13. <u>Total Costs for Soil Remediation Alternatives</u>: The line item and total costs for each alternative were copied to a spreadsheet (Attachment A1) for review and comparison. The costs in Attachment A1 are from the public review draft of the *Remedial Investigation/ Feasibility Study Report for the Port of Longview Maintenance Facility Area in Longview, Washington* dated July 12, 2016. Our review comments from this spreadsheet are summarized below:
 - Contractor Costs, Alternatives S5C, S6, and S7, Tasks 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, and 20: The cost estimates for DNAPL treatment and electrical resistance heating (ERH) are reasonable if only soil is being treated; however, combining soil treatment with groundwater treatment would eliminate redundant tasks and activities and reduce associated costs. Consider combining Alternative GW1 with a soil remediation alternative to eliminate separate mobilization, demobilization, equipment installation, and operations for soil and groundwater treatment.



- Contractor Cost, Alternatives S5C, S6, and S7: Each of these alternatives involves
 electrical resistance heating (ERH) treatment technology. In addition to combining
 ERH soil treatment with ERH groundwater treatment, conductive heating should be
 considered in lieu of ERH, especially as a thermal treatment technology to remove
 heavier polyaromatic hydrocarbons (PAHs).
- Contractor Costs, Alternative S5B: The purpose and need for additional backfill
 material for this alternative are unclear. This indicates that there will be a net
 decrease in volume. A table summarizing the material balance within each area
 should be provided to substantiate the quantities and costs associated with
 excavation, material swell, and backfilling.
- Contractor Costs, Alternatives S1 through S7, Contingency Factors: The
 contingency factors applied to Contractor Costs range from 20 percent to 30 percent.
 These factors seem low with respect to the relatively high levels of uncertainty
 associated with the more complex remediation systems. A contingency factor of 20
 percent is applied to contractor costs for Alternative S5B. This factor should probably
 be substantially higher. These contingency factors should be revisited, rationale for
 each factor should be provided, and each factor should be adjusted as necessary.
- Non-Routine Operations and Maintenance (O&M) Cost, Alternative S5A: An allowance of \$2,500 is provided for Alternative S5A only. This allowance for "non-routine O&M cost" is 2 percent of construction cost. Should this factor be applied to all 10 alternatives, or should it be eliminated and included as a contingency applied to the estimates of annual O&M and long-term monitoring (LTM) costs? This allowance should be revisited and addressed as necessary.
- Present Worth of O&M and LTM Costs: Allowances for the annual costs of long-term operating and maintenance (O&M) and long-term monitoring (LTM) are provided for all 10 alternatives. These allowances range from \$51,708 to \$123,058. A time frame of 30 years is assumed for long-term O&M and LTM; therefore, it's probably appropriate to project the total annual costs for O&M and LTM out over 30 years. This results in a substantially higher present worth and a higher total present worth alternative cost. Consider this proposed change in final evaluation of the alternatives for remedy selection.



- 14. <u>Total Costs for Groundwater Remediation Alternatives</u>: The line item and total costs for each alternative were copied to an attached spreadsheet (Attachment A2) for review and comparison. The costs in Attachment A2 are from the public review draft of the *Remedial Investigation/ Feasibility Study Report for the Port of Longview Maintenance Facility Area in Longview, Washington* dated July 12, 2016. Our review comments from this spreadsheet are summarized below:
 - Contractor Costs, Alternative GW4, Task 3: Allowances for "Contractor Coordination with Port's maintenance operations" should also be provided for Alternatives GW1, GW2, and GW3; and the allowance for GW4 should be substantially greater.
 - Contractor Costs, Alternative GW3, Task 3: Allowances for "Inconvenience Fee for Disruption of Port's maintenance operations" should be provided for Alternatives GW1 and GW2.
 - Contractor Costs, Alternatives GW3 and GW4, Task 4: The allowances for "Specialty Subcontractors (surveyor, utility locates)" for Alternatives GW3 and GW4 seem low. Provide the basis for these cost estimates and revise the estimates as needed.
 - **Contractor Costs, Alternative GW2, Task 8:** Allowances for "Environmental Protection" should be provided for Alternatives GW1 and GW3.
 - Contractor Costs, Alternative GW1, Task 8: Allowances should be provided for "Storm Water Handling and Environmental Protection" for Alternatives GW2 and GW3.
 - Contractor Costs, Alternatives GW2 and GW3, Tasks 15 and 11: An allowance should be provided for "General Site Restoration Work" for Alternative GW1.
 - Contractor Costs, Alternative GW1, Task 10: Allowances should be provided for "General Trenching and Site Restoration Work" for Alternatives GW2 and GW3.
 - Contractor Costs, Alternative GW1, Task 11: Provide a breakdown of the cost estimate for "Drilling & Analytical Services for subsurface ERH installations" to verify



the total amount. Clarify the scope of this task. Does it include just drilling or does it also include trenching?

- Contractor Costs, Alternative GW1, Tasks 18 and 19: Why is the use of an oxygen release compound (ORC) included for this alternative only and not for GW2, GW3, and GW4?
- Contractor Costs, Alternative GW2, Task 17: Regarding "Monitoring Well Installation for Oxidation and MNA," can the same wells can be used for chemical oxidation and long-term monitoring?
- Contractor Costs, Alternative GW4, Task 6: The \$4,000 allowance for demobilization on Alternative GW4 seems low.
- Annual O&M and LTM Costs, Alternative GW2 and GW4, Task 1: Cost allowances
 for annual monitoring of institutional controls for Alternatives GW2 and GW4 seem
 low at \$1,000 and \$2,000 per year, respectively.
- Annual O&M and LTM Costs, Alternative GW2 and GW4, O&M Contingency:
 Based on the risk and high probability that monitored natural attenuation (MNA) will not provide an adequate remedy, and groundwater treatment might be necessary, this contingency factor and contingency allowances are low.

COST COMPARISON OF INTERNATIONAL PAPER ALTERNATIVE S5B AND THE PORT OF LONGVIEW PREFERRED ALTERNATIVE FOR SOIL REMEDIATION

At the request of Ecology's project manager, the Ridolfi project team has prepared the following comparison of estimated costs for two soil cleanup action alternatives; Alternative S5B, identified as the preferred soil cleanup alternative in the draft Remedial Investigation/Feasibility Study Report for the Port of Longview Maintenance Facility Area in Longview, Washington (RI/FS), and the Port of Longview's preferred soil cleanup alternative, which was not evaluated in the RI/FS.

To compare the alternatives, Ridolfi reviewed cost estimates and supporting information provided by AECOM (on behalf of International Paper) and by GeoEngineers (on behalf on the Port of Longview). Additionally, Ridolfi developed revised versions of each of the cost estimates



that were intended to eliminate disparities between cost assumptions and present a fair comparison of costs.

Alternative Remediation Plans

Under both alternatives the upper three feet of soil is assumed to be clean (below cleanup standards). Therefore, the top three feet of soil will be excavated, stockpiled on-site, and re-used after completion of the remedy. In addition, both alternatives assume a maximum treatment depth of nine feet below ground surface.

Alternative S5B consists of soil excavation within the limits of a proposed "dump pit" area, consolidation of excavated dump pit soils within the remaining extent of the treatment area, and in-situ mechanical mixing of solidifying agents into the treatment area. Under this alternative, all contaminated soil remains on-site and is treated using the solidification technique. Due to the consolidation of excavated dump pit soil and volumetric expansion due to solidification, this alternative would increase the final surface elevation of the site.

The Port of Longview's preferred alternative consists of soil excavation within the limits of the dump pit area, and soil excavation from three to five feet below grade over the remaining treatment area. Contaminated soil will be transported and disposed of at an agency approved landfill. Once the excavation is complete, in-situ mechanical mixing of solidifying agents into the treatment area from five to nine feet below ground surface will be performed. New and stockpiled fill material will be used to return the site to its original grade.

To compare the cost estimates associated with each alternative, Ridolfi created a side-by-side comparison spreadsheet using the cost data provided by AECOM and GeoEngineers (Attachment B). Four discrete cost estimates are presented on Attachment B as follows:

- 1. <u>International Paper Alternative S5B</u>: This cost estimate presents the latest estimate provided by AECOM dated July 21, 2017. No changes were made to this estimate.
- 2. <u>Port of Longview Preferred Alternative</u>: This cost estimate presents the latest estimate provided by GeoEngineers dated March 6, 2018. No changes were made to this estimate.
- 3. <u>Ridolfi Alternative S5B</u>: This cost estimate presents Ridolfi's analysis of the necessary costs to complete Alternative S5B. To complete this analysis all estimates were based on unit costs or quantities provided by AECOM or GeoEngineers.



4. <u>Ridolfi Port of Longview Preferred Alternative</u>: This cost estimate presents Ridolfi's analysis of the necessary costs to complete the Port of Longview's preferred alternative. To complete this analysis all estimates were based on unit costs or quantities provided by AECOM or GeoEngineers.

For most tasks and cost elements, the costs associated with each alternative are equal since each alternative proposes similar treatment methods. However, to produce revised estimates that could be compared fairly and equally, wherever the cost estimates differed Ridolfi selected the unit cost or methodology from one of the base alternatives and assigned it to both alternatives. The following decisions were made during the Ridolfi analysis to present an objective analysis.

- Mobilization/Demobilization Task: Alternative S5B presented a solidification mobilization/demobilization cost of \$225,000 and the Port of Longview presented a cost of \$152,000. This was due to the Port of Longview receiving a lower cost estimate from a solidification contractor. Since each contractor will perform solidification, the lower mobilization/demobilization cost was used in the Ridolfi analysis.
- Shoring Tasks: Alternative S5B proposed freeze wall shoring for securing the perimeter of the excavation. The Port of Longview's preferred alternative proposed two methods, consisting of sheet pile near the building and existing slurry wall, and cut slopes at a 45-degree angle elsewhere to secure the excavation. Since either method is acceptable, the lower cost option of sheet pile and cut slopes was used for both alternatives in Ridolfi's analysis.
- <u>Solidification Labor</u>: Alternative S5B presented a solidification labor cost of \$60 per cubic yard and the Port of Longview presented a labor cost of \$30 per cubic yard. This was due to the Port of Longview receiving a lower cost estimate from a solidification contractor. Since each contractor will perform solidification, the lower solidification labor cost was used in the Ridolfi analysis.
- <u>Contaminated Soil Disposal</u>: Under the Port of Longview's preferred alternative, contaminated soil disposal of excavated soil is necessary. The Port of Longview assumption that 85 percent of the excavated material will be disposed of as hazardous waste was used in the Ridolfi analysis.



- Engineering Costs (Capital Direct): Alternative S5B used a 7 percent estimate for engineering design and the Port of Longview's preferred alternative used a 5 percent estimate. The Ridolfi analysis uses the more conservative 7 percent estimate for both alternatives.
- <u>Cost per Cubic Yard</u>: Ridolfi used the treatment area and depths given in both the Alternative S5B and the Port of Longview's preferred alternative cost estimates to calculate a total treatment volume of 7,404 cubic yards (CY).

In the attached spreadsheet, the cost difference between the original cost estimates provided by AECOM and GeoEngineers is presented in the column labeled "Cost Difference – (POL-S5B)". The cost difference between Alternative S5B and the Port of Longview's Preferred Alternative based on Ridolfi's revised analysis is presented in the column labeled "Cost Difference – (RPOL-RS5B)".

Based on information provided by AECOM and GeoEngineers, and Ridolfi's revised analysis of each alternative, the summary of estimated costs of the remediation alternatives are presented in Table 1. A detailed cost comparison is provided in Attachment B.



Table 1. Summary of Estimated Costs for Selected Alternatives

Alternative	International Paper Alternative S5B	Port of Longview's Preferred Alternative	International Paper Alternative S5B	Port of Longview's Preferred Alternative
Estimator	AECOM	GeoEngineers	Ridolfi	Ridolfi
Remedial Action Construction	\$2,258,300	\$1,751,500	\$1,883,800	\$1,751,000
Contaminated Waste Disposal and Transportation	\$24,400	\$850,100	\$24,400	\$850,100
Contractor Contingency (20%)	\$456,500	\$520,300	\$381,600	\$520,200
Total Engineering Costs	\$710,400	\$709,200	\$710,400	\$777,700
O&M and Long- Term Monitoring Costs	\$649,100	\$649,100	\$649,100	\$649,100
Sales Tax and Agency Oversight	\$322,600	\$364,700	\$273,200	\$366,700
Total Project Cost	\$4,421,300	\$4,844,900	\$3,922,500	\$4,914,800
Project Unit Cost (\$/CY)	\$597	\$654	\$530	\$664



Conclusions and Observations

The following conclusions and observations are based on the cost comparison analysis.

- Based on the comparison of Ridolfi revised cost estimates, the cost of International Paper Alternative S5B is approximately \$1,000,000 lower than the cost of Port of Longview Preferred Alternative.
- The majority (83 percent) of the cost disparity between International Paper Alternative S5B and the Port of Longview's Preferred Alternative is due to the costs associated with transportation and disposal of contaminated soil, which is only required in the Port of Longview's Preferred Alternative.
- Since most of the cost disparity is due to the transportation and disposal of contaminated soil, a significant savings could result if soil characterization determined that less than the assumed 85 percent of the soil is considered CAMU-eligible waste.
- The cost estimates presented in this memorandum do not include costs for dioxin sampling and analysis that would be required to adequately characterize site soils and groundwater. These costs would likely be equal for both alternatives, but may be slightly higher for the Port of Longview's Preferred Alternative depending on soil characterization requirements of the disposal facility.
- Engineering Costs for the Port of Longview's Preferred Alternative are likely biased high, since certain tasks are based on a percentage of the costs for "Remedial Action Construction" and "Contaminated Waste Disposal and Transportation." Costs associated with these two activities are approximately \$850,000 higher for the Port of Longview's Preferred Alternative due to soil disposal; however, the higher disposal and transportation costs would not necessarily result in proportionally higher costs for engineering and other support activities.



Prepared and reviewed by:

Bill Beckley

Principal Environmental Scientist

Sell Bedly

Bruno Ridolfi, P.E.

MRiddefi

Principal Engineer

Paul Bianco, P.E.

Senior Environmental Engineer



Task Numbers by Alternative Task Description				l ine-lten	n and Total Costs	s hy Alternativ	'A				
S1 S2 S3 S4 S5 S5A S5B S5C S6 S7 Alternatives for Soil Remediation	S1	S2	S3	S4	S5	S5A	S5B	S5C	S6	S7	Review Notes, Questions, and Comments
Contractor Costs (Capital Direct)											
Remedial Action Construction					Γ.			Τ.	1.		
1 1 1 1 1 1 1 1 1 1 1 Mobilization / Demobilization	67,000			67,000 \$	225,000 \$	225,000	\$ 225,000			\$ 150,000	
2 2 2 2 2 2 2 3 2 Contractor Design and Work Plans 3 3 3 3 3 3 Solidification Pilot Testing	21,600	\$ 21,600	\$ 21,600	\$ 21,600 \$	21,600 \$ 120,000 \$	21,600 120,000	\$ 21,600 \$ 105,000			\$ 70,000	
3 3 3 3 4 4 4 4 4 3 Temporary Relocation of Port Maintenance Operations	30,000	\$ 30,000	\$ 30,000	30,000 \$	30,000 \$	30,000	\$ 105,000			\$ 30,000	
4 Demo Port's Maintenance Building (east corner)		30,000	30,000	30,000 \$	30,000 \$	30,000	\$ 50,000	\$ 50,000	30,000	\$ 30,000	
4 Demo Port's Maintenance Buildling Interior Floor Slab				19,500							
5 4 4 5 5 5 5 5 5 5 4 Demo Horizontal Bioventing Wells & Connection Piping	29,600	\$ 29,600	\$ 29,600	29,600 \$	29,600 \$	29,600	\$ 29,600	\$ 29,600	\$ 29,600	\$ 29,600	
6 5 5 6 6 6 6 6 6 5 Decommission Groundwater Monitoring & Biovent Wells	32,200			\$ 23,000 \$	36,800 \$	36,800	\$ 36,800				
7 6 6 7 7 7 7 7 6 Specialty Subcontractors (surveyor, utility locate)	8,000				8,000 \$	8,000	\$ 8,000				
8 7 7 8 8 8 8 8 8 7 Demo Underground Utilities and Fencing	28,000			28,000 \$	28,000 \$	28,000	\$ 28,000				
9 8 8 9 9 9 9 8 Demo Retaining Wall \$ 10 Demo Portion of Building with Lower Roof Height \$ \$	12,000	\$ 12,000	\$ 12,000	\$ 12,000 \$	12,000 \$	12,000	\$ 16,500 \$ 62,500			\$ 12,000	
10 9 9 10 9 Install Freeze Wall Shoring for Building (200 LF)	142,800	\$ 142,800	\$ 142,800	142,800			\$ 02,300			\$ 225,000	
11 10 Install Freeze Wall Shoring for Excavation Perimeter (720 LF)	468,720		,,,,,,								
10 11 10 Install Freeze Wall Shoring for Excavation Perimeter (550 LF)			\$ 358,050	358,050						\$ 358,050	
											Verify that shoring will not be needed for Alternative S5B as well as Alternatives S5, S5A,
12 11 11 12 11 Install Sheet Pile Wall Shoring along Slurry Wall (100 LF) 9	112,500		\$ 112,500	112,500						\$ 112,500	S5C, and S6.
13 12 12 13 10 10 11 10 20 Remove Surface Asphalt in Storage Yard and Road	28,688	\$ 28,688	\$ 21,912	21,912 \$	28,688 \$	28,688	\$ 28,688			\$ 21,912	
14 13 14 11 12 12 11 21 Remove 42-IN HDPE Culvert and Replace after Excavation \$ 15 14 15 12 11 13 12 22 Excavation and Stockpiling of Overburden (0 to 3 FT bgs)	18,750 105,300	\$ 18,750 \$ 97,200	\$ 18,750 S \$ 75,600 S	\$ 18,750 \$ \$ 78,300 \$	18,750 \$ 97,200 \$	18,750 97,200	\$ 18,750 \$ 105,300			\$ 18,750 \$ 75,600	
15 14 14 15 12 11 13 12 22 Excavation and Stockpiling of Overburden (0 to 3 FT bgs) \$	105,500	ş 91,200	φ / 5,000 S	10,300 \$	31,200 \$	31,200	p 105,500	φ 01,000	'	φ / 5,000	Cost allowances for storm water handling and environmental protection should be
13 13 14 13 9 12 Storm Water Handling and Environmental Protection				¢	11,000 \$	11,000	\$ 11,000	\$ 11,000	\$ 17,500	\$ 15,000	included for Alternatives S1, S2, S3, and S4.
13 13 14 15 9 12 Stoffin Water Handling and Environmental Protection					11,000 \$	11,000	₊ 11,000	\$ 42,000		\$ 18,000	
11 General Trenching and Site Restoration Work								,	\$ 50,000		
											Review these nine tasks with Paul Bianco regarding DNAPL treatment and Electrical
15 12 14 Drilling & Analytical Services for subsurface ERH installations								\$ 70,500	\$ 234,000	\$ 41,310	Resistance Heating (ERH)
13 Upgrade Electrical Service to Treatment Pad									\$ 40,000		
											These cost estimates seem high, but are reasonable if only soil is being treated.
16 14 15 ERH Surface installations and startup								\$ 180,750	\$ 461,000	\$ 181,000	Assuming that only the soil, and not the groundwater, will be treated poses a problem.
								, , , , , ,	1,	, ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	If the approach provided here is used, it is recommended that Alternative GW1 be
											combined with the corresponding soil remediation alternative to reduce the total
											combined cost of soil and groundwater treatment. This combined treatment alternative
17 15 16 ERH Operations								\$ 348,000	\$ 726,000	\$ 314,000	would eliminate redundant costs for mobilization, installation, and operation.
18 16 17 Electrical Connection and Usage charges								\$ 102,750		\$ 79,000	
19 17 18 Activated Carbon Usage								\$ 7,000		\$ 10,000	
20 19 19 Other Misc. ERH operational costs								\$ 14,250	\$ 15,000	\$ 16,000	
15 Excavate Soil from 3 to 8 feet bgs within 80 feet of Railroad Tracks							\$ 23,100				
16 Relocate and Backfill Soil from Near the Railroad Tracks					110.000	440.000	\$ 14,850				
14 14 17 21 Solidification Materials (8% NewCem Slag Cement)				\$	113,880 \$ 50,370 \$	113,880 50,370	\$ 116,220 \$ 51,405				
16 16 19 23 Solidification Materials (2% Bentonite Grout - Hydrogel 90)			+	\$	69,806 \$	69,806	\$ 51,405 \$ 71,241		'		
17 17 24 Solidification Labor and Equipment				\$	438,000 \$	438,000	ψ /1,2 -1 1	\$ 366,000			
20 Solidification Labor and Equipment Outside Building Footprint				,	100,000	,	\$ 417,000				
21 Solidification Labor and Equipment Under Mechanics Shop							\$ 30,000				
18 18 22 25 Geotextile Fabric Market Layer over Solidified Soil				\$	6,650 \$	6,650					
19 19 23 26 Import of Clean Backfill for Transition Grades				\$	34,000 \$	34,000	\$ 34,000	\$ 34,000			
16 Specialty excavation of Contaminated Soil inside building				12,750		-					Miles in additional healfill material model for Alternative CED2 This is discussed as
24 Additional Import of Backfill Material to Replace Relocated Soil							¢ 22.000				Why is additional backfill material needed for Alternative S5B? This indicates that there will be a net decrease in soil volume.
16 15 17 24 Additional Import of Backfill Material to Replace Relocated Soil 16 15 17 23 Excavation and Stockpiling of Contaminated Soil 1	182,000	\$ 170,800	\$ 131,600	\$ 137,200	+		\$ 32,000	+		\$ 128,800	
25 Excavation and Stockplining or Contaminated Soil	, 102,000	ų 170,000	151,000	131,200		+				4 120,000	Request a summary table of the material balance include volumes of soil removed,
17 17 16 18	58,500	\$ 54,900	\$ 42,300	45,630						\$ 41,400	I - 1
18 18 20 26 Import of Clean Fill to the Site 9	130,000		\$ 94,000	101,400						\$ 92,000	
										<u> </u>	Allowances for water handling and environmental protection should be included for
19 16 17 19 18 25 Contaminated Water Handling and Environmental Protection	32,500	\$ 30,000	\$ 25,000	27,500					\$ 50,000	\$ 27,500	Alternatives S5, S5A, S5B, and S5C.
20 19 19 21 19 20 27 27 Backfill and Compaction of Excavation 9	93,600	\$ 87,300	\$ 67,500	\$ 71,730 \$	32,400 \$	32,400		\$ 27,000		\$ 66,600	
25 Backfill and Compaction of Overburden Soil Stockiles on Site							\$ 42,900				
26 Backfill and Compaction of Transitional Backfill Material	120.400	d 120.400	¢ 00.000	00.000			\$ 29,700	-		t 00.000	
21 20 20 22 28 Asphalt Paving of Site Excavation Areas 3 20 21 27 28 Asphalt Paving of Excavation, Solidification, and Transition Areas	130,400	\$ 130,400	\$ 99,600	99,600	130,400 \$	130,400	\$ 130,400	\$ 109,600		\$ 99,600	
22 21 23 21 22 28 29 20 29 Rebuild Access Road (150 LF) \$	22,500	\$ 18,750	\$ 22,500	\$ 22,500 \$	22,500 \$	22,500	\$ 130,400 \$ 22,500			\$ 22,500	
22 21 21 23 21 22 20 23 20 25 Rebuild Access Road (150 Lr)	. 22,300	- 10,130	- 22,500	. 22,500 \$		22,300		÷ 22,300	\$ 75,000	- 22,500	
29 Reconstruct Lower Roof Height Portion of Maintenance Building							\$ 125,000		.,		
23 23 22 24 22 23 30 30 Rebuild Retaining Wall	24,000			\$ 24,000 \$	24,000 \$	24,000		\$ 24,000		\$ 24,000	Why is the cost of rebuilding the retaining wall not included in Alternative S5B?
24 22 23 25 23 24 30 31 22 31 Replace Connection Piping for Bioventing System	24,000	\$ 24,000	\$ 24,000	\$ 24,000 \$	24,000 \$	24,000	\$ 24,000	\$ 24,000	\$ 24,000	\$ 24,000	
25 Reconstruct Maintenance Building (east corner)	150,000										
26 Reconstruct Maintenance Building Interior Floor Slab	F 1 000	f 51000	¢ 27.000	27,000	E4.000 #	E4.000	¢ 54000	d 5100	d 51000	¢	
26 24 24 27 24 25 31 32 24 32 Monitoring Well Installation	54,000	\$ 54,000	\$ 37,800	\$ 37,800 \$	54,000 \$	54,000	\$ 54,000	\$ 54,000	\$ 54,000	\$ 54,000	<u> </u>



							in Alternatives from the rubic Review Draft of the Remediat Investigation/resour				•			•				
		Numbe					Task Description					em and Total Cost						Review Notes, Questions, and Comments
S1 S2	2 S3	S4 S	S5 S5A	A S5B	S5C	S6	Alternatives for Soil Remediation	S1	S2	S 3	S4	S5	S5A	S5B	S5C	S6	S7	never rotes, questions, and comments
			26	,			Product Recovery Well Installation					\$	30,000					
			27				DNAPL Recovery Equipment and Supplies					\$	23,600					
			28				Heaters for Recovery Wells					\$	875					
			29	1			Product Recovery System Installation and Startup					\$	17,500					
																		Verify the relatively low cost allowances for all 10 alternatives. The level of effort (200
27 2	25	28 2	25 30	32	33	25	33 Contractor Reporting and Closeout Submittals \$	26,100	\$ 18,000	\$ 14,400	\$ 14,400 \$	14,400 \$	21,600	\$ 18,000	\$ 34,200	\$ 18,000	\$ 34,200	hours) for Alternative S5B seems low.
2, 2.		20 2		52	55		Subtotal \$				\$ 1,616,522 \$					\$ 2,918,800		nound) for recent cons
Conta	minata	d Waste	o Diene	ocal an	d Tra	nenori		2,107,730	\$ 1,031,200	\$ 1,331,312	3 1,010,322 3	1,001,044 \$	1,700,219	\$ 1,500,071	\$ 2,323,043	\$ 2,910,000	\$ 2,431,322	
							1 NAPL Soil (CAMU RCRA Stabilization) Costs \$	195,075	\$ 183,600	\$ 183,600	\$ 195,075 \$	- \$		¢	¢	\$ 1,275	\$ 183,600	
1 1	1	2 .	2 2	1	_							Ψ.	-	.	.	\$ 1,650		
2 2	2	2 4	2 2	2				42,075			\$ 42,075 \$	- \$	-	\$ -	5 -			
3 3	3		_				3 Liquid NAPL Material Disposal Costs (Incinerator) \$	31,000			\$ 31,000 \$	- \$	500		\$ 10,000	\$ 23,000		
4 4	4	4 4	4 4	4		_	4 Liquid NAPL Transportation Costs to Incinerator \$	15,500			\$ 15,500 \$	- \$	250		\$ 5,000	\$ 11,500	\$ 15,500	
5 5	5	5 !	5 5	5			5 CAMU-Eligible Material Disposal Costs (Subtitle C Landfill) \$	1,035,000			\$ 845,250 \$	- \$	-	\$ -	\$ -	\$ 3,450		
6 6	6	6 (6 6	6	6	6	6 Transportation Costs to Subtitle C Landfill \$	495,000			\$ 404,250 \$	- \$	-	\$ -	\$ -	\$ 1,650		
7 7	7	7	7 7	7	7	7	7 Non-Hazardous Material Disposal Costs (Subtitle D) \$	1,800	\$ 1,800	\$ 1,350	\$ 1,350 \$	- \$	-	\$ -	\$ -	\$ 300	\$ 1,350	
8 8	8	8 8	8 8	8	8	8	8 Transportation Costs to Subtitle D Landfill \$	1,500	\$ 1,500	\$ 1,125	\$ 1,125 \$	- \$	-	\$ -	\$ -	\$ 750	\$ 1,125	
9 9	9	9 9	9 9	9	9	9	9 Contaminated Water Treatment and Disposal \$	39,000	\$ 36,600	\$ 28,000	\$ 29,600 \$	- \$	-	\$ -	\$ -	\$ 6,000	\$ 28,600	
10 10	10	10 1	10 10	10	10	10	0 Non-Hazardous Material Disposal Costs (Asphalt Recycling) \$	6,761	\$ 6,761	\$ 5,200	\$ 5,200 \$	6,761 \$	6,948	\$ 6,761	\$ 7,197	\$ 240	\$ 2,640	
11 1	1 11						11 Transportation Costs to Asphalt Recycler \$				\$ 5,850 \$	7,607 \$	7,817			\$ 270		
	+		+	+			Subtotal \$					14,368 \$	15,515				\$ 1,479,385	
	+		-	+		-+	Subtotal Contractor Costs \$				\$ 3,192,797 \$							
 	+	\vdash	-	+			Subtotal Contractor Costs 3	3,310,010	¥ 3,312,170	¥ 3,030,231	y 3,132,131 \$	1,055,412 \$	1,113,134	ψ 1,302,433	Ψ £,333,331	Ψ £,300,003	¥ 3,330,101	Contractor contingency for Alternative CEP should probably be higher Described
																		Contractor contingency for Alternative SSB should probably be higher. Provide criteria
				4	ļ		Contingency Factors (% Contractor Costs)	20%	20%	20%	20%	20%	20%	20%	20%	30%	25%	on which contingency factors are based. Adjust factors as necessary.
							Contractor Contingency (20% for S1 to S5C, 30% for S6, 25% for S7) \$	795,615			\$ 638,559 \$	339,082 \$	355,147	\$ 396,488		\$ 890,666	\$ 982,677	
	T			\perp	T	T	Total Contractor Costs \$	4,773,691	\$ 4,214,611	\$ 3,645,884	\$ 3,831,356 \$	2,034,494 \$	2,130,881	\$ 2,378,927	\$ 2,824,724	\$ 3,859,551	\$ 4,913,384	
Engi	neering	Costs	(Capita	al Indir	ect)													
1 1	1		1 1			1	1 General Coordination, Meetings, and Planning (% DCC) \$	95,400	\$ 84,200	\$ 73,000	\$ 76,600 \$	40,600 \$	42,600	\$ 47,580	\$ 56,400	\$ 77,200	\$ 73,650	
2 2	2	2 :	2 2	2			2 Regulatory Review, Coordination, and Meetings (% DCC) \$	47,700				40,600 \$	42,600			\$ 38,600		
H	+-1		3 3	_	3	-	Pilot Test Sampling, CBR, and Reporting	,	, . 30		\$	75,000 \$	75,000			. 22,230	,	
2 2	3		4 4	_		2	3 Engineering Design (% DCC) \$	143,100	\$ 126,300	\$ 146,000	\$ 153,200 \$	142,100 \$	149,100	\$ 166,530		\$ 193,000	\$ 147,300	
1 1	3	1 1	5 5				4 Planning for temporary relocation of Port Maintenance Ops \$	13,500			\$ 13,500 \$	13,500 \$	13,500			\$ 13,500	\$ 13,500	
F F	- 4 - r	4 :	6 6	_			3 1 2	8,100				8,100 \$	8,100			\$ 10,800	\$ 13,500	
5 5	5	5 (_			5 Bid & RFI Support \$				\$ 8,100 \$			\$ 8,100				
6 6	6	6	7 7		7	6	6 Construction Oversight and QA (% DCC) \$	238,500	\$ 210,500	\$ 182,500	\$ 191,500 \$	101,500 \$	106,500	\$ 118,950	\$ 141,000	\$ 193,000	\$ 245,500	
			8		8		System Startup (if applicable)					\$	5,000		\$ -			
7 7	7	7 8	8 9		9		7 Confirmational Sample Collection and Reporting \$	30,000			\$ 20,000 \$	33,000 \$	33,000	\$ 33,000		\$ 33,000	\$ 33,000	
8 8	8	8 9	9 10	9	10	8	8 Closure Documentation & Reporting \$	53,000			\$ 53,000 \$	53,000 \$	53,000	\$ 53,000		\$ 53,000	\$ 53,000	
							Subtotal Engineering Costs \$					507,400 \$	528,400					
							Engineering Contingency (10 percent) \$	62,930	\$ 56,770	\$ 53,260	\$ 55,420 \$	50,740 \$	52,840	\$ 56,324	\$ 63,380	\$ 61,210	\$ 62,855	
							Total Engineering Costs \$	692,230	\$ 624,470	\$ 585,860	\$ 609,620 \$	558,140 \$	581,240	\$ 619,564	\$ 697,180	\$ 673,310	\$ 691,405	
Annue	ıl 0&M	Cost (E	DNAPL	Recov	ery)													
			1				Project Management & Coordination					\$	6,480					
			2				Mob/Demob for O&M (monthly)					\$	21,600					
			3				Monthly O&M Labor					\$	18,000					
			4				Equipment Repair and Supplies					\$	7,500					
			5				Annual Product Recovery Reporting					\$	3,500					
\vdash	+ +		- 3				Subtotal Annual O&M Cost (DNAPL Recovery)			+) dr	57,080					
\vdash	+	$\vdash\vdash$	-	+	- 	-+	, , ,	+			-	3	14,270					
 	+		-	+			O&M Contingency (DNAPL Recovery, 25 percent)					\$						
\vdash	1000		44	<u> </u>			Total Annual O&M Cost (DNAPL Recovery)					\$	71,350					
Annuc	ıı U&M	Cost (V	weekly	Temp	Moni		for 6 months)	T		1	I	1			1			
oxdot	\perp	$oxed{oxed}$		\perp	[1	1 Project Management and Communication									\$ 14,040		
$oxed{oxed}$	\perp	$oxed{oxed}$	_		_	2	7 1									\$ 10,400		
						3	3 Monthly Reports									\$ 12,000		
							Subtotal Annual O&M Cost (Weekly Temp Monitoring)									\$ 36,440		
$\Box\Box$							O&M Contingency (Weekly Temp Monitoring, 25 percent)									\$ 9,110		
	$oldsymbol{ol}}}}}}}}}}}}}}}}$			\perp			Total Annual O&M Cost (Weekly Temp Monitoring)									\$ 45,550	\$ 22,775	
Annuc	ıl O&M	Cost (II	nstitut	ional c	ontro	ls mai	ntenance, asphalt inspection and repair)						<u></u>					
1 1	1	1	1 1	1	1	1	1 Project Management & Coordination \$	2,160	\$ 2,160	\$ 2,160	\$ 2,160 \$	2,160 \$	2,160	\$ 2,160	\$ 2,160	\$ 2,160	\$ 2,160	
2 2	2		_				2 Annual Inspection and Reporting \$	3,520				3,520 \$	3,520					
3 3			_				3 Update ICs Plan (once every 5 years) \$	750				750 \$	750					
4 4	4		_				4 Prorated Cost for Asphalt Repairs \$	8,606			\$ 8,606 \$	8,606 \$	8,606	\$ 8,606				
 	-		-	_	-		Subtotal Annual O&M Cost \$					15,036 \$	15,036					
 	+			+			O&M Contingency (25 percent) \$	3,759				3,759 \$	3,759					
\vdash	+ +	\vdash	-	+-		otal 1	nnual O&M Cost (ICS Maintenance and Asphalt Inspection/Repair as Needed) \$	18,795				18,795 \$	18,795					
	+		-	+	<u>, </u>	otal A												
							Total Annual O&M Cost \$	18,795	\$ 18,795	\$ 18,795	\$ 18,795 \$	18,795 \$	90,145	\$ 18,795	\$ 18,795	\$ 64,345	\$ 41,570	
Annuc	ıı LTM (Cost (M						, ,										
1 1	1		_				1 Project Management & Coordination \$	3,240				3,240 \$	3,240					
2 2	2		_				2 Mobilization/Demobilization for Sampling (semi-annual) \$	3,600				3,600 \$	3,600					
3 3	3						3 Pickup Truck Rental \$	390				390 \$	390					
4 4	4	4	4 4	4	4	4	4 Sampling Labor and Supplies \$	8,000	\$ 8,000	\$ 8,000	\$ 8,000 \$	8,000 \$	8,000	\$ 8,000	\$ 8,000	\$ 8,000	\$ 8,000	
5 5	5	5	5 5	5	5	5	5 Analytical Testing (DRO and SVOCs) \$	7,600	\$ 7,600	\$ 7,600	\$ 7,600 \$	7,600 \$	7,600	\$ 7,600	\$ 7,600	\$ 7,600	\$ 7,600	
6 6			_				6 Annual Reporting \$	3,500				3,500 \$	3,500				\$ 3,500	
						-	Subtotal Annual LTM Cost \$					26,330 \$	26,330					
								,	,	,,	,	.,	, •	,-50	,	,	,	



Task Numbers by Alternative	Task Description				Line	Item and Total C	osts by Alternative	•				Review Notes, Questions, and Comments
S1 S2 S3 S4 S5 S5A S5B S5C S6 S7	Alternatives for Soil Remediation	S1	S2	S3	S4	S5	S5A	S5B	S5C	S6	S7	Review Notes, Questions, and Comments
	LTM Contingency (25 percent) \$	6,583	\$ 6,583	\$ 6,583	\$ 6,583	6,583	\$ 6,583 \$	6,583	\$ 6,583	\$ 6,583	\$ 6,583	
	Total Annual LTM Cost \$	32,913	\$ 32,913	\$ 32,913	\$ 32,913	\$ 32,913	\$ 32,913	32,913	\$ 32,913	\$ 32,913	\$ 32,913	
	Total Annual O&M and LTM Cost \$	51,708	\$ 51,708	\$ 51,708	\$ 51,708	\$ 51,708		51,708	\$ 51,708	\$ 97,258	\$ 74,483	
	Total Non-Routine O&M Cost (estimated to be 2% of construction costs						\$ 2,500					Should this allowance for non-routine O&M be included in all alternatives?
	Total O&M and LTM Cost (30 years until completion) \$	629,800	\$ 629,800	\$ 629,800	\$ 629,800	\$ 893,000	\$ 1,208,000	893,000	\$ 893,000	\$ 675,000	\$ 653,000	
	Present-Worth O&M Cost (with presumed interest rate of 3%) \$	431,000	\$ 431,000	\$ 431,000	\$ 431,000	\$ 649,000	\$ 920,000	649,000	\$ 649,000	\$ 476,000	\$ 454,000	
	Alternative Cost Summary	S1	S2	S3	S4	S5	S5A	S5B	S5C	S6	S7	
	Total Capital Costs (Direct & Indirect) \$	5,465,921	\$ 4,839,081			\$ 2,592,634		2,998,491	\$ 3,521,904			
	Total O&M Costs (Present Worth) \$	431,000		\$ 431,000		\$ 649,000		649,000	\$ 649,000	\$ 476,000	\$ 454,000	
	Sales Tax (WA State, 8% of direct capital costs) \$	381,895				\$ 162,760		190,314	\$ 225,978			
	Agency Oversight (Ecology, 3% of capital costs) \$	163,978				\$ 77,779		89,955	\$ 105,657			
	Total Present-Worth Cost \$	6,442,794	\$ 5,752,423	\$ 5,081,367	\$ 5,311,714	\$ 3,482,173	\$ 3,883,955	3,927,760	\$ 4,502,539	\$ 5,453,610	\$ 6,620,003	
				-	-					-		
	Recommended Calculation (Using 30 years for all O&M and LTM)	S1	S2	S3	S4	S5	S5A	S5B	S5C	S6	S7	
	Subtotal Annual O&M and LTM Cost \$	51,708						51,708				
	Total Non-Routine O&M Cost (estimated to be 2% of construction costs \$	1,034						1,034				
	Total Annual O&M and LTM Cost \$	52,742				\$ 52,742		52,742	\$ 52,742			
	Present-Worth Factor (I = 3%, n = 30 years)	19.600	19.600	19.600	19.600	19.600	19.600	19.600	19.600	19.600	19.600	
	Total Present-Worth O&M and LTM Cost \$	1,033,736	\$ 1,033,736	\$ 1,033,736		\$ 1,033,736	\$ 2,460,166	1,033,736	\$ 1,033,736	\$ 1,944,372		Consider projecting the annual cost of O&M and LTM out for 30 years.
	Sales Tax (WA State, 8% of direct capital costs) \$	381,895		\$ 291,671		\$ 162,760		190,314	\$ 225,978			
	Agency Oversight (Ecology, 3% of capital costs) \$	163,978				\$ 77,779		89,955	\$ 105,657	\$ 135,986	\$ 168,144	
	Total Present-Worth Cost \$	7,045,530	\$ 6,355,159	\$ 5,684,104	\$ 5,914,451	\$ 3,866,909	\$ 5,424,120 S	4,312,496	\$ 4,887,276	\$ 6,921,982	\$ 7,655,057	
	Rank (Lowest to Highest Cost)	9	7	5	6	1	4	2	3	8	10	

Notes:

bgs = below ground surface

CAMU = Corrective Action Management Unit

DCC = direct capital costs

DNAPL = dense non-aqueous phase liquid

DRO = diesel range organics

ERH = electrical resistance heating

FT = fee

HDPE = high density polyethylene

IC = institutional control

IN = inch LF = linear feet

LTM = long-term monitoring

NAPL = non-aqueous phase liquid

O&M = operation and maintenance

QA = quality assurance

RCRA = Resource Conservation and Recovery Act SVOCs = semi volatile organic compounds

S1 = Comprehensive Excavation (Baseline Alternative)

S1 = Comprehensive Excavation (Baseline Alternative)

S2 = Comprehensive Excavation Outside Building Footprint S3 = DNAPL Excavation Outside Building Footprint

S4 = DNAPL Excavation Outside Building Footprint, Limited Excavation Inside

S5 = Solidification Outside Building Footprint

S5A = Solidification Outside Building Footprint, DNAPL Recovery under Mechanics Shop

SSB = Solidification Outside and Inside Building Footprint with Relocation of Soil near Railroad Tracks (Preferred Alternative in RI/FS)

S5C = Solidification Outside Building Footprint, ERH Treatment under Mechanics Shop

S6 = DNAPL Treatment by Electrical Resistance Heating (ERH)

S7 = DNAPL Excavation and Electrical Resistance Heating (ERH)



T	ask Nu	umbers	5	Task Description		Line-	ltem	and Total (Costs	by Alterna	ative		
GW1	GW2	GW3	GW4	4 Groundwater Alternatives		GW1		GW2		GW3		5W4	Review Notes, Questions, and Comments
				al Direct)									
		ion Cor											
													Mobilization cost for Alternative GW1 is very high relative to mobilization costs for Alternatives GW2, GW3, and GW4. Provide a breakdown of this cost. (Overall the cost for GW-1 seems
1	1	1	1	Mobilization	\$	1,377,000	\$	60,000	\$	15,000	\$	6,000	high.)
2	2	2	2	Contractor Design and Work Plans	\$	146,300	\$	14,400	\$	8,000	\$	2,700	
			3	Contractor Coordination with Port's maintenance operations							\$	900	Allowances should be provided for Alternatives GW1, GW2, and GW3; and the allowance for GW4 should be substantially greater.
		3		Inconvenience Fee for Disruption of Port's maintenance operations					\$	10,000			Allowances should be provided for Alternatives GW1 and GW2.
3	3			Temporary Relocation of Port Maintenance Operations	\$	30,000	\$	30,000					
4	4			Demo Horizontal Bioventing Wells	\$	7,400	\$	7,400					
5	5			Decommission Groundwater Monitoring & Biovent Wells	\$	41,400	\$	41,400					
6	6	4	4	Specialty Subcontractors (surveyor, utility locates)	\$	20,000	\$	20,000	\$	6,000	\$	2,000	The allowances for Alternatives GW3 and GW4 seem too low.
		5	5	Monitoring Well Installation					\$	50,400	\$	86,400	
		6		BioVenting Well Installation					\$	60,000			
		7		BioVenting Connection Piping Installation					\$	21,000			
		8		BioVenting System Upgrade and Connections					\$	30,000			
		9		BioVenting System Startup Testing and Monitoring					\$	9,000			
		10		BioVenting Well and System Upgrade Reporting					\$	10,000			
	7			Demo Fencing			\$	5,000					
7				Demo Underground Utilities and Fencing	\$	28,000							
	8			Environmental Protection			\$	5,000					Allowances should be provided for Alternative GW1 and GW3.
8				Storm Water Handling and Environmental Protection	\$	10,000							Allowances should be provided for Alternatives GW2 and GW3.
	9			Pre and Post Injection Groundwater Monitoring (8 locations)			\$	104,000					
	10			1st Injection of Modified Fenton's Reagent (100%)			\$	720,000					
	11			2nd Injection of Modified Fenton's Reagent (100%)			\$	720,000					
	12			3rd Injection of Modified Fenton's Reagent (50%) Hot Spot			\$	360,000					
	13			4th Injection of Modified Fenton's Reagent (50%) Hot Spot			\$	360,000					
	14			Chemical Injection Reporting (4 events)			\$	30,000					
	15	11		General Site Restoration Work			\$	10,000	\$	20,000			An allowance should be provided for Alternative GW1.
9				Subsurface Installations by ERH Contactor(214 electrodes, 23 TMPs)	\$	251,200							
10				General Trenching and Site Restoration Work	\$	13,000							Allowances should be provided for Alternative GW2 and GW3.
11				Drilling & Analytical Services for subsurface ERH installations	\$	857,400							Provide a breakdown of this cost estimate to verify the total amount. Clarify if this is just drilling or trenching too.
12				Upgrade Electrical Services to Treatment Pad (4,500 kW)	\$	55,000							
13				ERH Surface installations and startup	\$	798,600							
14				ERH Operations	\$	1,641,300							Provide a breakdown of this cost estimate to verify the total amount.
15				Electrical Connection and Usage charges	\$	1,359,800							Provide a breakdown of this cost estimate to verify the total amount. Provide a breakdown of this cost estimate to verify the total amount.
16				Activated Carbon Usage	\$	7,000							a breakdonn of the cost estanded to very the total amount.
17				Other Misc. ERH Operational Costs	\$	26,700							What does this allowance cover? Why is it separate from the contingency allowance?
18				Chemical Injection of ORC using Push Probe (4 events)	\$	136,000							Explain why the use of ORC technology is included.
19				ORC Advanced Chemical or Equal	\$	88,000							Explain may the use of one technology is included.
20	16			Rebuild Access Road (150 LF)	\$	18,750	¢	18,750					
		12		Resurface Access Road (150 LF)	Ψ	10,100	Ψ	10,130	\$	18,750			

April 2018 Page 1 of 4



	Task N	umbers	s	Task Description		Line-Ite	m and Total	Cost	s by Alternat	tive	Parious Notes Ossetions and Comments
GW1	GW2	GW3	GW4	4 Groundwater Alternatives		GW1	GW2		GW3	GW4	Review Notes, Questions, and Comments
	17			Monitoring Well Installation for Oxidation and MNA		\$	151,200				Can the same wells be used for chemical oxidation and long-term monitoring?
21				Monitoring Well Installation (12 wells to 50 feet)	\$	86,400					
22	18	13	6	Demobilization	\$	50,000 \$	40,000	\$	-,	\$ 4,000	The allowance for demobilization on Alternative GW4 seems too low.
23	19	14	7	Contractor Reporting and Closeout Submittals	\$	32,400 \$	14,400		10,800	\$ 2,700	The allowance for Contractor Report and Closeout on Alternative GW4 seems too low.
				Subtotal	\$	7,081,650 \$	2,711,550	\$	278,950	\$ 104,700	
Contan	ninated	Waste	Dispos	sal and Transportation				_			
1	1	1	1	NAPL Soil (CAMU RCRA Stabilization) Costs	\$	2,550 \$	510		255	\$ 255	
2	2	2	2	Transportation Costs to RCRA Stabilization Facility	\$	550 \$	110	_	55	\$ 55	
3	3	3	3	Liquid NAPL Material Disposal Costs (Incinerator)	\$	50,000 \$	2,000	_	500	\$ 500	
4	4	4	4	Liquid NAPL Transportation Costs to Incinerator	\$	25,000 \$	1,000		250	\$ 250	
	5	5	5	Transportation Charge for Small Loads to Aragonite, Utah		\$	4,000		4,000	\$ 4,000	
5	6	6	6	CAMU-Eligible Material Disposal Costs (Subtitle C Landfill)	\$	4,600 \$	690	_	260	\$ 130	
6	7	7	7	Transportation costs to Subtitle C Editariii	\$	2,200 \$	330	_	110	\$ 55	
	8	8		Transportation Charge for Small Loads to Arlington, Oregon		\$	1,000	_	1,000	_	
7	9	9	8	Non-Hazardous Material Disposal Costs (Subtitle D)	\$	600 \$	390		612		
8	10	10	9	Transportation Costs to Subtitle D Landfill	\$	500 \$	325	\$	492	\$ 22	
_			10	Transportation Charge for Small Loads to Oregon						\$ 1,000	
9	11	11	11	Contaminated Water Treatment and Disposal	\$	100,000 \$	5,000		200	\$ 300	
10	12	12	12	Non-Hazardous Material Disposal Costs (Asphalt Recycling)	\$	240 \$	240	_	240	\$ -	
11	13	13	13	1 7	\$	270 \$	270	+	270	\$ -	
					\$	186,510 \$			♥/= · ·	\$ 6,597	
					\$	7,268,160 \$				\$ 111,297	
				Contractor Contingency (25%)	\$	1,817,040 \$	545,483		57,439	\$ 22,259	
Engino	orina (Costs (C	Canital	Total Contractor Costs al Indirect)	>	9,085,200 \$	3,272,898	>	344,633	\$ 133,556	
1	ering (Sapitai 1	General Coordination, Meetings, and Planning (% DCC)	¢	90,900 \$	65,400	T ¢	34,500	\$ 26,800	
2	2	2	2	Regulatory Review, Coordination, and Meetings (% DCC)	¢	90,900 \$	65,400	_	20,700	\$ 20,800	
	3			Pre-Design Investigation Testing (% DCC)	Ψ	\$0,500 \$	98,100	_	20,700	ψ 33,300	
3	1	3	3	Engineering Design (% DCC)	¢	363,600 \$	163,500	+	75,900	\$ 33,500	
	-	4	4	Coordinate with Port Maintenance Ops	Ą	303,000 \$	103,300	\$	2,700	\$ 2,160	
4	5			Planning for temporary relocation of Port Maintenance Ops	¢	13,500 \$	13,500	+	2,700	Ψ 2,100	
5	6	5	5	Bid & RFI Support	\$	10,800 \$	10,800		8,100	\$ 1,350	
6	7	6	6	Construction Oversight and QA (% DCC)	\$	181,800 \$	98,100		27,600	\$ 13,400	
7	8	7	7	Institutional Controls	\$	5,000 \$	5,000	_		\$ 5,000	
8	9	8	8	Closure Documentation & Reporting	\$	53,000 \$	35,000	_	20,000	\$ 12,000	
				Subtotal Engineering Costs	\$	809,500 \$	554,800			\$ 127,710	
				Engineering Contingency (10 percent)		80,950 \$	55,480		19,450	\$ 12,771	
				Total Engineering Costs		890,450 \$		_		\$ 140,481	
Annua	I 0&M	and L1	ГМ Со	osts		<u>'</u>			•		
<u>Annual</u>	0&M	Cost (W	eekly 1	Temp Monitoring for 6 months)							Cost allowances should be provided for annual O&M beyond 6 months.
1				Project Management and Communication	\$	14,040					
2				Weekly Temperature Readings	\$	18,720					
3				Monthly Reports	\$	18,000					
				Subtotal Annual O&M Cost	\$	50,760					
	-		-	O&M Contingency (25 percent)	\$	12,690					

April 2018 Page 2 of 4



Т	ask Nı	umbers	S	Task Description		Line-It	tem a	nd Total C	Costs	by Alterna	tive		Review Notes, Questions, and Comments
GW1	GW2	GW3	GW4	4 Groundwater Alternatives		GW1	(GW2		GW3	G	SW4	Review Notes, Questions, and Comments
	•			Total Annual O&M Cost	\$	63,450							Cost allowances should be provided for annual O&M beyond 6 months.
Annual	0 M&C	Cost (In:	stitutio	onal Controls) - 30 years of annual O&M									
	1		1	ICs Monitoring			\$	1,000			\$	2,000	Cost allowance for annual monitoring of institutional controls seems low.
				Subtotal Annual O&M Cost			\$	1,000			\$	2,000	
													Based on the risk that natural attenuation will not provide and adequate remedy, and
													groundwater treatment might be necessary, this contingency factor and allowance are much too
				O&M Contingency (25 percent)			\$	250			\$	500	low.
				Total Annual O&M Cost			\$	1,250			\$	2,500	
Annual	D&M C	Cost (Bi	oventi	ing system O&M, IC Monitoring)									
		1		ICs Monitoring					\$	2,000			
		2		Monthly O&M Visits					\$	16,800			
		3		Annual Electricity Consumption (Combined 20 hp motors)					\$	15,000			
		4		Miscellaneous Supplies & Replacement Part					\$	1,000			
		5		Bioventing System O&M Reporting					\$	6,000			
				Subtotal Annual O&M Cost					*	40,800			
				O&M Contingency (25 percent) Total Annual O&M Cost					>	10,200			
Annual	TMC	ost (Ann	aual M	I otal Annual O&M Cost INA monitoring and IC)					Þ	51,000			
Aririuat .	IIM CC	JSL (AΠ	Tuat M	Project Management & Coordination	¢	8,100							
2				Institutional Controls Monitoring	¢	1,000							
3				Mobilization/Demobilization for Sampling (two person crew)	φ (1,800							
4	-			Pickup Truck Rental	<u>\$</u>	260							
5				Lodging and Meals (2 people 3 days each)	\$	780							
6				Sampling Labor and Supplies	\$	4,800							
7				Analytical Testing (DRO)	\$	910							
8				Analytical Testing (SVOCs)	\$	4,030							
9				Analytical Testing (PAHs)	\$	2,600							
10				IDW Disposal	\$	300							
11				Annual Reporting	\$	7,500							
				Subtotal Annual LTM Cost	\$	32,080							
				LTM Contingency (25 percent)	\$	8,020							
				Total Annual LTM Cost (Annual MNA monitoring and IC)		40,100							
Annual	TM Co	ost (Anr	nual G	GW Monitoring, GW2: 2 years during treatment & 6 years after)									The timelines for long-term maintenance (LTM) for Alternatives GW2, GW3, and GW4 should be more than 6 years.
	1	1	1	Project Management & Coordination			\$	8,100	\$	8,100	\$	6,750	,
	2	2	2	Mobilization/Demobilization for Sampling (two person crew)			\$	1,800		1,800	\$	1,800	
	3	3	3	Pickup Truck Rental			\$	340		325	\$	510	
	4	4	4	Lodging and Meals (2 people 3 days each)			\$	1,014			\$	1,690	
	5	5	5	Sampling Labor and Supplies			\$	4,800	\$	7,200	\$	8,000	
	6	6	6	Analytical Testing (DRO)			\$	910	\$	1,610	\$	1,540	
	7	7	7	Analytical Testing (SVOCs)			\$	4,030	\$	7,130	\$	6,820	
	8	8	8	Analytical Testing (PAHs)			\$	2,600	\$	4,600	\$	4,400	
	9		9	Analytical Testing (MNA Specific)			\$	1,950			\$	3,300	
	10	9	10	IDW Disposal			\$	300		600	\$	900	
	11	10	11	Annual Reporting			\$	7,500	\$	8,000	\$	8,000	

April 2018 Page 3 of 4



Task Numbers	Task Description		Line-l	tem	and Total C	Cost	s by Alterna	tive		Review Notes, Questions, and Comments
GW1 GW2 GW3 GW4	Groundwater Alternatives		GW1		GW2		GW3		GW4	Review Notes, Questions, and Comments
	Subtotal Annual LTM Cost			\$	33,344	\$	41,055	\$	43,710	
	LTM Contingency (25 percent)			\$	8,336	\$	10,264	\$	10,928	
	Total Annual LTM Cost (Annual GW Monitoring)			\$	41,680	\$	51,319	\$	54,638	
	Total Annual O&M and LTM Cost	\$	103,550	\$	42,930	\$	102,319	\$	57,138	Verify the Total O&M and LTM Cost for Alternative GW1.
	Total O&M and LTM Cost (30 years until completion)	\$	223,850	\$	343,440	\$	1,840,000	\$	1,710,000	Verify the calcuations that yielded these total amounts.
	Present-Worth O&M Cost (with presumed interest rate of 3%)	\$	210,658	\$	301,355	\$	1,404,110	\$	1,119,920	Verify the calcuations that yielded these total amounts.
	Alternative Cost Summary		GW1		GW2		GW3		GW4	
	Total Capital Costs (Direct & Indirect)	\$	9,975,650	\$	3,883,178	\$	558,583	\$	274,037	
	Total O&M Costs (Present Worth)	\$	211,000	\$	301,000	\$	1,404,000	\$	1,120,000	
	Sales Tax (Washington State, 8% of direct capital costs)	\$	726,816	\$	261,832	\$	27,571	\$	10,685	
	Agency Oversight (Ecology, 3% of capital costs)	\$	299,270	\$	116,495	\$	16,757	\$	8,221	
	Total Present-Worth Cost	\$ 1	11,212,736	\$	4,562,505	\$	2,006,911	\$	1,412,943	
	Recommended Calculation (Using 30 years for all O&M and LTM)		GW1		GW2		GW3		GW4	
	Total Capital Costs (Direct & Indirect)	\$	9,975,650	\$	3,883,178	\$	558,583	\$	274,037	
	Total Annual O&M and LTM Cost (30 years until completion)	\$	103,550	\$	42,930	\$	102,319	\$	57,138	
	Present-Worth Factor (discount rate = 3% , $n = 30$ years)		19.600		19.600		19.600		19.600	
										Long-term costs for Alternatives GW2, GW3, and GW4 have been projected out for 30
	Total Present-Worth O&M and LTM Cost	\$	210,658	\$	841,428	\$	2,005,448	\$	1,119,895	years.Cost for Alternative GW1 are for 2 years.
	Sales Tax (Washington State, 8% of direct capital costs)	\$	726,816	\$	261,832	\$	27,571	\$	10,685	
	Agency Oversight (Ecology, 3% of capital costs)	\$	299,270	\$	116,495	\$	16,757	\$	8,221	
	Total Present-Worth Cost	\$ 1	11,212,394	\$	5,102,933	\$	2,608,358	\$	1,412,838	

Notes:

CAMU = Corrective Action Management Unit

DCC = direct capital costs

DRO = diesel range organics

ERH = electrical resistance heating

GW = groundwater

IDW = investigation-derived waste

kW = kilowatts

LF = linear feet

LTM = long-term monitoring

MNA = monitored natural attenuation

NAPL = non-aqueous phase liquid

O&M = operation and maintenance

ORC = oxygen releasing compound

PAH = polycyclic aromatic hydrocarbon

QA = quality assurance

RFI = request for information

RCRA = Resource Conservation and Recovery Act

SVOCs = semi volatile organic compounds

GW1 = Electrical Resistance Heating and Enhanced Biodegradation (Baseline Alternative)

GW2 = Chemical Oxidation and Monitored Natural Attenuation

GW3 = Active Biosparging

GW4 = Monitored Natural Attenuation (International Paper preferred alternative)

April 2018 Page 4 of 4



Attachment B. Comparison of Remedial Cost Estimates between Alternative S5B and the Port of Longview's Preferred Alternative

Internation Paper Site, Maintenance Facility Area (MFA) Remediation		-	r - Alternative S5 Disposal and Solic	B (Excavation with dification)	Port of Lo	_	lternative (Excava sal and Solidifica		Cost			per - Alternative Disposal and S	S5B (Excavation olidification)		_	lternative (Exca	evation with Off- cation)	Cout Diff		
Estimator (Date):		AEC	COM (July 21, 20	17)		Geoen	gineers (March 6,	2018)	Difference			Ridolfi				Ridolfi		Cost Difference (RGEO - RS5B)	Notes, Questions, and Comments	
Task Descripton	Quantity	Unit	Unit Cost	Total Cost	Quantity	Unit	Unit Cost	Total Cost	(GEO - S5B)	Quantity	Unit	Unit Cost	Total Cost	Quantity	Unit	Unit Cost	Total Cost	(RGEO - RSSB)		
								Co	ontractor Cos	ts (Capital	Direct)									
																			Offsite disposal of Corrective Action Management Unit (CAMU) waste (WAC 1	
Remedial Action Construction Mobilization / Demobilization	1 1	LS	\$ 225,000	¢ 22E.000	1	"859 LS	% Disposal as CAM \$ 152,000 \$		¢ (72,000) 1	Lic	\$ 152,000 \$	152.000	1		Disposal as CAM \$ 152,000 \$		ø	303-646920)	
Mobilization / Demobilization	- 1	L3	\$ 223,000	\$ 225,000	'	L3	\$ 132,000 \$	152,000	\$ (73,000)	' '	LS	\$ 132,000 \$	152,000	'	LS	\$ 152,000 \$	152,000	-	Based on Geoengineers Quote since cheaper vender. Both estimates seem low. For the Port of Longview (POL) alternative, more the	
																			one contractor work plan would be required, since more than one remediation	
2 Contractor Work Plans	240	HR	\$ 90 5	\$ 21.600	240	HR	\$ 90 \$	21.600	¢ -	240	HR	\$ 90 \$	21.600	240	HR	\$ 90 \$	21,600	\$ -	technology would be used.	
Solidification Pilot Testing	350	CY		, , , , , , , , , , , , , , , , , , , ,	350	CY	\$ 300 \$	105,000	\$ -	350	CY	\$ 300 \$	105,000		CY	\$ 300 \$	105,000	\$ -	teennotogy would be used.	
Temporary relocation of Port Maintenance Operations	1	LS	\$ 30,000	\$ 30,000	1	LS	\$ 30,000 \$	30,000	\$ -	1	LS	\$ 30,000 \$	30,000	1	LS	\$ 30,000 \$	30,000	\$ -		
Demo Horizontal Bioventing Wells and Connection Piping	800	LF	\$ 37 5		800	LF	\$ 37 \$	29,600	\$ -	800	LF	\$ 37 \$			LF	\$ 37 \$		\$ -		
Decommission Groundwater Monitoring & Bioventing Wells	40	EA			40	EA	\$ 920 \$	36,800	\$ -	40	EA	\$ 920 \$			EA	\$ 920 \$		\$ -		
Specialty Subcontractors (surveyor, utility locates)	1	LS LS	\$ 8,000 S \$ 28,000 S	\$ 8,000 \$ 28,000	1	LS LS	\$ 8,000 \$ \$ 28,000 \$	8,000 . 28,000 .	\$ - ¢	1	LS	\$ 8,000 \$ \$ 28,000 \$	8,000 28,000		LS LS	\$ 8,000 \$ \$ 28,000 \$	8,000 28,000	\$ -		
Demo Underground Utilities and Fencing Demo Retaining Wall	1 220	LS	\$ 28,000		220	LS LF	\$ 28,000 \$	16,500	\$ -	220	LS LF	\$ 28,000 \$			LS	\$ 28,000 \$		\$ -		
Demo Port's Maintenance Building (east corner) with Lower Roof Height	2,500	SF	\$ 25 5	\$ 62,500	2,500	SF	\$ 25 \$	62,500	\$ -	2,500	SF	\$ 25 \$	62,500		SF	\$ 25 \$		\$ -		
<u> </u>													* * * * * * * * * * * * * * * * * * * *			j i	• •		Removed all cost associated with freeze wall. Assume both IP and POL use c	
Install Freeze Wall Shoring for Building (200 LF)																			slopes for shoring.	
Install Sheet Pile Wall Shoring along building (200 LF)					2,400	SF	\$ 45 \$	108,000	\$ 108,000	2,400	SF	\$ 45 \$	108,000	2,400	SF	\$ 45 \$	108,000	\$ -	Use Sheet pile shoring against building and not freeze wall.	
									-										Removed all cost associated with freeze wall. Assume both IP and POL use co	
Install Freeze Wall Shoring for Excavation Perimeter (720 LF)	<u> </u>	<u> </u>												<u> </u>				\$ -	slopes for shoring.	
Install Sheet Pile Wall Shoring along slurry wall - 100 LF, 16 ft deep					1,200	SF	\$ 45 \$	54,000	\$ 54,000		SF	\$ 45 \$	- 1		SF	\$ 45 \$		\$ -	Use Sheet pile shoring against slurry wall and not freeze wall.	
Remove Surface Asphalt in Storage Yard and Road	32,600	SF	\$ 0.88	\$ 28,688	37,188	SF	\$ 0.88 \$	32,725	\$ 4,037	37,188	SF	\$ 0.88 \$	32,725		SF	\$ 0.88 \$	32,725	\$ -	Incresed asphalt removal for cut slope.	
Remove 42-inch HDPE Culvert and Replace	125	LF	\$ 150 5	\$ 18,750	125	LF	\$ 150 \$	18,750	\$ -	125	LF	\$ 150 \$	18,750	125	LF	\$ 150 \$	18,750	\$ -	Demoused all cost associated with franza wall Assume both ID and DOL use	
Franza Wall Sharing for Everystian Perimeter	9,450	SE	\$ 31 5	\$ 292,950					\$ (292,950)	,								ø	Removed all cost associated with freeze wall. Assume both IP and POL use c	
Freeze Wall Shoring for Excavation Perimeter Excavation and Stockpiling of Overburden (0 to 3 FT bgs)	3,900	CY	\$ 27 5		3,900	CY	\$ 27 \$	105,300	\$ (292,950) \$ -	3,900	CY	\$ 27 \$	105,300	3,900	CY	\$ 27 \$	105,300	\$ -	slopes for shoring.	
Excavate Cut Slope at 45 Degrees for Shoring	3,300	<u> </u>	Ψ 2,	103,300	596	CY	\$ 27 \$	16,092	4	596	CY	\$ 27 \$	16,092		CY	\$ 27 \$		\$ -		
Excavation and Stockpiling of Contaminated Soil					3,604	CY	\$ 27 \$	97,300	\$ 97,300				·	3,604	CY	\$ 27 \$		\$ 97,308		
Loading of Contaminated Soil					5,406	TN	\$ 6\$	32,433	\$ 32,433					5,406	TN	\$ 6\$		\$ 32,436		
Import of clean fill to the site		1.0	* 11.000	t 11.000	2,039	CY	\$ 20 \$	40,785	\$ 40,785		1.0	£ 11.000 £	11.000	2,039	CY	\$ 20 \$		\$ 40,780		
5 Stormwater Handling and Environmental Protection 5 Excavate Soil from 3 to 8 feet bgs within 80 feet of Railroad Tracks	1 1,650	LS CY	\$ 11,000 S	\$ 11,000 \$ 23,100	'	LS	\$ 11,000 \$	11,000	\$ - \$ (23,100)	1,650	LS CY	\$ 11,000 \$ \$ 14 \$	11,000 23,100	'	LS	\$ 11,000 \$	11,000	\$ (23,100)	ni	
Relocate and Backfill Soil from Near the Railroad Tracks	1,650	CY	\$ 9 5	•	1				\$ (23,100)	1,650	CY	\$ 9 \$						\$ (14,850)))	
Solidification Materials (8% NewCem Slag Cement)	890	TN	\$ 130 5	•	469	TN	\$ 130 \$	61,013	\$ (54,739)	890	TN	\$ 130 \$		469	TN	\$ 130 \$	60,970			
9 Solidification Materials (2% Bentonite Grout - Hydrogel 90)	223	TN	\$ 230 5		117	TN	\$ 230 \$	26,987	\$ (24,211)	223	TN	\$ 230 \$	51,198	117	TN	\$ 230 \$	26,910	\$ (24,288,)	
0 Solidification Materials (0.5% Caustic Soda)	56	TN	\$ 1,275	\$ 70,954	29	TN	\$ 1,275 \$	37,400	\$ (33,554)	56	TN	\$ 1,275 \$			TN	\$ 1,275 \$	36,975	\$ (33,979))	
Solidification Labor and Equipment Outside Building Footrprint	6,950	CY			3,689	CY	\$ 30 \$ \$ 30 \$	110,666	\$ (306,334)		CY	\$ 30 \$ \$ 30 \$		-,	CY	\$ 30 \$		\$ (97,830) \$ (7,440))	
Geotextile Fabric Marker Layer Over Solidified Soil	470 2,867	CY SY			222 2,933	CY SY	\$ 1.75 \$	6,667 . 5,133 .	\$ (21,533) \$ 116	2,933	SY	\$ 1.75 \$			CY SY	\$ 30 \$ \$ 1.75 \$	6,660 5,133	\$ (7,440,	7	
Import of Clean Backfill for Transition Grades	1,700	CY			2,555	J1	ψ 1.73 ψ	3,133	\$ (34,000)	1,700	CY	\$ 20 \$		2,555	31	1.75	3,133	\$ (34,000)))	
Additional Import of Backfill Material to Replace Relocated Soil	1,600	CY							\$ (32,000)	1,600	CY	\$ 20 \$						\$ (32,000,)	
Backfill and Compaction of Overburden Soil Stockpiles on Site	3,900	CY							\$ (42,900)	3,900	CY	\$ 11 \$						\$ (42,900))	
Backfill and Compaction of Excavation	3,300	CY			8,100	CY	\$ 9 \$	72,900	\$ 43,200	3,896	CY	\$ 9 \$			CY	\$ 9 \$		\$ 37,836		
Asphalt Paving Rebuild Access Road (150 LF)	32,600	SF SF	\$ 4 5		37,188	SF SF	\$ 4 \$		\$ 18,352 \$	37,188	SF SF	\$ 4 \$ \$ 6 \$		37,188 3,750	SF	\$ 4 \$ \$ 6 \$		\$ -	Increased asphalt for cut slope.	
Rebuild Access Road (150 LF) Rebuild Retaining Wall	3,750	31	\$ 6 5	φ ∠∠,500	3,750 160	LF		24,000	\$ - \$ 24,000	3,750	31	φ 0 \$	22,500	3,750 160	SF LF			•		
Reconstruct Portion of Maintenance Building	2,500	SF	\$ 50 5	\$ 125,000	2,500	SF	\$ 50 \$	125,000	\$ -	2,500	SF	\$ 50 \$	125,000		SF	\$ 50 \$				
Replace Connection Piping for Bioventing System	600	LF	\$ 40 5	\$ 24,000		LF	\$ 40 \$	24,000	\$ -	600	LF	\$ 40 \$	24,000		LF	\$ 40 \$	24,000	•		
2 Monitoring Well Installation	10	EA			10	EA		54,000	\$ -	10	EA									
Contractor Reporting and Closeout Submittals	200	HR	\$ 90		290	HR	\$ 90 \$				HR	\$ 90 \$			HR	\$ 90 \$			Used POL level of effort.	
Subtotal - Remedial Action Construction Contaminated Waste Disposal and Transportation				\$ 2,258,300			\$	1,751,500	\$ (506,800)			\$	1,883,800			\$	1,751,000	\$ (132,800))	
Contaminated Waste Disposal and Transportation NAPL Soil (CAMU RCRA Stabilization) Costs	0	TN	\$ 255 5	\$ -	0	TN	\$ 255 \$	-	\$ -	0	TN	\$ 255 \$	_	0	TN	\$ 255 \$	-	\$ -		
Transportation Costs to RCRA Stabilization Facility	0	TN			0	TN			\$ -	0	TN			0	TN					
Liquid NAPL Material Disposal Costs (Incinerator)	0	GAL	\$ 10 5	\$ -	0	GAL	\$ 10 \$	-	\$ -	0	GAL	\$ 10 \$		0	GAL	\$ 10 \$	-	\$ -		
Liquid NAPL Transportation Costs to Incinerator	0	DRUM			0	DRUM			\$ -	0	DRUM			0	DRUM			\$ -		
CAMU-Eligible Material Disposal Costs (Subtitle C Landfill)	0	TN			4,595	TN		528,393	\$ 528,393		TN	\$ 115 \$		4,595	TN				Assume 85% of excavated soil disposed of as CAMU-eligible waste	
Transportation Costs to Subtitle C Landfill Non-Hazardous Material Disposal Costs (Subtitle D)	0	TN TN			4,595 811	TN TN		252,710 24,325	\$ 252,710 \$ 24,325		TN	\$ 55 \$ \$ 30 \$		4,595 811	TN TN				Assume 15% of excavated soil disposed of using contained-in determination	
Transportation Costs to Subtitle D Landfill	0	TN			811	TN		20,271	\$ 24,323		TN	\$ 25 \$		811	TN	\$ 25 \$			Assume 1576 of excuvated soft disposed of using contained-in determination	
Contaminated water treatment and disposal	50,000	GAL			50,000	GAL			\$ -	50,000	GAL				GAL					
Non-Hazardous Material Disposal Costs (Asphalt Recycling)	845	TN	\$ 8 5	\$ 6,761	845	TN	\$ 8\$	6,760	\$ (1)	845	TN	\$ 8\$	6,761	845	TN	\$ 8\$	6,761	\$ -		
Transportation Costs to Asphalt Recycler	845	TN	\$ 9 5		845	TN	\$ 9 \$		\$ (2)	0.5	TN	\$ 9 \$		845	TN	\$ 9 \$				
Subtotal - Contaminated Waste Disposal and Transportation				\$ 24,400			\$		\$ 825,700			\$	24,400			\$	850,100			
Subtotal - Contractor Costs Contractor Contingency (percent)		0/.	\$ 2,282,700	\$ 2,282,700 \$ 456,500	20	0/.	\$ 2,601,600 \$	2,601,600 520,300			0/.	\$ 1,908,200 \$		20	0/.	\$ 2,601,100 \$				
TOTAL CONTRACTOR COSTS		7/0	ع د,۷۵۷,/۱۷	\$ 456,500 \$ 2,739,200		76	φ ∠,ου1,ουυ \$	3,121,900	•		70	\$ 1,500,200 \$	2,289,800		76	\$ 2,001,100 \$	3,121,300			

April 2018 Page 1 of 2



nternation Paper Site, Maintenance Facility Area (MFA) Remediation	Internat		r - Alternative S Disposal and Sol	5B (Excavation with idification)	Port of Long	_	ternative (Excava al and Solidificat		Cost				ive S5B (Excavation I Solidification)	Port o	_	Alternative (Exc posal and Solidif	avation with Off- ication)	Cost Difference	
Estimator (Date)		AEC	COM (July 21, 2	017)		Geoengi	ineers (March 6,	2018)	Difference			Ridolfi				Ridolfi			Notes, Questions, and Comments
,						Ī		-	(GEO - S5B))								(RGEO - RS5B)	
Task Descripton	Quantity	Unit	Unit Cost	Total Cost	Quantity	Unit	Unit Cost	Total Cost		Quantit	ty Unit	Unit Cost	Total Cost	Quant	ity Unit	Unit Cost	Total Cost		
					El	NGINEER	ING COSTS (CAP	ITAL INDIRECT)											
General Coordination, Meetings, and Planning (% DCC)	2	%	\$ 2,739,000	\$ 54,780		%	\$ 3,121,900 \$	62,438	\$ 7,65	8 2	%	\$ 2,739,000	\$ 54,78	30 2	%	\$ 3,121,300	\$ 62,426	\$ 7,646	
Regulatory Review, Coordination, and Meetings (% DCC)	2	%	\$ 2,739,000	\$ 54,780) 2	%	\$ 3,121,900 \$	62,438	\$ 7,65	8 2	%	\$ 2,739,000	\$ 54,78	30 2	%	\$ 3,121,300	\$ 62,426	\$ 7,646	
Pilot Test Sampling, CBR, and Reporting	1	LS	\$ 75,000	\$ 75,000) 1	LS	\$ 75,000 \$	75,000	\$ -	1	LS	\$ 75,000	\$ 75,00	00 1	LS	\$ 75,000 5	\$ 75,000	\$ -	
Engineering Design (% DCC)	7	%	\$ 2,739,000	\$ 191,730	5	%	\$ 3,121,900 \$	156,095	\$ (35,63	5) 7	%	\$ 2,739,000	\$ 191,73	30 7	%	\$ 3,121,300	\$ 218,491	\$ 26,761	Used IP estimate of 7%.
Planning for temporary relocation of Port maintenance ops	100	HR	\$ 135	\$ 13,500	100	HR	\$ 135 \$	13,500	\$ -	100	HR	\$ 135	\$ 13,50	00 100	HR	\$ 135	\$ 13,500	\$ -	
Bid and RFI Support	60	HR	\$ 135			HR	\$ 135 \$	8,100	\$ -	60	HR	\$ 135			HR	\$ 135 5			
Construction Oversight and QA (% DCC)	5	%	\$ 2,739,000	\$ 136,950	5	%	\$ 3,121,900 \$	156,095	\$ 19,14	5 5	%	\$ 2,739,000	\$ 136,95	50 5	%	\$ 3,121,300	\$ 156,065		
Confirmational Sample Collection and Reporting	1	LS	\$ 33,000			LS	\$ 33,000 \$	33,000	\$ -	1	LS				LS	\$ 33,000 5	\$ 33,000		
Zone 1 Soil Characterization	1	LS	\$ 25,000			LS	\$ 25,000 \$	25,000		1		\$ 25,000			LS	\$ 25,000 5			
Closure Documentation & Reporting	1	LS	\$ 53,000			LS	\$ 53,000 \$	53,000		1	LS	\$ 53,000			LS	\$ 53,000 5	\$ 53,000		
Subtotal - Engineering Costs				\$ 645,800			\$	644,700					\$ 645,80						
Engineering Contingency (percent)	10	%	\$ 645,800	\$ 64,600	10	%	\$ 644,700 \$	64,500	\$ (10	<i>0</i>) 10	%	\$ 645,800	\$ 64,60	10	%	\$ 707,000	\$ 70,700	\$ 6,100	
																			Difference between IP and POL alternatives. Engineering Costs for the
																			Alternative are probably biased high, since the same percentages were use
																			both alternatives. The engineering costs associated with soil removal and
																			for the POL Alternative should be less than the engineering costs associate
TOTAL ENGINEERING COSTS				\$ 710,400			\$	709,200	\$ (1,20)	0)			\$ 710,40	00			\$ 777,700	\$ 67,300	soil solidification for the International Paper Alternative.
					ANNUA	L O&M A	ND LONG TERM	MONITORING CO	STS										
Annual O&M Cost (Institutional Controls Maintenance; Asphalt Inspec	ion and Re	epair) - 30	years of annua	l O&M															
Project Management and Coordination	16	HR	\$ 135	\$ 2,160	16	HR	\$ 135 \$	2,160	\$ -	16	HR	\$ 135	\$ 2,16	50 16	HR	\$ 135 5	\$ 2,160	\$ -	
Annual Inspection and Reporting	32	HR	\$ 110	\$ 3,520	32	HR	\$ 110 \$	3,520	\$ -	32	HR	\$ 110	\$ 3,52	20 32	HR	\$ 110 !	\$ 3,520	\$ -	
Update Institutional Controls (ICs) Plan (once every 5 years)	1	LS	\$ 750	\$ 750) 1	LS	\$ 750 \$	750	\$ -	1	LS	\$ 750	\$ 75	50 1	LS	\$ 750	\$ 750	\$ -	
Prorated Cost for Asphalt Repairs	1	LS	\$ 8,606	\$ 8,606	5 1	LS	\$ 8,606 \$	8,606	\$ -	1	LS	\$ 8,606	\$ 8,60	06 1	LS	\$ 8,606	\$ 8,606	\$ -	
Subtotal - Annual O&M Cos				\$ 15,040)		\$	15,040	\$ -				\$ 15,04	10			\$ 15,040	\$ -	
O&M Contingency	25	%	\$ 15,040			%	\$ 15,040 \$	3,760		25	%	\$ 15,040			%	\$ 15,040			
Total Annual O&M Cost				\$ 18,800)		\$	18,800	\$ -				\$ 18,80	00			\$ 18,800	\$ -	
Annual LTM Cost (Monitoring of leachate and physical performance of	solidified																		Is 10 years sufficient for long-term monitoring of solidified soil?
Project Management and Coordination	24	HR	\$ 135			HR	\$ 135 \$	3,240		24	HR					\$ 135			
Mob/Demob for Sampling (semi-annual)	2	EA	\$ 1,800			EA	\$ 1,800 \$	3,600		2	EA	\$ 1,800			EA	\$ 1,800			
Pickup Truck Rental	6	DAY	\$ 65			DAY	\$ 65 \$	390		6	DAY	\$ 65		90 6	DAY	\$ 65			
Sampling Labor and Supplies	20		\$ 400			EA	\$ 400 \$	8,000		20	EA	\$ 400				\$ 400			
Analytical Testing (DRO and SVOCs)	20		\$ 380			EA	\$ 380 \$	7,600		20	EA					\$ 380			
Annual Reporting	1	LS	\$ 3,500			LS	\$ 3,500 \$	3,500		1	LS	\$ 3,500			LS	\$ 3,500			
Subtotal - Annual LTM Cost				\$ 26,330			\$	26,330					\$ 26,33						
LTM Contingency (percent)	25	%	\$ 26,330	\$ 6,580	25	%	\$ 26,330 \$	6,580	\$ -	25	%	\$ 26,330	\$ 6,58	25	%	\$ 26,330	\$ 6,580	\$ -	
																			The estimate for annual LTM costs for both alternatives is \$32,913 per year
																			Consider projecting this annual cost out for 30 years, along with the open
																			maintenance (O&M) cost, so that the allowance for all long-term costs is
Total Annual LTM Cost				\$ 32,900)		\$	32,900	\$ -				\$ 32,90	00			\$ 32,900	\$ -	a 30-year timeline.
Total Annual O&M and LTM Cost				\$ 51,700)		\$	51,700	\$ -				\$ 51,70	00			\$ 51,700	\$ -	
Total Non-Routine O&M Cost	2	%	\$ 2,258,300		2	%	\$ 1,751,500 \$		\$ -	2	%	\$ 1,883,800	•	2	%	\$ 1,751,000			Why is the allowance for non-routine O&M zero?
Total O&M and LTM Cost (over 30 years)				\$ 893,000)		\$	893,000	\$ -				\$ 893,00	00			\$ 893,000	\$ -	
																		\$ -	
O&M Present Value (PV) = \$18,795 (P/A 3%, 30 yr) =						PWF		368,500				\$ 18,800			0 PWF				PWF = Present Worth Factor
LTM Present Value (PV) = \$32,913 (P/A 3%, 10 yr) =		PWF	\$ 32,900			PWF	\$ 32,900 \$	280,600			PWF	\$ 32,900			U PWF	\$ 32,900			
NET PRESENT VALUE OF O&M and LTM COSTS				\$ 649,100	'		\$		\$ -				\$ 649,10	10			\$ 649,100	\$ -	
									ALTERNATIV	E COST SU	MMARY								
TOTAL CAPITAL COSTS (DIRECT & INDIRECT)				\$ 3,449,600			\$	3,831,100		0			\$ 3,000,20				\$ 3,899,000		
TOTAL O&M and LTM COSTS (PRESENT WORTH)				\$ 649,100			\$	649,100					\$ 649,10				\$ 649,100		
SALES TAX (Washington State)	8	%	\$ 2,739,200	\$ 219,100	8	%	\$ 3,121,900 \$	249,800	\$ 30,70	0 8	%	\$ 2,289,800	\$ 183,20	8	%	\$ 3,121,300	\$ 249,700	\$ 66,500	
																			Is this allowance different than Task 2 (Regulatory Review, Coordination,
AGENCY OVERSIGHT (Ecology)	3	%	\$ 3,449,600	\$ 103,500	3	%	\$ 3,831,100 \$	114,900	\$ 11,40	0 3	%	\$ 3,000,200	\$ 90,00	10 3	%	\$ 3,899,000	\$ 117,000	\$ 27,000	Meetings) of Engineering Costs?
						-	· / / T			_									
				\$ 4.421.200			¢	4 844 900	\$ 122.60	n			\$ 3022 EU	00			\$ <u>4</u> 01/200	\$ 002.500	Total Difference between IP and POL alternatives
TOTAL PRESENT-WORTH ALTERNATIVE COST UNIT COST (\$/CY:				\$ 4,421,300 \$ 597	_		<u> </u>		\$ 423,600 \$ 5	_			\$ 3,922,50 \$ 53				\$ 4,914,800 \$ 664		Total Difference between IP and POL alternatives Based on a total treatment volume of 7,404 cubic yards

Notes:

%DCC = percent Direct Capital Costs
CAMU = Corrective Action Management Unit
CY = cubic yard
DRO = diesel-range organics
DRUM = 55-gallon drum
EA = each
FT = feet
GAL = gallon
HR = hour
IP = International Paper
LF = linear feet
LTM = long term monitoring

LTM = long term monitoring LS = lump sum

MFA = Maintenance Facility Area O&M = operation and maintenance

P/A = uniform series present worth factor POL = Port of Longview

POL = Port of Longview
PV = present value
PWF = present worth factor
SF = square feet
SVOCs = semi-volatile organic compounds
SY = square yard
TN = ton

April 2018 Page 2 of 2 501D4_Attachment B Cost Estimate Comparison_180410