

Givens/References.

- 1) Stability study dated 4/26/95 by MJG. (Rete)
- 2) Boring log for MW-23, MW-24, & MW-25 - borings on the proposed wall alignment
- 3) Hydrographs for MW-23, MW-24 & MW-25 taken from BOO report. Shows gw readings from 10/90 to 10/00

Procedure:

Reference 1 - one conclusion is that the Rankine analysis for stability of the levee is more conservative than Coulomb procedure - i.e., Rankine results in a higher force than Coulomb. Therefore, the Rankine procedure will be utilized to evaluate parameter changes.

- A) Look @ water table level used in Ref. 1 calculation. The earlier calculation utilized a groundwater table 4.5 feet below the ground surface. The attached hydrographs indicate that a conservative gw would be 6' below the ground surface. This is the highest August level in the last 10 years.

⇒ Change A = lower the groundwater level to 6 ft bgs.

B) Soil Properties

Review boring log for MW-23, MW-24, MW-25 & MW-42. There are no legends available for the exact sample type, but I think that

□ = Denver Moore and ■ = SPT.

Blow Counts are □ = 50/3, 29, 50/3, 50/3, 50/5", 16

■ = 32, 15, 2

MW-42 was completed using Air Rotary ⇒ Blow counts could be suspect. Inquire of drilling method for Geotechnical borings

⇒ Use SPT $N = 30$ as a conservative value. Using Peck, Hanson's Theorem Fig. 19.5, $\phi = 36^\circ$ for $N = 30$. This is between medium dense & dense.

CALCULATION.


For a backslope of 26° for levee and $\phi = 36^\circ$, $K_A = 0.1366$

$$\gamma_s = 130 \text{ pcf}$$

$$\delta_{\text{unit}} = 125 \text{ pcf}$$

$$\delta_w = 62.4$$

$$\delta_b = 130 - 62.4 = 67.6 \text{ pcf}$$



$$P_{\text{total}} = 2.53 + 0.83 + 100 + 2.47 = 6.83 \text{ k/ft}$$

This value is reduced from reference 1 calculations due to a lowering of the groundwater table to a reasonable level and increasing the soil ϕ levee strength to 36° . It is reasonable to assume that adjusting these two parameters to realistic values will also lower the Coulomb trial wedge total force to below 6183 k. \Rightarrow the more conservative analysis remains the Rankine active calculation.

Required slurry density

For a slurry level @ 1' bgs \Rightarrow 14" from bottom of trench.

$$\gamma_s \left(\frac{H_s^2}{2} \right) = 6830 \text{ lbs.}$$

$$\gamma_s = 6830 \left(\frac{2}{14^2} \right)$$

$\gamma_s = 69.7$ pct. for a stable condition.

For a slurry level @ 14.5', $\gamma_s = 65$ pct

SPECIFICATION REQUIREMENTS

* Suggest that a slurry density of 73 pct is required and a max slurry depth of 1' bgs.

- See attached addendum verbage

FAX TRANSMITTAL SHEET




9 Pond Lane
Concord, MA 01742
(508) 371-1422
FAX (508) 369-9279

worst case -
digger working
along side
trench


Date	5/1/95
Charge No/Project No	3-1161-510
Send to FAX No	
Company Name	RETEC
Attention	ALCAT
From	MIKE G
Number of Pages to Follow	8
Comments/Special Instructions: I CAN FAX SOME BACK UP ON SLURRY INFILTRATING THE LEVEL, IF NEEDED - - if slurry is that permeables then fence would do it work on	

If you have any problems receiving this FAX, please call (508) 371-1422 as soon as possible.
Have a Pleasant Day!

Concord, MA • Harrisburg, PA • Fort Collins, CO • Austin, TX • Billings, MT • Chapel Hill, NC • St. Paul, MN • Seattle, WA
Mandeville, LA • Tucson, AZ • Ithaca, NY • Indianapolis, IN • Los Angeles, CA • Philadelphia, PA • Kansas, KS



Project No. 3-1161-510 Page 1 of 8
 Client B.N. Date 4/26/95
 Site SKYKOMISH RIVER By MLG
 Subject SLURRY TRENCH STABILITY App.





Project No.	<u>3-1167-510</u>	Page	<u>2</u> of <u>8</u>
Client	<u>B.N.</u>	Date	<u>4/26/95</u>
Site	<u>SKYKOMISH RIVER</u>	By	<u>MJG</u>
Subject	<u>SLURRY TRENCH</u>	App.	

SOIL PROPERTIES

GRAIN SIZE - SAND, SOME SILT, TRACE CLAY, TRACE GRAVEL
(SAY 6M)

$N \approx 40 - 100$ (REFUSAL) (FROM NEARBY BORINGS ALONG RIVER DR)

$\phi \approx 35^\circ$ (CONSERVATIVE ESTIMATE FROM BOWEN TABLE 3.4)

$$\gamma_{T(bat)} = 130 \text{ PLF}$$

$$\gamma_{T(wat)} = 110 \text{ PLF}$$

$$\gamma_{sat} = 62.4 \text{ PLF}$$

DESIGN ASSUMPTIONS

1. 2 MODES OF FAILURE ARE EVALUATED

- 1.) TRENCH IS LOCATED AT TOE OF LEVEE & FAILURE OCCURS DUE TO WEIGHT OF LEVEE. CONSIDER BOTH COULOMB TRIAL WEDGE AND RANKINE ACTIVE WEDGE
- 2.) TRENCH FAILURE DUE TO 40^k EQUIP LOAD OR 100 K/LF LINE LOAD DUE TO HOUSE. USE RANKINE ACTIVE WEDGE

USE SEASONAL HIGH GW



Project No. 3-1161-510
 Client B.N.
 Site SKYKOMISH RIVER
 Subject SLURRY TRENCH STABILITY

Page 4 of 8
 Date 4/20/95
 By M.K.
 App. _____

$$\text{TRAIL ①: } \theta = 45^\circ + \frac{35^\circ}{2} = 62.5^\circ$$

$$\sum F_u = P_A - N \sin \theta + T \cos \theta$$

$$W = \left[\frac{1}{2} (10.5)(5.5)(130) + 53 \text{ Ft}^2 (110) \right] = 10 \text{ kips}$$

$$N = W \cos \theta = 10^k \cos 62.5 = 4.6$$

$$T = N \tan \phi = 4.6^k \tan 35^\circ = 3.2^k$$

$$P_A = 4.6^k \sin 62.5 - 3.2^k \cos 62.5 + \frac{10.5}{2} \left(\frac{62.4}{1000} \right) = \underline{\underline{6.04 \text{ kips}}}$$

$\sim 3.44^k$ (pore pressure)

$$\text{TRAIL ②: } \theta = 60^\circ$$

$$W = \left[\frac{1}{2} (10.5)(6)(130) + 61 \text{ Ft}^2 (110) \right] = 10.8^k \text{ kips}$$

$$N = 10.8^k \cos 60 = 5.4$$

$$T = 5.4 \tan 35^\circ = 3.78$$

$$P_A = 5.4 \sin 60 - 3.78 \cos 60 + 3.44^k = \underline{\underline{6.22 \text{ kips}}}$$

$$\text{TRAIL ③: } \theta = 57.5^\circ$$

$$W = \left[\frac{1}{2} (10.5)(6.75)(130) + 71 \text{ Ft}^2 (110) \right] = 12.5^k \text{ kips}$$

$$N = 12.5^k \cos 57.5^\circ = 6.7$$

$$T = 6.7 \tan 35^\circ = 4.7$$

$$P_A = 6.7 \sin 57.5 - 4.7 \cos 57.5 + \underline{\underline{3.44^k}} = \underline{\underline{6.58 \text{ kips}}}$$



Project No.	<u>3-1161-610</u>	Page	<u>6</u>	of	<u>8</u>
Client	<u>B.N.</u>	Date	<u>4/20/95</u>		
Site	<u>SKYKAMISH RIVER</u>	By	<u>MYL</u>		
Subject	<u>SLURRY TRENCH STABILITY</u>	App.			

TRAIL (4): $\theta = 55^\circ$

$$W = \left[\frac{1}{2} (10.5)(7.4)(130) + 78(110) \right] = 13.65^k$$

$$N = 13.65^k \cos 55^\circ = 7.83$$

$$T = 7.83 \tan 35^\circ = 5.48$$

$$P_A = 7.83 \sin 55^\circ - 5.48 \cos 55^\circ + 3.44^k = \underline{6.71^k}$$

TRAIL (5): $\theta = 52.5$

$$W = \left[\frac{1}{2} (10.5)(8)(130) + 86(110) \right] = 14.90^k$$

$$N = 14.90 \cos 52.5^\circ = 9.07^k$$

$$T = 9.07 \tan 35^\circ = 6.35^k$$

$$P_A = 9.07 \sin 52.5^\circ - 6.35 \cos 52.5^\circ + 3.44^k = \underline{6.77^k}$$

TRAIL (6): $\theta = 50$

$$W = \left[\frac{1}{2} (10.5)(9)(130) + 99(110) \right] = 17.03^k$$

$$N = 17.03 \cos 50^\circ = 10.95^k$$

$$T = 10.95 \tan 35^\circ = 7.66^k$$

$$P_A = 10.95 (\sin 50^\circ) - 7.66 (\cos 50^\circ) + 3.44 = \underline{6.90^k}$$

TRAIL (7) $\theta = 47.5$

$$W = \left[\frac{1}{2} (10.5)(9.8)(130) + 113(110) \right] = 19.09^k$$

$$N = 19.09 \cos 47.5^\circ = 12.89^k$$

$$T = 12.89 \tan 35^\circ = 9.03$$

$$P_A = 12.89 (\sin 47.5^\circ) - 9.03 (\cos 47.5^\circ) + 3.44^k = \underline{6.85^k}$$

BY
5/3



Project No. 3-1161-S10 Page 6 of 8
 Client B.N. Date 4/28/95
 Site SKYKAMISH RIVER By M.S.G.
 Subject TROUGH STABILITY App. _____

- THE CRITICAL FAILURE SURFACE OCCURS @ AN ANGLE OF 50° PRODUCING A RESULTANT ACTIVE FORCE OF 3.46 KIPS w/o water @ 3.44


- CHECK: CHECK WITH RANKINE SOLUTION

OBTAIN K_a :

↙ SLOPE OF BACKFILL
 $i = 20^\circ, \phi = 35^\circ$

USE $K_a = 0.38$ (DM 7.02, FIG 3, PL 7.2-64)

$P_A = 7.25 \text{ KIPS}$ (HIGH WATER)




RETEC

Project No.	<u>3-1161-610</u>	Page	<u>7</u> of <u>8</u>
Client	<u>B.N.</u>	Date	<u>5/1/95</u>
Site	<u>SKYKOMISH RIVER</u>	By	<u>MTC</u>
Subject	<u>SLURRY TRENCH</u>	App.	<u></u>

CASE 2 FAILURES FROM 40^k DOZER WORKING ALONG TRENCH

USE RANKINE ACTIVE, FOR HORIZ. BACKFILL



IF THE TRENCH WAS LOCATED ALONG SOUTH SIDE OF RIVER DRIVE WITHIN 6' OF 1STORY W/F HOUSE. THE HOUSE WOULD PRODUCE A LINE LOAD OF 1000 LB/FT ALONG THE TRENCH THIS WOULD RESULT IN

A RESULTANT HORIZ. FORCE OF 0.5 KIPS & A TOTAL HORIZ. FORCE OF $2.71 (P_{\text{soil}}) + 3.44 (P_{\text{water}}) + 0.5 (P_{\text{house surcharge}}) = 6.65^k$



Project No.	3-1161-510	Page	8 of 8
Client	B.N.I.	Date	5/1/95
Site	SKYKOMISH RIVER	By	MJK
Subject	SLURRY TRENCH STABILITY	App.	

MAX ACTIVE FORCE WILL BE 7.35 K₁ ← soil (Flat) water + surcharge

REQUIRED SLURRY DENSITY (USE depth)

Slurry level @

$$\gamma_s - \gamma_s = 65.3 \text{ pcf}$$

$$\gamma_s \frac{(14.5^2)}{2} = 7350 \text{ LBS}$$

@ 14', $\gamma_s = 75 \text{ pcf}$

$$\gamma_s \approx \underline{\underline{70 \text{ LB/FT}^3}}$$


IF TRENCH WAS IN THE MIDDLE OF ...

North side of trench → P (North level side) 7.25 K₁

South side of trench → $P_T = 2.71(P_{soil}) + 3.44(P_{water}) + 1.2(P_{surcharge}) + 0.32(P_{active})$

$$P_T = 7670 \text{ LBS}$$

$$\gamma_s = 73 \text{ LB/FT}^3$$



MAX STRAIN TO MOBILIZE ACTIVE STRESSES

$$\Delta = 0.001(15 \text{ Ft}) \frac{12w}{\text{FT}} = 0.18''$$

NO RISK TO FOUNDATION

REFERENCE 2

MONITOR WELL NO. MW-25

WELL SCHEMATIC

Casing Elevation (ft.): 922.84
 Casing Stickup (ft.): -0.24


Vapor
 Conc. (ppm)
 Sheen

Blow-
 Count

Samples

DESCRIPTION

Surface Elevation (ft.): 923.08



Note: See Figure A-2 for explanation of symbols



Log of Monitor Well

Figure A-27

MONITOR WELL NO. MW-24

WELL SCHEMATIC

Casing Elevation (ft.): 921.82
 Casing Stickup (ft.): -0.77


Vapor
 Conc (ppm)
 Sheca

Blow-
 Count

Samples

DESCRIPTION

Surface Elevation (ft.): 922.59



Note: See Figure A-2 for explanation of symbols.



Log of Monitor Well

Figure A-26

MONITOR WELL NO. MW-23

WELL SCHEMATIC

Casing Elevation (ft.): 921.60
 Casing Stickup (ft.): -0.74


Vapor
 Conc.(ppm)
 Sheets

Blow-
 Count
 Samples

Group
 Symbol

DESCRIPTION

Surface Elevation (ft.): 922.34




Note: See Figure A-2 for explanation of symbols



BORING/WELL INSTALLATION LOG
Monitoring Well 42 (Boring SO-3)

1011 S.W. Klickitat Way
Suite #207
Seattle, Washington 98134
(206) 624-9349

PROJECT NO: 3-101-350 Skykomish RI/FS	CLIENT: Burlington Northern Santa Fe
LOCATION: Skykomish, Washington: Along N. School Yard Fence ~ 80' from N.W. Corner	DRILLING CO.: Cascade Drilling, Inc.
START DATE: 08/28/96 TIME: 09:00	BORING ID: 6 inches
DRILLER: Mike Colbert	
COMPLETION DATE: 08/28/96 TIME: 12:30	TOTAL DEPTH: 20.0 feet
RIG TYPE: Ingersoll Rand	
WATER LEVEL DURING DRILLING: 7.0' bgs	TOP OF CASING: -0.25 feet
METHOD: Air Rotary	
SURFACE ELEV.: _____	MP ELEV.: (Ground Surface)
	LOGGED BY: Shelly Birch




REMARKS: B - Analytical Sample
C - Cuttings
NR - No reading above background.
SS - Split Spoon

REMEDATION TECHNOLOGIES, INC.
A Thermo Electron Company

Page 1 of 1


gw level in August every year.




gw dep. to higher level in August

REFERENCE 3

Hydrograph of MW-24



Hydrograph of MW-23






BORING/WELL INSTALLATION LOG

Monitoring Well 42 (Boring SO-3)

1011 S.W. Klickitat Way
 Suite #207
 Seattle, Washington 98134
 (206) 624-9349

PROJECT NO.: 3-1101-350 Skykomish RI/FS	CLIENT: Burlington Northern Santa Fe
LOCATION: Skykomish, Washington; Along N. School Yard Fence - 80' from N.W. Corner	DRILLING CO.: Cascade Drilling, Inc.
START DATE: 08/28/98 TIME: 09:00	BORING ID: 8 inches
COMPLETION DATE: 08/28/98 TIME: 12:30	DRILLER: Mike Colbert
WATER LEVEL DURING DRILLING: 7.0' bgs	TOTAL DEPTH: 20.0 feet
SURFACE ELEV.: (Ground Surface)	RIG TYPE: Ingersoll Rand
	METHOD: Air Rotary
	LOGGED BY: Shelly Birch



REMARKS:
 Ø - Analytical Sample
 C - Cuttings
 NR - No reading above background
 SS - Split Spoon

REMEDICATION TECHNOLOGIES, INC.
 A Thermo Electron Company



June 15, 2001

(206) 624-9349 Phone
(206) 624-2839 Fax
www.retec.com

Dominic Parmantier
Project Manager
Hayward Baker Inc.
11004 E. Marginal Way South
Tukwila, WA 98168

RE: Addendum No. 1
Request for Proposal for Construction Services
LNAPL Containment Barrier Wall
BNSF – Skykomish, Washington

Dear Dominic:

On behalf of the Burlington Northern and Santa Fe Railway Company (BNSF), ThermoRetec Consulting Corporation is providing Addendum No. 1 to the Request for Proposal (RFP) for Construction Services for the above referenced project. The RFP was issued on June 8, 2001. Information in this addendum was developed in response to public, County and agency comments to the Basis of Design report which were not entirely available at the time of the RFP, and as clarification to issues identified internally.

Addenda items include the following:

- A-1-1: Bid Date. Given the information contained in this addendum, the bid date has been extended to 5:00pm Pacific Standard Time on Thursday, June 21, 2001. Bids will be accepted at the ThermoRetec office in Seattle, Washington until that time.
- A-1-2: Trench stability for cement bentonite slurry wall excavation. If a slurry wall is the chosen alternative, the contractor shall maintain stability of the trench walls at all times for its full depth. It should be noted that the flood control levee is very close to the slurry wall corridor, a fact that should be considered when evaluating stability of the trench walls. The level of slurry shall not be permitted to drop more than one (1) foot below the surfaces of the surrounding ground. The Contractor shall have personnel, equipment, and materials ready to raise the slurry level at any time. To this end, the Contractor shall have personnel on call to raise the slurry level (if required), weekends and/or holidays included. Additionally, the unit weight of the cement bentonite slurry shall not be allowed to drop below 73 pounds per cubic foot. This density is an in-place density, and as such, will be measured on slurry that is in the trench.

Modifications to the requirements set forth in this addenda item will be considered if the proposed modifications are presented with sufficient time for review, and with complete



stability calculations for the trench sealed by a Professional Engineer registered in the state of Washington. If a modification is requested, it should be indicated in the bidder's proposal with supporting information submitted along with the project work plan.

- A-1-3: Water Quality Data. The attached data is supplied so that the Contractor can develop a mix design that is compatible with groundwater contaminants on the site. These data specifically should be used as the basis for compatibility testing/evaluations of the proposed mix design. The attached Table 2 and Figure 2 indicate extent of dissolved TPH constituents monitored on groundwater beneath the LNAPL plume. LNAPL thicknesses measured in the vicinity of the proposed barrier range from 0.1 to 1.0 feet.
- A-1-4: Flood Events. With notice of a potential flood event on the Skykomish River, all trench excavation work (if a cement bentonite slurry wall is the chosen option) will be halted, or modified as specified herein. If the flood is eminent, the trench section that contains fresh slurry will be filled to the extent possible to maintain a stable trench in light of the rising flood waters and groundwater. If suitable time is available, all trench excavation will be halted at least 12 hours prior to flooding and the cement bentonite slurry in the trench will be allowed to remain in the trench with no additional backfilling. Standby time as defined in the RFP will be evaluated by the Engineer if requested by the Contractor during times when the project is halted by the Engineer for flooding.
- A-1-5: This is an environmental project with specific health and safety training requirements associated with working on a site impacted with Bunker C and diesel LNAPL. As such, spoils associated with barrier wall construction work are impacted with TPH constituents and will ultimately be disposed of at a Subtitle D landfill facility. The Contractor shall consider spoils as contaminated soil and include special handling requirements typically associated with contaminated soil. This includes at a minimum management, stockpiling and containment in lined holding areas with appropriate run-on and run-off controls.
- A-1-6: The chosen Contractor's proposal will need to be approved by Department of Ecology prior to awarding the work. ThermoRetec intends to issue an "Intent to Award" recommendation to the Department of Ecology once the bids are received and evaluated. The Department of Ecology will either concur with the recommendation or provide comments to the letter. All comments need to be addressed, and a concurrence from the Department of Ecology is required before BNSF can award the project.
- A-1-7: Construction Staging Area. A modification to the construction staging area has been required to remain clear of the school's drain field. The attached modified Plate 1 indicates the new dimensions of the staging area that will be available during construction.




A-1-8: GPR survey. A ground penetrating radar (gpr) study was completed along the alignment in an attempt to locate any potential undiscovered subsurface utilities. The results of the study indicate that there is a high potential for debris within 3 feet of the ground surface. The exact nature of the debris is not known, but it is speculated to be cobbles, wood, old piping, and/or boulders. There were also several locations where potential cobbles/boulders/pipe was identified at depths between 3 and 8 feet below the ground surface. These potential obstructions are not necessarily shown on the boring logs because they were not encountered during drilling. The contractor should consider this information in preparing their bids and in developing their recommended wall system.


Sincerely,



ThermoRetec Consulting Corporation

Bryan Stone
Construction Manager

Attachment: Revised Plate 1
Table 2
Figure 2

cc: B. Sheppard – BNSF
R. Truax, H. Voges, , W. Chen – ThermoRetec; BN050-04018-560





NOTE:
 SOIL SAMPLE LOCATIONS SS-50 & SS-51 ARE APPROXIMATE AND NOT BASED ON DATA GATHERED BY AN ENGINEERING SURVEY.

LEGEND	
●	MW-32 MONITORING WELL LOCATION
◆	DW-1 DEEP MONITORING WELL LOCATION
▲	B-11 BORING LOCATION
⊕	BG-1 BACKGROUND SAMPLE LOCATION
⊕	SS-23 SURFACE SOIL SAMPLE LOCATION
▲	HA-1 HAND AUGER SAMPLE LOCATION
✱	TP-2 TEST PIT LOCATION
○	SO-1 BORING LOCATION
■	R-2 RECOVERY WELL LOCATION
◇	SW-1 SURFACE WATER SAMPLE LOCATION
◇	SED-1 SEDIMENT SAMPLE LOCATION



BURLINGTON NORTHERN SANTA FE SKYKOMISH, WASHINGTON 3-4018-420			SAMPLE LOCATIONS
DATE: 8/30/99	DRWN: RB	FILE: 4018s074	FIGURE 2-3