

**2014 Annual Report
AOC-05 Remedial Action
Enhanced Anaerobic Biodegradation of
Gasoline-Range Petroleum Hydrocarbons
Boeing Developmental Center
Tukwila, Washington**

October 23, 2015

Prepared for

**The Boeing Company
Seattle, Washington**

 **LANDAU
ASSOCIATES**
130 2nd Avenue South
Edmonds, WA 98020
(425) 778-0907

TABLE OF CONTENTS

		<u>Page</u>
1.0	INTRODUCTION	1-1
2.0	OVERVIEW OF REMEDIAL APPROACH.....	2-1
3.0	SUMMARY OF PREVIOUS WORK.....	3-1
3.1	Pilot Testing.....	3-1
3.2	Well Installation and Baseline Monitoring.....	3-1
3.3	Prior Full-Scale Nitrate Injections and Performance Results	3-2
4.0	REMEDICATION ACTIVITIES DURING THIS REPORTING PERIOD	4-1
5.0	DISCUSSION OF RESULTS DURING THIS REPORTING PERIOD	5-1
5.1	TPH-G and BTEX	5-1
5.2	Nitrate and Nitrite.....	5-2
6.0	SUMMARY AND PLANNED ACTIVITIES.....	6-1
7.0	USE OF THIS REPORT.....	7-1
8.0	REFERENCES	8-1

FIGURES

<u>Figure</u>	<u>Title</u>
1	Site Location Map
2	Site Plan
3	BDC-103 TPH-G and BTEX Concentrations Beginning with 2007 Pilot Testing
4	BDC-104 TPH-G and BTEX Concentrations Beginning with 2007 Pilot Testing
5	BDC-101 TPH-G and Benzene Concentrations Since 2001
6	BDC-102 TPH-G and Benzene Concentrations Since 2001
7	BDC-103 TPH-G and Benzene Concentrations Since 2001
8	BDC-104 TPH-G and Benzene Concentrations Since 2001
9	BDC-103 Nitrate, TPH-G, and Benzene Concentrations
10	BDC-104 Nitrate, TPH-G, and Benzene Concentrations
11	Groundwater Levels
12	Nitrate Concentrations at Downgradient Monitoring Locations

TABLES

<u>Table</u>	<u>Title</u>
1	Data Summary
2	Remediation Progress and Key Milestones
3	Nitrate Concentrations at Downgradient Monitoring Locations

This page intentionally left blank.

1.0 INTRODUCTION

This document presents the 2014 annual report for the anaerobic bioremediation remedial action performed at Area of Concern (AOC)-05 of The Boeing Company's (Boeing) Developmental Center (DC) in Tukwila, Washington (Figure 1). Remedial action is performed to stimulate anaerobic biodegradation of gasoline contamination resulting from a 1985 release from a former leaking underground storage tank (UST) near injection well BDC-103. AOC-05 wells and site features are shown on Figure 2. Anaerobic bioremediation remedial action was performed in general accordance with the Remedial Action Work Plan (Work Plan, Landau Associates 2007a).

This annual report summarizes the activities and results for March 2014 through February 2015. Based on monitoring results, no injection events were conducted during this period.

Following this introductory section, the report is organized into five main sections. Sections 2 and 3 provide an overview of the remedial approach and a summary of prior work, as context to activities and results in the current reporting period. Section 4 documents activities during the reporting period, and Section 5 presents discussion of reporting period results. Section 6 provides a summary and describes planned activities.

2.0 OVERVIEW OF REMEDIAL APPROACH

Anaerobic bioremediation at AOC-05 is accomplished through stimulation of micro-organisms present in the aquifer to degrade petroleum hydrocarbons. The addition of nitrate (electron acceptor) allows the native bacteria to utilize petroleum as food (electron donor).

Biodegradation of total petroleum hydrocarbons (TPH) occurs through microbially mediated reactions whereby micro-organisms obtain energy by oxidation-reduction (redox) reactions. TPH is used as the electron donor together with various electron acceptors [oxygen, nitrate, manganese (IV), ferric iron, sulfate, and carbon dioxide]. These redox reactions can be compared to the process whereby humans obtain energy through consumption of food (electron donor) and oxygen (electron acceptor). Bacteria obtain the greatest energy yield by using oxygen as an acceptor, as it is highly oxidized and, therefore, can be more easily and more substantially reduced. When oxygen is depleted, bacteria sequentially use the less oxidized electron acceptors in the following order: nitrate, manganese (IV), ferric iron, sulfate, and carbon dioxide.

Biodegradation of petroleum hydrocarbons can occur under both aerobic and anaerobic conditions. Stimulation of anaerobic degradation can be the preferred approach in naturally anaerobic aquifers (such as the one at the DC) where stimulation of aerobic conditions is unlikely to be effective due to high natural oxygen demand (Wiedemeier et al. 1999). An attempt in 2002 to stimulate aerobic bioremediation of TPH in AOC-05 through injection of oxygen release compound (ORC™) was ineffective due to the naturally anaerobic condition (Landau Associates 2006a). During anaerobic biodegradation of TPH, nitrate (or sulfate) functions as the electron acceptor for microbial degradation of the TPH electron donor. In addition to the work being performed at the Boeing DC, nitrate amendment to enhance anaerobic biodegradation has been successfully implemented on other full-scale remediation projects for gasoline-range and fuel oil-range TPH, both nationally (Lozier and Hicks 2005; Wasserman et. al. 2005) and in Washington State (Landau Associates 2012a).

3.0 SUMMARY OF PREVIOUS WORK

Full-scale anaerobic bioremediation began in 2008 following anaerobic bioremediation pilot testing performed in 2007. 2007 Pilot testing using a single injection well (BDC-103; Landau Associates 2007b) was expanded to full-scale treatment in 2008 utilizing existing injection well BDC-103 and new injection well BDC-104. Following baseline groundwater monitoring for full-scale treatment, and prior to the current reporting period, nitrate was injected nine times, as follows:

- three times in 2008 (both wells)
- twice in 2009 (both wells)
- once in 2010 (BDC-103 only)
- twice in 2012 (BDC-103 only)
- once in 2013 (BDC-103 only).

3.1 Pilot Testing

2007 bioremediation pilot testing demonstrated degradation of petroleum hydrocarbons resulting from a one-time addition of ammonium nitrate (Landau Associates 2007b). Post-injection monitoring showed that concentrations of TPH in the gasoline range (TPH-G) decreased by about 50 percent compared to baseline over 4 months of post-injection monitoring, while benzene, toluene, ethylbenzene, and xylenes (BTEX) compounds decreased as much as 98 percent (Landau Associates 2007b). As expected, contaminant concentrations rebounded upon depletion of injected nitrate due to groundwater returning to equilibrium with sorbed mass and non-aqueous phase liquid (NAPL) mass remaining in the aquifer.

3.2 Well Installation and Baseline Monitoring

Full-scale implementation of anaerobic bioremediation began with installation of one additional injection well (BDC-104) and baseline monitoring of all four AOC-05 wells (BDC-101, BDC-102, BDC-103, and BDC-104) in February 2008. The new well was installed somewhat upgradient (east) and cross-gradient (north) of existing injection well BDC-103, to enhance treatment coverage during nitrate injections. BDC-103 is located within the tank pit of the former UST. BDC-104 is located near the known upgradient edge of contamination associated with the former UST (Landau Associates 2004). Injection of both wells allowed for groundwater transport of injected nitrate solution to the area of highest contamination. The well locations and their estimated radii of injection (ROIs) are shown relative to the area of groundwater contamination on Figure 2.

Baseline monitoring was performed prior to full-scale treatment to determine starting contaminant concentrations and aquifer redox conditions at the four AOC-05 wells (BDC-101, BDC-102, BDC-103, and BDC-104). Baseline results indicated nitrate- to sulfate-reducing conditions at source zone wells BDC-103 and BDC-104, nitrate- to iron-reducing conditions at downgradient well BDC-102, and aerobic to nitrate-reducing conditions at downgradient well BDC-101; the same conditions as

indicated by pre-pilot test baseline monitoring (Landau Associates 2006b). Prior to full-scale treatment, baseline (February 2008) concentrations of TPH-G were in excess of the preliminary screening level at both source zone wells BDC-103 and BDC 104, and the baseline benzene concentrations exceeded the preliminary screening level at BDC 103; preliminary screening levels in use at that time were developed in a prior DC site summary report (Landau Associates 2002). TPH-G and BTEX were not detected at downgradient wells BDC-101 and BDC-102 during baseline sampling, but had been during prior sampling extending back to 2001. Full results of baseline monitoring are included in the data summary presented in Table 1. Proposed cleanup levels (PCULs) developed in 2013 (Landau Associates 2013a) are also presented in Table 1 and contaminant concentrations above PCULs are boxed.

3.3 Prior Full-Scale Nitrate Injections and Performance Results

As indicated above, nitrate solution was injected nine times at AOC-05 following baseline groundwater monitoring and prior to the current reporting period. Nitrate solutions were injected to wells BDC-103 and BDC-104 three times during 2008 (February, June, and November) and twice during 2009 (June and November). After 2009, injections were required at BDC-103 only, with injections occurring in 2010 (September), 2012 (February and November), and 2013 (November); there were no injections in 2011. In accordance with the work plan (Landau Associates 2007a), the standard injection dose of nitrate was 6,500 gallons of 1,000 milligrams per liter (mg/L) nitrate solution [225 mg/L as nitrogen (mg-N/L)].

Prior performance results from 2008 through February 2014 indicated effective treatment of TPH-G and BTEX at source zone wells BDC-103 and BDC-104, while maintaining low to non-detect contaminant levels at downgradient wells BDC-101 and BDC-102. Detailed analysis of groundwater sampling results for 2008 through February 2014 can be found in previous annual reports (Landau Associates 2009a, 2010, 2011, 2012b, 2013b, 2014). Cumulative performance monitoring results are presented in Table 1. Treatment progress and key milestones are described for each year below and summarized in Table 2:

2008

- Nitrate was consumed rapidly following the first two injection events.
- After the third injection event (November 2008), monitoring indicated slower consumption of injected nitrate and a partial rebound in concentrations of petroleum hydrocarbons at source zone well BDC-103, despite the presence of adequate nitrate for continued treatment. This rebound of contaminant concentration, despite adequate nitrate, suggested that biodegradation in AOC-05 had become nutrient-limited.

2009

- During the fourth injection event (June 2009), ammonium phosphate was added to the nitrate injection fluid to overcome the observed treatment slowdown thought to be caused by a deficiency of the macro-nutrient phosphorus. The amount of phosphate added to the injection

solution was based on a nitrogen-to-phosphorus ratio of 10:1, a commonly cited optimal nutrient ratio (Metcalf and Eddy 2002). The amount of yeast extract (which provides micro-nutrients) was also increased from 2 lbs to 4 lbs per well. During this single injection event, the nitrate concentration injected was decreased by two thirds to 330 mg/L nitrate (75 mg-N/L) to limit the addition of nitrate while evaluating the effects of the ammonium phosphate.

- Data from the July 2009 sampling event suggested that consumption of nitrate and bioremediation of contaminants had resumed following the addition of ammonium phosphate to the injection solution. Based on these results, ammonium phosphate was added to subsequent injection solutions.
- During the fifth injection (November 2009), nitrate was increased back to the standard concentration at well BDC-103. Although TPH-G and BTEX were not detected during prior sampling events in July or September 2009 at well BDC-104, a half-concentration injection [500 mg/L nitrate (112 mg-N/L)] was performed at that well to treat contamination previously characterized to the north and east of well BDC-103 that may not have been within the ROI of BDC-103.

2010

- Contaminant concentrations decreased substantially following the fifth injection, with results from the February 2010 sampling event showing TPH-G and benzene concentrations below preliminary screening levels at BDC-103 for the first time since monitoring began in 2001.
- Contaminant concentrations at BDC-103 rebounded again in May and August 2010 as nitrate was consumed, prompting a sixth injection (September 2010).

2011

- Contaminant concentrations decreased to historical lows at source zone well BDC-103 in February 2011. All contaminant concentrations were below reporting limits and/or screening levels at all four AOC-05 monitoring wells during this event.
- In May 2011, TPH-G concentrations fell below the laboratory reporting limit of 0.25 mg/L at well BDC-103 for the first time since monitoring began in 2001.
- A substantial rebound in contaminant concentrations was observed in November 2011 upon nitrate depletion. This rebound was coincident with a rise groundwater levels resulting in a higher water table than had been observed during prior years of treatment. It is likely that the higher water table caused groundwater to contact higher portions of the contaminant smear zone not treated by prior injection events.

2012

- The November 2011 rebound prompted a seventh injection at BDC-103 (February 2012). Sampling following the February 2012 injection showed substantial decreases in contaminant concentrations at BDC-103 and abundant nitrate for resumed treatment.
- Contaminant concentrations at BDC-103 rebounded somewhat in September 2012 as nitrate was consumed, prompting an eighth injection.

2013

- In February 2013, contaminant concentrations at BDC-103 were all below reporting limits with the exception of low-level detections of total xylenes. These were the lowest concentrations observed at well BDC-103 since monitoring began in 2001.
- August 2013 groundwater monitoring results at BDC-103 showed a substantial decrease in nitrate (from 161 mg-N/L to 17.8 mg-N/L) coincident with an increase in contaminant concentrations. These results prompted the ninth injection event in November 2013.

2014

- In February 2014 (included in the 2013 reporting period), TPH-G and BTEX concentrations were below laboratory reporting limits at well BDC-103, with the exception of low level xylenes. February 2014 was the second time that these contaminants were below reporting limits since monitoring began in 2001 (first occurred in February 2013.)

As indicated in the Work Plan (Landau Associates 2007a), the Washington State Department of Ecology (Ecology) required an action level for nitrate of 10 mg-N/L for the AOC-05 remedial action. Detection of nitrate above the action level at either of the two nearest downgradient wells (BDC-101 or BDC-102) for two consecutive sampling events triggers implementation of additional groundwater monitoring at four wells located farther downgradient (BDC-05-04, MW-17A, MW-18A, and MW-21A). Semiannual monitoring for nitrate is required to continue at these four downgradient wells for 1 year after nitrate at wells BDC-101 and BDC-102 decreases below 10 mg-N/L. Based on continued periodic exceedances of the action level at wells BDC-101 and BDC-102, semiannual nitrate monitoring has been performed at the four downgradient wells since November 2009. Nitrate has not been detected at the four downgradient wells (BDC-05-04, MW-17A, MW-18A, and MW-21A) above the 10 mg-N/L action level. Cumulative downgradient nitrate monitoring results are included in Table 3.

4.0 REMEDIATION ACTIVITIES DURING THIS REPORTING PERIOD

This section describes remediation activities and monitoring results for the current reporting period of March 2014 through February 2015. Based on monitoring results indicating adequate nitrate for continued treatment, no injections were performed. Four quarterly monitoring events were performed in May, August, and November 2014, and in January 2015. In accordance with the Work Plan (Landau Associates 2007a), samples were analyzed for contaminant concentrations (TPH-G and BTEX) and parameters indicative of aquifer redox conditions [dissolved oxygen (DO), oxidation-reduction potential (ORP), nitrate, ferrous iron, sulfate, and pH]. Samples were also analyzed for nitrite. TPH-G, BTEX, nitrate, nitrite, and sulfate were analyzed in the laboratory, while other parameters (DO, ORP, ferrous iron, and pH) were measured in the field. Laboratory analysis was performed by Eurofins Lancaster Laboratories Environmental (LLI). A summary of monitoring results for the four AOC-05 wells (BDC 101 through BDC-104) is presented with cumulative data in Table 1.

Semiannual monitoring for nitrate continued in May and November 2014 at the four monitoring wells located farther downgradient of AOC-05 (MW-17A, MW-18A, MW-21A, and BDC-05-04). These results are presented with cumulative data in Table 3. Semiannual monitoring for nitrate is required to continue at these four downgradient wells for 1 year after nitrate at wells BDC-101 and BDC-102 decreases below 10 mg-N/L.

5.0 DISCUSSION OF RESULTS DURING THIS REPORTING PERIOD

Performance monitoring results for the current reporting period from March 2014 through February 2015 indicate continued effective treatment of TPH-G at AOC 05. Highlights are presented below and summarized in Table 2.

- Contaminant concentrations at BDC-101, BDC-102, and BDC-104 remained below laboratory reporting limits during all four quarterly sampling events.
- Contaminant concentrations at BDC-103 are generally below laboratory reporting limits. TPH-G, toluene, and ethylbenzene were all below reporting limits. Benzene and total xylenes were detected once (August 2014) during the reporting period. The August detection of benzene (7.8 µg/L) was the only contaminant detection during the reporting period above the PCUL (2.0 µg/L).
- In May 2014, AOC-05 groundwater levels were the highest since AOC-5 monitoring began in June 2001. Groundwater levels were approximately 0.1 to 0.3 ft higher than the prior high water table condition observed in May 2011. Accordingly, the minor increases in benzene and total xylenes concentrations observed in August 2014 are likely due to contact of the water table with minor residual contamination that remained in a higher portion of the smear zone. The contrast between these minor concentration increases in August 2014 and the substantial concentration rebound observed in November 2011 following the prior high water table condition (Section 3.3) suggests that most of the contaminant mass and smear zone thickness has been treated. A plot of groundwater elevations with time at the four AOC-05 wells is presented on Figure 11.

Monitoring results are presented on Figures 3 through 10, summarized in Table 1, and discussed further in the following sections. TPH-G and BTEX concentrations at BDC-103 and BDC-104 are plotted against time (from the period of nitrate pilot testing through full-scale treatment) on Figures 3 and 4, respectively. Concentrations of TPH-G and benzene (the compounds that have most commonly exceeded PCULs) are plotted since monitoring began in June 2001 on Figures 5 through 8 for wells BDC 101 through BDC-104. Concentrations of nitrate, TPH-G, and benzene are plotted against time for injected wells BDC-103 and BDC-104 on Figures 9 and 10, respectively. Cumulative monitoring results in Table 1 are compared to PCULs (Landau Associates 2013a) and contaminant concentrations above PCULs are boxed.

5.1 TPH-G and BTEX

In January 2015, TPH-G and BTEX concentrations at well BDC-103 were below laboratory reporting limits, continuing a general trend of sustained low to non-detect contaminant concentrations started in February 2014. Only benzene and total xylenes were detected during the current reporting period, in August, and only benzene was detected above its respective PCUL. No detections at the reporting limits indicate concentration reductions of 99.6 to 99.9 percent for TPH-G and BTEX compared to the 2008 baseline concentrations. Contaminant concentrations were below their respective reporting limits during the entire reporting period at the other three AOC-05 wells (BDC-101, BDC-102, and BDC-

104). Changes in contaminant concentrations from groundwater sampled at BDC-103 over the reporting period are further described as follows:

- TPH-G has remained below the reporting limit (0.25 mg/L) for four quarters beginning in February 2014. Although TPH-G was also not detected during events in 2011-2013, 2014 is the first time that it was not detected for more than two consecutive quarters. The reporting limit (0.25 mg/L) represents a decrease of 99.6 percent from the 2008 baseline concentration of 66 mg/L.
- The benzene reporting limit (1.0 µg/L) represents a 99.9 percent reduction from the 2008 baseline concentration of 1,100 µg/L. With the exception of August 2014 (7.8 µg/L), benzene concentrations have been below the detection limit beginning in February 2014; the PCUL for benzene is 2.0 µg/L
- Toluene has remained below the reporting limit (1.0 µg/L) beginning in February 2014, and has been below the PCUL (1,294 µg/L) beginning in February 2012. The reporting limit represents a 99.9 percent reduction compared to the 2008 baseline concentration of 2,600 µg/L.
- Ethylbenzene has remained below the reporting limit (1.0 µg/L) beginning in February 2014. The reporting limit represents a 99.9 percent reduction compared to the 2008 baseline concentration of 700 µg/L.
- Total xylenes have remained below the PCUL (1,546 µg/L) beginning in February 2012. They were only detected above the reporting limit (1.0 µg/L) once during the reporting period, in August at 2.4 µg/L. The reporting limit represents a 99.9 percent decrease from the 2008 baseline of 9,400 µg/L.

5.2 Nitrate and Nitrite

Nitrate was monitored at the four AOC-05 wells and at the four downgradient wells. Nitrite was also monitored at the four AOC-05 wells.

Aquifer nitrate concentrations at well BDC-103 remained relatively high (111 to 215 mg-N/L) during the reporting period despite more than 14 months since the prior injection at BDC-103 in November 2013. Persistence of these elevated nitrate concentrations is a strong indicator that TPH mass has been largely depleted and no longer exerts a substantial demand for the injected nitrate electron acceptor. Nitrate concentrations at BDC-104, which has not been injected since October 2009, remained near baseline concentrations (0.35 to 2.9 mg-N/L) for most of the reporting period, with an increase to 11.3 mg-N/L observed in January 2015.

Per the Work Plan (Landau Associates 2007a), detection of nitrate above the action level of 10 mg-N/L at either BDC-101 or BDC-102 for two consecutive sampling events triggers additional groundwater monitoring at farther downgradient wells MW-17A, MW-18A, MW-21A, and BDC-05-04. Nitrate concentrations at BDC-101 exceeded the action level during May 2014, August 2014, and January 2015 sample events, and were below the action level during the November 2014 sampling event. Nitrate concentrations at well BDC-102 remained above the action level throughout the reporting period. Semiannual nitrate monitoring at four downgradient wells continued during this reporting

period. All downgradient detections remained below the 10 mg-N/L action level, with the highest detection occurring at MW-17A (2.2 mg-N/L) in May 2014. Per the Work Plan, semiannual monitoring for nitrate will continue at the four downgradient wells for 1 year after nitrate at wells BDC-101 and BDC-102 drops below 10 mg-N/L. Cumulative monitoring results for downgradient wells are summarized in Table 3 and presented on Figure 12.

Detection of low levels of nitrite is a result of nitrate reduction. Nitrite is a highly reactive, short-lived compound that is further reduced through nitrous oxide and nitric oxide to nitrogen gas (Environment Agency 2005). Nitrite has been commonly detected at injection wells since the start of full-scale injection activities. The maximum nitrite concentration detected during this reporting period was 0.68 mg-N/L at injection well BDC-103 in November 2014. Nitrite was not detected at well BDC 104 or at downgradient wells BDC-101 and BDC-102 during this reporting period. This data confirms that nitrite continues to be reduced in the treatment area.

6.0 SUMMARY AND PLANNED ACTIVITIES

Data suggests that bioremediation treatment of TPH is nearing completion in AOC-05. TPH-G and BTEX have been below proposed CULs at wells BDC-101, BDC-102, and BDC-104 since 2009. Beginning in February 2014, TPH-G and BTEX have remained low to not detected at well BDC-103, the well with the highest historic contaminant concentrations. The only exceedance of proposed CULs during this period was benzene at 7.8 µg/L at BDC-103 in August 2014 compared to the 2.0 µg/L proposed CUL. Contaminant concentrations at BDC-103 have been reduced more than 99 percent compared to 2008 baseline conditions. Low to non-detect contaminant results have persisted despite groundwater levels during this period that were higher than previously observed. By contrast, a previous high water table condition in 2011 resulted in substantial rebound in contaminant concentrations due to remaining TPH in the high portion of the smear zone. Another indicator of a substantial reduction in contaminant mass is slow consumption of nitrate over nearly a year since the last injection event, as evidenced by continued high nitrate concentrations.

Additional nitrate injections at AOC-05 will continue, as needed, to treat remaining aqueous-phase, sorbed-phase, and/or NAPL contamination until contaminant concentrations remain consistently below PCULs and it has been demonstrated that substantial rebound of contaminant concentrations will not occur. It is understood that rebound will continue to occur as long as contaminant mass remains in the sorbed-phase or as NAPL within the aquifer or in upper portions of the smear zone that are periodically contacted by the water table. Upon depletion of nitrate in the aquifer, groundwater concentrations will return to equilibrium with remaining TPH mass present in non-aqueous phase. Treatment will be complete when rebound no longer occurs upon depletion of injected nitrate.

Results through February 2015 do not indicate that another injection is needed at this time; however, additional injections may be scheduled if monitoring results indicated rebound of contaminant concentrations following depletion of nitrate. Modification of the injection approach will be evaluated on an ongoing basis, based on the most current monitoring data. Ammonium phosphate (to prevent a nutrient stall), higher injection rates (to achieve mounding for contact with higher portions of the smear zone), and the larger injection volume (to extend the ROI and increase the longevity of treatment) will likely continue to be utilized for future injections.

Groundwater monitoring will continue at the four AOC-05 wells and at the four downgradient wells. AOC-05 groundwater sampling is planned to continue on a quarterly basis to evaluate contaminant treatment and nitrate consumption. The four AOC-05 wells will continue to be sampled for the parameters indicated in the Work Plan and for nitrite. Semiannual monitoring for nitrate only at downgradient wells MW-17A, MW-18A, MW-21A, and BDC-05-04, triggered by nitrate concentrations at wells BDC-101 and BDC-102, will continue per the Work Plan (Landau Associates 2007a).

7.0 USE OF THIS REPORT

This annual evaluation report has been prepared for the exclusive use of The Boeing Company for specific application to the Boeing Developmental Center. No other party is entitled to rely on the information, conclusions, and recommendations included in this document without the express written consent of Landau Associates. Further, the reuse of information, conclusions, and recommendations provided herein for extensions of the project or for any other project, without review and authorization by Landau Associates, shall be at the user's sole risk. Landau Associates warrants that within the limitations of scope, schedule, and budget, our services have been provided in a manner consistent with that level of care and skill ordinarily exercised by members of the profession currently practicing in the same locality under similar conditions as this project. We make no other warranty, either express or implied.

This document has been prepared under the supervision and direction of the following key staff.

LANDAU ASSOCIATES, INC.



Brandon R. Duncan, P.E.
Project Engineer



Clinton L. Jacob, P.E., L.G.
Principal Engineer

BRD/CLJ/tam

8.0 REFERENCES

Environment Agency. 2005. Attenuation of Nitrate in the Subsurface Environment. Science Report SC030155/SR2. November.

Landau Associates. 2014. 2013 Annual Report, AOC-05 Remedial Action, Enhanced Anaerobic Biodegradation of Gasoline-Range Petroleum Hydrocarbons, Boeing Developmental Center, Tukwila, Washington. Prepared for The Boeing Company. November 24.

Landau Associates. 2013a. Proposed Cleanup Standards and Comparison to Site Data, Boeing Developmental Center, Tukwila, Washington. May 7.

Landau Associates. 2013b. 2012 Annual Report, AOC-05 Remedial Action, Enhanced Anaerobic Biodegradation of Gasoline-Range Petroleum Hydrocarbons, Boeing Developmental Center, Tukwila, Washington. Prepared for The Boeing Company. August 22.

Landau Associates. 2012a. 2011 Cleanup Action Report, Washington State Department of Natural Resources Marine Station, Olympia, Washington. Prepared for The Boeing Company. March 7.

Landau Associates. 2012b. 2011 Annual Report, AOC-05 Remedial Action, Enhanced Anaerobic Biodegradation of Gasoline-Range Petroleum Hydrocarbons, Boeing Developmental Center, Tukwila, Washington. Prepared for The Boeing Company. July 24.

Landau Associates. 2011. 2010 Annual Report, AOC-05 Remedial Action, Enhanced Anaerobic Biodegradation of Gasoline-Range Petroleum Hydrocarbons, Boeing Developmental Center, Tukwila, Washington. Prepared for The Boeing Company. April 8.

Landau Associates. 2010. 2009 Annual Report, AOC-05 Remedial Action, Enhanced Anaerobic Biodegradation of Gasoline-Range Petroleum Hydrocarbons, Boeing Developmental Center, Tukwila, Washington. Prepared for The Boeing Company. April 9.

Landau Associates. 2009a. 2008 Annual Report, AOC-05 Remedial Action, Enhanced Anaerobic Biodegradation of Gasoline-Range Petroleum Hydrocarbons, Boeing Developmental Center, Tukwila, Washington. Prepared for The Boeing Company. March 13.

Landau Associates. 2007a. Work Plan, AOC-05 Remedial Action Plan, Enhanced Anaerobic Biodegradation of Gasoline-Range Petroleum Hydrocarbons, Boeing Developmental Center, Tukwila, Washington. Prepared for The Boeing Company. November.

Landau Associates. 2007b. AOC-05 Pilot Test Results, Enhanced Anaerobic Biodegradation of Petroleum Hydrocarbons, Boeing Developmental Center, Tukwila, Washington. Prepared for The Boeing Company. November 3.

Landau Associates. 2006a. Work Plan, AOC-05 Pilot Test, Enhanced Anaerobic Biodegradation of Gasoline-Range Petroleum Hydrocarbons, Boeing Developmental Center, Tukwila, Washington. Prepared for The Boeing Company. June.

Landau Associates. 2006b. Evidence of Nitrate Reducing Conditions, AOC-05, Boeing Developmental Center, Tukwila, Washington. Prepared for The Boeing Company. June.

Landau Associates. 2004. Evaluation Report, SWMU-17, SWMU-20, and AOC-05, Boeing Developmental Center, Tukwila, Washington. Prepared for The Boeing Company. March.

Landau Associates. 2002 Summary Report, Corrective Action, Boeing Developmental Center. February 27.

Lozier and Hicks. 2005. "Innovative Anaerobic Biodegradation Supplements Monitored Natural Attenuation." In: The Eighth International In Situ and On-Site Bioremediation Symposium, June 6-9, 2005. Baltimore, Maryland.


Metcalf and Eddy, Inc. 2002. Wastewater Engineering: Treatment, Disposal, and Reuse, 4th Ed., McGraw-Hill Book Co., Inc., Boston, MA.

Wasserman R.S., A.C. Easterday, E.C. Hice, A. Leite, and C.J. Varner. 2005. "Innovative Anaerobic In Situ Remediation to Treat Fuel-Oil Contamination – Case Study. In: The Eighth International In Situ and On-Site Bioremediation Symposium, June 6-9, 2005. Baltimore, Maryland.

Wiedemeier, T.H., J.T. Wilson, D.H. Kampbell, R.N. Miller, and J.E. Hansen. 1999. Technical Protocol for Implementing Intrinsic Remediation with Long-Term Monitoring for Natural Attenuation of Fuel Contamination Dissolved in Groundwater. Air Force Center for Environmental Excellence, Brooks Air Force Base, Texas.

Washington – Developmental Center

9725 East Marginal Way South, Seattle, WA 98108



Revised 3-00

Map provided by Boeing, March 2000


Not To Scale

LANDAU ASSOCIATES, INC. | V:\025\0931\13.022\AOC-05 2012 Annual Report\Figure 1 Vicmap.dwg (A) "Figure 1" 8/9/2013



<p>Boeing Development Center Tukwila, Washington</p>	<p>Site Location Map</p>	<p>Figure 1</p>
--	---------------------------------	----------------------------

Boeing Developmental Center | V:\025093\113.022\AOC-05 2012 Annual Report\Figure 2.dwg (A) "Figure 2" 8/9/2013




- Legend**
- AOC-05 Injection and/or Monitoring Well
 - Downgradient Well Location
 - Estimated Radius of Injection
 - Approximate extent of groundwater with gasoline-range hydrocarbon concentrations greater than the 0.8 mg/L preliminary screening level (data is pre-ORC® injection)
 - Approximate extent of groundwater with benzene concentrations greater than the 71 µg/L preliminary screening level (data is pre-ORC® injection)

0 60 120
Approximate Scale in Feet

Boeing Developmental Center Tukwila, Washington	Site Plan	Figure 2
--	------------------	--------------------






Boeing Developmental Center
Tukwila, Washington

**BDC-103 TPH-G and BTEX Concentrations
Beginning with 2007 Pilot Testing**

Figure
3




Note: BDC-104 was installed February 2008



Boeing Developmental Center
Tukwila, Washington

**BDC-104 TPH-G and BTEX Concentrations
Beginning with 2007 Pilot Testing**


Figure
4



Boeing Developmental Center
Tukwila, Washington

**BDC-101 TPH-G and Benzene
Concentrations Since 2001**


Figure
5



Boeing Developmental Center
Tukwila, Washington

**BDC-102 TPH-G and Benzene
Concentrations Since 2001**


Figure
6




Boeing Developmental Center
Tukwila, Washington

**BDC-103 TPH-G and Benzene
Concentrations Since 2001**

Figure
7






Boeing Developmental Center
Tukwila, Washington

BDC-103 Nitrate, TPH-G, and Benzene Concentrations


Figure
9




Boeing Developmental Center
Tukwila, Washington

BDC-104 Nitrate, TPH-G, and Benzene Concentrations

Figure
10



Boeing Developmental Center | G:\Projects\025093\115\022\2014 Ann Rpt\Figure 12.dwg (A) *Figure 12* 8/6/2015




Legend

- AOC-05 Monitoring Well Location
- Downgradient Well Location

MW-21A	Designation
11/12/10 <0.1	Nitrate Concentration (mg/L)
	Date

NA = Not Analyzed; Nitrate sampling was inadvertently missed during May 2012 Sampling.



Boeing Developmental Center Tukwila, Washington	Nitrate Concentrations at Downgradient Monitoring Locations	Figure 12
--	--	---------------------



**TABLE 1
AOC-05 CLEANUP ACTION SUMMARY
DEVELOPMENTAL CENTER GROUNDWATER MONITORING**

Well	Date	ORC Injection	Pilot Injection	Full Scale Injection 1	Full Scale Injection 2	Full Scale Injection 3	Full Scale Injection 4	Full Scale Injection 5	Full Scale Injection 6	Full Scale Injection 7	Full Scale Injection 8	Full Scale Injection 9	Volatile Organic Compounds (all units in ug/L)						Aquifer Redox Conditions						Donor Indicators		Comments			
		BDC-103	BDC-103	BDC-103/104	BDC-103/104	BDC-103/104	BDC-103/104	BDC-103/104	BDC-103/104	BDC-103	BDC-103	BDC-103	BDC-103	TPH-G (mg/L)	Benzene (µg/L)	Toluene (µg/L)	Ethylbenzene (µg/L)	m,p-Xylene (µg/L)	o-Xylene (µg/L)	Total Xylenes (µg/L)	DO (mg/L)	Nitrate (mg-N/L)	Nitrite (mg-N/L)	Iron II (mg/L)	Sulfate (mg/L)	Methane (µg/L)		ORP (mV)	TOC (mg/L)	pH
Proposed Groundwater Cleanup Levels (a)													0.8	2.0	1294	1.7	NA	NA	1546											
BDC-101	6/11/2001												3.0	11.9	<1.0	113.1			109.2											
BDC-101	9/4/2001												5.0	7.13	10.7	50.4			53.8											
BDC-101	12/3/2001												6.5	95	1.6	750			650											
BDC-101	3/13/2002												<0.25	1.4	<1.0	4.4			<1.0											
BDC-101	4/29/2002	-8											<0.25	<1.0	<1.0	2.2	<1.0	<1.0	<1.0											
BDC-101	6/3/2002	27											<0.25	1.0	<1.0	<1.0	<1.0	<1.0	<1.0											
BDC-101	7/1/2002	55											<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0											
BDC-101	8/1/2002	86											<0.25	3.1	<1.0	2.4	<1.0	<1.0	<1.0											
BDC-101	12/2/2002	209											0.61	4.3	<1.0	21	27	6.4	33.4											
BDC-101	3/10/2003	307											<0.25	1.0	<1.0	4.5	3.2	<1.0	3.2											
BDC-101	6/3/2003	392											<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0											
BDC-101	11/19/2003	561											0.42	13	<1.0	15	35	<1.0	35		0.36	1.1	0.010	0.2	16	240	120.3			
BDC-101	4/28/2004	722											<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0											
BDC-101	10/18/2004	895											0.64	10	<1.0	15	43	<1.0	43											
BDC-101	5/10/2005	1099											<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0											
BDC-101	11/10/2005	1283											0.25	7.6	<1.0	2.6	42	<1.0	42		0.96	4.4			34.3		259	2.05		
BDC-101	5/15/2006	1469											<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		2.78	17.8	0.059	0.0	64.1		80			
BDC-101	11/20/2006	1658	-59										1.1	10	<1.0	15	72.0	<1.0	72		0.92	0.122	0.016	2.4	8.7		174			
BDC-101	2/20/2007	1750	33										<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		2.39	15.0	0.047	0.2	50.0		277		6.63	
BDC-101	3/19/2007	1777	60										<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		5.97	8.83	0.037	0.5	38.5		213		6.60	
BDC-101	4/24/2007	1813	96										<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		3.09	9.59	0.041	0.5	34.1		136		6.46	
BDC-101	5/17/2007	1836	119										<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		2.35	9.95	0.046	0.4	35.7		297		6.55	
BDC-101	11/26/2007	2029	312										<0.25	<1.0	<1.0	2.1	6.5	<1.0	6.5		2.30	5.88	0.032	0.0	26.8		287			
BDC-101	2/18/2008	2113	396	-8									<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		3.55	8.10	0.040	0.0	31.5		341		6.29	
BDC-101	3/27/2008	2151	434	30									<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		3.19	9.3	<0.10	0.2	40.0		506			
BDC-101	5/15/2008	2200	483	79	-40								<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		2.57	6.8	<0.10	0.0	24.6		176		6.44	
BDC-101	7/16/2008	2262	545	141	22								<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		3.34	5.3	<0.10	0.0	21.8		-232		6.52	
BDC-101	9/15/2008	2323	606	202	83	-45							<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		1.22	5.33	0.023	0.0	28.7		153			
BDC-101	11/20/2008	2389	672	268	149	21							0.44	1.6	<1.0	<1.0	<1.0	<1.0	<1.0		1.45	2.9	0.1	0.8	17.1		-22		6.65	
BDC-101	1/16/2009	2446	729	325	206	78							<0.25	1.1	<1.0	<1.0	<1.0	<1.0	<1.0		0	4.40	0.042	0.4	29.5		-245		6.50	
BDC-101	2/11/2009	2472	755	351	232	104							<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		2.62	8.5	<0.1	0.4	39.6		-16		6.43	
BDC-101	3/9/2009	2498	781	377	258	130							<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		0.93	9.4	<0.1	0.0	46.8		54		6.54	
BDC-101	4/16/2009	2536	819	415	296	168							<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		1.69	9.0	<0.1	0.0	36.0		131		6.61	
BDC-101	5/14/2009	2564	847	443	324	196	-34						<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		1.00	13.0	<0.1	0.0	44.4		68		6.81	
BDC-101	7/17/2009	2628	911	507	388	260	30						<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		2.80	12.6	<0.1	0.0	49.0		19		7.17	
BDC-101	9/9/2009	2682	965	561	442	314	84	-49					<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		1.25	6.2	<0.1	0.0	31.7		179		6.90	
BDC-101	11/12/2009	2746	1029	625	506	378	148	15					0.35	1.8	<1.0	6.6	16	<1.0	16		1.37	11.3	<0.1	0.0-0.2	36.7		124		6.53	Very faint iron measurement
BDC-101	2/17/2010	2843	1126	722	603	475	245	112					<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		2.86	13.9	<0.1	0.0	48.7		640		6.55	
BDC-101	5/17/2010	2932	1215	811	692	564	334	201					<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		3.20	20.7	<1.0	0.0	58.7		372		6.86	
BDC-101	8/16/2010	3023	1306	902	783	655	425	292	-37				<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		2.21	15.6	<0.1	0.0	56.9		76		7.21	
BDC-101	11/8/2010	3107	1390	986	867	739	509	376	47				<0.25	2.0	<1.0	<1.0	<1.0	<1.0	<1.0		2.02	2.2	<0.1	0.4	14.7		145		6.97	
BDC-101	2/16/2011	3207	1490	1086	967	839	609	476	147				<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		7.46	23.9	<0.1	0.0	68.2		161		7.30	
BDC-101	5/3/2011	3283	1566	1162	1043	915	685	552	223				<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		5.57	23.7	<0.1	0.0	66.2		208		6.99	
BDC-101	8/1/2011	3373	1656	1252	1133	1005	775	642	313				<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		5.50	17.9	<0.1	0.0	48.1		150		7.07	
BDC-101	11/1/2011	3465	1748	1344	1225	1097	867	734	405	-105			<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0		6.69	6.1	<0.1	0.0	24.8		40		7.23	
BDC-101	2/19/2012	3575	1858	1454	1335	1207	977	844	515	5			<0.25	2.0	<1.0	<1.0	<2.0	<1.0	<2.0		0.53	6.6		0.3	27.7		12		6.81	
BDC-101	5/3/2012	3649	1932	1528	1409	1281	1051	918	589	79			<0.25	<1.0	<1.0	<1.0	<2.0	<1.0	<2.0		3.75	15.9		0.0	51.2		263		6.60	
B																														

**TABLE 1
AOC-05 CLEANUP ACTION SUMMARY
DEVELOPMENTAL CENTER GROUNDWATER MONITORING**

Well	Date	ORC Injection	Pilot Injection	Full Scale Injection 1	Full Scale Injection 2	Full Scale Injection 3	Full Scale Injection 4	Full Scale Injection 5	Full Scale Injection 6	Full Scale Injection 7	Full Scale Injection 8	Full Scale Injection 9	Volatile Organic Compounds (all units in ug/L)						Aquifer Redox Conditions						Donor Indicators		Comments			
		BDC-103	BDC-103	BDC-103/104	BDC-103/104	BDC-103/104	BDC-103/104	BDC-103/104	BDC-103/104	BDC-103	BDC-103	BDC-103	BDC-103	TPH-G (mg/L)	Benzene (µg/L)	Toluene (µg/L)	Ethylbenzene (µg/L)	m,p-Xylene (µg/L)	o-Xylene (µg/L)	Total Xylenes (µg/L)	DO (mg/L)	Nitrate (mg-N/L)	Nitrite (mg-N/L)	Iron II (mg/L)	Sulfate (mg/L)	Methane (µg/L)		ORP (mV)	TOC (mg/L)	pH
Proposed Groundwater Cleanup Levels (a)													0.8	2.0	1294	1.7	NA	NA	1546											
BDC-102	6/11/2001												0.55	5.33	<1.0	<1.0			<1.0											
BDC-102	9/4/2001												0.38	1.61	1.89	<1.0			1.87											
BDC-102	12/3/2001												1.6	3.7	<1.0	<1.0			3.49											
BDC-102	3/13/2002												0.50	1.3	<1.0	<1.0			<1.0											
BDC-102	4/29/2002	-8											0.33	2.6	<1.0	<1.0	1.1	<1.0	1.1											
BDC-102	6/3/2002	27											<0.25	4.4	<1.0	<1.0	<1.0	<1.0	<1.0											
BDC-102	7/1/2002	55											0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0											
BDC-102	8/1/2002	86											<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0											
BDC-102	12/2/2002	209											<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0											
BDC-102	3/10/2003	307											0.26	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0											
BDC-102	6/3/2003	392											<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0											
BDC-102	11/19/2003	561											0.99	120	<1.0	8.5	<1.0	<1.0	<1.0	0.38	0.19	0.011	5.5	46	1100	122.2				
BDC-102	4/28/2004	722											0.40	10	<1.0	<1.0	3.0	<1.0	3.0											
BDC-102	10/18/2004	895											0.33	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0											
BDC-102	5/10/2005	1099											<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0											
BDC-102	11/10/2005	1283											<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	0.82	4.4			34.0		122	18.4			
BDC-102	5/15/2006	1469											<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	2.21	4.72	0.175	2.2	35.7		-11				
BDC-102	11/20/2006	1658	-59										<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.25	<0.250	<0.250	2.2	9.2		163				
BDC-102	2/20/2007	1750	33										<0.25	5.8	<1.0	<1.0	<1.0	<1.0	<1.0	0.47	0.749	0.027	3.0	25.3		-145	6.54			
BDC-102	3/19/2007	1777	60										<0.25	18	<1.0	<1.0	32	<1.0	32	0.88	0.938	0.072	3.0	31.0		-98	6.67			
BDC-102	4/24/2007	1813	96										0.53	6.1	<1.0	3.1	100	<1.0	100	1.20	1.94	0.051	2.8	40.4		-93	6.51			
BDC-102	5/17/2007	1836	119										<0.25	1.8	<1.0	<1.0	7.4	<1.0	7.4	0.84	2.78	0.108	2.6	33.9		286	6.52			
BDC-102	11/26/2007	2029	312										<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	3.29	1.03	0.247	3.0	55.7		46				
BDC-102	2/18/2008	2113	396	-8									<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	2.51	3.91	0.054	2.8	42.8		431	5.97			
BDC-102	3/27/2008	2151	434	30									<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.85	1.3	<0.10	2.5	17.9		233				
BDC-102	5/15/2008	2200	483	79	-40								<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	2.40	3.0	<0.10	3.5	19.2		-115	6.56			
BDC-102	7/16/2008	2262	545	141	22								<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	2.46	2.5	<0.10	3.2	13.7		-312	6.67			
BDC-102	9/15/2008	2323	606	202	83	-45							<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.22	4.28	0.056	3.0	31.6		191				
BDC-102	11/20/2008	2389	672	268	149	21							<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	0.70	0.40	<0.10	2.0	5.6		-70	6.69			
BDC-102	1/16/2009	2446	729	325	206	78							<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	0.00	<0.100	0.200	2.5	8.3		-235	6.70			
BDC-102	2/11/2009	2472	755	351	232	104							<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.65	2.4	<0.1	3.0	20.4		-70	6.61			
BDC-102	3/9/2009	2498	781	377	258	130							<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	0.00	0.9	<0.1	3.0	8.7		-46	6.65			
BDC-102	4/16/2009	2536	819	415	296	168							<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	0.30	0.6	<0.1	3.0	8.3		-7	6.66			
BDC-102	5/14/2009	2564	847	443	324	196	-34						<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	0.29	0.9	<0.1	3.4	9.8		-35	6.78			
BDC-102	7/17/2009	2628	911	507	388	260	30						<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	0.66	4.9	<0.1	2.2	28.6		-11	6.46			
BDC-102	9/9/2009	2682	965	561	442	314	84	-49					<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	0.91	0.4	<0.1	2.7	5.5		2.8	6.66			
BDC-102	11/12/2009	2746	1029	625	506	378	148	15					<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	0.93	0.2	<0.1	3.2	2.4		-42.0	6.49			
BDC-102	2/17/2010	2843	1126	722	603	475	245	112					<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	0.90	3.4	0.2	2.8	17.2		892	6.56			
BDC-102	5/17/2010	2932	1215	811	692	564	334	201					<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.35	8.4	<1.0	3.0	30.1		440	6.61			
BDC-102	8/16/2010	3023	1306	902	783	655	425	292	-37				<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.61	8.9	<0.1	3.0	27.8		82	6.60			
BDC-102	11/8/2010	3107	1390	986	867	739	509	376	47				<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	2.34	0.4	<0.1	2.0	6.9		45	7.09			
BDC-102	2/16/2011	3207	1490	1086	967	839	609	476	147				<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	3.68	3.5	<0.1	2.2	43.3		399	6.88			
BDC-102	5/3/2011	3283	1566	1162	1043	915	685	552	223				<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.60	12.1	<0.1	2.0	32.4		40	6.70			
BDC-102	8/1/2011	3373	1656	1252	1133	1005	775	642	313				<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	7.01	13.6	<0.1	2.1	28.7		11	6.88			
BDC-102	11/1/2011	3465	1748	1344	1225	1097	867	734	405	-105			<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	3.45	9.8	<0.1	1.5	30.9		-48	7.19			
BDC-102	2/19/2012	3575	1858	1454	1335	1207	977	844	515	5			<0.25	<1.0	<1.0	<1.0	<2.0	<1.0	<2.0	0.25	2.4		1.0	15.4		21	6.60			
BDC-102	5/3/2012	3649	1932	1528	1409	1281	1051	918	589	79			<0.25	<1.0	<1.0	<1.0	<2.0	<1.0	<2.0	0.22	11.3		2.5	40.2		248	6.44			
BDC-102	9/4/2012	3773	2056	1652	1533	1405	1175	1042	713	203	-49		<0.25	<1.0	<1.0	<1.0	<2.0	<1.0	<2.0	0.20	13.2	<5.0	1.5	39.						

**TABLE 1
AOC-05 CLEANUP ACTION SUMMARY
DEVELOPMENTAL CENTER GROUNDWATER MONITORING**

Well	Date	ORC Injection	Pilot Injection	Full Scale Injection 1	Full Scale Injection 2	Full Scale Injection 3	Full Scale Injection 4	Full Scale Injection 5	Full Scale Injection 6	Full Scale Injection 7	Full Scale Injection 8	Full Scale Injection 9	Volatile Organic Compounds (all units in ug/L)						Aquifer Redox Conditions						Donor Indicators		Comments		
		BDC-103	BDC-103	BDC-103/104	BDC-103/104	BDC-103/104	BDC-103/104	BDC-103/104	BDC-103/104	BDC-103	BDC-103	BDC-103	BDC-103	TPH-G (mg/L)	Benzene (ug/L)	Toluene (ug/L)	Ethylbenzene (ug/L)	m,p-Xylene (ug/L)	o-Xylene (ug/L)	Total Xylenes (ug/L)	DO (mg/L)	Nitrate (mg-N/L)	Nitrite (mg-N/L)	Iron II (mg/L)	Sulfate (mg/L)	Methane (ug/L)		ORP (mV)	TOC (mg/L)
Proposed Groundwater Cleanup Levels (a)													0.8	2.0	1294	1.7	NA	NA	1546										
BDC-103	6/11/2001												177	875	12,010	1,985			11,430										
BDC-103	9/4/2001												123	494	3,760	419			2,636										
BDC-103 (b)	12/3/2001												120	5,100	2,300,000	10,000			3,400,000										
BDC-103	3/13/2002												200	1,700	17,000	4,900			26,400										
BDC-103	4/29/2002	-8											200	980	16,000	5,400	20,000	7,000	27,000										
BDC-103	6/3/2002	27											200	960	17,000	5,100	20,000	7,100	27,100										
BDC-103	7/1/2002	55											240	1,300	16,000	5,200	20,000	6,800	26,800										
BDC-103	8/1/2002	86											270	4,600	18,000	5,200	19,000	6,600	25,600										
BDC-103	12/2/2002	209											250	1,400	15,000	5,000	22,000	6,900	28,900										
BDC-103	3/10/2003	307											180	780	13,000	5,200	20,000	6,700	26,700										
BDC-103	6/3/2003	392											220	900	10,000	5,000	20,000	6,600	26,600										
BDC-103	11/19/2003	561											180	850	8,300	4,500	18,000	5,500	23,500	0.38	0.012	0.011	5.5	53	630	-75.9			
BDC-103	4/28/2004	722											160	1,600	6,600	3,900	16,000	5,100	21,100										
BDC-103	10/18/2004	895											140	2,100	5,500	3,700	15,000	4,400	19,400										
BDC-103	5/10/2005	1099											110	2,200	5,500	3,800	14,000	3,200	17,200										
BDC-103	11/10/2005	1283											90	2,200	3,500	3,700	12,000	2,500	15,000	0.72	<1.0			11.9		147	15.4		
BDC-103	5/15/2006	1469											84	1,600	3,800	3,100	10,000	2,200	12,000	0.92	<0.010	0.054	3.5	15.2		106			
BDC-103	11/20/2006	1658	-59										51	2,000	730	2,200	3,900	1,000	4,900	1.23	<0.10	<0.10	2.4	28.3		202			
BDC-103	2/20/2007	1750	33										26	460	420	140	3,600	1,600	5,200	0.31	60.8	11.1	0.5	99.2		109	6.54		
BDC-103	3/19/2007	1777	60										30	490	88	130	3,500	1,700	5,200	0.63	27.9	8.28	0.4	141		4	6.79		
BDC-103	4/24/2007	1813	96										36	820	440	220	3500	1800	5300	0.84	7.54	3.56	2.4	59.2		-14	6.70		
BDC-103	5/17/2007	1836	119										77	1,400	4,300	1,100	8,300	3,200	11,500	0.61	0.138	0.079	3.6	169		244	6.82		
BDC-103	11/26/2007	2029	312										190	3,300	21,000	4,000	11,000	4,900	15,900	3.37	0.063	0.049	3.6	49.1		-118			
BDC-103	2/18/2008	2113	396	-8									66	1,100	2,600	700	7,500	1,900	9,400	2.06	7.75	0.134	2.8	163		552	5.97		
BDC-103	3/27/2008	2151	434	30									84	1,500	1,900	1,100	9,700	3,000	12,700	1.60	54.1	18	4.0	115.0		182			
BDC-103	5/15/2008	2200	483	79	-40								91	2,700	4,400	1,400	11,000	3,600	14,600	1.38	<0.10	<0.10	3.2	192		-138	7.11		
BDC-103	7/16/2008	2262	545	141	22								79	1,800	440	490	10,000	3,100	13,100	1.61	56.1	16.6	2.8	149		-226	6.72		
BDC-103	9/15/2008	2323	606	202	83	-45							110	2,300	7,600	1,500	10,000	3,600	13,600	0.48	0.330	0.218	3.2	218		189			
BDC-103	11/20/2008	2389	672	268	149	21							47	1,200	260	110	7,000	2,100	9,100	0.21	152	12.5	2.0	120		-1.2	6.66		
BDC-103	1/16/2009	2446	729	325	206	78							11	190	220	12	1,000	480	1,480	0.24	193	2.32	0.6	62.5		-181	6.19		
BDC-103	2/11/2009	2472	755	351	232	104							36	820	510	<100	2,900	1,500	4,400	1.66	82.0	6.7	0.8	178		-65	6.69		
BDC-103	3/9/2009	2498	781	377	258	130							27	1100	440	18	2,400	1,200	3,600	0	47.3	2.4	0.4	192		17	6.80		
BDC-103	4/16/2009	2536	819	415	296	168							30	710	310	<50	2,700	1,200	3,900	0.95	64.8	5.6	0.2-0.4	194		62	6.77		
BDC-103	5/14/2009	2564	847	443	324	196	-34						30	680	320	20	2,400	1,500	3,900	0.48	49.8	4.8	0.8	222		20	6.85		
BDC-103	7/17/2009	2628	911	507	388	260	30						19	410	280	32	630	1,000	1,630	2.60	26.6	2.0	1.0	104		29	6.98		
BDC-103	9/9/2009	2682	965	561	442	314	84	-49					21	620	270	83	700	1200	1,900	0.88	<0.1	<0.1	2.5	134		2.8	7.01		
BDC-103	11/12/2009	2746	1029	625	506	378	148	15					24	340	140	27	1,800	1,200	3,000	1.42	94.1	7.7	0.4	71.7		117	6.11		
BDC-103	2/17/2010	2843	1126	722	603	475	245	112					0.73	10	<1.0	<1.0	3.1	22	25	1.45	123	1.1	0.0	60.3		939	6.22		
BDC-103	5/17/2010	2932	1215	811	692	564	334	201					3.1	79	44	5.2	60	86	146	1.56	67.9	2.6	0.4	71.6		436	6.63		
BDC-103	8/16/2010	3023	1306	902	783	655	425	292	-37				8.0	740	380	110	420	320	740	2.24	2.4	0.1	2.0	72.5		184	6.96		
BDC-103	11/8/2010	3107	1390	986	867	739	509	376	47				6.3	240	11	1.7	180	540	720	7.46	55.8	1.5	0.0	123		199	7.05		
BDC-103	2/16/2011	3207	1490	1086	967	839	609	476	147				0.28	4.6	<1.0	<1.0	<1.0	5.4	5.4	5.18	133	0.6	74.6		508	6.52			
BDC-103	5/3/2011	3283	1566	1162	1043	915	685	552	223				<0.25	9.1	<1.0	<1.0	<1.0	2.2	2.2	2.15	140	0.2	0.0	74.4		393	6.35		
BDC-103	8/1/2011	3373	1656	1252	1133	1005	775	642	313				0.30	76	<1.0	1.8	7.8	2.5	10.3	5.67	57.6	<0.1	0.2	63.2		168	7.09		
BDC-103	11/1/2011	3465	1748	1344	1225	1097	867	734	405	-105			33	1300	2200	780	2300	1300	3,600	1.72	<0.1	<0.1	1.2	8.1		-226	7.38		
BDC-103	2/19/2012	3575	1858	1454	1335	1207	977	844	515	5			2.2	5.1	31	19	260	69	329	0.21	143	0.3	57.1		36	6.41			
BDC-103	5/3/2012	3649	1932	1528	1409	1281	1051	918	589	79			<0.25	16	1.4	<1.0	3.6	14	17.6	0.11	149	0.83	0.0	56.2		239	6.49		
BDC-103	9/4/2012	3773	2056	1652	1533	1405	1175	1042	713	203	-49		0.72	530	24.0	9.4	40	42	82	0.45	7.2	<0.10	0.4	66.9		146	6.80		
BDC-103	11/13/2012	3843	2126	1722	1603	1475	1245	1112	783	273	21		4.5	120	9.5	3.7	210	380	590	1.02	165	2.8	0.4	93.6		108	6.50		
BDC-103	2/20/2013	3942	2225	1821	1702	1574	1344	1211	882	372	120		<0.25	<1.0	<1.0	<1.0	<2.0	3.4	3.4	0.14	161	0.60	0.2	51.6		109	6.42		
BDC-103	5/20/2013	4031	2314	1910	1791	1663	1433	1300	971	461	209		<0.25	9.3	<1.0	<1.0	4.4	1.8	6.2	0.29	161	<0.10	0.0	47.1		-281	7.47		
BDC-103	8/28/2013	4131	2414	2010	1891	1763	1533	1400	1071	561	309	-76	2	210	56	47	260	91	351	1.60	17.8	0.16	0.6	54.2		-290	6.83		
BDC-103	11/19/2013	4214	2497	2093	1974	1846	1616	1483	1154	644	392	7	5.9	22	37	31	590	350	940	4.42	154	2.6	0.0	51.0		-222	6.48		
BDC-103	2/11/2014	4298	2581	2177	2058	1930	1700	1567	1238	728	476	91	<0.25	<1.0	<1.0														

**TABLE 1
AOC-05 CLEANUP ACTION SUMMARY
DEVELOPMENTAL CENTER GROUNDWATER MONITORING**

Well	Date	ORC	Pilot	Full Scale	Full Scale	Full Scale	Full Scale	Full Scale	Full Scale	Full Scale	Full Scale	Full Scale	Volatile Organic Compounds (all units in ug/L)						Aquifer Redox Conditions					Donor Indicators		Comments		
		BDC-103	BDC-103	BDC-103/104	BDC-103/104	BDC-103/104	BDC-103/104	BDC-103/104	BDC-103	BDC-103	BDC-103	BDC-103	TPH-G	Benzene	Toluene	Ethylbenzene	m,p-Xylene	o-Xylene	Total Xylenes	DO	Nitrate	Nitrite	Iron II	Sulfate	Methane		ORP	TOC
		Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	(mg/L)	(ug/L)	(ug/L)	(ug/L)	(ug/L)	(ug/L)	(mg/L)	(mg-N/L)	(mg-N/L)	(mg/L)	(mg/L)	(ug/L)	(mV)	(mg/L)		
Proposed Groundwater Cleanup Levels (a)													0.8	2.0	1294	1.7	NA	NA	1546									
BDC-104	2/18/2008	2113	396	-8									2.9	<1.0	<1.0	47	180	28	208	2.09	1.63	0.072	3.0	18.7		598		
BDC-104	3/27/2008	2151	434	30									3.2	<1.0	<1.0	22	220	52	272	1.34	161	0.1	0.5	52.2		259		
BDC-104	5/15/2008	2200	483	79	-40								1.0	<1.0	<1.0	7.0	26	22	48	1.24	28.7	0.7	0.4	26.6		94	6.69	
BDC-104	7/16/2008	2262	545	141	22								2.3	<1.0	2.9	3.3	110	50	160	1.56	196	0.4	0.0	74.7		-221	7.17	
BDC-104	9/15/2008	2323	606	202	83	-45							0.64	<1.0	2.6	<1.0	20	16	36	0.06	122	0.729	0.0	38.4		191		
BDC-104	11/20/2008	2389	672	268	149	21							<0.25	<1.0	<1.0	<1.0	1.4	4.1	5.5	0.96	67.2	<0.10	0.2	24.3		-27	7.46	
BDC-104	1/16/2009	2446	729	325	206	78							0.26	<1.0	<1.0	<1.0	<1.0	5.5	5.5	0.05	71.4	0.204	0.6	34.6		-164	6.86	
BDC-104	2/11/2009	2472	755	351	232	104							<0.25	<1.0	<1.0	<1.0	1.3	1.1	2.4	1.78	95.4 J	0.1	0.2	20.1		-75	6.68	
BDC-104	3/9/2009	2498	781	377	258	130							<0.25	<1.0	<1.0	<1.0	1.3	1.1	2.4	0	91.5	<0.1	0.0	19.2		20	6.67	
BDC-104	4/16/2009	2536	819	415	296	168							<0.25	<1.0	<1.0	<1.0	<1.0	1.6	1.6	0.34	67.2	<0.1	0.0	21.6		67	6.63	
BDC-104	5/14/2009	2564	847	443	324	196	-34						<0.25	<1.0	<1.0	<1.0	<1.0	1.4	1.4	0.51	63.4	<0.1	0.0	20.1		6	6.70	
BDC-104	7/17/2009	2628	911	507	388	260	30						<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	1.41	21.0	0.5	1.0	30.8		-3	7.30		
BDC-104	9/9/2009	2682	965	561	442	314	84	-49					<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	0.63	39.8	0.1	0.8	41.6		61	7.20		
BDC-104	11/12/2009	2746	1029	625	506	378	148	15					<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	0.99	115	1.4	0.0	24.1		68	6.49		
BDC-104	2/17/2010	2843	1126	722	603	475	245	112					<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	0.73	119	0.1	0.0	111		868	6.93		
BDC-104	5/17/2010	2932	1215	811	692	564	334	201					<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	0.98	47.4	<1.0	0.6	30.5		482	6.74		
BDC-104	8/16/2010	3023	1306	902	783	655	425	292	-37				<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	1.59	38.4	0.2	2.5	23.6		76	6.92		
BDC-104	11/8/2010	3107	1390	986	867	739	509	376	47				<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	2.87	32.5	<0.1	0.0	18.6		115	7.23		
BDC-104	2/16/2011	3207	1490	1086	967	839	609	476	147				<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	3.48	40.0	<0.1	0.4	24.1		423	6.71		
BDC-104	5/3/2011	3283	1566	1162	1043	915	685	552	223				<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	1.19	31.3	<0.1	1.2	26.8		231	6.63		
BDC-104	8/1/2011	3373	1656	1252	1133	1005	775	642	313				<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	2.10	11.7	<0.1	0.0	21.2		121	7.20		
BDC-104	11/1/2011	3465	1748	1344	1225	1097	867	734	405	-105			<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	1.43	14.6	<0.1	0.0	18.7		-53	7.40		
BDC-104	2/19/2012	3575	1858	1454	1335	1207	977	844	515	5			<0.25	<1.0	<1.0	<1.0	<2.0	<1.0	<2.0	0.26	21.6		0.0	29.2		66	6.23	
BDC-104	5/3/2012	3649	1932	1528	1409	1281	1051	918	589	79			<0.25	<1.0	<1.0	<1.0	<2.0	<1.0	<2.0	0.06	19.4		1.5	26.5		207	6.78	
BDC-104	9/4/2012	3773	2056	1652	1533	1405	1175	1042	713	203	-49		<0.25	<1.0	<1.0	<1.0	<2.0	<1.0	<2.0	0.68	12.3	<0.10	0.5	22.1		130	7.11	
BDC-104	11/13/2012	3843	2126	1722	1603	1475	1245	1112	783	273	21		<0.25	<1.0	<1.0	<1.0	<2.0	<1.0	<2.0	0.24	0.80	<0.10		5.1		64	7.19	
BDC-104	2/20/2013	3942	2225	1821	1702	1574	1344	1211	882	372	120		0.28	<1.0	6.5	<1.0	17	3.3	20.3	0.44	2.5	<0.10	0.2	3.6		82	6.96	
BDC-104	5/20/2013	4031	2314	1910	1791	1663	1433	1300	971	461	209		<0.25	<1.0	<1.0	<1.0	<2.0	<1.0	<2.0	2.01	20.0	<0.10	0.0	20.8		-230	7.16	
BDC-104	8/28/2013	4131	2414	2010	1891	1763	1533	1400	1071	561	309	-76	<0.25	<1.0	<1.0	<1.0	<2.0	<1.0	<2.0	0.52	16.4	<0.10	1.0	35.3		-322	6.82	
BDC-104	11/19/2013	4214	2497	2093	1974	1846	1616	1483	1154	644	392	7	<0.25	<1.0	<1.0	<1.0	<2.0	<1.0	<2.0	8.09	0.47	<0.10	0.0	3.1		-35	7.16	
BDC-104	2/11/2014	4298	2581	2177	2058	1930	1700	1567	1238	728	476	91	<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	6.11	0.54	<0.10	0.0	3.4		-135	7.04		
BDC-104	5/6/2014	4382	2665	2261	2142	2014	1784	1651	1322	812	560	175	<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	8.49	0.35	<0.10	0.0	4.2		-113	6.82		
BDC-104	8/7/2014	4475	2758	2354	2235	2107	1877	1744	1415	905	653	268	<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	3.04	2.9	<0.10	0.0	4.4		64	7.44		
BDC-104	11/4/2014	4564	2847	2443	2324	2196	1966	1833	1504	994	742	357	<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	2.66	2.1	<0.10	0.0	10.1		39	6.50		
BDC-104	1/21/2015	4642	2925	2521	2402	2274	2044	1911	1582	1072	820	435	<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	4.02	11.3	<0.10	0.0	36.3		135	6.87		
TPH-G = Total Petroleum Hydrocarbon-Gasoline												Injection dates																
DO = Dissolved Oxygen												5/7/2002		ORC														
ORP = Oxidation Reduction Potential												1/18/2007		Pilot -scale nitrate														
TOC = Total Organic Carbon												2/26/2008		1st full scale injection														
NA = Not Applicable, not available												6/24/2008		2nd full scale injection														
ug/L = micrograms pr liter												10/30/2008		3rd full scale injection														
mg/L = milligrams per liter												6/17/2009		4th full scale injection (start ammonium phosphate, 1/3 ammonium nitrate dose to both wells)														
mV = millivolts												10/28/2009		5th full scale injection (103 full dose, 104 half dose)														
NA = Not Analyzed												9/22/2010		6th full scale injection (103 only full dose)														
= No sample collected or sample not analyzed for specified constituent.												2/14/2012		7th full scale injection (103 only full dose)														
												10/23/2012		8th full scale injection (103 only 1.5x volume dose)														
Box = Exceedance of proposed CUL												11/12/2013		9th full scale injection (103 only 1.5x volume dose)														
(a) Proposed Cleanup Standards and Comparison to Site Data, Boeing Developmental Center, Tukwila, Washington (Landau Associates, 5/7/13).																												
(b) BTEX data questionable for this event. Concentrations inconsistent with TPH-G data for indicated event and BTEX data from other events.																												
2/19/12 = LLI 1290767, 1291164																												

**TABLE 2
REMEDIATION PROGRESS SUMMARY AND KEY MILESTONES
AOC-5 BIOREMEDIATION REMEDIAL ACTION
BOEING DEVELOPMENTAL CENTER**

	2008				2009				2010				2011				2012				2013				2014				2015
	Quarter				Quarter				Quarter				Quarter				Quarter				Quarter								
	1	2	3	4	1	2	3	4	1	2	3	4	1	2	3	4	1	2	3	4	1	2	3	4	1	2	3	4	1
BDC-101																													
TPH-G																													
Benzene																													
Toluene																													
Ethylbenzene																													
Total Xylenes																													
BDC-102																													
TPH-G																													
Benzene																													
Toluene																													
Ethylbenzene																													
Total Xylenes																													
BDC-103	NI	NI	NI		NI	NI				NI						NI		NI				NI							
TPH-G																													
Benzene																													
Toluene																													
Ethylbenzene																													
Total Xylenes																													
BDC-104	NI	NI	NI		NI	NI																							
TPH-G																													
Benzene																													
Toluene																													
Ethylbenzene																													
Total Xylenes																													

■ - Contaminant concentration greater than proposed cleanup level.
■ - Contaminant concentration less than the proposed clean up level, but greater than the laboratory reporting limit.
■ - Contaminant concentration less than the laboratory reporting limit.

NI - Nitrate injection at the specified well.
 ↓ - The specified contaminant reaches historic lows.

* - Key milestones, described below

- 2010, 1st Quarter - Concentrations of TPH-G and benzene fall below screening levels for the first time since monitoring began in 2001.
- 2011, 1st Quarter - Concentrations of all contaminants reach historic lows in BDC-103. All contaminant concentrations are below screening levels in all four wells.
- 2011, 2nd Quarter - The TPH-G concentration in BDC-103 falls below the laboratory reporting limits for the first time since monitoring began in 2001.
- 2011, 4th Quarter - Contaminant concentrations rebound due to a high groundwater table, prompting additional injection.
- 2013, 1st Quarter - Contaminant concentrations were all below reporting limits at BDC-103, with the exception of low-level detections of total xylenes; lowest concentrations since monitoring began in 2001.
- 2014, 1st Quarter - Contaminant concentrations were all below reporting limits at BDC-103, with the exception of low-level detections of total xylenes; the second time this has occurred since monitoring began in 2001.
- 2014, 2nd Quarter - Contaminants are below laboratory reporting limits for in all four wells for the first time since monitoring began in 2001.
- 2014, 3rd Quarter - Concentrations of benzene and total xylenes in BDC-103 rebound slightly due to a historically shallow groundwater table.
- 2014, 4th Quarter - All contaminant concentrations in all four wells return to below laboratory reporting limits.

**TABLE 3
NITRATE CONCENTRATIONS AT DOWNGRADIENT MONITORING LOCATIONS
AOC-05 ANAEROBIC BIOREMEDIATION REMEDIAL ACTION
BOEING DEVELOPMENTAL CENTER**

Area	Well	Date		Aquifer Redox Conditions					
				DO (mg/L)	Nitrate (mg-N/L)	Iron II (mg/L)	Sulfate (mg/L)	Methane (mg/L)	ORP (mV)
SWMU-17	BDC-05-04	5/15/2006	Natural Redox Baseline		12.3	2.6	33.4		
SWMU-17	BDC-05-04	10/23/2008		2.45	7.6	0.1	31.0	0.29	73.5
SWMU-17	BDC-05-04	11/2/2008		0.59	4.5	0.8	25.2	0.05	-16
SWMU-17	BDC-05-04	12/16/2008		0.55	5.5	1.0	30.4	1.61	-98
SWMU-17	BDC-05-04	1/16/2009		0.06	4.3	1.0	21.8	1.48	-192
SWMU-17	BDC-05-04	2/11/2009		2.45	5.9	1.0	31.8	1.06	-54
SWMU-17	BDC-05-04	3/9/2009		0.27	4.8	1.5	30.1	0.20	35
SWMU-17	BDC-05-04	4/16/2009		1.48	5.9	1.4	33.6	<0.0007	68
SWMU-17	BDC-05-04	5/13/2009		0.33	4.5	1.6	26.6	0.37	49
SWMU-17	BDC-05-04	8/16/2009		0.86	5.4	2.2	30.6	<0.0007	93
SWMU-17	BDC-05-04	11/13/2009	Downgradient Monitoring Triggered	0.56	2.2	3.0	18.4	2.44	109
SWMU-17	BDC-05-04	2/16/2010		0.88	<0.1	3.3	24.6	1.49	899
SWMU-17	BDC-05-04	5/18/2010		0.75	<0.1	3.0	25.4	1.32	473
SWMU-17	BDC-05-04	8/17/2010		1.00	<0.1	2.8	17.1	3.53	108
SWMU-17	BDC-05-04	11/9/2010		2.21	<0.1	2.2	21.3	3.00	101
SWMU-17	BDC-05-04	2/15/2011		2.50	<0.1	2.4	19.4	4.46	93
SWMU-17	BDC-05-04	5/2/2011		1.69	<0.1	2.2	18.0	1.75	49
SWMU-17	BDC-05-04	11/2/2011		1.52	<1.0	1.2	<1.0		-3
SWMU-17	BDC-05-04	5/7/2012		0.16		2.0	21.5		98
SWMU-17	BDC-05-04	9/4/2012		0.21	<0.10		16.6		96
SWMU-17	BDC-05-04	11/13/2012		0.03	<0.10	1.8	16.9		64
SWMU-17	BDC-05-04	5/23/2013		0.49		1.5	13.7		-310
SWMU-17	BDC-05-04	11/19/2013		2.56	<0.10	1.0	13.2		-259
SWMU-17	BDC-05-04	5/6/2014		3.49	0.40		14.4		-299
SWMU-17	BDC-05-04	11/4/2014		0.05	<0.10	1.6	<1.0		-126
SWMU-20	MW-17A	05/15/2006	Natural Redox Baseline		1.37	0.0	27.0		
SWMU-20	MW-17A	11/12/2009	Downgradient Monitoring Triggered		0.9				
SWMU-20	MW-17A	5/17/2010			1.6	0.2	21.0		
SWMU-20	MW-17A	11/8/2010			0.1	2.1	15.7		
SWMU-20	MW-17A	5/3/2011			1.6	0.0	19.8		
SWMU-20	MW-17A	8/1/2011			0.5	0.0	20.5		
SWMU-20	MW-17A	11/1/2011			0.3	0.0	23.2		
SWMU-20	MW-17A	5/3/2012			4.4	0.0			
SWMU-20	MW-17A	9/4/2012			2.0		26.8		
SWMU-20	MW-17A	11/13/2012			0.59	0.0	22.9		
SWMU-20	MW-17A	5/20/2013			2.9		26.8		
SWMU-20	MW-17A	11/19/2013			1.3	0.4	23.9		
SWMU-20	MW-17A	5/6/2014			2.2	0.0	23.7		
SWMU-20	MW-17A	11/4/2014			0.16	0.4	26.0		
SWMU-20	MW-18A	05/15/2006	Natural Redox Baseline		0.154	0.4	64.8		
SWMU-20	MW-18A	11/12/2009	Downgradient Monitoring Triggered		0.8				
SWMU-20	MW-18A	05/17/2010			1.0	0.4	32.2		
SWMU-20	MW-18A	11/08/2010			0.1	0.0	14.2		
SWMU-20	MW-18A	5/3/2011			<0.1	0.0	31.5		
SWMU-20	MW-18A	8/1/2011			1.1	0.0	42.2		
SWMU-20	MW-18A	11/1/2011			0.7	0.0	93.3		
SWMU-20	MW-18A	5/3/2012			<0.10	0.0			
SWMU-20	MW-18A	9/4/2012			<0.10		19.5		
SWMU-20	MW-18A	11/13/2012			<0.10	0.0	21.5		
SWMU-20	MW-18A	5/20/2013			<0.10		19.6		
SWMU-20	MW-18A	11/19/2013			<0.10	0.6	15.0		
SWMU-20	MW-18A	5/6/2014			<0.10	0.0	26.1		
SWMU-20	MW-18A	11/4/2014			<0.10	0.4	21.0		
SWMU-20	MW-21A	05/15/2006	Natural Redox Baseline		0.136	0.4	54.9		
SWMU-20	MW-21A	11/12/2009	Downgradient Monitoring Triggered		<0.1				
SWMU-20	MW-21A	05/17/2010			0.2	0.0	11.9		
SWMU-20	MW-21A	11/08/2010			<0.1	0.0	5.9		
SWMU-20	MW-21A	5/3/2011			0.2	0.0	52.1		
SWMU-20	MW-21A	8/1/2011			0.1	0.0	26.7		
SWMU-20	MW-21A	11/1/2011			<0.1	0.0	9.3		
SWMU-20	MW-21A	5/3/2012			0.17	0.0			
SWMU-20	MW-21A	9/4/2012			<0.10		6.7		
SWMU-20	MW-21A	11/13/2012			0.16	0.0	18.5		
SWMU-20	MW-21A	5/20/2013			0.10	0.5	13.5		
SWMU-20	MW-21A	11/19/2013			<0.10	0.0	15.6		
SWMU-20	MW-21A	5/6/2014			<0.10	0.0	7.6		
SWMU-20	MW-21A	11/4/2014			<0.10	0.0	5.1		
= Not Analyzed									