



October 7, 2014

Byung Maeng  
Washington State Department of Ecology  
Northwest Regional Office  
3190 160th Avenue SE  
Bellevue WA 98008-5452

**RE: MAY 2014 SEMIANNUAL GROUNDWATER MONITORING REPORT  
BOEING DEVELOPMENTAL CENTER, TUKWILA, WASHINGTON**

Dear Byung:

This letter and attached data constitutes the semiannual letter report for groundwater monitoring at The Boeing Company Developmental Center in Tukwila, WA. The report covers the period following the November 2013 semiannual sampling event (and corresponding report) through the semiannual event in May 2014. This report provides a brief summary of the data and of remedial activities performed at the site during the reporting period. Remedial actions are underway in Solid Waste Management Unit (SWMU)-20, SWMU-17, and Area of Concern (AOC)-05. All other SWMUs and AOCs identified in the 1994 RFA have been excluded from further investigation based on determinations that they do not pose a threat to human health or the environment.

Groundwater monitoring during the reporting period was performed in February and May 2014 at SWMU-17 and AOC-05; and in May 2014 at SWMU-20 wells. Analytical data for SWMU-20, SWMU-17, and AOC-05 are enclosed for your review and include sample results summary tables and laboratory data packages. Summary figures, historical analytical summary data, and volatile organic compounds (VOCs) concentration trend charts are provided for key constituents present in SWMU-20. Included for AOC-05 are a well location figure; cumulative tables for total petroleum hydrocarbons (TPH); benzene, toluene, ethylbenzene, and xylenes (BTEX); and conventional parameters; as well as trend plots for TPH-Gasoline (TPH-G) and BTEX, and nitrate. A well location figure and tables of current data and cumulative data are provided for SWMU-17. Summary tables include proposed cleanup levels (CULs) from the May 7, 2013 *Proposed Cleanup Standards and Comparison to Site Data* document.

At SWMU-20, *in situ* anaerobic bioremediation continues for treatment of tetrachloroethene (PCE), trichloroethene (TCE), and breakdown products following the last electron donor injection performed in August 2008. Groundwater monitoring results indicate that enhanced treatment continues at and near injection wells, as indicated by the persistence of sulfate-reducing to methanogenic aquifer redox conditions, total organic carbon (TOC) levels generally above 10 milligrams per liter (mg/L), and the detection of end product ethane at several wells (see SWMU-20 Cleanup Action Summary – Source Zone table). At all source-zone wells, PCE and TCE remain below reporting limits and breakdown products cis-1,2-dichloroethene (cDCE)

and vinyl chloride (VC) are either below reporting limits or are detected at very low concentrations. cDCE concentrations are below reporting limits or less than 1 micrograms per liter ( $\mu\text{g/L}$ ) at all locations, well below the proposed CUL (134  $\mu\text{g/L}$ ). All VC detections at source zone wells are at or below the proposed CUL (2.4  $\mu\text{g/L}$ ). Following the successful source zone bioremediation that resulted from donor injection to source-zone wells, the highest PCE and TCE concentrations are now present at wells located crossgradient (north) (MW-13A and MW-17A) or upgradient (east) (MW-16A) of the treated source zone and the highest VC concentrations are at downgradient wells (see SWMU-20 Non-Source Zone Wells Summary table). PCE is less than the proposed CUL (5.3  $\mu\text{g/L}$ ) at all wells and TCE detections exceed the proposed CUL (1.4  $\mu\text{g/L}$ ) at only two upgradient or crossgradient wells (MW-16A and MW-17A), at 1.6 to 2.6  $\mu\text{g/L}$ , respectively. The proposed CUL for VC (2.4  $\mu\text{g/L}$ ) is slightly exceeded at downgradient wells MW-10C (2.9  $\mu\text{g/L}$ ) and MW-15C (2.9  $\mu\text{g/L}$ ). Semiannual monitoring will continue in SWMU-20 to evaluate potential source zone rebound and trends at crossgradient wells. Ongoing semiannual groundwater monitoring in SWMU-20 constitutes MNA with enhancement of natural attenuation due to residual effects of prior bioremediation injections. Additional injections within SWMU-20 are not anticipated at this time.

At AOC-05, *in situ* anaerobic bioremediation continues for treatment of TPH-G and BTEX. The ninth injection of nitrate electron acceptor solution took place (at well BDC-103 only) in November 2013. At downgradient wells BDC-101 and BDC-102, and at previously impacted well BDC-104, TPH-G and BTEX remain below reporting limits. At BDC-103, concentrations of TPH-G, benzene, toluene, and ethylbenzene were below reporting limits during both the February and May 2014 sampling events; xylenes were detected in February, but well below the proposed CUL. Nitrate in May at BDC-103 (215 mg/L) remains adequate for continued biotreatment. Nitrate monitoring is also performed at the two nearest downgradient wells and at four wells located farther downgradient. Nitrate concentrations were above the 10 mg/L action level at downgradient wells BDC-101(May) and BDC-102 (February and May). Nitrate continued to be well below the action level at the four wells farther downgradient (BDC-05-04, MW-17A, MW-18A, and MW-21A). Additional nitrate injections will continue, as needed, to treat remaining sorbed- and non-aqueous phase liquid-phase (NAPL) contamination that can lead to a rebound in aqueous-phase concentrations. Groundwater sampling at AOC-05 wells will continue on a quarterly basis to evaluate contaminant treatment and nitrate consumption. As required, semiannual monitoring for nitrate at the four wells farther downgradient will also continue until nitrate remains below 10 mg/L for two consecutive semiannual events at downgradient wells BDC-101 and BDC-102.

At SWMU-17, groundwater monitoring results from February and May 2014 show that *in situ* anaerobic bioremediation continues to be enhanced following the August 2011 electron donor injection. Increases in one or more breakdown or end products (cDCE, VC, and ethene) were observed at all injection wells following injection. In May 2014, PCE, TCE, and cDCE concentrations were below proposed CULs at all wells, with the exception of TCE at crossgradient well BDC-05-18 (2.4  $\mu\text{g/L}$ ), slightly above the proposed CUL of 1.4  $\mu\text{g/L}$ . Final breakdown product VC was present at six wells above the proposed CUL (2.4  $\mu\text{g/L}$ )

in May, compared to nine wells exceeding in November 2013; concentrations for these six wells ranged from 2.6 to 8.6 µg/L. Complete reductive dechlorination beyond VC continues to be indicated by end products ethene and/or ethane, which were detected in May at 15 of 18 wells analyzed. Low sulfate and elevated concentrations of methane persist at most wells, indicating occurrence of the highly reduced aquifer redox conditions required for complete dechlorination. TOC remains elevated at injection wells (9 to 66 mg/L) and adequate for continued biotreatment. Quarterly and semiannual monitoring will continue for evaluation of treatment progress. Additional donor injection within SWMU-17 is not necessary at this time.

Please call or email me if you have any questions or if you would like to discuss any of the sampling results in more detail.

LANDAU ASSOCIATES, INC.



Clinton L. Jacob, P.E., L.G.  
Principal Engineer

CLJ/tam

Enclosures:     Developmental Center Groundwater Monitoring – May 2014  
                  SWMU-20 Data Tables, Maps, and Trend Charts  
                  SWMU-17 Data Tables and Map  
                  AOC-05 Data Table, Trend Charts, and Map  
                  Groundwater Elevation Table  
                  Groundwater Sample Collection Forms and Analytical Data (CD)

cc:           James Bet, Boeing EHS Remediation (elec. w/o data)  
              Susanne McIlveen, Boeing Defense, Space & Security, EHS Manager (elec. w/o data)

***DEVELOPMENTAL CENTER  
GROUNDWATER MONITORING  
MAY 2014***

***DEVELOPMENTAL CENTER  
GROUNDWATER MONITORING  
May 2014***

**SWMU-20 VOC/CONVENTIONALS DATA TABLES**

**SWMU-20 SUMMARY DATA**

- **SWMU-20 VOC SUMMARY MAPS**
- **SWMU-20 ANALYTICAL RESULTS SUMMARY  
(January 1994 through Present)**
- **SWMU-20 VOC CONCENTRATION TREND CHARTS  
(January 1994 through Present)**
- **SWMU-20 CLEANUP ACTION SUMMARY – SOURCE  
ZONE**
- **SWMU-20 CLEANUP ACTION SUMMARY – NON-  
SOURCE ZONE**

**SWMU-20 VOA/CONVENTIONALS DATA  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING  
MAY 2014**

Sample Name:	DC-MW-6A	DC-MW-6B	DC-MW-9A	DC-MW-10A	DC-MW-10C	DC-MW-11A	DC-MW-12A	DC-MW-13A	DC-MW-13A-Dup	DC-MW-13C
Lab SDG:	1473257	1473257	1473257	1473257	1473257	1473257	1473257	1473257	1473257	1473257
Lab Sample ID:	7458251	7458253	7458238	7458236	7458235	7458233	7458234	7458248	7458250	7458249
Sample Date:	5/7/2014	5/7/2014	5/7/2014	5/7/2014	5/7/2014	5/7/2014	5/7/2014	5/7/2014	5/7/2014	5/7/2014
<b>Test ID: VOA SW8260C (µg/L)</b>										
Acetone	5.0 U	5.0 U	50 U	25 U	5.0 U	50 U	5.0 U	5.0 U	5.0 U	25 U
Acrolein	25 UJ	25 UJ	250 UJ	130 UJ	25 UJ	250 UJ	25 UJ	25 UJ	25 UJ	130 UJ
Acrylonitrile	5.0 U	5.0 U	50 U	25 U	5.0 U	50 U	5.0 U	5.0 U	5.0 U	25 U
<b>Benzene</b>	0.2 U	0.2 U	2.0 U	1.0 U	0.2 U	2.0 U	0.2 U	0.2 U	0.2 U	1.0 U
Bromobenzene	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
<b>Bromochloromethane</b>	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
Bromodichloromethane	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
Bromoform	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
Bromomethane	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
2-Butanone	5.0 U	5.0 U	50 U	25 U	5.0 U	50 U	5.0 U	5.0 U	5.0 U	25 U
n-Butylbenzene	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
sec-Butylbenzene	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
tert-Butylbenzene	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
Carbon Disulfide	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 UJ
Carbon Tetrachloride	0.2 U	0.2 U	2.0 U	1.0 U	0.2 U	2.0 U	0.2 U	0.2 U	0.2 U	1.0 U
Chlorobenzene	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
Chloroethane	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
Chloroform	0.2 U	0.2 U	2.0 U	1.0 U	0.2 U	2.0 U	0.2 U	0.5	0.5	1.0 U
Chloromethane	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 UJ	0.5 UJ	2.5 UJ
2-Chlorotoluene	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
4-Chlorotoluene	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
1,2-Dibromo-3-chloropropane	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
Dibromochloromethane	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
Dibromomethane	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
trans-1,4-Dichloro-2-butene	5.0 UJ	5.0 UJ	50 UJ	25 UJ	5.0 UJ	50 UJ	5.0 UJ	5.0 UJ	5.0 UJ	25 U
1,2-Dichlorobenzene	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
1,3-Dichlorobenzene	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
1,4-Dichlorobenzene	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
1,1-Dichloroethane	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
1,2-Dichloroethane	0.2 U	0.2 U	2.0 U	1.0 U	0.2 U	2.0 U	0.2 U	0.2 U	0.2 U	1.0 U
<b>1,1-Dichloroethene</b>	0.2 U	0.2 U	2.0 U	1.0 U	0.2 U	2.0 U	0.2 U	0.2 U	0.2 U	1.0 U
<b>cis-1,2-Dichloroethene</b>	0.4	0.2 U	2.0 U	1.0 U	5.4	19	0.2 U	0.2 U	0.2 U	1.0 U
<b>trans-1,2-Dichloroethene</b>	0.2 U	0.2 U	2.0 U	1.0 U	0.3	2.0 U	0.2 U	0.2 U	0.2 U	1.0 U
1,2-Dichloropropane	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
1,3-Dichloropropane	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
<b>2,2-Dichloropropane</b>	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
1,1-Dichloropropene	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
cis-1,3-Dichloropropene	0.2 U	0.2 U	2.0 U	1.0 U	0.2 U	2.0 U	0.2 U	0.2 U	0.2 U	1.0 U
trans-1,3-Dichloropropene	0.2 U	0.2 U	2.0 U	1.0 U	0.2 U	2.0 U	0.2 U	0.2 U	0.2 U	1.0 U
Ethylbenzene	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
Ethylene Dibromide	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
Hexachlorobutadiene	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
2-Hexanone	5.0 U	5.0 U	50 U	25 U	5.0 U	50 U	5.0 U	5.0 U	5.0 U	25 U
Isopropylbenzene	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
4-Isopropyltoluene	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
Methyl Iodide	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U

**SWMU-20 VOA/CONVENTIONALS DATA  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING  
MAY 2014**

Sample Name:	DC-MW-6A	DC-MW-6B	DC-MW-9A	DC-MW-10A	DC-MW-10C	DC-MW-11A	DC-MW-12A	DC-MW-13A	DC-MW-13A-Dup	DC-MW-13C
Lab SDG:	1473257	1473257	1473257	1473257	1473257	1473257	1473257	1473257	1473257	1473257
Lab Sample ID:	7458251	7458253	7458238	7458236	7458235	7458233	7458234	7458248	7458250	7458249
Sample Date:	5/7/2014	5/7/2014	5/7/2014	5/7/2014	5/7/2014	5/7/2014	5/7/2014	5/7/2014	5/7/2014	5/7/2014
4-Methyl-2-Pentanone (MIBK)	5.0 U	5.0 U	5.0 U	25 U	5.0 U	50 U	5.0 U	5.0 U	5.0 U	25 U
Methylene Chloride	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
<b>Naphthalene</b>	0.5 U	0.5 U	9.9	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
n-Propylbenzene	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
Styrene	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
1,1,1,2-Tetrachloroethane	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
1,1,2,2-Tetrachloroethane	0.2 U	0.2 U	2.0 U	1.0 U	0.2 U	2.0 U	0.2 U	0.2 U	0.2 U	1.0 U
<b>Tetrachloroethene</b>	0.2 U	0.2 U	2.0 U	1.0 U	0.2 U	2.0 U	0.3	3.1	3.4	1.0 U
Toluene	0.2 U	0.2 U	2.0 U	1.0 U	0.2 U	2.0 U	0.2 U	0.2 U	0.2 U	1.0 U
1,1,2-Trichloro-1,2,2-trifluoroethane	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
1,2,3-Trichlorobenzene	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
1,2,4-Trichlorobenzene	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
1,1,1-Trichloroethane	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
1,1,2-Trichloroethane	0.2 U	0.2 U	2.0 U	1.0 U	0.2 U	2.0 U	0.2 U	0.2 U	0.2 U	1.0 U
<b>Trichloroethene</b>	0.2 U	0.2 U	2.0 U	1.0 U	0.2 U	2.0 U	0.2 U	1.3	1.3	1.0 U
Trichlorofluoromethane	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
1,2,3-Trichloropropane	1.0 U	1.0 U	10 U	5.0 U	1.0 U	10 U	1.0 U	1.0 U	1.0 U	5.0 U
<b>1,2,4-Trimethylbenzene</b>	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
1,3,5-Trimethylbenzene	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
Vinyl Acetate	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
<b>Vinyl Chloride</b>	1.5	2.4	2.0 U	1.0 U	2.9	2.0 U	0.2 U	0.2 U	0.2 U	1.0 U
m,p-Xylene	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
o-Xylene	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	2.5 U
<b>NATURAL ATTENUATION PARAMETERS</b>										
<b>Method Modified RSK175 (µg/L)</b>										
Methane	1300	1200	26000	26000						
Ethane	1.0 U	1.0 U	29	1.0 U						
Ethene	1.0 U	1.0 U	1.0 U	1.0 U						
<b>Conventional Parameters</b>										
Sulfate (mg/L) (EPA 300.0)	11.2	2.8	0.50 J	0.30 U						
Total Organic Carbon (mg/L) (SM20 5310C)	7.2	10.2	21.5	27.9						

**SWMU-20 VOA/CONVENTIONALS DATA**  
**DEVELOPMENTAL CENTER GROUNDWATER MONITORING**  
**MAY 2014**


Sample Name:	DC-MW-14A	DC-MW-14C	DC-MW-15A	DC-MW-15C	DC-MW-16A	DC-MW-16C	DC-MW-17A	DC-MW-20C	DC-MW-22A	TRIP BLANK
Lab SDG:	1473257	1473257	1473257	1473257	1473257	1473257	1473257	1473257	1473257	1473257
Lab Sample ID:	7458244	7458243	7458242	7458241	7458255	7458256	7458232	7458240	7458246	7458257
Sample Date:	5/7/2014	5/7/2014	5/7/2014	5/7/2014	5/8/2014	5/8/2014	5/6/2014	5/7/2014	5/7/2014	5/7/2014
<b>Test ID: VOA SW8260C (µg/L)</b>										
Acetone	5.0 U	25 U	15 U	50 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U
Acrolein	25 UJ	130 UJ	25 UJ	250 UJ	25 UJ	25 UJ	25 UJ	250 UJ	25 UJ	25 UJ
Acrylonitrile	5.0 U	25 U	5.0 U	50 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U
<b>Benzene</b>	0.2 U	1.0 U	0.3 U	2.0 U	0.2 U	0.2 U	0.2 U	2.0 U	0.4 U	0.2 U
Bromobenzene	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
<b>Bromochloromethane</b>	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
Bromodichloromethane	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
Bromoform	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
Bromomethane	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
2-Butanone	5.0 U	25 U	5.0 U	50 U	5.0 U	5.0 U	5.0 U	50 U	5.0 U	5.0 U
n-Butylbenzene	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
sec-Butylbenzene	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
tert-Butylbenzene	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
Carbon Disulfide	0.5 U	2.5 UJ	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
Carbon Tetrachloride	0.2 U	1.0 U	0.2 U	2.0 U	0.2 U	0.2 U	0.2 U	2.0 U	0.2 U	0.2 U
Chlorobenzene	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
Chloroethane	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
Chloroform	0.2 U	1.0 U	0.2 U	2.0 U	0.2 U	0.2 U	0.2 U	2.0 U	0.2 U	0.2 U
Chloromethane	0.5 U	2.5 UJ	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
2-Chlorotoluene	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
4-Chlorotoluene	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
1,2-Dibromo-3-chloropropane	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
Dibromochloromethane	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
Dibromomethane	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
trans-1,4-Dichloro-2-butene	5.0 UJ	25 U	5.0 UJ	50 UJ	5.0 UJ	5.0 UJ	5.0 UJ	50 UJ	5.0 UJ	5.0 UJ
1,2-Dichlorobenzene	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
1,3-Dichlorobenzene	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
1,4-Dichlorobenzene	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
1,1-Dichloroethane	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
1,2-Dichloroethane	0.2 U	1.0 U	0.2 U	2.0 U	0.2 U	0.2 U	0.2 U	2.0 U	0.2 U	0.2 U
<b>1,1-Dichloroethene</b>	0.2 U	1.0 U	0.2 U	2.0 U	0.2 U	0.2 U	0.2 U	2.0 U	0.2 U	0.2 U
<b>cis-1,2-Dichloroethene</b>	0.3 U	1.0 U	0.6 U	2.0 U	0.4 U	3.4 U	0.4 U	2.0 U	0.5 U	0.2 U
<b>trans-1,2-Dichloroethene</b>	0.2 U	1.0 U	0.2 U	2.0 U	0.2 U	0.3 U	0.2 U	2.0 U	0.2 U	0.2 U
1,2-Dichloropropane	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
1,3-Dichloropropane	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
<b>2,2-Dichloropropane</b>	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
1,1-Dichloropropene	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
cis-1,3-Dichloropropene	0.2 U	1.0 U	0.2 U	2.0 U	0.2 U	0.2 U	0.2 U	2.0 U	0.2 U	0.2 U
trans-1,3-Dichloropropene	0.2 U	1.0 U	0.2 U	2.0 U	0.2 U	0.2 U	0.2 U	2.0 U	0.2 U	0.2 U
Ethylbenzene	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	2.5 U	0.5 U
Ethylene Dibromide	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
Hexachlorobutadiene	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
2-Hexanone	5.0 U	25 U	5.0 U	50 U	5.0 U	5.0 U	5.0 U	50 U	5.0 U	5.0 U
Isopropylbenzene	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
4-Isopropyltoluene	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
Methyl Iodide	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U




**SWMU-20 VOA/CONVENTIONALS DATA  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING  
MAY 2014**

Sample Name:	DC-MW-14A	DC-MW-14C	DC-MW-15A	DC-MW-15C	DC-MW-16A	DC-MW-16C	DC-MW17A	DC-MW-20C	DC-MW-22A	TRIP BLANK
Lab SDG:	1473257	1473257	1473257	1473257	1473257	1473257	1473257	1473257	1473257	1473257
Lab Sample ID:	7458244	7458243	7458242	7458241	7458255	7458256	7458232	7458240	7458246	7458257
Sample Date:	5/7/2014	5/7/2014	5/7/2014	5/7/2014	5/8/2014	5/8/2014	5/6/2014	5/7/2014	5/7/2014	5/7/2014
4-Methyl-2-Pentanone (MIBK)	5.0 U	25 U	5.0 U	50 U	5.0 U	5.0 U	5.0 U	50 U	5.0 U	5.0 U
Methylene Chloride	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
<b>Naphthalene</b>	0.5 U	2.5 U	89	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	9.8	0.5 U
n-Propylbenzene	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
Styrene	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
1,1,1,2-Tetrachloroethane	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
1,1,2,2-Tetrachloroethane	0.2 U	1.0 U	0.2 U	2.0 U	0.2 U	0.2 U	0.2 U	2.0 U	0.2 U	0.2 U
<b>Tetrachloroethene</b>	0.2 U	1.0 U	0.2 U	2.0 U	1.4	0.2 U	3.6	2.0 U	0.2 U	0.2 U
Toluene	0.2 U	1.0 U	2.9	2.0 U	0.2 U	0.2 U	0.2 U	2.0 U	1.2	0.2 U
1,1,2-Trichloro-1,2,2-trifluoroethane	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
1,2,3-Trichlorobenzene	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
1,2,4-Trichlorobenzene	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
1,1,1-Trichloroethane	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
1,1,2-Trichloroethane	0.2 U	1.0 U	0.2 U	2.0 U	0.2 U	0.2 U	0.2 U	2.0 U	0.2 U	0.2 U
<b>Trichloroethene</b>	0.2 U	1.0 U	0.2 U	2.0 U	1.6	0.2 U	2.6	2.0 U	0.2 U	0.2 U
Trichlorofluoromethane	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
1,2,3-Trichloropropane	1.0 U	5.0 U	1.0 U	10 U	1.0 U	1.0 U	1.0 U	10 U	1.0 U	1.0 U
<b>1,2,4-Trimethylbenzene</b>	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	2.3	0.5 U
1,3,5-Trimethylbenzene	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
Vinyl Acetate	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	0.5 U	0.5 U
<b>Vinyl Chloride</b>	0.3	1.0 U	1.0	2.9	0.2 U	1.2	0.2 U	2.0 U	1.6	0.2 U
m,p-Xylene	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	1.3	0.5 U
o-Xylene	0.5 U	2.5 U	0.5 U	5.0 U	0.5 U	0.5 U	0.5 U	5.0 U	3.6	0.5 U
<b>NATURAL ATTENUATION PARAMETERS</b>										
<b>Method Modified RSK175 (µg/L)</b>										
Methane	15000								4200	
Ethane	4.6 J								1.0 U	
Ethene	1.0 U								1.0 U	
<b>Conventional Parameters</b>										
Sulfate (mg/L) (EPA 300.0)	19.9								0.66 J	
Total Organic Carbon (mg/L) (SM20 5310C)	6.5								23.6	

U = Indicates compound was analyzed for, but was not detected at the given detection limit.  
J = Indicates the analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.  
UJ = The analyte was not detected in the sample; the reported sample reporting limit is an estimate.  
µg/L = micrograms per liter  
mg/L = milligrams per liter



**Legend**


-  Monitoring Well Location
- (ND) Tetrachloroethene Not Detected at 0.2 µg/L Detection Limit
- (3.6) Tetrachloroethene Groundwater Concentration in µg/L




Boeing Developmental Center  
Tukwila, Washington


**SWMU-20 Tetrachloroethene  
May 2014  
Groundwater Concentrations**

Figure  
**1**




**Legend**


-  Monitoring Well Location
- (ND) Trichloroethene Not Detected at 0.2 µg/L Detection Limit
- (2.6) Trichloroethene Groundwater Concentration in µg/L



Boeing Developmental Center Tukwila, Washington	<b>SWMU-20 Trichloroethene May 2014 Groundwater Concentrations</b>	Figure <b>2</b>
--	--	--------------------




**Legend**


-  Monitoring Well Location
- (ND) Cis-1,2-Dichloroethene Not Detected at 0.2 µg/L Detection Limit
- (19) Cis-1,2-Dichloroethene Groundwater Concentration in µg/L



Boeing Developmental Center Tukwila, Washington	<b>SWMU-20 Cis-1,2-Dichloroethene May 2014 Groundwater Concentrations</b>	Figure <b>3</b>
--	---	--------------------






- Legend**
-  Monitoring Well Location
  - (ND) Vinyl Chloride Not Detected at 0.2 µg/L Detection Limit
  - (2.4) Vinyl Chloride Groundwater Concentration in µg/L


0 100 200  
Scale in Feet




Boeing Developmental Center Tukwila, Washington	<b>SWMU-20 Vinyl Chloride May 2014 Groundwater Concentrations</b>	Figure <b>4</b>
--	---	--------------------



**Legend**


-  Monitoring Well Location
- (ND) Benzene Not Detected at 0.2 µg/L Detection Limit
- (0.4) Benzene Groundwater Concentration in µg/L



Boeing Developmental Center Tukwila, Washington	<b>SWMU-20 Benzene                  May 2014                  Groundwater Concentrations</b>	Figure <b>5</b>
--	--	--------------------







**Legend**

- Monitoring Well Location
- (ND) Naphthalene Not Detected at 0.2 µg/L Detection Limit
- (89) Naphthalene Groundwater Concentration in µg/L

Boeing Developmental Center Tukwila, Washington	<b>SWMU-20 Naphthalene                  May 2014                  Groundwater Concentrations</b>	Figure <b>6</b>
--	--	--------------------



**SWMU-20 ANALYTICAL RESULTS SUMMARY  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING  
JANUARY 1994 THROUGH PRESENT**

**TETRACHLOROETHENE (µg/L)**

	Jan-94	May-95	Oct-95	Feb-96	May-96	Aug-96	Nov-96	Feb-97	May-97	Aug-97	Nov-97	Jun-98	Oct-98	Jun-99	Nov-99	Jun-00	Dec-00	Jun-01	Dec-01	Jun-02	Dec-02	Jun-03	Nov-03	May-04	Aug-04	Oct-04	Feb-05	Mar-05	May-05	
06A	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	<1.0	<1.0	<1.0	<1.0	nt	<1.0		
06B	27	5.87	14.4	9.62 J	26.18	13.7	14.3	21.5	21.3	17	16.9	18.9	16.3	22.6	2.3	6	10.19	2.6	2.4	10	10	7.9	3.9	9.5	1.9	<1.0	<1.0	nt	<2.0	
06C	22	<1.00	<10.00	<10.00	<1.00	<2.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<2.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	
08C	16	<1.00	<5.00	<5.00	<3.33	<10.00	13.5	<5.00	<4.00	<4.00	<4.00	7.8	<5.00	<1.00	<2.00	<2.00	<2.00	<1.00	<1.00	<1.00	<1.00	<3.00	<5.00	<1.00	nt	<1.00	nt	<1.00		
09A	420	2568.25	1589	1970	785.7	114	272	98	76	96.9	56.6	39.4	94	5.1	38	40	36.6	12.65	16	14	540	1800	1000	150	<3.00	<5.00	<10	nt	<1.00	
09B	820	1972.65	668.1	1266	934.6	78.9	75.9	44.3	35	10.9	21.5	31.3	<10.00	6.74	3.6	<2.00	6.62	1.18	2.1	<1.00	<1.00	1.0	250	<3.00	<5.00	<5.00	<10	nt	<1.00	
09C	nd	11.32	<5.00	<10.00	1.24	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	
09D	8.8	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	nt	<1.00		
10A	180	635.8	754 E	468.85	242.1	114	342	67.5	77.8	76.5	70.3	72.5	86.4	38	21.5	16.6	21.63	30.3	11	24	24	34	58	29	14	15	4.7	nt	4.2	
10C	6.9	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	nt	<1.00	
11A	5.2	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	nt	<1.00		
12A	3.9	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	nt	<1.00	
13A	10	4.17	<5.00	<5.00	6.82	3	2.1	3.2	2.1	1.7	1.5	1.6	1.3	<1.00	<1.00	1.2	<1.00	<1.00	1.6	2.7	2.4	3.4	3.0	5.1	nt	4.3	nt	nt	6.1	
13C	5.1	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	nt	<1.00	
14A	410	4.42	<5.00	133.57	96.06	11.2	<5.00	<4.00	<2.00	<2.00	<2.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<5.00	<5.00	nt	<10
14C	7.2	9.02	10.53	8.64 J	5.44	6.1	<1.00	<10.00	<10.00	<10.00	<2.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	nt	nt	<1.00	
14E	nd	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	nt	<1.00	
15A	11	<1.00	<5.00	<5.00	<5.00	<2.00	<1.00	<4.00	<2.00	<1.00	<2.00	<3.33	<10.00	<1.00	<10.00	<10.00	<10.00	<1.00	<1.00	<1.00	<1.00	<5.00	<5.00	<5.00	nt	<5.00	nt	nt	<5.00	
15C	13	<1.00	<33.30	<5.00	<1.00	1.1	<1.00	<2.00	<10.00	<10.00	<10.00	<3.33	<1.00	<2.00	<2.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	nt	<1.00	
15D	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	nt	<1.00	
16A	1.6	1.10	<5.00	<5.00	<1.00	1.7	<1.00	1.1	<1.00	<1.00	<1.00	1.64	1.03	1.3	2.3	2.2	<1.00	<1.00	<1.00	<1.00	1.2	1.2	1.1	1.2	nt	1.2	nt	nt	1.2	
16C	nd	<1.00	<5.00	<10.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	nt	<1.00	
17A	36	1.39	<5.00	<5.00	1.55	<1.00	1.3	2.7	1.90 J	2.2	<1.00	2.6	2.4	2.5	2.1	2.6	4.15	nt	<1.00	3.8	4.6	4.6	4.8	4.8	nt	5.2	nt	nt	nt	
17C	36	<1.00	<5.00	<5.00	<1.00	1.6	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	
17D	46	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	
18A	5.4	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	<1.00	nt	nt	nt	nt	nt	
18C	4.6	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	nt	nt	<1.00	
18D	4.6	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	
19A	6	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	<1.00	nt	nt	<1.00	nt	<1.00	
19C	6.5	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	nt	nt	<1.00	
19D	9.5	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	
20A	3.4	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	
20C	3.9	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	nt	nt	<1.00	
20D	4.3	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	
21A	nt	nt	nt	nt	<1.00		<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	
21C	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	
22A	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	<1.00	<1.00	
23A	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	<1.00	<1.00	



**SWMU-20 ANALYTICAL RESULTS SUMMARY  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING  
JANUARY 1994 THROUGH PRESENT**

**TETRACHLOROETHENE (µg/L)**

Aug-05	Nov-05	Feb-06	May-06	Aug-06	Nov-06	Feb-07	May-07	Nov-07	May-08	Nov-08	May-09	Nov-09	May-10	Nov-10	May-11	Nov-11	May-12	Nov-12	May-13	Nov-13	May-14
<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<1.0	<1.0	<0.2	<1.0	<1.0	<4.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<0.2	<0.5	<0.2	<0.2
<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<0.2	<0.5	<0.2	<0.2
<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	<1.0	nt	<10	nt	<5.0	nt	<3.0	<5.0	<5.0	<5.0	<1.0	<3.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<0.2	<b>1.9</b>	<10	<5.0	<1.0	<1.0	<2.0	<0.2	<0.2	<2.0	<2.0	<2.0	<2.0
<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<0.2	<1.0	<1.0	<3.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	<1.0	nt	<1.0	nt	<1.0	nt	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
<b>2.7</b>	<b>3.3</b>	<b>3.7</b>	<b>1.8</b>	<b>1.6</b>	<0.2	<b>1.2</b>	<b>1.1</b>	<b>1.2</b>	<1.0	<1.0	<2.0	<1.0	<1.0	<1.0	<2.0	<0.2	<0.2	<0.2	<0.2	<0.2	<1.0
nt	<1.0	nt	<1.0	nt	<0.2	nt	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2
nt	<1.0	nt	<1.0	nt	<1.0	nt	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<2.0	<2.0	<2.0	<2.0
nt	<1.0	nt	<1.0	nt	<0.2	nt	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<b>0.2</b>	<0.2	<0.2	<0.2	<b>0.3</b>
nt	<b>6.0</b>	nt	<b>7.1</b>	nt	<b>8.3</b>	nt	<b>8.2</b>	<b>6.4</b>	<b>8.7</b>	<b>6.5</b>	<b>7.7</b>	<b>9.2</b>	<b>9.4</b>	<b>3.6</b>	<b>3.9</b>	<b>1.6</b>	<b>2.3</b>	<b>2.2</b>	<b>4.5</b>	<b>2.2</b>	<b>3.1</b>
nt	<1.0	nt	<1.0	nt	<0.2	nt	<0.2	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<2.0	<2.0	<2.0	<1.0
<10	<3.0	<1.0	<2.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<0.2	<0.5	<0.2	<0.2
nt	<1.0	nt	<1.0	nt	<0.2	nt	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<2.0	<2.0	<2.0	<1.0
nt	<1.0	nt	<1.0	nt	<0.2	nt	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	<5.0	nt	<5.0	nt	<3.0	nt	<1.0	<1.0	<3.0	<1.0	<3.0	<1.0	<1.0	<1.0	<10	<0.2	<0.1	<0.2	<0.5	<0.2	<0.2
nt	<1.0	nt	<1.0	nt	<0.2	nt	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<2.0	<5.0	<2.0	<2.0
nt	<1.0	nt	<1.0	nt	<1.0	nt	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	<b>1.3</b>	nt	<b>1.0</b>	nt	<0.2	nt	<b>1.1</b>	<b>1.7</b>	<b>1.2</b>	<b>1.5</b>	<b>1.6</b>	<b>2.2</b>	<b>1.4</b>	<b>1.3</b>	<b>1.6</b>	<b>1.4</b>	<b>1.6</b>	<b>1.1</b>	<b>1.4</b>	<b>2.1</b>	<b>1.4</b>
nt	<1.0	nt	<1.0	nt	<b>1.2</b>	nt	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<0.2	<0.5	<0.2	<0.2
nt	<b>4.0</b>	nt	<b>4.2</b>	nt	<b>2.2</b>	nt	<b>4.7</b>	<b>4.2</b>	<b>4.3</b>	<b>4.2</b>	<b>3.2</b>	<b>3.7</b>	<b>4.0</b>	<b>2.3</b>	<b>3.1</b>	<b>2.6</b>	<b>3.1</b>	<b>2.8</b>	<b>3.6</b>	<b>3.9</b>	<b>3.6</b>
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	<1.0	nt	<1.0	nt	<0.2	nt	<0.2	<1.0	<0.2	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	<1.0	nt	<1.0	nt	<0.2	nt	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	<1.0	nt	<1.0	nt	<0.2	nt	<0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<2.0	<5.0	<2.0	<2.0
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2
<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt

nd = Not Detected.  
 nt = Not Tested.  
 J = Indicates the analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.  
 E = Estimated concentration calculated for an analyte response above the valid instruction calibration range. A dilution is required to obtain an accurate quantification of the analyte.  
 Bold = Detected compound.

**SWMU-20 ANALYTICAL RESULTS SUMMARY  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING  
JANUARY 1994 THROUGH PRESENT**

**TRICHLOROETHENE (µg/L)**

	Jan-94	May-95	Oct-95	Feb-96	May-96	Aug-96	Nov-96	Feb-97	May-97	Aug-97	Nov-97	Jun-98	Oct-98	Jun-99	Nov-99	Jun-00	Dec-00	Jun-01	Dec-01	Jun-02	Dec-02	Jun-03	Nov-03	May-04	Aug-04	Oct-04	Feb-05	Mar-05	May-05	
06A	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	1.0	<1.0	<1.0	<1.0	nt	<1.0	
06B	4.2	3.57	6.00 J	<5.00	7.37	3.5	2.5	4.9	4.7	4.6	6.5	3.5	2.6	4.54	2.2	4.7	8.71	5.83	4.7	5.9	4.5	2.9	1.0	3.2	1.2	<1.0	<1.0	nt	<2.0	
06C	1.6	<1.00	31.36	<10.00	<1.00	<2.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	91.6	<2.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	
08C	21	3.16	<5.00	<5.00	<3.33	<10.00	26.2	<5.00	<4.00	<4.00	<4.00	26.6	<5.00	<1.00	<2.00	<2.00	<2.00	<1.00	<1.00	<1.00	<1.00	<3.00	<5.00	<1.00	nt	<1.00	nt	<1.00		
09A	500	1796.5	1507	2318	1160	90.8	191	49.3	51.1	69.2	56.4	15.4	77	3.5	35	23	24.3	25.21	32	24	580	990	1500	230	11	19	<10	nt	<1.00	
09B	160	1463	524.7	1206	554	58.6	35.2	28.7	31.5	4.9	15.4	20.65	<10.00	7.5	4.8	2.6	11.2	5.79	4.8	2.5	12	9.7	370	4.2	16	17	<10	nt	<1.00	
09C	nd	19.41	<5.00	<10.00	3.54	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	
09D	2.2	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	<1.00	
10A	120	333.23	411 E	268.41	115.3	56.7	128	28.4	38.2	36.6	48.8	23.8	33.9	19.2	14	8.3	13.11	17.02	18	24	29	32	49	27	12	15	4.8	nt	5.4	
10C	3.9	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	<1.00	
11A	7	2.41	<5.00	<5.00	2.54	1.9	1	<1.00	<1.00	1.2	1.6	<1.00	1.03	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	1.9	2.2	2.2	2.8	2.1	nt	2.0	nt	nt	2.0	
12A	5.5	1.13	<5.00	<5.00	<1.00	1.7	1.2	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	<1.00	
13A	31	12.23	<5.00	9.57 J	16.52	3.4	3.4	2	1.5	2.9	3	1.1	1.7	1.8	2.3	2.4	2.12	1.28	<1.00	3.4	3.3	3.9	3.8	4.6	nt	4.0	nt	nt	4.6	
13C	nd	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	<1.00	
14A	600	6.25	<5.00	151.58	146.72	84.1	2.8	<4.00	<2.00	<2.00	<2.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	2.9	39	<5.00	nt	<10	
14C	6.6	14.41	21.93	13.33	7.61	12.5	<1.00	<10.00	<10.00	<10.00	<2.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	<1.00	
14E	nd	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	<1.00	
15A	7.5	<1.00	<5.00	<5.00	<5.00	<2.00	<1.00	<4.00	<2.00	<1.00	<2.00	<3.33	<10.00	<1.00	<10.00	<10.00	<10.00	<1.00	<1.00	<1.00	<1.00	<5.00	<5.00	<5.00	nt	<5.00	nt	nt	<5.00	
15C	12	<1.00	<33.30	<5.00	<1.00	7.5	<1.00	<2.00	12	<10.00	<10.00	<3.33	<1.00	<2.00	<2.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	<1.00	
15D	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	<1.00	
16A	4.4	5.02	<5.00	<5.00	2.57	4	2.1	2.6	2	1.9	<1.00	<1.00	<1.00	1.01	1.4	1.2	1.08	<1.00	<1.00	<1.00	1.5	1.3	1.2	1.2	nt	1.3	nt	nt	1.8	
16C	nd	<1.00	<5.00	<10.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	<1.00	
17A	7.2	17.42	17.04	<5.00	7.28	<1.00	9.8	17.5	4.9	18	2	<1.00	12.4	11.1	11.5	6.6	13.99	nt	5.9	7.4	7.5	7.4	7.9	6.5	nt	4.8	nt	nt	nt	
17C	2.1	<1.00	<5.00	<5.00	<1.00	14.1	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	
17D	2.3	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	
18A	nd	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	<1.00	nt	nt	nt	nt	nt	
18C	nd	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	<1.00	
18D	nd	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
19A	1.5	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	<1.00	nt	nt	<1.00	nt	<1.00	
19C	nd	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	<1.00	
19D	nd	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
20A	1.1	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
20C	1.8	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	<1.00	
20D	1.5	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
21A	nt	nt	nt	nt	<1.00		<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	nt
21C	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	nt
22A	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	<1.00	nt	<1.00
23A	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	<1.00	nt	<1.00

**SWMU-20 ANALYTICAL RESULTS SUMMARY  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING  
JANUARY 1994 THROUGH PRESENT**

**TRICHLOROETHENE (µg/L)**

Aug-05	Nov-05	Feb-06	May-06	Aug-06	Nov-06	Feb-07	May-07	Nov-07	May-08	Nov-08	May-09	Nov-09	May-10	Nov-10	May-11	Nov-11	May-12	Nov-12	May-13	Nov-13	May-14
<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<1.0	<1.0	<0.2	<1.0	<1.0	<4.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<0.2	<0.5	<0.2	<0.2
<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<0.2	<0.5	<0.2	<0.2
<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	<1.0	nt	<10	nt	<5.0	nt	<3.0	<5.0	<5.0	<5.0	<1.0	<3.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<b>0.2</b>	<b>4.6</b>	<10	<1.0	<1.0	<1.0	<2.0	<0.2	<0.2	<2.0	<2.0	<2.0	<2.0
<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<0.2	<1.0	<1.0	<3.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	<1.0	nt	<1.0	nt	<1.0	nt	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
<b>6.3</b>	<b>6.7</b>	<b>9.6</b>	<b>3.7</b>	<b>1.6</b>	<0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<2.0	<1.0	<1.0	<1.0	<2.0	<0.2	<0.2	<0.2	<0.2	<0.2	<1.0
nt	<1.0	nt	<1.0	nt	<0.2	nt	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2
nt	<b>2.0</b>	nt	<b>1.1</b>	nt	<b>1.5</b>	nt	<b>1.5</b>	<b>1.1</b>	<b>1.2</b>	<b>1.2</b>	<1.0	<b>1.0</b>	<b>1.1</b>	<1.0	<1.0	<b>0.5</b>	<b>0.7</b>	<2.0	<2.0	<2.0	<2.0
nt	<1.0	nt	<1.0	nt	<b>0.7</b>	nt	<1.0	<1.0	<b>0.6</b>	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<b>0.6</b>	<0.2	<b>0.4</b>	<0.2	<b>0.5</b>	<0.2
nt	<b>4.5</b>	nt	<b>4.6</b>	nt	<b>6.5</b>	nt	<b>7.0</b>	<b>4.2</b>	<b>6.8</b>	<b>3.7</b>	<b>5.6</b>	<b>6.0</b>	<b>5.3</b>	<b>2.8</b>	<b>2.4</b>	<1.0	<b>0.8</b>	<b>0.8</b>	<b>2.5</b>	<b>0.6</b>	<b>1.3</b>
nt	<1.0	nt	<1.0	nt	<0.2	nt	<0.2	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<2.0	<2.0	<2.0	<1.0
<10	<3.0	<1.0	<2.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<0.2	<0.5	<0.2	<0.2
nt	<1.0	nt	<1.0	nt	<0.2	nt	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<2.0	<2.0	<2.0	<1.0
nt	<1.0	nt	<1.0	nt	<0.2	nt	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	<5.0	nt	<5.0	nt	<3.0	nt	<1.0	<1.0	<3.0	<1.0	<3.0	<1.0	<1.0	<1.0	<1.0	<0.2	<1.0	<0.2	<0.5	<0.2	<0.2
nt	<1.0	nt	<1.0	nt	<0.2	nt	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<b>3.2</b>	<5.0	<2.0	<2.0
nt	<1.0	nt	<1.0	nt	<1.0	nt	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	<b>2.2</b>	nt	<b>1.4</b>	nt	<b>0.8</b>	nt	<b>1.3</b>	<b>1.2</b>	<b>1.3</b>	<b>1.4</b>	<b>1.6</b>	<b>1.5</b>	<b>1.4</b>	<b>1.1</b>	<b>1.4</b>	<b>1.3</b>	<b>1.7</b>	<b>1.5</b>	<b>1.5</b>	<b>1.8</b>	<b>1.6</b>
nt	<1.0	nt	<1.0	nt	<b>2.3</b>	nt	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<0.2	<0.5	<0.2	<0.2
nt	<b>5.4</b>	nt	<b>4.4</b>	nt	<b>6.3</b>	nt	<b>5.3</b>	<b>4.3</b>	<b>5.1</b>	<b>5.2</b>	<b>4.9</b>	<b>4.5</b>	<b>3.1</b>	<b>4.8</b>	<b>2.2</b>	<b>2.8</b>	<b>2.0</b>	<b>3.5</b>	<b>2.8</b>	<b>3.4</b>	<b>2.6</b>
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	<1.0	nt	<1.0	nt	<0.2	nt	<0.2	<1.0	<0.2	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
<1.0	<1.0	<1.0	<1.0	<1.0	<b>0.2</b>	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	<1.0	nt	<1.0	nt	<0.2	nt	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	<1.0	nt	<1.0	nt	<b>0.2</b>	nt	<0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<2.0	<5.0	<2.0	<2.0
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
<1.0	<1.0	<1.0	<1.0	<1.0	<b>0.3</b>	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2
<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt

nd = Not Detected.  
 nt = Not Tested.  
 J = Indicates the analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.  
 E = Estimated concentration calculated for an analyte response above the valid instruction calibration range. A dilution is required to obtain an accurate quantification of the analyte.  
 Bold = Detected compound.

**SWMU-20 ANALYTICAL RESULTS SUMMARY  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING  
JANUARY 1994 THROUGH PRESENT**

**CIS-1,2-DICHLOROETHENE (µg/L)**

	Jan-94	May-95	Oct-95	Feb-96	May-96	Aug-96	Nov-96	Feb-97	May-97	Aug-97	Nov-97	Jun-98	Oct-98	Jun-99	Nov-99	Jun-00	Dec-00	Jun-01	Dec-01	Jun-02	Dec-02	Jun-03	Nov-03	May-04	Aug-04	Oct-04	Feb-05	Mar-05	May-05	
06A	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	23	45	2.6	3.3	nt	2.6	
06B	23	43.71	53.75	29.45	58.31	46.3	30.5	37.4	60.9	61.8	76.4	66.7	9.9	70.1	49.7	71.5	91.77	63.94	27	40	23	13	11	10	13	10	11	nt	5.5	
06C	7.9	14.57	99.09	<10.00	1.01	107	1.9	3.1	22.1	28.3	12.3	1.1	181 E	<2.00	<1.00	<1.00	<1.00	<1.00	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.4	<1.0	3.6	nt	1.1	
08C	44	14.95	<5.00	5.55 J	8	1.1	37.6	<5.00	37.3	46.1	42.3	38.4	<5.00	1.1	<2.00	3.2	<2.00	<1.00	<1.0	<1.0	<1.0	<3.0	<5.0	<1.0	nt	<1.0	nt	nt	<1.0	
09A	2500	5790.9	3286	7484	6143	443	816	520	258	206.E	199	94.3	680	15.5	187	421	60.75	266.6	100	280	1600	2300	2300	970	370	460	41	nt	<1.0	
09B	940	5010.35	1307 E	3407 E	1521	207	142	164 E	510	35.1	111	939 E	178	122.04	41.2	102.4	135.2	112.3	100	<180	180	140	850	250	530	300	890	nt	12	
09C	520	431.66	159.69	70	33.67	29.8	1.6	4.6	2.6	2	1.7	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	1.1	6.7	2.7	4.1	8.9	4.0	1.7	<1.0	1.7	nt	1.2	
09D	5.1	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	nt	<1.0	nt	nt	<1.0	
10A	470	421.26	297 E	249.16	159.2	90.1	17.8	29	66.1	58.5	74.1	29.3	6.9	33.3	20.6	10.6	14.14	14.09	36	80	110	88	98	80	170	100	24	nt	26	
10C	14	1.93	<5.00	<5.00	1.01	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.0	3.7	3.3	14	6.2	4.3	nt	6.4	nt	nt	4.0	
11A	54	15.86	10.82	7.17 J	10.27	9.3	6.4	4.9	6.6	6.1	4.2	2.8	2.3	2.1	1.1	1.5	1.55	1.27	2.1	6.0	12	17	18	21	nt	20	nt	nt	20	
12A	20	2.30	17.5	<5.00	1.09	9.5	6.6	<1.00	6.1	3.7	3	1.7	1.8	1.03	1.7	1.9	2.07	1.46	2.2	1.8	3.3	1.4	4	1.8	nt	4.4	nt	nt	2.0	
13A	8.2	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	1.6	<1.00	<1.00	1.2	1.3	1.2	1.2	<1.00	<1.00	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	nt	<1.0	nt	nt	<1.0	
13C	16	1.14	<5.00	<5.00	<1.00	1.3	<1.00	1.3	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.0	<1.0	<1.0	<1.0	1.4	<1.0	<1.0	nt	<1.0	nt	nt	<1.0	
14A	590	15.50	9.83 J	294.36	115.94	249	114	6.4	24.2	18.3	9.5	4.9	3.7	7	3.2	3.8	<1.00	<1.00	<1.0	<1.0	7.2	23	170	140	560	1200	300	nt	<10	
14C	110	187.91	1017.82	237.4	70.06	326	211	183	163	136	82.7	25.6	21.7	6.2	<1.00	1.2	2.83	1.64	<1.0	1.5	2.4	31	13	63	nt	22	nt	nt	11	
14E	1.1	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	nt	<1.0	nt	nt	<1.0
15A	9.1	3.29	<5.00	<5.00	<5.00	3.6	3.5	4.5	5	5.5	5.5	15.65	<10.00	<1.00	<10.00	<10.00	4.99	4.9	2.8	2.8	<5.0	<5.0	<5.0	nt	<5.0	nt	nt	nt	<5.0	
15C	92	69.14	640.52	93.62	1.47	463	532	187	1470	1100	719	785 E	90.5	53.2	28.4	1.01	2.53	<1.00	1.1	<1.0	<1.0	2.9	5.7	9.1	nt	11	nt	nt	13	
15D	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	nt	<1.0	nt	nt	<1.0	
16A	5.5	12.63	5.38 J	<5.00	25.39	12	3.2	6.2	2.4	1.7	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	1.76	1.82	2.6	<1.0	1.2	2.4	1.3	2.3	nt	1.8	nt	nt	2.6	
16C	14	11.83	6.24 J	<10.00	5.66	2.6	1.6	1.6	1.13	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.0	<1.0	<1.0	<1.0	<1.0	1.7	nt	2.4	nt	nt	2.8	
17A	4.3	1.38	<5.00	<5.00	1.09	<1.00	1.4	1.2	2.90 J	4.13	<1.00	2.3	3.8	4.1	4.3	2.3	2.1	nt	2	<1.0	1.0	1.4	1.6	1.0	nt	1.2	nt	nt	nt	
17C	5.3	<1.00	<5.00	<5.00	1.19	1.6	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	
17D	1.8	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	
18A	nd	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	<1.0	nt	nt	nt	nt	nt	
18C	1.3	2.02	<5.00	<5.00	<1.00	1	<1.00	<1.00	<1.00	<1.00	1.1	1.8	2.8	1.9	2.1	1.3	1.59	1.42	<1.0	<1.0	<1.0	1.7	<1.0	<1.0	nt	<1.0	nt	nt	<1.0	
18D	nd	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	
19A	2.4	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	<1.0	nt	nt	<1.0	nt	<1.0	
19C	1.7	1.17	<5.00	<5.00	1.37	1.3	<1.00	<1.00	1.2	1.2	1.2	2	1.2	1.4	<1.00	1.03	<1.00	1.01	<1.0	<1.0	<1.0	<1.0	1	<1.0	nt	<1.0	nt	nt	<1.0	
19D	nd	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	
20A	nd	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	
20C	16	7.34	6.06 J	<5.00	2.46	2.5	2.1	1.9	1.6	<1.00	<1.00	<1.00	1.5	<1.00	<1.00	1.3	<1.00	1.09	1.1	<1.0	1.3	2.1	1.6	1.4	nt	1.7	nt	nt	1.7	
20D	1.8	2.22	<5.00	<5.00	46.38	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	
21A	nt	nt	nt	nt	<1.00		<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	
21C	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	<1.00	<1.0	<1.0	1.3	nt	nt	nt	nt	nt	nt	nt	nt	
22A	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	3.5	2.3	
23A	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	<1.0	<1.0	

**SWMU-20 ANALYTICAL RESULTS SUMMARY  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING  
JANUARY 1994 THROUGH PRESENT**

**CIS-1,2-DICHLOROETHENE (µg/L)**

Aug-05	Nov-05	Feb-06	May-06	Aug-06	Nov-06	Feb-07	May-07	Nov-07	May-08	Nov-08	May-09	Nov-09	May-10	Nov-10	May-11	Nov-11	May-12	Nov-12	May-13	Nov-13	May-14
<b>1.6</b>	<b>1.3</b>	<b>1.4</b>	<1.0	<1.0	<b>0.4</b>	<1.0	<1.0	<0.2	<1.0	<b>1.7</b>	<4.0	<b>1.9</b>	<b>1.3</b>	<1.0	<1.0	<b>0.3</b>	<b>0.4</b>	<b>0.3</b>	<0.5	<b>0.4</b>	<b>0.4</b>
<b>1.8</b>	<b>1.1</b>	<1.0	<1.0	<1.0	<b>1.4</b>	<b>3.8</b>	<b>1.4</b>	<0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<b>0.5</b>	<0.2	<0.5	<0.2	<0.2
<b>1.1</b>	<b>1.1</b>	<1.0	<1.0	<1.0	<b>0.3</b>	<1.0	<1.0	<b>0.2</b>	<1.0	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	<1.0	nt	<10	nt	<5.0	nt	<3.0	<5.0	<5.0	<5.0	<1.0	<3.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
<1.0	<1.0	<1.0	<1.0	<1.0	<b>0.3</b>	<1.0	<1.0	<1.0	<b>110</b>	<b>160</b>	<10	<5.0	<1.0	<1.0	<2.0	<b>0.2</b>	<b>0.2</b>	<2.0	<2.0	<2.0	<2.0
<1.0	<1.0	<1.0	<1.0	<1.0	<b>0.3</b>	<1.0	<1.0	<1.0	<b>0.2</b>	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
<b>7.6</b>	<b>1.2</b>	<1.0	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<0.2	<1.0	<1.0	<3.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	<1.0	nt	<1.0	nt	<1.0	nt	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
<b>48</b>	<b>47</b>	<b>42</b>	<b>63</b>	<b>38</b>	<b>7.4</b>	<b>32</b>	<b>28</b>	<b>22</b>	<b>22</b>	<b>1.6</b>	<2.0	<1.0	<1.0	<1.0	<2.0	<b>0.2</b>	<b>0.2</b>	<b>0.3</b>	<b>0.2</b>	<b>0.2</b>	<1.0
nt	<1.0	nt	<b>1.5</b>	nt	<b>1.9</b>	nt	<b>6.7</b>	<b>7.2</b>	<b>15</b>	<b>8.5</b>	<1.0	<1.0	<1.0	<b>3.5</b>	<b>5.8</b>	<b>3.7</b>	<b>5.4</b>	<b>6.1</b>	<b>6.0</b>	<b>3.5</b>	<b>5.4</b>
nt	<b>22</b>	nt	<b>20</b>	nt	<b>24</b>	nt	<b>26</b>	<b>27</b>	<b>26</b>	<b>33</b>	<b>26</b>	<b>30</b>	<b>26</b>	<b>22</b>	<b>22</b>	<b>23</b>	<b>24</b>	<b>25</b>	<b>22</b>	<b>24</b>	<b>19</b>
nt	<b>3.8</b>	nt	<b>1.5</b>	nt	<b>4.4</b>	nt	<b>2.4</b>	<b>3.2</b>	<b>3.2</b>	<b>4.7</b>	<b>1.4</b>	<b>4.7</b>	<1.0	<b>4.3</b>	<1.0	<b>3.1</b>	<0.2	<b>2.1</b>	<b>0.5</b>	<b>2.2</b>	<0.2
nt	<1.0	nt	<1.0	nt	<b>0.3</b>	nt	<b>0.4</b>	<1.0	<b>0.3</b>	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<b>0.5</b>	<0.2	<0.2
nt	<1.0	nt	<1.0	nt	<b>0.8</b>	nt	<b>0.8</b>	<1.0	<b>0.2</b>	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<2.0	<2.0	<2.0	<1.0
<10	<b>6.0</b>	<1.0	<b>2.1</b>	<b>3.0</b>	<1.0	<1.0	<b>1.5</b>	<b>1.6</b>	<b>1.2</b>	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<b>0.6</b>	<b>0.3</b>	<b>0.6</b>	<0.5	<b>0.5</b>	<b>0.3</b>
nt	<1.0	nt	<1.0	nt	<0.2	nt	<1.0	<b>1.1</b>	<b>1.4</b>	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<2.0	<2.0	<2.0	<1.0
nt	<1.0	nt	<1.0	nt	<0.2	nt	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	<5.0	nt	<5.0	nt	<3.0	nt	<b>1.4</b>	<1.0	<3.0	<1.0	<3.0	<1.0	<1.0	<1.0	<10	<b>0.3</b>	<1.0	<b>0.4</b>	<b>0.6</b>	<b>0.5</b>	<b>0.6</b>
nt	<1.0	nt	<1.0	nt	<0.2	nt	<1.0	<1.0	<b>1.8</b>	<b>1.9</b>	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<2.0	<5.0	<2.0	<2.0
nt	<1.0	nt	<1.0	nt	<1.0	nt	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	<b>2.1</b>	nt	<b>2.3</b>	nt	<b>4.2</b>	nt	<b>1.9</b>	<b>1.2</b>	<b>1.2</b>	<b>1.0</b>	<1.0	<1.0	<1.0	<1.0	<1.0	<b>0.5</b>	<b>0.5</b>	<b>0.6</b>	<0.5	<b>0.3</b>	<b>0.4</b>
nt	<b>4.6</b>	nt	<b>5.2</b>	nt	<b>2.0</b>	nt	<b>8.8</b>	<b>7</b>	<b>7.8</b>	<b>5.3</b>	<b>5.0</b>	<b>4.9</b>	<b>3.7</b>	<b>3.3</b>	<b>3.7</b>	<b>3.3</b>	<b>4.8</b>	<b>4.9</b>	<b>3.9</b>	<b>4.4</b>	<b>3.4</b>
nt	<b>1.1</b>	nt	<1.0	nt	<b>1.0</b>	nt	<b>1.0</b>	<1.0	<b>0.8</b>	<b>1.2</b>	<b>1.4</b>	<b>1.1</b>	<1.0	<b>2.3</b>	<b>1.5</b>	<b>1.0</b>	<b>0.5</b>	<b>0.9</b>	<b>0.8</b>	<b>1.0</b>	<b>0.4</b>
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	<1.0	nt	<1.0	nt	<0.2	nt	<0.2	<1.0	<0.2	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
<1.0	<1.0	<1.0	<1.0	<1.0	<b>0.3</b>	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	<1.0	nt	<1.0	nt	<b>0.3</b>	nt	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	<b>2.1</b>	nt	<b>1.8</b>	nt	<b>2.1</b>	nt	<b>1.6</b>	<b>1.6</b>	<b>1.6</b>	<b>1.5</b>	<b>1.4</b>	<b>1.7</b>	<b>1.3</b>	<b>1.4</b>	<b>1.1</b>	<b>1.3</b>	<b>1.2</b>	<2.0	<5.0	<2.0	<2.0
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
<b>2.3</b>	<b>1.4</b>	<b>1.4</b>	<b>2.4</b>	<b>1.8</b>	<b>2.2</b>	<b>2.5</b>	<b>2.5</b>	<b>2</b>	<b>2.6</b>	<b>2.2</b>	<b>2.5</b>	<b>2.1</b>	<b>1.7</b>	<b>1.2</b>	<b>1.1</b>	<b>0.9</b>	<b>0.6</b>	<b>0.5</b>	<b>0.4</b>	<b>0.5</b>	<b>0.5</b>
<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<1.0	<1.0	<b>0.3</b>	<1.0	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt

nd = Not Detected.  
nt = Not Tested.  
J = Indicates the analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.  
E = Estimated concentration calculated for an analyte response above the valid instruction calibration range. A dilution is required to obtain an accurate quantification of the analyte.  
Bold = Detected compound.

**SWMU-20 ANALYTICAL RESULTS SUMMARY  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING  
JANUARY 1994 THROUGH PRESENT**

**VINYL CHLORIDE (µg/L)**

	Jan-94	May-95	Oct-95	Feb-96	May-96	Aug-96	Nov-96	Feb-97	May-97	Aug-97	Nov-97	Jun-98	Oct-98	Jun-99	Nov-99	Jun-00	Dec-00	Jun-01	Dec-01	Jun-02	Dec-02	Jun-03	Nov-03	May-04	Aug-04	Oct-04	Feb-05	Mar-05	May-05	Aug-05	Nov-05	Feb-06			
06A	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	4.0	5.9	31	<1.0	nt	<1.0	<1.0	1.2	4.8			
06B	13	36.53	31.8	52.29	44.78	54.5	49.4	63.7	88.7	55	62.7	46.3	4.2	48.4	25.9	8	21.58	10.62	8.9	12	11	8.4	17	9.4	2.3	3.6	<1.0	nt	<2.0	1.6	1.3	1.4			
06C	30	20.89	34.09	38.34	22.06	164	12	18.3	50.3	39.5	26.1	6	54.6	4.4	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00			
08C	130	42.13	32.69	35.33	35.96	129	41.2	201	488	256	210	20.6	<5.00	49.7	21.4	2.4	<2.00	<1.00	<1.00	<1.00	<1.00	<1.00	<3.0	<5.0	2.8	nt	3.5	<1.0	nt	<1.0	nt				
09A	240	917.05	449	1385	844.9	124	228	80.9	185	127	135	83.8	425	14	278	499	17.95	86.44	7.8	46	150	120	180	37	150	220	37	nt	<1.0	<1.0	<1.0	<1.0			
09B	140	648.6	175.6	836	228.2	104	62.6	41.7	270	20.9	50.7	439.56	132	152.36	66.6	82.6	146.7	78.9	110	7.6	27	19	360	<3.0	100	340	520	nt	24	1.7	<1.0	1.3			
09C	190	233.79	185 E	71.74	50.13	106	19.4	59.8	147	102.5	87.8	1.1	<1.00	59	16.4	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	18	8.6	5.6	8.0	3.3	<1.0	1.5	<1.0	2.2	<1.0	<1.0			
09D	nd	1.37	<5.00	<5.00	<1.00	1	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.0	nt	<1.0	<1.0			
10A	120	116.25	16.12	31.6	651.2	80.9	16.7	48.2	33.4	9.8	8.8	8.7	1.3	12.1	3.5	3	3.32	3.32	2.9	28	54	36	9.1	6.4	4.0	23	6.8	nt	7.2	76	73	150			
10C	39	28.29	33.16	40.41	18.69	11.6	10.1	9	<1.00	4.3	3.8	1.7	1.6	2.8	1.4	2.1	<1.00	<1.00	<1.00	<1.00	8.4	15	15	8.8	4.0	nt	11	nt	nt	1.9	nt	1.0	nt		
11A	39	26.80	8.37 J	12.14	14.04	3.8	1.8	<1.00	<1.00	<1.00	3.4	<1.00	<1.00	1.1	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.0	nt	nt	<1.0	nt	<1.0	nt		
12A	14	<1.00	17.16	<5.00	<1.00	2.9	8.6	<1.00	9.4	6.7	1.1	1.3	<1.00	2.7	1.06	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.0	nt	<1.0	nt	nt		
13A	12	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.0	nt	nt	<1.0	nt	<1.0	nt		
13C	760	3.03	<5.00	15.24	11.48	3.6	1.9	2.5	2.2	<1.00	<1.00	1	1.6	1.8	<1.00	<1.00	<1.00	<1.00	<1.00	1.6	3.3	4.9	2.2	2.5	nt	3.3	nt	nt	<1.0	nt	3.8	nt			
14A	170	11.38	30.32	44.4	36.4	339	232	162	270	158	70	29.1	13.74	58.2	20.9	19.7	<1.00	<1.00	<1.00	<1.00	69	28	240	110	180	650	1000	nt	<1.0	<1.0	<3.0	<1.0			
14C	120	103.49	1587.3	1477	134.78	414	175	1296	307	148	144	39.4	56.4	30.2	<1.00	<1.00	4.67	1.21	<1.00	<1.00	4.4	50	35	44	nt	75	nt	nt	6.1	nt	1.8	nt			
14E	10	1.43	<5.00	<5.00	<1.00	1.3	<1.00	<1.00	1.3	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.0	nt	<1.0	nt	nt		
15A	16	13.84	31.2	54.62	19.45	19.4	23	20.4	23.5	17.4	18.6	61.61	17.2	2.9	37	16	<10.00	3.86	1.8	2.0	3.3	<5.0	<5.0	<5.0	nt	<5.0	nt	nt	<5.0	nt	<5.0	nt			
15C	38	38.79	142.38	69.81	5.12	104	220	69	598	519	500	772 E	194 E	121.2	49.2	1.4	21.32	<1.00	1.5	<1.00	1.3	5.6	16	11	nt	17	nt	nt	6.4	nt	<1.0	nt			
15D	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	8.6	5.2	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt		
16A	6	9.18	<5.00	<5.00	8.42	4.4	<1.00	<1.00	2.2	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	
16C	15	23.46	38.59	45.16	31.71	20.8	11.8	11.3	9.1	3	<1.00	1.4	<1.00	1.9	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt		
17A	nd	<1.00	<5.00	<5.00	<1.00	1	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	
17C	10	2.32	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt		
17D	nd	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	
18A	nd	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	nt	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt	
18C	nd	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	1.1	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	
18D	nd	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	
19A	nd	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	<1.0	nt	nt	<1.0	nt	<1.0	<1.0	<1.0	<1.0	<1.0	nt	
19C	5.5	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	
19D	nd	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	
20A	nd	<1.00	<5.00	<5.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	
20C	47	20.12	12.63	13.77	8.32	6.7	3.4	3.3	3.4	<1.00	<1.00	1.6	1.8	<1.00	1.9	<1.00	1.06	<1.00	<1.00	1.4	2.7	4.0	3.1	2.4	nt	4.6	nt	2.3	nt	2.9	nt	nt			
20D	nd	6.98	<5.00	<5.00	31.12	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	
21A	nt	nt	nt	nt	<1.00		<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	
21C	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	
22A	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	2.0	2.9	3.2	2.2	3.3	nt	
23A	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	nt

**SWMU-20 ANALYTICAL RESULTS SUMMARY  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING  
JANUARY 1994 THROUGH PRESENT**

**VINYL CHLORIDE (µg/L)**

May-06	Aug-06	Nov-06	Feb-07	May-07	Nov-07	May-08	Nov-08	May-09	Nov-09	May-10	Nov-10	May-11	Nov-11	May-12	Nov-12	May-13	Nov-13	May-14
1.6	1.5	2.1	6.7	2.9	1.2	1.4	<1.0	<4.0	<1.0	1.9	1.7	1.4	0.8	1.2	0.8	1.3	2.4	1.5
1.3	1.1	2.6	9.5	6.5	1	<1.0	<1.0	<1.0	<1.0	4.2	5.4	5.2	0.8	6.0	3.7	4.3	2.5	2.4
<1.0	<1.0	<0.2	<1.0	<1.0	0.3	<1.0	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
<10	nt	<5.0	nt	<3.0	<5.0	<5.0	<5.0	<1.0	<3.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
<1.0	1.2	1.1	<1.0	2.8	<1.0	85	42	<10	<5.0	<1.0	<1.0	<2.0	<0.2	<0.2	<2.0	<2.0	<2.0	<2.0
<1.0	<1.0	0.5	<1.0	<1.0	<1.0	0.4	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	0.2	<1.0	<1.0	<3.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
<1.0	nt	<1.0	nt	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
19	20	9.2	35	44	78	180	5.0	<2.0	<1.0	<1.0	<1.0	<2.0	0.4	0.4	0.4	0.3	0.4	<1.0
2.2	nt	2.6	nt	5.8	5.6	6.9	7.5	<1.0	<1.0	<1.0	4.4	4.7	4.3	4.0	4.4	4.5	3.7	2.9
<1.0	nt	<1.0	nt	<1.0	<1.0	0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	0.4	0.4	<2.0	<2.0	<2.0	<2.0
<1.0	nt	<0.2	nt	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2
<1.0	nt	<0.2	nt	<0.2	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<0.2	<0.2	<0.2
2.2	nt	3.4	nt	4.4	2	0.6	2.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	0.3	<2.0	<2.0	<2.0	<1.0
<2.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	0.2	<0.2	<0.5	<0.2	0.3
<1.0	nt	1.0	nt	2.5	11	22	4.3	1.1	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<2.0	<2.0	<2.0	<1.0
<1.0	nt	<0.2	nt	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	<2.0	<2.0	<2.0	<1.0
<5.0	nt	<3.0	nt	2.6	1.3	<3.0	<2.0	<3.0	1.4	1.6	1.4	<10	1.0	1.2	0.8	1.1	0.8	1.0
<1.0	nt	<0.2	nt	2.2	2.5	6.6	6.6	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<2.0	<5.0	2.3	2.9
<1.0	nt	<1.0	nt	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
<1.0	nt	<0.2	nt	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<0.2	<0.5	<0.2	<0.2
6.3	nt	<0.2	nt	10	8.9	7.9	8.8	6.3	5.6	3.4	2.8	3.2	2.5	4.2	3.8	2.8	2.1	1.2
<1.0	nt	<0.2	nt	<0.2	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<0.2	<0.2	<0.2
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
<1.0	nt	<0.2	nt	0.2	<1.0	0.2	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
<1.0	nt	<0.2	nt	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
1.6	nt	1.5	nt	1.8	1.3	2.5	2.7	2.0	2.3	1.8	1.4	1.8	2.1	1.5	<2.0	<5.0	<2.0	<2.0
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
1.7	2.4	2.4	2.3	2.7	1.3	1.9	3.1	2.5	1.8	1.7	2.7	2.2	1.7	2.0	1.8	2.0	1.7	1.6
<1.0	<1.0	<0.2	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt

nd = Not Detected.  
 nt = Not Tested.  
 J = Indicates the analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.  
 E = Estimated concentration calculated for an analyte response above the valid instruction calibration range. A dilution is required to obtain an accurate quantification of the analyte.  
 Bold = Detected compound.





**SWMU-20 ANALYTICAL RESULTS SUMMARY  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING  
JANUARY 1994 THROUGH PRESENT**

**BENZENE (µg/L)**

May-06	Aug-06	Nov-06	Feb-07	May-07	Nov-07	May-08	Nov-08	May-09	Nov-09	May-10	Nov-10	May-11	Nov-11	May-12	Nov-12	May-13	Nov-13	May-14
<1.0	<1.0	<b>0.4</b>	<1.0	<1.0	<b>0.3</b>	<1.0	<1.0	<4.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<0.2	<0.5	<0.2	<0.2
<1.0	<1.0	<0.2	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<0.2	<0.5	<0.2	<0.2
<b>1.3</b>	<b>1.2</b>	<b>1.2</b>	<1.0	<1.0	<b>0.9</b>	<1.0	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
<10	nt	<5.0	nt	<3.0	<5.0	<5.0	<5.0	<1.0	<3.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<0.2	<1.0	<10	<5.0	<1.0	<1.0	<2.0	<0.2	<0.2	<2.0	<2.0	<2.0	<2.0
<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<0.2	<1.0	<1.0	<3.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
<1.0	nt	<1.0	nt	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
<1.0	<1.0	<b>0.3</b>	<1.0	<1.0	<1.0	<1.0	<1.0	<2.0	<1.0	<1.0	<1.0	<2.0	<0.2	<0.2	<0.2	<0.2	<0.2	<1.0
<1.0	nt	<b>0.2</b>	nt	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2
<1.0	nt	<1.0	nt	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<2.0	<2.0	<2.0	<2.0
<1.0	nt	<0.2	nt	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2
<1.0	nt	<0.2	nt	<0.2	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2
<b>2.1</b>	nt	<b>2.1</b>	nt	<b>1.2</b>	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<2.0	<2.0	<2.0	<1.0
<2.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<0.2	<0.5	<0.2	<0.2
<1.0	nt	<0.2	nt	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<2.0	<2.0	<2.0	<1.0
<1.0	nt	<0.2	nt	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
<5.0	nt	<3.0	nt	<1.0	<1.0	<3.0	<1.0	<3.0	<1.0	<1.0	<1.0	<10	<b>0.4</b>	<1.0	<b>0.4</b>	<0.5	<b>0.3</b>	<b>0.3</b>
<1.0	nt	<b>0.4</b>	nt	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<2.0	<5.0	<2.0	<2.0
<1.0	nt	<1.0	nt	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
<1.0	nt	<0.2	nt	<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<0.2	<0.5	<0.2	<0.2
<1.0	nt	<0.2	nt	<1.0	<1.0	<b>0.2</b>	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<0.2	<0.5	<0.2	<0.2
<1.0	nt	<0.2	nt	<0.2	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
<1.0	nt	<0.2	nt	<0.2	<1.0	<0.2	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
<1.0	<1.0	<0.2	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
<1.0	nt	<0.2	nt	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
<1.0	<1.0	<b>0.4</b>	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<b>0.2</b>	<b>0.4</b>	<b>0.4</b>	<b>0.5</b>	<b>0.3</b>	<b>0.4</b>
<1.0	<1.0	<0.2	<1.0	<1.0	<b>0.2</b>	<1.0	<1.0	<1.0	<1.0	nt	nt	nt	nt	nt	nt	nt	nt	nt

nd = Not Detected.  
 nt = Not Tested.  
 J = Indicates the analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.  
 E = Estimated concentration calculated for an analyte response above the valid instruction calibration range. A dilution is required to obtain an accurate quantification of the analyte.  
 Bold = Detected compound.

**SWMU-20 ANALYTICAL RESULTS SUMMARY  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING  
JANUARY 1994 THROUGH PRESENT**

**NAPHTHALENE (µg/L)**

	Jan-94	May-95	Oct-95	Feb-96	May-96	Aug-96	Nov-96	Feb-97	May-97	Aug-97	Nov-97	Jun-98	Oct-98	Jun-99	Nov-99	Jun-00	Dec-00	Jun-01	Dec-01	Jun-02	Dec-02	Jun-03	Nov-03	May-04	Aug-04	Oct-04	Feb-05	Mar-05	May-05	Aug-05	Nov-05	Feb-06	
06A	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	<5.0	<5.0	<5.0	<5.0	nt	<5.0	<5.0	<5.0	<5.0	
06B	nt	nt	nt	nt	<1.00	<b>2.8</b>	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<b>1.4</b>	<1.00	<1.00	<1.00	<1.00	<b>4.5</b>	<b>1.8</b>	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	nt	<10	<5.0	<5.0	<5.0		
06C	nt	nt	nt	nt	<b>29.26</b>	<b>10.4</b>	<b>9.1</b>	<b>8.8</b>	<b>7.2</b>	<1.00	<b>18.4</b>	<b>3</b>	<b>25.1</b>	<b>3.4</b>	<1.00	<b>7.7</b>	<b>44.97</b>	<b>9.73</b>	<b>2.8</b>	<5.0	<5.0	<5.0	<5.0	<b>220</b>	<b>14</b>	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0		
08C	nt	nt	nt	nt	<b>351.9</b>	<b>401</b>	<b>155</b>	<b>370</b>	<b>234</b>	<b>118</b>	<b>292</b>	<b>600 E</b>	<b>38.6</b>	<b>230</b>	<b>137</b>	<b>109.2</b>	<b>174.1</b>	<b>125</b>	<b>210</b>	<b>180 J</b>	<b>290</b>	<b>390</b>	<b>300</b>	<b>130</b>	nt	<b>180</b>	nt	<b>130</b>	nt	<b>82</b>	nt		
09A	nt	nt	nt	nt	<50.00	<3.33	<10.00	<4.00	<5.00	<1.00	<b>7</b>	<1.00	<10.00	<1.00	<10.00	<10.00	<b>8.65</b>	<b>3.63</b>	<1.0	<5.0	<5.0	<75	<100	<100	<15	<25	<50	nt	<5.0	<5.0	<5.0	<5.0	
09B	nt	nt	nt	nt	<10.00	<2.00	<1.00	<1.00	<b>13.8</b>	<b>22.4</b>	<2.00	<3.33	<10.00	<b>3.4</b>	<b>4.6</b>	<2.00	<b>11.2</b>	<b>2.24</b>	<b>3.1</b>	<5.0	<5.0	<5.0	<5.0	<15	<25	<25	<50	nt	<5.0	<5.0	<5.0	<5.0	
09C	nt	nt	nt	nt	<1.00	<b>1.2</b>	<1.00	<b>8.8</b>	<b>6.5</b>	<1.00	<b>25</b>	<1.00	<1.00	<b>9.9</b>	<b>6.8</b>	<1.00	<b>1.67</b>	<b>1.8</b>	<b>1.3</b>	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<b>7.7</b>	<b>68</b>	nt	<b>51</b>	<b>29</b>	<b>12</b>	<b>5.1</b>	
09D	nt	nt	nt	nt	<1.00	<b>1.3</b>	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	nt	<5.0	nt	<5.0	nt		
10A	nt	nt	nt	nt	<10.00	<b>4.2</b>	<3.33	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	nt	<5.0	<5.0	<5.0	<5.0		
10C	nt	nt	nt	nt	<b>14.27</b>	<b>30.5</b>	<b>6.3</b>	<b>56.1</b>	<b>6.4</b>	<b>7.6</b>	<b>5.8</b>	<b>2.8</b>	<1.00	<b>3.8</b>	<b>4.7</b>	<b>2.7</b>	<b>5.77</b>	<1.00	<b>36</b>	<b>5.0</b>	<5.0	<5.0	<5.0	<b>9.4</b>	nt	<5.0	nt	nt	<5.0	nt	<5.0	nt	
11A	nt	nt	nt	nt	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<b>5.1</b>	<1.00	<1.00	<1.0	<5.0	<5.0	<5.0	<5.0	<5.0	nt	<5.0	nt	nt	<5.0	nt	<5.0	nt	
12A	nt	nt	nt	nt	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	nt	<5.0	nt	nt	<5.0	nt	<5.0	nt
13A	nt	nt	nt	nt	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.0	<5.0	<5.0	<5.0	<5.0	<5.0	nt	<5.0	nt	nt	<5.0	nt	<5.0	nt	
13C	nt	nt	nt	nt	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.0	<5.0	<5.0	<5.0	<5.0	<5.0	nt	<5.0	nt	nt	<5.0	nt	<5.0	nt	
14A	nt	nt	nt	nt	<1.00	<10.00	<5.00	<4.00	<2.00	<2.00	<2.00	<1.00	<1.00	<b>150</b>	<b>4.8</b>	<b>235</b>	<b>113.23</b>	<b>84.7</b>	<b>35</b>	<b>5.7</b>	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<25	<25	nt	<50	<50	<15	<5.0
14C	nt	nt	nt	nt	<2.00	<10.00	<1.00	<10.00	<10.00	<10.00	<b>11.8</b>	<b>7.2</b>	<b>6.5</b>	<b>6.3</b>	<b>7.3</b>	<b>17.2</b>	<b>8.7</b>	<b>6.79</b>	<b>3.5</b>	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	nt	<5.0	nt	nt	<5.0	nt	<5.0	nt
14E	nt	nt	nt	nt	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.0	<5.0	<5.0	<5.0	<5.0	<5.0	nt	<5.0	nt	nt	<5.0	nt	<5.0	nt	
15A	nt	nt	nt	nt	<b>423.67</b>	<b>239</b>	<b>152</b>	<b>247</b>	<b>136</b>	<b>67.3</b>	<b>465 E</b>	<b>1721 E</b>	<b>916</b>	<b>58.9</b>	<b>561</b>	<b>797</b>	<b>695.6</b>	<b>985.5</b>	<b>1100</b>	<b>840 J</b>	<b>510</b>	<b>370</b>	<b>490</b>	<b>700</b>	nt	<b>430</b>	nt	nt	<b>440</b>	nt	<b>390</b>	nt	
15C	nt	nt	nt	nt	<1.00	<b>1</b>	<1.00	<b>4.4</b>	<10.00	<10.00	<10.00	<3.33	<b>4.8</b>	<2.00	<2.00	<b>29.8</b>	<1.00	<1.00	<1.0	<5.0 J	<5.0	<5.0	<5.0	<5.0	nt	<5.0	nt	nt	<5.0	nt	<5.0	nt	
15D	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<b>7.4</b>	<5.0	<5.0	<5.0	<5.0	<5.0	nt	<5.0	nt	nt	<5.0	nt	<5.0	nt	
16A	nt	nt	nt	nt	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<b>3.1</b>	<5.0	<5.0	<5.0	<5.0	<5.0	nt	<5.0	nt	nt	<5.0	nt	<5.0	nt	
16C	nt	nt	nt	nt	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.0	<5.0	<5.0	<5.0	<5.0	<5.0	nt	<5.0	nt	nt	<5.0	nt	<5.0	nt	
17A	nt	nt	nt	nt	<1.00	<b>62</b>	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	<1.0	<5.0	<5.0	<5.0	<5.0	<5.0	nt	<5.0	nt	nt	nt	nt	<5.0	nt	
17C	nt	nt	nt	nt	<1.00	<1.00	<b>26.6</b>	<1.00	<b>0.6</b>	<b>37.3</b>	<b>106</b>	<1.00	<1.00	<b>31.9</b>	<b>16.6</b>	<b>13.7</b>	nt	<b>12.12</b>	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
17D	nt	nt	nt	nt	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00
18A	nt	nt	nt	nt	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	nt	<5.0	nt	nt	nt	nt	nt	nt	nt	nt
18C	nt	nt	nt	nt	<1.00	<1.00	<1.00	<b>1.7</b>	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<b>1.1</b>	<1.00	<1.00	<1.0	<5.0	<5.0	<5.0	<5.0	<5.0	nt	<5.0	nt	nt	<5.0	nt	<5.0	nt	
18D	nt	nt	nt	nt	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
19A	nt	nt	nt	nt	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<b>1.54</b>	nt	nt	nt	nt	nt	<5.0	nt	nt	<5.0	nt	<5.0	<5.0	<5.0	<5.0
19C	nt	nt	nt	nt	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.0	<5.0	<5.0	<5.0	<5.0	<5.0	nt	<5.0	nt	nt	<5.0	nt	<5.0	nt	
19D	nt	nt	nt	nt	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
20A	nt	nt	nt	nt	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<b>5.48</b>	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
20C	nt	nt	nt	nt	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<b>1.81</b>	<1.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	nt	<5.0	nt	<5.0	nt	<5.0	nt	
20D	nt	nt	nt	nt	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
21A	nt	nt	nt	nt	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.0	<5.0	<5.0	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
21C	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	<b>207.4</b>	<1.0	<5.0	<5.0	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
22A	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	<b>9.9</b>	<b>140</b>	<b>180</b>	<b>170</b>	<b>210 J</b>
23A	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	<b>19</b>	<b>130</b>	<b>100</b>	<5.0	<b>45</b>


**SWMU-20 ANALYTICAL RESULTS SUMMARY  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING  
JANUARY 1994 THROUGH PRESENT**

**NAPHTHALENE (µg/L)**


May-06	Aug-06	Nov-06	Feb-07	May-07	Nov-07	May-08	Nov-08	May-09	Nov-09	May-10	Nov-10	May-11	Nov-11	May-12	Nov-12	May-13	Nov-13	May-14
<5.0	<5.0	<0.5	<5.0	<5.0	<0.5	<5.0	<5.0	<20	<5.0	<5.0	<5.0	<5.0	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5
<5.0	<5.0	<b>0.6</b>	<5.0	<5.0	<0.5	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5
<5.0	<5.0	<b>5.0</b>	<5.0	<5.0	<b>4.6</b>	<5.0	<5.0	<5.0	<5.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
<b>910</b>	nt	<b>440</b>	nt	<b>500</b>	<b>540</b>	<b>180</b>	<b>1100</b>	<b>62</b>	<b>65</b>	nt	nt	nt	nt	nt	nt	nt	nt	nt
<5.0	<5.0	<0.5	<5.0	<5.0	<5.0	<0.5	<5.0	<50	<25	<5.0	<5.0	<5.0	<b>5.3</b>	<b>9.5</b>	<b>7.5</b>	<b>56</b>	<b>23</b>	<b>9.9</b>
<5.0	<5.0	<0.5	<5.0	<5.0	<5.0	<b>0.6</b>	<5.0	<5.0	<5.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
<5.0	<5.0	<b>14</b>	<b>18</b>	<b>5.5</b>	<5.0	<b>6.7</b>	<5.0	<b>56</b>	<b>69</b>	nt	nt	nt	nt	nt	nt	nt	nt	nt
<5.0	nt	<2.5	nt	<5.0	<5.0	<0.5	<5.0	<5.0	<5.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
<5.0	<5.0	<0.5	<5.0	<5.0	<5.0	<5.0	<5.0	<10	<5.0	<5.0	<5.0	<5.0	<0.5	<0.5	<0.5	<0.5	<0.5	<2.5
<5.0	nt	<0.5	nt	<5.0	<5.0	<0.5	<5.0	<b>100</b>	39	12	<5.0	<5.0	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5
<5.0	nt	<5.0	nt	<5.0	<5.0	<0.5	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<0.5	<0.5	<5.0	<5.0	<5.0	<5.0
<5.0	nt	<0.5	nt	<5.0	<5.0	<0.5	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5
<5.0	nt	<b>16</b>	nt	<b>16</b>	<5.0	<b>0.5</b>	<5.0	<5.0	<5.0	22	<b>6.5</b>	<5.0	<5.0	<0.5	<5.0	<5.0	<5.0	<2.5
<10	<5.0	<b>7.0</b>	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<b>0.5</b>	<0.5	<b>0.8</b>	<0.5	<b>0.7</b>	<0.5	<0.5
<5.0	nt	<b>6.3</b>	nt	<b>6.2</b>	<5.0	<5.0	<5.0	<5.0	<5.0	15	<5.0	<5.0	<0.5	<0.5	<5.0	<5.0	<5.0	<2.5
<5.0	nt	<0.5	nt	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
<b>220</b>	nt	<b>180</b>	nt	<b>72</b>	<b>170</b>	<b>180</b>	<b>230</b>	<b>170</b>	<b>190</b>	<b>310</b>	<b>240</b>	<b>210</b>	<b>190</b>	<b>170</b>	<b>120</b>	<b>84</b>	<b>180</b>	<b>89</b>
<5.0	nt	<0.5	nt	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<0.5	<0.5	<5.0	<5.0	<5.0	<5.0
<5.0	nt	<2.5	nt	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
<5.0	nt	<0.5	nt	<5.0	<5.0	<0.5	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5
<5.0	nt	<0.5	nt	<5.0	<5.0	<0.5	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5
<5.0	nt	<0.5	nt	<0.5	<5.0	<0.5	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
<5.0	nt	<0.5	nt	<b>0.6</b>	<5.0	<0.5	<b>86</b>	<b>47</b>	<b>&lt;5.0</b>	nt	nt	nt	nt	nt	nt	nt	nt	nt
<5.0	<5.0	<0.5	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
<5.0	nt	<b>0.5</b>	nt	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt	nt
<b>120</b>	<b>200</b>	<b>140</b>	<b>110</b>	<b>100</b>	<b>25</b>	<b>41</b>	<b>32</b>	<b>51</b>	<b>15</b>	<b>14</b>	<b>16</b>	<b>20</b>	<b>12</b>	<b>15</b>	<b>9.2</b>	<b>11</b>	<b>7.1</b>	<b>9.8</b>
<b>69</b>	<b>140</b>	<b>9.0</b>	<b>26</b>	<b>36</b>	<b>6.1</b>	<b>5.3</b>	<5.0	<b>9.8</b>	<b>&lt;5.0</b>	nt	nt	nt	nt	nt	nt	nt	nt	nt

nd = Not Detected.  
nt = Not Tested.  
J = Indicates the analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.  
E = Estimated concentration calculated for an analyte response above the valid instruction calibration range. A dilution is required to obtain an accurate quantification of the analyte.  
**Bold** = Detected compound.

# DEVELOPMENTAL CENTER WELLS TETRACHLOROETHENE CONCENTRATIONS (Wells with PCE Historically Detected over 50 ppb)




# DEVELOPMENTAL CENTER WELLS TRICHLOROETHENE CONCENTRATIONS (Wells with TCE Historically Detected over 50 ppb)




# DEVELOPMENTAL CENTER WELLS

## CIS-1,2 DICHLOROETHENE CONCENTRATIONS


(Wells with cis-1,2 DCE Historically Detected over 50 ppb)



# DEVELOPMENTAL CENTER WELLS VINYL CHLORIDE CONCENTRATIONS (Wells with VC Historically Detected over 50 ppb)



# DEVELOPMENTAL CENTER WELLS BENZENE CONCENTRATIONS (Wells with Benzene Historically Detected over 50 ppb)





**SWMU-20 CLEANUP ACTION SUMMARY - SOURCE ZONE  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING**

Well	Date	Elapsed Time from Injections (a) (days)				Volatile Organic Compounds						Aquifer Redox Conditions					Donor Parameters		Notes
		1st Injection	2nd Injection	3rd (b) Injection	4th Injection	Proposed Groundwater Cleanup Levels (d)						DO (mg/L)	ORP (mV)	Iron II (mg/L)	Sulfate (mg/L)	Methane (µg/L)	pH	TOC (mg/L)	
						5.3 (µg/L)	1.4 (µg/L)	134 (µg/L)	2.4 (µg/L)	---	---								
06A (c)	06/15/2004	-2				<1.0	1.0	23	4.0	<0.50	<0.50	6.34	-19.6	0.8	58.9	<0.50	6.5	18.8	---
06A (c)	08/23/2004	67				<1.0	<1.0	45	5.9	<0.50	<0.50	0.46	92	3.5	40.7	21	7.0	288	Hazy brown
06A (c)	10/19/2004	124	-58			<1.0	<1.0	2.6	31	<0.50	<0.50	0.70	54	3.0	44.8	530	6.8	80.8	---
06A (c)	02/22/2005	250	68			<1.0	<1.0	3.3	<1.0	<0.50	<0.50	1.15	187	2.4	<0.1	130	6.8	244	---
06A (c)	05/16/2005	333	151			<1.0	<1.0	2.6	<1.0	<0.50	<0.50	1.25	58	3.0	0.1	10000	6.9	145	---
06A (c)	08/22/2005	431	249			<1.0	<1.0	1.6	<1.0	<0.50	<0.50	1.26	212	2.7	3.1	390	6.8	54.2	Clear, with yellow tint
06A (c)	11/14/2005	515	333			<1.0	<1.0	1.3	1.2	<0.50	<0.50	0.93	108	3.0	0.1	3700	6.9	31.8	---
06A (c)	02/22/2006	615	433			<1.0	<1.0	1.4	4.8	<11.4	<12.3	0.80	186	2.6	60.4	10100	6.4	15.5	---
06A (c)	05/18/2006	700	518			<1.0	<1.0	<1.0	1.6	<11	<12	6.41	1	3.0	20.9	16000	6.6	23.9	---
06A (c)	08/16/2006	790	608			<1.0	<1.0	<1.0	1.5	<1.1	<1.2	0.89	240	2.2	23.1	18800	6.5	23.2	---
06A (c)	11/29/2006	895	713			<0.2	<0.2	0.4	2.1	<1.1	<1.2	2.09	102	2.6	33.1	20200	6.5	31.4	---
06A (c)	02/23/2007	981	799			<1.0	<1.0	<1.0	6.7	<1.1	<1.2	0.65	-97	4.5	26.2	17400	6.5	24.6	---
06A (c)	05/24/2007	1071	889			<1.0	<1.0	<1.0	2.9	<1.1	2.0	0.56	184	4.0	21.0	18300	6.7	21.5	---
06A (c)	11/30/2007	1261	1079			<0.2	<0.2	<0.2	1.2	<1.1	2.2	0.80	173	3.0	29.1	21900	6.7	22.6	---
06A (c)	05/21/2008	1434	1252		-96	<1.0	<1.0	<1.0	1.4	<1.1	1.3	2.11	-82	2.5	21.0	13200	6.9	20.1	---
06A (c)	11/25/2008	1622	1440		92	<1.0	<1.0	1.7	<1.0	<1.1	<1.2	1.71	-73	3.4	0.1	19700	6.5	150	---
06A (c)	05/20/2009	1798	1616		268	<4.0	<4.0	<4.0	<4.0	<1.1	<1.2	0.52	-45	4.0	<0.5	19500	6.8	38.2	---
06A (c)	11/19/2009	1981	1799		451	<1.0	<1.0	1.9	<1.0	<1.1	<1.2	2.66	6	2.8	0.8	20100	6.2	25.4	---
06A (c)	5/24/2010	2167	1985		637	<1.0	<1.0	1.3	1.9	<1.1	<1.2	3.56	448	2.0	16	19900	6.6	19.3	---
06A (c)	11/11/2010	2338	2156		808	<1.0	<1.0	<1.0	1.7	<1.1	<1.2	4.75	106	2.6	0.4	24700	7.0	20.2	---
06A (c)	5/4/2011	2512	2330		982	<1.0	<1.0	<1.0	1.4	<1.1	<1.2	2.14	22	2.5	<0.2	21400	7.1	13.6	---
06A (c)	11/13/2011	2705	2523		1175	<0.2	<0.2	0.3	0.8	<1.1	<1.2	5.80	-54	1.0	0.3	6370	7.2	12.7	---
06A (c)	5/15/2012	2889	2707		1359	<0.2	<0.2	0.4	1.2	<1.0	<1.0	0.08	66	2.0	4.3	13000	6.7	11.6	---
06A (c)	11/14/2012	3072	2890		1542	<0.2	<0.2	0.3	0.8	<1.0	<4.0	0.02	-0.5	1.5	<0.30	13000	6.9	9.0	---
06A (c)	5/21/2013	3260	3078		1730	<0.5	<0.5	<0.5	1.3	<1.0	<1.0	0.17	-434	2.6	3.3	5200	7.9	8.8	---
06A (c)	11/12/2013	3435	3253		1905	<0.2	<0.2	0.4	2.4	<1.0	<1.0	2.68	-298	1.2	5.8	3500	6.8	8.3	---
06A (c)	5/7/2014	3611	3429		2081	<0.2	<0.2	0.4	1.5	<1.0	<1.0	3.60	-386	1.5	11.2	1300	7.1	7.2	---
06B	05/04/2004	-44				9.5	3.2	10	9.4	<0.50	<0.50	0.36	179	4.5	18.7	130	6.8	25.6	Clear, yellow tint
06B	08/23/2004	67				1.9	1.2	13	2.3	<0.50	<0.50	0.45	115	3.2	33.8	1100	6.9	177	Yellow-brown tint (nearly clear)
06B	10/19/2004	124	-58			<1.0	<1.0	10	3.6	<0.50	<0.50	0.61	217	3.5	14.8	590	6.7	53.6	Yellow tint
06B	02/22/2005	250	68			<1.0	<1.0	11	<1.0	<0.50	<0.50	0.79	224	2.6	<0.5	3800	6.9	968	---
06B	05/16/2005	333	151			<2.0	<2.0	5.5	<2.0	<0.50	<0.50	1.51	133	3.5	<0.5	2300	6.9	336	Clear, yellow-brown tint
06B	08/22/2005	431	249			<1.0	<1.0	1.8	1.6	<0.50	<0.50	1.21	217	2.8	<0.1	440	6.9	100	Clear, with yellow tint
06B	11/14/2005	515	333			<1.0	<1.0	1.1	1.3	<0.50	<0.50	1.05	241	2.8	<0.1	2900	6.9	64.4	---
06B	02/22/2006	615	433			<1.0	<1.0	<1.0	1.4	53.5	<12.3	0.74	184	2.6	14.8	13000	6.4	30.4	---
06B	05/18/2006	700	518			<1.0	<1.0	<1.0	1.3	<11	<12	2.25	52	3.2	13.6	16000	6.6	25.9	---
06B	08/16/2006	790	608			<1.0	<1.0	<1.0	1.1	<1.1	<1.2	0.82	225	2.4	12.9	21700	6.5	14.7	---
06B	11/29/2006	895	713			<0.2	<0.2	1.4	2.6	<1.1	<1.2	1.82	111	2.4	10.9	22000	6.5	25.2	---
06B	02/23/2007	981	799			<1.0	<1.0	3.8	9.5	<1.1	<1.2	0.75	-66	5.0	25.0	17700	6.5	21.1	---
06B	05/24/2007	1071	889			<1.0	<1.0	1.4	6.5	<1.1	<1.2	0.58	151	3.0	11.3	18500	6.6	21.4	---
06B	11/30/2007	1261	1079			<0.2	<0.2	<0.2	1.0	<1.1	4.0	0.83	135	4.0	26.3	24900	6.4	26.5	---
06B	05/21/2008	1434	1252		-96	<1.0	<1.0	<1.0	<1.0	<1.1	4.9	2.66	-61	3.4	21.1	12700	6.7	20.4	---
06B	11/25/2008	1622	1440		92	<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	2.53	-68	2.4	0.2	18400	6.6	19.6	---
06B	05/20/2009	1798	1616		268	<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	0.33	-36	4.0	<0.5	25300	6.9	20.9	---
06B	11/19/2009	1981	1799		451	<1.0	<1.0	<1.0	<1.0	<1.1	6.7	1.01	10	2.8	0.1	22500	6.9	20.0	---

**SWMU-20 CLEANUP ACTION SUMMARY - SOURCE ZONE  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING**

Well	Date	Elapsed Time from Injections (a) (days)				Volatile Organic Compounds						Aquifer Redox Conditions					Donor Parameters		Notes
		1st Injection	2nd Injection	3rd (b) Injection	4th Injection	Proposed Groundwater Cleanup Levels (d)						DO (mg/L)	ORP (mV)	Iron II (mg/L)	Sulfate (mg/L)	Methane (µg/L)	pH	TOC (mg/L)	
						5.3 (µg/L)	1.4 (µg/L)	134 (µg/L)	2.4 (µg/L)	---	---								
06B	5/24/2010	2167	1985		637	<1.0	<1.0	<1.0	<b>4.2</b>	<1.1	<b>1.6</b>	3.05	417	2.0	3.0	7110	7.0	19.1	---
06B	11/11/2010	2338	2156		808	<1.0	<1.0	<1.0	<b>5.4</b>	<1.1	<b>1.4</b>	3.40	112	2.0	8.6	4600	7.1	15.8	---
06B	5/4/2011	2512	2330		982	<1.0	<1.0	<1.0	<b>5.2</b>	<1.1	<1.2	2.55	57	2.2	19.7	2120	7.1	12.6	---
06B	11/13/2011	2705	2523		1175	<0.2	<0.2	<0.2	<b>0.8</b>	<1.1	<1.2	6.10	-34	1.5	0.3	2260	7.3	14.8	---
06B	5/15/2012	2889	2707		1359	<0.2	<0.2	<b>0.5</b>	<b>6.0</b>	<1.0	<b>1.3</b>	0.14	71	1.8	10.9	2200	6.6	11.4	---
06B	11/14/2012	3072	2890		1542	<0.2	<0.2	<0.2	<b>3.7</b>	<1.0	<b>1.8</b>	0.02	10	2.0	7.0	2300	6.8	13.7	---
06B	5/21/2013	3260	3078		1730	<0.5	<0.5	<0.5	<b>4.3</b>	<1.0	<1.0	0.17	-427	2.5	20.1	720	7.7	11.0	---
06B	11/12/2013	3435	3253		1905	<0.2	<0.2	<0.2	<b>2.5</b>	<1.0	<1.0	2.62	-309	1.5	4.0	350	7.0	15.5	---
06B	5/7/2014	3611	3429		2081	<0.2	<0.2	<0.2	<b>2.4</b>	<1.0	<1.0	3.50	-320	1.6	2.8	1200	7.1	10.2	---
06C	05/04/2004	-44				<1.0	<1.0	<1.0	<1.0	<0.50	<b>0.6</b>	0.40	93	5.0	20.7	360	6.7	29.0	---
06C	08/23/2004	67				<1.0	<1.0	<b>1.4</b>	<1.0	<1.0	<b>5.9</b>	0.63	95	2.5	42.7	3100	6.3	1560	White froth on surface of purge water
06C	10/19/2004	124	-58			<1.0	<1.0	<1.0	<1.0	<0.50	<0.50	2.00	206	3.0	18.1	450	6.3	464	Yellow tint
06C	02/22/2005	250	68			<1.0	<1.0	<b>3.6</b>	<1.0	<0.50	<0.50	0.82	198	2.6	<0.5	2400	6.9	858	---
06C	05/16/2005	333	151			<1.0	<1.0	<b>1.1</b>	<1.0	<0.50	<0.50	1.94	98	3.0	0.2	2700	7.0	111	Clear, with yellow tint
06C	08/22/2005	431	249			<1.0	<1.0	<b>1.1</b>	<1.0	<0.50	<0.50	1.36	194	2.8	<0.1	510	7.0	68.7	Clear, with yellow tint
06C	11/14/2005	515	333			<1.0	<1.0	<b>1.1</b>	<1.0	<0.50	<0.50	1.07	258	2.0	<0.1	2900	7.0	48.3	---
06C	02/22/2006	615	433			<1.0	<1.0	<1.0	<1.0	<b>47.7</b>	<12.3	0.88	247	1.4	47.5	12300	6.6	93.4	---
06C	05/18/2006	700	518			<1.0	<1.0	<1.0	<1.0	<11	<12	4.88	129	2.0	30.6	15000	6.6	36.6	---
06C	08/16/2006	790	608			<1.0	<1.0	<1.0	<1.0	<1.1	<b>2.3</b>	0.93	231	1.6	31.8	18900	6.6	13.4	---
06C	11/29/2006	895	713			<0.2	<0.2	<b>0.3</b>	<0.2	<1.1	<b>1.4</b>	2.25	192	1.8	27.3	20600	6.6	46.4	---
06C	02/23/2007	981	799			<1.0	<1.0	<1.0	<1.0	<1.1	<b>1.7</b>	1.08	-46	4.0	25.9	18900	6.4	39.0	---
06C	05/24/2007	1071	889			<1.0	<1.0	<1.0	<1.0	<1.1	<b>2.0</b>	0.72	216	3.5	20.8	20800	6.5	34.0	---
06C	11/30/2007	1261	1079			<0.2	<0.2	<b>0.2</b>	<b>0.3</b>	<1.1	<b>2.8</b>	1.58	174	4.2	32.6	30500	6.2	40.2	---
06C	05/21/2008	1434	1252		-96	<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	2.91	-16	2.5	21.0	23800	6.3	31.9	---
06C	11/25/2008	1622	1440		92	<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	3.39	-66	2.6	<0.1	28700	6.8	634	---
06C	05/20/2009	1798	1616		268	<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	0.66	-28	3.5	<0.8	20600	6.9	39.2	---
06C	11/19/2009	1981	1799		451	<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	1.89	26	NM	<0.1	25600	6.2	42.8	---
09A	05/03/2004	-45				<b>150</b>	<b>230</b>	<b>970</b>	<b>37</b>	<0.50	<0.50	0.46	287	1.0	64.2	8.4	6.7	16.2	Clear, yellow tint
09A	08/23/2004	67				<3.0	<b>11</b>	<b>370</b>	<b>150</b>	<b>4.2</b>	<0.50	0.40	143	2.6	51.8	4.7	7.1	56.8	Clear with black tint, H2S odor
09A	10/19/2004	124	-58			<5.0	<b>19</b>	<b>460</b>	<b>220</b>	<b>2.7</b>	<0.50	0.53	219	4.0	77.4	17	6.9	19.6	Clear, slightly yellow tint
09A	02/21/2005	249	67			<1.0	<1.0	<b>41</b>	<b>37</b>	<b>1.9</b>	<0.50	0.78	169	2.0	<0.5	1500	7.1	2110	Hazy, yellow color
09A	05/11/2005	328	146			<1.0	<1.0	<1.0	<1.0	<0.50	<0.50	1.53	141	2.0	<0.5	1700	7.2	1260	Hazy, yellow-brown tint
09A	08/22/2005	431	249			<1.0	<1.0	<1.0	<1.0	<0.50	<0.50	1.58	141	2.8	<0.1	460	6.8	156	Clear, yellow-brown tint
09A	11/14/2005	515	333			<1.0	<1.0	<1.0	<1.0	<0.50	<0.50	1.07	238	2.0	<0.1	2600	6.9	62.8	---
09A	02/21/2006	614	432			<1.0	<1.0	<1.0	<1.0	<11.4	<12.3	0.94	332	2.6	0.2	5650	6.3	58.8	---
09A	05/15/2006	697	515			<1.0	<1.0	<1.0	<1.0	<11	<12	1.35	193	2.2	63.4	15000	6.4	44.4	---
09A	08/16/2006	790	608			<1.0	<1.0	<1.0	<b>1.2</b>	<1.1	<b>2.1</b>	1.55	175	2.0	56.8	16800	6.4	50.0	---
09A	11/27/2006	893	711			<0.2	<0.2	<b>0.3</b>	<b>1.1</b>	<b>1.9</b>	<b>6.3</b>	2.09	211	3.2	52.5	15200	6.6	51.0	---
09A	02/22/2007	980	798			<1.0	<1.0	<1.0	<1.0	<1.1	<b>7.8</b>	0.65	-107	4.6	0.3	15300	6.4	48.8	---
09A	05/22/2007	1069	887			<1.0	<1.0	<1.0	<b>2.8</b>	<1.1	<b>4.8</b>	0.75	91	2.6	0.1	16700	6.6	43.1	---
09A	11/29/2007	1260	1078			<1.0	<1.0	<1.0	<1.0	<1.1	<b>24.5</b>	1.01	147	3.8	45.4	27600	6.4	40.6	---
09A	05/19/2008	1432	1250		-98	<0.2	<b>0.2</b>	<b>110</b>	<b>85</b>	<b>7.8</b>	<b>35.6</b>	2.26	-82	3.0	29.4	17100	6.7	31.0	---
09A	11/24/2008	1621	1439		91	<b>1.9</b>	<b>4.6</b>	<b>160</b>	<b>42</b>	<b>4.0</b>	<b>2.1</b>	2.61	-52	3.0	<2.0	13700	6.2	5600	---
09A	05/18/2009	1796	1614		266	<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	0.44	-88	2.5	<2.0	18100	7.1	1620	---
09A	11/16/2009	1978	1796		448	<5.0	<1.0	<5.0	<5.0	<1.1	<1.2	1.23	-61	2.6	<1.0	16600	6.6	403	---

**SWMU-20 CLEANUP ACTION SUMMARY - SOURCE ZONE  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING**

Well	Date	Elapsed Time from Injections (a) (days)				Volatile Organic Compounds						Aquifer Redox Conditions					Donor Parameters		Notes
		1st Injection	2nd Injection	3rd (b) Injection	4th Injection	Proposed Groundwater Cleanup Levels (d)						DO (mg/L)	ORP (mV)	Iron II (mg/L)	Sulfate (mg/L)	Methane (µg/L)	pH	TOC (mg/L)	
						5.3 (µg/L)	1.4 (µg/L)	134 (µg/L)	2.4 (µg/L)	---	---								
09A	5/20/2010	2163	1981		633	<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	11.09	515	2.2	<1.0	18700	7.0	72.8	Duffy: Interference w/DO sensor?
09A	11/10/2010	2337	2155		807	<1.0	<1.0	<1.0	<1.0	<1.1	<b>2.0</b>	3.92	118	2.2	0.3	24400	7.0	70.0	---
09A	5/3/2011	2511	2329		981	<2.0	<2.0	<2.0	<2.0	<1.1	<b>2.0</b>	2.55	33	2.0	<0.2	17800	6.9	44.4	---
09A	11/13/2011	2705	2523		1175	<0.2	<0.2	<b>0.2</b>	<0.2	<1.1	<b>1.2</b>	2.23	-66	1.2	0.4	11800	7.0	39.4	---
09A	5/14/2012	2888	2706		1358	<0.2	<0.2	<b>0.2</b>	<0.2	<1.0	<b>13</b>	0.57	91	1.5	0.40	22000	6.4	30.5	---
09A	11/14/2012	3072	2890		1542	<2.0	<2.0	<2.0	<2.0	<1.0	<b>11</b>	0.02	-4	2.0	0.53	21000	6.6	30.9	---
09A	5/21/2013	3260	3078		1730	<2.0	<2.0	<2.0	<2.0	<1.0	<b>16</b>	0.32	-399	1.8	<0.30	24000	7.8	33.0	---
09A	11/12/2013	3435	3253		1905	<2.0	<2.0	<2.0	<2.0	<1.0	<b>10</b>	3.87	-258	1.7	0.41	18000	6.5	30.2	---
09A	5/7/2014	3611	3429		2081	<2.0	<2.0	<2.0	<2.0	<1.0	<b>29</b>	4.46	-322	1.4	0.50	26000	6.7	21.5	---
09B	05/03/2004	-45				<3.0	<b>4.2</b>	<b>250</b>	<3.0	<0.50	<0.50	0.37	269	4.0	61.4	2.7	6.8	20.7	Clear, yellow tint
09B	08/23/2004	67				<5.0	<b>16</b>	<b>530</b>	<b>100</b>	<b>0.76</b>	<0.50	0.34	174	1.4	73.0	23	7.4	29.7	Clear, yellow-brown tint, H2S odor
09B	10/19/2004	124	-58			<5.0	<b>17</b>	<b>300</b>	<b>340</b>	<b>1.4</b>	<0.50	0.30	219	1.0	59.6	29	7.5	24.3	Clear with yellow color
09B	02/21/2005	249	67			<10	<10	<b>890</b>	<b>520</b>	<b>1.7</b>	<0.50	0.56	160	2.8	1.0	2000	6.8	608	Hazy, tan brown color
09B	05/11/2005	328	146			<1.0	<1.0	<b>12</b>	<b>24</b>	<0.50	<0.50	1.48	158	3.5	0.4	9600	7.0	219	Hazy, yellow-brown tint
09B	08/22/2005	431	249			<1.0	<1.0	<1.0	<b>1.7</b>	<0.50	<0.50	1.45	224	2.5	<0.1	400	6.7	17.6	Clear, with yellow-brown tint
09B	11/14/2005	515	333			<1.0	<1.0	<1.0	<1.0	<0.50	<0.50	1.24	235	1.4	<0.1	3100	6.8	51.2	---
09B	02/21/2006	614	432			<1.0	<1.0	<1.0	<b>1.3</b>	<11.4	<12.3	0.90	329	2.8	<0.1	8730	6.3	46.4	---
09B	05/15/2006	697	515			<1.0	<1.0	<1.0	<1.0	<11	<12	1.11	191	1.8	33.9	17000	6.3	45.6	---
09B	08/16/2006	790	608			<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	0.94	188	1.6	55.4	19300	6.3	250	---
09B	11/27/2006	893	711			<0.2	<0.2	<b>0.3</b>	<b>0.5</b>	<1.1	<1.2	1.76	190	2.8	50.2	21800	6.5	78.2	---
09B	02/22/2007	980	798			<1.0	<1.0	<1.0	<1.0	<1.1	<b>1.6</b>	0.67	-80	3.5	0.2	16100	6.3	64.0	---
09B	05/22/2007	1069	887			<1.0	<1.0	<1.0	<1.0	<1.1	<b>1.4</b>	0.76	154	3.0	<0.1	18700	6.5	35.3	---
09B	11/29/2007	1260	1078			<1.0	<1.0	<1.0	<1.0	<1.1	<b>3.8</b>	1.29	238	2.2	58.3	29800	6.2	44.5	---
09B	05/19/2008	1432	1250		-98	<0.2	<0.2	<b>0.2</b>	<b>0.4</b>	<1.1	<b>3.0</b>	2.34	-78	3.4	39.1	12900	6.4	37.3	---
09B	11/24/2008	1621	1439		91	<1.0	<1.0	<1.0	<1.0	<1.1	<b>17.6</b>	2.22	-47	3.0	<1.0	27000	6.7	27.0	---
09B	05/18/2009	1796	1614		266	<1.0	<1.0	<1.0	<1.0	<1.1	<b>6.9</b>	0.38	-38	3.5	<0.5	19700	6.9	37.1	---
09B	11/16/2009	1978	1796		448	<1.0	<1.0	<1.0	<1.0	<1.1	<b>16.1</b>	1.27	12	3.5	<0.1	24500	6.2	28.1	---
09C	05/03/2004	-45				<1.0	<1.0	<b>4.0</b>	<b>3.3</b>	<b>1.9</b>	<b>0.7</b>	0.33	229	4.0	19.1	350	6.8	28.5	Clear, yellow tint
09C	08/23/2004	67				<1.0	<1.0	<b>1.7</b>	<1.0	<b>1.1</b>	<b>2.8</b>	0.47	114	2.6	23.2	610	6.7	302	Clear, H2S odor
09C	10/19/2004	124	-58			<1.0	<1.0	<1.0	<b>1.5</b>	<b>1.1</b>	<0.50	0.60	185	3.0	12.2	620	7.0	99.6	Near clear, yellow tint
09C	02/21/2005	249	67			<1.0	<1.0	<b>1.7</b>	<1.0	<0.50	<b>1.6</b>	0.60	154	2.0	<0.1	3500	6.6	300	Clear with yellow tint
09C	05/11/2005	328	146			<1.0	<1.0	<b>1.2</b>	<1.0	<0.50	<0.50	1.34	138	2.5	<0.1	2700	6.4	44.6	Yellow-brown tint
09C	08/22/2005	431	249			<1.0	<1.0	<b>7.6</b>	<b>2.2</b>	<0.50	<0.50	1.31	230	2.5	<0.1	360	6.7	52.0	---
09C	11/14/2005	515	333			<1.0	<1.0	<b>1.2</b>	<1.0	<0.50	<0.50	1.41	228	2.4	<0.1	7300	6.9	50.6	---
09C	02/21/2006	614	432			<1.0	<1.0	<1.0	<1.0	<11.4	<12.3	0.78	326	2.4	<0.1	10300	6.5	44.2	---
09C	05/15/2006	697	515			<1.0	<1.0	<1.0	<1.0	<11	<12	1.01	192	2.0	27.9	21000	7.0	42.1	---
09C	08/16/2006	790	608			<1.0	<1.0	<1.0	<1.0	<1.1	<b>1.6</b>	0.80	199	1.2	28.8	22900	6.5	33.0	---
09C	11/27/2006	893	711			<0.2	<0.2	<0.2	<0.2	<1.1	<b>9.1</b>	1.40	289	2.4	26.7	23500	6.5	44.0	---
09C	02/22/2007	980	798			<1.0	<1.0	<1.0	<1.0	<1.1	<b>3.9</b>	0.75	-32	3.6	0.2	17700	6.5	33.8	---
09C	05/22/2007	1069	887			<1.0	<1.0	<1.0	<1.0	<1.1	<b>5.4</b>	0.52	123	3.5	<0.1	20600	6.6	25.4	---
09C	11/29/2007	1260	1078			<1.0	<1.0	<1.0	<1.0	<1.1	<b>5.4</b>	0.81	147	3.6	27.3	30000	6.5	27.1	---
09C	05/19/2008	1432	1250		-98	<0.2	<0.2	<0.2	<b>0.2</b>	<1.1	<b>15.2</b>	2.11	-57	4.6	18.6	22800	6.5	22.3	---
09C	11/24/2008	1621	1439		91	<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	2.92	-44	1.8	<2.0	17700	6.6	33.4	---
09C	05/18/2009	1796	1614		266	<1.0	<1.0	<1.0	<1.0	<1.1	<b>4.3</b>	0.45	-44	3.5	<0.5	21400	7.0	24.0	---
09C	11/16/2009	1978	1796		448	<3.0	<3.0	<3.0	<3.0	<1.1	<b>1.9</b>	1.27	-7	3.0	<0.1	22400	6.4	20.7	---

**SWMU-20 CLEANUP ACTION SUMMARY - SOURCE ZONE  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING**

Well	Date	Elapsed Time from Injections (a) (days)				Volatile Organic Compounds						Aquifer Redox Conditions					Donor Parameters		Notes
		1st Injection	2nd Injection	3rd (b) Injection	4th Injection	Proposed Groundwater Cleanup Levels (d)						DO (mg/L)	ORP (mV)	Iron II (mg/L)	Sulfate (mg/L)	Methane (µg/L)	pH	TOC (mg/L)	
						5.3 (µg/L)	1.4 (µg/L)	134 (µg/L)	2.4 (µg/L)	---	---								
10A	05/03/2004	-45				29	27	80	6.4	<0.50	<0.50	0.60	108	2.0	37.8	2.8	6.8	20.0	Clear, yellow tint
10A	08/23/2004	67				14	12	170	4.0	<0.50	<0.50	0.49	181	3.5	38.9	1.1	7.0	59.6	Clear, black tint
10A	10/19/2004	124	-58			15	15	100	23	<0.50	<0.50	0.66	224	4.0	37.8	2.7	7.0	24.0	Clear
10A	02/21/2005	249	67			4.7	4.8	24	6.8	<0.50	0.54	0.53	166	3.6	24.3	430	7.0	22.4	Clear, yellow color
10A	05/11/2005	328	146			4.2	5.4	26	7.2	<0.50	<0.50	0.95	47	3.0	27.9	540	7.2	25.9	Clear, yellow-brown tint
10A	08/22/2005	431	249			2.7	6.3	48	76	<0.50	<0.50	0.73	177	2.0	48.8	240	7.0	31.4	Clear, with yellow-brown tint
10A	11/14/2005	515	333			3.3	6.7	47	73	<0.50	<0.50	0.91	178	2.0	50.6	370	7.1	34.1	---
10A	02/21/2006	614	432			3.7	9.6	42	150	<11.4	<12.3	0.54	320	2.0	53.9	1130	6.8	45.8	---
10A	05/15/2006	697	515			1.8	3.7	63	19	<11	<12	0.67	190	1.8	57.4	3100	6.8	49.2	---
10A	08/16/2006	790	608			1.6	1.6	38	20	<1.1	<1.2	1.50	201	1.4	57.5	1620	6.7	50.8	---
10A	11/27/2006	893	711			<0.2	<0.2	7.4	9.2	2.6	2.6	2.67	201	3.0	57.9	1650	6.9	56.0	---
10A	02/22/2007	980	798			1.2	<1.0	32	35	<1.1	<1.2	0.57	-176	4.6	20.4	1370	6.8	56.4	---
10A	05/22/2007	1069	887			1.1	<1.0	28	44	<1.1	1.4	0.88	73	3.0	10.2	2590	6.9	47.3	---
10A	11/29/2007	1260	1078			1.2	<1.0	22	78	4.4	3.7	0.80	106	4.2	47.9	4810	6.9	47.8	---
10A	05/19/2008	1432	1250	-98		<1.0	<1.0	22	180	7.9	4.4	2.19	-177	4.0	32.5	4870	7.0	33.3	---
10A	11/24/2008	1621	1439	91		<1.0	<1.0	1.6	5.0	<1.1	<1.2	2.29	-87	3.4	1.3	16900	7.1	1200	---
10A	05/18/2009	1796	1614	266		<2.0	<2.0	<2.0	<2.0	<1.1	<1.2	0.66	-80	3.3	<1.0	17900	6.9	168	---
10A	11/16/2009	1978	1796	448		<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	3.14	-40	4.2	<1.0	18200	6.3	69.2	---
10A	5/20/2010	2163	1981	633		<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	16.23	341	3.0	<1.0	17600	6.8	60.4	Duffy: Replace DO electrolic membrane
10A	11/10/2010	2337	2155	807		<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	4.09	67	2.4	0.5	22800	6.9	56.8	---
10A	5/3/2011	2511	2329	981		<2.0	<2.0	<2.0	<2.0	<1.1	<1.2	2.47	-21	2.5	<0.2	20700	6.9	41.6	---
10A	11/13/2011	2705	2523	1175		<0.2	<0.2	0.2	0.4	<1.1	<1.2	2.45	-38	2.0	0.3	15400	7.1	33.8	---
10A	5/14/2012	2888	2706	1358		<0.2	<0.2	0.2	0.4	<1.0	<1.0	0.57	88	2.5	0.32	20000	6.4	38.0	---
10A	11/14/2012	3072	2890	1542		<0.2	<0.2	0.3	0.4	<1.0	<1.0	0.03	-16	2.0	<0.30	19000	6.6	30.6	---
10A	5/21/2013	3260	3078	1730		<0.2	<0.2	0.2	0.3	<1.0	<3.0	0.35	-340	1.8	<0.30	26000	7.5	29.5	---
10A	11/12/2013	3435	3253	1905		<0.2	<0.2	0.2	0.4	<1.0	2.5	3.53	-242	1.4	0.38	16000	6.5	29.1	---
10A	5/7/2014	3611	3429	2081		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	4.06	-305	2.1	<0.30	26000	6.7	27.9	---
14A	05/04/2004	-44				<1.0	<1.0	140	110	<0.50	<0.50	0.53	-8	7.5	38.9	590	6.8	20.7	Clear, yellow tint
14A	08/23/2004	67				<1.0	2.9	560	180	0.89	0.67	0.54	162	3.2	30.1	810	6.8	22.6	---
14A	10/19/2004	124	-58			<5.0	39	1200	650	<0.50	<0.50	0.64	69	3.0	43.3	350	6.9	20.6	---
14A	02/21/2005	249	67	-24		<5.0	<5.0	300	1000	13	2.7	0.41	101	1.8	3.8	1700	6.9	44.0	Clear, yellow tint
14A	05/16/2005	333	151	60		<10	<10	<10	<10	<0.50	<0.50	5.90	45	4.0	<2.0	590	6.4	8620	---
14A	08/22/2005	431	249	158		<10	<10	<10	<10	<0.50	<0.50	1.62	234	3.0	<2.0	220	6.8	5380	Clear, yellow-brown
14A	11/15/2005	516	334	243		<3.0	<3.0	6.0	<3.0	<0.50	<0.50	1.26	257	2.0	<0.1	2500	6.4	602	---
14A	02/21/2006	614	432	341		<1.0	<1.0	<1.0	<1.0	<11.4	<12.3	1.36	335	2.0	<0.1	5400	7.4	180	---
14A	05/17/2006	699	517	426		<2.0	<2.0	2.1	<2.0	<11	<12	1.78	76	2.8	12.0	9400	6.4	67.1	---
14A	08/16/2006	790	608	517		<1.0	<1.0	3.0	<1.0	<1.1	<1.2	1.16	240	1.2	16.5	6320	6.5	66.0	---
14A	11/29/2006	895	713	622		<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	1.57	248	2.8	11.8	11100	6.3	72.0	---
14A	02/22/2007	980	798	707		<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	0.89	-56	7.0	0.2	7670	6.2	34.9	---
14A	05/23/2007	1070	888	797		<1.0	<1.0	1.5	<1.0	<1.1	<1.2	1.11	165	3.0	8.6	10100	6.3	27.5	---
14A	12/03/2007	1264	1082	991		<1.0	<1.0	1.6	<1.0	<1.1	<1.2	2.29	-86	3.2	15.9	14500	6.4	55.6	---
14A	05/20/2008	1433	1251	1160	-97	<1.0	<1.0	1.2	<1.0	<1.1	<1.2	3.45	-88	3.6	<0.1	12100	6.3	26.3	---
14A	11/24/2008	1621	1439	1348	91	<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	2.79	-70	3.0	194	14500	6.1	8.68	---
14A	05/20/2009	1798	1616	1525	268	<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	0.41	-95	3.5	20.0	14400	6.3	9.83	---
14A	11/17/2009	1979	1797	1706	449	<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	0.81	-18	3.2	165	15800	5.7	6.22	---

**SWMU-20 CLEANUP ACTION SUMMARY - SOURCE ZONE  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING**

Well	Date	Elapsed Time from Injections (a) (days)				Volatile Organic Compounds						Aquifer Redox Conditions					Donor Parameters		Notes
		1st Injection	2nd Injection	3rd (b) Injection	4th Injection	Proposed Groundwater Cleanup Levels (d)						DO (mg/L)	ORP (mV)	Iron II (mg/L)	Sulfate (mg/L)	Methane (µg/L)	pH	TOC (mg/L)	
						5.3 (µg/L)	1.4 (µg/L)	134 (µg/L)	2.4 (µg/L)	---	---								
14A	5/24/2010	2167	1985	1894	637	<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	4.29	311	2.8	5.1	14600	6.4	8.07	---
14A	11/10/2010	2337	2155	2064	807	<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	2.47	171	2.6	38.6	14300	6.8	6.88	---
14A	5/5/2011	2513	2331	2240	983	<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	2.96	83	1.8	8.4	15100	7.1	3.28	---
14A	11/13/2011	2705	2523	2432	1175	<0.2	<0.2	<b>0.6</b>	<0.2	<1.1	<1.2	2.04	-52	1.5	<0.1	7510	6.9	8.05	---
14A	5/14/2012	2888	2706	2615	1358	<0.2	<0.2	<b>0.3</b>	<b>0.2</b>	<1.0	<b>8.7</b>	0.13	62	2.6	3.4	16000	6.4	5.9	---
14A	11/14/2012	3072	2890	2799	1542	<0.2	<0.2	<b>0.6</b>	<0.2	<1.0	<b>5.0</b>	0.03	31	1.5	79.0	16000	6.4	6.5	---
14A	5/21/2013	3260	3078	2987	1730	<0.5	<0.5	<0.5	<0.5	<1.0	<b>4.8</b>	0.24	-428	2.4	2.3	18000	7.4	6.5	---
14A	11/12/2013	3435	3253	3162	1905	<0.2	<0.2	<b>0.5</b>	<0.2	<1.0	<b>6.3</b>	4.46	-286	1.3	0.52	14000	6.4	8.0	---
14A	5/7/2014	3611	3429	3338	2081	<0.2	<0.2	<b>0.3</b>	<b>0.3</b>	<1.0	<b>4.6</b>	4.39	-427	1.6	19.9	15000	6.8	6.5	---
15A	05/03/2004	-45				<5.0	<5.0	<5.0	<5.0	NA	NA	NA	NA	NA	NA	NA	NA	NA	---
15A	10/26/2004	131	-51			<5.0	<5.0	<5.0	<5.0	NA	NA	NA	NA	NA	NA	NA	NA	NA	---
15A	05/16/2005	333	151			<5.0	<5.0	<5.0	<5.0	NA	NA	NA	NA	NA	NA	NA	NA	NA	---
15A	11/15/2005	516	334			<5.0	<5.0	<5.0	<5.0	NA	NA	NA	NA	NA	NA	NA	NA	NA	---
15A	05/17/2006	699	517			<5.0	<5.0	<5.0	<5.0	NA	NA	0.79	131	NA	NA	NA	6.7	NA	---
15A	11/29/2006	895	713			<3.0	<3.0	<3.0	<3.0	NA	NA	1.26	513	NA	NA	NA	6.6	NA	---
15A	05/23/2007	1070	888			<1.0	<1.0	<b>1.4</b>	<b>2.6</b>	NA	NA	1.19	144	NA	NA	NA	6.7	NA	---
15A	12/03/2007	1264	1082			<1.0	<1.0	<1.0	<b>1.3</b>	NA	NA	1.31	-105	NA	NA	NA	6.6	NA	---
15A	05/20/2008	1433	1251		-97	<3.0	<3.0	<3.0	<3.0	NA	NA	2.57	-135	NA	NA	NA	6.7	NA	---
15A	11/24/2008	1621	1439		91	<1.0	<1.0	<1.0	<2.0	NA	NA	2.07	-61	NA	NA	NA	6.8	NA	---
15A	05/19/2009	1797	1615		267	<3.0	<3.0	<3.0	<3.0	NA	NA	0.35	-33	NA	NA	NA	6.9	NA	---
15A	11/18/2009	1980	1798		450	<1.0	<1.0	<1.0	<b>1.4</b>	NA	NA	0.72	-0.1	NA	NA	NA	6.3	NA	---
15A	5/20/2010	2163	1981		633	<1.0	<1.0	<1.0	<b>1.6</b>	NA	NA	1.10	606	NA	NA	NA	6.8	NA	---
15A	11/10/2010	2337	2155		807	<1.0	<1.0	<1.0	<b>1.4</b>	NA	NA	2.42	118	NA	NA	NA	7.1	NA	---
15A	5/5/2011	2513	2331		983	<1.0	<1.0	<1.0	<1.0	NA	NA	4.83	-19	NA	NA	NA	7.2	NA	---
15A	11/13/2011	2705	2523		1175	<0.2	<0.2	<b>0.3</b>	<b>1.0</b>	NA	NA	4.01	-41	NA	NA	NA	7.3	NA	---
15A	5/14/2012	2888	2706		1358	<1.0	<1.0	<1.0	<b>1.2</b>	NA	NA	0.64	56	NA	NA	NA	6.7	NA	---
15A	11/13/2012	3071	2889		1541	<0.2	<0.2	<b>0.4</b>	<b>0.8</b>	NA	NA	0.03	23	NA	NA	NA	6.8	NA	---
15A	5/21/2013	3260	3078		1730	<0.5	<0.5	<b>0.6</b>	<b>1.1</b>	NA	NA	0.20	-394	NA	NA	NA	7.4	NA	---
15A	11/12/2013	3435	3253		1905	<0.2	<0.2	<b>0.5</b>	<b>0.8</b>	NA	NA	3.38	-267	NA	NA	NA	6.7	NA	---
15A	5/7/2014	3611	3429		2081	<0.2	<0.2	<b>0.6</b>	<b>1.0</b>	NA	NA	3.86	-351	NA	NA	NA	6.9	NA	---
19A	05/02/2004	-46	-228			<1.0	<1.0	<1.0	<1.0	NA	NA	0.33	-3	NA	NA	NA	6.5	NA	---
19A	02/21/2005	249	67			<1.0	<1.0	<1.0	<1.0	<0.50	<0.50	0.65	180	NA	47.4	17	6.7	15.5	---
19A	05/12/2005	329	147			<1.0	<1.0	<1.0	<1.0	<0.50	<0.50	0.63	169	3.0	31.3	9.1	6.8	14.2	Clear, colorless
19A	08/22/2005	431	249			<1.0	<1.0	<1.0	<1.0	<0.50	<0.50	0.74	106	3.0	68.3	16	6.6	10.5	Clear, colorless
19A	11/15/2005	516	334			<1.0	<1.0	<1.0	<1.0	<0.50	<0.50	0.56	201	2.6	95.9	35	6.8	9.30	---
19A	02/22/2006	615	433			<1.0	<1.0	<1.0	<1.0	<11.4	<12.3	0.77	65	3.0	124.0	111	6.6	31.3	---
19A	05/17/2006	699	517			<1.0	<1.0	<1.0	<1.0	<11	<12	1.14	56	2.0	73.4	230	6.4	15.7	---
19A	08/15/2006	789	607			<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	0.60	229	2.0	47.3	202	6.4	11.5	---
19A	11/27/2006	893	711			<0.2	<b>0.2</b>	<b>0.3</b>	<0.2	<1.1	<1.2	0.88	264	2.0	41.9	186	6.4	13.6	---
19A	02/22/2007	980	798			<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	0.42	-23	3.0	20.7	248	6.2	19.8	---
19A	05/22/2007	1069	887			<1.0	<1.0	<1.0	<1.0	<1.1	<b>5.2</b>	0.34	277	3.5	30.8	179	6.4	15.4	---

**SWMU-20 CLEANUP ACTION SUMMARY - SOURCE ZONE  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING**

Well	Date	Elapsed Time from Injections (a) (days)				Volatile Organic Compounds						Aquifer Redox Conditions					Donor Parameters		Notes
		1st Injection	2nd Injection	3rd (b) Injection	4th Injection	Proposed Groundwater Cleanup Levels (d)						DO (mg/L)	ORP (mV)	Iron II (mg/L)	Sulfate (mg/L)	Methane (µg/L)	pH	TOC (mg/L)	
						5.3 (µg/L)	1.4 (µg/L)	134 (µg/L)	2.4 (µg/L)	---	---								
19A	11/29/2007	1260	1078			<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	0.67	243	2.2	37.2	235	6.2	14.3	---
19A	05/20/2008	1433	1251		-97	<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	3.23	-79	3.8	20.9	134	6.4	11.5	---
19A	11/23/2008	1620	1438		90	<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	1.62	-61	2.0	46.1	97.8	6.4	10.6	---
19A	05/19/2009	1797	1615		267	<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	0.30	-28	3.2	28.6	127	6.8	12.8	---
19A	11/18/2009	1980	1798		450	<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	1.58	-2	3.4	22.1	122	6.5	10.7	---
22A	03/21/2005	277	95	4		<1.0	<1.0	3.5	2.0	<0.50	<0.50	1.86	53	2.8	12.8	280	7.0	11.1	Hazy, suspended silt
22A	05/12/2005	329	147	56		<1.0	<1.0	2.3	2.9	<0.50	<0.50	0.83	155	2.6	1.3	300	7.1	31.3	---
22A	08/22/2005	431	249	158		<1.0	<1.0	2.3	3.2	<0.50	<0.50	0.70	170	2.6	3.0	230	6.9	26.5	Clear, slight yellow-brown tint
22A	11/16/2005	517	335	244		<1.0	<1.0	1.4	2.2	<0.50	<0.50	1.67	321	2.4	1.3	1300	6.3	29.9	---
22A	02/22/2006	615	433	342		<1.0	<1.0	1.4	3.3	<11.4	<12.3	0.69	97	2.0	59.0	1940	6.8	32.0	---
22A	05/17/2006	699	517	426		<1.0	<1.0	2.4	1.7	<11	<12	0.67	102	2.6	32.7	3600	6.8	17.6	---
22A	08/15/2006	789	607	516		<1.0	<1.0	1.8	2.4	<1.1	<1.2	0.65	239	2.0	54.7	5700	6.7	24.0	---
22A	11/30/2006	896	714	623		<0.2	0.3	2.2	2.4	<1.1	<1.2	2.15	286	2.6	40.0	4020	6.6	25.2	---
22A	02/22/2007	980	798	707		<1.0	<1.0	2.5	2.3	<1.1	<1.2	0.53	-76	5.0	<0.1	3000	6.6	22.4	---
22A	05/23/2007	1070	888	797		<1.0	<1.0	2.5	2.7	<1.1	<1.2	0.30	51	3.0	27.3	3510	6.8	18.2	---
22A	12/03/2007	1264	1082	991		<1.0	<1.0	2.0	1.3	<1.1	<1.2	0.61	41	2.6	12.3	2030	6.6	16.0	---
22A	05/20/2008	1433	1251	1160	-97	<1.0	<1.0	2.6	1.9	<1.1	<1.2	2.83	-103	4.0	20.2	1540	6.7	13.8	---
22A	11/23/2008	1620	1438	1347	90	<1.0	<1.0	2.2	3.1	<1.1	<1.2	1.13	-70	1.8	2.6	3100	6.8	19.2	---
22A	05/19/2009	1797	1615	1524	267	<1.0	<1.0	2.5	2.5	<1.1	<1.2	0.26	-43	3.2	3.4	3490	7.0	21.0	---
22A	11/18/2009	1980	1798	1707	450	<1.0	<1.0	2.1	1.8	<1.1	<1.2	0.43	-3.3	3.0	2.1	2060	6.4	13.8	---
22A	5/24/2010	2167	1985	1894	637	<1.0	<1.0	1.7	1.7	<1.1	<1.2	6.58	204	2.4	0.6	2370	7.0	15.1	---
22A	11/11/2010	2338	2156	2065	808	<1.0	<1.0	1.2	2.7	<1.1	<1.2	3.27	113	2.2	0.5	4650	7.0	21.8	---
22A	5/4/2011	2512	2330	2239	982	<1.0	<1.0	1.1	2.2	<1.1	<1.2	1.96	4	2.0	0.6	6350	7.0	22.4	---
22A	11/13/2011	2705	2523	2432	1175	<0.2	<0.2	0.9	1.7	<1.1	<1.2	2.89	-38	1.2	0.4	2510	7.3	17.6	---
22A	5/14/2012	2888	2706	2615	1358	<0.2	<0.2	0.6	2.0	<1.0	3.3	0.03	45	2.2	<0.30	5100	6.8	25.4	---
22A	11/14/2012	3072	2890	2799	1542	<0.2	<0.2	0.5	1.8	<1.0	1.7	0.03	1	1.8	<0.30	4400	6.9	22.7	---
22A	5/20/2013	3259	3077	2986	1729	<0.2	<0.2	0.4	2.0	<1.0	1.6	0.24	-404	1.0	<0.30	6100	7.7	24.6	---
22A	11/12/2013	3435	3253	3162	1905	<0.2	<0.2	0.5	1.7	<1.0	1.1	3.69	-289	1.4	1.8	3500	6.7	19.8	---
22A	5/7/2014	3611	3429	3338	2081	<0.2	<0.2	0.5	1.6	<1.0	<1.0	4.8	-368	1.3	0.66	4200	6.8	23.6	---
23A	03/21/2005	277	95	4		<1.0	<1.0	<1.0	<1.0	<0.50	<0.50	0.63	81	2.0	0.4	410	7.0	33.0	Slight yellow tint
23A	05/12/2005	329	147	56		<1.0	<1.0	<1.0	<1.0	<0.50	<0.50	0.58	158	2.0	<0.1	260	7.2	39.9	---
23A	08/22/2005	431	249	158		<1.0	<1.0	<1.0	<1.0	<0.50	<0.50	0.75	130	3.4	1.5	98	7.0	21.0	---
23A	11/16/2005	517	335	244		<1.0	<1.0	<1.0	<1.0	<0.50	<0.50	0.49	291	2.6	4.1	140	7.2	30.8	---
23A	02/22/2006	615	433	342		<1.0	<1.0	<1.0	<1.0	<11.4	<12.3	0.60	127	2.2	91.8	1520	6.4	34.5	---
23A	05/17/2006	699	517	426		<1.0	<1.0	<1.0	<1.0	<11	<12	0.60	120	3.0	38.8	1700	6.7	30.0	---
23A	08/15/2006	789	607	516		<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	0.77	256	2.2	63.9	3080	6.7	32.6	---
23A	11/30/2006	896	714	623		<0.2	<0.2	<0.2	<0.2	<1.1	<1.2	1.96	287	2.5	40.7	1930	6.2	45.2	---
23A	02/22/2007	980	798	707		<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	0.40	-58	2.0	2.9	1360	6.5	34.6	---
23A	05/23/2007	1070	888	797		<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	0.41	193	3.3	52.7	1850	6.4	38.7	---
23A	11/30/2007	1261	1079	988		<0.2	<0.2	0.3	<0.2	<1.1	<1.2	0.55	159	2.2	81.1	4430	6.6	38.6	---
23A	05/21/2008	1434	1252	1161	-96	<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	3.12	-28	2.2	31.7	1570	6.1	29.6	---
23A	11/25/2008	1622	1440	1349	92	<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	4.22	-68	1.8	<0.1	3270	6.8	39.0	---
23A	05/19/2009	1797	1615	1524	267	<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	0.31	-3	3.2	0.1	2370	6.5	39.1	---
23A	11/18/2009	1980	1798	1707	450	<1.0	<1.0	<1.0	<1.0	<1.1	<1.2	0.41	1	2.4	1.6	1970	6.5	30.9	---

**SWMU-20 CLEANUP ACTION SUMMARY - SOURCE ZONE  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING**

Well	Date	Elapsed Time from Injections (a) (days)				Volatile Organic Compounds						Aquifer Redox Conditions					Donor Parameters		Notes	
		1st Injection	2nd Injection	3rd (b) Injection	4th Injection	Proposed Groundwater Cleanup Levels (d)						DO (mg/L)	ORP (mV)	Iron II (mg/L)	Sulfate (mg/L)	Methane (µg/L)	pH	TOC (mg/L)		
						PCE (µg/L)	TCE (µg/L)	cDCE (µg/L)	VC (µg/L)	Ethene (µg/L)	Ethane (µg/L)									
						5.3	1.4	134	2.4	---	---									

PCE = Tetrachloroethene  
TCE = Trichloroethene  
cDCE = cis-1,2-Dichloroethene  
VC = Vinyl Chloride  
DO = Dissolved Oxygen  
ORP = Oxidation Reduction Potential  
TOC = Total Organic Carbon

**Bold = Detect**  
µg/L = micrograms pr liter  
mg/L = milligrams per liter  
mV = millivolts  
NA = Not analyzed  
TMCL = Target Media Cleanup Level.  
Box = Exceedance of TMCL.

(a) Injections occurred on:  
6/17/04 (6A, B, C; 9A, B, C)  
12/16-17/04 (6A, 6B;9A,9B)  
3/17/05 (14A)  
8/25-28/08 (6A, 9A, 10A)  
(b) Conducted at Well MW-14A only.  
(c) MW-06A installed June 2004.

6/17/2004 for elapsed time relative to injection  
12/16/2004 for elapsed time relative to injection  
3/17/2005 for elapsed time relative to injection  
8/25/2008 for elapsed time relative to injection

(d) Proposed Cleanup Standards and Comparison to Site Data, Boeing Developmental Center, Tukwila, Washington (Landau Associates, 5/7/13).

**SWMU-20 CLEANUP ACTION SUMMARY - NON SOURCE ZONE  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING**

Well	Date	Elapsed Time from Injections (a) (days)				Volatile Organic Compounds			
						Proposed Groundwater Cleanup Levels (c)			
		1st Injection	2nd Injection	3rd (b) Injection	4th Injection	5.3 PCE (µg/L)	1.4 TCE (µg/L)	134 cDCE (µg/L)	2.4 VC (µg/L)
MW-8C	5/3/2004	-45				<1.0	<1.0	<1.0	<b>2.8</b>
MW-8C	10/25/2004	130	-52			<1.0	<1.0	<1.0	<b>3.5</b>
MW-8C	5/12/2005	329	147			<1.0	<1.0	<1.0	<1.0
MW-8C	11/14/2005	515	333			<1.0	<1.0	<1.0	<1.0
MW-8C	5/15/2006	697	515			<1.0	<1.0	<1.0	<1.0
MW-8C	11/27/2006	893	711			<5.0	<5.0	<5.0	<5.0
MW-8C	5/21/2007	1068	886			<3.0	<3.0	<3.0	<3.0
MW-8C	11/29/2007	1260	1078			<5.0	<5.0	<5.0	<5.0
MW-8C	5/19/2008	1432	1250	-98		<5.0	<5.0	<5.0	<5.0
MW-8C	11/23/2008	1620	1438	90		<5.0	<5.0	<5.0	<5.0
MW-8C	05/18/2009	1796	1614	266		<1.0	<1.0	<1.0	<1.0
MW-8C	11/16/2009	1978	1796	448		<3.0	<3.0	<3.0	<3.0
MW-9D	5/3/2004	-45				<1.0	<1.0	<1.0	<1.0
MW-9D	10/19/2004	124	-58			<1.0	<1.0	<1.0	<1.0
MW-9D	5/11/2005	328	146			<1.0	<1.0	<1.0	<1.0
MW-9D	11/14/2005	515	333			<1.0	<1.0	<1.0	<1.0
MW-9D	5/15/2006	697	515			<1.0	<1.0	<1.0	<1.0
MW-9D	11/27/2006	893	711			<1.0	<1.0	<1.0	<1.0
MW-9D	5/22/2007	1069	887			<1.0	<1.0	<1.0	<1.0
MW-9D	11/29/2007	1260	1078			<1.0	<1.0	<1.0	<1.0
MW-9D	5/19/2008	1432	1250	-98		<0.2	<0.2	<0.2	<0.2
MW-9D	11/24/2008	1621	1439	91		<1.0	<1.0	<1.0	<1.0
MW-9D	05/18/2009	1796	1614	266		<1.0	<1.0	<1.0	<1.0
MW-9D	11/16/2009	1978	1796	448		<1.0	<1.0	<1.0	<1.0
MW-10C	5/3/2004	-45				<1.0	<1.0	<b>4.3</b>	<b>4.0</b>
MW-10C	10/19/2004	124	-58			<1.0	<1.0	<b>6.4</b>	<b>11</b>
MW-10C	5/11/2005	328	146			<1.0	<1.0	<b>4.0</b>	<b>1.9</b>
MW-10C	11/14/2005	515	333			<1.0	<1.0	<1.0	<b>1.0</b>
MW-10C	5/15/2006	697	515			<1.0	<1.0	<b>1.5</b>	<b>2.2</b>
MW-10C	11/27/2006	893	711			<0.2	<0.2	<b>1.9</b>	<b>2.6</b>
MW-10C	5/22/2007	1069	887			<1.0	<1.0	<b>6.7</b>	<b>5.8</b>
MW-10C	11/29/2007	1260	1078			<1.0	<1.0	<b>7.2</b>	<b>5.6</b>
MW-10C	5/19/2008	1432	1250	-98		<0.2	<0.2	<b>15</b>	<b>6.9</b>
MW-10C	11/24/2008	1621	1439	91		<1.0	<1.0	<b>8.5</b>	<b>7.5</b>
MW-10C	05/18/2009	1796	1614	266		<1.0	<1.0	<1.0	<1.0
MW-10C	11/16/2009	1978	1796	448		<1.0	<1.0	<1.0	<1.0
MW-10C	5/20/2010	2163	1981	633		<1.0	<1.0	<1.0	<1.0
MW-10C	11/10/2010	2337	2155	807		<1.0	<1.0	<b>3.5</b>	<b>4.4</b>
MW-10C	5/3/2011	2511	2329	981		<1.0	<1.0	<b>5.8</b>	<b>4.7</b>
MW-10C	11/13/2011	2705	2523	1175		<0.2	<0.2	<b>3.7</b>	<b>4.3</b>
MW-10C	5/14/2012	2888	2706	1358		<0.2	<0.2	<b>5.4</b>	<b>4.0</b>
MW-10C	11/14/2012	3072	2890	1542		<0.2	<0.2	<b>6.1</b>	<b>4.4</b>
MW-10C	5/21/2013	3260	3078	1730		<0.2	<0.2	<b>6.0</b>	<b>4.5</b>
MW-10C	11/12/2013	3435	3253	1905		<0.2	<0.2	<b>3.5</b>	<b>3.7</b>
MW-10C	5/7/2014	3611	3429	2081		<0.2	<0.2	<b>5.4</b>	<b>2.9</b>
MW-11A	5/2/2004	-46				<1.0	<b>2.1</b>	<b>21</b>	<1.0
MW-11A	10/25/2004	130	-52			<1.0	<b>2.0</b>	<b>20</b>	<1.0
MW-11A	5/12/2005	329	147			<1.0	<b>2.0</b>	<b>20</b>	<1.0
MW-11A	11/15/2005	516	334			<1.0	<b>2.0</b>	<b>22</b>	<1.0
MW-11A	5/16/2006	698	516			<1.0	<b>1.1</b>	<b>20</b>	<1.0
MW-11A	11/26/2006	892	710			<1.0	<b>1.5</b>	<b>24</b>	<1.0
MW-11A	5/22/2007	1069	887			<1.0	<b>1.5</b>	<b>26</b>	<1.0
MW-11A	11/27/2007	1258	1076			<1.0	<b>1.1</b>	<b>27</b>	<1.0



**SWMU-20 CLEANUP ACTION SUMMARY - NON SOURCE ZONE  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING**

Well	Date	Elapsed Time from Injections (a) (days)				Volatile Organic Compounds			
						Proposed Groundwater Cleanup Levels (c)			
		1st Injection	2nd Injection	3rd (b) Injection	4th Injection	5.3 PCE (µg/L)	1.4 TCE (µg/L)	134 cDCE (µg/L)	2.4 VC (µg/L)
MW-11A	5/19/2008	1432	1250		-98	<0.2	<b>1.2</b>	<b>26</b>	<b>0.2</b>
MW-11A	11/23/2008	1620	1438		90	<1.0	<b>1.2</b>	<b>33</b>	<1.0
MW-11A	05/18/2009	1796	1614		266	<1.0	<1.0	<b>26</b>	<1.0
MW-11A	11/17/2009	1979	1797		449	<1.0	<b>1.0</b>	<b>30</b>	<1.0
MW-11A	5/19/2010	2162	1980		632	<1.0	<b>1.1</b>	<b>26</b>	<1.0
MW-11A	11/8/2010	2335	2153		805	<1.0	<1.0	<b>22</b>	<1.0
MW-11A	5/3/2011	2511	2329		981	<1.0	<1.0	<b>22</b>	<1.0
MW-11A	11/13/2011	2705	2523		1175	<0.2	<b>0.5</b>	<b>23</b>	<b>0.4</b>
MW-11A	5/14/2012	2888	2706		1358	<0.2	<b>0.7</b>	<b>24</b>	<b>0.4</b>
MW-11A	11/14/2012	3072	2890		1542	<2.0	<2.0	<b>25</b>	<2.0
MW-11A	5/21/2013	3260	3078		1730	<2.0	<2.0	<b>22</b>	<2.0
MW-11A	11/12/2013	3435	3253		1905	<2.0	<2.0	<b>24</b>	<2.0
MW-11A	5/7/2014	3611	3429		2081	<2.0	<2.0	<b>19</b>	<2.0
MW-12A	5/2/2004	-46				<1.0	<1.0	<b>1.8</b>	<1.0
MW-12A	10/25/2004	130	-52			<1.0	<1.0	<b>4.4</b>	<1.0
MW-12A	5/12/2005	329	147			<1.0	<1.0	<b>2.0</b>	<1.0
MW-12A	11/15/2005	516	334			<1.0	<1.0	<b>3.8</b>	<1.0
MW-12A	5/16/2006	698	516			<1.0	<1.0	<b>1.5</b>	<1.0
MW-12A	11/26/2006	892	710			<0.2	<b>0.7</b>	<b>4.4</b>	<0.2
MW-12A	5/22/2007	1069	887			<1.0	<1.0	<b>2.4</b>	<1.0
MW-12A	11/27/2007	1258	1076			<1.0	<1.0	<b>3.2</b>	<1.0
MW-12A	5/19/2008	1432	1250		-98	<0.2	<b>0.6</b>	<b>3.2</b>	<0.2
MW-12A	11/23/2008	1620	1438		90	<1.0	<1.0	<b>4.7</b>	<1.0
MW-12A	05/18/2009	1796	1614		266	<1.0	<1.0	<b>1.4</b>	<1.0
MW-12A	11/17/2009	1979	1797		449	<1.0	<1.0	<b>4.7</b>	<1.0
MW-12A	5/19/2010	2162	1980		632	<1.0	<1.0	<1.0	<1.0
MW-12A	11/8/2010	2335	2153		805	<1.0	<1.0	<b>4.3</b>	<1.0
MW-12A	5/3/2011	2511	2329		981	<1.0	<1.0	<1.0	<1.0
MW-12A	11/13/2011	2705	2523		1175	<0.2	<b>0.6</b>	<b>3.1</b>	<0.2
MW-12A	5/14/2012	2888	2706		1358	<b>0.2</b>	<0.2	<0.2	<0.2
MW-12A	11/14/2012	3072	2890		1542	<0.2	<b>0.4</b>	<b>2.1</b>	<0.2
MW-12A	5/21/2013	3260	3078		1730	<0.2	<0.2	<b>0.5</b>	<0.2
MW-12A	11/12/2013	3435	3253		1905	<0.2	<b>0.5</b>	<b>2.2</b>	<0.2
MW-12A	5/7/2014	3611	3429		2081	<b>0.3</b>	<0.2	<0.2	<0.2
MW-13A	5/2/2004	-46				<b>5.1</b>	<b>4.6</b>	<1.0	<1.0
MW-13A	10/25/2004	130	-52			<b>4.3</b>	<b>4.0</b>	<1.0	<1.0
MW-13A	5/12/2005	329	147			<b>6.1</b>	<b>4.6</b>	<1.0	<1.0
MW-13A	11/14/2005	515	333			<b>6.0</b>	<b>4.5</b>	<1.0	<1.0
MW-13A	5/16/2006	698	516			<b>7.1</b>	<b>4.6</b>	<1.0	<1.0
MW-13A	11/27/2006	893	711			<b>8.3</b>	<b>6.5</b>	<b>0.3</b>	<0.2
MW-13A	5/21/2007	1068	886			<b>8.2</b>	<b>7.0</b>	<b>0.4</b>	<0.2
MW-13A	11/28/2007	1259	1077			<b>6.4</b>	<b>4.2</b>	<1.0	<1.0
MW-13A	5/19/2008	1432	1250		-98	<b>8.7</b>	<b>6.8</b>	<b>0.3</b>	<0.2
MW-13A	11/23/2008	1620	1438		90	<b>6.5</b>	<b>3.7</b>	<1.0	<1.0
MW-13A	05/18/2009	1796	1614		266	<b>7.7</b>	<b>5.6</b>	<1.0	<1.0
MW-13A	11/17/2009	1979	1797		449	<b>9.2</b>	<b>6.0</b>	<1.0	<1.0
MW-13A	5/20/2010	2163	1981		633	<b>9.4</b>	<b>5.3</b>	<1.0	<1.0
MW-13A	11/10/2010	2337	2155		807	<b>3.6</b>	<b>2.8</b>	<1.0	<1.0
MW-13A	5/4/2011	2512	2330		982	<b>3.9</b>	<b>2.4</b>	<1.0	<1.0
MW-13A	11/3/2011	2695	2513		1165	<b>1.6</b>	<1.0	<1.0	<1.0
MW-13A	5/14/2012	2888	2706		1358	<b>2.3</b>	<b>0.8</b>	<0.2	<0.2
MW-13A	11/13/2012	3071	2889		1541	<b>2.2</b>	<b>0.8</b>	<0.2	<0.2
MW-13A	5/21/2013	3260	3078		1730	<b>4.5</b>	<b>2.5</b>	<b>0.5</b>	<0.2
MW-13A	11/12/2013	3435	3253		1905	<b>2.2</b>	<b>0.6</b>	<0.2	<0.2
MW-13A	5/7/2014	3611	3429		2081	<b>3.1</b>	<b>1.3</b>	<0.2	<0.2

**SWMU-20 CLEANUP ACTION SUMMARY - NON SOURCE ZONE  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING**

Well	Date	Elapsed Time from Injections (a) (days)				Volatile Organic Compounds			
						Proposed Groundwater Cleanup Levels (c)			
		1st Injection	2nd Injection	3rd (b) Injection	4th Injection	5.3 PCE (µg/L)	1.4 TCE (µg/L)	134 cDCE (µg/L)	2.4 VC (µg/L)
MW-13C	5/2/2004	-46				<1.0	<1.0	<1.0	<b>2.5</b>
MW-13C	10/25/2004	130	-52			<1.0	<1.0	<1.0	<b>3.3</b>
MW-13C	5/12/2005	329	147			<1.0	<1.0	<1.0	<1.0
MW-13C	11/14/2005	515	333			<1.0	<1.0	<1.0	<b>3.8</b>
MW-13C	5/16/2006	698	516			<1.0	<1.0	<1.0	<b>2.2</b>
MW-13C	11/27/2006	893	711			<0.2	<0.2	<b>0.8</b>	<b>3.4</b>
MW-13C	5/21/2007	1068	886			<0.2	<0.2	<b>0.8</b>	<b>4.4</b>
MW-13C	11/28/2007	1259	1077			<1.0	<1.0	<1.0	<b>2</b>
MW-13C	5/19/2008	1432	1250	-98		<0.2	<0.2	<b>0.2</b>	<b>0.6</b>
MW-13C	11/23/2008	1620	1438	90		<1.0	<1.0	<1.0	<b>2.2</b>
MW-13C	05/18/2009	1796	1614	266		<1.0	<1.0	<1.0	<1.0
MW-13C	11/17/2009	1979	1797	449		<1.0	<1.0	<1.0	<1.0
MW-13C	5/20/2010	2163	1981	633		<1.0	<1.0	<1.0	<1.0
MW-13C	11/10/2010	2337	2155	807		<1.0	<1.0	<1.0	<1.0
MW-13C	5/4/2011	2512	2330	982		<1.0	<1.0	<1.0	<1.0
MW-13C	11/3/2011	2695	2513	1165		<1.0	<1.0	<1.0	<1.0
MW-13C	5/14/2012	2888	2706	1358		<0.2	<0.2	<0.2	<b>0.3</b>
MW-13C	11/13/2012	3071	2889	1541		<2.0	<2.0	<2.0	<2.0
MW-13C	5/21/2013	3260	3078	1730		<2.0	<2.0	<2.0	<2.0
MW-13C	11/12/2013	3435	3253	1905		<2.0	<2.0	<2.0	<2.0
MW-13C	5/7/2014	3611	3429	2081		<1.0	<1.0	<1.0	<1.0
MW-14C	5/4/2004	-44				<1.0	<1.0	<b>63</b>	<b>44</b>
MW-14C	10/26/2004	131	-51	-142		<1.0	<1.0	<b>22</b>	<b>75</b>
MW-14C	5/16/2005	333	151	60		<1.0	<1.0	<b>11</b>	<b>6.1</b>
MW-14C	11/15/2005	516	334	243		<1.0	<1.0	<1.0	<b>1.8</b>
MW-14C	5/17/2006	699	517	426		<1.0	<1.0	<1.0	<1.0
MW-14C	11/29/2006	895	713	622		<0.2	<0.2	<0.2	<b>1.0</b>
MW-14C	5/23/2007	1070	888	797		<1.0	<1.0	<1.0	<b>2.5</b>
MW-14C	12/3/2007	1264	1082	991		<1.0	<1.0	<b>1.1</b>	<b>11</b>
MW-14C	5/20/2008	1433	1251	1160	-97	<1.0	<1.0	<b>1.4</b>	<b>22</b>
MW-14C	11/24/2008	1621	1439	1348	91	<1.0	<1.0	<1.0	<b>4.3</b>
MW-14C	05/20/2009	1798	1616	1525	268	<1.0	<1.0	<1.0	<b>1.1</b>
MW-14C	11/17/2009	1979	1797	1706	449	<1.0	<1.0	<1.0	<1.0
MW-14C	5/24/2010	2167	1985	1894	637	<1.0	<1.0	<1.0	<1.0
MW-14C	11/10/2010	2337	2155	2064	807	<1.0	<1.0	<1.0	<1.0
MW-14C	5/5/2011	2513	2331	2240	983	<1.0	<1.0	<1.0	<1.0
MW-14C	11/13/2011	2705	2523	2432	1175	<0.2	<0.2	<0.2	<0.2
MW-14C	5/14/2012	2888	2706	2615	1358	<0.2	<0.2	<0.2	<0.2
MW-14C	11/14/2012	3072	2890	2799	1542	<2.0	<2.0	<2.0	<2.0
MW-14C	5/21/2013	3260	3078	2987	1730	<2.0	<2.0	<2.0	<2.0
MW-14C	11/12/2013	3435	3253	3162	1905	<2.0	<2.0	<2.0	<2.0
MW-14C	5/7/2014	3611	3429	3338	2081	<1.0	<1.0	<1.0	<1.0
MW-14E	5/4/2004	-44				<1.0	<1.0	<1.0	<1.0
MW-14E	10/26/2004	131	-51	-142		<1.0	<1.0	<1.0	<1.0
MW-14E	5/16/2005	333	151	60		<1.0	<1.0	<1.0	<1.0
MW-14E	11/15/2005	516	334	243		<1.0	<1.0	<1.0	<1.0
MW-14E	5/17/2006	699	517	426		<1.0	<1.0	<1.0	<1.0
MW-14E	11/29/2006	895	713	622		<0.2	<0.2	<0.2	<0.2
MW-14E	5/23/2007	1070	888	797		<1.0	<1.0	<1.0	<1.0
MW-14E	12/3/2007	1264	1082	991		<1.0	<1.0	<1.0	<1.0
MW-14E	5/20/2008	1433	1251	1160	-97	<1.0	<1.0	<1.0	<1.0
MW-14E	11/24/2008	1621	1439	1348	91	<1.0	<1.0	<1.0	<1.0
MW-14E	05/20/2009	1798	1616	1525	268	<1.0	<1.0	<1.0	<1.0
MW-14E	11/17/2009	1979	1797	1706	449	<1.0	<1.0	<1.0	<1.0

**SWMU-20 CLEANUP ACTION SUMMARY - NON SOURCE ZONE  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING**

Well	Date	Elapsed Time from Injections (a) (days)				Volatile Organic Compounds			
						Proposed Groundwater Cleanup Levels (c)			
		1st Injection	2nd Injection	3rd (b) Injection	4th Injection	5.3 PCE (µg/L)	1.4 TCE (µg/L)	134 cDCE (µg/L)	2.4 VC (µg/L)
MW-15C	5/3/2004	-45				<1.0	<1.0	9.1	11
MW-15C	10/26/2004	131	-51			<1.0	<1.0	11	17
MW-15C	5/16/2005	333	151			<1.0	<1.0	13	6.4
MW-15C	11/15/2005	516	334			<1.0	<1.0	<1.0	<1.0
MW-15C	5/17/2006	699	517			<1.0	<1.0	<1.0	<1.0
MW-15C	11/29/2006	895	713			<0.2	<0.2	<0.2	<0.2
MW-15C	5/23/2007	1070	888			<1.0	<1.0	<1.0	2.2
MW-15C	12/3/2007	1264	1082			<1.0	<1.0	<1.0	2.5
MW-15C	5/20/2008	1433	1251	-97		<1.0	<1.0	1.8	6.6
MW-15C	11/24/2008	1621	1439	91		<1.0	<1.0	1.9	6.6
MW-15C	05/19/2009	1797	1615	267		<1.0	<1.0	<1.0	<1.0
MW-15C	11/18/2009	1980	1798	450		<1.0	<1.0	<1.0	<1.0
MW-15C	5/20/2010	2163	1981	633		<1.0	<1.0	<1.0	<1.0
MW-15C	11/10/2010	2337	2155	807		<1.0	<1.0	<1.0	<1.0
MW-15C	5/5/2011	2513	2331	983		<1.0	<1.0	<1.0	<1.0
MW-15C	11/13/2011	2705	2523	1175		<0.2	<0.2	<0.2	<0.2
MW-15C	5/14/2012	2888	2706	1358		<0.2	<0.2	<0.2	<0.2
MW-15C	11/13/2012	3071	2889	1541		<2.0	3.2	<2.0	<2.0
MW-15C	5/21/2013	3260	3078	1730		<5.0	<5.0	<5.0	<5.0
MW-15C	11/12/2013	3435	3253	1905		<2.0	<2.0	<2.0	2.3
MW-15C	5/7/2014	3611	3429	2081		<2.0	<2.0	<2.0	2.9
MW-15D	5/3/2004	-45				<1.0	<1.0	<1.0	<1.0
MW-15D	10/26/2004	131	-51			<1.0	<1.0	<1.0	<1.0
MW-15D	5/16/2005	333	151			<1.0	<1.0	<1.0	<1.0
MW-15D	11/15/2005	516	334			<1.0	<1.0	<1.0	<1.0
MW-15D	5/17/2006	699	517			<1.0	<1.0	<1.0	<1.0
MW-15D	11/29/2006	895	713			<1.0	<1.0	<1.0	<1.0
MW-15D	5/23/2007	1070	888			<1.0	<1.0	<1.0	<1.0
MW-15D	12/3/2007	1264	1082			<1.0	<1.0	<1.0	<1.0
MW-15D	5/20/2008	1433	1251	-97		<1.0	<1.0	<1.0	<1.0
MW-15D	11/24/2008	1621	1439	91		<1.0	<1.0	<1.0	<1.0
MW-15D	05/19/2009	1797	1615	267		<1.0	<1.0	<1.0	<1.0
MW-15D	11/18/2009	1980	1798	450		<1.0	<1.0	<1.0	<1.0
MW-16A	5/2/2004	-46				1.2	1.2	2.3	<1.0
MW-16A	10/25/2004	130	-52			1.2	1.3	1.8	<1.0
MW-16A	5/12/2005	329	147			1.2	1.8	2.6	<1.0
MW-16A	11/15/2005	516	334			1.3	2.2	2.1	<1.0
MW-16A	5/16/2006	698	516			1.0	1.4	2.3	<1.0
MW-16A	11/26/2006	892	710			<0.2	0.8	4.2	<0.2
MW-16A	5/22/2007	1069	887			1.1	1.3	1.9	<1.0
MW-16A	11/28/2007	1259	1077			1.7	1.2	1.2	<1.0
MW-16A	5/19/2008	1432	1250	-98		1.2	1.3	1.2	<0.2
MW-16A	11/23/2008	1620	1438	90		1.5	1.4	1.0	<1.0
MW-16A	05/18/2009	1796	1614	266		1.6	1.6	<1.0	<1.0
MW-16A	11/16/2009	1978	1796	448		2.2	1.5	<1.0	<1.0
MW-16A	5/20/2010	2163	1981	633		1.4	1.4	<1.0	<1.0
MW-16A	11/10/2010	2337	2155	807		1.3	1.1	<1.0	<1.0
MW-16A	5/4/2011	2512	2330	982		1.6	1.4	<1.0	<1.0
MW-16A	11/13/2011	2705	2523	1175		1.4	1.3	0.5	<0.2
MW-16A	5/14/2012	2888	2706	1358		1.6	1.7	0.5	<0.2
MW-16A	11/14/2012	3072	2890	1542		1.1	1.5	0.6	<0.2
MW-16A	5/21/2013	3260	3078	1730		1.4	1.5	<0.5	<0.5
MW-16A	11/12/2013	3435	3253	1905		2.1	1.8	0.3	<0.2
MW-16A	5/8/2014	3612	3430	2082		1.4	1.6	0.4	<0.2

**SWMU-20 CLEANUP ACTION SUMMARY - NON SOURCE ZONE  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING**

Well	Date	Elapsed Time from Injections (a) (days)				Volatile Organic Compounds			
						Proposed Groundwater Cleanup Levels (c)			
		1st Injection	2nd Injection	3rd (b) Injection	4th Injection	5.3 PCE (µg/L)	1.4 TCE (µg/L)	134 cDCE (µg/L)	2.4 VC (µg/L)
MW-16C	5/2/2004	-46				<1.0	<1.0	1.7	5.4
MW-16C	10/25/2004	130	-52			<1.0	<1.0	2.4	8.5
MW-16C	5/12/2005	329	147			<1.0	<1.0	2.8	7.7
MW-16C	11/15/2005	516	334			<1.0	<1.0	4.6	12
MW-16C	5/16/2006	698	516			<1.0	<1.0	5.2	6.3
MW-16C	11/26/2006	892	710			1.2	2.3	2.0	<0.2
MW-16C	5/22/2007	1069	887			<1.0	<1.0	8.8	10
MW-16C	11/28/2007	1259	1077			<1.0	<1.0	7	8.9
MW-16C	5/19/2008	1432	1250	-98		<0.2	<0.2	7.8	7.9
MW-16C	11/23/2008	1620	1438	90		<1.0	<1.0	5.3	8.8
MW-16C	05/18/2009	1796	1614	266		<1.0	<1.0	5.0	6.3
MW-16C	11/16/2009	1978	1796	448		<1.0	<1.0	4.9	5.6
MW-16C	5/20/2010	2163	1981	633		<1.0	<1.0	3.7	3.4
MW-16C	11/10/2010	2337	2155	807		<1.0	<1.0	3.3	2.8
MW-16C	5/4/2011	2512	2330	982		<1.0	<1.0	3.7	3.2
MW-16C	11/13/2011	2705	2523	1175		<0.2	<0.2	3.3	2.5
MW-16C	5/14/2012	2888	2706	1358		<0.2	<0.2	4.8	4.2
MW-16C	11/14/2012	3072	2890	1542		<0.2	<0.2	4.9	3.8
MW-16C	5/21/2013	3260	3078	1730		<0.5	<0.5	3.9	2.8
MW-16C	11/12/2013	3435	3253	1905		<0.2	<0.2	4.4	2.1
MW-16C	5/8/2014	3612	3430	2082		<0.2	<0.2	3.4	1.2
MW-17A	5/2/2004	-46				4.8	6.5	1.0	<1.0
MW-17A	10/25/2004	130	-52			5.2	4.8	1.2	<1.0
MW-17A	11/15/2005	516	334			4.0	5.4	1.1	<1.0
MW-17A	5/15/2006	697	515			4.2	4.4	<1.0	<1.0
MW-17A	11/27/2006	893	711			2.2	6.3	1.0	<0.2
MW-17A	5/21/2007	1068	886			4.7	5.3	1.0	<0.2
MW-17A	11/29/2007	1260	1078			4.2	4.3	<1.0	<1.0
MW-17A	5/19/2008	1432	1250	-98		4.3	5.1	0.8	<0.2
MW-17A	11/23/2008	1620	1438	90		4.2	5.2	1.2	<1.0
MW-17A	05/19/2009	1797	1615	267		3.2	4.9	1.4	<1.0
MW-17A	11/12/2009	1974	1792	444		3.7	4.5	1.1	<1.0
MW-17A	5/20/2010	2163	1981	633		4.0	3.1	<1.0	<1.0
MW-17A	11/8/2010	2335	2153	805		2.3	4.8	2.3	<1.0
MW-17A	5/3/2011	2511	2329	981		3.1	2.2	1.5	<1.0
MW-17A	11/3/2011	2695	2513	1165		2.6	2.8	1.0	<1.0
MW-17A	5/14/2012	2888	2706	1358		3.1	2.0	0.5	<0.2
MW-17A	11/13/2012	3071	2889	1541		2.8	3.5	0.9	<0.2
MW-17A	5/20/2013	3259	3077	1729		3.6	2.8	0.8	<0.2
MW-17A	11/12/2013	3435	3253	1905		3.9	3.4	1.0	<0.2
MW-17A	5/6/2014	3610	3428	2080		3.6	2.6	0.4	<0.2
MW-18A	5/2/2004	-46	-228			<1.0	<1.0	<1.0	<1.0
MW-18C	5/2/2004	-46				<1.0	<1.0	<1.0	<1.0
MW-18C	10/25/2004	130	-52			<1.0	<1.0	<1.0	<1.0
MW-18C	5/12/2005	329	147			<1.0	<1.0	<1.0	<1.0
MW-18C	11/15/2005	516	334			<1.0	<1.0	<1.0	<1.0
MW-18C	5/17/2006	699	517			<1.0	<1.0	<1.0	<1.0

**SWMU-20 CLEANUP ACTION SUMMARY - NON SOURCE ZONE  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING**

Well	Date	Elapsed Time from Injections (a) (days)				Volatile Organic Compounds			
		1st Injection	2nd Injection	3rd (b) Injection	4th Injection	Proposed Groundwater Cleanup Levels (c)			
						5.3	1.4	134	2.4
					PCE (µg/L)	TCE (µg/L)	cDCE (µg/L)	VC (µg/L)	
MW-18C	11/27/2006	893	711			<0.2	<0.2	<0.2	<0.2
MW-18C	5/21/2007	1068	886			<0.2	<0.2	<0.2	<b>0.2</b>
MW-18C	11/28/2007	1259	1077			<1.0	<1.0	<1.0	<1.0
MW-18C	5/19/2008	1432	1250		-98	<0.2	<0.2	<0.2	<b>0.2</b>
MW-18C	11/23/2008	1620	1438		90	<1.0	<1.0	<1.0	<1.0
MW-18C	05/19/2009	1797	1615		267	<1.0	<1.0	<1.0	<1.0
MW-18C	11/17/2009	1979	1797		449	<1.0	<1.0	<1.0	<1.0
MW-19C	5/2/2004	-46				<1.0	<1.0	<1.0	<1.0
MW-19C	10/25/2004	130	-52			<1.0	<1.0	<1.0	<1.0
MW-19C	5/12/2005	329	147			<1.0	<1.0	<1.0	<1.0
MW-19C	11/15/2005	516	334			<1.0	<1.0	<1.0	<1.0
MW-19C	5/17/2006	699	517			<1.0	<1.0	<1.0	<1.0
MW-19C	11/27/2006	893	711			<0.2	<0.2	<b>0.3</b>	<0.2
MW-19C	5/22/2007	1069	887			<1.0	<1.0	<1.0	<1.0
MW-19C	11/29/2007	1260	1078			<1.0	<1.0	<1.0	<1.0
MW-19C	5/20/2008	1433	1251		-97	<1.0	<1.0	<1.0	<1.0
MW-19C	11/23/2008	1620	1438		90	<1.0	<1.0	<1.0	<1.0
MW-19C	05/19/2009	1797	1615		267	<1.0	<1.0	<1.0	<1.0
MW-19C	11/18/2009	1980	1798		450	<1.0	<1.0	<1.0	<1.0
MW-20C	5/3/2004	-45				<1.0	<1.0	<b>1.4</b>	<b>2.4</b>
MW-20C	10/25/2004	130	-52			<1.0	<1.0	<b>1.7</b>	<b>4.6</b>
MW-20C	5/12/2005	329	147			<1.0	<1.0	<b>1.7</b>	<b>2.3</b>
MW-20C	11/15/2005	516	334			<1.0	<1.0	<b>2.1</b>	<b>2.9</b>
MW-20C	5/17/2006	699	517			<1.0	<1.0	<b>1.8</b>	<b>1.6</b>
MW-20C	11/29/2006	895	713			<0.2	<b>0.2</b>	<b>2.1</b>	<b>1.5</b>
MW-20C	5/21/2007	1068	886			<0.2	<0.2	<b>1.6</b>	<b>1.8</b>
MW-20C	11/29/2007	1260	1078			<1.0	<1.0	<b>1.6</b>	<b>1.3</b>
MW-20C	5/20/2008	1433	1251		-97	<1.0	<1.0	<b>1.6</b>	<b>2.5</b>
MW-20C	11/23/2008	1620	1438		90	<1.0	<1.0	<b>1.5</b>	<b>2.7</b>
MW-20C	05/19/2009	1797	1615		267	<1.0	<1.0	<b>1.4</b>	<b>2.0</b>
MW-20C	11/18/2009	1980	1798		450	<1.0	<1.0	<b>1.7</b>	<b>2.3</b>
MW-20C	5/20/2010	2163	1981		633	<1.0	<1.0	<b>1.3</b>	<b>1.8</b>
MW-20C	11/8/2010	2335	2153		805	<1.0	<1.0	<b>1.4</b>	<b>1.4</b>
MW-20C	5/4/2011	2512	2330		982	<1.0	<1.0	<b>1.1</b>	<b>1.8</b>
MW-20C	11/3/2011	2695	2513		1165	<1.0	<1.0	<b>1.3</b>	<b>2.1</b>
MW-20C	5/14/2012	2888	2706		1358	<0.2	<0.2	<b>1.2</b>	<b>1.5</b>
MW-20C	11/13/2012	3071	2889		1541	<2.0	<2.0	<2.0	<2.0
MW-20C	5/21/2013	3260	3078		1730	<5.0	<5.0	<5.0	<5.0
MW-20C	11/12/2013	3435	3253		1905	<2.0	<2.0	<2.0	<2.0
MW-20C	5/7/2014	3611	3429		2081	<2.0	<2.0	<2.0	<2.0

PCE = Tetrachloroethene  
TCE = Trichloroethene  
cDCE = cis-1,2-Dichloroethene  
VC = Vinyl Chloride  
µg/L - micrograms per liter  
Bold = Detect  
TMCL = Target Media Cleanup Level.  
Box = Exceedance of TMCL.

(a) Injections occurred on:  
6/17/04 (6A, B, C; 9A, B, C)  
12/16-17/04 (6A, 6B;9A,9B)  
3/17/05 (14A)  
8/25-28/08 (6A, 9A, 10A)

6/17/2004 for elapsed time relative to injection  
12/16/2004 for elapsed time relative to injection  
3/17/2005 for elapsed time relative to injection  
8/25/2008 for elapsed time relative to injection

(b) Conducted at Well MW-14A only.

(c) Proposed Cleanup Standards and Comparison to Site Data, Boeing Developmental Center, Tukwila, Washington (Landau Associates, 5/7/13).

*DEVELOPMENTAL CENTER  
GROUNDWATER MONITORING  
MAY 2014*

**SWMU-17 VOA/METALS/CONVENTIONALS DATA TABLES**

**SWMU-17 CLEANUP ACTION SUMMARY**

**SWMU-17 REMEDIAL ACTION INJECTION AND MONITORING WELLS**

**SWMU-17 VOA/METALS/CONVENTIONALS DATA  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING  
FEBRUARY AND MAY 2014**

Sample Name:	BDC-05-02	BDC-05-02	BDC-05-03	BDC-05-03-Dup	BDC-05-04	BDC-05-05	BDC-05-07	BDC-05-08	BDC-05-09	BDC-05-10	BDC-05-11	BDC-05-12	BDC-05-12	BDC-05-13	BDC-05-14	BDC-05-15	BDC-05-16	BDC-05-16-Dup	BDC-05-16
LLI SDG:	1452657	1474673	1474673	1474673	1474673	1474673	1474673	1474673	1474673	1474673	1474673	1452657	1474673	1474673	1474673	1474673	1452657	1452657	1474673
LLI Sample ID:	7364263	7465196	7465160	7465178	7465232	7465238	7465190	7465142	7465184	7465172	7465166	7364265	7465154	7465124	7465130	7465136	7364269	7364271	7465112
Sample Date:	2/11/2014	5/13/2014	5/13/2014	5/13/2014	5/13/2014	5/13/2014	5/13/2014	5/13/2014	5/13/2014	5/13/2014	5/13/2014	2/11/2014	5/13/2014	5/12/2014	5/12/2014	5/13/2014	2/11/2014	2/11/2014	5/12/2014
Test ID: VOA SW8260C (µg/L)																			
Vinyl Chloride	0.2 U	2.4	0.2 U	0.2 U	0.2 U	0.2 U	1.4	1.8	1.0	5.1	2.0	1.0 U	1.0 U	2.6	1.5	8.6	2.1	2.2	4.9
cis-1,2-Dichloroethene	0.2 U	1.5	0.2 U	0.2 U	0.8	0.2 U	2.5	2.9	0.7	0.2 U	0.2 U	1.0 U	1.0 U	0.2 U	0.2	0.2 U	1.0 U	1.0 U	1.0 U
Trichloroethene	0.2 U	1.1	0.7	0.7	0.3	0.9	0.2	0.2 U	0.2 U	0.2 U	0.2 U	1.0 U	1.0 U	0.2 U	0.2 U	0.2 U	1.0 U	1.0 U	1.3
Tetrachloroethene	0.8	0.8	1.5	1.5	0.6	0.4	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U	1.0 U	1.0 U	0.2 U	0.2 U	0.2 U	1.0 U	1.0 U	1.0 U
Test ID: Total Metals (mg/L)																			
Arsenic (EPA 200.8)		0.0225	0.0028	0.0023	0.0017 J	0.0008 U	0.0041	0.0145	0.0098	0.0368	0.0377			0.0065	0.0317	0.0182	0.0653		0.0438
Copper (EPA 200.8)		0.0034	0.0024	0.0023	0.0047	0.0020 U	0.0020 U	0.0035	0.0020 U	0.0020 U	0.0020 U			0.0020 U	0.0020 U	0.0020 U	0.0020 U		0.0020 U
Test ID: Dissolved Metals (mg/L)																			
Arsenic (EPA 200.8)		0.0192	0.0008 U	0.0011 J	0.0022	0.0008 U	0.0038	0.0108	0.010	0.0339	0.0357			0.0057	0.0316	0.0210	0.0611		0.0411
Copper (EPA 200.8)		0.0020 U	0.0020 U	0.0020 U	0.0021	0.0020 U	0.0020 U	0.0020 U	0.0020 U	0.0020 U	0.0020 U			0.0020 U	0.0020 U	0.0020 U	0.0020 U		0.0020 U
Test ID: Conventional (mg/L)																			
Sulfate (EPA 300.0)	0.30 U	5.7	9.6	9.9	14.1	18.6	1.8	0.31 J	1.9	0.30 U	0.30 U	0.37 J	0.49 J	0.30 U	0.30 U	0.30 U	0.30 U	0.30 U	0.30 U
Total Organic Carbon (SM5310C)	7.1	66.5	5.4	5.0	8.2	3.6	9.1	9.5	13.1	27.6	38.1	19.7	21.5	23.4	30.2	37.5	28.9	28.3	28.7
Test ID: Dissolved Gases; Mod RSK-175 (µg/L)																			
Methane	12000	15000	1000	1200			3700	7700	8000	21000	24000	23000	25000	19000	22000	26000	25000	22000	28000
Ethane	3.0 U	1.0 U	1.1 J	1.4 J			1.0 U	1.0 U	8.5	1.0 U	7.2	6.0 U	5.6	6.8	5.0 J	1.0 U	7.0 U	7.0 U	1.0 U
Ethene	1.0 U	5.1	1.0 U	1.0 U			1.0 U	1.0 U	1.6 J	29	9.0	1.1 J	1.0 J	4.3 J	2.2 J	9.4	2.0 J	1.9 J	4.9 J
Acetylene	1.0 U	1.0 U	1.0 U	1.0 U			1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U

**SWMU-17 VOA/METALS/CONVENTIONALS DATA  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING  
FEBRUARY AND MAY 2014**

Sample Name:	BDC-05-17	BDC-05-18	BDC-05-18	BDC-05-19	BDC-05-19	BDC-05-20	BDC-05-20	BDC-05-21	BDC-05-21	BDC-05-22	BDC-05-22	BDC-05-23	BDC-05-23	BDC-05-24	BDC-05-24	Trip Blank	Trip Blank
LLI SDG:	1474673	1452657	1474673	1452657	1474673	1452657	1474673	1452657	1474673	1452657	1474673	1452657	1474673	1452657	1474673	1452657	1474673
LLI Sample ID:	7465118	7364283	7465202	7364267	7465148	7364275	7465214	7364273	7465208	7364277	7465220	7364281	7465226	7364279	7465106	7364285	7465244
Sample Date:	5/12/2014	2/12/2014	5/13/2014	2/11/2014	5/13/2014	2/12/2014	5/13/2014	2/12/2014	5/13/2014	2/12/2014	5/13/2014	2/12/2014	5/13/2014	2/12/2014	5/12/2014	2/12/2014	5/13/2014
Test ID: VOA SW8260C (µg/L)																	
Vinyl Chloride	3.2	0.3	0.3	2.0	1.8	7.8	6.3	3.4	2.2	0.2 U	0.2 U	1.2	1.0	0.6	1.6	0.2 U	0.2 U
cis-1,2-Dichloroethene	0.4	5.4	4.4	1.0 U	1.0 U	3.9	3.8	3.0	1.9	5.7	6.7	2.7	4.5	1.7	4.8	0.2 U	0.2 U
Trichloroethene	0.2 U	2.1	2.4	1.0 U	1.0 U	0.2	0.2 U	0.2	0.2 U	0.7	1.4	0.2	0.3	0.2	0.3	0.2 U	0.2 U
Tetrachloroethene	0.2 U	1.7	2.0	1.0 U	1.0 U	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U
Test ID: Total Metals (mg/L)																	
Arsenic (EPA 200.8)	0.0379		0.0014 J		0.0325		0.0167		0.0217		0.0266		0.0234		0.0028		
Copper (EPA 200.8)	0.0020 U		0.0020 U		0.0031		0.0020 U		0.0020 U		0.0020 U		0.0020 U		0.0020 U		
Test ID: Dissolved Metals (mg/L)																	
Arsenic (EPA 200.8)	0.0334		0.0018 J		0.0253		0.0170		0.0170		0.0247		0.0228		0.0024		
Copper (EPA 200.8)	0.0020 U		0.0020 U		0.0020 U		0.0020 U		0.0020 U		0.0020 U		0.0020 U		0.0020 U		
Test ID: Conventional (mg/L)																	
Sulfate (EPA 300.0)	0.30 U	3.2	6.7	0.39 J	0.37 J	0.30 U	0.36 J	0.30 U	0.60 J	4.9	8.7	0.74 J	3.1	0.81 J	0.87 J		
Total Organic Carbon (SM5310C)	44.1	1.4	2.6	64.8	54.9	16.3	18.7	8.3	8.6 J	7.3	8.4	9.3	12.1	7.1	8.2 J		
Test ID: Dissolved Gases; Mod RSK-175 (µg/L)																	
Methane	25000	3700	3200	23000	26000	16000	16000	12000	9100					11000	10000	3.0 U	
Ethane	6.0	1.0 U	1.0 U	5.7	5.9	4.0 U	1.0 U	2.9 J	2.9 J					3.0 J	2.3 J	1.0 U	
Ethene	2.5 J	1.0 U	1.0 U	2.5 J	2.0 J	3.0 J	2.0 J	1.9 J	2.8 J					1.1 J	1.0 J	1.0 U	
Acetylene	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U					1.0 U	1.0 U	1.0 U	

µg/L = micrograms per liter.  
 mg/L = milligrams per liter.  
 EPA = U.S. Environmental Protection Agency  
 U = Indicates compound was analyzed for, but was not detected at the given detection limit.  
 J = Indicates the analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.





**TABLE 1  
GROUNDWATER DATA SUMMARY  
BOEING DEVELOPMENTAL CENTER SWMU-17**

Well	Date	Pilot Injection Elapsed Time From Injection (days)	Full Injection #1 Elapsed Time From Injection (days)	Volatile Organic Compounds							Metals				Aquifer Redox Conditions						Donor Indicators		Comments
				PCE (µg/L)	TCE (µg/L)	cDCE (µg/L)	VC (µg/L)	Ethene (µg/L)	Ethane (µg/L)	Acetylene (µg/L)	As, Tot (mg/L)	As, Dis (mg/L)	Cu, Tot (mg/L)	Cu, Dis (mg/L)	DO (mg/L)	Nitrate (mg-N/L)	Iron II (mg/L)	Sulfate (mg/L)	Methane (mg/L)	ORP (mV)	TOC (mg/L)	pH	
<b>Proposed Groundwater Cleanup Levels (a)</b>																							
				5.3	1.4	134	2.4	NA	NA	NA	0.008	0.008	0.008	0.008									
BDC-05-04	5/21/2007	-526		<1.0	<1.0	1.4	<1.0				0.018	<0.001	<0.002	<0.002									
(MW 22 ft XG)	11/26/2007	-337		<1.0	<1.0	1.6	<1.0				0.009	<0.001	<0.002	<0.002									
	5/22/2008	-159		1.5	0.9	1.2	<0.2				0.018	<0.001	<0.002	<0.002									
BDC-05-04	10/23/2008	-5		1.1	0.8	2.1	<0.2	<1.1	<1.2	<1.1	0.009	<0.001	<0.002	<0.002	2.45	7.6	0.1	31.0	0.3	73.5	3.8	6.33	
BDC-05-04	11/20/2008	23		1.1	0.7	3.6	<0.2	<1.1	<1.2	<1.1	0.019	<0.001	<0.002	<0.002	0.59	4.5	0.8	25.2	0.05	-16	5.1	6.25	
BDC-05-04	12/16/2008	49		<1.0	<1.0	2.4	<1.0	<1.1	<1.2	<1.1	0.019	0.002	0.003	<0.002	0.55	5.5	1.0	30.4	1.6	-98	6.9	6.24	
BDC-05-04	1/16/2009	80		<1.0	<1.0	2.0	<1.0	<1.1	<1.2	<1.1	0.017	<0.001	<0.002	<0.002	0.06	4.3	1.0	21.8	1.5	-192	5.1	6.23	
BDC-05-04	2/11/2009	106		1.0	<1.0	1.5	<1.0	<1.1	<1.2	<1.1	0.020	<0.001	<0.002	<0.002	2.45	5.9	1.0	31.8	1.1	-54	6.8	6.17	
BDC-05-04	3/9/2009	132		1.0	<1.0	1.3	<1.0	<1.1	<1.2	<1.1	0.014	0.001	0.002	<0.002	0.27	4.8	1.5	30.1	0.2	35	5.2	6.22	
BDC-05-04	4/16/2009	170		1.2	<1.0	<1.0	<1.0	<1.1	<1.2	<1.1	0.011	0.001	<0.002	<0.002	1.48	5.9	1.4	33.6	<0.0007	68	5.7	6.29	
BDC-05-04	5/13/2009	197		<1.0	<1.0	1.0	<1.0	<1.1	<1.2	<1.1	0.007	0.001	0.002	<0.002	0.33	4.5	1.6	26.6	0.4	49	5.2	6.37	
BDC-05-04	8/16/2009	292		1.3	<1.0	<1.0	<1.0	<1.1	<1.2	<1.1	0.012	0.001	0.002	<0.002	0.86	5.4	2.2	30.6	<0.0007	93	5.0	6.97	
BDC-05-04	11/13/2009	381		<1.0	<1.0	1.2	<1.0	<1.1	<1.2	<1.1	0.005	0.001	<0.002	<0.002	0.56	2.2	3.0	18.4	2.4	109	4.4	5.86	
BDC-05-04	2/16/2010	476		<1.0	<1.0	1.1	<1.0	<1.1	<1.2	<1.1	0.004	0.002	0.012	0.002	0.88	<0.1	3.3	24.6	1.5	899	8.9	6.24	
BDC-05-04	5/18/2010	567		1.1	<1.0	1.2	<1.0	<1.1	<1.2	<1.1	0.014	0.001	0.005	<0.002	0.75	<0.1	3.0	25.4	1.3	473	7.1	6.19	
BDC-05-04	8/17/2010	658		<1.0	<1.0	3.0	<1.0	<1.1	<1.2	<1.1	0.012	0.002	0.006	<0.002	1.00	<0.1	2.8	17.7	3.5	108	8.7	6.48	
BDC-05-04	11/9/2010	742		<1.0	<1.0	4.3	<1.0	<1.1	<1.2	<1.1	0.008	0.004	<0.002	<0.002	2.21	<0.1	2.2	21.3	3.0	101	7.2	6.84	
BDC-05-04	2/15/2011	840		<1.0	<1.0	2.9	<1.0	<1.1	<1.2	<1.1	0.007	0.004	<0.002	<0.002	2.50	<0.1	2.4	19.4	4.5	93	6.9	6.85	
BDC-05-04	5/2/2011	916	-108	0.4	0.5	3.1	<0.2	<1.1	<1.2	<1.1	0.008	0.004	<0.002	<0.002	1.69	<0.1	2.2	18.0	1.8	49	6.8	6.76	
BDC-05-04	11/2/2011	1100	76	<1.0	<1.0	4.2	<1.0				0.007	0.006	<0.002	<0.002	1.52	<1.0	1.2	<1.0		-3	6.6	7.17	
BDC-05-04	5/7/2012	1287	263	0.4	0.6	3.6	<0.2				0.017	0.016	<0.002	<0.002	0.16		2.0	21.5		98	8.6	6.39	
BDC-05-04	11/13/2012	1477	453	<0.5	<0.5	3.3	<0.5				0.012	0.010	0.002	<0.002	0.02		1.2	14.3		27	6.5	6.85	
BDC-05-04	5/23/2013	1668	644	<0.2	<0.2	2.1	<0.2				0.026	0.027	<0.002	<0.002	0.49		1.5	13.7		-310	12.7	7.78	
BDC-05-04	11/13/2013	1842	818	<0.2	0.3	3.6	<0.2				0.016	0.015	0.002	<0.002	2.05		1.8	14.4		-262	8.1	6.48	
BDC-05-04	5/13/2014	2023	999	0.6	0.3	0.8	<0.2				0.002	0.002	0.005	0.002	3.86		0.6	14.1		-177	8.2	6.28	
BDC-05-05	5/21/2007	-526		<1.0	<1.0	<1.0	<1.0				0.002	<0.001	0.003	<0.002									
(MW UG)	11/26/2007	-337		<1.0	<1.0	<1.0	<1.0				<0.001	<0.001	<0.002	<0.002									
	5/22/2008	-159		0.3	0.8	<0.2	<0.2				0.002	<0.001	0.003	<0.002									
BDC-05-05	10/23/2008	-5																					
BDC-05-05	11/20/2008	23		0.3	0.7	<0.2	<0.2				0.005	0.001	0.005	0.003	4.61					52		6.25	
BDC-05-05	12/16/2008	49																					
BDC-05-05	1/16/2009	80																					
BDC-05-05	2/11/2009	106																					
BDC-05-05	3/9/2009	132																					
BDC-05-05	4/16/2009	170																					
BDC-05-05	5/13/2009	197		<1.0	<1.0	<1.0	<1.0				0.003	<0.001	0.006	0.002	3.24					68		6.72	
BDC-05-05	8/16/2009	292																					
BDC-05-05	11/13/2009	381		<1.0	<1.0	<1.0	<1.0				0.001	<0.001	<0.002	<0.002	2.85	1.2	0.0	8.7		166		5.84	
BDC-05-05	2/16/2010	476																					
BDC-05-05	5/18/2010	567		<1.0	<1.0	<1.0	<1.0				0.002	0.0004	0.002	<0.002	3.47		0.0			494		6.74	
BDC-05-05	8/17/2010	658																					
BDC-05-05	11/9/2010	742		<1.0	1.1	<1.0	<1.0				0.001	0.0004	0.003	<0.002	3.20					135		6.90	
BDC-05-05	2/15/2011	840									0.001	0.0003	0.003	<0.002	3.40					158		6.98	
BDC-05-05	5/2/2011	916	-108	0.3	0.8	<0.2	<0.2				0.001	0.0003	0.002	0.003	2.84	<0.1	0.0	7.5		85	1.7	7.66	
BDC-05-05	11/2/2011	1100	76	<1.0	1.2	<1.0	<1.0				<0.001	<0.001	0.003	<0.002	3.23		0.0	22.1		219	1.1	6.42	
BDC-05-05	5/6/2012	1286	262	0.4	0.9	<0.2	<0.2				0.001	0.0005	0.003	<0.002	1.76		0.2	20.6	<0.003	27	<1.0	6.82	
BDC-05-05	11/13/2012	1477	453	<0.5	1.1	<0.5	<0.5	<1.0	<1.0	<1.0	0.001	0.001	<0.002	<0.002	4.69		0.7	11.7		-165	1.5	7.35	
BDC-05-05	5/23/2013	1668	644	0.3	0.9	<0.2	<0.2				<0.001	<0.001	0.003	<0.002	1.95		0.0	21.8		-219	<1.0	6.70	
BDC-05-05	11/14/2013	1843	819	0.5	1.1	<0.2	<0.2				<0.001	<0.001	<0.002	<0.002	4.35		0.0	18.6		-108	3.6	6.60	
BDC-05-05	5/13/2014	2023	999	0.4	0.9	<0.2	<0.2																
BDC-05-07	5/21/2007	-526		30	22	10	<1.0				0.003	<0.001	0.014	0.009									
(IW)	11/26/2007	-337		28	25	11	<1.0				<0.001	<0.001	0.011	0.002									
	5/22/2008	-159		33	32	9.2	<0.2				0.002	<0.001	0.012	0.006									
BDC-05-07	10/23/2008	-5		22	24	14	<0.2	<1.1	<1.2	<1.1	0.004	0.002	0.022	0.013	9.71	9.6	0.0	33.4	0.6	86.0	7.8	6.47	
BDC-05-07	11/20/2008	23		17	17	4.9	<0.2	<1.1	<1.2	<1.1	0.003	<0.001	0.016	0.010	0.60	2.2	0.4	15.8	0.2	-27	4.6	6.46	

**TABLE 1  
GROUNDWATER DATA SUMMARY  
BOEING DEVELOPMENTAL CENTER SWMU-17**

Well	Date	Pilot Injection Elapsed Time From Injection (days)	Full Injection #1 Elapsed Time From Injection (days)	Volatile Organic Compounds							Metals				Aquifer Redox Conditions					Donor Indicators		Comments	
				PCE (µg/L)	TCE (µg/L)	cDCE (µg/L)	VC (µg/L)	Ethene (µg/L)	Ethane (µg/L)	Acetylene (µg/L)	As, Tot (mg/L)	As, Dis (mg/L)	Cu, Tot (mg/L)	Cu, Dis (mg/L)	DO (mg/L)	Nitrate (mg-N/L)	Iron II (mg/L)	Sulfate (mg/L)	Methane (mg/L)	ORP (mV)	TOC (mg/L)		pH
				5.3	1.4	134	2.4	NA	NA	NA	0.008	0.008	0.008	0.008									
BDC-05-07	12/16/2008	49		16	25	7.2	<1.0	<1.1	<1.2	<1.1	0.003	0.001	0.016	0.012	1.20	4.8	0.0	29.4	0.6	-107	6.1	6.49	
BDC-05-07	1/16/2009	80		20	23	6.4	<1.0	<1.1	<1.2	<1.1	0.002	<0.001	0.013	0.008	0.00	8.4	0.0	32.6	0.03	-182	6.3	6.38	
BDC-05-07	2/11/2009	106		23	28	9.9	<1.0	<1.1	<1.2	<1.1	0.002	0.001	0.017	0.012	2.05	11.2	0.0	37.5	1.5	-68	9.3	6.37	
BDC-05-07	3/9/2009	132		20	21	8.4	<1.0	<1.1	<1.2	<1.1	<0.002	<0.001	0.013	0.009	0.00	8.8	0.3	35.3	5.5	-23	6.8	6.37	
BDC-05-07	4/16/2009	170		20	21	11	<1.0	<1.1	<1.2	<1.1	0.002	0.001	0.015	0.008	0.27	8.2	0.0	31.2	5.1	35	8.1	6.43	
BDC-05-07	5/13/2009	197		11	13	7.5	<1.0	<1.1	<1.2		0.002	0.001	0.016	0.008	0.29	6.8	0.4	27.2	7.9	34	7.3	6.47	
BDC-05-07	8/16/2009	292		11	12	13	<1.0	<1.1	<1.2	<1.1	0.002	0.001	0.010	<0.002	0.74	2.3	2.0	23.2	6.8	67	8.2	6.73	
BDC-05-07	11/13/2009	381		6.5	5.3	5.6	<1.0	<1.1	<1.2	<1.1	0.002	0.001	0.004	<0.002	0.50	<0.1	2.8	5.7	4.7	16	9.1	6.48	
BDC-05-07	2/16/2010	476		6.4	6.9	28	<1.0	<1.1	<1.2	<1.1	0.004	0.003	0.017	0.006	1.04	<0.1	2.5	20.4	5.2	839	14.7	6.88	
BDC-05-07	5/18/2010	567		5.8	9.2	41	1.2	<1.1	<1.2	<1.1	0.009	0.003	0.009	<0.002	1.06	<0.5	2.0	16.4	6.0	525	14.8	6.77	
BDC-05-07	8/17/2010	658		2.8	7.8	19	<1.0	<1.1	<1.2	<1.1	0.006	0.003	0.008	<0.002	2.30	<0.1	2.5	8.6	7.1	-15	18.8	7.34	
BDC-05-07	11/9/2010	742		<1.0	9.4	20	<1.0	<1.1	<1.2	<1.1	0.008	0.005	0.009	<0.002	2.42	<0.1	2.2	15.2	5.1	13	15.2	7.35	
BDC-05-07	2/15/2011	840		<1.0	8.7	20	<1.0	<1.1	<1.2	<1.1	0.013	0.010	0.012	0.002	3.02	<0.1	2.8	11.8	5.1	21	14.0	7.16	
BDC-05-07	5/2/2011	916	-108	5.2	11	17	<0.2	<1.1	<1.2	<1.1	0.017	0.004	0.014	0.003	2.14	0.1	2.6	15.6	3.2	33	16.8	6.90	
BDC-05-07	11/2/2011	1100	76	11	6.9	39	<1.0	<1.1	<1.2	<1.1	0.042	0.035	0.010	0.006	2.06	<0.1	2.4	<1.0	16.1	-51	1780	6.31	
BDC-05-07	5/7/2012	1287	263	0.8	<0.2	23	0.9	<1.0	<1.0	<1.0	0.026	0.024	0.003	<0.002	0.17		1.6	0.4	27.0	100	48.5	6.34	
BDC-05-07	11/15/2012	1479	455	<0.2	0.4	24	0.8	<1.0	<1.0	<1.0	0.016	0.017	<0.002	<0.002	0.01		1.6	<0.3	23.0	3.0	26	6.60	
BDC-05-07	5/22/2013	1667	643	<0.2	0.3	8.6	0.5	<1.0	<1.0	<1.0	0.006	0.007	<0.002	<0.002	0.17		1.4	0.45	11.0	-372	10.5	8.09	
BDC-05-07	11/13/2013	1842	818	<0.2	<0.2	3.4	1.6	<1.0	1.3	<1.0	0.006	0.007	<0.002	<0.002	2.12		1.2	<0.30	8.5	-276	8.8	6.70	
BDC-05-07	5/13/2014	2023	999	<0.2	0.2	2.5	1.4	<1.0	<1.0	<1.0	0.004	0.004	<0.002	<0.002	3.65		2.0	1.8	3.7	-368	9.1	6.55	
BDC-05-08	10/23/2008	-5		1.1	3.7	3.5	<0.2	<1.1	<1.2	<1.1	0.007	<0.001	0.004	<0.002	1.90	0.3	0.0	8.9	4.7	-12.0	5.1	6.65	
(MW 24 ft XG)	11/20/2008	23		1.1	3.4	4.2	<0.2	<1.1	<1.2	<1.1	0.035	0.004	0.036	<0.002	0.80	0.7	2.2	7.2	5.5	-43	5.9	6.63	
	12/16/2008	49		1.2	4.3	4.3	<1.0	<1.1	<1.2	<1.1	0.008	0.001	0.006	<0.002	0.50	0.9	4.6	21.8	3.6	-99	5.4	6.61	
BDC-05-08	1/16/2009	80		1.3	4.2	3.6	<1.0	<1.1	<1.2	<1.1	0.008	0.002	0.007	<0.002	0.25	1.7	3.0	7.0	6.9	-185	5.8	6.59	
BDC-05-08	2/11/2009	106		<1.0	3.2	3.9	<1.0	<1.1	<1.2	<1.1	0.019	0.001	0.010	<0.002	2.38	0.3	4.4	4.7	4.4	-78	7.0	6.69	
BDC-05-08	3/9/2009	132		<1.0	2.7	3.5	<1.0	<1.1	<1.2	<1.1	0.009	0.003	0.007	<0.002	0.07	<0.1	3.6	3.8	4.9	-4	6.7	6.65	
BDC-05-08	4/16/2009	170		<1.0	2.3	4.4	<1.0	<1.1	<1.2	<1.1	0.007	0.003	0.006	<0.002	0.42	<0.1	2.0	1.7	6.7	-8	6.8	6.80	
BDC-05-08	5/13/2009	197		<1.0	1.6	3.0	<1.0	<1.1	<1.2		0.009	0.003	0.007	0.002	1.77	<0.1	4.0	0.8	11.4	-13	6.0	6.87	
BDC-05-08	8/16/2009	292		<1.0	2.1	3.5	<1.0	<1.1	<1.2	<1.1	0.012	0.008	<0.002	<0.002	0.87	<0.1	2.8	5.3	13.2	-20	6.1	7.15	
BDC-05-08	11/13/2009	381		<1.0	1.2	3.1	<1.0	<1.1	<1.2	<1.1	0.011	0.008	0.007	<0.002	0.73	<0.1	2.8	3.3	17.4	0.8	8.4	6.44	
BDC-05-08	2/16/2010	476		<1.0	<1.0	2.3	<1.0	<1.1	<1.2	<1.1	0.024	0.009	0.024	<0.002	0.63	<0.1	3.0	0.8	13.1	841	8.3	6.76	
BDC-05-08	5/18/2010	567		<1.0	<1.0	2.4	<1.0	<1.1	<1.2	<1.1	0.031	0.011	0.027	<0.002	0.96	<0.1	3.0	0.8	14.9	451	7.3	6.92	
BDC-05-08	8/17/2010	658		<1.0	<1.0	2.3	<1.0	<1.1	<1.2	<1.1	0.014	0.009	0.013	<0.002	2.57	<0.1	3.2	0.5	10.1	-30	7.2	7.30	
BDC-05-08	11/9/2010	742		<1.0	<1.0	3.5	<1.0	<1.1	<1.2	<1.1	0.031	0.012	0.031	<0.002	2.74	<0.1	2.4	0.3	14.2	59	7.6	7.17	
BDC-05-08	2/15/2011	840		<1.0	<1.0	2.1	<1.0	<1.1	<1.2	<1.1	0.021	0.010	0.016	<0.002	2.36	<0.1	5.0	0.3	14.1	66	8.7	7.08	
BDC-05-08	5/2/2011	916	-108	<0.2	<0.2	2.2	<0.2	<1.1	<1.2	<1.1	0.029	0.010	0.024	<0.002	2.15	<0.1	2.4	0.7	7.8	-28	8.0	7.17	
BDC-05-08	11/2/2011	1100	76	<1.0	<1.0	2.4	<1.0				0.014	0.010	0.012	0.003	1.15	<0.1	1.2	0.8		-53	7.3	6.88	
BDC-05-08	5/6/2012	1286	262	<0.2	<0.2	2.7	<0.2				0.021	0.020	0.007	0.002	0.01		2.5	0.4		42	12.4	6.77	
BDC-05-08	11/16/2012	1480	456	<0.5	<0.5	1.3	<0.5				0.014	0.010	0.005	<0.002	0.01		1.0	<0.3		5	8.1	6.91	
BDC-05-08	5/23/2013	1668	644	<0.2	<0.2	0.4	<0.2				0.008	0.007	0.002	<0.002	0.39		1.3	<0.3		-249	5.7	7.68	
BDC-05-08	11/13/2013	1842	818	<0.2	<0.2	4.3	0.8				0.012	0.010	0.003	<0.002	2.02		1.4	<0.30		-275	15.0	6.73	
BDC-05-08	5/13/2014	2023	999	<0.2	<0.2	2.9	1.8	<1.0	<1.0	<1.0	0.015	0.011	0.004	<0.002	2.02		1.4	0.31	7.7	-255	9.5	6.87	
BDC-05-09	7/31/2011		-18	30	20	22	<1.0	<1.1	<1.2	<1.1	0.007	0.007	<0.002	<0.002	1.37	<0.1	2.5	12.1	1.4	15	5.5	6.89	
(IW)	11/2/2011	76		37	56	44	1.3	<1.1	<1.2	<1.1	0.042	0.040	0.009	0.006	2.80	<0.1	3.0	7.6	4.3	80	4360	5.24	
	5/7/2012	263		3.0	1.1	250	3.9	<1.0	<1.0	<1.0	0.059	0.052	0.011	<0.002	0.69		2.2	0.5	18.0	85	531	6.33	
BDC-05-09	11/15/2012	455	<2.0	<2.0	24	20	69	<1.0	<1.0	<1.0	0.074	0.070	0.006	<0.002	0.01		1.2	<0.3	27.0	-10	266	6.71	
BDC-05-09	5/22/2013	643	<0.2	<0.2	1.0	3.7	23	3.4	<1.0	<1.0	0.026	0.025	0.003	<0.002	0.18		1.5	<0.3	17.0	-300	40.6	7.83	
BDC-05-09	11/13/2013	818	<0.2	<0.2	3.2	14	8.6	8.3	<1.0	<1.0	0.022	0.022	<0.002	<0.002	2.80		1.4	0.9	11.0	-263	36.8	6.61	
BDC-05-09	5/13/2014	999	<0.2	<0.2	0.7	1.0	1.6	8.5	<1.0	<1.0	0.010	0.010	<0.002	<0.002	3.66		1.5	1.9	8.0	-356	13.1	6.53	
BDC-05-10	7/31/2011		-18	39	26	12	<1.0	<1.1	<1.2	<1.1	0.002	0.002	<0.002	<0.002	1.41	<0.1	2.0	19.7	0.3	76	4.5	6.84	
(IW)	11/2/2011	76		22	27	1.0	<1.0	1.6	1.7	<1.1	0.038	0.037	0.008	0.004	2.43	<0.1	2.2	10.9	0.1	-38	2030	5.72	
	5/6/2012	262	<1.0	<1.0	120	5.4	1.1	<1.0	<1.0	<1.0	0.052	0.048	0.012	<0.002	0.02		1.7	0.4	19.0	58	270	6.48	
BDC-05-10	11/15/2012	455	<1.0	<1.0	4.4	49	8.5	<1.0	<1.0	<1.0	0.069	0.060	0.003	<0.002	0.02		1.0	<0.3	24.0	-11	122	6.63	
BDC-05-10	5/22/2013	643	<0.2	<0.2	0.3	11	14	<3.0	<1.0	<1.0	0.056	0.053	0.										

**TABLE 1  
GROUNDWATER DATA SUMMARY  
BOEING DEVELOPMENTAL CENTER SWMU-17**

Well	Date	Pilot Injection Elapsed Time From Injection (days)	Full Injection #1 Elapsed Time From Injection (days)	Volatile Organic Compounds							Metals				Aquifer Redox Conditions					Donor Indicators		Comments																			
				PCE (µg/L)	TCE (µg/L)	cDCE (µg/L)	VC (µg/L)	Ethene (µg/L)	Ethane (µg/L)	Acetylene (µg/L)	As. Tot (mg/L)	As. Dis (mg/L)	Cu. Tot (mg/L)	Cu. Dis (mg/L)	DO (mg/L)	Nitrate (mg-N/L)	Iron II (mg/L)	Sulfate (mg/L)	Methane (mg/L)	ORP (mV)	TOC (mg/L)		pH																		
<b>Proposed Groundwater Cleanup Levels (a)</b>																						5.3	1.4	134	2.4	NA	NA	NA	0.008	0.008	0.008	0.008									
BDC-05-11 (IW)	7/31/2011	-18	16	19	5.8	<1.0	<1.1	<1.2	<1.1	0.005	0.005	<0.002	<0.002	1.41	<0.1	2.0	4.0	1.4	65	3.9	6.93																				
	11/2/2011	76	9.6	20	12	<1.0	<1.1	<1.2	<1.1	0.039	0.037	0.013	0.004	2.16	<0.1	1.8	<1.0	1.0	-38	1330	5.72																				
	5/6/2012	262	0.2	0.5	44	7.2	1.6	<1.0	<1.0	0.038	0.034	0.009	0.002	0.01		1.4	0.5	18.0	70	284	6.42																				
BDC-05-11	11/15/2012	455	<1.0	<1.0	6.1	5.7	7.6	<1.0	<1.0	0.043	0.038	0.003	<0.002	0.02		1.3	<0.3	26.0	-15	73.8	6.76																				
BDC-05-11	5/22/2013	643	<0.2	<0.2	0.3	2.9	16	3.7	<1.0	0.035	0.032	<0.002	<0.002	0.25		1.6	0.43	23.0	-299	42.1	7.71																				
BDC-05-11	11/13/2013	818	<0.2	<0.2	0.2	3.9	17	4.6	<1.0	0.038	0.035	0.002	<0.002	3.81		2.0	0.36	24.0	-264	48.4	6.5																				
BDC-05-11	5/13/2014	999	<0.2	<0.2	<0.2	2.0	9.0	7.2	<1.0	0.038	0.036	<0.002	<0.002	4.13		1.8	<0.30	24.0	-185	38.1	6.49																				
BDC-05-12 (IW)	7/31/2011	-18	15	18	16	<1.0	<1.1	<1.2	<1.1	0.002	0.002	0.002	<0.002	1.60	0.1	2.4	8.4	4.0	26	7.0	7.02																				
	11/2/2011	76	11	17	11	<1.0	<1.1	<1.2	<1.1	0.041	0.031	0.012	0.009	2.60	<0.1	3.5	5.6	1.0	-77	2960	5.83																				
	2/19/2012	185	<0.4	<0.4	53	1.8	<1.0	<1.0	<1.0					1.7	<0.5	2.0	<1.5	17.0	-2	279	6.59																				
BDC-05-12	5/6/2012	262	<0.2	<0.2	39	3.4	<1.0	<1.0	<1.0	0.082	0.071	0.005	<0.002	0.03		2.5	0.8	21.0	65	83.2	6.45																				
BDC-05-12	9/5/2012	384	<0.2	<0.2	6.5	3.3	1.0	<1.0	<1.0					0.13		1.8	<0.3	22.0	80	50.4	6.48																				
BDC-05-12	11/15/2012	455	<1.0	<1.0	7.9	5.4	1.1	<1.0	<1.0	0.037	0.036	0.002	<0.002	0.03		1.3	<0.3	27.0	7	52.9	6.56																				
BDC-05-12	2/25/2013	557	<1.0	<1.0	1.7	4.4	3.8	<1.0	<1.0					0.18		2.0	<0.3	26.0	54	27.5	6.68																				
BDC-05-12	5/22/2013	643	<0.2	<0.2	0.8	5.0	12	<3.0	<1.0	0.022	0.022	<0.002	<0.002	0.29		1.4	<0.3	24.0	-366	35.4	8.08																				
BDC-05-12	8/29/2013	742	<2.0	<2.0	<2.0	5.5	2.8	<1.0						5.25		1.6	<0.30	22.0	-320	32.6	6.53																				
BDC-05-12	11/13/2013	818	<2.0	<2.0	<2.0	2.2	3.4	<1.0		0.010	0.012	<0.002	<0.002	2.61		2.6	0.39	26.0	-268	26.9	6.66																				
BDC-05-12	2/11/2014	908	<1.0	<1.0	<1.0	1.1	<6.0	<1.0						4.83		2.2	0.37	23.0	-239	19.7	6.57																				
BDC-05-12	5/13/2014	999	<1.0	<1.0	<1.0	1.0	5.6	<1.0		0.007	0.006	<0.002	<0.002	3.01		2.0	0.49	25.0	-299	21.5	6.60																				
BDC-05-13 (IW)	7/31/2011	-18	5.2	6.6	2.6	<1.0	<1.1	<1.2	<1.1	0.003	0.002	0.002	<0.002	1.73	<0.1	2.0	2.3	5.0	-1	6.0	7.06																				
	11/1/2011	75	<1.0	1.2	39	<1.0	<1.1	<1.2	<1.1	0.068	0.064	0.017	0.003	1.82	<1.0	1.5	<1.0	2.2	-70	550	6.65																				
	5/6/2012	262	<0.2	<0.2	13	3.9	1.7	<1.0	<1.0	0.051	0.046	0.003	<0.002	0.03		3.0	0.4	19.0	78	34.2	6.40																				
BDC-05-13	11/15/2012	455	<1.0	<1.0	<1.0	2.3	3.7	<1.0	<1.0	0.060	0.055	<0.002	<0.002	0.04		2.2	<0.3	22.0	-9	30.2	6.75																				
BDC-05-13	5/22/2013	643	<0.2	<0.2	0.3	1.2	3.8	3.9	<1.0	0.019	0.019	<0.002	<0.002	0.29		1.8	0.43	23.0	-296	21.4	7.76																				
BDC-05-13	11/13/2013	818	<0.2	<0.2	0.3	2.1	3.6	6.4	<1.0	0.031	0.027	<0.002	<0.002	3.20		1.6	0.31	19.0	-241	24.7	6.59																				
BDC-05-13	5/12/2014	998	<0.2	<0.2	<0.2	2.6	4.3	6.8	<1.0	0.032	0.032	<0.002	<0.002	4.73		2.4	<0.30	19.0	-238	23.4	6.69																				
BDC-05-14 (IW)	7/31/2011	-18	2.8	6.8	2.8	<1.0	<1.1	<1.2	<1.1	0.004	0.004	0.004	<0.002	1.76	<0.1	2.0	10.1	6.5	-15	8.6	7.00																				
	11/1/2011	75	2.5	6.7	13	<1.0	<1.1	<1.2	<1.1	0.083	0.074	0.022	0.002	1.87	<1.0	2.3	<1.0	4.0	-124	725	6.13																				
	5/6/2012	262	<0.2	0.4	3.0	1.1	<1.0	<1.0	<1.0	0.012	0.009	<0.002	<0.002	0.08		1.7	0.6	23.0	99	41.5	6.33																				
BDC-05-14	11/15/2012	455	<0.2	<0.2	1.1	2.0	1.4	<1.0	<1.0	0.022	0.019	<0.002	<0.002	0.11		2.2	<0.3	24.0	-1.4	39.9	6.66																				
BDC-05-14	5/22/2013	643	<0.2	<0.2	0.2	1.3	1.3	<3.0	<1.0	0.012	0.012	<0.002	<0.002	0.40		1.8	<0.3	26.0	-311	26.3	7.69																				
BDC-05-14	11/13/2013	818	<0.2	<0.2	0.2	1.2	1.3	2.5	<1.0	0.017	0.015	<0.002	<0.002	3.80		1.5	<0.30	24.0	-219	29.5	6.44																				
BDC-05-14	5/12/2014	998	<0.2	<0.2	0.2	1.5	2.2	5.0	<1.0	0.018	0.021	<0.002	<0.002	5.21		2.0	<0.30	22.0	-233	30.2	6.55																				
BDC-05-15 (IW)	7/31/2011	-18	9.6	28	58	<1.0	<1.1	<1.2	<1.1	0.019	0.019	<0.002	<0.002	1.91	<0.1	1.3	18.6	3.1	-0.9	10.3	7.00																				
	11/1/2011	75	4.8	9.8	15	<1.0	<1.1	<1.2	<1.1	0.061	0.058	0.010	0.009	2.38	<0.1	3.0	11.3	3.5	-0.1	4420	5.67																				
	5/6/2012	262	<2.0	<2.0	49	6.3	<1.0	<1.0	<1.0	0.057	0.047	0.009	0.004	0.07		1.8	<0.3	21.0	93	423	6.36																				
BDC-05-15	11/15/2012	455	<1.0	<1.0	1.5	7.5	1.8	<1.0	<1.0	0.054	0.049	<0.002	<0.002	0.02		0.8	<0.3	27.0	8	71.2	6.61																				
BDC-05-15	5/22/2013	643	<0.2	<0.2	0.3	16	11	<3.0	<1.0	0.065	0.061	<0.002	<0.002	0.22		1.0	0.3	25.0	-317	42.9	7.82																				
BDC-05-15	11/13/2013	818	<0.2	<0.2	0.2	4.9	7.2	2.5	<1.0	0.066	0.059	<0.002	<0.002	2.11		2.6	<0.30	23.0	-265	45.5	6.60																				
BDC-05-15	5/13/2014	999	<0.2	<0.2	<0.2	8.6	9.4	<1.0	<1.0	0.065	0.061	<0.002	<0.002	2.92		1.7	<0.30	26.0	-230	37.5	6.69																				
BDC-05-16 (IW)	7/31/2011	-18	9.5	17	20	<1.0	<1.1	<1.2	<1.1	0.006	0.006	0.002	<0.002	1.91	<0.1	1.5	8.9	3.1	-8	7.8	7.06																				
	11/1/2011	75	2.6	2.8	37	<1.0	<1.1	<1.2	<1.1	0.079	0.074	0.005	0.002	2.30	<1.0	2.5	2.8	3.1	7	2250	5.51																				
	2/19/2012	185	<2.0	<2.0	46	7.4	<1.0	<1.0	<1.0					1.59	<0.5	2.2	<1.5	18.0	128	1270	5.12																				
BDC-05-16	5/6/2012	262	<0.2	0.3	6.7	24	2.5	<1.0	<1.0	0.042	0.039	0.003	<0.002	0.06		2.5	<0.3	25.0	121	207	6.28																				
BDC-05-16	9/5/2012	384	<0.4	<0.4	0.9	8.1	6.0	<1.0	<1.0					0.12		2.0	<0.3	22.0	64	40.6	6.67																				
BDC-05-16	11/15/2012	455	<1.0	<1.0	<1.0	4.9	4.0	<1.0	<1.0	0.041	0.037	<0.002	<0.002	0.02		1.0	<0.3	28.0	7	32.3	6.68																				
BDC-05-16	2/25/2013	557	<1.0	<1.0	<1.0	13	4.7	2.7	<1.0					0.41		2.0	<0.30	28.0	68	34.6	6.77																				
BDC-05-16	5/22/2013	643	<0.2	<0.2	0.2	7.7	3.9	<3.0	<1.0	0.043	0.048	<0.002	<0.002	0.19		1.0	0.38	26.0	-291	33.1	7.70																				
BDC-05-16	8/28/2013	741	<1.0	<1.0	<1.0	4.0	4.2	<3.0	<1.0					1.77		1.4	<0.30	26.0	-316	31.6	6.57																				
BDC-05-16	11/13/2013	818	<1.0	<1.0	<1.0	4.3	3.2	<1.0	<1.0	0.048	0.046	<0.002	<0.002	2.04		2.2	<0.30	24.0	-263	36.0	6.64																				
BDC-05-16	2/11/2014	908	<1.0	<1.0	<1.0	2.1	2.0	<7.0	<1.0					4.05		2.0	<0.30	25.0	-236	28.9	6.67																				
BDC-05-16	5/12/2014	998																																							

**TABLE 1  
GROUNDWATER DATA SUMMARY  
BOEING DEVELOPMENTAL CENTER SWMU-17**

Well	Date	Pilot Injection Elapsed Time From Injection (days)	Full Injection #1 Elapsed Time From Injection (days)	Volatile Organic Compounds							Metals				Aquifer Redox Conditions						Donor Indicators		Comments
				PCE (µg/L)	TCE (µg/L)	cDCE (µg/L)	VC (µg/L)	Ethene (µg/L)	Ethane (µg/L)	Acetylene (µg/L)	As, Tot (mg/L)	As, Dis (mg/L)	Cu, Tot (mg/L)	Cu, Dis (mg/L)	DO (mg/L)	Nitrate (mg-N/L)	Iron II (mg/L)	Sulfate (mg/L)	Methane (mg/L)	ORP (mV)	TOC (mg/L)	pH	
<b>Proposed Groundwater Cleanup Levels (a)</b>																							
				5.3	1.4	134	2.4	NA	NA	NA	0.008	0.008	0.008	0.008									
BDC-05-17 (IW)	7/31/2011		-18	11	22	34	<1.0	<1.1	<1.2	<1.1	0.004	0.004	0.003	0.002	2.03	0.6	1.5	16.0	0.30	59	10.2	6.95	
	11/1/2011		75	3.2	4.8	5.1	<1.0	<1.1	<1.2	<1.1	0.053	0.047	0.005	<0.002	2.61	<1.0	2.4	23.9	2.8	-50	3500	5.74	
	5/6/2012		262	<2.0	<2.0	9.3	5.6	<1.0	<1.0	<1.0	0.058	0.026	0.003	<0.002	0.24		2.0	0.7	15.0	182	839	6.08	
BDC-05-17	11/15/2012		455	<5.0	<5.0	<5.0	5.4	2.0	<1.0	<1.0	0.081	0.062	<0.002	<0.002	0.02		1.0	<0.3	23.0	13	73.5	6.62	
BDC-05-17	5/23/2013		644	<0.2	<0.2	0.7	5.1	4.3	<3.0	<1.0	0.142	0.062	<0.002	<0.002	0.44		1.2	<0.3	26.0	-259	45.8	7.54	
BDC-05-17	11/13/2013		818	<0.2	<0.2	0.5	4.0	3.0	2.2	<1.0	0.057	0.037	<0.002	<0.002	2.21		2.0	<0.30	26.0	-266	49.8	6.57	
BDC-05-17	5/12/2014		998	<0.2	<0.2	0.4	3.2	2.5	6.0	<1.0	0.038	0.033	<0.002	<0.002	4.60		1.8	<0.30	25.0	-368	44.1	6.64	
BDC-05-18 (MW 12 ft XG)	7/31/2011		-18	3.6	5.0	6.6	<1.0	<1.1	<1.2	<1.1	0.019	0.020	<0.002	<0.002	1.57	<0.1	2.4	4.5	3.9	-19	3.2	7.13	
	11/1/2011		75	2.8	4.0	7.6	<1.0	<1.1	<1.2	<1.1	0.019	0.020	0.003	0.003	1.37	<0.1	1.2	1.2	4.3	-106	21.7	6.88	
	2/19/2012		185	1.8	3.7	12	<0.2	<1.0	<1.0	<1.0					0.19	<0.5	2.2	<1.5	11.0	9	2.7	6.66	
BDC-05-18	5/6/2012		262	2.0	4.0	9.6	<0.2	<1.0	<1.0	<1.0	0.013	0.013	<0.002	<0.002	0.21		2.5	2.1	7.5	132	2.5	6.39	
BDC-05-18	9/5/2012		384	1.5	3.1	11	0.2	<1.0	<1.0	<1.0					0.13		1.5	2.0	7.9	58	1.8	6.91	
BDC-05-18	11/15/2012		455	1.0	4.3	16	<0.5	<1.0	<1.0	<1.0	0.015	0.014	<0.002	<0.002	0.48		1.4	2.4	8.3	25	1.7	6.62	
BDC-05-18	2/25/2013		557	2.0	4.6	5.7	<0.2	<1.0	<1.0	<1.0					0.25		2.0	9.2	1.3	72	2.0	6.53	
BDC-05-18	5/23/2013		644	3.1	5.2	4.1	<0.2	<1.0	<1.0	<1.0	0.014	0.014	<0.002	<0.002	0.30		1.5	7.0	1.0	-262	1.3	7.24	
BDC-05-18	8/28/2013		741	2.2	3.7	7.4	<0.2	<1.0	<1.0	<1.0					0.76		1.6	4.1	1.5	-309	2.2	6.25	
BDC-05-18	11/14/2013		819	1.2	1.8	1.4	0.2	<1.0	<1.0	<1.0	0.006	0.002	<0.002	<0.002	2.53		1.0	4.7	0.68	-164	<1.0	7.03	
BDC-05-18	2/11/2014		908	1.7	2.1	5.4	0.3	<1.0	<1.0	<1.0					2.53		1.2	3.2	3.70	-224	1.4	6.68	
BDC-05-18	5/13/2014		999	2.0	2.4	4.4	0.3	<1.0	<1.0	<1.0	0.001	0.002	<0.002	<0.002	3.54		1.5	6.7	3.2	-208	2.6	6.44	
BDC-05-19 (MW 10 ft DG)	7/31/2011		-18	15	21	23	<1.0	<1.1	<1.2	<1.1	0.002	0.001	0.002	<0.002	1.81	0.2	2.6	5.2	4.7	34	7.3	6.97	
	11/1/2011		75	9.1	13	36	4.1	<1.1	<1.2	<1.1	0.020	0.020	0.007	<0.002	1.53	<1.0	1.8	2.5	4.5	-142	170	6.82	
	2/19/2012		185	<1.0	1.7	68	14	1.4	<1.0	<1.0					0.85	<0.5	2.0	<1.5	22.0	36	296	6.40	
BDC-05-19	5/6/2012		262	0.7	1.4	52	23	1.8	<1.0	<1.0	0.058	0.052	0.032	0.008	0.02		2.0	1.4	25.0	69	244	6.39	
BDC-05-19	9/5/2012		384	<2.0	<2.0	13	15	3.9	<1.0	<1.0					0.19		1.8	1.4	19.0	73	68.0	6.43	
BDC-05-19	11/15/2012		455	<1.0	1.1	9.9	15	5.5	<1.0	<1.0	0.088	0.074	0.006	<0.002	0.21		1.6	1.8	24.0	3	68.1	6.58	
BDC-05-19	2/25/2013		557	<1.0	<1.0	6.9	20	6.5	<1.0	<1.0					0.25		2.0	0.31	23.0	71	53.0	6.64	
BDC-05-19	5/22/2013		643	<0.2	<0.2	5.1	9.6	7.2	<3.0	<1.0	0.054	0.051	0.006	<0.002	0.28		1.6	0.85	22.0	-385	52.4	8.12	
BDC-05-19	8/28/2013		741	<2.0	<2.0	6.9	7.3	7.3	2.5	<1.0					1.53		2.0	0.52	22.0	-318	60.6	6.54	
BDC-05-19	11/13/2013		818	<2.0	<2.0	2.3	3.1	4.1	3.0	<1.0	0.046	0.040	0.003	<0.002	3.93		1.4	0.52	26.0	-270	57.7	6.54	
BDC-05-19	2/11/2014		908	<1.0	<1.0	<1.0	2.0	2.5	5.7	<1.0					5.69		2.0	0.39	23.0	-239	64.8	6.51	
BDC-05-19	5/13/2014		999	<1.0	<1.0	<1.0	1.8	2.0	5.9	<1.0	0.033	0.025	0.003	<0.002	2.51		2.2	0.37	26.0	-306	54.9	6.56	
BDC-05-20 (MW 31 ft DG)	7/31/2011		-18	<1.0	7.0	45	<1.0	<1.1	<1.2	<1.1	0.011	0.011	<0.002	<0.002	2.33	<0.1	1.5	7.4	0.2	-42	10.8	7.12	
	11/3/2011		77	<1.0	5.7	25	1.0	<1.1	<1.2	<1.1	0.010	0.011	<0.002	<0.002	1.54	<0.1	1.0	6.0	4.6	11	8.3	7.14	
	2/19/2012		185	<0.2	2.9	17	2.5	<1.0	<1.0	<1.0					0.35	<0.5	1.5	<1.5	16.0	31	8.2	6.69	
BDC-05-20	5/7/2012		263	<0.2	1.8	14	2.2	<1.0	<1.0	<1.0	0.011	0.011	<0.002	<0.002	0.69		1.8	2.3	20.0	20	11.1	6.66	
BDC-05-20	9/5/2012		384	<0.4	<0.4	12	2.0	<1.0	<1.0	<1.0					0.08		1.4	<0.3	14.0	67	12.1	6.75	
BDC-05-20	11/16/2012		456	<0.5	0.6	17	3.5	<1.0	<1.0	<1.0	0.012	0.013	<0.002	<0.002	0.07		2.0	<0.3	18.0	0.9	13.1	6.88	
BDC-05-20	2/26/2013		558	<0.2	0.5	9.8	6.1	<1.0	<1.0	<1.0					0.16		1.5	<0.3	22.0	16	16.3	6.86	
BDC-05-20	5/23/2013		644	<0.2	0.4	10	8.1	1.5	<1.0	<1.0	0.016	0.017	<0.002	<0.002	0.25		1.2	<0.3	25.0	-233	16.9	7.55	
BDC-05-20	8/28/2013		741	<0.2	0.2	6.5	10	2.1	<1.0	<1.0					2.38		2.6	<0.30	20.0	-317	15.4	6.70	
BDC-05-20	11/14/2013		819	<0.2	0.3	8.1	8.8	2.2	<1.0	<1.0	0.021	0.021	<0.002	<0.002	2.26		1.4	<0.30	19.0	-287	17.9	6.77	
BDC-05-20	2/12/2014		909	<0.2	0.2	3.9	7.8	3.0	<4.0	<1.0					2.82		1.8	<0.30	16.0	-205	16.3	6.78	
BDC-05-20	5/13/2014		999	<0.2	<0.2	3.8	6.3	2.0	<1.0	<1.0	0.017	0.017	<0.002	<0.002	3.44		1.6	0.36	16.0	-213	18.7	6.79	
BDC-05-21 (MW 30 ft XG)	7/31/2011		-18	<1.0	<1.0	1.3	14	2.6	<1.2	<1.1	0.006	0.006	<0.002	<0.002	2.98	<0.1	3.2	0.2	5.6	-31	6.4	7.33	
	11/3/2011		77	<1.0	<1.0	1.0	4.7				0.005	0.005	<0.002	<0.002	1.95	<0.1	1.4	6.3		-12	5.2	7.29	
	2/19/2012		185	<0.2	0.3	0.7	5.9								0.40	<0.5	1.4	<1.5		47	7.2	6.65	
BDC-05-21	5/7/2012		263	<0.2	0.4	0.8	2.5				0.010	0.011	0.005	<0.002	0.86		1.5	1.9		-35	12.3	6.76	
BDC-05-21	9/5/2012		384	<0.2	0.3	0.6	2.9								0.08		2.5	1.4		62	9.5	6.78	
BDC-05-21	11/16/2012		456	<0.5	<0.5	0.6	2.9				0.020	0.020	<0.002	<0.002	0.02		1.5	0.6		-4	8.9	6.92	
BDC-05-21	2/26/2013		558	<0.2	0.3	0.8	3.3	<1.0	<1.0	<1.0					0.24		1.4	<0.3	18.0	-2.6	8.7	7.03	
BDC-05-21	5/23/2013		644	<0.2	0.3	0.9	6.5				0.024	0.022	<0.002	<0.002	0.19		1.5	<0.3		-235	8.2	7.50	
BDC-05-21	8/28/2013		741	<0.2	0.2	0.8	7.7	6.2	1.8	<1.0			</										

**TABLE 1  
GROUNDWATER DATA SUMMARY  
BOEING DEVELOPMENTAL CENTER SWMU-17**

Well	Date	Pilot Injection Elapsed Time From Injection (days)	Full Injection #1 Elapsed Time From Injection (days)	Volatile Organic Compounds						Metals				Aquifer Redox Conditions					Donor Indicators		Comments																		
				PCE (µg/L)	TCE (µg/L)	cDCE (µg/L)	VC (µg/L)	Ethene (µg/L)	Ethane (µg/L)	Acetylene (µg/L)	As, Tot (mg/L)	As, Dis (mg/L)	Cu, Tot (mg/L)	Cu, Dis (mg/L)	DO (mg/L)	Nitrate (mg-N/L)	Iron II (mg/L)	Sulfate (mg/L)	Methane (mg/L)	ORP (mV)		TOC (mg/L)	pH																
<b>Proposed Groundwater Cleanup Levels (a)</b>																				5.3	1.4	134	2.4	NA	NA	NA	0.008	0.008	0.008	0.008									
BDC-05-22	7/31/2011		-18	<1.0	1.1	9.6	1.0	<1.1	<1.2	<1.1	0.025	0.024	<0.002	<0.002	2.02	<0.1	2.2	14.0	5.1	-59	7.9	7.21																	
(MW 48 ft XG)	11/3/2011		77	<1.0	2.1	10	<1.0				0.020	0.020	<0.002	<0.002	1.46	<0.1	0.8	18.1		19	6.1	7.08																	
	2/19/2012		185	<0.2	2.0	13	0.4							0.43	<0.5	1.2	17.0		110	6.2	6.73																		
BDC-05-22	5/7/2012		263	<0.2	2.0	11	0.5				0.025	0.023	0.002	<0.002	0.81		1.6	19.4		32	8.4	6.68																	
BDC-05-22	9/5/2012		384	<0.2	1.8	9.5	0.8							0.06		2.2	14.7		75	7.6	6.71																		
BDC-05-22	11/16/2012		456	<0.5	1.6	10	0.7				0.033	0.031	<0.002	<0.002	0.02		0.8	17.8		5	7.7	6.93																	
BDC-05-22	2/26/2013		558	<0.2	1.3	9.4	1.2							0.09		1.6	10.1		23	7.5	6.92																		
BDC-05-22	5/23/2013		644	<0.2	1.2	10	0.6				0.029	0.029	<0.002	<0.002	0.25		1.4	6.3		-233	8.7	7.63																	
BDC-05-22	8/28/2013		741	<0.2	1.2	7.3	0.2							0.65			3.5		-322	8.9	6.69																		
BDC-05-22	11/14/2013		819	<0.2	1.2	6.9	<0.2				0.028	0.027	<0.002	<0.002	1.96		1.5	5.9		-240	8.8	6.74																	
BDC-05-22	2/12/2014		909	<0.2	0.7	5.7	<0.2							2.67		2.0	4.9		-224	7.3	6.88																		
BDC-05-22	5/13/2014		999	<0.2	1.4	6.7	<0.2				0.027	0.025	<0.002	<0.002	3.16		1.5	8.7		-183	8.4	6.68																	
BDC-05-23	7/31/2011		-18	<1.0	<1.0	3.2	<1.0	<1.1	<1.2	<1.1	0.005	0.005	0.002	<0.002	2.72	<0.1	2.2	8.6	6.0	-101	9.1	7.47																	
(MW 170ft DG)	11/3/2011		77	<1.0	<1.0	4.8	<1.0				0.005	0.006	<0.002	<0.002	1.45	<0.1	1.0	25.2		1	8.8	7.08																	
	2/19/2012		185	<0.2	0.6	4.7	0.7							0.96	<0.5	1.2	8.9		162	8.1	6.33																		
BDC-05-23	5/7/2012		263	<0.2	0.7	5.4	0.8				0.008	0.008	<0.002	<0.002	0.07		2.0	15.8		45	9.3	6.70																	
BDC-05-23	9/5/2012		384	<0.2	0.7	6.2	0.9							0.08		1.9	8.8		78	11.3	6.84																		
BDC-05-23	11/16/2012		456	<0.5	0.8	6.9	0.5				0.012	0.010	<0.002	<0.002	0.09		1.0	4.9		-6	11.6	7.06																	
BDC-05-23	2/25/2013		557	<0.2	0.5	4.2	1.0							0.08		1.5	0.87		72	9.2	6.91																		
BDC-05-23	5/23/2013		644	<0.2	0.5	4.7	1.0				0.015	0.015	<0.002	<0.002	0.31		1.2	1.7		-234	11.0	7.59																	
BDC-05-23	8/28/2013		741	<1.0	2.2	2.1	5.4							0.60		0.5	0.35		-323	10.4	6.76																		
BDC-05-23	11/14/2013		819	<0.2	0.3	3.0	0.9				0.017	0.015	<0.002	<0.002	1.58		1.3	0.62		-252	11.1	6.87																	
BDC-05-23	2/12/2014		909	<0.2	0.2	2.7	1.2							2.40		1.8	0.74		-229	9.3	6.86																		
BDC-05-23	5/13/2014		999	<0.2	0.3	4.5	1.0				0.023	0.023	<0.002	<0.002	3.15		1.4	3.1		-207	12.1	6.97																	
BDC-05-24	7/31/2011		-18	<1.0	<1.0	1.6	1.6	<1.1	<1.2	<1.1	0.003	0.003	<0.002	<0.002	1.67	<0.1	2.0	1.1	7.6	-7	10.0	7.06																	
(MW 18 ft XG)	11/1/2011		75	<1.0	2.0	4.0	2.2				0.002	0.002	<0.002	<0.002	1.50	<0.1	1.6	0.3		-2.6	8.1	7.06																	
	2/19/2012		185	<0.2	0.2	0.7	0.8							0.31	<0.5	1.8	<1.5		63	9.8	6.55																		
BDC-05-24	5/8/2012		262	<0.2	1.3	2.8	1.0				0.006	0.004	<0.002	<0.002	0.03			0.9		73	9.1	6.60																	
BDC-05-24	9/5/2012		384	<0.2	1.2	4.0	0.9							0.08		2.0	<0.3		67	7.4	6.67																		
BDC-05-24	11/15/2012		455	<0.5	<0.5	1.2	<0.5				0.002	0.003	<0.002	<0.002	0.13		1.0	<0.3		-1.7	10.7	6.94																	
BDC-05-24	2/25/2013		557	<0.2	0.7	5.1	1.9	1.1	<1.2	<1.0				0.10		1.5	1.1	9.1		87	7.2	6.72																	
BDC-05-24	5/22/2013		643	<0.2	0.8	7.6	2.1				0.004	0.003	<0.002	<0.002	0.58		1.4	0.82		-272	7.4	7.54																	
BDC-05-24	8/28/2013		741	<0.2	0.5	4.4	1.6	<1.0	1.8	<1.0				0.78		1.4	0.47	11.0		-321	8.6	6.57																	
BDC-05-24	11/13/2013		818	<0.2	0.4	3.3	1.4	<1.0	1.4	<1.0	0.003	0.003	<0.002	<0.002	2.43		1.3	1.4	11.0	-219	8.7	6.54																	
BDC-05-24	2/12/2014		909	<0.2	0.2	1.7	0.6	1.1	3.0	<1.0				2.72		2.0	0.81	11.0		-211	7.1	6.76																	
BDC-05-24	5/12/2014		998	<0.2	0.3	4.8	1.6	1.0	2.3	<1.0	0.003	0.002	<0.002	<0.002	2.58		1.2	0.87	10.0	-196	8.2	6.75																	
PCE = Tetrachloroethene		Dis = Dissolved		IW = Injection Well																																			
TCE = Trichloroethene		DO = Dissolved Oxygen		MW = Monitoring Well																																			
cDCE = cis-1,2-Dichloroethene		ORP = Oxidation Reduction Potential		DG = Downgradient; distance from nearest injection well																																			
VC = Vinyl Chloride		TOC = Total Organic Carbon		UG = Upgradient; distance from nearest injection well																																			
As = Arsenic		NA = Not Applicable, not available		XG = Crossgradient; distance from nearest injection well																																			
Cu = Copper		µg/L = micrograms pr liter		not analyzed																																			
Tot = Total		mg/L = milligrams per liter		Box = Exceedance of Proposed Cleanup Level																																			
<b>(a) Proposed Cleanup Standards and Comparison to Site Data, Boeing Developmental Center, Tukwila, Washington (Landau Associates, 5/7/13).</b>																																							
Injection Dates:																																							
10/28/2008	Pilot Injection: BDC-05-02 only																																						
8/18/2011	Full Injection #1: BDC-05-02, BDC-05-07, and BDC-05-09 through BDC-05-17; performed 8/15/11-8/18/11																																						




LANDAU ASSOCIATES, INC. | G:\cad\025\093\112.012\May 2012 Semiannual Report\Figure 7.dwg (A) Figure 7 9/29/2014



- Legend**
- New Monitoring Well
  - Existing Monitoring Well
  - New Injection Wells
  - Existing Injection Wells
  - Abandoned Monitoring Well
  - Catch Basin
  - Manhole
  - SS — SS — Sanitary Sewer Utility
  - SD — SD — Storm Drain Utility
  - E — E — Electrical Utility
  - V — V — Water Utility
  - X — X — Existing Fence
  - 20 — Baseline Concentration Contours for PCE and/or TCE (µg/L)
  - ← Groundwater Flow Direction (May 2009)
  - SWMU-17 Solid Waste Management Unit

**Note**

- Black and white reproduction of this color original may reduce its effectiveness and lead to incorrect interpretation.



***DEVELOPMENTAL CENTER  
GROUNDWATER MONITORING  
MAY 2014***

**AOC-05 DATA**

- **AOC-05 Cleanup Action Summary**
- **AOC-05 Downgradient Monitoring**
- **AOC-05 TPH-G, BTEX, and Nitrate Concentration Trend Charts  
(June 2001 through Present)**
- **Site Plan**



**AOC-05 CLEANUP ACTION SUMMARY  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING**

Well	Date	ORC	Pilot	Full Scale	Full Scale	Full Scale	Full Scale	Full Scale	Full Scale	Full Scale	Full Scale	Full Scale	Volatile Organic Compounds (all units in ug/L)						Aquifer Redox Conditions						Donor Indicators									
		Injection	Injection	Injection 1	Injection 2	Injection 3	Injection 4	Injection 5	Injection 6	Injection 7	Injection 8	Injection 9	TPH-G	Benzene	Toluene	Ethylbenzene	m,p-Xylene	o-Xylene	Total Xylenes	DO	Nitrate	Nitrite	Iron II	Sulfate	Methane	ORP	TOC	pH						
		Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	(mg/L)	(ug/L)	(ug/L)	(ug/L)	(ug/L)	(ug/L)	(ug/L)	(mg/L)	(mg-N/L)	(mg-N/L)	(mg/L)	(mg/L)	(ug/L)	(mV)	(mg/L)							
Proposed Groundwater Cleanup Levels (a)													0.8	2.0	1294	1.7	NA	NA	1546															
BDC-101	6/11/2001												3.0	11.9	<1.0	113.1			109.2															
BDC-101	9/4/2001												5.0	7.13	10.7	50.4			53.8															
BDC-101	12/3/2001												6.5	95	1.6	750			650															
BDC-101	3/13/2002												<0.25	1.4	<1.0	4.4			<1.0															
BDC-101	4/29/2002	-8											<0.25	<1.0	<1.0	2.2	<1.0	<1.0	<1.0															
BDC-101	6/3/2002	27											<0.25	1.0	<1.0	<1.0	<1.0	<1.0	<1.0															
BDC-101	7/1/2002	55											<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0															
BDC-101	8/1/2002	86											<0.25	3.1	<1.0	2.4	<1.0	<1.0	<1.0															
BDC-101	12/2/2002	209											0.61	4.3	<1.0	21	27	6.4	33.4															
BDC-101	3/10/2003	307											<0.25	1.0	<1.0	4.5	3.2	<1.0	<1.0															
BDC-101	6/3/2003	392											<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0															
BDC-101	11/19/2003	561											0.42	13	<1.0	15	35	<1.0	35	0.36	1.1	0.010	0.2	16	240	120.3								
BDC-101	4/28/2004	722											<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0															
BDC-101	10/18/2004	895											0.64	10	<1.0	15	43	<1.0	43															
BDC-101	5/10/2005	1099											<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0															
BDC-101	11/10/2005	1283											0.25	7.6	<1.0	2.6	42	<1.0	42	0.96	4.4			34.3		259	2.05							
BDC-101	5/15/2006	1469											<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	2.78	17.8	0.059	0.0	64.1		80								
BDC-101	11/20/2006	1658	-59										1.1	10	<1.0	15	72.0	<1.0	72	0.92	0.122	0.016	2.4	8.7		174								
BDC-101	2/20/2007	1750	33										<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	2.39	15.0	0.047	0.2	50.0		277		6.63						
BDC-101	3/19/2007	1777	60										<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	5.97	8.83	0.037	0.5	38.5		213		6.60						
BDC-101	4/24/2007	1813	96										<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	3.09	9.59	0.041	0.5	34.1		136		6.46						
BDC-101	5/17/2007	1836	119										<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	2.35	9.95	0.046	0.4	35.7		297		6.55						
BDC-101	11/26/2007	2029	312										<0.25	<1.0	<1.0	2.1	6.5	<1.0	6.5	2.30	5.88	0.032	0.0	26.8		287								
BDC-101	2/18/2008	2113	396	-8									<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	3.55	8.10	0.040	0.0	31.5		341		6.29						
BDC-101	3/27/2008	2151	434	30									<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	3.19	9.3	<0.10	0.2	40.0		506								
BDC-101	5/15/2008	2200	483	79	-40								<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	2.57	6.8	<0.10	0.0	24.6		176		6.44						
BDC-101	7/16/2008	2262	545	141	22								<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	3.34	5.3	<0.10	0.0	21.8		-232		6.52						
BDC-101	9/15/2008	2323	606	202	83	-45							<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.22	5.33	0.023	0.0	28.7		153								
BDC-101	11/20/2008	2389	672	268	149	21							0.44	1.6	<1.0	<1.0	<1.0	<1.0	<1.0	1.45	2.9	0.1	0.8	17.1		-22		6.65						
BDC-101	1/16/2009	2446	729	325	206	78							<0.25	1.1	<1.0	<1.0	<1.0	<1.0	<1.0	0	4.40	0.042	0.4	29.5		-245		6.50						
BDC-101	2/11/2009	2472	755	351	232	104							<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	2.62	8.5	<0.1	0.4	39.6		-16		6.43						
BDC-101	3/9/2009	2498	781	377	258	130							<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	0.93	9.4	<0.1	0.0	46.8		54		6.54						
BDC-101	4/16/2009	2536	819	415	296	168							<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.69	9.0	<0.1	0.0	36.0		131		6.61						
BDC-101	5/14/2009	2564	847	443	324	196	-34						<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.00	13.0	<0.1	0.0	44.4		68		6.81						
BDC-101	7/17/2009	2628	911	507	388	260	30						<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	2.80	12.6	<0.1	0.0	49.0		19		7.17						
BDC-101	9/9/2009	2682	965	561	442	314	84	-49					<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.25	6.2	<0.1	0.0	31.7		179		6.90						
BDC-101	11/12/2009	2746	1029	625	506	378	148	15					0.35	1.8	<1.0	6.6	16	<1.0	16	1.37	11.3	<0.1	0-0.2	36.7		124		6.53						
BDC-101	2/17/2010	2843	1126	722	603	475	245	112					<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	2.86	13.9	<0.1	0.0	48.7		640		6.55						
BDC-101	5/17/2010	2932	1215	811	692	564	334	201					<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	3.20	20.7	<0.1	0.0	58.7		372		6.86						
BDC-101	8/16/2010	3023	1306	902	783	655	425	292	-37				<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	2.21	15.6	<0.1	0.0	56.9		76		7.21						
BDC-101	11/8/2010	3107	1390	986	867	739	509	376	47				<0.25	2.0	<1.0	<1.0	<1.0	<1.0	<1.0	2.02	2.2	<0.1	0.4	14.7		145		6.97						
BDC-101	2/16/2011	3207	1490	1086	967	839	609	476	147				<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	7.46	23.9	<0.1	0.0	68.2		161		7.30						
BDC-101	5/3/2011	3283	1566	1162	1043	915	685	552	223				<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	5.57	23.7	<0.1	0.0	66.2		208		6.99						
BDC-101	8/1/2011	3373	1656	1252	1133	1005	775	642	313				<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	5.50	17.9	<0.1	0.0	48.1		150		7.07						
BDC-101	11/1/2011	3465	1748	1344	1225	1097	867	734	405	-105			<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	6.69	6.1	<0.1	0.0	24.8		40		7.23						
BDC-101	2/19/2012	3575	1858	1454	1335	1207	977	844	515	5			<0.25	2.0	<1.0	<1.0	<2.0	<1.0	<2.0	0.53	6.6		0.3	27.7		12		6.81						
BDC-101	5/3/2012	3649	1932	1528	1409	1281	1051	918	589	79			<0.25	<1.0	<1.0	<1.0	<2.0	<1.0	<2.0	3.75	15.9		0.0	51.2		263		6.60						
BDC-101	9/4/2012	3773	2056	1652	1533	1405	1175	1042	713	203	-49		<0.25	<1.0	<1.0	<1.0	<2.0	<1.0	<2.0	0.88	13.8	<0.10	0.0	36.0		154		6.97						
BDC-101	11/13/2012	3843	2126	1722	1603	1475	1245	1112	783	273	21		<0.25	<1.0	<1.0	<1.0	<2.0	<1.0	<2.0	0.41	10.3	<0.10	0.0	40.4		150		6.90						
BDC-101	2/20/2013	3942	2225	1821	1702	1574	1344	1211	882	372	120		<0.25	<1.0	<1.0	<1.0	<2.0	<1.0	<2.0	2.55	21.3	<0.10	0.2	68.0		73		6.83						
BDC-101	5/20/2013	4031	2314	1910	1791	1663	1433	1300	971	461	209		<0.25	<1.0	<1.0	<1.0	<2.0	<1.0	<2.0	3.35	17	<0.10	0.0	52.9		-190		6.72						
BDC-101	8/28/2013	4131	2414	2010	1891	1763	1533	1400	1071	561	309	-76	<0.25	<1.0	<1.0	<1.0	<2.0	<1.0	<2.0	1.99	10.5	<0.10	0.0	41.5		-277		6.46						
BDC-101	11/19/2013</																																	

**AOC-05 CLEANUP ACTION SUMMARY  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING**

Well	Date	ORC	Pilot	Full Scale	Full Scale	Full Scale	Full Scale	Full Scale	Full Scale	Full Scale	Full Scale	Full Scale	Volatile Organic Compounds (all units in ug/L)						Aquifer Redox Conditions						Donor Indicators								
		Injection	Injection	Injection 1	Injection 2	Injection 3	Injection 4	Injection 5	Injection 6	Injection 7	Injection 8	Injection 9	TPH-G	Benzene	Toluene	Ethylbenzene	m,p-Xylene	o-Xylene	Total Xylenes	DO	Nitrate	Nitrite	Iron II	Sulfate	Methane	ORP	TOC	pH					
		Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	(mg/L)	(ug/L)	(ug/L)	(ug/L)	(ug/L)	(ug/L)	(ug/L)	(mg/L)	(mg-N/L)	(mg-N/L)	(mg/L)	(mg/L)	(ug/L)	(mV)	(mg/L)						
Proposed Groundwater Cleanup Levels (a)													0.8	2.0	1294	1.7	NA	NA	1546														
BDC-102	6/11/2001												0.55	5.33	<1.0	<1.0		<1.0															
BDC-102	9/4/2001												0.38	1.61	1.89	<1.0		1.87															
BDC-102	12/3/2001												1.6	3.7	<1.0	<1.0		3.49															
BDC-102	3/13/2002												0.50	1.3	<1.0	<1.0		<1.0															
BDC-102	4/29/2002	-8											0.33	2.6	<1.0	<1.0	1.1	<1.0	1.1														
BDC-102	6/3/2002	27											<0.25	4.4	<1.0	<1.0	<1.0	<1.0	<1.0														
BDC-102	7/1/2002	55											0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0														
BDC-102	8/1/2002	86											<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0														
BDC-102	12/2/2002	209											<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0														
BDC-102	3/10/2003	307											0.26	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0														
BDC-102	6/3/2003	392											<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0														
BDC-102	11/19/2003	561											0.99	120	<1.0	8.5	<1.0	<1.0	<1.0	0.38	0.19	0.011	5.5	46	1100	122.2							
BDC-102	4/28/2004	722											0.40	10	<1.0	<1.0	3.0	<1.0	3.0														
BDC-102	10/18/2004	895											0.33	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0														
BDC-102	5/10/2005	1099											<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0														
BDC-102	11/10/2005	1283											<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	0.82	4.4		34.0		122	18.4							
BDC-102	5/15/2006	1469											<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	2.21	4.72	0.175	2.2	35.7		-11							
BDC-102	11/20/2006	1658	-59										<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.25	<0.250	<0.250	2.2	9.2		163							
BDC-102	2/20/2007	1750	33										<0.25	5.8	<1.0	<1.0	<1.0	<1.0	<1.0	0.47	0.749	0.027	3.0	25.3		-145	6.54						
BDC-102	3/19/2007	1777	60										<0.25	18	<1.0	<1.0	32	<1.0	32	0.88	0.938	0.072	3.0	31.0		-98	6.67						
BDC-102	4/24/2007	1813	96										0.53	6.1	<1.0	3.1	100	<1.0	100	1.20	1.94	0.051	2.8	40.4		-93	6.51						
BDC-102	5/17/2007	1836	119										<0.25	1.8	<1.0	<1.0	7.4	<1.0	7.4	0.84	2.78	0.108	2.6	33.9		-286	6.52						
BDC-102	11/26/2007	2029	312										<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	3.29	1.03	0.247	3.0	55.7		46							
BDC-102	2/18/2008	2113	396	-8									<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	2.51	3.91	0.054	2.8	42.8		431	5.97						
BDC-102	3/27/2008	2151	434	30									<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.85	1.3	<0.10	2.5	17.9		233							
BDC-102	5/15/2008	2200	483	79	-40								<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	2.40	3.0	<0.10	3.5	19.2		-115	6.56						
BDC-102	7/16/2008	2262	545	141	22								<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	2.46	2.5	<0.10	3.2	13.7		-312	6.67						
BDC-102	9/15/2008	2323	606	202	83	-45							<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.22	4.28	0.056	3.0	31.6		191							
BDC-102	11/20/2008	2389	672	268	149	21							<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	0.70	0.40	<0.10	2.0	5.6		-70	6.69						
BDC-102	1/16/2009	2446	729	325	206	78							<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	0.00	<0.100	0.200	2.5	8.3		-235	6.70						
BDC-102	2/11/2009	2472	755	351	232	104							<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.65	2.4	<0.1	3.0	20.4		-70	6.61						
BDC-102	3/9/2009	2498	781	377	258	130							<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	0.00	0.9	<0.1	3.0	8.7		-46	6.65						
BDC-102	4/16/2009	2536	819	415	296	168							<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	0.30	0.6	<0.1	3.0	8.3		-7	6.66						
BDC-102	5/14/2009	2564	847	443	324	196	-34						<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	0.29	0.9	<0.1	3.4	9.8		-35	6.78						
BDC-102	7/17/2009	2628	911	507	388	260	30						<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	0.66	4.9	<0.1	2.2	28.6		-11	6.46						
BDC-102	9/9/2009	2682	965	561	442	314	84	-49					<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	0.91	0.4	<0.1	2.7	5.5		2.8	6.66						
BDC-102	11/12/2009	2746	1029	625	506	378	148	15					<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	0.93	0.2	<0.1	3.2	2.4		-42.0	6.49						
BDC-102	2/17/2010	2843	1126	722	603	475	245	112					<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	0.90	3.4	0.2	2.8	17.2		892	6.56						
BDC-102	5/17/2010	2932	1215	811	692	564	334	201					<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.35	8.4	<1.0	3.0	30.1		440	6.61						
BDC-102	8/16/2010	3023	1306	902	783	655	425	292	-37				<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.61	8.9	<0.1	3.0	27.8		82	6.60						
BDC-102	11/8/2010	3107	1390	986	867	739	509	376	47				<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	2.34	0.4	<0.1	2.0	6.9		45	7.09						
BDC-102	2/16/2011	3207	1490	1086	967	839	609	476	147				<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	3.68	3.5	<0.1	2.2	43.3		399	6.88						
BDC-102	5/3/2011	3283	1566	1162	1043	915	685	552	223				<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	1.60	12.1	<0.1	2.0	32.4		40	6.70						
BDC-102	8/1/2011	3373	1656	1252	1133	1005	775	642	313				<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	7.01	13.6	<0.1	2.1	28.7		11	6.88						
BDC-102	11/1/2011	3465	1748	1344	1225	1097	867	734	405	-105			<0.25	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	3.45	9.8	<0.1	1.5	30.9		-48	7.19						
BDC-102	2/19/2012	3575	1858	1454	1335	1207	977	844	515	5			<0.25	<1.0	<1.0	<1.0	<2.0	<1.0	<2.0	0.25	2.4		1.0	15.4		21	6.60						
BDC-102	5/3/2012	3649	1932	1528	1409	1281	1051	918	589	79			<0.25	<1.0	<1.0	<1.0	<2.0	<1.0	<2.0	0.22	11.3		2.5	40.2		248	6.44						
BDC-102	9/4/2012	3773	2056	1652	1533	1405	1175	1042	713	203	-49		<0.25	<1.0	<1.0	<1.0	<2.0	<1.0	<2.0	0.20	13.2	<5.0	1.5	39.2		130	6.63						
BDC-102	11/13/2012	3843	2126	1722	1603	1475	1245	1112	783	273	21		<0.25	<1.0	<1.0	<1.0	<2.0	<1.0	<2.0	0.10	1.7	<0.10	1.6	27.7		48	6.77						
BDC-102	2/20/2013	3942	2225	1821	1702	1574	1344	1211	882	372	120		<0.25	<1.0	<1.0	<1.0	<2.0	<1.0	<2.0	0.17	18.4	<0.10	1.0	58.5		92	6.60						
BDC-102	5/20/2013	4031	2314	1910	1791	1663	1433	1300	971	461	209		<0.25	<1.0	<1.0	<1.0	<2.0	<1.0	<2.0	0.49	20	<0.10	1.5	62.2		-280	7.31						
BDC-102	8/28/2013	4131	2414	2010	1891	1763	1533	1400	1071	561	309	-76	<0.25	<1.0	<1.0	<1.0	<2.0	<1.0	<2.0	1.93	12.2	<0.10	1.0	39.1		-341	6.45						
BDC-102	11/19/2013	4214	2497	2093	1974	1846	1616	1483	1154	644	392	7	<0.25																				

**AOC-05 CLEANUP ACTION SUMMARY  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING**

Well	Date	ORC	Pilot	Full Scale	Full Scale	Full Scale	Full Scale	Full Scale	Full Scale	Full Scale	Full Scale	Full Scale	Volatile Organic Compounds (all units in ug/L)						Aquifer Redox Conditions						Donor Indicators																
		Injection	Injection	Injection 1	Injection 2	Injection 3	Injection 4	Injection 5	Injection 6	Injection 7	Injection 8	Injection 9	TPH-G	Benzene	Toluene	Ethylbenzene	m,p-Xylene	o-Xylene	Total Xylenes	DO	Nitrate	Nitrite	Iron II	Sulfate	Methane	ORP	TOC	pH													
		Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	Elapsed Time from Injection (days)	(mg/L)	(ug/L)	(ug/L)	(ug/L)	(ug/L)	(ug/L)	(ug/L)	(mg/L)	(mg-N/L)	(mg-N/L)	(mg/L)	(mg/L)	(ug/L)	(mV)	(mg/L)														
<b>Proposed Groundwater Cleanup Levels (a)</b>													<b>0.8</b>	<b>2.0</b>	<b>1294</b>	<b>1.7</b>	<b>NA</b>	<b>NA</b>	<b>1546</b>																						
BDC-103	6/11/2001												177	875	12,010	1,985			11,430																						
BDC-103	9/4/2001												123	494	3,760	419			2,636																						
BDC-103 (b)	12/3/2001												120	5,100	2,300,000	10,000			3,400,000																						
BDC-103	3/13/2002												200	1,700	17,000	4,900			26,400																						
BDC-103	4/29/2002	-8											200	980	16,000	5,400	20,000	7,000	27,000																						
BDC-103	6/3/2002	27											200	960	17,000	5,100	20,000	7,100	27,100																						
BDC-103	7/1/2002	55											240	1,300	16,000	5,200	20,000	6,800	26,800																						
BDC-103	8/1/2002	86											270	4,600	18,000	5,200	19,000	6,600	25,600																						
BDC-103	12/2/2002	209											250	1,400	15,000	5,000	22,000	6,900	28,900																						
BDC-103	3/10/2003	307											180	780	13,000	5,200	20,000	6,700	26,700																						
BDC-103	6/3/2003	392											220	900	10,000	5,000	20,000	6,600	26,600																						
BDC-103	11/19/2003	561											180	850	8,300	4,500	18,000	5,500	23,500	0.38	0.012	0.011	5.5	53	630	-75.9															
BDC-103	4/28/2004	722											160	1,600	6,600	3,900	16,000	5,100	21,100																						
BDC-103	10/18/2004	895											140	2,100	5,500	3,700	15,000	4,400	19,400																						
BDC-103	5/10/2005	1099											110	2,200	5,500	3,800	14,000	3,200	17,200																						
BDC-103	11/10/2005	1283											90	2,200	3,500	3,700	12,000	2,500	15,000	0.72	<1.0			11.9		147	15.4														
BDC-103	5/15/2006	1469											84	1,600	3,800	3,100	10,000	2,200	12,000	0.92	<0.10	0.054	3.5	15.2		106															
BDC-103	11/20/2006	1658	-59										51	2,000	730	2,200	3,900	1,000	4,900	1.23	<0.10	<0.10	2.4	28.3		202															
BDC-103	2/20/2007	1750	33										26	460	420	140	3,600	1,600	5,200	0.31	60.8	11.1	0.5	99.2		109	6.54														
BDC-103	3/19/2007	1777	60										30	490	88	130	3,500	1,700	5,200	0.63	27.9	8.28	0.4	141		4	6.79														
BDC-103	4/24/2007	1813	96										36	820	440	220	3,500	1,800	5,300	0.84	7.54	3.56	2.4	59.2		-14	6.70														
BDC-103	5/17/2007	1836	119										77	1,400	4,300	1,100	8,300	3,200	11,500	0.61	0.138	0.079	3.6	169		244	6.82														
BDC-103	11/26/2007	2029	312										190	3,300	21,000	4,000	11,000	4,900	15,900	3.37	0.063	0.049	3.6	49.1		-118															
BDC-103	2/18/2008	2113	396	-8									66	1,100	2,600	700	7,500	1,900	9,400	2.06	7.75	0.134	2.8	163		552	5.97														
BDC-103	3/27/2008	2151	434	30									84	1,500	1,900	1,100	9,700	3,000	12,700	1.60	54.1	18	4.0	115.0		182															
BDC-103	5/15/2008	2200	483	79	-40								91	2,700	4,400	1,400	11,000	3,600	14,600	1.38	<0.10	<0.10	3.2	192		-138	7.11														
BDC-103	7/16/2008	2262	545	141	22								79	1,800	440	490	10,000	3,100	13,100	1.61	56.1	16.6	2.8	149		-226	6.72														
BDC-103	9/15/2008	2323	606	202	83	-45							110	2,300	7,600	1,500	10,000	3,600	13,600	0.48	0.330	0.218	3.2	218		189															
BDC-103	11/20/2008	2389	672	268	149	21							47	1,200	260	110	7,000	2,100	9,100	0.21	152	12.5	2.0	120		-1.2	6.66														
BDC-103	1/16/2009	2446	729	325	206	78							11	190	220	12	1,000	480	1,480	0.24	193	2.32	0.6	62.5		-181	6.19														
BDC-103	2/11/2009	2472	755	351	232	104							36	820	510	<100	2,900	1,500	4,400	1.66	82.0	6.7	0.8	178		-65	6.69														
BDC-103	3/9/2009	2498	781	377	258	130							27	1100	440	18	2,400	1,200	3,600	0	47.3	2.4	0.4	192		17	6.80														
BDC-103	4/16/2009	2536	819	415	296	168							30	710	310	<50	2,700	1,200	3,900	0.95	64.8	5.6	0.2-0.4	194		62	6.77														
BDC-103	5/14/2009	2564	847	443	324	196	-34						30	680	320	20	2,400	1,500	3,900	0.48	49.8	4.8	0.8	222		20	6.85														
BDC-103	7/17/2009	2628	911	507	388	260	30						19	410	280	32	630	1,000	1,630	2.60	26.6	2.0	1.0	104		29	6.98														
BDC-103	9/9/2009	2682	965	561	442	314	84	-49					21	620	270	83	700	1,200	1,900	0.88	<0.1	<0.1	2.5	134		2.8	7.01														
BDC-103	11/12/2009	2746	1029	625	506	378	148	15					24	340	140	27	1,800	1,200	3,000	1.42	94.1	7.7	0.4	71.7		117	6.11														
BDC-103	2/17/2010	2843	1126	722	603	475	245	112					0.73	10	<1.0	<1.0	3.1	22	25	1.45	123	1.1	0.0	60.3		939	6.22														
BDC-103	5/17/2010	2932	1215	811	692	564	334	201					3.1	79	44	5.2	60	86	146	1.56	67.9	2.6	0.4	71.6		436	6.63														
BDC-103	8/16/2010	3023	1306	902	783	655	425	292	-37				8.0	740	380	110	420	320	740	2.24	2.4	0.1	2.0	72.5		184	6.96														
BDC-103	11/8/2010	3107	1390	986	867	739	509	376	47				6.3	240	11	1.7	180	540	720	7.46	55.8	1.5	0.0	123		199	7.05														
BDC-103	2/16/2011	3207	1490	1086	967	839	609	476	147				0.28	4.6	<1.0	<1.0	<1.0	5.4	5.4	5.18	133	0.6		74.6		508	6.52														
BDC-103	5/3/2011	3283	1566	1162	1043	915	685	552	223				<0.25	9.1	<1.0	<1.0	<1.0	2.2	2.2	2.15	140	0.2	0.0	74.4		393	6.35														
BDC-103	8/1/2011	3373	1656	1252	1133	1005	775	642	313				0.30	76	<1.0	1.8	7.8	2.5	10.3	5.67	57.6	<0.1	0.2	63.2		168	7.09														
BDC-103	11/1/2011	3465	1748	1344	1225	1097	867	734	405	-105			33	1300	2200	780	2300	1300	3,600	1.72	<0.1	<0.1	1.2	8.1		-226	7.38														
BDC-103	2/19/2012	3575	1858	1454	1335	1207	977	844	515	5			2.2	5.1	31	19	260	69	329	0.21	143		0.3	57.1		36	6.41														
BDC-103	5/3/2012	3649	1932	1528	1409	1281	1051	918	589	79			<0.25	16	1.4	<1.0	3.6	14	17.6	0.11	149	0.83	0.0	56.2		239	6.49														
BDC-103	9/4/2012	3773	2056	1652																																					



**AOC-05 DOWNGRADIENT MONITORING  
AOC-05 ANAEROBIC BIOREMEDIATION REMEDIAL ACTION  
DEVELOPMENTAL CENTER GROUNDWATER MONITORING**

**SWMU-17**


Well	Date		Aquifer Redox Conditions					
			DO (mg/L)	Nitrate (mg-N/L)	Iron II (mg/L)	Sulfate (mg/L)	Methane (mg/L)	ORP (mV)
BDC-05-04	5/15/2006	Natural Redox Baseline		12.3	2.6	33.4		
BDC-05-04	10/23/2008		2.45	7.6	0.1	31.0	0.29	73.5
BDC-05-04	11/2/2008		0.59	4.5	0.8	25.2	0.05	-16
BDC-05-04	12/16/2008		0.55	5.5	1.0	30.4	1.61	-98
BDC-05-04	1/16/2009		0.06	4.3	1.0	21.8	1.48	-192
BDC-05-04	2/11/2009		2.45	5.9	1.0	31.8	1.06	-54
BDC-05-04	3/9/2009		0.27	4.8	1.5	30.1	0.20	35
BDC-05-04	4/16/2009		1.48	5.9	1.4	33.6	<0.0007	68
BDC-05-04	5/13/2009		0.33	4.5	1.6	26.6	0.37	49
BDC-05-04	8/16/2009		0.86	5.4	2.2	30.6	<0.0007	93
BDC-05-04	11/13/2009		0.56	2.2	3.0	18.4	2.44	109
BDC-05-04	2/16/2010		0.88	<0.1	3.3	24.6	1.49	899
BDC-05-04	5/18/2010		0.75	<0.1	3.0	25.4	1.32	473
BDC-05-04	8/17/2010		1.00	<0.1	2.8	17.1	3.53	108
BDC-05-04	11/9/2010		2.21	<0.1	2.2	21.3	3.00	101
BDC-05-04	2/15/2011		2.50	<0.1	2.4	19.4	4.46	93
BDC-05-04	5/2/2011		1.69	<0.1	2.2	18.0	1.75	49
BDC-05-04	11/2/2011		1.52	<1.0	1.2	<1.0		-3
BDC-05-04	5/7/2012		0.16		2.0	21.5		98
BDC-05-04	9/4/2012		0.21	<0.10		16.6		96
BDC-05-04	11/13/2012		0.03	<0.10	1.8	16.9		64
BDC-05-04	5/23/2013		0.49		1.5	13.7		-310
BDC-05-04	11/19/2013		2.56	<0.10	1.0	13.2		-259
BDC-05-04	5/6/2014		3.49	0.40		14.4		-299

**AOC-05 DOWNGRADIENT MONITORING**  
**AOC-05 ANAEROBIC BIOREMEDIATION REMEDIAL ACTION**  
**DEVELOPMENTAL CENTER GROUNDWATER MONITORING**

Well	Date		Aquifer Redox Conditions		
			Nitrate (mg-N/L)	Iron II (mg/L)	Sulfate (mg/L)
<b>SWMU-20</b>					
MW-17A	05/15/2006	Natural Redox Baseline	1.37	0.0	27.0
MW-17A	11/12/2009	Downgradient Monitoring Triggered	0.9		
MW-17A	5/17/2010		1.6	0.2	21.0
MW-17A	11/8/2010		0.1	2.1	15.7
MW-17A	5/3/2011		1.6	0.0	19.8
MW-17A	8/1/2011		0.5	0.0	20.5
MW-17A	11/1/2011		0.3	0.0	23.2
MW-17A	5/3/2012		4.4	0.0	
MW-17A	9/4/2012		2.0		26.8
MW-17A	11/13/2012		0.59	0.0	22.9
MW-17A	5/20/2013		2.9		26.8
MW-17A	11/19/2013		1.3	0.4	23.9
MW-17A	5/6/2014		2.2	0.0	23.7
MW-18A	05/15/2006	Natural Redox Baseline	0.154	0.4	64.8
MW-18A	11/12/2009	Downgradient Monitoring Triggered	0.8		
MW-18A	5/17/2010		1.0	0.4	32.2
MW-18A	11/8/2010		0.1	0.0	14.2
MW-18A	5/3/2011		<0.1	0.0	31.5
MW-18A	8/1/2011		1.1	0.0	42.2
MW-18A	11/1/2011		0.7	0.0	93.3
MW-18A	5/3/2012		<0.10	0.0	
MW-18A	9/4/2012		<0.10		19.5
MW-18A	11/13/2012		<0.10	0.0	21.5
MW-18A	5/20/2013		<0.10		19.6
MW-18A	11/19/2013		<0.10	0.6	15.0
MW-18A	5/6/2014		<0.10	0.0	26.1
MW-21A	05/15/2006	Natural Redox Baseline	0.136	0.4	54.9
MW-21A	11/12/2009	Downgradient Monitoring Triggered	<0.1		
MW-21A	5/17/2010		0.2	0.0	11.9
MW-21A	11/8/2010		<0.1	0.0	5.9
MW-21A	5/3/2011		0.2	0.0	52.1
MW-21A	8/1/2011		0.1	0.0	26.7
MW-21A	11/1/2011		<0.1	0.0	9.3
MW-21A	5/3/2012		0.17	0.0	
MW-21A	9/4/2012		<0.10		6.7
MW-21A	11/13/2012		0.16	0.0	18.5
MW-21A	5/20/2013		0.10	0.5	13.5
MW-21A	11/19/2013		<0.10	0.0	15.6
MW-21A	5/6/2014		<0.10	0.0	7.6


 = Not Analyzed

### BDC-103 TPH-G and BTEX Concentrations Beginning with 2007 Pilot Testing






## BDC-104 TPH-G and BTEX Concentrations Beginning with 2007 Pilot Testing




Note: BDC-104 was installed February 2008




### BDC-101 TPH-G and Benzene Concentrations Since 2001



### BDC-102 TPH-G and Benzene Concentrations Since 2001




### BDC-103 TPH-G and Benzene Concentrations Since 2001







### BDC-103 Nitrate, TPH-G, and Benzene Concentrations




### BDC-104 Nitrate, TPH-G, and Benzene Concentrations



Boeing Developmental Center | V:\025093\112.012\May 2012 Semiannual Report\Figure 8.dwg (A) "Figure 8" 7/24/2012



- Legend**
- AOC-05 Injection and/or Monitoring Well
  - Downgradient Well Location
  - Estimated Radius of Injection
  - Approximate extent of groundwater with gasoline-range hydrocarbon concentrations greater than the 0.8 mg/L preliminary screening level (data is pre-ORC<sup>®</sup> injection)
  - Approximate extent of groundwater with benzene concentrations greater than the 71 µg/L preliminary screening level (data is pre-ORC<sup>®</sup> injection)



Boeing Developmental Center Tukwila, Washington	<b>Site Plan</b>	Figure <b>8</b>
--	------------------	--------------------




*DEVELOPMENTAL CENTER  
GROUNDWATER MONITORING  
MAY 2014*

**GROUNDWATER ELEVATION INFORMATION**

- **CONTOUR MAP**
- **CUMULATIVE WATER LEVEL MEASUREMENTS  
(November 1999 to Present)**






**Notes:**

- 1. Contours based primarily on A-Zone wells.

**Legend**

MW-20D Monitoring Well Location and Designation



**DEVELOPMENTAL CENTER  
CUMULATIVE WATER LEVEL MEASUREMENTS**

Well Location / Bldg.	Well ID No.	Well Depth	May 2014		Feb 2014		Nov 2013		August 2013		May 2013		Feb 2013		Nov 2012	
			Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation
9-101-bldg.	MW-6A	24.25	12.10	2.70			12.82	1.98			12.92	1.88			12.82	1.98
9-101-bldg.	MW-6B	27.20	14.44	0.65			13.16	1.93			13.27	1.82			13.17	1.92
9-101-bldg.	MW-6C	40.55														
9-101-bldg.	MW-8C	40.20														
9-101-bldg.	MW-9A	21.30	12.07	2.67			12.88	1.86			12.80	1.94			12.83	1.91
9-101-bldg.	MW-9B	26.90														
9-101-bldg.	MW-9C	38.80														
9-101-bldg.	MW-9D	56.00														
9-101-bldg.	MW-10A	20.20	11.98	2.71			12.81	1.88			12.72	1.97			12.77	1.92
9-101-bldg.	MW-10C	40.40	11.91	2.71			12.73	1.89			12.65	1.97			12.70	1.92
9-101-bldg.	MW-11A	19.90	12.10	2.78			12.89	1.99			12.84	2.04			12.19	2.69
9-101-bldg.	MW-12A	20.20	12.17	2.66			12.98	1.85			12.88	1.95			13.01	1.82
9-101-bldg.	MW-13A	19.37	11.62	2.52			12.37	1.77			12.36	1.78			12.27	1.87
9-101-bldg.	MW-13C	35.62	11.49	2.53			12.23	1.79			12.22	1.80			12.11	1.91
9-101-bldg.	MW-14A	19.00	11.85	2.52			12.59	1.78			12.65	1.72			12.53	1.84
9-101-bldg.	MW-14C	33.30	11.49	2.48			12.17	1.80			12.25	1.72			12.07	1.90
9-101-bldg.	MW-14E	82.10														
9-101-bldg.	MW-15A	20.70	11.72	2.45			12.44	1.73			12.48	1.69			12.34	1.83
9-101-bldg.	MW-15C	34.35	11.71	2.46			12.42	1.75			12.54	1.63			12.27	1.90
9-101-bldg.	MW-15D	51.80														
9-101-bldg.	MW-16A	20.55	12.22	2.77			13.06	1.93			13.07	1.92			13.02	1.97
9-101-bldg.	MW-16C	38.30	12.32	2.72			13.24	1.80			13.25	1.79			13.17	1.87
9-101-bldg.	MW-17A	19.00	12.11	2.69			12.90	1.90			12.98	1.82			12.78	2.02
9-101-bldg.	MW-17C	35.00														
9-101-bldg.	MW-17D	52.50														
9-101-bldg.	MW-18A	20.02	11.70	2.60			12.23	2.07			12.58	1.72			12.39	1.91
9-101-bldg.	MW-18C	34.55														
9-101-bldg.	MW-18D	52.85														
9-101-bldg.	MW-19A	16.86								10.74	1.49					
9-101-bldg.	MW-19C	33.92														
9-101-bldg.	MW-19D	51.86														
9-101-bldg.	MW-20A	19.34														
9-101-bldg.	MW-20C	35.32	11.58	2.57			12.40	1.75			12.50	1.65			12.22	1.93
9-101-bldg.	MW-20D	50.15														
9-101-bldg.	MW-22A	19.20	11.90	2.35			12.42	1.83			12.72	1.53			12.42	1.83
9-101-bldg.	MW-23A	19.50														
9-101/9-50 bldg.	MW-21A	19.90	11.90	2.55			12.39	2.06			12.80	1.65			12.60	1.85
9-101/9-50 bldg.	MW-21C	34.00														
9-64-bldg.	BDC-05-02	25.35	11.69	2.72	12.21	2.20	12.36	2.05	12.47	1.94	12.29	2.12	12.19	2.22	12.31	2.10
9-64-bldg.	BDC-05-03	25.47	11.76	2.65			12.43	1.98			12.36	2.05			12.36	2.05
9-64-bldg.	BDC-05-04	25.36	11.93	2.66			12.51	2.08			12.17	2.42			12.52	2.07
9-64-bldg.	BDC-05-05	24.18	11.47	2.97			12.15	2.29			12.13	2.31			13.40	1.04
9-64-bldg.	BDC-05-07	25.30	11.29	2.70			11.96	2.03			11.92	2.07			11.97	2.02
9-64-bldg.	BDC-05-08	26.75	12.07	2.60			12.72	1.95			12.64	2.03			12.64	2.03
9-64-bldg.	BDC-05-09	24.55	11.71	2.70			12.37	2.04			12.31	2.10			12.36	2.05
9-64-bldg.	BDC-05-10	24.57	11.70	2.71			12.36	2.05			12.31	2.10			12.30	2.11
9-64-bldg.	BDC-05-11	24.85	11.91	2.74			12.59	2.06			12.51	2.14			12.55	2.10
9-64-bldg.	BDC-05-12	24.87	12.01	2.71	12.53	2.19	12.88	1.84	12.78	1.94	12.61	2.11	12.53	2.19	12.66	2.06
9-64-bldg.	BDC-05-13	24.78	11.86	2.57			12.44	1.99			12.40	2.03			12.44	1.99
9-64-bldg.	BDC-05-14	24.85	11.68	2.54			12.25	1.97			12.21	2.01			12.29	1.93
9-64-bldg.	BDC-05-15	24.48	11.42	2.55			12.04	1.93			12.07	1.90			11.97	2.00
9-64-bldg.	BDC-05-16	24.89	11.60	2.47	12.00	2.07	12.16	1.91	12.25	1.82	12.19	1.88	12.04	2.03	12.09	1.98
9-64-bldg.	BDC-05-17	24.82	11.83	2.42			12.34	1.91			12.30	1.95			12.27	1.98
9-64-bldg.	BDC-05-18	24.69	11.16	2.63	11.62	2.17	11.71	2.08	11.90	1.89	11.72	2.07	11.63	2.16	11.75	2.04
9-64-bldg.	BDC-05-19	24.85	11.91	2.65	12.43	2.13	12.58	1.98	12.68	1.88	12.52	2.04	12.44	2.12	12.60	1.96
9-64-bldg.	BDC-05-20	24.80	11.95	2.39	12.28	2.06	12.46	1.88	12.55	1.79	12.38	1.96	12.41	1.93	12.44	1.90

**DEVELOPMENTAL CENTER  
CUMULATIVE WATER LEVEL MEASUREMENTS**

Well Location / Bldg.	Well ID No.	Well Depth	May 2014		Feb 2014		Nov 2013		August 2013		May 2013		Feb 2013		Nov 2012	
			Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation
9-64-bldg.	BDC-05-21	24.86	11.79	2.40	12.15	2.04	12.30	1.89	12.42	1.77	12.26	1.93	12.25	1.94	12.30	1.89
9-64-bldg.	BDC-05-22	25.07	11.75	2.41	12.08	2.08	12.25	1.91	12.38	1.78	12.22	1.94	12.18	1.98	12.24	1.92
9-64-bldg.	BDC-05-23	25.10	12.36	2.10	12.51	1.95	12.74	1.72	12.83	1.63	12.70	1.76	12.56	1.90	12.74	1.72
9-64-bldg.	BDC-05-24	24.73	11.64	2.55	12.04	2.15	12.22	1.97	12.34	1.85	12.19	2.00	12.09	2.10	12.20	1.99
9-60 bldg.	BDC-101	18.42	11.22	3.25	11.97	2.50	11.99	2.48	12.27	2.20	11.99	2.48	11.77	2.70	12.20	2.27
9-60 bldg.	BDC-102	18.83	10.97	3.30	11.73	2.54	11.75	2.52	12.04	2.23	11.79	2.48	11.55	2.72	11.93	2.34
9-60 bldg.	BDC-103	18.51	10.85	3.49	11.75	2.59	11.66	2.68	12.06	2.28	11.71	2.63	11.43	2.91	11.88	2.46
9-60 bldg.	BDC-104	18.90	10.66	3.50	11.45	2.71	11.51	2.65	11.87	2.29	11.51	2.65	11.24	2.92	11.78	2.38
9-52-bldg.	952MW-1	17.40														
9-52-bldg.	952MW-2	17.54														
9-52-bldg.	952MW-3	17.95														
9-52-bldg. (west)	MW-5	27.43														
9-04-bldg. (north)	MW-2	26.98														
9-04-bldg. (north)	MW-7	18.50														
9-04-bldg. (north)	MW-8	18.50														
9-04-bldg. (north)	MW-9	18.50														

**DEVELOPMENTAL CENTER  
CUMULATIVE WATER LEVEL MEASUREMENTS**

Well Location / Bldg.	Well ID No.	Well Depth	May 2012		Nov 2011		July 2011		May 2011		Nov 2010		May 2010		Nov 2009		May 2009		Nov 2008		
			Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	
9-101-bldg.	MW-6A	24.25	12.61	2.19	12.99	1.81			12.50	2.30	12.70	2.10	12.69	2.11	12.42	2.38	12.73	2.07	12.79	2.01	
9-101-bldg.	MW-6B	27.20	12.96	2.13	13.29	1.80			12.81	2.28	13.06	2.03	13.04	2.05	12.73	2.36	13.08	2.01	13.12	1.97	
9-101-bldg.	MW-6C	40.55													12.72	2.35	13.05	2.02	13.06	2.01	
9-101-bldg.	MW-8C	40.20													12.70	2.22	13.01	1.91	12.88	2.04	
9-101-bldg.	MW-9A	21.30	12.54	2.20	13.03	1.71			12.53	2.21	12.65	2.09	12.65	2.09	12.43	2.31	12.77	1.97	12.69	2.05	
9-101-bldg.	MW-9B	26.90													12.30	2.29	12.64	1.95	12.68	1.91	
9-101-bldg.	MW-9C	38.80													12.40	2.26	12.67	1.99	12.66	2.00	
9-101-bldg.	MW-9D	56.00													12.43	2.23	12.79	1.87	12.78	1.88	
9-101-bldg.	MW-10A	20.20	12.55	2.14	12.97	1.72			12.47	2.22	12.64	2.05	12.62	2.07	12.46	2.23	12.65	2.04	12.68	2.01	
9-101-bldg.	MW-10C	40.40	12.49	2.13	12.90	1.72			12.38	2.24	12.55	2.07	12.53	2.09	12.41	2.21	12.60	2.02	12.62	2.00	
9-101-bldg.	MW-11A	19.90	12.65	2.23	13.03	1.85			12.62	2.26	12.59	2.29	12.69	2.19	12.52	2.36	12.81	2.07	12.81	2.07	
9-101-bldg.	MW-12A	20.20	12.70	2.13	13.23	1.60			12.71	2.12	12.68	2.15	12.73	2.10	12.56	2.27	12.96	1.87	12.91	1.92	
9-101-bldg.	MW-13A	19.37	12.20	1.94	12.66	1.48			12.11	2.03	12.08	2.06	12.14	2.00	11.89	2.25	12.29	1.85	12.25	1.89	
9-101-bldg.	MW-13C	35.62	12.06	1.96	12.52	1.50			11.94	2.08	11.92	2.10	12.02	2.00	11.71	2.31	12.14	1.88	12.12	1.90	
9-101-bldg.	MW-14A	19.00	12.46	1.91	12.71	1.66			12.16	2.21	12.22	2.15	12.39	1.98	12.10	2.27	12.50	1.87	12.50	1.87	
9-101-bldg.	MW-14C	33.30	12.09	1.88	12.20	1.77			12.78	1.19	11.82	2.15	12.00	1.97	11.65	2.32	12.20	1.77	12.08	1.89	
9-101-bldg.	MW-14E	82.10													7.20	6.98	7.55	6.63	7.51	6.67	
9-101-bldg.	MW-15A	20.70	12.16	2.01	12.51	1.66			11.87	2.30	12.12	2.05	12.22	1.95	11.89	2.28	12.44	1.73	12.31	1.86	
9-101-bldg.	MW-15C	34.35	12.36	1.81	12.44	1.73			11.49	2.68	12.00	2.17	12.17	2.00	11.85	2.32	12.46	1.71	12.23	1.94	
9-101-bldg.	MW-15D	51.80													12.02	2.39	12.78	1.63	12.47	1.94	
9-101-bldg.	MW-16A	20.55	12.81	2.18	13.19	1.80			12.67	2.32	12.84	2.15	12.88	2.11	12.68	2.31	12.98	2.01	12.95	2.04	
9-101-bldg.	MW-16C	38.30	13.01	2.03	13.33	1.71			12.84	2.20	13.02	2.02	13.04	2.00	12.63	2.41	13.12	1.92	13.13	1.91	
9-101-bldg.	MW-17A	19.00	12.26	2.54	12.73	2.07	12.84	1.96	12.45	2.35	12.65	2.15	12.63	2.17	12.55	2.25	12.75	2.05	12.80	2.00	
9-101-bldg.	MW-17C	35.00																			
9-101-bldg.	MW-17D	52.50																			
9-101-bldg.	MW-18A	20.02	11.90	2.40	12.84	1.46	12.43	1.87	12.14	2.16	12.22	2.08	12.25	2.05	12.21	2.09	12.42	1.88	12.37	1.93	
9-101-bldg.	MW-18C	34.55													12.36	2.27	12.66	1.97	12.67	1.96	
9-101-bldg.	MW-18D	52.85																			
9-101-bldg.	MW-19A	16.86													10.11	2.12	10.49	1.74	10.47	1.76	
9-101-bldg.	MW-19C	33.92													9.98	2.25	10.44	1.79	10.33	1.90	
9-101-bldg.	MW-19D	51.86																			
9-101-bldg.	MW-20A	19.34													12.37	1.94	12.56	1.75	12.69	1.62	
9-101-bldg.	MW-20C	35.32	12.18	1.97	12.76	1.39			12.27	1.88	11.87	2.28	12.06	2.09	11.70	2.45	12.15	2.00	12.13	2.02	
9-101-bldg.	MW-20D	50.15																			
9-101-bldg.	MW-22A	19.20	12.35	1.90	12.52	1.73			12.14	2.11	12.40	1.85	12.30	1.95	12.04	2.21	12.57	1.68	12.35	1.90	
9-101-bldg.	MW-23A	19.50													11.86	2.41	13.27	1.00	12.67	1.60	
9-101/9-50 bldg.	MW-21A	19.90	12.13	2.32	13.05	1.40	12.67	1.78	12.41	2.04	12.43	2.02	12.45	2.00	12.37	2.08					
9-101/9-50 bldg.	MW-21C	34.00																			
9-64-bldg.	BDC-05-02	25.35	11.81	2.60	12.63	1.78	12.35	2.06	11.81	2.60	12.10	2.31	12.14	2.27	12.05	2.36	12.19	2.22	12.20	2.21	
9-64-bldg.	BDC-05-03	25.47	11.95	2.46	12.77	1.64			11.94	2.47	12.21	2.20	12.24	2.17	12.11	2.30	12.29	2.12	12.28	2.13	
9-64-bldg.	BDC-05-04	25.36	12.05	2.54	12.82	1.77			12.03	2.56	12.30	2.29	12.33	2.26	12.22	2.37	12.40	2.19	12.35	2.24	
9-64-bldg.	BDC-05-05	24.18	11.65	2.79	12.50	1.94			11.61	2.83	11.95	2.49	11.97	2.47	11.89	2.55	12.02	2.42	12.00	2.44	
9-64-bldg.	BDC-05-07	25.30	11.40	2.59	12.23	1.76			11.42	2.57	11.95	2.04	11.75	2.24	11.95	2.04	11.82	2.17	11.80	2.19	
9-64-bldg.	BDC-05-08	26.75	12.28	2.39	13.02	1.65			12.20	2.47	12.49	2.18	12.51	2.16	12.39	2.28	12.79	1.88	12.57	2.10	
9-64-bldg.	BDC-05-09	24.55	11.90	2.51	12.68	1.73	12.27	2.13													
9-64-bldg.	BDC-05-10	24.57	11.95	2.46	12.74	1.67	12.27	2.14													
9-64-bldg.	BDC-05-11	24.85	12.13	2.52	12.92	1.73	12.60	2.05													
9-64-bldg.	BDC-05-12	24.87	12.24	2.48	13.00	1.72	12.57	2.15													
9-64-bldg.	BDC-05-13	24.78	12.02	2.41	12.78	1.65	12.35	2.08													
9-64-bldg.	BDC-05-14	24.85	11.83	2.39	12.55	1.67	12.23	1.99													
9-64-bldg.	BDC-05-15	24.48	11.63	2.34	12.34	1.63	11.95	2.02													
9-64-bldg.	BDC-05-16	24.89	11.78	2.29	12.44	1.63	12.05	2.02													
9-64-bldg.	BDC-05-17	24.82	11.65	2.60	12.60	1.65	12.27	1.98													
9-64-bldg.	BDC-05-18	24.69	11.34	2.45	12.10	1.69	11.84	1.95													
9-64-bldg.	BDC-05-19	24.85	12.15	2.41	12.90	1.66	12.59	1.97													
9-64-bldg.	BDC-05-20	24.80	12.08	2.26	12.75	1.59	12.47	1.87													

**DEVELOPMENTAL CENTER  
CUMULATIVE WATER LEVEL MEASUREMENTS**

Well Location / Bldg.	Well ID No.	Well Depth	May 2012		Nov 2011		July 2011		May 2011		Nov 2010		May 2010		Nov 2009		May 2009		Nov 2008	
			Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation
9-64-bldg.	BDC-05-21	24.86	11.94	2.25	12.59	1.60	12.34	1.85												
9-64-bldg.	BDC-05-22	25.07	11.87	2.29	12.54	1.62	12.27	1.89												
9-64-bldg.	BDC-05-23	25.10	12.39	2.07	13.08	1.38	12.79	1.67												
9-64-bldg.	BDC-05-24	24.73	11.82	2.37	12.59	1.60	12.28	1.91												
9-60 bldg.	BDC-101	18.42	11.32	3.15	12.46	2.01	12.16	2.31	11.48	2.99	11.92	2.55	11.82	2.65	11.82	2.65	11.89	2.58	11.95	2.52
9-60 bldg.	BDC-102	18.83	11.13	3.14	12.16	2.11	11.92	2.35	11.20	3.07	11.67	2.60	11.57	2.70	11.58	2.69	11.64	2.63	11.67	2.60
9-60 bldg.	BDC-103	18.51	11.09	3.25	12.20	2.14	11.90	2.44	10.96	3.38	11.63	2.71	11.54	2.80	11.55	2.79	11.61	2.73	11.68	2.66
9-60 bldg.	BDC-104	18.90	10.93	3.23	12.00	2.16	11.72	2.44	10.97	3.19	11.45	2.71	11.32	2.84	11.36	2.80	11.40	2.76	11.51	2.65
9-52-bldg.	952MW-1	17.40																		
9-52-bldg.	952MW-2	17.54																		
9-52-bldg.	952MW-3	17.95																		
9-52-bldg. (west)	MW-5	27.43																		
9-04-bldg. (north)	MW-2	26.98																		
9-04-bldg. (north)	MW-7	18.50																		
9-04-bldg. (north)	MW-8	18.50																		
9-04-bldg. (north)	MW-9	18.50																		

**DEVELOPMENTAL CENTER  
CUMULATIVE WATER LEVEL MEASUREMENTS**

Well Location / Bldg.	Well ID No.	Well Depth	May 2008		Nov 2007		May 2007		February 2007		Nov 2006		Aug 2006		May 2006		February 2006		November 2005		
			Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	
9-101-bldg.	MW-6A	24.25	12.87	1.93	13.08	1.72	12.97	1.83	12.42	2.38	12.30	2.50	13.16	1.64	12.77	2.03	12.42	2.38	12.80	2.00	
9-101-bldg.	MW-6B	27.20	13.21	1.88	13.46	1.63	13.32	1.77	12.75	2.34	12.67	2.42	13.50	1.59	13.09	2.00	12.75	2.34	13.15	1.94	
9-101-bldg.	MW-6C	40.55	13.13	1.94	13.41	1.66	13.27	1.80	12.69	2.38	12.65	2.42	13.41	1.66	13.07	2.00	12.71	2.36	13.14	1.93	
9-101-bldg.	MW-8C	40.20	13.16	1.76	13.28	1.64	13.00	1.92			12.21	2.71			13.18	1.74			13.00	1.92	
9-101-bldg.	MW-9A	21.30	12.93	1.81	13.07	1.67	12.90	1.84	12.36	2.38	12.12	2.62	13.05	1.69	13.00	1.74	12.37	2.37	12.73	2.01	
9-101-bldg.	MW-9B	26.90	12.75	1.84	12.91	1.68	12.71	1.88	12.19	2.40	11.95	2.64	12.87	1.72	13.81	0.78	12.19	2.40	12.69	1.90	
9-101-bldg.	MW-9C	38.80	12.82	1.84	13.02	1.64	12.81	1.85	12.20	2.46	12.05	2.61	13.01	1.65	12.91	1.75	12.26	2.40	12.69	1.97	
9-101-bldg.	MW-9D	56.00	12.90	1.76	13.56	1.10	12.88	1.78			12.30	2.36			13.15	1.51			12.90	1.76	
9-101-bldg.	MW-10A	20.20	12.89	1.80	13.05	1.64	12.72	1.97	12.35	2.34	12.06	2.63	12.88	1.81	12.98	1.71	11.93	2.76	12.73	1.96	
9-101-bldg.	MW-10C	40.40	12.78	1.84	12.96	1.66	12.77	1.85			11.99	2.63			12.88	1.74			12.63	1.99	
9-101-bldg.	MW-11A	19.90	13.16	1.72	13.16	1.72	12.96	1.92			11.85	3.03			12.80	2.08			12.92	1.96	
9-101-bldg.	MW-12A	20.20	13.22	1.61	13.24	1.59	13.00	1.83			11.89	2.94			12.97	1.86			12.98	1.85	
9-101-bldg.	MW-13A	19.37	12.62	1.52	12.42	1.72	12.33	1.81			11.50	2.64			12.48	1.66			12.26	1.88	
9-101-bldg.	MW-13C	35.62	12.46	1.56	12.29	1.73	12.20	1.82			11.35	2.67			12.33	1.69			12.10	1.92	
9-101-bldg.	MW-14A	19.00	12.64	1.73	12.55	1.82	12.73	1.64	12.03	2.34	11.46	2.91	12.83	1.54	12.59	1.78	11.95	2.42	12.39	1.98	
9-101-bldg.	MW-14C	33.30	12.14	1.83	12.00	1.97	12.32	1.65			11.72	2.25			12.26	1.71			12.13	1.84	
9-101-bldg.	MW-14E	82.10	8.07	6.11	6.83	7.35	7.59	6.59			6.71	7.47			8.78	5.40			7.87	6.31	
9-101-bldg.	MW-15A	20.70	12.35	1.82	12.24	1.93	12.52	1.65			11.93	2.24			12.05	2.12			12.42	1.75	
9-101-bldg.	MW-15C	34.35	12.50	1.67	12.30	1.87	12.55	1.62			11.91	2.26			12.37	1.80			12.50	1.67	
9-101-bldg.	MW-15D	51.80	12.68	1.73	12.53	1.88	12.76	1.65			12.14	2.27			12.52	1.89			12.63	1.78	
9-101-bldg.	MW-16A	20.55	13.17	1.82	12.53	2.46	13.11	1.88			12.05	2.94			13.04	1.95			13.05	1.94	
9-101-bldg.	MW-16C	38.30	13.34	1.70	13.33	1.71	13.23	1.81			12.22	2.82			13.23	1.81			13.22	1.82	
9-101-bldg.	MW-17A	19.00	13.07	1.73	13.00	1.80	12.80	2.00			12.04	2.76			12.85	1.95			12.74	2.30	
9-101-bldg.	MW-17C	35.00																		12.83	2.21
9-101-bldg.	MW-17D	52.50																		12.82	2.22
9-101-bldg.	MW-18A	20.02	12.72	1.58	12.46	1.84	12.45	1.85			11.57	2.73			12.43	1.87			12.44	1.86	
9-101-bldg.	MW-18C	34.55	12.98	1.65	12.88	1.75	12.74	1.89			11.85	2.78			12.70	1.93			12.72	1.91	
9-101-bldg.	MW-18D	52.85																		12.42	2.21
9-101-bldg.	MW-19A	16.86	10.49	1.74	10.68	1.55	10.55	1.68	9.92	2.31	9.59	2.64	10.77	1.46	10.44	1.79	10.22	2.01	10.43	1.80	
9-101-bldg.	MW-19C	33.92	10.41	1.82	10.59	1.64	10.50	1.73			9.50	2.73			10.32	1.91			10.36	1.87	
9-101-bldg.	MW-19D	51.86																		10.69	1.54
9-101-bldg.	MW-20A	19.34	12.60	1.71	12.76	1.55	12.30	2.01			12.10	2.21			12.09	2.22			12.68	1.63	
9-101-bldg.	MW-20C	35.32	12.50	1.65	12.39	1.76	12.28	1.87			11.67	2.48			12.05	2.10			12.30	1.85	
9-101-bldg.	MW-20D	50.15																		12.66	1.49
9-101-bldg.	MW-22A	19.20	12.50	1.75	12.25	2.00	12.64	1.61	11.90	2.35	12.11	2.14	12.77	1.48	12.41	1.84	12.25	2.00	12.55	1.70	
9-101-bldg.	MW-23A	19.50	12.67	1.60	12.83	1.44	12.90	1.37	12.03	2.24	13.02	1.25	12.94	1.33	12.49	1.78	12.44	1.83	12.78	1.49	
9-101/9-50 bldg.	MW-21A	19.90													12.68	1.77					
9-101/9-50 bldg.	MW-21C	34.00																			
9-64-bldg.	BDC-05-02	25.35	12.28	2.09	12.31	2.06	12.23	2.14			11.53	2.84			12.21	2.16			12.21	2.16	
9-64-bldg.	BDC-05-03	25.47	12.47	1.94	12.51	1.90	12.45	1.96			11.75	2.66			12.40	2.01			12.43	1.98	
9-64-bldg.	BDC-05-04	25.36	12.58	2.01	12.57	2.02	12.54	2.05			11.85	2.74			12.54	2.05			12.52	2.07	
9-64-bldg.	BDC-05-05	24.18	12.18	2.26	12.30	2.14	12.07	2.37			11.51	2.93			12.16	2.28			12.16	2.28	
9-64-bldg.	BDC-05-07	25.30	12.02	1.97	12.03	1.96	11.96	2.03			11.27	2.72			11.94	2.05			11.96	2.03	
9-64-bldg.	BDC-05-08	26.75																			
9-64-bldg.	BDC-05-09	24.55																			
9-64-bldg.	BDC-05-10	24.57																			
9-64-bldg.	BDC-05-11	24.85																			
9-64-bldg.	BDC-05-12	24.87																			
9-64-bldg.	BDC-05-13	24.78																			
9-64-bldg.	BDC-05-14	24.85																			
9-64-bldg.	BDC-05-15	24.48																			
9-64-bldg.	BDC-05-16	24.89																			
9-64-bldg.	BDC-05-17	24.82																			
9-64-bldg.	BDC-05-18	24.69																			
9-64-bldg.	BDC-05-19	24.85																			
9-64-bldg.	BDC-05-20	24.80																			

**DEVELOPMENTAL CENTER  
CUMULATIVE WATER LEVEL MEASUREMENTS**

Well Location / Bldg.	Well ID No.	Well Depth	May 2008		Nov 2007		May 2007		February 2007		Nov 2006		Aug 2006		May 2006		February 2006		November 2005	
			Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation
9-64-bldg.	BDC-05-21	24.86																		
9-64-bldg.	BDC-05-22	25.07																		
9-64-bldg.	BDC-05-23	25.10																		
9-64-bldg.	BDC-05-24	24.73																		
9-60 bldg.	BDC-101	18.42	12.29	2.18	12.22	2.25	12.13	2.34			11.42	3.05			12.07	2.40			11.91	2.56
9-60 bldg.	BDC-102	18.83	12.08	2.19	11.86	2.41	11.89	2.38			11.13	3.14			11.85	2.42			11.79	2.48
9-60 bldg.	BDC-103	18.51	12.02	2.32	11.93	2.41	11.87	2.47			11.10	3.24			11.78	2.56			11.81	2.53
9-60 bldg.	BDC-104	18.90	11.84	2.32																
9-52-bldg.	952MW-1	17.40																		
9-52-bldg.	952MW-2	17.54																		
9-52-bldg.	952MW-3	17.95																		
9-52-bldg. (west)	MW-5	27.43																		
9-04-bldg. (north)	MW-2	26.98																		
9-04-bldg. (north)	MW-7	18.50																		
9-04-bldg. (north)	MW-8	18.50																		
9-04-bldg. (north)	MW-9	18.50																		

**DEVELOPMENTAL CENTER  
CUMULATIVE WATER LEVEL MEASUREMENTS**

Well Location / Bldg.	Well ID No.	Well Depth	August 2005		May 2005		February 2005		October 2004		August 2004		May 2004		November 2003		June 2003		December 2002	
			Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation
9-101-bldg.	MW-6A	24.25	13.02	1.78	12.52	2.28	12.68	2.12	12.90	1.90	13.06	1.74								
9-101-bldg.	MW-6B	27.20	13.35	1.74	12.88	2.21	12.97	2.12	13.25	1.84	13.40	1.69	13.00	1.83	12.88	1.95	13.30	1.53	13.01	1.82
9-101-bldg.	MW-6C	40.55	13.32	1.75	12.87	2.20	12.90	2.17	13.18	1.89	13.37	1.70	13.14	1.85	13.03	1.96	13.44	1.55	13.16	1.83
9-101-bldg.	MW-8C	40.20			12.64	2.28			12.91	2.01			13.11	1.81	13.11	1.81	13.39	1.53	13.19	1.73
9-101-bldg.	MW-9A	21.30	13.08	1.66	12.53	2.21	12.51	2.23	12.92	1.82	13.05	1.69	12.82	1.82	12.78	1.86	13.00	1.64	12.90	1.74
9-101-bldg.	MW-9B	26.90	12.90	1.69	12.17	2.42	10.80	3.79	12.76	1.83	12.90	1.69	12.77	1.95	12.82	1.90	13.08	1.64	12.96	1.76
9-101-bldg.	MW-9C	38.80	12.93	1.73	12.55	2.11	12.46	2.20	12.87	1.79	13.01	1.65	12.85	1.83	12.77	1.91	13.09	1.59	12.90	1.78
9-101-bldg.	MW-9D	56.00			12.90	1.76			13.92	0.74			12.92	1.74	13.04	1.62	13.39	1.27	13.17	1.49
9-101-bldg.	MW-10A	20.20	12.85	1.84	12.52	2.17	12.58	2.11	12.95	1.74	13.05	1.64	12.93	1.76	12.83	1.86	13.08	1.61	13.03	1.66
9-101-bldg.	MW-10C	40.40			12.45	2.17			12.74	1.88			12.80	1.82	12.71	1.91	12.97	1.65	12.90	1.72
9-101-bldg.	MW-11A	19.90			12.42	2.46			12.78	2.10			13.12	1.76	12.91	1.97	13.14	1.74	13.13	1.75
9-101-bldg.	MW-12A	20.20			12.58	2.25			12.86	1.97			13.21	1.62	13.00	1.83	13.23	1.60	13.20	1.63
9-101-bldg.	MW-13A	19.37			11.97	2.17			12.35	1.79			12.47	1.67	12.18	1.96	12.49	1.65	12.38	1.76
9-101-bldg.	MW-13C	35.62			11.78	2.24			12.19	1.83			12.35	1.67	12.02	2.00	12.30	1.72	12.22	1.80
9-101-bldg.	MW-14A	19.00	12.56	1.81	12.35	2.02	12.38	2.09	12.60	1.87	12.94	1.53	12.71	1.76	12.57	1.90	12.91	1.56	12.70	1.77
9-101-bldg.	MW-14C	33.30			11.84	2.13			12.09	1.88			12.16	1.81	12.07	1.90	12.43	1.54	12.18	1.79
9-101-bldg.	MW-14E	82.10			7.29	6.89			7.58	6.60			6.94	7.24	7.26	6.92	8.56	5.62	7.69	6.49
9-101-bldg.	MW-15A	20.70			11.74	2.43			12.17	2.00			12.67	1.50	12.36	1.81	12.57	1.60	12.55	1.62
9-101-bldg.	MW-15C	34.35			12.02	2.15			12.31	1.86			12.72	1.45	12.37	1.80	12.56	1.61	12.47	1.70
9-101-bldg.	MW-15D	51.80			12.20	2.21			12.56	1.85			12.88	1.53	12.64	1.77	12.41	2.00	12.80	1.61
9-101-bldg.	MW-16A	20.55			12.67	2.32			12.97	2.02			13.19	1.80	12.96	2.03	13.35	1.64	13.03	1.96
9-101-bldg.	MW-16C	38.30			12.83	2.21			13.15	1.89			13.38	1.66	13.15	1.89	13.51	1.53	13.33	1.71
9-101-bldg.	MW-17A	19.00							12.81	1.99			13.05	1.75	12.83	1.97	13.10	1.70	12.99	1.81
9-101-bldg.	MW-17C	35.00							12.80	2.05			13.11	1.74						
9-101-bldg.	MW-17D	52.50							12.97	1.90			13.20	1.67						
9-101-bldg.	MW-18A	20.02			12.11	2.19			12.43	1.87			12.57	1.73	12.36	1.94				
9-101-bldg.	MW-18C	34.55			12.36	2.27			12.75	1.88			12.84	1.79	12.62	2.01	12.89	1.74	12.82	1.81
9-101-bldg.	MW-18D	52.85							12.42	1.84			12.60	1.66						
9-101-bldg.	MW-19A	16.86	10.70	1.53	10.22	2.01	10.19	2.04	10.54	1.69			10.85	1.38	10.39	1.84				
9-101-bldg.	MW-19C	33.92			10.22	2.01			10.43	1.80			10.22	2.01	10.31	1.92	10.55	1.68	10.41	1.82
9-101-bldg.	MW-19D	51.86							10.67	1.56			10.86	1.37						
9-101-bldg.	MW-20A	19.34			12.33	1.98			12.75	1.56			12.73	1.58	12.58	1.73				
9-101-bldg.	MW-20C	35.32			11.90	2.25			12.39	1.76			12.66	1.49	12.24	1.91	12.48	1.67	12.26	1.89
9-101-bldg.	MW-20D	50.15							12.80	1.63			13.17	1.26						
9-101-bldg.	MW-22A	19.20	12.81	1.44	12.38	1.87														
9-101-bldg.	MW-23A	19.50	13.73	0.54	13.55	0.72														
9-101/9-50 bldg.	MW-21A	19.90																	12.79	1.66
9-101/9-50 bldg.	MW-21C	34.00																	10.53	1.67
9-64-bldg.	BDC-05-02	25.35			11.86	2.51			12.40	1.97			12.24	2.13	12.08	2.29	12.47	1.90	12.40	1.97
9-64-bldg.	BDC-05-03	25.47			12.07	2.34			12.60	1.81			12.46	1.95	12.28	2.13	12.66	1.75	12.60	1.81
9-64-bldg.	BDC-05-04	25.36			12.17	2.42			12.72	1.87			12.55	2.04	12.40	2.19	12.80	1.79	12.71	1.88
9-64-bldg.	BDC-05-05	24.18			11.87	2.57			12.41	2.03			12.12	2.32	12.13	2.31	12.51	1.93	12.42	2.02
9-64-bldg.	BDC-05-07	25.30			11.59	2.40			12.14	1.85			11.97	2.02	11.81	2.18	12.18	1.81	12.11	1.88
9-64-bldg.	BDC-05-08	26.75																		
9-64-bldg.	BDC-05-09	24.55																		
9-64-bldg.	BDC-05-10	24.57																		
9-64-bldg.	BDC-05-11	24.85																		
9-64-bldg.	BDC-05-12	24.87																		
9-64-bldg.	BDC-05-13	24.78																		
9-64-bldg.	BDC-05-14	24.85																		
9-64-bldg.	BDC-05-15	24.48																		
9-64-bldg.	BDC-05-16	24.89																		
9-64-bldg.	BDC-05-17	24.82																		
9-64-bldg.	BDC-05-18	24.69																		
9-64-bldg.	BDC-05-19	24.85																		
9-64-bldg.	BDC-05-20	24.80																		



**DEVELOPMENTAL CENTER  
CUMULATIVE WATER LEVEL MEASUREMENTS**

Well Location / Bldg.	Well ID No.	Well Depth	August 2005		May 2005		February 2005		October 2004		August 2004		May 2004		November 2003		June 2003		December 2002	
			Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation
9-64-bldg.	BDC-05-21	24.86																		
9-64-bldg.	BDC-05-22	25.07																		
9-64-bldg.	BDC-05-23	25.10																		
9-64-bldg.	BDC-05-24	24.73																		
9-60 bldg.	BDC-101	18.42			11.73	2.74			12.31	2.16			12.04	2.43	12.08	2.39	12.43	2.04	12.34	2.13
9-60 bldg.	BDC-102	18.83			11.53	2.74			11.97	2.30			11.84	2.43	11.82	2.45	12.24	2.03	12.14	2.13
9-60 bldg.	BDC-103	18.51			11.50	2.84			12.08	2.26			11.79	2.55	11.72	2.62	12.27	2.07	12.15	2.19
9-60 bldg.	BDC-104	18.90																		
9-52-bldg.	952MW-1	17.40																		
9-52-bldg.	952MW-2	17.54																		
9-52-bldg.	952MW-3	17.95																		
9-52-bldg. (west)	MW-5	27.43																		
9-04-bldg. (north)	MW-2	26.98											9.96	2.71	9.78	2.89				
9-04-bldg. (north)	MW-7	18.50											10.90	2.79	10.72	2.97				
9-04-bldg. (north)	MW-8	18.50											11.10	2.82	10.88	3.04				
9-04-bldg. (north)	MW-9	18.50											11.03		10.84					

**DEVELOPMENTAL CENTER  
CUMULATIVE WATER LEVEL MEASUREMENTS**

Well Location / Bldg.	Well ID No.	Well Depth	June 2002		December 2001		June 2001		December 2000		June 2000		November 1999	
			Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation
9-101-bldg.	MW-6A	24.25												
9-101-bldg.	MW-6B	27.20	13.21	1.62	12.45	2.38	13.50	1.33	13.55	1.28	13.01	1.82	13.33	1.50
9-101-bldg.	MW-6C	40.55	13.36	1.63	12.60	2.39	13.67	1.32	13.70	1.29	13.15	1.84	13.50	1.49
9-101-bldg.	MW-8C	40.20	13.27	1.65	12.89	2.03	13.85	1.07	13.71	1.21	13.13	1.79	13.79	1.13
9-101-bldg.	MW-9A	21.30	12.94	1.70	12.69	1.95	13.76	0.88	13.72	0.92	12.78	1.86	13.67	0.97
9-101-bldg.	MW-9B	26.90	13.00	1.72	12.82	1.90	13.90	0.82	13.82	0.90	12.81	1.91	13.90	0.82
9-101-bldg.	MW-9C	38.80	12.94	1.74	12.61	2.07	13.64	1.04	13.57	1.11	12.75	1.93	13.60	1.08
9-101-bldg.	MW-9D	56.00	13.20	1.46	12.25	2.41	13.15	1.51	13.03	1.63	12.74	1.92	13.00	1.66
9-101-bldg.	MW-10A	20.20	12.94	1.75	12.52	2.17	13.52	1.17	13.62	1.07	12.84	1.85	13.50	1.19
9-101-bldg.	MW-10C	40.40	12.84	1.78	12.32	2.30	13.37	1.25	13.40	1.22	12.74	1.88	13.29	1.33
9-101-bldg.	MW-11A	19.90	12.97	1.91	12.28	2.60	13.35	1.53	13.52	1.36	12.91	1.97	13.20	1.68
9-101-bldg.	MW-12A	20.20	13.03	1.80	12.33	2.50	13.35	1.48	13.50	1.33	13.02	1.81	13.21	1.62
9-101-bldg.	MW-13A	19.37	12.50	1.64	11.92	2.22	12.59	1.55	12.76	1.38	12.50	1.64	12.33	1.81
9-101-bldg.	MW-13C	35.62	12.31	1.71	11.45	2.57	12.43	1.59	12.69	1.33	12.37	1.65	12.21	1.81
9-101-bldg.	MW-14A	19.00	12.85	1.62	12.16	2.31	13.00	1.47	12.98	1.49	12.70	1.77	12.78	1.69
9-101-bldg.	MW-14C	33.30	12.33	1.64	11.60	2.37	12.59	1.38	12.49	1.48	12.17	1.80	12.35	1.62
9-101-bldg.	MW-14E	82.10	7.64	6.54	6.10	8.08	7.83	6.35	7.44	6.74	7.45	6.73	7.90	6.28
9-101-bldg.	MW-15A	20.70	12.52	1.65	11.82	2.35	12.66	1.51	12.82	1.35	12.40	1.77	12.35	1.82
9-101-bldg.	MW-15C	34.35	12.50	1.67	11.73	2.44	12.80	1.37	12.77	1.40	12.36	1.81	12.49	1.68
9-101-bldg.	MW-15D	51.80	13.02	1.39	11.90	2.51	12.88	1.53	12.90	1.51	12.59	1.82	12.44	1.97
9-101-bldg.	MW-16A	20.55	13.02	1.97	12.45	2.54	13.55	1.44	13.50	1.49	13.19	1.80	13.34	1.65
9-101-bldg.	MW-16C	38.30	13.29	1.75	12.62	2.42	13.77	1.27	13.67	1.37	13.36	1.68	13.52	1.52
9-101-bldg.	MW-17A	19.00	13.07	1.73	12.34	2.46			13.32	1.48	13.05	1.75	13.03	1.77
9-101-bldg.	MW-17C	35.00					13.25	1.60			13.10	1.75	13.05	1.80
9-101-bldg.	MW-17D	52.50					13.20	1.67			13.25	1.62	12.82	2.05
9-101-bldg.	MW-18A	20.02			11.82	2.48	12.61	1.69	12.84	1.46	12.55	1.75	12.38	1.92
9-101-bldg.	MW-18C	34.55	12.92	1.71			12.87	1.76	13.12	1.51	12.83	1.80	12.61	2.02
9-101-bldg.	MW-18D	52.85					12.58	1.68	12.85	1.41	12.52	1.74	12.33	1.93
9-101-bldg.	MW-19A	16.86			9.93	2.30	10.62	1.61	10.93	1.30	10.68	1.55	10.42	1.81
9-101-bldg.	MW-19C	33.92	10.71	1.52			10.55	1.68	10.89	1.34	10.65	1.58	10.35	1.88
9-101-bldg.	MW-19D	51.86					11.00	1.23	10.90	1.33	10.71	1.52	11.05	1.18
9-101-bldg.	MW-20A	19.34			12.20	2.11	12.60	1.71	12.89	1.42	12.44	1.87	12.75	1.56
9-101-bldg.	MW-20C	35.32	12.55	1.60			12.50	1.65	12.69	1.46	12.16	1.99	12.44	1.71
9-101-bldg.	MW-20D	50.15					12.83	1.60	12.87	1.56	12.41	2.02	12.66	1.77
9-101-bldg.	MW-22A	19.20												
9-101-bldg.	MW-23A	19.50												
9-101/9-50 bldg.	MW-21A	19.90	12.74	1.71	12.05	2.40	12.77	1.68	13.04	1.41	12.93	1.52	12.50	1.95
9-101/9-50 bldg.	MW-21C	34.00	10.52	1.68	9.87	2.33	10.50	1.70						
9-64-bldg.	BDC-05-02	25.35	12.25	2.12	11.45	2.92	12.38	1.99	12.56	1.81	12.37	2.00	12.03	2.34
9-64-bldg.	BDC-05-03	25.47	12.47	1.94	11.70	2.71	12.56	1.85	12.82	1.59	12.56	1.85	12.33	2.08
9-64-bldg.	BDC-05-04	25.36	12.57	2.02	11.78	2.81	12.69	1.90	12.86	1.73	12.65	1.94	12.33	2.26
9-64-bldg.	BDC-05-05	24.18	12.22	2.22	11.38	3.06	12.37	2.07	12.53	1.91	12.36	2.08	11.96	2.48
9-64-bldg.	BDC-05-07	25.30	12.02	1.97	11.18	2.81	12.10	1.89	12.28	1.71	12.08	1.91	11.72	2.27
9-64-bldg.	BDC-05-08	26.75												
9-64-bldg.	BDC-05-09	24.55												
9-64-bldg.	BDC-05-10	24.57												
9-64-bldg.	BDC-05-11	24.85												
9-64-bldg.	BDC-05-12	24.87												
9-64-bldg.	BDC-05-13	24.78												
9-64-bldg.	BDC-05-14	24.85												
9-64-bldg.	BDC-05-15	24.48												
9-64-bldg.	BDC-05-16	24.89												
9-64-bldg.	BDC-05-17	24.82												
9-64-bldg.	BDC-05-18	24.69												
9-64-bldg.	BDC-05-19	24.85												
9-64-bldg.	BDC-05-20	24.80												

**DEVELOPMENTAL CENTER  
CUMULATIVE WATER LEVEL MEASUREMENTS**

Well Location / Bldg.	Well ID No.	Well Depth	June 2002		December 2001		June 2001		December 2000		June 2000		November 1999	
			Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation	Depth to Water	Water Elevation
9-64-bldg.	BDC-05-21	24.86												
9-64-bldg.	BDC-05-22	25.07												
9-64-bldg.	BDC-05-23	25.10												
9-64-bldg.	BDC-05-24	24.73												
9-60 bldg.	BDC-101	18.42	12.07	2.40	11.29	3.18	12.30	2.17						
9-60 bldg.	BDC-102	18.83	11.82	2.45	11.05	3.22	12.06	2.21						
9-60 bldg.	BDC-103	18.51	11.81	2.53	11.03	3.31	12.04	2.30						
9-60 bldg.	BDC-104	18.90												
9-52-bldg.	952MW-1	17.40	11.10	2.38	10.21	3.27	11.25	2.23	11.50	1.98			10.97	2.51
9-52-bldg.	952MW-2	17.54	11.37	2.63	10.46	3.54	11.48	2.52	11.76	2.24			11.25	2.75
9-52-bldg.	952MW-3	17.95	11.40	2.36	10.52	3.24	11.55	2.21	11.85	1.91			11.28	2.48
9-52-bldg. (west)	MW-5	27.43											10.53	2.42
9-04-bldg. (north)	MW-2	26.98					10.03	2.64			10.19	2.48	9.53	3.14
9-04-bldg. (north)	MW-7	18.50			9.96	3.73	11.05	2.64						
9-04-bldg. (north)	MW-8	18.50			10.08	3.84	11.23	2.69						
9-04-bldg. (north)	MW-9	18.50			10.08		11.23	-11.23						

Notes:

Depth to Water measurements taken from top of well casing

Top of casing elevation altered in wells MW-6B, MW-6C, MW-9A, MW-9B, and MW-9C by installation of threaded fitting on 6/19/2004.

Top of casing elevation was lowered in well MW-14A by 0.10 ft on 3/17/2005; resurveyed 9/9/05.

Top of casing elevation at wells MS-22A and MW-23A measured 9/9/05.

BDC05-02 was modified in October 2008 for utilization as an injection well. Elevation changed from 14.37 to 14.41 ft; total depth changed from 25.35 to 25.27.

*DEVELOPMENTAL CENTER*  
*GROUNDWATER MONITORING*  
*May 2014*

**GROUNDWATER SAMPLE COLLECTION FORMS**

**ANALYTICAL DATA**

**(DVD)**