August 23, 2017

Mr. Scott Koppelman **AMLI Residential Partners** 425 Pontius Avenue North, Suite 400 Seattle, Washington 98109

SUBJECT: SECOND QUARTER 2017 GROUNDWATER MONITORING REPORT

Former Avtech Property (AMLI Wallingford)

3400 Wallingford Avenue North, Seattle, Washington

Project Number: 0789-004-24

Mr. Koppelman:

SoundEarth Strategies, Inc. (SoundEarth) has prepared this report to present the results of the Second Quarter 2017 groundwater monitoring event (monitoring event) conducted at the AMLI Wallingford property located at 3400 Wallingford Avenue North in Seattle, Washington (the Property), as shown in Figure 1. The Property consists of 2.02 acres under redevelopment on the north and south sides of North 34th Street (North Block and South Block, respectively), as shown on Figure 2.

BACKGROUND

The Property was initially developed by the early 1900s with four single-family residences. A two-story factory/commercial building was constructed on the North Block in 1909. This building contained a shoe manufacturer from 1909 to the 1940s and Grandma's Cookies in the 1950s and 1960s. Avtech Corporation (Avtech), a manufacturer of aviation electronics, occupied the building from 1974 to 2011. Two furniture workshop buildings were constructed on the south side of North 34th Street in the 1930s (South Block), with an additional single-story warehouse constructed in 1965. Avtech occupied the South Block buildings from the 1980s to 2011.

Based on the results of previous subsurface investigations (2011 through 2014) and cleanup action activities performed during site redevelopment between November 2014 and April 2015, subsurface soil beneath the Property consists primarily of localized, near-surface anthropogenic fill overlying Vashonage glacial till, which overlies glacial advance outwash deposits. Groundwater was encountered within the advance outwash deposits during subsurface exploration activities. This water-bearing zone was typically encountered at depths ranging from approximately 21.5 to 45 feet below the pre-construction ground surface and appeared to extend beyond the maximum depth explored of 55 feet below the preconstruction ground surface. The groundwater migration direction has been consistently toward the southeast.

The site is defined by the nature and extent of contamination associated with one or more releases of hazardous substances prior to any cleanup of that contamination (the Site). Based on the information gathered to date, the Site includes soil contaminated with trichloroethene (TCE), tetrachloroethene (PCE), lead, and carcinogenic polycyclic aromatic hydrocarbons (cPAHs), and groundwater contaminated

with TCE. The TCE and PCE impacts likely resulted from past manufacturing activities at the former Avtech facility on the Property. Sampling conducted to date indicates that soil was impacted by TCE in the former loading dock area of the commercial building, formerly located on the North Block, at depths ranging from approximately 9 to 30 feet below grade. Groundwater containing TCE concentrations exceeding the Washington State Model Toxics Control Act (MTCA) Method A cleanup level was present on the southern half of the North Block and apparently migrated to the south across North 34th Street to the South Block, the adjacent Varsity Inn property, and beneath Burke Avenue North (east of North 34th Street). The results of previous groundwater sampling at the Site are summarized in Table 1.

The Site was accepted into the Washington State Department of Ecology's Voluntary Cleanup Program (VCP) Project No. NW2739 on June 11, 2013. An interim cleanup action was performed at the Site between November 2014 and February 2015, along with the installation of a soil vapor extraction system on the North Block and the installation of new injection wells and the injection events with potassium permanganate at the Site in March 2015. Approximately 5,414 tons of TCE-, petroleum hydrocarbon-, cPAH-, and lead-impacted soils were excavated from the Property in the course of mass excavation activities and disposed of at Waste Management's Columbia Ridge Landfill in Arlington, Oregon, between December 2, 2014, and February 18, 2015. In March 2015, SoundEarth injected 53,765 gallons of an aqueous potassium permanganate solution containing 18,480 pounds of potassium permanganate. The solution was injected into 56 wells on the North and South Blocks: 31,068 gallons were injected into 32 wells on the North Block and 22,697 gallons were injected into 24 wells on the South Block.

SoundEarth conducted additional injection events in July and December 2016. During the July 2016 injection event, SoundEarth set up a multipoint automated injection system and a single-point injection system to inject mixed batches of potassium permanganate solution into 14 injection wells. Over the course of the July 2016 injection event, approximately 12,000 gallons of 3 percent solution potassium permanganate and 4,000 gallons of rinse water were injected.

During the December 2016 injection event, SoundEarth injected batches of potassium permanganate solution into injection wells IW56 and IW57. Over the course of the injection event conducted on December 19 through 21, 2016, SoundEarth injected a total of 2,000 gallons of solution into injection wells IW56 and IW57. The purpose of the injection was to treat residual contamination in MW18.

SECOND QUARTER FIELD ACTIVITIES

The monitoring event was conducted on May 24 and 25, 2017. The monitoring event was performed to evaluate the environmental quality of groundwater beneath the Property and Site.

Second Quarter 2017 Groundwater Sampling Event

Upon arrival at the Property on May 24, 2017, SoundEarth personnel opened monitoring wells MW05, MW12, MW16A, MW18, and IW08. Water levels were permitted to equilibrate with atmospheric pressure for a minimum of 15 minutes before groundwater level measurements were obtained. Groundwater levels were measured relative to the top of well casing to an accuracy of 0.01 feet using an electronic water level meter.

On May 24 and 25, 2017, groundwater samples were collected from monitoring wells MW05, MW12, MW16A, MW18, and IW08. Groundwater samples from MW05, MW12, MW16A, and MW18 were

collected in accordance with the U.S. Environmental Protection Agency (EPA) Low-Flow (Minimal Drawdown) Ground-Water Sampling Procedures (April 1996). Purging and sampling of each monitoring well were performed using a bladder pump or peristaltic pump and dedicated polyethylene tubing at flow rates ranging from 60 to 125 milliliters per minute. The intake was placed approximately 2 to 3 feet below the surface of the groundwater or mid-screen in each monitoring well. During purging, water quality was monitored using a Quanta or YSI water quality meter equipped with a flow-through cell. The water quality parameters that were monitored and recorded included temperature, pH, specific conductance, dissolved oxygen, turbidity, and oxidation-reduction potential. Each monitoring well was purged until a minimum subset of pH, specific conductivity, and dissolved oxygen and/or turbidity stabilized. Due to the depth to groundwater and the limited water column, injection well IW08 was sampled using a Waterra hand pump. No water quality parameters were recorded or measured from well IW08.

Following purging, groundwater samples were collected from the pump outlet tubing located upstream of the flow-through cell and placed directly into clean, laboratory-prepared sample containers. Each container was labeled with a unique sample identification number, placed on ice in a cooler, and transported to Friedman & Bruya, Inc., of Seattle, Washington, under standard chain-of-custody protocols for laboratory analysis.

The groundwater samples were submitted for analysis of chlorinated volatile organic compounds (CVOCs) by EPA Method 8260C. Purge water generated during the monitoring event was placed in an appropriately labeled 55-gallon steel drum and temporarily stored on the Property pending receipt of analytical data and proper disposal.

Groundwater Results

Groundwater levels measured on May 24, 2017, ranged from 22.23 (MW05) to 35.84 (IW08) feet below the top of the monitoring well casings (Table 1). Due to rerouting of the top of casings in several monitoring wells during construction activities, the groundwater elevations for the monitoring event were not calculated and contoured. Historically, the groundwater contours have indicated a general groundwater flow direction toward the southeast.

Groundwater analytical results from the monitoring event are summarized below (Figure 2; Table 1):

- A concentration of TCE exceeding the MTCA Method A cleanup level of 5 micrograms per liter (μg/L) was detected in the groundwater sample collected from monitoring well MW16A at 5.6 μg/L.
- All other CVOCs were below their respective laboratory reporting limits and/or MTCA Method A cleanup levels in the groundwater samples collected during the monitoring event.

DATA QUALITY REVIEW

SoundEarth performed a quality assurance/quality control (QA/QC) review of the analytical results, which included a review of accuracy and precision of the data supplied by the laboratory. All QA/QC criteria are acceptable for the groundwater samples, and the analytical results are considered usable to meet the project objectives. A copy of the laboratory analytical report is provided as Attachment A.

CONCLUSIONS AND RECOMMENDATIONS

The targeted chemical injection event in 2016 resulted in a decrease in TCE concentrations below the MTCA Method A cleanup level in groundwater monitoring wells across the Site. Concentrations of TCE in groundwater above the MTCA Method A cleanup level still remain in monitoring well MW16A. SoundEarth recommends additional quarterly sampling, including a groundwater monitoring event at the Site in Third Quarter 2017, the results of which will be included in a groundwater monitoring report. Continued quarterly monitoring should be conducted during 2017 to evaluate the need for an additional injection of chemical oxidation compounds.

CLOSING

SoundEarth appreciates this opportunity to provide AMLI Residential Partners with environmental consulting services. Please call either of the undersigned at 206-306-1900 if you have any questions or comments regarding the content of this report.

Respectfully,

SoundEarth Strategies, Inc.

Jonathan Loeffler, LG Project Geologist Rob Roberts
Senior Scientist

Attachments: Figure 1, Property Location Map


Figure 2, Post-Permanganate Injections Groundwater Analytical Results

Table 1, Summary of Groundwater Data

A, Laboratory Analytical Report

Friedman & Bruya, Inc. #705465

JSL/CER:dnm/hsb



LEGEND

PROPERTY BOUNDARY

KING COUNTY PARCEL BOUNDARY

2-FOOT CONTOUR INTERVAL

MAP SOURCES: Esri, DeLorme, NAVTEQ, TomTom, Intermap, increment P Corp., GEBCO, USGS,

FAO, NPS, NRCAN, GeoBase, IGN, Kadaster NL, Ordnance Survey, Esrl Japan, METI, Esrl China

(Hong Kong), swisstopo, and the GIS User Community





DATE: --08/30/13 DRAWN BY:--BLR CHECKED BY: --CER CAD FILE: --0789-004_FIG1 PROJECT NAME: FORMER AVTECH PROPERTY (AMLI WALLINGFORD PROJECT NUMBER:--0789-004-10 STREET ADDRESS: -3400 WALLINGFORD AVENUE NORTH CITY, STATE: -SEATTLE, WASHINGTON

LAKE UNION

FIGURE 1

PROPERTY LOCATION MAP







										1		Anal	lytical R	esults (
Sample ID and TOC Elevation	Sample Date	Depth to Groundwater ⁽¹⁾ (feet)	Groundwater Elevation ⁽²⁾ (feet)	окрн ⁽³⁾	ORPH ⁽³⁾	Benzene ⁽⁴⁾	Toluene ⁽⁴⁾	Ethylbenzene ⁽⁴⁾	Total Xylenes ⁽⁴⁾	Vinyl Chloride ⁽⁴⁾	cis-1,2-DCE ⁽⁴⁾	TCE ⁽⁴⁾	PCE ⁽⁴⁾	Naphthalene ⁽⁴⁾	Dissolved Chromium ⁽⁵⁾	Dissolved Arsenic ⁽⁵⁾	Dissolved Selenium ⁽⁵⁾	Dissolved Silver ⁽⁵⁾	Dissolved Cadmium ⁽⁵⁾	Dissolved Barium ⁽⁵⁾	Dissolved Lead ⁽⁵⁾	Dissolved Mercury ⁽⁶⁾	Total Manganese ⁽⁵⁾
MW01	01/17/12	27.59	56.85	<50	<250	< 0.35	<1	<1	<3	<0.2 ^{pr}	<1	<1	<1	<1	1.58	1.43	<1	<1	<1	3.94	<1	< 0.1	
84.44	05/01/12	25.02	59.42							<0.2	<1	<1	<1										
	01/11/13	26.25	58.19	-				-									-						
	04/25/13	24.75	59.69																				
	07/10/13	25.55	58.89																				
	10/10/13	27.43	57.01																				
	03/25/14	27.67	56.77							<0.2	<1	2.3	<1										
								Well I	Decomn	nissione	d On O	tober 2	9, 2014										
MW02	01/17/12	DRY																					
69.73	04/27/12	DRY																					
	01/11/13	DRY																					
	04/25/13	DRY																					
	07/10/13	DRY																					
	10/10/13	DRY																					
			ı	1		•			Decomn	nissione	1	tober 2	·				1	1	•				
MW03	01/17/12	DRY																					
75.48	04/27/12	31.18	44.30							<0.2	2.2	83	<1										
	05/08/12	31.06	44.42							<0.2	1.9	64	<1		1.69	1.44	<1	<1	<1	11.9	<1	<0.1	
	01/14/13	31.78	43.70							<0.2	1.7	71	<1										
	04/24/13	30.96	44.52							<0.2	1.8	76	<1										
	07/10/13 10/10/13										Inacces												
	06/29/15	36.15	39.33								macce:										l		
	09/14/15	30.13	39.33																				
	12/02/15	31.72	43.76																				
	02/18/16	31.10	44.38						<u> </u>														
	05/27/16	32.55	42.93																				
	12/27/16	34.48	41.00																				
MW04	01/17/12	36.70	42.77			<0.35	<1	<1	<3	<0.2 ^{pr}	<1	110	<1	<1	18.6	<1	<1	<1	<1	4.33	<1	<0.1	
79.47	04/27/12	36.09	43.38							<0.2	<1	170	<1							4.33			
, , , ,	01/11/13	36.44	43.03							<0.2	<1	85	<1										
	04/24/13	35.93	43.54							<0.2	<1	290	<1										
	07/10/13	36.15	43.32							<0.2	<1	150	<1										
	10/10/13	36.90	42.57																				
	06/29/15																						
	09/14/15																						
MW04 (Field Dup)	01/17/12	36.70	42.77			<0.35	<1	<1	<3	<0.2 ^{pr}	<1	120	<1	<1	18.6	<1	<1	<1	<1	4.65	<1	<0.1	
79.47	04/27/12	36.09	43.38							<0.2	<1	170	<1										
- * * *	06/29/15																						
	09/14/15																						
MTCA Method A Cle		or Groundwater ⁽⁷	7)	500	500	5	1,000	700	1.000	0.2	NE	5	5	160	50	5	NE	NE	5	NE	15	2	NE



												Ana	lytical R	esults (¡									
Sample ID and TOC Elevation	Sample Date	Depth to Groundwater ⁽¹⁾ (feet)	Groundwater Elevation ⁽²⁾ (feet)	DRPH ⁽³⁾	ОКРН ⁽³⁾	Benzene ⁽⁴⁾	Toluene ⁽⁴⁾	Ethylbenzene ⁽⁴⁾	Total Xylenes ⁽⁴⁾	Vinyl Chloride ⁽⁴⁾	cis-1,2-DCE ⁽⁴⁾	TCE ⁽⁴⁾	PCE ⁽⁴⁾	Naphthalene ⁽⁴⁾	Dissolved Chromium ⁽⁵⁾	Dissolved Arsenic ⁽⁵⁾	Dissolved Selenium ⁽⁵⁾	Dissolved Silver ⁽⁵⁾	Dissolved Cadmium ⁽⁵⁾	Dissolved Barium ⁽⁵⁾	Dissolved Lead ⁽⁵⁾	Dissolved Mercury ⁽⁶⁾	Total Manganese ⁽⁵⁾
MW05	01/17/12	24.90	30.71			<0.35	<1	<1	<3	<0.2 ^{pr}	<1	3.3	<1	<1	<1	5.31	3.55	<1	<1	22.6	<1	<0.1	
55.61	05/01/12	23.40	32.21							<0.2	<1	1.9	<1										
	01/14/13	24.34	31.27							<0.2	<1	3.3	<1										
	04/24/13	22.86	32.75							<0.2	<1	3.0	<1										
	07/10/13	23.71	31.90							<0.2	<1	1.9	<1										
	10/10/13	25.57	30.04							<0.2	1.1	8.2	<1										
	10/28/13									<0.2	1.1	8.4	<1										
	03/25/14	25.77	29.84							<0.2	2.1	9.9	<1										
	06/29/15	24.02	20.70							40.3	Inacces				l				l		l	l	
	09/14/15 12/03/15	24.82 25.24	30.79 30.37							<0.2	<1 2.8	<1 27	<1 <1										
	02/22/16	24.66	30.37							<0.2	2.5	23	<1										
	05/27/16	24.52	31.09							<0.2	2.5	21	<1										
	09/29/16	24.85	30.76							<0.2	<1	<1	<1										
	12/27/16	24.04	31.57							<0.2	<1	7.9	<1										
	03/21/17	22.95	32.66							<0.2	<1	<1	<1										
	05/24/17	22.23	33.38							<0.2	<1	<1	<1										
MW06	04/25/12	31.84	36.55							<0.2	<1	3.2	<1										
68.39	01/14/13	31.86	36.53							<0.2	<1	2.4	<1										
	04/26/13	30.85	37.54							<0.2	<1	4.5	<1										
	07/11/13	32.01	36.38							<0.2	<1	3.2	<1										
	10/11/13	33.61	34.78							<0.2	<1	<1	<1										
	04/17/14									<0.2	<1	3.9	<1										
			•			•		Well I	Decomn	nissione	d On O	tober 2	9, 2014	•	•	•		•	•	•			
MW07	04/25/12	37.43	39.35		-					<0.2	<1	3.3	<1										
76.78	01/11/13	37.59	39.19	-	ŀ					<0.2	<1	3.5	<1										
	04/25/13	36.52	40.26							<0.2	<1	6.1	<1										
[07/11/13	36.97	39.81							<0.2	<1	11	<1										
	10/10/13	37.97	38.81							<0.2	<1	6.5	<1										
	03/25/14	38.32	38.46							<0.2	<1	6.4	<1										
			,					Well	Decomn			tober 2	·										
MW08	04/25/12	37.86	38.75							<0.2	<1	<1	<1										
76.61	01/11/13	37.34	39.27																				
	04/25/13										Inacces												
	07/10/13										Inacces												
	10/10/13				_			!	_		Inacces		0 204 -	_									
										·	I	tober 2	r	1	1	1	1	1	1				
MTCA Method A Cle	anup Level f	for Groundwater'	,	500	500	5	1,000	700	1,000	0.2	NE	5	5	160	50	5	NE	NE	5	NE	15	2	NE



												Ana	lytical R	esults (µ	ıg/L)								
Sample ID and TOC Elevation	Sample Date	Depth to Groundwater ⁽¹⁾ (feet)	Groundwater Elevation ⁽²⁾ (feet)	DRPH ⁽³⁾	ORPH ⁽³⁾	Benzene ⁽⁴⁾	Toluene ⁽⁴⁾	Ethylbenzene ⁽⁴⁾	Total Xylenes ⁽⁴⁾	Vinyl Chloride ⁽⁴⁾	cis-1,2-DCE ⁽⁴⁾	TCE ⁽⁴⁾	PCE ⁽⁴⁾	Naphthalene ⁽⁴⁾	Dissolved Chromium ⁽⁵⁾	Dissolved Arsenic ⁽⁵⁾	Dissolved Selenium ⁽⁵⁾	Dissolved Silver ⁽⁵⁾	Dissolved Cadmium ⁽⁵⁾	Dissolved Barium ⁽⁵⁾	Dissolved Lead ⁽⁵⁾	Dissolved Mercury ⁽⁶⁾	Total Manganese ⁽⁵⁾
MW09	05/01/12	23.19	57.98							<0.2	<1	2.0	<1										
81.17	01/14/13	24.00	57.17							<0.2	1.5	42	<1										
	04/24/13	22.87	58.30							<0.2	<1	24	<1		-	-	-	-	-				
	07/10/13	23.65	57.52							<0.2	<1	36	<1		-		1	-					
	10/10/13	25.52	55.65							<0.2	1.5	43	<1				-	-					
	03/25/14	25.72	55.45	-						<0.2	2.4	51	<1		-		-		-		-		
								Well I	Decomn	nissione	d On O	tober 2	9, 2014										
MW10	05/01/12	21.90	63.60							<0.2	<1	<1	<1										
85.50	01/11/13	22.56	62.94																				
	04/25/13	21.49	64.01																				
	07/10/13	22.63	62.87																				
	10/10/13	24.75	60.75																				
	03/25/14	24.82	60.68							<0.2	<1	<1	<1										
								Well I	Decomm	nissione	d On O	tober 2	9, 2014										
MW11	04/30/12	44.56	34.24							<0.2	<1	14	<1										
78.80	05/08/12	44.52	34.28							<0.2	<1	29	<1										
	01/11/13	44.74	34.06							<0.2	<1	78	<1				-						
	04/25/13	43.56	35.24							<0.2	<1	39	<1										
	07/10/13	43.90	34.90							<0.2	<1	56	<1										
	10/10/13	44.59	34.21							<0.2	<1	35	<1										
	03/25/14	44.86	33.94							<0.2	<1	48	<1										
	06/29/15	41.43	37.37																				
	09/14/15	42.24	36.56										Inacce	essible									
	12/03/15	42.40	36.40							<0.2	<1	16	<1				-						
	02/18/16	41.15	37.65																				
	05/27/16												Inacce	essible									
MW11D	04/30/14	43.74	NS							<0.2	<1	<1	<1										
76.01	06/29/15	44.25	31.76							<0.2	<1	<1	<1										
	09/15/15	44.65	31.36							<0.2	<1	<1	<1										
	12/03/15	43.71	32.30							<0.2	<1	<1	<1										
	02/18/16	43.18	32.83							<0.2	<1	<1	<1										
	05/27/16	42.59	33.42							<0.2	<1	<1	<1										
MTCA Method A Cle	anup Level 1	for Groundwater ⁽⁷	7)	500	500	5	1,000	700	1,000	0.2	NE	5	5	160	50	5	NE	NE	5	NE	15	2	NE



												Anal	ytical R	esults (բ	ıg/L)								
Sample ID and TOC Elevation	Sample Date	Depth to Groundwater ⁽¹⁾ (feet)	Groundwater Elevation ⁽²⁾ (feet)	DRPH ⁽³⁾	ORPH ⁽³⁾	Benzene ⁽⁴⁾	Toluene ⁽⁴⁾	Ethylbenzene ⁽⁴⁾	Total Xylenes ⁽⁴⁾	Vinyl Chloride ⁽⁴⁾	cis-1,2-DCE ⁽⁴⁾	TCE ⁽⁴⁾	PCE ⁽⁴⁾	Naphthalene ⁽⁴⁾	Dissolved Chromium ⁽⁵⁾	Dissolved Arsenic ⁽⁵⁾	Dissolved Selenium ⁽⁵⁾	Dissolved Silver ⁽⁵⁾	Dissolved Cadmium ⁽⁵⁾	Dissolved Barium ⁽⁵⁾	Dissolved Lead ⁽⁵⁾	Dissolved Mercury ⁽⁶⁾	Total Manganese ⁽⁵⁾
MW12	04/27/12	32.81	49.02							<0.2	<1	14	<1										
81.83	01/14/13	33.30	48.53							<0.2	<1	5.0	<1										
	04/25/13	32.76	49.07							<0.2	<1	5.7	<1										
	07/10/13	33.08	48.75							<0.2	<1	10	<1										
	10/10/13	32.95	48.88																				
	06/29/15	32.89	48.94							<0.2	<1	2.9	<1										
	09/15/15	33.70	48.13							<0.2	<1	13	<1										
	12/03/15	33.74	48.09							<0.2	<1	15	<1										
	02/18/16	31.96	49.87							<0.2	<1	9.1	<1										
	05/27/16	32.36	49.47							<0.2	<1	9.2	<1										
	09/29/16	34.10	47.73							<0.2	<1	<1	<1										
	12/27/16	33.09	48.74							<0.2	<1	<1	<1										
	03/21/17	32.03	49.80							<0.2	<1	<1	<1										
	05/25/17	31.90	49.93							<0.2	<1	<1	<1										
MW13	04/27/12	34.97	43.97	-		ŀ			-	<0.2	<1	1.0	<1	1	-	-	ı			ı	-		
78.94	05/07/12	34.94	44.00							<0.2	<1	2.0	<1										
	04/24/13	34.88	44.06			-				<0.2	<1	2.5	<1				-			-			
	07/10/13	35.15	43.79							<0.2	<1	37	<1										
	10/10/13	35.73	43.21						-	-				-									-
	06/29/15					-	-		-	-				-			-						-
	09/14/15								-	1				-									-
	02/18/16									-				-									
	05/27/16						-			-				-			-						-
	12/27/16	39.67	39.27	-		-				-			-	-	-	-	-			-	-		
MW14	04/30/12	29.99	54.61						-	<0.2	<1	<1	<1	-	-		-			-			
84.60	01/11/13	30.95	53.65	-		-	-		-	1			-	1	1	1	-			-	-		
	04/25/13										Inacces	ssible				-					-		
	07/10/13	30.56	54.04																				
	10/10/13	32.00	52.60						-	-													
	06/29/15	32.00	52.60							-													
	09/14/15	33.18	51.42										Inacce	essible									•
	02/18/16										Inacces	ssible											
	05/27/16	31.35	53.25																				
MTCA Method A Cle	anup Level 1	or Groundwater (7	7)	500	500	5	1,000	700	1,000	0.2	NE	5	5	160	50	5	NE	NE	5	NE	15	2	NE



												Ana	lytical R	esults (µ									
Sample ID and TOC Elevation	Sample Date	Depth to Groundwater ⁽¹⁾ (feet)	Groundwater Elevation ⁽²⁾ (feet)	окрн ⁽³⁾	ОКРН ⁽³⁾	Benzene ⁽⁴⁾	Toluene ⁽⁴⁾	Ethylbenzene ⁽⁴⁾	Total Xylenes ⁽⁴⁾	Vinyl Chloride ⁽⁴⁾	cis-1,2-DCE ⁽⁴⁾	TCE ⁽⁴⁾	PCE ⁽⁴⁾	Naphthalene ⁽⁴⁾	Dissolved Chromium ⁽⁵⁾	Dissolved Arsenic ⁽⁵⁾	Dissolved Selenium ⁽⁵⁾	Dissolved Silver ⁽⁵⁾	Dissolved Cadmium ⁽⁵⁾	Dissolved Barium ⁽⁵⁾	Dissolved Lead ⁽⁵⁾	Dissolved Mercury ⁽⁶⁾	Total Manganese ⁽⁵⁾
MW15	04/30/12	27.37	38.72				-			<0.2	<1	<1	<1									-	-
66.09	01/14/13	27.76	38.33							<0.2	<1	<1	<1										
	04/24/13	26.69	39.40	-				-		<0.2	<1	<1	<1		-								
	07/10/13										Inacces	sible											
	10/28/13	28.02	38.07							<0.2	<1	<1	<1										
	04/16/14	28.38	37.71				-			<0.2	<1	<1	<1										-
	06/29/15	32.76	33.33				-	-		1											-		-
	09/14/15	29.14	36.95					-		-					-								
	12/03/15	29.65	36.44				-			<0.2	<1	<1	<1		-								-
	02/18/16	28.75	37.34				-	-		1											-		-
	05/27/16	29.11	36.98				-			<0.2	<1	<1	<1										-
	12/27/16	28.45	37.64				-			-					-								-
MW16	04/16/14	40.18	NS			-		-		<0.2	<1	<1	<1				-						
							Well D	Destroy	ed By Ea	rthworl	Const	ruction:	Februa	ry 2015									
MW16A	06/29/15	34.78								<0.2	<1	<1	<1										
81.97 ⁽⁸⁾	09/30/15									<0.2	<1	3.0	<1										
	12/03/15	37.09	44.88							<0.2	<1	<1	<1										
	02/18/16	36.06	45.91				-	-		<0.2	<1	<1	<1								-		-
	05/27/16	36.60	45.37					-		<0.2	<1	9.7	<1		-								
	09/29/16	35.01	46.96	-		-		ı		<0.2	<1	6.4	<1		1		-						
	12/27/16	34.00	47.97							<0.2	<1	20	<1										
	03/21/17	33.71	48.26					-		<0.2	<1	3.5	<1		-								
	05/25/17	33.70	48.27							<0.2	<1	5.6	<1										
MW17	06/29/15	12.51	31.44							<0.2	<1	<1	<1										
43.95	07/17/15																						276
	09/14/15	13.36	30.59							<0.2	<1	1.2	<1										8.10
	12/03/15	12.83	31.12																				3.00
	02/22/16	11.15	32.80							<0.2	<1	<1	<1										
	05/27/16	12.00	31.95							<0.2	<1	<1	<1										
	12/27/16										Inacces	sible											
MW18	06/29/15	32.76	39.67							<0.2	4.9	46	<1										
72.43	07/16/15																						251
	09/15/15	33.94	38.49							<0.2	5.1	45	<1										25.6
	12/03/15	34.00	38.43							<0.2	8.2	69	<1										35.6
	02/19/16	33.31	39.12							<0.2	5.1	50	<1										
	05/27/16	31.98	40.45							<0.2	4.2	36	<1										
	09/29/16	33.06	39.37							<0.2	4.4	41	<1										
	12/27/16	32.18	40.25							<0.2	<1	<1	<1										
	03/21/17	31.82	40.61			-				<0.2	<1	<1	<1				-						
	05/25/17	30.50	41.93			-				<0.2	<1	<1	<1				-						
MTCA Method A Cle	anup Level f	or Groundwater ⁽⁷	1	500	500	5	1,000	700	1,000	0.2	NE	5	5	160	50	5	NE	NE	5	NE	15	2	NE



												Ana	lytical R	esults (բ	ıg/L)								
Sample ID and TOC Elevation	Sample Date	Depth to Groundwater ⁽¹⁾ (feet)	Groundwater Elevation ⁽²⁾ (feet)	DRPH ⁽³⁾	ORPH ⁽³⁾	Benzene ⁽⁴⁾	Toluene ⁽⁴⁾	Ethylbenzene ⁽⁴⁾	Total Xylenes ⁽⁴⁾	Vinyl Chloride ⁽⁴⁾	cis-1,2-DCE ⁽⁴⁾	TCE ⁽⁴⁾	PCE ⁽⁴⁾	Naphthalene ⁽⁴⁾	Dissolved Chromium ⁽⁵⁾	Dissolved Arsenic ⁽⁵⁾	Dissolved Selenium ⁽⁵⁾	Dissolved Silver ⁽⁵⁾	Dissolved Cadmium ⁽⁵⁾	Dissolved Barium ⁽⁵⁾	Dissolved Lead ⁽⁵⁾	Dissolved Mercury ⁽⁶⁾	Total Manganese ⁽⁵⁾
IW01	04/16/14	24.90	NS							<0.2	<1	<1	<1										
								Well I	Decomm	nissione	d On Fe	bruary	3, 2015										
IW02	04/16/14	36.91	NS							<0.2	<1	<1	<1										
							Well D	Destroy	ed By Ea	rthwork	Consti	ruction:	Februai	y 2015									
IW03	04/16/14	33.20	NS							<0.2	<1	17	<1										
IW04	04/16/14	30.05	NS							<0.2	<1	44	<1										
								Well	Decom		ed On N	March 9	, 2015										
IW05	04/16/14	30.29	NS							<0.2	<1	<1	<1										
IW06	04/16/14	28.75	NS							<0.2	<1	<1	<1										
								Well I	Decomm		d On Fe	bruary	5, 2015										
IW08	07/16/15		NS							<0.2	<1	<1	<1										
75.90	09/15/15	35.54	40.36							<0.2	<1	5.7	<1										
	12/03/15	35.34	40.56							<0.2	<1	16	<1										
	02/19/16	35.00	40.90							<0.2	<1	15	<1										
	05/27/16	35.55	40.35							<0.2	<1	7.2	<1										
	10/24/16	38.73	37.17							<0.2	<1	<1	<1										
	12/27/16	35.99	39.91																				
	03/21/17	35.79	40.11							<0.2	<1	<1	<1										
	05/24/17	35.84	40.06							<0.2	<1	1.6	<1										
MTCA Method A Cle	anup Level 1	for Groundwater ⁽⁷	7)	500	500	5	1,000	700	1,000	0.2	NE	5	5	160	50	5	NE	NE	5	NE	15	2	NE

NOTES:

Red denotes concentrations exceeding the MTCA Method A Cleanup Level.

Sample analyses conducted by Friedman & Bruya, Inc. of Seattle, Washington.

TOC elevations surveyed by Triad Associates on May 3, 2012.

-- = not analyzed/not measured

< = not detected at a concentration exceeding the laboratory reporting limit

μg/L = micrograms per liter

 $cis\text{-}1,2\text{-}DCE = cis\text{-}1,2\text{-}dichloroethene}$

DRPH = diesel-range petroleum hydrocarbons

EPA = U.S. Environmental Protection Agency

MTCA = Washington State Model Toxics Control Act

NAVD88 = North American Vertical Datum of 1988

NE = no MTCA Method A cleanup level established for this analyte

NS = well casing not surveyed

NWTPH = Northwest Total Petroleum Hydrocarbon

ORPH = oil-range petroleum hydrocarbons

 $\mbox{PCE} = tetrachloroethene$

TCE = trichloroethene

TOC = top of casing elevation

 $[\]ensuremath{^{(1)}}\text{Measured}$ in feet below a fixed spot on the top of the well casing rim.

⁽²⁾ Elevation datum NAVD88, Seattle BM#2609CC 58A at 60.344' and BM#2609CC 55A at 32.066'.

⁽³⁾Analyzed by Method NWTPH-Dx.

 $^{^{(4)}}$ Analyzed by EPA Method 8260C. All other 8260C analytes were not detected above the laboratory reporting limit.

 $^{^{\}rm (5)}\!\mbox{Analyzed}$ by EPA Method 6020 or 200.8.

⁽⁶⁾Analyzed by EPA Method 1631E.

⁽⁷⁾MTCA Cleanup Regulation, Method A Cleanup Levels, Table 720-1 of Section 900 of Chapter 340 of Title 173 of the Washington Administrative Code, revised November 2007.

⁽⁸⁾ Well casing was repaired, extended-up, and surveyed after the Third Quarter 2015 groundwater sampling event was performed. Laboratory Note:

^{pr}Sample received with incorrect preservation. Results should be considered an estimate.

ATTACHMENT A LABORATORY ANALYTICAL REPORT

Friedman & Bruya, Inc. #705465

ENVIRONMENTAL CHEMISTS

James E. Bruya, Ph.D. Yelena Aravkina, M.S. Michael Erdahl, B.S. Arina Podnozova, B.S. Eric Young, B.S. 3012 16th Avenue West Seattle, WA 98119-2029 (206) 285-8282 fbi@isomedia.com www.friedmanandbruya.com

June 1, 2017

Rob Roberts, Project Manager SoundEarth Strategies 2811 Fairview Ave. East, Suite 2000 Seattle. WA 98102

Dear Mr Roberts:

Included are the results from the testing of material submitted on May 25, 2017 from the SOU_0789-004_ 20170525, F&BI 705465 project. There are 9 pages included in this report. Any samples that may remain are currently scheduled for disposal in 30 days. If you would like us to return your samples or arrange for long term storage at our offices, please contact us as soon as possible.

We appreciate this opportunity to be of service to you and hope you will call if you should have any questions.

Sincerely,

FRIEDMAN & BRUYA. INC.

Michael Erdahl Project Manager

Enclosures c: Jonathan Loeffler SOU0601R.DOC

ENVIRONMENTAL CHEMISTS

CASE NARRATIVE

This case narrative encompasses samples received on May 25, 2017 by Friedman & Bruya, Inc. from the SoundEarth Strategies SOU_0789-004_ 20170525, F&BI 705465 project. Samples were logged in under the laboratory ID's listed below.

<u>Laboratory ID</u>	SoundEarth Strategies
705465 -01	MW05-20170524
705465 -02	IW08-20170524
705465 -03	MW18-20170525
705465 -04	MW12-20170525
705465 -05	MW16A-20170525

All quality control requirements were acceptable.

ENVIRONMENTAL CHEMISTS

Analysis For Volatile Compounds By EPA Method 8260C

Client Sample ID:	MW05-20170524	Client:	SoundEarth Strategies
Date Received:	05/25/17	Project:	SOU_0789-004_ 20170525
Date Extracted:	05/26/17	Lab ID:	705465-01
Date Analyzed:	05/26/17	Data File:	052622.D
Matrix:	Water	Instrument:	GCMS4
Units:	ug/L (ppb)	Operator:	VM

		Lower	∪pper
Surrogates:	% Recovery:	Limit:	Limit:
1,2-Dichloroethane-d4	102	57	121
Toluene-d8	106	63	127
4-Bromofluorobenzene	99	60	133

Compounds:	Concentration ug/L (ppb)
Vinyl chloride	< 0.2
Chloroethane	<1
1,1-Dichloroethene	<1
Methylene chloride	<5
trans-1,2-Dichloroethene	<1
1,1-Dichloroethane	<1
cis-1,2-Dichloroethene	<1
1,2-Dichloroethane (EDC)	<1
1,1,1-Trichloroethane	<1
Trichloroethene	<1
Tetrachloroethene	<1

ENVIRONMENTAL CHEMISTS

Analysis For Volatile Compounds By EPA Method 8260C

IW08-20170524 Client Sample ID: Client: SoundEarth Strategies Date Received: Project: SOU_0789-004_ 20170525 05/25/17 Lab ID: 705465-02 Date Extracted: 05/26/17 Date Analyzed: 05/26/17 Data File: 052623.D Instrument: Matrix: Water GCMS4 Units: ug/L (ppb) Operator: VM

		Lower	Upper
Surrogates:	% Recovery:	Limit:	Limit:
1,2-Dichloroethane-d4	102	57	121
Toluene-d8	106	63	127
4-Bromofluorobenzene	99	60	133

Concentration Compounds: ug/L (ppb) Vinyl chloride < 0.2 Chloroethane <1 1,1-Dichloroethene <1 Methylene chloride < 5 trans-1,2-Dichloroethene <1 1.1-Dichloroethane <1 cis-1,2-Dichloroethene <1 1,2-Dichloroethane (EDC) <1 1,1,1-Trichloroethane <1 Trichloroethene 1.6 Tetrachloroethene <1

ENVIRONMENTAL CHEMISTS

Analysis For Volatile Compounds By EPA Method 8260C

Client Sample ID:	MW18-20170525	Client:	SoundEarth Strategies
Date Received:	05/25/17	Project:	SOU_0789-004_ 20170525
Date Extracted:	05/26/17	Lab ID:	705465-03
Date Analyzed:	05/26/17	Data File:	052624.D
Matrix:	Water	Instrument:	GCMS4
Units:	ug/L (ppb)	Operator:	VM

		Lower	∪pper
Surrogates:	% Recovery:	Limit:	Limit:
1,2-Dichloroethane-d4	102	57	121
Toluene-d8	105	63	127
4-Bromofluorobenzene	97	60	133

Compounds:	Concentration ug/L (ppb)
Vinyl chloride	< 0.2
Chloroethane	<1
1,1-Dichloroethene	<1
Methylene chloride	<5
trans-1,2-Dichloroethene	<1
1,1-Dichloroethane	<1
cis-1,2-Dichloroethene	<1
1,2-Dichloroethane (EDC)	<1
1,1,1-Trichloroethane	<1
Trichloroethene	<1
Tetrachloroethene	<1

ENVIRONMENTAL CHEMISTS

Analysis For Volatile Compounds By EPA Method 8260C

Client Sample ID: MW12-20170525 Client: SoundEarth Strategies Date Received: Project: SOU_0789-004_ 20170525 05/25/17 05/26/17 Lab ID: 705465-04 Date Extracted: Date Analyzed: 05/26/17 Data File: 052625.D Matrix: Instrument: Water GCMS4 Units: ug/L (ppb) Operator: VM

		Lower	Upper
Surrogates:	% Recovery:	Limit:	Limit:
1,2-Dichloroethane-d4	103	57	121
Toluene-d8	105	63	127
4-Bromofluorobenzene	100	60	133

Concentration Compounds: ug/L (ppb) Vinyl chloride < 0.2 Chloroethane <1 1,1-Dichloroethene <1 Methylene chloride < 5 trans-1,2-Dichloroethene <1 1.1-Dichloroethane <1 cis-1,2-Dichloroethene <1 1,2-Dichloroethane (EDC) <1 1,1,1-Trichloroethane <1 Trichloroethene <1 Tetrachloroethene <1

ENVIRONMENTAL CHEMISTS

Analysis For Volatile Compounds By EPA Method 8260C

Client Sample ID:	MW16A-20170525	Client:	SoundEarth Strategies
Date Received:	05/25/17	Project:	SOU_0789-004_ 20170525
Date Extracted:	05/26/17	Lab ID:	705465-05

Date Extracted: 05/26/17 Lab ID: 705465-05
Date Analyzed: 05/26/17 Data File: 052626.D
Matrix: Water Instrument: GCMS4
Units: ug/L (ppb) Operator: VM

		Lower	∪pper
Surrogates:	% Recovery:	Limit:	Limit:
1,2-Dichloroethane-d4	102	57	121
Toluene-d8	105	63	127
4-Bromofluorobenzene	97	60	133

1 Bromondorobenzene	01
Compounds:	Concentration ug/L (ppb)
Vinyl chloride	< 0.2
Chloroethane	<1
1,1-Dichloroethene	<1
Methylene chloride	<5
trans-1,2-Dichloroethene	<1
1,1-Dichloroethane	<1
cis-1,2-Dichloroethene	<1
1,2-Dichloroethane (EDC)	<1
1,1,1-Trichloroethane	<1
Trichloroethene	5.6
Tetrachloroethene	<1

ENVIRONMENTAL CHEMISTS

Analysis For Volatile Compounds By EPA Method 8260C

Client Sample ID: Method Blank Client: SoundEarth Strategies Date Received: Project: SOU_0789-004_ 20170525 Not Applicable 05/26/17 Lab ID: 07-1045 mb Date Extracted: Date Analyzed: 05/26/17 Data File: 052616.D Instrument: Matrix: Water GCMS4 Units: ug/L (ppb) Operator: VM

		Lower	Upper
Surrogates:	% Recovery:	Limit:	Limit:
1,2-Dichloroethane-d4	100	57	121
Toluene-d8	106	63	127
4-Bromofluorobenzene	99	60	133

Concentration Compounds: ug/L (ppb) Vinyl chloride < 0.2 Chloroethane <1 1,1-Dichloroethene <1 Methylene chloride < 5 trans-1,2-Dichloroethene <1 1.1-Dichloroethane <1 cis-1,2-Dichloroethene <1 1,2-Dichloroethane (EDC) <1 1,1,1-Trichloroethane <1 Trichloroethene <1 Tetrachloroethene <1

ENVIRONMENTAL CHEMISTS

Date of Report: 06/01/17 Date Received: 05/25/17

Project: SOU_0789-004_20170525, F&BI 705465

QUALITY ASSURANCE RESULTS FOR THE ANALYSIS OF WATER SAMPLES FOR VOLATILES BY EPA METHOD 8260C

Laboratory Code: Laboratory Control Sample

			Percent	Percent		
	Reporting	Spike	Recovery	Recovery	Acceptance	RPD
Analyte	Units	Level	LCS	LCSD	Criteria	(Limit 20)
Vinyl chloride	ug/L (ppb)	50	81	84	50-154	4
Chloroethane	ug/L (ppb)	50	94	96	58-146	2
1,1-Dichloroethene	ug/L (ppb)	50	89	95	67-136	7
Methylene chloride	ug/L (ppb)	50	87	95	39-148	9
trans-1,2-Dichloroethene	ug/L (ppb)	50	88	94	68-128	7
1,1-Dichloroethane	ug/L (ppb)	50	82	87	79-121	6
cis-1,2-Dichloroethene	ug/L (ppb)	50	86	91	80-123	6
1,2-Dichloroethane (EDC)	ug/L (ppb)	50	90	94	73-132	4
1,1,1-Trichloroethane	ug/L (ppb)	50	91	96	83-130	5
Trichloroethene	ug/L (ppb)	50	87	91	80-120	4
Tetrachloroethene	ug/L (ppb)	50	87	90	76-121	3

ENVIRONMENTAL CHEMISTS

Data Qualifiers & Definitions

- a The analyte was detected at a level less than five times the reporting limit. The RPD results may not provide reliable information on the variability of the analysis.
- b The analyte was spiked at a level that was less than five times that present in the sample. Matrix spike recoveries may not be meaningful.
- ca The calibration results for the analyte were outside of acceptance criteria. The value reported is an estimate.
- c The presence of the analyte may be due to carryover from previous sample injections.
- cf The sample was centrifuged prior to analysis.
- d The sample was diluted. Detection limits were raised and surrogate recoveries may not be meaningful.
- dv Insufficient sample volume was available to achieve normal reporting limits.
- f The sample was laboratory filtered prior to analysis.
- fb The analyte was detected in the method blank.
- fc The compound is a common laboratory and field contaminant.
- hr The sample and duplicate were reextracted and reanalyzed. RPD results were still outside of control limits. Variability is attributed to sample inhomogeneity.
- hs Headspace was present in the container used for analysis.
- ht The analysis was performed outside the method or client-specified holding time requirement.
- ip Recovery fell outside of control limits. Compounds in the sample matrix interfered with the quantitation of the analyte.
- j The analyte concentration is reported below the lowest calibration standard. The value reported is an estimate.
- J The internal standard associated with the analyte is out of control limits. The reported concentration is an estimate.
- jl The laboratory control sample(s) percent recovery and/or RPD were out of control limits. The reported concentration should be considered an estimate.
- js The surrogate associated with the analyte is out of control limits. The reported concentration should be considered an estimate.
- lc The presence of the analyte is likely due to laboratory contamination.
- L The reported concentration was generated from a library search.
- nm The analyte was not detected in one or more of the duplicate analyses. Therefore, calculation of the RPD is not applicable.
- pc The sample was received with incorrect preservation or in a container not approved by the method. The value reported should be considered an estimate.
- ve The analyte response exceeded the valid instrument calibration range. The value reported is an estimate.
- vo The value reported fell outside the control limits established for this analyte.
- x The sample chromatographic pattern does not resemble the fuel standard used for quantitation.

70546	5
Send Report to	Rob R

SAMPLE CHAIN OF CUSTODY

REMARKS

ME 05/25/17
Page#

VW2

Send Report to	Dala Dalameta	T1	теп.
sena neport to	noo noberts.	cc: Jonathan	Loemer

Company SoundEarth Strategies, Inc.

Address 2811 Fairview Avenue E, Suite 2000

City, State, ZIP Seattle, Washington 98102

Phone # 206-306-1900 Fax # 206-306-1907

PROJECT NAME/NO. PO#

AMLI – AvTech / 0789-004

TURNAROUND TIME
Standard (2 Weeks)
RUSH
Rush charges authorized by:

SAMPLE DISPOSAL
Dispose after 30 days
Return samples
Will call with instructions

				· · · · · · · · · · · · · · · · · · ·					,		Al	VALYSE	S REQU	JESTED)	
Sample ID	Sample Location	Sample Depth	Lab ID	Date Sampled	Time Sampled	Matrix	# of Jars	NWTPH-D _x	NWTPH-Gx	BTEX by 8021B	CVOCs by 8260	Total Manganese by 200.8		THE THE PROPERTY OF THE PROPER	Property and the second	Notes
MW05-20170524 Ilvob-20170524 MW18-20170525	MW05		OIAC	5/24/17	1650	WATER	. 3				X				ļ	and add the control of the control o
IWO8-20170524	IWO8		OR T	5/24/17	1710		3				×					
MW18-20170525	MW18		03	5/25/17	1300		3		4.4		X					
MW12-20170525	MW12		đư	5/25/17	1448		3				X					
MW6A20170525	MW16A		07	5/25/17	194)		3				Х					
								() g	1.							
				The state of the s				TH	7-	5/25	47					
								70	1					-	<u> </u>	
		:														

Friedman & Bruya, Inc. 3012 16th Avenue West Seattle, WA 98119-2029 Ph. (206) 285-8282

Received by:		Samples received a	4 °C	
Relinquished by:		1 22	7	1000
Received by:	Dovo	FEBZ	T-2 T-14	-16.20
Relinquished by	JONATHAN LOEFFLER	SOUNDEARTH	5/25/17	1620
SIGNATURE	PRINT NAME	COMPANY	DATE	TIME

FORMS\COC\COC.DOC

Fax (206) 283-5044