

Independent Soil Remediation Smudge Pot Storage Area

Ranch 19 East 441 Williamson Road Sunnyside, Washington

Project Number: 192902.15


January 5, 2021

Prepared for:

WA LAND MGMT, LLC c/o: Guy Kisling 22605 Southeast 56th Street #200 Issaquah, Washington 98029

Prepared by:

Fulcrum Environmental Consulting, Inc. 406 North 2nd Street Yakima, Washington 98901





Report Title: Independent Soil Remediation, Smudge Pot Storage Area

Project Number: 192902.15

Date: January 5, 2021

Site: Ranch 19 East

441 Williamson Road, Sunnyside, Washington GPS coordinates: 46°24'11.19"N, 120° 0'0.49"W

Prepared for: WA LAND MGMT, LLC


c/o: Guy Kisling

22605 Southeast 56th Street #200 Issaquah, Washington 98029

Prepared by: Fulcrum Environmental Consulting, Inc.

406 North Second Street Yakima, Washington 98901

509.574.0839



The professionals who completed site services, prepared, and reviewed this report include but are not limited to:

Authored by:

Date: 1/5/2021

Nicole McPhee, Environmental Technician Fulcrum Environmental Consulting, Inc.

Reviewed by:

Date: 1/5/202

Jeremy M. Lynn, LHG, PMP, Hydrogeologist Fulcrum Environmental Consulting, Inc.

Report Integrity:

Fulcrum Environmental Consulting, Inc.'s scope of service for this project was limited to those services as established in the proposal, contract, verbal direction, and/or agreement. This report is subject to applicable federal, state, and local regulations governing project-specific conditions and was performed using recognized procedures and standards of the industry. Scientific data collected in situ may document conditions that may be specific to the time and day of service, and subject to change as a result of conditions beyond Fulcrum's control or knowledge. Fulcrum makes no warranties, expressed or implied as to the accuracy or completeness of other's work included herein. Fulcrum has performed these services in accordance with generally accepted environmental science standards of care at the time of the inspection. No warranty, expressed or implied, is made.



TABLE OF CONTENTS

SECTION	ON	PAGE
1.0	Introduction	1
2.0	Scope of Work	2
3.0	Discussion of Pertinent Regulations and Guidance	2
	3.1 MTCA Regulations	
	3.2 Cleanup Standard Selected	3
	3.3 Sampling Guidance Criteria	3
4.0	Environmental Setting	
	4.1 Regional Setting	4
	4.2 Local Geologic Setting	5
5.0	Site Activities	
	5.1 Initial Investigation and Waste Characterization	5
	5.2 Remedial Excavation	8
6.0	Laboratory Results	9
7.0	Soil Treatment	10
8.0	Discussion	11
	8.1 PAH Screening Analysis	11
	8.2 Terrestrial Ecological Evaluation	11
9.0	Conclusions	
10.0	Limitations	12



TABLES

Table 1: Waste Characterization Laboratory Results	6
Table 2: Field Screening – October 22, 26, 27, and 28, 2020	
Table 3: Former Smudge Pot Storage Area Laboratory Results	9

FIGURES

Figure 1 Site Location
Figure 2 Remediation Area
Figure 3 Sample Location
Figure 4 TEE Acreage

APPENDICES


Appendix A
 Appendix B
 Appendix C
 Appendix C
 Appendix D
 Appendix D
 Appendix E
 Appendix E
 Appendix E
 Appendix F
 TEE Form



1.0 Introduction

Fulcrum Environmental Consulting, Inc. (Fulcrum) was retained by WA LAND MGMT, LLC to complete site characterization and remediation of one area of suspected petroleum contaminated soil (PCS) associated with historical smudge pot storage. See Figure 1 for the site location.

Ranch 19 is located at 441 Williamson Road in Sunnyside, Washington. The former smudge pot area is located at coordinates 46°24'11.19"N, 120°0'0.49"W in Township 11N, Range 22E, Section 36, Yakima County, Washington. The former smudge pot storage area is located north of Washout Road in the northeast portion of the ranch. A second area of PCS associated with smudge pot storage is located in the western



General Site Location – See Figure 2

portion of the ranch just north of Williamson Road and is reported under separate cover. The site addressed in this report is referred to as Ranch 19 East. The site and surrounding area land-use consists of arable land, typically utilized as orchards or other crop use.

During a Phase I Environmental Site Assessment (ESA) site walk performed on behalf of a prospective buyer, visibly stained soils were observed in the smudge pot storage area. The prospective buyer notified WA LAND MGMT, LLC and requested additional investigation and remediation if necessary.

Fulcrum completed limited Phase II investigation activities at the site to evaluate constituents of concern and to approximate extents of impact and soil volumes. The investigation identified localized diesel fuel contamination at the site. The site was reported to the Washington State Department of Ecology (Ecology) on December 19, 2019 under the letter *Release Reporting at a Former Smudge Pot Storage Area – Ranch 19 East, 441 Williamson Road, Sunnyside, Washington.* Site remediation of the identified PCS occurred on October 22 to October 28, 2020.

See Section 5.0 for a summary of the site activities. See Figure 2 for the former smudge pot storage location. See Figure 3 for sampling locations.

All investigation and remediation activities were completed as provided in The Model Toxics Control Act (MTCA), Washington Administrative Code (WAC) 173-340. In our professional opinion, the use of the independent remediation process is appropriate.



2.0 Scope of Work

Fulcrum's scope of services consisted of the following tasks:

- Complete initial investigation and waste characterization sampling of suspect contaminated soils.
- Complete waste characterization evaluation and request for offsite treatment or disposal.
- Direct excavation of petroleum contaminated soils.
- Collect confirmatory samples at the excavation extents for identified contaminants of concern.
- Prepare documentation of remedial activities.

Investigation and remedial activities were limited to the area of impact by the former smudge pot storage releases and were guided through the use of field screening including color, odor, sheet, and head space volatile organic compounds (VOCs) evaluated through a photoionization detector (PID). Investigation and remediation activities were supervised by Nicole McPhee, a staff geologist with Fulcrum. Work was performed under the direction of Jeremy Lynn, Washington State Licensed Hydrogeologist, with Fulcrum. See Appendix A for Professional certification.

Excavation of test pits completed during initial investigation and waste characterization activities were completed by WA LAND MGMT, LLC. Subsequent remedial excavation of PCS was completed by Spokane Environmental Services (SES) under contract to Fulcrum. Fulcrum utilized Fremont Analytical, Inc. (Fremont), of Seattle, Washington to provide laboratory services. Fremont is an Ecology accredited laboratory (accreditation number C910).

The following project partners were retained by WA LAND MGMT, LLC:

- DTG Recycle (formerly Anderson Rock & Demolition Pit and Treatment Facility) of Yakima,
 Washington to provide transport and treatment of PCS
- Tri-Valley Construction to transport soils to the selected disposal facility.
- DR Trucking Services, LLC to transport soils to the selected disposal facility.
- SD Construction to transport soils to the selected disposal facility.

No groundwater or surface water were encountered during remediation.

3.0 Discussion of Pertinent Regulations and Guidance

Fulcrum utilized applicable portions of the following guidance and Washington State regulations.

3.1 MTCA Regulations

In March of 1989, The Model Toxics Control Act (MTCA) went into effect in Washington State. The MTCA regulations, WAC 173-340-360, set standards to ensure quality of cleanup and protection of human health and the environment. A major portion of the MTCA regulation (completed in 1991) was the development of numerical cleanup standards and requirements for cleanup actions. Three options were established under



MTCA for site-specific cleanup levels: Method A, B, and C. Method A defines cleanup levels for 25 of the most common hazardous substances found at sites. Method B levels are set using a site risk assessment, which enables consideration of site-specific characteristics. Method C is similar to Method B; however, the individual substance's cancer risk portion of the assessment is set at 1 in 100,000 rather than 1 in 1,000,000.

Rule amendments to MTCA, which became effective August 15, 2001, changed the cleanup levels of petroleum hydrocarbon contamination. Whereas diesel and heavy oil concentrations were increased, the MTCA Method A cleanup levels for gasoline and gasoline components Benzene, Toluene, Ethylbenzene, and Xylene (BTEX) were lowered significantly. Updates since 2001 have been primarily administrative in nature, although review and adjustment of cleanup levels are ongoing.

3.2 Cleanup Standard Selected

Ecology's MTCA Method A cleanup tables were developed to provide conservative cleanup levels for sites undergoing routine cleanup actions or those sites with relatively few hazardous substances. Method A cleanup levels are specifically designated as appropriate for residential facilities and are appropriate for a conservative approach at schools and public sites. Therefore, Fulcrum has determined that Ecology's MTCA Method A cleanup levels to be the most appropriate regulatory guidance for evaluating the need for site cleanup at the site. Where Method A cleanup levels are not published, Fulcrum utilized default published Method B values.

3.3 Sampling Guidance Criteria

Fulcrum has utilized applicable portions of the following documents as guidance criteria for confirmation sampling protocol:

- 1. Washington State Department of Ecology, *Guidance for Remediation of Petroleum Contaminated Soil*, revised June 2016.
- 2. American Petroleum Institute, *A Guide to the Assessment and Remediation of Underground Petroleum Releases*, publication 1628, dated July 1996.
- 3. Washington State Department of Ecology, *Guidance for Site Checks and Site Assessments for Underground Storage Tanks*, revised April 2003.

4.0 Environmental Setting


Contaminant transport within the subsurface and extent of impact is largely determined by the nature of the contaminant, as well as, regional and local geologic and hydrogeologic conditions. The following subsections describe regional and local subsurface site settings.



4.1 Regional Setting

From a regional setting, the subject site is located within the Yakima Folds Geomorphic Province (YFGP) on the western margin of the Columbia River Plateau. The Yakima Fold Belt is generally characterized by anticlinal ridge and synclinal valley structures; and valley lowlands are composed erosional sedimentary deposits including: alluvium, lacustrine, glacial, glacial-fluvial materials and localized areas of windblown loess. The Yakima River is located to the northeast.

The Yakima River Basin (YRB) is located within the boundaries of the YFGP and extends from the northeastern slopes of the Cascade Mountain Range in Kittitas County to the confluence of the Yakima and Columbia Rivers in Benton County. The YRB additionally incorporates portions of Benton County and the majority of Yakima County. The YRB consists of a total of six structural aquifer basins and occupies 6,200 square



Six Structural Aquifer Basins - Courtesy of USGS

miles. The network of Yakima Basin aquifers is supplied by the headwaters of the eastern slopes of the Cascade Mountain Range.

The Subject Site is located within the Benton Basin. The Benton Basin comprises approximately 1,020-square miles in the southeast portion of the YRB and is bordered by the Rattlesnake Hills to the north and east, the Horse Haven Hills to the south, and the City of Granger and the Toppenish Basin to the west. The east extent is defined as the Columbia River. The basin is characterized by folds and faults striking in an east-west direction. The basin fill deposit stratigraphy is divided into two hydrogeologic subunits. The first unit consists of unconsolidated alluvial fan, loess, terrace, dune sand, Touchet, Missoula flood, and Ringold Formation sedimentary deposits with a thickness range of 0 to 870-feet. The second unit consists primarily of consolidated Ellensburg Formation and similar continental sedimentary deposits present in the southwestern portion of the basin and ranges in thickness from 0 to 680-feet. The Benton Basin ranges in total thickness from 0 to 870-feet with the greatest thickness present in the western and northeastern portions of the basin.



4.2 Local Geologic Setting

Site soils are identified by the U.S. Department of Agriculture's (USDA) Natural Resources Conservation Service (NRCS) Web Soil Survey at the smudge pot storage area as *Scoon silt loam*. According to the USDA Soil Survey, *Scoon silt loam* is well drained with a very low to moderately low capacity to transmit water.

Typical soil profile of Scoon silt loam consists of the following:

- $Silt\ loam 0$ to 6 inches below ground surface (bgs);
- *Gravelly very fine sandy loam* 6 to 16 inches bgs;
- *Cemented material* 16 to 60 inches bgs;

While completing site activities, Fulcrum observed soil within the excavation pit at the smudge pot area to be composed of poorly graded sandy loam with gravel.

Groundwater was not encountered during remediation activities. Shallow groundwater wells are not generally present within the vicinity of the subject site. Fulcrum viewed Ecology's well viewer database within the same township and the range of well depths were from 8 feet to 633 feet bgs. Projected depths to groundwater are unknown at the smudge pot location; however, is estimated to be greater than 40 feet bgs.

5.0 Site Activities

Site activities consisted of an initial investigation for waste characterization followed by remediation.

5.1 Initial Investigation and Waste Characterization

In September 2019, initial investigation and waste characterization activities were completed to evaluate the approximate vertical and horizontal extents of impact and to determine a potential treatment or disposal facility for remedial planning purposes. Fulcrum met with WA LAND MGMT, LLC and completed select test pits through the former smudge pot area. Fulcrum completed visual observation and field screening to evaluate general extents of impact in each test pit. Field screening included evaluation of odor, color, sheen, and VOCs with the use of a PID. At each location, Fulcrum collected one composite sample of near surface and representative soils to evaluate the level of petroleum impact. See Appendix C for site photographs.

The former smudge pot storage area was estimated, based on the presence of surface staining, to be approximately 85 feet north to south and 100 feet east to west. The storage area was located immediately northeast of an orchard access roadway extending from Washout Road.

Three soil samples were collected from areas of where petroleum impacts appeared to be the greatest. Samples included:



- R19E-91619-01: Northern portion of Smudge Pot Storage Area, Surface to 1-foot bgs
- <u>R19E-91619-02</u>: Central portion of Smudge Pot Storage Area, Surface to 1-foot bgs
- R19E-91619-03: Southern portion of Smudge Pot Storage Area, Surface to 1-foot bgs

Each sample was collected into one, 4-ounce borosilicate jar with Teflon lined lids and two, 40-milliliter glass vials with Teflon lined lids. New, clean nitrile gloves were used during sampling. See Appendix B for a summary of Fulcrum's sample handling methodology. The soil samples were packaged on ice and shipped overnight via commercial carrier under chain-of-custody to Fremont for analysis.

Samples were composited in the laboratory for waste characterization. Samples were submitted for the following analyses:

- Polychlorinated Biphenyls (PCBs) by Environmental Protection Agency (EPA) Method 8082
- Diesel and heavy Oil by Northwest Total Petroleum Hydrocarbons (NWTPH) Diesel Extended (Dx Ext)
- Polyaromatic Hydrocarbons (PAH) by EPA Method 8270 (SIM)
- Volatile Organic Compounds by EPA Method 8260D
- Mercury by EPA Method 7471
- Total Arsenic, Cadmium, Chromium and Lead by EPA Method 6020B.

Results were reported under Fremont work order number 1909309. See Appendix E for Complete Laboratory Report.

Table 1: Waste Characterization Sample Results

Analyte	Result (mg/Kg)	MTCA Method A CUL	Exceeds MTCA Method A CUL	Dangerous Waste Level (mg/L)	Exceeds Dangerous Waste Level
Total PCBs ¹	< 0.101	10^{2}	No	-	-
Diesel	86,000	2,000	Yes	-	-
Heavy Oil	< 503	2,000	No	-	-
Polyaromatic Hydrocarbon	S				_
Benzo[a]pyrene	< 0.402	0.1^{2}	Yes	-	-
Benz[a]anthracene	0.234	NA	NA	-	-
Benzo[b]fluoranthene	0.356	NA	NA	-	-
Benzo[k]fluoranthene	0.292	NA	NA	-	-
Chrysene	0.762	NA	NA	-	-
Dibenz[a,h]anthracene	0.076	NA	NA	-	-
Indeno[1,2,3-cd]pyrene	0.225	NA	NA	-	-
PAH TTEC (Per WAC 173-340-708)	0.1259	0.12	Yes	-	-
Pyrene	8.19	2,400	No	-	-
Benzo[g,h,i]perylene	0.177	NA	NA	-	-
Total PAH [Percentage Per WAC 173-303-100(6)]	0.107%	-	-	1%	No
Semi-Volatile Organic Com	pounds				
Naphthalene	0.081	5	No	-	-
2-Methylnaphthalene	0.148	320^{3}	No	-	-



Analyte	Result (mg/Kg)	MTCA Method A CUL	Exceeds MTCA Method A CUL	Dangerous Waste Level (mg/L)	Exceeds Dangerous Waste Level
1-Methynaphthalene	0.091	340^{3}	No	-	-
Volatile Organic Compound	ds				
Halogenated/Chlorinated VOCs ¹	-	-	-	-	-
Benzene	< 0.020	0.03	No	0.5	No
Toluene	0.027	7	No	-	-
Ethylbenzene	< 0.025	6	No	-	-
Total Xylenes	0.064	9	No	-	-
1,2,4-Trimethylbenzene	0.040	800 ³	No	-	-
Metals					
Mercury	< 0.245	2	No	0.2	No
Arsenic	3.07	20	No	5	No
Cadmium	0.281	2	No	1	No
Total Chromium	10.3	19 / 2,000 ⁴	No	5	No
Lead	8.63	250	No	5	No

All results, method reporting limits, and cleanup levels are presented in mg/Kg. Dangerous waste threshold values where published in WAC 173-303-090(8) are presented in milligrams per liter.

Results in **Bold** indicate a result above the MTCA Method cleanup level.

- ¹ The individual chemical constituents were not detected above the method reporting limit (MRL)
- ² The Unrestricted MTCA Method A cleanup level for Benzo[a]pyrene was used for waste characterization.
- ³ Select constituents have established MTCA Method A cleanup level. When a MTCA Method A cleanup level is not available, the MTCA Method B Standard Value is utilized for evaluation.
- ⁴ The MTCA Method A cleanup level for Chromium (III) is 2,000 mg/Kg and for Chromium (VI) is 19 mg/Kg

The following data qualifiers were noted in the laboratory results for the project samples:

- D Dilution was required for diesel
- S Spike recovery outside accepted recovery limits for petroleum surragates
- J Analyte detected below Reporting Limit for select PAHs
- Q Analyte with an initial or continuing calibration that does not meet established acceptance criteria (<20% RSD, <20% Drift or minimum RRF) for select VOCs

Dilution, spike recovery, and calibration drift are commonly associated with high levels of petroleum hydrocarbons. An analyte reported below the reporting limit is typically found where analytical sensitivity exceeds the method reporting requirements. A review of these notes indicates that laboratory QA/QC are satisfactory and should not affect project data or objectives.

The initial investigation confirmed the presence of diesel range petroleum hydrocarbons as the contaminants of concern for remediation.

The selected MTCA Method A threshold for PAHs was industrial land use as the treatment facility is an industrial site. PAHs are typically associated with diesel product and are expected to be remediated to below unrestricted land use threshold concentrations at the site with removal of the diesel impacted soil. However, based on discussions with Ecology associated with concurrent smudge pot remediation sites, screening for PAHs is appropriate for final site confirmation samples based on the waste characterization results.



5.2 Remedial Excavation

Remedial excavation of PCS began on October 22, 2020 and was completed on October 28, 2020. Soils were excavated utilizing an excavator and loaded directly into dump trucks for transport to the treatment facility.

Fulcrum utilized field screening methods, including visual observation for staining or discoloration, sheen on water, and use of a PID, to guide the excavation. When visibly impacted soils were removed and field indications of contamination were absent, soil samples were collected to confirm completion of remediation.

Fulcrum completed field screening of all soil samples as shown in Tables 2 and 3. Laboratory results are provided in Section 6.0, Table 4.

Table 2: Field Screening – October 22, 26, 27, and 28, 2020

Color	Odor	PID (ppm)	Sheen	Other
Light Brown	No	0	No	Sandy silt loam with gravel and cobbles
Light Brown	Slight	1	No	Sandy silt loam with gravel and cobbles
Light Brown	Slight	0	No	Sandy silt loam with gravel and cobbles
Light Brown	No	0	No	Sandy silt loam with gravel and cobbles
Light Brown	No	0	No	Sandy silt loam with gravel and cobbles
Light Brown	No	0	No	Sandy silt loam with gravel and cobbles
Light Brown	No	0	No	Sandy silt loam with gravel and cobbles
Light Brown	No	0	No	Sandy silt loam with gravel and cobbles
Light Brown	Slight	1	No	Sandy silt loam with gravel and cobbles
Light Brown	No	0	No	Sandy silt loam with gravel and cobbles
Light Brown	No	0	No	Sandy silt loam with gravel and cobbles
Light Brown	Slight	0	No	Sandy silt loam with gravel and cobbles
Light Brown	No	0	No	Sandy silt loam with gravel and cobbles
	Light Brown	Light Brown No Light Brown Slight Light Brown Slight Light Brown No Light Brown Slight Light Brown No	Light Brown No 0 Light Brown Slight 1 Light Brown Slight 0 Light Brown No 0 Light Brown Slight 1 Light Brown No 0 Light Brown No 0	Light Brown No 0 No Light Brown Slight 1 No Light Brown Slight 0 No Light Brown No 0 No Light Brown Slight 1 No Light Brown No 0 No Light Brown No No No Light Brown No No No Light Brown No No No

ppm Parts Per Million in air

The former smudge pot staging area was excavated to a footprint approximately 94 feet in length (north-south), 103 feet wide (east-west), and ranging from 1 to 8 feet in depth with an average of about 1 to 2 feet deep. The central portion of the excavation was completed to approximately 3 to 8 feet bgs in localized areas.

Based on total area and linear extents of sidewalls exceeding 3 feet bgs, a total of nineteen (19) samples were collected and included fourteen (14) from pit bottom and five (5) from excavation sidewalls.

Soil samples were collected by hand where possible, and from the excavator bucket where indicated. Soil samples were placed within a 4-ounce borosilicate jars with Teflon-lined lid (Diesel, Heavy Oil, and PAHs) and two 40 milliliter glass vials (for BTEX analysis) with a Teflon-lined lid for each sample location. New, clean nitrile gloves were used for each sample set.



6.0 Laboratory Results

The samples were packed on ice and shipped overnight via commercial carrier under chain-of-custody to Fremont for analysis by the following:

- Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.
- Volatile Organic Compounds (VOC) for Benzene, Toluene, Ethylbenzene and Xylenes (BTEX) by Environmental Protection Agency (EPA) Method 8260D

Based on feedback from Ecology on concurrent smudge-pot remediation sites and as a screening approach, additional analysis for the following was completed for one sample (R19E-102820-13.1):

Polycyclic Aromatic Hydrocarbons (PAH) by EPA Method 8270 (SIM)

Results were reported under Fremont Project No. 2010457 and 2010479 and are summarized in Table 4. See Appendix E for Complete Laboratory Results.

Table 3: Former Smudge Pot Storage Area Laboratory Results

		Analyte					
Sample ID and Location	Diesel	Heavy Oil	Benzene	Toluene	Ethylbenzene	Total Xylenes	
	al Event –	December	12, 2019	1	1		
R19E-102720-01.2 Southeast pit bottom, 2 feet bgs	<18.7	<46.8	< 0.0247	< 0.0247	<0.0309	< 0.617	
R19E-102720-02.5.5 South pit bottom, 5.5 feet bgs	<17.2	<43.0	< 0.0238	<0.0238	< 0.0297	< 0.0594	
R19E102720-03.3 Central east pit bottom, 3 feet bgs	<20.7	<51.8	< 0.0238	<0.0238	< 0.0297	<0.0595	
R19E-102720-04.2.5 Central pit bottom, 2.5 feet bgs	<20.0	<49.9	< 0.0224	< 0.0224	<0.0280	<0.0560	
R19E-102720-05.2 Southwest pit bottom, 2 feet bgs	<20.1	<50.4	< 0.0243	< 0.0243	< 0.0304	<0.0608	
R19E-102720-06.2 East pit bottom, 2 feet bgs	<20.7	<51.7	< 0.0237	< 0.0237	< 0.0296	<0.0593	
R19E-102720-07.2 Northeast pit bottom, 2 feet bgs	<19.6	<49.0	< 0.0265	< 0.0265	< 0.0331	<0.0662	
R19E-102720-08.3 South sidewall, 3 feet bgs	<19.6	<49.1	< 0.0244	< 0.0244	< 0.0305	<0.0610	
R19E-102720-09.3 Southwest sidewall, 3 feet bgs	<19.7	<49.2	< 0.0239	<0.0239	<0.0299	<0.0598	
R19E-102820-10.1 Northeast pit bottom, 1 feet bgs	<18.6	<46.5	< 0.0452	< 0.0452	< 0.0565	<0.113	
R19E-102820-11.2 Pit bottom, 2 feet bgs	<20.1	<50.2	<0.0282	<0.0282	< 0.0353	< 0.0706	
R19E-102820-12.8	<17.7	<44.3	< 0.0286	< 0.0286	< 0.0357	< 0.0715	



	Analyte						
Sample ID and Location	Diesel	Heavy Oil	Benzene	Toluene	Ethylbenzene	Total Xylenes	
Pit bottom, 8 feet bgs							
R19E-102820-13.1 West pit bottom, 1 feet bgs	74.6	<47.6	< 0.0266	< 0.0266	< 0.0332	< 0.0665	
R19E-102820-14.1 North pit bottom, 1 feet bgs	<19.8	<49.4	< 0.0340	< 0.0340	< 0.0425	< 0.0850	
R19E-102820-15.1 North pit bottom, 1 feet bgs	<20.5	<51.3	< 0.0276	< 0.0276	< 0.0346	<0.0690	
R19E-102820-16.1 South of pit, 1 feet bgs	<21.6	<54.0	< 0.0375	< 0.0375	<0.0469	< 0.0937	
R19E-102820-17.6 East Sidewall, 6 feet bgs	<18.5	<46.3	< 0.0225	< 0.0225	<0.0281	< 0.0562	
R19E-102820-18.6 South sidewall, 6 feet bgs	<17.9	<44.8	<0.0241	<0.0241	< 0.0301	< 0.0602	
R19E-102820-19.6 West sidewall, 6 feet bgs	<19.8	<49.5	<0.0284	< 0.0284	< 0.0355	< 0.0709	
MTCA Method A Cleanup Level	2,000	2,000	0.03	7	6	9	

Results in **Bold** indicate a result above the MTCA Method cleanup level.

Laboratory analysis identified one sample location with a detectable concentration of diesel range hydrocarbons: R19E-102820-13.1 at 1 foot bgs with 74.6 milligrams of analyte per kilogram of soil (mg/Kg), below the MTCA Method A cleanup level of 2,000 mg/Kg for diesel.

All other constituents including heavy oil and BTEX were non-detect for all samples collected. Sample R19E-102820-13.1 was reported with non-detectable concentrations of PAHs.

Three of the samples reported with non-detect concentrations of benzene had analytical reporting limits slightly above the MTCA Method A cleanup level. Based on site use, the previous waste characterization sampling completed at the site, and consistency with other samples collected during site remediation, benzene has not been identified as a constituent of concern

No data qualifiers were noted in the laboratory results. A review of data qualifiers indicates that laboratory QA/QC are satisfactory and should not affect project data or objectives.

7.0 Soil Treatment

Tri-Valley Construction, DR Trucking Services, LLC, and SD Construction completed 36 trips during remedial activities in October 2020. A total of 881.83 tons of PCS was delivered to Anderson's Rock & Demolition Pits and PCS Treatment Facility in Yakima, Washington for treatment by land farming:



- October 22, 2020 4 trips
- October 26, 2020 14 trips
- October 27, 2020 12 trips
- October 28, 2020 6 trips

See Appendix D for copies of weight tickets from DTG Recycle.

8.0 Discussion

The completed waste characterization event for the smudge pot storage area confirmed the presence of diesel fuel in site soils at 86,000 mg/Kg which is above the MTCA Method A cleanup levels for diesel range petroleum hydrocarbons of 2,000 mg/Kg.

During the remediation event from October 22 to October 28, 2020, Fulcrum collected nineteen (19) representative confirmation samples from excavation pit bottom and sidewalls of the former smudge pot storage area. One of the sample results detected a diesel concentration of 74.6 mg/Kg below the MTCA Method A Cleanup level. All other samples collected from the excavation area were documented with non-detect concentrations for all constituents analyzed.

8.1 PAH Screening Analysis

Following analysis of final confirmation samples, Fulcrum requested additional analysis of one sample from the final excavation (R19E-102820-13.1) for carcinogenic PAHs to assess human health risk pursuant to WAC 173-340-708(8)(e). Results were reported under Fremont work order 2010479. See Appendix E for complete laboratory results.

The sample was reported with carcinogenic PAH concentrations below the method reporting limit. Using ½ the practical quantitation limit (PQL) for the samples, method reporting limits are confirmed to be low enough to provide a maximum total technical equivalent concentration (TTEC) of 0.030 mg/Kg, which is below the MTCA Method A cleanup level of 0.1 mg/Kg for carcinogenic PAHs in soil.

8.2 Terrestrial Ecological Evaluation

The Terrestrial Ecological Evaluation (TEE) process is required to be completed as a portion of cleanup action alternative review under MTCA. The intent of the TEE is to determine if site soil conditions subsequent to development of remedial alternative(s) may pose a threat to the terrestrial environment, including soil biota, plants, and wildlife. The TEE procedures are presented in WAC 173-340-7490 through 7494.

Under the simplified TEE in WAC 173-340-7492, evaluation may be ended where residual concentrations are below threshold values in WAC 173-340-900, Table 749-2. Final confirmation sample results identified detectable concentration of diesel at a maximum concentration of 74.6 mg/Kg and below the Table 749-2



threshold value of 460 mg/Kg for unrestricted land use. Based on the final confirmation sample results, no further TEE is warranted.

9.0 Conclusions

Fulcrum performed waste characterization and soil remediation excavation services associated with a former smudge pot storage area located at Ranch 19 East located in Yakima County, Washington. The smudge pot storage area was impacted by diesel as a result of handling and storing smudge pots that contained diesel fuel.

A total of 881.83 tons of soil was excavated from the former smudge pot storage location on the site. All excavated soils were transported to DTG Recycle for land farming.

Final post-remedial conditions were documented to meet Ecology regulatory criteria at the apparent smudge pot area and in Fulcrum's opinion no additional remediation is warranted associated with the Ranch 19 East area.

Fulcrum recommends that a copy of this remediation report be retained. A copy of this report should be provided to a prospective buyer or investor of this property.

10.0 Limitations

Fulcrum Environmental Consulting, Inc. has performed professional services in accordance with generally accepted professional consulting principles and practices. No other warranty, expressed or implies, is made. The conclusions and recommendations are based upon our field observations, field screening, and independent laboratory analysis. The scope of services for this project is limited to the investigation of one petroleum spill location associated with the site.

Fulcrum makes no warranties expressed or implied as to the accuracy or completeness of other's work included or referenced herein, nor the use of segregated portions of this report. This document does not imply that the property is free of other environmental concerns. This report is solely for the use and information of our client. Any reliance on this report by a third party is at that party's sole risk.

Opinions and recommendations contained in this report apply to conditions existing at the time services were performed. Fulcrum Environmental Consulting, Inc. is not responsible for the impact of changes in environmental standards, practices, or regulations subsequent to the performance of services. Fulcrum Environmental Consulting, Inc. assumes no liability for conditions that were not included in our scope of services, or conditions not generally recognized as predictable when services were performed.



Figures

Figure 1: Site Location

Figure 2: Smudge Pot Excavation
Figure 3: Sample Location

Figure 4: TEE Acreage






Fulcrum Environmental Consulting, Inc. 406 North Second Street, Yakima, Washington 98901 p: 509.574.0839 f: 509.575.8453 efulcrum.net Smudge Pot Remediation. 192902.15. KDA. 12/13/19 Ranch 19 West 441 Williamson Road Sunnyside, WA

Site Location

FIGURE







Fulcrum Environmental Consulting, Inc.

I00 FEET 200

406 North Second Street, Yakima, Washington 98901 p: 509.574.0839 f: 509.575.8453 efulcrum.net Smudge Pot Remediation. 192902.15. NLM. 12/17/20


Ranch 19 East 441 Williamson Road Sunnyside, Washington


ORCHARDS

Excavation Location

FIGURE 2







Fulcrum Environmental Consulting, Inc.

406 North Second Street, Yakima, Washington 98901 p: 509.574.0839 f: 509.575.8453 efulcrum.net Smudge Pot Remediation. 192902.15. NLM. 12/15/20

Ranch 19 East 441 Williamson Road Sunnyside, Washington

Sample Location Map

FIGURE 3





Fulcrum Environmental Consulting, Inc.

406 North Second Street, Yakima, Washington 98901 p: 509.574.0839 f: 509.575.8453 efulcrum.net Smudge Pot Remediation. 192902.15. ALY. 1/4/21

Ranch 19 East 441 Williamson Road Sunnyside, Washington

TEE Acreage Map



Appendix A

Professional Certifications



THIS CERTIFIES THAT

RYAN K. MATHEWS

HAS SUCCESSFULLY MET ALL THE REQUIREMENTS OF EDUCATION, EXPERIENCE AND EXAMINATION, AND IS HEREBY DESIGNATED A

CERTIFIED HAZARDOUS MATERIALS MANAGER CHMM



January 31, 2007

DATE OF CERTIFICATION

January 31, 2023

CERTIFICATION EXPIRES

14149

CREDENTIAL NUMBER

EXECUTIVE DIRECTOR





STATE OF WASHINGTON

DEPARTMENT OF LICENSING - BUSINESS AND PROFESSIONS DIVISION





GEOLOGIST HYDROGEOLOGIST

JEREMY MATTHEW LYNN 1406 SUNSET DRIVE PROSSER WA 99350

2914

License Number

12/05/2011

Issued Date

01/18/2019

Expiration Date

Pat Kohler
Pat Kohler, Director

PL-630-159 (R/3/16)



Appendix B

Remediation Work Plan




Remediation Work Plan Smudge Pot Storage Area

Ranch 19 441 Williamson Road Sunnyside, Washington

Project Number: 1992902.15

December 17, 2019



Prepared for:

WA LAND MGMT, LLC c/o: Guy Kisling 22605 Southeast 56th Street #200 Issaquah, Washington 98029

Prepared by:

Fulcrum Environmental Consulting, Inc. 406 North 2nd Street Yakima, Washington 98901



Report Title: Remediation Work Plan, Smudge Pot Storage Area

Project Number: 192902.15

Date: December 17, 2019

Site: Ranch 19, 441 Williamson Road

Sunnyside, Washington

GPS coordinates 19W: 46.390524, -120.012625 / 19E: 46.403126, -120.000132

Date: 12.17.19

Prepared for: WA LAND MGMT, LLC

c/o: Guy Kisling

22605 Southeast 56th Street #200 Issaquah, Washington 98029

Prepared by: Fulcrum Environmental Consulting, Inc.

406 North Second Street Yakima, Washington 98901

509.574.0839

The professionals who completed site services, prepared, and reviewed this report include but are not limited to:

7 7

Nicole McPhee, Environmental Technician Fulcrum Environmental Consulting, Inc.

U Ryan K. Mathews, CIH, CHMM, Principal

Fulcrum Environmental Consulting, Inc.

Report Integrity:

Authored by:

Reviewed by:

Fulcrum Environmental Consulting, Inc.'s scope of service for this project was limited to those services as established in the proposal, contract, verbal direction, and/or agreement. This report is subject to applicable federal, state, and local regulations governing project-specific conditions and was performed using recognized procedures and standards of the industry. Scientific data collected in situ may document conditions that may be specific to the time and day of service, and subject to change as a result of conditions beyond Fulcrum's control or knowledge. Fulcrum makes no warranties, expressed or implied as to the accuracy or completeness of other's work included herein. Fulcrum has performed these services in accordance with generally accepted environmental science standards of care at the time of the inspection. No warranty, expressed or implied, is made.



TABLE OF CONTENTS

<u>SEC</u>	TION		PAGE
1.0	Introduction		1
1.0			
	_	rties	
	·	organization	
	_	Regulations and Approach	
		Evaluation	
		iew	
2.0	Site Description		4
	2.1 Physical S	Setting	4
	2.1.1 Clima	ate	4
	2.1.2 Topo	graphy	4
	2.1.3 Region	onal Geology	4
	2.1.4 Regio	onal Hydrogeology	4
	2.1.5 Groun	ndwater	5
	2.2 Land Use.		5
3.0	Previously Compl	leted Investigations	5
4.0	Remedial Objective	ves	7
	4.1 Remedial	Action Objectives	7
	4.2 Basis for t	he Selected Remedy	7
5.0	Remediation Acti	vities	8
	5.1 General St	teps	8
	5.2 Field Scre	ening	9
	5.3 Confirmat	ion Soil Sampling	9
	5.3.1 Pit Bo	ottom Samples	9
	5.3.2 Sidev	vall Samples	9
	5.4 Evaluation	n of Laboratory Results	10
6.0	Risk Screening Ev	valuation	10
	6.1 Potential I	Human Health Impacts	10
	6.2 Potential F	Ecological Impacts	11
7.0	Reporting & Sche	eduling	12
8.0	References		12



 -			
/\	u	 _	v.

Table 1	Organization of Project Staff and Responsibilities	2
Table 2	Waste Characterization Sample Results	
Table 3	Projected Schedule of Events	

FIGURES

Figure 1 Site Location Map

Figure 2 General Remediation Area Map

APPENDICES

Appendix A Field Form

Appendix B Sampling and Analysis Plan/Quality Assurance Project Plan



1.0 Introduction

This Remediation Work Plan has been prepared on behalf of WA LAND MGMT, LLC by Fulcrum Environmental Consulting, Inc. (Fulcrum) to describe the remediation activities that will be conducted at Ranch 19, located at 441 Williamson Road, Sunnyside, WA. See Figure 1 for general site location.

The property is operated as irrigated permanent plantings of fruit trees. Property operated by WA LAND MGMT, LLC includes apples and soft fruits (peaches, apricots, etc.). Since first orchard use, smudge pots have been utilized as the primary frost protection system at the site. Typical of common regional practice, during off-season use in summer months, the smudge pots were removed from the field and stored at the site in a concentrated area(s).

During a Phase I Environmental Site Assessment (ESA) site walk performed on behalf of a prospective buyer, visibly stained soils were observed in the smudge pot storage area. The prospective buyer notified WA LAND MGMT, LLC and requested additional investigation and remediation if necessary.

Fulcrum completed limited Phase II investigation activities at the site to evaluate constituents of concern (COC); and to approximate extents of impact and soil volumes. Applicable results of the Phase II investigation are summarized in Section 3.

The intent is that all project activities were completed as provided in The Model Toxics Control Act (MTCA), Washington Administrative Code (WAC) 173-340. In our professional opinion, the use of the independent remediation process is appropriate given the current understanding of site conditions.





1.1 Purpose

The purpose of the work plan is to complete an independent remediation of site soils as provided under WAC 173-340-515. During this work, Fulcrum intends to consider all appropriate remedial strategies in accordance with the MTCA including engagement of Ecology under the Voluntary Cleanup Program and/or proceeding as an independent remedial action. These strategies may include calculating alternate cleanup levels under WAC 173-340-700 for petroleum hydrocarbons; completing a risk-based evaluation; using of monitored natural attenuation (MNA); applying institutional and engineering controls with a restrictive covenant; etc., or a combination of these methods.



1.2 Project Parties

This project is a coordination of the efforts of WA LAND MGMT, LLC, Fulcrum, and selected contractors. Fulcrum will lead remediation activities. Table 1 lists the people involved in this project, their respective organization, and their role.

Table 1: Organization of Project Staff and Responsibilities

Person/Agency or Firm	Role/Responsibility
Brett Calhoun, General Manager WA LAND MGMT, LLC Brett.Calhoun@pridepacking.com, 509.728.2772	Site General Manager: Responsible for assisting with site access.
Frank Winslow, Site Manager Washington State Department of Ecology frank.winslow@ecy.wa.gov, 509.454.7886	Provides local regulatory review of investigation findings and review of project documentation.
Ryan K. Mathews, CIH, CHMM Fulcrum Environmental Consulting, Inc. RMathews@efulcrum.net , 509.574.0839	Fulcrum Principal: Responsible for reviewing and managing project charter and contracting.
Jeremy M. Lynn, LHG, PMP Fulcrum Environmental Consulting, Inc. <u>Jeremy.Lynn@efulcrum.net</u> , 509.405.2450	Reviews the project scope, budget, and tracks progress. Provides supervision of onsite investigation activities and review of project geologic and hydrogeologic evaluation and documentation. All project documentation will be stamped by a Washington State Licensed Hydrogeologist.
Kyle Ames, GIT Fulcrum Environmental Consulting, Inc. Jeremy.Lynn@efulcrum.net, 509.574.0839	Assist with the site remediation and completes soil sampling under the direction of Fulcrum's Licensed Hydrogeologist.
Ashley Yellick, GIT Fulcrum Environmental Consulting, Inc. Jeremy.Lynn@efulcrum.net, 509.574.0839	Assist with the site remediation and completes soil sampling under the direction of Fulcrum's Licensed Hydrogeologist.
Mike Ridgeway Fremont Analytical, Inc. mridgeway@fremontanalytical.com; 206.352.3790	Project Laboratory: Responsible for completion of work tasks, including laboratory analysis, sample container provision, laboratory QA/QC, and review of project laboratory analysis.
Chris Smith Spokane Environmental Solutions, Inc. chris@spokaneenvironmental.com ; 509.999.3600	Remedial Excavation Contractor Principal: Responsible for completion of excavation and soil transport activities.

1.3 Work Plan Organization

In addition to this Introduction, the Work Plan includes the following sections:

- Section 2: Site Description describes the location, physical setting, and operational history at the Site.
- Section 3: Prior Investigation summarizes the scope and results from previous environmental investigations that have been conducted at the Site in chronological order and describes the current



understanding of environmental site conditions based on the previous investigations and the operational history of the Site.

- Section 4: Remedial Objectives describes the objectives of the soil remediation work.
- Section 5: Remediation Activities provides a narrative of the work tasks that will be completed to accomplish soil removal.
- Section 6: Reporting and Schedule describes the investigation report that will be prepared per MTCA requirements and the schedule for completion of significant investigation tasks.
- Section 7: References provides a list of references cited in the Work Plan.
- Several appendices are included to provide information supporting the scope of the Work Plan.

1.4 Pertinent Regulations and Approach

In March of 1989, the Model Toxics Control Act (MTCA) went into effect in Washington State. The MTCA regulations set standards to ensure quality of cleanup and protection of human health and the environment. A major portion of the MTCA regulation (completed in 1991) was the development of numerical cleanup standards and requirements for cleanup actions. Three options were established under MTCA for site-specific cleanup levels: Method A, B and C. Method A defines cleanup levels for 25 of the most common hazardous substances found at sites. Method B levels are set using a site risk assessment, which enables consideration of site-specific characteristics. Method C is similar to Method B, however, the individual substance's cancer risk portion of the assessment is set at 1 in 100,000 rather than 1 in 1,000,000.

Ecology's MTCA Method A cleanup tables were developed to provide conservative cleanup levels for sites undergoing routine cleanup actions or those sites with relatively few hazardous substances. Method A cleanup levels are specifically designated as appropriate for residential facilities and are appropriate for a conservative approach at school, public and commercial sites. Therefore, Fulcrum has determined that Ecology's MTCA Method A cleanup levels will be used as site screening levels (SSLs) during the investigation. However, use of Method A levels does not limit the use of site-specific Method B levels in future remediation design or implementation. Where MTCA Method A cleanup levels are not provided, Fulcrum will utilize Method B levels as the SSL.

1.5 Wetlands Evaluation

Prior to initiation of remedial excavation, the site will be evaluated for the presence of wetlands. Evaluation will be completed using the following guidance criteria:

- US Army Corps of Engineers Wetland Delineation Manual, January 1987.
- US Army Corps of Engineers Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Arid West Region (Version 2.0), September 2008.
- Eastern Washington Wetland Rating System, January 2015.

Should wetlands be identified, a wetlands mitigation plan will be completed under separate and appended to this remediation work plan.



1.6 SEPA Review

Due to projected remedial soil volume exceeding 500 cubic yards, review of proposed excavation will be completed under State Environmental Policy Act (SEPA) checklists, and if applicable public comment, prior to initializing excavation activities. The SEPA documentation will be completed under separate cover and is not included within this remediation.

2.0 Site Description

Ranch 19 site is located at 441 Williamson Road, in Sunnyside, WA and is located on Yakima County Assessor tax parcel 191321-24002.

2.1 Physical Setting

The physical setting of the Site in terms of climate, topography, regional geology, regional hydrogeology, and surface water is described in the following paragraphs.

2.1.1 Climate

The climate is semi-arid with cool winters and hot/dry summers. The average daily maximum temperature at the Site ranges from 36 to 88 degrees Fahrenheit and the average annual precipitation is 8.4 inches (NOAA, 2016).

2.1.2 Topography

Site topography is generally level and varies with an elevation of about 1225 feet above sea level.

2.1.3 Regional Geology

The Site is located in the Yakima Valley. The regional geology consists of Miocene basalt flows of the Columbian River Basalt Group overlain by the Ellensburg Formation, which is overlain by mostly Holocene alluvial deposits resulting from the adjacent Yakima River. Geologic information for the Site comes from the Geologic Map of the Yakima Quadrangle, Washington (Bentley, 1983) and the logs from nearby wells.

2.1.4 Regional Hydrogeology

The hydrogeologic units of the Yakima region can be split into the following two categories (Vaccaro, et al., 2009):

- Basin-Fill Units (including unconsolidated alluvial deposits and semi-consolidated to consolidated units of the Ellensburg Formation)
- Columbia River Basalt Group and interbedded units



The lithology and hydraulic characteristics of the basin-fill units are diverse and groundwater levels generally follow land surface contours. Groundwater generally flows towards the Yakima River in the shallow basin-fill units at the Site. The flow in the deeper units is controlled primarily by characteristics of the unit itself and the overlying units. Flowing artesian conditions exist in the Yakima basin where groundwater is present under confined conditions, described as "aerially extensive productive artesian zones."

2.1.5 Groundwater

A limited review of well logs on Washington State Department of Ecology Well Log Report indicates the first groundwater bearing zone is estimated to be present within the upper 50-feet but production wells are likely to be in excess of 300-feet.

2.2 Land Use

The current land use of Ranch 19 is designated by Yakima County as "agricultural". Presently the site is operated as irrigated permanent plantings of apples or soft fruits (including apricots, peaches, etc.).

3.0 Previously Completed Investigations

An initial investigation completed in September 2019 identified the following constituents of concern:



Table 2: Waste Characterization Sample Results - Ranch 19E & 19W

Diesel Heavy Oil Polyaromatic Hydrocarbons Benzo[a]pyrene Benzo[b]fluoranthene Benzo[k]fluoranthene Chrysene Dibenz[a,h]anthracene Indeno[1,2,3-cd]pyrene	 <0.402 0.234 0.356 0.292 0.762 0.076 0.225 0.1259 8.19 	<0.100 233,000 <50.4 0.267 <0.385 0.628 0.491 1.27 0.096 0.541 0.4553	10 ² 2,000 2,000 2.0 ² NA NA NA NA NA NA	No Yes No No No NA NA NA NA NA NA NA NA	- - - - - - - -	- - - - - - -
Heavy Oil Polyaromatic Hydrocarbons Benzo[a]pyrene Benzo[b]fluoranthene Benzo[k]fluoranthene Chrysene Dibenz[a,h]anthracene Indeno[1,2,3-cd]pyrene PAH TTEC (Per WAC 173-340-708)	<503 <0.402 0.234 0.356 0.292 0.762 0.076 0.225 0.1259 8.19	<50.4 0.267 <0.385 0.628 0.491 1.27 0.096 0.541	2,000 2.0 ² NA NA NA NA NA NA NA	No No NA NA NA NA NA NA NA	- - - - -	- - - -
Polyaromatic Hydrocarbons Benzo[a]pyrene Benz[a]anthracene Benzo[b]fluoranthene Benzo[k]fluoranthene Chrysene Dibenz[a,h]anthracene Indeno[1,2,3-cd]pyrene PAH TTEC (Per WAC 173-340-708)	<0.402 0.234 0.356 0.292 0.762 0.076 0.225 0.1259 8.19	0.267 <0.385 0.628 0.491 1.27 0.096 0.541	2.0 ² NA NA NA NA NA NA NA NA	No NA NA NA NA NA NA NA	- - - - -	- - - -
Benzo[a]pyrene Benzo[a]anthracene Benzo[b]fluoranthene Benzo[k]fluoranthene Chrysene Dibenz[a,h]anthracene Indeno[1,2,3-cd]pyrene PAH TTEC (Per WAC 173-340-708)	 <0.402 0.234 0.356 0.292 0.762 0.076 0.225 0.1259 8.19 	<0.385 0.628 0.491 1.27 0.096 0.541	NA NA NA NA NA NA	No NA NA NA NA NA NA NA	- - - -	- - -
Benzo[a]pyrene Benzo[a]anthracene Benzo[b]fluoranthene Benzo[k]fluoranthene Chrysene Dibenz[a,h]anthracene Indeno[1,2,3-cd]pyrene PAH TTEC (Per WAC 173-340-708)	 <0.402 0.234 0.356 0.292 0.762 0.076 0.225 0.1259 8.19 	<0.385 0.628 0.491 1.27 0.096 0.541	NA NA NA NA NA NA	NA NA NA NA NA	- - - -	- - -
Benz[a]anthracene Benzo[b]fluoranthene Benzo[k]fluoranthene Chrysene Dibenz[a,h]anthracene Indeno[1,2,3-cd]pyrene PAH TTEC (Per WAC 173-340-708)	0.234 0.356 0.292 0.762 0.076 0.225 0.1259 8.19	<0.385 0.628 0.491 1.27 0.096 0.541	NA NA NA NA NA NA	NA NA NA NA NA	- - -	- - -
Benzo[b]fluoranthene Benzo[k]fluoranthene Chrysene Dibenz[a,h]anthracene Indeno[1,2,3-cd]pyrene PAH TTEC (Per WAC 173-340-708)	0.356 0.292 0.762 0.076 0.225 0.1259 8.19	0.628 0.491 1.27 0.096 0.541	NA NA NA NA NA	NA NA NA	- - -	-
Benzo[k]fluoranthene Chrysene Dibenz[a,h]anthracene Indeno[1,2,3-cd]pyrene PAH TTEC (Per WAC 173-340-708)	0.292 0.762 0.076 0.225 0.1259 8.19	0.491 1.27 0.096 0.541	NA NA NA NA	NA NA NA	-	-
Chrysene Dibenz[a,h]anthracene Indeno[1,2,3-cd]pyrene PAH TTEC (Per WAC 173-340-708)	0.762 0.076 0.225 0.1259 8.19	1.27 0.096 0.541	NA NA NA	NA NA	-	
Dibenz[a,h]anthracene Indeno[1,2,3-cd]pyrene PAH TTEC (Per WAC 173-340-708)	0.076 0.225 0.1259 8.19	0.096 0.541	NA NA	NA		-
Indeno[1,2,3-cd]pyrene <i>PAH TTEC</i> (<i>Per WAC 173-340-708</i>)	0.225 0.1259 8.19	0.541	NA			
PAH TTEC (Per WAC 173-340-708)	<i>0.1259</i> 8.19				_	_
(Per WAC 173-340-708)	8.19	0.4553				-
			2.0^{2}	No	-	
		12.9	2,400	No	_	_
Benzo[g,h,i]perylene	0.177	0.556	NA	NA	_	_
Total PAH						
[Percentage Per WAC	0.107	0.171%	-	-	1%	No
173-303-100(6)]	%					
Semi-Volatile Organic Compo	ounds					
Naphthalene	0.081	0.443	5	No	-	-
2-Methylnaphthalene	0.148	1.32	320^{3}	No	-	-
	0.091	0.879	340^{3}	No	-	-
Volatile Organic Compounds	5					
Halogenated/Chlorinated						
VOCs 1	-	-	-	-	-	-
Benzene	< 0.020	< 0.021	0.03	No	0.5	No
Toluene	0.027	0.085	7	No	-	-
Ethylbenzene	< 0.025	0.048	6	No	-	-
Total Xylenes	0.064	0.202	9	No	-	-
n-Propylbenzene	-	0.045	$8,000^3$	No	-	-
sec-Butylbenzene	-	0.080	$8,000^3$	No	-	-
	0.040	0.152	8003	No	-	-
Naphthalene	-	0.199	5	No	-	-
Metals	I				•	
	< 0.245	< 0.250	2	No	0.2	No
Arsenic	3.07	2.41	20	No	5	No
Cadmium	0.281	0.416	2	No	1	No
Total Chromium	10.3	9.85	19 /	No	5	No
Lead	8.63	16.1	$\frac{2,000^4}{250}$	No	5	No

All results, method reporting limits, and cleanup levels are presented in mg/Kg. Dangerous waste threshold values where published in WAC 173-303-090(8) are presented in milligrams per liter.

Results in **Bold** indicate a result above the MTCA Method cleanup level.

¹ The individual chemical constituents were not detected above the method reporting limit (MRL)

² Industrial MTCA Method A cleanup level

³ Select constituents have established MTCA Method A cleanup level. When a MTCA Method A cleanup level is not available, the MTCA Method B Standard Value is utilized for evaluation.

⁴ The MTCA Method A cleanup level for Chromium (III) is 2,000 mg/Kg and for Chromium (VI) is 19 mg/Kg



Depth of soil impact based on test pits completed during the initial investigation identified the following conditions:

- Ranch 19E approximately 515 tons of soil estimated to be removed
- Ranch 19W approximately 1,537 tons of soil estimated to be removed

Based on results of the initial investigation, groundwater is not anticipated to be encountered during remediation excavation. If groundwater is encountered, additional evaluation may be needed to meet MTCA regulatory requirements and applicable amendments to this remediation work plan will be required.

4.0 Remedial Objectives

4.1 Remedial Action Objectives

Remedial Action Objectives are narrative goals for a cleanup action that address how the cleanup fits into the overall MTCA cleanup process. The following Remedial Action Objectives have been identified for the primary contaminants found at the Site:

1. Petroleum contaminated soils (diesel range petroleum hydrocarbons) will be addressed to achieve MTCA Method A cleanup levels in accordance with MTCA, including engagement of Ecology under the Voluntary Cleanup Program and/or proceeding as an independent remedial action through use of remedial strategies that may include calculating alternate cleanup levels under WAC 173-340-700 for petroleum hydrocarbons; completing a risk-based evaluation; using of monitored natural attenuation (MNA); applying institutional and engineering controls with a restrictive covenant; etc., or a combination of these methods.

Guidance associated with remedial action evaluation is presented in WAC 173-340-360.

4.2 Basis for the Selected Remedy

The selected remedy also meets the other requirements for selection under WAC 173-340-360(2)(b), which include the following:

- 1. Using Permanent Solutions to the Maximum Extent Practicable. Excavation and offsite treatment or disposal is a permanent solution. Use of treatment technologies such as incineration for the full extent of impacted soil is not a permanent solutions to the maximum extent practicable because their costs are substantially disproportionate to their benefits compared to other options.
- 2. Providing for a Reasonable Restoration Time Frame. Cleanup goals will be achieved at the Site following excavation of accessible soils. Where soils cannot be fully excavated, the remedial solution is required to have reasonable restoration time frame. MTCA does not provide a definition for "reasonable restoration time frame" and this approach is best considered in evaluation with the toxicity, mobility, and accessibly of the contamination.



3. Considering Public Concerns. The public review process is not required for independently completed projects.

If in-place management of impacted soils is appropriate it must meet the following minimum requirement for selection of a cleanup action under WAC 173-340-360(2)(a):

- 1. Protect Human Health and the Environment. The selected remedy will protect human health and the environment in the short-term and long-term by removing discrete areas of localized soil contamination and preventing exposure to impacted soil via consolidation of such soil beneath impermeable concrete or asphalt structures.
- 2. Comply with Cleanup Standards. The selected remedy will comply with cleanup levels for soil.
- 3. Comply with Applicable State and Federal Laws. The selected remedy is expected to comply with applicable state and federal laws.
- 4. Provide Compliance Monitoring. If contamination remains, a compliance monitoring program will be required.

The Remediation Work Plan takes into consideration identified contaminants, project construction scope, regulatory guidance, and remediation objectives.

5.0 Remediation Activities

5.1 General Steps

Remedial activities will be performed in accordance with MTCA. Excavation extent will be determined based on the conditions encountered in the field and will be guided by field screening, including color, odor, sheen, and headspace volatile organic compounds (VOCs) measured with a photoionization detector (PID). The excavation extents, primarily the depth, will be informed by the initial investigation completed in September 2019.

Safety measures will be implemented at each property, as follows:

- Controlling traffic as needed during earthwork activities.
- Protecting the excavations on a daily basis, if the area is not backfilled immediately or a gentle slope (typically less than 1 to 4) cannot be achieved.
- Placing high-visibility fencing around each excavation area to provide a visual warning for the public, personnel, and/or trespassers, until the area is ready to be backfilled.
- Using warning tape or other barriers at the site during earthwork activities.

Only if the excavation exceeds 3-feet will backfill be placed. If PCS remains at the location, a landscaping geotextile fabric shall be placed prior to placement of clean backfill.



All excavated soils will be delivered to Anderson's Rock & Demolition Pits and PCS Facility for treatment. If debris or large rock are encountered and reasonably separable, these materials may be retained onsite or disposed as solid waste.

Given the fall conditions and generally moist soil conditions, dust abatement is not anticipated to be needed. However, if conditions occur and dust abatement is needed only the water needed to accomplish dust abatement will be used as wet soils are more difficult to excavate and transport and impair the use of field screening techniques.

If trucks cannot be placed in close proximity to the excavation area plastic sheeting or tarps will be placed under trucks during the loading activities.

5.2 Field Records

A record of all field work shall be kept on the field form included in Appendix A and in the field geologist log book. The field forms and log book shall be reviewed by the supervision Geologist on a daily basis.

5.3 Field Screening

All sample locations will be screened in the field using the following methods:

- Visual indicators of staining
- Odor
- Sheen test
- Photo-ionization detector (PID)

5.4 Confirmation Soil Sampling

Final discrete soil samples will be collected from the specific location that based on field screening suggests the highest potential for COCs. The confirmation sampling will be collected based on the following field criteria:

5.4.1 Pit Bottom Samples

- A minimum of 3 samples will be collected from the pit bottom from the excavation
- Where the total area of the excavation exceeds 500 square feet, then 1 additional pit bottom sample will be collected for every 1,000 additional square feet

5.4.2 Sidewall Samples

- Where the excavation depth exceed 3 feet below ground surface, a minimum of four sidewall samples will be collected
- Sidewall samples will be collected at a frequency of one sample per 50 linear feet of excavation sidewall



Sample labeling scheme shall consist of the following:

Ranch Number – Date – Unique Sample Number – Depth of Sample (e.g. R44 – 010120 – 01.01)

Sample locations within the established parameters above, will additionally use field indicators of impact to select sample locations with the greatest potential for residual impact. Soil samples at depths of up to 3-feet below ground surface where a safely accessed excavation is present shall be collected directly from the desired sample location. Where the sampling depth exceeds 3-feet, the soil sample shall be collected from the relatively undisturbed soil between the teeth of the excavator bucket.

Confirmation soil samples will be collected and analyzed by the following methodologies:

- Diesel and Heavy Oil by NWTPH-DxExt
- Benzene, Toluene, Ethylbenzene and Xylenes by Environmental Protection Agency (EPA)
 Method 8260C

All laboratory analysis shall be performed to demonstrate that the COCs are not present above the respective cleanup level.

5.4 Evaluation of Laboratory Results

Upon receipt of laboratory results review laboratory and method performance as provided in the QAPP.

6.0 Risk Screening Evaluation

This section describes the screening level risk assessment that will be conducted for the Site as part of the Remediation Work Plan if all PCS cannot be excavated. Sample locations or areas that do not meet MTCA cleanup levels will be described on tables and maps.

6.1 Potential Human Health Impacts

Data collected at the Site will be screened using Method A cleanup levels and standard Method B default values as developed by Ecology pursuant to Washington's MTCA Act (part VII of chapter 70.105D RCW) and released to stakeholders through the Cleanup Levels and Risk Calculation (CLARC) web site to determine whether concentrations of hazardous substances warrant further consideration with regard to potential human health impacts. Standard Method B cleanup levels will be adjusted for additive health effects associated with multiple hazardous substances and pathways of exposure in accordance with WAC 173-340-708. Locations that meet Method A or Method B cleanup levels may generally be used without future use restrictions on the property due to residual levels of contamination.

As described in WAC 173-340-700(6)(d), practical quantitation limits (PQLs) will also be considered during the screening level human health risk assessment. PQLs and Site screening levels that will be used



in the Work Plan are described in the QAPP in Appendix B. The importance of using laboratory methods that will provide PQLs at or below Site screening levels is acknowledged.

6.2 Potential Ecological Impacts

Potential ecological impacts will be evaluated by following the requirements for a terrestrial ecological evaluation (TEE) set forth in WAC 173-340-7491 through WAC 173-340-7493 to determine whether concentrations of hazardous substances warrant further consideration with regard to terrestrial receptors (including soil biota, plants, and wildlife), Site conditions identified through the Work Plan will be evaluated to determine whether the Site meets any of the no further evaluation criteria for a TEE in WAC 173-340-7491(1). The four no further evaluation criteria are:

- All soil contaminated with hazardous substances is, or will be, located below the point of compliance.
- All soil contaminated with hazardous substances is, or will be, covered by buildings, paved roads, pavement, or other physical barriers that will prevent plants or wildlife from being exposed to the soil contamination.
- There is less than 1.5 acres of contiguous undeveloped land on the Site or within 500 feet of the Site contaminated with hazardous substances and there is less than ¼ acre of contiguous undeveloped land on or within 500 feet of the Site affected by specific hazardous substances known to pose ecological concern.
- Concentrations of hazardous substances in soil do not exceed natural background levels.

The results of this evaluation will be documented in the Investigation Report. It is acknowledged that the no further evaluation criteria are dependent on institutional controls and/or completion dates for future development that are acceptable to Ecology.

If an exclusion from a TEE cannot be documented, then Site conditions will be evaluated to determine whether the Site meets any of the criteria for a site-specific TEE as set forth in WAC 173-340-7491. In summary, the site-specific TEE criteria are:

- The site is located on, or directly adjacent to, an area where management or land use plans will maintain or restore native or semi-native vegetation.
- The site is used by a threatened or endangered species.
- The area of contamination is located on a property that contains at least ten acres of native. vegetation within 500 feet of the contamination, not including vegetation beyond the property boundaries.
- Ecology determines that the site may present a risk to significant wildlife populations.

If none of these site-specific criteria apply to the Site, then a simplified TEE will be conducted as set forth in WAC 173-340-7492 and the results will be summarized in the remediation report. If one or more of these site-specific criteria apply to the Site, then a site-specific TEE will be conducted as set forth in WAC 173-340-7493 and the results will be summarized in the remediation report. WAC Table 749-3 will be used for initial screening purposes using the COCs used in the remediation report.



7.0 Reporting & Scheduling

Fulcrum anticipates completing proposed remediation activities as follows:

Table 3: Projected Schedule of Events

Projected Completion Date	Tasks
March 30, 2020	Submit public utility request
March 30, 2020	Submit request for soil treatment to Yakima Health District
April 1, 2020	Complete private utility locate
April 6 to April 17, 2020	Complete soil excavation
About 7 days following sample collection	Receive laboratory results
Before May 15, 2020	Issue Soil Remediation Report

The proposed timeline is dependent upon subcontractor availability and currently scheduled onsite activities. Approximately 2 weeks following completion of receipt and review of laboratory analysis, a draft report of the investigation findings will be issued by Fulcrum. The proposed timeline is additionally based on an anticipated 5-business day turn-around-time for receipt of sample analytical results following completion of onsite activities.

8.0 References


- EPA Requirements for Quality Assurance Project Plans, EAP QA/R-5, EPA/240/B-01/003, U. S. Environmental Protection Agency, March 2001.
- *Guidance for Quality Assurance Project Plans*, EAP QA/G-5, EPA/240/R-02/009, U. S. Environmental Protection Agency, December 2002.
- Guidance for Data Quality Assessment Practical Methods for Data Analysis, U.S. Environmental Protection Agency, EPA 600/R-96/084, EPA EZ/G9, QA97 Version, January 1998.
- Guidance for Remediation of Petroleum Contaminated Sites, Washington State Department of Ecology, Publication 10-09-057, November 2010, revised June 2016.
- *Incremental Sampling Methodology*, Interstate Technology & Regulatory Council, https://www.itrcweb.org/ism-1/, February 2012.
- *Model Toxics Control Act*, Washington State Department of Ecology, Washington Administrative Code 173-340.
- Test Methods for Evaluating Solid Waste, Physical/Chemical Methods, U.S. Environmental Protection Agency, EPA SW-846.



Figures

Figure 1: Site Location Figure 2: Smudge Pot Excavation






Fulcrum Environmental Consulting, Inc. 406 North Second Street, Yakima, Washington 98901 p: 509.574.0839 f: 509.575.8453 efulcrum.net Soil Remediation Ranch 19. 192902.15. KDA. 121319 Ranch 19 441 Williamson Road Sunnyside, WA

Site Location

FIGURE 1






Fulcrum Environmental Consulting, Inc. 406 North Second Street, Yakima, Washington 98901 p: 509.574.0839 f: 509.575.8453 efulcrum.net Smudge Pot Work Plan. 192902.15. NLM. 12/17/19

Ranch 19 West 441 Williamson Road Sunnyside, Washington

Site Location

FIGURE 2





Fulcrum Environmental Consulting, Inc. 406 North Second Street, Yakima, Washington 98901 p: 509.574.0839 f: 509.575.8453 efulcrum.net Smudge Pot Work Plan. 192902.15. NLM. 12/17/19

Ranch 19 East 441 Williamson Road Sunnyside, Washington

Site Location

FIGURE 3



<u>Appendix A</u>

Field Form

Ranch	Address			Field Lead:		Start Date/Time:	End Date/	Time:	_
Table 1: Labora	ntory Results	Table 2:	PCS						
Contaminant Present (Y/N) Dimension (approx.)				Feet					
Diesel	1100000 (1/11)	Length	(uppront)	1000					
Heavy Oil		Width							
Metals		Depth							
PAHs		Вериг							
171113	<u> </u>								
Estimated Volum	ne of PCS:	Trucks or	Trucks & Trailer:	Loads (Est.)					
Truck No.	Driver	Left (time)	How Full	Returned (time)					
Sample Plan									
Collect pit botton	m samples at 1 per 500-sq	uare feet							
AND Duplicate	s 3-ft or more collect side es at 10% of laboratory sa	mples							
Container	Per Location	Planned For	Ranch	Actual Collected					
4-ounce jars					1				
40-ml voa vials					1				
					2				
Laboratory Ana	alysis				3				
 Diesel and 	heavy oil by NWPTH – l	Diesel Extended (D	x)						
	EPA Method 8260		,		7				
	EPA Method 8270 – PM s	election following 1	review Dx results		5				
•					6				
Notes:									
·									
					1				
					2				
					3				
					4				
					5		<u></u>		
					6				
					2	;		<u>:</u>	

Ranch	Address	Field Lead:	Start Date/Time:	End Date/Time:



Table 3: Field Screening and Samples Collected

Sample	Color Odor	mples Col Sheen	VOCs (ppm)	Description	Soil Sample Y/N	Sample Number (R##-MMDDYY-##.Depth)	# of Jars	# of Voas	Duplicate Collected Here	Other
			(ppm)		1/11	(K##-MIMIDD11-##.DCptii)		Vuas	Conceted Here	



<u>Appendix B</u>

Project SAP / QAPP



Sampling & Analysis Plan Quality Assurance Project Plan Former Smudge Pot Storage Area Remediation

Ranch 19 441 Williamson Road Sunnyside, Washington

Project Number: 192902.15

December 17, 2019

Prepared for:

WA LAND MGMT, LLC c/o: Guy Kisling 22605 Southeast 56th Street #200 Issaquah, Washington 98029

Prepared by:

Fulcrum Environmental Consulting, Inc. 406 North 2nd Street Yakima, Washington 98901



TABLE OF CONTENTS

SECT	ION		PAGE
1.0	Data	Quality Objectives	1
2.0	Samp	oling Procedures	2
	2.1	Sampling Procedure for Soils	
	2.2	Sample Preparation for Various Analytical Methods	
	2.3	Decontamination	
	2.4	Soil Sample Containers, Preservation, and Holding Time Requirements	
	2.5	Investigation Derived Wastes	
	2.6	Sample Handling and Custody Requirements	
	2.7	Inspection/Acceptance Requirements for Supplies and Consumables	
3.0	Meas	surement Procedures	
	3.1	Data Acquisition Requirements (Non-direct Measurements)	7
	3.2	Data Management	7
4.0	Samp	ple Quality Control Requirements	8
	4.1	Field QC Requirements	8
	4.2	Laboratory QA/QC Requirements	8
5.0	Data	Management Procedures	9
6.0	Audi	ts and Reports	10
7.0	Data	Verification and Validation	10
8.0	Refe	rences	11
TABL	ES		
Table	1	Laboratory Analyte MQOs for Soil Analysis	1
Table	2	Soil Sample Type, Analytical Parameters, Preservation and Holding Times	
Table	3	QA/QC Requirements for Soil Analysis	
Table	4	Sample Coding	



1.0 Data Quality Objectives

The primary goal of this project is to accurately define magnitudes and extents of impact of petroleum hydrocarbons and other constituents in site soils post-remedial excavation. To do this, samples collected must be representative of site soil conditions. Variations in the level of site soil impact can occur due to natural environmental heterogeneity or may be caused by the sampling and analytical procedures, or sample collection and handling methods.

For this project to succeed, the precision (random error) and bias (systematic error) of the sample results must be low to reveal variability in concentrations between samples. Standard procedures will be used when collecting and handling soil samples to minimize any bias caused by the sampling process.

The precision and bias routinely obtained by the project laboratory for the selected analytical methods will meet the measurements quality objectives (MQOs) for this project. Table 1 lists the MQOs for assessing project data quality. Recovery limits (RL) and method reporting limit (MRL) are a function of the analytical methodology, laboratory equipment and concentration of other analytes in the sample. For instance, a sample with an appropriate methodology, sensitive laboratory equipment and very low or non-detect concentrations of analytes will typically achieve an exceptionally low MRL, often more than an order of magnitude below the MTCA cleanup regulations as the selected regulatory cleanup values. However, the same sample with a mixture of similar analytes may result in interferences among like analytes or sample dilution may result in significantly higher MRLs. As such, MRLs on samples collected during an investigation are likely to vary in RL and MRL.

These MQOs are based on adequacy and completeness of field sampling and performance characteristics of measurements done by the project laboratory.

Table 1: Laboratory Analyte MQOs for Soil Analysis

Analyte	Reporting Limit (mg/Kg)	LCS % Recovery Limits		Duplicate % RPD Limits	MS / MSD % recovery limits			
Petroleum Range Hydrocarbons								
Diesel by NWTPH-DxExt	20	65	135	30	65	135		
Heavy Oil by NWTPH-DxExt	50	NA	NA	NA	NA	NA		
Volatile Organic Compounds by EPA Meth	nod 8260							
Benzene	0.02	64.3	133	30	63.5	133		
Ethylbenzene	0.025	74	129	30	54.5	134		
m,p-Xylene	0.05	70	124	30	53.1	132		
o-Xylene	0.025	68.1	139	30	53.3	139		
Toluene	0.02	67	144	30	63.4	132		

mg/Kg milligrams per kilogram
LCS Laboratory Control Standard
RPD Relative Percent Difference

NA Not Applicable



Should additional analysis beyond those specified in Table 1 be required, all additional analysis will be completed within applicable MQOs as appropriate for the selected methodologies to meet both analysis method and regulatory requirements.

2.0 Sampling Procedures

Soil sampling procedures were selected based upon observed and anticipated field conditions. Sampling will be consistent with Environmental Protection Agency (EPA) protocols as set forth in the document titles, *Preparation of Soil Sampling Protocols: Sampling Techniques and Strategies*. Additionally, all soil samples for volatile analysis will be collected per Ecology's *Technical Memorandum #5: Collecting and Preserving Soil Samples for VOC Analysis*. Specific analytes will be selected based on Ecology's published document titled, *Guidance for Remediation of Petroleum Contaminated Sites, Publication 10-09-057*, Revised June 2016.

The following is a summary of collection procedures anticipated for soil sampling and a summary of sample preparation for sample analysis and decontamination procedures.

2.1 Sampling Procedure for Soils

Soil samples collected from excavation extents will be obtained by direct collection from the desired location if accessible, otherwise collected from the excavator bucket. Samples will be collected at locations and elevations with the highest field indicators of impact during remedial excavation. All samples will be collected by hand using new nitrile gloves.

Samples will be collected into labeled, 4-ounce borosilicate sample jars. The number of sample containers at each location will be determined by sample location and analyses to be performed.

Each 40-milliliter vial sample utilized for EPA Method 8260 analysis will be collected using an impinger sampler to minimize loss of volatile organic compounds. Disposable, single-use impingers are utilized to collect a measured soil sample of undisturbed soil. Following each sample collection, the sample will be immediately placed into a new 40-milliliter glass vial with Teflon-lined lid. Consistent with Ecology guidance, sample preparation, including extraction by Methanol will be completed at the laboratory within 48-hours of sample collection. If laboratory provided methanol preserved sample vials are used, samples will be analyzed within 14-days of collection.

Field collected samples will be divided into two portions. The first portion will be placed in a clean, appropriately sized sample jar or vial and immediately placed on ice for laboratory analysis. The second portion of the sample will be placed in a re-closeable plastic bag for field screening.

Field screening will include observation, sheen analysis and/or headspace sampling. Observation refers to visual/olfactory observation of the sample for obvious indications of contamination. Sheen analysis involves dropping a small volume of sample into a container of clean water and observing any resulting sheen produced on the water surface. Headspace sampling is a measurement of the relative concentration



of volatile organic carbons (VOCs) in the soil sample headspace. For headspace sampling, the sample will remain in the sealed plastic bag for approximately 10 minutes in a warm area to promote volatilization. The probe of a photo-ionization detector (PID) will then be inserted into the bag and the highest response will be recorded for each sample. The intent of field screening for VOCs is limited to identification of presence of elevated concentrations only in order to assist with efficient selection of soil samples for laboratory analysis and is not intended to be utilized to document VOC concentrations, absence of impact or correlation of field screening data with laboratory analysis results.

Record of physical description of the soil including grain proportions, color, odor, location, condition, etc. will be completed in the field.

2.2 Sample Preparation for Various Analytical Methods

The following general procedures will be used during sample collection and preparation. Wear new disposable protective gloves during sampling activities. Preserve samples and adhere to holding times as described in Table 2 as required by the analytical method being requested. Check the sample lid to ensure cleanliness and that it is secured. Carefully label the sample container with the appropriate information. Use only waterproof ink to complete sample container labels. After label information has been completed, secure labels to the sample container by wrapping clear tape over the label and around the container. Transfer samples to a cooler. Preserve samples in the field on ice at 4° Celsius pending preparation for field analysis or shipping to the analytical laboratory.

At a minimum, the following information will be recorded in the field logbook:

- 1. Sample location designation
- 2. Sampling location condition and pertinent observations of surrounding area
- 3. Weather conditions
- 4. Manufacturer, model number and calibration results of meters/instruments used to measure field parameters
- 5. Soil color, grain size, and visual and olfactory indications of contamination
- 6. Soil sample interval/depth
- 7. Time of sample collection
- 8. Initials of samplers
- 9. Laboratory analysis to be performed
- 10. Any miscellaneous comments or observations

The following field information will additionally be included on the chain-of-custody forms:

- 1. Sample identification
- 2. Time of sample collection
- 3. Initials of samplers
- 4. Laboratory analysis to be performed
- 5. Any miscellaneous comments or observations



2.3 Decontamination

Every effort will be made to minimize the need for decontamination of sampling equipment through the use of dedicated sampling equipment (i.e. bowls, spoons, etc.): however, the use of non-dedicated sampling equipment (i.e., hand trowels, hand augers, split spoons, etc.) may be required in some locations. In these cases, the non-dedicated sampling equipment will be decontaminated prior to each use. Field equipment, that directly contacts samples or sample containers, will be decontaminated prior to use and between each sampling event. The following procedures will be used to prevent cross contamination of samples collected during this project.

Gross contamination will be removed by dry brushing or wiping the equipment with disposable toweling. Field equipment will then be washed in a solution of AlconoxTM, LiquinoxTM or comparable non-hazardous laboratory detergent product and deionized water. Washed equipment will be double rinsed with deionized water. Rinsate will be discharged to the sample collection location. Field equipment will then be placed on clean aluminum foil or similar material.

All sample containers will be pre-cleaned as required by EPA guidance titled, *Test Methods for Evaluating Solid Waste* (SW-846); Standard Methods for the Examination of Water and Wastewater; and laboratory QA/QC protocol by the container manufacturer or selected analytical laboratory prior to shipping for sample collection. Sample containers will not be used for sample collection and storage without being certified clean by the manufacturer or analytical laboratory.

After the sample is collected and the container lids are tightly sealed, the exterior portion of the sample container will be cleaned. Care will be taken to ensure that sample labels remain legible during the exterior container cleaning.

2.4 Soil Sample Containers, Preservation, and Holding Time Requirements

Required sample containers, preservation methods, and holding times for the analytical parameters selected are summarized in Table 2. Analytical precision and accuracy are defined by the analytical test methodology and the project laboratory's QA/QC program. All analytical method accuracy, precision, and detection limits are within laboratory certification requirements and below the associated selected contaminant concentration cleanup values as established under MTCA Method A, or default Method B levels where Method A levels have not been established.

Table 2 presents the sample types, location, analytical parameters and methods, sample preservation, and specific requirements for sample container size and type for sample collected. Table 3 summarizes the number of QA/QC samples to be submitted according to method requirements.



Table 2: Soil Sample Type, Analytical Parameters, Preservation and Holding Times

Analytical Parameter and Method	Sample Preservation	Sample Containers, Other Comments	Maximum Holding Time
Diesel and Heavy Oil by NWTPH- DxExt	Cool to 4° C	4 oz. glass jar with Teflon lined lid	Preserve within 14 days, Analyze within 40 days
Volatile Organic Compounds by EPA Method 8260	Cool to 4° C	Two, 40-millimeter glass with septum lid	Preserve with 48-hours, Analyze within 14-days

Table 3: QA/QC Requirements for Soil Analysis

Analytical Parameter and Method	Total Field Samples ^a	QA/QC Sample Summary Analyses/Containers				
	/Containers	Organic MS/MSD	Inorganic MS/MSD	Rinsate Blanks ^b	Trip Blanks	
Diesel by NWTPH-Dx	# + d	2/2	NA	None	None	
Volatile Organic Compounds by EPA Method 8260	# + d	1/1	NA	None	None	

^a Total number of field samples are estimated.

NA Not Applicable

d Duplicate Sample

One duplicate sample will be collected for each analytical methodology at the ranch.

2.5 Investigation Derived Wastes

Every effort will be made to minimize generation of investigation derived wastes (IDW) that cannot be disposed of as solid waste. All extra soil volume collected for a sample will remain at the sampling location. Disposable personal protective equipment and sampling equipment will double bagged in plastic garbage bags, labeled and disposed of at an approved solid waste facility.

2.6 Sample Handling and Custody Requirements

The project laboratory will provide sample containers for sample collection, and chain-of-custody forms. Each sample will be placed in the appropriate documented clean, laboratory provided container and sealed. Disposable nitrile gloves will be worn during the sampling process. Gloves will be changed between sample areas or if the gloves have been damaged in any manner. Sample documentation will be completed immediately following sample collection. The chain-of-custody forms will be filled out in ink and placed in a re-sealable plastic bag to avoid damage. Duplicates will be maintained in Fulcrum's files. The original will be sent to the analytical laboratory. The forms will include the date, site designation, sample designation, analysis required, turn-around-time, preservation and authorized signatures.

Each sample will have a unique identification number. The specific designation for sample codes is presented in Table 4 and is based on the date, sample location identification, sample matrix and consecutive sample number. At a minimum, label information will include:

^b Rinsate blanks only required for 1 in 20 samples per non-dedicated sampling device.



- 1. Initials of the collector
- 2. Date and time of collection
- 3. Location
- 4. Sample number

A chain-of-custody record will be filled out and accompany each sample to document sample possession from collection through analytical reporting. A copy of this record will be maintained with analytical results and be included in subsequent data reporting.

Table 4: Sample Coding

Ranch Number	Sample Type	Consecutive Sample Number (assigned sequentially)	Sample Interval (depth in feet below ground surface)	Example
##	Date	01-20	0.01 (1-foot), .02 (2-feet), etc. bgs	R##-010120-01.01

Samples destined for analysis by an offsite laboratory will be cold transported in a cooler. Packaging and shipping of sample for analyses and storage will be per the following protocol:

- 1. Roughly 2 inches of cushioning material will be placed in the bottom of the cooler
- 2. Sample containers will be placed in the cooler in a manner to prevent breakage
- 3. Glass jars will be placed in re-sealable plastic bags and centered in the cooler to prevent breakage
- 4. Samples will be packaged with ice enclosed in re-sealable plastic bags or freeze packs ("blue ice")
- 5. QA/QC samples will be packaged with the samples that were collected that day
- 6. Free space in the cooler will be filled with cushioning material
- 7. Chain-of-custody paper work will be placed in plastic bags and placed inside the cooler
- 8. Cooler will be wrapped with strapping tape and signed custody seal(s) will be used to secure the cooler lid
- 9. Samples will be shipped by commercial carrier for next day delivery. However, samples will not be shipped on Fridays, weekends, or immediately preceding a holiday, due to next day delivery limitations
- 10. Use of separate coolers to protect more delicate sample containers, such as 40 milliliter vials, is encouraged

When delivery for a sample set is scheduled, the shipper will receive a copy of the shipping manifest/tracking number. The documentation will be placed in the project file.

Upon receipt of the shipping container, the laboratory will inspect the integrity of the shipping container seal. The cooler will be opened and the shipment checked against the chain-of-custody record. Any inconsistencies or problems with a sample shipment will be noted and resolved. Once at the laboratory, the samples will be tracked through the laboratory by internal custody procedures and the laboratory's QA/QC procedures will be followed.



2.7 Inspection/Acceptance Requirements for Supplies and Consumables

Upon receipt, all supplies and consumable will be inspected for damage, including the shipping carton, individual packages and product integrity. Any product that is cracked, leaking or otherwise damaged or whose individual package is torn or opened to the environment will be discarded or returned.

A certificate indicating the sample container lot and statement that they have been cleaned in accordance to applicable standards will accompany each carton of new sample containers. A statement of cleaning will also be provided for sample containers that have been pre-cleaned and pre-preserved by the laboratory.

All reasonable effort will be made to ensure all sampling supplies and consumable are acquired prior to initiating field activities.

The following is a minimum list of supplies and consumable that will be required to conduct soil sampling:

- 1. Field notebook
- 2. Disposable nitrile gloves
- 3. Sampling equipment for soils (Hydraulic-push sampler, hand coring sampler, plastic spoons and bowls, stainless steel shovel, color chart for soil and water)
- 4. Camera
- 5. Sample containers: 4-ounce borosilicate with Teflon lined lids and 40 milliliter glass vials with septum lids
- 6. Sample labels
- 7. Ice or "Blue Ice" reusable packages
- 8. Chain-of-custody forms
- 9. Decontamination equipment (buckets, spray bottles, brushes, soap, etc.)
- 10. Deionized water
- 11. Insulated shipping containers (coolers or ice chests)

3.0 Measurement Procedures

3.1 Data Acquisition Requirements (Non-direct Measurements)

Non-direct data measurements are those items that require a subjective assessment. Items such as weather, problems with sample collection, etc. will be logged in the field notebook.

3.2 Data Management

Field data will be recorded in the field notebooks by, or under the supervision of a licensed Geologist. Daily observation reports will be generated by Fulcrum and submitted for internal review. Laboratory analytical reports will be transmitted to Fulcrum electronically. The project laboratory will review and validate analytical data in accordance with their internal QA/QC program.



All field notebooks and the project laboratory's analytical data will be reviewed by Fulcrum to assure that all pertinent information is accounted for and is correlated. Fulcrum will complete review of sample collection and laboratory analytical data and summarize the information in a database or report format.

Hard copies of all field notebooks, chain-of-custody forms, analytical data, laboratory reports, assessment reports and all electronic databases will be maintained by Fulcrum until project completion. Support and backup data will be archived for 5 years beyond completion of the project.

4.0 Sample Quality Control Requirements

4.1 Field QC Requirements

Field quality control will be maintained through the use of standard operating procedures for sample collection, handling and documentation. Any problems occurring during the sample process will be recorded in the field notebook or field datasheets.

Duplicate samples will be collected as part of sampling activities. The number, type and handling of QA/QC samples are specified in Table 3 for soil samples.

Duplicate samples are used to check the precision of field collection or laboratory analyses and verifies repeatability of the sample data. Duplicates are collected at the same time as the sample. The duplicate sample will be collected by evenly splitting the collected sample such that the both sub-samples are comparable and representative of the single sample. Duplicate soil samples will be collected from a sample location that is believed to have elevated levels of a particular compound.

4.2 Laboratory QA/QC Requirements

The selected project laboratory will be appropriately Ecology and EPA certified to complete the selected analysis.

Laboratory quality control tests consist of method blanks, matrix spikes, as well as duplicate and check standards (laboratory control standards). Surrogate recoveries will also be included for the organic analyses. Surrogate recoveries will be used to judge the accuracy for analysis of similar target analytes. Analytical precision can be estimated from duplicate and check standards, duplicate sample analysis and duplicate spiked sample analyses. Analytical bias will be estimated from matrix spikes, matrix spike duplicates and check standards. Recoveries from check standards provide an estimate of bias due to calibration. Mean percent recoveries of spiked sample analyses provide an estimate of bias due to interference.

The laboratory staff will report results of quality control analyses in the same units as expressed for the MQOs. They will also conduct quality assurance review of all analytical data generated at the project laboratory prior to releasing the data to the project manager.



The laboratory will be responsible for following their established QA/QC procedures and those required by the analytical methods. The following minimum QA/QC procedures will apply:

- 1. Sample holding and preservation requirements will be in accordance with analytical method reference parameters
- 2. Instrument tuning and calibration will be performed as required by the analytical method and equipment manufacturer
- 3. Laboratory QA/QC samples (duplicates) will be analyzed at frequencies specified by EPA, Ecology, and analytical reference methods
- 4. The laboratory will review the data package for performance, quality, and completeness
- 5. The method detection limit for the parameter analyzed will be below regulatory guidance levels
- 6. All laboratory parameters (recoveries, spikes, duplicates, etc.) are within their stated limits

Laboratory instrumentation will meet applicable calibration requirements to ensure that the instrumentation is capable of producing acceptable quantitative data. Initial calibration demonstrates that the instrument is capable of acceptable quantitative performance at the onset of analysis. Calibration during operation verifies acceptable performance of the instrument on a day-to-day basis. Tuning and instrument performance criteria will also be established, as appropriate, to ensure that instrument measurements may be interpreted correctly.

Laboratory calibration procedures are specified in the protocol for the specific analytical methods used. When there are no previously defined specifications, the calibration procedures will include:

- An initial and final three-point calibration before and after a run.
- A mid-range calibration after every tenth sample.

5.0 Data Management Procedures

At the completion of each sampling event, all field data and laboratory analytical data will be compiled and evaluated against the project MQOs.

Field methods and forms will be reviewed to ensure consistency. Field datasheets will be checked for missing or improbable measurements before leaving each site. Field data entered into spreadsheets or databases will be checked against the field datasheets for errors or omissions. Missing or unusual field parameter data will be omitted from the data set.

Field replicate variability will be evaluated by calculating the relative percent difference (RPD) for each duplicate set of samples and compared to the MQOs listed in Table 1.

Laboratory-generated data review and reporting will follow the procedures outlined in the laboratory's quality assurance program. Results will be checked for missing or questionable data. Individual data which fails to achieve QA/QC objectives will be flagged with appropriate qualifiers and their use restricted as



appropriate. A standard case narrative of laboratory QA/QC results will be issued by the laboratory for each sampling event.

If the data review and verification suggest significant problems with QA/QC for a sample event, the sample event or individual sample may be reanalyzed by the laboratory or resampled as necessary.

6.0 Audits and Reports

The project laboratory participates in performance and system audits of their routine procedures and is an environmental laboratory accredited by the Washington State Department of Ecology as of July 9, 2019. See the following link for accreditations associated with Fremont Analytical:

https://fortress.wa.gov/ecy/laboratorysearch/SearchLabName.aspx

Results of the laboratory's performance and system audits of their routine procedures are available from the laboratory on request.

7.0 Data Verification and Validation

As part of data review, field notes and data from the laboratory will be reviewed for errors and omissions and to ensure that data are correct, complete, meet investigation objectives, and are consistent. Other items that will be reviewed include:

- Results for quality control samples described in Quality Control section of this document accompany sample results
- Quality control results indicate that acceptance criteria were met
- Data qualifiers are properly assigned where necessary
- Data specified in the Sampling Design section above were obtained
- Methods and protocols specified in this QAPP were followed

After receiving the data package, Fulcrum will verify that the results have met the MQOs for bias, precision and accuracy. Precision will be estimated by calculating the RPD for the field duplicate results. Analytical bias is assumed to be within acceptable limits if laboratory quality control limits are met for blanks, matrix spikes and check standards. Overall accuracy will be assessed by comparing the measured result with the true value of the blind reference sample. If appropriate, sampling procedures, quality control steps or analytical procedures will be modified to address identified problems.

Once the data have been reviewed, verified and validated, the project manager will determine if the data can be used toward the project goals and objectives. A technical report will be prepared at the completion of all sampling and will include the following:



- Maps of the investigation area showing site features, soil and groundwater sample locations, water levels, groundwater flow direction, contaminant concentrations and distribution
- Description of field and laboratory methods
- Discussion of data quality and the significance of any problems encountered
- Summary tables of field and analytical data
- Discussion of water quality results. Significant or potentially significant findings
- Recommendations based on project goals if appropriate

8.0 References

- *D3370-18: Standard Practices for Sampling Water*, ASTM Standards on Environmental Sampling, Designation: Pages 110-116, 2018.
- EPA Requirements for Quality Assurance Project Plans, EAP QA/R-5, EPA/240/B-01/003, U. S. Environmental Protection Agency, March 2001.
- Guidance for Quality Assurance Project Plans, EAP QA/G-5, EPA/240/R-02/009, U. S. Environmental Protection Agency, December 2002.
- Guidance for Data Quality Assessment Practical Methods for Data Analysis, U.S. Environmental Protection Agency, EPA 600/R-96/084, EPA EZ/G9, QA97 Version, January 1998.
- Guidance for Remediation of Petroleum Contaminated Sites, Washington State Department of Ecology, Publication 10-09-057, November 2010, revised June 2016.
- *Model Toxics Control Act*, Washington State Department of Ecology, Washington Administrative Code 173-340.
- Test Methods for Evaluating Solid Waste, Physical/Chemical Methods, U.S. Environmental Protection Agency, EPA SW-846.



Appendix C

Site Photographs





Looking southeast - excavation extent with average excavation depth of approximately 1 to 2 feet bgs.



Localized area within central portion of excavation, approximately 5 to 6 feet bgs.



Looking southeast - central area of excavation to depth of approximately 3 to 4 feet bgs.



Looking east - final excavation extent.



Appendix D

Soil Treatment Receipts



Yakima Health District 1210 Ahtanum Ridge Drive Union Gap, Washington 98903 Phone (509) 575-4040

June 18, 2020

Mr. Jeremy Lynn C\O Fulcrum Environmental Services 406 North 2nd Street Yakima, WA 98901

RE: WA Land Management, Ranches 16 East, 19 East, 19 West, 36 and 47, Yakima County, WA: Petroleum Contaminated Soil

Mr. Jeremy Lynn,

This office has reviewed the data on the above mentioned project. The data submitted indicates that the contaminant which requires remediation is diesel. Based on the data submitted it has been determined that the soil may be processed as one batch at the Anderson PCS Facility provided that all handling is in accordance with the procedure that has been approved by this office and Washington State Department of Ecology. This letter is to notify you that currently the soil will be considered to be stored on the property and no treatment can begin until the total fee is paid. Waste material may be stored for up to 90 days. Anderson PCS Facility will notify me of the total number of tons delivered for treatment and I will bill you for the remainder of the fee at that time.

FEE ACCOUNT:

Fulcrum Environmental Services

PROJECT NAME:

19 East, 19 West, 36 and 47

WA Land Management, Ranches 16 East,

Yakima County

, WA

PRE-TREATMENT AUTHORIZATION:

(Based on time spent prior to soil delivery

to the site at \$141/hour)

TONNAGE FEE AT \$0.60 PER TON:

To be determined after delivery

BALANCE OWED:

To be billed after delivery

If you have any questions regarding this letter, please contact me at (509) 249-6562.

Sincerely,

Ted Silvestri, RS

Environmental Health Specialist

cc:

Anderson PCS Facility

DTG Enterprises Inc.

Date Invoice # 10/19/2020 130380

Invoice

PO Box 14203 Mill Creek, WA 98082 425-549-3000

Bill To:	
WA. LAND 22605 SE 56 Suite 200 Issaquah, WA	

Please make checks payable to "DTG Enterprises Inc."				
Terms	Due Date			
Net 30	11/18/2020			

		E-mail		All Past Due Invoices Are Subj			
	accounting@dtgrecycle.com			۱ ۲	ges & Late Fee Month 18% F	es Computed at Per Annum	
Item	Date	Desc	ription	Quantity	Rate	Amount	

-		produced enough renewable biomass fuel from vaste to power 2,149 homes for an entire year	Total		\$46,807.10
					.,,
PCS - Petroleu	10/23/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523218 / RANCH 19 Refuse Collection Tax	21.79	30.00	653.70T 1,626.50
PCS - Petroleu	10/23/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523203 / RANCH 19	22.54	30.00	676.20T
PCS - Petroleu	10/22/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523185 / RANCH 19	24.81	30.00	744.30T
PCS - Petroleu	10/22/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523189 / RANCH 19	23.53	30.00	705.90T
PCS - Petroleu	10/22/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523160	23.33	30.00	699.90T

DTG Enterprises Inc.

PO Box 14203 Mill Creek, WA 98082 425-549-3000

Date	Invoice #
10/26/2020	131159

Invoice

Bill To:	
WA. LAND MGMT. LLC. 22605 SE 56TH Street Suite 200 Issaquah, WA 98029	

Please make checks payable to "DTG Enterprises Inc."		
Terms Due Date		
Net 30	11/25/2020	

		E-mail		ue Invoices Are ges & Late Fee	
	accor	unting@dtgrecycle.com		Month 18% Po	
Item	Date	Description	Quantity	Rate	Amount
PCS - Petroleu	10/26/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523299 / RANCH 19 EAST	25.93	30.00	777.90T
PCS - Petroleu	10/26/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523298 / RANCH 19 EAST	28.24	30.00	847.20T
PCS - Petroleu	10/26/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523296 / RANCH 19 EAST	26.56	30.00	796.80T
PCS - Petroleu	10/26/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523301 / RANCH 19 EAST	21.77	30.00	653.10T
PCS - Petroleu	10/26/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523319 / RANCH 19 EAST	26.4	30.00	792.00T
PCS - Petroleu	10/26/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523316 / RANCH 19 EAST	28.53	30.00	855.90T
PCS - Petroleu	10/26/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523327 / RANCH 19 EAST	24.41	30.00	732.30T
PCS - Petroleu	10/26/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523332 / RANCH 19 EAST	21.76	30.00	652.80T
PCS - Petroleu	10/26/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523323 / RANCH 19 EAST	26.91	30.00	807.30T
PCS - Petroleu	10/26/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523342 / RANCH 19 EAST	25.51	30.00	765.30T
PCS - Petroleu	10/26/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523348 / RANCH 19 EAST	27.03	30.00	810.90T
PCS - Petroleu	10/26/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523365 / RANCH 19 EAST	23.17	30.00	695.10T
PCS - Petroleu	10/27/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523449 / RANCH 19 EAST	24.08	30.00	722.40T
PCS - Petroleu	10/27/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523446 / RANCH 19 EAST	24.92	30.00	747.60T
PCS - Petroleu	10/27/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523429 / RANCH 19 EAST	23.88	30.00	716.40T
PCS - Petroleu	10/27/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523411 / RANCH 19 EAST	22.96	30.00	688.80T
PCS - Petroleu	10/27/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523407	26.07	30.00	782.10T
PCS - Petroleu	10/27/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523408 / RANCH 19 EAST	19.87	30.00	596.10T
PCS - Petroleu	10/27/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523404 / RANCH 19 EAST	28.6	30.00	858.00T

DTG Enterprises Inc.

PO Box 14203 Mill Creek, WA 98082 425-549-3000

Invoice

Date	Invoice #
10/26/2020	131159

Bill To:	
WA. LAND MGMT. LLC. 22605 SE 56TH Street Suite 200 Issaquah,WA 98029	

Please make checks payable to "DTG Enterprises Inc."		
Terms	Due Date	
Net 30	11/25/2020	

	accoi	E-mail unting@dtgrecycle.com	Finance Char	oue Invoices Ar ges & Late Fear Month 18% I	es Computed at
Item	Date	Description	Quantity	Rate	Amount
PCS - Petroleu	10/27/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523393 / RANCH 19 EAST	24.93	30.00	747.90T
PCS - Petroleu	10/27/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523383 / RANCH 19 EAST	25.41	30.00	762.30T
PCS - Petroleu	10/27/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523385 / RANCH 19 EAST	25.42	30.00	762.60T
PCS - Petroleu	10/27/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523442 / RANCH 19 EAST	25.76	30.00	772.80T
PCS - Petroleu	10/27/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523451 / RANCH 19 EAST	20.99	30.00	629.70T
PCS - Petroleu	10/27/2020	Petroleum contaminated soil per ton or \$1,500 inimum - TKT#523475 / RANCH 19 EAST	23.73	30.00	711.90T
PCS - Petroleu	10/27/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523486 / RANCH 19 EAST	27.71	30.00	831.30T
PCS - Petroleu	10/28/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523562 / RANCH 19 EAST	26.21	30.00	786.30T
PCS - Petroleu	10/28/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523555 / RANCH 19 EAST	24.72	30.00	741.60T
PCS - Petroleu	10/28/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523507 / RANCH 19 EAST	28.45	30.00	853.50T
PCS - Petroleu	10/28/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523508 / RANCH 19	22.37	30.00	671.10T
PCS - Petroleu	10/28/2020	Petroleum contaminated soil per ton or \$1,500 minimum - TKT#523619 / RANCH 19	26.99	30.00	809.70T
PCS - Petroleu	10/28/2020	Petroleum contaminated soil per ton or \$1,500 minimum -	21.63	30.00	648.90T
		TKT#523631 / RANCH 19 Refuse Collection Tax		3.60%	864.99
		produced enough renewable biomass fuel from vaste to power 2,149 homes for an entire year	n Total		\$24,892.59



Appendix E

Laboratory Results



3600 Fremont Ave. N.
Seattle, WA 98103
T: (206) 352-3790
F: (206) 352-7178
info@fremontanalytical.com

Fulcrum Environmental Ryan Mathews 406 N. 2nd Street Yakima, WA 98901

RE: Ranch 19 East

Work Order Number: 2010457

November 04, 2020

Attention Ryan Mathews:

Fremont Analytical, Inc. received 9 sample(s) on 10/28/2020 for the analyses presented in the following report.

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Sample Moisture (Percent Moisture)

Volatile Organic Compounds by EPA Method 8260D

This report consists of the following:

- Case Narrative
- Analytical Results
- Applicable Quality Control Summary Reports
- Chain of Custody

All analyses were performed consistent with the Quality Assurance program of Fremont Analytical, Inc. Please contact the laboratory if you should have any questions about the results.

Thank you for using Fremont Analytical.

Sincerely,

Brianna Barnes Project Manager

DoD-ELAP Accreditation #79636 by PJLA, ISO/IEC 17025:2017 and QSM 5.3 for Environmental Testing ORELAP Certification: WA 100009 (NELAP Recognized) for Environmental Testing Washington State Department of Ecology Accredited for Environmental Testing, Lab ID C910

Date: 11/04/2020



CLIENT: Fulcrum Environmental Work Order Sample Summary

Project: Ranch 19 East **Work Order:** 2010457

Lab Sample ID	Client Sample ID	Date/Time Collected	Date/Time Received
2010457-001	R19E-102720-01.2	10/27/2020 9:35 AM	10/28/2020 9:28 AM
2010457-002	R19E-102720-02.5.5	10/27/2020 9:45 AM	10/28/2020 9:28 AM
2010457-003	R19E-102720-03.3	10/27/2020 9:55 AM	10/28/2020 9:28 AM
2010457-004	R19E-102720-04.2.5	10/27/2020 10:30 AM	10/28/2020 9:28 AM
2010457-005	R19E-102720-05.2	10/27/2020 10:15 AM	10/28/2020 9:28 AM
2010457-006	R19E-102720-06.2	10/27/2020 10:20 AM	10/28/2020 9:28 AM
2010457-007	R19E-102720-07.2	10/27/2020 10:23 AM	10/28/2020 9:28 AM
2010457-008	R19E-102720-08.3	10/27/2020 10:53 AM	10/28/2020 9:28 AM
2010457-009	R19E-102720-09.3	10/27/2020 11:00 AM	10/28/2020 9:28 AM

Note: If no "Time Collected" is supplied, a default of 12:00AM is assigned



Case Narrative

WO#: **2010457**Date: **11/4/2020**

CLIENT: Fulcrum Environmental

Project: Ranch 19 East

I. SAMPLE RECEIPT:

Samples receipt information is recorded on the attached Sample Receipt Checklist.

II. GENERAL REPORTING COMMENTS:

Results are reported on a wet weight basis unless dry-weight correction is denoted in the units field on the analytical report ("mg/kg-dry" or "ug/kg-dry").

Matrix Spike (MS) and MS Duplicate (MSD) samples are tested from an analytical batch of "like" matrix to check for possible matrix effect. The MS and MSD will provide site specific matrix data only for those samples which are spiked by the laboratory. The sample chosen for spike purposes may or may not have been a sample submitted in this sample delivery group. The validity of the analytical procedures for which data is reported in this analytical report is determined by the Laboratory Control Sample (LCS) and the Method Blank (MB). The LCS and the MB are processed with the samples and the MS/MSD to ensure method criteria are achieved throughout the entire analytical process.

III. ANALYSES AND EXCEPTIONS:

Exceptions associated with this report will be footnoted in the analytical results page(s) or the quality control summary page(s) and/or noted below.



Qualifiers & Acronyms

WO#: **2010457**

Date Reported: 11/4/2020

Qualifiers:

- * Flagged value is not within established control limits
- B Analyte detected in the associated Method Blank
- D Dilution was required
- E Value above quantitation range
- H Holding times for preparation or analysis exceeded
- I Analyte with an internal standard that does not meet established acceptance criteria
- J Analyte detected below Reporting Limit
- N Tentatively Identified Compound (TIC)
- Q Analyte with an initial or continuing calibration that does not meet established acceptance criteria (<20%RSD, <20% Drift or minimum RRF)
- S Spike recovery outside accepted recovery limits
- ND Not detected at the Reporting Limit
- R High relative percent difference observed

Acronyms:

%Rec - Percent Recovery

CCB - Continued Calibration Blank

CCV - Continued Calibration Verification

DF - Dilution Factor

DUP - Sample Duplicate

HEM - Hexane Extractable Material

ICV - Initial Calibration Verification

LCS/LCSD - Laboratory Control Sample / Laboratory Control Sample Duplicate

MB or MBLANK - Method Blank

MDL - Method Detection Limit

MS/MSD - Matrix Spike / Matrix Spike Duplicate

PDS - Post Digestion Spike

Ref Val - Reference Value

REP - Sample Replicate

RL - Reporting Limit

RPD - Relative Percent Difference

SD - Serial Dilution

SGT - Silica Gel Treatment

SPK - Spike

Surr - Surrogate



Work Order: **2010457**Date Reported: **11/4/2020**

Client: Fulcrum Environmental Collection Date: 10/27/2020 9:35:00 AM

Project: Ranch 19 East

Lab ID: 2010457-001 **Matrix:** Soil

Client Sample ID: R19E-102720-01.2

Analyses	Result	Batch ID: 30217 Analyst: D 18.7 mg/Kg-dry 1 10/31/2020 4:55:52 46.8 mg/Kg-dry 1 10/31/2020 4:55:52 50 - 150 %Rec 1 10/31/2020 4:55:52 50 - 150 %Rec 1 10/31/2020 4:55:52 50 - 150 %Rec 1 10/31/2020 4:55:52 18.8260D Batch ID: 30262 Analyst: K 0.0247 mg/Kg-dry 1 11/3/2020 12:33:30 0.0247 mg/Kg-dry 1 11/3/2020 12:33:30 0.0309 mg/Kg-dry 1 11/3/2020 12:33:30 0.0617 mg/Kg-dry 1 11/3/2020 12:33:30 0.0309 mg/Kg-dry 1 11/3/2020 12:33:30 0.0309 mg/Kg-dry 1 11/3/2020 12:33:30 85.2 - 113 %Rec 1 11/3/2020 12:33:30 85.5 - 110 %Rec 1 11/3/2020 12:33:30 88.6 - 109 %Rec 1 11/3/2020 12:33:30 Batch ID: R63094 Analyst: R	Date Analyzed		
Diesel and Heavy Oil by NWTPH	-Dx/Dx Ext.		Batch	ı ID:	30217 Analyst: DW
Diesel (Fuel Oil)	ND	18.7	mg/Kg-dry	1	10/31/2020 4:55:52 AM
Heavy Oil	ND	46.8	mg/Kg-dry	1	10/31/2020 4:55:52 AM
Surr: 2-Fluorobiphenyl	68.4	50 - 150	%Rec	1	10/31/2020 4:55:52 AM
Surr: o-Terphenyl	84.8	50 - 150	%Rec	1	10/31/2020 4:55:52 AM
Volatile Organic Compounds by	EPA Method	8260D	Batch	ı ID:	30262 Analyst: KT
Benzene	Batch ID: 30217 Analyst: DV	11/3/2020 12:33:30 PM			
Toluene	ND	11/3/2020 12:33:30 PM			
Ethylbenzene	ND	0.0309	mg/Kg-dry	1	11/3/2020 12:33:30 PM
m,p-Xylene	ND	0.0617	mg/Kg-dry	1	11/3/2020 12:33:30 PM
o-Xylene	ND	0.0309	mg/Kg-dry	1	11/3/2020 12:33:30 PM
Surr: Dibromofluoromethane	96.9	85.2 - 113	%Rec	1	11/3/2020 12:33:30 PM
Surr: Toluene-d8	99.0	88.5 - 110	%Rec	1	11/3/2020 12:33:30 PM
Surr: 1-Bromo-4-fluorobenzene	97.1	88.6 - 109	%Rec	1	11/3/2020 12:33:30 PM
Sample Moisture (Percent Moist	ure)		Batch	ID:	R63094 Analyst: RL
Percent Moisture	9.69	0.500	wt%	1	11/3/2020 2:01:34 PM

Original



Work Order: **2010457**Date Reported: **11/4/2020**

Client: Fulcrum Environmental Collection Date: 10/27/2020 9:45:00 AM

Project: Ranch 19 East

Lab ID: 2010457-002 **Matrix:** Soil

Client Sample ID: R19E-102720-02.5.5

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
Diesel and Heavy Oil by NWTPH	-Dx/Dx Ext.			Batch	ı ID:	30217 Analyst: DW
Diesel (Fuel Oil)	ND	17.2		mg/Kg-dry	1	10/31/2020 5:25:37 AM
Heavy Oil	ND	43.0		mg/Kg-dry	1	10/31/2020 5:25:37 AM
Surr: 2-Fluorobiphenyl	59.3	50 - 150		%Rec	1	10/31/2020 5:25:37 AM
Surr: o-Terphenyl	76.6	50 - 150		%Rec	1	10/31/2020 5:25:37 AM
Volatile Organic Compounds by	EPA Method	8260D		Batch	ı ID:	30262 Analyst: KT
Benzene	ND	0.0238		mg/Kg-dry	1	11/3/2020 1:34:26 PM
Toluene	ND	0.0238		mg/Kg-dry	1	11/3/2020 1:34:26 PM
Ethylbenzene	ND	0.0297		mg/Kg-dry	1	11/3/2020 1:34:26 PM
m,p-Xylene	ND	0.0594		mg/Kg-dry	1	11/3/2020 1:34:26 PM
o-Xylene	ND	0.0297		mg/Kg-dry	1	11/3/2020 1:34:26 PM
Surr: Dibromofluoromethane	95.2	85.2 - 113		%Rec	1	11/3/2020 1:34:26 PM
Surr: Toluene-d8	99.7	88.5 - 110		%Rec	1	11/3/2020 1:34:26 PM
Surr: 1-Bromo-4-fluorobenzene	92.1	88.6 - 109		%Rec	1	11/3/2020 1:34:26 PM
Sample Moisture (Percent Moist	ure)			Batch	ı ID:	R63094 Analyst: RL
Percent Moisture	3.03	0.500		wt%	1	11/3/2020 2:01:34 PM

Original



Work Order: **2010457**Date Reported: **11/4/2020**

Client: Fulcrum Environmental Collection Date: 10/27/2020 9:55:00 AM

Project: Ranch 19 East

Lab ID: 2010457-003 **Matrix:** Soil

Client Sample ID: R19E-102720-03.3

Analyses	Result	RL	Qual	Units	DF	Date Analyzed	
Diesel and Heavy Oil by NWTPH-	Dx/Dx Ext.			Batch	ı ID:	30217 Analyst: DW	
Diesel (Fuel Oil)	ND	20.7		mg/Kg-dry	1	10/31/2020 5:55:15 AM	
Heavy Oil	ND	51.8		mg/Kg-dry	1	10/31/2020 5:55:15 AM	
Surr: 2-Fluorobiphenyl	53.4	50 - 150		%Rec	1	10/31/2020 5:55:15 AM	
Surr: o-Terphenyl	72.4	50 - 150		%Rec	1	10/31/2020 5:55:15 AM	
Volatile Organic Compounds by	EPA Method	8260D		Batch	ı ID:	30262 Analyst: KT	
Benzene	ND	0.0238		mg/Kg-dry	1	11/3/2020 2:04:51 PM	
Toluene	ND	0.0238		mg/Kg-dry	1	11/3/2020 2:04:51 PM	
Ethylbenzene	ND	0.0297		mg/Kg-dry	1	11/3/2020 2:04:51 PM	
m,p-Xylene	ND	0.0595		mg/Kg-dry	1	11/3/2020 2:04:51 PM	
o-Xylene	ND	0.0297		mg/Kg-dry	1	11/3/2020 2:04:51 PM	
Surr: Dibromofluoromethane	95.4	85.2 - 113		%Rec	1	11/3/2020 2:04:51 PM	
Surr: Toluene-d8	99.4	88.5 - 110		%Rec	1	11/3/2020 2:04:51 PM	
Surr: 1-Bromo-4-fluorobenzene	94.4	88.6 - 109		%Rec	1	11/3/2020 2:04:51 PM	
Sample Moisture (Percent Moistu	<u>ure)</u>			Batch	ID:	R63094 Analyst: RL	
Percent Moisture	12.2	0.500		wt%	1	11/3/2020 2:01:34 PM	



Work Order: **2010457**Date Reported: **11/4/2020**

Client: Fulcrum Environmental Collection Date: 10/27/2020 10:30:00 AM

Project: Ranch 19 East

Lab ID: 2010457-004 **Matrix:** Soil

Client Sample ID: R19E-102720-04.2.5

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
Diesel and Heavy Oil by NWTPH	-Dx/Dx Ext.			Batch	ı ID:	30217 Analyst: DW
Diesel (Fuel Oil)	ND	20.0		mg/Kg-dry	1	10/31/2020 6:25:00 AM
Heavy Oil	ND	49.9		mg/Kg-dry	1	10/31/2020 6:25:00 AM
Surr: 2-Fluorobiphenyl	50.7	50 - 150		%Rec	1	10/31/2020 6:25:00 AM
Surr: o-Terphenyl	72.4	50 - 150		%Rec	1	10/31/2020 6:25:00 AM
Volatile Organic Compounds by	EPA Method	8260D		Batch	ı ID:	30262 Analyst: KT
Benzene	ND	0.0224		mg/Kg-dry	1	11/3/2020 2:35:17 PM
Toluene	ND	0.0224		mg/Kg-dry	1	11/3/2020 2:35:17 PM
Ethylbenzene	ND	0.0280		mg/Kg-dry	1	11/3/2020 2:35:17 PM
m,p-Xylene	ND	0.0560		mg/Kg-dry	1	11/3/2020 2:35:17 PM
o-Xylene	ND	0.0280		mg/Kg-dry	1	11/3/2020 2:35:17 PM
Surr: Dibromofluoromethane	95.3	85.2 - 113		%Rec	1	11/3/2020 2:35:17 PM
Surr: Toluene-d8	100	88.5 - 110		%Rec	1	11/3/2020 2:35:17 PM
Surr: 1-Bromo-4-fluorobenzene	94.8	88.6 - 109		%Rec	1	11/3/2020 2:35:17 PM
Sample Moisture (Percent Moist	ure)			Batch	ID:	R63094 Analyst: RL
Percent Moisture	11.0	0.500		wt%	1	11/3/2020 2:01:34 PM

Original



Work Order: **2010457**Date Reported: **11/4/2020**

Client: Fulcrum Environmental Collection Date: 10/27/2020 10:15:00 AM

Project: Ranch 19 East

Lab ID: 2010457-005 **Matrix:** Soil

Client Sample ID: R19E-102720-05.2

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
Diesel and Heavy Oil by NWTPH	-Dx/Dx Ext.			Batch	ı ID:	30217 Analyst: DW
Diesel (Fuel Oil)	ND	20.1		mg/Kg-dry	1	10/31/2020 7:24:11 AM
Heavy Oil	ND	50.4		mg/Kg-dry	1	10/31/2020 7:24:11 AM
Surr: 2-Fluorobiphenyl	55.3	50 - 150		%Rec	1	10/31/2020 7:24:11 AM
Surr: o-Terphenyl	84.3	50 - 150		%Rec	1	10/31/2020 7:24:11 AM
Volatile Organic Compounds by	EPA Method	8260D		Batch	ı ID:	30262 Analyst: KT
Benzene	ND	0.0243		mg/Kg-dry	1	11/3/2020 3:05:44 PM
Toluene	ND	0.0243		mg/Kg-dry	1	11/3/2020 3:05:44 PM
Ethylbenzene	ND	0.0304		mg/Kg-dry	1	11/3/2020 3:05:44 PM
m,p-Xylene	ND	0.0608		mg/Kg-dry	1	11/3/2020 3:05:44 PM
o-Xylene	ND	0.0304		mg/Kg-dry	1	11/3/2020 3:05:44 PM
Surr: Dibromofluoromethane	94.7	85.2 - 113		%Rec	1	11/3/2020 3:05:44 PM
Surr: Toluene-d8	99.6	88.5 - 110		%Rec	1	11/3/2020 3:05:44 PM
Surr: 1-Bromo-4-fluorobenzene	91.8	88.6 - 109		%Rec	1	11/3/2020 3:05:44 PM
Sample Moisture (Percent Moist	ure)			Batch	ID:	R63094 Analyst: RL
Percent Moisture	9.32	0.500		wt%	1	11/3/2020 2:01:34 PM



Work Order: **2010457**Date Reported: **11/4/2020**

Client: Fulcrum Environmental Collection Date: 10/27/2020 10:20:00 AM

Project: Ranch 19 East

Lab ID: 2010457-006 **Matrix:** Soil

Client Sample ID: R19E-102720-06.2

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
Diesel and Heavy Oil by NWTPH	-Dx/Dx Ext.			Batch	ı ID:	30217 Analyst: DW
Diesel (Fuel Oil)	ND	20.7		mg/Kg-dry	1	10/31/2020 7:53:49 AM
Heavy Oil	ND	51.7		mg/Kg-dry	1	10/31/2020 7:53:49 AM
Surr: 2-Fluorobiphenyl	62.0	50 - 150		%Rec	1	10/31/2020 7:53:49 AM
Surr: o-Terphenyl	73.0	50 - 150		%Rec	1	10/31/2020 7:53:49 AM
Volatile Organic Compounds by	EPA Method	<u>8260D</u>		Batch	ı ID:	30262 Analyst: KT
Benzene	ND	0.0237		mg/Kg-dry	1	11/3/2020 3:36:15 PM
Toluene	ND	0.0237		mg/Kg-dry	1	11/3/2020 3:36:15 PM
Ethylbenzene	ND	0.0296		mg/Kg-dry	1	11/3/2020 3:36:15 PM
m,p-Xylene	ND	0.0593		mg/Kg-dry	1	11/3/2020 3:36:15 PM
o-Xylene	ND	0.0296		mg/Kg-dry	1	11/3/2020 3:36:15 PM
Surr: Dibromofluoromethane	95.1	85.2 - 113		%Rec	1	11/3/2020 3:36:15 PM
Surr: Toluene-d8	99.7	88.5 - 110		%Rec	1	11/3/2020 3:36:15 PM
Surr: 1-Bromo-4-fluorobenzene	93.5	88.6 - 109		%Rec	1	11/3/2020 3:36:15 PM
Sample Moisture (Percent Moist	<u>ure)</u>			Batch	ı ID:	R63094 Analyst: RL
Percent Moisture	8.14	0.500		wt%	1	11/3/2020 2:01:34 PM



Work Order: **2010457**Date Reported: **11/4/2020**

Client: Fulcrum Environmental Collection Date: 10/27/2020 10:23:00 AM

Project: Ranch 19 East

Lab ID: 2010457-007 **Matrix:** Soil

Client Sample ID: R19E-102720-07.2

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
Diesel and Heavy Oil by NWTPH	-Dx/Dx Ext.			Batch	ı ID:	30217 Analyst: DW
Diesel (Fuel Oil)	ND	19.6		mg/Kg-dry	1	10/31/2020 8:23:27 AM
Heavy Oil	ND	49.0		mg/Kg-dry	1	10/31/2020 8:23:27 AM
Surr: 2-Fluorobiphenyl	69.8	50 - 150		%Rec	1	10/31/2020 8:23:27 AM
Surr: o-Terphenyl	80.4	50 - 150		%Rec	1	10/31/2020 8:23:27 AM
Volatile Organic Compounds by	EPA Method	8260D		Batch	ID:	30262 Analyst: KT
Benzene	ND	0.0265		mg/Kg-dry	1	11/3/2020 4:06:46 PM
Toluene	ND	0.0265		mg/Kg-dry	1	11/3/2020 4:06:46 PM
Ethylbenzene	ND	0.0331		mg/Kg-dry	1	11/3/2020 4:06:46 PM
m,p-Xylene	ND	0.0662		mg/Kg-dry	1	11/3/2020 4:06:46 PM
o-Xylene	ND	0.0331		mg/Kg-dry	1	11/3/2020 4:06:46 PM
Surr: Dibromofluoromethane	94.7	85.2 - 113		%Rec	1	11/3/2020 4:06:46 PM
Surr: Toluene-d8	99.1	88.5 - 110		%Rec	1	11/3/2020 4:06:46 PM
Surr: 1-Bromo-4-fluorobenzene	95.5	88.6 - 109		%Rec	1	11/3/2020 4:06:46 PM
Sample Moisture (Percent Moist	ure)			Batch	ID:	R63094 Analyst: RL
Percent Moisture	8.33	0.500		wt%	1	11/3/2020 2:01:34 PM



Work Order: **2010457**Date Reported: **11/4/2020**

Client: Fulcrum Environmental Collection Date: 10/27/2020 10:53:00 AM

Project: Ranch 19 East

Lab ID: 2010457-008 **Matrix:** Soil

Client Sample ID: R19E-102720-08.3

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
Diesel and Heavy Oil by NWTPH-	Dx/Dx Ext.			Batch	ID:	30217 Analyst: DW
Diesel (Fuel Oil)	ND	19.6		mg/Kg-dry	1	10/31/2020 8:53:10 AM
Heavy Oil	ND	49.1		mg/Kg-dry	1	10/31/2020 8:53:10 AM
Surr: 2-Fluorobiphenyl	72.0	50 - 150		%Rec	1	10/31/2020 8:53:10 AM
Surr: o-Terphenyl	82.3	50 - 150		%Rec	1	10/31/2020 8:53:10 AM
Volatile Organic Compounds by	EPA Method	8260D		Batch	ID:	30262 Analyst: KT
Benzene	ND	0.0244		mg/Kg-dry	1	11/3/2020 4:37:10 PM
Toluene	ND	0.0244		mg/Kg-dry	1	11/3/2020 4:37:10 PM
Ethylbenzene	ND	0.0305		mg/Kg-dry	1	11/3/2020 4:37:10 PM
m,p-Xylene	ND	0.0610		mg/Kg-dry	1	11/3/2020 4:37:10 PM
o-Xylene	ND	0.0305		mg/Kg-dry	1	11/3/2020 4:37:10 PM
Surr: Dibromofluoromethane	95.1	85.2 - 113		%Rec	1	11/3/2020 4:37:10 PM
Surr: Toluene-d8	99.2	88.5 - 110		%Rec	1	11/3/2020 4:37:10 PM
Surr: 1-Bromo-4-fluorobenzene	90.8	88.6 - 109		%Rec	1	11/3/2020 4:37:10 PM
Sample Moisture (Percent Moistu	ure)			Batch	ID:	R63094 Analyst: RL
Percent Moisture	10.8	0.500		wt%	1	11/3/2020 2:01:34 PM



Work Order: **2010457**Date Reported: **11/4/2020**


Client: Fulcrum Environmental Collection Date: 10/27/2020 11:00:00 AM

Project: Ranch 19 East

Lab ID: 2010457-009 **Matrix:** Soil

Client Sample ID: R19E-102720-09.3

Analyses	Result	Result RL		Units	DF	Date Analyzed
Diesel and Heavy Oil by NWTPH	-Dx/Dx Ext.			Batch	ID:	30217 Analyst: DW
Diesel (Fuel Oil)	ND	19.7		mg/Kg-dry	1	10/31/2020 9:22:47 AM
Heavy Oil	ND	49.2		mg/Kg-dry	1	10/31/2020 9:22:47 AM
Surr: 2-Fluorobiphenyl	58.8	50 - 150		%Rec	1	10/31/2020 9:22:47 AM
Surr: o-Terphenyl	72.7	50 - 150		%Rec	1	10/31/2020 9:22:47 AM
Volatile Organic Compounds by	EPA Method	8260D		Batch	ID:	30262 Analyst: KT
Benzene	ND	0.0239		mg/Kg-dry	1	11/3/2020 5:07:41 PM
Toluene	ND	0.0239		mg/Kg-dry	1	11/3/2020 5:07:41 PM
Ethylbenzene	ND	0.0299		mg/Kg-dry	1	11/3/2020 5:07:41 PM
m,p-Xylene	ND	0.0598		mg/Kg-dry	1	11/3/2020 5:07:41 PM
o-Xylene	ND	0.0299		mg/Kg-dry	1	11/3/2020 5:07:41 PM
Surr: Dibromofluoromethane	94.6	85.2 - 113		%Rec	1	11/3/2020 5:07:41 PM
Surr: Toluene-d8	99.4	88.5 - 110		%Rec	1	11/3/2020 5:07:41 PM
Surr: 1-Bromo-4-fluorobenzene	93.4	88.6 - 109		%Rec	1	11/3/2020 5:07:41 PM
Sample Moisture (Percent Moist	ure)			Batch	ID:	R63094 Analyst: RL
Percent Moisture	8.27	0.500		wt%	1	11/3/2020 2:01:34 PM





QC SUMMARY REPORT

CLIENT: Fulcrum Environmental

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Sample ID: MB-30217	SampType: MBLK			Units: mg/Kg		Prep Date	e: 10/29/2	020	RunNo: 630	36	
Client ID: MBLKS	Batch ID: 30217					Analysis Date	e: 10/30/2	020	SeqNo: 126	55240	
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qua
Diesel (Fuel Oil)	ND	20.0									
Heavy Oil	ND	50.0									
Surr: 2-Fluorobiphenyl	12.4		20.00		62.3	50	150				
Surr: o-Terphenyl	14.6		20.00		73.0	50	150				
Sample ID: LCS-30217	SampType: LCS			Units: mg/Kg		Prep Date	e: 10/29/2	020	RunNo: 630)36	
Client ID: LCSS	Batch ID: 30217					Analysis Date	e: 10/30/2	020	SeqNo: 126	55241	
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qua
Diesel (Fuel Oil)	481	20.0	500.0	0	96.2	65	135				
Surr: 2-Fluorobiphenyl	16.5		20.00		82.5	50	150				
Surr: o-Terphenyl	17.6		20.00		88.0	50	150				
Sample ID: 2010457-004ADUP	SampType: DUP			Units: mg/Kg	-dry	Prep Date	e: 10/29/2	020	RunNo: 630)36	
Client ID: R19E-102720-04.2.5	Batch ID: 30217					Analysis Date	e: 10/31/2	020	SeqNo: 126	55255	
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qua
Diesel (Fuel Oil)	ND	21.3						0		30	
Heavy Oil	ND	53.2						0		30	
Surr: 2-Fluorobiphenyl	15.3		21.27		72.0	50	150		0		
Surr: o-Terphenyl	17.8		21.27		83.6	50	150		0		
Sample ID: 2010441-003AMS	SampType: MS			Units: mg/Kg	-dry	Prep Date	e: 10/29/2	020	RunNo: 630)52	
Client ID: BATCH	Batch ID: 30217					Analysis Date	e: 11/2/20	20	SeqNo: 126	55528	
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qua
Diesel (Fuel Oil)	514	18.1	452.1	0	114	65	135				
Surr: 2-Fluorobiphenyl	20.2		18.08		111	50	150				

Original Page 14 of 19

Date: 11/4/2020



Work Order: 2010457

Project:

QC SUMMARY REPORT

CLIENT: Fulcrum Environmental

Ranch 19 East

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.


Sample ID: 2010441-003AMS SampType: MS Units: mg/Kg-dry Prep Date: 10/29/2020 RunNo: 63052

Client ID: **BATCH** Batch ID: **30217** Analysis Date: **11/2/2020** SeqNo: **1265528**

Analyte Result RL SPK value SPK Ref Val %REC LowLimit HighLimit RPD Ref Val %RPD RPDLimit Qual

Sample ID: 2010441-003AMSD	SampType: MSD			Units: mg/K	g-dry	Prep Da	te: 10/29/2	2020	RunNo: 630)52	
Client ID: BATCH	Batch ID: 30217					Analysis Da	te: 11/2/20	20	SeqNo: 126	55529	
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	531	18.1	451.3	0	118	65	135	514.1	3.17	30	
Surr: 2-Fluorobiphenyl	20.0		18.05		111	50	150		0		
Surr: o-Terphenyl	20.1		18.05		112	50	150		0		

Original Page 15 of 19





QC SUMMARY REPORT

CLIENT: Fulcrum Environmental

Volatile Organic Compounds by EPA Method 8260D

Sample ID: LCS-30262	SampType: LCS			Units: mg/Kg		Prep Dat	te: 11/3/20	20	RunNo: 631	18	
Client ID: LCSS	Batch ID: 30262					Analysis Dat	te: 11/3/20	20	SeqNo: 126	6808	
Analyte	Result	RL	SPK value	SPK Ref Val	%REC			RPD Ref Val	%RPD	RPDLimit	Qua
Benzene	0.996	0.0200	1.000	0	99.6	79.4	116				
Toluene	1.04	0.0200	1.000	0	104	80.5	115				
Ethylbenzene	1.05	0.0250	1.000	0	105	81.6	116				
m,p-Xylene	2.10	0.0500	2.000	0	105	83.2	115				
o-Xylene	1.03	0.0250	1.000	0	103	82.5	114				
Surr: Dibromofluoromethane	1.26		1.250		101	85.2	113				
Surr: Toluene-d8	1.27		1.250		102	88.5	110				
Surr: 1-Bromo-4-fluorobenzene	1.26		1.250		101	88.6	109				
Sample ID: MB-30262	SampType: MBLK			Units: mg/Kg		Prep Dat	te: 11/3/20	20	RunNo: 631	18	
Client ID: MBLKS	Batch ID: 30262					Analysis Dat	te: 11/3/20	20	SeqNo: 126	6807	
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qua
Benzene	ND	0.0200									
Toluene	ND	0.0200									
Ethylbenzene	ND	0.0250									
m,p-Xylene	ND	0.0500									
o-Xylene	ND	0.0250									
Surr: Dibromofluoromethane	1.20		1.250		95.8	85.2	113				
Surr: Toluene-d8	1.23		1.250		98.4	88.5	110				
Surr: 1-Bromo-4-fluorobenzene	1.18		1.250		94.0	88.6	109				
Sample ID: 2010457-001BDUP	SampType: DUP			Units: mg/Kg-	dry	Prep Dat	te: 11/3/20	20	RunNo: 631	18	
Client ID: R19E-102720-01.2	Batch ID: 30262					Analysis Dat	te: 11/3/2 0	20	SeqNo: 126	6793	
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qua
Benzene	ND	0.0247						0		30	
Toluene	ND	0.0247						0		30	
Ethylbenzene	ND	0.0309						0		30	

Original Page 16 of 19

Date: 11/4/2020



Work Order: 2010457

Project:

QC SUMMARY REPORT

CLIENT: Fulcrum Environmental

Ranch 19 East

Volatile Organic Compounds by EPA Method 8260D

Sample ID: 2010457-001BDUP	2: 2010457-001BDUP SampType: DUP Units: mg/Kg-dry				Prep Da	te: 11/3/20	20	RunNo: 63 1	118		
Client ID: R19E-102720-01.2	Batch ID: 30262					Analysis Da	te: 11/3/20	20	SeqNo: 126	66793	
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
m,p-Xylene	ND	0.0617						0		30	
o-Xylene	ND	0.0309						0		30	
Surr: Dibromofluoromethane	1.49		1.543		96.6	85.2	113		0		
Surr: Toluene-d8	1.54		1.543		99.9	88.5	110		0		
Surr: 1-Bromo-4-fluorobenzene	1.47		1.543		95.5	88.6	109		0		

Sample ID: 2010457-002BMS	SampType: MS			Units: mg/	Kg-dry	Prep Da	te: 11/3/20	20	RunNo: 631	118	
Client ID: R19E-102720-02.5.5	Batch ID: 30262					Analysis Da	te: 11/4/20	20	SeqNo: 126	66795	
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	1.23	0.0238	1.189	0	103	74.6	126				
Toluene	1.25	0.0238	1.189	0	105	72.6	127				
Ethylbenzene	1.29	0.0297	1.189	0	109	77.3	126				
m,p-Xylene	2.58	0.0594	2.378	0	109	78.5	126				
o-Xylene	1.27	0.0297	1.189	0	107	79.4	123				
Surr: Dibromofluoromethane	1.52		1.486		102	85.2	113				
Surr: Toluene-d8	1.50		1.486		101	88.5	110				
Surr: 1-Bromo-4-fluorobenzene	1.55		1.486		104	88.6	109				

Original Page 17 of 19



Sample Log-In Check List

С	lient Name:	FE	Work Order Numb	ber: 2010457	
Lo	ogged by:	Clare Griggs	Date Received:	10/28/2020	9:28:00 AM
Cha	in of Custo	ody			
		ustody complete?	Yes 🗸	No 🗌	Not Present
2.	How was the	sample delivered?	<u>UPS</u>		
Log	ı İn				
_		procent?	Yes 🗸	No 🗆	na 🗆
3.	Coolers are p	nesent:	res 💌	NO 🗀	NA L
4.	Shipping cont	tainer/cooler in good condition?	Yes 🗸	No \square	
5.		s present on shipping container/cooler? nments for Custody Seals not intact)	Yes	No 🗆	Not Present 🗹
6.	Was an atten	npt made to cool the samples?	Yes 🗸	No 🗌	NA 🗆
7.	Were all item	s received at a temperature of >2°C to 6°C *	Yes 🗸	No 🗆	NA 🗆
8.	Sample(s) in	proper container(s)?	Yes 🗸	No 🗆	
9.	Sufficient san	nple volume for indicated test(s)?	Yes 🗸	No \square	
10.	Are samples	properly preserved?	Yes 🗸	No \square	
11.	Was preserva	ative added to bottles?	Yes	No 🗸	NA 🗆
12.	Is there head	space in the VOA vials?	Yes	No 🗌	NA 🗹
		es containers arrive in good condition(unbroken)?	Yes 🗸	No \square	
14.	Does paperw	ork match bottle labels?	Yes 🗸	No 🗌	
15.	Are matrices	correctly identified on Chain of Custody?	Yes 🗸	No \square	
16.	Is it clear wha	at analyses were requested?	Yes 🗹	No 🗌	
17.	Were all hold	ing times able to be met?	Yes 🗸	No 🗌	
Spe	cial Handli	ing (if applicable)			
_		otified of all discrepancies with this order?	Yes	No 🗌	NA 🗹
	Person	Notified: Date			
	By Who		,	one Fax	In Person
	Regardi	-		Tax [1111 013011
		nstructions:			
19	Additional rer	,			
_	<u>Information</u>				
ICIII	oimation	Item # Temp °C			

Sample

^{*} Note: DoD/ELAP and TNI require items to be received at 4°C +/- 2°C

Date: 10/27/20 Project Name: RANCH 19 595 F Project No: 10/29 02.15 Collected by: NM Location: Report To (PM): JEREMY LYNN PM Email: PM Email: Self-Ball Ball Ball Ball Ball Ball Ball Ball	3600 Fremont Ave N.	Chain of Custody Record & Labo	Laboratory Services Agreement
Colored North 2nd Street Sample S	7	Page: of:	Laboratory Project No (Internal): 37 17457
Illerum Environmental		RANCH 19 EAST	
Collected by: North 2nd Street		192902.15	
SO9.574.0839 PAN Email: Continue Christie Chris	Address: 406 North 2nd Street		
Sumple Sample S		Location:	
PM Email: PM E	Telephone: 509.574.0839	JEREMY (Sample Disposal: Return to client Disposal by lab (after 30 da
Sample S	Fax:		
Sample S			
102720 - 01.2 10/21/26 0.35 3	Sample Sample		
-102720 - 03.5.5	52720-01,2 110/c7/20 9:35	×	
-102720 - 03. 5.	02.5.5		
Color Nitrate Nitrat	-102720-03.3		7
**TID27120-05, 2	-102720 - 04.2.5		> PAHS
10:2720-00; 2 10:23 10:55 10	102726-05, 2		
COLOR MANAGEMENT. 10:73 10:753 10:5	2		
Cold Mark Date/Time Da	2		
Air, AQ = Aqueous, B = Bulk, O = Other, P = Product, S = Soil, SD = Sediment, SL = Soild, W = Water, DW = Drinking Water, GW = Ground Water, SW = Storm Water, WW = Waste Water iricle): Mitrate Nitrite Chloride Sulfate Bromide O-Phosphate Fluoride Nitrate+Nitrite by Christ I am authorized to enter into this Agreement with Fremont Analytical on behalf of the Client named above and that I have verified Client's agreement to be terms on the from and backside of this Agreement. Cold Machine Date/Time Date/Time Date/Time Date/Time Date/Time	ဟ		
Air, AQ = Aqueous, B = Bulk, O = Other, P = Product, S = Soil, SD = Sediment, SL = Soild, W = Water, DW = Drinking Water, GW = Ground Water, SW = Storm Water, WW = Waste Water ricle): MITCA-5 RCRA-8 Priority Pollutants TAL Individual: Ag Al As B Ba Be Ca Cd Co Cr Cu Fe Hg K Mg Mn Mo Na Ni Pb Sb Se Sr Sn Ti Ti U v Zn Circle): Nitrate Nitrite Chloride Sulfate Bromide O-Phosphate Fluoride Nitrate+Nitrite Put that I am authorized to enter into this Agreement with Fremont Analytical on behalf of the Client named above and that I have verified Client's agreement to the terms on they front and backside of this Agreement. Date/Time Date/Time Date/Time Date/Time Date/Time Date/Time Date/Time	<i>(</i> 2)	(
Air, AQ = Aqueous, B = Bulk, O = Other, P = Product, S = Soil, SD = Sediment, SL = Soild, W = Water, DW = Drinking Water, GW = Ground Water, SW = Storm Water, WW = Water with French to be terms on the front and backside of this Agreement. Agreement Agrae	10		
Circle): Nitrate Nitrite Chloride Sulfate Bromide O-Phosphate Fluoride Nitrate+Nitrite but that I am authorized to enter into this Agreement with Fremont Analytical on behalf of the Client named above and that I have verified Client's agreement to be terms on the front and backside of this Agreement. Color Management With Fremont Analytical on behalf of the Client named above and that I have verified Client's agreement to be terms on the front and backside of this Agreement. Date/Time Date/Time Date/Time Date/Time	AQ = Aqueous, B = Bulk, O = Other, P = Product, S = Soil MTCA-5 RCRA-8 Priority Pollutants TAL	St = Solid, W = Water, DW = Drinking Water, GW = Ground Water, As B Ba Be Ca Cd Co Cr Cu Fe Hg K Mg Mn Mo Na Ni	Water, WW = Waste Water Sr Sn Ti Ti U V Zn
bent that I am authorized to enter into this Agreement with Fremont Analytical on behalf of the Client named above and that I have verified Client's agreement to the terms on the front and backside of this Agreement. Column	Nitrate Nitrite Chloride Sulfate	O-Phosphate Fluoride	X 300,000
cole Mill Date/Time Received Date/Time Date/Time Date/Time Date/Time Date/Time Cole Cole Date/Time Date/Time Cole Cole Date/Time Cole	I represent that I am authorized to enter into this Agreement with cach of the terms on the front and backside of this Agreement.	Fremont Analytical on behalf of the Client named above and that I h	7
Date/Time Received Date/Time	Refinquished MCMM Date/Time 10/27/20	ecelupad	
L D I GOING VOY		A SCAR SCAR SCAR	S



3600 Fremont Ave. N.
Seattle, WA 98103
T: (206) 352-3790
F: (206) 352-7178
info@fremontanalytical.com

Fulcrum Environmental Jeremy Lynn 406 N. 2nd Street Yakima, WA 98901

RE: WA Land MGMT Ranch 19 Work Order Number: 2010479

November 11, 2020

Attention Jeremy Lynn:

Fremont Analytical, Inc. received 10 sample(s) on 10/29/2020 for the analyses presented in the following report.

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Sample Moisture (Percent Moisture)

Volatile Organic Compounds by EPA Method 8260D

This report consists of the following:

- Case Narrative
- Analytical Results
- Applicable Quality Control Summary Reports
- Chain of Custody

All analyses were performed consistent with the Quality Assurance program of Fremont Analytical, Inc. Please contact the laboratory if you should have any questions about the results.

Thank you for using Fremont Analytical.

Sincerely,

Brianna Barnes Project Manager

DoD-ELAP Accreditation #79636 by PJLA, ISO/IEC 17025:2017 and QSM 5.3 for Environmental Testing ORELAP Certification: WA 100009 (NELAP Recognized) for Environmental Testing Washington State Department of Ecology Accredited for Environmental Testing, Lab ID C910

Date: 11/11/2020



CLIENT: Fulcrum Environmental Work Order Sample Summary

Project: WA Land MGMT Ranch 19

Work Order: 2010479

Lab Sample ID	Client Sample ID	Date/Time Collected	Date/Time Received
2010479-001	R19E-102820-10.1	10/28/2020 10:05 AM	10/29/2020 9:34 AM
2010479-002	R19E-102820-11.2	10/28/2020 10:15 AM	10/29/2020 9:34 AM
2010479-003	R19E-102820-12.8	10/28/2020 10:18 AM	10/29/2020 9:34 AM
2010479-004	R19E-102820-13.1	10/28/2020 10:20 AM	10/29/2020 9:34 AM
2010479-005	R19E-102820-14.1	10/28/2020 10:40 AM	10/29/2020 9:34 AM
2010479-006	R19E-102820-15.1	10/28/2020 10:40 AM	10/29/2020 9:34 AM
2010479-007	R19E-102820-16.1	10/28/2020 1:00 PM	10/29/2020 9:34 AM
2010479-008	R19E-102820-17.6	10/28/2020 10:25 AM	10/29/2020 9:34 AM
2010479-009	R19E-102820-18.6	10/28/2020 10:28 AM	10/29/2020 9:34 AM
2010479-010	R19E-102820-19.6	10/28/2020 10:30 AM	10/29/2020 9:34 AM

Note: If no "Time Collected" is supplied, a default of 12:00AM is assigned



Case Narrative

WO#: **2010479**Date: **11/11/2020**

CLIENT: Fulcrum Environmental
Project: WA Land MGMT Ranch 19

I. SAMPLE RECEIPT:

Samples receipt information is recorded on the attached Sample Receipt Checklist.

II. GENERAL REPORTING COMMENTS:

Results are reported on a wet weight basis unless dry-weight correction is denoted in the units field on the analytical report ("mg/kg-dry" or "ug/kg-dry").

Matrix Spike (MS) and MS Duplicate (MSD) samples are tested from an analytical batch of "like" matrix to check for possible matrix effect. The MS and MSD will provide site specific matrix data only for those samples which are spiked by the laboratory. The sample chosen for spike purposes may or may not have been a sample submitted in this sample delivery group. The validity of the analytical procedures for which data is reported in this analytical report is determined by the Laboratory Control Sample (LCS) and the Method Blank (MB). The LCS and the MB are processed with the samples and the MS/MSD to ensure method criteria are achieved throughout the entire analytical process.

III. ANALYSES AND EXCEPTIONS:

Exceptions associated with this report will be footnoted in the analytical results page(s) or the quality control summary page(s) and/or noted below.

Revision 1 includes analysis requested by client.



Qualifiers & Acronyms

WO#: **201047**9

Date Reported: 11/11/2020

Qualifiers:

- * Flagged value is not within established control limits
- B Analyte detected in the associated Method Blank
- D Dilution was required
- E Value above quantitation range
- H Holding times for preparation or analysis exceeded
- I Analyte with an internal standard that does not meet established acceptance criteria
- J Analyte detected below Reporting Limit
- N Tentatively Identified Compound (TIC)
- Q Analyte with an initial or continuing calibration that does not meet established acceptance criteria (<20%RSD, <20% Drift or minimum RRF)
- S Spike recovery outside accepted recovery limits
- ND Not detected at the Reporting Limit
- R High relative percent difference observed

Acronyms:

%Rec - Percent Recovery

CCB - Continued Calibration Blank

CCV - Continued Calibration Verification

DF - Dilution Factor

DUP - Sample Duplicate

HEM - Hexane Extractable Material

ICV - Initial Calibration Verification

LCS/LCSD - Laboratory Control Sample / Laboratory Control Sample Duplicate

MB or MBLANK - Method Blank

MDL - Method Detection Limit

MS/MSD - Matrix Spike / Matrix Spike Duplicate

PDS - Post Digestion Spike

Ref Val - Reference Value

REP - Sample Replicate

RL - Reporting Limit

RPD - Relative Percent Difference

SD - Serial Dilution

SGT - Silica Gel Treatment

SPK - Spike

Surr - Surrogate



Work Order: **2010479**Date Reported: **11/11/2020**

Client: Fulcrum Environmental Collection Date: 10/28/2020 10:05:00 AM

Project: WA Land MGMT Ranch 19

Lab ID: 2010479-001 **Matrix:** Soil

Client Sample ID: R19E-102820-10.1

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
Diesel and Heavy Oil by NWTPH	-Dx/Dx Ext.			Batch	ı ID:	30227 Analyst: DW
Diesel (Fuel Oil)	ND	18.6		mg/Kg-dry	1	10/31/2020 3:56:35 AM
Heavy Oil	ND	46.5		mg/Kg-dry	1	10/31/2020 3:56:35 AM
Surr: 2-Fluorobiphenyl	102	50 - 150		%Rec	1	10/31/2020 3:56:35 AM
Surr: o-Terphenyl	85.1	50 - 150		%Rec	1	10/31/2020 3:56:35 AM
Volatile Organic Compounds by	EPA Method	<u>8260D</u>		Batch	ı ID:	30262 Analyst: KT
Benzene	ND	0.0452		mg/Kg-dry	1	11/4/2020 10:02:02 AM
Toluene	ND	0.0452		mg/Kg-dry	1	11/4/2020 10:02:02 AM
Ethylbenzene	ND	0.0565		mg/Kg-dry	1	11/4/2020 10:02:02 AM
m,p-Xylene	ND	0.113		mg/Kg-dry	1	11/4/2020 10:02:02 AM
o-Xylene	ND	0.0565		mg/Kg-dry	1	11/4/2020 10:02:02 AM
Surr: Dibromofluoromethane	97.3	85.2 - 113		%Rec	1	11/4/2020 10:02:02 AM
Surr: Toluene-d8	100	88.5 - 110		%Rec	1	11/4/2020 10:02:02 AM
Surr: 1-Bromo-4-fluorobenzene	93.2	88.6 - 109		%Rec	1	11/4/2020 10:02:02 AM
Sample Moisture (Percent Moist	ure)			Batch	ID:	R63112 Analyst: CJ
Percent Moisture	7.70	0.500		wt%	1	11/4/2020 8:11:58 AM



Work Order: **2010479**Date Reported: **11/11/2020**

Client: Fulcrum Environmental Collection Date: 10/28/2020 10:15:00 AM

Project: WA Land MGMT Ranch 19

Lab ID: 2010479-002 **Matrix:** Soil

Client Sample ID: R19E-102820-11.2

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
Diesel and Heavy Oil by NWTPH	-Dx/Dx Ext.			Batch	ı ID:	30227 Analyst: DW
Diesel (Fuel Oil)	ND	20.1		mg/Kg-dry	1	10/31/2020 4:26:15 AM
Heavy Oil	ND	50.2		mg/Kg-dry	1	10/31/2020 4:26:15 AM
Surr: 2-Fluorobiphenyl	106	50 - 150		%Rec	1	10/31/2020 4:26:15 AM
Surr: o-Terphenyl	90.0	50 - 150		%Rec	1	10/31/2020 4:26:15 AM
Volatile Organic Compounds by	EPA Method	<u>8260D</u>		Batch	ı ID:	30262 Analyst: KT
Benzene	ND	0.0282		mg/Kg-dry	1	11/4/2020 10:32:28 AM
Toluene	ND	0.0282		mg/Kg-dry	1	11/4/2020 10:32:28 AM
Ethylbenzene	ND	0.0353		mg/Kg-dry	1	11/4/2020 10:32:28 AM
m,p-Xylene	ND	0.0706		mg/Kg-dry	1	11/4/2020 10:32:28 AM
o-Xylene	ND	0.0353		mg/Kg-dry	1	11/4/2020 10:32:28 AM
Surr: Dibromofluoromethane	96.9	85.2 - 113		%Rec	1	11/4/2020 10:32:28 AM
Surr: Toluene-d8	100	88.5 - 110		%Rec	1	11/4/2020 10:32:28 AM
Surr: 1-Bromo-4-fluorobenzene	94.6	88.6 - 109		%Rec	1	11/4/2020 10:32:28 AM
Sample Moisture (Percent Moist	ure)			Batch	ı ID:	R63112 Analyst: CJ
Percent Moisture	7.34	0.500		wt%	1	11/4/2020 8:11:58 AM



Work Order: **2010479**Date Reported: **11/11/2020**

Client: Fulcrum Environmental Collection Date: 10/28/2020 10:18:00 AM

Project: WA Land MGMT Ranch 19

Lab ID: 2010479-003 **Matrix:** Soil

Client Sample ID: R19E-102820-12.8

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
Diesel and Heavy Oil by NWTPH	-Dx/Dx Ext.			Batch	ı ID:	30227 Analyst: DW
Diesel (Fuel Oil)	ND	17.7		mg/Kg-dry	1	10/31/2020 4:55:52 AM
Heavy Oil	ND	44.3		mg/Kg-dry	1	10/31/2020 4:55:52 AM
Surr: 2-Fluorobiphenyl	102	50 - 150		%Rec	1	10/31/2020 4:55:52 AM
Surr: o-Terphenyl	86.4	50 - 150		%Rec	1	10/31/2020 4:55:52 AM
Volatile Organic Compounds by	EPA Method	8260D		Batch	ı ID:	30262 Analyst: KT
Benzene	ND	0.0286		mg/Kg-dry	1	11/4/2020 11:02:56 AM
Toluene	ND	0.0286		mg/Kg-dry	1	11/4/2020 11:02:56 AM
Ethylbenzene	ND	0.0357		mg/Kg-dry	1	11/4/2020 11:02:56 AM
m,p-Xylene	ND	0.0715		mg/Kg-dry	1	11/4/2020 11:02:56 AM
o-Xylene	ND	0.0357		mg/Kg-dry	1	11/4/2020 11:02:56 AM
Surr: Dibromofluoromethane	96.1	85.2 - 113		%Rec	1	11/4/2020 11:02:56 AM
Surr: Toluene-d8	99.2	88.5 - 110		%Rec	1	11/4/2020 11:02:56 AM
Surr: 1-Bromo-4-fluorobenzene	94.3	88.6 - 109		%Rec	1	11/4/2020 11:02:56 AM
Sample Moisture (Percent Moist	ure)			Batch	ı ID:	R63112 Analyst: CJ
Percent Moisture	3.52	0.500		wt%	1	11/4/2020 8:11:58 AM



Work Order: **2010479**Date Reported: **11/11/2020**

Client: Fulcrum Environmental Collection Date: 10/28/2020 10:20:00 AM

Project: WA Land MGMT Ranch 19

Lab ID: 2010479-004 **Matrix:** Soil

Client Sample ID: R19E-102820-13.1

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
Diesel and Heavy Oil by NWTPH	-Dx/Dx Ext.			Batch	ı ID:	30227 Analyst: DW
Diesel (Fuel Oil)	74.6	19.0		mg/Kg-dry	1	10/31/2020 5:25:37 AM
Heavy Oil	ND	47.6		mg/Kg-dry	1	10/31/2020 5:25:37 AM
Surr: 2-Fluorobiphenyl	110	50 - 150		%Rec	1	10/31/2020 5:25:37 AM
Surr: o-Terphenyl	95.0	50 - 150		%Rec	1	10/31/2020 5:25:37 AM
Polyaromatic Hydrocarbons by	EPA Method 8	270 (SIM)		Batch	ID:	30353 Analyst: SB
Naphthalene	ND	39.5		μg/Kg-dry	1	11/10/2020 7:27:14 PM
2-Methylnaphthalene	ND	39.5		μg/Kg-dry	1	11/10/2020 7:27:14 PM
1-Methylnaphthalene	ND	39.5		μg/Kg-dry	1	11/10/2020 7:27:14 PM
Acenaphthylene	ND	39.5		μg/Kg-dry	1	11/10/2020 7:27:14 PM
Acenaphthene	ND	39.5		μg/Kg-dry	1	11/10/2020 7:27:14 PM
Fluorene	ND	39.5		μg/Kg-dry	1	11/10/2020 7:27:14 PM
Phenanthrene	ND	39.5		μg/Kg-dry	1	11/10/2020 7:27:14 PM
Anthracene	ND	39.5		μg/Kg-dry	1	11/10/2020 7:27:14 PM
Fluoranthene	ND	39.5		μg/Kg-dry	1	11/10/2020 7:27:14 PM
Pyrene	ND	39.5		μg/Kg-dry	1	11/10/2020 7:27:14 PM
Benz(a)anthracene	ND	39.5		μg/Kg-dry	1	11/10/2020 7:27:14 PM
Chrysene	ND	39.5		μg/Kg-dry	1	11/10/2020 7:27:14 PM
Benzo(b)fluoranthene	ND	39.5		μg/Kg-dry	1	11/10/2020 7:27:14 PM
Benzo(k)fluoranthene	ND	39.5		μg/Kg-dry	1	11/10/2020 7:27:14 PM
Benzo(a)pyrene	ND	39.5		μg/Kg-dry	1	11/10/2020 7:27:14 PM
Indeno(1,2,3-cd)pyrene	ND	39.5		μg/Kg-dry	1	11/10/2020 7:27:14 PM
Dibenz(a,h)anthracene	ND	39.5		μg/Kg-dry	1	11/10/2020 7:27:14 PM
Benzo(g,h,i)perylene	ND	39.5		μg/Kg-dry	1	11/10/2020 7:27:14 PM
Surr: 2-Fluorobiphenyl	72.6	16.9 - 122		%Rec	1	11/10/2020 7:27:14 PM
Surr: Terphenyl-d14 (surr)	97.1	38.4 - 153		%Rec	1	11/10/2020 7:27:14 PM
Volatile Organic Compounds by	EPA Method	8260D		Batch	ID:	30262 Analyst: KT
Benzene	ND	0.0266		mg/Kg-dry	1	11/4/2020 11:33:23 AM
Toluene	ND	0.0266		mg/Kg-dry	1	11/4/2020 11:33:23 AM
Ethylbenzene	ND	0.0332		mg/Kg-dry	1	11/4/2020 11:33:23 AM
m,p-Xylene	ND	0.0665		mg/Kg-dry	1	11/4/2020 11:33:23 AM
o-Xylene	ND	0.0332		mg/Kg-dry	1	11/4/2020 11:33:23 AM
Surr: Dibromofluoromethane	95.8	85.2 - 113		%Rec	1	11/4/2020 11:33:23 AM
Surr: Toluene-d8	99.8	88.5 - 110		%Rec	1	11/4/2020 11:33:23 AM
Surr: 1-Bromo-4-fluorobenzene	94.5	88.6 - 109		%Rec	1	11/4/2020 11:33:23 AM



Work Order: **2010479**Date Reported: **11/11/2020**

Client: Fulcrum Environmental Collection Date: 10/28/2020 10:20:00 AM

Project: WA Land MGMT Ranch 19

Lab ID: 2010479-004 **Matrix:** Soil

Client Sample ID: R19E-102820-13.1

Analyses Result RL Qual Units DF Date Analyzed

Sample Moisture (Percent Moisture)

Batch ID: R63112 Analyst: CJ

Percent Moisture 7.23 0.500 wt% 1 11/4/2020 8:11:58 AM



Work Order: **2010479**Date Reported: **11/11/2020**

Client: Fulcrum Environmental Collection Date: 10/28/2020 10:40:00 AM

Project: WA Land MGMT Ranch 19

Lab ID: 2010479-005 **Matrix:** Soil

Client Sample ID: R19E-102820-14.1

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
Diesel and Heavy Oil by NWTPH	-Dx/Dx Ext.			Batch	ID:	30253 Analyst: DW
Diesel (Fuel Oil)	ND	19.8		mg/Kg-dry	1	11/3/2020 5:16:07 AM
Heavy Oil	ND	49.4		mg/Kg-dry	1	11/3/2020 5:16:07 AM
Surr: 2-Fluorobiphenyl	107	50 - 150		%Rec	1	11/3/2020 5:16:07 AM
Surr: o-Terphenyl	89.9	50 - 150		%Rec	1	11/3/2020 5:16:07 AM
Volatile Organic Compounds by	EPA Method	8260D		Batch	ID:	30262 Analyst: KT
Benzene	ND	0.0340		mg/Kg-dry	1	11/4/2020 12:03:51 PM
Toluene	ND	0.0340		mg/Kg-dry	1	11/4/2020 12:03:51 PM
Ethylbenzene	ND	0.0425		mg/Kg-dry	1	11/4/2020 12:03:51 PM
m,p-Xylene	ND	0.0850		mg/Kg-dry	1	11/4/2020 12:03:51 PM
o-Xylene	ND	0.0425		mg/Kg-dry	1	11/4/2020 12:03:51 PM
Surr: Dibromofluoromethane	95.9	85.2 - 113		%Rec	1	11/4/2020 12:03:51 PM
Surr: Toluene-d8	99.9	88.5 - 110		%Rec	1	11/4/2020 12:03:51 PM
Surr: 1-Bromo-4-fluorobenzene	93.9	88.6 - 109		%Rec	1	11/4/2020 12:03:51 PM
Sample Moisture (Percent Moist	ure)			Batch	ID:	R63112 Analyst: CJ
Percent Moisture	7.32	0.500		wt%	1	11/4/2020 8:11:58 AM



Work Order: **2010479**Date Reported: **11/11/2020**

Client: Fulcrum Environmental Collection Date: 10/28/2020 10:40:00 AM

Project: WA Land MGMT Ranch 19

Lab ID: 2010479-006 **Matrix:** Soil

Client Sample ID: R19E-102820-15.1

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
Diesel and Heavy Oil by NWTPH	-Dx/Dx Ext.			Batch	ı ID:	30244 Analyst: DW
Diesel (Fuel Oil)	ND	20.5		mg/Kg-dry	1	11/3/2020 8:44:39 AM
Heavy Oil	ND	51.3		mg/Kg-dry	1	11/3/2020 8:44:39 AM
Surr: 2-Fluorobiphenyl	79.5	50 - 150		%Rec	1	11/3/2020 8:44:39 AM
Surr: o-Terphenyl	79.8	50 - 150		%Rec	1	11/3/2020 8:44:39 AM
Volatile Organic Compounds by	EPA Method	8260D		Batch	ı ID:	30262 Analyst: KT
Benzene	ND	0.0276		mg/Kg-dry	1	11/4/2020 12:34:21 PM
Toluene	ND	0.0276		mg/Kg-dry	1	11/4/2020 12:34:21 PM
Ethylbenzene	ND	0.0345		mg/Kg-dry	1	11/4/2020 12:34:21 PM
m,p-Xylene	ND	0.0690		mg/Kg-dry	1	11/4/2020 12:34:21 PM
o-Xylene	ND	0.0345		mg/Kg-dry	1	11/4/2020 12:34:21 PM
Surr: Dibromofluoromethane	95.5	85.2 - 113		%Rec	1	11/4/2020 12:34:21 PM
Surr: Toluene-d8	99.1	88.5 - 110		%Rec	1	11/4/2020 12:34:21 PM
Surr: 1-Bromo-4-fluorobenzene	94.4	88.6 - 109		%Rec	1	11/4/2020 12:34:21 PM
Sample Moisture (Percent Moist	ure)			Batch	ı ID:	R63112 Analyst: CJ
Percent Moisture	6.84	0.500		wt%	1	11/4/2020 8:11:58 AM



Work Order: **2010479**Date Reported: **11/11/2020**

Client: Fulcrum Environmental Collection Date: 10/28/2020 1:00:00 PM

Project: WA Land MGMT Ranch 19

Lab ID: 2010479-007 **Matrix:** Soil

Client Sample ID: R19E-102820-16.1

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
Diesel and Heavy Oil by NWTPH	-Dx/Dx Ext.			Batch	ı ID:	30244 Analyst: DW
Diesel (Fuel Oil)	ND	21.6		mg/Kg-dry	1	11/3/2020 10:14:33 AM
Heavy Oil	ND	54.0		mg/Kg-dry	1	11/3/2020 10:14:33 AM
Surr: 2-Fluorobiphenyl	76.6	50 - 150		%Rec	1	11/3/2020 10:14:33 AM
Surr: o-Terphenyl	76.2	50 - 150		%Rec	1	11/3/2020 10:14:33 AM
Volatile Organic Compounds by	EPA Method	<u>8260D</u>		Batch	ı ID:	30262 Analyst: KT
Benzene	ND	0.0375		mg/Kg-dry	1	11/4/2020 1:04:54 PM
Toluene	ND	0.0375		mg/Kg-dry	1	11/4/2020 1:04:54 PM
Ethylbenzene	ND	0.0469		mg/Kg-dry	1	11/4/2020 1:04:54 PM
m,p-Xylene	ND	0.0937		mg/Kg-dry	1	11/4/2020 1:04:54 PM
o-Xylene	ND	0.0469		mg/Kg-dry	1	11/4/2020 1:04:54 PM
Surr: Dibromofluoromethane	94.8	85.2 - 113		%Rec	1	11/4/2020 1:04:54 PM
Surr: Toluene-d8	99.4	88.5 - 110		%Rec	1	11/4/2020 1:04:54 PM
Surr: 1-Bromo-4-fluorobenzene	93.7	88.6 - 109		%Rec	1	11/4/2020 1:04:54 PM
Sample Moisture (Percent Moist	ure)			Batch	ID:	R63112 Analyst: CJ
Percent Moisture	10.3	0.500		wt%	1	11/4/2020 8:11:58 AM



Work Order: **2010479**Date Reported: **11/11/2020**

Client: Fulcrum Environmental Collection Date: 10/28/2020 10:25:00 AM

Project: WA Land MGMT Ranch 19

Lab ID: 2010479-008 **Matrix:** Soil

Client Sample ID: R19E-102820-17.6

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
Diesel and Heavy Oil by NWTPH	-Dx/Dx Ext.			Batch	ı ID:	30244 Analyst: DW
Diesel (Fuel Oil)	ND	18.5		mg/Kg-dry	1	11/3/2020 10:44:27 AM
Heavy Oil	ND	46.3		mg/Kg-dry	1	11/3/2020 10:44:27 AM
Surr: 2-Fluorobiphenyl	90.2	50 - 150		%Rec	1	11/3/2020 10:44:27 AM
Surr: o-Terphenyl	89.6	50 - 150		%Rec	1	11/3/2020 10:44:27 AM
Volatile Organic Compounds by	EPA Method	8260D		Batch	ı ID:	30262 Analyst: KT
Benzene	ND	0.0225		mg/Kg-dry	1	11/4/2020 1:35:20 PM
Toluene	ND	0.0225		mg/Kg-dry	1	11/4/2020 1:35:20 PM
Ethylbenzene	ND	0.0281		mg/Kg-dry	1	11/4/2020 1:35:20 PM
m,p-Xylene	ND	0.0562		mg/Kg-dry	1	11/4/2020 1:35:20 PM
o-Xylene	ND	0.0281		mg/Kg-dry	1	11/4/2020 1:35:20 PM
Surr: Dibromofluoromethane	95.4	85.2 - 113		%Rec	1	11/4/2020 1:35:20 PM
Surr: Toluene-d8	99.8	88.5 - 110		%Rec	1	11/4/2020 1:35:20 PM
Surr: 1-Bromo-4-fluorobenzene	95.0	88.6 - 109		%Rec	1	11/4/2020 1:35:20 PM
Sample Moisture (Percent Moist	ure)			Batch	ID:	R63112 Analyst: CJ
Percent Moisture	3.74	0.500		wt%	1	11/4/2020 8:11:58 AM



Work Order: **2010479**Date Reported: **11/11/2020**

Client: Fulcrum Environmental Collection Date: 10/28/2020 10:28:00 AM

Project: WA Land MGMT Ranch 19

Lab ID: 2010479-009 **Matrix:** Soil

Client Sample ID: R19E-102820-18.6

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
Diesel and Heavy Oil by NWTPH	-Dx/Dx Ext.			Batch	ı ID:	30244 Analyst: DW
Diesel (Fuel Oil)	ND	17.9		mg/Kg-dry	1	11/3/2020 11:14:24 AM
Heavy Oil	ND	44.8		mg/Kg-dry	1	11/3/2020 11:14:24 AM
Surr: 2-Fluorobiphenyl	77.8	50 - 150		%Rec	1	11/3/2020 11:14:24 AM
Surr: o-Terphenyl	78.1	50 - 150		%Rec	1	11/3/2020 11:14:24 AM
Volatile Organic Compounds by	EPA Method	8260D		Batch	ı ID:	30262 Analyst: KT
Benzene	ND	0.0241		mg/Kg-dry	1	11/4/2020 2:05:45 PM
Toluene	ND	0.0241		mg/Kg-dry	1	11/4/2020 2:05:45 PM
Ethylbenzene	ND	0.0301		mg/Kg-dry	1	11/4/2020 2:05:45 PM
m,p-Xylene	ND	0.0602		mg/Kg-dry	1	11/4/2020 2:05:45 PM
o-Xylene	ND	0.0301		mg/Kg-dry	1	11/4/2020 2:05:45 PM
Surr: Dibromofluoromethane	95.0	85.2 - 113		%Rec	1	11/4/2020 2:05:45 PM
Surr: Toluene-d8	100	88.5 - 110		%Rec	1	11/4/2020 2:05:45 PM
Surr: 1-Bromo-4-fluorobenzene	93.9	88.6 - 109		%Rec	1	11/4/2020 2:05:45 PM
Sample Moisture (Percent Moist	ure)			Batch	ID:	R63112 Analyst: CJ
Percent Moisture	2.93	0.500		wt%	1	11/4/2020 8:11:58 AM



Work Order: **2010479**Date Reported: **11/11/2020**


Client: Fulcrum Environmental Collection Date: 10/28/2020 10:30:00 AM

Project: WA Land MGMT Ranch 19

Lab ID: 2010479-010 **Matrix:** Soil

Client Sample ID: R19E-102820-19.6

Analyses	Result	RL	Qual	Units	DF	Date Analyzed
Diesel and Heavy Oil by NWTPH	-Dx/Dx Ext.			Batch	ı ID:	30244 Analyst: DW
Diesel (Fuel Oil)	ND	19.8		mg/Kg-dry	1	11/3/2020 11:44:12 AM
Heavy Oil	ND	49.5		mg/Kg-dry	1	11/3/2020 11:44:12 AM
Surr: 2-Fluorobiphenyl	76.6	50 - 150		%Rec	1	11/3/2020 11:44:12 AM
Surr: o-Terphenyl	77.5	50 - 150		%Rec	1	11/3/2020 11:44:12 AM
Volatile Organic Compounds by	EPA Method	8260D		Batch	ı ID:	30262 Analyst: KT
Benzene	ND	0.0284		mg/Kg-dry	1	11/4/2020 2:36:18 PM
Toluene	ND	0.0284		mg/Kg-dry	1	11/4/2020 2:36:18 PM
Ethylbenzene	ND	0.0355		mg/Kg-dry	1	11/4/2020 2:36:18 PM
m,p-Xylene	ND	0.0709		mg/Kg-dry	1	11/4/2020 2:36:18 PM
o-Xylene	ND	0.0355		mg/Kg-dry	1	11/4/2020 2:36:18 PM
Surr: Dibromofluoromethane	94.4	85.2 - 113		%Rec	1	11/4/2020 2:36:18 PM
Surr: Toluene-d8	100	88.5 - 110		%Rec	1	11/4/2020 2:36:18 PM
Surr: 1-Bromo-4-fluorobenzene	92.0	88.6 - 109		%Rec	1	11/4/2020 2:36:18 PM
Sample Moisture (Percent Moist	ure)			Batch	ID:	R63112 Analyst: CJ
Percent Moisture	3.01	0.500		wt%	1	11/4/2020 8:11:58 AM






QC SUMMARY REPORT

CLIENT: Fulcrum Environmental

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext

Project: WA Land N	MGMT Ranch 19						Diesel	and Heavy	Oil by NW	TPH-Dx/I	Ox Ex	
Sample ID: MB-30227	SampType: MBLK			Units: mg/Kg	g	Prep Date	e: 10/30/2	020	RunNo: 630)22		
Client ID: MBLKS	Batch ID: 30227					Analysis Date	e: 10/30/2	020	SeqNo: 126	64972		
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qua	
Diesel (Fuel Oil)	ND	20.0										
Heavy Oil	ND	50.0										
Surr: 2-Fluorobiphenyl	19.9		20.00		99.4	50	150					
Surr: o-Terphenyl	16.2		20.00		80.8	50	150					
Sample ID: LCS-30227	SampType: LCS			Units: mg/Kg	g	Prep Date	e: 10/30/2	020	RunNo: 63022			
Client ID: LCSS	Batch ID: 30227					Analysis Date: 10/30/2020			SeqNo: 1264973			
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qua	
Diesel (Fuel Oil)	451	20.0	500.0	0	90.3	65	135					
Surr: 2-Fluorobiphenyl	20.3		20.00		101	50	150					
Surr: o-Terphenyl	18.7		20.00		93.6	50	150					
Sample ID: 2010496-003AMS	SampType: MS			Units: mg/Kg	g-dry	Prep Date	e: 10/30/2	2020	RunNo: 630)22		
Client ID: BATCH	Batch ID: 30227					Analysis Date	e: 10/30/2	020	SeqNo: 126	64980		
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qua	
Diesel (Fuel Oil)	487	19.8	494.2	20.75	94.3	65	135					
Surr: 2-Fluorobiphenyl	19.2		19.77		96.9	50	150					
Surr: o-Terphenyl	18.2		19.77		91.9	50	150					
Sample ID: 2010496-003AMSD	SampType: MSD			Units: mg/Kg	g-dry	Prep Date	e: 10/30/2	2020	RunNo: 630)22		
Client ID: BATCH	Batch ID: 30227					Analysis Date	e: 10/30/2	020	SeqNo: 126	64981		
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qua	
Diesel (Fuel Oil)	630	22.6	564.6	20.75	108	65	135	486.8	25.7	30		
Surr: 2-Fluorobiphenyl	22.1		22.59		97.7	50	150		0			
Surr: o-Terphenyl	21.1		22.59		93.3	50	150		0			

Revision v1 Page 16 of 28






QC SUMMARY REPORT

CLIENT: Fulcrum Environmental

Diesel and Heavy Oil by NWTPH-Dx/Dx Ext.

Project: WA Land M	IGMT Ranc	h 19						Diesel	and Heavy	Oil by NW	TPH-Dx/I	Dx Ex
Sample ID: 2010479-004ADUP	SampType	: DUP	Units: mg/Kg-dry Prep Date: 10/30/2020					RunNo: 63022				
Client ID: R19E-102820-13.1	Batch ID:	30227					Analysis Date	e: 10/31/2	2020	SeqNo: 126	64999	
Analyte	I	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)		74.3	20.4						74.57	0.406	30	
Heavy Oil		ND	51.0						0		30	
Surr: 2-Fluorobiphenyl		20.1		20.40		98.4	50	150		0		
Surr: o-Terphenyl		17.7		20.40		86.9	50	150		0		
Sample ID: MB-30244	SampType	e: MBLK			Units: mg/Kg		Prep Date	e: 11/2/2 0)20	RunNo: 630		
Client ID: MBLKS	Batch ID:	30244					Analysis Date	e: 11/2/2 0	20	SeqNo: 126	55670	
Analyte	1	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)		ND	20.0									
Heavy Oil		ND	50.0									
Surr: 2-Fluorobiphenyl		17.7		20.00		88.7	50	150				
Surr: o-Terphenyl		18.1		20.00		90.4	50	150				
Sample ID: LCS-30244	SampType	e: LCS			Units: mg/Kg		Prep Date	e: 11/2/2 0)20	RunNo: 630)59	
Client ID: LCSS	Batch ID:	30244					Analysis Date	e: 11/2/2 0	20	SeqNo: 1265671		
Analyte	-	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)		524	20.0	500.0	0	105	65	135				
Surr: 2-Fluorobiphenyl		22.4		20.00		112	50	150				
Surr: o-Terphenyl		23.4		20.00		117	50	150				
Sample ID: MB-30253	SampType	e: MBLK			Units: mg/Kg		Prep Date	e: 11/2/20)20	RunNo: 630)61	
Client ID: MBLKS	Batch ID:	30253					Analysis Date	e: 11/2/2 0	20	SeqNo: 126	5708	
Analyte	I	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)		ND	20.0									
Diosci (i dei Oii)		ND	20.0									
Heavy Oil		ND	50.0									

Page 17 of 28 Revision v1






QC SUMMARY REPORT

CLIENT: Fulcrum Environmental

	IGMT Ranch 19						Diesel a	and Heavy	Oil by NW	TPH-Dx/I	Dx Ex	
Sample ID: MB-30253	SampType: MBLK			Units: mg/Kg		Prep Date	: 11/2/20	20	RunNo: 630	061		
Client ID: MBLKS	Batch ID: 30253					Analysis Date	e: 11/2/20	20	SeqNo: 126	55708		
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual	
Surr: o-Terphenyl	20.1		20.00		101	50	150					
Sample ID: LCS-30253	SampType: LCS			Units: mg/Kg		Prep Date	e: 11/2/20	20	RunNo: 63061			
Client ID: LCSS	Batch ID: 30253					Analysis Date	e: 11/2/20	20	SeqNo: 12 6	55709		
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual	
Diesel (Fuel Oil)	492	20.0	500.0	0	98.5	65	135					
Surr: 2-Fluorobiphenyl	23.6		20.00		118	50	150					
Surr: o-Terphenyl	22.1		20.00		110	50	150					
Sample ID: 2010469-011ADUP	SampType: DUP			Units: mg/Kg-	dry	Prep Date	e: 11/2/20	20	RunNo: 630	061		
Client ID: BATCH	Batch ID: 30253					Analysis Date	is Date: 11/3/2020		SeqNo: 1265725			
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual	
Diesel (Fuel Oil)	ND	23.0						0		30		
Heavy Oil	ND	57.4						0		30		
Surr: 2-Fluorobiphenyl	25.0		22.96		109	50	150		0			
Surr: o-Terphenyl	21.3		22.96		92.8	50	150		0			
Sample ID: 2010469-014AMS	SampType: MS			Units: mg/Kg-	dry	Prep Date	e: 11/2/20	20	RunNo: 63061			
Client ID: BATCH	Batch ID: 30253				Analysis Date: 11/3/2020		20	SeqNo: 126	65729			
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual	
Diesel (Fuel Oil)	586	24.5	611.7	0	95.8	65	135					
Surr: 2-Fluorobiphenyl	27.1		24.47		111	50	150					
Surr: o-Terphenyl	25.5		24.47		104	50	150					

Page 18 of 28 Revision v1






QC SUMMARY REPORT

CLIENT: Fulcrum Environmental

	IGMT Ranch 19						Diesel a	and Heavy	Oil by NW	TPH-Dx/I	Ox Ext
Sample ID: 2010469-014AMSD	SampType: MSD			Units: mg/	Kg-dry	Prep Dat	e: 11/2/20 2	20	RunNo: 630	061	
Client ID: BATCH	Batch ID: 30253					Analysis Dat	e: 11/3/20	20	SeqNo: 126	65730	
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	543	22.1	553.3	0	98.1	65	135	585.8	7.66	30	
Surr: 2-Fluorobiphenyl	23.7		22.13		107	50	150		0		
Surr: o-Terphenyl	23.1		22.13		104	50	150		0		
Sample ID: 2010479-006AMS	SampType: MS	Units: mg/Kg-dry Prep Date: 11/2/2020				20	RunNo: 630	059			
Client ID: R19E-102820-15.1	Batch ID: 30244					Analysis Dat	e: 11/3/20	20	SeqNo: 126	66524	
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	455	18.2	455.6	4.710	98.7	65	135				
Surr: 2-Fluorobiphenyl	16.4		18.22		90.0	50	150				
Surr: o-Terphenyl	14.7		18.22		80.5	50	150				
Sample ID: 2010479-006AMSD	SampType: MSD			Units: mg/	Kg-dry	Prep Dat	e: 11/2/20 2	20	RunNo: 630	059	
Client ID: R19E-102820-15.1	Batch ID: 30244					Analysis Dat	e: 11/3/20	20	SeqNo: 126	66525	
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Diesel (Fuel Oil)	446	18.3	458.7	4.710	96.2	65	135	454.6	1.96	30	
Surr: 2-Fluorobiphenyl	17.9		18.35		97.5	50	150		0		
Surr: o-Terphenyl	18.7		18.35		102	50	150		0		

Page 19 of 28 Revision v1





QC SUMMARY REPORT


CLIENT: Fulcrum Environmental

Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Project: WA Land	MGMT Ranch 19				Ро	lyaromatic	Hydrocarb	ons by	/ EPA Met	hod 8270	O (SIM)
Sample ID: MB-30353	SampType: MBLK			Units: µg/Kg		Prep Date:	11/10/2020		RunNo: 632	97	
Client ID: MBLKS	Batch ID: 30353					Analysis Date:	11/10/2020		SeqNo: 127	0424	
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit Hi	ghLimit RPD F	Ref Val	%RPD	RPDLimit	Qual
Naphthalene	ND	40.0									
2-Methylnaphthalene	ND	40.0									
1-Methylnaphthalene	ND	40.0									
Acenaphthylene	ND	40.0									
Acenaphthene	ND	40.0									
Fluorene	ND	40.0									
Phenanthrene	ND	40.0									
Anthracene	ND	40.0									
Fluoranthene	ND	40.0									
Pyrene	ND	40.0									
Benz(a)anthracene	ND	40.0									
Chrysene	ND	40.0									
Benzo(b)fluoranthene	ND	40.0									
Benzo(k)fluoranthene	ND	40.0									
Benzo(a)pyrene	ND	40.0									
Indeno(1,2,3-cd)pyrene	ND	40.0									
Dibenz(a,h)anthracene	ND	40.0									
Benzo(g,h,i)perylene	ND	40.0									
Surr: 2-Fluorobiphenyl	519		500.0		104	16.9	122				
Surr: Terphenyl-d14 (surr)	562		500.0		112	38.4	153				

Sample ID: LCS-30353	SampType: LCS			Units: µg/Kg		Prep Da	te: 11/10/2	020	RunNo: 632	297	
Client ID: LCSS	Batch ID: 30353					Analysis Da	te: 11/10/2	020	SeqNo: 12 7	70425	
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	1,050	40.0	1,000	0	105	57.2	127				
2-Methylnaphthalene	1,050	40.0	1,000	0	105	55.1	134				
1-Methylnaphthalene	1,090	40.0	1,000	0	109	56.9	136				
Acenaphthylene	830	40.0	1,000	0	83.0	58.5	132				
Acenaphthene	1,020	40.0	1,000	0	102	57.9	132				

Page 20 of 28 Revision v1





Project:

QC SUMMARY REPORT


CLIENT: Fulcrum Environmental

WA Land MGMT Ranch 19

Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Sample ID: LCS-30353	SampType: LCS			Units: µg/Kg	3	Prep Da	te: 11/10/2	2020	RunNo: 632	297	
Client ID: LCSS	Batch ID: 30353					Analysis Da	te: 11/10/2	2020	SeqNo: 12 7	70425	
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Fluorene	1,260	40.0	1,000	0	126	59.2	134				
Phenanthrene	1,050	40.0	1,000	0	105	57.1	135				
Anthracene	1,030	40.0	1,000	0	103	55.7	137				
Fluoranthene	1,120	40.0	1,000	0	112	58.1	134				
Pyrene	1,090	40.0	1,000	0	109	59.6	136				
Benz(a)anthracene	1,030	40.0	1,000	0	103	51.5	139				
Chrysene	1,070	40.0	1,000	0	107	58.3	130				
Benzo(b)fluoranthene	1,040	40.0	1,000	0	104	53.4	138				
Benzo(k)fluoranthene	1,160	40.0	1,000	0	116	50.9	140				
Benzo(a)pyrene	1,300	40.0	1,000	0	130	50.4	143				
Indeno(1,2,3-cd)pyrene	1,270	40.0	1,000	0	127	52.3	138				
Dibenz(a,h)anthracene	1,190	40.0	1,000	0	119	53	140				
Benzo(g,h,i)perylene	1,180	40.0	1,000	0	118	51.7	139				
Surr: 2-Fluorobiphenyl	536		500.0		107	16.9	122				
Surr: Terphenyl-d14 (surr)	596		500.0		119	38.4	153				
Sample ID: 2010479-004AMS	SampType: MS			Units: µg/Kg	g-dry	Prep Da	te: 11/10/2	2020	RunNo: 632	297	
Client ID: R19E-102820-13.1	Batch ID: 30353					Analysis Da	te: 11/10/2	2020	SeqNo: 127	70427	
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	701	39.0	975.5	0	71.9	46	106				
2-Methylnaphthalene	698	39.0	975.5	0	71.6	45.3	117				
1-Methylnaphthalene	719	39.0	975.5	0	73.7	48.6	116				
Acenaphthylene	652	39.0	975.5	0	66.8	50	114				
Acenaphthene	680	39.0	975.5	0	69.7	54.9	108				
Fluorene		39.0	975.5	0	74.9	54.3	110				
	731	39.0	37 3.3	•							
Phenanthrene	731 710	39.0	975.5	0	72.8	48.9	114				
							114 111				
Phenanthrene	710	39.0	975.5	0	72.8	48.9					

Revision v1 Page 21 of 28





Project:

QC SUMMARY REPORT

CLIENT: Fulcrum Environmental

WA Land MGMT Ranch 19

Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Sample ID: 2010479-004AMS	SampType: MS			Units: µg/K	g-dry	Prep Da	te: 11/10/2	020	RunNo: 632	297	
Client ID: R19E-102820-13.1	Batch ID: 30353					Analysis Da	te: 11/10/2	020	SeqNo: 127	70427	
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benz(a)anthracene	786	39.0	975.5	0	80.6	39.9	125				
Chrysene	725	39.0	975.5	0	74.3	46.8	112				
Benzo(b)fluoranthene	781	39.0	975.5	0	80.1	42.4	123				
Benzo(k)fluoranthene	735	39.0	975.5	0	75.3	41.7	122				
Benzo(a)pyrene	889	39.0	975.5	0	91.1	48.2	121				
Indeno(1,2,3-cd)pyrene	783	39.0	975.5	0	80.3	43.6	114				
Dibenz(a,h)anthracene	730	39.0	975.5	0	74.8	43.7	116				
Benzo(g,h,i)perylene	731	39.0	975.5	0	75.0	43.7	115				
Surr: 2-Fluorobiphenyl	356		487.7		73.1	16.9	122				
Surr: Terphenyl-d14 (surr)	374		487.7		76.6	38.4	153				

Sample ID: 2010479-004AMSD	SampType: MSD			Units: µg/K	g-dry	Prep Date	e: 11/10/2	020	RunNo: 632	297	
Client ID: R19E-102820-13.1	Batch ID: 30353					Analysis Date	e: 11/10/2	020	SeqNo: 127	70428	
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Naphthalene	746	38.6	965.9	0	77.2	46	106	700.9	6.23	30	
2-Methylnaphthalene	734	38.6	965.9	0	76.0	45.3	117	698.0	5.03	30	
1-Methylnaphthalene	767	38.6	965.9	0	79.4	48.6	116	719.4	6.42	30	
Acenaphthylene	601	38.6	965.9	0	62.2	50	114	651.5	8.06	30	
Acenaphthene	719	38.6	965.9	0	74.4	54.9	108	679.9	5.60	30	
Fluorene	890	38.6	965.9	0	92.1	54.3	110	730.8	19.7	30	
Phenanthrene	732	38.6	965.9	0	75.7	48.9	114	710.4	2.94	30	
Anthracene	729	38.6	965.9	0	75.4	53.1	111	719.8	1.20	30	
Fluoranthene	726	38.6	965.9	0	75.2	48.5	117	834.5	13.9	30	
Pyrene	702	38.6	965.9	8.157	71.9	48.5	121	811.7	14.5	30	
Benz(a)anthracene	854	38.6	965.9	0	88.4	39.9	125	786.2	8.28	30	
Chrysene	751	38.6	965.9	0	77.8	46.8	112	724.9	3.59	30	
Benzo(b)fluoranthene	764	38.6	965.9	0	79.1	42.4	123	781.4	2.30	30	
Benzo(k)fluoranthene	742	38.6	965.9	0	76.8	41.7	122	734.8	0.954	30	
Benzo(a)pyrene	873	38.6	965.9	0	90.4	48.2	121	888.5	1.72	30	

Revision v1 Page 22 of 28

Date: 11/11/2020



Work Order: 2010479

Project:

QC SUMMARY REPORT


CLIENT: Fulcrum Environmental

WA Land MGMT Ranch 19

Polyaromatic Hydrocarbons by EPA Method 8270 (SIM)

Sample ID: 2010479-004AMSD	SampType: MSD			Units: µg/K	g-dry	Prep Da	te: 11/10/2	2020	RunNo: 632	297	
Client ID: R19E-102820-13.1	Batch ID: 30353					Analysis Da	te: 11/10/2	2020	SeqNo: 12 7	70428	
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Indeno(1,2,3-cd)pyrene	803	38.6	965.9	0	83.2	43.6	114	783.1	2.54	30	
Dibenz(a,h)anthracene	743	38.6	965.9	0	77.0	43.7	116	730.0	1.83	30	
Benzo(g,h,i)perylene	745	38.6	965.9	0	77.2	43.7	115	731.4	1.89	30	
Surr: 2-Fluorobiphenyl	385		482.9		79.8	16.9	122		0		
Surr: Terphenyl-d14 (surr)	379		482.9		78.5	38.4	153		0		

Revision v1 Page 23 of 28





QC SUMMARY REPORT

CLIENT: Fulcrum Environmental

Volatile Organic Compounds by EPA Method 8260D

Project: WA Land MC	GMT Ranch 19					Volatile	Organic	Compoun	ds by EPA	Method	8260
Sample ID: LCS-30262	SampType: LCS			Units: mg/Kg		Prep Da	te: 11/3/20	20	RunNo: 631	18	
Client ID: LCSS	Batch ID: 30262					Analysis Da	te: 11/3/20	20	SeqNo: 126	6808	
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	0.996	0.0200	1.000	0	99.6	79.4	116				
Toluene	1.04	0.0200	1.000	0	104	80.5	115				
Ethylbenzene	1.05	0.0250	1.000	0	105	81.6	116				
m,p-Xylene	2.10	0.0500	2.000	0	105	83.2	115				
o-Xylene	1.03	0.0250	1.000	0	103	82.5	114				
Surr: Dibromofluoromethane	1.26		1.250		101	85.2	113				
Surr: Toluene-d8	1.27		1.250		102	88.5	110				
Surr: 1-Bromo-4-fluorobenzene	1.26		1.250		101	88.6	109				
Sample ID: MB-30262	SampType: MBLK			Units: mg/Kg		Prep Da	te: 11/3/20	20	RunNo: 631	18	
Client ID: MBLKS	Batch ID: 30262					Analysis Da	te: 11/3/20	20	SeqNo: 126	6807	
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qua
Benzene	ND	0.0200									
Toluene	ND	0.0200									
Ethylbenzene	ND	0.0250									
n,p-Xylene	ND	0.0500									
o-Xylene	ND	0.0250									
Surr: Dibromofluoromethane	1.20		1.250		95.8	85.2	113				
Surr: Toluene-d8	1.23		1.250		98.4	88.5	110				
Surr: 1-Bromo-4-fluorobenzene	1.18		1.250		94.0	88.6	109				
Sample ID: 2010457-001BDUP	SampType: DUP			Units: mg/Kg-	dry	Prep Da	te: 11/3/20	20	RunNo: 631	18	
Client ID: BATCH	Batch ID: 30262					Analysis Da	te: 11/3/20	20	SeqNo: 126	6793	
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qua
Benzene	ND	0.0247	-					0		30	
Toluene	ND	0.0247						0		30	
Ethylbenzene	ND	0.0309						0		30	

Page 24 of 28 Revision v1

Date: 11/11/2020



Work Order: 2010479

Project:

QC SUMMARY REPORT

CLIENT: Fulcrum Environmental

WA Land MGMT Ranch 19

Volatile Organic Compounds by EPA Method 8260D

Sample ID: 2010457-001BDUP	SampType: DUP			Units: mg/K	g-dry	Prep Da	te: 11/3/20	20	RunNo: 631	118	
Client ID: BATCH	Batch ID: 30262					Analysis Da	te: 11/3/20	20	SeqNo: 126	66793	
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
m,p-Xylene	ND	0.0617						0		30	
o-Xylene	ND	0.0309						0		30	
Surr: Dibromofluoromethane	1.49		1.543		96.6	85.2	113		0		
Surr: Toluene-d8	1.54		1.543		99.9	88.5	110		0		
Surr: 1-Bromo-4-fluorobenzene	1.47		1.543		95.5	88.6	109		0		

Sample ID: 2010457-002BMS	SampType: MS			Units: mg/	Kg-dry	Prep Da	te: 11/3/20	20	RunNo: 631	118	
Client ID: BATCH	Batch ID: 30262					Analysis Da	te: 11/4/20	20	SeqNo: 126	66795	
Analyte	Result	RL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	RPD Ref Val	%RPD	RPDLimit	Qual
Benzene	1.23	0.0238	1.189	0	103	74.6	126				
Toluene	1.25	0.0238	1.189	0	105	72.6	127				
Ethylbenzene	1.29	0.0297	1.189	0	109	77.3	126				
m,p-Xylene	2.58	0.0594	2.378	0	109	78.5	126				
o-Xylene	1.27	0.0297	1.189	0	107	79.4	123				
Surr: Dibromofluoromethane	1.52		1.486		102	85.2	113				
Surr: Toluene-d8	1.50		1.486		101	88.5	110				
Surr: 1-Bromo-4-fluorobenzene	1.55		1.486		104	88.6	109				

Revision v1 Page 25 of 28



Sample Log-In Check List

С	lient Name:	FE	Work Order Numb	ber: 2010479		
Lo	ogged by:	Carissa True	Date Received:	10/29/2020	9:34:00 AM	
Cha	in of Custo	ody				
1.	Is Chain of C	ustody complete?	Yes 🗸	No \square	Not Present	
2.	How was the	sample delivered?	<u>UPS</u>			
Log	ı İn					
_	Coolers are p	oresent?	Yes 🗸	No 🗌	NA 🗆	
٥.	осолого ало р		. 55			
4.	Shipping con	tainer/cooler in good condition?	Yes 🗹	No \square		
5.		ls present on shipping container/cooler? nments for Custody Seals not intact)	Yes	No 🗌	Not Present ✓	
6.	Was an atten	npt made to cool the samples?	Yes 🗸	No 🗌	NA \square	
7.	Were all item	s received at a temperature of >2°C to 6°C *	Yes 🗸	No 🗆	na 🗆	
8.	Sample(s) in	proper container(s)?	Yes 🗹	No 🗆		
9.	Sufficient sar	nple volume for indicated test(s)?	Yes 🗸	No \square		
10.	Are samples	properly preserved?	Yes 🗸	No \square		
11.	Was preserva	ative added to bottles?	Yes	No 🗹	NA 🗆	
12.	Is there head	space in the VOA vials?	Yes	No 🗆	NA 🗹	
13.	Did all sample	es containers arrive in good condition(unbroken)?	Yes 🗸	No \square		
14.	Does paperw	ork match bottle labels?	Yes 🗸	No \square		
15.	Are matrices	correctly identified on Chain of Custody?	Yes 🗹	No \square		
16.	Is it clear wha	at analyses were requested?	Yes 🗸	No \square		
17.	Were all hold	ing times able to be met?	Yes 🗹	No \square		
Spe	cial Handl	ing (if applicable)				
-		otified of all discrepancies with this order?	Yes	No 🗌	NA 🗹	
	Person	Notified: Date:				
	By Who	m: Via:	eMail Ph	one 🗌 Fax 🛛	In Person	
	Regardi	ng:				
	Client In	nstructions:				
19.	Additional rer	marks:				
<u>lte</u> m	<u>Information</u>					
		Item # Temp °C				

Sample 1

^{*} Note: DoD/ELAP and TNI require items to be received at 4°C +/- 2°C

(specify)											N ASSET SPECIAL PR
Same Day		odie/ imie			×					/	
Next Day	100 00 0121	1014	100	Received	P	6:00	20	Date/Time	***************************************	1	Relinguished
) (z say	5	Date/Time	4	Received //	×		`	Date/Time		7	Relinquished
	I represent that I am authorized to enter into this Agreement with Fremont Analytical on behalf of the Client named above and that I have verified Client's agreement to each of the terms on the front and backside of this Agreement.	above and that	of the Client named	ical on behalf o	emont Analyt	nent with Fro	this Agreen f this Agreen	o enter into l backside o	I represent that I am authorized to enter into this Agreement each of the terms on the front and backside of this Agreement.	that I am terms on t	I represent
_			Nitrate+Nitrite	Fluoride	O-Phosphate	Bromide	Sulfate	Chloride	ite Nitrite	le): Nitrate	***Anions (Circle):
Standard	bSbSeSrSnTiTIUVZn	Mn Mo Na Ni Pb	Cr Cu Fe Hg K Mg	Be Ca Cd Co	Ag Al As B Ba	Individual: I	tants TAL	Priority Pollutants	RC	3	**Metals (Circle):
Turn-around Time:	SW = Storm Water, WW = Waste Water	= Ground Water, SV	DW = Drinking Water, GW	W = Water,	nent, SL = Solid,	soil, SD = Sediment,	P = Product, S = Soil,	0 = Other, P	ous,	, AQ = Aque	*Matrix: A = Air
				-	-	,-	10:50	_	-15.6		10
							87:01		-18.6		
							10:25		-17.6		86
							13:00		-16.1		7
							10:40	-	-15.1		6
							10:40		-14.1		5
							16:20		1.51-		4
							10:18		-12,8		3
						-	10:15	-	11.2	,	2
					×	2165	10:05	10/24	10.1	241	17496-1028z
Comments		18 (E) 18	18 18 25 18 08 14 16 18 18 18 18 18 18 18 18 18 18 18 18 18	Secure to the Company of the Company	Secretary Secology	Sample Type (Matrix)*	Sample	Sample		8	Sample Name
		· NET	of Cetudasum	any. Lym	PM Email: TEARNY.	P			509.575.8453	9.575	Fax: S
Disposal by lab (after 30 days)	Sample Disposal: Return to client	***************************************		Report To (PM): ゴ・レソルへ	epart To (PM):	Re			2230.46		Telephone: 504
				Pl Hamper	Location: 72.0		o/	9890/	VAICHER, WA		City, State, Zip:
			***************************************	Jeynn.	Collected by: ゴ・レイルル	C	2	STREET	2	6	Address: 406
	***************************************				Project No:	P	2774	Conscience	ENVINO		Client: Fulcour
	Special Remarks:	nex 19	Mant Tra	5	Project Name: 600			A L M L J MI	TOWNS CONTROL		
2440106	Laboratory Project No (internal):	\$\\\ 2	Page:	8	Date: 10/28/20		Tel: 206-352-3790				
Agreement	ord or Laboratory Services Agreement	טוט פע דמ	Stody Nec	200	C110	98103	Seattle, WA 98103	3		D	
A	horstory Corvings	Ord 8. 12	Chain of Custody Rec		Chu	Ave N.	3600 Fremont Ave N.				Wall and

Page 27 of 28

COC 1.2 - 2.22.17

	3600 Fremont Ave N.	Chain of Custody Rec	ord & Laboratory Services Agreement
remonu		Date: 10 / 72/ 720 Page:	Laboratory Project No (Internal): 7010479
Analytical	Fax: 206-352-7178	Project Name: LAN LAND MAINT TOANCE	Special Remarks: Add applysis 11/5/20 per NM- gas
Client: Fulcour ENVIGO CO.	CONSCIENCE	Project No:	5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5
Address: 406 N 25 5	SPRESS	Collected by: 1. LY NX	
City, State, Zip: YAICHER WA	9890/	Location: Tearett 19	
Telephone: 504, 574.0839			Sample Disposal: Return to client Disposal by lab (after 30 days)
Fax: 509.575,8453		PM Email:	
		Maria Constantino	
Sample Name	Sample Sample Type Date Time (Matrix)*	THE SOLD STATES OF STATES	Comments
1749E-102820 - 10.1	10/24 10:05 Soil	×	
2 - 11.2	10:15		
3 -12,8	81:01		
4 -13.1	16:70	×	
5 -14.1	10:40		
-15/	loig.		
7 -16.1	13:00		
8 -17.6	10:25		
-18.6	82:01		
10 -15.6	1 10:50		
*Matrix: A = Air, AQ = Aqueous, B = Bulk, O = Other, P = Product, S = Soil, SD = Sediment,	Other, P=Product, S=Soil, S	SL = Solid, W = Water, DW = Drinking Water, GW = Ground Water,	SW = Storm Water, WW = Waste Water Turn-ground Time:
: Nitrate Nitrite	Chloride Sulfate Br	Bromide O-Phosphate Fluoride Nitrate+Nitrite	Se Sr Sn Ti Ti U V Zn Standard
I represent that I am authorized to enter into this Agreement each of the terms on the front and backside of this Agreement	iter into this Agreement v	remont Analytical on behalf of	ave verified Client's agreement to 3 Day
Relinquished	Date/Time	Received	□ 2 Day
8	10/28/20 16:00		O C939 Next Day
Relinguished	Date/Time	Received Date/Time	1

Page 28 of 28

COC 1.2 - 2.22.17



Appendix F

TEE Form



Voluntary Cleanup Program

Washington State Department of Ecology Toxics Cleanup Program

TERRESTRIAL ECOLOGICAL EVALUATION FORM

Under the Model Toxics Control Act (MTCA), a terrestrial ecological evaluation is necessary if hazardous substances are released into the soils at a Site. In the event of such a release, you must take one of the following three actions as part of your investigation and cleanup of the Site:

- 1. Document an exclusion from further evaluation using the criteria in WAC 173-340-7491.
- 2. Conduct a simplified evaluation as set forth in WAC 173-340-7492.
- 3. Conduct a site-specific evaluation as set forth in WAC 173-340-7493.

When requesting a written opinion under the Voluntary Cleanup Program (VCP), you must complete this form and submit it to the Department of Ecology (Ecology). The form documents the type and results of your evaluation.

Completion of this form is not sufficient to document your evaluation. You still need to document your analysis and the basis for your conclusion in your cleanup plan or report.

If you have questions about how to conduct a terrestrial ecological evaluation, please contact the Ecology site manager assigned to your Site. For additional guidance, please refer to https://ecology.wa.gov/Regulations-Permits/Guidance-technical-assistance/Terrestrial-ecological-evaluation.

Step 1: IDENTIFY HAZARDOUS WASTE SITE			
Please identify below the hazardous waste site for which you are documenting an evaluation.			
Facility/Site Name: Ranch 19 East			
Facility/Site Address: 441 Williamson Road, Sunnyside, Washington			
Facility/Site No:	VCP Project No.:		

Step 2: IDENTIFY EVALUATOR							
Please identify below the person who conducted the evaluation and their contact information.							
Name: Jeremy Lynn			Title: Hydrogeologist				
Organization: Fulcrum Environmental Consulting, Inc.							
Mailing address: 406 North 2 nd Street							
City: Yakima		State: WA		Zip code: 98901			
Phone: 509-574-0839	Fax:		E-mail: Jeremy.lynn@efulcrum.net				


Step 3: DOCUMENT EVALUATION TYPE AND RESULTS A. Exclusion from further evaluation. 1. Does the Site qualify for an exclusion from further evaluation? If you answered "YES," then answer Question 2. ☐ Yes ⊠ No or If you answered "NO" or "UNKNOWN," then skip to Step 3B of this form. Unknown 2. What is the basis for the exclusion? Check all that apply. Then skip to Step 4 of this form. Point of Compliance: WAC 173-340-7491(1)(a) All soil contamination is, or will be,* at least 15 feet below the surface. All soil contamination is, or will be,* at least 6 feet below the surface (or alternative depth if approved by Ecology), and institutional controls are used to manage remaining contamination. Barriers to Exposure: WAC 173-340-7491(1)(b) All contaminated soil, is or will be,* covered by physical barriers (such as buildings or paved roads) that prevent exposure to plants and wildlife, and institutional controls are used to manage remaining contamination. Undeveloped Land: WAC 173-340-7491(1)(c) There is less than 0.25 acres of contiguous# undeveloped* land on or within 500 feet of any area of the Site and any of the following chemicals is present: chlorinated dioxins or furans, PCB mixtures, DDT, DDE, DDD, aldrin, chlordane, dieldrin, endosulfan, endrin, heptachlor, heptachlor epoxide, benzene hexachloride, toxaphene, hexachlorobenzene, pentachlorophenol, or pentachlorobenzene. For sites not containing any of the chemicals mentioned above, there is less than 1.5 acres of contiguous# undeveloped± land on or within 500 feet of any area of the Site. Background Concentrations: WAC 173-340-7491(1)(d) Concentrations of hazardous substances in soil do not exceed natural background levels as described in WAC 173-340-200 and 173-340-709. * An exclusion based on future land use must have a completion date for future development that is acceptable to Ecology. [±] "Undeveloped land" is land that is not covered by building, roads, paved areas, or other barriers that would prevent wildlife from feeding on plants, earthworms, insects, or other food in or on the soil. # "Contiguous" undeveloped land is an area of undeveloped land that is not divided into smaller areas of highways, extensive paving, or similar structures that are likely to reduce the potential use of the overall area by wildlife.

В.	s. Simplified evaluation.						
1.	. Does the Site qualify for a simplified evaluation?						
	⊠ Yes	If you answered "YES," then answer Question 2 below.					
	☐ No Unknow	IT VALL ANSWARAD "NEE" AT "LINK NEEDWIN " THAN SKIN TO STAN SEE AT THIS TARM					
2.	. Did you conduct a simplified evaluation?						
	⊠ Yes	If you answered "YES," then answer Question 3 below.					
	☐ No	If you answered "NO," then skip to Step 3C of this form.					
3.	Was further	evaluation necessary?					
	☐ Yes	If you answered "YES," then answer Question 4 below.					
	⊠ No	If you answered "NO," then answer Question 5 below.					
4.	If further eva	luation was necessary, what did you do?					
		Used the concentrations listed in Table 749-2 as cleanup levels. If so, then skip to Step 4 of this form.					
		Conducted a site-specific evaluation. If so, then skip to Step 3C of this form.					
5.	5. If no further evaluation was necessary, what was the reason? Check all that apply. Then skip to Step 4 of this form.						
	Exposure Analysis: WAC 173-340-7492(2)(a)						
		Area of soil contamination at the Site is not more than 350 square feet.					
		Current or planned land use makes wildlife exposure unlikely. Used Table 749-1.					
	Pathway Ana	llysis: WAC 173-340-7492(2)(b)					
	No potential exposure pathways from soil contamination to ecological receptors.						
	Contaminant Analysis: WAC 173-340-7492(2)(c)						
	IXI	No contaminant listed in Table 749-2 is, or will be, present in the upper 15 feet at concentrations that exceed the values listed in Table 749-2.					
		No contaminant listed in Table 749-2 is, or will be, present in the upper 6 feet (or alternative depth if approved by Ecology) at concentrations that exceed the values isted in Table 749-2, and institutional controls are used to manage remaining contamination.					
		No contaminant listed in Table 749-2 is, or will be, present in the upper 15 feet at concentrations likely to be toxic or have the potential to bioaccumulate as determined using Ecology-approved bioassays.					
		No contaminant listed in Table 749-2 is, or will be, present in the upper 6 feet (or alternative depth if approved by Ecology) at concentrations likely to be toxic or have he potential to bioaccumulate as determined using Ecology-approved bioassays, and nstitutional controls are used to manage remaining contamination.					

C.	C. Site-specific evaluation. A site-specific evaluation process consists of two parts: (1) formulating the problem, and (2) selecting the methods for addressing the identified problem. Both steps require consultation with and approval by Ecology. See WAC 173-340-7493(1)(c).						
1.	Was there a problem? See WAC 173-340-7493(2).						
	Yes If you answered "YES," then answer Question 2 below.						
	No If you answered " NO ," then identify the reason here and then skip to Question 5 below:						
	No issues were identified during the problem formulation step.						
	While issues were identified, those issues were addressed by the cleanup actions for protecting human health.						
2.	What did you do to resolve the problem? See WAC 173-340-7493(3).						
	Used the concentrations listed in Table 749-3 as cleanup levels. <i>If so, then skip to</i> Question 5 below.						
	Used one or more of the methods listed in WAC 173-340-7493(3) to evaluate and address the identified problem. <i>If so, then answer Questions 3 and 4 below.</i>						
3.	B. If you conducted further site-specific evaluations, what methods did you use? Check all that apply. See WAC 173-340-7493(3).						
	Literature surveys.						
	Soil bioassays.						
	☐ Wildlife exposure model.						
	☐ Biomarkers.						
	Site-specific field studies.						
	☐ Weight of evidence.						
	Other methods approved by Ecology. If so, please specify:						
4.	What was the result of those evaluations?						
	Confirmed there was no problem.						
	Confirmed there was a problem and established site-specific cleanup levels.						
5.	5. Have you already obtained Ecology's approval of both your problem formulation and problem resolution steps?						
	Yes If so, please identify the Ecology staff who approved those steps:						
	□ No						

Step 4: SUBMITTAL

Please mail your completed form to the Ecology site manager assigned to your Site. If a site manager has not yet been assigned, please mail your completed form to the Ecology regional office for the County in which your Site is located.



Northwest Region: Attn: VCP Coordinator 3190 160th Ave. SE Bellevue, WA 98008-5452

Southwest Region: Attn: VCP Coordinator P.O. Box 47775 Olympia, WA 98504-7775 Central Region:
Attn: VCP Coordinator

1250 West Alder St. Union Gap, WA 98903-0009

Eastern Region: Attn: VCP Coordinator N. 4601 Monroe Spokane WA 99205-1295