



NOTE:

1. INSTALL NEW PACKED PUMP STATION, AFTER DUPLEX PUMP PACKAGE PER SPECIFICATION IN 48" FRP BASIN, TOP ELEVATION 73.0.
2. LOCATE PUMP STATION CONTROL PANEL ON 4"x4" TREATED WOOD POST, 10' X 10' CONCRETE FOUNDATION, FACE OF PANEL TO BE MIN. 2' FROM EDGE OF ROAD.
3. NOT USED ON THIS SHEET.
4. EXTEND FENCE ALONG DRIVEWAY 2' BACK FROM FACE OF CURB AND RELOCATE REMAINING FENCE TO ENCLOSE NEW PUMP STATION AND SDR MANHOLE.
5. REPLACE EXISTING MH UD WITH FIBERGLASS CASKETS UD 5 LOCATIONS. UD SHALL BE AS SPECIFIED IN SECTION 02805.

No.	REVISION	BY	APPD	DATE

RECORD DRAWING
 This document was compiled from all available information provided relative to this sheet upon the completion of the King County DWP WTD does not warrant or guarantee the accuracy or completion of the information contained herein.
 June 2012

DESIGNED/DRAWN	C. WOOD	SCALE	1"=40'-0"
PROJECT ENGINEER	A. LINTOT		
SEEN APPROVAL	R. BRODIE		
PROJECT SUPERVISOR	L. HOBELL		
CONTRACT NO.	00048508		

DEPARTMENT OF NATURAL RESOURCES & PARKS
 CANYON WASTEWATER TREATMENT FACILITY
 PROCESS & STORM WATER SEPARATION
 KING COUNTY
 YARD PIPING SITE PLAN

DATE	DEC 08
FILE NO.	423554-735
DRAWING NO.	C101
SHEET NO.	3 OF 28

ONE INCH
 AT FULL SIZE, IF NOT ONE INCH SCALE, ACCORDINGLY