


PUBLIC IMPROVEMENTS		XXXXXX	
COUNTRY ENGINEER _____		PERMIT # _____	
PIERCE COUNTY ORDINANCE NUMBER <b>99-2445</b>		DATE _____	
PROJECT LOCATION _____		DATE OF SUBMITTAL <b>3/7/08</b>	
CONTACT NAME _____		TO COORDINATE THE PROJECT, THE AREA INSPECTOR AT 233-5986 _____	
CONTACT PHONE _____		THE PROJECT SHALL BE COMPLETED BY _____	
CONTACT E-MAIL _____		THE PROJECT SHALL BE COMPLETED BY _____	
APPOINT A CERTIFIED EROSION AND SEDIMENT CONTROL LEAD WHO SHALL BE PROVIDED A COPY OF THE SWPPP, EROSION CONTROL PLAN & INSPECTION SCHEDULE.		APPOINT A CERTIFIED EROSION AND SEDIMENT CONTROL LEAD WHO SHALL BE PROVIDED A COPY OF THE SWPPP, EROSION CONTROL PLAN & INSPECTION SCHEDULE.	
FAILURE TO OBTAIN REQUIRED INSPECTIONS MAY ENDOANGER OR DELAY PROJECT APPROVAL.		FAILURE TO OBTAIN REQUIRED INSPECTIONS MAY ENDOANGER OR DELAY PROJECT APPROVAL.	
ALL WORK IN THE PUBLIC RIGHT-OF-WAY REQUIRES A GENERAL RIGHT-OF-WAY PERMIT FROM PIERCE COUNTY.		ALL WORK IN THE PUBLIC RIGHT-OF-WAY REQUIRES A GENERAL RIGHT-OF-WAY PERMIT FROM PIERCE COUNTY.	

ALL WORK IN THE PUBLIC RIGHT-OF-WAY REQUIRES A GENERAL RIGHT-OF-WAY PERMIT FROM PIERCE



CHECK DAMS	
DITCH SLOPE	CHECK DAM SPACING
0.50%	400'
1.0%	200'
2.0%	100'
3.0%	70'
4.0%	50'
5.0% OR GREATER	30'

- ① EXISTING UTILITIES TO REMAIN. CONTRACTOR TO PROTECT AND ADJUST TO FINISH GRADE.
- ② LANDSCAPE WALL TO BE DESIGNED BY HOMEOWNER.

EXISTING POWER, CABLE, TELEPHONE, AND GAS LINES, PEDESTALS, VAULTS, ETC. AROUND THE PERIMETER OF THE SITE SHALL BE PROTECTED DURING CONSTRUCTION.

**Know what's below.  
Call before you dig.**

**Call before you dig.**

© APEX ENGINEERING LLC 2021

SETBACK DISTANCE  
2 FEET  
HEIGHT OF FILL  
20 FEET

FILL DEPTH  
UNDER 5 FEET  
5 - 40 FEET  
OVER 40 FEET

**TESC KEY NOTES:**

① EXISTING UTILITIES TO REMAIN. CONTRACTOR TO PROTECT AND ADJUST TO FINISH GRADE.

② LANDSCAPE WALL TO BE DESIGNED BY HOMEOWNER.

**EXISTING UTILITY NOTES:**

EXISTING POWER, CABLE, TELEPHONE, AND GAS LINES, PEDESTALS, VAULTS, ETC. AROUND THE PERIMETER OF THE SITE SHALL BE PROTECTED DURING CONSTRUCTION.

50°	
30°	

© APEX ENGINEERING LLC 2021

During construction, all releases of oils, hydraulic fluids, fuels, other petroleum products, paints, solvents, and other deleterious materials shall be contained, and stored in a manner that will prevent their discharge to the ground and soils of the State. The cleanup of spills shall take precedence over other work of the site.

**GRADING NOTES:**

GROUND SURFACE FOR FILLS OVER 5' IN HEIGHT SHALL BE PREPARED BY REMOVING VEGETATION, NONCOMPLYING FILL, SOIL, AND OTHER UNSUITABLE MATERIALS, AND SCARPING.

GROUND SURFACE FOR FILLS WHERE EXISTING SLOPES ARE STEEPER THAN 1 VERTICAL BY BENCHING INTO 1 HORIZONTAL.

IN 5 HORIZONTAL TO 1 VERTICAL IS AT LEAST 10' WIDE OR  
RECOMMENDED BY A GEOTECHNICAL ENGINEER.

NO MATERIAL OTHER THAN EARTH MATERIAL SHALL BE  
LIED OR PLACED IN FILLS.

SETBACK FROM PROPERTY LINES.

CUT DEPTH UNDER 5 FEET	SETBACK DISTANCE 2 FEET
5 - 20 FEET	HEIGHT/2
OVER 20 FEET	10 FEET

THE TOE OR CATCH POINT OF FILL SLOPES SHALL BE SET  
BACK FROM THE SITE BOUNDARY LINE IN ACCORDANCE WITH THE